


**CONNECTICUT DEPARTMENT OF
TRANSPORTATION**

**BUREAU OF ENGINEERING AND
CONSTRUCTION**

**OFFICE OF CONSTRUCTION
*DIVISION OF MATERIALS TESTING***



Quality Assurance (QA) Program for Materials
Acceptance and Assurance Testing Policies and Procedures

Prepared by Materials Testing Staff

Chapter 1 – Purpose	1
Chapter 2 – Division of Materials Testing Overview	2
ORGANIZATIONAL CHART	3
Project Support & Portland Cement Concrete (PS) Section	4
District Laboratories’ Operations	4
Physical Testing Lab/Cement	4
Precast Concrete Fabrication.....	5
Hot Mix Asphalt and Final Material Certification (HMA) Section	5
Bituminous Materials Laboratory	5
Final Materials Certification and File Retention.....	5
HMA Density and Verification Lab.....	5
HMA Plant Acceptance	5
Independent Assurance and Field Inspection (IA) Section.....	5
HMA Plant and Core Assurance.....	6
HMA Plant Inspection.....	7
Material Certification and Certified Test Reports.	7
SiteManager	7
Structural Steel Fabrication Plant/Field Operations.....	7
Consultants/Fabrication Records	7
Chapter 3 – Material Code Definitions	8
Paint/Coatings/Markings.....	8
Landscaping Materials	9
Precast Concrete Drainage Materials	10
Pipe.....	11
Steel Reinforcement.....	12
Portland Cement Concrete.....	12
Prestressed/Post-Tensioned/Concrete Members.....	12
Portland Cement/Chemical Anchor.....	13
Joint Materials	13
Brick and Block.....	14
Metal Castings	14
Fences	14
Railings.....	15
Structural Anchors & Bearings.....	16
Structural Steel.....	17
Highway Lighting & Traffic Control.....	17
Hot Mix Asphalt Materials.....	18
Aggregates	20
Chapter 4 – Materials Evaluation and Testing Procedures	22
Materials Evaluation	22
Materials Testing Procedures	22
Sampling Materials for Test	22
Aggregates	23
Precast Concrete Production Facility Inspection.....	23
Reinforced Concrete Pipe	23
Precast Concrete Drainage Items.....	25
PRECAST/PRESTRESSED CONCRETE (STRUCTURAL).....	27
PORTLAND CEMENT CONCRETE (ALL).....	29
Concrete Batch Plants and Delivery Vehicles.....	29

Compressive Strength of Cylindrical Concrete Specimens	29
Mass, Yield, and Air Content (Gravimetric) of PC Concrete	29
Assurance Report (DMT Only): MAT-224, or MAT-225, and MAT-222	29
Admixtures	29
Structural Steel and Welding Shop Inspection	29
HOT MIX ASPHALT (BITUMINOUS CONCRETE/SUPERPAVE)	30
Annual Qualification of Hot Mix Asphalt Plants	30
Sampling HMA Mixtures	30
Binder Content by Ignition Method	30
Correlation Between Production Pull and Binder Content by Ignition Method	30
Mechanical Analysis of Extracted Aggregate	31
Degree of Particle Coating of HMA Mixtures	31
Bulk Specific Gravity of Compacted HMA Mixtures	31
Volumetric Calculations of VMA	31
Preparation of Gyratory Specimens	31
Maximum Specific Gravity of HMA Paving Mixtures	32
Status of New Mixes, Existing Mixes From Previous Year's Production	32
Mix Design / Job Mix Formula(JMF) Submittal and Change Procedure	32
HMA Verification Testing Procedures	33
Resistance of Compacted HMA to Moisture Induced Damage	36
Volumetric and Specific Gravity Using Gyratory Compactor	36
Performance Graded Asphalt Binder (PGAB)	36
DENSITY OF SOIL AND SOIL - AGGREGATES	36
DENSITY OF IN-PLACE ASPHALT PAVEMENT BY THE CORE METHOD	36
<i>Chapter 5 – AMRL Document.....</i>	<i>37</i>
<i>Chapter 6 – Independent Assessment/Verification Program</i>	<i>38</i>
<i>Chapter 7 – Minimum Schedule for Acceptance Testing (Non-NHS)</i>	<i>40</i>
<i>Chapter 8 – Minimum Schedule for Acceptance Testing.....</i>	<i>41</i>
<i>Chapter 9 – Minimum Schedule for Assurance Testing</i>	<i>53</i>
<i>Appendix A – Reporting Forms</i>	<i>A1</i>
<i>Appendix B – Final Materials Certification</i>	<i>B1</i>
<i>Appendix C – Sample Scope of Work for Third-Party Testing Agency.....</i>	<i>C1</i>
<i>Appendix D – Active Material Codes.....</i>	<i>D1</i>
<i>Appendix E – Certification of Portland Cement Program</i>	<i>E1</i>
<i>Appendix F – Connecticut Reference File Specifications</i>	<i>F1</i>
<i>Appendix G – Standard Operating Procedures.</i>	<i>G1</i>
<i>Index.....</i>	<i>H1</i>

Chapter 1 – Purpose

This manual describes the organization, functions, and procedures performed by the Connecticut Department of Transportation’s (Department) Division of Materials Testing (DMT) relating to sampling, testing, and inspection of materials incorporated into Department projects or State funded municipal projects. In addition, the procedures used to verify Contractor test results and the Department’s independent assurance test programs are also described. These functions and procedures comply with the criteria set forth in Federal Regulation 23 CFR 637, CONSTRUCTION INSPECTION AND APPROVAL, which governs quality assurance on all federal-aid highway projects on the National Highway System.

It is the function of the DMT to predetermine in some cases, and determine prior to completion of the work in other cases, if materials used by Contractors and the Department in the construction and maintenance of transportation facilities comply with the specification requirements and plans, and to assist others within the Department with developing and maintaining materials specifications and materials-related project specifications. Occasionally, DMT personnel perform investigational work on new materials and procedures. Testing procedures utilized by DMT personnel are as specified in the current edition of the ConnDOT Standard Specifications; Standard Specifications and Methods of Sampling and Testing by the American Association of State Highway and Transportation Officials (AASHTO); the American Society for Testing and Materials (ASTM); and ConnDOT Reference Files.

The method and frequency of testing of materials used in the construction of Department projects are identified in the “*Minimum Schedule for Acceptance Testing*” and the “*Minimum Schedule for Assurance Testing*,” Chapters 8 and 9 of this manual respectively. The schedules are arranged according to standard contract item nomenclature common to the Department’s Standard Specifications and listing of contract items.

All contract items within the Department’s highway construction management system (SiteManager) have been, and continue to be, reviewed and where appropriate have material(s) that typically require testing associated to them. Appendix D lists the material codes used in SiteManager. During the course of a project, modifications to these associations may be required on a project-by-project basis due to a changed field condition or Contractor selections. As materials are used on the project, project personnel submit a “Request for Test” at the frequency described in the minimum test schedules to the DMT to perform whatever actions are necessary to make a recommendation to the contract administrator as to the acceptability of these materials in relation to the specific contract item. These actions are typically referred to as “acceptance testing” and may include physical testing, visual inspection, and/or review of pertinent documentation for a sample of the total material used.

Actions showing that the samples meet the acceptance criteria stated within the contract specification generally would prompt a recommendation of acceptance from the DMT for that material quantity represented by the sample. Conversely, actions showing that samples do not meet the acceptance criteria stated within the contract specification generally would prompt a recommendation of rejection.

The typical number of test requests processed annually by the DMT are listed below in decreasing order.

Material Name	Samples	% of total
<i>Hot Mix Asphalt (All)</i>	3300	24
<i>Stone (Broken/Crushed) Gravel</i>	2900	21
<i>Precast Concrete (All)</i>	1650	12
<i>Concrete (PCC)</i>	4400	32
<i>Sand</i>	1100	8
<u><i>Reinforcing Steel</i></u>	<u>400</u>	<u>3</u>
<i>Totals</i>	13750	100

The contract administrator, in most cases a District Engineer, is ultimately responsible for the acceptance of the total material quantity used on a project and may accept materials recommended for rejection, or reject materials recommended for acceptance, in accordance with the Department's Specifications.

Assurance testing is performed independently from acceptance testing to assure that personnel are performing the testing procedures in accordance with the applicable sampling and testing specification and that the testing equipment used is calibrated and working properly.

After all construction on a project is completed and all requests for test have been processed, a Final Materials Certificate (FMC) is issued by DMT staff that reconciles the testing for materials that are subject to testing and/or inspection and their installed quantities. Any materials that were subject to testing and were permanently incorporated into the project that were not accepted in accordance with the specifications are listed as exceptions to the project specifications.

Chapter 2 – Division of Materials Testing Overview

The Division of Materials Testing (DMT) consists of three Sections, Project Support and Portland Cement Concrete; Independent Assurance and Field Inspection; and HMA & Final Materials Certification. All are under the jurisdiction of the Division Chief for the Office of Construction (DC) and the Principal Engineer for Materials Testing (PEMT). The DC, as the Department's representative to the AASHTO Subcommittee on Materials (SOM), advises and assists in the preparation and continuous revision of AASHTO specifications used by transportation agencies throughout North America.

The PEMT maintains an association with Materials Testing Engineers of other states through AASHTO correspondence and their annual meeting and maintains a close association with the surrounding states Materials Testing Engineers through the Northeastern States Materials Engineers' Association (NESMEA). The PEMT also maintains a close relationship with professional organizations such as the New England Transportation Technician Certification Program (NETTCP); Northeast Asphalt User /Producers' Group (NEAUPG); and the Northeast Protective Coating Committee (NEPCOAT).

The DC and PEMT are responsible for administering and providing direction for the technical operations such as the personnel policies, affirmative action goals, union contracts, code of ethics, and other pertinent Department technical guidelines/policies that are brought to the attention of, and enforced by, each individual section supervisor in the DMT.


The PEMT is assisted by three Transportation Supervising Engineers (TSEs) who lead the three sections and a complement of 45 employees. The organization of the Division of Materials Testing is graphically represented in the following Organizational Chart. (Figure 1)

It is the responsibility of the TSEs to supervise the day-to-day operations of the three sections in order to assure that materials are recommended for approval or rejection and the specified sampling and testing procedures are followed. Testing results are input to SiteManager for dissemination to the appropriate construction project and District personnel. This serves as a historical record of materials tested for use on a construction project or maintenance activity and their status during the testing process.

The duties of the three TSEs also include the submission of budget, equipment, and overtime requirements; investigation of materials failures; and communication with Contractors and Engineers on materials specifications and specific project-level issues.

The DMT participates in the AASHTO Accreditation Program (AAP). This program provides accreditation for laboratories that meet strict organization, personnel, equipment, and testing proficiency requirements. The program includes the following construction materials pertinent to the Division of Materials Testing: Asphalt Cement, Performance Graded Binder, Emulsified Asphalt, HMA, HMA Aggregate, Portland Cement Concrete, and Portland Cement Concrete Aggregate.

Figure 1.
STAFFING CHART
CONNECTICUT DEPARTMENT OF TRANSPORTATION
BUREAU OF ENGINEERING AND CONSTRUCTION
DIVISION OF MATERIALS TESTING



Division of Materials Testing Overview (cont.)

Project Support & Portland Cement Concrete (PS) Section

The PS Section is primarily involved with the operation of the satellite laboratories in each of the outlying Districts and the testing and inspection of Portland cement concrete and precast and prestressed concrete members. In conjunction with those materials, this section also performs the physical testing of steel reinforcing material and other steel-related items. A large part of the service provided by this section is the support of the active construction projects and delivering some material samples to the Central Laboratory. Visits to the project sites are commonly done to retrieve all types of samples, assist project personnel in the submittal of all samples, and to assist in the testing of materials on site, or the assurance testing of PC concrete.

The PS Section of the DMT is divided into three functional units: District Laboratories' Operations, Physical Testing Lab/Cement, and Precast Concrete Fabrication Operations.

District Laboratories' Operations

This unit oversees the operations of the three satellite District Laboratories located in each of the outlying three Districts and the Central Laboratory's District 1 Lab in Rocky Hill. These laboratories are located in each District Office within the State to expedite the sampling and testing of common materials, such as aggregates. The unit is also responsible for maintaining an active independent assurance testing program for aggregates and concrete for the satellite District Laboratories consistent with that of the Central Laboratory.

The satellite District Laboratories are primarily assigned materials sampling and testing for projects within the District in which they are located.

The principal duties of the satellite District Laboratories are as follows:

- Perform acceptance testing of fine and coarse aggregates including but not limited to gradation analysis, specific gravity, density, and unit weight.
- Determine laboratory maximum density of soils and processed aggregates.
- Inspect metal pipe and metal culvert ends at project sites.
- Inspect and sample transportation materials at quarries, gravel banks, Portland cement concrete plants, and other sources of supply for Department projects.
- Perform acceptance sampling and testing of fine and coarse aggregates.
- Observe assurance sampling and testing for aggregates and Portland cement concrete.
- Obtain samples and transport them to the Central Laboratory as needed.
- Inspect any new sources of materials.
- Assist Division of Purchasing regarding sampling and testing of road salts.

The District 1 Lab located within the Central Laboratory facility performs the same operations as the satellite District Labs with the additional task of checking the satellite District Labs' test results for aggregates using split samples and performing additional tests on fine and coarse aggregates such as soundness, resistance to degradation by abrasion and impact, specific gravity, absorption, unit weights, angularity, and elongation.

Physical Testing Lab/Cement

The responsibilities of the physical testing unit include the testing for compressive strengths of concrete cylinders, testing of drilled cores, properties of brick and block, the tensile strengths of several ferrous and nonferrous structural steel products, the Rockwell or Brinell hardness of structural steel products, the coating thickness of zinc and epoxy coated products, and evaluating weld coupons for welder certification testing. This subsection may also perform testing on new products and materials being evaluated by the Department.

Precast Concrete Fabrication

This unit acts as a liaison with precast concrete producers and project personnel to schedule on-site inspections and resolve technical and administrative issues. Inspectors in this unit are responsible for the quality assurance of prefabricated concrete products. These products include reinforced concrete pipe, precast and prestressed concrete items. The overall duties of the individual inspectors are to monitor the fabricators compliance to their own Quality Control (QC) Plan on file with the Department. At varying frequencies, the inspectors also sample all component materials for compliance with the Department's specifications; inspect the casting beds and forms to ensure dimensional conformance to the approved drawings; observe the concrete batching operation to ascertain conformance to an approved mix design; witness plastic concrete testing; observe the concrete placement and consolidation operation; witness the compression testing of specimens; inspect the finished product for conformance to dimensional tolerances and finished appearance; and maintain complete and accurate Department records for all phases of the work. Consultants under contract to the Department are used as needed to supplement DMT personnel to meet this responsibility.

Hot Mix Asphalt and Final Material Certification (HMA) Section

The HMA Section is divided into five functional units: Bituminous Materials Lab, Final Materials Certification and File Retention, HMA Density and Verification Lab, and HMA Plant Acceptance.

Bituminous Materials Laboratory

This unit is responsible for testing of various performance graded (PG) binders and other petroleum based products. HMA paving and associated products physically tested by this unit are PG Binders, emulsified asphalts and bituminous component materials used in Ultra-thin HMA. In addition, this unit reviews binder and emulsified asphalt suppliers QC Plans and other required documentation to maintain the supplier certification by AASHTO R 26 and AASHTO R 77.

Final Materials Certification and File Retention

This unit is responsible for tracking material testing data on a project to ensure that all materials permanently incorporated into the project are tested/certified in sufficient quantity and that the results are acceptable or alternative acceptance criteria are met. Upon request from the District, a final materials certificate is provided for all completed projects stating the disposition of all materials incorporated into the project. If applicable, exceptions to the project specifications are listed individually on the certificate. Examples of this certification are in Appendix B.

HMA Density and Verification Lab

This unit is responsible for verifying that mix designs are in compliance with project specifications and for validating Contractor data used for acceptance. Comparison testing during the paving season is performed on test specimens that are fabricated by both Contractor or DMT staff. Test records are maintained for each mixture type produced by each vendor providing materials to the Department. The HMA Density and Verification unit also performs extraction and aggregate tests on samples; processes cores for payment adjustment; and investigates new mix designs, additives, and aggregate sources.

HMA Plant Acceptance

Staff in this unit are responsible for monitoring HMA producer QC testing at the plant used for acceptance on a project-by-project basis and processing the results for payment adjustment purposes. HMA mix designs are also reviewed by staff in this unit for compliance to the project specifications and monitors changes in materials sources and the resulting mix design changes during the paving season. During the winter months, staff review producer generated QC Plans to ensure that the current specification requirements are recognized and any revisions are acceptable to the Department.

Independent Assurance and Field Inspection (IA) Section

The IA Section is divided into six units: HMA Plant Assurance, HMA Plant Inspection, Material Certification and Certified Test Reports, SiteManager, Structural Steel Fabrication Plant/Field Operations, and Consultants/Fabrication Records.

The IA Section of the DMT is primarily responsible to assure that the testing being performed by Department and/or Contractor personnel for acceptance purposes is performed by qualified personnel in accordance with standard test procedures and that the equipment used is adequate and calibrated. This typically includes a review of personnel qualifications, calibration records, witnessing test procedures first hand, and performing verification testing. The schedule for IA inspection is as follows:

Test	Acceptance Samples	Assurance Samples
T-168 Sampling Bituminous Mixtures	10	1 (Min 1 per Month per Technician during Construction Season)
R-47 Reducing Samples of HMA		
T-308 Asphalt Content Ignition Oven		
T-30 Sieve Analysis		
T-312 Preparation of Gyrotory Sample		
T-166 Bulk Specific Gravity		
T-209 Theoretical Maximum Specific Gravity	40	1
T-331 Standard Method of Test for Bulk Specific Gravity (Gmb) and Density of Compacted Hot Mix Asphalt (HMA) Using Automatic Vacuum Sealing Method		

This section is also responsible for the day-to-day administration of a consultant contract for the testing of structural steel at various out-of-state fabricators, and other seasonal inspection needs within the State; the review and processing of the consultant inspection reports; the update and maintenance of the materials module of SiteManager and interacting with construction field inspectors to revise and maintain materials testing results for individual projects; and addressing building-related issues for all Department personnel within the facility.

HMA Plant and Core Assurance

This unit follows an independent process from that for acceptance testing to ensure that material sampling and testing at the HMA plants and the DMT HMA Density and Verification Lab is being done correctly. The process evaluates personnel sampling and testing material for compliance with established standard test procedures and evaluates the equipment used for acceptance testing for adequacy and calibration.

The evaluation process generally involves witnessing personnel during the testing procedure and documenting what is observed on the “Report of Witness” (MAT-600) form. Test equipment is evaluated through calibration checks, testing split samples, or any combination of these methods. Split sample results that agree with acceptance tests within the limits of Table 2, Column C, will not require any further action. Results that fall outside the limits will require an investigation to determine the cause of the discrepancy and have it corrected.

Any sampling or testing of material for IA purposes is done on a separate schedule and frequency using separate equipment. Personnel assigned to this unit will not test material for acceptance nor will the results of any assurance testing be used for acceptance purposes.

HMA Plant Inspection

This unit is responsible for quality assurance of all HMA material used on construction and maintenance projects. This is accomplished through the inspection of HMA material at the plant. Approximately thirty source locations that provide HMA for State projects are inspected by personnel in the HMA Plant Inspection unit. All producers are required to have a field laboratory to provide a DMT inspector immediate access to test results to assure material meets the specification at the plant. In addition to the testing of HMA, the plant inspectors sample the binder; observe the production process; inspect fine and coarse aggregates; verify batch weights, mix temperatures, and appearance; and check plant machinery and hauling vehicles for specification compliance. Plant inspectors maintain test records at each field lab and complete all applicable DMT forms. The supervisor of this section is responsible for daily field supervision and observation of field technicians sampling and testing techniques; performing plant and field lab inspections; notifying producers of material problems; performing verification and assurance sampling and testing; training and reviewing procedures and specifications with the field personnel; serving as a liaison between material producers and project personnel to remedy material issues; and working closely with the HMA Plant Acceptance unit to carry out QA and investigative tasks.

Material Certification and Certified Test Reports.

This unit is responsible for the review of material certificates and certified test reports to determine if the documentation provides the information necessary to recommend acceptance of the material. Following the issuance of the Final Materials Certificate for a particular project, personnel in this unit also compile and review the project records in accordance with the Department's record retention policies so that they can be transferred to the Department's record storage facility in Newington.

SiteManager

Staff are responsible for updating and maintaining the materials module of the SiteManager Reporting System and interacting with construction field inspectors and DMT personnel to revise and maintain materials testing results for individual projects.

Structural Steel Fabrication Plant/Field Operations

This unit has the responsibility to assure that all materials and physical aspects of structural steel fabrication are in compliance with the applicable specifications. Duties of this unit include the review and approval of shop and field welding procedures; assistance to other Department personnel regarding welding techniques and procedures; on-site audits and review of field welding and in-state fabrication; testing and certification of Department approved welders; and any related duties as they apply to structural steel fabrication.

Consultants/Fabrication Records

DMT personnel monitor consultant contracts for structural steel fabrication inspection on a day-to-day basis. Personnel in this unit are also responsible for the review and processing of steel fabrication inspection reports and making technical recommendations to the TSE of the section.

Chapter 3 – Material Code Definitions

Paint/Coatings/Markings

00001 ENAMEL PAINT (BLACK/BURNT ORANGE)

Scope: All enamel paint

Sampling and Procedure: None

Specification / Report Form: Black, Reference File No. 25, Burnt Orange Reference File No. 104 / NA

00031 PAINT – PRIME COAT FOR STRUCTURAL STEEL

00032 (Interim), 00033 (Top), 00039 (Field)

STRUCTURAL STEEL COATINGS

Sampling: Samples of coatings are generally not required unless specified in the Special Provisions.

Procedure: Fabricators of structural steel are responsible for making themselves aware of the entire coating specification for each individual project prior to starting the work. The DMT must be notified in advance of any coating work on structural steel for Department use. Field painting and touch-up work must conform to Standard Specifications, Article 6.03.03-38. Project personnel are responsible for submitting a MAT-100 when the material is delivered to the project site.

Specification: As specified in a Special Provision or Standard Specifications, Section 6.03 and M.07.

00054 PAVEMENT MARKING PAINT, 15-MINUTE DRY, WHITE AND YELLOW

Scope: White and yellow pavement marking paint

Sampling: Two quart samples will be taken by the manufacturer for each Lot Number in accordance with ASTM D3925, and forwarded to the DMT by the manufacturer accompanied by a certified test report.

Procedure: As listed in Specification(s)

Specification/Report Form(s): Federal Specification Paint TT-P-1952, Reference File No. 207D and M.07 / MAT-236, MAT-237, or MAT-240.

00060 TRAFFIC PAINT, 3 MINUTE DRY, WHITE AND YELLOW

Scope: White and yellow low-heated, fast-drying pavement marking paint

Sampling: Two quart samples will be taken by the manufacturer for each Lot Number in accordance with ASTM D3925, and forwarded to the DMT by the manufacturer accompanied by a certified test report.

Procedure: Same as 00054

Specification/Report Form: Federal Specification Paint TT-P-1952, Reference File No. 200I and Section M.07 / MAT-235, MAT-238, or MAT-239.

00064 PAINT EPOXY

00091 PAINT EPOXY PAVEMENT MARKINGS

Scope: White and yellow epoxy resin pavement marking paint

Sampling: Two quart samples will be taken by the manufacturer for each Lot Number in accordance with ASTM D3925, and forwarded to the DMT by the manufacturer accompanied by a certified test report. Once per calendar year, one quart sample of the hardener forwarded to the DMT by the manufacturer accompanied by a certified test report.

00097 & 03057 Sand Blasting

00097 SAND BLAST DEBRIS (Toxicity Test)

03057 SAND BLAST ABRASIVE

Scope: Sandblast debris from bridge painting. Sent to third-party laboratory for testing.

Sampling and Procedure: EPA Method 1311

Specification/Report Form: Connecticut DEEP Drinking Water Remediation Standards / NA

00206 Black Pavement Markings
00206 PREFORMED BLACK MARKING TAPE

Scope: Rolled tape for pavement markings.

Sampling and Procedure: None

Specification/Report Form: M.07 / NA

00297 to 00303 Snow & Ice Control

00297 CALCIUM CHLORIDE (LIQUID) 00302 CALCIUM CHLORIDE

Scope: Highway Maintenance use only.

Sampling and Procedure: None

Specification/Report Form: AASHTO M 144 / NA

00298 SODIUM CHLORIDE (INERTIAL BARRIERS)

00303 SODIUM CHLORIDE (ROCK SALT)

Scope: All sodium chloride used for snow and ice control on highways; or for use in inertial barriers.

Sampling: For snow and ice control AASHTO T 2, none for inertial barriers.

Procedure: Sieve analysis, AASHTO T 27; chemical, ASTM E 534; moisture content, AASHTO T 265.

Specification/Report Form: For snow and ice control, ConnDOT Reference File No. 139 / MAT-208. For inertial barriers, Standard Specifications, Section 18.07 (Materials Certificate) / NA.

00306 GLASS SPHERES (GLASS BEADS)

NOTE: All other material codes for glass beads are inactive.

Scope: Glass spheres (glass beads) for application on pavement markings.

Sampling: One sample will be provided for each Lot Number and forwarded to the DMT by the manufacturer.

Procedure: AASHTO M 247

Specification/Report Form: AASHTO M 247, Type 1 and 4 / MAT-228 or MAT-229

00327 WATER

Scope: For production of PCC and any other material or process.

Sampling and Procedure: None for potable sources. For other sources, ASTM C 1602.

Specification/Report Form: Standard Specifications, Article M.03.01-4 / MAT-230

Landscaping Materials

00496 FERTILIZER

Scope: Fertilizer for use in turf establishment.

Sampling: None.

Procedure: Standard Specifications, M.13.03

Specification/Report Form: Standard Specifications, Article M.13.03 / NA

00497 SEED

Scope: Mixtures to establish turf or grass.

Sampling: None

Procedure: Standard Specifications, Article M.13.04

Specification/Report Form: Standard Specifications, Article M.13.04 / NA

00510 PEAT

Scope: Commercially package peat from sedge, sphagnum or reed sources used on planting soil.

Sampling: None - visual inspection by project personnel.

Specification/report Form: Standard Specification, Article M.13.07 / NA

00511 LIMESTONE

Scope: Agricultural ground dolomitic limestone used to increase pH on topsoils.

Sampling: None

Specification/Report Form: Standard Specification, Article M.13.02/ NA

00515 WOOD CHIP MULCH

00534 WOOD MULCH

Scope: To establish quick germinating vegetation and/or prevent erosion.

Sampling: None - visual inspection by project personnel.

Specification/Report Form: Standard Specifications, Article M.13.05 / NA

00514 MULCH (HAY)

04776 BALED HAY

Scope: Used for turf establishment or sedimentation control.

Sampling: None - visual inspection by project personnel.

Specification/Report Form: Standard Specifications, Article M.13.05 (Mulch) or Section 2.18 (Sedimentation Control) / NA.

00518 SOD

Scope: Sod used for the immediate establishment of a grass surface.

Sampling: None - visual inspection by project personnel.

Procedure: Project personnel contact Landscape Design Unit

Specification/Report Form: Standard Specifications, Article M.13.08/ NA

00536 PLANT MATERIALS

07547 TREE

Scope: All living plant materials are to be inspected by staff from the Department's Landscape Design Unit. A MAT-100 is NOT required. Initial contact and follow up is the responsibility of project staff.

Sampling: None - visual inspection by Landscape Design personnel.

Procedure: Project staff contact Landscape Design Unit

Specification/Report Form: Standard Specifications, Article M.13.07/ NA

00542 TOP SOIL

Scope: Cut and fill material taken from the project site and used on the project site.

Sampling: None - visual inspection by project personnel.

Specification/Report Form: Standard Specifications, Article M.13.01 / NA

00542X TOP SOIL

00542P PLANTING SOIL

Scope: Soil brought from off the project site for use under items 0949XXX furnishing and planting trees.

Sampling: None. Materials Certificate and Certified Test Report submitted with MAT-100.

Specification/Report Form: Standard Specifications, Article M.13.01 / NA

Precast Concrete Drainage Materials

00699, 1700, 1708 Reinforced Concrete Pipe

00699 REINFORCED CONCRETE PIPE

01700 PLAIN AND PERFORATED CONCRETE DRAIN PIPE

01708 PIPE – FOR UNDERDRAIN or OUTLET

Scope: Plain and perforated concrete drain pipe.

Sampling: Each size and type of pipe is subject to 3-edge bearing and absorption tests each spring.

Procedure: AASHTO M 170 and AASHTO T 280.

Specification/Report Form: Standard Specifications, Article M.08.01-7 / MAT-314

Precast Units For Drainage Structures

00823 to 01650 Precast Concrete Drainage & Misc.

Refer to Appendix D for material codes

Scope: Precast concrete units to be used in the construction of drainage structures. Precast units shall include, but not be limited to, products such as box culverts, catch basins, drop inlet and manhole tops, riser sections, sumps and other appurtenances. The recommendation for acceptance of precast units is based on the manufacturer's certification that the units conform to the project specifications. Ultimate acceptance of the material should be based on receipt of the manufacturer's certification and a visual inspection by project personnel following delivery.

Pipe

01940 to 2650 PIPE (Metal, Iron, Poly, PVC)

01940 PIPE – CCM, Fittings & Accessories

01949 PIPE – COATED CORRUGATED METAL

Scope: The field inspection of metal and aluminum pipe and structural plate pipe and pipe arches.

Sampling: Depending on the size of the shipment, one or two representative pieces of metal pipe, bands, and accessories are selected by DMT and inspection personnel for testing.

Procedure: Procedures and measurements are shown in the "Field Inspection of Metal and Aluminum Pipe" procedure in Appendix G. Materials Certificates and Certified Test Reports are also required.

Report Form: MAT-200, MAT-201, MAT-202, MAT-203, or MAT-204.

02501 DUCTILE IRON PIPE

02510 DUCTILE IRON PIPE FITTINGS & ACCESSORIES

02724 PIPE- STEEL & FITTINGS & ACCESSORIES

Scope: This section covers welded and seamless steel pipe.

Sampling: ASTM A 53 and as supplemented in Standard Specifications, M.06.02.

Procedure: ASTM A 53 and as supplemented in Standard Specifications, M.06.02.

Specification/Report Form: Standard Specifications, Article M.06.02. / MAT-100

02600 POLYETHYLENE PIPE

02672 POLYETHYLENE PIPE FITTINGS AND ACCESSORIES

Scope: Plastic and polyethylene corrugated pipe or tubing for use in drainage.

Sampling and Procedure: None - visual inspection by project personnel.

Specification/Report Form: Standard Specifications, Article M.08.01. / MAT-100.

02649 POLYVINYL CHLORIDE PLASTIC PIPE

Scope: This section covers polyvinyl chloride plastic pipe, elbows, and couplings for highway drainage.

Sampling and Procedure: None - visual inspection by project personnel.

Specification/Report Form: Standard Specifications, 5.13 and Article M.08.01 / NA

04178 PIPE JOINT COMPOUND

Scope: Cold applied bituminous sealer for reinforced concrete pipe.

Sampling: None

Procedure: None

Specification/Report Form: Standard Specifications, M.08.01 / NA

Steel Reinforcement

02998 DEFORMED STEEL BARS, EPOXY COATED

03100 DEFORMED STEEL, REINFORCING

Scope: Deformed steel bars (plain or epoxy coated) for concrete reinforcement.

Sampling: A sample of each size bar will be submitted for each shipment as follows: All sizes-one sample per size from each manufacturer for each 200 tons. Samples submitted for test will be cut from the shipment on the project site and will be not less than 5 ft. (1.5 m) in length.

Procedure: AASHTO T 244

Specification/Report Form: Bar reinforcement will be tested according to procedures prescribed in AASHTO M 31. Epoxy coated reinforcement shall be tested as prescribed in AASHTO M 284. Standard Specifications, Article M.06.01 / MAT-305

07999 WIRE AND WELDED WIRE STEEL WIRE FABRIC (MESH)

Scope: This section covers wire and welded steel wire fabric for use as concrete reinforcement.

Sampling: A 1 yd² (0.9 m²) sample of each type will be submitted for test per 8,000 yd² (7,000 m²) of fabric used.

Procedure: AASHTO T 244

Specification:

- Cold-drawn steel wire: AASHTO M 32
- Welded steel wire fabric: AASHTO M 55
- Deformed steel wire: AASHTO M 225
- Welded Deformed Steel Wire Fabric: AASHTO M 221

Report Form: MAT-306 or 328

03145 DEFORMED BAR MAT-REINFORCEMENT

Scope: Deformed bar mat reinforcement for use in the construction of concrete pavement.

Sampling: 1 yd² (m²) of each type will be submitted for each 1 mile (1.6 km) of pavement.

Procedure: AASHTO T 244

Specification/Report Form: Standard Specifications, Article M.06.01/ MAT-305

Portland Cement Concrete

03014-X Concrete Class - X

03014-SPXK Concrete Spec. Prov. (X000psi/Mpa)

03014-other

Scope: Fresh Portland Cement Concrete Testing

Sampling: Project personnel are responsible for sampling the concrete at the point of placement.

Procedure: Sampling - AASHTO T 141, Slump - AASHTO T 119, Temperature - AASHTO T 309, Air Content - AASHTO T 152 or AASHTO T 196, Making and Curing Concrete Test Specimens in the Field - AASHTO T 23. Project personnel are responsible for filling the cylinder molds, determining air content, temperature, and slump. Cylinders must be immediately placed where they can remain undisturbed for at least 24 hours.

Assurance Report (DMT Only): MAT-224, or MAT-225, and MAT-222

Acceptance Report (Project Personnel): MAT-308

03040 NON-SHRINK, NON-STAINING GROUT

Scope: Non-shrink, nonstaining grout.

Sampling: Project personnel are responsible for reviewing the bags containing the material for markings indicating compliance with the specifications.

Procedure: Visual inspection of bag.

Specification/Report Form: Standard Specifications, Article M.03.01 / NA

Prestressed/Post-Tensioned/Concrete Members

08044 RETAINING WALL – PRECAST CONCRETE

Scope: Precast, prestressed, and post-tensioned concrete members for use in structures.

Procedure: Precast, prestressed, and post-tensioned concrete members are inspected at the fabricating plant during fabrication and immediately prior to shipment by a representative of the DMT to ensure conformance with the requirements of the applicable specifications. Representative samples of component materials used in the manufacture of these concrete members may be sampled and tested to determine compliance with Standard Specifications. Details of this inspection are provided in Chapter 4.

FABRICATION INSPECTION OF PRECAST CONCRETE MEMBERS

Scope: Due to the critical function of precast, prestressed, and post-tensioned concrete members as load-bearing units of bridges and structures, the DMT assigns an inspector to the manufacturing plant to inspect, in detail, all phases of manufacture. Details of this inspection are provided in Chapter 4.

03148 PRESTRESSING STEEL

Scope: Uncoated high tensile strength, seven-wire, steel strand.

Sampling: One 7 ft. (2.2 m) length and one 1 ft. (305 mm) length of strand from each reel or coil. Up to five reel packs or coils identified with the same heat number can be represented with a single sample.

Procedure: AASHTO T 244

Specification/Report Form: Standard Specifications, Article M.14.02/ MAT-323

Portland Cement/Chemical Anchor

03060 PORTLAND CEMENT TYPE I

03061 PORTLAND CEMENT TYPE II

03066 PORTLAND CEMENT TYPE I/II

Scope: Portland cement used in the production of concrete for Department projects.

Sampling/Procedure: All Portland cement producers are required to submit quarterly test reports to the DMT in accordance with the requirements of Appendix E, "Criteria for Acceptance of Portland Cement by Certification."

Specification/Report Form: Standard Specifications, Article M.03.01 / None

03105 CHEMICAL ANCHOR

Sampling and Procedure: No sample required. Accepted based on Department's Qualified Products List.

Specification: Standard Specifications, Article M.03.07

Joint Materials

03094 JOINT SEALANTS

Scope: This section covers joint sealants for use in PC concrete structures (excluding pavements).

Sampling: None

Procedure: DMT personnel are responsible for reviewing the Materials Certificate and Certified Test Report.

Specification/Report Form: Standard Specifications, Article M.03.01 / MAT-100

03158 PREFORMED EXPANSION JOINT FILLER

Scope: This section covers corrosion-resistant load transfer devices, preformed expansion joint fillers, and wood joint filler.

Sampling and Procedure: None. Project staff reviews the Materials Certificate for compliance with contract specifications.

Specification/Report Form: Standard Specifications, Article M.03.01/ NA.

03444 CLOSED CELL ELASTOMER

Scope: Elastomeric material and lubricant adhesives for use in transverse joints in concrete structures.

Sampling and Procedure: None. Project staff reviews the Materials Certificate for compliance with contract specifications.

Specification/Report Form: Standard Specifications, Article M.17.02 / NA

04177 JOINT SEALER

Scope: Joint sealants of the hot poured type for use in all PC concrete and HMA pavements.

Sampling: None

Procedure: DMT personnel are responsible for reviewing the Materials Certificate and Certified Test Report

Specification/Report Form: Standard Specifications, Article M.04.01/ MAT-100

Brick and Block

03200 & 03201 Brick & Block

Project Staff must submit a Request for Test (MAT-100) indicating manufacturer. A copy of a delivery ticket or receipt from the manufacturer must be attached to the MAT-100. Should the manufacturer not be known DMT personnel may request samples from the project. Project personnel should contact DMT immediately should the manufacturer be unfamiliar to prevent substandard material from being used.

03200 MASONRY BRICK AND BLOCK (Solid)

Scope: Precast, rectangular blocks made from PC concrete.

Procedure: ASTM C 140 and Standard Specifications, Article M.12.12.

Specification/Report Form: Standard Specifications, Article M.12.12 / MAT-313

03201 BRICK (Clay) - RED

Scope: Brick (made from clay or shale and burned)

Procedure: AASHTO T 32

Specification/Report Form: Standard Specifications, Article M.08.02/ MAT-312

Metal Castings

03209 MANHOLE COVERS & FRAMES

03253 METAL CASTINGS

Scope: This section covers castings for general application in highway and bridge construction.

Sampling: None. DMT personnel will review Materials Certificate.

Specification/Report Form: Standard Specifications, Article M.06.02 / MAT-100

ALUMINUM CASTING, TUBING AND FITTINGS

Scope: This section covers aluminum castings, tubing and fittings for ornamental posts, traffic rail posts, bases, post connection splice bars, end caps, etc.

Specification/Report Form: Standard Specifications, Article M.06.02 / MAT-100

Fences

03300 FENCE CHAIN LINK, FABRIC

Including most material codes up to and including

03327 FENCE, PROTECTIVE

Scope: Aluminum-coated or polyvinyl chloride-coated steel chain-link fabric, aluminum alloy fabric, galvanized metal or polyvinyl chloride-coated material or aluminum alloy posts, top and brace rails, and fittings to be used in the construction of chain-link fence.

FABRIC

Sampling: One sample of chain-link fabric at least 3 feet (1 meter) wide and the full height of the fence will be submitted to the DMT for each shipment of 100 rolls or fraction thereof.

Procedure: AASHTO T 244 and the following as applicable:

1. Aluminum-Coated Steel Fabric: Standard Method of Test for Weight [Mass] of coating on aluminum-coated iron or steel articles, AASHTO T 213.
2. Polyvinyl Chloride-Coated Steel Fabric: Standard Specification for Poly (Vinyl-Chloride) (PVC) – Coated Steel Chain Link Fence, ASTM F 668.
3. Aluminum Alloy Fabric: Standard Specification for Aluminum and Aluminum-Alloy Bar, Rod, and Wire, ASTM B 211.

Specification/Report Form: Standard Specifications, Article M.10.01 Fabric / MAT-303

METAL POSTS, RAILS, AND GATE

Sampling:

Gate: Submit one (1) Request for Test with a Materials Certificate for each shipment.

Metal Posts and Rails: Submit one (1) Request for Test with a Materials Certificate for each size and type.

Procedure: DMT personnel will review Materials Certificate

Specification/Report Form: Standard Specifications, Article M.10.05 / MAT--100

FITTINGS

Sampling: Submit one (1) representative sample for each size and type.

Procedure: Average thickness of coating on hot-dipped galvanized fittings shall be determined with the use of a magnetic thickness gage, ASTM Practice E 376.

Specification/Report Form: Standard Specifications, Article M.10.05 Fittings. / MAT-325.

TENSION WIRE

Sampling: Submit one (1) representative sample for each type of tension wire.

Procedure: AASHTO T 244 and AASHTO T 213

Specification/Report Form: Standard Specifications, Article M.10.05 / MAT-326

WIRE FENCE

Scope: Wire fence and support posts.

Sampling: All fence components will be inspected in the field by project personnel to determine conformance to specifications. Project personnel are responsible for submitting a Request for Test, with a Materials Certificate. For treated wood posts, a certificate of treatment is also required.

Procedure: Laboratory personnel are responsible for reviewing the Request for Test and the Materials Certificate to determine conformance to applicable specifications.

Specification/Report Form: Standard Specifications, Article M.10.04 / MAT-100

03985 GEOTEXTILES

Scope: For use in highway drainage, erosion control, or sedimentation control.

Sampling and Procedure: No Sample required. Accepted based on visual inspection and the Department's Qualified Products List.

Report Form: None

Railings

03405 to 03429 Metal Beam & Bridge Rail

Refer to Appendix D for material codes

Scope: Metal beam elements attached to steel posts by various types of hardware and ending in appropriate terminal treatment for use in various highway guardrail installations.

Sampling: Project personnel will submit Request for Test (MAT-100) indicating the following Brand Registration, which shall be marked on each rail element, rub rail, or terminal section:

1. Name or brand of manufacture.

2. Identification symbols, or code for heat number or coating lot.
3. Class (A or B).
4. Type (1 or 2).

Procedure: DMT personnel will review the submittal for conformance to project specifications.

Specification/Report Form: Standard Specifications, Article M.10.02 / MAT-329

03419 to 03439 Cable Guide Rail & Related

03419 CABLE GUIDE RAIL

Scope: Wire rope and fittings for use in wire rope railing supported by wood or steel posts.

Sampling: Samples are not required. Submit a MAT-100 with a Materials Certificate.

Procedure: DMT personnel will review the submittal for conformance to project specifications.

Specification/Report Form: Standard Specifications, Article M.10.01 / MAT-100

Structural Anchors & Bearings

03504 ANCHOR BOLTS

Scope: This section covers anchor bolts, nuts and washers for structural steel construction.

Sampling: One (1) bolt for each size, heat #, and shipment is required for each project. Each sample must be submitted with a Certified Test Report and Materials Certificate.

Procedure: AASHTO T 244

Specification/Report Form: Standard Specifications, Articles M.06.02 and M.15.02, / MAT-300 or 301.

03505 to 03531 Bearing Pads

03505-L BEARING PADS (Elastomeric Laminated)

03505-P BEARING PADS (Elastomeric Plain)

Scope: Laminated and non-laminated bearing pads and adhesive for use in bridge structures.

Sampling: Submitting a MAT-100 with a Certified Test Report. In addition, a copy of the approved shop drawings must be provided. One test pad must be provided for every fifty (50) pads, or portion thereof, required on a structure. If there are multiple types/sizes of pads on a structure, the test pad shall be representative of the most common type/size.

Procedure: Review the Certified Test Report and test material as required to determine conformance to the project specifications.

Specification/Report Form: Standard Specifications, Article M.17.01 / MAT-310

03531 PREFABRICATED BEARING PADS

Scope: Prefabricated pads for bearing areas.

Sampling: None

Procedure: DMT personnel are responsible for reviewing the Materials Certificate.

Specification/Report Form: Standard Specifications, Article M.12.01. / MAT-100

03540 BEARINGS, POT OR SPHERICAL

Scope: This section covers bronze or copper alloy bridge bearings or expansion plates.

Sampling: None

Procedure: DMT personnel are responsible for reviewing the Materials Certificate.

Specification/Report Form: Standard Specifications, Article M.06.02 / MAT-100

Structural Steel

03541 WELDING ELECTRODES

Sampling: As required during shop or field visits

Specification/Report Form: Standard Specifications, Article M.06.04 / NA

03549 PILES, STEEL

Sampling: Field personnel should contact the DMT for sampling requirements.

Procedure: AASHTO T 244.

Specification/Report Form: Standard Specifications, Article M.09.02 / MAT-327.

07762 SHEET PILING, STEEL

Scope: Sheet piling constructed wholly or substantially of steel. No sample required.

Procedure: Laboratory personnel are responsible for reviewing the Request for Test and the Materials Certificate to determine conformance to applicable specifications.

Specification/Report Form: Standard Specifications, Article M.09.01 / MAT-100.

03571 STRUCTURAL STEEL

Scope: This section covers all structural steel for use in riveted, bolted, or welded construction.

Sampling: Test samples for the grade of structural steel may be specified on the plans or in the project specifications. Samples are not common. Standard Specifications, Article M.06.02 (Charpy V-notch)

Procedure: Submit a MAT-100 when the material is delivered to the project site.

Specification/Report Form: Standard Specifications, Section 6.03 and Article M.06.02./MAT-305 or 100.

03707 HIGH STRENGTH BOLTS

08022 BOLT (HIGH STRENGTH), NUT & WASHER

Scope: High strength bolts, nuts, and washers for use in structural steel construction.

Sampling: Request for Test (one per size) with sample, Certified Test Report, and Materials Certificate.

Procedure: "Standard Method of Test for Mechanical Testing of Steel Products," AASHTO T 244. Certified Test Report and Materials Certificate must show conformance to applicable specifications.

Specification/Report Form: Standard Specifications, Article M.06.02 /MAT-302

Highway Lighting & Traffic Control

03500 to 03799 Highway & Bridge Lighting

Refer to Appendix D for material codes

Scope: Materials used in highway illumination. Typically, the Contractor must submit catalog cuts to the Designer for approval. Refer to the "Materials Approved by Catalog Cut" section in Chapter 2.

Sampling: None

Specification/Report Form: Standard Specifications, Section M.15/ NA

03700 to 03984 Traffic Control Materials (Electric)

Refer to Appendix D for material codes

07687 COMMUNICATION CABLE & HARDWARE

08043 TRAFFIC CONTROL EQUIPMENT

Scope: Materials used in traffic control signal installations. The Contractor may use materials provided they meet the contract specifications and are approved by the Engineer/Designer.

Sampling: The contract documents will generally designate the type of material control (i.e., Certified Test Report or Materials Certificate) required. In the absence of specific requirements, the provisions of Standard Specifications, Article 1.06 apply.

Procedure: None.

Specification/Report Form: Standard Specifications, Section M.16/ NA

03933 to 03974 Signs and Traffic Control Devices

03933 DELINEATOR

03934 REFLECTIVE SHEETING

03943 OBJECT MARKERS

Scope: Aluminum sign blanks, silk-screen ink, reflective sheeting, and object markers.

Sampling: None.

Procedure: AASHTO T 244, AASHTO T 65, and ASTM E 376

Specification/Report Form: Standard Specifications, Article M.18.14 / NA.

03936 SIGN PANELS EXTRUDED ALUMINUM

03938 SIGN FACE - SHEET ALUMINUM

03939 SIGNS

03945 CONSTRUCTION SIGNS

03952 SIGN POSTS

Scope: All signs on Department projects.

Sampling: The contract documents for the project should designate the type of material documentation (i.e., Certified Test Report or Materials Certificate) required for materials used in signing installations. In the absence of specific instructions for individual projects, the method of material control shall be provisions of Standard Specifications, Article 1.06.

Procedure: Submit Request for Test with appropriate documentation.

Specification/Report Form: Standard Specifications, Section M.18 / MAT-100

03948 TRAFFIC CONES

03956 TRAFFIC DRUMS

03970 IMPACT ATTENUATOR

03974 CONSTRUCTION BARRICADE

Hot Mix Asphalt Materials

04000 to 04100 Hot Mix Asphalt & Bituminous Concrete

04003 Curb Mix

04052,3,4 HMA Level 1,2,3 (9.5 mm / 0.375 in.)

04056,7,8 HMA Level 1,2,3 (12.5 mm / 0.5 in.)

04064,5,6 HMA Level 1,2,3 (25mm /1.0 in.)

04076,7,8 HMA Level 1,2,3 (6.25 mm / 0.25 in.)

04128 to 04148 Emulsified Asphalt

Submit a Request for Test (MAT-100) indicating the source of the material. Sources are prequalified by the DMT in accordance with AASHTO R 77. The specific refiner of the material must be indicated on the MAT-100, not the Contractor, subcontractor or vendor, Contractor, subcontractor or vendor can be noted in the comments section of the MAT-100.

Table 1. Asphalt Emulsions Material Codes and Grades

04128 RS-1	04133 SS-1	04138 CRS-1	04142 CMS-2	04145 CSS-1H
04147 RS-1H	04134 SS-1H	04139 CRS-2		04146 CSS-1
		04148 CRS-1P (polymer modified)		

Scope: Asphalt emulsions composed of a semisolid liquid asphaltic base, water, and emulsifying agent.

Sampling and Procedure: AASHTO T 40 / AASHTO T 59: Testing Emulsified Asphalt

Specification/Report Form: Standard Specifications, Section M.04 / MAT-402

08010 EXPANSION JOINT - Asphaltic Plug

Scope: Components, testing, and application requirements for field molded asphaltic plug material used within expansion joints on bridges with asphalt concrete overlays or PC concrete decks.

Sampling: AASHTO T 40

Procedure: ASTM D 6297 Table 1 and special provision specifications.

1. Thermoplastic polymeric-modified asphalt binder per manufacturer specifications.
2. Aggregate per manufacturer specifications.
3. Foam expansion joint filler per manufacturer specifications.
4. Steel bridge plate per manufacturer specifications.

Specification/Report Form: Special Provision / MAT-100

04199 Membrane Waterproofing

Scope: Fully-adhered built-up bituminous membrane waterproofing system for bridge decks.

Sampling: AASHTO T 40

Procedure: Materials Certificate must be stored in the Project Records.

1. Primer: ASTM D 41:
2. Asphalt: ASTM D 449, Type III:
3. Fabric: ASTM D 1668:
4. Bituminous Plastic Cement: ASTM D 2822, Type I:

Specification/Report Form: Standard Specifications, Section 7.07 / None

04207 to 04208 DAMP PROOFING

04207 DAMP PROOFING (PRIMER)

04208 DAMP PROOFING (SEALER)

Scope: Three asbestos-free asphalt roof coatings of brushing or spraying consistency suitable for use as waterproofing and damp proofing of concrete and concrete masonry.

Sampling and Procedure: None. Project staff reviews the Materials Certificate for compliance with contract specifications.

Specification/Report Form: Standard Specifications, Section 7.08 /NA

Aggregates

SAMPLING OF AGGREGATES

Scope: Obtaining coarse and fine aggregates at the source of supply and/or at the project site.

Sampling: Samples are to be obtained by a representative of the Department. Samples from potential open faced banks or pits are the responsibility of the producer unless an adequate and representative stockpile has been prepared for use on Department projects.

Procedure: AASHTO T 2

REDUCING SAMPLES OF AGGREGATE TO TEST SIZE (DMT Staff only)

Scope: Reduction of large field samples of aggregate by quartering or by use of the mechanical splitter.

Sampling: AASHTO T 2

Procedure: AASHTO T 248

04697 to 04905 & 08034 to 08054 Fine & Coarse Aggregate

04697 SAND MASONRY GRADING A

04700 SAND

04703 SAND FILLER

04704 SAND MASONRY GRADING B

04709 SAND (FOR TRENCHING AND BACKFILLING)

04819 GRAVEL BANK RUN

04820 GRAVEL FILL

04901 BEDDING MATERIAL M08.01-21

04902 BORROW

04905 FREE DRAINING MATERIAL

08034 STONE (BROKEN/CRUSHED)

08032 SAND (WASHED)

08033 SAND (NATURAL)

08035 GRAVEL (CRUSHED)

08036 RECLAIMED MISC. AGGREGATE - 08036X (OFF SITE)

08037 RECLAIMED WASTE - 08037X (OFF SITE)

08038 SUBGRADE

08039 EMBANKMENT MATERIAL

08054 WETLAND SOIL

Scope: Material is tested using various test methods to determine conformance to project specifications. These methods include sieve analysis, washed sieve analysis, soundness, and others listed below.

Reclaimed Misc. Aggregate: Glass-free and clinker-free reclaimed waste, which has been crushed, graded and blended, as specified in the Contract, with natural crushed stone or gravel.

Reclaimed Waste: Crushed and graded concrete removed from pavements, structures, or buildings.

Sampling: AASHTO T 2 and AASHTO T 248

Specification: Standard Specifications, Sections (M.01, M.02, M.03, M.04, M.05 or M.12)

Procedures:

SIEVE ANALYSIS – AASHTO T 27

Report Form: MAT-205, MAT-206, or MAT-207.

WASHED SIEVE ANALYSIS – AASHTO T 11

Report Form: MAT-205, MAT-206, MAT-207, or MAT-223.

DEGRADATION RESISTANCE OF AGGREGATE (L.A. ABRASION TEST) – AASHTO T 96

Report Form: MAT-211

SOUNDNESS OF AGGREGATE (MAGNESIUM SULFATE) – AASHTO T 104

Report Form: MAT-220 or MAT-221

MOISTURE DENSITY RELATIONSHIP OF SOILS – AASHTO T 99, AASHTO T 180

Report Form: MAT-213, and MAT-217 or MAT-218

TOTAL EVAPORATIVE MOISTURE CONTENT OF AGGREGATE BY DRYING – AASHTO T 255

FLAT AND/OR ELONGATED PARTICLES IN COARSE AGGREGATE – ASTM D4791

Report Form: MAT-104

FRACTURED PARTICLES IN COARSE AGGREGATE– ASTM D5821

Report Form: MAT-104

BULK DENSITY (UNIT MASS) AND VOIDS IN AGGREGATE– AASHTO T 19

Report Form: MAT-104

SPECIFIC GRAVITY AND ABSORPTION OF COARSE AGGREGATE– AASHTO T 85

Report Form: MAT-219

ORGANIC IMPURITIES IN FINE AGGREGATE – AASHTO T 21

Report Form: MAT-206

04771 MASONRY FACING

Scope: Masonry facing stone shall be either dimensioned masonry stone or ashlar masonry stone.

Sampling and Procedure: Field inspection of stone by project personnel unless samples are required.

Specification/Report Form: Standard Specifications, Article M.11.01 / MAT-100.

04909 CURBING - GRANITE STONE

Scope: Granite curbing typically used on highway bridges at the bottom of parapets adjacent to the bridge deck. Shape typically has one sloped face.

Sampling and Procedure: Field inspection of stone by project personnel.

Specification/Report Form: Special Provision / MAT-100.

04910 CURBING - GRANITE SLOPE

Scope: Granite curbing typically used on at the approaches to bridges or parking lots. Shape is typically rectangular.

Sampling and Procedure: Field inspection of stone by project personnel.

Specification/Report Form: Standard Specifications, Article M.12.07 / MAT-100.

Chapter 4 – Materials Evaluation and Testing Procedures

This chapter describes in detail the procedures used by Division of Materials Testing (DMT) personnel to develop recommendations on the conformance to specification of materials purchased by the Department for its own use or used by a Contractor in the construction or maintenance of a facility.

In addition this chapter also describes the procedures used by DMT personnel to inspect and qualify facilities that produce materials for use on a regular basis by the Department or Department contractors.

Materials Evaluation

Material Catalog Cuts

Many materials used on a project are evaluated based on catalog cuts. These materials are typically mass produced items such as louvers, bathroom fixtures, roadway lighting, and electronic equipment available from numerous manufacturers. Due to the variety of choices, the designer typically develops a specification that can be met by several of the manufacturers. The Designer is then responsible for reviewing the catalog cuts submitted by the Contractor to the Contract Administrator and determining if the contractor-selected product meets the project specification. Consequently, the DMT will not repeat the evaluation performed by the Designer and recommend acceptance or rejection of the material. A Request for Test (MAT-100) for the materials reviewed and approved or rejected by the Designer is not required. Project field personnel are responsible for verifying that appropriate materials incorporated into the project were approved by a catalog cut submittal.

Visual Inspection of Materials on Project Site

Many materials used on a project can be initially evaluated or must be evaluated daily by project staff. The acceptance of these materials is most effectively based on the visual inspection of all these materials at the project site and over the course of the entire project. Examples of these materials are, but not limited to, temporary precast concrete barrier curb, bedding material, and topsoil (from project site). The Minimum Schedule for Acceptance Testing clearly defines which materials require a formal Request for Test (MAT-100) for acceptance purposes.

Material Certificate

Many materials used on a project can be evaluated by Project or DMT staff by the review of a material certificate. The Minimum Schedule for Acceptance Testing clearly defines which material certificates require review by project or DMT staff.

Materials Testing Procedures

Materials typically used on highway projects (i.e., concrete, HMA, subbase, etc.) and also used in vertical construction are frequently tested and as such must be tested in accordance with the Minimum Schedule for Sampling Materials for Test (Minimum Schedule). A recommendation of acceptance or rejection of the material will be made by DMT personnel based on the results of this testing.

Sampling Materials for Test

Laboratory personnel regularly sample both fine and coarse aggregates, aggregate blends for roadbase applications, and other various materials used for Construction and/or Maintenance purposes. On a less frequent basis, these personnel also oversee the field sampling of aggregates and plastic PC concrete by construction inspection personnel as required for assurance purposes.

Sampling is a critical component of testing and is performed according to the applicable specification indicated under “sampling” in each section of this manual. DMT personnel collecting samples will utilize every precaution to obtain unbiased samples that represent the nature and condition of the material to be sampled. DMT personnel are certified in the applicable sampling procedures through the New England Transportation Technician Certification Program (NETTCP) and qualified by established procedures as described in *Appendix H* to assure uniform procedures in obtaining random samples.

DMT personnel also regularly transport field samples to the central or satellite laboratories for testing. It is also important that samples are carefully handled and transported to prevent damage to the samples. Containers used to transport samples should be clean and adequate for the particular material being sampled. Furthermore, the containers should be durable and of a type and size that prevents loss, damage, or contamination of any portion of the sample.

Aggregates

Scope: Coarse and fine aggregates are obtained at the source of supply for annual qualification. Qualified sources are listed on the DMT website. Typical sampling locations include sampling from flowing aggregate streams (bins or belt discharge), conveyor belts, roadways, stockpiles, or vehicles typically used to transport material.

Sampling: Samples are to be obtained by a representative of the Department. Preliminary samples and tests for potential open faced banks or pits are the responsibility of the producer unless an adequate and representative stockpile has been prepared for testing for use on Department projects.

Procedure: AASHTO T 2

Precast Concrete Production Facility Inspection Reinforced Concrete Pipe

Purpose: This outline is a guide to personnel involved in the inspection of the manufacture of reinforced concrete pipe and allied products. The following factors must be considered while inspecting this material.

- Testing and inspection of the various materials selected for use.
- Proper proportioning and adequate mixing of the materials.
- Sufficient reinforcement and proper placement of reinforcement within form work.
- Proper handling, placing, and consolidating procedures.
- Proper curing of the product.

Materials inspector must become familiar with the manufacturing processes, designs, specifications, and procedures followed for any particular plant.

Scope: Reinforced concrete pipe, elliptical pipe, slotted pipe, and culvert ends may be accepted by the DMT on the basis of the manufacturer's certification. Products covered under this section include, but are not limited to, reinforced concrete pipe for use as a culvert, slotted reinforced concrete pipe for use as underdrains, and reinforced concrete culvert ends.

Annual Plant Inspection

This inspection is to ensure that a plant is capable of producing a product that meets AASHTO M 170, AASHTO M 207, and AASHTO M 175 Type II requirements, supplemented by Standard Specifications, Article M.08.01, as applicable.

Inspection MAT-324 indicates the name, address, and plant number of the manufacturer; and lists the number, make, capacity, type, and condition of all scales and seal dates, mixers, and pipe machines.

Materials: The inspector will obtain samples of cement, water, coarse aggregate, fine aggregate, admixtures, and reinforcing steel he proposed for use on the project from the manufacturer and indicate on MAT-324 the suppliers of the materials.

Sampling: All cement must be sampled at the mill and tested by an approved laboratory whose methods and equipment are regularly inspected by the Cement and Concrete Reference Laboratory. One copy of the test report certifying the acceptability of the cement shall be furnished to the Department. At the time of the annual inspection and at any time thereafter, the inspector may obtain a sample of cement currently in use and a copy of the corresponding certified test report.

1. Aggregate: Samples shall be obtained from approved storage piles or bins by the inspector during the annual inspection. Additional samples shall be taken at least once every month or from each new source.
2. Water: Each source of supply shall be sampled annually.
3. Reinforcement: Samples of each size and type of reinforcement shall be taken every six months, or as required.
4. Admixtures: Samples of each type of admixture from each source of supply may be obtained annually or as required.

Fabrication: Reinforced concrete pipe (RCP) must meet the requirements of the contract specifications. The inspector will observe the production process, which shall include checking the splices, spacing, and size of reinforcing at the time cages are assembled. The reinforcing shall be lapped not less than 51 mm and welded with an electric welding machine. The spacing, center-to-center, of adjacent rings of circumferential reinforcement in the cage shall not exceed 102 mm for pipe having a 102 mm wall thickness, nor exceed the wall thickness for larger pipe, and in no case shall exceed 152 mm. The cage shall contain sufficient longitudinal bars or members, extending through the wall of the pipe to maintain the reinforcement rigidly in shape and in the correct position within the form. For multiple layers, a line of circumferential reinforcement for any given total area may be composed of two layers for pipe with a wall thickness of less than 178 mm or three layers for pipe with a wall thickness of 178 mm or greater. The layers shall not be separated by more than the thickness of one longitudinal plus 6.4 mm. The multiple layers shall be fastened together to form a single rigid cage. All other specification requirements such as laps, welds, tolerance of placement in the wall of the pipe, etc., shall apply to this method of fabricating a line of reinforcement.

The reinforcing shall be free of objectionable coatings, particularly heavy corrosion prior to installation in the form. An adherent film of rust or mill scale is not considered objectionable. The reinforcement should be secure so that the placement of the concrete will not displace the steel from its proper position.

Preliminary Tests and Tests for Extended Deliveries - Sampling

As part of the yearly certification process, laboratory personnel will select RCP and witness 3-edge testing in the Spring and Fall of each year that certification is requested, two of each size pipe up through 750 mm diameter and one of each size greater than 750 mm diameter. The pipe sample shall be tested by the 3-edge bearing test as per AASHTO T 280, except as follows:

1. Modified or special design pipe shall be tested to the 0.3 mm (0.01 in.) load and the ultimate load requirements as per AASHTO M 170 and M 207.
2. At the discretion of the Engineer, pipe of standard design, as specified in AASHTO M 170, may be tested to the 0.3 mm (0.01 in.) requirement plus 10 percent additional load in lieu of ultimate load testing. Test pipe attaining 0.3 mm (0.01 in.) crack will not be acceptable for use on Department projects.

Rejection: The manufacturer **must** isolate the rejected pipe in its yard or provide some means to clearly indicate rejected pipe. Any size pipe previously rejected must be retested.

Precast Concrete Drainage Items

The following describes the role of the DMT in monitoring the production, quality assurance, and acceptance of precast concrete units such as catch basins, manholes, and pipe.

Quality Control Manual

Each fabricator, which proposes to manufacture precast units for use by the Department shall develop and maintain a plant-specific Quality Control Manual addressing in detail the production and certification process of products for use on Department projects. This Manual shall be submitted to the Department for initial approval, and resubmitted as required due to either operational changes within the company or changes in source of materials.

Annual Plant Certification

Each plant is subject to an annual inspection by a representative of the DMT. The purpose of this inspection is to determine if the facility has the infrastructure to manufacture precast units to the Department's requirements and the personnel and procedures necessary to adhere to the Quality Control Manual specific to that facility.

The inspector may review all phases of the manufacturing process, and will document the results of his inspection by completing the information required on Inspection MAT-324 "*Yearly Inspection of Precast/Prestressed Concrete Structure, and Concrete Pipe Manufacturers.*"

Periodic Plant Inspection

While the plant is producing precast units for the Department, an inspector from the DMT may visit the plant unannounced to perform the following inspection activities:

1. Ascertain that the fabrication process and equipment used in production and the test procedures, equipment and personnel employed in the manufacturer's quality control program are in continuing compliance with the specifications and the approved Quality Control Plan for that plant.
2. Review the manufacturer's records relative to production, testing, and shipment of the precast units for the purpose of determining that:
 - 2.1 the compressive strength, air content and slump of the concrete consistently met the requirements at time of shipping; and,
 - 2.2 the records are complete and accurate.
3. Sample component materials as prescribed previously under "Sampling."

Sampling

The quality of the materials used in the manufacture of precast units shall be determined by tests on samples taken on the following schedule:

Portland Cement: Cement shall conform to AASHTO M 85 or AASHTO M 240 and shall be from a source that participates in the Cement Certification Program (Appendix E). All cement shall be sampled at the mill and tested by an approved laboratory whose methods and equipment are regularly inspected by the Cement and Concrete Reference Laboratory. Test reports certifying the acceptability of the cement shall be furnished to the DMT. Cement shall be subject to sampling and testing at any time by the DMT.

Aggregate: Samples of aggregate shall be obtained from approved storage piles or bins by the inspector during the annual inspection. Additional samples shall be taken at least every month or from each new source.

Water: Each source of supply shall be sampled annually.

Reinforcement: Samples of each size and type of reinforcement shall be taken every six (6) months or as directed by the Engineer.

Miscellaneous Hardware: Manhole steps shall conform to AASHTO M 199. Sampling frequency will be determined by the Engineer. All steel frames and grates incorporated into catch basin and drop inlet tops shall bear the Independent Testing Agency Acceptance stamp.

Admixtures: Only admixtures meeting AASHTO M 194 will be considered during the mix design review.

Fabrication Process Review

During the annual inspection, the inspector will review the standard fabrication process in use at the plant to determine that the precast units are manufactured according to the requirements specified in Standard Specifications, Article M.08.02, and the approved Quality Control Manual for that plant. The following areas of the production operations are to be carefully inspected:

- Storage and handling of component materials.
- Equipment and mixing procedures, including use of approved concrete mix designs.
- Fabrication of reinforcement or reinforcing cages, where applicable.
- Dimensions, condition, and construction of forms.
- Prior to placing concrete, the positioning of reinforcing bars or cages in the forms; and in the case of catch basin or drop inlet tops, the positioning of steel frames.
- Transportation, placement, and consolidation of plastic concrete.
- Curing methods, handling and storage of units.
- Dimensions, details, surface finish, and freedom from defects of finished units.
- Proper marking and identification of units.
- Application of protective compound to surfaces of precast catch basin and drop inlet tops, which will be exposed when in service.

Review of Materials Testing by Plant Personnel

The manufacturer is required to furnish the equipment and personnel necessary to perform compressive strength tests and air content determinations to demonstrate conformance to the contract specifications and plans and to document the results of these tests in the plant records.

During the annual inspection, the inspector will review the testing equipment and procedures employed at the plant for conformance to the following requirements:

1. Sampling Freshly Mixed Concrete - AASHTO T 41.
2. Making and Curing Concrete Test Specimens in the Field - AASHTO T 23.
3. Obtaining and Testing Drilled Cores and Sawed Beams of Concrete - AASHTO T 24.
4. Compressive Strength of Cylindrical Concrete Specimens - AASHTO T 22.
5. Air Content of Freshly Mixed Concrete by the Pressure Method – AASHTO T 52.
6. Slump of Hydraulic Cement Concrete - AASHTO T 119.
7. Frequency of sampling and testing shall be Standard Specifications, Article M.08.02-4.
8. The compressive strength machine shall be calibrated by an approved agency at least once each twelve (12) months.
9. The pressure/volumetric meter is to be calibrated by the plant quality control personnel as required by the Engineer.

The inspector will witness the performance of the required tests by the manufacturer's personnel and shall designate on Inspection MAT-324 those plant employees qualified to perform the respective tests. The inspector will consult the manufacturer's Quality Control Manual for the procedure for recording test results to ensure that said records are accurate, complete, and available to a representative of the DMT upon request.

PRECAST/PRESTRESSED CONCRETE (STRUCTURAL) BEAMS/PILES/SUBSTRUCTURE

Production Inspection

The DMT will assign personnel to inspect/witness the fabrication of precast/prestressed items such as bridge girders, deck slabs, culverts, or piles. The length of the assignment will be prioritized as to the type of member being produced and the other current resource demands.

In general, any structure or component that primarily carries live load over or beneath a transportation facility will have oversight during production from the DMT or its representative.

Any structure or component that is used to primarily resist dead load such as, but not limited to, retaining walls and proprietary items such as gross particle separators may have oversight during the production time. The DMT may adjust the amount of inspection based on the reputation of the fabrication facility and the producer's daily adherence to their quality control plan.

Plant Inspection Procedure

Sampling and Frequency

The following component materials shall be sampled and tested at the frequencies listed below:

1. Portland cement (PC): PC shall be from an approved source. Each load shall be accepted by certification.
2. Aggregate: Samples from bins or stockpiles each month for each source of supply.
3. Admixtures: Only qualified admixtures are to be used.
4. Prestressing steel strand: Standard Specifications, Article M.14.01.
5. Post-tensioning tendons and anchorages: Sample as per Special Provisions.
6. Reinforcing steel: From each source, a 5 ft. (1.5 m) sample of each size for every 400 tons (181.4 mtons), with a minimum of one sample of each size from each source per project.

Inspection of Plant Facilities and Manufacturing Procedures (MAT-324)

1. Storage and handling of materials.
2. Batching, mixing, transportation and placement of concrete.
3. Curing method and apparatus; i.e., steam, radiant heat or other approved method including provision for recording time and temperature data during the curing cycle.
4. Concrete testing equipment; i.e., compression-testing machine (should be calibrated each 12 months), pressure-type air meters, cylinder molds, slump cones, unit weight apparatus and facilities for moist-curing test cylinders, ASTM C 192.
5. Equipment and procedure for consolidation of concrete.
6. Construction and capacity of casting beds.
7. Dimensions, condition, and construction of forms.
8. Method and equipment for applying prestressing or post-tensioning forces.
9. Method and equipment for measuring prestressing or post-tensioning forces and the procedure for measuring elongation of strands or tendons.
10. Construction details, accuracy, and calibration data of pressure gauges. (Gauges shall be calibrated at intervals not to exceed 6 months.)

Inspection of Casting Bed

1. Check cleanliness, level, and alignment of form liner.
2. Check position of bulkheads for proper length of units and skewed or sloped ends.
3. Inspect stringing of prestressing strands to ensure correct number and position of strands and location of "hold-downs."
4. For each strand: inspect tension, measure elongation, and check gauge reading for proper force application. Force measurement of elongation and gauge reading shall check each other and the theoretical value within 5 percent; if they do not, notify QC manager.
5. Witness back tensioning at the non-jacking end of deflected strands and straight strands to verify application of the required prestressing force. Standard Specifications, Article 5.14.03.
6. Inspect installation of post-tensioning tendons and anchorages, when applicable.
7. Check size, type, and location of in-place reinforcing steel, hardware, and miscellaneous steel.
8. Inspect condition and alignment of side forms.
9. Check proper bracing and anchorage of casting bed and end anchorages.

Inspection of Concrete Operations

1. Check identification marker for required data and placement in unit.
2. For deck units, inspect internal void forms for material, size, and proper installation.
3. Inspect concrete delivered to forms for homogeneity and uniformity of successive batches.
4. Witness/monitor sampling of concrete for quality control testing.
5. Witness slump, air tests, concrete temperature, and unit weight for conformance to specifications; accept or deem unacceptable on basis of results.
6. Spot-check batching and mixing of concrete to assure that approved mix design and procedures are being used.
7. Inspect placement, consolidation, and finishing of concrete for conformance to specifications and accepted concrete practices.
8. Ensure that approved curing method is used and applied at proper time; if steam or radiant heat is used, ensure that required preset period is observed.

Inspection of Fabricated Units

1. Inspect units to determine if they were cured uniformly. Review the time/temperature record of curing cycle for specification compliance.
2. Witness testing of cylinders for required concrete strength prior to removal of forms or detensioning.
3. After removal of side forms, inspect units for honeycomb, cracks, etc. Report major defects to supervisor for structural review by Department Bridge Design Section and or Designer.
4. Inspect detensioning operations for proper sequence, method, and timing of strand release.
5. Witness removal of units from casting bed.
6. Inspect completed units for as-built dimensions, camber, horizontal alignment, etc.
7. When applicable, witness testing of cylinders for required concrete strength prior to post-tensioning.
8. Witness post-tensioning operations (checking elongation of tendons and gauge readings) to assure gauge pressures and elongations are within prescribed limits.
9. Witness grouting of post-tensioning ducts for conformance to approved grout mix, equipment, and pumping procedure.
10. Witness all repairs to determine compliance with approved procedures and use of approved materials.
11. Witness testing of cylinders to determine concrete strength for shipping, when required, and 28-day strength for acceptance.

Report: Results of all tests and inspections shall be reported on appropriate forms. The inspector will maintain accurate records in the form of a daily log and production records of all information concerning the manufacture of each individual member. Final approval of precast, prestressed, and post-tensioned concrete members will be reported on MAT-100.

PORTLAND CEMENT CONCRETE (ALL)

Concrete Batch Plants and Delivery Vehicles

Scope: Each year, Producers must obtain certification of the plants and the hauling/mixing vehicles from the National Ready Mix Concrete Association (NRMCA)

Sampling: NA

Procedure: From NRMCA.

Report: DMT may request copies of the NRMCA inspection reports from the producer.

Compressive Strength of Cylindrical Concrete Specimens

Scope: Compression testing of molded concrete cylinders.

Sampling: Standard Method of Sampling Freshly Mixed Concrete, AASHTO T 141; Standard Method of Making and Curing Concrete Test Specimens in the Lab, AASHTO T 126.

Procedure: Refer to Standard Operating Procedure (SOP) in Appendix G

Specification/Report Form: Standard Specifications, Section 4.01 or 6.01 / MAT-308

Mass, Yield, and Air Content (Gravimetric) of PC Concrete

Scope: Determining the mass (per cubic meter or cubic foot) of plastic PC concrete delivered to project sites. The method also provides procedures for determining yield, cement content, and air content.

Sampling: Standard Method of Sampling Freshly Mixed Concrete, AASHTO T 141.

Procedure: Standard Method of Test for Mass per Cubic Meter (Cubic Foot), Yield and Air Content (Gravimetric) of Concrete, AASHTO T 121

Specification: Standard Specifications, Section 4.01 or 6.01 and M.03 or project Special Provisions.

Assurance Report (DMT Only): MAT-224, or MAT-225, and MAT-222

Acceptance Report (Project Personnel): MAT-308.

Admixtures

Scope: Project specifications normally require that an admixture shall perform the desired function without injurious effect upon the concrete. Proof of conformance to this requirement will be in the form of a certified statement from a recognized laboratory. The certified statement will contain evidence based on tests pertinent to the admixture made in the recognized laboratory by the use of concrete materials and by methods that meet requirements of current AASHTO and ASTM standards. Tests may be made on samples taken from a quantity submitted by the Contractor for use on the project or on samples submitted and certified by the manufacturer as representative of the admixture to be supplied. A recognized laboratory is any cement and concrete laboratory approved by the Engineer and inspected regularly by the Cement and Concrete Reference Laboratory sponsored by ASTM.

Sampling: AASHTO M 154 and AASHTO M 194

Procedure: Approval of the certified statement submitted for an admixture will qualify that admixture for inclusion in the Department's Qualified Products List regarding Admixtures for Portland Cement Concrete.

Specification/Report Form: Standard Specifications, Article M.03.01-9 / None

Structural Steel and Welding Shop Inspection

Scope: All structural steel fabricated for permanent incorporation into the project must be inspected by DMT staff during fabrication. DMT staff supplemented by consultant inspection staff can inspect any facility no matter where it is located to determine the adherence to quality control standards and project specifications. Adherence to the "Buy America" requirements of the contract is also an important aspect of this on-site inspection.

Sampling: None Documentation on material sources, quality control test results, and other appropriate topics are kept by the DMT representative until all fabrication is completed. This documentation is then forwarded to the Central Laboratory for inclusion in the project records.

Procedure: DMT staff must be notified where and when fabrication will take place so that inspection can be scheduled. The Contractor is responsible for notifying project staff, who in turn must notify the DMT.

Specification/Report Form: Standard Specifications, Section 6.03/NA

HOT MIX ASPHALT (BITUMINOUS CONCRETE/SUPERPAVE)

Annual Qualification of Hot Mix Asphalt Plants

Scope: Materials, technician qualifications, mix designs procedures, and calibration records and quality control test records are evaluated annually. The Department may perform random spot inspections of any aspect of the operation during the production season to ensure compliance to all specifications.

Sampling: Sampling of materials will be done during annual site inspection.

Procedure: Plants are inspected annually in the Spring.

Report: MAT- 404

Sampling HMA Mixtures

Scope: Procedures for sampling mixtures of HMA paving material.

Sampling: AASHTO T 168 modified.

Procedure: AASHTO M 323: Superpave Volumetric Design Method, AASHTO R 47: Reducing Samples of Hot Mix Asphalt (HMA) to Testing Size. Sampling and testing is required to be performed by a NETTCP certified technician. The sample from the transport vehicle can be taken from one location as specified in AASHTO T 168 modified.

Report Form: MAT-412s

HMA Inspection Personnel Assignment Procedure

Scope: A priority system is utilized in assigning Hot Mix Asphalt plant inspectors, employing a review of performance and current testing results. This priority system is developed by analyzing all test data on a daily basis and rating the plants according to past performance data. The details of this rating are included in the Department's Standard Specifications, Article M.04.02-2c. This information assists supervisors in prioritizing daily assignment of HMA inspectors to bituminous plants based on the following:

- **Poor recent performance** – determined by tabulating the latest 10 test average for each class where the running average is below 70%.
- **Daily tonnage produced** – where larger tonnage will generally get higher priority.
- **Random sampling** – as determined by the DC.

Binder Content by Ignition Method

Scope: This method of test is for the determination of the total percentage of bitumen in HMA mixtures. Aggregate calibration for each class of mixture shall be provided by the DC or may be submitted by the contractor for use during production.

Sampling: AASHTO T 168 modified, AASHTO R 47.

Procedure: AASHTO T 308

Report Form: MAT-412s

Correlation Between Production Pull and Binder Content by Ignition Method

Scope: To monitor the difference between the target plant production binder content and the corrected binder content by ignition method using a five (5) point moving average. If two (2) consecutive differences are more than 0.3%, a new correction factor may be required for the mix.

Sampling: AASHTO T 168 modified, AASHTO R 47.

Procedure:

1. AASHTO T 308, Asphalt Binder Content of HMA by Ignition Method
2. AASHTO T 329, Moisture Content of Hot Mix Asphalt by Oven Method
3. AASHTO R 47, Reducing Samples of HMA to Testing Size

Report Form: MAT-412s

Mechanical Analysis of Extracted Aggregate

Scope: To monitor mix compliance with the specifications and job mix formula (JMF) target values.

Sampling: AASHTO T 168 modified, AASHTO R 47

Procedure: AASHTO T 30 modified

Report Form: MAT-412s

Degree of Particle Coating of HMA Mixtures

Scope: Degree of coating of coarse particles of aggregate in a HMA mixture in relation to the wet mixing time. When HMA is mixed, coarse particles of aggregate are the last and the most difficult to coat, and the degree of their coating may be a measure of the degree of mixing.

Sampling: AASHTO T 195 modified and AASHTO T 168 modified.

Procedure: AASHTO T 195 modified.

1. Only one truck load of mixture is sampled.
2. Sample is taken from opposite sides of the load.

Report Form: NA

Bulk Specific Gravity of Compacted HMA Mixtures

Scope: This method determines of the bulk specific gravity to determine volumetric properties of compacted HMA mixtures.

Sampling: AASHTO T 168 modified, AASHTO R 47

Procedure: AASHTO T 166: Bulk Specific Gravity of Compacted Asphalt Mixtures Using Saturated-Surface Dry Specimens

Report Form: MAT-412s

Volumetric Calculations of VMA

Scope: These methods cover the formulas used to calculate VMA.

Sampling: AASHTO T 168 modified, AASHTO R 47.

Procedure:

1. AASHTO M 323: Superpave Volumetric Mix Design
2. AASHTO R 35: Superpave Volumetric Design for Hot Mix Asphalt
3. AASHTO T 329: Moisture Content of Hot Mix Asphalt by Oven Method
4. AASHTO T 312: Preparing and Determining the Density of Hot-Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor

Report Form: MAT-412s

Preparation of Gyratory Specimens

Scope: Preparation of test specimens using the gyratory compactor.

Sampling: AASHTO T 168 modified, AASHTO R 47.

Procedures:

1. AASHTO M 323: Superpave Volumetric Mix Design
2. AASHTO R 35: Superpave Volumetric Design for Hot Mix Asphalt
3. AASHTO T 329: Moisture Content of Hot Mix Asphalt by Oven Method
4. AASHTO T 312: Preparing and Determining the Density of Hot-Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor

Testing of HMA materials, fabrication of gyratory molds, and theoretical, and liquid content must be started and fabricated within 1/2 hour from the time of sampling from the delivery truck and completely finished within 2 hours. Physical, volumetric and other properties shall be calculated in accordance with the contract specifications and AASHTO M 323 and AASHTO R 35.

Maximum Specific Gravity of HMA Paving Mixtures

Scope: Determination of the maximum specific gravity of uncompacted HMA paving mixtures.

Sampling: AASHTO T 168 modified, AASHTO R 47.

Procedure: AASHTO T 209 modified.

1. Water bath temperature correction shall not be utilized provided that the water bath temperature is $77 \pm 0.9^{\circ}\text{F}$

Report Form: MAT-412s

Production Inspection at HMA Plants

Scope: The purpose of production inspection is to monitor compliance with the quality assurance program and the specifications. The aggregate must be of uniform quality and gradation and must be fed into the plant in a uniform manner; the heating and drying of the aggregates must be uniform; the separation of the aggregates must be controlled; and the components must be combined and mixed in a uniform, consistent manner. For these reasons, the inspector must be thoroughly familiar with all phases of the manufacturing process. HMA production activities includes the following:

1. **Process Control (PC):** Typically performed by the HMA producer prior to shipment.
2. **Quality Control (QC):** The sum total of activities performed by the seller (producer, manufacture, contractors) to make sure that a product meets contract specification requirements.
3. **Acceptance System (Acceptance/Verification Plan):** All factors that comprise the Agency's determination of degree of compliance with contract requirements and value of a product. These factors include Agency sampling, testing, acceptance limits, risk evaluation, and inspection. These factors should also include validated results of contractor sampling and testing.
4. **Independent Assurance (IA):** IA is an unbiased and independent verification of the Quality Assurance system used as a method of determining the reliability of the test results obtained in the regular sampling and testing activities. These results are not to be used elsewhere.

Report Form: MAT-412s

Duties of the HMA Plant Inspector

Scope: The inspection includes but is not limited to checking component materials in the stockpile, cold bins, hot bins; PG binder, and additive; inspection of processing, sampling; and testing the finished product for conformance to the specifications.

Sampling and Procedure: NA

Report Form: Daily Inspector Report \ MAT-431.

Status of New Mixes, Existing Mixes From Previous Year's Production

Scope: Each plant will have each class of HMA material evaluated based on previous year's production compliance for Va and VMA. Based on the ranking a class receives, it will determine whether the material can be produced without the prior completion of a PPT. Rankings will be provided to each HMA producer annually at the beginning of the paving season.

Sampling: NA

Procedure: Included in the Standard Specifications Section M.04

Report Form: NA

Mix Design / Job Mix Formula(JMF) Submittal and Change Procedure

Scope: The Producer shall submit an annual JMF as specified in Article M.04.02. The JMF will be reviewed by the DC and a mix status will be provided in accordance to Article M.04.02.2.c. Based on acceptance test results, the Contractor may be required to submit an updated JMF using MAT-429 (JMF Changes tab) for that class of material in order to continue supplying material.

Sampling: NA

Procedure: Included in the Standard Specifications Section M.04

Reports: JMF annual submittal MAT-429, MAT-440

HMA Verification Testing Procedures

Scope: Verification testing will be performed to validate Contractor's QC tests used for acceptance. Samples will be randomly obtained by Department personnel from the quartered field samples obtained as indicated in Section M.04.

For non-PWL lots, the ratio of verification tests to the Contractor tests will be a minimum 1 to 10. For PWL lots, the ratio of verification tests to the Contractor tests will be a minimum of 1 to 3.5. Verification samples will be tested at the Central Laboratory. QC and verification test results for Gmm, Gmb, Pb, VA and VMA will be compared using the F-test and t-test at a 0.01 significance level for PWL lots and the absolute difference for Non-PWL lots.

Sampling: All verification samples are obtained and transported to the Central Laboratory by the Contractor within 2 business days of production.

The Contractor will follow AASHTO T 168 5.2.3 for sampling and AASHTO R 47 for the mechanical splitting of the sample. The following figures demonstrate the procedure to be used.




Figure 2- First Splitting Process




Figure 3- Second and Third Splitting Processes

Procedures:

1. AASHTO T 308: Method for Determining the Asphalt Content of HMA by the Ignition Method.
2. AASHTO T 209: Theoretical Maximum Specific Gravity and Density of HMA Mixtures.
3. AASHTO T 166: Bulk Specific Gravity of Compacted Asphalt Mixtures using Saturated Surface-Dry Specimens.
4. AASHTO T 168: Sampling of Paving Mixtures.
5. AASHTO T 312: Preparing and Determining the Density of Hot Mix Asphalt Specimens by Means of the Superpave Gyrotory Compactor. The compaction temperature will match the subplot compaction temperature as tested at the Contractor Laboratory.
6. AASHTO T 329: Moisture Content of Hot-Mix Asphalt (HMA) by Oven Method. Should the field sample be re-heated for 1.5 hours or more, this test may be omitted.

For non-PWL lots, results will be considered validated when the the difference of te QC and verification results falls within the tolerances in Table 4.

For PWL lots, when the project estimated quantity is below 10,500 tons or when the remaining tonnage after a JMF change or after failing fata validation lot is below 10,500 tons, one data validation analysis will be performed for all the tonnage or remaining tonnage per mix design per project. The minimum number of verification tests per each data validation lot is three. Results will be considered validated when both the F- and t- tests pass.

For PWL lots with project estimated quantities over 10,500 tons, a data validation lot will include QC and verification results in three consecutive acceptance lots under the same mix design. The first data validation lot will be performed when the first three acceptance lots are completed and consecutive data validation lots will be performed each time a new acceptance lot is closed. QC and verification data from the last two acceptance lots will be rolled over to be used in consecutive data validation lots except when prior data validation lots failed. The minimum number of verification tests per each data validation lot is five. Results will be considered validated when both the F- and t- tests pass.

Should the Department be unable to validate the Contractor's acceptance test result(s) in any acceptance PWL lot, The Engineer will test the remaining verification samples in the lot and use the verification results to calculate the lot pay adjustment.

When any single result fails the F- or t- tests, HMA staff will notify IA staff. HMA staff shall review past tests specific to the type of material that failed to look for trends. The HMA staff shall contact the Contractor's Quality Control manager to notify them of the deficiency and request that the Contractor investigate.

If the Contractor request dispute resolution testing, all sublots in the disputed lot will be tested by the Independent Assurance Section and those test results will be used for the lot pay adjustment. The Department reserves the right to deny dispute resolution testing is there is a history of disputed lots that confirmed verification results or if the dispute resolution samples appear to be tampered.

Should the Department be unable to validate the Contractor's Non-PWL acceptance test result(s), The Engineer will use verification results for the pay adjustment calculation in the corresponding sublots.

Report Forms: MAT-408PWL and MAT-408NON_PWL

Mix Design / Job Mix Evaluation

Scope: In order for a JMF to be approved, the properties of the aggregate components or mix shall meet the verification tolerances shown in Table 3.

Sampling: As part of the JMF submittal, the Producer shall submit the following samples to the Division of Material Testing:

- 4 - one quart cans of PG binder, with corresponding Safety Data Sheet (SDS)
- 1 - 50 lbs bag of RAP
- 2 – 50 lbs bag of plant blended virgin aggregate
- 2 - 10,000 kg boxed split sample material for TSR design

Procedure: Testing will be performed by the DMT to evaluate each proposed JMF and will include:

Aggregate Components Consensus Properties Verification:

- 1.AASHTO T27: Mechanical Analysis of Aggregate
- 2.AASHTO T85: Coarse Aggregate Specific Gravity
- 3.AASHTO T84: Fine Aggregate Specific Gravity
- 4.ASTM D 5821: Coarse Aggregate Angularity
- 5.AASHTO T304, Method A: Fine Aggregate Angularity
- 6.ASTM D 4791: Flat and Elongated Particles (1:5)
- 7.AASHTO T176: Sand Equivalent

Mix Verification:

1. AASHTO T209: Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures.
2. AASHTO T166: Bulk Specific Gravity of Compacted Asphalt Mixtures using Saturated Surface-Dry Specimens.
3. AASHTO T312: Preparing and Determining the Density of Hot Mix Asphalt Specimens by Means of the Superpave Gyrotory Compactor
4. AASHTO R35: Air Voids, VMA, VFA, Density to Nini
5. AASHTO T283: Resistance of Compacted Asphalt Mixtures to Moisture-Induced Damage

Properties	Tolerance b	Properties	Tolerance b
#200	1.0	Gmm	0.022
#100	3.0	Gmb	0.020
#50	3.0	Pba	0.6
#30	4.0	PD@Ni	1.5
#16	4.0	Gse	0.052
#8	5.0	Gsb	0.028
#4	5.0	Gsa	0.025
3/8"	5.0	CAA (1 face/2 faces)	10
1/2"	4.0	SE	15
3/4"	4.0	FAA	0.8
1"	3.0	F & E	5.0
Va	1.3	TSR	15 & Minimal Stripping
VMA	1.3		
VFA	6.0		

⁽¹⁾ Tolerance is the absolute difference in the measured values, not a percentage of the values.

Report Form: MAT-418

Resistance of Compacted HMA to Moisture Induced Damage

Scope: Preparation of specimens and measurement of the change of diametral tensile strength resulting from the effects of saturation and accelerated water conditioning of compacted HMA mixtures in the laboratory. This test may be performed on HMA laboratory mixture, mixtures sampled from newly loaded trucks, field pavement samples, and pavement cores.

Sampling and Procedure: AASHTO T 283 modified

Report Form: AASHTO T 283 modified Table 1, Moisture Damage Laboratory Data Sheet or MAT-428

Volumetric and Specific Gravity Using Gyrotory Compactor

Scope: These methods cover the determination of volumetric and specific gravity calculations of test specimens made by Superpave gyrotory compactor.

Sampling: AASHTO T 168 modified, AASHTO R 47

Procedure: AASHTO M 323, and AASHTO R 35

Report Form: MAT-412s

Performance Graded Asphalt Binder (PGAB)

Scope: PGAB suppliers are prequalified by the DMT in accordance with AASHTO R 26 modified. To maintain qualified status, suppliers must submit monthly split samples to the DMT. HMA producers must maintain a log of binder deliveries using a MAT-435 or equivalent approved by the Engineer.

Requirements: A Certified Test Report and bill of lading representing each delivery must be provided to the producer in accordance with AASHTO R 26 modified. Upon material delivery, plant personnel shall record lot number, date, grade of binder, witnessed by, hauler name, liquid supplier, ticket number, receiving storage tank number, quantity received, and previous tank status (quantity) in the binder log (MAT-435). The Contractor shall provide binder samples from the delivery upon request of DC. The blending of PG binder from different suppliers is not allowed unless the HMA producer submits a QC plan for this purpose.

Sampling: In accordance with AASHTO T 40

Procedure: In accordance with all AASHTO standard methods of test listed in AASHTO 332

Report Form: QC Plan / MAT-401

DENSITY OF SOIL AND SOIL - AGGREGATES

Scope: The Contractor shall determine of the in-place density of soil and soil aggregate by using a measurement device approved by the Engineer. Density measurements shall be performed where specified in the Contract.

Procedure: Field testing shall be performed in accordance with AASHTO T 310 or other approved industry standard test method. The density results obtained shall be reported as a percent of the maximum dry density as determined by AASHTO T 180 Method D.

Correlation: All gauges shall be correlated annually prior to use on Department projects. Correlation blocks shall be provided by the Department or the gauge manufacturer. The gauge shall be correlated in accordance with manufacturer's recommendations.

Standardization: As a minimum, standardization of the gauge shall be performed daily prior to its use. This process shall be performed in accordance with the manufacturer's recommendations.

Report Form: Form CON-125

DENSITY OF IN-PLACE ASPHALT PAVEMENT BY THE CORE METHOD

Procedure: Refer to Standard Operating Procedure (SOP) in Appendix G



Chapter 6 – Independent Assessment/Verification Program

INDEPENDENT ASSESSMENT

Independent assessment of DMT methods and equipment is performed through the AASHTO Accreditation Program (AAP). This program entails on-site inspection by personnel from the AASHTO Materials Reference Laboratory (AMRL) and the Cement and Concrete Reference Laboratory (CCRL). After the inspection by AMRL or CCRL, any deficiencies noted in equipment, personnel, or procedures are addressed in a timely fashion.

In addition to the on-site inspection, AMRL and CCRL also send samples of various materials for testing (proficiency samples). The results of these tests are compared with the test results for the same material from other testing facilities. If proficiency sample results vary by more than two standard deviations, an internal investigation will be undertaken to determine what may have affected the results. This investigation will include, but not be limited to, the following: review of work sheets and data entry; equipment check; scale check; test procedure; and a review of previous proficiency test results. Corrective action is taken as soon as possible. The determination is documented and kept on file before forwarding to AMRL or CCRL.

EQUIPMENT CALIBRATION AND CHECKING

The following tables indicate testing equipment that is calibrated and checked according to requirements set forth by the AASHTO Accreditation Program. Included are the frequency, range, procedure, and method for tractability to the National Institute of Standards and Technology (NIST). To assure proper compliance with calibration, verification, and checking requirements, a list based on these tables is maintained by the room supervisors where the equipment is located. The list includes equipment numbers, date of calibration, and must be updated at a minimum at the indicated frequency. Should equipment be damaged, moved, or provide suspect results, a recalibration or check will be requested by the room supervisor and documented on the list.

Table 1 EQUIPMENT TO BE CALIBRATED

	AASHTO REFERENCE	FREQ. (Months)	PROCEDURE	TRACEABILITY to NIST
Analytical Balances	Methods for HMA, Soils Aggregates	12	Calibration Performed by Outside Agency	Test Weights
G.P. Balances Scales & Weights	Methods for Bituminous, Soils, Aggregates	12	Calibration Performed by Outside Agency	Test Weights
HMA Mech. Compactor	T 245	36	Calibrated with the Hand Operated Hammer	Not Applicable
Mechanical Compactor	T 180	12	Calibrated with the Hand Operated Hammer	Not Applicable
Pressure Air Meters	T 152	36	AASHTO T 152 (Section 4 Calibration of Apparatus)	Not Applicable
Saybolt Viscometers	T 59	36	AASHTO T 72 (Section 9)	AASHTO T 72 (Section 9)
Test Thermometers	T 201, T 202, T 49, T 51	6	ASTM E-77 (Section 9)	Thermometers
Unit Weight Measures Scales	T 19	12	AASHTO T 19 (Section 8)	Not Applicable
Viscometers	T 201	36	Zeithfuchs Cross-arm Viscometer AASHTO T 201 (Section A3)	AASHTO T 201 (Section A3.2)
	T 202		Vacuum Capillary Viscometer	AASHTO T 202 (Section A4.2)
Compression Testing Machines	T 22, T 245	12	Verification Performed by third party in Accordance with AASHTO T 67	Proving Ring by third party

Table 2 EQUIPMENT TO BE CHECKED

	AASHTO REFERENCE	CHECKING FOR	FREQUENCY (months)	PROCEDURE
Autoclave	T 107	Heating Time, Temperature, Pressure, Cooling Time	24	Performed by CCRL AASHTO T 107 (Section 4.5)
Autoclave Safety Valve Agency	T 84	Proper Relief of Pressure	6	Checked by Outside AASHTO T 107 (Section 6.4)
Conical Mold, Tamper	T 84	Critical Dimensions	24	Performed by AMRL AASHTO T 84 (Section 4.3, 4.4)
Testing Equipment for Portland Cement	T 106	Critical Dimensions	24	Performed by CCRL AASHTO T 106 (Section 3.4)
	T 137	Critical Dimensions	24	AASHTO T 137 (Section 5)
	T 131	Critical Dimensions	24	AASHTO T 131 (Section 3)
L.A. Machine	T 96	RPM & Critical Dimensions	24	In-house procedure #42
Steel Spheres	T 96	Individual Weight and Charge Weight	24	In-house procedure #42
Mechanical Shakers	T 27	Sieving Thoroughness	12	In-house procedure #45
Sulfate Oven	T 104	Rate of Evaporation	12	In-house procedure #44
Sulfate Soundness Containers	T 104	Physical Condition	12	In-house procedure #43
Sieves	All applicable	Physical Condition and Measure Openings as Required	6	M-92 via applicable In-house procedures
Drying Ovens	All applicable	Verify Temperature Settings	4	Applicable in-house procedures
Manual Hammer	T 180	Weight and Critical Dimensions	12	In-house procedure #31
Molds	T 180	Critical Dimensions	12	In-house procedure #32
Straight Edge	T 180	Planeness of Edge	6	In-house procedure #33

Note: In-house procedures are maintained by the supervisor of the room where the equipment is located.

Chapter 7 - Suggested Minimum Schedule for Acceptance Testing (LOTICIP)

Local Transportation Capital Improvement Program (LOTICIP)

4/2/2019

*ONLY Applies to Municipal Adminstered LOTICIP Projects **not** on National Highway System*

Material Name	Unit	Test/Documentation	Frequency 1 per	Notes
Anchor Bolts	ea.	MC	project	1 per size
Asphalt Emulsions (CSS-1, RS-1 or SS-1)	gal	MC	10k	
Bituminous Concrete (HMA)	ton	D 2950 FLDT	day	See Note 3
Cement - Portland Type I/II	bag	FLDT	project	empty bag
Chemical Anchor	lb.	QPL MC	project	
Concrete-Ready Mixed	c.y.	T22 FLDL	75	4 cylinders
Construction Signing	ea.	MC	project	
Geotextile	s.y.	QPL MC	project	
Gravel (Bank Run or Crushed)	c.y.	T27 LABT	5k	
Grout, Non-shrink	bag	MC	project	
Masonry Brick & Block (Solid)	ea.	FLDT	project	See Note 1
Pipe - Reinforced Concrete	l.f.	PC-1	project	See Note 1
Pipe (Metal & Plastic) All types	lf	MC	project	See Note 1
Pipe Arch - Aluminum	lf	MC	project	See Note 1
Precast Concrete Items (not pipe)	ea.	PC-1	Item type	
Prestressed Concrete Members	ea.	LABT	1	See Note 2 & 3
Reclaimed Misc. Aggregate	c.y.	T27/Chem Analysis	2500	See Note 5
Reclaimed Waste	c.y.	T180 LABT	50k	See Note 5
Sand (Masonry /Trenching & Backfilling)	c.y.	T27 LABT	2500	
Sheet Piling	l.f.	MC	project	See Note 4
Sign Post	ea	MC	project	See Note 1
Span Pole - Steel or Wood	ea.	MC	project	See Note 3
Steel Reinforcing Bars (Plain or Epoxy)	lb.	T244 MC	200t	
Stone (Broken/Crushed)	c.y.	T27 LABT	20k	
Structural Steel	cw	Shop Drawings	project	Notes 2, 3 & 4
Traffic Signal Equipment	ea.	MC	project	NA

Notes

1	Material should be inspected on the project site prior to use. Suspect material should be physically tested to determine conformance.
2	QC Inspection should be provided and documented during fabrication.
3	Contact the Department of Transportation Division of Materials Testing to determine vendor qualifications and QA inspection availability.
4	Documentation should be provided to determine conformance to Buy America requirements.
5	FORM MAT-212 should be completed and provided by the Contractor prior to use of material.

Test Method/Test Type

LABT	Laboratory Test
FLDT	Test performed in the field
QPL	ConnDOT Qualified Products List (http://www.ct.gov/dot/lib/dot/documents/dresearch/conndot_qpl.pdf)
PC-1	MAT-308 Required from producer with shipment
MC*	Materials Certificate

*Should comply with ConnDOT Standard Specification Section 1.06.07

Legend

Item: Standard Specification Section and the first four digits of the Contract Item number.
Title: Generally the overall subject of the Standard Specification Section and the Contract Item numbers.
Item Unit: Generally the pay unit of the Contract Item.
Material #: Code used in SiteManager and by the Division of Materials Testing to identify component materials used in Contract Items.
Material Name: Definition of the Material #.
Material Unit: Unit of Material that defines a quantity represented by a sample. Example: A sample of concrete represents 50 CY of material regardless of what the item unit is.
MAT 100: Indicates whether a Request for Test (MAT-100) is required to be submitted to the Division of Materials Testing (See Note 11. for ALT)
Sample Type: Acceptance (Prod) or Information requires a MAT-100 to be submitted. Accept (Field) does not require a MAT-100 to be submitted.
Test Method: AASHTO or ASTM test method. See below. "Chem" requires
Test Type: Describes the test, where the test is performed, or what is required to be submitted with the MAT-100.
Responsibility: Person who performs the test.
Frequency: Number of tests required per quantity of material using the material units: (E) English (M) Metric.
 1 per "quantity" indicates that **all** the quantity of each type (size/shape/composition) of material, per item, from a single vendor and manufacturer **must be represented** on a single or multiple Request for Test(s) (MAT-100). MAT-100(s) total represented quantity must match total quantity installed.
Sample Size: Size of Sample.

Test Type:

FLDT	Test performed in the field
LABT	Laboratory Test
FLABT	Field and Laboratory Testing
LMCT*	Lab Test, Mat Cert and Cert Test Report (Originals Required)
MC*	Materials Certificate (Original Required)
MCCTR*	Materials Certificate and Certified Test Report (Originals Required)
PC1	Self Certification from producer supplied per shipment
QPL	Qualified Product List
Visual	Project Inspector must visually inspect upon delivery/installation. Visual inspection by DMT staff denotes witnessing fabrication of material where it is being fabricated. Documentation of visual inspection on the project by project staff is in accordance with District/Office of Construction policies.

*Materials Certificates and Certified Test Reports must comply with Standard Specification Section 1.06.07. Note: Materials Certificates for items composed of, or containing, steel or cast iron must also indicate where the steel and cast iron was produced and fabricated.

Chapter 8 - Minimum Schedule for Acceptance Testing

Chapter 8_Acceptance Testing v19.9

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size									
											(E)	(M)	lbs	kg								
01.01	Environmental Items		03166	Sheeting, Polyethylene	s.y.	NO	None	NA	Visual	Project Staff			See Note 8.									
			04XXX	Bit. Concrete (Various)	ton	NO	None	NA	Visual	Project Staff												
			04776	Hay, Baled	ea.	NO	None	NA	Visual	Project Staff												
			04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff												
			08044	Retaining Wall - Precast Conc.	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	1	1	NA									
02.01	Clearing & Grubbing	l.s.	00000	Labor only		NO																
02.02	Rdwy Ex, Formation of Embankment and Disposal of Surplus Material	c.y.	08037X	Reclaimed Waste (OFFSITE)	c.y.	YES	Accept (Prod)	Chem(offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72								
			08037	Reclaimed Waste			Information	T180	LABT	District Lab	20k	15k	160	72								
			08039	Embankment Material																		
02.03	Structure Excavation	c.y.	00000	Labor Only		NO																
02.04	Cofferdam	l.f.	00000	None		NO																
02.05	Trench Excav	c.y.	00000	None		NO																
02.06	Ditch Excav	c.y.	00000	None		NO																
02.07	Borrow	c.y.	04902	Borrow	c.y.	YES	Information	T180	LABT	District Lab	20k	15k	160	72								
			08037X	Reclaimed Waste (OFFSITE)																		
02.08	Free-Draining Material	c.y.	08037X	Reclaimed Waste (OFFSITE)	c.y.	YES	Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72								
			08037	Reclaimed Waste			Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72								
			08039	Embankment Material			Information	T180	LABT	District Lab	20k	15k	160	72								
02.09	Subgrade, Form	s.y.	00000	Labor Only		NO																
02.10	A Water Pollution Control	est.	03166	Sheeting, Polyethylene	l.f.	NO	None	NA	Visual	Project Staff			See Note 8.									
			04XXX	Bit. Concrete (Various)	ton	NO	None	NA	Visual	Project Staff												
			03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff			NA									
			See 06.01 for Portland Cement Concrete materials, 06.51 for pipe, 07.03 for Riprap, and 09.53 for Sod.																			
02.12	Subbase	c.y.	04819	Gravel (Bank Run)	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72								
			08034	Stone (Broken/Crushed)																		
			08035	Gravel (Crushed)											Information	T180	LABT	District Lab	20k	15k	160	72
			08036	Recl. Misc. Agg.																		
			08036X	Recl. Misc. Agg. (OFFSITE)											Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72
02.13	Granular Fill	c.y.	All Materials and Frequencies as listed under 02.12, except Lab (T180) and Field Density (D6938) are not required for this item.																			
02.14	Comp Gran Fill	c.y.	All Materials and Frequencies as listed under 02.12.																			

Chapter 8 - Minimum Schedule for Acceptance Testing

Chapter 8_Acceptance Testing v19.9

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size			
											(E)	(M)	lbs	kg		
02.16	A Pervious Structr Backfill	c.y.	All Materials and Frequencies as listed under 02.12.													
			03014-SP-CLSM	Contolled Low Strength Material	c.y.	YES	Accept (Prod)	D 4832	FLABT	Central Lab	100	76	TBD			
02.19	Sedimentation Control Sys	l.f.	03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff			NA			
			04776	Hay, Baled	ea.	NO	None	NA	Visual	Project Staff			See Note 8.			
03.02	X Rolld Gran Base	c.y.	All Materials and Frequencies as listed under 02.12, except Lab (T180) and Field Density (D6938) are not required for this item.													
03.03	X Concrete Base	c.y.	03015-03540	Concrete-PCC03540	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75(60)/day	4 cyl	4 cyl			
03.04	Processed Aggregate Base	ton	04819	Gravel (Bank Run)	c.y.	YES	Accept (Prod) Information	T27 T180	LABT LABT	District Lab District Lab	5k	3.8k	160	72		
			08034	Stone (Broken/Crushed)							20k	15k	160	72		
			08035	Gravel (Crushed)									160	72		
			08036	Reclaimed Misc. Aggregate									160	72		
			08036X	Recl. Misc. Agg. (OFFSITE)							2.5k	1.9k	160	72		
03.05	Processed Agg	ton	Use of Stone (Broken.Crushed) with requirements as listed under 03.04.													
04.01	Concrete Pavement	c.y.	03015-0354X Concrete-PCC354X		c.y.	YES	Accept (Prod)	T22	LABT	Central Lab	50(40)/day	4 cyl	4 cyl			
			Other materials as listed under 06.01.													
04.06	Bituminous Concrete	ton	04052,3,4	Level 1,2,3 (6.25mm / 0.25 in)	ton	YES	Accept (Prod)	Table M.04.03-3	LABT	Producer	Project quantities ≥ 3500 tons Use Percent Within Limits (PWL). 1 test per 500 tons					
			04056,7,8	Level 1,2,3 (9.5 mm / 0.375 in)							Project quantities <3500 tons Non-PWL See Table M.04.03-2 of Specification.					
			04064,5,6	Level 1,2,3 (12.5 mm / 0.5 in)							See Section 4.06.03-10 of Specification.					
			04076,7,8	Level 1,2,3 (25.0 mm / 1.0 in)							Project quantities ≥ 3500 tons Use Percent Within Limits (PWL). 1 mat core per 500 tons 1 joint core per 2000 ft. of joint					
04.06	Curb Mix	ton	04003 Curb Mix		ton	YES	One test per every 250 tons of cumulative production. See section M.04.03-2b.									
			Project quantities <3500 tons Simple Average See Table 4.06-4 & 4.06-5 of Specification.													

Chapter 8 - Minimum Schedule for Acceptance Testing

Chapter 8_Acceptance Testing v19.9

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size				
											(E)	(M)	lbs	kg			
04.06	Emulsified Asphalt	gal	04128	RS-1, RS-1H	gal		Accept (Prod)	M140 & M208	LABT	Central Lab	≤1000 gal None	≤1000 gal None					
			04133	SS-1, SS-1H		YES	Total project quantities up to 1000 gallons requires only a Materials Certificate and Certified Test Report from certified source.										
			04146	CSS-1, CSS-1H		YES	Total project quantities >1000 gals also require sample(s) for testing, which must be submitted within 15 days of sampling.										
			04147	CRS-1			>1000 gal 10k	>1000 gal 38kl	>1000 gal 2 qts	>1000 gal 2L							
04.15	Press Rlf Joint	s.y.	See 04.06 for Bituminous Materials and 2.12 for unbound material.														
05.02	X Temp Crossings		00000	None													
5.03	Removal of Super Structure	l.s.	00000	None													
05.04	RR Protection	hr.	00000	None													
05.06	Retaining Walls, and Steps	c.y.	03015-X	Concrete-Class (Various)	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75(60)/day	4 cyl					
			All non-precas materials that may be used for 05.06 items are listed under 05.07 and must be tested at the same frequency.														
05.07	Catch Basins,	ea.	00327	Water	gal	NO	None	NA	Visual	Project Staff			See Note 4.				
05.80	X Manholes & Drop Inlets		01422	Concrete Section, Precast	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	1	1	NA				
			01440A	Catch Basin - Precast (Complete													
			01441A	Manhole - Precast (Complete)													
			03025	Mortar (prebagged)													
			03066	Cement - Portland Type I/II	bag	NO	None	NA	Visual	Project Staff			See Note 9.				
															06552	Lime - Hydrated	
			03200	Concrete Masonry Unit (CMU)	ea.	YES	Accept (Prod)	NA	LABT	Central Lab			See Note 13.				
															03201	Brick (Clay) - RED	
			03209	Manhole Covers / Frame	ea.	YES	Accept (Prod)	NA	MC	Central Lab	1	1	See Note 12.				
															03205	Catch Basin - Grate	
			06566	Lawn Drain Grate													
			04697	Sand (Masonry) - Grading A	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	2.5k	1.9k	25	12			
																	04704
			04819	Gravel (Bank Run)													
08034	Stone (Broken / Crushed)	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72						
														08035	Gravel (Crushed)		
08036	Reclaimed Misc. Aggregate																
08036X	Recl. Misc. Agg. (OFFSITE)						Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72			
05.08	Shear Connectors	ea.	03542	Stud Shear Connector	ea.	YES	Accept (Prod)	AWS D1.5	MCCTR	Central Lab	quantity	1 per size					
05.09	Welded Studs	ea.	03543	Studs - Welded	ea.	YES	Accept (Prod)	AWS D1.5	MCCTR	Central Lab	quantity	1 per size					
05.13	PVC Pipe	l.f.	02649	Pipe - PVC & Fittings & Acc.	l.f.	NO	None	NA	Visual	Project Staff			See Note 8.				
05.14	Prestressd Conc	l.f.	03040,16	Grout	See requirements for material #03040 or #03016 under item 06.01												
	Members		03050	Concrete Members, Prestressed	l.f.	YES	Accept (Prod)	NA	Visual	Lab & Project			See Note 2.				

Chapter 8 - Minimum Schedule for Acceptance Testing

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size	
											(E)	(M)	lbs	kg
05.20	X Exp Jnt System	c.f.	07067	Exp. Joint System	l.f.	NO	None	NA	MC	Project Staff				
	A Asp Plug Jnt		08010-SP	Exp. Jt. - Asphalt Plug-Spec Pro	c.f.	YES	See Special Pro for Testing Requirements (MAT 100 for stone only)							
05.21	Elastomeric Bearing Pads	c.i.	03040,16	Grout	See requirements for material #03040 or #03016 under item 06.01									
			03505-L	Bearing Pads (Laminated)	ea.	YES	Accept (Prod)	NA	MCCTR	Central Lab	See Note 3.	See Note 3.		
			03505-P	Bearing Pads (Plain)	ea.									
05.22	Elastomeric Comp. Seal	l.f.	03432	Joint Seal, Elastomeric Comp	l.f.	None	NA	MC	Project Staff				NA	
			03040,16	Grout	See requirements for material #03040 or #03016 under item 06.01									
06.01	Concrete for Structures	c.y.	00804	Box Culvert, Precast Concrete	ea.	YES	Accept (Prod)	NA	Visual	Lab & Project				See Note 2.
			01422	Concrete Section, Precast										
			03015-X	Concrete-PCCXXXXX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75(60)/day	4 cyl		
			03014-SP_K	Concrete Special Provision										
			03040	Grout, Non-shrink	bag	NO	None	NA	Visual	Project Staff			See Note 9.	
			03016	Grout (Batched)	c.y.	YES	Accept (Prod)	T106	FLABT	Central Lab				
			04177	Joint Sealer, Concrete Structure	lb.	NO	None	NA	MC	Project Staff			NA	
			03158	Preformed Expansion Joint Filler	ea.									
03444	Closed Cell Elastomer	l.f.	NO	None	NA	MC	Project Staff			NA				
Note: All steel reinforcement under 06.01 will be tested as described in 06.02.														
06.02	Reinforcing	lb.	02995	Dowel Splice System, Epoxy Ctd	ea.	YES	Accept (Prod)	T244	LMCT	Central Lab	quantity			1
			02997	Dowel Splice System										
			02998	Deformed Steel Bars, Epoxy Ctd	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	1.5m
			03040, 16	Grout	See requirements for material #03040 or #03016 under item 06.01									
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	1.5m
			03105	Chemical Anchor	lb.	NO	None	NA	QPL/MC	Project Staff				NA
			03138	Dowels, Steel	ea.	YES	Accept (Prod)	T244	LMCT	Central Lab	quantity			NA
			03145	Fabric, Wire and Welded Steel	s.y.	YES	Accept (Prod)	T244	LMCT	Central Lab	60k ft ²	6k m ²	1yd ²	1 m ²
06.03	Structural Steel	cwt.	00031	Paint - Prime Coat for Struct. Stl	gal	NO	None	NEPCOAT	MC	Project Staff	quantity			NA
			00032	Paint - Interm. Coat for Struct Stl										
			00033	Paint - Top Coat for Struct Stl										
			03537	Steel, Structural	cwt.	YES	Accept (Prod)	NA	Visual	Lab & Project			See Note 2.	
			01839	Bolt/Nut/Washer	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	quantity			
			08022	Bolt/Nut/Washer, High strength	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	quantity			
			03542	Stud Shear Connectors	See item 5.08.									
			03040, 16	Grout	See requirements for material #03040 or #03016 under item 06.01									
06.05	Masonry Facing	s.y.	04771	Stone, Masonry	tons	NO	None	NA	Visual	Project Staff				NA
			03138	Dowels, Steel	lb.	YES	Accept (Prod)	NA	LMCT	Central Lab	quantity			NA
			Note: Mortar components to be tested as described in 05.07.											

Chapter 8 - Minimum Schedule for Acceptance Testing

Chapter 8_Acceptance Testing v19.9

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size			
											(E)	(M)	lbs	kg		
06.06	Cement Rubble Masonry	c.y.	4771	Stone, Masonry	c.y.	NO	None	NA	Visual	Project Staff			NA			
			Note: Mortar components to be tested as described in 05.07.													
06.07	Dry Rubble Masonry	c.y.	4771	Stone, Masonry	c.y.	NO	None	NA	Visual	Project Staff			NA			
06.09	Repointed Masonry	s.y.	Note: All materials under 06.09 will be tested as described in 05.07.													
06.11	Shotcrete	c.y.	Note: All materials under 06.11 will be tested as described in 06.01.													
06.12	Curing Box	ea.	00000	None	ea.	NO	None	NA	Catalog Cut	Project Staff			See Note 8.			
06.51	Culverts/Pipe	l.f.	00327	Water	gal	NO	None	NA	Visual	Project Staff			See Note 4.			
			00699	Pipe - R.C. & Fittings & Acc.	l.f.	YES	Accept (Prod)	NA	PC1	Central Lab	size		See Note 7.			
			various	Pipe (Metal) All types	l.f.	YES	Accept (Prod)	NA	MC	District Lab	quantity		See Note 8.			
			01783	Pipe -Alum & Fitting & Acc.	l.f.	YES	None	NA	MC	Project Staff						
			03066	Cement - Portland Type I/II	bag	NO	None	NA	Visual	Project Staff			See Note 9.			
			03040	Grout, Non-shrink	See requirements for material #03040 under item 06.01											
			03016	Grout (Batched)	c.y.	YES	Accept (Prod)	T106	FLABT	Central Lab						
			04704	Sand (Masonry) - Grading B	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	2.5k	1.9k	25	12		
			04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff			See Note 8.			
			04819	Gravel (Bank Run)	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72		
			08034	Stone (Broken / Crushed)												
			08035	Gravel (Crushed)												
			08036	Reclaimed Misc. Aggregate												
08036X	Recl. Misc. Agg. (OFFSITE)	c.y.	YES	Accept (Prod)	Chem(Offsite)	MCCTR	District Lab	2.5k	1.9k	160	72					
06.52	Culvert Ends	ea.	00823	Culvert End - Reinforced Conc	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	quantity		NA			
			Note: All non-precast materials that may be used for 06.52 items are listed under 06.51 and must be tested at the same frequency.													
06.53	Clean Drng Sys	ea.	00000	None		NO										
07.01	Drilled Shafts	l.f.	0306X	Cement (Type)		NO	None	NA	Visual	Project Staff			See Note 9.			
			03100	Deformed Steel, Reinforcing		YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	1.5m		
			03016	Grout (Batched)		YES	Accept (Prod)	T106	FLABT	Central Lab						
			03532	Pipe, Steel Shell		YES	Accept (Prod)	NA	MC	Central Lab	quantity		NA			
			02724	Pipe, Steel & Fit & Acc.		YES	Accept (Prod)	NA	MC	Central Lab	quantity		NA			
			02600	Pipe, Polyethylene & Fit & Acc.		NO	None	NA	Visual	Project Staff			See Note 8.			
07.02	Piles	lb.	03040	Grout, Non-shrink	See requirements for material #03040 under item 06.01											
			03549	H-Piles, Steel	ton	YES	Accept (Prod)	NA	MCCTR	Central Lab	See Note 1.		See Note 1.			
			3559	Pile Point, Steel	ea.	YES	Accept (Prod)	NA	MCCTR	Central Lab	quantity		NA			

Chapter 8 - Minimum Schedule for Acceptance Testing

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size		
											(E)	(M)	lbs	kg	
07.03	Riprap (all types)	c.y.	04819	Gravel (Bank Run)	c.y.	NO	None	NA	Visual	Project Staff			See Note 8.		
			08034	Stone (Broken/Crushed)											
			08035	Gravel (Crushed)											
07.04	Gabions	c.y.	03546	Gabions	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quantity	NA			
07.05	Slope Paving	s.y.	08031	To Be Determined.											
07.06	Micropiles	ea.	See materials listed under 07.01												
07.07	Membrane Waterproofing (Woven Glass)	s.y.	04199	Membrane Waterproofing	s.y.	NO	None	NA	MC	Project Staff	quantity				
07.08	Dampproofing	s.y.	04207	Dampproofing Primer	gal	NO	None	NA	MC	Project Staff	quantity				
			04208	Dampproofing Sealer											
07.11	X Conc Crib Wall		08031	To Be Determined.											
07.13	Permanent Steel Sheet Piling	s.f.	03535	Piling, Steel Sheet	l.f.	YES	Accept (Prod)	NA	MCCTR	Central Lab	quantity	NA			
07.14	Temp Steel Sheet Piling														
07.15	Sht Piling Left														
07.17	Earth Ret Syst	s.f.	07627	Reinforced Earth Wall	ea.	YES	Accept(Prod)	NA	MC	Lab and Project	quantity	See Note 8.			
07.28	Crushed Stone for Slope Protection	ton	08034	Stone (Broken/Crushed)	c.y.	NO	None	NA	Visual	Project Staff		See Note 8.			
			08035	Gravel (Crushed)											
07.32	Conc. Block Slope Prot.	s.y.	03200	Concrete Masonry Unit (CMU)	See requirements for material #03200 under item 05.07.										
		lb	03025	Mortar	See requirements for material #03025 under item 05.07.										
07.51	Underdrain and Outlets	l.f.	01708	Pipe - For Underdrain or Outlet	See requirements for Pipe, Metal (All types) under item 06.51.										
			03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff		NA			
			04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff		NA			
			02649	Pipe - PVC & Fittings & Acc.	l.f.	NO	None	NA	Visual	Project Staff		See Note 8.			
07.55	Geotextile	s.y.	03985	Geotextile	s.y.	NO	None	NA	QPL/MC	Project Staff		NA			
08.03	Paved Ditches and Channels	s.y.	04003	Curb Mix	See requirements under 04.06.										
			04819	Gravel (Bank Run)	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72	
			08034	Stone (Broken/Crushed)											
			08035	Gravel (Crushed)											
			08036	Reclaimed Misc. Aggregate											
08036X	Recl. Misc. Agg. (OFFSITE)	Accept (Prod)	Chem(Offsite ONLY)	MCCTR											District Lab
08.11	Concrete Curbing	l.f.	01511	Curb, Precast	l.f.	YES	Accept (Prod)	NA	PCI	Central Lab	quantity	NA			
			03015-03X	Concrete PCC03XXX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75	60	4 cyl	4 cyl	
			03155	Expansion Joint filler	l.f.	NO	None	NA	MC	Project Staff			NA		
			03158	Preformed Expansion Joint Filler	s.f.										

Chapter 8 - Minimum Schedule for Acceptance Testing

Chapter 8_Acceptance Testing v19.9

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size	
											(E)	(M)	lbs	kg
08.13	Stone Curbing	l.f.	04909	Curbing, Granite Stone	l.f.	NO	None	NA	Visual	Project Staff			NA	
08.14	Reset Stone Curbing	l.f.	00000	None		NO	None							
08.15	Bit. Conc. Lip Curbing	l.f.	04003	Curb Mix	See requirements under 04.06.									
		gal	04128,47	RS-1 or RS-1H	See requirements under 04.06.									
08.16	X Granite Slope Curbing	l.f.	04910	Curbing, Granite Slope	l.f.	NO	None	NA	Visual	Project Staff			NA	
08.18	Prtctve Cmpnd for Bridges	s.y.	00328	Protective Coating	gal	NO	None	NA	QPL/MC	Project Staff			NA	
08.21	Precast Concrete Barrier Curb	l.f.	00895	Concrete Barrier, Precast	l.f.	YES	Accept(Prod)	NA	PC1	Central Lab	size		See Note 7.	
			03015-04X	Concrete-PCC04XXX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 60	4 cyl	4 cyl	
08.22	Temp Precast Conc. Barrier	l.f.	00865	Concrete Barrier, Precast, Temp	l.f.	NO	None							
09.01	A Bollard	ea.	07351	Bollard, Steel	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quantity		NA	
09.04	Metal Br Rail	l.f.	03429	Metal Bridge Rail System	l.f.	YES	Accept(Prod)	NA	MC	Lab and Project	quantity		See Note 2.	
09.05	Stone Wall Fence	l.f.	00000	None		NO	None							
09.06	Wire Fence	l.f.	03326	Fence - Wire, Posts & Hardware	l.f.	YES	Accept(Prod)	TBD	MC	Central Lab	quantity		NA	
09.10	Metal Beam Rail	l.f.	03406	Metal Beam Rail System	l.f.	YES	Accept (Prod)	NA	MC	Central Lab	quantity		NA	
09.11	Metal Beam Rail Anchorages	ea.	01435	Anchor, (Precast)	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	quantity		NA	
			03405	Metal Beam Rail, Anchorages for	ea.	YES	Accept (Prod)	NA	Visual	Lab and Project	quantity		See Note 2.	
			03015-033X	Concrete PCC033XX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 60	4 cyl	4 cyl	
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t 180t	5ft	1.5m	
09.12	Remove and Reset Posts, ...	l.f.	08031	To Be Determined.		TBD								
09.13	Chain Lnk Fence	l.f.	03309	Fence, Chain Link	l.f.		Accept(Prod)	NA	MC	Central Lab	quantity		3 lf	1m
			03310	Fence, Chain Link, Post for	ea.	YES			LABT				1	1
			03320	Fence, Hardware & Acc. (Chain Link)	ea.								1	1
09.14	Metal Handrail	l.f.	03414	Metal Handrail	l.f.	YES	Accept(Prod)	NA	MC	Lab and Project	quantity		See Note 2.	
09.16	Noise Bar Wall	s.f.	07822	Noise Barrier Wall	s.f.	YES	Accept (Prod)	NA	MC	Central Lab	quantity		NA	
09.18	Three-Cable Guide Railing (I_Beam Posts) & Anchorages	ea.	03015-033X	Concrete PCC033XX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 60	4 cyl	4 cyl	
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t 180t	5ft	1.5m	
			03419	Cable Guide Rail	l.f.		Accept (Prod)	NA	MC	Central Lab	quantity		NA	
			03421	Cable Guide Railing Anchorage	ea.	YES								

Chapter 8 - Minimum Schedule for Acceptance Testing

Chapter 8_Acceptance Testing v19.9

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size			
											(E)	(M)	lbs	kg		
09.21	Concrete Sidewalks	s.f.	01467	Slab, Precast	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	quantity		NA			
			02998	Deformed Steel Bars, Epoxy Ctd	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	1.5m		
			03015-044X	Concrete-PCC044XX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75	60	See Note 14.			
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	1.5m		
			03145	Fabric, Wire & Welded Steel	s.y.	YES	Accept (Prod)	T244	LABT	Central Lab	60k ft ²	6k m ²	1yd ²	1 m ²		
			03158	Preformed Expansion Joint Filler	s.f.	NO	None	NA	MC	Project Staff			See Note 1.			
			04819	Gravel (Bank Run)	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72		
			08034	Stone (Broken/Crushed)												
			08035	Gravel (Crushed)												
			08036	Reclaimed Misc. Aggregate												
08036X	Recl. Misc. Agg. (OFFSITE)			Accept (Prod)	Chem (Offsite ONLY)	MCCTR	District Lab	2.5k	1.9k	160	72					
08060	Detectable Warning Strip	ea.	NO	None	NA	QPL/MC	Project Staff	quantity								
09.22	Bituminous Concrete Driveway	s.y.	0405X	HMA S 0.375	ton	YES	Accept(Prod)	TBD	FLDT	Project Staff	day	day	NA			
			04819	Gravel (Bank Run)	c.y.	YES	Accept (Prod)	T27	LABT	District Lab	5k	3.8k	160	72		
			08035	Gravel (Crushed)												
			08036	Reclaimed Misc. Aggregate												
			08036X	Recl. Misc. Agg. (OFFSITE)											Accept (Prod)	Chem (Offsite ONLY)
09.24	Concrete Ramp/Driveway	c.y.	See materials listed under 06.01 and 06.02.													
09.25	Pvmnt for Railing		04003	Curb Mix	See requirements under 04.06.											
09.30	Object Marker	ea.	03943	Object Marker	ea.	NO	None	NA	QPL/MC	Project Staff	quantity					
			03952	Sign Post	ea.	YES	Accept(Prod)	TBD	MC	Central Lab	quantity		See Note 1.			
09.39	Sweeping for Dust Control	hr.	00000	None		NO	None									
09.41	X Service Bridges	ea.	08031	To Be Determined.												
09.42	Calc Chloride Dust Control	ton	00302	Calcium Chloride	gal	NO	None	NA	Visual	Project Staff			NA			
09.44	Topsoil	s.y.	00542X	Topsoil (from offsite)	c.y.	YES	Accept (Prod)	NA	MCCTR	Central Lab	1k	765	NA			
			00542	Topsoil (from project)	c.y.	NO	None	NA	Visual	Project Staff						
09.45	X Wildflowers	lb.	00000	None		ALT	None	Landscape Design Unit Approval								See Note 11.
09.46	Liming	ton	00533	Lime	lb.	NO	None	NA	Visual	Project Staff			NA			

Chapter 8 - Minimum Schedule for Acceptance Testing

Chapter 8_Acceptance Testing v19.9

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size			
											(E)	(M)	lbs	kg		
09.47	Bus Shelter	ea.	08031	To Be Determined.		TBD										
09.49	Planting and Mulching Trees, Shrubs Vines and Groundcover Plants	ea.	00327P	Water (plantings)	gal	NO	None	NA	Visual	Project Staff			NA			
			00510	Peat	c.y.	NO	None	NA	Visual	Project Staff			NA			
			00533	Lime	ton	NO	None	NA	Visual	Project Staff			NA			
			00496	Fertilizer	lb.	NO	None	NA	MC	Project Staff			See Note 10.			
			00536	Plant Materials		ALT	None			Landscape Design Unit Approval				See Note 11.		
			00542P	Topsoil - plantings (no turf estab)	c.y.	YES	Accept (Prod)	NA	MCCTR	Central Lab	1k	765			NA	
			07547	Tree		ALT	None			Landscape Design Unit Approval				See Note 11.		
09.50	Turf Establishment Erosion Control	s.y.	00327P	Water (plantings)	gal	NO	None	NA	Visual	Project Staff			NA			
			00496	Fertilizer	lb.	NO	None	NA	MC	Project Staff			See Note 10.			
			00497	Seed	lb.	NO	None	NA	MC	Project Staff			See Note 10.			
			00533	Lime	lb.	NO	None	NA	Visual	Project Staff			NA			
			00534	Mulch - All Types	lb.	NO	None	NA	Visual	Project Staff			NA			
			00542	Topsoil (from project)	c.y.	NO	None	NA	Visual	Project Staff			NA			
			00542X	Topsoil (from offsite)	c.y.	YES	Accept (Prod)	NA	MCCTR	Central Lab	1k	765			NA	
09.53	Sodding	s.y.	3985	Geotextiles	s.y.	NO	None	NA	QPL/MC	Project Staff			NA			
			00518	Sod	s.y.	NO	None	NA	MC	Project Staff			See Note 11.			
				Other materials as listed in 09.50.												
09.76	Barricade Warning Lights	day	03603	Warning Lights	ea.	NO	None	NA	Visual	Project Staff			NA			
09.77	Traffic Cone	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA			
			03948	Traffic Cones	ea.	NO	None	NA	Visual	Project Staff			NA			
09.78	Traffic Drum	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA			
			03927	Traffic Drums	ea.	NO	None	NA	Visual	Project Staff			NA			
09.79	Construction Barricades	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA			
			03974	Construction Barricade	ea.	NO	None	NA	MC	Project Staff						
09.81	42 in. Traffic Cone	ea.	03934	Reflective Sheeting	s.f.	NO	None	NA	QPL/MC	Project Staff			NA			
			03948	Traffic Cones	ea.	NO	None	NA	Visual	Project Staff						
10.01	Trenching and Backfilling	l.f.	04901	Bedding Material	c.y.	NO	None	NA	Visual	Project Staff			See Note 8.			
				Other materials as listed elsewhere.												
10.02	Light Standards and Traffic Control Foundations	ea.	01432	Foundation (Precast)	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	size		See Note 7.			
			03015-033X	Concrete PCC033XX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75 60	4 cyl	4 cyl			
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t 180t	5ft	1.5m			
			03504	Anchor Bolts	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	quantity		1 per size			
			03711	Ground Rod	ea.	NO	None	NA	Visual	Project Staff			NA			
10.03	Light Standards	ea.	03704	Light Standard	ea.	YES	Accept (Prod)	TBD	MC	Central Lab	quantity		See Note 6.			

Chapter 8 - Minimum Schedule for Acceptance Testing

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size	
											(E)	(M)	lbs	kg
10.04	Roadway Luminaire	ea.	07645	Luminaire	ea.	NO	Catalog Cut - Designer							
10.06	Underbridge Luminaire	ea.	07645	Luminaire	ea.	NO								
10.08	Elec. Conduit	l.f.	03693	Conduit & Fittings (all types)	l.f.	NO	No Request for Test - Catalog Cut - Designer							
10.09	Cast Iron Junction Box	ea.	03724	Junction Box & Cover	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quantity	NA		
10.10	Conc Handhole	ea.	01462	Handhole & Cover, Precast	ea.	YES	Accept (Prod)	NA	PC1	Central Lab	size	See Note 7.		
10.11	4" Drain Pipe	l.f.	01708	Pipe - For Underdrain or Outlets	l.f.	NO	Catalog Cut - Designer							
10.12	Single Conductor	l.f.	08031	To Be Determined.		TBD								
10.14	Cable In Duct	l.f.	08031	To Be Determined.		TBD								
10.15	Grounding Conductor	l.f.	03709	Ground Wire	l.f.	NO	None	NA	Visual	Project Staff		NA		
			03711	Ground Rod	ea.	NO	None	NA	Visual	Project Staff		NA		
10.17	Service Entrance & Cabinet	ea.	00000	None		NO	Catalog Cut		Designer of Record					
10.18	Navigation Light	ea.	08031	To Be Determined.		TBD	Catalog Cut - Designer							
11.01	Pole Anchor	ea.	08031	To Be Determined.		TBD								
11.02	Pedestals	ea.	03801	Pedestals, Aluminum	ea.	NO	None	NA	Visual	Project Staff		NA		
11.03	Span Pole	ea.	03802	Span Pole - Steel	ea.	YES	Accept(Prod)	NA	MC	Central Lab	quantity	See Note 2 & 6.		
11.04	X Mast Arm		03806	Mast Arm Assembly	ea.	YES	Accept(Prod)	NA	MC	Central Lab	quantity	See Note 2 & 6.		
11.05	Traffic Signals	ea.	03766	Traffic Signal Equipment	ea.	NO	Catalog Cut - Designer							
			03807	Traffic Signal	ea.	NO								
11.06	Pedestrian Signal	ea.	00000	None		NO							Catalog Cut	
11.07	Pedestrian Push Button	ea.	00000											
11.08	Controllers	ea.	00000											
11.10	X Press. Veh. Det.		00000											
11.11	Loop Detector & Sawcut	ea.	00000											
11.12	Mag. Veh. Det.	ea.	00000											
11.13	Control Cable	l.f.	00000											
11.14	A Msngr Spn Wire	l.f.	00000											
11.15	PVC Conduit		00000											
11.16	Illum. Signs	ea.	00000				None		NO	Catalog Cut		Designer of Record		

Chapter 8 - Minimum Schedule for Acceptance Testing

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency 1 per		Sample Size	
											(E)	(M)	lbs	kg
11.17	A Alt. Flsh Sig for Wrngng Sgns	ea.	00000	None		NO	Catalog Cut			Designer of Record				
11.18	Rmvl/ Relo Traff Sig. Equip	l.s.	08031	To Be Determined.		TBD								
11.30	High Mounted Inter Illum. Flashing Arrow	day	00000	None		NO	Catalog Cut			Designer of Record				
11.31	Changeable Message Sign / Remote Controlled Sign	day	03764	Sign (Variable Message)	ea.	NO	None	NA	MC	Project Staff				NA
12.00	Gen. Clauses for Hwy Signing		00000	None		NO								
12.01	Overhead Sign Sup.	ea.	03928	Sign Support, Structural Steel	ea.	YES	Accept(Prod)	NA	MC	Central Lab	quantity			See Note 2 & 6.
12.02	Overhead Sign Support Foundation	ea.	03015-X	Concrete PCC03XXX	c.y.	YES	Accept (Prod)	T22	FLABT	Central Lab	75	60	4 cyl	4 cyl
			03100	Deformed Steel, Reinforcing	lb.	YES	Accept (Prod)	T244	LMCT	Central Lab	200t	180t	5ft	1.5m
			03504	Anchor Bolts	ea.	YES	Accept (Prod)	TBD	LMCT	Central Lab	quantity			1 per size
			03711	Ground Rod	ea.	NO	None	NA	Visual	Project Staff				NA
12.03	Side Mntd Sign Fndtn	ea.	All Materials and Frequencies as listed under 12.02.											
12.04	Sign Panel Overlay	s.f.	00000	None		NO	None	NA	Visual	Project Staff				NA
12.05	Delineators	ea.	03933	Delineator	ea.	NO	None	NA	QPL/MC	Project Staff				NA
			03952	Sign Post	ea.	YES	Accept(Prod)	TBD	MC	Central Lab	quantity			See Note 1.
12.07	Sign Face - Extrdd Alum.	s.f.	03938	Sign Face, Sheet Aluminum	s.f.	NO	None	NA	QPL/MC	Project Staff				NA
12.08	Sign Face - Sheet Alum.	s.f.	03938	Sign Face, Sheet Aluminum	s.f.	NO	None	NA	QPL/MC	Project Staff				NA
		ea.	03952	Sign Post	ea.	YES	Accept (Prod)	NA	MC	Central Lab	quantity			See Note 1.
12.09	Painted Pvmnt Markings	l.f.	00060	Paint Wtrbrn Pvmnt Mrk (3 min)	gal	NO	None	NA	MC	Project Staff				See Note 5.
		lb.	00306	Glass Spheres	lb.	NO	None	NA	MC	Project Staff				
12.10	Epoxy Pvmnt, Symb and Lgnds	l.f.	00091	Paint - Epoxy Pvmnt Markings	gal	NO	None	NA	MC	Project Staff				See Note 5.
		s.f.	00306	Glass Spheres	lb.	NO	None	NA	MC	Project Staff				
12.11	Removal of Pvmnt Markings	s.f.	00000	None		NO	None							
12.12	Temp Pvmnt Mrkng Tape	l.f.	00000	None		NO	None							

Chapter 8 - Minimum Schedule for Acceptance Testing

Item	Title	Unit	Material #	Material Name	Material Unit	MAT 100	Sample Type	Test Method	Test Type	Test Responsibility	Frequency		Sample Size	
											(E)	(M)	lbs	kg
12.14	Black Mrkng Tape	l.f.	00206	Preformed Black Marking Tape	l.f.	NO	None	NA	MC	Project Staff			NA	
12.15	X Tublr Sign Sup.	ea.	See 06.03 Structural Steel requirements.											
12.16	X Black Epoxy Resin Pvmnt Mrkings Symls and Lgnds	l.f.	00091	Paint - Epoxy Pvmnt Markings	gal	NO	None	NA	MC	Project Staff			See Note 5.	
		s.f.	00091	Paint - Epoxy Pvmnt Markings										
12.20	Constr. Signs - Encap. Lens Refl Sheeting	s.f.	03945	Construction Signing	s.f.	NO	None	NA	QPL/MC	Project Staff			NA	
13.00	X Utilities		Utilities Special Provisions			NO	None							
18.01	X Repair Impact Att Sys.		08031	To Be Determined.		TBD								
18.02	Sand Barrels	ea.	04915	Sand (Inertial Barriers)	lbs	NO	None	NA	Visual	Project Staff			See Note 8.	
18.03	Imp Att Sys.	ea.	03970	Impact Attenuator	ea.	NO	None	NA	QPL/MC	Project Staff	quantity		NA	
18.06	Truck Mntd Imp Att Sys.	hr.	03970	Impact Attenuator	ea.	NO	None	NA	MC	Project Staff	quantity		NA	
18.07	Temp Impact Atten Sys.	ea.	00298	Sodium Chloride, Interial Barriers	lb.	NO	None	NA	MC	Project Staff			NA	
			03970	Impact Attenuator	ea.	NO	None	NA	QPL/MC	Project Staff	quantity		NA	
			4700	Sand	c.y.	NO	None	NA	MC	Project Staff			NA	

General Note: Materials used within an item not referenced in the table must be tested as specified in the special provision for that item, or as they would be typically tested with other items. Should neither provide direction, contact the Division of Materials Testing for assistance.

Notes

- 1 Sample may be required depending on source of material. DMT personnel will request sample from project if needed.
- 2 Notify Division of Materials Testing prior to fabrication to schedule plant inspection. Submit Request for Test after items are inspected by project staff upon delivery.
- 3 Submit one test pad per 50 of the same type or portions thereof. If there are less than 50 pads total and more than one type, submit the type with the greatest quantity.
- 4 DO NOT submit a Request for Test unless the water is non-potable. Water may be tested if drawn from a suspect source. (1qt/1 lt sample if needed - 1 per project)
- 5 Confirm Batch # on MC matches information on Project Wise. **CTDOT/Documents\04.1 – Construction Libraries\04.400 – Offices\04.406 - Materials Testing\Pavement Marking Materials**
- 6 Material Certificate must indicate conformance for entire assembly including, but not limited to, base, shaft, bracket arm, galvanized coating and deflection testing (if required).
- 7 Mat-100 can contain multiple sizes, each size on the project must be documented with a MAT-100. Total project quantity per size does not require testing.
- 8 If assistance is needed, notify District Laboratory to schedule a field inspection.
- 9 Project staff should verify bags used are labeled as meeting ASTM C150; mortar must meet C1714 or C387; Lime must meet C207; Grout must meet C1107.
- 10 Material Certificate may be substituted for affidavit.
- 11 Send request for inspection to Landscape Design Unit, Newington Room 3401 NWA (860) 594-3336
- 12 PCI for item will cover frames and grates if incorporated into precast items. Material Certification applies when material is not integral with a precast item.
- 13 Delivery Ticket clearly listing the manufacturer of the bricks and blocks is required. Unfamiliar sources should not be used, contact DMT for confirmation.
- 14 Represented quantity can be adjusted based on field testing results. Contact DMT for direction.

Legend															
Item: Standard Specification Section and the first four digits of the Contract Item number. Column also includes section headings															
Title: Generally the overall subject of the Standard Specification Section and the Contract Item numbers.															
Material Code: Code used in SiteManager and by the Division of Materials Testing to identify component materials used in Contract Items															
Material Name: Definition of the Material #															
Test Type: Describes where the test is performed															
Sample Resp: Who performs the sampling															
Frequency: Number of tests required per quantity of material using the sample units.															
Sample Units: Units of the amount of material represented by a single sample or test.															
Sample Size: Size of Sample															
Item	Title	Material Code(s)	Material Name	Test Type	Sample Resp.	Freq. 1 per	Freq Units	Sample Size							
Earthwork															
02.02	Roadway Excavation, Formation of Embankment and Disposal of Surplus Material	08037 08037X 08039	Recl. Waste Recl. Waste (OFFSITE) Embankment Material	Field	Central Lab	50000	c.y.	na							
	02.03	Structure Excavation	08037 08037X 08039						Recl. Waste Recl. Waste (OFFSITE) Embankment Material	Field	Central Lab	50000	c.y.	na	
			04902						Borrow						Field
02.12			Subbase	04819 08034 08035 08036 08036X	Gravel (Bank Run) Stone (Broken/Crushed) Gravel (Crushed) Recl. Misc. Agg. Recl. Misc. Agg. (OFFSITE)	Laboratory	District Lab Central Lab	50000 30000	c.y. c.y.						80 lbs na
	08036X	Recl. Misc. Agg. (OFFSITE)		Field Density	Central Lab					50000	c.y.	na			
	03.03	Concrete Base		03015-XXXXX	Concrete-Class PCCXXXYZ					Field	Project Personnel	2500	c.y.	na	
	03.04	Processed Aggregate Base		04819 08034 08035 08036 08036X	Gravel (Bank Run) Stone (Broken/Crushed) Gravel (Crushed) Recl. Misc. Agg. Recl. Misc. Agg. (OFFSITE)					Laboratory	District Lab Central Lab	30000 30000	c.y. c.y.	80 lbs na	
				03.05	Processed Aggregate	04819 08034 08035 08036 08036X	Gravel (Bank Run) Stone (Broken/Crushed) Gravel (Crushed) Recl. Misc. Agg. Recl. Misc. Agg. (OFFSITE)	Laboratory	District Lab Central Lab						30000 30000

Item	Title	Material Code(s)	Material Name	Test Type	Sample Resp.	Freq. 1 per	Freq Units	Sample Size
Surface Courses or Pavements								
04.01	Concrete Pavement	03015-XXXXX	Concrete Class PCCXXXYZ	Field	Project Personnel	2500	c.y.	4 cyl na
04.06	Bituminous Concrete	04003	Curb Mix	Laboratory	Central Lab	3500	tons	15 kg
		040XX	HMA, Level 1,2,3 (6.25 mm / 0.25 in), (9.5 mm / 0.375 in), (12.5 mm / 0.5 in), (25.0 mm / 1.0 in)					
		040XX	HMA, Level 1,2,3 (6.25 mm / 0.25 in), (9.5 mm / 0.375 in), (12.5 mm / 0.5 in), (25.0 mm / 1.0 in)					
						40	core	1 core
Structures								
05.06	Retaining Walls, Endwalls and Steps	03015-XXXXX	Concrete-Class PCCXXXYZ	Field	Project Personnel	2500	c.y.	na
06.01	Concrete for Structures	03015-XXXXX	Concrete Class PCCXXXYZ	Field	Project Personnel	2500	c.y.	na

Appendix A - Forms

Form	Name	Spec
MAT-100	Request for Test	
MAT-103	Report of Rejected Material	
MAT-104	Report of Test of Miscellaneous Material	
MAT-106	DMT Contact List	
MAT-107	Quality Assurance – Notable Observation	
MAT-108	Daily Work Report	
MAT-108HMA	Daily Work Report (Hot Mix Asphalt)	
MAT-108PCC	Daily Work Report (Precast Concrete)	
MAT-109	Core Sample Documentation	
MAT-110	Welding Operator Qualification Record	
MAT-111	Welding Certification Application	
MAT-112	Welding Call In Report	
MAT-200	Report of Test of Metal Pipe (Steel)	
MAT-202	Report of Test of Perforated Metal Pipe	
MAT-203	Report of Test of Structural Plate and Pipe Arches	
MAT-204	Report of Test of Culvert End	
MAT-205	Report of Tests of Bank Run Gravels or Processed Aggregate	
MAT-206	Report of Test of Sand	
MAT-207	Report of Test of Coarse Aggregate	
MAT-208	Report of Test of Rock Salt	
MAT-209	Report of Test of Calcium Chloride	
MAT-211	Report of Test of L.A. Abrasion	
MAT-212	Acceptance Criteria for Use of Reclaimed Material	
MAT-213	Report of Test of Moisture/Density (Proctor)	
MAT-217	Worksheet: Moisture Density (Proctor) 6” mold	
MAT-218	Worksheet: Moisture Density (Proctor) 4” mold	
MAT-219	Worksheet for Specific Gravity and Absorption of Coarse Aggregate	
MAT-220	Worksheet for Soundness of Fine Aggregate - AASHTO T-104	
MAT-221	Worksheet for Soundness of Coarse Aggregate- AASHTO T-104	
MAT-222	Assurance Report: Material Testing Personnel and equipment in the field.	
MAT-224	Assurance Report: Plastic PC Concrete	
MAT-225	Assurance Report: Plastic PC Concrete (Metric)	
MAT-228	Report of Test: Glass Beads	
MAT-229	Report of Test: Visi Beads	
MAT-235	Report of Test: Paint-Solvent White & Yellow Pav. Mark (FastDry)	
MAT-236	Report of Test: Paint-Solvent White & Yellow Pav. Mark (Reg.Dry)	
MAT-239	Report of Test: Paint - Waterborne White & Yellow Paint (Fast Dry)	
MAT-240	Report of Test: Paint - Waterborne White & Yellow Paint (Reg. Dry)	
MAT-241	Independent Assurance Report: Concrete Fine Aggregates	
MAT-242	Independent Assurance Report: Concrete Coarse Aggregate	
MAT-243	Independent Assurance Report: Subbase & Processed Agg Base	
MAT-244	Independent Assurance Report: Plastic PC Concrete	

MAT-245	Report of Test – Aggregate Variation Limits	
MAT-246	Tracking Report: Asphaltic Plug Joint	
MAT-248	Tracking Report: Pavement Marking Materials	
MAT-300	Report of Test: Anchor Bolts (Straight)	
MAT-301	Report of Test: Anchor Bolts (w/Hook)	
MAT-302	Report of Test: Hex Bolt	
MAT-303	Report of Test: Chain Link Fence Fabric	4.58
MAT-304	Report of Test: Reinforced Concrete Pipe	
MAT-305	Report of Test: Steel Bars and Shapes	
MAT-306	Report of Test: Steel Fabric Reinforcement	
MAT-307	Report of Test: General Tensile Strength	
MAT-308	Report for Test on Cylinders	
MAT-308A	Report of Test on Cylinder Diameter	
MAT-309	Report of Test: Masonry Concrete Units	4.48
MAT-310	Report of Test: Elastomeric Bearing Pad	
MAT-312	Report of Test: Clay Brick	4.48
MAT-313	Report of Test: Concrete Block for Slope Protection	
MAT-314	Certification of Precast Concrete Prod.	
MAT-316	Report of Test: Portland Cement (All Types)	
MAT-323	Report of Test: Steel Strand	4.25
MAT-324	Field Report : Yearly inspection for certification of prestress/precast concrete and pipe manufacturers	
MAT-325	Report of Test: Chain Link Fence Hardware	
MAT-326	Report of Test: Chain Link Fence Tension Wire	
MAT-327	Report of Test: H-Piles and Wide Flange Shapes	
MAT-328	Report of Test: Deformed Steel Wire for Concrete Reinforcement	
MAT-329	Certification of Brand Registry	
MAT-330	Guideline: Visual Inspection of Reinforcing Steel	
MAT-401	Report of Test: Asphalt Binder	
MAT-402	Report of Test: Emulsified Asphalts	
MAT-404	Field Report: Bituminous Concrete Plant Inspection	
MAT-406	Field Report: Inspection of HMA Field Laboratory	
MAT-407	Field Report: Plant and Laboratory Deficiency Report	
MAT-408	Field Report: QA Verification Form	
MAT-412cm	Report of Test: Bituminous Curb Mix Quality	
MAT412S	Report of Test: Bituminous SuperPave Quality (2 sided)	
MAT-412s-ppt	Report of Test: Bituminous SuperPave Quality (Pre-Production Trial)	
MAT-412ut	Report of Test: Bituminous Ultrathin Quality	
MAT-417	Worksheet: Random Lot Selection at Plant	
MAT-418	Worksheet: Job Mix Formula Verification	
MAT-419	Template: Quality Control Plan for Fine Aggregate. used in HMA.	
MAT-429cm	Template: Job Mix Formula (curb mix)	
MAT-429s	Template: Job Mix Formula (SuperPave)	

MAT-429ut	Template: Job Mix Formula (Ultrathin)	
MAT-433	Worksheet: Ignition Oven Correction	
MAT-438NonPWL	Worksheet: Daily Plant Adjustment (Non-PWL Lots)	
MAT-438PWL	Worksheet: Daily Plant Adjustment (PWL Lots)	
MAT-440	Field Report: Producer Facility Mix Design Status	
MAT-600	Report of Witness Test – HMA Independent Assurance	

State of Connecticut
Department of Transportation
Material Test Report

SAMPLE ID	
REVISED SAMPLE ID	
Material Code	
Material Description	
Sample Date	
Sampled By	
Source of Supply	
Producer/Supplier Code	
Material Rep Qty	
Sample Unit	
Sample Test Type	
Acceptance Method Type	
Control Type	
Control Number	
Sample Taken From	
Purpose/Intended Use	
Location of Sample	
Plant ID / TYPE	/
Plant Name	
Contract Number	
District Number	
Federal Aid Number	
Field Office Phone Number	
Sample Status	
Date of Assigned Status	
Creator User ID	

REMARKS

Project Number	LIN	Item Code	CAT	Item Description	Material Rep Qty
Total Material Represented Quantity:					

The MAT-100 must accompany all samples and documentation submitted to the Division of Materials Testing. The form is normally produced electronically through CMR/SiteManager. All samples other than PC concrete cylinders must have a MAT-100 attached or included so that the sample can be tracked by DMT personnel. Samples or documentation received without a MAT-100 may be returned to the project or discarded without any action by the DMT.

**STATE OF CONNECTICUT - DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

MAT-103 REV 11/16

REPORT OF REJECTED MATERIAL

Project Number		ITEM # (If multiple, only list first from MAT-100)	Date
Material	Sample ID.		
Source of Material	Quantity Represented	Reason for Rejection	

Complete section 1 OR 2. See below for instructions.

**1. ACTION TAKEN - DOES NOT INCLUDE RETESTING THE SAME MATERIAL WITH A DIFFERENT TEST METHOD.
(i.e., Windsor Probe, Swiss Hammer)**

New Sample	Source	Sample ID.	Sample Status
-------------------	--------	------------	---------------

Material Replaced	Source	Sample ID.	Sample Status
--------------------------	--------	------------	---------------

Signature

Inspector _____	Print _____
Project Engineer _____	Print _____
District or Assistant District Engineer _____	Print _____
Town Official/Title (municipal projects only) _____	Print _____

2. ACCEPTANCE OF REJECTED MATERIAL WITHOUT ACTION
In accordance with ConnDOT Standard Specifications Section 1.06.02 or 1.06.04, the non-complying material is hereby accepted by the District.

Section Applied	
1.06.02	1.06.04
Check one	

Signature/Print

Inspector _____	Print _____
Project Engineer _____	Print _____
District or Assistant District Engineer _____	Print _____
Town Official/Title (Municipal Projects Only) _____	Print _____

For acceptance by Section 1.06.02, all the following criteria must be met.

- Results of prior and subsequent series of tests of the material or materials from the same source or sources are found satisfactory.
- The incidence and degree of non-conformance with the Contract requirements are, in the Engineer's judgement, within reasonable limits.
- The Contractor, in the Engineer's judgement, had diligently exercised material controls consistent with good practices.
- No adverse effect on the value or serviceability of the completed work could result.

For acceptance by Section 1.06.04, any credits, allowances, warranties, or other conditions of acceptance must be described below.

Report of Rejected Material (MAT-103) Instructions

The Report of Rejected Material form serves the following purpose:

1. Identify the project and material that did not meet specification.
2. Report action taken (if any) **which only includes retesting** the material with an additional sample and achieving acceptable results or **removing** and replacing the deficient material with acceptable material. When such an action is taken, the MAT-103 provides the DMT with information on how rejected material was addressed. Signatures are required in this section to acknowledge the rejection and the action taken.

Please Note: Portland Cement (PC) Concrete is recommended for acceptance or rejection based on concrete cylinder test results at 28 days of age. Windsor Probe or Swiss Hammer results are for information only and will not override the test cylinder results at 28 days regardless of when they are performed. The PC concrete will be listed as an exception to the specifications on the Final Materials Certificate unless the District accepts the concrete using the acceptance criteria described below.

3. In the case where no action was taken, the District may formally accept the non-complying or deficient material in accordance with Sections 1.06.02 or 1.06.04. Signatures in this section are intended for formal acceptance of the non-complying or deficient material by the District. In the case where a Town Official or Consulting Engineer accepts material, if the District agrees, it must formally concur with the signatures. The DMT may still take exception to the District acceptance and list the material as an exception to the specification on the Final Materials Certificate if it is unable to concur.

MAT-104 REPORT OF TEST MISCELLANEOUS MATERIAL

	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF HIGHWAYS REPORT OF TEST OF MISCELLANEOUS MATERIAL MAT 104 Revised July 2003	DATE	PROJECT/SAMPLE NO.
		LABORATORY NO.	
	RECOMMENDED FOR	REMARKS	

The MAT-104 will be used by DMT personnel to report the results of testing on materials that are not otherwise covered by any specific reporting form.

REPRESENTATIVE (DMT - Rocky Hill)			
MATERIAL TO BE TESTED			
MATERIALS		STAFF	Telephone (860)
AGGREGATES (COARSE & FINE)		See District Labs Below*	
BRICK, CONCRETE BLOCK, CONCRETE CYLINDER RESULTS		<i>email:</i>	(860)
	Mark Brothwell	Mark.Brothwell@ct.gov	258 - 0378
CALCIUM CHLORIDE, FERTILIZER, PAINT (TRAFFIC), SODIUM CHLORIDE,			
	John Giannini	John.Giannini@ct.gov	258 - 0324
CEMENT (TYPE I, I/II, III), GROUT			
	Moses Marino	Moses.Marino@ct.gov	258 - 0379
CERTIFICATIONS, PIPE – PLASTIC			
	Stephen Mann	Stephen.Mann@ct.gov	258 - 0344
CHAIN LINK FENCE, GUARD RAIL, STEEL ITEMS (REBAR, BOLTS, ETC.)			
	Mark Brothwell	Mark.Brothwell@ct.gov	258 - 0378
CONCRETE MIX DESIGNS (NON-STANDARD), PRECAST/ CONCRETE, BOX CULVERTS			
	John Giannini	John.Giannini@ct.gov	258 - 0324
CONCRETE MIX, (STANDARD) MIXES <i>(Check SiteManager Terminal Server Materials Folder)</i>			
	Charles Gardon	Charles.Gardon@ct.gov	258 - 0717
CORROGATED METAL PIPE		See District Labs Below*	
CRACK SEALERS, JOINT SEALERS, MEMBRANES			
	John Giannini	John.Giannini@ct.gov	258 - 0324
FENCE, CHAINLINK, GUARD RAIL			
	Mark Brothwell	Mark.Brothwell@ct.gov	258 - 0378
HOT MIX ASPHALT			
HMA PLANT – DMT Office	David Howley	David.Howley@ct.gov	258 - 0350
HMA Plant Operation's / Field Inspection	David Parillo	David.M.Parillo@ct.gov	258 - 0389
HOT MIX ASPHALT (Density Acceptance by Cores)	David Howley	David.Howley@ct.gov	258 - 0350
HOT MIX ASPHALT (Mix Assurance)	Andrew Bednar	Andrew.Bednar@ct.gov	258 - 0708
STRUCTURAL STEEL/ WELDING/ COATINGS			
	David Parillo	David.M.Parillo@ct.gov	258 - 0389
CERTIFICATIONS/ PRECAST CONCRETE CATCH BASINS, MANHOLES and TOPS, PIPE – REINFORCED CONCRETE			
	Stephen Mann	Stephen.Mann@ct.gov	258 - 0344
FINAL MATERIAL CERTIFICATION			
	Laura Pelletier	Laura.Pelletier@ct.gov	258 - 0323
	David Howley	David.Howley@ct.gov	258 - 0350
SITEMANAGER			
	David Parillo	David.M.Parillo@ct.gov	258 - 0389
DISTRICT LABORATORY*			
AGGREGATES and RIP RAP, PIPE, METAL, ALUMINUM CORRUGATED See District Labs Below*			
DISTRICT 1		DISTRICT 3	
Justin Labossiere	(860) 258 - 0335	Steve Parkosewich	(203) 389 - 3128
DISTRICT 2		DISTRICT 4	
Mark Tice	(860) 537 – 8935/36	Gerald Smith	(203) 591 - 3739



STATE OF CONNECTICUT

Department of Transportation
Division of Materials Testing
280 West Street
Rocky Hill, CT 06067

NOTABLE OBSERVATION

MAT-107

Rev. 12/16

Project Number: _____ District: _____ Date: _____

Project Description: _____ Prime Contractor: _____

Producer/Supplier: _____ P/S Location: _____

QA Inspector: _____ QA Firm: _____

THE FOLLOWING OBSERVATION(S) AND/OR DISCREPANCY(IES) WAS/WERE NOTED:

[Empty box for observation notes]

Photos Attached: YES NO

If yes, number of photos:

Verbally provided to: _____ of _____ on _____
Name Company/Project Date

- Distribution: Project Engineer (District)
- Project Manager (District)
- Supervising Engineer (DMT)
- Principal Engineer (DMT)

Inspector: _____
Print
Signature

If you have any questions or require further information, please contact the Division of Materials Testing as noted below:

Email: DOT.MatTesting@ct.gov • Tel: (860) 258 - 0321 • Fax: (860) 258 - 0399

**CONNECTICUT DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING
DAILY WORK REPORT
MAT-108**

Rev. 12/16

DATE	INSPECTOR

PLANT / PROJECT LOCATION	PROJECT #	MATERIAL	MATERIAL QUANTITY

COMMENTS / DEFICIENCIES:

TRAVEL INFORMATION
<p>Enter Start and End times for time from and to work station or home.</p> <p>Start: _____ End: _____</p>
<p>Enter Start and End times for actual time at the plants or projects.</p> <p>Start: _____ End: _____</p>

**CONNECTICUT DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING
HMA INSPECTOR'S REPORT
MAT-108 HMA**

REV. 12/16

PLANT #: _____

DATE: _____

PRODUCER NAME: _____

STATE INSPECTOR: _____

LOCATION: _____

PLANT TECHNICIAN: _____

Project #	Route	Town	Material Code	Material Description	RAP	WMA	Contract	Mix Status On Departure	State Test	Load #	IA	Load #
						<input type="checkbox"/>			<input type="checkbox"/>		<input type="checkbox"/>	
						<input type="checkbox"/>			<input type="checkbox"/>		<input type="checkbox"/>	
						<input type="checkbox"/>			<input type="checkbox"/>		<input type="checkbox"/>	
						<input type="checkbox"/>			<input type="checkbox"/>		<input type="checkbox"/>	
						<input type="checkbox"/>			<input type="checkbox"/>		<input type="checkbox"/>	
						<input type="checkbox"/>			<input type="checkbox"/>		<input type="checkbox"/>	

COMMENTS / DEFICIENCIES:

✓ AASHTO TESTS WITNESSED	✓ ADDITIONAL INFORMATION
<input type="checkbox"/> T 168 - Sampling Bituminous Mixtures <input type="checkbox"/> R 47 - Sample Reduction <input type="checkbox"/> T 312 - Preparation of Gyratory Sample <input type="checkbox"/> T 308 - Asphalt Content - Ignition Sample <input type="checkbox"/> T 209 - Theoretical Maximum Gravity (Gmm) <input type="checkbox"/> T 30 - Sieve Analysis <input type="checkbox"/> T 166 - Bulk Specific Gravity (Gmb) <input type="checkbox"/> T 255 - Moisture Content	<input type="checkbox"/> Verify plant settings are in accordance with JMF. <input type="checkbox"/> Verify proper PG Binder in accordance with JMF & Contract. <input type="checkbox"/> Verify the use of anti-strip if required by JMF. <input type="checkbox"/> Inspect aggregate and RAP stockpiles. <input type="checkbox"/> Testing equipment is functioning properly. <input type="checkbox"/> Check the temperature of the mix. <input type="checkbox"/> Inspect haul units for proper canvas covers and release agents. <input type="checkbox"/> Technician performed Quality Control testing (aggregates, HMA, etc.).

Enter Start & End times from and to work station or home.					Total Shift Hours:	
Start:		End:			Regular Hours:	
Enter Start & End times for actual time at Plant.					Overtime Hours:	
Start:		End:			Vacation / Sick / PL:	

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING
PORTLAND CEMENT CONCRETE (PCC) INSPECTOR'S DAILY WORK REPORT
MAT-108 PCC**

Rev. 12-16

PLANT INFORMATION
DATE:
PLANT NAME:
LOCATION:
PLANT MANAGER & PHONE NUMBER:
INSPECTOR'S NAME:
PROJECT #:

ITEM BEING INSPECTED
ITEM DESCRIPTION:
FORM INSPECTED BY:
DID FORM MEET REQUIREMENTS? Yes No
NON CONFORMANCE:
REMARKS:

CONCRETE POUR
TIME:
TEMP. OF CONCRETE:
TEMP. OF BUILDING:
AIR:
SLUMP:
DID CONCRETE POUR MEET REQUIREMENTS? Yes No
NON CONFORMANCE:
REMARKS:

WITNESS CYLINDER BREAKS
BREAKS:
DID BREAKS MEET REQUIREMENTS? Yes No
NON CONFORMANCE:
REMARKS:

END OF DAY REMARKS

TRAVEL INFORMATION
Enter Start and End times for time from and to work station or home. Start: _____ End: _____
Enter Start and End times for actual time at the plants or projects. Start: _____ End: _____

STATE OF CONNECTICUT
 DEPARTMENT OF TRANSPORTATION
 DIVISION OF MATERIALS TESTING

Security ID Tag:
SEAL NO. 1: _____
SEAL NO. 2: _____

Project No.: _____ Route: _____
 Town: _____ District No.: _____
 Paving Contractor: _____ HMA Plant: _____
 HMA Mix Size: _____ Level: _____ Lift Thickness: _____
 Inspector: _____ Project Phone Number: _____

Core Sample Label Lot (M or J)# - # <i>FORM 816 Section 4.06.03</i>	Date Paved (If paving at Night, date before midnight applies)	Date Cored	Base Material		Location		Offset (ft)
			leveling	milled	Bridge Number <i>(if applies)</i>	Station Number	

Do any of the Core Sample(s) above complete a lot(s)? Yes No

If "Yes", list the Lot(s): _____

Inspector Signature

Contractor Rep. Signature



State of Connecticut

Department of Transportation
Division of Materials Testing
280 West Street
Rocky Hill, Ct 06067
MAT-110

**WELDER AND WELDING OPERATOR
QUALIFICATION RECORD**

PHOTO

Welder's Name: _____ Identification No.: _____
Address: _____ City: _____
State: _____ Zip Code: _____ Telephone No.: _____
Email Address: _____ Test Site: _____

WELDING PERFORMANCE QUALIFICATION TEST RECORD

Welding process: _____ Manual Semi-automatic Machine
Position: _____ (Flat, horizontal, overhead or vertical – if vertical, state whether upward or downward)
In conformance with **WPS No.:** _____
Material Specification: _____ Thickness range this qualifies: _____

FILLER METAL

Specification No.: _____ Classification: _____
Describe filler metal (if not covered by AWS specification): _____
Is backing used? _____
Filler metal diameter and trade name: _____ Flux for SAW or gas for GMAW or FCAW-G: _____

VISUAL INSPECTION (6.26.1 OR 9.21.1)

Appearance: _____ Undercut: _____ Piping porosity: _____

GUIDED BEND TEST RESULTS

Type	Result	Type	Result

Test Conducted By: _____ Laboratory Test No.: _____
Per: _____ Test Date: _____

FILLET TEST RESULTS

Appearance: _____ Fillet Size: _____
Fracture Test Root Penetration: _____ Macroetch: _____
(Describe the location, nature, and size of any crack or tearing of the specimen.)
Test Conducted By: _____ Laboratory Test No.: _____
Per: _____ Test Date: _____

RADIOGRAPHIC TEST RESULTS

Film Identification	Results	Remarks	Film Identification	Results	Remarks

Test Witnessed By: _____ Test No. _____
Per: _____ Test Date: _____

We the undersigned certify that the statements in this record are correct and that the welds were prepared and tested in conformance with the requirements of AASHTO/AWS D1.5M/D1.5 (2010) Bridge Welding Code.

Manufacturer or Contractor: _____
Authorized By: _____
Date: _____



State of Connecticut

Department of Transportation
Division of Materials Testing
280 West Street
Rocky Hill, CT 06067
MAT111

WELDER'S CERTIFICATION PROGRAM

Rev. 4-19

Requirements for a State of Connecticut Department of Transportation (ConnDOT) Welder Certification Card:

1. New applicants must receive a Welder Qualification Test from an approved Contractor listed on page 2. The State also reserves the right to require a Welder Qualification Test at any time.
2. The Welder Certification card must be carried on the welder's person whenever welding is performed on ConnDOT Projects and is prohibited to be used as certification for other business.
3. The Welder Certification card shall remain the property of ConnDOT and may be revoked.
4. **The Welder Certification must be updated by emailing DOT.WelderCertification@ct.gov or calling 860-258-0327 every six months after the date of issue or six months from the date of the last valid update. A Welder must be performing welding on ConnDOT Projects to be updated.**
5. Only authorized representatives of ConnDOT shall update the Welder Certification.

For a Welder Certification card to be issued or re-issued, the following conditions must be met:

- ❖ Adherence to the requirements stated above
- ❖ Please complete contact information below with an attached **current photo** and do **one** of the following:
 - a. Mail form and hard copy photo to: 280 West Street, Rocky Hill CT 06067, Attention Thomas Lynch
 - b. Email form and digital photo to: DOT.WelderCertification@ct.gov

Contact Information:

FILLABLE FORM (Blue Area)			
Full Name:	<input type="text"/>		
	<i>Last</i>	<i>First</i>	<i>M.I.</i>
Address:	<input type="text"/>		
	<i>Street Address</i>		<i>Apartment/Unit #</i>
	<i>City</i>	<i>State</i>	<i>ZIP Code</i>
Mailing Address: <i>(IF DIFFERENT)</i>	<input type="text"/>		
	<i>Street Address</i>		<i>Apartment/Unit #</i>
	<i>City</i>	<i>State</i>	<i>ZIP Code</i>
Home Phone:	<input type="text"/>	Alternate Phone: <input type="text"/>	Cell Phone: <input type="text"/>
Email:	<input type="text"/>		
	❖ PLEASE PROVIDE AN EMAIL ADDRESS		

Any questions:

Christopher Carlo
280 West Street
Rocky Hill, CT 06067
Email:
Christopher.Carlo@ct.gov
(860) 258-0334
Fax: (860) 258-0399

Jonathan Boardman
280 West Street
Rocky Hill, CT 06067
Email:
Jonathan.Boardman@ct.gov
(860) 258-0327
Fax: (860) 258-0399



State of Connecticut

Department of Transportation
Division of Materials Testing
280 West Street
Rocky Hill, Ct 06067

MAT112

WELDER'S CALL IN REPORT

Call Received Date: _____ Certification Number: _____

Full Name: _____
First *Last*

Address: _____
Street Address *Apartment/Unit #*

City *State* *ZIP Code*

Cell Phone: _____ Home Phone: _____

Email: _____

Current / Past Project: _____ Contact Name: _____

Phone Number: _____

- ❖ **Make sure you ask for the following information:**
 1. Certification Number.
 2. Address if it has changed.
 3. Cell phone and home.
 4. Email address if they have one.



State of Connecticut

Department of Transportation
Division of Materials Testing
280 West Street
Rocky Hill, Ct 06067

MAT112

WELDER'S CALL IN REPORT

Call Received Date: _____ Certification Number: _____

Full Name: _____
First *Last*

Address: _____
Street Address *Apartment/Unit #*

City *State* *ZIP Code*

Cell Phone: _____ Home Phone: _____

Email: _____

Current / Past Project: _____ Contact Name: _____

Phone Number: _____

- ❖ **Make sure you ask for the following information:**
 1. Certification Number
 2. Address if it has changed
 3. Cell phone and home (one that we can get a hold of welder)
 4. Email address if they have one

METAL PIPE (Steel)

Note: Attach Manufacturer's/Fabricator's Material Certifications

KIND OF MATERIAL	State of Connecticut Department of Transportation Bureau of Engineering & Construction Inspection Report of Metal Pipe MAT-200	Date	Project #	
SOURCE OF SUPPLY		Sample ID #		
LOCATION OF SOURCE OF SUPPLY				
SAMPLE TAKEN FROM	Nominal Size of Pipe (inches/mm): _____ Thickness of Steel (inches/mm): _____ Type of Seam: _____ Thickness of Asphalt (inches/mm): _____ Paved Invert (inches/mm): _____ Type of Coupling Bands (inches/mm): _____ Thickness of Steel - Bands (inches/mm): _____ Width of Coupling Bands (inches/mm): _____ Corrugation or Helical Rib Size (inches/mm): _____			
LOCATION OF				
SAMPLED BY				
DATE SAMPLED				
USING AGENCY				
QUANTITY PRESENTED				
PURPOSE FOR WHICH MATERIAL WILL BE USED				
SAMPLE RECEIVED		<div style="border: 1px solid black; padding: 2px; display: inline-block;"> NOTE: Aluminized Steel Pipe does not require asphalt coating or paved invert </div> Person Performing Inspection (Initials): _____		
DATE MATERIAL WILL BE USED		Recommended For:	Remarks:	
WHERE MATERIAL WILL BE USED				
Division of Materials Testing				

PERFORATED METAL PIPE (Steel)

Note: Attach Manufacturer's/Fabricator's Material Certifications

KIND OF MATERIAL	State of Connecticut Department of Transportation Bureau of Engineering & Construction Inspection Report of Perforated Metal Pipe MAT-202	Date	Project #	
SOURCE OF SUPPLY		Sample ID #		
LOCATION OF SOURCE OF SUPPLY				
SAMPLE TAKEN FROM	Nominal Size of Pipe (inches/mm): _____ Thickness of Steel (inches/mm): _____ Type of Seam: _____ Number of Rows of Perforations: _____ Diameter of Perforations (inches/mm): _____ Height of Uppermost Rows of Perforations Above bottom of Invert (inches/mm): _____ Chord Length of Unperforated Segment (inches/mm): _____ Type of Coupling Bands: _____ Thickness of Steel Bands (inches/mm): _____ Width of Coupling Bands (inches/mm): _____ Corrugation or Helical Rib Size (inches/mm): _____ Person Performing Inspection (initials) : _____			
LOCATION OF				
SAMPLED BY				
DATE SAMPLED				
USING AGENCY				
QUANTITY PRESENTED				
PURPOSE FOR WHICH MATERIAL WILL BE USED				
SAMPLE RECEIVED				
DATE MATERIAL WILL BE USED				
WHERE MATERIAL WILL BE USED				
		Recommended For	Remarks	
Division of Materials Testing				

STRUCTURAL PLATE AND PIPE ARCHES

Note: Attach Manufacturer's/Fabricator's Material Certifications

KIND OF MATERIAL	State of Connecticut Department of Transportation Bureau of Engineering & Construction Inspection Report of Structural Plate and Pipe Arches MAT-203	Date	Project #
SOURCE OF SUPPLY		Sample ID #	
LOCATION OF SOURCE OF SUPPLY			
SAMPLE TAKEN FROM	<p align="center">Steel <input type="checkbox"/> Aluminized Steel <input type="checkbox"/> Aluminum <input type="checkbox"/></p>		
LOCATION OF	Nominal Size of Structural Plate (inches/mm): _____		
SAMPLED BY	Thickness of Plates (inches/mm): _____		
DATE SAMPLED	Diameter of Perforations (inches/mm): _____		
USING AGENCY	Size of Corrugations or Helical Ribs (inches/mm): _____		
QUANTITY PRESENTED	Location of Longitudinal Bolt Holes: _____		
PURPOSE FOR WHICH MATERIAL WILL BE USED	Location of Circumferential Bolt Holes: _____		
SAMPLE RECEIVED	Center of Bolt Hole to Edge of Plate: _____		
	Type of Coating: _____		
	Person Performing Inspection (initials) : _____		
DATE MATERIAL WILL BE USED	Recommended For	Remarks	
WHERE MATERIAL WILL BE USED			
Division of Materials Testing			

CULVERT END

Note: Attach Manufacturer's/Fabricator's Material Certifications

KIND OF MATERIAL	<p align="center">State of Connecticut Department of Transportation Bureau of Engineering & Construction Inspection Report of Culvert End MAT-204</p>	Date	Project #
SOURCE OF SUPPLY		Sample ID #	
LOCATION OF SOURCE OF SUPPLY			
SAMPLE TAKEN FROM	<p align="center">Steel <input type="checkbox"/> Aluminized Steel <input type="checkbox"/> Aluminum <input type="checkbox"/></p>		
LOCATION OF	Nominal Size of Pipe (inches/mm):	_____	
SAMPLED BY	Thickness of Sheet (inches/mm):	_____	
DATE SAMPLED	Thickness of Asphalt (inches/mm):	_____	
USING AGENCY	Dimension "B" (inches/mm):	_____	
QUANTITY PRESENTED	Dimension "H" (inches/mm):	_____	
PURPOSE FOR WHICH MATERIAL WILL BE USED	Dimension "L" (inches/mm):	_____	
SAMPLE RECEIVED	Dimension "W" (inches/mm):	_____	
DATE MATERIAL WILL BE USED	Attachment System:	_____	
WHERE MATERIAL WILL BE USED	Edge Reinforcement:	_____	
	Type of Seam:	_____	
	<p align="center">NOTE: Aluminized Steel Pipe does not require asphalt coating or paved invert.</p>		
	Recommended For:	Remarks:	
Division of Materials Testing			

T27/C136

Non-cumulative RETAINED MASSES

					2 1/2" 63 mm									
5" 125 mm					2" 50 mm									
3 1/2" 90 mm					1 1/2" 37.5 mm									
1 1/2" 37.5 mm					1" 25 mm									
3/4" 19 mm					3/4" 19 mm									
1/4" 6.3 mm					1/4" 6.3 mm									
PAN					PAN									

1/4" 6.3 mm					1/4" 6.3 mm									
No. 10 2.0 mm					No. 10 2.0 mm									
No. 40 425 μm					No. 40 425 μm									
No. 100 150 μm					No. 100 150 μm									
No. 200 75 μm					No. 200 75 μm									
PAN					PAN									

KIND OF MATERIAL		STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING & CONSTRUCTION REPORT OF TESTS OF BANK RUN GRAVELS OR PROCESSED AGGREGATE MAT-205				DATE	PROJECT #
SOURCE OF SUPPLY						SAMPLE ID #	
LOCATION OF SOURCE OF SUPPLY		SIEVES	% PASS	SIEVES	% PASS	% WEAR & LAB NO.	MAXIMUM DENSITY
SAMPLE TAKEN FROM		5" 125 mm		5" 125 mm			
LOCATION OF		3 1/2" 90 mm		3 1/2" 90 mm		SOUNDNESS LOSS & LAB NO.	OPTIMUM MOISTURE
SAMPLED BY		2 1/2" 63 mm		2 1/2" 63 mm			
DATE SAMPLED		2" 50 mm		2" 50 mm		% LIQUID ASPHALT	
USING AGENCY		1 1/2" 37.5 mm		1 1/2" 37.5 mm		PLASTICITY & LAB NO. (PLASTIC OR NON-PLASTIC)	
QUANTITY REPRESENTED		1" 25 mm		1" 25 mm			
PURPOSE FOR WHICH MATERIAL WILL BE USED		3/4" 19 mm		3/4" 19 mm		RECOMMENDED FOR:	
		1/4" 6.3 mm		1/4" 6.3 mm			
DATE MATERIAL WILL BE USED		No. 10 2.0 mm		No. 10 2.0 mm		REMARKS:	
WHERE MATERIAL WILL BE USED		No. 40 425 μm		No. 40 425 μm			
DATE SAMPLED		No. 100 150 μm		No. 100 150 μm			
		No. 200 75 μm		No. 200 75 μm		Person Performing Test (Initials):	
Division of Materials Testing							

T11/C117		T11/C117	
ORIGINAL MASS	gm	ORIGINAL MASS	gm
LESS WASHED MASS	gm	LESS WASHED MASS	gm
MASS OF SILT	gm	MASS OF SILT	gm
SILT	%	SILT	%

T27/C136					T27/C136				
	RETAINED MASS	IND.RETAINED %	PASSING %	RETAINED %		RETAINED MASS	IND.RETAINED %	PASSING %	RETAINED %
5/8"					5/8"				
16.0 mm					16.0 mm				
1/2"					1/2"				
12.5 mm					12.5 mm				
3/8"					3/8"				
9.5 mm					9.5 mm				
No. 4					No. 4				
4.75 mm					4.75 mm				
No. 8					No. 8				
2.36 mm					2.36 mm				
No. 16					No. 16				
1.18 mm					1.18 mm				
No. 30					No. 30				
600 µm					600 µm				
No. 50					No. 50				
300 µm					300 µm				
No. 100					No. 100				
150 µm					150 µm				
PAN					PAN				
TOTAL MASS			F.M.		TOTAL MASS			F.M.	

KIND OF MATERIAL	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING & CONSTRUCTION REPORT OF TEST OF SAND MAT-206			DATE	PROJECT #
SOURCE OF SUPPLY				SAMPLE ID #	
LOCATION OF SOURCE OF SUPPLY	PASSING SIEVE	PERCENT	PERCENT	COLOR (GARDNER COLOR STANDARD) T21/C40 UNDER #11 <input type="checkbox"/> OVER #11 <input type="checkbox"/>	
SAMPLE TAKEN FROM	1/2" 12.5 mm			COMPRESSIVE STRENGTH (MPa)	
LOCATION OF	3/8" 9.5 mm			7 day	28 day
SAMPLED BY	No. 4 4.75 mm			SAMPLE SAND	
DATE SAMPLED	No. 8 2.36 mm			OTTAWA SAND	
USING AGENCY	No. 16 1.18 mm			PERCENT OF OTTAWA	
QUANTITY REPRESENTED	No. 30 600 µm			RECOMMENDED FOR	
PURPOSE FOR WHICH MATERIAL WILL BE USED	No. 50 300 µm				
DATE MATERIAL WILL BE USED	No. 100 150 µm			REMARKS	
WHERE MATERIAL WILL BE USED	FINENESS MODULUS				
	SILT %			Person Performing Test (initials) : _____	

Division of Materials Testing

NO. 3

NO. 6

NO. 8

2 1/2" 63 mm											
2" 50 mm				1" 25 mm					1/2" 12.5 mm		
1 1/2" 37.5 mm				3/4" 19 mm					3/8" 9.5 mm		
1 1/4" 31.5 mm				1/2" 12.5 mm					No. 4 4.75 mm		
1" 25 mm				3/8" 9.5 mm					No. 8 2.36 mm		
1/2" 12.5 mm				No. 4 4.75 mm					No. 16 1.18 mm		
PAN				PAN					PAN		

NO. 4

NO. 67

2" 50 mm											
1 1/2" 37.5 mm				1" 25 mm							
1 1/4" 31.5 mm				3/4" 19 mm							
1" 25 mm				1/2" 12.5 mm							
3/4" 19 mm				3/8" 9.5 mm							
1/2" 12.5 mm				No. 4 4.75 mm							
3/8" 9.5 mm				No. 8 2.36 mm							
PAN				PAN					PAN		

KIND OF MATERIAL		MAT-207 DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST OF COARSE AGGREGATE				DATE	PROJECT #		
SOURCE OF SUPPLY						SAMPLE ID #			
LOCATION OF SOURCE OF SUPPLY						SQUARE MESH		PERCENT PASSING	
SAMPLE TAKEN FROM		SIEVES				SOUNDNESS % LOSS			
LOCATION OF		2" 50 mm				RECOMMENDED FOR			
SAMPLED BY		1 1/2" 37.5 mm							
DATE SAMPLED		1 1/4" 31.5 mm							
USING AGENCY		1" 25 mm							
QUANTITY REPRESENTED		3/4" 19 mm							
PURPOSE FOR WHICH MATERIAL WILL BE USED		1/2" 12.5 mm				REMARKS			
		3/8" 9.5 mm							
DATE MATERIAL WILL BE USED		No. 4 4.75 mm							
WHERE MATERIAL WILL BE USED		No. 8 2.36 mm							
SAMPLE RECEIVED		No. 16 1.18 mm				Person Performing Test (initials): _____			
		No. 100 150 µm							
Division of Materials Testing									

Rock Salt

Sample Weight	1/2 inch	% passing
ml AgNO ₃ Sample	3/8 inch	% passing
Wt of Standard	# 4	% passing
ml AgNO ₃ Standard	# 8	% passing
% NaCl	# 30	% passing
Salt Wt	Pan	
Dry Salt Wt	Project #	Sample ID#
% moisture	Date	Analyst

Specification Reference

Standard Specification _____
 Supplemental Specification _____
 Project Specification _____
 Other _____
 Person Accepting Technical Responsibility
 Name: _____
 Title: _____

Specification: Reference File 139 - AASHTO M143, Type 1 (except sections 9.1.2 and 11.2) Methods: M143 Rapid, T27, T265 <hr/> <p style="text-align: center;">Lab use only</p> Material # _____ Vendor # _____ Date Sampled _____ Destination Code _____ Material Quantity _____ Material Unit _____ Date Received _____ C or M _____ Dates _____	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Rock Salt MAT-208	Date	Project #	
	Sample ID # _____			
	<u>Spec.</u>	<u>Results</u>		
	% NaCl	95 % min	_____	
	Moisture	3% max	_____	
	% Passing 1/2 inch	100	_____	
	% Passing 3/8 inch	95 – 100	_____	
	% passing # 4	20 – 90	_____	
	% passing # 8	10 – 60	_____	
	% passing # 30	0 – 15	_____	
	Person Performing Test (initials) : _____			
	Recommended For	Remarks		

Division of Materials Testing

Calcium Chloride

Project #	Sample ID #
Date	Analyst
Sample Wt.	
N KmnO ₄	
ml KmnO ₄	
CaCl Factor	
% CaCl	

Specification Reference

Standard Specification _____
 Supplemental Specification _____
 Project Specification _____
 Other _____
 Person Accepting Technical Responsibility
 Name: _____
 Title: _____

Specification: AASHTO M144 via Form 815 Section (9.42.02) Methods: AASHTO T143, ASTM E449 <hr/> Lab use only Material # Vendor # Date Sampled Destination Code Material Quantity Material Unit Date Received Batch # C or M Dates -----	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Calcium Chloride MAT-209		Date	Project #
			Sample ID #	
	Grade % CaCl Grade 1 min. 77% Grade 2 min. 90% % CaCl _____ Grade 3 min. 94%	Person Performing Test (initials) : _____		
	Recommended For	Remarks		
Division of Materials Testing				

T96/C131 Los Angeles Abrasion Test

	<u>Pass.</u> (inches/mm)	<u>Ret.</u> (inches/mm)			
Class A:	1 ½ (37.5)	1 (25) -		+ 12 (1.7mm)	
	1 (25)	¾ (19) -			
	¾ (19)	½ (12.5) -		+ 12 (1.7mm)	
	½ (12.5)	3/8 (9.5) -			Total of +12 (1.7mm)
	Total Weight =			Total Wt. -	
			Minus +12 (1.7mm)		Total of -12 (1.7mm)
 Class B:	 ¾ (19)	 ½ (12.5) -			
	½ (12.5)	3/8 (9.5) -			
	Total Weight =				
			Total of -12 (1.7mm)	=	
			Total Weight	=	
				=	
					%

A: 1250 each required size – 12 spheres
 B: 1250 each required size – 11 spheres

Dust = _____

KIND OF MATERIAL	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of L. A. Abrasion & Soundness MAT-211	Date	IN-HOUSE TEST
SOURCE OF SUPPLY		Sample ID #	
LOCATION OF SOURCE OF SUPPLY			
SAMPLE TAKEN FROM	Class _____ Wear, %: _____ % Soundness, % Loss (if applicable): _____ % <div style="border: 1px solid black; padding: 2px; margin: 5px auto; width: 80%;"> (If Soundness reported, attach worksheet.) </div>		
LOCATION OF			
SAMPLED BY			
DATE SAMPLED	<div style="border: 1px solid black; padding: 2px; margin: 5px auto; width: 60%;"> Material # _____ Vendor # _____ </div>		
USING AGENCY			
QUANTITY PRESENTED			
PURPOSE FOR WHICH MATERIAL WILL BE USED			
SAMPLE RECEIVED			
DATE MATERIAL WILL BE USED	Recommended For	Remarks	
WHERE MATERIAL WILL BE USED			

ACCEPTANCE CRITERIA FOR USE OF RECLAIMED MATERIAL
MAT-212 (REV. 04-19)

This form is to be completed and signed by both the selected DPH-certified analytical Laboratory and the Contractor. The original laboratory test reports, including chain of custody, must be attached to this form.

Project Number _____ Contractor _____
Project Location _____ Contractor Telephone _____
_____ Contractor Email _____
Laboratory Name _____ Laboratory Telephone _____

Section 1

ANALYTICAL LABORATORY TO COMPLETE

Sample containers - Samples received at the laboratory in clean, laboratory-supplied containers, appropriately preserved, and transmitted to the lab under proper "chain-of-custody" protocols. **(check one)** Yes No

Other - Does the sample have an unusual appearance or odor? Yes No

If yes, please describe: _____

Laboratory Certification: I certify that the analytical report provided for sample ID #(s)

_____ represents the laboratory analysis of a sample that was received in acceptable condition (clean, appropriate sample container, preservation chemicals per sample protocols, proper temperature, chain of custody maintained, etc.) on _____ (date).

Signature Date

Name (printed) Title

ACCEPTANCE CRITERIA FOR USE OF RECLAIMED MATERIAL
MAT-212 (REV. 04-19)

Project Number _____ **Contractor** _____
Project Location _____ **Contractor Telephone** _____
 _____ **Contractor Email** _____
Material Source _____ **Source Telephone** _____
Source Address _____ **Source Email** _____
Represented Quantity _____ **Sample Collected by** _____
(name)

Section 2

CONTRACTOR TO COMPLETE

Leachable RCRA metals by SPLP method 1312

List of RCRA Metals	GA Pollutant Mobility Criteria (mg/l)	Result (mg/l)	≤ Specified Limits	
Arsenic	0.05		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Barium	1.00		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Cadmium	0.005		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Chromium	0.05		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Lead	0.015		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Mercury	0.002		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Selenium	0.05		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Silver	0.036		<input type="checkbox"/> Yes	<input type="checkbox"/> No

Total RCRA metals mass analysis by EPA Method 3050 & 6000 or equivalent

List of RCRA Metals	Residential Direct Exposure Criteria (mg/kg)	Result (mg/kg)	≤ Specified Limits	
Arsenic	10		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Barium	4700		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Cadmium	34		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Chromium	100		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Lead	400		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Mercury	20		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Selenium	340		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Silver	340		<input type="checkbox"/> Yes	<input type="checkbox"/> No

ACCEPTANCE CRITERIA FOR USE OF RECLAIMED MATERIAL
MAT-212 (REV. 04-19)

Volatile Organic Compounds (VOC) by EPA Method 8260B	Class GA Pollutant Mobility Criteria (mg/kg)	Results (mg/kg)	≤ Specified Limits	
Acetone	14		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Acrylonitrile	0.01		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Benzene	0.02		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Bromodichloromethane	0.011		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Bromoform	0.08		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Bromomethane	0.2		<input type="checkbox"/> Yes	<input type="checkbox"/> No
2-Butane (MEK)	8		<input type="checkbox"/> Yes	<input type="checkbox"/> No
n-Butylbenzene	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
sec-Butylbenzene	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
tert-Butylbenzene	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Carbon Disulfide	14		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Carbon Tetrachloride	0.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Chlorobenzene	2		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Chloroform	0.12		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Chloromethane	0.054		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Dibromochloromethane	0.01		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,2-Dibromoethane (EDB)	0.01		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,2-Dichlorobenzene	3.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,3-Dichlorobenzene	12		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,4- Dichlorobenzene	1.5		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,1-Dichloroethane	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,2- Dichloroethane	0.02		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,1-Dichloroethylene	0.14		<input type="checkbox"/> Yes	<input type="checkbox"/> No
cis-1,2- Dichloroethylene	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
trans-1,2- Dichloroethylene	2		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,2- Dichloropropane	0.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,3- Dichloropropane	0.01		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Ethylbenzene	10.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Hexachlorobutadiene	1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Isopropylbenzene	0.6		<input type="checkbox"/> Yes	<input type="checkbox"/> No
p-Isopropyltoluene	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
MTBE	2		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Methylene Chloride	0.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Methyl Isobutyl Ketone (MIBK)	7		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Naphthalene	5.6		<input type="checkbox"/> Yes	<input type="checkbox"/> No
n-Propylbenzene	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Styrene	2		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,1,1,2-Tetrachloroethane	0.02		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,1,1,2-Tetrachloroethane	0.01		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Tetrachloroethylene	0.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Toluene	20		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,2,4,-Trichlorobenzene	1.4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,1,1,-Trichloroethane	4		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,1,2- Trichloroethane	0.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Trichloroethylene	0.1		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Trichlorofluoromethane	26		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,2,4-Trimethylbenzene	7		<input type="checkbox"/> Yes	<input type="checkbox"/> No
1,3,5- Trimethylbenzene	7		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Vinyl Chloride	0.04		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Total Xylenes	19.5		<input type="checkbox"/> Yes	<input type="checkbox"/> No

ACCEPTANCE CRITERIA FOR USE OF RECLAIMED MATERIAL
MAT-212 (REV. 04-19)

Note: Samples must be analyzed for all substances listed above. When a substance is not detected in the sample, enter **ND**. For substances reported under a different name on the lab report, see instructions below. DOT Environmental Compliance will review the acceptability of any substance detected but not listed above on a case-by-case basis.

For any VOC listed on the lab report as a different name than that above, verify that they are the same compound and the difference is in nomenclature only.

<u>Name on List Above</u>	<u>Name on Lab Report</u>	<u>Same compound?</u>	
_____		<input type="checkbox"/> Yes	<input type="checkbox"/> No
_____		<input type="checkbox"/> Yes	<input type="checkbox"/> No
_____		<input type="checkbox"/> Yes	<input type="checkbox"/> No

Asbestos – analysis using California Air Research Board Method 435 Polarized Light Microscopy (CARB 435 PLM)

Result (%)	< 1%	
	<input type="checkbox"/> Yes	<input type="checkbox"/> No

Polychlorinated Biphenyls (PCB's) - Mass analysis by EPA Method 8082 or equivalent

Residential Direct Exposure Criteria	Result (mg/kg)	≤ 1 mg/kg	
1 mg/kg		<input type="checkbox"/> Yes	<input type="checkbox"/> No

Contractor Certification: I certify that the information provided on this form represents the laboratory analysis of a representative sample of reclaimed material that was collected at the location indicated above and placed in clean, laboratory-supplied sample containers, preserved (as appropriate), and transmitted to the lab under proper “chain-of-custody” protocols in a manner consistent with the prevailing standards and guidelines specified by the Connecticut Department of Energy & Environmental Compliance (CT DEEP) and Connecticut Department of Transportation (CT DOT).

Signature	Name (printed)	Title	Date

Notary Required on this page

ACCEPTANCE CRITERIA FOR USE OF RECLAIMED MATERIAL
MAT-212 (REV. 04-19)

RECLAIMED MATERIAL GUIDELINE

ConnDOT Standard Specifications, Section 1.01.01, defines the three types of reclaimed construction materials and requires environmental testing of these materials prior to use or hauling to project sites.

Form MAT-212 (Acceptance Criteria for Use of Reclaimed Material) is to be completed by and signed by both the Contractor and its selected analytical laboratory. The Contractor proposing to utilize the reclaimed material must have material tested by a CT DPH approved analytical testing laboratory.

Section 1 of the Form MAT-212 must be completed and signed by the Contractor's analytical laboratory.

Section 2 of the Form MAT-212 is to be completed by the Contractor. The Contractor must check off (yes) if results exceed specified limits or (no) if results do not exceed specified limits. All analytes must have results included on the form. Incomplete forms will be returned to the contractor.

The contractor must sign and notarize the MAT-212 and submit with the full analytical report.

FOR CONNDOT PROJECTS ONLY:

If all forms are submitted correctly and materials meet the environmental criteria, project personnel can request source testing by forwarding these forms and the applicable Form Mat-100 (Request for Test) to the district laboratory for review.

The laboratory will review the documentation and the Request for Test. Project personnel will be notified if the source of the material has been recommended for acceptance or rejection.

The project personnel can then allow material recommended for acceptance to be brought on to the project site.

Production samples should then be submitted to the Division of Materials Testing for testing according to the minimum sampling frequency.

FOR MUNICIPAL PROJECTS ONLY:

The Form MAT 212 must be reviewed by a competent representative of the municipality to determine if the material is environmentally acceptable. If so, the material must be tested and used in accordance with the project specifications.


MOISTURE/DENSITY

	State of Connecticut Department of Transportation Bureau of Engineering and Construction Report of Test of Moisture/Density MAT 213	Date	Project #
		Sample ID #	
	AASHTO T180 <input type="checkbox"/> ASTM METHOD <input type="checkbox"/> D _____		
	Maximum Density (Kg/cu.m-Lbs/cu.ft) _____		
Optimum Moisture _____			
Person Performing Test (initials) : _____			
	Recommended For	Remarks	
	Information		
Division of Materials Testing			

**Connecticut Department of Transportation
Moisture Density Data Computation Sheet
MAT-217 - 6" Mold**

Date Tested				1	2	3	4
Project No.		Soil & Tare					
Sampled From		Tare					
Sampled By		Wet Weight					
Date Sampled				X	X	X	X
Type of Material		Volume		13.33	13.33	13.33	13.33
Tested By		Wet Density					
		W.C.					
Sample ID No.		Dry Density					
% Stone Replaced	lbs.		Wet	500	500	500	500
Maximum Density =	pcf	kg/m ³	Dry				
Optimum Moisture =	%		W.C.				


Clear Sheet



**Connecticut Department of Transportation
Moisture Density Data Computation Sheet
MAT-218 - 4" Mold**

Date Tested				1	2	3	4
Project No.		Soil & Tare					
Sampled From		Tare					
Sampled By		Wet Weight					
Date Sampled				X	X	X	X
Type of Material		Volume		30	30	30	30
Tested By		Wet Density					
		W.C.					
Sample ID No.		Dry Density					
% Stone Replaced	lbs.		Wet	500	500	500	500
Maximum Density =	pcf	kg/m ³	Dry				
Optimum Moisture =	%		W.C.				

Clear Sheet



**SPECIFIC GRAVITY AND ABSORPTION OF COARSE AGGREGATE – T 85/C127
DIVISION OF MATERIALS TESTING - MAT-219**

Source: _____

Location: _____

Tested By: _____

Date: _____

SAMPLE #		1	2	3
Mass of SSD Sample + Basket in Air				
Less Mass of Basket in Air				
Mass of SSD Sample	B			
Mass of Saturated Sample in Water + Basket in Water				
Less Mass of Basket in Water				
Mass of Saturated Sample in Water	C			
Mass of SSD Sample	B			
Less Mass of Saturated Sample in Water	C			
Loss in Mass (Volume of SSD Sample)	B - C			

Mass of Oven-Dry Sample + Pan				
Less Mass of Pan				
Mass of Oven-Dry Sample in Air	A			

Mass of SSD Sample in Air	B			
Less Mass of Oven-Dry Sample	A			
Mass of Water (Volume of Permeable Voids)	B - A			

Mass of Oven-Dry Sample	A			
Less Mass of Saturated Sample in Water	C			
Loss in Mass (Volume of Oven-Dry Sample)	A - C			

Bulk Specific Gravity	A			
	B - C			
Bulk Specific Gravity (SSD Basis)	B			
	B - C			
Apparent Specific Gravity	A			
	A - C			
Absorption %	B - A			
	A x 100			

**Connecticut Department of Transportation - Division of Materials Testing
Fine Aggregate Soundness Worksheet T104/C88 - MAT-220**

Kind of Material:	Source:	Tech/Eng. Initials:
Date Sampled:	Location:	Date Completed:

Original Grading (Plus #4)				Sample Sizes For Original Grading			Soak - Dry Schedule																																										
Sieve In(mm)	Retained Mass	Pass & Ret. %	% Pass	Note:			Date in Sol.	Time	Date in oven																																								
			100																																														
1/2 (12.5)				<table border="1"> <thead> <tr> <th colspan="3">Grading of Original Sample</th> </tr> <tr> <th>Pass</th> <th>Ret. On</th> <th></th> </tr> </thead> <tbody> <tr> <td>3/8 (9.5)</td> <td>#4 (4.75)</td> <td>%</td> </tr> <tr> <td>#4 (4.75)</td> <td>#8 (2.36)</td> <td>%</td> </tr> <tr> <td>#8 (2.36)</td> <td>#16 (1.18)</td> <td>%</td> </tr> <tr> <td>#16 (1.18)</td> <td>#30 (600 μ)</td> <td>%</td> </tr> <tr> <td>#30 (600 μ)</td> <td>#50 (300 μ)</td> <td>%</td> </tr> <tr> <td>Totals</td> <td></td> <td>100</td> <td></td> <td align="center" colspan="3">Total</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td align="center" colspan="3">100</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>			Grading of Original Sample			Pass	Ret. On		3/8 (9.5)	#4 (4.75)	%	#4 (4.75)	#8 (2.36)	%	#8 (2.36)	#16 (1.18)	%	#16 (1.18)	#30 (600 μ)	%	#30 (600 μ)	#50 (300 μ)	%	Totals		100		Total										100							
Grading of Original Sample																																																	
Pass	Ret. On																																																
3/8 (9.5)	#4 (4.75)	%																																															
#4 (4.75)	#8 (2.36)	%																																															
#8 (2.36)	#16 (1.18)	%																																															
#16 (1.18)	#30 (600 μ)	%																																															
#30 (600 μ)	#50 (300 μ)	%																																															
Totals		100		Total																																													
				100																																													
#8 (2.36)																																																	
#16 (1.18)																																																	
#30 (600 μ)																																																	
#50 (300 μ)																																																	
Totals		100																																															

(Required Sample Not Less Than 100g For Each Size)

Passing	Retained	Actual Mass	Mass Before Test Grams.	Mass After Test Grams.	Loss in Grams	Loss in %	Grading of Orig. Sample	Weighted Average %
3/8 (9.5)	#4 (4.75)							
#4 (4.75)	#8 (2.36)							
#8 (2.36)	#16 (1.18)							
#16 (1.18)	#30 (600 μ)							
#30 (600 μ)	#50 (300 μ)							

**Connecticut Department of Transportation - Division of Materials Testing
Coarse Aggregate Soundness Worksheet T104/C88 - MAT-221**

Kind of Material:	Source:	Tech/Eng. Initials:
Date Sampled:	Location:	Date Completed:

Original Grading (Plus #4)				Sample Sizes For Original Grading		Soak - Dry Schedule		
Sieve In(mm)	Retained Mass	Pass & Ret. %	% Pass	#	lbs. (kg)	Date in Sol.	Date	Date in oven
			100	#	lbs. (kg)			
2 ½ (63)				#	lbs. (kg)			
2 (50)				#	lbs. (kg)			
1 ½ (37.5)				#	lbs. (kg)			
1 (25)				Total	lbs. (kg)			
¾ (19)				Grading of Original Sample				
½ (12.5)				Pass	Ret. On			
⅜ (9.5)				2 ½ (63)	1 ½ (37.5)			
# 4 (4.75)				1 ½ (37.5)	¾ (19)			
Totals		100		¾ (19)	⅜ (9.5)			
				⅜ (9.5)	# 4 (4.75)			

Total 100

Sieve Size	Not Less Than	Consisting of	Actual Mass	Mass Before Test Grams.	Mass After Test Grams.	Loss in Grams	Loss in %	Grading of Orig. Sample	Weighted Average %
2 ½ to 1 ½ (63) (37.5)	5000	3000 2 (50)							
		2000 1 ½ (37.5)							
1 ½ to ¾ (37.5) (19)	1500	1000 1 (25)							
		500 ¾ (19)							
¾ to ⅜ (19) (9.5)	1000	670 ½ (12.5)							
		330 ⅜ (9.5)							
⅜ to # 4 (9.5) (4.75)	300	300 # 4 (4.75)							

**CONNECTICUT DEPARTMENT OF TRANSPORTATION
 DIVISION OF MATERIALS TESTING
 ASSURANCE REPORT: FIELD TESTING PERSONNEL AND
 EQUIPMENT
 MAT-222**

Project Number:	Date:
-----------------	-------

Location:

Inspected By:	<input type="checkbox"/> Consultant	<input type="checkbox"/> State
---------------	-------------------------------------	--------------------------------

Name of Inspector(s) Certification(s) (NETTCP, ACI, Etc.) and Certification #s

Required Testing Equipment			
<input type="checkbox"/>	Air Meter	<input type="checkbox"/>	Thermometer
<input type="checkbox"/>	Slump Cone	<input type="checkbox"/>	Small Tools (scoops, measures, etc.)
<input type="checkbox"/>	Tamping Rod (24" ok for all)	<input type="checkbox"/>	Sampling Receptacle
<input type="checkbox"/>	Strike Off Bar (1/8 x 3/4 x 12)	<input type="checkbox"/>	Cylinder Curing Box (operating to manufacturer specs)
<input type="checkbox"/>	Mallet (1.25 ± .5 lbs)		

Air Meter Calibration Date:

Remarks/Observations

Form Completed By	District lab
-------------------	--------------

**CONNECTICUT DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING
ASSURANCE REPORT
PLASTIC PC CONCRETE - MAT-224**

DATE:	PROJECT NUMBER:
CLASS OF CONCRETE:	PROJECT LOCATION:
TRUCK NUMBER:	CONCRETE PRODUCER:
CYLINDER NUMBERS:	PRODUCER LOCATION:
MIX TEMP. (T309/C1064): o	NOTE: COMPLETED MAT 222 MUST BE ATTACHED TO THIS REPORT

BATCH MASS PER CUBIC METER								
	CEMENT lb.	OTHER lb.	SAND + _____ % Moisture lb.	STONE lb.	STONE lb.	STONE lb.	TOTAL MIXING WATER lb.	TOTAL MASS lb.
ACTUAL								
MIX DESIGN								
TOLERANCE	± 1%	± 1%	± 2%	± 2%	± 2%	± 2%	± 1% (Central Mix)	

AIR TEST (T152/C231) (side by side check of test equip. required)				SLUMP TEST (T119/C143)		
TIME TAKEN	PROJECT TEST RESULTS	TIME TAKEN	COMPARISON TEST RESULTS	TIME TAKEN	TOTAL WATER PER BATCH (gal.)	AMOUNT OF SLUMP
	% air		% air			
TOLERANCE – results should not differ by more than 1 %						

UNIT MASS (T121/C138)					
		-	=	÷	=
TIME TAKEN	MASS OF MEASURE & SAMPLE lb.	MASS OF MEASURE lb.	NET MASS OF CONCRETE lb.	VOLUME OF MEASURE (ft ³)	MASS PER CUBIC METER lb./ ft ³

YIELD (T121/C138)							
		÷	=	÷	=	÷	=
TIME TAKEN	TOTAL BATCH WEIGHT lb.	UNIT WEIGHT lb./ ft ³	YIELD PER BATCH (ft ³ / batch)	BATCH SIZE (y ³)	YIELD PER CUBIC YARD (ft ³ / y ³)		RELATIVE YIELD
						27	

Witnessed By (Print Name)	Project Inspector (Print Name)
Signature	Signature

**CONNECTICUT DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING
ASSURANCE REPORT
PLASTIC PC CONCRETE (METRIC) - MAT-225**

DATE	PROJECT NUMBER:
CLASS OF CONCRETE	PROJECT LOCATION:
TRUCK NUMBER	CONCRETE PRODUCER:
CYLINDER NUMBERS	PRODUCER LOCATION:
MIX TEMP. (T309/C1064) °	NOTE: COMPLETED MAT 222 MUST BE ATTACHED TO THIS REPORT

BATCH MASS PER CUBIC METER								
	CEMENT kg	OTHER kg	+ SAND % Moisture kg	STONE kg	STONE kg	STONE kg	TOTAL MIXING WATER kg	TOTAL MASS kg
ACTUAL								
MIX DESIGN								
TOLERANCE	± 1%	± 1%	± 2%	± 2%	± 2%	± 2%	± 1% (Central Mix)	

AIR TEST (T152/C231) (side by side check of test equip.)				SLUMP TEST (T119/C143)		
TIME TAKEN	PROJECT TEST RESULTS	TIME TAKEN	COMPARISON TEST RESULTS	TIME TAKEN	TOTAL WATER PER BATCH (L)	AMOUNT OF SLUMP
	% air		% air			
TOLERANCE – results should not differ by more than 1 %						

UNIT MASS (T121/C138)					
		-	=	÷	=
TIME TAKEN	MASS OF MEASURE & SAMPLE kg	MASS OF MEASURE kg	NET MASS OF CONCRETE kg	VOLUME OF MEASURE (m ³)	MASS PER CUBIC METER kg / m ³

YIELD (T121/C138)					
		÷	=	÷	=
TIME TAKEN	TOTAL MASS OF BATCH kg	MASS PER CUBIC METER kg / m ³	YIELD PER BATCH (m ³ / batch)	BATCH SIZE (m ³)	RELATIVE YIELD

Witnessed By (Print Name)	Project Inspector (Print Name)
----------------------------------	---------------------------------------

Signature	Signature
-----------	-----------

Glass Beads

Grams	% Passing	Moisture Resistance
# 20		Imperfect Wt
# 30		Round Wt
# 40		% Perfect
# 50		Refractive index
# 80		Date
# 100		Analyst
Pan		Project #
Totals		Sample ID #

Specification Reference

Standard/Project Specification _____

Supplemental Specification _____

Other _____

Person Accepting Technical Responsibility

Name: _____

Title: _____

Specifications: AASHTO M 247 Type 1 (via Form 815 M.07.03), and Federal Specification TT-8-1325C (contract for glass beads) Methods: In accordance with above specifications.	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Glass Beads MAT-228	Date	Project #	
			Sample ID #	
Lab use only	% Passing	Type 1A	Type 1B	Results
Material #	# 20	100	----	-----
Vendor #	# 30	75 – 95	100	-----
Date Sampled	# 40	----	90 – 100	-----
Destination Code	# 50	15 – 35	50 - 75	-----
Material Quantity	# 80	----	0 - 5	-----
Material Unit	# 100	0 – 5	----	-----
Date Received	% Perfect		> 70%	-----
Batch #	Moisture Resistance			-----
C or M	Refractive Index		> 1.50	-----
Dates	Person Performing Test (initials) : _____			
	Recommended For	Remarks		
Division of Materials Testing				

Visi Beads

	% Retained	Project #
# 10		Sample ID #
# 12		Date
# 14		Analyst
# 16		
# 18		
# 20		
pan		

Specification Reference

Standard Specification _____

Supplemental Specification _____

Project Specification _____

Other _____

Person Accepting Technical Responsibility

Name: _____

Title: _____

Specifications: Form 815 M.07.22, Specification for Large Beads (via contract for glass beads), and Reference File 199 – (beads for epoxy resin pavement markings). Methods: In accordance with above specifications. Lab use only	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Visi Beads MAT-229	Date	Project #																								
			Sample ID #																								
Material # Vendor # Date Sampled Destination Code Material Quantity Material Unit Date Received C or M Dates ----	<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 25%;"><u>% Retained</u></th> <th style="width: 25%;"><u>Specs.</u></th> <th style="width: 50%;"><u>Results</u></th> </tr> </thead> <tbody> <tr> <td>#10</td> <td style="text-align: center;">0</td> <td style="text-align: center;">-----</td> </tr> <tr> <td># 12</td> <td style="text-align: center;">0 – 5</td> <td style="text-align: center;">-----</td> </tr> <tr> <td># 14</td> <td style="text-align: center;">5 – 20</td> <td style="text-align: center;">-----</td> </tr> <tr> <td># 16</td> <td style="text-align: center;">40 – 80</td> <td style="text-align: center;">-----</td> </tr> <tr> <td>#18</td> <td style="text-align: center;">10 – 40</td> <td style="text-align: center;">-----</td> </tr> <tr> <td># 20</td> <td style="text-align: center;">0 – 5</td> <td style="text-align: center;">-----</td> </tr> <tr> <td>Pan</td> <td style="text-align: center;">0 – 2</td> <td style="text-align: center;">-----</td> </tr> </tbody> </table>	<u>% Retained</u>	<u>Specs.</u>	<u>Results</u>	#10	0	-----	# 12	0 – 5	-----	# 14	5 – 20	-----	# 16	40 – 80	-----	#18	10 – 40	-----	# 20	0 – 5	-----	Pan	0 – 2	-----	Person Performing Test (initials) : _____	
<u>% Retained</u>	<u>Specs.</u>	<u>Results</u>																									
#10	0	-----																									
# 12	0 – 5	-----																									
# 14	5 – 20	-----																									
# 16	40 – 80	-----																									
#18	10 – 40	-----																									
# 20	0 – 5	-----																									
Pan	0 – 2	-----																									
	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">Recommended For</td> <td>Remark</td> </tr> <tr> <td style="height: 40px;"></td> <td></td> </tr> </table>	Recommended For	Remark																								
Recommended For	Remark																										
Division of Materials Testing																											

Water

Appearance	Color
pH	Water Factor
ml Silver Nitrate	Chlorides
Project #	Sample ID #
Date	Analyst

Specification Reference

Standard Specification _____

Supplemental Specification _____

Project Specification _____

Other _____

Person Accepting Technical Responsibility

Name: _____

Title: _____

<p>Specification: Form 815 M.03.01-4 Methods: In accordance with AASHTO T26</p> <p>Note: If tests indicate unfavorable results, further testing may be required. (T107, T131, or T154 and T106, or other recommended tests in cooperation with Concrete/Steel Section)</p>	<p>State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Water MAT-230</p>	<p>Date</p>	<p>Project #</p>	
			<p>Sample ID #</p>	
	<p>Appearance _____</p> <p>Color _____</p> <p>pH (T26, range 4.5 – 8.5) _____</p> <p>Chloride Ion Concentration (D512) _____</p> <p style="text-align: right; margin-top: 20px;">Person Performing Test (initials) : _____</p>			
		<p>Recommended For</p>	<p>Remarks</p>	
<p>Division of Materials Testing</p>				

White & Yellow Fast Dry, Solvent Based Pavement Markings

Color (Fed. 595 – 33538)	Dry times (ASTM D 711)	% Pigment (ASTM D 3720)
Contrast Ratio (Fed. Test 141-4121))	Direct Reflect. (Fed. Ref. 141-6121)	1 _____ (100) =
Viscosity @ 77 (ASTM D 562)	Weight /Gal (ASTM D 1475)	2 _____ (100) =

Specification Reference

Standard Specification _____

Supplemental Specification _____

Project Specification _____

Other _____

Person Accepting Technical Responsibility

Name: _____

Title: _____

Specification: M.07.21 (814A) for 3 minute dry paint Method: FTMS #141 Material # _____ Vendor # _____ Date Sampled _____ Destination Code _____ Material Quantity _____ Material Unit _____ Date Received _____ Batch # _____ C or M _____ Dates -----	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of White & Yellow Fast Dry Solvent Based Pavement Markings MAT-235	Date	Project #																																
	Sample ID #																																		
	<table style="width: 100%; border-collapse: collapse;"> <tr> <td></td> <td style="text-align: center;">White</td> <td style="text-align: center;">Yellow</td> <td></td> </tr> <tr> <td style="text-align: right;">Viscosity</td> <td style="text-align: center;">80 – 100 KU</td> <td style="text-align: center;">80 – 100 KU</td> <td style="text-align: right;">_____</td> </tr> <tr> <td style="text-align: right;">Dry Time</td> <td style="text-align: center;">- 3 min.</td> <td style="text-align: center;">3 min.</td> <td style="text-align: right;">_____</td> </tr> <tr> <td style="text-align: right;">Direct Reflectance</td> <td style="text-align: center;">85% +</td> <td style="text-align: center;">50 % +</td> <td style="text-align: right;">_____</td> </tr> <tr> <td style="text-align: right;">Color</td> <td></td> <td style="text-align: center;">Visual</td> <td style="text-align: right;">_____</td> </tr> <tr> <td style="text-align: right;">Contrast Ratio</td> <td style="text-align: center;">0.96 +</td> <td style="text-align: center;">0.96 +</td> <td style="text-align: right;">_____</td> </tr> <tr> <td style="text-align: right;">Weight/Gal</td> <td style="text-align: center;">11.8 +</td> <td style="text-align: center;">11.8 +</td> <td style="text-align: right;">_____</td> </tr> <tr> <td style="text-align: right;">% Pigment</td> <td style="text-align: center;">55% +</td> <td style="text-align: center;">55% +</td> <td style="text-align: right;">_____</td> </tr> </table>		White	Yellow		Viscosity	80 – 100 KU	80 – 100 KU	_____	Dry Time	- 3 min.	3 min.	_____	Direct Reflectance	85% +	50 % +	_____	Color		Visual	_____	Contrast Ratio	0.96 +	0.96 +	_____	Weight/Gal	11.8 +	11.8 +	_____	% Pigment	55% +	55% +	_____		
	White	Yellow																																	
Viscosity	80 – 100 KU	80 – 100 KU	_____																																
Dry Time	- 3 min.	3 min.	_____																																
Direct Reflectance	85% +	50 % +	_____																																
Color		Visual	_____																																
Contrast Ratio	0.96 +	0.96 +	_____																																
Weight/Gal	11.8 +	11.8 +	_____																																
% Pigment	55% +	55% +	_____																																
	Person Performing Test (initials) : _____																																		
	Recommended For	Remarks																																	
Division Chief – Division of Materials Testing																																			

White & Yellow Regular Dry Solvent Based Pavement Markings

Weight/Gal <small>(ASTM D 1475)</small>	Viscosity @ 77 <small>(ASTM D 562)</small>	% Pigment <small>(ASTM D 3720)</small>
Direct Reflect. <small>(Fed. Ref. 141-6121)</small>	Contrast Ratio <small>(Fed. Test 141-4121)</small>	1 _____ (100) =
Dry times <small>(ASTM D 711)</small>	Color <small>(Fed. 595 – 33538)</small>	2 _____ (100) =

Specification Reference

Standard Specification _____
 Supplemental Specification _____
 Project Specification _____
 Other _____
 Person Accepting Technical Responsibility
 Name: _____
 Title: _____

Specification: M.07.20 (814A) for 15 minute dry paint Method: FTMS #141 Material # _____ Vendor # _____ Date Sampled _____ Destination Code _____ Material Quantity _____ Material Unit _____ Date Received _____ Batch # _____ C or M _____ Dates -----	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of White & Yellow Regular Dry Solvent Based Pavement Markings MAT-236	Date _____	Project # _____																						
	<table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 30%; text-align: center; padding: 5px;">White</td> <td style="width: 30%; text-align: center; padding: 5px;">Yellow</td> <td style="width: 40%;"></td> </tr> <tr> <td style="padding: 5px;">Viscosity</td> <td style="padding: 5px;">70 – 80 KU</td> <td style="padding: 5px;">70 – 80 KU _____</td> </tr> <tr> <td style="padding: 5px;">Dry Time</td> <td style="padding: 5px;">- 15 min.</td> <td style="padding: 5px;">15 min. _____</td> </tr> <tr> <td style="padding: 5px;">Direct Reflectance</td> <td style="padding: 5px;">85% +</td> <td style="padding: 5px;">50 % + _____</td> </tr> <tr> <td style="padding: 5px;">Color</td> <td style="padding: 5px;">Visual</td> <td style="padding: 5px;">Visual _____</td> </tr> <tr> <td style="padding: 5px;">Contrast Ratio</td> <td style="padding: 5px;">0.96 +</td> <td style="padding: 5px;">0.96 + _____</td> </tr> <tr> <td style="padding: 5px;">Weight/Gal</td> <td style="padding: 5px;">12.8 +</td> <td style="padding: 5px;">11.4 + _____</td> </tr> <tr> <td style="padding: 5px;">% Pigment</td> <td style="padding: 5px;">50% +</td> <td style="padding: 5px;">50% + _____</td> </tr> </table>	White	Yellow		Viscosity	70 – 80 KU	70 – 80 KU _____	Dry Time	- 15 min.	15 min. _____	Direct Reflectance	85% +	50 % + _____	Color	Visual	Visual _____	Contrast Ratio	0.96 +	0.96 + _____	Weight/Gal	12.8 +	11.4 + _____	% Pigment	50% +	50% + _____
White	Yellow																								
Viscosity	70 – 80 KU	70 – 80 KU _____																							
Dry Time	- 15 min.	15 min. _____																							
Direct Reflectance	85% +	50 % + _____																							
Color	Visual	Visual _____																							
Contrast Ratio	0.96 +	0.96 + _____																							
Weight/Gal	12.8 +	11.4 + _____																							
% Pigment	50% +	50% + _____																							
		Person Performing Test (initials) : _____																							
	Recommended For	Remarks																							

Division Chief – Division of Materials Testing

Fast Dry White & Yellow Waterborne Paint

% Non Volatile (ASTM D 2697) 1 _____ _____ (100) = 2 _____ _____ (100) =	% Pigment (ASTM D 3723) 1 _____ (100)= 2 _____ (100)= Avg. _____	Color test (595-33538 yellow) Flash Point (Ref. 200G) Flexibility (Fed Test 141c-6223) Dry Opacity (Fed. Test 141c-4121) Wt/Gal @ 77 (ASTM D 1475) (X)(0.10) = lbs/gal cup – cup & sample = X	Scrub Resist. (ASTM D 2486) Dry times (ASTM D 711) Viscosity @ 77 (ASTM D 562)
---	--	---	---

Specification Reference

Standard Specification _____
 Supplemental Specification _____
 Project Specification _____
 Other _____
 Person Accepting Technical Responsibility
 Name: _____
 Title: _____

Specification: M.07.21 (Note: for next maintenance contract review delete reference file 200 and refer to M.07.21 as the spec) Method: FTMS #141 Material # _____ Vendor # _____ Date Sampled _____ Destination Code _____ Material Quantity _____ Material Unit _____ Date Received _____ Batch # _____ C or M _____ Dates -----	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Fast Dry White & Yellow Waterborne Paint MAT-239	Date _____	Project # _____	Sample ID # _____
	Viscosity (80 – 90 KU) _____ Flexibility (NO Flaws) _____ Weight/Gal. (12.5 +) _____ Dry Opacity (0.96 +) _____ Nonvolatile (76% +) _____ Flash Point (145°F+) _____	Dry Time (-120 sec) _____ Color (visual) _____ Lead (-0.06%) _____ Pigment (58-63) _____ Scrub Resistance (500+) _____	Person Performing Test (initials) : _____	
	Recommended For _____	Remarks _____		

Division of Materials Testing

Regular Dry White & Yellow Waterborne Paint

% Non Volatile (ASTM D 2697) 1 _____ 2 _____ _____ _____ (100) = _____ (100) =	% Pigment (ASTM D 3723) 1 _____ (100)= 2 _____ (100)=	Color test (595-13538 yellow) Flexibility (Fed Test 141c-6223) Flash Point (Ref. 207) Dry times (ASTM D 711)
Wt/Gal @ 77 (ASTM D 1475) (X)(0.10) = _____ lbs/gal cup – cup & sample = X	Viscosity @ 77 (ASTM D 562) Dry Opacity (Fed. Test 141c-4121)	

Specification Reference

Standard Specification _____
 Supplemental Specification _____
 Project Specification _____
 Other _____
 Person Accepting Technical Responsibility
 Name: _____
 Title: _____

Specification: M.07.20 (Note: for next maintenance contract review delete reference file 207 and refer to M.07.20 as the spec) Method: FTMS #141 Material # _____ Vendor # _____ Date Sampled _____ Destination Code _____ Material Quantity _____ Material Unit _____ Date Received _____ Batch # _____ C or M _____ Dates -----	State of Connecticut Department of Transportation Bureau of Engineering & Construction Report of Test of Regular Dry White & Yellow Waterborne Paint MAT-240	Date _____	Project # _____
	Sample ID # _____		
	Viscosity (75 – 85 KU) _____ Flexibility (NO Flaws) _____ Weight/Gal. (12.5 +) _____ Dry Opacity (0.96 +) _____ Nonvolatile (70% +) _____ Flash Point (145°F+) _____ Scrub Resistance (500+) _____	Dry Time (-15 min) _____ Color (visual) _____ Dry Time (-15 min) _____ Lead (-0.06%) _____ Pigment (50-60) _____ Freeze/Thaw (+8 can) _____ Freeze/Thaw (-10KU) _____	
	Person Performing Test (initials): _____		
	Recommended For _____	Remarks _____	
Division of Materials Testing			

**State of Connecticut Department of Transportation
 Division of Materials Testing MAT-241
 Independent Assurance Program Evaluation Report
 Concrete Aggregates – Fine Aggregates**

Purpose: This form is for evaluation of assurance testing of concrete aggregates. In accordance with the minimum requirements for testing, concrete aggregates are sampled and tested for acceptance purposes randomly on a bi-weekly basis, and assurance testing of these processes is required each ten tests. This assurance testing evaluates in-house (not directly related to the projects) sample reducing and gradation analysis of concrete aggregates tested at various satellite locations utilizing various equipment and personnel. See MAT 245 for assurance testing criteria.

Assurance Testing Period (Dates): From: _____ To: _____			
Number of assurance tests performed.	Number of assurance tests not meeting assurance criteria.	Percentage of assurance tests not meeting assurance criteria.	Was corrective action taken and noted for tests not meeting criteria?
District II Lab			
District III Lab			
District IV Lab			
Totals for Concrete Aggregate Assurance Testing in the Period			

NOTES: _____

**State of Connecticut Department of Transportation
 Division of Materials Testing MAT-242
 Independent Assurance Program Evaluation Report
 Concrete Aggregates – Coarse Aggregates**

Purpose: This form is for evaluation of assurance testing of concrete aggregates. In accordance with the minimum requirements for testing, concrete aggregates are sampled and tested for acceptance purposes randomly on a bi-weekly basis, and assurance testing of these processes is required each ten tests. This assurance testing evaluates in-house (not directly related to the projects) sample reducing and gradation analysis of concrete aggregates tested at various satellite locations utilizing various equipment and personnel. See MAT 245 for assurance testing criteria.

Assurance Testing Period (Dates): From: _____ To: _____			
Number of assurance tests performed.	Number of assurance tests not meeting assurance criteria.	Percentage of assurance tests not meeting assurance criteria.	Was corrective action taken and noted for tests not meeting criteria?
District II Lab			
District III Lab			
District IV Lab			
Totals for Concrete Aggregate Assurance Testing in the Period			

NOTES: _____

**State of Connecticut Department of Transportation
 Division of Materials Testing MAT-243
 Independent Assurance Program Evaluation Report
 Subbase and Processed Aggregate Base**

Purpose: This form is for evaluation of assurance testing of Subbase and Processed Aggregate Base. In accordance with the minimum requirements for testing, roadbase aggregates are sampled and tested for acceptance and assurance processes. To meet project related minimum testing requirements, project personnel notify the District Laboratories for required acceptance and assurance testing of these materials. The process starts at the project site, where laboratory personnel witness and critique the sampling procedure at the site. Laboratory acceptance testing is then performed and split samples are sent to the Central Laboratory for in-house (not directly related to the projects) assurance testing, which evaluates sample reducing and gradation analysis of the materials tested at various satellite locations utilizing various equipment and personnel. See MAT 245 for assurance testing criteria.

Assurance Testing Period (Dates): From: To:			
Number of assurance tests performed.	Number of assurance tests not meeting assurance criteria.	Percentage of assurance tests not meeting assurance criteria.	Was corrective action taken and noted for tests not meeting criteria?
District II Lab			
District III Lab			
District IV Lab			
Totals for Subbase & Processed Aggregate Base Assurance Testing in the Period			

NOTES: _____

**State of Connecticut Department of Transportation
 Division of Materials Testing MAT-244
 Independent Assurance Program Evaluation Report
 Plastic PC Concrete**

Purpose: This form is for evaluation of assurance testing of plastic PC concrete. In accordance with the minimum requirements for testing, plastic PC concrete is required to be sampled and tested by project personnel for required acceptance and assurance testing. After notifying project staff of the need for required assurance testing, laboratory personnel evaluate the sampling and testing procedure, verify that adequate and calibrated testing equipment is utilized and readily available, and verify use of qualified personnel for NHS projects. Side-by-side air content testing is performed to validate project test equipment. When requested, technical expertise is also provided to the project personnel during the subject assurance testing. Forms MAT 222 and MAT 224 (MAT 225 for metric projects) are required to be completed by laboratory personnel during the assurance testing, and if testing deficiencies are encountered, they are noted. NOTES: 1) This form does not evaluate the projects on an individual basis for conformance to minimum acceptance and assurance testing requirements as specified in the "Schedule of Minimum Requirements for Sampling Materials for Test." As stated above, this form is for evaluation of the assurance testing of plastic PC concrete. 2) Comparison concrete specimens are not required to be fabricated by laboratory personnel during the assurance test.

Assurance Testing Period (Dates):		From:	To:
Number of assurance tests performed.	Number of assurance tests noting any testing deficiencies.	Percentage of assurance tests noting testing deficiencies.	Was the project notified via memorandum of any testing deficiencies?
District I Lab			
District II Lab			
District III Lab			
District IV Lab			
Totals for Plastic PC Concrete Assurance Testing in the Period			

NOTES: _____

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
BUREAU OF ENGINEERING AND CONSTRUCTION
DIVISION OF MATERIALS TESTING
MAT-245

AGGREGATE ASSURANCE SAMPLES – VARIATION LIMITS

If assurance samples tested at the Central Laboratory vary from the samples tested at the District Laboratories by more than the percent shown below, the cause of the variations shall be investigated. These limits were derived from historical experience, along with engineering expertise.

NO. 4 AGGREGATE		NO. 6 AGGREGATE		NO. 67 AGGREGATE		NO. 8 AGGREGATE	
37.5 mm (1 1/2")	- 4.0	19.0 mm (3/4")	- 4.0	19.0 mm (3/4")	- 4.0	9.5 mm (3/8")	- 5.0
25.0 mm (1")	- 9.0	12.5 mm (1/2")	- 6.0	9.5 mm (3/8")	- 3.0	4.75 mm (#4)	- 5.0
19.0 mm (3/4")	- 6.0	9.5 mm (3/8")	- 3.0	4.75 mm (#4)	- 3.0	2.36 mm (#8)	- 3.0
9.5 mm (3/8")	- 3.0	4.75 mm (#4)	- 3.0	2.36 mm (#8)	- 3.0	1.18 mm (#16)	- 3.0

CONCRETE SAND		SUBBASE		PROCESSED AGGREGATE BASE	
4.75 mm (#4)	- 3.0	37.5 mm (1 1/2")	- 6.0	19.0 mm (3/4")	- 6.0
2.36 mm (#8)	- 6.0	6.3 mm (1/4")	- 6.0	6.3 mm (1/4")	- 6.0
1.18 mm (#16)	- 10.0	2.0 mm (#10)	- 6.0	425 µm (#40)	- 5.0
600 µm (#30)	- 10.0	425 µm (#40)	- 5.0	150 µm (#100)	-4.0
300 µm (#50)	- 9.0	150 µm (#100)	- 4.0		
150 µm (#100)	- 4.0	75 µm (#200)	- 3.0		
F.M. – 0.40 SILT – 1.5					

**CONNECTICUT DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING (DMT)
TRACKING REPORT: PAVEMENT MARKING MATERIALS**

MAT-248

Rev. 11/16

Date:

Company:

Material:

Batch/ Lot #	Quantity


Remarks/Observations:

DMT Tracking Number: DMT XXXXXXXX


Form Completed By:

Recommendation Made For This Material: <small>Choose an item.</small>
--


MAT-300



GALVANIZATION oz/ft ² (g/m ²)		
BOLT	NUT	WASHER
Mils (μm)	Mils (μm)	Mils (μm)
SUM		
AVE.		
AVE x 1.7 (AVE x7.067)		



THK. =




THK. =


PROJECT NUMBER:	MAT-300 STATE OF CT D.O.T. DIV. OF MATERIALS TESTING REPORT OF TEST: ANCHOR BOLTS (STRAIGHT)	DATE		MATERIAL CODE 3504	
SAMPLE NUMBER:		LAB #			
<u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION _____ SUPPLEMENTAL SPECIFICATION _____ PROJECT SPECIAL PROVISION _____ OTHER _____ PERSON ACCEPTING _____ <u>TECHNICAL RESPONSIBILITY</u> NAME : _____ TITLE: _____	ITEM	BOLT	SPEC.	NUT	WASHER
	SIZE (Nom. Dia.)				
	GRADE				
	AREA in ² (mm ²)				
	HARDNESS				
	EST. T.S. psi (MPa)				
	GALV. oz/ft ² (g/m ²)				
	Begin Test	End Test	Tested By	REMARKS	
	Recommendations				

DIVISION CHIEF – MATERIALS TESTING


MAT-301



GALVANIZATION oz/ft ² (g/m ²)		
BOLT	NUT	WASHER
Mils (μm)	Mils (μm)	Mils (μm)
SUM		
AVE.		
AVE x 1.7 (AVE x 7.067)		



THK. =



THK. =

PROJECT NUMBER:	MAT-301 STATE OF CT D.O.T. DIV. OF MAT. TESTING	DATE	MATERIAL CODE		
SAMPLE NUMBER:	REPORT OF TEST: ANCHOR BOLTS (WITH HOOK)	LAB #	3504		
<u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION _____ SUPPLEMENTAL SPECIFICATION _____ PROJECT SPECIAL PROVISION _____ OTHER _____ PERSON ACCEPTING _____ <u>TECHNICAL RESPONSIBILITY</u> NAME: _____ TITLE: _____	ITEM	BOLT	SPEC.	NUT	WASHER
	SIZE (Nom. Dia.)				
	GRADE				
	AREA in ² (mm ²)				
	HARDNESS				
	EST. T.S. PSI (MPa)				
	GALV. Oz/ft ² (g/m ²)				
	RECOMMENDED FOR	REMARKS			
c:\jwh\forms\Anchor Bolt with Hook combo.doc					
DIVISION CHIEF – MATERIALS TESTING					

MAT-303

PROJECT NUMBER:	MAT-303 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CHAIN LINK FENCE FABRIC	PROCESSING DATE	MATERIAL CODE 3300	
SAMPLE NUMBER:		LABORATORY NO.		
<div style="display: flex; justify-content: space-between;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);"> <u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION SUPPLEMENTAL SPECIFICATION PROJECT SPECIAL PROVISION OTHER </div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);"> PERSON ACCEPTING <u>TECHNICAL RESPONSIBILITY</u> NAME: _____ TITLE: _____ </div> </div>		Actual	Specification	
	Height of Fabric, inches (mm)			As specified on plans or spec. prov.
	Gage of Wire			No. 9 gage
	Size of Mesh, inches (mm)			2-inch (50 mm) mesh
	Edge of Finish			Knuckled
	Tensile Strength, psi (MPa)			See above
	Weight of Coating, oz/ft ² (g/m ²)			See above
	BEGIN DATE	END DATE	TESTED BY	REMARKS
	RECOMMENDATION			
	DIVISION CHIEF – MATERIALS TESTING			

MAT-304 REPORT OF TEST: REINFORCED CONCRETE PIPE
(Reduced for inclusion in manual)

Source and Location of Fine Aggregate Supply:																					
Source and Location of Coarse Aggregate Supply:																					
Tests Witnessed by:																					
Machine Readings																					
RCP	RCP	RCP	RCP	Slot	Method of	Date	Date	Age	Req'd	Req'd	Req'd	Actual	Actual	Actual	Actual	Core	Absp.	Req'd Reinf.	Actual Reinf.	Remarks	Status
Size	Length	Class	Wall		Manufacture	Cast	Broken		.01Crack	.01+10%	Ultimate	Visible	.01Crack	.01+10%	Ultimate			(in ² /ft)	(in ² /ft)		
(in.)	(ft)			(Y/N)				(days)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(lbs.)	(Y/N)	(%)	i o	i o		

PROJECT NUMBER:	MAT-305		DATE	MATERIAL CODE		
SAMPLE NUMBER:	STATE OF CONNECTICUT DEPT. OF TRANSPORTATION DIV. OF MATERIALS TESTING REPORT OF TEST: STEEL BARS AND SHAPES		LAB #			
<u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION _____ SUPPLEMENTAL SPECIFICATION _____ PROJECT SPECIAL PROVISION _____ OTHER _____ PERSON ACCEPTING _____ <u>TECHNICAL RESPONSIBILITY</u> NAME : _____ TITLE: _____	Size					
	Grade					
	Area, in ² (mm ²)					
	Load, lbf (kN)					
	Y.P., psi (MPa)					
	Load, lbf (kN)					
	T.S., psi (MPa)					
	Elong. (%)					
	Cold Bend					
	Epox, mils (µm)					
	Test No.					
	Begin Test	End Test	Tested By	REMARKS		
	Recommendations					
	DIVISION CHIEF – MATERIALS TESTING					

MAT-306

Tables From ASTM A 82 Steel Wire, Plain, For Concrete Reinforcement

Table 1 Tension Test Requirements	
Tensile strength, min, ksi (MPa)	80 (550)
Yield strength, min, ksi (MPa)	70 (485)
Reduction of area, min, %	30 ⁴

⁴For material testing of 100 ksi (690 MPa) tensile strength, the reduction of area shall be not less than 25%.

Table 2 Tension Test Requirements (Material for Welded Wire Reinforcement)		
	Size W1.2 and Larger	Smaller than Size W1.2
Tensile strength based on wire nom. area, min, ksi (MPa)	75 (515)	70 (485)
Yield strength based on wire nom. Area, min, ksi (MPa)	65 (450)	56 (385)
Reduction of area, min, %	30 ⁴	30 ⁴

⁴For material testing over 100 ksi (690 MPa) tensile strength, the reduction of area shall be not less than 25 %.

Table 4 Permissible Variation in Wire Diameter		
Size Number	Nominal Diameter, in. (mm)	Permissible Variation Plus and Minus, in. (mm)
Smaller than W5	Under 0.252 (6.40)	0.003 (0.08)
W5 to W12, incl	0.252 (6.40) to 0.391 (9.93), incl	0.004 (0.10)
Over to W20, incl	Over 0.391 (9.93) to 0.505 (12.83), incl	0.006 (0.15)
Over W20	Over 0.505 (12.83)	0.008 (0.20)

PROJECT NUMBER:	MAT-306 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: PLAIN WIRE FOR WELDED WIRE FABRIC		PROCESSING DATE	3145		
SAMPLE NUMBER:			LABORATORY NO.			
<u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION _____ SUPPLEMENTAL SPECIFICATION _____ PROJECT SPECIAL PROVISION _____ OTHER _____ <u>PERSON ACCEPTING TECHNICAL RESPONSIBILITY</u> NAME: _____ TITLE: _____		Horizontal	Horizontal Spec.	Vertical	Vertical Spec.	
	Spacing (in.)		—		—	
	Size Number					
	Act. Diam. (in)					
	Nom. Area (in ²)		—		—	
	Load (lbf)		—		—	
	T.S. (psi)					
	Condition		—		—	
	BEGIN DATE	END DATE	TESTED BY	REMARKS		
	RECOMMENDATION					
DIVISION CHIEF – MATERIALS TESTING						

MAT-307

PROJECT NUMBER:	MAT-307		PROCESSING DATE	MATERIAL CODE		
SAMPLE NUMBER:	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: GENERAL TENSILE STRENGTH		LABORATORY NO.			
<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p style="text-align: center;"><u>SPECIFICATION REFERENCE</u></p> <p>STANDARD SPECIFICATION _____</p> <p>SUPPLEMENTAL SPECIFICATION _____</p> <p>PROJECT SPECIAL PROVISION _____</p> <p>OTHER _____</p> </div> <div style="width: 45%;"> <p style="text-align: center;"><u>PERSON ACCEPTING</u></p> <p style="text-align: center;"><u>TECHNICAL RESPONSIBILITY</u></p> <p>NAME : _____</p> <p>TITLE: _____</p> </div> </div>	Size					
	Grade					
	Area (in ²)					
	Load (lbf)					
	Y.P. (psi)					
	Load (lbf)					
	T.S. (psi)					
	Elong. (%)					
	Cold Bend					
	Galv (mils)					
	Test No.					
	BEGIN DATE	END DATE	TESTED BY	REMARKS		
	RECOMMENDATION					
DIVISION CHIEF – MATERIALS TESTING						

State of Connecticut - Department of Transportation
Division of Materials Testing - 280 West Street, Rocky Hill, CT 06067
DOT.MATesting@ct.gov (860)258-0371

REPORT OF TEST ON PORTLAND CEMENT CONCRETE CYLINDERS - MAT-308 Rev 2-14-19

Reproduction of this report by any entity other than the Department without prior written approval of the Division Chief of Construction is prohibited

Sample ID:		Curing Box Used?	<input type="checkbox"/> YES <input type="checkbox"/> NO (Check one)			
Structure/Location: (Where concrete was placed.)		Source/Location:				
		Sampled From: (i.e. chute/pump)				
Item Number:*		Sampled By:				
Item Quantity:**		Date Sampled:				
Material Quantity:***		Item Units:				
Brand of Cement:		Unit:	<input type="checkbox"/> C.Y. <input type="checkbox"/> CU.M (Check one)			
Required Strength:		Contractor:				
Field Test Results	Test 1		Test 2	(Required if material fails test 1.)		
Air (ASTM C173/C231)		}		} Field Sampling is performed in accordance with ASTM C172		
Conc. Temp. (ASTM C1064)						
Slump (ASTM C143)						
* Measured at point of placement.						
Specimen ID:	(1)	(2)	(3)	(4)	(5)	(6)
Age(s) Requested:						
Date Received:						
Date Tested:						
Age Tested:						
Tested By:						
	<input type="checkbox"/> 4 in. cylinder		<input type="checkbox"/> 6 in. cylinder		(Check one)	
Average Diameter:****						
Area :						
Maximum Load: (AASHTO T-22)						
Compressive Strength:(PSI/Mpa)						
Fracture Type: (a-e)						
Status:						
Technical Responsibility: Name: _____ Title: _____						
Signature _____						
NOTES:						
*Item Number : Contract Item under which Contractor is being paid for concrete that is represented by sample.						
**Item Quantity: Amount of concrete/number of items represented by sample in pay units for that contract item. It is never the number of cylinders submitted.						
***Material Quantity: Amount of concrete represented by sample. Minimum Schedule for Test requires one sample every 75 CY (60 m ³) for structures and 50 CY (40 m ³) for pavement. It is never the number of cylinders submitted.						
****Average Diameter: Value is taken from MAT-308A.						

MAT-308A

CONNECTICUT DEPARTMENT OF TRANSPORTATION BUREAU OF ENGINEERING AND CONSTRUCTION DIVISION OF MATERIALS TESTING DAILY CONCRETE CYLINDER DIAMETER LOG					
					MAT-308A
Year	Cylinder Diameters (inches)				Rev. 12-14-18
20__					
Month					Measured
Day	#1	#2	#3	AVERAGE	By:
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					

MAT-309

Compression Units

Specimen:	#1	#2	#3
Received Weight (W_R), lb or kg			
Gross Area (A_g), in ² or mm ²			
Max. Comp. Load (P_{MAX}), lbf or N			

Absorption Units

Specimen:	#1	#2	#3
Ave. Height (H), in or mm			
Immersed Weight (W_i), lb or kg			
Saturated Weight (W_s), lb or kg			
O.D. Weight – Final (W_d), lb or kg			

Oven Dry Density (D), lb/ft³ = $[W_d/(W_s-W_i)] \times 62.4$
 Oven Dry Density (D), kg/m³ = $[W_d/(W_s-W_i)] \times 1000$
 Absorption, lb/ft³ = $[(W_s-W_d)/(W_s-W_i)] \times 62.4$
 Absorption, kg/m³ = $[(W_s-W_d)/(W_s-W_i)] \times 1000$
 Net Volume (V_n), ft³ or mm³ = W_d/D
 Average Net Area (A_n), in² = $(V_n \times 1728)/H$
 Average Net Area (A_n), mm² = V_n/H

PROJECT NUMBER:	MAT-309 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: MASONRY CONCRETE UNITS/BRICK			PROCESSING DATE	MATERIAL CODE			
SAMPLE NUMBER:				LABORATORY NO.				
SPECIFICATION REFERENCE STANDARD SPECIFICATION SUPPLEMENTAL SPECIFICATION PROJECT SPECIAL PROVISION OTHER PERSON ACCEPTING TECHNICAL RESPONSIBILITY NAME: _____ TITLE: _____		#1	#2	#3	Ave.	Spec. Ave.	Spec. Ind.	
	Height, in (mm)							
	Length, in (mm)							
	Width, in (mm)							
	Comp. Strength, psi (MPa)							
	Absorption, lb/ft ³ (kg/m ³)							
	BEGIN DATE	END DATE	TESTED BY	REMARKS				
	RECOMMENDATION							
DIVISION CHIEF – MATERIALS TESTING								

MAT-310

Durometer Readings

- 1.
- 2.
- 3.
- 4.
- 5.

Average =

Identification

Conn.:

Proj. No.:

Manufacturers I.D.:

Pad Type No.:

Month and Year:

Bridge Number:

Lot Number:

Pad Number:

PROJECT NUMBER:	MAT-310 STATE OF CT D.O.T. DIV. OF MAT. TESTING	DATE	MATERIAL CODE	
SAMPLE NUMBER:	REPORT OF TEST: ELASTOMERIC BEARING PAD	LAB #	3505	
<p style="text-align: center;"><u>SPECIFICATION REFERENCE</u></p> <p style="text-align: center;">STANDARD SPECIFICATION</p> <p style="text-align: center;">SUPPLEMENTAL SPECIFICATION</p> <p style="text-align: center;">PROJECT SPECIAL PROVISION</p> <p style="text-align: center;">OTHER</p> <p style="text-align: center;">PERSON ACCEPTING</p> <p style="text-align: center;"><u>TECHNICAL RESPONSIBILITY</u></p> <p style="text-align: center;">NAME: _____</p> <p style="text-align: center;">TITLE: _____</p>		PAD DATA	SPECIFICATIONS	
	Size			
	Slope			
	Spacing (Lam.)			
	No. & Thickness			
	Edge Cover			
	Elast. Layer			
	Comp. Strain			
	Duro. Hardness			
	Shop Drawing			
	Cert. Test Report			
	Test Date	Report Date	Tested By	Remarks
	Recommendation			
	DIVISION CHIEF – MATERIALS TESTING			

MAT-311 (Deleted)

MAT-312

Compression Units

Specimen:	#1	#2	#3	#4	#5
Gross Area (A), in ² (mm ²)					
Maximum Load (W), lbf (N)					

Absorption Units





Specimen:	#1	#2	#3	#4	#5
Saturated Weight 5-h boil (W_b), lb (kg)					
Oven Dry Weight – Final (W_d), lb (kg)					

Compressive Strength, psi = W/A

Absorption, % = $100(W_b - W_d)/W_d$

PROJECT NUMBER:	MAT-312 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CLAY BRICK					PROCESSING DATE		MATERIAL CODE	
SAMPLE NUMBER:						LABORATORY NO.			
<u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION _____ SUPPLEMENTAL SPECIFICATION _____ PROJECT SPECIAL PROVISION _____ OTHER _____ PERSON ACCEPTING <u>TECHNICAL RESPONSIBILITY</u> NAME: _____ TITLE: _____		#1	#2	#3	#4	#5	Ave	Spec. Ave.	Spec. Ind.
	Depth, in (mm)								
	Length, in (mm)								
	Width, in (mm)								
	Strength, psi (MPa)								
	Absorption by 5-hour boiling (%)								
	BEGIN DATE	END DATE	TESTED BY		REMARKS				
	RECOMMENDATION								
DIVISION CHIEF – MATERIALS TESTING									

MAT-313



PROJECT NUMBER:		MAT-313 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CONCRETE BLOCK FOR SLOPE PROTECTION			PROCESSING DATE		MATERIAL CODE 3197		
SAMPLE NUMBER:					LABORATORY NO.				
SPECIFICATION REFERENCE STANDARD SPECIFICATION SUPPLEMENTAL SPECIFICATION PROJECT SPECIAL PROVISION OTHER PERSON ACCEPTING TECHNICAL RESPONSIBILITY NAME: _____ TITLE: _____		SAMPLE 1	SAMPLE 2	SAMPLE 3	SPEC.				
	L, Length, inches (mm)				16 +/- 1/2 in 406 +/- 12.5 mm				
	W, Width, inches (mm)				8 +/- 1/2 203 +/- 12.5 mm				
	H, Height, inches (mm)				4 +/- 1/2 100 +/- 12.5 mm				
	A, Area, in ² (mm ²)				----				
	Load, lbf (N)				----				
	Strength, psi (MPa)				3000 psi 21 MPa				
	BEGIN DATE	END DATE	TESTED BY	REMARKS					
	RECOMMENDATION								
	DIVISION CHIEF – MATERIALS TESTING								

**CERTIFICATION OF PRECAST
CONCRETE PRODUCTS**

MAT-314 (PC-1)

REV. 1/15

STATE OF CONNECTICUT

DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING
280 West Street , Rocky Hill CT 06067-3502

DATE OF SHIPMENT

--

Project Personnel: Submit with Request for Test **AFTER** visual inspection on project site.

List one type of product per cast date per line.

DISTRIBUTION: Original to Lab, Copy to Project Engineer, Copy to be kept by Manufacturer.

MANUFACTURER	LOCATION		
SHIPPED TO: (Contractor's Name)		PROJECT NO. OR PURCHASE ORDER NO.	
Description of Products	Cast Date	Quantity	
Remarks			
This document certifies that all the products listed above conform to all applicable Department and project specifications, including but not limited to the "Buy America" requirements regarding all steel components.			
Authorized Agent of Manufacturer			
Signed:			Date:

MAT-315 (Deleted)

MAT-316

SAMPLE	
BRAND	
TYPE	
IN LAB	
94 Lbs. Bag 42 Kgs. Bag	
GAL CAN	
OTHER	

<u>SPECIFICATION REFERENCE</u>	
STANDARD SPECIFICATION	_____
SUPPLEMENTAL SPECIFICATION	_____
PROJECT SPECIAL PROVISION	_____
OTHER	_____
PERSON ACCEPTING TECHNICAL RESPONSIBILITY	
NAME	_____
TITLE	_____

DATE TO CHEM. RM.		FULL CHEMICAL		PROJECT #
DATE RESULTS RETURNED		FINENESS ONLY		SAMPLE #

Mat-316	AASHTO M - 85 (ASTM C - 150)				LAB NO.		
REPORT OF TEST: PORTLAND CEMENT (ALL TYPES)							
PHYSICAL SECTION TEST RESULTS				CHEMICAL SECTION TEST RESULTS			
TEST	LAB RESULT	AASHTO SPEC.		TEST	LAB RESULT	AASHTO SPEC.	
AIR CONTENT %		12 MAX.		FINENESS SoCm/Gm		2600 - 4200	
				SiO ₂ %		NONE	
AUTOCLAVE EXPANSION %		.80 MAX		Al ₂ O ₃ %		NONE	
COMPRESSIVE STRENGTH				Fe ₂ O ₃ %		NONE	
1 Day <u>MPa</u> PSI		NONE		MgO %		6.0 MAX.	
3 Day <u>MPa</u> PSI		12 MPa Min. 1740 PSI Min.		SO ₃ %		a) 3.0 MAX. b) 3.5 MAX.	
7 Day <u>MPa</u> PSI		19 MPa Min. 2760 PSI Min.		LOSS ON IGNITION %		3.0 MAX.	
				INSOLUABLE RESIDUE %		0.75 MAX.	
				C ₃ S %		NONE	
TIME OF SETTING				C ₂ S %		NONE	
VICAT, MIN		45 to 375		C ₃ A %		NONE	
				a) WHEN C ₃ A < 8% b) WHEN C ₃ A > 8% NOTES:			
RECOMMENDED FOR:				REMARKS:			

CEMENT _____ TYPE _____ LAB NO. _____

T - 106 C - 109 DATE: TIME:			T - 137 C - 185			
CUBES MADE:			AIR CONTENT			
AGE			WATER %			
DATE			WATER ml			
1.			FLOW %			
2.			GROSS WT			
3.			- CUP WT			
AVG			= NET WT			
			FACTOR			
			NET WT* FACTOR			
			AIR CONT %			

DATE					
T-107 C-151 AUTOCLAVE		T-129 C-187 NORMAL CONSISTENCY			
TIME BARS MADE		WATER %			
BARS MEASURE		WATER ml			
SWITCHES ON		PENETRATION mm			
VENT CLOSED					

295 PSI		T-131 C-191 VICAT - TIME OF SET		
ADD 3 HOURS		MADE	INITIAL	
SWITCHES OFF		TIME OF DAY		
DOWN 1 ½ HRS		HR: MIN		
COOL 30 MIN		MINUTES		
AFTER STEAM				
BEFORE STEAM				
DIFFERENCE				
% EXPANSION				

MAT-323

Description	Sample #1	Sample #2	Sample #3	Specifications
Overall Diam. Across Crowns, in (mm)				
Diameter of Exterior Wire #1, in (mm)				
Diameter of Exterior Wire #2, in (mm)				
Diameter of Exterior Wire #3, in (mm)				
Diameter of Exterior Wire #4, in (mm)				
Diameter of Exterior Wire #5, in (mm)				
Diameter of Exterior Wire #6, in (mm)				
Diameter of Center Wire, in (mm)				
Diff Betwn. Center & Any Ext. Wire, in (mm)				
Pitch, in (mm)				
Load @ 1% Extension, lbf (kN)				
Breaking Load, lbf (kN)				
Breaking Strength, psi (MPa)				
No. Wires Broken				
Type of Break				
Location of Break				
Length Meas. @ 1% Extension, "A", in (mm)				
Length Meas. @ Breaking Load, "B", in (mm)				
Total Elongation Under Load (%)				

Total Elongation Under Load = (100%)[(B-A)/A] + 1%

PROJECT NUMBER:	MAT-323 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: STEEL STRAND		PROCESSING DATE		MATERIAL CODE	
SAMPLE NUMBER:			LABORATORY NO.		3148	
<u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION SUPPLEMENTAL SPECIFICATION PROJECT SPECIAL PROVISION OTHER PERSON ACCEPTING <u>TECHNICAL RESPONSIBILITY</u> NAME: _____ TITLE: _____		Sample 1	Sample 2	Sample 3		
	Reel No.					
	Heat No.					
	Diameter of Strand, in (mm)					
	Min. Ext. Wire Diameter, in (mm)					
	Center Wire Diameter, in (mm)					
	Diff in Diameter of Center Wire, in (mm)					
	Total Area of 7 Wires, in. ² , mm ²					
	Load @ 1% Elongation, lbf (kN)					
	Total Elongation (%)					
	Breaking Load, lbf (kN)					
	BEGIN DATE	END DATE	TESTED BY	REMARKS		
	RECOMMENDATION					
	DIVISION CHIEF – MATERIALS TESTING					

Field Report: Inspection of Prestressed, Precast and Reinforced Concrete Pipe Manufacturers

Date: _____ Inspection by: _____

Phone: _____

Fax No: _____

E-Mail: _____

Plant Name _____

Address _____

Plant Manager _____

NPCA Certified _____

Items of Manufacture _____

MIXERS

<u>Manufacturer</u>	<u>Type</u>	<u>Capacity</u>

PIPE MACHINES

<u>Manufacturer</u>	<u>Type</u>	<u>Sizes</u>

CALIBRATION of SCALES

<u>Scale</u>	<u>Date of Calibration</u>	<u>Calibration Company</u>
Cement		
Aggregate		
Water		
Other		

TESTING EQUIPMENT

<u>Testing Machine</u>	<u>Date of Calibration</u>	<u>Calibration Company</u>
3-Edge		
Compression		
<u>Concrete Testing Equip.</u>	<u>Condition</u>	<u>Calibration Info. Available</u>
Air Meter		
Slump Cone		
Thermometers		

PLANT QUALITY CONTROL PERSONNEL

Employee

ACI/PCI Certified

NETTCP Conc. Tech.

Additional remarks _____

SOURCE of CEMENT AND POZZOLANS

AGGREGATES AND WATER

Material

Source

Size

SOURCE OF CATCH BASIN FRAMES AND GRATES

REINFORCEMENT

Domestic Steel _____

Foreign Steel Onsite _____

ADMIXTURES


Manufacturers of Admixtures

Name

Type

Q.C. PLAN DEFICIENCIES

MAT-325



PROJECT NUMBER:	MAT-325	PROCESSING DATE	MATERIAL CODE
SAMPLE NUMBER:	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CHAIN LINK FENCE HARDWARE	LABORATORY NO.	3320

	ITEM	Galv. Oz/in ² (g/m ²)	ITEM	Galv. Oz/in ² (g/m ²)
	BEGIN DATE	END DATE	TESTED BY	REMARKS
	RECOMMENDATION			


SPECIFICATION REFERENCE
 STANDARD SPECIFICATION _____
 SUPPLEMENTAL SPECIFICATION _____
 PROJECT SPECIAL PROVISION _____
 OTHER _____
 PERSON ACCEPTING _____
TECHNICAL RESPONSIBILITY
 NAME: _____
 TITLE: _____

DIVISION CHIEF – MATERIALS TESTING

MAT-326

PROJECT NUMBER:	MAT-326 STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: CHAIN LINK FENCE TENSION WIRE		PROCESSING DATE	MATERIAL CODE
SAMPLE NUMBER:			LABORATORY NO.	
<u>SPECIFICATION REFERENCE</u> STANDARD SPECIFICATION _____ SUPPLEMENTAL SPECIFICATION _____ PROJECT SPECIAL PROVISION _____ OTHER _____ PERSON ACCEPTING <u>TECHNICAL RESPONSIBILITY</u> NAME: _____ TITLE: _____		Actual	Specification	
	Gage of Wire			
	Tensile Strength, psi (MPa)			
	Weight of Coating, oz/ft ² (g/m ²)			
	BEGIN DATE	END DATE	TESTED BY	REMARKS
	RECOMMENDATION			
	DIVISION CHIEF – MATERIALS TESTING			

MAT-327



PROJECT NUMBER:	MAT-327	POST DATE	LAB #	MAT. CODE 3549	
SAMPLE NUMBER:	STATE OF CONNECTICUT DOT REPORT OF TEST: H-PILES AND WIDE FLANGE SHAPES	DATE RECEIVED		RECEIVED BY	
<p style="text-align: center;"><u>SPECIFICATION REFERENCE</u></p> <p style="text-align: center;">STANDARD SPECIFICATION</p> <p style="text-align: center;">SUPPLEMENTAL SPECIFICATION</p> <p style="text-align: center;">PROJECT SPECIAL PROVISION</p> <p style="text-align: center;">OTHER</p> <p style="text-align: center;">PERSON ACCEPTING</p> <p style="text-align: center;"><u>TECHNICAL RESPONSIBILITY</u></p> <p style="text-align: center;">NAME: _____</p> <p style="text-align: center;">TITLE: _____</p>	Item	Sample	<u>Specification</u>		
			U.S. Cust. (in)	Metric (mm)	
	b, flange width		+ 1/4 - 3/16	+ 4 - 3	
	d, depth		+1/4 -3/16	+6 -5	
	t _f , flange thickness		---	---	
	t _w , web thickness		---	---	
	wt/ft		+/-2.5%	+/-2.5%	
	Tensile Strength (ksi, MPa)		Gr. 36: 58-80 Gr. 50: 65-95	Gr. 36: 400-550 Gr. 50: 450-655	
	Begin Date	End Date	Tested By	REMARKS	
DIVISION CHIEF – MATERIALS TESTING					

ASTM A 496 Steel Wire, Deformed, for Concrete Reinforcement

Table 4 Tension Test Requirements (Material for Welded Wire Reinforcement)

	psi (MPa) min
Tensile strength	80000 (550)
Yield strength	70000(485)

Section 9 Permissible Variation in Weight

9.1 The permissible variation in weight of any deformed wire is +/-6% of its nominal weight. The theoretical weights shown in Table 1, or similar calculations on unlisted sizes, shall be used to establish the variation.

PROJECT NUMBER:	MAT-328		PROCESSING DATE	MATERIAL CODE		
SAMPLE NUMBER:	STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION DIVISION OF MATERIALS TESTING REPORT OF TEST: DEFORMED STEEL WIRE FOR CONCRETE REINFORCEMENT		LABORATORY NO.	3145		
<div style="display: flex; justify-content: space-between;"> <div style="width: 45%;"> <p style="text-align: center; margin: 0;"><u>SPECIFICATION REFERENCE</u></p> <p style="margin: 0;">STANDARD SPECIFICATION _____</p> <p style="margin: 0;">SUPPLEMENTAL SPECIFICATION _____</p> <p style="margin: 0;">PROJECT SPECIAL PROVISION _____</p> <p style="margin: 0;">OTHER _____</p> </div> <div style="width: 45%;"> <p style="text-align: center; margin: 0;"><u>PERSON ACCEPTING</u> <u>TECHNICAL RESPONSIBILITY</u></p> <p style="margin: 0;">NAME: _____</p> <p style="margin: 0;">TITLE: _____</p> </div> </div>		Horizontal	Horizontal Spec.	Vertical	Vertical Spec.	
	Spacing (in.)	—	—	—	—	
	Size Number					
	Unit Wt. (lb/ft)					
	Nom. Area (in ²)		—		—	
	Load (lbf)		—		—	
	T.S. (psi)					
	Condition		—		—	
	BEGIN DATE	END DATE	TESTED BY	REMARKS		
	RECOMMENDATION					
DIVISION CHIEF – MATERIALS TESTING						

Laboratory: Central Lab Rocky Hill, CT
Sample Date Tested:
Kind of Material:
Source of Supply:
Location of Source or Supply:
Sample Taken From:
Source of Supply:
Location of:
Sampled By:
Date Sampled:
Using Agency: ConnDOT
Quantity Represented:
Lot Number:
Tank Number:
Sample Received:
Remarks:

State of Connecticut Department of Transportation
Bureau of Engineering & Highway Operations
Report of Test: Asphalt Binder MAT-401
Standard Specifications CONNDOT: M04 Bit. Concrete, AASHTO M320 AND AASHTO M332
Procedures in conformance with AASHTO R-29

Rocky Hill Binder Results

Original Binder						Specification
<i>SG @ 25°C</i>						
<i>Temperature (°C)</i>	58	64	70	76	82	
<i>Viscosity (Pa-s) @ 135°C</i>						max. 3
<i>Viscosity (Pa-s) @ 165°C</i>						
<i>Mixing Temperature Range</i>						
<i>Compaction Temperature Range</i>						
<i>Complex Modulus, G* (kPa)</i>						
<i>Phase Angle (δ)</i>						
<i>Original G*/sin δ @ T°C</i>						min. 1

Binder True Grade

<i>High Temp</i>	
<i>Inter Temp</i>	
<i>Low (BBR)</i>	
<i>T(S)-T(m)</i>	

RTFO Binder						
<i>Mass change (%)</i>						-1 to +1
<i>Temperature (°C)</i>	58	64	70	76	82	
<i>Complex Modulus, G* (kPa)</i>						
<i>Phase Angle (δ)</i>						
<i>RTFO G*/sin δ @ T°C</i>						min. 2.2
<i>RTFO Jnr 3.2 (kPa⁻¹) @ T°C</i>						max. 4.5 (S), 0.5 (E)
<i>RTFO R3.2 @ T°C</i>						
<i>RTFO Jnr 0.1 (kPa-1) @ T°C</i>						
<i>RTFO Jnr Diff (%) @ T°C</i>						max. 75
<i>Modified by an acceptable elastomeric poly?</i>						Yes (E)

PAV Binder						
<i>Temperature (°C)</i>	34	31	28	25	22	
<i>Complex Modulus, G* (kPa)</i>						
<i>Phase Angle (δ)</i>						
<i>PAV G* sin δ @ T°C</i>						max. 5000 (S), 6000 (E)
<i>Temperature (°C)</i>	-6	-12	-18	-24		
<i>PAV BBR Stiffness (MPa) @ T°C</i>						max. 300
<i>PAV BBR m-value @ T°C</i>						min. 0.3
<i>Failure Stress</i>						
<i>Failure Strain (%)</i>						min. 1

Laboratory: Central Lab Rocky Hill, CT
Sample Date Tested:
Kind of Material:
Source of Supply:
Location of Source or Supply:
Sample Taken From:
Source of Supply:
Location of:
Sampled By:
Date Sampled:
Using Agency: ConnDOT
Quantity Represented:
Lot Number:
Tank Number:
Sample Received:
Remarks:

Mass per Gallon

M_e , mass in measure at 77 °F g
D_e , density of the emulsified asphalt, lb/gal at 77 °F
D_e , density of the emulsified asphalt, lb/gal at 60 °F

<p>State of Connecticut Department of Transportation Bureau of Engineering & Highway Operations Report of Test: Emulsified Asphalt MAT-402 Standard Specifications CONNDOT: M.04 Bit. Concrete, AASHTO M 140 AND AASHTO M 208 Procedures in conformance with AASHTO T 59 and AASHTO T 49</p>

Rocky Hill Emulsified Asphalt Results

Residue by Evaporation

Set	1	2	3	4	Specification
M_{br} Beaker + Rod + Screen (if used) weight, g					
Emulsified Asphalt weight (49 - 51 g)					
M_{br} Beaker + Rod + Screen (if used) + residue, g					
Residue, %					
Residue by Evaporation, %					*

* Requirement for residue by distillation: For grades RS-1, RS-1h, CRS-1 and CRS-1h, min 60; SS-1, SS-1h, CSS-1 and CSS-1h, min 57

Penetration at 77°F

Trial	1	2	3	Specification
Penetration at 77°F				
Average Penetration				*
Difference between highest and lowest				**

* Requirement for testing on residue by distillation: For grades RS-1h, SS-1h, CRS-1h and CSS-1h, 40-90; RS-1 and CRS-1, 90-150; SS-1 and CSS-1, 90-250

** For Penetration 0-49, max. 2; 50-149, max. 4; 150-249, max. 12

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 404 (REV 1-29-07) Check List for Bituminous Concrete Plants (Batch Type) Page 1 of 7

Plant: _____ Location _____

Inspected By: _____ Date: _____

– The mixing plant used in the preparation of bituminous concrete shall conform to the following requirements:

Aggregates:

TYPE	SOURCE OF SUPPLY	TYPE	SOURCE OF SUPPLY
<input type="checkbox"/> Trap Rock		<input type="checkbox"/> Crushed Gravel	
<input type="checkbox"/> 1/4"		<input type="checkbox"/> 1/4"	
<input type="checkbox"/> 3/8"		<input type="checkbox"/> 3/8"	
<input type="checkbox"/> 1/2"		<input type="checkbox"/> 1/2"	
<input type="checkbox"/> 3/4"		<input type="checkbox"/> 3/4"	
<input type="checkbox"/> 1"		<input type="checkbox"/> 1"	
<input type="checkbox"/> 1 1/4"		<input type="checkbox"/> 1 1/4"	

TYPE	SOURCE OF SUPPLY	TYPE	SOURCE OF SUPPLY
<input type="checkbox"/> Natural Sand		<input type="checkbox"/> Stone Sand	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 404 (REV 1-29-07) Check List for Bituminous Concrete Plants (Batch Type) Page 2 of 7

TYPE	SOURCE OF SUPPLY	TYPE	SOURCE OF SUPPLY
<input type="checkbox"/> Screenings		<input type="checkbox"/> Other	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	

Cold Bins:

Number of cold feed storage bins (minimum of 4 required)

Dust Return:

Method of Introduction:

- Pneumatic
- Screwed
- Separate Bin

Bag House Options:

- Reversible Screw
- Knockout Box
- Other

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 404 (REV 1-29-07) Check List for Bituminous Concrete Plants (Batch Type) Page 3 of 7

Hot Bins:

- Number of compartments (minimum of 3 required)
- Overflow pipes
- Snug fitting gate

Asphalt Delivery System:

- Spray Bar Pressure System
- Spray Bar Gravity Fed System
- Measures accurately to within +/-0.1% of the total batch
- Delivers asphalt cement in thin, uniform sheet full width of the mixer

Hot Storage Tanks:

- Lines to be separated or equipped with a reverse pump to eliminate contamination
- Thermostatically controlled, with a thermometer in bulkhead
- Sampling valves located in lower half of an end bulkhead and on mixer supply line.

Number of storage tanks on site _____

Tank Inventory:	Tank Number:	Tank Capacity:	Type of Asphalt:

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 404 (REV 1-29-07) Check List for Bituminous Concrete Plants (Batch Type) Page 4 of 7

Tickets:

All vendors producing bituminous concrete for the State of Connecticut under the terms of a contract must have their truck-weighting scales, storage bin scales and mixing plant automated so as to provide a detailed ticket containing the following information:

- 1) **State of Connecticut printed on ticket**
- 2) **Name of producer, and identification of plant or specific storage bin, if used**
- 3) **Date and time of day**
- 4) **Individual bin high/target/low batch weights marked with an * asterisk**
- 5) **Type of material* (including RAP (dry weight) percentage and moisture content, if used)**
- 6) **Net weight of material**
- 7) **Gross weight or tare weight of truck**
- 8) **Project number, purchase order number, name of contractor (if contractor other than producer), whichever applies**
- 9) **Truck number for positive identification of truck**

***NOTE: Class 3 mixture to be used for machine-placed curbing must be shown on the ticket as “curb
Mix only.”**

Items 1 to 9 must be printed on the ticket. The time of day may be printed by a separate time clock.

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 404 (REV 1-29-07) Check List for Bituminous Concrete Plants (Batch Type) Page 5 of 7

The State reserves the right to have a weigh man at the scales to monitor the weighing of trucks.

Plant Scales:

In addition to complying with the above requirements, the weighing equipment shall be constructed with the necessary adjustable devices that will permit any part thereof that gets out of alignment or adjustment to be easily readjusted so that the weighing device will function properly. Scales will be checked and sealed by the Weights and Measures Division at least annually and more often if deemed necessary in to insure their accuracy.

Seal Dates:

Plant:

Truck:

Storage Bin(s):

Copy of Printout(s) (Plant and Truck)

D.E.P. Operating Permit (Obtain Copy)

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 404 (REV 1-29-07) Check List for Bituminous Concrete Plants (Batch Type) Page 6 of 7

Automation and Recordation of Bituminous Concrete Plant:

The plant shall be equipped with an automated weighing, cycling, and monitoring system approved by the Division Chief, and installed as part of the batching equipment with displays located in full view of the operator.

The automatic proportioning system shall be capable of consistently delivering materials within the full range of batch sizes with the following tolerances:

- Each Aggregate Component: $\pm 1.5\%$ of individual of cumulative target weight for each bin
- Mineral filler: $\pm 0.5\%$ of the total batch
- Bituminous Material: $\pm 0.1\%$ of the total batch
- Zero Return (Aggregate): $\pm 0.5\%$ of the total batch
- Zero Return (Bituminous Material): $\pm 0.1\%$ of the total batch

Tolerance controls shall be automatically or manually adjustable to provide for spans suitable for less than full size of batches.

Recording equipment shall monitor the batching sequence of each component of the mixture and produce a printed record of these operations on each truck ticket in accordance with Sub article 4.06.03-2 and as specified herein. For each day's production, each D.O.T. project shall be provided a clear, legible copy of the recording. Provision will be made so that scales may not be manually manipulated during the printing process. In addition, the system shall be interlocked to allow printing only when the scale has come to a complete rest.

A printed character (asterisk or other shall also automatically be printed on the batch plant printout when the automatic batching sequence is interrupted or switched to auto-manual or manual during proportioning..

- Ten standard 50 lb. (22.7 kg.) test weights for checking plant scales.

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 404 (REV 1-29-07) Check List for Bituminous Concrete Plants (Batch Type) Page 7 of 7

Hot Storage Silos:

Number of Silos: _____.

Heated

Type of Heat:

- Cone Hot Oil
- Cone Electric

Unheated

Silo Capacity:

Silo Number	Capacity	Silo Number	Capacity

Brand/Manufacture:

Brand/Manufacture: _____

Brand/Manufacture: _____

Brand/Manufacture: _____

The silos shall be equipped with a light or indicator to show when the level of material reaches the top of the discharge cone.

Please note any variations in specifications below:

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 405 (REV 1-29-07) Check List for Bituminous Concrete Plants (Drum Type) Page 1 of 7

Plant: _____ Location _____

Inspected By: _____ Date: _____

– The mixing plant used in the preparation of bituminous concrete shall conform to the following requirements:

Aggregates:

TYPE	SOURCE OF SUPPLY	TYPE	SOURCE OF SUPPLY
<input type="checkbox"/> Trap Rock		<input type="checkbox"/> Crushed Gravel	
<input type="checkbox"/> 1/4"		<input type="checkbox"/> 1/4"	
<input type="checkbox"/> 3/8"		<input type="checkbox"/> 3/8"	
<input type="checkbox"/> 1/2"		<input type="checkbox"/> 1/2"	
<input type="checkbox"/> 3/4"		<input type="checkbox"/> 3/4"	
<input type="checkbox"/> 1"		<input type="checkbox"/> 1"	
<input type="checkbox"/> 1 1/4"		<input type="checkbox"/> 1 1/4"	

TYPE	SOURCE OF SUPPLY	TYPE	SOURCE OF SUPPLY
<input type="checkbox"/> Natural Sand		<input type="checkbox"/> Stone Sand	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 405 (REV 1-29-07) Check List for Bituminous Concrete Plants (Drum Type) Page 2 of 7

TYPE	SOURCE OF SUPPLY	TYPE	SOURCE OF SUPPLY
<input type="checkbox"/> Screenings		<input type="checkbox"/> Other	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	
<input type="checkbox"/>		<input type="checkbox"/>	

Mineral Filler

- Separate Bin
- Delivery System accurate to 0.1% of total weight of bituminous mixture
- 5-second interrupt interlock

Aggregate Weighing:

- Continuous weighing device
- Individual Feeders (belt type)
- 5-second interrupt device
- Moisture compensating device
- Means for diverting aggregate prior to entry into drum
- Belt scale accurate to +/-1/2 of 1% (verified by plant records)

Dust Return Type: Pneumatic Screw conveyer

Bitumen Delivery System:

- Accurate to 0.1% based on total weight of mixture
- Presetting actual Bitumen content directly as a percentage/per total mixture weight
- Interlock to halt production within 5 seconds if Bitumen flow is interrupted
- Temperature compensating device to correct quantity of asphalt to 60F (16C)
- Recordation of Proportions. The plant shall be quipped with an automatic digital recording device approved by the Division Chief, that simultaneously records the weight of each aggregate, mineral filler if added separately and bitumen a 5-minute intervals during production time and on demand. The recordation shall include the actual bitumen quantity as a percentage of the total weight. The maximum resolution shall be 0.1 tons for dry aggregate, 0.01 tons for mineral filler if added separately, 0.01 tons for bitumen and 0.1% for bitumen content.

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 405 (REV 1-29-07) Check List for Bituminous Concrete Plants (Drum Type) Page 3 of 7

All recording shall show the date, including day, month, and year, and time to the nearest minute for each print. For each day's production, each DOT project(s) shall be provided with a clear and legible copy of the recording.

Mixing Plant and Machinery:

- A capacity of at least 125 tons (115 metric tons) per hour
- A minimum of four (4) cold-feed storage bins
- RAP capability, per specifications
- Scalping screens or other devices installed in the cold feed system to remove any debris or other foreign material in excess of 4 inches (100 mm). (Individual bins shall be labeled for the aggregate sizes being used.)
- Flights in drum checked and found in satisfactory condition.
- The plant shall have at hand the required number of 50-lb. (22.7 kg) test weights for frequent testing off all scales.
- Provisions shall be made at the drum outlet so that the pyrometer reading may be checked by means of an armored thermometer

Bag House Options:

- Reversible Screw
- Knockout Box
- Other

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 405 (REV 1-29-07) Check List for Bituminous Concrete Plants (Drum Type) Page 4 of 7

Hot Storage Tanks:

- Lines to be separated or equipped with a reverse pump to eliminate contamination
- Thermostatically controlled, with a thermometer in bulkhead
- Sampling valves located in lower half of an end bulkhead and on mixer supply line.

Number of storage tanks on site _____

Tank Inventory:	Tank Number:	Tank Capacity:	Type of Asphalt:

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 405 (REV 1-29-07) Check List for Bituminous Concrete Plants (Drum Type) Page 5 of 7

Tickets:

All vendors producing bituminous concrete for the State of Connecticut under the terms of a contract must have their truck-weighing scales, storage bin scales and mixing plant automated so as to provide a detailed ticket containing the following information:

- 1) State of Connecticut printed on ticket
- 2) Name of producer, and identification of plant or specific storage bin, if used
- 3) Date and time of day
- 4) Individual bin high/target/low batch weights marked with an * asterisk
- 5) Type of material* (including RAP (dry weight) percentage and moisture content, if used)
- 6) Net weight of material
- 7) Gross weight or tare weight of truck
- 8) Project number, purchase order number, name of contractor (if contractor other than producer), whichever applies
- 9) Truck number for positive identification of truck

***NOTE: Class 3 mixture to be used for machine-placed curbing must be shown on the ticket as "curb
Mix only."**

Items 1 to 9 must be printed on the ticket. The time of day may be printed by a separate time clock.

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 405 (REV 1-29-07) Check List for Bituminous Concrete Plants (Drum Type) Page 6 of 7

The State reserves the right to have a weigh man at the scales to monitor the weighing of trucks.

Plant Scales:

In addition to complying with the above requirements, the weighing equipment shall be constructed with the necessary adjustable devices that will permit any part thereof that gets out of alignment or adjustment to be easily readjusted so that the weighing device will function properly. Scales will be checked and sealed by the Weights and Measures Division at least annually and more often if deemed necessary in to insure their accuracy.

Seal Dates:

Plant:

Truck:

Storage Bin(s):

Copy of Printout(s) (Plant and Truck)

D.E.P. Operating Permit (Obtain Copy)

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 405 (REV 1-29-07) Check List for Bituminous Concrete Plants (Drum Type) Page 7 of 7

Hot Storage Silos:

Number of Silos: _____.

Heated

Type of Heat:

- Cone Hot Oil
- Cone Electric

Unheated

Silo Capacity:

Silo Number	Capacity	Silo Number	Capacity

Brand/Manufacture:

Brand/Manufacture: _____

Brand/Manufacture: _____

Brand/Manufacture: _____

Brand/Manufacture: _____

The silos shall be equipped with a light or indicator to show when the level of material reaches the top of the discharge cone.

Please note any variations in specifications below:

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 1 of 9

Plant: _____ **Inspection**
Date: _____

Site: _____ **Inspector(s):** _____

Contractor Representative: _____

FIELD LABORATORY REQUIREMENTS

At all points during the production season this lab will comply with all requirements.

GENERAL:

- 1. A field laboratory that is equipped for performing required tests shall be provided at each mixing plant for the use of the State's inspectors at no expense to the State.**
- 2. The Contractor shall ensure that the State's inspectors are given priority in the use of the field laboratory.**
- 3. The field laboratory shall be approved by the Division Chief of Materials.**
- 4. The field laboratory shall:**
 - a. be a separate building or a separate room and shall have a minimum floor space of 300 ft² minimum floor space and 20 ft² of counter space. for laboratories constructed after January 1, 1991] with the least dimension to be 6 ft (1.8 m)**
 - b. has windows installed that allow for sufficient light and ventilation**
 - c. has a source of fresh air from a door and/or from windows that open**
 - d. have an exhaust fan located directly behind and within 2 ft (0.6 m) of both extractor and drying source, and 12m. (304 mm) from top of workbench and shall not adversely effect the room temperature**
 - f. has a telephone available within the testing laboratory.**
 - g. be equipped with a suitable heating and air conditioning cooling system able to maintain the temperature between 65°F and 80°F(18°C to 27°C)**
 - h. be clean, and be free of all materials and equipment not associated with the laboratory**

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 2 of 9

EQUIPMENT:

The field laboratory shall be equipped with the following:

- 1. Paint brush: 1 in to 1 ½ in (25 mm to 38 mm) wide
- 2. Hand brush: suitable for cleaning sieves
- 3. 1000 ml unbreakable wash bottle or flask.

MIX PLANT FIELD LABORATORY – APPARATUS INSPECTION SHEET (continued)

- 4. Two, 6 in. (152 mm) spatulas, heavy enough to rod molds without bending
- 5. Two Thermometer 50°F to 450°F (10°C to 230°C)
- For Superpave laboratories, Thermometers: Calibrated liquid-in-glass, total immersion type, of suitable range with gradations at least over 0.1° (0.2F) and a maximum scale error of 0.1° (0.2F) as prescribed in ASTM Specification E2.
- For Superpave laboratories, Vacuum Pump or Water Aspirator: For evacuation of air from the container: The vacuum pump or water aspirator shall be equipped with a needle valve to maintain constant vacuum. ***
- For Superpave laboratories, Water bath: Shall be capable of maintaining constant temperature and constant suitable water level.
- For Superpave laboratories, Manometer and Residual Pressure Manometer. Two (2) Meeting contract requirements and NIST traceable per ASSHTO T-209 (6.4-5). *** (Mercury Manometers not allowed for use).
- For Superpave laboratories, Superpave Gyrotory Compactor: capable of providing a consolidation pressure of 600 ± 18 kPa, an angle of gyration of 1.25 ± 0.02 degrees, and a speed of gyration of 30 ± 0.5 rpm. Gyrotory shall be directly connected to printer.
- For Superpave laboratories, Three (3) cylindrical molds: large enough to accommodate the following specimen requirements: 150 mm diameter, 150 mm maximum heights, and 90 mm minimum height.
- For Superpave laboratories, Extrusion jack or arbor press: capable of extruding compacted specimens from molds without distortion or damage.

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 3 of 9

EQUIPMENT: Continued

- Timer: Accurate to one minute increments and capable of measuring from 1 min. to 60 min. timer shall have audible alert when the time has expired.**

- For Superpave laboratories, Pans;: Four (4) metal pans of adequate size to hold 5000 grams of material, for reheating gyratory sample to compaction temperature.**

- For Superpave laboratories, The field laboratory shall include a PC, printer and dedicated phone line and modem (phone is able to be used while modem is connected to server) suitable to run software and perform all necessary computations, as directed by the Division Chief. This equipment shall be maintained in good working order and be made available for use by State inspectors.**

- For Superpave laboratories, The field laboratory shall have potable source (with documentation stating the sources potability) and drainage for use with testing equipment.**

- 6. Putty knife or scraper**

- 7. Trowel or similar tool to quarter samples**

- 8. Eye wash station: A double (two-eye) wash station (2,000 ml minimum) or sink mounted (potable water source with documentation stating the sources potability) capable of cleaning both eyes simultaneously, installed in the laboratory for ready access contents shall be tamperproof and dated.
Solution Expiration Date: _____**

- 9. Scoop: large enough to scoop a 1200 g sample**

- 10. Heavy (Kraft) wrapping paper: 36 in. (915 mm) minimum width**

- 11. Long-handled, pointed shovel**

- 12. Six metal pie plates: 10 in. (250 mm) minimum diameter**

- 13. Five, 3 gal (12L) sample buckets. Eight, 3 gal (12L) sample buckets for Superpave Labs only. *****

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 4 of 9

EQUIPMENT: Continued

14. Sample splitter suitable to split aggregate samples and sand, through and including No. 4 aggregate
15. Fire extinguisher: for electrical or chemical fires, effective on all solvents used in the laboratory
Date refilled or checked (within one year) _____
16. Hot plate and infrared lamp of suitable wattage, or a vented drying oven for drying samples
- a. Type (describe) _____
- b. Placed within 2 ft (0.6 m) of exhaust fan
- c. Vented to the outside (if oven)
17. Oven
- a. Thermostatically controlled so as to maintain temperature within $\pm 5^{\circ}\text{F}$ (3°C)
- b. Temperature range of 104°F to 395° (40°C to 200°C)
- c. 12 Cu. ft forced draft oven capable of being controlled to $\pm 3^{\circ}\text{C}$ as a minimum of 104°C to 395°C (40°C to 200°C) for Superpave Labs and an inside dimension shall be at least 17 in W x 12 in. D x 17 in. H (432 mm/304 mm/432 mm) for Marshal Laboratories.

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 5 of 9

MIX PLANT FIELD LABORATORY – APPARATUS INSPECTION SHEET

18. A suitable non-chlorinated solvent that has been approved by the Division Chief (Some non chlorinated solvents may require additional equipment or supplies, which shall be the responsibility of the Contractor. These may include a potable water source, a revised disposal method and other items deemed necessary for the particular solvent used.

a. Brand

a. Brand Name: _____

b. Solvent to be located at a reasonable distance from the laboratory –not to exceed 75 ft (25m)

c. Materials Safety Data Sheet to be posted in the field laboratory.*

*A statement from the Department of Environmental Protection, Water Compliance Unit, reads: Discharge of solvents into the surface or ground waters is not an acceptable method for disposal. This waste should be collected in a sealed, quality container free of leaks and held on site in a dry location for adequate disposal through a licensed waste hauler. Ground and surface water discharge require a permit under the provisions of the Connecticut General Statutes.)

19. Centrifugal Extractor. (May be waved if ignition oven is used). ***

a. Sufficient amount of filter rings and filter paper on hand

b. Rings and paper are at least the outside diameter of the extractor bowl

c. Solvent disposal from the extractor is piped directly to the outside into a closed container contained in a larger containment area or container.

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 6 of 9

MIX PLANT FIELD LABORATORY – APPARATUS INSPECTION SHEET (continued)

20. Ignition Oven:
Date Scale last calibrated _____
Brand. _____
21. Truck Body Release Agent:
 Brand Name: _____
22. Sieve Shaker
- a. Motorized shaker having a horizontal sieving motion and a tapping action (or one of equal performance as determined by the Division Chief)
- b. Equipped with an automatic 0 to 30 minute timer capable of turning off the shaker after a predetermined 0 to 30 minute time period
- c. Brand Name: _____
- d. Shaking Action: Good Fair Unacceptable
- e. Sieve retaining & Hold-down Good Fair Unacceptable
- f. Able to hold a 15 in. (380 mm) nest of sieves Yes No
- g. Timer accuracy: Acceptable Unacceptable

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 7 of 9

MIX PLANT FIELD LABORATORY – APPARATUS INSPECTION SHEET (continued)

23. Sieves: Set of U.S. Standard 8 in. (200 mm) minimum for Marshal laboratories and 12 in. (300 mm) sieves minimum for Superpave Laboratories ; minimum of one each of the following:

- | | |
|--|---|
| <input type="checkbox"/> Pan (May Be Half Height) | <input type="checkbox"/> #200 (75 μ m) (May Be Half Height) |
| <input type="checkbox"/> #100(150 μ m)(May Be Half Height) | <input type="checkbox"/> #50(300 μ m) (May Be Half Height) |
| <input type="checkbox"/> #30(600 μ m) (May Be Half Height) | <input type="checkbox"/> #16(1.18mm) (May Be Half Height) |
| <input type="checkbox"/> #8(2.36mm) (May Be Half Height) | <input type="checkbox"/> #4(4.75 mm) |
| <input type="checkbox"/> 3/8" (6.3mm) | <input type="checkbox"/> 1/2" (9.5 mm) |
| <input type="checkbox"/> 3/4" (19 mm) | <input type="checkbox"/> 1" (25 mm) |
| <input type="checkbox"/> 1 1/2" (37.5 mm) | <input type="checkbox"/> 2" (50mm) |

24. Electronic Balances

a. For Superpave laboratories, one 20kg. (42 lbs) capacity scale, with sufficient sensitivity to read to ± 0.1 grams. For the bowl determination method the balance shall be equipped with a suitable suspension apparatus and holder to permit weighing the sample while suspended from the center of the scale pan or balance.

a. For Marshal laboratories, 1500g capacity; 1 g sensitivity

b. Type: _____

b. Type: _____

c. Brand Name: _____

c. Brand Name: _____

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 8 of 9

MIX PLANT FIELD LABORATORY – APPARATUS INSPECTION SHEET (continued)

- 25. Workbench: Adequate in Size
- 26. Sampling table: Adequate size for quartering samples and cooling theoretical gravities 36 in. x 36 in. (914 mm x 914 mm)

- 27. Marshall Mold Block
 - a. Wood block dimensions: 8 in. x 8 in. x 18 in. (203 mm x 203 mm x 457 mm)
 - b. Steel Plate dimension: 12 in. x 12 in. x 1 in. (304 mm x 304 mm x 25 mm)
 - c. Steel plate to be plum and level
 - d. Block to be firmly attached to a concrete slab or floor

- 28. Mechanical Marshall Hammer
 - a. Automatically compacts sample and shuts off motor after desired number of strokes
 - b. Trip hammer falls the same distance for every stroke
 - c. Spring-loaded clamp ring to hold molds in position for easy insertion and removal from compactor

- 29. Marshall Molds
 - a. Two-mold cylinders, one base plate, one extension collar, one mechanical mold extractor
 - b. A sufficient amount of 4 in. (102 mm) paper disks
 - c. Molds, upper collar and base plate fit together freely

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM MAT-406 (REV 1-07) FIELD LABORATORY (Mix Plant) - APPARATUS INSPECTION SHEET
Page 9 of 9

MIX PLANT FIELD LABORATORY – APPARATUS INSPECTION SHEET (continued)

30. Sampling Platform or Catwalk (FORM 415)*

- a. Safe and adequate with step access and railing to accommodate the inspector. *If two mixing plants, one platform may be used for both plants, Platform must be as close to the laboratory as traffic patterns allow.
- b. Located a safe distance from plant and a maximum of 75 ft (25 m) from the laboratory entrance. , Platform must be as close to the laboratory as traffic patterns allow.
- c. Located so that plant traffic flow is not impeded.
- d. Height of platform adequate to sample any size truck
- e. Platform permanently anchored and wobble free
- f. Sampling Platform structure: no visible weak or rotted materials
- g. General Condition: Acceptable Unacceptable
- h. Sufficient lighting for night work – Describe:

Plant: _____ **Location** _____

Inspected By: _____ **Date:** _____

On the above date, the following deficiencies were found in your Plant/Laboratory.

Item	Deficiency
1	
2	
3	
4	
5	
6	
7	
8	
9	
10	

Please make the necessary corrections as soon as possible.

Failure to correct the indicated deficiencies may result in loss of State approval.

Inspector
Connecticut Department of Transportation
Division of Materials Testing

State of Connecticut Department of Transportation
 Division of Materials Testing
 MAT-412cm revision 12/16

Project Number:				Material Code:				Curb Mix				Production Date:									
Vendor Number:				Mix Time (Dry-Wet):								Contract:									
Plant:				Technician Name(Print):								Departure Tonnage:									
Location:				Test Date				Test Date				Test Date									
Mix Size:				9.5 mm 50 gyrations				Test Time				Test Time									
Percent RAP:								Load Number				Load Number									
Rap AC:		Total AC		AC Range		Truck Temp.				Truck Temp.											
Production AC:				6.5 - 0.4		Sublot Number				Sublot Number											
Input only one value for each test below (Oven).				Plant / Silo Number								Plant / Silo Number									
Correction Factor / Ignition Oven Ticket Information				Mixture Mass on Ticket								Mixture Mass on Ticket									
Test		Correction Factor		Oven ID		Wt. Loss				Wt. Loss											
Test 1						% Loss				% Loss											
Test 2						Temp Comp				Temp Comp											
Test 3						Mix Moisture				Mix Moisture											
D.O.T. INSPECTORS ENTER YOUR NAME IN THE CELLS TO THE RIGHT PER TEST WITNESSED				Pb by Ignition oven								Pb by Ignition oven									
Inch	mm	Production Tolerance	JMF	Sieve Weights	Passing	Cumm. Passing	Sieve Weights	Passing	Cumm. Passing	Sieve Weights	Passing	Cumm. Passing									
JMF Binder Content																					
#200	0.075	2.0																			
#100	0.150																				
#50	0.300	4																			
#30	0.600	5																			
#16	1.18																				
#8	2.36	6																			
#4	4.75	7																			
3/8"	9.5	8																			
1/2"	12.5																				
3/4"	19.0																				
		Total Wt.																			
Temperature / Weather				JMF DATE / Notes																	
Binder				Aggregate		1"/Other		1/2"		3/8"		RAP		Sand #1		Sand #2		Sand #3/Other		Virgin Binder	
Binder Grade				Source																	
Binder Source				JMF Cold Feed %																	
Antistrip Source				Plant Cold Feed Setting																	
Antistrip %				Cold Feed Setting to 100%																N/A	
WMA Technology				Aggregate		Bin 5/Other		Bin 4		Bin 3		Bin 2		Bin 1		RAP		Virgin Binder			
Technology				JMF Hot Bin %																	
Name				Plant Hot Bin Settings		A103															
Rate (%)				Hot Bin Settings to 100%														N/A			

State of Connecticut Department of Transportation Division Of Materials Testing
MAT-412s revision 11/16

Project Number:		Rt/Town		Gyrations:			Material Code:			Production Date:					
Vendor Number:		Lot		Mix Time (Dry-Wet):			NETTCP ID #:			Contract:					
Plant / Location: /				Technician Name(Print):						Daily Departure Tonnage in Lot :					
Estimated Total Project Tonnage for mix				Test Date/Time		Test Date/Time		Test Date/Time		Test Date/Time					
Type of Lot				Load Number		Load Number		Load Number		Load Number					
Today Results Complete Lot ?				Truck Temp.		Truck Temp.		Truck Temp.		Truck Temp.					
Mix Size:		RAP Daily (dried & w/o IO CF) Ignition Oven Pb		Sublot Number		Sublot Number		Sublot Number		Sublot Number					
Percent RAP:		JMF RAP IO CF		Gyro Temp. (1)-(2)		Gyro Temp. (1)-(2)		Gyro Temp. (1)-(2)		Gyro Temp. (1)-(2)					
Corrected Rap Pb:		Total AC		Minimum AC		Plant / Silo Number		Silo Number		Silo Number					
Virgin Pb:		Mixture Mass on Ticket		Mixture Mass on Ticket		Mixture Mass on Ticket		Mixture Mass on Ticket		Mixture Mass on Ticket					
Correction Factor / Ignition Oven Ticket Information				Wt. Loss		Wt. Loss		Wt. Loss		Wt. Loss					
Ext. Weight After Test				Ext. Weight After Test		Ext. Weight After Test		Ext. Weight After Test		Ext. Weight After Test					
Test		Correction Factor		Oven ID		% Loss		% Loss		% Loss					
Test 1		Temp Comp		Temp Comp		Temp Comp		Temp Comp		Temp Comp					
Test 2		Mix Moisture (T 329)		Mix Moisture (T 329)		Mix Moisture (T 329)		Mix Moisture (T 329)		Mix Moisture (T 329)					
Test 3		Pb by AASHTO T 308		Pb by AASHTO T 308		Pb by AASHTO T 308		Pb by AASHTO T 308		Pb by AASHTO T 308					
D.O.T. INSPECTORS ENTER YOUR NAME IN THE CELLS TO THE RIGHT PER TEST WITNESSED				Pb from Plant/Truck Ticket		Pb from Plant/Truck Ticket		Pb from Plant/Truck Ticket		Pb from Plant/Truck Ticket					
Pb Difference				Pb Difference		Pb Difference		Pb Difference		Pb Difference					
Inch		mm		Control Points		Prod Range for +Adj		JMF Target		Sieve Weights		Passing		Cumm. Passing (AASHTO T 30)	
Total Binder Content		Sieve Weights		Passing		Cumm. Passing (AASHTO T 30)		Sieve Weights		Passing		Cumm. Passing (AASHTO T 30)		Sieve Weights	
Passing		Cumm. Passing (AASHTO T 30)		Sieve Weights		Passing		Cumm. Passing (AASHTO T 30)		Sieve Weights		Passing		Cumm. Passing (AASHTO T 30)	
#200		0.075													
#100		0.150													
#50		0.300													
#30		0.600													
#16		1.18													
#8		2.36													
#4		4.75													
3/8"		9.5													
1/2"		12.5													
3/4"		19.0													
1"		25.0													
1 1/2"		37.5													
2"		50.0													
Total Wt.															
JMF Date:		Pba													
JMF Gsa:		VFA													
JMF Gsb:		Gse													
JMF Pba:		<small>Info only: VMA(Pb ticket, Est Gsb from Gse)</small>													
Specimen mass in air															
Saturated specimen mass in air (I)															
Less mass of specimen in water (J)															
Volume of specimen (I-J)															
Gmb @ Ndes (AASHTO T 166)															
Mass of HMA plus bowl in air (A)															
Less mass of bowl in air															
Mass of HMA in air															
Mass of HMA plus bowl in water															
Less mass of bowl in water															
Mass of HMA in water															
Volume of HMA															
Gmm (AASHTO T 209)		JMF Gmm		0.030											
Va (100-(Gmb @ Ndes / Gmm)*100)				1.0		4.0									
VMA (AASHTO R 35)				1.0											
Calculated Gsb from Gse / INFORMATION ONLY				<small>Gse-(0.8/0.6)*(JMG Gsa-JMFGsb)</small>											
VMA from calculated Gsb / INFORMATION ONLY				<small>From Gsb(F=0.6 / F=0.8)</small>											
HEIGHT (Hi) @ Nini															
Density to Nini															
HEIGHT(Hd) @ Ndes															
Temperature / Weather															
JMF Changes / Notes															
Binder		Aggregate		1"/Other		1/2"		3/8"		RAP		Sand #1		Sand #2	
Binder Grade		Source													
Binder Source		JMF Cold Feed %													
Antistrip Source		Plant Cold Feed Setting													
Antistrip %		Cold Feed Setting to 100%													
WMA Technology				Aggregate		Bin 5/Other		Bin 4		Bin 3		Bin 2		Bin 1	
Technology		Only for Batch Plants		JMF Hot Bin %		Bin 5/Other		Bin 4		Bin 3		Bin 2		Bin 1	
Name				Plant Hot Bin Settings											
Rate (%)				Hot Bin Settings to 100%											

State of Connecticut
Department of Transportation
Division of Materials Testing

MAT-429s rev 12/16

Plant		MIX #	Curb Mix
Location			
Plant Type/Capacity			
Submitted By			
Date Submitted			

Description	Size/Type of Aggregate	Source of Supply	Source Location	Blend Percent
CA-Aggregate 1				
CA-Aggregate 2				
CA-Aggregate 3				
CA/RAP-Aggregate 4				
FA-Aggregate 5				
FA-Aggregate 6				
FA-Aggregate 7				

Description	Source of Supply	Laboratory Temperature Ranges	Production Temperature Ranges
Asphalt Binder Grade		Mfg recommended mix temp range	Mfg recommended mix temp range
Antistrip Percentage		Mfg recomm compaction temp range	Mfg recomm compaction temp range
Warm Mix Technology	Water inject rate per weight of binder or	additive rate per weight of binder	or additive rate per total weight of mix

Nom. Size	Contractor Data								Specifications		Contractor JMF
9.5mm L1	Agg 1	Agg 2	Agg 3	Agg 4	Agg 5	Agg 6	Agg 7	Calc.	Control Points		
	Description	CA	CA	CA	CA/RAP	FA	FA	FA	JMF	Submitted	
Blend Percent									Min %	Max %	
0.075									3.0	8.0	
0.150											
0.300									10.0	30.0	
0.600									20.0	40.0	
1.18											
2.36									40.0	70.0	
4.75									65.0	87.0	
9.5									95.0	100.0	
12.5									100.0	100.0	
19.0											
25.0											

Production Virgin Pb		RAP AC	Total/Target AC
Total binder in RAP			

Test Results	MIX TEMP	COMPACTION TEMP	Mix Times	WET
Gmm	AC Range	6.5 - 9.0		DRY

Gmb - Ndes	
Gmb - Nini	
Height-Ndes	
Height-Ndes	
Height-Nini	
% Gmm at Nini	
Gse	
Va - Ndes	
Ignition Oven Corr. Factor	

User Notes:

- White cells to be completed by the Contractor.
- Production Pb (w/ RAP) = The total production binder in the HMA.
- Contractor JMF should reflect extracted asphalt and washed sieved analysis.
- List all the JMF Changes in the "JMF Changes" sheet.
- Volumetric data for total asphalt content.
- Complete the % passing per each specimen up to at least the 25.0mm sieve.
- Add binder specific gravity data if it differs from 1.033.

Remarks:	
-----------------	--

Accepted By		Date
--------------------	--	-------------

State of Connecticut
Department of Transportation
Division of Materials Testing

MAT-429s rev 11/2016

Plant		MIX # Example "4000" or "4000R" or "4000- W" or "4000R-W"	
Location			
Plant Type/Capacity			
Submitted By			
Date Submitted			

Description	Size/Type of Aggregate	Source of Supply	Source Location	Blend Percent
CA-Aggregate 1				
CA-Aggregate 2				
CA-Aggregate 3				
CA/RAP-Aggregate 4				
FA-Aggregate 5				
FA-Aggregate 6				
FA-Aggregate 7				

Description	Source of Supply	Temperature Ranges (Without WMA)	Temperature Ranges (With WMA)
Asphalt Binder Grade		Mfg recommended mix temp range	Mfg recommended mix temp range
Antistrip Percentage		Mfg recomm compaction temp range	Mfg recomm compaction temp range
Warm Mix Technology	Where WMA Additive is Added?	Water injection or additive rate per weight of binder	or additive rate per total weight of mix

Nom. Size	Contractor Data								Specifications	Contractor JMF
	Agg 1 CA	Agg 2 CA	Agg 3 CA	Agg 4 CA/RAP	Agg 5 FA	Agg 6 FA	Agg 7 FA	Calc. JMF		
Description									Comp.	
Blend Percent										Min % Max % Submitted
0.075										
0.150										
0.300										
0.600										
1.18										
2.36										
4.75										
9.5										
12.5										
19.0										
25.0										
37.5										
50.0										

Production Virgin Pb		RAP AC	Total/Target AC
Total binder in RAP			
Gsa			
Gsb			

Test Results	MIX TEMP	COMPACTION TEMP	Mix Times	WET
Gmm	Minimum AC	PCS		DRY

User Notes:

- White cells to be completed by the Contractor.
- Production Pb (w/ RAP) = The total production binder in the HMA.
- Contractor JMF should reflect extracted asphalt and washed sieved analysis.
- List all the JMF Changes in the "JMF Changes" sheet.
- Volumetric data for total asphalt content.
- Complete the % passing per each specimen up to at least the 25.0mm sieve.
- Add binder specific gravity data if it differs from 1.033.

Gmb - Nmax	
Gmb - Ndes	
Gmb - Nini	
Height-Nmax	
% Gmm at Nmax	
Height-Ndes	
Height-Nini	
% Gmm at Nini	
Gse	
Multiplier (AASHTO R35 App. X1.2)	
Va - Ndes	
VMA	
VFA - Ndes	
Pba	
Pba/Pw	
Pbe	
Dust/Pbe	
TSR (AASHTO T283 (M))	
Ignition Oven Corr. Factor	

Remarks:

Accepted 106	Date
---------------------	------

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

1. Basic Information	
A. Origin of Materials	
1. Name and address of property owner or lessee	
Name	
Address	

2. Name, title, and telephone number of company contact person	
Name	
Title	
Telephone number	

3. Name, title, telephone number and certifications, if applicable, of the person(s) responsible for the QCPFA	
Name	
Title	
Telephone number	
Certifications	
Name	
Title	
Telephone number	
Certifications	

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

2. Controls Implemented During Excavation

A. Overburden Removal

1. To what depth is the overburden removed?

Depth	
-------	--

2. What is the minimum separation between the edge of overburden and the production face??

Separation	
------------	--

3. How will sloughed overburden be avoided?

Method of Avoidance	
---------------------	--

B. Mining Controls

1. Describe how excavation will be performed so that intended materials are being mined?

Description	
-------------	--

2. Who will make the determination?

Name	
Title	
Telephone number	
Certifications	

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

2. Controls Implemented During Excavation continued

B. Mining Controls cont.

3. How will clean-out materials from old ramps, overlying lifts, striping or floor leveling be handled?

Description	
-------------	--

4. What tests are being utilized to verify that intended materials are being mined?

Description	
-------------	--

5. How will it be assured that your material meet all specifications as required by the latest ConnDOT M.04 criteria before it is shipped?

Description	
-------------	--

C. Product Uniformity Controls

1. Describe method of loading out shot rock or sand & gravel from a face to minimize non-uniformity?

Description	
-------------	--

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

2. Controls Implemented During Excavation continued	
C. Product Uniformity Controls cont.	
2. Describe any other procedure(s) used to minimize non-uniformity?	
Description	

3. Processing Controls	
A. Type of processing	
1. Describe the type of processing being done on the material.	
Description	

2. Describe the type of equipment used during processing.	
Description	

3. Describe how non-uniformity will be minimized during aggregate processing.	
Description	

4. Describe how aggregate quality will be improved by processing.	
Description	

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

4. Stockpiling	
A. Stockpiles	
1. Describe the height, width of stockpile.	
Height	
Width	

2. Describe the method by which the stockpile is created, by haul unit, belt system etc...	
Description	

3. Describe how non-uniformity will be minimized in the stockpiles.	
Description	

4. Describe how contamination will be minimized in the stockpiles.	
Description	

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

4. Stockpiling continued	
A. Stockpiles	
5. Describe how the stockpiles will be monitored for non-uniformity and contamination:	
a. How will non-uniformity and contamination be visually monitored, and by who?	
Description	
Who will be monitoring?	

6. What physical tests will be employed to monitor quality of fine aggregate?	
Description	

7. What is the minimum testing frequency?	
Description	

8. Who will do the test?	
Description	

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

4. Stockpiling continued	
A. Stockpiles cont.	
8. What actions will be taken when the material does not meet the requirements?	
Description	

5. Records	
A. Method	
1. What quality monitoring records are maintained?	
Description	

2. Where are the quality monitoring records maintained?	
Description	

3. Who is responsible for maintaining these records?	
Name	
Title	
Telephone number	
Name	
Title	
Telephone number	

**Quality Control Plan for Fine Aggregates used in HMA
QCPFA**

Please submit to the DMT via e-mail at, DOT.MatTesting@ct.gov

**STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION
DIVISION OF MATERIALS TESTING**

FORM 433(REV 1-29-07) Ignition Oven Correction Factor Work Sheet Page 1 of 1

Plant: _____ **Location** _____

State Inspector: _____ **Date:** _____

Contractor's Rep: _____

All Aggregates Should Be Burned At 538° C For 45 Minutes Each (If Material or Equipment Is Unable To Comply With This Process Revert To AASHTO T 308-05)

Material	Minimum Sample Size	Maximum Sample Size	Source	Correction Factors
1 1/4" **	4000 grams	4500 grams		
1"	3000 grams	3500 grams		
3/4"	2000 grams	2500 grams		
1/2"	1500 grams	2000 grams		
3/8"	1200 grams	1700 grams		
1/4"	1200 grams	1700 grams		
Stone Sand	1200 grams	1700 grams		
Blended Sand	1200 grams	1700 grams		
Natural Sand "A"	1200 grams	1700 grams		
Natural Sand "B"	1200 grams	1700 grams		
Rap	1200 grams	1700 grams		
Other				


Specimen size shall not exceed 500 grams greater than the minimum sample size

**** For ovens with a max sample size of 4,000 grams use 3,500 grams for 1 1/4" ****

In Accordance With: AASHTO T 308-05(M)

State of Connecticut Department of Transportation
 Division of Materials Testing
 Daily Plant Adjustment Form MAT-438non-PWL

Project #	0	Day/Night	Day	Contract Year	0
Location (RT/Town)	0	PO #		Payable Tons	
Date Placed	1/0/1900	District #		Cost per ton (US\$)	
<i>Mix</i>	<i>Level</i>	<i>Material Code</i>	<i>DMT ID</i>	<i>Min Pb</i>	
		0			
<i>Producer</i>	<i>Plant Location</i>	<i>Vendor #</i>			
		0			
Plant Adjustment Detail					
<i>Plant Test</i>		<i>Va Result</i>	<i>Va Adjustment</i>	<i>Pb Result</i>	<i>Pb Adjustment</i>
1					
2					
3					
4					
5					
6					
AVa					
APb					
Plant Adjustment Tsd=(Ava + APb) X Tons			0.0000	Adjusted Tons	0.00
Cost Adjustment Tsd X Unit Price					\$0.00
				Data entered by:	Matt Garretson
				Checked by:	



STATE OF CONNECTICUT

Department of Transportation
 Division of Materials Testing
 280 West Street
 Rocky Hill, CT 06067

Rev. 12/16

INDEPENDENT ASSURANCE

Report of WITNESS TEST
MAT-600

Name (Tester): _____ NETTCP#: _____

IA Sampled By: _____ Date (Witness Test): _____

Location: _____

Type of Material: _____ Project No.: _____

AASHTO TEST METHODS WITNESSED	YES	NO	REMARKS
T 168 – SAMPLING BITUMINOUS MIXTURES	<input type="checkbox"/>	<input type="checkbox"/>	
R 47 – SAMPLE REDUCTION	<input type="checkbox"/>	<input type="checkbox"/>	
T 308 – ASPHALT CONTENT – IGNITION OVEN	<input type="checkbox"/>	<input type="checkbox"/>	
T 30 – SIEVE ANALYSIS	<input type="checkbox"/>	<input type="checkbox"/>	
T 312 – PREPARATION OF GYRATORY SAMPLE	<input type="checkbox"/>	<input type="checkbox"/>	
T 166 – BULK SPECIFIC GRAVITY (Gmb)	<input type="checkbox"/>	<input type="checkbox"/>	
T 209 – THEORETICAL MAXIMUM (Gmm)	<input type="checkbox"/>	<input type="checkbox"/>	
T 185 – SPECIFIC GRAVITY – COARSE AGGREGATE	<input type="checkbox"/>	<input type="checkbox"/>	
T 184 – SPECIFIC GRAVITY – FINE AGGREGATE	<input type="checkbox"/>	<input type="checkbox"/>	
T 283 – MOISTURE INDUCED DAMAGE – (TSR)	<input type="checkbox"/>	<input type="checkbox"/>	
T 255 – MOISTURE CONTENT	<input type="checkbox"/>	<input type="checkbox"/>	
T 304 – UN-COMPACTED VOID CONTENT	<input type="checkbox"/>	<input type="checkbox"/>	
T 176 – SAND EQUIVALENT TEST	<input type="checkbox"/>	<input type="checkbox"/>	
BOWL WEIGHTS	<input type="checkbox"/>	<input type="checkbox"/>	
GYRATORY ANGLE	<input type="checkbox"/>	<input type="checkbox"/>	
THERMOMETER CHECK	<input type="checkbox"/>	<input type="checkbox"/>	

COMMENTS:

WAS A SPLIT SAMPLE TAKEN YES NO SAMPLE NO.: _____

SAMPLE GRADE:	Pb:		Sieve:		Gmb:		Gmm:	
---------------	------------	--	---------------	--	-------------	--	-------------	--

Enter Start and End times for time from and to work station or home.				Total Shift Hours	
Start:		End:		Total Regular Hours:	
Enter Start and End times for actual time at the plant.				Total Overtime Hours:	
Start:		End:		Vacation / Sick / PL:	

Appendix B – Final Materials Certification

A Final Materials Certificate (FMC) summarizes the results of acceptance testing of the material used on each FHWA-funded project and select state-funded projects. Materials used on these projects that require acceptance testing must be sampled and tested in accordance with the “Schedule of Minimum Requirements for Acceptance Testing,” Chapter 8 of this manual. It is imperative that the represented quantity of each material with a sampling frequency of “one per quantity” or “one per x units” accumulate to or exceed the total quantity of that material used on the project. For some materials the minimum schedule does not indicate a testing frequency. In this instance, a single sample will be adequate to represent that material incorporated into the project.

In addition, the Division of Materials Testing (DMT) documents the process of materials testing on the project site by checking the sampling and testing procedures performed by inspection personnel in accordance with the “Schedule of Minimum Requirements for Assurance Testing,” Chapter 9 of this manual. Testing equipment is also checked to ensure that the test results are valid. Discrepancies in this testing are investigated and rectified immediately. The DMT reports the results of this testing to the Federal Highway Administration on an annual basis.

To initiate the development of a FMC, a request from the appropriate District office staff for a FMC is sent to the DMT. Following a review of project records, DMT staff issue a memorandum to the project personnel entitled “Test Coverage Required for FINAL CERTIFICATION” that lists all testing deficiencies and rejected materials not previously documented.

It is the responsibility of the Transportation Supervising Engineers of each DMT section to identify material that did not meet the project specifications, was not documented correctly, and was permanently incorporated into the project. This is accomplished through the issuance of a FMC listing exceptions to the specifications. When all materials used on the project are sampled and found to meet the specification or are documented properly, the DMT issues a FMC without exceptions.

When tested material does not meet specification, a MAT-103 “Report of Rejected Material” form is used to document how the deficiency was addressed. This form must be completed for any rejected material samples and must include the signatures of appropriate Project and District personnel acknowledging the rejection.

Section 1 of the Mat-103 form under the heading “Action Taken” describes the physical action taken to retest or replace the material. This addresses when rejected materials were removed and replaced with acceptable material or were resampled and found acceptable. The Sample ID of the acceptable re-test is required on this form. If physical action was not taken, Section 2 of the MAT-103 must be completed.

Section 2 of the Mat-103 form under the heading “Acceptance of Rejected Material without Action” documents the acceptance of noncompliant materials or minor quantities

of untested materials in accordance with Section 1.06.02 or Section 1.06.04 of the Department's Standard Specification. Section 1.06.02 states that the Engineer may accept material or combination of materials and thereby waive noncomplying test results, provided that the following conditions are met:

1. Results of prior and subsequent series of tests of the material or materials from the same source or sources are found satisfactory.
2. The incidence and degree of nonconformance with the Contract requirements are, in the Engineer's judgment, within reasonable limits.
3. The contractor, in the Engineer's judgment, had diligently exercised material controls consistent with good practices.
4. No adverse affect on the value or serviceability of the completed work could result.

Section 1.06.04 states that the Engineer may accept a material or combination of materials provided that an equitable reduction of the payment is made. Any credits, allowances, warranties, or other conditions of acceptance must be listed.

Projects that did not perform any testing would obviously not meet the above criteria, while a project that utilized minor amounts of nonconforming material from a producer who generally meets requirements may meet the above criteria. Exception can be taken and noted on the FMC if it is determined by DMT staff and the Transportation Principal Engineer in the DMT that the alternate acceptance criteria has not been met for the materials in question.

Adequate Assurance Testing: Project related assurance testing is required as specified in the Schedule of Minimum Requirements for Assurance Testing (Chapter 9) or exceptions for deficiencies in assurance testing will be noted on the FMC as such. This testing does not include independent assurance testing that is performed within the DMT and is not directly associated with a project.

For projects classified as vertical or non-roadway: In accordance with section 1-2207 of the Construction Manual, "A FMC will not be provided by the DMT for facilities (vertical/non-roadway) projects; this information will be retained by the DMT for information only purposes."

Examples of Final Materials Certificates follow.

(THE FOLLOWING MEMORANDUM IS ADDRESSED TO THE DISTRICT ENGINEER AND IS REQUIRED FOR ALL FEDERAL AID PROJECTS.)

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

subject: FINAL MATERIALS CERTIFICATION
STATE PROJECT NUMBER: [XXXX-XXXX]
FAP NUMBER: [XXXX (XXX)]

memorandum

date: [Month, Day, Year]

to: [Name]
District Engineer
District [X] Construction
Bureau of Engineering and Construction

from: [Name]
Transportation Principal Engineer
Division of Materials Testing
Bureau of Engineering and Construction

THIS IS TO CERTIFY THAT:

Results of tests on acceptance samples indicate the materials incorporated in the construction work and the construction operations controlled by sampling and testing were in conformity with approved plans and specifications, and that such results compare favorably with the results of independent assurance sampling and testing.

Exceptions to the plans and specifications are documented in the project records and are also listed below:

NONE (or exceptions included as follows:)

<u>Item #</u>	<u>Description</u>	<u>Quantity</u>	<u>Reason</u>
---------------	--------------------	-----------------	---------------

If you have any questions regarding this certification, please contact [Name], Transportation Supervising Engineer, at (860) 258-[XXXX] or [Email address].

[Author]:[Typist]/[Drive location/file name]

cc: [Name of Construction Division Chief]
[Name of Federal Billing Representatives]
[Name of Assistant District Engineer]
[Name of District OOC Liaison]
[DMT Representatives]
[DMT Author] - DMT Files
DOT FedBilling
DOT ConstD[#]

(THE FOLLOWING MEMORANDUM IS ADDRESSED TO THE DISTRICT MAINTENANCE DIRECTOR AND IS REQUIRED FOR ALL MAINTENANCE PROJECTS FUNDED WITH FEDERAL AID FUNDS.)

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

subject: FINAL MATERIALS CERTIFICATION
STATE PROJECT NUMBER: [XXXX-XXXX]
FAP NUMBER: [XXXX (XXX)]

memorandum

date: [Month, Day, Year]

to: [Name]
Transportation Maintenance Director
District [X] Maintenance
Bureau of Engineering and Construction

from: [Name]
Transportation Principal Engineer
Division of Materials Testing
Bureau of Engineering and Construction

THIS IS TO CERTIFY THAT:

Results of tests on acceptance samples indicate the materials incorporated in the construction work and the construction operations controlled by sampling and testing were in conformity with approved plans and specifications, and that such results compare favorably with the results of independent assurance sampling and testing.

Exceptions to the plans and specifications are documented in the project records and are also listed below:

NONE (or exceptions included as follows:)

<u>Item #</u>	<u>Description</u>	<u>Quantity</u>	<u>Reason</u>
---------------	--------------------	-----------------	---------------

If you have any questions regarding this certification, please contact [Name], Transportation Supervising Engineer, at (860) 258-[XXXX] or [Email address].

[Author]:[Typist]/[Drive location/file name]

cc: [Name of Construction Division Chief]
[Name of Federal Billing Representatives]
[Name of District OOC Liaison]
[DMT Representatives]
[DMT Author] - DMT Files
DOT FedBilling
DOT ConstD[#]

APPENDIX C
SCOPE OF WORK
FABRICATION INSPECTION
For third-party testing agency

As determined by the Connecticut Department of Transportation's (Department) Division Chief, the testing agency shall provide qualified inspection and testing personnel to perform inspections, sampling, and testing of materials in the following areas:

- General Requirements
- Steel Fabrication - Scope
- Structural Steel Inspection - General
- Coatings Process Inspection
- Precast, Prestressed and Post- Tensioned Concrete Inspection

All inspections, sampling, and testing are to be done in accordance with applicable standards including, but not limited to, those described by the American Welding Society (AWS), National Association of Corrosion Engineers (NACE), American Association of State Highway Transportation Officials (AASHTO), and the American Society of Testing Materials (ASTM).

Personnel performing the inspection, sampling, or testing of specific materials may require certification that is administered by agencies such as the New England Transportation Technician Certification Program (NETTCP), American Concrete Institute (ACI), and others.

The purpose of this inspection, sampling, or testing is to assure conformance of the material to project specifications. As such, the Quality Assurance (QA) inspector may visually inspect, witness, sample, or test material during all phases of manufacture/fabrication/production. The primary function of the QA inspector is to assure the Engineer that the fabricator/producer is exercising adequate quality control during the entire fabrication/production process.

General Requirements

The testing agency shall:

1. Assume responsibility for the assigned inspection, sampling, or testing of materials as of the date stipulated by the Department in the formal notice to the testing agency to proceed with the work. This includes any partially completed work performed by the Department's former testing agency under the "Contract for Inspection, Sampling and Testing of Materials" concluded February 14, 2016.

2. Make no decisions and offer no advice or opinion to a proposed action by the manufacturer/fabricator/producer/contractor without first consulting with the Engineer. The Engineer is defined as the Division Chief or his duly authorized representative.
3. Provide all equipment required for the safe and comprehensive execution of the work including personal safety equipment such as clothing, hard hats, safety glasses, shoes, and gloves. This may also include appropriate means of transportation for some job classifications. All such equipment may be subject to the approval of the Engineer.
4. Adhere to the Travel Expense Guidelines dated April 19, 2016 for the purpose of determining travel expenses and work locations.

The Inspector shall:

1. Be certified in the applicable field and have a thorough knowledge of the State of Connecticut - Department of Transportation - Standard Specifications for Roads, Bridges and Incidental Construction (Form 816 as supplemented), and project specifications, including approved shop drawings.

Specific information on scope of work, personnel, and reporting requirements for each area are provided in the following pages.

Steel Fabrication - Scope

The testing agency shall submit to the Department of Transportation, Division of Materials Testing, 280 West Street, Rocky Hill, CT 06067, three copies of daily reports on a weekly basis, or as directed, for each Department project where inspection services were performed indicating the status of each member in fabrication and the shipping status of each completed member. Report cover sheets and the body of the reports must be generated with a word processing computer application and output on 8.5" X 11" white paper. Handwritten reports will not be accepted. The reports shall include daily notes of the testing agency's plant inspector and any nondestructive testing reports and shipping documents that were obtained during the day. These reports shall further include a daily summary of the number of hours worked. Weekly reports shall be due at the Department of Transportation's Division of Materials Testing (DMT) no later than seven days after the close of the period covered by such reports. The final weekly report submitted for a single project shall include all certified mill test reports documenting all steel used in the project work.

Due to their critical function as load-bearing units of bridges and structures, structural steel members must be constructed in strict conformance with the specifications. To assure this conformance, the DMT assigns a QA inspector to the manufacturing/fabrication plant to inspect, in detail, all phases of manufacture/fabrication. The primary function of the QA inspector is to assure the Engineer that the fabricator is exercising adequate quality control during the entire fabrication process. Should the inspector discover deficiencies or witness a lack of quality control, it is imperative that the Engineer be notified immediately so that corrective action can be initiated.

These specifications are not to be considered as covering every aspect of the testing agency's responsibilities, and they shall in no way relieve the testing agency of the responsibility for the inspection of all requirements of the plans, specifications, and special provisions that are pertinent to the work.

Structural Steel Inspection - General

The inspector shall:

1. Commence inspection with the beginning of fabrication and continue throughout the entire fabrication process, or as directed by the Engineer.
2. Throughout the fabrication, document information on standardized forms provided by the Engineer or on an acceptable substitution to the Engineer. All such documentation shall be neat and legible to the satisfaction of the Engineer.
3. Confirm that the proper approval has been granted for all shop drawings used during fabrication/manufacture. This should be accomplished before fabrication; however, it may be done during or after fabrication. Should the fabricator decide to commence, continue, or deliver work without proper approval; the inspector is required to immediately notify the fabricator's Quality Control (QC) Manager that the fabricator is proceeding at his own risk, and notify the Engineer that work began, is ongoing, or is being shipped without approved drawings. Inspector must note names, times, and summary of the discussion in his daily report.
4. Be cognizant of the conditions of fabrication including the time of delivery, desired order of shipment, and any special features in connection with delivery.
5. Obtain the records of the chemical and physical tests of the heat numbers of material from the mill. Review mill test reports for conformance to specifications and report status to the Engineer through daily reports.

6. Compare heat marks with those on the mill test reports. Should there be any doubt about the identity or correctness of the metal, samples of the metal may be taken and tested by the fabricator to ascertain conformance with the appropriate specifications.
7. See that material is properly identified throughout the entire fabrication process.
8. Conduct a surface inspection of a sample of incoming metals with attention to defects such as piping, cracks, laminations, buckles and kinks.
9. Observe that material not immediately used is properly stored and identified.
10. Ensure that no material from shop stock is used without approval or without properly documented test reports. Pitted or corroded material shall not be used.
11. Document the position of heat numbers in main members by means of diagrams showing member elevations and associated heat numbers.
12. Check a sample of cuts for neatness and trueness, and ensure that the proper method of cutting is used.
13. Inspect a sample of templates for accuracy.
14. Check a sample of splices, joints, and connections in accordance with appropriate specifications.
15. Check the fit and positioning of a sample of shop assemblies, and ensure that members are clearly match-marked when members that are to be field-spliced are given a shop laydown assembly.
16. Be present when material is being cambered or straightened by the application of heat to ensure use of proper procedures and temperature requirements. Confirm that only approved methods are being utilized.
17. Inspect a sample of completed work for general finish and workmanship. Check a sample of finished members for dimensions, proper section, connection locations, detailing and other related features. Measure and record on approved forms the overall length, length center-to-center of bearings, and camber of a sample of main members.

18. Check that surfaces of “weathering” steel and surface areas to receive protective coatings are properly prepared and that coatings are applied in accordance with specifications. The coating dates of all material shall be recorded in the daily report.
19. Ascertain that all welders, welding operators, and tackers have been properly qualified and that welding procedures have been properly followed. Copies of welder certifications and approved welding procedures shall be incorporated into the project records. Actual welding should be inspected regularly to ensure that the minimum temperature requirements for welding are being maintained, that the specified joint-welding procedures are being followed, and that the required preheat, interpass and postheat temperatures are being utilized.
20. Witness all nondestructive testing of welds and sign all reports of such testing. Ultrasonic inspection shall be witnessed and the interpretation of the results verified by the testing agency personnel, who shall be qualified NDT Level II or better in accordance with requirements of the American Society for Nondestructive Testing’s Recommended Practice Number SNT-TC-1A and Supplement C, Ultrasonic Testing Method.
21. Check to ensure use of proper electrodes, electrode-flux combination, or grade of weld metal for the steel specified. Review materials certification for electrodes or electrode-flux combinations. Regularly inspect storage conditions and care of electrodes and flux for conformance to specifications. Check welding equipment for proper operation and proper calibration.
22. Perform visual inspection of a sample of completed welds and the base metals for cracks, notches, undercutting, and other defects.
23. Check a sample of the finished welds for proper profile and cross-section.
24. Prior to shipment of the material, ensure that the fabricator’s QC representative has inspected the members and reviewed the shipping documents for completeness. Determining the acceptability of each piece prior to shipping is the sole responsibility of the fabricator. The testing agency shall ensure that members are marked in such a manner as to enable the Department’s field representative to correlate shop inspection reports and shipping reports with the appropriate members.
25. Report and record all defects or problems observed, as well as all corresponding corrective action taken within their daily reports submitted to the Department.

Coatings Process Inspection

The NACE coating inspector shall fully complete a paint inspection checklist for all coated materials, take necessary samples of protective coatings for testing as directed by the Department's DMT, and permit only approved material to be used. The NACE inspector shall be present at the fabrication/coating shop during all cleaning and coating operations. The daily coating activity shall be recorded in the latest edition of the NACE Coating Inspector's log book and shall commence prior to the structural steel surface preparation. The testing agency shall be responsible for the purchase of the log books and shall provide them to each NACE inspector. At the time of material shipment from the fabricator's plant, the NACE inspector shall stamp the front page of each inspector's log book used during the coating operation. The stamped book shall indicate the inspector's NACE certification number, expiration date, printed name of the inspector, and shall be signed by the inspector. The log book(s) shall then be furnished to the Senior Fabrication Inspector to be included with the submission of the weekly reports.

Precast, Prestressed and Post-Tensioned Concrete Inspection

Due to their critical function as load-bearing units of bridges and structures, precast, prestressed, and post-tensioned concrete members must be constructed in strict conformance with the specifications. To assure this conformance, the DMT assigns a QA inspector to the manufacturing/fabrication plant to inspect, in detail, all phases of manufacture/fabrication. The primary function of the QA inspector is to assure the Engineer that the fabricator is exercising adequate quality control during the entire fabrication process. Should the inspector discover deficiencies or witness a lack of quality control, it is imperative that the Engineer be notified immediately so that corrective action can be initiated.

The inspector shall perform the following:

Sampling

The following component materials shall be sampled for testing in accordance with standard Department procedures and frequencies listed below:

1. Portland cement: Shall be from a qualified source. Each load shall be accepted by certification. Samples shall be taken as directed by the Engineer.
2. Aggregate: Samples from bins or stockpiles each month for each source of supply, or as directed by the Engineer.
3. Admixtures: Only qualified admixtures are to be used. Samples are to be taken as directed by the Engineer.

4. Prestressing steel strand: Sample each reel or coil in accordance with Standard Specifications, Article M.14.01-2.
5. Post-tensioning tendons and anchorages: Sample as per Special Provisions.
6. Reinforcing steel: From each source, a 5-foot (1.5 m) sample of each size for every 200 tons (181.4 metric tons), with a minimum of one sample of each size from each source per project.

Inspection of Plant Facilities and Manufacturing Procedures

The plant facilities shall be inspected annually or as directed by the Engineer. A form provided by the Department shall be utilized as a guide to plant facilities inspection. As a minimum, the following shall be inspected:

1. Storage and handling of materials.
2. Batching, mixing, transportation and placement of concrete.
3. Curing method and apparatus (i.e., steam, radiant heat or other approved method) including provision for recording time and temperature data during the curing cycle.
4. Concrete testing equipment (i.e., compression-testing machine - should be calibrated every 12 months, pressure-type air meters, cylinder molds, slump cones, and unit weight apparatus) and facilities for moist-curing test cylinders in accordance with ASTM C 192.
5. Equipment and procedure for consolidation of concrete.
6. Construction and capacity of casting beds.
7. Dimensions, condition, and construction of forms.
8. Method and equipment for applying prestressing or post-tensioning forces.
9. Method and equipment for measuring prestressing or post-tensioning forces and the procedure for measuring elongation of strands or tendons.
10. Accuracy and calibration data of pressure gauges. (Gauges shall be calibrated at intervals not to exceed 6 months)

Inspection of Casting Bed

1. Check cleanliness, level, and alignment of form liner.
2. Check position of bulkheads for proper length of units and skewed or sloped ends, when applicable.
3. Inspect stringing of prestressing strands to ensure correct number and position of strands and location of "hold-downs."
4. For a sample of strands: inspect tension, measure elongation, and check gauge reading for proper force application. Force measurement of elongation and gauge reading shall check each other and the theoretical value shall be within 5 percent.
5. Witness retensioning at the non-jacking end of deflected strands and straight strands to verify application of the required prestressing force in accordance with the Standard Specifications, Article 5.14.03.
6. Inspect installation of a sample of post-tensioning tendons and anchorages, when applicable.
7. Check size, type, and location of a sample of reinforcing steel, hardware, and miscellaneous steel when placed in forms.
8. Inspect condition and alignment of a sample of side forms.
9. Check proper bracing and anchorage of casting bed and end anchorages.

Inspection of Concrete Operations

1. Inspect a sample of concrete delivered to forms for homogeneity and uniformity of successive batches.
2. Spot-check batching and mixing of concrete to assure that approved mix design and procedures are being used.
3. Witness/monitor sampling of concrete for quality control testing.
4. Witness slump, air tests, concrete temperature, and unit weight for conformance to specifications and accept or deem unacceptable on the basis of results.
5. Inspect placement, consolidation and finishing of concrete for conformance to specifications and accepted concrete practices.

6. For deck units, inspect internal void forms for material, size, and proper installation.
7. Check identification marker for required data and placement in unit.
8. Ensure that approved curing method is used and applied at proper time. If steam or radiant heat is used, ensure that required preset period is observed.

Inspection of Fabricated Units

1. Inspect a sample of units to determine if they were cured uniformly. Review the time/temperature record of curing cycle for specification compliance.
2. Witness testing of cylinders for required concrete strength prior to detensioning or removal of forms.
3. Verify dimensions, details, surface finish, and freedom from defects of a sample of finished units.
4. Verify proper marking and identification of units.
5. Witness application of protective compound to surfaces of precast catch basin and drop inlet tops, which will be exposed when in service.
6. Catch basin, drop inlets, manhole riser sections, bases, and appurtenances that exhibit the following may be recommended for rejection:
 - 6.1 Fractures or cracks passing through the wall, except for a single end crack that does not exceed the depth of the joint.
 - 6.2 Defects that indicate imperfect proportioning, mixing, or molding.
 - 6.3 Surface defects indicating honeycombed or open texture.
 - 6.4 Any continuous crack having a surface width of 0.01 in. (0.3mm) or more and extending for a length of 1.0 ft. (300mm) or more, regardless of position in the section wall.
 - 6.5 Damaged or cracked ends where such damage would prevent making a satisfactory joint.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department.

SCOPE OF WORK
MATERIAL TESTING INSPECTION
For Consultant third-party Testing Agency (Testing Agency)

As determined by the Connecticut Department of Transportation's (Department) Division Chief of Construction Services and Materials Testing (Division Chief), the Testing Agency shall provide qualified inspection and testing personnel to perform inspections, sampling, and testing of materials in the following areas:

- General Requirements
- Precast, Prestressed and Post-Tensioned Concrete Inspection
- HMA Plant Inspection
- Sampling Materials (i.e., Hot Mix Asphalt [HMA], aggregates) on Project Sites or Sources
- Testing In-Place Materials (HMA, aggregates) on Project Sites
- Testing Material Samples at Department Material Testing Facilities
- Inputting Test Results, Processing Request for Test (MAT-100) Forms, and Filing Documentation

All inspections, sampling, and testing are to be done in accordance with applicable standards including, but not limited to, those described by the American Welding Society (AWS), National Association of Corrosion Engineers (NACE), American Association of State Highway Transportation Officials (AASHTO), and the American Society of Testing Materials (ASTM).

Personnel performing the inspection, sampling, or testing of specific materials shall require certification that is administered by agencies such as the New England Transportation Technician Certification Program (NETTCP), American Concrete Institute (ACI), and others.

The purpose of this inspection, sampling, or testing is to assure conformance of the material to project specifications. The primary function of the Quality Assurance (QA) Inspector is to assure the Engineer that the fabricator/producer is exercising adequate quality control during the entire fabrication/production process. The Engineer is defined as the Division Chief or his duly authorized representative. As such, the QA Inspector shall visually inspect, witness, sample, or test material during all phases of manufacture/fabrication/production.

General Requirements

The Testing Agency shall:

1. Assume responsibility for the assigned inspection, sampling, or testing of materials as of the date stipulated by the Department in the formal notice to the Testing Agency to proceed with the work. This includes any partially completed work performed by the Department's former Testing Agency under the "Task Order Fabrication/Materials Inspection Services" contract that concluded February 14, 2016.

2. Make no decisions and offer no advice or opinion to a proposed action by the manufacturer/fabricator/producer/contractor without first consulting with the Engineer.
3. Provide all equipment required for the safe and comprehensive execution of the work including personal safety equipment such as clothing, hard hats, safety glasses, shoes, and gloves. This will also include appropriate means of transportation for some job classifications. All such equipment is subject to the approval of the Engineer.
4. Adhere to the Travel Expense Guidelines dated April 19, 2016 for the purpose of determining travel expenses and work locations.

The QA Inspector shall:

1. Be certified in the applicable field and have a thorough knowledge of the State of Connecticut - Department of Transportation - Standard Specifications for Roads, Bridges and Incidental Construction (Form 816 as supplemented), and project specifications, including approved shop drawings.

Specific information on scope of work, personnel, and reporting requirements for each area are provided in the following pages.

Precast, Prestressed and Post-Tensioned Concrete Inspection

Due to their critical function as load-bearing units of bridges and structures, precast, prestressed, and post-tensioned concrete members must be constructed in strict conformance with the specifications. To assure this conformance, the DMT assigns a QA Inspector to the manufacturing/fabrication plant to inspect, in detail, all phases of manufacture/fabrication. The primary function of the QA Inspector is to assure the Engineer that the fabricator is exercising adequate quality control during the entire fabrication process. Should the QA Inspector discover deficiencies or witness a lack of quality control, it is imperative that the Engineer be notified immediately so that corrective action can be initiated.

The QA Inspector shall perform the following:

Sampling

The following component materials shall be sampled for testing in accordance with standard Department procedures and frequencies listed below:

1. Portland cement: Shall be from a qualified source. Each load shall be accepted by certification. Samples shall be taken as directed by the Engineer.

2. Aggregate: Samples from bins or stockpiles each month for each source of supply, or as directed by the Engineer.
3. Admixtures: Only qualified admixtures are to be used. Samples are to be taken as directed by the Engineer.
4. Prestressing steel strand: Sample each reel or coil in accordance with Standard Specifications, Article M.14.01-2.
5. Post-tensioning tendons and anchorages: Sample as per Special Provisions.
6. Reinforcing steel: From each source, a 5-foot (1.5 m) sample of each size for every 200 tons (181.4 metric tons), with a minimum of one sample of each size from each source per project.

Inspection of Plant Facilities and Manufacturing Procedures

The plant facilities shall be inspected annually or as directed by the Engineer. A form provided by the Department shall be utilized as a guide to plant facilities inspection. As a minimum, the following shall be inspected:

1. Storage and handling of materials.
2. Batching, mixing, transportation and placement of concrete.
3. Curing method and apparatus (i.e., steam, radiant heat or other approved method) including provision for recording time and temperature data during the curing cycle.
4. Concrete testing equipment (i.e., compression-testing machine - should be calibrated every 12 months, pressure-type air meters, cylinder molds, slump cones, and unit weight apparatus) and facilities for moist-curing test cylinders in accordance with ASTM C 192.
5. Equipment and procedure for consolidation of concrete.
6. Construction and capacity of casting beds.
7. Dimensions, condition, and construction of forms.
8. Method and equipment for applying prestressing or post-tensioning forces.
9. Method and equipment for measuring prestressing or post-tensioning forces and the procedure for measuring elongation of strands or tendons.
10. Accuracy and calibration data of pressure gauges. (Gauges shall be calibrated at intervals not to exceed 6 months)

Inspection of Casting Bed

1. Check cleanliness, level, and alignment of form liner.
2. Check position of bulkheads for proper length of units and skewed or sloped ends, when applicable.
3. Inspect stringing of prestressing strands to ensure correct number and position of strands and location of "hold-downs."
4. For a sample of strands: inspect tension, measure elongation, and check gauge reading for proper force application. Force measurement of elongation and gauge reading shall check each other and the theoretical value shall be within 5 percent.
5. Witness retensioning at the non-jacking end of deflected strands and straight strands to verify application of the required prestressing force in accordance with the Standard Specifications, Article 5.14.03.
6. Inspect installation of a sample of post-tensioning tendons and anchorages, when applicable.
7. Check size, type, and location of a sample of reinforcing steel, hardware, and miscellaneous steel when placed in forms.
8. Inspect condition and alignment of a sample of side forms.
9. Check proper bracing and anchorage of casting bed and end anchorages.

Inspection of Concrete Operations

1. Inspect a sample of concrete delivered to forms for homogeneity and uniformity of successive batches.
2. Spot-check batching and mixing of concrete to assure that approved mix design and procedures are being used.
3. Witness/monitor sampling of concrete for quality control testing.
4. Witness slump, air tests, concrete temperature, and unit weight for conformance to specifications and accept or deem unacceptable on the basis of results.
5. Inspect placement, consolidation and finishing of concrete for conformance to specifications and accepted concrete practices.
6. For deck units, inspect internal void forms for material, size, and proper installation.

7. Check identification marker for required data and placement in unit.
8. Ensure that approved curing method is used and applied at proper time. If steam or radiant heat is used, ensure that required preset period is observed.

Inspection of Fabricated Units

1. Inspect a sample of units to determine if they were cured uniformly. Review the time/temperature record of curing cycle for specification compliance.
2. Witness testing of cylinders for required concrete strength prior to detensioning or removal of forms.
3. Verify dimensions, details, surface finish, and freedom from defects of a sample of finished units.
4. Verify proper marking and identification of units.
5. Witness application of protective compound to surfaces of precast catch basin and drop inlet tops, which will be exposed when in service.
6. Catch basin, drop inlets, manhole riser sections, bases, and appurtenances that exhibit the following shall be recommended for rejection:
 - 6.1 Fractures or cracks passing through the wall, except for a single end crack that does not exceed the depth of the joint.
 - 6.2 Defects that indicate imperfect proportioning, mixing, or molding.
 - 6.3 Surface defects indicating honeycombed or open texture.
 - 6.4 Any continuous crack having a surface width of 0.01 in. (0.3mm) or more and extending for a length of 1.0 ft. (300mm) or more, regardless of position in the section wall.
 - 6.5 Damaged or cracked ends where such damage would prevent making a satisfactory joint.

Reporting – As directed by the Engineer, the QA Inspector will document test results on forms provided by the Department.

HMA PLANT INSPECTION

The duties listed here are minimum requirements to be performed by HMA Inspectors. The daily responsibilities of an HMA Inspector shall be for elements and frequency, as specified in the contract, and will typically include, but are not limited to, the following items.

AASHTO Test Witnessed (at a Minimum)

- T 168 – Sampling Bituminous Mixtures
 - R 47 – Sample Reduction
 - T 312 – Preparation of Gyratory Sample
 - T 308 – Asphalt Content – Ignition Sample
 - T 209 – Theoretical Maximum Gravity (GMM)
 - T 30 – Sieve Analysis
 - T 166 – Bulk Specific Gravity (GMB)
 - T 255 – Moisture Content
1. Confirm assignment, correct specification year, and mix status (A/PT) with plant technician.
 2. Review test data charts, past technician notes, and copies of past testing reports.
 3. Inspect aggregates for consistency, quality, and cleanliness, and verify it was obtained from an approved source of supply.
 4. Visually inspect stockpiles and cold-feed bins for segregation and/or contamination.
 5. Verify that the latest JMF and HMA laboratory correction factors are available and accurate.
 6. Verify the appropriate PG binder grade is being used for the day's production.
 7. Inspect haul units for proper canvas covers and approved truck body release agents (no fuel oil).
 8. Check the temperature of the mix.
 9. Inspect the process of the batch/drum plant operations.
 10. Check truck tickets for mix proportion, class, RAP content, moisture, and target weights.
 11. Verify and note the status of the HMA plant. It should be running only on full automatic (not auto-manual or manual).

12. Retrieve all QC documentation.
13. Obtain random verification sample(s).
14. Obtain a liquid bituminous sample.
15. Obtain an Independent Assurance split sample.

Sampling Materials on Project Sites or Sources

The technician shall perform the following at the direction of a Department employee:

Sampling – Sample materials at a project site or source and transport such material all in accordance with applicable standards. The technician shall transport the sample to a location designated by the Department. The technician must be aware of the hazards of the project site or material sources and perform sampling in a safe manner.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department. For example, HMA Inspectors shall report results on Forms MAT 412, MAT 413, and Daily Inspector Report/Form MAT 431. Pavement density and subbase density testing are reported on Forms CON 133 and CON 125.

Testing In-Place Materials on Project Sites

The technician shall perform the following at the direction of a Department employee:

Sampling – Test in-place material in accordance with applicable standards. The technician must be capable of following directions to various project and supplier sites throughout the state to independently test materials. The technician must be qualified to use the testing equipment safely and effectively. The technician must be aware of the hazards of the project site and perform testing in a safe manner.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department within 24 hours. For example, HMA Inspectors shall report results on Forms MAT 412, MAT 413, and Daily Inspector Report/Form MAT 431. Pavement density and subbase density testing are reported on Forms CON 133 and CON 125.

Testing Material Samples at Department Material Testing Facilities

The technician shall perform the following at the direction of a Department employee:

Sampling – In accordance with applicable standards, assist or independently test material samples including, but not limited to, concrete cylinders, steel reinforcing bars, chains, fasteners, sand, and Portland cement in a laboratory setting. The technician shall also document the test results, input the test results into the Department’s reporting system, and file the documentation as needed. Assist in the cleaning and maintenance of testing equipment and surrounding areas.

Reporting – As directed by a Department representative, the inspector will document test results on forms provided by the Department.

Inputting Test Results, Processing Request for Test (MAT-100) Forms, & Filing Documentation

The technician shall perform the following at the direction of a Department employee:

Request for Test (Form MAT-100) Processing – Through the Department’s computerized construction management system (Site Manager), record test results and status of MAT-100 forms. File hardcopy versions of the MAT-100 forms in the Department’s files.

Legend	
Material Code:	Coding used in SiteManager
Unit (Eng):	English unit of material that defines a quantity
Material - Full Name:	The full detail description of a material
Status:	Type of Acceptance required A: A request for test (Mat100) B: An alternative method for Acceptance (see Minimum Schedule for Acceptance Testing)
Section:	Section responsibility within the Division of Materials Testing for material
	1: District 1 Rocky Hill 2: District 2 Colchester 3: District 3 New Haven 4: District 4 Thomaston 5: Chemical 6: Hot Mix Asphalt 7: Asphalt Binder 9: Physical Testing 10: Precast Concrete 11: Certifications 15: Structural Steel 17: Road Salts

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
00000	NO REQUEST FOR TEST REQUIRED	NONE	B	11
00031	Paint - Prime Coat for Struct. Steel	gal	B	15
00032	Paint - Interm. Coat for Struct. Steel	gal	B	15
00033	Paint - Top Coat For Struct. Steel	gal	B	15
00039	Paint - For Field Touchup	gal	B	15
00054	Paint - Waterborne Pvmt Mark (15 Min)	gal	B	5
00060	Paint - Waterborne Pvmt. Mark (3 Min)	gal	B	5
00091	Paint - Epoxy Pavement Markings	gal	B	5
00097	Sand Blast Debris (Toxicity Test)	TEST	B	5
00206	Preformed Black Marking Tape	l.f.	B	5
00297	Calcium Chloride - Liquid	gal	B	17
00298	Sodium Chloride, Inertial Barriers	lb.	B	5
00302	Calcium Chloride	ton	B	5
00303	Sodium Chloride	ton	A	17
00306	Glass Spheres	lb.	B	5
00310	Pavement Marking, Plastic, Preformed.	l.f.	B	5
00327	Water	gal	B	5
00327P	Water - Plantings	gal	B	5
00328	Protective Coating	s.f.	B	11
00496	Fertilizer	lb.	B	5
00497	Seed	lb.	B	5
00510	Peat	c.y.	B	5
00518	Sod	s.y.	B	5
00533	Lime	lb.	B	5
00534	Mulch - All Types	lb.	B	5
00536	Plant Materials	ea.	B	5
00542	Topsoil (from project)	c.y.	B	5
00542X	Topsoil (OFFSITE)	c.y.	A	5
00542P	Topsoil - Plantings	c.y.	B	5
00699	Pipe - R.C. & Fittings & Acc.	l.f.	A	10

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
00800	Box Culvert, Precast Concrete, 3 sided	l.f.	A	10
00804	Box Culvert, Precast Concrete	l.f.	A	10
00823	Culvert End - Reinforced Concrete	ea.	A	10
00865	Concrete Barrier, Precast, Temporary	l.f.	B	10
00895	Concrete Barrier, Precast	l.f.	A	10
01422	Concrete Section, Precast	ea.	A	10
01432	Foundation (precast)	ea.	A	10
01435	Anchor, Precast	ea.	A	10
01440A	Catch Basin - Precast (Complete)	ea.	A	10
01441A	Manhole - Precast (Complete)	ea.	A	10
01444	Catch Basin Riser, Precast	ea.	A	10
01458	Catch Basin Sump, Precast	ea.	A	10
01462	Handhole & Cover, Precast	ea.	A	10
01467	Slab, Precast	ea.	A	10
01491	Manhole - Riser (precast)	ea.	A	10
01499	Manhole - Base (precast)	ea.	A	10
01511	Curb, Precast	l.f.	A	10
01649	Catch Basin Top, Frame & Grate	ea.	A	10
01708	Pipe - For Underdrain or Outlet	l.f.	A	11
01783	Pipe - Aluminum & Fittings & Acc.	l.f.	B	11
01807	Culvert End - Aluminum	ea.	B	11
01839	Bolt / Nut / Washer	ea.	A	9
01940	Pipe - CCM & Fittings & Acc.	l.f.	A	1
01977	Pipe - ACCM & Fittings & Acc.	l.f.	A	1
02018	Culvert End - Coated Metal	ea.	A	1
02110	Pipe - Cast Iron & Fittings & Acc.	l.f.	A	15
02449	Pipe - Copper & Fittings & Acc.	l.f.	B	11
02501	Pipe - Ductile Iron & Fittings & Acc.	l.f.	A	15
02600	Pipe - Polyethylene & Fittings & Acc.	l.f.	B	11
02649	Pipe - PVC & Fittings & Acc.	l.f.	B	11
02673	Culvert End - Polyethylene	ea.	B	11
02724	Pipe - Steel & Fittings & Acc.	l.f.	A	15
02731	Pipe - Fiberglass & Fittings & Acc.	l.f.	B	11
02995	Dowel Splice System, Epoxy Coated	ea.	A	9
02996	Dowel Splice System, Galvanized	ea.	A	9
02997	Dowel Splice System	ea.	A	9
02998	Deformed Steel Bars, Epoxy Coated	lb.	A	9
03014-A-3.3K	Concrete-Class A (3300psi/22.8MPa)	c.y.	A	9
03014-C-3.3K	Concrete-Class C (3300psi/22.8MPa)	c.y.	A	9
03014-F-4.4K	Concrete-Class F (4400psi/30.4MPa)	c.y.	A	9
03014-SP2500	Concrete-Spec. Prov. (2500psi/18MPa)	c.y.	A	9
03014-SP3.3K	Concrete-Spec. Prov. (3300psi/23MPa)	CY	A	9
03014-SP3K	Concrete-Spec. Prov. (3000psi/21MPa)	c.y.	A	9
03014-SP4.4K	Concrete-Spec. Prov. (4400psi/30MPa)	CY	A	9
03014-SP4500	Concrete-Spec. Prov. (4500psi/31MPa)	c.y.	A	9
03014-SP4K	Concrete-Spec. Prov. (4000psi/28MPa)	c.y.	A	9

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
03014-SP5.7K	Concrete-Spec. Prov. (5656psi/39MPa)	c.y.	A	9
03014-SP5K	Concrete-Spec. Prov. (5000psi/35MPa)	c.y.	A	9
03014-SP6.5K	Concrete-Spec. Prov. (6527psi/45MPa)	CY	A	9
03014-SP6K	Concrete-Spec. Prov. (6000psi/41MPa)	c.y.	A	9
03014-SP8K	Concrete-Spec. Prov. (8000psi/55MPa)	c.y.	A	9
03014-SP-CLSM	Concrete-Controlled Low Strngth Material	c.y.	A	9
03015-02230	PCC 2200 psi, No. 3, Exp. 0	c.y.	A	9
03015-03081	PCC 3000 psi, No. 8, Exp. 1	c.y.	A	9
03015-03340	PCC 3300 psi, No. 4, Exp. 0	c.y.	A	9
03015-03360	PCC 3300 psi, No. 6, Exp. 0	c.y.	A	9
03015-03540	PCC 3500 psi, No. 4, Exp. 0	c.y.	A	9
03015-04081	PCC 4000 psi, No. 8, Exp. 1	c.y.	A	9
03015-04460	PCC 4400 psi, No. 6, Exp. 0	c.y.	A	9
03015-04462	PCC 4400 psi, No. 6, Exp. 2	c.y.	A	9
03015-04481	PCC 4400 psi, No. 8, Exp. 1	c.y.	A	9
03015-05081	PCC 5000 psi, No. 8, Exp. 1	c.y.	A	9
03015-05560	PCC 5500 psi, No. 6, Exp. 0	c.y.	A	9
03015-05562	PCC 5500 psi, No. 6, Exp. 2	c.y.	A	9
03016	Grout - Non Shrink (Batched)	c.y.	A	10
03025	Mortar (prebagged)	bag	B	10
03040	Grout, Non-Shrink	bag	B	10
03050	Concrete Members, Prestressed	l.f.	A	10
03051	Concrete Piles - Prestressed	l.f.	A	10
03062	Cement - Portland Type III	bag	B	9
03066	Cement - Portland Type I/II	bag	B	10
03092	Bituminous Concrete Joint / Crack Sealer	gal	A	7
03093	Bituminous Concrete Joint / Crack Filler	lb.	A	7
03094	Joint Sealer (Hot-Applied Rubberized)	l.f.	A	7
03100	Deformed Steel, Reinforcing	lb.	A	9
03100-G	Deformed, Steel, Reinforcing Bars, Galva	lb.	A	9
03100-SS	Stainless Steel Rebar	lb.	A	9
03102-FRP	Reinforcing Bars - Fiber Reinf - Polymer	lb.	A	9
03105	Chemical Anchor	ea.	B	11
03138	Dowels, Steel	ea.	A	9
03145	Fabric, Wire & Welded Steel	s.y.	A	9
03155	Expansion Joint Filler	l.f.	B	5
03158	Preformed Expansion Joint Filler	s.f.	B	5
03166	Sheeting, Polyethylene	s.y.	B	11
03200	Concrete Masonry Unit (CMU)	ea.	B	9
03201	Brick (Clay) - RED	ea.	B	9
03205	Catch Basin - Grates	ea.	A	15
03209	Manhole Covers / Frames	ea.	A	15
03211	Handhole Covers / Frames	ea.	A	15
03243	Supper Grates and Frames	ea.	A	15
03251	Catch Basin - Adjustment Ring	ea.	A	15
03252	Manhole - Adjustment Ring	ea.	A	15

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
03307	Fence, Chain Link, Gate	ea.	A	9
03309	Fence, Chain Link	l.f.	A	9
03310	Fence, Chain Link, Post for	ea.	A	9
03320	Fence, Hardware & Access. (Chain Link)	ea.	A	9
03326	Fence - Wire, Posts & Hardware	l.f.	A	9
03327	Fence, Protective	l.f.	A	15
03405	Metal Beam Rail, Anchorages for	ea.	A	15
03406	Metal Beam Rail System	l.f.	A	15
03413	Box Beam Guide Railing	l.f.	A	15
03414	Metal Handrail	l.f.	A	15
03419	Cable Guide Rail	l.f.	A	9
03421	Cable Guide Railing, Anchorages for	ea.	A	9
03429	Metal Bridge Rail System	l.f.	A	15
03430	Metal Bridge Rail Components	l.f.	A	15
03432	Joint Seal, Elastomeric Compression	l.f.	B	11
03444	Closed Cell Elastomer	c.i.	B	11
03449	Timber Guide Rail	l.f.	A	15
03450	Timber Guide Rail - Anchorages	ea.	A	10
03504	Anchor Bolts	ea.	A	9
03505-L	Bearing Pads (Elastomeric Laminated)	ea.	A	9
03505-P	Bearing Pads (Elastomeric Plain)	ea.	A	9
03532	Pile, Steel Shell	l.f.	A	9
03535	Piling, Steel Sheet	l.f.	A	9
03537	Steel, Structural	cwt.	A	15
03539	Piles, Timber	l.f.	B	11
03540	Bearings, Pot or Spherical	ea.	A	15
03542	Stud Shear Connector	ea.	A	9
03543	Studs - Welded	ea.	A	9
03546	Gabions	ea.	A	11
03549	H-Piles, Steel	lb.	A	9
03559	Pile Point, Steel	ea.	A	15
03566	Steel Plates	ea.	A	15
03603	Warning Lights	ea.	B	11
03693	Conduit & Fittings (all types)	l.f.	B	11
03704	Light Standard	ea.	A	15
03709	Ground Wire	l.f.	B	15
03711	Ground Rod	ea.	B	11
03723	Rigid Metal Conduit	l.f.	B	11
03724	Junction Box & Cover	ea.	A	15
03764	Sign (Variable Message)	ea.	B	11
03766	Traffic Signal Equipment	ea.	B	11
03801	Pedestals, Aluminum or Steel	ea.	B	11
03802	Span Pole - Steel	ea.	A	15
03806	Mast Arm Assembly	ea.	A	15
03807	Traffic Signal	ea.	B	11
03927	Traffic Drum	ea.	B	11

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
03928	Sign Support (Overhead), Structural Steel	ea.	A	15
03933	Delineator	ea.	B	11
03934	Reflective Sheeting	s.f.	B	11
03938	Sign Face - Sheet Aluminum	s.f.	B	11
03943	Object Marker	ea.	B	11
03945	Construction Signing	s.f.	B	11
03948	Traffic Cones	ea.	B	11
03952	Sign Post	ea.	A	9
03956	Traffic Drums	ea.	B	11
03970	Impact Attenuator	ea.	B	11
03974	Construction Barricade	ea.	B	11
03985	Geotextile	s.y.	B	11
04003	Bituminous Concrete - Curb Mix	ton	A	6
04029	Ultra-Thin Bonded HMA Pavement (Type B)	ton	A	6
04050	Asphalt Binder 64-22	gal	A	7
04052	HMA- Level 1 (9.5 mm / 0.375 in)	ton	A	6
04053	HMA, Level 2 (9.5 mm / 0.375 in)	ton	A	6
04054	HMA, Level 3 (9.5 mm / 0.375 in)	ton	A	6
04056	HMA, Level 1 (12.5 mm / 0.5 in)	ton	A	6
04057	HMA, Level 2 (12.5 mm / 0.5 in)	ton	A	6
04058	HMA, Level 3 (12.5 mm / 0.5 in)	ton	A	6
04064	HMA, Level 1 (25.0 mm / 1.0 in)	ton	A	6
04065	HMA, Level 2 (25.0 mm / 1.0 in)	ton	A	6
04066	HMA, Level 3 (25.0 mm / 1.0 in)	ton	A	6
04076	HMA, Level 1 (6.25 mm / 0.25 in)	ton	A	6
04077	HMA, Level 2 (6.25 mm / 0.25 in)	ton	A	6
04078	HMA, Level 3 (6.25 mm / 0.25 in)	ton	A	6
04092	PMA, Level 1 (6.25 mm / 0.25 in)	ton	A	6
04093	PMA, Level 2 (6.25 mm / 0.25 in)	ton	A	6
04094	PMA, Level 3 (6.25 mm / 0.25 in)	ton	A	6
04095	PMA, Level 1 (9.5 mm / 0.375 in)	ton	A	6
04096	PMA, Level 2 (9.5 mm / 0.375 in)	ton	A	6
04097	PMA, Level 3 (9.5 mm / 0.375 in)	ton	A	6
04098	PMA, Level 1 (12.5 mm / 0.5 in)	ton	A	6
04099	PMA, Level 2 (12.5 mm / 0.5 in)	ton	A	6
04100	PMA, Level 3 (12.5 mm / 0.5 in)	ton	A	6
04101	PMA, Level 1 (25.0 mm / 1.0 in)	ton	A	6
04102	PMA, Level 2 (25.0 mm / 1.0 in)	ton	A	6
04103	PMA, Level 3 (25.0 mm / 1.0 in)	ton	A	6
04108-SP	HMA- POROUS PAVEMENT	ton	A	6
04128	RS-1	gal	A	7
04133	SS-1- Slow Setting Asphalt Emulsion	gal	A	7
04134	SS-1H - Slow Setting Asphalt Emulsion -	GAL	A	7
04138	CRS-1 (Cationic Rapid Setting Asphalt)	gal	A	7
04139	CRS-2 (Cationic Rapid Setting)	gal	A	7
04142	Cationic Emulsion (CMS-2)	gal	A	7

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
04145	CSS-1H - Slow Setting Asphalt Emulsion	gal	A	7
04146	CSS-1- Cationic Emulsion	gal	A	7
04147	RS-1H	gal	A	7
04148	CRS-1P - Polymer Modified	GAL	A	7
04177	Joint Sealer, Concrete Structure	lb.	B	5
04199	Membrane Waterproofing	s.y.	B	7
04207	Dampproofing, Primer for	gal	B	7
04208	Dampproofing, Sealer for	gal	B	7
04697	Sand (Masonry) - Grading A	c.y.	A	1
04700	Sand	c.y.	A	1
04704	Sand (Masonry) - Grading B	c.y.	A	1
04749	Aggregate (Lightweight)	c.y.	A	1
04771	Stone, Masonry	ton	B	1
04776	Hay, Baled	ea.	B	11
04817	Stone Dust/Screenings	ton	A	1
04819	Gravel (Bank Run)	c.y.	A	1
04901	Bedding Material	c.y.	B	1
04902	Borrow	c.y.	A	1
04909	Curbing, Granite Stone	l.f.	B	1
04910	Curbing, Granite Slope	l.f.	B	1
04959	Railroad Ballast Mat	s.f.	A	15
06566	Lawn Drain	ea.	A	15
06659	Expansion Joint Sealer	l.f.	B	5
06923	Stay In Place Forms	l.f.	A	15
07067	Expansion Joint System	l.f.	B	5
07351	Bollard, Steel	ea.	A	15
07392	Bolt / Nut / Washer, Stainless Steel	ea.	A	9
07403	Rod, Threaded	ea.	A	15
07547	Tree	ea.	B	5
07627	Reinforced Earth Wall	ea.	B	10
07645	Luminaire	ea.	B	11
07799	Impact Attenuator Parts/Devices	ea.	B	11
07822	Noise Barrier Wall	s.f.	B	11
08010 - SP	Exp. Jt.- Asphaltic Plug - SPECIAL PROV.	c.f.	B	5
08022	Bolt / Nut / Washer, High Strength	ea.	A	9
08032	Sand (Washed)	c.y.	A	1
08033	Sand (Natural)	c.y.	A	1
08034	Stone (Broken/Crushed)	c.y.	A	1
08035	Gravel (Crushed)	c.y.	A	1
08036	Reclaimed Misc. Aggregate (ON-SITE)	c.y.	A	1
08036X	Reclaimed Misc. Aggregate (OFFSITE)	c.y.	A	1
08037	Reclaimed Waste	c.y.	A	1
08037X	Reclaimed Waste (OFFSITE)	c.y.	A	1
08039	Embankment Material	c.y.	A	1
08042	Pull Box - Precast Concrete	ea.	A	10
08044	Retaining Wall - Precast Concrete	ea.	A	10

MATERIAL CODES	MATERIAL - FULL NAME	UNIT (ENG)	STATUS	SECTION
08060	Detectable Warning Strip - (ADA)	s.f.	B	11
08069	Prefabricated Bridge Units	EACH	A	10

CONNECTICUT DEPARTMENT OF TRANSPORTATION
BUREAU OF ENGINEERING AND CONSTRUCTION
DIVISION OF MATERIALS TESTING

CRITERIA FOR ACCEPTANCE OF PORTLAND CEMENT BY CERTIFICATION

Before a cement producer is qualified to provide cement for use on Connecticut Department of Transportation (Department) projects, an authorized representative of the cement producer must agree to and comply with the following:

A. QUALIFICATION

1. The cement producer shall demonstrate that the production of cement at each mill providing material to the Department is regulated by an effective program of quality control. The cement producer shall submit a quality control plan to the Division of Materials Testing (DMT) that includes a detailed account of the quality control methods employed, the sampling and testing frequency, and testing procedures for review. Furthermore, the cement producer shall provide upon request, any documentation produced during any quality control related sampling and testing.
2. The testing laboratory of the cement producer shall be certified by the Cement and Concrete Reference Laboratory. Copies of the two (2) latest inspection reports shall be submitted to the DMT for review. The laboratory must be CCRL certified during any period that the mill provides material to the Department.
3. The cement producer shall certify the quality of the cement supplied as conforming to the requirements of the applicable specifications.

B. OPERATIONAL PROCEDURE

1. One (1) certified summary laboratory test report for all cement being produced shall be furnished on a monthly basis by the cement producer to the Division of Materials Testing, 280 West Street, Rocky Hill, Connecticut 06067.
2. Each bulk shipment to a ready mix producer, precast fabricator, or distributor shall be accompanied by a Bill of Lading that includes the following information:
 - a. Cement Producer's Name
 - b. Mill Location
 - c. Cement Carrier Number
 - d. Date Loaded
 - e. Weight of Material Contained in Carrier

Appendix E

- f. Silo, Bin or Lot Number of Cement, Terminals
- g. Consignee
- h. Destination
- i. Cement Type

Original BOL's must be provided to the purchaser for retention and review by the Department.

3. Random samples of the cement supplied may be selected and tested by the Department. Results of tests on these samples may be compared with the certified test values provided by the cement producer.
4. Results from bulk cement testing may also apply to bagged material from the same source.

Failure of the cement producer to comply with the requirements of the operational procedure may be considered grounds for suspending the qualification of the cement producer to provide cement on the basis of certification.

The procedure outlined above is intended to establish general guidelines for the acceptance of cement on the basis of producer qualification. However, the ConnDOT reserves the right to modify the above requirements if the best interest of the Department is served.

Appendix F – Connecticut Reference File (CRF) Specifications*

* used for Bureau of Highway Operations purchasing contracts ONLY.
The following CRF's are active.

File #	Title/Description
25	Black Enamel Paint
104	Burnt Orange Enamel Paint For Trucks
139	Sodium Chloride (Rock salt)
161	Non-reflective Plastic Sheeting
163	Processed Aggregate
191	Grits
194	Premixed Sodium Chloride (Salt) And Calcium Chloride
199	Epoxy Resin Pavement Markings, Symbols and Legends
200	White and Yellow Fast-Drying Waterborne Pavement Marking Paint
207	White and Yellow Regular-Drying Waterborne Pavement Marking Paint
2007-03	Liquid Calcium Chloride Anti-icing Agent

BLACK ENAMEL PAINT

REFERENCE FILE NO. 25—G

Issued March 10, 1953

Revised November 2, 1981

GENERAL — This material shall be shipped in regulation 1—gallon metal pails. Each container shall be marked with the following: name and type of paint, net weight, batch number, date of manufacture and State of Connecticut reference file and purchase order numbers, together with name and address of the manufacturer. When so requested, samples and analyses of all pigments, oils, resins, thinners and driers used for the enamel furnished shall be supplied by the manufacturer within ten days after request is made therefore.

A certified test report containing the physical and chemical properties of the material shall be submitted with each batch shipment.

The enamel shall consist of pigments and composition ground in the required vehicle by a suitable grinding machine to the required fineness. All pigments, oils, resins, thinners and driers used shall be of the best quality, free from adulterants of any kind and shall comply with the specific requirements given below. The enamel shall not contain any lead or lead by products.

The material desired under this specification is an extremely durable, highest quality black enamel for use on highway signs, and shall be resistant to air, sun and water.

COLOR — The color shall be jet black, conforming to Federal Standard No. 595, Color No. 17038.

ENAMEL COMPOSITION

	MIN.	MAX.
Carbon Black, %	3	4
Total solids, % by weight	42	-
Coarse particles retained on #325 screen based on paint, %	-	0.5
Weight per gallon, lb.	7.5	--
Viscosity, Krebs units at 77°F.	67	77
Fitness of grind (North Standard)	7	--

PIGMENT COMPOSITION — The pigment shall be carbon black only.

VEHICLE - The vehicle shall consist of a phthalic alkyd resin conforming to the requirements of Federal Specification TT—R-266, Type 3, of latest issue, with the following exceptions: Viscosity - Z maximum; Compatibility — delete raw linseed oil and mineral spirits dilution tests. The necessary quantities of suitable aliphatic, aromatic or terpene thinners and driers shall be added to yield a product conforming to all the requirements of this specification.

SPECULAR GLOSS - The enamel shall be flowed on a tin panel and allowed to dry for 24 hours before measuring. The specular gloss at 60° angle of incident, ASTM designation D523 of latest issue, shall be not less than 85.

SETTING AND DRYING TIME — This enamel shall air dry dust free within 2 hours, dry hard within 8 hours and reach full hardness within 48 hours.

DRY OPACITY — This enamel shall have a contrast ratio of at least 0.99 when spread at the rate of 630 sq. ft. per gallon (0.0025—inch wet film thickness).

WATER RESISTANCE — A film of enamel 0.002 inch thick shall be allowed to air dry for 96 hours, and then immersed in distilled water for 16 hours. It shall show no blistering or wrinkling immediately upon removal and no more than slight dulling or whitening after 2 hours recovery. After 24 hours, the gloss of the immersed portion shall be at least 90 percent of a comparison panel, which was not immersed.

FLEXIBILITY - A film of enamel 0.002 inch thick shall be allowed to dry for 18 hours, then baked for 72 hours at 105± 2°C, allowed to cool for 1/2 hour at 25°C (77°F), then bent over an 1/8—inch mandrel. There shall be no visible cracks when examined in a strong light at a 7—diameter magnification.

SKINNING — The enamel shall not skin within 48 hours in a three—quarter filled, closed container. Small amounts of anti—skinning agents, wetting agents, suspension agents and anti—drier agents may be added at the discretion of the manufacturer.

WORKING PROPERTIES — The enamel shall be well ground and shall show no more settling or caking than may be easily redispersed with a paddle to a homogeneous state. It shall be of good brushing consistency and shall dry to a smooth, glossy, uniform film, free from running, sagging or streaking.

BURNT ORANGE ENAMEL PAINT FOR TRUCKS (LEAD FREE)

REFERENCE FILE NO. 104-P

Issued May 17, 1945

Revised January 25, 1999

INTENDED USE – This specification covers a lead-free high-grade, synthetic-type high gloss enamel intended for use on trucks and other metallic motorized mechanical equipment. It is highly weather-resistant and is characterized by excellent color and gloss-retention, good drying, flexibility and freedom from aftertack. This enamel may be applied by brush or spray. It fails by mild chalking rather than by checking or cracking. The application of wax at periodic intervals will retard chalking and improve the appearance of the finish.

GENERAL – This material shall consist of pigments of the required fineness and composition, ground in the specified vehicle by a suitable grinding machine to the required fineness. All pigments, oils, resins, thinners and driers shall comply with the requirements below.

This enamel shall be shipped in regulation one-or five-gallon metal pails, as specified by the Purchasing Department. Each container shall be marked with the following: name and type of paint, net weight, batch number, date of manufacture and State of Connecticut Reference File and Purchase Order Numbers, together with the name and address of the manufacturer. When so requested, samples and, analyses of all pigments, oils, resins, thinners, and driers used shall be supplied by the manufacture within ten (10) days after request is made.

COLOR – Standard color chips may be viewed at the Connecticut Department of Transportation, Research and Materials Testing Laboratory, 280 West Street, Rocky Hill, Connecticut 06067. The color shall essentially match that of color Omaha Orange, DuPont #082.

VEHICLE - The vehicle for this air-drying enamel shall consist of a phthalic alkyd resin.

Necessary quantities of suitable aliphatic, aromatic or terpene thinners and driers, or mixture thereof, shall be added to yield a product conforming to all the requirements of this specification. Small amounts of antiskinning agents, wetting agents, suspension agents and antidrier absorption agents may be added at the discretion of the manufacturer.

QUANTITATIVE REQUIREMENTS	Min.	Max.
Pigment, % by weight	16	
Vehicle, % by weight	--	84
Volatile matter in vehicle, % by weight	--	55
Coarse particles and skins retained on #325 sieve, % by weight of pigment	--	0.5
Viscosity, Krebs units at 77°F.	75	85
Specular gloss (without correction for diffuse reflectance)	85	
Fineness of grind (North Standard)	6	
Dry opacity (540 sq. ft. per gallon)	0.52	
Weight per gallon, lbs.	8.0	
Drying time: Dust-free setting time, hours	--	1
Dry hard, hours	--	8
Full hardness, hours	--	48

BRUSHING PROPERTIES – As received, this enamel shall be ready-mixed for use. It shall be of good brushing consistency in the packaged condition. When tested as described below, laps

shall be picked up without pulling under the brush; and the enamel shall dry to a smooth, glossy, uniform film, free from running, sagging or streaking.

Brush the evenly mixed enamel on a thoroughly cleaned, rust-free, smooth, cold-rolled steel or aluminum panel (2 ft. square) with a 2-1/2 inch paint brush, applying the enamel uniformly at an approximately spreading rate of 500 square feet per gallon. Place the panel in a nearly vertical position, allow to air dry for 24 hours and examine for defects described above.

DRYING TIME – A wet film, 0.0015-inch thick, shall set to a dust-free condition within one hour, dry hard and tack-free within 8-hours and reach full hardness within 48 hours.

FILM FOR FLEXIBILITY, WATER-RESISTANCE AND GASOLINE-RESISTANCE – Tin panels, measuring 4 by 6 inches and weighing 19 to 25 grams per square centimeter, will be used for this test. They will be thoroughly cleaned with a suitable solvent and lightly buffed with steel wool immediately before using. Apply the film with a 0.002-inch (approximately 0.004-inch gap clearance). Bird Film Applicator or any other doctor blade which produces a film of the same thickness as that produced by the Bird blade.

FLEXIBILITY – Films prepared as above shall be allowed to air dry in a horizontal position for 18 hours, then baked for 168 hours at $105 \pm 2^{\circ}\text{C}$ ($221 \pm 4^{\circ}\text{F}$). After baking, condition the panel for one-half hour at $23 \pm 1^{\circ}\text{C}$ ($73.4 \pm 2^{\circ}\text{F}$) and relative humidity 50% - 4%. Bend over a 1/8 inch mandrel. Examine the coating for cracks over the area of the bend in a strong light at a 7-diameter magnification. The film of the enamel shall show no cracking.

APPEARANCE OF FILM AFTER BAKING – After drying and baking the panel for flexibility, the enamel film shall retain at least 75 percent of the original secular gloss value.

ADHESION – In testing for adhesion, use the flat portion of the panel from the flexibility test. Cut a narrow ribbon of the film from the panel by use of the sharp knife blade held at about 30 degrees from the panel. The film should cut loose in the form of a ribbon without flaking or cracking.

COLOR WATER RESISTANCE – After drying for 96 hours, place one of the test panels in a beaker containing approximately 2-1/2 inches of distilled water at room temperature (21 to 32°C), and allow to remain for 16 hours. Remove and allow to dry. The film shall show no blistering or wrinkling immediately upon removal from the water. There shall be no more than a slight dulling or whitening when examined 2 hours after removal of the panels and after 24 hours of air drying, the gloss of the immersed portion shall be at least 90 percent of the gloss of a comparison panel which was not immersed. The immersed and comparison panel shall be indistinguishable with regard to film hardness after the 24 hours of air drying.

GASOLINE RESISTANCE – After drying for 96 hours, place one of the panels in a beaker containing approximately 2-1/2 inches of gasoline conforming to Federal Specification VVG-1690, cover with a watch glass and allow to remain at room temperature (21 to 32°C), for 16 hours. Remove and allow to dry. The film shall show no blistering or wrinkling immediately upon removal of the panel, and any softening or whitening effect that may remain two hours after removal shall have completely disappeared after air drying for 24 hours. The immersed portion shall retain at least 50 percent of the gloss of a comparison panel which was not immersed.

DRY OPACITY – At a spreading rate of 540 square feet per gallon, this enamel shall have a minimum dry-film contrast ratio of not less than 0.98.

MISCIBILITY WITH MINERAL SPIRITS – Mix thoroughly one part of mineral spirits conforming to Grade I of Federal Specification AA-2904 with eight parts of enamel by slowly adding the mineral spirits to the enamel with constant stirring. The enamel shall be completely miscible with mineral

spirits. After standing 24 hours there shall be no curdling or precipitation of the vehicle. Any settling of the pigment shall be disregarded.

SKINNING – The enamel shall not skin within 48 hours in a three-quarters filled, closed container.

RESIN – Resin and resin derivatives shall be absent.

RECOATING – Recoating after 24 hours air drying shall produce no film irregularity.

ODOR – The odor of the wet enamel and of the dry film shall not be obnoxious.

TOXICITY – The enamel shall contain no benzol or chlorinated solvents.

PARTIALLY FILLED CONTAINER – After standing 30 days at a temperature between 21 and 32°C, a three-quarters filled, closed 8-ounce glass jar of the enamel shall show no livering, curdling, hard settlement or caking. Any skin formed shall be continuously and easily removed, and the enamel shall mix readily to a smooth, homogeneous state.

FULL CONTAINER - Upon being opened after six months of storage under warehouse storage conditions, a full, closed container shall show no livering or curding of the enamel and no more settling than can be redispersed with a paddle to a homogeneous state. There shall be no hard settlement or caking and no skinning. The viscosity shall not have increased more than an equivalent of 10 K.U. during the storage period. The enamel shall have retained its drying properties and shall dry to a full gloss finish, free from grit and seediness.

APPLICABLE FEDERAL SPECIFICATIONS AND STANDARDS –

A-A2504	Thinners; Paint, Volatile Mineral Spirits
VV-3-1690	Gasoline, Automotive
141	Paint, Varnish, Lacquer and Related Materials; Methods of Inspection, Sampling and Testing

SODIUM CHLORIDE (ROCK SALT)

REFERENCE FILE NO. 139R

Issued July 7, 1955

Revised June 1, 2002

Scope: This specification prescribes the composition, storage, inspection, acceptance and delivery of road salt obtained from (natural deposits/artificially produced) which is to be used for snow & ice control on highways and bridges.

Requirements: All road salt shall conform to AASHTO M 143 (ASTM D—632) Type 1, with the exceptions and additions stated herein. When material is not in conformance as stated herein, and the state formally agrees to accept such material, payment reduction shall apply and will be the sum of the individual reductions based on the bid price.

Inspection & Testing: At the vendor's location the stockpile shall be covered as required and the road salt shall be tested by Division of Materials Testing. The Bureau of Finance and Administration shall accept the material prior to any shipment to the State. Road salt from different origins (natural deposits/artificially produced) shall be stockpiled separately. If at any time, the purity of road salt is less than 95 percent sodium chloride, the vendor shall maintain this material in a physically separated stockpile. Once the stockpile has been accepted, material shall not be added to the stockpile without prior notification to and additional testing by the State. Failure to properly control these stockpiles may result in revocation of the award.

Material acceptance:

PURITY: The road salt requirements for material acceptance shall be as stated in AASHTO M—143 (ASTM D—632) Type 1, except sections 9.1.2 and 11.2 will not apply. It is intended that only products meeting the specified sodium chloride content (95.0 percent or greater) will be accepted; however, at the sole discretion of the Department of Transportation, road salt having a purity of less than 95.0 percent sodium chloride content may be accepted with an adjustment in payment in accordance with Table 1.

TABLE 1: Adjustment in Payment for Purity of Sodium Chloride

Percent of Sodium Chloride	Percent Payment of Unit Bid Price
95.0% to 100%	100
93.0% to 94.9%	95
91.0% to 92.9%	90
90.9% & below	73

Grading: The gradation requirements for material acceptance shall be as stated below. Failure to conform to these requirements may result in rejection of the stockpile. If non-conforming material is accepted, a reduction in payment of 2 percent per screen shall be assessed for deviations in the gradation.

Sieve Size	Percent Passing by Weight
12.5 mm (1/2in.)	100
9.5 mm (3/8in.)	95 to 100
4.75 mm (No.4)	20 to 90
2.36 mm (No.8)	10 to 60
600 µm (No.30)	0 to 15

Moisture: Full payment will apply to the road salt when its moisture content does not exceed two (2.0) percent. Road salt with a moisture content greater than (2.0) percent may be accepted at the discretion of the Department, with an adjustment in weight for moisture content over 2.0 percent.

Anticaking Agent: Road salt furnished under this contract shall be free flowing and granular. All bulk road salt shall be treated with an approved conditioner, such as sodium ferrocyanide, to prevent caking while in storage. This treatment shall be prior to shipping product from the origin (natural deposits/artificially produced). This conditioner shall be visible and introduced uniformly throughout the road salt at a maximum rate of 50 parts per million or 0.0050 percent.

NON-REFLECTIVE PLASTIC SHEETING

REFERENCE FILE NO. 161-D

Issued October 19, 1962

Revised June 10, 1983

Description: The material shall consist of a flexible, pigmented plastic film, completely pre-coated with a solvent or heat-activated tack-free adhesive. The adhesive shall be protected by a paper liner, which shall be removable without soaking in water or other solvents.

Property Requirements:

A. Thickness: The thickness of the plastic film with adhesive shall be a minimum of 0.003 inches and a maximum of 0.0045 inches.

B. Film: The unapplied and/or applied film shall be readily processed with, and ensure adequate adhesion of, process inks recommended by the manufacturer.

1. Flexibility: The material shall be sufficiently flexible to permit application over and conform to moderately contoured surfaces.

2. Gloss: The film shall have an initial 60-degree gloss value of 35 (minimum), when tested in accordance with ASTM Method D 523, measuring at least three portions of the film to obtain uniformity.

C. Adhesive: The pre-coated adhesive shall form a durable bond to smooth, clean, corrosion- and weather-resistant surfaces, shall be of uniform thickness, non-corrosive to applied surfaces and shall have no staining effect on the film.

Adhesion: The material, applied according to Paragraph I "Preparation of Test Panels" shall have sufficient bond to prevent removal from the panel in one piece without the aid of a physical tool.

D. Exterior Exposure: The material shall withstand three years' vertical, south-facing exterior exposure in Texas, showing no appreciable discoloration, cracking, crazing, blistering, delamination or loss of adhesion. A slight amount of caulking is permissible.

E. Dimensional Stability: The material shall show no more than 1/64" shrinkage in any direction from edge of the panel when prepared in accordance with Paragraph I after being subjected to a temperature of 150° F for 48 hours.

F. Heat Resistance: The material applied according to Paragraph I, shall be heat-resistant enough to retain adhesion after one week at 150° F.

G. Solvent and Chemical Resistance: The material, when prepared in accordance with Paragraph I, shall withstand immersion in the following liquids at 70°-90° F, showing no appreciable decrease in adhesion, color or general appearance.

Liquids

Hours

Time,

Reference Fuel (MIL-F-8799A) (15 parts xylol – 85 parts mineral spirits by weight)	1	
Distilled Water		24
SAE #20 Motor Oil		24

H. Opacity: when applied, the material shall be sufficiently opaque to hide a contrasting black printed legend and white surface.

I. Preparation of Test Panels: Test panel shall be prepared using a 6 ½" × 6 ½" piece of the plastic film, applied to a clean 6" × 6" aluminum panel, pre-masked or as recommended by the manufacturer, trimmed evenly at the edge of the panel, and aged for 48 hours at 70-90°F.

J. Shelf Life Storage: The material shall withstand one year's shelf life when stored in a clean area free from exposure to excessive heat, moisture, and direct sunlight.

K. General Characteristics and Packaging: The plastic film shall be furnished in rolls, cut sheets or characters as may be specified. The film, as supplied, shall be free from ragged edges, streaks, blisters, foreign matter, or other surface imperfections which would make it unsuitable for the intended usage, and shall be readily cut with scissors, knife, blade, shears, or other production tools. Complete and detailed instructions for mounting the plastic film shall be supplied with each package of material.

Rolls, sheets or letters shall be individually packaged in suitable containers and in such a manner that no damage or defacement may occur to the plastic film during transport to destination.

Quality Assurance: The vendor shall furnish a Certified Test Report conforming to the requirements stated herein below for all materials supplied under this specification.

1. A Certified Test Report is a document containing a list of the dimensional, chemical, and physical results obtained by an approved testing organization from an actual test of the material involved. It shall also certify that the materials meet the requirements of the specifications and shall include the following information:

- a. Description of material
- b. Connecticut Department of Transportation purchase order number.
- c. Date of manufacture.
- d. Date of testing.
- e. Name of organization to which the material is consigned.
- f. Quantity of material represented.
- g. Means of identifying consignment such as label, marking, lot number, etc.
- h. Date and method of shipment.
- i. Name of organization performing the tests.

EACH SHIPMENT SHALL BE ACCOMPANIED BY A CERTIFIED TEST REPORT. THIS REPORT SHALL STATE THAT MATERIAL FURNISHED WILL CONFORM TO THE SPECIFICATIONS IN EVERY DETAIL. The Certified Test Report shall be signed by an authorized and responsible agent for the organization supplying the material. The certificate MUST be notarized.

**PROCESSED AGGREGATE
REFERENCE FILE NO. 163-K**

Issued: March 4, 1963

Revised: January 28, 2015

Description: Generally used by the Office of Maintenance as a base material for incidental work such as bike paths or ancillary paved surfaces.

Processed Aggregate shall conform to the following:

All Processed Aggregate shall conform to ConnDOT Standard Specifications, Article M.05.01, except that reclaimed material is prohibited and Medium processed aggregate shall conform to the following gradation:

Medium Processed Aggregate	
Square Mesh Sieves	Percent Passing by Weight (Mass)
2 ½ in. (63 mm)	100
2 in. (50 mm)	100
1 ½ in. (37.5 mm.)	100
1 in. (25.4 mm)	90-100
¾ in. (19 mm)	75-100
¼ in. (6.3 mm)	30-60
#40 (425 um)	5-25
#100 (150 um)	3-12

GRITS

REFERENCE FILE NO. 191-E

Issued January 14, 1980

Revised June 29, 2001

REFERENCE FILE 191-E

CONNECTICUT DEPARTMENT OF TRANSPORTATION
BUREAU OF ENGINEERING AND HIGHWAY OPERATIONS
SPECIFICATION FOR GRITS

DESCRIPTION: Grits shall consist of sound, tough, durable particles of crushed or uncrushed screened stone or gravel, and shall be free from lumps of clay, soil, loam or organic matter.

MATERIAL REQUIREMENTS:

- 1) Soundness: When tested for soundness with a magnesium sulfate solution using AASHTO Method T 104, the plus No. 4 fraction shall show a loss of not more than 10 percent at the end of five cycles.
- 2) Loss on Abrasion: When tested by means of the Los Angeles Machine using AASHTO Method T 96, the plus No. 8 fraction shall show a loss on abrasion of not more than 40 percent.
- 3) Flat and Elongated: All plus No. 8 material shall not contain more than 15 percent of flat or elongated pieces, the longest dimensions of which exceed three times the maximum thickness.
- 4) Grading: The grit material shall conform to one of the gradations shown in Table 1 below. The grading will be specified on the Purchase Order.

Table 1. Percent Passing per Grading

Sieve Size	Grading "A"	Grading "B"
3/8	100	100
#4	40-90	85-100
#8	0-30	10-40
#16	---	0-10
#50	0-10	0-5
#100	0-3	---

**PREMIXED SODIUM CHLORIDE (Salt) AND CALCIUM CHLORIDE
REFERENCE FILE NUMBER 194-E
Issued March 12, 1976
Revised June 1, 1998**

SCOPE:

This specification covers a premixed blend of sodium chloride (rock salt) and calcium chloride to be used for ice control on highways and bridges.

DESCRIPTION:

Sodium Chloride: The sodium chloride shall conform to the requirements of Reference File 139, latest revision.

Calcium Chloride: The calcium chloride shall conform to the requirements of AASHTO M 144, Type I.

MIXTURE:

The premix for the CONTNDOT shall be a completely uniform and free-flowing mixture of three parts sodium chloride by weight to one part flake calcium chloride by weight.

SAMPLES FOR TEST:

Before a purchase order is issued, vendor(s) awarded the contract must forward, UNBLENDED, a thirty-pound bag of sodium chloride and a ten-pound bag of calcium chloride to be used for test to the Director of Research and Materials, 280 West St., Rocky Hill, CT 06067.

GENERAL:

The State reserves the right to inspect or sample material at the place of manufacture or stockpile, or to test materials before accepting delivery.

EPOXY RESIN PAVEMENT MARKINGS, SYMBOLS AND LEGENDS

REFERENCE FILE NO. 199-C

Issued: November 1, 1985

Revised: October 30, 1995

DESCRIPTION: This specification covers reflectorized white and yellow two component epoxy resin to be used for pavement marking on both asphaltic and Portland cement concrete pavement surfaces. It is to be used in conjunction with a surface application of glass beads and in accordance with these requirements. Upon curing, it produces an adherent reflectorized stripe of specified thickness and width capable of resisting wear from traffic.

CLASSIFICATION: This specification provides for the classification of epoxy resin pavement marking system by type.

Type I	A fast—cure material suitable for centerline, skipline and edgeline use under traffic conditions
Type II	A slow—cure material suitable for centerline, skipline and edgeline use under minimal traffic conditions; e.g., unopened roadways
Type III	A medium—cure material suitable for pavement marking message and transverse line work

MATERIALS -GENERAL REQUIREMENTS:

Standards - All standards herein are minimum standards.

Identification: Each container must bear a label with the following information thereon: Name and address of manufacturer, shipping point, grade production batch number, date of manufacture, shipping point, grade name and/or identification number, type of material, number of gallons, contract number, use intended, directions for application, and formula. Improperly labeled samples and deliveries will be rejected.

Qualification of Manufacturer: No material will be considered unless the firm submitting the material can meet the following conditions (these qualifications must be provided to approve a subcontractor for this work):

- a. that it has in operation a factory adequate for and devoted to manufacturer of the pavement marking material that it proposes to furnish;
- b. that it is capable of predicting batch sizes consistent with the quantities to be delivered;
- c. that it maintains a laboratory to scientifically control the product bid on to ensure accuracy and quality of formulation; and
- d. that it has produced pavement marking material over the past two (2) years with a successful application record.

Certification: The manufacturer shall furnish a certified test report by an independent testing laboratory prior to the start of work indicating that the material as specified has been tested in accordance with ASTM or ACI testing procedures noted in this specification. The certified test report shall indicate the results of testing for the following criteria:

Composition, Color, Adhesion Capabilities, Abrasion Resistance, Hardness, Tensile Strength, and Compressive Strength.

Additionally, infrared spectrophotometer plots for both components of the test material shall be included by the independent laboratory in the certified test report.

The manufacturer shall furnish certified test reports for each batch delivered for application at the project site. Certified test reports shall be in accordance with the State of Connecticut, Department of Transportation Standard Specifications for Roads, Bridges and Incidental Construction, Section 1.06.07 of the latest edition,

MATERIALS - DETAILED REQUIREMENTS:

Epoxy Resin Material: The material shall be composed of epoxy resins and pigments only. No solvents to be given off to the environment upon application to the pavement surface, nor fillers, will be allowed.

<u>Composition:</u>	WHITE (percent by weight) 20 ± 2 Titanium Dioxide (ASTM D 476 Type III) 80 ± 2 Epoxy Resins	YELLOW (percent by weight) 20 ± 2 Chrome Yellow (ASTM D211 Type III) 75 ± 2 Epoxy Resins
---------------------	---	--

Color: The color of the WHITE material shall be no darker or yellower than color chip 17778 of Federal Standard No. 595a of the latest issue, when the material is placed in a Type EH weatherometer for a period of 500 hours and weathered according to ASTM F 42. The color of the YELLOW shall be reasonably close to color chip 13538 of the Federal Standard No. 595a of the latest issue.

Adhesion Capabilities: When the adhesion of the material to Portland cement concrete (the concrete shall have a minimum of 300 psi tensile strength) is tested according to American Concrete Institute Committee 503R testing procedure, the failure of the system must take place in the concrete. The concrete shall be 32 °C when the material is applied, after which the material shall be allowed to cure for 72 hours at 23 ± 2 °C.

Abrasion Resistance: When the abrasion resistance of the material is tested according to ASTM C 501 with a CS-17 wheel under a load of 1000 grams for 1000 cycles, the wear index shall be no greater than 82. (The index is the weight in milligrams that is abraded from the sample under the test conditions)

Hardness: The Type D durometer hardness of the material shall be not less than 75 or more than 90 when tested according to ASTM D 2240 after the material has cured for 72 hours at 23 ± 2 °C.

Compressive Strength: The compressive strength of the material, when tested according to ASTM D 695, shall not be less than 12,000 psi after 72 hours cured at 23 ± 2 °C.

Shelf Life: The individual components shall not require mixing prior to use when stored for a period of 12 months.

Glass Beads: The moisture resistant glass beads shall meet the requirements of AASHTO M 246, except that glass spheres shall meet the gradation requirements as follows:

<u>Grading "A"</u>		<u>Grading "B"</u>	
<u>Sieve Size</u>	<u>Percent</u>	<u>Sieve Size</u>	<u>Percent</u>
% Passing #20	100	% Retained #10	0
% Passing #30	80—95	% Retained #12	0—5
% Passing #50	9—42	% Retained #14	5—20
% Passing #80	0—10	% Retained #16	40—80
		% Retained #18	10—40
		% Retained #20	0—5
		% Retained Pan	0—2

Glass beads conforming to the requirements of Grading "A" shall be applied at a rate of 25 pounds per gallon of epoxy pavement marking material.

If specified, glass beads conforming to the requirements of Grading "B" shall be applied at a rate of 12 pounds per gallon of epoxy pavement marking material, immediately followed by a scanned drop of glass beads conforming to the requirements of Grading "A" applied at a rate of 12 pounds per gallon of epoxy pavement marking material.

Traffic cones or any other acceptable method shall be used to protect the pavement marking until cured.

Time To No—Track: The Type I material shall be in "no—tracking" condition in 60 seconds or less.

The no-tracking condition shall be determined by actual application on the pavement of the pigmented binder at 20 mils wet, covered with glass spheres at a rate of 25 pounds per gallon. The lines for this test shall be applied with the specialized striping equipment operated so as to have the material at the manufacturer's recommended application temperature. This maximum no—tracking time shall not be exceeded when the pavement temperature varies from 50 °F to 120 °F, and under all humidity conditions, provided the pavement is surface dry.

The no-tracking time shall be determined by passing over the line with a passenger car or pickup truck in the simulated passing maneuver. A line showing no visual deposition of the material to the pavement surface when viewed from a distance of 50 feet shall be considered as showing "no— tracking" and conforming to this requirement for time to no-track.

WHITE AND YELLOW FAST-DRYING WATERBORNE PAVEMENT MARKING PAINT

REFERENCE FILE NUMBER 200-I

Revised: May 29, 2008

Scope: White and yellow fast-drying waterborne pavement marking paint to be applied to bituminous concrete and Portland cement concrete pavements. This paint shall be capable of being applied with paint striping equipment at an application temperature of 130° F to 145° F (54° C to 63° C).

General: Specifications and publications that apply are as follows:

FS: TT-P-1952 Paint, Traffic and Air Field Marking, Water Emulsion Base; Federal Test-Method Standard #141 Paint, Varnish, Lacquer and Related Materials, Methods of Inspection, Sampling and Testing; FS No. 595 Colors; and HH-R-59 Roofing Felt (Asbestos, Asphalt-saturated).

ASTM Standards: D 211-Specifications for Chrome Yellow and Chrome Orange; D 476-Specifications for Titanium Dioxide Pigments; D 562 Test for Consistency of Paints Using the Stormer Viscometer; D 869-Test for 45-deg, 0-deg Directional Reflectance Factor of Opaque Specimens by Broad Band Filter Reflectometry.

Detailed Requirements, Formulation and Manufacture: The paint shall be formulated and manufactured from first-grade raw materials and shall be free from defects and imperfections that might adversely affect the serviceability of the finished product. The materials shall not exhibit settling or jelling after storage in the sealed containers as received that will affect the performance of the products. The paint shall provide the proper anchorage, refraction and reflection for the finished glass spheres when applied as specified.

Composition: The composition of the paint shall be at the discretion of the manufacturer, provided that the finished product meets the requirements of any applicable Federal, State or Local regulations for products of this type and the requirements as follows:

1. Paint shall not contain more than 0.06% lead;

- 2 Total nonvolatile shall not be less than 76% by weight (mass);
3. Pigment shall be 58-63% by weight (mass);
4. Resin solids shall be composed of 100% acrylic emulsion polymer;
5. Volatile organic compounds shall not exceed 150 grams/liter, excluding water;
6. Closed-cup flash point shall not be less than 145° F (38° C);
7. Weight per gallon (mass per liter) shall not be less than 12.5 pounds/gallon (1.50 kilograms/liter) when tested in accordance with ASTM D 1475.
8. Drying time to no pick up shall be 3 minutes or less when tested in accordance with ASTM D 711

Scrub Resistance: The paint shall pass test for scrub resistance when tested in accordance with ASTM D2486, Method B.

Viscosity: The consistency of the paint shall not be less than 80, nor more than 90 Kneb units when tested in accordance with ASTM D562.

Flexibility: The paint shall not show cracking or flaking when subjected to the TT-P-1952 flexibility test in which the panels used shall be tin plates that are 3 inches x 5 inches (76 millimeters x 127 millimeters) in area and 35 - 31 U.S. Gauge in thickness. The tin panels shall be lightly buffed with steel wool and thoroughly cleaned with solvent before being used for tests.

Dry Opacity: Both white and yellow paints shall have a minimum contrast ratio of 0.96. Contrast ratio shall be determined by applying a wet film thickness of 0.005 inches (127 microns) to a standard hiding power chart. After drying, the black and white reflectance values shall be determined using a suitable reflectometer and the contrast ratio determined.

Bleeding: The paints shall have a minimum bleeding ratio of 0.97 when tested in accordance with FS TT-P-1952. The asphalt-saturated felt shall conform to FS HH-R-59.

Abrasion Resistance: No less than 210 liters of sand shall be required to remove paint film when tested in accordance with TT-P-1952.

Color: The paint shall not discolor in sunlight and shall maintain colorfastness throughout its life, approximately two years. Color determination shall be made without beads, after a minimum of 24 hours. Color for yellow paint shall be a visual match for 595-13538. If not a visual match, the diffuse day color of the paint shall conform to the CIE Chromaticity coordinate limits as follows:

	x y		x y		x y		x y		Brightness
White:	(x) 0.305	(y) 0.295	(x) 0.360	(y) 0.360	(x) 0.388	(y) 0.377	(x) 0.280	(y) 0.310	84.0
Yellow:	(x) 0.485	(y) 0.455	(x) 0.506	(y) 0.452	(x) 0.484	(y) 0.428	(x) 0.477	(y) 0.438	50.0

**WHITE AND YELLOW REGULAR-DRYING WATERBORNE PAVEMENT MARKING PAINT
REFERENCE FILE NUMBER 207- D**

Revised: May 29, 2008

Scope: White and yellow regular-drying waterborne pavement marking paint that is to be applied to bituminous concrete and Portland cement concrete pavements. This paint shall be capable of being applied with paint striping equipment that does not require heating above ambient temperatures.

General: Specifications and publications that apply are as follows:

FS: TT-P-1952 Paint, Traffic and Air Field Marking, Water Emulsion Base; Federal Test-Method Standard #141 Paint, Varnish, Lacquer and Related Materials, Methods of Inspection, Sampling and Testing; FS No. 595 Colors; and HH-R-59 Roofing Felt (Asbestos, Asphalt-saturated).

ASTM Standards: D 211-Specifications for Chrome Yellow and Chrome Orange; D 476-Specifications for Titanium Dioxide Pigments; D 562 Test for Consistency of Paints Using the Stormer Viscometer; D 869-Test for 45-deg, 0-deg Directional Reflectance Factor of Opaque Specimens by Broad Band Filter Reflectometry.

Detailed Requirements, Formulation and Manufacture: The paint shall be formulated and manufactured from first-grade raw materials and shall be free from defects and imperfections that might adversely affect the serviceability of the finished product. The materials shall not exhibit settling or jelling after storage in the sealed containers as received that will affect the performance of the products. The paint shall provide the proper anchorage, refraction and reflection for the finished glass spheres when applied as specified.

Composition: The composition of the paint shall be at the discretion of the manufacturer, provided that the finished product meets the requirements of any applicable Federal, State or Local regulations for products of this type and the requirements as follows:

1. Paint shall not contain more than 0.06% lead;
- 2 Total nonvolatile shall not be less than 70% by weight (mass);
3. Pigment shall be 50-60% by weight (mass);
4. Resin solids shall be composed of 100% acrylic emulsion polymer;
5. Volatile organic compounds shall not exceed 150 grams/liter, excluding water;
6. Closed-cup flash point shall not be less than 145° F (38° C), and weight per gallon (mass per liter) shall not be less than 12.5 pounds/gallon (1.50 kilograms/liter) when tested in accordance with ASTM D 1475.
7. Weight per gallon (Mass per liter) shall not be less than 12.5 pounds/gallon (1.50 kilograms/liter) when tested in accordance with ASTM D 1475;
8. Drying time to no pick up shall be 15 minutes or less when tested in accordance with ASTM D 711

Scrub Resistance: The paint shall pass test for scrub resistance when tested in accordance with ASTM D2486, Method B.

Viscosity: The consistency of the paint shall not be less than 75, nor more than 85 Kreb units when tested in accordance with ASTM D562.

Flexibility: The paint shall not show cracking or flaking when subjected to the TT-P-1952 flexibility test in which the panels used shall be tin plates that are 3 inches x 5 inches (76 millimeters x 127 millimeters) in area and 35 - 31 U.S. Gauge in thickness. The tin panels shall be lightly buffed with steel wool and thoroughly cleaned with solvent before being used for tests.

Dry Opacity: Both white and yellow paints shall have a minimum contrast ratio of 0.96. Contrast ratio shall be determined by applying a wet film thickness of 0.005 inches (127 microns) to a standard hiding power chart. After drying, the black and white reflectance values shall be determined using a suitable reflectometer and the contrast ratio determined.

Freeze-Thaw Resistance: After five freeze thaw cycles in accordance with ASTM D2243: 1) Evidence of settling, gelation, or coagulation in the can shall have a rating of no less than 8 (very slight). 2) The paint shall not have a change in viscosity (ASTM D562) of more than 10 Kreb units. 3) Test panel changes in hiding, gloss, speckiness, agglomeration, coagulation, or color change shall have a rating of no less than 8 (very slight).

Bleeding: The paints shall have a minimum bleeding ratio of 0.97 when tested in accordance with FS TT-P-1952. The asphalt-saturated felt shall conform to FS HH-R-59.

Abrasion Resistance: No less than 210 liters of sand shall be required to remove paint film when tested in accordance with TT-P-1952.

Color: The paint shall not discolor in sunlight and shall maintain colorfastness throughout its life, approximately two years. Color determination shall be made without beads, after a minimum of 24 hours. Color for yellow paint shall be a visual match for 595-13538. If not a visual match, the diffuse day color of the paint shall conform to the CIE Chromaticity coordinate limits as follows:

	x y		x y		x y		x y		Brightness
<u>White:</u>	(x) 0.305	(y) 0.295	(x) 0.360	(y) 0.360	(x) 0.388	(y) 0.377	(x) 0.280	(y) 0.310	84.0
<u>Yellow:</u>	(x) 0.485	(y) 0.455	(x) 0.506	(y) 0.452	(x) 0.484	(y) 0.428	(x) 0.477	(y) 0.438	50.0

Liquid Calcium Chloride Anti-icing Agent

REFERENCE FILE Number 2007-3

Issued August 1, 2007

Scope: This reference file consists of the specification for Liquid Calcium Chloride Anti-icing Agent, which is to be used with Sodium Chloride for snow and ice control by the Connecticut Department of Transportation (Department).

The supplier shall furnish a Certified Test Report and Materials Certificate as detailed below for each batch delivered to the Department.

The Certified Test Report is a document containing a list of the dimensional, chemical, metallurgical, electrical and physical results obtained from a physical test of the materials involved, and shall certify that the materials being supplied meet the requirements of this specification. Such Report shall also include the following information:

- (1) Description of materials
- (2) Date of manufacture
- (3) Date of testing
- (4) Name of organization to which the material has been consigned, if applicable
- (5) Quantity of material represented, such as batch, lot, group, etc.
- (6) Means of identifying the consignment, such as label, marking, lot number, etc.
- (7) Date and method of shipment
- (8) Name of organization performing tests

The Certified Test Report shall be signed by a duly-authorized and responsible agent for the organization manufacturing the materials, and the signature must be notarized.

A Materials Certificate is a document certifying that the materials, components and equipment furnished conform to all requirements of this specification. Such Certificate shall also include the following information:

- (1) Quantity of material represented, such as batch, lot, group, etc., and certified test report identification number representing materials being delivered

- (2) Quantity of material represented by the certificate
- (3) Means of identifying the consignment, such as labels, lot numbers, etc.
- (4) Date and method of shipment

The Materials Certificate shall be signed by a duly-authorized and responsible agent for the organization supplying the material, and the signature must be notarized.

The supplier shall be responsible for all testing and materials certificates.

Samples: The ConnDOT representative may take one gallon sample at start, and one gallon prior to the end of delivery, Samples must be taken directly from the truck.

References to the web site of the Pacific Northwest Snowfighters Association (PNSA) of British Columbia, Idaho, Montana, Oregon and Washington (<http://www.wsdot.wa.gov/partners/pns/default.htm>) are exclusively to the 2007 testing method(s) that the Department’s Division of Materials Testing will use to determine if the product meets this specification. PNSA specifications listed on the PNSA Web site are for information only and do not necessarily reflect requirements of this REFERENCE FILE (Number 2007_3).

ConnDOT Test Methods and Specification Limits:

ConnDOT Test #1 - Percent Concentration of Active Ingredient in the Liquid

The Product shall be 32% Calcium Chloride by weight; tolerance: ±1%, per PNSA Test Method Number 1 on page 24 of the PNSA Web site or by ASTM methods D345 and E449. It is intended that only products meeting the specified Liquid Calcium Chloride content of 31% to 33% will be accepted; however, at the sole discretion of the Department of Transportation, Liquid Calcium Chloride content lower or greater than this percent may be accepted with an adjustment in payment in accordance with table 1.

Percent of Liquid Calcium	Percent Payment of Unit Bid Price
29% to 30%	90
34% to 35%	90

At the sole discretion of the Department, Liquid Calcium Chloride content lower than 29% or greater than 35% is subject to rejection and nonpayment.

All test data shall be rounded in accordance with the latest version of **AASHTO R11**.

ConnDOT Test #2 - Weight per Gallon

Specific Gravity by ASTM D 1429 Test Method A - Pycnometer at 20°C +/- 1°C per PNSA Test Method Number 2 on page 24 of the PNSA Web site.

ConnDOT Test #3 - PH

The PH shall be between 6.0 -10.0 per PNSA Test Method Number 4 on page 24 of the PNSA Web site.

ConnDOT Test #4 - Sampling Liquid Calcium Chloride

Sampling Liquid Calcium Chloride shall be done in accordance with ASTM D345. Product shall be tested using generally accepted industry standard analytical procedures as appropriate.

ConnDOT Test #5 - Visual Inspection and Field Observations

A ConnDOT representative may perform a visual inspection to assure that the material remains clean and free of extraneous matter, remains free from hard caking, does not segregate, and remains suitable for the intended purpose and as otherwise outlined in Section IV. NOTE: Purchaser may use any laboratory test method necessary to verify conclusions from visual inspections. Per PNSA Test Method Number 14 on page 25 of the PNSA Web site.

ConnDOT Test #6 - Total Arsenic, Barium, Cadmium, Chromium, Copper, Lead, Mercury, Selenium, Zinc, Phosphorus, and Cyanide

Atomic Absorption Spectrophotometry or Plasma Emission Spectroscopy as described in "Standard Methods for the Examination of Water and Waste Water," APHA-AWWA-WPCF per PNSA Test Method Number 9 on page 25 of the PNSA Web site.

A submitted product that contains any constituent in excess of the following established total concentration limits as tested in accordance with the above test shall not be acceptable. Results are stated as parts per million (ppm).

Arsenic	1.0 ppm
Barium	100.0 ppm
Cadmium	0.20 ppm
Chromium	1.0 ppm
Copper	1.0 ppm
Lead	1.0 ppm
Mercury	0.05 ppm
Selenium	5.0 ppm
Zinc	10.00 ppm
Phosphorus	250.00 ppm
Cyanide	0.20 ppm

Note: Liquid products shall be tested as received .

All laboratory results must be below the maximum concentrations listed above.

Appendix G – Standard Operating Procedures

	Version	Date	Pages
Portland Cement Concrete			
Compression Testing	V1.1	Dec 2014	G2-G6
Grout			
Compression Testing	V1.0		G7-G12
Bituminous Concrete			
In-place density using Cores	V1.1	Dec 2014	G13-G18
Steel Reinforcement			
Tensile Testing			Pending
Bend Testing			Pending
Hardness Testing			Pending
Snow and Ice Control			
Testing for Moisture of Roadway Salt	V1.0		G19

TINIUS-OLSEN COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1

John Giannini

Supervisor of Laboratory/Workshop

Tinius-Olsen Hydraulic Compression Tester Equip. #68-3695

Name and Function of Lab/Project

Tinius-Olsen

Make

Mechanical & Electrical

Type of hazards (mechanical, electrical, chemical, biological or radiation)

Room 150

Location

400,000 Lbf Super "L"

Model

A. Introduction/Features

- 400,000 Lbf Capacity
- Heavy-duty, ultra-stiff frame design permits testing of 6" X 12" and 4" X 8" concrete cylinders
- Side and rear safety guards ensure operator safety
- High-accuracy pressure transducer load weighing system
- HP Compaq MXL31707H6 Controller
- Wire safety cage to prevent debris from falling outside testing area.

B. Health and Safety Considerations

I. Safety devices required (e.g. machine guards, personal protective equipment, etc.)

- ***SAFETY GOGGLES/GLASSES*** must be worn **at all times in the lab**. Prescription glasses can be worn under the safety goggles.
- ***HARD TOE BOOTS/SHOES*** must be worn **at all times while handling cylinders**.

II. General Safety

- **FOOD AND DRINK** are not allowed in any laboratory.
- Be aware of the specific hazards associated with each lab procedure.
- Wear appropriate clothing and foot wear (**NO OPEN-TOED SHOES**).
- Familiarize yourself with all emergency safety equipment (eyewash, fire alarm, fire extinguishers, telephone).
- Do not leave in-progress tests unattended.
- **Keep work areas Clean.**

TINIUS-OLSEN COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1

FIRE: Immediately **report it to a supervisor** and then exit the laboratory and building quickly via proper exit route. (Make sure you know where the exits are located.)

ACCIDENTS AND INJURIES must be reported to a supervisor. There are emergency first aid supplies available, and emergency responders are trained in basic first-aid.

THE BEST SAFETY PRECAUTIONS include **ADVANCED PREPARATION** for each laboratory and a **CLEAN ORGANIZED WORK SPACE**.

C. Operation Procedures:

The following guidelines are for persons who are authorized to use the Tinius-Olsen compression machine for **ASTM C-39 & ASTM-1231**. If a person is operating equipment for the first time, a competent operator of that equipment must also be present.

Power On equipment

1. Turn on the testing machine by using the power switch (LPLH-LF-CIR.9) located on the wall near the service panel to the right of the testing machine as shown in Figure 1.




Figure 1. Power Switch Location for Tinius-Olsen Compression Machine

2. Turn on computer and computer monitor using switches shown in Figure 2.



Figure 2. Computer and Monitor Power Switches

TINIUS-OLSEN COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1

Turn on hydraulic pump by pressing “Pump” button on handheld controller as shown in Figure 3. **When leaving the area of the machine for an extended period of time (10 minutes or more) shut off pump.**

1) **PUMP** will appear on the display (let pump warm up for about 20 seconds)

2) Press “Return” button on handheld controller (the bottom compression plate will raise to specific height)



Figure 3. Handheld Controller and Compression Plates

- a. Using the computer mouse, Click on “Navigator” icon **on the computer monitor**
- b. **Using the steps below, check that the software is configured for the proper size cylinder.**
 - 1) go to file
 - 2) load test setting
 - 3) #8 for 6x12 or #9 for 4x8

Test Preparation

- c. Review MAT-308 and enter project number and sample ID on “NEXT” tab
- d. Check cylinder markings for concurrence with MAT-308
- e. Type in or check appropriate cylinder size (typically 6 or 4 inches) is displayed
- f. Place test caps on bottom and top of cylinder. Caps are shown in Figure 4.
- g. Properly place specimen (centered on bottom compression plate)
- h. Place wire safety cage centered around specimen, close cage. Cage is shown in Figure 4.

TINIUS-OLSEN COMPRESSION MACHINE

Standard Operating Procedure




Version 1.1



Figure 4. Wire Safety Cage and Test Caps

3. Test Procedure

4"x8" cylinders

- Double click on  in top menu bar to raise base plate until **the cylinder is located $\frac{1}{8}$ " from top plate** then click on the red STOP sign.
- Click on the "LOAD ZERO" icon in top menu bar (handheld controller should show zero load)
- Click on TEST NOW button
- Monitor the testing (Click on ABORT button if needed)

6"x12" cylinders

- Click on the "LOAD ZERO" icon in top menu bar (handheld controller should show zero load)
- Click on TEST NOW button
- Monitor the testing (Click on ABORT button if needed)

4. Documentation of Results

- Observe how specimen broke and that no contact with wire safety cage was made.
- Double check project number and sample ID, edit on "RESULTS" tab if needed.
- Click on "ACCEPT" if no issues were observed. Click "DISCARD" if needed.
- Record Total load and Load (PSI/Mpa) on Mat-308 from yellow highlighted information at the bottom the window.

5. Remove crushed specimen

- Open and remove wire safety cage
- Discard crushed specimen in yellow rolling metal bin.
- Clean bottom plate of any debris.

TINIUS-OLSEN COMPRESSION MACHINE



Version 1.1

Standard Operating Procedure

6. To test another specimen;
 - e. Press the “**NEXT**” tab;
 - f. Return to step 2

7. Clean and shutdown
 - g. Properly close “Navigator” window by clicking on [X] in top right corner.
 - h. Click on “Start” icon in lower left corner and select “SHUTDOWN” from menu.
 - i. Turn pump off using handheld controller shown in Figure 3.
 - j. Switch test equipment off by using switch shown in Figure 1.
 - k. Clean floor, pan, and plates of any debris.
 - l. Record number of cylinders tested on Pad Usage Sheet in three ring binder located on test console.

If you ever have any doubts or questions, ASK!

Emergency Contacts:

John Giannini, Supervising Engineer, 860-258-0324

Daniel Guzzo, Transportation Engineer III, 860-258-0339

Mark Brothwell, Transportation Engineer II, 860-258-0378

FIRE/AMBULANCE/SAFETY -Emergency Response, 9-911

SATEC COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1

John Giannini

Supervisor of Laboratory/Workshop

Mechanical & Electrical

Type of hazards (mechanical, electrical, chemical, biological or radiation)

SATEC SYSTEMS

Hydraulic Compression Tester

Equip. #68-3712

Name and Function of Lab/Project

Room 155

Location

SATEC-QC PRISM

Make

Mark III Smart "C" 100QC

Model

A. Introduction/Features

- 100,000 Lbs. Capacity
- Heavy-duty, ultra-stiff frame design permits testing of 2" X 2" grout cube
- Side and rear safety guards ensure operator safety
- High-accuracy pressure transducer load weighing system
- Mark III *Smart "C"* Indicator display Controller
- Wire safety cage to prevent debris from falling outside testing area.

B. Health and Safety Considerations

I. Safety devices required (e.g. machine guards, personal protective equipment, etc.)

- ***SAFETY GOGGLES/GLASSES*** must be worn **at all times in the lab**. Prescription glasses can be worn under the safety goggles.
- ***HARD TOE BOOTS/SHOES*** must be worn **at all times while handling cubes**.

II. General Safety

- **FOOD AND DRINK** are not allowed in any laboratory.
- Be aware of the specific hazards associated with each lab procedure.
- Wear appropriate clothing and foot wear (**NO OPEN-TOED SHOES**).
- Familiarize yourself with all emergency safety equipment (eyewash, fire alarm, fire extinguishers, telephone).
- Do not leave in-progress tests unattended.
- **Keep work areas Clean.**

See attached sheets pages 1-5

SATEC COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1

COMPRESSION MACHINE PROCEDURES




These buttons will all be explained on the next few pages.

SATEC COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1



Step 1
Flip switch for power.



Step 2
Turn knob clockwise
till it pops up.



Step 3
Press the button to turn on
the pumps.




SATEC COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1



SATEC COMPRESSION MACHINE


Standard Operating Procedure



Version 1.1


Step 8

Place cube between cylinders with the **rough sides** facing away from the plane surfaces.




plane surfaces

rough side



Step 9

Start placing a load on the specimen gradually. You will see the digital display numbers go up. Set the dial at around 4 and 5.



SATEC COMPRESSION MACHINE

Standard Operating Procedure



Version 1.1




Step 10

Push the servo button. It will then start placing a load on the specimen gradually. You will see the digital display numbers go up.

Step 11

When you notice the numbers slowing down or stress cracks on the cube itself that means it's reached its breaking point.



Total Load

PSI

These are procedures that will ensure the proper methods of testing cement cubes per ASTM C109.

HANDLING AND TESTING BITUMINOUS CONCRETE CORE SAMPLES FOR IN-PLACE DENSITY DETERMINATION



Version 1.1

Standard Operating Procedure

Eliana Carlson

Supervisor of Laboratory/Workshop

Mechanical & Electrical

Type of hazards (mechanical, electrical, chemical, biological or radiation)

**Handling and Testing Hot Mix
Cores for Density Determination**

Name and Function of Lab/Project

Rooms 162 and 159

Location

Various

Make

Various

Model

A. Introduction/Features

- Procedures to be followed for the in-place density of bituminous concrete mixtures by testing cores samples
- Handling of the bituminous concrete core samples include:
 - Receiving core samples (chain of custody)
 - Organization
- Testing of the bituminous concrete core samples include:
 - Saw cutting core samples
 - Drying core samples
 - Testing for bulk specific gravity
 - Reporting
 - Core sample retention and disposal
- Equipment:
 - 5 Vacuum drying apparatus located in room 162:
 - Make: Instrotek
 - Model: CoreDry
 - 1 Automatic vacuum sealing apparatus located in Room 162
 - Make: Instrotek
 - Model: CoreLok
 - 2 Radial cutting table saws located in Room 159
 - Make: Nuova Mondial Mec
 - Model: Manta ED 120

HANDLING AND TESTING BITUMINOUS CONCRETE CORE SAMPLES FOR IN-PLACE DENSITY DETERMINATION



Version 1.1

Standard Operating Procedure

B. Health and Safety Considerations

I. Safety devices required (e.g. machine guards, personal protective equipment, etc.)

- **SAFETY GOGGLES/GLASSES** must be worn when operating the table saw. Prescription glasses can be worn under the safety goggles.
- **SAFETY EAR PROTECTION** must be worn when operating the table saw.
- The operator shall keep all body parts outside the **MACHINE GUARDS** when operating the table saw
- **HARD TOE BOOTS/SHOES** must be worn **at all times in the laboratory**.

II. General Safety

- **FOOD AND DRINK** are not allowed in any laboratory.
- Be aware of the specific hazards associated with each laboratory procedure.
- Wear appropriate clothing and foot wear (**NO OPEN-TOED SHOES**).
- Familiarize yourself with all emergency safety equipment (eyewash, fire alarm, fire extinguishers, telephone).
- Do not leave in-progress tests unattended.
- **Keep work areas Clean.**

FIRE: Immediately **report it to a supervisor** and then exit the laboratory and building quickly via proper exit route. (Make sure you know where the exits are located.)

ACCIDENTS AND INJURIES must be reported to a supervisor. There are emergency first aid supplies available, and emergency responders are trained in basic first-aid.

THE BEST SAFETY PRECAUTIONS include ADVANCED PREPARATION for each laboratory and a CLEAN ORGANIZED WORK SPACE.

C. Equipment Maintenance

All maintenance operations shall follow the corresponding operator's manual.

CoreDry Maintenance:

- Change the vacuum pump oil (InstroTek part number 1520137) after 80 hours of use. A software indicator will prompt you to do so. Keep the maintenance records updated in the corresponding calibration and maintenance book.
- Change your Tank Filters (InstroTek part number 1009012) every 1 to 2 months. Keep the maintenance records updated in the corresponding calibration and maintenance book.

HANDLING AND TESTING BITUMINOUS CONCRETE CORE SAMPLES FOR IN-PLACE DENSITY DETERMINATION



Version 1.1

Standard Operating Procedure

- Change your exhaust filter (InstroTek part number 1520084) on the vacuum pump once a year. Keep the maintenance records updated in the corresponding calibration and maintenance book.

CoreLok Maintenance:

- Weekly, check oil level, the condition of the silicon pad in lid, the condition of the silicon gasket in lid, the condition of the seal bar Teflon tape and seal element, the condition of the CoreLok lid and glass viewing window. Keep records of the oil refills in corresponding calibration and maintenance book.
- Yearly, replace vacuum oil using 10-weight synthetic oil, exhaust filter, seal element and Teflon tape of the seal bar. Keep records of these replacements in the corresponding calibration and maintenance book.

D. Operation Procedures – Handling Bituminous Concrete Core Samples:

Receipt of Cores (Chain of Custody):

The Contractor is responsible to obtain, label and transport core samples to the DMT. The Engineer will select the core locations, witness the extraction and labeling of the core samples and will complete Form MAT 109. The cores and corresponding MAT 109 will be delivered to the DMT in a secured container approved by the Engineer. Upon delivery DMT staff will:

1. Inspect the container and cut the security seal(s).
2. Verify the security seal numbers match numbers documented on MAT 109.
3. Check in and take possession of each core sample by comparing the labeling on the core to the sample identifications listed on the MAT 109 and inspecting each core sample for visible damage. Document discrepancies or damaged core(s) on the MAT 109. The DMT inspector will initial and date the MAT 109.
4. If no discrepancies exist, place cores and MAT 109 on a rack for testing.
5. If discrepancies or damaged samples are found, notify the room lead who will send an e-mail to the project inspector or other designated district staff detailing the observation(s).
6. Damaged cores shall not be tested.
7. If a Mat 109 or security seal(s) are not present, the room lead will send an e-mail to the project inspector or other designated district staff. The cores will be retained until such time a decision is made to test or not.
8. Once the observation(s) is cleared the sample(s), or replacement sample(s), will be placed on a rack for subsequent testing.

Organization:

Log in all the core samples received (including damage cores and note this in the corresponding column) in the “Tracking Cores” file located in the year folder in: S:\Verification & Cores\HMA Core Density Testing. The room lead will input an entry in the tracking file for any correspondence with project personnel.

HANDLING AND TESTING BITUMINOUS CONCRETE CORE SAMPLES FOR IN-PLACE DENSITY DETERMINATION



Version 1.1

Standard Operating Procedure

E. Operation Procedures – Testing Bituminous Concrete Core Samples:

*The following guidelines are for persons who are authorized to use the CoreDry, CoreLok and Table Saws for **ASTM D 7227/D 7227M & AASHTO T 331**. If a person is operating any of this equipment for the first time, a competent operator of said equipment must also be present.*

Sample Preparation - Saw Cutting Core Samples:

When applicable, the core will be separated into individual lifts. This will be accomplished by slight strokes with a chisel or the use of a table saw. Care shall be taken to ensure the lift to be tested is not damaged. In general, any sample that cannot be readily separated into individual lifts by the use of a chisel or if the testing bag does not conform to the specimen in a uniform manner will be saw cut. Any remaining material that is not used for testing will be discarded. The lift will be cleaned to remove any deleterious material from the coring or sawing process.

Before operating the table saw, refer to the corresponding job hazard analysis document in Appendix A of this manual.

Sample Preparation - Drying Core Samples:

1. CoreDry Daily Test: Everyday, before starting operation, test the CoreDry equipment according to the equipment manual. If the test fails, notify the room lead.
2. Towel-dry the surface of the core and place it on its side on the wire mesh sample support (Figure 1).
3. Place the lid on sample chamber (Figure 2 – red arrow) and press start (Figure 2 - blue arrow).
4. When sample is dry, the unit will automatically stop and the lids can be removed.
5. If the sample is not dry after 45 cycles, remove the sample and place at room temperature for 15 minutes and continue drying the sample.
6. Between samples, remove the cold trap lid (Figure 2 – green arrow) and the divider plate and wipe out the cumulate moisture using a lint free cloth. Always replace the divider before drying the next sample.



HANDLING AND TESTING BITUMINOUS CONCRETE CORE SAMPLES FOR IN-PLACE DENSITY DETERMINATION

Standard Operating Procedure



Version 1.1

**Figure 1. Placing a Core Sample in the CoreDry Sample Chamber
(Instrotek CoreDry Manual)**




Figure 2. CoreDry Components

Testing for Bulk Specific Gravity:

1. Select and inspect the bag for holes or stress points. Do not use the bag if you find holes or stress points.
2. Record the thickness of the core in column L in the "input" sheet in of Form MAT 438.
3. Weight the bag and enter this weight in column F in the "input" sheet in of Form MAT 438.
4. Weigh the dry sample and record the sample weight in column G in the "input" sheet in of Form MAT 438.
5. Check CoreLok oil level as indicated in the equipment operator manual.
6. Place the bag in the CoreLok Chamber and carefully place the sample inside the bag. The bag opening shall be over the seal bar (Figures 3 and 4) with approximately 1" overlap.
7. Close the CoreLok door and the equipment will seal the bag.
8. Record the weight of the sample sealed inside the bag under water in column I in the "input" sheet in of Form MAT 438. Make sure that the bag is not touching the sides or bottom of the water tank and that all entrapped air has been remove (this may be accomplished by gently shaking the bag under water).
9. Remove the bag and sample from the water bath, cut the bag and record the dry weight of the core in column J in the "input" sheet in of Form MAT 438. If the dry weight of the core before and after test in column J and G differ by more than 1gr, repeat the process from 1 thought 9.
10. All weights of shall be entered into the electronic MAT 438 between two days of testing and all the data shall be reviewed.
11. Notify your chain of command and obtain a quote when the stock of bags is reduced to ten boxes (1000 bags).

HANDLING AND TESTING BITUMINOUS CONCRETE CORE SAMPLES FOR IN-PLACE DENSITY DETERMINATION



Version 1.1

Standard Operating Procedure



**Figures 3 and 4. CoreDry Seal bar and Sample Placement
(Instrotek CoreLok Manual)**

Reporting:

The percentage compaction shall be reported as the percent of the average day's production acceptance maximum theoretical gravity (Gmm) results performed in accordance with AASHTO T 209. Gmm test results determined to be invalid will not be included in the daily's average Gmm determination. The Engineer may replace the contractor's Gmm result(s) with the verification result(s). If Gmm test results are not available from acceptance testing, the Gmm shall be tested from a sample obtained by breaking down the core after the core has been tested or shall be determined from historical data.

The percent compaction of each core (sub-lot) will be determined using the following formula:

$$\text{Percent compaction} = 100[\text{Gmb of core} / \text{Gmm of day's production (avg.) or Gmm core sample or historical Gmm}]$$

All percent compaction results will be reported to the nearest 0.1 percent. The density report will automatically mark in red all individual density results that are outside the 87-95% range and that are outside +/-3.5% of the average. The cores that provide results on red will be re-tested.

The handling, testing and reporting of core samples will be monitored and reviewed by DMT supervisory staff (E3 and above) on an ongoing basis. Any change to the standard procedure, shall be approved by the SE or above prior to implementation.

Once a lot is completed the results shall be emailed by the DMT's core testing room lead to project inspection staff or other designated district staff. At no time will the DMT forward results directly to the Contractor. In general, the following shall be included in the email list:

HANDLING AND TESTING BITUMINOUS CONCRETE CORE SAMPLES FOR IN-PLACE DENSITY DETERMINATION



Version 1.1

Standard Operating Procedure

- Construction projects; Project Engineer, Project Inspector, District email, DMT chain of command.
- VIP and other Maintenance Projects; District Planners and/or other designated staff, DMT chain of command.
- Municipal Projects; Muni Team leader, Muni team inspector (if known), muni MAT 100 email, DMT chain of command.

Report Form: Form MAT 438 or other form approved by the DMT.

Core Sample Retention and Disposal:

After the specific gravity testing has been completed and reviewed by the room lead, store the tested core in the back hall rack for a two-week period. After two weeks, dispose the cores in the HMA recycling bin located in the back dock. In general cores that are below the minimum acceptable density (negative adjustment range) should be retained for a slightly longer period to allow for inspection by others. Any lot that is remove and replace will be retained until such time it is determined they are no longer needed.

If you ever have any doubts or questions, ASK!

Emergency Contacts:


Eliana Carlson, Supervising Engineer, 860-258-0325

David Howley, Transportation Engineer III, 860-258-0350

Shane St. Lauren, Transportation Technician III, 860-258-03??

FIRE/AMBULANCE/SAFETY -Emergency Response, 9-911

STANDARD OPERATING PROCEDURE



Testing For Moisture of Roadway Salt



Division of Materials Testing

Connecticut Department of Transportation

Why is roadway salt tested for moisture content?

- Roadway salt is paid for based on gross weight.
- Specifications allow 3% moisture content for full payment.
- Weight of water in excess of 3% is deducted from payment by contract administrator (Purchasing).
- Salt with excess moisture may clump and freeze, making handling difficult.

Scale Inspection/Check

- Scales must be labeled with current calibration date.
- Scale must show same reading (within 0.1 gram) when weighing the same reference weight.
- These steps must be performed before each test or if a scale has been moved.



Connecticut Department of Transportation

Sample, and chain of custody, must be maintained at all times.

- Sample must be representative of the pile being tested.
- Sample must not be taken from surface of a pile.
- **Do not** pick out large or discolored particles.
- Take samples from no less than 3 areas of the pile.
- All equipment used in the testing process must be maintained at all times.



Connecticut Department of Transportation

Equipment Needed:

- *Oven*



- *Calibrated Digital Scale*



- *Sampling Containers/Sampling Bag*



- *Shovel / Scoop / Sample Thief*



Connecticut Department of Transportation

Reference: Standard Testing Specification For (Sodium Chloride ASTM D632)

This procedure must be consistently and thoroughly followed.

Sampling:

1. Scrape aside the top layer of salt to a depth of no less than 1 inch.



Figure 1 - Preparing field sampling location



Connecticut Department of Transportation

2. Take approximately 500 g of material to a depth of six inches.
 - Repeat steps 1 and 2 at two locations, no less than five feet from each other.



Figure 2 - Sampling

3. Place the three samples in a sample bag.



Figure 3 - Filling field sample bag



Connecticut Department of Transportation

4. Sample bag must be closed tightly while transporting field sample.



Figure 4 – Securing sample bag

5. The field sample must be reduced to a minimum of 300 grams test sample using sample splitter.



Figure 5 - Sample splitter

6. Determine the mass of the test sample and a metal container of stable shape and weight, using a scale.



Figure 6 - Scale



Connecticut Department of Transportation

- Place the test sample, within the container into the drying oven at a temperature of $230^{\circ} \pm 9^{\circ}\text{F}$.



Figure 7 – Drying oven

- Cool sample on the counter until cool to the touch, then determine the mass weight of the test sample and container.
- Repeat steps 7 and 8 until test sample weight changes less than 0.1 %.
- Use the following formula to determine the moisture content of the test sample.

$$\text{moisture content (\%)} = \frac{(\text{wet mass} - \text{dry mass})}{(\text{dry mass})} \times 100$$



References

Photos:

1. Oven – “Clarkson Laboratory”,
 - <http://store.clarksonlab.com/O4325-B.aspx>
2. Digital Scale – “Scale Palace”,
 - https://scalepalace.com/index.php?main_page=index&manufacturers_id=6&sort=20a&page=3
3. Scoop – “Cole-Palmer”,
 - [http://www.coleparmer.com/Product/Stainless Steel Scoop 201 Grade 5 oz 1 each/EW-07205-01](http://www.coleparmer.com/Product/Stainless%20Steel%20Scoop%20201%20Grade%205%20oz%201%20each/EW-07205-01)
4. Sample Thief – Wilkey Industries, Inc”,
 - <http://www.wilkeyindustries.com/sample-probe.php>
5. CTDOT Salt Shed – “Ctpost”,
 - <http://www.ctpost.com/local/article/Storms-draining-road-salt-supplies-straining-5222298.php>

❖ All other photos are property of CTDOT



Index

- Admixtures for Portland Cement Concrete, 29
- Aggregate Degradation, Resistance to, 20
- Aggregate Soundness, 21
- Aggregate, Bulk Density, 21
- Aggregate, Flat and/or Elongated Particles, 21
- Aggregate, Fractured Particles, 21
- Aggregate, Inorganic Impurities in., 21
- Aggregate, Mechanical Analysis for HMA, 30**
- Aggregate, Reducing Sample size, 20
- Aggregate, Sampling, 20, 23
- Aggregate, Sieve analysis, 20
- Aggregate, Specific Gravity and Absorption, 21
- Aggregate, Total Evaporative Moisture Content, 21
- Aggregate, Voids in, 21
- Aluminum, Castings, 14
- Aluminum, fittings, 14
- Aluminum, tubing, 14
- AMRL Certification Document, 36
- Anchor Bolts, Steel, 16
- Anchorage, Cable Guide Rail, 16
- Asphalt, Emulsified, 18
- Asphaltic Plug Joint, 19
- Bearing Pads, 16
- Bearing Pads, Elastomeric, 16
- Bearing plates, bronze or copper, 16
- Bolts, Anchor, 16
- Bolts, High strength Steel, 17
- Bronze Bearing plates, 16
- Bronze Expansion plates, 16
- Bulk Specific Gravity of HMA, 31**
- Cable Guide Railing, 16
- Calcium Chloride, 9
- Castings, Metal, 14
- Cement, 13
- Chain Link Fence, 14
- Compression Seals, Elastomeric, 14
- Concrete Block, 14
- Concrete Brick, 14
- Concrete Mix Design, 12
- Concrete Pavement, Transverse joints, 13
- Concrete Pipe inspection, 23
- Concrete, Admixtures, 29
- Concrete, Gravimetric test, 29**
- Concrete, Inspection of batch plants and truck mixers), 29
- Concrete, Pipe reinforced, 23
- Copper Bearing plates, 16
- Copper Expansion plates, 16
- Evaporative Moisture Content, Aggregate, 21
- Expansion plates, Bronze or Copper, 16
- Fence, Chain Link, 14
- Fence, Wire, 15
- Fertilizer, 9
- Geotextiles, 15
- Glass Beads/Spheres, 9
- Grass, 9
- Grout, non-shrink, non-staining, 12
- HMA Plants, Annual Qualification, 30
- HMA Sampling, 30
- HMA, Gyrotory Specimens, 31
- HMA, Mix Design Submittal and JMF Change Procedure, 32
- HMA, New and Existing Mixes, 32
- HMA, Particle Coating, 31
- HMA, Personnel Assignment, 30
- HMA, Plant Inspector, 32
- HMA, Production Inspection, 32
- HMA, Resistance to Moisture Induced Damage, 35
- HMA, Verification Testing, 33
- HMA, VMA and Correction Factor, 31
- HMA, Volumetric and Specific Gravity, 35
- Hot Mix Asphalt, 18
- Illumination, Highway, 17
- Independent Assessment/Verification Program, 37
- Joint Sealants, 13
- Joints, Transverse for Concrete Pavement, 13
- L.A. Abrasion, 20
- Limestone, 10
- Magnesium Sulfate, 21
- Markers, Object, 18
- Masonry Facing, 21
- Maximum Specific Gravity of HMA, 32**
- Metal, Castings, 14
- Mulch, Wood Cellulose, 10
- Nuclear Density of Soils, 35**
- Object Markers, 18
- Organizational Chart, 3
- Overview, Division of Materials Testing, 2
- Paint, Pvmnt Marking 15 Min., 8
- Paint, Traffic 3 Min., 8
- Peat, 9
- Perforated Concrete Pipe, 10*
- Performance Graded Asphalt Binder (PGAB), 35**

Piles, Steel, 17
 Pipe, Concrete, 23
Pipe, Concrete Perforated, 10
Pipe, Concrete plain, 10
 Pipe, plastic, 11
 Pipe, polyethylene, 11
 Pipe, PVC, 11
 Pipe, Steel, Welded and Seamless,
 11, 12
Plain Concrete Pipe, 10
Plastic Flow of HMA, 31
 Portland Cement, 12, 13
 Precast Concrete Drainage Items, 11
 Precast Concrete for drainage
 structures, 11
 Precast Concrete Structural
 Members, 13
 Precast Concrete Structural
 Members, Fabrication Inspection,
 13
 Purpose, 1
 Quality Acceptance Section (QAC), 4
 Quality Assurance Section, 5
 Rock Salt, 9
Sampling, Care in, 22
 Sand Blast Debris, 8
 Sealers, Hot Poured, 14
 Seed, 9
 Sheet Piling, Steel, 17
 Signals, Traffic Control, 17
 Signs, 18
 Sod, 10
 Sodium Chloride, 9
 Steel Sheet Piling, 17
 Steel, Anchor Bolts, 16
 Steel, Bar Mat, 12
 Steel, Coatings, 8
 Steel, High strength bolts, 17
 Steel, Prestressing, 13
 Steel, Reinforcing Bar, 12
 Steel, Structural, 17
 Steel, Welded Wire Fabric, 12
 Steel, Wire, 12
 Top Soil, 10
Washing, Material finer than #200 Sieve, 20
 Water, 9
 Waterproofing, Membrane, 19
 Welding, Filler metal, 17
 Wire Fence, 15
 Wood Fiber Mulch, 10