

STATE OF CONNECTICUT
CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051
Phone: (860) 827-2935 Fax: (860) 827-2950
E-Mail: siting.council@ct.gov
www.ct.gov/csc

November 2, 2012

Christopher Bisson
New Cingular Wireless PCS, LLC
154 General Patton Drive
Naugatuck, CT 06770

RE: **EM-CING-013-121015** – New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 133 Gifford Lane, Bozrah, Connecticut.

Dear Mr. Bisson:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- The coax lines and accessory equipment shall be installed in accordance with the recommendations made in the Structural Analysis Report prepared by FDH Engineering dated August 27, 2012 and stamped by Christopher Murphy; and
- Following the installation of the proposed equipment, AT&T shall provide documentation certifying that the installation complied with the engineer's recommendation.
- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Not less than 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated October 5, 2012. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General

Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,



Linda Roberts
Executive Director

LR/CDM/cm

c: The Honorable William E. Ballinger, First Selectman, Town of Bozrah
Seymour Adelman, Planning and Zoning Chairman, Town of Bozrah



STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: siting.council@ct.gov

www.ct.gov/csc

October 16, 2012

The Honorable William E. Ballinger
First Selectman
Town of Bozrah
1 River Road
Bozrah, CT 06334-0158

RE: **EM-CING-013-121015** – New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 133 Gifford Lane, Bozrah, Connecticut.

Dear First Selectman Ballinger:

The Connecticut Siting Council (Council) received a request to modify an existing telecommunications facility, pursuant to Regulations of Connecticut State Agencies Section 16-50j-72. A copy of which has already been provided to you.

If you have any questions or comments regarding the proposal, please call me or inform the Council by October 30, 2012.

Thank you for your cooperation and consideration.

Very truly yours,

Linda Roberts
Executive Director

LR/cm

c: Seymour Adelman, Planning and Zoning Chairman, Town of Bozrah



EM-CING-013-121015


Cingular Wireless PCS, LLC
154 General Patton Dr.
Naugatuck, CT 06770
Phone: (203)-217-6200
Christopher Bisson
Real Estate Consultant

ORIGINAL

October 5, 2012

Hand Delivered

Ms. Linda Roberts
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051



RE: New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located at 133 Gifford Lane, Bozrah, CT 06334, Known to AT&T as site CT2223.

Dear Ms. Roberts:

In order to accommodate technological changes, implement Uniform Mobile Telecommunications System ("UMTS") and/or Long Term Evolution ("LTE") capabilities, and enhance system performance in the state of Connecticut, New Cingular Wireless PCS, LLC ("AT&T") plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and its attachments is being sent to the chief elected official of the municipality in which affected cell site is located.

UMTS offers services to mobile computer and phone users anywhere in the world. Based on the Global System for Mobile ("GSM") communication standard, UMTS is the planned worldwide standard for mobile users. UMTS, fully implemented, gives computer and phone users high-speed access to the internet as they travel. They have the same capabilities even when they roam, through both terrestrial wireless and satellite transmissions.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in AT&T's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration based on the supplied structural modification plan dated 4/26/2012 requiring the restacking of the existing coaxial cables.

The changes to the facility do not constitute modification as defined Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for the R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will not be affected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound as all proposed equipment will be located in the existing AT&T equipment shelter.
3. The proposed changes will not increase the noise level at the existing facility by 6 decibels or more.
4. Radio Frequency power density may increase due to the use of one or more GSM channels for UMTS transmissions. Moreover, LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons New Cingular Wireless PCS, LLC respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (203)-217-6200 or email CBisson@Transcendwireless.com with questions concerning this matter. Thank you for your consideration.

Sincerely,

Christopher Bisson
Real Estate Consultant



C Squared Systems, LLC
65 Dartmouth Drive, Unit A3
Auburn, NH 03032
(603) 644-2800
support@csquaredsystems.com

Calculated Radio Frequency Emissions



at&t

CT2223

(Bozrah)

133 Gifford Lane, Bozrah, CT 06334

(a.k.a. 131 Gifford Lane)

September 14, 2012

Table of Contents

1. Introduction.....	1
2. FCC Guidelines for Evaluating RF Radiation Exposure Limits.....	1
3. RF Exposure Prediction Methods	2
4. Calculation Results	3
5. Conclusion	4
6. Statement of Certification.....	4
Attachment A: References	5
Attachment B: FCC Limits for Maximum Permissible Exposure (MPE)	6
Attachment C: AT&T Antenna Data Sheets and Electrical Patterns.....	8

List of Tables

Table 1: Carrier Information.....	3
Table 2: FCC Limits for Maximum Permissible Exposure (MPE)	6

List of Figures

Figure 1: Graph of FCC Limits for Maximum Permissible Exposure (MPE).....	7
---	---

1. Introduction

The purpose of this report is to investigate compliance with applicable FCC regulations for the proposed modifications to the existing AT&T antenna arrays mounted on the lattice tower located at 133 Gifford Lane in Bozrah, CT. The coordinates of the tower are 41° 33' 9" N, 72° 9' 2.6" W.

AT&T is proposing the following modifications:

- 1) Install three multi-band (700/850/1900/2100 MHz) antennas (one per sector) for their LTE network.

2. FCC Guidelines for Evaluating RF Radiation Exposure Limits

In 1985, the FCC established rules to regulate radio frequency (RF) exposure from FCC licensed antenna facilities. In 1996, the FCC updated these rules, which were further amended in August 1997 by OET Bulletin 65 Edition 97-01. These new rules include Maximum Permissible Exposure (MPE) limits for transmitters operating between 300 kHz and 100 GHz. The FCC MPE limits are based upon those recommended by the National Council on Radiation Protection and Measurements (NCRP), developed by the Institute of Electrical and Electronics Engineers, Inc., (IEEE) and adopted by the American National Standards Institute (ANSI).

The FCC general population/uncontrolled limits set the maximum exposure to which most people may be subjected. General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure.

Public exposure to radio frequencies is regulated and enforced in units of milliwatts per square centimeter (mW/cm^2). The general population exposure limits for the various frequency ranges are defined in the attached "FCC Limits for Maximum Permissible Exposure (MPE)" in Attachment B of this report.

Higher exposure limits are permitted under the occupational/controlled exposure category, but only for persons who are exposed as a consequence of their employment and who have been made fully aware of the potential for exposure, and they must be able to exercise control over their exposure. General population/uncontrolled limits are five times more stringent than the levels that are acceptable for occupational, or radio frequency trained individuals. Attachment B contains excerpts from OET Bulletin 65 and defines the Maximum Exposure Limit.

Finally, it should be noted that the MPE limits adopted by the FCC for both general population/uncontrolled exposure and for occupational/controlled exposure incorporate a substantial margin of safety and have been established to be well below levels generally accepted as having the potential to cause adverse health effects.

3. RF Exposure Prediction Methods

The emission field calculation results displayed in the following figures were generated using the following formula as outlined in FCC bulletin OET 65:

$$\text{Power Density} = \left(\frac{1.6^2 \times \text{EIRP}}{4\pi \times R^2} \right) \times \text{Off Beam Loss}$$

Where:

EIRP = Effective Isotropic Radiated Power

R = Radial Distance = $\sqrt{(H^2 + V^2)}$

H = Horizontal Distance from antenna in meters

V = Vertical Distance from radiation center of antenna in meters

Ground reflection factor of 1.6

Off Beam Loss is determined by the selected antenna pattern

These calculations assume that the antennas are operating at 100 percent capacity and power, and that all channels are transmitting simultaneously. Obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. The calculations assume even terrain in the area of study and do not take into account actual terrain elevations which could attenuate the signal. As a result, the predicted signal levels reported below are much higher than the actual signal levels will be from the finished modifications.

4. Calculation Results

Table 1 below outlines the power density information for the site. Because the proposed AT&T antennas are directional in nature, the majority of the RF power is focused out towards the horizon. As a result, there will be less RF power directed below the antennas relative to the horizon, and consequently lower power density levels around the base of the tower. Please refer to Attachment C for the vertical pattern of the proposed AT&T antennas. The calculated results for AT&T in Table 1 include a nominal 10 dB off-beam pattern loss to account for the lower relative gain below the antennas.

Carrier	Antenna Height (Feet)	Operating Frequency (MHz)	Number of Trans.	ERP Per Transmitter (Watts)	Power Density (mw/cm ²)	Limit	%MPE
<i>Cingular UMTS</i>	182	880	1	500	0.0054	0.5867	0.93%
<i>Cingular GSM</i>	182	880	4	296	0.0129	0.5867	2.19%
<i>Cingular</i>	182	1900	2	427	0.0093	1.0000	0.93%
Omnipoint	195	1930	2	386	0.0073	1.0000	0.73%
Verizon	162	869	9	264	0.0326	0.5793	5.62%
Verizon	162	1970	3	244	0.0100	1.0000	1.00%
Verizon	162	757	1	711	0.0097	0.5047	1.93%
Sprint	175	1962.5	11	122	0.0158	1.0000	1.58%
AT&T UMTS	182	880	2	565	0.0012	0.5867	0.21%
AT&T UMTS	182	1900	2	875	0.0019	1.0000	0.19%
AT&T LTE	182	734	1	1375	0.0015	0.4893	0.31%
AT&T GSM	182	880	1	283	0.0003	0.5867	0.05%
AT&T GSM	182	1900	4	525	0.0023	1.0000	0.23%
Total							11.84%

Table 1: Carrier Information^{1 2 3}

¹ The existing CSC filing for Cingular should be removed and replaced with the updated AT&T technologies and values provided in Table 1. The power density information for carriers other than AT&T was taken directly from the CSC database dated 7/26/2012. Please note that %MPE values listed are rounded to two decimal points. The total %MPE listed is a summation of each unrounded contribution. Therefore, summing each rounded value may not reflect the total value listed in the table.

² In the case where antenna models are not uniform across all 3 sectors for the same frequency band, the antenna model with the highest gain was used for the calculations to present a worse-case scenario.

³ Antenna height listed for AT&T is in reference to the FDH Engineering Inc. Structural Analysis dated August 27, 2012.


5. Conclusion

The above analysis verifies that emissions from the existing site will be below the maximum power density levels as outlined by the FCC in the OET Bulletin 65 Ed. 97-01. Even when using conservative methods, the cumulative power density from the proposed transmit antennas at the existing facility is well below the limits for the general public. The highest expected percent of Maximum Permissible Exposure at ground level is **11.84% of the FCC limit**.

As noted previously, obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. As a result, the predicted signal levels are more conservative (higher) than the actual signal levels will be from the finished modifications.

6. Statement of Certification

I certify to the best of my knowledge that the statements in this report are true and accurate. The calculations follow guidelines set forth in ANSI/IEEE Std. C95.3, ANSI/IEEE Std. C95.1 and FCC OET Bulletin 65 Edition 97-01.



Daniel L. Goulet
C Squared Systems, LLC

September 14, 2012

Date

Attachment A: References

OET Bulletin 65 - Edition 97-01 - August 1997 Federal Communications Commission Office of Engineering & Technology

ANSI C95.1-1982, American National Standard Safety Levels With Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 300 kHz to 100 GHz. IEEE-SA Standards Board

IEEE Std C95.3-1991 (Reaff 1997), IEEE Recommended Practice for the Measurement of Potentially Hazardous Electromagnetic Fields - RF and Microwave. IEEE-SA Standards Board

Attachment B: FCC Limits for Maximum Permissible Exposure (MPE)

(A) Limits for Occupational/Controlled Exposure⁴

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f ²)*	6
30-300	61.4	0.163	1.0	6
300-1500	-	-	f/300	6
1500-100,000	-	-	5	6

(B) Limits for General Population/Uncontrolled Exposure⁵

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f ²)*	30
30-300	27.5	0.073	0.2	30
300-1500	-	-	f/1500	30
1500-100,000	-	-	1.0	30

f = frequency in MHz * Plane-wave equivalent power density

Table 2: FCC Limits for Maximum Permissible Exposure (MPE)

⁴ Occupational/controlled limits apply in situations in which persons are exposed as a consequence of their employment provided those persons are fully aware of the potential for exposure and can exercise control over their exposure. Limits for occupational/controlled exposure also apply in situations when an individual is transient through a location where occupational/controlled limits apply provided he or she is made aware of the potential for exposure

⁵ General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure







Figure 1: Graph of FCC Limits for Maximum Permissible Exposure (MPE)

Attachment C: AT&T Antenna Data Sheets and Electrical Patterns

<p>700 MHz</p> <p>Manufacturer: Commscope Model #: SBNH-1D6565C Frequency Band: 698-806 MHz Gain: 13.6 dBd Vertical Beamwidth: 8.6° Horizontal Beamwidth: 71° Polarization: ± 45° Size L x W x D: 96.42" x 11.85" x 7.1"</p>	
<p>850 MHz</p> <p>Manufacturer: Powerwave Model #: 7770.00 Frequency Band: 824-896 MHz Gain: 11.5 dBd Vertical Beamwidth: 15° Horizontal Beamwidth: 82° Polarization: Dual Linear ± 45° Size L x W x D: 55.0" x 11.0" x 5.0"</p>	
<p>1900 MHz</p> <p>Manufacturer: Powerwave Model #: 7770.00 Frequency Band: 1850-1990 MHz Gain: 13.4 dBd Vertical Beamwidth: 7° Horizontal Beamwidth: 86° Polarization: Dual Linear ± 45° Size L x W x D: 55.0" x 11.0" x 5.0"</p>	



FDH Engineering, Inc., 6521 Meridien Drive Raleigh, NC 27616, Ph. 919.755.1012

**Structural Analysis for
SBA Network Services, Inc.**

193' Self-Support Tower

**SBA Site Name: Bozrah
SBA Site ID: CT01105-S
New Cingular Site ID: CT2223
New Cingular Site Name: Bozrah East**

FDH Project Number 12-08607E S1

Analysis Results

Tower Components	88.3 %	Sufficient
Foundation	80.4 %	Sufficient

Prepared By:

Joe W Fulk, EI
Project Engineer

Reviewed By:

Christopher M Murphy, PE
President
CT PE License No. 25842

FDH Engineering, Inc.
6521 Meridien Drive
Raleigh, NC 27616
(919) 755-1012
info@fdh-inc.com



August 27, 2012

Prepared pursuant to TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and 2005 Connecticut State Building Code

TABLE OF CONTENTS

EXECUTIVE SUMMARY 3

 Conclusions..... 3

 Recommendations 3

APPURTENANCE LISTING 4

RESULTS 6

GENERAL COMMENTS 7

LIMITATIONS..... 7

APPENDIX 8

EXECUTIVE SUMMARY

At the request of SBA Network Services, Inc., FDH Engineering, Inc. performed a structural analysis of the existing self-supported tower located in Bozrah, CT to determine whether the tower is structurally adequate to support both the existing and proposed loads pursuant to the *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA-222-F* and *2005 Connecticut State Building Code (CSBC)*. Information pertaining to the existing/proposed antenna loading, current tower geometry, the member sizes, soil parameters, and foundation dimensions was obtained from:

- Pirod, Inc. (Eng File No. A-115466) original design drawings dated February 23, 1999
- Jaworski Geotech, Inc. (Project No. C98492G) Geotechnical Evaluation dated December 14, 1998
- SBA Network Services, Inc.

The *basic design wind speed* per the *TIA/EIA-222-F* standards and *2005 CSBC* is 85 mph without ice and 38 mph with 3/4" radial ice. Ice is considered to increase in thickness with height.

Conclusions

With the existing and proposed antennas from New Cingular in place at 182 ft, the tower meets the requirements of the *TIA/EIA-222-F* standards and *2005 CSBC* provided the **Recommendations** listed below are satisfied. Furthermore, provided the foundations were designed and constructed to support the original design reactions (see Pirod, Inc. Eng. File No. A-115466), the foundations should have the necessary capacity to support the existing and proposed loading. For a more detailed description of the analysis of the tower, see the **Results** section of this report.

Our structural analysis has been performed assuming all information provided to FDH Engineering, Inc. is accurate (i.e., the steel data, tower layout, existing antenna loading, and proposed antenna loading) and that the tower has been properly erected and maintained per the original design drawings.

Recommendations

To ensure the requirements of the *TIA/EIA-222-F* standards and *2005 CSBC* are met with the existing and proposed loading in place, we have the following recommendations:

1. The coax must be installed as shown in **Figure 1**.
2. The existing TMAs and diplexers should be installed directly behind the proposed and existing panel antennas.
3. RRU/RRH Stipulation: The proposed equipment may be installed in any configuration determined by the client.

APPURTENANCE LISTING

The proposed and existing antennas with their corresponding cables/coax lines are shown in **Table 1**. *If the actual layout determined in the field deviates from the layout, FDH Engineering, Inc. should be contacted to perform a revised analysis.*

Table 1 - Appurtenance Loading

Existing Loading:

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
195	(9) EMS RR90-17-02DP	(12) 1-5/8"	T-Mobile	193	(1) Low Profile Platform
182	(6) Powerwave 7770 (6) Powerwave LGP21401 TMAs (6) Powerwave LGP21903 Diplexers (6) TMAs	(12) 1-5/8"	New Cingular	182	(3) T-Frames
175	(6) 6'x1' panels (assumed)	(6) 1-5/8"	Sprint	175	(3) T-Frames
162	(3) RFS APX75-866514-CTO (6) Antel LPA-80080/6CF (3) Antel BXA-185090/8CF (6) RFS FD9R6004/2C-3L Diplexers	(12) 1-5/8"	Verizon	162	(3) T-Frames
30	(2) Andrew PC1N0F-0190B-002M E911	(2) 1/2"	T-Mobile	30	Direct Mount

Proposed Loading:

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
182	(3) Andrew SBNH-1D6565C (6) Powerwave 7770 (6) Powerwave LGP21401 TMAs (6) Powerwave LGP21903 Diplexers (6) Ericsson RRUS-11 RRUs (1) Raycap DC6-48-60-18-8F Surge Arrestor	(12) 1-5/8" (1) 3/8" Fiber (2) 3/4" DC Power	New Cingular	182	(3) T-Frames




Figure 1 – Coax Layout

RESULTS

The following yield strength of steel for individual members was used for analysis:

Table 2 - Material Strength

Member Type	Yield Strength
Legs	50 ksi
Bracing	50 ksi & 36 ksi

Table 3 displays the summary of the ratio (as a percentage) of force in the member to their capacities. Values greater than 100% indicate locations where the maximum force in the member exceeds its capacity. **Table 4** displays the maximum foundation reactions.

If the assumptions outlined in this report differ from actual field conditions, FDH Engineering, Inc. should be contacted to perform a revised analysis. Furthermore, as no information pertaining to the allowable twist and sway requirements for the existing or proposed appurtenances was provided, deflection and rotation were not taken into consideration when performing this analysis.

See the **Appendix** for detailed modeling information

Table 3 - Summary of Working Percentage of Structural Components

Section No.	Elevation ft	Component Type	Size	% Capacity*	Pass Fail
T1	193 - 185	Leg	1 3/4	9.4 9.6 (b)	Pass
		Diagonal	7/8	16.7	Pass
		Top Girt	1	9.2	Pass
		Bottom Girt	1	10.7	Pass
T2	185 - 170	Leg	1 3/4	72.5	Pass
		Diagonal	7/8	62.3	Pass
		Top Girt	1	3.8	Pass
		Bottom Girt	1	29.7	Pass
T3	170 - 150	Leg	2 1/4	80.2	Pass
		Diagonal	1	55.9	Pass
		Top Girt	1	32.3	Pass
		Bottom Girt	1	34.4	Pass
		Mid Girt	1" solid	6.5	Pass
T4	150 - 140	Leg	Pirol 105244	87.9	Pass
		Diagonal	L2 1/2x2 1/2x3/16	73.9 88.3 (b)	Pass
T5	140 - 120	Leg	Pirol 105217	83.4	Pass
		Diagonal	L3x3x3/16	47.8 73.0 (b)	Pass
T6	120 - 100	Leg	Pirol 105218	74.4	Pass
		Diagonal	L3x3x3/16	52.9 66.3 (b)	Pass
T7	100 - 80	Leg	Pirol 105219	66.3	Pass
		Diagonal	L3x3x5/16	42.5	Pass
T8	80 - 60	Leg	Pirol 105219	76.0	Pass

Section No.	Elevation ft	Component Type	Size	% Capacity*	Pass Fail
		Diagonal	L3x3x5/16	55.6	Pass
T9	60 - 40	Leg	Pirod 105220	66.5	Pass
		Diagonal	L3x3x5/16	69.9	Pass
T10	40 - 20	Leg	Pirod 105220	73.5	Pass
		Diagonal	L3 1/2x3 1/2x5/16	55.9	Pass
T11	20 - 0	Leg	Pirod 105220	80.0	Pass
		Diagonal	L3 1/2x3 1/2x5/16	76.3	Pass

*Capacities include a 1/3 allowable stress increase for wind.

Table 4 - Maximum Base Reactions

Load Type	Direction	Current Analysis (TIA/EIA-222-F)	Original Design (TIA/EIA-222-F)
Individual Foundation	Horizontal	35 k	---
	Uplift	323 k	405 k
	Compression	361 k	449 k
Overturning Moment	---	5,963 k-ft	7,388 k-ft

GENERAL COMMENTS

This engineering analysis is based upon the theoretical capacity of the structure. It is not a condition assessment of the tower and its foundation. It is the responsibility of SBA Network Services, Inc. to verify that the tower modeled and analyzed is the correct structure (with accurate antenna loading information) modeled. If there are substantial modifications to be made or the assumptions made in this analysis are not accurate, FDH Engineering, Inc. should be notified immediately to perform a revised analysis.


LIMITATIONS

All opinions and conclusions are considered accurate to a reasonable degree of engineering certainty based upon the evidence available at the time of this report. All opinions and conclusions are subject to revision based upon receipt of new or additional/updated information. All services are provided exercising a level of care and diligence equivalent to the standard and care of our profession. No other warranty or guarantee, expressed or implied, is offered. Our services are confidential in nature and we will not release this report to any other party without the client's consent. The use of this engineering work is limited to the express purpose for which it was commissioned and it may not be reused, copied, or distributed for any other purpose without the written consent of FDH Engineering, Inc.

APPENDIX

Section	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11
Legs	SR 1 3/4		SR 2 1/4	A	Pirod 105217	Pirod 105218	Pirod 105219	Pirod 105220		Pirod 105220	
Leg Grade											
Diagonals	SR 7/8		SR 1	B	L3x3x3/16	L3x3x3/16	L3x3x5/16	L3 1/2x3 1/2x5/16		L3 1/2x3 1/2x5/16	
Diagonal Grade	A572-50										
Top Girts	SR 1		SR 1" solid								
Mid Girts	N.A.										
Bottom Girts	SR 1										
Face Width (ft)	4.5			5	6	6	10	14	16	18	18
# Panels @ (ft)	9 @ 2.333333		9 @ 2.34375	1.0	2.2	2.7	4.2	4.3	4.9	5.3	5.4
Weight (K)	0.5	0.8	1.8								

193.0 ft
185.0 ft
170.0 ft
150.0 ft
140.0 ft
120.0 ft
100.0 ft
80.0 ft
60.0 ft
40.0 ft
20.0 ft
0.0 ft



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
(3) RR90-17-02DP w/ Mount Pipe	193	(2) Powerwave 7770 w/ Mount Pipe	182
(3) RR90-17-02DP w/ Mount Pipe	193	(2) 6' Panel w/ Mount Pipe	175
(3) RR90-17-02DP w/ Mount Pipe	193	(2) 6' Panel w/ Mount Pipe	175
Low-Pro Platform Mount	193	(3) T-Frames	175
(1) Lightning Rod	193	(2) 6' Panel w/ Mount Pipe	175
(2) Powerwave 7770 w/ Mount Pipe	182	APX75-866514-CT0 w/Mount Pipe	162
(2) Powerwave 7770 w/ Mount Pipe	182	APX75-866514-CT0 w/Mount Pipe	162
(2) TMA - Powerwave LGP21401	182	(2) LPA-80080/6CF w/ Mount Pipe	162
(2) TMA - Powerwave LGP21401	182	(2) LPA-80080/6CF w/ Mount Pipe	162
(2) TMA - Powerwave LGP21401	182	(2) LPA-80080/6CF w/ Mount Pipe	162
(2) LGP21903 Diplexer	182	Antel BXA-185090/8CF w/ Mount Pipe	162
(2) LGP21903 Diplexer	182	Antel BXA-185090/8CF w/ Mount Pipe	162
(2) LGP21903 Diplexer	182	Antel BXA-185090/8CF w/ Mount Pipe	162
SBNH-1D6565C w/ Mount Pipe	182	(2) Diplexer - RFS FD9R6004/2C-3L	162
SBNH-1D6565C w/ Mount Pipe	182	(2) Diplexer - RFS FD9R6004/2C-3L	162
SBNH-1D6565C w/ Mount Pipe	182	(2) Diplexer - RFS FD9R6004/2C-3L	162
(2) RRUS-11	182	(3) T-Frames	162
(2) RRUS-11	182	APX75-866514-CT0 w/Mount Pipe	162
(2) RRUS-11	182	PC1N0F-0190B-002M	30
DC6-48-60-18-8F Surge Arrestor	182	PC1N0F-0190B-002M	30
(3) T-Frames	182		

SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	Pirod 105244	B	L2 1/2x2 1/2x3/16

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi


TOWER DESIGN NOTES

1. Tower is located in New London County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 88.3%

MAX. CORNER REACTIONS AT BASE:

DOWN: 361 K
SHEAR: 35 K

UPLIFT: -323 K
SHEAR: 31 K



REACTIONS - 85 mph WIND

<p>Tower Analysis</p>	<p>FDH Engineering, Inc. 6521 Meridian Drive Raleigh, NC 27616 Phone: 919-755-1012 FAX: 919-755-1031</p>		<p>Job: Bozrah, CT01105-S</p>		
	<p>Project: 12-08607E S1</p>				
	<p>Client: SBA Network Services, Inc</p>	<p>Code: TIA/EIA-222-F</p>	<p>Drawn by: Joe Fulk</p>	<p>Date: 08/27/12</p>	<p>App'd:</p>
	<p>Path:</p>		<p>Scale: NTS</p>	<p>Dwg No. E-1</p>	

PROJECT INFORMATION

SCOPE OF WORK: TELECOMMUNICATIONS FACILITY UPGRADE (LTE):
 1. INSTALL (3) NEW LTE ANTENNAS, (6) RRH'S, (1) SURGE ARRESTOR,
 (1) FIBER LINE, (2) DC POWER LINES & (1) GPS ANTENNA
 2. INSTALL (1) LTE 6601 CABINET

SITE ADDRESS: 133 GIFFORD LANE
 BOZRAH, CT 06334

LATITUDE: 41.55251 N 41° 33' 09.0" N
 LONGITUDE: 72.15071 W 72° 09' 02.6" W

CURRENT USE: TELECOMMUNICATIONS FACILITY

PROPOSED USE: TELECOMMUNICATIONS FACILITY



SITE NUMBER: CT2223
SITE NAME: BOZRAH

DRAWING INDEX

REV

VICINITY MAP

GENERAL NOTES

- T-1 TITLE SHEET
- GN-1 GENERAL NOTES
- A-1 COMPOUND AND EQUIPMENT PLAN
- A-2 ELEVATION AND ANTENNA PLAN
- A-3 DETAILS
- G-1 PLUMBING DIAGRAM & GROUNDING DETAILS


- 1
- 1
- 1
- 1
- 1
- 1

DIRECTIONS TO SITE:
 START OUT GOING NORTHEAST ON ENTERPRISE DR TOWARD CAPITOL BLVD. TURN LEFT ONTO CAPITOL BLVD. TURN LEFT ONTO WEST ST. MERGE ONTO I-91 N VIA THE RAMP ON THE LEFT TOWARD HARTFORD. 4.4 MI. MERGE ONTO CT-3 N VIA EXIT 25 TOWARD GLASTONBURY. 2.4 MI. MERGE ONTO CT-2 E TOWARD NORWICH. 29.1 MI. TAKE THE CT-163 EXIT, EXIT 23, TOWARD BOZRAH/MONTVILLE. 0.2 MI. STAY STRAIGHT TO GO ONTO BOZRAH ST/CT-163. 0.5 MI. TURN LEFT ONTO GAGER RD. 1.1 MI. TURN LEFT ONTO GIFFORD LN. 1.1 MI. END AT 133 GIFFORD LN BOZRAH, CT 06334.

1. THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF AT&T. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.
2. THE FACILITY IS AN UNMANNED PRIVATE AND SECURED EQUIPMENT INSTALLATION. IT IS ONLY ACCESSED BY TRAINED TECHNICIANS FOR PERIODIC ROUTINE MAINTENANCE AND THEREFORE DOES NOT REQUIRE ANY WATER OR SANITARY SEWER SERVICE. THE FACILITY IS NOT GOVERNED BY REGULATIONS REQUIRING PUBLIC ACCESS PER ADA REQUIREMENTS.
3. CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE AT&T REPRESENTATIVE IN WRITING OF DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

SBA SITE ID: CT01105-5

SITE NAME: BOZRAH



CALL

BEFORE YOU DIG



CALL TOLL FREE 1-800-922-4455 OR DIAL 811

UNDERGROUND SERVICE ALERT



SITE NUMBER: CT2223
SITE NAME: BOZRAH

133 GIFFORD LANE
 BOZRAH, CT 06334
 NEW LONDON COUNTY



500 ENTERPRISE DRIVE, SUITE 3A
 ROCKY HILL, CT 06067

								AT&T	
1	09/17/12	ISSUED FOR PERMITTING	CG	DC	BPH	TITLE SHEET (LTE)			
0	08/01/12	ISSUED FOR REVIEW	RM	DC	BPH	DRAWING NUMBER			
NO. DATE		REVISIONS		BY		CHK		REV	
SCALE: AS SHOWN		DESIGNED BY: DC		DRAWN BY: RM		23.01		T-1	
								1	



GROUNDING NOTES

1. THE SUBCONTRACTOR SHALL REVIEW AND INSPECT THE EXISTING FACILITY GROUNDING SYSTEM AND LIGHTNING PROTECTION SYSTEM (AS DESIGNED AND INSTALLED) FOR STRICT COMPLIANCE WITH THE NEC (AS ADOPTED BY THE AHJ), THE SITE-SPECIFIC (UL, LPI, OR NFPA) LIGHTNING PROTECTION CODE, AND GENERAL COMPLIANCE WITH TELCORDIA AND TIA GROUNDING STANDARDS. THE SUBCONTRACTOR SHALL REPORT ANY VIOLATIONS OR ADVERSE FINDINGS TO THE CONTRACTOR FOR RESOLUTION.
2. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION, AND AC POWER GES'S) SHALL BE BONDED TOGETHER, AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
3. THE SUBCONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR NEW GROUND ELECTRODE SYSTEMS. THE SUBCONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
4. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
5. EACH BTS CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, 6 AWG STRANDED COPPER OR LARGER FOR INDOOR BTS 2 AWG STRANDED COPPER FOR OUTDOOR BTS.
6. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
7. APPROVED ANTIOXIDANT COATINGS (I.E., CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
8. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
11. METAL CONDUIT SHALL BE MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH 6 AWS COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
12. ALL NEW STRUCTURES WITH A FOUNDATION AND/OR FOOTING HAVING 20 FT. OR MORE 1/2" OR GREATER ELECTRICALLY CONDUCTIVE REINFORCING STEEL MUST HAVE IT BONDED TO THE GROUND RING USING AN EXOTHERMIC WELD CONNECTION USING #2 AWG SOLID TINNED COPPER GROUND WIRE, PER NEC 250.50

GENERAL NOTES

1. FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:
 CONTRACTOR - NEXLINK
 SUBCONTRACTOR - GENERAL CONTRACTOR (CONSTRUCTION)
 OWNER - AT&T MOBILITY
 2. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING SUBCONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CONTRACTOR.
 3. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES. SUBCONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS, AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
 4. DRAWINGS PROVIDED HERE ARE NOT TO BE SCALED AND ARE INTENDED TO SHOW OUTLINE ONLY.
 5. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
 6. "KITTING LIST" SUPPLIED WITH THE BID PACKAGE IDENTIFIES ITEMS THAT WILL BE SUPPLIED BY CONTRACTOR. ITEMS NOT INCLUDED IN THE BILL OF MATERIALS AND KITTING LIST SHALL BE SUPPLIED BY THE SUBCONTRACTOR.
 7. THE SUBCONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
 8. IF THE SPECIFIED EQUIPMENT CANNOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE SUBCONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION SPACE FOR APPROVAL BY THE CONTRACTOR.
 9. SUBCONTRACTOR SHALL DETERMINE ACTUAL ROUTING OF CONDUIT, POWER AND T1 CABLES, GROUNDING CABLES AS SHOWN ON THE POWER, GROUNDING AND TELCO PLAN DRAWING. SUBCONTRACTOR SHALL UTILIZE EXISTING TRAYS AND/OR SHALL ADD NEW TRAYS AS NECESSARY. SUBCONTRACTOR SHALL CONFIRM THE ACTUAL ROUTING WITH THE CONTRACTOR.
 10. THE SUBCONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT SUBCONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
 11. SUBCONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
 12. SUBCONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION.
 13. ALL CONCRETE REPAIR WORK SHALL BE DONE IN ACCORDANCE WITH AMERICAN CONCRETE INSTITUTE (ACI) 301.
 14. ANY NEW CONCRETE NEEDED FOR THE CONSTRUCTION SHALL BE AIR-ENTRAINED AND SHALL HAVE 4000 PSI STRENGTH AT 28 DAYS. ALL CONCRETE WORK SHALL BE DONE IN ACCORDANCE WITH ACI 318 CODE REQUIREMENTS.
 15. ALL STRUCTURAL STEEL WORK SHALL BE DETAILED, FABRICATED AND ERECTED IN ACCORDANCE WITH AISC SPECIFICATIONS. ALL STRUCTURAL STEEL SHALL BE ASTM A36 (Fy = 36 ksi) UNLESS OTHERWISE NOTED. PIPES SHALL BE ASTM A53 TYPE E (Fy = 36 ksi). ALL STEEL EXPOSED TO WEATHER SHALL BE HOT DIPPED GALVANIZED. TOUCHUP ALL SCRATCHES AND OTHER MARKS IN THE FIELD AFTER STEEL IS ERECTED USING A COMPATIBLE ZINC RICH PAINT.
 16. CONSTRUCTION SHALL COMPLY WITH UMS SPECIFICATIONS AND "GENERAL CONSTRUCTION SERVICES FOR CONSTRUCTION OF AT&T MOBILITY SITES."
 17. SUBCONTRACTOR SHALL VERIFY ALL EXISTING DIMENSIONS AND CONDITIONS PRIOR TO COMMENCING ANY WORK. ALL DIMENSIONS OF EXISTING CONSTRUCTION SHOWN ON THE DRAWINGS MUST BE VERIFIED. SUBCONTRACTOR SHALL NOTIFY THE CONTRACTOR OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
 18. THE EXISTING CELL SITE IS IN FULL COMMERCIAL OPERATION. ANY CONSTRUCTION WORK BY SUBCONTRACTOR SHALL NOT DISRUPT THE EXISTING NORMAL OPERATION. ANY WORK ON EXISTING EQUIPMENT MUST BE COORDINATED WITH CONTRACTOR. ALSO, WORK SHOULD BE SCHEDULED FOR AN APPROPRIATE MAINTENANCE WINDOW USUALLY IN LOW TRAFFIC PERIODS AFTER MIDNIGHT.
 19. SINCE THE CELL SITE IS ACTIVE, ALL SAFETY PRECAUTIONS MUST BE TAKEN WHEN WORKING AROUND HIGH LEVELS OF ELECTROMAGNETIC RADIATION. EQUIPMENT SHOULD BE SHUTDOWN PRIOR TO PERFORMING ANY WORK THAT COULD EXPOSE THE WORKERS TO DANGER. PERSONAL RF EXPOSURE MONITORS ARE ADVISED TO BE WORN TO ALERT OF ANY DANGEROUS EXPOSURE LEVELS.
 20. APPLICABLE BUILDING CODES:
 SUBCONTRACTOR'S WORK SHALL COMPLY WITH ALL APPLICABLE NATIONAL, STATE, AND LOCAL CODES AS ADOPTED BY THE LOCAL AUTHORITY HAVING JURISDICTION (AHJ) FOR THE LOCATION. THE EDITION OF THE AHJ ADOPTED CODES AND STANDARDS IN EFFECT ON THE DATE OF CONTRACT AWARD SHALL GOVERN THE DESIGN.
 BUILDING CODE: 2003 IBC WITH 2005 CT SUPPLEMENT & 2009 CT AMENDMENTS
 ELECTRICAL CODE: REFER TO ELECTRICAL DRAWINGS
 LIGHTENING CODE: REFER TO ELECTRICAL DRAWINGS
- SUBCONTRACTOR'S WORK SHALL COMPLY WITH THE LATEST EDITION OF THE FOLLOWING STANDARDS:
- AMERICAN CONCRETE INSTITUTE (ACI) 318; BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE;
 - AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) MANUAL OF STEEL CONSTRUCTION, ASD, NINTH EDITION;
 - TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA) 222-F, STRUCTURAL STANDARDS FOR STEEL
 - ANTENNA TOWER AND ANTENNA SUPPORTING STRUCTURES; REFER TO ELECTRICAL DRAWINGS FOR SPECIFIC ELECTRICAL STANDARDS.
- FOR ANY CONFLICTS BETWEEN SECTIONS OF LISTED CODES AND STANDARDS REGARDING MATERIAL, METHODS OF CONSTRUCTION, OR OTHER REQUIREMENTS, THE MOST RESTRICTIVE REQUIREMENT SHALL GOVERN. WHERE THERE IS CONFLICT BETWEEN A GENERAL REQUIREMENT AND A SPECIFIC REQUIREMENT, THE SPECIFIC REQUIREMENT SHALL GOVERN.

ABBREVIATIONS

AGL	ABOVE GRADE LEVEL	G.C.	GENERAL CONTRACTOR	RF	RADIO FREQUENCY
AWG	AMERICAN WIRE GAUGE	MGB	MASTER GROUND BUS		
BCW	BARE COPPER WIRE	MIN	MINIMUM	TBD	TO BE DETERMINED
BTS	BASE TRANSCEIVER STATION	PROPOSED	NEW	TBR	TO BE REMOVED
EXISTING	EXISTING	N.T.S.	NOT TO SCALE	TBRR	TO BE REMOVED AND REPLACED
EG	EQUIPMENT GROUND	REFERENCE		TYP	TYPICAL
EGR	EQUIPMENT GROUND RING	REQUIRED			

1600 OSGOOD STREET
 BUILDING 20 NORTH-1, SUITE 2-101
 N. ANDOVER, MA 01845
 TEL: (978) 557-5553
 FAX: (978) 336-5586


a UniTek GLOBAL SERVICES company
 800 MARSHALL PHELPS ROAD UNIT#: 2A
 WINDSOR, CT 06095



SITE NUMBER: CT2223
SITE NAME: BOZRAH
 133 GIFFORD LANE
 BOZRAH, CT 06334
 NEW LONDON COUNTY

500 ENTERPRISE DRIVE, SUITE 3A
 ROCKY HILL, CT 06067



NO.		DATE	REVISIONS	BY	CHK	APP	SCALE	DESIGNED BY	DRAWN BY	DRAWING NUMBER	REV
1	09/17/12		ISSUED FOR PERMITTING	CG	DC	DPH	AS SHOWN	DC	RM	223.01	1
0	08/01/12		ISSUED FOR REVIEW	RM	DC	DPH					

AT&T
 GENERAL NOTES (LTE)
 DRAWING NUMBER: GN-1





COMPOUND PLAN
SCALE: 3/16" = 1'-0"



EQUIPMENT PLAN
SCALE: 1/2" = 1'-0"



NOTE:
REFER TO THE FINAL RF DATA SHEET FOR FINAL ANTENNA SETTINGS.

NOTE:
AN ANALYSIS FOR THE CAPACITY OF THE EXISTING STRUCTURES TO SUPPORT THE PROPOSED EQUIPMENT SHALL BE DETERMINED PRIOR TO CONSTRUCTION.

Hudson Design Group, LLC
1600 OSGOOD STREET
BUILDING 20 NORTH-1, SUITE 2-101
N. ANDOVER, MA 01845
TEL: (978) 557-5533
FAX: (978) 336-5586



NEXLINK GLOBAL SERVICES
a UniTek GLOBAL SERVICES company
800 MARSHALL PHELPS ROAD UNIT#: 2A
WINDSOR, CT 06095

SITE NUMBER: CT2223
SITE NAME: BOZRAH
133 GIFFORD LANE
BOZRAH, CT 06334
NEW LONDON COUNTY

at&t
500 ENTERPRISE DRIVE, SUITE 3A
ROCKY HILL, CT 06067

				AT&T	
				COMPOUND AND EQUIPMENT PLAN (LTE)	
NO.	DATE	REVISIONS	BY	CHK	REV
1	09/17/12	ISSUED FOR PERMITTING	CG	DC	DP
0	08/01/12	ISSUED FOR REVIEW	RM	DC	DP
SCALE: AS SHOWN			DESIGNED BY: DC	DRAWN BY: RM	
			NO. 2223.01	DRAWING NUMBER	A-1
					1





EXISTING GSM/UMTS ANTENNA PLAN
SCALE: N.T.S.



NOTE:
REFER TO THE FINAL RF DATA SHEET FOR FINAL ANTENNA SETTINGS.

NOTE:
AN ANALYSIS FOR THE CAPACITY OF THE EXISTING STRUCTURES TO SUPPORT THE PROPOSED EQUIPMENT SHALL BE DETERMINED PRIOR TO CONSTRUCTION.

TOP OF EXISTING TOWER
ELEV. 193'-0"± (AGL)
CENTER OF PROPOSED AT&T LTE ANTENNAS, RRHS & SURGE ARRESTOR
ELEV. 182'-0"± (AGL)

PROPOSED RRH WITH UNISTRUT MOUNTED TO EXISTING SECTOR FRAME (TYP. OF 2 PER SECTOR, TOTAL OF 6)
EXISTING GSM/UMTS ANTENNA (TYP. OF 2 PER SECTOR, TOTAL OF 6)
PROPOSED SURGE ARRESTOR DC6-48-60-18-8F MOUNTED TO EXISTING TOWER LEG
EXISTING ANTENNA BY OTHERS (TYP.)
EXISTING LATTICE TOWER
PROPOSED DC POWER & FIBER (TO FOLLOW EXISTING COAX)

PROPOSED LTE ANTENNA MOUNTED TO NEW MOUNTING PIPE AT POSITION 3
ALPHA SECTOR: SBNH-1D6565C
BETA SECTOR: SBNH-1D6565C
GAMMA SECTOR: SBNH-1D6565C
(TYP. OF 1 PER SECTOR, TOTAL OF 3)



PROPOSED LTE ANTENNA PLAN
SCALE: N.T.S.

PROPOSED LTE GPS ANTENNA MOUNTED TO EXISTING ICE BRIDGE (10' MIN. FROM EXISTING GPS ANTENNA)
PROPOSED 3" FLEX CONDUIT FOR DC POWER & FIBER (TO FOLLOW EXISTING COAX ON ICE BRIDGE)
EXISTING AT&T ICE BRIDGE WITH (12) 1-5/8" COAX TO REMAIN
EXISTING AT&T GPS ANTENNA
EXISTING AT&T EQUIPMENT SHELTER
EXISTING VERIZON SHELTER
EXISTING CHAIN LINK FENCE (TYP.)

GROUND LEVEL
ELEV. 0'-0"± (AGL)

WEST ELEVATION
SCALE: 1/16"=1'-0"


Hudson Design Group LLC
1600 OSGOOD STREET
BUILDING 20 NORTH, SUITE 2-101
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586


NEXLINK GLOBAL SERVICES
a UniTek GLOBAL SERVICES company
800 MARSHALL PHELPS ROAD UNIT#: 2A
WINDSOR, CT 06095

SITE NUMBER: CT2223
SITE NAME: BOZRAH
133 GIFFORD LANE
BOZRAH, CT 06334
NEW LONDON COUNTY

at&t
500 ENTERPRISE DRIVE, SUITE 3A
ROCKY HILL, CT 06067

NO.		DATE	REVISIONS	BY	JOB NUMBER	DRAWING NUMBER	REV
1	09/17/12		ISSUED FOR PERMITTING	CG	2223.01	A-2	1
0	08/01/12		ISSUED FOR REVIEW	RM			
SCALE:		DESIGNED BY:		DC	DRAWN BY:		RM






NOTE:
MOUNT PER MANUFACTURER'S SPECIFICATIONS.

DC SURGE SUPPRESSOR DETAIL

SCALE: N.T.S.




NOTE:
MOUNT PER MANUFACTURER'S SPECIFICATIONS.

RRH DETAIL

SCALE: N.T.S.


NOTE:
REFER TO THE FINAL RF DATA SHEET FOR FINAL ANTENNA SETTINGS.

NOTE:
AN ANALYSIS FOR THE CAPACITY OF THE EXISTING STRUCTURES TO SUPPORT THE PROPOSED EQUIPMENT SHALL BE DETERMINED PRIOR TO CONSTRUCTION.





PROPOSED LTE ANTENNA DETAIL

SCALE: N.T.S.



GPS MOUNTING DETAIL

SCALE: N.T.S.



PROPOSED RRH & SURGE ARRESTOR MOUNTING DETAIL

SCALE: N.T.S.



1600 OSGOOD STREET
BUILDING 20 NORTH, SUITE 2-101
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586



a UniTek GLOBAL SERVICES company
800 MARSHALL PHELPS ROAD UNIT#: 2A
WINDSOR, CT 06095


SITE NUMBER: CT2223
SITE NAME: BOZRAH


133 GIFFORD LANE
BOZRAH, CT 06334
NEW LONDON COUNTY



500 ENTERPRISE DRIVE, SUITE 3A
ROCKY HILL, CT 06067

				AT&T	
				DETAILS (LTE)	
NO.	DATE	REVISIONS	BY	CHKD	REV
1	09/17/12	ISSUED FOR PERMITTING	CG	DJR	
0	08/01/12	ISSUED FOR REVIEW	AM	DJR	
SCALE: AS SHOWN			DESIGNED BY: DC	DRAWN BY: RM	
			JOB NUMBER	DRAWING NUMBER	
			2223.01	A-3	1






NOTE:
 1. "DOUBLING UP" OR "STACKING" OF CONNECTION IS NOT PERMITTED.
 2. OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.
 3. CADWELD DOWNLEADS FROM UPPER EGB, LOWER EGB, AND MGB.


TYPICAL GROUND BAR CONNECTION DETAIL

1
 N.T.S.



GROUNDING RISER DIAGRAM

3
 N.T.S.



NOTE:

CONTRACTOR TO CONFIRM ALL PARTS & INSTALL ALL EQUIPMENT TO MANUFACTURER'S RECOMMENDATIONS.

LTE PLUMBING DIAGRAM

2
 N.T.S.

WIRELESS SOLUTIONS INC.			
NO.	REQ.	PART NO.	DESCRIPTION
1	1	HLGB-0420-IS	SOLID GND. BAR (20"x4"x1/4")
2	2		WALL MTG. BRKT.
3	2		INSULATORS
4	4		5/8"-11x1" H.H.C.S.
5	4		5/8 LOCKWASHER


EACH GROUND CONDUCTOR TERMINATING ON ANY GROUND BAR SHALL HAVE AN IDENTIFICATION TAG ATTACHED AT EACH END THAT WILL IDENTIFY ITS ORIGIN AND DESTINATION.

SECTION "P" - SURGE PRODUCERS

- CABLE ENTRY PORTS (HATCH PLATES) (#2)
- GENERATOR FRAMEWORK (IF AVAILABLE) (#2)
- TELCO GROUND BAR
- COMMERCIAL POWER COMMON NEUTRAL/GROUND BOND (#2)
- +24V POWER SUPPLY RETURN BAR (#2)
- 48V POWER SUPPLY RETURN BAR (#2)
- RECTIFIER FRAMES.

SECTION "A" - SURGE ABSORBERS

- INTERIOR GROUND RING (#2)
- EXTERNAL EARTH GROUND FIELD (BURIED GROUND RING) (#2)
- METALLIC COLD WATER PIPE (IF AVAILABLE) (#2)
- BUILDING STEEL (IF AVAILABLE) (#2)



GROUND BAR DETAIL

4
 N.T.S.



1600 OSGOOD STREET
 BUILDING 20 NORTH, SUITE 2-101
 N. ANDOVER, MA 01845
 TEL: (978) 557-5553
 FAX: (978) 336-5586



a UniTek GLOBAL SERVICES company
 800 MARSHALL PHELPS ROAD UNIT#: 2A
 WINDSOR, CT 06095


SITE NUMBER: CT2223
 SITE NAME: BOZRAH

133 GIFFORD LANE
 BOZRAH, CT 06334
 NEW LONDON COUNTY



500 ENTERPRISE DRIVE, SUITE 3A
 ROCKY HILL, CT 06067

NO.	DATE	REVISIONS	BY	JOB NUMBER	DRAWING NUMBER	REV
1	09/17/12	ISSUED FOR PERMITTING	DC	2223.01	G-1	1
0	08/01/12	ISSUED FOR REVIEW	DC			



AT&T

PLUMBING DIAGRAM & GROUNDING DETAILS
 (LTE)