



10 INDUSTRIAL AVENUE,  
SUITE 3  
MAHWAH, NJ 07430  
  
PHONE: 201.684.0055  
FAX: 201.684.0066

July 29, 2020

Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**Re: Notice of Exempt Modification**  
**33 Boardman Road, New Milford CT**  
**Latitude 41.59944444**  
**Longitude -73.4375**  
**T-Mobile site: CTNH362B / Anchor**

Dear Ms. Bachman:

T-Mobile currently maintains (6) antennas at the 140 foot level of the existing 154-foot Monopine tower at 33 Boardman Road in New Milford. The Monopine tower and property is owned by O&G Industries. T-Mobile now intends to swap (3) antennas and add (3) 2500 MHz antennas. The new antennas would be installed at the 140 foot level of the tower.

**Planned Modifications:**

**Remove:**

(3) TMAs  
(12) 1-5/8" coax

**Existing to Remain:**

(3) RFS APXVAARR24\_43-U-NA20 Antennas  
(3) Ericsson 4449 B71 B12 RRH's

**Remove/Replace:**

**Antennas:**

(3) RFS APXV18-209014 (Remove) – APX16DWV-16DWVS-C (Replace)

**Install New:**

**Antennas:**

(3) Air6449 B41- 2500 MHz / 2500 MHz Antennas  
(3) Ericsson 4424 B25 RRU's  
(3) Ericsson 4415 B66A RRU's  
(2) 6x12 hybrid cable

**Ground:**

**Install**

(1) B6160 Equipment Cabinet and (1) 6160 Equipment cabinet

This facility was approved by Docket No. 285 by the Siting Council July 13, 2004, with no record of conditions that would restrict exempt modifications. Therefore, this modification complies with the aforementioned approval. A copy of the original approval is attached.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Mayor Pete Bass of New Milford, and Laura Regan, New Milford Planner.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, T-Mobile respectfully submits that the proposed modifications to the above referenced telecommunications facility constitute an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

*Elizabeth Jamieson*

Elizabeth Jamieson  
Transcend Wireless  
10 Industrial Ave., Suite 3  
Mahwah, New Jersey 07430  
860-605-7808  
EJamieson@TranscendWireless.com

cc:

Peter Bass, New Milford Mayor  
Laura Regan, Planner, New Milford  
O& Industries as tower and land owner

# Exhibit A

## **Original Facility Approval**

# Connecticut Siting Council

## Decisions

<b>DOCKET NO. 285</b> - Sprint Spectrum, L.P. application for a Certificate of Environmental Compatibility and Public Need for the construction, maintenance and operation of a wireless telecommunications facility at 33 Boardman Road, New Milford, Connecticut.	}	Connecticut
	}	Siting
	}	Council
		July 13, 2004

### Decision and Order

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council (Council) finds that the effects associated with the construction, operation, and maintenance of a telecommunications facility including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not disproportionate either alone or cumulatively with other effects when compared to need, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by General Statutes § 16-50k, be issued to Sprint Spectrum, L.P. for the construction, maintenance and operation of a wireless telecommunications facility at 33 Boardman Road, New Milford, Connecticut.

The facility shall be constructed, operated, and maintained substantially as specified in the Council's record in this matter, and subject to the following conditions:

1. The tower shall be constructed as a monopole, no taller than necessary to provide the proposed telecommunications services, sufficient to accommodate the antennas of Sprint Spectrum L.P., Nextel Communications, Inc., and other entities, both public and private, but such tower shall not exceed a height of 150 feet above ground level. The height at the top of the antennas shall not exceed a height of 153 feet above ground level.
2. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plan shall be served on the Town of New Milford, and all parties and intervenors as listed in the service list, and submitted to and approved by the Council prior to the commencement of facility construction. The D&M shall include:
  - a. a final site plan(s) of site development to include specifications for the tower, tower foundation, antennas, equipment building, access road, utility line, and landscaping; and
  - b. construction plans for site clearing, water drainage, and erosion and sedimentation control consistent with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended.
3. Prior to submission of the D&M plan to the Council, the Certificate Holder shall discuss the appropriateness and feasibility of stealth tower designs for this site with the Town. The Town and Certificate Holder shall agree upon the final tower design.
4. The Certificate Holder shall, prior to the commencement of operation, provide the Council worst-case modeling of electromagnetic radio frequency power density of all proposed entities' antennas at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65, August 1997. The Certificate Holder shall ensure a recalculated report of electromagnetic radio frequency power density is submitted to the

Council when circumstances in operation cause a change in power density above the levels calculated and provided pursuant to this Decision and Order.

5. Upon the establishment of any new State or federal radio frequency standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.

6. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.

7. The Certificate Holder shall provide reasonable space on the tower for no compensation for any municipal antennas, provided such antennas are compatible with the structural integrity of the tower.

8. If the facility does not initially provide wireless services within one year of completion of construction or ceases to provide wireless services for a period of one year, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made.

9. Any antenna that becomes obsolete and ceases to function shall be removed within 60 days after such antennas become obsolete and cease to function.

10. Unless otherwise approved by the Council, this Decision and Order shall be void if the facility authorized herein is not operational within one year of the effective date of this Decision and Order or within one year after all appeals to this Decision and Order have been resolved. Any request for extension of this period shall be filed with the Council no later than sixty days prior to expiration date of this Certificate and shall be served on all parties and intervenors, as listed in the service list. Any proposed modifications to this Decision and Order shall likewise be so served.

Pursuant to General Statutes § 16-50p, we hereby direct that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below, and notice of issuance shall be published in the Hartford Courant, the New Milford Spectrum, and the New Milford Times.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of Connecticut State Agencies.

The parties and intervenors to this proceeding are:

<p><b><u>Applicant</u></b></p> <p>Sprint Spectrum, L.P.</p> <p>-</p>	<p><b><u>Its Representative</u></b></p> <p>Thomas J. Regan, Esquire Brown Rudnick Berlack Isreals LLP CityPlace I, 38<sup>th</sup> Floor 185 Asylum Street Hartford, CT 06103-3402</p>
<p><b><u>Intervenor</u></b></p> <p>Nextel Communications, Inc.</p>	<p><b><u>Its Representative</u></b></p> <p>Julie Donaldson Kohler Hurwitz &amp; Sagarin P.O. Box 112 Milford, CT 06460</p>

# Exhibit B

## Property card

# 33 BOARDMAN RD

---

**Location** 33 BOARDMAN RD

**Mblu** 47 / / 73 / /

**Acct#**

**Owner** QUARRY STONE AND GRAVEL  
LLC

**Assessment** \$2,871,680

**Appraisal** \$4,896,500

**PID** 8323

**Building Count** 1

## Current Value

Appraisal			
Valuation Year	Improvements	Land	Total
2015	\$1,205,300	\$3,691,200	\$4,896,500
Assessment			
Valuation Year	Improvements	Land	Total
2015	\$843,710	\$2,027,970	\$2,871,680

## Owner of Record

**Owner** QUARRY STONE AND GRAVEL LLC  
**Co-Owner** % O + G INDUSTRIES  
**Address** 112 WALL ST  
TORRINGTON, CT 06790

**Sale Price** \$0  
**Certificate**  
**Book & Page** 778 / 681  
**Sale Date** 09/11/2003  
**Instrument** 03

## Ownership History

Ownership History					
Owner	Sale Price	Certificate	Book & Page	Instrument	Sale Date
QUARRY STONE AND GRAVEL LLC	\$0		778/ 681	03	09/11/2003
QUARRY STONE AND GRAVEL LLC	\$0		765/ 512	03	07/08/2003
KOVACS ROBERT G + KOVACS PAUL B + KOVACS	\$0		705/ 499	29	05/23/2002
QUARRY STONE AND GRAVEL LLC	\$0		690/ 804	03	01/09/2002
KOVACS ROGER P + PAUL B + ROBERT G	\$0		361/ 142		12/24/1986

## Building Information

### Building 1 : Section 1

**Year Built:** 1989  
**Living Area:** 9,000  
**Replacement Cost:** \$305,640  
**Building Percent** 66  
**Good:**  
**Replacement Cost**  
**Less Depreciation:** \$201,700

Building Attributes	
Field	Description
STYLE	Pre-Eng Whse
MODEL	Ind/Comm
Grade	C
Stories:	1




Occupancy	1
Exterior Wall 1	Pre-finish Metl
Exterior Wall 2	Minimum
Roof Structure	Gable
Roof Cover	Enamel Metal
Interior Wall 1	Minim/Masonry
Interior Wall 2	
Interior Floor 1	Concr-Finished
Interior Floor 2	
Heating Fuel	Oil
Heating Type	Forced Air-Duc
AC Type	None
Bldg Use	Sand+Gravl
Total Rooms	
Total Bedrms	00
Total Baths	0
1st Floor Use:	410I
Heat/AC	NONE
Frame Type	STEEL
Baths/Plumbing	AVERAGE
Ceiling/Wall	NONE
Rooms/Prtns	AVERAGE
Wall Height	20
% Comn Wall	0

## Building Photo



(<http://images.vgsi.com/photos/NewMilfordCTPhotos//\00\01\57>,

## Building Layout



(<http://images.vgsi.com/photos/NewMilfordCTPhotos//Sketches/ε>

**Building Sub-Areas (sq ft)**

**Legend**

Code	Description	Gross Area	Living Area
BAS	First Floor	9,000	9,000
SLB	Slab	9,000	0
		18,000	9,000

**Extra Features**

Extra Features	Legend
No Data for Extra Features	

**Land**

**Land Use**

**Use Code** 410  
**Description** Sand+Gravl  
**Zone** I/R40  
**Neighborhood** C100  
**Alt Land Appr Category** No

**Land Line Valuation**

**Size (Acres)** 342.45  
**Frontage** 0  
**Depth** 0  
**Assessed Value** \$2,027,970  
**Appraised Value** \$3,691,200

**Outbuildings**

Outbuildings						Legend
Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
SHD1	Shed	CB	CindBk/Frame	200 S.F.	\$1,600	1

SHD1	Shed	FR	Frame	400 S.F.	\$3,200	1
LT1	Light (1)			100 Units	\$93,600	1
SCL1	Scale			60 TONS	\$21,600	1
SCL1	Scale			60 TONS	\$21,600	1
SITE	Cell Site Tenant	TW	Tower	4 Units	\$862,000	1


## Valuation History

<b>Appraisal</b>			
<b>Valuation Year</b>	<b>Improvements</b>	<b>Land</b>	<b>Total</b>
2018	\$1,205,300	\$3,691,200	\$4,896,500
2014	\$1,086,200	\$3,691,200	\$4,777,400
2009	\$219,200	\$9,275,200	\$9,494,400

<b>Assessment</b>			
<b>Valuation Year</b>	<b>Improvements</b>	<b>Land</b>	<b>Total</b>
2018	\$843,710	\$2,027,970	\$2,871,680
2014	\$760,340	\$2,010,550	\$2,770,890
2009	\$153,440	\$2,038,320	\$2,191,760

(c) 2016 Vision Government Solutions, Inc. All rights reserved.

### 33 Boardman Rd New Milford CT



**MAP FOR REFERENCE ONLY  
NOT A LEGAL DOCUMENT**

Town of New Milford, CT makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

Geometry updated 5/1/2018  
Data updated 11/19/2018

# Exhibit C

## **Construction Drawings**

# T-Mobile

## WIRELESS COMMUNICATIONS FACILITY

NH362/BOARDMAN\_MP  
 SITE ID: CTNH362B  
 33 BOARDMAN ROAD  
 NEW MILFORD, CT 06776


**T-MOBILE RF CONFIGURATION**  
 67D5998C\_1xAIR+1QP+1OP

- GENERAL NOTES**
- ALL WORK SHALL BE IN ACCORDANCE WITH THE 2015 INTERNATIONAL BUILDING CODE AS MODIFIED BY THE 2018 CONNECTICUT SUPPLEMENT, INCLUDING THE TIA/EIA-222 REVISION "G" STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND SUPPORTING STRUCTURES, 2017 CONNECTICUT FIRE SAFETY CODE, NATIONAL ELECTRICAL CODE AND LOCAL CODES.
  - CONTRACTOR SHALL REVIEW ALL DRAWINGS AND SPECIFICATIONS IN THE CONTRACT DOCUMENT SET. CONTRACTOR SHALL COORDINATE ALL WORK SHOWN IN THE SET OF DRAWINGS. THE CONTRACTOR SHALL PROVIDE A COMPLETE SET OF DRAWINGS TO ALL SUBCONTRACTORS AND ALL RELATED PARTIES. THE SUBCONTRACTORS SHALL EXAMINE ALL THE DRAWINGS AND SPECIFICATIONS FOR THE INFORMATION THAT AFFECTS THEIR WORK.
  - CONTRACTOR SHALL PROVIDE A COMPLETE BUILD-OUT WITH ALL FINISHES, STRUCTURAL, MECHANICAL, AND ELECTRICAL COMPONENTS AND PROVIDE ALL ITEMS AS SHOWN OR INDICATED ON THE DRAWINGS OR IN THE WRITTEN SPECIFICATIONS.
  - CONTRACTOR SHALL FURNISH ALL MATERIAL, LABOR AND EQUIPMENT TO COMPLETE THE WORK AND FURNISH A COMPLETED JOB ALL IN ACCORDANCE WITH LOCAL AND STATE GOVERNING AUTHORITIES AND OTHER AUTHORITIES HAVING LAWFUL JURISDICTION OVER THE WORK.
  - CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND ALL INSPECTIONS REQUIRED AND SHALL ALSO PAY FEES REQUIRED FOR THE GENERAL CONSTRUCTION, PLUMBING, ELECTRICAL, AND HVAC. PERMITS SHALL BE PAID FOR BY THE RESPECTIVE SUBCONTRACTORS.
  - CONTRACTOR SHALL MAINTAIN A CURRENT SET OF DRAWINGS AND SPECIFICATIONS ON SITE AT ALL TIMES AND INSURE DISTRIBUTION OF NEW DRAWINGS TO SUBCONTRACTORS AND OTHER RELEVANT PARTIES AS SOON AS THEY ARE MADE AVAILABLE. ALL OLD DRAWINGS SHALL BE MARKED VOID AND REMOVED FROM THE CONTRACT AREA. THE CONTRACTOR SHALL FURNISH AN "AS-BUILT" SET OF DRAWINGS TO OWNER UPON COMPLETION OF PROJECT.
  - LOCATION OF EQUIPMENT, AND WORK SUPPLIED BY OTHERS THAT IS DIAGRAMMATICALLY INDICATED ON THE DRAWINGS SHALL BE DETERMINED BY THE CONTRACTOR. THE CONTRACTOR SHALL DETERMINE LOCATIONS AND DIMENSIONS SUBJECT TO STRUCTURAL CONDITIONS AND WORK OF THE SUBCONTRACTORS.
  - THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION PROCEDURE AND SEQUENCE AND TO ENSURE THE SAFETY OF THE EXISTING STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THIS INCLUDES THE ADDITION OF WHATEVER SHORING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY.
  - DRAWINGS INDICATE THE MINIMUM STANDARDS, BUT IF ANY WORK SHOULD BE INDICATED TO BE SUBSTANDARD TO ANY ORDINANCES, LAWS, CODES, RULES, OR REGULATIONS BEARING ON THE WORK, THE CONTRACTOR SHALL INCLUDE IN HIS WORK AND SHALL EXECUTE THE WORK CORRECTLY IN ACCORDANCE WITH SUCH ORDINANCES, LAWS, CODES, RULES OR REGULATIONS WITH NO INCREASE IN COSTS.
  - ALL UTILITY WORK SHALL BE IN ACCORDANCE WITH LOCAL UTILITY COMPANY REQUIREMENTS AND SPECIFICATIONS.
  - ALL EQUIPMENT AND PRODUCTS PURCHASED ARE TO BE REVIEWED BY CONTRACTOR AND ALL APPLICABLE SUBCONTRACTORS FOR ANY CONDITION PER MANUFACTURER'S RECOMMENDATIONS. CONTRACTOR TO SUPPLY THESE ITEMS AT NO COST TO OWNER OR CONSTRUCTION MANAGER.
  - ANY AND ALL ERRORS, DISCREPANCIES, AND 'MISSED' ITEMS ARE TO BE BROUGHT TO THE ATTENTION OF THE T-MOBILE CONSTRUCTION MANAGER DURING THE BIDDING PROCESS BY THE CONTRACTOR. ALL THESE ITEMS ARE TO BE INCLUDED IN THE BID. NO 'EXTRA' WILL BE ALLOWED FOR MISSED ITEMS.
  - CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ON-SITE SAFETY FROM THE TIME THE JOB IS AWARDED UNTIL ALL WORK IS COMPLETE AND ACCEPTED BY THE OWNER.
  - CONTRACTOR TO REVIEW ALL SHOP DRAWINGS AND SUBMIT COPY TO ENGINEER FOR APPROVAL. DRAWINGS MUST BEAR THE CHECKER'S INITIALS BEFORE SUBMITTING TO THE CONSTRUCTION MANAGER FOR REVIEW.
  - THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, ANGLES AND EXISTING CONDITIONS AT THE SITE, PRIOR TO FABRICATION AND/OR INSTALLATION OF ANY WORK IN THE CONTRACT AREA.
  - COORDINATION, LAYOUT, FURNISHING AND INSTALLATION OF CONDUITS AND ALL APPURTENANCES REQUIRED FOR PROPER INSTALLATION OF ELECTRICAL AND TELECOMMUNICATION SERVICE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
  - ALL DAMAGE CAUSED TO ANY EXISTING STRUCTURE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR WILL BE HELD LIABLE FOR ALL REPAIRS REQUIRED FOR EXISTING STRUCTURES IF DAMAGED DURING CONSTRUCTION ACTIVITIES.
  - THE CONTRACTOR SHALL CONTACT 'CALL BEFORE YOU DIG' AT LEAST 48 HOURS PRIOR TO ANY EXCAVATIONS AT 1-800-922-4455. ALL UTILITIES SHALL BE IDENTIFIED AND CLEARLY MARKED. CONTRACTOR SHALL MAINTAIN AND PROTECT MARKED UTILITIES THROUGHOUT PROJECT COMPLETION.
  - CONTRACTOR SHALL COMPLY WITH THE OWNER'S ENVIRONMENTAL ENGINEER ON ALL METHODS AND PROVISIONS FOR ALL EXCAVATION ACTIVITIES INCLUDING SOIL DISPOSAL. ALL BACKFILL MATERIALS TO BE PROVIDED BY THE CONTRACTOR.

**SITE DIRECTIONS**

FROM:	TO:
35 GRIFFIN ROAD SOUTH BLOOMFIELD, CT 06002	33 BOARDMAN ROAD NEW MILFORD, CT 06776

- HEAD NORTH ON GRIFFIN ROAD S. TOWARD HARTMAN RD. 0.30 MI.
- TAKE LEFT ONTO DAY HILL RD. 0.61 MI.
- TAKE RIGHT ONTO TUNNIS AVE/CT-189 0.30 MI.
- TAKE LEFT ONTO STATE HIGHWAY 187/CT-187 0.56 MI.
- MERGE ONTO CT-189 N TOWARD TARIFFVILLE/GRANBY 5.14 MI.
- TAKE RIGHT ONTO SALMON BROOK ST/US-202 E/CT-10 0.09 MI.
- TAKE SLIGHT LEFT ONTO N GRANBY RD/ CT-189/CT-20 3.65 MI.
- TAKE LEFT ONTO BARKHAMSTED RD/CT-219 3.78 MI.
- TAKE SLIGHT LEFT ONTO E HARTFORD RD/CT-179/CT-219 2.52 MI.
- TAKE SLIGHT RIGHT ONTO SAVILLE DAM RD 1.69 MI.
- TAKE LEFT ONTO PLEASANT VALLEY RD/CT-181/CT-318 1.46 MI.
- TAKE RIGHT ONTO NEW HARTFORD RD/US-44 W 3.15 MI.
- MERGE ONTO CT-8 S VIA THE RAMP ON THE LEFT 11.19 MI.
- TAKE THE CT-118 EXIT, EXIT 42, TOWARD LITCHFIELD/HARWINTON 0.23 MI.
- TAKE RIGHT ONTO EAST ST/CT-118 4.77 MI.
- TAKE SLIGHT LEFT ONTO EAST ST/US-202 W. 18.55 MI.
- TAKE RIGHT ONTO ELM ST 0.19 MI.
- TAKE RIGHT ONTO RAILROAD ST. 0.02 MI.
- TAKE LEFT ONTO HOUSATONIC AVE 0.75 MI.
- HOUSATONIC AVE BECOMES BOARDMAN RD 0.30 MI.



- PROJECT SUMMARY**
- THE PROPOSED SCOPE OF WORK CONSISTS OF A MODIFICATION TO THE EXISTING UNMANNED TELECOMMUNICATIONS FACILITY INCLUDING THE FOLLOWING:
- INSTALL (1) B160 EQUIPMENT CABINET
  - INSTALL (1) 6160 EQUIPMENT CABINET
  - REMOVE (3) EXISTING PANEL ANTENNAS
  - INSTALL (6) NEW PANEL ANTENNAS
  - INSTALL (6) NEW RRH'S
  - REMOVE ALL EXISTING TMA'S
  - REMOVE ALL EXISTING COAX CABLES
  - INSTALL (2) 6x12 HYBRID CABLES

**PROJECT INFORMATION**

SITE NAME: NH362/BOARDMAN\_MP  
 SITE ID: CTNH362B  
 SITE ADDRESS: 33 BOARDMAN ROAD  
 NEW MILFORD, CT 06776

APPLICANT: T-MOBILE NORTHEAST, LLC  
 35 GRIFFIN ROAD SOUTH  
 BLOOMFIELD, CT 06002

CONTACT PERSON: DAN REID (PROJECT MANAGER)  
 TRANSCEND WIRELESS, LLC  
 (203) 592-8291

ENGINEER OF RECORD: CENTEK ENGINEERING, INC.  
 63-2 NORTH BRANFORD RD.  
 BRANFORD, CT 06405

PROJECT COORDINATES: CARLO F. CENTORE, PE  
 (203) 488-0580 EXT. 122

LATITUDE: 41°-35'-58.3" N  
 LONGITUDE: 73°-26'-15.0" W  
 GROUND ELEVATION: 580'± A.G.L.

SITE COORDINATES AND GROUND ELEVATION REFERENCED FROM GOOGLE EARTH.

**SHEET INDEX**

SHT. NO.	DESCRIPTION	REV.
T-1	TITLE SHEET	0
N-1	GENERAL NOTES AND SPECIFICATIONS	0
C-1	SITE LOCATION PLAN	0
C-2	COMPOUND PLAN AND ELEVATION	0
C-3	EQUIPMENT PLANS	0
C-4	ANTENNA PLANS	0
C-5	TYPICAL EQUIPMENT DETAILS	0
E-1	TYPICAL ELECTRICAL DETAILS	0

PROFESSIONAL ENGINEER SEAL

**T-Mobile**  
 Transcend Wireless

**CENTEK engineering**  
 Centered on Solutions  
 (203) 488-0580  
 (203) 488-8587 Fax  
 63-2 North Branford Road  
 Branford, CT 06405  
 www.CentekEng.com

**T-MOBILE NORTHEAST LLC**  
 WIRELESS COMMUNICATIONS FACILITY  
 NH362/BOARDMAN\_MP  
 SITE ID: CTNH362B  
 33 BOARDMAN ROAD  
 NEW MILFORD, CT 06776

DATE: 07/09/20  
 SCALE: AS NOTED  
 JOB NO. 20074.50

TITLE SHEET

**T-1**  
 Sheet No. 1 of 8

CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION  
 DRAWN BY: CHK'D BY: TJR  
 DATE: 07/23/20  
 REV. 0

**NOTES AND SPECIFICATIONS**

**DESIGN BASIS:**

GOVERNING CODE: 2015 INTERNATIONAL BUILDING (IBC) AS MODIFIED BY THE 2018 CONNECTICUT STATE BUILDING CODE.

- 1. DESIGN CRITERIA:
  - RISK CATEGORY III (BASED ON IBC TABLE 1604.5)
  - NOMINAL DESIGN SPEED (OTHER STRUCTURE): 89 MPH ( $V_{wsd}$ ) (EXPOSURE C/ IMPORTANCE FACTOR 1.0 BASED ON ASCE 7-10).

**SITE NOTES**

1. THE CONTRACTOR SHALL CALL UTILITIES PRIOR TO THE START OF CONSTRUCTION.
2. ACTIVE EXISTING UTILITIES, WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES. THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY, PRIOR TO PROCEEDING, SHOULD ANY UNCOVERED EXISTING UTILITY PRECLUDE COMPLETION OF THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
3. THE AREAS OF THE COMPOUND DISTURBED BY THE WORK SHALL BE RETURNED TO THEIR ORIGINAL CONDITION.
4. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
5. IF ANY FIELD CONDITIONS EXIST WHICH PRECLUDE COMPLIANCE WITH THE DRAWINGS, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER AND SHALL PROCEED WITH AFFECTED WORK AFTER CONFLICT IS SATISFACTORILY RESOLVED.

**GENERAL NOTES**

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE 2015 INTERNATIONAL BUILDING CODE AS MODIFIED BY THE 2018 CONNECTICUT SUPPLEMENT, INCLUDING THE TIA/EIA-222 REVISION "G" "STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND SUPPORTING STRUCTURES." 2017 CONNECTICUT FIRE SAFETY CODE, NATIONAL ELECTRICAL CODE AND LOCAL CODES.
2. CONTRACTOR SHALL REVIEW ALL DRAWINGS AND SPECIFICATIONS IN THE CONTRACT DOCUMENT SET. CONTRACTOR SHALL COORDINATE ALL WORK SHOWN IN THE SET OF DRAWINGS. THE CONTRACTOR SHALL PROVIDE A COMPLETE SET OF DRAWINGS TO ALL SUBCONTRACTORS AND ALL RELATED PARTIES. THE SUBCONTRACTORS SHALL EXAMINE ALL THE DRAWINGS AND SPECIFICATIONS FOR THE INFORMATION THAT AFFECTS THEIR WORK.
3. CONTRACTOR SHALL PROVIDE A COMPLETE BUILD-OUT WITH ALL FINISHES, STRUCTURAL, MECHANICAL, AND ELECTRICAL COMPONENTS AND PROVIDE ALL ITEMS AS SHOWN OR INDICATED ON THE DRAWINGS OR IN THE WRITTEN SPECIFICATIONS.
4. CONTRACTOR SHALL FURNISH ALL MATERIAL, LABOR AND EQUIPMENT TO COMPLETE THE WORK AND FURNISH A COMPLETED JOB ALL IN ACCORDANCE WITH LOCAL AND STATE GOVERNING AUTHORITIES AND OTHER AUTHORITIES HAVING LAWFUL JURISDICTION OVER THE WORK.
5. CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND ALL INSPECTIONS REQUIRED AND SHALL ALSO PAY FEES REQUIRED FOR THE GENERAL CONSTRUCTION, PLUMBING, ELECTRICAL AND HVAC. PERMITS SHALL BE PAID FOR BY THE RESPECTIVE SUBCONTRACTORS.
6. CONTRACTOR SHALL MAINTAIN A CURRENT SET OF DRAWINGS AND SPECIFICATIONS ON SITE AT ALL TIMES AND INSURE DISTRIBUTION OF NEW DRAWINGS TO SUBCONTRACTORS AND OTHER RELEVANT PARTIES AS SOON AS THEY ARE MADE AVAILABLE. ALL OLD DRAWINGS SHALL BE MARKED VOID AND REMOVED FROM THE CONTRACT AREA. THE CONTRACTOR SHALL FURNISH AN 'AS-BUILT' SET OF DRAWINGS TO OWNER UPON COMPLETION OF PROJECT.
7. LOCATION OF EQUIPMENT AND WORK SUPPLIED BY OTHERS THAT IS DIAGRAMMATICALLY INDICATED ON THE DRAWINGS, SHALL BE DETERMINED BY THE CONTRACTOR. THE CONTRACTOR SHALL DETERMINE LOCATIONS AND DIMENSIONS SUBJECT TO STRUCTURAL CONDITIONS AND WORK OF THE SUBCONTRACTORS.
8. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION PROCEDURE AND SEQUENCE, AND TO ENSURE THE SAFETY OF THE EXISTING STRUCTURES AND IT'S COMPONENT PARTS DURING CONSTRUCTION. THIS INCLUDES THE ADDITION OF WHATEVER SHORING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY.
9. DRAWINGS INDICATE THE MINIMUM STANDARDS, BUT IF ANY WORK SHOULD BE INDICATED TO BE SUBSTANDARD TO ANY ORDINANCES, LAWS, CODES, RULES, OR REGULATIONS BEARING ON THE WORK, THE CONTRACTOR SHALL INCLUDE IN HIS WORK AND SHALL EXECUTE THE WORK CORRECTLY IN ACCORDANCE WITH SUCH ORDINANCES, LAWS, CODES, RULES OR REGULATIONS WITH NO INCREASE IN COSTS.
10. ALL UTILITY WORK SHALL BE IN ACCORDANCE WITH LOCAL UTILITY COMPANY REQUIREMENTS AND SPECIFICATIONS.
11. ALL EQUIPMENT AND PRODUCTS PURCHASED ARE TO BE REVIEWED BY CONTRACTOR AND ALL APPLICABLE SUBCONTRACTORS FOR ANY CONDITION PER MFR.'S RECOMMENDATIONS. CONTRACTOR TO SUPPLY THESE ITEMS AT NO COST TO OWNER OR CONSTRUCTION MANAGER.
12. ANY AND ALL ERRORS, DISCREPANCIES, AND "MISSED" ITEMS, ARE TO BE BROUGHT TO THE ATTENTION OF THE SITE OWNER'S CONSTRUCTION MANAGER DURING THE BIDDING PROCESS BY THE CONTRACTOR. ALL THESE ITEMS ARE TO BE INCLUDED IN THE BID. NO 'EXTRA' WILL BE ALLOWED FOR MISSED ITEMS.
13. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ON-SITE SAFETY FROM THE TIME THE JOB IS AWARDED UNTIL ALL WORK IS COMPLETE AND ACCEPTED BY THE OWNER.
14. CONTRACTOR TO REVIEW ALL SHOP DRAWINGS AND SUBMIT COPY TO ENGINEER FOR APPROVAL. DRAWINGS MUST BEAR THE CHECKER'S INITIALS BEFORE SUBMITTING TO THE CONSTRUCTION MANAGER FOR REVIEW.
15. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, ANGLES, AND EXISTING CONDITIONS AT THE SITE, PRIOR TO FABRICATION AND/OR INSTALLATION OF ANY WORK IN THE CONTRACT AREA.
16. COORDINATION, LAYOUT, FURNISHING AND INSTALLATION OF CONDUIT AND ALL APPURTENANCES REQUIRED FOR PROPER INSTALLATION OF ELECTRICAL AND TELECOMMUNICATION SERVICE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
17. ALL DAMAGE CAUSED TO ANY EXISTING STRUCTURE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR WILL BE HELD LIABLE FOR ALL REPAIRS REQUIRED FOR EXISTING STRUCTURES IF DAMAGED DURING CONSTRUCTION ACTIVITIES.
18. THE CONTRACTOR SHALL CONTACT "DIG SAFE" (DIAL 811) AT LEAST 48 HOURS PRIOR TO ANY EXCAVATIONS. ALL UTILITIES SHALL BE IDENTIFIED AND CLEARLY MARKED. CONTRACTOR SHALL MAINTAIN AND PROTECT MARKED UTILITIES THROUGHOUT PROJECT COMPLETION.
19. CONTRACTOR SHALL COMPLY WITH OWNER'S ENVIRONMENTAL ENGINEER ON ALL METHODS AND PROVISIONS FOR ALL EXCAVATION ACTIVITIES INCLUDING SOIL DISPOSAL. ALL BACKFILL MATERIALS TO BE PROVIDED BY THE CONTRACTOR.
20. THE COUNTY/CITY/TOWN WILL MAKE PERIODIC FIELD OBSERVATION AND INSPECTIONS TO MONITOR THE INSTALLATION, MATERIALS, WORKMANSHIP AND EQUIPMENT INCORPORATED INTO THE PROJECT TO ENSURE COMPLIANCE WITH THE DESIGN PLANS, SPECIFICATIONS, CONTRACT DOCUMENTS AND APPROVED SHOP DRAWINGS.
21. THE COUNTY/CITY/TOWN MUST BE NOTIFIED (2) WORKING DAYS PRIOR TO CONCEALMENT/BURIAL OF ANY SYSTEM OR MATERIAL THAT WILL PREVENT THE DIRECT INSPECTION OF MATERIALS, METHODS OR WORKMANSHIP. EXAMPLES OF THESE PROCESSES ARE BACKFILLING A GROUND RING OR TOWER FOUNDATION, POURING TOWER FOUNDATIONS, BURYING GROUND RODS, PLATES OR GRIDS, ETC. THE CONTRACTOR MAY PROCEED WITH THE SCHEDULED PROCESS (2) WORKING DAYS AFTER PROVIDING NOTICE UNLESS NOTIFIED OTHERWISE BY THE COUNTY/CITY/TOWN.

PROFESSIONAL ENGINEER SEAL	CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION
	TJR
	DATE
	07/23/20
	REV.
<p>Centred on Solutions</p> <p>(203) 488-0580 (203) 488-8587 Fax 63-2 North Branford Road Branford, CT 06405 www.CentekEng.com</p>	
<p>T-MOBILE NORTHEAST LLC WIRELESS COMMUNICATIONS FACILITY</p> <p>NH362/BOARDMAN_MP SITE ID: CTNH362B 33 BOARDMAN ROAD NEW MILFORD, CT 06776</p>	
DATE: 07/09/20	
SCALE: AS NOTED	
JOB NO. 20074.50	
GENERAL NOTES AND SPECIFICATIONS	
N-1	
Sheet No. 2 of 8	

NOTE:  
ALL COAX LENGTHS TO BE MEASURED  
AND VERIFIED IN FIELD BEFORE ORDERING

ANTENNA SCHEDULE								
SECTOR	EXISTING/PROPOSED	ANTENNA	SIZE (INCHES) (L x W x D)	ANTENNA & HEIGHT	AZIMUTH	(E/P) RRU (QTY)	(E/P) TMA (QTY)	(QTY) PROPOSED COAX (LENGTH)
A1	PROPOSED	RFS (APX16DWV-16DWVS-C)	55.9 x 13.3 x 3.15	140'	60°	(P) RADIO 4415 B66A (1)		(1) 6x12 HYBRID CABLE (±160')
A2	PROPOSED	ERICSSON (AIR6449 B41)	33.1 x 20.6 x 8.6	140'	60°			
A3	EXISTING	RFS (APXVAARR24_43-U-NA20)	95.9 x 24 x 8.7	140'	60°	(E) RADIO 4449 B71 (1), (P) RADIO 4424 B25 (1)		
B1	PROPOSED	RFS (APX16DWV-16DWVS-C)	55.9 x 13.3 x 3.15	140'	180°	(P) RADIO 4415 B66A (1)		(1) 6x12 HYBRID CABLE (±160')
B2	PROPOSED	ERICSSON (AIR6449 B41)	33.1 x 20.6 x 8.6	140'	180°			
B3	EXISTING	RFS (APXVAARR24_43-U-NA20)	95.9 x 24 x 8.7	140'	180°	(E) RADIO 4449 B71 (1), (P) RADIO 4424 B25 (1)		
C1	PROPOSED	RFS (APX16DWV-16DWVS-C)	55.9 x 13.3 x 3.15	140'	300°	(P) RADIO 4415 B66A (1)		
C2	PROPOSED	ERICSSON (AIR6449 B41)	33.1 x 20.6 x 8.6	140'	300°			
C3	EXISTING	RFS (APXVAARR24_43-U-NA20)	95.9 x 24 x 8.7	140'	300°	(E) RADIO 4449 B71 (1), (P) RADIO 4424 B25 (1)		



1 SITE LOCATION PLAN  
C-1 SCALE: 1" = 200'



PROFESSIONAL ENGINEER SEAL

PROFESSIONAL ENGINEER SEAL

T-Mobile  
Transcend Wireless

CENTER engineering  
Centered on Solutions  
(203) 488-0380  
(203) 488-8387 Fax  
63-2 North Branford Road  
Branford, CT 06405  
www.CenterEng.com

T-MOBILE NORTHEAST LLC  
WIRELESS COMMUNICATIONS FACILITY  
NH362/BOARDMAN\_MP  
SITE ID: CTNH362B  
33 BOARDMAN ROAD  
NEW MILFORD, CT 06776

DATE: 07/09/20  
SCALE: AS NOTED  
JOB NO. 20074.50

SITE LOCATION PLAN

C-1

Sheet No. 3 of 8

REV. DATE DRAWN BY CHECK'D BY DESCRIPTION

0 07/23/20 RJS TJR CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION




STRUCTURAL COMPLIANCE

ANTENNA MOUNTS



A STRUCTURAL ANALYSIS OF THE ANTENNA FRAMES WAS PERFORMED FOR THE PROPOSED EQUIPMENT INSTALLATION AND THEY WERE FOUND TO BE STRUCTURALLY SUFFICIENT TO ACCOMMODATE THE PROPOSED LOADING.

REFER TO THE STRUCTURAL ANALYSIS REPORT PREPARED BY CENTEK ENGINEERING (PROJECT # 20074.50) DATED 07/08/20 FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

NOTE: NO EQUIPMENT SHALL BE INSTALLED ON THE HOSTING STRUCTURE WITHOUT A PASSING STRUCTURAL ANALYSIS REPORT AND CONTRACTOR PRIOR CONFIRMATION THAT ANY AND ALL REQUISITE MODIFICATIONS HAVE BEEN COMPLETED.




**2** PROPOSED TOWER ELEVATION  
C-2 SCALE: 1" = 10'




**1** COMPOUND PLAN - PROPOSED  
C-2 SCALE: 1/8" = 1' APPROXIMATE NORTH




PROFESSIONAL ENGINEER SEAL			TJR	R.T.S.	DATE	DRAWN BY	CHECK'D BY
			0	07/23/20	REV.	DESCRIPTION	ISSUED FOR CONSTRUCTION
(203) 488-0380 (203) 488-8387 Fax 63-2 North Branford Road Branford, CT 06405 www.CentekEng.com							
<b>T-MOBILE NORTHEAST LLC</b> WIRELESS COMMUNICATIONS FACILITY <b>NH362/BOARDMAN_MP</b> <b>SITE ID: CTNH362B</b> 33 BOARDMAN ROAD NEW MILFORD, CT 06776							
DATE: 07/09/20							
SCALE: AS NOTED							
JOB NO. 20074.50							
COMPOUND PLAN AND ELEVATION							
C-2							
Sheet No. 4 of 8							




**1**  
C-3 **EXISTING EQUIPMENT PLAN**  
SCALE: 3/8" = 1'  
APPROXIMATE NORTH




**2**  
C-3 **PROPOSED EQUIPMENT PLAN**  
SCALE: 3/8" = 1'  
APPROXIMATE NORTH

PROFESSIONAL ENGINEER SEAL				DATE	DRAWN BY	CHK'D BY	DESCRIPTION
				07/23/20	RJS	TJR	CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION
				0			
				07/09/20			
				AS NOTED			
				20074.50			
EQUIPMENT PLANS							
<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: left;"> <p><b>T-MOBILE NORTHEAST LLC</b> WIRELESS COMMUNICATIONS FACILITY <b>NH362/BOARDMAN_MP</b> <b>SITE ID: CTNH362B</b> 33 BOARDMAN ROAD NEW MILFORD, CT 06776</p> </div> <div style="text-align: right;">  </div> </div>							
 <p>(203) 488-0580 (203) 488-8587 Fax 63-2 North Branford Road Branford, CT 06405 www.CentekEng.com</p>							
<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: left;"> <p><b>C-3</b></p> </div> <div style="text-align: right;"> <p>Sheet No. 5 of 8</p> </div> </div>							




**1** EXISTING ANTENNA MOUNTING CONFIGURATION  
 C-4 SCALE: 1/2" = 1' 140' ELEVATION TRUE NORTH




**3** PROPOSED ANTENNA MOUNTING CONFIGURATION  
 C-4 SCALE: 1/2" = 1' 140' ELEVATION TRUE NORTH

NOTE:  
 PAINT PROPOSED ANTENNAS AND APPURTENANCES TO MATCH EXISTING.





**2** ANTENNA ELEVATION - EXISTING  
 C-4 SCALE: 1/2" = 1'



**4** ANTENNA ELEVATION - PROPOSED  
 C-4 SCALE: 1/2" = 1'

REV.	DATE	BY	CHK'D BY	DESCRIPTION
0	07/23/20	RFS	TJR	CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION



**CENTEK** engineering  
 Centered on Solutions  
 (203) 489-0380  
 (203) 489-8587 Fax  
 63-2 North Branford Road  
 Branford, CT 06405  
 www.CentekEng.com


T-MOBILE NORTHEAST LLC  
 WIRELESS COMMUNICATIONS FACILITY  
**NH362/BOARDMAN\_MP**  
**SITE ID: CTNH362B**  
 33 BOARDMAN ROAD  
 NEW MILFORD, CT 06776

DATE: 07/09/20  
 SCALE: AS NOTED  
 JOB NO. 20074.50

ANTENNA PLANS

**C-4**


Sheet No. 6 of 8



**NOTES:**

1. T-MOBILE SHALL SUPPLY RRU, AND RRU POLE-MOUNTING BRACKET. CONTRACTOR SHALL SUPPLY POLE/PIPE AND INSTALL ALL MOUNTING HARDWARE INCLUDING ERICSSON RRU POLE-MOUNTING BRACKET. CONTRACTOR SHALL INSTALLS RRU AND MAKES CABLE TERMINATIONS.
2. NO PAINTING OF THE RRU OR SOLAR SHIELD IS ALLOWED.

**1 TYPICAL RRUS MOUNTING DETAILS**  
C-5 SCALE: NOT TO SCALE



ALPHA/BETA/GAMMA ANTENNA		
EQUIPMENT	DIMENSIONS	WEIGHT
MAKE: ERICSSON MODEL: AIR6449 B41	33.1"L x 20.6"W x 8.6"D	±104 LBS.
MAKE: RFS MODEL: APX16DW-16DWS-C	55.9"L x 13.3"W x 3.15"D	±39.6 LBS.

**NOTES:**  
1. CONTRACTOR TO COORDINATE FINAL EQUIPMENT MODEL SELECTION WITH T-MOBILE CONSTRUCTION MANAGER PRIOR TO ORDERING.

**2 PROPOSED ANTENNA DETAIL**  
C-5 SCALE: NOT TO SCALE



RRU (REMOTE RADIO UNIT)			
EQUIPMENT	DIMENSIONS	WEIGHT	CLEARANCES
MAKE: ERICSSON MODEL: RADIO 4415 B66A	14.9"L x 13.2"W x 5.4"D	±46 LBS.	BEHIND ANT.: 8" MIN. BELOW ANT.: 20" MIN. BELOW RRU: 16" MIN.
MAKE: ERICSSON MODEL: RADIO 4424 B25	16.5"L x 13.2"W x 9.6"D	±46 LBS.	BEHIND ANT.: 8" MIN. BELOW ANT.: 20" MIN. BELOW RRU: 16" MIN.

**NOTES:**  
1. CONTRACTOR TO COORDINATE FINAL EQUIPMENT MODEL SELECTION WITH T-MOBILE CONSTRUCTION MANAGER PRIOR TO ORDERING.

**3 PROPOSED RRU DETAIL**  
C-5 SCALE: NOT TO SCALE



EQUIPMENT CABINET		
EQUIPMENT	DIMENSIONS	WEIGHT
MAKE: ERICSSON MODEL: ENCLOSURE 6160	62.0"H x 26.0"W x 26.0"D	±1200 LBS



**4 ENCLOSURE 6160 (OUTDOOR)**  
C-5 SCALE: NOT TO SCALE



EQUIPMENT CABINET		
EQUIPMENT	DIMENSIONS	WEIGHT
MAKE: ERICSSON MODEL: BATTERY CABINET B160	62.0"H x 26.0"W x 26.0"D	±1883 LBS

**5 BATTERY CABINET DETAIL**  
C-5 NOT TO SCALE

REV.	DATE	BY	CHK'D	DESCRIPTION
0	07/23/20	RFS	TJR	CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION




**CENTEX** engineering  
Centered on Solutions™  
(203) 488-0580  
(203) 488-8587 Fax  
63-2 North Branford Road  
Branford, CT 06405  
www.CentexEng.com

**T-MOBILE NORTHEAST LLC**  
WIRELESS COMMUNICATIONS FACILITY  
**NH362/BOARDMAN\_MP**  
SITE ID: CTNH362B  
33 BOARDMAN ROAD  
NEW MILFORD, CT 06776


DATE: 07/09/20  
SCALE: AS NOTED  
JOB NO. 20074.50

TYPICAL EQUIPMENT DETAILS

**C-5**  
Sheet No. 7 of 8




**1 TYPICAL ANTENNA/RRU GROUNDING DETAILS**  
E-1 SCALE: NOT TO SCALE




**NOTES:**

1. BOND COAXIAL CABLE GROUND KITS TO EACH OWNER'S GROUND BAR ALONG ENTIRE COAX RUN FROM ANTENNA TO SHELTER.
2. BOND ALL EQUIPMENT TO GROUND PER NEC AND MANUFACTURERS SPECIFICATIONS.
3. DETAIL IS TYPICAL FOR ALL ANTENNA SECTORS, INCLUDING GPS ANTENNA.

**2 TYPICAL ANTENNA GROUNDING DETAIL**  
E-1 SCALE: NOT TO SCALE



**3 PROPOSED PLUMBING DIAGRAM**  
E-1 SCALE: NOT TO SCALE




**GROUNDING SCHEMATIC NOTES**

- 1 #2 AWG
- 2 #6 AWG

**GENERAL NOTES:**

1. ALL SURGE SUPPRESSION EQUIPMENT SHALL BE BONDED TO GROUND PER MANUFACTURER'S SPECIFICATIONS
2. UNLESS OTHERWISE NOTED OR REQUIRED BY CODE, GROUND CONDUCTORS SHOWN SHALL BE #2 AWG (SOLID TINNED BCW - EXTERIOR; STRANDED GREEN INSULATED - INTERIOR).
3. ALL SECTOR GROUND BARS SHALL BE BONDED TOGETHER WITH #2 AWG SOLID TINNED BCW.
4. BOND ALL EQUIPMENT CABINETS AND BATTERY CABINETS TO GROUND PER MANUFACTURER'S SPECIFICATIONS.
5. COORDINATE ALL ROOF MOUNTED EQUIPMENT WITH OWNER.
6. ALL ROOF MOUNTED AMPLIFIERS AND ASSOCIATED EQUIPMENT SHALL BE BONDED TO THE SECTOR GROUND BAR PER MANUFACTURER'S SPECIFICATIONS.
7. ALL GROUNDING SHALL BE IN ACCORDANCE WITH NEC AND OWNER'S REQUIREMENTS.

**4 TYPICAL GROUNDING SCHEMATIC DETAIL**  
E-1 SCALE: NOT TO SCALE



**5 ELECTRICAL POWER RISER DIAGRAM**  
E-1 SCALE: NOT TO SCALE

REV.	DATE	BY	CHK'D	DESCRIPTION
0	07/23/20	RTS	TJR	CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION

PROFESSIONAL ENGINEER SEAL

**T-Mobile**

Transcend Wireless

**CENTER** engineering  
Centered on Solutions  
(203) 488-0380  
(203) 488-8587 Fax  
63-2 North Branford Road  
Branford, CT 06405  
www.CenterEng.com

**T-MOBILE NORTHEAST LLC**  
WIRELESS COMMUNICATIONS FACILITY  
NH362/BOARDMAN\_MP  
SITE ID: CTNH362B  
33 BOARDMAN ROAD  
NEW MILFORD, CT 06776

DATE: 07/09/20  
SCALE: AS NOTED  
JOB NO. 20074.50

TYPICAL ELECTRICAL DETAILS

**E-1**

Sheet No. 8 of 8

# Exhibit D

## **Structural Analysis Report**

**Structural Analysis Report**

*153-ft Existing EEI Monopole*

*Proposed T-Mobile  
Antenna Upgrade*


*T-Mobile Site Ref: CTNH362B*

*33 Boardman Road  
New Milford, CT*

*Centek Project No. 20074.50*

*Date: July 8, 2020*

*Max Stress Ratio = 87.9%*



**Prepared for:**  
T-Mobile USA  
35 Griffin Road  
Bloomfield, CT 06002

# **Table of Contents**

## **SECTION 1 - REPORT**

- INTRODUCTION
- ANTENNA AND APPURTENANCE SUMMARY
- PRIMARY ASSUMPTIONS USED IN THE ANALYSIS
- ANALYSIS
- TOWER LOADING
- TOWER CAPACITY
- FOUNDATION AND ANCHORS
- CONCLUSION

## **SECTION 2 – CONDITIONS & SOFTWARE**

- STANDARD ENGINEERING CONDITIONS
- GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM

## **SECTION 3 – CALCULATIONS**

- tnxTower INPUT/OUTPUT SUMMARY
- tnxTower DETAILED OUTPUT
- ANCHOR BOLT AND BASE PLATE ANALYSIS
- FOUNDATION ANALYSIS

## **SECTION 4 – REFERENCE MATERIAL**

- RF DATA SHEET



## *I n t r o d u c t i o n*

The purpose of this report is to summarize the results of the non-linear, P- $\Delta$  structural analysis of the antenna upgrade proposed by T-Mobile on the existing monopine (tower) located in New Milford, CT.

The host tower is a 153-ft tall, four-section, eighteen sided, tapered monopine, originally designed and manufactured by Engineered Endeavors Inc., job no; 13200, dated March 2, 2005. The tower geometry, structure member sizes and foundation system information were obtained from a previous structural report prepared by Centek job no. 19027.65 dated May 14, 2019. Antenna and appurtenance information were obtained from the aforementioned structural report and a RF data sheet.

The tower is made up of four (4) tapered vertical sections consisting of A572-65 pole sections. The vertical tower sections are slip joint connected. The diameter of the pole (flat-flat) is 25.25-in at the top and 61.0-in at the base.

## *A n t e n n a   a n d   A p p u r t e n a n c e   S u m m a r y*

The existing, proposed and future loads considered in this analysis consist of the following:

- **MOTOROLA (EXISTING):**  
Antennas: One (1) RFI BA40-41 Omni-directional whip antenna, one (1) Radiowave HP2-4.7 microwave dish and one (1) Radiowave HP3-4.7 microwave dish pipe mounted on one (1) universal tri-bracket to the top of the tower.  
Coax Cables: Three (3) 7/8"  $\varnothing$  coax cables running within the interior of the existing tower.
- **SPRINT (EXISTING):**  
Antennas: Three (3) Commscope DT465B-2XR panel antennas, three (3) RFS APXVSP18-C-A20 panel antennas, three (3) ALU 1900 MHz RRHs, six (6) ALU 800 MHz RRHs and three (3) 2500 MHz RRHs mounted on three (3) existing 10-ft T-Arms with a RAD center elevation of 150-ft above grade.  
Coax Cables: Nine (9) 1-5/8"  $\varnothing$  coax cables and four (4) 1-1/4"  $\varnothing$  Hybriflex cables running within the interior of the existing tower.
- **VERIZON (EXISTING):**  
Antennas: Three (3) Antel BXA-70063-6CF panel antennas, six (6) Andrew HBXX-6517DS panel antennas, three (3) Andrew LNX-8513DS panel antennas, three (3) Alcatel-Lucent RRH-2x60-AWS remote radio heads, six (6) RFS FD9R6004/2C-3L Diplexers and one (1) RFD DB-T1-6Z-8AB-0Z main distribution box mounted on three (3) existing 10-ft T-Arms with a RAD center elevation of 130-ft above grade.  
Coax Cables: Twelve (12) 1-5/8"  $\varnothing$  coax cables and one (1) 1-5/8"  $\varnothing$  fiber cable running within the interior of the existing tower.

- **AT&T (EXISTING):**  
Antennas: Two (2) Kathrein 80010965 panel antennas, one (1) Kathrein 80010966 panel antenna, three (3) Powerwave 7770 panel antennas, six (6) HPA-65R-BUU-H6 panel antennas, three (3) Powerwave LGP21401 TMAs, three (3) Ericsson RRUS-11 Remote Radio Heads, six (6) Ericsson RRUS-32 Remote Radio Heads, three (3) Ericsson 4426 B66 Remote Radio Heads, six (6) Ericsson 4478 Remote Radio Heads and three (3) Raycap DC6-48-60-18-8F surge arrestor mounted on three (3) existing 10-ft T-Arms with a RAD center elevation of 120-ft above grade.  
Coax Cables: Twelve (12) 1-5/8" Ø coax cables, one (1) fiber cable and two (2) dc control cables running within the interior of the existing tower.
- **T-MOBILE (Existing to Remain):**  
Antennas: Three (3) RFS APXVAARR24\_43 panel antennas and three (3) Ericsson 4449 remote radio heads mounted on three (3) existing 10-ft T-Arms w/ stabilizer kits with a RAD center elevation of 140-ft above grade.  
Coax Cables: One (1) 6x12 fiber cable running on the inside of the existing tower.
- **T-MOBILE (Existing to Remove):**  
Antennas: Three (3) RFS APXV18-209014 panel antennas and three (3) TMAs mounted on three (3) existing 10-ft T-Arms w/ stabilizer kits with a RAD center elevation of 140-ft above grade.  
Coax Cables: Twelve (12) 1-5/8" Ø coax cables running on the inside of the existing tower.
- **T-MOBILE (Proposed):**  
Antennas: **Three (3) RFS APX16DWV-16DWVS panel antennas, three (3) Ericsson AIR6449 panel antennas, three (3) Ericsson 4449 remote radio units, three (3) Ericsson 4415 remote radio units, three (3) Ericsson 4424 remote radio units mounted on three (3) existing 10-ft T-Arms w/ stabilizer kits with a RAD center elevation of 140-ft above grade.**  
Coax Cables: **Two (2) 6x12 fiber cables running on the inside of the existing tower.**

### *Primary Assumptions Used in the Analysis*

- The tower structure's theoretical capacity not including any assessment of the condition of the tower.
- The tower carries the horizontal and vertical loads due to the weight of antennas, ice load and wind.
- Tower is properly installed and maintained.
- Tower is in plumb condition.
- Tower loading for antennas and mounts as listed in this report.
- All bolts are appropriately tightened providing the necessary connection continuity.
- All welds are fabricated with ER-70S-6 electrodes.
- All members are assumed to be as specified in the original tower design documents or reinforcement drawings.
- All members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
- All member protective coatings are in good condition.
- All tower members were properly designed, detailed, fabricated, installed and have been properly maintained since erection.
- Any deviation from the analyzed antenna loading will require a new analysis for verification of structural adequacy.
- All existing coax cables to be installed as indicated in this report.

## A n a l y s i s

The existing tower was analyzed using a comprehensive computer program entitled tnxTower. The program analyzes the tower, considering the worst case loading condition. The tower is considered as loaded by concentric forces along the tower, and the model assumes that the tower members are subjected to bending, axial, and shear forces.

The existing tower was analyzed for the controlling basic wind speed (3-second gust) with no ice and the applicable wind and ice combination to determine stresses in members as per guidelines of TIA-222-G-2005 entitled “Structural Standard for Antenna Support Structures and Antennas”, the American Institute of Steel Construction (AISC) and the Manual of Steel Construction; Load and Resistance Factor Design (LRFD).

The controlling wind speed is determined by evaluating the local available wind speed data as provided in Appendix N of the CSBC<sup>1</sup> and the wind speed data available in the TIA-222-G-2005 Standard.

## T o w e r L o a d i n g

Tower loading was determined by the basic wind speed as applied to projected surface areas with modification factors per TIA-222-G-2005, gravity loads of the tower structure and its components, and the application of 1.00” radial ice on the tower structure and its components.

Basic Wind Speed:	New Milford; v = 89 mph (3 second gust)	<i>[Appendix N of the 2018 CT Building Code]</i>
-------------------	---	--

Load Cases:	<u>Load Case 1</u> ; 89 mph wind speed w/ no ice plus gravity load – used in calculation of tower stresses and rotation.	<i>[Appendix N of the 2018 CT Building Code]</i>
-------------	--	--

	<u>Load Case 2</u> ; 40 mph wind speed w/ 1.00” radial ice plus gravity load – used in calculation of tower stresses.	<i>[Annex B of TIA-222-G-2005]</i>
--	---	------------------------------------

---

<sup>1</sup> The 2015 International Building Code as amended by the 2018 Connecticut State Building Code (CSBC).

## Tower Capacity

- Calculated stresses were found to be within allowable limits. This tower was found to be at **87.9%** of its total capacity.

Tower Section	Elevation	Stress Ratio (percentage of capacity)	Result
Pole Shaft (L2)	89.16'-134.83'	87.9%	<b>PASS</b>

## Foundation and Anchors

The existing foundation consists of a 7.5-ft square x 3.5-ft long reinforced concrete pier on a 32.0-ft square x 4.0-ft thick reinforced concrete pad. The sub-grade conditions used in the analysis of the existing foundation were obtained from the aforementioned structural report prepared by Centek. The base of the tower is connected to the foundation by means of (28) 2.25"Ø, ASTM A615-75 anchor bolts embedded approximately 7-ft into the concrete foundation structure.

- The tower base reactions developed from the governing Load Case 1 were used in the verification of the foundation and its anchors:

Location	Vector	Proposed Reactions
Base	Shear	68 kips
	Compression	79 kips
	Moment	7980 kip-ft

- The foundation was found to be within allowable limits.

Foundation	Design Limit	TIA-222-G Section 9.4 FS <sup>(1)</sup>	Proposed Loading (FS) <sup>(1)</sup>	Result
Reinforced Concrete Pad and Pier	OTM <sup>(2)</sup>	1.0	1.6	<b>PASS</b>

Note 1: FS denotes Factor of Safety.

Note 2: OTM denotes Overturning Moment.

- The anchor bolts and base plate were found to be within allowable limits.

Tower Component	Design Limit	Stress Ratio (percentage of capacity)	Result
Anchor Bolts	Combined Axial and Shear	63.8%	PASS
Base Plate	Bending	70.3%	PASS

### Conclusion

This analysis shows that the subject tower **is adequate** to support the proposed modified antenna configuration.


The analysis is based, in part, on the information provided to this office by T-Mobile. If the existing conditions are different than the information in this report, Centek Engineering, Inc. must be contacted for resolution of any potential issues.

Please feel free to call with any questions or comments.

Respectfully Submitted by:



Timothy J. Lynn, PE  
Structural Engineer



*Standard Conditions for Furnishing of  
Professional Engineering Services on  
Existing Structures*

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessarily limited to:

- Information supplied by the client regarding the structure itself, its foundations, the soil conditions, the antenna and feed line loading on the structure and its components, or other relevant information.
- Information from the field and/or drawings in the possession of Centek Engineering, Inc. or generated by field inspections or measurements of the structure.
- It is the responsibility of the client to ensure that the information provided to Centek Engineering, Inc. and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and are in an uncorroded condition and have not deteriorated. It is therefore assumed that its capacity has not significantly changed from the “as new” condition.
- All services will be performed to the codes specified by the client, and we do not imply to meet any other codes or requirements unless explicitly agreed in writing. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement. In the absence of information to the contrary, all work will be performed in accordance with the latest revision of ANSI/ASCE10 & ANSI/EIA-222
- All services performed, results obtained, and recommendations made are in accordance with generally accepted engineering principles and practices. Centek Engineering, Inc. is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.

## GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM


TnxTower, is an integrated structural analysis and design software package for Designed specifically for the telecommunications industry, TnxTower, formerly ERITower, automates much of the tower analysis and design required by the TIA/EIA 222 Standard.

### TnxTower Features:

- TnxTower can analyze and design 3- and 4-sided guyed towers, 3- and 4-sided self-supporting towers and either round or tapered ground mounted poles with or without guys.
- The program analyzes towers using the TIA-222-G (2005) standard or any of the previous TIA/EIA standards back to RS-222 (1959). Steel design is checked using the AISC ASD 9th Edition or the AISC LRFD specifications.
- Linear and non-linear (P-delta) analyses can be used in determining displacements and forces in the structure. Wind pressures and forces are automatically calculated.
- Extensive graphics plots include material take-off, shear-moment, leg compression, displacement, twist, feed line, guy anchor and stress plots.
- TnxTower contains unique features such as True Cable behavior, hog rod take-up, foundation stiffness and much more.



Section	1	2	3	4
Length (ft)	19.170	50.000	50.290	50.460
Number of Sides	18	18	18	18
Thickness (in)	0.188	0.313	0.500	0.563
Socket Length (ft)	4.330	5.670	6.920	
Top Dia (in)	25.250	28.575	38.886	48.575
Bot Dia (in)	30.030	40.910	51.280	61.000
Grade		A572-65		
Weight (K)	1.1	5.8	12.1	16.6



**DESIGNED APPURTENANCE LOADING**


TYPE	ELEVATION	TYPE	ELEVATION
HP2-4.7 (Motorola - Existing)	156	BXA-70063/6CF (Verizon - Existing)	130
HP3-4.7 (Motorola - Existing)	156	LNx-8513DS (Verizon - Existing)	130
BA40-41 (Motorola - Existing)	154	HBXX-6517DS (Verizon - Existing)	130
Valmont Uni-Tri Bracket (Motorola - Existing)	154	HBXX-6517DS (Verizon - Existing)	130
5'0"x4.5" Pipe Mount (Motorola - Existing)	154	LNx-8513DS (Verizon - Existing)	130
5'0"x4.5" Pipe Mount (Motorola - Existing)	154	HBXX-6517DS (Verizon - Existing)	130
5'0"x4.5" Pipe Mount (Motorola - Existing)	154	HBXX-6517DS (Verizon - Existing)	130
DT465B-2XR (Sprint - Existing)	150	LNx-8513DS (Verizon - Existing)	130
DT465B-2XR (Sprint - Existing)	150	HBXX-6517DS (Verizon - Existing)	130
DT465B-2XR (Sprint - Existing)	150	HBXX-6517DS (Verizon - Existing)	130
APXVSP18-C-A20 (Sprint - Existing)	150	RRH2x60-AWS (Verizon - Existing)	130
APXVSP18-C-A20 (Sprint - Existing)	150	RRH2x60-AWS (Verizon - Existing)	130
APXVSP18-C-A20 (Sprint - Existing)	150	RRH2x60-AWS (Verizon - Existing)	130
TD-RRH8x20-25 (Sprint - Existing)	150	DB-T1-6Z-8AB-0Z (Verizon - Existing)	130
TD-RRH8x20-25 (Sprint - Existing)	150	(2) FD9R6004/2C-3L Diplexer (Verizon - Existing)	130
TD-RRH8x20-25 (Sprint - Existing)	150	(2) FD9R6004/2C-3L Diplexer (Verizon - Existing)	130
(2) FD-RRH 2x50 800 (Sprint - Existing)	150	(2) FD9R6004/2C-3L Diplexer (Verizon - Existing)	130
(2) FD-RRH 2x50 800 (Sprint - Existing)	150	EEL 10' Universal T-Arm (Verizon - Existing)	130
(2) FD-RRH 2x50 800 (Sprint - Existing)	150	EEL 10' Universal T-Arm (Verizon - Existing)	130
FD-RRH 4x40 1900 (Sprint - Existing)	150	EEL 10' Universal T-Arm (Verizon - Existing)	130
FD-RRH 4x40 1900 (Sprint - Existing)	150	RRH2x60-AWS (Verizon - Existing)	130
FD-RRH 4x40 1900 (Sprint - Existing)	150	RRH2x60-AWS (Verizon - Existing)	130
EEL 10' Universal T-Arm (Sprint - Existing)	150	BXA-70063/6CF (Verizon - Existing)	130
EEL 10' Universal T-Arm (Sprint - Existing)	150	7770.00 (ATI - Existing)	120
EEL 10' Universal T-Arm (Sprint - Existing)	150	(2) HPA-65R-BUU-H6 (ATI - Existing)	120
EEL 10' Universal T-Arm (Sprint - Existing)	150	(2) HPA-65R-BUU-H6 (ATI - Existing)	120
EEL Pine Branches	150	(2) HPA-65R-BUU-H6 (ATI - Existing)	120
Monopole Sector Stabilizer Kit VSK-M (T-Mobile - Existing)	142	80010965 (ATI - Existing)	120
APX16DWV-16DWVS-E-A20 (T-Mobile - Proposed)	140	80010965 (ATI - Existing)	120
APX16DWV-16DWVS-E-A20 (T-Mobile - Proposed)	140	80010966 (ATI - Existing)	120
APX16DWV-16DWVS-E-A20 (T-Mobile - Proposed)	140	LGP21401 TMA (ATI - Existing)	120
APX16DWV-16DWVS-E-A20 (T-Mobile - Proposed)	140	LGP21401 TMA (ATI - Existing)	120
APXVAARR24-43 (T-Mobile - Existing)	140	LGP21401 TMA (ATI - Existing)	120
APXVAARR24-43 (T-Mobile - Existing)	140	RRUS-11 (ATI - Existing)	120
APXVAARR24-43 (T-Mobile - Existing)	140	RRUS-11 (ATI - Existing)	120
AIR6449 (T-Mobile - Proposed)	140	RRUS-11 (ATI - Existing)	120
AIR6449 (T-Mobile - Proposed)	140	(2) RRUS-32 (ATI - Existing)	120
AIR6449 (T-Mobile - Proposed)	140	(2) RRUS-32 (ATI - Existing)	120
4449 B12,B71 (T-Mobile - Existing)	140	(2) RRUS-32 (ATI - Existing)	120
4449 B12,B71 (T-Mobile - Existing)	140	4426 B66 (ATI - Existing)	120
4449 B12,B71 (T-Mobile - Existing)	140	4426 B66 (ATI - Existing)	120
4424 B25 (T-Mobile - Proposed)	140	4426 B66 (ATI - Existing)	120
4424 B25 (T-Mobile - Proposed)	140	(2) 4478 B14 (ATI - Existing)	120
4424 B25 (T-Mobile - Proposed)	140	(2) 4478 B14 (ATI - Existing)	120
4415 B25 (T-Mobile - Proposed)	140	(2) 4478 B14 (ATI - Existing)	120
4415 B25 (T-Mobile - Proposed)	140	EEL 10' Universal T-Arm (ATI - Existing)	120
4415 B25 (T-Mobile - Proposed)	140	EEL 10' Universal T-Arm (ATI - Existing)	120
4415 B25 (T-Mobile - Proposed)	140	EEL 10' Universal T-Arm (ATI - Existing)	120
TMA 10"x8"x3" (T-Mobile - Existing)	140	DC6-48-60-18-8F Surge Arrestor (ATI - Existing)	120
TMA 10"x8"x3" (T-Mobile - Existing)	140	DC6-48-60-18-8F Surge Arrestor (ATI - Existing)	120
TMA 10"x8"x3" (T-Mobile - Existing)	140	DC6-48-60-18-8F Surge Arrestor (ATI - Existing)	120
APX16DWV-16DWVS-E-A20 (T-Mobile - Proposed)	140	7770.00 (ATI - Existing)	120
EEL 10' Universal T-Arm (T-Mobile - Existing)	140	EEL Pine Branches	120
EEL 10' Universal T-Arm (T-Mobile - Existing)	140	7770.00 (ATI - Existing)	120
EEL 10' Universal T-Arm (T-Mobile - Existing)	140	EEL Pine Branches	110
EEL Pine Branches	140	EEL Pine Branches	100
BXA-70063/6CF (Verizon - Existing)	130	EEL Pine Branches	90
		EEL Pine Branches	80

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower designed for Exposure C to the TIA-222-G Standard.
2. Tower designed for a 89 mph basic wind in accordance with the TIA-222-G Standard.
3. Tower is also designed for a 40 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Structure Class II.
6. Topographic Category 1 with Crest Height of 0.000 ft
7. TOWER RATING: 87.9%



<b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	Job: <b>20074.50 - CTNH362B</b>
	Project: <b>153-ft EEI Monopole - 33 Boardman Rd., New Milford, CT</b>
	Client: T-Mobile    Drawn by: T.JL    App'd:
	Code: TIA-222-G    Date: 07/08/20    Scale: NTS
	Path:    Dwg No. E-1

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 1 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

## Tower Input Data

The tower is a monopole.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

- Basic wind speed of 89 mph.
- Structure Class II.
- Exposure Category C.
- Topographic Category 1.
- Crest Height 0.000 ft.
- Nominal ice thickness of 1.000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 40 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

- |  |   |   |
|--|---|---|
| <ul style="list-style-type: none"> <li>Consider Moments - Legs</li> <li>Consider Moments - Horizontals</li> <li>Consider Moments - Diagonals</li> <li>Use Moment Magnification</li> <li>√ Use Code Stress Ratios</li> <li>Use Code Safety Factors - Guys</li> <li>Escalate Ice</li> <li>Always Use Max Kz</li> <li>Use Special Wind Profile</li> <li>Include Bolts In Member Capacity</li> <li>Leg Bolts Are At Top Of Section</li> <li>Secondary Horizontal Braces Leg</li> <li>Use Diamond Inner Bracing (4 Sided)</li> <li>SR Members Have Cut Ends</li> <li>SR Members Are Concentric</li> </ul> | <ul style="list-style-type: none"> <li>Distribute Leg Loads As Uniform</li> <li>Assume Legs Pinned</li> <li>√ Assume Rigid Index Plate</li> <li>Use Clear Spans For Wind Area</li> <li>Use Clear Spans For KL/r</li> <li>Retension Guys To Initial Tension</li> <li>√ Bypass Mast Stability Checks</li> <li>Use Azimuth Dish Coefficients</li> <li>√ Project Wind Area of Appurt.</li> <li>Autocalc Torque Arm Areas</li> <li>Add IBC .6D+W Combination</li> <li>√ Sort Capacity Reports By Component</li> <li>Triangulate Diamond Inner Bracing</li> <li>Treat Feed Line Bundles As Cylinder</li> <li>Ignore KL/ry For 60 Deg. Angle Legs</li> </ul> | <ul style="list-style-type: none"> <li>Use ASCE 10 X-Brace Ly Rules</li> <li>Calculate Redundant Bracing Forces</li> <li>Ignore Redundant Members in FEA</li> <li>SR Leg Bolts Resist Compression</li> <li>All Leg Panels Have Same Allowable</li> <li>Offset Girt At Foundation</li> <li>Consider Feed Line Torque</li> <li>Include Angle Block Shear Check</li> <li>Use TIA-222-G Bracing Resist. Exemption</li> <li>Use TIA-222-G Tension Splice Exemption</li> <li style="text-align: center;">Poles</li> <li>√ Include Shear-Torsion Interaction</li> <li>Always Use Sub-Critical Flow</li> <li>Use Top Mounted Sockets</li> <li>Pole Without Linear Attachments</li> <li>Pole With Shroud Or No Appurtenances</li> <li>Outside and Inside Corner Radii Are Known</li> </ul> |
|--|---|---|

## Tapered Pole Section Geometry

Section	Elevation	Section Length	Splice Length	Number of Sides	Top Diameter	Bottom Diameter	Wall Thickness	Bend Radius	Pole Grade
	ft	ft	ft		in	in	in	in	
L1	154.000-134.830	19.170	4.330	18	25.250	30.030	0.188	0.750	A572-65 (65 ksi)

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 2 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L2	134.830-89.160	50.000	5.670	18	28.575	40.910	0.313	1.250	A572-65 (65 ksi)
L3	89.160-44.540	50.290	6.920	18	38.886	51.280	0.500	2.000	A572-65 (65 ksi)
L4	44.540-1.000	50.460		18	48.575	61.000	0.563	2.250	A572-65 (65 ksi)

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	It/Q in <sup>2</sup>	w in	w/t
L1	25.611	14.915	1183.638	8.897	12.827	92.277	2368.833	7.459	4.114	21.941
	30.464	17.760	1998.257	10.594	15.255	130.988	3999.143	8.882	4.955	26.428
L2	30.053	28.033	2829.053	10.033	14.516	194.888	5661.828	14.019	4.479	14.334
	41.493	40.268	8384.791	14.412	20.782	403.459	16780.616	20.138	6.650	21.281
L3	40.828	60.919	11340.739	13.627	19.754	574.092	22696.401	30.465	5.964	11.928
	51.994	80.588	26253.818	18.027	26.050	1007.815	52542.181	40.302	8.145	16.291
L4	50.967	85.720	24964.271	17.044	24.676	1011.687	49961.392	42.868	7.559	13.438
	61.854	107.904	49795.073	21.455	30.988	1606.915	99655.668	53.962	9.746	17.326

Tower Elevation ft	Gusset Area (per face) ft <sup>2</sup>	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
L1 154.000-134.830				1	1	1			
L2 134.830-89.160				1	1	1			
L3 89.160-44.540				1	1	1			
L4 44.540-1.000				1	1	1			

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	C <sub>A</sub> A <sub>A</sub> ft <sup>2</sup> /ft	Weight klf
7/8 (Town - Existing)	B	No	Yes	Inside Pole	151.000 - 4.000	3	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.001
1 5/8 (Sprint - Existing)	B	No	Yes	Inside Pole	151.000 - 4.000	9	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.001
HYBRIFLEX 1-1/4" (Sprint - Existing)	C	No	Yes	Inside Pole	151.000 - 4.000	4	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.001
1 5/8	B	No	Yes	Inside Pole	131.000 - 4.000	12	No Ice	0.000

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 3 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	CAAA	Weight
							ft <sup>2</sup> /ft	klf
(Verizon - Existing)							1/2" Ice 1" Ice	0.000 0.001
HYBRIFLEX 1-5/8" (Verizon - Existing)	B	No	Yes	Inside Pole	131.000 - 4.000	1	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.002
1 5/8 (AT&T - Existing)	B	No	Yes	Inside Pole	121.000 - 4.000	12	No Ice 1/2" Ice 1" Ice	0.000 0.001 0.001
RG6-Fiber (AT&T - Existing)	C	No	Yes	Inside Pole	121.000 - 4.000	1	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.001
#8 AWG Copper Wire (AT&T - Existing)	C	No	Yes	Inside Pole	121.000 - 4.000	2	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.000
HYBRIFLEX 1-5/8" (T-Mobile - Existing)	B	No	Yes	Inside Pole	141.000 - 4.000	1	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.002
HYBRIFLEX 1-5/8" (T-Mobile - Proposed)	B	No	Yes	Inside Pole	141.000 - 4.000	2	No Ice 1/2" Ice 1" Ice	0.000 0.000 0.002

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub>	A <sub>F</sub>	CAAA In Face	CAAA Out Face	Weight
			ft <sup>2</sup>	ft <sup>2</sup>	ft <sup>2</sup>	ft <sup>2</sup>	K
L1	154.000-134.830	A	0.000	0.000	0.000	0.000	0.000
		B	0.000	0.000	0.000	0.000	0.213
		C	0.000	0.000	0.000	0.000	0.084
L2	134.830-89.160	A	0.000	0.000	0.000	0.000	0.000
		B	0.000	0.000	0.000	0.000	1.761
		C	0.000	0.000	0.000	0.000	0.273
L3	89.160-44.540	A	0.000	0.000	0.000	0.000	0.000
		B	0.000	0.000	0.000	0.000	1.943
		C	0.000	0.000	0.000	0.000	0.281
L4	44.540-1.000	A	0.000	0.000	0.000	0.000	0.000
		B	0.000	0.000	0.000	0.000	1.765
		C	0.000	0.000	0.000	0.000	0.255

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub>	A <sub>F</sub>	CAAA In Face	CAAA Out Face	Weight
				ft <sup>2</sup>	ft <sup>2</sup>	ft <sup>2</sup>	ft <sup>2</sup>	K
L1	154.000-134.830	A	2.318	0.000	0.000	0.000	0.000	0.000
		B		0.000	0.000	0.000	0.000	0.213
		C		0.000	0.000	0.000	0.000	0.084
L2	134.830-89.160	A	2.258	0.000	0.000	0.000	0.000	0.000
		B		0.000	0.000	0.000	0.000	1.761
		C		0.000	0.000	0.000	0.000	0.273
L3	89.160-44.540	A	2.145	0.000	0.000	0.000	0.000	0.000

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	4 of 27
	<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b>	16:09:00 07/08/20
	<b>Client</b>	T-Mobile	<b>Designed by</b>	TJL

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
L4	44.540-1.000	B		0.000	0.000	0.000	0.000	1.943
		C		0.000	0.000	0.000	0.000	0.281
		A	1.929	0.000	0.000	0.000	0.000	0.000
		B		0.000	0.000	0.000	0.000	1.765
		C		0.000	0.000	0.000	0.000	0.255

### Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K <sub>a</sub> No Ice	K <sub>a</sub> Ice
---------------	----------------------	-------------	-------------------------	--------------------------	-----------------------

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K	
EEI Pine Branches	C	None		0.000	150.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
EEI Pine Branches	C	None		0.000	140.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
EEI Pine Branches	C	None		0.000	130.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
EEI Pine Branches	C	None		0.000	120.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
EEI Pine Branches	C	None		0.000	110.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
EEI Pine Branches	C	None		0.000	100.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
EEI Pine Branches	C	None		0.000	90.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
EEI Pine Branches	C	None		0.000	80.000	No Ice	90.000	90.000	1.500
						1/2" Ice	130.000	130.000	1.900
						1" Ice	170.000	170.000	2.300
DT465B-2XR (Sprint - Existing)	A	From Face	3.000	0.000	150.000	No Ice	9.098	5.973	0.060
			5.000			1/2" Ice	9.564	6.432	0.118
			0.000			1" Ice	10.036	6.898	0.182
DT465B-2XR (Sprint - Existing)	B	From Face	3.000	0.000	150.000	No Ice	9.098	5.973	0.060
			5.000			1/2" Ice	9.564	6.432	0.118
			0.000			1" Ice	10.036	6.898	0.182
DT465B-2XR (Sprint - Existing)	C	From Face	3.000	0.000	150.000	No Ice	9.098	5.973	0.060
			5.000			1/2" Ice	9.564	6.432	0.118
			0.000			1" Ice	10.036	6.898	0.182
APXVSP18-C-A20	A	From Face	3.000	0.000	150.000	No Ice	8.024	5.283	0.057

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>						<b>Page</b>		
	20074.50 - CTNH362B						5 of 27		
	<b>Project</b>						<b>Date</b>		
153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT						16:09:00 07/08/20			
<b>Client</b>						<b>Designed by</b>			
T-Mobile						TJL			

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	CAAA Front	CAAA Side	Weight K	
(Sprint - Existing)			-5.000			1/2" Ice	8.480	5.736	0.107
			0.000			1" Ice	8.943	6.196	0.162
APXVSP18-C-A20	B	From Face	3.000	0.000	150.000	No Ice	8.024	5.283	0.057
(Sprint - Existing)			-5.000			1/2" Ice	8.480	5.736	0.107
			0.000			1" Ice	8.943	6.196	0.162
APXVSP18-C-A20	C	From Face	3.000	0.000	150.000	No Ice	8.024	5.283	0.057
(Sprint - Existing)			-5.000			1/2" Ice	8.480	5.736	0.107
			0.000			1" Ice	8.943	6.196	0.162
TD-RRH8x20-25	A	From Face	3.000	0.000	150.000	No Ice	4.045	1.533	0.070
(Sprint - Existing)			0.000			1/2" Ice	4.298	1.712	0.097
			0.000			1" Ice	4.557	1.899	0.128
TD-RRH8x20-25	B	From Face	3.000	0.000	150.000	No Ice	4.045	1.533	0.070
(Sprint - Existing)			0.000			1/2" Ice	4.298	1.712	0.097
			0.000			1" Ice	4.557	1.899	0.128
TD-RRH8x20-25	C	From Face	3.000	0.000	150.000	No Ice	4.045	1.533	0.070
(Sprint - Existing)			0.000			1/2" Ice	4.298	1.712	0.097
			0.000			1" Ice	4.557	1.899	0.128
(2) FD-RRH 2x50 800	A	From Face	3.000	0.000	150.000	No Ice	2.058	1.932	0.064
(Sprint - Existing)			0.000			1/2" Ice	2.240	2.109	0.086
			0.000			1" Ice	2.429	2.293	0.111
(2) FD-RRH 2x50 800	B	From Face	3.000	0.000	150.000	No Ice	2.058	1.932	0.064
(Sprint - Existing)			0.000			1/2" Ice	2.240	2.109	0.086
			0.000			1" Ice	2.429	2.293	0.111
(2) FD-RRH 2x50 800	C	From Face	3.000	0.000	150.000	No Ice	2.058	1.932	0.064
(Sprint - Existing)			0.000			1/2" Ice	2.240	2.109	0.086
			0.000			1" Ice	2.429	2.293	0.111
FD-RRH 4x40 1900	A	From Face	3.000	0.000	150.000	No Ice	2.236	2.322	0.060
(Sprint - Existing)			0.000			1/2" Ice	2.439	2.527	0.083
			0.000			1" Ice	2.648	2.739	0.109
FD-RRH 4x40 1900	B	From Face	3.000	0.000	150.000	No Ice	2.236	2.322	0.060
(Sprint - Existing)			0.000			1/2" Ice	2.439	2.527	0.083
			0.000			1" Ice	2.648	2.739	0.109
FD-RRH 4x40 1900	C	From Face	3.000	0.000	150.000	No Ice	2.236	2.322	0.060
(Sprint - Existing)			0.000			1/2" Ice	2.439	2.527	0.083
			0.000			1" Ice	2.648	2.739	0.109
EEI 10' Universal T-Arm	A	None		0.000	150.000	No Ice	13.340	13.340	0.450
(Sprint - Existing)						1/2" Ice	16.800	16.800	0.600
						1" Ice	20.260	20.260	0.750
EEI 10' Universal T-Arm	B	None		0.000	150.000	No Ice	13.340	13.340	0.450
(Sprint - Existing)						1/2" Ice	16.800	16.800	0.600
						1" Ice	20.260	20.260	0.750
EEI 10' Universal T-Arm	C	None		0.000	150.000	No Ice	13.340	13.340	0.450
(Sprint - Existing)						1/2" Ice	16.800	16.800	0.600
						1" Ice	20.260	20.260	0.750
APX16DWV-16DWVS-E-A	A	From Face	3.000	0.000	140.000	No Ice	6.460	2.150	0.041
20			6.000			1/2" Ice	6.833	2.490	0.074
(T-Mobile - Proposed)			0.000			1" Ice	7.214	2.837	0.112
APX16DWV-16DWVS-E-A	B	From Face	3.000	0.000	140.000	No Ice	6.460	2.150	0.041
20			6.000			1/2" Ice	6.833	2.490	0.074
(T-Mobile - Proposed)			0.000			1" Ice	7.214	2.837	0.112
APX16DWV-16DWVS-E-A	C	From Face	3.000	0.000	140.000	No Ice	6.460	2.150	0.041
20			6.000			1/2" Ice	6.833	2.490	0.074
(T-Mobile - Proposed)			0.000			1" Ice	7.214	2.837	0.112
APXVAARR24-43	A	From Face	3.000	0.000	140.000	No Ice	20.243	8.889	0.153
(T-Mobile - Existing)			-6.000			1/2" Ice	20.890	9.487	0.266
			0.000			1" Ice	21.544	10.092	0.387
APXVAARR24-43	B	From Face	3.000	0.000	140.000	No Ice	20.243	8.889	0.153

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>		20074.50 - CTNH362B		<b>Page</b>		6 of 27	
	<b>Project</b>		153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT		<b>Date</b>		16:09:00 07/08/20	
	<b>Client</b>		T-Mobile		<b>Designed by</b>		TJL	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
			Horz Lateral ft	Vert ft					
(T-Mobile - Existing)			-6.000			1/2" Ice	20.890	9.487	0.266
			0.000			1" Ice	21.544	10.092	0.387
APXVAARR24-43	C	From Face	3.000	0.000	140.000	No Ice	20.243	8.889	0.153
(T-Mobile - Existing)			-6.000			1/2" Ice	20.890	9.487	0.266
			0.000			1" Ice	21.544	10.092	0.387
AIR6449	A	From Face	3.000	0.000	140.000	No Ice	5.655	2.416	0.103
(T-Mobile - Proposed)			-2.000			1/2" Ice	5.956	2.641	0.141
			0.000			1" Ice	6.265	2.874	0.184
AIR6449	B	From Face	3.000	0.000	140.000	No Ice	5.655	2.416	0.103
(T-Mobile - Proposed)			-2.000			1/2" Ice	5.956	2.641	0.141
			0.000			1" Ice	6.265	2.874	0.184
AIR6449	C	From Face	3.000	0.000	140.000	No Ice	5.655	2.416	0.103
(T-Mobile - Proposed)			-2.000			1/2" Ice	5.956	2.641	0.141
			0.000			1" Ice	6.265	2.874	0.184
4449 B12,B71	A	From Face	3.000	0.000	140.000	No Ice	1.650	1.156	0.080
(T-Mobile - Existing)			-6.000			1/2" Ice	1.810	1.295	0.096
			0.000			1" Ice	1.978	1.441	0.115
4449 B12,B71	B	From Face	3.000	0.000	140.000	No Ice	1.650	1.156	0.080
(T-Mobile - Existing)			-6.000			1/2" Ice	1.810	1.295	0.096
			0.000			1" Ice	1.978	1.441	0.115
4449 B12,B71	C	From Face	3.000	0.000	140.000	No Ice	1.650	1.156	0.080
(T-Mobile - Existing)			-6.000			1/2" Ice	1.810	1.295	0.096
			0.000			1" Ice	1.978	1.441	0.115
4424 B25	A	From Face	3.000	0.000	140.000	No Ice	2.052	1.610	0.086
(T-Mobile - Proposed)			-6.000			1/2" Ice	2.231	1.772	0.107
			0.000			1" Ice	2.417	1.941	0.131
4424 B25	B	From Face	3.000	0.000	140.000	No Ice	2.052	1.610	0.086
(T-Mobile - Proposed)			-6.000			1/2" Ice	2.231	1.772	0.107
			0.000			1" Ice	2.417	1.941	0.131
4424 B25	C	From Face	3.000	0.000	140.000	No Ice	2.052	1.610	0.086
(T-Mobile - Proposed)			-6.000			1/2" Ice	2.231	1.772	0.107
			0.000			1" Ice	2.417	1.941	0.131
4415 B25	A	From Face	3.000	0.000	140.000	No Ice	1.843	0.820	0.046
(T-Mobile - Proposed)			6.000			1/2" Ice	2.012	0.943	0.060
			0.000			1" Ice	2.190	1.075	0.077
4415 B25	B	From Face	3.000	0.000	140.000	No Ice	1.843	0.820	0.046
(T-Mobile - Proposed)			6.000			1/2" Ice	2.012	0.943	0.060
			0.000			1" Ice	2.190	1.075	0.077
4415 B25	C	From Face	3.000	0.000	140.000	No Ice	1.843	0.820	0.046
(T-Mobile - Proposed)			6.000			1/2" Ice	2.012	0.943	0.060
			0.000			1" Ice	2.190	1.075	0.077
TMA 10"x8"x3"	A	From Face	3.000	0.000	140.000	No Ice	0.667	0.258	0.015
(T-Mobile - Existing)			0.000			1/2" Ice	0.770	0.331	0.020
			0.000			1" Ice	0.881	0.411	0.027
TMA 10"x8"x3"	B	From Face	3.000	0.000	140.000	No Ice	0.667	0.258	0.015
(T-Mobile - Existing)			0.000			1/2" Ice	0.770	0.331	0.020
			0.000			1" Ice	0.881	0.411	0.027
TMA 10"x8"x3"	C	From Face	3.000	0.000	140.000	No Ice	0.667	0.258	0.015
(T-Mobile - Existing)			0.000			1/2" Ice	0.770	0.331	0.020
			0.000			1" Ice	0.881	0.411	0.027
Monopole Sector Stabilizer Kit VSK-M	A	None		0.000	142.000	No Ice	9.000	9.000	0.350
(T-Mobile - Existing)						1/2" Ice	11.500	11.500	0.425
						1" Ice	14.000	14.000	0.500
EEI 10' Universal T-Arm	A	None		0.000	140.000	No Ice	13.340	13.340	0.450
(T-Mobile - Existing)						1/2" Ice	16.800	16.800	0.600
						1" Ice	20.260	20.260	0.750
EEI 10' Universal T-Arm	B	None		0.000	140.000	No Ice	13.340	13.340	0.450

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>		20074.50 - CTNH362B		<b>Page</b>		7 of 27	
	<b>Project</b>		153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT		<b>Date</b>		16:09:00 07/08/20	
	<b>Client</b>		T-Mobile		<b>Designed by</b>		TJL	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Vert					
(T-Mobile - Existing)									
						1/2" Ice	16.800	16.800	0.600
						1" Ice	20.260	20.260	0.750
EEI 10' Universal T-Arm	C	None			0.000	140.000	No Ice	13.340	0.450
(T-Mobile - Existing)							1/2" Ice	16.800	0.600
							1" Ice	20.260	0.750
BXA-70063/6CF	A	From Face	3.000		0.000	130.000	No Ice	7.569	0.012
(Verizon - Existing)			0.000				1/2" Ice	8.016	0.054
			0.000				1" Ice	8.470	0.103
BXA-70063/6CF	B	From Face	3.000		0.000	130.000	No Ice	7.569	0.012
(Verizon - Existing)			0.000				1/2" Ice	8.016	0.054
			0.000				1" Ice	8.470	0.103
BXA-70063/6CF	C	From Face	3.000		0.000	130.000	No Ice	7.569	0.012
(Verizon - Existing)			0.000				1/2" Ice	8.016	0.054
			0.000				1" Ice	8.470	0.103
LNX-8513DS	A	From Face	3.000		0.000	130.000	No Ice	8.173	0.045
(Verizon - Existing)			6.000				1/2" Ice	8.633	0.096
			0.000				1" Ice	9.100	0.152
HBXX-6517DS	A	From Face	3.000		0.000	130.000	No Ice	8.528	0.050
(Verizon - Existing)			4.000				1/2" Ice	9.000	0.100
			0.000				1" Ice	9.480	0.157
HBXX-6517DS	A	From Face	3.000		0.000	130.000	No Ice	8.528	0.050
(Verizon - Existing)			-4.000				1/2" Ice	9.000	0.100
			0.000				1" Ice	9.480	0.157
LNX-8513DS	B	From Face	3.000		0.000	130.000	No Ice	8.173	0.045
(Verizon - Existing)			6.000				1/2" Ice	8.633	0.096
			0.000				1" Ice	9.100	0.152
HBXX-6517DS	B	From Face	3.000		0.000	130.000	No Ice	8.528	0.050
(Verizon - Existing)			4.000				1/2" Ice	9.000	0.100
			0.000				1" Ice	9.480	0.157
HBXX-6517DS	B	From Face	3.000		0.000	130.000	No Ice	8.528	0.050
(Verizon - Existing)			-4.000				1/2" Ice	9.000	0.100
			0.000				1" Ice	9.480	0.157
LNX-8513DS	C	From Face	3.000		0.000	130.000	No Ice	8.173	0.045
(Verizon - Existing)			6.000				1/2" Ice	8.633	0.096
			0.000				1" Ice	9.100	0.152
HBXX-6517DS	C	From Face	3.000		0.000	130.000	No Ice	8.528	0.050
(Verizon - Existing)			4.000				1/2" Ice	9.000	0.100
			0.000				1" Ice	9.480	0.157
HBXX-6517DS	C	From Face	3.000		0.000	130.000	No Ice	8.528	0.050
(Verizon - Existing)			-4.000				1/2" Ice	9.000	0.100
			0.000				1" Ice	9.480	0.157
RRH2x60-AWS	A	From Face	3.000		0.000	130.000	No Ice	3.357	0.055
(Verizon - Existing)			-4.000				1/2" Ice	3.614	0.078
			0.000				1" Ice	3.878	0.105
RRH2x60-AWS	B	From Face	3.000		0.000	130.000	No Ice	3.357	0.055
(Verizon - Existing)			-4.000				1/2" Ice	3.614	0.078
			0.000				1" Ice	3.878	0.105
RRH2x60-AWS	C	From Face	3.000		0.000	130.000	No Ice	3.357	0.055
(Verizon - Existing)			-4.000				1/2" Ice	3.614	0.078
			0.000				1" Ice	3.878	0.105
DB-T1-6Z-8AB-0Z	C	From Face	3.000		0.000	130.000	No Ice	4.800	0.044
(Verizon - Existing)			-4.000				1/2" Ice	5.070	0.080
			0.000				1" Ice	5.348	0.120
(2) FD9R6004/2C-3L	A	From Face	3.000		0.000	130.000	No Ice	0.314	0.003
Diplexer			0.000				1/2" Ice	0.386	0.005
(Verizon - Existing)			0.000				1" Ice	0.466	0.009
(2) FD9R6004/2C-3L	B	From Face	3.000		0.000	130.000	No Ice	0.314	0.003



<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>		20074.50 - CTNH362B		<b>Page</b>		8 of 27	
	<b>Project</b>		153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT		<b>Date</b>		16:09:00 07/08/20	
	<b>Client</b>		T-Mobile		<b>Designed by</b>		TJL	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
			Horz Lateral ft	Vert ft					
Diplexer (Verizon - Existing)				0.000			1/2" Ice 0.386	0.119	0.005
(2) FD9R6004/2C-3L Diplexer (Verizon - Existing)	C	From Face	3.000	0.000	0.000	130.000	No Ice 0.314 1" Ice 0.466	0.076	0.003
EEI 10' Universal T-Arm (Verizon - Existing)	A	None		0.000	0.000	130.000	No Ice 13.340 1/2" Ice 16.800 1" Ice 20.260	13.340	0.450
EEI 10' Universal T-Arm (Verizon - Existing)	B	None		0.000	0.000	130.000	No Ice 13.340 1/2" Ice 16.800 1" Ice 20.260	13.340	0.450
EEI 10' Universal T-Arm (Verizon - Existing)	C	None		0.000	0.000	130.000	No Ice 13.340 1/2" Ice 16.800 1" Ice 20.260	13.340	0.450
7770.00 (AT&T - Existing)	A	From Face	3.000	0.000	0.000	120.000	No Ice 5.508 1/2" Ice 5.867 1" Ice 6.233	2.928	0.035
7770.00 (AT&T - Existing)	B	From Face	3.000	0.000	0.000	120.000	No Ice 5.508 1/2" Ice 5.867 1" Ice 6.233	2.928	0.035
7770.00 (AT&T - Existing)	C	From Face	3.000	0.000	0.000	120.000	No Ice 5.508 1/2" Ice 5.867 1" Ice 6.233	2.928	0.035
(2) HPA-65R-BUU-H6 (AT&T - Existing)	A	From Face	3.000	0.000	0.000	120.000	No Ice 9.658 1/2" Ice 10.128 1" Ice 10.606	6.450	0.051
(2) HPA-65R-BUU-H6 (AT&T - Existing)	B	From Face	3.000	0.000	0.000	120.000	No Ice 9.658 1/2" Ice 10.128 1" Ice 10.606	6.450	0.051
(2) HPA-65R-BUU-H6 (AT&T - Existing)	C	From Face	3.000	0.000	0.000	120.000	No Ice 9.658 1/2" Ice 10.128 1" Ice 10.606	6.450	0.051
80010965 (AT&T - Existing)	A	From Face	3.000	0.000	0.000	120.000	No Ice 13.814 1/2" Ice 14.347 1" Ice 14.888	5.833	0.109
80010965 (AT&T - Existing)	B	From Face	3.000	0.000	0.000	120.000	No Ice 13.814 1/2" Ice 14.347 1" Ice 14.888	5.833	0.109
80010966 (AT&T - Existing)	C	From Face	3.000	0.000	0.000	120.000	No Ice 17.363 1/2" Ice 17.991 1" Ice 18.626	7.500	0.126
LGP21401 TMA (AT&T - Existing)	A	From Face	3.000	0.000	0.000	120.000	No Ice 0.817 1/2" Ice 0.937 1" Ice 1.065	0.346	0.018
LGP21401 TMA (AT&T - Existing)	B	From Face	3.000	0.000	0.000	120.000	No Ice 0.817 1/2" Ice 0.937 1" Ice 1.065	0.346	0.018
LGP21401 TMA (AT&T - Existing)	C	From Face	3.000	0.000	0.000	120.000	No Ice 0.817 1/2" Ice 0.937 1" Ice 1.065	0.346	0.018
RRUS-11 (AT&T - Existing)	A	From Face	1.000	0.000	0.000	120.000	No Ice 2.566 1/2" Ice 2.765 1" Ice 2.971	1.068	0.050
RRUS-11 (AT&T - Existing)	B	From Face	1.000	0.000	0.000	120.000	No Ice 2.566 1/2" Ice 2.765 1" Ice 2.971	1.068	0.050
RRUS-11	C	From Face	1.000	0.000	0.000	120.000	No Ice 2.566	1.068	0.050

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>		20074.50 - CTNH362B				<b>Page</b>		9 of 27
	<b>Project</b>		153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT				<b>Date</b>		16:09:00 07/08/20
	<b>Client</b>		T-Mobile				<b>Designed by</b>		TJL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
			Horz Lateral ft	Vert ft					
(AT&T - Existing)			2.000				1/2" Ice 2.765	1.211	0.070
			0.000				1" Ice 2.971	1.361	0.092
(2) RRUS-32	A	From Face	1.000		0.000	120.000	No Ice 3.314	2.424	0.077
(AT&T - Existing)			2.000				1/2" Ice 3.558	2.638	0.105
			0.000				1" Ice 3.809	2.860	0.136
(2) RRUS-32	B	From Face	1.000		0.000	120.000	No Ice 3.314	2.424	0.077
(AT&T - Existing)			2.000				1/2" Ice 3.558	2.638	0.105
			0.000				1" Ice 3.809	2.860	0.136
(2) RRUS-32	C	From Face	1.000		0.000	120.000	No Ice 3.314	2.424	0.077
(AT&T - Existing)			2.000				1/2" Ice 3.558	2.638	0.105
			0.000				1" Ice 3.809	2.860	0.136
4426 B66	A	From Face	1.000		0.000	120.000	No Ice 1.650	0.727	0.049
(AT&T - Existing)			2.000				1/2" Ice 1.810	0.844	0.062
			0.000				1" Ice 1.978	0.971	0.077
4426 B66	B	From Face	1.000		0.000	120.000	No Ice 1.650	0.727	0.049
(AT&T - Existing)			2.000				1/2" Ice 1.810	0.844	0.062
			0.000				1" Ice 1.978	0.971	0.077
4426 B66	C	From Face	1.000		0.000	120.000	No Ice 1.650	0.727	0.049
(AT&T - Existing)			2.000				1/2" Ice 1.810	0.844	0.062
			0.000				1" Ice 1.978	0.971	0.077
(2) 4478 B14	A	From Face	1.000		0.000	120.000	No Ice 1.843	1.059	0.060
(AT&T - Existing)			2.000				1/2" Ice 2.012	1.197	0.076
			0.000				1" Ice 2.190	1.342	0.094
(2) 4478 B14	B	From Face	1.000		0.000	120.000	No Ice 1.843	1.059	0.060
(AT&T - Existing)			2.000				1/2" Ice 2.012	1.197	0.076
			0.000				1" Ice 2.190	1.342	0.094
(2) 4478 B14	C	From Face	1.000		0.000	120.000	No Ice 1.843	1.059	0.060
(AT&T - Existing)			2.000				1/2" Ice 2.012	1.197	0.076
			0.000				1" Ice 2.190	1.342	0.094
EEI 10' Universal T-Arm	A	None			0.000	120.000	No Ice 13.340	13.340	0.450
(AT&T - Existing)							1/2" Ice 16.800	16.800	0.600
							1" Ice 20.260	20.260	0.750
EEI 10' Universal T-Arm	B	None			0.000	120.000	No Ice 13.340	13.340	0.450
(AT&T - Existing)							1/2" Ice 16.800	16.800	0.600
							1" Ice 20.260	20.260	0.750
EEI 10' Universal T-Arm	C	None			0.000	120.000	No Ice 13.340	13.340	0.450
(AT&T - Existing)							1/2" Ice 16.800	16.800	0.600
							1" Ice 20.260	20.260	0.750
DC6-48-60-18-8F Surge	A	From Face	0.500		0.000	120.000	No Ice 1.909	1.909	0.020
Arrestor			0.000				1/2" Ice 2.098	2.098	0.039
(AT&T - Existing)			0.000				1" Ice 2.294	2.294	0.062
DC6-48-60-18-8F Surge	B	From Face	0.500		0.000	120.000	No Ice 1.909	1.909	0.020
Arrestor			0.000				1/2" Ice 2.098	2.098	0.039
(AT&T - Existing)			0.000				1" Ice 2.294	2.294	0.062
DC6-48-60-18-8F Surge	C	From Face	0.500		0.000	120.000	No Ice 1.909	1.909	0.020
Arrestor			0.000				1/2" Ice 2.098	2.098	0.039
(AT&T - Existing)			0.000				1" Ice 2.294	2.294	0.062
BA40-41	A	From Leg	1.000		0.000	154.000	No Ice 4.480	4.480	0.032
(Motorola - Existing)			0.000				1/2" Ice 7.660	7.660	0.040
			5.000				1" Ice 10.840	10.840	0.048
Valmont Uni-Tri Bracket	A	From Face	0.000		0.000	154.000	No Ice 1.750	1.750	0.290
(Motorola - Existing)			0.000				1/2" Ice 1.940	1.940	0.306
			0.000				1" Ice 2.130	2.130	0.323
5'0"x4.5" Pipe Mount	A	From Face	1.000		0.000	154.000	No Ice 1.538	1.538	0.054
(Motorola - Existing)			0.000				1/2" Ice 2.076	2.076	0.070
			2.000				1" Ice 2.397	2.397	0.090
5'0"x4.5" Pipe Mount	B	From Face	1.000		0.000	154.000	No Ice 1.538	1.538	0.054

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	10 of 27
	<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b>	16:09:00 07/08/20
	<b>Client</b>	T-Mobile	<b>Designed by</b>	TJL

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz Lateral	Vert					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
(Motorola - Existing)			0.000			1/2" Ice	2.076	2.076	0.070
			2.000			1" Ice	2.397	2.397	0.090
5'0"x4.5" Pipe Mount (Motorola - Existing)	C	From Face	1.000		0.000	No Ice	1.538	1.538	0.054
			0.000			1/2" Ice	2.076	2.076	0.070
			2.000			1" Ice	2.397	2.397	0.090

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz Lateral	Vert							
			ft	ft	°	°	ft	ft	ft <sup>2</sup>	K		
HP2-4.7 (Motorola - Existing)	B	Paraboloid w/Shroud (HP)	From Leg	1.000		Worst		156.000	2.000	No Ice	3.142	0.027
				0.000						1/2" Ice	3.409	0.044
				0.000						1" Ice	3.676	0.062
HP3-4.7 (Motorola - Existing)	C	Paraboloid w/Shroud (HP)	From Leg	1.000		Worst		156.000	3.000	No Ice	7.069	0.050
				0.000						1/2" Ice	7.467	0.067
				0.000						1" Ice	7.865	0.084

### Tower Pressures - No Ice

$$G_H = 1.100$$

Section Elevation	z	K <sub>Z</sub>	q <sub>z</sub>	A <sub>G</sub>	F <sub>a</sub>	A <sub>F</sub>	A <sub>R</sub>	A <sub>leg</sub>	Leg %	C <sub>AA</sub> In Face	C <sub>AA</sub> Out Face
ft	ft		ksf	ft <sup>2</sup>	c	ft <sup>2</sup>	ft <sup>2</sup>	ft <sup>2</sup>		ft <sup>2</sup>	ft <sup>2</sup>
L1 154.000-134.8	144.139	1.367	0.026	44.790	A	0.000	44.790	44.790	100.00	0.000	0.000
30					B	0.000	44.790		100.00	0.000	0.000
L2 134.830-89.16	111.022	1.294	0.025	136.145	C	0.000	44.790		100.00	0.000	0.000
0					A	0.000	136.145	136.145	100.00	0.000	0.000
L3 89.160-44.540	66.351	1.161	0.022	172.571	B	0.000	136.145		100.00	0.000	0.000
					C	0.000	136.145		100.00	0.000	0.000
L4 44.540-1.000	22.981	0.929	0.018	204.677	A	0.000	172.571	172.571	100.00	0.000	0.000
					B	0.000	172.571		100.00	0.000	0.000
					C	0.000	172.571		100.00	0.000	0.000
					A	0.000	204.677	204.677	100.00	0.000	0.000
					B	0.000	204.677		100.00	0.000	0.000
					C	0.000	204.677		100.00	0.000	0.000

### Tower Pressure - With Ice

$$G_H = 1.100$$

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 11 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Section Elevation ft	z ft	K <sub>Z</sub>	q <sub>z</sub> ksf	t <sub>z</sub> in	A <sub>G</sub> ft <sup>2</sup>	F a c e	A <sub>F</sub> ft <sup>2</sup>	A <sub>R</sub> ft <sup>2</sup>	A <sub>leg</sub> ft <sup>2</sup>	Leg %	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>
L1 154.000-134.830	144.139	1.367	0.005	2.318	52.195	A	0.000	52.195	52.195	100.00	0.000	0.000
						B	0.000	52.195		100.00	0.000	0.000
						C	0.000	52.195		100.00	0.000	0.000
L2 134.830-89.160	111.022	1.294	0.005	2.258	153.787	A	0.000	153.787	153.787	100.00	0.000	0.000
						B	0.000	153.787		100.00	0.000	0.000
						C	0.000	153.787		100.00	0.000	0.000
L3 89.160-44.540	66.351	1.161	0.005	2.145	189.363	A	0.000	189.363	189.363	100.00	0.000	0.000
						B	0.000	189.363		100.00	0.000	0.000
						C	0.000	189.363		100.00	0.000	0.000
L4 44.540-1.000	22.981	0.929	0.004	1.929	220.241	A	0.000	220.241	220.241	100.00	0.000	0.000
						B	0.000	220.241		100.00	0.000	0.000
						C	0.000	220.241		100.00	0.000	0.000

**Tower Pressure - Service**

$G_H = 1.100$

Section Elevation ft	z ft	K <sub>Z</sub>	q <sub>z</sub> ksf	A <sub>G</sub> ft <sup>2</sup>	F a c e	A <sub>F</sub> ft <sup>2</sup>	A <sub>R</sub> ft <sup>2</sup>	A <sub>leg</sub> ft <sup>2</sup>	Leg %	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>
L1 154.000-134.830	144.139	1.367	0.011	44.790	A	0.000	44.790	44.790	100.00	0.000	0.000
					B	0.000	44.790		100.00	0.000	0.000
					C	0.000	44.790		100.00	0.000	0.000
L2 134.830-89.160	111.022	1.294	0.010	136.145	A	0.000	136.145	136.145	100.00	0.000	0.000
					B	0.000	136.145		100.00	0.000	0.000
					C	0.000	136.145		100.00	0.000	0.000
L3 89.160-44.540	66.351	1.161	0.009	172.571	A	0.000	172.571	172.571	100.00	0.000	0.000
					B	0.000	172.571		100.00	0.000	0.000
					C	0.000	172.571		100.00	0.000	0.000
L4 44.540-1.000	22.981	0.929	0.007	204.677	A	0.000	204.677	204.677	100.00	0.000	0.000
					B	0.000	204.677		100.00	0.000	0.000
					C	0.000	204.677		100.00	0.000	0.000

**Tower Forces - No Ice - Wind Normal To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 154.000-134.830	0.297	1.066	A	1	0.65	0.026	1	1	44.790	0.843	0.044	C
			B	1	0.65		1	1	44.790			
			C	1	0.65		1	1	44.790			
L2 134.830-89.160	2.033	5.810	A	1	0.65	0.025	1	1	136.145	2.423	0.053	C
			B	1	0.65		1	1	136.145			
			C	1	0.65		1	1	136.145			
L3 89.160-44.540	2.224	12.108	A	1	0.65	0.022	1	1	172.571	2.749	0.062	C
			B	1	0.65		1	1	172.571			
			C	1	0.65		1	1	172.571			
L4 44.540-1.000	2.021	16.623	A	1	0.65	0.018	1	1	204.677	2.604	0.060	C
			B	1	0.65		1	1	204.677			

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 12 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJJ

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	q <sub>z</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K				ksf			ft <sup>2</sup>	K	klf	
Sum Weight:	6.574	35.607	C	1	0.65		1	1	204.677 624.200 kip-ft	8.620		

**Tower Forces - No Ice - Wind 45 To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	q <sub>z</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K				ksf			ft <sup>2</sup>	K	klf	
L1 154.000-134.8	0.297	1.066	A	1	0.65	0.026	1	1	44.790	0.843	0.044	C
30			B	1	0.65		1	1	44.790			
L2 134.830-89.16	2.033	5.810	C	1	0.65		1	1	44.790			
0			A	1	0.65	0.025	1	1	136.145	2.423	0.053	C
L3 89.160-44.540	2.224	12.108	B	1	0.65		1	1	136.145			
0			C	1	0.65		1	1	136.145			
L4 44.540-1.000	2.021	16.623	A	1	0.65	0.018	1	1	172.571	2.749	0.062	C
			B	1	0.65		1	1	172.571			
			C	1	0.65		1	1	172.571			
Sum Weight:	6.574	35.607	A	1	0.65		1	1	204.677 624.200 kip-ft	8.620		

**Tower Forces - No Ice - Wind 60 To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	q <sub>z</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K				ksf			ft <sup>2</sup>	K	klf	
L1 154.000-134.8	0.297	1.066	A	1	0.65	0.026	1	1	44.790	0.843	0.044	C
30			B	1	0.65		1	1	44.790			
L2 134.830-89.16	2.033	5.810	C	1	0.65		1	1	44.790			
0			A	1	0.65	0.025	1	1	136.145	2.423	0.053	C
L3 89.160-44.540	2.224	12.108	B	1	0.65		1	1	136.145			
0			C	1	0.65		1	1	136.145			
L4 44.540-1.000	2.021	16.623	A	1	0.65	0.018	1	1	172.571	2.749	0.062	C
			B	1	0.65		1	1	172.571			
			C	1	0.65		1	1	172.571			
Sum Weight:	6.574	35.607	A	1	0.65		1	1	204.677 624.200 kip-ft	8.620		

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 13 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

**Tower Forces - No Ice - Wind 90 To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	q <sub>z</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K	e			ksf			ft <sup>2</sup>	K	klf	
L1	0.297	1.066	A	1	0.65	0.026	1	1	44.790	0.843	0.044	C
154.000-134.8			B	1	0.65		1	1	44.790			
30			C	1	0.65		1	1	44.790			
L2	2.033	5.810	A	1	0.65	0.025	1	1	136.145	2.423	0.053	C
134.830-89.16			B	1	0.65		1	1	136.145			
0			C	1	0.65		1	1	136.145			
L3	2.224	12.108	A	1	0.65	0.022	1	1	172.571	2.749	0.062	C
89.160-44.540			B	1	0.65		1	1	172.571			
			C	1	0.65		1	1	172.571			
L4	2.021	16.623	A	1	0.65	0.018	1	1	204.677	2.604	0.060	C
44.540-1.000			B	1	0.65		1	1	204.677			
			C	1	0.65		1	1	204.677			
Sum Weight:	6.574	35.607						OTM	624.200	8.620		
									kip-ft			

**Tower Forces - With Ice - Wind Normal To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	q <sub>z</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K	e			ksf			ft <sup>2</sup>	K	klf	
L1	0.297	2.709	A	1	1.2	0.005	1	1	52.195	0.366	0.019	C
154.000-134.8			B	1	1.2		1	1	52.195			
30			C	1	1.2		1	1	52.195			
L2	2.033	10.588	A	1	1.2	0.005	1	1	153.787	1.021	0.022	C
134.830-89.16			B	1	1.2		1	1	153.787			
0			C	1	1.2		1	1	153.787			
L3	2.224	17.769	A	1	1.2	0.005	1	1	189.363	1.125	0.025	C
89.160-44.540			B	1	1.2		1	1	189.363			
			C	1	1.2		1	1	189.363			
L4	2.021	22.591	A	1	1.2	0.004	1	1	220.241	1.045	0.024	C
44.540-1.000			B	1	1.2		1	1	220.241			
			C	1	1.2		1	1	220.241			
Sum Weight:	6.574	53.656						OTM	261.238	3.557		
									kip-ft			

**Tower Forces - With Ice - Wind 45 To Face**

Section Elevation	Add Weight	Self Weight	F a c e	e	C <sub>F</sub>	q <sub>z</sub>	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub>	F	w	Ctrl. Face
ft	K	K	e			ksf			ft <sup>2</sup>	K	klf	
L1	0.297	2.709	A	1	1.2	0.005	1	1	52.195	0.366	0.019	C
154.000-134.8			B	1	1.2		1	1	52.195			
30			C	1	1.2		1	1	52.195			

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 14 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Section Elevation ft	Add Weight K	Self Weight K	Face	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L2 134.830-89.160	2.033	10.588	A	1	1.2	0.005	1	1	153.787	1.021	0.022	C
			B	1	1.2		1	1	153.787			
			C	1	1.2		1	1	153.787			
L3 89.160-44.540	2.224	17.769	A	1	1.2	0.005	1	1	189.363	1.125	0.025	C
			B	1	1.2		1	1	189.363			
			C	1	1.2		1	1	189.363			
L4 44.540-1.000	2.021	22.591	A	1	1.2	0.004	1	1	220.241	1.045	0.024	C
			B	1	1.2		1	1	220.241			
			C	1	1.2		1	1	220.241			
Sum Weight:	6.574	53.656						OTM	261.238 kip-ft	3.557		

**Tower Forces - With Ice - Wind 60 To Face**

Section Elevation ft	Add Weight K	Self Weight K	Face	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 154.000-134.830	0.297	2.709	A	1	1.2	0.005	1	1	52.195	0.366	0.019	C
			B	1	1.2		1	1	52.195			
			C	1	1.2		1	1	52.195			
L2 134.830-89.160	2.033	10.588	A	1	1.2	0.005	1	1	153.787	1.021	0.022	C
			B	1	1.2		1	1	153.787			
			C	1	1.2		1	1	153.787			
L3 89.160-44.540	2.224	17.769	A	1	1.2	0.005	1	1	189.363	1.125	0.025	C
			B	1	1.2		1	1	189.363			
			C	1	1.2		1	1	189.363			
L4 44.540-1.000	2.021	22.591	A	1	1.2	0.004	1	1	220.241	1.045	0.024	C
			B	1	1.2		1	1	220.241			
			C	1	1.2		1	1	220.241			
Sum Weight:	6.574	53.656						OTM	261.238 kip-ft	3.557		

**Tower Forces - With Ice - Wind 90 To Face**

Section Elevation ft	Add Weight K	Self Weight K	Face	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 154.000-134.830	0.297	2.709	A	1	1.2	0.005	1	1	52.195	0.366	0.019	C
			B	1	1.2		1	1	52.195			
			C	1	1.2		1	1	52.195			
L2 134.830-89.160	2.033	10.588	A	1	1.2	0.005	1	1	153.787	1.021	0.022	C
			B	1	1.2		1	1	153.787			
			C	1	1.2		1	1	153.787			
L3 89.160-44.540	2.224	17.769	A	1	1.2	0.005	1	1	189.363	1.125	0.025	C
			B	1	1.2		1	1	189.363			
			C	1	1.2		1	1	189.363			
L4	2.021	22.591	A	1	1.2	0.004	1	1	220.241	1.045	0.024	C

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	15 of 27
	<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b>	16:09:00 07/08/20
	<b>Client</b>	T-Mobile	<b>Designed by</b>	TJL

Section Elevation ft	Add Weight K	Self Weight K	Face	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
44.540-1.000			B	1	1.2		1	1	220.241			
			C	1	1.2		1	1	220.241			
Sum Weight:	6.574	53.656						OTM	261.238 kip-ft	3.557		

### Tower Forces - Service - Wind Normal To Face

Section Elevation ft	Add Weight K	Self Weight K	Face	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1	0.297	1.066	A	1	0.65	0.011	1	1	44.790	0.343	0.018	C
154.000-134.8			B	1	0.65		1	1	44.790			
30			C	1	0.65		1	1	44.790			
L2	2.033	5.810	A	1	0.65	0.010	1	1	136.145	0.985	0.022	C
134.830-89.16			B	1	0.65		1	1	136.145			
0			C	1	0.65		1	1	136.145			
L3	2.224	12.108	A	1	0.65	0.009	1	1	172.571	1.118	0.025	C
89.160-44.540			B	1	0.65		1	1	172.571			
			C	1	0.65		1	1	172.571			
L4	2.021	16.623	A	1	0.65	0.007	1	1	204.677	1.059	0.024	C
44.540-1.000			B	1	0.65		1	1	204.677			
			C	1	0.65		1	1	204.677			
Sum Weight:	6.574	35.607						OTM	253.829 kip-ft	3.505		

### Tower Forces - Service - Wind 45 To Face

Section Elevation ft	Add Weight K	Self Weight K	Face	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1	0.297	1.066	A	1	0.65	0.011	1	1	44.790	0.343	0.018	C
154.000-134.8			B	1	0.65		1	1	44.790			
30			C	1	0.65		1	1	44.790			
L2	2.033	5.810	A	1	0.65	0.010	1	1	136.145	0.985	0.022	C
134.830-89.16			B	1	0.65		1	1	136.145			
0			C	1	0.65		1	1	136.145			
L3	2.224	12.108	A	1	0.65	0.009	1	1	172.571	1.118	0.025	C
89.160-44.540			B	1	0.65		1	1	172.571			
			C	1	0.65		1	1	172.571			
L4	2.021	16.623	A	1	0.65	0.007	1	1	204.677	1.059	0.024	C
44.540-1.000			B	1	0.65		1	1	204.677			
			C	1	0.65		1	1	204.677			
Sum Weight:	6.574	35.607						OTM	253.829 kip-ft	3.505		



<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 16 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

**Tower Forces - Service - Wind 60 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 154.000-134.8	0.297	1.066	A	1	0.65	0.011	1	1	44.790	0.343	0.018	C
30			B	1	0.65		1	1				
L2			C	1	0.65		1	1				
L2 134.830-89.16	2.033	5.810	A	1	0.65	0.010	1	1	136.145	0.985	0.022	C
0			B	1	0.65		1	1				
L3			C	1	0.65		1	1				
L3 89.160-44.540	2.224	12.108	A	1	0.65	0.009	1	1	172.571	1.118	0.025	C
0			B	1	0.65		1	1				
L4			C	1	0.65		1	1				
L4 44.540-1.000	2.021	16.623	A	1	0.65	0.007	1	1	204.677	1.059	0.024	C
0			B	1	0.65		1	1				
0			C	1	0.65		1	1				
Sum Weight:	6.574	35.607						OTM	253.829 kip-ft	3.505		

**Tower Forces - Service - Wind 90 To Face**

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C <sub>F</sub>	q <sub>z</sub> ksf	D <sub>F</sub>	D <sub>R</sub>	A <sub>E</sub> ft <sup>2</sup>	F K	w klf	Ctrl. Face
L1 154.000-134.8	0.297	1.066	A	1	0.65	0.011	1	1	44.790	0.343	0.018	C
30			B	1	0.65		1	1				
L2			C	1	0.65		1	1				
L2 134.830-89.16	2.033	5.810	A	1	0.65	0.010	1	1	136.145	0.985	0.022	C
0			B	1	0.65		1	1				
L3			C	1	0.65		1	1				
L3 89.160-44.540	2.224	12.108	A	1	0.65	0.009	1	1	172.571	1.118	0.025	C
0			B	1	0.65		1	1				
L4			C	1	0.65		1	1				
L4 44.540-1.000	2.021	16.623	A	1	0.65	0.007	1	1	204.677	1.059	0.024	C
0			B	1	0.65		1	1				
0			C	1	0.65		1	1				
Sum Weight:	6.574	35.607						OTM	253.829 kip-ft	3.505		

**Force Totals**

Load Case	Vertical Forces K	Sum of Forces X K	Sum of Forces Z K	Sum of Overturning Moments, M <sub>x</sub> kip-ft	Sum of Overturning Moments, M <sub>z</sub> kip-ft	Sum of Torques kip-ft
Leg Weight	35.607					

<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	17 of 27
<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b>	16:09:00 07/08/20
<b>Client</b>	T-Mobile	<b>Designed by</b>	TJL

Load Case	Vertical Forces K	Sum of Forces X K	Sum of Forces Z K	Sum of Overturning Moments, M <sub>x</sub> kip-ft	Sum of Overturning Moments, M <sub>z</sub> kip-ft	Sum of Torques kip-ft
Bracing Weight	0.000					
Total Member Self-Weight	35.607			0.124	0.163	
Total Weight	65.875			0.124	0.163	
Wind 0 deg - No Ice		0.000	-42.716	-4811.187	0.163	-0.029
Wind 30 deg - No Ice		21.306	-36.994	-4166.593	-2398.900	0.199
Wind 45 deg - No Ice		30.131	-30.205	-3401.986	-3392.625	0.296
Wind 60 deg - No Ice		36.902	-21.358	-2405.531	-4155.137	0.373
Wind 90 deg - No Ice		42.611	0.000	0.124	-4797.964	0.448
Wind 120 deg - No Ice		36.902	21.358	2405.779	-4155.137	0.402
Wind 135 deg - No Ice		30.131	30.205	3402.234	-3392.625	0.337
Wind 150 deg - No Ice		21.306	36.994	4166.841	-2398.900	0.249
Wind 180 deg - No Ice		0.000	42.716	4811.434	0.163	0.029
Wind 210 deg - No Ice		-21.306	36.994	4166.841	2399.226	-0.199
Wind 225 deg - No Ice		-30.131	30.205	3402.234	3392.951	-0.296
Wind 240 deg - No Ice		-36.902	21.358	2405.779	4155.463	-0.373
Wind 270 deg - No Ice		-42.611	0.000	0.124	4798.290	-0.448
Wind 300 deg - No Ice		-36.902	-21.358	-2405.531	4155.463	-0.402
Wind 315 deg - No Ice		-30.131	-30.205	-3401.986	3392.951	-0.337
Wind 330 deg - No Ice		-21.306	-36.994	-4166.593	2399.226	-0.249
Member Ice	18.050					
Total Weight Ice	126.179			1.395	-0.410	
Wind 0 deg - Ice		0.000	-20.421	-2295.588	-0.410	0.001
Wind 30 deg - Ice		10.199	-17.685	-1987.851	-1147.470	-0.021
Wind 45 deg - Ice		14.423	-14.440	-1622.817	-1622.598	-0.030
Wind 60 deg - Ice		17.665	-10.210	-1147.096	-1987.177	-0.037
Wind 90 deg - Ice		20.398	0.000	1.395	-2294.531	-0.043
Wind 120 deg - Ice		17.665	10.210	1149.887	-1987.177	-0.038
Wind 135 deg - Ice		14.423	14.440	1625.608	-1622.598	-0.031
Wind 150 deg - Ice		10.199	17.685	1990.641	-1147.470	-0.023
Wind 180 deg - Ice		0.000	20.421	2298.379	-0.410	-0.001
Wind 210 deg - Ice		-10.199	17.685	1990.641	1146.651	0.021
Wind 225 deg - Ice		-14.423	14.440	1625.608	1621.779	0.030
Wind 240 deg - Ice		-17.665	10.210	1149.887	1986.358	0.037
Wind 270 deg - Ice		-20.398	0.000	1.395	2293.712	0.043
Wind 300 deg - Ice		-17.665	-10.210	-1147.096	1986.358	0.038
Wind 315 deg - Ice		-14.423	-14.440	-1622.817	1621.779	0.031
Wind 330 deg - Ice		-10.199	-17.685	-1987.851	1146.651	0.023
Total Weight	65.875			0.124	0.163	
Wind 0 deg - Service		0.000	-17.371	-1956.382	0.163	-0.012
Wind 30 deg - Service		8.664	-15.043	-1694.260	-975.409	0.081
Wind 45 deg - Service		12.253	-12.283	-1383.335	-1379.505	0.120
Wind 60 deg - Service		15.006	-8.685	-978.129	-1689.578	0.152
Wind 90 deg - Service		17.328	0.000	0.124	-1950.982	0.182
Wind 120 deg - Service		15.006	8.685	978.377	-1689.578	0.164
Wind 135 deg - Service		12.253	12.283	1383.583	-1379.505	0.137
Wind 150 deg - Service		8.664	15.043	1694.508	-975.409	0.101
Wind 180 deg - Service		0.000	17.371	1956.630	0.163	0.012
Wind 210 deg - Service		-8.664	15.043	1694.508	975.736	-0.081
Wind 225 deg - Service		-12.253	12.283	1383.583	1379.831	-0.120
Wind 240 deg - Service		-15.006	8.685	978.377	1689.904	-0.152
Wind 270 deg - Service		-17.328	0.000	0.124	1951.308	-0.182
Wind 300 deg - Service		-15.006	-8.685	-978.129	1689.904	-0.164
Wind 315 deg - Service		-12.253	-12.283	-1383.335	1379.831	-0.137
Wind 330 deg - Service		-8.664	-15.043	-1694.260	975.736	-0.101

**Load Combinations**

<p style="text-align: center;"><b>tnxTower</b></p> <p style="text-align: center;"><b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587</p>	<p><b>Job</b></p> <p style="text-align: center;">20074.50 - CTNH362B</p>	<p><b>Page</b></p> <p style="text-align: center;">18 of 27</p>
	<p><b>Project</b></p> <p style="text-align: center;">153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT</p>	<p><b>Date</b></p> <p style="text-align: center;">16:09:00 07/08/20</p>
	<p><b>Client</b></p> <p style="text-align: center;">T-Mobile</p>	<p><b>Designed by</b></p> <p style="text-align: center;">TJL</p>

<i>Comb. No.</i>	<i>Description</i>
1	Dead Only
2	1.2 Dead+1.6 Wind 0 deg - No Ice
3	0.9 Dead+1.6 Wind 0 deg - No Ice
4	1.2 Dead+1.6 Wind 30 deg - No Ice
5	0.9 Dead+1.6 Wind 30 deg - No Ice
6	1.2 Dead+1.6 Wind 45 deg - No Ice
7	0.9 Dead+1.6 Wind 45 deg - No Ice
8	1.2 Dead+1.6 Wind 60 deg - No Ice
9	0.9 Dead+1.6 Wind 60 deg - No Ice
10	1.2 Dead+1.6 Wind 90 deg - No Ice
11	0.9 Dead+1.6 Wind 90 deg - No Ice
12	1.2 Dead+1.6 Wind 120 deg - No Ice
13	0.9 Dead+1.6 Wind 120 deg - No Ice
14	1.2 Dead+1.6 Wind 135 deg - No Ice
15	0.9 Dead+1.6 Wind 135 deg - No Ice
16	1.2 Dead+1.6 Wind 150 deg - No Ice
17	0.9 Dead+1.6 Wind 150 deg - No Ice
18	1.2 Dead+1.6 Wind 180 deg - No Ice
19	0.9 Dead+1.6 Wind 180 deg - No Ice
20	1.2 Dead+1.6 Wind 210 deg - No Ice
21	0.9 Dead+1.6 Wind 210 deg - No Ice
22	1.2 Dead+1.6 Wind 225 deg - No Ice
23	0.9 Dead+1.6 Wind 225 deg - No Ice
24	1.2 Dead+1.6 Wind 240 deg - No Ice
25	0.9 Dead+1.6 Wind 240 deg - No Ice
26	1.2 Dead+1.6 Wind 270 deg - No Ice
27	0.9 Dead+1.6 Wind 270 deg - No Ice
28	1.2 Dead+1.6 Wind 300 deg - No Ice
29	0.9 Dead+1.6 Wind 300 deg - No Ice
30	1.2 Dead+1.6 Wind 315 deg - No Ice
31	0.9 Dead+1.6 Wind 315 deg - No Ice
32	1.2 Dead+1.6 Wind 330 deg - No Ice
33	0.9 Dead+1.6 Wind 330 deg - No Ice
34	1.2 Dead+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 45 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
39	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
40	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
41	1.2 Dead+1.0 Wind 135 deg+1.0 Ice+1.0 Temp
42	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
43	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
44	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
45	1.2 Dead+1.0 Wind 225 deg+1.0 Ice+1.0 Temp
46	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
47	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
48	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
49	1.2 Dead+1.0 Wind 315 deg+1.0 Ice+1.0 Temp
50	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
51	Dead+Wind 0 deg - Service
52	Dead+Wind 30 deg - Service
53	Dead+Wind 45 deg - Service
54	Dead+Wind 60 deg - Service
55	Dead+Wind 90 deg - Service
56	Dead+Wind 120 deg - Service
57	Dead+Wind 135 deg - Service
58	Dead+Wind 150 deg - Service
59	Dead+Wind 180 deg - Service
60	Dead+Wind 210 deg - Service
61	Dead+Wind 225 deg - Service

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 19 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Comb. No.	Description
62	Dead+Wind 240 deg - Service
63	Dead+Wind 270 deg - Service
64	Dead+Wind 300 deg - Service
65	Dead+Wind 315 deg - Service
66	Dead+Wind 330 deg - Service

### Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	154 - 134.83	Pole	Max Tension	2	0.000	-0.001	-0.000
			Max. Compression	34	-30.290	0.449	0.129
			Max. Mx	26	-10.038	137.941	0.176
			Max. My	2	-10.032	0.311	137.759
			Max. Vy	26	-21.594	137.941	0.176
			Max. Vx	18	21.596	0.311	-137.425
			Max. Torque	18			-0.529
L2	134.83 - 89.16	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	34	-79.678	-0.377	-1.420
			Max. Mx	26	-30.438	1882.579	-0.126
			Max. My	18	-30.412	0.203	-1888.028
			Max. Vy	26	-54.213	1882.579	-0.126
			Max. Vx	18	54.388	0.203	-1888.028
			Max. Torque	11			-0.698
L3	89.16 - 44.54	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	34	-108.655	-0.377	-1.420
			Max. Mx	26	-51.365	4573.594	-0.148
			Max. My	18	-51.351	0.210	-4586.649
			Max. Vy	26	-65.468	4573.594	-0.148
			Max. Vx	18	65.642	0.210	-4586.649
			Max. Torque	11			-0.696
L4	44.54 - 1	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	34	-141.475	-0.377	-1.420
			Max. Mx	26	-78.988	7958.564	-0.150
			Max. My	18	-78.988	0.212	-7980.309
			Max. Vy	26	-68.250	7958.564	-0.150
			Max. Vx	18	68.419	0.212	-7980.309
			Max. Torque	11			-0.693

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	43	141.475	-0.000	-20.421
	Max. H <sub>x</sub>	26	79.050	68.178	-0.000
	Max. H <sub>z</sub>	2	79.050	0.000	68.346
	Max. M <sub>x</sub>	2	7979.997	0.000	68.346
	Max. M <sub>z</sub>	10	7958.142	-68.178	-0.000
	Max. Torsion	27	0.692	68.178	-0.000
	Min. Vert	15	59.288	-48.209	-48.328
	Min. H <sub>x</sub>	10	79.050	-68.178	-0.000
	Min. H <sub>z</sub>	18	79.050	0.000	-68.346
	Min. M <sub>x</sub>	18	-7980.309	0.000	-68.346

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	20 of 27
	<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b>	16:09:00 07/08/20
	<b>Client</b>	T-Mobile	<b>Designed by</b>	TJL

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
	Min. M <sub>z</sub>	26	-7958.564	68.178	-0.000
	Min. Torsion	11	-0.692	-68.178	-0.000

### Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	65.875	0.000	0.000	0.124	0.163	0.000
1.2 Dead+1.6 Wind 0 deg - No Ice	79.050	-0.000	-68.346	-7979.997	0.212	-0.083
0.9 Dead+1.6 Wind 0 deg - No Ice	59.288	0.000	-68.346	-7903.541	0.156	-0.073
1.2 Dead+1.6 Wind 30 deg - No Ice	79.050	34.089	-59.190	-6910.900	-3978.941	0.273
0.9 Dead+1.6 Wind 30 deg - No Ice	59.288	34.089	-59.190	-6844.676	-3940.848	0.284
1.2 Dead+1.6 Wind 45 deg - No Ice	79.050	48.209	-48.328	-5642.715	-5627.176	0.428
0.9 Dead+1.6 Wind 45 deg - No Ice	59.288	48.209	-48.328	-5588.650	-5573.280	0.438
1.2 Dead+1.6 Wind 60 deg - No Ice	79.050	59.044	-34.173	-3989.970	-6891.923	0.554
0.9 Dead+1.6 Wind 60 deg - No Ice	59.288	59.044	-34.173	-3951.751	-6825.900	0.563
1.2 Dead+1.6 Wind 90 deg - No Ice	79.050	68.178	0.000	0.150	-7958.142	0.687
0.9 Dead+1.6 Wind 90 deg - No Ice	59.288	68.178	0.000	0.111	-7881.912	0.692
1.2 Dead+1.6 Wind 120 deg - No Ice	79.050	59.044	34.173	3990.273	-6891.928	0.635
0.9 Dead+1.6 Wind 120 deg - No Ice	59.288	59.044	34.173	3951.975	-6825.904	0.635
1.2 Dead+1.6 Wind 135 deg - No Ice	79.050	48.209	48.328	5643.021	-5627.182	0.543
0.9 Dead+1.6 Wind 135 deg - No Ice	59.288	48.209	48.328	5588.876	-5573.285	0.540
1.2 Dead+1.6 Wind 150 deg - No Ice	79.050	34.089	59.190	6911.209	-3978.946	0.414
0.9 Dead+1.6 Wind 150 deg - No Ice	59.288	34.089	59.190	6844.905	-3940.852	0.408
1.2 Dead+1.6 Wind 180 deg - No Ice	79.050	-0.000	68.346	7980.309	0.212	0.083
0.9 Dead+1.6 Wind 180 deg - No Ice	59.288	0.000	68.346	7903.771	0.156	0.073
1.2 Dead+1.6 Wind 210 deg - No Ice	79.050	-34.089	59.190	6911.208	3979.369	-0.271
0.9 Dead+1.6 Wind 210 deg - No Ice	59.288	-34.089	59.190	6844.904	3941.163	-0.282
1.2 Dead+1.6 Wind 225 deg - No Ice	79.050	-48.209	48.328	5643.020	5627.605	-0.426
0.9 Dead+1.6 Wind 225 deg - No Ice	59.288	-48.209	48.328	5588.875	5573.595	-0.436
1.2 Dead+1.6 Wind 240 deg - No Ice	79.050	-59.044	34.173	3990.272	6892.350	-0.552
0.9 Dead+1.6 Wind 240 deg - No Ice	59.288	-59.044	34.173	3951.974	6826.214	-0.562

<p style="text-align: center;"><b>tnxTower</b></p> <p style="text-align: center;"><b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587</p>	<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	21 of 27	
	<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT		<b>Date</b>	16:09:00 07/08/20
	<b>Client</b>	T-Mobile		<b>Designed by</b>	TJL

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
1.2 Dead+1.6 Wind 270 deg - No Ice	79.050	-68.178	0.000	0.150	7958.564	-0.687
0.9 Dead+1.6 Wind 270 deg - No Ice	59.288	-68.178	0.000	0.111	7882.222	-0.692
1.2 Dead+1.6 Wind 300 deg - No Ice	79.050	-59.044	-34.173	-3989.969	6892.345	-0.637
0.9 Dead+1.6 Wind 300 deg - No Ice	59.288	-59.044	-34.173	-3951.750	6826.211	-0.637
1.2 Dead+1.6 Wind 315 deg - No Ice	79.050	-48.209	-48.328	-5642.714	5627.599	-0.545
0.9 Dead+1.6 Wind 315 deg - No Ice	59.288	-48.209	-48.328	-5588.649	5573.591	-0.542
1.2 Dead+1.6 Wind 330 deg - No Ice	79.050	-34.089	-59.190	-6910.899	3979.364	-0.416
0.9 Dead+1.6 Wind 330 deg - No Ice	59.288	-34.089	-59.190	-6844.676	3941.159	-0.410
1.2 Dead+1.0 Ice+1.0 Temp	141.475	0.000	0.000	1.420	-0.377	0.000
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	141.475	0.000	-20.421	-2500.911	-0.447	-0.008
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	141.475	10.199	-17.685	-2165.627	-1250.180	-0.031
1.2 Dead+1.0 Wind 45 deg+1.0 Ice+1.0 Temp	141.475	14.423	-14.440	-1767.937	-1767.857	-0.039
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	141.475	17.665	-10.210	-1249.613	-2165.049	-0.045
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	141.475	20.398	0.000	1.684	-2499.913	-0.047
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	141.475	17.665	10.210	1252.981	-2165.047	-0.037
1.2 Dead+1.0 Wind 135 deg+1.0 Ice+1.0 Temp	141.475	14.423	14.440	1771.304	-1767.855	-0.028
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	141.475	10.199	17.685	2168.992	-1250.179	-0.017
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	141.475	0.000	20.421	2504.275	-0.447	0.008
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	141.475	-10.199	17.685	2168.993	1249.285	0.031
1.2 Dead+1.0 Wind 225 deg+1.0 Ice+1.0 Temp	141.475	-14.423	14.440	1771.305	1766.962	0.039
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	141.475	-17.665	10.210	1252.981	2164.154	0.045
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	141.475	-20.398	0.000	1.684	2499.020	0.047
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	141.475	-17.665	-10.210	-1249.614	2164.156	0.037
1.2 Dead+1.0 Wind 315 deg+1.0 Ice+1.0 Temp	141.475	-14.423	-14.440	-1767.938	1766.964	0.028
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp	141.475	-10.199	-17.685	-2165.627	1249.287	0.016
Dead+ Wind 0 deg - Service	65.875	0.000	-17.371	-2018.674	0.174	-0.020
Dead+ Wind 30 deg - Service	65.875	8.664	-15.043	-1748.206	-1006.460	0.072
Dead+ Wind 45 deg - Service	65.875	12.253	-12.283	-1427.380	-1423.422	0.112
Dead+ Wind 60 deg - Service	65.875	15.006	-8.685	-1009.272	-1743.368	0.144
Dead+ Wind 90 deg - Service	65.875	17.328	0.000	0.131	-2013.096	0.178
Dead+ Wind 120 deg - Service	65.875	15.006	8.685	1009.534	-1743.369	0.164
Dead+ Wind 135 deg - Service	65.875	12.253	12.283	1427.642	-1423.422	0.140
Dead+ Wind 150 deg - Service	65.875	8.664	15.043	1748.468	-1006.460	0.106
Dead+ Wind 180 deg - Service	65.875	0.000	17.371	2018.936	0.174	0.020
Dead+ Wind 210 deg - Service	65.875	-8.664	15.043	1748.468	1006.809	-0.072
Dead+ Wind 225 deg - Service	65.875	-12.253	12.283	1427.642	1423.771	-0.112
Dead+ Wind 240 deg - Service	65.875	-15.006	8.685	1009.534	1743.717	-0.144

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 22 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead+Wind 270 deg - Service	65.875	-17.328	0.000	0.131	2013.444	-0.178
Dead+Wind 300 deg - Service	65.875	-15.006	-8.685	-1009.272	1743.717	-0.164
Dead+Wind 315 deg - Service	65.875	-12.253	-12.283	-1427.380	1423.771	-0.140
Dead+Wind 330 deg - Service	65.875	-8.664	-15.043	-1748.206	1006.809	-0.106

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.000	-65.875	0.000	0.000	65.875	0.000	0.000%
2	0.000	-79.050	-68.346	0.000	79.050	68.346	0.000%
3	0.000	-59.288	-68.346	0.000	59.288	68.346	0.000%
4	34.089	-79.050	-59.190	-34.089	79.050	59.190	0.000%
5	34.089	-59.288	-59.190	-34.089	59.288	59.190	0.000%
6	48.209	-79.050	-48.328	-48.209	79.050	48.328	0.000%
7	48.209	-59.288	-48.328	-48.209	59.288	48.328	0.000%
8	59.044	-79.050	-34.173	-59.044	79.050	34.173	0.000%
9	59.044	-59.288	-34.173	-59.044	59.288	34.173	0.000%
10	68.178	-79.050	0.000	-68.178	79.050	-0.000	0.000%
11	68.178	-59.288	0.000	-68.178	59.288	-0.000	0.000%
12	59.044	-79.050	34.173	-59.044	79.050	-34.173	0.000%
13	59.044	-59.288	34.173	-59.044	59.288	-34.173	0.000%
14	48.209	-79.050	48.328	-48.209	79.050	-48.328	0.000%
15	48.209	-59.288	48.328	-48.209	59.288	-48.328	0.000%
16	34.089	-79.050	59.190	-34.089	79.050	-59.190	0.000%
17	34.089	-59.288	59.190	-34.089	59.288	-59.190	0.000%
18	0.000	-79.050	68.346	0.000	79.050	-68.346	0.000%
19	0.000	-59.288	68.346	0.000	59.288	-68.346	0.000%
20	-34.089	-79.050	59.190	34.089	79.050	-59.190	0.000%
21	-34.089	-59.288	59.190	34.089	59.288	-59.190	0.000%
22	-48.209	-79.050	48.328	48.209	79.050	-48.328	0.000%
23	-48.209	-59.288	48.328	48.209	59.288	-48.328	0.000%
24	-59.044	-79.050	34.173	59.044	79.050	-34.173	0.000%
25	-59.044	-59.288	34.173	59.044	59.288	-34.173	0.000%
26	-68.178	-79.050	0.000	68.178	79.050	-0.000	0.000%
27	-68.178	-59.288	0.000	68.178	59.288	-0.000	0.000%
28	-59.044	-79.050	-34.173	59.044	79.050	34.173	0.000%
29	-59.044	-59.288	-34.173	59.044	59.288	34.173	0.000%
30	-48.209	-79.050	-48.328	48.209	79.050	48.328	0.000%
31	-48.209	-59.288	-48.328	48.209	59.288	48.328	0.000%
32	-34.089	-79.050	-59.190	34.089	79.050	59.190	0.000%
33	-34.089	-59.288	-59.190	34.089	59.288	59.190	0.000%
34	0.000	-141.475	0.000	0.000	141.475	0.000	0.000%
35	0.000	-141.475	-20.421	-0.000	141.475	20.421	0.000%
36	10.199	-141.475	-17.685	-10.199	141.475	17.685	0.000%
37	14.423	-141.475	-14.440	-14.423	141.475	14.440	0.000%
38	17.665	-141.475	-10.210	-17.665	141.475	10.210	0.000%
39	20.398	-141.475	0.000	-20.398	141.475	-0.000	0.000%
40	17.665	-141.475	10.210	-17.665	141.475	-10.210	0.000%
41	14.423	-141.475	14.440	-14.423	141.475	-14.440	0.000%
42	10.199	-141.475	17.685	-10.199	141.475	-17.685	0.000%
43	0.000	-141.475	20.421	-0.000	141.475	-20.421	0.000%
44	-10.199	-141.475	17.685	10.199	141.475	-17.685	0.000%
45	-14.423	-141.475	14.440	14.423	141.475	-14.440	0.000%
46	-17.665	-141.475	10.210	17.665	141.475	-10.210	0.000%
47	-20.398	-141.475	0.000	20.398	141.475	-0.000	0.000%
48	-17.665	-141.475	-10.210	17.665	141.475	10.210	0.000%

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	23 of 27
	<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b>	16:09:00 07/08/20
	<b>Client</b>	T-Mobile	<b>Designed by</b>	TJL

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
49	-14.423	-141.475	-14.440	14.423	141.475	14.440	0.000%
50	-10.199	-141.475	-17.685	10.199	141.475	17.685	0.000%
51	0.000	-65.875	-17.371	0.000	65.875	17.371	0.000%
52	8.664	-65.875	-15.043	-8.664	65.875	15.043	0.000%
53	12.253	-65.875	-12.283	-12.253	65.875	12.283	0.000%
54	15.006	-65.875	-8.685	-15.006	65.875	8.685	0.000%
55	17.328	-65.875	0.000	-17.328	65.875	0.000	0.000%
56	15.006	-65.875	8.685	-15.006	65.875	-8.685	0.000%
57	12.253	-65.875	12.283	-12.253	65.875	-12.283	0.000%
58	8.664	-65.875	15.043	-8.664	65.875	-15.043	0.000%
59	0.000	-65.875	17.371	0.000	65.875	-17.371	0.000%
60	-8.664	-65.875	15.043	8.664	65.875	-15.043	0.000%
61	-12.253	-65.875	12.283	12.253	65.875	-12.283	0.000%
62	-15.006	-65.875	8.685	15.006	65.875	-8.685	0.000%
63	-17.328	-65.875	0.000	17.328	65.875	0.000	0.000%
64	-15.006	-65.875	-8.685	15.006	65.875	8.685	0.000%
65	-12.253	-65.875	-12.283	12.253	65.875	12.283	0.000%
66	-8.664	-65.875	-15.043	8.664	65.875	15.043	0.000%

## Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.0000001	0.0000001
2	Yes	4	0.0000001	0.00025219
3	Yes	4	0.0000001	0.00010686
4	Yes	6	0.0000001	0.00005124
5	Yes	5	0.0000001	0.00049416
6	Yes	6	0.0000001	0.00005315
7	Yes	5	0.0000001	0.00051132
8	Yes	6	0.0000001	0.00005094
9	Yes	5	0.0000001	0.00049107
10	Yes	4	0.0000001	0.00035220
11	Yes	4	0.0000001	0.00018515
12	Yes	6	0.0000001	0.00005151
13	Yes	5	0.0000001	0.00049692
14	Yes	6	0.0000001	0.00005315
15	Yes	5	0.0000001	0.00051128
16	Yes	6	0.0000001	0.00005090
17	Yes	5	0.0000001	0.00049075
18	Yes	4	0.0000001	0.00025217
19	Yes	4	0.0000001	0.00010686
20	Yes	6	0.0000001	0.00005113
21	Yes	5	0.0000001	0.00049286
22	Yes	6	0.0000001	0.00005317
23	Yes	5	0.0000001	0.00051142
24	Yes	6	0.0000001	0.00005142
25	Yes	5	0.0000001	0.00049597
26	Yes	4	0.0000001	0.00035227
27	Yes	4	0.0000001	0.00018517
28	Yes	6	0.0000001	0.00005085
29	Yes	5	0.0000001	0.00049014
30	Yes	6	0.0000001	0.00005318
31	Yes	5	0.0000001	0.00051150
32	Yes	6	0.0000001	0.00005146
33	Yes	5	0.0000001	0.00049631



<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b>	20074.50 - CTNH362B	<b>Page</b>	24 of 27
	<b>Project</b>	153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b>	16:09:00 07/08/20
	<b>Client</b>	T-Mobile	<b>Designed by</b>	TJL

34	Yes	4	0.00000001	0.00000001
35	Yes	5	0.00000001	0.00051228
36	Yes	5	0.00000001	0.00092838
37	Yes	6	0.00000001	0.00011676
38	Yes	5	0.00000001	0.00093099
39	Yes	5	0.00000001	0.00051262
40	Yes	5	0.00000001	0.00093261
41	Yes	6	0.00000001	0.00011730
42	Yes	5	0.00000001	0.00093426
43	Yes	5	0.00000001	0.00051377
44	Yes	5	0.00000001	0.00093434
45	Yes	6	0.00000001	0.00011719
46	Yes	5	0.00000001	0.00093113
47	Yes	5	0.00000001	0.00051223
48	Yes	5	0.00000001	0.00092947
49	Yes	6	0.00000001	0.00011664
50	Yes	5	0.00000001	0.00092841
51	Yes	4	0.00000001	0.00005112
52	Yes	4	0.00000001	0.00079402
53	Yes	4	0.00000001	0.00091130
54	Yes	4	0.00000001	0.00078272
55	Yes	4	0.00000001	0.00005576
56	Yes	4	0.00000001	0.00080423
57	Yes	4	0.00000001	0.00091181
58	Yes	4	0.00000001	0.00078229
59	Yes	4	0.00000001	0.00005114
60	Yes	4	0.00000001	0.00079111
61	Yes	4	0.00000001	0.00091311
62	Yes	4	0.00000001	0.00080103
63	Yes	4	0.00000001	0.00005578
64	Yes	4	0.00000001	0.00077989
65	Yes	4	0.00000001	0.00091309
66	Yes	4	0.00000001	0.00080323

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	154 - 134.83	29.861	59	1.677	0.001
L2	139.16 - 89.16	24.681	59	1.643	0.001
L3	94.83 - 44.54	11.224	59	1.139	0.000
L4	51.46 - 1	3.220	59	0.585	0.000

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
156.000	HP2-4.7	59	29.861	1.677	0.001	29731
154.000	BA40-41	59	29.861	1.677	0.001	29731
150.000	EEI Pine Branches	59	28.454	1.672	0.001	29731
142.000	Monopole Sector Stabilizer Kit VSK-M	59	25.660	1.654	0.001	12423
140.000	EEI Pine Branches	59	24.969	1.647	0.001	10805
130.000	EEI Pine Branches	59	21.592	1.581	0.001	7668

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 25 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
120.000	EEI Pine Branches	59	18.371	1.478	0.000	6103
110.000	EEI Pine Branches	59	15.346	1.351	0.000	5064
100.000	EEI Pine Branches	59	12.559	1.211	0.000	4324
90.000	EEI Pine Branches	59	10.048	1.072	0.000	3993
80.000	EEI Pine Branches	59	7.838	0.939	0.000	3937

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	154 - 134.83	117.984	18	6.635	0.004
L2	139.16 - 89.16	97.530	18	6.500	0.003
L3	94.83 - 44.54	44.376	18	4.505	0.001
L4	51.46 - 1	12.734	18	2.316	0.000

### Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
156.000	HP2-4.7	18	117.984	6.635	0.004	7742
154.000	BA40-41	18	117.984	6.635	0.004	7742
150.000	EEI Pine Branches	18	112.428	6.616	0.004	7742
142.000	Monopole Sector Stabilizer Kit VSK-M	18	101.396	6.546	0.003	3233
140.000	EEI Pine Branches	18	98.670	6.515	0.003	2811
130.000	EEI Pine Branches	18	85.333	6.256	0.002	1986
120.000	EEI Pine Branches	18	72.611	5.849	0.002	1573
110.000	EEI Pine Branches	18	60.663	5.345	0.001	1302
100.000	EEI Pine Branches	18	49.651	4.793	0.001	1109
90.000	EEI Pine Branches	18	39.730	4.242	0.001	1021
80.000	EEI Pine Branches	18	30.992	3.716	0.001	1004

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio $\frac{P_u}{\phi P_n}$
L1	154 - 134.83 (1)	TP30.03x25.25x0.188	19.170	0.000	0.0	17.118	-10.036	1101.640	0.009
L2	134.83 - 89.16 (2)	TP40.91x28.575x0.313	50.000	0.000	0.0	38.880	-30.412	2704.810	0.011
L3	89.16 - 44.54	TP51.28x38.886x0.5	50.290	0.000	0.0	77.881	-51.351	5786.200	0.009

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 26 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJL

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio $\frac{P_u}{\phi P_n}$
L4	44.54 - 1 (4) (3)	TP61x48.575x0.563	50.460	0.000	0.0	107.904	-78.988	7868.290	0.010

### Pole Bending Design Data

Section No.	Elevation ft	Size	M <sub>ux</sub> kip-ft	φM <sub>ux</sub> kip-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	M <sub>uy</sub> kip-ft	φM <sub>uy</sub> kip-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
L1	154 - 134.83 (1)	TP30.03x25.25x0.188	137.980	652.443	0.211	0.000	652.443	0.000
L2	134.83 - 89.16 (2)	TP40.91x28.575x0.313	1888.025	2179.983	0.866	0.000	2179.983	0.000
L3	89.16 - 44.54 (3)	TP51.28x38.886x0.5	4586.650	5825.591	0.787	0.000	5825.591	0.000
L4	44.54 - 1 (4)	TP61x48.575x0.563	7980.308	9764.667	0.817	0.000	9764.667	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V <sub>u</sub> K	φV <sub>n</sub> K	Ratio $\frac{V_u}{\phi V_n}$	Actual T <sub>u</sub> kip-ft	φT <sub>n</sub> kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	154 - 134.83 (1)	TP30.03x25.25x0.188	21.594	550.821	0.039	0.373	1307.767	0.000
L2	134.83 - 89.16 (2)	TP40.91x28.575x0.313	54.388	1352.410	0.040	0.083	4370.550	0.000
L3	89.16 - 44.54 (3)	TP51.28x38.886x0.5	65.642	2893.100	0.023	0.083	11683.333	0.000
L4	44.54 - 1 (4)	TP61x48.575x0.563	68.419	3934.150	0.017	0.083	19580.583	0.000

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio $\frac{P_u}{\phi P_n}$	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	Ratio $\frac{M_{uy}}{\phi M_{uy}}$	Ratio $\frac{V_u}{\phi V_n}$	Ratio $\frac{T_u}{\phi T_n}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	154 - 134.83 (1)	0.009	0.211	0.000	0.039	0.000	0.222	1.000	4.8.2 ✓
L2	134.83 - 89.16 (2)	0.011	0.866	0.000	0.040	0.000	0.879	1.000	4.8.2 ✓
L3	89.16 - 44.54 (3)	0.009	0.787	0.000	0.023	0.000	0.797	1.000	4.8.2 ✓
L4	44.54 - 1 (4)	0.010	0.817	0.000	0.017	0.000	0.828	1.000	4.8.2 ✓

<b>tnxTower</b>  <b>Centek Engineering Inc.</b> 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587	<b>Job</b> 20074.50 - CTNH362B	<b>Page</b> 27 of 27
	<b>Project</b> 153-ft EEI Monopine - 33 Boardman Rd., New Milford, CT	<b>Date</b> 16:09:00 07/08/20
	<b>Client</b> T-Mobile	<b>Designed by</b> TJJ

## Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail
L1	154 - 134.83	Pole	TP30.03x25.25x0.188	1	-10.036	1101.640	22.2	Pass
L2	134.83 - 89.16	Pole	TP40.91x28.575x0.313	2	-30.412	2704.810	87.9	Pass
L3	89.16 - 44.54	Pole	TP51.28x38.886x0.5	3	-51.351	5786.200	79.7	Pass
L4	44.54 - 1	Pole	TP61x48.575x0.563	4	-78.988	7868.290	82.8	Pass
Summary								
Pole (L2)							87.9	Pass
<b>RATING =</b>							<b>87.9</b>	<b>Pass</b>

**Anchor Bolt and Base Plate Analysis:**

**Input Data:**

Tower Reactions:

Overturing Moment =	$M_U := 7980$ -ft-kips	(Input From trnTower)
Shear Force =	Shear := 68-kips	(Input From trnTower)
Axial Force =	$R_U := 79$ -kips	(Input From trnTower)

Anchor Bolt Data:

ASTMA615 Grade 75		
Number of Anchor Bolts =	$N := 28$	(User Input)
Diameter of Bolt Circle =	$D_{BC} := 68.0$ -in	(User Input)
Bolt "Column" Distance =	$l := 3.0$ -in	(User Input)
Bolt Ultimate Strength =	$F_U := 100$ -ksi	(User Input)
Bolt Yield Strength =	$F_y := 75$ -ksi	(User Input)
Bolt Modulus =	$E := 29000$ -ksi	(User Input)
Diameter of Anchor Bolts =	$D := 2.25$ -in	(User Input)
Threads per Inch =	$n := 4.5$	(User Input)
Top of Concrete to Bot Leveling Nut =	$l_{ar} := 2$ -in	(User Input)
Anchor Rod Force Correction Factor =	$n_c = 1$	Table 2-1 Addendum 3

Base Plate Data:

UseASTMA572 Grade 60		
Plate Yield Strength =	$F_{yf} := 60$ -ksi	(User Input)
Base Plate Thickness =	$t_{TP} := 3$ -in	(User Input)
Base Plate Diameter =	$D_{OD} := 74$ -in	(User Input)
Outer Pole Diameter =	$D_T := 61$ -in	(User Input)
Pole Wall Thickness =	$t_T := 0.5625$ -in	(User Input)
Pole Design Yield Strength =	$F_{yp} := 65$ -ksi	(User Input)
	$\eta := 0.5$	For Ungrouted Base Plate per TIA-222-G Section 4.9.9

**Anchor Bolt Analysis:**

GrossArea of Bolt =  $A_g := \frac{\pi}{4} \cdot D^2 = 3.976 \cdot \text{in}^2$

NetArea of Bolt =  $A_n := \frac{\pi}{4} \cdot \left( D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 = 3.248 \cdot \text{in}^2$

Tensile Root Diameter =  $d_{rt} := D - \frac{0.9743 \cdot \text{in}}{n} = 2.033 \cdot \text{in}$

Plastic Section Modulus =  $Z := \frac{d_{rt}^3}{6} = 1.401 \cdot \text{in}^3$

Maximum Anchor Rod Force =  $P_u := \frac{n_c \cdot \pi \cdot M_u}{N \cdot D_{BC}} + \frac{R_u}{N} = 160.8 \cdot \text{kips}$

Maximum Shear Force =  $V_u := \frac{\text{Shear}}{N} = 2.4 \cdot \text{kips}$

Design Tensile Strength =  $\Phi R_{nt} := 0.8 \cdot F_u \cdot A_n = 259.815 \cdot \text{k}$

Bolt % of Capacity =  $\frac{\left( P_u + \frac{V_u}{\eta} \right)}{\Phi R_{nt}} \cdot 100 = 63.8$

Condition1 =  $\text{Condition1} := \text{if} \left[ \frac{\left( P_u + \frac{V_u}{\eta} \right)}{\Phi R_{nt}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right]$

Condition1 = "OK"

Design Shear Strength =  $\Phi R_{nv} := 0.75 \cdot 0.45 \cdot F_u \cdot A_g = 134.193 \cdot \text{k}$

Design Flexural Strength =  $\Phi R_{nm} := 0.9 \cdot F_y \cdot Z = 94.597 \cdot \text{in} \cdot \text{k}$

$M_u := \begin{cases} 0 & \text{if } l_{ar} < D \\ 0.65 \cdot l_{ar} \cdot V_u & \text{otherwise} \end{cases} = 0 \cdot \text{in} \cdot \text{k}$

Bolt % of Capacity =  $\left[ \left( \frac{V_u}{\Phi R_{nv}} \right)^2 + \left( \frac{P_u}{\Phi R_{nt}} + \frac{M_u}{\Phi R_{nm}} \right)^2 \right] \cdot 100 = 38.3$

Condition2 =  $\text{Condition2} := \text{if} \left[ \left( \frac{V_u}{\Phi R_{nv}} \right)^2 + \left( \frac{P_u}{\Phi R_{nt}} + \frac{M_u}{\Phi R_{nm}} \right)^2 \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right]$

Condition2 = "OK"

**Base Plate Analysis:**

Strength Resistance Factor for Yielding due to Bending =

$$\phi_b := 0.9$$

Strength Resistance Factor for Yielding due to Shear =

$$\phi_v := 1.0$$

Outside Fillet Horizontal Leg Dimension =

$$w_1 := 0.25 \text{ in}$$

Effective Pole Outside Diameter =

$$D_e := D_T + w_1 = 61.25 \text{ in}$$

Effective Base Plate Outside Diameter =

$$D_{oe} := \begin{cases} D_{OD} & \text{if } D_{OD} \leq (D_{BC} + 6 \cdot t_{TP}) \\ (D_{BC} + 6 \cdot t_{TP}) & \text{otherwise} \end{cases} = 74 \text{ in}$$

Half-Angle Between Radial Lines Extending from Pole  
 Centerline Through Midpoints Between Adjacent Anchor

$$\theta_1 := \frac{\pi}{N} = 0.112$$

Rods =

Angle Defining Limiting Effective Base Plate Width  
 Based on Plate Thickness =

$$\theta_2 := \text{asin}\left(\frac{12 \cdot t_{TP}}{D_{BC}}\right) = 0.558$$

Angle Defining Limiting Effective Base Plate Width  
 Based on Distance Between Anchor Rod Bolt Circle and  
 Effective Pole Outside Diameter =

$$\theta_3 := \text{acos}\left(\frac{D_{BC} + D_e}{2 \cdot D_{BC}}\right) = 0.316$$

Governing Angle Defining Effective Base Plate Width  
 Resisting Bending =

$$\theta := \min(\theta_1, \theta_2, \theta_3) = 0.112$$

Effective Moment Arm of Anchor Rod Force =

$$x := 0.5 \cdot (D_{BC} - D_e) = 3.375 \text{ in}$$

Effective Base Plate Width Resisting Bending from  
 Transverse Bend Line =

$$B_{et} := D_{BC} \cdot \sin(\theta) = 7.614 \text{ in}$$

Effective Base Plate Width Resisting Bending from  
 Radial Bend Lines =

$$B_{er} := (D_{oe} - D_e) \cdot \sin(\theta) = 1.428 \text{ in}$$

Total Effective Base Plate Width Resisting Bending =

$$B_{eff} := B_{et} + B_{er} = 9.041 \text{ in}$$

Required Base Plate Thickness =

$$t_{TP,Req} := \sqrt{\frac{4 \cdot P_u \cdot x}{\phi_b \cdot F_{yf} \cdot B_{eff}}} = 2.109 \text{ in}$$

Plate Bending Stress % of Capacity =

$$\frac{t_{TP,Req}}{t_{TP}} = 70.3\%$$

Condition2 =

$$\text{Condition3} := \text{if}\left(\frac{t_{TP,Req}}{t_{TP}} < 1.00, \text{"Ok"}, \text{"Overstressed"}\right)$$

Condition3 = "Ok"

Required Base Plate Thickness =

$$t_{TP,Req} := \frac{\phi_b \cdot t_T \cdot F_{yp}}{\phi_v \cdot 0.6 \cdot F_{yf}} = 0.914 \text{ in}$$

Plate Bending Stress % of Capacity =

$$\frac{t_{TP,Req}}{t_{TP}} = 30.5\%$$

Condition2 =

$$\text{Condition4} := \text{if}\left(\frac{t_{TP,Req}}{t_{TP}} < 1.00, \text{"Ok"}, \text{"Overstressed"}\right)$$

Condition4 = "Ok"

**Standard Monopole Foundation:**

**Input Data:**

Tower Data

Overturing Moment = OM := 7980-ft-kips (User Input)  
 Shear Force = Shear := 68-kip (User Input)  
 Axial Force = Axial := 79-kip (User Input)  
 Tower Height =  $H_t := 153$ -ft (User Input)

Footing Data:

Overall Depth of Footing =  $D_f := 6.5$ -ft (User Input)  
 Length of Pier =  $L_p := 3.5$ -ft (User Input)  
 Extension of Pier Above Grade =  $L_{pag} := 1$ -ft (User Input)  
 Diameter of Pier =  $d_p := 7.5$ -ft (User Input)  
 Thickness of Footing =  $T_f := 4$ -ft (User Input)  
 Width of Footing =  $W_f := 32$ -ft (User Input)

Anchor Bolt Data:

Length of Anchor Bolts =  $L_{st} := 96$ -in (User Input)  
 Projection of Anchor Bolts Above Pier =  $A_{BP} := 12$ -in (User Input)  
 Anchor Bolt Diameter =  $d_{anchor} := 2.25$ -in (User Input)  
 Base Plate Bolt Circle =  $MP := 68$ -in (User Input)

Material Properties:

Concrete Compressive Strength =  $f_c := 3000$ -psi (User Input)  
 Steel Reinforcement Yield Strength =  $f_y := 60000$ -psi (User Input)  
 Anchor Bolt Yield Strength =  $f_{ya} := 75000$ -psi (User Input)  
 Internal Friction Angle of Soil =  $\Phi_s := 10$ -deg (User Input)  
 Ultimate Soil Bearing Capacity =  $q_u := 12000$ -psf (User Input)  
 Allowable Soil Bearing Capacity =  $q_a := \frac{q_u}{2} = 6000$ -psf (User Input)  
 Unit Weight of Soil =  $\gamma_{soil} := 100$ -pcf (User Input)  
 Unit Weight of Concrete =  $\gamma_{conc} := 150$ -pcf (User Input)  
 Foundation Bouyancy = Bouyancy := 0 (User Input) (Yes=1 / No=0)  
 Depth to Neglect =  $n := 0$ -ft (User Input)  
 Cohesion of Clay Type Soil =  $c := 0$ -ksf (User Input) (Use 0 for Sandy Soil)  
 Seismic Zone Factor =  $Z := 2$  (User Input) (UBC-1997 Fig 23-2)  
 Coefficient of Friction Between Concrete =  $\mu := 0.45$  (User Input)



Pier Reinforcement:

Bar Size =	BS <sub>pier</sub> := 11	(User Input)	
Bar Diameter =	d <sub>b</sub> pier := 1.41·in	(User Input)	
Number of Bars =	NB <sub>pier</sub> := 36	(User Input)	
Clear Cover of Reinforcement =	Cvr <sub>pier</sub> := 3-in	(User Input)	
Reinforcement Location Factor =	α <sub>pier</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)
Coating Factor =	β <sub>pier</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)
Concrete Strength Factor =	λ <sub>pier</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)
Reinforcement Size Factor =	γ <sub>pier</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)
Diameter of Tie =	d <sub>Tie</sub> := 3-in	(User Input)	

Pad Reinforcement:

Bar Size =	BS <sub>top</sub> := 11	(User Input)	(Top of Pad)
Bar Diameter =	d <sub>b</sub> top := 1.41·in	(User Input)	(Top of Pad)
Number of Bars =	NB <sub>top</sub> := 42	(User Input)	(Top of Pad)
Bar Size =	BS <sub>bot</sub> := 11	(User Input)	(Bottom of Pad)
Bar Diameter =	d <sub>b</sub> bot := 1.41·in	(User Input)	(Bottom of Pad)
Number of Bars =	NB <sub>bot</sub> := 42	(User Input)	(Bottom of Pad)
Clear Cover of Reinforcement =	Cvr <sub>pad</sub> := 3.0·in	(User Input)	
Reinforcement Location Factor =	α <sub>pad</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)
Coating Factor =	β <sub>pad</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)
Concrete Strength Factor =	λ <sub>pad</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)
Reinforcement Size Factor =	γ <sub>pad</sub> := 1.0	(User Input)	(ACI-2008 12.2.4)

**Calculated Factors:**

Pier Reinforcement Bar Area =	$A_{b\text{pier}} := \frac{\pi \cdot d_{b\text{pier}}^2}{4} = 1.561 \cdot \text{in}^2$
Pad Top Reinforcement Bar Area =	$A_{b\text{top}} := \frac{\pi \cdot d_{b\text{top}}^2}{4} = 1.561 \cdot \text{in}^2$
Pad Bottom Reinforcement Bar Area =	$A_{b\text{bot}} := \frac{\pi \cdot d_{b\text{bot}}^2}{4} = 1.561 \cdot \text{in}^2$
Coefficient of Lateral Soil Pressure =	$K_p := \frac{1 + \sin(\Phi_s)}{1 - \sin(\Phi_s)} = 1.42$

**Stability of Footing:**

Adjusted Concrete Unit Weight =

$$\gamma_c := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{conc}} - 62.4\text{pcf}, \gamma_{\text{conc}}) = 150\text{-pcf}$$

Adjusted Soil Unit Weight =

$$\gamma_s := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{soil}} - 62.4\text{pcf}, \gamma_{\text{soil}}) = 100\text{-pcf}$$

Passive Pressure =

$$P_{pn} := K_p \cdot \gamma_s \cdot n + c \cdot 2 \cdot \sqrt{K_p} = 0\text{-ksf}$$

$$P_{pt} := K_p \cdot \gamma_s \cdot (D_f - T_f) + c \cdot 2 \cdot \sqrt{K_p} = 0.355\text{-ksf}$$

$$P_{top} := \text{if}[n < (D_f - T_f), P_{pt}, P_{pn}] = 0.355\text{-ksf}$$

$$P_{bot} := K_p \cdot \gamma_s \cdot D_f + c \cdot 2 \cdot \sqrt{K_p} = 0.923\text{-ksf}$$

$$P_{ave} := \frac{P_{top} + P_{bot}}{2} = 0.639\text{-ksf}$$

$$T_p := \text{if}[n < (D_f - T_f), T_f, (D_f - n)] = 4$$

$$A_p := W_f \cdot T_p = 128$$

Ultimate Shear =

$$S_u := P_{ave} \cdot A_p = 81.808\text{-kip}$$

Weight of Concrete Pad =

$$WT_c := \left[ (W_f^2 \cdot T_f) + d_p^2 \cdot L_p \right] \cdot \gamma_c = 643.931\text{-kip}$$

Weight of Soil Above Footing =

$$WT_{s1} := \left[ (W_f^2 - d_p^2) \cdot (L_p - L_{pag} - n) \right] \cdot \gamma_s = 241.94\text{-kip}$$

Weight of Soil Wedge at Back Face =

$$WT_{s2} := \left( \frac{D_f^2 \cdot \tan(\phi_s)}{2} \cdot W_f \right) \cdot \gamma_s = 11.92\text{-kip}$$

Weight of Soil Wedge at back face Corners =

$$WT_{s3} := 2 \cdot \left[ (D_f)^3 \cdot \frac{\tan(\phi_s)}{3} \right] \cdot \gamma_s = 3.228\text{-kips}$$

Total Weight =

$$WT_{tot} := WT_c + WT_{s1} + \text{Axial} = 964.869\text{-kip}$$

Resisting Weight =

$$WT_R := 0.9 \cdot WT_c + 0.75 \cdot WT_{s1} + 0.75 \cdot \text{Axial} = 820.241\text{-kip}$$

Resisting Moment =

$$M_r := (WT_R) \cdot \frac{W_f}{2} + 0.75 \cdot S_u \cdot \frac{T_f}{3} + 0.75 \cdot \left[ (WT_{s2} + WT_{s3}) \cdot \left( W_f + \frac{D_f \cdot \tan(\phi_s)}{3} \right) \right] = 13574\text{-kip-ft}$$

Overtuning Moment =

$$M_{ot} := \text{OM} + \text{Shear} \cdot (L_p + T_f) = 8490\text{-kip-ft}$$

Factor of Safety Actual =

$$FS := \frac{M_r}{M_{ot}} = 1.6$$

Factor of Safety Required =

$$FS_{req} := 1$$

$$\text{OverTurning\_Moment\_Check} := \text{if}(FS \geq FS_{req}, \text{"Okay"}, \text{"No Good"})$$

$$\text{OverTurning\_Moment\_Check} = \text{"Okay"}$$

**Shear Capacity in Pier:**

Shear Resistance of Pier =

$$S_p := \frac{P_{ave} \cdot A_p + \mu \cdot W_{T_{tot}}}{FS_{req}} = 515.999 \cdot \text{kips}$$

$$\text{Shear\_Check} := \text{if}(S_p > \text{Shear}, \text{"Okay"}, \text{"No Good"})$$

Shear\_Check = "Okay"

**Bearing Pressure Caused by Footing:**

Area of the Mat =

$$A_{mat} := W_f^2 = 1.024 \times 10^3$$

Section Modulus of Mat =

$$S := \frac{W_f^3}{6} = 5461.33 \cdot \text{ft}^3$$

Maximum Pressure in Mat =

$$P_{max} := \frac{W_{T_{tot}}}{A_{mat}} + \frac{M_{ot}}{S} = 2.497 \cdot \text{ksf}$$

$$\text{Max\_Pressure\_Check} := \text{if}(P_{max} < .75 \cdot q_u, \text{"Okay"}, \text{"No Good"})$$

Max\_Pressure\_Check = "Okay"

Minimum Pressure in Mat =

$$P_{min} := \frac{W_{T_{tot}}}{A_{mat}} - \frac{M_{ot}}{S} = -0.612 \cdot \text{ksf}$$

$$\text{Min\_Pressure\_Check} := \text{if}[(P_{min} \geq 0) \cdot (P_{min} < .75 \cdot q_u), \text{"Okay"}, \text{"No Good"}]$$

Min\_Pressure\_Check = "No Good"

Distance to Resultant of Pressure Distribution =

$$X_p := \frac{P_{max}}{P_{max} - P_{min}} \cdot \frac{1}{3} = 8.566$$

Distance to Kern =

$$X_k := \frac{W_f}{6} = 5.333$$

Since Resultant Force is Not in Kern, Area to which Pressure is Applied Must be Reduced.

Eccentricity =

$$e := \frac{M_{ot}}{W_{T_{tot}}} = 5.499$$

Adjusted Soil Pressure =

$$P_a := \frac{2 \cdot W_{T_{tot}}}{3 \cdot W_f \left( \frac{W_f}{2} - e \right)} = 1.914 \cdot \text{ksf}$$

$$q_{adj} := \text{if}(P_{min} < 0, P_a \cdot P_{max}) = 1.914 \cdot \text{ksf}$$

$$\text{Pressure\_Check} := \text{if}(q_{adj} < q_a, \text{"Okay"}, \text{"No Good"})$$

Pressure\_Check = "Okay"

**Concrete Bearing Capacity:**

Strength Reduction Factor =

$$\Phi_c := 0.65 \quad (\text{ACI-2008 9.3.2.2})$$

Bearing Strength Between Pier and Pad =

$$P_b := \Phi_c \cdot 0.85 \cdot f_c \cdot \frac{\pi \cdot d_p^2}{4} = 1.054 \times 10^4 \text{ kips} \quad (\text{ACI-2008 10.14})$$

$$\text{Bearing\_Check} := \text{if}(P_b > \text{Axial}, \text{"Okay"}, \text{"No Good"})$$

Bearing\_Check = "Okay"

**Shear Strength of Concrete:**

Beam Shear:

(Critical section located at a distance d from the face of Pier) (ACI 11.3.1.1)

$$\Phi_c := 0.85 \quad (\text{ACI 9.3.2.5})$$

$$d := T_f - C_{vr\_pad} - d_{bot} = 3.632$$

$$d_1 := \frac{W_f}{2} - \frac{d_p}{2}$$

$$d_2 := d_1 - d$$

$$L := \left( \frac{W_f}{2} - e \right) \cdot 3$$

$$\text{Slope} := \text{if} \left( L > W_f, \frac{P_{\max} - P_{\min}}{W_f}, \frac{q_{adj}}{L} \right)$$

$$V_{req} := \left[ (q_{adj} - \text{Slope} \cdot d_1) + \left( \frac{\text{Slope} \cdot d_1}{2} \right) \right] \cdot W_f \cdot d_1$$

$$V_{Avail} := \Phi_c \cdot 2 \cdot \sqrt{f_c \cdot \psi} \cdot W_f \cdot d \quad (\text{ACI-2008 11.2.1.1})$$

$$\text{Beam\_Shear\_Check} := \text{if}(V_{req} < V_{Avail}, \text{"Okay"}, \text{"No Good"})$$

Beam\_Shear\_Check = "Okay"

Punching Shear:

(Critical Section Located at a distance of d/2 from the face of pier) (ACI 11.11.1.2)

Critical Perimeter of Punching Shear =

$$b_o := (d_p + d) \cdot \pi = 35$$

Area Included Inside Perimeter =

$$A_{bo} := \frac{\pi \cdot (d_p + d)^2}{4} = 97.3$$

Area Outside of Perimeter =

$$A_{out} := A_{mat} - A_{bo} = 926.7$$

Guess Value =

$$v_u := 1 \text{ksf}$$

(From "Foundation Analysis and design", By Joseph Bowles, Eq. 8-9)

Given

$$d^2 + d_p \cdot d = \frac{W_{T_{tot}}}{\pi \cdot v_u}$$

$$v_u := \text{Find}(v_u) = 7.6 \cdot \text{ksf}$$

$$V_u := v_u \cdot d \cdot W_f = 882.8 \cdot \text{kips}$$

Required Shear Strength =

$$V_{req} := V_u = 882.8 \cdot \text{kips}$$

Available Shear Strength =

$$V_{Avail} := \phi_c \cdot 4 \cdot \sqrt{f_c \cdot \text{psi}} \cdot b_o \cdot d = 3406.8 \cdot \text{kip} \quad (\text{ACI-2008 11.11.2.1})$$

$$\text{Punching\_Shear\_Check} := \text{if}(V_{req} < V_{Avail}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Punching\_Shear\_Check} = \text{"Okay"}$$

### Steel Reinforcement in Pad:

Required Reinforcement for Bending:

Strength Reduction Factor =

$$\phi_m := .90 \quad (\text{ACI-2008 9.3.2.1})$$

$$q_b := q_{adj} - d_1 \cdot \text{Slope} = 1.17 \cdot \text{ksf}$$

Maximum Bending at Face of Pier =

$$M_n := \frac{1}{\phi_m} \cdot \left[ (q_{adj} - q_b) \cdot \frac{d_1^2}{3} + q_b \cdot \frac{d_1^2}{2} \right] \cdot W_f = 4445 \cdot \text{kip-ft}$$

$$\beta := \begin{cases} 0.85 & \text{if } 2500 \cdot \text{psi} \leq f_c \leq 4000 \cdot \text{psi} \\ 0.65 & \text{if } f_c > 8000 \cdot \text{psi} \end{cases} = 0.85$$

$$\left[ \left[ \left[ \left[ \frac{f_c}{\text{psi}} - 4000 \right] \right] \right] \cdot 0.5 \right] \text{ otherwise} \quad (\text{ACI-2008 10.2.7.3})$$

$$R_n := \frac{M_n}{W_f \cdot d^2} = 73.1 \cdot \text{psi}$$

$$\rho := \frac{0.85 \cdot f_c}{f_y} \left( 1 - \sqrt{1 - \frac{2 \cdot R_n}{0.85 \cdot f_c}} \right) = 0.0012$$

$$\rho_{min} := \rho = 0.00124$$

Required Reinforcement for Temperature and Shrinkage:

$$\rho_{sh} := \begin{cases} .0018 & \text{if } f_y \geq 60000\text{-psi} \\ .0020 & \text{otherwise} \end{cases} \quad (\text{ACI-2008 7.12.2.1})$$

Check Bottom Bars:

$$A_s := \begin{cases} \rho_{min} \cdot W_f \cdot d & \text{if } \rho_{min} > \frac{\rho_{sh}}{2} = 20.696\text{-in}^2 \\ \rho_{sh} \cdot W_f \cdot \frac{d}{2} & \text{otherwise} \end{cases}$$

$$A_{s\text{prov.bot}} := A_{\text{bbot}} \cdot NB_{\text{bot}} = 65.6\text{-in}^2$$

$$\text{Pad\_Reinforcement\_Bot} := \text{if}(A_{s\text{prov.bot}} > A_s, \text{"Okay"}, \text{"No Good"})$$

**Pad\_Reinforcement\_Bot = "Okay"**

Check Temp Shrinkage Reinforcement:

$$A_s := \rho_{sh} \cdot (W_f \cdot T_f) = 33.2\text{-in}^2$$

$$A_{s\text{prov.top}} := A_{\text{btop}} \cdot NB_{\text{top}} = 65.6\text{-in}^2$$

$$A_{s\text{prov.tot}} := A_{s\text{prov.bot}} + A_{s\text{prov.top}} = 131.2\text{-in}^2$$

$$\text{Pad\_Reinforcement\_Temp} := \text{if}(A_{s\text{prov.tot}} > A_s, \text{"Okay"}, \text{"No Good"})$$

**Pad\_Reinforcement\_Temp = "Okay"**

**Development Length Pad Reinforcement:**

Bar Spacing =

$$B_{s\text{Pad}} := \frac{W_f - 2 \cdot C_{vr\text{pad}} - NB_{\text{bot}} \cdot d_{\text{bbot}}}{NB_{\text{bot}} - 1} = 7.78\text{-in}$$

Spacing or Cover Dimension =

$$c := \text{if}\left(C_{vr\text{pad}} < \frac{B_{s\text{Pad}}}{2}, C_{vr\text{pad}}, \frac{B_{s\text{Pad}}}{2}\right) = 3\text{-in}$$

Transverse Reinforcement Index =

$$k_{tr} := 0 \quad (\text{ACI-2008 12.2.3})$$

$$L_{\text{dbt}} := \frac{3 \cdot f_y \cdot \alpha_{\text{pad}} \cdot \beta_{\text{pad}} \cdot \gamma_{\text{pad}} \cdot \lambda_{\text{pad}}}{40 \cdot \sqrt{f_c \cdot \text{psi}} \cdot \frac{c + k_{tr}}{d_{\text{bbot}}}} \cdot d_{\text{bbot}} = 54.4\text{-in}$$

Minimum Development Length =

$$L_{\text{dbmin}} := 12\text{-in} \quad (\text{ACI-2008 12.2.1})$$

$$L_{\text{dbtCheck}} := \text{if}(L_{\text{dbt}} \geq L_{\text{dbmin}}, \text{"Use L.dbt"}, \text{"Use L.dbmin"})$$

Available Length in Pad =

$$L_{\text{Pad}} := \frac{W_f}{2} - \frac{d_p}{2} - C_{vr\text{pad}} = 144\text{-in}$$

$$L_{\text{pad\_Check}} := \text{if}(L_{\text{Pad}} > L_{\text{dbt}}, \text{"Okay"}, \text{"No Good"})$$

**Lpad\_Check = "Okay"**

**Steel Reinforcement in Pier:**

Area of Pier =

$$A_p := d_p^2 = 8100 \cdot \text{in}^2$$

$$A_{smin} := 0.01 \cdot 0.5 \cdot A_p = 40.5 \cdot \text{in}^2 \quad (\text{ACI-2008 10.8.4 \& 10.9.1})$$

$$A_{sprov} := N_{B_{pier}} \cdot A_{B_{pier}} = 56.21 \cdot \text{in}^2$$

$$\text{Steel\_Area\_Check} := \text{if}(A_{sprov} > A_{smin}, \text{"Okay"}, \text{"No Good"})$$

Steel\_Area\_Check = "Okay"

**NOTE:** Anchor Bolts are not accounted for in reinforcement calculation and will provide additional reinforcement to satisfy minimum requirement of steel.

Bar Spacing In Pier =

$$B_{sPier} := \frac{d_p \cdot \pi}{N_{B_{pier}}} - d_{B_{pier}} = 6.444 \cdot \text{in}$$

Diameter of Reinforcement Cage =

$$\text{Diam}_{cage} := d_p - 2 \cdot C_{vr_{pier}} = 84 \cdot \text{in}$$

Maximum Moment in Pier =

$$M_p := \left[ OM + \text{Shear} \cdot \left( L_p + \frac{A_{BP}}{2} \right) \right] = 99024 \cdot \text{in} \cdot \text{kips}$$

Pier Check evaluated from outside program and results are listed below;

$$(D \ N \ n \ P_u \ M_{xu}) := \left( d_p \cdot 12 \ N_{B_{pier}} \ B_{s_{pier}} \ \frac{\text{Axial} \cdot 1.333}{\text{kips}} \ \frac{M_p}{\text{in} \cdot \text{kips}} \right)$$

$$(D \ N \ n \ P_u \ M_{xu}) = (90 \ 36 \ 11 \ 105.3 \ 99024)$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) := (0 \ 0 \ 0 \ 0)$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) := \phi P'_n (D, N, n, P_u, M_{xu})^T$$

$$(\phi P_n \ \phi M_{xn} \ f_{sp} \ \rho) = (119.5 \ 1.1 \times 10^5 \ -60 \ 0)$$

$$\text{Axial\_Load\_Check} := \text{if}(\phi P_n \geq P_u, \text{"Okay"}, \text{"No Good"})$$

Axial\_Load\_Check = "Okay"

$$\text{Bending\_Check} := \text{if}(\phi M_{xn} \geq M_{xu}, \text{"Okay"}, \text{"No Good"})$$

Bending\_Check = "Okay"

**Development Length Pier Reinforcement:**

Available Length in Foundation:

$$L_{\text{pier}} := L_p - C_{\text{vr}}_{\text{pier}} = 39 \cdot \text{in}$$

$$L_{\text{pad}} := T_f - C_{\text{vr}}_{\text{pad}} = 45 \cdot \text{in}$$

Tension:

(ACI-2008 12.2.3)

Spacing or Cover Dimension =

$$c := \text{if} \left( C_{\text{vr}}_{\text{pier}} < \frac{B_{\text{sPier}}}{2}, C_{\text{vr}}_{\text{pier}}, \frac{B_{\text{sPier}}}{2} \right) = 3 \cdot \text{in}$$

Transverse Reinforcement =

$$k_{\text{tr}} := 0$$

(ACI-2008 12.2.3)

$$L_{\text{dbt}} := \frac{3 \cdot f_y \cdot \alpha_{\text{pier}} \cdot \beta_{\text{pier}} \cdot \gamma_{\text{pier}} \cdot \lambda_{\text{pier}}}{40 \cdot \sqrt{f_c \cdot \text{psi}} \cdot \left( \frac{c + k_{\text{tr}}}{d_{\text{bpier}}} \right)} \cdot d_{\text{bpier}} = 54.45 \cdot \text{in}$$

Minimum Development Length =

$$L_{\text{dh}} := \frac{1200 \cdot d_{\text{bpier}}}{\sqrt{\frac{f_c}{\text{psi}}}} \cdot .7 = 21.624 \cdot \text{in} \quad (\text{ACI } 12.2.1)$$

Pier reinforcement bars are standard 90 degree hooks and therefore development in the pad is computed as follows:

$$L_{\text{db}} := \max(L_{\text{dbt}}, L_{\text{dbmin}})$$

$$L_{\text{tension\_Check}} := \text{if}(L_{\text{pier}} + L_{\text{pad}} > L_{\text{db}}, \text{"Okay"}, \text{"No Good"})$$

$$L_{\text{tension\_Check}} = \text{"Okay"}$$

Compression:

(ACI-2008 12.3.2)

$$L_{\text{dbc1}} := \frac{.02 \cdot d_{\text{bpier}} \cdot f_y}{\sqrt{f_c \cdot \text{psi}}} = 30.892 \cdot \text{in}$$

$$L_{\text{dbmin}} := 0.0003 \cdot \frac{\text{in}^2}{l_b} \cdot (d_{\text{bpier}} \cdot f_y) = 25.38 \cdot \text{in}$$

$$L_{\text{dbc}} := \text{if}(L_{\text{dbc1}} \geq L_{\text{dbmin}}, L_{\text{dbc1}}, L_{\text{dbmin}}) = 30.892 \cdot \text{in}$$

$$L_{\text{compression\_Check}} := \text{if}(L_{\text{pier}} + L_{\text{pad}} > L_{\text{dbc}}, \text{"Okay"}, \text{"No Good"})$$

$$L_{\text{compression\_Check}} = \text{"Okay"}$$



<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---


### Section 1 - Site Information

<b>Site ID:</b> CTNH362B	<b>Site Name:</b> NH362/Boardman_MP	<b>Latitude:</b> 41.59955439
<b>Status:</b> Draft	<b>Site Class:</b> Monopole	<b>Longitude:</b> -73.43760920
<b>Version:</b> 6	<b>Site Type:</b> Structure Non Building	<b>Address:</b> 33 Boardman Road
<b>Project Type:</b> Anchor	<b>Plan Year:</b> 2020	<b>City, State:</b> New Milford, CT
<b>Approved:</b> Not Approved	<b>Market:</b> CONNECTICUT CT	<b>Region:</b> NORTHEAST
<b>Approved By:</b> Not Approved	<b>Vendor:</b> Ericsson	
<b>Last Modified:</b> 7/2/2020 9:20:52 AM	<b>Landlord:</b> private	
<b>Last Modified By:</b> Dominic.Kallas2@T-Mobile.com		

<b>RAN Template:</b> 67D5A998C ODE+6160		<b>AL Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)		
<b>Sector Count:</b> 3	<b>Antenna Count:</b> 9	<b>Coax Line Count:</b> 0	<b>TMA Count:</b> 0	<b>RRU Count:</b> 9

### Section 2 - Existing Template Images


Capture.JPG



Notes:

Section 3 - Proposed Template Images

67D5998C\_1xAIR+1QP+1OP.PNG



Notes:

Section 4 - Siteplan Images

----- This section is intentionally blank. -----

DRAFT

<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

Section 5 - RAN Equipment

Existing RAN Equipment

Template: 67D04G

<b>Enclosure</b>	1		
<b>Enclosure Type</b>	RBS 6201 ODE		
<b>Baseband</b>	DUG20 G1900	BB 6630 L1900 L700 L600	BB 6630 N600
<b>Hybrid Cable System</b>	Ericsson 6x12 HCS *Select Length & AWG*		
<b>Radio</b>	RUS01 B2 (x 3) G1900	RUS01 B2 (x 3) L1900	

Proposed RAN Equipment

Template: 67D5A998C ODE+6160

<b>Enclosure</b>	1	2	3
<b>Enclosure Type</b>	RBS 6201 ODE	Enclosure 6160	B160
<b>Baseband</b>	DUG20 G1900	BB 6630 L2100 L1900 L700 L600	BB 6630 L2500
<b>Hybrid Cable System</b>	Ericsson 6x12 HCS *Select Length & AWG*	Ericsson 6x12 HCS *Select AWG & Length* (x 2)	
<b>Radio</b>	RUS01 B2 (x 6)		

RAN Scope of Work:

Check AC service, and upgrade AC Service, Breakers, and PPC where necessary.

All Cabinet Radios will become dark, since GSM and L1900 will move to the new Radio 4424 B25.

Add (1) Enclosure 6160.

Add (1) Battery Cabinet B160.

Add (1) iXRe Router to new Enclosure 6160.

Add (1) BB6630 for L2500 to new Enclosure 6160.

Add (1) BB6648 for N2500 to new Enclosure 6160.

Existing: (12) Coaxial Lines; (1) 6X12 HCS.

Remove all coaxial lines.

Add (2) 6X12 HCS for Anchor A&L Equipment. Length of new HCS will match that of existing HCS.

Paint to match.

<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

Section 6 - A&L Equipment

Existing Template: 67D04G\_1DP+1OP  
Proposed Template: 67D5998C\_1xAIR+1QP+1OP (U21 Market)

Sector 1 (Existing) view from behind

<b>Coverage Type</b>	A - Outdoor Macro				
<b>Antenna</b>	1		2		
<b>Antenna Model</b>	RFS - APXV18-209014-C-A20 (Dual)		RFS - APXVAARR24_43-U-NA20 (Octo)		
<b>Azimuth</b>	60		60		
<b>M. Tilt</b>	0		0		
<b>Height</b>	140		140		
<b>Ports</b>	P1		P2	P3	P4 P5
<b>Active Tech.</b>	L1900 G1900		L700 L600 N600	L700 L600 N600	
<b>Dark Tech.</b>					
<b>Restricted Tech.</b>					
<b>Decomm. Tech.</b>					
<b>E. Tilt</b>	2		2		
<b>Cables</b>	1-5/8" Coax - 160 ft. (x2)		Coax Jumper (x2)	Coax Jumper (x2)	
<b>TMA's</b>	Generic Twin Style 1A - PCS (AtAntenna)				
<b>Diplexers / Combiners</b>					
<b>Radio</b>			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)	
<b>Sector Equipment</b>					

Unconnected Equipment:

Cable: 1-5/8" Coax - 160 ft. Cable: 1-5/8" Coax - 160 ft.

Scope of Work:

Replace LB Dual in Position 2 with (1) LB/MB Octo.  
Add (1) Radio 4449 B71+B12 for L600 and L700 to Position 2 at antenna.  
Ensure to Daisy-chain all Octa RETs to 4449.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

Sector 1 (Proposed) view from behind								
Coverage Type	A - Outdoor Macro							
Antenna	1		2		3			
Antenna Model	RFS - APX16DWV-16DWV-S-E-A20 (Quad)		Ericsson - AIR6449 B41 (Active Antenna - Massive MIMO)		RFS - APXVAARR24_43-U-NA20 (Octo)			
Azimuth	60		60		60			
M. Tilt	0		0		0			
Height	140		140		140			
Ports	P1	P2	P3	P4	P5	P6	P7	P8
Active Tech.	L2100	L2100	L2500 N2500	L2500 N2500	L700 L600 N600	L700 L600 N600	L1900 G1900	L1900
Dark Tech.								
Restricted Tech.								
Decomm. Tech.								
E. Tilt	2	2	2	2	2	2	2	2
Cables	Coax Jumper (x2)	Coax Jumper (x2)			Coax Jumper (x2)	Coax Jumper (x2)	Coax Jumper (x2)	Coax Jumper (x2)
TMA's								
Diplexers / Combiners								
Radio	Radio 4415 B66A (At Antenna)	SHARED Radio 4415 B66A (At Antenna)			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)	Radio 4424 B25 (At Antenna)	SHARED Radio 4424 B25 (At Antenna)
Sector Equipment								

**Unconnected Equipment:**

**Scope of Work:**

Remove PCS TMA from Position 1.  
 Remove all coaxial lines.  
 Replace Mid-Band Dual in Position 1 with (1) Mid-Band Quad.  
 Add (1) Radio 4415 B66A for L2100 to Position 1 at antenna, and connect its ports to the new Quad antenna.  
 Add new mount between Positions 1 and 2 for new Position 2.  
 Install (1) AIR6449 B41 for L2500 and N2500 in new Position 2.  
 Add (1) Radio 4424 B25 for L1900 (both carriers) and GSM to new Position 3 at antenna, and connect its ports to the Mid-Band ports of the Octo antenna.  
 Ensure RET control is enabled for all technology layers according to the Design Documents.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

Sector 2 (Existing) view from behind						
Coverage Type	A - Outdoor Macro					
Antenna	1		2			
Antenna Model	RFS - APXV18-209014-C-A20 (Dual)		RFS - APXVAARR24_43-U-NA20 (Octo)			
Azimuth	180		180			
M. Tilt	0		0			
Height	140		140			
Ports	P1		P2	P3	P4	P5
Active Tech.	L1900 G1900		L700 L600 N600	L700 L600 N600		
Dark Tech.						
Restricted Tech.						
Decomm. Tech.						
E. Tilt	4		3			
Cables	1-5/8" Coax - 160 ft. (x2)		Coax Jumper (x2)	Coax Jumper (x2)		
TMA's	Generic Twin Style 1A - PCS (AtAntenna)					
Diplexers / Combiners						
Radio			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)		
Sector Equipment						

**Unconnected Equipment:**

Cable: 1-5/8" Coax - 160 ft.    Cable: 1-5/8" Coax - 160 ft.

**Scope of Work:**

Replace LB Dual in Position 2 with (1) LB/MB Octo.  
 Add (1) Radio 4449 B71+B12 for L600 and L700 to Position 2 at antenna.  
 Ensure to Daisy-chain all Octa RETs to 4449.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.



<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

Sector 2 (Proposed) view from behind								
Coverage Type	A - Outdoor Macro							
Antenna	1		2		3			
Antenna Model	RFS - APX16DWV-16DWV-S-E-A20 (Quad)		Ericsson - AIR6449 B41 (Active Antenna - Massive MIMO)		RFS - APXVAARR24_43-U-NA20 (Octo)			
Azimuth	180		180		180			
M. Tilt	0		0		0			
Height	140		140		140			
Ports	P1	P2	P3	P4	P5	P6	P7	P8
Active Tech.	L2100	L2100	L2500 N2500	L2500 N2500	L700 L600 N600	L700 L600 N600	L1900 G1900	L1900
Dark Tech.								
Restricted Tech.								
Decomm. Tech.								
E. Tilt	2	2	2	2	2	2	2	2
Cables	Coax Jumper (x2)	Coax Jumper (x2)			Coax Jumper (x2)	Coax Jumper (x2)	Coax Jumper (x2)	Coax Jumper (x2)
TMA's								
Diplexers / Combiners								
Radio	Radio 4415 B66A (At Antenna)	SHARED Radio 4415 B66A (At Antenna)			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)	Radio 4424 B25 (At Antenna)	SHARED Radio 4424 B25 (At Antenna)
Sector Equipment								

**Unconnected Equipment:**

**Scope of Work:**

Remove PCS TMA from Position 1.  
 Remove all coaxial lines.  
 Replace Mid-Band Dual in Position 1 with (1) Mid-Band Quad.  
 Add (1) Radio 4415 B66A for L2100 to Position 1 at antenna, and connect its ports to the new Quad antenna.  
 Add new mount between Positions 1 and 2 for new Position 2.  
 Install (1) AIR6449 B41 for L2500 and N2500 in new Position 2.  
 Add (1) Radio 4424 B25 for L1900 (both carriers) and GSM to new Position 3 at antenna, and connect its ports to the Mid-Band ports of the Octo antenna.  
 Ensure RET control is enabled for all technology layers according to the Design Documents.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

Sector 3 (Existing) view from behind						
Coverage Type	A - Outdoor Macro					
Antenna	1		2			
Antenna Model	RFS - APXV18-209014-C-A20 (Dual)		RFS - APXVAARR24_43-U-NA20 (Octo)			
Azimuth	300		300			
M. Tilt	0		0			
Height	140		140			
Ports	P1		P2	P3	P4	P5
Active Tech.	L1900 G1900		L700 L600 N600	L700 L600 N600		
Dark Tech.						
Restricted Tech.						
Decomm. Tech.						
E. Tilt	4		2			
Cables	1-5/8" Coax - 160 ft. (x2)		Coax Jumper (x2)	Coax Jumper (x2)		
TMA's	Generic Twin Style 1A - PCS (AtAntenna)					
Diplexers / Combiners						
Radio			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)		
Sector Equipment						

**Unconnected Equipment:**

Cable: 1-5/8" Coax - 160 ft.    Cable: 1-5/8" Coax - 160 ft.

**Scope of Work:**

Replace LB Dual in Position 2 with (1) LB/MB Octo.  
 Add (1) Radio 4449 B71+B12 for L600 and L700 to Position 2 at antenna.  
 Ensure to Daisy-chain all Octa RETs to 4449.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

Sector 3 (Proposed) view from behind								
Coverage Type	A - Outdoor Macro							
Antenna	1		2		3			
Antenna Model	RFS - APX16DWV-16DWV-S-E-A20 (Quad)		Ericsson - AIR6449 B41 (Active Antenna - Massive MIMO)		RFS - APXVAARR24_43-U-NA20 (Octo)			
Azimuth	300		300		300			
M. Tilt	0		0		0			
Height	140		140		140			
Ports	P1	P2	P3	P4	P5	P6	P7	P8
Active Tech.	L2100	L2100	L2500 N2500	L2500 N2500	L700 L600 N600	L700 L600 N600	L1900 G1900	L1900
Dark Tech.								
Restricted Tech.								
Decomm. Tech.								
E. Tilt	2	2	2	2	2	2	2	2
Cables	Coax Jumper (x2)	Coax Jumper (x2)			Coax Jumper (x2)	Coax Jumper (x2)	Coax Jumper (x2)	Coax Jumper (x2)
TMA's								
Diplexers / Combiners								
Radio	Radio 4415 B66A (At Antenna)	SHARED Radio 4415 B66A (At Antenna)			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)	Radio 4424 B25 (At Antenna)	SHARED Radio 4424 B25 (At Antenna)
Sector Equipment								

**Unconnected Equipment:**

**Scope of Work:**

Remove PCS TMA from Position 1.  
 Remove all coaxial lines.  
 Replace Mid-Band Dual in Position 1 with (1) Mid-Band Quad.  
 Add (1) Radio 4415 B66A for L2100 to Position 1 at antenna, and connect its ports to the new Quad antenna.  
 Add new mount between Positions 1 and 2 for new Position 2.  
 Install (1) AIR6449 B41 for L2500 and N2500 in new Position 2.  
 Add (1) Radio 4424 B25 for L1900 (both carriers) and GSM to new Position 3 at antenna, and connect its ports to the Mid-Band ports of the Octo antenna.  
 Ensure RET control is enabled for all technology layers according to the Design Documents.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

<b>RAN Template:</b> 67D5A998C ODE+6160	<b>A&amp;L Template:</b> 67D5998C_1xAIR+1QP+1OP (U21 Market)
--	---

**Section 7 - Power Systems Equipment**

**Existing Power Systems Equipment**

----- This section is intentionally blank. -----

**Proposed Power Systems Equipment**

# Exhibit E

## **Mount Analysis**

**Structural Analysis Report**

*Antenna Mount Analysis*


*T-Mobile Site #: CTNH362B*

*33 Boardman Road  
New Milford, CT*

*Centek Project No. 20074.50*

*Date: July 8, 2020*

*Max Stress Ratio = 67.2%*



**Prepared for:**

*T-Mobile USA  
35 Griffin Road  
Bloomfield, CT 06002*

*CENTEK Engineering, Inc.*  
*Structural Analysis – Mount Analysis*  
*T-Mobile Site Ref. ~ CTNH362B*  
*New Milford, CT*  
*July 8, 2020*

## **Table of Contents**

### **SECTION 1 – REPORT**

- ANTENNA AND APPURTENANCE SUMMARY
- STRUCTURE LOADING
- CONCLUSION

### **SECTION 2 – CALCULATIONS**

- WIND LOAD ON APPURTENANCES
- RISA3D OUTPUT REPORT

### **SECTION 3 – REFERENCE MATERIALS (NOT INCLUDED WITHIN REPORT)**

- RF DATA SHEET, DATED 07/06/2020

July 8, 2020

Mr. Dan Reid  
Transcend Wireless  
10 Industrial Ave  
Mahwah, NJ 07430

Re: *Structural Letter ~ Antenna Mount*  
*T-Mobile – Site Ref: CTNH362B*  
*33 Boardman Road*  
*New Milford, CT 06776*

*Centek Project No. 20074.50*

Dear Mr. Reid,

Centek Engineering, Inc. has reviewed the T-Mobile antenna installation at the above referenced site. The purpose of the review is to determine the structural adequacy of the existing mount, consisting of three (3) 10-ft T-arms w/ stabilizer kits to support the proposed/existing equipment configuration. The review considered the effects of wind load, dead load and ice load in accordance with the 2015 International Building Code as modified by the 2018 Connecticut State Building Code (CTBC) including ASCE 7-10 and ANSI/TIA-222-G *Structural Standards for Steel Antenna Towers and Supporting Structures*.

The loads considered in this analysis consist of the following:


- T-Mobile:  
T-Arms: Three (3) RFS APX16DWV-16DWVS panel antennas, three (3) RFS APXVAARR24-43- panel antennas, three (3) Ericsson AIR6449 panel antennas, three (3) Ericsson 4449 remote radio units, three (3) Ericsson 4415 remote radio units and three (3) Ericsson 4424 remote radio units mounted on three (3) T-Arms with a RAD center elevation of 140-ft +/- AGL.

The antenna mount was analyzed per the requirements of the 2015 International Building Code as modified by the 2018 Connecticut State Building Code considering a nominal design wind speed of 89 mph for New Milford as required in Appendix N of the 2018 Connecticut State Building Code.


A structural analysis of tower and foundation needs to be completed prior to any work.

Based on our review of the installation, it is our opinion that the subject antenna mount has sufficient capacity to support the aforementioned antenna configuration. If there are any questions regarding this matter, please feel free to call.

Respectfully Submitted by:



Timothy J. Lynn, PE  
Structural Engineer





**CEN TEK** Engineering, Inc.  
Structural Analysis – Mount Analysis  
T-Mobile Site Ref. ~ CTNH362B  
New Milford, CT  
July 8, 2020

## **Section 2 - Calculations**

**Development of Design Heights, Exposure Coefficients,  
 and Velocity Pressures Per TIA-222-G**

**Wind Speeds**

Basic Wind Speed  $V := 89$  mph (User Input - 2018 CSBC Appendix N)  
 Basic Wind Speed with Ice  $V_i := 40$  mph (User Input per Annex B of TIA-222-G)

**Input**

Structure Type = Structure\_Type := Pole (User Input)  
 Structure Category = SC := II (User Input)  
 Exposure Category = Exp := C (User Input)  
 Structure Height = h := 154 ft (User Input)  
 Height to Center of Antennas =  $z_{Ant} := 140$  ft (User Input)  
 Radial Ice Thickness =  $t_i := 1.00$  in (User Input per Annex B of TIA-222-G)  
 Radial Ice Density =  $\rho_d := 56.00$  pcf (User Input)  
 Topographic Factor =  $K_{zt} := 1.0$  (User Input)  
 $K_a := 1.0$  (User Input)  
 Gust Response Factor =  $G_H := 1.1$  (User Input)

**Output**

Wind Direction Probability Factor =  $K_d := \begin{cases} 0.95 & \text{if Structure\_Type} = \text{Pole} \\ 0.85 & \text{if Structure\_Type} = \text{Lattice} \end{cases} = 0.95$  (Per Table 2-2 of TIA-222-G)

Importance Factors =  $I_{Wind} := \begin{cases} 0.87 & \text{if SC} = 1 \\ 1.00 & \text{if SC} = 2 \\ 1.15 & \text{if SC} = 3 \end{cases} = 1$  (Per Table 2-3 of TIA-222-G)

$I_{Wind\_w\_Ice} := \begin{cases} 0 & \text{if SC} = 1 \\ 1.00 & \text{if SC} = 2 \\ 1.00 & \text{if SC} = 3 \end{cases} = 1$

$I_{ice} := \begin{cases} 0 & \text{if SC} = 1 \\ 1.00 & \text{if SC} = 2 \\ 1.25 & \text{if SC} = 3 \end{cases} = 1$

$$K_{iz} := \left( \frac{z_{Ant}}{33} \right)^{0.1} = 1.155$$

$$t_{iz} := 2.0 \cdot t_i \cdot I_{ice} \cdot K_{iz} \cdot K_{zt}^{0.35} = 2.311$$

Velocity Pressure Coefficient Antennas =

$$K_{z_{Ant}} := 2.01 \left( \frac{z_{Ant}}{z_g} \right)^{\frac{2}{\alpha}} = 1.359$$

Velocity Pressure w/o Ice Antennas =

$$q_{z_{Ant}} := 0.00256 \cdot K_d \cdot K_{z_{Ant}} \cdot V^2 \cdot I_{Wind} = 26.17$$

Velocity Pressure with Ice Antennas =

$$q_{z_{ice.Ant}} := 0.00256 \cdot K_d \cdot K_{z_{Ant}} \cdot V_i^2 \cdot I_{Wind} = 5.286$$

**Development of Wind & Ice Load on Antennas**

**Antenna Data:**

Antenna Model =	RFSAPXVAARR24-43	
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 95.9$	in (User Input)
Antenna Width =	$W_{ant} := 24$	in (User Input)
Antenna Thickness =	$T_{ant} := 8.7$	in (User Input)
Antenna Weight =	$WT_{ant} := 153$	lbs (User Input)
Number of Antennas =	$N_{ant} := 1$	(User Input)
Antenna Aspect Ratio =	$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 4.0$	
Antenna Force Coefficient =	$Ca_{ant} = 1.27$	

**Wind Load (without ice)**

Surface Area for One Antenna =  $SA_{antF} := \frac{L_{ant} \cdot W_{ant}}{144} = 16$  sf

Total Antenna Wind Force =  $F_{ant} := qz_{Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{antF} = 583$  lbs

Surface Area for One Antenna =  $SA_{antS} := \frac{L_{ant} \cdot T_{ant}}{144} = 5.8$  sf

Total Antenna Wind Force =  $F_{ant} := qz_{Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{antS} = 211$  lbs

**Wind Load (with ice)**

Surface Area for One Antenna w/ Ice =  $SA_{ICEantF} := \frac{(L_{ant} + 2 \cdot t_{iz}) \cdot (W_{ant} + 2 \cdot t_{iz})}{144} = 20$  sf

Total Antenna Wind Force w/ Ice =  $F_{ant} := qz_{ice.Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{ICEantF} = 147$  lbs

Surface Area for One Antenna w/ Ice =  $SA_{ICEantS} := \frac{(L_{ant} + 2 \cdot t_{iz}) \cdot (T_{ant} + 2 \cdot t_{iz})}{144} = 9.3$  sf

Total Antenna Wind Force w/ Ice =  $F_{ant} := qz_{ice.Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{ICEantS} = 68$  lbs

**Gravity Load (without ice)**

Weight of All Antennas =  $WT_{ant} \cdot N_{ant} = 153$  lbs

**Gravity Loads (ice only)**

Volume of Each Antenna =  $V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 2 \times 10^4$  cu in

Volume of Ice on Each Antenna =  $V_{ice} := (L_{ant} + 2 \cdot t_{iz})(W_{ant} + 2 \cdot t_{iz})(T_{ant} + 2 \cdot t_{iz}) - V_{ant} = 2 \times 10^4$  cu in

Weight of Ice on Each Antenna =  $W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 593$  lbs

Weight of Ice on All Antennas =  $W_{ICEant} \cdot N_{ant} = 593$  lbs

**Development of Wind & Ice Load on Antennas**

**Antenna Data:**

Antenna Model =	RFSAPX16DWV-16DWVS
Antenna Shape =	Flat (User Input)
Antenna Height =	$L_{ant} := 55.9$ in (User Input)
Antenna Width =	$W_{ant} := 13$ in (User Input)
Antenna Thickness =	$T_{ant} := 3.15$ in (User Input)
Antenna Weight =	$WT_{ant} := 45$ lbs (User Input)
Number of Antennas =	$N_{ant} := 1$ (User Input)
Antenna Aspect Ratio =	$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 4.3$
Antenna Force Coefficient =	$Ca_{ant} = 1.28$

**Wind Load (without ice)**

Surface Area for One Antenna =  $SA_{antF} := \frac{L_{ant} \cdot W_{ant}}{144} = 5$  sf

Total Antenna Wind Force =  $F_{ant} := qz_{Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{antF} = 186$  lbs

Surface Area for One Antenna =  $SA_{antS} := \frac{L_{ant} \cdot T_{ant}}{144} = 1.2$  sf

Total Antenna Wind Force =  $F_{ant} := qz_{Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{antS} = 45$  lbs

**Wind Load (with ice)**

Surface Area for One Antenna w/ Ice =  $SA_{ICEantF} := \frac{(L_{ant} + 2 \cdot t_{iz}) \cdot (W_{ant} + 2 \cdot t_{iz})}{144} = 7.4$  sf

Total Antenna Wind Force w/ Ice =  $F_{ant} := qz_{ice.Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{ICEantF} = 55$  lbs

Surface Area for One Antenna w/ Ice =  $SA_{ICEantS} := \frac{(L_{ant} + 2 \cdot t_{iz}) \cdot (T_{ant} + 2 \cdot t_{iz})}{144} = 3.3$  sf

Total Antenna Wind Force w/ Ice =  $F_{ant} := qz_{ice.Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{ICEantS} = 24$  lbs

**Gravity Load (without ice)**

Weight of All Antennas =  $WT_{ant} \cdot N_{ant} = 45$  lbs

**Gravity Loads (ice only)**

Volume of Each Antenna =  $V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 2289$  cu in

Volume of Ice on Each Antenna =  $V_{ice} := (L_{ant} + 2 \cdot t_{iz}) \cdot (W_{ant} + 2 \cdot t_{iz}) \cdot (T_{ant} + 2 \cdot t_{iz}) - V_{ant} = 6000$  cu in

Weight of Ice on Each Antenna =  $W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 194$  lbs

Weight of Ice on All Antennas =  $W_{ICEant} \cdot N_{ant} = 194$  lbs

**Development of Wind & Ice Load on Antennas**

**Antenna Data:**

Antenna Model =	Ericsson AIR6449	
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 33.1$	in (User Input)
Antenna Width =	$W_{ant} := 20.5$	in (User Input)
Antenna Thickness =	$T_{ant} := 8.3$	in (User Input)
Antenna Weight =	$WT_{ant} := 103$	lbs (User Input)
Number of Antennas =	$N_{ant} := 1$	(User Input)
Antenna Aspect Ratio =	$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 1.6$	
Antenna Force Coefficient =	$Ca_{ant} = 1.2$	

**Wind Load (without ice)**

Surface Area for One Antenna =	$SA_{antF} := \frac{L_{ant} \cdot W_{ant}}{144} = 4.7$	sf
<b>Total Antenna Wind Force =</b>	<b><math>F_{ant} := qz_{Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{antF} = 163</math></b>	lbs

Surface Area for One Antenna =	$SA_{antS} := \frac{L_{ant} \cdot T_{ant}}{144} = 1.9$	sf
<b>Total Antenna Wind Force =</b>	<b><math>F_{ant} := qz_{Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{antS} = 66</math></b>	lbs

**Wind Load (with ice)**

Surface Area for One Antenna w/ Ice =	$SA_{ICEantF} := \frac{(L_{ant} + 2 \cdot t_{iz}) \cdot (W_{ant} + 2 \cdot t_{iz})}{144} = 6.6$	sf
<b>Total Antenna Wind Force w/ Ice =</b>	<b><math>F_{ant} := qz_{ice.Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{ICEantF} = 46</math></b>	lbs

Surface Area for One Antenna w/ Ice =	$SA_{ICEantS} := \frac{(L_{ant} + 2 \cdot t_{iz}) \cdot (T_{ant} + 2 \cdot t_{iz})}{144} = 3.4$	sf
<b>Total Antenna Wind Force w/ Ice =</b>	<b><math>F_{ant} := qz_{ice.Ant} \cdot G_H \cdot Ca_{ant} \cdot K_a \cdot SA_{ICEantS} = 24</math></b>	lbs

**Gravity Load (without ice)**

<b>Weight of All Antennas =</b>	<b><math>WT_{ant} \cdot N_{ant} = 103</math></b>	lbs
---------------------------------	--	-----

**Gravity Loads (ice only)**

Volume of Each Antenna =	$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 5632$	cu in
Volume of Ice on Each Antenna =	$V_{ice} := (L_{ant} + 2 \cdot t_{iz}) \cdot (W_{ant} + 2 \cdot t_{iz}) \cdot (T_{ant} + 2 \cdot t_{iz}) - V_{ant} = 6613$	cu in
Weight of Ice on Each Antenna =	$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 214$	lbs
<b>Weight of Ice on All Antennas =</b>	<b><math>W_{ICEant} \cdot N_{ant} = 214</math></b>	lbs

**Development of Wind & Ice Load on RRUS**

**RRUS Data:**

RRUS Model =	Ericsson 4449
RRUS Shape =	Flat (User Input)
RRUS Height =	$L_{RRUS} := 14.9$ in (User Input)
RRUS Width =	$W_{RRUS} := 13.2$ in (User Input)
RRUS Thickness =	$T_{RRUS} := 10.4$ in (User Input)
RRUS Weight =	$W_{T_{RRUS}} := 74$ lbs (User Input)
Number of RRUSs =	$N_{RRUS} := 1$ (User Input)
RRUS Aspect Ratio =	$A_{r_{RRUS}} := \frac{L_{RRUS}}{W_{RRUS}} = 1.1$
RRUS Force Coefficient =	$C_{a_{RRUS}} = 1.2$

**Wind Load (without ice)**

Surface Area for One RRUS =  $SA_{RRUSF} := \frac{L_{RRUS} \cdot W_{RRUS}}{144} = 1.4$  sf

Total RRUS Wind Force =  $F_{RRUS} := qZ_{Ant} \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{RRUSF} = 47$  lbs

Surface Area for One RRUS =  $SA_{RRUSS} := \frac{L_{RRUS} \cdot T_{RRUS}}{144} = 1.1$  sf

Total RRUS Wind Force =  $F_{RRUS} := qZ_{Ant} \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{RRUSS} = 37$  lbs

**Wind Load (with ice)**

Surface Area for One RRUS w/ Ice =  $SA_{ICERRUSF} := \frac{(L_{RRUS} + 2 \cdot t_{iz}) \cdot (W_{RRUS} + 2 \cdot t_{iz})}{144} = 2.4$  sf

Total RRUS Wind Force w/ Ice =  $F_{i_{RRUS}} := qZ_{ice} \cdot Ant \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{ICERRUSF} = 17$  lbs

Surface Area for One RRUS w/ Ice =  $SA_{ICERRUSS} := \frac{(L_{RRUS} + 2 \cdot t_{iz}) \cdot (T_{RRUS} + 2 \cdot t_{iz})}{144} = 2$  sf

Total RRUS Wind Force w/ Ice =  $F_{i_{RRUS}} := qZ_{ice} \cdot Ant \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{ICERRUSS} = 14$  lbs

**Gravity Load (without ice)**

Weight of All RRUSs =  $W_{T_{RRUS}} \cdot N_{RRUS} = 74$  lbs

**Gravity Loads (ice only)**

Volume of Each RRUS =  $V_{RRUS} := L_{RRUS} \cdot W_{RRUS} \cdot T_{RRUS} = 2045$  cu in

Volume of Ice on Each RRUS =  $V_{ice} := (L_{RRUS} + 2 \cdot t_{iz})(W_{RRUS} + 2 \cdot t_{iz})(T_{RRUS} + 2 \cdot t_{iz}) - V_{RRUS} = 3$  cu in

Weight of Ice on Each RRUS =  $W_{ICERRUS} := \frac{V_{ice}}{1728} \cdot \rho_d = 103$  lbs

Weight of Ice on All RRUSs =  $W_{ICERRUS} \cdot N_{RRUS} = 103$  lbs

**Development of Wind & Ice Load on RRUS**

**RRUS Data:**

RRUS Model =	Ericsson 4415
RRUS Shape =	Flat (User Input)
RRUS Height =	$L_{RRUS} := 14.9$ in (User Input)
RRUS Width =	$W_{RRUS} := 13.2$ in (User Input)
RRUS Thickness =	$T_{RRUS} := 5.4$ in (User Input)
RRUS Weight =	$W_{T_{RRUS}} := 47$ lbs (User Input)
Number of RRUSs =	$N_{RRUS} := 1$ (User Input)
RRUS Aspect Ratio =	$A_{r_{RRUS}} := \frac{L_{RRUS}}{W_{RRUS}} = 1.1$
RRUS Force Coefficient =	$C_{a_{RRUS}} = 1.2$

**Wind Load (without ice)**

Surface Area for One RRUS =  $SA_{RRUSF} := \frac{L_{RRUS} \cdot W_{RRUS}}{144} = 1.4$  sf

Total RRUS Wind Force =  $F_{RRUS} := q_{Z_{Ant}} \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{RRUSF} = 47$  lbs

Surface Area for One RRUS =  $SA_{RRUSS} := \frac{L_{RRUS} \cdot T_{RRUS}}{144} = 0.6$  sf

Total RRUS Wind Force =  $F_{RRUS} := q_{Z_{Ant}} \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{RRUSS} = 19$  lbs

**Wind Load (with ice)**

Surface Area for One RRUS w/ Ice =  $SA_{ICERRUSF} := \frac{(L_{RRUS} + 2 \cdot t_{iz}) \cdot (W_{RRUS} + 2 \cdot t_{iz})}{144} = 2.4$  sf

Total RRUS Wind Force w/ Ice =  $F_{i_{RRUS}} := q_{Z_{ice}} \cdot Ant \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{ICERRUSF} = 17$  lbs

Surface Area for One RRUS w/ Ice =  $SA_{ICERRUSS} := \frac{(L_{RRUS} + 2 \cdot t_{iz}) \cdot (T_{RRUS} + 2 \cdot t_{iz})}{144} = 1.4$  sf

Total RRUS Wind Force w/ Ice =  $F_{i_{RRUS}} := q_{Z_{ice}} \cdot Ant \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{ICERRUSS} = 9$  lbs

**Gravity Load (without ice)**

Weight of All RRUSs =  $W_{T_{RRUS}} \cdot N_{RRUS} = 47$  lbs

**Gravity Loads (ice only)**

Volume of Each RRUS =  $V_{RRUS} := L_{RRUS} \cdot W_{RRUS} \cdot T_{RRUS} = 1062$  cu in

Volume of Ice on Each RRUS =  $V_{ice} := (L_{RRUS} + 2 \cdot t_{iz})(W_{RRUS} + 2 \cdot t_{iz})(T_{RRUS} + 2 \cdot t_{iz}) - V_{RRUS} = 2425$  cu in

Weight of Ice on Each RRUS =  $W_{ICERRUS} := \frac{V_{ice}}{1728} \cdot \rho = 79$  lbs

Weight of Ice on All RRUSs =  $W_{ICERRUS} \cdot N_{RRUS} = 79$  lbs

**Development of Wind & Ice Load on RRUS**

**RRUS Data:**

RRUS Model =	Ericsson 4424
RRUS Shape =	Flat (User Input)
RRUS Height =	$L_{RRUS} := 16.5$ in (User Input)
RRUS Width =	$W_{RRUS} := 13.5$ in (User Input)
RRUS Thickness =	$T_{RRUS} := 9.6$ in (User Input)
RRUS Weight =	$W_{T_{RRUS}} := 88$ lbs (User Input)
Number of RRUSs =	$N_{RRUS} := 1$ (User Input)
RRUS Aspect Ratio =	$A_{r_{RRUS}} := \frac{L_{RRUS}}{W_{RRUS}} = 1.2$
RRUS Force Coefficient =	$C_{a_{RRUS}} = 1.2$

**Wind Load (without ice)**

Surface Area for One RRUS =  $SA_{RRUSF} := \frac{L_{RRUS} \cdot W_{RRUS}}{144} = 1.5$  sf

Total RRUS Wind Force =  $F_{RRUS} := q_{Z_{Ant}} \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{RRUSF} = 53$  lbs

Surface Area for One RRUS =  $SA_{RRUSS} := \frac{L_{RRUS} \cdot T_{RRUS}}{144} = 1.1$  sf

Total RRUS Wind Force =  $F_{RRUS} := q_{Z_{Ant}} \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{RRUSS} = 38$  lbs

**Wind Load (with ice)**

Surface Area for One RRUS w/ Ice =  $SA_{ICERRUSF} := \frac{(L_{RRUS} + 2 \cdot t_{iz}) \cdot (W_{RRUS} + 2 \cdot t_{iz})}{144} = 2.7$  sf

Total RRUS Wind Force w/ Ice =  $F_{i_{RRUS}} := q_{z_{ice}} \cdot Ant \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{ICERRUSF} = 19$  lbs

Surface Area for One RRUS w/ Ice =  $SA_{ICERRUSS} := \frac{(L_{RRUS} + 2 \cdot t_{iz}) \cdot (T_{RRUS} + 2 \cdot t_{iz})}{144} = 2.1$  sf

Total RRUS Wind Force w/ Ice =  $F_{i_{RRUS}} := q_{z_{ice}} \cdot Ant \cdot G_H \cdot C_{a_{RRUS}} \cdot K_a \cdot SA_{ICERRUSS} = 15$  lbs

**Gravity Load (without ice)**

Weight of All RRUSs =  $W_{T_{RRUS}} \cdot N_{RRUS} = 88$  lbs

**Gravity Loads (ice only)**


Volume of Each RRUS =  $V_{RRUS} := L_{RRUS} \cdot W_{RRUS} \cdot T_{RRUS} = 2138$  cu in

Volume of Ice on Each RRUS =  $V_{ice} := (L_{RRUS} + 2 \cdot t_{iz}) \cdot (W_{RRUS} + 2 \cdot t_{iz}) \cdot (T_{RRUS} + 2 \cdot t_{iz}) - V_{RRUS} = 3305$  cu in

Weight of Ice on Each RRUS =  $W_{ICERRUS} := \frac{V_{ice}}{1728} \cdot \rho_d = 107$  lbs

Weight of Ice on All RRUSs =  $W_{ICERRUS} \cdot N_{RRUS} = 107$  lbs





Envelope Only Solution

Centek

TJL

20074.50

CTNH362B  
Member Framing

July 8, 2020 at 3:04 PM

Mount.r3d

**(Global) Model Settings**

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation?	Yes
Increase Nailing Capacity for Wind?	Yes
Include Warping?	Yes
Trans Load Btwn Intersecting Wood Wall?	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Include P-Delta for Walls?	Yes
Automatically Iterate Stiffness for Walls?	Yes
Max Iterations for Wall Stiffness	3
Gravity Acceleration (ft/sec^2)	32.2
Wall Mesh Size (in)	12
Eigensolution Convergence Tol. (1.E-)	4
Vertical Axis	Y
Global Member Orientation Plane	XZ
Static Solver	Sparse Accelerated
Dynamic Solver	Accelerated Solver

Hot Rolled Steel Code	AISC 14th(360-10): LRFD
Adjust Stiffness?	Yes(Iterative)
RISAConnection Code	AISC 14th(360-10): ASD
Cold Formed Steel Code	AISI S100-10: ASD
Wood Code	AWC NDS-12: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-11
Masonry Code	ACI 530-11: ASD
Aluminum Code	AA ADM1-10: ASD - Building
Stainless Steel Code	AISC 14th(360-10): ASD
Adjust Stiffness?	Yes(Iterative)

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parme Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections?	Yes
Use Cracked Sections Slab?	No
Bad Framing Warnings?	No
Unused Force Warnings?	Yes
Min 1 Bar Diam. Spacing?	No
Concrete Rebar Set	REBAR_SET_ASTMA615
Min % Steel for Column	1
Max % Steel for Column	8

**(Global) Model Settings, Continued**

Seismic Code	ASCE 7-10
Seismic Base Elevation (ft)	Not Entered
Add Base Weight?	Yes
Ct X	.02
Ct Z	.02
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	3
R Z	3
Ct Exp. X	.75
Ct Exp. Z	.75
SD1	1
SDS	1
S1	1
TL (sec)	5
Risk Cat	I or II
Drift Cat	Other
Om Z	1
Om X	1
Cd Z	4
Cd X	4
Rho Z	1
Rho X	1
Footing Overturning Safety Factor	1
Optimize for OTM/Sliding	No
Check Concrete Bearing	No
Footing Concrete Weight (k/ft^3)	150.001
Footing Concrete f'c (ksi)	4
Footing Concrete Ec (ksi)	3644
Lambda	1
Footing Steel fy (ksi)	60
Minimum Steel	0.0018
Maximum Steel	0.0075
Footing Top Bar	#3
Footing Top Bar Cover (in)	2
Footing Bottom Bar	#3
Footing Bottom Bar Cover (in)	3.5
Pedestal Bar	#3
Pedestal Bar Cover (in)	1.5
Pedestal Ties	#3

**Hot Rolled Steel Properties**

	Label	E [ksi]	G [ksi]	Nu	Therm (\1...	Density[k/ft^3]	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	58	1.2
3	A992	29000	11154	.3	.65	.49	50	1.1	58	1.2
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.3	58	1.1
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.2	58	1.1
6	A53 Grade B	29000	11154	.3	.65	.49	35	1.5	58	1.2

### Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rul...A [in2]	lyy [in4]	lzz [in4]	J [in4]	
1	Outrigger	HSS4X4X4	Beam	Tube	A500 Gr.46	Typical	3.37	7.8	7.8	12.8
2	Horz	HSS4X4X4	Beam	Pipe	A500 Gr.46	Typical	3.37	7.8	7.8	12.8
3	Antenna Mast	PIPE_2.0	Column	Pipe	A53 Grade B	Typical	1.02	.627	.627	1.25
4	Vert	PIPE_4.0	Column	Pipe	A53 Grade B	Typical	2.96	6.82	6.82	13.6
5	Stabilizer Kit	PIPE_2.0	Beam	Pipe	A53 Grade B	Typical	1.02	.627	.627	1.25

### Hot Rolled Steel Design Parameters

	Label	Shape	Length[ft]	Lbyy[ft]	Lbzz[ft]	Lcomp top[...Lcomp bot[...L-torq...	Kyy	Kzz	Cb	Functi...
1	M1	Outrigger	2.5			Lbyy				Lateral
2	M2	Vert	2			Lbyy				Lateral
3	M3	Horz	10.5			Lbyy				Lateral
4	M4	Antenna Mast	8			Lbyy				Lateral
5	M5	Antenna Mast	6			Lbyy				Lateral
6	M6	Antenna Mast	6			Lbyy				Lateral
7	M7	Antenna Mast	6			Lbyy				Lateral
8	M8	Stabilizer Kit	10.5			Lbyy				Lateral
9	M9	Stabilizer Kit	3.905			Lbyy				Lateral
10	M10	Stabilizer Kit	3.905			Lbyy				Lateral

### Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(d...	Section/Shape	Type	Design List	Material	Design Rul...
1	M1	N1	N2			Outrigger	Beam	Tube	A500 Gr...	Typical
2	M2	N3	N4			Vert	Column	Pipe	A53 Gra...	Typical
3	M3	N6	N5			Horz	Beam	Pipe	A500 Gr...	Typical
4	M4	N12	N15			Antenna Mast	Column	Pipe	A53 Gra...	Typical
5	M5	N11	N14			Antenna Mast	Column	Pipe	A53 Gra...	Typical
6	M6	N10	N13			Antenna Mast	Column	Pipe	A53 Gra...	Typical
7	M7	N18	N17			Antenna Mast	Column	Pipe	A53 Gra...	Typical
8	M8	N21	N20			Stabilizer Kit	Beam	Pipe	A53 Gra...	Typical
9	M9	N22	N19			Stabilizer Kit	Beam	Pipe	A53 Gra...	Typical
10	M10	N19	N23			Stabilizer Kit	Beam	Pipe	A53 Gra...	Typical

### Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Dia...
1	N1	0	0	0	0	
2	N2	0	0	2.5	0	
3	N3	0	1	2.5	0	
4	N4	0	-1	2.5	0	
5	N5	5.25	0	2.5	0	
6	N6	-5.25	0	2.5	0	
7	N7	5	0	2.5	0	
8	N8	2	0	2.5	0	
9	N9	-5	0	2.5	0	
10	N10	5	-1.5	2.5	0	
11	N11	2	-1.5	2.5	0	
12	N12	-5	-2.5	2.5	0	

**Joint Coordinates and Temperatures (Continued)**

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Dia...
13	N13	5	4.5	2.5	0	
14	N14	2	4.5	2.5	0	
15	N15	-5	5.5	2.5	0	
16	N16	-2	0	2.5	0	
17	N17	-2	-1.5	2.5	0	
18	N18	-2	4.5	2.5	0	
19	N19	0	2.5	0	0	
20	N20	5.25	2.5	2.5	0	
21	N21	-5.25	2.5	2.5	0	
22	N22	-3	2.5	2.5	0	
23	N23	3	2.5	2.5	0	
24	N24	5	2.5	2.5	0	
25	N25	2	2.5	2.5	0	
26	N26	-5	2.5	2.5	0	
27	N27	-2	2.5	2.5	0	

**Joint Boundary Conditions**

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]
1	N1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2	N19	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

**Member Point Loads (BLC 2 : Equipment Weight)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M4	Y	-.077	.5
2	M4	Y	-.077	7.5
3	M6	Y	-.023	.5
4	M6	Y	-.023	5.5
5	M4	Y	-.074	%50
6	M7	Y	-.052	.5
7	M7	Y	-.052	3.5
8	M4	Y	-.088	7
9	M4	Y	-.107	7
10	M6	Y	-.047	%50

**Member Point Loads (BLC 3 : Ice Weight)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M4	Y	-.297	.5
2	M4	Y	-.297	7.5
3	M6	Y	-.097	.5
4	M6	Y	-.097	5.5
5	M4	Y	-.103	%50
6	M7	Y	-.107	.5
7	M7	Y	-.107	3.5
8	M6	Y	-.079	%50

**Member Point Loads (BLC 4 : Wind w/ Ice X)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M4	X	.034	.5

**Member Point Loads (BLC 4 : Wind w/ Ice X) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
2	M4	X	.034	7.5
3	M6	X	.012	.5
4	M6	X	.012	5.5
5	M4	X	.014	%50
6	M7	X	.012	.5
7	M7	X	.012	3.5
8	M4	X	.015	7
9	M6	X	.009	%50

**Member Point Loads (BLC 5 : Wind X)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M4	X	.106	.5
2	M4	X	.106	7.5
3	M6	X	.023	.5
4	M6	X	.023	5.5
5	M4	X	.037	%50
6	M7	X	.033	.5
7	M7	X	.033	3.5
8	M4	X	.038	7
9	M6	X	.019	%50

**Member Point Loads (BLC 6 : Wind w/ Ice Z)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M4	Z	.074	.5
2	M4	Z	.074	7.5
3	M6	Z	.028	.5
4	M6	Z	.028	5.5
5	M7	Z	.023	.5
6	M7	Z	.023	3.5

**Member Point Loads (BLC 7 : Wind Z)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M4	Z	.292	.5
2	M4	Z	.292	7.5
3	M6	Z	.093	.5
4	M6	Z	.093	5.5
5	M7	Z	.082	.5
6	M7	Z	.082	3.5

**Member Distributed Loads (BLC 4 : Wind w/ Ice X)**

	Member Label	Direction	Start Magnitude[k/ft,...	End Magnitude[k/ft,F...	Start Location[ft,%]	End Location[ft,%]
1	M4	X	.003	.003	0	0
2	M7	X	.003	.003	0	0
3	M5	X	.003	.003	0	0
4	M6	X	.003	.003	0	0
5	M2	X	.003	.003	0	0
6	M1	X	.003	.003	0	0
7	M9	X	.003	.003	0	0
8	M10	X	.003	.003	0	0

**Member Distributed Loads (BLC 5 : Wind X)**

	Member Label	Direction	Start Magnitude[k/ft,...	End Magnitude[k/ft,F...	Start Location[ft,%]	End Location[ft,%]
1	M4	X	.009	.009	0	0
2	M7	X	.009	.009	0	0
3	M5	X	.009	.009	0	0
4	M6	X	.009	.009	0	0
5	M2	X	.009	.009	0	0
6	M1	X	.009	.009	0	0
7	M9	X	.009	.009	0	0
8	M10	X	.009	.009	0	0

**Member Distributed Loads (BLC 6 : Wind w/ Ice Z)**

	Member Label	Direction	Start Magnitude[k/ft,...	End Magnitude[k/ft,F...	Start Location[ft,%]	End Location[ft,%]
1	M5	Z	.003	.003	0	0
2	M3	Z	.003	.003	0	0
3	M8	Z	.003	.003	0	0
4	M2	Z	.003	.003	0	0
5	M9	Z	.003	.003	0	0
6	M10	Z	.003	.003	0	0

**Member Distributed Loads (BLC 7 : Wind Z)**

	Member Label	Direction	Start Magnitude[k/ft,...	End Magnitude[k/ft,F...	Start Location[ft,%]	End Location[ft,%]
1	M5	Z	.009	.009	0	0
2	M3	Z	.009	.009	0	0
3	M8	Z	.009	.009	0	0
4	M2	Z	.009	.009	0	0
5	M9	Z	.009	.009	0	0
6	M10	Z	.009	.009	0	0

**Basic Load Cases**

	BLC Description	Category	X Gra...	Y Gra...	Z Gra...	Joint	Point	Distrib...	Area(... Surfa...
1	Self Weight	DL		-1					
2	Equipment Weight	DL					10		
3	Ice Weight	DL					8		
4	Wind w/ Ice X	WLX					9	8	
5	Wind X	WLX					9	8	
6	Wind w/ Ice Z	WLZ					6	6	
7	Wind Z	WLZ					6	6	

**Load Combinations**

	Description	Solve	P...	S...	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..	BLCFac..
1	1.2D + 1.6W (X-direc...	Yes	Y		1	1.2	2	1.2	5	1.6				
2	0.9D + 1.6W (X-direc...	Yes	Y		1	.9	2	.9	5	1.6				
3	1.2D + 1.0Di + 1.0Wi...	Yes	Y		1	1.2	2	1.2	3	1	4	1		
4	1.2D + 1.6W (Z-direc...	Yes	Y		1	1.2	2	1.2	7	1.6				
5	0.9D + 1.6W (Z-direc...	Yes	Y		1	.9	2	.9	7	1.6				
6	1.2D + 1.0Di + 1.0Wi...	Yes	Y		1	1.2	2	1.2	3	1	6	1		

### Envelope Joint Reactions

	Joint		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	N1	max	-.732	5	2.094	6	.417	3	-1.181	5	-1.097	6	.005	5
2		min	-1.08	3	.764	2	-.38	5	-4.317	3	-2.974	4	-1.672	6
3	N19	max	1.004	6	.237	3	-.148	2	-.063	5	.572	6	.126	5
4		min	-.269	2	-.018	5	-1.695	4	-.334	3	-.627	5	-.656	3
5	Totals:	max	0	6	2.316	6	0	3						
6		min	-1.22	1	.849	2	-2.024	4						

### Envelope Joint Displacements

	Joint		X [in]	LC	Y [in]	LC	Z [in]	LC	X Rotation [rad]	LC	Y Rotatio...	LC	Z Rotatio...	LC
1	N1	max	0	6	0	6	0	6	0	6	0	6	0	6
2		min	0	1	0	1	0	1	0	1	0	1	0	1
3	N2	max	.069	5	-.015	5	0	5	3.446e-03	3	3.931e-03	5	4.216e-03	6
4		min	.009	6	-.081	3	0	3	2.154e-04	5	-3.28e-04	3	-1.253e-05	5
5	N3	max	.069	5	-.015	5	.041	3	3.446e-03	3	3.931e-03	5	4.216e-03	6
6		min	-.041	6	-.081	3	.003	5	2.176e-04	5	-3.28e-04	3	-1.253e-05	5
7	N4	max	.075	4	-.015	5	-.002	5	3.446e-03	3	3.931e-03	5	4.216e-03	6
8		min	.055	2	-.081	3	-.042	3	2.132e-04	5	-3.28e-04	3	-1.253e-05	5
9	N5	max	.069	5	.066	6	.056	6	3.328e-03	3	2.739e-03	2	1.752e-03	3
10		min	.009	6	-.089	5	-.187	5	-5.86e-04	5	-1.181e-03	6	-1.613e-03	5
11	N6	max	.07	5	-.049	5	.42	5	1.089e-03	3	8.251e-03	5	8.223e-03	3
12		min	.01	6	-.558	3	-.11	3	-2.849e-03	5	-2.199e-03	3	3.662e-04	5
13	N7	max	.069	5	.061	6	.053	6	3.328e-03	3	2.739e-03	2	1.752e-03	3
14		min	.009	6	-.084	5	-.18	5	-5.86e-04	5	-1.181e-03	6	-1.613e-03	5
15	N8	max	.069	5	-.005	6	.014	6	3.235e-03	3	3.068e-03	5	2.305e-03	6
16		min	.009	6	-.031	4	-.083	5	-2.359e-04	5	-8.537e-04	6	-1.164e-03	5
17	N9	max	.07	5	-.048	5	.396	5	1.089e-03	3	8.251e-03	5	8.223e-03	3
18		min	.01	6	-.533	3	-.103	3	-2.849e-03	5	-2.199e-03	3	3.662e-04	5
19	N10	max	.045	4	.061	6	-.002	6	3.325e-03	3	2.739e-03	2	1.826e-03	3
20		min	.039	2	-.084	5	-.173	2	-1.322e-03	5	-1.181e-03	6	-1.613e-03	5
21	N11	max	.054	4	-.005	6	-.04	6	3.235e-03	3	3.068e-03	5	2.317e-03	3
22		min	.042	2	-.031	4	-.082	1	-3.161e-04	5	-8.537e-04	6	-1.164e-03	5
23	N12	max	.273	3	-.048	5	.686	5	1.083e-03	3	8.251e-03	5	8.92e-03	3
24		min	.081	5	-.533	3	-.136	3	-1.209e-02	5	-2.199e-03	3	3.657e-04	5
25	N13	max	.162	5	.06	6	.236	6	3.856e-03	4	2.535e-03	2	2.595e-03	6
26		min	-.144	6	-.084	5	-.148	2	1.223e-04	2	-1.959e-03	6	-1.697e-03	5
27	N14	max	.15	5	-.005	6	.098	3	1.179e-03	6	3.353e-03	5	3.012e-03	6
28		min	-.154	6	-.031	4	-.101	5	6.869e-05	5	-2.154e-03	6	-1.215e-03	5
29	N15	max	.34	2	-.049	5	1.308	5	2.628e-02	5	1.574e-02	5	5.069e-03	6
30		min	-.265	6	-.534	3	-.177	3	-1.29e-03	3	-9.38e-04	3	-9.264e-03	2
31	N16	max	.069	5	-.026	5	.125	5	1.965e-03	3	6.33e-03	5	7.491e-03	6
32		min	.01	6	-.232	3	-.028	3	-1.257e-03	5	-1.758e-03	3	5.651e-04	5
33	N17	max	.146	3	-.026	5	.148	5	1.965e-03	3	6.33e-03	5	7.495e-03	3
34		min	.073	2	-.232	3	-.064	3	-1.257e-03	5	-1.758e-03	3	5.651e-04	5
35	N18	max	.136	5	-.027	5	.115	5	2.078e-03	5	5.312e-03	5	4.942e-03	6
36		min	-.201	6	-.233	3	-.076	3	-9.076e-04	3	-3.332e-03	3	-5.445e-04	5
37	N19	max	0	6	0	6	0	6	0	6	0	6	0	6
38		min	0	1	0	1	0	1	0	1	0	1	0	1
39	N20	max	.121	5	.068	6	.16	6	3.206e-03	6	2.535e-03	2	2.592e-03	6
40		min	-.082	6	-.089	5	-.171	5	1.223e-04	2	-1.959e-03	6	-1.697e-03	5







**Envelope Joint Displacements (Continued)**

	Joint		X [in]	LC	Y [in]	LC	Z [in]	LC	X Rotation [rad]	LC	Y Rotatio...	LC	Z Rotatio...	LC
41	N21	max	.123	5	-.046	5	.553	5	1.17e-02	5	1.574e-02	5	4.998e-03	6
42		min	-.083	6	-.547	3	-.134	3	-1.272e-03	3	-9.38e-04	3	-2.13e-03	2
43	N22	max	.124	5	-.032	5	.154	5	3.349e-03	4	9.182e-03	5	9.592e-03	3
44		min	-.083	6	-.323	3	-.096	3	3.568e-04	2	-3.046e-03	3	8.785e-04	5
45	N23	max	.121	5	.02	6	.098	6	1.381e-03	6	3.244e-03	5	1.56e-03	3
46		min	-.082	6	-.047	5	-.143	5	3.203e-04	2	-2.729e-03	6	-1.369e-03	5
47	N24	max	.121	5	.06	6	.154	6	3.206e-03	6	2.535e-03	2	2.592e-03	6
48		min	-.082	6	-.084	5	-.169	5	1.223e-04	2	-1.959e-03	6	-1.697e-03	5
49	N25	max	.121	5	-.005	6	.071	3	1.152e-03	3	3.353e-03	5	3.012e-03	6
50		min	-.082	6	-.031	4	-.102	5	-1.214e-04	5	-2.154e-03	6	-1.215e-03	5
51	N26	max	.123	5	-.048	5	.505	5	1.17e-02	5	1.574e-02	5	4.998e-03	6
52		min	-.083	6	-.533	3	-.131	3	-1.272e-03	3	-9.38e-04	3	-2.131e-03	2
53	N27	max	.123	5	-.027	5	.073	5	6.16e-04	5	5.312e-03	5	4.96e-03	3
54		min	-.083	6	-.233	3	-.059	6	-9.06e-04	3	-3.332e-03	3	-5.442e-04	5

**Envelope AISC 14th(360-10): LRFD Steel Code Checks**

Member	Shape	Code Check	Lo...	LC	She...Lo.....	phi*P...	phi*P...	phi*...	phi*...	Cb	Eqn				
1	M1	HSS4X4X4	.341	0	3	.177	0	y	6	135....	139....	16.181	16.181	1.9...	H1-...
2	M2	PIPE 4.0	.001	1	4	.001	1		4	92.055	93.24	10.631	10.631	1	H1-...
3	M3	HSS4X4X4	.303	5.25	3	.098	5.25	y	6	87.952	139....	16.181	16.181	1.6...	H1-...
4	M4	PIPE 2.0	.672	5	4	.227	5		4	14.916	32.13	1.872	1.872	4.6...	H1-...
5	M5	PIPE 2.0	.101	1.5	6	.040	4		3	20.867	32.13	1.872	1.872	2.1...	H1-...
6	M6	PIPE 2.0	.134	1.5	6	.062	4		4	20.867	32.13	1.872	1.872	2.2...	H1-...
7	M7	PIPE 2.0	.524	4.5	6	.110	2		6	20.867	32.13	1.872	1.872	2.1...	H1-...
8	M8	PIPE 2.0	.614	2....	4	.316	2....		5	8.922	32.13	1.872	1.872	2.9...	H3-6
9	M9	PIPE 2.0	.394	3....	6	.109	3....		3	26.761	32.13	1.872	1.872	2.1...	H1-...
10	M10	PIPE 2.0	.248	0	5	.043	3....		3	26.761	32.13	1.872	1.872	1.8...	H1-...



Member Code Checks Displayed (Enveloped)  
Envelope Only Solution

Centek
TJL
20074.50

CTNH362B
Unity Check

July 8, 2020 at 3:04 PM
Mount.r3d

# Exhibit F

## **Power Density/RF Emissions Report**

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT  
EVALUATION OF HUMAN EXPOSURE POTENTIAL  
TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CTNH362B

NH362/Boardman\_MP  
33 Boardman Road  
New Milford, Connecticut 06776

**July 25, 2020**

**EBI Project Number: 6220003393**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>23.69%</b>

July 25, 2020

T-Mobile

Attn: Jason Overbey, RF Manager  
35 Griffin Road South  
Bloomfield, Connecticut 06002

Emissions Analysis for Site: CTNH362B - NH362/Boardman\_MP

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **33 Boardman Road in New Milford, Connecticut** for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately  $400 \mu\text{W}/\text{cm}^2$  and  $467 \mu\text{W}/\text{cm}^2$ , respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed T-Mobile Wireless antenna facility located at 33 Boardman Road in New Milford, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 LTE channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 1 NR channel (600 MHz Band) was considered for each sector of the proposed installation. This Channel has a transmit power of 80 Watts.
- 3) 2 LTE channels (700 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 4) 4 GSM channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 5) 2 LTE channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.

- 6) 2 LTE channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 7) 2 LTE channels (BRS Band - 2500 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 8) 2 NR channels (BRS Band - 2500 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 9) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 10) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 11) The antennas used in this modeling are the RFS APX16DWV-I6DWV-S-E-A20 for the 2100 MHz channel(s), the Ericsson AIR 6449 for the 2500 MHz / 2500 MHz channel(s), the RFS APXVAARR24\_43-U-NA20 for the 600 MHz / 600 MHz / 700 MHz / 1900 MHz / 1900 MHz channel(s) in Sector A, the RFS APX16DWV-I6DWV-S-E-A20 for the 2100 MHz channel(s), the Ericsson AIR 6449 for the 2500 MHz / 2500 MHz channel(s), the RFS APXVAARR24\_43-U-NA20 for the 600 MHz / 600 MHz / 700 MHz / 1900 MHz / 1900 MHz channel(s) in Sector B, the RFS APX16DWV-I6DWV-S-E-A20 for the 2100 MHz channel(s), the Ericsson AIR 6449 for the 2500 MHz / 2500 MHz channel(s), the RFS APXVAARR24\_43-U-NA20 for the 600 MHz / 600 MHz / 700 MHz / 1900 MHz / 1900 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 12) The antenna mounting height centerline of the proposed antennas is 140 feet above ground level (AGL).
- 13) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 14) All calculations were done with respect to uncontrolled / general population threshold limits.



## T-Mobile Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APX16DWV-16DWV-S-E-A20	Make / Model:	RFS APX16DWV-16DWV-S-E-A20	Make / Model:	RFS APX16DWV-16DWV-S-E-A20
Frequency Bands:	2100 MHz	Frequency Bands:	2100 MHz	Frequency Bands:	2100 MHz
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	140 feet	Height (AGL):	140 feet	Height (AGL):	140 feet
Channel Count:	2	Channel Count:	2	Channel Count:	2
Total TX Power (W):	120 Watts	Total TX Power (W):	120 Watts	Total TX Power (W):	120 Watts
ERP (W):	4,668.54	ERP (W):	4,668.54	ERP (W):	4,668.54
Antenna A1 MPE %:	<b>0.86%</b>	Antenna B1 MPE %:	<b>0.86%</b>	Antenna C1 MPE %:	<b>0.86%</b>
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Ericsson AIR 6449	Make / Model:	Ericsson AIR 6449	Make / Model:	Ericsson AIR 6449
Frequency Bands:	2500 MHz / 2500 MHz	Frequency Bands:	2500 MHz / 2500 MHz	Frequency Bands:	2500 MHz / 2500 MHz
Gain:	22.05 dBd / 22.05 dBd	Gain:	22.05 dBd / 22.05 dBd	Gain:	22.05 dBd / 22.05 dBd
Height (AGL):	140 feet	Height (AGL):	140 feet	Height (AGL):	140 feet
Channel Count:	4	Channel Count:	4	Channel Count:	4
Total TX Power (W):	160 Watts	Total TX Power (W):	160 Watts	Total TX Power (W):	160 Watts
ERP (W):	25,651.93	ERP (W):	25,651.93	ERP (W):	25,651.93
Antenna A2 MPE %:	<b>4.71%</b>	Antenna B2 MPE %:	<b>4.71%</b>	Antenna C2 MPE %:	<b>4.71%</b>
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	RFS APXVAARR24_43-U-NA20	Make / Model:	RFS APXVAARR24_43-U-NA20	Make / Model:	RFS APXVAARR24_43-U-NA20
Frequency Bands:	600 MHz / 600 MHz / 700 MHz / 1900 MHz / 1900 MHz	Frequency Bands:	600 MHz / 600 MHz / 700 MHz / 1900 MHz / 1900 MHz	Frequency Bands:	600 MHz / 600 MHz / 700 MHz / 1900 MHz / 1900 MHz
Gain:	12.95 dBd / 12.95 dBd / 13.35 dBd / 15.65 dBd / 15.65 dBd	Gain:	12.95 dBd / 12.95 dBd / 13.35 dBd / 15.65 dBd / 15.65 dBd	Gain:	12.95 dBd / 12.95 dBd / 13.35 dBd / 15.65 dBd / 15.65 dBd
Height (AGL):	140 feet	Height (AGL):	140 feet	Height (AGL):	140 feet
Channel Count:	11	Channel Count:	11	Channel Count:	11
Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts
ERP (W):	12,873.80	ERP (W):	12,873.80	ERP (W):	12,873.80
Antenna A3 MPE %:	<b>3.39%</b>	Antenna B3 MPE %:	<b>3.39%</b>	Antenna C3 MPE %:	<b>3.39%</b>

Site Composite MPE %	
Carrier	MPE %
T-Mobile (Max at Sector A):	8.95%
Sprint	2.37%
AT&T	8.92%
Verizon	3.45%
<b>Site Total MPE % :</b>	<b>23.69%</b>

T-Mobile MPE % Per Sector	
T-Mobile Sector A Total:	8.95%
T-Mobile Sector B Total:	8.95%
T-Mobile Sector C Total:	8.95%
Site Total MPE % :	23.69%

### T-Mobile Maximum MPE Power Values (Sector A)

T-Mobile Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
T-Mobile 2100 MHz LTE	2	2334.27	140.0	8.56	2100 MHz LTE	1000	0.86%
T-Mobile 2500 MHz LTE	2	6412.98	140.0	23.53	2500 MHz LTE	1000	2.35%
T-Mobile 2500 MHz NR	2	6412.98	140.0	23.53	2500 MHz NR	1000	2.35%
T-Mobile 600 MHz LTE	2	591.73	140.0	2.17	600 MHz LTE	400	0.54%
T-Mobile 600 MHz NR	1	1577.94	140.0	2.89	600 MHz NR	400	0.72%
T-Mobile 700 MHz LTE	2	648.82	140.0	2.38	700 MHz LTE	467	0.51%
T-Mobile 1900 MHz GSM	4	1101.85	140.0	8.08	1900 MHz GSM	1000	0.81%
T-Mobile 1900 MHz LTE	2	2203.69	140.0	8.08	1900 MHz LTE	1000	0.81%
						<b>Total:</b>	<b>8.95%</b>

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector A:	8.95%
Sector B:	8.95%
Sector C:	8.95%
T-Mobile Maximum MPE % (Sector A):	8.95%
Site Total:	23.69%
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **23.69%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

# Exhibit G

## **Mailing Receipts/Proof of Notice**

# View/Print Label

1. **Ensure there are no other shipping or tracking labels attached to your package.** Select the Print button on the print dialogue box that appears. Note: If your browser does not support this function, select Print from the File menu to print the label.

2. **Fold the printed label at the solid line below.** Place the label in a UPS Shipping Pouch. If you do not have a pouch, affix the folded label using clear plastic shipping tape over the entire label.

### 3. GETTING YOUR SHIPMENT TO UPS

#### Customers with a scheduled Pickup

- Your driver will pickup your shipment(s) as usual.

#### Customers without a scheduled Pickup

- Schedule a Pickup on [ups.com](https://www.ups.com) to have a UPS driver pickup all of your packages.
- Take your package to any location of The UPS Store®, UPS Access Point(TM) location, UPS Drop Box, UPS Customer Center, Staples® or Authorized Shipping Outlet near you. To find the location nearest you, please visit the 'Locations' Quick link at [ups.com](https://www.ups.com).

UPS Access Point™  
MICHAELS STORE # 7773  
75 INTERSTATE SHOP CTR  
RAMSEY NJ

UPS Access Point™  
THE UPS STORE  
115 FRANKLIN TPKE  
MAHWAH NJ

UPS Access Point™  
THE UPS STORE  
120 E MAIN ST  
RAMSEY NJ

FOLD HERE

NEIL GUERRIERO 3473040176 TRANSCEND WIRELESS 10 INDUSTRIAL AVE MAHWAH NJ 07430	0.0 LBS LTR 1 OF 1	SHIP TO: CONNECTICUT SITING COUNCIL 10 FRANKLIN SQUARE NEW BRITAIN CT 06051	CT 067 9-06 	UPS 2ND DAY AIR 2 TRACKING #: 1Z V25 742 02 9730 0346 	BILLING: P/P UPS CARBON NEUTRAL SHIPMENT	Reference #1: CTNH62B Reference #2: CSC XOL 20.08.05 NV45 31.0A 07/2020 
--	--------------------	--	--	--	---	--

# View/Print Label

1. **Ensure there are no other shipping or tracking labels attached to your package.** Select the Print button on the print dialogue box that appears. Note: If your browser does not support this function, select Print from the File menu to print the label.

2. **Fold the printed label at the solid line below.** Place the label in a UPS Shipping Pouch. If you do not have a pouch, affix the folded label using clear plastic shipping tape over the entire label.

### 3. GETTING YOUR SHIPMENT TO UPS

#### Customers with a scheduled Pickup

- Your driver will pickup your shipment(s) as usual.

#### Customers without a scheduled Pickup





- Schedule a Pickup on [ups.com](https://www.ups.com) to have a UPS driver pickup all of your packages.
- Take your package to any location of The UPS Store®, UPS Access Point(TM) location, UPS Drop Box, UPS Customer Center, Staples® or Authorized Shipping Outlet near you. To find the location nearest you, please visit the 'Locations' Quick link at [ups.com](https://www.ups.com).

UPS Access Point™  
MICHAELS STORE # 7773  
75 INTERSTATE SHOP CTR  
RAMSEY NJ

UPS Access Point™  
THE UPS STORE  
115 FRANKLIN TPKE  
MAHWAH NJ

UPS Access Point™  
THE UPS STORE  
120 E MAIN ST  
RAMSEY NJ

FOLD HERE

NEIL GUERRIERO 3473040176 TRANSCEND WIRELESS 10 INDUSTRIAL AVE MAHWAH NJ 07430	0.0 LBS LTR 1 OF 1
<b>SHIP TO:</b> JOE METZGER O AND G INDUSTRIES 112 WALL STREET TORRINGTON CT 06790	<b>CT 067 9-02</b> 
	<b>UPS 2ND DAY AIR</b> 2 TRACKING #: 1Z V25 742 02 9661 0334
	
BILLING: P/P UPS CARBON NEUTRAL SHIPMENT	
Reference #1: CTNH362B Reference #2: LL	 XOL 20.08.05 NV45 31.0A.07/2020

# View/Print Label

1. **Ensure there are no other shipping or tracking labels attached to your package.** Select the Print button on the print dialogue box that appears. Note: If your browser does not support this function, select Print from the File menu to print the label.

2. **Fold the printed label at the solid line below.** Place the label in a UPS Shipping Pouch. If you do not have a pouch, affix the folded label using clear plastic shipping tape over the entire label.

### 3. GETTING YOUR SHIPMENT TO UPS

#### Customers with a scheduled Pickup

- Your driver will pickup your shipment(s) as usual.

#### Customers without a scheduled Pickup





- Schedule a Pickup on [ups.com](https://www.ups.com) to have a UPS driver pickup all of your packages.
- Take your package to any location of The UPS Store®, UPS Access Point(TM) location, UPS Drop Box, UPS Customer Center, Staples® or Authorized Shipping Outlet near you. To find the location nearest you, please visit the 'Locations' Quick link at [ups.com](https://www.ups.com).

UPS Access Point™  
MICHAELS STORE # 7773  
75 INTERSTATE SHOP CTR  
RAMSEY NJ

UPS Access Point™  
THE UPS STORE  
115 FRANKLIN TPKE  
MAHWAH NJ

UPS Access Point™  
THE UPS STORE  
120 E MAIN ST  
RAMSEY NJ

FOLD HERE

NEIL GUERRIERO 3473040176 TRANSCEND WIRELESS 10 INDUSTRIAL AVE MAHWAH NJ 07430	0.0 LBS LTR 1 OF 1
<b>SHIP TO:</b> THE HONORABLE PETER BASS TOWN OF NEW MILFORD 10 MAIN STREET NEW MILFORD CT 06776	
	<b>CT 068 0-03</b> 
<b>UPS 2ND DAY AIR</b> TRACKING #: 1Z V25 742 02 9108 3468	<b>2</b>
	
BILLING: P/P UPS CARBON NEUTRAL SHIPMENT	
Reference #1: CTNH362B Reference #2: Mayor	 XOL 20.08.05 NV45 31.0A 07/2020

# View/Print Label

1. **Ensure there are no other shipping or tracking labels attached to your package.** Select the Print button on the print dialogue box that appears. Note: If your browser does not support this function, select Print from the File menu to print the label.

2. **Fold the printed label at the solid line below.** Place the label in a UPS Shipping Pouch. If you do not have a pouch, affix the folded label using clear plastic shipping tape over the entire label.

### 3. GETTING YOUR SHIPMENT TO UPS

#### Customers with a scheduled Pickup

- Your driver will pickup your shipment(s) as usual.

#### Customers without a scheduled Pickup

- Schedule a Pickup on [ups.com](https://www.ups.com) to have a UPS driver pickup all of your packages.
- Take your package to any location of The UPS Store®, UPS Access Point(TM) location, UPS Drop Box, UPS Customer Center, Staples® or Authorized Shipping Outlet near you. To find the location nearest you, please visit the 'Locations' Quick link at [ups.com](https://www.ups.com).

UPS Access Point™  
MICHAELS STORE # 7773  
75 INTERSTATE SHOP CTR  
RAMSEY NJ

UPS Access Point™  
THE UPS STORE  
115 FRANKLIN TPKE  
MAHWAH NJ

UPS Access Point™  
THE UPS STORE  
120 E MAIN ST  
RAMSEY NJ

FOLD HERE

NEIL GUERRIERO 3473040176 TRANSCEND WIRELESS 10 INDUSTRIAL AVE MAHWAH NJ 07430	0.0 LBS LTR 1 OF 1	<b>SHIP TO:</b> LAURA REGAN, TOWN PLANNER TOWN OF NEW MILFORD 10 MAIN STREET <b>NEW MILFORD CT 06776</b>	<b>CT 068 0-03</b> 	<b>UPS 2ND DAY AIR 2</b> TRACKING #: 1Z V25 742 02 9447 3479		BILLING: P/P UPS CARBON NEUTRAL SHIPMENT	 Reference #1: CTNH362B Reference #2: Planner XOL 20.08.05 NV45 31.0A 07/2020
--	--------------------	--	------------------------	---	--	---	--