



**Crown Castle**  
3530 Torington Way, Suite 300  
Charlotte, NC 28277

June 26, 2014

Melanie A. Bachman  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**RE: Sprint PCS-Exempt Modification - Crown Site BU: 876336**  
**Sprint PCS Site ID: CT03XC102**  
**Located at: 430 Middlesex Turnpike, Old Saybrook, CT 06475**

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Mr. Carl P. Fortuna, Jr., First Selectman, Town of Old Saybrook.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **430 Middlesex Turnpike, Old Saybrook, CT 06475**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

June 26, 2014

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Jeff Barbadora  
Real Estate Specialist

Enclosures


Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mr. Carl P. Fortuna, Jr., First Selectman  
Town of Old Saybrook  
Town Hall, 302 Main Street  
Old Saybrook, CT 06475

# Sprint



# CROWN CASTLE

PROJECT: 2.5 EQUIPMENT DEPLOYMENT  
 SITE NAME: OLD SAYBROOK  
 SITE CASCADE: CT03XC102  
 SITE NUMBER: 876336  
 SITE ADDRESS: 430 MIDDLESEX TURNPIKE  
 OLD SAYBROOK, CT 06475  
 SITE TYPE: MONOPOLE TOWER  
 MARKET: NORTHERN CONNECTICUT

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:  
**OLD SAYBROOK**

SITE CASCADE:  
**CT03XC102**

SITE ADDRESS:  
 430 MIDDLESEX TURNPIKE  
 OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:  
**TITLE SHEET & PROJECT DATA**

SHEET NUMBER:  
**T-1**

SITE INFORMATION	AREA MAP	PROJECT DESCRIPTION	DRAWING INDEX																																										
<p><b>TOWER OWNER:</b>            CROWN ATLANTIC COMPANY LLC            2000 CORPORATE DRIVE            CANONSBURG, PA 15317            (704) 405-6555</p> <p><b>LATITUDE (NAD83):</b>            41° 18' 44.5" N            41.313194°</p> <p><b>LONGITUDE (NAD83):</b>            72° 22' 48.7" W            -72.381056°</p> <p><b>COUNTY:</b>            MIDDLESEX</p> <p><b>ZONING JURISDICTION:</b>            CONNECTICUT SITING COUNCIL</p> <p><b>ZONING DISTRICT:</b>            TBD</p> <p><b>POWER COMPANY:</b>            CONNECTICUT LIGHT &amp; POWER            (860) 947-2000</p> <p><b>SPRINT PM:</b>            PETER GIARD            (508) 801-0074            peter.giard@sprint.com</p> <p><b>SPRINT CM:</b>            PETER CULBERT            (803) 203-6446            (803) 969-0686            peter.culbert@sprint.com</p> <p><b>CROWN CASTLE CM:</b>            JASON D'AMICO            (860) 209-0104            JASON.D'AMICO@CROWNCastle.COM</p>		<p>SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.</p> <ul style="list-style-type: none"> <li>INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS CABINET</li> <li>INSTALL (3) PANEL ANTENNAS</li> <li>INSTALL (3) RRU'S TO TOWER</li> <li>INSTALL (27) JUMPER CABLES</li> <li>INSTALL (1) HYBRID CABLE</li> <li>INSTALL (4) BATTERIES IN EXISTING BBU CABINET</li> </ul> <p>THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.</p>	<table border="1"> <thead> <tr> <th>SHEET NO:</th> <th>SHEET TITLE</th> <th>REV</th> </tr> </thead> <tbody> <tr> <td>T-1</td> <td>TITLE SHEET &amp; PROJECT DATA</td> <td>0</td> </tr> <tr> <td>SP-1</td> <td>SPRINT SPECIFICATIONS</td> <td>0</td> </tr> <tr> <td>SP-2</td> <td>SPRINT SPECIFICATIONS</td> <td>0</td> </tr> <tr> <td>SP-3</td> <td>SPRINT SPECIFICATIONS</td> <td>0</td> </tr> <tr> <td>A-1</td> <td>SITE PLAN</td> <td>0</td> </tr> <tr> <td>A-2</td> <td>TOWER ELEVATION &amp; CABLE PLAN</td> <td>0</td> </tr> <tr> <td>A-3</td> <td>ANTENNA LAYOUT &amp; MOUNTING DETAILS</td> <td>0</td> </tr> <tr> <td>A-4</td> <td>COLOR CODING &amp; NOTES</td> <td>0</td> </tr> <tr> <td>A-5</td> <td>EQUIPMENT &amp; MOUNTING DETAILS</td> <td>0</td> </tr> <tr> <td>A-6</td> <td>CIVIL DETAILS</td> <td>0</td> </tr> <tr> <td>A-7</td> <td>PLUMBING DIAGRAM</td> <td>0</td> </tr> <tr> <td>E-1</td> <td>ELECTRICAL &amp; GROUNDING PLAN</td> <td>0</td> </tr> <tr> <td>E-2</td> <td>ELECTRICAL &amp; GROUNDING DETAILS</td> <td>0</td> </tr> </tbody> </table>	SHEET NO:	SHEET TITLE	REV	T-1	TITLE SHEET & PROJECT DATA	0	SP-1	SPRINT SPECIFICATIONS	0	SP-2	SPRINT SPECIFICATIONS	0	SP-3	SPRINT SPECIFICATIONS	0	A-1	SITE PLAN	0	A-2	TOWER ELEVATION & CABLE PLAN	0	A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0	A-4	COLOR CODING & NOTES	0	A-5	EQUIPMENT & MOUNTING DETAILS	0	A-6	CIVIL DETAILS	0	A-7	PLUMBING DIAGRAM	0	E-1	ELECTRICAL & GROUNDING PLAN	0	E-2	ELECTRICAL & GROUNDING DETAILS	0
SHEET NO:	SHEET TITLE	REV																																											
T-1	TITLE SHEET & PROJECT DATA	0																																											
SP-1	SPRINT SPECIFICATIONS	0																																											
SP-2	SPRINT SPECIFICATIONS	0																																											
SP-3	SPRINT SPECIFICATIONS	0																																											
A-1	SITE PLAN	0																																											
A-2	TOWER ELEVATION & CABLE PLAN	0																																											
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0																																											
A-4	COLOR CODING & NOTES	0																																											
A-5	EQUIPMENT & MOUNTING DETAILS	0																																											
A-6	CIVIL DETAILS	0																																											
A-7	PLUMBING DIAGRAM	0																																											
E-1	ELECTRICAL & GROUNDING PLAN	0																																											
E-2	ELECTRICAL & GROUNDING DETAILS	0																																											
	<p><b>LOCATION MAP</b></p>	<p><b>APPLICABLE CODES</b></p> <p>ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.</p> <ol style="list-style-type: none"> <li>INTERNATIONAL BUILDING CODE (2012 IBC)</li> <li>TIA-EIA-222-G OR LATEST EDITION</li> <li>NFPA 780 - LIGHTNING PROTECTION CODE</li> <li>2011 NATIONAL ELECTRIC CODE OR LATEST EDITION</li> <li>ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS</li> <li>CT BUILDING CODE</li> <li>LOCAL BUILDING CODE</li> <li>CITY/COUNTY ORDINANCES</li> </ol>																																											



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

**SECTION 01 100 – SCOPE OF WORK**

**PART 1 – GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT 'STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES' ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
  - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
    1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
    5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
    3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
    4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - 'NEC') AND NFPA 101 (LIFE SAFETY CODE).
    5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
    6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
    7. AMERICAN CONCRETE INSTITUTE (ACI)
    8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
    9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
    10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
    11. PORTLAND CEMENT ASSOCIATION (PCA)
    12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
    13. BRICK INDUSTRY ASSOCIATION (BIA)
    14. AMERICAN WELDING SOCIETY (AWS)
    15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
    16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
    17. DOOR AND HARDWARE INSTITUTE (DHI)
    18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
    19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

**1.5 DEFINITIONS:**

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND 'A&E'. THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
  - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF 'AS-BUILT' DRAWINGS.
  - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
  - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.
 

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HERewith, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

**SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT**

**PART 1 – GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT 'STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES' ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
  - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
  - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
    1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
    2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
    3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
    4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
    5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
    6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
  - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
  - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
  - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

**SECTION 01 300 – CELL SITE CONSTRUCTION CO.**

**PART 1 – GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT 'STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES' ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 NOTICE TO PROCEED
  - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
  - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

**TOWER OWNER NOTIFICATION**  
 ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.

**PART 2 – PRODUCTS (NOT USED)**

**PART 3 – EXECUTION**

- 3.1 FUNCTIONAL REQUIREMENTS:
  - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
  - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
  - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
  - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:

OLD SAYBROOK

SITE CASCADE:

CT03XC102

SITE ADDRESS:

430 MIDDLESEX TURNPIKE  
 OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

**CONTINUE FROM SP-1**

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

**3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:**

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
  1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
  2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

**3.3 DELIVERABLES:**

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
  1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
  2. PROJECT PROGRESS REPORTS.
  3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
  4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS:
  - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
  - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
    1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
    2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
    3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
    4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
    5. CHEMICAL GROUNDING DESIGN
  - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

**1.4 TESTS AND INSPECTIONS:**

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
  2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
  3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
  1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
  2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
  3. ALL AVAILABLE JURISDICTIONAL INFORMATION
  4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

**3.1 REQUIREMENTS FOR TESTING:**

**A. THIRD PARTY TESTING AGENCY:**

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

**3.2 REQUIRED TESTS:**

**A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:**

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

**3.3 REQUIRED INSPECTIONS**

**A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.**

**B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:**

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNALIGN ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:

**OLD SAYBROOK**

SITE CASCADE:

**CT03XC102**

SITE ADDRESS:

**430 MIDDLESEX TURNPIKE  
OLD SAYBROOK, CT 06475**

SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:

**SP-2**

**CONTINUE FROM SP-2**

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
  8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
  9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL
  10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
  11. ALL AVAILABLE JURISDICTIONAL INFORMATION
  12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
  2. STRUCTURAL BACKFILL COMPACTION REPORTS.
  3. SITE RESISTANCE TO EARTH TEST.
  4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
  5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
  6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
  2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
  3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
  4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
  5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
  6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
  7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL
  8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
  9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

**1.2 RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

**3.1 WEEKLY REPORTS:**

- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

**3.2 PROJECT CONFERENCE CALLS:**

- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

**3.3 PROJECT TRACKING IN SMS:**

- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

**3.4 ADDITIONAL REPORTING:**

- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

**3.5 PROJECT PHOTOGRAPHS:**

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:

1. SHELTER AND TOWER OVERVIEW.
2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
5. PHOTOS OF TOWER SECTION STACKING.
6. CONCRETE TESTING / SAMPLES.
7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
11. COAX CABLE ENTRY INTO SHELTER.
12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
  25. ALL BTS GROUND CONNECTIONS.
  26. ALL GROUND TEST WELLS.
  27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
  28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
  29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
  30. GPS ANTENNAS.
  31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
  32. DOGHOUSE/CABLE EXIT FROM ROOF.
  33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
  34. MASTER BUS BAR.
  35. TELCO BOARD AND NIU.
  36. ELECTRICAL DISTRIBUTION WALL.
  37. CABLE ENTRY WITH SURGE SUPPRESSION.
  38. ENTRANCE TO EQUIPMENT ROOM.
  39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
  40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
  41. ANTENNA AND MAST GROUNDING.
  42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:



1033 Walerviet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:

**OLD SAYBROOK**

SITE CASCADE:

**CT03XC102**

SITE ADDRESS:

430 MIDDLESEX TURNPIKE  
OLD SAYBROOK, CT 06475



SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:



**SP-3**

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:

6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:  
 OLD SAYBROOK


SITE CASCADE:  
 CT03XC102

SITE ADDRESS:  
 430 MIDDLESEX TURNPIKE  
 OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:  
 SITE PLAN

SHEET NUMBER:  
 A-1






EXISTING ANTENNA & RRU LAYOUT

NO SCALE

1

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.


**NOTE:**  
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET



FINAL ANTENNA LAYOUT

NO SCALE

2



**NOTES:**

1. CUT DC CONDUCTORS TO LENGTH.
2. COIL FIBER CABLE AND SECURE AT SIDE OF RRU.
3. DO NOT EXCEED BEND RADIUS.

**NOTE:**  
CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

**NOTE:**  
SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.

**NOTE:**  
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS.

DETAIL NOT USED

NO SCALE

3

TYPICAL ANTENNA & RRU MOUNTING DETAILS

NO SCALE

4

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:  
OLD SAYBROOK

SITE CASCADE:  
CT03XC102

SITE ADDRESS:  
430 MIDDLESEX TURNPIKE  
OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:  
ANTENNA LAYOUT  
& MOUNTING DETAILS


SHEET NUMBER:  
A-3

NV CABLES			
BAND	INDICATOR	PORT	COLOR
800-1	YEL GRN	NV-1	GRN
1900-1	YEL RED	NV-2	BLU
1900-2	YEL BRN	NV-3	BRN
1900-3	YEL BLU	NV-4	WHT
1900-4	YEL SLT	NV-5	RED
800-2	YEL ORG	NV-6	SLT
SPARE	YEL WHT	NV-7	PPL
2500	YEL PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL WHT	GRN	GRN
YEL WHT	BLU	BLU
YEL WHT	BRN	BRN
YEL WHT	WHT	WHT
YEL WHT	RED	RED
YEL WHT	SLT	SLT
YEL WHT	PPL	PPL
YEL WHT	ORG	ORG

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2	White	No Tape	No Tape
	3	Brown	No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2	White	White	No Tape
	3	Brown	Brown	No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2	White	White	White
	3	Brown	Brown	Brown
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL GRN	GRN
1900-1	YEL RED	BLU
1900-2	YEL BRN	BRN
1900-3	YEL BLU	WHT
1900-4	YEL SLT	RED
800-1	YEL ORG	SLT
RESERVED	YEL WHT	PPL
RESERVED	YEL PPL	ORG

2.5 FREQUENCY	INDICATOR	ID
2500 -1	YEL WHT GRN	GRN
2500 -2	YEL WHT RED	RED
2500 -3	YEL WHT BRN	BRN
2500 -4	YEL WHT BLU	BLU
2500 -5	YEL WHT SLT	SLT
2500 -6	YEL WHT ORG	ORG
2500 -7	YEL WHT WHT	WHT
2500 -8	YEL WHT PPL	PPL



PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		5/22/14	SKB	0

SITE NAME:

OLD SAYBROOK

SITE CASCADE:

CT03XC102

SITE ADDRESS:

430 MIDDLESEX TURNPIKE  
OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:


COLOR CODING AND NOTES

SHEET NUMBER:


A-4

RRU: ALCATEL LUCENT TD-RRH8X20


COLOR: LIGHT GREY  
WEIGHT: 70 LBS.



SIDE VIEW



FRONT VIEW



PLAN VIEW

NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN

DS3 SURGE PROTECTOR

POWER INJECTOR 5-8

POWER INJECTOR 1-4

7210 SAS-M 2

7210 SAS-M 1

7205 SAR-B

LTE-BBU 2.5GHz

LTE-BBU FDD

CDMA MT-BBU GROWTH

CDMA MT-BBU PRIMARY

PDP1

PDP2

15MHz SPLITTER


ETHERNET HUB SEC-B

PRIMARY PROTECTION T1

SEC-B #1, #1 & #3

RECTIFIER SHELF PRIMARY

RECTIFIER SHELF 2.5GHz



FRONT VIEW

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:

OLD SAYBROOK

SITE CASCADE:

CT03XC102

SITE ADDRESS:

430 MIDDLESEX TURNPIKE  
OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:

EQUIPMENT &  
MOUNTING DETAILS

SHEET NUMBER:

A-5

2.5\_RRU

NO SCALE

1


NEW EQUIPMENT IN EXISTING CABINET

NO SCALE


2

ANTENNA: RFS APXVTM14-C-I20

RADOME MATERIAL: ASA  
RADOME COLOR: LIGHT GRAY  
DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)  
WEIGHT: 52.9 lbs  
CONNECTORS: (8) 4.1/9.5 DIN FEMALE  
(1) NF - CALIBRATION CONNECTOR



PLAN VIEW



2.5 ANTENNA

NO SCALE

3

DETAIL NOT USED

NO SCALE

4




**RFS HYBRIFLEX RISER CABLE SCHEDULE**

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
MN: HB058-M12-200F	200 ft	
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
MN: HB114-08U3M12-200F	200 ft	
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft


**RFS HYBRIFLEX JUMPER CABLE SCHEDULE**

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

**NOTE:**  
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE  
AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF  
HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.



**FIBER ONLY**



**FIBER JUNCTION BOX PENETRATION**

NO SCALE

2

2.5 CABLE CROSS SECTION DATA

NO SCALE

3

DETAIL NOT USED

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:

OLD SAYBROOK

SITE CASCADE:

CT03XC102

SITE ADDRESS:


430 MIDDLESEX TURNPIKE  
OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:


CIVIL DETAILS

SHEET NUMBER:


A-6



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLUMBING DIAGRAM

NO SCALE

1

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		5/22/14	SKB	0

SITE NAME:  
 OLD SAYBROOK

SITE CASCADE:  
 CT03XC102

SITE ADDRESS:  
 430 MIDDLESEX TURNPIKE  
 OLD SAYBROOK, CT 06475


SHEET DESCRIPTION:  
 CIVIL DETAILS

SHEET NUMBER:  
 A-7


PLAN NOT USED

NO SCALE 1

- LEGEND:**
- — EXISTING GROUND RING
  - CADWELD CONNECTION (EXOTHERMIC WELD)
  - ▲ MECHANICAL CONNECTION
  - ⊗ GROUND ROD
  - CABLE GROUND KIT



**NOTE:**  
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	SKB	0

SITE NAME:

**OLD SAYBROOK**

SITE CASCADE:

**CT03XC102**

SITE ADDRESS:

430 MIDDLESEX TURNPIKE  
OLD SAYBROOK, CT 06475


SHEET DESCRIPTION:

**ELECTRICAL &  
GROUNDING PLAN**

SHEET NUMBER:

**E-1**


**NOTES**  
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.




CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

**ELECTRICAL ONE-LINE DIAGRAM**

NO SCALE 1




**NOTES**  
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.  
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.



**TWO HOLE LUG**

NO SCALE 3



**GROUNDING RISER DIAGRAM**

NO SCALE 4

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		5/22/14	SKB	0

SITE NAME:  
**OLD SAYBROOK**

SITE CASCADE:  
**CT03XC102**

SITE ADDRESS:  
 430 MIDDLESEX TURNPIKE  
 OLD SAYBROOK, CT 06475

SHEET DESCRIPTION:  
**ELECTRICAL & GROUNDING DETAILS**

SHEET NUMBER:  
**E-2**

**INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR**

NO SCALE 2

Date: **May 8, 2014**

Patrick Byrum  
Crown Castle  
3530 Toringdon Way, Suite 300  
Charlotte, NC 28277  
(704) 405-6532



Tower Engineering Professionals  
3703 Junction Boulevard  
Raleigh, NC 27603  
(919) 661-6351  
[crown@tepgroup.net](mailto:crown@tepgroup.net)

**Subject: Structural Analysis Report**

<b>Carrier Designation:</b>	<b>Sprint PCS Co-Locate</b>	Scenario 2.5B
	<b>Carrier Site Number:</b>	CT03XC102
	<b>Carrier Site Name:</b>	N/A
<b>Crown Castle Designation:</b>	<b>Crown Castle BU Number:</b>	876336
	<b>Crown Castle Site Name:</b>	Old Saybrook
	<b>Crown Castle JDE Job Number:</b>	286432
	<b>Crown Castle Work Order Number:</b>	757938
	<b>Crown Castle Application Number:</b>	245403 Rev. 2
<b>Engineering Firm Designation:</b>	<b>TEP Project Number:</b>	54536.19007
<b>Site Data:</b>	<b>430 Middlesex Turnpike, Old Saybrook, Middlesex County, CT 06475</b> <b>Latitude 41° 18' 44.5", Longitude -72° 22' 48.7"</b> <b>175 Foot - Monopole Tower</b>	

Dear Patrick Byrum,

*Tower Engineering Professionals* is pleased to submit this "**Structural Analysis Report**" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 644644, in accordance with application 245403, revision 2.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC5: Existing + Proposed Equipment

**Sufficient Capacity**

Note: See Table I and Table II for the proposed and existing loading, respectively.

The analysis has been performed in accordance with the TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, ASCE 7-05 Minimum Design Loads for Buildings and Other Structures and the 2005 Connecticut State Building Code (with 2009 amendments) based upon a wind speed of 85 mph fastest mile.


All modifications and equipment proposed in this report shall be installed in accordance with the appurtenances listed in Tables 1 and 2 and the attached drawing for the determined available structural capacity to be effective.

We at *Tower Engineering Professionals* appreciate the opportunity of providing our continuing professional services to you and *Crown Castle*. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Matt Young, E.I. / WEM

Respectfully submitted by:

Graham M. Andres, P.E.



## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

### 3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 - Tower Component Stresses vs. Capacity

Table 7 - Dish Twist/Sway Results for 50 mph Service Wind Speed

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

This tower is a 175-ft monopole tower designed by Valmont Industries, Inc. in May of 1998. The tower was originally designed for a wind speed of 85 mph per EIA/TIA-222-F for the appurtenances listed in Table 3. TEP did not visit the site. All information provided to TEP was assumed to be accurate and complete.

## 2) ANALYSIS CRITERIA

The analysis has been performed in accordance with the TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and ASCE 7-05 Minimum Design Loads for Buildings and Other Structures using a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch escalating ice thickness, and 50 mph under service loads.

**Table 1 - Proposed Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
172.0	172.0	3	Alcatel Lucent	TD-RRH8x20-25	1	1-1/4	1
		3	RFS Celwave	APXVTM14-C-120 w/ Mount Pipe			

Notes:

- 1) See "Appendix B – Base Level Drawing" for assumed feed line configuration.

**Table 2 - Existing Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
172.0	178.0	1	RFS Celwave	ALG6	3 2	1-1/4 7/8	1
	172.0	3	RFS Celwave	APXVSP18-C-A20 w/ Mount Pipe			
		1	Tower Mounts	Platform Mount [LP 712-1]			
	165.0	1	Sinclair	SC381-HL			
170.0	170.0	3	Alcatel Lucent	PCS 1900MHz 4x45W-65MHz	-	-	1
		1	Tower Mounts	Side Arm Mount [SO 102-3]			
	166.0	3	Alcatel Lucent	800MHz 2X50W RRH w/ Filter w/ Mount Pipe			
85.0	85.0	1	Gabriel Electronics	HE2-105	1	EW90	1
		1	Tower Mounts	Pipe Mount [PM 601-1]			
72.0	72.0	1	Lucent	KS24019-L112A	1	1/2	1
		1	Tower Mounts	Side Arm Mount [SO 701-1]			

Notes:

- 1) Existing equipment

**Table 3 - Design Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
172.0	172.0	9	Decibel	DB980H	-	-
152.0	152.0	12	Allgon	ALP9212-N	-	-
132.0	132.0	12	Allgon	ALP9212-N	-	-
100.0	100.0	2	Generic	Omni	-	-
70.0	70.0	1	Generic	GPS	-	-

### 3) ANALYSIS PROCEDURE

**Table 4 - Documents Provided**

Document	Remarks	Reference	Source
Geotechnical Report	Clough, Harbour & Associates, LLP	1531893	CCISites
Tower Foundation Drawings	FDH Engineering, Inc.	1614591	CCISites
Tower Manufacturer Drawings	Valmont Industries, Inc.	2264466	CCISites

#### 3.1) Analysis Method

tnxTower (version 6.1.4.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

#### 3.2) Assumptions

- 1) The tower and foundation were built in accordance with the manufacturer’s specifications.
- 2) The tower and foundation have been maintained in accordance with the manufacturer’s specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2, and “Appendix B – Base Level Drawing”.
- 4) When applicable, transmission cables are considered as structural components for calculating wind loads as allowed by the standard.
- 5) All tower components are in sufficient condition to carry their full design capacity.
- 6) Serviceability with respect to antenna twist, tilt, roll, or lateral translation, is not checked and is left to the carrier or tower owner to ensure conformance. See Table 7.
- 7) All antenna mounts and mounting hardware are structurally sufficient to carry the full design capacity requirements of appurtenance wind area and weight as provided by the original manufacturer specifications. It is the carrier’s responsibility to ensure compliance to the structural limitations of the existing and/or proposed antenna mounts. TEP did not perform a site visit to verify the size, condition or capacity of the antenna mounts and did not analyze antennas supporting mounts as part of this structural analysis report.
- 8) The following material grades were assumed:
  - a) Foundation concrete  $f'c = 3000$  psi
  - b) Foundation reinforcement  $f_y = 60$  ksi

This analysis may be affected if any assumptions are not valid or have been made in error. Tower Engineering Professionals should be notified to determine the effect on the structural integrity of the tower.

#### 4) ANALYSIS RESULTS

**Table 5 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (lb)	SF·P <sub>allow</sub> (lb)	% Capacity	Pass / Fail
L1	175 - 125.667	Pole	TP27.49x17.63x0.188	1	-3981.430	763792.972	80.8	Pass
L2	125.667 - 84.75	Pole	TP35.3x26.248x0.281	2	-8292.800	1594347.914	76.0	Pass
L3	84.75 - 38.75	Pole	TP43.94x33.688x0.344	3	-16140.200	2411330.250	80.0	Pass
L4	38.75 - 0	Pole	TP51x42.002x0.405	4	-27337.301	3366624.660	79.2	Pass
							Summary	
						Pole (L1)	80.8	Pass
						<b>Rating =</b>	<b>80.8</b>	<b>Pass</b>

**Table 6 - Tower Component Stresses vs. Capacity**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	-	69.7	Pass
1	Base Plate	-	46.6	Pass
1	Base Foundation Soil Interaction	-	63.3	Pass
1	Base Foundation Structural	-	25.1	Pass

<b>Structure Rating (max from all components) =</b>	<b>80.8%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C - Additional Calculations" for calculations supporting the % capacity listed.

**Table 7 - Dish Twist/Sway Results for 50 mph Service Wind Speed**

Elevation (ft)	Dish Model	Beam Deflection		
		Deflection (in)	Tilt (deg)	Twist (deg)
85.0	Gabriel Electronics HE2-105	9.852	1.126	0.002

#### 4.1) Recommendations

- 1) If the load differs from that described in Tables 1 and 2 of this report, "Appendix B – Base Level Drawing" or the provisions of this analysis are found to be invalid, another structural analysis should be performed.
- 2) The tower and its foundation have sufficient capacity to carry the existing and proposed loads. No modifications are required at this time.

**APPENDIX A**  
**TNXTOWER OUTPUT**

175.0 ft


Section	1	2	3	4	
Length (ft)	49.33	45.25	51.25	45.00	
Number of Sides	12	12	12	12	
Thickness (in)	0.188	0.281	0.344	0.405	
Socket Length (ft)	4.33	5.25	6.25	42.002	
Top Dia (in)	17.630	26.248	33.688	51.000	
Bot Dia (in)	27.490	35.300	43.940	9204.9	
Grade	2273.5	4248.3	7431.3	9204.9	23156.0
Weight (lb)					

125.7 ft

84.8 ft

38.8 ft

0.0 ft



**DESIGNED APPURTENANCE LOADING**


TYPE	ELEVATION	TYPE	ELEVATION
1/2" x 5' L/Rod	175	800MHz 2X50W RRH W/FILTER w/ Mount Pipe	170
APXVSPP18-C-A20 w/ Mount Pipe	172	800MHz 2X50W RRH W/FILTER w/ Mount Pipe	170
APXVSPP18-C-A20 w/ Mount Pipe	172	PCS 1900MHz 4x45W-65MHz	170
APXVSPP18-C-A20 w/ Mount Pipe	172	PCS 1900MHz 4x45W-65MHz	170
ALG6	172	PCS 1900MHz 4x45W-65MHz	170
SC381-HL	172	Side Arm Mount [SO 102-3]	170
APXVTM14-C-120 w/ Mount Pipe	172	Detuner Brace 28" (PL3"x3/16")	125
APXVTM14-C-120 w/ Mount Pipe	172	Detuner Brace 28" (PL3"x3/16")	125
APXVTM14-C-120 w/ Mount Pipe	172	Detuner Brace 28" (PL3"x3/16")	125
TD-RRH8x20-25	172	Detuner Brace 28" (PL3"x3/16")	125
TD-RRH8x20-25	172	Pipe Mount [PM 601-1]	85
TD-RRH8x20-25	172	HE2-105	85
2.4" Dia. x 6' Mount Pipe	172	Side Arm Mount [SO 701-1]	72
2.4" Dia. x 6' Mount Pipe	172	KS24019-L112A	72
2.4" Dia. x 6' Mount Pipe	172		
Platform Mount [LP 712-1]	172		
800MHz 2X50W RRH W/FILTER w/ Mount Pipe	170		

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower is located in Middlesex County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 80.8%



**Tower Engineering Professionals**

3703 Junction Boulevard

Raleigh, NC 27603

Phone: (919) 661-6351

FAX: (919) 661-6350

Job: **Old Saybrook (BU 876336)**

Project: **TEP No. 54536.19007**

Client: Crown Castle

Drawn by: myoung

App'd:

Code: TIA/EIA-222-F

Date: 05/08/14

Scale: NTS

Path: C:\Users\myoung\Desktop\Tnx\876336-Old Saybrook\876336\_LCS.er

Dwg No. E-1

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b> Old Saybrook (BU 876336)	<b>Page</b> 1 of 10
	<b>Project</b> TEP No. 54536.19007	<b>Date</b> 11:27:26 05/08/14
	<b>Client</b> Crown Castle	<b>Designed by</b> myoung

## Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Middlesex County, Connecticut.

Basic wind speed of 85 mph.

Nominal ice thickness of 0.750 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 38 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

- |  |  |   |
|--|--|---|
| <ul style="list-style-type: none"> <li>Consider Moments - Legs</li> <li>Consider Moments - Horizontals</li> <li>Consider Moments - Diagonals</li> <li>Use Moment Magnification</li> <li>√ Use Code Stress Ratios</li> <li>√ Use Code Safety Factors - Guys</li> <li>√ Escalate Ice</li> <li>Always Use Max Kz</li> <li>Use Special Wind Profile</li> <li>Include Bolts In Member Capacity</li> <li>Leg Bolts Are At Top Of Section</li> <li>Secondary Horizontal Braces Leg</li> <li>Use Diamond Inner Bracing (4 Sided)</li> <li>Add IBC .6D+W Combination</li> </ul> | <ul style="list-style-type: none"> <li>Distribute Leg Loads As Uniform</li> <li>Assume Legs Pinned</li> <li>√ Assume Rigid Index Plate</li> <li>√ Use Clear Spans For Wind Area</li> <li>Use Clear Spans For KL/r</li> <li>Retension Guys To Initial Tension</li> <li>√ Bypass Mast Stability Checks</li> <li>√ Use Azimuth Dish Coefficients</li> <li>√ Project Wind Area of Appurt.</li> <li>Autocalc Torque Arm Areas</li> <li>SR Members Have Cut Ends</li> <li>√ Sort Capacity Reports By Component</li> <li>Triangulate Diamond Inner Bracing</li> <li>Use TIA-222-G Tension Splice Capacity</li> <li>Exemption</li> </ul> | <ul style="list-style-type: none"> <li>Treat Feedline Bundles As Cylinder</li> <li>Use ASCE 10 X-Brace Ly Rules</li> <li>Calculate Redundant Bracing Forces</li> <li>Ignore Redundant Members in FEA</li> <li>SR Leg Bolts Resist Compression</li> <li>All Leg Panels Have Same Allowable</li> <li>Offset Girt At Foundation</li> <li>√ Consider Feedline Torque</li> <li>Include Angle Block Shear Check</li> <li style="text-align: center;">Poles</li> <li>√ Include Shear-Torsion Interaction</li> <li>Always Use Sub-Critical Flow</li> <li>Use Top Mounted Sockets</li> </ul> |
|--|--|---|

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	175.00-125.67	49.33	4.333	12	17.630	27.490	0.188	0.752	A572-65 (65 ksi)
L2	125.67-84.75	45.25	5.250	12	26.248	35.300	0.281	1.124	A572-65 (65 ksi)
L3	84.75-38.75	51.25	6.250	12	33.688	43.940	0.344	1.376	A572-65 (65 ksi)
L4	38.75-0.00	45.00		12	42.002	51.000	0.405	1.620	A572-65 (65 ksi)



<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	3 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#		C <sub>AA</sub> ft <sup>2</sup> /ft	Weight plf
Step Pegs (5/8" SR) 7-in. w/30" step	C	No	CaAa (Out Of Face)	175.00 - 0.00	0.000	0	1	No Ice	0.01	0.244
								1/2" Ice	0.11	0.639
								1" Ice	0.21	1.644
								2" Ice	0.41	5.488
								4" Ice	0.81	20.505
Safety Line 3/8	C	No	CaAa (Out Of Face)	175.00 - 0.00	0.000	0	1	No Ice	0.04	0.220
								1/2" Ice	0.14	0.750
								1" Ice	0.24	1.280
								2" Ice	0.44	2.340
								4" Ice	0.84	4.460
*** AM Detuner	C	No	CaAa (Out Of Face)	125.00 - 0.00	12.000	0	2	No Ice	0.03	1.000
1/2" Ice								0.13	1.476	
1" Ice								0.23	2.564	
2" Ice								0.43	6.571	
4" Ice								0.83	21.916	
AM Detuner	C	No	CaAa (Out Of Face)	125.00 - 0.00	12.000	0	1	No Ice	0.00	1.000
1/2" Ice								0.00	1.476	
1" Ice								0.00	2.564	
2" Ice								0.00	6.571	
4" Ice								0.00	21.916	

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight lb
L1	175.00-125.67	A	0.000	0.000	0.000	0.000	206.647
		B	0.000	0.000	0.000	0.000	30.580
		C	0.000	0.000	0.000	2.570	22.891
L2	125.67-84.75	A	0.000	0.000	0.000	0.000	182.488
		B	0.000	0.000	0.000	0.000	27.085
		C	0.000	0.000	0.000	4.386	139.735
L3	84.75-38.75	A	0.000	0.000	0.000	0.000	210.148
		B	0.000	0.000	0.000	0.000	45.080
		C	0.000	0.000	0.000	4.973	159.344
L4	38.75-0.00	A	0.000	0.000	0.000	0.000	178.638
		B	0.000	0.000	0.000	0.000	37.975
		C	0.000	0.000	0.000	4.189	134.230

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight lb
L1	175.00-125.67	A	0.899	0.000	0.000	0.000	0.000	206.647
		B		0.000	0.000	0.000	0.000	30.580
		C		0.000	0.000	0.000	20.302	128.891
L2	125.67-84.75	A	0.861	0.000	0.000	0.000	0.000	182.488
		B		0.000	0.000	0.000	0.000	27.085
		C		0.000	0.000	0.000	33.560	389.854
L3	84.75-38.75	A	0.808	0.000	0.000	0.000	0.000	210.148
		B		0.000	0.000	0.000	0.000	45.080
		C		0.000	0.000	0.000	36.671	427.122
L4	38.75-0.00	A	0.750	0.000	0.000	0.000	0.000	178.638

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	4 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight lb
		B		0.000	0.000	0.000	0.000	37.975
		C		0.000	0.000	0.000	29.241	340.011

### Feed Line Center of Pressure

Section	Elevation ft	CP <sub>x</sub> in	CP <sub>z</sub> in	CP <sub>x</sub> Ice in	CP <sub>z</sub> Ice in
L1	175.00-125.67	-0.066	0.038	-0.412	0.238
L2	125.67-84.75	-0.134	0.077	-0.777	0.449
L3	84.75-38.75	-0.136	0.078	-0.805	0.465
L4	38.75-0.00	-0.137	0.079	-0.799	0.461

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight lb	
1/2" x 5' L Rod	C	From Leg	0.00	0.000	175.00	No Ice	0.25	0.25	3.340
			0.000			1/2" Ice	0.76	0.76	6.452
			2.500			1" Ice	1.29	1.29	12.821
						2" Ice	1.92	1.92	35.945
						4" Ice	3.30	3.30	128.007
* APXVSPP18-C-A20 w/ Mount Pipe	A	From Centroid-Le g	4.00	0.000	172.00	No Ice	8.50	6.95	82.550
			0.000			1/2" Ice	9.15	8.13	150.561
			0.000			1" Ice	9.77	9.02	226.532
						2" Ice	11.03	10.84	405.983
						4" Ice	13.68	14.85	908.948
APXVSPP18-C-A20 w/ Mount Pipe	B	From Centroid-Le g	4.00	0.000	172.00	No Ice	8.50	6.95	82.550
			0.000			1/2" Ice	9.15	8.13	150.561
			0.000			1" Ice	9.77	9.02	226.532
						2" Ice	11.03	10.84	405.983
						4" Ice	13.68	14.85	908.948
APXVSPP18-C-A20 w/ Mount Pipe	C	From Centroid-Le g	4.00	0.000	172.00	No Ice	8.50	6.95	82.550
			0.000			1/2" Ice	9.15	8.13	150.561
			0.000			1" Ice	9.77	9.02	226.532
						2" Ice	11.03	10.84	405.983
						4" Ice	13.68	14.85	908.948
ALG6	C	From Centroid-Le g	4.00	0.000	172.00	No Ice	4.27	4.27	36.000
			0.000			1/2" Ice	4.76	4.76	72.299
			6.000			1" Ice	5.26	5.26	114.312
						2" Ice	6.30	6.30	216.092
						4" Ice	8.48	8.48	494.941
SC381-HL	C	From Centroid-Le g	4.00	0.000	172.00	No Ice	5.56	5.56	47.000
			0.000			1/2" Ice	6.84	6.84	85.516
			-7.000			1" Ice	7.86	7.86	132.193
						2" Ice	9.37	9.37	250.637

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	5 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Vert						ft
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb	
APXVTM14-C-120 w/ Mount Pipe	A	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	12.51	12.51	592.167
			0.000	0.000			No Ice	7.13	4.96	76.775
			0.000	0.000			1/2" Ice	7.66	5.75	131.384
			0.000	0.000			1" Ice	8.18	6.47	192.678
			0.000	0.000			2" Ice	9.26	8.01	338.476
APXVTM14-C-120 w/ Mount Pipe	B	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	11.53	11.41	752.452
			0.000	0.000			No Ice	7.13	4.96	76.775
			0.000	0.000			1/2" Ice	7.66	5.75	131.384
			0.000	0.000			1" Ice	8.18	6.47	192.678
			0.000	0.000			2" Ice	9.26	8.01	338.476
APXVTM14-C-120 w/ Mount Pipe	C	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	11.53	11.41	752.452
			0.000	0.000			No Ice	7.13	4.96	76.775
			0.000	0.000			1/2" Ice	7.66	5.75	131.384
			0.000	0.000			1" Ice	8.18	6.47	192.678
			0.000	0.000			2" Ice	9.26	8.01	338.476
TD-RRH8x20-25	A	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	11.53	11.41	752.452
			0.000	0.000			No Ice	4.72	1.70	70.000
			0.000	0.000			1/2" Ice	5.01	1.92	97.151
			0.000	0.000			1" Ice	5.32	2.15	127.829
			0.000	0.000			2" Ice	5.95	2.62	200.542
TD-RRH8x20-25	B	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	7.31	3.68	396.842
			0.000	0.000			No Ice	4.72	1.70	70.000
			0.000	0.000			1/2" Ice	5.01	1.92	97.151
			0.000	0.000			1" Ice	5.32	2.15	127.829
			0.000	0.000			2" Ice	5.95	2.62	200.542
TD-RRH8x20-25	C	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	7.31	3.68	396.842
			0.000	0.000			No Ice	4.72	1.70	70.000
			0.000	0.000			1/2" Ice	5.01	1.92	97.151
			0.000	0.000			1" Ice	5.32	2.15	127.829
			0.000	0.000			2" Ice	5.95	2.62	200.542
2.4" Dia. x 6' Mount Pipe	A	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	7.31	3.68	396.842
			0.000	0.000			No Ice	1.43	1.43	21.900
			0.000	0.000			1/2" Ice	1.93	1.93	37.813
			0.000	0.000			1" Ice	2.32	2.32	55.556
			0.000	0.000			2" Ice	3.15	3.15	99.637
2.4" Dia. x 6' Mount Pipe	B	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	5.06	5.06	251.605
			0.000	0.000			No Ice	1.43	1.43	21.900
			0.000	0.000			1/2" Ice	1.93	1.93	37.813
			0.000	0.000			1" Ice	2.32	2.32	55.556
			0.000	0.000			2" Ice	3.15	3.15	99.637
2.4" Dia. x 6' Mount Pipe	C	From Centroid-Le g	4.00	0.000	0.000	172.00	4" Ice	5.06	5.06	251.605
			0.000	0.000			No Ice	1.43	1.43	21.900
			0.000	0.000			1/2" Ice	1.93	1.93	37.813
			0.000	0.000			1" Ice	2.32	2.32	55.556
			0.000	0.000			2" Ice	3.15	3.15	99.637
Platform Mount [LP 712-1]	C	None			0.000	172.00	4" Ice	5.06	5.06	251.605
							No Ice	24.53	24.53	1335.000
							1/2" Ice	29.94	29.94	1645.590
							1" Ice	35.35	35.35	1956.180
							2" Ice	46.17	46.17	2577.360
*** 800MHz 2X50W RRH W/FILTER w/ Mount Pipe	A	From Leg	1.00	0.000	0.000	170.00	4" Ice	67.81	67.81	3819.720
			0.000	0.000			No Ice	2.59	2.73	73.429
			-4.000	0.000			1/2" Ice	2.86	3.10	102.534
							1" Ice	3.15	3.49	135.687
							2" Ice	3.78	4.37	216.173
		4" Ice	5.21	6.40	452.718					

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	6 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb	
800MHz 2X50W RRH W/FILTER w/ Mount Pipe	B	From Leg	1.00	0.000	0.000	170.00	No Ice	2.59	2.73	73.429
			0.000				1/2" Ice	2.86	3.10	102.534
			-4.000				1" Ice	3.15	3.49	135.687
							2" Ice	3.78	4.37	216.173
							4" Ice	5.21	6.40	452.718
800MHz 2X50W RRH W/FILTER w/ Mount Pipe	C	From Leg	1.00	0.000	0.000	170.00	No Ice	2.59	2.73	73.429
			0.000				1/2" Ice	2.86	3.10	102.534
			-4.000				1" Ice	3.15	3.49	135.687
							2" Ice	3.78	4.37	216.173
							4" Ice	5.21	6.40	452.718
PCS 1900MHz 4x45W-65MHz	A	From Leg	1.00	0.000	0.000	170.00	No Ice	2.71	2.61	60.000
			0.000				1/2" Ice	2.95	2.85	83.134
			0.000				1" Ice	3.20	3.09	109.502
							2" Ice	3.72	3.61	172.719
							4" Ice	4.86	4.74	346.520
PCS 1900MHz 4x45W-65MHz	B	From Leg	1.00	0.000	0.000	170.00	No Ice	2.71	2.61	60.000
			0.000				1/2" Ice	2.95	2.85	83.134
			0.000				1" Ice	3.20	3.09	109.502
							2" Ice	3.72	3.61	172.719
							4" Ice	4.86	4.74	346.520
PCS 1900MHz 4x45W-65MHz	C	From Leg	1.00	0.000	0.000	170.00	No Ice	2.71	2.61	60.000
			0.000				1/2" Ice	2.95	2.85	83.134
			0.000				1" Ice	3.20	3.09	109.502
							2" Ice	3.72	3.61	172.719
							4" Ice	4.86	4.74	346.520
Side Arm Mount [SO 102-3]	C	None			0.000	170.00	No Ice	3.00	3.00	81.000
							1/2" Ice	3.48	3.48	111.000
							1" Ice	3.96	3.96	141.000
							2" Ice	4.92	4.92	201.000
							4" Ice	6.84	6.84	321.000
*** Pipe Mount [PM 601-1]	C	From Face	0.50	0.000	0.000	85.00	No Ice	3.00	0.90	21.667
0.000				1/2" Ice			3.74	1.12	26.370	
0.000				1" Ice			4.48	1.34	31.073	
				2" Ice			5.96	1.78	40.479	
				4" Ice			8.92	2.66	59.291	
*** KS24019-L112A	C	From Leg	3.00	0.000	0.000	72.00	No Ice	0.09	0.09	5.000
0.000				1/2" Ice			0.15	0.15	6.247	
0.000				1" Ice			0.22	0.22	8.258	
				2" Ice			0.40	0.40	15.181	
				4" Ice			0.89	0.89	44.910	
Side Arm Mount [SO 701-1]	C	From Leg	1.50	0.000	0.000	72.00	No Ice	0.85	1.67	65.000
			0.000				1/2" Ice	1.14	2.34	79.000
			0.000				1" Ice	1.43	3.01	93.000
							2" Ice	2.01	4.35	121.000
							4" Ice	3.17	7.03	177.000
**** Detuner Brace 28" (PL3"x3/16")	A	From Leg	1.00	0.000	0.000	125.00	No Ice	0.01	0.82	4.500
0.000				1/2" Ice			0.03	1.02	8.454	
0.000				1" Ice			0.06	1.24	14.623	
				2" Ice			0.16	1.69	34.388	
				4" Ice			0.45	2.70	109.063	
Detuner Brace 28" (PL3"x3/16")	B	From Leg	1.00	0.000	0.000	125.00	No Ice	0.01	0.82	4.500
			0.000				1/2" Ice	0.03	1.02	8.454
			0.000				1" Ice	0.06	1.24	14.623
							2" Ice	0.16	1.69	34.388
							4" Ice	0.45	2.70	109.063

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	7 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	CAAA		Weight	
			Horz Lateral	Vert			Front	Side		
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	lb	
Detuner Brace 28" (PL3"x3/16")	C	From Leg	1.00	0.000	0.000	125.00	4" Ice	0.45	2.70	109.063
			0.000	0.000			No Ice	0.01	0.82	4.500
			0.000	0.000			1/2" Ice	0.03	1.02	8.454
							1" Ice	0.06	1.24	14.623
							2" Ice	0.16	1.69	34.388
		4" Ice	0.45	2.70	109.063					

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz Lateral	Vert							
			ft	ft	°	°	ft	ft	ft <sup>2</sup>	lb		
HE2-105	C	Paraboloid w/Shroud (HP)	From Face	1.00	0.000	-9.000		85.00	2.00	No Ice	3.10	60.000
				0.000	0.000					1/2" Ice	3.41	70.000
				0.000	0.000					1" Ice	3.71	90.000
										2" Ice	4.33	120.000
										4" Ice	5.56	190.000

### Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	8 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

<i>Comb. No.</i>	<i>Description</i>
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

### Maximum Tower Deflections - Service Wind

<i>Section No.</i>	<i>Elevation ft</i>	<i>Horz. Deflection in</i>	<i>Gov. Load Comb.</i>	<i>Tilt °</i>	<i>Twist °</i>
L1	175 - 125.667	45.705	33	2.505	0.019
L2	130 - 84.75	24.188	33	1.879	0.006
L3	90 - 38.75	11.100	33	1.207	0.002
L4	45 - 0	2.697	33	0.546	0.001

### Critical Deflections and Radius of Curvature - Service Wind

<i>Elevation ft</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
175.00	1/2" x 5' L Rod	33	45.705	2.505	0.019	23322
172.00	APXVSP18-C-A20 w/ Mount Pipe	33	44.166	2.466	0.018	23322
170.00	800MHz 2X50W RRH W/FILTER w/ Mount Pipe	33	43.142	2.440	0.017	23322
125.00	Detuner Brace 28" (PL3"x3/16")	33	22.202	1.799	0.005	2712
85.00	HE2-105	33	9.852	1.126	0.002	3996
72.00	KS24019-L112A	33	6.961	0.924	0.002	3796

### Maximum Tower Deflections - Design Wind

<i>Section No.</i>	<i>Elevation ft</i>	<i>Horz. Deflection in</i>	<i>Gov. Load Comb.</i>	<i>Tilt °</i>	<i>Twist °</i>
L1	175 - 125.667	131.387	8	7.195	0.054
L2	130 - 84.75	69.624	8	5.408	0.016
L3	90 - 38.75	31.980	2	3.476	0.007
L4	45 - 0	7.777	2	1.576	0.002

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	9 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

### Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
175.00	1/2" x 5' L Rod	8	131.387	7.195	0.054	8341
172.00	APXVSP18-C-A20 w/ Mount Pipe	8	126.973	7.084	0.051	8341
170.00	800MHz 2X50W RRH W/FILTER w/ Mount Pipe	8	124.034	7.010	0.049	8341
125.00	Detuner Brace 28" (PL3"x3/16")	8	63.917	5.178	0.014	961
85.00	HE2-105	2	28.386	3.242	0.007	1396
72.00	KS24019-L112A	2	20.063	2.663	0.005	1324

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>a</sub> ft	Kl/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P lb	Allow. P <sub>a</sub> lb	Ratio P/P <sub>a</sub>
L1	175 - 125.667 (1)	TP27.49x17.63x0.188	49.33	0.00	0.0	35.804	16.003	-3981.430	572988.000	0.007
L2	125.667 - 84.75 (2)	TP35.3x26.248x0.281	45.25	0.00	0.0	38.914	30.736	-8292.800	1196060.000	0.007
L3	84.75 - 38.75 (3)	TP43.94x33.688x0.344	51.25	0.00	0.0	38.566	46.905	-16140.200	1808950.000	0.009
L4	38.75 - 0 (4)	TP51x42.002x0.405	45.00	0.00	0.0	38.278	65.981	-27337.301	2525600.000	0.011

### Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M <sub>x</sub> lb-ft	Actual f <sub>bx</sub> ksi	Allow. F <sub>bx</sub> ksi	Ratio f <sub>bx</sub> /F <sub>bx</sub>	Actual M <sub>y</sub> lb-ft	Actual f <sub>by</sub> ksi	Allow. F <sub>by</sub> ksi	Ratio f <sub>by</sub> /F <sub>by</sub>
L1	175 - 125.667 (1)	TP27.49x17.63x0.188	330355.833	38.299	35.804	1.070	0.000	0.000	35.804	0.000
L2	125.667 - 84.75 (2)	TP35.3x26.248x0.281	831799.167	39.120	38.914	1.005	0.000	0.000	38.914	0.000
L3	84.75 - 38.75 (3)	TP43.94x33.688x0.344	1649091.667	40.761	38.566	1.057	0.000	0.000	38.566	0.000
L4	38.75 - 0 (4)	TP51x42.002x0.405	2719333.333	39.987	38.278	1.045	0.000	0.000	38.278	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V lb	Actual f <sub>v</sub> ksi	Allow. F <sub>v</sub> ksi	Ratio f <sub>v</sub> /F <sub>v</sub>	Actual T lb-ft	Actual f <sub>vt</sub> ksi	Allow. F <sub>vt</sub> ksi	Ratio f <sub>vt</sub> /F <sub>vt</sub>
-------------	--------------	------	-------------	---------------------------	---------------------------	--------------------------------------	----------------	----------------------------	----------------------------	--

<b>tnxTower</b>  <b>Tower Engineering Professionals</b> 3703 Junction Boulevard Raleigh, NC 27603 Phone: (919) 661-6351 FAX: (919) 661-6350	<b>Job</b>	Old Saybrook (BU 876336)	<b>Page</b>	10 of 10
	<b>Project</b>	TEP No. 54536.19007	<b>Date</b>	11:27:26 05/08/14
	<b>Client</b>	Crown Castle	<b>Designed by</b>	myoung

Section No.	Elevation ft	Size	Actual V lb	Actual $f_v$ ksi	Allow. $F_v$ ksi	Ratio $\frac{f_v}{F_v}$	Actual T lb-ft	Actual $f_{vt}$ ksi	Allow. $F_{vt}$ ksi	Ratio $\frac{f_{vt}}{F_{vt}}$
L1	175 - 125.667 (1)	TP27.49x17.63x0.188	10096.0 00	0.631	26.000	0.049	0.002	0.000	26.000	0.000
L2	125.667 - 84.75 (2)	TP35.3x26.248x0.281	15008.2 00	0.488	26.000	0.038	0.537	0.000	26.000	0.000
L3	84.75 - 38.75 (3)	TP43.94x33.688x0.344	21043.8 01	0.449	26.000	0.035	2011.38 3	0.023	26.000	0.001
L4	38.75 - 0 (4)	TP51x42.002x0.405	26492.1 99	0.402	26.000	0.031	2101.10 8	0.015	26.000	0.001

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio P $P_a$	Ratio $f_{bx}$ $F_{bx}$	Ratio $f_{by}$ $F_{by}$	Ratio $f_v$ $F_v$	Ratio $f_{vt}$ $F_{vt}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	175 - 125.667 (1)	0.007	1.070	0.000	0.049	0.000	1.077	1.333	H1-3+VT
L2	125.667 - 84.75 (2)	0.007	1.005	0.000	0.038	0.000	1.013	1.333	H1-3+VT
L3	84.75 - 38.75 (3)	0.009	1.057	0.000	0.035	0.001	1.066	1.333	H1-3+VT
L4	38.75 - 0 (4)	0.011	1.045	0.000	0.031	0.001	1.056	1.333	H1-3+VT


### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	SF* $P_{allow}$ lb	% Capacity	Pass Fail	
L1	175 - 125.667	Pole	TP27.49x17.63x0.188	1	-3981.430	763792.972	80.8	Pass	
L2	125.667 - 84.75	Pole	TP35.3x26.248x0.281	2	-8292.800	1594347.91 4	76.0	Pass	
L3	84.75 - 38.75	Pole	TP43.94x33.688x0.344	3	-16140.200	2411330.25 0	80.0	Pass	
L4	38.75 - 0	Pole	TP51x42.002x0.405	4	-27337.301	3366624.66 0	79.2	Pass	
							Summary		
							Pole (L1)	80.8	Pass
							<b>RATING =</b>	<b>80.8</b>	<b>Pass</b>

**APPENDIX B**  
**BASE LEVEL DRAWING**



(PROPOSED)  
(1) 1-1/4" TO 172 FT LEVEL  
(INSTALLED)  
(1) 1/2" TO 72 FT LEVEL  
(3) 1 1/4" TO 172 FT LEVEL



(INSTALLED)  
(1) EW90 TO 85 FT LEVEL  
(2) 7/8" TO 172 FT LEVEL

**APPENDIX C**  
**ADDITIONAL CALCULATIONS**

# Stiffened or Unstiffened, Ungrouted, Circular Base Plate - Any Rod Material

## TIA Rev F

### Site Data

BU#: 876336
Site Name: Old Saybrook
App #: 245403 Rev. 2
Pole Manufacturer: <b>Other</b>

Reactions	
Moment:	2719.33 ft-kips
Axial:	27.354 kips
Shear:	26.475 kips

### Anchor Rod Data

Qty:	16	
Diam:	2.25	in
Rod Material:	A615-J	
Strength (Fu):	100	ksi
Yield (Fy):	75	ksi
Bolt Circle:	59.3	in

If No stiffeners, Criteria: **AISC ASD** <-Only Applicable to Unstiffened Cases

### Anchor Rod Results

Maximum Rod Tension: 135.9 Kips  
 Allowable Tension: 195.0 Kips  
 Anchor Rod Stress Ratio: 69.7% **Pass**

<b>Rigid</b>
Service ASD
Fty*ASIF

### Plate Data

Diam:	65.3	in
Thick:	2.75	in
Grade:	60	ksi
Single-Rod B-eff:	10.25	in

### Base Plate Results

Base Plate Stress: 27.9 ksi  
 Allowable Plate Stress: 60.0 ksi  
 Base Plate Stress Ratio: 46.6% **Pass**

### Flexural Check

<b>Rigid</b>
Service ASD
0.75*Fy*ASIF
Y.L. Length:
30.26

### Stiffener Data (Welding at both sides)

Config:	0	*
Weld Type:		
Groove Depth:		in **
Groove Angle:		degrees
Fillet H. Weld:		<-- Disregard
Fillet V. Weld:		in
Width:		in
Height:		in
Thick:		in
Notch:		in
Grade:		ksi
Weld str.:		ksi

n/a

### Stiffener Results

Horizontal Weld : n/a  
 Vertical Weld: n/a  
 Plate Flex+Shear, fb/Fb+(fv/Fv)^2: n/a  
 Plate Tension+Shear, ft/Ft+(fv/Fv)^2: n/a  
 Plate Comp. (AISC Bracket): n/a

### Pole Results


Pole Punching Shear Check: n/a

### Pole Data

Diam:	51	in
Thick:	0.405	in
Grade:	65	ksi
# of Sides:	12	"0" IF Round
Fu	80	ksi
Reinf. Fillet Weld	0	"0" if None

### Stress Increase Factor

ASIF:	1.333
-------	-------



\* 0 = none, 1 = every bolt, 2 = every 2 bolts, 3 = 2 per bolt

\*\* Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

JOB: Old Saybrook (BU 876336)  
 SHEET NUMBER: 1 OF 2  
 CALCULATED BY: MGY DATE 5/8/2014  
 CHECKED BY: WEM DATE 5/8/2014

**Pad and Pier Foundation for Monopole - TIA-222-F**

<b>Q<sub>a</sub></b> , ALLOWABLE SOIL PRESS. (ksf)	40
NET or GROSS	NET
SOIL DENSITY (pcf)	120

<b>F'c</b> (ksi)	3
<b>F'y</b> (ksi)	60

**Base Reactions LC1: Maximum Wind**

<b>M</b> , MOMENT (k-ft)	2719.3
<b>P<sub>t</sub></b> , TOTAL DOWNLOAD (k)	27.4
<b>H</b> , HORIZONTAL SHEAR (k)	26.5

**Base Reaction LC 2: Ice Wind + Ice**

<b>M</b> (k-ft)	690.9
<b>P<sub>t</sub></b> (k)	37.3
<b>H</b> (k)	6.5

Try:	<b>L</b> (ft.)	<b>B</b> (ft.)	<b>t</b> (ft.)	<b>Soil depth to TOP of mat</b> (ft.)	<b>Soil depth to BOT. of mat</b> (ft.)	<b>Pier dia./width</b> (ft.)	<b>Pier Height, h</b> (ft.)	<b>Pier Shape</b>
	25	25	5.5	0	5	4.25	0.00	Round

<b>W<sub>m</sub></b> , Weight of Mat (k) =	515.6	<b>Concrete Vol.</b> (cu ft)	127.31
<b>W<sub>p</sub></b> , Weight of Pier (k) =	0.0		
<b>W<sub>s</sub></b> , WEIGHT OF SOIL (k) =	0.0		

**CHECK DESIGN CRITERIA**

**CHECK STABILITY:**

	LC1	LC2	<b>Capacity:</b>	63.3%
<b>Mst</b> = $P * (L/2) + (Vf+s * L/2) =$	6787.2 k-ft	6911.3 k-ft		
<b>Mot</b> = $M+H*(t+h) =$	2864.9 k-ft	727 k-ft		
<b>SF</b> = $Mot/Mst =$	2.37 > 1.5	9.51 > 1.5		

**CHECK BEARING PRESSURE**

	LC1	LC2	<b>Capacity:</b>	5.0%
<b>P</b> = $P_t + W_i + W_s =$	543.0 k	552.9 k		
<b>e</b> = $M / P =$	5.28 ft	1.31 ft		
<b>L/6</b> =	4.17 ft	4.17 ft		
<b>Width of Wedge, L'</b> =	21.67 ft	25.00 ft		
<b>0 Deg Wind: Q<sub>max</sub></b> =	1.40 ksf	0.56 ksf		
<b>45 Deg Wind: Q<sub>max</sub></b> =	1.99 ksf	0.68 ksf		

JOB: Old Saybrook (BU 876336)  
 SHEET NUMBER: 2 OF 2  
 CALCULATED BY: MGY DATE 5/8/2014  
 CHECKED BY: WEM DATE 5/8/2014

**CHECK ONE WAY SHEAR**

$V_u = 300.6 \text{ k}$   
 $V_c = 1528.1 \text{ k}$

**Capacity:** 19.67%

**CHECK TWO WAY SHEAR: PUNCHING + UNBALANCED MOMENT**

$V_u = 13.4 \text{ psi}$   
 $\phi V_c = 164.3 \text{ psi}$

**Capacity:** 8.16%

**CALCULATE REINFORCING REQUIRED**

$F'_c = 3.0 \text{ ksi}$        $F'_y = 60.0 \text{ ksi}$

Temp & Shrinkage reinforcing,  $A_{s, \text{temp}} = 0.40 \text{ in}^2/\text{ft}$  (ACI 318 Sec. 10.5.4)

**BOTTOM REINFORCING**

Bar Size = 8  
 Bar Spacing, c-c: 12.0  
 d = 61.5 in.

$M_u = 467.1 \text{ in-k/ft}$

$\phi Mn = 0.9 \cdot A_s \cdot F_y \cdot d (1 - 0.59 \cdot A_s \cdot F_y / (b \cdot d \cdot F'_c))$

Solution:  $A_{s, \text{req}} = 0.14 \text{ in}^2/\text{ft}$

Check,  $A_s = 0.79 \text{ in}^2/\text{ft}$

**Capacity:** 17.84%

**TOP REINFORCING**

Bar Size = 8  
 Bar Spacing, c-c: 12.0  
 d = 61.5 in.

$M_u = 656.9 \text{ in-k/ft}$

$\phi Mn = 0.9 \cdot A_s \cdot F_y \cdot d (1 - 0.59 \cdot A_s \cdot F_y / (b \cdot d \cdot F'_c))$

Solution:  $A_{s, \text{req}} = 0.20 \text{ in}^2/\text{ft}$

Bar Spacing, c-c:

Check,  $A_s = 0.79 \text{ in}^2/\text{ft}$

**Top Reinforcing O.K.**

**Capacity:** 25.12%

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC102

Old Saybrook

430 Middlesex Turnpike  
Old Saybrook, CT 06475

**June 12, 2014**

**EBI Project Number: 62143376**

June 12, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT03XC102 - Old Saybrook**

**Site Total: 2.81% - MPE% in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 430 Middlesex Turnpike, Old Saybrook, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 430 Middlesex Turnpike, Old Saybrook, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 3 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **172 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC102 - Old Saybrook
Site Address	430 Middlesex Turnpike , Old Saybrook, CT, 06475
Site Type	Monopole

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	172	166	1/2 "	0.5	3	104.27	0.14%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	172	166	1/2 "	0.5	3	19.54	0.04%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	172	166	1/2 "	0.5	3	69.51	0.16%
Sector total Power Density Value:															0.34%	

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	172	166	1/2 "	0.5	3	104.27	0.14%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	172	166	1/2 "	0.5	3	19.54	0.04%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	172	166	1/2 "	0.5	3	69.51	0.16%
Sector total Power Density Value:															0.34%	

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	172	166	1/2 "	0.5	3	104.27	0.14%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	172	166	1/2 "	0.5	3	19.54	0.04%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	172	166	1/2 "	0.5	3	69.51	0.16%
Sector total Power Density Value:															0.34%	

Site Composite MPE %	
Carrier	MPE %
Sprint	1.02%
Town	1.79%
<b>Total Site MPE %</b>	<b>2.81%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **1.02% (0.34% from sector 1, 0.34% from sector 2 and 0.34% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **2.81%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803