

•T•••Mobile•

Please Reply To:
Sam Simons
35 Griffin Road South
Bloomfield, CT 06002
203-482-5156
Sam.Simons@T-
Mobile.com

January 25, 2016

Attorney Melanie Bachman
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06501

EM-T-MOBILE-132-150116
T-Mobile Site ID CT11279D
300 Governors Highway, South Windsor CT
Notice of Compliance with Conditions and Construction Completion

Dear Attorney Bachman:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- Prior to any proposed tower load changes, T-Mobile shall modify the tower in accordance with the structural analysis report, including drawings, prepared by Paul J. Ford and Company dated December 9, 2014 and stamped by Justin Kline;
- Within 45 days following completion of the equipment installation, T-Mobile shall provide documentation certified by a professional engineer that its installation complied with the recommendations included in the Structural Analysis Report;
- Any deviation from the proposed modification as specified in this notice and supporting materials with the Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Within 45 days after completion of construction, the Council shall be notified in writing that construction has been completed
- Any nonfunctioning antenna and associated antenna mounting equipment on this facility owned and operated by T-Mobile shall be removed within 60 days of the date the antenna ceased to function;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration.

The attached PE Closeout Letter dated January 20, 2016 provides evidence of compliance with the conditions outlined by the Council.

In addition, T-Mobile hereby notifies the Council that construction of the acknowledged modifications were complete as of August 20, 2014.

Sincerely,

Sam Simons

Samuel Simons, T-Mobile

CC: Mark Richard, T-Mobile

Date: **January 20, 2016**

Sam Simons
Engineering Development - Connecticut
T-Mobile
35 Griffin Road South
Bloomfield, CT 06002

Paul J Ford and Company
250 E. Broad St., Suite 600
Columbus, OH 43215
614-221-6679

Subject: Post Construction Review

Carrier Designation:

T-Mobile Co-Locate

Carrier Site Number:

CT11279D

Siting Council ID:

EM-T-Mobile-132-150116

Engineering Firm Designation:

Paul J Ford and Company Project Number: 79916-0003.001.7100

Site Data:

**300 Governors Highway, South Windsor, Hartford County, CT
169 Foot – Monopole Tower**

Dear Sam Simons,

Paul J. Ford and Company has completed a post-construction review per the requirements of the Connecticut Siting Council. The purpose of the letter is to verify that the proposed antennas listed in Table 1 (next page) have been installed. The review is consistent with the guidelines as stated in the 2005 Connecticut Building Code and the TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 80 mph with no ice, 37.6 mph with 1 inch ice thickness and 50 mph under service loads.

Based on a comparison of the verified proposed loading (shown Table 1 & 2) versus the previous analysis loads (including wind speeds) from Paul J. Ford and Company [project number 37513-1535.003.7700, dated December 9, 2014] we have determined that loading is similar and should not change the analysis concluded in our 2014 report.

Based upon a review of the photos provided, it appears that the antennas and equipment listed in Table 1 have been installed.

We at *Paul J. Ford and Company* appreciate the opportunity of providing our continuing professional services to you. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:

Kurt J. Swarts, P.E.
Project Manager

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
165.0	165.0	3	commscope	LNx-6515DS-VTM w/ Mount Pipe	2	1-5/8	-
		3	ericsson	RRUS 11 B12			

Notes:

- 1) Verified antenna/coax installation heights and quantities

Table 2 - Existing Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
165.0	165.0	3	ericsson	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	11	1-5/8	1
		3	ericsson	ERICSSON AIR 21 B4A B2P w/ Mount Pipe			
		3	ericsson	KRY 112 144/1			
		1	tower mounts	Platform Mount [LP 712-1]			
156.0	156.0	3	communication components inc.	DTMABP7819VG12A	12	1-5/8	1
		6	css	DUO1417-8686 w/ Mount Pipe			
		3	ericsson	RRUS 11			
		3	powerwave technologies	7770.00 w/ Mount Pipe			
		1	tower mounts	Platform Mount [LP 712-1]			
148.0	148.0	3	andrew	932LG65VTE-B w/ Mount Pipe	6	1-5/8	1
		1	tower mounts	Side Arm Mount [SO 102-3]			
138.0	138.0	3	rfs celwave	APXV18-206517-A	6	1-5/8	1
		1	tower mounts	Pipe Mount [PM 601-3]			
128.0	128.0	3	argus technologies	LLPX310R w/ Mount Pipe	3	1/4	1
		3	dragonwave	A-ANT-18G-2-C			
		3	dragonwave	HORIZON DUO			
		3	samsung	WIMAX DAP HEAD			
		1	tower mounts	Side Arm Mount [SO 701-3]			
111.0	111.0	3	alcatel lucent	RRH2X60-AWS	2	1-5/8	2
		3	alcatel lucent	RRH2X60-PCS			
		6	andrew	HBXX-6517DS-A2M w/ Mount Pipe			
		6	andrew	LNx-6514DS-A1M w/ Mount Pipe			
		2	rfs celwave	DB-B1-6C-12AB-0Z			
		1	tower mounts	Platform Mount [LP 303-1]			

Notes:

- 1) Existing Equipment
 2) Reserved Equipment