## STATE OF CONNECTICUT



### CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051 Phone: (860) 827-2935 Fax: (860) 827-2950 E-Mail: siting.council@ct.gov www.ct.gov/csc

#### VIA ELECTRONIC MAIL

July 20, 2021

Lucia Chiocchio, Esq. Christopher B. Fisher, Esq. Cuddy & Feder, LLP 445 Hamilton Avenue, 14th Floor White Plains, NY 10601

RE:

**DOCKET NO. 488** - Homeland Towers, LLC Certificate of Environmental Compatibility and Public Need for the construction, maintenance, and operation of a telecommunications facility located at 93 Richards Road, Kent, Connecticut.

Dear Attorneys Chiocchio and Fisher:

At a public meeting of the Connecticut Siting Council (Council) held on July 15, 2021, the Council considered and approved the Development and Management (D&M) Plan submitted for this project on June 15, 2021 with the following conditions;

- 1. Submit an Erosion and Sedimentation Control Plan prior to commencement of construction;
- 2. Provide construction hours/days of week; and
- 3. Provide detail regarding the Town's equipment and anticipated date of installation.

This approval applies only to the D&M Plan submitted on June 15, 2021. Requests for any changes to the D&M Plan shall be approved by Council staff in accordance with Regulations of Connecticut State Agencies Section (RCSA) §16-50j-77(b).

The Certificate Holder is responsible for compliance with the reporting requirements under RCSA 16-50j-77, including:

- 1. Notification of commencement of construction;
- 2. Quarterly construction progress reports;
- 3. Notification of completion of construction and commencement of operation; and
- 4. Final report.

The Council acknowledges the contact information for the personnel of the contractor assigned to the project is included in the D&M Plan.

Please be advised that deviations from the approved D&M Plan and non-compliance with the D&M Plan reporting requirements are enforceable under Connecticut General Statutes § 16-50u.

Enclosed is a copy of the staff report for this D&M Plan, dated July 15, 2021.

Thank you for your attention and cooperation.



Sincerely,

# s/Melanie A. Bachman

Melanie A. Bachman Executive Director

Enclosure: Staff Report, dated July 15, 2021





### CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051 Phone: (860) 827-2935 Fax: (860) 827-2950 E-Mail: siting.council@ct.gov www.ct.gov/csc

> Docket No. 488 Homeland Towers, LLC 93 Richards Road, Kent

Development and Management Plan Staff Report July 15, 2021

On December 7, 2020, the Connecticut Siting Council (Council) issued a Certificate of Environmental Compatibility and Public Need to Homeland Towers, LLC (Homeland) for the construction, maintenance, and operation of a 135-foot wireless telecommunications facility at 93 Richards Road in Kent, Connecticut. As required in the Council's Decision and Order (D&O), Homeland submitted a Development and Management (D&M) Plan to the Council on June 15, 2021.

The site is located in the northeast corner of a 6.8 acre parcel developed with a residence and a commercial building. The tower/compound site is partially located in a construction vehicle storage area.

Consistent with the Council's D&O, Homeland will construct a 135-foot monopole designed in accordance with the EIA/TIA Structural Standards for Steel Antenna Towers and Antenna Supporting Structures-Revision H. The tower can support four levels of platform-mounted antennas, and municipal/emergency communication whip antennas. The tower has the potential for a 20-foot extension to accommodate future tower sharing.

The nearest property boundary is approximately 84 feet to the southeast. In accordance with D&O Condition 2(d), the tower is designed with a yield point at 51 feet to ensure that the tower setback radius remains within the boundaries of the subject property.

In accordance with D&O Condition No. 2(a), the D&M Plan contains a letter from New Cingular Wireless PCS, LLC (AT&T) dated June 9, 2021 certifying that AT&T is committed to co-locating on the facility once construction of the site is completed by Homeland. Specifically, AT&T will install 6 panel antennas and 9 remote radio heads on a V-frame antenna mount at a centerline height of 131 feet above ground level (agl). The top of AT&T's antennas will extend to 135 feet agl.

The D&M Plan depicts two dipole whip antennas at the top of the tower to support Town of Kent (Town) highway, fire, and dispatch communications, with the whip antennas extending to a height of 154 feet agl. A Town microwave dish would be installed at centerline height of 138 feet agl attached to a mast mounted on top of the tower. Two additional Town whip antennas would be installed at a tower height of 100 feet agl. The exact number of antennas may change and will be coordinated with the Town.

Homeland will construct an approximately 60-foot by 60-foot equipment compound at the site within a irregularly shaped 6,075 square foot lease area. Within the compound, AT&T will install a 6-foot by 6-foot walk in equipment cabinet on an 8-foot by 8-foot wide concrete pad. The cabinet will reach a maximum height of about 11 feet above grade. The compound also has space for the Town's radio equipment (12-foot by 20-foot area) and space for two additional tenants.

The compound will be enclosed by an eight-foot high chain link fence with green privacy slats. Electrical meter equipment and a transformer will be installed outside of the perimeter fence, protected by bollards.



Docket 488 D&M Plan Staff Report Page 2 of 2

Nine new evergreens, 8 to 10 feet tall at planting, will be installed along the north compound fence line to screen views of the compound from the abutting property. The plantings have a 3 year warranty.

Access to the compound will utilize an existing gravel driveway on the property except for a new 60-foot long section of gravel driveway that will be constructed near the entrance on Richards Road to ensure the entire access way remains on the site property. The total length of the new and existing access road to the site is 1,050 feet.

Utilities will be installed underground and would extend along the edge of the existing and new gravel drive, connecting to an existing utility pole on the west side of Richards Road. The underground utilities will extend across Richards Road within a trench.

Emergency power will be provided to AT&T's equipment from a 15-kilowatt propane generator supplied by two 120 gallon above ground fuel tanks. The Town's equipment will have a separate propane emergency power generator supplied by a single 250 gallon above ground propane tank.

Several existing landscape trees will be removed to construct the compound area and one tree will be removed to construct the new section of the driveway. There are no wetlands or watercourses within the facility construction limits.

Erosion and sedimentation controls will comply with the 2002 Connecticut Guidelines for Soil Erosion and Sedimentation Control. An E&S inspection schedule has been provided. Construction hours will comply with the Town's ordinances and will be coordinated with the landowner.

In accordance with D&O Condition No. 2(c), the tower will be painted in a two-tone color scheme with a brown-gray on the bottom portion and a blue-gray on the upper portion. Color swatches were included within the D&M Plan filing. All antennas and mounting equipment will be painted to match the tower color.

The cumulative worst-case radio frequency power density level for AT&T's antennas at the base of the tower will be 8.0 percent of the FCC's General Public/Uncontrolled Maximum Permissible Exposure limit taking into account a 10 dB off-beam pattern loss to account for the relative gain below the antennas.

Consistent with D&O Condition Nos. 2(f) and 7 Homeland intends to commence construction immediately after approval of the D&M Plan. AT&T will locate on the tower within 18 months.

The D&M Plan is consistent with the Council's D&O for Docket No. 488.

### Recommendations

If approved, staff recommends the following conditions:

- 1) Provide construction hours/days of week; and
- 2) Provide detail regarding the Town's equipment and anticipated date of installation.