ATTACHMENT 4

PROJECT INFORMATION

SCOPE OF WORK:

NEW TOWERCO COLOCATION 3,600± SQ.FT. FENCED LEASE AREA NEW TOWERCO 134'± MONOPOLE WITH LIGHTNING ROD AND FAA BEACON LIGHT

NEW TOWERCO ACCESS ROAD AND UTILITIES

• NEW AT&T ANTENNAS: (4) ANTENNAS PER SECTOR WITH (3) SECTORS, FOR A TOTAL OF (12) ANTENNAS

• NEW AT&T (9) RRUS PER SECTOR WITH (3) SECTORS, FOR A TOTAL OF (27) RRUS

• (4) NEW AT&T RAYCAP SURGE SUPPRESSORS

ITEMS LISTED ABOVE TO BE MOUNTED ON THE PROPOSED 134' MONOPOLE

NEW AT&T 11'-5" x 16'-0" EQUIPMENT SHELTER WITH 8'x11' PATIO FOR GENERATOR ON 11'-5" x 24'-0" CONCRETE PAD

(1) NEW AT&T GPS ANTENNA TO BE MOUNTED ON THE PROPOSED AT&T ITEMS LISTED ABOVE TO BE INSTALLED WITHIN THE PROPOSED COMPOUND

(4) NEW AT&T EQUIPMENT RACK

(1) NEW DC POWER PLANT

(1) NEW BATTERY RACK

ITEMS LISTED ABOVE TO BE INSTALLED INSIDE THE PROPOSED

AT&T 11'-5" X 16'-0" EQUIPMENT SHELTER

SITE ADDRESS: BRANFORD, CT 06405

41° 16' 22.96" N 72° 51' 22.57" W ONGITUDE: 72.856269° W

TOWER OWNER: TOWERCO 2013 LLC

CARY, NC 27519

TYPE OF SITE: RAW LAND COLLOCATION MONOPOLE/INDOOR EQUIPMENT

TOWER HEIGHT: 134'-0"±

ANTENNA

CENTERLINE HEIGHT: 130'-0"±

CURRENT USE: TELECOMMUNICATIONS FACILITY PROPOSED USE: TELECOMMUNICATIONS FACILITY



SITE NAME: CT0016 SITE NAME: **BRANFORD-ROSE HILL ROAD**

PROJECT TEAM

TOWERCO 2013 LLC 5000 VALLEYSTONE DRIVE CARY, NC 27519 CITY, STATE, ZIP:

ENGINEERING

COMPANY: HUDSON DESIGN GROUP, LLC. ADDRESS: 1600 OSGOOD STREET

BUILDING 20 NORTH, SUITE 3090 NORTH ANDOVER, MA 01845

CITY, STATE, ZIP: CONTACT: DANIEL P. HAMM, PE PHONE: (978) 557-5553 X222

E-MAIL: daniél.hamm@hudsondesigngroupllc.com

SURVEY

NORTHEAST SURVEY CONSULTANTS 116 PLEASANT ST. SUITE 302 COMPANY:

EASTHAMPTON, MA 01027 CITY, STATE, ZIP: PHONE:

(413) 203-5144



* TowerCo

TOWERCO 2013 LLC

5000 VALLEYSTONE DRIVE CARY, NC 27519

LICENSED ENGINEER

	DRAWING INDEX	REV
T-1	TITLE SHEET	5
C-1	ABUTTERS PLAN	1
C-2	EXISTING CONDITIONS	1
C-3	SITE PLAN	5
A-1	COMPOUND PLAN & ELEVATION	5
A-2	SHELTER DETAILS	5
A-3	EROSION CONTROL NOTES AND DETAILS	5
A-4	TREE PLANTING DETAIL	5

VICINITY MAP



THIS DOCUMENT IS THE CREATION, DESIGN, PROPERTY AND COPYRIGHTED WORK OF TOWERCO. ANY DUPLICATION OR USE WITHOUT EXPRESS WRITTEN CONSENT IS STRICTLY PROHIBITED. DUPLICATION AND USE BY GOVERNMENT AGENCIES FOR THE PURPOSES OF CONDUCTING THEIR LAWFULLY AUTHORIZED REGULATORY AND ADMINISTRATIVE FUNCTIONS IS SPECIFICALLY ALLOWED.

GENERAL NOTES

- THE FACILITY IS AN UNMANNED PRIVATE AND SECURED EQUIPMENT INSTALLATION. IT IS ONLY ACCESSED BY TRAINED TECHNICIANS FOR PERIODIC ROUTINE MAINTENANCE AND THEREFORE DOES NOT REQUIRE ANY WATER OR SANITARY SEWER SERVICE. THE FACILITY IS NOT GOVERNED BY REGULATIONS REQUIRING PUBLIC ACCESS PER ADA REQUIREMENTS.
- CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE TOWERCO REPRESENTATIVE IN WRITING OF DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR

	REVISIONS				
ı					
	5	05/06/15	REVISED PER COMMENTS		
	4	03/30/15	REVISED PER COMMENTS		
l	3	10/24/14	REVISED PER COMMENTS		
l	2	10/15/14	REVISED PER COMMENTS		
l	1	10/09/14	ISSUED FOR REVIEW		
l	0	10/02/14	ISSUED FOR REVIEW		
l	REV. #	DATE	DESCRIPTION		
	DOOLEGE NO. Local C				

DESIGNED BY: DJR SCALE: DRAWN BY: KMS AS SHOWN CHECKED BY: DPH CT0016

SITE NAME:

CT0016 **BRANFORD** -ROSE HILL ROAD

SITE ADDRESS:


45 ROSE HILL ROAD BRANFORD, CT 06405


SHEET TITLE:


TITLE SHEET


SHEET NO:


| -

















\STABILIZED CONSTRUCTION ENTRANCE DETAIL

A-3 /SCALE: N.T.S.

EROSION CONTROL

CONSTRUCTION SEQUENCE

- 1) NOTIFY THE TOWN INLAND WETLANDS AGENT AT LEAST ONE WEEK PRIOR TO THE
- 2) COMPLETE A "CALL BEFORE YOU DIG" PRIOR TO ANY ON SITE ACTIVITY. RECALL EVERY 30 DAYS.
- 3) CUT AND STUMP AREAS OF PROPOSED CONSTRUCTION.
- 4) INSTALL TEMPORARY SEDIMENT AND EROSION CONTROL MEASURES AS REQUIRED.
- 5) WOOD CHIPS GENERATED FROM CLEARING ACTIVITIES MAY BE USED AS A TEMPORARY STABILIZATION MEASURE IN ADDITION TO SILT FENCING & HAY BALES.
- 6) INSTALL HAY BALES TO "BACK UP" SILTATION FENCE ALONG ALL DOWNGRADIENT WETLANDS BOUNDARIES.
- 7) ESTABLISH ROADWAY CENTERLINE WITH GRADE STAKES AND OFF SETS.
- 8) STOCKPILE EXCAVATED SOILS A MINIMUM OF 75 FEET FROM ANY WETLAND AREA.
- 9) CONSTRUCT CLOSED DRAINAGE SYSTEM. PROTECT CULVERT INLETS WITH SEDIMENTATION
- 10) ROUGH GRADE DITCH STARTING FROM THE DOWNGRADIENT LOCATION
- 11) INSTALL STONE LINING AND LEVEL SPREADERS AT CULVERT OUTLETS
- 12) STABILIZE GRADED SLOPES.
- 13) CONSTRUCT ROADWAYS AND PERFORM SITE GRADING, PLACING HAY BALES AND SILTATION FENCES AS REQUIRED TO CONTROL SOIL EROSION.
- 14) EXCAVATE FOR ANY SUBSURFACE UTILITIES.
- 15) STOCKPILE EXCAVATED SOILS A MINIMUM OF 75 FEET FROM ANY WETLAND AREA.
- 16) ESTABLISH SEDIMENT AND EROSION CONTROLS AROUND STOCKPILE SOILS.
- 18) INSTALL STORM DRAINAGE STARTING AT THE MOST DOWNGRADIENT LOCATION.
- 19) INSTALL ALL RIP RAP AT OUTLETS FOR STORM DRAINAGE.
- 20) INSTALL HAY BALE PROTECTION TO STORM DRAINAGE INLETS
- 22) BEGIN TEMPORARY AND PERMANENT SEEDING AND MULCHING. ALL CUT AND FILL SLOPES SHALL BE SEEDED OR MULCHED IMMEDIATELY AFTER THEIR CONSTRUCTION. NO AREA SHALL BE LEFT UNSTABILIZED FOR A TIME PERIOD OF MORE THAN 30 DAYS.
- 23) DAILY, OR AS REQUIRED, CONSTRUCT, INSPECT, AND IF NECESSARY, RECONSTRUCT TEMPORARY BERMS, DRAINS, DITCHES, SILT FENCES AND SEDIMENT TRAPS INCLUDING MULCHING AND SEEDING.
- 24) BEGIN EXCAVATION FOR AND CONSTRUCTION OF TOWERS AND PLATFORMS.
- 25) FINISH PAVING ALL ROADWAYS, DRIVES, AND PARKING AREAS,
- 26) COMPLETE PERMANENT SEEDING AND LANDSCAPING.
- 27) NO FLOW SHALL BE DIVERTED TO ANY WETLANDS UNTIL A HEALTHY STAND OF GRASS HAS BEEN ESTABLISHED IN REGRADED AREAS.
- 28) AFTER GRASS HAS BEEN FULLY GERMINATED IN ALL SEEDED AREAS, REMOVE ALL TEMPORARY EROSION CONTROL MEASURES.

IMPACT OF STORMWATER DURING CONSTRUCTION ACTIVITY

ALL SEDIMENT CONTROLS, INCLUDING SILTATION FENCES AND HAY BALES MUST BE INSPECTED WEEKLY OR IMMEDIATELY AFTER A STORMWATER RUNOFF GENERATING EVENT. ALL SEDIMENT CONTROLS MUST BE MAINTAINED IN AN EFFECTIVE CONDITION.

IN THE EVENT THAT STORMWATER IS FLOWING IN THE EXISTING/PROPOSED DRAINAGE SWALE, THE FOLLOWING MUST BE NOTED:

- 1) BY INSTALLING THE STORM DRAINAGE STARTING AT THE MOST DOWNGRADIENT LOCATION, AND BY CONSTRUCTION THE DITCH STARTING AT THE MOST DOWNGRADIENT LOCATION, STORMWATER FLOW WILL NOT BE IMPOUNDED DURING THE CONSTRUCTION ACTIVITY.
- 2) ADDITIONAL MEASURES MUST BE TAKEN DURING TIMES OF RAIN OR FLOW. THESE INCLUDE THE CESSATION OF ALL CONSTRUCTION ACTIVITY IN THE DRAINAGE SWALES AT TIMES OF "HEAVY RAIN" OR "SIGNIFICANT FLOW" WHICH HAVE THE POTENTIAL TO CAUSE SOIL SCOURING. IN THE ABSENCE OF AN ON SITE AGREEMENT WITH THE TOWN INLAND WETLANDS AGENT.

CONSTRUCTION SPECIFICATIONS - SILT FENCE

- 1) THE GEOTEXTILE FABRIC SHALL MEET THE DESIGN CRITERIA FOR SILT FENCES.
- 2) THE FABRIC SHALL BE EMBEDDED A MINIMUM OF 8 INCHES INTO THE GROUND AND THE SOIL COMPACTED OVER THE EMBEDDED FABRIC.
- 3) WOVEN WIRE FENCE SHALL BE FASTENED SECURELY TO THE FENCE POSTS WITH WIRE TIES OR STAPLES.
- 4) FILTER CLOTH SHALL BE FASTENED SECURELY TO THE WOVEN WIRE FENCE WITH TIES SPACED EVERY 24 INCHES AT THE TOP, MID-SECTION AND BOTTOM.
- 5) WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6 INCHES, FOLDED, AND STAPLED.
- 6) FENCE POSTS SHALL BE A MINIMUM OF 36 INCHES LONG AND DRIVEN A MINIMUM OF 16 INCHES INTO THE GROUND. WOOD POSTS SHALL BE OF SOUND QUALITY HARDWOOD AND SHALL HAVE A MINIMUM CROSS SECTIONAL AREA OF 3.0 SQUARE INCHES.
- 7) MAINTENANCE SHALL BE PERFORMED AS NEEDED TO PREVENT BULGES IN THE SILT FENCE DUE TO DEPOSITION OF SEDIMENT.

MAINTENANCE - SILT FENCE

SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE 1) IMMEDIATELY.

IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY.

SEDIMENT SHOULD BE INSPECTED AFTER EVERY STORM EVENT. THE DEPOSITS SHOULD BE REMOVED WHEN THEY REACHED APPROXIMATELY ONE—HALF THE HEIGHT OF THE BARRIER.

SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED

EROSION CONTROL MEASURES:

THE CONTRACTOR (TO BE NAMED PRIOR TO ANY WORK BEING PERFORMED) IS ASSIGNED THE RESPONSIBILITY FOR IMPLEMENTING THIS EROSION AND SEDIMENT CONTROL PLAN. THIS RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN, NOTIFYING THE PLANNING AND ZONING OFFICE OF ANY TRANSFER OF THIS RESPONSIBILITY, AND FOR CONVEYING A COPY OF THE EROSION AND SECULATION OF THE PLAN IS THE TITLE TO THE LAND IS TRANSFERDED. SEDIMENT CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED

- 1) DISTURBED AREAS SHALL BE KEPT TO THE MINIMUM AREA NECESSARY TO CONSTRUCT THE ROADWAYS AND ASSOCIATED DRAINAGE FACILITIES.
- 2) HAY BALE BARRIERS AND SEDIMENT TRAPS SHALL BE INSTALLED AS REQUIRED. BARRIERS AND TRAPS ARE TO BE MAINTAINED AND CLEANED UNTIL ALL SLOPES HAVE A HEALTHY STAND OF GRASS.
- 3) BALED HAY AND MULCH SHALL BE MOWINGS OF ACCEPTABLE HERBACEOUS GROWTH, FREE FROM NOXIOUS WEEDS OR WOODY STEMS, AND SHALL BE DRY. NO SALT HAY SHALL BE USED.
- 4) FILL MATERIAL SHALL BE FREE FROM STUMPS, WOOD, ROOTS, ETC.
- 5) STOCKPILED MATERIALS SHALL BE PLACED ONLY IN NON RESTRICTED WETLAND AREAS ON PLANS. STOCKPILES SHALL BE PROTECTED BY SILTATION FENCE AND SEEDED TO PREVENT EROSION. THESE MEASURES SHALL REMAIN UNTIL ALL MATERIAL HAS BEEN PLACED OR DISPOSED OFF SITE.
- 6) ALL DISTURBED AREAS SHALL BE LOAMED AND SEEDED. A MINIMUM OF 4 INCHES OF LOAM SHALL BE INSTALLED WITH NOT LESS THAN ONE POUND OF SEED PER 50 SQUARE YARDS OF AREA. SLOPES 2:1 OR GRATED TO BE STABILISED WITH TURF REINFORCEMENT MAT TYPE P300P NORTH AMERICAN GREEN (1-800-772-2040), OR ENGINEER APPROVED EQUAL.
- 7) APPLICATION OF GRASS SEED, FERTILIZERS AND MULCH SHALL BE ACCOMPLISHED Y BROADCAST SEEDING OR HYDROSEEDING AT THE RATES OUTLINED BELOW:

LIMESTONE: 75-100 LBS./1,000 SQUARE FEET. FERTILIZER: RATE RECOMMENDED BY MANUFACTURER. MULCH: HAY MULCH APPROXIMATELY 3 TONS/ACRE UNLESS EROSION CONTROL MATTING IS USED.

SEED MIX (SLOPES LESS THAN 4:1)
CREEPING RED FESCUE
TALL FESCUE
RED TOP SLOPE MIX (SLOPES GREATER TAN 4:1)
CREEPING RED FESCUE
TALL FESCUE BIRDSFOOT TREEFOIL

- 8) AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED THE TEMPORARY EROSION CONTROL MEASURES ARE TO BE REMOVED.
- 9) PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES.
- 10) ALL CATCH BASIN INLETS WILL BE PROTECTED WITH LOW POINT SEDIMENTION
- 11) ALL STORM DRAINAGE OUTLETS WILL BE STABILIZED AND CLEANED AS REQUIRED, BEFORE THE DISCHARGE POINTS BECOME OPERATIONAL.
- 12) ALL DEWATERING OPERATIONS MUST DISCHARGE DIRECTLY INTO A SEDIMENT FILTER AREA.
- 13) NO DISCHARGE SHALL BE DIRECTED TOWARDS ANY PROPOSED DITCHES, SWALES, OR PONDS UNTIL THEY HAVE BEEN PROPERLY STABILIZED.

CONSTRUCTION SPECIFICATIONS - STRAW OR HAY BALES

- 1) BALES SHALL BE PLACED IN A ROW WITH THE ENDS TIGHTLY ADJOINING.
- 2) EACH BALE SHALL BE EMBEDDED IN THE GROUND A MINIMUM OF 4 INCHES.
- 3) BALES SHALL BE ANCHORED IN PLACE BY AT LEAST TWO STAKES DRIVEN THROUGH THE BALE. THE STAKES SHALL BE DRIVEN AT LEAST 18 INCHES INTO THE GROUND.
- 4) BARRIERS SHALL BE INSPECTED AFTER EVERY RAINFALL AND PROMPTLY REPAIRED FOR REPLACED AS NECESSARY.
- 5) BALES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED OF PROPERLY.


MAINTENANCE - STRAW OR HAY BALES

- STRAW OR HAY BALES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL,
- 2) CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED BALES, UNDERCUTTING BENEATH THE BALES, AND FLOW AROUND THE END OF THE BALES.
- 3) NECESSARY REPAIRS OR REPLACEMENT OF BALES SHALL BE ACCOMPLISHED
- 4) SEDIMENT DEPOSITS SHOULD BE CHECKED AFTER EACH RAINFALL. THE DEPOSITS SHOULD BE REMOVED WHEN THE LEVEL OF DEPOSITION REACHES APPROXIMATELY ONE—HALF OF THE HEIGHT OF THE TABLE.
- 5) SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE BARRIER HAS BEEN DISMANTLED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED USING THE APPROPRIATE VEGETATIVE BMP.



TOWERCO 2013 LLC 5000 VALLEYSTONE DRIVE CARY, NC 27519





- 1							
- 1							
		REVISIONS					
		112101010					
	5	05/06/15	REVISED PER COMMENTS				
	4	03/30/15	REVISED PER COMMENTS				
	3	10/24/14	REVISED PER COMMENTS				
	2	10/15/14	REVISED PER COMMENTS				
	1	10/09/14	ISSUED FOR REVIEW				
	0	10/02/14	ISSUED FOR REVIEW				
	REV. #	DATE	DESCRIPTION				

DESIGNED BY: DJR SCALE: DRAWN BY: KMS AS SHOWN CT0016

SITE NAME:

CT0016 **BRANFORD** -ROSE HILL ROAD

SITE ADDRESS:


45 ROSE HILL ROAD BRANFORD, CT 06405

SHEET TITLE:

EROSION CONTROL NOTES AND DETAILS


SHEET NO:

A-3



NOTES:

- LANDSCAPE TREES SHALL BE A MINIMUM OF 6'-0" IN HEIGHT WHEN PLANTED.
- 2. SPECIES PROPOSED THUJA OCCIDENTALIS PYRAMIDAL (PYRAMIDAL ARBORVITAE)





TOWERCO 2013 LLC 5000 VALLEYSTONE DRIVE CARY, NC 27519



A LE P. HAM.

No. 24178

OF CONNECTOR

No. 24178

OF CONNECTOR

OF CONNE

LICENSED ENGINEER

l	REVISIONS				
ı					
ı	5	05/06/15	REVISED PER COMMENTS		
ı	4	03/30/15	REVISED PER COMMENTS		
ı	3	10/24/14	REVISED PER COMMENTS		
ı	2	10/15/14	REVISED PER COMMENTS		
ı	1	10/09/14	ISSUED FOR REVIEW		
ı	0	10/02/14	ISSUED FOR REVIEW		
ı	REV. #	DATE	DESCRIPTION		

ı	PROJECT NO.	DESIGNED BY:	DJR	SCALE:	
ı	CT0016	DRAWN BY:	KMS	l as	SHO
ı	0.00.0	CHECKED BY:	DPH		

SITE NAME:

CT0016 BRANFORD -ROSE HILL ROAD

SITE ADDRESS:


45 ROSE HILL ROAD BRANFORD, CT 06405


SHEET TITLE:

TREE PLANTING DETAIL

SHEET NO:

A-4







SITE NO: CT0016 SITE NAME:BRANFORD ROSE HILL ROAD ADDRESS: 45 ROSE HILL ROAD BRANFORD, CT 06405

TowerCo


TowerCO 2013 LLC
5000 VALLEYSTONE DRIVE
CARY, NC 27519

Hudson Dealgn Group G


TOPOGRAPHY MAP

DATE: 10/01/2014

DRAWN BY: KMS SCALE: 1"=500'



SOURCE: BING MAPS





SITE NO: CT0016 SITE NAME:BRANFORD ROSE HILL ROAD

ADDRESS: 45 ROSE HILL ROAD BRANFORD, CT 06405



TOWERCO 2013 LLC 5000 VALLEYSTONE DRIVE CARY, NC 27519




AERIAL PHOTO

DATE: 10/01/2014

DRAWN BY: KMS

SCALE: 1"=500"



Issued Date: 06/05/2014

Amanda V. Fry TowerCo 2013 LLC 5000 Valleystone Drive Suite 200 Cary, NC 27519

** DETERMINATION OF NO HAZARD TO AIR NAVIGATION **

The Federal Aviation Administration has conducted an aeronautical study under the provisions of 49 U.S.C., Section 44718 and if applicable Title 14 of the Code of Federal Regulations, part 77, concerning:

Structure: Monopole CT0016 Rose Hill

Location: Branford, CT

Latitude: 41-16-22.96N NAD 83

Longitude: 72-51-22.57W

Heights: 118 feet site elevation (SE)

140 feet above ground level (AGL) 258 feet above mean sea level (AMSL)

This aeronautical study revealed that the structure would have no substantial adverse effect on the safe and efficient utilization of the navigable airspace by aircraft or on the operation of air navigation facilities. Therefore, pursuant to the authority delegated to me, it is hereby determined that the structure would not be a hazard to air navigation provided the following condition(s) is(are) met:

As a condition to this Determination, the structure is marked/lighted in accordance with FAA Advisory circular 70/7460-1 K Change 2, Obstruction Marking and Lighting, paint/red lights - Chapters 3(Marked),4,5(Red),&12.

It is required that FAA Form 7460-2, Notice of Actual Construction or Alteration, be e-filed any time the project is abandoned or:

	At least 10 days prior to start of construction (7460-2, Part 1)
X	Within 5 days after the construction reaches its greatest height (7460-2, Part 2)

See attachment for additional condition(s) or information.

Any height exceeding 140 feet above ground level (258 feet above mean sea level), will result in a substantial adverse effect and would warrant a Determination of Hazard to Air Navigation.

This determination expires on 12/05/2015 unless:

- (a) the construction is started (not necessarily completed) and FAA Form 7460-2, Notice of Actual Construction or Alteration, is received by this office.
- (b) extended, revised, or terminated by the issuing office.
- (c) the construction is subject to the licensing authority of the Federal Communications Commission (FCC) and an application for a construction permit has been filed, as required by the FCC, within 6 months of the date of this determination. In such case, the determination expires on the date prescribed by the FCC for completion of construction, or the date the FCC denies the application.

NOTE: REQUEST FOR EXTENSION OF THE EFFECTIVE PERIOD OF THIS DETERMINATION MUST BE E-FILED AT LEAST 15 DAYS PRIOR TO THE EXPIRATION DATE. AFTER RE-EVALUATION OF CURRENT OPERATIONS IN THE AREA OF THE STRUCTURE TO DETERMINE THAT NO SIGNIFICANT AERONAUTICAL CHANGES HAVE OCCURRED, YOUR DETERMINATION MAY BE ELIGIBLE FOR ONE EXTENSION OF THE EFFECTIVE PERIOD.

This determination is subject to review if an interested party files a petition that is received by the FAA on or before July 05, 2014. In the event a petition for review is filed, it must contain a full statement of the basis upon which it is made and be submitted to the Manager, Airspace Regulations & ATC Procedures Group, Federal Aviation Administration, 800 Independence Ave, SW, Room 423, Washington, DC 20591.

This determination becomes final on July 15, 2014 unless a petition is timely filed. In which case, this determination will not become final pending disposition of the petition. Interested parties will be notified of the grant of any review. For any questions regarding your petition, please contact Airspace Regulations & ATC Procedures Group via telephone -- 202-267-8783 - or facsimile 202-267-9328.

This determination is based, in part, on the foregoing description which includes specific coordinates, heights, frequency(ies) and power. Any changes in coordinates, heights, and frequencies or use of greater power will void this determination. Any future construction or alteration, including increase to heights, power, or the addition of other transmitters, requires separate notice to the FAA.

This determination does include temporary construction equipment such as cranes, derricks, etc., which may be used during actual construction of the structure. However, this equipment shall not exceed the overall heights as indicated above. Equipment which has a height greater than the studied structure requires separate notice to the FAA.

This determination concerns the effect of this structure on the safe and efficient use of navigable airspace by aircraft and does not relieve the sponsor of compliance responsibilities relating to any law, ordinance, or regulation of any Federal, State, or local government body.

Any failure or malfunction that lasts more than thirty (30) minutes and affects a top light or flashing obstruction light, regardless of its position, should be reported immediately to (877) 487-6867 so a Notice to Airmen (NOTAM) can be issued. As soon as the normal operation is restored, notify the same number.

This aeronautical study considered and analyzed the impact on existing and proposed arrival, departure, and en route procedures for aircraft operating under both visual flight rules and instrument flight rules; the impact on all existing and planned public-use airports, military airports and aeronautical facilities; and the cumulative impact resulting from the studied structure when combined with the impact of other existing or proposed structures. The study disclosed that the described structure would have no substantial adverse effect on air navigation.

An account of the study findings, aeronautical objections received by the FAA during the study (if any), and the basis for the FAA's decision in this matter can be found on the following page(s).

A copy of this determination will be forwarded to the Federal Communications Commission (FCC) because the structure is subject to their licensing authority.

If we can be of further assistance, please contact Cindy Whitten, at (816) 329-2528. On any future correspondence concerning this matter, please refer to Aeronautical Study Number 2013-ANE-2363-OE.

Signature Control No: 203767476-220079795

(DNH)

John Page Manager, Obstruction Evaluation Group

Attachment(s) Additional Information Frequency Data Map(s)

cc: FCC

Additional information for ASN 2013-ANE-2363-OE

Proposal: To construct a(n) Monopole to a height of 140 feet above ground level, 258 feet above mean sea level.

Location: The structure will be located 1.49 nautical miles east of HVN Airport reference point.

Part 77 Obstruction Standard(s) Exceeded:

Section 77.17 (a) (5) a height that affects an Airport Surface by penetrating

Section 77.19 (a) Horizontal Surface by 96 feet as applied to HVN.

Preliminary FAA study indicates that the above mentioned structure would:

have no effect on any existing or proposed arrival, departure, or en route instrument flight rules (IFR) operations or procedures.

have no effect on any existing or proposed arrival, departure, or en route instrument/visual flight rules (IFR/VFR) minimum flight altitudes.

not exceed traffic pattern airspace

have no physical or electromagnetic effect on the operation of air navigation and communications facilities.

have no effect on any airspace and routes used by the military.

No objections were received from the public comment period.

Frequency Data for ASN 2013-ANE-2363-OE

LOW FREQUENCY	HIGH FREQUENCY	FREQUENCY UNIT	ERP	ERP UNIT
698	806	MHz	1000	W
806	824	MHz	500	W
824	849	MHz	500	W
851	866	MHz	500	W
869	894	MHz	500	W
896	901	MHz	500	W
901	902	MHz	7	W
930	931	MHz	3500	W
931	932	MHz	3500	W
932	932.5	MHz	17	dBW
935	940	MHz	1000	W
940	941	MHz	3500	W
1850	1910	MHz	1640	W
1930	1990	MHz	1640	W
2305	2310	MHz	2000	W
2345	2360	MHz	2000	W

TOPO Map for ASN 2013-ANE-2363-OE

