



**REVISED DRAINAGE REPORT  
INDEPENDENT SPENT FUEL STORAGE  
INSTALLATION  
DOMINION NUCLEAR CONNECTICUT  
MILLSTONE POWER STATION  
WATERFORD, CONNECTICUT**

**PREPARED FOR:**

Dominion Nuclear Connecticut, Inc.  
Rope Ferry Road  
Waterford, CT 06385

**PREPARED BY:**



GZA GeoEnvironmental, Inc.  
One Edgewater Drive  
Norwood, Massachusetts 02062

April 2012  
File No. 01.0171138.00

April 12, 2012  
File No. 01.171138.00

Dominion Nuclear Connecticut  
Rope Ferry Road  
Waterford, Connecticut 06385



Attention: J. David Dakers, P.E.

Re: Revised Drainage Report and Drawings  
Independent Spent Fuel Storage Installation  
Millstone Power Station  
Waterford, Connecticut

Dear Mr. Dakers:

One Edgewater Drive  
Norwood  
Massachusetts  
02062  
781-278-3700  
FAX 781-278-5701  
www.gza.com

As per Purchase Order No. 70237837 dated December 8, 2011, GZA GeoEnvironmental, Inc. (GZA) is pleased to provide the enclosed revised Draft Drainage Report and Drawings for the above-referenced project. This report includes an evaluation of the hydrology of pre-construction and post-construction site conditions. The report discusses GZA's approach to the full build-out site drainage and presents drainage details. Modifications to the drainage system to accommodate full ISFSI build-out include construction of new catch basins and pipes to convey runoff from the site to the existing drainage network. Recommendations for Best Management Practices, consistent with Connecticut Guidelines for Soil Erosion and Sediment Control, are also presented.

Revised Site Plans detailing the existing conditions, the proposed grading and drainage, and the proposed erosion and sediment control measures are also enclosed.

We understand that the supplemental construction of the ISFSI will require a permit application under the Department of Environmental Protection (DEP) General Storm Water Management Program, including preparation of a Soil Erosion and Sediment Control plan and details, and Stormwater Pollution Control Plan (SWCP). This report will be provided under separate cover shortly. Finally, GZA is evaluating our Environmental Report, originally prepared in 2003, to confirm that the site modifications do not affect the conclusions therein. The revised report, or a letter confirming that no changes are necessary in our opinion, will follow under separate cover shortly.

Please contact David Leone at (781) 278-5788 if you have any questions. We appreciate the opportunity to assist you with this project.

Very truly yours,

GZA GEOENVIRONMENTAL, INC.

A handwritten signature in blue ink, appearing to read "David Leone".

David M. Leone, P.E.  
Sr. Project Manager

A handwritten signature in blue ink, appearing to read "Daniel C. Stapleton".

Daniel C. Stapleton, P.E.  
Consultant / Reviewer

A handwritten signature in blue ink, appearing to read "Peter H. Baril".

Peter H. Baril, P.E.  
Principal

# TABLE OF CONTENTS

	<u>Page</u>
<b>EXECUTIVE SUMMARY</b> .....	<b>I</b>
<b>1.0 INTRODUCTION</b> .....	<b>1</b>
<b>2.0 PROJECT DESCRIPTION</b> .....	<b>2</b>
2.1 SITE DESCRIPTION.....	2
2.2 CONSTRUCTION .....	3
2.3 PROPOSED DRAINAGE IMPROVEMENTS .....	5
<b>3.0 PRE-CONSTRUCTION DRAINAGE CONDITIONS</b> .....	<b>6</b>
3.1 SURFICIAL SOIL AND SUBSURFACE CONDITIONS .....	6
3.2 DRAINAGE PATTERNS .....	6
3.3 DRAINAGE CALCULATIONS - PRE-CONSTRUCTION CONDITION .....	7
<b>4.0 PROPOSED FULL BUILD-OUT CONDITION</b> .....	<b>8</b>
4.1 DESIGN OBJECTIVES AND CRITERIA .....	8
4.2 PROPOSED SITE CHARACTERISTICS AND DRAINAGE SYSTEM LAYOUT ..	8
4.3 DRAINAGE CALCULATIONS – FULL BUILD-OUT CONDITION .....	10
<b>5.0 POST CONSTRUCTION STORM WATER MANAGEMENT</b> .....	<b>11</b>
5.1 CATCH BASINS .....	11
5.2 VELOCITY DISSIPATION .....	12
<b>6.0 EROSION AND SEDIMENT CONTROLS</b> .....	<b>12</b>
6.1 EROSION AND SEDIMENT CONTROL MEASURES .....	12
6.1.1 <i>Site Clearing and Excavation</i> .....	13
6.1.2 <i>Hay Bale/ Silt Fence Barriers</i> .....	13
6.1.3 <i>Catch Basin Inlet Protection</i> .....	13
6.1.4 <i>Construction Site Entrance</i> .....	13
6.1.5 <i>Slope Protection</i> .....	14
6.1.6 <i>Temporary Sediment Basins</i> .....	14
6.1.7 <i>Stockpiled Materials</i> .....	14
6.1.8 <i>Soil Placement Area</i> .....	14
6.1.9 <i>Winter Stabilization</i> .....	14
6.1.10 <i>Outlet Protection</i> .....	15
6.1.11 <i>Dust Control</i> .....	15
6.1.12 <i>Construction Dewatering</i> .....	15
6.1.13 <i>Equipment Fueling</i> .....	15
6.2 INSPECTION AND MAINTENANCE .....	15
6.3 SEQUENCE OF GRADING AND CONSTRUCTION ACTIVITIES .....	15

## **TABLE OF CONTENTS (cont.)**

### **TABLES**

Table 1	Rainfall / Runoff Modeling Results
Table 2	Pipe Node Report

### **FIGURES**

Figure 1	Site Locus
Figure 2	Existing Conditions Drainage Area Plan
Figure 3	Proposed Conditions Drainage Area Plan

### **APPENDICES**

Appendix A	GZA Limitations
Appendix B	Hydrologic Analysis Results
Appendix C	Drainage System Analysis Results
Appendix D	Quality Control Statements



## EXECUTIVE SUMMARY

In 2003, GZA GeoEnvironmental, Inc. (GZA) conducted hydrologic and hydraulic analyses, and drainage design, for Dominion Nuclear Connecticut, Inc.'s (DNC's) construction and operation of an Independent Spent Fuel Storage Installation (ISFSI) at the Millstone Power Station (Millstone), located in the Town of Waterford, New London County, Connecticut. The ISFSI is located in the southerly portion of the 520-acre Millstone property, in an area that was previously developed as a parking lot (See Locus Plan – Figure 1). The ISFSI project was planned for construction in phases. The first phase (Phase I), which included the construction of a pad for 19 horizontal storage modules (HSMs) and the installation of a trench drain within the concrete aprons located west of the HSMs, was completed in 2004. Much of the site work required for full build-out was performed during the initial phase. The ISFSI is designed to support a total of 135 HSMS at full build-out.

Please note that for the purposes of this report, “pre-construction” indicates the site conditions prior to the construction of the Phase I ISFSI, “existing conditions” refer to the Phase I ISFSI construction and “proposed conditions” refers to the full ISFSI build out conditions.

The ISFSI project involves the following principal elements:

1. Development of the approximately 2-acre ISFSI site. The ISFSI site consists of a level, graded surface (at approximately Elevation 21) covered with concrete pads (to support the HSMs), concrete aprons and asphalt (at the north-western portion of the site);
2. Construction of a haul path (paved road) between the ISFSI site and the Millstone Unit 2 Auxiliary Building (completed as part of the Phase I work);
3. Abandonment of certain existing drainage structures and construction of new drainage and other utilities (completed as part of the Phase I work);
4. Removal and transportation of excess soil (generated from the ISFSI site grading construction) to an approximately 5-acre Soil Placement Area, located in a central portion of Millstone property that was previously used by Amtrak for railroad construction staging (completed as part of the Phase I work); and
5. Realignment of existing Security Protected Area (PA) fence to encompass the ISFSI site, haul path, and an approximately 4-acre Equipment Laydown Area (located immediately west of the ISFSI site) (completed as part of the Phase I work).

Subsequent to the completion of Phase I, GZA understands that the opposing slope condition, created by the grading and drainage design to convey runoff to the Phase I trench drain, resulted in a hindrance to loading the HSMs. As such DNC is requesting a revision to the design of the full build-out portion of the ISFSI to eliminate these restrictive hauling conditions. GZA understands that the existing grading and drainage for the Phase I ISFSI area, including the existing trench drain, need not be modified since the majority of the Phase I HSMs have already been loaded. DNC also plans to expand the entire western portion of the ISFSI site by approximately 0.23 acres during the full build-out to allow for easier access by the HSM transporter/ hauler.

Based on these proposed changes, GZA has conducted a revised hydrologic and hydraulic analysis, and drainage design. This Drainage Report presents the basis and results of these analyses, and also presents recommendations for sediment and erosion control during the final (full-build-out) ISFSI construction phase. Details of the existing and proposed site features, drainage improvements and sediment and erosion controls for construction, are presented separately on the *Revised Site Plans*<sup>1</sup>.

Based on the existing site grades, drainage patterns and drainage structures, the ISFSI site is located within a contributory drainage area that is approximately 23 acres in size. This drainage area, prior to construction of the Phase I ISFSI, was comprised of developed upland and filled areas, some wooded low-lying areas, a pond and a former parking lot. The Phase I ISFSI now occupies a portion of this area (~2 acres). Surface runoff within the contributory drainage area flows in a general northwest to southeast direction.

The pre-construction drainage characteristics further subdivide this area into four sub-areas (referenced in the report as Sub-Areas 1 through 4). The locations of the pre-construction drainage sub-areas are indicated on Figure 2. Sub-Area 1 is a small (approximately 3 acre) low-lying area with no defined outlet, which provides temporary ponding and storage of stormwater. Sub-Area 2 is a larger (approximately 11 acre) area consisting of wetland areas and a small pond and associated upland areas. Sub-Area 3 consists principally of the ISFSI site and Equipment Laydown Area and is about 8 acres in size. Runoff from the 30-inch diameter trunkline discharges at the existing permitted outlet located east of the ISFSI site (No. DSN 011). Sub-Area 4 is located at the southeast corner of Sub-Area 3 and is about 2 acres in size.

The full build-out construction of the ISFSI will not significantly change the existing or pre-construction drainage patterns. Runoff characteristics will remain nearly identical to pre-construction and Phase I ISFSI conditions, in terms of infiltration potential as well as magnitude, timing, and volume of runoff. The drainage improvements constructed in 2004 separate the conveyance of stormwater into two trunklines. These are detailed on the

---

<sup>1</sup> Revisions to original design, Millstone Power Station, Independent Spent Fuel Storage Installation (ISFSI), Dominion Nuclear Connecticut, Waterford, CT. April 2012

*Revised Site Plans.* One trunkline (30-inch diameter RCP) conveys stormwater from Sub-Areas 1 and 2, which encompass approximately 14 acres and are located upgradient of the ISFSI site. Catch basins within Sub-Area 3 but outside the Equipment Laydown Area and the ISFSI site are also connected to the 30-inch trunkline. This trunkline was constructed along the existing Access Road and discharges at the existing outlet location (No. DSN 011). Stormwater is collected within the Phase I ISFSI site using an approximately 210 feet long trench drain located west of the HSMs and catch basins constructed during Phase I in 2004. Within the Equipment Laydown Area, stormwater is collected using catch basins and drainage swales. Once collected, the stormwater is conveyed via the second trunkline along the southern and eastern portions of the ISFSI site and also discharges to the common manhole (no.4) and from there is conveyed to the existing outlet location. The outlet discharges stormwater to an existing drainage swale, which in turn discharges to an existing freshwater pond located about 250 feet east of the ISFSI site. This approach diverts stormwater emanating from the upgradient portions of the drainage area away from the close proximity of the ISFSI. It also minimizes the potential for transient flooding (i.e. surcharging), within the ISFSI site during storm events exceeding the 25-year design storm.

Additional catch basins are proposed to be installed within the ISFSI site for the full build-out condition. The proposed catch basins will be connected to the existing drainage network at the ISFSI site via 12-inch and 21-inch diameter reinforced concrete pipes.

Peak rates of runoff, under the design storm condition for the proposed changes are not expected to be significantly different from existing condition (Phase I construction). Phase I development of the ISFSI site is estimated to have increased peak rates of runoff, under the design storm condition by approximately 5 percent or less. This increase is not appreciable, as it will not materially increase water surface profiles or flooding potential to the existing freshwater pond (which will receive the runoff).

The drainage system incorporates structural Best Management Practices (BMPs), consistent with Connecticut guidelines<sup>2</sup>, Structural Best Management Practices, including, but not limited to deep sump catch basins with hooded outlet pipes, a velocity dissipater (rip-rap swale) at the outlet and grassed swales. Standard erosion and sedimentation controls measures will be incorporated during the final phase of construction.

---

<sup>2</sup> These include: 1) the “2002 Connecticut Guidelines for Soil and Erosion and Sediment Control”; and 2) the “Connecticut Stormwater Quality Manual”, 2004. Both these documents were prepared by the Connecticut Department of Environmental Protection.

## 1.0 INTRODUCTION

GZA GeoEnvironmental, Inc. (GZA) conducted hydrologic and hydraulic analyses, and drainage design, for Dominion Nuclear Connecticut, Inc.'s (DNC's) construction and operation of an Independent Spent Fuel Storage Installation (ISFSI) at the Millstone Power Station (Millstone) in 2003. The ISFSI project was planned for construction in phases. Most of the site work required for full build-out was performed during the first phase (Phase I) constructed in 2004.

Phase I included the construction of a pad for 19 horizontal storage modules (HSMs), and included the installation of a trench drain within the concrete aprons located west of the HSMs. GZA understands that the opposing slope condition created by the grading and drainage design to convey runoff to the trench drain is a hindrance to loading the HSMs. DNC requested a revision to the design of the full build-out portion of the ISFSI to eliminate these restrictive hauling conditions. The ISFSI is designed to support a total of 135 HSMS at full build-out. GZA understands that the existing grading and drainage for the Phase I ISFSI area, including the existing trench drain, need not be modified since the majority of the Phase I HSMs have already been loaded. DNC also plans to expand the entire western portion of the ISFSI site by approximately 0.23 acres during the full build-out to allow for easier access by the HSM transporter. This additional area will be lined with asphalt.

GZA GeoEnvironmental, Inc. (GZA) has revised the hydrologic and hydraulic analyses, and drainage design, to include the proposed changes to the original design for the construction and operation of the ISFSI. The objectives of the drainage study were to:

1. Describe the pre-construction and existing site conditions, including drainage areas and patterns, and the runoff potential and hydraulic capacity of existing storm water collection systems in comparison to the proposed conditions; and
2. Revise the storm water drainage design for the full build-out condition.

This Drainage Report presents the basis and results of these analyses, and recommendations for sediment and erosion control during the final construction phase. Details of the existing and proposed site features, drainage improvements and erosion and sediment controls for construction, are presented separately on the *Revised Site Plans*.

Upon completion of construction, the ISFSI site and related drainage improvements will be incorporated into Millstone's existing "*General Permit for the Discharge of Stormwater Associated with Industrial Activities*".

This report is subject to the limitations listed in **Appendix A**.

## **2.0 PROJECT DESCRIPTION**

Millstone is located in the Town of Waterford, New London County, Connecticut. The ISFSI site is a dry fuel storage facility that provides interim storage for spent nuclear fuel. It is composed of individual concrete and steel containment units (Horizontal Storage Modules [HSMs]) housed on concrete storage pads with concrete apron areas for haul vehicle access. The project, partially constructed in 2004, involves the following principal elements:

1. Development of the approximately 2-acre ISFSI site. The ISFSI site will consist of a level, graded surface (at approximately Elevation 21) covered with concrete pads (to support the HSMs), concrete aprons and asphalt (partially completed as part of the Phase I work).
2. Construction of a haul path (paved road) between the ISFSI site and the Millstone Unit 2 Auxiliary Building (completed as part of the Phase I work).
3. Abandonment of certain existing drainage structures and construction of new drainage and other utilities (partially completed as part of the Phase I work).
4. Removal and transportation of excess soil (generated from the ISFSI site grading construction) to an approximately 5-acre Soil Placement Area, located in a central portion of Millstone property that was previously used by Amtrak for railroad construction staging (completed as part of the Phase I work).
5. Realignment of existing Security Protected Area (PA) fence to encompass the ISFSI site, haul path, and an approximately 4-acre Equipment Laydown Area (located immediately west of the ISFSI site) (completed as part of the Phase I work).

The first Phase ("Phase I") of the ISFSI Project was constructed in 2004. During the Phase I (partial build-out), a pad for 19 HSMs was constructed. Most of the site work required for full build-out was performed during the first phase (Phase I). When at full build-out, the ISFSI will support a total of 135 HSMs.

### **2.1 SITE DESCRIPTION**

All construction components of the project, including the ISFSI site, the haul path, the Equipment Laydown Area and the Soil Placement Area are located on upland portions of the Millstone property that have been previously disturbed, filled, and developed. The ISFSI area, haul path and Equipment Laydown Area are all contiguous, whereas the Soil Placement Area is located in the central portion of the Millstone property, north of the Amtrak railroad line.

The ISFSI site is approximately 92,000 square feet (approximately 2 acres) in size. The area is abutted to the east by an existing asphalt-paved access road. The grade at the ISFSI site is approximately Elevation 21 (NGVD 29).

The Equipment Laydown Area is about 157,350 square feet (approximately 4 acres) in size and is located immediately west of the ISFSI site. This area, which was previously developed as an asphalt and gravel paved parking lot, was not substantially changed by the development with the exception of minor grading and drainage improvements. Existing grades within the Equipment Laydown Area range from about Elevation 32 to about Elevation 22 and slope to the east-southeast.

The Soil Placement Area, which was used in the past for equipment laydown by Amtrak and the plant, consists of a gravel and dirt surface. The area is abutted to the south by Amtrak train rails, to the west by the asphalt-paved Millstone access road and to the north by an existing ball field. The area for excess soil placement is approximately 5-acres in size.

## **2.2 CONSTRUCTION**

The ISFSI pad and approach apron, constructed during Phase I to support the 19 Phase I HSMs, covers an area of approximately 12,000 square feet (approximately 0.3 acre). Most of the site work required for full build-out was performed during Phase I, in order to minimize the extent of construction required in the future. The portion of the ISFSI site not covered with concrete pads or aprons during Phase I was graded and covered with a gravel surface.

The Phase I construction generally included the following:

1. Site preparation, including stripping of existing topsoil and pavement within the ISFSI area;
2. Removal and/or abandonment of existing drainage utilities;
3. Re-grading within the limits of the site;
4. Over-excavation and replacement of soil beneath the concrete pads to improve the soil dynamic properties (and resultant seismic response);
5. Construction of a concrete retaining wall at the northeast corner of the ISFSI site. The wall is approximately 350 feet in length and range in height from about 1 foot to 6 feet;
6. Construction of approximately 12,000 square feet of concrete pad and apron;
7. Construction of new drainage structures;
8. Construction of approximately 500 feet of asphalt-paved roadway, for the new haul path; and
9. Construction of new protected area security fencing.

During the Phase I construction, the formerly existing drainage structures within the proposed ISFSI site were removed. The existing drainage structures located within the Equipment Laydown Area were abandoned in-place. We understand that the principal components of the drainage improvements constructed during Phase I included:

1. A new trunkline along the existing Access Road, which conveys stormwater from approximately 14 acres of the contributory drainage area located upgradient of the ISFSI site. Catch basins were constructed along this trunkline to intercept flows at various points.
2. An approximately 210 feet long trench drain within the concrete aprons located west of the HSMs constructed during Phase I
3. Two new catch basins (CB#3 and CB#4) within the Equipment Laydown Area and two new catch basins (CB#7 and CB#8) within the ISFSI site. A temporary catch basin (CB#9A) was also constructed within the ISFSI site to help drain the site. This catch basin will be removed during subsequent phases of construction.
4. The trench drain and catch basins discharge to a second trunkline which extends along the southern and eastern portions of the ISFSI site.
5. Drainage Manholes to connect the catch basins to the trunk lines and at various sections of the trunklines.
6. The trunklines join at a manhole located east of the ISFSI site. A 30-inch diameter RCP conveys the water from this manhole to an outlet located at an existing permitted outlet (current outlet designation No. DSN 011).
7. Lowering of the permitted outlet invert by about 2 feet, from approximately Elevation 13 to Elevation 11.

Earthwork for the Phase I construction included excavation to achieve proposed grades, re-grading, over-excavation of some existing material considered unsuitable for foundation support, replacement with a stable backfill material or concrete, and import of clean structural fill. Excess or natural unsuitable material generated during construction was placed in the designated Soil Placement Area. Topsoil, excavated soil and boulders were relocated to the Soil Placement Area.

Approximately 550 cubic yards of clean structural fill and 600 cubic yards of gravel/crushed stone (for a total amount of 1,150 cubic yards) was imported during Phase I to provide a sound base for the pad, apron and new haul path. Construction of the Phase I pads and aprons required placement of approximately 1,500 cubic yards of reinforced, structural concrete.

As noted above, earthwork included excavation to achieve the proposed site grades, as well as over-excavation and replacement of soil beneath the pads to improve seismic response. The soil beneath the pads was over-excavated to bedrock and replaced with low strength, non-structural concrete or stable backfill material.

Construction activities for the next (and final) project phase would include:

1. Additional excavation of soil for construction of additional concrete pads and aprons;
2. Modification of some of the drainage structures constructed during Phase I;
3. Addition of 15-ft of bottom width along the entire western portion of the ISFSI apron to allow for easier access by the HSM transporter;
4. Construction of the additional concrete pads and aprons; and
5. Delivery and assembly of the HSMs.

The personnel fence along the western portion of the site will have to be moved approximately 15 feet west to accommodate the additional 15-ft of bottom width.

Full build-out would generate about 7,000 cubic yards of additional excess material that would be relocated to the Soil Placement Area. An additional, approximately 5,000 cubic yards of concrete would also be required to achieve full build-out.

Soil generated during construction and brought to the Soil Placement Area will be placed in controlled lifts that match the existing ground contours. The area will be loamed and hydro seeded after construction.

### **2.3 PROPOSED DRAINAGE IMPROVEMENTS**

The proposed drainage improvements are detailed on the revised site plans titled “Revisions to Original Design, Independent Spent Fuel Storage Installation (ISFSI). Dominion Nuclear Connecticut Inc., Waterford, Connecticut” and dated March 2012.

Proposed Drainage Improvements which is the focus of this revised drainage report include:

1. Construction of three (3) new catch basins within the ISFSI site to drain the concrete pads and aprons;
2. Replacement of one drainage manhole (DMH#5) with a fourth new catch basin;
3. Construction of one (1) drainage manhole at the northern end of the ISFSI site;
4. Reconstruction of a 128-foot long 15-inch reinforced concrete pipe (RCP) on the north-western end of the ISFSI site;
5. Replacement of a 168-foot 15-inch RCP on the south-western portion of the ISFSI site with a 168-foot long 21-inch RCP;
6. The new catch basins and drainage manhole will be connected to the drainage network at the ISFSI site using 12-inch and 21-inch diameter reinforced concrete pipes as shown on the site plans.

These are discussed in detail in Section 4.



### **3.0 PRE-CONSTRUCTION DRAINAGE CONDITIONS**

#### **3.1 SURFICIAL SOIL AND SUBSURFACE CONDITIONS**

As noted above, all components of the project, including the ISFSI site, the haul path, the Equipment Laydown Area and the Soil Placement Area, are located on upland portions of the Millstone property that have been previously disturbed and developed. According to the Soil Conservation Service map (ref. Soil Conservation Services, Soil Survey of New London County, Connecticut), surficial soils at the ISFSI site, the Equipment Laydown Area and the Soil Laydown Area consist of Urban Land (Ub), consistent with the developed nature of the area and the presence of the shallow fill.

The geology at Millstone consists typically of glacial till overlying bedrock of the Monson Gneiss and Westerly Granite formations. At the southwestern portion of the Millstone peninsula, glacial stream deposits overlay the bedrock, and at the southern tip of the peninsula artificial fill is present. A 2002 geotechnical study of the proposed ISFSI site (ref. Geotechnical Study, Dry Storage Project, Millstone Nuclear Power Plant, by Dr. Clarence Welti, dated December 2002) indicates that bedrock is encountered at elevations ranging from about Elevation 7 to Elevation 14.5, corresponding to depths of about 6.5 feet to 28 feet below existing grade. The glacial till typically consists of a well-graded, poorly sorted sand and gravel with about 10 to 30 percent fine-grained soil (silt). One to 2 feet of sand fill is present throughout the area, above the glacial till.

#### **3.2 DRAINAGE PATTERNS**

Based on the site grades, drainage patterns and drainage structures, the ISFSI site is located within a contributory drainage area that is approximately 24 acres in size. This drainage area is comprised of developed upland areas, some wooded low-lying areas, a pond and the ISFSI site. The ISFSI site is located within an area previously developed as a parking lot, and is at the southern, downgradient portion of the drainage area. Surface runoff within the contributory drainage area flows in a general northwest to southeast direction.

The pre-construction drainage characteristics further subdivide this area into four sub-areas (referenced in the report as Sub-Areas 1 through 4). The locations of the drainage sub-areas are indicated on Figure 2. Sub-Area 1 is a small (approximately 3 acre) low-lying area with no outlet, which provides temporary ponding and storage of stormwater. Sub-Area 2 is a larger (approximately 11 acre) wetland and pond area. Sub-Area 2 has an outlet at its southern end, which connects to an existing 30-inch diameter RCP trunkline. Sub-Area 3 is about 8 acres in size and previously consisted principally of a parking lot. The ISFSI site is located in Sub-Area 3. Stormwater within Sub-Area 3 was conveyed as sheet flow to shallow concentrated flow until intercepted by one of seven catch basin structures located throughout the parking lot. Once collected in these catch basins, storm water was conveyed to the existing 30-inch diameter RCP trunkline. The 30-inch diameter trunkline discharges at the permitted outlet located east of the ISFSI site (No. DSN 011). The outlet discharges to a drainage swale, which in turn discharges to a freshwater pond located about 250 feet east of the proposed ISFSI site. Stormwater at the fourth sub-area (Sub-Area 4),

which is located at the southeast corner of Sub-Area 3 and is about 2 acres in size, is conveyed via sheet run-off toward the southeast portion of the Millstone property.

As discussed in Section 2.3, the drainage improvements constructed during Phase I included the construction of a new trunkline along the Access Road to convey flow from Sub-Area 2 to the permitted outlet east of the ISFSI site. Flow intercepted by the catch basins outside the ISFSI site and the Equipment Laydown area discharge to this trunkline. Flow intercepted by catch basins within the ISFSI site and the Equipment Laydown Area discharge to a second trunkline located along the southern and eastern portions of the ISFSI Site. The two trunklines join at a common manhole located east of the ISFSI site.

It appears that during the design storms considered in this study (up to the 100-year storm), stormwater remains ponded within Sub-Area 1 and does not contribute to flow to the 30-inch trunkline; however, it may contribute during larger storm events.

### **3.3 DRAINAGE CALCULATIONS - PRE-CONSTRUCTION CONDITION**

GZA estimated the volume and peak rates of runoff, emanating from the contributory drainage area, under various conditions, including the 24-hour, 2-, 10-, 25-, and 100-year storms. The design outlet point for the hydrologic analysis was the outfall (No. DSN 011).

Inflow hydrographs developed by GZA for the various frequency storms were initially generated in 2003 using the U.S. Army Corps of Engineers HEC-1 Flood Hydrograph Package computer program. Incremental rainfall input to the HEC-1 simulation model was based on the National Resource Conservation Services' (NRCS), Type III, 24-hour duration distribution pattern. Total rainfall depths for southeastern Connecticut were obtained from the State of Connecticut Drainage Manual, originally developed by Weiss (USGS, 1983). Storm hydrographs created within HEC-1, were based on NRCS Dimensionless Unit Hydrograph theory. Resultant flood hydrographs for each sub-area were combined at the design outlet point to produce composite flood hydrographs for the site, for the various storm frequencies previously noted. The runoff from the approximately 11-acre Sub-Area 2 to the pond was hydrologically routed to account for the natural storage characteristics of the pond, which attenuated the peak discharge by about 30 percent. The results of these rainfall/runoff simulations indicate that runoff from the approximately 3.0-acre Sub-Area 1 drains to an isolated low lying area just west of the Millstone access road and does not contribute surface runoff to the existing 30-inch diameter RCP trunkline during the design storms considered. Combined peak rates of runoff at the design point were 19, 33, 39, and 53 cubic feet per second (cfs) for the 2-, 10-, 25-, and 100-year storms, respectively. These inflow hydrographs have been updated as part of this revised report using the Army Corps of Engineers HEC-HMS computer program, which has superseded HEC-1. Inputs to the HEC-HMS model are identical to the inputs to the HEC-1 model. Results from the HEC-HMS model are the same as those from the HEC-1 model. The updated results for each sub-area are summarized in **Table 1**. HEC-HMS input and output summaries for the existing condition analyses are presented in **Appendix B**.

The hydraulic capacity of the existing trunk line drainage system (completed as part of Phase I construction in 2004) was also estimated by GZA using the StormCAD<sup>®</sup> engineering software package. The StormCAD<sup>®</sup> program computes the hydraulic grade line profile along a specified drainage pipeline network using standard step backwater methodology. Energy (i.e. head) losses are computed based on user-specified pipe sizes, Mannings friction “n” factors, pipe slopes and also accounts for minor (i.e., “shock”) losses due to pipe size transitions, bends, and junction manhole structures. Assuming free discharge (i.e. critical depth) at the design outlet point, the full-flow capacity of the lower end of the trunk line system is approximately 50 cfs. StormCAD<sup>®</sup> results, including the layout and hydraulic profile of the existing drainage system, are presented in **Appendix C**.

## **4.0 PROPOSED FULL BUILD-OUT CONDITION**

### **4.1 DESIGN OBJECTIVES AND CRITERIA**

The objective of the proposed conditions hydrologic analysis was to evaluate the rainfall/runoff characteristics of the site under the proposed conditions described in earlier sections (full build-out conditions with the additional 15-ft of bottom width along the entire western apron of the ISFSI). Based on Connecticut Department of Transportation (ConnDOT)<sup>3</sup> and the Department of Environmental Protection (DEP)<sup>4</sup> design and guidance documents, and local ordinances, the hydraulic design for the structural components of the proposed drainage system was based on the 25-year storm. As discussed in Section 5.0 below, the drainage system has been designed utilizing appropriate structural Best Management Practices to improve the general storm water quality being discharged from the Site. This is primarily accomplished through the settling and capture of total suspended solids and other particulate matter, and by providing oil-water separation.

### **4.2 PROPOSED SITE CHARACTERISTICS AND DRAINAGE SYSTEM LAYOUT**

Several alternatives for the updated site drainage system layout were analyzed. Project goals included the following:

1. Generally maintain the existing drainage patterns;
2. Divert stormwater emanating from the upgradient portions of the drainage area away from the close proximity of the ISFSI, to minimize the potential for flooding during typical storm events;
3. Utilize the existing design outlet point;
4. Maintain a level, constant grade along the length of the HSM pads;
5. Efficiently drain water away from the pads and prevent ponding within the ISFSI site during typical storm events; and
6. Avoid locating drainage structures beneath the HSM pads.

---

<sup>3</sup> Connecticut Department of Transportation. Drainage Manual, 2000.

<sup>4</sup> 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, 2002.

An additional consideration in the drainage design is the grade of the ISFSI site. The ISFSI site is in a topographic depression. The ISFSI site grade is Elevation 21 while the grade of the surrounding vicinity ranges from Elevation 28 to Elevation 19. This means that the ISFSI site would generally accumulate runoff from adjacent areas that is not appropriately diverted.

To achieve these goals, GZA selected the approach described below. The installation of the ISFSI drainage structures has been phased to coincide with Millstone's fuel storage requirements. During Phase I, which was completed in 2004, the Equipment Laydown Area drainage system was fully constructed along with the reconstruction of the outlet. Within the ISFSI site, a concrete pad and concrete apron was constructed to store 19 HSMs. The section of trench drain collecting runoff from this pad and apron was installed during Phase I. As discussed in earlier sections, the drainage improvements completed during Phase I are:

1. Division of the drainage system into two trunklines, with one conveying runoff from the Sub-Areas 1 and 2 and a second system conveying runoff from the Equipment Laydown Area and ISFSI site. The overall existing site drainage patterns was maintained under the proposed conditions; runoff continues to generally travel from the northwest to the southeast.
2. The design outlet point remained at the same location. However, due to the hydraulic profile required to pass the design flow, the invert of the 30-inch diameter outlet at the railroad outlet was lowered from Elevation 13.0 to Elevation 11.0.
3. A trunkline to convey runoff from Sub-Areas 1 and 2 was constructed. The trunkline begins at a new manhole located east of Building 532, allowing stormwater to flow in an easterly direction adjacent to the Access Road. The new manhole was constructed to replace an older manhole at the same location. The trunkline crosses the Access Road where the road bends to the east. At this point, water in the trunkline was routed along the eastern shoulder of the Access Road and discharge at the existing outlet (No. DSN 011).
4. Two new catch basins were installed within the Equipment Laydown Area to take advantage of existing site grading, and to minimize potential ponding and flooding.
5. Structural Best Management Practices included sumped catch basins and riprap installation (energy dissipater) at the 30-inch discharge outlet.

As part of the proposed modifications, GZA proposes the following drainage approach to complete the drainage network at the ISFSI site:

1. In addition to the constructed 210-foot long trench drain at the Phase I ISFSI, four new catch basins will be constructed within the concrete aprons at the western-most

end of the ISFSI site to intercept runoff from the concrete pads and aprons. Two of the four catch basins will be used to intercept runoff from the northern portion of the site and the other two will be used to intercept runoff from the southern portion of the site. One of the two catch basins intercepting flow from the southern portion of the site will be located at the present location of Drainage Manhole No. 5 (DMH#5). DMH#5 will be removed and replaced with the new catch basin.

2. The catch basins intercepting runoff from the northern portion of the ISFSI site will be connected to the existing catch basin at the northern end of the site (CB#7) using 12- inch diameter RCPs. A drainage manhole (sump) will be required at the northern end of the site to connect the 12-inch RCP to CB#7. The catch basin replacing DMH#5 will be connected to the existing DMH#6 using a 21-inch RCP. The existing 15-inch RCP connecting DMH#5 to DMH#6 will be removed. The second catch basin intercepting runoff from the southern portion of the ISFSI site will be connected to the existing DMH#7 at the southern end of the site using 12- inch diameter RCP.
3. The grade of the concrete aprons will remain at the existing grade (Elevation 21.0 ft) with the rims of the catch basins at elevation 20.9 ft to convey surface runoff to the inlets. The existing trench drain was constructed to maintain the level grade required within the ISFSI site. The adjacent apron areas were sloped (1 percent grade) at right angles to the pads and the trench drain grate (rim elevation 20.75 ft.). The trench drain discharges to a sump, and in turn to the trunk line located along the southern end of the ISFSI site.
4. The existing 128-foot long 15-inch RCP that connects the existing catch basin no.3 (CB#3) to the existing DMH#5 will be reconstructed at a different grade as shown of the revised site plans.
5. Structural Best Management Practices, including, but not limited to deep sump catch basins with hooded outlet pipes will be included in the design.

The ISFSI site construction has slightly modified the individual drainage sub-areas, as indicated on **Figure 3**. Additional detail related to site grading and drainage features are presented in the *Site Plans*.

#### **4.3 DRAINAGE CALCULATIONS – FULL BUILD-OUT CONDITION**

The hydrology of the proposed site condition was analyzed by GZA using the HEC-HMS program. The results are presented in **Appendix B**. The limits of the drainage sub-areas were modified slightly to reflect the change in grading and pipe rerouting. Other input variables including runoff potential (expressed as a Curve Number) and time of concentration, were adjusted based on minor changes to surface cover and shorter in-pipe travel times. Resultant peak rates of runoff for the various frequency storms are summarized in **Table 1**. The proposed conditions resulted in no appreciable change in peak

runoffs compared to the existing conditions. The partial construction of the ISFSI site in 2004 resulted in a minor (5 percent or less) increase in peak run-off. This increase is not appreciable, as it will not materially increase water surface profiles or flooding potential to the freshwater pond, into which the runoff ultimately discharges.

The hydrologic and hydraulic analysis of the drainage pipe network in the access roadway and ISFSI Area was developed by GZA using StormCAD<sup>®</sup>. As much as was practically possible, the drainage system modifications were designed to operate under open channel conditions (i.e. resultant 25-year design hydraulic grade line (HGL) set below the crown of pipe). Due to site grading and Phase I ISFSI as-built condition constraints, some pipe sections may experience pressure flow during transient peak flow conditions during the 25-year design storm. This does not compromise the drainage system nor present an unacceptable risk to the ISFSI. Per design guidance by the Federal Highway Administration (FHWA)<sup>5</sup>, “pipes may be designed to operate under pressure so long as the hydraulic gradient is below the intake lip of the inlet which may be affected”. The FHWA recommended allowance between the hydraulic grade line and the intake lip is 0.75 feet. The StormCAD<sup>®</sup> computations for the proposed drainage system are provided in **Appendix C**.

## **5.0 POST CONSTRUCTION STORM WATER MANAGEMENT**

Post construction storm water management will include the use of Best Management Practices (BMPs). BMPs are defined as “structural, non-structural, and managerial techniques that prevent or reduce non-point source pollutants from entering receiving waters.” Phase I ISFSI drainage structures included the BMPs discussed below. The full-build out ISFSI will also utilize these BMPs, discussed below.

As noted previously, upon completion of construction, the ISFSI site and related drainage improvements will be incorporated into Millstone’s existing “*General Permit for the Discharge of Stormwater Associated with Industrial Activities*”. Managerial requirements will be established in that permit.

### **5.1 CATCH BASINS**

Deep sump catch basins will be used at each of the inlets to the storm water collection system. Deep sump catch basins are designed to remove trash, debris, and some sediment and oil from storm water runoff. They operate as modified catch basins, with inverted discharge pipes or hoods and sumps which are typically four times the diameter of the inflow pipe. Storm water may only exit the catch basin through the bottom opening of the pipe. A permanent pool of water remains in the sump. Oil and grease float on the water surface. During storms, the discharge pipe becomes submerged as the water level in the sump increases. The floating oil and grease are not discharged, but rather continue to float on top of the water surface. Some sediment removal is achieved by settling within the

---

<sup>5</sup> Design of Urban Highway Drainage, FHWA-TS-79-225, August 1979.

deep sump. With proper maintenance, deep sump catch basins with hooded outlets typically provide for 25 percent Total Suspended Solid (TSS) removal, on an average annual basis. Deep sump catch basins, when left unmaintained can however become a source of pollutants or a mosquito breeding habitat between rainfall events. They are also not effective in removing soluble or fine particles.

## **5.2 VELOCITY DISSIPATION**

Velocity dissipation devices are typically structurally lined aprons placed between storm water outfalls and a stable downstream channel. They prevent scour and minimize the potential for downstream erosion by reducing the velocity of concentrated storm water flows. Velocity dissipation devices are not anticipated to be needed during the final construction phase. Drainage system improvements during Phase I included the provision of additional velocity dissipation measures at the 30-inch outfall, including a headwall and riprap outlet protection. A sand filter blanket and geotextile was added to protect the material under the riprap from possible scouring.

## **6.0 EROSION AND SEDIMENT CONTROLS**

The *Revised Site Plans* include a Soil Erosion and Sediment Control plan. The following describes the proposed erosion and sediment control measures to be implemented during construction.

### **6.1 EROSION AND SEDIMENT CONTROL MEASURES**

While the Phase I construction required clearing and disturbance of less than 3 acres in area, it involved extensive earthwork. Cuts of up to about 8 feet were required to achieve the proposed site grades. This involved the construction of earth slopes at the north and west portion of the ISFSI site. In addition, over-excavation to about Elevation 10 was required to remove unsuitable soils beneath the concrete pads. Approximately 25,000 to 30,000 cubic yards of soil was excavated. A portion of this soil was placed at the Soil Placement Area. The remainder was temporarily stockpiled and replaced within the ISFSI site. The final phase of construction will include some soil excavation in addition to removal and stockpiling of the existing gravel on the ISFSI site. Similar to what was done during Phase I, excess soil will be placed at the Soil Placement Area. Similar erosion and sediment control concerns encountered during the Phase I construction are expected during the final construction (full build-out) phase. These erosion and sediment control concerns include the following:

1. Erosion of the earth slopes, the cleared ISFSI site and soil / gravel stockpiles. Unless properly managed, sediment from this erosion would run off to other areas of the ISFSI site.
2. Soil excavation and stockpiling, and related activities, will generate significant dust if not adequately controlled.

3. Placement of soil at the Soil Placement Area. Existing grades within this area slope to the east-southeast towards a stream and wetlands area.

The principal pollution concerns include:

1. Temporary on-site storage of petroleum products and fueling of construction equipment.
2. On-site storage of cement.

The following erosion and sediment control techniques will be used during the final phase of the ISFSI construction and will be employed to minimize erosion and transport of sediment to resource areas, and to protect against pollution from hazardous materials during subsequent earthwork and final construction phase of the project. Adjacent or nearby resources areas include inland wetlands located northeast and east of the ISFSI site, and the freshwater pond located east of the ISFSI site.

#### **6.1.1 Site Clearing and Excavation**

Prior to any site clearing activities, silt fence and hay bale barriers will be placed around the perimeter of the ISFSI site. Clearing will be limited to those areas necessary to complete the proposed work. This generally includes the limits of the ISFSI site, localized areas of the Equipment Laydown Area and areas where utility trenching will occur. Disturbed areas will be kept to a minimum.

#### **6.1.2 Hay Bale / Silt Fence Barriers**

Hay bale/silt fence barriers will be placed to trap sediment transported by runoff before it reaches the drainage system or leaves the construction site, in addition to areas where high runoff velocities or high sediment loads are expected. The silt fences and hay bale barrier are to be replaced as determined by periodic field inspections.

#### **6.1.3 Catch Basin Inlet Protection**

Newly constructed and existing catch basins will be protected with hay bale barriers (where appropriate) or silt sacks throughout construction.

#### **6.1.4 Construction Site Entrance / Exit**

To reduce the tracking of sediment from the construction site onto other areas of the Millstone Property and to public ways, as well as the production of airborne dust, stabilized construction entrances/exits will be established at all permanent unimproved construction staging areas, including the Soil Laydown Area. The entrances/exits will consist of a 2- to 3-inch thick pad of crushed stone underlain with a filter cloth or a bituminous concrete apron and will be constructed on level ground.



### **6.1.5 Slope Protection**

Exposed soil slopes will be especially susceptible to erosion. Temporary sediment protection from unprotected slopes will be provided using silt fence/hay bale installations. Should erosion become excessive the Contractor will install matting such as straw, jute, wood fiber, and/or plastic netting. The matting provides cushioning against splash erosion from raindrop impact, does not generate high velocity runoff, captures a great deal of sediment, and will provide long-term protection. Permanent slope protection will be provided by covering the slopes with a geotextile and crushed stone.

### **6.1.6 Temporary Sediment Basins**

The contractor will be allowed to utilize temporary sediment basins, if needed. The basins will be designed either as excavations or bermed storm water detention structures (depending on grading) that will retain runoff for a sufficient period of time to allow suspended soil particles to settle out prior to discharge. These temporary basins will be located based on construction needs as determined by the contractor in consultation with the DNC's Project Manager. A perforated riser surrounded by a crushed stone filter will be typically used to control discharge from the basin. Points of discharge from sediment basins will be stabilized to minimize erosion.

### **6.1.7 Stockpiled Materials**

Any stockpiles created during construction activities will be surrounded with hay bales and silt fence, where possible. Other alternatives utilized may include curb inlet filters or gravel filter berms laid around the perimeter of the stockpile. Stockpiles will be covered prior to inclement weather, graded to shed water, and covered at the end of each workday with plastic.

### **6.1.8 Soil Placement Area**

Soil deposited at the Soil Placement Area will be placed in controlled lifts and graded to drain. Establishment of a permanent vegetative cover was established by loaming and hydro-seeding at the end of Phase I. Establishment of a permanent vegetative cover will be established by loaming and hydro-seeding at the end of any later construction phases.

### **6.1.9 Winter Stabilization**

If construction is temporarily discontinued during winter months, all areas disturbed areas will be stabilized with straw mulch, hydro-seeding, mulching, or erosion control blankets as necessary to control erosion.

### **6.1.10 Outlet Protection**

Permanent outlet protection, consisting of riprap channel lining, was provided at the storm water outlet to reduce storm water velocities and enhance sedimentation prior to discharge to the adjacent pond.

### **6.1.11 Dust Control**

Standard dust control measures, including use of water trucks, misting and placement of calcium chloride will be used.

### **6.1.12 Construction Dewatering**

Where possible, the wastewater discharge from construction dewatering is to be infiltrated into the ground in temporary sediment/infiltration basins. The existing soils may have limited infiltration capacity. Construction dewatering wastewater discharged to a surface water body will be pre-treated for sediment removal by residing in a fractionation/sedimentation tank or sediment basin prior to discharge.

### **6.1.13 Equipment Fueling**

Equipment fueling and other activities including petroleum, oil and other potentially hazardous substances will be performed at a pre-approved, designated area with appropriate spill prevention and control measures. This area will be located on an asphalt paved surface, away from catch basins and other drainage structures. Portable secondary containment will be used, and sorbent materials will typically be placed around the perimeter of the fueling area, during all fueling activities. Non-liquid hazardous materials (e.g., cement) will be stored in a protected area and covered.

## **6.2 INSPECTION AND MAINTENANCE**

Areas disturbed by the construction, including construction entrances, will be inspected to ensure that the Erosion and Sediment Control measures are correctly installed and maintained. Inspections of the active work area will occur weekly and after every significant precipitation event (exceeding ½-inch precipitation). Inspection reports will be maintained.

## **6.3 SEQUENCE OF GRADING AND CONSTRUCTION ACTIVITIES**

The following provides a summary of the proposed sequence of grading and construction activities and the installation of the erosion and sediment control measures for proposed drainage modifications.

1. Install stabilized construction entrance and exit as needed
2. Install perimeter hay bales and silt fence as necessary
3. Provide catch basin inlet protection at existing catch basins
4. Perform stripping (removal of gravel surface) at the ISFSI site
5. Provide protection for all stockpiles
6. Prepare temporary sedimentation basins, as may be required
7. During stripping and excavation, install berms to collect site runoff as required.
8. Implement other dewatering control measures (e.g. frac tanks w/filters,) as required
9. Begin earthwork within the ISFSI Site
10. In areas where water flow is concentrated, install crushed stone or hay bale check dams
11. Upon completion of earthwork within the ISFSI site, install remaining drainage structures
12. Provide catch basin inlet protection at newly constructed catch basins
13. Construct concrete pads and aprons, and gravel surface within the ISFSI Site
14. Complete grading
15. Remove accumulated sediment from basins and other sediment control devices
16. Perimeter erosion control will remain in place until permanent stabilization has been achieved
17. Loam and seed the Soil Placement Area

## **TABLES**

Table 1  
**Rainfall / Runoff Modeling Results**

**Results of Existing Conditions Analysis**

Drainage area	Peak Flow (cfs)			
	2-year storm	10-year storm	25-year storm	100-year storm
Sub-Area 1	2	4	5	6
Sub-Area 2	4	12	16	24
Sub-Area 3	13	22	25	32
Sub-Area 4	4	6	7	9
Site	19	33	39	53

Note: Peak flows for site represent combined hydrographs. Individual drainage areas represent unrouted peak flows

**Results of Proposed Conditions Analysis**

Drainage area	Peak Flow (cfs)			
	2-year storm	10-year storm	25-year storm	100-year storm
Sub-Area 1	2	4	5	6
Sub-Area 2	4	12	16	24
Sub-Area 3	16	24	29	37
Sub-Area 4	2	4	4	5
Site	20	34	40	54

Note: Peak flows for site represent combined hydrographs. Individual drainage areas represent unrouted peak flows.

**Comparison of Existing and Proposed Conditions Results**


	Peak Flow (cfs)			
	2-year storm	10-year storm	25-year storm	100-year storm
Existing Conditions	19	33	39	53
Proposed Conditions	20	34	40	54
Change	1	1	1	1

Table 2  
**Combined Pipe/Node Report**


Upstream Node	Downstream Node	Section Size	Mannings n	Full Capacity (cfs)	Total System Flow (cfs)	Average Velocity (ft/s)	Length (ft)	Constructed Slope (ft/ft)	Upstream Inlet Rational Flow (cfs)	Upstream Ground Elevation (ft)	Downstream Ground Elevation (ft)	Upstream Invert Elevation (ft)	Downstream Invert Elevation (ft)	Upstream Cover (ft)	Downstream Cover (ft)
CB#1	DMH#1	30 inch	0.013	29.07	17.06	5.86	342	0.005	5.06	30.5	33	24.87	23.82	3.13	6.68
DMH#1	DMH#2	30 inch	0.013	44.59	17	8.14	192	0.012	N/A	33	30.1	23.82	20	6.68	7.6
DMH#2	DMH#3	30 inch	0.013	29	16.94	5.14	218	0.005	N/A	30.1	27.5	20	18.9	7.6	6.1
CB#2	DMH#3	15 inch	0.013	10.21	6	7.99	80	0.025	6	26.5	27.5	22	20	3.25	6.25
DMH#3	DMH#4	30 inch	0.013	58	21.73	10.01	329	0.020	N/A	27.5	19.7	18.9	12.32	6.1	4.88
CB#6	DMH#4	15 inch	0.013	4.57	4.31	4.56	15	0.005	4.31	19.5	19.7	15.25	15.18	3	3.27
I-12	I-11	12 inch	0.013	2.53	1.26	1.6	195	0.005	1.26	20.9	20.9	17.84	16.86	2.06	3.04
I-11	J-10	12 inch	0.013	2.55	2.3	2.93	45	0.005	1.2	20.9	20.9	16.86	16.63	3.04	3.27
J-10	CB#7	12 inch	0.013	2.52	2.28	2.91	50	0.005	N/A	20.9	20.9	16.63	16.38	3.27	3.52
CB#7	CB#8	12 inch	0.01	3.27	2.74	3.48	168	0.005	2.02	20.9	20.9	16.38	15.54	3.52	4.36
CB#8	DMH#12	12 inch	0.01	3.27	3.12	3.97	168	0.005	0.52	20.9	20.9	15.54	14.7	4.36	5.2
DMH#12	DMH#10	15 inch	0.013	11.88	3.04	2.48	21	0.034	N/A	20.9	20.9	14.47	13.76	5.18	5.89
CB#3	I-13	15 inch	0.013	4.57	4.48	4.18	128	0.005	4.48	24.5	24.2	17.64	17	5.61	5.95
I-13	DMH#6	21 inch	0.013	11.2	6.48	2.69	168	0.005	N/A	20.9	21	16.91	16.07	2.24	3.18
CB#4	DMH#6	15 inch	0.013	4.57	4.55	3.71	6	0.005	4.55	20.7	21	16.45	16.39	3	3.36
DMH#6	DMH#15	21 inch	0.013	11.2	8.42	3.5	153	0.005	N/A	21	21	16.07	15.3	3.18	3.95
I-14	DMH#15	12 inch	0.013	3.09	1.15	1.46	19	0.008	1.15	20.9	21	15.5	15.35	4.4	4.65
DMH#15	DMH#7	21 inch	0.013	11.88	11.97	4.97	16	0.005	N/A	21	20.9	15.3	15.21	3.95	3.94
DMH#7	DMH#8	21 inch	0.013	11.2	11.96	4.97	84	0.005	N/A	20.9	20.9	15.21	14.79	3.94	4.36
DMH#13	DMH#8	15 inch	0.013	5.9	2.02	1.65	6	0.008	2.02	20.75	20.9	15.75	15.7	3.75	3.95
DMH#8	DMH#9	24 inch	0.013	9.05	13.59	4.33	50	0.002	N/A	20.9	20.9	15.05	14.97	3.85	3.93
DMH#9	DMH#10	24 inch	0.013	11.19	13.56	4.32	237	0.002	N/A	20.9	20.9	14.97	14.39	3.93	4.51
DMH#10	DMH#11	24 inch	0.013	10.12	16.22	5.79	40	0.002	N/A	20.9	20.5	14.39	14.31	4.51	4.19
CB#5	DMH#11	12 inch	0.013	2.52	1.51	3.44	10	0.005	1.51	20.5	20.5	16.5	16.45	3	3.05
DMH#11	DMH#4	30 inch	0.013	29.22	17.42	3.66	65	0.005	N/A	20.5	19.7	12.65	12.32	5.35	4.88
DMH#4	O-1	30 inch	0.013	44.47	39.07	9.79	91	0.012	N/A	19.7	16.5	12.07	11	5.13	3

## FIGURES





**MILLSTONE POWER STATION ISFSI**



PROJ. MGR.: DML  
 DESIGNED BY: KDH  
 REVIEWED BY: PHB  
 OPERATOR: KDH  
 DATE: 12 -20 -11


LOCUS MAP

INDEPENDENT SPENT FUEL STORAGE INSTALLATION

JOB NO.  
 171138

FIGURE NO.  
**1**





JOB NO. 171138.00  
 FIGURE NO. 2

MILLSTONE POWER PLANT/DNC  
 WATERFORD, CONNECTICUT  
 PRE-CONSTRUCTION CONDITIONS


SCALE: 1" = 150'  
 0 75' 150' 300'

PROJ MGR: DML  
 DESIGNED BY: KDH  
 REVIEWED BY: PHB  
 OPERATOR: KDH  
 DATE: 01/10/12  
 GZA Geotechnical, Inc.

- NOTES**
1. BASE PLAN TAKEN FROM A MAP ENTITLED "ISFSI PROJECT EXISTING DRAINAGE," DATED 11-27-02 AND PROVIDED ELECTRONICALLY BY ENERCON SERVICES, INC. OF MOUNT ARLINGTON, NEW JERSEY.
  2. DRAINAGE BASIN DELINEATION BASED ON TOPOGRAPHIC SURVEY AND SITE VISIT PERFORMED ON DECEMBER 11, 2002 BY GZA PERSONNEL.

**LEGEND**

- DRAINAGE BOUNDARY
- STORM WATER CONDUIT



**NOTES:**  
 1. BASE PLAN TAKEN FROM A MAP ENTITLED "ISFSI PROJECT EXISTING DRAINAGE," DATED 11-27-02 AND PROVIDED ELECTRONICALLY BY ENERCON SERVICES, INC. OF MOUNT ARLINGTON, NEW JERSEY.  
 2. DRAINAGE BASIN DELINEATION BASED ON TOPOGRAPHIC SURVEY AND SITE VISIT PERFORMED ON DECEMBER 11, 2002 BY GZA PERSONNEL.

**LEGEND:**  
 ——— DRAINAGE BOUNDARY  
 ——— STORM WATER CONDUIT

**APPENDIX A  
GZA LIMITATIONS**

## LIMITATIONS

1. This Drainage Report (“Report”) has been prepared by GZA GeoEnvironmental, Inc. (“GZA”) for the exclusive use of Dominion Nuclear Connecticut, Inc. for specific application for an Independent Spent Fuel Storage Installation (“ISFSI”) at the Millstone Power Station located in Waterford, Connecticut, to the Connecticut Siting Council, in accordance with generally accepted engineering practices. No other warranty, express or implied, is made.
2. The observations described in the Report were made under the conditions stated herein. The conclusions presented in the Report were based solely upon the services described therein.
3. In preparing the Report, GZA has relied on certain information provided by Enercon Services, Inc. GZA did not attempt to independently verify the accuracy or completeness of all information reviewed or received during the course of this work.
4. In the event that any changes in the nature, design, or location of the drainage structures for the ISFSI Project are planned, the conclusions and recommendations contained in the Report shall not be considered valid unless the changes are reviewed and conclusions of the Report modified or verified by GZA.
5. It is recommended that GZA be retained to provide engineering services during construction of the drainage improvements for this project. This is to observe compliance with the design concepts, specifications, and recommendations and to allow design changes in the event conditions differ from those anticipated prior to the start of construction.
6. In preparing this report, GZA has relied upon topographic survey data prepared by others and soil characteristics as reported by the National Resource Conservation Service (formerly known as the SCS). GZA did not independently verify the accuracy of that data.
7. GZA based the hydrologic analysis of existing conditions on the site plans made available to GZA as of the date of the Report. In the event that any other site changes are planned, the conclusions and recommendations contained in the Report shall not be considered valid unless the changes are reviewed and conclusions of the Report modified or verified by GZA.
8. The analysis presented is for the rainfall volumes and distributions stated herein. For storm conditions other than those analyzed, the response of the sites drainage network has not been analyzed.

**APPENDIX B**  
**RESULTS OF HYDROLOGIC (HEC-HMS) ANALYSES**

**CURVE NUMBERS**

**CURVE NUMBER CALCULATIONS**  
Pre-Construction Conditions

Sub-Area 1 - Small Pool

Cover		Soil Group	CN	Product
Impervious Cover	24826	C	98	2432948
Woods, Good Condition	104143	C	70	7290010
Total	128969			9722958
Weighted CN				76

Sub-Area 2 - Large Pool Drainage Area

Cover	Area	Soil Group	CN	Product
Impervious Cover	51619	C	98	5058662
Open space, Fair Conditon	193945	A	49	9503305
Woods, Good Condition	228291	C	70	15980370
Total	473855			30542337
Weighted CN				65

Sub-Area 3 - Parking Areas to Storm Drain

Cover		Soil Group	CN	Product
Impervious Cover	105050	Ud	98	10294900
Gravel	231288	Ud	85	19659480
Grass, Fair Condition	0	Ud	69	0
Total	336338			29954380
Weighted CN				90

Sub-Area 4 - Disconnected Parking Area

Cover		Soil Group	CN	Product
Impervious Cover	38000	Ud	98	3724000
Gravel	44727	Ud	85	3801795
Grass, Good Condition	0	Ud	61	0
Total	82727			7525795
Weighted CN				91

**CURVE NUMBER CALCULATIONS**  
Existing Conditions

Sub-Area 1 - Small Pool

Cover		Soil Group	CN	Product
Impervious Cover	24826	C	98	2432948
Woods, Good Condition	104143	C	70	7290010
Total	128969			9722958
Weighted CN				76

Sub-Area 2 - Large Pool Drainage Area

Cover	Area	Soil Group	CN	Product
Impervious Cover	51619	C	98	5058662
Open space, Fair Conditon	193945	A	49	9503305
Woods, Good Condition	228291	C	70	15980370
Total	473855			30542337
Weighted CN				65

Sub-Area 3 - Parking Areas to Storm Drain

Cover		Soil Group	CN	Product
Impervious Cover	185000	Ud	98	18130000
Gravel	184792	Ud	85	15707320
Grass, Fair Condition	0	Ud	69	0
Total	369792			33837320
Weighted CN				92

Sub-Area 4 - Disconnected Parking Area

Cover		Soil Group	CN	Product
Impervious Cover	24668	Ud	98	2417464
Gravel	24605	Ud	85	2091425
Grass, Good Condition	0	Ud	61	0
Total	49273			4508889
Weighted CN				92



**CURVE NUMBER CALCULATIONS**  
Proposed Conditions

Sub-Area 1 - Small Pool

Cover		Soil Group	CN	Product
Impervious Cover	24826	C	98	2432948
Woods, Good Condition	104143	C	70	7290010
Total	128969			9722958
Weighted CN				76

Sub-Area 2 - Large Pool Drainage Area

Cover	Area	Soil Group	CN	Product
Impervious Cover	51619	C	98	5058662
Open space, Fair Conditon	193945	A	49	9503305
Woods, Good Condition	228291	C	70	15980370
Total	473855			30542337
Weighted CN				65

Sub-Area 3 - ISFI Sub-Drainage Area

Cover		Soil Group	CN	Product
Impervious Cover	194700	Ud	98	19080600
Gravel	175092	Ud	85	14882820
Grass, Fair Condition	0	Ud	69	0
Total	369792			33963420
Weighted CN				92

Sub-Area 4 - Disconnected Parking Area


Cover		Soil Group	CN	Product
Impervious Cover	24668	Ud	98	2417464
Gravel	24605	Ud	85	2091425
Grass, Good Condition	0	Ud	61	0
Total	49273			4508889
Weighted CN				92

## **HMS OUTPUT FILES**



HEC-HMS

**Project : Millstone**  
Basin Model : 2YR POST  
Jan 18 12:14:02 EST 2012



Project: Millstone  
Simulation Run: 2YR POST Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	2YR POST
End of Run:	02Jan1999, 04:00	Meteorologic Model:	2yr post
Compute Time:	19Dec2011, 09:25:40	Control Specifications:	2yr post

Volume Units: IN

#### Computed Results

Peak Outflow :	20.3 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:24
Total Outflow :	1.36 (IN)		

Project: Millstone Simulation Run: 2YR POST

Start of Run: 01Jan1999, 00:00 Basin Model: 2YR POST  
End of Run: 02Jan1999, 04:00 Meteorologic Model: 2yr post  
Compute Time: 19Dec2011, 09:25:40 Control Specifications: 2yr post

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	4.3	01Jan1999, 12:30	0.70
SA1	0.0046	1.8	01Jan1999, 12:42	1.23
SPOOL	0.0046	0.0	01Jan1999, 00:00	0.00
COM1	0.0216	4.3	01Jan1999, 12:30	0.55
LPOOL	0.0216	4.1	01Jan1999, 12:36	0.54
SA3	0.0133	15.7	01Jan1999, 12:18	2.54
SA4	0.0018	2.3	01Jan1999, 12:18	2.54
COM	0.0367	20.3	01Jan1999, 12:24	1.36

2YR\_POST.basin

Basin: 2YR POST

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB #171138.00 2-YEAR  
PROPOSED CONDITION ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:04:38

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 95.69310344827586

Canvas Y: 262.4137931034483

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: -48.80344827586205

Canvas Y: 256.45517241379315

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: -10.072413793103436

Canvas Y: 213.25517241379313

2YR\_POST.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(2YR POST)  
Elevation-Storage Table: SPOOL(2YR POST)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 37.59655172413794  
Canvas Y: 171.54482758620694  
Downstream: LPOOL

End:

Reservoir: LPOOL

Canvas X: 52.400000000000006  
Canvas Y: 95.19999999999999  
Downstream: COM

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: LPOOL(2YR POST)  
Elevation-Storage Table: LPOOL(2YR POST)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 115.0586206896552  
Canvas Y: 158.88275862068969  
Area: 0.0133  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 92

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA4

Canvas X: 196.2448275862069  
Canvas Y: 147.71034482758623  
Area: 0.0018  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0

2YR\_POST.basin

Curve Number: 92

Transform: SCS

Lag: 9.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND

Canvas X: 118.78275862068968

Canvas Y: 56.09655172413795

End:

Basin Schematic Properties:

Last View N: 5000.0

Last View S: -5000.0

Last View W: -5000.0

Last View E: 5000.0

Maximum View N: 300.40000000000003

Maximum View S: 19.6

Maximum View W: 36.2

Maximum View E: 138.8

Extent Method: Elements

Buffer: 0

Draw Icons: Yes

Draw Icon Labels: Yes

Draw Map Objects: No

Draw Gridlines: No

Draw Flow Direction: No

Fix Element Locations: No

Fix Hydrologic Order: No


End:





HEC-HMS

**Project : Millstone**  
Basin Model : 2YR PRE  
Jan 18 12:15:54 EST 2012



Project: Millstone  
Simulation Run: 2YR PRE Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	2YR PRE
End of Run:	02Jan1999, 04:00	Meteorologic Model:	2yr pre
Compute Time:	19Dec2011, 09:26:30	Control Specifications:	2yr pre

Volume Units: IN

#### Computed Results

Peak Outflow :	19.4 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:24
Total Outflow :	1.30 (IN)		

Project: Millstone Simulation Run: 2YR PRE

Start of Run: 01Jan1999, 00:00 Basin Model: 2YR PRE  
End of Run: 02Jan1999, 04:00 Meteorologic Model: 2yr pre  
Compute Time: 19Dec2011, 09:26:30 Control Specifications: 2yr pre

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	4.3	01Jan1999, 12:30	0.70
SA1	0.0046	1.8	01Jan1999, 12:42	1.23
SPOOL	0.0046	0.0	01Jan1999, 00:00	0.00
COM1	0.0216	4.3	01Jan1999, 12:30	0.55
POOL1	0.0216	4.1	01Jan1999, 12:36	0.54
SA3	0.0121	13.4	01Jan1999, 12:18	2.35
COM2	0.0337	16.3	01Jan1999, 12:24	1.19
SA4	0.0030	3.7	01Jan1999, 12:18	2.45
COM	0.0367	19.4	01Jan1999, 12:24	1.30

2YR\_PRE.basin

Basin: 2YR PRE

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB #171138.00 2-YEAR  
EXISTING CONDITION ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:04:51

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 84.45358090185675

Canvas Y: 327.82281167108755

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: -64.91299734748011

Canvas Y: 329.71352785145893

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: -33.716180371352806

Canvas Y: 268.26525198939

2YR\_PRE.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(2YR PRE)  
Elevation-Storage Table: SPOOL(2YR PRE)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 12.606366047745354  
Canvas Y: 234.2323607427056  
Downstream: POOL1

End:

Reservoir: POOL1

Canvas X: 34.34960212201591  
Canvas Y: 175.62015915119363  
Downstream: COM2

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: POOL1(2YR PRE)  
Elevation-Storage Table: POOL1(2YR PRE)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 126.9946949602122  
Canvas Y: 229.50557029177722  
Area: 0.0121  
Downstream: COM2

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 90

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM2

Description: COMBINE HYDROGRAPHS TO ESTIMATE DISCHARGE FROM 30" DRAIN TO POND  
Canvas X: 69.6  
Canvas Y: 92.4  
Downstream: COM

End:

Subbasin: SA4

Canvas X: 172.3718832891247  
Canvas Y: 156.7129973474801  
Area: 0.0030  
Downstream: COM

2YR\_PRE.basin

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 91

Transform: SCS  
Lag: 9.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND  
Canvas X: 113.75968169761273  
Canvas Y: 50.83289124668431

End:

Basin Schematic Properties:


Last View N: 5000.0  
Last View S: -5000.0  
Last View W: -5000.0  
Last View E: 5000.0  
Maximum View N: 373.20000000000005  
Maximum View S: 16.8  
Maximum View W: 37.2  
Maximum View E: 112.80000000000001  
Extent Method: Elements  
Buffer: 0  
Draw Icons: Yes  
Draw Icon Labels: Yes  
Draw Map Objects: No  
Draw Gridlines: No  
Draw Flow Direction: No  
Fix Element Locations: No  
Fix Hydrologic Order: No

End:



HEC-HMS

**Project : Millstone**  
Basin Model : 10YR POST  
Jan 18 11:59:40 EST 2012



Project: Millstone

Simulation Run: 10YR POST Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	10YR POST
End of Run:	02Jan1999, 04:00	Meteorologic Model:	10yr post
Compute Time:	19Dec2011, 09:08:14	Control Specifications:	10yr post

Volume Units: IN

### Computed Results

Peak Outflow :	34.3 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:18
Total Outflow :	2.44 (IN)		



Project: Millstone Simulation Run: 10YR POST

Start of Run: 01Jan1999, 00:00 Basin Model: 10YR POST  
End of Run: 02Jan1999, 04:00 Meteorologic Model: 10yr post  
Compute Time: 19Dec2011, 09:08:14 Control Specifications: 10yr post

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	11.7	01Jan1999, 12:24	1.65
SA1	0.0046	3.7	01Jan1999, 12:42	2.45
SPOOL	0.0046	0.0	01Jan1999, 00:00	0.00
COM1	0.0216	11.7	01Jan1999, 12:24	1.30
LPOOL	0.0216	9.3	01Jan1999, 12:36	1.29
SA3	0.0133	24.8	01Jan1999, 12:18	4.09
SA4	0.0018	3.6	01Jan1999, 12:18	4.09
COM	0.0367	34.3	01Jan1999, 12:18	2.44

10YR\_POST.basin

Basin: 10YR POST

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB #171138.00 10-YEAR  
PROPOSED CONDITIONS ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:03:16

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 91.22413793103449

Canvas Y: 284.75862068965523

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: -42.84482758620689

Canvas Y: 285.5034482758621

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: -24.968965517241372

Canvas Y: 228.15172413793107

10YR\_POST.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(10YR POST)  
Elevation-Storage Table: SPOOL(10YR POST)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 18.975862068965526  
Canvas Y: 176.7586206896552  
Downstream: LPOOL

End:

Reservoir: LPOOL

Canvas X: 27.9137931034483  
Canvas Y: 114.19310344827588  
Downstream: COM

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: LPOOL(10YR POST)  
Elevation-Storage Table: LPOOL(10YR POST)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 83.77586206896554  
Canvas Y: 164.09655172413795  
Area: 0.0133  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 92

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA4

Canvas X: 149.2275862068966  
Canvas Y: 214.37241379310342  
Area: 0.0018  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0

10YR\_POST.basin

Curve Number: 92

Transform: SCS

Lag: 9.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND

Canvas X: 85.26551724137933

Canvas Y: 65.03448275862073

End:

Basin Schematic Properties:

Last View N: 5000.0

Last View S: -5000.0

Last View W: -5000.0

Last View E: 5000.0

Maximum View N: 300.40000000000003

Maximum View S: 19.6

Maximum View W: 36.2

Maximum View E: 138.8

Extent Method: Elements

Buffer: 0

Draw Icons: Yes

Draw Icon Labels: Yes

Draw Map Objects: No

Draw Gridlines: No

Draw Flow Direction: No

Fix Element Locations: No


Fix Hydrologic Order: No

End:



HEC-HMS

**Project : Millstone**  
Basin Model : 10YR PRE  
Jan 18 12:03:30 EST 2012



Project: Millstone  
Simulation Run: 10YR PRE Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	10YR PRE
End of Run:	02Jan1999, 04:00	Meteorologic Model:	10yr pre
Compute Time:	19Dec2011, 09:11:50	Control Specifications:	10yr pre

Volume Units: IN

### Computed Results

Peak Outflow :	33.5 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:18
Total Outflow :	2.36 (IN)		

Project: Millstone Simulation Run: 10YR PRE

Start of Run: 01Jan1999, 00:00 Basin Model: 10YR PRE

End of Run: 02Jan1999, 04:00 Meteorologic Model: 10yr pre

Compute Time: 19Dec2011, 09:11:50 Control Specifications: 10yr pre

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	11.7	01Jan1999, 12:24	1.65
SA1	0.0046	3.7	01Jan1999, 12:42	2.45
SPOOL	0.0046	0.0	01Jan1999, 00:00	0.00
COM1	0.0216	11.7	01Jan1999, 12:24	1.30
POOL1	0.0216	9.3	01Jan1999, 12:36	1.29
SA3	0.0121	21.7	01Jan1999, 12:18	3.88
COM2	0.0337	28.0	01Jan1999, 12:24	2.22
SA4	0.0030	5.9	01Jan1999, 12:18	3.98
COM	0.0367	33.5	01Jan1999, 12:18	2.36

10YR\_PRE.basin

Basin: 10YR PRE

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB #171138.00 10-YEAR  
EXISTING CONDITION ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:03:37

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 101.47002652519893

Canvas Y: 342.00318302387274

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: -50.732625994694985

Canvas Y: 351.4567639257295

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: -16.699734748010627

Canvas Y: 297.5713527851459



10YR\_PRE.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(10YR PRE)  
Elevation-Storage Table: SPOOL(10YR PRE)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 36.240318302387266  
Canvas Y: 247.46737400530506  
Downstream: POOL1

End:

Reservoir: POOL1

Canvas X: 48.52997347480107  
Canvas Y: 171.83872679045092  
Downstream: COM2

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: POOL1(10YR PRE)  
Elevation-Storage Table: POOL1(10YR PRE)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 132.6668435013263  
Canvas Y: 199.25411140583554  
Area: 0.0121  
Downstream: COM2

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 90

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM2

Description: COMBINE HYDROGRAPHS TO ESTIMATE DISCHARGE FROM 30" DRAIN TO POND  
Canvas X: 88.23501326259947  
Canvas Y: 93.37400530503976  
Downstream: COM

End:

Subbasin: SA4

Canvas X: 196.00583554376664  
Canvas Y: 152.9315649867374  
Area: 0.0030  
Downstream: COM

10YR\_PRE.basin

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 91

Transform: SCS  
Lag: 9.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND  
Canvas X: 130.7761273209549  
Canvas Y: 53.66896551724136

End:

Basin Schematic Properties:


Last View N: 5000.0  
Last View S: -5000.0  
Last View W: -5000.0  
Last View E: 5000.0  
Maximum View N: 373.20000000000005  
Maximum View S: 16.8  
Maximum View W: 37.2  
Maximum View E: 112.80000000000001  
Extent Method: Elements  
Buffer: 0  
Draw Icons: Yes  
Draw Icon Labels: Yes  
Draw Map Objects: No  
Draw Gridlines: No  
Draw Flow Direction: No  
Fix Element Locations: No  
Fix Hydrologic Order: No

End:



HEC-HMS

**Project : Millstone**  
Basin Model : 25YR POST  
Jan 18 12:07:35 EST 2012



Project: Millstone  
Simulation Run: 25YR POST Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	25YR POST
End of Run:	02Jan1999, 04:00	Meteorologic Model:	25yr post
Compute Time:	18Jan2012, 12:08:33	Control Specifications:	25yr post

Volume Units: IN

#### Computed Results

Peak Outflow :	40.2 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:18
Total Outflow :	2.95 (IN)		

Project: Millstone Simulation Run: 25YR POST

Start of Run: 01Jan1999, 00:00 Basin Model: 25YR POST  
End of Run: 02Jan1999, 04:00 Meteorologic Model: 25yr post  
Compute Time: 18Jan2012, 12:08:33 Control Specifications: 25yr post

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	15.5	01Jan1999, 12:24	2.14
SA1	0.0046	4.5	01Jan1999, 12:42	3.03
SPOOL	0.0046	0.0	01Jan1999, 00:00	0.00
COM1	0.0216	15.5	01Jan1999, 12:24	1.68
LPOOL	0.0216	12.5	01Jan1999, 12:36	1.67
SA3	0.0133	28.8	01Jan1999, 12:18	4.77
SA4	0.0018	4.2	01Jan1999, 12:18	4.77
COM	0.0367	40.2	01Jan1999, 12:18	2.95

25YR\_POST.basin

Basin: 25YR POST

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB #171138.00 25-YEAR  
PROPOSED CONDITIONS ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:04:05

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 89.7344827586207

Canvas Y: 286.9931034482759

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: -28.69310344827585

Canvas Y: 284.01379310344834

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: -10.072413793103436

Canvas Y: 238.5793103448276

25YR\_POST.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(25YR POST)  
Elevation-Storage Table: SPOOL(25YR POST)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 30.89310344827588  
Canvas Y: 179.73793103448278  
Downstream: LPOOL

End:

Reservoir: LPOOL

Canvas X: 42.06551724137931  
Canvas Y: 104.51034482758624  
Downstream: COM

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: LPOOL(25YR POST)  
Elevation-Storage Table: LPOOL(25YR POST)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 95.60000000000001  
Canvas Y: 160.0  
Area: 0.0133  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 92

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA4

Canvas X: 186.56206896551726  
Canvas Y: 204.31724137931036  
Area: 0.0018  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0

25YR\_POST.basin

Curve Number: 92

Transform: SCS

Lag: 9.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND

Canvas X: 97.92758620689658

Canvas Y: 47.903448275862104

End:

Basin Schematic Properties:

Last View N: 5000.0

Last View S: -5000.0

Last View W: -5000.0

Last View E: 5000.0

Maximum View N: 300.40000000000003

Maximum View S: 19.6

Maximum View W: 36.2

Maximum View E: 138.8

Extent Method: Elements

Buffer: 0

Draw Icons: Yes

Draw Icon Labels: Yes

Draw Map Objects: No

Draw Gridlines: No

Draw Flow Direction: No

Fix Element Locations: No

Fix Hydrologic Order: No


End:





HEC-HMS

**Project : Millstone**  
Basin Model : 25YR PRE  
Jan 18 12:11:21 EST 2012



Project: Millstone  
Simulation Run: 25YR PRE Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	25YR PRE
End of Run:	02Jan1999, 04:00	Meteorologic Model:	25yr pre
Compute Time:	19Dec2011, 09:24:13	Control Specifications:	25yr pre

Volume Units: IN

#### Computed Results

Peak Outflow :	39.5 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:18
Total Outflow :	2.87 (IN)		

Project: Millstone Simulation Run: 25YR PRE

Start of Run: 01Jan1999, 00:00 Basin Model: 25YR PRE

End of Run: 02Jan1999, 04:00 Meteorologic Model: 25yr pre

Compute Time: 19Dec2011, 09:24:13 Control Specifications: 25yr pre

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	15.5	01Jan1999, 12:24	2.14
SA1	0.0046	4.5	01Jan1999, 12:42	3.03
SPOOL	0.0046	0.0	01Jan1999, 00:00	0.00
COM1	0.0216	15.5	01Jan1999, 12:24	1.68
POOL1	0.0216	12.4	01Jan1999, 12:36	1.67
SA3	0.0121	25.3	01Jan1999, 12:18	4.55
COM2	0.0337	33.5	01Jan1999, 12:24	2.71
SA4	0.0030	6.9	01Jan1999, 12:18	4.66
COM	0.0367	39.5	01Jan1999, 12:18	2.87

25YR\_PRE.basin

Basin: 25YR PRE

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB #171138.00 25-YEAR  
EXISTING CONDITION ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:04:21

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 111.8689655172414

Canvas Y: 342.9485411140584

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: -93.27374005305042

Canvas Y: 335.385676392573

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: -35.606896551724134

Canvas Y: 273.937400530504

25YR\_PRE.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(25YR PRE)  
Elevation-Storage Table: SPOOL(25YR PRE)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 53.40000000000006  
Canvas Y: 232.80000000000004  
Downstream: POOL1

End:

Reservoir: POOL1

Canvas X: 53.40000000000006  
Canvas Y: 168.00000000000003  
Downstream: COM2

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: POOL1(25YR PRE)  
Elevation-Storage Table: POOL1(25YR PRE)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 140.82162162162166  
Canvas Y: 194.4648648648649  
Area: 0.0121  
Downstream: COM2

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 90

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM2

Description: COMBINE HYDROGRAPHS TO ESTIMATE DISCHARGE FROM 30" DRAIN TO POND  
Canvas X: 69.6  
Canvas Y: 92.4  
Downstream: COM

End:

Subbasin: SA4

Canvas X: 171.85945945945946  
Canvas Y: 116.33513513513515  
Area: 0.0030  
Downstream: COM

25YR\_PRE.basin

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 91

Transform: SCS  
Lag: 9.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND  
Canvas X: 106.19681697612737  
Canvas Y: 58.39575596816974

End:

Basin Schematic Properties:


Last View N: 5000.0  
Last View S: -5000.0  
Last View W: -5000.0  
Last View E: 5000.0  
Maximum View N: 373.20000000000005  
Maximum View S: 16.8  
Maximum View W: 37.2  
Maximum View E: 112.80000000000001  
Extent Method: Elements  
Buffer: 0  
Draw Icons: Yes  
Draw Icon Labels: Yes  
Draw Map Objects: No  
Draw Gridlines: No  
Draw Flow Direction: No  
Fix Element Locations: No  
Fix Hydrologic Order: No

End:



HEC-HMS

**Project : Millstone**  
Basin Model : 100YR POST  
Jan 18 11:50:03 EST 2012



Project: Millstone  
Simulation Run: 100YR POST Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	100YR POST
End of Run:	02Jan1999, 04:00	Meteorologic Model:	100yr post
Compute Time:	18Jan2012, 11:51:43	Control Specifications:	100yr post

Volume Units: IN

#### Computed Results

Peak Outflow :	54.0 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:24
Total Outflow :	4.05 (IN)		



Project: Millstone Simulation Run: 100YR POST

Start of Run: 01Jan1999, 00:00 Basin Model: 100YR POST  
End of Run: 02Jan1999, 04:00 Meteorologic Model: 100yr post  
Compute Time: 18Jan2012, 11:51:43 Control Specifications: 100yr post

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	23.7	01Jan1999, 12:24	3.18
SA1	0.0046	6.4	01Jan1999, 12:42	4.24
SPOOL	0.0046	0.2	01Jan1999, 22:18	0.36
COM1	0.0216	23.7	01Jan1999, 12:24	2.58
LPOOL	0.0216	18.6	01Jan1999, 12:36	2.57
SA3	0.0133	36.6	01Jan1999, 12:18	6.15
SA4	0.0018	5.3	01Jan1999, 12:18	6.15
COM	0.0367	54.0	01Jan1999, 12:24	4.05

100YR\_POST.basin

Basin: 100YR POST

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB #171138.00 100-YEAR  
PROPOSED CONDITIONS ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:02:38

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 105.62972972972973

Canvas Y: 264.1405405405406

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: 1.1000000000000085

Canvas Y: 278.0551724137931

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: 36.2

Canvas Y: 235.60000000000002

100YR\_POST.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(100YR POST)  
Elevation-Storage Table: SPOOL(100YR POST)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 52.400000000000006  
Canvas Y: 160.0  
Downstream: LPOOL

End:

Reservoir: LPOOL

Canvas X: 52.400000000000006  
Canvas Y: 95.199999999999999  
Downstream: COM

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: LPOOL(100YR POST)  
Elevation-Storage Table: LPOOL(100YR POST)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 109.8448275862069  
Canvas Y: 155.9034482758621  
Area: 0.0133  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 92

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA4

Canvas X: 179.1137931034483  
Canvas Y: 153.66896551724142  
Area: 0.0018  
Downstream: COM

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0

100YR\_POST.basin

Curve Number: 92

Transform: SCS

Lag: 9.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND

Canvas X: 111.3344827586207

Canvas Y: 65.03448275862073

End:

Basin Schematic Properties:

Last View N: 5000.0

Last View S: -5000.0

Last View W: -5000.0

Last View E: 5000.0

Maximum View N: 300.40000000000003

Maximum View S: 19.6

Maximum View W: 36.2

Maximum View E: 138.8

Extent Method: Elements

Buffer: 0

Draw Icons: Yes

Draw Icon Labels: Yes

Draw Map Objects: No

Draw Gridlines: No

Draw Flow Direction: No

Fix Element Locations: No


Fix Hydrologic Order: No

End:



HEC-HMS

**Project : Millstone**  
Basin Model : 100YR PRE  
Jan 18 11:56:20 EST 2012



Project: Millstone

Simulation Run: 100YR PRE Junction: COM

Start of Run:	01Jan1999, 00:00	Basin Model:	100YR PRE
End of Run:	02Jan1999, 04:00	Meteorologic Model:	100yr pre
Compute Time:	19Dec2011, 09:03:51	Control Specifications:	100yr pre

Volume Units: IN

### Computed Results

Peak Outflow :	53.1 (CFS)	Date/Time of Peak Outflow :	01Jan1999, 12:24
Total Outflow :	3.96 (IN)		

Project: Millstone Simulation Run: 100YR PRE

Start of Run: 01Jan1999, 00:00 Basin Model: 100YR PRE  
End of Run: 02Jan1999, 04:00 Meteorologic Model: 100yr pre  
Compute Time: 19Dec2011, 09:03:51 Control Specifications: 100yr pre

Hydrologic Element	Drainage Area (MI <sup>2</sup> )	Peak Discharge (CFS)	Time of Peak	Volume (IN)
SA2	0.0170	23.7	01Jan1999, 12:24	3.18
SA1	0.0046	6.4	01Jan1999, 12:42	4.24
SPOOL	0.0046	0.2	01Jan1999, 22:18	0.36
COM1	0.0216	23.7	01Jan1999, 12:24	2.58
POOL1	0.0216	18.6	01Jan1999, 12:36	2.57
SA3	0.0121	32.5	01Jan1999, 12:18	5.92
COM2	0.0337	45.9	01Jan1999, 12:24	3.77
SA4	0.0030	8.8	01Jan1999, 12:18	6.04
COM	0.0367	53.1	01Jan1999, 12:24	3.96

100YR\_PRE.basin

Basin: 100YR PRE

Description: MILLSTONE POWER PLANT WATERFORD, CT GZA JOB # 171138.00 100-YEAR  
EXISTING CONDITION ANALYSIS

Last Modified Date: 23 January 2012

Last Modified Time: 21:02:58

Version: 3.5

Filepath Separator: \

Unit System: English

Missing Flow To Zero: No

Enable Flow Ratio: No

Allow Blending: No

Compute Local Flow At Junctions: No

Enable Sediment Routing: No

Enable Quality Routing: No

End:

Subbasin: SA2

Canvas X: 109.97824933687002

Canvas Y: 337.27639257294436

Area: 0.0170

Downstream: COM1

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 65

Transform: SCS

Lag: 15.0

Unitgraph Type: STANDARD

Baseflow: None

End:

Subbasin: SA1

Canvas X: -76.25729442970824

Canvas Y: 346.7299734748011

Area: 0.0046

Downstream: SPOOL

Canopy: None

Surface: None

LossRate: SCS

Percent Impervious Area: 0.0

Curve Number: 75

Transform: SCS

Lag: 30.6

Unitgraph Type: STANDARD

Baseflow: None

End:

Reservoir: SPOOL

Canvas X: -41.2790450928382

Canvas Y: 285.2816976127321



100YR\_PRE.basin

Downstream: COM1

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 28.0  
Storage-Outflow Table: SPOOL(100YR PRE)  
Elevation-Storage Table: SPOOL(100YR PRE)  
Primary Table: Storage-Outflow

End:

Junction: COM1

Description: COMBINE SUB-AREA 2 WITH OVERFLOW FROM SUB-AREA 1  
Canvas X: 34.34960212201591  
Canvas Y: 243.68594164456235  
Downstream: POOL1

End:

Reservoir: POOL1

Canvas X: 39.076392572944314  
Canvas Y: 170.89336870026526  
Downstream: COM2

Route: Modified Puls  
Routing Curve: Storage-Elevation-Outflow  
Initial Elevation: 24.2  
Storage-Outflow Table: POOL1(100YR PRE)  
Elevation-Storage Table: POOL1(100YR PRE)  
Primary Table: Storage-Outflow

End:

Subbasin: SA3

Canvas X: 144.01114058355438  
Canvas Y: 238.0137931034483  
Area: 0.0121  
Downstream: COM2

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 90

Transform: SCS  
Lag: 12.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM2

Description: COMBINE HYDROGRAPHS TO ESTIMATE DISCHARGE FROM 30" DRAIN TO POND  
Canvas X: 92.01644562334218  
Canvas Y: 114.17188328912465  
Downstream: COM

End:

Subbasin: SA4

Canvas X: 200.732625994695  
Canvas Y: 150.09549071618036  
Area: 0.0030  
Downstream: COM

100YR\_PRE.basin

Canopy: None

Surface: None

LossRate: SCS  
Percent Impervious Area: 0.0  
Curve Number: 91

Transform: SCS  
Lag: 9.0  
Unitgraph Type: STANDARD

Baseflow: None

End:

Junction: COM

Description: COMBINE HYDROGRAPHS TO ESTIMATE TOTAL DISCHARGE TO POND  
Canvas X: 154.41007957559685  
Canvas Y: 66.90397877984083

End:

Basin Schematic Properties:

Last View N: 5000.0  
Last View S: -5000.0  
Last View W: -5000.0  
Last View E: 5000.0  
Maximum View N: 373.20000000000005  
Maximum View S: 16.8  
Maximum View W: 37.2  
Maximum View E: 112.80000000000001  
Extent Method: Elements  
Buffer: 0  
Draw Icons: Yes  
Draw Icon Labels: Yes  
Draw Map Objects: No  
Draw Gridlines: No  
Draw Flow Direction: No  
Fix Element Locations: No  
Fix Hydrologic Order: No

End:

**APPENDIX C**  
**RESULTS OF DRAINAGE SYSTEM HYDRAULIC**  
**(STORM CAD) ANALYSES**

**AS-BUILT CONDITIONS**

Scenario: Base

>>>> Info: Subsurface Analysis iterations: 3  
 >>>> Info: Convergence was achieved.

Gravity subnetwork discharging at: O-1

>>>> Info: Loading and hydraulic computations completed successfully.  
 >>>> Info: P-23 Hydraulic jump formed.  
 >>>> Info: P-23 Critical depth assumed upstream.  
 >>>> Warning: P-23 Pipe fails maximum velocity constraint.  
 >>>> Warning: P-12 Pipe fails minimum slope constraint.  
 >>>> Warning: P-13 Pipe fails minimum slope constraint.  
 >>>> Warning: P-13 Pipe discharge is above full flow capacity.  
 >>>> Warning: P-14 Pipe fails minimum slope constraint.  
 >>>> Warning: P-14 Pipe discharge is above full flow capacity.  
 >>>> Warning: P-22 Pipe fails minimum slope constraint.  
 >>>> Warning: P-22 Pipe discharge is above full flow capacity.  
 >>>> Info: P-1 Hydraulic jump formed.  
 >>>> Info: P-1 Critical depth assumed upstream.  
 >>>> Info: P-2 Hydraulic jump formed.  
 >>>> Info: P-2 Critical depth assumed upstream.  
 >>>> Info: P-26 Hydraulic jump formed.  
 >>>> Info: P-26 Critical depth assumed upstream.  
 >>>> Warning: P-29 Pipe fails minimum velocity constraint.  
 >>>> Info: P-10 Hydraulic jump formed.  
 >>>> Info: P-10 Critical depth assumed upstream.  
 >>>> Info: P-32 Hydraulic jump formed.  
 >>>> Info: P-32 Critical depth assumed upstream.  
 >>>> Warning: P-33 Pipe fails minimum velocity constraint.

CALCULATION SUMMARY FOR SURFACE NETWORKS

Label	Inlet Type	Inlet	Total Intercepted Flow (cfs)	Total Bypassed Flow (cfs)	Capture Efficiency (%)	Gutter Spread (ft)	Gutter Depth (ft)
I-8	Generic Inlet	Generic Default 100%	2.41	0.00	100.0	0.00	0.00
I-7	Generic Inlet	Generic Default 100%	4.38	0.00	100.0	0.00	0.00
I-5	Generic Inlet	Generic Default 100%	1.51	0.00	100.0	0.00	0.00
I-1	Generic Inlet	Generic Default 100%	5.06	0.00	100.0	0.00	0.00
I-2	Generic Inlet	Generic Default 100%	6.00	0.00	100.0	0.00	0.00
I-3	Generic Inlet	Generic Default 100%	4.48	0.00	100.0	0.00	0.00
I-4	Generic Inlet	Generic Default 100%	4.55	0.00	100.0	0.00	0.00
I-9	Generic Inlet	Generic Default 100%	0.00	0.00	100.0	0.00	0.00
I-UNDERDRAIN	Generic Inlet	Generic Default 100%	0.99	0.00	100.0	0.00	0.00

CALCULATION SUMMARY FOR SUBSURFACE NETWORK WITH ROOT: O-1


Label	Number of Sections	Section Size	Section Shape	Length (ft)	Total System Flow (cfs)	Average Velocity (ft/s)	Hydraulic Grade Upstream (ft)	Hydraulic Grade Downstream (ft)
P-7	1	30 inch	Circular	91.00	38.78	9.42	14.04	12.92
P-23	1	30 inch	Circular	329.00	25.67	11.39	22.33	14.64
P-24	1	30 inch	Circular	65.00	14.51	3.22	14.68	14.64
P-26	1	30 inch	Circular	218.00	16.92	5.92	23.60	22.80
P-27	1	15 inch	Circular	80.00	9.97	8.12	24.70	22.80
P-25	1	12 inch	Circular	10.00	1.51	3.44	17.05	16.97
P-22	1	24 inch	Circular	40.00	13.48	5.32	16.00	15.63
P-2	1	30 inch	Circular	324.00	17.00	5.95	25.22	23.93

P-14	1	24 inch	Circular	237.00	13.06	4.17	17.06	16.31
P-29	1	15 inch	Circular	21.00	0.89	0.73	16.31	16.31
P-1	1	30 inch	Circular	209.00	17.06	5.94	26.27	25.50
P-13	1	24 inch	Circular	50.00	13.11	4.17	17.45	17.28
P-33	1	12 inch	Circular	168.00	0.96	1.24	16.38	16.32
P-12	1	21 inch	Circular	86.00	10.01	4.16	17.95	17.61
P-18	1	15 inch	Circular	9.00	4.38	3.71	17.64	17.61
P-32	1	12 inch	Circular	168.00	0.99	2.87	16.80	16.38
P-17	1	12 inch	Circular	14.00	2.41	3.06	18.23	18.17
P-31	1	21 inch	Circular	16.00	8.27	3.44	18.21	18.17
P-30	1	21 inch	Circular	153.00	8.40	3.49	18.73	18.30
P-10	1	15 inch	Circular	168.00	4.43	4.97	20.46	18.85
P-16	1	15 inch	Circular	6.00	4.55	3.71	18.88	18.85
P-9	1	15 inch	Circular	128.00	4.48	4.18	21.26	20.65

Label	Total System Flow (cfs)	Ground Elevation (ft)	Hydraulic Grade Line In (ft)	Hydraulic Grade Line Out (ft)
O-1	38.69	16.50	12.92	12.92
J-4	38.78	19.70	14.64	14.04
J-3	25.67	27.50	22.80	22.33
J-11	14.51	20.50	14.77	14.68
J-2	16.92	30.10	23.93	23.60
I-2	9.97	26.50	25.21	24.70
I-5	1.51	20.50	17.14	17.05
J-10	13.48	20.90	16.31	16.00
J-1	17.00	33.00	25.50	25.22
J-9	13.06	20.90	17.28	17.06
J-12	0.89	20.75	16.32	16.31
I-1	17.06	30.50	26.55	26.27
J-8	13.11	20.90	17.61	17.45
I-9	0.96	20.67	16.38	16.38
J-7	10.01	20.90	18.17	17.95
I-7	4.38	20.75	17.75	17.64
I-UNDERDRAIN	0.99	20.75	16.80	16.80
I-8	2.41	20.75	18.30	18.23
J-14	8.27	20.90	18.30	18.21
J-6	8.40	21.00	18.85	18.73
J-5	4.43	24.20	20.65	20.46
I-4	4.55	20.70	18.98	18.88
I-3	4.48	24.50	21.40	21.26


Completed: 01/18/2012 01:05:09 PM

# Scenario: Base




# Profile

## Scenario: Base






# Profile Scenario: Base



# Profile Scenario: Base



## **PROPOSED CONDITIONS**

=====  
 Scenario: 25 yr Storm

>>> Info: Subsurface Analysis iterations: 3  
 >>> Info: Convergence was achieved.

=====  
 Gravity subnetwork discharging at: 0-1

>>> Info: Loading and hydraulic computations completed successfully.  
 >>> Info: P-23 Hydraulic jump formed.  
 >>> Info: P-23 Critical depth assumed upstream.  
 >>> Warning: P-12 Pipe discharge is above full flow capacity.  
 >>> Warning: P-13 Pipe fails minimum slope constraint.  
 >>> Warning: P-13 Pipe discharge is above full flow capacity.  
 >>> Warning: P-18 Pipe fails minimum velocity constraint.  
 >>> Warning: P-14 Pipe fails minimum slope constraint.  
 >>> Warning: P-14 Pipe discharge is above full flow capacity.  
 >>> Warning: P-22 Pipe fails minimum slope constraint.  
 >>> Warning: P-22 Pipe discharge is above full flow capacity.  
 >>> Warning: P-31 Pipe discharge is above full flow capacity.  
 >>> Warning: P-35 Pipe fails minimum cover constraint.  
 >>> Warning: P-35 Pipe fails minimum velocity constraint.  
 >>> Warning: P-36 Pipe fails minimum cover constraint.  
 >>> Warning: P-37 Pipe fails minimum velocity constraint.

CALCULATION SUMMARY FOR SURFACE NETWORKS

Label	Inlet Type	Inlet	Total Intercepted Flow (cfs)	Total Bypassed Flow (cfs)	Capture Efficiency (%)	Gutter Spread (ft)	Gutter Depth (ft)
CB#6	Generic Inlet	Generic Default	100%	0.00	0.00	100.0	0.00
DMH#13	Generic Inlet	Generic Default	100%	2.02	0.00	100.0	0.00
CB#5	Generic Inlet	Generic Default	100%	1.51	0.00	100.0	0.00
CB#8	Generic Inlet	Generic Default	100%	0.52	0.00	100.0	0.00
CB#7	Generic Inlet	Generic Default	100%	0.52	0.00	100.0	0.00
I-11	Generic Inlet	Generic Default	100%	1.20	0.00	100.0	0.00
I-12	Generic Inlet	Generic Default	100%	1.26	0.00	100.0	0.00
I-13	Generic Inlet	Generic Default	100%	2.00	0.00	100.0	0.00
I-14	Generic Inlet	Generic Default	100%	1.35	0.00	100.0	0.00
CB#4	Generic Inlet	Generic Default	100%	4.76	0.00	100.0	0.00

CALCULATION SUMMARY FOR SUBSURFACE NETWORK WITH ROOT: 0-1

Label	Number of Sections	Section Size	Section Shape	Length (ft)	Total System Flow (cfs)	Average Velocity (ft/s)	Hydraulic Grade Upstream (ft)	Hydraulic Grade Downstream (ft)
P-7	1	30 inch	Circular	91.00	39.07	9.79	14.18	12.84
P-24	1	30 inch	Circular	65.00	17.42	3.66	14.86	14.79
P-23	1	30 inch	Circular	329.00	21.73	9.95	20.49	14.79
P-25	1	12 inch	Circular	10.00	1.51	3.44	17.05	16.97
P-22	1	24 inch	Circular	40.00	16.22	5.79	16.19	15.76
P-14	1	24 inch	Circular	237.00	13.56	4.32	17.41	16.56
P-29	1	15 inch	Circular	21.00	3.04	2.48	16.60	16.56
P-13	1	24 inch	Circular	50.00	13.59	4.33	17.82	17.64
P-33	1	12 inch	Circular	168.00	3.12	3.98	17.41	16.65
P-12	1	21 inch	Circular	84.00	11.96	4.97	18.47	17.99
P-18	1	15 inch	Circular	6.00	2.02	1.65	18.00	17.99
P-32	1	12 inch	Circular	168.00	2.74	3.48	18.12	17.54
P-31	1	21 inch	Circular	16.00	11.97	4.97	18.76	18.66
P-39	1	12 inch	Circular	50.00	2.28	2.91	18.42	18.22

P-30	1	21 inch	Circular	153.00	10.92	4.54	19.67	18.95
P-37	1	12 inch	Circular	19.00	1.35	1.71	18.98	18.95
P-38	1	12 inch	Circular	45.00	2.30	2.93	18.61	18.42
P-16	1	15 inch	Circular	6.00	4.76	3.88	19.87	19.83
P-36	1	21 inch	Circular	168.00	6.48	2.69	20.11	19.83
P-35	1	12 inch	Circular	195.00	1.26	1.60	18.92	18.68

Label	Total System Flow (cfs)	Ground Elevation (ft)	Hydraulic Grade Line In (ft)	Hydraulic Grade Line Out (ft)
O-1	39.03	16.50	12.84	12.84
DMH#4	39.07	19.70	14.79	14.18
DMH#11	17.42	20.50	14.98	14.86
CB#6	21.73	27.50	20.83	20.49
CB#5	1.51	20.50	17.14	17.05
DMH#10	16.22	20.90	16.56	16.19
DMH#9	13.56	20.90	17.64	17.41
DMH#12	3.04	20.75	16.65	16.60
DMH#8	13.59	20.90	17.99	17.82
CB#8	3.12	20.67	17.54	17.41
DMH#7	11.96	20.90	18.66	18.47
DMH#13	2.02	20.75	18.02	18.00
CB#7	2.74	20.67	18.22	18.12
DMH#15	11.97	20.90	18.95	18.76
J-10	2.28	20.90	18.42	18.42
DMH#6	10.92	21.00	19.83	19.67
I-14	1.35	20.90	19.00	18.98
I-11	2.30	20.90	18.68	18.61
CB#4	4.76	20.70	19.87	19.87
I-13	6.48	20.90	20.11	20.11
I-12	1.26	20.90	18.94	18.92

=====  
Completed: 04/02/2012 03:45:35 PM

Scenario: 25 yr Storm

O-1

P-7

DMH#4

P-24

DMH#11

P-25

CB#52

P-29

DMH#10

DMH#12

P-33

CB#8

I-12

P-36

I-13

P-14

DMH#6

P-16

CB#4

DMH#9

P-13

P-18

DMH#8

DMH#13

P-12

CB#6

P-32

CB#7

P-39

J-10

P-38

I-11

DMH#7

P-31


DMH#15

I-14

P-30


# Profile

## Scenario: 25 yr Storm




# Profile

## Scenario: 25 yr Storm







# Profile Scenario: 25 yr Storm




# Profile Scenario: 25 yr Storm



**Profile**  
**Scenario: 25 yr Storm**



# Profile Scenario: 25 yr Storm



**APPENDIX D**  
**QUALITY CONTROL STATEMENTS**



## QUALITY CONTROL STATEMENT

The hydrologic and hydraulic analyses for the Independent Spent Fuel Storage Installation Project presented within this Drainage Report were conducted by GZA GeoEnvironmental, Inc. (“GZA”) staff engineer, Mr. Kenneth D. Hunu. Oversight of the work and review of associated engineering calculations and drainage design were conducted by Mr. David M. Leone (GZA Hydrologist). Mr. Peter H. Baril is the Engineer-in-Charge and Mr. David M. Leone is the Project Manager. Mr. Daniel C. Stapleton served as the reviewer. Mr. Leone is a hydrologic and hydraulic engineer with over 14 years of experience in civil engineering and surface water hydrology and is also a Professional Engineer. Mr. Baril specializes in urban hydrology and flood control analyses. He is a Registered Professional Engineer as well as a Registered Hydrologist (American Institute of Hydrology). He has over 30 years of experience in the field of water resources engineering, primarily in the areas of surface water hydrology and open channel hydraulics. Mr. Stapleton is a Vice-President of GZA and has degrees in geology and civil engineering and is a Professional Engineer registered in the State of Connecticut.

The runoff analysis was carried out using the USCOE HEC-HMS computer software, which has superseded USCOE HEC-1. GZA has successfully applied this software package over the past 10 years on numerous site drainage and dam engineering projects and has independently verified the numerical accuracy of this deterministic model. Likewise, GZA has conducted independent checks, in the form of hand calculations, of friction and shock losses, to verify hydraulic results from the StormCAD computer program used by GZA, under license from Haestad Methods, Inc.

**APPENDIX E**  
**ISFSI DESIGN DRAWINGS**

# MILLSTONE POWER STATION



## GENERAL NOTES:

1. VERTICAL DATUM IS NATIONAL GEODETIC VERTICAL DATUM OF 1929.
2. 250 FOOT GRID BASED ON THE CONNECTICUT STATE PLANE COORDINATE SYSTEM.
3. BASE PLAN USED FOR ALL DRAWING IS FROM DOMINION NUCLEAR CONNECTICUT DATED FEBRUARY 18, 2004 AND TITLED "25205 - 59007, ISFSI FINAL GRADING AND DRAINAGE PLAN. BASE PLAN WAS PROVIDED ELECTRONICALLY BY DOMINION AS CAD FILE 59007. SCALE 1" = 40'.
4. OTHER MAP REFERENCES INCLUDE: "NORTHEAST NUCLEAR ENERGY CO. MILLSTONE STATION, SITE PLAN," SCALE 1" = 100', DATED 08/03/99 AND "THE CONNECTICUT LIGHT & POWER CO., BERLIN, CONNECTICUT PROJECT: MILLSTONE POINT, SCALE: 1" = 200', SHEET 1 OF 2 AND 2 OF 2.
5. CERTAIN EXISTING CONDITIONS, INCLUDING CERTAIN UTILITIES, ARE NOT INDICATED ON THE PLANS FOR CLARITY AND SECURITY REASONS. THESE PLANS ARE NOT TO BE USED FOR UTILITY CLEARANCE PURPOSES.
6. POTENTIAL UTILITY INTERFERENCES WILL BE CONFIRMED PRIOR TO CONSTRUCTION. THE ALIGNMENT OF THE PROPOSED OR EXISTING UTILITIES MAY BE ADJUSTED TO AVOID IDENTIFIED INTERFERENCES.

## LIST OF DRAWINGS

NO.	DESCRIPTION
1	TITLE SHEET
2	EXISTING CONDITIONS PLAN (PHASE -1)
3	REVISED GRADING PLAN AND DRAINAGE SYSTEM (FULL BUILD-OUT)
4	STORMWATER DRAINAGE DETAILS
5	EROSION AND SEDIMENT CONTROL PLAN (FULL BUILD-OUT)
6	EROSION AND SEDIMENT CONTROL DETAILS
7	SOIL PLACEMENT AREA PLAN AND NOTES

THESE DRAWINGS ARE FOR THE PURPOSE OF CONNECTICUT SITING COUNCIL AND TOWN OF WATERFORD REVIEW. NOT FOR USE FOR CONSTRUCTION.

## REVISIONS TO ORIGINAL DESIGN

### Independent Spent Fuel Storage Installation (ISFSI)

### Dominion Nuclear Connecticut Inc.

### Waterford, Connecticut

NO.	REVISION	DATE

COVER SHEET

MILLSTONE POWER STATION	
WATERFORD, CONNECTICUT	
PROJECT NO. 11183.00	
DRAWING NO. 1	
SHEET NO.	



STATE OF CONNECTICUT  
 PROFESSIONAL ENGINEER  
 STATE OF CONNECTICUT  
 NO. 11183.00  
 PROJECT: MILLSTONE POWER STATION  
 DRAWING NO. 1  
 SHEET NO.





**LEGEND:**


- ± BOUNDARY SURFACE FOOT ELEVATION
- EXISTING SURFACE ELEVATION (MAY VARY)
- EXISTING CATCH BASIN AND IDENTIFICATION
- I-11 PROPOSED CATCH BASIN AND IDENTIFICATION
- EXISTING MANHOLE AND IDENTIFICATION
- I-10 PROPOSED MANHOLE AND IDENTIFICATION
- EXISTING STORM DRAIN, PIPE SECTION LENGTH, DIAMETER AND SLOPE
- EXISTING TRENCH DRAIN
- DIRECTION OF PIPE FLOW

**REFERENCES:**

1. 25205-99007, ISFI FINAL GRADING & DRAINAGE PLAN DATED 02/18/04, PROVIDED ELECTRONICALLY BY DOMINION AS CAD FILE 59007
2. 25205-99006, ISFI SITE PLAN (FULL BUILD-OUT) DATED 02/18/04, PROVIDED ELECTRONICALLY BY DOMINION AS CAD FILE 59006&BUILDOUT

**NOTES:**

1. ELEVATIONS SHOWN IN NOV029 DATUM
2. REFER TO DRAWING NO. 4 FOR SCHEDULE OF ELEVATIONS FOR PROPOSED DRAINAGE NETWORK
3. REFER TO DRAWING NO. 2 FOR ADDITIONAL LEGEND INFORMATION



NO.	SCALE/DESCRIPTION	BY	DATE

**MILLSTONE POWER STATION**  
**WATERFORD, CONNECTICUT**

Prepared by: **CDM**  
 Civil and Environmental  
 1000 Main Street, Suite 200  
 Waterford, CT 06495

MADE AVAILABLE UNDER THE PUBLIC ACCESS TO INFORMATION ACT (PAITIA) OF CANADA AND THE FREEDOM OF INFORMATION ACT (FOIA) OF THE UNITED STATES OF AMERICA. THIS DOCUMENT IS UNCLASSIFIED AND IS BEING RELEASED TO THE PUBLIC. ANY INFORMATION CONTAINED HEREIN IS UNCLASSIFIED EXCEPT WHERE SHOWN OTHERWISE. FOR MORE INFORMATION, CONTACT THE NATIONAL ARCHIVES AT 866.963.0900.

**PROPOSED GRADING AND DRAINAGE PLAN (FULL BUILD-OUT)**

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DESIGNER:	DESIGNER:	DESIGNER:	DESIGNER:
CDM	CDM	CDM	CDM

SCALE:	SCALE:	SCALE:	SCALE:
AS SHOWN	AS SHOWN	AS SHOWN	AS SHOWN

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013


PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

PROJECT NO.:	PROJECT NO.:	PROJECT NO.:	PROJECT NO.:
11182	11182	11182	11182

DATE:	DATE:	DATE:	DATE:
04/27/2013	04/27/2013	04/27/2013	04/27/2013

CATCH BASIN FRAME AND GRATE TO BE MECHANICALLY WELDED TO REINFORCING BARS IN AREAS BOLT AND/OR WELD AS REQUIRED IN HIGH SECURITY AREAS



**GENERAL NOTES**

1. MIN. 0.12 30 IN STEEL PIPE SHALL BE AT LEAST 4 FEET FROM THE BOTTOM OF THE CATCH BASIN INLET GRATE
2. CONFIRM WITH MANUFACTURER FOR IBS'S SITE LOAD REQUIREMENTS

**REINFORCEMENT NOTES:**

1. MIN. 0.12 30 IN STEEL REINFORCING BARS SHALL BE PLACED ACCORDING TO AASHO DESIGNATION M199
2. CONFIRM WITH MANUFACTURER FOR IBS'S SITE LOAD REQUIREMENTS

**PIPE NOTES**

1. LIFTING MINIMUM COVER WITH 4\"/>


**CATCH BASIN DETAIL**  
NOT TO SCALE

ITEM	DESCRIPTION	DATE
EXIST. DMH#15	EXIST. DMH#15	
RM#21.00	PROPOSED INV IN (-1.12)= 15.35	
RM#24.50	EXISTING INV IN (DMH#2)= 15.30	
RM#21.00	EXISTING INV OUT (DMH#7)= 15.30	
EXIST. CB#7	EXIST. CB#7	
RM#20.9	PROPOSED INV IN (-1.10)= 15.35	
RM#20.9	EXISTING INV IN (CB#2)= 15.35	
RM#20.9	EXISTING INV OUT (CB#2)= 15.35	

ITEM	DESCRIPTION	DATE
MODIFIED CB#3	MODIFIED CB#3	
RM#24.50	PROPOSED INV OUT (-1.15)= 17.64	
MODIFIED DMH#6	MODIFIED DMH#6	
RM#20.9	PROPOSED INV IN (-1.12)= 16.39	
RM#20.9	EXISTING INV IN (CB#4)= 16.39	
RM#20.9	EXISTING INV OUT (DMH#15)= 16.07	

ITEM	DESCRIPTION	DATE
PROP. I-10	PROP. I-10	
RM#20.9	INV IN (-1.12)= 16.63	
INV OUT (CB#7)= 16.63		
PROP. I-11	PROP. I-11	
RM#20.9	INV IN (-1.12)= 16.86	
INV OUT (I-10)= 16.86		
PROP. I-13	PROP. I-13	
RM#20.9	INV IN (-1.13)= 16.91	
INV OUT (DMH#2)= 16.91		
PROP. I-12	PROP. I-12	
RM#20.9	INV OUT (-1.11)= 17.84	
PROP. I-14	PROP. I-14	
RM#20.9	INV IN (-1.13)= 15.35	
INV OUT (DMH#7)= 15.35		

NOTE. ELEVATIONS SHOWN IN FEET (NGVD 29 DATUM)  
DRAINAGE STRUCTURE SCHEDULE



**60\"/>**

**GENERAL NOTES:**

1. CO-POLYMER MANHOLE STEPS SHALL BE INSTALLED AT 12\"/>

**REINFORCEMENT NOTES:**

1. MIN. 0.12 30 IN STEEL REINFORCING BARS SHALL BE PLACED ACCORDING TO AASHO DESIGNATION M199
2. CONFIRM WITH MANUFACTURER FOR IBS'S SITE LOAD REQUIREMENTS

NO.	DATE	DESCRIPTION	BY	CHKD.

**MILLSTONE POWER STATION**  
WATERFORD, CONNECTICUT

PROJECT NO. 111129.00  
SHEET NO. 4

DESIGNED BY: [ ]  
CHECKED BY: [ ]  
DATE: 11/12/00

SCALE: AS SHOWN

PROJECT: STORM WATER DRAINAGE DETAILS

CONTRACTOR: DOMINION NUCLEAR CONNECTICUT INC.


ENGINEER: [ ]

**NOTES:**

1. THE ISFSI PROJECT IS SUBJECT TO A STATE OF CONNECTICUT GENERAL PERMIT FOR THE DISCHARGE OF STORMWATER AND DEWATERING WASTEWATERS ASSOCIATED WITH CONSTRUCTION ACTIVITY.
2. THE 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL ARE TO BE FOLLOWED.
3. SEE DWG. 6 FOR NARRATIVE, NOTES AND DETAILS.
4. SILT FENCE AND HAYBALES ARE NOT TO BE PLACED AGAINST ANY PROTECTED AREA FENCE. REMOVE PRIOR TO INSTALLATION OF PROTECTED AREA FENCE.
5. LOCATION OF TEMPORARY SEDIMENTATION TANKS AND BASINS AND CONTRACTOR FUELING AREA ARE NOT INDICATED AND WILL BE DETERMINED PRIOR TO THE START OF CONSTRUCTION.

**REFERENCES:**

1. 25205-59007, ISFT FINAL GRADING & DRAINAGE PLAN DATED 02/18/04, "PROVIDED ELECTRONICALLY BY DOMINION AS CAD FILE '59007'"
2. 25205-59006, ISFT SITE PLAN (FULL BUILD-OUT) DATED 02/18/04, "PROVIDED ELECTRONICALLY BY DOMINION AS CAD FILE '59006&BUILDOUT'"



NO.	DATE/DESCRIPTION	BY	DATE

APPROVED:		MILLSTONE POWER STATION WATERFORD, CONNECTICUT
PROJECT NO.: 043 PROJECT NAME: EROSION AND SEDIMENT CONTROL	PREPARED BY: Christopher J. Meehan CHECKED BY: Christopher J. Meehan DATE: 04/12/2012	PROJECT NO.: 77-118-00 SHEET NO.: 5

THIS DOCUMENT IS THE PROPERTY OF CHRYSLER FINANCIAL CORPORATION AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE EXPRESS WRITTEN PERMISSION OF CHRYSLER FINANCIAL CORPORATION. THIS DOCUMENT IS THE PROPERTY OF CHRYSLER FINANCIAL CORPORATION AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE EXPRESS WRITTEN PERMISSION OF CHRYSLER FINANCIAL CORPORATION.



**EROSION AND SEDIMENT CONTROL NARRATIVE**

**EROSION AND SEDIMENT CONTROL MEASURES** shall be implemented to minimize erosion and transport of sediment to resource areas during the earthwork and construction phases of the project.

**SITE STRIPPING AND EXCAVATION** shall be implemented to minimize erosion and sediment transport to resource areas during the earthwork and construction phases of the project. Erosion control measures shall be installed prior to the start of site stripping and excavation. Erosion control measures shall be installed around the outer work perimeter. Disturbance is to be limited to those areas necessary to complete the proposed work.

**HAY/BALE SILT FENCE BARRIERS** shall be installed to trap sediment transported by runoff before it reaches the drainage system or leaves the construction site, in addition to areas where high runoff velocities or high erosion potential exist. Hay bales or silt fences should not be placed along the restricted area fence.

**CATCH BASIN INLET PROTECTION** Existing and newly constructed catch basins are to be protected with hay bales and silt fences (where appropriate) or silt socks throughout construction.

**SLOPE PROTECTION** shall be installed with the following minimum specifications: If this erosion and sediment control method is ineffective, then the Contractor shall install existing silt fences, silt socks, hay bales, and/or plastic netting.

**TEMPORARY SEDIMENT BASINS** Temporary sediment basins will be designed either as excavations or bermed stormwater detention structures. These basins shall be designed to settle out prior to discharge. These temporary basins will be located based on construction site conditions and shall be designed with a minimum 10% slope to the outlet. The basins shall be surrounded by a crushed stone filter wall with a minimum 18" depth. The basins shall be equipped with a perforated metal grate at the outlet. Points of discharge from sediment basins will be stabilized to minimize erosion.

**STOCKPILED MATERIALS** Construction materials shall be stored in piles with hay bales and silt fences. Other acceptable alternatives include gravel filter berms laid around the perimeter of the stockpile. Stormwater runoff is to be diverted away from stockpiles.

**SLOPE STABILIZATION** Slope stabilization is to be implemented within 10 days after grading or construction activities have temporarily or permanently ceased. Slope stabilization is to be implemented on slopes of 3:1 or steeper. Establishment of temporary and permanent vegetation cover is to be established on slopes of 3:1 or steeper. Temporary vegetation cover is to be established on slopes of 3:1 or steeper. Permanent vegetation cover is to be established on slopes of 3:1 or steeper. Slope stabilization is to include crushed stone and/or gravel surfacing, underlain by a geotextile separation fabric.

**WINTER STABILIZATION** At any phase of on-site activity, unexcavated surface water, seepage, or other water shall be stabilized with hay and straw mulch, hydro-seeding, mulching, or erosion control blankets as necessary to control erosion during winter storm events.

**CONSTRUCTION Dewatering** For construction where possible, the wastewater/dewatering is to be infiltrated into the ground. However, the existing soils have limited infiltration capacity. Construction dewatering wastewater discharged to a surface water body is to be pre-treated for sediment removal by residing in a construction dewatering tank with a temporary sediment basin prior to discharge.

**CONSTRUCTION SITE EROSION CONTROL** Stabilized construction entrance and exit are to be established at all permanent construction staging areas including the Soil Placement Area, to reduce the tracking of sediment from the construction site onto other areas. Stabilized construction entrance and exit are to be established at all permanent construction staging areas and exit are not adequate to prevent sediment from being tracked onto the road.

**DUST CONTROL** Standard dust control measures are to be used, such as use of water trucks, misting, mulch, or placement of straw or hay bales. Dust control measures are to be considered prior to grading and grading activities, which can contribute to large amounts of dust to be blown.

**EQUIPMENT FUELING** Fueling activities including petroleum, oil and other petroleum based substances is to be performed at a pre-approved, designated area with appropriate spill prevention and control measures. Fueling activities shall be performed in a designated area with appropriate spill prevention and control measures. Structures within the Equipment Fueling Area shall be constructed of concrete and other non-combustible materials and are to be placed around the perimeter of the fueling area, during all fueling activities.

**GOOD HOUSEKEEPING AND WASTE DISPOSAL** Construction materials, equipment, building materials, building materials, or similar materials are to be stored in a covered area to prevent dust, debris, and other materials from being tracked onto the site. Internal truck routes are to be established to prevent dust, debris, and other materials from being tracked onto the site.

**INSPECTION AND MAINTENANCE** Qualified personnel, as determined by Dominion, are to inspect disturbed areas of the construction activity on a regular basis. Inspection is to be performed at least once every month for three months. Inspection is to be performed at least once every month for three months. Inspection is to be performed at least once every month for three months. Inspection is to be performed at least once every month for three months.

**SEQUENCE OF GRADING AND CONSTRUCTION ACTIVITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.

**REPORTING AND RECORD KEEPING** In addition to the aforementioned inspection and maintenance procedures, the contractor is to keep a log of all construction activities. The log is to include the following information: Date, location, description of activity, and results of inspection. The log is to be maintained for the duration of the project.

**CONTRACTOR RESPONSIBILITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.

**CONTRACTOR RESPONSIBILITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.














**CONTRACTOR RESPONSIBILITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.

**CONTRACTOR RESPONSIBILITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.

**CONTRACTOR RESPONSIBILITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.

**CONTRACTOR RESPONSIBILITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.

**CONTRACTOR RESPONSIBILITIES** The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures. The contractor shall be responsible for installation, monitoring, inspection and correction of erosion and sediment control measures.



NO. 100

NO. 101

NO. 102

NO. 103

NO. 104

NO. 105

NO. 106

NO. 107

NO. 108

NO. 109

NO. 110

NO. 111

NO. 112

NO. 113





NO. 114

NO. 115

NO. 116

NO. 117

NO.	SCALE/DESCRIPTION	BY	DATE
1	1" = 10'	PHB	01/11/2017
2	1" = 10'	PHB	01/11/2017
3	1" = 10'	PHB	01/11/2017
4	1" = 10'	PHB	01/11/2017
5	1" = 10'	PHB	01/11/2017
6	1" = 10'	PHB	01/11/2017
7	1" = 10'	PHB	01/11/2017
8	1" = 10'	PHB	01/11/2017
9	1" = 10'	PHB	01/11/2017
10	1" = 10'	PHB	01/11/2017
11	1" = 10'	PHB	01/11/2017
12	1" = 10'	PHB	01/11/2017
13	1" = 10'	PHB	01/11/2017
14	1" = 10'	PHB	01/11/2017
15	1" = 10'	PHB	01/11/2017
16	1" = 10'	PHB	01/11/2017
17	1" = 10'	PHB	01/11/2017
18	1" = 10'	PHB	01/11/2017



**WATERFORD, CONNECTICUT**

**MILLSTONE POWER STATION**

PROJECT NO. 171138.00

DESIGNED BY: PHB

DRAWN BY: PHB

CHECKED BY: PHB

DATE: 01/11/2017

**EROSION AND SEDIMENT CONTROL DETAILS**

NO. 118

SCALE/DESCRIPTION: 1" = 10'

BY: PHB

DATE: 01/11/2017

NO. 118

NO. 119

NO. 120

NO. 121

NO. 122

NO. 123

NO. 124

NO. 125

NO. 126

NO. 127

NO. 128

NO. 129

NO. 130

NO. 131

NO. 132

NO. 133

NO. 134


NO. 135

**NOTES**

1. SEE DRAWING 2 FOR LEGEND
2. SEE DRAWING 6 FOR EROSION CONTROL DETAILS
3. SOIL TO BE PLACED ON AS-BEHEED BASIS. SOIL TO BE PLACED IN CONTROLLED LIFTS OF 12 INCHES OR LESS AND GRADED TO DRAIN TO THE SOUTH AND EAST TO MAINTAIN PRE-CONSTRUCTION DRAINAGE PATTERN
4. SOIL PLACEMENT AREA TO BE FILLED TO AN EVEN LEVEL TO THE EXTENT PRACTICABLE
5. LIDAM AND CEED MAINTAIN EROSION AND SEDIMENTATION CONTROLS UNTIL VEGETATED
6. WETLANDS ARE PRESENT EAST OF THE SOIL PLACEMENT AREA. NO EXCESS SOIL SHALL BE PLACED WITHIN 100 FEET OF THE WETLANDS
7. APPROXIMATE CAPACITY OF SOIL PLACEMENT AREA
  - ASSUMING AVERAGE THICKNESS OF TWO FEET - 5,000 CUBIC YARDS
  - ASSUMING AVERAGE THICKNESS OF THREE FEET - 8,000 CUBIC YARDS

**REFERENCES**

1. SA-PAS9007.DWG (SFI SOIL PLACEMENT AREA TOPOGRAPHY PLAN PROVIDED ELECTRONICALLY BY DOMINION AS CAD FILE 'SFI\TOP0.DWG' ON FEBRUARY 15, 2012)



NO.	DATE	DESCRIPTION

**MILLSTONE POWER STATION**  
 WATERFORD, CONNECTICUT  
 PROJECT BY: Dominion Nuclear Connecticut, Inc.  
 DRAWING NO.: SA-PAS9007.DWG  
 SHEET NO.: 7

**SOIL PLACEMENT AREA PLAN AND NOTES**

DATE	BY	CHKD BY	DATE

THIS DRAWING IS THE PROPERTY OF GSA CONSULTANTS, INC. AND IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF GSA CONSULTANTS, INC. THE INFORMATION CONTAINED HEREIN IS FOR THE EXCLUSIVE USE OF THE CLIENT AND IS NOT TO BE USED FOR ANY OTHER PROJECT OR FOR ANY OTHER PURPOSE. GSA CONSULTANTS, INC. SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS IN THIS DRAWING. THE USER OF THIS DRAWING SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES. GSA CONSULTANTS, INC. IS NOT RESPONSIBLE FOR ANY CONSTRUCTION DEFECTS OR DAMAGES TO PERSONS OR PROPERTY. THE USER OF THIS DRAWING SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES. GSA CONSULTANTS, INC. IS NOT RESPONSIBLE FOR ANY CONSTRUCTION DEFECTS OR DAMAGES TO PERSONS OR PROPERTY.