# TABLE OF CONTENTS

| 1.0  | PRO  | JECT INTRODUCTION1-1   |
|--|--|--|
| 1.1  | SITE   | SUMMARY  |
| 1  | .1.1   | Existing Conditions  |
| 1  | .1.2   | Project Description  |
| 1  | .1.3   | Site Specific Concerns1-1  |
| 1  | .1.4   | Construction Schedule1-1   |
| 1.2  |  | IECT OWNER AND OPERATOR1-2   |
| 1.3  |  | S, SLOPES, VEGETATION, AND CURRENT DRAINAGE PATTERNS   |
| -  | .3.1   | Soil type(s)   |
|  | .3.2   | Slopes 1-2   |
|  | .3.3   | Drainage Patterns  |
|  | .3.4   | Vegetation   |
|  |  | FEATURES AND SENSITIVE AREAS TO BE PROTECTED1-2  |
|  | .4.1   | Receiving Waters and TMDL Applicability  |
| 1  | .4.2   | Wetlands1-3  |
|  |  |  |
| 2.0  |  | STRUCTION ACTIVITIES2-1  |
| 2.1  |  | CRIPTION OF CONSTRUCTION ACTIVITY  |
| 2.2  | CON  | STRUCTION SITE ESTIMATES   |
|  |  |  |
|  |  |  |
| 3.0  | BEST   | Г MANAGEMENT PRACTICES 3-1   |
| <b>3.0</b><br>3.1  |  | <b>Γ MANAGEMENT PRACTICES</b>  |
|  | STR  |  |
| 3.1<br>3.2   | STR  | JCTURAL CONTROL PRACTICES  |
| 3.1<br>3.2<br>3  | Str<br>Tem   | JCTURAL CONTROL PRACTICES  |
| 3.1<br>3.2<br>3<br>3   | STR<br>Tem<br>.2.1   | JCTURAL CONTROL PRACTICES  |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3  | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4   | JCTURAL CONTROL PRACTICES  |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3   | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5   | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2   |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3   | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5<br>.2.6   | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-2   |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3   | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5<br>.2.6<br>.2.7   | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-2Temporary Sediment Trap (TST)3-3   |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3                                    | STR<br>TEM<br>2.1<br>2.2<br>2.3<br>2.4<br>2.5<br>2.6<br>2.7<br>2.8   | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-3Construction Entrance (CE)3-3  |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3                               | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5<br>.2.6<br>.2.7<br>.2.8<br>.2.9   | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-3Construction Entrance (CE)3-3Tree Protection (TP)3-3   |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3                          | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5<br>.2.6<br>.2.7<br>.2.8<br>.2.9<br>.2.10  | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-2Temporary Sediment Trap (TST)3-3Construction Entrance (CE)3-3Temporary Erosion Control Blankets (ECB)3-3   |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3.3                                       | STR<br>TEM<br>2.1<br>2.2<br>2.3<br>2.4<br>2.5<br>2.6<br>2.7<br>2.8<br>2.9<br>2.10<br>SOII  | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-3Construction Entrance (CE)3-3Tree Protection (TP)3-3Temporary Erosion Control Blankets (ECB)3-3STABILIZATION PRACTICES3-3  |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3.3<br>3.4                                | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5<br>.2.6<br>.2.7<br>.2.8<br>.2.9<br>.2.10<br>SOII<br>MAI                                 | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-2Temporary Sediment Trap (TST)3-3Construction Entrance (CE)3-3Tree Protection (TP)3-3Temporary Erosion Control Blankets (ECB)3-3NTENANCE AND INSPECTIONS3-4                   |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3.3<br>3.4<br>3.5                         | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5<br>.2.6<br>.2.7<br>.2.8<br>.2.9<br>.2.10<br>SOII<br>MAI<br>FINA                         | JCTURAL CONTROL PRACTICES3-1PORARY EROSION CONTROL PRACTICES3-1Sediment Fence (GSF)3-1Hay Bale Barrier (HB)3-2Stone Check Dam (SCD)3-2Temporary Pipe Slope Drain (TSD)3-2Temporary Diversion (TD)3-2Temporary Fill Berm (TFB)3-2Temporary Sediment Trap (TST)3-3Construction Entrance (CE)3-3Tree Protection (TP)3-3Temporary Erosion Control Blankets (ECB)3-3NTENANCE AND INSPECTIONS3-4L STABILIZATION3-4 |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>4<br>3.5<br>3         | STR<br>TEM<br>2.1<br>2.2<br>2.3<br>2.4<br>2.5<br>2.6<br>2.7<br>2.8<br>2.9<br>2.10<br>SOII<br>MAI<br>FINA<br>5.1                            | JCTURAL CONTROL PRACTICES  |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3 | STR<br>TEM<br>2.1<br>2.2<br>2.3<br>2.4<br>2.5<br>2.6<br>2.7<br>2.8<br>2.9<br>2.10<br>SOII<br>MAI<br>FINA<br>5.1<br>5.2                     | JCTURAL CONTROL PRACTICES  |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3 | STR<br>TEM<br>.2.1<br>.2.2<br>.2.3<br>.2.4<br>.2.5<br>.2.6<br>.2.7<br>.2.8<br>.2.9<br>.2.10<br>SOII<br>MAI<br>FINA<br>.5.1<br>.5.2<br>.5.3 | JCTURAL CONTROL PRACTICES  |
| 3.1<br>3.2<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3<br>3 | STR<br>TEM<br>2.1<br>2.2<br>2.3<br>2.4<br>2.5<br>2.6<br>2.7<br>2.8<br>2.9<br>2.10<br>SOII<br>MAI<br>FINA<br>5.1<br>5.2                     | JCTURAL CONTROL PRACTICES  |

| 4.0 | APPENDICES4 | <b>l-</b> ] | l |
|-----|-------------|-------------|---|
|     |             |             | • |

#### **APPENDICES**

Appendix A Appendix B Appendix C Maps and Drawings

Inspection and Maintenance Records Supporting Calculations

#### **Contact Information / Responsible Parties:**

Permittee(s): BNE Energy 29 South Main Street Town Center, Suite 200 West Hartford, CT 06107 (800) 450-0503

Contractor Co-Permittee: To be determined

Contractor Operator(s): To be determined

Stormwater Manager and SWPPP Contact(s): BNE Energy 29 South Main Street Town Center Suite 200 West Hartford, CT 06107 (800) 450-0503

This SWPPP was prepared by: Curtis Jones, P.E., LEED AP CIVIL 1 43 Sherman Hill Road Suite D-101 Woodbury, CT 06798

Section 1.0 PROJECT INTRODUCTION

#### **1.0 PROJECT INTRODUCTION**

#### **Project/Site Information:**

| Project/Site Name:  | Wind Colebrook North                            |                              |  |
|---------------------|---|------------------------------|--|
| Location:           | Winsted- Norfolk Road<br>Colebrook, Connecticut |                              |  |
| Latitude/Longitude: | Latitude:<br>41° 58' 30" N                      | Longitude:<br>73° 08' 28'' W |  |

Method for determining latitude/longitude: Google Earth

#### 1.1 SITE SUMMARY

#### 1.1.1 Existing Conditions

Located along the Winsted- Norfolk Road and Rock Hall Road, the project site consists of approximately 125 acres of primarily undeveloped property. Development on the property is limited to a seasonal use building in the southwest corner of the property which services a golf driving range. The Property is located approximately 1,050 feet east of the Norfolk town line town line and is located in Drainage Basin 4302 Mad River which is part of the larger Farmington Regional Basin as indentified in the Atlas of the Public Water Supply Sources and Drainage Basins of Connecticut. The surrounding land is predominately low density residential. The site will be accessed via Rock Hall Road. This access point will be maintained throughout the construction process. Currently, there are no structural stormwater discharge points. All stormwater flows over land to discharge points off site.

#### 1.1.2 Project Description

The Project consists of three GE 1.6MW wind turbines, associated ground equipment, the installation of an access driveway and an electrical connection. The installation of the turbines will require the construction of temporary equipment lay-down areas for the turbines, crane assembly area, access road and associated ground equipment including an electrical collector yard and associated utility infrastructure so that the turbines can be interconnected to the electrical grid. Following completion of the project, all temporary structures will be removed and the site returned to pre-construction conditions as far as practicable.

#### 1.1.3 Site Specific Concerns

The terrain and existing topography of the project site is such that during construction special care will be required to ensure that all BMPs remain intact and are functional.

#### 1.1.4 Construction Schedule

Currently specific dates for construction have not been determined but anticipate construction to begin in Spring 2011. Specific dates will be provided to reviewing officials.

#### **1.2 PROJECT OWNER AND OPERATOR**

The project owner and operator, BNE Energy, will be the responsible entity for completing the project. The address and telephone is: BNE Energy

29 South Main Street Town Center Suite 200 West Hartford, CT 06107 (800) 450-0503

#### 1.3 SOILS, SLOPES, VEGETATION, AND CURRENT DRAINAGE PATTERNS

#### **1.3.1** Soil type(s)

Based upon a review of typical geologic conditions and the National Soil Cooperative Survey, the soils have been classified as (1) Bice- Millsite complex 3-15% slopes, very rocky, (2) Bice-Millsite complex 15-45% slopes, very rocky, (3) Bice fine sandy loam 3-8% slopes, very stony, (4) Bice fine sandy loam 8-15% slopes, very stony, (5) Bice fine sandy loam 15-25% slopes, very stony, (6) Schroon fine sandy loam 2-15% slopes, very stony, (7) Shelburne fine sandy loam 3-8% slopes, (8) Shelburne fine sandy loam 8-15% slopes, (9) Shelburne fine sandy loam 8-15% slopes, very stony and (10) Brayton- Loonmeadow complex extremely stony.

#### 1.3.2 Slopes

The project site consists of varying slope conditions ranging from relatively flat conditions in the central portion of the site and moderately steeper slopes in the extreme easterly and westerly portion of the site. The proposed towers are to be located on gentle slopes.

#### 1.3.3 Drainage Patterns

Existing site topography is such that runoff migrates, typically via overland sheet flow from the easterly and westerly upland portions of the site towards the wetlands in the center portion of the site. The flow through the wetlands is generally from the north to the south and southeast through the Mill Brook which is a perennial watercourse.

#### 1.3.4 Vegetation

Six major habitat types have been identified in the Terrestrial Wildlife Habitat & Wetland Impact Analysis prepared by VHB, Inc. These types include (1) second growth Northern Hardwood forest, (2) second growth Northern Hardwoods- Hemlock- White Pine forest, (3) early successional Northern Hardwood forest, (4) Palustrine forested wetlands (which include Mill Brook, a pereenial watercourse), (5) Palustrinescrub- shrub- emergent wetlands and (6) maintained lawn (golf driving range).

#### **1.4** SITE FEATURES AND SENSITIVE AREAS TO BE PROTECTED

#### 1.4.1 Receiving Waters and TMDL Applicability

Mill Brook runs through the property and ultimately receives the storm water runoff from the site.. This water body is not considered impaired and is not listed on the most current 303(d) listing of impaired waterways.

# 1.4.2 Wetlands

Within to the property boundary a wetland has been identified and delineated. Mitigation and impacts are discussed in the environmental assessment completed by VHB, Inc.

Section 2.0 CONSTRUCTION ACTIVITIES

# 2.0 CONSTRUCTION ACTIVITIES

#### 2.1 DESCRIPTION OF CONSTRUCTION ACTIVITY

Prior to construction BNE will complete all pre-construction planning activities. BNE will continue to consult with municipalities, state agencies and federal agencies, as applicable, and will conduct site surveys to determine construction methodologies and procedures to minimize adverse effects to the environment and public.

Construction will typically consist of activities such as:

- Surveys to stake access roads and structural locations
- Wetland delineation
- Geotechnical investigations
- Establishment of construction staging area
- Installation of sediment and erosion control devices
- Excavation and installation of access roads
- Excavation and installation of lay-down and equipment assembly areas
- Excavation and installation of foundations and erection of new structures
- Installation of conductors
- Restoration of site, including re-establishment of vegetative areas

#### 2.2 CONSTRUCTION SITE ESTIMATES

The following are estimates of the construction site:

Property Area: 125 acres Area to be disturbed: 7.86 acres Percentage impervious area before construction: 0% Runoff coefficient number (RCN) before construction: 58 Percentage impervious area after construction: 0.98% Runoff coefficient number (RCN) after construction: 60 Summary of peak flows: See 2.3.3 Summary of groundwater recharge: 0.015 AC-FT Section 3.0 BEST MANAGEMENT PRACTICES

# **3.0 BEST MANAGEMENT PRACTICES**

Soil erosion and sediment controls are measures that are used to reduce the amount of soil particles that are carried from a land area and deposited in receiving waters. This section provides a general description of the most appropriate control measures proposed for the Project. The permittee's construction contractor(s) and their subcontractors will be responsible for amending the erosion and sediment controls in the SWPPP for their portion(s) of the project as needed. Based on field conditions at the time of construction, the contractors or subcontractors may adjust the locations and types of BMPs so that erosion and sedimentation are controlled to the maximum extent practicable. However, in no case will modifications to the SWPPP result in any less stringent erosion and sedimentation control measures than specified herein.

# 3.1 STRUCTURAL CONTROL PRACTICES

Structural control practices divert flows from exposed soils, store water flow, or otherwise limit runoff from exposed areas of the site. Such practices may include silt fences, drainage swales, sediment traps, check dams, subsurface drains, pipe slope drains, rock outlet protection (rip-rap), reinforced soil retaining systems, and temporary or permanent sediment basins. Some of these practices may be used as both temporary and permanent control measures. Structural control practices should be placed in upland areas to the degree practicable to prevent erosion and reduce sedimentation in lower elevation areas. See Appendix A for additional information.

# 3.2 TEMPORARY EROSION CONTROL PRACTICES

Erosion and sediment control measures will be in place prior to the initiation of soil disturbing activities and will be maintained throughout construction. The contractor may need erosion control measures in other locations of the project as work progresses to keep sediment from leaving the construction site. These measures will be determined by the contractor in the field; if measures are changed in the field, the SWPPP must be modified accordingly. All temporary erosion controls will be removed after the protected area is finally stabilized. The minimum temporary erosion and sediment control practices that will be used for the Project are discussed in the following sections. See Appendix D for additional information.

# 3.2.1 Sediment Fence (GSF)

Will retain sediment from small disturbed areas. Sediment fence will be placed along slopes as shown on construction details. The contractor will use his best judgment to install additional sediment fence as necessary to prevent loss of sediment. Refer to section 5-11 of 2002 Connecticut Guidelines for Soil Erosion and Sediment Control.

Maintenance: Inspect the silt fence at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs. When used for dewatering operations, inspect frequently before, during and after pumping operations. Remove the sediment deposits, or if room allows, install a second silt fence up slope from the existing fence when deposits reach approximately one half the height of the existing fence. Replace or repair within 24 hours of an observed failure. Refer to Connecticut Guidelines for Soil Erosion and Sediment Control figure GF-5 for troubleshooting failures. Maintain silt fence until the contributing area is stabilized.

# 3.2.2 Hay Bale Barrier (HB)

Will retain sediment from small disturbed areas. Hay bales will be placed along slopes as shown on construction details. The contractor will use his best judgment to install additional hay bales as necessary to prevent loss of sediment. Refer to section 5-11 of 2002 Connecticut Guidelines for Soil and Sediment Control.

Maintenance: Inspect the hay bale barrier at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs. When used for dewatering operations, inspect frequently before, during and after pumping operations. Remove the sediment deposits, or if room allows, install a secondary barrier up slope from the existing barrier when deposits reach approximately one half the height of the barrier. Replace or repair within 24 hours of an observed failure. Refer to Connecticut Guidelines for Soil Erosion and Sediment Control figure HB-5 for troubleshooting failures. Maintain hay bale barrier until the contributing area is stabilized.

#### 3.2.3 Stone Check Dam (SCD)

Will be used to reduce velocity of concentrated flows, thus reducing erosion of the drainage way.

Maintenance: Inspect the stone check dam at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs. Remove the sediment deposits when deposits reach approximately one half the height of the Check dam. Replace or repair within 24 hours of an observed failure. Maintain until the contributing area is stabilized.

#### 3.2.4 Temporary Pipe Slope Drain (TSD)

Will be used to carry water over excessive changes in grade. TSD's will convey concentrated stormwater runoff flows without causing erosion problems either on or at the toe of the slope.

Maintenance: Inspect the temporary pipe slope drain at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs. Repair damage as necessary. Avoid the placement of any material on the top of the pipe and prevent vehicular traffic from crossing the slope drain.

#### 3.2.5 Temporary Diversion (TD)

Will be used to divert sediment laden runoff from a disturbed area to a sediment trapping facility.

Maintenance: When the temporary diversion is located within close proximity to on going construction activities, inspect the diversion at the end of each work day and immediately repair damage caused by construction equipment. Otherwise, inspect the temporary diversion and associated measures at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs. Repair within 24 hours of an observed failure.

# 3.2.6 Temporary Fill Berm (TFB)

Will be used to divert runoff from unprotected fill slopes during construction to a stabilized outlet or sediment trapping facility.

Maintenance: Inspect the temporary fill berm and associated controls at the end of each work day to ensure the criteria for installing the measures have been met. Determine if repair or modification is needed. This measure is temporary and under most situations will be covered the next work day. Maintenance requirements should be minimal. The contractor should avoid placing other material over the berm and construction traffic should not be allowed to cross.

# 3.2.7 Temporary Sediment Trap (TST)

Will be used to detain sediment laden runoff from small disturbed areas long enough to allow the majority of sediment to settle out.

Maintenance: Inspect the temporary sediment trap and associated controls at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs. Check the outlet to verify that it is structurally sound and has not been damaged by erosion or construction equipment. The height of the stone outlet should be maintained at least 1 foot below the crest of the embankment. When sediment has accumulated more than one quarter of the minimum wet storage volume, dewater and remove sediment as necessary to restore the trap to its original dimensions.

# 3.2.8 Construction Entrance (CE)

Will be used to reduce tracking of sediment off site to paved areas.

Maintenance: Maintain the entrance in a condition which will prevent tracking and washing of sediment onto paved surfaces. Provide periodic top dressing with additional stone or additional length as required. Immediately remove all sediment spilled, dropped, washed or tracked onto paved surfaces.

# 3.2.9 Tree Protection (TP)

Will be used to ensure the survival of existing desirable trees for their effectiveness in soil erosion and sediment control during construction.

Maintenance: Inspect tree protection zones weekly during site construction for damage to the tree crown, trunk and root system. When trees have been damaged or the protection zone has been compromised, consult an arborist licensed in CT to determine how damage should be addressed.

# 3.2.10 Temporary Erosion Control Blankets (ECB)

Will be used to provide temporary surface protection to disturbed soils to absorb raindrop impact and to reduce sheet and rill erosion until vegetation is established.

Maintenance: Inspect temporary erosion control blankets at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inches or greater to determine maintenance needs. Repair any dislodged or failed blankets immediately.

# 3.3 SOIL STABILIZATION PRACTICES

Soil stabilization involves covering disturbed soils with grass, mulch, straw, geotextiles, trees, vines, or shrubs. Stabilization practices for exposed disturbed soils are extremely important while

conducting construction activities. Vegetative cover serves to reduce the erosion potential by absorbing the energy of raindrops, promoting infiltration in lieu of runoff, and reducing the velocity of runoff. Stabilization measures shall be initiated as soon as practicable, but no more than 14 days after construction activities have temporarily or permanently ceased on any portion of the site.

## 3.4 MAINTENANCE AND INSPECTIONS

All erosion and sediment control devices shall be installed pursuant to the specifications in the construction details and in accordance with the Connecticut General Permit for the Discharge of Stormwater and Dewatering Wastewaters Associated with Construction Activities . They will be maintained so that they remain effective at all times.

Erosion and sediment control devices will be inspected by qualified personnel at least once every seven calendar days or at least once every 14 calendar days and within 24 hours of each 0.5-inch or greater rainfall event. During each inspection, the construction inspector will complete the Inspection and Maintenance Report Form located in the appendix. This form will be copied and used as necessary. Ineffective temporary erosion control measures will be repaired or replaced before the next storm event or as soon as practicable. The permittee will immediately install additional temporary erosion control devices in any area deemed in need of protection.

Following temporary or final stabilization, inspections must be conducted at least once a month. If construction has been halted due to frozen conditions, regular inspections are not mandatory until one month before the expected thaw. If vegetation establishment is not satisfactory, special steps to correct the problem will be implemented such as over seeding, mulching, sodding, or the use of erosion control blankets. Once a definable area of the construction site has been finally stabilized, no further inspection requirements apply to that area.

#### 3.5 FINAL STABILIZATION

# 3.5.1 Seeding

The contractor will be responsible for labor, materials, tools, equipment, and other related items required for preparing ground, providing for sowing of seeds, fertilizing, mulching and top dressing, and other management practices required for erosion control and to achieve final stabilization. It will be the contractor's responsibility to make sure that the soil seedbed is not blown, washed, or otherwise removed from the site. The contractor will make repairs (including replacement of lost topsoil and mulch) to the seedbed preparation site in the event of heavy rain, wind, or other natural events that cause damage. When practicable, native plant species should be used for landscaping.

# 3.5.2 Fertilizer

Soil in areas of disturbance may need supplementation from fertilizer. Soil tests may be necessary to determine the most appropriate fertilizer for each location. Once applied, the fertilizer will be worked into the soil to limit exposure to stormwater. Fertilizer spills will be cleaned up immediately and will not be applied along or in a waterway.

# 3.5.3 Mulching

Mulching will be used in conjunction with both temporary and permanent seeding practices to enhance success by providing erosion protection prior to the onset of vegetative growth. Mulches enhance plant establishment by moderating soil temperatures and conserving moisture. After seeding, straw or hay mulch will be applied at a rate of two to three tons per acre on the disturbed areas. Other forms of mulch will be applied at a rate designated by the Project Engineer. Mulch will not be applied in wetlands, on lawns, and areas where hydro-mulch is used. Mulch will be anchored immediately after placement on steep slopes and stream banks. Mulch will be held in place by a very thin covering of topsoil, small brush, pins, stakes, wire mesh, asphalt binder, or other adhesive material approved by the project engineer.

# 3.5.4 Topsoiling

Topsoil should be applied in areas where the subsoil or existing surface soil does not provide an adequate growth medium for the desired vegetation, where soil is too shallow to provide adequate rooting depth, or where the soil contains substances toxic to the desired vegetation. Topsoil shall be reasonably free from subsoil and stumps, roots, brush, stones, and clay lumps or similar objects.

# 3.5.5 Temporary Control Removal

Temporary erosion controls will be left in place until the Project site is stabilized with a uniform vegetative cover of 70 percent density of the native background vegetative cover on all unpaved areas. Following re-vegetation, the permittee will conduct periodic site visits to make sure that vegetation establishment is satisfactory. If sufficient vegetative cover has not been achieved, additional restoration measures will be implemented. Inspection results will be documented using the Inspection and Maintenance Report Form found in the appendix. All temporary soil erosion and sediment control measures will be removed and disposed of after final site stabilization is achieved and before submitting the Notice of Termination (NOT) to the CT DEP.

Section 4.0 EROSION CONTROL PLAN APPENDICES

# 4.0 SWPPP APPENDICES

Attach the following documentation to the SWPPP in the following appendices.

Appendix A – Maps and Drawings

- Site Maps
- Site Plan


Appendix B – Inspection and Maintenance Records


- Inspection & Maintenance Log
- Inspection Report
- Maintenance Report

Appendix C – Supporting Calculations

• Calculations for Swales, Culverts, Riprap and Temporary Sediment Traps

Appendix A
MAPS AND DRAWINGS





Soil Map-State of Connecticut

|                        | MAP LEGEND             |                       |                    | MAP INFORMATION  |  |  |
|------------------------|------------------------|-----------------------|--------------------|--|--|--|
| Area of Interest (AOI) |                        | (0) Very Stony Spot   |                    | Map Scale: 1:2,900 if printed on D size (22" × 34") sheet.   |  |  |
|                        | Area of Interest (AOI) | *                     | Wet Spot           | The soil surveys that comprise your AOI were mapped at 1:12,00   |  |  |
| Soils                  | Soil Map Units         | •                     | Other              | Please rely on the bar scale on each map sheet for accurate map  |  |  |
| Special Point Features |                        | Special Line Features |                    | measurements.  |  |  |
| opecial                | Blowout                | 2                     | Gully              | Source of Map: Natural Resources Conservation Service<br>Web Soil Survey URL: http://websoilsurvey.nrcs.usda.gov               |  |  |
| M                      | Borrow Pit             | 1.0.0                 | Short Steep Slope  | Coordinate System: UTM Zone 18N NAD83  |  |  |
| 1000                   | Clay Spot              | ~ ·                   | Other              | This product is generated from the USDA-NRCS certified data as   |  |  |
| *                      |                        | Political F           | eatures            | the version date(s) listed below.  |  |  |
| •                      | Closed Depression      | •                     | Cities             | Soil Survey Area: State of Connecticut   |  |  |
| ×                      | Gravel Pit             | Water Fea             | itures             | Survey Area Data: Version 8, Dec 13, 2010  |  |  |
| ~                      | Gravelly Spot          |                       | Oceans             | Date(s) aerial images were photographed: 8/14/2006   |  |  |
| ø                      | Landfill               | ~                     | Streams and Canals | The orthophoto or other base map on which the soil lines were  |  |  |
| A                      | Lava Flow              | Transport             |                    | compiled and digitized probably differs from the background<br>imagery displayed on these maps. As a result, some minor shifti |  |  |
| -                      | Marsh or swamp         | * * *                 | Rails              | of map unit boundaries may be evident.   |  |  |
| 8                      | Mine or Quarry         | nterstate Highways    |                    |  |  |  |
| 0                      | Miscellaneous Water    | ~                     | US Routes          |  |  |  |
| ۲                      | Perennial Water        |                       | Major Roads        |  |  |  |
| ~                      | Rock Outcrop           | ~                     | Local Roads        |  |  |  |
| +                      | Saline Spot            |                       |                    |  |  |  |
|                        | Sandy Spot             |                       |                    |  |  |  |
| -                      | Severely Eroded Spot   |                       |                    |  |  |  |
| ٥                      | Sinkhole               |                       |                    |  |  |  |
| 3                      | Slide or Slip          |                       |                    |  |  |  |
| ø                      | Sodic Spot             |                       |                    |  |  |  |
| =                      | Spoil Area             |                       |                    |  |  |  |
|                        | Stony Spot             |                       |                    |  |  |  |

Natural Resources Conservation Service Web Soil Survey National Cooperative Soil Survey 3/13/2011 Page 2 of 3

|   | State of Connecticut (CT  | 600)         |                |
|---|---|--------------|----------------|
| Map Unit Symbol   | Map Unit Name   | Acres in AOI | Percent of AOI |
| 61C   | Canton and Charlton soils, 8 to 15 percent slopes, very stony       | 0.3          | 0.1%           |
| 62D   | Canton and Charlton soils, 15 to 35 percent slopes, extremely stony | 0.4          | 0.1%           |
| 412B  | Bice fine sandy loam, 3 to 8 percent slopes                         | 15.4         | 3.0%           |
| 412C  | Bice fine sandy loam, 8 to 15 percent slopes                        | 15.3         | 3.0%           |
| 413C  | Bice-Millsite complex, 3 to 15 percent slopes, very rocky           | 64.9         | 12.8%          |
| 413E  | Bice-Millsite complex, 15 to 45 percent slopes, very rocky          | 23.5         | 4.6%           |
| 417B  | Bice fine sandy loam, 3 to 8 percent slopes, very stony             | 58.1         | 11.5%          |
| 417C  | Bice fine sandy loam, 8 to 15 percent slopes, very stony            | 93.1         | 18.4%          |
| 417D Bice fine sandy loam, 15 to 25 percent slopes,<br>very stony |   | 18.3         | 3.6%           |
| 418C Schroon fine sandy loam, 2 to 15 percent slopes, very stony  |   | 57.5         | 11.3%          |
| 420B  | Schroon fine sandy loam, 3 to 8 percent slopes                      | 0.6          | 0.1%           |
| 424C  | Shelburne fine sandy loam, 8 to 15 percent slopes                   | 9.1          | 1.8%           |
| 425B Shelburne fine sandy loam, 3 to 8 percent slopes, very stony |   | 21.1         | 4.2%           |
| 425C  | Shelburne fine sandy loam, 8 to 15 percent slopes, very stony       | 4.9          | 1.0%           |
| 426D  | Shelburne fine sandy loam, 15 to 35 percent slopes, extremely stony | 2.8          | 0.6%           |
| 427B  | Ashfield fine sandy loam, 2 to 8 percent slopes, very stony         | 17.3         | 3.4%           |
| 427C  | Ashfield fine sandy loam, 8 to 15 percent slopes, very stony        | 12.3         | 2.4%           |
| 428A  | Ashfield fine sandy loam, 0 to 3 percent slopes                     | 2.9          | 0.6%           |
| 437   | Wonsqueak mucky peat  | 22.6         | 4.5%           |
| 443   | Brayton-Loonmeadow complex, extremely stony                         | 65.9         | 13.0%          |
| Totals for Area of Intere   | st  | 506.5        | 100.0%         |

# Map Unit Legend



Natural Resources Conservation Service Web Soil Survey National Cooperative Soil Survey 3/13/2011 Page 3 of 3

# Appendix B INSPECTION AND MAINTENANCE RECORDS

### INSPECTOR CERTIFICATION

| Project:          | Wind Colebrook North  |
|-------------------|-----------------------|
|                   | Winsted- Norfolk Road |
| Project Location: | Colebrook North       |
| Contractor:       |                       |
| Address:          |                       |
|                   |                       |
|                   |                       |
| Phone:            |                       |
| Fax:              |                       |

# CONSTRUCTION INSPECTION & MAINTENANCE LOG

| Date | Activity   | Description | (1) Report No. |
|------|--|-------------|----------------|
|      | <ul><li>Inspection</li><li>Maintenance</li></ul> | By:         |                |

| General Information  |   |                      |               |  |  |  |  |
|--|---|----------------------|---------------|--|--|--|--|
| Project Name:  | Wind Colebrook Nort   | h                    |               |  |  |  |  |
| Location:  | Winsted- Norfolk Roa<br>Colebrook, Connectic                                |                      |               |  |  |  |  |
| CT DEP Tracking No.  |   | (1) Report           | No.           |  |  |  |  |
| Date of Inspection:  |   | Start / End<br>Time: |               |  |  |  |  |
| Inspector's Name(s):   |   |                      |               |  |  |  |  |
| Inspector's Title(s):  |   |                      |               |  |  |  |  |
| Inspector's Contact<br>Information:  |   |                      |               |  |  |  |  |
| Describe present phase<br>of construction:   | 1 I   |                      |               |  |  |  |  |
| Type of Inspection:<br>Regular Pre-stor  | rm event During   | storm event 🖵 Pos    | t-storm event |  |  |  |  |
| Weather Information  |   |                      |               |  |  |  |  |
| Has it rained since the last inspection?<br>Yes No   |   |                      |               |  |  |  |  |
| If yes, provide:<br>Storm Start Date & Time: Storm Duration (hrs): Approximate Rainfall<br>(in): |   |                      |               |  |  |  |  |
| Weather at time of this in   | spection?   |                      |               |  |  |  |  |
| Discharge Information (  | (A)   |                      |               |  |  |  |  |
| Do you suspect that disch  | Do you suspect that discharges may have occurred since the last inspection? |                      |               |  |  |  |  |
| Are there any discharges<br>Yes No   | at the time of inspectio  | n?                   |               |  |  |  |  |
| Describe location of any   | discharges from the site  | ::                   |               |  |  |  |  |

# CONSTRUCTION SITE INSPECTION REPORT

#### SITE-SPECIFIC BMPs

| (B) | BMP Description | BMP Installed<br>and Operating<br>Properly? | Corrective Action Needed | Date for corrective<br>action / responsible<br>party |
|-----|-----------------|---|--------------------------|--|
| 1   |                 | □Yes □No                                    |                          |  |
| 2   |                 | □Yes □No                                    |                          |  |
| 3   |                 | □Yes □No                                    |                          |  |
| 4   |                 | □Yes □No                                    |                          |  |
| 5   |                 | □Yes □No                                    |                          |  |
| 6   |                 | □Yes □No                                    |                          |  |
| 7   |                 | □Yes □No                                    |                          |  |
| 8   |                 | □Yes □No                                    |                          |  |
| 9   |                 | □Yes □No                                    |                          |  |
| 10  |                 | □Yes □No                                    |                          |  |
| 11  |                 | □Yes □No                                    |                          |  |
| 12  |                 | □Yes □No                                    |                          |  |
| 13  |                 | Yes No                                      |                          |  |
| 14  |                 | Yes No                                      |                          |  |
| 15  |                 | □Yes □No                                    |                          |  |
| 16  |                 | □Yes □No                                    |                          |  |
| 17  |                 | □Yes □No                                    |                          |  |
| 18  |                 | □Yes □No                                    |                          |  |
| 19  |                 | □Yes □No                                    |                          |  |

# OVERALL SITE ISSUES

| (C) | BMP/activity   | Implemented? | Maintained? | Corrective<br>Action | Date for corrective<br>action/responsible<br>person |
|-----|--|--------------|-------------|----------------------|---|
| 1   | Are all slopes and<br>disturbed areas<br>not actively being<br>worked properly<br>stabilized?  | □Yes □No     | □Yes □No    |                      |   |
| 2   | Are natural<br>resource areas<br>(e.g., streams,<br>wetlands, mature<br>trees, etc.)<br>protected with<br>barriers or similar<br>BMPs? | □Yes □No     | □Yes □No    |                      |   |
| 3   | Are perimeter<br>controls and<br>sediment barriers<br>adequately<br>installed (keyed<br>into substrate) and<br>maintained?             | □Yes □No     | □Yes □No    |                      |   |
| 4   | Are discharge<br>points and<br>receiving waters<br>free of sediment<br>deposits?   | □Yes □No     | □Yes □No    |                      |   |
| 5   | Are storm drain<br>inlets properly<br>protected?   | □Yes □No     | □Yes □No    |                      |   |
| 6   | Is there evidence<br>of sediment being<br>tracked into the<br>street?  | □Yes □No     | □Yes □No    |                      |   |
| 7   | Is trash/litter from<br>work areas<br>collected and<br>placed in covered<br>dumpsters?   | □Yes □No     | □Yes □No    |                      |   |

| (C) | BMP/activity   | Implemented? | Maintained? | Corrective<br>Action | Date for corrective<br>action/responsible<br>person |
|-----|--|--------------|-------------|----------------------|---|
| 8   | Are washout<br>facilities (e.g.,<br>paint, stucco,<br>concrete)<br>available, clearly<br>marked, and<br>maintained?                                  | □Yes □No     | □Yes □No    |                      |   |
| 9   | Are vehicle and<br>equipment<br>fueling, cleaning,<br>and maintenance<br>areas free of<br>spills, leaks, or<br>any other<br>deleterious<br>material? | □Yes □No     | □Yes □No    |                      |   |
| 10  | Are materials that<br>are potential<br>stormwater<br>contaminants<br>stored inside or<br>under cover?  | □Yes □No     | □Yes □No    |                      |   |
| 11  | Are non-<br>stormwater<br>discharges (e.g.,<br>wash water,<br>dewatering)<br>properly<br>controlled?   | □Yes □No     | □Yes □No    |                      |   |
| 12  | (Other)  | □Yes □No     | □Yes □No    |                      |   |
| 13  | (Other)  | □Yes □No     | □Yes □No    |                      |   |

| (C) | BMP/activity | Implemented? | Maintained? | Corrective<br>Action | Date for corrective<br>action/responsible<br>person |
|-----|--------------|--------------|-------------|----------------------|---|
|     |              |              |             |                      |   |

#### GENERAL INSPECTION COMMENTS AND EXPLANATION

| General Inspection Comments (D)                                      |  |
|--|--|
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
|  |  |
| Is other descriptive information attached to this inspection report? |  |
| $\Box$ Yes $\Box$ No   |  |

Plan Information (E)

Were all current plan BMP's in place at the time of inspection?

□Yes □No

Are additional BMP's required?

□Yes □No

Does the plan need to be updated?

□Yes □No

Explanation of additional BMP and Plan update requirements:

#### Certification statement:

I certify that I have thoroughly and completely reviewed the Stormwater Pollution Control Plan for the site. I further certify, based on such review and in my professional judgment, that the Stormwater Pollution Control Plan has been prepared in accordance with the Connecticut Guidelines for Soil Erosion and Sediment Control, as amended, and the conditions for the General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities issued on October 1, 2002 (or as reissued or modified), and the controls required for such Plan are appropriate for the site. I am aware that there are significant penalties for false statements in this certification, including the possibility of fine and imprisonment for knowingly making false statements.

| Name:          |       |  |
|----------------|-------|--|
| (Please print) |       |  |
| Signature:     |       |  |
| <b>T1</b>      |       |  |
| Title:         | Date: |  |

.

| General Information                         |   |  |  |  |
|---|---|--|--|--|
| Project Name:                               | Wind Colebrook North                            |  |  |  |
| Location:                                   | Winsted- Norfolk Road<br>Colebrook, Connecticut |  |  |  |
| CT DEP Tracking No.:                        | (1) Report No.                                  |  |  |  |
| Date of Maintenance:                        | Start / End<br>Time:                            |  |  |  |
| Describe present phase<br>of construction:  |   |  |  |  |
| Type of Maintenance:                        |   |  |  |  |
| Regular Pre-stor<br>Maintenance Information | <b>A</b>  |  |  |  |
| Inspection Report                           | Maintenance performed:                          |  |  |  |
| Reference (No., Item)                       | mannenance performed.                           |  |  |  |
|   |   |  |  |  |
| Performed by:                               |   |  |  |  |
| Inspection Report<br>Reference (No., Item)  | Maintenance performed:                          |  |  |  |
| Performed by:                               |   |  |  |  |
| Inspection Report<br>Reference (No., Item)  | Maintenance performed:                          |  |  |  |
| Performed by:                               |   |  |  |  |
| Inspection Report<br>Reference (No., Item)  | Maintenance performed:                          |  |  |  |
| Performed by:                               |   |  |  |  |
| Inspection Report<br>Reference (No., Item)  | Maintenance performed:                          |  |  |  |
| Performed by:                               |   |  |  |  |

#### CONSTRUCTION SITE MAINTENANCE REPORT

| Inspection Deport      | Maintananaa narfarmad  |
|------------------------|------------------------|
| Inspection Report      | Maintenance performed: |
| Reference (No., Item)  |                        |
|                        |                        |
|                        |                        |
| Performed by:          |                        |
|                        | Malutana a sufare a la |
| Inspection Report      | Maintenance performed: |
| Reference (No., Item)  |                        |
|                        |                        |
|                        |                        |
| Performed by:          |                        |
|                        | Maintananaa narfarmad  |
| Inspection Report      | Maintenance performed: |
| Reference (No., Item)  | -                      |
|                        |                        |
|                        |                        |
| Performed by:          |                        |
| Inspection Report      | Maintenance performed: |
| Reference (No., Item)  |                        |
| Reference (ivo., item) | -                      |
|                        |                        |
|                        |                        |
| Performed by:          |                        |
| Inspection Report      | Maintenance performed: |
| Reference (No., Item)  |                        |
|                        | -                      |
|                        |                        |
|                        |                        |
| Performed by:          |                        |
| Inspection Report      | Maintenance performed: |
| Reference (No., Item)  |                        |
|                        |                        |
|                        |                        |
| D C 11                 |                        |
| Performed by:          |                        |
| Inspection Report      | Maintenance performed: |
| Reference (No., Item)  |                        |
|                        |                        |
|                        |                        |
| Performed by:          |                        |
| Inspection Report      | Maintenance performed: |
|                        |                        |
| Reference (No., Item)  | 4                      |
|                        |                        |
|                        |                        |
| Performed by:          |                        |

Certification statement:

I certify that I have thoroughly and completely reviewed the Stormwater Pollution Control Plan for the site. I further certify, based on such review and in my professional judgment, that the Stormwater Pollution Control Plan has been prepared in accordance with the Connecticut Guidelines for Soil Erosion and Sediment Control, as amended, and the conditions for the General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities issued on October 1, 2002 (or as reissued or modified), and the controls required for such Plan are appropriate for the site. I am aware that there are significant penalties for false statements in this certification, including the possibility of fine and imprisonment for knowingly making false statements.

| Name:      |       |
|------------|-------|
| Signature: |       |
| Title:     | Date: |

Appendix C
SUPPORTING CALCULATIONS

# CALCULATIONS FOR SWALES, CULVERTS, RIP RAP AND TEMPORARY SEDIMENT TRAPS

# DRAINAGE CALCULATIONS FOR TEMPORARY DIVERSION #1 (TD1)

# 10-YEAR DESIGN STORM **3-18-11**

# **Rational Method:**

Q = CIA Where: Q = flow rate (cfs) C = runoff coefficient I = rainfall intensity (in/hr) A = area (ac.)

Total area contributing to swale: 2.13 ac. Proposed Land Cover Grass = 0.15 ac. Wooded = 1.98 ac.

 $C = [(.3^*.15)+(.2^*1.98)]/2.13 = 0.21$ Time of Concentration = 20 minutes  $\therefore$  I = 3.6 in/hr

Q = C\*I\*A = .21 \* 3.6 \* 2.13 = 1.62 cfs

Velocity in grass-lined swale at 5% slope = 3.34 fps.

| Worksheet TD1          |           |             |        |          |    |       |      |
|------------------------|-----------|-------------|--------|----------|----|-------|------|
| Flow Element           |           | Trapezoidal |        |          |    |       |      |
| Method                 |           |             | 's For |          |    |       |      |
| Solve For              |           |             |        |          |    |       |      |
| Solve For              | Una       | innei       | Dept   | <u> </u> |    |       |      |
| Input Data             |           |             | -      |          |    |       |      |
| Mannings Coel          | fic 0.030 |             |        |          |    |       |      |
| Channel Slope          | .050000   | ft/ft       |        |          |    |       |      |
| Left Side Slope        | 2.00      | H:\         | 1      |          |    |       |      |
| <b>Right Side Slop</b> | e 2.00    | H:\         | 1      |          |    |       |      |
| Bottom Width           | 2.00      | ft          |        |          |    |       |      |
| Discharge              | 1.60      | cfs         |        |          |    |       |      |
|                        |           |             | _      |          |    |       |      |
| Results                |           |             |        |          |    |       |      |
| Depth                  | 0.20      | ft          |        |          |    |       |      |
| Flow Area              | 0.5       | ft²         |        |          |    |       |      |
| Wetted Perim           | 2.89      | ft          |        |          |    |       |      |
| Top Width              | 2.80      | ft          |        |          |    |       |      |
| Critical Depth         | 0.25      | ft          |        |          |    |       |      |
| Critical Slope         | 0.023407  | ft/ft       |        |          |    |       |      |
| Velocity               | 3.34      | ft/s        | diama. | GRA      | 53 | LINED | SUAL |
| Velocity Head          | 0.17      | ft          |        |          |    |       |      |
| Specific Energ         | 0.37      | ft          |        |          |    |       |      |
| Froude Numb            | 1.42      |             |        |          |    |       |      |
|                        |           |             |        |          |    |       |      |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 10:18:08 AM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

## DRAINAGE CALCULATIONS FOR TEMPORARY DIVERSION #2 (TD2)

### 10-YEAR DESIGN STORM **3-18-11**

### **Rational Method:**

Q = CIA Where: Q = flow rate (cfs) C = runoff coefficient I = rainfall intensity (in/hr) A = area (ac.)

Total area contributing to swale: 0.73 ac. Proposed Land Cover Grass = 0.05 ac. Wooded = 0.68 ac.

 $C = [(.3^*.05)+(.2^*0.68)]/.73 = 0.21$ Time of Concentration = 12 minutes  $\therefore$  I = 4.5 in/hr

 $Q = C^*I^*A = .21 * 4.5 * 0.73 = 0.70 \text{ cfs}$ 

Velocity in grass-lined swale at max 14% slope = 3.51 fps.

| Project Descript | ion             |           |     | 10.10.1 |       |       |
|------------------|-----------------|-----------|-----|---------|-------|-------|
| Worksheet        | TD2             |           |     | _       |       |       |
| Flow Element     | Trapezoidal Cha |           |     |         |       |       |
| Method           | Mar             | nning's l | orm | u       |       |       |
| Solve For        | Cha             | innel De  | pth | -       |       |       |
| Input Data       |                 |           |     |         |       |       |
| Mannings Coeff   | ic 0.030        |           |     |         |       |       |
| Channel Slope    | 140000          | ft/ft     |     |         |       |       |
| Left Side Slope  | 2.00            | H:V       |     |         |       |       |
| Right Side Slope | 2.00            | H:V       |     |         |       |       |
| Bottom Width     | 2.00            | ft        |     |         |       |       |
| Discharge        | 0.70            | cfs       |     |         |       |       |
|                  |                 |           |     |         |       |       |
| Results          |                 |           |     |         |       |       |
| Depth            | 0.09            | ft        |     |         |       |       |
| Flow Area        | 0.2             | ft²       |     |         |       |       |
| Wetted Perim     | 2.41            | ft        |     |         |       |       |
| Top Width        | 2.37            | ft        |     |         |       |       |
| Critical Depth   | 0.15            | ft        |     |         |       |       |
| Critical Slope   | 0.026813        | ft/ft     |     |         |       |       |
| Velocity         | 3.51            | ft/s 💰    | -   | GRASS   | LINED | SWALE |
| Velocity Head    | 0.19            | ft        |     |         |       |       |
| Specific Energ   | 0.28            | ft        |     |         |       |       |
| Froude Numb      | 2.13            |           |     |         |       |       |
| Flow Type 🛛 🕯 ม  | percritical     |           |     |         |       |       |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 10:53:24 AM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

## DRAINAGE CALCULATIONS FOR TEMPORARY DIVERSION #3 (TD3)

### 10-YEAR DESIGN STORM **3-18-11**

### **Rational Method:**

Q = CIAWhere: Q = flow rate (cfs)C = runoff coefficientI = rainfall intensity (in/hr)A = area (ac.)

Total area contributing to swale: 0.62 ac. Proposed Land Cover Grass = 0.06 ac. Wooded = 0.56 ac.

C = [(.3\*.06)+(.2\*0.56)]/0.62 = 0.21 Time of Concentration = 25 minutes  $\therefore$  I = 3.2 in/hr

 $Q = C^*I^*A = .21 * 3.2 * 0.62 = 0.42 cfs$ 

Velocity in grass-lined swale at 12% slope = 2.78 fps.

| Worksheet               | TD       | 3         |        |       |       |
|-------------------------|----------|-----------|--------|-------|-------|
| Flow Element            | Tra      | pezoidal  | Cha    |       |       |
| Method                  |          | nning's F |        |       |       |
| Solve For               | Cha      | nnel De   | pth    |       |       |
|                         |          |           |        |       |       |
| Input Data              |          |           |        |       |       |
| Mannings Coeff          | ic 0.030 |           |        |       |       |
| Channel Slope           | 120000   | ft/ft     |        |       |       |
| Left Side Slope         | 2.00     | H:V       |        |       |       |
| <b>Right Side Slope</b> | 2.00     | H:V       |        |       |       |
| Bottom Width            | 2.00     | ft        |        |       |       |
| Discharge               | 0.42     | cfs       |        |       |       |
|                         |          |           |        |       |       |
| Results                 |          |           |        |       |       |
| Depth                   | 0.07     | ft        |        |       |       |
| Flow Area               | 0.2      | ft²       |        |       |       |
| Wetted Perim            | 2.32     | ft        |        |       |       |
| Top Width               | 2.28     | ft        |        |       |       |
| Critical Depth          | 0.11     | ft        |        |       |       |
| Critical Slope          | 0.029456 | ft/ft     |        |       |       |
| Velocity                | 2.78     | ft/s c    | -GRASS | LINED | SLOHE |
| Velocity Head           | 0.12     | ft        | 0      |       |       |
| Specific Energ          | 0.19     | ft        |        |       |       |
|                         |          |           |        |       |       |
| Froude Numb             | 1.91     |           |        |       |       |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 11:07:11 AM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

## DRAINAGE CALCULATIONS FOR PERMANENT DIVERSION SWALE #1(PDS1)

25-YEAR DESIGN STORM **3-18-11** 

### **Rational Method:**

Q = CIA Where: Q = flow rate (cfs) C = runoff coefficient I = rainfall intensity (in/hr) A = area (ac.)

Total area contributing to swale: 2.78 ac. Proposed Land Cover Grass = 0.22 ac. Wooded = 2.56 ac.

C =  $[(.3^*.22)+(.2^*2.56)]/2.78= 0.21$ Time of Concentration = 18 minutes ∴ I = 4.4 in/hr

Q = C\*I\*A = .21 \* 4.4 \* 2.78 = 2.54 cfs

Velocity in riprap-lined swale at 9.9% slope = 2.78 fps.

| Worksheet   | PD  | S1   | _    |          |        |
|---|---|--|------|----------|--------|
| Flow Element  | Tra   | pezoidal Cha                                     |      |          |        |
| Method  |   | ning's Form                                      |      |          |        |
| Solve For Channel Dept  |   |  | _    |          |        |
| Input Data  |   |  |      |          |        |
| Mannings Coeff  | ic 0.040  |  |      |          |        |
| Channel Slope   | 099000  | ft/ft  |      |          |        |
| Left Side Slope   | 2.00  | H:V  |      |          |        |
| Right Side Slope  | e 2.00  | H:V  |      |          |        |
| Bottom Width  | 2.00  | ft   |      |          | a      |
| Discharge   | 2.78  | cfs  |      |          |        |
|   |   |  |      |          |        |
|   |   |  |      |          |        |
| Results   |   |  |      |          |        |
|   | 0.27  | ft   |      |          |        |
| Results<br>Depth<br>Flow Area   | 0.27  |  |      |          |        |
| Depth   |   | ft²  |      |          |        |
| Depth<br>Flow Area<br>Wetted Perim  | 0.7   | ft²<br>ft  | v    |          |        |
| Depth<br>Flow Area  | 0.7<br>3.19                                     | ft²<br>ft<br>ft                                  | ĸ    |          |        |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth                               | 0.7<br>3.19<br>3.06<br>0.35<br>0.038164         | ft²<br>ft<br>ft<br>ft                            | v    |          | _      |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth                               | 0.7<br>3.19<br>3.06<br>0.35<br>0.038164         | ft²<br>ft<br>ft<br>ft                            | 10D. | RIPEAP   | CHANNE |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth<br>Critical Slope             | 0.7<br>3.19<br>3.06<br>0.35<br>0.038164         | ft²<br>ft<br>ft<br>ft/ft<br>ft/ft<br>ft/s ∠→ (*  | 100  | (Z) PKAP | СНАНИЕ |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth<br>Critical Slope<br>Velocity | 0.7<br>3.19<br>3.06<br>0.35<br>0.038164<br>4.14 | ft²<br>ft<br>ft<br>ft/ft<br>ft/ft<br>ft/ft<br>ft | 100. | (ZI PRAP | CHANNE |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 11:53:46 AM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

## DRAINAGE CALCULATIONS FOR PERMANENT DIVERSION SWALE #2(PDS2)

### 25-YEAR DESIGN STORM 3-18-11

### **Rational Method:**

Q = CIA Where: Q = flow rate (cfs) C = runoff coefficient I = rainfall intensity (in/hr) A = area (ac.)

Total area contributing to swale: 5.35 ac. Proposed Land Cover Grass = .08 ac. Wooded = 5.27 ac.

 $C = [(.3^*.08)+(.2^*5.27)]/5.35= 0.20$ Time of Concentration = 21 minutes  $\therefore$  I = 4.1 in/hr

Q = C\*I\*A = .20 \* 4.1 \* 5.35 = 4.39 cfs

Velocity in riprap-lined swale at 4.5% slope = 2.78 fps.

------

#### Worksheet Worksheet for Trapezoidal Channel

| Worksheet   | PDS   | S2  |       |       |         |    |
|---|---|---|-------|-------|---------|----|
| Flow Element  | Trapezoidal Cha                                 |   |       |       |         |    |
| Method  | Manning's Form                                  |   |       |       |         |    |
| Solve For Channel Depth   |   |   |       |       |         |    |
| Input Data  |   |   |       |       |         |    |
| Mannings Coeff  | ic 0.040  |   |       |       |         |    |
| Channel Slope   | 045000  | ft/ft   |       |       |         |    |
| Left Side Slope   | 2.00  | H:V   |       |       |         |    |
| Right Side Slope  | e 2.00  | H:V   |       |       |         |    |
| Bottom Width  | 2.00  | ft  |       |       |         |    |
| Discharge   | 4.39  | cfs   |       |       |         |    |
|   |   |   |       |       |         |    |
|   |   |   |       |       |         |    |
| Results   |   |   |       |       |         |    |
|   | 0.43  | ft  |       |       |         |    |
| Depth   | 0.43<br>1.2                                     |   |       |       |         |    |
| Depth<br>Flow Area  |   | ft²   |       |       |         |    |
| Depth<br>Flow Area<br>Wetted Perim  | 1.2   | ft²<br>ft   |       |       |         |    |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width   | 1.2<br>3.90                                     | ft²<br>ft<br>ft   |       |       |         |    |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth   | 1.2<br>3.90<br>3.70<br>0.45<br>0.035723         | ft²<br>ft<br>ft<br>ft<br>ft                               |       |       |         |    |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth<br>Critical Slope   | 1.2<br>3.90<br>3.70<br>0.45<br>0.035723         | ft²<br>ft<br>ft<br>ft<br>ft                               | oC. ( | ZIPRA | P CHANK | 11 |
| Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth<br>Critical Slope<br>Velocity   | 1.2<br>3.90<br>3.70<br>0.45<br>0.035723         | ft <sup>2</sup><br>ft<br>ft<br>ft/ft<br>ft/ft             | oC. ( | ZIPRA | 2 CHANK | 1  |
| Results<br>Depth<br>Flow Area<br>Wetted Perim<br>Top Width<br>Critical Depth<br>Critical Slope<br>Velocity<br>Velocity Head<br>Specific Enerç | 1.2<br>3.90<br>3.70<br>0.45<br>0.035723<br>3.61 | ft <sup>2</sup><br>ft<br>ft<br>ft/ft<br>ft/fs < /^v<br>ft | oC. 6 | ZIPRA | 2 CHANK | 1  |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 11:54:32 AM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

## DRAINAGE CALCULATIONS FOR CROSS CULVERT TO LEVEL SPREADER TURBINE 2 ACCESS ROAD STATION 0+55

### 25-YEAR DESIGN STORM 3-18-11

### **Rational Method:**


Q = CIA Where: Q = flow rate (cfs) C = runoff coefficient I = rainfall intensity (in/hr) A = area (ac.)

Total area contributing to swale: 8.13 ac. Proposed Land Cover Grass = 0.30 ac. Wooded = 7.83 ac.

 $C = [(.3^*.30)+(.2^*7.83)]/8.13= 0.20$ Time of Concentration = 21 minutes  $\therefore$  I = 4.1 in/hr

Q = C\*I\*A = .20 \* 4.1 \* 8.13 = 6.67 cfs

For 18" culvert - HW/D = 1.05






Table 8-6.1 - Length - L<sub>a</sub> (feet) Type A Riprap Apron

Notes: 1. Bold face outlined boxes indicate minimum L<sub>a</sub> to be used for a given pipe diameter or span. 2. Rounding and interpolating are acceptable.

Wa= 3 (Sp) + 0.4 (La) Wa= 3(1.5) + 0.4 (12) = 9.3', use 10'W 10'W ×12'L MOD RIPRAP PAD

October 2000

ConnDOT Drainage Manual

#### Cross culvert - Turbine 2 Access Road Worksheet for Circular Channel

| Project Descrip              | tion       |         |         |      |          |   |
|------------------------------|------------|---------|---------|------|----------|---|
| Worksheet                    | Circ       | cular ( | Channel |      |          |   |
| Flow Element                 | Circ       | ular (  | Channel |      |          |   |
| Method                       | Mar        | nning   | s Formu |      |          |   |
| Solve For                    | Cha        | nnel    | Depth   |      |          |   |
| Input Data                   |            |         | _       |      |          |   |
| Mannings Coet                | ffic 0.013 |         | _       |      |          |   |
| Channel Slope                |            | ft/ft   |         |      |          |   |
| Diameter                     | 18.0       |         |         |      |          |   |
| Discharge                    | 6.67       |         |         |      |          |   |
| Results                      |            |         |         |      |          |   |
| Depth                        | 0.87       | 7 ft    |         |      |          |   |
| Flow Area                    | 1.1        | ft²     |         |      |          |   |
| Wetted Perime                | 2.59       | ft      |         |      |          |   |
| Top Width                    | 0.00       | ) ft    |         |      |          |   |
| Critical Depth               | 1.00       | ) ft    |         |      |          |   |
| Percent Full                 | 57.9       | %       |         |      |          |   |
| Critical Slope               | 0.006577   | ft/ft   |         |      |          | 0 |
| Velocity                     | 6.29       | ft/s    | E-USE   | MOD. | RIPICITY | 6 |
| Velocity Head                | 0.62       |         |         |      |          |   |
| Specific Energ               | 1.48       | ft      |         |      |          |   |
| Froude Numbe                 | 1.31       |         |         |      |          |   |
| Maximum Disc                 | 11.30      | cfs     |         |      |          |   |
| D: 1                         | 10.50      | cfs     |         |      |          |   |
| Discharge Full               | 10.50      |         |         |      |          |   |
| Discharge Full<br>Slope Full | 0.004032   |         |         |      |          |   |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 01:12:43 PM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

### DRAINAGE CALCULATIONS FOR PERMANENT DIVERSION SWALE #3(PDS3) 25-YEAR DESIGN STORM **3-18-11**

### **Rational Method:**

Q = CIAWhere: Q = flow rate (cfs)C = runoff coefficientI = rainfall intensity (in/hr)A = area (ac.)

Total area contributing to swale: 8.35 ac. Proposed Land Cover Grass = 0.52 ac. Wooded = 7.83 ac.

 $C = [(.3^*.52)+(.2^*7.83)]/8.35= 0.21$ Time of Concentration = 22 minutes  $\therefore$  I = 4.0 in/hr

Q = C\*I\*A = .21 \* 4.0 \* 8.35 = 7.01 cfs

Velocity in riprap-lined swale at max 20.0% slope = 7.02 fps.

#### Worksheet Worksheet for Trapezoidal Channel

| Project Descrip   | tion   |  |              |     |
|---|--|--|--------------|-----|
| Worksheet   | PDS  | S3   |              |     |
| Flow Element  | Tra  | pezoidal Cha   |              |     |
| Method  |  |  |              |     |
| Solve For   | Cha  | annel Depth  |              |     |
| Input Data  |  |  |              |     |
|   |  |  |              |     |
| Mannings Coef   |  |  |              |     |
| Channel Slope   |  |  |              |     |
| Left Side Slope   | 2.00   | H:V  |              |     |
| Right Side Slop   | e 2.00   | H:V  |              |     |
| Bottom Width  | 2.00   | ft   |              |     |
| Discharge   | 7.01   | cfs  |              |     |
|   |  |  |              |     |
| Results   |  |  |              |     |
| Depth   | 0.37   | ft   |              |     |
|   |  |  |              |     |
| Flow Area   | 1.0  | ft²  |              |     |
|   | 1.0<br>3.64                                      |  |              |     |
| Wetted Perim  |  | ft   |              |     |
| Wetted Perim<br>Top Width   | 3.64   | ft<br>ft   | ,            |     |
| Wetted Perime<br>Top Width<br>Critical Depth  | 3.64<br>3.46<br>0.59                             | ft<br>ft<br>ft                                       |              |     |
| Wetted Perim<br>Top Width<br>Critical Depth<br>Critical Slope                               | 3.64<br>3.46<br>0.59                             | ft<br>ft<br>ft                                       | 10, R1       | 11- |
| Top Width<br>Critical Depth<br>Critical Slope<br>Velocity                                   | 3.64<br>3.46<br>0.59                             | ft<br>ft<br>ft/ft<br>ft/s ⇐── M                      | )<br>20, (Z) | 11- |
| Wetted Perima<br>Top Width<br>Critical Depth<br>Critical Slope<br>Velocity<br>Velocity Head | 3.64<br>3.46<br>0.59<br>0.033524<br>7.02         | ft<br>ft<br>ft/ft<br>ft/s ← ∩<br>ft                  | 90, R1       | Pr  |
| Wetted Perim<br>Top Width   | 3.64<br>3.46<br>0.59<br>0.033524<br>7.02<br>0.77 | ft<br>ft<br>ft/ft<br>ft/ft<br>ft/s ⇐── M<br>ft<br>ft | 20, R1       | 24  |

 Untitled.fm2
 Curtis Jones & Associates
 Project Engineer: Emily Jones

 03/16/11
 01:57:57 PM
 © Haestad Methods, Inc.
 37 Brookside Road
 Waterbury, CT 06708 USA
 +1-203-755-1666
 Page 1 of 1

### STORMWATER POND 1 OUTLET

Worksheet Worksheet for Circular Channel

| Project Descript | ion       |                   | _      |     |      |         |
|------------------|-----------|-------------------|--------|-----|------|---------|
| Worksheet        | Pon       | d 1 o             | utlet  |     |      |         |
| Flow Element     | Circ      | ular C            | hann   |     |      |         |
| Method           | Mar       | ning's            | S Forr |     |      | 9       |
| Solve For        | Cha       | nnel (            | Depth  |     |      |         |
| Input Data       |           |                   | -      |     |      |         |
| Mannings Coeff   | fic 0.013 |                   | _      |     |      |         |
| Channel Slope    | 050000    | ft/ft             |        |     |      |         |
| Diameter         | 15.0      | in                |        |     |      |         |
| Discharge        | 2.30      | cfs               |        |     |      |         |
| Results          |           |                   |        |     |      |         |
| Depth            | 0.34      | ft                |        |     |      |         |
| Flow Area        | 0.3       | B ft <sup>2</sup> |        |     |      |         |
| Wetted Perime    | 1.37      | ft                |        |     |      |         |
| Top Width        | 0.00      | ) ft              |        |     |      |         |
| Critical Depth   | 0.61      | ft                |        |     |      |         |
| Percent Full     | 27.0      | %                 |        |     |      |         |
| Critical Slope   | 0.005630  | ft/ft             |        |     |      |         |
| Velocity         | 8.61      | ft/s              | 6      | USE | INT. | RIPEAPP |
| Velocity Head    | 1.15      | ft                |        |     |      |         |
| Specific Energ   | 1.49      | ft                |        |     |      |         |
| Froude Numbe     | 3.09      | 1                 |        |     |      |         |
| Maximum Disc     | 15.54     | cfs               |        |     |      |         |
| Discharge Full   | 14.44     | cfs               |        |     |      |         |
| Slope Full       | 0.001268  | ft/ft             |        |     |      |         |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 02:30:01 PM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

| Culverts  |  |                | JUE                                 |                                  | 3                                | 10.005                                   |                           |                           |                | 8.7-7         |
|-----------|--|----------------|-------------------------------------|----------------------------------|----------------------------------|--|---------------------------|---------------------------|----------------|---------------|
|           |  |                |                                     |                                  |                                  |  |                           |                           |                |               |
| t         | JUTLEI                                   | PROI           | ECHO                                | N-OL                             | ILEI                             | VELO                                     | cny≤                      | 14 feet/se                | ec             |               |
|           |  |                |                                     |                                  |                                  |  |                           | SPAN (i                   |                |               |
| DISCHARGE | 12                                       | 15.            | 18                                  | 24                               | 30                               | 36                                       | 42                        | 48                        | 54             |               |
| (cfs)     |  | 175-2          | And a state of the state            | -                                | and the second second            | a and a fact a state of the              | Contraction of the second | win with the state        |                | visci cat-may |
| 0-5       | 10                                       | (10)           | 1.1.1.1.1                           | USE                              |                                  | Diana pa                                 |                           |                           |                |               |
| 6         | 12                                       | 11             |                                     | reine Car                        | Contrast Marchen                 | a sin Terr                               | A DECEMBER OF             | and a second second       | and the second |               |
| 7         |  | 13             |                                     | 1921                             | The second                       | (State                                   | 建制品源                      |                           |                |               |
| 8         | 1000                                     | 14             | 13                                  | 12                               | and the second                   | MI                                       | VIMUM                     | the index is              |                |               |
| 9         |  | 11.2 Mar       | 14                                  | 13                               |                                  | Section .                                | v sit and the             |                           |                | ene singe     |
| 10        | - Portania                               |                | 15                                  | 13                               | to and the                       | autor data                               | 5                         | · 建雄金                     | and the state  | 1             |
| 11        | PET 24                                   |                | 16                                  | 14                               | L. Marshire                      | 2.1.4                                    |                           | LE                        | NGTH           |               |
| 12        |  |                | arta<br>A Sittanata                 | 14,                              |                                  |  |                           |                           |                |               |
| 14        |  |                |                                     | 16                               | 14                               |  |                           | Sap Salar                 |                | 「安静           |
| 16        |  | inter a        |                                     | 17                               | 15                               | 14                                       | T. R. W. B. Street        | Later and                 | OUT            | LINE          |
| 18        | San Carlo                                | 2. V. k        |                                     | 18                               | 16                               | 15                                       | 2010月                     |                           |                |               |
| 20        |  |                |                                     |                                  | 17                               | 15                                       | 14                        |                           |                |               |
| 22        | 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1 | USE            | -1. (                               |                                  | 18                               | 16                                       | 15                        |                           |                | - Cata        |
| 24        | - all ages of                            | and the        | A. Stat                             |                                  | i statio                         | 17                                       | 15                        | 14                        | an and a state | Sec.          |
| 26        |  | and the second |                                     | Alta second                      | NATION OF C                      | 17                                       | 16                        | 15                        | e searchead    |               |
| 28        | 120.00                                   | a sere         |                                     |                                  |                                  | 18                                       | 16                        | 15                        |                |               |
| 30        | - Si & A                                 | Care Sale      | Sector 1                            | Server .                         | Sec. 6                           | 19                                       | 17                        | 16                        | 12.9           | No.           |
| 35        |  |                |                                     | THE REAL                         |                                  | 20                                       | 18                        | 17                        | 16             |               |
| 40        | 112.14                                   | 1949/7-1       | PRE                                 | FORM                             | ED                               | V Land                                   | 20                        | 18                        | 17             | 16            |
| 45        |  |                | MT CHARLES (AS)<br>Inclusion of the | er andre her i<br>here her state | ti kun zerinten ku<br>Senten fin | an a | 21                        | 19                        | 18             | 16            |
| 50        |  |                |                                     |                                  | Electron 1                       |  | 22                        | 20                        | 18             | 17            |
| 55        | The la                                   | an line of     |                                     | 4.57-72                          |                                  | S and                                    | the set of the set        | 21                        | 19             | 18            |
| 60        | 合理合于                                     |                |                                     | Silen a s                        | . Pinte                          |  |                           | 22                        | 20             | 19            |
| • 65      |  |                |                                     |                                  |                                  | 3.32 J                                   |                           | 24                        | 21             | 20            |
| 70        |  | t.T. L         |                                     |                                  | SCOL                             | R  | -due                      | 25                        | 22             | 20            |
| 75        | 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1 | in an air      | Sec.                                |                                  | 4. A .                           |  | Califica.                 | 26                        | 23             | 21            |
| 80        |  | Self           |                                     | 9.74 <sup>4</sup> 24 75          | <b>在</b> 名字。第                    |  |                           |                           | 24             | 22            |
| 90        |  | South a        | Carlos and                          |                                  | Carl Sector                      | and a                                    | anti-sea tore to          |                           | 26             | 24            |
| 100       |  |                | Sec.                                | States and                       |                                  |  | 5.2.5                     | a ing siliti.<br>Magaziti | 28             | 25            |
| 110       |  |                |                                     | Contraction of the second        | 3. A ( ) - 1                     | NAMES AND COMPANY OF A                   |                           |                           |                | 27            |
| 125       |  |                | Tree Pres                           |                                  | R - 2 - 3                        |  | HOLE                      |                           | · Charles      | 29            |
| 130       | 國的國際                                     |                | W C                                 | 國際管                              | th - L <sub>a</sub> (            | CONTRACTOR NO.                           | <b>第63</b> 334            |                           |                | 30            |

2. Rounding and interpolating are acceptable.

W= 3(5p) + 0.4 (Le) = 3(1.25) + 0.4(10)= 7.75', USE 8' S'WX10'L INT. RIPKAP PAD

October 2000

ConnDOT Drainage Manual

## DRAINAGE CALCULATIONS FOR CROSS CULVERT UNDER MAIN ACCESS DRIVE STATION 19+85

25-YEAR DESIGN STORM 3-18-11

### **Rational Method:**

Q = CIA Where: Q = flow rate (cfs) C = runoff coefficient I = rainfall intensity (in/hr) A = area (ac.)


Total area contributing to swale: 1.24 ac. Proposed Land Cover Impervious = 0.05Grass = 0.33 ac. Wooded = 0.86 ac.

C =  $[(.9^*.05)+(.3^*.33)+(.2^*.86)]/1.24 = 0.24$ Time of Concentration = 20 minutes ∴ I = 3.6 in/hr

Q = C\*I\*A = .25 \* 3.6 \* 1.24 = 1.14 cfs

For 15" culvert - HW/D = <0.5

Use 5' X 5' modified riprap pad at outlet into swale



## DRAINAGE CALCULATIONS FOR PERMANENT CONVEYANCE SWALE #1 (PCS1) AND CROSS CULVERT UNDER MAIN ACCESS DRIVE AT STATION 15+25

## 25-YEAR DESIGN STORM **3-18-11**

### **Rational Method:**

Q = CIA Where: Q = flow rate (cfs) C = runoff coefficient I = rainfall intensity (in/hr) A = area (ac.)

Total area contributing to swale: 0.30 ac. Proposed Land Cover Grass = 0.06 ac. Impervious = 0.24 ac.


C = [(.3\*.06)+(.9\*.24)]/.30= 0.78 Time of Concentration = 5 minutes ∴ I = 6.7 in/hr

Q = C\*I\*A = .78 \* 6.7 \* 0.30 = 1.57 cfs

Velocity in riprap swale at max 5% slope = 2.73 fps

For 15" culvert - HW/D = 0.55

Use 5' X 5' modified riprap pad at outlet into swale



| Project Descrip      | tion         |            |       | - |
|----------------------|--------------|------------|-------|---|
| Worksheet            | PC           | 51         |       | - |
| Flow Element         | Tra          | pezoidal   | Cha   |   |
| Method               | Mar          | nning's Fe | m     |   |
| Solve For Channel De |              |            | th    |   |
| Input Data           |              |            |       |   |
| Mannings Coe         | ffic 0.040   |            |       |   |
| Channel Slope        | 050000       | ft/ft      |       |   |
| Left Side Slope      | 2.00         | H : V      |       |   |
| Right Side Slop      | be 2.00      | H : V      |       |   |
| Bottom Width         | 2.00         | ft         |       |   |
| Discharge            | 1.57         | cfs        |       |   |
|                      |              |            |       |   |
| Results              | 2            |            |       |   |
| Depth                | 0.23         | ft         |       |   |
| Flow Area            | 0.6          | ft²        |       |   |
| Wetted Perim         | 3.04         | ft         |       |   |
| Top Width            | 2.93         | ft         |       |   |
| Critical Depth       | 0.25         | ft         |       |   |
| Critical Slope       | 0.041716     | ft/ft      |       |   |
| Velocity             | 2.73         | ft/s ⇐     | - MOO | 1 |
| Velocity Head        | 0.12         | ft         |       |   |
| Specific Energ       | 0.35         | ft         |       |   |
| Froude Numb          | 1.09         |            |       |   |
| Flow Type 3          | upercritical |            |       |   |

untitled.fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 03:31:03 PM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1

## DRAINAGE CALCULATIONS FOR PERMANENT CONVEYANCE SWALE #2 (PCS2)

25-YEAR DESIGN STORM **3-18-11** 

#### **Rational Method:**

Q = CIAWhere: Q = flow rate (cfs)C = runoff coefficientI = rainfall intensity (in/hr)A = area (ac.)

Total area contributing to swale: 4.53 ac.Proposed Land Cover Impervious = 0.68 ac.Grass = 0.30 ac.Wooded = 3.55 ac.

 $C = [(.9^{*}.68)+(.3^{*}.30)+(.2^{*}3.55)]/4.53 = 0.31$ Time of Concentration = 21 minutes  $\therefore$  I = 4.1 in/hr

Q = C\*I\*A = .31 \* 4.1 \* 4.53 = 5.76 cfs

Velocity in riprap-lined swale at max 15% slope = 5.98 fps

| Project Descript       | tion        |       |       |          |      |
|------------------------|-------------|-------|-------|----------|------|
| Worksheet              | PC          | 52    |       |          |      |
| Flow Element           | Trapezoida  |       |       | a        |      |
| Method                 | Mar         | ning  | s For | ימ       |      |
| Solve For              | Cha         | Innel | Depth | <u> </u> |      |
| Input Data             |             |       |       |          |      |
| Mannings Coef          | fic 0.040   |       |       |          |      |
| Channel Slope          | 150000      | ft/ft |       |          |      |
| Left Side Slope        | 2.00        | H:V   |       | -        | 2    |
| <b>Right Side Slop</b> | e 2.00      | H:V   |       |          |      |
| Bottom Width           | 2.00        | ft    |       |          |      |
| Discharge              | 5.76        | cfs   |       |          |      |
|                        |             |       | _     |          |      |
| Results                |             |       |       |          |      |
| Depth                  | 0.36        | ft    |       |          |      |
| Flow Area              | 1.0         | ft²   |       |          |      |
| Wetted Perim           | 3.59        | ft    |       |          |      |
| Top Width              | 3.42        | ft    |       |          |      |
| Critical Depth         | 0.53        | ft    |       |          |      |
| Critical Slope         | 0.034409    | ft/ft |       |          |      |
| Velocity               | 5.98        | ft/s  | 6-    | USE      | MOD, |
| Velocity Head          | 0.56        | ft    |       |          |      |
| Specific Energ         | 0.91        | ft    |       |          |      |
| Froude Numb            | 1.99        |       |       |          |      |
| Flow Type 30           | percritical |       |       |          |      |

untitled.fm2 03/16/11 03:48:44 PM

Curtis Jones & Associates © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666

Project Engineer: Emily Jones FlowMaster v7.0 [7.0005] 866 Page 1 of 1

## DRAINAGE CALCULATIONS FOR PERMANENT CONVEYANCE SWALE #3 (PCS3)

25-YEAR DESIGN STORM **3-18-11** 

#### **Rational Method:**

Q = CIAWhere: Q = flow rate (cfs)C = runoff coefficientI = rainfall intensity (in/hr)A = area (ac.)

Total area contributing to swale: 2.02 ac.Proposed Land Cover Impervious = 0.25 ac.Grass = 1.21 ac.Wooded = 0.56 ac.

 $C = [(.9^*.25)+(.3^*1.21)+(.2^*.56)]/2.02 = 0.70$ Time of Concentration = 25 minutes  $\therefore$  I = 3.2 in/hr

Q = C\*I\*A = .70 \* 3.2 \* 2.02 = 4.52 cfs

Velocity in riprap-lined swale at max 5.5% slope = 3.91 fps

| Worksheet                        |    |
|----------------------------------|----|
| Worksheet for Trapezoidal Channe | el |

| Project Descripti   | ion   |   |        |      |        |     |
|---|---|---|--------|------|--------|-----|
| Worksheet   | PC  | S3  |        |      |        |     |
| Flow Element  | Tra   | pezoid  | al Cha |      |        |     |
| Method  | Mar   | nning's   | Form   |      |        |     |
| Solve For   | Cha   | innel [   | Depth  |      |        |     |
| Input Data  |   |   | -      |      |        |     |
| Mannings Coeff  | ic 0.040  |   | _      |      |        |     |
| Channel Slope   | 055000  | ft/ft   |        |      |        |     |
| Left Side Slope   | 2.00  | H:V   |        |      |        |     |
| Right Side Slope  | 2.00  | H:V   |        |      |        |     |
| Bottom Width  | 2.00  | ft  |        |      |        |     |
| Discharge   | 4.52  | cfs   |        |      |        |     |
|   |   |   | _      |      |        |     |
| Results   |   |   |        |      |        |     |
|   |   |   |        |      |        |     |
| Depth   | 0.41  | ft  |        |      |        |     |
|   |   | ft<br>ft²                                       |        |      |        |     |
| Depth   |   | ft²   |        |      |        |     |
| Depth<br>Flow Area  | 1.2   | ft²<br>ft                                       |        |      |        |     |
| Depth<br>Flow Area<br>Wetted Perim  | 1.2<br>3.83   | ft²<br>ft<br>ft                                 |        |      |        |     |
| Depth<br>Flow Area<br>Wetted Perima<br>Top Width<br>Critical Depth  | 1.2<br>3.83<br>3.64<br>0.46<br>0.035635                 | ft²<br>ft<br>ft<br>ft<br>ft                     |        |      |        |     |
| Depth<br>Flow Area<br>Wetted Perima<br>Top Width<br>Critical Depth  | 1.2<br>3.83<br>3.64<br>0.46<br>0.035635                 | ft²<br>ft<br>ft<br>ft<br>ft                     | e use  | мор. | RIPERE | SWA |
| Depth<br>Flow Area<br>Wetted Perima<br>Top Width<br>Critical Depth<br>Critical Slope<br>Velocity                  | 1.2<br>3.83<br>3.64<br>0.46<br>0.035635                 | ft²<br>ft<br>ft<br>ft/ft<br>ft/ft<br>ft/s       | E USE  | MOP. | RIPEAP | SWA |
| Depth<br>Flow Area<br>Wetted Perima<br>Top Width<br>Critical Depth<br>Critical Slope                              | 1.2<br>3.83<br>3.64<br>0.46<br>0.035635<br>3.91         | ft²<br>ft<br>ft<br>ft/ft<br>ft/ft<br>ft/s<br>ft | E USE  | мор. | RIPERE | SWA |
| Depth<br>Flow Area<br>Wetted Perimi<br>Top Width<br>Critical Depth<br>Critical Slope<br>Velocity<br>Velocity Head | 1.2<br>3.83<br>3.64<br>0.46<br>0.035635<br>3.91<br>0.24 | ft²<br>ft<br>ft<br>ft/ft<br>ft/ft<br>ft/s<br>ft | E USE  | MOP. | RIPFAP | SWA |

untitled,fm2 Curtis Jones & Associates FlowMaster v7.0 [7.0005] 03/16/11 04:03:44 PM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666 Page 1 of 1


# STORMWATER POND 2 OUTLET PROTECTION

#### Worksheet Worksheet for Circular Channel

| Project Descrip  | tion                  |                  |
|--|-----------------------|------------------|
| Worksheet  | Pon                   | d 2 ou           |
| Flow Element   | Circ                  | ular C           |
| Method   | Mar                   | ning's           |
| Solve For  | Cha                   | nnel (           |
| Input Data   |                       |                  |
| Mannings Coef  |                       |                  |
| Channel Slope  |                       |                  |
| Diameter   | 15.0                  |                  |
| Discharge  | 1.13                  | cfs              |
| Results  |                       |                  |
| Depth  | 0.22                  | e ft             |
| Flow Area  |                       | ft2              |
| Wetted Perime  | 1.08                  |                  |
| Top Width  | 0.00                  |                  |
| Critical Depth   | 0.42                  | ft               |
| Percent Full   | 17.6                  | %                |
| Critical Slope   | 0.005230              | ft/ft            |
| Velocity   | 7.75                  | ft/s 4           |
| Velocity Head  | 0.93                  | ft               |
|  |                       |                  |
| Specific Energ   | 1.15                  |                  |
|  |                       | ft               |
| Froude Numbe   | 1.15                  | ft               |
| Specific Energ<br>Froude Numbe<br>Maximum Disc<br>Discharge Full | 1.15<br>3.49          | ft               |
| Froude Numbe<br>Maximum Disc                                     | 1.15<br>3.49<br>17.95 | ft<br>cfs<br>cfs |

untitled.fm2 Curtis Jones & Associates 03/16/11 04:11:26 PM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666

Project Engineer: Emily Jones FlowMaster v7.0 [7.0005] 666 Page 1 of 1



Wa= 3(Sp)+04 La = 3(1.25)+0.4(10)=7.75, USE 8'

8'WX10'L MOD RIPRAD PAD

October 2000

ConnDOT Drainage Manual

## TEMPORARY SEDIMENT TRAP SIZING PER 2002 CT DEP E&S MANUAL 3-18-11

#### TST 1 (MAIN ACCESS DRIVE - STATION 20+00 - TURBINE 3 LOCATION):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 0.85 acres = 114 cubic yards Half of Storage Volume will be wet and half dry = 114 / 2 = 57 cubic yards = 1,539 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 2.0' deep: 1,539 cubic feet = 0.85 x Awet x 2.0' Awet required = 905 square feet Use dimension of 20' x 46' for Wet Surface Area = Awet = 920 square feet

Vdry =  $(Awet + Adry)/2 \times Ddry$ If dry area is 1.5' high, Adry = 26' x 52' = 1,352 sf Vdry =  $(920 + 1,352)/2 \times 1.5' = 1,704$  cubic feet Use dimension of 26' x 52' for Dry Surface Area

### TST 2 (TURBINE 2 LOCATION):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 0.89 acres = 119 cubic yards Half of Storage Volume will be wet and half dry = 119 / 2 = 59.5 cubic yards = 1,606 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 2.0' deep: 1,606 cubic feet = 0.85 x Awet x 2.0' Awet required = 945 square feet Use dimension of 20' x 50' for Wet Surface Area = Awet = 1,000 square feet

Vdry =  $(Awet + Adry)/2 \times Ddry$ If dry area is 1.5' high, Adry = 26' x 56' = 1,456 sf Vdry =  $(1,000 + 1,456)/2 \times 1.5' = 1,842$  cubic feet Use dimension of 26' x 56' for Dry Surface Area

#### TST 3 (MAIN ACCESS DRIVE - STATION 10+50 – STORNWATER POND 1 LOCATION):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 3.60 acres = 482 cubic yards Half of Storage Volume will be wet and half dry = 482/2 = 241 cubic yards = 6,507 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 3.0' deep: 6,507 cubic feet = 0.85 x Awet x 3.0' Awet required = 2,552 square feet Use dimension of 38' x 98' for Wet Surface Area = Awet = 3,724 square feet

Vdry = (Awet + Adry)/2 x Ddry If dry area is 3.0' high, Adry = 56' x 116' = 6,496 sf Vdry =  $(3,724 + 6,496)/2 \times 3.0' = 15,330$  cubic feet Use dimension of 56' x 116' for Dry Surface Area

\*Note – TST3 is significantly oversized because area will be rough graded to be used as Stormwater Pond post-construction.

#### TST 4 (MAIN ACCESS DRIVE - STATION 6+50 – STORNWATER POND 2 LOCATION):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 1.62 acres = 217 cubic yards Half of Storage Volume will be wet and half dry = 217/2 = 108.5 cubic yards = 2,930 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 3.0' deep: 2,930 cubic feet = 0.85 x Awet x 3.0' Awet required = 1,149 square feet Use dimension of 24' x 86' for Wet Surface Area = Awet = 2,064 square feet

 $Vdry = (Awet + Adry)/2 \times Ddry$ If dry area is 2.5' high, Adry = 39' x 101' = 3,939 sf Vdry = (2,064 + 3,939)/2 x 2.5' = 7,504 cubic feet Use dimension of 39' x 101' for Dry Surface Area

\*Note – TST4 is significantly oversized because area will be rough graded to be used as Stormwater Pond post-construction.

### TST 5 (STATION 60+80):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 0.25 acres = 34 cubic yards Half of Storage Volume will be wet and half dry = 34 / 2 = 17 cubic yards = 459 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 2.0' deep: 459 cubic feet = 0.85 x Awet x 2.0' Awet required = 270square feet Use dimension of 12' x 24' for Wet Surface Area = Awet = 288 square feet

Vdry = (Awet + Adry)/2 x Ddry If dry area is 1.5' high, Adry =  $18' \times 30' = 540$  sf Vdry =  $(540 + 288)/2 \times 1.5' = 621$  cubic feet Use dimension of  $18' \times 30'$  for Dry Surface Area

### TST 6 (STATION 64+30):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 0.25 acres = 34 cubic yards Half of Storage Volume will be wet and half dry = 34 / 2 = 17 cubic yards = 459 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 2.0' deep: 459 cubic feet = 0.85 x Awet x 2.0' Awet required = 270square feet Use dimension of 12' x 24' for Wet Surface Area = Awet = 288 square feet

Vdry = (Awet + Adry)/2 x Ddry If dry area is 1.5' high, Adry =  $18' \times 30' = 540$  sf Vdry =  $(540 + 288)/2 \times 1.5' = 621$  cubic feet Use dimension of  $18' \times 30'$  for Dry Surface Area

### TST 7 (STATION 77+00):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 1.85 acres = 248 cubic yards Half of Storage Volume will be wet and half dry = 248 / 2 = 124 cubic yards = 3,346 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 3.0' deep: 3,346 cubic feet = 0.85 x Awet x 3.0' Awet required = 1,312 square feet Use dimension of 20' x 66' for Wet Surface Area = Awet = 1,320 square feet

Vdry = (Awet + Adry)/2 x Ddry If dry area is 2.25' high, Adry = 26' x 72' = 1,872 sf Vdry =  $(1,872 + 1,320)/2 \times 2.25' = 3,591$  cubic feet Use dimension of 26' x 72' for Dry Surface Area

### TST 8 (STATION 28+40):

Initial Storage Volume = 134 cubic yards per acre of drainage area V = 134 cubic yards x 1.75 acres = 235 cubic yards Half of Storage Volume will be wet and half dry = 235 / 2 = 117.5 cubic yards = 3,165 cubic feet

Vwet = 0.85 x Awet x Dwet If trap is 3.0' deep: 3,165 cubic feet = 0.85 x Awet x 3.0' Awet required = 1,241 square feet Use dimension of 20' x 64' for Wet Surface Area = Awet = 1,280 square feet

Vdry = (Awet + Adry)/2 x Ddry If dry area is 2.25' high, Adry = 26' x 70' = 1,820 sf Vdry =  $(1,820 + 1,280)/2 \times 2.25' = 3,488$  cubic feet Use dimension of 26' x 70' for Dry Surface Area