



March 20, 2015

Members of the Siting Council  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

RE: Notice of Exempt Modification  
99 Knowlton Hill Rd., Ashford, CT 06278  
N 41° 50' 26.77"  
W 72° 12' 27.07"  
T-Mobile Site #: CT11519D\_L700

Members of the Siting Council:

On behalf of T-Mobile, SBA Communications is submitting an exempt modification application to the Connecticut Siting Council for modification of existing equipment at a tower facility located at 99 Knowlton Hill Rd., Ashford, CT 06278.

The 99 Knowlton Hill Rd., Ashford, CT facility consists of a 150' Monopole Tower owned and operated by SBA Towers V, LLC. In order to accommodate technological changes and enhance system performance in the State of Connecticut, T-Mobile plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the chief elected official of the municipality in which the affected cell site is located.

As part of T-Mobile's L700 project, T-Mobile desires to upgrade their equipment to meet the new standards of 4G technology. The new equipment will allow customers to download files and browse the internet at a high rate of speed while also allowing their phones to be compatible with the latest 4G technology.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in T-Mobile's operations at the site along with the required fee of \$625.

The changes to the facility do not constitute modifications as defined in Connecticut General Statutes (“C.G.S.”) Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. The overall height of the structure will be unaffected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound other than the new equipment cabinets.
3. The proposed changes will not increase the noise level at the existing facility by six decibels or more.
4. The changes in radio frequency power density will not increase the calculated “worst case” power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons, SBA Communications on behalf of T-Mobile, respectfully submits that he proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at 508.251.0720 x 3804 with any questions you may have concerning this matter.

Thank you,



Kri Pelletier  
SBA Communications Corporation  
33 Boston Post Road West Suite 320  
Marlborough, MA 01752  
508-251-0720 x 3804 + T  
508-251-1755 + F  
203-446-7700 + C  
[kpelletier@sbsite.com](mailto:kpelletier@sbsite.com)



**T-Mobile  
Equipment Modification**

99 Knowlton Hill Rd., Ashford, CT 06278  
Site number CT11519D\_L700

**Tower Owner:** SBA Towers V, LLC

**Equipment Configuration:** Monopole

**Current and/or approved:**

- (9) EMS RR90-18-02DP
- (6) TMAs
- (18) 1-5/8" feed lines

**Planned Modifications:**

- (6) RFS APXV18-209014-02
- (3) Commscope Antenna (96.4" x 11.9" x 7.1")
- (6) TMAs
- (3) Kathrein 782 11056
- (18) 1-5/8" feed lines

**Structural Information:**

The attached structural analysis demonstrates that the tower and foundation will have adequate structural capacity to accommodate the proposed modifications.

**Power Density:**

The anticipated Maximum Composite contributions from the T-Mobile facility are 4.59% of the allowable FCC established general public limit. The anticipated composite MPE value for this site assuming all carriers present is 43.86% of the allowable FCC established general public limit sampled at the ground level.

Site Composite MPE%	
Carrier	MPE%
T-Mobile	4.59
AT&T	18.92 %
Verizon Wireless	20.35 %
Site Total MPE %:	43.86 %





March 20, 2015

Mr. Ralph Fletcher  
First Selectman  
Town of Ashford  
Ashford Municipal Offices  
5 Town Hall Road  
Ashford, CT 06278

RE: Telecommunications Facility @ 99 Knowlton Hill Rd., Ashford, CT 06278

Dear Mr. Fletcher,

In order to accommodate technological changes and enhance system performance in the State of Connecticut, T-Mobile will be changing its equipment configuration at certain cell sites.

As required by Regulations of Connecticut State Agencies (R.C.S.A.) Section 16-50j-73, the Connecticut Siting Council has been notified of the changes and will review T-Mobile's proposal. Please accept this letter as notification under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The accompanying letter to the Siting Council fully describes T-Mobile's proposal for the referenced cell site. However, if you have any questions or require any further information on our plans or the Siting Council's procedures, please call me at 508.251.0720 x 3804.

Thank you,

A handwritten signature in black ink, appearing to read "Kri Pelletier", is written over a horizontal line.

Kri Pelletier  
SBA Communications Company  
33 Boston Post Road West Suite 320  
Marlborough, MA 01752  
508-251-0720 x 3804 + T  
508-251-1755 + F  
203-446-7700 + C  
[kpelletier@sbsite.com](mailto:kpelletier@sbsite.com)

March 20, 2015

Thomas E. Knowlton  
317 Squaw Hollow Road  
Ashford, CT 06178

RE: Telecommunications Facility @ 99 Knowlton Hill Rd., Ashford, CT 06278

Dear Mr. Knowlton:

In order to accommodate technological changes and enhance system performance in the State of Connecticut, T-Mobile will be changing its equipment configuration at certain cell sites.

As required by Regulations of Connecticut State Agencies (R.C.S.A.) Section 16-50j-73, the Connecticut Siting Council has been notified of the changes and will review T-Mobile's proposal. Please accept this letter as notification under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The accompanying letter to the Siting Council fully describes T-Mobile's proposal for the referenced cell site. However, if you have any questions or require any further information on our plans or the Siting Council's procedures, please call me at 508.251.0720 x 3804.

Thank you,



Kri Pelletier  
SBA Communications Company  
33 Boston Post Road West Suite 320  
Marlborough, MA 01752  
508-251-0720 x 3804 + T  
508-251-1755 + F  
203-446-7700 + C  
[kpelletier@sbsite.com](mailto:kpelletier@sbsite.com)

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT  
EVALUATION OF HUMAN EXPOSURE POTENTIAL  
TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CT11519D

TVI Ashford- Prime  
99 Knowlton Hill Road  
Ashford, CT 06278

**March 18, 2015**

**EBI Project Number: 6215001638**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general public allowable limit:	<b>43.86 %</b>

March 18, 2015

T-Mobile USA  
Attn: Jason Overbey, RF Manager  
35 Griffin Road South  
Bloomfield, CT 06002

Emissions Analysis for Site: **CT11519D – TVI Ashford- Prime**

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **99 Knowlton Hill Road, Ashford, CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the 700 MHz Band is  $467 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the PCS and AWS bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **99 Knowlton Hill Road, Ashford, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 GSM channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel
- 2) 2 UMTS channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 LTE channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 4) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.
- 5) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.



- 6) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antennas used in this modeling are the **RFS APXV18-209014** for 1900 MHz (PCS) and 2100 MHz (AWS) channels and the **Commscope LNX-6515DS-VTM** for 700 MHz channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The **RFS APXV18-209014** has a maximum gain of **14.4 dBd** at its main lobe. The **Commscope LNX-6515DS-VTM** has a maximum gain of **14.6 dBd** at its main lobe. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antenna mounting height centerline of the proposed antennas is **147 feet** above ground level (AGL).
- 9) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.

**T-Mobile Site Inventory and Power Data**

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APXV18-209014	Make / Model:	RFS APXV18-209014	Make / Model:	RFS APXV18-209014
Gain:	14.4 dBd	Gain:	14.4 dBd	Gain:	14.4 dBd
Height (AGL):	147	Height (AGL):	147	Height (AGL):	147
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	2	Channel Count	2	# PCS Channels:	2
Total TX Power:	120	Total TX Power:	120	# AWS Channels:	120
ERP (W):	3,305.07	ERP (W):	3,305.07	ERP (W):	3,305.07
Antenna A1 MPE%	0.60	Antenna B1 MPE%	0.60	Antenna C1 MPE%	0.60
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXV18-209014	Make / Model:	RFS APXV18-209014	Make / Model:	RFS APXV18-209014
Gain:	14.4 dBd	Gain:	14.4 dBd	Gain:	14.4 dBd
Height (AGL):	147	Height (AGL):	147	Height (AGL):	147
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power:	120	Total TX Power:	120	Total TX Power:	120
ERP (W):	3,305.07	ERP (W):	3,305.07	ERP (W):	3,305.07
Antenna A2 MPE%	0.60	Antenna B2 MPE%	0.60	Antenna C2 MPE%	0.60
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM
Gain:	14.6 dBd	Gain:	14.6 dBd	Gain:	14.6 dBd
Height (AGL):	147	Height (AGL):	147	Height (AGL):	147
Frequency Bands	700 MHz	Frequency Bands	700 MHz	Frequency Bands	700 MHz
Channel Count	1	Channel Count	1	Channel Count	1
Total TX Power:	30	Total TX Power:	30	Total TX Power:	30
ERP (W):	865.21	ERP (W):	865.21	ERP (W):	865.21
Antenna A3 MPE%	0.34	Antenna B3 MPE%	0.34	Antenna C3 MPE%	0.34

Site Composite MPE%	
Carrier	MPE%
T-Mobile	4.59
AT&T	18.92 %
Verizon Wireless	20.35 %
<b>Site Total MPE %:</b>	<b>43.86 %</b>

T-Mobile Sector 1 Total:	1.53 %
T-Mobile Sector 2 Total:	1.53 %
T-Mobile Sector 3 Total:	1.53 %
<b>Site Total:</b>	<b>43.86 %</b>

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector 1:	1.53 %
Sector 2:	1.53 %
Sector 3 :	1.53 %
T-Mobile Total:	4.59 %
Site Total:	43.86 %
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **43.86%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803



**Structural Analysis for  
SBA Network Services, Inc.**

**150' Monopole Tower**

**SBA Site Name: Knowlton  
SBA Site ID: CT13614-A-02  
T-Mobile Site ID: CT11519D**

FDH Project Number 15BFFV1400

**Analysis Results**

Tower Components	50.7 %	Sufficient
Foundation	50.3%	Sufficient

Prepared By:

Zachary Shepherd, EI  
Project Engineer

Reviewed By:

Dennis D. Abel, PE  
Director – Structural Engineering  
CT PE License No. 23247

**FDH Engineering, Inc.**  
6521 Meridien Dr.  
Raleigh, NC 27616  
(919) 755-1012  
info@fdh-inc.com

March 4, 2015





**TABLE OF CONTENTS**

EXECUTIVE SUMMARY ..... 3

    Conclusions..... 3

    Recommendation ..... 3

APPURTENANCE LISTING ..... 4

RESULTS ..... 5

GENERAL COMMENTS ..... 6

LIMITATIONS ..... 6

APPENDIX ..... 7

## EXECUTIVE SUMMARY

At the request of SBA Network Services, Inc., FDH Engineering, Inc. performed a structural analysis of the monopole located in Ashford, CT to determine whether the tower is structurally adequate to support both the existing and proposed loads pursuant to the *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA-222-F and the 2005 Connecticut Building Code*. Information pertaining to the existing/proposed antenna loading, soil parameters, foundation dimensions, current tower geometry, and member sizes was obtained from:

- JGI Eastern, Inc. (Project No. 05360G) Geotechnical Evaluation dated June 28, 2005
- Sabre Communications Corp. (Job No. 06-06307) Stamped Permit Drawings dated June 29, 2005
- Hudson Design Group (for CT1250) Mapping Report dated January 16, 2013
- SBA Network Services, Inc.

The *basic design wind speed* per the *TIA/EIA-222-F* standards and the *2005 Connecticut Building Code* is 85 mph without ice and 38 mph with 1" radial ice. Ice is considered to increase in thickness with height.

## Conclusions

With the existing and proposed antennas from T-Mobile in place at 147 ft., the tower meets the requirements of the *TIA/EIA-222-F* standards and the *2005 Connecticut Building Code* provided the **Recommendations** listed below are satisfied. Furthermore, provided the foundation was designed and constructed to support the original design reactions (see Sabre Job No. 06-06307), the foundation should have the necessary capacity to support the existing and proposed loading. For a more detailed description of the analysis of the tower, see the **Results** section of this report.

Our structural analysis has been performed assuming all information provided to FDH Engineering, Inc. is accurate (i.e., the steel data, tower layout, existing antenna loading, and proposed antenna loading) and that the tower has been properly erected and maintained per the original design drawings.

## Recommendations

To ensure the requirements of the *TIA/EIA-222-F* standards and the *2005 Connecticut Building Code* are met with the existing and proposed loading in place, we have the following recommendations:

1. The coax should be installed inside the pole's shaft.
2. The existing/proposed TMAs should be installed directly behind the proposed panel antennas.

## APPURTENANCE LISTING

The proposed and existing antennas with their corresponding cables/coax lines are shown in **Table 1**. *If the actual layout determined in the field deviates from the layout, FDH Engineering, Inc. should be contacted to perform a revised analysis.*

**Table 1 - Appurtenance Loading**

### Existing Loading:

Antenna Elevation (ft)	Description	Coax and Lines <sup>1</sup>	Carrier	Mount Elevation (ft)	Mount Type
147	(9) EMS RR90-18-02DP (6) TMA's	(18) 1-5/8"	T-Mobile	147	(1) 12' Low Profile Platform
137.5	(6) Powerwave 7770 (3) KMW AM-X-CD-17-65-00T (6) Powerwave LGP21401 (6) Powerwave LGP21903 (6) Ericsson RRUS11 (1) Raycap DC2-48-60-18-8F	(12) 1-5/8" (2) 3/4" DC (1) 7/16" Fiber	AT&T	137.5	(1) 14' Low Profile Platform
127	(6) Antel LPA-80080/4CF (6) Antel LPA 185080-8CF	(12) 1-5/8"	Verizon	127	(1) 10' Low Profile Platform

1. Coax installed inside the pole's shaft, unless otherwise noted.

### Proposed Carrier Final Loading:

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
147	(6) RFS APXV18-209014-02 (3) Commscope Antenna (96.4" x 11.9" x 7.1") (6) TMA's (3) Kathrein 782 11056	(18) 1-5/8"	T-Mobile	147	(1) 12' Low Profile Platform

## RESULTS

The following yield strength of steel for individual members was used for analysis:

**Table 2 - Material Strength**

Member Type	Yield Strength
Tower Shaft Sections	65 ksi
Base Plate	60 ksi
Anchor Bolts	75 ksi

**Table 3** displays the summary of the ratio (as a percentage) of force in the member to their capacities. Values greater than 100% indicate locations where the maximum force in the member exceeds its capacity. *Note: Capacities up to 100% are considered acceptable.* **Table 4** displays the maximum foundation reactions.

If the assumptions outlined in this report differ from actual field conditions, FDH Engineering, Inc. should be contacted to perform a revised analysis. Furthermore, as no information pertaining to the allowable twist and sway requirements for the existing or proposed appurtenances was provided, deflection and rotation were not taken into consideration when performing this analysis.

See the **Appendix** for detailed modeling information

**Table 3 - Summary of Working Percentage of Structural Components**

Section No.	Elevation ft	Component Type	Size	% Capacity*	Pass Fail
L1	150 - 96.75	Pole	TP38.7x25.7x0.375	32.3	Pass
L2	96.75 - 48	Pole	TP49.86x36.7904x0.4375	42.9	Pass
L3	48 - 0	Pole	TP60.46x47.7025x0.4375	50.7	Pass
		Anchor Bolts	(20) 2.25"Ø x 68" BC	47.0	Pass
		Base Plate	68" Sq. x 3" tk. PL	39.7	Pass

\*Capacities include 1/3 allowable stress increase for wind per TIA/EIA-222-F standards.

**Table 4 - Maximum Base Reactions**

Base Reactions	Current Analysis (TIA/EIA-222-F)	Original Design (TIA/EIA-222-F)
Axial	43 k	56 k
Shear	25 k	40 k
Moment	2,658 k-ft	5,289 k-ft

\* Per our experience with foundations of a similar type, the horizontal and axial loading should not control the foundation analysis.



## **GENERAL COMMENTS**


This engineering analysis is based upon the theoretical capacity of the structure. It is not a condition assessment of the tower and its foundation. It is the responsibility of SBA Network Services, Inc. to verify that the tower modeled and analyzed is the correct structure (with accurate antenna loading information) modeled. If there are substantial modifications to be made or the assumptions made in this analysis are not accurate, FDH Engineering, Inc. should be notified immediately to perform a revised analysis.

## **LIMITATIONS**

All opinions and conclusions are considered accurate to a reasonable degree of engineering certainty based upon the evidence available at the time of this report. All opinions and conclusions are subject to revision based upon receipt of new or additional/updated information. All services are provided exercising a level of care and diligence equivalent to the standard and care of our profession. No other warranty or guarantee, expressed or implied, is offered. Our services are confidential in nature and we will not release this report to any other party without the client's consent. The use of this engineering work is limited to the express purpose for which it was commissioned and it may not be reused, copied, or distributed for any other purpose without the written consent of FDH Engineering, Inc.

## **APPENDIX**

Section	1	2	3
Length (ft)	53.25	53.50	53.25
Number of Sides	18	18	18
Thickness (in)	0.3750	0.4375	0.4375
Socket Length (ft)	4.75	6.25	47.4582
Top Dia (in)	25.7000	36.7904	47.4582
Bot Dia (in)	38.7000	49.8600	60.4600
Grade		A572-65	
Weight (K)	6.9	10.8	13.5



**DESIGNED APPURTENANCE LOADING**


TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod	149	KMW AM-X-CD-17-65-00T w/ Mount Pipe	137.5
Commscope	147	(2) LGP21401 TMA	137.5
Commscope	147	(2) LGP21401 TMA	137.5
(2) TMA	147	(2) LGP21903 Diplexer	137.5
(2) TMA	147	(2) LGP21903 Diplexer	137.5
(2) APXV18-209014-02 w/Mount Pipe	147	(2) Ericsson RRUS-11	137.5
(2) APXV18-209014-02 w/Mount Pipe	147	(2) Ericsson RRUS-11	137.5
(2) APXV18-209014-02 w/Mount Pipe	147	(2) Ericsson RRUS-11	137.5
782 11056	147	Raycap DC2-48-60-18-8F	137.5
782 11056	147	14' Low Profile Platform	137.5
Empty Mount Pipe	147	Empty Mount Pipe	137.5
Empty Mount Pipe	147	Empty Mount Pipe	137.5
Empty Mount Pipe	147	Empty Mount Pipe	137.5
12' Low Profile Platform	147	10' Low Profile Platform	127
(2) 7770.00 w/Mount Pipe	137.5	LPA-185080/8CF w/ Mount Pipe	127
(2) 7770.00 w/Mount Pipe	137.5	LPA-185080/8CF w/ Mount Pipe	127
(2) 7770.00 w/Mount Pipe	137.5	LPA-185080/8CF w/ Mount Pipe	127
KMW AM-X-CD-17-65-00T w/ Mount Pipe	137.5	(2) LPA-80080/4CF W/Mount Pipe	127
KMW AM-X-CD-17-65-00T w/ Mount Pipe	137.5	(2) LPA-80080/4CF W/Mount Pipe	127

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			


**TOWER DESIGN NOTES**

1. Tower is located in Windham County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 50.7%



**FDH Engineering, Inc.**  
 6521 Meridian Drive, Suite 107  
 Raleigh, North Carolina 27616  
 Phone: 9197551012  
 FAX: 9197551031

Job: **Knowlton, CT13614-A-02**  
 Project: **15BFFV1400**  
 Client: SBA Network Services, Inc. Drawn by: ZShepherd App'd:  
 Code: TIA/EIA-222-F Date: 03/04/15 Scale: NTS  
 Path: Dwg No. E-1



**STRUCTURAL NOTES:**  
 1. ADDITIONAL TOWER MAPPING AND STRUCTURAL ANALYSIS ARE REQUIRED PRIOR TO CONSTRUCTION. DRAWINGS ARE SUBJECT TO CHANGE PENDING OUTCOME OF STRUCTURAL ANALYSIS.  
 2. MOUNT ALL ANTENNAS, COAX, ETC. IN ACCORDANCE WITH STRUCTURAL ANALYSIS.

**ANTENNA MOUNT STRUCTURAL ASSESSMENT REQUIREMENT:**  
 ENGINEER OF RECORD HAS MADE A VISUAL ASSESSMENT ONLY AND DETERMINED THAT THE EXISTING ANTENNA MOUNT IS ADEQUATE TO ACCOMMODATE ADDITIONAL EQUIPMENT LOADS. STRUCTURAL DESIGNS AND DETAILS AS SHOWN HEREIN FOR STRUCTURAL MODIFICATIONS OF THE EXISTING ANTENNA MOUNT ARE PRELIMINARY ONLY AND FINAL CONSTRUCTION DETAILS ARE SUBJECT TO CHANGE PENDING THE COMPLETION OF AN ANTENNA MOUNT STRUCTURAL ASSESSMENT.



**PARTIAL ELEVATION PHOTO DETAIL** (2/A-1)  
 SCALE: N.T.S




**EQUIPMENT PHOTO DETAIL** (3/A-1)  
 SCALE: N.T.S

(ALL/A-3) (2&3/A-3) PROPOSED T-MOBILE ANTENNA MODIFICATIONS


(2/A-2) (1,2/A-3) T-MOBILE PLATFORM ELEV. = 147.0'± A.G.L.

(4/A-3) (4/G-1) PROPOSED BBU CABINET, POWER SUPPLY AND INTERCONNECT KIT TO BE INSTALLED PER MANUFACTURERS RECOMMENDATIONS



**COMPOUND PLAN**  
 22x34 SCALE: 3/16"=1'-0"  
 11x17 SCALE: 3/32"=1'-0"

(1/A-1)



**T-MOBILE NORTHEAST LLC**  
 35 GRIFFIN ROAD SOUTH  
 BLOOMFIELD, CT 06002  
 OFFICE: (860) 648-1116

**SBA**  
 SBA COMMUNICATIONS CORP.  
 33 BOSTON POST ROAD WEST, SUITE 320 TEL: (508) 251-0720  
 MARLBOROUGH, MA 01752 FAX: (508) 251-1755

**Hudson Design Group**  
 1600 OSGOOD STREET  
 BUILDING 20 NORTH, SUITE 3090 TEL: (978) 557-5553  
 N. ANDOVER, MA 01845 FAX: (978) 336-5586

STATE OF CONNECTICUT  
 DANIEL P. HAMM  
 No. 24178  
 LICENSED PROFESSIONAL ENGINEER

*Daniel P. Hamm*

CHECKED BY: KB

APPROVED BY: DPH

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
1	03/11/15	ISSUED FOR CONSTRUCTION	KMS
0	02/25/15	ISSUED FOR CONSTRUCTION	KMS

SITE NUMBER:  
 CT11519D  
 SITE NAME:  
 CT519/TM ASHFORD-PRIME  
 SITE ADDRESS:  
 99 KNOWLTON HILL ROAD  
 ASHFORD, CT 06278  
 WINDHAM COUNTY

SHEET TITLE  
 COMPOUND PLAN & ELEVATION

SHEET NUMBER  
**A-1**



**T-MOBILE  
NORTHEAST LLC**


35 GRIFFIN ROAD SOUTH  
BLOOMFIELD, CT 06002  
OFFICE: (860) 648-1116



SBA COMMUNICATIONS CORP.  
33 BOSTON POST ROAD WEST, SUITE 320 TEL: (508) 251-0720  
MARLBOROUGH, MA 01752 FAX: (508) 251-1755



1600 OSGOOD STREET  
BUILDING 20 NORTH, SUITE 3090 TEL: (978) 557-5553  
N. ANDOVER, MA 01845 FAX: (978) 336-5586



*Daniel P. Hamm*

CHECKED BY: KB

APPROVED BY: DPH

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
1	03/11/15	ISSUED FOR CONSTRUCTION	KMS
0	02/25/15	ISSUED FOR CONSTRUCTION	KMS

SITE NUMBER:

CT11519D

SITE NAME:

CT519/TM ASHFORD-PRIME

SITE ADDRESS:

99 KNOWLTON HILL ROAD  
ASHFORD, CT 06278  
WINDHAM COUNTY

SHEET TITLE

EXISTING &  
PROPOSED ANTENNA  
PLANS

SHEET NUMBER

**A-2**

**STRUCTURAL NOTES:**


- ADDITIONAL TOWER MAPPING AND STRUCTURAL ANALYSIS ARE REQUIRED PRIOR TO CONSTRUCTION. DRAWINGS ARE SUBJECT TO CHANGE PENDING OUTCOME OF STRUCTURAL ANALYSIS.
- MOUNT ALL ANTENNAS, COAX, ETC. IN ACCORDANCE WITH STRUCTURAL ANALYSIS.

**ANTENNA MOUNT STRUCTURAL ASSESSMENT REQUIREMENT:**


ENGINEER OF RECORD HAS MADE A VISUAL ASSESSMENT ONLY AND DETERMINED THAT THE EXISTING ANTENNA MOUNT IS ADEQUATE TO ACCOMMODATE ADDITIONAL EQUIPMENT LOADS. STRUCTURAL DESIGNS AND DETAILS AS SHOWN HEREIN FOR STRUCTURAL MODIFICATIONS OF THE EXISTING ANTENNA MOUNT ARE PRELIMINARY ONLY AND FINAL CONSTRUCTION DETAILS ARE SUBJECT TO CHANGE PENDING THE COMPLETION OF AN ANTENNA MOUNT STRUCTURAL ASSESSMENT.

**SPECIAL WORK NOTE:**  
VERTICALLY CENTER ON EXISTING MOUNTING RAIL, THE PIPE MAST AND ANTENNA


- 1  
A-3 PROPOSED T-MOBILE ANTENNA ON PROPOSED PIPE (TYP. OF 1 PER SECTOR, TOTAL OF 3)
- 5  
A-3 PROPOSED T-MOBILE SMART BIAS TEE (TYP. OF 1 PER SECTOR, TOTAL OF 3)



**EXISTING ANTENNA PLAN** 1  
SCALE: N.T.S. A-2




**PROPOSED ANTENNA PLAN** 2  
SCALE: N.T.S. A-2




SOURCE: HDG 01-23-2015

**PROPOSED ANTENNA PHOTO DETAIL** 3  
SCALE: N.T.S. A-2



**LNX ANTENNA DETAIL** 1  
SCALE: N.T.S. A-3




**PROPOSED ANTENNA MOUNTING DETAIL** 2  
SCALE: N.T.S. A-3

**ANTENNA MOUNT STRUCTURAL ASSESSMENT REQUIREMENT:**  
ENGINEER OF RECORD HAS MADE A VISUAL ASSESSMENT ONLY AND DETERMINED THAT THE EXISTING ANTENNA MOUNT IS ADEQUATE TO ACCOMMODATE ADDITIONAL EQUIPMENT LOADS. STRUCTURAL DESIGNS AND DETAILS AS SHOWN HEREIN FOR STRUCTURAL MODIFICATIONS OF THE EXISTING ANTENNA MOUNT ARE PRELIMINARY ONLY AND FINAL CONSTRUCTION DETAILS ARE SUBJECT TO CHANGE PENDING THE COMPLETION OF AN ANTENNA MOUNT STRUCTURAL ASSESSMENT.


**STRUCTURAL NOTES:**  
1. ADDITIONAL TOWER MAPPING AND STRUCTURAL ANALYSIS ARE REQUIRED PRIOR TO CONSTRUCTION. DRAWINGS ARE SUBJECT TO CHANGE PENDING OUTCOME OF STRUCTURAL ANALYSIS.  
2. MOUNT ALL ANTENNAS, COAX, ETC. IN ACCORDANCE WITH STRUCTURAL ANALYSIS.

**SPECIAL WORK NOTE:**  
VERTICALLY CENTER ON EXISTING MOUNTING RAIL, THE PIPE MAST AND ANTENNA




**ANTENNA MOUNTING BRACKET** 3  
SCALE: N.T.S. A-3

BBU DIMENSIONS	
MODEL #	DVBBM-2ALM
MANUF.	MSF DATA SERVICES
WIDTH	28.45"
DEPTH	28.45"
HEIGHT	29.67"
WEIGHT	1,264 LBS
MOUNT BASE WITH (4) 1/2" DROP IN ANCHOR'S WITH 2" MINIMUM EMBEDMENT (INSTALL PER MANUFACTURER'S INSTALLATION GUIDELINES)	



**BATTERY CABINET (BBU)** 4  
SCALE: N.T.S. A-3



**SMART BIAS TEE (SBT)** 5  
SCALE: N.T.S. A-3

**T-MOBILE NORTHEAST LLC**  
35 GRIFFIN ROAD SOUTH  
BLOOMFIELD, CT 06002  
OFFICE: (860) 648-1116

**SBA**   
SBA COMMUNICATIONS CORP.  
33 BOSTON POST ROAD WEST, SUITE 320 TEL: (508) 251-0720  
MARLBOROUGH, MA 01752 FAX: (508) 251-1755

**Hudson Design Group**   
1600 OSGOOD STREET  
BUILDING 20 NORTH, SUITE 3090 TEL: (978) 557-5553  
N. ANDOVER, MA 01845 FAX: (978) 336-5586

STATE OF CONNECTICUT  
**DANIEL P. HAMM**  
No. 24178  
LICENSED PROFESSIONAL ENGINEER

*Daniel P. Hamm*

CHECKED BY: KB

APPROVED BY: DPH

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
1	03/11/15	ISSUED FOR CONSTRUCTION	KMS
0	02/25/15	ISSUED FOR CONSTRUCTION	KMS

SITE NUMBER:  
CT11519D  
SITE NAME:  
CT519/TM ASHFORD-PRIME  
SITE ADDRESS:  
99 KNOWLTON HILL ROAD  
ASHFORD, CT 06278  
WINDHAM COUNTY

SHEET TITLE  
DETAILS

SHEET NUMBER  
**A-3**