



STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: siting.council@ct.gov

www.ct.gov/csc

VIA ELECTRONIC MAIL

September 27, 2019

Jeffrey Barbadora
Real Estate Specialist
12 Gill Street, Suite 5800
Woburn, MA 01801

RE: **EM-VER-007-190918** – Cellco Partnership d/b/a Verizon Wireless notice of intent to modify an existing telecommunications facility located at 240 Kensington Road, Berlin, Connecticut.

Dear Mr. Barbadora:

The Connecticut Siting Council (Council) is in receipt of your correspondence of September 25, 2019 submitted in response to the Council's September 19, 2019 notification of an incomplete request for exempt modification with regard to the above-referenced matter.

The submission renders the request for exempt modification complete and the Council will process the request in accordance with the Federal Communications Commission 60-day timeframe.

Thank you for your attention and cooperation.

Sincerely,

Melanie A. Bachman
Executive Director

MAB/IN/emr



Robidoux, Evan

From: Barbadora, Jeff <Jeff.Barbadora@crowncastle.com>
Sent: Wednesday, September 25, 2019 2:41 PM
To: Robidoux, Evan
Cc: CSC-DL Siting Council
Subject: RE: Council Incomplete Letter for EM-VER-007-190918 (240 Kensington Road, Berlin)
Attachments: SA.pdf

Good afternoon Evan,

A hard copy of the attached structural analysis is being overnighted to your office for 9/26/19 delivery.

Thanks,

Jeffrey Barbadora
781-970-0053
12 Gill Street, Suite 5800, Woburn, MA 01801
CrownCastle.com

From: Robidoux, Evan <Evan.Robidoux@ct.gov>
Sent: Monday, September 23, 2019 2:14 PM
To: Barbadora, Jeff <Jeff.Barbadora@crowncastle.com>
Cc: CSC-DL Siting Council <Siting.Council@ct.gov>
Subject: Council Incomplete Letter for EM-VER-007-190918 (240 Kensington Road, Berlin)

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.

Please see the attached correspondence.

Evan Robidoux
Clerk Typist
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

This email may contain confidential or privileged material. Use or disclosure of it by anyone other than the recipient is unauthorized. If you are not an intended recipient, please delete this email.



B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 (918) 587-4630

Date: **July 16, 2019**

Rebecca Klein
 Crown Castle
 3530 Toringdon Way
 Charlotte, NC 28277

Subject: **Structural Analysis Report**

Carrier Designation: **Verizon Wireless Co-Locate**
Carrier Site Number: 76307
Carrier Site Name: Berlin Kensington CT

Crown Castle Designation: **Crown Castle BU Number:** 826217
Crown Castle Site Name: Newington_1
Crown Castle JDE Job Number: 581679
Crown Castle Work Order Number: 1762750
Crown Castle Order Number: 498392 Rev. 0

Engineering Firm Designation: **B+T Group Project Number:** 87581.023.01

Site Data: **240 Kensington Road, Berlin, Hartford County, CT**
Latitude 41° 37' 34.3", Longitude -72° 46' 32.33"
191.667 Foot - Monopole

Dear Rebecca Klein,

B+T Group is pleased to submit this "**Structural Analysis Report**" to determine the structural integrity of the above mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

Sufficient Capacity

The analysis has been performed in accordance with the TIA-222-H standard and IBC 2015/2018 Connecticut State Building Code based upon a wind speed of 125 mph 3-second gust, exposure category B with topographic category 1 and crest height of 0 feet.

Structural analysis prepared by: John Landon

Respectfully submitted by: B+T Engineering, Inc.

COA: PEC.0001564 Expires: 02/10/2020



Chad E. Tuttle, P.E. tnxTower

Report - version 8.0.5.0

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

Table 2 - Other Considered Equipment

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Table 5 – Tower Component Stresses vs. Capacity - LC7

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 191.6 ft. Monopole designed by PiROD Manufactures and mapped by TEP in May of 2015. The tower was originally designed for a wind speed of 80 mph per TIA/EIA-222-F. This tower was modified multiple times to accommodate additional loading.

2) ANALYSIS CRITERIA

TIA-222 Revision:	TIA-222-H
Risk Category:	II
Wind Speed:	125 mph
Exposure Category:	B
Topographic Factor:	1
Ice Thickness:	2 in
Wind Speed with Ice:	50 mph
Service Wind Speed:	60 mph

Table 1 - Proposed Equipment Configuration

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
160.0	160.0	2	Andrew	LNX-6514DS-A1M	7	1-5/8
		4	Commscope	LNX-8513DS-A1M		
		6	Commscope	NNHH-65B-R4		
		1	RFS Celwave	DB-T1-6Z-8AB-0Z		
		3	Samsung Telecom.	RFV01U-D1A		
		3	Samsung Telecom.	RFV01U-D2A		
		1	--	Platform Mount [LP 303-1]		

Table 2 - Other Considered Equipment

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	
191.0	191.0	1	--	Side Arm Mount [SO 701-1]	1	5/16	
	190.0	1	Motorola	WB2623			
184.0	188.0	1	Kathrein	OGB4-900D	15 1	1-5/8 7/8	
	184.0	1	--	Platform Mount [LP 405-1]			
	181.0	181.0	3	Commscope			ATBT-BOTTOM-24V
			3	Ericsson			AIR -32 B2A/B66AA
			3	Ericsson			KRY 112 144/1
			3	Ericsson			KRY 112 489/2
			3	Ericsson			RADIO 4449 B12/B71
			3	RFS Celwave			APX16DWV-16DWVS-E-A20
	3	RFS Celwave	APXVAARR24_43-U-NA20				
179.0	1	Andrew	DB589-A				
158.0	158.0	1	Decibel	DB205-A	2	7/8	
		1	Sinclair	SRL-224NM-4			
		2	--	Side Arm Mount [SO 702-1]			
151.0	151.0	3	Andrew	SBNH-1D6565C			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		3	CCI Antennas	TPA-65R-LCUUUU-H8	12	1-1/4
		3	Comm Comp Inc.	DTMABP7819VG12A		
		3	Ericsson	RRUS 32		
		3	Ericsson	RRUS 32 B2		
		3	Kaelus	DBC0062F3V52-1		
		3	Powerwave Tech.	7770.00		
		1	Raycap	DC6-48-60-18-8F		
		9	--	2.5" Std Pipe Masts		
		1	Site Pro 1	PRK-1245		
		3	--	2.5" Std Pipe Handrail		
		1	--	Platform Mount [LP 403-1]		
150.0	152.0	3	Ericsson	RRUS 12	2 1	3/4 3/8
		1	Raycap	DC6-48-60-18-8F		
	150.0	3	Ericsson	RRUS 11		
		1	--	Pipe Mount [PM 601-3]		
132.0	132.0	1	Sinclair	SRL-235-2	1	7/8
		1	--	Side Arm Mount [SO 702-1]		
124.0	124.0	1	Decibel	PCS 1900 TMA RX	--	--
		1	--	Side Arm Mount [SO 104-3]		
116.0	120.0	1	Andrew	VHLP2-18	3 1 1	1-5/8 1-1/2 1/2
	118.0	6	Alcatel Lucent	800MHZ 2X50W RRH		
		3	Alcatel Lucent	PCS 1900MHZ 4X45W-65MHZ		
		3	Commscope	NNVV-65B-R4		
		3	Nokia	AAHC		
	116.0	1	Dragonwave	HORIZON DUO		
		3	Site Pro1	PRK-HD		
1		--	Platform Mount [LP 405-1]			
90.0	99.0	1	Decibel	DB205-A	1 2 1	7/8 1/2 5/16
	90.0	1	Andrew	KP2F-34		
		1	MTI Wireless Edge	MT-485002		
		2	--	Side Arm Mount [SO 702-1]		
70.0	70.0	1	Sinclair	SRL-235-2	2	7/8
		1	--	Side Arm Mount [SO 701-1]		
33.0	33.0	1	Decibel	DB909XVTE-M	2	1/2
		1	--	Side Arm Mount [SO 702-1]		

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Remarks	Reference	Source
Online Order Information	Verizon Wireless Co-Locate, Rev# 0	498392	CCI Sites
Tower Manufacturer Drawing	PIROD, File No. A-115400	3438498	CCI Sites
Tower Mapping	TEP, Project No. 25651-57340	3438498	CCI Sites
Mount Analysis Report	TEP, Project No. 25651.275018	8521102	CCI Sites
Mount Analysis Report	B+T Group, Project No. 87581.021.01 Date: 07/01/2019	8506409	CCI Sites
Tower Modification Drawing	Natcomm Inc., Date: 03/18/2008	3678661	CCI Sites
Tower Modification Drawing	B+T Group, Project No. 87581.005.01 Date: 10/17/2014	4003976	CCI Sites
Post Modification Inspection	SGS, Date: 01/08/2015	5493013	CCI Sites
Tower Modification Drawing	B+T Group, Project No. 87581.012.01 Date: 06/16/2015	5753424	CCI Sites
Post Modification Inspection	SGS, Date: 10/21/2015	5947973	CCI Sites
Foundation Drawing	Pirod, File No. A-115400	3463552	CCI Sites
Geotech Report	French & Parrello, Job No. 98A209ERI	3438510	CCI Sites
	FDH, Project No. 1307031600		
Antenna Configuration	Crown CAD Package	Date: 06/26/2019	CCI Sites

3.1) Analysis Method

tnxTower (version 8.0.5.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) The tower and structures were built and have been maintained in accordance with the manufacturer's specification.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 3) Mount areas and weights are assumed based on photographs provided.
- 4) The existing base plate grout was considered in this analysis. Grout must be maintained and inspected periodically, and must be replaced if damaged or cracked. Refer to crown document ENG-BUL-10122, Tower Base Plate Grout Inspection and Classification.

This analysis may be affected if any assumptions are not valid or have been made in error. B+T Group should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	191.67 - 186.67	Pole	P18x0.375	1	-0.640	--	0.7	Pass
L2	186.67 - 181.57	Pole	P24x0.375	2	-11.581	--	1.6	Pass
L3	181.57 - 176.57	Pole	P24x0.375	3	-5.762	--	5.6	Pass
L4	176.57 - 171.57	Pole	P24x0.375	4	-6.450	--	9.9	Pass
L5	171.57 - 166.57	Pole	P24x0.375	5	-7.141	--	14.5	Pass
L6	166.57 - 161.57	Pole	P24x0.375	6	-7.834	--	19.2	Pass
L7	161.57 - 156.57	Pole	P24x0.375	7	-12.294	--	27.3	Pass
L8	156.57 - 151.57	Pole	P24x0.375	8	-13.045	--	36.5	Pass
L9	151.57 - 146.57	Pole	P24x0.375	9	-18.937	--	50.6	Pass
L10	146.57 - 141.57	Pole	P24x0.375	10	-19.806	--	65.1	Pass
L11	141.57 - 141.42	Pole	P24x0.375	11	-19.840	--	65.5	Pass
L12	141.42 - 136.42	Pole	P36x0.375	12	-20.970	--	37.8	Pass
L13	136.42 - 131.42	Pole	P36x0.375	13	-22.552	--	45.0	Pass
L14	131.42 - 126.42	Pole	P36x0.375	14	-23.712	--	52.3	Pass
L15	126.42 - 121.42	Pole	P36x0.375	15	-25.921	--	60.0	Pass
L16	121.42 - 121.17	Pole	P36x0.375	16	-25.996	--	60.4	Pass
L17	121.17 - 116.17	Pole	P42x0.375	17	-27.464	--	51.2	Pass
L18	116.17 - 111.17	Pole	P42x0.375	18	-32.770	--	58.6	Pass
L19	111.17 - 110.04	Pole	P42x0.375	19	-33.081	--	60.2	Pass
L20	110.04 - 109.79	Pole + Reinf.	P42x0.4875	20	-33.170	--	47.0	Pass
L21	109.79 - 105.08	Pole + Reinf.	P42x0.4875	21	-34.791	--	52.3	Pass
L22	105.08 - 104.83	Pole + Reinf.	P42x0.5625	22	-34.902	--	47.7	Pass
L23	104.83 - 100.92	Pole + Reinf.	P42x0.5625	23	-37.327	--	51.9	Pass
L24	100.92 - 100.67	Pole	P48x0.375	24	-37.437	--	57.6	Pass
L25	100.67 - 95.83	Pole	P48x0.375	25	-39.273	--	63.4	Pass
L26	95.83 - 95.58	Pole + Reinf.	P48x0.475	26	-39.370	--	50.7	Pass
L27	95.58 - 90.58	Pole + Reinf.	P48x0.475	27	-41.151	--	55.6	Pass
L28	90.58 - 89.92	Pole + Reinf.	P48x0.475	28	-41.887	--	56.3	Pass
L29	89.92 - 89.67	Pole + Reinf.	P48x0.575	29	-42.001	--	47.0	Pass
L30	89.67 - 84.67	Pole + Reinf.	P48x0.575	30	-44.836	--	51.3	Pass
L31	84.67 - 80.83	Pole + Reinf.	P48x0.575	31	-48.016	--	54.8	Pass
L32	80.83 - 80.33	Pole + Reinf.	P54x0.55	32	-48.398	--	46.0	Pass
L33	80.33 - 80.08	Pole + Reinf.	P54x0.4875	33	-48.539	--	52.0	Pass
L34	80.08 - 75.08	Pole + Reinf.	P54x0.4875	34	-51.016	--	56.3	Pass
L35	75.08 - 70.08	Pole + Reinf.	P54x0.4875	35	-53.919	--	60.8	Pass
L36	70.08 - 69.5	Pole + Reinf.	P54x0.4875	36	-54.599	--	61.3	Pass
L37	69.5 - 69.25	Pole + Reinf.	P54x0.5875	37	-54.787	--	50.9	Pass
L38	69.25 - 64.25	Pole + Reinf.	P54x0.5875	38	-61.154	--	54.8	Pass
L39	64.25 - 60.58	Pole + Reinf.	P54x0.5875	39	-66.334	--	57.8	Pass
L40	60.58 - 60.33	Pole + Reinf.	P60x0.5125	40	-66.540	--	54.3	Pass
L41	60.33 - 55.33	Pole + Reinf.	P60x0.5125	41	-70.324	--	58.1	Pass
L42	55.33 - 52.17	Pole + Reinf.	P60x0.5125	42	-71.817	--	60.6	Pass
L43	52.17 - 51.92	Pole + Reinf.	P60x0.625	43	-71.963	--	50.8	Pass
L44	51.92 - 46.92	Pole + Reinf.	P60x0.625	44	-75.064	--	54.1	Pass

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail	
L45	46.92 - 41.92	Pole + Reinf.	P60x0.625	45	-79.037	--	57.5	Pass	
L46	41.92 - 40.33	Pole + Reinf.	P60x0.625	46	-80.285	--	58.6	Pass	
L47	40.33 - 40.08	Pole + Reinf.	P60x0.6	47	-80.478	--	59.3	Pass	
L48	40.08 - 35.08	Pole + Reinf.	P60x0.6	48	-84.151	--	62.8	Pass	
L49	35.08 - 30.08	Pole + Reinf.	P60x0.6	49	-87.481	--	66.5	Pass	
L50	30.08 - 28	Pole + Reinf.	P60x0.6	50	-88.606	--	68.0	Pass	
L51	28 - 27.75	Pole + Reinf.	P60x0.725	51	-88.772	--	57.2	Pass	
L52	27.75 - 22.75	Pole + Reinf.	P60x0.725	52	-92.893	--	60.4	Pass	
L53	22.75 - 20.08	Pole + Reinf.	P60x0.725	53	-95.121	--	62.1	Pass	
L54	20.08 - 19.83	Pole	P60x0.625	54	-95.320	--	69.3	Pass	
L55	19.83 - 17	Pole	P60x0.625	55	-97.470	--	71.3	Pass	
L56	17 - 16.75	Pole + Reinf.	P60x0.725	56	-97.696	--	61.8	Pass	
L57	16.75 - 11.65	Pole + Reinf.	P60x0.75	57	-101.930	--	63.5	Pass	
L58	11.65 - 11.42	Pole + Reinf.	P60x0.75	58	-102.094	--	63.7	Pass	
L59	11.42 - 9.4	Pole + Reinf.	P60x0.75	59	-103.448	--	64.9	Pass	
L60	9.4 - 9.15	Pole + Reinf.	P60x0.8	60	-103.630	--	64.6	Pass	
L61	9.15 - 4.83	Pole + Reinf.	P60x0.8	61	-106.631	--	67.3	Pass	
L62	4.83 - 4.58	Pole + Reinf.	P60x0.75	62	-106.810	--	68.8	Pass	
L63	4.58 - 0	Pole + Reinf.	P60x0.75	63	-109.954	--	71.7	Pass	
							Summary		
							Pole	71.7	Pass
							Reinforcement	69.8	Pass
							Overall	71.7	Pass

Table 5 - Tower Component Stresses vs. Capacity – LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Flange Connection	181.583	1.3	Pass
1	Flange Connection	141.417	42.6	Pass
1	Bridge Stiffener	121.167	64.2	Pass
	Flange Connections		53.2	Pass
1	Bridge Stiffener	100.917	62.7	Pass
	Flange Connections		39.3	Pass
1	Bridge Stiffener	80.833	60.1	Pass
	Flange Connections		38.7	Pass
1	Bridge Stiffener	60.583	43.6	Pass
	Flange Connections		34.5	Pass
1	Existing Bridge Stiffener	40.333	52.1	Pass
	New Bridge Stiffener		39.9	Pass
	Flange Connections		51.7	Pass
1	Existing Bridge Stiffener	20.083	48.6	Pass
	New Bridge Stiffener		38.6	Pass
	Flange Connections		69.1	Pass
1	Anchor Rods	Base	42.2	Pass
1	Base Plate	Base	77.8	Pass
1	Base Foundation (Structure)	Base	74.0	Pass
1	Base Foundation (Soil Interaction)	Base	70.6	Pass

Structure Rating (max from all components) =	77.8%
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.
- 2) Rating per TIA-222-H Section 15.5

4.1) Recommendations



The tower and its foundations have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

APPENDIX A

TNXTOWER OUTPUT

Section	Size	Length (ft)	Grade	Weight (K)
1				0.4
2				0.5
3				0.5
4				0.5
5				0.5
6				0.5
7				0.5
8				0.5
9				0.5
10				0.5
11				0.70
12				0.5
13				0.7
14				0.7
15				0.7
16				0.80
17				0.8
18				0.8
19				1.10
20				1.00
21				1.10
22				1.00
23				1.20
24				1.00
25				1.20
26				1.20
27				1.40
28				1.40
29				1.40
30				1.40
31				1.40
32				1.40
33				1.40
34				1.40
35				1.40
36				1.40
37				1.40
38				1.70
39				1.70
40				1.60
41				1.60
42				2.00
43				2.00
44				2.00
45				1.90
46				1.90
47				1.90
48				1.90
49				2.30
50				2.30
51				2.30
52				2.30
53				1.0
54				1.0
55				1.2
56				1.2
57				1.2
58				1.2
59				1.2
60				1.2
61				1.2
62				1.2
63				1.2
64				1.2
65				1.2
66				1.2
67				1.2
68				1.2
69				1.2
70				1.2
71				1.2
72				1.2
73				1.2
74				1.2
75				1.2
76				1.2
77				1.2
78				1.2
79				1.2
80				1.2
81				1.2
82				1.2
83				1.2
84				1.2
85				1.2
86				1.2
87				1.2
88				1.2
89				1.2
90				1.2
91				1.2
92				1.2
93				1.2
94				1.2
95				1.2
96				1.2
97				1.2
98				1.2
99				1.2
100				1.2

A53-B-42




MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A53-B-42	42 ksi	63 ksi			

TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-H Standard.
3. Tower designed for a 125 mph basic wind in accordance with the TIA-222-H Standard.
4. Tower is also designed for a 50 mph basic wind with 2.00 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Risk Category II.
7. Topographic Category 1 with Crest Height of 0.000 ft
8. TIA-222-H Annex S
9. TOWER RATING: 71.7%

 <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job: 87581.023.01 - Newington_1, CT (BU# 82621)</p>		
	<p>Project:</p>		
	<p>Client: Crown Castle</p>	<p>Drawn by: Pavan Upadhya</p>	<p>App'd:</p>
	<p>Code: TIA-222-H</p>	<p>Date: 07/13/19</p>	<p>Scale: NTS</p>
	<p>Path:</p>		<p>Dwg No. E-1</p>


Vx

Vz


Mx

Mz

Global Mast Shear (K)






Global Mast Moment (kip-ft)



B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job: 87581.023.01 - Newington_1, CT (BU# 82621)		
Project:		
Client: Crown Castle	Drawn by: Pavan Upadhya	App'd:
Code: TIA-222-H	Date: 07/13/19	Scale: NTS
Path:		Dwg No. E-4




B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job: 87581.023.01 - Newington_1, CT (BU# 82621)		
Project:		
Client: Crown Castle	Drawn by: Pavan Upadhya	App'd:
Code: TIA-222-H	Date: 07/13/19	Scale: NTS
Path:		Dwg No. E-5

Feed Line Distribution Chart

0' - 191'8"

— Round
 — Flat
 — App In Face
 — App Out Face
 — Truss Leg



B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job: 87581.023.01 - Newington_1, CT (BU# 82621)			
Project:			
Client: Crown Castle	Drawn by: Pavan Upadhy	App'd:	
Code: TIA-222-H	Date: 07/13/19	Scale: NTS	
Path:	Dwg No. E-7		

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 1 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Tower Input Data

The tower is a monopole.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

- Tower is located in Hartford County, Connecticut.
- Tower base elevation above sea level: 133.000 ft.
- Basic wind speed of 125 mph.
- Risk Category II.
- Exposure Category B.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.000 ft.
- Nominal ice thickness of 2.000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56.000 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50.000 °F.
- Deflections calculated using a wind speed of 60 mph.
- TIA-222-H Annex S.
- TOWER RATING: 71.7%.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.05.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used: $K_{cs}(F_w) = 0.95$, $K_{cs}(t_i) = 0.85$.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|--|---|---|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric | <ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs | <ul style="list-style-type: none"> Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption <li style="text-align: center;">Poles √ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known |
|--|---|---|

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 2 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Pole Section Geometry

Section	Elevation ft	Section Length ft	Pole Size	Pole Grade	Socket Length ft
L1	191.667-186.667	5.000	P18x0.375	A53-B-42 (42 ksi)	
L2	186.667-181.567	5.100	P24x0.375	A53-B-42 (42 ksi)	
L3	181.567-176.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L4	176.567-171.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L5	171.567-166.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L6	166.567-161.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L7	161.567-156.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L8	156.567-151.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L9	151.567-146.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L10	146.567-141.567	5.000	P24x0.375	A53-B-42 (42 ksi)	
L11	141.567-141.417	0.150	P24x0.375	A53-B-42 (42 ksi)	
L12	141.417-136.417	5.000	P36x0.375	A53-B-42 (42 ksi)	
L13	136.417-131.417	5.000	P36x0.375	A53-B-42 (42 ksi)	
L14	131.417-126.417	5.000	P36x0.375	A53-B-42 (42 ksi)	
L15	126.417-121.417	5.000	P36x0.375	A53-B-42 (42 ksi)	
L16	121.417-121.167	0.250	P36x0.375	A53-B-42 (42 ksi)	
L17	121.167-116.167	5.000	P42x0.375	A53-B-42 (42 ksi)	
L18	116.167-111.167	5.000	P42x0.375	A53-B-42 (42 ksi)	
L19	111.167-110.042	1.125	P42x0.375	A53-B-42 (42 ksi)	
L20	110.042-109.792	0.250	P42x0.4875	A53-B-42 (42 ksi)	
L21	109.792-105.083	4.709	P42x0.4875	A53-B-42 (42 ksi)	
L22	105.083-104.833	0.250	P42x0.5625	A53-B-42 (42 ksi)	
L23	104.833-100.917	3.916	P42x0.5625	A53-B-42 (42 ksi)	
L24	100.917-100.667	0.250	P48x0.375	A53-B-42 (42 ksi)	
L25	100.667-95.833	4.834	P48x0.375	A53-B-42 (42 ksi)	
L26	95.833-95.583	0.250	P48x0.475	A53-B-42 (42 ksi)	
L27	95.583-90.583	5.000	P48x0.475	A53-B-42 (42 ksi)	
L28	90.583-89.917	0.666	P48x0.475	A53-B-42 (42 ksi)	
L29	89.917-89.667	0.250	P48x0.575	A53-B-42 (42 ksi)	

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job 87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page 3 of 92</p>
	<p>Project</p>	<p>Date 13:18:51 07/13/19</p>
	<p>Client Crown Castle</p>	<p>Designed by Pavan Upadhya</p>

Section	Elevation ft	Section Length ft	Pole Size	Pole Grade	Socket Length ft
L30	89.667-84.667	5.000	P48x0.575	A53-B-42 (42 ksi)	
L31	84.667-80.833	3.834	P48x0.575	A53-B-42 (42 ksi)	
L32	80.833-80.333	0.500	P54x0.55	A53-B-42 (42 ksi)	
L33	80.333-80.083	0.250	P54x0.4875	A53-B-42 (42 ksi)	
L34	80.083-75.083	5.000	P54x0.4875	A53-B-42 (42 ksi)	
L35	75.083-70.083	5.000	P54x0.4875	A53-B-42 (42 ksi)	
L36	70.083-69.500	0.583	P54x0.4875	A53-B-42 (42 ksi)	
L37	69.500-69.250	0.250	P54x0.5875	A53-B-42 (42 ksi)	
L38	69.250-64.250	5.000	P54x0.5875	A53-B-42 (42 ksi)	
L39	64.250-60.583	3.667	P54x0.5875	A53-B-42 (42 ksi)	
L40	60.583-60.333	0.250	P60x0.5125	A53-B-42 (42 ksi)	
L41	60.333-55.333	5.000	P60x0.5125	A53-B-42 (42 ksi)	
L42	55.333-52.167	3.166	P60x0.5125	A53-B-42 (42 ksi)	
L43	52.167-51.917	0.250	P60x0.625	A53-B-42 (42 ksi)	
L44	51.917-46.917	5.000	P60x0.625	A53-B-42 (42 ksi)	
L45	46.917-41.917	5.000	P60x0.625	A53-B-42 (42 ksi)	
L46	41.917-40.333	1.584	P60x0.625	A53-B-42 (42 ksi)	
L47	40.333-40.083	0.250	P60x0.6	A53-B-42 (42 ksi)	
L48	40.083-35.083	5.000	P60x0.6	A53-B-42 (42 ksi)	
L49	35.083-30.083	5.000	P60x0.6	A53-B-42 (42 ksi)	
L50	30.083-28.000	2.083	P60x0.6	A53-B-42 (42 ksi)	
L51	28.000-27.750	0.250	P60x0.725	A53-B-42 (42 ksi)	
L52	27.750-22.750	5.000	P60x0.725	A53-B-42 (42 ksi)	
L53	22.750-20.083	2.667	P60x0.725	A53-B-42 (42 ksi)	
L54	20.083-19.833	0.250	P60x0.625	A53-B-42 (42 ksi)	
L55	19.833-17.000	2.833	P60x0.625	A53-B-42 (42 ksi)	
L56	17.000-16.750	0.250	P60x0.725	A53-B-42 (42 ksi)	
L57	16.750-11.650	5.100	P60x0.75	A53-B-42 (42 ksi)	
L58	11.650-11.417	0.233	P60x0.75	A53-B-42 (42 ksi)	
L59	11.417-9.396	2.021	P60x0.75	A53-B-42 (42 ksi)	
L60	9.396-9.146	0.250	P60x0.8	A53-B-42	

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>5 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhya</p>

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
ft	ft ²	in							
L16				1	1	1			
121.417-121.167									
L17				1	1	1			
121.167-116.167									
L18				1	1	1			
116.167-111.167									
L19				1	1	1			
111.167-110.042									
L20				1	1	0.983655			
110.042-109.792									
L21				1	1	0.983655			
109.792-105.083									
L22				1	1	0.976951			
105.083-104.833									
L23				1	1	0.976951			
104.833-100.917									
L24				1	1	1			
100.917-100.667									
L25				1	1	1			
100.667-95.833									
L26				1	1	0.981492			
95.833-95.583									
L27				1	1	0.981492			
95.583-90.583									
L28				1	1	0.981492			
90.583-89.917									
L29				1	1	0.97009			
89.917-89.667									
L30				1	1	0.97009			
89.667-84.667									
L31				1	1	0.97009			
84.667-80.833									
L32				1	1	0.976401			
80.833-80.333									
L33				1	1	0.990478			
80.333-80.083									
L34				1	1	0.990478			
80.083-75.083									
L35				1	1	0.990478			
75.083-70.083									
L36				1	1	0.990478			
70.083-69.500									
L37				1	1	1.00601			
69.500-69.250									
L38				1	1	1.00601			
69.250-64.250									
L39				1	1	1.00601			
64.250-60.583									
L40				1	1	0.987891			

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 6 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
ft	ft ²	in							
60.583-60.333									
L41				1	1	0.987891			
60.333-55.333									
L42				1	1	0.987891			
55.333-52.167									
L43				1	1	1.01747			
52.167-51.917									
L44				1	1	1.01747			
51.917-46.917									
L45				1	1	1.01747			
46.917-41.917									
L46				1	1	1.01747			
41.917-40.333									
L47				1	1	0.995499			
40.333-40.083									
L48				1	1	0.995499			
40.083-35.083									
L49				1	1	0.995499			
35.083-30.083									
L50				1	1	0.995499			
30.083-28.000									
L51				1	1	1.00337			
28.000-27.750									
L52				1	1	1.00337			
27.750-22.750									
L53				1	1	1.00337			
22.750-20.083									
L54				1	1	1			
20.083-19.833									
L55				1	1	1			
19.833-17.000									
L56				1	1	1.04129			
17.000-16.750									
L57				1	1	1.02849			
16.750-11.650									
L58				1	1	1.02849			
11.650-11.417									
L59				1	1	1.02849			
11.417-9.396									
L60				1	1	1.00535			
9.396-9.146									
L61				1	1	1.00535			
9.146-4.833									
L62				1	1	1.04998			
4.833-4.583									
L63				1	1	1.04998			
4.583-0.000									

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
-------------	--------	---------------------------------	----------------	--------------	--------------	----------------	--------------------	----------------------	--------------	------------

* Reinforcement Plates*

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job

87581.023.01 - Newington_1, CT (BU# 826217)

Page

7 of 92

Project**Date**

13:18:51 07/13/19

Client

Crown Castle

Designed by

Pavan Upadhyia

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
CCI 4" x 0.75" Plate (E)	A	No	Surface Af (CaAa)	10.875 - 0.000	1	1	0.400 0.450	4.000	9.500	0.000
CCI 4" x 0.75" Plate (E)	B	No	Surface Af (CaAa)	10.875 - 0.000	1	1	-0.250 -0.200	4.000	9.500	0.000
CCI 4" x 0.75" Plate (E)	C	No	Surface Af (CaAa)	13.167 - 3.167	1	1	0.250 0.300	4.000	9.500	0.000
LW										
CCI 6" x 1" Plate (E)	A	No	Surface Af (CaAa)	39.750 - 20.750	1	1	0.400 0.500	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	B	No	Surface Af (CaAa)	39.750 - 20.750	1	1	0.400 0.500	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	39.750 - 20.750	1	1	0.400 0.500	6.000	14.000	0.000
LW										
CCI 6.5" x 1.25" Plate (E)	A	No	Surface Af (CaAa)	59.917 - 40.833	1	1	-0.450 -0.400	6.500	15.500	0.000
CCI 6.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	59.917 - 40.833	1	1	-0.450 -0.400	6.500	15.500	0.000
CCI 6.5" x 1.25" Plate (E)	C	No	Surface Af (CaAa)	59.917 - 40.833	1	1	-0.400 -0.350	6.500	15.500	0.000
LW										
CCI 6" x 1" Plate (E)	A	No	Surface Af (CaAa)	80.167 - 61.167	1	1	-0.450 -0.400	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	B	No	Surface Af (CaAa)	80.167 - 61.167	1	1	-0.350 -0.300	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	80.167 - 61.167	1	1	-0.450 -0.400	6.000	14.000	0.000
LW										
CCI 4" x 0.75" Plate (E)	A	No	Surface Af (CaAa)	106.583 - 101.583	1	1	-0.500 -0.450	4.000	9.500	0.000
CCI 4" x 0.75" Plate (E)	B	No	Surface Af (CaAa)	106.583 - 101.583	1	1	-0.500 -0.450	4.000	9.500	0.000
CCI 4" x 0.75" Plate (E)	C	No	Surface Af (CaAa)	106.583 - 101.583	1	1	-0.500 -0.450	4.000	9.500	0.000
LW										
1" x 2" Plate (E)	A	No	Surface Af (CaAa)	50.417 - 40.583	1	1	-0.450 -0.400	1.000	6.000	0.007
1" x 2" Plate (E)	B	No	Surface Af (CaAa)	50.417 - 40.583	1	1	-0.350 -0.300	1.000	6.000	0.007
1" x 2" Plate (E)	B	No	Surface Af (CaAa)	50.417 - 40.583	1	1	0.200 0.250	1.000	6.000	0.007
1" x 2" Plate (E)	C	No	Surface Af (CaAa)	50.417 - 40.583	1	1	-0.350 -0.300	1.000	6.000	0.007
LW										
1" x 2" Plate (E)	A	No	Surface Af (CaAa)	66.167 - 61.083	1	1	-0.350 -0.300	1.000	6.000	0.007
1" x 2" Plate (E)	B	No	Surface Af (CaAa)	66.167 - 61.083	1	1	-0.450 -0.400	1.000	6.000	0.007
1" x 2" Plate (E)	B	No	Surface Af (CaAa)	66.167 - 61.083	1	1	0.300 0.350	1.000	6.000	0.007
1" x 2" Plate (E)	C	No	Surface Af (CaAa)	66.167 - 61.083	1	1	-0.450 -0.400	1.000	6.000	0.007
LW										
CCI 6" x 1" Plate (E)	A	No	Surface Af (CaAa)	19.000 - 0.000	1	1	0.300 0.350	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	B	No	Surface Af (CaAa)	19.000 - 0.000	1	1	0.400 0.450	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	19.000 - 0.000	1	1	0.450 0.500	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	19.000 - 0.000	1	1	-0.500	6.000	14.000	0.000

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job

87581.023.01 - Newington_1, CT (BU# 826217)

Page

8 of 92

Project**Date**

13:18:51 07/13/19

Client

Crown Castle

Designed by

Pavan Upadhy

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
(E)			(CaAa)	0.000			-0.450			
LW										
CCI 6" x 1" Plate (E)	A	No	Surface Af (CaAa)	30.000 - 17.000	1	1	-0.150 -0.100	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	B	No	Surface Af (CaAa)	30.000 - 17.000	1	1	-0.450 -0.400	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	30.000 - 17.000	1	1	0.350 0.400	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	30.000 - 17.000	1	1	-0.500 -0.450	6.000	14.000	0.000
LW										
CCI 6" x 1" Plate (E)	A	No	Surface Af (CaAa)	50.167 - 37.167	1	1	0.250 0.300	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	B	No	Surface Af (CaAa)	50.167 - 37.167	1	1	0.100 0.150	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	50.167 - 37.167	1	1	-0.400 -0.350	6.000	14.000	0.000
CCI 6" x 1" Plate (E)	C	No	Surface Af (CaAa)	50.167 - 37.167	1	1	0.450 0.500	6.000	14.000	0.000
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	71.000 - 61.000	1	1	-0.250 -0.200	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	71.000 - 61.000	1	1	-0.450 -0.400	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	71.000 - 61.000	1	1	0.400 0.450	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	71.000 - 61.000	1	1	0.350 0.400	4.500	11.000	0.000
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	97.333 - 81.333	1	1	-0.500 -0.450	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	97.333 - 81.333	1	1	-0.500 -0.450	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	97.333 - 81.333	1	1	-0.500 -0.450	4.500	11.000	0.000
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	111.542 - 101.542	1	1	-0.350 -0.300	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	111.542 - 101.542	1	1	-0.350 -0.300	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	111.542 - 101.542	1	1	-0.350 -0.300	4.500	11.000	0.000
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	91.417 - 81.417	1	1	-0.150 -0.100	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	91.417 - 81.417	1	1	-0.150 -0.100	4.500	11.000	0.000
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	91.417 - 81.417	1	1	-0.150 -0.100	4.500	11.000	0.000
LW										
* BS*										
CCI 6.5" x 1.25" Plate (E)	A	No	Surface Af (CaAa)	27.500 - 12.670	1	1	0.400 0.450	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	A	No	Surface Af (CaAa)	27.500 - 12.670	1	1	-0.250 -0.200	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	27.500 - 12.670	1	1	0.450 0.500	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	27.500 - 12.670	1	1	-0.250 -0.200	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	C	No	Surface Af (CaAa)	27.500 - 12.670	1	1	0.350	6.500	15.500	0.028

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job
87581.023.01 - Newington_1, CT (BU# 826217)

Page
9 of 92

Project
Date
13:18:51 07/13/19

Client
Crown Castle
Designed by
Pavan Upadhy

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
(E)			(CaAa)	12.670			0.400			
CCI 6.5" x 1.25" Plate	C	No	Surface Af	27.500 -	1	1	-0.250	6.500	15.500	0.028
(E)			(CaAa)	12.670			-0.200			
LW										
CCI 6.5" x 1.25" Plate	A	No	Surface Af	47.830 -	1	1	0.400	6.500	15.500	0.028
(E)			(CaAa)	32.830			0.450			
CCI 6.5" x 1.25" Plate	A	No	Surface Af	47.830 -	1	1	-0.400	6.500	15.500	0.028
(E)			(CaAa)	32.830			-0.350			
CCI 6.5" x 1.25" Plate	B	No	Surface Af	47.830 -	1	1	-0.400	6.500	15.500	0.028
(E)			(CaAa)	32.830			-0.350			
CCI 6.5" x 1.25" Plate	B	No	Surface Af	47.830 -	1	1	-0.250	6.500	15.500	0.028
(E)			(CaAa)	32.830			-0.200			
CCI 6.5" x 1.25" Plate	C	No	Surface Af	47.830 -	1	1	-0.400	6.500	15.500	0.028
(E)			(CaAa)	32.830			0.350			
CCI 6.5" x 1.25" Plate	C	No	Surface Af	47.830 -	1	1	-0.250	6.500	15.500	0.028
(E)			(CaAa)	32.830			-0.200			
LW										
CCI 8.5" x 1.25" Plate	A	No	Surface Af	60.083 -	1	1	0.200	8.500	19.500	0.036
(E)			(CaAa)	55.250			0.250			
CCI 8.5" x 1.25" Plate	A	No	Surface Af	60.083 -	1	1	-0.400	8.500	19.500	0.036
(E)			(CaAa)	55.250			-0.350			
CCI 8.5" x 1.25" Plate	B	No	Surface Af	60.083 -	1	1	0.150	8.500	19.500	0.036
(E)			(CaAa)	55.250			0.200			
CCI 8.5" x 1.25" Plate	B	No	Surface Af	60.083 -	1	1	-0.350	8.500	19.500	0.036
(E)			(CaAa)	55.250			-0.300			
CCI 8.5" x 1.25" Plate	C	No	Surface Af	60.083 -	1	1	0.100	8.500	19.500	0.036
(E)			(CaAa)	55.250			0.150			
CCI 8.5" x 1.25" Plate	C	No	Surface Af	60.083 -	1	1	-0.500	8.500	19.500	0.036
(E)			(CaAa)	55.250			-0.450			
LW										
CCI 8.5" x 1.25" Plate	A	No	Surface Af	61.083 -	1	1	0.200	8.500	19.500	0.036
(E)			(CaAa)	60.083			0.250			
CCI 8.5" x 1.25" Plate	A	No	Surface Af	61.083 -	1	1	-0.400	8.500	19.500	0.036
(E)			(CaAa)	60.083			-0.350			
CCI 8.5" x 1.25" Plate	B	No	Surface Af	61.083 -	1	1	0.150	8.500	19.500	0.036
(E)			(CaAa)	60.083			0.200			
CCI 8.5" x 1.25" Plate	B	No	Surface Af	61.083 -	1	1	-0.350	8.500	19.500	0.036
(E)			(CaAa)	60.083			-0.300			
CCI 8.5" x 1.25" Plate	C	No	Surface Af	61.083 -	1	1	0.100	8.500	19.500	0.036
(E)			(CaAa)	60.083			0.150			
CCI 8.5" x 1.25" Plate	C	No	Surface Af	61.083 -	1	1	-0.500	8.500	19.500	0.036
(E)			(CaAa)	60.083			-0.450			
LW										
CCI 8.5" x 4.25" Plate	A	No	Surface Af	68.417 -	1	1	0.200	8.500	25.500	0.123
(E)			(CaAa)	61.083			0.250			
CCI 8.5" x 4.25" Plate	A	No	Surface Af	68.417 -	1	1	-0.400	8.500	25.500	0.123
(E)			(CaAa)	61.083			-0.350			
CCI 8.5" x 4.25" Plate	B	No	Surface Af	68.417 -	1	1	0.150	8.500	25.500	0.123
(E)			(CaAa)	61.083			0.200			
CCI 8.5" x 4.25" Plate	B	No	Surface Af	68.417 -	1	1	-0.350	8.500	25.500	0.123
(E)			(CaAa)	61.083			-0.300			
CCI 8.5" x 4.25" Plate	C	No	Surface Af	68.417 -	1	1	0.100	8.500	25.500	0.123
(E)			(CaAa)	61.083			0.150			
CCI 8.5" x 4.25" Plate	C	No	Surface Af	68.417 -	1	1	-0.500	8.500	25.500	0.123
(E)			(CaAa)	61.083			-0.450			
LW										
CCI 8.5" x 1.25" Plate	A	No	Surface Af	73.417 -	1	1	0.200	8.500	19.500	0.036
(E)			(CaAa)	68.417			0.250			
CCI 8.5" x 1.25" Plate	A	No	Surface Af	73.417 -	1	1	-0.400	8.500	19.500	0.036
(E)			(CaAa)	68.417			-0.350			

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	10 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhy

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
CCI 8.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	73.417 - 68.417	1	1	0.150 0.200	8.500	19.500	0.036
CCI 8.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	73.417 - 68.417	1	1	-0.350 -0.300	8.500	19.500	0.036
CCI 8.5" x 1.25" Plate (E)	C	No	Surface Af (CaAa)	73.417 - 68.417	1	1	0.100 0.150	8.500	19.500	0.036
CCI 8.5" x 1.25" Plate (E)	C	No	Surface Af (CaAa)	73.417 - 68.417	1	1	-0.500 -0.450	8.500	19.500	0.036
LW										
CCI 6.5" x 1.25" Plate (E)	A	No	Surface Af (CaAa)	80.333 - 76.500	1	1	0.050 0.100	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	80.333 - 76.500	1	1	0.000 0.050	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	C	No	Surface Af (CaAa)	80.333 - 76.500	1	1	0.150 0.200	6.500	15.500	0.028
LW										
CCI 6.5" x 1.25" Plate (E)	A	No	Surface Af (CaAa)	80.500 - 80.333	1	1	0.050 0.100	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	80.500 - 80.333	1	1	0.000 0.050	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	C	No	Surface Af (CaAa)	80.500 - 80.333	1	1	0.150 0.200	6.500	15.500	0.028
LW										
CCI 6.5" x 4.25" Plate (E)	A	No	Surface Af (CaAa)	85.833 - 80.500	1	1	0.050 0.100	6.500	21.500	0.094
CCI 6.5" x 4.25" Plate (E)	B	No	Surface Af (CaAa)	85.833 - 80.500	1	1	0.000 0.050	6.500	21.500	0.094
CCI 6.5" x 4.25" Plate (E)	C	No	Surface Af (CaAa)	85.833 - 80.500	1	1	0.150 0.200	6.500	21.500	0.094
LW										
CCI 6.5" x 1.25" Plate (E)	A	No	Surface Af (CaAa)	89.750 - 85.833	1	1	0.050 0.100	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	B	No	Surface Af (CaAa)	89.750 - 85.833	1	1	0.000 0.050	6.500	15.500	0.028
CCI 6.5" x 1.25" Plate (E)	C	No	Surface Af (CaAa)	89.750 - 85.833	1	1	0.150 0.200	6.500	15.500	0.028
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	100.417 - 97.917	1	1	-0.150 -0.100	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	100.417 - 97.917	1	1	-0.100 -0.050	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	100.417 - 97.917	1	1	-0.100 -0.050	4.500	11.000	0.015
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	101.417 - 100.417	1	1	-0.150 -0.100	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	101.417 - 100.417	1	1	-0.100 -0.050	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	101.417 - 100.417	1	1	-0.100 -0.050	4.500	11.000	0.015
LW										
CCI 4.5" x 4" Plate (E)	A	No	Surface Af (CaAa)	104.417 - 101.417	1	1	-0.150 -0.100	4.500	17.000	0.061
CCI 4.5" x 4" Plate (E)	B	No	Surface Af (CaAa)	104.417 - 101.417	1	1	-0.100 -0.050	4.500	17.000	0.061
CCI 4.5" x 4" Plate (E)	C	No	Surface Af (CaAa)	104.417 - 101.417	1	1	-0.100 -0.050	4.500	17.000	0.061
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	107.167 - 104.417	1	1	-0.150 -0.100	4.500	11.000	0.015

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 11 of 92
Project	Date 13:18:51 07/13/19
Client Crown Castle	Designed by Pavan Upadhy

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	107.167 - 104.417	1	1	-0.100 -0.050	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	107.167 - 104.417	1	1	-0.100 -0.050	4.500	11.000	0.015
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	120.667 - 117.917	1	1	-0.150 -0.100	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	120.667 - 117.917	1	1	-0.100 -0.050	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	120.667 - 117.917	1	1	-0.200 -0.150	4.500	11.000	0.015
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	121.667 - 120.667	1	1	-0.150 -0.100	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	121.667 - 120.667	1	1	-0.100 -0.050	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	121.667 - 120.667	1	1	-0.200 -0.150	4.500	11.000	0.015
LW										
CCI 4.5" x 4" Plate (E)	A	No	Surface Af (CaAa)	124.417 - 121.667	1	1	-0.150 -0.100	4.500	17.000	0.061
CCI 4.5" x 4" Plate (E)	B	No	Surface Af (CaAa)	124.417 - 121.667	1	1	-0.100 -0.050	4.500	17.000	0.061
CCI 4.5" x 4" Plate (E)	C	No	Surface Af (CaAa)	124.417 - 121.667	1	1	-0.200 -0.150	4.500	17.000	0.061
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	127.167 - 124.417	1	1	-0.150 -0.100	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	127.167 - 124.417	1	1	-0.100 -0.050	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	127.167 - 124.417	1	1	-0.200 -0.150	4.500	11.000	0.015
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	61.458 - 58.000	1	1	-0.250 -0.200	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	61.458 - 58.000	1	1	-0.450 -0.400	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	61.458 - 58.000	1	1	0.400 0.450	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	61.458 - 58.000	1	1	0.350 0.400	4.500	11.000	0.015
LW										
CCI 4.5" x 3" Plate (E)	A	No	Surface Af (CaAa)	62.958 - 61.548	1	1	-0.250 -0.200	4.500	15.000	0.046
CCI 4.5" x 3" Plate (E)	B	No	Surface Af (CaAa)	62.958 - 61.548	1	1	-0.450 -0.400	4.500	15.000	0.046
CCI 4.5" x 3" Plate (E)	B	No	Surface Af (CaAa)	62.958 - 61.548	1	1	0.400 0.450	4.500	15.000	0.046
CCI 4.5" x 3" Plate (E)	C	No	Surface Af (CaAa)	62.958 - 61.548	1	1	0.350 0.400	4.500	15.000	0.046
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	81.708 - 78.333	1	1	-0.500 -0.450	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	81.708 - 78.333	1	1	-0.500 -0.450	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	81.708 - 78.333	1	1	-0.500 -0.450	4.500	11.000	0.015
LW										
CCI 4.5" x 3" Plate (E)	A	No	Surface Af (CaAa)	83.205 - 81.708	1	1	-0.500 -0.450	4.500	15.000	0.046

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 12 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
CCI 4.5" x 3" Plate (E)	B	No	Surface Af (CaAa)	83.205 - 81.708	1	1	-0.500 -0.450	4.500	15.000	0.046
CCI 4.5" x 3" Plate (E)	C	No	Surface Af (CaAa)	83.205 - 81.708	1	1	-0.500 -0.450	4.500	15.000	0.046
LW										
CCI 4.5" x 1" Plate (E)	A	No	Surface Af (CaAa)	101.792 - 98.417	1	1	0.300 0.350	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	B	No	Surface Af (CaAa)	101.792 - 98.417	1	1	0.300 0.350	4.500	11.000	0.015
CCI 4.5" x 1" Plate (E)	C	No	Surface Af (CaAa)	101.792 - 98.417	1	1	0.300 0.350	4.500	11.000	0.015
LW										
CCI 4.5" x 3" Plate (E)	A	No	Surface Af (CaAa)	103.292 - 101.792	1	1	0.300 0.350	4.500	15.000	0.046
CCI 4.5" x 3" Plate (E)	B	No	Surface Af (CaAa)	103.292 - 101.792	1	1	0.300 0.350	4.500	15.000	0.046
CCI 4.5" x 3" Plate (E)	C	No	Surface Af (CaAa)	103.292 - 101.792	1	1	0.300 0.350	4.500	15.000	0.046
HCS 6X12 4AWG(1-5/8) (1R)	A	No	Surface Ar (CaAa)	184.000 - 0.000	1	1	-0.320 -0.300	1.660		0.002
LW										
AL7-50(1-5/8) (E)	B	No	Surface Ar (CaAa)	160.000 - 0.000	7	7	-0.320 -0.050	1.960		0.001
LW										
Safety Line 3/8 (E)	C	No	Surface Ar (CaAa)	191.667 - 0.000	1	1	0.000 0.010	0.375		0.000
Climbing Rung (E-Per Photo)	C	No	Surface Ar (CaAa)	191.667 - 0.000	1	1	-0.050 0.050	1.000		0.008
LW										

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C _A A _A ft ² /ft	Weight klf
LW									
LW									
LDF5-50A(7/8) (E)	B	No	No	Inside Pole	191.667 - 0.000	1	No Ice 1/2" Ice 1" Ice 2" Ice	0.000 0.000 0.000 0.000	0.000 0.000 0.000 0.000
LW									
ATCB-B01-001(5/16) (E)	B	No	No	Inside Pole	191.000 - 0.000	1	No Ice 1/2" Ice 1" Ice 2" Ice	0.000 0.000 0.000 0.000	0.000 0.000 0.000 0.000
LW									
LDF7-50A(1-5/8) (E)	A	No	No	Inside Pole	184.000 - 0.000	14	No Ice 1/2" Ice 1" Ice 2" Ice	0.000 0.000 0.000 0.000	0.001 0.001 0.001 0.001
LW									
LDF5-50A(7/8) (E)	B	No	No	Inside Pole	158.000 - 0.000	2	No Ice 1/2" Ice 1" Ice 2" Ice	0.000 0.000 0.000 0.000	0.000 0.000 0.000 0.000

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 13 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number		C _{AA} ft ² /ft	Weight klf
LW									
LDF6-50A(1-1/4)(E)	C	No	No	Inside Pole	151.000 - 0.000	12	No Ice	0.000	0.001
							1/2" Ice	0.000	0.001
							1" Ice	0.000	0.001
							2" Ice	0.000	0.001
2" Rigid Conduit (E-inside pole)	C	No	No	Inside Pole	150.000 - 0.000	1	No Ice	0.000	0.003
							1/2" Ice	0.000	0.003
							1" Ice	0.000	0.003
							2" Ice	0.000	0.003
FB-L98B-034-XXX(3/8)(E-inside conduit)	C	No	No	Inside Pole	150.000 - 0.000	1	No Ice	0.000	0.000
							1/2" Ice	0.000	0.000
							1" Ice	0.000	0.000
							2" Ice	0.000	0.000
WR-VG86ST-BRD(3/4)(E-inside conduit)	C	No	No	Inside Pole	150.000 - 0.000	2	No Ice	0.000	0.001
							1/2" Ice	0.000	0.001
							1" Ice	0.000	0.001
							2" Ice	0.000	0.001
LW									
LDF5-50A(7/8)(E)	B	No	No	Inside Pole	132.000 - 0.000	1	No Ice	0.000	0.000
							1/2" Ice	0.000	0.000
							1" Ice	0.000	0.000
							2" Ice	0.000	0.000
LW									
2-1/4" Rigid Conduit (E-per photo)	B	No	No	Inside Pole	116.000 - 0.000	2	No Ice	0.000	0.003
							1/2" Ice	0.000	0.003
							1" Ice	0.000	0.003
							2" Ice	0.000	0.003
LDF4-50A(1/2)(E-inside conduit)	B	No	No	Inside Pole	116.000 - 0.000	1	No Ice	0.000	0.000
							1/2" Ice	0.000	0.000
							1" Ice	0.000	0.000
							2" Ice	0.000	0.000
HB158-21U6M48-30F(1-5/8)(R)	B	No	No	Inside Pole	116.000 - 0.000	3	No Ice	0.000	0.002
							1/2" Ice	0.000	0.002
							1" Ice	0.000	0.002
							2" Ice	0.000	0.002
2" Rigid Conduit (R)	B	No	No	Inside Pole	116.000 - 0.000	1	No Ice	0.000	0.003
							1/2" Ice	0.000	0.003
							1" Ice	0.000	0.003
							2" Ice	0.000	0.003
MLC6C-06C-008R-008R(1-1/2)(R)	B	No	No	Inside Pole	116.000 - 0.000	1	No Ice	0.000	0.002
							1/2" Ice	0.000	0.002
							1" Ice	0.000	0.002
							2" Ice	0.000	0.002
LW									
ATCB-B01-001(5/16)(E)	B	No	No	Inside Pole	90.000 - 0.000	1	No Ice	0.000	0.000
							1/2" Ice	0.000	0.000
							1" Ice	0.000	0.000
							2" Ice	0.000	0.000
LDF4-50A(1/2)(E)	B	No	No	Inside Pole	90.000 - 0.000	2	No Ice	0.000	0.000
							1/2" Ice	0.000	0.000
							1" Ice	0.000	0.000
							2" Ice	0.000	0.000
LDF5-50A(7/8)(E)	B	No	No	Inside Pole	90.000 - 0.000	1	No Ice	0.000	0.000
							1/2" Ice	0.000	0.000
							1" Ice	0.000	0.000
							2" Ice	0.000	0.000
LW									
LDF5-50A(7/8)(E)	B	No	No	Inside Pole	70.000 - 0.000	2	No Ice	0.000	0.000
							1/2" Ice	0.000	0.000
							1" Ice	0.000	0.000

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 14 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	C _{AA} ft ² /ft	Weight klf
LW							2" Ice	0.000
LDF4-50A(1/2) (E)	B	No	No	Inside Pole	33.000 - 0.000	2	No Ice	0.000
							1/2" Ice	0.000
							1" Ice	0.000
							2" Ice	0.000
LW								

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	191.667-186.667	A	0.000	0.000	0.000	0.000	0.000
		B	0.000	0.000	0.000	0.000	0.002
		C	0.000	0.000	0.688	0.000	0.043
L2	186.667-181.567	A	0.000	0.000	0.404	0.000	0.034
		B	0.000	0.000	0.000	0.000	0.002
		C	0.000	0.000	0.701	0.000	0.044
L3	181.567-176.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	0.000	0.000	0.002
		C	0.000	0.000	0.688	0.000	0.043
L4	176.567-171.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	0.000	0.000	0.002
		C	0.000	0.000	0.688	0.000	0.043
L5	171.567-166.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	0.000	0.000	0.002
		C	0.000	0.000	0.688	0.000	0.043
L6	166.567-161.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	0.000	0.000	0.002
		C	0.000	0.000	0.688	0.000	0.043
L7	161.567-156.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	4.710	0.000	0.015
		C	0.000	0.000	0.688	0.000	0.043
L8	156.567-151.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	6.860	0.000	0.024
		C	0.000	0.000	0.688	0.000	0.043
L9	151.567-146.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	6.860	0.000	0.024
		C	0.000	0.000	0.688	0.000	0.089
L10	146.567-141.567	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	6.860	0.000	0.024
		C	0.000	0.000	0.688	0.000	0.099
L11	141.567-141.417	A	0.000	0.000	0.025	0.000	0.002
		B	0.000	0.000	0.206	0.000	0.001
		C	0.000	0.000	0.021	0.000	0.003
L12	141.417-136.417	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	6.860	0.000	0.024
		C	0.000	0.000	0.688	0.000	0.099
L13	136.417-131.417	A	0.000	0.000	0.830	0.000	0.069
		B	0.000	0.000	6.860	0.000	0.024
		C	0.000	0.000	0.688	0.000	0.099
L14	131.417-126.417	A	0.000	0.000	1.225	0.000	0.081
		B	0.000	0.000	7.255	0.000	0.037

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L15	126.417-121.417	C	0.000	0.000	1.083	0.000	0.111
		A	0.000	0.000	3.371	0.000	0.272
		B	0.000	0.000	9.401	0.000	0.228
L16	121.417-121.167	C	0.000	0.000	3.229	0.000	0.302
		A	0.000	0.000	0.154	0.000	0.007
		B	0.000	0.000	0.456	0.000	0.005
L17	121.167-116.167	C	0.000	0.000	0.147	0.000	0.009
		A	0.000	0.000	2.505	0.000	0.119
		B	0.000	0.000	8.535	0.000	0.075
L18	116.167-111.167	C	0.000	0.000	2.363	0.000	0.149
		A	0.000	0.000	1.674	0.000	0.069
		B	0.000	0.000	6.860	0.000	0.110
L19	111.167-110.042	C	0.000	0.000	0.688	0.000	0.099
		A	0.000	0.000	2.718	0.000	0.016
		B	0.000	0.000	1.544	0.000	0.026
L20	110.042-109.792	C	0.000	0.000	0.155	0.000	0.022
		A	0.000	0.000	0.604	0.000	0.003
		B	0.000	0.000	0.343	0.000	0.006
L21	109.792-105.083	C	0.000	0.000	0.034	0.000	0.005
		A	0.000	0.000	13.304	0.000	0.097
		B	0.000	0.000	8.388	0.000	0.139
L22	105.083-104.833	C	0.000	0.000	2.575	0.000	0.125
		A	0.000	0.000	0.874	0.000	0.007
		B	0.000	0.000	0.613	0.000	0.010
L23	104.833-100.917	C	0.000	0.000	0.304	0.000	0.009
		A	0.000	0.000	12.995	0.000	0.335
		B	0.000	0.000	10.313	0.000	0.369
L24	100.917-100.667	C	0.000	0.000	5.478	0.000	0.358
		A	0.000	0.000	0.291	0.000	0.011
		B	0.000	0.000	0.593	0.000	0.013
L25	100.667-95.833	C	0.000	0.000	0.284	0.000	0.013
		A	0.000	0.000	4.564	0.000	0.144
		B	0.000	0.000	10.394	0.000	0.186
L26	95.833-95.583	C	0.000	0.000	4.426	0.000	0.173
		A	0.000	0.000	0.229	0.000	0.003
		B	0.000	0.000	0.530	0.000	0.006
L27	95.583-90.583	C	0.000	0.000	0.222	0.000	0.005
		A	0.000	0.000	5.205	0.000	0.069
		B	0.000	0.000	11.236	0.000	0.113
L28	90.583-89.917	C	0.000	0.000	5.063	0.000	0.099
		A	0.000	0.000	1.110	0.000	0.009
		B	0.000	0.000	1.913	0.000	0.015
L29	89.917-89.667	C	0.000	0.000	1.091	0.000	0.013
		A	0.000	0.000	0.480	0.000	0.006
		B	0.000	0.000	0.781	0.000	0.008
L30	89.667-84.667	C	0.000	0.000	0.472	0.000	0.007
		A	0.000	0.000	12.155	0.000	0.285
		B	0.000	0.000	18.185	0.000	0.333
L31	84.667-80.833	C	0.000	0.000	12.012	0.000	0.315
		A	0.000	0.000	9.741	0.000	0.496
		B	0.000	0.000	14.365	0.000	0.532
L32	80.833-80.333	C	0.000	0.000	9.632	0.000	0.519
		A	0.000	0.000	0.725	0.000	0.051
		B	0.000	0.000	1.328	0.000	0.055
L33	80.333-80.083	C	0.000	0.000	0.711	0.000	0.054
		A	0.000	0.000	0.452	0.000	0.014
		B	0.000	0.000	0.753	0.000	0.017
L34	80.083-75.083	C	0.000	0.000	0.444	0.000	0.016
		A	0.000	0.000	9.501	0.000	0.195
		B	0.000	0.000	15.531	0.000	0.243
		C	0.000	0.000	9.358	0.000	0.225

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L35	75.083-70.083	A	0.000	0.000	13.127	0.000	0.311
		B	0.000	0.000	19.845	0.000	0.358
		C	0.000	0.000	12.984	0.000	0.340
L36	70.083-69.500	A	0.000	0.000	2.273	0.000	0.050
		B	0.000	0.000	3.413	0.000	0.056
		C	0.000	0.000	2.256	0.000	0.054
L37	69.500-69.250	A	0.000	0.000	0.975	0.000	0.022
		B	0.000	0.000	1.464	0.000	0.024
		C	0.000	0.000	0.967	0.000	0.023
L38	69.250-64.250	A	0.000	0.000	20.260	0.000	1.167
		B	0.000	0.000	30.360	0.000	1.231
		C	0.000	0.000	20.118	0.000	1.197
L39	64.250-60.583	A	0.000	0.000	15.257	0.000	0.966
		B	0.000	0.000	23.775	0.000	1.103
		C	0.000	0.000	15.152	0.000	0.987
L40	60.583-60.333	A	0.000	0.000	0.604	0.000	0.025
		B	0.000	0.000	1.043	0.000	0.032
		C	0.000	0.000	0.597	0.000	0.027
L41	60.333-55.333	A	0.000	0.000	16.850	0.000	0.467
		B	0.000	0.000	24.164	0.000	0.553
		C	0.000	0.000	16.708	0.000	0.497
L42	55.333-52.167	A	0.000	0.000	4.119	0.000	0.050
		B	0.000	0.000	7.937	0.000	0.082
		C	0.000	0.000	4.028	0.000	0.069
L43	52.167-51.917	A	0.000	0.000	0.312	0.000	0.003
		B	0.000	0.000	0.614	0.000	0.006
		C	0.000	0.000	0.305	0.000	0.005
L44	51.917-46.917	A	0.000	0.000	12.058	0.000	0.144
		B	0.000	0.000	18.672	0.000	0.218
		C	0.000	0.000	15.166	0.000	0.174
L45	46.917-41.917	A	0.000	0.000	22.913	0.000	0.380
		B	0.000	0.000	29.777	0.000	0.465
		C	0.000	0.000	27.771	0.000	0.410
L46	41.917-40.333	A	0.000	0.000	6.676	0.000	0.119
		B	0.000	0.000	8.808	0.000	0.144
		C	0.000	0.000	8.214	0.000	0.128
L47	40.333-40.083	A	0.000	0.000	0.833	0.000	0.017
		B	0.000	0.000	1.135	0.000	0.020
		C	0.000	0.000	1.076	0.000	0.019
L48	40.083-35.083	A	0.000	0.000	19.246	0.000	0.346
		B	0.000	0.000	25.276	0.000	0.397
		C	0.000	0.000	22.020	0.000	0.376
L49	35.083-30.083	A	0.000	0.000	10.711	0.000	0.194
		B	0.000	0.000	16.741	0.000	0.246
		C	0.000	0.000	10.569	0.000	0.224
L50	30.083-28.000	A	0.000	0.000	4.429	0.000	0.029
		B	0.000	0.000	6.941	0.000	0.051
		C	0.000	0.000	6.369	0.000	0.041
L51	28.000-27.750	A	0.000	0.000	0.541	0.000	0.003
		B	0.000	0.000	0.843	0.000	0.006
		C	0.000	0.000	0.784	0.000	0.005
L52	27.750-22.750	A	0.000	0.000	21.122	0.000	0.332
		B	0.000	0.000	27.152	0.000	0.384
		C	0.000	0.000	25.979	0.000	0.362
L53	22.750-20.083	A	0.000	0.000	10.888	0.000	0.185
		B	0.000	0.000	14.105	0.000	0.212
		C	0.000	0.000	13.479	0.000	0.200
L54	20.083-19.833	A	0.000	0.000	0.833	0.000	0.017
		B	0.000	0.000	1.135	0.000	0.020
		C	0.000	0.000	1.076	0.000	0.019
L55	19.833-17.000	A	0.000	0.000	11.441	0.000	0.196

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	Page	
		87581.023.01 - Newington_1, CT (BU# 826217)	17 of 92
	Project		Date
		13:18:51 07/13/19	
	Client	Designed by	
	Crown Castle	Pavan Upadhya	

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L56	17.000-16.750	B	0.000	0.000	14.858	0.000	0.226
		C	0.000	0.000	16.194	0.000	0.213
		A	0.000	0.000	0.833	0.000	0.017
L57	16.750-11.650	B	0.000	0.000	1.135	0.000	0.020
		C	0.000	0.000	1.076	0.000	0.019
		A	0.000	0.000	14.787	0.000	0.296
L58	11.650-11.417	B	0.000	0.000	20.937	0.000	0.350
		C	0.000	0.000	20.753	0.000	0.327
		A	0.000	0.000	0.272	0.000	0.003
L59	11.417-9.396	B	0.000	0.000	0.553	0.000	0.006
		C	0.000	0.000	0.653	0.000	0.005
		A	0.000	0.000	3.342	0.000	0.028
L60	9.396-9.146	B	0.000	0.000	5.780	0.000	0.049
		C	0.000	0.000	5.667	0.000	0.040
		A	0.000	0.000	0.458	0.000	0.003
L61	9.146-4.833	B	0.000	0.000	0.760	0.000	0.006
		C	0.000	0.000	0.701	0.000	0.005
		A	0.000	0.000	7.904	0.000	0.060
L62	4.833-4.583	B	0.000	0.000	13.106	0.000	0.105
		C	0.000	0.000	12.094	0.000	0.086
		A	0.000	0.000	0.458	0.000	0.003
L63	4.583-0.000	B	0.000	0.000	0.760	0.000	0.006
		C	0.000	0.000	0.701	0.000	0.005
		A	0.000	0.000	8.399	0.000	0.064
		B	0.000	0.000	13.926	0.000	0.112
		C	0.000	0.000	10.740	0.000	0.091

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	191.667-186.667	A	2.024	0.000	0.000	0.000	0.000	0.000
		B		0.000	0.000	0.000	0.000	0.002
		C		0.000	0.000	4.736	0.000	0.110
L2	186.667-181.567	A	2.019	0.000	0.000	1.386	0.000	0.056
		B		0.000	0.000	0.000	0.000	0.002
		C		0.000	0.000	4.820	0.000	0.112
L3	181.567-176.567	A	2.013	0.000	0.000	2.843	0.000	0.115
		B		0.000	0.000	0.000	0.000	0.002
		C		0.000	0.000	4.714	0.000	0.110
L4	176.567-171.567	A	2.008	0.000	0.000	2.838	0.000	0.114
		B		0.000	0.000	0.000	0.000	0.002
		C		0.000	0.000	4.703	0.000	0.109
L5	171.567-166.567	A	2.002	0.000	0.000	2.832	0.000	0.114
		B		0.000	0.000	0.000	0.000	0.002
		C		0.000	0.000	4.691	0.000	0.109
L6	166.567-161.567	A	1.996	0.000	0.000	2.826	0.000	0.114
		B		0.000	0.000	0.000	0.000	0.002
		C		0.000	0.000	4.679	0.000	0.109
L7	161.567-156.567	A	1.990	0.000	0.000	2.820	0.000	0.114
		B		0.000	0.000	7.595	0.000	0.118
		C		0.000	0.000	4.667	0.000	0.108
L8	156.567-151.567	A	1.983	0.000	0.000	2.813	0.000	0.114
		B		0.000	0.000	11.054	0.000	0.172
		C		0.000	0.000	4.654	0.000	0.108
L9	151.567-146.567	A	1.977	0.000	0.000	2.807	0.000	0.113
		B		0.000	0.000	11.046	0.000	0.171

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	18 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhy

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L10	146.567-141.567	C		0.000	0.000	4.641	0.000	0.153
		A	1.970	0.000	0.000	2.800	0.000	0.113
		B		0.000	0.000	11.037	0.000	0.171
		C		0.000	0.000	4.627	0.000	0.163
L11	141.567-141.417	A	1.966	0.000	0.000	0.084	0.000	0.003
		B		0.000	0.000	0.331	0.000	0.005
		C		0.000	0.000	0.139	0.000	0.005
L12	141.417-136.417	A	1.963	0.000	0.000	2.793	0.000	0.113
		B		0.000	0.000	11.028	0.000	0.170
		C		0.000	0.000	4.613	0.000	0.163
L13	136.417-131.417	A	1.956	0.000	0.000	2.786	0.000	0.113
		B		0.000	0.000	11.020	0.000	0.170
		C		0.000	0.000	4.599	0.000	0.162
L14	131.417-126.417	A	1.948	0.000	0.000	3.327	0.000	0.134
		B		0.000	0.000	11.559	0.000	0.192
		C		0.000	0.000	5.132	0.000	0.184
L15	126.417-121.417	A	1.940	0.000	0.000	6.360	0.000	0.397
		B		0.000	0.000	14.590	0.000	0.454
		C		0.000	0.000	8.158	0.000	0.446
L16	121.417-121.167	A	1.936	0.000	0.000	0.307	0.000	0.013
		B		0.000	0.000	0.719	0.000	0.016
		C		0.000	0.000	0.397	0.000	0.015
L17	121.167-116.167	A	1.932	0.000	0.000	5.106	0.000	0.206
		B		0.000	0.000	13.334	0.000	0.264
		C		0.000	0.000	6.896	0.000	0.256
L18	116.167-111.167	A	1.924	0.000	0.000	3.836	0.000	0.127
		B		0.000	0.000	10.980	0.000	0.254
		C		0.000	0.000	4.535	0.000	0.161
L19	111.167-110.042	A	1.919	0.000	0.000	3.863	0.000	0.071
		B		0.000	0.000	2.469	0.000	0.058
		C		0.000	0.000	1.018	0.000	0.036
L20	110.042-109.792	A	1.917	0.000	0.000	0.858	0.000	0.016
		B		0.000	0.000	0.549	0.000	0.013
		C		0.000	0.000	0.226	0.000	0.008
L21	109.792-105.083	A	1.913	0.000	0.000	18.809	0.000	0.375
		B		0.000	0.000	12.979	0.000	0.320
		C		0.000	0.000	6.902	0.000	0.230
L22	105.083-104.833	A	1.909	0.000	0.000	1.228	0.000	0.026
		B		0.000	0.000	0.919	0.000	0.023
		C		0.000	0.000	0.596	0.000	0.018
L23	104.833-100.917	A	1.905	0.000	0.000	18.532	0.000	0.643
		B		0.000	0.000	15.492	0.000	0.623
		C		0.000	0.000	10.433	0.000	0.548
L24	100.917-100.667	A	1.901	0.000	0.000	0.492	0.000	0.020
		B		0.000	0.000	0.903	0.000	0.027
		C		0.000	0.000	0.580	0.000	0.022
L25	100.667-95.833	A	1.896	0.000	0.000	7.956	0.000	0.271
		B		0.000	0.000	15.902	0.000	0.410
		C		0.000	0.000	9.651	0.000	0.318
L26	95.833-95.583	A	1.891	0.000	0.000	0.415	0.000	0.009
		B		0.000	0.000	0.826	0.000	0.016
		C		0.000	0.000	0.503	0.000	0.011
L27	95.583-90.583	A	1.886	0.000	0.000	9.093	0.000	0.188
		B		0.000	0.000	17.310	0.000	0.331
		C		0.000	0.000	10.837	0.000	0.236
L28	90.583-89.917	A	1.880	0.000	0.000	1.741	0.000	0.032
		B		0.000	0.000	2.835	0.000	0.051
		C		0.000	0.000	1.973	0.000	0.039
L29	89.917-89.667	A	1.879	0.000	0.000	0.733	0.000	0.016
		B		0.000	0.000	1.144	0.000	0.023
		C		0.000	0.000	0.820	0.000	0.018

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L30	89.667-84.667	A	1.873	0.000	0.000	17.873	0.000	0.545
		B		0.000	0.000	26.086	0.000	0.691
		C		0.000	0.000	19.604	0.000	0.593
L31	84.667-80.833	A	1.864	0.000	0.000	14.318	0.000	0.728
		B		0.000	0.000	20.614	0.000	0.839
		C		0.000	0.000	15.638	0.000	0.764
L32	80.833-80.333	A	1.859	0.000	0.000	1.115	0.000	0.071
		B		0.000	0.000	1.936	0.000	0.085
		C		0.000	0.000	1.286	0.000	0.075
L33	80.333-80.083	A	1.858	0.000	0.000	0.673	0.000	0.025
		B		0.000	0.000	1.083	0.000	0.032
		C		0.000	0.000	0.759	0.000	0.027
L34	80.083-75.083	A	1.852	0.000	0.000	14.196	0.000	0.391
		B		0.000	0.000	22.404	0.000	0.537
		C		0.000	0.000	15.905	0.000	0.439
L35	75.083-70.083	A	1.839	0.000	0.000	18.223	0.000	0.563
		B		0.000	0.000	27.302	0.000	0.719
		C		0.000	0.000	19.920	0.000	0.610
L36	70.083-69.500	A	1.832	0.000	0.000	3.035	0.000	0.093
		B		0.000	0.000	4.547	0.000	0.118
		C		0.000	0.000	3.232	0.000	0.098
L37	69.500-69.250	A	1.831	0.000	0.000	1.301	0.000	0.040
		B		0.000	0.000	1.950	0.000	0.050
		C		0.000	0.000	1.386	0.000	0.042
L38	69.250-64.250	A	1.824	0.000	0.000	27.344	0.000	1.584
		B		0.000	0.000	41.081	0.000	1.825
		C		0.000	0.000	29.026	0.000	1.631
L39	64.250-60.583	A	1.812	0.000	0.000	21.026	0.000	1.304
		B		0.000	0.000	32.990	0.000	1.614
		C		0.000	0.000	22.250	0.000	1.339
L40	60.583-60.333	A	1.806	0.000	0.000	0.848	0.000	0.040
		B		0.000	0.000	1.444	0.000	0.054
		C		0.000	0.000	0.931	0.000	0.042
L41	60.333-55.333	A	1.798	0.000	0.000	22.562	0.000	0.789
		B		0.000	0.000	32.489	0.000	1.000
		C		0.000	0.000	24.218	0.000	0.836
L42	55.333-52.167	A	1.785	0.000	0.000	6.365	0.000	0.126
		B		0.000	0.000	11.551	0.000	0.218
		C		0.000	0.000	7.405	0.000	0.155
L43	52.167-51.917	A	1.779	0.000	0.000	0.487	0.000	0.009
		B		0.000	0.000	0.896	0.000	0.016
		C		0.000	0.000	0.569	0.000	0.011
L44	51.917-46.917	A	1.770	0.000	0.000	17.719	0.000	0.362
		B		0.000	0.000	27.638	0.000	0.561
		C		0.000	0.000	23.230	0.000	0.454
L45	46.917-41.917	A	1.751	0.000	0.000	31.161	0.000	0.756
		B		0.000	0.000	41.805	0.000	0.977
		C		0.000	0.000	38.734	0.000	0.872
L46	41.917-40.333	A	1.738	0.000	0.000	9.023	0.000	0.227
		B		0.000	0.000	12.268	0.000	0.293
		C		0.000	0.000	11.416	0.000	0.263
L47	40.333-40.083	A	1.734	0.000	0.000	1.078	0.000	0.030
		B		0.000	0.000	1.487	0.000	0.037
		C		0.000	0.000	1.455	0.000	0.036
L48	40.083-35.083	A	1.722	0.000	0.000	25.299	0.000	0.633
		B		0.000	0.000	33.475	0.000	0.776
		C		0.000	0.000	30.349	0.000	0.718
L49	35.083-30.083	A	1.698	0.000	0.000	15.065	0.000	0.361
		B		0.000	0.000	23.234	0.000	0.504
		C		0.000	0.000	16.620	0.000	0.406
L50	30.083-28.000	A	1.678	0.000	0.000	6.192	0.000	0.097

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 20 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
		B		0.000	0.000	9.593	0.000	0.156
		C		0.000	0.000	9.203	0.000	0.142
L51	28.000-27.750	A	1.672	0.000	0.000	0.754	0.000	0.012
		B		0.000	0.000	1.162	0.000	0.019
		C		0.000	0.000	1.127	0.000	0.017
L52	27.750-22.750	A	1.655	0.000	0.000	27.301	0.000	0.629
		B		0.000	0.000	35.460	0.000	0.770
		C		0.000	0.000	34.730	0.000	0.738
L53	22.750-20.083	A	1.628	0.000	0.000	13.975	0.000	0.335
		B		0.000	0.000	18.323	0.000	0.409
		C		0.000	0.000	17.916	0.000	0.392
L54	20.083-19.833	A	1.617	0.000	0.000	1.060	0.000	0.029
		B		0.000	0.000	1.468	0.000	0.036
		C		0.000	0.000	1.429	0.000	0.034
L55	19.833-17.000	A	1.604	0.000	0.000	14.637	0.000	0.351
		B		0.000	0.000	19.253	0.000	0.429
		C		0.000	0.000	21.442	0.000	0.436
L56	17.000-16.750	A	1.590	0.000	0.000	1.092	0.000	0.029
		B		0.000	0.000	1.499	0.000	0.035
		C		0.000	0.000	1.494	0.000	0.034
L57	16.750-11.650	A	1.563	0.000	0.000	19.586	0.000	0.496
		B		0.000	0.000	27.884	0.000	0.635
		C		0.000	0.000	29.057	0.000	0.614
L58	11.650-11.417	A	1.530	0.000	0.000	0.414	0.000	0.007
		B		0.000	0.000	0.793	0.000	0.014
		C		0.000	0.000	0.987	0.000	0.014
L59	11.417-9.396	A	1.515	0.000	0.000	4.910	0.000	0.077
		B		0.000	0.000	8.194	0.000	0.131
		C		0.000	0.000	8.530	0.000	0.122
L60	9.396-9.146	A	1.497	0.000	0.000	0.666	0.000	0.010
		B		0.000	0.000	1.071	0.000	0.017
		C		0.000	0.000	1.051	0.000	0.015
L61	9.146-4.833	A	1.456	0.000	0.000	11.392	0.000	0.168
		B		0.000	0.000	18.387	0.000	0.281
		C		0.000	0.000	17.975	0.000	0.250
L62	4.833-4.583	A	1.399	0.000	0.000	0.653	0.000	0.009
		B		0.000	0.000	1.058	0.000	0.016
		C		0.000	0.000	1.029	0.000	0.014
L63	4.583-0.000	A	1.302	0.000	0.000	11.754	0.000	0.163
		B		0.000	0.000	19.152	0.000	0.276
		C		0.000	0.000	15.774	0.000	0.218

Feed Line Center of Pressure

Section	Elevation ft	CP _x in	CP _z in	CP _x Ice in	CP _z Ice in
L1	191.667-186.667	-0.003	1.248	-0.014	2.811
L2	186.667-181.567	-0.715	1.295	-0.875	3.012
L3	181.567-176.567	-1.409	1.313	-1.691	2.912
L4	176.567-171.567	-1.409	1.313	-1.689	2.908
L5	171.567-166.567	-1.409	1.313	-1.688	2.904
L6	166.567-161.567	-1.409	1.313	-1.686	2.900
L7	161.567-156.567	2.198	-3.144	0.767	-0.497
L8	156.567-151.567	3.059	-4.207	1.432	-1.418
L9	151.567-146.567	3.059	-4.207	1.434	-1.422
L10	146.567-141.567	3.059	-4.207	1.437	-1.427

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	21 of 92
	Project		Date	13:18:51 07/13/19
	Client	Crown Castle		Designed by

Section	Elevation	CP _x	CP _z	CP _x	CP _z
	ft	in	in	Ice in	Ice in
L11	141.567-141.417	3.059	-4.207	1.438	-1.429
L12	141.417-136.417	3.698	-5.079	1.799	-1.762
L13	136.417-131.417	3.698	-5.079	1.802	-1.767
L14	131.417-126.417	3.593	-4.737	1.814	-1.696
L15	126.417-121.417	3.199	-3.430	1.867	-1.356
L16	121.417-121.167	3.236	-3.576	1.857	-1.381
L17	121.167-116.167	3.615	-4.206	2.014	-1.615
L18	116.167-111.167	2.955	-4.459	1.462	-1.483
L19	111.167-110.042	-3.391	2.109	-3.123	2.605
L20	110.042-109.792	-3.391	2.109	-3.123	2.604
L21	109.792-105.083	-2.932	1.913	-2.728	2.355
L22	105.083-104.833	-2.399	1.655	-2.260	2.033
L23	104.833-100.917	-1.786	1.121	-1.694	1.532
L24	100.917-100.667	1.712	-2.189	1.383	-1.177
L25	100.667-95.833	2.590	-3.400	1.524	-1.381
L26	95.833-95.583	2.673	-3.669	1.553	-1.532
L27	95.583-90.583	1.857	-2.549	1.498	-1.480
L28	90.583-89.917	1.524	-2.091	1.261	-1.247
L29	89.917-89.667	1.184	-2.125	0.977	-1.331
L30	89.667-84.667	0.617	-2.184	0.489	-1.477
L31	84.667-80.833	0.569	-2.134	0.447	-1.453
L32	80.833-80.333	0.866	-2.987	0.681	-2.046
L33	80.333-80.083	1.101	-2.735	0.952	-1.888
L34	80.083-75.083	1.914	-2.574	1.741	-1.757
L35	75.083-70.083	2.300	-2.147	2.120	-1.499
L36	70.083-69.500	0.147	-1.316	0.065	-0.848
L37	69.500-69.250	0.147	-1.316	0.065	-0.849
L38	69.250-64.250	0.267	-1.279	0.230	-0.785
L39	64.250-60.583	-0.436	-1.001	-0.473	-0.468
L40	60.583-60.333	0.061	-1.900	-0.195	-1.215
L41	60.333-55.333	1.185	-1.652	0.959	-1.068
L42	55.333-52.167	1.711	-2.002	1.478	-1.090
L43	52.167-51.917	1.687	-2.003	1.456	-1.083
L44	51.917-46.917	2.890	-3.046	2.908	-1.986
L45	46.917-41.917	3.122	-3.377	3.204	-2.528
L46	41.917-40.333	3.292	-3.699	3.335	-2.852
L47	40.333-40.083	3.633	-4.730	3.434	-4.094
L48	40.083-35.083	2.800	-3.652	2.619	-3.072
L49	35.083-30.083	2.116	-2.823	1.921	-2.086
L50	30.083-28.000	-1.701	-4.283	-1.537	-3.468
L51	28.000-27.750	-1.809	-4.329	-1.636	-3.523
L52	27.750-22.750	-1.382	-2.478	-1.287	-2.027
L53	22.750-20.083	-1.421	-2.508	-1.323	-2.062
L54	20.083-19.833	-1.612	-2.846	-1.506	-2.355
L55	19.833-17.000	-0.523	-2.920	-0.378	-2.523
L56	17.000-16.750	2.346	-1.706	2.346	-1.353
L57	16.750-11.650	2.199	-1.767	2.174	-1.377
L58	11.650-11.417	2.159	-2.614	2.009	-1.940
L59	11.417-9.396	2.923	-4.818	2.805	-4.254
L60	9.396-9.146	3.176	-5.549	3.071	-5.027
L61	9.146-4.833	3.176	-5.549	3.080	-5.051
L62	4.833-4.583	3.176	-5.549	3.092	-5.085
L63	4.583-0.000	4.346	-6.340	4.271	-5.909

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 22 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L1	218	Safety Line 3/8	186.67 - 191.67	1.0000	1.0000
L1	219	Climbing Rung	186.67 - 191.67	1.0000	1.0000
L2	187	HCS 6X12 4AWG(1-5/8)	181.57 - 184.00	1.0000	1.0000
L2	218	Safety Line 3/8	181.57 - 186.67	1.0000	1.0000
L2	219	Climbing Rung	181.57 - 186.67	1.0000	1.0000
L3	187	HCS 6X12 4AWG(1-5/8)	176.57 - 181.57	1.0000	1.0000
L3	218	Safety Line 3/8	176.57 - 181.57	1.0000	1.0000
L3	219	Climbing Rung	176.57 - 181.57	1.0000	1.0000
L4	187	HCS 6X12 4AWG(1-5/8)	171.57 - 176.57	1.0000	1.0000
L4	218	Safety Line 3/8	171.57 - 176.57	1.0000	1.0000
L4	219	Climbing Rung	171.57 - 176.57	1.0000	1.0000
L5	187	HCS 6X12 4AWG(1-5/8)	166.57 - 171.57	1.0000	1.0000
L5	218	Safety Line 3/8	166.57 - 171.57	1.0000	1.0000
L5	219	Climbing Rung	166.57 - 171.57	1.0000	1.0000
L6	187	HCS 6X12 4AWG(1-5/8)	161.57 - 166.57	1.0000	1.0000
L6	218	Safety Line 3/8	161.57 - 166.57	1.0000	1.0000
L6	219	Climbing Rung	161.57 - 166.57	1.0000	1.0000
L7	187	HCS 6X12 4AWG(1-5/8)	156.57 - 161.57	1.0000	1.0000
L7	190	AL7-50(1-5/8)	156.57 - 160.00	1.0000	1.0000
L7	218	Safety Line 3/8	156.57 - 161.57	1.0000	1.0000
L7	219	Climbing Rung	156.57 - 161.57	1.0000	1.0000
L8	187	HCS 6X12 4AWG(1-5/8)	151.57 - 156.57	1.0000	1.0000
L8	190	AL7-50(1-5/8)	151.57 - 156.57	1.0000	1.0000
L8	218	Safety Line 3/8	151.57 - 156.57	1.0000	1.0000
L8	219	Climbing Rung	151.57 - 156.57	1.0000	1.0000
L9	187	HCS 6X12 4AWG(1-5/8)	146.57 - 151.57	1.0000	1.0000
L9	190	AL7-50(1-5/8)	146.57 - 151.57	1.0000	1.0000
L9	218	Safety Line 3/8	146.57 - 151.57	1.0000	1.0000
L9	219	Climbing Rung	146.57 -	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
L10	187	HCS 6X12 4AWG(1-5/8)	151.57 141.57 - 146.57	1.0000	1.0000
L10	190	AL7-50(1-5/8)	141.57 - 146.57	1.0000	1.0000
L10	218	Safety Line 3/8	141.57 - 146.57	1.0000	1.0000
L10	219	Climbing Rung	141.57 - 146.57	1.0000	1.0000
L11	187	HCS 6X12 4AWG(1-5/8)	141.42 - 141.57	1.0000	1.0000
L11	190	AL7-50(1-5/8)	141.42 - 141.57	1.0000	1.0000
L11	218	Safety Line 3/8	141.42 - 141.57	1.0000	1.0000
L11	219	Climbing Rung	141.42 - 141.57	1.0000	1.0000
L12	187	HCS 6X12 4AWG(1-5/8)	136.42 - 141.42	1.0000	1.0000
L12	190	AL7-50(1-5/8)	136.42 - 141.42	1.0000	1.0000
L12	218	Safety Line 3/8	136.42 - 141.42	1.0000	1.0000
L12	219	Climbing Rung	136.42 - 141.42	1.0000	1.0000
L13	187	HCS 6X12 4AWG(1-5/8)	131.42 - 136.42	1.0000	1.0000
L13	190	AL7-50(1-5/8)	131.42 - 136.42	1.0000	1.0000
L13	218	Safety Line 3/8	131.42 - 136.42	1.0000	1.0000
L13	219	Climbing Rung	131.42 - 136.42	1.0000	1.0000
L14	151	CCI 4.5" x 1" Plate	126.42 - 127.17	1.0000	1.0000
L14	152	CCI 4.5" x 1" Plate	126.42 - 127.17	1.0000	1.0000
L14	153	CCI 4.5" x 1" Plate	126.42 - 127.17	1.0000	1.0000
L14	187	HCS 6X12 4AWG(1-5/8)	126.42 - 131.42	1.0000	1.0000
L14	190	AL7-50(1-5/8)	126.42 - 131.42	1.0000	1.0000
L14	218	Safety Line 3/8	126.42 - 131.42	1.0000	1.0000
L14	219	Climbing Rung	126.42 - 131.42	1.0000	1.0000
L15	143	CCI 4.5" x 1" Plate	121.42 - 121.67	1.0000	1.0000
L15	144	CCI 4.5" x 1" Plate	121.42 - 121.67	1.0000	1.0000
L15	145	CCI 4.5" x 1" Plate	121.42 - 121.67	1.0000	1.0000
L15	147	CCI 4.5" x 4" Plate	121.67 - 124.42	1.0000	1.0000
L15	148	CCI 4.5" x 4" Plate	121.67 - 124.42	1.0000	1.0000
L15	149	CCI 4.5" x 4" Plate	121.67 - 124.42	1.0000	1.0000
L15	151	CCI 4.5" x 1" Plate	124.42 - 126.42	1.0000	1.0000
L15	152	CCI 4.5" x 1" Plate	124.42 -	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L15	153	CCI 4.5" x 1" Plate	126.42 124.42 - 126.42	1.0000	1.0000
L15	187	HCS 6X12 4AWG(1-5/8)	121.42 - 126.42	1.0000	1.0000
L15	190	AL7-50(1-5/8)	121.42 - 126.42	1.0000	1.0000
L15	218	Safety Line 3/8	121.42 - 126.42	1.0000	1.0000
L15	219	Climbing Rung	121.42 - 126.42	1.0000	1.0000
L16	143	CCI 4.5" x 1" Plate	121.17 - 121.42	1.0000	1.0000
L16	144	CCI 4.5" x 1" Plate	121.17 - 121.42	1.0000	1.0000
L16	145	CCI 4.5" x 1" Plate	121.17 - 121.42	1.0000	1.0000
L16	187	HCS 6X12 4AWG(1-5/8)	121.17 - 121.42	1.0000	1.0000
L16	190	AL7-50(1-5/8)	121.17 - 121.42	1.0000	1.0000
L16	218	Safety Line 3/8	121.17 - 121.42	1.0000	1.0000
L16	219	Climbing Rung	121.17 - 121.42	1.0000	1.0000
L17	139	CCI 4.5" x 1" Plate	117.92 - 120.67	1.0000	1.0000
L17	140	CCI 4.5" x 1" Plate	117.92 - 120.67	1.0000	1.0000
L17	141	CCI 4.5" x 1" Plate	117.92 - 120.67	1.0000	1.0000
L17	143	CCI 4.5" x 1" Plate	120.67 - 121.17	1.0000	1.0000
L17	144	CCI 4.5" x 1" Plate	120.67 - 121.17	1.0000	1.0000
L17	145	CCI 4.5" x 1" Plate	120.67 - 121.17	1.0000	1.0000
L17	187	HCS 6X12 4AWG(1-5/8)	116.17 - 121.17	1.0000	1.0000
L17	190	AL7-50(1-5/8)	116.17 - 121.17	1.0000	1.0000
L17	218	Safety Line 3/8	116.17 - 121.17	1.0000	1.0000
L17	219	Climbing Rung	116.17 - 121.17	1.0000	1.0000
L18	56	CCI 4.5" x 1" Plate	111.17 - 111.54	1.0000	1.0000
L18	57	CCI 4.5" x 1" Plate	111.17 - 111.54	1.0000	1.0000
L18	58	CCI 4.5" x 1" Plate	111.17 - 111.54	1.0000	1.0000
L18	187	HCS 6X12 4AWG(1-5/8)	111.17 - 116.17	1.0000	1.0000
L18	190	AL7-50(1-5/8)	111.17 - 116.17	1.0000	1.0000
L18	218	Safety Line 3/8	111.17 - 116.17	1.0000	1.0000
L18	219	Climbing Rung	111.17 - 116.17	1.0000	1.0000
L19	56	CCI 4.5" x 1" Plate	110.04 - 111.17	1.0000	1.0000
L19	57	CCI 4.5" x 1" Plate	110.04 -	1.0000	1.0000

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job
 87581.023.01 - Newington_1, CT (BU# 826217)

Page
 25 of 92

Project
 Date
 13:18:51 07/13/19

Client
 Crown Castle
 Designed by
 Pavan Upadhya

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
L19	58	CCI 4.5" x 1" Plate	111.17 110.04 - 111.17	1.0000	1.0000
L19	187	HCS 6X12 4AWG(1-5/8)	110.04 - 111.17	1.0000	1.0000
L19	190	AL7-50(1-5/8)	110.04 - 111.17	1.0000	1.0000
L19	218	Safety Line 3/8	110.04 - 111.17	1.0000	1.0000
L19	219	Climbing Rung	110.04 - 111.17	1.0000	1.0000
L20	56	CCI 4.5" x 1" Plate	109.79 - 110.04	1.0000	1.0000
L20	57	CCI 4.5" x 1" Plate	109.79 - 110.04	1.0000	1.0000
L20	58	CCI 4.5" x 1" Plate	109.79 - 110.04	1.0000	1.0000
L20	187	HCS 6X12 4AWG(1-5/8)	109.79 - 110.04	1.0000	1.0000
L20	190	AL7-50(1-5/8)	109.79 - 110.04	1.0000	1.0000
L20	218	Safety Line 3/8	109.79 - 110.04	1.0000	1.0000
L20	219	Climbing Rung	109.79 - 110.04	1.0000	1.0000
L21	18	CCI 4" x 0.75" Plate	105.08 - 106.58	1.0000	1.0000
L21	19	CCI 4" x 0.75" Plate	105.08 - 106.58	1.0000	1.0000
L21	20	CCI 4" x 0.75" Plate	105.08 - 106.58	1.0000	1.0000
L21	56	CCI 4.5" x 1" Plate	105.08 - 109.79	1.0000	1.0000
L21	57	CCI 4.5" x 1" Plate	105.08 - 109.79	1.0000	1.0000
L21	58	CCI 4.5" x 1" Plate	105.08 - 109.79	1.0000	1.0000
L21	135	CCI 4.5" x 1" Plate	105.08 - 107.17	1.0000	1.0000
L21	136	CCI 4.5" x 1" Plate	105.08 - 107.17	1.0000	1.0000
L21	137	CCI 4.5" x 1" Plate	105.08 - 107.17	1.0000	1.0000
L21	187	HCS 6X12 4AWG(1-5/8)	105.08 - 109.79	1.0000	1.0000
L21	190	AL7-50(1-5/8)	105.08 - 109.79	1.0000	1.0000
L21	218	Safety Line 3/8	105.08 - 109.79	1.0000	1.0000
L21	219	Climbing Rung	105.08 - 109.79	1.0000	1.0000
L22	18	CCI 4" x 0.75" Plate	104.83 - 105.08	1.0000	1.0000
L22	19	CCI 4" x 0.75" Plate	104.83 - 105.08	1.0000	1.0000
L22	20	CCI 4" x 0.75" Plate	104.83 - 105.08	1.0000	1.0000
L22	56	CCI 4.5" x 1" Plate	104.83 - 105.08	1.0000	1.0000
L22	57	CCI 4.5" x 1" Plate	104.83 - 105.08	1.0000	1.0000
L22	58	CCI 4.5" x 1" Plate	104.83 -	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
			105.08		
L22	135	CCI 4.5" x 1" Plate	104.83 - 105.08	1.0000	1.0000
L22	136	CCI 4.5" x 1" Plate	104.83 - 105.08	1.0000	1.0000
L22	137	CCI 4.5" x 1" Plate	104.83 - 105.08	1.0000	1.0000
L22	187	HCS 6X12 4AWG(1-5/8)	104.83 - 105.08	1.0000	1.0000
L22	190	AL7-50(1-5/8)	104.83 - 105.08	1.0000	1.0000
L22	218	Safety Line 3/8	104.83 - 105.08	1.0000	1.0000
L22	219	Climbing Rung	104.83 - 105.08	1.0000	1.0000
L23	18	CCI 4" x 0.75" Plate	101.58 - 104.83	1.0000	1.0000
L23	19	CCI 4" x 0.75" Plate	101.58 - 104.83	1.0000	1.0000
L23	20	CCI 4" x 0.75" Plate	101.58 - 104.83	1.0000	1.0000
L23	56	CCI 4.5" x 1" Plate	101.54 - 104.83	1.0000	1.0000
L23	57	CCI 4.5" x 1" Plate	101.54 - 104.83	1.0000	1.0000
L23	58	CCI 4.5" x 1" Plate	101.54 - 104.83	1.0000	1.0000
L23	127	CCI 4.5" x 1" Plate	100.92 - 101.42	1.0000	1.0000
L23	128	CCI 4.5" x 1" Plate	100.92 - 101.42	1.0000	1.0000
L23	129	CCI 4.5" x 1" Plate	100.92 - 101.42	1.0000	1.0000
L23	131	CCI 4.5" x 4" Plate	101.42 - 104.42	1.0000	1.0000
L23	132	CCI 4.5" x 4" Plate	101.42 - 104.42	1.0000	1.0000
L23	133	CCI 4.5" x 4" Plate	101.42 - 104.42	1.0000	1.0000
L23	135	CCI 4.5" x 1" Plate	104.42 - 104.83	1.0000	1.0000
L23	136	CCI 4.5" x 1" Plate	104.42 - 104.83	1.0000	1.0000
L23	137	CCI 4.5" x 1" Plate	104.42 - 104.83	1.0000	1.0000
L23	173	CCI 4.5" x 1" Plate	100.92 - 101.79	1.0000	1.0000
L23	174	CCI 4.5" x 1" Plate	100.92 - 101.79	1.0000	1.0000
L23	175	CCI 4.5" x 1" Plate	100.92 - 101.79	1.0000	1.0000
L23	177	CCI 4.5" x 3" Plate	101.79 - 103.29	1.0000	1.0000
L23	178	CCI 4.5" x 3" Plate	101.79 - 103.29	1.0000	1.0000
L23	179	CCI 4.5" x 3" Plate	101.79 - 103.29	1.0000	1.0000
L23	187	HCS 6X12 4AWG(1-5/8)	100.92 - 104.83	1.0000	1.0000
L23	190	AL7-50(1-5/8)	100.92 - 104.83	1.0000	1.0000
L23	218	Safety Line 3/8	100.92 -	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
			104.83		
L23	219	Climbing Rung	100.92 - 104.83	1.0000	1.0000
L24	127	CCI 4.5" x 1" Plate	100.67 - 100.92	1.0000	1.0000
L24	128	CCI 4.5" x 1" Plate	100.67 - 100.92	1.0000	1.0000
L24	129	CCI 4.5" x 1" Plate	100.67 - 100.92	1.0000	1.0000
L24	173	CCI 4.5" x 1" Plate	100.67 - 100.92	1.0000	1.0000
L24	174	CCI 4.5" x 1" Plate	100.67 - 100.92	1.0000	1.0000
L24	175	CCI 4.5" x 1" Plate	100.67 - 100.92	1.0000	1.0000
L24	187	HCS 6X12 4AWG(1-5/8)	100.67 - 100.92	1.0000	1.0000
L24	190	AL7-50(1-5/8)	100.67 - 100.92	1.0000	1.0000
L24	218	Safety Line 3/8	100.67 - 100.92	1.0000	1.0000
L24	219	Climbing Rung	100.67 - 100.92	1.0000	1.0000
L25	52	CCI 4.5" x 1" Plate	95.83 - 97.33	1.0000	1.0000
L25	53	CCI 4.5" x 1" Plate	95.83 - 97.33	1.0000	1.0000
L25	54	CCI 4.5" x 1" Plate	95.83 - 97.33	1.0000	1.0000
L25	123	CCI 4.5" x 1" Plate	97.92 - 100.42	1.0000	1.0000
L25	124	CCI 4.5" x 1" Plate	97.92 - 100.42	1.0000	1.0000
L25	125	CCI 4.5" x 1" Plate	97.92 - 100.42	1.0000	1.0000
L25	127	CCI 4.5" x 1" Plate	100.42 - 100.67	1.0000	1.0000
L25	128	CCI 4.5" x 1" Plate	100.42 - 100.67	1.0000	1.0000
L25	129	CCI 4.5" x 1" Plate	100.42 - 100.67	1.0000	1.0000
L25	173	CCI 4.5" x 1" Plate	98.42 - 100.67	1.0000	1.0000
L25	174	CCI 4.5" x 1" Plate	98.42 - 100.67	1.0000	1.0000
L25	175	CCI 4.5" x 1" Plate	98.42 - 100.67	1.0000	1.0000
L25	187	HCS 6X12 4AWG(1-5/8)	95.83 - 100.67	1.0000	1.0000
L25	190	AL7-50(1-5/8)	95.83 - 100.67	1.0000	1.0000
L25	218	Safety Line 3/8	95.83 - 100.67	1.0000	1.0000
L25	219	Climbing Rung	95.83 - 100.67	1.0000	1.0000
L26	52	CCI 4.5" x 1" Plate	95.58 - 95.83	1.0000	1.0000
L26	53	CCI 4.5" x 1" Plate	95.58 - 95.83	1.0000	1.0000
L26	54	CCI 4.5" x 1" Plate	95.58 - 95.83	1.0000	1.0000
L26	187	HCS 6X12 4AWG(1-5/8)	95.58 - 95.83	1.0000	1.0000
L26	190	AL7-50(1-5/8)	95.58 - 95.83	1.0000	1.0000
L26	218	Safety Line 3/8	95.58 - 95.83	1.0000	1.0000
L26	219	Climbing Rung	95.58 - 95.83	1.0000	1.0000
L27	52	CCI 4.5" x 1" Plate	90.58 - 95.58	1.0000	1.0000
L27	53	CCI 4.5" x 1" Plate	90.58 - 95.58	1.0000	1.0000
L27	54	CCI 4.5" x 1" Plate	90.58 - 95.58	1.0000	1.0000
L27	60	CCI 4.5" x 1" Plate	90.58 - 91.42	1.0000	1.0000
L27	61	CCI 4.5" x 1" Plate	90.58 - 91.42	1.0000	1.0000
L27	62	CCI 4.5" x 1" Plate	90.58 - 91.42	1.0000	1.0000
L27	187	HCS 6X12 4AWG(1-5/8)	90.58 - 95.58	1.0000	1.0000
L27	190	AL7-50(1-5/8)	90.58 - 95.58	1.0000	1.0000
L27	218	Safety Line 3/8	90.58 - 95.58	1.0000	1.0000
L27	219	Climbing Rung	90.58 - 95.58	1.0000	1.0000
L28	52	CCI 4.5" x 1" Plate	89.92 - 90.58	1.0000	1.0000
L28	53	CCI 4.5" x 1" Plate	89.92 - 90.58	1.0000	1.0000
L28	54	CCI 4.5" x 1" Plate	89.92 - 90.58	1.0000	1.0000

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job
87581.023.01 - Newington_1, CT (BU# 826217)

Page
28 of 92

Project
Date
13:18:51 07/13/19

Client
Crown Castle
Designed by
Pavan Upadhy

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L28	60	CCI 4.5" x 1" Plate	89.92 - 90.58	1.0000	1.0000
L28	61	CCI 4.5" x 1" Plate	89.92 - 90.58	1.0000	1.0000
L28	62	CCI 4.5" x 1" Plate	89.92 - 90.58	1.0000	1.0000
L28	187	HCS 6X12 4AWG(1-5/8)	89.92 - 90.58	1.0000	1.0000
L28	190	AL7-50(1-5/8)	89.92 - 90.58	1.0000	1.0000
L28	218	Safety Line 3/8	89.92 - 90.58	1.0000	1.0000
L28	219	Climbing Rung	89.92 - 90.58	1.0000	1.0000
L29	52	CCI 4.5" x 1" Plate	89.67 - 89.92	1.0000	1.0000
L29	53	CCI 4.5" x 1" Plate	89.67 - 89.92	1.0000	1.0000
L29	54	CCI 4.5" x 1" Plate	89.67 - 89.92	1.0000	1.0000
L29	60	CCI 4.5" x 1" Plate	89.67 - 89.92	1.0000	1.0000
L29	61	CCI 4.5" x 1" Plate	89.67 - 89.92	1.0000	1.0000
L29	62	CCI 4.5" x 1" Plate	89.67 - 89.92	1.0000	1.0000
L29	119	CCI 6.5" x 1.25" Plate	89.67 - 89.75	1.0000	1.0000
L29	120	CCI 6.5" x 1.25" Plate	89.67 - 89.75	1.0000	1.0000
L29	121	CCI 6.5" x 1.25" Plate	89.67 - 89.75	1.0000	1.0000
L29	187	HCS 6X12 4AWG(1-5/8)	89.67 - 89.92	1.0000	1.0000
L29	190	AL7-50(1-5/8)	89.67 - 89.92	1.0000	1.0000
L29	218	Safety Line 3/8	89.67 - 89.92	1.0000	1.0000
L29	219	Climbing Rung	89.67 - 89.92	1.0000	1.0000
L30	52	CCI 4.5" x 1" Plate	84.67 - 89.67	1.0000	1.0000
L30	53	CCI 4.5" x 1" Plate	84.67 - 89.67	1.0000	1.0000
L30	54	CCI 4.5" x 1" Plate	84.67 - 89.67	1.0000	1.0000
L30	60	CCI 4.5" x 1" Plate	84.67 - 89.67	1.0000	1.0000
L30	61	CCI 4.5" x 1" Plate	84.67 - 89.67	1.0000	1.0000
L30	62	CCI 4.5" x 1" Plate	84.67 - 89.67	1.0000	1.0000
L30	115	CCI 6.5" x 4.25" Plate	84.67 - 85.83	1.0000	1.0000
L30	116	CCI 6.5" x 4.25" Plate	84.67 - 85.83	1.0000	1.0000
L30	117	CCI 6.5" x 4.25" Plate	84.67 - 85.83	1.0000	1.0000
L30	119	CCI 6.5" x 1.25" Plate	85.83 - 89.67	1.0000	1.0000
L30	120	CCI 6.5" x 1.25" Plate	85.83 - 89.67	1.0000	1.0000
L30	121	CCI 6.5" x 1.25" Plate	85.83 - 89.67	1.0000	1.0000
L30	187	HCS 6X12 4AWG(1-5/8)	84.67 - 89.67	1.0000	1.0000
L30	190	AL7-50(1-5/8)	84.67 - 89.67	1.0000	1.0000
L30	218	Safety Line 3/8	84.67 - 89.67	1.0000	1.0000
L30	219	Climbing Rung	84.67 - 89.67	1.0000	1.0000
L31	52	CCI 4.5" x 1" Plate	81.33 - 84.67	1.0000	1.0000
L31	53	CCI 4.5" x 1" Plate	81.33 - 84.67	1.0000	1.0000
L31	54	CCI 4.5" x 1" Plate	81.33 - 84.67	1.0000	1.0000
L31	60	CCI 4.5" x 1" Plate	81.42 - 84.67	1.0000	1.0000
L31	61	CCI 4.5" x 1" Plate	81.42 - 84.67	1.0000	1.0000
L31	62	CCI 4.5" x 1" Plate	81.42 - 84.67	1.0000	1.0000
L31	115	CCI 6.5" x 4.25" Plate	80.83 - 84.67	1.0000	1.0000
L31	116	CCI 6.5" x 4.25" Plate	80.83 - 84.67	1.0000	1.0000
L31	117	CCI 6.5" x 4.25" Plate	80.83 - 84.67	1.0000	1.0000
L31	165	CCI 4.5" x 1" Plate	80.83 - 81.71	1.0000	1.0000
L31	166	CCI 4.5" x 1" Plate	80.83 - 81.71	1.0000	1.0000
L31	167	CCI 4.5" x 1" Plate	80.83 - 81.71	1.0000	1.0000
L31	169	CCI 4.5" x 3" Plate	81.71 - 83.20	1.0000	1.0000
L31	170	CCI 4.5" x 3" Plate	81.71 - 83.20	1.0000	1.0000
L31	171	CCI 4.5" x 3" Plate	81.71 - 83.20	1.0000	1.0000
L31	187	HCS 6X12 4AWG(1-5/8)	80.83 - 84.67	1.0000	1.0000
L31	190	AL7-50(1-5/8)	80.83 - 84.67	1.0000	1.0000
L31	218	Safety Line 3/8	80.83 - 84.67	1.0000	1.0000
L31	219	Climbing Rung	80.83 - 84.67	1.0000	1.0000
L32	111	CCI 6.5" x 1.25" Plate	80.33 - 80.50	1.0000	1.0000
L32	112	CCI 6.5" x 1.25" Plate	80.33 - 80.50	1.0000	1.0000
L32	113	CCI 6.5" x 1.25" Plate	80.33 - 80.50	1.0000	1.0000
L32	115	CCI 6.5" x 4.25" Plate	80.50 - 80.83	1.0000	1.0000
L32	116	CCI 6.5" x 4.25" Plate	80.50 - 80.83	1.0000	1.0000
L32	117	CCI 6.5" x 4.25" Plate	80.50 - 80.83	1.0000	1.0000
L32	165	CCI 4.5" x 1" Plate	80.33 - 80.83	1.0000	1.0000

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job
87581.023.01 - Newington_1, CT (BU# 826217)

Page
29 of 92

Project
Date
13:18:51 07/13/19

Client
Crown Castle
Designed by
Pavan Upadhy

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L32	166	CCI 4.5" x 1" Plate	80.33 - 80.83	1.0000	1.0000
L32	167	CCI 4.5" x 1" Plate	80.33 - 80.83	1.0000	1.0000
L32	187	HCS 6X12 4AWG(1-5/8)	80.33 - 80.83	1.0000	1.0000
L32	190	AL7-50(1-5/8)	80.33 - 80.83	1.0000	1.0000
L32	218	Safety Line 3/8	80.33 - 80.83	1.0000	1.0000
L32	219	Climbing Rung	80.33 - 80.83	1.0000	1.0000
L33	14	CCI 6" x 1" Plate	80.08 - 80.17	1.0000	1.0000
L33	15	CCI 6" x 1" Plate	80.08 - 80.17	1.0000	1.0000
L33	16	CCI 6" x 1" Plate	80.08 - 80.17	1.0000	1.0000
L33	107	CCI 6.5" x 1.25" Plate	80.08 - 80.33	1.0000	1.0000
L33	108	CCI 6.5" x 1.25" Plate	80.08 - 80.33	1.0000	1.0000
L33	109	CCI 6.5" x 1.25" Plate	80.08 - 80.33	1.0000	1.0000
L33	165	CCI 4.5" x 1" Plate	80.08 - 80.33	1.0000	1.0000
L33	166	CCI 4.5" x 1" Plate	80.08 - 80.33	1.0000	1.0000
L33	167	CCI 4.5" x 1" Plate	80.08 - 80.33	1.0000	1.0000
L33	187	HCS 6X12 4AWG(1-5/8)	80.08 - 80.33	1.0000	1.0000
L33	190	AL7-50(1-5/8)	80.08 - 80.33	1.0000	1.0000
L33	218	Safety Line 3/8	80.08 - 80.33	1.0000	1.0000
L33	219	Climbing Rung	80.08 - 80.33	1.0000	1.0000
L34	14	CCI 6" x 1" Plate	75.08 - 80.08	1.0000	1.0000
L34	15	CCI 6" x 1" Plate	75.08 - 80.08	1.0000	1.0000
L34	16	CCI 6" x 1" Plate	75.08 - 80.08	1.0000	1.0000
L34	107	CCI 6.5" x 1.25" Plate	76.50 - 80.08	1.0000	1.0000
L34	108	CCI 6.5" x 1.25" Plate	76.50 - 80.08	1.0000	1.0000
L34	109	CCI 6.5" x 1.25" Plate	76.50 - 80.08	1.0000	1.0000
L34	165	CCI 4.5" x 1" Plate	78.33 - 80.08	1.0000	1.0000
L34	166	CCI 4.5" x 1" Plate	78.33 - 80.08	1.0000	1.0000
L34	167	CCI 4.5" x 1" Plate	78.33 - 80.08	1.0000	1.0000
L34	187	HCS 6X12 4AWG(1-5/8)	75.08 - 80.08	1.0000	1.0000
L34	190	AL7-50(1-5/8)	75.08 - 80.08	1.0000	1.0000
L34	218	Safety Line 3/8	75.08 - 80.08	1.0000	1.0000
L34	219	Climbing Rung	75.08 - 80.08	1.0000	1.0000
L35	14	CCI 6" x 1" Plate	70.08 - 75.08	1.0000	1.0000
L35	15	CCI 6" x 1" Plate	70.08 - 75.08	1.0000	1.0000
L35	16	CCI 6" x 1" Plate	70.08 - 75.08	1.0000	1.0000
L35	47	CCI 4.5" x 1" Plate	70.08 - 71.00	1.0000	1.0000
L35	48	CCI 4.5" x 1" Plate	70.08 - 71.00	1.0000	1.0000
L35	49	CCI 4.5" x 1" Plate	70.08 - 71.00	1.0000	1.0000
L35	50	CCI 4.5" x 1" Plate	70.08 - 71.00	1.0000	1.0000
L35	100	CCI 8.5" x 1.25" Plate	70.08 - 73.42	1.0000	1.0000
L35	101	CCI 8.5" x 1.25" Plate	70.08 - 73.42	1.0000	1.0000
L35	102	CCI 8.5" x 1.25" Plate	70.08 - 73.42	1.0000	1.0000
L35	103	CCI 8.5" x 1.25" Plate	70.08 - 73.42	1.0000	1.0000
L35	104	CCI 8.5" x 1.25" Plate	70.08 - 73.42	1.0000	1.0000
L35	105	CCI 8.5" x 1.25" Plate	70.08 - 73.42	1.0000	1.0000
L35	187	HCS 6X12 4AWG(1-5/8)	70.08 - 75.08	1.0000	1.0000
L35	190	AL7-50(1-5/8)	70.08 - 75.08	1.0000	1.0000
L35	218	Safety Line 3/8	70.08 - 75.08	1.0000	1.0000
L35	219	Climbing Rung	70.08 - 75.08	1.0000	1.0000
L36	14	CCI 6" x 1" Plate	69.50 - 70.08	1.0000	1.0000
L36	15	CCI 6" x 1" Plate	69.50 - 70.08	1.0000	1.0000
L36	16	CCI 6" x 1" Plate	69.50 - 70.08	1.0000	1.0000
L36	47	CCI 4.5" x 1" Plate	69.50 - 70.08	1.0000	1.0000
L36	48	CCI 4.5" x 1" Plate	69.50 - 70.08	1.0000	1.0000
L36	49	CCI 4.5" x 1" Plate	69.50 - 70.08	1.0000	1.0000
L36	50	CCI 4.5" x 1" Plate	69.50 - 70.08	1.0000	1.0000
L36	100	CCI 8.5" x 1.25" Plate	69.50 - 70.08	1.0000	1.0000
L36	101	CCI 8.5" x 1.25" Plate	69.50 - 70.08	1.0000	1.0000
L36	102	CCI 8.5" x 1.25" Plate	69.50 - 70.08	1.0000	1.0000
L36	103	CCI 8.5" x 1.25" Plate	69.50 - 70.08	1.0000	1.0000
L36	104	CCI 8.5" x 1.25" Plate	69.50 - 70.08	1.0000	1.0000
L36	105	CCI 8.5" x 1.25" Plate	69.50 - 70.08	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
L36	187	HCS 6X12 4AWG(1-5/8)	69.50 - 70.08	1.0000	1.0000
L36	190	AL7-50(1-5/8)	69.50 - 70.08	1.0000	1.0000
L36	218	Safety Line 3/8	69.50 - 70.08	1.0000	1.0000
L36	219	Climbing Rung	69.50 - 70.08	1.0000	1.0000
L37	14	CCI 6" x 1" Plate	69.25 - 69.50	1.0000	1.0000
L37	15	CCI 6" x 1" Plate	69.25 - 69.50	1.0000	1.0000
L37	16	CCI 6" x 1" Plate	69.25 - 69.50	1.0000	1.0000
L37	47	CCI 4.5" x 1" Plate	69.25 - 69.50	1.0000	1.0000
L37	48	CCI 4.5" x 1" Plate	69.25 - 69.50	1.0000	1.0000
L37	49	CCI 4.5" x 1" Plate	69.25 - 69.50	1.0000	1.0000
L37	50	CCI 4.5" x 1" Plate	69.25 - 69.50	1.0000	1.0000
L37	100	CCI 8.5" x 1.25" Plate	69.25 - 69.50	1.0000	1.0000
L37	101	CCI 8.5" x 1.25" Plate	69.25 - 69.50	1.0000	1.0000
L37	102	CCI 8.5" x 1.25" Plate	69.25 - 69.50	1.0000	1.0000
L37	103	CCI 8.5" x 1.25" Plate	69.25 - 69.50	1.0000	1.0000
L37	104	CCI 8.5" x 1.25" Plate	69.25 - 69.50	1.0000	1.0000
L37	105	CCI 8.5" x 1.25" Plate	69.25 - 69.50	1.0000	1.0000
L37	187	HCS 6X12 4AWG(1-5/8)	69.25 - 69.50	1.0000	1.0000
L37	190	AL7-50(1-5/8)	69.25 - 69.50	1.0000	1.0000
L37	218	Safety Line 3/8	69.25 - 69.50	1.0000	1.0000
L37	219	Climbing Rung	69.25 - 69.50	1.0000	1.0000
L38	14	CCI 6" x 1" Plate	64.25 - 69.25	1.0000	1.0000
L38	15	CCI 6" x 1" Plate	64.25 - 69.25	1.0000	1.0000
L38	16	CCI 6" x 1" Plate	64.25 - 69.25	1.0000	1.0000
L38	27	1" x 2" Plate	64.25 - 66.17	1.0000	1.0000
L38	28	1" x 2" Plate	64.25 - 66.17	1.0000	1.0000
L38	29	1" x 2" Plate	64.25 - 66.17	1.0000	1.0000
L38	30	1" x 2" Plate	64.25 - 66.17	1.0000	1.0000
L38	47	CCI 4.5" x 1" Plate	64.25 - 69.25	1.0000	1.0000
L38	48	CCI 4.5" x 1" Plate	64.25 - 69.25	1.0000	1.0000
L38	49	CCI 4.5" x 1" Plate	64.25 - 69.25	1.0000	1.0000
L38	50	CCI 4.5" x 1" Plate	64.25 - 69.25	1.0000	1.0000
L38	93	CCI 8.5" x 4.25" Plate	64.25 - 68.42	1.0000	1.0000
L38	94	CCI 8.5" x 4.25" Plate	64.25 - 68.42	1.0000	1.0000
L38	95	CCI 8.5" x 4.25" Plate	64.25 - 68.42	1.0000	1.0000
L38	96	CCI 8.5" x 4.25" Plate	64.25 - 68.42	1.0000	1.0000
L38	97	CCI 8.5" x 4.25" Plate	64.25 - 68.42	1.0000	1.0000
L38	98	CCI 8.5" x 4.25" Plate	64.25 - 68.42	1.0000	1.0000
L38	100	CCI 8.5" x 1.25" Plate	68.42 - 69.25	1.0000	1.0000
L38	101	CCI 8.5" x 1.25" Plate	68.42 - 69.25	1.0000	1.0000
L38	102	CCI 8.5" x 1.25" Plate	68.42 - 69.25	1.0000	1.0000
L38	103	CCI 8.5" x 1.25" Plate	68.42 - 69.25	1.0000	1.0000
L38	104	CCI 8.5" x 1.25" Plate	68.42 - 69.25	1.0000	1.0000
L38	105	CCI 8.5" x 1.25" Plate	68.42 - 69.25	1.0000	1.0000
L38	187	HCS 6X12 4AWG(1-5/8)	64.25 - 69.25	1.0000	1.0000
L38	190	AL7-50(1-5/8)	64.25 - 69.25	1.0000	1.0000
L38	218	Safety Line 3/8	64.25 - 69.25	1.0000	1.0000
L38	219	Climbing Rung	64.25 - 69.25	1.0000	1.0000
L39	14	CCI 6" x 1" Plate	61.17 - 64.25	1.0000	1.0000
L39	15	CCI 6" x 1" Plate	61.17 - 64.25	1.0000	1.0000
L39	16	CCI 6" x 1" Plate	61.17 - 64.25	1.0000	1.0000
L39	27	1" x 2" Plate	61.08 - 64.25	1.0000	1.0000
L39	28	1" x 2" Plate	61.08 - 64.25	1.0000	1.0000
L39	29	1" x 2" Plate	61.08 - 64.25	1.0000	1.0000
L39	30	1" x 2" Plate	61.08 - 64.25	1.0000	1.0000
L39	47	CCI 4.5" x 1" Plate	61.00 - 64.25	1.0000	1.0000
L39	48	CCI 4.5" x 1" Plate	61.00 - 64.25	1.0000	1.0000
L39	49	CCI 4.5" x 1" Plate	61.00 - 64.25	1.0000	1.0000
L39	50	CCI 4.5" x 1" Plate	61.00 - 64.25	1.0000	1.0000
L39	86	CCI 8.5" x 1.25" Plate	60.58 - 61.08	1.0000	1.0000
L39	87	CCI 8.5" x 1.25" Plate	60.58 - 61.08	1.0000	1.0000
L39	88	CCI 8.5" x 1.25" Plate	60.58 - 61.08	1.0000	1.0000

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 31 of 92
Project	Date 13:18:51 07/13/19
Client Crown Castle	Designed by Pavan Upadhy

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L39	89	CCI 8.5" x 1.25" Plate	60.58 - 61.08	1.0000	1.0000
L39	90	CCI 8.5" x 1.25" Plate	60.58 - 61.08	1.0000	1.0000
L39	91	CCI 8.5" x 1.25" Plate	60.58 - 61.08	1.0000	1.0000
L39	93	CCI 8.5" x 4.25" Plate	61.08 - 64.25	1.0000	1.0000
L39	94	CCI 8.5" x 4.25" Plate	61.08 - 64.25	1.0000	1.0000
L39	95	CCI 8.5" x 4.25" Plate	61.08 - 64.25	1.0000	1.0000
L39	96	CCI 8.5" x 4.25" Plate	61.08 - 64.25	1.0000	1.0000
L39	97	CCI 8.5" x 4.25" Plate	61.08 - 64.25	1.0000	1.0000
L39	98	CCI 8.5" x 4.25" Plate	61.08 - 64.25	1.0000	1.0000
L39	155	CCI 4.5" x 1" Plate	60.58 - 61.46	1.0000	1.0000
L39	156	CCI 4.5" x 1" Plate	60.58 - 61.46	1.0000	1.0000
L39	157	CCI 4.5" x 1" Plate	60.58 - 61.46	1.0000	1.0000
L39	158	CCI 4.5" x 1" Plate	60.58 - 61.46	1.0000	1.0000
L39	160	CCI 4.5" x 3" Plate	61.55 - 62.96	1.0000	1.0000
L39	161	CCI 4.5" x 3" Plate	61.55 - 62.96	1.0000	1.0000
L39	162	CCI 4.5" x 3" Plate	61.55 - 62.96	1.0000	1.0000
L39	163	CCI 4.5" x 3" Plate	61.55 - 62.96	1.0000	1.0000
L39	187	HCS 6X12 4AWG(1-5/8)	60.58 - 64.25	1.0000	1.0000
L39	190	AL7-50(1-5/8)	60.58 - 64.25	1.0000	1.0000
L39	218	Safety Line 3/8	60.58 - 64.25	1.0000	1.0000
L39	219	Climbing Rung	60.58 - 64.25	1.0000	1.0000
L40	86	CCI 8.5" x 1.25" Plate	60.33 - 60.58	1.0000	1.0000
L40	87	CCI 8.5" x 1.25" Plate	60.33 - 60.58	1.0000	1.0000
L40	88	CCI 8.5" x 1.25" Plate	60.33 - 60.58	1.0000	1.0000
L40	89	CCI 8.5" x 1.25" Plate	60.33 - 60.58	1.0000	1.0000
L40	90	CCI 8.5" x 1.25" Plate	60.33 - 60.58	1.0000	1.0000
L40	91	CCI 8.5" x 1.25" Plate	60.33 - 60.58	1.0000	1.0000
L40	155	CCI 4.5" x 1" Plate	60.33 - 60.58	1.0000	1.0000
L40	156	CCI 4.5" x 1" Plate	60.33 - 60.58	1.0000	1.0000
L40	157	CCI 4.5" x 1" Plate	60.33 - 60.58	1.0000	1.0000
L40	158	CCI 4.5" x 1" Plate	60.33 - 60.58	1.0000	1.0000
L40	187	HCS 6X12 4AWG(1-5/8)	60.33 - 60.58	1.0000	1.0000
L40	190	AL7-50(1-5/8)	60.33 - 60.58	1.0000	1.0000
L40	218	Safety Line 3/8	60.33 - 60.58	1.0000	1.0000
L40	219	Climbing Rung	60.33 - 60.58	1.0000	1.0000
L41	10	CCI 6.5" x 1.25" Plate	55.33 - 59.92	1.0000	1.0000
L41	11	CCI 6.5" x 1.25" Plate	55.33 - 59.92	1.0000	1.0000
L41	12	CCI 6.5" x 1.25" Plate	55.33 - 59.92	1.0000	1.0000
L41	79	CCI 8.5" x 1.25" Plate	55.33 - 60.08	1.0000	1.0000
L41	80	CCI 8.5" x 1.25" Plate	55.33 - 60.08	1.0000	1.0000
L41	81	CCI 8.5" x 1.25" Plate	55.33 - 60.08	1.0000	1.0000
L41	82	CCI 8.5" x 1.25" Plate	55.33 - 60.08	1.0000	1.0000
L41	83	CCI 8.5" x 1.25" Plate	55.33 - 60.08	1.0000	1.0000
L41	84	CCI 8.5" x 1.25" Plate	55.33 - 60.08	1.0000	1.0000
L41	86	CCI 8.5" x 1.25" Plate	60.08 - 60.33	1.0000	1.0000
L41	87	CCI 8.5" x 1.25" Plate	60.08 - 60.33	1.0000	1.0000
L41	88	CCI 8.5" x 1.25" Plate	60.08 - 60.33	1.0000	1.0000
L41	89	CCI 8.5" x 1.25" Plate	60.08 - 60.33	1.0000	1.0000
L41	90	CCI 8.5" x 1.25" Plate	60.08 - 60.33	1.0000	1.0000
L41	91	CCI 8.5" x 1.25" Plate	60.08 - 60.33	1.0000	1.0000
L41	155	CCI 4.5" x 1" Plate	58.00 - 60.33	1.0000	1.0000
L41	156	CCI 4.5" x 1" Plate	58.00 - 60.33	1.0000	1.0000
L41	157	CCI 4.5" x 1" Plate	58.00 - 60.33	1.0000	1.0000
L41	158	CCI 4.5" x 1" Plate	58.00 - 60.33	1.0000	1.0000
L41	187	HCS 6X12 4AWG(1-5/8)	55.33 - 60.33	1.0000	1.0000
L41	190	AL7-50(1-5/8)	55.33 - 60.33	1.0000	1.0000
L41	218	Safety Line 3/8	55.33 - 60.33	1.0000	1.0000
L41	219	Climbing Rung	55.33 - 60.33	1.0000	1.0000
L42	10	CCI 6.5" x 1.25" Plate	52.17 - 55.33	1.0000	1.0000
L42	11	CCI 6.5" x 1.25" Plate	52.17 - 55.33	1.0000	1.0000
L42	12	CCI 6.5" x 1.25" Plate	52.17 - 55.33	1.0000	1.0000
L42	79	CCI 8.5" x 1.25" Plate	55.25 - 55.33	1.0000	1.0000

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job
87581.023.01 - Newington_1, CT (BU# 826217)

Page
32 of 92

Project
Date
13:18:51 07/13/19

Client
Crown Castle
Designed by
Pavan Upadhy

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L42	80	CCI 8.5" x 1.25" Plate	55.25 - 55.33	1.0000	1.0000
L42	81	CCI 8.5" x 1.25" Plate	55.25 - 55.33	1.0000	1.0000
L42	82	CCI 8.5" x 1.25" Plate	55.25 - 55.33	1.0000	1.0000
L42	83	CCI 8.5" x 1.25" Plate	55.25 - 55.33	1.0000	1.0000
L42	84	CCI 8.5" x 1.25" Plate	55.25 - 55.33	1.0000	1.0000
L42	187	HCS 6X12 4AWG(1-5/8)	52.17 - 55.33	1.0000	1.0000
L42	190	AL7-50(1-5/8)	52.17 - 55.33	1.0000	1.0000
L42	218	Safety Line 3/8	52.17 - 55.33	1.0000	1.0000
L42	219	Climbing Rung	52.17 - 55.33	1.0000	1.0000
L43	10	CCI 6.5" x 1.25" Plate	51.92 - 52.17	1.0000	1.0000
L43	11	CCI 6.5" x 1.25" Plate	51.92 - 52.17	1.0000	1.0000
L43	12	CCI 6.5" x 1.25" Plate	51.92 - 52.17	1.0000	1.0000
L43	187	HCS 6X12 4AWG(1-5/8)	51.92 - 52.17	1.0000	1.0000
L43	190	AL7-50(1-5/8)	51.92 - 52.17	1.0000	1.0000
L43	218	Safety Line 3/8	51.92 - 52.17	1.0000	1.0000
L43	219	Climbing Rung	51.92 - 52.17	1.0000	1.0000
L44	10	CCI 6.5" x 1.25" Plate	46.92 - 51.92	1.0000	1.0000
L44	11	CCI 6.5" x 1.25" Plate	46.92 - 51.92	1.0000	1.0000
L44	12	CCI 6.5" x 1.25" Plate	46.92 - 51.92	1.0000	1.0000
L44	22	1" x 2" Plate	46.92 - 50.42	1.0000	1.0000
L44	23	1" x 2" Plate	46.92 - 50.42	1.0000	1.0000
L44	24	1" x 2" Plate	46.92 - 50.42	1.0000	1.0000
L44	25	1" x 2" Plate	46.92 - 50.42	1.0000	1.0000
L44	42	CCI 6" x 1" Plate	46.92 - 50.17	1.0000	1.0000
L44	43	CCI 6" x 1" Plate	46.92 - 50.17	1.0000	1.0000
L44	44	CCI 6" x 1" Plate	46.92 - 50.17	1.0000	1.0000
L44	45	CCI 6" x 1" Plate	46.92 - 50.17	1.0000	1.0000
L44	72	CCI 6.5" x 1.25" Plate	46.92 - 47.83	1.0000	1.0000
L44	73	CCI 6.5" x 1.25" Plate	46.92 - 47.83	1.0000	1.0000
L44	74	CCI 6.5" x 1.25" Plate	46.92 - 47.83	1.0000	1.0000
L44	75	CCI 6.5" x 1.25" Plate	46.92 - 47.83	1.0000	1.0000
L44	76	CCI 6.5" x 1.25" Plate	46.92 - 47.83	1.0000	1.0000
L44	77	CCI 6.5" x 1.25" Plate	46.92 - 47.83	1.0000	1.0000
L44	187	HCS 6X12 4AWG(1-5/8)	46.92 - 51.92	1.0000	1.0000
L44	190	AL7-50(1-5/8)	46.92 - 51.92	1.0000	1.0000
L44	218	Safety Line 3/8	46.92 - 51.92	1.0000	1.0000
L44	219	Climbing Rung	46.92 - 51.92	1.0000	1.0000
L45	10	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	11	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	12	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	22	1" x 2" Plate	41.92 - 46.92	1.0000	1.0000
L45	23	1" x 2" Plate	41.92 - 46.92	1.0000	1.0000
L45	24	1" x 2" Plate	41.92 - 46.92	1.0000	1.0000
L45	25	1" x 2" Plate	41.92 - 46.92	1.0000	1.0000
L45	42	CCI 6" x 1" Plate	41.92 - 46.92	1.0000	1.0000
L45	43	CCI 6" x 1" Plate	41.92 - 46.92	1.0000	1.0000
L45	44	CCI 6" x 1" Plate	41.92 - 46.92	1.0000	1.0000
L45	45	CCI 6" x 1" Plate	41.92 - 46.92	1.0000	1.0000
L45	72	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	73	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	74	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	75	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	76	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	77	CCI 6.5" x 1.25" Plate	41.92 - 46.92	1.0000	1.0000
L45	187	HCS 6X12 4AWG(1-5/8)	41.92 - 46.92	1.0000	1.0000
L45	190	AL7-50(1-5/8)	41.92 - 46.92	1.0000	1.0000
L45	218	Safety Line 3/8	41.92 - 46.92	1.0000	1.0000
L45	219	Climbing Rung	41.92 - 46.92	1.0000	1.0000
L46	10	CCI 6.5" x 1.25" Plate	40.83 - 41.92	1.0000	1.0000
L46	11	CCI 6.5" x 1.25" Plate	40.83 - 41.92	1.0000	1.0000
L46	12	CCI 6.5" x 1.25" Plate	40.83 - 41.92	1.0000	1.0000
L46	22	1" x 2" Plate	40.58 - 41.92	1.0000	1.0000

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job
 87581.023.01 - Newington_1, CT (BU# 826217)

Page
 33 of 92

Project
 Date
 13:18:51 07/13/19

Client
 Crown Castle
 Designed by
 Pavan Upadhy

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
L46	23	1" x 2" Plate	40.58 - 41.92	1.0000	1.0000
L46	24	1" x 2" Plate	40.58 - 41.92	1.0000	1.0000
L46	25	1" x 2" Plate	40.58 - 41.92	1.0000	1.0000
L46	42	CCI 6" x 1" Plate	40.33 - 41.92	1.0000	1.0000
L46	43	CCI 6" x 1" Plate	40.33 - 41.92	1.0000	1.0000
L46	44	CCI 6" x 1" Plate	40.33 - 41.92	1.0000	1.0000
L46	45	CCI 6" x 1" Plate	40.33 - 41.92	1.0000	1.0000
L46	72	CCI 6.5" x 1.25" Plate	40.33 - 41.92	1.0000	1.0000
L46	73	CCI 6.5" x 1.25" Plate	40.33 - 41.92	1.0000	1.0000
L46	74	CCI 6.5" x 1.25" Plate	40.33 - 41.92	1.0000	1.0000
L46	75	CCI 6.5" x 1.25" Plate	40.33 - 41.92	1.0000	1.0000
L46	76	CCI 6.5" x 1.25" Plate	40.33 - 41.92	1.0000	1.0000
L46	77	CCI 6.5" x 1.25" Plate	40.33 - 41.92	1.0000	1.0000
L46	187	HCS 6X12 4AWG(1-5/8)	40.33 - 41.92	1.0000	1.0000
L46	190	AL7-50(1-5/8)	40.33 - 41.92	1.0000	1.0000
L46	218	Safety Line 3/8	40.33 - 41.92	1.0000	1.0000
L46	219	Climbing Rung	40.33 - 41.92	1.0000	1.0000
L47	42	CCI 6" x 1" Plate	40.08 - 40.33	1.0000	1.0000
L47	43	CCI 6" x 1" Plate	40.08 - 40.33	1.0000	1.0000
L47	44	CCI 6" x 1" Plate	40.08 - 40.33	1.0000	1.0000
L47	45	CCI 6" x 1" Plate	40.08 - 40.33	1.0000	1.0000
L47	72	CCI 6.5" x 1.25" Plate	40.08 - 40.33	1.0000	1.0000
L47	73	CCI 6.5" x 1.25" Plate	40.08 - 40.33	1.0000	1.0000
L47	74	CCI 6.5" x 1.25" Plate	40.08 - 40.33	1.0000	1.0000
L47	75	CCI 6.5" x 1.25" Plate	40.08 - 40.33	1.0000	1.0000
L47	76	CCI 6.5" x 1.25" Plate	40.08 - 40.33	1.0000	1.0000
L47	77	CCI 6.5" x 1.25" Plate	40.08 - 40.33	1.0000	1.0000
L47	187	HCS 6X12 4AWG(1-5/8)	40.08 - 40.33	1.0000	1.0000
L47	190	AL7-50(1-5/8)	40.08 - 40.33	1.0000	1.0000
L47	218	Safety Line 3/8	40.08 - 40.33	1.0000	1.0000
L47	219	Climbing Rung	40.08 - 40.33	1.0000	1.0000
L48	6	CCI 6" x 1" Plate	35.08 - 39.75	1.0000	1.0000
L48	7	CCI 6" x 1" Plate	35.08 - 39.75	1.0000	1.0000
L48	8	CCI 6" x 1" Plate	35.08 - 39.75	1.0000	1.0000
L48	42	CCI 6" x 1" Plate	37.17 - 40.08	1.0000	1.0000
L48	43	CCI 6" x 1" Plate	37.17 - 40.08	1.0000	1.0000
L48	44	CCI 6" x 1" Plate	37.17 - 40.08	1.0000	1.0000
L48	45	CCI 6" x 1" Plate	37.17 - 40.08	1.0000	1.0000
L48	72	CCI 6.5" x 1.25" Plate	35.08 - 40.08	1.0000	1.0000
L48	73	CCI 6.5" x 1.25" Plate	35.08 - 40.08	1.0000	1.0000
L48	74	CCI 6.5" x 1.25" Plate	35.08 - 40.08	1.0000	1.0000
L48	75	CCI 6.5" x 1.25" Plate	35.08 - 40.08	1.0000	1.0000
L48	76	CCI 6.5" x 1.25" Plate	35.08 - 40.08	1.0000	1.0000
L48	77	CCI 6.5" x 1.25" Plate	35.08 - 40.08	1.0000	1.0000
L48	187	HCS 6X12 4AWG(1-5/8)	35.08 - 40.08	1.0000	1.0000
L48	190	AL7-50(1-5/8)	35.08 - 40.08	1.0000	1.0000
L48	218	Safety Line 3/8	35.08 - 40.08	1.0000	1.0000
L48	219	Climbing Rung	35.08 - 40.08	1.0000	1.0000
L49	6	CCI 6" x 1" Plate	30.08 - 35.08	1.0000	1.0000
L49	7	CCI 6" x 1" Plate	30.08 - 35.08	1.0000	1.0000
L49	8	CCI 6" x 1" Plate	30.08 - 35.08	1.0000	1.0000
L49	72	CCI 6.5" x 1.25" Plate	32.83 - 35.08	1.0000	1.0000
L49	73	CCI 6.5" x 1.25" Plate	32.83 - 35.08	1.0000	1.0000
L49	74	CCI 6.5" x 1.25" Plate	32.83 - 35.08	1.0000	1.0000
L49	75	CCI 6.5" x 1.25" Plate	32.83 - 35.08	1.0000	1.0000
L49	76	CCI 6.5" x 1.25" Plate	32.83 - 35.08	1.0000	1.0000
L49	77	CCI 6.5" x 1.25" Plate	32.83 - 35.08	1.0000	1.0000
L49	187	HCS 6X12 4AWG(1-5/8)	30.08 - 35.08	1.0000	1.0000
L49	190	AL7-50(1-5/8)	30.08 - 35.08	1.0000	1.0000
L49	218	Safety Line 3/8	30.08 - 35.08	1.0000	1.0000
L49	219	Climbing Rung	30.08 - 35.08	1.0000	1.0000
L50	6	CCI 6" x 1" Plate	28.00 - 30.08	1.0000	1.0000

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	34 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhya

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L50	7	CCI 6" x 1" Plate	28.00 - 30.08	1.0000	1.0000
L50	8	CCI 6" x 1" Plate	28.00 - 30.08	1.0000	1.0000
L50	37	CCI 6" x 1" Plate	28.00 - 30.00	1.0000	1.0000
L50	38	CCI 6" x 1" Plate	28.00 - 30.00	1.0000	1.0000
L50	39	CCI 6" x 1" Plate	28.00 - 30.00	1.0000	1.0000
L50	40	CCI 6" x 1" Plate	28.00 - 30.00	1.0000	1.0000
L50	187	HCS 6X12 4AWG(1-5/8)	28.00 - 30.08	1.0000	1.0000
L50	190	AL7-50(1-5/8)	28.00 - 30.08	1.0000	1.0000
L50	218	Safety Line 3/8	28.00 - 30.08	1.0000	1.0000
L50	219	Climbing Rung	28.00 - 30.08	1.0000	1.0000
L51	6	CCI 6" x 1" Plate	27.75 - 28.00	1.0000	1.0000
L51	7	CCI 6" x 1" Plate	27.75 - 28.00	1.0000	1.0000
L51	8	CCI 6" x 1" Plate	27.75 - 28.00	1.0000	1.0000
L51	37	CCI 6" x 1" Plate	27.75 - 28.00	1.0000	1.0000
L51	38	CCI 6" x 1" Plate	27.75 - 28.00	1.0000	1.0000
L51	39	CCI 6" x 1" Plate	27.75 - 28.00	1.0000	1.0000
L51	40	CCI 6" x 1" Plate	27.75 - 28.00	1.0000	1.0000
L51	187	HCS 6X12 4AWG(1-5/8)	27.75 - 28.00	1.0000	1.0000
L51	190	AL7-50(1-5/8)	27.75 - 28.00	1.0000	1.0000
L51	218	Safety Line 3/8	27.75 - 28.00	1.0000	1.0000
L51	219	Climbing Rung	27.75 - 28.00	1.0000	1.0000
L52	6	CCI 6" x 1" Plate	22.75 - 27.75	1.0000	1.0000
L52	7	CCI 6" x 1" Plate	22.75 - 27.75	1.0000	1.0000
L52	8	CCI 6" x 1" Plate	22.75 - 27.75	1.0000	1.0000
L52	37	CCI 6" x 1" Plate	22.75 - 27.75	1.0000	1.0000
L52	38	CCI 6" x 1" Plate	22.75 - 27.75	1.0000	1.0000
L52	39	CCI 6" x 1" Plate	22.75 - 27.75	1.0000	1.0000
L52	40	CCI 6" x 1" Plate	22.75 - 27.75	1.0000	1.0000
L52	65	CCI 6.5" x 1.25" Plate	22.75 - 27.50	1.0000	1.0000
L52	66	CCI 6.5" x 1.25" Plate	22.75 - 27.50	1.0000	1.0000
L52	67	CCI 6.5" x 1.25" Plate	22.75 - 27.50	1.0000	1.0000
L52	68	CCI 6.5" x 1.25" Plate	22.75 - 27.50	1.0000	1.0000
L52	69	CCI 6.5" x 1.25" Plate	22.75 - 27.50	1.0000	1.0000
L52	70	CCI 6.5" x 1.25" Plate	22.75 - 27.50	1.0000	1.0000
L52	187	HCS 6X12 4AWG(1-5/8)	22.75 - 27.75	1.0000	1.0000
L52	190	AL7-50(1-5/8)	22.75 - 27.75	1.0000	1.0000
L52	218	Safety Line 3/8	22.75 - 27.75	1.0000	1.0000
L52	219	Climbing Rung	22.75 - 27.75	1.0000	1.0000
L53	6	CCI 6" x 1" Plate	20.75 - 22.75	1.0000	1.0000
L53	7	CCI 6" x 1" Plate	20.75 - 22.75	1.0000	1.0000
L53	8	CCI 6" x 1" Plate	20.75 - 22.75	1.0000	1.0000
L53	37	CCI 6" x 1" Plate	20.08 - 22.75	1.0000	1.0000
L53	38	CCI 6" x 1" Plate	20.08 - 22.75	1.0000	1.0000
L53	39	CCI 6" x 1" Plate	20.08 - 22.75	1.0000	1.0000
L53	40	CCI 6" x 1" Plate	20.08 - 22.75	1.0000	1.0000
L53	65	CCI 6.5" x 1.25" Plate	20.08 - 22.75	1.0000	1.0000
L53	66	CCI 6.5" x 1.25" Plate	20.08 - 22.75	1.0000	1.0000
L53	67	CCI 6.5" x 1.25" Plate	20.08 - 22.75	1.0000	1.0000
L53	68	CCI 6.5" x 1.25" Plate	20.08 - 22.75	1.0000	1.0000
L53	69	CCI 6.5" x 1.25" Plate	20.08 - 22.75	1.0000	1.0000
L53	70	CCI 6.5" x 1.25" Plate	20.08 - 22.75	1.0000	1.0000
L53	187	HCS 6X12 4AWG(1-5/8)	20.08 - 22.75	1.0000	1.0000
L53	190	AL7-50(1-5/8)	20.08 - 22.75	1.0000	1.0000
L53	218	Safety Line 3/8	20.08 - 22.75	1.0000	1.0000
L53	219	Climbing Rung	20.08 - 22.75	1.0000	1.0000
L54	37	CCI 6" x 1" Plate	19.83 - 20.08	1.0000	1.0000
L54	38	CCI 6" x 1" Plate	19.83 - 20.08	1.0000	1.0000
L54	39	CCI 6" x 1" Plate	19.83 - 20.08	1.0000	1.0000
L54	40	CCI 6" x 1" Plate	19.83 - 20.08	1.0000	1.0000
L54	65	CCI 6.5" x 1.25" Plate	19.83 - 20.08	1.0000	1.0000
L54	66	CCI 6.5" x 1.25" Plate	19.83 - 20.08	1.0000	1.0000
L54	67	CCI 6.5" x 1.25" Plate	19.83 - 20.08	1.0000	1.0000

tnxTower

B+T Group
1717 S, Boulder, Suite 300
Tulsa, OK 74119
Phone: (918) 587-4630
FAX:

Job
87581.023.01 - Newington_1, CT (BU# 826217)

Page
35 of 92

Project
Date
13:18:51 07/13/19

Client
Crown Castle
Designed by
Pavan Upadhya

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
L54	68	CCI 6.5" x 1.25" Plate	19.83 - 20.08	1.0000	1.0000
L54	69	CCI 6.5" x 1.25" Plate	19.83 - 20.08	1.0000	1.0000
L54	70	CCI 6.5" x 1.25" Plate	19.83 - 20.08	1.0000	1.0000
L54	187	HCS 6X12 4AWG(1-5/8)	19.83 - 20.08	1.0000	1.0000
L54	190	AL7-50(1-5/8)	19.83 - 20.08	1.0000	1.0000
L54	218	Safety Line 3/8	19.83 - 20.08	1.0000	1.0000
L54	219	Climbing Rung	19.83 - 20.08	1.0000	1.0000
L55	32	CCI 6" x 1" Plate	17.00 - 19.00	1.0000	1.0000
L55	33	CCI 6" x 1" Plate	17.00 - 19.00	1.0000	1.0000
L55	34	CCI 6" x 1" Plate	17.00 - 19.00	1.0000	1.0000
L55	35	CCI 6" x 1" Plate	17.00 - 19.00	1.0000	1.0000
L55	37	CCI 6" x 1" Plate	17.00 - 19.83	1.0000	1.0000
L55	38	CCI 6" x 1" Plate	17.00 - 19.83	1.0000	1.0000
L55	39	CCI 6" x 1" Plate	17.00 - 19.83	1.0000	1.0000
L55	40	CCI 6" x 1" Plate	17.00 - 19.83	1.0000	1.0000
L55	65	CCI 6.5" x 1.25" Plate	17.00 - 19.83	1.0000	1.0000
L55	66	CCI 6.5" x 1.25" Plate	17.00 - 19.83	1.0000	1.0000
L55	67	CCI 6.5" x 1.25" Plate	17.00 - 19.83	1.0000	1.0000
L55	68	CCI 6.5" x 1.25" Plate	17.00 - 19.83	1.0000	1.0000
L55	69	CCI 6.5" x 1.25" Plate	17.00 - 19.83	1.0000	1.0000
L55	70	CCI 6.5" x 1.25" Plate	17.00 - 19.83	1.0000	1.0000
L55	187	HCS 6X12 4AWG(1-5/8)	17.00 - 19.83	1.0000	1.0000
L55	190	AL7-50(1-5/8)	17.00 - 19.83	1.0000	1.0000
L55	218	Safety Line 3/8	17.00 - 19.83	1.0000	1.0000
L55	219	Climbing Rung	17.00 - 19.83	1.0000	1.0000
L56	32	CCI 6" x 1" Plate	16.75 - 17.00	1.0000	1.0000
L56	33	CCI 6" x 1" Plate	16.75 - 17.00	1.0000	1.0000
L56	34	CCI 6" x 1" Plate	16.75 - 17.00	1.0000	1.0000
L56	35	CCI 6" x 1" Plate	16.75 - 17.00	1.0000	1.0000
L56	65	CCI 6.5" x 1.25" Plate	16.75 - 17.00	1.0000	1.0000
L56	66	CCI 6.5" x 1.25" Plate	16.75 - 17.00	1.0000	1.0000
L56	67	CCI 6.5" x 1.25" Plate	16.75 - 17.00	1.0000	1.0000
L56	68	CCI 6.5" x 1.25" Plate	16.75 - 17.00	1.0000	1.0000
L56	69	CCI 6.5" x 1.25" Plate	16.75 - 17.00	1.0000	1.0000
L56	70	CCI 6.5" x 1.25" Plate	16.75 - 17.00	1.0000	1.0000
L56	187	HCS 6X12 4AWG(1-5/8)	16.75 - 17.00	1.0000	1.0000
L56	190	AL7-50(1-5/8)	16.75 - 17.00	1.0000	1.0000
L56	218	Safety Line 3/8	16.75 - 17.00	1.0000	1.0000
L56	219	Climbing Rung	16.75 - 17.00	1.0000	1.0000
L57	4	CCI 4" x 0.75" Plate	11.65 - 13.17	1.0000	1.0000
L57	32	CCI 6" x 1" Plate	11.65 - 16.75	1.0000	1.0000
L57	33	CCI 6" x 1" Plate	11.65 - 16.75	1.0000	1.0000
L57	34	CCI 6" x 1" Plate	11.65 - 16.75	1.0000	1.0000
L57	35	CCI 6" x 1" Plate	11.65 - 16.75	1.0000	1.0000
L57	65	CCI 6.5" x 1.25" Plate	12.67 - 16.75	1.0000	1.0000
L57	66	CCI 6.5" x 1.25" Plate	12.67 - 16.75	1.0000	1.0000
L57	67	CCI 6.5" x 1.25" Plate	12.67 - 16.75	1.0000	1.0000
L57	68	CCI 6.5" x 1.25" Plate	12.67 - 16.75	1.0000	1.0000
L57	69	CCI 6.5" x 1.25" Plate	12.67 - 16.75	1.0000	1.0000
L57	70	CCI 6.5" x 1.25" Plate	12.67 - 16.75	1.0000	1.0000
L57	187	HCS 6X12 4AWG(1-5/8)	11.65 - 16.75	1.0000	1.0000
L57	190	AL7-50(1-5/8)	11.65 - 16.75	1.0000	1.0000
L57	218	Safety Line 3/8	11.65 - 16.75	1.0000	1.0000
L57	219	Climbing Rung	11.65 - 16.75	1.0000	1.0000
L58	4	CCI 4" x 0.75" Plate	11.42 - 11.65	1.0000	1.0000
L58	32	CCI 6" x 1" Plate	11.42 - 11.65	1.0000	1.0000
L58	33	CCI 6" x 1" Plate	11.42 - 11.65	1.0000	1.0000
L58	34	CCI 6" x 1" Plate	11.42 - 11.65	1.0000	1.0000
L58	35	CCI 6" x 1" Plate	11.42 - 11.65	1.0000	1.0000
L58	187	HCS 6X12 4AWG(1-5/8)	11.42 - 11.65	1.0000	1.0000
L58	190	AL7-50(1-5/8)	11.42 - 11.65	1.0000	1.0000
L58	218	Safety Line 3/8	11.42 - 11.65	1.0000	1.0000

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
L58	219	Climbing Rung	11.42 - 11.65	1.0000	1.0000
L59	2	CCI 4" x 0.75" Plate	9.40 - 10.88	1.0000	1.0000
L59	3	CCI 4" x 0.75" Plate	9.40 - 10.88	1.0000	1.0000
L59	4	CCI 4" x 0.75" Plate	9.40 - 11.42	1.0000	1.0000
L59	32	CCI 6" x 1" Plate	9.40 - 11.42	1.0000	1.0000
L59	33	CCI 6" x 1" Plate	9.40 - 11.42	1.0000	1.0000
L59	34	CCI 6" x 1" Plate	9.40 - 11.42	1.0000	1.0000
L59	35	CCI 6" x 1" Plate	9.40 - 11.42	1.0000	1.0000
L59	187	HCS 6X12 4AWG(1-5/8)	9.40 - 11.42	1.0000	1.0000
L59	190	AL7-50(1-5/8)	9.40 - 11.42	1.0000	1.0000
L59	218	Safety Line 3/8	9.40 - 11.42	1.0000	1.0000
L59	219	Climbing Rung	9.40 - 11.42	1.0000	1.0000
L60	2	CCI 4" x 0.75" Plate	9.15 - 9.40	1.0000	1.0000
L60	3	CCI 4" x 0.75" Plate	9.15 - 9.40	1.0000	1.0000
L60	4	CCI 4" x 0.75" Plate	9.15 - 9.40	1.0000	1.0000
L60	32	CCI 6" x 1" Plate	9.15 - 9.40	1.0000	1.0000
L60	33	CCI 6" x 1" Plate	9.15 - 9.40	1.0000	1.0000
L60	34	CCI 6" x 1" Plate	9.15 - 9.40	1.0000	1.0000
L60	35	CCI 6" x 1" Plate	9.15 - 9.40	1.0000	1.0000
L60	187	HCS 6X12 4AWG(1-5/8)	9.15 - 9.40	1.0000	1.0000
L60	190	AL7-50(1-5/8)	9.15 - 9.40	1.0000	1.0000
L60	218	Safety Line 3/8	9.15 - 9.40	1.0000	1.0000
L60	219	Climbing Rung	9.15 - 9.40	1.0000	1.0000
L61	2	CCI 4" x 0.75" Plate	4.83 - 9.15	1.0000	1.0000
L61	3	CCI 4" x 0.75" Plate	4.83 - 9.15	1.0000	1.0000
L61	4	CCI 4" x 0.75" Plate	4.83 - 9.15	1.0000	1.0000
L61	32	CCI 6" x 1" Plate	4.83 - 9.15	1.0000	1.0000
L61	33	CCI 6" x 1" Plate	4.83 - 9.15	1.0000	1.0000
L61	34	CCI 6" x 1" Plate	4.83 - 9.15	1.0000	1.0000
L61	35	CCI 6" x 1" Plate	4.83 - 9.15	1.0000	1.0000
L61	187	HCS 6X12 4AWG(1-5/8)	4.83 - 9.15	1.0000	1.0000
L61	190	AL7-50(1-5/8)	4.83 - 9.15	1.0000	1.0000
L61	218	Safety Line 3/8	4.83 - 9.15	1.0000	1.0000
L61	219	Climbing Rung	4.83 - 9.15	1.0000	1.0000
L62	2	CCI 4" x 0.75" Plate	4.58 - 4.83	1.0000	1.0000
L62	3	CCI 4" x 0.75" Plate	4.58 - 4.83	1.0000	1.0000
L62	4	CCI 4" x 0.75" Plate	4.58 - 4.83	1.0000	1.0000
L62	32	CCI 6" x 1" Plate	4.58 - 4.83	1.0000	1.0000
L62	33	CCI 6" x 1" Plate	4.58 - 4.83	1.0000	1.0000
L62	34	CCI 6" x 1" Plate	4.58 - 4.83	1.0000	1.0000
L62	35	CCI 6" x 1" Plate	4.58 - 4.83	1.0000	1.0000
L62	187	HCS 6X12 4AWG(1-5/8)	4.58 - 4.83	1.0000	1.0000
L62	190	AL7-50(1-5/8)	4.58 - 4.83	1.0000	1.0000
L62	218	Safety Line 3/8	4.58 - 4.83	1.0000	1.0000
L62	219	Climbing Rung	4.58 - 4.83	1.0000	1.0000
L63	2	CCI 4" x 0.75" Plate	0.00 - 4.58	1.0000	1.0000
L63	3	CCI 4" x 0.75" Plate	0.00 - 4.58	1.0000	1.0000
L63	4	CCI 4" x 0.75" Plate	3.17 - 4.58	1.0000	1.0000
L63	32	CCI 6" x 1" Plate	0.00 - 4.58	1.0000	1.0000
L63	33	CCI 6" x 1" Plate	0.00 - 4.58	1.0000	1.0000
L63	34	CCI 6" x 1" Plate	0.00 - 4.58	1.0000	1.0000
L63	35	CCI 6" x 1" Plate	0.00 - 4.58	1.0000	1.0000
L63	187	HCS 6X12 4AWG(1-5/8)	0.00 - 4.58	1.0000	1.0000
L63	190	AL7-50(1-5/8)	0.00 - 4.58	1.0000	1.0000
L63	218	Safety Line 3/8	0.00 - 4.58	1.0000	1.0000
L63	219	Climbing Rung	0.00 - 4.58	1.0000	1.0000

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 37 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	CAAA Front	CAAA Side	Weight	
			Horz Lateral	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
Lightning Rod 5/8" x 4' on 4' Pole (E)	B	From Leg	1.000	0.000	0.000	191.667	No Ice	1.356	1.356	0.066
			0.000			1/2" Ice	2.131	2.131	0.087	
			4.000			1" Ice	2.702	2.702	0.112	
						2" Ice	3.773	3.773	0.175	
LW										
LW										
WB2623 w/ Mount Pipe (E)	B	From Leg	2.000	0.000	0.000	191.000	No Ice	1.929	0.866	0.020
			0.000			1/2" Ice	2.158	1.110	0.038	
			-1.000			1" Ice	2.399	1.369	0.058	
						2" Ice	2.915	1.938	0.111	
3' x 2" Pipe Mount (E-For Omni)	B	From Leg	2.000	0.000	0.000	191.000	No Ice	0.583	0.583	0.011
			0.000			1/2" Ice	0.770	0.770	0.017	
			-1.000			1" Ice	0.967	0.967	0.024	
						2" Ice	1.388	1.388	0.047	
Side Arm Mount [SO 701-1] (E)	B	From Leg	1.000	0.000	0.000	191.000	No Ice	0.850	1.670	0.065
			0.000			1/2" Ice	1.140	2.340	0.079	
			0.000			1" Ice	1.430	3.010	0.093	
						2" Ice	2.010	4.350	0.121	
LW										
OGB4-900D (E - Per Photo)	B	From Leg	4.000	0.000	0.000	184.000	No Ice	0.785	0.785	0.010
			0.000			1/2" Ice	1.028	1.028	0.016	
			4.000			1" Ice	1.281	1.281	0.025	
						2" Ice	1.814	1.814	0.053	
DB589-A (E - Per Photo)	B	From Leg	4.000	0.000	0.000	184.000	No Ice	2.763	2.763	0.012
			0.000			1/2" Ice	4.170	4.170	0.033	
			-5.000			1" Ice	5.593	5.593	0.063	
						2" Ice	8.490	8.490	0.150	
AIR -32 B2A/B66AA w/ Mount Pipe (E)	A	From Leg	4.000	0.000	0.000	184.000	No Ice	6.747	6.070	0.153
			0.000			1/2" Ice	7.202	6.867	0.214	
			-3.000			1" Ice	7.648	7.583	0.282	
						2" Ice	8.565	9.063	0.441	
AIR -32 B2A/B66AA w/ Mount Pipe (E)	B	From Leg	4.000	0.000	0.000	184.000	No Ice	6.747	6.070	0.153
			0.000			1/2" Ice	7.202	6.867	0.214	
			-3.000			1" Ice	7.648	7.583	0.282	
						2" Ice	8.565	9.063	0.441	
AIR -32 B2A/B66AA w/ Mount Pipe (E)	C	From Leg	4.000	0.000	0.000	184.000	No Ice	6.747	6.070	0.153
			0.000			1/2" Ice	7.202	6.867	0.214	
			-3.000			1" Ice	7.648	7.583	0.282	
						2" Ice	8.565	9.063	0.441	
APX16DWV-16DWVS-E-A 20 w/ Mount Pipe (E)	A	From Leg	4.000	0.000	0.000	184.000	No Ice	7.154	3.703	0.062
			0.000			1/2" Ice	7.600	4.495	0.113	
			-3.000			1" Ice	8.044	5.215	0.170	
						2" Ice	8.956	6.704	0.307	
APX16DWV-16DWVS-E-A 20 w/ Mount Pipe (E)	B	From Leg	4.000	0.000	0.000	184.000	No Ice	7.154	3.703	0.062
			0.000			1/2" Ice	7.600	4.495	0.113	
			-3.000			1" Ice	8.044	5.215	0.170	
						2" Ice	8.956	6.704	0.307	
APX16DWV-16DWVS-E-A 20 w/ Mount Pipe (E)	C	From Leg	4.000	0.000	0.000	184.000	No Ice	7.154	3.703	0.062
			0.000			1/2" Ice	7.600	4.495	0.113	
			-3.000			1" Ice	8.044	5.215	0.170	
						2" Ice	8.956	6.704	0.307	
KRY 112 144/1	A	From Leg	4.000	0.000	0.000	184.000	No Ice	0.350	0.175	0.011

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job		87581.023.01 - Newington_1, CT (BU# 826217)		Page		38 of 92	
	Project				Date		13:18:51 07/13/19	
	Client		Crown Castle		Designed by		Pavan Upadhy	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C _{AA}		Weight K
			Horz Lateral ft	Vert ft			Front ft ²	Side ft ²	
(E)			0.000			1/2" Ice	0.426	0.234	0.014
			-3.000			1" Ice	0.509	0.301	0.019
						2" Ice	0.698	0.456	0.032
KRY 112 144/1 (E)	B	From Leg	4.000	0.000	184.000	No Ice	0.350	0.175	0.011
			0.000			1/2" Ice	0.426	0.234	0.014
			-3.000			1" Ice	0.509	0.301	0.019
						2" Ice	0.698	0.456	0.032
KRY 112 144/1 (E)	C	From Leg	4.000	0.000	184.000	No Ice	0.350	0.175	0.011
			0.000			1/2" Ice	0.426	0.234	0.014
			-3.000			1" Ice	0.509	0.301	0.019
						2" Ice	0.698	0.456	0.032
KRY 112 489/2 (E)	A	From Leg	4.000	0.000	184.000	No Ice	0.559	0.365	0.015
			0.000			1/2" Ice	0.658	0.448	0.020
			-3.000			1" Ice	0.764	0.542	0.027
						2" Ice	0.998	0.752	0.046
KRY 112 489/2 (E)	B	From Leg	4.000	0.000	184.000	No Ice	0.559	0.365	0.015
			0.000			1/2" Ice	0.658	0.448	0.020
			-3.000			1" Ice	0.764	0.542	0.027
						2" Ice	0.998	0.752	0.046
KRY 112 489/2 (E)	C	From Leg	4.000	0.000	184.000	No Ice	0.559	0.365	0.015
			0.000			1/2" Ice	0.658	0.448	0.020
			-3.000			1" Ice	0.764	0.542	0.027
						2" Ice	0.998	0.752	0.046
ATBT-BOTTOM-24V (E)	A	From Leg	4.000	0.000	184.000	No Ice	0.104	0.065	0.003
			0.000			1/2" Ice	0.148	0.102	0.004
			-3.000			1" Ice	0.199	0.147	0.006
						2" Ice	0.323	0.259	0.013
ATBT-BOTTOM-24V (E)	B	From Leg	4.000	0.000	184.000	No Ice	0.104	0.065	0.003
			0.000			1/2" Ice	0.148	0.102	0.004
			-3.000			1" Ice	0.199	0.147	0.006
						2" Ice	0.323	0.259	0.013
ATBT-BOTTOM-24V (E)	C	From Leg	4.000	0.000	184.000	No Ice	0.104	0.065	0.003
			0.000			1/2" Ice	0.148	0.102	0.004
			-3.000			1" Ice	0.199	0.147	0.006
						2" Ice	0.323	0.259	0.013
APXVAARR24_43-U-NA20 w/ Mount Pipe (R)	A	From Leg	4.000	0.000	184.000	No Ice	14.690	6.870	0.186
			0.000			1/2" Ice	15.460	7.550	0.315
			-3.000			1" Ice	16.230	8.250	0.458
						2" Ice	17.820	9.670	0.788
APXVAARR24_43-U-NA20 w/ Mount Pipe (R)	B	From Leg	4.000	0.000	184.000	No Ice	14.690	6.870	0.186
			0.000			1/2" Ice	15.460	7.550	0.315
			-3.000			1" Ice	16.230	8.250	0.458
						2" Ice	17.820	9.670	0.788
APXVAARR24_43-U-NA20 w/ Mount Pipe (R)	C	From Leg	4.000	0.000	184.000	No Ice	14.690	6.870	0.186
			0.000			1/2" Ice	15.460	7.550	0.315
			-3.000			1" Ice	16.230	8.250	0.458
						2" Ice	17.820	9.670	0.788
RADIO 4449 B12/B71 (R)	A	From Leg	4.000	0.000	184.000	No Ice	1.650	1.300	0.075
			0.000			1/2" Ice	1.810	1.445	0.092
			-3.000			1" Ice	1.978	1.597	0.112
						2" Ice	2.336	1.924	0.161
RADIO 4449 B12/B71 (R)	B	From Leg	4.000	0.000	184.000	No Ice	1.650	1.300	0.075
			0.000			1/2" Ice	1.810	1.445	0.092
			-3.000			1" Ice	1.978	1.597	0.112
						2" Ice	2.336	1.924	0.161
RADIO 4449 B12/B71 (R)	C	From Leg	4.000	0.000	184.000	No Ice	1.650	1.300	0.075
			0.000			1/2" Ice	1.810	1.445	0.092

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 39 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
			-3.000			1" Ice 2" Ice	1.978 2.336	1.597 1.924	0.112 0.161
4' x 2" Pipe Mount (E-For Omni)	B	From Leg	4.000 0.000 0.000	0.000	184.000	No Ice 1/2" Ice 1" Ice 2" Ice	0.785 1.028 1.281 1.814	0.785 1.028 1.281 1.814	0.029 0.035 0.044 0.072
Platform Mount [LP 405-1] (E)	C	None		0.000	184.000	No Ice 1/2" Ice 1" Ice 2" Ice	20.800 28.100 35.400 50.000	20.800 28.100 35.400 50.000	1.800 2.066 2.332 2.864
LW									
(2) LNX-8513DS-A1M (E)	A	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	8.173 8.633 9.100 10.055	5.405 5.863 6.327 7.278	0.039 0.090 0.146 0.279
(2) LNX-6514DS-A1M (E)	B	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	8.173 8.633 9.100 10.055	5.405 5.863 6.327 7.278	0.039 0.089 0.146 0.278
(2) LNX-8513DS-A1M (E)	C	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	8.173 8.633 9.100 10.055	5.405 5.863 6.327 7.278	0.039 0.090 0.146 0.279
DB-T1-6Z-8AB-0Z (E)	A	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	4.800 5.070 5.348 5.926	2.000 2.193 2.393 2.815	0.044 0.080 0.120 0.213
(2) NNHH-65B-R4 (P)	A	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	7.620 8.120 8.630 9.680	3.010 3.450 3.900 4.820	0.077 0.150 0.228 0.407
(2) NNHH-65B-R4 (P)	B	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	7.620 8.120 8.630 9.680	3.010 3.450 3.900 4.820	0.077 0.150 0.228 0.407
(2) NNHH-65B-R4 (P)	C	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	7.620 8.120 8.630 9.680	3.010 3.450 3.900 4.820	0.077 0.150 0.228 0.407
RFV01U-D1A (P)	A	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	1.875 2.045 2.223 2.601	1.250 1.393 1.543 1.865	0.084 0.103 0.124 0.175
RFV01U-D1A (P)	B	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	1.875 2.045 2.223 2.601	1.250 1.393 1.543 1.865	0.084 0.103 0.124 0.175
RFV01U-D1A (P)	C	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	1.875 2.045 2.223 2.601	1.250 1.393 1.543 1.865	0.084 0.103 0.124 0.175
RFV01U-D2A (P)	A	From Leg	4.000 0.000 0.000	0.000	160.000	No Ice 1/2" Ice 1" Ice 2" Ice	1.875 2.045 2.223 2.601	1.013 1.145 1.284 1.585	0.070 0.087 0.106 0.153
RFV01U-D2A (P)	B	From Leg	4.000 0.000	0.000	160.000	No Ice 1/2" Ice	1.875 2.045	1.013 1.145	0.070 0.087

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 40 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft ²	ft ²	K
			0.000				1" Ice 2.223	1.284	0.106
							2" Ice 2.601	1.585	0.153
RFV01U-D2A (P)	C	From Leg	4.000		0.000	160.000	No Ice 1.875	1.013	0.070
			0.000				1/2" Ice 2.045	1.145	0.087
			0.000				1" Ice 2.223	1.284	0.106
							2" Ice 2.601	1.585	0.153
5' x 2" Pipe Mount (E-per MA)	A	From Leg	2.000		0.000	160.000	No Ice 1.000	1.000	0.029
			0.000				1/2" Ice 1.393	1.393	0.037
			0.000				1" Ice 1.703	1.703	0.048
							2" Ice 2.351	2.351	0.082
(4) 8' x 2.375" Mount Pipe (E-per MA)	A	From Leg	4.000		0.000	160.000	No Ice 1.900	1.900	0.061
			0.000				1/2" Ice 2.728	2.728	0.075
			0.000				1" Ice 3.401	3.401	0.095
							2" Ice 4.396	4.396	0.150
(4) 8' x 2.375" Mount Pipe (E-per MA)	B	From Leg	4.000		0.000	160.000	No Ice 1.900	1.900	0.061
			0.000				1/2" Ice 2.728	2.728	0.075
			0.000				1" Ice 3.401	3.401	0.095
							2" Ice 4.396	4.396	0.150
(4) 8' x 2.375" Mount Pipe (E-per MA)	C	From Leg	4.000		0.000	160.000	No Ice 1.900	1.900	0.061
			0.000				1/2" Ice 2.728	2.728	0.075
			0.000				1" Ice 3.401	3.401	0.095
							2" Ice 4.396	4.396	0.150
Platform Mount [LP 303-1] (E)	C	None			0.000	160.000	No Ice 14.660	14.660	1.250
							1/2" Ice 18.870	18.870	1.481
							1" Ice 23.080	23.080	1.713
							2" Ice 31.500	31.500	2.175
LW									
SRL-224NM-4 (E)	B	From Leg	6.000		0.000	158.000	No Ice 2.600	2.600	0.035
			0.000				1/2" Ice 4.680	4.680	0.045
			0.000				1" Ice 6.760	6.760	0.056
							2" Ice 10.920	10.920	0.077
DB205-A (E)	C	From Leg	6.000		0.000	158.000	No Ice 1.200	1.200	0.038
			0.000				1/2" Ice 2.160	2.160	0.049
			0.000				1" Ice 3.120	3.120	0.061
							2" Ice 5.040	5.040	0.084
4' x 2" Pipe Mount (E-For Omni)	B	From Leg	6.000		0.000	158.000	No Ice 0.785	0.785	0.029
			0.000				1/2" Ice 1.028	1.028	0.035
			0.000				1" Ice 1.281	1.281	0.044
							2" Ice 1.814	1.814	0.072
4' x 2" Pipe Mount (E-For Omni)	C	From Leg	6.000		0.000	158.000	No Ice 0.785	0.785	0.029
			0.000				1/2" Ice 1.028	1.028	0.035
			0.000				1" Ice 1.281	1.281	0.044
							2" Ice 1.814	1.814	0.072
Side Arm Mount [SO 702-1] (E)	B	From Leg	3.000		0.000	158.000	No Ice 1.000	1.430	0.027
			0.000				1/2" Ice 1.250	2.050	0.038
			0.000				1" Ice 1.500	2.670	0.049
							2" Ice 2.000	3.910	0.071
Side Arm Mount [SO 702-1] (E)	C	From Leg	3.000		0.000	158.000	No Ice 1.000	1.430	0.027
			0.000				1/2" Ice 1.250	2.050	0.038
			0.000				1" Ice 1.500	2.670	0.049
							2" Ice 2.000	3.910	0.071
LW									
7770.00 w/ Mount Pipe (E)	A	From Leg	4.000		0.000	151.000	No Ice 5.746	4.254	0.055
			0.000				1/2" Ice 6.179	5.014	0.103
			0.000				1" Ice 6.607	5.711	0.157
							2" Ice 7.488	7.155	0.287
7770.00 w/ Mount Pipe	B	From Leg	4.000		0.000	151.000	No Ice 5.746	4.254	0.055

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 41 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K
			Horz Lateral ft	Vert ft					
(E)			0.000			1/2" Ice	6.179	5.014	0.103
			0.000			1" Ice	6.607	5.711	0.157
			0.000			2" Ice	7.488	7.155	0.287
7770.00 w/ Mount Pipe (E)	C	From Leg	4.000	0.000	151.000	No Ice	5.746	4.254	0.055
			0.000			1/2" Ice	6.179	5.014	0.103
			0.000			1" Ice	6.607	5.711	0.157
			0.000			2" Ice	7.488	7.155	0.287
SBNH-1D6565C w/ Mount Pipe (E)	A	From Leg	4.000	0.000	151.000	No Ice	5.560	4.470	0.085
			0.000			1/2" Ice	6.070	4.970	0.167
			0.000			1" Ice	6.590	5.470	0.262
			0.000			2" Ice	7.650	6.520	0.495
SBNH-1D6565C w/ Mount Pipe (E)	B	From Leg	4.000	0.000	151.000	No Ice	5.560	4.470	0.085
			0.000			1/2" Ice	6.070	4.970	0.167
			0.000			1" Ice	6.590	5.470	0.262
			0.000			2" Ice	7.650	6.520	0.495
SBNH-1D6565C w/ Mount Pipe (E)	C	From Leg	4.000	0.000	151.000	No Ice	5.560	4.470	0.085
			0.000			1/2" Ice	6.070	4.970	0.167
			0.000			1" Ice	6.590	5.470	0.262
			0.000			2" Ice	7.650	6.520	0.495
DTMABP7819VG12A (E)	A	From Leg	4.000	0.000	151.000	No Ice	0.976	0.339	0.019
			0.000			1/2" Ice	1.100	0.419	0.026
			0.000			1" Ice	1.232	0.510	0.036
			0.000			2" Ice	1.517	0.714	0.060
DTMABP7819VG12A (E)	B	From Leg	4.000	0.000	151.000	No Ice	0.976	0.339	0.019
			0.000			1/2" Ice	1.100	0.419	0.026
			0.000			1" Ice	1.232	0.510	0.036
			0.000			2" Ice	1.517	0.714	0.060
DTMABP7819VG12A (E)	C	From Leg	4.000	0.000	151.000	No Ice	0.976	0.339	0.019
			0.000			1/2" Ice	1.100	0.419	0.026
			0.000			1" Ice	1.232	0.510	0.036
			0.000			2" Ice	1.517	0.714	0.060
DC6-48-60-18-8F (E)	A	From Leg	4.000	0.000	151.000	No Ice	1.212	1.212	0.033
			0.000			1/2" Ice	1.892	1.892	0.055
			0.000			1" Ice	2.105	2.105	0.080
			0.000			2" Ice	2.570	2.570	0.138
TPA-65R-LCUUUU-H8 (R)	A	From Leg	4.000	0.000	151.000	No Ice	11.870	7.020	0.082
			0.000			1/2" Ice	12.820	7.910	0.161
			0.000			1" Ice	13.770	8.820	0.248
			0.000			2" Ice	15.740	10.680	0.448
TPA-65R-LCUUUU-H8 (R)	B	From Leg	4.000	0.000	151.000	No Ice	11.870	7.020	0.082
			0.000			1/2" Ice	12.820	7.910	0.161
			0.000			1" Ice	13.770	8.820	0.248
			0.000			2" Ice	15.740	10.680	0.448
TPA-65R-LCUUUU-H8 (R)	C	From Leg	4.000	0.000	151.000	No Ice	11.870	7.020	0.082
			0.000			1/2" Ice	12.820	7.910	0.161
			0.000			1" Ice	13.770	8.820	0.248
			0.000			2" Ice	15.740	10.680	0.448
RRUS 32 (R)	A	From Leg	4.000	0.000	151.000	No Ice	2.857	1.777	0.055
			0.000			1/2" Ice	3.083	1.968	0.077
			0.000			1" Ice	3.316	2.166	0.103
			0.000			2" Ice	3.805	2.583	0.165
RRUS 32 (R)	B	From Leg	4.000	0.000	151.000	No Ice	2.857	1.777	0.055
			0.000			1/2" Ice	3.083	1.968	0.077
			0.000			1" Ice	3.316	2.166	0.103
			0.000			2" Ice	3.805	2.583	0.165
RRUS 32 (R)	C	From Leg	4.000	0.000	151.000	No Ice	2.857	1.777	0.055
			0.000			1/2" Ice	3.083	1.968	0.077

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	42 of 92
	Project		Date	13:18:51 07/13/19
	Client	Crown Castle		Designed by

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral					
			0.000						
RRUS 32 B2 (R)	A	From Leg	4.000	0.000	151.000	1" Ice	3.316	2.166	0.103
			0.000	0.000		2" Ice	3.805	2.583	0.165
			0.000	0.000		No Ice	2.731	1.668	0.053
			0.000	0.000		1/2" Ice	2.953	1.855	0.074
			0.000	0.000		1" Ice	3.182	2.049	0.098
RRUS 32 B2 (R)	B	From Leg	4.000	0.000	151.000	2" Ice	3.663	2.458	0.157
			0.000	0.000		No Ice	2.731	1.668	0.053
			0.000	0.000		1/2" Ice	2.953	1.855	0.074
			0.000	0.000		1" Ice	3.182	2.049	0.098
			0.000	0.000		2" Ice	3.663	2.458	0.157
RRUS 32 B2 (R)	C	From Leg	4.000	0.000	151.000	No Ice	2.731	1.668	0.053
			0.000	0.000		1/2" Ice	2.953	1.855	0.074
			0.000	0.000		1" Ice	3.182	2.049	0.098
			0.000	0.000		2" Ice	3.663	2.458	0.157
			0.000	0.000		No Ice	2.731	1.668	0.053
DBC0062F3V52-1 (R)	A	From Leg	4.000	0.000	151.000	1/2" Ice	2.953	1.855	0.074
			0.000	0.000		1" Ice	3.182	2.049	0.098
			0.000	0.000		2" Ice	3.663	2.458	0.157
			0.000	0.000		No Ice	0.711	0.220	0.013
			0.000	0.000		1/2" Ice	0.818	0.289	0.018
DBC0062F3V52-1 (R)	B	From Leg	4.000	0.000	151.000	1" Ice	0.932	0.366	0.025
			0.000	0.000		2" Ice	1.182	0.543	0.044
			0.000	0.000		No Ice	0.711	0.220	0.013
			0.000	0.000		1/2" Ice	0.818	0.289	0.018
			0.000	0.000		1" Ice	0.932	0.366	0.025
DBC0062F3V52-1 (R)	C	From Leg	4.000	0.000	151.000	2" Ice	1.182	0.543	0.044
			0.000	0.000		No Ice	0.711	0.220	0.013
			0.000	0.000		1/2" Ice	0.818	0.289	0.018
			0.000	0.000		1" Ice	0.932	0.366	0.025
			0.000	0.000		2" Ice	1.182	0.543	0.044
(3) 10' x 2.875" Pipe Mount (R - Mount Mod)	A	From Leg	4.000	0.000	151.000	No Ice	2.875	2.875	0.085
			0.000	0.000		1/2" Ice	3.907	3.907	0.106
			0.000	0.000		1" Ice	4.956	4.956	0.134
			0.000	0.000		2" Ice	6.188	6.188	0.209
			0.000	0.000		No Ice	2.875	2.875	0.085
(3) 10' x 2.875" Pipe Mount (R - Mount Mod)	B	From Leg	4.000	0.000	151.000	1/2" Ice	3.907	3.907	0.106
			0.000	0.000		1" Ice	4.956	4.956	0.134
			0.000	0.000		2" Ice	6.188	6.188	0.209
			0.000	0.000		No Ice	2.875	2.875	0.085
			0.000	0.000		1/2" Ice	3.907	3.907	0.106
(3) 10' x 2.875" Pipe Mount (R - Mount Mod)	C	From Leg	4.000	0.000	151.000	1" Ice	4.956	4.956	0.134
			0.000	0.000		2" Ice	6.188	6.188	0.209
			0.000	0.000		No Ice	2.875	2.875	0.085
			0.000	0.000		1/2" Ice	3.907	3.907	0.106
			0.000	0.000		1" Ice	4.956	4.956	0.134
Miscellaneous [NA 510-1] (R - Mount Mod)	C	None		0.000	151.000	2" Ice	6.188	6.188	0.209
				0.000		No Ice	6.000	6.000	0.256
				0.000		1/2" Ice	8.500	8.500	0.340
				0.000		1" Ice	11.000	11.000	0.423
				0.000		2" Ice	16.000	16.000	0.591
Miscellaneous [NA 509-3] (R-PRK-1245 - Mount Mod)	C	None		0.000	151.000	No Ice	11.840	11.840	0.275
				0.000		1/2" Ice	16.960	16.960	0.296
				0.000		1" Ice	22.080	22.080	0.317
				0.000		2" Ice	32.320	32.320	0.360
				0.000		No Ice	18.850	18.850	1.500
Platform Mount [LP 403-1] (E)	C	None		0.000	151.000	1/2" Ice	24.300	24.300	1.797
				0.000		1" Ice	29.750	29.750	2.093
				0.000		2" Ice	40.650	40.650	2.686
				0.000		No Ice	1.212	1.212	0.033
				0.000		1/2" Ice	1.892	1.892	0.055
LW DC6-48-60-18-8F (E)	C	From Leg	1.000	0.000	150.000	1" Ice	2.105	2.105	0.080
			0.000	0.000		2" Ice	2.570	2.570	0.138
			2.000	0.000		No Ice	2.784	1.187	0.048
			0.000	0.000		1/2" Ice	2.992	1.334	0.068
			0.000	0.000		No Ice	2.784	1.187	0.048

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 43 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral					
			ft	ft	°	ft	ft ²	ft ²	K
			0.000				1" Ice 3.207	1.490	0.092
							2" Ice 3.658	1.833	0.150
RRUS 11 (R)	B	From Leg	1.000	0.000	150.000		No Ice 2.784	1.187	0.048
			0.000				1/2" Ice 2.992	1.334	0.068
			0.000				1" Ice 3.207	1.490	0.092
							2" Ice 3.658	1.833	0.150
RRUS 11 (R)	C	From Leg	1.000	0.000	150.000		No Ice 2.784	1.187	0.048
			0.000				1/2" Ice 2.992	1.334	0.068
			0.000				1" Ice 3.207	1.490	0.092
							2" Ice 3.658	1.833	0.150
RRUS 12 (R)	A	From Leg	1.000	0.000	150.000		No Ice 3.145	1.285	0.058
			0.000				1/2" Ice 3.365	1.438	0.081
			2.000				1" Ice 3.592	1.600	0.108
							2" Ice 4.069	1.954	0.171
RRUS 12 (R)	B	From Leg	1.000	0.000	150.000		No Ice 3.145	1.285	0.058
			0.000				1/2" Ice 3.365	1.438	0.081
			2.000				1" Ice 3.592	1.600	0.108
							2" Ice 4.069	1.954	0.171
RRUS 12 (R)	C	From Leg	1.000	0.000	150.000		No Ice 3.145	1.285	0.058
			0.000				1/2" Ice 3.365	1.438	0.081
			2.000				1" Ice 3.592	1.600	0.108
							2" Ice 4.069	1.954	0.171
Side Arm Mount [SO 102-3] (E)	C	None		0.000	150.000		No Ice 3.000	3.000	0.081
							1/2" Ice 3.480	3.480	0.111
							1" Ice 3.960	3.960	0.141
							2" Ice 4.920	4.920	0.201
Pipe Mount [PM 601-3] (E)	C	None		0.000	150.000		No Ice 4.390	4.390	0.195
							1/2" Ice 5.480	5.480	0.237
							1" Ice 6.570	6.570	0.280
							2" Ice 8.750	8.750	0.365
LW									
SRL-235-2 (E)	B	From Leg	6.000	0.000	132.000		No Ice 7.000	7.000	0.076
			0.000				1/2" Ice 9.037	9.037	0.125
			0.000				1" Ice 11.092	11.092	0.187
							2" Ice 15.250	15.250	0.351
4' x 2" Pipe Mount (E-For Omni)	B	From Leg	6.000	0.000	132.000		No Ice 0.785	0.785	0.029
			0.000				1/2" Ice 1.028	1.028	0.035
			0.000				1" Ice 1.281	1.281	0.044
							2" Ice 1.814	1.814	0.072
Side Arm Mount [SO 702-1] (E)	B	From Leg	3.000	0.000	132.000		No Ice 1.000	1.430	0.027
			0.000				1/2" Ice 1.250	2.050	0.038
			0.000				1" Ice 1.500	2.670	0.049
							2" Ice 2.000	3.910	0.071
Side Arm Mount [SO 104-3] (E-Mount Attachment)	C	None		0.000	132.000		No Ice 3.300	3.300	0.287
							1/2" Ice 4.130	4.130	0.317
							1" Ice 4.960	4.960	0.347
							2" Ice 6.620	6.620	0.407
LW									
PCS 1900 TMA RX (E)	A	From Leg	2.000	0.000	124.000		No Ice 0.539	0.529	0.018
			0.000				1/2" Ice 0.638	0.628	0.023
			0.000				1" Ice 0.745	0.734	0.031
							2" Ice 0.981	0.969	0.052
2' x 2" Pipe Mount (E-For TMA)	A	From Leg	2.000	0.000	124.000		No Ice 0.023	0.023	0.007
			0.000				1/2" Ice 0.049	0.049	0.008
			0.000				1" Ice 0.085	0.085	0.009
							2" Ice 0.186	0.186	0.013
Side Arm Mount [SO 104-3]	C	None		0.000	124.000		No Ice 3.300	3.300	0.287

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 44 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
(E)									
						1/2" Ice	4.130	4.130	0.317
						1" Ice	4.960	4.960	0.347
						2" Ice	6.620	6.620	0.407
LW									
* Sprint*									
* Clear Wire*									
(2) 6' x 2" Mount Pipe (E - Per Photo)	A	From Leg	4.000	0.000	116.000	No Ice	1.425	1.425	0.022
			0.000			1/2" Ice	1.925	1.925	0.033
			0.000			1" Ice	2.294	2.294	0.048
						2" Ice	3.060	3.060	0.090
6' x 2" Mount Pipe (E - Per Photo)	B	From Leg	4.000	0.000	116.000	No Ice	1.425	1.425	0.022
			0.000			1/2" Ice	1.925	1.925	0.033
			0.000			1" Ice	2.294	2.294	0.048
						2" Ice	3.060	3.060	0.090
8' x 2.375" Mount Pipe (E - Per Photo(Dia))	B	From Leg	4.000	0.000	116.000	No Ice	1.900	1.900	0.061
			0.000			1/2" Ice	2.728	2.728	0.075
			0.000			1" Ice	3.401	3.401	0.095
						2" Ice	4.396	4.396	0.150
(2) 6' x 2" Mount Pipe (E - Per Photo)	C	From Leg	4.000	0.000	116.000	No Ice	1.425	1.425	0.022
			0.000			1/2" Ice	1.925	1.925	0.033
			0.000			1" Ice	2.294	2.294	0.048
						2" Ice	3.060	3.060	0.090
HORIZON DUO (E - V. Offset Per APP)	A	From Leg	4.000	0.000	116.000	No Ice	0.469	0.294	0.007
			0.000			1/2" Ice	0.556	0.365	0.012
			0.000			1" Ice	0.650	0.444	0.018
						2" Ice	0.861	0.624	0.036
NNVV-65B-R4 w/ Mount Pipe (R)	A	From Leg	4.000	0.000	116.000	No Ice	12.509	7.413	0.103
			0.000			1/2" Ice	13.108	8.598	0.194
			2.000			1" Ice	13.672	9.496	0.293
						2" Ice	14.822	11.328	0.520
NNVV-65B-R4 w/ Mount Pipe (R)	B	From Leg	4.000	0.000	116.000	No Ice	12.509	7.413	0.103
			0.000			1/2" Ice	13.108	8.598	0.194
			2.000			1" Ice	13.672	9.496	0.293
						2" Ice	14.822	11.328	0.520
NNVV-65B-R4 w/ Mount Pipe (R)	C	From Leg	4.000	0.000	116.000	No Ice	12.509	7.413	0.103
			0.000			1/2" Ice	13.108	8.598	0.194
			2.000			1" Ice	13.672	9.496	0.293
						2" Ice	14.822	11.328	0.520
AAHC w/ Mount Pipe (R)	A	From Leg	4.000	0.000	116.000	No Ice	4.409	2.691	0.115
			0.000			1/2" Ice	4.727	3.079	0.156
			2.000			1" Ice	5.055	3.486	0.202
						2" Ice	5.743	4.359	0.310
AAHC w/ Mount Pipe (R)	B	From Leg	4.000	0.000	116.000	No Ice	4.409	2.691	0.115
			0.000			1/2" Ice	4.727	3.079	0.156
			2.000			1" Ice	5.055	3.486	0.202
						2" Ice	5.743	4.359	0.310
AAHC w/ Mount Pipe (R)	C	From Leg	4.000	0.000	116.000	No Ice	4.409	2.691	0.115
			0.000			1/2" Ice	4.727	3.079	0.156
			2.000			1" Ice	5.055	3.486	0.202
						2" Ice	5.743	4.359	0.310
800MHZ 2X50W RRH (R)	A	From Leg	4.000	0.000	116.000	No Ice	2.134	1.773	0.053
			0.000			1/2" Ice	2.320	1.946	0.074
			2.000			1" Ice	2.512	2.127	0.098
						2" Ice	2.920	2.510	0.157
(2) 800MHZ 2X50W RRH (R)	B	From Leg	4.000	0.000	116.000	No Ice	2.134	1.773	0.053
			0.000			1/2" Ice	2.320	1.946	0.074
			2.000			1" Ice	2.512	2.127	0.098

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 45 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight K	
			Horz Lateral ft	Vert ft						
(3) 800MHZ 2X50W RRH (R)	C	From Leg	4.000	0.000	0.000	116.000	2" Ice	2.920	2.510	0.157
							No Ice	2.134	1.773	0.053
							1/2" Ice	2.320	1.946	0.074
							1" Ice	2.512	2.127	0.098
(2) PCS 1900MHZ 4X45W-65MHZ (R)	A	From Leg	4.000	0.000	0.000	116.000	2" Ice	2.920	2.510	0.157
							No Ice	2.322	2.238	0.060
							1/2" Ice	2.527	2.441	0.083
							1" Ice	2.739	2.651	0.110
PCS 1900MHZ 4X45W-65MHZ (R)	B	From Leg	4.000	0.000	0.000	116.000	2" Ice	3.185	3.093	0.173
							No Ice	2.322	2.238	0.060
							1/2" Ice	2.527	2.441	0.083
							1" Ice	2.739	2.651	0.110
Miscellaneous [NA 509-3] (R - Site Pro1 - PRK-HD)	C	None	0.000	0.000	0.000	114.000	2" Ice	3.185	3.093	0.173
							No Ice	11.840	11.840	0.275
							1/2" Ice	16.960	16.960	0.296
							1" Ice	22.080	22.080	0.317
Platform Mount [LP 405-1] (E)	C	None	0.000	0.000	0.000	116.000	2" Ice	32.320	32.320	0.360
							No Ice	20.800	20.800	1.800
							1/2" Ice	28.100	28.100	2.066
							1" Ice	35.400	35.400	2.332
LW DB205-A (E-Per Photo)	B	From Leg	6.000	0.000	0.000	90.000	2" Ice	50.000	50.000	2.864
							No Ice	1.200	1.200	0.038
							1/2" Ice	2.160	2.160	0.049
							1" Ice	3.120	3.120	0.061
MT-485002 w/ Mount Pipe (E)	C	From Leg	6.000	0.000	0.000	90.000	2" Ice	5.040	5.040	0.084
							No Ice	1.372	0.473	0.011
							1/2" Ice	1.574	0.681	0.022
							1" Ice	1.788	0.902	0.037
5' x 2" Pipe Mount (E-For Omni)	B	From Leg	6.000	0.000	0.000	90.000	2" Ice	2.253	1.391	0.075
							No Ice	1.000	1.000	0.029
							1/2" Ice	1.393	1.393	0.037
							1" Ice	1.703	1.703	0.048
Side Arm Mount [SO 104-3] (E-per photo)	C	None	0.000	0.000	0.000	90.000	2" Ice	2.351	2.351	0.082
							No Ice	3.300	3.300	0.287
							1/2" Ice	4.130	4.130	0.317
							1" Ice	4.960	4.960	0.347
Side Arm Mount [SO 702-1] (E)	B	From Leg	3.000	0.000	0.000	90.000	2" Ice	6.620	6.620	0.407
							No Ice	1.000	1.430	0.027
							1/2" Ice	1.250	2.050	0.038
							1" Ice	1.500	2.670	0.049
Side Arm Mount [SO 702-1] (E)	C	From Leg	3.000	0.000	0.000	90.000	2" Ice	2.000	3.910	0.071
							No Ice	1.000	1.430	0.027
							1/2" Ice	1.250	2.050	0.038
							1" Ice	1.500	2.670	0.049
LW SRL-235-2 (E)	C	From Leg	3.000	0.000	0.000	70.000	2" Ice	2.000	3.910	0.071
							No Ice	7.000	7.000	0.076
							1/2" Ice	9.037	9.037	0.125
							1" Ice	11.092	11.092	0.187
2" x 2' Omni (E-Per Photo)	C	From Leg	3.000	0.000	0.000	70.000	2" Ice	15.250	15.250	0.351
							No Ice	0.304	0.304	0.005
							1/2" Ice	0.432	0.432	0.008
							1" Ice	0.578	0.578	0.013
6' x 2" Mount Pipe (E-For Omni)	C	From Leg	3.000	0.000	0.000	70.000	2" Ice	0.933	0.933	0.028
							No Ice	1.425	1.425	0.022
							1/2" Ice	1.925	1.925	0.033

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 47 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft ²	Weight K	
VHLP2-18 (E)	B	Paraboloid w/o Radome	From Leg	4.000 0.000 4.000	0.000		116.000	2.175	No Ice 1/2" Ice 1" Ice 2" Ice	3.715 4.006 4.296 4.876	0.031 0.052 0.072 0.113
LW KP2F-34 (E)	B	Grid	From Leg	6.000 0.000 0.000	5.000		90.000	2.000	No Ice 1/2" Ice 1" Ice 2" Ice	3.140 3.410 3.680 4.276	0.005 0.023 0.040 0.075
LW											

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 48 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Comb. No.	Description
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	191.667 - 186.667	Pole	Max Tension	48	0.000	-0.000	0.000
			Max. Compression	26	-1.286	-0.896	-0.610
			Max. Mx	8	-0.641	-2.139	-0.215
			Max. My	14	-0.641	-0.301	-2.043
			Max. Vy	20	-0.476	1.487	-0.215
			Max. Vx	2	-0.470	-0.301	1.585
			Max. Torque	4			-0.440
L2	186.667 - 181.567	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-11.614	-2.135	-1.449
			Max. Mx	8	-5.052	-7.120	-0.414
			Max. My	14	-5.050	-0.530	-6.951
			Max. Vy	20	-5.005	5.959	-0.362
			Max. Vx	2	-5.001	-0.476	6.087
			Max. Torque	5			-1.397
L3	181.567 - 176.567	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-13.091	-2.108	-1.041
			Max. Mx	8	-5.773	-32.965	-0.443
			Max. My	14	-5.767	-0.554	-32.851
			Max. Vy	20	-5.353	31.842	-0.337
			Max. Vx	2	-5.392	-0.444	32.006
			Max. Torque	5			-1.397
L4	176.567 - 171.567	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-14.227	-2.084	-1.144
			Max. Mx	8	-6.461	-60.502	-0.524
			Max. My	14	-6.455	-0.578	-60.653
			Max. Vy	20	-5.673	59.419	-0.364
			Max. Vx	2	-5.712	-0.411	59.718
			Max. Torque	5			-1.382
L5	171.567 - 166.567	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-15.361	-2.059	-1.247
			Max. Mx	8	-7.152	-89.619	-0.605
			Max. My	14	-7.146	-0.602	-90.037
			Max. Vy	20	-5.986	88.578	-0.390

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	49 of 92
	Project		Date	13:18:51 07/13/19
	Client	Crown Castle	Designed by	Pavan Upadhya

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L6	166.567 - 161.567	Pole	Max. Vx	2	-6.026	-0.377	89.014
			Max. Torque	5			-1.381
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-16.494	-2.036	-1.350
			Max. Mx	8	-7.846	-120.286	-0.686
			Max. My	14	-7.839	-0.626	-120.972
			Max. Vy	20	-6.294	119.289	-0.416
L7	161.567 - 156.567	Pole	Max. Vx	2	-6.333	-0.343	119.862
			Max. Torque	5			-1.381
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-28.205	-2.087	-1.482
			Max. Mx	8	-12.319	-169.224	-1.035
			Max. My	14	-12.302	-0.623	-170.868
			Max. Vy	20	-11.682	168.294	-0.708
L8	156.567 - 151.567	Pole	Max. Vx	2	-11.841	-0.277	169.069
			Max. Torque	5			-2.017
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-29.508	-2.240	-1.499
			Max. Mx	8	-13.061	-228.299	-1.111
			Max. My	14	-13.045	-0.674	-230.788
			Max. Vy	20	-11.962	227.385	-0.724
L9	151.567 - 146.567	Pole	Max. Vx	2	-12.121	-0.264	228.931
			Max. Torque	5			-2.017
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-43.969	-2.159	-0.945
			Max. Mx	8	-18.956	-316.362	-1.043
			Max. My	14	-18.937	-0.668	-319.619
			Max. Vy	20	-18.534	315.615	-0.594
L10	146.567 - 141.567	Pole	Max. Vx	2	-18.695	-0.187	318.026
			Max. Torque	5			-2.016
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-45.335	-2.326	-0.965
			Max. Mx	8	-19.823	-409.504	-1.121
			Max. My	14	-19.806	-0.724	-413.619
			Max. Vy	20	-18.752	408.791	-0.610
L11	141.567 - 141.417	Pole	Max. Vx	2	-18.912	-0.172	411.977
			Max. Torque	5			-1.870
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-45.376	-2.332	-0.966
			Max. Mx	8	-19.858	-412.314	-1.124
			Max. My	14	-19.840	-0.727	-416.455
			Max. Vy	20	-18.751	411.602	-0.610
L12	141.417 - 136.417	Pole	Max. Vx	2	-18.911	-0.172	414.811
			Max. Torque	5			-1.869
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-47.504	-2.543	-0.324
			Max. Mx	8	-20.989	-507.071	-1.148
			Max. My	14	-20.970	-0.786	-512.074
			Max. Vy	20	-19.182	506.391	-0.572
L13	136.417 - 131.417	Pole	Max. Vx	2	-19.382	-0.159	510.495
			Max. Torque	5			-1.869
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-50.268	-5.870	-2.143

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 50 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L14	131.417 - 126.417	Pole	Max. Mx	8	-22.571	-605.162	-1.715
			Max. My	14	-22.552	-1.666	-610.844
			Max. Vy	20	-20.116	602.631	-1.083
			Max. Vx	2	-20.325	-0.975	608.097
			Max. Torque	5			-4.567
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-52.133	-6.085	-2.167
			Max. Mx	8	-23.731	-706.620	-1.770
			Max. My	14	-23.713	-1.687	-713.419
			Max. Vy	20	-20.494	704.122	-1.153
L15	126.417 - 121.417	Pole	Max. Vx	2	-20.703	-1.000	710.593
			Max. Torque	5			-4.567
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-55.427	-6.365	-1.989
			Max. Mx	8	-25.957	-810.498	-1.753
			Max. My	14	-25.921	-1.757	-819.250
			Max. Vy	20	-21.446	808.897	-1.150
			Max. Vx	14	21.649	-1.757	-819.250
			Max. Torque	5			-4.566
			Max Tension	1	0.000	0.000	0.000
L16	121.417 - 121.167	Pole	Max. Compression	26	-55.540	-6.379	-1.992
			Max. Mx	8	-26.032	-815.761	-1.757
			Max. My	14	-25.996	-1.760	-824.668
			Max. Vy	20	-21.479	814.260	-1.154
			Max. Vx	14	21.681	-1.760	-824.668
			Max. Torque	5			-4.526
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-57.971	-7.212	-2.362
			Max. Mx	20	-27.465	923.309	-0.874
			Max. My	14	-27.464	-2.055	-934.701
L17	121.167 - 116.167	Pole	Max. Vy	20	-22.124	923.309	-0.874
			Max. Vx	14	22.218	-2.055	-934.701
			Max. Torque	5			-4.873
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-68.406	-7.828	-2.224
			Max. Mx	20	-32.769	1055.638	-0.378
			Max. My	14	-32.770	-2.443	-1067.785
			Max. Vy	20	-26.279	1055.638	-0.378
			Max. Vx	14	26.363	-2.443	-1067.785
			Max. Torque	5			-4.935
L18	116.167 - 111.167	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-68.924	-7.781	-2.233
			Max. Mx	20	-33.080	1085.240	-0.260
			Max. My	14	-33.082	-2.471	-1097.498
			Max. Vy	20	-26.369	1085.240	-0.260
			Max. Vx	14	26.453	-2.471	-1097.498
			Max. Torque	5			-4.934
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-69.053	-7.776	-2.237
			Max. Mx	20	-33.169	1091.832	-0.235
L19	111.167 - 110.042	Pole	Max. My	14	-33.170	-2.478	-1104.114
			Max. Vy	20	-26.385	1091.832	-0.235
			Max. Vx	14	26.468	-2.478	-1104.114
			Max. Torque	5			-4.934
			Max. Compression	26	-69.053	-7.776	-2.237
			Max. Mx	20	-33.169	1091.832	-0.235
			Max. My	14	-33.170	-2.478	-1104.114
			Max. Vy	20	-26.385	1091.832	-0.235
			Max. Vx	14	26.468	-2.478	-1104.114
			Max. Torque	5			-4.934
L20	110.042 - 109.792	Pole	Max. Torque	5			-4.934
			Max. Compression	26	-69.053	-7.776	-2.237
			Max. Mx	20	-33.169	1091.832	-0.235
			Max. My	14	-33.170	-2.478	-1104.114
			Max. Vy	20	-26.385	1091.832	-0.235
			Max. Vx	14	26.468	-2.478	-1104.114
			Max. Torque	5			-4.934
			Max. Compression	26	-69.053	-7.776	-2.237
			Max. Mx	20	-33.169	1091.832	-0.235
			Max. My	14	-33.170	-2.478	-1104.114

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L21	109.792 - 105.083	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-71.736	-7.571	-2.282
			Max. Mx	20	-34.835	1216.977	0.254
			Max. My	14	-34.837	-2.591	-1229.731
			Max. Vy	8	26.855	-1213.389	-2.136
			Max. Vx	2	-27.110	1.346	1221.619
			Max. Torque	5			-4.934
L22	105.083 - 104.833	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-71.907	-7.565	-2.287
			Max. Mx	20	-34.945	1223.675	0.278
			Max. My	14	-34.948	-2.598	-1236.455
			Max. Vy	8	26.896	-1220.106	-2.142
			Max. Vx	2	-27.153	1.394	1228.397
			Max. Torque	5			-4.934
L23	104.833 - 100.917	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-75.478	-7.425	-2.360
			Max. Mx	20	-37.372	1330.128	0.654
			Max. My	14	-37.376	-2.674	-1343.284
			Max. Vy	8	27.659	-1326.890	-2.238
			Max. Vx	2	-27.933	2.174	1336.148
			Max. Torque	5			-4.933
L24	100.917 - 100.667	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-75.641	-7.442	-2.364
			Max. Mx	20	-37.481	1337.020	0.679
			Max. My	14	-37.485	-2.680	-1350.198
			Max. Vy	8	27.702	-1333.808	-2.244
			Max. Vx	2	-27.976	2.222	1343.131
			Max. Torque	5			-4.933
L25	100.667 - 95.833	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-79.367	-7.663	-2.398
			Max. Mx	20	-39.316	1472.775	1.171
			Max. My	14	-39.336	-2.794	-1485.272
			Max. Vy	20	-28.598	1472.775	1.171
			Max. Vx	2	-28.523	3.163	1479.555
			Max. Torque	5			-4.933
L26	95.833 - 95.583	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-79.506	-7.681	-2.401
			Max. Mx	20	-39.412	1479.924	1.196
			Max. My	14	-39.432	-2.802	-1492.329
			Max. Vy	20	-28.614	1479.924	1.196
			Max. Vx	2	-28.540	3.211	1486.683
			Max. Torque	5			-4.932
L27	95.583 - 90.583	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-82.313	-7.917	-2.420
			Max. Mx	20	-41.192	1625.223	1.714
			Max. My	14	-41.227	-2.924	-1634.621
			Max. Vy	20	-29.522	1625.223	1.714
			Max. Vx	2	-29.443	4.180	1631.543
			Max. Torque	5			-4.932
L28	90.583 - 89.917	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-83.631	-9.133	-4.060
			Max. Mx	20	-41.928	1644.867	1.251
			Max. My	14	-41.963	-3.423	-1654.774

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	52 of 92
	Project		Date	13:18:51 07/13/19
	Client	Crown Castle	Designed by	Pavan Upadhya

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L29	89.917 - 89.667	Pole	Max. Vy	20	-30.056	1644.867	1.251
			Max. Vx	2	-29.960	3.826	1651.071
			Max. Torque	17			5.939
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-83.805	-9.149	-4.063
			Max. Mx	20	-42.042	1652.386	1.274
			Max. My	14	-42.077	-3.428	-1662.079
			Max. Vy	20	-30.103	1652.386	1.274
			Max. Vx	2	-30.006	3.874	1658.562
			Max. Torque	17			5.939
L30	89.667 - 84.667	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-88.088	-9.207	-4.021
			Max. Mx	20	-44.875	1805.494	1.793
			Max. My	2	-44.878	4.947	1810.979
			Max. Vy	20	-31.104	1805.494	1.793
			Max. Vx	2	-30.981	4.947	1810.979
			Max. Torque	17			5.939
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-92.464	-9.131	-3.947
			Max. Mx	20	-48.053	1926.429	2.231
L31	84.667 - 80.833	Pole	Max. My	2	-48.056	5.887	1931.225
			Max. Vy	20	-31.892	1926.429	2.231
			Max. Vx	2	-31.752	5.887	1931.225
			Max. Torque	17			5.938
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-92.975	-9.130	-3.941
			Max. Mx	20	-48.436	1942.419	2.286
			Max. My	2	-48.439	6.006	1947.122
			Max. Vy	20	-31.990	1942.419	2.286
			Max. Vx	2	-31.849	6.006	1947.122
L32	80.833 - 80.333	Pole	Max. Torque	17			5.938
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-93.183	-9.140	-3.941
			Max. Mx	20	-48.577	1950.425	2.310
			Max. My	2	-48.579	6.057	1955.087
			Max. Vy	20	-32.043	1950.425	2.310
			Max. Vx	2	-31.902	6.057	1955.087
			Max. Torque	17			5.938
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-96.972	-9.273	-3.938
L33	80.333 - 80.083	Pole	Max. Mx	20	-51.052	2113.203	2.800
			Max. My	2	-51.055	7.068	2117.056
			Max. Vy	20	-33.060	2113.203	2.800
			Max. Vx	2	-32.919	7.068	2117.056
			Max. Torque	17			5.938
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-101.350	-9.686	-3.966
			Max. Mx	20	-53.953	2280.939	3.266
			Max. My	2	-53.956	7.882	2284.157
			Max. Vy	20	-34.110	2280.939	3.266
L34	80.083 - 75.083	Pole	Max. Vx	2	-33.969	7.882	2284.157
			Max. Torque	17			5.937
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-102.746	-7.267	-5.398

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	53 of 92
	Project		Date	13:18:51 07/13/19
	Client	Crown Castle	Designed by	Pavan Upadhyia

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L37	69.5 - 69.25	Pole	Max. Mx	20	-54.633	2301.813	2.879
			Max. My	2	-54.635	8.752	2303.687
			Max. Vy	20	-34.695	2301.813	2.879
			Max. Vx	2	-34.568	8.752	2303.687
			Max. Torque	17			5.937
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-103.025	-7.297	-5.401
			Max. Mx	20	-54.821	2310.482	2.905
			Max. My	2	-54.823	8.792	2312.331
			Max. Vy	20	-34.751	2310.482	2.905
L38	69.25 - 64.25	Pole	Max. Vx	2	-34.625	8.792	2312.331
			Max. Torque	7			-5.460
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-111.431	-8.289	-5.401
			Max. Mx	20	-61.187	2486.549	3.440
			Max. My	2	-61.188	9.167	2488.343
			Max. Vy	20	-35.947	2486.549	3.440
			Max. Vx	2	-35.821	9.167	2488.343
			Max. Torque	7			-5.460
			Max Tension	1	0.000	0.000	0.000
L39	64.25 - 60.583	Pole	Max. Compression	26	-118.237	-9.100	-5.355
			Max. Mx	20	-66.364	2619.405	3.866
			Max. My	2	-66.361	9.402	2621.644
			Max. Vy	20	-36.816	2619.405	3.866
			Max. Vx	2	-36.916	9.402	2621.644
			Max. Torque	7			-5.460
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-118.521	-9.132	-5.356
			Max. Mx	20	-66.570	2628.602	3.893
			Max. My	2	-66.567	9.443	2630.874
L40	60.583 - 60.333	Pole	Max. Vy	20	-36.864	2628.602	3.893
			Max. Vx	2	-36.964	9.443	2630.874
			Max. Torque	7			-5.460
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-124.059	-9.630	-5.334
			Max. Mx	20	-70.353	2815.482	4.430
			Max. My	2	-70.349	10.243	2818.405
			Max. Vy	20	-37.993	2815.482	4.430
			Max. Vx	2	-38.093	10.243	2818.405
			Max. Torque	7			-5.460
L41	60.333 - 55.333	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-124.059	-9.630	-5.334
			Max. Mx	20	-70.353	2815.482	4.430
			Max. My	2	-70.349	10.243	2818.405
			Max. Vy	20	-37.993	2815.482	4.430
			Max. Vx	2	-38.093	10.243	2818.405
			Max. Torque	7			-5.460
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-126.248	-9.767	-5.335
			Max. Mx	20	-71.845	2936.635	4.761
L42	55.333 - 52.167	Pole	Max. My	2	-71.842	10.876	2939.835
			Max. Vy	20	-38.573	2936.635	4.761
			Max. Vx	2	-38.673	10.876	2939.835
			Max. Torque	7			-5.459
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-126.442	-9.784	-5.338
			Max. Mx	20	-71.990	2946.280	4.787
			Max. My	2	-71.987	10.926	2949.502
			Max. Vy	20	-38.613	2946.280	4.787
			Max. Vx	2	-38.713	10.926	2949.502
L43	52.167 - 51.917	Pole	Max. Torque	7			-5.459
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-126.442	-9.784	-5.338
			Max. Mx	20	-71.990	2946.280	4.787
			Max. My	2	-71.987	10.926	2949.502
			Max. Vy	20	-38.613	2946.280	4.787
			Max. Vx	2	-38.713	10.926	2949.502
			Max. Torque	7			-5.459
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-131.017	-10.154	-5.308
L44	51.917 - 46.917	Pole	Max. Compression	26	-131.017	-10.154	-5.308
			Max. Mx	20	-71.990	2946.280	4.787

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L45	46.917 - 41.917	Pole	Max. Mx	20	-75.089	3141.689	5.393
			Max. My	2	-75.086	11.863	3145.470
			Max. Vy	20	-39.600	3141.689	5.393
			Max. Vx	2	-39.691	11.863	3145.470
			Max. Torque	7			-5.459
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-136.954	-10.579	-4.774
			Max. Mx	20	-79.059	3342.231	6.378
			Max. My	2	-79.057	12.784	3346.851
			Max. Vy	20	-40.678	3342.231	6.378
L46	41.917 - 40.333	Pole	Max. Vx	2	-40.732	12.784	3346.851
			Max. Torque	7			-5.459
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-138.789	-10.703	-4.605
			Max. Mx	20	-80.307	3406.873	6.691
			Max. My	2	-80.305	13.081	3411.715
			Max. Vy	20	-41.007	3406.873	6.691
			Max. Vx	2	-41.050	13.081	3411.715
			Max. Torque	7			-5.458
			Max Tension	1	0.000	0.000	0.000
L47	40.333 - 40.083	Pole	Max. Compression	26	-139.050	-10.720	-4.580
			Max. Mx	20	-80.499	3417.126	6.740
			Max. My	2	-80.498	13.132	3421.998
			Max. Vy	20	-41.041	3417.126	6.740
			Max. Vx	2	-41.082	13.132	3421.998
			Max. Torque	7			-5.458
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-144.326	-10.927	-3.982
			Max. Mx	20	-84.170	3624.591	7.730
			Max. My	2	-84.169	14.156	3630.038
L48	40.083 - 35.083	Pole	Max. Vy	20	-41.963	3624.591	7.730
			Max. Vx	2	-42.000	14.156	3630.038
			Max. Torque	7			-5.458
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-149.145	-12.474	-4.458
			Max. Mx	20	-87.498	3836.454	8.220
			Max. My	2	-87.496	14.756	3842.443
			Max. Vy	20	-42.939	3836.454	8.220
			Max. Vx	2	-42.996	14.756	3842.443
			Max. Torque	7			-6.091
L49	35.083 - 30.083	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-150.777	-12.541	-4.493
			Max. Mx	20	-88.622	3926.162	8.426
			Max. My	2	-88.620	15.162	3932.252
			Max. Vy	20	-43.236	3926.162	8.426
			Max. Vx	2	-43.304	15.162	3932.252
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-150.997	-12.552	-4.498
			Max. Mx	20	-88.787	3936.971	8.451
L50	30.083 - 28	Pole	Max. My	2	-88.786	15.211	3943.074
			Max. Vy	20	-43.261	3936.971	8.451
			Max. Vx	2	-43.330	15.211	3943.074
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-156.739	-12.790	-4.631
			Max. Mx	20	-88.787	3936.971	8.451
			Max. My	2	-88.786	15.211	3943.074
			Max. Vy	20	-43.261	3936.971	8.451
			Max. Vx	2	-43.330	15.211	3943.074
L51	28 - 27.75	Pole	Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-156.739	-12.790	-4.631
L52	27.75 - 22.75	Pole	Max. Mx	20	-88.787	3936.971	8.451
			Max. My	2	-88.786	15.211	3943.074
			Max. Vy	20	-43.261	3936.971	8.451

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	55 of 92
	Project		Date	13:18:51 07/13/19
	Client	Crown Castle	Designed by	Pavan Upadhyia

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L53	22.75 - 20.083	Pole	Max. Mx	20	-92.906	4155.232	8.912
			Max. My	2	-92.905	16.124	4161.701
			Max. Vy	20	-44.092	4155.232	8.912
			Max. Vx	2	-44.187	16.124	4161.701
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-159.796	-12.920	-4.702
			Max. Mx	20	-95.133	4273.312	9.156
			Max. My	2	-95.131	16.609	4280.025
			Max. Vy	20	-44.526	4273.312	9.156
L54	20.083 - 19.833	Pole	Max. Vx	2	-44.631	16.609	4280.025
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-160.056	-12.935	-4.710
			Max. Mx	20	-95.331	4284.439	9.179
			Max. My	2	-95.330	16.654	4291.176
			Max. Vy	20	-44.548	4284.439	9.179
			Max. Vx	2	-44.653	16.654	4291.176
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
L55	19.833 - 17	Pole	Max. Compression	26	-163.088	-13.116	-4.859
			Max. Mx	20	-97.480	4411.202	9.439
			Max. My	2	-97.478	17.168	4418.227
			Max. Vy	20	-45.009	4411.202	9.439
			Max. Vx	2	-45.124	17.168	4418.227
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-163.371	-13.139	-4.872
			Max. Mx	20	-97.706	4422.448	9.462
			Max. My	2	-97.704	17.214	4429.499
L56	17 - 16.75	Pole	Max. Vy	20	-45.024	4422.448	9.462
			Max. Vx	2	-45.140	17.214	4429.499
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-168.900	-13.512	-5.137
			Max. Mx	20	-101.937	4653.897	9.935
			Max. My	2	-101.936	18.150	4661.574
			Max. Vy	20	-45.788	4653.897	9.935
			Max. Vx	2	-45.936	18.150	4661.574
			Max. Torque	7			-6.091
L57	16.75 - 11.65	Pole	Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-169.101	-13.526	-5.152
			Max. Mx	20	-102.100	4664.561	9.958
			Max. My	2	-102.099	18.195	4672.272
			Max. Vy	20	-45.786	4664.561	9.958
			Max. Vx	2	-45.955	18.195	4672.272
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-170.869	-13.630	-5.199
			Max. Mx	20	-103.453	4757.345	10.157
L58	11.65 - 11.417	Pole	Max. My	2	-103.452	18.585	4765.383
			Max. Vy	20	-46.067	4757.345	10.157
			Max. Vx	2	-46.248	18.585	4765.383
			Max. Torque	7			-6.091
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-171.094	-13.645	-5.202
			Max. Mx	20	-103.634	4768.860	10.181
			Max. My	2	-103.633	18.633	4776.940
			Max. Vy	20	-46.086	4768.860	10.181
			Max. Vx	2	-46.268	18.633	4776.940

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	56 of 92
	Project		Date	13:18:51 07/13/19
	Client	Crown Castle	Designed by	Pavan Upadhyia

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L61	9.146 - 4.833	Pole	Max. Torque	7			-6.090
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-174.950	-13.868	-5.247
			Max. Mx	20	-106.634	4968.826	10.604
			Max. My	2	-106.633	19.464	4977.682
			Max. Vy	20	-46.673	4968.826	10.604
			Max. Vx	2	-46.877	19.464	4977.682
L62	4.833 - 4.583	Pole	Max. Torque	7			-6.090
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-175.168	-13.881	-5.250
			Max. Mx	20	-106.813	4980.492	10.629
			Max. My	2	-106.812	19.512	4989.396
			Max. Vy	20	-46.689	4980.492	10.629
			Max. Vx	2	-46.895	19.512	4989.396
L63	4.583 - 0	Pole	Max. Torque	7			-6.090
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-179.068	-14.127	-5.238
			Max. Mx	20	-109.954	5195.748	11.077
			Max. My	2	-109.954	20.392	5205.562
			Max. Vy	20	-47.284	5195.748	11.077
			Max. Vx	2	-47.502	20.392	5205.562
			Max. Torque	7			-6.090

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	26	179.068	-0.000	-0.000
	Max. H _x	20	109.965	47.257	0.114
	Max. H _z	2	109.965	0.195	47.476
	Max. M _x	2	5205.562	0.195	47.476
	Max. M _z	8	5077.280	-45.845	-0.002
	Max. Torsion	19	5.826	40.469	-23.245
	Min. Vert	17	82.474	22.526	-39.209
	Min. H _x	8	109.965	-45.845	-0.002
	Min. H _z	14	109.965	-0.022	-45.770
	Min. M _x	14	-5107.594	-0.022	-45.770
	Min. M _z	20	-5195.748	47.257	0.114
	Min. Torsion	7	-6.090	-39.064	22.630

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	91.638	0.000	0.000	2.750	-3.205	-0.000
1.2 Dead+1.0 Wind 0 deg - No Ice	109.965	-0.195	-47.476	-5205.562	20.392	3.986
0.9 Dead+1.0 Wind 0 deg - No Ice	82.474	-0.195	-47.476	-5156.502	21.220	3.991
1.2 Dead+1.0 Wind 30 deg - No Ice	109.965	23.867	-41.503	-4570.615	-2629.148	5.723

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>57 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhyia</p>

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
0.9 Dead+1.0 Wind 30 deg - No Ice	82.474	23.867	-41.503	-4527.701	-2602.989	5.728
1.2 Dead+1.0 Wind 60 deg - No Ice	109.965	39.064	-22.630	-2570.092	-4439.056	6.087
0.9 Dead+1.0 Wind 60 deg - No Ice	82.474	39.064	-22.630	-2546.100	-4395.160	6.090
1.2 Dead+1.0 Wind 90 deg - No Ice	109.965	45.845	0.002	3.948	-5077.280	4.740
0.9 Dead+1.0 Wind 90 deg - No Ice	82.474	45.845	0.002	3.037	-5027.239	4.741
1.2 Dead+1.0 Wind 120 deg - No Ice	109.965	41.034	23.793	2610.823	-4491.678	1.841
0.9 Dead+1.0 Wind 120 deg - No Ice	82.474	41.034	23.793	2584.919	-4447.657	1.840
1.2 Dead+1.0 Wind 150 deg - No Ice	109.965	23.759	41.328	4583.756	-2632.448	-1.552
0.9 Dead+1.0 Wind 150 deg - No Ice	82.474	23.759	41.328	4538.951	-2606.240	-1.556
1.2 Dead+1.0 Wind 180 deg - No Ice	109.965	0.022	45.770	5107.594	-6.942	-4.243
0.9 Dead+1.0 Wind 180 deg - No Ice	82.474	0.022	45.770	5057.308	-5.874	-4.248
1.2 Dead+1.0 Wind 210 deg - No Ice	109.965	-22.526	39.209	4355.710	2491.444	-5.740
0.9 Dead+1.0 Wind 210 deg - No Ice	82.474	-22.526	39.209	4312.596	2468.307	-5.745
1.2 Dead+1.0 Wind 240 deg - No Ice	109.965	-40.469	23.245	2548.030	4423.222	-5.823
0.9 Dead+1.0 Wind 240 deg - No Ice	82.474	-40.469	23.245	2522.623	4381.723	-5.826
1.2 Dead+1.0 Wind 270 deg - No Ice	109.965	-47.257	-0.114	-11.078	5195.748	-4.347
0.9 Dead+1.0 Wind 270 deg - No Ice	82.474	-47.257	-0.114	-11.854	5146.938	-4.349
1.2 Dead+1.0 Wind 300 deg - No Ice	109.965	-39.454	-22.879	-2550.922	4392.183	-1.856
0.9 Dead+1.0 Wind 300 deg - No Ice	82.474	-39.454	-22.879	-2527.091	4350.700	-1.855
1.2 Dead+1.0 Wind 330 deg - No Ice	109.965	-22.784	-39.416	-4362.518	2516.822	1.154
0.9 Dead+1.0 Wind 330 deg - No Ice	82.474	-22.784	-39.416	-4321.112	2493.474	1.158
1.2 Dead+1.0 Ice+1.0 Temp	179.068	0.000	0.000	5.238	-14.127	0.000
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	179.068	-0.063	-11.704	-1484.940	-7.960	1.630
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	179.068	5.747	-10.038	-1279.353	-749.429	2.437
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	179.068	9.905	-5.757	-734.935	-1285.445	2.592
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	179.068	11.470	-0.008	3.954	-1481.608	2.055
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	179.068	10.062	5.849	749.358	-1292.638	0.872
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	179.068	5.743	10.032	1290.484	-748.791	-0.550
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	179.068	-0.003	11.586	1488.401	-13.765	-1.735
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	179.068	-5.713	9.972	1284.389	717.290	-2.434
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	179.068	-10.043	5.766	741.785	1263.469	-2.490

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 58 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	179.068	-11.527	-0.038	1.695	1457.438	-1.855
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	179.068	-9.972	-5.801	-737.007	1260.171	-0.840
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp	179.068	-5.773	-10.002	-1274.960	722.327	0.391
Dead+Wind 0 deg - Service	91.638	-0.042	-10.302	-1120.727	1.937	0.869
Dead+Wind 30 deg - Service	91.638	5.179	-9.006	-983.780	-569.587	1.247
Dead+Wind 60 deg - Service	91.638	8.477	-4.911	-552.218	-959.927	1.326
Dead+Wind 90 deg - Service	91.638	9.948	0.000	2.975	-1097.578	1.032
Dead+Wind 120 deg - Service	91.638	8.904	5.163	565.279	-971.326	0.400
Dead+Wind 150 deg - Service	91.638	5.156	8.968	990.857	-570.296	-0.339
Dead+Wind 180 deg - Service	91.638	0.005	9.932	1103.774	-3.961	-0.925
Dead+Wind 210 deg - Service	91.638	-4.888	8.508	941.579	534.903	-1.251
Dead+Wind 240 deg - Service	91.638	-8.782	5.044	551.718	951.611	-1.268
Dead+Wind 270 deg - Service	91.638	-10.255	-0.025	-0.268	1118.267	-0.946
Dead+Wind 300 deg - Service	91.638	-8.561	-4.965	-548.080	944.883	-0.403
Dead+Wind 330 deg - Service	91.638	-4.944	-8.553	-938.811	540.385	0.253

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.000	-91.638	0.000	0.000	91.638	0.000	0.000%
2	-0.195	-109.965	-47.476	0.195	109.965	47.476	0.000%
3	-0.195	-82.474	-47.476	0.195	82.474	47.476	0.000%
4	23.867	-109.965	-41.503	-23.867	109.965	41.503	0.000%
5	23.867	-82.474	-41.503	-23.867	82.474	41.503	0.000%
6	39.064	-109.965	-22.630	-39.064	109.965	22.630	0.000%
7	39.064	-82.474	-22.630	-39.064	82.474	22.630	0.000%
8	45.845	-109.965	0.002	-45.845	109.965	-0.002	0.000%
9	45.845	-82.474	0.002	-45.845	82.474	-0.002	0.000%
10	41.034	-109.965	23.793	-41.034	109.965	-23.793	0.000%
11	41.034	-82.474	23.793	-41.034	82.474	-23.793	0.000%
12	23.759	-109.965	41.328	-23.759	109.965	-41.328	0.000%
13	23.759	-82.474	41.328	-23.759	82.474	-41.328	0.000%
14	0.022	-109.965	45.770	-0.022	109.965	-45.770	0.000%
15	0.022	-82.474	45.770	-0.022	82.474	-45.770	0.000%
16	-22.526	-109.965	39.209	22.526	109.965	-39.209	0.000%
17	-22.526	-82.474	39.209	22.526	82.474	-39.209	0.000%
18	-40.469	-109.965	23.245	40.469	109.965	-23.245	0.000%
19	-40.469	-82.474	23.245	40.469	82.474	-23.245	0.000%
20	-47.257	-109.965	-0.114	47.257	109.965	0.114	0.000%
21	-47.257	-82.474	-0.114	47.257	82.474	0.114	0.000%
22	-39.454	-109.965	-22.879	39.454	109.965	22.879	0.000%
23	-39.454	-82.474	-22.879	39.454	82.474	22.879	0.000%
24	-22.784	-109.965	-39.416	22.784	109.965	39.416	0.000%
25	-22.784	-82.474	-39.416	22.784	82.474	39.416	0.000%
26	0.000	-179.068	0.000	-0.000	179.068	-0.000	0.000%
27	-0.063	-179.068	-11.704	0.063	179.068	11.704	0.000%
28	5.747	-179.068	-10.038	-5.747	179.068	10.038	0.000%
29	9.905	-179.068	-5.757	-9.905	179.068	5.757	0.000%
30	11.470	-179.068	-0.008	-11.470	179.068	0.008	0.000%
31	10.062	-179.068	5.849	-10.062	179.068	-5.849	0.000%
32	5.743	-179.068	10.032	-5.743	179.068	-10.032	0.000%
33	-0.003	-179.068	11.586	0.003	179.068	-11.586	0.000%
34	-5.713	-179.068	9.972	5.713	179.068	-9.972	0.000%

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 59 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
35	-10.043	-179.068	5.766	10.043	179.068	-5.766	0.000%
36	-11.527	-179.068	-0.038	11.527	179.068	0.038	0.000%
37	-9.972	-179.068	-5.801	9.972	179.068	5.801	0.000%
38	-5.773	-179.068	-10.002	5.773	179.068	10.002	0.000%
39	-0.042	-91.638	-10.302	0.042	91.638	10.302	0.000%
40	5.179	-91.638	-9.006	-5.179	91.638	9.006	0.000%
41	8.477	-91.638	-4.911	-8.477	91.638	4.911	0.000%
42	9.948	-91.638	0.000	-9.948	91.638	-0.000	0.000%
43	8.904	-91.638	5.163	-8.904	91.638	-5.163	0.000%
44	5.156	-91.638	8.968	-5.156	91.638	-8.968	0.000%
45	0.005	-91.638	9.932	-0.005	91.638	-9.932	0.000%
46	-4.888	-91.638	8.508	4.888	91.638	-8.508	0.000%
47	-8.782	-91.638	5.044	8.782	91.638	-5.044	0.000%
48	-10.255	-91.638	-0.025	10.255	91.638	0.025	0.000%
49	-8.561	-91.638	-4.965	8.561	91.638	4.965	0.000%
50	-4.944	-91.638	-8.553	4.944	91.638	8.553	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.0000001	0.00000158
2	Yes	5	0.0000001	0.00066540
3	Yes	5	0.0000001	0.00033269
4	Yes	6	0.0000001	0.00028674
5	Yes	6	0.0000001	0.00010491
6	Yes	6	0.0000001	0.00023400
7	Yes	6	0.0000001	0.00008490
8	Yes	5	0.0000001	0.00067030
9	Yes	5	0.0000001	0.00033586
10	Yes	6	0.0000001	0.00025807
11	Yes	6	0.0000001	0.00009395
12	Yes	6	0.0000001	0.00027264
13	Yes	6	0.0000001	0.00009913
14	Yes	5	0.0000001	0.00075745
15	Yes	5	0.0000001	0.00038164
16	Yes	6	0.0000001	0.00022152
17	Yes	6	0.0000001	0.00008063
18	Yes	6	0.0000001	0.00026830
19	Yes	6	0.0000001	0.00009865
20	Yes	5	0.0000001	0.00058770
21	Yes	5	0.0000001	0.00029104
22	Yes	6	0.0000001	0.00024345
23	Yes	6	0.0000001	0.00008890
24	Yes	6	0.0000001	0.00023567
25	Yes	6	0.0000001	0.00008610
26	Yes	4	0.0000001	0.00087125
27	Yes	6	0.0000001	0.00069530
28	Yes	6	0.0000001	0.00076093
29	Yes	6	0.0000001	0.00075411
30	Yes	6	0.0000001	0.00070066
31	Yes	6	0.0000001	0.00076221
32	Yes	6	0.0000001	0.00076356
33	Yes	6	0.0000001	0.00070209
34	Yes	6	0.0000001	0.00074521
35	Yes	6	0.0000001	0.00074654

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>60 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhya</p>

36	Yes	6	0.00000001	0.00068104
37	Yes	6	0.00000001	0.00073424
38	Yes	6	0.00000001	0.00073770
39	Yes	5	0.00000001	0.00004536
40	Yes	5	0.00000001	0.00009123
41	Yes	5	0.00000001	0.00007044
42	Yes	5	0.00000001	0.00004428
43	Yes	5	0.00000001	0.00007592
44	Yes	5	0.00000001	0.00008118
45	Yes	5	0.00000001	0.00004662
46	Yes	5	0.00000001	0.00006781
47	Yes	5	0.00000001	0.00008567
48	Yes	4	0.00000001	0.00099127
49	Yes	5	0.00000001	0.00006910
50	Yes	5	0.00000001	0.00006711

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	191.667 - 186.667	18.482	44	0.882	0.006
L2	186.667 - 181.567	17.558	44	0.882	0.005
L3	181.567 - 176.567	16.617	44	0.881	0.005
L4	176.567 - 171.567	15.696	44	0.878	0.005
L5	171.567 - 166.567	14.780	44	0.870	0.005
L6	166.567 - 161.567	13.875	44	0.858	0.004
L7	161.567 - 156.567	12.986	44	0.841	0.004
L8	156.567 - 151.567	12.116	44	0.818	0.004
L9	151.567 - 146.567	11.276	44	0.786	0.003
L10	146.567 - 141.567	10.474	44	0.743	0.003
L11	141.567 - 141.417	9.725	44	0.685	0.003
L12	141.417 - 136.417	9.704	44	0.683	0.003
L13	136.417 - 131.417	9.000	44	0.661	0.003
L14	131.417 - 126.417	8.320	44	0.635	0.002
L15	126.417 - 121.417	7.670	44	0.605	0.002
L16	121.417 - 121.167	7.055	44	0.569	0.002
L17	121.167 - 116.167	7.025	44	0.568	0.002
L18	116.167 - 111.167	6.444	44	0.542	0.002
L19	111.167 - 110.042	5.892	44	0.513	0.001
L20	110.042 - 109.792	5.772	44	0.506	0.001
L21	109.792 - 105.083	5.745	44	0.505	0.001
L22	105.083 - 104.833	5.259	44	0.480	0.001
L23	104.833 - 100.917	5.234	44	0.479	0.001
L24	100.917 - 100.667	4.850	44	0.459	0.001
L25	100.667 - 95.833	4.826	44	0.458	0.001
L26	95.833 - 95.583	4.375	44	0.431	0.001
L27	95.583 - 90.583	4.353	44	0.430	0.001
L28	90.583 - 89.917	3.915	44	0.406	0.001
L29	89.917 - 89.667	3.859	44	0.402	0.001
L30	89.667 - 84.667	3.838	44	0.401	0.001
L31	84.667 - 80.833	3.429	44	0.379	0.001
L32	80.833 - 80.333	3.133	44	0.360	0.001
L33	80.333 - 80.083	3.095	44	0.358	0.001
L34	80.083 - 75.083	3.076	44	0.357	0.001
L35	75.083 - 70.083	2.713	44	0.336	0.001
L36	70.083 - 69.5	2.374	44	0.312	0.001
L37	69.5 - 69.25	2.336	44	0.309	0.001
L38	69.25 - 64.25	2.320	44	0.308	0.001
L39	64.25 - 60.583	2.008	44	0.287	0.001

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 61 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L40	60.583 - 60.333	1.794	44	0.270	0.001
L41	60.333 - 55.333	1.780	44	0.269	0.001
L42	55.333 - 52.167	1.508	44	0.249	0.000
L43	52.167 - 51.917	1.347	44	0.236	0.000
L44	51.917 - 46.917	1.335	44	0.235	0.000
L45	46.917 - 41.917	1.099	44	0.216	0.000
L46	41.917 - 40.333	0.882	44	0.196	0.000
L47	40.333 - 40.083	0.818	44	0.190	0.000
L48	40.083 - 35.083	0.808	44	0.189	0.000
L49	35.083 - 30.083	0.622	44	0.167	0.000
L50	30.083 - 28	0.460	44	0.143	0.000
L51	28 - 27.75	0.400	44	0.133	0.000
L52	27.75 - 22.75	0.393	44	0.132	0.000
L53	22.75 - 20.083	0.266	44	0.110	0.000
L54	20.083 - 19.833	0.208	44	0.098	0.000
L55	19.833 - 17	0.203	44	0.097	0.000
L56	17 - 16.75	0.150	44	0.082	0.000
L57	16.75 - 11.65	0.145	44	0.081	0.000
L58	11.65 - 11.417	0.072	44	0.057	0.000
L59	11.417 - 9.396	0.069	44	0.056	0.000
L60	9.396 - 9.146	0.047	44	0.046	0.000
L61	9.146 - 4.833	0.045	44	0.045	0.000
L62	4.833 - 4.583	0.013	44	0.025	0.000
L63	4.583 - 0	0.012	44	0.024	0.000

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
191.667	Lightning Rod 5/8" x 4' on 4' Pole	44	18.482	0.882	0.006	377563
191.000	WB2623 w/ Mount Pipe	44	18.359	0.882	0.006	377563
184.000	OGB4-900D	44	17.066	0.881	0.005	284785
178.000	4' ICE SHIELDS	44	15.959	0.879	0.005	67111
160.000	(2) LNX-8513DS-A1M	44	12.711	0.835	0.004	13214
158.000	SRL-224NM-4	44	12.363	0.825	0.004	11542
151.000	7770.00 w/ Mount Pipe	44	11.182	0.782	0.003	7420
150.000	DC6-48-60-18-8F	44	11.019	0.774	0.003	6971
138.000	4' ICE SHIELDS	44	9.220	0.664	0.003	11665
132.000	SRL-235-2	44	8.398	0.639	0.002	10355
124.000	PCS 1900 TMA RX	44	7.368	0.588	0.002	8434
120.000	VHLP2-18	44	6.887	0.560	0.002	9969
116.000	(2) 6' x 2" Mount Pipe	44	6.425	0.541	0.002	10483
114.000	Miscellaneous [NA 509-3]	44	6.201	0.531	0.002	10014
98.000	4' ICE SHIELDS	44	4.574	0.443	0.001	10728
90.000	KP2F-34	44	3.866	0.403	0.001	12199
70.000	SRL-235-2	44	2.368	0.312	0.001	12626
33.000	DB909XVTE-M	44	0.552	0.157	0.000	12168

Maximum Tower Deflections - Design Wind

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	62 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhya

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	191.667 - 186.667	85.377	12	4.072	0.026
L2	186.667 - 181.567	81.120	12	4.070	0.025
L3	181.567 - 176.567	76.779	12	4.069	0.024
L4	176.567 - 171.567	72.531	12	4.054	0.023
L5	171.567 - 166.567	68.308	12	4.020	0.022
L6	166.567 - 161.567	64.132	12	3.964	0.020
L7	161.567 - 156.567	60.024	12	3.887	0.019
L8	156.567 - 151.567	56.011	12	3.782	0.018
L9	151.567 - 146.567	52.128	12	3.635	0.016
L10	146.567 - 141.567	48.425	12	3.435	0.014
L11	141.567 - 141.417	44.966	12	3.167	0.012
L12	141.417 - 136.417	44.866	12	3.157	0.012
L13	136.417 - 131.417	41.613	12	3.058	0.012
L14	131.417 - 126.417	38.474	12	2.939	0.011
L15	126.417 - 121.417	35.471	12	2.797	0.010
L16	121.417 - 121.167	32.627	12	2.634	0.009
L17	121.167 - 116.167	32.490	12	2.625	0.009
L18	116.167 - 111.167	29.803	12	2.507	0.008
L19	111.167 - 110.042	27.248	12	2.373	0.007
L20	110.042 - 109.792	26.693	12	2.340	0.007
L21	109.792 - 105.083	26.570	12	2.334	0.007
L22	105.083 - 104.833	24.324	12	2.220	0.006
L23	104.833 - 100.917	24.208	12	2.215	0.006
L24	100.917 - 100.667	22.430	12	2.123	0.006
L25	100.667 - 95.833	22.319	12	2.117	0.005
L26	95.833 - 95.583	20.238	12	1.994	0.005
L27	95.583 - 90.583	20.133	12	1.989	0.005
L28	90.583 - 89.917	18.109	12	1.877	0.005
L29	89.917 - 89.667	17.849	12	1.861	0.004
L30	89.667 - 84.667	17.751	12	1.856	0.004
L31	84.667 - 80.833	15.862	12	1.752	0.004
L32	80.833 - 80.333	14.489	12	1.666	0.004
L33	80.333 - 80.083	14.315	12	1.658	0.004
L34	80.083 - 75.083	14.229	12	1.653	0.004
L35	75.083 - 70.083	12.550	12	1.553	0.003
L36	70.083 - 69.5	10.980	12	1.444	0.003
L37	69.5 - 69.25	10.805	12	1.431	0.003
L38	69.25 - 64.25	10.730	12	1.426	0.003
L39	64.25 - 60.583	9.288	12	1.328	0.003
L40	60.583 - 60.333	8.297	12	1.250	0.002
L41	60.333 - 55.333	8.232	12	1.246	0.002
L42	55.333 - 52.167	6.976	12	1.153	0.002
L43	52.167 - 51.917	6.232	12	1.091	0.002
L44	51.917 - 46.917	6.175	12	1.086	0.002
L45	46.917 - 41.917	5.082	12	1.001	0.002
L46	41.917 - 40.333	4.082	12	0.909	0.002
L47	40.333 - 40.083	3.785	12	0.879	0.002
L48	40.083 - 35.083	3.739	12	0.874	0.002
L49	35.083 - 30.083	2.878	12	0.771	0.001
L50	30.083 - 28	2.128	12	0.661	0.001
L51	28 - 27.75	1.850	12	0.614	0.001
L52	27.75 - 22.75	1.818	12	0.609	0.001
L53	22.75 - 20.083	1.231	12	0.510	0.001
L54	20.083 - 19.833	0.962	12	0.455	0.001
L55	19.833 - 17	0.938	12	0.449	0.001
L56	17 - 16.75	0.692	12	0.380	0.001
L57	16.75 - 11.65	0.672	12	0.374	0.001
L58	11.65 - 11.417	0.331	12	0.265	0.000
L59	11.417 - 9.396	0.318	12	0.260	0.000
L60	9.396 - 9.146	0.218	12	0.215	0.000
L61	9.146 - 4.833	0.206	12	0.209	0.000

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 63 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L62	4.833 - 4.583	0.059	12	0.116	0.000
L63	4.583 - 0	0.053	12	0.110	0.000

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
191.667	Lightning Rod 5/8" x 4' on 4' Pole	12	85.377	4.072	0.026	132111
191.000	WB2623 w/ Mount Pipe	12	84.809	4.072	0.026	132111
184.000	OGB4-900D	12	78.850	4.070	0.025	90977
178.000	4' ICE SHIELDS	12	73.747	4.060	0.023	15647
160.000	(2) LNX-8513DS-A1M	12	58.755	3.858	0.019	2906
158.000	SRL-224NM-4	12	57.150	3.816	0.018	2536
151.000	7770.00 w/ Mount Pipe	12	51.698	3.615	0.016	1622
150.000	DC6-48-60-18-8F	12	50.946	3.579	0.015	1523
138.000	4' ICE SHIELDS	12	42.631	3.069	0.012	2531
132.000	SRL-235-2	12	38.833	2.956	0.011	2251
124.000	PCS 1900 TMA RX	12	34.075	2.722	0.009	1833
120.000	VHLP2-18	12	31.852	2.589	0.008	2165
116.000	(2) 6' x 2" Mount Pipe	12	29.715	2.503	0.008	2277
114.000	Miscellaneous [NA 509-3]	12	28.678	2.455	0.007	2174
98.000	4' ICE SHIELDS	12	21.155	2.047	0.005	2326
90.000	KP2F-34	12	17.881	1.863	0.004	2644
70.000	SRL-235-2	12	10.955	1.442	0.003	2733
33.000	DB909XVTE-M	12	2.551	0.727	0.001	2630

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
L1	191.667 - 190.667	P18x0.375	5.000	0.000	0.0	20.764	-0.650	784.878	0.001
	190.667 - 189.667						-0.808	784.878	0.001
	189.667 - 188.667						-0.966	784.878	0.001
	188.667 - 187.667						-1.124	784.878	0.001
	187.667 - 186.667						-0.640	784.878	0.001
	186.667 - 185.647						-0.771	1052.070	0.001
L2	185.647 - 184.627	P24x0.375	5.100	0.000	0.0	27.833	-0.902	1052.070	0.001
	184.627 - 183.607						-11.177	1052.070	0.011*

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>64 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhy</p>

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio P _u / φP _n
	183.607 - 182.587					27.833	-11.362	1052.070	0.011
	182.587 - 181.567					27.833	-11.581	1052.070	0.011
L3	181.567 - 180.567	P24x0.375	5.000	0.000	0.0	27.833	-5.186	1052.070	0.005
	180.567 - 179.567					27.833	-5.323	1052.070	0.005
	179.567 - 178.567					27.833	-5.460	1052.070	0.005
	178.567 - 177.567					27.833	-5.631	1052.070	0.005
	177.567 - 176.567					27.833	-5.762	1052.070	0.005
L4	176.567 - 175.567	P24x0.375	5.000	0.000	0.0	27.833	-5.900	1052.070	0.006
	175.567 - 174.567					27.833	-6.037	1052.070	0.006
	174.567 - 173.567					27.833	-6.175	1052.070	0.006
	173.567 - 172.567					27.833	-6.312	1052.070	0.006
	172.567 - 171.567					27.833	-6.450	1052.070	0.006
L5	171.567 - 170.567	P24x0.375	5.000	0.000	0.0	27.833	-6.588	1052.070	0.006
	170.567 - 169.567					27.833	-6.726	1052.070	0.006
	169.567 - 168.567					27.833	-6.864	1052.070	0.007
	168.567 - 167.567					27.833	-7.002	1052.070	0.007
	167.567 - 166.567					27.833	-7.141	1052.070	0.007
L6	166.567 - 165.567	P24x0.375	5.000	0.000	0.0	27.833	-7.279	1052.070	0.007
	165.567 - 164.567					27.833	-7.418	1052.070	0.007
	164.567 - 163.567					27.833	-7.556	1052.070	0.007
	163.567 - 162.567					27.833	-7.695	1052.070	0.007
	162.567 - 161.567					27.833	-7.834	1052.070	0.007
L7	161.567 - 160.567	P24x0.375	5.000	0.000	0.0	27.833	-7.977	1052.070	0.008
	160.567 - 159.567					27.833	-11.661	1052.070	0.011
	159.567 - 158.567					27.833	-11.806	1052.070	0.011
	158.567 - 157.567					27.833	-12.148	1052.070	0.012
	157.567 - 156.567					27.833	-12.294	1052.070	0.012
L8	156.567 - 155.567	P24x0.375	5.000	0.000	0.0	27.833	-12.441	1052.070	0.012
	155.567 - 154.567					27.833	-12.589	1052.070	0.012
	154.567 - 153.567					27.833	-12.738	1052.070	0.012

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>65 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhy</p>

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
	153.567 - 152.567					27.833	-12.895	1052.070	0.012
	152.567 - 151.567					27.833	-13.045	1052.070	0.012
L9	151.567 - 150.567	P24x0.375	5.000	0.000	0.0	27.833	-17.568	1052.070	0.017
	150.567 - 149.567					27.833	-18.435	1052.070	0.018
	149.567 - 148.567					27.833	-18.602	1052.070	0.018
	148.567 - 147.567					27.833	-18.769	1052.070	0.018
	147.567 - 146.567					27.833	-18.937	1052.070	0.018
L10	146.567 - 145.567	P24x0.375	5.000	0.000	0.0	27.833	-19.109	1052.070	0.018
	145.567 - 144.567					27.833	-19.282	1052.070	0.018
	144.567 - 143.567					27.833	-19.455	1052.070	0.018
	143.567 - 142.567					27.833	-19.630	1052.070	0.019
	142.567 - 141.567					27.833	-19.806	1052.070	0.019
L11	141.567 - 141.417 (11)	P24x0.375	0.150	0.000	0.0	27.833	-19.840	1052.070	0.019
L12	141.417 - 140.417	P36x0.375	5.000	0.000	0.0	41.970	-20.058	1490.100	0.013
	140.417 - 139.417					41.970	-20.277	1490.100	0.014
	139.417 - 138.417					41.970	-20.497	1490.100	0.014
	138.417 - 137.417					41.970	-20.749	1490.100	0.014
	137.417 - 136.417					41.970	-20.970	1490.100	0.014
L13	136.417 - 135.417	P36x0.375	5.000	0.000	0.0	41.970	-21.190	1490.100	0.014
	135.417 - 134.417					41.970	-21.411	1490.100	0.014
	134.417 - 133.417					41.970	-21.633	1490.100	0.015
	133.417 - 132.417					41.970	-21.854	1490.100	0.015
	132.417 - 131.417					41.970	-22.552	1490.100	0.015
L14	131.417 - 130.417	P36x0.375	5.000	0.000	0.0	41.970	-22.783	1490.100	0.015
	130.417 - 129.417					41.970	-23.015	1490.100	0.015
	129.417 - 128.417					41.970	-23.247	1490.100	0.016
	128.417 - 127.417					41.970	-23.480	1490.100	0.016
	127.417 - 126.417					41.970	-23.712	1490.100	0.016
L15	126.417 - 125.417	P36x0.375	5.000	0.000	0.0	41.970	-24.080	1490.100	0.016
	125.417 - 124.417					41.970	-24.448	1490.100	0.016

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio P _u / φP _n
	124.417 - 123.417					41.970	-25.183	1490.100	0.017
	123.417 - 122.417					41.970	-25.552	1490.100	0.017
	122.417 - 121.417					41.970	-25.921	1490.100	0.017
L16	121.417 - 121.167 (16)	P36x0.375	0.250	0.000	0.0	41.970	-25.996	1490.100	0.017
L17	121.167 - 120.167	P42x0.375	5.000	0.000	0.0	49.038	-26.281	1668.870	0.016
	120.167 - 119.167					49.038	-26.601	1668.870	0.016
	119.167 - 118.167					49.038	-26.888	1668.870	0.016
	118.167 - 117.167					49.038	-27.176	1668.870	0.016
	117.167 - 116.167					49.038	-27.464	1668.870	0.016
L18	116.167 - 115.167	P42x0.375	5.000	0.000	0.0	49.038	-31.358	1668.870	0.019
	115.167 - 114.167					49.038	-31.633	1668.870	0.019
	114.167 - 113.167					49.038	-32.218	1668.870	0.019
	113.167 - 112.167					49.038	-32.494	1668.870	0.019
	112.167 - 111.167					49.038	-32.770	1668.870	0.020
L19	111.167 - 110.042 (19)	P42x0.375	1.125	0.000	0.0	49.038	-33.081	1668.870	0.020
L20	110.042 - 109.792 (20)	P42x0.4875	0.250	0.000	0.0	63.577	-33.170	2332.130	0.014
L21	109.792 - 108.615	P42x0.4875	4.709	0.000	0.0	63.577	-33.550	2332.130	0.014
	108.615 - 107.438					63.577	-33.963	2332.130	0.015
	107.438 - 106.26					63.577	-34.377	2332.130	0.015
	106.26 - 105.083					63.577	-34.791	2332.130	0.015
L22	105.083 - 104.833 (22)	P42x0.5625	0.250	0.000	0.0	73.226	-34.902	2767.950	0.013
L23	104.833 - 103.528	P42x0.5625	3.916	0.000	0.0	73.226	-35.706	2767.950	0.013
	103.528 - 102.222					73.226	-36.516	2767.950	0.013
	102.222 - 100.917					73.226	-37.327	2767.950	0.013
L24	100.917 - 100.667 (24)	P48x0.375	0.250	0.000	0.0	56.107	-37.437	1847.490	0.020
L25	100.667 - 99.4585	P48x0.375	4.834	0.000	0.0	56.107	-37.864	1847.490	0.020
	99.4585 - 98.25					56.107	-38.299	1847.490	0.021
	98.25 - 97.0415					56.107	-38.837	1847.490	0.021
	97.0415 - 95.833					56.107	-39.273	1847.490	0.021
L26	95.833 - 95.583 (26)	P48x0.475	0.250	0.000	0.0	70.920	-39.370	2481.390	0.016

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 67 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhy

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
L27	95.583 - 94.583	P48x0.475	5.000	0.000	0.0	70.920	-39.722	2481.390	0.016
	94.583 - 93.583					70.920	-40.078	2481.390	0.016
	93.583 - 92.583					70.920	-40.435	2481.390	0.016
	92.583 - 91.583					70.920	-40.793	2481.390	0.016
	91.583 - 90.583					70.920	-41.151	2481.390	0.017
L28	90.583 - 89.917 (28)	P48x0.475	0.666	0.000	0.0	70.920	-41.887	2481.390	0.017
L29	89.917 - 89.667 (29)	P48x0.575	0.250	0.000	0.0	85.669	-42.001	3174.020	0.013
L30	89.667 - 88.667	P48x0.575	5.000	0.000	0.0	85.669	-42.564	3174.020	0.013
	88.667 - 87.667					85.669	-43.132	3174.020	0.014
	87.667 - 86.667					85.669	-43.700	3174.020	0.014
	86.667 - 85.667					85.669	-44.268	3174.020	0.014
	85.667 - 84.667					85.669	-44.836	3174.020	0.014
L31	84.667 - 83.389	P48x0.575	3.834	0.000	0.0	85.669	-45.894	3174.020	0.014
	83.389 - 82.111					85.669	-46.955	3174.020	0.015
	82.111 - 80.833					85.669	-48.016	3174.020	0.015
L32	80.833 - 80.333 (32)	P54x0.55	0.500	0.000	0.0	92.355	-48.398	3257.830	0.015
L33	80.333 - 80.083 (33)	P54x0.4875	0.250	0.000	0.0	81.956	-48.539	2797.170	0.017
L34	80.083 - 79.083	P54x0.4875	5.000	0.000	0.0	81.956	-49.031	2797.170	0.018
	79.083 - 78.083					81.956	-49.527	2797.170	0.018
	78.083 - 77.083					81.956	-50.023	2797.170	0.018
	77.083 - 76.083					81.956	-50.519	2797.170	0.018
	76.083 - 75.083					81.956	-51.016	2797.170	0.018
L35	75.083 - 74.083	P54x0.4875	5.000	0.000	0.0	81.956	-51.596	2797.170	0.018
	74.083 - 73.083					81.956	-52.176	2797.170	0.019
	73.083 - 72.083					81.956	-52.757	2797.170	0.019
	72.083 - 71.083					81.956	-53.338	2797.170	0.019
	71.083 - 70.083					81.956	-53.919	2797.170	0.019
L36	70.083 - 69.5 (36)	P54x0.4875	0.583	0.000	0.0	81.956	-54.599	2797.170	0.020
L37	69.5 - 69.25 (37)	P54x0.5875	0.250	0.000	0.0	98.583	-54.787	3545.230	0.015
L38	69.25 - 68.25	P54x0.5875	5.000	0.000	0.0	98.583	-56.056	3545.230	0.016
	68.25 - 67.25					98.583	-57.330	3545.230	0.016

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 68 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhy

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio P _u / φP _n
	67.25 - 66.25					98.583	-58.604	3545.230	0.017
	66.25 - 65.25					98.583	-59.879	3545.230	0.017
	65.25 - 64.25					98.583	-61.154	3545.230	0.017
L39	64.25 - 63.0277	P54x0.5875	3.667	0.000	0.0	98.583	-62.879	3545.230	0.018
	63.0277 - 61.8053					98.583	-64.606	3545.230	0.018
	61.8053 - 60.583					98.583	-66.334	3545.230	0.019
L40	60.583 - 60.333 (40)	P60x0.5125	0.250	0.000	0.0	95.779	-66.540	3222.890	0.021
L41	60.333 - 59.333	P60x0.5125	5.000	0.000	0.0	95.779	-67.292	3222.890	0.021
	59.333 - 58.333					95.779	-68.050	3222.890	0.021
	58.333 - 57.333					95.779	-68.807	3222.890	0.021
	57.333 - 56.333					95.779	-69.565	3222.890	0.022
	56.333 - 55.333					95.779	-70.324	3222.890	0.022
L42	55.333 - 54.2777	P60x0.5125	3.166	0.000	0.0	95.779	-70.821	3222.890	0.022
	54.2777 - 53.2223					95.779	-71.319	3222.890	0.022
	53.2223 - 52.167					95.779	-71.817	3222.890	0.022
L43	52.167 - 51.917 (43)	P60x0.625	0.250	0.000	0.0	116.583	-71.963	4139.150	0.017
L44	51.917 - 50.917	P60x0.625	5.000	0.000	0.0	116.583	-72.579	4139.150	0.018
	50.917 - 49.917					116.583	-73.200	4139.150	0.018
	49.917 - 48.917					116.583	-73.821	4139.150	0.018
	48.917 - 47.917					116.583	-74.442	4139.150	0.018
	47.917 - 46.917					116.583	-75.064	4139.150	0.018
L45	46.917 - 45.917	P60x0.625	5.000	0.000	0.0	116.583	-75.858	4139.150	0.018
	45.917 - 44.917					116.583	-76.652	4139.150	0.019
	44.917 - 43.917					116.583	-77.447	4139.150	0.019
	43.917 - 42.917					116.583	-78.242	4139.150	0.019
	42.917 - 41.917					116.583	-79.037	4139.150	0.019
L46	41.917 - 40.333 (46)	P60x0.625	1.584	0.000	0.0	116.583	-80.285	4139.150	0.019
L47	40.333 - 40.083 (47)	P60x0.6	0.250	0.000	0.0	111.966	-80.478	3929.110	0.020
L48	40.083 - 39.083	P60x0.6	5.000	0.000	0.0	111.966	-81.207	3929.110	0.021
	39.083 - 38.083					111.966	-81.943	3929.110	0.021
	38.083 - 37.083					111.966	-82.679	3929.110	0.021
	37.083 -					111.966	-83.415	3929.110	0.021

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 69 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
	36.083								
	36.083 - 35.083					111.966	-84.151	3929.110	0.021
L49	35.083 - 34.083	P60x0.6	5.000	0.000	0.0	111.966	-84.779	3929.110	0.022
	34.083 - 33.083					111.966	-85.407	3929.110	0.022
	33.083 - 32.083					111.966	-86.223	3929.110	0.022
	32.083 - 31.083					111.966	-86.852	3929.110	0.022
	31.083 - 30.083					111.966	-87.481	3929.110	0.022
L50	30.083 - 29.0415	P60x0.6	2.083	0.000	0.0	111.966	-88.043	3929.110	0.022
	29.0415 - 28					111.966	-88.606	3929.110	0.023
L51	28 - 27.75 (51)	P60x0.725	0.250	0.000	0.0	135.008	-88.772	5015.910	0.018
L52	27.75 - 26.75	P60x0.725	5.000	0.000	0.0	135.008	-89.592	5015.910	0.018
	26.75 - 25.75					135.008	-90.417	5015.910	0.018
	25.75 - 24.75					135.008	-91.242	5015.910	0.018
	24.75 - 23.75					135.008	-92.067	5015.910	0.018
	23.75 - 22.75					135.008	-92.893	5015.910	0.019
L53	22.75 - 21.4165	P60x0.725	2.667	0.000	0.0	135.008	-94.005	5015.910	0.019
	21.4165 - 20.083					135.008	-95.121	5015.910	0.019
L54	20.083 - 19.833 (54)	P60x0.625	0.250	0.000	0.0	116.583	-95.320	4139.150	0.023
L55	19.833 - 18.4165	P60x0.625	2.833	0.000	0.0	116.583	-96.389	4139.150	0.023
	18.4165 - 17					116.583	-97.470	4139.150	0.024
L56	17 - 16.75 (56)	P60x0.725	0.250	0.000	0.0	135.008	-97.696	5015.910	0.019
L57	16.75 - 15.73	P60x0.75	5.100	0.000	0.0	139.605	-98.537	5244.230	0.019
	15.73 - 14.71					139.605	-99.385	5244.230	0.019
	14.71 - 13.69					139.605	-100.233	5244.230	0.019
	13.69 - 12.67					139.605	-101.081	5244.230	0.019
	12.67 - 11.65					139.605	-101.930	5244.230	0.019
L58	11.65 - 11.417 (58)	P60x0.75	0.233	0.000	0.0	139.605	-102.094	5244.230	0.019
L59	11.417 - 10.4065	P60x0.75	2.021	0.000	0.0	139.605	-102.768	5244.230	0.020
	10.4065 - 9.396					139.605	-103.448	5244.230	0.020
L60	9.396 - 9.146 (60)	P60x0.8	0.250	0.000	0.0	148.786	-103.630	5624.100	0.018
L61	9.146 - 8.06775	P60x0.8	4.313	0.000	0.0	148.786	-104.374	5624.100	0.019
	8.06775 - 6.9895					148.786	-105.126	5624.100	0.019
	6.9895 - 5.91125					148.786	-105.878	5624.100	0.019
	5.91125 - 4.833					148.786	-106.631	5624.100	0.019
L62	4.833 - 4.583 (62)	P60x0.75	0.250	0.000	0.0	139.605	-106.810	5244.230	0.020
L63	4.583 - 3.43725	P60x0.75	4.583	0.000	0.0	139.605	-107.589	5244.230	0.021
	3.43725 - 2.2915					139.605	-108.377	5244.230	0.021
	2.2915 -					139.605	-109.165	5244.230	0.021

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 70 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
	1.14575					139.605	-109.954	5244.230	0.021
	1.14575 - 0								

* DL controls

Pole Bending Design Data

Section No.	Elevation ft	Size	M _{ux} kip-ft	φM _{ux} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	M _{uy} kip-ft	φM _{uy} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
L1	191.667 - 190.667	P18x0.375	1.185	367.000	0.003	0.000	367.000	0.000
	190.667 - 189.667		1.312	367.000	0.004	0.000	367.000	0.000
	189.667 - 188.667		1.460	367.000	0.004	0.000	367.000	0.000
	188.667 - 187.667		1.628	367.000	0.004	0.000	367.000	0.000
	187.667 - 186.667		2.211	367.000	0.006	0.000	367.000	0.000
L2	186.667 - 185.647	P24x0.375	2.737	623.717	0.004	0.000	623.717	0.000
	185.647 - 184.627		3.331	623.717	0.005	0.000	623.717	0.000
	184.627 - 183.607		2.552	623.717	0.004	0.000	623.717	0.000
	183.607 - 182.587		3.988	623.717	0.006	0.000	623.717	0.000
	182.587 - 181.567		5.611	623.717	0.009	0.000	623.717	0.000
L3	181.567 - 180.567	P24x0.375	12.327	623.717	0.020	0.000	623.717	0.000
	180.567 - 179.567		17.436	623.717	0.028	0.000	623.717	0.000
	179.567 - 178.567		22.609	623.717	0.036	0.000	623.717	0.000
	178.567 - 177.567		27.835	623.717	0.045	0.000	623.717	0.000
	177.567 - 176.567		33.162	623.717	0.053	0.000	623.717	0.000
L4	176.567 - 175.567	P24x0.375	38.592	623.717	0.062	0.000	623.717	0.000
	175.567 - 174.567		44.086	623.717	0.071	0.000	623.717	0.000
	174.567 - 173.567		49.644	623.717	0.080	0.000	623.717	0.000
	173.567 - 172.567		55.266	623.717	0.089	0.000	623.717	0.000
	172.567 - 171.567		60.952	623.717	0.098	0.000	623.717	0.000
L5	171.567 - 170.567	P24x0.375	66.701	623.717	0.107	0.000	623.717	0.000
	170.567 - 169.567		72.513	623.717	0.116	0.000	623.717	0.000
	169.567 - 168.567		78.389	623.717	0.126	0.000	623.717	0.000

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>71 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhy</p>

Section No.	Elevation ft	Size	M_{ux} kip-ft	ϕM_{rx} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{rx}}$	M_{uy} kip-ft	ϕM_{ry} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ry}}$
	168.567 - 167.567		84.327	623.717	0.135	0.000	623.717	0.000
	167.567 - 166.567		90.328	623.717	0.145	0.000	623.717	0.000
L6	166.567 - 165.567	P24x0.375	96.391	623.717	0.155	0.000	623.717	0.000
	165.567 - 164.567		102.515	623.717	0.164	0.000	623.717	0.000
	164.567 - 163.567		108.702	623.717	0.174	0.000	623.717	0.000
	163.567 - 162.567		114.949	623.717	0.184	0.000	623.717	0.000
	162.567 - 161.567		121.258	623.717	0.194	0.000	623.717	0.000
L7	161.567 - 160.567	P24x0.375	127.628	623.717	0.205	0.000	623.717	0.000
	160.567 - 159.567		135.827	623.717	0.218	0.000	623.717	0.000
	159.567 - 158.567		147.135	623.717	0.236	0.000	623.717	0.000
	158.567 - 157.567		159.237	623.717	0.255	0.000	623.717	0.000
	157.567 - 156.567		171.028	623.717	0.274	0.000	623.717	0.000
L8	156.567 - 155.567	P24x0.375	182.876	623.717	0.293	0.000	623.717	0.000
	155.567 - 154.567		194.780	623.717	0.312	0.000	623.717	0.000
	154.567 - 153.567		206.741	623.717	0.331	0.000	623.717	0.000
	153.567 - 152.567		218.694	623.717	0.351	0.000	623.717	0.000
	152.567 - 151.567		230.789	623.717	0.370	0.000	623.717	0.000
L9	151.567 - 150.567	P24x0.375	245.119	623.717	0.393	0.000	623.717	0.000
	150.567 - 149.567		263.762	623.717	0.423	0.000	623.717	0.000
	149.567 - 148.567		282.333	623.717	0.453	0.000	623.717	0.000
	148.567 - 147.567		300.953	623.717	0.483	0.000	623.717	0.000
	147.567 - 146.567		319.620	623.717	0.512	0.000	623.717	0.000
L10	146.567 - 145.567	P24x0.375	338.333	623.717	0.542	0.000	623.717	0.000
	145.567 - 144.567		357.091	623.717	0.573	0.000	623.717	0.000
	144.567 - 143.567		375.892	623.717	0.603	0.000	623.717	0.000
	143.567 - 142.567		394.735	623.717	0.633	0.000	623.717	0.000
	142.567 - 141.567		413.619	623.717	0.663	0.000	623.717	0.000
L11	141.567 - 141.417 (11)	P24x0.375	416.456	623.717	0.668	0.000	623.717	0.000
L12	141.417 - 140.417	P36x0.375	435.411	1338.808	0.325	0.000	1338.808	0.000
	140.417 - 139.417		454.447	1338.808	0.339	0.000	1338.808	0.000

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	72 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhy

Section No.	Elevation ft	Size	M_{ux} kip-ft	ϕM_{ux} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	M_{uy} kip-ft	ϕM_{uy} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
	139.417 - 138.417		473.567	1338.808	0.354	0.000	1338.808	0.000
	138.417 - 137.417		492.732	1338.808	0.368	0.000	1338.808	0.000
	137.417 - 136.417		512.075	1338.808	0.382	0.000	1338.808	0.000
L13	136.417 - 135.417	P36x0.375	531.498	1338.808	0.397	0.000	1338.808	0.000
	135.417 - 134.417		551.002	1338.808	0.412	0.000	1338.808	0.000
	134.417 - 133.417		570.582	1338.808	0.426	0.000	1338.808	0.000
	133.417 - 132.417		590.242	1338.808	0.441	0.000	1338.808	0.000
	132.417 - 131.417		610.846	1338.808	0.456	0.000	1338.808	0.000
L14	131.417 - 130.417	P36x0.375	631.210	1338.808	0.471	0.000	1338.808	0.000
	130.417 - 129.417		651.650	1338.808	0.487	0.000	1338.808	0.000
	129.417 - 128.417		672.166	1338.808	0.502	0.000	1338.808	0.000
	128.417 - 127.417		692.756	1338.808	0.517	0.000	1338.808	0.000
	127.417 - 126.417		713.421	1338.808	0.533	0.000	1338.808	0.000
L15	126.417 - 125.417	P36x0.375	734.207	1338.808	0.548	0.000	1338.808	0.000
	125.417 - 124.417		755.148	1338.808	0.564	0.000	1338.808	0.000
	124.417 - 123.417		776.243	1338.808	0.580	0.000	1338.808	0.000
	123.417 - 122.417		797.671	1338.808	0.596	0.000	1338.808	0.000
	122.417 - 121.417		819.252	1338.808	0.612	0.000	1338.808	0.000
L16	121.417 - 121.167 (16)	P36x0.375	824.670	1338.808	0.616	0.000	1338.808	0.000
L17	121.167 - 120.167	P42x0.375	846.408	1796.558	0.471	0.000	1796.558	0.000
	120.167 - 119.167		868.417	1796.558	0.483	0.000	1796.558	0.000
	119.167 - 118.167		890.425	1796.558	0.496	0.000	1796.558	0.000
	118.167 - 117.167		912.525	1796.558	0.508	0.000	1796.558	0.000
	117.167 - 116.167		934.700	1796.558	0.520	0.000	1796.558	0.000
L18	116.167 - 115.167	P42x0.375	963.542	1796.558	0.536	0.000	1796.558	0.000
	115.167 - 114.167		989.133	1796.558	0.551	0.000	1796.558	0.000
	114.167 - 113.167		1015.217	1796.558	0.565	0.000	1796.558	0.000
	113.167 - 112.167		1041.458	1796.558	0.580	0.000	1796.558	0.000
	112.167 - 111.167		1067.792	1796.558	0.594	0.000	1796.558	0.000
L19	111.167 - 110.042 (19)	P42x0.375	1097.500	1796.558	0.611	0.000	1796.558	0.000

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>73 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhy</p>

Section No.	Elevation ft	Size	M_{ux} kip-ft	ϕM_{ux} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	M_{uy} kip-ft	ϕM_{uy} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
L20	110.042 - 109.792 (20)	P42x0.4875	1104.117	2395.433	0.461	0.000	2395.433	0.000
L21	109.792 - 108.615 108.615 - 107.438 107.438 - 106.26 106.26 - 105.083	P42x0.4875	1135.642 1167.350 1199.308 1231.517	2395.433 2395.433 2395.433 2395.433	0.474 0.487 0.501 0.514	0.000 0.000 0.000 0.000	2395.433 2395.433 2395.433 2395.433	0.000 0.000 0.000 0.000
L22	105.083 - 104.833 (22)	P42x0.5625	1238.392	2809.308	0.441	0.000	2809.308	0.000
L23	104.833 - 103.528 103.528 - 102.222 102.222 - 100.917	P42x0.5625	1274.483 1310.917 1347.692	2809.308 2809.308 2809.308	0.454 0.467 0.480	0.000 0.000 0.000	2809.308 2809.308 2809.308	0.000 0.000 0.000
L24	100.917 - 100.667 (24)	P48x0.375	1354.775	2321.108	0.584	0.000	2321.108	0.000
L25	100.667 - 99.4585 99.4585 - 98.25 98.25 - 97.0415 97.0415 - 95.833	P48x0.375	1389.167 1423.825 1458.858 1494.192	2321.108 2321.108 2321.108 2321.108	0.598 0.613 0.629 0.644	0.000 0.000 0.000 0.000	2321.108 2321.108 2321.108 2321.108	0.000 0.000 0.000 0.000
L26	95.833 - 95.583 (26)	P48x0.475	1501.525	2999.958	0.501	0.000	2999.958	0.000
L27	95.583 - 94.583 94.583 - 93.583 93.583 - 92.583 92.583 - 91.583 91.583 - 90.583	P48x0.475	1530.983 1560.617 1590.433 1620.433 1650.617	2999.958 2999.958 2999.958 2999.958 2999.958	0.510 0.520 0.530 0.540 0.550	0.000 0.000 0.000 0.000 0.000	2999.958 2999.958 2999.958 2999.958 2999.958	0.000 0.000 0.000 0.000 0.000
L28	90.583 - 89.917 (28)	P48x0.475	1672.008	2999.958	0.557	0.000	2999.958	0.000
L29	89.917 - 89.667 (29)	P48x0.575	1679.708	3702.967	0.454	0.000	3702.967	0.000
L30	89.667 - 88.667 88.667 - 87.667 87.667 - 86.667 86.667 - 85.667 85.667 - 84.667	P48x0.575	1710.633 1741.758 1773.083 1804.608 1836.333	3702.967 3702.967 3702.967 3702.967 3702.967	0.462 0.470 0.479 0.487 0.496	0.000 0.000 0.000 0.000 0.000	3702.967 3702.967 3702.967 3702.967 3702.967	0.000 0.000 0.000 0.000 0.000
L31	84.667 - 83.389 83.389 - 82.111 82.111 - 80.833	P48x0.575	1877.142 1918.283 1959.758	3702.967 3702.967 3702.967	0.507 0.518 0.529	0.000 0.000 0.000	3702.967 3702.967 3702.967	0.000 0.000 0.000

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 74 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Section No.	Elevation ft	Size	M_{ux}	ϕM_{rx}	Ratio	M_{uy}	ϕM_{ry}	Ratio
			kip-ft	kip-ft	$\frac{M_{ux}}{\phi M_{rx}}$	kip-ft	kip-ft	$\frac{M_{uy}}{\phi M_{ry}}$
L32	80.833 - 80.333 (32)	P54x0.55	1976.075	4408.408	0.448	0.000	4408.408	0.000
L33	80.333 - 80.083 (33)	P54x0.4875	1984.267	3864.467	0.513	0.000	3864.467	0.000
L34	80.083 - 79.083	P54x0.4875	2017.142	3864.467	0.522	0.000	3864.467	0.000
	79.083 - 78.083		2050.225	3864.467	0.531	0.000	3864.467	0.000
	78.083 - 77.083		2083.508	3864.467	0.539	0.000	3864.467	0.000
	77.083 - 76.083		2116.992	3864.467	0.548	0.000	3864.467	0.000
	76.083 - 75.083		2150.683	3864.467	0.557	0.000	3864.467	0.000
L35	75.083 - 74.083	P54x0.4875	2184.600	3864.467	0.565	0.000	3864.467	0.000
	74.083 - 73.083		2218.733	3864.467	0.574	0.000	3864.467	0.000
	73.083 - 72.083		2253.067	3864.467	0.583	0.000	3864.467	0.000
	72.083 - 71.083		2287.617	3864.467	0.592	0.000	3864.467	0.000
	71.083 - 70.083		2322.375	3864.467	0.601	0.000	3864.467	0.000
L36	70.083 - 69.5 (36)	P54x0.4875	2342.917	3864.467	0.606	0.000	3864.467	0.000
L37	69.5 - 69.25 (37)	P54x0.5875	2351.800	4739.867	0.496	0.000	4739.867	0.000
L38	69.25 - 68.25	P54x0.5875	2387.492	4739.867	0.504	0.000	4739.867	0.000
	68.25 - 67.25		2423.433	4739.867	0.511	0.000	4739.867	0.000
	67.25 - 66.25		2459.608	4739.867	0.519	0.000	4739.867	0.000
	66.25 - 65.25		2496.025	4739.867	0.527	0.000	4739.867	0.000
	65.25 - 64.25		2532.675	4739.867	0.534	0.000	4739.867	0.000
L39	64.25 - 63.0277	P54x0.5875	2577.792	4739.867	0.544	0.000	4739.867	0.000
	63.0277 - 61.8053		2623.258	4739.867	0.553	0.000	4739.867	0.000
	61.8053 - 60.583		2669.075	4739.867	0.563	0.000	4739.867	0.000
L40	60.583 - 60.333 (40)	P60x0.5125	2678.483	4992.042	0.537	0.000	4992.042	0.000
L41	60.333 - 59.333	P60x0.5125	2716.233	4992.042	0.544	0.000	4992.042	0.000
	59.333 - 58.333		2754.217	4992.042	0.552	0.000	4992.042	0.000
	58.333 - 57.333		2792.425	4992.042	0.559	0.000	4992.042	0.000
	57.333 - 56.333		2830.858	4992.042	0.567	0.000	4992.042	0.000
	56.333 - 55.333		2869.517	4992.042	0.575	0.000	4992.042	0.000
L42	55.333 - 54.2777	P60x0.5125	2910.508	4992.042	0.583	0.000	4992.042	0.000
	54.2777 - 53.2223		2951.708	4992.042	0.591	0.000	4992.042	0.000
	53.2223 - 52.167		2993.117	4992.042	0.600	0.000	4992.042	0.000
L43	52.167 - 51.917 (43)	P60x0.625	3002.950	6198.183	0.484	0.000	6198.183	0.000
L44	51.917 -	P60x0.625	3042.417	6198.183	0.491	0.000	6198.183	0.000

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>75 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhy</p>

Section No.	Elevation ft	Size	M_{ux} kip-ft	ϕM_{rx} kip-ft	Ratio $\frac{M_{ux}}{\phi M_{rx}}$	M_{uy} kip-ft	ϕM_{ry} kip-ft	Ratio $\frac{M_{uy}}{\phi M_{ry}}$
	50.917							
	50.917 - 49.917		3082.067	6198.183	0.497	0.000	6198.183	0.000
	49.917 - 48.917		3121.917	6198.183	0.504	0.000	6198.183	0.000
	48.917 - 47.917		3161.950	6198.183	0.510	0.000	6198.183	0.000
	47.917 - 46.917		3202.183	6198.183	0.517	0.000	6198.183	0.000
L45	46.917 - 45.917	P60x0.625	3242.550	6198.183	0.523	0.000	6198.183	0.000
	45.917 - 44.917		3283.125	6198.183	0.530	0.000	6198.183	0.000
	44.917 - 43.917		3323.900	6198.183	0.536	0.000	6198.183	0.000
	43.917 - 42.917		3364.892	6198.183	0.543	0.000	6198.183	0.000
	42.917 - 41.917		3406.092	6198.183	0.550	0.000	6198.183	0.000
L46	41.917 - 40.333 (46)	P60x0.625	3471.758	6198.183	0.560	0.000	6198.183	0.000
L47	40.333 - 40.083 (47)	P60x0.6	3482.158	5926.841	0.588	0.000	5926.841	0.000
L48	40.083 - 39.083	P60x0.6	3523.900	5926.841	0.595	0.000	5926.841	0.000
	39.083 - 38.083		3565.817	5926.841	0.602	0.000	5926.841	0.000
	38.083 - 37.083		3607.908	5926.841	0.609	0.000	5926.841	0.000
	37.083 - 36.083		3650.183	5926.841	0.616	0.000	5926.841	0.000
	36.083 - 35.083		3692.642	5926.841	0.623	0.000	5926.841	0.000
L49	35.083 - 34.083	P60x0.6	3735.300	5926.841	0.630	0.000	5926.841	0.000
	34.083 - 33.083		3778.117	5926.841	0.637	0.000	5926.841	0.000
	33.083 - 32.083		3821.692	5926.841	0.645	0.000	5926.841	0.000
	32.083 - 31.083		3865.025	5926.841	0.652	0.000	5926.841	0.000
	31.083 - 30.083		3908.517	5926.841	0.659	0.000	5926.841	0.000
L50	30.083 - 29.0415	P60x0.6	3954.000	5926.841	0.667	0.000	5926.841	0.000
	29.0415 - 28		3999.633	5926.841	0.675	0.000	5926.841	0.000
L51	28 - 27.75 (51)	P60x0.725	4010.617	7302.233	0.549	0.000	7302.233	0.000
L52	27.75 - 26.75	P60x0.725	4054.633	7302.233	0.555	0.000	7302.233	0.000
	26.75 - 25.75		4098.825	7302.233	0.561	0.000	7302.233	0.000
	25.75 - 24.75		4143.175	7302.233	0.567	0.000	7302.233	0.000
	24.75 - 23.75		4187.692	7302.233	0.573	0.000	7302.233	0.000
	23.75 - 22.75		4232.375	7302.233	0.580	0.000	7302.233	0.000
L53	22.75 - 21.4165	P60x0.725	4292.208	7302.233	0.588	0.000	7302.233	0.000
	21.4165 - 20.083		4352.317	7302.233	0.596	0.000	7302.233	0.000
L54	20.083 - 19.833 (54)	P60x0.625	4363.625	6198.183	0.704	0.000	6198.183	0.000
L55	19.833 - 18.4165	P60x0.625	4427.833	6198.183	0.714	0.000	6198.183	0.000

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 76 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Section No.	Elevation ft	Size	M_{ux}	ϕM_{rx}	Ratio	M_{uy}	ϕM_{ry}	Ratio
			kip-ft	kip-ft	$\frac{M_{ux}}{\phi M_{rx}}$	kip-ft	kip-ft	$\frac{M_{uy}}{\phi M_{ry}}$
	18.4165 - 17		4492.350	6198.183	0.725	0.000	6198.183	0.000
L56	17 - 16.75 (56)	P60x0.725	4503.767	7302.233	0.617	0.000	7302.233	0.000
L57	16.75 - 15.73	P60x0.75	4550.442	7582.875	0.600	0.000	7582.875	0.000
	15.73 - 14.71		4597.258	7582.875	0.606	0.000	7582.875	0.000
	14.71 - 13.69		4644.233	7582.875	0.612	0.000	7582.875	0.000
	13.69 - 12.67		4691.342	7582.875	0.619	0.000	7582.875	0.000
	12.67 - 11.65		4738.608	7582.875	0.625	0.000	7582.875	0.000
L58	11.65 - 11.417 (58)	P60x0.75	4749.417	7582.875	0.626	0.000	7582.875	0.000
L59	11.417 - 10.4065	P60x0.75	4796.333	7582.875	0.633	0.000	7582.875	0.000
	10.4065 - 9.396		4843.300	7582.875	0.639	0.000	7582.875	0.000
L60	9.396 - 9.146 (60)	P60x0.8	4854.933	8149.650	0.596	0.000	8149.650	0.000
L61	9.146 - 8.06775	P60x0.8	4905.183	8149.650	0.602	0.000	8149.650	0.000
	8.06775 - 6.9895		4955.583	8149.650	0.608	0.000	8149.650	0.000
	6.9895 - 5.91125		5006.133	8149.650	0.614	0.000	8149.650	0.000
	5.91125 - 4.833		5056.842	8149.650	0.620	0.000	8149.650	0.000
L62	4.833 - 4.583 (62)	P60x0.75	5068.617	7582.875	0.668	0.000	7582.875	0.000
L63	4.583 - 3.43725	P60x0.75	5122.692	7582.875	0.676	0.000	7582.875	0.000
	3.43725 - 2.2915		5176.933	7582.875	0.683	0.000	7582.875	0.000
	2.2915 - 1.14575		5231.325	7582.875	0.690	0.000	7582.875	0.000
	1.14575 - 0		5285.883	7582.875	0.697	0.000	7582.875	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual	ϕV_n	Ratio	Actual	ϕT_n	Ratio
			V_u K	K	$\frac{V_u}{\phi V_n}$	T_u kip-ft	kip-ft	$\frac{T_u}{\phi T_n}$
L1	191.667 - 190.667	P18x0.375	0.108	235.463	0.000	0.000	364.865	0.000
	190.667 - 189.667		0.128	235.463	0.001	0.000	364.865	0.000
	189.667 - 188.667		0.148	235.463	0.001	0.000	364.865	0.000
	188.667 - 187.667		0.169	235.463	0.001	0.000	364.865	0.000
	187.667 - 186.667		0.479	235.463	0.002	0.000	364.865	0.000
L2	186.667 - 185.647	P24x0.375	0.545	315.621	0.002	0.000	655.568	0.000
	185.647 - 184.627		0.612	315.621	0.002	0.000	655.568	0.000
	184.627 - 183.607		0.007	315.621	0.000	0.000	655.568	0.000
	183.607 - 182.587		1.574	315.621	0.005	0.000	655.568	0.000

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	77 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhya

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L3	182.587 - 181.567	P24x0.375	1.600	315.621	0.005	0.000	655.568	0.000
	181.567 - 180.567		5.074	315.621	0.016	0.001	655.568	0.000
	180.567 - 179.567		5.139	315.621	0.016	0.001	655.568	0.000
	179.567 - 178.567		5.204	315.621	0.016	0.001	655.568	0.000
	178.567 - 177.567		5.303	315.621	0.017	0.028	655.568	0.000
L4	177.567 - 176.567	P24x0.375	5.392	315.621	0.017	0.714	655.568	0.001
	176.567 - 175.567		5.456	315.621	0.017	0.714	655.568	0.001
	175.567 - 174.567		5.520	315.621	0.017	0.714	655.568	0.001
	174.567 - 173.567		5.584	315.621	0.018	0.714	655.568	0.001
	173.567 - 172.567		5.648	315.621	0.018	0.714	655.568	0.001
L5	172.567 - 171.567	P24x0.375	5.712	315.621	0.018	0.714	655.568	0.001
	171.567 - 170.567		5.775	315.621	0.018	0.714	655.568	0.001
	170.567 - 169.567		5.838	315.621	0.018	0.714	655.568	0.001
	169.567 - 168.567		5.901	315.621	0.019	0.714	655.568	0.001
	168.567 - 167.567		5.964	315.621	0.019	0.714	655.568	0.001
L6	167.567 - 166.567	P24x0.375	6.026	315.621	0.019	0.714	655.568	0.001
	166.567 - 165.567		6.088	315.621	0.019	0.714	655.568	0.001
	165.567 - 164.567		6.150	315.621	0.019	0.714	655.568	0.001
	164.567 - 163.567		6.212	315.621	0.020	0.714	655.568	0.001
	163.567 - 162.567		6.273	315.621	0.020	0.714	655.568	0.001
L7	162.567 - 161.567	P24x0.375	6.334	315.621	0.020	0.714	655.568	0.001
	161.567 - 160.567		6.395	315.621	0.020	0.714	655.568	0.001
	160.567 - 159.567		11.274	315.621	0.036	0.940	655.568	0.001
	159.567 - 158.567		11.333	315.621	0.036	0.940	655.568	0.001
	158.567 - 157.567		11.758	315.621	0.037	0.940	655.568	0.001
L8	157.567 - 156.567	P24x0.375	11.816	315.621	0.037	0.733	655.568	0.001
	156.567 - 155.567		11.873	315.621	0.038	0.733	655.568	0.001
	155.567 - 154.567		11.930	315.621	0.038	0.733	655.568	0.001
	154.567 - 153.567		11.986	315.621	0.038	0.733	655.568	0.001
	153.567 - 152.567		12.064	315.621	0.038	1.585	655.568	0.002

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job
 87581.023.01 - Newington_1, CT (BU# 826217)

Page
 78 of 92

Project
 Date
 13:18:51 07/13/19

Client
 Crown Castle
 Designed by
 Pavan Upadhy

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L9	152.567 - 151.567	P24x0.375	12.119	315.621	0.038	1.585	655.568	0.002
	151.567 - 150.567		17.666	315.621	0.056	1.585	655.568	0.002
	150.567 - 149.567		18.546	315.621	0.059	1.585	655.568	0.002
	149.567 - 148.567		18.595	315.621	0.059	1.513	655.568	0.002
	148.567 - 147.567		18.644	315.621	0.059	1.513	655.568	0.002
	147.567 - 146.567		18.691	315.621	0.059	1.513	655.568	0.002
	146.567 - 145.567		P24x0.375	18.737	315.621	0.059	1.513	655.568
145.567 - 144.567	18.782	315.621		0.060	1.512	655.568	0.002	
144.567 - 143.567	18.825	315.621		0.060	1.512	655.568	0.002	
143.567 - 142.567	18.867	315.621		0.060	1.512	655.568	0.002	
142.567 - 141.567	18.908	315.621		0.060	1.512	655.568	0.002	
141.567 - 141.417 (11)	P36x0.375	18.907		315.621	0.060	1.512	655.568	0.002
141.417 - 140.417		18.989		454.187	0.042	1.512	1094.275	0.001
140.417 - 139.417		19.072	454.187	0.042	1.512	1094.275	0.001	
139.417 - 138.417		19.153	454.187	0.042	1.512	1094.275	0.001	
138.417 - 137.417		19.297	454.187	0.042	1.512	1094.275	0.001	
137.417 - 136.417		19.378	454.187	0.043	1.512	1094.275	0.001	
136.417 - 135.417		P36x0.375	19.457	454.187	0.043	1.511	1094.275	0.001
135.417 - 134.417	19.536		454.187	0.043	1.511	1094.275	0.001	
134.417 - 133.417	19.615		454.187	0.043	1.511	1094.275	0.001	
133.417 - 132.417	19.693		454.187	0.043	1.511	1094.275	0.001	
132.417 - 131.417	20.320		454.187	0.045	3.860	1094.275	0.004	
131.417 - 130.417	P36x0.375		20.397	454.187	0.045	3.860	1094.275	0.004
130.417 - 129.417			20.473	454.187	0.045	3.859	1094.275	0.004
129.417 - 128.417		20.548	454.187	0.045	3.859	1094.275	0.004	
128.417 - 127.417		20.623	454.187	0.045	3.859	1094.275	0.004	
127.417 - 126.417		20.698	454.187	0.046	3.859	1094.275	0.004	
126.417 - 125.417		P36x0.375	20.854	454.187	0.046	3.859	1094.275	0.004
125.417 - 124.417			21.009	454.187	0.046	3.859	1094.275	0.004
124.417 - 123.417	21.342		454.187	0.047	3.859	1094.275	0.004	

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
	123.417 - 122.417		21.496	454.187	0.047	3.858	1094.275	0.004
	122.417 - 121.417		21.649	454.187	0.048	3.858	1094.275	0.004
L16	121.417 - 121.167 (16)	P36x0.375	21.681	454.187	0.048	3.858	1094.275	0.004
L17	121.167 - 120.167	P42x0.375	21.771	421.127	0.052	3.858	1185.508	0.003
	120.167 - 119.167		21.956	421.127	0.052	4.308	1185.508	0.004
	119.167 - 118.167		22.044	421.127	0.052	4.308	1185.508	0.004
	118.167 - 117.167		22.131	421.127	0.053	4.308	1185.508	0.004
	117.167 - 116.167		22.218	421.127	0.053	4.308	1185.508	0.004
L18	116.167 - 115.167	P42x0.375	25.545	421.127	0.061	4.462	1185.508	0.004
	115.167 - 114.167		25.628	421.127	0.061	4.462	1185.508	0.004
	114.167 - 113.167		26.202	421.127	0.062	4.462	1185.508	0.004
	113.167 - 112.167		26.283	421.127	0.062	4.462	1185.508	0.004
	112.167 - 111.167		26.363	421.127	0.063	4.462	1185.508	0.004
L19	111.167 - 110.042 (19)	P42x0.375	26.453	421.127	0.063	4.462	1185.508	0.004
L20	110.042 - 109.792 (20)	P42x0.4875	26.468	720.969	0.037	4.462	2272.017	0.002
L21	109.792 - 108.615	P42x0.4875	26.823	720.969	0.037	2.749	2272.017	0.001
	108.615 - 107.438		27.037	720.969	0.038	2.749	2272.017	0.001
	107.438 - 106.26		27.250	720.969	0.038	2.749	2272.017	0.001
	106.26 - 105.083		27.462	720.969	0.038	2.749	2272.017	0.001
L22	105.083 - 104.833 (22)	P42x0.5625	27.508	830.384	0.033	2.749	3025.183	0.001
L23	104.833 - 103.528	P42x0.5625	27.774	830.384	0.033	2.749	3025.183	0.001
	103.528 - 102.222		28.036	830.384	0.034	2.748	3025.183	0.001
	102.222 - 100.917		28.296	830.384	0.034	2.748	3025.183	0.001
L24	100.917 - 100.667 (24)	P48x0.375	28.339	394.372	0.072	2.748	1270.217	0.002
L25	100.667 - 99.4585	P48x0.375	28.566	394.372	0.072	2.748	1270.217	0.002
	99.4585 - 98.25		28.787	394.372	0.073	2.748	1270.217	0.002
	98.25 - 97.0415		29.120	394.372	0.074	2.748	1270.217	0.002
	97.0415 - 95.833		29.340	394.372	0.074	2.748	1270.217	0.002
L26	95.833 - 95.583 (26)	P48x0.475	29.356	710.639	0.041	2.748	2284.058	0.001
L27	95.583 - 94.583	P48x0.475	29.541	710.639	0.042	2.748	2284.058	0.001

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 80 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
	94.583 - 93.583		29.722	710.639	0.042	2.748	2284.058	0.001
	93.583 - 92.583		29.903	710.639	0.042	2.748	2284.058	0.001
	92.583 - 91.583		30.084	710.639	0.042	2.748	2284.058	0.001
	91.583 - 90.583		30.263	710.639	0.043	2.748	2284.058	0.001
L28	90.583 - 89.917 (28)	P48x0.475	30.789	710.639	0.043	3.030	2284.058	0.001
L29	89.917 - 89.667 (29)	P48x0.575	30.837	971.490	0.032	3.030	3667.025	0.001
L30	89.667 - 88.667	P48x0.575	31.040	971.490	0.032	3.030	3667.025	0.001
	88.667 - 87.667		31.241	971.490	0.032	3.029	3667.025	0.001
	87.667 - 86.667		31.441	971.490	0.032	3.029	3667.025	0.001
	86.667 - 85.667		31.640	971.490	0.033	3.029	3667.025	0.001
	85.667 - 84.667		31.839	971.490	0.033	3.029	3667.025	0.001
L31	84.667 - 83.389	P48x0.575	32.104	971.490	0.033	3.029	3667.025	0.001
	83.389 - 82.111		32.366	971.490	0.033	3.029	3667.025	0.001
	82.111 - 80.833		32.627	971.490	0.034	3.029	3667.025	0.001
L32	80.833 - 80.333 (32)	P54x0.55	32.724	966.315	0.034	3.029	3493.033	0.001
L33	80.333 - 80.083 (33)	P54x0.4875	32.777	729.657	0.045	3.029	2639.000	0.001
L34	80.083 - 79.083	P54x0.4875	32.984	729.657	0.045	3.029	2639.000	0.001
	79.083 - 78.083		33.188	729.657	0.045	3.029	2639.000	0.001
	78.083 - 77.083		33.391	729.657	0.046	3.029	2639.000	0.001
	77.083 - 76.083		33.593	729.657	0.046	3.029	2639.000	0.001
	76.083 - 75.083		33.794	729.657	0.046	3.029	2639.000	0.001
L35	75.083 - 74.083	P54x0.4875	34.006	729.657	0.047	3.029	2639.000	0.001
	74.083 - 73.083		34.216	729.657	0.047	3.029	2639.000	0.001
	73.083 - 72.083		34.426	729.657	0.047	3.029	2639.000	0.001
	72.083 - 71.083		34.635	729.657	0.047	3.029	2639.000	0.001
	71.083 - 70.083		34.844	729.657	0.048	3.029	2639.000	0.001
L36	70.083 - 69.5 (36)	P54x0.4875	35.450	729.657	0.049	3.029	2639.000	0.001
L37	69.5 - 69.25 (37)	P54x0.5875	35.505	1117.930	0.032	1.187	4113.450	0.000
L38	69.25 - 68.25	P54x0.5875	35.751	1117.930	0.032	1.187	4113.450	0.000
	68.25 - 67.25		35.990	1117.930	0.032	1.187	4113.450	0.000
	67.25 - 66.25		36.229	1117.930	0.032	1.187	4113.450	0.000
	66.25 - 65.25		36.466	1117.930	0.033	1.187	4113.450	0.000

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	81 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhy

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L39	65.25 - 64.25	P54x0.5875	36.702	1117.930	0.033	1.187	4113.450	0.000
	64.25 - 63.0277		36.994	1117.930	0.033	1.187	4113.450	0.000
	63.0277 - 61.8053		37.282	1117.930	0.033	1.187	4113.450	0.000
	61.8053 - 60.583		37.569	1117.930	0.034	1.187	4113.450	0.000
L40	60.583 - 60.333 (40)	P60x0.5125	37.613	838.764	0.045	1.187	3372.333	0.000
	L41		60.333 - 59.333	37.846	838.764	0.045	1.187	3372.333
59.333 - 58.333		38.072	838.764	0.045	1.187	3372.333	0.000	
58.333 - 57.333		38.297	838.764	0.046	1.187	3372.333	0.000	
57.333 - 56.333		38.521	838.764	0.046	1.187	3372.333	0.000	
56.333 - 55.333		38.744	838.764	0.046	1.187	3372.333	0.000	
55.333 - 54.2777		38.939	838.764	0.046	1.187	3372.333	0.000	
L42	54.2777 - 53.2223	P60x0.5125	39.132	838.764	0.047	1.187	3372.333	0.000
	53.2223 - 52.167		39.324	838.764	0.047	1.187	3372.333	0.000
L43	52.167 - 51.917 (43)	P60x0.625	39.361	1308.390	0.030	1.187	5250.550	0.000
L44	51.917 - 50.917	P60x0.625	39.560	1308.390	0.030	1.187	5250.550	0.000
	50.917 - 49.917		39.753	1308.390	0.030	1.187	5250.550	0.000
	49.917 - 48.917		39.945	1308.390	0.031	1.187	5250.550	0.000
	48.917 - 47.917		40.136	1308.390	0.031	1.187	5250.550	0.000
	47.917 - 46.917		40.327	1308.390	0.031	1.187	5250.550	0.000
	46.917 - 45.917		40.537	1308.390	0.031	1.187	5250.550	0.000
L45	45.917 - 44.917	P60x0.625	40.746	1308.390	0.031	1.187	5250.550	0.000
	44.917 - 43.917		40.955	1308.390	0.031	1.187	5250.550	0.000
	43.917 - 42.917		41.162	1308.390	0.031	1.187	5250.550	0.000
	42.917 - 41.917		41.369	1308.390	0.032	1.187	5250.550	0.000
L46	41.917 - 40.333 (46)	P60x0.625	41.688	1308.390	0.032	1.187	5250.550	0.000
L47	40.333 - 40.083 (47)	P60x0.6	41.717	1194.070	0.035	1.187	4793.808	0.000
L48	40.083 - 39.083	P60x0.6	41.908	1194.070	0.035	1.187	4793.808	0.000
	39.083 - 38.083		42.088	1194.070	0.035	1.187	4793.808	0.000
	38.083 - 37.083		42.268	1194.070	0.035	1.187	4793.808	0.000
	37.083 - 36.083		42.446	1194.070	0.036	1.187	4793.808	0.000
	36.083 - 35.083		42.624	1194.070	0.036	1.187	4793.808	0.000
	35.083 - 34.083		42.802	1194.070	0.036	1.187	4793.808	0.000

<p>tnxTower</p> <p>B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:</p>	<p>Job</p> <p>87581.023.01 - Newington_1, CT (BU# 826217)</p>	<p>Page</p> <p>82 of 92</p>
	<p>Project</p>	<p>Date</p> <p>13:18:51 07/13/19</p>
	<p>Client</p> <p>Crown Castle</p>	<p>Designed by</p> <p>Pavan Upadhy</p>

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
L49	35.083 35.083 - 34.083 34.083 - 33.083 33.083 - 32.083 32.083 - 31.083 31.083 - 30.083	P60x0.6	42.776 42.927 43.300 43.450 43.598	1194.070 1194.070 1194.070 1194.070 1194.070	0.036 0.036 0.036 0.036 0.037	1.187 1.187 1.553 1.553 1.553	4793.808 4793.808 4793.808 4793.808 4793.808	0.000 0.000 0.000 0.000 0.000
L50	30.083 - 29.0415	P60x0.6	43.747	1194.070	0.037	1.553	4793.808	0.000
L51	29.0415 - 28	P60x0.725	43.894	1194.070	0.037	1.553	4793.808	0.000
L52	28 - 27.75 (51) 27.75 - 26.75 26.75 - 25.75 25.75 - 24.75 24.75 - 23.75 23.75 - 22.75	P60x0.725	43.917 44.094 44.258 44.423 44.586 44.748	1530.990 1530.990 1530.990 1530.990 1530.990 1530.990	0.029 0.029 0.029 0.029 0.029 0.029	1.553 1.553 1.553 1.553 1.553 1.553	7317.325 7317.325 7317.325 7317.325 7317.325 7317.325	0.000 0.000 0.000 0.000 0.000 0.000
L53	22.75 - 21.4165 21.4165 - 20.083	P60x0.725	44.968 45.181	1530.990 1530.990	0.029 0.030	1.553 1.553	7317.325 7317.325	0.000 0.000
L54	20.083 - 19.833 (54)	P60x0.625	45.200	1308.390	0.035	1.553	5250.550	0.000
L55	19.833 - 18.4165 18.4165 - 17	P60x0.625	45.439 45.652	1308.390 1308.390	0.035 0.035	1.553 1.553	5250.550 5250.550	0.000 0.000
L56	17 - 16.75 (56)	P60x0.725	45.663	1530.990	0.030	1.553	7317.325	0.000
L57	16.75 - 15.73 15.73 - 14.71 14.71 - 13.69 13.69 - 12.67 12.67 - 11.65	P60x0.75	45.823 45.969 46.114 46.257 46.400	1583.120 1583.120 1583.120 1583.120 1583.120	0.029 0.029 0.029 0.029 0.029	1.553 1.553 1.553 1.553 1.553	7957.825 7957.825 7957.825 7957.825 7957.825	0.000 0.000 0.000 0.000 0.000
L58	11.65 - 11.417 (58)	P60x0.75	46.395	1583.120	0.029	1.553	7957.825	0.000
L59	11.417 - 10.4065 10.4065 - 9.396	P60x0.75	46.458 46.504	1583.120 1583.120	0.029 0.029	1.553 1.553	7957.825 7957.825	0.000 0.000
L60	9.396 - 9.146 (60)	P60x0.8	46.521	1687.230	0.028	1.553	8781.667	0.000
L61	9.146 - 8.06775 8.06775 - 6.9895 6.9895 - 5.91125 5.91125 - 4.833	P60x0.8	46.679 46.820 46.960 47.099	1687.230 1687.230 1687.230 1687.230	0.028 0.028 0.028 0.028	1.553 1.553 1.553 1.553	8781.667 8781.667 8781.667 8781.667	0.000 0.000 0.000 0.000
L62	4.833 - 4.583 (62)	P60x0.75	47.114	1583.120	0.030	1.552	7957.825	0.000
L63	4.583 - 3.43725 3.43725 - 2.2915 2.2915 - 1.14575 1.14575 - 0	P60x0.75	47.276 47.418 47.559 47.698	1583.120 1583.120 1583.120 1583.120	0.030 0.030 0.030 0.030	1.552 1.552 1.552 1.552	7957.825 7957.825 7957.825 7957.825	0.000 0.000 0.000 0.000

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 83 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Section No.	Elevation ft	Size	Actual V_u K	ϕV_n K	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u kip-ft	ϕT_n kip-ft	Ratio $\frac{T_u}{\phi T_n}$
-------------	-----------------	------	----------------------	-----------------	---------------------------------	---------------------------	----------------------	---------------------------------

Pole Interaction Design Data

Section No.	Elevation ft	Ratio P_u ϕP_n	Ratio M_{ux} ϕM_{rx}	Ratio M_{uy} ϕM_{ry}	Ratio V_u ϕV_n	Ratio T_u ϕT_n	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	191.667 - 190.667	0.001	0.003	0.000	0.000	0.000	0.004	1.050	4.8.2 ✓
	190.667 - 189.667	0.001	0.004	0.000	0.001	0.000	0.005	1.050	4.8.2 ✓
	189.667 - 188.667	0.001	0.004	0.000	0.001	0.000	0.005	1.050	4.8.2 ✓
	188.667 - 187.667	0.001	0.004	0.000	0.001	0.000	0.006	1.050	4.8.2 ✓
	187.667 - 186.667	0.001	0.006	0.000	0.002	0.000	0.007	1.050	4.8.2 ✓
L2	186.667 - 185.647	0.001	0.004	0.000	0.002	0.000	0.005	1.050	4.8.2 ✓
	185.647 - 184.627	0.001	0.005	0.000	0.002	0.000	0.006	1.050	4.8.2 ✓
	184.627 - 183.607	0.011	0.004	0.000	0.000	0.000	0.015*	1.000	4.8.2 ✓
	183.607 - 182.587	0.011	0.006	0.000	0.005	0.000	0.017	1.050	4.8.2 ✓
	182.587 - 181.567	0.011	0.009	0.000	0.005	0.000	0.020	1.050	4.8.2 ✓
L3	181.567 - 180.567	0.005	0.020	0.000	0.016	0.000	0.025	1.050	4.8.2 ✓
	180.567 - 179.567	0.005	0.028	0.000	0.016	0.000	0.033	1.050	4.8.2 ✓
	179.567 - 178.567	0.005	0.036	0.000	0.016	0.000	0.042	1.050	4.8.2 ✓
	178.567 - 177.567	0.005	0.045	0.000	0.017	0.000	0.050	1.050	4.8.2 ✓
	177.567 - 176.567	0.005	0.053	0.000	0.017	0.001	0.059	1.050	4.8.2 ✓
L4	176.567 - 175.567	0.006	0.062	0.000	0.017	0.001	0.068	1.050	4.8.2 ✓
	175.567 - 174.567	0.006	0.071	0.000	0.017	0.001	0.077	1.050	4.8.2 ✓
	174.567 - 173.567	0.006	0.080	0.000	0.018	0.001	0.086	1.050	4.8.2 ✓
	173.567 - 172.567	0.006	0.089	0.000	0.018	0.001	0.095	1.050	4.8.2 ✓
	172.567 - 171.567	0.006	0.098	0.000	0.018	0.001	0.104	1.050	4.8.2 ✓
L5	171.567 - 170.567	0.006	0.107	0.000	0.018	0.001	0.114	1.050	4.8.2 ✓

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job
 87581.023.01 - Newington_1, CT (BU# 826217)

Page
 84 of 92

Project
 Date
 13:18:51 07/13/19

Client
 Crown Castle
 Designed by
 Pavan Upadhy

Section No.	Elevation ft	Ratio	Ratio	Ratio	Ratio	Ratio	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
		P_u	M_{ux}	M_{uy}	V_u	T_u			
	170.567 - 169.567	0.006	0.116	0.000	0.018	0.001	0.123	1.050	4.8.2 ✓
	169.567 - 168.567	0.007	0.126	0.000	0.019	0.001	0.133	1.050	4.8.2 ✓
	168.567 - 167.567	0.007	0.135	0.000	0.019	0.001	0.142	1.050	4.8.2 ✓
	167.567 - 166.567	0.007	0.145	0.000	0.019	0.001	0.152	1.050	4.8.2 ✓
L6	166.567 - 165.567	0.007	0.155	0.000	0.019	0.001	0.162	1.050	4.8.2 ✓
	165.567 - 164.567	0.007	0.164	0.000	0.019	0.001	0.172	1.050	4.8.2 ✓
	164.567 - 163.567	0.007	0.174	0.000	0.020	0.001	0.182	1.050	4.8.2 ✓
	163.567 - 162.567	0.007	0.184	0.000	0.020	0.001	0.192	1.050	4.8.2 ✓
	162.567 - 161.567	0.007	0.194	0.000	0.020	0.001	0.202	1.050	4.8.2 ✓
L7	161.567 - 160.567	0.008	0.205	0.000	0.020	0.001	0.213	1.050	4.8.2 ✓
	160.567 - 159.567	0.011	0.218	0.000	0.036	0.001	0.230	1.050	4.8.2 ✓
	159.567 - 158.567	0.011	0.236	0.000	0.036	0.001	0.249	1.050	4.8.2 ✓
	158.567 - 157.567	0.012	0.255	0.000	0.037	0.001	0.268	1.050	4.8.2 ✓
	157.567 - 156.567	0.012	0.274	0.000	0.037	0.001	0.287	1.050	4.8.2 ✓
L8	156.567 - 155.567	0.012	0.293	0.000	0.038	0.001	0.307	1.050	4.8.2 ✓
	155.567 - 154.567	0.012	0.312	0.000	0.038	0.001	0.326	1.050	4.8.2 ✓
	154.567 - 153.567	0.012	0.331	0.000	0.038	0.001	0.345	1.050	4.8.2 ✓
	153.567 - 152.567	0.012	0.351	0.000	0.038	0.002	0.365	1.050	4.8.2 ✓
	152.567 - 151.567	0.012	0.370	0.000	0.038	0.002	0.384	1.050	4.8.2 ✓
L9	151.567 - 150.567	0.017	0.393	0.000	0.056	0.002	0.413	1.050	4.8.2 ✓
	150.567 - 149.567	0.018	0.423	0.000	0.059	0.002	0.444	1.050	4.8.2 ✓
	149.567 - 148.567	0.018	0.453	0.000	0.059	0.002	0.474	1.050	4.8.2 ✓
	148.567 - 147.567	0.018	0.483	0.000	0.059	0.002	0.504	1.050	4.8.2 ✓
	147.567 - 146.567	0.018	0.512	0.000	0.059	0.002	0.534	1.050	4.8.2 ✓
L10	146.567 - 145.567	0.018	0.542	0.000	0.059	0.002	0.564	1.050	4.8.2 ✓
	145.567 - 144.567	0.018	0.573	0.000	0.060	0.002	0.595	1.050	4.8.2 ✓

Section No.	Elevation ft	Ratio P_u ϕP_n	Ratio M_{ux} ϕM_{nx}	Ratio M_{uy} ϕM_{ny}	Ratio V_u ϕV_n	Ratio T_u ϕT_n	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
	144.567 - 143.567	0.018	0.603	0.000	0.060	0.002	0.625	1.050	4.8.2 ✓
	143.567 - 142.567	0.019	0.633	0.000	0.060	0.002	0.655	1.050	4.8.2 ✓
	142.567 - 141.567	0.019	0.663	0.000	0.060	0.002	0.686	1.050	4.8.2 ✓
L11	141.567 - 141.417 (11)	0.019	0.668	0.000	0.060	0.002	0.690	1.050	4.8.2 ✓
L12	141.417 - 140.417	0.013	0.325	0.000	0.042	0.001	0.341	1.050	4.8.2 ✓
	140.417 - 139.417	0.014	0.339	0.000	0.042	0.001	0.355	1.050	4.8.2 ✓
	139.417 - 138.417	0.014	0.354	0.000	0.042	0.001	0.369	1.050	4.8.2 ✓
	138.417 - 137.417	0.014	0.368	0.000	0.042	0.001	0.384	1.050	4.8.2 ✓
	137.417 - 136.417	0.014	0.382	0.000	0.043	0.001	0.398	1.050	4.8.2 ✓
L13	136.417 - 135.417	0.014	0.397	0.000	0.043	0.001	0.413	1.050	4.8.2 ✓
	135.417 - 134.417	0.014	0.412	0.000	0.043	0.001	0.428	1.050	4.8.2 ✓
	134.417 - 133.417	0.015	0.426	0.000	0.043	0.001	0.443	1.050	4.8.2 ✓
	133.417 - 132.417	0.015	0.441	0.000	0.043	0.001	0.458	1.050	4.8.2 ✓
	132.417 - 131.417	0.015	0.456	0.000	0.045	0.004	0.474	1.050	4.8.2 ✓
L14	131.417 - 130.417	0.015	0.471	0.000	0.045	0.004	0.489	1.050	4.8.2 ✓
	130.417 - 129.417	0.015	0.487	0.000	0.045	0.004	0.505	1.050	4.8.2 ✓
	129.417 - 128.417	0.016	0.502	0.000	0.045	0.004	0.520	1.050	4.8.2 ✓
	128.417 - 127.417	0.016	0.517	0.000	0.045	0.004	0.536	1.050	4.8.2 ✓
	127.417 - 126.417	0.016	0.533	0.000	0.046	0.004	0.551	1.050	4.8.2 ✓
L15	126.417 - 125.417	0.016	0.548	0.000	0.046	0.004	0.567	1.050	4.8.2 ✓
	125.417 - 124.417	0.016	0.564	0.000	0.046	0.004	0.583	1.050	4.8.2 ✓
	124.417 - 123.417	0.017	0.580	0.000	0.047	0.004	0.599	1.050	4.8.2 ✓
	123.417 - 122.417	0.017	0.596	0.000	0.047	0.004	0.616	1.050	4.8.2 ✓
	122.417 - 121.417	0.017	0.612	0.000	0.048	0.004	0.632	1.050	4.8.2 ✓
L16	121.417 - 121.167 (16)	0.017	0.616	0.000	0.048	0.004	0.636	1.050	4.8.2 ✓
L17	121.167 - 120.167	0.016	0.471	0.000	0.052	0.003	0.490	1.050	4.8.2 ✓

tnxTower

B+T Group
 1717 S, Boulder, Suite 300
 Tulsa, OK 74119
 Phone: (918) 587-4630
 FAX:

Job
 87581.023.01 - Newington_1, CT (BU# 826217)

Page
 86 of 92

Project
 Date
 13:18:51 07/13/19

Client
 Crown Castle
 Designed by
 Pavan Upadhy

Section No.	Elevation ft	Ratio P_u ϕP_n	Ratio M_{ux} ϕM_{nx}	Ratio M_{uy} ϕM_{ny}	Ratio V_u ϕV_n	Ratio T_u ϕT_n	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
	120.167 - 119.167	0.016	0.483	0.000	0.052	0.004	0.502	1.050	4.8.2 ✓
	119.167 - 118.167	0.016	0.496	0.000	0.052	0.004	0.515	1.050	4.8.2 ✓
	118.167 - 117.167	0.016	0.508	0.000	0.053	0.004	0.527	1.050	4.8.2 ✓
	117.167 - 116.167	0.016	0.520	0.000	0.053	0.004	0.540	1.050	4.8.2 ✓
L18	116.167 - 115.167	0.019	0.536	0.000	0.061	0.004	0.559	1.050	4.8.2 ✓
	115.167 - 114.167	0.019	0.551	0.000	0.061	0.004	0.574	1.050	4.8.2 ✓
	114.167 - 113.167	0.019	0.565	0.000	0.062	0.004	0.589	1.050	4.8.2 ✓
	113.167 - 112.167	0.019	0.580	0.000	0.062	0.004	0.604	1.050	4.8.2 ✓
	112.167 - 111.167	0.020	0.594	0.000	0.063	0.004	0.618	1.050	4.8.2 ✓
L19	111.167 - 110.042 (19)	0.020	0.611	0.000	0.063	0.004	0.635	1.050	4.8.2 ✓
L20	110.042 - 109.792 (20)	0.014	0.461	0.000	0.037	0.002	0.477	1.050	4.8.2 ✓
L21	109.792 - 108.615	0.014	0.474	0.000	0.037	0.001	0.490	1.050	4.8.2 ✓
	108.615 - 107.438	0.015	0.487	0.000	0.038	0.001	0.503	1.050	4.8.2 ✓
	107.438 - 106.26	0.015	0.501	0.000	0.038	0.001	0.517	1.050	4.8.2 ✓
	106.26 - 105.083	0.015	0.514	0.000	0.038	0.001	0.531	1.050	4.8.2 ✓
L22	105.083 - 104.833 (22)	0.013	0.441	0.000	0.033	0.001	0.455	1.050	4.8.2 ✓
L23	104.833 - 103.528	0.013	0.454	0.000	0.033	0.001	0.468	1.050	4.8.2 ✓
	103.528 - 102.222	0.013	0.467	0.000	0.034	0.001	0.481	1.050	4.8.2 ✓
	102.222 - 100.917	0.013	0.480	0.000	0.034	0.001	0.494	1.050	4.8.2 ✓
L24	100.917 - 100.667 (24)	0.020	0.584	0.000	0.072	0.002	0.609	1.050	4.8.2 ✓
L25	100.667 - 99.4585	0.020	0.598	0.000	0.072	0.002	0.625	1.050	4.8.2 ✓
	99.4585 - 98.25	0.021	0.613	0.000	0.073	0.002	0.640	1.050	4.8.2 ✓
	98.25 - 97.0415	0.021	0.629	0.000	0.074	0.002	0.655	1.050	4.8.2 ✓
	97.0415 - 95.833	0.021	0.644	0.000	0.074	0.002	0.671	1.050	4.8.2 ✓
L26	95.833 - 95.583 (26)	0.016	0.501	0.000	0.041	0.001	0.518	1.050	4.8.2 ✓
L27	95.583 - 94.583	0.016	0.510	0.000	0.042	0.001	0.528	1.050	4.8.2 ✓

Job	87581.023.01 - Newington_1, CT (BU# 826217)	Page	87 of 92
Project		Date	13:18:51 07/13/19
Client	Crown Castle	Designed by	Pavan Upadhy

Section No.	Elevation ft	Ratio P_u ϕP_n	Ratio M_{ux} ϕM_{nx}	Ratio M_{uy} ϕM_{ny}	Ratio V_u ϕV_n	Ratio T_u ϕT_n	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
	94.583 - 93.583	0.016	0.520	0.000	0.042	0.001	0.538	1.050	4.8.2 ✓
	93.583 - 92.583	0.016	0.530	0.000	0.042	0.001	0.548	1.050	4.8.2 ✓
	92.583 - 91.583	0.016	0.540	0.000	0.042	0.001	0.558	1.050	4.8.2 ✓
	91.583 - 90.583	0.017	0.550	0.000	0.043	0.001	0.569	1.050	4.8.2 ✓
L28	90.583 - 89.917 (28)	0.017	0.557	0.000	0.043	0.001	0.576	1.050	4.8.2 ✓
L29	89.917 - 89.667 (29)	0.013	0.454	0.000	0.032	0.001	0.468	1.050	4.8.2 ✓
L30	89.667 - 88.667	0.013	0.462	0.000	0.032	0.001	0.476	1.050	4.8.2 ✓
	88.667 - 87.667	0.014	0.470	0.000	0.032	0.001	0.485	1.050	4.8.2 ✓
	87.667 - 86.667	0.014	0.479	0.000	0.032	0.001	0.494	1.050	4.8.2 ✓
	86.667 - 85.667	0.014	0.487	0.000	0.033	0.001	0.502	1.050	4.8.2 ✓
	85.667 - 84.667	0.014	0.496	0.000	0.033	0.001	0.511	1.050	4.8.2 ✓
L31	84.667 - 83.389	0.014	0.507	0.000	0.033	0.001	0.523	1.050	4.8.2 ✓
	83.389 - 82.111	0.015	0.518	0.000	0.033	0.001	0.534	1.050	4.8.2 ✓
	82.111 - 80.833	0.015	0.529	0.000	0.034	0.001	0.546	1.050	4.8.2 ✓
L32	80.833 - 80.333 (32)	0.015	0.448	0.000	0.034	0.001	0.464	1.050	4.8.2 ✓
L33	80.333 - 80.083 (33)	0.017	0.513	0.000	0.045	0.001	0.533	1.050	4.8.2 ✓
L34	80.083 - 79.083	0.018	0.522	0.000	0.045	0.001	0.542	1.050	4.8.2 ✓
	79.083 - 78.083	0.018	0.531	0.000	0.045	0.001	0.550	1.050	4.8.2 ✓
	78.083 - 77.083	0.018	0.539	0.000	0.046	0.001	0.559	1.050	4.8.2 ✓
	77.083 - 76.083	0.018	0.548	0.000	0.046	0.001	0.568	1.050	4.8.2 ✓
	76.083 - 75.083	0.018	0.557	0.000	0.046	0.001	0.577	1.050	4.8.2 ✓
L35	75.083 - 74.083	0.018	0.565	0.000	0.047	0.001	0.586	1.050	4.8.2 ✓
	74.083 - 73.083	0.019	0.574	0.000	0.047	0.001	0.595	1.050	4.8.2 ✓
	73.083 - 72.083	0.019	0.583	0.000	0.047	0.001	0.604	1.050	4.8.2 ✓
	72.083 - 71.083	0.019	0.592	0.000	0.047	0.001	0.613	1.050	4.8.2 ✓
	71.083 - 70.083	0.019	0.601	0.000	0.048	0.001	0.623	1.050	4.8.2 ✓

Section No.	Elevation ft	Ratio P_u ϕP_n	Ratio M_{ux} ϕM_{nx}	Ratio M_{uy} ϕM_{ny}	Ratio V_u ϕV_n	Ratio T_u ϕT_n	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L36	70.083 - 69.5 (36)	0.020	0.606	0.000	0.049	0.001	0.628	1.050	4.8.2 ✓
L37	69.5 - 69.25 (37)	0.015	0.496	0.000	0.032	0.000	0.513	1.050	4.8.2 ✓
L38	69.25 - 68.25	0.016	0.504	0.000	0.032	0.000	0.521	1.050	4.8.2 ✓
	68.25 - 67.25	0.016	0.511	0.000	0.032	0.000	0.529	1.050	4.8.2 ✓
	67.25 - 66.25	0.017	0.519	0.000	0.032	0.000	0.537	1.050	4.8.2 ✓
	66.25 - 65.25	0.017	0.527	0.000	0.033	0.000	0.545	1.050	4.8.2 ✓
	65.25 - 64.25	0.017	0.534	0.000	0.033	0.000	0.553	1.050	4.8.2 ✓
L39	64.25 - 63.0277	0.018	0.544	0.000	0.033	0.000	0.563	1.050	4.8.2 ✓
	63.0277 - 61.8053	0.018	0.553	0.000	0.033	0.000	0.573	1.050	4.8.2 ✓
	61.8053 - 60.583	0.019	0.563	0.000	0.034	0.000	0.583	1.050	4.8.2 ✓
L40	60.583 - 60.333 (40)	0.021	0.537	0.000	0.045	0.000	0.559	1.050	4.8.2 ✓
L41	60.333 - 59.333	0.021	0.544	0.000	0.045	0.000	0.567	1.050	4.8.2 ✓
	59.333 - 58.333	0.021	0.552	0.000	0.045	0.000	0.575	1.050	4.8.2 ✓
	58.333 - 57.333	0.021	0.559	0.000	0.046	0.000	0.583	1.050	4.8.2 ✓
	57.333 - 56.333	0.022	0.567	0.000	0.046	0.000	0.591	1.050	4.8.2 ✓
	56.333 - 55.333	0.022	0.575	0.000	0.046	0.000	0.599	1.050	4.8.2 ✓
L42	55.333 - 54.2777	0.022	0.583	0.000	0.046	0.000	0.607	1.050	4.8.2 ✓
	54.2777 - 53.2223	0.022	0.591	0.000	0.047	0.000	0.616	1.050	4.8.2 ✓
	53.2223 - 52.167	0.022	0.600	0.000	0.047	0.000	0.624	1.050	4.8.2 ✓
L43	52.167 - 51.917 (43)	0.017	0.484	0.000	0.030	0.000	0.503	1.050	4.8.2 ✓
L44	51.917 - 50.917	0.018	0.491	0.000	0.030	0.000	0.509	1.050	4.8.2 ✓
	50.917 - 49.917	0.018	0.497	0.000	0.030	0.000	0.516	1.050	4.8.2 ✓
	49.917 - 48.917	0.018	0.504	0.000	0.031	0.000	0.522	1.050	4.8.2 ✓
	48.917 - 47.917	0.018	0.510	0.000	0.031	0.000	0.529	1.050	4.8.2 ✓
	47.917 - 46.917	0.018	0.517	0.000	0.031	0.000	0.536	1.050	4.8.2 ✓
L45	46.917 - 45.917	0.018	0.523	0.000	0.031	0.000	0.542	1.050	4.8.2 ✓

Section No.	Elevation ft	Ratio P_u	Ratio M_{ux}	Ratio M_{uy}	Ratio V_u	Ratio T_u	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
		ϕP_n	ϕM_{nx}	ϕM_{ny}	ϕV_n	ϕT_n			
	45.917 - 44.917	0.019	0.530	0.000	0.031	0.000	0.549	1.050	4.8.2 ✓
	44.917 - 43.917	0.019	0.536	0.000	0.031	0.000	0.556	1.050	4.8.2 ✓
	43.917 - 42.917	0.019	0.543	0.000	0.031	0.000	0.563	1.050	4.8.2 ✓
	42.917 - 41.917	0.019	0.550	0.000	0.032	0.000	0.570	1.050	4.8.2 ✓
L46	41.917 - 40.333 (46)	0.019	0.560	0.000	0.032	0.000	0.581	1.050	4.8.2 ✓
L47	40.333 - 40.083 (47)	0.020	0.588	0.000	0.035	0.000	0.609	1.050	4.8.2 ✓
L48	40.083 - 39.083	0.021	0.595	0.000	0.035	0.000	0.616	1.050	4.8.2 ✓
	39.083 - 38.083	0.021	0.602	0.000	0.035	0.000	0.624	1.050	4.8.2 ✓
	38.083 - 37.083	0.021	0.609	0.000	0.035	0.000	0.631	1.050	4.8.2 ✓
	37.083 - 36.083	0.021	0.616	0.000	0.036	0.000	0.638	1.050	4.8.2 ✓
	36.083 - 35.083	0.021	0.623	0.000	0.036	0.000	0.646	1.050	4.8.2 ✓
L49	35.083 - 34.083	0.022	0.630	0.000	0.036	0.000	0.653	1.050	4.8.2 ✓
	34.083 - 33.083	0.022	0.637	0.000	0.036	0.000	0.661	1.050	4.8.2 ✓
	33.083 - 32.083	0.022	0.645	0.000	0.036	0.000	0.668	1.050	4.8.2 ✓
	32.083 - 31.083	0.022	0.652	0.000	0.036	0.000	0.676	1.050	4.8.2 ✓
	31.083 - 30.083	0.022	0.659	0.000	0.037	0.000	0.683	1.050	4.8.2 ✓
L50	30.083 - 29.0415	0.022	0.667	0.000	0.037	0.000	0.691	1.050	4.8.2 ✓
	29.0415 - 28	0.023	0.675	0.000	0.037	0.000	0.699	1.050	4.8.2 ✓
L51	28 - 27.75 (51)	0.018	0.549	0.000	0.029	0.000	0.568	1.050	4.8.2 ✓
L52	27.75 - 26.75	0.018	0.555	0.000	0.029	0.000	0.574	1.050	4.8.2 ✓
	26.75 - 25.75	0.018	0.561	0.000	0.029	0.000	0.580	1.050	4.8.2 ✓
	25.75 - 24.75	0.018	0.567	0.000	0.029	0.000	0.586	1.050	4.8.2 ✓
	24.75 - 23.75	0.018	0.573	0.000	0.029	0.000	0.593	1.050	4.8.2 ✓
	23.75 - 22.75	0.019	0.580	0.000	0.029	0.000	0.599	1.050	4.8.2 ✓
L53	22.75 - 21.4165	0.019	0.588	0.000	0.029	0.000	0.607	1.050	4.8.2 ✓
	21.4165 - 20.083	0.019	0.596	0.000	0.030	0.000	0.616	1.050	4.8.2 ✓

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 90 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Section No.	Elevation ft	Ratio P_u	Ratio M_{ux}	Ratio M_{uy}	Ratio V_u	Ratio T_u	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
		ϕP_n	ϕM_{nx}	ϕM_{ny}	ϕV_n	ϕT_n			
L54	20.083 - 19.833 (54)	0.023	0.704	0.000	0.035	0.000	0.728	1.050	4.8.2 ✓
L55	19.833 - 18.4165	0.023	0.714	0.000	0.035	0.000	0.739	1.050	4.8.2 ✓
	18.4165 - 17	0.024	0.725	0.000	0.035	0.000	0.750	1.050	4.8.2 ✓
L56	17 - 16.75 (56)	0.019	0.617	0.000	0.030	0.000	0.637	1.050	4.8.2 ✓
L57	16.75 - 15.73	0.019	0.600	0.000	0.029	0.000	0.620	1.050	4.8.2 ✓
	15.73 - 14.71	0.019	0.606	0.000	0.029	0.000	0.626	1.050	4.8.2 ✓
	14.71 - 13.69	0.019	0.612	0.000	0.029	0.000	0.632	1.050	4.8.2 ✓
	13.69 - 12.67	0.019	0.619	0.000	0.029	0.000	0.639	1.050	4.8.2 ✓
	12.67 - 11.65	0.019	0.625	0.000	0.029	0.000	0.645	1.050	4.8.2 ✓
L58	11.65 - 11.417 (58)	0.019	0.626	0.000	0.029	0.000	0.647	1.050	4.8.2 ✓
L59	11.417 - 10.4065	0.020	0.633	0.000	0.029	0.000	0.653	1.050	4.8.2 ✓
	10.4065 - 9.396	0.020	0.639	0.000	0.029	0.000	0.659	1.050	4.8.2 ✓
L60	9.396 - 9.146 (60)	0.018	0.596	0.000	0.028	0.000	0.615	1.050	4.8.2 ✓
L61	9.146 - 8.06775	0.019	0.602	0.000	0.028	0.000	0.621	1.050	4.8.2 ✓
	8.06775 - 6.9895	0.019	0.608	0.000	0.028	0.000	0.628	1.050	4.8.2 ✓
	6.9895 - 5.91125	0.019	0.614	0.000	0.028	0.000	0.634	1.050	4.8.2 ✓
	5.91125 - 4.833	0.019	0.620	0.000	0.028	0.000	0.640	1.050	4.8.2 ✓
L62	4.833 - 4.583 (62)	0.020	0.668	0.000	0.030	0.000	0.690	1.050	4.8.2 ✓
L63	4.583 - 3.43725	0.021	0.676	0.000	0.030	0.000	0.697	1.050	4.8.2 ✓
	3.43725 - 2.2915	0.021	0.683	0.000	0.030	0.000	0.704	1.050	4.8.2 ✓
	2.2915 - 1.14575	0.021	0.690	0.000	0.030	0.000	0.712	1.050	4.8.2 ✓
	1.14575 - 0	0.021	0.697	0.000	0.030	0.000	0.719	1.050	4.8.2 ✓

* DL controls

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 91 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhyia

Section Capacity Table


Section No.	Elevation ft	Component Type	Size	Critical Element	P K	ϕP_{allow} K	% Capacity	Pass Fail
L1	191.667 - 186.667	Pole	P18x0.375	1	-0.640	824.122	**	**
L2	186.667 - 181.567	Pole	P24x0.375	2	-11.581	1104.673	**	**
L3	181.567 - 176.567	Pole	P24x0.375	3	-5.762	1104.673	**	**
L4	176.567 - 171.567	Pole	P24x0.375	4	-6.450	1104.673	**	**
L5	171.567 - 166.567	Pole	P24x0.375	5	-7.141	1104.673	**	**
L6	166.567 - 161.567	Pole	P24x0.375	6	-7.834	1104.673	**	**
L7	161.567 - 156.567	Pole	P24x0.375	7	-12.294	1104.673	**	**
L8	156.567 - 151.567	Pole	P24x0.375	8	-13.045	1104.673	**	**
L9	151.567 - 146.567	Pole	P24x0.375	9	-18.937	1104.673	**	**
L10	146.567 - 141.567	Pole	P24x0.375	10	-19.806	1104.673	**	**
L11	141.567 - 141.417	Pole	P24x0.375	11	-19.840	1104.673	**	**
L12	141.417 - 136.417	Pole	P36x0.375	12	-20.970	1564.605	**	**
L13	136.417 - 131.417	Pole	P36x0.375	13	-22.552	1564.605	**	**
L14	131.417 - 126.417	Pole	P36x0.375	14	-23.712	1564.605	**	**
L15	126.417 - 121.417	Pole	P36x0.375	15	-25.921	1564.605	**	**
L16	121.417 - 121.167	Pole	P36x0.375	16	-25.996	1564.605	**	**
L17	121.167 - 116.167	Pole	P42x0.375	17	-27.464	1752.313	**	**
L18	116.167 - 111.167	Pole	P42x0.375	18	-32.770	1752.313	**	**
L19	111.167 - 110.042	Pole	P42x0.375	19	-33.081	1752.313	**	**
L20	110.042 - 109.792	Pole	P42x0.4875	20	-33.170	2448.736	**	**
L21	109.792 - 105.083	Pole	P42x0.4875	21	-34.791	2448.736	**	**
L22	105.083 - 104.833	Pole	P42x0.5625	22	-34.902	2906.347	**	**
L23	104.833 - 100.917	Pole	P42x0.5625	23	-37.327	2906.347	**	**
L24	100.917 - 100.667	Pole	P48x0.375	24	-37.437	1939.864	**	**
L25	100.667 - 95.833	Pole	P48x0.375	25	-39.273	1939.864	**	**
L26	95.833 - 95.583	Pole	P48x0.475	26	-39.370	2605.459	**	**
L27	95.583 - 90.583	Pole	P48x0.475	27	-41.151	2605.459	**	**
L28	90.583 - 89.917	Pole	P48x0.475	28	-41.887	2605.459	**	**
L29	89.917 - 89.667	Pole	P48x0.575	29	-42.001	3332.721	**	**
L30	89.667 - 84.667	Pole	P48x0.575	30	-44.836	3332.721	**	**
L31	84.667 - 80.833	Pole	P48x0.575	31	-48.016	3332.721	**	**
L32	80.833 - 80.333	Pole	P54x0.55	32	-48.398	3420.721	**	**
L33	80.333 - 80.083	Pole	P54x0.4875	33	-48.539	2937.028	**	**
L34	80.083 - 75.083	Pole	P54x0.4875	34	-51.016	2937.028	**	**

tnxTower B+T Group 1717 S, Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX:	Job 87581.023.01 - Newington_1, CT (BU# 826217)	Page 92 of 92
	Project	Date 13:18:51 07/13/19
	Client Crown Castle	Designed by Pavan Upadhya

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	ϕP_{allow} K	% Capacity	Pass Fail
L35	75.083 - 70.083	Pole	P54x0.4875	35	-53.919	2937.028	**	**
L36	70.083 - 69.5	Pole	P54x0.4875	36	-54.599	2937.028	**	**
L37	69.5 - 69.25	Pole	P54x0.5875	37	-54.787	3722.491	**	**
L38	69.25 - 64.25	Pole	P54x0.5875	38	-61.154	3722.491	**	**
L39	64.25 - 60.583	Pole	P54x0.5875	39	-66.334	3722.491	**	**
L40	60.583 - 60.333	Pole	P60x0.5125	40	-66.540	3384.034	**	**
L41	60.333 - 55.333	Pole	P60x0.5125	41	-70.324	3384.034	**	**
L42	55.333 - 52.167	Pole	P60x0.5125	42	-71.817	3384.034	**	**
L43	52.167 - 51.917	Pole	P60x0.625	43	-71.963	4346.107	**	**
L44	51.917 - 46.917	Pole	P60x0.625	44	-75.064	4346.107	**	**
L45	46.917 - 41.917	Pole	P60x0.625	45	-79.037	4346.107	**	**
L46	41.917 - 40.333	Pole	P60x0.625	46	-80.285	4346.107	**	**
L47	40.333 - 40.083	Pole	P60x0.6	47	-80.478	4125.565	**	**
L48	40.083 - 35.083	Pole	P60x0.6	48	-84.151	4125.565	**	**
L49	35.083 - 30.083	Pole	P60x0.6	49	-87.481	4125.565	**	**
L50	30.083 - 28	Pole	P60x0.6	50	-88.606	4125.565	**	**
L51	28 - 27.75	Pole	P60x0.725	51	-88.772	5266.705	**	**
L52	27.75 - 22.75	Pole	P60x0.725	52	-92.893	5266.705	**	**
L53	22.75 - 20.083	Pole	P60x0.725	53	-95.121	5266.705	**	**
L54	20.083 - 19.833	Pole	P60x0.625	54	-95.320	4346.107	**	**
L55	19.833 - 17	Pole	P60x0.625	55	-97.470	4346.107	**	**
L56	17 - 16.75	Pole	P60x0.725	56	-97.696	5266.705	**	**
L57	16.75 - 11.65	Pole	P60x0.75	57	-101.930	5506.441	**	**
L58	11.65 - 11.417	Pole	P60x0.75	58	-102.094	5506.441	**	**
L59	11.417 - 9.396	Pole	P60x0.75	59	-103.448	5506.441	**	**
L60	9.396 - 9.146	Pole	P60x0.8	60	-103.630	5905.305	**	**
L61	9.146 - 4.833	Pole	P60x0.8	61	-106.631	5905.305	**	**
L62	4.833 - 4.583	Pole	P60x0.75	62	-106.810	5506.441	**	**
L63	4.583 - 0	Pole	P60x0.75	63	-109.954	5506.441	**	**
							Summary	
							Pole (L55)	**
							RATING =	**

**See Additional Calculations

APPENDIX B
BASE LEVEL DRAWING



BUSINESS UNIT: 826217

APPENDIX C
ADDITIONAL CALCULATIONS

Pole Geometry

	Pole Height Above Base (ft)	Section Length (ft)	Lap Splice Length (ft)	Number of Sides	Top Diameter (in)	Bottom Diameter (in)	Wall Thickness (in)	Bend Radius (in)	Pole Material
1	191.667	10.084		0	18	18	0.375		A53-B-42
2	181.583	40.166		0	24.00	24	0.375		A53-B-42
3	141.417	20.25		0	36.00	36	0.375		A53-B-42
4	121.167	20.25		0	42.00	42	0.375		A53-B-42
5	100.917	20.084		0	48.00	48	0.375		A53-B-42
6	80.833	20.25		0	54.00	54	0.375		A53-B-42
7	60.583	20.25		0	60.00	60	0.375		A53-B-42
8	40.333	20.25		0	60.00	60	0.5		A53-B-42
9	20.083	20.083		0	60.00	60	0.625		A53-B-42

Reinforcement Configuration

	Bottom Effective Elevation (ft)	Top Effective Elevation (ft)	Type	Model	Number	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
1	0	9.396	plate	CCI-AFP-040075	2				70												313		
2	20.083	40.333	plate	CCI-SFP-060100	3				66					189							312		
3	40.333	60.583	plate	CCI-SFP-065125	3				67.5					188							307		
4	60.583	80.333	plate	CCI-SFP-060100	3				67.5					190							307		
5	80.333	89.917	plate	CCI-SFP-045100	3				72					192							312		
6	100.917	105.083	plate	CCI-AFP-040075	3			53						178							303		
7	4.833	11.667	plate	CCI-AFP-040075	1									198									
8	0	17	plate	CCI-SFP-060100	4		36				113						223			294			
9	20.083	28	plate	CCI-SFP-060100	4			53					157					247				339	
10	40.333	52.167	plate	CCI-SFP-060100	4		36				126						234			294			
11	60.583	69.5	plate	CCI-SFP-045100	4				80				155					254					341
12	80.333	95.833	plate	CCI-SFP-045100	3					93							213					333	
13	100.917	110.042	plate	CCI-SFP-045100	3		30							150						270			
14																							

Reinforcement Details

	B (in)	H (in)	Gross Area (in ²)	Pole Face to Centroid (in)	Bottom Termination Length (in)	Top Termination Length (in)	L _u (in)	Net Area (in ²)	Bolt Hole Size (in)	Reinforcement Material
1	4	0.75	3	0.375	18.000	18.000	16.000	2.063	1.1875	A572-65
2	6	1	6	0.5	24.000	24.000	16.000	4.750	1.1875	A572-65
3	6.5	1.25	8.125	0.625	33.000	33.000	19.000	6.563	1.1875	A572-65
4	6	1	6	0.5	24.000	24.000	16.000	4.750	1.1875	A572-65
5	4.5	1	4.5	0.5	18.000	18.000	20.000	3.250	1.1875	A572-65
6	4	0.75	3	0.375	18.000	18.000	16.000	2.063	1.1875	A572-65
7	4	0.75	3	0.375	18.000	18.000	16.000	2.063	1.1875	A572-65
8	6	1	6	0.5	24.000	24.000	16.000	4.750	1.1875	A572-65
9	6	1	6	0.5	24.000	24.000	16.000	4.750	1.1875	A572-65
10	6	1	6	0.5	24.000	24.000	16.000	4.750	1.1875	A572-65
11	4.5	1	4.5	0.5	18.000	18.000	20.000	3.250	1.1875	A572-65
12	4.5	1	4.5	0.5	18.000	18.000	20.000	3.250	1.1875	A572-65
13	4.5	1	4.5	0.5	18.000	18.000	20.000	3.250	1.1875	A572-65

TNX Geometry Input

Increment (ft): 5

	Section Height (ft)	Section Length (ft)	Lap Splice Length (ft)	Number of Sides	Top Diameter (in)	Bottom Diameter (in)	Wall Thickness (in)	Tapered Pole Grade	Weight Multiplier
1	191.667 - 186.667	5	0	0	18.000	18.000	0.375	A53-B-42	1.000
2	186.667 - 181.567	5.1		0	24.000	24.000	0.375	A53-B-42	1.000
3	181.567 - 176.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
4	176.567 - 171.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
5	171.567 - 166.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
6	166.567 - 161.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
7	161.567 - 156.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
8	156.567 - 151.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
9	151.567 - 146.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
10	146.567 - 141.567	5		0	24.000	24.000	0.375	A53-B-42	1.000
11	141.567 - 141.417	0.15	0	0	24.000	24.000	0.375	A53-B-42	1.000
12	141.417 - 136.417	5		0	36.000	36.000	0.375	A53-B-42	1.000
13	136.417 - 131.417	5		0	36.000	36.000	0.375	A53-B-42	1.000
14	131.417 - 126.417	5		0	36.000	36.000	0.375	A53-B-42	1.000
15	126.417 - 121.417	5		0	36.000	36.000	0.375	A53-B-42	1.000
16	121.417 - 121.167	0.25	0	0	36.000	36.000	0.375	A53-B-42	1.000
17	121.167 - 116.167	5		0	42.000	42.000	0.375	A53-B-42	1.000
18	116.167 - 111.167	5		0	42.000	42.000	0.375	A53-B-42	1.000
19	111.167 - 110.042	1.125		0	42.000	42.000	0.375	A53-B-42	1.000
20	110.042 - 109.792	0.25		0	42.000	42.000	0.4875	A53-B-42	0.984
21	109.792 - 105.083	4.709		0	42.000	42.000	0.4875	A53-B-42	0.984
22	105.083 - 104.833	0.25		0	42.000	42.000	0.5625	A53-B-42	0.977
23	104.833 - 100.917	3.916	0	0	42.000	42.000	0.5625	A53-B-42	0.977
24	100.917 - 100.667	0.25		0	48.000	48.000	0.375	A53-B-42	1.000
25	100.667 - 95.833	4.834		0	48.000	48.000	0.375	A53-B-42	1.000
26	95.833 - 95.583	0.25		0	48.000	48.000	0.475	A53-B-42	0.981
27	95.583 - 90.583	5		0	48.000	48.000	0.475	A53-B-42	0.981
28	90.583 - 89.917	0.666		0	48.000	48.000	0.475	A53-B-42	0.981
29	89.917 - 89.667	0.25		0	48.000	48.000	0.575	A53-B-42	0.970
30	89.667 - 84.667	5		0	48.000	48.000	0.575	A53-B-42	0.970
31	84.667 - 80.833	3.834	0	0	48.000	48.000	0.575	A53-B-42	0.970
32	80.833 - 80.333	0.5		0	54.000	54.000	0.55	A53-B-42	0.976
33	80.333 - 80.083	0.25		0	54.000	54.000	0.4875	A53-B-42	0.990
34	80.083 - 75.083	5		0	54.000	54.000	0.4875	A53-B-42	0.990
35	75.083 - 70.083	5		0	54.000	54.000	0.4875	A53-B-42	0.990
36	70.083 - 69.5	0.583		0	54.000	54.000	0.4875	A53-B-42	0.990
37	69.5 - 69.25	0.25		0	54.000	54.000	0.5875	A53-B-42	1.006
38	69.25 - 64.25	5		0	54.000	54.000	0.5875	A53-B-42	1.006
39	64.25 - 60.583	3.667	0	0	54.000	54.000	0.5875	A53-B-42	1.006
40	60.583 - 60.333	0.25		0	60.000	60.000	0.5125	A53-B-42	0.988
41	60.333 - 55.333	5		0	60.000	60.000	0.5125	A53-B-42	0.988
42	55.333 - 52.167	3.166		0	60.000	60.000	0.5125	A53-B-42	0.988
43	52.167 - 51.917	0.25		0	60.000	60.000	0.625	A53-B-42	1.017
44	51.917 - 46.917	5		0	60.000	60.000	0.625	A53-B-42	1.017
45	46.917 - 41.917	5		0	60.000	60.000	0.625	A53-B-42	1.017
46	41.917 - 40.333	1.584	0	0	60.000	60.000	0.625	A53-B-42	1.017
47	40.333 - 40.083	0.25		0	60.000	60.000	0.6	A53-B-42	0.995
48	40.083 - 35.083	5		0	60.000	60.000	0.6	A53-B-42	0.995
49	35.083 - 30.083	5		0	60.000	60.000	0.6	A53-B-42	0.995
50	30.083 - 28	2.083		0	60.000	60.000	0.6	A53-B-42	0.995
51	28 - 27.75	0.25		0	60.000	60.000	0.725	A53-B-42	1.003
52	27.75 - 22.75	5		0	60.000	60.000	0.725	A53-B-42	1.003
53	22.75 - 20.083	2.667	0	0	60.000	60.000	0.725	A53-B-42	1.003
54	20.083 - 19.833	0.25		0	60.000	60.000	0.625	A53-B-42	1.000
55	19.833 - 17	2.833		0	60.000	60.000	0.625	A53-B-42	1.000
56	17 - 16.75	0.25		0	60.000	60.000	0.725	A53-B-42	1.041
57	16.75 - 11.65	5.1		0	60.000	60.000	0.75	A53-B-42	1.028
58	11.65 - 11.417	0.233		0	60.000	60.000	0.75	A53-B-42	1.028
59	11.417 - 9.396	2.021		0	60.000	60.000	0.75	A53-B-42	1.028
60	9.396 - 9.146	0.25		0	60.000	60.000	0.8	A53-B-42	1.005
61	9.146 - 4.833	4.313		0	60.000	60.000	0.8	A53-B-42	1.005
62	4.833 - 4.583	0.25		0	60.000	60.000	0.75	A53-B-42	1.050
63	4.583 - 0	4.583		0	60.000	60.000	0.75	A53-B-42	1.050

TNX Section Forces

Increment (ft):		TNX Output			
5					
	Section Height (ft)	P _u	M _{ux} (kip-ft)	V _u	
		(K)		(K)	
1	191.667 - 186.667	0.64	2.21	0.48	
2	186.667 - 181.567	5.05	7.28	5.01	
3	181.567 - 176.567	5.77	33.17	5.37	
4	176.567 - 171.567	6.45	60.95	5.71	
5	171.567 - 166.567	7.14	90.33	6.03	
6	166.567 - 161.567	7.83	121.26	6.33	
7	161.567 - 156.567	12.29	171.03	11.82	
8	156.567 - 151.567	13.04	230.83	12.10	
9	151.567 - 146.567	18.94	319.62	18.69	
10	146.567 - 141.567	19.81	413.62	18.91	
11	141.567 - 141.417	19.84	416.46	18.91	
12	141.417 - 136.417	20.97	512.08	19.38	
13	136.417 - 131.417	22.54	610.86	20.29	
14	131.417 - 126.417	23.71	713.42	20.70	
15	126.417 - 121.417	25.92	819.25	21.65	
16	121.417 - 121.167	26.00	824.67	21.68	
17	121.167 - 116.167	27.46	934.70	22.22	
18	116.167 - 111.167	32.77	1067.79	26.36	
19	111.167 - 110.042	33.05	1097.54	26.57	
20	110.042 - 109.792	33.14	1104.19	26.61	
21	109.792 - 105.083	34.79	1231.52	27.46	
22	105.083 - 104.833	34.90	1238.39	27.51	
23	104.833 - 100.917	37.33	1347.69	28.30	
24	100.917 - 100.667	37.44	1354.77	28.34	
25	100.667 - 95.833	39.27	1494.19	29.34	
26	95.833 - 95.583	39.37	1501.53	29.36	
27	95.583 - 90.583	41.15	1650.61	30.26	
28	90.583 - 89.917	41.89	1672.01	30.79	
29	89.917 - 89.667	42.00	1679.71	30.84	
30	89.667 - 84.667	44.84	1836.33	31.84	
31	84.667 - 80.833	48.02	1959.76	32.63	
32	80.833 - 80.333	48.40	1976.08	32.72	
33	80.333 - 80.083	48.54	1984.26	32.78	
34	80.083 - 75.083	51.02	2150.68	33.79	
35	75.083 - 70.083	53.92	2322.37	34.84	
36	70.083 - 69.5	54.60	2342.92	35.45	
37	69.5 - 69.25	54.79	2351.80	35.51	
38	69.25 - 64.25	61.15	2532.67	36.70	
39	64.25 - 60.583	66.33	2669.08	37.57	
40	60.583 - 60.333	66.54	2678.48	37.61	
41	60.333 - 55.333	70.32	2869.52	38.74	
42	55.333 - 52.167	71.82	2993.11	39.32	
43	52.167 - 51.917	71.96	3002.95	39.36	
44	51.917 - 46.917	75.06	3202.18	40.33	
45	46.917 - 41.917	79.04	3406.09	41.37	
46	41.917 - 40.333	80.28	3471.76	41.69	
47	40.333 - 40.083	80.48	3482.16	41.72	
48	40.083 - 35.083	84.15	3692.64	42.62	
49	35.083 - 30.083	87.48	3908.51	43.60	
50	30.083 - 28	88.61	3999.63	43.89	
51	28 - 27.75	88.77	4010.61	43.92	
52	27.75 - 22.75	92.89	4232.37	44.75	
53	22.75 - 20.083	95.12	4352.32	45.18	
54	20.083 - 19.833	95.32	4363.62	45.20	
55	19.833 - 17	97.47	4492.35	45.65	
56	17 - 16.75	97.70	4503.76	45.66	
57	16.75 - 11.65	101.93	4738.61	46.40	
58	11.65 - 11.417	102.09	4749.42	46.40	
59	11.417 - 9.396	103.45	4843.30	46.50	
60	9.396 - 9.146	103.63	4854.93	46.52	
61	9.146 - 4.833	106.63	5056.84	47.10	
62	4.833 - 4.583	106.81	5068.62	47.11	
63	4.583 - 0	109.95	5285.89	47.70	

Analysis Results

Elevation (ft)	Component Type	Size	Critical Element	% Capacity	Pass / Fail
191.67 - 186.67	Pole	TP18x18x0.375	Pole	0.7%	Pass
186.67 - 181.57	Pole	TP24x24x0.375	Pole	1.6%	Pass
181.57 - 176.57	Pole	TP24x24x0.375	Pole	5.6%	Pass
176.57 - 171.57	Pole	TP24x24x0.375	Pole	9.9%	Pass
171.57 - 166.57	Pole	TP24x24x0.375	Pole	14.5%	Pass
166.57 - 161.57	Pole	TP24x24x0.375	Pole	19.2%	Pass
161.57 - 156.57	Pole	TP24x24x0.375	Pole	27.3%	Pass
156.57 - 151.57	Pole	TP24x24x0.375	Pole	36.5%	Pass
151.57 - 146.57	Pole	TP24x24x0.375	Pole	50.6%	Pass
146.57 - 141.57	Pole	TP24x24x0.375	Pole	65.1%	Pass
141.57 - 141.42	Pole	TP24x24x0.375	Pole	65.5%	Pass
141.42 - 136.42	Pole	TP36x36x0.375	Pole	37.8%	Pass
136.42 - 131.42	Pole	TP36x36x0.375	Pole	45.0%	Pass
131.42 - 126.42	Pole	TP36x36x0.375	Pole	52.3%	Pass
126.42 - 121.42	Pole	TP36x36x0.375	Pole	60.0%	Pass
121.42 - 121.17	Pole	TP36x36x0.375	Pole	60.4%	Pass
121.17 - 116.17	Pole	TP42x42x0.375	Pole	51.2%	Pass
116.17 - 111.17	Pole	TP42x42x0.375	Pole	58.6%	Pass
111.17 - 110.04	Pole	TP42x42x0.375	Pole	60.2%	Pass
110.04 - 109.79	Pole + Reinf.	TP42x42x0.4875	Reinf. 13 Tension Rupture	47.0%	Pass
109.79 - 105.08	Pole + Reinf.	TP42x42x0.4875	Reinf. 13 Tension Rupture	52.3%	Pass
105.08 - 104.83	Pole + Reinf.	TP42x42x0.5625	Reinf. 6 Tension Rupture	47.7%	Pass
104.83 - 100.92	Pole + Reinf.	TP42x42x0.5625	Reinf. 6 Tension Rupture	51.9%	Pass
100.92 - 100.67	Pole	TP48x48x0.375	Pole	57.6%	Pass
100.67 - 95.83	Pole	TP48x48x0.375	Pole	63.4%	Pass
95.83 - 95.58	Pole + Reinf.	TP48x48x0.475	Pole	50.7%	Pass
95.58 - 90.58	Pole + Reinf.	TP48x48x0.475	Pole	55.6%	Pass
90.58 - 89.92	Pole + Reinf.	TP48x48x0.475	Pole	56.3%	Pass
89.92 - 89.67	Pole + Reinf.	TP48x48x0.575	Pole	47.0%	Pass
89.67 - 84.67	Pole + Reinf.	TP48x48x0.575	Pole	51.3%	Pass
84.67 - 80.83	Pole + Reinf.	TP48x48x0.575	Pole	54.8%	Pass
80.83 - 80.33	Pole + Reinf.	TP54x54x0.55	Pole	46.0%	Pass
80.33 - 80.08	Pole + Reinf.	TP54x54x0.4875	Pole	52.0%	Pass
80.08 - 75.08	Pole + Reinf.	TP54x54x0.4875	Pole	56.3%	Pass
75.08 - 70.08	Pole + Reinf.	TP54x54x0.4875	Pole	60.8%	Pass
70.08 - 69.5	Pole + Reinf.	TP54x54x0.4875	Pole	61.3%	Pass
69.5 - 69.25	Pole + Reinf.	TP54x54x0.5875	Pole	50.9%	Pass
69.25 - 64.25	Pole + Reinf.	TP54x54x0.5875	Pole	54.8%	Pass
64.25 - 60.58	Pole + Reinf.	TP54x54x0.5875	Pole	57.8%	Pass
60.58 - 60.33	Pole + Reinf.	TP60x60x0.5125	Pole	54.3%	Pass
60.33 - 55.33	Pole + Reinf.	TP60x60x0.5125	Pole	58.1%	Pass
55.33 - 52.17	Pole + Reinf.	TP60x60x0.5125	Pole	60.6%	Pass
52.17 - 51.92	Pole + Reinf.	TP60x60x0.625	Pole	50.8%	Pass
51.92 - 46.92	Pole + Reinf.	TP60x60x0.625	Pole	54.1%	Pass
46.92 - 41.92	Pole + Reinf.	TP60x60x0.625	Pole	57.5%	Pass
41.92 - 40.33	Pole + Reinf.	TP60x60x0.625	Pole	58.6%	Pass
40.33 - 40.08	Pole + Reinf.	TP60x60x0.6	Pole	59.3%	Pass
40.08 - 35.08	Pole + Reinf.	TP60x60x0.6	Pole	62.8%	Pass
35.08 - 30.08	Pole + Reinf.	TP60x60x0.6	Pole	66.5%	Pass
30.08 - 28	Pole + Reinf.	TP60x60x0.6	Pole	68.0%	Pass
28 - 27.75	Pole + Reinf.	TP60x60x0.725	Pole	57.2%	Pass
27.75 - 22.75	Pole + Reinf.	TP60x60x0.725	Pole	60.4%	Pass
22.75 - 20.08	Pole + Reinf.	TP60x60x0.725	Pole	62.1%	Pass
20.08 - 19.83	Pole	TP60x60x0.625	Pole	69.3%	Pass
19.83 - 17	Pole	TP60x60x0.625	Pole	71.3%	Pass
17 - 16.75	Pole + Reinf.	TP60x60x0.725	Pole	61.8%	Pass
16.75 - 11.65	Pole + Reinf.	TP60x60x0.75	Pole	63.5%	Pass
11.65 - 11.42	Pole + Reinf.	TP60x60x0.75	Pole	63.7%	Pass
11.42 - 9.4	Pole + Reinf.	TP60x60x0.75	Pole	64.9%	Pass
9.4 - 9.15	Pole + Reinf.	TP60x60x0.8	Reinf. 7 Tension Rupture	64.6%	Pass
9.15 - 4.83	Pole + Reinf.	TP60x60x0.8	Reinf. 7 Tension Rupture	67.3%	Pass
4.83 - 4.58	Pole + Reinf.	TP60x60x0.75	Pole	68.8%	Pass
4.58 - 0	Pole + Reinf.	TP60x60x0.75	Pole	71.7%	Pass
				Summary	
			Pole	71.7%	Pass
			Reinforcement	69.8%	Pass
			Overall	71.7%	Pass

Additional Calculations

Section Elevation (ft)	Moment of Inertia (in ⁴)			Area (in ²)			% Capacity*													
	Pole	Reinf.	Total	Pole	Reinf.	Total	Pole	R1	R2	R3	R4	R5	R6	R7	R8	R9	R10	R11	R12	R13
191.67 - 186.67	807	n/a	807	20.76	n/a	20.76	0.7%													
186.67 - 181.57	1942	n/a	1942	27.83	n/a	27.83	1.6%													
181.57 - 176.57	1942	n/a	1942	27.83	n/a	27.83	5.6%													
176.57 - 171.57	1942	n/a	1942	27.83	n/a	27.83	9.9%													
171.57 - 166.57	1942	n/a	1942	27.83	n/a	27.83	14.5%													
166.57 - 161.57	1942	n/a	1942	27.83	n/a	27.83	19.2%													
161.57 - 156.57	1942	n/a	1942	27.83	n/a	27.83	27.3%													
156.57 - 151.57	1942	n/a	1942	27.83	n/a	27.83	36.5%													
151.57 - 146.57	1942	n/a	1942	27.83	n/a	27.83	50.6%													
146.57 - 141.57	1942	n/a	1942	27.83	n/a	27.83	65.1%													
141.57 - 141.42	1942	n/a	1942	27.83	n/a	27.83	65.5%													
141.42 - 136.42	6659	n/a	6659	41.97	n/a	41.97	37.8%													
136.42 - 131.42	6659	n/a	6659	41.97	n/a	41.97	45.0%													
131.42 - 126.42	6659	n/a	6659	41.97	n/a	41.97	52.3%													
126.42 - 121.42	6659	n/a	6659	41.97	n/a	41.97	60.0%													
121.42 - 121.17	6659	n/a	6659	41.97	n/a	41.97	60.4%													
121.17 - 116.17	10622	n/a	10622	49.04	n/a	49.04	51.2%													
116.17 - 111.17	10622	n/a	10622	49.04	n/a	49.04	58.6%													
111.17 - 110.04	10622	n/a	10622	49.04	n/a	49.04	60.2%													
110.04 - 109.79	10622	3132	13754	49.04	13.50	62.54	46.6%													47.0%
109.79 - 105.08	10622	3132	13754	49.04	13.50	62.54	51.9%													52.3%
105.08 - 104.83	10622	5106	15728	49.04	22.50	71.54	45.8%						47.7%							46.3%
104.83 - 100.92	10622	5106	15728	49.04	22.50	71.54	49.8%						51.9%							50.4%
100.92 - 100.67	15908	n/a	15908	56.11	n/a	56.11	57.6%													
100.67 - 95.83	15908	n/a	15908	56.11	n/a	56.11	63.4%													
95.83 - 95.58	15908	4064	19972	56.11	13.50	69.61	50.7%													50.1%
95.58 - 90.58	15908	4064	19972	56.11	13.50	69.61	55.6%													55.0%
90.58 - 89.92	15908	4064	19972	56.11	13.50	69.61	56.3%													55.8%
89.92 - 89.67	15908	8127	24036	56.11	27.00	83.11	47.0%					46.5%								46.5%
89.67 - 84.67	15908	8127	24036	56.11	27.00	83.11	51.3%					50.8%								50.8%
84.67 - 80.83	15908	8127	24036	56.11	27.00	83.11	54.8%					54.2%								54.2%
80.83 - 80.33	22710	10233	32943	63.18	27.00	90.18	46.0%					44.9%								44.9%
80.33 - 80.08	22710	6614	29324	63.18	18.00	81.18	52.0%				46.2%									
80.08 - 75.08	22710	6614	29324	63.18	18.00	81.18	56.3%				50.0%									
75.08 - 70.08	22710	6614	29324	63.18	18.00	81.18	60.8%				53.9%									
70.08 - 69.5	22710	6614	29324	63.18	18.00	81.18	61.3%				54.4%									
69.5 - 69.25	22710	12688	35398	63.18	36.00	99.18	50.9%				45.2%									48.8%
69.25 - 64.25	22710	12688	35398	63.18	36.00	99.18	54.8%				48.7%									52.6%
64.25 - 60.58	22710	12688	35398	63.18	36.00	99.18	57.8%				51.4%									55.4%
60.58 - 60.33	31217	11364	42581	70.24	24.38	94.62	54.3%			47.2%										
60.33 - 55.33	31217	11364	42581	70.24	24.38	94.62	58.1%			50.5%										
55.33 - 52.17	31217	11364	42581	70.24	24.38	94.62	60.6%			52.7%										
52.17 - 51.92	31219	19812	51030	70.24	48.38	118.62	50.8%			43.8%										43.1%
51.92 - 46.92	31219	19812	51030	70.24	48.38	118.62	54.1%			46.7%										46.0%
46.92 - 41.92	31219	19812	51030	70.24	48.38	118.62	57.5%			49.6%										48.9%
41.92 - 40.33	31219	19812	51030	70.24	48.38	118.62	58.6%			50.6%										49.8%
40.33 - 40.08	41363	7892	49255	93.46	18.00	111.46	59.3%		53.4%											
40.08 - 35.08	41363	7892	49255	93.46	18.00	111.46	62.8%		56.6%											
35.08 - 30.08	41363	7892	49255	93.46	18.00	111.46	66.5%		59.9%											
30.08 - 28	41363	7892	49255	93.46	18.00	111.46	68.0%		61.2%											
28 - 27.75	41368	17587	58955	93.46	42.00	135.46	57.2%		50.4%											50.5%
27.75 - 22.75	41368	17587	58955	93.46	42.00	135.46	60.4%		53.2%											53.3%
22.75 - 20.08	41368	17587	58955	93.46	42.00	135.46	62.1%		54.7%											54.8%
20.08 - 19.83	51381	n/a	51381	116.58	n/a	116.58	69.3%													
19.83 - 17	51381	n/a	51381	116.58	n/a	116.58	71.3%													
17 - 16.75	51383	8145	59528	116.58	24.00	140.58	61.8%													54.4%
16.75 - 11.65	51395	9920	61315	116.58	27.00	143.58	63.5%													63.3%
11.65 - 11.42	51395	9920	61315	116.58	27.00	143.58	63.7%													63.4%
11.42 - 9.4	51395	9920	61315	116.58	27.00	143.58	64.9%													64.7%
9.4 - 9.15	51382	13787	65169	116.58	33.00	149.58	60.8%	64.1%												64.6%
9.15 - 4.83	51382	13787	65169	116.58	33.00	149.58	63.3%	66.7%												67.3%
4.83 - 4.58	51446	9839	61284	116.58	30.00	146.58	68.8%	67.0%												59.9%
4.58 - 0	51446	9839	61284	116.58	30.00	146.58	71.7%	69.8%												62.4%

Note: Section capacity checked in 5 degree increments.
Rating per TIA-222-H Section 15.5.

Monopole Flange Plate Connection

Elevation = 181.583 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0

Applied Loads	
Moment (kip-ft)	7.28
Axial Force (kips)	5.05
Shear Force (kips)	5.01


*TIA-222-H Section 15.5 Applied

TIA-222 Revision	H
------------------	---

Top Plate - External



Bottom Plate - External



Connection Properties

Bolt Data

(16) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 21" BC

Top Plate Data

24" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Plate Data

24" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

(8) 5"H x 3"W x 0.625"T, Notch: 0.75"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Bottom Stiffener Data

N/A

Top Pole Data

18" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Pole Data

24" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	0.72
Allowable (kips)	54.54
Stress Rating:	1.3% Pass

Top Plate Capacity

Max Stress (ksi):	-
Allowable Stress (ksi):	-
Stress Rating:	N/A
Tension Side Stress Rating:	N/A

Bottom Plate Capacity

Max Stress (ksi):	-
Allowable Stress (ksi):	-
Stress Rating:	N/A
Tension Side Stress Rating:	N/A

Top Stiffener Capacity

Horizontal Weld:	N/A
Vertical Weld:	N/A
Plate Flexure+Shear:	N/A
Plate Tension+Shear:	N/A
Plate Compression:	N/A

Bottom Stiffener Capacity

Horizontal Weld:	N/A
Vertical Weld:	N/A
Plate Flexure+Shear:	N/A
Plate Tension+Shear:	N/A
Plate Compression:	N/A

Top Pole Capacity

Punching Shear:	N/A
-----------------	-----

Bottom Pole Capacity

Punching Shear:	N/A
-----------------	-----

Monopole Flange Plate Connection

Elevation = 141.417 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0
TIA-222 Revision	H


Applied Loads	
Moment (kip-ft)	416.46
Axial Force (kips)	19.84
Shear Force (kips)	18.91

*TIA-222-H Section 15.5 Applied

Top Plate - External



Bottom Plate - External



Connection Properties

Bolt Data

(24) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 33" BC

Top Plate Data

36.375" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

(12) 8"H x 6"W x 1"T, Notch: 1"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Top Pole Data

24" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Plate Data

36.375" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Stiffener Data

N/A

Bottom Pole Data

36" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	24.40
Allowable (kips)	54.53
Stress Rating:	42.6% Pass

Top Plate Capacity

Max Stress (ksi):	-
Allowable Stress (ksi):	-
Stress Rating:	N/A
Tension Side Stress Rating:	N/A

Top Stiffener Capacity

Horizontal Weld:	N/A
Vertical Weld:	N/A
Plate Flexure+Shear:	N/A
Plate Tension+Shear:	N/A
Plate Compression:	N/A

Top Pole Capacity

Punching Shear:	N/A
-----------------	------------

Bottom Plate Capacity

Max Stress (ksi):	-
Allowable Stress (ksi):	-
Stress Rating:	N/A
Tension Side Stress Rating:	N/A

Bottom Stiffener Capacity

Horizontal Weld:	N/A
Vertical Weld:	N/A
Plate Flexure+Shear:	N/A
Plate Tension+Shear:	N/A
Plate Compression:	N/A

Bottom Pole Capacity

Punching Shear:	N/A
-----------------	------------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 121.167 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **121.167** ft Apply TIA-222-H Section 15.5? **Yes**

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	824.67 k-ft
Axial Load (P)	25.996 kip
Shear Load (V)	21.681 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	36 in
Upper Shaft Thickness (t1)	0.375 in
Lower Shaft Diameter (Dshaft2)	42 in
Lower Shaft Thickness (t2)	0.375 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	3
Thickness of Proposed Bridge Stiffeners (texist)	1 in
Width of Proposed Bridge Stiffeners (wexist)	4.5 in
Existing Bridge Stiffener Grade:	
Fyex	65 ksi
Fuex	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	44 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	4.5 in ²
Radius of Gyration about x-axis (rx)	0.289 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	3267 in ⁴

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	28
Diameter of Flange Bolts	1 in
Bolt Circle of Flange Bolts (BCbolts)	39 in
Gross Area of One Flange Bolt (Ag_bolts)	0.785 in ²
Moment of Inertia of Flange Bolts (Ibolts)	4181 in ⁴

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 121.167 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	35.49 in ²
Total Moment of Inertia (Itotal)	7448 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	361.7 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	462.9 kip-ft	} Check Flange Connection with these Reactions
Axial Reaction to Flange Bolts (Pbolts)	26.0 kips	
Shear Reaction to Flange Bolts (Vbolts)	21.7 kips	

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing

Outer Radius of Bolt Circle (C)	22 in
Critical Compression Bending Stress (Pcomp)	131.5 kips
Critical Tension Bending Stress (Ptens)	131.5 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9	
Unbraced Length (Lu)	16 in	
Effective Length Factor (K)	1	
Strength of Bridge Stiffener:		
Fy	65 ksi	
Fu	80 ksi	
Effective Length of Member (Lc)	16.00 in	[AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	93.2 ksi	[AISC 15th Edition, Eq. E3-4]
Limit	99.5	
Determination of Critical Stress (Fcr)	48.5 ksi	
[AISC 15th Edition, Eqs. E3-2 and E3-3]		

Allowable Compressive Strength (ϕP_n)	196.6 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp) 63.7% Pass

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 121.167 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t) [AISC 15th Ed., Ch.D2] 263.3 kips

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.00 in
 Net Area (A_{net}) 3.250 in²
 Net Area Limitation (A_e) 3.250 in²
 Available Fractile Strength (ϕP_{tr}) 195.0 kips

Tension Check

Controlling Mode of Failure (Check mode) (ϕP_{nt}) Fracture Controls 195.0 kips
 Controlling Tension Mode Check (Checktension) **64.2%** **Pass**

SUMMARY

tnxTower Reactions

M 824.7 kip-ft
 P 26.0 kip
 V 21.7 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.00 in
 Bolt Circle of Flange Bolts (BCbolts) 39.0 in
 Loads to Flange Bolts

Mbolts 462.9 kip-ft
 P 26.0 kip
 V 21.7 kip

} See Flange tool for Flange Bolt and Plate Capacities

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M_{exist}) 361.7 kip-ft
 Number of Existing Bridge Stiffeners (N_{exist}) 3
 Thickness (t_{exist}) 1.00 in
 Width (w_{exist}) 4.50 in
 Controlling Capacity of Existing Bridge Stiffeners (Capacity_{max}) **64.2%** **Pass**

Monopole Flange Plate Connection

Elevation = 121.167 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0
TIA-222 Revision	H


Applied Loads	
Moment (kip-ft)	462.90
Axial Force (kips)	26.00
Shear Force (kips)	21.70

*TIA-222-H Section 15.5 Applied

Top Plate - External



Bottom Plate - Internal



Connection Properties

Bolt Data

(28) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 39" BC

Top Plate Data

42" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

(14) 5"H x 3"W x 0.625"T, Notch: 0.75"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Top Pole Data

36" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Plate Data

36" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Stiffener Data

N/A

Bottom Pole Data

42" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	19.41
Allowable (kips)	54.53
Stress Rating:	33.9% Pass

Top Plate Capacity

Max Stress (ksi):	12.73	(Flexural (b/Le>2))
Allowable Stress (ksi):	32.40	
Stress Rating:	37.4%	Pass
Tension Side Stress Rating:	12.9%	Pass

Top Stiffener Capacity

Horizontal Weld:	53.2%	Pass
Vertical Weld:	34.1%	Pass
Plate Flexure+Shear:	23.0%	Pass
Plate Tension+Shear:	39.4%	Pass
Plate Compression:	50.7%	Pass

Top Pole Capacity

Punching Shear:	17.4%	Pass
-----------------	--------------	-------------

Bottom Plate Capacity

Max Stress (ksi):	13.24	(Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	38.9%	Pass
Tension Side Stress Rating:	N/A	

Bottom Stiffener Capacity

Horizontal Weld:	N/A
Vertical Weld:	N/A
Plate Flexure+Shear:	N/A
Plate Tension+Shear:	N/A
Plate Compression:	N/A

Bottom Pole Capacity

Punching Shear:	N/A
-----------------	------------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 100.917 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **100.917** ft Apply TIA-222-H Section 15.5?

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	1347.692 k-ft
Axial Load (P)	37.327 kip
Shear Load (V)	28.296 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	42 in
Upper Shaft Thickness (t1)	0.375 in
Lower Shaft Diameter (Dshaft2)	48 in
Lower Shaft Thickness (t2)	0.375 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	6
Thickness of Proposed Bridge Stiffeners (texist)	1 in
Width of Proposed Bridge Stiffeners (wexist)	4.5 in
Existing Bridge Stiffener Grade:	
Fyex	65 ksi
Fuex	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	49 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	4.5 in ²
Radius of Gyration about x-axis (rx)	0.289 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	7660 in ⁴

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	32
Diameter of Flange Bolts	1 in
Bolt Circle of Flange Bolts (BCbolts)	45 in
Gross Area of One Flange Bolt (Ag_bolts)	0.785 in ²
Moment of Inertia of Flange Bolts (Ibolts)	6362 in ⁴

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 100.917 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	52.13 in ²
Total Moment of Inertia (Itotal)	14023 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	736.1 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	611.4 kip-ft	} Check Flange Connection with these Reactions
Axial Reaction to Flange Bolts (Pbolts)	37.3 kips	
Shear Reaction to Flange Bolts (Vbolts)	28.3 kips	

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing

Outer Radius of Bolt Circle (C)	24.5 in
Critical Compression Bending Stress (Pcomp)	127.1 kips
Critical Tension Bending Stress (Ptens)	127.1 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9	
Unbraced Length (Lu)	16.5 in	
Effective Length Factor (K)	1	
Strength of Bridge Stiffener:		
Fy	65 ksi	
Fu	80 ksi	
Effective Length of Member (Lc)	16.50 in	[AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	87.6 ksi	[AISC 15th Edition, Eq. E3-4]
Limit	99.5	
Determination of Critical Stress (Fcr)	47.6 ksi	
[AISC 15th Edition, Eqs. E3-2 and E3-3]		

Allowable Compressive Strength (ϕP_n)	193.0 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp) 62.7% Pass

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 100.917 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t) 263.3 kips
 [AISC 15th Ed., Ch.D2]

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.00 in
 Net Area (A_{net}) 3.250 in²
 Net Area Limitation (A_e) 3.250 in²
 Available Fractile Strength (ϕP_{tr}) 195.0 kips

Tension Check

Controlling Mode of Failure (Check mode) Fracture Controls
 (ϕP_{nt}) 195.0 kips
 Controlling Tension Mode Check (Checktension) **62.1%** **Pass**

SUMMARY

tnxTower Reactions

M 1347.7 kip-ft
 P 37.3 kip
 V 28.3 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.00 in
 Bolt Circle of Flange Bolts (BCbolts) 45.0 in
 Loads to Flange Bolts

Mbolts 611.4 kip-ft
 P 37.3 kip
 V 28.3 kip } See Flange tool for Flange Bolt and Plate Capacities

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M_{exist}) 736.1 kip-ft
 Number of Existing Bridge Stiffeners (N_{exist}) 6
 Thickness (t_{exist}) 1.00 in
 Width (w_{exist}) 4.50 in
 Controlling Capacity of Existing Bridge Stiffeners (Capacity_{max}) **62.7%** **Pass**

Monopole Flange Plate Connection

Elevation = 100.917 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0

Applied Loads	
Moment (kip-ft)	611.40
Axial Force (kips)	37.30
Shear Force (kips)	28.30


TIA-222 Revision	H
------------------	---

*TIA-222-H Section 15.5 Applied

Top Plate - External



Bottom Plate - Internal



Connection Properties

Bolt Data

(32) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 45" BC

Top Plate Data

48" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Plate Data

42" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

(32) 5"H x 3"W x 0.625"T, Notch: 0.75"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Bottom Stiffener Data

N/A

Top Pole Data

42" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Pole Data

48" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	19.21
Allowable (kips)	54.52
Stress Rating:	33.6% Pass

Top Plate Capacity

Max Stress (ksi):	12.76	(Roark's Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	37.5%	Pass
Tension Side Stress Rating:	N/A	

Bottom Plate Capacity

Max Stress (ksi):	13.37	(Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	39.3%	Pass
Tension Side Stress Rating:	N/A	

Top Stiffener Capacity

Horizontal Weld:	38.5%	Pass
Vertical Weld:	24.7%	Pass
Plate Flexure+Shear:	15.3%	Pass
Plate Tension+Shear:	27.0%	Pass
Plate Compression:	36.7%	Pass

Bottom Stiffener Capacity

Horizontal Weld:	N/A
Vertical Weld:	N/A
Plate Flexure+Shear:	N/A
Plate Tension+Shear:	N/A
Plate Compression:	N/A

Top Pole Capacity

Punching Shear:	12.6%	Pass
-----------------	--------------	-------------

Bottom Pole Capacity

Punching Shear:	N/A
-----------------	------------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 80.833 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **80.833** ft Apply TIA-222-H Section 15.5?

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	1959.755 k-ft
Axial Load (P)	48.015 kip
Shear Load (V)	32.626 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	48 in
Upper Shaft Thickness (t1)	0.375 in
Lower Shaft Diameter (Dshaft2)	54 in
Lower Shaft Thickness (t2)	0.375 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	3	3
Thickness of Proposed Bridge Stiffeners (texist)	1 in	1.25 in
Width of Proposed Bridge Stiffeners (wexist)	4.5 in	6.5 in
Existing Bridge Stiffener Grade:		
Fyex	65 ksi	65 ksi
Fuex	80 ksi	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	55 in	55.126 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	4.5 in ²	8.125 in ²
Radius of Gyration about x-axis (rx)	0.289 in	0.361 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	14462 in ⁴	

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	36
Diameter of Flange Bolts	1 in
Bolt Circle of Flange Bolts (BCbolts)	51 in
Gross Area of One Flange Bolt (Ag_bolts)	0.785 in ²
Moment of Inertia of Flange Bolts (Ibolts)	9193 in ⁴

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 80.833 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	41.77 in ²
Total Moment of Inertia (Itotal)	23655 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	1198.2 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	761.6 kip-ft
Axial Reaction to Flange Bolts (Pbolts)	48.0 kips
Shear Reaction to Flange Bolts (Vbolts)	32.6 kips

**Check Flange Connection
with these Reactions**

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing Bridge

Outer Radius of Bolt Circle (C)	27.5 in
Critical Compression Bending Stress (Pcomp)	123.0 kips
Critical Tension Bending Stress (Ptens)	123.0 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9
Unbraced Length (Lu)	16 in
Effective Length Factor (K)	1
Strength of Bridge Stiffener:	
Fy	65 ksi
Fu	80 ksi
Effective Length of Member (Lc)	16.00 in [AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	93.2 ksi [AISC 15th Edition, Eq. E3-4]
Limit	99.5
Determination of Critical Stress (Fcr)	48.5 ksi
[AISC 15th Edition, Eqs. E3-2 and E3-3]	

Allowable Compressive Strength (ϕP_n)	196.6 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp)

59.6% Pass

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 80.833 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t) [AISC 15th Ed., Ch.D2] 263.3 kips

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.00 in
 Net Area (A_{net}) 3.250 in²
 Net Area Limitation (A_e) 3.250 in²
 Available Fractile Strength (ϕP_{tr}) 195.0 kips

Tension Check

Controlling Mode of Failure (Check mode) (ϕP_{nt}) Fracture Controls 195.0 kips
 Controlling Tension Mode Check (Checktension) **60.1%** **Pass**

SUMMARY

tnxTower Reactions

M 1959.8 kip-ft
 P 48.0 kip
 V 32.6 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.00 in
 Bolt Circle of Flange Bolts (BCbolts) 51.0 in
 Loads to Flange Bolts

Mbolts 761.6 kip-ft } See Flange tool for Flange
 P 48.0 kip } Bolt and Plate Capacities
 V 32.6 kip }

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M_{exist}) 1198.2 kip-ft
 Number of Existing Bridge Stiffeners (N_{exist}) 3
 Thickness (t_{exist}) 1.00 in
 Width (w_{exist}) 4.50 in
 Controlling Capacity of Existing Bridge Stiffeners (Capacity_{max}) **60.1%** **Pass**

Monopole Flange Plate Connection

Elevation = 80.833 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0
TIA-222 Revision	H


Applied Loads	
Moment (kip-ft)	761.60
Axial Force (kips)	48.00
Shear Force (kips)	32.60

*TIA-222-H Section 15.5 Applied

Top Plate - External



Bottom Plate - Internal



Connection Properties

Bolt Data

(36) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 51" BC

Top Plate Data

54" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

(36) 5"H x 3"W x 0.625"T, Notch: 0.75"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Top Pole Data

48" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Plate Data

48" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Stiffener Data

N/A

Bottom Pole Data

54" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	18.57
Allowable (kips)	54.52
Stress Rating:	32.4% Pass

Top Plate Capacity

Max Stress (ksi):	12.58	(Roark's Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	37.0%	Pass
Tension Side Stress Rating:	N/A	

Top Stiffener Capacity

Horizontal Weld:	37.3%	Pass
Vertical Weld:	24.0%	Pass
Plate Flexure+Shear:	14.8%	Pass
Plate Tension+Shear:	26.1%	Pass
Plate Compression:	35.6%	Pass

Top Pole Capacity

Punching Shear:	12.2%	Pass
-----------------	--------------	-------------

Bottom Plate Capacity

Max Stress (ksi):	13.16	(Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	38.7%	Pass
Tension Side Stress Rating:	N/A	

Bottom Stiffener Capacity

Horizontal Weld:	N/A
Vertical Weld:	N/A
Plate Flexure+Shear:	N/A
Plate Tension+Shear:	N/A
Plate Compression:	N/A

Bottom Pole Capacity

Punching Shear:	N/A
-----------------	------------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 60.583 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **60.58** ft Apply TIA-222-H Section 15.5?

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	2669.076 k-ft
Axial Load (P)	66.333 kip
Shear Load (V)	37.568 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	54 in
Upper Shaft Thickness (t1)	0.375 in
Lower Shaft Diameter (Dshaft2)	60 in
Lower Shaft Thickness (t2)	0.375 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	4	6
Thickness of Proposed Bridge Stiffeners (texist)	1 in	1.25 in
Width of Proposed Bridge Stiffeners (wexist)	4.5 in	8.5 in
Existing Bridge Stiffener Grade:		
Fyex	65 ksi	65 ksi
Fuex	80 ksi	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	61 in	61.836 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	4.5 in ²	10.625 in ²
Radius of Gyration about x-axis (rx)	0.289 in	0.361 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	34387 in ⁴	

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	48
Diameter of Flange Bolts	1 in
Bolt Circle of Flange Bolts (BCbolts)	57 in
Gross Area of One Flange Bolt (Ag_bolts)	0.785 in ²
Moment of Inertia of Flange Bolts (Ibolts)	15311 in ⁴

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 60.583 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	119.45 in ²
Total Moment of Inertia (Itotal)	49737 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	1845.4 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	821.6 kip-ft	} Check Flange Connection with these Reactions
Axial Reaction to Flange Bolts (Pbolts)	66.3 kips	
Shear Reaction to Flange Bolts (Vbolts)	37.6 kips	

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing

Outer Radius of Bolt Circle (C)	30.5 in
Critical Compression Bending Stress (Pcomp)	88.4 kips
Critical Tension Bending Stress (Ptens)	88.4 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9	
Unbraced Length (Lu)	16.5 in	
Effective Length Factor (K)	1	
Strength of Bridge Stiffener:		
Fy	65 ksi	
Fu	80 ksi	
Effective Length of Member (Lc)	16.50 in	[AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	87.6 ksi	[AISC 15th Edition, Eq. E3-4]
Limit	99.5	
Determination of Critical Stress (Fcr)	47.6 ksi	
[AISC 15th Edition, Eqs. E3-2 and E3-3]		

Allowable Compressive Strength (ϕP_n)	193.0 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp)	43.6%	Pass
--	-------	------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 60.583 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t)
[AISC 15th Ed., Ch.D2] 263.3 kips

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.00 in
 Net Area (A_{net}) 3.250 in²
 Net Area Limitation (A_e) 3.250 in²
 Available Fractile Strength (ϕP_{tr}) 195.0 kips

Tension Check

Controlling Mode of Failure (Check mode)
(ϕP_{nt}) Fracture Controls
195.0 kips
 Controlling Tension Mode Check (Checktension) **43.2%** **Pass**

SUMMARY

tnxTower Reactions

M 2669.1 kip-ft
 P 66.3 kip
 V 37.6 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.00 in
 Bolt Circle of Flange Bolts (BCbolts) 57.0 in
 Loads to Flange Bolts

Mbolts 821.6 kip-ft
 P 66.3 kip
 V 37.6 kip

} See Flange tool for Flange Bolt and Plate Capacities

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M_{exist}) 1845.4 kip-ft
 Number of Existing Bridge Stiffeners (N_{exist}) 4
 Thickness (t_{exist}) 1.00 in
 Width (w_{exist}) 4.50 in
 Controlling Capacity of Existing Bridge Stiffeners (Capacity_{max}) **43.6%** **Pass**

Monopole Flange Plate Connection

Elevation = 60.583 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0
TIA-222 Revision	H


Applied Loads	
Moment (kip-ft)	821.60
Axial Force (kips)	66.30
Shear Force (kips)	37.60

*TIA-222-H Section 15.5 Applied

Top Plate - External



Bottom Plate - Internal



Connection Properties

Bolt Data

(48) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 57" BC

Top Plate Data

60" OD x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

N/A

Top Pole Data

54" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Plate Data

54" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Stiffener Data

N/A

Bottom Pole Data

60" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	13.03
Allowable (kips)	54.53
Stress Rating:	22.8% Pass

Top Plate Capacity

Max Stress (ksi):	11.12	(Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	32.7%	Pass
Tension Side Stress Rating:	10.1%	Pass

Bottom Plate Capacity

Max Stress (ksi):	11.73	(Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	34.5%	Pass
Tension Side Stress Rating:	N/A	

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 40.333 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **40.33** ft New Apply TIA-222-H Section 15.5?

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	3471.755 k-ft
Axial Load (P)	80.284 kip
Shear Load (V)	41.688 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	60 in
Upper Shaft Thickness (t1)	0.375 in
Lower Shaft Diameter (Dshaft2)	60 in
Lower Shaft Thickness (t2)	0.5 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	6	4
Thickness of Proposed Bridge Stiffeners (texist)	1.25 in	1 in
Width of Proposed Bridge Stiffeners (wexist)	6.5 in	6 in
Existing Bridge Stiffener Grade:		
Fyex	65 ksi	65 ksi
Fuex	80 ksi	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	63.75 in	63.5 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	8.125 in ²	6 in ²
Radius of Gyration about x-axis (rx)	0.361 in	0.289 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	33930 in ⁴	

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	32	32
Diameter of Flange Bolts	1 1/4 in	1 1/4 in
Bolt Circle of Flange Bolts (BCbolts)	47 in	53 in
Gross Area of One Flange Bolt (Ag_bolts)	1.227 in ²	1.227 in ²
Moment of Inertia of Flange Bolts (Ibolts)	31535 in ⁴	

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 40.333 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	151.29 in ²
Total Moment of Inertia (Itotal)	65466 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	1799.4 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	1672.4 kip-ft	} Check Flange Connection with these Reactions
Axial Reaction to Flange Bolts (Pbolts)	80.3 kips	
Shear Reaction to Flange Bolts (Vbolts)	41.7 kips	

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing

Outer Radius of Bolt Circle (C)	31.875 in
Critical Compression Bending Stress (Pcomp)	164.8 kips
Critical Tension Bending Stress (Ptens)	164.8 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9	
Unbraced Length (Lu)	16 in	
Effective Length Factor (K)	1	
Strength of Bridge Stiffener:		
Fy	65 ksi	
Fu	80 ksi	
Effective Length of Member (Lc)	16.00 in	[AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	145.6 ksi	[AISC 15th Edition, Eq. E3-4]
Limit	99.5	
Determination of Critical Stress (Fcr)	53.9 ksi	
[AISC 15th Edition, Eqs. E3-2 and E3-3]		

Allowable Compressive Strength (ϕP_n)	394.3 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp)	39.8%	Pass
--	-------	------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 40.333 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t) 475.3 kips
 [AISC 15th Ed., Ch.D2]

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.25 in
 Net Area (A_{net}) 6.563 in²
 Net Area Limitation (A_e) 6.563 in²
 Available Fractile Strength (ϕP_{tr}) 393.8 kips

Tension Check

Controlling Mode of Failure (Check mode) Fracture Controls
 (ϕP_{nt}) 393.8 kips
 Controlling Tension Mode Check (Checktension) **39.9%** **Pass**

SUMMARY

tnxTower Reactions

M 3471.8 kip-ft
 P 80.3 kip
 V 41.7 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.25 in
 Bolt Circle of Flange Bolts (BCbolts) 47.0 in
 Loads to Flange Bolts

Mbolts 1672.4 kip-ft
 P 80.3 kip
 V 41.7 kip } See Flange tool for Flange Bolt and Plate Capacities

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M_{exist}) 1799.4 kip-ft
 Number of Existing Bridge Stiffeners (N_{exist}) 6
 Thickness (t_{exist}) 1.25 in
 Width (w_{exist}) 6.50 in
 Controlling Capacity of Existing Bridge Stiffeners (Capacity_{max}) **39.9%** **Pass**

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 40.333 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **40.33** ft Apply TIA-222-H Section 15.5?

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	3471.755 k-ft
Axial Load (P)	80.284 kip
Shear Load (V)	41.688 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	60 in
Upper Shaft Thickness (t1)	0.375 in
Lower Shaft Diameter (Dshaft2)	60 in
Lower Shaft Thickness (t2)	0.5 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	6	4
Thickness of Proposed Bridge Stiffeners (texist)	1.25 in	1 in
Width of Proposed Bridge Stiffeners (wexist)	6.5 in	6 in
Existing Bridge Stiffener Grade:		
Fyex	65 ksi	65 ksi
Fuex	80 ksi	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	63.75 in	63.5 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	8.125 in ²	6 in ²
Radius of Gyration about x-axis (rx)	0.361 in	0.289 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	33930 in ⁴	

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	32	32
Diameter of Flange Bolts	1 1/4 in	1 1/4 in
Bolt Circle of Flange Bolts (BCbolts)	47 in	53 in
Gross Area of One Flange Bolt (Ag_bolts)	1.227 in ²	1.227 in ²
Moment of Inertia of Flange Bolts (Ibolts)	31535 in ⁴	

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 40.333 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	151.29 in ²
Total Moment of Inertia (Itotal)	65466 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	1799.4 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	1672.4 kip-ft	} Check Flange Connection with these Reactions
Axial Reaction to Flange Bolts (Pbolts)	80.3 kips	
Shear Reaction to Flange Bolts (Vbolts)	41.7 kips	

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing

Outer Radius of Bolt Circle (C)	31.875 in
Critical Compression Bending Stress (Pcomp)	164.8 kips
Critical Tension Bending Stress (Ptens)	164.8 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9	
Unbraced Length (Lu)	25 in	
Effective Length Factor (K)	1	
Strength of Bridge Stiffener:		
Fy	65 ksi	
Fu	80 ksi	
Effective Length of Member (Lc)	25.00 in	[AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	59.6 ksi	[AISC 15th Edition, Eq. E3-4]
Limit	99.5	
Determination of Critical Stress (Fcr)	41.2 ksi	
[AISC 15th Edition, Eqs. E3-2 and E3-3]		

Allowable Compressive Strength (ϕP_n)	301.2 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp)	52.1%	Pass
--	-------	------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 40.333 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t) 475.3 kips
 [AISC 15th Ed., Ch.D2]

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.25 in
 Net Area (A_{net}) 6.563 in²
 Net Area Limitation (A_e) 6.563 in²
 Available Fractile Strength (ϕP_{tr}) 393.8 kips

Tension Check

Controlling Mode of Failure (Check mode) Fracture Controls
 (ϕP_{nt}) 393.8 kips
 Controlling Tension Mode Check (Checktension) **39.9%** **Pass**

SUMMARY

tnxTower Reactions

M 3471.8 kip-ft
 P 80.3 kip
 V 41.7 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.25 in
 Bolt Circle of Flange Bolts (BCbolts) 47.0 in
 Loads to Flange Bolts

Mbolts 1672.4 kip-ft } See Flange tool for Flange
 P 80.3 kip } Bolt and Plate Capacities
 V 41.7 kip }

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M_{exist}) 1799.4 kip-ft
 Number of Existing Bridge Stiffeners (N_{exist}) 6
 Thickness (t_{exist}) 1.25 in
 Width (w_{exist}) 6.50 in
 Controlling Capacity of Existing Bridge Stiffeners (Capacity_{max}) **52.1%** **Pass**

Monopole Flange Plate Connection

Elevation = 40.333 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0

Applied Loads	
Moment (kip-ft)	1672.40
Axial Force (kips)	80.30
Shear Force (kips)	41.70


TIA-222 Revision	H
------------------	---

*TIA-222-H Section 15.5 Applied

Top Plate - Internal



Bottom Plate - Internal



Connection Properties

Bolt Data

GROUP 1: (32) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 53" BC
 GROUP 2: (32) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 47" BC

Top Plate Data

45" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

(32) 10"H x 7"W x 0.625"T, Notch: 0.5"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Top Pole Data

60" x 0.375" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Plate Data

45" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Stiffener Data

(32) 10"H x 7"W x 0.625"T, Notch: 0.5"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Bottom Pole Data

60" x 0.5" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	25.24
Allowable (kips)	54.53
Stress Rating:	44.1% Pass

Top Plate Capacity

Max Stress (ksi):	15.20	(Roark's Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	44.7%	Pass
Tension Side Stress Rating:	N/A	

Top Stiffener Capacity

Horizontal Weld:	35.9%	Pass
Vertical Weld:	31.4%	Pass
Plate Flexure+Shear:	20.9%	Pass
Plate Tension+Shear:	25.0%	Pass
Plate Compression:	51.7%	Pass

Top Pole Capacity

Punching Shear:	16.9%	Pass
-----------------	--------------	-------------

Bottom Plate Capacity

Max Stress (ksi):	15.45	(Roark's Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	45.4%	Pass
Tension Side Stress Rating:	N/A	

Bottom Stiffener Capacity

Horizontal Weld:	31.7%	Pass
Vertical Weld:	27.7%	Pass
Plate Flexure+Shear:	17.9%	Pass
Plate Tension+Shear:	21.7%	Pass
Plate Compression:	45.6%	Pass

Bottom Pole Capacity

Punching Shear:	11.2%	Pass
-----------------	--------------	-------------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 20.083 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **20.08** ft

Apply TIA-222-H Section 15.5?

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	4352.32 k-ft
Axial Load (P)	95.121 kip
Shear Load (V)	45.18 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	60 in
Upper Shaft Thickness (t1)	0.5 in
Lower Shaft Diameter (Dshaft2)	60 in
Lower Shaft Thickness (t2)	0.625 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	6	4
Thickness of Proposed Bridge Stiffeners (texist)	1.25 in	1 in
Width of Proposed Bridge Stiffeners (wexist)	6.5 in	6 in
Existing Bridge Stiffener Grade:		
Fyex	65 ksi	65 ksi
Fuex	80 ksi	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	63.75 in	63.5 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	8.125 in ²	6 in ²
Radius of Gyration about x-axis (rx)	0.361 in	0.289 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	35505 in ⁴	

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	32	32
Diameter of Flange Bolts	1 1/4 in	1 1/4 in
Bolt Circle of Flange Bolts (BCbolts)	47 in	53 in
Gross Area of One Flange Bolt (Ag_bolts)	1.227 in ²	1.227 in ²
Moment of Inertia of Flange Bolts (Ibolts)	49270 in ⁴	

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 20.083 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	151.29 in ²
Total Moment of Inertia (Itotal)	84837 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	1821.5 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	2527.7 kip-ft	} Check Flange Connection with these Reactions
Axial Reaction to Flange Bolts (Pbolts)	95.1 kips	
Shear Reaction to Flange Bolts (Vbolts)	45.2 kips	

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing

Outer Radius of Bolt Circle (C)	31.875 in
Critical Compression Bending Stress (Pcomp)	159.4 kips
Critical Tension Bending Stress (Ptens)	159.4 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9	
Unbraced Length (Lu)	16 in	
Effective Length Factor (K)	1	
Strength of Bridge Stiffener:		
Fy	65 ksi	
Fu	80 ksi	
Effective Length of Member (Lc)	16.00 in	[AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	145.6 ksi	[AISC 15th Edition, Eq. E3-4]
Limit	99.5	
Determination of Critical Stress (Fcr)	53.9 ksi	
[AISC 15th Edition, Eqs. E3-2 and E3-3]		

Allowable Compressive Strength (ϕP_n)	394.3 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp)	38.5%	Pass
--	-------	------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 20.083 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t) [AISC 15th Ed., Ch.D2] 475.3 kips

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.25 in
 Net Area (A_{net}) 6.563 in²
 Net Area Limitation (A_e) 6.563 in²
 Available Fractile Strength (ϕP_{tr}) 393.8 kips

Tension Check

Controlling Mode of Failure (Check mode) (ϕP_{nt}) Fracture Controls 393.8 kips
 Controlling Tension Mode Check (Checktension) **38.6%** **Pass**

SUMMARY

tnxTower Reactions

M 4352.3 kip-ft
 P 95.1 kip
 V 45.2 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.25 in
 Bolt Circle of Flange Bolts (BCbolts) 47.0 in
 Loads to Flange Bolts

Mbolts 2527.7 kip-ft
 P 95.1 kip
 V 45.2 kip } See Flange tool for Flange Bolt and Plate Capacities

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M_{exist}) 1821.5 kip-ft
 Number of Existing Bridge Stiffeners (N_{exist}) 6
 Thickness (t_{exist}) 1.25 in
 Width (w_{exist}) 6.50 in
 Controlling Capacity of Existing Bridge Stiffeners (Capacity_{max}) **38.6%** **Pass**

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 20.083 ft		
DATE	07-13-19	PAGE	1 OF 3



V1.0.1

Bolted Bridge Stiffeners Reinforcement Check

Assumptions / Notes:

1. For design purposes, it is assumed that the proposed bridge stiffeners are to take the full load.
2. The plastification of the pole is not considered.
3. All shear and axial loads are taken by the flange bolts.

1. PARAMETERS

Elevation **20.08** ft Apply TIA-222-H Section 15.5?

Rev. H
Yes

1.1 tnxTower Reactions

Moment (M)	4352.32 k-ft
Axial Load (P)	95.121 kip
Shear Load (V)	45.18 kips

1.2 Shaft Properties at the Flange

Upper Shaft Diameter (Dshaft1)	60 in
Upper Shaft Thickness (t1)	0.5 in
Lower Shaft Diameter (Dshaft2)	60 in
Lower Shaft Thickness (t2)	0.625 in
Shaft Grade:	
Fyshaft	42 ksi
Fushaft	63 ksi

1.3 Existing Bridge Stiffeners Properties

(Verify existing bolted connection for reduced moment.)

Number of Proposed Bridge Stiffeners (Nexist)	6	4
Thickness of Proposed Bridge Stiffeners (texist)	1.25 in	1 in
Width of Proposed Bridge Stiffeners (wexist)	6.5 in	6 in
Existing Bridge Stiffener Grade:		
Fyex	65 ksi	65 ksi
Fuex	80 ksi	80 ksi
Diameter to the centroid of Existing Bridge Stiffeners (BCexist)	63.75 in	63.5 in
Gross Area of One Existing Bridge Stiffener (Ag_exist)	8.125 in ²	6 in ²
Radius of Gyration about x-axis (rx)	0.361 in	0.289 in
Moment of Inertia of Existing Bridge Stiffeners (Iexist)	35505 in ⁴	

1.4 Flange Bolt Properties

Number of Flange Bolts (Nbolts)	32	32
Diameter of Flange Bolts	1 1/4 in	1 1/4 in
Bolt Circle of Flange Bolts (BCbolts)	47 in	53 in
Gross Area of One Flange Bolt (Ag_bolts)	1.227 in ²	1.227 in ²
Moment of Inertia of Flange Bolts (Ibolts)	49270 in ⁴	

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 20.083 ft		
DATE	07-13-19	PAGE 2	OF 3



V1.0.1

1.5 Division of Forces

Total Gross Area (Ag_total)	151.29 in ²
Total Moment of Inertia (Itotal)	84837 in ⁴

1.6 Reactions to Existing Bridge Stiffeners

Moment Reaction to Existing Bridge Stiffeners (Mexist)	1821.5 kip-ft
Axial Reaction to Existing Bridge Stiffeners (Pexist)	0.0 kips
Shear Reaction to Flange Bolts (Vexist)	0.0 kips

1.7 Reactions to Flange Bolts

(It is assumed that all shear and axial loads are taken by the flange bolts)

Moment Reaction to Flange Bolts (Mbolts)	2527.7 kip-ft
Axial Reaction to Flange Bolts (Pbolts)	95.1 kips
Shear Reaction to Flange Bolts (Vbolts)	45.2 kips

Check Flange Connection with these Reactions

2. Existing Bridge Stiffener

2.1 Maximum Axial Forces in Single Existing

Outer Radius of Bolt Circle (C)	31.875 in
Critical Compression Bending Stress (Pcomp)	159.4 kips
Critical Tension Bending Stress (Ptens)	159.4 kips

2.2 Available Compression Strength

[AISC 15th Edition E3-1]

Resistance Factor (ϕ_c)	0.9	
Unbraced Length (Lu)	24 in	
Effective Length Factor (K)	1	
Strength of Bridge Stiffener:		
Fy	65 ksi	
Fu	80 ksi	
Effective Length of Member (Lc)	24.00 in	[AISC 15th Edition E3-2]
Elastic Buckling Stress (Fe)	64.7 ksi	[AISC 15th Edition, Eq. E3-4]
Limit	99.5	
Determination of Critical Stress (Fcr)	42.7 ksi	
[AISC 15th Edition, Eqs. E3-2 and E3-3]		

Allowable Compressive Strength (ϕP_n)	312.2 kips
[AISC 15th Ed., Eqs. J4-6 and E3-1]	

Check Compressive Strength (Checkcomp)	48.6%	Pass
--	-------	------

PROJECT	87581.023.01 - Newington_1, CT Intiti		
SUBJECT	Bridge Stiffener - 20.083 ft		
DATE	07-13-19	PAGE 3	OF 3



V1.0.1

2.3 Available Tension Strength

Gross Section Yield

Available Tension Yield Strength (ϕP_t) 475.3 kips
 [AISC 15th Ed., Ch.D2]

Net Section Fracture

Bolt Hole Diameter (BH) 1.188 in
 Thickness (T) 1.25 in
 Net Area (A_{net}) 6.563 in²
 Net Area Limitation (A_e) 6.563 in²
 Available Fractile Strength (ϕP_{tr}) 393.8 kips

Tension Check

Controlling Mode of Failure (Check mode) (φP _{nt})	Fracture Controls
Controlling Tension Mode Check (Checktension)	393.8 kips
	38.6% Pass

SUMMARY

tnxTower Reactions

M 4352.3 kip-ft
 P 95.1 kip
 V 45.2 kip

Flange Bolts

Diameter of Flange Bolts (Dbolts) 1.25 in
 Bolt Circle of Flange Bolts (BCbolts) 47.0 in
 Loads to Flange Bolts

Mbolts	2527.7 kip-ft	} See Flange tool for Flange Bolt and Plate Capacities
P	95.1 kip	
V	45.2 kip	

Existing Jump Plates

Moment to Existing Bridge Stiffeners (M _{exist})	1821.5 kip-ft
Number of Existing Bridge Stiffeners (N _{exist})	6
Thickness (t _{exist})	1.25 in
Width (w _{exist})	6.50 in
Controlling Capacity of Existing Bridge Stiffeners (Capacity _{max})	48.6% Pass

Monopole Flange Plate Connection

Elevation = 20.083 ft.




BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0
TIA-222 Revision	H


Applied Loads	
Moment (kip-ft)	2527.70
Axial Force (kips)	95.10
Shear Force (kips)	45.20

*TIA-222-H Section 15.5 Applied

Top Plate - Internal



Bottom Plate - Internal



Connection Properties

Bolt Data

GROUP 1: (32) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 53" BC
 GROUP 2: (32) 1" ϕ bolts (A325 N; Fy=92 ksi, Fu=120 ksi) on 47" BC

Top Plate Data

45" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Top Stiffener Data

(32) 10"H x 7"W x 0.625"T, Notch: 0.5"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Top Pole Data

60" x 0.5" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Bottom Plate Data

45" ID x 1.25" Plate (A36; Fy=36 ksi, Fu=58 ksi)

Bottom Stiffener Data

(32) 10"H x 7"W x 0.625"T, Notch: 0.5"
 plate: Fy= 36 ksi ; weld: Fy= 70 ksi
 horiz. weld: 0.3125" fillet
 vert. weld: 0.3125" fillet

Bottom Pole Data

60" x 0.625" round pole (A53-B-42; Fy=42 ksi, Fu=63 ksi)

Analysis Results

Bolt Capacity

Max Load (kips)	38.55
Allowable (kips)	54.53
Stress Rating:	67.3% Pass

Top Plate Capacity

Max Stress (ksi):	23.12	(Roark's Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	67.9%	Pass
Tension Side Stress Rating:	N/A	

Top Stiffener Capacity

Horizontal Weld:	47.3%	Pass
Vertical Weld:	41.3%	Pass
Plate Flexure+Shear:	29.6%	Pass
Plate Tension+Shear:	34.3%	Pass
Plate Compression:	68.1%	Pass

Top Pole Capacity

Punching Shear:	16.7%	Pass
-----------------	--------------	-------------

Bottom Plate Capacity

Max Stress (ksi):	23.51	(Roark's Flexural)
Allowable Stress (ksi):	32.40	
Stress Rating:	69.1%	Pass
Tension Side Stress Rating:	N/A	

Bottom Stiffener Capacity

Horizontal Weld:	42.5%	Pass
Vertical Weld:	36.2%	Pass
Plate Flexure+Shear:	25.0%	Pass
Plate Tension+Shear:	30.3%	Pass
Plate Compression:	60.3%	Pass

Bottom Pole Capacity

Punching Shear:	11.6%	Pass
-----------------	--------------	-------------

Monopole Base Plate Connection




Site Info	
BU #	826217
Site Name	Newington_1, CT
Order #	498392, Rev# 0

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
l_{ar} (in)	1.25

Applied Loads	
Moment (kip-ft)	5285.89
Axial Force (kips)	109.95
Shear Force (kips)	47.70

*TIA-222-H Section 15.5 Applied



Connection Properties	Analysis Results
-----------------------	------------------

Anchor Rod Data
GROUP 1: (52) 1-1/4" ϕ bolts (A687 N; $F_y=105$ ksi, $F_u=125$ ksi) on 67" BC
GROUP 2: (10) 2-1/4" ϕ bolts (A687 N; $F_y=105$ ksi, $F_u=125$ ksi) on 92.3" BC
Base Plate Data
70" OD x 1.25" Plate (A36; $F_y=36$ ksi, $F_u=58$ ksi)
Stiffener Data
(52) 6"H x 5"W x 0.5"T, Notch: 0.5"
plate: $F_y=36$ ksi ; weld: $F_y=70$ ksi
horiz. weld: 0.3125" fillet
vert. weld: 0.3125" fillet
Pole Data
60" x 0.625" round pole (A53-B-42; $F_y=42$ ksi, $F_u=63$ ksi)

Anchor Rod Summary	<i>(units of kips, kip-in)</i>	
GROUP 1:		
$P_{u_c} = 34.85$	$\phi P_{n_c} = 101.75$	Stress Rating
$V_u = 0.92$	$\phi V_n = 30.52$	32.7%
$M_u = n/a$	$\phi M_n = n/a$	Pass
GROUP 2:		
$P_{u_c} = 151.26$	$\phi P_{n_c} = 341.25$	Stress Rating
$V_u = 0$	$\phi V_n = 102.38$	42.2%
$M_u = n/a$	$\phi M_n = n/a$	Pass
Base Plate Summary		
Max Stress (ksi):	2.79	(Shear)
Allowable Stress (ksi):	21.6	
Stress Rating:	12.3%	Pass
Stiffener Summary		
Horizontal Weld:	35.8%	Pass
Vertical Weld:	39.0%	Pass
Plate Flexure+Shear:	36.4%	Pass
Plate Tension+Shear:	32.5%	Pass
Plate Compression:	77.8%	Pass
Pole Summary		
Punching Shear:	13.5%	Pass

PROJECT	87581.023.01 - Newington_1, CT
SUBJECT	Anchor Rod Bracket Analysis
DATE	07-13-19



V3.3.0

Analysis Criteria	
Design or Analysis?	Analysis
AR Load Considered	Current Load
Current load	151.26 kips
AR Capacity	341.3 kips

Tower Type	Monopole
------------	----------

Post-Installed Adhesive AR Modification	
Size	2.25 in
Quantity	10
Bolt Circle	92.3 in
Grade	F1554-105
Fy	105 ksi
Fu	125 ksi

TIA-222 Rev.	H
Apply TIA-222-H Section 15.5?	Yes

Anchor Rod Bracket Analysis Checks		
Tube Bearing	26.3%	-
Tube Compression	N/A	-
Gusset Shear Yield	28.1%	-
Gusset Shear Rupture	30.5%	-
Gusset Flexure	N/A	-
Welds	Gusset to Tower and BP	51.4%
	Gusset to Tube	39.4%
	Geometry	N/A
Tower Punching	36.3%	-
Tube Punching	44.7%	-
Utilization	51.4%	

Manufacturers Tower Properties	
Pole Thickness	0.625 in
Pole Grade	Custom
Fy	42 ksi
Fu	63 ksi
Base Plate Gr.	A36
Fy	36 ksi
Fu	58 ksi
Anchor Rods	
Size	1.25 in
Quantity	52
Bolt Circle	67 in
Grade	A687
Fy	105 ksi
Fu	125 ksi

Bracket Properties	
Gusset	Pipe/Tube
Thickness	1.25 in
Width at Tube	14.875 in
Height at Pole	36 in
Height at Tube	10.5 in
Grade	A572-65
Fy	65 ksi
Fu	80 ksi
Size	4 XXS Pipe
Total Length	10.5 in
Length above Gusset	0 in
Length below Gusset	0 in
Grade	Custom
Fy	50 ksi
Fu	65 ksi
Weld - Gusset to Tower	Weld - Gusset to Pipe/Tube
FEXX	70 ksi
Weld Type	Double Fillet
Fillet Size	3/8 in
FEXX	80 ksi
Weld Type	Double Bevel+Fillet
Fillet Size	1/2 in
Bevel Depth	1/2 in
Length	36 in
Load Angle	45 deg.
Weld - Gusset to Base Plate	
FEXX	70 ksi
Weld Type	Double Bevel+Fillet
Fillet Size	1/2 in
Bevel Depth	1/2 in
Gap	0 in
Notch (horiz)	0.75 in
Notch (vert)	0.75 in
Pipe/Tube Welded to Base/Footpad?	Yes
Fillet Size	1/2 in

Pier and Pad Foundation



BU #: 826217
Site Name: Newington_1, CT
App. Number: 498392, Rev# 0

TIA-222 Revision: H
Tower Type: Monopole

Top & Bot. Pad Rein. Different?:
Block Foundation?:

Superstructure Analysis Reactions		
Compression, P_{comp} :	110	kips
Base Shear, V_{u_comp} :	48	kips
Moment, M_u :	4086	ft-kips
Tower Height, H :	191.667	ft
BP Dist. Above Fdn, bp_{dist} :	2.5	in

Foundation Analysis Checks				
	Capacity	Demand	Rating*	Check
<i>Lateral (Sliding) (kips)</i>	334.77	48.00	13.7%	Pass
<i>Bearing Pressure (ksf)</i>	12.00	4.56	38.0%	Pass
<i>Overturing (kip*ft)</i>	6449.73	4552.00	70.6%	Pass
<i>Pier Flexure (Comp.) (kip*ft)</i>	5688.21	4422.00	74.0%	Pass
<i>Pier Compression (kip)</i>	24494.62	158.49	0.6%	Pass
<i>Pad Flexure (kip*ft)</i>	4887.26	2110.59	41.1%	Pass
<i>Pad Shear - 1-way (kips)</i>	580.76	419.98	68.9%	Pass
<i>Pad Shear - 2-way (Comp) (ksi)</i>	0.190	0.000	0.0%	Pass
<i>Flexural 2-way (Comp) (kip*ft)</i>	6892.45	2653.20	36.7%	Pass

Pier Properties		
Pier Shape:	Circular	
Pier Diameter, dpier :	7	ft
Ext. Above Grade, E :	0.5	ft
Pier Rebar Size, Sc :	9	
Pier Rebar Quantity, mc :	34	
Pier Tie/Spiral Size, St :	4	
Pier Tie/Spiral Quantity, mt :	11	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, cc_{pier} :	3	in

*Rating per TIA-222-H Section 15.5

Soil Rating*:	70.6%
Structural Rating*:	74.0%

Pad Properties		
Depth, D :	9	ft
Pad Width, W :	20.5	ft
Pad Thickness, T :	2.5	ft
Pad Rebar Size (Bottom), Sp :	11	
Pad Rebar Quantity (Bottom), mp :	30	
Pad Clear Cover, cc_{pad} :	3	in

Material Properties		
Rebar Grade, Fy :	60	ksi
Concrete Compressive Strength, F'c :	4	ksi
Dry Concrete Density, δc :	150	pcf

Soil Properties		
Total Soil Unit Weight, γ :	130	pcf
Ultimate Gross Bearing, Qult :	16.000	ksf
Cohesion, Cu :	0.000	ksf
Friction Angle, φ :	36	degrees
SPT Blow Count, N_{blows} :		
Base Friction, μ :	0.35	
Neglected Depth, N :	3.33	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, gw :	None	ft



<--Toggle between Gross and Net

ASCE 7 Hazards Report

Address:
No Address at This
Location

Standard: ASCE/SEI 7-10
Risk Category: II
Soil Class: D - Stiff Soil

Elevation: 133.49 ft (NAVD 88)
Latitude: 41.626194
Longitude: -72.775647



Wind

Results:

Wind Speed:	123 Vmph
10-year MRI	77 Vmph
25-year MRI	86 Vmph
50-year MRI	93 Vmph
100-year MRI	100 Vmph

Data Source: ASCE/SEI 7-10, Fig. 26.5-1A and Figs. CC-1–CC-4, incorporating errata of March 12, 2014

Date Accessed: Fri Jul 12 2019

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.



Mountainous terrain, gorges, ocean promontories, and special wind regions should be examined for unusual wind conditions.

Site Soil Class: D - Stiff Soil

Results:

S_s :	0.183	S_{DS} :	0.195
S_1 :	0.063	S_{D1} :	0.102
F_a :	1.6	T_L :	6
F_v :	2.4	PGA :	0.093
S_{MS} :	0.292	PGA _M :	0.149
S_{M1} :	0.152	F _{PGA} :	1.6
		I_e :	1

Seismic Design Category B



Data Accessed:

Fri Jul 12 2019

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness: 1.00 in.
Concurrent Temperature: 5 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Fri Jul 12 2019

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.