



Together with Nextel

10 Industrial Ave, Suite 3
Mahwah, NJ 07430
Phone: (845)499-4712
Jennifer Notaro
Real Estate Consultant

8/26/14

Hand Delivered

Ms. Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

CC to Property Owner
Berlin Volunteer Fire Department, Inc.
1657 Wilbur Cross Highway
Berlin, CT 06037

RE: Sprint Spectrum L.P. notice of intent to modify an existing telecommunications facility located at 1657 Wilbur Cross Highway, Berlin, CT. Known to Sprint Spectrum L.P. as site CT43XC846.

Dear Ms. Bachman:

In order to accommodate technological changes, implement Code Division Multiple Access (“CDMA”) and/or Long Term Evolution (“LTE”) capabilities, and enhance system performance in the state of Connecticut, Sprint Spectrum L.P. plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and its attachments is being sent to the chief elected official of the municipality in which affected cell site is located.

CDMA employs Spread-Spectrum technology and special coding scheme to allow multiple users to be multiplexed over the same physical channel.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

The changes to the facility do not constitute modification as defined Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for the R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will not be affected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound.
3. The proposed changes will not increase the noise level at the existing facility by 6 decibels or more.
4. Radio Frequency power density may increase due to the use of one or more CDMA transmissions. Moreover, LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons Sprint Spectrum L.P. respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (845)-499-4712 or email JNotaro@Transcendwireless.com with questions concerning this matter. Thank you for your consideration.

Sincerely,

Jennifer Notaro
Real Estate Consultant

RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT43XC846

Berlin / RT15/Fire Dept

1657 Wilbur Cross
Berlin, CT 06037

August 22, 2014

EBI Project Number: 62144355

August 22, 2014

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT43XC846 - Berlin / RT15/Fire Dept

Site Total: 66.43% - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at **1657 Wilbur Cross, Berlin, CT**, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band (850 MHz Band) is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at **1657 Wilbur Cross, Berlin, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 3 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **150 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT43XC846 - Berlin / RT15/Fire Dept
Site Address	1657 Wilbur Cross, Berlin, CT, 06037
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	150	144	1/2 "	0.5	0	208.04	0.36%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	150	144	1/2 "	0.5	0	39.00	0.12%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	150	144	1/2 "	0.5	0	138.69	0.42%
Sector total Power Density Value:															0.90%	

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	150	144	1/2 "	0.5	0	208.04	0.36%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	150	144	1/2 "	0.5	0	39.00	0.12%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	150	144	1/2 "	0.5	0	138.69	0.42%
Sector total Power Density Value:															0.90%	

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	150	144	1/2 "	0.5	0	208.04	0.36%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	150	144	1/2 "	0.5	0	39.00	0.12%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	150	144	1/2 "	0.5	0	138.69	0.42%
Sector total Power Density Value:															0.90%	

Site Composite MPE %	
Carrier	MPE %
Sprint	2.71%
Police Channel	0.41%
Fire Main	0.55%
Fire Intercity	0.54%
Highway	0.35%
Fire Ground	0.05%
SP Hotline	0.45%
RAFS	0.11%
960 Link	0.12%
Clearwire	0.83%
AT&T	12.23%
T-Mobile	2.76%
Verizon Wireless	45.32%
Total Site MPE %	66.43%

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **2.71% (0.90% from sector 1, 0.90% from sector 2 and 0.90% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **66.43%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803



RAMAKER & ASSOCIATES, INC.


STRUCTURAL ASSESSMENT - 175-FOOT MONOPOLE TOWER FOR: TRANSCEND WIRELESS - SPRINT

SITE NAME: BERLIN / RT15 / FIRE DEPT.
SITE ID: CT43XC846-A

TOWER: PASS - 91.0%
FOUNDATION: PASS

RAMAKER & ASSOCIATES, INC.
JOB NUMBER: 28744

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 ▲ Fax: 608-643-7999
www.ramaker.com



STRUCTURAL ASSESSMENT

SITE: Berlin / RT15 / Fire Dept. (CT43XC846-A)
1657 Wilbur Cross
Berlin, Hartford County, Connecticut 06037


PREPARED FOR: Transcend Wireless

CONTACT PERSON: Mike Kithcart
Transcend Wireless
48 Spruce Street, Oakland, NJ 07436

PREPARED BY: Ramaker & Associates, Inc.
1120 Dallas Street
Sauk City, Wisconsin 53583
Telephone: (608) 643-4100
Facsimile: (608) 643-7999


RAMAKER JOB NUMBER: 28744

DATE OF REPORT ISSUANCE: August 5, 2014



Jonathan Styx
Project Engineer

08/05/14
Date



James R. Skowronski, P.E.
Supervising Engineer

08/05/14
Date




TABLE OF CONTENTS

EXECUTIVE SUMMARY3

INTRODUCTION.....4

 2.1 PROJECT INFORMATION

 2.2 PURPOSE OF REPORT

 2.3 SCOPE OF SERVICES

MODEL DEVELOPMENT5

 3.1 INTRODUCTION

 3.2 EXISTING STRUCTURE INFORMATION

 3.3 TOWER LOADING

 3.4 WIND AND ICE LOAD

ANALYSIS RESULTS7

 4.1 ANALYSIS RESULTS

 4.2 BASE REACTIONS

 4.3 MOUNT ASSESSMENT

LIMITATIONS.....9

REFERENCES..... 10

LIST OF APPENDICES

- A. TOWER FIGURES
- B. TOWER CALCULATIONS
- C. MOUNT CALCULATIONS

SECTION 1

EXECUTIVE SUMMARY

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

The Sprint proposed loading includes installing three (3) RFS APXV9TM14-ALU-I20 panel antennas and three (3) Alcatel-Lucent TD-RRH8x20-25 RRH units on the existing platform at a centerline elevation of 150 feet AGL. The proposed antennas shall be fed with one (1) 1-1/4-inch hybrid cable that was assumed to be routed up inside the tower.

The existing tower base plate could become overstressed under the proposed loading conditions. *The tower base plate shall be modified with the addition of seventeen (17) new stiffener plates per modification drawings included in this report. The required modifications shall be completed prior to any equipment loading changes.*

Results of our analysis show that the *modified* tower will be stressed to a maximum of 91.0 percent of capacity under proposed loading conditions *after the proposed modifications are made to the tower per construction documents by RAMAKER are completed.*

All model foundation tower base reactions are greater than the original design reactions from 1.2 to 3.2 percent. However, the foundation was analyzed using the data provided within the previous URS structural analysis. The foundation was determined to provide adequate strength under proposed loading conditions.

Results of our mount assessment show that by engineering calculation and inspection, the antenna and RRH mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna and RRH mounting structure.

In summary, the *modified* tower and foundations will pass the TIA/EIA-222-F code requirements under proposed loading conditions *after all proposed tower modifications are completed.* The mounting structure will pass the TIA-222 code requirements under proposed loading conditions.

SECTION 2

INTRODUCTION

2.1 PROJECT INFORMATION

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (RAMAKER) for Transcend Wireless on behalf of Sprint, who intends to install additional equipment on an existing tower.

2.2 PURPOSE OF REPORT

The analysis activities of this report were conducted for the purposes of creating and analyzing a model of the subject structure under the required loading conditions. Base reactions from the resulting model were also determined for tower foundation and support development. Recommendations regarding the analysis results, loading configuration, and structural modifications are also provided.

2.3 SCOPE OF SERVICES

RAMAKER developed a finite element model (FEM) of the tower, using tnxTower, for member force, joint deflection, and structure reaction determinations. Subsequently, this report was drafted to provide our engineering recommendations. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the tower loading occur.

**SECTION 3
MODEL DEVELOPMENT**

3.1 INTRODUCTION

RAMAKER developed a FEM of the tower superstructure. Required static loads consisting of the antenna configuration, wind forces, ice loads, and linear appurtenances (including cable loads) were then applied to the FEM. As a result, all member forces, allowable capacities, and base reactions were computed. Additionally, potentially overstressed members were identified.

3.2 EXISTING STRUCTURE INFORMATION

Existing structure information was gathered from:

- Structural analysis by Tectonic, Site No. CT43XC846 (Sprint), dated 11/16/12
- Structural analysis by URS, Site No. CT-HFD0126A (Clearwire), dated 4/7/10
- Structural analysis by URS, Site No. CT-375 (AT&T), dated 10/18/02

3.3 TOWER LOADING

RAMAKER understands that the tower loading to be used for this analysis will consist of the existing and proposed antenna, mount, and cable configurations as shown in the following chart:

Elev.	Appurtenance	Mount	Coax	Owner	Status
175	10' Dipole	Low Profile Platform	(7) 1-5/8 (I)	City	Reserved
	(2) 10' Dipoles				Existing
	(2) 10' Omnis				
	(2) Scala MF-900B				
170	(3) Kathrein 800 10121	(3) T-Arms	(6) 1-5/8 (I) (1) Fiber (I) (2) Power (I)	AT&T	Existing
	(3) KMW AM-X-CD-16-65-00T-RET				
	(6) Kathrein 860-10025				
	(6) Powerwave LGP214nn				
	(3) Ericsson RRUS-11				
	Raycap DC6-48-60-18-8F				
162	10' Dipole	6' Standoff	(2) 1-5/8 (I)	City	Existing
	Scala MF-900B				
160	(6) EMS DR65-19-00DPQ	(3) T-Arms	(12) 1-5/8 (I)	T-Mobile	Existing
	(6) Andrew ETD819H-12UB		(12) 1-5/8 (I)		Reserved
	(3) EMS DR65-19-00DPQ				
	(6) Andrew ETD819H-12UB				
150	(3) RFS APXVSP18-C-A20	Low Profile Platform	(3) 1-1/4 (I)	Sprint	Existing
	(3) ALU 1900MHz 4x45W RRH				
	(3) ALU 800MHz 2x50W RRH		(1) 1-1/4 (I)		<i>Proposed</i>
	<i>(3) RFS APXV9TM14-ALU-I20</i>				
	<i>(3) ALU TD-RRH8x20-25</i>				
	(3) Kathrein 840 10054				

BERLIN / RT15 / FIRE DEPT.

	(3) Samsun nRRH				
	(4) Andrew VHLP2.5-11		(4) 1/2 (I)		
130	10' Dipole	6' Standoff	1-5/8 (I)	City	Existing
	TMA				
124	(3) Kathrein 742 213V01	Face Mount	(6) 1-5/8 (I)	Pocket	Existing
114	(4) Antel LPA-80063-6CF-EDIN-X	Low Profile Platform	(12) 1-5/8 (I) (7) 1-5/8 (E)	Verizon	Existing
	(2) Antel RWA-80013				
	(3) Andrew LNX-6514DS-T4M				
	(1) Antel BX-185060-12CF-EDIN-X				
	(2) Rymosa MGD3-900TX				
	(3) TMAs				
100	10' Dipole	6' Standoff	(2) 1-5/8 (I)	City	Existing
	TMA				
	Scala MF-900B				
75	GPS Antenna	2' Standoff	1/2 (I)	Sprint	Existing
60	GPS Antenna	2' Standoff	1/2 (I)	T-Mobile	Existing
	Scanner Antenna	2' Standoff	1/2 (I)	City	

I = Interior Coax, E = Exterior Coax

3.4 WIND AND ICE LOAD

Wind forces used in model development are in compliance with the TIA/EIA-222-F Standard. These guidelines call for an analysis to be performed, which assumes a basic wind speed of 80 miles-per-hour (mph) without ice in Hartford County. The tower is also designed for a 38 mph basic wind speed with 0.75-inch of radial ice.

SECTION 4

ANALYSIS RESULTS

4.1 ANALYSIS RESULTS

The *modified* tower superstructure was analyzed with the combined existing and proposed antenna loading with and without radial ice. The computed maximum tower member stress capacities are as follows:

Component Type	Percent Capacity
Section 1	56.3
Section 2	85.4
Section 3	87.7
Section 4	81.8
Base Plate	70.0
Anchor Bolts	91.0
RATING =	91.0

4.2 BASE REACTIONS

The computed maximum reactions under the corresponding maximum moment are as follows:

Load Type	Original Design	Proposed Model
Axial (k)	49.6	51.2
Shear (k)	34.94	35.1
Moment (k-ft)	4306.5	4319.6

All model foundation tower base reactions are greater than the original design reactions from 1.2 to 3.2 percent. However, the foundation was analyzed using the data provided within the previous URS structural analysis. The foundation was determined to provide adequate strength under proposed loading conditions.

4.3 MOUNT ASSESSMENT

Results of our mount assessment show that by engineering calculation and inspection, the antenna and RRH mounting structure is capable of supporting the existing and proposed Sprint 2.5 equipment deployment without causing an overstress condition in the antenna and RRH mounting structure.

This assessment is inclusive of the entire antenna mounting structure, including tower platforms, arms, and all other aspects of the mounting structure that will support the Sprint 2.5 equipment deployment. This assessment assumes that the mounting structure(s) has been installed correctly, is free from deterioration, and is maintained properly.

SECTION 5

LIMITATIONS

The recommendations contained within this report were developed using general project information provided by the owner, tower manufacturer, general field observations, reference information and laboratory testing data, as applicable. All recommendations pertain only to the proposed tower construction, location, and loading as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

1. Missing, corroding, and/or deteriorating members
2. Improper manufacturing and/or construction
3. Improper maintenance

RAMAKER assumes no responsibility for modifications completed prior to or hereafter in which RAMAKER was not directly involved. These modifications include but are not limited to the following:

1. Replacing or strengthening bracing members
2. Reinforcing or extending vertical members
3. Installing or removing antenna mounting gates or side arms
4. Changing loading configurations

Furthermore, RAMAKER hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations and conclusions are based on the information contained and set forth herein. If you are aware of any information contrary to that contained herein, or if you are aware of any defects arising from the original design, material, fabrication and erection deficiencies, you should disregard this report and immediately contact RAMAKER. RAMAKER isn't liable for any representation, recommendation or conclusion not expressly stated herein.



The tower owner is responsible for verifying that the existing loading on the tower is consistent with the loading applied to the tower within this report.

SECTION 6
REFERENCES

1. 2003 International Building Code.
2. Telecommunications Industries Association, Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA Standard TIA/EIA-222-F 1996, Washington, D.C.

APPENDIX A
TOWER FIGURES

Section	1	2	3	4
Length (ft)	45.25	49.13	48.87	49.00
Number of Sides	18	18	18	18
Thickness (in)	0.2500	0.3125	0.3750	0.4375
Socket Length (ft)	4.50	5.75	7.00	
Top Dia (in)	21.0000	30.2260	39.8381	48.9596
Bot Dia (in)	31.8000	41.8200	51.3600	60.5000
Grade		A572-65		
Weight (lb)	3195.0	5921.5	8951.3	12570.6
				30638.4



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
10' Dipole (City)	176	840 10054 w/Mount Pipe (Clearwire)	150
10' Dipole (City)	176	840 10054 w/Mount Pipe (Clearwire)	150
10' Dipole (City)	176	840 10054 w/Mount Pipe (Clearwire)	150
10' Omni (City)	176	nRRH (Clearwire)	150
10' Omni (City)	176	nRRH (Clearwire)	150
Valmont 13'-5" Platform (City)	176	nRRH (Clearwire)	150
MF-900B	176	Valmont 13'-5" Platform (Sprint)	150
MF-900B	176	APXV9TM14-ALU-I20 w/Mount Pipe (Sprint)	150
800 10121 w/Mount Pipe (ATT)	170	APXV9TM14-ALU-I20 w/Mount Pipe (Sprint)	150
AM-X-CD-16-65-00T-RET w/Mount Pipe (ATT)	170	APXV9TM14-ALU-I20 w/Mount Pipe (Sprint)	150
AM-X-CD-16-65-00T-RET w/Mount Pipe (ATT)	170	VHLP2.5-11 (Clearwire)	150
AM-X-CD-16-65-00T-RET w/Mount Pipe (ATT)	170	VHLP2.5-11 (Clearwire)	150
(2) 860-10025 (ATT)	170	VHLP2.5-11 (Clearwire)	150
(2) 860-10025 (ATT)	170	VHLP2.5-11 (Clearwire)	150
(2) 860-10025 (ATT)	170	10' Dipole (City)	130
(2) LGP214nn (ATT)	170	TMA (City)	130
(2) LGP214nn (ATT)	170	6' Standoff (City)	130
RRUS-11 (ATT)	170	742 213V01 w/Mount Pipe (Pocket)	124
RRUS-11 (ATT)	170	742 213V01 w/Mount Pipe (Pocket)	124
RRUS-11 (ATT)	170	742 213V01 w/Mount Pipe (Pocket)	124
RRUS-11 (ATT)	170	LNX-6514DS-T4M w/Mount Pipe (Verizon)	114
DC6-48-60-18-8F (ATT)	170	LNX-6514DS-T4M w/Mount Pipe (Verizon)	114
EEL (3) 12' Universal T-Arms (ATT)	170	BXA-185060-12CF-EDIN-X w/Mount Pipe (Verizon)	114
800 10121 w/Mount Pipe (ATT)	170	MGD3-900TX w/Mount Pipe (Verizon)	114
800 10121 w/Mount Pipe (ATT)	170	MGD3-900TX w/Mount Pipe (Verizon)	114
10' Dipole (City)	162	MGD3-900TX w/Mount Pipe (Verizon)	114
6' Standoff (City)	162	TMA (Verizon)	114
MF-900B	162	TMA (Verizon)	114
(4) ETD819H-12UB (T-Mobile)	160	TMA (Verizon)	114
(4) ETD819H-12UB (T-Mobile)	160	Valmont 13'-5" Platform (Verizon)	114
EEL (3) 12' Universal T-Arms (T-Mobile)	160	LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	114
(3) DR65-19-00DPQ w/Mount Pipe (T-Mobile)	160	LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	114
(3) DR65-19-00DPQ w/Mount Pipe (T-Mobile)	160	LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	114
(3) DR65-19-00DPQ w/Mount Pipe (T-Mobile)	160	RWA-80013 w/Mount Pipe (Verizon)	114
TD-RRH8x20-25 (Sprint)	150	RWA-80013 w/Mount Pipe (Verizon)	114
TD-RRH8x20-25 (Sprint)	150	LNX-6514DS-T4M w/Mount Pipe (Verizon)	114
TD-RRH8x20-25 (Sprint)	150	LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	114
APXVSP18-C-A20 w/Mount Pipe (Sprint)	150	10' Dipole (City)	100
APXVSP18-C-A20 w/Mount Pipe (Sprint)	150	TMA (City)	100
APXVSP18-C-A20 w/Mount Pipe (Sprint)	150	6' Standoff (City)	100
1900MHz 4x45W RRH (Sprint)	150	MF-900B	100
1900MHz 4x45W RRH (Sprint)	150	GPS (Sprint)	76
800MHz 2x50W RRH (Sprint)	150	2' Standoff (Sprint)	76
800MHz 2x50W RRH (Sprint)	150	GPS (City)	61
800MHz 2x50W RRH (Sprint)	150	2' Standoff (City)	61
800MHz 2x50W RRH (Sprint)	150	GPS (T-Mobile)	61
800MHz 2x50W RRH (Sprint)	150	2' Standoff (T-Mobile)	61

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. TOWER RATING: 91%

<p>Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	<p>Job: Berlin / RT15 / Fire Dept. (CT43XC846-A)</p>
	<p>Project: 28744</p>
	<p>Client: Transcend Wireless / Sprint</p>
	<p>Code: TIA/EIA-222-F</p>
	<p>Drawn by: JDS</p>
	<p>Date: 08/05/14</p>
	<p>Scale: NTS</p>
	<p>Path: \\28700\28744\Structural\TNX\28744 Rev1.eri</p>
	<p>Dwg No. E-1</p>

TIA/EIA-222-F - 80 mph/38 mph 0.7500 in Ice

Leg Capacity ——— Leg Compression (lb)





 <p>Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	Job: Berlin / RT15 / Fire Dept. (CT43XC846-A)		
	Project: 28744		
	Client: Transcend Wireless / Sprint	Drawn by: JDS	App'd:
	Code: TIA/EIA-222-F	Date: 08/05/14	Scale: NTS
	Path: I:\28700\28744\Structural\TNX\28744 Rev1.eri		Dwg No. E-3


Vx

Vz

Mx

Mz






	Ramaker & Associates			Job: Berlin / RT15 / Fire Dept. (CT43XC846-A)		
	1120 Dallas St.			Project: 28744		
	Sauk City, WI 53583			Client: Transcend Wireless / Sprint	Drawn by: JDS	App'd:
	Phone: (608) 643-4100			Code: TIA/EIA-222-F	Date: 08/05/14	Scale: NTS
	FAX: (608) 643-7999			Path: I:\28700\28744\Structural\TNX\28744 Rev1.eri		

Feed Line Distribution Chart

1' - 176'

— Round
 — Flat
 — App In Face
 — App Out Face
 — Truss Leg





	Ramaker & Associates		Job: Berlin / RT15 / Fire Dept. (CT43XC846-A)		
	1120 Dallas St.		Project: 28744		
	Sauk City, WI 53583		Client: Transcend Wireless / Sprint	Drawn by: JDS	App'd:
	Phone: (608) 643-4100		Code: TIA/EIA-222-F	Date: 08/05/14	Scale: NTS
	FAX: (608) 643-7999		Path: I:\28700\28744\Structural\TNX\28744 Rev1.eri		Dwg No. E-7

Stress Distribution Chart

1' - 176'

■ > 100%
 ■ 90%-100%
 ■ 75%-90%
 ■ 50%-75%
 ■ < 50% Overstress



 Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job: Berlin / RT15 / Fire Dept. (CT43XC846-A)		
	Project: 28744		
	Client: Transcend Wireless / Sprint	Drawn by: JDS	App'd:
	Code: TIA/EIA-222-F	Date: 08/05/14	Scale: NTS
	Path: I:\28700\28744\Structural\TNX\28744 Rev1.eri		Dwg No. E-8

APPENDIX B
TOWER CALCULATIONS

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page 1 of 21
	Project 28744	Date 16:00:00 08/05/14
	Client Transcend Wireless / Sprint	Designed by JDS

Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

- Tower is located in Hartford County, Connecticut.
- Basic wind speed of 80 mph.
- Nominal ice thickness of 0.7500 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 38 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.333.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	176.00-130.75	45.25	4.50	18	21.0000	31.8000	0.2500	1.0000	A572-65 (65 ksi)
L2	130.75-86.12	49.13	5.75	18	30.2260	41.8200	0.3125	1.2500	A572-65 (65 ksi)
L3	86.12-43.00	48.87	7.00	18	39.8381	51.3600	0.3750	1.5000	A572-65 (65 ksi)
L4	43.00-1.00	49.00		18	48.9596	60.5000	0.4375	1.7500	A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	It/Q in ²	w in	w/t
L1	21.3240	16.4651	895.6507	7.3663	10.6680	83.9568	1792.4800	8.2341	3.2560	13.024
	32.2906	25.0349	3148.3461	11.2003	16.1544	194.8909	6300.8349	12.5198	5.1568	20.627
L2	31.7706	29.6704	3354.2439	10.6193	15.3548	218.4493	6712.9014	14.8380	4.7698	15.263
	42.4651	41.1703	8961.3641	14.7352	21.2446	421.8192	17934.5198	20.5890	6.8103	21.793
L3	41.8292	46.9709	9241.6269	14.0094	20.2377	456.6531	18495.4142	23.4899	6.3515	16.937
	52.1523	60.6849	19929.7987	18.0997	26.0909	763.8607	39885.8215	30.3482	8.3794	22.345
L4	51.3890	67.3790	20042.0464	17.2254	24.8715	805.8240	40110.4646	33.6959	7.8469	17.936
	61.4333	83.4043	38013.0437	21.3222	30.7340	1236.8401	76076.1060	41.7101	9.8780	22.578

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page 2 of 21
	Project 28744	Date 16:00:00 08/05/14
	Client Transcend Wireless / Sprint	Designed by JDS

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
ft	ft ²	in						
L1 176.00-130.75				1	1	1		
L2 130.75-86.12				1	1	1		
L3 86.12-43.00				1	1	1		
L4 43.00-1.00				1	1	1		

Monopole Base Plate Data

Base Plate Data	
Base plate is square	
Base plate is grouted	
Anchor bolt grade	A615-75
Anchor bolt size	2.2500 in
Number of bolts	18
Embedment length	24.0000 in
f_c	4 ksi
Grout space	2.0000 in
Base plate grade	A572-60
Base plate thickness	2.0000 in
Bolt circle diameter	70.0000 in
Outer diameter	76.0000 in
Inner diameter	60.7500 in
Base plate type	Stiffened Plate
Bolts per stiffener	1
Stiffener thickness	0.5000 in
Stiffener height	12.0000 in

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement	Total Number		$C_A A_A$	Weight
							ft ² /ft	plf
1 5/8 (City)	C	No	Inside Pole	175.00 - 21.00	7	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
1 5/8 (AT&T)	C	No	Inside Pole	170.00 - 9.00	6	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
Fiber Cable (AT&T)	C	No	Inside Pole	170.00 - 9.00	1	No Ice	0.00	0.17
						1/2" Ice	0.00	0.17
						1" Ice	0.00	0.17
						2" Ice	0.00	0.17
						4" Ice	0.00	0.17
Power Cable (AT&T)	C	No	Inside Pole	170.00 - 9.00	2	No Ice	0.00	0.60
						1/2" Ice	0.00	0.60
						1" Ice	0.00	0.60
						2" Ice	0.00	0.60
						4" Ice	0.00	0.60
1 5/8	C	No	Inside Pole	162.00 - 21.00	2	No Ice	0.00	1.04

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job		Berlin / RT15 / Fire Dept. (CT43XC846-A)		Page		3 of 21	
	Project		28744		Date		16:00:00 08/05/14	
	Client		Transcend Wireless / Sprint		Designed by		JDS	

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C _A A _A ft ² /ft	Weight plf
(City)						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
1 5/8 (T-Mobile)	C	No	Inside Pole	160.00 - 9.00	24	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
1 1/4 (Sprint)	C	No	Inside Pole	150.00 - 9.00	3	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
						2" Ice	0.00	0.66
						4" Ice	0.00	0.66
1 1/4 (Sprint)	C	No	Inside Pole	150.00 - 9.00	1	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
						2" Ice	0.00	0.66
						4" Ice	0.00	0.66
7919A CAT5E (Clearwire)	C	No	Inside Pole	150.00 - 9.00	6	No Ice	0.00	0.03
						1/2" Ice	0.00	0.03
						1" Ice	0.00	0.03
						2" Ice	0.00	0.03
						4" Ice	0.00	0.03
1/2 (Clearwire)	C	No	Inside Pole	150.00 - 9.00	4	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
						1" Ice	0.00	0.25
						2" Ice	0.00	0.25
						4" Ice	0.00	0.25
1 5/8 (City)	C	No	Inside Pole	130.00 - 21.00	1	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
1 5/8 (Pocket Wireless)	C	No	Inside Pole	124.00 - 9.00	6	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
1 5/8 (Verizon)	C	No	CaAa (Out Of Face)	114.00 - 21.00	2	No Ice	0.20	1.04
						1/2" Ice	0.30	2.55
						1" Ice	0.40	4.68
						2" Ice	0.60	10.76
						4" Ice	1.00	30.26
1 5/8 (Verizon)	C	No	CaAa (Out Of Face)	114.00 - 21.00	5	No Ice	0.00	1.04
						1/2" Ice	0.00	2.55
						1" Ice	0.00	4.68
						2" Ice	0.00	10.76
						4" Ice	0.00	30.26
1 5/8 (Verizon)	C	No	Inside Pole	114.00 - 21.00	12	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
1 5/8 (City)	C	No	Inside Pole	100.00 - 21.00	2	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
						2" Ice	0.00	1.04
						4" Ice	0.00	1.04
1/2 (Sprint)	C	No	Inside Pole	75.00 - 9.00	1	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	4 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C _{AA}	Weight
							ft ² /ft	plf
1/2 (City)	C	No	Inside Pole	60.00 - 21.00	1	1" Ice	0.00	0.25
						2" Ice	0.00	0.25
						4" Ice	0.00	0.25
						No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
						1" Ice	0.00	0.25
1/2 (T-Mobile)	C	No	Inside Pole	60.00 - 9.00	1	2" Ice	0.00	0.25
						4" Ice	0.00	0.25
						No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
						1" Ice	0.00	0.25
						2" Ice	0.00	0.25
						4" Ice	0.00	0.25

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight lb
L1	176.00-130.75	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	1489.45
L2	130.75-86.12	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	11.040	2903.61
L3	86.12-43.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	17.076	3244.89
L4	43.00-1.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	8.712	2181.20

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight lb
L1	176.00-130.75	A	0.901	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	1489.45
L2	130.75-86.12	A	0.864	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	21.088	3531.73
L3	86.12-43.00	A	0.812	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	31.984	4169.36
L4	43.00-1.00	A	0.750	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	15.862	2618.82

Feed Line Center of Pressure

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	5 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Section	Elevation	CP _x	CP _z	CP _x Ice	CP _z Ice
	ft	in	in	in	in
L1	176.00-130.75	0.0000	0.0000	0.0000	0.0000
L2	130.75-86.12	-0.3133	0.1809	-0.5372	0.3101
L3	86.12-43.00	-0.4665	0.2693	-0.7836	0.4524
L4	43.00-1.00	-0.2470	0.1426	-0.4229	0.2442

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A		Weight
			Horz Lateral Vert ft ft ft	°			Front ft ²	Side ft ²	
10' Dipole (City)	A	From Face	5.00	0.0000	176.00	No Ice	3.00	3.00	30.00
			0.00			1/2" Ice	4.00	4.00	55.00
			5.00			1" Ice	5.00	5.00	85.00
						2" Ice	6.25	6.25	100.00
						4" Ice	9.00	9.00	140.00
10' Dipole (City)	B	From Face	5.00	0.0000	176.00	No Ice	3.00	3.00	30.00
			0.00			1/2" Ice	4.00	4.00	55.00
			5.00			1" Ice	5.00	5.00	85.00
						2" Ice	6.25	6.25	100.00
						4" Ice	9.00	9.00	140.00
10' Dipole (City)	B	From Leg	6.00	0.0000	176.00	No Ice	3.00	3.00	30.00
			0.00			1/2" Ice	4.00	4.00	55.00
			5.00			1" Ice	5.00	5.00	85.00
						2" Ice	6.25	6.25	100.00
						4" Ice	9.00	9.00	140.00
10' Omni (City)	C	From Face	5.00	0.0000	176.00	No Ice	2.50	2.50	30.00
			0.00			1/2" Ice	3.53	3.53	48.64
			5.00			1" Ice	4.58	4.58	73.79
						2" Ice	5.98	5.98	144.26
						4" Ice	8.54	8.54	370.10
10' Omni (City)	C	From Face	6.00	0.0000	176.00	No Ice	2.75	2.75	30.00
			5.00			1/2" Ice	3.78	3.78	50.21
			5.00			1" Ice	4.83	4.83	76.96
						2" Ice	6.12	6.12	150.70
						4" Ice	8.69	8.69	383.40
Valmont 13'-5" Platform (City)	C	None		0.0000	176.00	No Ice	18.43	18.43	1759.00
						1/2" Ice	22.32	22.32	2143.00
						1" Ice	26.21	26.21	2527.00
						2" Ice	33.99	33.99	3295.00
						4" Ice	49.55	49.55	4831.00

800 10121 w/Mount Pipe (ATT)	A	From Face	4.00	0.0000	170.00	No Ice	5.80	4.72	72.60
			-6.00			1/2" Ice	6.35	5.56	121.39
			0.00			1" Ice	6.87	6.29	176.64
						2" Ice	7.95	7.82	309.77
						4" Ice	10.24	11.24	697.16
800 10121 w/Mount Pipe (ATT)	B	From Face	4.00	0.0000	170.00	No Ice	5.80	4.72	72.60
			-6.00			1/2" Ice	6.35	5.56	121.39
			0.00			1" Ice	6.87	6.29	176.64
						2" Ice	7.95	7.82	309.77
						4" Ice	10.24	11.24	697.16

Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	6 of 21
Project	28744	Date	16:00:00 08/05/14
Client	Transcend Wireless / Sprint	Designed by	JDS

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA}		Weight	
			Horz	Vert			Front	Side		
			ft	ft	°	ft	ft ²	ft ²	lb	
800 10121 w/Mount Pipe (ATT)	C	From Face	4.00	0.00	0.0000	170.00	No Ice	5.80	4.72	72.60
			-6.00				1/2" Ice	6.35	5.56	121.39
			0.00				1" Ice	6.87	6.29	176.64
							2" Ice	7.95	7.82	309.77
							4" Ice	10.24	11.24	697.16
AM-X-CD-16-65-00T-RET w/Mount Pipe (ATT)	A	From Face	4.00	0.00	0.0000	170.00	No Ice	8.50	6.30	74.05
			6.00				1/2" Ice	9.15	7.48	139.04
			0.00				1" Ice	9.77	8.37	211.91
							2" Ice	11.03	10.18	384.96
							4" Ice	13.68	14.02	874.27
AM-X-CD-16-65-00T-RET w/Mount Pipe (ATT)	B	From Face	4.00	0.00	0.0000	170.00	No Ice	8.50	6.30	74.05
			6.00				1/2" Ice	9.15	7.48	139.04
			0.00				1" Ice	9.77	8.37	211.91
							2" Ice	11.03	10.18	384.96
							4" Ice	13.68	14.02	874.27
AM-X-CD-16-65-00T-RET w/Mount Pipe (ATT)	C	From Face	4.00	0.00	0.0000	170.00	No Ice	8.50	6.30	74.05
			6.00				1/2" Ice	9.15	7.48	139.04
			0.00				1" Ice	9.77	8.37	211.91
							2" Ice	11.03	10.18	384.96
							4" Ice	13.68	14.02	874.27
(2) 860-10025 (ATT)	A	From Face	4.00	0.00	0.0000	170.00	No Ice	0.14	0.23	1.16
			-6.00				1/2" Ice	0.20	0.30	3.13
			0.00				1" Ice	0.26	0.38	6.08
							2" Ice	0.42	0.56	15.75
							4" Ice	0.84	1.02	55.54
(2) 860-10025 (ATT)	B	From Face	4.00	0.00	0.0000	170.00	No Ice	0.14	0.23	1.16
			-6.00				1/2" Ice	0.20	0.30	3.13
			0.00				1" Ice	0.26	0.38	6.08
							2" Ice	0.42	0.56	15.75
							4" Ice	0.84	1.02	55.54
(2) 860-10025 (ATT)	C	From Face	4.00	0.00	0.0000	170.00	No Ice	0.14	0.23	1.16
			-6.00				1/2" Ice	0.20	0.30	3.13
			0.00				1" Ice	0.26	0.38	6.08
							2" Ice	0.42	0.56	15.75
							4" Ice	0.84	1.02	55.54
(2) LGP214nn (ATT)	A	From Face	4.00	0.00	0.0000	170.00	No Ice	1.30	0.23	14.10
			-6.00				1/2" Ice	1.45	0.31	21.30
			0.00				1" Ice	1.62	0.40	30.39
							2" Ice	1.98	0.61	55.04
							4" Ice	2.80	1.12	135.66
(2) LGP214nn (ATT)	B	From Face	4.00	0.00	0.0000	170.00	No Ice	1.30	0.23	14.10
			-6.00				1/2" Ice	1.45	0.31	21.30
			0.00				1" Ice	1.62	0.40	30.39
							2" Ice	1.98	0.61	55.04
							4" Ice	2.80	1.12	135.66
(2) LGP214nn (ATT)	C	From Face	4.00	0.00	0.0000	170.00	No Ice	1.30	0.23	14.10
			-6.00				1/2" Ice	1.45	0.31	21.30
			0.00				1" Ice	1.62	0.40	30.39
							2" Ice	1.98	0.61	55.04
							4" Ice	2.80	1.12	135.66
RRUS-11 (ATT)	A	From Face	4.00	0.00	0.0000	170.00	No Ice	2.94	1.25	55.00
			5.00				1/2" Ice	3.17	1.41	74.32
			0.00				1" Ice	3.41	1.59	96.56
							2" Ice	3.91	1.96	150.56
							4" Ice	5.02	2.82	302.12
RRUS-11 (ATT)	B	From Face	4.00	0.00	0.0000	170.00	No Ice	2.94	1.25	55.00
			5.00				1/2" Ice	3.17	1.41	74.32

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	7 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA}		Weight
			Horz Lateral	Vert			Front	Side	
			ft	ft	°	ft	ft ²	ft ²	lb
			0.00				1" Ice 3.41	1.59	96.56
							2" Ice 3.91	1.96	150.56
							4" Ice 5.02	2.82	302.12
RRUS-11 (ATT)	C	From Face	4.00		0.0000	170.00	No Ice 2.94	1.25	55.00
			5.00				1/2" Ice 3.17	1.41	74.32
			0.00				1" Ice 3.41	1.59	96.56
							2" Ice 3.91	1.96	150.56
							4" Ice 5.02	2.82	302.12
DC6-48-60-18-8F (ATT)	C	None			0.0000	170.00	No Ice 1.47	1.47	33.00
							1/2" Ice 1.67	1.67	50.72
							1" Ice 1.88	1.88	70.92
							2" Ice 2.33	2.33	119.44
							4" Ice 3.38	3.38	253.12
EEI (3) 12' Universal T-Arms (ATT)	A	None			0.0000	170.00	No Ice 16.66	16.66	550.00
							1/2" Ice 21.00	21.00	710.00
							1" Ice 25.34	25.34	870.00
							2" Ice 34.02	34.02	1190.00
							4" Ice 51.38	51.38	1830.00

10' Dipole (City)	A	From Face	6.00		0.0000	162.00	No Ice 3.00	3.00	30.00
			0.00				1/2" Ice 4.00	4.00	55.00
			4.00				1" Ice 5.00	5.00	85.00
							2" Ice 6.25	6.25	100.00
							4" Ice 9.00	9.00	140.00
6' Standoff (City)	A	From Face	3.00		0.0000	162.00	No Ice 4.97	4.97	70.00
			0.00				1/2" Ice 6.12	6.12	130.00
			0.00				1" Ice 7.27	7.27	190.00
							2" Ice 9.57	9.57	310.00
							4" Ice 14.17	14.17	550.00

(3) DR65-19-00DPQ w/Mount Pipe (T-Mobile)	A	From Face	4.00		0.0000	160.00	No Ice 8.64	5.20	57.55
			0.00				1/2" Ice 9.29	6.36	117.82
			0.00				1" Ice 9.91	7.24	185.86
							2" Ice 11.18	9.03	348.91
							4" Ice 13.83	12.81	816.90
(3) DR65-19-00DPQ w/Mount Pipe (T-Mobile)	B	From Face	4.00		0.0000	160.00	No Ice 8.64	5.20	57.55
			0.00				1/2" Ice 9.29	6.36	117.82
			0.00				1" Ice 9.91	7.24	185.86
							2" Ice 11.18	9.03	348.91
							4" Ice 13.83	12.81	816.90
(3) DR65-19-00DPQ w/Mount Pipe (T-Mobile)	C	From Face	4.00		0.0000	160.00	No Ice 8.64	5.20	57.55
			0.00				1/2" Ice 9.29	6.36	117.82
			0.00				1" Ice 9.91	7.24	185.86
							2" Ice 11.18	9.03	348.91
							4" Ice 13.83	12.81	816.90
(4) ETD819H-12UB (T-Mobile)	A	From Face	4.00		0.0000	160.00	No Ice 1.53	0.39	18.50
			0.00				1/2" Ice 1.70	0.49	27.42
			0.00				1" Ice 1.87	0.60	38.39
							2" Ice 2.25	0.84	67.28
							4" Ice 3.11	1.44	158.27
(4) ETD819H-12UB (T-Mobile)	B	From Face	4.00		0.0000	160.00	No Ice 1.53	0.39	18.50
			0.00				1/2" Ice 1.70	0.49	27.42
			0.00				1" Ice 1.87	0.60	38.39
							2" Ice 2.25	0.84	67.28
							4" Ice 3.11	1.44	158.27
(4) ETD819H-12UB (T-Mobile)	C	From Face	4.00		0.0000	160.00	No Ice 1.53	0.39	18.50
			0.00				1/2" Ice 1.70	0.49	27.42

tnxTower

Ramaker & Associates

1120 Dallas St.
Sauk City, WI 53583
Phone: (608) 643-4100
FAX: (608) 643-7999

Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	8 of 21
Project	28744	Date	16:00:00 08/05/14
Client	Transcend Wireless / Sprint	Designed by	JDS

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA}		Weight	
			Horz	Vert	Lateral			Front	Side		
			ft	ft	ft	°	ft	ft ²	ft ²	lb	
			0.00					1" Ice	1.87	0.60	38.39
								2" Ice	2.25	0.84	67.28
								4" Ice	3.11	1.44	158.27
EEI (3) 12' Universal T-Arms (T-Mobile)	A	None				0.0000	160.00	No Ice	16.66	16.66	550.00
								1/2" Ice	21.00	21.00	710.00
								1" Ice	25.34	25.34	870.00
								2" Ice	34.02	34.02	1190.00
								4" Ice	51.38	51.38	1830.00

APXV9TM14-ALU-I20 w/Mount Pipe (Sprint)	A	From Face				0.0000	150.00	No Ice	7.21	5.03	77.02
								1/2" Ice	7.77	5.89	132.43
								1" Ice	8.31	6.63	194.59
								2" Ice	9.42	8.20	342.42
APXV9TM14-ALU-I20 w/Mount Pipe (Sprint)	B	From Face				0.0000	150.00	4" Ice	11.77	11.67	762.71
								No Ice	7.21	5.03	77.02
								1/2" Ice	7.77	5.89	132.43
								1" Ice	8.31	6.63	194.59
APXV9TM14-ALU-I20 w/Mount Pipe (Sprint)	C	From Face				0.0000	150.00	2" Ice	9.42	8.20	342.42
								4" Ice	11.77	11.67	762.71
								No Ice	7.21	5.03	77.02
								1/2" Ice	7.77	5.89	132.43
TD-RRH8x20-25 (Sprint)	A	From Face				0.0000	150.00	1" Ice	8.31	6.63	194.59
								2" Ice	9.42	8.20	342.42
								4" Ice	11.77	11.67	762.71
								No Ice	4.72	1.70	70.00
TD-RRH8x20-25 (Sprint)	B	From Face				0.0000	150.00	1/2" Ice	5.01	1.92	97.14
								1" Ice	5.32	2.14	127.80
								2" Ice	5.95	2.62	200.48
								4" Ice	7.31	3.68	396.71
TD-RRH8x20-25 (Sprint)	C	From Face				0.0000	150.00	No Ice	4.72	1.70	70.00
								1/2" Ice	5.01	1.92	97.14
								1" Ice	5.32	2.14	127.80
								2" Ice	5.95	2.62	200.48
APXVSPP18-C-A20 w/Mount Pipe (Sprint)	A	From Face				0.0000	150.00	4" Ice	7.31	3.68	396.71
								No Ice	8.56	6.95	82.55
								1/2" Ice	9.21	8.13	150.82
								1" Ice	9.83	9.03	227.06
APXVSPP18-C-A20 w/Mount Pipe (Sprint)	B	From Face				0.0000	150.00	2" Ice	11.10	10.85	407.06
								4" Ice	13.75	14.86	911.21
								No Ice	8.56	6.95	82.55
								1/2" Ice	9.21	8.13	150.82
APXVSPP18-C-A20 w/Mount Pipe (Sprint)	C	From Face				0.0000	150.00	1" Ice	9.83	9.03	227.06
								2" Ice	11.10	10.85	407.06
								4" Ice	13.75	14.86	911.21
								No Ice	8.56	6.95	82.55
1900MHz 4x45W RRH (Sprint)	A	From Face				0.0000	150.00	1/2" Ice	9.21	8.13	150.82
								1" Ice	9.83	9.03	227.06
								2" Ice	11.10	10.85	407.06
								4" Ice	13.75	14.86	911.21
								No Ice	2.71	2.61	59.50
								1/2" Ice	2.95	2.84	82.62
								1" Ice	3.20	3.09	108.98

tnxTower

Ramaker & Associates
 1120 Dallas St.
 Sauk City, WI 53583
 Phone: (608) 643-4100
 FAX: (608) 643-7999

Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	9 of 21
Project	28744	Date	16:00:00 08/05/14
Client	Transcend Wireless / Sprint	Designed by	JDS

Description	Face or Leg	Offset Type	Offsets:			Azimuth Adjustment	Placement	C _{AA}		Weight	
			Horz	Lateral	Vert			Front	Side		
			ft	ft	ft	°	ft	ft ²	ft ²	lb	
1900MHz 4x45W RRH (Sprint)	B	From Face	4.00			0.0000	150.00	2" Ice	3.72	3.61	172.17
			-6.00					4" Ice	4.86	4.74	345.91
			-2.00					No Ice	2.71	2.61	59.50
								1/2" Ice	2.95	2.84	82.62
								1" Ice	3.20	3.09	108.98
								2" Ice	3.72	3.61	172.17
1900MHz 4x45W RRH (Sprint)	C	From Face	4.00			0.0000	150.00	4" Ice	4.86	4.74	345.91
			-6.00					No Ice	2.71	2.61	59.50
			-2.00					1/2" Ice	2.95	2.84	82.62
								1" Ice	3.20	3.09	108.98
								2" Ice	3.72	3.61	172.17
								4" Ice	4.86	4.74	345.91
800MHz 2x50W RRH (Sprint)	A	From Face	4.00			0.0000	150.00	No Ice	2.40	2.25	64.00
			-4.00					1/2" Ice	2.61	2.46	86.12
			-2.00					1" Ice	2.83	2.68	111.30
								2" Ice	3.30	3.13	171.62
								4" Ice	4.34	4.15	337.52
								No Ice	2.40	2.25	64.00
800MHz 2x50W RRH (Sprint)	B	From Face	4.00			0.0000	150.00	1/2" Ice	2.61	2.46	86.12
			-4.00					1" Ice	2.83	2.68	111.30
			-2.00					2" Ice	3.30	3.13	171.62
								4" Ice	4.34	4.15	337.52
								No Ice	2.40	2.25	64.00
								1/2" Ice	2.61	2.46	86.12
800MHz 2x50W RRH (Sprint)	C	From Face	4.00			0.0000	150.00	1" Ice	2.83	2.68	111.30
			-4.00					2" Ice	3.30	3.13	171.62
			-2.00					4" Ice	4.34	4.15	337.52
								No Ice	2.40	2.25	64.00
								1/2" Ice	2.61	2.46	86.12
								1" Ice	2.83	2.68	111.30
840 10054 w/Mount Pipe (Clearwire)	A	From Face	4.00			0.0000	150.00	2" Ice	3.30	3.13	171.62
			0.00					4" Ice	4.34	4.15	337.52
			0.00					No Ice	5.29	2.23	48.60
								1/2" Ice	5.68	2.73	83.42
								1" Ice	6.08	3.25	123.44
								2" Ice	6.91	4.34	221.61
840 10054 w/Mount Pipe (Clearwire)	B	From Face	4.00			0.0000	150.00	4" Ice	8.70	6.97	514.20
			0.00					No Ice	5.29	2.23	48.60
			0.00					1/2" Ice	5.68	2.73	83.42
								1" Ice	6.08	3.25	123.44
								2" Ice	6.91	4.34	221.61
								4" Ice	8.70	6.97	514.20
840 10054 w/Mount Pipe (Clearwire)	C	From Face	4.00			0.0000	150.00	No Ice	5.29	2.23	48.60
			0.00					1/2" Ice	5.68	2.73	83.42
			0.00					1" Ice	6.08	3.25	123.44
								2" Ice	6.91	4.34	221.61
								4" Ice	8.70	6.97	514.20
								No Ice	2.69	0.85	45.00
nRRH (Clearwire)	A	From Face	4.00			0.0000	150.00	1/2" Ice	2.91	1.01	60.06
			0.00					1" Ice	3.14	1.18	77.79
			-1.00					2" Ice	3.63	1.55	122.04
								4" Ice	4.72	2.38	251.13
								No Ice	2.69	0.85	45.00
								1/2" Ice	2.91	1.01	60.06
nRRH (Clearwire)	B	From Face	4.00			0.0000	150.00	1" Ice	3.14	1.18	77.79
			0.00					2" Ice	3.63	1.55	122.04
			-1.00					4" Ice	4.72	2.38	251.13
								No Ice	2.69	0.85	45.00
								1/2" Ice	2.91	1.01	60.06
								1" Ice	3.14	1.18	77.79
nRRH (Clearwire)	C	From Face	4.00			0.0000	150.00	2" Ice	3.63	1.55	122.04
			0.00					4" Ice	4.72	2.38	251.13
			-1.00					No Ice	2.69	0.85	45.00
								1/2" Ice	2.91	1.01	60.06
								1" Ice	3.14	1.18	77.79
								2" Ice	3.63	1.55	122.04
					4" Ice	4.72	2.38	251.13			

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	10 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA}		Weight
			Horz Lateral	Vert			Front	Side	
			ft	ft	°	ft	ft ²	ft ²	lb
Valmont 13'-5" Platform (Sprint)	C	None			0.0000	150.00	No Ice 18.43 1/2" Ice 22.32 1" Ice 26.21 2" Ice 33.99 4" Ice 49.55	18.43 22.32 26.21 33.99 49.55	1759.00 2143.00 2527.00 3295.00 4831.00

10' Dipole (City)	B	From Face	6.00 0.00 5.00		0.0000	130.00	No Ice 3.00 1/2" Ice 4.00 1" Ice 5.00 2" Ice 6.25 4" Ice 9.00	3.00 4.00 5.00 6.25 9.00	30.00 55.00 85.00 100.00 140.00
TMA (City)	B	From Face	2.00 0.00 0.00		0.0000	130.00	No Ice 1.40 1/2" Ice 1.56 1" Ice 1.73 2" Ice 2.09 4" Ice 2.92	0.70 0.82 0.95 1.24 1.91	5.00 15.34 27.81 59.96 158.48
6' Standoff (City)	B	From Face	3.00 0.00 0.00		0.0000	130.00	No Ice 4.97 1/2" Ice 6.12 1" Ice 7.27 2" Ice 9.57 4" Ice 14.17	4.97 6.12 7.27 9.57 14.17	70.00 130.00 190.00 310.00 550.00

742 213V01 w/Mount Pipe (Pocket)	A	From Face	0.00 0.00 0.00		0.0000	124.00	No Ice 5.41 1/2" Ice 5.99 1" Ice 6.54 2" Ice 7.65 4" Ice 9.99	4.75 6.10 7.09 8.97 12.93	46.84 91.94 144.76 277.34 685.64
742 213V01 w/Mount Pipe (Pocket)	B	From Face	0.00 0.00 0.00		0.0000	124.00	No Ice 5.41 1/2" Ice 5.99 1" Ice 6.54 2" Ice 7.65 4" Ice 9.99	4.75 6.10 7.09 8.97 12.93	46.84 91.94 144.76 277.34 685.64
742 213V01 w/Mount Pipe (Pocket)	C	From Face	0.00 0.00 0.00		0.0000	124.00	No Ice 5.41 1/2" Ice 5.99 1" Ice 6.54 2" Ice 7.65 4" Ice 9.99	4.75 6.10 7.09 8.97 12.93	46.84 91.94 144.76 277.34 685.64

LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	A	From Face	4.00 6.00 2.00		0.0000	114.00	No Ice 11.00 1/2" Ice 11.78 1" Ice 12.53 2" Ice 13.95 4" Ice 16.94	10.96 12.33 13.57 15.70 20.20	56.20 152.21 256.95 496.56 1133.83
LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	A	From Face	4.00 -2.00 2.00		0.0000	114.00	No Ice 11.00 1/2" Ice 11.78 1" Ice 12.53 2" Ice 13.95 4" Ice 16.94	10.96 12.33 13.57 15.70 20.20	56.20 152.21 256.95 496.56 1133.83
LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	B	From Face	4.00 6.00 2.00		0.0000	114.00	No Ice 11.00 1/2" Ice 11.78 1" Ice 12.53 2" Ice 13.95 4" Ice 16.94	10.96 12.33 13.57 15.70 20.20	56.20 152.21 256.95 496.56 1133.83
LPA-80063-6CF-EDIN-X w/Mount Pipe (Verizon)	B	From Face	4.00 -2.00 2.00		0.0000	114.00	No Ice 11.00 1/2" Ice 11.78 1" Ice 12.53 2" Ice 13.95	10.96 12.33 13.57 15.70	56.20 152.21 256.95 496.56

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	11 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA}		Weight	
			Horz	Vert			Front	Side		
			ft	ft	°	ft	ft ²	ft ²	lb	
RWA-80013 w/Mount Pipe (Verizon)	C	From Face	4.00		0.0000	114.00	4" Ice	16.94	20.20	1133.83
			6.00				No Ice	6.14	4.66	39.85
			2.00				1/2" Ice	6.85	5.70	90.85
							1" Ice	7.43	6.50	148.20
							2" Ice	8.63	8.14	285.62
RWA-80013 w/Mount Pipe (Verizon)	C	From Face	4.00		0.0000	114.00	4" Ice	11.19	11.63	685.30
			-2.00				No Ice	6.14	4.66	39.85
			2.00				1/2" Ice	6.85	5.70	90.85
							1" Ice	7.43	6.50	148.20
							2" Ice	8.63	8.14	285.62
LNx-6514DS-T4M w/Mount Pipe (Verizon)	A	From Face	4.00		0.0000	114.00	4" Ice	11.19	11.63	685.30
			-6.00				No Ice	8.41	6.83	60.30
			2.00				1/2" Ice	8.96	7.79	126.69
							1" Ice	9.52	8.62	200.90
							2" Ice	10.67	10.34	376.04
LNx-6514DS-T4M w/Mount Pipe (Verizon)	B	From Face	4.00		0.0000	114.00	4" Ice	13.07	14.13	863.78
			-6.00				No Ice	8.41	6.83	60.30
			2.00				1/2" Ice	8.96	7.79	126.69
							1" Ice	9.52	8.62	200.90
							2" Ice	10.67	10.34	376.04
LNx-6514DS-T4M w/Mount Pipe (Verizon)	C	From Face	4.00		0.0000	114.00	4" Ice	13.07	14.13	863.78
			-6.00				No Ice	8.41	6.83	60.30
			2.00				1/2" Ice	8.96	7.79	126.69
							1" Ice	9.52	8.62	200.90
							2" Ice	10.67	10.34	376.04
BXA-185060-12CF-EDIN-X w/Mount Pipe (Verizon)	A	From Face	4.00		0.0000	114.00	4" Ice	13.07	14.13	863.78
			2.00				No Ice	5.03	5.29	38.35
			2.00				1/2" Ice	5.58	6.46	84.33
							1" Ice	6.10	7.34	137.75
							2" Ice	7.15	9.13	270.51
MGD3-900TX w/Mount Pipe (Verizon)	B	From Face	4.00		0.0000	114.00	4" Ice	9.42	12.93	673.81
			2.00				No Ice	5.19	5.01	45.39
			2.00				1/2" Ice	5.74	6.18	90.69
							1" Ice	6.26	7.06	143.45
							2" Ice	7.32	8.86	274.97
MGD3-900TX w/Mount Pipe (Verizon)	C	From Face	4.00		0.0000	114.00	4" Ice	9.60	12.66	676.06
			2.00				No Ice	5.19	5.01	45.39
			2.00				1/2" Ice	5.74	6.18	90.69
							1" Ice	6.26	7.06	143.45
							2" Ice	7.32	8.86	274.97
TMA (Verizon)	A	From Face	3.00		0.0000	114.00	4" Ice	9.60	12.66	676.06
			-5.00				No Ice	1.40	0.70	5.00
			2.00				1/2" Ice	1.56	0.82	15.34
							1" Ice	1.73	0.95	27.81
							2" Ice	2.09	1.24	59.96
TMA (Verizon)	B	From Face	3.00		0.0000	114.00	4" Ice	2.92	1.91	158.48
			-5.00				No Ice	1.40	0.70	5.00
			2.00				1/2" Ice	1.56	0.82	15.34
							1" Ice	1.73	0.95	27.81
							2" Ice	2.09	1.24	59.96
TMA (Verizon)	C	From Face	3.00		0.0000	114.00	4" Ice	2.92	1.91	158.48
			-5.00				No Ice	1.40	0.70	5.00
			2.00				1/2" Ice	1.56	0.82	15.34
							1" Ice	1.73	0.95	27.81
							2" Ice	2.09	1.24	59.96
Valmont 13'-5" Platform	C	None			0.0000	114.00	No Ice	18.43	18.43	1759.00

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page 13 of 21
	Project 28744	Date 16:00:00 08/05/14
	Client Transcend Wireless / Sprint	Designed by JDS

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft ²	Weight lb	
MF-900B	B	Grid	From Leg	5.00 0.00 0.00	0.0000		176.00	1.33	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.66 1.58 0.00 0.00 0.00	13.00 21.09 29.17 45.35 77.70
MF-900B	C	Grid	From Leg	5.00 0.00 0.00	0.0000		176.00	1.33	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.66 1.58 0.00 0.00 0.00	13.00 21.09 29.17 45.35 77.70
MF-900B	A	Grid	From Face	5.00 0.00 0.00	0.0000		162.00	1.33	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.66 1.58 0.00 0.00 0.00	13.00 21.09 29.17 45.35 77.70
MF-900B	B	Grid	From Leg	5.00 0.00 0.00	0.0000		100.00	1.33	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.66 1.58 0.00 0.00 0.00	13.00 21.09 29.17 45.35 77.70

VHLP2.5-11 (Clearwire)	A	Paraboloid w/Shroud (HP)	From Face	5.00 -2.00 4.00	0.0000		150.00	2.92	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	6.68 7.07 7.46 8.24 9.80	48.00 76.00 104.00 160.00 272.00
VHLP2.5-11 (Clearwire)	A	Paraboloid w/Shroud (HP)	From Face	5.00 2.00 2.00	0.0000		150.00	2.92	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	6.68 7.07 7.46 8.24 9.80	48.00 76.00 104.00 160.00 272.00
VHLP2.5-11 (Clearwire)	B	Paraboloid w/Shroud (HP)	From Face	5.00 2.00 2.00	0.0000		150.00	2.92	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	6.68 7.07 7.46 8.24 9.80	48.00 76.00 104.00 160.00 272.00
VHLP2.5-11 (Clearwire)	C	Paraboloid w/Shroud (HP)	From Face	5.00 2.00 2.00	0.0000		150.00	2.92	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	6.68 7.07 7.46 8.24 9.80	48.00 76.00 104.00 160.00 272.00

Force Totals

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M _x lb-ft	Sum of Overturning Moments, M _z lb-ft	Sum of Torques lb-ft
Leg Weight	30638.40					
Bracing Weight	0.00					
Total Member Self-Weight	30638.40			-179.63	869.20	

Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	14 of 21
Project	28744	Date	16:00:00 08/05/14
Client	Transcend Wireless / Sprint	Designed by	JDS

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M _x lb-ft	Sum of Overturning Moments, M _z lb-ft	Sum of Torques lb-ft
Total Weight	51247.07			-179.63	869.20	
Wind 0 deg - No Ice		-99.33	-34959.61	-4139151.49	17021.40	761.14
Wind 30 deg - No Ice		17363.56	-30276.72	-3584701.16	-2051899.68	-2383.05
Wind 60 deg - No Ice		30313.96	-17325.51	-2045427.16	-3592248.76	-3402.31
Wind 90 deg - No Ice		35050.09	150.75	23760.69	-4155667.57	-3596.53
Wind 120 deg - No Ice		30373.08	17556.79	2081737.09	-3601824.08	-3914.55
Wind 150 deg - No Ice		17637.38	30303.06	3588706.48	-2094943.27	-3383.65
Wind 180 deg - No Ice		167.29	34940.30	4135900.45	-25496.21	-1247.15
Wind 210 deg - No Ice		-17504.05	30195.59	3571801.76	2075352.43	2072.68
Wind 240 deg - No Ice		-30302.26	17401.21	2056617.72	3592358.86	3336.38
Wind 270 deg - No Ice		-34978.52	-15.64	-3696.12	4146454.03	3531.93
Wind 300 deg - No Ice		-30276.50	-17497.05	-2073054.25	3589107.86	3649.78
Wind 330 deg - No Ice		-17498.28	-30300.74	-3588412.12	2075915.70	3428.36
Member Ice	7381.04					
Total Weight Ice	69802.52			-265.32	3317.89	
Wind 0 deg - Ice		-25.82	-9353.37	-1125475.89	7290.62	187.93
Wind 30 deg - Ice		4645.98	-8101.39	-974822.23	-555001.33	-637.91
Wind 60 deg - Ice		8099.14	-4637.69	-556711.52	-971871.65	-976.71
Wind 90 deg - Ice		9355.17	34.23	5197.96	-1123311.77	-1067.01
Wind 120 deg - Ice		8107.89	4687.14	564132.81	-973445.38	-1121.10
Wind 150 deg - Ice		4707.73	8098.71	974114.46	-564815.93	-921.62
Wind 180 deg - Ice		41.41	9345.45	1123799.09	-3299.25	-319.19
Wind 210 deg - Ice		-4679.39	8080.71	971149.81	566655.84	573.72
Wind 240 deg - Ice		-8097.65	4651.42	558390.29	978080.28	977.89
Wind 270 deg - Ice		-9338.13	-7.60	-1619.66	1127235.50	1079.51
Wind 300 deg - Ice		-8083.98	-4676.75	-563085.69	976313.56	1051.60
Wind 330 deg - Ice		-4675.11	-8099.27	-974700.38	566354.84	892.61
Total Weight	51247.07			-179.63	869.20	
Wind 0 deg - Service		-55.87	-19664.78	-2328994.38	8840.97	428.14
Wind 30 deg - Service		9767.00	-17030.65	-2017116.06	-1154927.14	-1340.46
Wind 60 deg - Service		17051.60	-9745.60	-1151274.44	-2021373.49	-1913.80
Wind 90 deg - Service		19715.68	84.80	12643.72	-2338296.58	-2023.05
Wind 120 deg - Service		17084.86	9875.70	1170255.45	-2026759.61	-2201.94
Wind 150 deg - Service		9921.03	17045.47	2017925.73	-1179139.15	-1903.30
Wind 180 deg - Service		94.10	19653.92	2325722.34	-15075.19	-701.52
Wind 210 deg - Service		-9846.03	16985.02	2008416.83	1166652.18	1165.88
Wind 240 deg - Service		-17045.02	9788.18	1156125.81	2019968.29	1876.72
Wind 270 deg - Service		-19675.42	-8.79	-2800.73	2331646.83	1986.71
Wind 300 deg - Service		-17030.53	-9842.09	-1166814.68	2018139.61	2053.00
Wind 330 deg - Service		-9842.78	-17044.17	-2019203.48	1166969.02	1928.45

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	15 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Comb. No.	Description
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
L1	176 - 130.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-19499.26	1801.57	-2.70
			Max. Mx	11	-10490.28	435853.55	1078.08
			Max. My	2	-10505.00	3083.85	432169.55
			Max. Vy	5	17848.94	-435720.50	-3359.21
			Max. Vx	2	-17673.44	3083.85	432169.55
			Max. Torque	3			2906.23
L2	130.75 - 86.12	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-35689.15	-244.54	1794.48
			Max. Mx	5	-21417.41	-1439277.45	-10356.36
			Max. My	2	-21430.79	7445.00	1429901.28
			Max. Vy	5	27622.33	-1439277.45	-10356.36
			Max. Vx	2	-27525.70	7445.00	1429901.28
			Max. Torque	6			3854.39
L3	86.12 - 43	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-50445.63	1882.60	1144.28
			Max. Mx	5	-33654.78	-2678690.41	-17020.89
			Max. My	2	-33661.32	12390.02	2665817.35
			Max. Vy	5	31589.15	-2678690.41	-17020.89
			Max. Vx	2	-31494.48	12390.02	2665817.35
			Max. Torque	6			3981.56
L4	43 - 1	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-70618.58	3365.83	287.94
			Max. Mx	5	-51225.08	-4314922.86	-24806.00
			Max. My	2	-51225.22	17771.00	4297662.47
			Max. Vy	5	35082.25	-4314922.86	-24806.00

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page 16 of 21
	Project 28744	Date 16:00:00 08/05/14
	Client Transcend Wireless / Sprint	Designed by JDS

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
			Max. Vx	2	-34991.64	17771.00	4297662.47
			Max. Torque	6			3913.16

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Pole	Max. Vert	24	70618.58	9338.17	7.60
	Max. H _x	11	51247.07	34978.52	15.64
	Max. H _z	2	51247.08	99.33	34959.63
	Max. M _x	2	4297662.47	99.33	34959.63
	Max. M _z	5	4314922.86	-35050.11	-150.75
	Max. Torsion	6	3833.37	-30373.08	-17556.79
	Min. Vert	1	51247.07	0.00	0.00
	Min. H _x	5	51247.08	-35050.11	-150.75
	Min. H _z	8	51247.08	-167.29	-34940.32
	Min. M _x	8	-4294267.13	-167.29	-34940.32
	Min. M _z	11	-4305361.50	34978.52	15.64
	Min. Torsion	12	-3572.80	30276.50	17497.05

Tower Mast Reaction Summary

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x lb-ft	Overturning Moment, M _z lb-ft	Torque lb-ft
Dead Only	51247.07	0.00	0.00	-179.63	869.20	0.00
Dead+Wind 0 deg - No Ice	51247.08	-99.33	-34959.63	-4297662.47	17771.15	775.48
Dead+Wind 30 deg - No Ice	51247.07	17363.56	-30276.72	-3722003.90	-2130480.04	-2308.07
Dead+Wind 60 deg - No Ice	51247.07	30313.96	-17325.51	-2123633.83	-3729970.76	-3310.87
Dead+Wind 90 deg - No Ice	51247.08	35050.11	150.75	24806.67	-4314922.86	-3506.29
Dead+Wind 120 deg - No Ice	51247.07	30373.08	17556.79	2161499.53	-3739862.56	-3833.37
Dead+Wind 150 deg - No Ice	51247.07	17637.38	30303.06	3726116.30	-2175303.24	-3330.99
Dead+Wind 180 deg - No Ice	51247.08	167.29	34940.32	4294267.13	-26601.67	-1248.37
Dead+Wind 210 deg - No Ice	51247.07	-17504.05	30195.59	3708553.94	2154889.23	2001.38
Dead+Wind 240 deg - No Ice	51247.07	-30302.26	17401.21	2135311.85	3730043.01	3238.56
Dead+Wind 270 deg - No Ice	51247.07	-34978.52	-15.64	-3876.83	4305361.50	3438.20
Dead+Wind 300 deg - No Ice	51247.07	-30276.50	-17497.05	-2152460.95	3726676.89	3572.80
Dead+Wind 330 deg - No Ice	51247.07	-17498.28	-30300.74	-3725829.56	2155531.54	3379.93
Dead+Ice+Temp	70618.58	-0.00	-0.00	-287.94	3365.83	-0.04
Dead+Wind 0 deg+Ice+Temp	70618.58	-25.82	-9353.40	-1197075.04	7768.43	195.94
Dead+Wind 30 deg+Ice+Temp	70618.58	4646.00	-8101.42	-1036846.42	-590267.43	-606.79
Dead+Wind 60 deg+Ice+Temp	70618.58	8099.17	-4637.71	-592127.65	-1033678.42	-931.50
Dead+Wind 90 deg+Ice+Temp	70618.58	9355.20	34.23	5471.11	-1194753.43	-1019.51
Dead+Wind 120 deg+Ice+Temp	70618.58	8107.92	4687.16	599883.03	-1035371.53	-1083.58
Dead+Wind 150 deg+Ice+Temp	70618.58	4707.74	8098.74	1035891.75	-600785.93	-904.06
Dead+Wind 180 deg+Ice+Temp	70618.58	41.41	9345.49	1195072.16	-3583.66	-326.73
Dead+Wind 210 deg+Ice+Temp	70618.58	-4679.40	8080.74	1032707.64	602655.98	542.02
Dead+Wind 240 deg+Ice+Temp	70618.58	-8097.68	4651.43	593721.05	1040235.08	931.61
Dead+Wind 270 deg+Ice+Temp	70618.58	-9338.17	-7.60	-1848.82	1198871.66	1031.26
Dead+Wind 300 deg+Ice+Temp	70618.58	-8084.01	-4676.77	-598971.25	1038362.23	1013.92
Dead+Wind 330 deg+Ice+Temp	70618.58	-4675.12	-8099.30	-1036725.64	602357.98	875.29
Dead+Wind 0 deg - Service	51247.07	-55.87	-19664.79	-2419996.09	10406.34	435.07

<p style="text-align: center;">tnxTower</p> <p style="text-align: center;">Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999</p>	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	17 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x lb-ft	Overturning Moment, M _z lb-ft	Torque lb-ft
Dead+Wind 30 deg - Service	51247.07	9767.00	-17030.66	-2095851.98	-1199212.52	-1310.47
Dead+Wind 60 deg - Service	51247.07	17051.60	-9745.60	-1195856.61	-2099855.34	-1873.75
Dead+Wind 90 deg - Service	51247.07	19715.69	84.80	13876.02	-2429262.77	-1981.65
Dead+Wind 120 deg - Service	51247.07	17084.86	9875.70	1217011.13	-2105465.47	-2166.98
Dead+Wind 150 deg - Service	51247.07	9921.03	17045.47	2098013.30	-1224484.10	-1883.73
Dead+Wind 180 deg - Service	51247.07	94.10	19653.93	2417898.90	-14586.33	-704.99
Dead+Wind 210 deg - Service	51247.07	-9846.03	16985.02	2088091.35	1213762.59	1136.26
Dead+Wind 240 deg - Service	51247.07	-17045.02	9788.18	1202245.58	2100702.43	1834.28
Dead+Wind 270 deg - Service	51247.07	-19675.43	-8.80	-2279.87	2424649.61	1943.97
Dead+Wind 300 deg - Service	51247.07	-17030.53	-9842.09	-1212099.89	2098810.21	2018.91
Dead+Wind 330 deg - Service	51247.07	-9842.78	-17044.17	-2098025.35	1214128.29	1910.53

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
1	0.00	-51247.07	0.00	0.00	51247.07	0.00	0.000%
2	-99.33	-51247.07	-34959.61	99.33	51247.08	34959.63	0.000%
3	17363.56	-51247.07	-30276.72	-17363.56	51247.07	30276.72	0.000%
4	30313.96	-51247.07	-17325.51	-30313.96	51247.07	17325.51	0.000%
5	35050.09	-51247.07	150.75	-35050.11	51247.08	-150.75	0.000%
6	30373.08	-51247.07	17556.79	-30373.08	51247.07	-17556.79	0.000%
7	17637.38	-51247.07	30303.06	-17637.38	51247.07	-30303.06	0.000%
8	167.29	-51247.07	34940.30	-167.29	51247.08	-34940.32	0.000%
9	-17504.05	-51247.07	30195.59	17504.05	51247.07	-30195.59	0.000%
10	-30302.26	-51247.07	17401.21	30302.26	51247.07	-17401.21	0.000%
11	-34978.52	-51247.07	-15.64	34978.52	51247.07	15.64	0.000%
12	-30276.50	-51247.07	-17497.05	30276.50	51247.07	17497.05	0.000%
13	-17498.28	-51247.07	-30300.74	17498.28	51247.07	30300.74	0.000%
14	0.00	-70618.58	0.00	0.00	70618.58	0.00	0.000%
15	-25.82	-70618.58	-9353.37	25.82	70618.58	9353.40	0.000%
16	4645.98	-70618.58	-8101.39	-4646.00	70618.58	8101.42	0.000%
17	8099.14	-70618.58	-4637.69	-8099.17	70618.58	4637.71	0.000%
18	9355.17	-70618.58	34.23	-9355.20	70618.58	-34.23	0.000%
19	8107.89	-70618.58	4687.14	-8107.92	70618.58	-4687.16	0.000%
20	4707.73	-70618.58	8098.71	-4707.74	70618.58	-8098.74	0.000%
21	41.41	-70618.58	9345.45	-41.41	70618.58	-9345.49	0.000%
22	-4679.39	-70618.58	8080.71	4679.40	70618.58	-8080.74	0.000%
23	-8097.65	-70618.58	4651.42	8097.68	70618.58	-4651.43	0.000%
24	-9338.13	-70618.58	-7.60	9338.17	70618.58	7.60	0.000%
25	-8083.98	-70618.58	-4676.75	8084.01	70618.58	4676.77	0.000%
26	-4675.11	-70618.58	-8099.27	4675.12	70618.58	8099.30	0.000%
27	-55.87	-51247.07	-19664.78	55.87	51247.07	19664.79	0.000%
28	9767.00	-51247.07	-17030.65	-9767.00	51247.07	17030.66	0.000%
29	17051.60	-51247.07	-9745.60	-17051.60	51247.07	9745.60	0.000%
30	19715.68	-51247.07	84.80	-19715.69	51247.07	-84.80	0.000%
31	17084.86	-51247.07	9875.70	-17084.86	51247.07	-9875.70	0.000%
32	9921.03	-51247.07	17045.47	-9921.03	51247.07	-17045.47	0.000%
33	94.10	-51247.07	19653.92	-94.10	51247.07	-19653.93	0.000%
34	-9846.03	-51247.07	16985.02	9846.03	51247.07	-16985.02	0.000%
35	-17045.02	-51247.07	9788.18	17045.02	51247.07	-9788.18	0.000%
36	-19675.42	-51247.07	-8.79	19675.43	51247.07	8.80	0.000%
37	-17030.53	-51247.07	-9842.09	17030.53	51247.07	9842.09	0.000%
38	-9842.78	-51247.07	-17044.17	9842.78	51247.07	17044.17	0.000%

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	18 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Non-Linear Convergence Results

<i>Load Combination</i>	<i>Converged?</i>	<i>Number of Cycles</i>	<i>Displacement Tolerance</i>	<i>Force Tolerance</i>
1	Yes	4	0.0000001	0.0000001
2	Yes	4	0.0000001	0.00059613
3	Yes	5	0.0000001	0.00082558
4	Yes	5	0.0000001	0.00088591
5	Yes	4	0.0000001	0.00087458
6	Yes	5	0.0000001	0.00084604
7	Yes	5	0.0000001	0.00089537
8	Yes	4	0.0000001	0.00072476
9	Yes	5	0.0000001	0.00088341
10	Yes	5	0.0000001	0.00082907
11	Yes	5	0.0000001	0.00005209
12	Yes	5	0.0000001	0.00088877
13	Yes	5	0.0000001	0.00084178
14	Yes	4	0.0000001	0.00000397
15	Yes	5	0.0000001	0.00021263
16	Yes	5	0.0000001	0.00027449
17	Yes	5	0.0000001	0.00027907
18	Yes	5	0.0000001	0.00021259
19	Yes	5	0.0000001	0.00027626
20	Yes	5	0.0000001	0.00028078
21	Yes	5	0.0000001	0.00021159
22	Yes	5	0.0000001	0.00027971
23	Yes	5	0.0000001	0.00027501
24	Yes	5	0.0000001	0.00021330
25	Yes	5	0.0000001	0.00028187
26	Yes	5	0.0000001	0.00027825
27	Yes	4	0.0000001	0.00025570
28	Yes	5	0.0000001	0.00021865
29	Yes	5	0.0000001	0.00024293
30	Yes	4	0.0000001	0.00041571
31	Yes	5	0.0000001	0.00022610
32	Yes	5	0.0000001	0.00024564
33	Yes	4	0.0000001	0.00028038
34	Yes	5	0.0000001	0.00024154
35	Yes	5	0.0000001	0.00021992
36	Yes	4	0.0000001	0.00047222
37	Yes	5	0.0000001	0.00024370
38	Yes	5	0.0000001	0.00022501

Maximum Tower Deflections - Service Wind

<i>Section No.</i>	<i>Elevation</i> <i>ft</i>	<i>Horz. Deflection</i> <i>in</i>	<i>Gov. Load Comb.</i>	<i>Tilt</i> <i>°</i>	<i>Twist</i> <i>°</i>
L1	176 - 130.75	67.206	31	3.4101	0.0084
L2	135.25 - 86.12	39.403	31	2.9336	0.0056
L3	91.87 - 43	17.167	31	1.8691	0.0034
L4	50 - 1	4.803	31	0.9020	0.0012

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page 19 of 21
	Project 28744	Date 16:00:00 08/05/14
	Client Transcend Wireless / Sprint	Designed by JDS

Critical Deflections and Radius of Curvature - Service Wind

Elevation	Appurtenance	Gov. Load Comb.	Deflection	Tilt	Twist	Radius of Curvature
ft			in	°	°	ft
176.00	MF-900B	31	67.206	3.4101	0.0099	20707
170.00	800 10121 w/Mount Pipe	31	62.924	3.3598	0.0092	17256
162.00	MF-900B	31	57.258	3.2880	0.0084	7394
160.00	(3) DR65-19-00DPQ w/Mount Pipe	31	55.855	3.2687	0.0082	6470
154.00	VHLP2.5-11	31	51.696	3.2054	0.0076	4704
152.00	VHLP2.5-11	31	50.328	3.1823	0.0074	4312
150.00	APXV9TM14-ALU-I20 w/Mount Pipe	31	48.972	3.1581	0.0072	3980
130.00	10' Dipole	31	36.223	2.8304	0.0058	2513
124.00	742 213V01 w/Mount Pipe	31	32.751	2.6984	0.0055	2487
114.00	LPA-80063-6CF-EDIN-X w/Mount Pipe	31	27.351	2.4537	0.0048	2442
100.00	MF-900B	31	20.621	2.0840	0.0041	2377
76.00	GPS	31	11.403	1.4747	0.0027	2306
61.00	GPS	31	7.160	1.1337	0.0019	2275

Maximum Tower Deflections - Design Wind

Section No.	Elevation	Horz. Deflection	Gov. Load Comb.	Tilt	Twist
	ft	in		°	°
L1	176 - 130.75	119.127	6	6.0511	0.0147
L2	135.25 - 86.12	69.888	6	5.2059	0.0098
L3	91.87 - 43	30.471	6	3.3180	0.0061
L4	50 - 1	8.529	6	1.6018	0.0022

Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov. Load Comb.	Deflection	Tilt	Twist	Radius of Curvature
ft			in	°	°	ft
176.00	MF-900B	6	119.127	6.0511	0.0175	11873
170.00	800 10121 w/Mount Pipe	6	111.545	5.9617	0.0164	9894
162.00	MF-900B	6	101.511	5.8345	0.0149	4238
160.00	(3) DR65-19-00DPQ w/Mount Pipe	6	99.027	5.8001	0.0145	3708
154.00	VHLP2.5-11	6	91.661	5.6879	0.0134	2695
152.00	VHLP2.5-11	6	89.239	5.6469	0.0131	2470
150.00	APXV9TM14-ALU-I20 w/Mount Pipe	6	86.837	5.6039	0.0127	2279
130.00	10' Dipole	6	64.255	5.0228	0.0105	1435
124.00	742 213V01 w/Mount Pipe	6	58.102	4.7888	0.0099	1418
114.00	LPA-80063-6CF-EDIN-X w/Mount Pipe	6	48.531	4.3548	0.0086	1388
100.00	MF-900B	6	36.598	3.6991	0.0073	1349
76.00	GPS	6	20.244	2.6182	0.0048	1305
61.00	GPS	6	12.714	2.0130	0.0033	1284

Base Plate Design Data

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	20 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Plate Thickness	Number of Anchor Bolts	Anchor Bolt Size	Actual	Actual	Actual	Actual	Controlling Condition	Ratio
			Allowable Ratio Bolt Tension lb	Allowable Ratio Bolt Compression lb	Allowable Ratio Plate Stress ksi	Allowable Ratio Stiffener Stress ksi		
in		in						
2.0000	18	2.2500	159209.11	164900.78	41.902	29.123	Bolt T	1.21 ✓
			131210.58	217809.56	45.000	45.000		
			1.21	0.76	0.93	0.65		

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _a ft	KL/r	F _a ksi	A in ²	Actual P lb	Allow. P _a lb	Ratio P/P _a
L1	176 - 130.75 (1)	TP31.8x21x0.25	45.25	0.00	0.0	39.000	24.1827	-10475.40	943125.00	0.011
L2	130.75 - 86.12 (2)	TP41.82x30.226x0.3125	49.13	0.00	0.0	39.000	39.8244	-21413.70	1553150.00	0.014
L3	86.12 - 43 (3)	TP51.36x39.8381x0.375	48.87	0.00	0.0	39.000	58.7205	-33652.80	2290100.00	0.015
L4	43 - 1 (4)	TP60.5x48.9596x0.4375	49.00	0.00	0.0	39.000	83.4043	-51225.00	3252770.00	0.016

Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M _x lb-ft	Actual f _{bx} ksi	Allow. F _{bx} ksi	Ratio f _{bx} /F _{bx}	Actual M _y lb-ft	Actual f _{by} ksi	Allow. F _{by} ksi	Ratio f _{by} /F _{by}
L1	176 - 130.75 (1)	TP31.8x21x0.25	436199.17	28.792	39.000	0.738	0.00	0.000	39.000	0.000
L2	130.75 - 86.12 (2)	TP41.82x30.226x0.3125	1440625.00	43.811	39.000	1.123	0.00	0.000	39.000	0.000
L3	86.12 - 43 (3)	TP51.36x39.8381x0.375	2681558.33	45.003	39.000	1.154	0.00	0.000	39.000	0.000
L4	43 - 1 (4)	TP60.5x48.9596x0.4375	4319566.67	41.909	39.000	1.075	0.00	0.000	39.000	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V lb	Actual f _v ksi	Allow. F _v ksi	Ratio f _v /F _v	Actual T lb-ft	Actual f _{vr} ksi	Allow. F _{vr} ksi	Ratio f _{vr} /F _{vr}
L1	176 - 130.75 (1)	TP31.8x21x0.25	17879.00	0.739	26.000	0.057	1974.13	0.064	26.000	0.002
L2	130.75 - 86.12 (2)	TP41.82x30.226x0.3125	27656.70	0.694	26.000	0.053	3841.88	0.057	26.000	0.002
L3	86.12 - 43 (3)	TP51.36x39.8381x0.375	31622.20	0.539	26.000	0.041	3948.91	0.032	26.000	0.001
L4	43 - 1 (4)	TP60.5x48.9596x0.4375	35114.40	0.421	26.000	0.032	3837.76	0.018	26.000	0.001

tnxTower Ramaker & Associates 1120 Dallas St. Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Berlin / RT15 / Fire Dept. (CT43XC846-A)	Page	21 of 21
	Project	28744	Date	16:00:00 08/05/14
	Client	Transcend Wireless / Sprint	Designed by	JDS

Pole Interaction Design Data

Section No.	Elevation ft	Ratio	Ratio	Ratio	Ratio	Ratio	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
		P	f_{bx}	f_{by}	f_v	f_{vt}			
L1	176 - 130.75 (1)	0.011	0.738	0.000	0.057	0.002	0.750	1.333	H1-3+VT
L2	130.75 - 86.12 (2)	0.014	1.123	0.000	0.053	0.002	1.138	1.333	H1-3+VT
L3	86.12 - 43 (3)	0.015	1.154	0.000	0.041	0.001	1.169	1.333	H1-3+VT
L4	43 - 1 (4)	0.016	1.075	0.000	0.032	0.001	1.091	1.333	H1-3+VT

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	SF*P _{allow} lb	% Capacity	Pass Fail	
L1	176 - 130.75	Pole	TP31.8x21x0.25	1	-10475.40	1257185.57	56.3	Pass	
L2	130.75 - 86.12	Pole	TP41.82x30.226x0.3125	2	-21413.70	2070348.86	85.4	Pass	
L3	86.12 - 43	Pole	TP51.36x39.8381x0.375	3	-33652.80	3052703.17	87.7	Pass	
L4	43 - 1	Pole	TP60.5x48.9596x0.4375	4	-51225.00	4335942.23	81.8	Pass	
							Summary		
							Pole (L3)	87.7	Pass
							Base Plate	91.0	Pass
							RATING =	91.0	Pass

 * CAISSON - Pier Foundations Analysis and Design - Copyright Power Line Systems, Inc. 1993-2013 *

Project Title: Berlin / RT15 / Fire Dept. (CT43XC846-A)
 Project Notes: 28744

Calculation Method: Full 8CD

***** I N P U T D A T A

Pier Properties

Diameter (ft)	Distance of Top of Pier above Ground (ft)	Concrete Strength (ksi)	Steel Yield Strength (ksi)
7.50	4.00	3.00	60.00

Soil Properties

Layer	Type	Thickness (ft)	Depth at Top of Layer (ft)	Density (lbs/ft^3)	CU (psf)	KP	PHI (deg)
1	Sand	3.33	0.00	62.0		1.000	
2	Sand	1.67	3.33	62.0		3.000	30.00
3	Sand	6.00	5.00	62.0		3.255	32.00
4	Sand	5.00	11.00	62.0		3.537	34.00
5	Sand	30.00	16.00	62.0		3.852	36.00

Design (Factored) Loads at Top of Pier

Moment (ft-k)	Axial Load (kips)	Shear Load (kips)	Additional Safety Factor Against Soil Failure
4365.8	51.2	35.37	2.60

***** R E S U L T S

Calculated Pier Properties

Length (ft)	Weight (kips)	Pressure Due To Axial Load (psf)	Pressure Due To Weight (psf)	Total End-Bearing Pressure (psf)
35.000	231.938	1158.5	5250.0	6408.5

Ultimate Resisting Forces Along Pier

Type	Distance of Top of Layer to Top of Pier (ft)	Thickness (ft)	Density (lbs/ft ³)	CU (psf)	KP	Force (kips)	Arm (ft)
Sand	4.00	3.33	62.0		1.000	7.73	6.22
Sand	7.33	1.67	62.0		3.000	29.11	8.22
Sand	9.00	6.00	62.0		3.255	217.95	12.37
Sand	15.00	5.00	62.0		3.537	333.05	17.65
Sand	20.00	6.72	62.0		3.852	699.30	23.56
Sand	26.72	8.28	62.0		3.852	-1194.87	31.07

Shear and Moments Along Pier

Distance below Top of Pier (ft)	Shear (with Safety Factor) (kips)	Moment (with Safety Factor) (ft-k)	Shear (without Safety Factor) (kips)	Moment (without Safety Factor) (ft-k)
0.00	92.3	11792.3	35.5	4535.5
3.50	92.3	12115.2	35.5	4659.7
7.00	86.0	12431.9	33.1	4781.5
10.50	16.3	12633.6	6.3	4859.1
14.00	-114.8	12477.3	-44.2	4799.0
17.50	-313.6	11750.2	-120.6	4519.3
21.00	-584.2	10205.7	-224.7	3925.3
24.50	-936.9	7562.9	-360.3	2908.8
28.00	-1034.4	3774.0	-397.8	1451.5
31.50	-550.1	981.9	-211.6	377.7
35.00	-0.0	-0.0	-0.0	-0.0

Reinforcement and Capacity

Total Reinforcement Percent	Reinforcement Area (in ²)	Usable Axial Capacity (kips)	Usable Moment Capacity (ft-k)
0.48	30.54	51.2	5031.2

US Standard Re-Bars (Select one of the following)

Quantity	Name	Area (in ²)	Diameter (in)	Spacing (in)
153	#4	0.20	0.500	1.64
99	#5	0.31	0.625	2.54
70	#6	0.44	0.750	3.59
51	#7	0.60	0.875	4.93
39	#8	0.79	1.000	6.44
31	#9	1.00	1.128	8.11
25	#10	1.27	1.270	10.05
20	#11	1.56	1.410	12.57
14	#14	2.25	1.693	17.95

APPENDIX C
MOUNT CALCULATIONS


Search Results

Latitude: 41.6062
Longitude: -72.7497

**ASCE 7-10 Wind Speeds
(3-sec peak gust MPH*):**

Risk Category I: 113
Risk Category II: 124
Risk Category III-IV: 133
MRI 10 Year:** 77
MRI 25 Year:** 87
MRI 50 Year:** 93
MRI 100 Year:** 100

ASCE 7-05: 102
ASCE 7-93: 81



*MPH(Miles per hour)

**MRI Mean Recurrence Interval (years)

Users should consult with local building officials
to determine if there are community-specific wind speed
requirements that govern.

WIND SPEED WEB SITE DISCLAIMER:

While the information presented on this web site is believed to be correct, ATC assumes no responsibility or liability for its accuracy. The material presented in the wind speed report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the wind speed report provided by this web site. Users of the information from this web site assume all liability arising from such use. Use of the output of this web site does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site(s) described by latitude/longitude location in the wind speed report.



1120 Dallas Street
 Sauk City, WI 53583
 Office: (608) 643-4100

Job: 28744
 Project: Berlin/RT15/Fire Dept. (CT43XC846-A)
 By: JMO
 Date: 6/19/2014

Wind Load on Antennas TIA-222

2.6.9.6 Velocity Pressure

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	C	Exposure Category
V:	102 mph	Basic Wind Speed (Annex B)
z:	150 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K _z :	1.38	Velocity Pressure Coefficient (2.6.5.2)
K _{zt} :	1	Topographic Factor (2.6.6.4)
K _d :	0.95	Wind Direction Probability Factor (Table 2-2)

q_z = 34.9 psf

G_h: 1.00 Appurtenances and their Connections

Mount & Antenna Wind Loads

Appurtenance	Height	Width	h/D	Shape	C _a	A _f	F = q _z G _h C _a A _a	
Pipe2STD x 8.5 ft	102.0 in	2.4 in	42.9	Round	1.200	1.69 sf	70.6 lb	8.3 plf
L2X2X1/8 x 1 ft	12.0 in	2.0 in	6.0	Flat	1.356	0.17 sf	7.9 lb	7.9 plf
HSS4X4X1/4 x 15 ft	180.0 in	4.0 in	45.0	Flat	2.000	5.00 sf	348.8 lb	23.3 plf
HSS4X4X1/4 x 8.5 ft	102.0 in	4.0 in	25.5	Flat	2.000	2.83 sf	197.6 lb	23.3 plf
APXVSPP18-C-A20	72.0 in	11.9 in	6.1	Flat	1.358	5.95 sf	281.6 lb	
1900MHz 4x40W RRH	25.1 in	11.1 in	2.3	Flat	1.200	1.93 sf	81.0 lb	
800MHz 2x50W RRH	19.0 in	13.0 in	1.5	Flat	1.200	1.72 sf	71.8 lb	
840 10054	42.0 in	12.7 in	3.3	Flat	1.236	3.70 sf	159.7 lb	
DAP	16.1 in	11.6 in	1.4	Flat	1.200	1.30 sf	54.6 lb	
VHLP2.5	35.0 in	0.0 in	1.0	Generic	1.262	6.68 sf	294.0 lb	
VHLP2	26.1 in	0.0 in	1.0	Generic	1.262	3.72 sf	163.5 lb	
APXV9TM14-ALU-120	56.3 in	12.6 in	4.5	Flat	1.287	4.93 sf	221.2 lb	
TD-RRH8x20	26.1 in	18.6 in	1.4	Flat	1.200	3.37 sf	141.1 lb	



1120 Dallas Street
 Sauk City, WI 53583
 Office: (608) 643-4100

Job: 28744
 Project: Berlin/RT15/Fire Dept. (CT43XC846-A)
 By: JMO
 Date: 6/19/2014

Wind Load on Antennas TIA-222

2.6.9.6 Velocity Pressure

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$


Occupancy:	II	Classification of Structures (Table 2-1)
Exposure:	C	Exposure Category
V:	102 mph	Basic Wind Speed (Annex B)
z:	150 ft	Height above ground level to the center of the antenna
I:	1.00	Importance Factor (Table 2-3)
K _z :	1.38	Velocity Pressure Coefficient (2.6.5.2)
K _{zt} :	1	Topographic Factor (2.6.6.4)
K _d :	0.95	Wind Direction Probability Factor (Table 2-2)

q_z = 34.9 psf

G_h: 1.00 Appurtenances and their Connections

Mount & Antenna Wind Loads

Appurtenance	Height	Depth	h/D	Shape	C _a	A _f	F = q _z G _h C _a A _a	
Pipe2STD x 8.5 ft	102.0 in	2.4 in	42.9	Round	1.200	1.69 sf	70.6 lb	8.3 plf
L2X2X1/8 x 1 ft	12.0 in	2.0 in	6.0	Flat	1.356	0.17 sf	7.9 lb	7.9 plf
HSS4X4X1/4 x 15 ft	180.0 in	4.0 in	45.0	Flat	2.000	5.00 sf	348.8 lb	23.3 plf
HSS4X4X1/4 x 8.5 ft	102.0 in	4.0 in	25.5	Flat	2.000	2.83 sf	197.6 lb	23.3 plf
APXVSPP18-C-A20	72.0 in	7.0 in	10.3	Flat	1.509	3.50 sf	184.5 lb	
1900MHz 4x40W RRH	25.1 in	10.7 in	2.3	Flat	1.200	1.86 sf	78.0 lb	
800MHz 2x50W RRH	19.0 in	12.2 in	1.6	Flat	1.200	1.61 sf	67.4 lb	
840 10054	42.0 in	2.8 in	15.0	Flat	1.667	0.82 sf	47.5 lb	
DAP	16.1 in	5.3 in	3.1	Flat	1.224	0.59 sf	25.3 lb	
VHLP2.5	35.0 in	0.0 in	1.0	Generic	0.625	6.68 sf	145.6 lb	
VHLP2	26.1 in	0.0 in	1.0	Generic	0.625	3.72 sf	81.0 lb	
APXV9TM14-ALU-120	56.3 in	6.3 in	8.9	Flat	1.465	2.46 sf	125.8 lb	
TD-RRH8x20	26.1 in	6.7 in	3.9	Flat	1.262	1.21 sf	53.5 lb	



Envelope Only Solution

Ramaker & Associates

JMO


28744

Berlin/RT15/Fire Dept. (CT43XC846-A)

SK - 1

June 19, 2014 at 3:56 PM

28744 Mount.r3d



Envelope Only Solution

Ramaker & Associates

JMO

28744

Berlin/RT15/Fire Dept. (CT43XC846-A)

SK - 2

June 19, 2014 at 3:57 PM

28744 Mount.r3d



Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1E...	Density[k/ft...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	60	1.2
2	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
3	Gr. 33	29000	11154	.3	.65	.49	33	1.5	58	1.2
4	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
5	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
6	A500 Gr.42	29000	11154	.3	.65	.49	42	1.4	58	1.3
7	A500 Gr.46	29000	11154	.3	.65	.49	46	1.4	58	1.3

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design R...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	pipe 2.0	PIPE 2.0	Beam	Pipe	A53 Gr. B	Typical	1.02	.627	.627	1.25
2	pipe 2.5	PIPE 2.5	Beam	Pipe	A53 Gr. B	Typical	1.61	1.45	1.45	2.89
3	pipe 3.0	PIPE 3.0	Beam	Pipe	A53 Gr. B	Typical	2.07	2.85	2.85	5.69
4	grating angle	L2x2x2	Beam	Single Angle	A36 Gr.36	Typical	.491	.189	.189	.003
5	face/standoff	HSS4x4x4	Beam	SquareTube	A36 Gr.36	Typical	3.37	7.8	7.8	12.8

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N1	N2			face/standoff	Beam	SquareTube	A36 Gr.36	Typical
2	BETA	N4	N3			face/standoff	Beam	SquareTube	A36 Gr.36	Typical
3	GAMMA	N5	N3			face/standoff	Beam	SquareTube	A36 Gr.36	Typical
4	ALPHA	N4	N5			face/standoff	Beam	SquareTube	A36 Gr.36	Typical
5	M11	N27	N36			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
6	M13	N23	N32			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
7	M16	N66	N70		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
8	M17	N63	N69		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
9	M19	N56	N67		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
10	M20	N57	N72		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
11	M21	N59	N73		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
12	M22	N62	N75		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
13	M23	N65	N77		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
14	M24	N64	N78		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
15	M25	N61	N76		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
16	M26	N58	N74		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
17	M27	N55	N71		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
18	M26A	N78A	N79B			face/standoff	Beam	SquareTube	A36 Gr.36	Typical
19	M27A	N78B	N79C			face/standoff	Beam	SquareTube	A36 Gr.36	Typical
20	M22A	N51	N75A			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
21	M25A	N65A	N68A			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
22	M27B	N64A	N67A			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
23	M28	N77A	N76B			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
24	M27C	N78C	N81			pipe 3.0	Beam	Pipe	A53 Gr. B	Typical
25	M28A	N79	N82			pipe 3.0	Beam	Pipe	A53 Gr. B	Typical
26	M29	N80	N83			pipe 3.0	Beam	Pipe	A53 Gr. B	Typical
27	M30	N85	N84			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
28	M31A	N87	N86			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
29	M29A	N80A	N82A			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
30	M30A	N79D	N81A			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
31	M31	N90	N91			pipe 2.0	Beam	Pipe	A53 Gr. B	Typical
32	M32	N93	N94		90	grating angle	Beam	Single Angle	A36 Gr.36	Typical
33	M33	N97	N98			pipe 2.5	Beam	Pipe	A53 Gr. B	Typical
34	M34	N103	N102			pipe 2.5	Beam	Pipe	A53 Gr. B	Typical
35	M35	N107	N106			pipe 2.5	Beam	Pipe	A53 Gr. B	Typical



Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
36	M36	N105A	N110			RIGID	None	None	RIGID	Typical
37	M37	N101	N110			RIGID	None	None	RIGID	Typical

Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
1	N1	0	0	1.12	0	
2	N2	0	0	9.660254	0	
3	N3	0	0	8.660254	0	
4	N4	7.5	0	-4.330127	0	
5	N5	-7.5	0	-4.330127	0	
6	N14	6.5	0	-4.330127	0	
7	N18	-6.5	0	-4.330127	0	
8	N23	6.5	5	-4.330127	0	
9	N27	-6.5	5	-4.330127	0	
10	N32	6.5	-3.5	-4.330127	0	
11	N36	-6.5	-3.5	-4.330127	0	
12	APXVSP18-C-A20-TOP-A	-5.25	4.75	-4.330127	0	
13	APXVSP18-C-A20-BOT-A	-5.25	-1	-4.330127	0	
14	APXV9TM14-ALU-120-TOP-A	6.5	4.75	-4.330127	0	
15	APXV9TM14-ALU-120-BOT-A	6.5	.25	-4.330127	0	
16	TD-RRH8X20-A	6.5	-1.5	-4.330127	0	
17	N55	-6	0	-1.732051	0	
18	N56	4.5	0	-4.330127	0	
19	N57	6	0	-1.732051	0	
20	N58	-4.5	0	0.866025	0	
21	N59	4.5	0	0.866025	0	
22	N61	-3	0	3.464102	0	
23	N62	3	0	3.464102	0	
24	N63	-1.5	0	-4.330127	0	
25	N64	-1.5	0	6.062178	0	
26	N65	1.5	0	6.062178	0	
27	N66	-4.5	0	-4.330127	0	
28	N67	4.5	0	-3.330127	0	
29	N69	-1.5	0	-3.330127	0	
30	N70	-4.5	0	-3.330127	0	
31	N71	-5.133987	0	-2.2321	0	
32	N72	5.133987	0	-2.2321	0	
33	N73	3.633958	0	0.365959	0	
34	N74	-3.633958	0	0.365959	0	
35	N75	2.13393	0	2.964019	0	
36	N76	-2.13393	0	2.964019	0	
37	N77	0.633851	0	5.562165	0	
38	N78	-0.633851	0	5.562165	0	
39	N79A	0	0	-0.	0	
40	N78A	0.969948	0	-.56	0	
41	N79B	8.366025	0	-4.830127	0	
42	N78B	-0.969948	0	-.56	0	
43	N79C	-8.366025	0	-4.830127	0	
44	N49	-5.25	0	-4.330127	0	
45	N51	-5.25	5	-4.330127	0	
46	N62A	0.5	0	7.794229	0	
47	N63A	7	0	-3.464102	0	
48	N64A	0.5	5	7.794229	0	
49	N65A	7	5	-3.464102	0	
50	N67A	0.5	-3.5	7.794229	0	



Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
51	N68A	7	-3.5	-3.464102	0	
52	APXVSP18-C-A20-TOP-B	1.125	4.75	6.711697	0	
53	APXVSP18-C-A20-BOT-B	1.125	-1	6.711697	0	
54	APXV9TM14-ALU-120-TOP-B	7	4.75	-3.464102	0	
55	APXV9TM14-ALU-120-BOT-B	7	.25	-3.464102	0	
56	TD-RRH8X20-B	7	-1.5	-3.464102	0	
57	N77A	1.125	5	6.711697	0	
58	N72A	0	0	-4.330127	0	
59	N73A	3.75	0	2.165064	0	
60	N74A	-3.75	0	2.165064	0	
61	N75A	-5.25	-3	-4.330127	0	
62	N76B	1.125	-3	6.711697	0	
63	N78C	0	5.5	-4.330127	0	
64	N79	3.75	6.5	2.165064	0	
65	N80	-3.75	5.5	2.165064	0	
66	N81	0	-5	-4.330127	0	
67	N82	3.75	-6.5	2.165064	0	
68	N83	-3.75	-5	2.165064	0	
69	N84	3.75	4.5	2.165064	0	
70	N85	-3.75	4.5	2.165064	0	
71	N86	0	4	-4.330127	0	
72	N87	-3.75	4	2.165064	0	
73	VHLP2.5 G	-3.75	5	2.165064	0	
74	VHLP2 A1	0	5	-4.330127	0	
75	VHLP2 A2	0	3.5	-4.330127	0	
76	N91A	1.125	0	6.711697	0	
77	N77B	-7.	0	-3.464102	0	
78	N78D	-0.5	0	7.794229	0	
79	N79D	-7.	5	-3.464102	0	
80	N80A	-0.5	5	7.794229	0	
81	N81A	-7.	-3.5	-3.464102	0	
82	N82A	-0.5	-3.5	7.794229	0	
83	APXVSP18-C-A20-TOP-G	-1.125	4.75	6.711697	0	
84	APXVSP18-C-A20-BOT-G	-1.125	-1	6.711697	0	
85	APXV9TM14-ALU-120-TOP-G	-7	4.75	-3.464102	0	
86	APXV9TM14-ALU-120-BOT-G	-7	.25	-3.464102	0	
87	TD-RRH8X20-G	-7	-1.5	-3.464102	0	
88	N89	-1.125	0	6.711697	0	
89	N90	-1.125	5	6.711697	0	
90	N91	-1.125	-3	6.711697	0	
91	VHLP2.5 B	3.75	5.5	2.165064	0	
92	VHLP2 B	3.75	3	2.165064	0	
93	N93	1.5	0	-4.330127	0	
94	N94	1.5	0	-3.330127	0	
95	N96	-2.268987	0	-1.31	0	
96	N98	-2.268987	-4	-1.31	0	
97	N97	-2.268987	3.5	-1.31	0	
98	800MHZ-RRH A	-2.268987	2	-1.31	0	
99	1900MHZ-RRH A	-2.268987	-1.5	-1.31	0	
100	N101	0.25	0	2.62	0	
101	N102	0.25	-4	2.62	0	
102	N103	0.25	3.5	2.62	0	
103	800MHZ-RRH B	.25	2	2.62	0	
104	1900MHZ-RRH B	.25	-1.5	2.62	0	
105	N105A	-0.25	0	2.62	0	
106	N106	-0.25	-4	2.62	0	
107	N107	-0.25	3.5	2.62	0	



Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
108	800MHZ-RRH G	-0.25	2	2.62	0	
109	1900MHZ-RRH G	-0.25	-1.5	2.62	0	
110	N110	0.	0	2.62	0	
111	840-10054 TOP A	0	1.5	-4.330127	0	
112	840-10054 TOP B	3.75	1.5	2.165064	0	
113	840-10054 TOP G	-3.75	1.5	2.165064	0	
114	840-10054 BOT A	0	-2	-4.330127	0	
115	840-10054 BOT B	3.75	-2	2.165064	0	
116	840-10054 BOT G	-3.75	-2	2.165064	0	
117	DAP A	0	-1	-4.330127	0	
118	DAP B	3.75	-1	2.165064	0	
119	DAP G	-3.75	-1	2.165064	0	

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footing
1	N1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction	
2	N78A	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction	
3	N78B	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction	

Joint Loads and Enforced Displacements (BLC 1 : DL)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXVSP18-C-A20-TOP-A	L	Y	-28.5
2	APXVSP18-C-A20-BOT-A	L	Y	-28.5
3	APXV9TM14-ALU-120-TOP-A	L	Y	-27.5
4	APXV9TM14-ALU-120-BOT-A	L	Y	-27.5
5	TD-RRH8X20-A	L	Y	-70
6	APXVSP18-C-A20-TOP-B	L	Y	-28.5
7	APXVSP18-C-A20-BOT-B	L	Y	-28.5
8	APXV9TM14-ALU-120-TOP-B	L	Y	-27.5
9	APXV9TM14-ALU-120-BOT-B	L	Y	-27.5
10	TD-RRH8X20-B	L	Y	-70
11	APXVSP18-C-A20-TOP-G	L	Y	-28.5
12	APXVSP18-C-A20-BOT-G	L	Y	-28.5
13	APXV9TM14-ALU-120-TOP-G	L	Y	-27.5
14	APXV9TM14-ALU-120-BOT-G	L	Y	-27.5
15	TD-RRH8X20-G	L	Y	-70
16	800MHZ-RRH A	L	Y	-64
17	1900MHZ-RRH A	L	Y	-60
18	800MHZ-RRH B	L	Y	-64
19	1900MHZ-RRH B	L	Y	-60
20	800MHZ-RRH G	L	Y	-64
21	1900MHZ-RRH G	L	Y	-60
22	840-10054 TOP A	L	Y	-17
23	840-10054 TOP B	L	Y	-17
24	840-10054 TOP G	L	Y	-17
25	840-10054 BOT A	L	Y	-17
26	840-10054 BOT B	L	Y	-17
27	840-10054 BOT G	L	Y	-17
28	DAP A	L	Y	-33
29	DAP B	L	Y	-33
30	DAP G	L	Y	-33
31	VHLP2.5 G	L	Y	-48
32	VHLP2.5 B	L	Y	-48
33	VHLP2 A1	L	Y	-27



Joint Loads and Enforced Displacements (BLC 1 : DL) (Continued)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
34	VHLP2 A2	L	Y	-27
35	VHLP2 B	L	Y	-27

Joint Loads and Enforced Displacements (BLC 2 : WLz)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXV9TM14-ALU-120-TOP-A	L	Z	-110.6
2	APXV9TM14-ALU-120-BOT-A	L	Z	-110.6
3	APXV9TM14-ALU-120-TOP-B	L	Z	-110.6
4	APXV9TM14-ALU-120-BOT-B	L	Z	-110.6
5	APXV9TM14-ALU-120-TOP-G	L	Z	-110.6
6	APXV9TM14-ALU-120-BOT-G	L	Z	-110.6
7	TD-RRH8X20-A	L	Z	-141.1
8	TD-RRH8X20-B	L	Z	-141.1
9	TD-RRH8X20-G	L	Z	-141.1
10	APXVSPP18-C-A20-TOP-A	L	Z	-140.8
11	APXVSPP18-C-A20-BOT-A	L	Z	-140.8
12	APXVSPP18-C-A20-TOP-B	L	Z	-140.8
13	APXVSPP18-C-A20-BOT-B	L	Z	-140.8
14	APXVSPP18-C-A20-TOP-G	L	Z	-140.8
15	APXVSPP18-C-A20-BOT-G	L	Z	-140.8
16	800MHZ-RRH A	L	Z	-71.8
17	1900MHZ-RRH A	L	Z	-81
18	800MHZ-RRH B	L	Z	-71.8
19	1900MHZ-RRH B	L	Z	-81
20	800MHZ-RRH G	L	Z	-71.8
21	1900MHZ-RRH G	L	Z	-81
22	840-10054 TOP A	L	Z	-79.8
23	840-10054 TOP B	L	Z	-79.8
24	840-10054 TOP G	L	Z	-79.8
25	840-10054 BOT A	L	Z	-79.8
26	840-10054 BOT B	L	Z	-79.8
27	840-10054 BOT G	L	Z	-79.8
28	DAP A	L	Z	-54.6
29	DAP B	L	Z	-54.6
30	DAP G	L	Z	-54.6
31	VHLP2.5 G	L	Z	-294
32	VHLP2.5 B	L	Z	-294
33	VHLP2 A1	L	Z	-163.5
34	VHLP2 A2	L	Z	-163.5
35	VHLP2 B	L	Z	-163.5

Joint Loads and Enforced Displacements (BLC 3 : WLx)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*...]
1	APXV9TM14-ALU-120-TOP-A	L	X	-110.6
2	APXV9TM14-ALU-120-BOT-A	L	X	-110.6
3	APXV9TM14-ALU-120-TOP-B	L	X	-110.6
4	APXV9TM14-ALU-120-BOT-B	L	X	-110.6
5	APXV9TM14-ALU-120-TOP-G	L	X	-110.6
6	APXV9TM14-ALU-120-BOT-G	L	X	-110.6
7	TD-RRH8X20-A	L	X	-141.1
8	TD-RRH8X20-B	L	X	-141.1
9	TD-RRH8X20-G	L	X	-141.1
10	APXVSPP18-C-A20-TOP-A	L	X	-140.8
11	APXVSPP18-C-A20-BOT-A	L	X	-140.8
12	APXVSPP18-C-A20-TOP-B	L	X	-140.8
13	APXVSPP18-C-A20-BOT-B	L	X	-140.8



Joint Loads and Enforced Displacements (BLC 3 : WLx) (Continued)

	Joint Label	L,D,M	Direction	Magnitude(lb,lb-ft), (in,rad), (lb*...
14	APXVSP18-C-A20-TOP-G	L	X	-140.8
15	APXVSP18-C-A20-BOT-G	L	X	-140.8
16	800MHZ-RRH A	L	X	-71.8
17	1900MHZ-RRH A	L	X	-81
18	800MHZ-RRH B	L	X	-71.8
19	1900MHZ-RRH B	L	X	-81
20	800MHZ-RRH G	L	X	-71.8
21	1900MHZ-RRH G	L	X	-81
22	840-10054 TOP A	L	X	-79.8
23	840-10054 TOP B	L	X	-79.8
24	840-10054 TOP G	L	X	-79.8
25	840-10054 BOT A	L	X	-79.8
26	840-10054 BOT B	L	X	-79.8
27	840-10054 BOT G	L	X	-79.8
28	DAP A	L	X	-54.6
29	DAP B	L	X	-54.6
30	DAP G	L	X	-54.6
31	VHLP2.5 G	L	X	-294
32	VHLP2.5 B	L	X	-294
33	VHLP2 A1	L	X	-163.5
34	VHLP2 A2	L	X	-163.5
35	VHLP2 B	L	X	-163.5

Member Distributed Loads (BLC 1 : DL)

	Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
1	M16	Y	-5	-5	0	0
2	M19	Y	-5	-5	0	0
3	M20	Y	-5	-5	0	0
4	M24	Y	-5	-5	0	0
5	M27	Y	-5	-5	0	0
6	M23	Y	-5	-5	0	0

Member Distributed Loads (BLC 2 : WLz)

	Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
1	M11	PZ	-8.3	-8.3	0	0
2	M27B	PZ	-8.3	-8.3	0	0
3	M30	PZ	-8.3	-8.3	0	0
4	M31A	PZ	-8.3	-8.3	0	0
5	M29A	PZ	-8.3	-8.3	0	0
6	M1	PZ	-22.3	-22.3	0	0
7	BETA	PZ	-22.3	-22.3	0	0
8	GAMMA	PZ	-22.3	-22.3	0	0
9	ALPHA	PZ	-22.3	-22.3	0	0
10	M26A	PZ	-22.3	-22.3	0	0
11	M27A	PZ	-22.3	-22.3	0	0
12	M16	PZ	-7.9	-7.9	0	0
13	M17	PZ	-7.9	-7.9	0	0
14	M19	PZ	-7.9	-7.9	0	0
15	M20	PZ	-7.9	-7.9	0	0
16	M21	PZ	-7.9	-7.9	0	0
17	M22	PZ	-7.9	-7.9	0	0
18	M23	PZ	-7.9	-7.9	0	0
19	M24	PZ	-7.9	-7.9	0	0
20	M25	PZ	-7.9	-7.9	0	0
21	M26	PZ	-7.9	-7.9	0	0



Member Distributed Loads (BLC 2 : WLz) (Continued)

Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
22	M27	PZ	-7.9	-7.9	0 0
23	M32	PZ	-7.9	-7.9	0 0

Member Distributed Loads (BLC 3 : WLx)

Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
1	M11	PX	-8.3	-8.3	0 0
2	M27B	PX	-8.3	-8.3	0 0
3	M30	PX	-8.3	-8.3	0 0
4	M31A	PX	-8.3	-8.3	0 0
5	M29A	PX	-8.3	-8.3	0 0
6	M1	PX	-22.3	-22.3	0 0
7	BETA	PX	-22.3	-22.3	0 0
8	GAMMA	PX	-22.3	-22.3	0 0
9	ALPHA	PX	-22.3	-22.3	0 0
10	M26A	PX	-22.3	-22.3	0 0
11	M27A	PX	-22.3	-22.3	0 0
12	M16	PX	-7.9	-7.9	0 0
13	M17	PX	-7.9	-7.9	0 0
14	M19	PX	-7.9	-7.9	0 0
15	M20	PX	-7.9	-7.9	0 0
16	M21	PX	-7.9	-7.9	0 0
17	M22	PX	-7.9	-7.9	0 0
18	M23	PX	-7.9	-7.9	0 0
19	M24	PX	-7.9	-7.9	0 0
20	M25	PX	-7.9	-7.9	0 0
21	M26	PX	-7.9	-7.9	0 0
22	M27	PX	-7.9	-7.9	0 0
23	M32	PX	-7.9	-7.9	0 0

Member Distributed Loads (BLC 4 : LL1)

Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
1	M16	Y	-25	-25	0 0
2	M19	Y	-25	-25	0 0
3	M20	Y	-25	-25	0 0
4	M24	Y	-25	-25	0 0
5	M27	Y	-25	-25	0 0
6	M23	Y	-25	-25	0 0

Member Distributed Loads (BLC 6 : BLC 1 Transient Area Loads)

Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
1	M24	Y	-7.5	-7.5	1.861e-5 1
2	M25	Y	-15	-15	7.048e-6 1
3	M26	Y	-15	-15	0 1
4	M27	Y	-7.5	-7.5	1.147e-5 1
5	M20	Y	-7.5	-7.5	1.164e-5 1
6	M21	Y	-15.001	-15.001	7.99e-5 1
7	M22	Y	-15.001	-15.001	3.574e-5 1
8	M23	Y	-7.5	-7.5	0 1
9	M16	Y	-7.5	-7.5	2.685e-15 1
10	M17	Y	-15	-15	7.425e-16 1
11	M19	Y	-7.5	-7.5	2.311e-15 1
12	M32	Y	-15	-15	1.943e-15 1

Member Distributed Loads (BLC 7 : BLC 4 Transient Area Loads)

Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]
--------------	-----------	--------------------------	------------------------	----------------------	--------------------



Member Distributed Loads (BLC 7 : BLC 4 Transient Area Loads) (Continued)

Member Label	Direction	Start Magnitude[lb/ft,F]	End Magnitude[lb/ft,F]	Start Location[ft,%]	End Location[ft,%]	
1	M24	Y	-37.502	-37.502	1.861e-5	1
2	M25	Y	-75.001	-75.001	7.048e-6	1
3	M26	Y	-75	-75	0	1
4	M27	Y	-37.502	-37.502	1.147e-5	1
5	M20	Y	-37.502	-37.502	1.164e-5	1
6	M21	Y	-75.006	-75.006	7.99e-5	1
7	M22	Y	-75.005	-75.005	3.574e-5	1
8	M23	Y	-37.501	-37.501	0	1
9	M16	Y	-37.5	-37.5	2.685e-15	1
10	M17	Y	-75	-75	7.425e-16	1
11	M19	Y	-37.5	-37.5	2.311e-15	1
12	M32	Y	-75	-75	1.943e-15	1

Member Area Loads (BLC 1 : DL)

Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]	
1	N64	N55	N71	N78	Y	A-B	-5
2	N77	N72	N57	N65	Y	A-B	-5
3	N56	N66	N70	N67	Y	A-B	-5

Member Area Loads (BLC 4 : LL1)

Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]	
1	N64	N55	N71	N78	Y	A-B	-25
2	N77	N72	N57	N65	Y	A-B	-25
3	N56	N66	N70	N67	Y	A-B	-25

Basic Load Cases

BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...)	Surface(P...
1	DL		-1		35		6	3
2	WLz				35		23	
3	WLx				35		23	
4	LL1						6	3
5	LL2					2		
6	BLC 1 Transient Area L...						12	
7	BLC 4 Transient Area L...						12	

Load Combinations

Description	Sol..PDelta	SR..BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..	BLC Fact..
1	1.4DL	Yes	Y	DL	1.4				
2	1.2DL+1.6WLz	Yes	Y	DL	1.2	WLZ	1.6		
3	1.2DL-1.6WLz	Yes	Y	DL	1.2	WLZ	-1.6		
4	1.2DL+1.6WLx	Yes	Y	DL	1.2	W...	1.6		
5	1.2DL-1.6WLx	Yes	Y	DL	1.2	W...	-1.6		
6	1.2DL+1.6(0.75WLz+0.75WLx)	Yes	Y	DL	1.2	WLZ	1.2	W...	1.2
7	1.2DL+1.6(0.75WLz-0.75WLx)	Yes	Y	DL	1.2	WLZ	1.2	W...	-1.2
8	1.2DL-1.6(0.75WLz-0.75WLx)	Yes	Y	DL	1.2	WLZ	-1.2	W...	1.2
9	1.2DL-1.6(0.75WLz+0.75WLx)	Yes	Y	DL	1.2	WLZ	-1.2	W...	-1.2
10	1.2DL+1.5LLend	Yes	Y	DL	1.2	LL	1.5		
11	1.2DL+1.5LLmid	Yes	Y	DL	1.2	5	1.5		
12	1.2DL+1.5LL+10%1.6WLz	Yes	Y	DL	1.2	LL	1.5	WLZ	.16
13	1.2DL+1.5LL-10%1.6WLz	Yes	Y	DL	1.2	LL	1.5	WLZ	-.16
14	1.2DL+1.5LL+10%1.6WLx	Yes	Y	DL	1.2	LL	1.5	W...	.16
15	1.2DL+1.5LL-10%1.6WLx	Yes	Y	DL	1.2	LL	1.5	W...	-.16



Load Combinations (Continued)

	Description	Sol.	PDelta	SR	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.	BLC Fact.
16	1.2DL+1.5LL+10%1.6(0.75WLz+...	Yes	Y		DL 1.2	LL 1.5	WLZ .12	W...	.12				
17	1.2DL+1.5LL+10%1.6(0.75WLz-...	Yes	Y		DL 1.2	LL 1.5	WLZ .12	W...	-.12				
18	1.2DL+1.5LL-10%1.6(0.75WLz-0...	Yes	Y		DL 1.2	LL 1.5	WLZ -.12	W...	.12				
19	1.2DL+1.5LL-10%1.6(0.75WLz+...	Yes	Y		DL 1.2	LL 1.5	WLZ -.12	W...	-.12				
20	1.2DL+1.5LL+10%1.6WLz	Yes	Y		DL 1.2	5 1.5	WLZ .16						
21	1.2DL+1.5LL-10%1.6WLz	Yes	Y		DL 1.2	5 1.5	WLZ -.16						
22	1.2DL+1.5LL+10%1.6WLx	Yes	Y		DL 1.2	5 1.5	W...	.16					
23	1.2DL+1.5LL-10%1.6WLx	Yes	Y		DL 1.2	5 1.5	W...	-.16					
24	1.2DL+1.5LL+10%1.6(0.75WLz+...	Yes	Y		DL 1.2	5 1.5	WLZ .12	W...	.12				
25	1.2DL+1.5LL+10%1.6(0.75WLz-...	Yes	Y		DL 1.2	5 1.5	WLZ .12	W...	-.12				
26	1.2DL+1.5LL-10%1.6(0.75WLz-0...	Yes	Y		DL 1.2	5 1.5	WLZ -.12	W...	.12				
27	1.2DL+1.5LL-10%1.6(0.75WLz+...	Yes	Y		DL 1.2	5 1.5	WLZ -.12	W...	-.12				
28	DL		Y		DL 1								
29	WLz		Y		WLZ 1								
30	WLx		Y		W... 1								

Envelope Joint Reactions

Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC	
1	N1	max	1250.491	4	2437.427	3	5102.195	2	1603.599	2	2617.59	4	1598.371	5
2		min	-1260.68	5	250.628	2	-5095.178	3	-10208.715	3	-2644.919	5	-1493.704	4
3	N78A	max	4057.647	8	2146.267	7	2707.561	7	5290.33	7	1642.041	3	8525.695	7
4		min	-4033.667	7	-4.526	8	-2707.176	8	-862.162	8	-1651.362	2	-845.688	8
5	N78B	max	4286.391	6	2278.738	6	2759.489	6	5244.096	6	1206.837	7	1217.603	9
6		min	-4297.597	9	90.646	9	-2751.21	9	-885.47	9	-1192.37	8	-8557.267	6
7	Totals:	max	8640.365	4	4796.779	12	8751.721	2						
8		min	-8640.365	5	3559.223	3	-8751.721	3						

Envelope AISC 13th(360-05): LRFD Steel Code Checks

Member	Shape	Code Ch...	Loc[ft]	LC	Shear ...	Loc[ft]	Dir	LC	phi*Pnc ...	phi*Pnt [...]	phi*Mn ...	phi*Mn ...	Cb	Eqn	
1	M1	HSS4x4x4	.880	0	8	.194	0	y	5	85986.0...	109188	12663	12663	2...	H1-1b
2	BETA	HSS4x4x4	.455	0	5	.185	0	z	6	52254.7...	109188	12663	12663	2...	H1-1b
3	GAMMA	HSS4x4x4	.420	15	3	.163	15	z	7	52254.7...	109188	12663	12663	2...	H1-1b
4	ALPHA	HSS4x4x4	.493	0	7	.159	0	z	3	52254.7...	109188	12663	12663	2...	H1-1b
5	M11	PIPE 2.0	.094	4.958	6	.007	4.958		6	13511.2...	32130	1871.625	1871.625	1...	H1-1b
6	M13	PIPE 2.0	.499	4.958	7	.039	4.781		7	13511.2...	32130	1871.625	1871.625	1...	H1-1b
7	M16	L2x2x2	.144	0	14	.023	0	z	14	13860.6...	15908.4	402.563	844.628	2...	H2-1
8	M17	L2x2x2	.172	0	14	.027	0	z	10	13860.6...	15908.4	402.563	844.628	2...	H2-1
9	M19	L2x2x2	.144	0	14	.023	0	z	10	13860.6...	15908.4	402.563	844.628	2...	H2-1
10	M20	L2x2x2	.144	0	12	.023	0	z	12	13860.6...	15908.4	402.563	844.628	2...	H2-1
11	M21	L2x2x2	.172	0	12	.027	0	z	18	13860.5...	15908.4	402.563	844.628	2...	H2-1
12	M22	L2x2x2	.172	0	12	.027	0	z	18	13860.5...	15908.4	402.563	844.628	2...	H2-1
13	M23	L2x2x2	.144	0	12	.023	0	z	12	13860.4...	15908.4	402.563	844.628	2...	H2-1
14	M24	L2x2x2	.144	0	13	.023	0	z	19	13860.4...	15908.4	402.563	844.628	2...	H2-1
15	M25	L2x2x2	.172	0	13	.027	0	z	10	13860.5...	15908.4	402.563	844.628	2...	H2-1
16	M26	L2x2x2	.172	0	13	.027	0	z	19	13860.5...	15908.4	402.563	844.628	2...	H2-1
17	M27	L2x2x2	.144	0	13	.023	0	z	10	13860.6...	15908.4	402.563	844.628	2...	H2-1
18	M26A	HSS4x4x4	.902	0	7	.153	0	y	9	85986.0...	109188	12663	12663	2...	H1-1b
19	M27A	HSS4x4x4	.856	0	6	.185	0	y	8	85986.0...	109188	12663	12663	2...	H1-1b
20	M22A	PIPE 2.0	.612	5	7	.025	.25		7	14916.0...	32130	1871.625	1871.625	1...	H1-1b
21	M25A	PIPE 2.0	.499	4.958	9	.039	4.781		9	13511.2...	32130	1871.625	1871.625	1...	H1-1b
22	M27B	PIPE 2.0	.094	4.958	9	.007	4.958		9	13511.2...	32130	1871.625	1871.625	1...	H1-1b
23	M28	PIPE 2.0	.612	5	9	.025	.25		9	14916.0...	32130	1871.625	1871.625	1...	H1-1b
24	M27C	PIPE 3.0	.584	5.469	4	.106	4.047		5	36138.4	65205	5748.75	5748.75	1...	H1-1b
25	M28A	PIPE 3.0	.694	6.5	3	.089	5.01		7	26386.7...	65205	5748.75	5748.75	1...	H1-1b



Company : Ramaker & Associates
 Designer : JMO
 Job Number : 28744
 Model Name : Berlin/RT15/Fire Dept. (CT43XC846-A)

June 19, 2014

Checked By: _____

Envelope AISC 13th(360-05): LRFD Steel Code Checks (Continued)

Member	Shape	Code Ch...	Loc[ft]	LC	Shear ...	Loc[ft]	Dir	LC	phi*Pnc ...	phi*Pnt [...	phi*Mn ...	phi*Mn ...	Cb	Eqn	
26	M29	PIPE 3.0	.728	5.469	9	.105	1.094		9	36138.4	65205	5748.75	5748.75	1...	H1-1b
27	M30	PIPE 2.0	.465	7.5	5	.060	0		8	16368.5...	32130	1871.625	1871.625	2...	H1-1b
28	M31A	PIPE 2.0	.462	7.5	7	.049	0		3	16368.5...	32130	1871.625	1871.625	2...	H1-1b
29	M29A	PIPE 2.0	.094	4.958	8	.007	4.958		8	13511.2...	32130	1871.625	1871.625	1...	H1-1b
30	M30A	PIPE 2.0	.499	4.958	8	.039	4.781		8	13511.2...	32130	1871.625	1871.625	1...	H1-1b
31	M31	PIPE 2.0	.612	5	8	.025	.25		8	14916.0...	32130	1871.625	1871.625	1...	H1-1b
32	M32	L2x2x2	.172	0	14	.027	0	z	17	13860.6...	15908.4	402.563	844.628	2...	H2-1
33	M33	PIPE 2.5	.068	3.438	6	.009	3.516		6	32005.2...	50715	3596.25	3596.25	2...	H1-1b
34	M34	PIPE 2.5	.068	3.438	9	.009	3.516		9	32005.2...	50715	3596.25	3596.25	2...	H1-1b
35	M35	PIPE 2.5	.068	3.438	9	.009	3.516		9	32005.2...	50715	3596.25	3596.25	2...	H1-1b



PROJECT: 2.5 EQUIPMENT DEPLOYMENT

SITE NAME: BERLIN/RT 15/FIRE DEPT

SITE CASCADE: CT43XC846-A

SITE ADDRESS: 1 657 WILBUR CROSS
BERLIN, CT 06037

SITE TYPE: 175'-0" MONOPOLE

Sprint

6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251


RAMAKER & ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

Transcend Wireless

48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS
ISSUE PHASE	FINAL	DATE ISSUED 06/10/2014

PROJECT TITLE:
**BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A**

PROJECT INFORMATION:
 1 657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
TITLE SHEET

SCALE: NONE

PROJECT NUMBER	28744
SHEET NUMBER	T-1

SITE INFORMATION

PROPERTY OWNER:
 BERLIN VOLUNTEER FIRE DEPT
 1 657 BERLIN TURNPIKE
 BERLIN, CT 06037
 PH.:(860)828-7000

SITE ADDRESS:
 1 657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

GEOGRAPHIC COORDINATES:
 LATITUDE: 41.606217°, 41° 36' 22.3812" N
 LONGITUDE: -72.749686°, 72° 44' 58.869" W

ZONING JURISDICTION:
 CONNECTICUT SITING COUNCIL

ZONING DISTRICT:
 BT-1 BERLIN TURNPIKE

POWER COMPANY:
 CONN. LIGHT AND POWER
 PH.: (800) 286-2000


AAV PROVIDER:
 AT&T
 PH.: (210) 821-4105

SPRINT CONSTRUCTION MANAGER:
 NAME: MIKE DELIA
 PHONE: (781) 316-6348
 E-MAIL: michael.delia@sprint.com

EQUIPMENT SUPPLIER:
 ALCATEL-LUCENT
 600-700 MOUNTAIN AVENUE
 MURRAY HILL, NJ 07974
 PH.: (908) 508-8080

PLANS PREPARED BY:
 RAMAKER & ASSOCIATES, INC.
 CONTACT: KEITH BOHNSACK, PROJECT MANAGER
 PH.: (608) 643-4100
 EMAIL: kbohnsack@ramaker.com

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

- INSTALL NEW 2.5 EQUIPMENT IN EXISTING BTS CABINET
 *(1) RECTIFIER SHELF AND (3) RECTIFIERS
 *(1) BASE BAND UNIT
- INSTALL NEW BATTERY STRING IN EXISTING BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRHS ON TOWER
- INSTALL (1) FIBER CABLE AND (2) FIBER JUMPERS
- INSTALL (27) ANTENNA / RRH JUMPERS

APPLICABLE CODES

- * ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.
1. INTERNATIONAL BUILDING CODE
 2. ANSI/TIA-222 STRUCTURAL STANDARD FOR ANTENNA STRUCTURES
 3. NFPA 780 - LIGHTNING PROTECTION CODE
 4. NATIONAL ELECTRIC CODE



SECTION 01 100 - SCOPE OF WORK

THE WORK:
THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

RELATED DOCUMENTS:
A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY AND COLLECTIVELY.
B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING.
1. EN-201 2-001 : (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS)
2. TS-0200 - (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)
3. EL-0568: (FIBER TESTING POLICY)
4. NP-312-201 : (EXTERIOR GROUNDING SYSTEM TESTING)
5. NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

PRECEDENCE:
SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

NATIONALLY RECOGNIZED CODES AND STANDARDS:
THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
C. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
G. AMERICAN CONCRETE INSTITUTE (ACI)
H. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
I. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
J. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
K. PORTLAND CEMENT ASSOCIATION (PCA)
L. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
M. BRICK INDUSTRY ASSOCIATION (BIA)
N. AMERICAN WELDING SOCIETY (AWS)
O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
P. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
Q. DOOR AND HARDWARE INSTITUTE (DHI)
R. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
S. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

DEFINITIONS:
A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND ITS OPERATING ENTITIES.
C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR, INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
F. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT.

SITE FAMILIARITY:
CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

POINT OF CONTACT:
COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

ON-SITE SUPERVISION:
THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

DRAWINGS REQUIRED AT JOBSITE:
THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
A. THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

USE OF JOB SITE:
THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

UTILITY SERVICES:
WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED.

PERMITS/FEE:
WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

CONTRACTOR:
CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:
CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

TEMPORARY UTILITIES AND FACILITIES:
THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

ACCESS TO WORK:
THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

DIMENSIONS:
VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

EXISTING CONDITIONS:
NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

FURNISHED MATERIALS:
COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

RECEIPT OF MATERIAL AND EQUIPMENT:
A. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
B. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
C. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
D. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

DELIVERABLES:
A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

SECTION 01 300 - CELL SITE CONSTRUCTION

NOTICE TO PROCEED:
A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S ISSUANCE OF THE WORK ORDER.
B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

GENERAL REQUIREMENTS FOR CONSTRUCTION:
A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

FUNCTIONAL REQUIREMENTS:
A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND BACKHAUL (FIBER, COPPER, OR MICROWAVE).
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- 18. CONDUCT ALL REQUIRED TESTS AND INSPECTIONS
- 19. PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
- 20. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING, INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS.

DELIVERABLES:
A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
1. PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUESTED BY SPRINT
2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLOAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL SITE PHOTOS
3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.
4. ALL REQUIRED TEST REPORTS.
5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:
a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION
b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD
c. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS
d. LIEN WAIVERS
e. FINAL PAYMENT APPLICATION
f. REQUIRED FINAL CONSTRUCTION PHOTOS
g. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
h. LISTS OF SUBCONTRACTORS
B. PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. PRE-CONSTRUCTION MEETING NOTES.

SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT CLOSEOUT

TESTS AND INSPECTIONS:
A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
1. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS
2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
3. CONCRETE BREAK TESTS
4. SITE RESISTANCE TO EARTH TEST
5. STRUCTURAL BACKFILL COMPACTION TESTS
6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION.

SUBMITTALS:
A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
B. UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
3. CHEMICAL GROUNDING SYSTEM .
4. REINFORCEMENT CERTIFICATIONS
5. STRUCTURAL BACKFILL TEST RESULTS
6. SWEEP AND FIBER TESTS
7. ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION
8. POST CONSTRUCTION HEIGHT VERIFICATION
9. ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS
C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

TESTING BY THIRD PARTY AGENCY:
A. EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED. AGENCY IS SUBJECT TO APPROVAL BY COMPANY.
1. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
B. REQUIRED THIRD PARTY TESTS:
1. SITE RESISTANCE TO EARTH TEST PER NP-312-201
2. CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED STANDARDS
3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS
4. REBAR PLACEMENT VERIFICATION WITH REPORT
5. TESTING TENSION STUDY FOR ROCK ANCHORS
6. ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION
C. REQUIRED TESTS BY CONTRACTOR
1. COAX SWEEP TESTS PER SPRINT STANDARD TS-0200
2. FIBER TESTS PER SPRINT STANDARD EL-0568
3. MICROWAVE LINK TESTS PER NP-760-500
4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN.



**6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251**



**1120 Dallas Street, Sauk City, WI 53585
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com**



**48 SPRUCE STREET
OAKLAND, NJ 07346**

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski 8/07/2014
Signature: Date:

B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 06/10/2014

PROJECT TITLE:
**BERLIN/RT 15/FIRE DEPT
SITE#:CT43XC846-A**

PROJECT INFORMATION:
**1 657 WILBUR CROSS
BERLIN, CT 06037
HARTFORD COUNTY**

SHEET TITLE:
SPRINT SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	28744
SHEET NUMBER	SP-1

5. POST CONSTRUCTION HEIGHT VERIFICATION AS REQUIRED HERewith IN THE TOWER INSTALLATION SPECIFICATIONS.
 6. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED HERewith IN THE ASPHALT PAVING SPECIFICATIONS.
 7. FIELD QUALITY CONTROL TESTING AS SPECIFIED HERewith IN THE CONCRETE PAVING SPECIFICATIONS.
 8. TESTING REQUIRED HERewith UNDER SPECIFICATIONS FOR AGGREGATE BASE FOR ROADWAYS
 9. ALL OTHER TESTS REQUIRED BY LOCAL JURISDICTION
- D. INSPECTIONS BY COMPANY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN INSPECTION ACTIVITIES, FINAL ACCEPTANCE / PUNCH WALK REVIEW, AND/OR AS A RESULT OF TESTING
- E. SPRINT RESERVES THE RIGHT TO INSPECT THE CONSTRUCTION SITE AT ANY TIME VIA SITE WALKS AND/OR PHOTO REVIEWS. CONTRACTOR SHALL GIVE SPRINT 24 HOURS NOTICE PRIOR TO THE COMMENCEMENT OF THE FOLLOWING CONSTRUCTION ACTIVITIES AND PHOTOGRAPHS OF THE IN-PROGRESS WORK.
1. GROUNDING SYSTEM AND BURIED UTILITIES INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS, AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS, ASPHALT PAVING, AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE AND POST CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES. PRIOR TO CONSTRUCTION ACTIVITIES AND AFTER CONSTRUCTION IS COMPLETE, PROVIDE PHOTOGRAPHIC DOCUMENTATION OF ROOF, FLASHINGS, AND PARAPETS, BOTH BEFORE AND AFTER CONSTRUCTION IS COMPLETE.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. TOWER TOP AND INACCESSIBLE EQUIPMENT (RRUS, ANTENNAS, AND CABLING): PROVIDE PHOTOS OF THE BACKS OF ALL ANTENNAS, RRUS, COMBINERS, FILTERS, FIBER AND DC CABLING, CABLE COLOR CODING, EQUIPMENT GROUNDING AND CONNECTOR WATER PROOFING INCLUDING NAME PLATE AND SERIAL NUMBER FOR ALL SERIALIZED EQUIPMENT.

PROJECT CLOSEOUT:

- A. FINAL ACCEPTANCE PUNCH WALK AND INSPECTION: AS IDENTIFIED IN THE SCOPE OF SERVICES, SPRINT WILL CONDUCT A FINAL PUNCH WALK OR FINAL DESK TOP PHOTO REVIEW (SITE MODIFICATIONS). PUNCH WALKS MUST BE SCHEDULED IN ADVANCE AS REQUIRED. AT THE PUNCH WALK / REVIEW, SPRINT MAY IDENTIFY CRITICAL DEFICIENCIES WHICH MUST BE CORRECTED PRIOR TO PUTTING SITE ON AIR. MINOR DEFICIENCIES MUST BE CORRECTED WITHIN 30 DAYS EXCEPT AS OTHERWISE REQUIRED. VERIFICATIONS OF CORRECTIONS MAY BE MADE BY COMPANY DURING A REPEAT SITE WALK OR DESK TOP PHOTO REVIEW AT COMPANY'S SOLE DISCRETION.
- B. CLOSEOUT DOCUMENTATION: ALL CLOSEOUT DOCUMENTATION AND PHOTOGRAPHS SHALL BE UPLOADED PRIOR TO FINAL ACCEPTANCE. SPRINT WILL REVIEW CLOSEOUT DOCUMENTATION FOR PRESENCE AND CONTENT. CLOSEOUT DOCUMENTATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING AS APPLICABLE:
1. COAX SWEEP TESTS:
 2. FIBER TESTS:
 3. JURISDICTION FINAL INSPECTION DOCUMENTATION
 4. REINFORCEMENT CERTIFICATION (MILL CERTIFICATION)
 5. CONCRETE MIX DESIGN AND PRODUCT DATA (TOWER FOUNDATION)
 6. LIEN WAIVERS AND RELEASES.
 7. POST -CONSTRUCTION HEIGHT VERIFICATION
 8. JURISDICTION CERTIFICATE OF OCCUPANCY
 9. ELECTRONIC ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 10. STRUCTURAL BACKFILL TEST RESULTS (IF APPLICABLE)
 11. CELL SITE UTILITY SETUP
 12. AS-BUILT REDLINE CONSTRUCTION DRAWINGS (PDF SCAN OF FIELD MARKS)
 13. AS-BUILT CONSTRUCTION DRAWINGS IN DWG AND PDF FORMATS
 14. LIST OF SUB CONTRACTORS
 15. APPROVED PERMITTING DOCUMENTS
16. FINAL SITE PHOTOS UP-LOADED TO SITERRA. INCLUDE THE FOLLOWING AS APPLICABLE:
- a. TOWER, ANTENNAS, RRUS, AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX/CABLE LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - b. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 - c. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 - d. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.

PROJECT PHOTOGRAPHS:

- A. PROVIDE PROJECT CLOSEOUT GENERAL ARRANGEMENT PHOTOS OF ALL NEW WORK. THE FOLLOWING LIST REPRESENTS MINIMUM REQUIREMENTS AND MINIMUM QUANTITY. ADDITIONAL PHOTOS MAY BE REQUIRED TO ADEQUATELY DOCUMENT THE WORK.
1. ASR AND RF MPE SIGNAGE (IF NOT IN PLACE, SUPPLIER NOTIFIES EMS FIELD REPRESENTATIVE)
 2. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR)
 3. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR) CLOSE UP SHOWING WEATHERPROOFING AND GROUNDING (AS REQUIRED). CLOSE-UP OF BACK SIDE OF EACH PERMANENT RRU SHOWING SERIAL NUMBER/BAR CODE
 4. VIEW (1 EACH SECTOR) ALONG THE AZIMUTH AND TILT OF THE ANTENNAS
 5. TOP OF TOWER FROM GROUND, 1 EACH SECTOR
 6. MAINLINE HYBRID CABLE ROUTE DOWN TOWER SHOWING FASTENERS AND SUPPORT
 7. MAINLINE/HYBRID CABLE ROUTE ALONG ICE BRIDGE OR IN CABLE TRAY SHOWING FASTENERS AND SUPPORT
 8. GROUND MOUNTED RRU RACKS (FRONT AND BACK)
 9. FRONT, SIDE AND BACK ELEVATIONS OF ALL GROUND CABINETS
 10. VIEW OF COMPOUND FROM A DISTANCE
 11. VIEW OF EACH GROUND CABINET (POWER, RF, FIBER SPOOL, PPC POWER, PPC TELCO WITH DOOR OPEN)
 12. BACKHAUL FIBER MEET-ME-POINT AND CONDUIT ROUTE (MICROWAVE INSTALLATION IF NOT FIBER)
 13. AAV NETWORK INTERFACE DEVICE OR MICROWAVE RADIO INSTALLATION

DEFICIENCY CORRECTIONS:

CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIONS TO DEFICIENCIES IDENTIFIED THROUGH TESTING, REVIEW OF SUBMITTALS, INSPECTIONS AND CLOSEOUT REVIEWS.

SECTION 01 500 - PROJECT REPORTING

WEEKLY REPORTS:

- A. CONTRACTOR SHALL REPORT TO SPRINT AT MINIMUM ON A WEEKLY BASIS VIA SITERRA BY UPDATING ALL APPLICABLE POST END KEEPING MILESTONES WITH ACTUAL AND FORECASTED COMPLETION DATES.
- B. ADDITIONAL REQUIREMENTS FOR REPORTING MAY BE IDENTIFIED ELSEWHERE OR REQUIRED BY THE SCOPE OF SERVICES OR SPRINTS LOCAL MARKET CONSTRUCTION MANAGER. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

PROJECT CONFERENCE CALLS:

SPRINT MAY HOLD PERIODIC PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

FINAL PROJECT ACCEPTANCE: PRIOR TO SPRINTS FINAL PROJECT ACCEPTANCE. ALL REQUIRED MILESTONE ACTUALS MUST BE UPDATED IN SITERRA AND ALL REQUIRED REPORTING TASKS MUST BE COMPLETE.

SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO UNITS AND CABLE INSTALLATION

SUMMARY:

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRUS, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

ANTENNAS AND RRUS:

THE NUMBER AND TYPE OF ANTENNAS AND RRUS TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE:

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

JUMPERS AND CONNECTORS:

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRUS AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRUS AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE, MIN. LENGTH FOR JUMPER SHALL BE 10'-0".

REMOTE ELECTRICAL TILT (RET) CABLES:

MISCELLANEOUS:

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

ANTENNA INSTALLATION:

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.

B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

HYBRID CABLE INSTALLATION:

A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADIUS.

C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.

1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE INSTALLED INSIDE MONOPOLE WITH CABLE SUPPORT GRIPS AS REQUIRED BY THE MANUFACTURER.
2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
 - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH AT 18" O.C. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
 - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
4. CABLE INSTALLATION:
 - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
 - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSEOVERS.
 - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.
5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 (CURRENT VERSION).
7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.

B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.

1. COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CX5 SERIES OR EQUAL.
2. SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBS) AND RELATED EQUIPMENT

SUMMARY:

A. THIS SECTION SPECIFIES MMBS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).

B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRED BY THE APPLICABLE INSTALLATION MOPS.

C. COMPLY WITH MANUFACTURER'S INSTALLATION AND START-UP REQUIREMENTS.

DC CIRCUIT BREAKER LABELING

A. NEW DC CIRCUIT IS REQUIRED IN MMBS CABINET SHALL BE CLEARLY IDENTIFIED AS TO RRU BEING SERVICED.

SECTION 26 100 - BASIC ELECTRICAL REQUIREMENTS

SUMMARY:

THIS SECTION SPECIFIES BASIC ELECTRICAL REQUIREMENTS FOR SYSTEMS AND COMPONENTS

QUALITY ASSURANCE:

A. ALL EQUIPMENT FURNISHED UNDER DIVISION 26 SHALL CARRY UL LABELS AND LISTINGS WHERE SUCH LABELS AND LISTINGS ARE AVAILABLE IN THE INDUSTRY.

B. MANUFACTURERS OF EQUIPMENT SHALL HAVE A MINIMUM OF THREE YEARS EXPERIENCE WITH THEIR EQUIPMENT INSTALLED AND OPERATING IN THE FIELD IN A USE SIMILAR TO THE PROPOSED USE FOR THIS PROJECT.

C. MATERIALS AND EQUIPMENT: ALL MATERIALS AND EQUIPMENT SPECIFIED IN DIVISION 26 OF THE SAME TYPE SHALL BE OF THE SAME MANUFACTURER AND SHALL BE NEW, OF THE BEST QUALITY AND DESIGN, AND FREE FROM DEFECTS.

SUPPORTING DEVICES:

A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:

1. ALLIED TUBE AND CONDUIT.
2. B-LINE SYSTEM.
3. UNISTRUT DIVERSIFIED PRODUCTS.
4. THOMAS & BETTS.

B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:

1. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.



6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com



48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
ISSUE PHASE	FINAL	DATE ISSUED 06/10/2014

PROJECT TITLE:
**BERLIN/RT 15/FIRE DEPT
SITE#:CT43XC846-A**

PROJECT INFORMATION:
1657 WILBUR CROSS
BERLIN, CT 06037
HARTFORD COUNTY

SHEET TITLE:
SPRINT SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	28744
SHEET NUMBER	SP-2

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
 - 1. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
 - 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6-FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
 - 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY ROXTEC.
 - 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS. CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM:

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS
MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL	DATE ISSUED 06/10/2014


PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
 SPRINT SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	28744
SHEET NUMBER	SP-3



Sprint
 6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251

RAMAKER & ASSOCIATES, INC.
 1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

Transcend Wireless
 48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014


PROJECT TITLE:
**BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A**

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
SITE PLAN

11" x 17" - 1" = 5'
 22" x 34" - 1" = 2.5'

PROJECT NUMBER: **28744**
 SHEET NUMBER: **A-1**



CONTRACTOR TO INSTALL CONNECTION KIT FROM EXISTING 9927 MM-BTS TO EXISTING FIBER DISTRIBUTION BOX

(1) PROPOSED 5/8" FIBER CABLE TO BE INSTALLED ALONG EXISTING SPRINT CABLES FROM FIBER DISTRIBUTION BOX TO ALPHA SECTOR ANTENNA. CONTRACTOR TO USE SNAP-IN HANGERS AS NEEDED, SPACED MAX. 4'-0" O.C.

EXISTING SPRINT CABLE TRAY

FIBER DISTRIBUTION

TELCO

AC (200A)

EXISTING SPRINT PPC POWER & TELCO ENCLOSURE

EXISTING SPRINT GPS ANTENNA

EXISTING SPRINT EQUIPMENT PLATFORM

EXISTING 9927 MM-BTS CABINET

EXISTING BATTERY CABINET

EXISTING CLEARWIRE CABINET

INSTALL NEW 2.5 EQUIPMENT IN EXISTING MM-BTS

EXISTING LADDER

EQUIPMENT PLAN
 SCALE: 1" = 2.5'



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS





ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014
 PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
 EQUIPMENT PLAN



PROJECT NUMBER: 28744
 SHEET NUMBER: A-2



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS
ISSUE PHASE	FINAL	DATE ISSUED 06/10/2014

PROJECT TITLE:
**BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A**

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
**BUILDING ELEVATIONS &
 ANTENNA DETAILS**

SCALE:
 AS NOTED

PROJECT NUMBER: 28744
 SHEET NUMBER: A-3



RFDS Sheet

General Site Information

Site ID	CT43XC846
Market	Northern Connecticut
Region	Northeast
MLA	N/A
Structure Type	MONOPOLE
BTS Type	

Equipment Vendor	Alcatel-Lucent
Latitude	41.606217
Longitude	-72.749686
LL SITE ID	N/A

Solution ID	
-------------	--

Siterra SR Equipment type	
Equipment Vendor	Alcatel-Lucent

Incremental Power Draw needed by added Equipment	N/A
--	-----

Base Equipment

BBU Kit	ALU BBU Kit
BBU Kit Qty	1
Growth Cabinet	None
Growth Cabinet Qty	N/A
Growth Cabinet Dimensions	N/A
Growth Cabinet Weight	N/A

Top Hat	None
Top Hat Qty	N/A
Top Hat Dimensions	N/A
Top Hat Weight (lbs)	N/A

RF Path Information

RRH	TD-RRH8x20-25
RRH Qty	3
RRH Dimensions	26.1"x18.6"x6.7"
RRH Weight. lbs.	70
RRH Mount Weight. Lbs.	10
Power and Fiber Cable	ALU Fiber only
Cable Qty	1
Weight per foot. Lbs.	0.242
Diameter. Inches.	0.625
Length Ft.	180 (calculated as antenna height plus 20%)
Coax Jumper	TBD
Coax Jumper Qty	27
Coax Jumper Length. Feet.	8
Coax Jumper Weight	1.7
Coax Jumper Diameter. Inches	0.5
AISG Cable	COMMSCOPE ATCB-B01-006
AISG Cable Qty	3
AISG Diameter. Inches.	0.315
AISG Cable length.	8'
Weight of entire AISG cable. Lbs.	1.3

Antenna Sector Information

	Sector 1	Sector 2	Sector 3
Antenna make/model	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20
Antenna qty	1	1	1
Antenna Dimensions. Inches	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"
Antenna Weight. Lbs	55.12	55.12	55.12
Antenna Mounting Kit Weight. Lbs.	11.5	11.5	11.5
CL Height	150	150	150
Antenna Azimuth	330	90	210
Antenna Mechanical Downtilt	0	0	0
Antenna etilt	-2	-2	-2

*RFDS SHEET WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (POR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.



6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com



48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

NOTES:

- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS 1.9GHZ ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT 1.9GHZ AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT IS LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND 1.9GHZ AND 800MHZ ANTENNA.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014

PROJECT TITLE:

BERLIN/RT 15/FIRE DEPT
SITE#:CT43XC846-A


PROJECT INFORMATION:
1657 WILBUR CROSS
BERLIN, CT 06037
HARTFORD COUNTY

SHEET TITLE:


RF DATA SHEET

SCALE:
AS NOTED


PROJECT NUMBER: 28744
SHEET NUMBER: A-4




TYPICAL FIBER DISTRIBUTION BOX DETAIL
 SCALE: NTS




RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL
 SCALE: NTS



8T8R DETAIL
 SCALE: NTS



BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL
 SCALE: NTS



RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS
ISSUE PHASE	FINAL	DATE ISSUED 06/10/2014

PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
 FIBER PLUMBING DIAGRAM





SCALE:
 AS NOTED

PROJECT NUMBER: 28744
 SHEET NUMBER: A-5

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Blue	No Tape	No Tape
1	3	Brown	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Blue	Blue	No Tape
2	3	Brown	Brown	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Blue	Blue	Blue
3	3	Brown	Brown	Brown
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange



COLOR CODING CHARTS
 SCALE: NTS

CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014

PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
 CABLE COLOR CODING

SCALE:
 AS NOTED

PROJECT NUMBER: 28744
 SHEET NUMBER: A-6

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE
 MANUF:RFS

CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
*Fiber Only	Varies	Use NV Hybridflex	5/8"
Hybridflex	<200'	8 AWG	1-1/4"
Hybridflex	225-300'	6 AWG	1-1/4"
Hybridflex	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE

FIBER ONLY (EXISTING DC POWER)	Hybrid cable	
MN:HB058-M12-050F	12x multi-mode fiber pairs, Top:Outdoor protected connectors, Bottom:LC Connectors, 5/8 cable, 50 ft	50 ft
MN:HB058-M12-075F		75 ft
MN:HB058-M12-100F		100 ft
MN:HB058-M12-125F		125 ft
MN:HB058-M12-150F		150 ft
MN:HB058-M12-175F		175 ft
MN:HB058-M12-200F		200 ft
8 AWG Power	Hybrid cable	
MN:HB114-08U3M12-050F	3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 50 ft	50 ft
MN:HB114-08U3M12-075F		75 ft
MN:HB114-08U3M12-100F		100 ft
MN:HB114-08U3M12-125F		125 ft
MN:HB114-08U3M12-150F		150 ft
MN:HB114-08U3M12-175F		175 ft
MN:HB114-08U3M12-200F		200 ft
6 AWG Power	Hybrid cable	
MN:HB114-13U3M12-225F	3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 225 ft	225 ft
MN:HB114-13U3M12-250F		250 ft
MN:HB114-13U3M12-275F		275 ft
MN:HB114-13U3M12-300F		300 ft
4 AWG Power	Hybrid cable	
MN:HB114-21U3M12-325F	3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 325 ft	325 ft
MN:HB114-21U3M12-350F		350 ft
MN:HB114-21U3M12-375F		375 ft





RFS HYBRIFLEX JUMPER CABLE SCHEDULE

FIBER ONLY	Hybrid Jumper cable	
MN:HBF012-M3-5F1	5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
MN:HBF012-M3-10F1		10 ft
MN:HBF012-M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
8 AWG POWER	Hybrid Jumper cable	
MN:HBF058-08U1M3-5F1	5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft
MN:HBF058-08U1M3-10F1		10 ft
MN:HBF058-08U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
6 AWG POWER	Hybrid Jumper cable	
MN:HBF058-13U1M3-5F1	5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN:HBF058-13U1M3-10F1		10 ft
MN:HBF058-13U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		
4 AWG POWER	Hybrid Jumper cable	
MN:HBF078-21U1M3-5F1	5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN:HBF078-21U1M3-10F1		10 ft
MN:HBF078-21U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15' NOTIFY SPRINT CM OF ANY DISCREPANCY		

*NOTE: SPRINT CM TO CONFIRM HYBRID/FIBER RISER CABLE # HYBRID/FIBER JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.

FIBER CABLE CROSS SECTION & DATA


SCALE: NTS



RFS: APXV9TM14-ALU-120

DIMENSIONS, HxWxD: 56.3" x 12.6" x 6.3"
 WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs.
 CONNECTOR: (9) XX* MINI-DIN FEMALE/BOTTOM

2.5 ANTENNA DETAIL
 SCALE: NTS



ALCATEL-LUCENT: TD-RRH8x20-25

HxWxD = (26.1" x 18.6" x 6.7")

WEIGHT = 70 lbs.

2.5 RRH DETAIL
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: James R. Skowronski Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014


PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
 ANTENNA & HYBRID CABLE
 DETAILS

SCALE:
 AS NOTED


PROJECT NUMBER	28744
SHEET NUMBER	A-7



NOTES:

1. LINE UP WHITE MARKINGS ON JUMPER AND RISER IP-MPO CONNECTORS AND SLIDE THE RISER CONNECTOR TO THE JUMPER CONNECTOR. PUSH THE WHITE MARK ON THE JUMPER CONNECTOR FLUSH AGAINST THE RED SEAL ON THE RISER CONNECTOR.
2. ROTATE THE BAYONET HOUSING CLOCKWISE UNTIL YOU HEAR A CLICK SOUND.


HYBRID BREAKOUT DETAIL
 SCALE: NTS



CABLE ROUTE FROM CABINET
 SCALE: NTS



EXISTING BBU CABINET
 SCALE: NTS



EXISTING MMBS CABINET
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski
 Signature: _____ Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWINGS REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014


PROJECT TITLE:
**BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A**

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY


SHEET TITLE:
EQUIPMENT DETAILS

SCALE:
 AS NOTED


PROJECT NUMBER: 28744
 SHEET NUMBER: A-8



BASE PLATE MODIFICATIONS
 SCALE: NTS



STIFFENER PLATE SIDE ELEVATION VIEW
 SCALE: NTS



STIFFENER PLATE FRONT ELEVATION VIEW
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014
 PROJECT TITLE:



BERLIN/RT 15/FIRE DEPT
SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
EQUIPMENT DETAILS

SCALE:
 AS NOTED

PROJECT NUMBER: 28744
 SHEET NUMBER: 5-1



- GROUNDING NOTES:**
- CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
 - ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.
 - ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (GADWELD).
 - ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.
 - CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
 - MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
 - WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BEAR METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTED TO ORIGINAL FINISH.
 - GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

LEGEND:	
-----	EXISTING GROUND CABLE
-----	PROPOSED GROUND CABLE
▲	MECHANICAL CONNECTION
■	EXOTHERMIC CONNECTION
—E—E—E—E—E—	PROPOSED ELECTRIC

EQUIPMENT UTILITY & GROUNDING PLAN ①
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014


PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY


SHEET TITLE:
 EQUIPMENT UTILITY &
 GROUNDING PLAN

SCALE:
 AS NOTED

PROJECT NUMBER	28744
SHEET NUMBER	E-1




GROUNDING RISER DIAGRAM
 SCALE: NTS



NOTES:

1. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

GROUNDING CONDUCTOR INSTALLATION
 SCALE: NTS



TWO-HOLE LUG
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS
ISSUE PHASE	FINAL	DATE ISSUED 06/10/2014

PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A


PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
 GROUNDING DETAILS

SCALE:
 AS NOTED

PROJECT NUMBER	28744
SHEET NUMBER	E-2

Copyright 2014 - Ramaker & Associates, Inc. - All Rights Reserved
 DRAWN BY: TJN
 CHECKED BY: KAB
 Printed by: kgalston on Aug 07, 2014 - 3:09pm
 I:\28700\28744\CAD\28744 Sprint 2.5 CD for CT.dwg





A/C PANEL SCHEDULE

VOLTAGE:	240V/120	PANEL STATUS:	EXISTING	N TO GROUND BOND:	YES
MAIN BREAKER:	200 AMP	MODEL NUMBER:	TBD	INTERNAL TVSS:	YES
MOUNT:	ROOFTOP	PHASE:	1	WIRE:	3
ENCLOSURE TYPE:	NEMA 3R	BUSS RATING:	200 AMP	GROUND BAR:	YES
		NEUTRAL BAR:	YES		

CKT	DESCRIPTION	BREAKER AMPS	BREAKER POLES	BREAKER STATUS	PHASE A VA	PHASE B VA	BREAKER STATUS	BREAKER POLES	BREAKER AMPS	DESCRIPTION	CKT
1	RADIO EQUIPMENT	100	2	ON			ON	2	60	SUPPRESSOR	7
2											8
3	BLANK (UNUSED)	-	-	-			ON	2	30	CLEARWIRE	9
4	BLANK (UNUSED)	-	-	-							10
5	BLANK (UNUSED)	-	-	-			ON	1	15	TELCO GFI	11
6	FAN	10	1	ON						BLANK (UNUSED)	12

AC PANEL SCHEDULE
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251

1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

Transcend Wireless

48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

Signature: *James R. Skowronski* Date: 8/07/2014

MARK	DATE	DESCRIPTION
B	08/07/14	FINAL CONSTRUCTION DRAWINGS REVISIONS
A	06/10/14	FINAL CONSTRUCTION DRAWING REVISIONS

ISSUE PHASE: FINAL DATE ISSUED: 06/10/2014

PROJECT TITLE:
 BERLIN/RT 15/FIRE DEPT
 SITE#:CT43XC846-A

PROJECT INFORMATION:
 1657 WILBUR CROSS
 BERLIN, CT 06037
 HARTFORD COUNTY

SHEET TITLE:
 DC POWER DETAILS
 & PANEL SCHEDULES

SCALE:
 AS NOTED

PROJECT NUMBER: 28744
 SHEET NUMBER: E-3

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.