

JULIE D. KOHLER

PLEASE REPLY TO: Bridgeport
WRITER'S DIRECT DIAL: (203) 337-4157
E-Mail Address: jkohler@cohenandwolf.com

January 6, 2015

Attorney Melanie Bachman
Acting Executive Director
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

**Re: Notice of Exempt Modification
The Berlin Volunteer Fire Department, Inc./T-Mobile equipment upgrade
Site ID CTHA231A
1657 Berlin Turnpike (aka 1657 Wilbur Cross Highway) Berlin, CT 06037**

Dear Attorney Bachman:

This office represents T-Mobile Northeast LLC ("T-Mobile") and has been retained to file exempt modification filings with the Connecticut Siting Council on its behalf.

In this case, the Berlin Volunteer Fire Department, Inc. owns the existing monopole telecommunications tower and related facility at 1657 Berlin Turnpike, Berlin, CT (41.6062/-72.7497). T-Mobile intends to replace six (6) existing antennas with six (6) new antennas, add three (3) new antennas and related equipment at this existing telecommunications facility in Berlin ("Berlin Facility"). Please accept this letter as notification, pursuant to R.C.S.A. §16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to the Town Manager, Denise McNair, and the property owner, The Berlin Volunteer Fire Department, Inc..

The existing Berlin Facility consists of a 176 foot monopole tower.¹ T-Mobile plans to replace six (6) existing antennas with six (6) new antennas, and add three (3) new antennas at

¹ While the online docket for the Connecticut Siting Council does not provide a docket or petition number for approval of this structure, it does reference this structure in connection with a notices of intent captioned TS-AT&T-007-021025; TS-AT&T-007-021025, TS-T-MOBILE-007-051028, EM-VER-123-007-010-099-060308, EM-CING-007-062-126-135-137-070809, EM-VER-007-080305, EM-VER-007-080305, EM-POCKET-007-080918, EM-T-MOBILE-007-090417, EM-VER-007-100224, EM-CLEARWIRE-007-100305, EM-VER-007-100224, EM-AT&T-007-120427B, EM-SPRINT-007-121203, EM-METROPCS-007-130204MA, EM-VER-007-131122 and EM-SPRINT-007-140912.

a centerline of 160 feet. (See the plans revised to September 10, 2014 attached hereto as **Exhibit A**). T-Mobile will also install three (3) remote radio units mounted on new masts behind the antennas, remove three (3) tower mounted amplifiers ("TMAs"), replace an equipment cabinet, install fiber cable, and reuse existing coax cable which will be consolidated inside the monopole. The existing Berlin Facility is structurally capable of supporting T-Mobile's proposed modifications, as indicated in the structural analysis dated December 11, 2014, and attached hereto as **Exhibit B**.²

The planned modifications to the Berlin Facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modification will not increase the height of the tower. T-Mobile's existing antennas are at a centerline of 160 feet; the replacement/additional antennas and equipment will be installed at the same 160 foot level. The enclosed tower drawing confirms that the proposed modification will not increase the height of the tower.

2. The proposed modifications will not require an extension on the site boundaries or lease area, as depicted on Sheet 2 of Exhibit A. T-Mobile's equipment will be located entirely within the existing compound area.

3. The proposed modification to the Facility will not increase the noise levels at the existing facility by six decibels or more.

4. The operation of the replacement/additional antennas and equipment will not increase the total radio frequency (RF) power density, measured at the base of the tower, to a level at or above the applicable standard. According to a Radio Frequency Emissions Analysis Report prepared by EBI dated September 15, 2014, T-Mobile's operations would add 5.09% of the FCC Standard. Therefore, the calculated "worst case" power density for the planned combined operation at the site including all of the proposed antennas would be 71.02% of the FCC Standard as calculated for a mixed frequency site as evidenced by the engineering exhibit attached hereto as **Exhibit C**.

For the foregoing reasons, T-Mobile respectfully submits that the proposed replacement/additional antennas and equipment at the Berlin Facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Upon acknowledgement of this exempt modification, T-Mobile shall commence construction approximately sixty days from the receipt of the Council's decision.

² The Structural Analysis Report provides for modifications to the monopole base plate. These modifications will be completed prior to T-Mobile's facility upgrade.

January 6, 2015
Site ID CTHA231A
Page 3

Sincerely,



Julie D. Kohler, Esq.

cc: Town Manager Denise McNair, Town of Berlin
Berlin Volunteer Fire Department, Inc.
Sheldon J. Freinckle, Northeast Site Solutions (via e-mail)

EXHIBIT A



KEY PLAN

N.T.S.

PROJECT : L700
CONFIGURATION

702CU

SUBMITTALS	
LE REV A	09.09.14
LE REV 0	09.10.14

ATLANTIS GROUP
 1340 Centre Street
 Suite 212
 Newton, MA 02459
 Office: 617-965-0789
 Fax: 617-213-5056

LEASE EXHIBIT
 SITE NUMBER:
 CTHA231A
 SITE NAME:
 HA231/BERLIN FD TOWER
 SITE ADDRESS:
 1697 BERLIN TURNPIKE
 BERLIN, CT 06037



NORTHEAST SITE SOLUTIONS
 54 MAIN STREET, UNIT 3
 STURBRIDGE, MA 01566
 (508) 434-5237
 FOR
T-MOBILE NORTHEAST, LLC
 35 GRIFFIN ROAD SOUTH
 BLOOMFIELD, CT 06002
 OFFICE: (860) 692-7100
 FAX: (860) 692-7159

DRAWN BY: EB

CHECKED BY: SM

PAGE 1 OF 3

BERLIN TURNPIKE



ALL EQUIPMENT LOCATIONS ARE APPROXIMATE AND ARE SUBJECT TO APPROVAL BY LESSEE/LICENSEE'S STRUCTURAL & RF ENGINEERS. LOCATIONS OF POWER & TELEPHONE FACILITIES ARE SUBJECT TO APPROVAL BY UTILITY COMPANIES.

SITE PLAN

N.T.S.



PROJECT : L700
CONFIGURATION

702CU

SUBMITTALS	
LE REV A	09.09.14
LE REV 0	09.10.14

ATLANTIS GROUP
1340 Centre Street
Suite 212
Newton, MA 02459
Office: 617-965-0789
Fax: 617-213-5056


LEASE EXHIBIT
SITE NUMBER:
CTHA231A
SITE NAME:
HA231/BERLIN FD TOWER
SITE ADDRESS:
1697 BERLIN TURNPIKE
BERLIN, CT 06037

NORTHEAST SITE SOLUTIONS
54 MAIN STREET, UNIT 3
STURBRIDGE, MA 01566
(508) 434-5237
FOR
T-MOBILE NORTHEAST, LLC
35 GRIFFIN ROAD SOUTH
BLOOMFIELD, CT 06002
OFFICE: (860) 692-7100
FAX: (860) 692-7159

DRAWN BY: EB

CHECKED BY: SM

PAGE 2 OF 3



ELEVATION
 SCALE : N.T.S.

1
 LE-3

PROJECT : L700
 CONFIGURATION
702CU

SUBMITTALS	
LE REV A	09.09.14
LE REV 0	09.10.14

ATLANTIS GROUP
 1340 Centre Street
 Suite 212
 Newton, MA 02459
 Office: 617-965-0789
 Fax: 617-213-5056

LEASE EXHIBIT
 SITE NUMBER:
 CTHA231A
 SITE NAME:
 HA231/BERLIN FD TOWER
 SITE ADDRESS:
 1697 BERLIN TURNPIKE
 BERLIN, CT 06037

NORTHEAST SITE SOLUTIONS
 54 MAIN STREET, UNIT 3
 STURBRIDGE, MA 01566
 (508) 434-5237
 FOR
T-MOBILE NORTHEAST, LLC
 35 GRIFFIN ROAD SOUTH
 BLOOMFIELD, CT 06002
 OFFICE: (860) 692-7100
 FAX: (860) 692-7159

EXHIBIT B

STRUCTURAL ANALYSIS REPORT – POST MODIFICATION

December 11, 2014

T-Mobile, USA
35 Griffin Road South
Bloomfield, CT 06002
Attention: Mark Richard

Subject: 700 MHz Upgrade Project
Site #: CTHA231A
EBI Reference #: 81140835
Site Name: HA231 / Berlin FD Tower
Address: 1657 Berlin Turnpike, Berlin, CT 06037

Dear Mr. Richard:

EBI Consulting's structural engineers have prepared this structural report for the tower at the above address, in accordance with the CT State Building Code (with amendments) and ANSI/TIA/EIA-222 Revision F. Information from the following sources was utilized in our analysis:

1. Tower analysis by Ramaker & Associates, Inc. dated 8-5-14.
2. Photographs from site visit by EBI on 6-17-14 and 7-24-14.

The tower was analyzed for a wind speed of 80 mph without ice and with 1/2" radial ice at a reduced wind speed of 69 mph.

The monopole base plate shall be modified with the addition of eighteen (18) proposed stiffener plates in accordance with the EBI Construction Drawings. The required modifications shall be completed prior to any proposed equipment loading changes.

The proposed (3) Commscope LNX-6515DS-VTM panel antennas, (3) Ericsson AIR21B2A/B4P panel antennas, and (3) Ericsson AIR21B4A/B2P panel antennas shall be installed on proposed 2-7/8" O.D. pipe masts, mounted to existing sector frames at a centerline elevation of 160' above grade level. The antennas will use the proposed fiber cable, which will be installed inside the monopole. The three proposed RRUS11 B12 remote radio units are to be located behind the antennas with one in each sector.

Local Equipment Support:

Our inspection of the tower mounting frame shows that the structural elements HAVE ADEQUATE CAPACITY for the proposed loading. The sector frame is estimated to consist of:

- T-shaped in plan with a nominal face width between 10'-0" and 12'-0".

- Horizontal T-arm members are made from 3-1/2" outer diameter Sch. 40 pipe minimum.
- Main supporting members, spanning from the tower connection point to the center point of the horizontal T-arm, are square hollow structural section, HSS3.5x3.5x1/4" minimum, with a standoff of no more than 40".
- Standoff arms are connected to the ring mount with at least (4) 5/8" minimum diameter A325 bolts.
- Robust ring mount with (3) 3/4" minimum diameter high-strength steel threaded rods at each connection.

Global Tower Analysis Summary of Results: (Refer to attached TNX Tower Analysis for detailed analysis results)

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	SF*P _{allow} lb	% Capacity	Pass Fail	
L1	176 - 130.75	Pole	TP31.8x21x0.25	1	-11003.20	1257185.57	55.8	Pass	
L2	130.75 - 86.12	Pole	TP41.82x30.226x0.3125	2	-22142.50	2070348.86	83.8	Pass	
L3	86.12 - 43	Pole	TP51.36x39.8381x0.375	3	-34549.10	3052703.17	86.2	Pass	
L4	43 - 1	Pole	TP60.5x48.9596x0.4375	4	-52198.60	4335942.23	80.5	Pass	
							Summary		
							Pole (L3)	86.2	Pass
							Base Plate	89.5	Pass
							RATING =	89.5	Pass

The maximum stress under the proposed conditions and configurations is **89.5%** of the tower capacity, governed by the base plate. Therefore **the tower has sufficient structural capacity with the modifications listed herein** for the proposed equipment configurations.

Global Tower Analysis Foundation:

Max. corner reaction at base:	Previous Report Reactions (kips)	Proposed Loading Reactions (kips)
Axial (kips)	51.2	52.2 (no ice)
Moment (foot-kips)	4320	4250
Shear (kips)	35.1	34.6

The previous structural analysis was made available to EBI Consulting for comparing current reactions with previous reactions. It can be seen that the current moment reaction is below that of the previous analysis and that the foundation will have adequate capacity for the proposed loading. The previous foundation analysis remains valid for the proposed loading.

Limitations and Assumptions:

This report is based on the following:

1. Tower is properly installed and maintained.
2. All members are as specified in the original design documents and are in good condition.
3. All required members are in place.
4. All bolts are in place and are tightly fastened.
5. Tower is in plumb condition.
6. All member protective coatings are in good condition.
7. All tower members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
8. Base plate modifications specified in the EBI Construction Drawings have been installed.

EBI is not responsible for any modifications completed prior to or hereafter in which EBI is not or was not directly involved. Modifications include but are not limited to:

- A. Adding antennas
- B. Removing/replacing antennas
- C. Adding coaxial cables

EBI hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations, and conclusions are based upon information contained and set forth herein. If you are aware of any information which conflicts with that which is contained herein, or you are aware of any defects arising from the original design, material, fabrication, or erection deficiencies, you should disregard this report and immediately contact EBI. EBI disclaims all liability for any representation, recommendation, or conclusion not expressly stated herein.

THE CONCLUSION OF THE TOWER STRUCTURAL ANALYSIS IS THAT THE TOWER HAS ADEQUATE CAPACITY WITH THE MODIFICATIONS LISTED HEREIN FOR THE PROPOSED LOADING. Please contact this office should you have any questions regarding this matter.


Sincerely,

EBI Consulting


December 11, 2014



Brandon Kelsey, E.I.T.



Richard L. Peterman, P.E.
Professional Engineer



STRUCTURAL PHOTO LOG



<p>Photo 1: General view of top of monopole</p>	
<p>Photo 2: General view of the existing base plate – stiffener plates not yet constructed.</p>	

Photo 3:
Overall view of tower.



APPENDIX A

TNX Tower Results

Section	1	2	3	4	
Length (ft)	45.25	49.13	48.87	49.00	
Number of Sides	18	18	18	18	
Thickness (in)	0.2500	0.3125	0.3750	0.4375	
Socket Length (ft)	4.50	5.75	7.00		
Top Dia (in)	21.0000	30.2260	39.8981	48.9596	
Bot Dia (in)	31.8000	41.9200	51.3600	60.5000	
Grade			A572-65		
Weight (lb)	3195.0	5921.5	8951.3	12570.6	


176.0 ft

130.8 ft

86.1 ft

43.0 ft

1.0 ft





DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
10' Dipole	176	840 10054 w pipe	150
10' Dipole	176	840 10054 w pipe	150
10' Dipole	176	840 10054 w pipe	150
10' Omni	176	nRRH	150
10' Omni	176	nRRH	150
Vallmont 13'-5" Platform	176	nRRH	150
MF-900B	176	Vallmont 13'-5" Platform	150
MF-900B	176	APXVSP18-C-A20 w pipe	150
800 10121 w Pipe	170	APXVSP18-C-A20 w pipe	150
AM-X-CD-16-65-00T-RET	170	APXVSP18-C-A20 w pipe	150
AM-X-CD-16-65-00T-RET	170	VHLP2.5-11	150
AM-X-CD-16-65-00T-RET	170	VHLP2.5-11	150
(2) 860-10025	170	VHLP2.5-11	150
(2) 860-10025	170	VHLP2.5-11	150
(2) 860-10025	170	10' Dipole	130
(2) LGP214nn	170	TMA	130
(2) LGP214nn	170	6' Standoff	130
(2) LGP214nn	170	742 213V01 w pipe	124
RRUS11	170	742 213V01 w pipe	124
RRUS11	170	742 213V01 w pipe	124
RRUS11	170	LNX-6514DS-T4M w pipe	114
DC6-28-60-18-8F	170	LNX-6514DS-T4M w pipe	114
EEl (3) 12' Universal T-arms	170	BXA-185060-12CF-EDIN-X w pipe	114
800 10121 w Pipe	170	MGD3-900TX w pipe	114
800 10121 w Pipe	170	MGD3-900TX w pipe	114
10' Dipole	162	TMA	114
6' Standoff	162	TMA	114
MF-900B	162	TMA	114
(4) ETD819H-12UB	160	Vallmont 13'-5" Platform	114
(4) ETD819H-12UB	160	LPA-80063-6CF-EDIN-X w pipe	114
(4) ETD819H-12UB	160	LPA-80063-6CF-EDIN-X w pipe	114
LNX-6515DS-VTM w pipe	160	LPA-80063-6CF-EDIN-X w pipe	114
LNX-6515DS-VTM w pipe	160	RWA-80013 w pipe	114
LNX-6515DS-VTM w pipe	160	RWA-80013 w pipe	114
RRUS11_B12	160	LNX-6514DS-T4M w pipe	114
RRUS11_B12	160	LPA-80063-6CF-EDIN-X w pipe	114
RRUS11_B12	160	10' Dipole	100
EEl (3) 12' Universal T-arms	160	TMA	100
(2) AIR21 B4A/B2P w/ mast pipe	160	6' Standoff	100
(2) AIR21 B4A/B2P w/ mast pipe	160	MF-900B	100
(2) AIR21 B4A/B2P w/ mast pipe	160	GPS	76
1900MHz 4x45W RRH	150	2' Standoff	76
1900MHz 4x45W RRH	150	GPS	61
1900MHz 4x45W RRH	150	2' Standoff	61
800MHz 2x50W RRH	150	GPS	61
800MHz 2x50W RRH	150	2' Standoff	61
800MHz 2x50W RRH	150		

TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 69 mph basic wind with 0.50 in ice.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 89.5%



 EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job: CTHA231A		
	Project: 81140835		
	Client: T-Mobile	Drawn by: Brandon Kelsey	App'd:
	Code: TIA/EIA-222-F	Date: 12/11/14	Scale: NTS
	Path:		Dwg No. E-1

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	1 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Hartford County, Connecticut.

Basic wind speed of 80 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56 pcf.

A wind speed of 69 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|--|--|---|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) Add IBC .6D+W Combination | <ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. Autocalc Torque Arm Areas SR Members Have Cut Ends Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Use TIA-222-G Tension Splice Capacity Exemption | <ul style="list-style-type: none"> Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feedline Torque Include Angle Block Shear Check <li style="padding-left: 20px;">Poles Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets |
|--|--|---|

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	176.00-130.75	45.25	4.50	18	21.0000	31.8000	0.2500	1.0000	A572-65 (65 ksi)
L2	130.75-86.12	49.13	5.75	18	30.2260	41.8200	0.3125	1.2500	A572-65 (65 ksi)
L3	86.12-43.00	48.87	7.00	18	39.8381	51.3600	0.3750	1.5000	A572-65 (65 ksi)
L4	43.00-1.00	49.00		18	48.9596	60.5000	0.4375	1.7500	A572-65 (65 ksi)

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job CTHA231A	Page 2 of 16
	Project 81140835	Date 16:47:41 12/11/14
	Client T-Mobile	Designed by Brandon Kelsey

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	I/Q in ²	w in	w/t
L1	21.3240	16.4651	895.6507	7.3663	10.6680	83.9568	1792.4800	8.2341	3.2560	13.024
	32.2906	25.0349	3148.3461	11.2003	16.1544	194.8909	6300.8349	12.5198	5.1568	20.627
L2	31.7706	29.6704	3354.2440	10.6193	15.3548	218.4493	6712.9015	14.8380	4.7698	15.263
	42.4651	41.1703	8961.3641	14.7352	21.2446	421.8192	17934.5198	20.5890	6.8103	21.793
L3	41.8292	46.9709	9241.6271	14.0094	20.2377	456.6531	18495.4146	23.4899	6.3515	16.937
	52.1523	60.6849	19929.7987	18.0997	26.0909	763.8607	39885.8215	30.3482	8.3794	22.345
L4	51.3890	67.3790	20042.0460	17.2254	24.8715	805.8240	40110.4639	33.6959	7.8469	17.936
	61.4333	83.4043	38013.0437	21.3222	30.7340	1236.8401	76076.1060	41.7101	9.8780	22.578

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A _f	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals
ft	ft ²	in					in	in
L1 176.00-130.75				1	1	1		
L2 130.75-86.12				1	1	1		
L3 86.12-43.00				1	1	1		
L4 43.00-1.00				1	1	1		

Monopole Base Plate Data

Base Plate Data

Base plate is square	
Base plate is grouted	
Anchor bolt grade	A615-75
Anchor bolt size	2.2500 in
Number of bolts	18
Embedment length	48.0000 in
f _c	4 ksi
Grout space	2.0000 in
Base plate grade	A572-60
Base plate thickness	2.0000 in
Bolt circle diameter	70.0000 in
Outer diameter	76.0000 in
Inner diameter	60.7500 in
Base plate type	Stiffened Plate
Bolts per stiffener	1
Stiffener thickness	0.5000 in
Stiffener height	12.0000 in

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Shield Leg	Allow Shield	Component Type	Placement ft	Total Number	C _A A _A	Weight plf
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	22.00 - 176.00	7	No Ice	0.00
						1/2" Ice	0.00
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	10.00 - 171.00	6	No Ice	0.00

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job CTHA231A	Page 3 of 16
	Project 81140835	Date 16:47:41 12/11/14
	Client T-Mobile	Designed by Brandon Kelsey

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	C _A A _A		Weight
						1/2" Ice	ft ² /ft	plf
Fiber	C	No	Inside Pole	10.00 - 171.00	1	1/2" Ice	0.00	1.04
						No Ice	0.00	0.33
						1/2" Ice	0.00	0.33
Power Cable	C	No	Inside Pole	10.00 - 171.00	2	No Ice	0.00	0.33
						1/2" Ice	0.00	0.33
						1/2" Ice	0.00	1.04
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	22.00 - 163.00	2	No Ice	0.00	1.04
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	10.00 - 161.00	24	1/2" Ice	0.00	1.04
						No Ice	0.00	1.04
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	10.00 - 161.00	1	1/2" Ice	0.00	1.04
						No Ice	0.00	1.04
LDF6-50A (1-1/4 FOAM) CAT5e	C	No	Inside Pole	10.00 - 151.00	3	1/2" Ice	0.00	0.66
						No Ice	0.00	0.66
						1/2" Ice	0.00	0.82
HJ4-50 (1/2 AIR)	C	No	Inside Pole	10.00 - 151.00	4	1/2" Ice	0.00	0.82
						No Ice	0.00	0.25
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	22.00 - 131.00	1	1/2" Ice	0.00	0.25
						No Ice	0.00	1.04
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	10.00 - 125.00	6	1/2" Ice	0.00	1.04
						No Ice	0.00	1.04
HJ7-50A (1-5/8 AIR)	C	No	CaAa (Out Of Face)	22.00 - 115.00	2	1/2" Ice	0.00	1.04
						No Ice	0.20	2.55
HJ7-50A (1-5/8 AIR)	C	No	CaAa (Out Of Face)	22.00 - 115.00	5	1/2" Ice	0.00	1.04
						No Ice	0.00	1.04
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	22.00 - 115.00	12	1/2" Ice	0.00	1.04
						No Ice	0.00	1.04
HJ7-50A (1-5/8 AIR)	C	No	Inside Pole	22.00 - 101.00	2	1/2" Ice	0.00	1.04
						No Ice	0.00	1.04
HJ4-50 (1/2 AIR)	C	No	Inside Pole	10.00 - 76.00	1	1/2" Ice	0.00	0.25
						No Ice	0.00	0.25
HJ4-50 (1/2 AIR)	C	No	Inside Pole	22.00 - 61.00	1	1/2" Ice	0.00	0.25
						No Ice	0.00	0.25

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A	C _A A _A	Weight lb
					In Face ft ²	Out Face ft ²	
L1	176.00-130.75	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	1634.24
L2	130.75-86.12	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	11.436	3144.01
L3	86.12-43.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	17.076	3445.53
L4	43.00-1.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	8.316	2253.75

Feed Line/Linear Appurtenances Section Areas - With Ice

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job CTHA231A	Page 4 of 16
	Project 81140835	Date 16:47:41 12/11/14
	Client T-Mobile	Designed by Brandon Kelsey

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight lb
L1	176.00-130.75	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	1634.24
L2	130.75-86.12	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	17.212	3231.52
L3	86.12-43.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	25.699	3576.18
L4	43.00-1.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	12.516	2317.38

Feed Line Center of Pressure

Section	Elevation ft	CP _X in	CP _Z in	CP _X Ice in	CP _Z Ice in
L1	176.00-130.75	0.0000	0.0000	0.0000	0.0000
L2	130.75-86.12	-0.3227	0.1863	-0.4562	0.2634
L3	86.12-43.00	-0.4665	0.2693	-0.6583	0.3800
L4	43.00-1.00	-0.2357	0.1361	-0.3417	0.1973

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight lb
**								
10' Dipole	A	From Face	5.00 0.00 5.00	0.0000	176.00	No Ice 1/2" Ice 4.00	3.00 4.00	30.00 55.00
10' Dipole	B	From Face	5.00 0.00 5.00	0.0000	176.00	No Ice 1/2" Ice 4.00	3.00 4.00	30.00 55.00
10' Dipole	B	From Leg	5.00 0.00 5.00	0.0000	176.00	No Ice 1/2" Ice 4.00	3.00 4.00	30.00 55.00
10' Omni	C	From Face	5.00 0.00 5.00	0.0000	176.00	No Ice 1/2" Ice 3.53	2.50 3.53	30.00 48.64
10' Omni	C	From Face	6.00 5.00 5.00	0.0000	176.00	No Ice 1/2" Ice 3.53	2.50 3.53	30.00 48.64
Vallmont 13'-5" Platform	C	None		0.0000	176.00	No Ice 1/2" Ice 22.32	18.43 22.32	1759.00 2143.00
**								
800 10121 w Pipe	A	From Face	4.00	0.0000	170.00	No Ice 5.80	4.72	72.60

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	5 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight lb	
			-6.00			1/2" Ice	6.35	5.56	121.39
800 10121 w Pipe	B	From Face	0.00	0.0000	170.00	No Ice	5.80	4.72	72.60
			4.00			1/2" Ice	6.35	5.56	121.39
800 10121 w Pipe	C	From Face	0.00	0.0000	170.00	No Ice	5.80	4.72	72.60
			4.00			1/2" Ice	6.35	5.56	121.39
AM-X-CD-16-65-00T-RET	A	From Face	0.00	0.0000	170.00	No Ice	8.50	6.30	74.05
			4.00			1/2" Ice	9.15	7.48	139.04
AM-X-CD-16-65-00T-RET	B	From Face	0.00	0.0000	170.00	No Ice	8.50	6.30	74.05
			4.00			1/2" Ice	9.15	7.48	139.04
AM-X-CD-16-65-00T-RET	C	From Face	0.00	0.0000	170.00	No Ice	8.50	6.30	74.05
			4.00			1/2" Ice	9.15	7.48	139.04
(2) 860-10025	A	From Face	0.00	0.0000	170.00	No Ice	0.14	0.23	1.16
			4.00			1/2" Ice	0.20	0.30	3.13
(2) 860-10025	B	From Face	0.00	0.0000	170.00	No Ice	0.14	0.23	1.16
			4.00			1/2" Ice	0.20	0.30	3.13
(2) 860-10025	C	From Face	0.00	0.0000	170.00	No Ice	0.14	0.23	1.16
			4.00			1/2" Ice	0.20	0.30	3.13
(2) LGP214nn	A	From Face	0.00	0.0000	170.00	No Ice	1.30	0.23	14.10
			4.00			1/2" Ice	1.45	0.31	21.30
(2) LGP214nn	B	From Face	0.00	0.0000	170.00	No Ice	1.30	0.23	14.10
			4.00			1/2" Ice	1.45	0.31	21.30
(2) LGP214nn	C	From Face	0.00	0.0000	170.00	No Ice	1.30	0.23	14.10
			4.00			1/2" Ice	1.45	0.31	21.30
RRUS11	A	From Leg	0.00	0.0000	170.00	No Ice	3.31	1.36	55.00
			4.00			1/2" Ice	3.55	1.54	74.32
RRUS11	B	From Leg	0.00	0.0000	170.00	No Ice	3.31	1.36	55.00
			4.00			1/2" Ice	3.55	1.54	74.32
RRUS11	C	From Leg	0.00	0.0000	170.00	No Ice	3.31	1.36	55.00
			4.00			1/2" Ice	3.55	1.54	74.32
DC6-28-60-18-8F	C	None	0.0000	0.0000	170.00	No Ice	1.47	1.47	33.00
						1/2" Ice	1.67	1.67	50.70
EEI (3) 12' Universal T-arms	A	None	0.0000	0.0000	170.00	No Ice	16.66	16.66	550.00
						1/2" Ice	21.00	21.00	710.00

10' Dipole	A	From Face	6.00	0.0000	162.00	No Ice	3.00	3.00	30.00
			0.00			1/2" Ice	4.00	4.00	55.00
			4.00						
6' Standoff	A	From Face	3.00	0.0000	162.00	No Ice	4.97	4.97	70.00
			0.00			1/2" Ice	6.12	6.12	130.00
			0.00						

(2) AIR21 B4A/B2P w/ mast	A	From Leg	5.00	0.0000	160.00	No Ice	6.85	5.78	126.90

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	6 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A ₁ Front ft ²	C _A A ₂ Side ft ²	Weight lb
pipe			-5.00 0.00			1/2" Ice 7.41	6.70	182.26
(2) AIR21 B4A/B2P w/ mast pipe	B	From Leg	5.00 -5.00 0.00	0.0000	160.00	No Ice 1/2" Ice 7.41	5.78 6.70	126.90 182.26
(2) AIR21 B4A/B2P w/ mast pipe	C	From Leg	5.00 -5.00 0.00	0.0000	160.00	No Ice 1/2" Ice 7.41	5.78 6.70	126.90 182.26
(4) ETD819H-12UB	A	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1.70	0.39 0.49	18.50 27.42
(4) ETD819H-12UB	B	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1.70	0.39 0.49	18.50 27.42
(4) ETD819H-12UB	C	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1.70	0.39 0.49	18.50 27.42
LNX-6515DS-VTM w pipe	A	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 12.06	10.00 11.42	96.62 187.36
LNX-6515DS-VTM w pipe	B	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 12.06	10.00 11.42	96.62 187.36
LNX-6515DS-VTM w pipe	C	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 12.06	10.00 11.42	96.62 187.36
RRUS11_B12	A	From Leg	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 3.55	1.36 1.54	51.00 71.87
RRUS11_B12	B	From Leg	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 3.55	1.36 1.54	51.00 71.87
RRUS11_B12	C	From Leg	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 3.55	1.36 1.54	51.00 71.87
EEl (3) 12' Universal T-arms	A	None		0.0000	160.00	No Ice 1/2" Ice 21.00	16.66 21.00	550.00 710.00
** APXVSPP18-C-A20 w pipe	A	From Face	4.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 9.21	6.95 8.13	82.55 150.82
APXVSPP18-C-A20 w pipe	B	From Face	4.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 9.21	6.95 8.13	82.55 150.82
APXVSPP18-C-A20 w pipe	C	From Face	4.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 9.21	6.95 8.13	82.55 150.82
1900MHz 4x45W RRH	A	From Face	4.00 0.00 -2.00	0.0000	150.00	No Ice 1/2" Ice 2.95	2.61 2.84	82.62 108.98
1900MHz 4x45W RRH	B	From Face	4.00 0.00 -2.00	0.0000	150.00	No Ice 1/2" Ice 2.95	2.61 2.84	82.62 108.98
1900MHz 4x45W RRH	C	From Face	4.00 0.00 -2.00	0.0000	150.00	No Ice 1/2" Ice 2.95	2.61 2.84	82.62 108.98
800MHz 2x50W RRH	A	From Face	4.00	0.0000	150.00	No Ice	2.25	64.00

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	7 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight lb
			0.00			1/2" Ice 2.61	2.46	86.12
800MHz 2x50W RRH	B	From Face	-2.00	0.0000	150.00	No Ice 2.40	2.25	64.00
			4.00			1/2" Ice 2.61	2.46	86.12
			0.00					
			-2.00					
800MHz 2x50W RRH	C	From Face	4.00	0.0000	150.00	No Ice 2.40	2.25	64.00
			0.00			1/2" Ice 2.61	2.46	86.12
			-2.00					
840 10054 w pipe	A	From Face	4.00	0.0000	150.00	No Ice 5.29	2.23	48.60
			0.00			1/2" Ice 5.68	2.73	83.42
			0.00					
840 10054 w pipe	B	From Face	4.00	0.0000	150.00	No Ice 5.29	2.23	48.60
			0.00			1/2" Ice 5.68	2.73	83.42
			0.00					
840 10054 w pipe	C	From Face	4.00	0.0000	150.00	No Ice 5.29	2.23	48.60
			0.00			1/2" Ice 5.68	2.73	83.42
			0.00					
nRRH	A	From Face	4.00	0.0000	150.00	No Ice 2.69	0.85	45.00
			0.00			1/2" Ice 2.91	1.01	60.06
			-1.00					
nRRH	B	From Face	4.00	0.0000	150.00	No Ice 2.69	0.85	45.00
			0.00			1/2" Ice 2.91	1.01	60.06
			-1.00					
nRRH	C	From Face	4.00	0.0000	150.00	No Ice 2.69	0.85	45.00
			0.00			1/2" Ice 2.91	1.01	60.06
			-1.00					
Vallmont 13'-5" Platform	C	None		0.0000	150.00	No Ice 18.43	18.43	1759.00
						1/2" Ice 22.32	22.32	2143.00
**								
10' Dipole	B	From Face	6.00	0.0000	130.00	No Ice 3.00	3.00	30.00
			0.00			1/2" Ice 4.00	4.00	55.00
			5.00					
TMA	B	From Face	2.00	0.0000	130.00	No Ice 1.40	0.70	5.00
			0.00			1/2" Ice 1.56	0.83	15.34
			0.00					
6' Standoff	B	From Face	3.00	0.0000	130.00	No Ice 4.97	4.97	70.00
			0.00			1/2" Ice 6.12	6.12	130.00
			0.00					
**								
742 213V01 w pipe	A	From Face	0.00	0.0000	124.00	No Ice 5.41	4.75	46.80
			0.00			1/2" Ice 5.99	6.10	91.90
			0.00					
742 213V01 w pipe	B	From Face	0.00	0.0000	124.00	No Ice 5.41	4.75	46.80
			0.00			1/2" Ice 5.99	6.10	91.90
			0.00					
742 213V01 w pipe	C	From Face	0.00	0.0000	124.00	No Ice 5.41	4.75	46.80
			0.00			1/2" Ice 5.99	6.10	91.90
			0.00					
**								
LPA-80063-6CF-EDIN-X w pipe	A	From Face	4.00	0.0000	114.00	No Ice 11.00	12.33	56.20
			6.00			1/2" Ice 11.78	0.00	152.21
			2.00					
LPA-80063-6CF-EDIN-X w pipe	B	From Face	4.00	0.0000	114.00	No Ice 11.00	12.33	56.20
			6.00			1/2" Ice 11.78	0.00	152.21
			2.00					
LPA-80063-6CF-EDIN-X w pipe	A	From Face	4.00	0.0000	114.00	No Ice 11.00	12.33	56.20
			-2.00			1/2" Ice 11.78	0.00	152.21

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	8 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A ₁ Front ft ²	C _A A ₂ Side ft ²	Weight lb	
LPA-80063-6CF-EDIN-X w pipe	B	From Face	2.00 4.00 -2.00	0.0000	114.00	No Ice 1/2" Ice	11.00 11.78	12.33 0.00	56.20 152.21
RWA-80013 w pipe	C	From Face	2.00 4.00 6.00	0.0000	114.00	No Ice 1/2" Ice	6.14 6.85	4.66 5.70	39.85 90.85
RWA-80013 w pipe	C	From Face	2.00 4.00 -2.00	0.0000	114.00	No Ice 1/2" Ice	6.14 6.85	4.66 5.70	39.85 90.85
LNx-6514DS-T4M w pipe	A	From Face	2.00 4.00 -6.00	0.0000	114.00	No Ice 1/2" Ice	8.41 8.96	6.83 7.79	60.30 126.69
LNx-6514DS-T4M w pipe	B	From Face	2.00 4.00 -6.00	0.0000	114.00	No Ice 1/2" Ice	8.41 8.96	6.83 7.79	60.30 126.69
LNx-6514DS-T4M w pipe	C	From Face	2.00 4.00 -6.00	0.0000	114.00	No Ice 1/2" Ice	8.41 8.96	6.83 7.79	60.30 126.69
BXA-185060-12CF-EDIN-X w pipe	A	From Face	2.00 4.00 2.00	0.0000	114.00	No Ice 1/2" Ice	5.03 5.58	5.29 6.46	38.35 84.33
MGD3-900TX w pipe	B	From Face	2.00 4.00 2.00	0.0000	114.00	No Ice 1/2" Ice	5.19 5.74	5.01 6.18	45.40 90.70
MGD3-900TX w pipe	C	From Face	2.00 4.00 2.00	0.0000	114.00	No Ice 1/2" Ice	5.19 5.74	5.01 6.18	45.40 90.70
TMA	A	From Face	2.00 3.00 -5.00	0.0000	114.00	No Ice 1/2" Ice	1.40 1.56	0.70 0.83	5.00 15.34
TMA	B	From Face	2.00 3.00 -5.00	0.0000	114.00	No Ice 1/2" Ice	1.40 1.56	0.70 0.83	5.00 15.34
TMA	C	From Face	2.00 3.00 -5.00	0.0000	114.00	No Ice 1/2" Ice	1.40 1.56	0.70 0.83	5.00 15.34
Vallmont 13'-5" Platform	C	None	2.00	0.0000	114.00	No Ice 1/2" Ice	18.43 22.32	18.43 22.32	1759.00 2143.00
** 10' Dipole	B	From Face	0.00 5.00 2.00	0.0000	100.00	No Ice 1/2" Ice	3.00 4.00	3.00 4.00	30.00 55.00
TMA	B	From Face	0.00 0.00 0.00	0.0000	100.00	No Ice 1/2" Ice	1.40 1.56	0.70 0.83	5.00 15.34
6' Standoff	B	From Face	0.00 3.00 0.00	0.0000	100.00	No Ice 1/2" Ice	4.97 6.12	4.97 6.12	70.00 130.00
GPS	A	From Face	0.00 2.00 0.00	0.0000	76.00	No Ice 1/2" Ice	1.00 1.50	1.00 1.50	10.00 15.00
2' Standoff	A	From Face	0.00 1.00 0.00	0.0000	76.00	No Ice 1/2" Ice	1.80 3.30	1.80 3.30	33.00 59.00
GPS	A	From Face	0.00 2.00 0.00	0.0000	61.00	No Ice 1/2" Ice	1.00 1.50	1.00 1.50	10.00 15.00

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job CTHA231A	Page 9 of 16
	Project 81140835	Date 16:47:41 12/11/14
	Client T-Mobile	Designed by Brandon Kelsey

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A Front	C _A A _A Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	lb	
2' Standoff	A	From Face	0.00	1.00	0.0000	61.00	No Ice	1.80	1.80	33.00
			0.00	0.00			1/2" Ice	3.30	3.30	59.00
			0.00	0.00						
GPS	B	From Face	2.00	0.00	0.0000	61.00	No Ice	1.00	1.00	10.00
			0.00	0.00			1/2" Ice	1.50	1.50	15.00
			0.00	0.00						
2' Standoff	B	From Face	1.00	0.00	0.0000	61.00	No Ice	1.80	1.80	33.00
			0.00	0.00			1/2" Ice	3.30	3.30	59.00
			0.00	0.00						

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz	Vert							
				ft	ft	°	°	ft	ft	ft ²	lb	
MF-900B	B	Grid	From Leg	5.00	0.00	0.0000		176.00	1.33	No Ice	1.39	13.00
				0.00	0.00					1/2" Ice	1.57	21.06
				0.00	0.00							
MF-900B	C	Grid	From Leg	5.00	0.00	0.0000		176.00	1.33	No Ice	1.39	13.00
				0.00	0.00					1/2" Ice	1.57	21.06
				0.00	0.00							
MF-900B	A	Grid	From Leg	5.00	0.00	0.0000		162.00	1.33	No Ice	1.39	13.00
				0.00	0.00					1/2" Ice	1.57	21.06
				0.00	0.00							
MF-900B	B	Grid	From Leg	5.00	0.00	0.0000		100.00	1.33	No Ice	1.39	13.00
				0.00	0.00					1/2" Ice	1.57	21.06
				0.00	0.00							
**												
VHLP2.5-11	A	Paraboloid w/Shroud (HP)	From Face	5.00	-2.00	0.0000		150.00	2.92	No Ice	6.70	48.00
				4.00	2.00					1/2" Ice	7.08	84.34
				2.00	2.00							
VHLP2.5-11	A	Paraboloid w/Shroud (HP)	From Face	5.00	2.00	0.0000		150.00	2.92	No Ice	6.70	48.00
				2.00	2.00					1/2" Ice	7.08	84.34
				2.00	2.00							
VHLP2.5-11	B	Paraboloid w/Shroud (HP)	From Face	5.00	2.00	0.0000		150.00	2.92	No Ice	6.70	48.00
				2.00	2.00					1/2" Ice	7.08	84.34
				2.00	2.00							
VHLP2.5-11	C	Paraboloid w/Shroud (HP)	From Face	5.00	2.00	0.0000		150.00	2.92	No Ice	6.70	48.00
				2.00	2.00					1/2" Ice	7.08	84.34
				2.00	2.00							

Load Combinations

Comb. No.	Description
-----------	-------------

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	10 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Pole	Max. Vert	18	61836.02	-28637.09	-71.52
	Max. H _x	11	52219.97	34386.11	12.00
	Max. H _z	2	52219.98	86.15	34538.21
	Max. M _x	2	4240737.37	86.15	34538.21
	Max. M _z	5	4234943.32	-34457.89	-139.90
	Max. Torsion	6	4659.77	-29861.16	-17324.03
	Min. Vert	1	52219.97	0.00	0.00
	Min. H _x	5	52219.97	-34457.89	-139.90
	Min. H _z	8	52219.98	-156.29	-34514.73
	Min. M _x	8	-4236531.09	-156.29	-34514.73
	Min. M _z	11	-4225219.71	34386.11	12.00
	Min. Torsion	12	-4394.57	29762.07	17266.77

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	11 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Tower Mast Reaction Summary

Load Combination	Vertical	Shear _x	Shear _z	Overtuning Moment, M _x	Overtuning Moment, M _z	Torque
	lb	lb	lb	lb-ft	lb-ft	lb-ft
Dead Only	52219.97	0.00	0.00	-236.79	822.04	0.00
Dead+Wind 0 deg - No Ice	52219.98	-86.15	-34538.21	-4240737.37	15724.18	835.28
Dead+Wind 30 deg - No Ice	52219.97	17100.94	-29926.43	-3674784.35	-2095844.39	-2710.84
Dead+Wind 60 deg - No Ice	52219.97	29823.91	-17122.01	-2096152.86	-3664315.49	-4069.98
Dead+Wind 90 deg - No Ice	52219.97	34457.89	139.90	23126.55	-4234943.32	-4393.13
Dead+Wind 120 deg - No Ice	52219.97	29861.16	17324.03	2129599.03	-3670987.38	-4659.77
Dead+Wind 150 deg - No Ice	52219.97	17349.88	29916.25	3673358.08	-2137053.52	-3864.17
Dead+Wind 180 deg - No Ice	52219.98	156.29	34514.73	4236531.09	-25122.39	-1314.22
Dead+Wind 210 deg - No Ice	52219.97	-17241.02	29845.56	3661374.31	2119879.03	2423.10
Dead+Wind 240 deg - No Ice	52219.97	-29809.25	17194.58	2107227.35	3663683.58	4005.81
Dead+Wind 270 deg - No Ice	52219.97	-34386.11	-12.00	-3445.81	4225219.71	4353.01
Dead+Wind 300 deg - No Ice	52219.97	-29762.07	-17266.77	-2121025.87	3657130.41	4394.57
Dead+Wind 330 deg - No Ice	52219.97	-17203.39	-29917.95	-3673944.41	2115782.54	3865.37
Dead+Ice+Temp	61836.02	-0.00	-0.00	-1172.03	855.67	0.00
Dead+Wind 0 deg+Ice+Temp	61836.02	-124.71	-27933.73	-3515551.93	18637.60	646.77
Dead+Wind 30 deg+Ice+Temp	61836.02	14243.20	-24137.37	-3036020.86	-1788108.14	34.86
Dead+Wind 60 deg+Ice+Temp	61836.02	24795.15	-13829.57	-1736091.76	-3117034.52	461.27
Dead+Wind 90 deg+Ice+Temp	61836.02	28637.09	71.52	10103.42	-3600270.38	715.03
Dead+Wind 120 deg+Ice+Temp	61836.02	24845.63	14005.01	1761888.31	-3125907.30	-62.20
Dead+Wind 150 deg+Ice+Temp	61836.02	14380.70	24178.09	3040332.16	-1809816.31	-973.36
Dead+Wind 180 deg+Ice+Temp	61836.02	128.10	27880.28	3504687.26	-20421.21	-1104.66
Dead+Wind 210 deg+Ice+Temp	61836.02	-14289.24	24110.13	3029457.79	1795860.28	-269.16
Dead+Wind 240 deg+Ice+Temp	61836.02	-24839.49	13857.46	1739273.89	3124009.30	-440.91
Dead+Wind 270 deg+Ice+Temp	61836.02	-28601.03	-84.26	-14901.46	3594992.94	-607.01
Dead+Wind 300 deg+Ice+Temp	61836.02	-24774.92	-13965.80	-1758298.55	3114637.63	-143.18
Dead+Wind 330 deg+Ice+Temp	61836.02	-14373.21	-24141.44	-3036472.13	1809560.90	839.40
Dead+Wind 0 deg - Service	52219.97	-33.65	-13491.49	-1658749.26	6674.85	325.57
Dead+Wind 30 deg - Service	52219.97	6680.06	-11690.01	-1437396.83	-819169.03	-1070.66
Dead+Wind 60 deg - Service	52219.97	11649.96	-6688.28	-819982.86	-1432608.78	-1601.78
Dead+Wind 90 deg - Service	52219.97	13460.12	54.65	8877.09	-1655798.24	-1726.67
Dead+Wind 120 deg - Service	52219.97	11664.52	6767.20	832741.04	-1435249.56	-1831.90
Dead+Wind 150 deg - Service	52219.97	6777.30	11686.04	1436525.69	-835313.05	-1519.86
Dead+Wind 180 deg - Service	52219.97	61.05	13482.32	1656771.91	-9306.81	-516.23
Dead+Wind 210 deg - Service	52219.97	-6734.77	11658.42	1431817.62	829627.63	956.67
Dead+Wind 240 deg - Service	52219.97	-11644.24	6716.63	823977.16	1433419.32	1577.76
Dead+Wind 270 deg - Service	52219.97	-13432.08	-4.69	-1519.35	1653029.08	1711.71
Dead+Wind 300 deg - Service	52219.97	-11625.81	-6744.83	-829717.31	1430852.35	1727.22
Dead+Wind 330 deg - Service	52219.97	-6720.07	-11686.70	-1437078.38	828022.17	1519.56

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
1	0.00	-52219.97	0.00	0.00	52219.97	0.00	0.000%
2	-86.15	-52219.97	-34538.20	86.15	52219.98	34538.21	0.000%
3	17100.94	-52219.97	-29926.43	-17100.94	52219.97	29926.43	0.000%
4	29823.91	-52219.97	-17122.01	-29823.91	52219.97	17122.01	0.000%
5	34457.89	-52219.97	139.90	-34457.89	52219.97	-139.90	0.000%
6	29861.16	-52219.97	17324.03	-29861.16	52219.97	-17324.03	0.000%
7	17349.88	-52219.97	29916.25	-17349.88	52219.97	-29916.25	0.000%
8	156.29	-52219.97	34514.71	-156.29	52219.98	-34514.73	0.000%
9	-17241.02	-52219.97	29845.56	17241.02	52219.97	-29845.56	0.000%
10	-29809.25	-52219.97	17194.58	29809.25	52219.97	-17194.58	0.000%

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	12 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
11	-34386.11	-52219.97	-12.00	34386.11	52219.97	12.00	0.000%
12	-29762.07	-52219.97	-17266.77	29762.07	52219.97	17266.77	0.000%
13	-17203.39	-52219.97	-29917.95	17203.39	52219.97	29917.95	0.000%
14	0.00	-61836.02	0.00	0.00	61836.02	0.00	0.000%
15	-124.71	-61836.02	-27933.69	124.71	61836.02	27933.73	0.000%
16	14243.20	-61836.02	-24137.37	-14243.20	61836.02	24137.37	0.000%
17	24795.15	-61836.02	-13829.57	-24795.15	61836.02	13829.57	0.000%
18	28637.05	-61836.02	71.52	-28637.09	61836.02	-71.52	0.000%
19	24845.63	-61836.02	14005.01	-24845.63	61836.02	-14005.01	0.000%
20	14380.70	-61836.02	24178.08	-14380.70	61836.02	-24178.09	0.000%
21	128.10	-61836.02	27880.23	-128.10	61836.02	-27880.28	0.000%
22	-14289.24	-61836.02	24110.12	14289.24	61836.02	-24110.13	0.000%
23	-24839.49	-61836.02	13857.46	24839.49	61836.02	-13857.46	0.000%
24	-28600.99	-61836.02	-84.26	28601.03	61836.02	84.26	0.000%
25	-24774.91	-61836.02	-13965.80	24774.92	61836.02	13965.80	0.000%
26	-14373.21	-61836.02	-24141.44	14373.21	61836.02	24141.44	0.000%
27	-33.65	-52219.97	-13491.48	33.65	52219.97	13491.49	0.000%
28	6680.06	-52219.97	-11690.01	-6680.06	52219.97	11690.01	0.000%
29	11649.96	-52219.97	-6688.28	-11649.96	52219.97	6688.28	0.000%
30	13460.11	-52219.97	54.65	-13460.12	52219.97	-54.65	0.000%
31	11664.52	-52219.97	6767.20	-11664.52	52219.97	-6767.20	0.000%
32	6777.30	-52219.97	11686.04	-6777.30	52219.97	-11686.04	0.000%
33	61.05	-52219.97	13482.31	-61.05	52219.97	-13482.32	0.000%
34	-6734.77	-52219.97	11658.42	6734.77	52219.97	-11658.42	0.000%
35	-11644.24	-52219.97	6716.63	11644.24	52219.97	-6716.63	0.000%
36	-13432.07	-52219.97	-4.69	13432.08	52219.97	4.69	0.000%
37	-11625.81	-52219.97	-6744.83	11625.81	52219.97	6744.83	0.000%
38	-6720.07	-52219.97	-11686.70	6720.07	52219.97	11686.70	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.0000001	0.0000001
2	Yes	4	0.0000001	0.00060411
3	Yes	5	0.0000001	0.00088636
4	Yes	5	0.0000001	0.00096291
5	Yes	5	0.0000001	0.00005942
6	Yes	5	0.0000001	0.00090040
7	Yes	5	0.0000001	0.00097070
8	Yes	4	0.0000001	0.00078359
9	Yes	5	0.0000001	0.00095806
10	Yes	5	0.0000001	0.00088464
11	Yes	5	0.0000001	0.00007388
12	Yes	5	0.0000001	0.00096447
13	Yes	5	0.0000001	0.00089947
14	Yes	4	0.0000001	0.00000001
15	Yes	5	0.0000001	0.00035897
16	Yes	6	0.0000001	0.00009513
17	Yes	6	0.0000001	0.00009490
18	Yes	5	0.0000001	0.00036373
19	Yes	6	0.0000001	0.00009765
20	Yes	6	0.0000001	0.00009713
21	Yes	5	0.0000001	0.00035961
22	Yes	6	0.0000001	0.00009587
23	Yes	6	0.0000001	0.00009608

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job	CTHA231A	Page	13 of 16
	Project	81140835	Date	16:47:41 12/11/14
	Client	T-Mobile	Designed by	Brandon Kelsey

24	Yes	5	0.00000001	0.00036080
25	Yes	6	0.00000001	0.00009555
26	Yes	6	0.00000001	0.00009651
27	Yes	4	0.00000001	0.00015048
28	Yes	5	0.00000001	0.00008449
29	Yes	5	0.00000001	0.00010002
30	Yes	4	0.00000001	0.00030659
31	Yes	5	0.00000001	0.00008638
32	Yes	5	0.00000001	0.00010006
33	Yes	4	0.00000001	0.00016372
34	Yes	5	0.00000001	0.00009838
35	Yes	5	0.00000001	0.00008409
36	Yes	4	0.00000001	0.00032705
37	Yes	5	0.00000001	0.00009977
38	Yes	5	0.00000001	0.00008678

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	176 - 130.75	45.925	32	2.3347	0.0067
L2	135.25 - 86.12	26.900	32	2.0017	0.0049
L3	91.87 - 43	11.724	32	1.2759	0.0029
L4	50 - 1	3.281	32	0.6161	0.0010

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
176.00	MF-900B	32	45.925	2.3347	0.0076	29775
170.00	800 10121 w Pipe	32	42.993	2.2988	0.0072	24813
162.00	MF-900B	32	39.114	2.2480	0.0065	10633
160.00	(2) AIR21 B4A/B2P w/ mast pipe	32	38.154	2.2343	0.0064	9304
154.00	VHLP2.5-11	32	35.307	2.1899	0.0059	6766
152.00	VHLP2.5-11	32	34.372	2.1738	0.0057	6202
150.00	APXVSPP18-C-A20 w pipe	32	33.444	2.1569	0.0056	5725
130.00	10' Dipole	32	24.728	1.9309	0.0049	3627
124.00	742 213V01 w pipe	32	22.356	1.8407	0.0047	3600
114.00	LPA-80063-6CF-EDIN-X w pipe	32	18.671	1.6738	0.0044	3554
100.00	MF-900B	32	14.080	1.4221	0.0036	3480
76.00	GPS	32	7.789	1.0070	0.0022	3385
61.00	GPS	32	4.892	0.7743	0.0015	3332

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	176 - 130.75	117.171	7	5.9632	0.0168

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job CTHA231A	Page 14 of 16
	Project 81140835	Date 16:47:41 12/11/14
	Client T-Mobile	Designed by Brandon Kelsey

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L2	135.25 - 86.12	68.685	7	5.1144	0.0122
L3	91.87 - 43	29.959	7	3.2610	0.0075
L4	50 - 1	8.389	7	1.5752	0.0027

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
176.00	MF-900B	7	117.171	5.9632	0.0196	11915
170.00	800 10121 w Pipe	7	109.701	5.8719	0.0184	9929
162.00	MF-900B	7	99.817	5.7425	0.0167	4253
160.00	(2) AIR21 B4A/B2P w/ mast pipe	7	97.370	5.7076	0.0163	3721
154.00	VHLP2.5-11	7	90.115	5.5944	0.0151	2705
152.00	VHLP2.5-11	7	87.731	5.5533	0.0147	2479
150.00	APXVSPP18-C-A20 w pipe	7	85.366	5.5101	0.0143	2288
130.00	10' Dipole	7	63.145	4.9337	0.0128	1444
124.00	742 213V01 w pipe	7	57.097	4.7034	0.0120	1430
114.00	LPA-80063-6CF-EDIN-X w pipe	7	47.694	4.2773	0.0111	1407
100.00	MF-900B	7	35.977	3.6346	0.0092	1375
76.00	GPS	7	19.910	2.5742	0.0056	1331
61.00	GPS	7	12.505	1.9796	0.0039	1307

Base Plate Design Data

Plate Thickness in	Number of Anchor Bolts	Anchor Bolt Size in	Actual Allowable Ratio Bolt Tension lb	Actual Allowable Ratio Compression Bolt	Actual Allowable Stress Plate ksi	Actual Allowable Stress Stiffener ksi	Controlling Condition	Ratio
2.0000	18	2.2500	156536.57 131210.58 1.19	162336.41 217809.56 0.75	41.250 45.000 0.92	28.670 45.000 0.64	Bolt T	1.19 ✓

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P lb	Allow. P _a lb	Ratio P/P _a
L1	176 - 130.75 (1)	TP31.8x21x0.25	45.25	0.00	0.0	39.000	24.1827	-11003.20	943125.00	0.012
L2	130.75 - 86.12 (2)	TP41.82x30.226x0.3125	49.13	0.00	0.0	39.000	39.8244	-22142.50	1553150.00	0.014
L3	86.12 - 43 (3)	TP51.36x39.8381x0.375	48.87	0.00	0.0	39.000	58.7205	-34549.10	2290100.00	0.015

tnxTower EBI Consulting 21 B St Burlington, MA 01803 Phone: (781) 273 - 2500 FAX: (781) 273 - 3311	Job CTHA231A	Page 15 of 16
	Project 81140835	Date 16:47:41 12/11/14
	Client T-Mobile	Designed by Brandon Kelsey

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P lb	Allow. P _a lb	Ratio P P _a
L4	43 - 1 (4)	TP60.5x48.9596x0.4375	49.00	0.00	0.0	39.000	83.4043	-52198.60	3252770.00	0.016

Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M _x lb-ft	Actual f _{bx} ksi	Allow. F _{bx} ksi	Ratio f _{bx} F _{bx}	Actual M _y lb-ft	Actual f _{by} ksi	Allow. F _{by} ksi	Ratio f _{by} F _{by}
L1	176 - 130.75 (1)	TP31.8x21x0.25	432917. 50	-28.576	39.000	0.733	0.00	0.000	39.000	0.000
L2	130.75 - 86.12 (2)	TP41.82x30.226x0.3125	1414483. .33	-43.016	39.000	1.103	0.00	0.000	39.000	0.000
L3	86.12 - 43 (3)	TP51.36x39.8381x0.375	2635508. .33	-44.230	39.000	1.134	0.00	0.000	39.000	0.000
L4	43 - 1 (4)	TP60.5x48.9596x0.4375	4249775. .00	-41.232	39.000	1.057	0.00	0.000	39.000	0.000

Pole Interaction Design Data

Section No.	Elevation ft	Size	Ratio P P _a	Ratio f _{bx} F _{bx}	Ratio f _{by} F _{by}	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	176 - 130.75 (1)	TP31.8x21x0.25	0.012	0.733	0.000	0.744	1.333	H1-3 ✓
L2	130.75 - 86.12 (2)	TP41.82x30.226x0.3125	0.014	1.103	0.000	1.117	1.333	H1-3 ✓
L3	86.12 - 43 (3)	TP51.36x39.8381x0.375	0.015	1.134	0.000	1.149	1.333	H1-3 ✓
L4	43 - 1 (4)	TP60.5x48.9596x0.4375	0.016	1.057	0.000	1.073	1.333	H1-3 ✓

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	SF*P _{allow} lb	% Capacity	Pass Fail
L1	176 - 130.75	Pole	TP31.8x21x0.25	1	-11003.20	1257185.57	55.8	Pass
L2	130.75 - 86.12	Pole	TP41.82x30.226x0.3125	2	-22142.50	2070348.86	83.8	Pass
L3	86.12 - 43	Pole	TP51.36x39.8381x0.375	3	-34549.10	3052703.17	86.2	Pass
L4	43 - 1	Pole	TP60.5x48.9596x0.4375	4	-52198.60	4335942.23	80.5	Pass
Summary								
Pole (L3)							86.2	Pass
Base Plate							89.5	Pass
RATING =							89.5	Pass

EXHIBIT C

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CTHA231A

Berlin FD Tower
1657 Berlin Turnpike
Berlin, CT 06037

September 15, 2014

EBI Project Number: 62144787

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general public allowable limit:	71.02 %

September 15, 2014

T-Mobile USA
Attn: Jason Overbey, RF Manager
35 Griffin Road South
Bloomfield, CT 06002

Emissions Analysis for Site: **CTHA231A – Berlin FD Tower**

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **1657 Berlin Turnpike, Berlin, CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the 700 MHz Band is $467 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the PCS and AWS bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **1657 Berlin Turnpike, Berlin, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 GSM channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel
- 2) 2 UMTS channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 3) 2 LTE channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 4) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.
- 5) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 6) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antennas used in this modeling are the **Ericsson AIR21 B4A/B2P** for 1900 MHz (PCS) and 2100 MHz (AWS) channels and the **Commscope LNX-6515DS-VTM** for 700 MHz channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The **Ericsson AIR21 B4A/B2P** has a maximum gain of **15.9 dBd** at its main lobe. The **Commscope LNX-6515DS-VTM** has a maximum gain of **14.6 dBd** at its main lobe. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antenna mounting height centerline of the proposed antennas is **160 feet** above ground level (AGL).
- 9) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general public threshold limits.



EBI Consulting

environmental | engineering | due diligence

T-Mobile Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	160	Height (AGL):	160	Height (AGL):	160
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	2	Channel Count	2	# PCS Channels:	2
Total TX Power:	120	Total TX Power:	120	# AWS Channels:	120
ERP (W):	1,906.06	ERP (W):	1,906.06	ERP (W):	1,906.06
Antenna A1 MPE%	0.71	Antenna B1 MPE%	0.71	Antenna C1 MPE%	0.71
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P	Make / Model:	Ericsson AIR21 B4A/B2P
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	160	Height (AGL):	160	Height (AGL):	160
Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)	Frequency Bands	1900 MHz(PCS) / 2100 MHz (AWS)
Channel Count	4	Channel Count	4	Channel Count	4
Total TX Power:	120	Total TX Power:	120	Total TX Power:	120
ERP (W):	1,906.06	ERP (W):	1,906.06	ERP (W):	1,906.06
Antenna A2 MPE%	0.71	Antenna B2 MPE%	0.71	Antenna C2 MPE%	0.71
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM	Make / Model:	Commscope LNX-6515DS-VTM
Gain:	14.6 dBd	Gain:	14.6 dBd	Gain:	14.6 dBd
Height (AGL):	160	Height (AGL):	160	Height (AGL):	160
Frequency Bands	700 Mhz	Frequency Bands	700 Mhz	Frequency Bands	700 Mhz
Channel Count	1	Channel Count	1	Channel Count	1
Total TX Power:	30	Total TX Power:	30	Total TX Power:	30
ERP (W):	445.37	ERP (W):	445.37	ERP (W):	445.37
Antenna A3 MPE%	0.28	Antenna B3 MPE%	0.28	Antenna C3 MPE%	0.28

Site Composite MPE%	
Carrier	MPE%
T-Mobile	5.09
Police Channel	0.41 %
Fire Main	0.55 %
Fire Intercity	0.54 %
Highway	0.35 %
Fire Ground	0.05 %
SP Hotline	0.45 %
RAFS	0.11 %
960 Link	0.12 %
Sprint	4.97 %
Clearwire	0.83 %
AT&T	12.23 %
Verizon Wireless	45.32 %
Site Total MPE %:	71.02 %

T-Mobile Sector 1 Total:	1.70 %
T-Mobile Sector 2 Total:	1.70 %
T-Mobile Sector 3 Total:	1.70 %
Site Total:	71.02 %

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector 1:	1.70 %
Sector 2:	1.70 %
Sector 3 :	1.70 %
T-Mobile Total:	5.09 %
Site Total:	71.02 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **71.02%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803`