



...y, CT, 06810
P.: 203.797.1112

ORIGINAL

October 4, 2013

RECEIVED
OCT - 8 2013

CONNECTICUT
SITING COUNCIL

VIA OVERNIGHT COURIER

Connecticut Siting Council
10 Franklin Square
New Britain, Connecticut 06051
Attn: Ms. Melanie Bachman, Acting Executive Director

Re: Sprint Spectrum, L.P. – Exempt Modification
8 Sky Edge Drive, Bethel, Connecticut

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Sprint Spectrum, L.P. ("Sprint"). Sprint is undertaking modifications to certain existing sites in its Connecticut system in order to implement updated technology. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction that constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the First Selectman of the Town of Bethel.

Sprint plans to modify the existing wireless communications facility owned by The Connecticut Light and Power Company and located at 8 Sky Edge Drive, Bethel (coordinates 41°-24'-48.6" N, 73°-24'-3.12" W). Attached are plan and elevation drawings depicting the planned changes, and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration. Also included is a power density report reflecting the modification to Sprint's operations at the site.

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. Sprint will remove the existing six (6) CMDA antennas and add three (3) dual-band panel LTE antennas on existing pipe masts on the existing platform, at the centerline height of the existing antennas of approximately 157.6' AGL. Sprint will also install ~~six (6)~~ ^{nine (9)} RRHs (remote radio heads) on existing canopy posts, also at a centerline height of approximately 157.6' AGL. During an interim period of up to one year, the six (6) existing CDMA antennas will remain. Sprint will also install three (3) hybri-flex

cables along the existing coaxial cable run, and will remove the coaxial cable at the end of the interim period. The proposed modifications will not extend the height of the approximately 150' structure, which is approximately 167.6' when the tower extension is included.


2. Sprint will replace the three (3) existing cabinets with three (3) similar cabinets on the existing concrete pad. Sprint will also add a new surge suppressor, and place a new fiber junction box on new unistruts on a proposed H-frame, all on the existing concrete pad. The existing GPS antenna will be replaced by another GPS antenna. These changes will have no effect on the site boundaries.

3. The proposed changes will not increase the noise level at the existing facility by six decibels or more. The incremental effect of the proposed changes will be negligible.

4. The changes to the facility will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site. As indicated on the attached report prepared by EBI Consulting, Sprint's operations at the site will result in a power density of approximately 19.525%; the combined site operations will result in a total power density of approximately 33.215%.

Please contact me by phone at (203) 610-1071 or by e-mail at mjhowlett@optonline.net with questions concerning this matter. Thank you for your consideration.

Respectfully yours,



Melanie J. Howlett

Attachments

cc: Honorable Matt Knickerbocker, First Selectman, Town of Bethel
Ms. Alvera Chiarella (underlying property owner)



Connecticut
Light & Power

TOWER FOUNDATION IMPROVEMENTS DESIGN

CL&P STRUCT. NO. 10255
SKY EDGE LANE
BETHEL, CT 06801



VICINITY MAP

SITE INFO		
CL&P STRUCT. NO.	10255	
SITE ADDRESS:	SKY EDGE LANE BETHEL, CT 06801	
PROJECT COORDINATES:	LAT: 41°-24'-48.46"N LON.: 73°-24'-3.12W ELEV.: 450' AMSL	
CL&P CONTACT:	ROBERT GRAY 860.665.3175	
CO-LOCATOR INFO		
VERIZON WIRELESS		
CONTACT:	BRIAN RAGOZZINE 860.982.4246	
SITE NAME:	BETHEL NORTH	
ANTENNA & HEIGHT:	167'-6" A.T.B.	
SPRINT		
CONTACT:	MELODY MESSICK 410.782.9495	
SITE NO.:	CT03XC351	
ANTENNA & HEIGHT:	157'-6" A.T.B.	
ENGINEER OF RECORD:	CENITEK ENGINEERING, INC. 63-2 NORTH BRANFORD ROAD BRANFORD, CT 06405	
CONTACT:	CARLO F. CENTORE, PE 203.488.0580, EXT 102	
SHEET INDEX		
SHT. NO.	DESCRIPTION	REV.
T-1	TITLE SHEET	0
N-1	DESIGN BASIS, GENERAL AND SITE NOTES	0
N-2	BORING LOG, EARTHWORK AND FOUNDATION CONSTRUCTION NOTES	0
N-3	CONCRETE CONSTRUCTION NOTES	0
MI-1	MODIFICATION INSPECTION REQUIREMENTS	0
S-1	SITE KEY PLAN	0
S-2	CAISSON COLLAR PLAN	0
S-3	SECTION (BEYOND CAISSON)	0
S-4	SECTION AND DETAIL	2

DESIGNED BY: TIL
DRAWN BY: DEB
CHECKED BY: GED

DATE	BY	DESCRIPTION
2/22/13	TA	ISSUED FOR CONSTRUCTION
3/22/13	TA	ISSUED FOR CONSTRUCTION
4/17/13	TA	ISSUED FOR CONSTRUCTION
5/17/13	TA	ISSUED FOR CONSTRUCTION
6/17/13	TA	ISSUED FOR CONSTRUCTION
7/17/13	TA	ISSUED FOR CONSTRUCTION
8/17/13	TA	ISSUED FOR CONSTRUCTION
9/17/13	TA	ISSUED FOR CONSTRUCTION
10/17/13	TA	ISSUED FOR CONSTRUCTION
11/17/13	TA	ISSUED FOR CONSTRUCTION
12/17/13	TA	ISSUED FOR CONSTRUCTION

www.CentekEngineering.com

10255 Sky Edge Lane
Bethel, CT 06801

10255 Sky Edge Lane
Bethel, CT 06801

10255 Sky Edge Lane
Bethel, CT 06801

TOWER FOUNDATION
IMPROVEMENTS DESIGN
CL&P STRUCTURE NO. 10255

SKY EDGE LANE
BETHEL, CT 06801

TITLE SHEET

SHEET NO. T-1

Sheet No. 1 of 2

DESIGN BASIS

1. GOVERNING CODE: 2003 INTERNATIONAL BUILDING CODE AS MODIFIED BY THE 2005 CT STATE BUILDING CODE AND 2009 AMENDMENTS.

2. TIA/EIA-222-F-1996, ASCE MANUAL NO. 72 - "DESIGN OF STEEL TRANSMISSION POLE STRUCTURES SECOND EDITION", NESC C2-2007 AND NORTHEAST UTILITIES DESIGN CRITERIA.

3. DESIGN CRITERIA

WIND LOAD: (PCS MAST)
BASIC WIND SPEED (V) = 85 MPH (FASTEST MILE); BASED ON TIA/EIA-222F AND NU MAST DESIGN CRITERIA EXCEPTION 1.

WIND LOAD: (UTILITY POLE & FOUNDATION)
BASIC WIND SPEED (V) = 110 MPH (3-SECOND GUST) BASED ON NESC C2-2007, SECTION 25 RULE 250C.

GENERAL NOTES

1. REFER TO STRUCTURAL ANALYSIS AND REINFORCEMENT DESIGN PREPARED BY CENTEK ENGINEERING, INC., FOR VERIZON WIRELESS, REVISION #0, DATED 2/14/13.

2. TOWER GEOMETRY AND STRUCTURE MEMBER SIZES WERE OBTAINED FROM THE ORIGINAL TOWER DESIGN DOCUMENTS PREPARED BY AMERICAN POLE STRUCTURES COMBUSTION ENGINEERING, INC., CUST. ORDER NO. CLP-409642, CIRCA 1976/1977. CAISSON DESIGN INFORMATION WAS OBTAINED FROM THE ORIGINAL DESIGN DOCUMENTS PREPARED BY NORTHEAST UTILITIES SERVICE CO., DWG. NO. 01143-60001 SH. 3, DATED MARCH, 1977.

3. THE CONTRACTOR SHALL LIMIT THE DURATION OF THE FOUNDATION REINFORCEMENT WORK. THE EXISTING CAISSON WITHIN THE SHOWN LIMITS IS STABLE FOR WIND SPEEDS LESS THAN 50 MPH WITHOUT ICE LOADING. IF HIGHER WIND SPEED OR ICE EVENT IS EXPECTED, THE EXCAVATION AREA SHALL BE FILLED WITH COMPACT FILL MATERIAL.

4. THE TOWER STRUCTURE IS DESIGNED TO BE SELF-SUPPORTING AND STABLE AFTER REINFORCEMENTS ARE COMPLETE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURE & SEQUENCE AND TO INSURE THE SAFETY OF THE TOWER STRUCTURE AND ITS COMPONENT PARTS DURING ERECTION. THIS INCLUDES PROVIDING AND MAINTAINING ADEQUATE SHORING, BRACING, UNDERPINNING, TEMPORARY ANCHORS, GUYING, BARRICADES, ETC. AS MAY BE REQUIRED FOR THE PROTECTION OF EXISTING PROPERTY, CONSTRUCTION WORKERS, AND FOR PUBLIC SAFETY. MAINTAIN EXISTING SITE OPERATIONS AND COORDINATE WORK WITH TOWER OWNER.

5. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE GOVERNING BUILDING CODE.

6. DRAWINGS INDICATE THE MINIMUM STANDARDS, BUT IF ANY WORK SHOULD BE INDICATED TO BE SUBSTANDARD TO ANY ORDINANCES, LAWS, CODES, RULES, OR REGULATIONS BEARING ON THE WORK, THE CONTRACTOR SHALL INCLUDE IN HIS SCOPE OF WORK AND SHALL EXECUTE THE WORK CORRECTLY IN ACCORDANCE WITH SUCH ORDINANCES, LAWS, CODES, RULES OR REGULATIONS WITH NO INCREASE IN COSTS.

7. BEFORE BEGINNING THE WORK, THE CONTRACTOR IS RESPONSIBLE FOR MAKING SUCH INVESTIGATIONS CONCERNING PHYSICAL CONDITIONS (SURFACE AND SUBSURFACE) AT OR CONTIGUOUS TO THE SITE WHICH MAY AFFECT PERFORMANCE AND COST OF THE WORK. THIS INCLUDES VERIFYING ALL DIMENSIONS, ELEVATIONS, ANGLES, AND EXISTING CONDITIONS AT THE SITE, PRIOR TO FABRICATION AND/OR INSTALLATION OF ANY WORK IN THE CONTRACT AREA. CONTRACTOR SHALL TAKE FIELD MEASUREMENTS NECESSARY TO ASSURE PROPER FIT OF ALL FINISHED WORK.

8. FOUNDATION REINFORCEMENTS SHALL BE CONDUCTED BY FIELD CREWS EXPERIENCED IN THE ASSEMBLY AND ERECTION OF TRANSMISSION STRUCTURES. ALL SAFETY PROCEDURES, RIGGING AND ERECTION METHODS SHALL BE STANDARD TO THE INDUSTRY AND IN COMPLIANCE WITH OSHA.

9. EXISTING COAXIAL CABLES AND ALL ACCESSORIES SHALL BE RELOCATED AS NECESSARY AND REINSTALLED BY THE CONTRACTOR WITHOUT INTERRUPTION IN SERVICE WHERE THEY ARE IN CONFLICT WITH THE TOWER FOUNDATION REINFORCEMENT WORK.

10. IF ANY FIELD CONDITIONS EXIST WHICH PRECLUDE COMPLIANCE WITH THE DRAWINGS, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER AND SHALL PROCEED WITH AFFECTED WORK AFTER CONFLICT IS SATISFACTORILY RESOLVED.

11. ALL DAMAGE CAUSED TO ANY EXISTING STRUCTURE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR WILL BE HELD LIABLE FOR ALL REPAIRS REQUIRED FOR EXISTING STRUCTURES IF DAMAGED DURING CONSTRUCTION ACTIVITIES.

12. NO DRILLING WELDING OR TAPING IS PERMITTED ON CL&P OWNED EQUIPMENT.

SITE NOTES

1. THE CONTRACTOR SHALL CALL UTILITIES PRIOR TO THE START OF CONSTRUCTION.

2. ACTIVE EXISTING UTILITIES, WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES. THE ENGINEER SHALL BE NOTIFIED IMMEDIATELY, PRIOR TO PROCEEDING, SHOULD ANY UNCOVERED EXISTING UTILITY PRECLUDE COMPLETION OF THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

3. ALL RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED OFF SITE AND BE LEGALLY DISPOSED, AT NO ADDITIONAL COST.

4. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE EQUIPMENT AND TOWER AREAS.





5. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND, FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

6. THE SUBGRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.

7. THE AREAS OF THE COMPOUND DISTURBED BY THE WORK SHALL BE RETURNED TO THEIR ORIGINAL CONDITION.

8. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.

DESIGNED BY: JAL	DATE: 02/04/13	SCALE: AS SHOWN	JOB NO. 12007.0005
DRAWN BY: JAL	DATE: 02/04/13	SCALE: AS SHOWN	JOB NO. 12007.0005
CHECKED BY: JAL	DATE: 02/04/13	SCALE: AS SHOWN	JOB NO. 12007.0005
APPROVED BY: JAL	DATE: 02/04/13	SCALE: AS SHOWN	JOB NO. 12007.0005



VERIZON WIRELESS
TOWER FOUNDATION
IMPROVEMENTS DESIGN
CL&P STRUCTURE NO. 10255

SKY EDGE LANE
BETHEL, CT 06801

DATE: 02/04/13
SCALE: AS SHOWN
JOB NO. 12007.0005

DESIGN BASIS,
GENERAL AND
SITE NOTES

SHEET NO. 2
N-1
OF 3

EARTHWORK NOTES

1. COMPACTED GRAVEL FILL SHALL BE FURNISHED AND PLACED AS A FOUNDATION FOR STRUCTURES, WHERE SHOWN ON THE CONTRACT DRAWINGS OR DIRECTED BY THE ENGINEER.
2. CRUSHED STONE FILL SHALL BE PLACED IN 12" MAX. LIFTS AND CONSOLIDATED USING A HAND OPERATED VIBRATORY PLATE COMPACTOR WITH A MINIMUM OF 2 PASSES OF COMPACTOR PER LIFT.
3. COMPACTED GRAVEL FILL TO BE WELL GRADED BANK RUN GRAVEL MEETING THE FOLLOWING GRADATION REQUIREMENTS:

SIEVE DESIGNATION	% PASSING
1 1/2"	100
No. 4	40-70
No. 100	5-20
No. 200	4-8
4. CRUSHED STONE TO BE UNIFORMLY GRADED, CLEAN, HARD PROCESS AGGREGATE MEETING THE FOLLOWING GRADATION REQUIREMENTS:

SIEVE DESIGNATION	% PASSING
1"	100
3/4"	90-100
1/2"	0-15
3/8"	0-5
5. SELECT BACKFILL FOR FOUNDATION WALLS SHALL BE FREE OF ORGANIC MATERIAL, TOPSOIL, DEBRIS AND BOULDERS LARGER THAN 6".
6. GRAVEL AND GRANULAR FILL SHALL BE INSTALLED IN 10" MAX. LIFTS, COMPACTED TO 95% MIN. AT MAX. DRY DENSITY.
7. NON WOVEN GEOTEXTILE FOR SEPARATION PURPOSES SHALL BE MIRAFI 140N, OR ENGINEER APPROVED EQUAL.

FOUNDATION CONSTRUCTION NOTES

1. ALL FOOTINGS SHALL BE PLACED ON SUITABLE, COMPACTED SOIL HAVING ADEQUATE BEARING CAPACITY AND FREE OF ORGANIC CONTENT, CLAY, OR OTHER UNSUITABLE MATERIAL. ADDITIONAL EXCAVATION MAY BE REQUIRED BELOW FOOTING ELEVATIONS INDICATED IF UNSUITABLE MATERIAL IS ENCOUNTERED.
2. SUBGRADE PREPARATION: IF UNSUITABLE SOIL IS ENCOUNTERED, REMOVE ALL UNSUITABLE MATERIALS FROM BELOW PROPOSED STRUCTURE FOUNDATIONS AND COMPACT EXPOSED SOIL SURFACES. PLACE AND COMPACT APPROVED GRAVEL FILL. PLACEMENT OF ALL COMPACTED FILL MUST BE UNDER SUPERVISION OF AN APPROVED TESTING LABORATORY. FILL SHALL BE COMPACTED IN LAYERS NOT TO EXCEED 10" BEFORE COMPACTON. DETERMINE MAXIMUM DRY DENSITY IN ACCORDANCE WITH ASTM D1557-70 AND MAKE ONE (1) FIELD DENSITY TEST IN ACCORDANCE WITH ASTM D2167-66 FOR EACH 50 CUBIC YARDS OF COMPACTED FILL, BUT NOT LESS THAN ONE (1) PER LAYER, TO INSURE COMPACTON TO 95% OF MAX. DRY DENSITY.
3. ALL SOIL SURROUNDING AND UNDER ALL FOOTINGS SHALL BE KEPT REASONABLY DRY AND PROTECTED FROM FREEZING AND FROST ACTION DURING THE COURSE OF CONSTRUCTION.
4. WHERE GROUNDWATER IS ENCOUNTERED, DEWATERING SHALL BE ACCOMPLISHED CONTINUOUSLY AND COMPLETELY DURING FOUNDATION CONSTRUCTION. PROVIDE CRUSHED STONE AS REQUIRED TO STABILIZE FOOTING SUBGRADE.
5. ALL FOOTINGS ARE TO REST ON FIRM SOIL, REGARDLESS OF ELEVATIONS SHOWN ON THE DRAWINGS, BUT IN NO CASE MAY FOOTING ELEVATIONS BE HIGHER THAN INDICATED ON THE FOUNDATION PLAN, UNLESS SPECIFICALLY DIRECTED BY THE ENGINEER.
6. FOUNDATION WATERPROOFING AND DAMPPROOFING SHALL COMPLY WITH BUILDING CODE REQUIREMENTS UNLESS A MORE SUBSTANTIAL SYSTEM IS INDICATED OR SPECIFIED.

CLARENCE BELT ASSOC., INC.
 100 NEW LONDON TURNPIKE
 CLAYTON, CT 06415

PROJECT: "BORING LOG"

CLIENT: MUSCO
 LOCATION: 1111 PLANTATION HILL, TRANE-11
 NEW MILFORD, CONNECTICUT

BORING NO. 77
 DATE: 10/2/25
 LINE & STA. 10+25.5
 GR. ELEV. 100.00

BORING NO. 77
 DATE: 10/2/25
 LINE & STA. 10+25.5
 GR. ELEV. 100.00

DEPTH (FEET)	SOIL DESCRIPTION	PER. (FEET)	BLDG. NO.
0-10	BR. FINE-GRA. SAND & GRAVEL	2-5-3	
10-15	BR. FINE SAND	7-35-19	
15-20	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
20-25	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
25-30	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
30-35	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
35-40	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
40-45	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
45-50	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
50-55	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
55-60	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
60-65	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
65-70	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
70-75	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
75-80	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
80-85	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
85-90	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
90-95	BR. FINE-GRA. SAND & GRAVEL	7-35-19	
95-100	BR. FINE-GRA. SAND & GRAVEL	7-35-19	

1. COL. A - TESTED SPEC. 2. COL. B - TESTED SPEC. 3. COL. C - TESTED SPEC. 4. COL. D - TESTED SPEC. 5. COL. E - TESTED SPEC.

DATE: 1/19/77
 DRILLER: BARACCO

REFUSAL AT 27.0' WATER AT 17.0' 0 HRS.

AND - 10 IN. DIA. TRACE - 10 IN. DIA.

DESIGNED BY: JAL
 DRAWN BY: JED
 CHECKED BY: JED
 DATE: 02/04/13
 SCALE: AS SHOWN
 JOB NO.: 10001.0000

BORING LOG,
 EARTHWORK AND
 CONSTRUCTION
 NOTES

SHEET NO. 2
 N-2

VERIZON WIRELESS
 TOWER FOUNDATION
 IMPROVEMENTS DESIGN
 CL&P STRUCTURE NO. 10255
 SKY EDGE LANE
 BETHEL, CT 06801

www.verizonwireless.com
 10001.0000
 10001.0000
 10001.0000
 10001.0000

1. CONCRETE CONSTRUCTION SHALL CONFORM TO THE FOLLOWING STANDARDS:
 - ACI 211 – STANDARD PRACTICE FOR SELECTING PROPORTIONS FOR NORMAL AND HEAVYWEIGHT CONCRETE.
 - ACI 301 – SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
 - ACI 302 – GUIDE FOR CONCRETE FLOOR AND SLAB CONSTRUCTION
 - ACI 304 – RECOMMENDED PRACTICE FOR MEASURING, MIXING, TRANSPORTING, AND PLACING CONCRETE.
 - ACI 306.1 – STANDARD SPECIFICATION FOR COLD WEATHER CONCRETING
 - ACI 318 – BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE.
2. CONCRETE SHALL BE AIR ENTRAINED AND SHALL DEVELOP COMPRESSIVE STRENGTH IN 28 DAYS AS FOLLOWS:
 - ALL CONCRETE 3,500 PSI
3. REINFORCING STEEL SHALL BE 60,000 PSI YIELD STRENGTH.
4. ALL DETAILING, FABRICATION, AND ERECTION OF REINFORCING BARS, UNLESS OTHERWISE NOTED, MUST FOLLOW THE LATEST ACI CODE AND LATEST ACI "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES".
5. CONCRETE COVER OVER REINFORCING SHALL BE 3 INCHES.
6. NO STEEL WIRE, METAL FORM TIES, OR ANY OTHER METAL SHALL REMAIN WITHIN THE REQUIRED COVER OF ANY CONCRETE SURFACE.
7. ALL REINFORCEMENT SHALL BE CONTINUOUS. SPLICES WILL NOT BE ALLOWED.
8. NO TACK WELDING OF REINFORCING WILL BE PERMITTED.
9. NO CALCIUM CHLORIDE OR ADMIXTURES CONTAINING MORE THAN 1 % CHLORIDE BY WEIGHT OF ADMIXTURE SHALL BE USED IN THE CONCRETE.
10. TOP OF FOOTING SURFACES SHALL RECEIVE A UNIFORM FLOAT FINISH. CURE FOOTING SURFACE WITH SONNEBORN KURE-N-SEAL WB OR APPROVED EQUAL, APPLIED AS RECOMMENDED BY MANUFACTURER.

15. FOUR COPIES OF ALL INSPECTION TEST REPORTS SHALL BE SUBMITTED TO THE OWNER WITHIN TEN (10) WORKING DAYS OF THE DATE OF INSPECTION.

[illegible]

[illegible][illegible]

MODIFICATION INSPECTOR (MI)


1. THE MI SHALL CONTACT THE GC UPON AUTHORIZATION BY THE CLIENT TO:
 - REVIEW THE MODIFICATION INSPECTION REPORT REQUIREMENTS.
 - WORK WITH THE GC IN DEVELOPMENT OF A SCHEDULE FOR ON-SITE INSPECTIONS.
 - DISCUSS CRITICAL INSPECTIONS AND PROJECT CONCERNS.
 2. THE MI IS RESPONSIBLE FOR COLLECTION OF ALL INSPECTION AND TEST REPORTS, REVIEWING REPORTS FOR ADHERENCE TO THE CONTRACT DOCUMENTS, CONDUCTING ON-SITE INSPECTIONS AND COMPILATION & SUBMISSION OF THE MODIFICATION INSPECTION REPORT TO THE CLIENT AND THE EOR.
- GENERAL CONTRACTOR (GC)**
1. THE GC IS REQUIRED TO CONTACT THE GC UPON AUTHORIZATION TO PROCEED WITH CONSTRUCTION BY THE CLIENT TO:
 - REVIEW THE MODIFICATION INSPECTION REPORT REQUIREMENTS.
 - WORK WITH THE MI IN DEVELOPMENT OF A SCHEDULE FOR ON-SITE INSPECTIONS.
 - DISCUSS CRITICAL INSPECTIONS AND PROJECT CONCERNS.
 2. THE GC IS RESPONSIBLE FOR COORDINATING AND SCHEDULING IN ADVANCE ALL REQUIRED INSPECTIONS AND TESTS WITH THE MI.

CORRECTION OF FAILING MODIFICATION INSPECTION

1. SHOULD THE STRUCTURAL MODIFICATION NOT COMPLY WITH THE REQUIREMENTS OF THE CONSTRUCTION DOCUMENTS, THE GC SHALL WORK WITH THE MODIFICATION INSPECTOR IN A VIABLE REMEDIATION PLAN AS FOLLOWS:
 - CORRECT ALL DEFICIENCIES TO COMPLY WITH THE CONTRACT DOCUMENTS AND COORDINATE WITH THE MI FOR A FOLLOW UP INSPECTION.
 - WITH CLIENT AUTHORIZATION, THE GC MAY WORK WITH THE EOR TO REANALYZE THE MODIFICATION USING THE AS-BUILT CONDITION.

REQUIRED PHOTOGRAPHS

1. THE GC AND MI SHALL AT MINIMUM PHOTO DOCUMENT THE FOLLOWING FOR INCLUSION IN THE MODIFICATION INSPECTION REPORT:
 - PRE-CONSTRUCTION: GENERAL CONDITION OF THE SITE.
 - DURING CONSTRUCTION: RAW MATERIALS, CRITICAL DETAILS, WELD PREPARATION, BOLT INSTALLATION & TORQUE; FINAL INSTALLED CONDITION & SURFACE COATING REPAIRS.
 - POST-CONSTRUCTION: FINAL CONDITION OF THE SITE



DESIGNED BY: JAL
DRAWN BY: ESD
CHECKED BY: CFC

REV	DATE	DESCRIPTION
1	07/18/13	ISSUED FOR CONSTRUCTION
2	07/18/13	ISSUED FOR CONSTRUCTION
3	07/18/13	ISSUED FOR CONSTRUCTION
4	07/18/13	ISSUED FOR CONSTRUCTION
5	07/18/13	ISSUED FOR CONSTRUCTION
6	07/18/13	ISSUED FOR CONSTRUCTION
7	07/18/13	ISSUED FOR CONSTRUCTION
8	07/18/13	ISSUED FOR CONSTRUCTION
9	07/18/13	ISSUED FOR CONSTRUCTION
10	07/18/13	ISSUED FOR CONSTRUCTION

CEN TEK
Engineering & Construction
www.centeek.com

2201 4th Street
Bethel, CT 06801
Phone: 203.261.1234
Fax: 203.261.1235


VERIZON WIRELESS
TOWER FOUNDATION
CL&P STRUCTURE NO. 10255

SKY EDGE LANE
BETHEL, CT 06801



DATE: 07/18/13
SCALE: AS SHOWN
JOB NO. 12001.C085

SECTION
(CAISSON BEYOND)

SHEET NO. **S-3**
OF 2



INTERNATIONAL BLVD, SUITE 800
HAMMATH, NJ 07495
P: 800-357-7641



PAUL GIONFRIDDO P. E.

THIS DOCUMENT IS THE DESIGN PROPERTY AND COPYRIGHT OF SALIENT ASSOCIATES, LLC AND FOR THE EXCLUSIVE USE BY THE TITLE CLIENT. DUPLICATION OR USE WITHOUT THE EXPRESS WRITTEN CONSENT OF THE CREATOR IS STRICTLY PROHIBITED.

DRAWING SCALES ARE INTENDED FOR 24"x36" SIZE PRINTED MEDIA ONLY. ALL OTHER PRINTED SIZES ARE DESIGNED "NOT TO SCALE".

SUBMITTALS				
NO	DATE	DESCRIPTION	BY	
1	4-10-72	PRELIMINARY	PJP	
2	5-10-72	REVISIONS PER COMMENTS	JWP	
3	05-24-73	ISSUED AS FINAL	FS	

SITE NUMBER:
CT03XC351

SITE NAME:
BETHEL CL+P
POLE 10255

SITE ADDRESS:
503 KY EDGE LANE
BETHEL, CT 06801

COMMON LAW

VALIENT PROJ. NO:	SHEET NO
-------------------	----------

ATB


BY:

ANTENNA CONFIGURATION NOTE

ALL EXISTING COMA ANTENNAS TO BE REMOVED, REPLACED WITH NEW COMA VISION ANTENNAS FOR FINAL CONFIGURATION. ANTENNA SEPARATION TO BE FIELD VERIFIED BY THE GENERAL CONTRACTOR.

NOTES:

SEE UTILITY; FCGE NOTED ON GN-2



COMPOUND Q-42

SCALE : 3/6 : 1-0



**Northeast
Utilities System**

107 Selden Street, Berlin, CT 06037

Northeast Utilities Service Company
P.O. Box 270
Hartford, CT 06141-0270
(203) 665-5000

September 19, 2013

Ms. Jennifer Gaudet
HPC Development

Sprint,
1 International Blvd.
Suite 300
Mahwah NJ
07495

RE: Sprint Antenna Site, CT-03XC351, 8 Sky Edge Lane, Bethel CT, structure 10255.

Dear Ms. Gaudet:

Based on our reviews of the site drawings, the structural analysis and foundation reinforcement provided by Centek Engineering, we have reviewed for acceptance this modification.

Since there are no outstanding structural issues to resolve at this time please contact Mr. O'Brien (860-665-6987) to resolve any lease issues; once the lease amendment is secured you may then contact Mr. John Landry directly (860-665-5425) to begin the construction arrangements.

Sincerely,

Robert Gray

Transmission Line Engineering

REF: NV_CT03XC351_Issued as Final CD_V3_PE S&S(2).pdf
CL-P Pole 10255 Foundation Improvements Design - Rev-2 04.1.13(2).pdf
12047.CO3 - CT03XC351.pdf

Structural Analysis of PCS
Structure and CL&P Pole


Sprint Site Ref: CT03XC351

CL&P Structure No. 10255
150' Electric Transmission Pole

Sky Edge Lane
Bethel, CT

CEN TEK Project No. 12047.CO3

Date: February 18, 2013



Prepared for:
Sprint Nextel
8 Airline Drive, Suite 105
Albany, NY 12205

Table of Contents

SECTION 1 - REPORT

- INTRODUCTION
- PRIMARY ASSUMPTIONS USED IN THE ANALYSIS
- ANALYSIS
- DESIGN BASIS
- RESULTS
- CONCLUSION AND RECOMMENDATIONS

SECTION 2 - CONDITIONS & SOFTWARE

- STANDARD ENGINEERING CONDITIONS
- GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAMS
 - RISA 3-D
 - PLS POLE

SECTION 3 - DESIGN CRITERIA

- CRITERIA FOR DESIGN OF PCS FACILITIES ON OR EXTENDING ABOVE METAL ELECTRIC TRANSMISSION TOWERS
- NU DESIGN CRITERIA TABLE
- PCS SHAPE FACTOR CRITERIA
- WIRE LOADS SHEET

SECTION 4 - DRAWINGS

- EL-1 TOWER ELEVATION
- FP-1 FEEDLINE PLAN

SECTION 5 - EIA/TIA-222-F LOAD CALCULATIONS FOR PCS STRUCTURE ANALYSIS

- EQUIPMENT WIND & ICE LOAD

SECTION 6 - PCS STRUCTURE ANALYSIS PER EIA/TIA-222F

- LOAD CASES AND COMBINATIONS (TIA/EIA LOADING)
- RISA 3-D ANALYSIS REPORT

SECTION 7 - NECS/NU LOAD CALCULATIONS FOR OBTAINING PCS STRUCTURE REACTIONS APPLIED TO UTILITY STRUCTURE

- WIND LOAD

**SECTION 8 - PCS STRUCTURE ANALYSIS PER NESC/NU FOR
OBTAINING PCS STRUCTURE REACTIONS APPLIED TO
UTILITY STRUCTURE**

- LOAD CASES AND COMBINATIONS (NESC/NU LOADING)
- RISA 3-D ANALYSIS REPORT

**SECTION 9 - PLS TOWER RESULTS FROM MAST REACTIONS
CALCULATED IN RISA WITH NESC/NU CRITERIA**

- COAX CABLE LOAD ON CL&P POLE CALCULATION
- PLS REPORT
- ANCHOR BOLT ANALYSIS
- FOUNDATION ANALYSIS

SECTION 10 - REFERENCE MATERIAL

- EQUIPMENT CUT SHEETS

Introduction

The purpose of this report is to analyze the existing PCS mast and 150' CL&P pole located on Sky Edge Lane Bethel, CT for the proposed antenna and equipment upgrade by Sprint.

The proposed loads consist of the following:

- VERIZON (EXISTING/RESERVED):

Antennas: Three (3) Antel BXA-70063/6CF panel antennas, three (3) Andrew DBXNH-6565A-VTM panel antennas and six (6) RFS FD9R6004/2C-3L diplexers mounted on three (3) dual standoff mounts to a 12-in Sch. 80 pipe mast with RAD center elevation of 167-ft 6-in above tower base plate.

Coax Cables: Twelve (12) 1-5/8" Ø coax cables running on the outside of the tower as indicated in section 4 of this report.

- SPRINT (Existing to Remain):

Coax Cables: Six (6) 1-5/8" Ø coax cables running on the outside of the existing tower as indicated in section 4 of this report.

- SPRINT (Existing to Remove):

Antennas: Six (6) Andrew DB980F65E-M panel antennas mounted on an existing 13-ft low profile platform to a 12-in Sch. 80 pipe mast with RAD center elevation of 157-ft 6-in above tower base plate.

- SPRINT (PROPOSED):

Antennas: Three (3) RFS APXVSP18-C panel antennas mounted on an existing 13-ft low profile platform to a 12-in Sch. 80 pipe mast with RAD center elevation of 157-ft 6-in above tower base plate.

Coax Cables: Twelve (12) 1-5/8" Ø coax cables running on the outside of the existing tower as indicated in section 4 of this report.

Primary assumptions used in the analysis

- Allowable steel stresses are defined by AISC-ASD 9th edition for design of the PCS Mast and antenna supporting elements.
- ASCE Manual No. 72, "Design of Steel Transmission Pole Structures Second Edition", defines allowable steel stresses for evaluation of the CL&P utility pole.
- All utility pole members are adequately protected to prevent corrosion of steel members.
- All proposed antenna mounts are modeled as listed above.
- Pipe mast will be properly installed and maintained.
- No residual stresses exist due to incorrect pole erection.
- All bolts are appropriately tightened providing the necessary connection continuity.
- All welds conform to the requirements of AWS D1.1.
- Pipe mast and utility pole will be in plumb condition.
- Utility pole was properly installed and maintained and all members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
- Any deviation from the analyzed loading will require a new analysis for verification of structural adequacy.
- Existing mast information was taken from URS Corp. construction drawings project no. 38929204 dated 1/15/2007.

A n a l y s i s

Structural analysis of the existing *PCS Mast Structure* was independently completed using the current version of RISA-3D computer program licensed to CEN TEK engineering, Inc.

The existing mast consisting of a 33-ft long pipe 12-in SCH. 80 (O.D. = 12.8-in) connected at two points to the existing pole was analyzed for its ability to resist loads prescribed by the TIA/EIA standard. Section 5 of this report details these gravity and lateral wind loads. NESC prescribed loads were applied to the existing mast structure in order to obtain reactions needed for analyzing the CL&P pole structure. These loads are developed in Section 7 of this report. Load cases and combinations used in RISA-3D for TIA/EIA loading and for NESC/NU loading are listed in report Sections 6 and 8, respectively.

An envelope solution was first made to determine maximum and minimum forces, stresses, and deflections to confirm the selected section as adequate. Additional analyses were then made to determine the NESC forces to be applied to the CL&P pole structure.

The RISA-3D program contains a library of all AISC shapes and corresponding section properties are computed and applied directly within the program. The program's Steel Code Check option was also utilized. The forces calculated in RISA-3D using NESC guidelines were then applied to the CL&P pole using PLS-Pole. Maximum usage for the pole was calculated considering the additional forces from the mast and associated appurtenances.

D e s i g n B a s i s

Our analysis was performed in accordance with TIA/EIA-222-F-1996, ASCE Manual No. 72 – "Design of Steel Transmission Pole Structures Second Edition", NESC C2-2007 and Northeast Utilities Design Criteria.

The CL&P pole structure, considering existing and future conductor and shield wire loading, with the pcs antenna mast was analyzed under two conditions:

▪ UTILITY POLE ANALYSIS

The purpose of this analysis is to determine the adequacy of the existing utility pole to support the proposed antenna loads. The loading and design requirements were analyzed in accordance with the NU Design Criteria Table, NESC C2-2007 ~ Construction Grade B, and ASCE Manual No. 72.

Load cases considered:

Load Case 1: NESC Heavy

Wind Pressure.....	4.0 psf
Radial Ice Thickness.....	0.5"
Vertical Overload Capacity Factor.....	1.50
Wind Overload Capacity Factor.....	2.50
Wire Tension Overload Capacity Factor.....	1.65

Load Case 2: NESC Extreme

Wind Speed.....	100 mph ⁽¹⁾
Radial Ice Thickness.....	0"

Note 1: NESC C2-2007, Section 25, Rule 250C: Extreme Wind Loading, 1.25 x Gust Response Factor (wind speed: 3-second gust)

▪ PCS MAST ANALYSIS

The PCS mast, appurtenances and connections to the utility pole were analyzed and designed in accordance with the NU Design Criteria Table, TIA/EIA-222-F, and AISC-ASD standards.

Load cases considered:

Load Case 1:

Wind Speed..... 85 mph ⁽²⁾
 Radial Ice Thickness..... 0"

Load Case 2:

Wind Pressure..... 75% of 85 mph wind pressure
 Radial Ice Thickness..... 0.5"

| Note 2: Per NU Mast Design Criteria Exception 1.

R e s u l t s

PCS MAST

The proposed mast was determined to be structurally adequate.

Member	Stress Ratio (% of capacity)	Result
12" Sch. 80 Pipe	73.5% ⁽¹⁾	PASS
Flange Plate	71.3% ⁽²⁾	PASS
PCS Mast to Pole Connection Bolts	49.6% ⁽²⁾	PASS

Note 1 – 1/3 Increase in allowable stress used for mast.

Note 2 – 1/3 increase in allowable stress not used for mast connection.

UTILITY POLE

This analysis finds that the subject utility pole is adequate to support the proposed antenna mast and related appurtenances. The pole stresses meet the requirements set forth by the ASCE Manual No. 72, "Design of Steel Transmission Pole Structures Second Edition", for the applied NESC Heavy and Hi-Wind load cases. The detailed analysis results are provided in Section 9 of this report. The analysis results are summarized as follows:

A maximum usage of **97.5%** occurs in the utility pole base plate under the **NESC Extreme** loading condition.

POLE SECTION:

The utility pole was found to be within allowable limits.

Tower Section	Elevation	Stress Ratio (% of capacity)	Result
Tube Number 3	0' -51.2' (AGL)	95.68%	PASS

BASE PLATE:

The base plate was found to be within allowable limits from the PLS output based on 24 bend lines.

Tower Component	Design Limit	Stress Ratio (percentage of capacity)	Result
Base Plate	Bending	97.5%	PASS

▪ **FOUNDATION AND ANCHORS**

The existing foundation consists of a 8-ft Ø x 20.5-ft long reinforced concrete caisson. The base of the tower is connected to the foundation by means of (24) 2.25"Ø, ASTM A615-75 anchor bolts embedded approximately 7.5-ft into the concrete foundation structure. Foundation information was obtained from NUSCO drawing # 01143-60001 Sh. 3. Reinforcement to the existing foundation with a proposed 24-ft square by 4-ft deep reinforced concrete mat installed at the periphery of the existing caisson is required prior to the Sprint antenna upgrade.

Review of the foundation and anchor design consisted of verification of applied loads obtained from the tower design calculations and code checks of allowable stresses:

BASE REACTIONS:

From PLS-Pole analysis of CL&P pole based on NESC/NU prescribed loads.

Load Case	Shear	Axial	Moment
NESC Heavy Wind	33.73 kips	121.21 kips	4170.18 ft-kips
NESC Extreme Wind	53.58 kips	59.23 kips	6039.79 ft-kips

Note 1 – 10% increase applied to tower base reactions per OTRM 051

ANCHOR BOLTS:

The anchor bolts were found to be within allowable limits.

Tower Component	Design Limit	Stress Ratio (% of capacity)	Result
Anchor Bolts	Tension	57.9%	PASS

FOUNDATION:

The foundation with modifications per the reinforcement drawings prepared by this office dated February 18, 2013 was found to be within allowable limits.

Foundation	Design Limit	Required FS ⁽¹⁾	Proposed Loading FS ⁽¹⁾	Result
Reinf. Conc. Pad and Pier	OTM ⁽²⁾	1.0	1.54	PASS

Note: 1. FS denote Factor of Safety
 2. OTM denotes Overturning Moment

CEN TEK Engineering, Inc.
Structural Analysis – 150-ft CL&P Pole # 10255
Sprint Antenna Upgrade – CT03XC351
Bethel, CT
February 18, 2013


C o n c l u s i o n s a n d R e c o m m e n d a t i o n s

This analysis shows that **provided the proposed foundation modifications prepared by this office dated February 18, 2013 have been implemented** the subject utility pole **is adequate** to support the proposed Sprint equipment upgrade.


The analysis is based, in part on the information provided to this office by Northeast Utilities and Sprint. If the existing conditions are different than the information in this report, CENTEK Engineering, Inc. must be contacted for resolution of any potential issues.

Please feel free to call with any questions or comments.

Respectfully Submitted by:



Carlo F. Centore, PE
Principal ~ Structural Engineer



Prepared by:



Timothy J. Lynn, EIT
Structural Engineer

CEN TEK Engineering, Inc.
Structural Analysis – 150-ft CL&P Pole # 10255
Sprint Antenna Upgrade – CT03XC351
Bethel, CT
February 18, 2013

STANDARD CONDITIONS FOR FURNISHING OF
PROFESSIONAL ENGINEERING SERVICES ON
EXISTING STRUCTURES

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessarily limited to:

- Information supplied by the client regarding the structure itself, its foundations, the soil conditions, the antenna and feed line loading on the structure and its components, or other relevant information.
- Information from the field and/or drawings in the possession of CEN TEK engineering, Inc. or generated by field inspections or measurements of the structure.
- It is the responsibility of the client to ensure that the information provided to CEN TEK engineering, Inc. and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and are in an un-corroded condition and have not deteriorated. It is therefore assumed that its capacity has not significantly changed from the "as new" condition.
- All services will be performed to the codes specified by the client, and we do not imply to meet any other codes or requirements unless explicitly agreed in writing. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement. In the absence of information to the contrary, all work will be performed in accordance with the latest revision of ANSI/ASCE10 & ANSI/EIA-222.
- All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. CEN TEK engineering, Inc. is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.

GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM ~ RISA - 3 D

RISA-3D Structural Analysis Program is an integrated structural analysis and design software package for buildings, bridges, tower structures, etc.

Modeling Features:

- Comprehensive CAD-like graphic drawing/editing capabilities that let you draw, modify and load elements as well as snap, move, rotate, copy, mirror, scale, split, merge, mesh, delete, apply, etc.
- Versatile drawing grids (orthogonal, radial, skewed)
- Universal snaps and object snaps allow drawing without grids
- Versatile general truss generator
- Powerful graphic select/unselect tools including box, line, polygon, invert, criteria, spreadsheet selection, with locking
- Saved selections to quickly recall desired selections
- Modification tools that modify single items or entire selections
- Real spreadsheets with cut, paste, fill, math, sort, find, etc.
- Dynamic synchronization between spreadsheets and views so you can edit or view any data in the plotted views or in the spreadsheets
- Simultaneous view of multiple spreadsheets
- Constant in-stream error checking and data validation
- Unlimited undo/redo capability
- Generation templates for grids, disks, cylinders, cones, arcs, trusses, tanks, hydrostatic loads, etc.
- Support for all units systems & conversions at any time
- Automatic interaction with RISASection libraries
- Import DXF, RISA-2D, STAAD and ProSteel 3D files
- Export DXF, SDNF and ProSteel 3D files

Analysis Features:

- Static analysis and P-Delta effects
- Multiple simultaneous dynamic and response spectra analysis using Gupta, CQC or SRSS mode combinations
- Automatic inclusion of mass offset (5% or user defined) for dynamic analysis
- Physical member modeling that does not require members to be broken up at intermediate joints
- State of the art 3 or 4 node plate/shell elements
- High-end automatic mesh generation — draw a polygon with any number of sides to create a mesh of well-formed quadrilateral (NOT triangular) elements.
- Accurate analysis of tapered wide flanges - web, top and bottom flanges may all taper independently
- Automatic rigid diaphragm modeling
- Area loads with one-way or two-way distributions
- Multiple simultaneous moving loads with standard AASHTO loads and custom moving loads for bridges, cranes, etc.
- Torsional warping calculations for stiffness, stress and design
- Automatic Top of Member offset modeling
- Member end releases & rigid end offsets
- Joint master-slave assignments
- Joints detachable from diaphragms
- Enforced joint displacements
- 1-Way members, for tension only bracing, slipping, etc.

- 1-Way springs, for modeling soils and other effects
- Euler members that take compression up to their buckling load, then turn off.
- Stress calculations on any arbitrary shape
- Inactive members, plates, and diaphragms allows you to quickly remove parts of structures from consideration
- Story drift calculations provide relative drift and ratio to height
- Automatic self-weight calculations for members and plates
- Automatic subgrade soil spring generator

Graphics Features:

- Unlimited simultaneous model view windows
- Extraordinary "true to scale" rendering, even when drawing
- High-speed redraw algorithm for instant refreshing
- Dynamic scrolling stops right where you want
- Plot & print virtually everything with color coding & labeling
- Rotate, zoom, pan, scroll and snap views
- Saved views to quickly restore frequent or desired views
- Full render or wire-frame animations of deflected model and dynamic mode shapes with frame and speed control
- Animation of moving loads with speed control
- High quality customizable graphics printing

Design Features:

- Designs concrete, hot rolled steel, cold formed steel and wood
- ACI 1999/2002, BS 8110-97, CSA A23.3-94, IS456:2000, EC 2-1992 with consistent bar sizes through adjacent spans
- Exact integration of concrete stress distributions using parabolic or rectangular stress blocks
- Concrete beam detailing (Rectangular, T and L)
- Concrete column interaction diagrams
- Steel Design Codes: AISC ASD 9th, LRFD 2nd & 3rd, HSS Specification, CAN/CSA-S16.1-1994 & 2004, BS 5950-1-2000, IS 800-1984, Euro 3-1993 including local shape databases
- AISI 1999 cold formed steel design
- NDS 1991/1997/2001 wood design, including Structural Composite Lumber, multi-ply, full sawn
- Automatic spectra generation for UBC 1997, IBC 2000/2003
- Generation of load combinations: ASCE, UBC, IBC, BOCA, SBC, ACI
- Unbraced lengths for physical members that recognize connecting elements and full lengths of members
- Automatic approximation of K factors
- Tapered wide flange design with either ASD or LRFD codes
- Optimization of member sizes for all materials and all design codes, controlled by standard or user-defined lists of available sizes and criteria such as maximum depths
- Automatic calculation of custom shape properties
- Steel Shapes: AISC, HSS, CAN, ARBED, British, Euro, Indian, Chilean
- Light Gage Shapes: AISI, SSMA, Dale / Incor, Dietrich, MarinoWARE
- Wood Shapes: Complete NDS species/grade database
- Full seamless integration with RISAFoot (Ver 2 or better) for advanced footing design and detailing
- Plate force summation tool

CEN TEK Engineering, Inc.
Structural Analysis – 150-ft CL&P Pole # 10255
Sprint Antenna Upgrade – CT03XC351
Bethel, CT
February 18, 2013

Results Features:

- Graphic presentation of color-coded results and plotted designs
- Color contours of plate stresses and forces with quadratic smoothing, the contours may also be animated
- Spreadsheet results with sorting and filtering of: reactions, member & joint deflections, beam & plate forces/stresses, optimized sizes, code designs, concrete reinforcing, material takeoffs, frequencies and mode shapes
- Standard and user-defined reports
- Graphic member detail reports with force/stress/deflection diagrams and detailed design calculations and expanded diagrams that display magnitudes at any dialed location
- Saved solutions quickly restore analysis and design results.

GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM ~ PLS - POLE

PLS-POLE provides all of the capabilities a structural engineer requires to design transmission, substation or communications structures. It does so using a simple easy to use graphical interface that rests upon our time tested finite element engine. Regardless of whether you want to model a simple wood pole or a guyed steel X-Frame; PLS-POLE can handle the job simply, reliably and efficiently.

Modeling Features:

- Structures are made of standard reusable components that are available in libraries. You can easily create your own libraries or get them from a manufacturer
- Structure models are built interactively using interactive menus and graphical commands
- Automatic generation of underlying finite element model of structure
- Steel poles can have circular, 4, 6, 8, 12, 16, or 18-sided, regular, elliptical or user input cross sections (flat-to-flat or tip-to-tip orientations)
- Steel and concrete poles can be selected from standard sizes available from manufacturers
- Automatic pole class selection
- Cross brace position optimizer
- Capability to specify pole ground line rotations
- Capability to model foundation displacements
- Can optionally model foundation stiffness
- Guys are easily handled (modeled as exact cable elements in nonlinear analysis)
- Powerful graphics module (members color-coded by stress usage)
- Graphical selection of joints and components allows graphical editing and checking
- Poles can be shown as lines, wire frames or can be rendered as 3-d polygon surfaces

Analysis Features:

- Automatic distribution of loads in 2-part suspension insulators (v-strings, horizontal vees, etc.)
- Design checks for ASCE, ANSI/TIA/EIA 222 (Revisions F and G) or other requirements
- Automatic calculation of dead and wind loads
- Automated loading on structure (wind, ice and drag coefficients) according to:
 - ASCE 74-1991
 - NESC 2002
 - NESC 2007
 - IEC 60826:2003
 - EN50341-1:2001 (CENELEC)
 - EN50341-3-9:2001 (UK NNA)
 - EN50341-3-17:2001 (Portugal NNA)
 - ESAA C(b)1-2003 (Australia)
 - TPNZ (New Zealand)
 - REE (Spain)
 - EIA/TIA 222-F
 - ANSI/TIA 222-G
 - CSA S37-01
- Automated microwave antenna loading as per EIA/TIA 222-F and ANSI/TIA 222-G
- Detects buckling by nonlinear analysis

CEN TEK Engineering, Inc.
Structural Analysis – 150-ft CL&P Pole # 10255
Sprint Antenna Upgrade – CT03XC351
Bethel, CT
February 18, 2013

Results Features:

- Detects buckling by nonlinear analysis
- Easy to interpret text, spreadsheet and graphics design summaries
- Automatic determination of allowable wind and weight spans
- Automatic determination of interaction diagrams between allowable wind and weight spans
- Automatic tracking of part numbers and costs

Criteria for Design of PCS Facilities On or
Extending Above Metal Electric Transmission
Towers & Analysis of Transmission Towers
Supporting PCS Masts ⁽¹⁾

Introduction

This criteria is the result from an evaluation of the methods and loadings specified by the separate standards, which are used in designing telecommunications towers and electric transmission towers. That evaluation is detailed elsewhere, but in summary; the methods and loadings are significantly different. This criteria specifies the manner in which the appropriate standard is used to design PCS facilities including masts and brackets (hereafter referred to as "masts"), and to evaluate the electric transmission towers to support PCS masts. The intent is to achieve an equivalent level of safety and security under the extreme design conditions expected in Connecticut and Massachusetts.

ANSI Standard TIA/EIA-222 covering the design of telecommunications structures specifies a working strength/allowable stress design approach. This approach applies the loads from extreme weather loading conditions, and designs the structure so that it does not exceed some defined percentage of failure strength (allowable stress).

ANSI Standard C2-2007 (National Electrical Safety Code) covering the design of electric transmission metal structures is based upon an ultimate strength/yield stress design approach. This approach applies a multiplier (overload capacity factor) to the loads possible from extreme weather loading conditions, and designs the structure so that it does not exceed its ultimate strength (yield stress).

Each standard defines the details of how loads are to be calculated differently. Most of the NU effort in "unifying" both codes was to establish what level of strength each approach would provide, and then increasing the appropriate elements of each to achieve a similar level of security under extreme weather loadings.

Two extreme weather conditions are considered. The first is an extreme wind condition (hurricane) based upon a 50-year recurrence (2% annual probability). The second is a winter condition combining wind and ice loadings.

The following sections describe the design criteria for any PCS mast extending above the top of an electric transmission tower, and the analysis criteria for evaluating the loads on the transmission tower from such a mast from the lower portions of such a mast, and loads on the pre-existing electric lower portions of such a mast, and loads on the pre-existing electric transmission tower and the conductors it supports.

| Note 1: Prepared from documentation provide from Northeast Utilities.

P C S M a s t

The PCS facility (mast, external cable/trays, including the initial and any planned future support platforms, antennas, etc. extending the full height above the top level of the electric transmission structure) shall be designed in accordance with the provisions of TIA/EIA Standard 222 with two exceptions:

1. An 85 mph extreme wind speed shall be used for locations in all counties throughout the NU system.
2. The stress increase of TIA Section 3.1.1.1 is disallowed. The combined wind and ice condition shall consider ½" radial ice in combination with the wind load (0.75 Wi) as specified in TIA section 2.3.16.

E L E C T R I C T R A N S M I S S I O N T O W E R

The electric transmission tower shall be analyzed using yield stress theory in accordance with the attached table titled "NU Design Criteria". This specifies uniform loadings (different from the TIA loadings) on the each of the following components of the installed facility:

- PCS mast for its total height above ground level, including the initial and planned future support platforms, antennas, etc. above the top of an electric transmission structure.
- Conductors are related devices and hardware.
- Electric transmission structure. The loads from the PCS facility and from the electric conductors shall be applied to the structure at conductor and PCS mast attachment points, where those load transfer to the tower.

The uniform loadings and factors specified for the above components in the table are based upon the National Electrical Safety Code 2007 Edition Extreme Wind (Rule 250C) and Combined Ice and Wind (Rule 250B-Heavy) Loadings. These provide equivalent loadings compared to TIA and its loads and factors with the exceptions noted above. (Note that the NESC does not require the projected wind surfaces of structures and equipment to be increased by the ice covering.)

In the event that the electric transmission tower is not sufficient to support the additional loadings of the PCS mast, reinforcement will be necessary to upgrade the strength of the overstressed members.



Northeast Utilities Overhead Transmission Standards



Attachment A

NU Design Criteria

			Basic Wind Speed V (MPH)	Pressure Q (PSF)	Height Factor Kz	Gust Factor Gh	Load or Stress Factor	Force Coef - Shape Factor
Ice Condition	TIA/EIA	Antenna Mount	TIA	TIA (.75Wi)	TIA	TIA	TIA, Section 3.1.1.1 disallowed for connection design	TIA
	NESC Heavy	Tower/Pole Analysis with antennas extending above top of Tower/Pole (Yield Stress)	---	4	1.00	1.00	2.50	1.6 Flat Surfaces 1.3 Round Surfaces
		Tower/Pole Analysis with Antennas below top of Tower/Pole (on two faces)	---	4	1.00	1.00	2.50	1.6 Flat Surfaces 1.3 Round Surfaces
	Conductors:		Conductor loads provided by NU					
High Wind Condition	TIA/EIA	Antenna Mount	85	TIA	TIA	TIA	TIA, Section 3.1.1.1 disallowed for connection design	TIA
	NESC Extreme Wind	Tower/Pole Analysis with antennas extending above top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250C: Extreme Wind Loading 1.25 x Gust Response Factor Height above ground level based on top of Mast/Antenna					1.6 Flat Surfaces 1.3 Round Surfaces
		Tower/Pole Analysis with Antennas below top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250C: Extreme Wind Loading Height above ground level based on top of Tower/Pole					1.6 Flat Surfaces 1.3 Round Surfaces
	Conductors:		Conductor loads provided by NU					
NESC Extreme Ice with Wind Condition*		Tower/Pole Analysis with antennas extending above top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250D: Extreme Ice with Wind Loading 4PSF Wind Load 1.25 x Gust Response Factor Height above ground level based on top of Mast/Antenna					1.6 Flat Surfaces 1.3 Round Surfaces
		Tower/Pole Analysis with Antennas below top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250D: Extreme Ice with Wind Loading 4PSF Wind Load Height above ground level based on top of Tower/Pole					1.6 Flat Surfaces 1.3 Round Surfaces
	Conductors:		Conductor loads provided by NU					

* Only for Structures Installed after 2007

Communication Antennas on Transmission Structures (CL&P & WMECo Only)

Northeast Utilities Approved by: KMS (NU)	Design NU Confidential Information	OTRM 059	Rev.1
		Page 7 of 9	03/17/2011



Shape Factor Criteria shall be per TIA Shape Factors.

- 2) STEP 2 - The electric transmission structure analysis and evaluation shall be performed in accordance with NESC requirements and shall include the mast and antenna loads determined from NESC applied loading conditions (not TIA/EIA Loads) on the structure and mount as specified below, and shall include the wireless communication mast and antenna loads per NESC criteria)

The structure shall be analyzed using yield stress theory in accordance with Attachment A, "NU Design Criteria." This specifies uniform loadings (different from the TIA loadings) on each of the following components of the installed facility:

- a) Wireless communication mast for its total height above ground level, including the initial and any planned future equipment (Support Platforms, Antennas, TMA's etc.) above the top of an electric transmission structure.
- b) Conductors and related devices and hardware (wire loads will be provided by NU).
- c) Electric Transmission Structure
 - i) The loads from the wireless communication equipment components based on NESC and NU Criteria in Attachment A, and from the electric conductors shall be applied to the structure at conductor and wireless communication mast attachment points, where those loads transfer to the tower.
 - ii) Shape Factor Multiplier:

NESC Structure Shape	Cd
Polyround (for polygonal steel poles)	1.3
Flat	1.6
Open Lattice	3.2

- iii) When Coaxial Cables are mounted along side the pole structure, the shape multiplier shall be:

Mount Type	Cable Cd	Pole Cd
Coaxial Cables on outside periphery (One layer)	1.45	1.45
Coaxial Cables mounted on stand offs	1.6	1.3

- d) The uniform loadings and factors specified for the above components in Attachment A, "NU Design Criteria" are based upon the National Electric Safety Code 2007 Edition Extreme Wind (Rule 250C) and Combined Ice and Wind (Rule 250B-Heavy) Loadings. These provide equivalent loadings compared to the TIA and its loads and factors with the exceptions noted above.

Note: The NESC does not require ice load be included in the supporting structure. (Ice on conductors and shield wire only, and NU will provide these loads).

- e) Mast reaction loads shall be evaluated for local effects on the transmission structure members at the attachment points.

Communication Antennas on Transmission Structures (CL&P & WMECo Only)			
Northeast Utilities Approved by: KMS (NU)	Design NU Confidential Information	OTRM 059	Rev.1
		Page 3 of 9	03/17/2011



Job :

Description:

Spec. Number

Computed by

Checked by

Page of

Sheet of

Date 10/25/10

Date

INPUT DATA

TOWER ID: 10255

Structure Height (ft) : 150

Wind Zone : Central CT (green)

Wind Speed : 90.5711047 mph

Tower Type : ☒ Suspension

☐ Strain

Extreme Wind Model : PCS Addition

Shield Wire Properties:

	BACK	AHEAD
NAME =	3/8 AW	3/8 AW
DESCRIPTION =	3/8	3/8
STRANDING =	7 #8 Al Weld	7 #8 Al Weld
DIAMETER =	0.385 in	0.385 in
WEIGHT =	0.262 lb/ft	0.262 lb/ft

Conductor Properties:

	BACK	AHEAD
NAME =	BITTERN	BITTERN
Number of Conductors per phase	2	2
	1272.000	1272.000
	45/7 ACSR	45/7 ACSR
DIAMETER =	1.345 in	1.345 in
WEIGHT =	1.432 lb/ft	1.432 lb/ft
		Number of Conductors per phase

Insulator Weight = 0 lbs

Broken Wire Side = AHEAD SPAN

Horizontal Line Tensions:

	BACK		AHEAD	
	Shield	Conductor	Shield	Conductor
NESC HEAVY =	4,200	10,000	4,200	10,000
EXTREME WIND =	3,440	10,733	3,440	10,733
LONG. WIND =	na	na	na	na
250D COMBINED =	na	na	na	na
NESC W/O OLF =	na	na	na	na
60 DEG F NO WIND =	1,239	4,616	1,239	4,616

Line Geometry:

					SUM
LINE ANGLE (deg) =	BACK:	0	AHEAD:	0	0
WIND SPAN (ft) =	BACK:	441	AHEAD:	493	934
WEIGHT SPAN (ft) =	BACK:	544	AHEAD:	386	931



Job :

Description:

Spec. Number

Computed by

Checked by

Page of

Sheet of

Date 10/25/10

Date

WIRE LOADING AT ATTACHMENTS

TOWER ID: 10255

Wind Span = 934 ft
Weight Span = 931 ft
Total Angle = 0 degrees

Broken Wire Span = AHEAD SPAN
Type of Insulator Attachment = SUSPENSION

1. NESC RULE 250B Heavy Loading:

	INTACT CONDITION			BROKEN WIRE CONDITION		
	Horizontal	Longitudinal	Vertical	Horizontal	Longitudinal	Vertical
Shield Wire =	1,078 lb	0 lb	1,134 lb	509 lb	6,930 lb	663 lb
Conductor =	3,651 lb	0 lb	7,201 lb	1,724 lb	33,000 lb	4,212 lb

2. NESC RULE 250C Transverse Extreme Wind Loading:

	Horizontal	Longitudinal	Vertical
Shield Wire =	715 lb	0 lb	280 lb
Conductor =	4,999 lb	0 lb	3,065 lb

3. NESC RULE 250C Longitudinal Extreme Wind Loading:

	Horizontal	Longitudinal	Vertical
Shield Wire =	#VALUE!	#VALUE!	280 lb
Conductor =	#VALUE!	#VALUE!	3,065 lb

4. NESC RULE 250D Extreme Ice & Wind Loading:

	Horizontal	Longitudinal	Vertical
Shield Wire =	#VALUE!	#VALUE!	1,846 lb
Conductor =	#VALUE!	#VALUE!	8,093 lb

5. NESC RULE 250B w/o OLE's

	Horizontal	Longitudinal	Vertical
Shield Wire =	#VALUE!	#VALUE!	756 lb
Conductor =	#VALUE!	#VALUE!	4,800 lb

6. 60 Deg. F. No Wind

	Horizontal	Longitudinal	Vertical
Shield Wire =	0 lb	0 lb	244 lb
Conductor =	0 lb	0 lb	2,665 lb

7. Construction

	Horizontal	Longitudinal	Vertical
Shield Wire =	0 lb	0 lb	365 lb
Conductor =	0 lb	0 lb	3,998 lb



Northeast
Utilities System

Job :

Description:

Spec. Number

Computed by

Checked by

Page of

Sheet of

Date 10/25/10

Date

NOTE: All loads include required overload factors (OLF's).

LC 1		HORIZONTAL	LONGITUDINAL	VERTICAL
NESC Heavy	shield - back	509.2529583	6930	663.0142153
	shield - ahead	569.0041667	-6930	470.5537229
	SHIELD - SUM	1078.257125	0	1133.567938
	conductor - back	1724.473917	33000	4211.530273
	conductor - ahead	1926.808333	-33000	2989.002654
	CONDUCTOR - SUM	3651.28225	0	7200.532927
LC 2		HORIZONTAL	LONGITUDINAL	VERTICAL
Extreme Wind	shield - back	337.8929873	3956	163.872401
	shield - ahead	377.5383423	-3956	116.303341
	SHIELD - SUM	715.4313296	0	280.175742
	conductor - back	2360.862691	24685.9	1792.70648
	conductor - ahead	2637.8653	-24685.9	1272.31768
	CONDUCTOR - SUM	4998.727991	0	3065.02416
LC 3		HORIZONTAL	LONGITUDINAL	VERTICAL
Long. Wind	shield - back	#VALUE!	#VALUE!	163.872401
	shield - ahead	#VALUE!	#VALUE!	116.303341
	SHIELD - SUM	#VALUE!	#VALUE!	280.175742
	conductor - back	#VALUE!	#VALUE!	1792.70648
	conductor - ahead	#VALUE!	#VALUE!	1272.31768
	CONDUCTOR - SUM	#VALUE!	#VALUE!	3065.02416
LC 4		HORIZONTAL	LONGITUDINAL	VERTICAL
RULE 250D	shield - back	#VALUE!	#VALUE!	1079.952555
	shield - ahead	#VALUE!	#VALUE!	766.4627447
	SHIELD - SUM	#VALUE!	#VALUE!	1846.4153
	conductor - back	#VALUE!	#VALUE!	4733.36118
	conductor - ahead	#VALUE!	#VALUE!	3359.355913
	CONDUCTOR - SUM	#VALUE!	#VALUE!	8092.717093
LC 5		HORIZONTAL	LONGITUDINAL	VERTICAL
NESC w/o OLF's	shield - back	#VALUE!	#VALUE!	442.0094769
	shield - ahead	#VALUE!	#VALUE!	313.7024819
	SHIELD - SUM	#VALUE!	#VALUE!	755.7119588
	conductor - back	#VALUE!	#VALUE!	2807.686849
	conductor - ahead	#VALUE!	#VALUE!	1992.668436
	CONDUCTOR - SUM	#VALUE!	#VALUE!	4800.355285
LC 6		HORIZONTAL	LONGITUDINAL	VERTICAL
Raking	shield - back	0	1239	142.49774
	shield - ahead	0	-1239	101.13334
	SHIELD - SUM	0	0	243.63108
	conductor - back	0	9232	1558.8752
	conductor - ahead	0	-9232	1106.3632
	CONDUCTOR - SUM	0	0	2665.2384
LC 6		HORIZONTAL	LONGITUDINAL	VERTICAL
60 DEG F NO WIND	shield - back	0	1858.5	213.74661
	shield - ahead	0	-1858.5	151.70001
	SHIELD - SUM	0	0	365.44662
	conductor - back	0	13848	2338.3128
	conductor - ahead	0	-13848	1659.5448
	CONDUCTOR - SUM	0	0	3997.8576

EXISTING 12" SCH. 80 X
33'-0" LONG PIPE MAST

☉ VERIZON ANTENNAS
EL. ±167'-6" ABP

☉ SPRINT ANTENNAS
EL. ±157'-6" ABP

☉ TOP CONNECTION
EL. ±146'-6" ABP

☉ BOT. CONNECTION
EL. ±140'-3" ABP

NOTE: ABP DENOTES
ABOVE OF BASE PLATE

VERIZON (EXISTING/RESERVED):
THREE (3) ANTEL BXA-70063/6CF
PANEL ANTENNAS, THREE (3) ANDREW
DBXNH-6565A-VTM PANEL ANTENNAS
AND SIX (6) RFS FD9R6004/2C-3L
DIPLEXERS MOUNTED ON THREE (3)
DUAL STANDOFF MOUNTS

SPRINT (PROPOSED): THREE (3) RFS
APXVSP18-C PANEL ANTENNAS
MOUNTED ON AN EXISTING LOW PROFILE
PLATFORM

SPRINT (EXISTING TO REMOVE): SIX (6)
DECIBEL DB980F65T2E-M PANEL
ANTENNAS

EXISTING 150' TALL
CL&P STEEL POLE
STRUCTURE NO. 10255

EXISTING SPRINT SIX (6)
1-5/8" DIA. COAX CABLES

EXISTING VERIZON TWELVE
(12) 1-5/8" DIA. COAX
CABLES (BEHIND)

SPRINT PROPOSED TWELVE (12)
1-5/8" DIA. COAX CABLES MOUNTED
TO THE EXTERIOR OF THE POLE

FOUNDATION REINFORCEMENT PER
CENTEK ENGINEERING DRAWINGS DATED
FEBRUARY 18, 2013 TO BE COMPLETED
PRIOR TO SPRINT ANTENNA UPGRADE

1
EL-1

TOWER & MAST ELEVATION

SCALE: NOT TO SCALE


REVISIONS		
00	2/18/13	ISSUED FOR NJ REVIEW

CEN TEK engineering
Centered on Solutions™
www.CentekEng.com
(203) 488-0580
(203) 488-8587 Fax
63-2 North Branford Road, Branford, CT 06405

CT03XC351
CL&P 10255

SKY EDGE LANE
BETHEL, CT 06801

PROJECT NO: 12047.C03
DRAWN BY: TJL
CHECKED BY: CFC
SCALE: AS NOTED
DATE: 2/12/13



TOWER AND MAST
ELEVATION


EL-1
DWG. 1 OF 2

EXISTING VERIZON TWELVE (12)
1-5/8" DIA. COAX CABLES

EXISTING 150' TALL CL&P STEEL
POLE STRUCTURE NO. 10255

SPRINT EXISTING SIX (6)
1-5/8" DIA. COAX CABLES

SPRINT PROPOSED TWELVE (12)
1-5/8" DIA. COAX CABLES



1
FP-1

FEEDLINE PLAN - TOWER

SCALE: NOT TO SCALE

REVISIONS

00	2/18/13	ISSUED FOR NJ REVIEW

CEN TEK engineering
Centered on Solutions™

(203) 488-0580
(203) 488-8587 Fax
63-2 North Branford Road, Branford, CT 06405
www.CentekEng.com

CT03XC351
CL&P 10255

SKY EDGE LANE
BETHEL, CT 06801

PROJECT NO: 12047.CO3
DRAWN BY: TJL
CHECKED BY: CFC
SCALE: AS NOTED
DATE: 2/12/13

FEEDLINE
PLAN

FP-1

DWG. 2 OF 2

**RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS**

Sprint Existing Facility

Site ID: CT03XC351

**Bethel NU Pole # 10255
8 Sky Drive
Bethel, CT 06801**

May 24, 2013

EBI Project Number: 62136519

May 24, 2013

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Emissions Values for Site: **CT03XC351 – Bethel NU Pole # 10255**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 8 Sky Drive, Bethel, CT, for the purpose of determining whether the emissions from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the PCS band is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 8 Sky Drive, Bethel, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 5 CDMA Carriers (1900 MHz) were considered for each sector of the proposed installation.
- 2) 1 CDMA Carrier (850 MHz) was considered for each sector of the proposed installation
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The actual gain in this direction was used per the manufactures supplied specifications.
- 5) The antenna used in this modeling is the APXVSPP18-C-A20. This is based on feedback from the carrier with regards to anticipated antenna selection. This antenna has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.

- 6) The antenna mounting height centerline of the proposed antennas is **157.5 feet** above ground level (AGL)
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site IDCT03XC351 - Bethel NU Pole # 10255																		
Site Address8 Sky Drive, Bethel, CT, 06801																		
Site TypeUtility Transmission Tower																		
Sector 1																		
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBD)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage	
	1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	5	100	15.9	157.5	151.5	1/2 "	0.5	0	3467.3685	54.31011	5.43101%
	1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	157.5	151.5	1/2 "	0.5	0	389.96892	6.108164	1.07728%
Sector total Power Density Value: 6.508%																		
Sector 2																		
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBD)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage	
	2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	5	100	15.9	157.5	151.5	1/2 "	0.5	0	3467.3685	54.31011	5.43101%
	2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	157.5	151.5	1/2 "	0.5	0	389.96892	6.108164	1.07728%
Sector total Power Density Value: 6.508%																		
Sector 3																		
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBD)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage	
	3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	5	100	15.9	157.5	151.5	1/2 "	0.5	0	3467.3685	54.31011	5.43101%
	3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	157.5	151.5	1/2 "	0.5	0	389.96892	6.108164	1.07728%
Sector total Power Density Value: 6.508%																		

Site Composite MPE %	
Carrier	MPE %
Sprint	19.525%
Verizon Wireless	13.690%
Total Site MPE %	33.215%

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public exposure to RF Emissions.

The anticipated Maximum Composite contributions from the Sprint facility are **19.525% (6.508% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **33.215%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L. Checked by: C.F.C.
Job No. 12047.CO3

**Development of Design Heights, Exposure Coefficients,
and Velocity Pressures Per TIA/EIA**

Wind Speeds

Basic Wind Speed	$V := 85$	mph	(User Input per NU Mast Design Criteria Exception 1)
Basic Wind Speed with Ice	$V_i := 74$	mph	(User Input per TIA/EIA-222-F Section 2.3.16)

Heights above ground level, z

Mast	$z_{\text{mast}} := 153.5$	ft	(User Input)
Verizon	$z_{\text{vz}} := 167.5$	ft	(User Input)
Sprint	$z_{\text{sprt}} := 157.5$	ft	(User Input)
Coax Cable	$z_{\text{coax}} := 153.5$	ft	(User Input)

Exposure Coefficients, k_z

(per TIA/EIA-222-F Section 2.3.3)

Mast	$K_{z_{\text{mast}}} := \left(\frac{z_{\text{mast}}}{33} \right)^{\frac{2}{7}} = 1.551$
Verizon	$K_{z_{\text{vz}}} := \left(\frac{z_{\text{vz}}}{33} \right)^{\frac{2}{7}} = 1.591$
Sprint	$K_{z_{\text{sprt}}} := \left(\frac{z_{\text{sprt}}}{33} \right)^{\frac{2}{7}} = 1.563$
Coax Cable	$K_{z_{\text{coax}}} := \left(\frac{z_{\text{coax}}}{33} \right)^{\frac{2}{7}} = 1.551$

Velocity Pressure without ice, q_z

(per TIA/EIA-222-F Section 2.3.3)

Mast	$q_{z_{\text{mast}}} := 0.00256 \cdot K_{z_{\text{mast}}} \cdot V^2 = 28.696$
Verizon	$q_{z_{\text{vz}}} := 0.00256 \cdot K_{z_{\text{vz}}} \cdot V^2 = 29.42$
Sprint	$q_{z_{\text{sprt}}} := 0.00256 \cdot K_{z_{\text{sprt}}} \cdot V^2 = 28.908$
Coax Cable	$q_{z_{\text{coax}}} := 0.00256 \cdot K_{z_{\text{coax}}} \cdot V^2 = 28.696$

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L. Checked by: C.F.C.
Job No. 12047.CO3

Velocity Pressure with ice, qzICE

(per TIA/EIA-222-F Section 2.3.3)

Mast	$qzICE_{mast} := 0.00256 \cdot Kz_{mast} \cdot V_i^2 = 21.749$
Verizon	$qzICE_{vz} := 0.00256 \cdot Kz_{vz} \cdot V_i^2 = 22.298$
Sprint	$qzICE_{sprt} := 0.00256 \cdot Kz_{sprt} \cdot V_i^2 = 21.91$
Coax Cable	$qzICE_{coax} := 0.00256 \cdot Kz_{coax} \cdot V_i^2 = 21.749$

TIA/EIA Common Factors:

Gust Response Factor =	$G_H := 1.69$	(User Input per TIA/EIA-222-F Section 2.3.4)
Gust Response Factor Multiplier =	$m := 1.25$	(User Input per TIA/EIA-222-F Section 2.3.4.4)
Radial Ice Thickness =	$Ir := 0.50$	in (User Input per TIA/EIA-222-F Section 2.3.1)
Radial Ice Density =	$Id := 56.00$	pcf (User Input)

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

 Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 12047.CO3

Development of Wind & Ice Load on PCS Mast

(per TIA/EIA-222-F-1996 Criteria)

Mast Data:

Mast Shape =	Round	(User Input)
Mast Diameter =	$D_{\text{mast}} := 12.8$ in	(User Input)
Mast Length =	$L_{\text{mast}} := 33$ ft	(User Input)
Mast Thickness =	$t_{\text{mast}} := 0.5$ in	(User Input)

$$\text{Mast Aspect Ratio} = A_{r_{\text{mast}}} := \frac{12L_{\text{mast}}}{D_{\text{mast}}} = 30.9$$

$$\text{Mast Force Coefficient} = C_{a_{\text{mast}}} = 1.2 \quad (\text{per TIA/EIA-222-F Table 3})$$

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

$$\text{Mast Projected Surface Area} = A_{\text{mast}} := \frac{D_{\text{mast}}}{12} = 1.067$$

$$\text{Total Mast Wind Force} = qZ_{\text{mast}} G_H C_{a_{\text{mast}}} A_{\text{mast}} = 62$$

 plf **BLC 5**
Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

$$\text{Mast Projected Surface Area w/ Ice} = A_{ICE_{\text{mast}}} := \frac{(D_{\text{mast}} + 2 \cdot I_r)}{12} = 1.15$$

$$\text{Total Mast Wind Force w/ Ice} = qZ_{ICE_{\text{mast}}} G_H C_{a_{\text{mast}}} A_{ICE_{\text{mast}}} = 51$$

 plf **BLC 4**
Gravity Loads (without ice)
Weight of the mast =

Self Weight (Computed internally by Risa-3D)

 plf **BLC 1**
Gravity Loads (ice only)

Ice Area per Linear Foot =

$$A_{i_{\text{mast}}} := \frac{\pi}{4} \left[(D_{\text{mast}} + I_r \cdot 2)^2 - D_{\text{mast}}^2 \right] = 20.9$$

sq in

Weight of Ice on Mast =

$$W_{ICE_{\text{mast}}} := I_d \cdot \frac{A_{i_{\text{mast}}}}{144} = 8$$

 plf **BLC 3**

Development of Wind & Ice Load on Antennas

Antenna Data:

Antenna Model =	Antel BXA-70063/6CF	
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 71$	in (User Input)
Antenna Width =	$W_{ant} := 11.2$	in (User Input)
Antenna Thickness =	$T_{ant} := 5.2$	in (User Input)
Antenna Weight =	$WT_{ant} := 17$	lbs (User Input)
Number of Antennas =	$N_{ant} := 3$	(User Input)
Antenna Aspect Ratio =	$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 6.3$	
Antenna Force Coefficient =	$Ca_{ant} = 1.4$	(per TIA/EIA-222-F-1996 Table 3)

(per TIA/EIA-222-F-1996 Criteria)

(Verizon)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
Applied to All Antennas Simultaneously*

Surface Area for One Antenna =	$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 5.5$	sf
Antenna Projected Surface Area =	$A_{ant} := SA_{ant} \cdot N_{ant} = 16.6$	sf

Total Antenna Wind Force =

$$F_{ant} := qz_{vz} \cdot G_H \cdot Ca_{ant} \cdot A_{ant} = 1153 \quad \text{lbs} \quad \text{BLC 5}$$

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
Applied to All Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =	$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 6.1$	sf
Antenna Projected Surface Area w/ Ice =	$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 18.3$	sf

Total Antenna Wind Force w/ Ice =

$$F_{ant} := qz_{ICEvz} \cdot G_H \cdot Ca_{ant} \cdot A_{ICEant} = 965 \quad \text{lbs} \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 51 \quad \text{lbs} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Volume of Each Antenna =	$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 4135$	cu in
Volume of Ice on Each Antenna =	$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1311$	cu in
Weight of Ice on Each Antenna =	$W_{ICEant} := \frac{V_{ice}}{1728} \cdot Id = 42$	lbs
Weight of Ice on All Antennas =	$W_{ICEant} \cdot N_{ant} = 127$	lbs BLC 3

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L. Checked by: C.F.C.
Job No. 12047.CO3

Development of Wind & Ice Load on Antennas

Antenna Data:

Antenna Model =	Andrew DBXNH-6565A-VTM	
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 50.91$	in (User Input)
Antenna Width =	$W_{ant} := 11.85$	in (User Input)
Antenna Thickness =	$T_{ant} := 7.1$	in (User Input)
Antenna Weight =	$WT_{ant} := 34.17$	lbs (User Input)
Number of Antennas =	$N_{ant} := 3$	(User Input)
Antenna Aspect Ratio =	$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 4.3$	
Antenna Force Coefficient =	$Ca_{ant} = 1.4$	(per TIA/EIA-222-F-1996 Table 3)

(per TIA/EIA-222-F-1996 Criteria)

(Verizon)

Wind Load (without ice)

Assumes Maximum Possible Wind Pressure Applied to All Antennas Simultaneously

Surface Area for One Antenna =	$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 4.2$	sf
Antenna Projected Surface Area =	$A_{ant} := SA_{ant} \cdot N_{ant} = 12.6$	sf

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Antenna Wind Force =

$$F_{ant} := qz_{vz} \cdot G_H \cdot Ca_{ant} \cdot A_{ant} = 875 \quad \text{lbs} \quad \text{BLC 5}$$

Wind Load (with ice)

Assumes Maximum Possible Wind Pressure Applied to All Antennas Simultaneously

Surface Area for One Antenna w/ Ice =	$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 4.6$	sf
Antenna Projected Surface Area w/ Ice =	$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 13.9$	sf

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Antenna Wind Force w/ Ice =

$$F_{ant} := qz_{ICEvz} \cdot G_H \cdot Ca_{ant} \cdot A_{ICEant} = 733 \quad \text{lbs} \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 103 \quad \text{lbs} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Volume of Each Antenna =	$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 4283$	cu in
Volume of Ice on Each Antenna =	$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1120$	cu in

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 36 \quad \text{lbs}$$

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 109 \quad \text{lbs} \quad \text{BLC 3}$$

Development of Wind & Ice Load on Diplexers

Diplexer Data:

Diplexer Model =	RFS FD9R6004/2C-3L Diplexer	(per TIA/EIA-222-F-1996 Criteria)
Diplexer Shape =	Flat	(User Input)
Diplexer Height =	$L_{dplx} := 5.8$ in	(User Input)
Diplexer Width =	$W_{dplx} := 6.5$ in	(User Input)
Diplexer Thickness =	$T_{dplx} := 1.5$ in	(User Input)
Diplexer Weight =	$WT_{dplx} := 3$ lbs	(User Input)
Number of Diplexers =	$N_{dplx} := 6$	(User Input)
Diplexer Aspect Ratio =	$Ar_{dplx} := \frac{L_{dplx}}{W_{dplx}} = 0.9$	
Diplexer Force Coefficient =	$Ca_{dplx} = 1.4$	(per TIA/EIA-222-F-1996 Table 3)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Assumes Maximum Possible Wind Pressure Applied to All Diplexers Simultaneously

Surface Area for One Diplexer =	$SA_{dplx} := \frac{L_{dplx} \cdot W_{dplx}}{144} = 0.3$	sf
Diplexer Projected Surface Area =	$A_{dplx} := SA_{dplx} \cdot N_{dplx} = 1.6$	sf

Total Diplexer Wind Force =

$$F_{dplx} := qz_{vz} \cdot G_H \cdot Ca_{dplx} \cdot A_{dplx} = 109 \quad \text{lbs} \quad \text{BLC 5}$$

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Assumes Maximum Possible Wind Pressure Applied to All Diplexers Simultaneously

Surface Area for One Diplexer w/ Ice =	$SA_{ICEdplx} := \frac{(L_{dplx} + 1) \cdot (W_{dplx} + 1)}{144} = 0.4$	sf
Diplexer Projected Surface Area w/ Ice =	$A_{ICEdplx} := SA_{ICEdplx} \cdot N_{dplx} = 2.1$	sf

Total Diplexer Wind Force w/ Ice =

$$F_{dplx} := qz_{ICE} \cdot qz_{vz} \cdot G_H \cdot Ca_{dplx} \cdot A_{ICEdplx} = 112 \quad \text{lbs} \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Diplexers =

$$WT_{dplx} \cdot N_{dplx} = 18 \quad \text{lbs} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Volume of Each Diplexer =	$V_{dplx} := L_{dplx} \cdot W_{dplx} \cdot T_{dplx} = 57$	cu in
Volume of Ice on Each Diplexer =	$V_{ice} := (L_{dplx} + 1) \cdot (W_{dplx} + 1) \cdot (T_{dplx} + 1) - V_{dplx} = 71$	cu in
Weight of Ice on Each Diplexer =	$W_{ICEdplx} := \frac{V_{ice}}{1728} \cdot Id = 2$	lbs
Weight of Ice on All Diplexers =	$W_{ICEdplx} \cdot N_{dplx} = 14$	lbs

Subject:

Load Analysis of PCS Mast on CL&P Pole #
10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L. Checked by: C.F.C.
Job No. 12047.CO3**Development of Wind & Ice Load on Antenna Mounts**

(per TIA/EIA-222-F-1996 Criteria)

Mount Data:

(Verizon)

Mount Type:

Dual Standoff Mount
B1827 w/ 6 Pipe Mounts

Platform Shape =

Flat

(User Input)

Platform Area =

 $A_{plt} := 7$

sq ft

(User Input)

(Force Coefficient Included)

Platform Area w/ Ice =

 $A_{ICE,plt} := 10$

sq ft

(User Input)

(Force Coefficient Included)

Platform Weight =

 $WT_{plt} := 575$

lbs

(User Input)

Platform Weight w/ Ice =

 $WT_{ICE,plt} := 800$

lbs

(User Input)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Platform Wind Force =

$$F_{plt} := q_{z,vz} \cdot G_H \cdot A_{plt} = 348$$

lbs

BLC 5**Wind Load (with ice)**

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Platform Wind Force w/ Ice =

$$F_{ICE,plt} := q_{z,vz} \cdot G_H \cdot A_{ICE,plt} = 377$$

lbs

BLC 4**Gravity Load (without ice)**

Weight of Platform =

$$WT_{plt} = 575$$

lbs

BLC 2**Gravity Loads (ice only)**

Weight of Ice on Platform =

$$WT_{ICE,plt} - WT_{plt} = 225$$

lbs

BLC 3

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

 Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 12047.CO3

Development of Wind & Ice Load on Antennas

Antenna Data:

Antenna Model =	RFS APX VSPP18-C	(per TIA/EIA-222-F-1996 Criteria)
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 72$ in	(User Input)
Antenna Width =	$W_{ant} := 11.8$ in	(User Input)
Antenna Thickness =	$T_{ant} := 7$ in	(User Input)
Antenna Weight =	$WT_{ant} := 57$ lbs	(User Input)
Number of Antennas =	$N_{ant} := 3$	(User Input)
Antenna Aspect Ratio =	$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 6.1$	
Antenna Force Coefficient =	$Ca_{ant} = 1.4$	(per TIA/EIA-222-F-1996 Table 3)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna =	$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 5.9$	sf
Antenna Projected Surface Area =	$A_{ant} := SA_{ant} \cdot N_{ant} = 17.7$	sf

Total Antenna Wind Force =

$$F_{ant} := qz_{sprt} \cdot G_H \cdot Ca_{ant} \cdot A_{ant} = 1211 \quad \text{lbs} \quad \text{BLC 5}$$

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =	$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 6.5$	sf
Antenna Projected Surface Area w/ Ice =	$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 19.5$	sf

Total Antenna Wind Force w/ Ice =

$$F_{ant} := qz_{ICEsprt} \cdot G_H \cdot Ca_{ant} \cdot A_{ICEant} = 1009 \quad \text{lbs} \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 171 \quad \text{lbs} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Volume of Each Antenna =	$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 5947$	cu in
Volume of Ice on Each Antenna =	$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1528$	cu in

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 50 \quad \text{lbs}$$

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 149 \quad \text{lbs} \quad \text{BLC 3}$$

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L. Checked by: C.F.C.
Job No. 12047.CO3**Development of Wind & Ice Load on Antenna Mounts**

(per TIA/EIA-222-F-1996 Criteria)

Mount Data:

(Sprint)

Mount Type:

13-ft Low Profile Platform

Platform Shape =

Flat

(User Input)

Platform Area =

 $A_{plt} := 20$

sq ft

(User Input)

(Force Coefficient Included)

Platform Area w/ Ice =

 $A_{ICE,plt} := 25$

sq ft

(User Input)

(Force Coefficient Included)

Platform Weight =

 $WT_{plt} := 1500$

lbs

(User Input)

Platform Weight w/ Ice =

 $WT_{ICE,plt} := 2000$

lbs

(User Input)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Platform Wind Force =

$$F_{plt} := q_{Z_{sprt}} G_H A_{plt} = 977$$

lbs

BLC 5**Wind Load (with ice)**

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Platform Wind Force w/ Ice =

$$F_{iplt} := q_{Z_{ICE}} q_{sprt} G_H A_{ICE,plt} = 926$$

lbs

BLC 4**Gravity Load (without ice)**

Weight of Platform =

$$WT_{plt} = 1500$$

lbs

BLC 2**Gravity Loads (ice only)**

Weight of Ice on Platform =

$$WT_{ICE,plt} - WT_{plt} = 500$$

lbs

BLC 3

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 12047.CO3

Development of Wind & Ice Load on Coax Cables

Coax Cable Data:

Coax Type =
 Shape =
 Coax Outside Diameter =
 Coax Cable Length =
 Weight of Coax per foot =
 Total Number of Coax =
 No. of Coax Projecting Outside Face of PCS Mast =

Coax aspect ratio,

Coax Cable Force Factor Coefficient =

per TIA/EIA-222-F-96 Criteria

(Bottom Mast to Sprint Antennas)

HELIAX 1-5/8"

Round (User Input)

$D_{\text{coax}} := 1.98$ in (User Input)

$L_{\text{coax}} := 31$ ft (User Input)

$Wt_{\text{coax}} := 1.04$ plf (User Input)

$N_{\text{coax}} := 30$ (User Input)

$NP_{\text{coax}} := 4$ (User Input)

$$Ar_{\text{coax}} := \frac{(L_{\text{coax}}^{12})}{D_{\text{coax}}} = 187.9$$

$Ca_{\text{coax}} = 1.2$ TIA/EIA-222-F-96 Table 3

per TIA/EIA-222-F-96 Section 2.3.2

Coax projected surface area =

$$A_{\text{coax}} := \frac{NP_{\text{coax}} \cdot D_{\text{coax}}}{12} = 0.7 \text{ ft}$$

Total Coax Wind Force =

$$F_{\text{coax}} := Ca_{\text{coax}} \cdot qz_{\text{coax}} \cdot G_H \cdot A_{\text{coax}} = 38 \text{ plf} \quad \text{BLC 5}$$

Wind Load (with ice)

per TIA/EIA-222-F-96 Section 2.3.2

Coax projected surface area w/ Ice =

$$A_{\text{ICE}_{\text{coax}}} := \frac{NP_{\text{coax}} \cdot (D_{\text{coax}} + 2 \cdot Ir)}{12} = 1 \text{ ft}$$

Total Coax Wind Force w/ Ice =

$$F_{\text{ICE}_{\text{coax}}} := Ca_{\text{coax}} \cdot qz_{\text{ICE}_{\text{coax}}} \cdot G_H \cdot A_{\text{ICE}_{\text{coax}}} = 44 \text{ plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of all cables w/o ice

$$WT_{\text{coax}} := Wt_{\text{coax}} \cdot N_{\text{coax}} = 31 \text{ plf} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Ice Area per Linear Foot =

$$A_{\text{ICE}_{\text{coax}}} := \frac{\pi}{4} \left[(D_{\text{coax}} + 2 \cdot Ir)^2 - D_{\text{coax}}^2 \right] = 3.9 \text{ sq in}$$

Ice Weight All Coax per foot =

$$WT_{\text{ICE}_{\text{coax}}} := Id \cdot \left(N_{\text{coax}} \cdot \frac{A_{\text{ICE}_{\text{coax}}}}{144} \right) = 45 \text{ plf} \quad \text{BLC 3}$$

Subject:

Load Analysis of PCS Mast on CL&P Pole # 10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L. Checked by: C.F.C.
Job No. 12047.CO3

Development of Wind & Ice Load on Coax Cables

Coax Cable Data:

Coax Type =
Shape =
Coax Outside Diameter =
Coax Cable Length =
Weight of Coax per foot =
Total Number of Coax =
No. of Coax Projecting Outside Face of PCS Mast =

per TIA/EIA-222-F-96 Criteria

(Above Sprint Antennas)

HELIAX 1-5/8"

Round (User Input)

$D_{\text{coax}} := 1.98$ in (User Input)

$L_{\text{coax}} := 31$ ft (User Input)

$Wt_{\text{coax}} := 1.04$ plf (User Input)

$N_{\text{coax}} := 12$ (User Input)

$NP_{\text{coax}} := 2$ (User Input)

Coax aspect ratio,

$$Ar_{\text{coax}} := \frac{(L_{\text{coax}} \cdot 12)}{D_{\text{coax}}} = 187.9$$

Coax Cable Force Factor Coefficient =

$Ca_{\text{coax}} = 1.2$ TIA/EIA-222-F-96 Table 3

Wind Load (without ice)

Coax projected surface area =

$$A_{\text{coax}} := \frac{NP_{\text{coax}} \cdot D_{\text{coax}}}{12} = 0.3 \text{ ft}$$

Total Coax Wind Force =

$$F_{\text{coax}} := Ca_{\text{coax}} \cdot qz_{\text{coax}} \cdot G_H \cdot A_{\text{coax}} = 19 \text{ plf} \quad \text{BLC 5}$$

Wind Load (with ice)

Coax projected surface area w/ Ice =

$$A_{\text{ICE}_{\text{coax}}} := \frac{NP_{\text{coax}} \cdot (D_{\text{coax}} + 2 \cdot I_n)}{12} = 0.5 \text{ ft}$$

Total Coax Wind Force w/ Ice =

$$F_{\text{ICE}_{\text{coax}}} := Ca_{\text{coax}} \cdot qz_{\text{ICE}_{\text{coax}}} \cdot G_H \cdot A_{\text{ICE}_{\text{coax}}} = 22 \text{ plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of all cables w/o ice

$$WT_{\text{coax}} := Wt_{\text{coax}} \cdot N_{\text{coax}} = 12 \text{ plf} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Ice Area per Linear Foot =

$$A_{\text{ICE}_{\text{coax}}} := \frac{\pi}{4} \left[(D_{\text{coax}} + 2 \cdot I_n)^2 - D_{\text{coax}}^2 \right] = 3.9 \text{ sq in}$$

Ice Weight All Coax per foot =

$$WT_{\text{ICE}_{\text{coax}}} := Id \cdot \left(N_{\text{coax}} \cdot \frac{A_{\text{ICE}_{\text{coax}}}}{144} \right) = 18 \text{ plf} \quad \text{BLC 3}$$

CEN TEK engineering, INC. Consulting Engineers 63-2 North Branford Road Branford, CT 06405 Ph. 203-488-0580 / Fax. 203-488-8587	Subject: Analysis of TIA/EIA Wind and Ice Loads for Analysis of Mast Only Tabulated Load Cases Location: Bethel, CT Date: 2/4/13	Prepared by: T.J.L. Checked by: C.F.C. Job No. 12047.CO3
Load Case	Description	
1	Self Weight (Mast)	
2	Weight of Appurtenances	
3	Weight of Ice Only on PCS Structure	
4	TIA/EIA Wind with Ice on PCS Structure	
5	TIA/EIA Wind on PCS Structure	
Footnotes: (1) PCS Structure includes: Mast and Appurtenances		

CENTEK engineering, INC.
Consulting Engineers
 63-2 North Branford Road
 Branford, CT 06405
 Ph. 203-488-0580 / Fax. 203-488-8567

Subject: Analysis of TIA/EIA Wind and Ice Loads for Analysis of Mast Only
Load Combinations Table
 Location: **Bethel, CT**
 Date: 2/4/13 Prepared by: T.J.L. Checked by: C.F.C. Job No. 12047/CO3

Load Combination	Description	Envelope Wind									
		Soullion	Factor	P-Delta	BLC	Factor	BLC	Factor	BLC	Factor	BLC
1	TIA/EIA Wind + Ice on PCS Structure	1	1	1	1	2	1	3	1	4	1
2	TIA/EIA Wind on PCS Structure	1	1	1	1	2	1	5	1		

Footnotes:
 (1) BLC = Basic Load Case
 (2) PCS Structure includes: Mast and Appurtenances

Global

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation	Yes
Include Warping	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Vertical Axis	Y
Global Member Orientation Plane	XZ

Hot Rolled Steel Code	AISC 9th: ASD
Cold Formed Steel Code	AISI 1999: ASD
Wood Code	AF&PA NDS-97: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-02
Masonry Code	ACI 530-05/08: ASD
Aluminum Code	AA ADM1-05: ASD

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	PCA Load Contour
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections	Yes
Bad Framing Warnings	No
Unused Force Warnings	Yes

Seismic Code	UBC 1997
Seismic Base Elevation (ft)	Not Entered
Ct X	.035
Ct Z	.035
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	8.5
R Z	8.5
Ct Exp. X	.75
Ct Exp. Z	.75
Ca	.36
Cv	.54
Nv	1
SD1	1
SDS	1
S1	1
Occupancy Code	4
Seismic Zone	3
Use Group	I
Use Gravity Self Wt in Diaphragm Mass	Yes
Use Deck Self Wt in Diaphragm Mass	Yes
Use Lateral Self Wt in Diaphragm Mass	Yes
Seismic Detailing Code	None
Om X	1
Om Z	1
Rho X	1
Rho Z	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1/E)	Density[k/ft...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	58	1.2
3	A992	29000	11154	.3	.65	.49	50	1.1	58	1.2
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.3	58	1.1
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.2	58	1.1
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	58	1.2

Hot Rolled Steel Design Parameters

	Label	Shape	Length	Lbyy[ft]	Lbzz[ft]	Lcomp top[ft]	Lcomp bot[ft]	Kyy	Kzz	Cm...	Cm...	Cb	y sw...	z sw...	Function
1	M1	Mast	14												Lateral
2	M2	Mast	19												Lateral

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rul...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Mast	PIPE 12.0X	Beam	Pipe	A53 Gr. B	Typical	17.9	339	339	678

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N1	N4			Mast	Beam	Pipe	A53 Gr. B	Typical
2	M2	N4	N5			Mast	Beam	Pipe	A53 Gr. B	Typical

Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
1	N1	0	0	0	0	
2	N2	0	3.25	0	0	
3	N3	0	9.42	0	0	
4	N4	0	14	0	0	
5	N5	0	33	0	0	

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footing
1	N1							
2	N2	Reaction	Reaction	Reaction				
3	N4							
4	N3	Reaction	Reaction	Reaction				

Joint Loads and Enforced Displacements

Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/f...
No Data to Print ...			

Member Point Loads (BLC 2 : Weight of Appurtenances)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	M2	Y	-.051	16.5
2	M2	Y	-.103	16.5
3	M2	Y	-.018	16.5
4	M2	Y	-.575	16.5
5	M2	Y	-.171	6.5
6	M2	Y	-1.5	6.5

Member Point Loads (BLC 3 : Weight of Ice Only on PCS Struct)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	M2	Y	-.127	16.5
2	M2	Y	-.109	16.5
3	M2	Y	-.014	16.5
4	M2	Y	-.225	16.5
5	M2	Y	-.149	6.5
6	M2	Y	-.5	6.5

Member Point Loads (BLC 4 : TIA/EIA Wind with Ice on P)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	M2	X	.965	16.5
2	M2	X	.733	16.5
3	M2	X	.112	16.5
4	M2	X	.377	16.5
5	M2	X	1.009	6.5
6	M2	X	.926	6.5

Member Point Loads (BLC 5 : TIA/EIA Wind on PCS Struct)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	M2	X	1.153	16.5
2	M2	X	.875	16.5
3	M2	X	.109	16.5
4	M2	X	.348	16.5
5	M2	X	1.211	6.5
6	M2	X	.977	6.5

Member Distributed Loads (BLC 2 : Weight of Appurtenances)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	M1	Y	-.031	-.031	0	0
2	M2	Y	-.031	-.031	0	6.5
3	M2	Y	-.012	-.012	6.5	16.5

Member Distributed Loads (BLC 3 : Weight of Ice Only on PCS Struct)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	M1	Y	-.008	-.008	0	0
2	M2	Y	-.008	-.008	0	0
3	M1	Y	-.045	-.045	0	0
4	M2	Y	-.045	-.045	0	6.5
5	M2	Y	-.018	-.018	6.5	16.5

Company : CENTEK Engineering, INC.

Designer : tjf, cfc

Job Number : 12047.CO3 - CT03XC351 CL&P Pole # 10255 - PCS Mast

Feb 4, 2013

4:14 PM

Checked By: _____

Member Distributed Loads (BLC 4 : TIA/EIA Wind with Ice on P)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
1	M1	X	.051	.051	0	0
2	M2	X	.051	.051	0	0
3	M1	X	.044	.044	0	0
4	M2	X	.044	.044	0	0
5	M2	X	.022	.022	6.5	16.5

Member Distributed Loads (BLC 5 : TIA/EIA Wind on PCS Struct)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
1	M1	X	.062	.062	0	0
2	M2	X	.062	.062	0	0
3	M1	X	.038	.038	0	0
4	M2	X	.038	.038	0	0
5	M2	X	.019	.019	6.5	16.5

Basic Load Cases

	BLC Description	Category	X Grav...	Y Grav...	Z Gravity	Joint	Point	Distrib...	Area(...	Surfac...
1	Self Weight	None		-1						
2	Weight of Appurtenances	None					6	3		
3	Weight of Ice Only on PCS Struct	None					6	5		
4	TIA/EIA Wind with Ice on P	None					6	5		
5	TIA/EIA Wind on PCS Struct	None					6	5		

Load Combinations

	Description	So...	PDelta	SRSS	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...
1	TIA/EIA Wind + Ice on PCS ...	Yes			1	1	2	1	3	1	4	1		
2	TIA/EIA Wind on PCS Struct...	Yes			1	1	2	1	5	1				
3	Self Weight													

Envelope Member Section Forces

Member	Sec	Axial[k]	LC	y Shear[k]	LC	z Shear[k]	LC	Torque[k-ft]	LC	y-y Momen...	LC	z-z Momen...	LC
1	M1	1	max	0	1	0	1	0	1	0	1	0	1
2			min	0	1	0	1	0	1	0	1	0	1
3		2	max	.411	1	-13.905	1	0	1	0	1	4.454	2
4			min	.261	2	-15.717	2	0	1	0	1	3.975	1
5		3	max	-.061	2	-14.238	1	0	1	0	1	60.076	2
6			min	-.096	1	-16.067	2	0	1	0	1	53.225	1
7		4	max	6.152	1	6.638	2	0	1	0	1	92.024	2
8			min	4.218	2	5.929	1	0	1	0	1	81.499	1
9		5	max	5.645	1	6.288	2	0	1	0	1	69.403	2
10			min	3.897	2	5.597	1	0	1	0	1	61.328	1
11	M2	1	max	5.645	1	6.288	2	0	1	0	1	69.403	2
12			min	3.897	2	5.597	1	0	1	0	1	61.328	1
13		2	max	4.957	1	5.813	2	0	1	0	1	40.663	2
14			min	3.46	2	5.146	1	0	1	0	1	35.814	1
15		3	max	2.087	1	3.207	2	0	1	0	1	20.658	2
16			min	1.41	2	2.826	1	0	1	0	1	18.149	1
17		4	max	1.617	1	2.822	2	0	1	0	1	6.339	2
18			min	1.063	2	2.479	1	0	1	0	1	5.552	1

Envelope Member Section Forces (Continued)

Member	Sec		Axial[k]	LC	y Shear[k]	LC	z Shear[k]	LC	Torque[k-ft]	LC	y-y Momen...	LC	z-z Momen...	LC
19	5	max	0	1	0	1	0	1	0	1	0	1	0	1
20		min	0	1	0	1	0	1	0	1	0	1	0	1

Envelope Member Section Stresses

Member	Sec		Axial[ksi]	LC	y Shear[...]	LC	z Shear[...]	LC	y-Top[ksi]	LC	y-Bot[ksi]	LC	z-Top[ksi]	LC	z-Bot[ksi]	LC
1	M1	1	max	0	1	0	1	0	1	0	1	0	1	0	1	1
2			min	0	1	0	1	0	1	0	1	0	1	0	1	1
3		2	max	.023	1	-1.554	1	0	1	-.897	1	1.005	2	0	1	1
4			min	.015	2	-1.756	2	0	1	-1.005	2	.897	1	0	1	1
5		3	max	-.003	2	-1.591	1	0	1	-12.011	1	13.557	2	0	1	1
6			min	-.005	1	-1.795	2	0	1	-13.557	2	12.011	1	0	1	1
7		4	max	.344	1	.742	2	0	1	-18.391	1	20.766	2	0	1	1
8			min	.236	2	.663	1	0	1	-20.766	2	18.391	1	0	1	1
9		5	max	.315	1	.703	2	0	1	-13.84	1	15.662	2	0	1	1
10			min	.218	2	.625	1	0	1	-15.662	2	13.84	1	0	1	1
11	M2	1	max	.315	1	.703	2	0	1	-13.84	1	15.662	2	0	1	1
12			min	.218	2	.625	1	0	1	-15.662	2	13.84	1	0	1	1
13		2	max	.277	1	.649	2	0	1	-8.082	1	9.176	2	0	1	1
14			min	.193	2	.575	1	0	1	-9.176	2	8.082	1	0	1	1
15		3	max	.117	1	.358	2	0	1	-4.096	1	4.662	2	0	1	1
16			min	.079	2	.316	1	0	1	-4.662	2	4.096	1	0	1	1
17		4	max	.09	1	.315	2	0	1	-1.253	1	1.43	2	0	1	1
18			min	.059	2	.277	1	0	1	-1.43	2	1.253	1	0	1	1
19		5	max	0	1	0	1	0	1	0	1	0	1	0	1	1
20			min	0	1	0	1	0	1	0	1	0	1	0	1	1

Envelope Joint Reactions

	Joint		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	N2	max	15.367	2	.918	1	0	1	0	1	0	1	0	1
2		min	13.573	1	.582	2	0	1	0	1	0	1	0	1
3	N3	max	-20.5	1	6.756	1	0	1	0	1	LOCKED		0	1
4		min	-23.055	2	4.601	2	0	1	0	1	LOCKED		0	1
5	Totals:	max	-6.927	1	7.674	1	0	1						
6		min	-7.688	2	5.184	2	0	1						

Envelope Joint Displacements

	Joint		X [in]	LC	Y [in]	LC	Z [in]	LC	X Rotation [...]	LC	Y Rotation [...]	LC	Z Rotation [...]	LC
1	N1	max	.053	2	0	2	0	1	0	1	0	1	1.354e-3	2
2		min	.047	1	0	1	0	1	0	1	0	1	1.201e-3	1
3	N2	max	0	1	0	2	0	1	0	1	0	1	1.346e-3	2
4		min	0	2	0	1	0	1	0	1	0	1	1.193e-3	1
5	N3	max	0	2	0	2	0	1	0	1	0	1	-2.777e-3	1
6		min	0	1	0	1	0	1	0	1	0	1	-3.134e-3	2
7	N4	max	.34	2	0	2	0	1	0	1	0	1	-7.774e-3	1
8		min	.301	1	0	1	0	1	0	1	0	1	-8.78e-3	2
9	N5	max	3.506	2	-.001	2	0	1	0	1	0	1	-1.384e-2	1
10		min	3.1	1	-.002	1	0	1	0	1	0	1	-1.567e-2	2

Company : CENTEK Engineering, INC.
 Designer : tjf, cfc
 Job Number : 12047.CO3 - CT03XC351 CL&P Pole # 10255 - PCS Mast

Feb 4, 2013
 4:14 PM
 Checked By: _____

Envelope AISC ASD Steel Code Checks

Member	Shape	Code Check	Loc[ft]	LC	Sh...	Loc[ft]	Fa...	Ft [ksi]	Fb y-y [ksi]	Fb.....	AS...
1	M1	PIPE_1...	.735	9.479	2	.098	9.333	225...	27.93	30.723	30...1.6...H1..
2	M2	PIPE_1...	.518	0	2	.038	0	223...	27.93	30.723	30...6...H1..

Company : CENTEK Engineering, INC.
Designer : tjf, cfc
Job Number : 12047.CO3 - CT03XC351 CL&P Pole # 10255 - PCS Mast

Feb 4, 2013

4:15 PM

Checked By: _____

Joint Reactions



	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	1	N2	13.573	.918	0	0	0	0
2	1	N3	-20.5	6.756	0	0	LOCKED	0
3	1	Totals:	-6.927	7.674	0			
4	1	COG (ft):	X: 0	Y: 19.022	Z: 0			

Company : CENTEK Engineering, INC.
Designer : tjf, cfc
Job Number : 12047.CO3 - CT03XC351 CL&P Pole # 10255 - PCS Mast

Feb 4, 2013
4:17 PM
Checked By: _____

Joint Reactions

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	2	N2	15.367	.582	0	0	0	0
2	2	N3	-23.055	4.601	0	0	LOCKED	0
3	2	Totals:	-7.688	5.184	0			
4	2	COG (ft):	X: 0	Y: 19.249	Z: 0			



Solution: Envelope
Z-direction Reaction units are k and k-ft

CEN TEK Engineering, INC.

tjl, cfc



12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast

Unity Check

Feb 4, 2013 at 4:17 PM

EIA-TIA.r3d



Loads: LC 1, TIA/EIA Wind + Ice on PCS Structure

CEN TEK Engineering, INC.

tjl, cfc




12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast

LC #1 Loads

Feb 4, 2013 at 4:15 PM

EIA-TIA.r3d



Results for LC 1, TIA/EIA Wind + Ice on PCS Structure
Z-direction Reaction units are k and k-ft

CEN TEK Engineering, INC.



tjl, cfc

12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast
LC #1 Reactions and Deflected Shape

Feb 4, 2013 at 4:16 PM

EIA-TIA.r3d



Loads: LC 2, TIA/EIA Wind on PCS Structure

CENTEK Engineering, INC.

tjl, cfc


12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast


LC #2 Loads

Feb 4, 2013 at 4:15 PM

EIA-TIA.r3d



Code Check	
No Calc	
> 1.0	
.90-1.0	
.75-.90	
.50-.75	
0-.50	



Results for LC 2, TIA/EIA Wind on PCS Structure
Z-direction Reaction units are k and k-ft

CEN TEK Engineering, INC.

tjl, cfc

12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast
LC #2 Reactions and Deflected Shape

Feb 4, 2013 at 4:17 PM

EIA-TIA.r3d

Beam: **M2**

Shape: **PIPE_12.0X**

Material: **A53 Gr. B**

Length: **19 ft**


I Joint: **N4**

J Joint: **N5**



LC 2: TIA/EIA Wind on PCS Structure

Code Check: **0.518 (bending)**

Report Based On 97 Sections




D_z _____ in





V_z _____ k

T _____ k-ft



M_y _____ k-ft

f_a _____ ksi



AISC 9th: ASD Code Check

Max Bending Check **0.518**

Location **0 ft**

Equation **H1-2**

Max Shear Check **0.038 (s)**

Location **0 ft**

Max Defl Ratio **L/72**

Compact

Allowables Increase: **1.33**

F_y **35 ksi**
 F_a **23.538 ksi**
 F_t **27.93 ksi**
 F_{by} **30.723 ksi**
 F_{bz} **30.723 ksi**
 F_{vy} **18.62 ksi**
 F_{vz} **18.62 ksi**
 C_b **1.75**

$y-y$
 C_m **.6**
 L_b **19 ft**
 KL/r **52.392**
Sway **No**
L Comp Flange **19 ft**
Torque Length **NC**

$z-z$
 C_m **.85**
 L_b **19 ft**
 KL/r **52.392**
Sway **No**

Mast Connection to CL&P Pole:


Maximum Design Reactions at Brace:

Vertical = Vert := 4.6-kips (User Input)
Horizontal = Horz := 23.1-kips (User Input)
Moment = Moment := 0 (User Input)

Bolt Data:

Bolt Grade = A325 (User Input)
Number of Bolts = $n_b := 6$ (User Input)
Bolt Diameter = $d_b := 1.0\text{in}$ (User Input)
Allowable Tensile Stress = $F_{t,all} := 44.0\text{-ksi}$ (User Input)
Allowable Shear Stress = $F_{v,all} := 21\text{-ksi}$ (User Input)
Bolt Eccentricity from C.L. Mast = $e := 12\text{-in}$ (User Input)
Horizontal Spacing Between Bolts = $S_{horz} := 7\text{-in}$ (User Input)
Vertical Spacing Between Bolts = $S_{vert} := 8\text{-in}$ (User Input)

Bolt Area = $a_b := \frac{1}{4} \cdot \pi \cdot d_b^2 = 0.785\text{-in}^2$



Check Bolt Stresses:

Wind Acting Parallel to Bolts:

Shear Force per Bolt =

$$F_{v.conn} := \frac{Vert}{n_b} = 0.767 \text{ kips}$$

Shear Stress per Bolt =

$$F_{v.act} := \frac{F_{v.conn}}{a_b} = 0.976 \text{ ksi}$$

$$Condition1 := \text{if}(F_{v.act} < F_{v.all}, "OK", "Overstressed")$$

$$Condition1 = "OK"$$

Allowable Tensile Stress Adjusted for Shear =

$$F_{t.adj} := \sqrt{F_{t.all}^2 - 4.39 \cdot F_{v.act}^2} = 43.95 \text{ ksi} \quad (\text{AISC 9th Ed. Table J3.3})$$

Moment From Mast Eccentricity =

$$M_{par} := Vert \cdot e = 55.2 \text{ kips-in}$$

Tension Force Each Bolt =

$$F_{tension.bolt} := \frac{Horz}{n_b} + \frac{M_{par}}{S_{vert} \cdot 2} = 7.3 \text{ kips}$$

Tension Stress Each Bolt =

$$F_{t.act} := \frac{F_{tension.bolt}}{a_b} = 9.3 \text{ ksi}$$

$$Condition2 := \text{if}(F_{t.act} < F_{t.adj}, "OK", "Overstressed")$$

$$Condition2 = "OK"$$

Wind Acting Perpendicular to Bolts:

Shear Force per Bolt =

$$F_{v.conn} := \frac{\sqrt{Vert^2 + Horz^2}}{n_b} = 3.926 \text{ kips}$$

Shear Stress per Bolt =

$$F_{v.act} := \frac{F_{v.conn}}{a_b} = 5 \text{ ksi}$$

$$Condition3 := \text{if}(F_{v.act} < F_{v.all}, "OK", "Overstressed")$$

$$Condition3 = "OK"$$

Allowable Tensile Stress Adjusted for Shear =

$$F_{t.adj} := \sqrt{F_{t.all}^2 - 4.39 \cdot F_{v.act}^2} = 42.74 \text{ ksi} \quad (\text{AISC 9th Ed. Table J3.3})$$

Moment from Mast Eccentricity =

$$M_{perp} := Horz \cdot e = 277 \text{ kips-in}$$

Tension Force per Bolt =

$$F_{tension.conn} := \frac{M_{perp}}{S_{horz} \cdot 3} + \frac{M_{par}}{S_{vert} \cdot 2} = 16.65 \text{ kips}$$

Tension Stress Each Bolt =

$$F_{tension.act} := \frac{F_{tension.conn}}{a_b} = 21.199 \text{ ksi}$$

$$Condition4 := \text{if}(F_{tension.act} < F_{t.adj}, "OK", "Overstressed")$$

$$Condition4 = "OK"$$

Flange Bolt and Flange Plate Analysis:**Input Data:**Mast Reactions:

Overturning Moment =	OM := 69.4-ft-kips	(Input From RisaTower)
Shear Force =	Shear := 6.3-kips	(Input From RisaTower)
Axial Force =	Axial := 3.9-kips	(Input From RisaTower)

Flange Bolt Data:

Use ASTM A325

Number of Flange Bolts =	N := 8	(User Input)
Diameter of Bolt Circle =	D _{bc} := 17-in	(User Input)
Bolt Ultimate Strength =	F _u := 120-ksi	(User Input)
Bolt Yield Strength =	F _y := 92-ksi	(User Input)
Bolt Modulus =	E := 29000-ksi	(User Input)
Diameter of Flange Bolts =	D := 1.0-in	(User Input)
Threads per Inch =	n := 8	(User Input)

Flange Plate Data:

Use ASTM A36

Plate Yield Strength =	F _{ybp} := 36-ksi	(User Input)
Flange Plate Thickness =	t _{bp} := 1.00-in	(User Input)
Flange Plate Diameter =	D _{bp} := 20-in	(User Input)
Outer Pole Diameter =	D _{pole} := 12.8-in	(User Input)

Geometric Layout Data:

Distance from Bolts to Centroid of Pole:

Radius of Bolt Circle =

$$R_{bc} := \frac{D_{bc}}{2} = 8.5\text{-in}$$

Distance to Bolts =

$$i := 1..N$$

$$d_i := \begin{cases} \theta \leftarrow 2\pi \cdot \left(\frac{i}{N}\right) \\ d \leftarrow R_{bc} \cdot \sin(\theta) \end{cases}$$

$$d_1 = 6.01\text{-in}$$

$$d_7 = -6.01\text{-in}$$

$$d_2 = 8.50\text{-in}$$

$$d_8 = -0.00\text{-in}$$

$$d_3 = 6.01\text{-in}$$

$$d_4 = 0.00\text{-in}$$

$$d_5 = -6.01\text{-in}$$

$$d_6 = -8.50\text{-in}$$

Critical Distances For Bending in Plate:

Outer Pole Radius =

$$R_{pole} := \frac{D_{pole}}{2} = 6.4\text{-in}$$

Moment Arms of Bolts about Neutral Axis =

$$MA_i := \text{if}(d_i \geq R_{pole}, d_i - R_{pole}, 0\text{in})$$

$$MA_1 = 0.00\text{-in}$$

$$MA_7 = 0.00\text{-in}$$

$$MA_2 = 2.10\text{-in}$$

$$MA_8 = 0.00\text{-in}$$

$$MA_3 = 0.00\text{-in}$$

$$MA_4 = 0.00\text{-in}$$

$$MA_5 = 0.00\text{-in}$$

$$MA_6 = 0.00\text{-in}$$

Effective Width of Flangeplate for Bending =

$$B_{eff} := .8 \cdot 2 \cdot \sqrt{\left(\frac{D_{bp}}{2}\right)^2 - \left(\frac{D_{pole}}{2}\right)^2} = 12.3\text{-in}$$

Flange Bolt Analysis:

Calculated Flange Bolt Properties:

Polar Moment of Inertia =

$$I_p := \sum_i (d_i)^2 = 289 \cdot \text{in}^2$$

Gross Area of Bolt =

$$A_g := \frac{\pi}{4} \cdot D^2 = 0.785 \cdot \text{in}^2$$

Net Area of Bolt =

$$A_n := \frac{\pi}{4} \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 = 0.606 \cdot \text{in}^2$$

Net Diameter =

$$D_n := \frac{2 \cdot \sqrt{A_n}}{\sqrt{\pi}} = 0.878 \cdot \text{in}$$

Radius of Gyration of Bolt =

$$r := \frac{D_n}{4} = 0.22 \cdot \text{in}$$

Section Modulus of Bolt =

$$S_x := \frac{\pi \cdot D_n^3}{32} = 0.066 \cdot \text{in}^3$$

Check Flange Bolt Tension Force:

Maximum Tensile Force =

$$T_{\text{Max}} := \text{OM} \cdot \frac{R_{bc}}{I_p} - \frac{\text{Axial}}{N} = 24 \cdot \text{kips}$$

Allowable Tensile Force =

$$T_{\text{ALL.Gross}} := 1.333 \cdot (0.33 \cdot A_g \cdot F_u) = 41.5 \cdot \text{kips} \quad (1.333 \text{ increase allowed per TIA/EIA})$$

Bolt Tension % of Capacity =

$$\frac{T_{\text{Max}}}{T_{\text{ALL.Gross}}} = 57.9\%$$

Condition1 =

$$\text{Condition1} := \text{if} \left(\frac{T_{\text{Max}}}{T_{\text{ALL.Gross}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Condition1 = "OK"

Flange Plate Analysis:

Force from Bolts =
$$C_i := \frac{OM \cdot d_i}{I_p} + \frac{Axial}{N}$$

$C_1 = 17.8\text{-kips}$ $C_7 = -16.8\text{-kips}$

$C_2 = 25.0\text{-kips}$ $C_8 = 0.5\text{-kips}$

$C_3 = 17.8\text{-kips}$

$C_4 = 0.5\text{-kips}$

$C_5 = -16.8\text{-kips}$

$C_6 = -24.0\text{-kips}$

Maximum Bending Stress in Plate =

$$f_{bp} := \sum_i \frac{6 \cdot C_i \cdot M A_i}{(B_{eff} t_{bp})^2} = 25.6\text{-ksi}$$

Allowable Bending Stress in Plate =

$$F_{bp} := 1.33 \cdot 0.75 \cdot F_y = 35.9\text{-ksi}$$

Plate Bending Stress % of Capacity =

$$\frac{f_{bp}}{F_{bp}} = 71.3\%$$

Condition3 =

$$\text{Condition2} := \text{if} \left(\frac{f_{bp}}{F_{bp}} < 1.00, \text{"Ok"}, \text{"Overstressed"} \right)$$

Condition2 = "Ok"

Subject:

Load Analysis of Pipe Mast on CL&P Pole #10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L Checked by: C.F.C.
 Job No. 12047.CO3

Basic Components

Heavy Wind Pressure =	p := 4.00	psf	(User Input NESC 2007 Figure 250-1 & Table 250-1)
Basic Windspeed =	V := 100	mph	(User Input NESC 2007 Figure 250-2(e))
Radial Ice Thickness =	Ir := 0.50	in	(User Input)
Radial Ice Density =	Id := 56.0	pcf	(User Input)

Factors for Extreme Wind Calculation

Elevation of Top of PCS Mast Above Grade =	TME := 170	ft	(User Input)
Multiplier Gust Response Factor =	m := 1.25		(User Input - Only for NESC Extreme wind case)
NESC Factor =	kv := 1.43		(User Input from NESC 2007 Table 250-3 equation)
Importance Factor =	I := 1.0		(User Input from NESC 2007 Section 250.C.2)

Velocity Pressure Coefficient =	$K_z := 2.01 \cdot \left(\frac{TME}{900} \right)^{\frac{2}{9.5}} = 1.415$	(NESC 2007 Table 250-2)
---------------------------------	--	-------------------------

Exposure Factor =	$E_s := 0.346 \left[\frac{33}{(0.67 \cdot TME)} \right]^{\frac{1}{7}} = 0.29$	(NESC 2007 Table 250-3)
-------------------	--	-------------------------

Response Term =	$B_s := \frac{1}{\left(1 + 0.375 \cdot \frac{TME}{220} \right)} = 0.775$	(NESC 2007 Table 250-3)
-----------------	---	-------------------------

Gust Response Factor =	$Grf := \frac{\left[1 + \left(2.7 \cdot E_s \cdot B_s \right)^{\frac{1}{2}} \right]}{kv^2} = 0.826$	(NESC 2007 Table 250-3)
------------------------	---	-------------------------

Wind Pressure =	$q_z := 0.00256 \cdot K_z \cdot V^2 \cdot Grf \cdot I = 29.9$	psf	(NESC 2007 Section 250.C.2)
-----------------	---	-----	-----------------------------

Shape Factors

NUS Design Criteria Issued April 12, 2007

Shape Factor for Round Members =	Cd _R := 1.3	(User Input)
Shape Factor for Flat Members =	Cd _F := 1.6	(User Input)
Shape Factor for Coax Cables Attached to Outside of Pole =	Cd _{coax} := 1.45	(User Input)

Overload Factors

NU Design Criteria Table

Overload Factors for Wind Loads:

NESC Heavy Loading =	2.5	(User Input)	Apply in Risa-3D Analysis
NESC Extreme Loading =	1.0	(User Input)	Apply in Risa-3D Analysis

Overload Factors for Vertical Loads:

NESC Heavy Loading =	1.5	(User Input)	Apply in Risa-3D Analysis
NESC Extreme Loading =	1.0	(User Input)	Apply in Risa-3D Analysis

Development of Wind & Ice Load on PCS Mast

PCS Mast Data:

(Pipe 12.0" SCH. 80)

Mast Shape = Round (User Input)
Mast Diameter = $D_{\text{mast}} := 12.8$ in (User Input)
Mast Length = $L_{\text{mast}} := 33$ ft (User Input)
Mast Thickness = $t_{\text{mast}} := 0.5$ in (User Input)

Wind Load (NESC Extreme)

Mast Projected Surface Area =

$$A_{\text{mast}} := \frac{D_{\text{mast}}}{12} = 1.067$$

Total Mast Wind Force =

$$qz \cdot C_d R \cdot A_{\text{mast}} = 41$$

plf **BLC 5**

Wind Load (NESE Heavy)

Mast Projected Surface Area w/ Ice =

$$A_{\text{ICE mast}} := \frac{(D_{\text{mast}} + 2 \cdot I_r)}{12} = 1.15$$

Total Mast Wind Force w/ Ice =

$$p \cdot C_d R \cdot A_{\text{ICE mast}} = 6$$

plf **BLC 4**

Gravity Loads (without ice)

Weight of the Mast =

Self Weight (Computed internally by Risa-3D)

plf **BLC 1**

Gravity Loads (ice only)

Ice Area per Linear Foot =

$$A_{\text{imast}} := \frac{\pi}{4} L \left[(D_{\text{mast}} + I_r \cdot 2)^2 - D_{\text{mast}}^2 \right] = 20.9$$

sq in

Weight of Ice on Mast =

$$W_{\text{ICE mast}} := I_d \cdot \frac{A_{\text{imast}}}{144} = 8$$

plf **BLC 3**

Development of Wind & Ice Load on Antennas

Antenna Data:

(Verizon)

Antenna Model =	Antel BXA-70063/6CF	
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 71.0$	in (User Input)
Antenna Width =	$W_{ant} := 11.2$	in (User Input)
Antenna Thickness =	$T_{ant} := 5.2$	in (User Input)
Antenna Weight =	$WT_{ant} := 17$	lbs (User Input)
Number of Antennas =	$N_{ant} := 3$	(User Input)

Wind Load (NESC Extreme)

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 5.5$$

sf

Antenna Projected Surface Area =

$$A_{ant} := SA_{ant} \cdot N_{ant} = 16.6$$

sf

Total Antenna Wind Force =

$$F_{ant} := qz \cdot C_d \cdot F \cdot A_{ant} \cdot m = 992$$

lbs **BLC 5**

Wind Load (NESC Heavy)

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 6.1$$

sf

Antenna Projected Surface Area w/ Ice =

$$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 18.3$$

sf

Total Antenna Wind Force w/ Ice =

$$F_{iceant} := p \cdot C_d \cdot F \cdot A_{ICEant} = 117$$

lbs **BLC 4**

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 51$$

lbs **BLC 2**

Gravity Load (ice only)

Volume of Each Antenna =

$$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 4135$$

cu in

Volume of Ice on Each Antenna =

$$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1311$$

cu in

Weight of Ice on Each Antenna =

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_{ice} = 42$$

lbs

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 127$$

lbs **BLC 3**

Development of Wind & Ice Load on Antennas

Antenna Data:

(Verizon)

Antenna Model =	Andrew DBXNH-6565A-VTM
Antenna Shape =	Flat (User Input)
Antenna Height =	$L_{ant} := 50.91$ in (User Input)
Antenna Width =	$W_{ant} := 11.85$ in (User Input)
Antenna Thickness =	$T_{ant} := 7.1$ in (User Input)
Antenna Weight =	$WT_{ant} := 34.17$ lbs (User Input)
Number of Antennas =	$N_{ant} := 3$ (User Input)

Wind Load (NESC Extreme)

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 4.2 \quad sf$$

Antenna Projected Surface Area =

$$A_{ant} := SA_{ant} \cdot N_{ant} = 12.6 \quad sf$$

Total Antenna Wind Force =

$$F_{ant} := qz \cdot C_d \cdot F \cdot A_{ant} = 752 \quad lbs \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 4.6 \quad sf$$

Antenna Projected Surface Area w/ Ice =

$$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 13.9 \quad sf$$

Total Antenna Wind Force w/ Ice =

$$F_{ant} := p \cdot C_d \cdot F \cdot A_{ICEant} = 89 \quad lbs \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 103 \quad lbs \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each Antenna =

$$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 4283 \quad cu \text{ in}$$

Volume of Ice on Each Antenna =

$$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1120 \quad cu \text{ in}$$

Weight of Ice on Each Antenna =

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 36 \quad lbs$$

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 109 \quad lbs \quad \text{BLC 3}$$

Subject:

Load Analysis of Pipe Mast on CL&P Pole #10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L Checked by: C.F.C.
 Job No. 12047.CO3

Development of Wind & Ice Load on Diplexers

Diplexer Data:

(Verizon)

Diplexer Model =	RFS FD9R6004/2C-3L Diplexer		
Diplexer Shape =	Flat		(User Input)
Diplexer Height =	$L_{dplx} := 5.8$	in	(User Input)
Diplexer Width =	$W_{dplx} := 6.5$	in	(User Input)
Diplexer Thickness =	$T_{dplx} := 1.5$	in	(User Input)
Diplexer Weight =	$WT_{dplx} := 3$	lbs	(User Input)
Number of Diplexers =	$N_{dplx} := 6$		(User Input)

Wind Load (NESC Extreme)

Assumes Maximum Possible Wind Pressure Applied to all Diplexers Simultaneously

Surface Area for One Diplexer =

$$SA_{dplx} := \frac{L_{dplx} \cdot W_{dplx}}{144} = 0.3 \quad sf$$

Diplexer Projected Surface Area =

$$A_{dplx} := SA_{dplx} \cdot N_{dplx} = 1.6 \quad sf$$

Total Diplexer Wind Force =

$$F_{dplx} := qz \cdot C_d \cdot A_{dplx} \cdot m = 94 \quad lbs \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

Assumes Maximum Possible Wind Pressure Applied to all Diplexers Simultaneously

Surface Area for One Diplexer w/ Ice =

$$SA_{ICEdplx} := \frac{(L_{dplx} + 1) \cdot (W_{dplx} + 1)}{144} = 0.4 \quad sf$$

Diplexer Projected Surface Area w/ Ice =

$$A_{ICEdplx} := SA_{ICEdplx} \cdot N_{dplx} = 2.1 \quad sf$$

Total Diplexer Wind Force w/ Ice =

$$F_{dplx} := p \cdot C_d \cdot A_{ICEdplx} = 14 \quad lbs \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Diplexers =

$$WT_{dplx} \cdot N_{dplx} = 18 \quad lbs \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each Diplexer =

$$V_{dplx} := L_{dplx} \cdot W_{dplx} \cdot T_{dplx} = 57 \quad cu \text{ in}$$

Volume of Ice on Each Diplexer =

$$V_{ice} := (L_{dplx} + 1) \cdot (W_{dplx} + 1) \cdot (T_{dplx} + 1) - V_{dplx} = 71 \quad cu \text{ in}$$

Weight of Ice on Each Diplexer =

$$W_{ICEdplx} := \frac{V_{ice}}{1728} \cdot Id = 2 \quad lbs$$

Weight of Ice on All Diplexers =

$$W_{ICEdplx} \cdot N_{dplx} = 14 \quad lbs \quad \text{BLC 3}$$

Subject:

Load Analysis of Pipe Mast on CL&P Pole #10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L Checked by: C.F.C.
Job No. 12047.CO3

Development of Wind & Ice Load on Mounts

Mount Data:

(Verizon)

Mount Type =

Dual Standoff Mount
B1827 w/ 6 Pipe Mounts

Platform Shape =

Flat (User Input)

Platform Area =

$A_{plt} := 7$ sq ft (User Input) (Shape Factor Included)

Platform Area w/ Ice =

$A_{ICEplt} := 10$ sq ft (User Input) (Shape Factor Included)

Platform Weight =

$WT_{plt} := 575$ lbs (User Input)

Platform Weight w/ Ice =

$WT_{ICEplt} := 800$ lbs (User Input)

Wind Load (NESC Extreme)

Total Platform Wind Force =

$F_{plt} := qz \cdot A_{plt} \cdot m = 262$ lbs **BLC 5**

Wind Load (NESC Heavy)

Total Platform Wind Force w/ Ice =

$F_{iplt} := p \cdot A_{ICEplt} = 40$ lbs **BLC 4**

Gravity Load (without ice)

Weight of Platform =

$WT_{plt} = 575$ lbs **BLC 2**

Gravity Load (ice only)

Weight of Ice on Platform =

$WT_{ICEplt} - WT_{plt} = 225$ lbs **BLC 3**

Subject:

Load Analysis of Pipe Mast on CL&P Pole #10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L Checked by: C.F.C.
 Job No. 12047.CO3

Development of Wind & Ice Load on Antennas

Antenna Data:

Antenna Model =	RFS APX VSPP18-C	
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 72$	in (User Input)
Antenna Width =	$W_{ant} := 11.8$	in (User Input)
Antenna Thickness =	$T_{ant} := 7$	in (User Input)
Antenna Weight =	$WT_{ant} := 57$	lbs (User Input)
Number of Antennas =	$N_{ant} := 3$	(User Input)

Wind Load (NESC Extreme)

Assumes Maximum Possible Wind Pressure Applied to all Antennas Simultaneously

Surface Area for One Antenna =

$$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 5.9 \quad sf$$

Antenna Projected Surface Area =

$$A_{ant} := SA_{ant} \cdot N_{ant} = 17.7 \quad sf$$

Total Antenna Wind Force =

$$F_{ant} := qz \cdot C_d \cdot F \cdot A_{ant} \cdot m = 1059 \quad lbs \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

Assumes Maximum Possible Wind Pressure Applied to all Antennas Simultaneously

Surface Area for One Antenna w/ Ice =

$$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 6.5 \quad sf$$

Antenna Projected Surface Area w/ Ice =

$$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 19.5 \quad sf$$

Total Antenna Wind Force w/ Ice =

$$F_{ant} := p \cdot C_d \cdot F \cdot A_{ICEant} = 125 \quad lbs \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 171 \quad lbs \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each Antenna =

$$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 5947 \quad cu \text{ in}$$

Volume of Ice on Each Antenna =

$$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1528 \quad cu \text{ in}$$

Weight of Ice on Each Antenna =

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 50 \quad lbs$$

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 149 \quad lbs \quad \text{BLC 3}$$

Subject:

Load Analysis of Pipe Mast on CL&P Pole #10255

Location:

Bethel, CT

Rev. 0: 2/4/13

Prepared by: T.J.L Checked by: C.F.C.
Job No. 12047.CO3

Development of Wind & Ice Load on Mounts

Mount Data:

(Sprint)

Mount Type = 13-ft Low Profile Platform

Platform Shape = Flat (User Input)

Platform Area = $A_{plt} := 20$ sq ft (User Input) (Shape Factor Included)

Platform Area w/ Ice = $A_{ICEplt} := 25$ sq ft (User Input) (Shape Factor Included)

Platform Weight = $WT_{plt} := 1500$ lbs (User Input)

Platform Weight w/ Ice = $WT_{ICEplt} := 2000$ lbs (User Input)

Wind Load (NESC Extreme)

Total Platform Wind Force = $F_{plt} := qz \cdot C_d F \cdot A_{plt} \cdot m = 1197$ lbs **BLC 5**

Wind Load (NESC Heavy)

Total Platform Wind Force w/ Ice = $F_{plt} := p \cdot C_d F \cdot A_{ICEplt} = 160$ lbs **BLC 4**

Gravity Load (without ice)

Weight of Platform = $WT_{plt} = 1500$ lbs **BLC 2**

Gravity Load (ice only)

Weight of Ice on Platform = $WT_{ICEplt} - WT_{plt} = 500$ lbs **BLC 3**

Development of Wind & Ice Load on Coax Cables

Coax Cable Data:

(Bottom Mast to Sprint Antennas / Below Top of CL&P Pole)

Coax Type =	HELIAX 1-5/8"	
Shape =	Round	(User Input)
Coax Outside Diameter =	$D_{coax} := 1.98$	in (User Input)
Coax Cable Length =	$L_{coax} := 31$	ft (User Input)
Weight of Coax per foot =	$Wt_{coax} := 1.04$	plf (User Input)
Total Number of Coax =	$N_{coax} := 30$	(User Input)
No. of Coax Projecting Outside Face of PCS Mast =	$NP_{coax} := 4$	(User Input)

Wind Load (NESC Extreme)

Coax projected surface area =

$$A_{coax} := \frac{(NP_{coax} D_{coax})}{12} = 0.7 \quad \text{sf/ft}$$

Total Coax Wind Force (Above NU Structure) =

$$F_{coax} := qz \cdot C_d \cdot A_{coax} = 29 \quad \text{plf} \quad \text{BLC 5}$$

Total Coax Wind Force (Below NU Structure) =

$$F_{coax} := qz \cdot C_d \cdot A_{coax} \cdot m = 36 \quad \text{plf} \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

Coax projected surface area w/ Ice =

$$AICE_{coax} := \frac{NP_{coax} (D_{coax} + 2 \cdot Ir)}{12} = 1 \quad \text{sf/ft}$$

Total Coax Wind Force w/ Ice =

$$F_{i_{coax}} := p \cdot C_d \cdot AICE_{coax} = 6 \quad \text{plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of all cables w/o ice

$$WT_{coax} := Wt_{coax} \cdot N_{coax} = 31 \quad \text{plf} \quad \text{BLC 2}$$

Gravity Load (ice only)

Ice Area per Linear Foot =

$$A_{i_{coax}} := \frac{\pi}{4} L \left[(D_{coax} + 2 \cdot Ir)^2 - D_{coax}^2 \right] = 3.9 \quad \text{sq in}$$

Ice Weight All Coax per foot =

$$WT_{i_{coax}} := N_{coax} \cdot Id \cdot \frac{A_{i_{coax}}}{144} = 45 \quad \text{plf} \quad \text{BLC 3}$$

Development of Wind & Ice Load on Coax Cables

Coax Cable Data:

(Above Sprint Antennas)

Coax Type =	HELIAX 1-5/8"	
Shape =	Round	(User Input)
Coax Outside Diameter =	$D_{coax} := 1.98$	in (User Input)
Coax Cable Length =	$L_{coax} := 31$	ft (User Input)
Weight of Coax per foot =	$Wt_{coax} := 1.04$	plf (User Input)
Total Number of Coax =	$N_{coax} := 12$	(User Input)
No. of Coax Projecting Outside Face of PCS Mast =	$NP_{coax} := 2$	(User Input)

Wind Load (NESC Extreme)

Coax projected surface area =

$$A_{coax} := \frac{(NP_{coax} D_{coax})}{12} = 0.3 \quad \text{sf/ft}$$

Total Coax Wind Force (Above NU Structure) =

$$F_{coax} := qz \cdot C_d \cdot A_{coax} \cdot m = 18 \quad \text{plf} \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

Coax projected surface area w/ Ice =

$$AICE_{coax} := \frac{NP_{coax} (D_{coax} + 2 \cdot Ir)}{12} = 0.5 \quad \text{sf/ft}$$

Total Coax Wind Force w/ Ice =

$$F_{i_{coax}} := p \cdot C_d \cdot AICE_{coax} = 3 \quad \text{plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of all cables w/o ice

$$WT_{coax} := Wt_{coax} \cdot N_{coax} = 12 \quad \text{plf} \quad \text{BLC 2}$$

Gravity Load (ice only)

Ice Area per Linear Foot =

$$Ai_{coax} := \frac{\pi}{4} \left[(D_{coax} + 2 \cdot Ir)^2 - D_{coax}^2 \right] = 3.9 \quad \text{sq in}$$

Ice Weight All Coax per foot =

$$WTi_{coax} := N_{coax} \cdot Id \cdot \frac{Ai_{coax}}{144} = 18 \quad \text{plf} \quad \text{BLC 3}$$

CENTEK engineering, INC. Consulting Engineers 63-2 North Branford Road Branford, CT 06405 Ph. 203-488-0580 / Fax. 203-488-8587	Subject: Analysis of NESC Heavy Wind and NESC Extreme Wind for Obtaining PCS Structure Reactions Applied to CL&P Pole Tabulated Load Cases Location: Bethel, CT Date: 2/4/13	Prepared by: T.J.L.	Checked by: C.F.C.	Job No. 12047.CO3
Load Case	Description			
1	Self Weight (PCS Mast)			
2	Weight of Appurtenances			
3	Weight of Ice Only on PCS Structure ⁽¹⁾			
4	NESC Heavy Wind on PCS Structure ⁽¹⁾			
5	NESC Extreme Wind on PCS Structure ⁽¹⁾			
Footnotes: (1) PCS Structure includes: Mast and Appurtenances				

CEN TEK engineering, INC. Consulting Engineers 63-2 North Brantford Road Brantford, CT 06405 Ph. 203-488-0580 / Fax. 203-488-8587		Subject: Analysis of NESC Heavy Wind and NESC Extreme Wind for Obtaining PCS Structure Reactions Applied to CL&P Pole Load Combinations Table Location: Bethel, CT Date: 2/4/13 Prepared by: T.J.L. Checked by: C.F.C. Job No. 12047.CO3									
Load Combination	Description	Envelope Wind									
		Soultion	Factor	P-Delta	BLC	Factor	BLC	Factor	BLC	Factor	BLC
1	NESC Heavy Wind on PCS Structure	1			1	1.5	2	1.5	3	1.5	4
2	NESC Extreme Wind on PCS Structure	1			1	1	2	1	5	1	
Footnotes: (1) BLC = Basic Load Case (2) PCS Structure includes: Mast and Appurtenances											

Global

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation	Yes
Include Warping	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Vertical Axis	Y
Global Member Orientation Plane	XZ

Hot Rolled Steel Code	AISC 9th: ASD
Cold Formed Steel Code	AISI 1999: ASD
Wood Code	AF&PA NDS-97: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-02
Masonry Code	ACI 530-05/08: ASD
Aluminum Code	AA ADM1-05: ASD

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	PCA Load Contour
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections	Yes
Bad Framing Warnings	No
Unused Force Warnings	Yes

Seismic Code	UBC 1997
Seismic Base Elevation (ft)	Not Entered
Ct X	.035
Ct Z	.035
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	8.5
R Z	8.5
Ct Exp. X	.75
Ct Exp. Z	.75
Ca	.36
Cv	.54
Nv	1
SD1	1
SDS	1
S1	1
Occupancy Code	4
Seismic Zone	3
Use Group	I
Use Gravity Self Wt in Diaphragm Mass	Yes
Use Deck Self Wt in Diaphragm Mass	Yes
Use Lateral Self Wt in Diaphragm Mass	Yes
Seismic Detailing Code	None
Om X	1
Om Z	1
Rho X	1
Rho Z	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1/E...)	Density[k/ft...]	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	58	1.2
3	A992	29000	11154	.3	.65	.49	50	1.1	58	1.2
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.3	58	1.1
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.2	58	1.1
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	58	1.2

Hot Rolled Steel Design Parameters

	Label	Shape	Length...	Lbyy[ft]	Lbzz[ft]	Lcomp top[ft]	Lcomp bot[ft]	Kyy	Kzz	Cm-...	Cm-...	Cb	y sw...	z sw...	Function
1	M1	Mast	14												Lateral
2	M2	Mast	19												Lateral

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rul...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Mast	PIPE 12.0X	Beam	Pipe	A53 Gr. B	Typical	17.9	339	339	678

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N1	N4			Mast	Beam	Pipe	A53 Gr. B	Typical
2	M2	N4	N5			Mast	Beam	Pipe	A53 Gr. B	Typical

Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
1	N1	0	0	0	0	
2	N2	0	3.25	0	0	
3	N3	0	9.42	0	0	
4	N4	0	14	0	0	
5	N5	0	33	0	0	

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot. [k-ft/rad]	Y Rot. [k-ft/rad]	Z Rot. [k-ft/rad]	Footing
1	N1							
2	N2	Reaction	Reaction	Reaction				
3	N3	Reaction	Reaction	Reaction				
4	N4							

Joint Loads and Enforced Displacements

Joint Label	L,D,M	Direction	Magnitude(k,k-ft), (in,rad), (k*s^2/f...
No Data to Print ...			

Member Point Loads (BLC 2 : Weight of Appurtenances)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M2	Y	-.051	16.5
2	M2	Y	-.103	16.5
3	M2	Y	-.018	16.5
4	M2	Y	-.575	16.5
5	M2	Y	-.171	6.5
6	M2	Y	-1.5	6.5

Member Point Loads (BLC 3 : Weight of Ice Only on PCS Struct)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M2	Y	-.127	16.5
2	M2	Y	-.109	16.5
3	M2	Y	-.014	16.5
4	M2	Y	-.225	16.5
5	M2	Y	-.149	6.5
6	M2	Y	-.5	6.5

Member Point Loads (BLC 4 : NESC Heavy Wind on PCS Str)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M2	X	.117	16.5
2	M2	X	.089	16.5
3	M2	X	.014	16.5
4	M2	X	.04	16.5
5	M2	X	.125	6.5
6	M2	X	.16	6.5

Member Point Loads (BLC 5 : NESC Extreme Wind on PCS S)

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	M2	X	.992	16.5
2	M2	X	.752	16.5
3	M2	X	.094	16.5
4	M2	X	.262	16.5
5	M2	X	1.059	6.5
6	M2	X	1.197	6.5

Member Distributed Loads (BLC 2 : Weight of Appurtenances)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
1	M1	Y	.031	.031	0	0
2	M2	Y	.031	.031	0	6.5
3	M2	Y	.012	.012	6.5	16.5

Member Distributed Loads (BLC 3 : Weight of Ice Only on PCS Struct)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
1	M1	Y	-.008	-.008	0	0
2	M2	Y	-.008	-.008	0	0
3	M1	Y	-.045	-.045	0	0
4	M2	Y	-.045	-.045	0	6.5
5	M2	Y	-.018	-.018	6.5	16.5

Member Distributed Loads (BLC 4 : NESC Heavy Wind on PCS Str)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
1	M1	X	.006	.006	0	0
2	M2	X	.006	.006	0	0
3	M1	X	.006	.006	0	0
4	M2	X	.006	.006	0	6.5
5	M2	X	.003	.003	6.5	16.5

Member Distributed Loads (BLC 5 : NESC Extreme Wind on PCS S)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
1	M1	X	.041	.041	0	0
2	M2	X	.041	.041	0	0
3	M1	X	.029	.029	0	0
4	M2	X	.036	.036	0	6.5
5	M2	X	.018	.018	6.5	16.5

Basic Load Cases

	BLC Description	Category	X Grav...	Y Grav...	Z Gravity	Joint	Point	Distrib...	Area(...	Surfac...
1	Self Weight (PCS Mast)	None		-1						
2	Weight of Appurtenances	None					6	3		
3	Weight of Ice Only on PCS Struct	None					6	5		
4	NESC Heavy Wind on PCS Str	None					6	5		
5	NESC Extreme Wind on PCS S	None					6	5		

Load Combinations

	Description	So...	PDelta	SRSS	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...	BLCFac...
1	NESC Heavy Wind on PCS ...	Yes			1	1.5	2	1.5	3	1.5	4	2.5					
2	NESC Extreme Wind on PCS...	Yes			1	1	2	1	5	1							
3	Self Weight				1	1											

Envelope Member Section Forces

	Member	Sec		Axial[k]	LC	y Shear[k]	LC	z Shear[k]	LC	Torque[k-ft]	LC	y-y Momen...	LC	z-z Momen...	LC
1	M1	1	max	0	1	0	1	0	1	0	1	0	1	0	1
2			min	0	1	0	1	0	1	0	1	0	1	0	1
3		2	max	.353	1	-4.41	1	0	1	0	1	0	1	3.775	2
4			min	.085	2	-13.63	2	0	1	0	1	0	1	1.26	1
5		3	max	-.02	2	-4.515	1	0	1	0	1	0	1	51.91	2
6			min	-.083	1	-13.875	2	0	1	0	1	0	1	16.879	1
7		4	max	7.939	1	5.794	2	0	1	0	1	0	1	79.395	2
8			min	3.358	2	1.925	1	0	1	0	1	0	1	25.797	1
9		5	max	7.503	1	5.549	2	0	1	0	1	0	1	59.545	2
10			min	3.254	2	1.82	1	0	1	0	1	0	1	19.243	1
11	M2	1	max	7.503	1	5.549	2	0	1	0	1	0	1	59.545	2
12			min	3.254	2	1.82	1	0	1	0	1	0	1	19.243	1
13		2	max	6.913	1	5.183	2	0	1	0	1	0	1	34.056	2
14			min	3.112	2	1.678	1	0	1	0	1	0	1	10.937	1
15		3	max	2.878	1	2.615	2	0	1	0	1	0	1	16.991	2
16			min	1.242	2	.845	1	0	1	0	1	0	1	5.411	1
17		4	max	2.344	1	2.335	2	0	1	0	1	0	1	5.233	2
18			min	1.009	2	.738	1	0	1	0	1	0	1	1.651	1

Envelope Member Section Forces (Continued)

Member	Sec		Axial[k]	LC	y Shear[k]	LC	z Shear[k]	LC	Torque[k-ft]	LC	y-y Momen...	LC	z-z Momen...	LC
19	5	max	0	1	0	1	0	1	0	1	0	1	0	1
20		min	0	1	0	1	0	1	0	1	0	1	0	1

Envelope Member Section Stresses

Member	Sec		Axial[ksi]	LC	y Shear[...]	LC	z Shear[...]	LC	y-Top[ksi]	LC	y-Bot[ksi]	LC	z-Top[ksi]	LC	z-Bot[ksi]	LC
1	M1	1	max	0	1	0	1	0	1	0	1	0	1	0	1	0
2			min	0	1	0	1	0	1	0	1	0	1	0	1	0
3		2	max	.02	1	-.493	1	0	1	-.284	1	.852	2	0	1	0
4			min	.005	2	-1.523	2	0	1	-.852	2	.284	1	0	1	0
5		3	max	-.001	2	-.504	1	0	1	-3.809	1	11.714	2	0	1	0
6			min	-.005	1	-1.55	2	0	1	-11.714	2	3.809	1	0	1	0
7		4	max	.444	1	.647	2	0	1	-5.821	1	17.917	2	0	1	0
8			min	.188	2	.215	1	0	1	-17.917	2	5.821	1	0	1	0
9		5	max	.419	1	.62	2	0	1	-4.342	1	13.437	2	0	1	0
10			min	.182	2	.203	1	0	1	-13.437	2	4.342	1	0	1	0
11	M2	1	max	.419	1	.62	2	0	1	-4.342	1	13.437	2	0	1	0
12			min	.182	2	.203	1	0	1	-13.437	2	4.342	1	0	1	0
13		2	max	.386	1	.579	2	0	1	-2.468	1	7.685	2	0	1	0
14			min	.174	2	.187	1	0	1	-7.685	2	2.468	1	0	1	0
15		3	max	.161	1	.292	2	0	1	-1.221	1	3.834	2	0	1	0
16			min	.069	2	.094	1	0	1	-3.834	2	1.221	1	0	1	0
17		4	max	.131	1	.261	2	0	1	-.373	1	1.181	2	0	1	0
18			min	.056	2	.082	1	0	1	-1.181	2	.373	1	0	1	0
19		5	max	0	1	0	1	0	1	0	1	0	1	0	1	0
20			min	0	1	0	1	0	1	0	1	0	1	0	1	0

Envelope Joint Reactions

	Joint		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	N2	max	13.385	2	.788	1	0	1	0	1	0	1	0	1
2		min	4.305	1	.189	2	0	1	0	1	0	1	0	1
3	N3	max	-6.545	1	8.457	1	0	1	0	1	LOCKED		0	1
4		min	-19.914	2	3.483	2	0	1	0	1	LOCKED		0	1
5	Totals:	max	-2.24	1	9.245	1	0	1						
6		min	-6.529	2	3.673	2	0	1						

Envelope Joint Displacements

	Joint		X [in]	LC	Y [in]	LC	Z [in]	LC	X Rotation...	LC	Y Rotation...	LC	Z Rotation...	LC
1	N1	max	.046	2	0	2	0	1	0	1	0	1	1.167e-3	2
2		min	.015	1	0	1	0	1	0	1	0	1	3.808e-4	1
3	N2	max	0	1	0	2	0	1	0	1	0	1	1.162e-3	2
4		min	0	2	0	1	0	1	0	1	0	1	3.783e-4	1
5	N3	max	0	2	0	2	0	1	0	1	0	1	-8.807e-4	1
6		min	0	1	0	1	0	1	0	1	0	1	-2.707e-3	2
7	N4	max	.293	2	0	2	0	1	0	1	0	1	-2.458e-3	1
8		min	.095	1	0	1	0	1	0	1	0	1	-7.571e-3	2
9	N5	max	3.001	2	-.001	2	0	1	0	1	0	1	-4.313e-3	1
10		min	.971	1	-.003	1	0	1	0	1	0	1	-1.335e-2	2

Company : CENTEK Engineering, Inc.
 Designer : tjf, cfc
 Job Number : 12047.CO3 - CT03XC351 CL&P Pole # 10255 - PCS Mast

Feb 13, 2013
 1:27 PM
 Checked By: _____

Envelope AISC ASD Steel Code Checks

Member	Shape	Code Check	Loc[ft]	LC	Sh...	Loc[ft]	Fa...	Ft [ksi]	Fb y-y [ksi]	Fb.....	AS...
1	M1	PIPE_1...	.843	9.479	2	.112	9.333	21	23.1	23.1	H1...
2	M2	PIPE_1...	.590	0	2	.044	0	21	23.1	23.1	H1...

Company : CENTEK Engineering, Inc.
Designer : tjf, cfc
Job Number : 12047.CO3 - CT03XC351 CL&P Pole # 10255 - PCS Mast

Feb 13, 2013

1:29 PM

Checked By: _____

Joint Reactions

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	1	N2	4.305	.788	0	0	0	0
2	1	N3	-6.545	8.457	0	0	LOCKED	0
3	1	Totals:	-2.24	9.245	0			
4	1	COG (ft):	X: 0	Y: 20.578	Z: 0			

Company : CENTEK Engineering, Inc.
Designer : tjf, cfc
Job Number : 12047.CO3 - CT03XC351 CL&P Pole # 10255 - PCS Mast


Feb 13, 2013

1:29 PM

Checked By: _____

Joint Reactions

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	2	N2	13.385	.189	0	0	0	0
2	2	N3	-19.914	3.483	0	0	LOCKED	0
3	2	Totals:	-6.529	3.673	0			
4	2	COG (ft):	X: 0	Y: 21.955	Z: 0			



Loads: LC 1, NESC Heavy Wind on PCS Structure

CEN TEK Engineering, Inc.

tjl, cfc


12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast

LC #1 Loads

Feb 13, 2013 at 1:27 PM

NESC.r3d



Results for LC 1, NESC Heavy Wind on PCS Structure
Z-direction Reaction units are k and k-ft

CEN TEK Engineering, Inc.

tjl, cfc


12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast

LC #1 Reactions

Feb 13, 2013 at 1:28 PM

NESC.r3d



Loads: LC 2, NESC Extreme Wind on PCS Structure

CEN TEK Engineering, Inc.

tjl, cfc



12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast

LC #2 Loads

Feb 13, 2013 at 1:28 PM

NESC.r3d



Results for LC 2, NESC Extreme Wind on PCS Structure
Z-direction Reaction units are k and k-ft

CEN TEK Engineering, Inc.

tjl, cfc

12047.CO3 - CT03XC351

CL&P Pole # 10255 - PCS Mast

LC #2 Reactions

Feb 13, 2013 at 1:29 PM

NESC.r3d

Coax Cable on CL&P Pole

Distance Between Coax Cable Attach Points =

Coaxial Cable Span =

$$\text{CoaxSpan} := \begin{pmatrix} 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \\ 10 \end{pmatrix} \cdot \text{ft} \quad (\text{User Input})$$

Notes:

1. Cables attached to Pole @ 5-ft AGL
2. Cables attached to PCS Mast @ 137-ft AGL

Diameter of Coax Cable =

$$D_{\text{coax1}} := 1.98 \cdot \text{in} \quad (\text{User Input})$$

Weight of Coax Cable =

$$W_{\text{coax1}} := 1.04 \cdot \text{plf} \quad (\text{User Input})$$

Number of Coax Cables =

$$N_{\text{coax1}} := 30 \quad (\text{User Input}) \quad (12 \text{ Verizon and } 18 \text{ Sprint})$$

Number of Projected Coax Cables =

$$NP_{\text{coax1}} := 3 \quad (\text{User Input})$$

Extreme Wind Pressure =

$$qz := 29.9 \cdot \text{psf} \quad (\text{User Input})$$

Heavy Wind Pressure =

$$p := 4 \cdot \text{psf} \quad (\text{User Input})$$

Radial Ice Thickness =

$$Ir := 0.5 \cdot \text{in} \quad (\text{User Input})$$

Radial Ice Density =

$$Id := 56 \cdot \text{pcf} \quad (\text{User Input})$$

Shape Factor =

$$Cd_{\text{coax}} := 1.45 \quad (\text{User Input})$$

Overload Factor for NESC Heavy Wind Load =

$$OF_{HW} := 2.5 \quad (\text{User Input})$$

Overload Factor for NESC Extreme Wind Load =

$$OF_{EW} := 1.0 \quad (\text{User Input})$$

Overload Factor for NESC Heavy Vertical Load =

$$OF_{HV} := 1.5 \quad (\text{User Input})$$

Overload Factor for NESC Extreme Vertical Load =

$$OF_{EV} := 1.0 \quad (\text{User Input})$$

Wind Area with Ice =

$$A_{\text{ice}} := (NP_{\text{coax1}} \cdot D_{\text{coax1}} + 2 \cdot Ir) = 6.94 \cdot \text{in}$$

Wind Area without Ice =

$$A := (NP_{\text{coax1}} \cdot D_{\text{coax1}}) = 5.94 \cdot \text{in}$$

Ice Area per Liner Ft =

$$A_{i\text{coax1}} := \frac{\pi}{4} \cdot \left[(D_{\text{coax1}} + 2 \cdot Ir)^2 - D_{\text{coax1}}^2 \right] = 0.027 \cdot \text{ft}^2$$

Weight of Ice on All Coax Cables =

$$W_{\text{ice}} := A_{i\text{coax1}} \cdot Id \cdot N_{\text{coax1}} = 45 \cdot \text{plf}$$

Heavy Vertical Load =

$$\text{HeavyVert} := \overrightarrow{\left[(N_{\text{coax1}} \cdot W_{\text{coax1}} + W_{\text{ice}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{HV}} \right]}$$

Heavy Transverse Load =

$$\text{HeavyTrans} := \overrightarrow{(p \cdot A_{\text{ice}} \cdot C_{d_{\text{coax}}} \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{HW}})}$$

$$\text{HeavyVert} = \begin{pmatrix} 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \\ 1150 \end{pmatrix} \text{ lb}$$

$$\text{HeavyTrans} = \begin{pmatrix} 84 \\ 84 \\ 84 \\ 84 \\ 84 \\ 84 \\ 84 \\ 84 \\ 84 \\ 84 \\ 84 \\ 84 \end{pmatrix} \text{ lb}$$

Extreme Vertical Load =


$$\text{ExtremeVert} := \overrightarrow{\left[(N_{\text{coax1}} \cdot W_{\text{coax1}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{EV}} \right]}$$

Extreme Transverse Load =

$$\text{ExtremeTrans} := \overrightarrow{\left[(qz \cdot A \cdot C_{d_{\text{coax}}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{EW}} \right]}$$

$$\text{ExtremeVert} = \begin{pmatrix} 312 \\ 312 \\ 312 \\ 312 \\ 312 \\ 312 \\ 312 \\ 312 \\ 312 \\ 312 \\ 312 \\ 312 \end{pmatrix} \text{ lb}$$

$$\text{ExtremeTrans} = \begin{pmatrix} 215 \\ 215 \\ 215 \\ 215 \\ 215 \\ 215 \\ 215 \\ 215 \\ 215 \\ 215 \\ 215 \\ 215 \end{pmatrix} \text{ lb}$$



Project Name : 12047.CO3 - Bethel, CT
 Project Notes: CL&P - Str # 10255/ Sprint CT03XC351
 Project File : J:\Jobs\1204700.WI\CO3 - CT03XC351\Calcs\PLS-Pole\cl&p structure # 10255.pol
 Date run : 9:50:35 AM Wednesday, February 13, 2013
 by : PLS-POLE Version 11.11
 Licensed to : Centek Engineering Inc

Successfully performed nonlinear analysis

The model has 0 warnings.

Loads from file: j:\jobs\1204700.wi\co3 - ct03xc351\calcs\pls-pole\cl&p #10255.lca

*** Analysis Results:

Maximum element usage is 97.50% for Base Plate "10255" in load case "NESC Extreme"
 Maximum insulator usage is 25.27% for Clamp "Clamp9" in load case "NESC Extreme"

Summary of Joint Support Reactions For All Load Cases:

Load Case	Joint Label	Long. Force (kips)	Trans. Force (kips)	Vert. Force (kips)	Shear Force (kips)	Trans. Moment (ft-k)	Long. Moment (ft-k)	Vert. Moment (ft-k)	Bending Found. Moment Usage %
NESC Heavy	10255:g	-0.17	-33.73	121.21	33.73	4170.16	-12.06	-0.02	4170.18 0.00
NESC Extreme	10255:g	-0.05	-53.58	59.23	53.58	6039.79	-3.68	-0.01	6039.79 0.00

Summary of Tip Deflections For All Load Cases:

Note: positive tip load results in positive rotation

Load Case	Joint Label	Long. Defl. (in)	Trans. Defl. (in)	Vert. Defl. (in)	Resultant Defl. (in)	Long. Rot. (deg)	Trans. Rot. (deg)	Twist (deg)
NESC Heavy	10255:t	0.21	100.69	-3.90	100.76	0.01	-5.98	0.00
NESC Extreme	10255:t	0.06	142.81	-7.72	143.02	0.00	-8.59	0.00

Tubes Summary:

Pole Label	Tube Num.	Weight (lbs)	Load Case	Maximum Usage %	Resultant Moment (ft-k)
10255	1	5022	NESC Extreme	83.12	1187.56
10255	2	10058	NESC Extreme	93.55	3411.75
10255	3	12901	NESC Extreme	95.68	5772.78

*** Overall summary for all load cases - Usage = Maximum Stress / Allowable Stress

Summary of Steel Pole Usages:

Steel Pole Label	Pole Maximum Usage %	Load Case	Segment Number	Weight (lbs)
10255	95.68	NESC Extreme	37	30952.3

Summary of Tubular Davit Usages:

Centek Engineering Inc - cl&p structure # 10255

Clamp4	Clamp	10.09	NESC Heavy	0.0
Clamp5	Clamp	10.09	NESC Heavy	0.0
Clamp6	Clamp	10.09	NESC Heavy	0.0
Clamp7	Clamp	10.09	NESC Heavy	0.0
Clamp8	Clamp	10.09	NESC Heavy	0.0
Clamp9	Clamp	25.27	NESC Extreme	0.0
Clamp10	Clamp	16.73	NESC Extreme	0.0
Clamp11	Clamp	1.44	NESC Heavy	0.0
Clamp12	Clamp	1.44	NESC Heavy	0.0
Clamp13	Clamp	1.44	NESC Heavy	0.0
Clamp14	Clamp	1.44	NESC Heavy	0.0
Clamp15	Clamp	1.44	NESC Heavy	0.0
Clamp16	Clamp	1.44	NESC Heavy	0.0
Clamp17	Clamp	1.44	NESC Heavy	0.0
Clamp18	Clamp	1.44	NESC Heavy	0.0
Clamp19	Clamp	1.44	NESC Heavy	0.0
Clamp20	Clamp	1.44	NESC Heavy	0.0
Clamp21	Clamp	1.44	NESC Heavy	0.0
Clamp22	Clamp	1.44	NESC Heavy	0.0
Clamp23	Clamp	1.44	NESC Heavy	0.0

*** Weight of structure (lbs):
 Weight of Tubular Davit Arms: 3814.7
 Weight of Steel Poles: 30952.3
 Total: 34767.0

*** End of Report

* PLS-POLE *
* POLE AND FRAME ANALYSIS AND DESIGN *
* Copyright Power Line Systems, Inc. 1999-2011 *

Project Name : 12047.CO3 - Bethel, CT
Project Notes: CL&P - Str # 10255/ Sprint CT03XC351
Project File : J:\Jobs\1204700.WI\CO3 - CT03XC351\Calcs\PLS-Pole\cl&p structure # 10255.pol
Date run : 9:50:35 AM Wednesday, February 13, 2013
by : PLS-POLE Version 11.11
Licensed to : Centek Engineering Inc

Successfully performed nonlinear analysis

The model has 0 warnings.

.....
.....
.....

Modeling options:

Offset Arms from Pole/Mast: Yes
Offset Braces from Pole/Mast: Yes
Offset Guys from Pole/Mast: Yes
Offset Posts from Pole/Mast: Yes
Offset Strains from Pole/Mast: Yes
Use Alternate Convergence Process: No
Steel poles checked with ASCE/SEI 48-05

Default Modulus of Elasticity for Steel = 29000.00 (ksi)
Default Weight Density for Steel = 490.00 (lbs/ft^3)

Steel Pole Properties:

Steel Pole Ultimate	Stock Length	Default	Base	Shape	Tip	Base	Taper Default	Tubes Modulus of	Weight	Shape	Strength Distance
Property Number	Embedded Plate				Diameter	Diameter	Drag	Elasticity	Density	At	Check From

Trans. Load	Long. Label	Length (ft)	Coef.	Override (in)	Override (in/ft)	Base (ksi)	Type	Tip (ft)						
CL&P10255	10255	150.00	0	Yes	12F	20.18	55.99	0	1.3	3 tubes	0	0	Calculated	0.000
0.0000	0.0000													

Steel Tubes Properties:


Property No.	Pole Tube Length (ft)	Thickness (in)	Lap Length (ft)	Lap Gap (in)	Yield Stress (ksi)	Override (ft-k)	Cap. (ft-k)	Tube Weight (lbs)	Center of Gravity (ft)	Tube Diameter (in)	Top Tube Diameter (in)	Bot. Tube Diameter (in)	1.5x Diam. Lap Length (ft)
CL&P10255	1	55	0.3125	4.670	0.000	65.000	0.000	5022	29.85	0.24873	20.18	33.86	4.15
CL&P10255	2	54.67	0.4375	6.170	0.000	65.000	0.000	10058	28.95	0.24873	32.07	45.67	5.60
CL&P10255	3	51.17	0.46875	0.000	0.000	65.000	0.000	12901	26.69	0.24873	43.26	55.99	0.00

Base Plate Properties:

Property	Pole Plate Diam. (in)	Plate Shape	Thick. (in)	Weight (lbs)	Bend Line	Hole Diam. (in)	Hole Shape	Steel Density (lbs/ft^3)	Yield Stress (ksi)	Bolt Diam. (in)	Bolt Pattern	Bolt Num.	Cage X Inertia (in^4)	Cage Y Inertia (in^4)
CL&P10255	72.000	8F	3.000	2971	0.000	30.000	0	490.00	60.000	2.250	65.000	24	67953.29	37978.89

Base Plate Bolt Coordinates for Property "CL&P10255":

Bolt X Coord.	Bolt Y Coord.	Bolt Angle (deg)
0	1	0
0.8538	0.5615	0
0.7077	0.7077	0
0.5615	0.8538	0
0.4154	1	0
0.2077	1	0
1	0	0




Steel Pole Connectivity:

Pole Label	Tip Joint	Base Joint	X of Base (ft)	Y of Base (ft)	Z of Base (ft)	Inclin. About X (deg)	Inclin. About Y (deg)	Property Set	Attach. Labels	Base Connect	Embed Override	Embed C. Override (ft)
10255			0	0	0	0	0	CL&P10255	19 labels		0.00	0

Relative Attachment Labels for Steel Pole "10255":

Joint Label	Distance From Origin/Top Joint (ft)	Global Z of Attach (ft)
10255:Arm1	0.00	149.30
10255:Arm2	0.00	136.63
10255:Arm3	0.00	114.63
10255:Arm4	0.00	92.63
10255:TopConn	0.00	146.42

10255:BotConn	0.00	140.25
10255:WVGDI1	0.00	10.00
10255:WVGDI2	0.00	20.00
10255:WVGDI3	0.00	30.00
10255:WVGDI4	0.00	40.00
10255:WVGDI5	0.00	50.00
10255:WVGDI6	0.00	60.00
10255:WVGDI7	0.00	70.00
10255:WVGDI8	0.00	80.00
10255:WVGDI9	0.00	90.00
10255:WVGDI10	0.00	100.00
10255:WVGDI11	0.00	110.00
10255:WVGDI12	0.00	120.00
10255:WVGDI13	0.00	130.00



Pole Steel Properties:

Warning: Capacities and usages printed in splices are listed for the inner tube except at the splice top which uses the outer tube. ??

Element Label	Joint Label	Joint Position	Rel. Dist. (ft)	Outer Diam. (in)	Area (in ²)	T-Moment (in ⁴)	I-Moment (in ⁴)	D/t	W/t	Fy (ksi)	Fa Min. (ksi)	ASCE Cap Trans. (ft-k)	ASCE Cap Long. (ft-k)
10255	10255:t	10255:t Ori	0.00	20.18	19.96	1008.79	1008.79	0.00	14.6	65.00	65.00	541.55	541.55

10255	10255:Arm1	10255:Arm1 End	0.70	20.35	20.14	1035.54	1035.54	0.00	14.8	65.00	65.00	551.16	551.16
10255	10255:Arm1	10255:Arm1 Ori	0.70	20.35	20.14	1035.54	1035.54	0.00	14.8	65.00	65.00	551.16	551.16
10255	10255:TopConn	10255:TopConn End	3.58	21.07	20.86	1150.58	1150.58	0.00	15.4	65.00	65.00	591.56	591.56
10255	10255:TopConn	10255:TopConn Ori	3.58	21.07	20.86	1150.58	1150.58	0.00	15.4	65.00	65.00	591.56	591.56
10255	#10255:0	Tube 1 End	6.67	21.84	21.63	1282.93	1282.93	0.00	16.0	65.00	65.00	636.44	636.44
10255	#10255:0	Tube 1 Ori	6.67	21.84	21.63	1282.93	1282.93	0.00	16.0	65.00	65.00	636.44	636.44
10255	10255:BotConn	10255:BotConn End	9.75	22.61	22.40	1425.06	1425.06	0.00	16.7	65.00	65.00	682.95	682.95
10255	10255:BotConn	10255:BotConn Ori	9.75	22.61	22.40	1425.06	1425.06	0.00	16.7	65.00	65.00	682.95	682.95
10255	10255:Arm2	10255:Arm2 End	13.38	23.51	23.31	1605.04	1605.04	0.00	17.5	65.00	65.00	739.70	739.70
10255	10255:Arm2	10255:Arm2 Ori	13.38	23.51	23.31	1605.04	1605.04	0.00	17.5	65.00	65.00	739.70	739.70
10255	#10255:1	Tube 1 End	16.69	24.33	24.13	1782.21	1782.21	0.00	18.2	65.00	65.00	793.54	793.54
10255	#10255:1	Tube 1 Ori	16.69	24.33	24.13	1782.21	1782.21	0.00	18.2	65.00	65.00	793.54	793.54
10255	10255:WVGDI3	10255:WVGDI3 End	20.00	25.15	24.96	1971.97	1971.97	0.00	18.9	65.00	65.00	849.26	849.26
10255	10255:WVGDI3	10255:WVGDI3 Ori	20.00	25.15	24.96	1971.97	1971.97	0.00	18.9	65.00	65.00	849.26	849.26
10255	#10255:2	Tube 1 End	25.00	26.40	26.21	2283.18	2283.18	0.00	20.0	65.00	65.00	936.97	936.97
10255	#10255:2	Tube 1 Ori	25.00	26.40	26.21	2283.18	2283.18	0.00	20.0	65.00	65.00	936.97	936.97
10255	10255:WVGDI2	10255:WVGDI2 End	30.00	27.64	27.46	2625.52	2625.52	0.00	21.0	65.00	65.00	1028.98	1028.98
10255	10255:WVGDI2	10255:WVGDI2 Ori	30.00	27.64	27.46	2625.52	2625.52	0.00	21.0	65.00	65.00	1028.98	1028.98
10255	#10255:3	Tube 1 End	32.69	28.31	28.13	2822.91	2822.91	0.00	21.6	65.00	65.00	1080.22	1080.22
10255	#10255:3	Tube 1 Ori	32.69	28.31	28.13	2822.91	2822.91	0.00	21.6	65.00	65.00	1080.22	1080.22
10255	10255:Arm3	10255:Arm3 End	35.38	28.98	28.80	3029.96	3029.96	0.00	22.2	65.00	65.00	1132.70	1132.70
10255	10255:Arm3	10255:Arm3 Ori	35.38	28.98	28.80	3029.96	3029.96	0.00	22.2	65.00	65.00	1132.70	1132.70
10255	10255:WVGDI1	10255:WVGDI1 End	40.00	30.13	29.96	3409.54	3409.54	0.00	23.2	65.00	65.00	1225.94	1225.94
10255	10255:WVGDI1	10255:WVGDI1 Ori	40.00	30.13	29.96	3409.54	3409.54	0.00	23.2	65.00	65.00	1225.94	1225.94
10255	#10255:4	Tube 1 End	45.00	31.37	31.21	3854.19	3854.19	0.00	24.2	65.00	65.00	1330.88	1330.88
10255	#10255:4	Tube 1 Ori	45.00	31.37	31.21	3854.19	3854.19	0.00	24.2	65.00	65.00	1330.88	1330.88
10255	10255:WVGDI0	10255:WVGDI0 End	50.00	32.62	32.46	4335.91	4335.91	0.00	25.3	65.00	65.00	1440.13	1440.13
10255	10255:WVGDI0	10255:WVGDI0 Ori	50.00	32.62	32.46	4335.91	4335.91	0.00	25.3	65.00	65.00	1440.13	1440.13
10255	#10255:5	Splicer End	50.33	32.70	32.54	4369.04	4369.04	0.00	25.4	65.00	65.00	1447.49	1447.49
10255	#10255:5	Splicer Ori	50.33	32.70	32.54	4369.04	4369.04	0.00	25.4	65.00	65.00	1447.49	1447.49
10255	#10255:6	Splicer End	55.00	33.24	46.14	6353.36	6353.36	0.00	17.7	65.00	65.00	2070.93	2070.93
10255	#10255:6	Splicer Ori	55.00	33.24	46.14	6353.36	6353.36	0.00	17.7	65.00	65.00	2070.93	2070.93
10255	10255:Arm4	10255:Arm4 End	57.38	33.83	46.97	6702.85	6702.85	0.00	18.0	65.00	65.00	2146.69	2146.69
10255	10255:Arm4	10255:Arm4 Ori	57.38	33.83	46.97	6702.85	6702.85	0.00	18.0	65.00	65.00	2146.69	2146.69
10255	10255:WVGDI9	10255:WVGDI9 End	60.00	34.48	47.89	7103.77	7103.77	0.00	18.4	65.00	65.00	2232.01	2232.01
10255	10255:WVGDI9	10255:WVGDI9 Ori	60.00	34.48	47.89	7103.77	7103.77	0.00	18.4	65.00	65.00	2232.01	2232.01
10255	10255:WVGDI9	10255:WVGDI9 Ori	60.00	34.48	47.89	7103.77	7103.77	0.00	18.4	65.00	65.00	2232.01	2232.01
10255	#10255:7	Tube 2 End	65.00	35.72	49.64	7911.06	7911.06	0.00	19.2	65.00	65.00	2399.12	2399.12
10255	#10255:7	Tube 2 Ori	65.00	35.72	49.64	7911.06	7911.06	0.00	19.2	65.00	65.00	2399.12	2399.12
10255	10255:WVGDI8	10255:WVGDI8 End	70.00	36.97	51.39	8777.30	8777.30	0.00	20.0	65.00	65.00	2572.27	2572.27
10255	10255:WVGDI8	10255:WVGDI8 Ori	70.00	36.97	51.39	8777.30	8777.30	0.00	20.0	65.00	65.00	2572.27	2572.27
10255	#10255:8	Tube 2 End	75.00	38.21	53.14	9704.59	9704.59	0.00	20.7	65.00	65.00	2751.45	2751.45
10255	#10255:8	Tube 2 Ori	75.00	38.21	53.14	9704.59	9704.59	0.00	20.7	65.00	65.00	2751.45	2751.45
10255	10255:WVGDI7	10255:WVGDI7 End	80.00	39.45	54.89	10694.98	10694.98	0.00	21.5	65.00	65.00	2936.66	2936.66
10255	10255:WVGDI7	10255:WVGDI7 Ori	80.00	39.45	54.89	10694.98	10694.98	0.00	21.5	65.00	65.00	2936.66	2936.66
10255	#10255:9	Tube 2 End	85.00	40.70	56.63	11750.57	11750.57	0.00	22.2	65.00	65.00	3127.91	3127.91
10255	#10255:9	Tube 2 Ori	85.00	40.70	56.63	11750.57	11750.57	0.00	22.2	65.00	65.00	3127.91	3127.91
10255	10255:WVGDI6	10255:WVGDI6 End	90.00	41.94	58.38	12873.43	12873.43	0.00	23.0	65.00	65.00	3325.19	3325.19
10255	10255:WVGDI6	10255:WVGDI6 Ori	90.00	41.94	58.38	12873.43	12873.43	0.00	23.0	65.00	65.00	3325.19	3325.19
10255	#10255:10	Tube 2 End	94.42	43.04	59.93	13922.50	13922.50	0.00	23.7	65.00	65.00	3504.41	3504.41
10255	#10255:10	Tube 2 Ori	94.42	43.04	59.93	13922.50	13922.50	0.00	23.7	65.00	65.00	3504.41	3504.41
10255	#10255:11	Splicer End	98.83	44.14	61.47	15027.07	15027.07	0.00	24.4	65.00	65.00	3688.33	3688.33
10255	#10255:11	Splicer Ori	98.83	44.14	61.47	15027.07	15027.07	0.00	24.4	65.00	65.00	3688.33	3688.33
10255	10255:WVGDI5	10255:WVGDI5 End	100.00	43.55	64.94	15430.22	15430.22	0.00	22.2	65.00	65.00	3838.06	3838.06
10255	10255:WVGDI5	10255:WVGDI5 Ori	100.00	43.55	64.94	15430.22	15430.22	0.00	22.2	65.00	65.00	3838.06	3838.06
10255	#10255:12	Splicer End	105.00	44.80	66.81	16805.27	16805.27	0.00	22.9	65.00	65.00	4064.04	4064.04
10255	#10255:12	Splicer Ori	105.00	44.80	66.81	16805.27	16805.27	0.00	22.9	65.00	65.00	4064.04	4064.04
10255	10255:WVGDI4	10255:WVGDI4 End	110.00	46.04	68.69	18259.67	18259.67	0.00	23.6	65.00	65.00	4296.48	4296.48
10255	10255:WVGDI4	10255:WVGDI4 Ori	110.00	46.04	68.69	18259.67	18259.67	0.00	23.6	65.00	65.00	4296.48	4296.48
10255	#10255:13	Tube 3 End	115.00	47.28	70.56	19793.66	19793.66	0.00	24.3	65.00	65.00	4535.39	4535.39

10255	#10255:13	Tube 3 Ori	115.00	47.28	70.56	19795.66	19795.66	0.00	24.3	65.00	65.00	4535.39	4535.39
10255	10255:WVG D3	10255:WVG D3 End	120.00	48.53	72.44	21415.47	21415.47	0.00	25.1	65.00	65.00	4780.76	4780.76
10255	10255:WVG D3	10255:WVG D3 Ori	120.00	48.53	72.44	21415.47	21415.47	0.00	25.1	65.00	65.00	4780.76	4780.76
10255	#10255:14	Tube 3 End	125.00	49.77	74.31	23121.31	23121.31	0.00	25.8	65.00	65.00	5032.59	5032.59
10255	#10255:14	Tube 3 Ori	125.00	49.77	74.31	23121.31	23121.31	0.00	25.8	65.00	65.00	5032.59	5032.59
10255	10255:WVG D2	10255:WVG D2 End	130.00	51.02	76.18	24915.41	24915.41	0.00	26.5	65.00	65.00	5290.89	5290.89
10255	10255:WVG D2	10255:WVG D2 Ori	130.00	51.02	76.18	24915.42	24915.42	0.00	26.5	65.00	65.00	5290.89	5290.89
10255	#10255:15	Tube 3 End	135.00	52.26	78.06	26800.01	26800.01	0.00	27.2	65.00	65.00	5555.66	5555.66
10255	#10255:15	Tube 3 Ori	135.00	52.26	78.06	26800.01	26800.01	0.00	27.2	65.00	65.00	5555.66	5555.66
10255	10255:WVG D1	10255:WVG D1 End	140.00	53.50	79.93	28777.33	28777.33	0.00	27.9	65.00	65.00	5826.89	5826.89
10255	10255:WVG D1	10255:WVG D1 Ori	140.00	53.50	79.93	28777.33	28777.33	0.00	27.9	65.00	65.00	5826.89	5826.89
10255	#10255:16	Tube 3 End	145.00	54.75	81.81	30849.59	30849.59	0.00	28.6	65.00	65.00	6104.58	6104.58
10255	#10255:16	Tube 3 Ori	145.00	54.75	81.81	30849.59	30849.59	0.00	28.6	65.00	65.00	6104.58	6104.58
10255	10255:g	10255:g End	150.00	55.99	83.68	33019.02	33019.02	0.00	29.3	65.00	65.00	6388.74	6388.74

Tubular Davit Properties:

Steel	Davit Stock	Steel Thickness	Base	Tip	Taper	Drag	Modulus Geometry	Strength Vertical	Tension	Compress.	Long.	Yield	Weight
Property Number	Shape	Diameter	Diameter	Tip	Taper	Drag	Modulus Geometry	Strength Vertical	Tension	Compress.	Long.	Yield	Weight
Shape		Diameter	Diameter	Tip	Taper	Drag	Modulus Geometry	Strength Vertical	Tension	Compress.	Long.	Yield	Weight
Label		or Depth	or Depth					Type	Capacity	Capacity	Capacity	Capacity	Override
At End		(in)	(in)	(in)	(in/ft)		(ksi)		(lbs)	(lbs)	(lbs)	(ksi)	(lbs/ft^3)
ARM1	601420	6T	0.1875	10.75	6	0	1	29000 1 point	Calculated	0	0	0	65
ARM2	601515	8T	0.25	18.46	9	0	1	29000 1 point	Calculated	0	0	0	65

Intermediate Joints for Davit Property "ARM1":


Joint Horiz. Vert.	
Label Offset Offset	
(ft) (ft)	
End 10 -1.2	


Intermediate Joints for Davit Property "ARM2":

Joint Horiz. Vert.	
Label Offset Offset	
(ft) (ft)	
End 15 -2	

Tubular Davit Arm Connectivity:

Davit	Attach	Davit Azimuth
Label	Label Property	Set (deg)
Davit1	10255:Arm1	ARM1 180
Davit2	10255:Arm1	ARM1 0
Davit3	10255:Arm2	ARM2 180
Davit4	10255:Arm2	ARM2 0
Davit5	10255:Arm3	ARM2 180
Davit6	10255:Arm3	ARM2 0
Davit7	10255:Arm4	ARM2 180





Tubular Davit Arm Steel Properties:

Element Label	Joint Label	Joint Position	Rel. Dist. (ft)	Outer Diam. (in)	Area (in ²)	V-Moment (in ⁴)	H-Moment (in ⁴)	D/t	W/t Max.	Fy (ksi)	Fa Min. (ksi)	ASCE V-Mom. (ft-k)	ASCE Cap H-Mom. (ft-k)
Davit1	Davit1:0	Origin	0.00	10.75	6.86	106.34	106.34	0.00	27.3	65.00	65.00	92.80	107.16
Davit1	#Davit1:0	End	5.00	8.39	5.33	49.84	49.84	0.00	20.1	65.00	65.00	55.72	64.34
Davit1	#Davit1:0	Origin	5.00	8.39	5.33	49.84	49.84	0.00	20.1	65.00	65.00	55.72	64.34
Davit1	#Davit1:1	End	7.54	7.20	4.55	31.08	31.08	0.00	16.4	65.00	65.00	40.52	46.78
Davit1	#Davit1:1	Origin	7.54	7.20	4.55	31.08	31.08	0.00	16.4	65.00	65.00	40.52	46.78
Davit1	Davit1:End	End	10.07	6.00	3.78	17.73	17.73	0.00	12.7	65.00	65.00	27.73	32.02
Davit2	Davit2:0	Origin	0.00	10.75	6.86	106.34	106.34	0.00	27.3	65.00	65.00	92.80	107.16
Davit2	#Davit2:0	End	5.00	8.39	5.33	49.84	49.84	0.00	20.1	65.00	65.00	55.72	64.34
Davit2	#Davit2:0	Origin	5.00	8.39	5.33	49.84	49.84	0.00	20.1	65.00	65.00	55.72	64.34
Davit2	#Davit2:1	End	7.54	7.20	4.55	31.08	31.08	0.00	16.4	65.00	65.00	40.52	46.78
Davit2	#Davit2:1	Origin	7.54	7.20	4.55	31.08	31.08	0.00	16.4	65.00	65.00	40.52	46.78
Davit2	Davit2:End	End	10.07	6.00	3.78	17.73	17.73	0.00	12.7	65.00	65.00	27.73	32.02
Davit3	Davit3:0	Origin	0.00	18.46	15.09	661.20	661.20	0.00	26.4	65.00	65.00	358.49	358.49
Davit3	#Davit3:0	End	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit3	#Davit3:0	Origin	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32

Davit3	#Davit3:1	End	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit3	#Davit3:1	Origin	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit3	#Davit3:2	End	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit3	#Davit3:2	Origin	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit3	Davit3:End	End	15.13	9.00	7.25	73.40	73.40	0.00	10.8	65.00	65.00	81.63	81.63
Davit4	Davit4:0	Origin	0.00	18.46	15.09	661.20	661.20	0.00	26.4	65.00	65.00	358.49	358.49
Davit4	#Davit4:0	End	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit4	#Davit4:0	Origin	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit4	#Davit4:1	End	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit4	#Davit4:1	Origin	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit4	#Davit4:2	End	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit4	#Davit4:2	Origin	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit4	Davit4:End	End	15.13	9.00	7.25	73.40	73.40	0.00	10.8	65.00	65.00	81.63	81.63
Davit5	Davit5:0	Origin	0.00	18.46	15.09	661.20	661.20	0.00	26.4	65.00	65.00	358.49	358.49
Davit5	#Davit5:0	End	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit5	#Davit5:0	Origin	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit5	#Davit5:1	End	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit5	#Davit5:1	Origin	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit5	#Davit5:2	End	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit5	#Davit5:2	Origin	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit5	Davit5:End	End	15.13	9.00	7.25	73.40	73.40	0.00	10.8	65.00	65.00	81.63	81.63
Davit6	Davit6:0	Origin	0.00	18.46	15.09	661.20	661.20	0.00	26.4	65.00	65.00	358.49	358.49
Davit6	#Davit6:0	End	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit6	#Davit6:0	Origin	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit6	#Davit6:1	End	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit6	#Davit6:1	Origin	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit6	#Davit6:2	End	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit6	#Davit6:2	Origin	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit6	Davit6:End	End	15.13	9.00	7.25	73.40	73.40	0.00	10.8	65.00	65.00	81.63	81.63
Davit7	Davit7:0	Origin	0.00	18.46	15.09	661.20	661.20	0.00	26.4	65.00	65.00	358.49	358.49
Davit7	#Davit7:0	End	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit7	#Davit7:0	Origin	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit7	#Davit7:1	End	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit7	#Davit7:1	Origin	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit7	#Davit7:2	End	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit7	#Davit7:2	Origin	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit7	Davit7:End	End	15.13	9.00	7.25	73.40	73.40	0.00	10.8	65.00	65.00	81.63	81.63
Davit8	Davit8:0	Origin	0.00	18.46	15.09	661.20	661.20	0.00	26.4	65.00	65.00	358.49	358.49
Davit8	#Davit8:0	End	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit8	#Davit8:0	Origin	5.00	15.33	12.50	375.85	375.85	0.00	21.3	65.00	65.00	245.32	245.32
Davit8	#Davit8:1	End	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit8	#Davit8:1	Origin	10.00	12.21	9.91	187.31	187.31	0.00	16.1	65.00	65.00	153.55	153.55
Davit8	#Davit8:2	End	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit8	#Davit8:2	Origin	12.57	10.60	8.58	121.60	121.60	0.00	13.4	65.00	65.00	114.77	114.77
Davit8	Davit8:End	End	15.13	9.00	7.25	73.40	73.40	0.00	10.8	65.00	65.00	81.63	81.63

*** Insulator Data

Clamp Properties:

Label Stock Holding
Number Capacity
(lbs)

clamp clamp1 8e+004

Clamp Insulator Connectivity:

Clamp Label	Structure And Tip Attach	Property Min. Set Vertical Load (uplift) (lbs)
Clamp1	Davilt1:End	clamp No Limit
Clamp2	Davilt2:End	clamp No Limit
Clamp3	Davilt3:End	clamp No Limit
Clamp4	Davilt4:End	clamp No Limit
Clamp5	Davilt5:End	clamp No Limit
Clamp6	Davilt6:End	clamp No Limit
Clamp7	Davilt7:End	clamp No Limit
Clamp8	Davilt8:End	clamp No Limit
Clamp9	10255:TopConn	clamp No Limit
Clamp10	10255:BotConn	clamp No Limit
Clamp11	10255:WVGD1	clamp No Limit
Clamp12	10255:WVGD2	clamp No Limit
Clamp13	10255:WVGD3	clamp No Limit
Clamp14	10255:WVGD4	clamp No Limit
Clamp15	10255:WVGD5	clamp No Limit
Clamp16	10255:WVGD6	clamp No Limit
Clamp17	10255:WVGD7	clamp No Limit
Clamp18	10255:WVGD8	clamp No Limit
Clamp19	10255:WVGD9	clamp No Limit
Clamp20	10255:WVGD10	clamp No Limit
Clamp21	10255:WVGD11	clamp No Limit
Clamp22	10255:WVGD12	clamp No Limit
Clamp23	10255:WVGD13	clamp No Limit

Loads from file: j:\jobs\1204700.wi\co3 - ct03xc351\calcs\pls-pole\cl1p #10255.1ca

Loading Method Parameters:

Structure Height Summary (used for calculating wind/ice adjust with height):

Structure Height Summary (used for calculating wind/ice adjust with height):	
Z of ground for wind height adjust	0.00 (ft)
Ground elevation shift	0.00 (ft)
Z of ground with shift	0.00 (ft)
Z of structure top (highest joint)	150.50 (ft)
Structure height	150.50 (ft)
Structure height above ground	150.50 (ft)

Vector Load Cases:

Load Case	Dead	Wind	SF for SF	for SF	for SF	for SF	for SF	Point	Wind/Ice	Trans.	Longit.
Ice Temperature			Pole								
Description	Load	Area	Steel Poles	Wood Conc.	Guy	Non Braces	Insuls.	Found.	Model	Wind	Wind
Thick.	Density		Deflection	Deflection							
	Factor	Factor	Tubular Arms	Poles	Ult.	First	Zero	and Tubular		Pressure	Pressure
Check Limit											
(in) (lbs/Et ^{1/3})	(deg F)		and Towers	% or (ft)		Crack	Tens.	Cables	Arms	(psf)	(psf)

[illegible]

Point Loads for Load Case "NESC Heavy":

	Joint Vertical Label	Transverse Load (lbs)	Longitudinal Load (lbs)	Load Comment
	David1:End	1134	1078	0 Shield Wire
	David2:End	1134	1078	0 Shield Wire
	David3:End	7201	3651	0 Conductor
	David4:End	7201	3651	0 Conductor
	David5:End	7201	3651	0 Conductor
	David6:End	7201	3651	0 Conductor
	David7:End	7201	3651	0 Conductor
	David8:End	7201	3651	0 Conductor
	10255:TopConn	8657	6545	0 Top Connection
	10255:BotConn	788	-4305	0 Bottom Connection
	10255:WVG1	1150	84	0 Coax Cables
	10255:WVG2	1150	84	0 Coax Cables
	10255:WVG3	1150	84	0 Coax Cables
	10255:WVG4	1150	84	0 Coax Cables
	10255:WVG5	1150	84	0 Coax Cables
	10255:WVG6	1150	84	0 Coax Cables

10255:WVGD7	1150	84	0	Coax Cables
10255:WVGD8	1150	84	0	Coax Cables
10255:WVGD9	1150	84	0	Coax Cables
10255:WVGD10	1150	84	0	Coax Cables
10255:WVGD11	1150	84	0	Coax Cables
10255:WVGD12	1150	84	0	Coax Cables
10255:WVGD13	1150	84	0	Coax Cables

Detailed Pole Loading Data for Load Case "NESC Heavy":

Notes: Does not include loads from equipment, arms, guys, braces, etc. or user input loads.
Wind load is calculated for the undeformed shape of a pole.

Pole Label	Top Joint	Bottom Joint	Section Z		Section Average Elevation (ft)	Outer Diameter (in)	Reynolds Number	Drag Coef.	Adjusted Wind Pressure (psf)	Adjusted Ice Thickness (in)	Pole Vert. Load (lbs)	Pole Wind Load (lbs)	Pole Ice Load (lbs)	Ice Wind Load (lbs)	Ice Tran. Load (lbs)	Long. Wind Load (lbs)
			Top	Bottom												
10255	10255:t	10255:Arm1	150.00	149.30	149.65	20.267	9.6e+005	1.300	10.00	0.50	71.64	15.37	8.87	0.76	16.13	0.00
10255			149.30	146.42	147.86	20.712	9.81e+005	1.300	10.00	0.50	301.32	64.63	37.29	3.12	67.75	0.00
10255	10255:TopConn	10255:BotConn	146.42	143.34	144.88	21.454	1.02e+006	1.300	10.00	0.50	334.50	71.71	41.38	3.34	75.05	0.00
10255			143.34	140.25	141.79	22.221	1.05e+006	1.300	10.00	0.50	346.65	74.27	42.86	3.34	77.61	0.00
10255	10255:BotConn	10255:Arm2	140.25	136.63	138.44	23.056	1.09e+006	1.300	10.00	0.50	422.84	90.55	52.25	3.93	94.47	0.00
10255			136.63	133.31	134.97	23.919	1.13e+006	1.300	10.00	0.50	401.04	85.84	49.54	3.59	89.43	0.00
10255	10255:WVGD13	10255:WVGD12	133.31	130.00	131.66	24.743	1.17e+006	1.300	10.00	0.50	441.04	88.79	51.24	3.59	92.38	0.00
10255			130.00	125.00	127.50	25.777	1.22e+006	1.300	10.00	0.50	652.99	139.63	80.58	5.42	145.05	0.00
10255	10255:WVGD12	10255:WVGD11	125.00	120.00	122.50	27.020	1.28e+006	1.300	10.00	0.50	684.88	146.37	84.47	5.42	151.78	0.00
10255			120.00	117.31	118.66	27.976	1.32e+006	1.300	10.00	0.50	381.30	81.46	47.01	2.91	84.37	0.00
10255	10255:Arm3	10255:WVGD11	117.31	114.63	115.97	28.645	1.36e+006	1.300	10.00	0.50	390.51	83.40	48.13	2.91	86.31	0.00
10255			114.63	110.00	112.31	29.554	1.4e+006	1.300	10.00	0.50	693.62	148.09	85.46	5.01	153.10	0.00
10255	10255:WVGD11	10255:WVGD10	110.00	105.00	107.50	30.751	1.46e+006	1.300	10.00	0.50	780.56	166.58	96.13	5.42	171.99	0.00
10255			105.00	100.00	102.50	31.995	1.51e+006	1.300	10.00	0.50	812.45	173.31	100.02	5.42	178.73	0.00
10255	10255:WVGD10	10255:Arm4	100.00	99.67	99.84	32.658	1.55e+006	1.300	10.00	0.50	54.74	11.68	6.74	0.36	12.03	0.00
10255			99.67	95.00	97.34	32.967	1.56e+006	1.300	10.00	0.50	1869.88	166.79	96.26	5.06	171.85	0.00
10255	10255:Arm4	10255:WVGD9	95.00	92.63	93.81	33.531	1.59e+006	1.300	10.00	0.50	564.48	86.28	49.79	2.57	88.85	0.00
10255			92.63	90.00	91.31	34.153	1.62e+006	1.300	10.00	0.50	635.46	97.13	56.05	2.84	99.97	0.00
10255	10255:WVGD9	10255:WVGD8	90.00	85.00	87.50	35.101	1.66e+006	1.300	10.00	0.50	1244.45	190.14	109.73	5.42	195.56	0.00
10255			85.00	80.00	82.50	36.345	1.72e+006	1.300	10.00	0.50	1289.10	196.88	113.62	5.42	202.29	0.00
10255	10255:WVGD8	10255:WVGD7	85.00	80.00	82.50	36.345	1.72e+006	1.300	10.00	0.50	1289.10	196.88	113.62	5.42	202.29	0.00
10255			80.00	75.00	77.50	37.588	1.78e+006	1.300	10.00	0.50	1333.75	203.61	117.50	5.42	209.03	0.00
10255	10255:WVGD7	10255:WVGD6	75.00	70.00	72.50	38.832	1.84e+006	1.300	10.00	0.50	1378.39	210.35	121.39	5.42	215.77	0.00
10255			70.00	65.00	67.50	40.076	1.9e+006	1.300	10.00	0.50	1423.04	217.09	125.28	5.42	222.50	0.00
10255	10255:WVGD6	10255:WVGD5	65.00	60.00	62.50	41.319	1.96e+006	1.300	10.00	0.50	1467.69	223.82	129.17	5.42	229.24	0.00
10255			60.00	55.59	57.79	42.490	2.01e+006	1.300	10.00	0.50	1333.09	203.24	117.29	4.78	208.02	0.00
10255	10255:WVGD5	10255:WVGD4	60.00	55.59	57.79	42.490	2.01e+006	1.300	10.00	0.50	1367.90	208.49	120.32	4.78	213.27	0.00
10255			55.59	51.17	53.38	43.588	2.06e+006	1.300	10.00	0.50	754.83	55.58	32.07	1.27	56.84	0.00
10255	10255:WVGD4	10255:WVGD3	51.17	50.00	50.59	43.845	2.08e+006	1.300	10.00	0.50	1382.82	239.29	138.09	5.42	244.71	0.00
10255			45.00	44.50	44.175	2.09e+006	1.300	10.00	0.50	3282.82	246.03	141.98	5.42	251.45	0.00	
10255	10255:WVGD3	10255:WVGD2	45.00	44.50	44.175	2.09e+006	1.300	10.00	0.50	1729.02	246.03	141.98	5.42	251.45	0.00	
10255			40.00	35.00	37.50	46.662	2.21e+006	1.300	10.00	0.50	1776.86	252.77	145.87	5.42	258.19	0.00
10255	10255:WVGD2	10255:WVGD1	40.00	35.00	37.50	46.662	2.21e+006	1.300	10.00	0.50	1824.70	259.51	149.76	5.42	264.92	0.00
10255			35.00	30.00	32.50	47.906	2.27e+006	1.300	10.00	0.50	1872.54	266.24	153.65	5.42	271.66	0.00
10255	10255:WVGD1	10255:g	30.00	25.00	27.50	49.150	2.33e+006	1.300	10.00	0.50	1920.37	272.98	157.53	5.42	278.40	0.00
10255			25.00	20.00	22.50	50.394	2.39e+006	1.300	10.00	0.50	1968.21	279.72	161.42	5.42	285.13	0.00
10255	10255:WVGD1	10255:g	20.00	15.00	17.50	51.637	2.44e+006	1.300	10.00	0.50	2016.05	286.45	165.31	5.42	291.87	0.00
10255			15.00	10.00	12.50	52.881	2.5e+006	1.300	10.00	0.50	2063.89	293.19	169.20	5.42	298.61	0.00
10255	10255:WVGD1	10255:g	10.00	5.00	7.50	54.125	2.56e+006	1.300	10.00	0.50	2111.73	299.93	173.08	5.42	305.34	0.00
10255			5.00	0.00	2.50	55.368	2.62e+006	1.300	10.00	0.50						

Point Loads for Load Case "NESC Extreme":

Joint Vertical Transverse Longitudinal Load

Label	Load (lbs)	Load (lbs)	Load (lbs)	Comment
Davit1:End	280	715	0	Shield Wire
Davit2:End	280	715	0	Shield Wire
Davit3:End	3065	4999	0	Conductor
Davit4:End	3065	4999	0	Conductor
Davit5:End	3065	4999	0	Conductor
Davit6:End	3065	4999	0	Conductor
Davit7:End	3065	4999	0	Conductor
Davit8:End	3065	4999	0	Conductor
10255:TopConn	3483	19914	0	Top Connection
10255:BotConn	189	-13385	0	Bottom Connection
10255:WVGd1	312	215	0	Coax Cables
10255:WVGd2	312	215	0	Coax Cables
10255:WVGd3	312	215	0	Coax Cables
10255:WVGd4	312	215	0	Coax Cables
10255:WVGd5	312	215	0	Coax Cables
10255:WVGd6	312	215	0	Coax Cables
10255:WVGd7	312	215	0	Coax Cables
10255:WVGd8	312	215	0	Coax Cables
10255:WVGd9	312	215	0	Coax Cables
10255:WVGd10	312	215	0	Coax Cables
10255:WVGd11	312	215	0	Coax Cables
10255:WVGd12	312	215	0	Coax Cables
10255:WVGd13	312	215	0	Coax Cables

Detailed Pole Loading Data for Load Case "NESC Extreme":


Notes: Does not include loads from equipment, arms, guys, braces, etc. or user input loads.
Wind load is calculated for the undeformed shape of a pole.

Pole Label	Top Joint	Bottom Joint	Section Top Z (ft)	Section Bottom Z (ft)	Section Average Elevation (ft)	Outer Diameter (in)	Reynolds Number	Drag Coef.	Adjusted Wind Pressure (psf)	Adjusted Ice Thickness (in)	Pole Vert. Load (lbs)	Pole Wind Load (lbs)	Pole Ice Vertical Load (lbs)	Pole Ice Wind Load (lbs)	Tran. Wind Load (lbs)	Long. Wind Load (lbs)
10255	10255:t	10255:Arm1	150.00	149.30	149.65	20.267	1.58e+006	1.000	27.12	0.00	47.76	32.07	0.00	0.00	32.07	0.00
10255	10255:Arm1	10255:TopConn	149.30	146.42	147.86	20.712	1.62e+006	1.000	27.12	0.00	200.88	134.83	0.00	0.00	134.83	0.00
10255	10255:TopConn		146.42	143.34	144.88	21.454	1.67e+006	1.000	27.12	0.00	223.00	149.61	0.00	0.00	149.61	0.00
10255		10255:BotConn	143.34	140.25	141.79	22.221	1.73e+006	1.000	27.12	0.00	231.10	154.96	0.00	0.00	154.96	0.00
10255	10255:BotConn	10255:Arm2	140.25	136.63	138.44	23.056	1.8e+006	1.000	27.12	0.00	281.89	188.92	0.00	0.00	188.92	0.00
10255	10255:Arm2		136.63	133.31	134.97	23.919	1.87e+006	1.000	27.12	0.00	267.36	179.09	0.00	0.00	179.09	0.00
10255		10255:WVGd13	133.31	130.00	131.66	24.743	1.93e+006	1.000	27.12	0.00	276.69	185.26	0.00	0.00	185.26	0.00
10255	10255:WVGd13		130.00	125.00	127.50	25.777	2.01e+006	1.000	27.12	0.00	435.33	291.32	0.00	0.00	291.32	0.00
10255		10255:WVGd12	125.00	120.00	122.50	27.020	2.11e+006	1.000	27.12	0.00	456.59	305.38	0.00	0.00	305.38	0.00
10255	10255:WVGd12		120.00	117.31	118.66	27.976	2.18e+006	1.000	27.12	0.00	254.20	169.95	0.00	0.00	169.95	0.00
10255		10255:Arm3	117.31	114.63	115.97	28.645	2.23e+006	1.000	27.12	0.00	260.34	174.01	0.00	0.00	174.01	0.00
10255	10255:Arm3	10255:WVGd11	114.63	110.00	112.31	29.554	2.3e+006	1.000	27.12	0.00	462.41	308.97	0.00	0.00	308.97	0.00
10255	10255:WVGd11		110.00	105.00	107.50	30.751	2.4e+006	1.000	27.12	0.00	520.37	347.55	0.00	0.00	347.55	0.00
10255		10255:WVGd10	105.00	100.00	102.50	31.995	2.49e+006	1.000	27.12	0.00	541.63	361.60	0.00	0.00	361.60	0.00
10255	10255:WVGd10		100.00	99.67	99.84	32.658	2.55e+006	1.000	27.12	0.00	36.50	24.36	0.00	0.00	24.36	0.00
10255			99.67	95.00	97.34	32.967	2.57e+006	1.000	27.12	0.00	1246.59	348.00	0.00	0.00	348.00	0.00
10255		10255:Arm4	95.00	92.63	93.81	33.531	2.61e+006	1.000	27.12	0.00	376.32	180.01	0.00	0.00	180.01	0.00
10255	10255:Arm4		92.63	90.00	91.31	34.153	2.66e+006	1.000	27.12	0.00	423.64	202.64	0.00	0.00	202.64	0.00
10255		10255:WVGd9	90.00	85.00	87.50	35.101	2.74e+006	1.000	27.12	0.00	829.63	396.71	0.00	0.00	396.71	0.00
10255	10255:WVGd9		85.00	80.00	82.50	36.345	2.83e+006	1.000	27.12	0.00	859.40	410.76	0.00	0.00	410.76	0.00
10255		10255:WVGd8	80.00	75.00	77.50	37.588	2.93e+006	1.000	27.12	0.00	889.16	424.82	0.00	0.00	424.82	0.00
10255	10255:WVGd8		75.00	70.00	72.50	38.832	3.03e+006	1.000	27.12	0.00	918.93	438.87	0.00	0.00	438.87	0.00

10255	10255:WVGD7	70.00	65.00	67.50	40.076	3.12e+006	1.000	27.12	0.00	948.70	452.93	0.00	0.00	452.93	0.00
10255		65.00	60.00	62.50	41.319	3.22e+006	1.000	27.12	0.00	978.46	466.98	0.00	0.00	466.98	0.00
10255	10255:WVGD6	60.00	55.59	57.79	42.490	3.31e+006	1.000	27.12	0.00	888.73	434.03	0.00	0.00	424.03	0.00
10255		55.59	51.17	53.38	43.588	3.4e+006	1.000	27.12	0.00	911.94	434.99	0.00	0.00	434.99	0.00
10255	10255:WVGD5	51.17	50.00	50.59	43.845	3.42e+006	1.000	27.12	0.00	503.22	115.96	0.00	0.00	115.96	0.00
10255		50.00	45.00	47.50	44.175	3.44e+006	1.000	27.12	0.00	2188.55	499.26	0.00	0.00	499.26	0.00
10255	10255:WVGD4	45.00	40.00	42.50	45.419	3.54e+006	1.000	27.12	0.00	1152.68	513.32	0.00	0.00	513.32	0.00
10255		40.00	35.00	37.50	46.662	3.64e+006	1.000	27.12	0.00	1184.57	527.37	0.00	0.00	527.37	0.00
10255	10255:WVGD3	35.00	30.00	32.50	47.906	3.74e+006	1.000	27.12	0.00	1216.46	541.43	0.00	0.00	541.43	0.00
10255		30.00	25.00	27.50	49.150	3.83e+006	1.000	27.12	0.00	1248.36	555.49	0.00	0.00	555.49	0.00
10255	10255:WVGD2	25.00	20.00	22.50	50.394	3.93e+006	1.000	27.12	0.00	1280.25	569.54	0.00	0.00	569.54	0.00
10255		20.00	15.00	17.50	51.637	4.03e+006	1.000	27.12	0.00	1312.14	583.60	0.00	0.00	583.60	0.00
10255	10255:WVGD1	15.00	10.00	12.50	52.881	4.12e+006	1.000	27.12	0.00	1344.03	597.65	0.00	0.00	597.65	0.00
10255		10.00	5.00	7.50	54.125	4.22e+006	1.000	27.12	0.00	1375.92	611.71	0.00	0.00	611.71	0.00
10255	10255:WVGD1	5.00	0.00	2.50	55.368	4.32e+006	1.000	27.12	0.00	1407.82	625.76	0.00	0.00	625.76	0.00
10255															

*** Analysis Results:

Maximum element usage is 97.50% for Base Plate "10255" in load case "NESC Extreme"
Maximum insulator usage is 25.27% for Clamp "Clamp9" in load case "NESC Extreme"



*** Analysis Results for Load Case No. 1 "NESC Heavy" - Number of iterations in SAPS 19

Equilibrium Joint Positions and Rotations for Load Case "NESC Heavy":

Joint Label	X-Displ (ft)	Y-Displ (ft)	Z-Displ (ft)	X-Rot (deg)	Y-Rot (deg)	Z-Rot (deg)	X-Pos (ft)	Y-Pos (ft)	Z-Pos (ft)
10255:g	0	0	0	0.0000	0.0000	0.0000	0	0	0
10255:t	0.01789	8.391	-0.3249	-5.9796	0.0113	0.0003	0.01789	8.391	149.7
10255:Arml	0.01775	8.318	-0.321	-5.9796	0.0113	0.0003	0.01775	8.318	149

10255:TopConn	0.01719	8.018	-0.3054	-5.9748	0.0113	0.0003	0.01719	8.018	146.1										
10255:BotConn	0.01598	7.377	-0.2719	-5.9197	0.0113	0.0003	0.01598	7.377	140										
10255:Arm2	0.01527	7.005	-0.2527	-5.8632	0.0112	0.0003	0.01527	7.005	136.4										
10255:WVGDI3	0.01398	6.337	-0.2187	-5.6942	0.0111	0.0002	0.01398	6.337	129.8										
10255:WVGDI2	0.01209	5.374	-0.1717	-5.3375	0.0106	0.0002	0.01209	5.374	119.8										
10255:Arm3	0.01111	4.884	-0.1491	-5.1163	0.0103	0.0002	0.01111	4.884	114.5										
10255:WVGDI1	0.01028	4.479	-0.1311	-4.9017	0.0100	0.0002	0.01028	4.479	109.9										
10255:WVGDI0	0.008595	3.668	-0.09754	-4.3821	0.0093	0.0001	0.008595	3.668	99.9										
10255:Arm4	0.007437	3.126	-0.07728	-4.0393	0.0087	0.0001	0.007437	3.126	92.55										
10255:WVGDI9	0.007041	2.944	-0.07079	-3.9229	0.0085	0.0001	0.007041	2.944	89.93										
10255:WVGDI8	0.005617	2.299	-0.04941	-3.4602	0.0078	0.0001	0.005617	2.299	79.95										
10255:WVGDI7	0.004335	1.736	-0.033	-2.9839	0.0069	0.0001	0.004335	1.736	69.97										
10255:WVGDI6	0.003207	1.256	-0.02094	-2.5083	0.0060	0.0000	0.003207	1.256	59.98										
10255:WVGDI5	0.002241	0.8585	-0.01249	-2.0425	0.0050	0.0000	0.002241	0.8585	49.99										
10255:WVGDI4	0.001443	0.5406	-0.006925	-1.5951	0.0041	0.0000	0.001443	0.5406	39.99										
10255:WVGDI3	0.0008164	0.2993	-0.003496	-1.1664	0.0031	0.0000	0.0008164	0.2993	30										
10255:WVGDI2	0.0003656	0.1311	-0.001566	-0.7576	0.0021	0.0000	0.0003656	0.1311	20										
10255:WVGDI1	9.28e-005	0.03246	-0.0005665	-0.3689	0.0010	0.0000	9.28e-005	0.03246	9.999										
David1:O	0.01778	8.322	-0.2327	-5.9796	0.0113	0.0003	0.01778	7.474	149.1										
David1:End	0.01827	8.436	-0.7793	-5.7503	0.0113	0.0003	0.01827	-2.352	151.3										
David2:O	0.01773	8.313	-0.4094	-5.9796	0.0113	0.0003	0.01773	9.161	148.9										
David2:End	0.0177	8.384	-1.488	-6.2766	0.0113	0.0003	0.0177	19.23	149										
David3:O	0.01529	7.01	-0.1527	-5.8631	0.0112	0.0003	0.01529	6.031	136.5										
David3:End	0.01604	7.272	-1.277	-5.2168	0.0113	0.0003	0.01604	-8.708	139.9										
David4:O	0.01524	7	-0.3528	-5.6631	0.0112	0.0003	0.01524	7.98	136.3										
David4:End	0.01524	7.129	-2.007	-6.6186	0.0112	0.0003	0.01524	23.11	136.6										
David5:O	0.01113	4.888	-0.04142	-5.1163	0.0104	0.0002	0.01113	3.681	114.6										
David5:End	0.01177	5.106	-1.194	-4.4631	0.0104	0.0002	0.01177	-11.1	117.8										
David6:O	0.01108	4.879	-0.2568	-5.1163	0.0103	0.0002	0.01108	6.086	114.4										
David6:End	0.01113	5.002	-1.714	-5.8764	0.0103	0.0002	0.01113	21.21	114.9										
David7:O	0.007455	3.13	-0.022	-4.0393	0.0087	0.0001	0.007455	1.72	92.65										
David7:End	0.00794	3.289	-0.9781	-3.3764	0.0088	0.0001	0.00794	-13.12	95.6										
David8:O	0.007419	3.123	-0.1766	-4.0393	0.0087	0.0001	0.007419	4.532	92.45										
David8:End	0.007518	3.233	-1.351	-4.8057	0.0087	0.0001	0.007518	19.64	93.27										

Joint Support Reactions for Load Case "NESC Heavy":

Joint	X	X	Y	Y	Z	Comp.	Uplift	Result.	Result.	X	X-M.	Y	Y-M.	Z	Z-M.	Max.
Label	Force	Usage	Force	Usage	Force	Usage	Usage	Usage	Usage	Moment	Usage	Moment	Usage	Moment	Usage	%
(kips)	% (kips)	% (kips)	% (kips)	% (kips)	% (kips)	% (kips)	% (kips)	% (kips)	% (kips)	(ft-k)	% (ft-k)	(ft-k)	% (ft-k)	(ft-k)	% (ft-k)	%
10255:G	-0.17	0.0	-33.73	0.0	121.21	0.0	0.0	125.82	0.0	4170.16	0.0	-12.1	0.0	-0.02	0.0	0.0

Detailed Steel Pole Usages for Load Case "NESC Heavy":

Element	Joint	Joint	Rel.	Trans.	Long.	Vert.	Trans.	Mom.	Long.	Mom.	Tors.	Axial	Tran.	Long.	P/A	M/S.	V/Q.	T/R.	Res.	Max.
At	Label	Label	Position	Dist.	Defl.	Defl.	Defl.	(Local Mx)	(Local My)	Mom.	Force	Shear	Shear	Shear						Usage
Pt.			(ft)	(in)	(in)	(in)	(ft-k)	(ft-k)	(ft-k)	(ft-k)	(kips)	(kips)	(kips)	(ksi)	(ksi)	(ksi)	(ksi)	(ksi)		%
-	10255	10255:t	Origin	0.00	100.69	0.21	-3.90	-0.00	-0.00	0.0	-0.04	0.01	-0.00	-0.00	0.00	0.00	0.00	0.00	0.00	0.0
5	10255	10255:Arm1	End	0.70	99.81	0.21	-3.85	0.01	-0.00	0.0	-0.04	0.01	-0.00	-0.00	0.00	0.00	0.00	0.00	0.00	0.0
3	10255	10255:Arm1	Origin	0.70	99.81	0.21	-3.85	2.85	-0.00	0.0	-2.82	2.51	-0.00	-0.14	0.25	0.18	0.00	0.50	0.8	

2	10255	10255:TopConn	End	3.58	96.21	0.21	-3.66	10.09	-0.01	0.0	-2.82	2.51	-0.00	-0.14	1.11	0.06	0.00	1.25	1.9
2	10255	10255:TopConn	Origin	3.58	96.21	0.21	-3.66	10.09	-0.01	0.0	-10.91	10.01	-0.01	-0.52	0.30	0.95	0.00	1.83	2.8
4	10255	Tube 1	End	6.67	92.36	0.20	-3.46	40.97	-0.03	0.0	-10.91	10.01	-0.01	-0.50	4.18	0.25	0.00	4.71	7.2
2	10255	Tube 1	Origin	6.67	92.36	0.20	-3.46	40.97	-0.03	0.0	-11.29	10.12	-0.01	-0.52	4.18	0.25	0.00	4.73	7.3
2	10255	10255:BotConn	End	9.75	88.53	0.19	-3.26	72.19	-0.05	0.0	-11.29	10.12	-0.01	-0.50	6.87	0.24	0.00	7.39	11.4
2	10255	10255:BotConn	Origin	9.75	88.53	0.19	-3.26	72.19	-0.05	0.0	-12.96	6.04	-0.01	-0.58	6.87	0.14	0.00	7.45	11.5
2	10255	10255:Arm2	End	13.38	84.06	0.18	-3.03	94.08	-0.09	0.0	-12.96	6.04	-0.01	-0.56	8.27	0.14	0.00	8.83	13.6
2	10255	10255:Arm2	Origin	13.38	84.06	0.18	-3.03	110.89	-0.10	0.0	-28.72	15.07	-0.02	-1.23	9.75	0.34	0.00	10.99	16.9
2	10255	Tube 1	End	16.69	80.02	0.18	-2.83	160.80	-0.15	0.0	-28.72	15.07	-0.02	-1.19	13.17	0.33	0.00	14.38	22.1
2	10255	Tube 1	Origin	16.69	80.02	0.18	-2.83	160.80	-0.15	0.0	-29.19	15.16	-0.02	-1.21	13.17	0.33	0.00	14.40	22.1
2	10255	10255:WVGD13	End	20.00	76.04	0.17	-2.62	211.01	-0.22	0.0	-29.19	15.16	-0.02	-1.17	16.15	0.32	0.00	17.33	26.7
2	10255	10255:WVGD13	Origin	20.00	76.04	0.17	-2.62	211.01	-0.22	0.0	-30.96	15.47	-0.02	-1.24	16.15	0.33	0.00	17.40	26.8
2	10255	Tube 1	End	25.00	70.17	0.16	-2.33	288.34	-0.33	0.0	-30.96	15.47	-0.02	-1.18	20.01	0.31	0.00	21.20	32.6
2	10255	Tube 1	Origin	25.00	70.17	0.16	-2.33	288.34	-0.33	0.0	-31.76	15.59	-0.03	-1.21	20.01	0.31	0.00	21.23	32.7
2	10255	10255:WVGD12	End	30.00	64.48	0.15	-2.06	366.27	-0.47	0.0	-31.76	15.59	-0.03	-1.16	23.15	0.30	0.00	24.31	37.4
2	10255	10255:WVGD12	Origin	30.00	64.48	0.15	-2.06	366.27	-0.47	0.0	-33.53	15.87	-0.03	-1.22	23.15	0.31	0.00	24.37	37.5
2	10255	Tube 1	End	32.69	61.51	0.14	-1.92	408.91	-0.55	0.0	-33.53	15.87	-0.03	-1.19	24.61	0.30	0.00	25.81	39.7
2	10255	Tube 1	Origin	32.69	61.51	0.14	-1.92	408.91	-0.55	0.0	-34.00	15.92	-0.03	-1.21	24.61	0.30	0.00	25.83	39.7
2	10255	10255:Arm3	End	35.38	58.60	0.13	-1.79	451.70	-0.64	0.0	-34.00	15.92	-0.03	-1.18	25.93	0.29	0.00	27.12	41.7
2	10255	10255:Arm3	Origin	35.38	58.60	0.13	-1.79	468.15	-0.64	0.0	-50.07	24.69	-0.04	-1.74	26.87	0.45	0.00	28.62	44.0
2	10255	10255:WVGD11	End	40.00	53.75	0.12	-1.57	582.32	-0.83	0.0	-50.07	24.69	-0.04	-1.67	30.89	0.44	0.00	32.57	50.1
2	10255	10255:WVGD11	Origin	40.00	53.75	0.12	-1.57	582.32	-0.83	0.0	-52.13	24.89	-0.04	-1.74	30.89	0.44	0.00	32.64	50.2
2	10255	Tube 1	End	45.00	48.75	0.11	-1.36	706.78	-1.05	0.0	-52.13	24.89	-0.04	-1.67	34.53	0.42	0.00	36.21	55.7
2	10255	Tube 1	Origin	45.00	48.75	0.11	-1.36	706.78	-1.05	0.0	-53.13	24.90	-0.05	-1.70	34.53	0.42	0.00	36.24	55.8
2	10255	10255:WVGD10	End	50.00	44.01	0.10	-1.17	831.28	-1.29	0.0	-53.13	24.90	-0.05	-1.64	37.54	0.41	0.00	39.18	60.3
2	10255	10255:WVGD10	Origin	50.00	44.01	0.10	-1.17	831.28	-1.29	0.0	-54.82	25.07	-0.05	-1.69	37.54	0.41	0.00	39.23	60.4
2	10255	SpliceF	End	50.33	43.71	0.10	-1.16	839.55	-1.30	0.0	-54.82	25.07	-0.05	-1.68	37.72	0.41	0.00	39.41	60.6
2	10255	SpliceF	Origin	50.33	43.71	0.10	-1.16	839.55	-1.30	0.0	-55.89	25.12	-0.05	-1.72	37.72	0.41	0.00	39.44	60.7
2	10255	SpliceB	End	55.00	39.55	0.09	-1.00	956.86	-1.55	0.0	-55.89	25.12	-0.05	-1.21	30.05	0.29	0.00	31.26	48.1
2	10255	SpliceB	Origin	55.00	39.55	0.09	-1.00	956.86	-1.55	0.0	-57.25	25.18	-0.06	-1.24	30.05	0.29	0.00	31.29	48.1

2	10255	10255:Arm4	End	57.38	37.52	0.09	-0.93	1016.67	-1.68	0.0	-57.25	25.18	-0.06	-1.22	30.80	0.28	0.00	32.02	49.3
2	10255	10255:Arm4	Origin	57.38	37.52	0.09	-0.93	1032.58	-1.69	0.0	-73.52	33.62	-0.06	-1.57	31.28	0.38	0.00	32.85	50.5
2	10255	10255:WVG09	End	60.00	35.33	0.08	-0.85	1120.82	-1.85	0.0	-73.52	33.62	-0.06	-1.54	32.65	0.37	0.00	34.20	52.6
2	10255	10255:WVG09	Origin	60.00	35.33	0.08	-0.85	1120.82	-1.85	0.0	-75.78	33.78	-0.07	-1.58	32.65	0.37	0.00	34.24	52.7
2	10255	Tube 2	End	65.00	31.34	0.08	-0.71	1289.70	-2.18	0.0	-75.78	33.78	-0.07	-1.53	34.96	0.36	0.00	36.49	56.1
2	10255	Tube 2	Origin	65.00	31.34	0.08	-0.71	1289.70	-2.18	0.0	-77.29	33.75	-0.07	-1.56	34.96	0.36	0.00	36.52	56.2
2	10255	10255:WVG08	End	70.00	27.59	0.07	-0.59	1458.46	-2.54	0.0	-77.29	33.75	-0.07	-1.50	36.87	0.35	0.00	38.38	59.0
2	10255	10255:WVG08	Origin	70.00	27.59	0.07	-0.59	1458.46	-2.54	0.0	-80.00	33.87	-0.08	-1.56	36.87	0.35	0.00	38.43	59.1
2	10255	Tube 2	End	75.00	24.08	0.06	-0.49	1627.82	-2.92	0.0	-80.00	33.87	-0.08	-1.51	38.47	0.34	0.00	39.98	61.5
2	10255	Tube 2	Origin	75.00	24.08	0.06	-0.49	1627.82	-2.92	0.0	-81.61	33.83	-0.08	-1.54	38.47	0.34	0.00	40.01	61.6
2	10255	10255:WVG07	End	80.00	20.83	0.05	-0.40	1796.97	-3.32	0.0	-81.61	33.83	-0.08	-1.49	39.79	0.33	0.00	41.28	63.5
2	10255	10255:WVG07	Origin	80.00	20.83	0.05	-0.40	1796.97	-3.32	0.0	-84.42	33.93	-0.09	-1.54	39.79	0.33	0.00	41.34	63.6
2	10255	Tube 2	End	85.00	17.83	0.05	-0.32	1966.60	-3.76	0.0	-84.42	33.93	-0.09	-1.49	40.89	0.32	0.00	42.38	65.2
2	10255	Tube 2	Origin	85.00	17.83	0.05	-0.32	1966.60	-3.76	0.0	-86.13	33.87	-0.09	-1.52	40.89	0.32	0.00	42.41	65.3
2	10255	10255:WVG06	End	90.00	15.07	0.04	-0.25	2135.96	-4.22	0.0	-86.13	33.87	-0.09	-1.48	41.78	0.31	0.00	43.25	66.5
2	10255	10255:WVG06	Origin	90.00	15.07	0.04	-0.25	2135.96	-4.22	0.0	-88.93	33.95	-0.10	-1.52	41.78	0.31	0.00	43.30	66.6
2	10255	Tube 2	End	94.42	12.85	0.03	-0.20	2285.86	-4.64	0.0	-88.93	33.95	-0.10	-1.48	42.42	0.30	0.00	43.91	67.6
2	10255	Tube 2	Origin	94.42	12.85	0.03	-0.20	2285.86	-4.64	0.0	-90.52	33.90	-0.10	-1.51	42.42	0.30	0.00	43.93	67.6
2	10255	SpliceT	End	98.83	10.81	0.03	-0.16	2435.53	-5.10	0.0	-90.52	33.90	-0.10	-1.47	42.95	0.29	0.00	44.42	68.3
2	10255	SpliceT	Origin	98.83	10.81	0.03	-0.16	2435.53	-5.10	0.0	-91.74	33.87	-0.11	-1.49	42.95	0.29	0.00	44.44	68.4
2	10255	10255:WVG05	End	100.00	10.30	0.03	-0.15	2475.15	-5.22	0.0	-91.74	33.87	-0.11	-1.41	41.94	0.28	0.00	43.36	66.7
2	10255	10255:WVG05	Origin	100.00	10.30	0.03	-0.15	2475.15	-5.22	0.0	-95.07	33.99	-0.11	-1.46	41.94	0.28	0.00	43.41	66.8
2	10255	SpliceB	End	105.00	8.28	0.02	-0.11	2645.11	-5.76	0.0	-95.07	33.99	-0.11	-1.42	42.33	0.27	0.00	43.76	67.3
2	10255	SpliceB	Origin	105.00	8.28	0.02	-0.11	2645.11	-5.76	0.0	-97.85	33.95	-0.12	-1.46	42.33	0.27	0.00	43.80	67.4
2	10255	10255:WVG04	End	110.00	6.49	0.02	-0.08	2814.83	-6.34	0.0	-97.85	33.95	-0.12	-1.42	42.61	0.26	0.00	44.04	67.7
2	10255	10255:WVG04	Origin	110.00	6.49	0.02	-0.08	2814.83	-6.34	0.0	-101.02	33.99	-0.12	-1.47	42.61	0.26	0.00	44.08	67.8
2	10255	Tube 3	End	115.00	4.93	0.01	-0.06	2984.78	-6.94	0.0	-101.02	33.99	-0.12	-1.43	42.80	0.25	0.00	44.24	68.1
2	10255	Tube 3	Origin	115.00	4.93	0.01	-0.06	2984.78	-6.94	0.0	-103.09	33.92	-0.13	-1.46	42.80	0.25	0.00	44.27	68.1
2	10255	10255:WVG03	End	120.00	3.59	0.01	-0.04	3154.35	-7.58	0.0	-103.09	33.92	-0.13	-1.42	42.91	0.25	0.00	44.34	68.2

2	10255	10255:WVG03	Origin	120.00	3.59	0.01	-0.04	3154.35	-7.58	0.0	-106.37	33.95	-0.13	-1.47	42.91	0.25	0.00	44.39	68.3
2	10255	Tube 3	End	125.00	2.47	0.01	-0.03	3324.10	-8.24	0.0	-106.37	33.95	-0.13	-1.43	42.96	0.24	0.00	44.40	68.3
2	10255	Tube 3	Origin	125.00	2.47	0.01	-0.03	3324.10	-8.24	0.0	-108.54	33.88	-0.14	-1.46	42.96	0.24	0.00	44.42	68.3
2	10255	10255:WVG02	End	130.00	1.57	0.00	-0.02	3493.47	-8.94	0.0	-108.54	33.88	-0.14	-1.42	42.95	0.23	0.00	44.37	68.3
2	10255	10255:WVG02	Origin	130.00	1.57	0.00	-0.02	3493.47	-8.94	0.0	-111.91	33.90	-0.15	-1.47	42.95	0.24	0.00	44.42	68.3
2	10255	Tube 3	End	135.00	0.88	0.00	-0.01	3662.97	-9.67	0.0	-111.91	33.90	-0.15	-1.43	42.89	0.23	0.00	44.32	68.2
2	10255	Tube 3	Origin	135.00	0.88	0.00	-0.01	3662.97	-9.67	0.0	-114.18	33.83	-0.15	-1.46	42.89	0.23	0.00	44.35	68.2
2	10255	10255:WVG01	End	140.00	0.39	0.00	-0.01	3832.09	-10.44	0.0	-114.18	33.83	-0.15	-1.43	42.78	0.22	0.00	44.21	68.0
2	10255	10255:WVG01	Origin	140.00	0.39	0.00	-0.01	3832.09	-10.44	0.0	-117.65	33.85	-0.16	-1.47	42.78	0.22	0.00	44.25	68.1
2	10255	Tube 3	End	145.00	0.10	0.00	-0.00	4001.31	-11.23	0.0	-117.65	33.85	-0.16	-1.44	42.64	0.22	0.00	44.08	67.8
2	10255	Tube 3	Origin	145.00	0.10	0.00	-0.00	4001.31	-11.23	0.0	-120.02	33.77	-0.17	-1.47	42.64	0.22	0.00	44.11	67.9
2	10255	End	150.00	0.00	0.00	0.00	0.00	4170.16	-12.06	0.0	-120.02	33.77	-0.17	-1.43	42.46	0.21	0.00	43.90	67.5

Detailed Tubular Davit Arm Usages for Load Case "NESC Heavy":

Element Label	Joint Label	Joint Position	Rel. Dist. (ft)	Trans. Defl. (in)	Long. Defl. (in)	Vert. Defl. (in)	Vert. Mom. (ft-k)	Horz. Mom. (ft-k)	Tors. Mom. (ft-k)	Axial Force (kips)	Vert. Shear (kips)	Horz. Shear (kips)	P/A (ksi)	M/S. (ksi)	V/Q. (ksi)	T/R. (ksi)	Res. Usage %	Max. At Pt.	
Davit1	Davit1:0	Origin	0.00	99.87	0.21	-2.79	-9.98	0.00	0.0	-1.34	1.06	-0.00	-0.20	6.99	0.00	0.00	7.18	11.1	1
Davit1	#Davit1:0	End	5.00	100.92	0.22	3.30	-4.69	0.00	0.0	-1.34	1.06	-0.00	-0.25	5.47	0.00	0.00	5.73	8.8	1
Davit1	#Davit1:0	Origin	5.00	100.92	0.22	3.30	-4.69	0.00	0.0	-1.33	0.95	-0.00	-0.25	5.47	0.00	0.00	5.72	8.8	1
Davit1	#Davit1:1	End	7.54	101.44	0.22	6.34	-2.28	0.00	0.0	-1.32	0.95	-0.00	-0.29	3.65	0.00	0.00	3.94	6.1	1
Davit1	#Davit1:1	Origin	7.54	101.44	0.22	6.34	-2.28	0.00	0.0	-1.31	0.90	-0.00	-0.29	3.65	0.00	0.00	3.94	6.1	1
Davit1	Davit1:End	End	10.07	101.96	0.22	9.35	-0.00	0.00	0.0	-1.31	0.90	-0.00	-0.35	0.00	0.51	0.00	0.94	1.5	3
Davit2	Davit2:0	Origin	0.00	99.76	0.21	-4.91	-12.82	-0.00	-0.0	1.06	1.34	0.00	0.15	8.98	0.00	0.00	9.13	14.0	1
Davit2	#Davit2:0	End	5.00	100.18	0.21	-11.26	-6.10	-0.00	-0.0	1.06	1.34	0.00	0.20	7.11	0.00	0.00	7.31	11.2	1
Davit2	#Davit2:0	Origin	5.00	100.18	0.21	-11.26	-6.10	-0.00	-0.0	1.06	1.23	0.00	0.20	7.11	0.00	0.00	7.31	11.2	1
Davit2	#Davit2:1	End	7.54	100.39	0.21	-14.54	-2.97	-0.00	-0.0	1.06	1.23	0.00	0.23	4.77	0.00	0.00	5.00	7.7	1
Davit2	#Davit2:1	Origin	7.54	100.39	0.21	-14.54	-2.97	-0.00	0.0	1.07	1.17	0.00	0.23	4.77	0.00	0.00	5.00	7.7	1
Davit2	Davit2:End	End	10.07	100.61	0.21	-17.86	0.00	0.00	0.0	1.07	1.17	0.00	0.28	0.00	0.66	0.00	1.18	1.8	3
Davit3	Davit3:0	Origin	0.00	84.12	0.18	-1.83	-99.22	0.03	0.0	-5.37	6.83	-0.00	-0.36	17.99	0.00	0.00	18.35	28.2	1
Davit3	#Davit3:0	End	5.00	85.22	0.19	4.08	-65.10	0.02	0.0	-5.37	6.83	-0.00	-0.43	17.25	0.00	0.00	17.68	27.2	1
Davit3	#Davit3:0	Origin	5.00	85.22	0.19	4.08	-65.10	0.02	0.0	-5.27	6.54	-0.00	-0.42	17.25	0.00	0.00	17.67	27.2	1
Davit3	#Davit3:1	End	10.00	86.25	0.19	9.74	-32.39	0.01	0.0	-5.27	6.54	-0.00	-0.53	13.71	0.00	0.00	14.24	21.9	1
Davit3	#Davit3:1	Origin	10.00	86.25	0.19	9.74	-32.39	0.01	0.0	-5.21	6.36	-0.00	-0.53	13.71	0.00	0.00	14.24	21.9	1
Davit3	#Davit3:2	End	12.57	86.76	0.19	12.55	-16.07	0.00	0.0	-5.21	6.36	-0.00	-0.61	9.10	0.00	0.00	9.71	14.9	1
Davit3	#Davit3:2	Origin	12.57	86.76	0.19	12.55	-16.07	0.00	0.0	-5.17	6.26	-0.00	-0.60	9.10	0.00	0.00	9.70	14.9	1
Davit3	Davit3:End	End	15.13	87.26	0.19	15.32	-0.00	0.00	0.0	-5.17	6.26	-0.00	-0.71	0.00	1.79	0.00	3.18	4.9	3
Davit4	Davit4:0	Origin	0.00	84.00	0.18	-4.23	-116.03	-0.02	-0.0	3.43	7.99	0.00	0.23	21.04	0.00	0.00	21.27	32.7	1
Davit4	#Davit4:0	End	5.00	84.50	0.18	-10.50	-76.10	-0.02	-0.0	3.43	7.99	0.00	0.27	20.16	0.00	0.00	20.44	31.4	1
Davit4	#Davit4:0	Origin	5.00	84.50	0.18	-10.50	-76.10	-0.02	-0.0	3.48	7.65	0.00	0.28	20.16	0.00	0.00	20.44	31.5	1
Davit4	#Davit4:1	End	10.00	85.02	0.18	-17.06	-37.85	-0.01	-0.0	3.48	7.65	0.00	0.35	16.02	0.00	0.00	16.37	25.2	1

Davit4	#Davit4:1	Origin	10.00	85.02	0.18	-17.06	-37.85	-0.01	-0.0	3.51	7.43	0.00	0.35	16.02	0.00	0.00	16.38	25.2	1
Davit4	#Davit4:2	End	12.57	85.28	0.18	-20.54	-18.77	-0.00	-0.0	3.51	7.43	0.00	0.41	10.63	0.00	0.00	11.04	17.0	1
Davit4	#Davit4:2	Origin	12.57	85.28	0.18	-20.54	-18.77	-0.00	0.0	3.52	7.32	0.00	0.41	10.63	0.00	0.00	11.04	17.0	1
Davit4	Davit4:End	End	15.13	85.55	0.18	-24.08	-0.00	0.00	0.0	3.52	7.32	0.00	0.49	0.00	2.09	0.00	3.66	5.6	3
Davit5	Davit5:0	Origin	0.00	58.66	0.13	-0.50	-100.27	0.03	0.0	-5.28	6.90	-0.00	-0.35	18.18	0.00	0.00	18.53	28.5	1
Davit5	#Davit5:0	End	5.00	59.58	0.14	4.65	-65.79	0.02	0.0	-5.28	6.90	-0.00	-0.42	17.43	0.00	0.00	17.85	27.5	1
Davit5	#Davit5:0	Origin	5.00	59.58	0.14	4.65	-65.79	0.02	0.0	-5.18	6.61	-0.00	-0.41	17.43	0.00	0.00	17.85	27.5	1
Davit5	#Davit5:1	End	10.00	60.44	0.14	9.54	-32.74	0.01	0.0	-5.18	6.61	-0.00	-0.52	13.86	0.00	0.00	14.38	22.1	1
Davit5	#Davit5:1	Origin	10.00	60.44	0.14	9.54	-32.74	0.01	0.0	-5.12	6.43	-0.00	-0.52	13.86	0.00	0.00	14.38	22.1	1
Davit5	#Davit5:2	End	12.57	60.86	0.14	11.96	-16.24	0.00	0.0	-5.12	6.43	-0.00	-0.60	9.20	0.00	0.00	9.79	15.1	1
Davit5	#Davit5:2	Origin	12.57	60.86	0.14	11.96	-16.24	0.00	0.0	-5.09	6.33	-0.00	-0.59	9.20	0.00	0.00	9.79	15.1	1
Davit5	Davit5:End	End	15.13	61.27	0.14	14.33	-0.00	0.00	0.0	-5.09	6.33	-0.00	-0.70	0.00	1.81	0.00	3.21	4.9	3
Davit6	Davit6:0	Origin	0.00	58.55	0.13	-3.08	-116.71	-0.02	-0.0	3.33	8.03	0.00	0.22	21.16	0.00	0.00	21.38	32.9	1
Davit6	#Davit6:0	End	5.00	59.02	0.13	-8.57	-76.56	-0.01	-0.0	3.33	8.03	0.00	0.27	20.28	0.00	0.00	20.55	31.6	1
Davit6	#Davit6:0	Origin	5.00	59.02	0.13	-8.57	-76.56	-0.01	-0.0	3.38	7.69	0.00	0.27	20.28	0.00	0.00	20.55	31.6	1
Davit6	#Davit6:1	End	10.00	59.51	0.13	-14.35	-38.08	-0.01	-0.0	3.38	7.69	0.00	0.34	16.12	0.00	0.00	16.46	25.3	1
Davit6	#Davit6:1	Origin	10.00	59.51	0.13	-14.35	-38.08	-0.01	-0.0	3.41	7.48	0.00	0.34	16.12	0.00	0.00	16.47	25.3	1
Davit6	#Davit6:2	End	12.57	59.77	0.13	-17.43	-18.89	-0.00	-0.0	3.41	7.48	0.00	0.40	10.70	0.00	0.00	11.10	17.1	1
Davit6	#Davit6:2	Origin	12.57	59.77	0.13	-17.43	-18.89	-0.00	0.0	3.43	7.36	0.00	0.40	10.70	0.00	0.00	11.10	17.1	1
Davit6	Davit6:End	End	15.13	60.02	0.13	-20.57	-0.00	0.00	0.0	3.43	7.36	0.00	0.47	0.00	2.10	0.00	3.68	5.7	3
Davit7	Davit7:0	Origin	0.00	37.56	0.09	0.26	-101.74	0.02	0.0	-5.15	7.00	-0.00	-0.34	18.45	0.00	0.00	18.79	28.9	1
Davit7	#Davit7:0	End	5.00	38.24	0.09	4.30	-66.77	0.01	0.0	-5.15	7.00	-0.00	-0.41	17.69	0.00	0.00	18.10	27.9	1
Davit7	#Davit7:0	Origin	5.00	38.24	0.09	4.30	-66.77	0.01	0.0	-5.06	6.71	-0.00	-0.40	17.69	0.00	0.00	18.10	27.8	1
Davit7	#Davit7:1	End	10.00	38.87	0.09	8.09	-33.23	0.01	0.0	-5.06	6.71	-0.00	-0.51	14.07	0.00	0.00	14.58	22.4	1
Davit7	#Davit7:1	Origin	10.00	38.87	0.09	8.09	-33.23	0.01	0.0	-5.00	6.52	-0.00	-0.50	14.07	0.00	0.00	14.57	22.4	1
Davit7	#Davit7:2	End	12.57	39.17	0.09	9.94	-16.49	0.00	0.0	-5.00	6.52	-0.00	-0.58	9.34	0.00	0.00	9.92	15.3	1
Davit7	#Davit7:2	Origin	12.57	39.17	0.09	9.94	-16.49	0.00	0.0	-4.97	6.42	-0.00	-0.58	9.34	0.00	0.00	9.92	15.3	1
Davit7	Davit7:End	End	15.13	39.47	0.10	11.74	-0.00	0.00	0.0	-4.97	6.42	-0.00	-0.69	0.00	1.84	0.00	3.25	5.0	3
Davit8	Davit8:0	Origin	0.00	37.47	0.09	-2.12	-117.64	-0.02	-0.0	3.18	8.09	0.00	0.21	21.33	0.00	0.00	21.54	33.1	1
Davit8	#Davit8:0	End	5.00	37.90	0.09	-6.48	-77.19	-0.01	-0.0	3.18	8.09	0.00	0.25	20.45	0.00	0.00	20.71	31.9	1
Davit8	#Davit8:0	Origin	5.00	37.90	0.09	-6.48	-77.19	-0.01	-0.0	3.23	7.76	0.00	0.26	20.45	0.00	0.00	20.71	31.9	1
Davit8	#Davit8:1	End	10.00	38.33	0.09	-11.14	-38.41	-0.01	-0.0	3.23	7.76	0.00	0.33	16.26	0.00	0.00	16.58	25.5	1
Davit8	#Davit8:1	Origin	10.00	38.33	0.09	-11.14	-38.41	-0.01	-0.0	3.27	7.54	0.00	0.33	16.26	0.00	0.00	16.59	25.5	1
Davit8	#Davit8:2	End	12.57	38.56	0.09	-13.65	-19.05	-0.00	-0.0	3.27	7.54	0.00	0.38	10.79	0.00	0.00	11.17	17.2	1
Davit8	#Davit8:2	Origin	12.57	38.56	0.09	-13.65	-19.05	-0.00	0.0	3.29	7.42	0.00	0.38	10.79	0.00	0.00	11.17	17.2	1
Davit8	Davit8:End	End	15.13	38.80	0.09	-16.21	-0.00	0.00	0.0	3.29	7.42	0.00	0.45	0.00	2.12	0.00	3.70	5.7	3

Summary of Clamp Capacities and Usages for Load Case "NESC Heavy":

Clamp Label	Force	Input Holding Capacity (kips)	Factored Holding Capacity (kips)	Usage %
Clamp1	1.565	80.00	80.00	1.96
Clamp2	1.565	80.00	80.00	1.96
Clamp3	8.074	80.00	80.00	10.09
Clamp4	8.074	80.00	80.00	10.09
Clamp5	8.074	80.00	80.00	10.09
Clamp6	8.074	80.00	80.00	10.09
Clamp7	8.074	80.00	80.00	10.09
Clamp8	8.074	80.00	80.00	10.09
Clamp9	10.694	80.00	80.00	13.37
Clamp10	4.377	80.00	80.00	5.47

Clamp11	1.153	80.00	80.00	1.44
Clamp12	1.153	80.00	80.00	1.44
Clamp13	1.153	80.00	80.00	1.44
Clamp14	1.153	80.00	80.00	1.44
Clamp15	1.153	80.00	80.00	1.44
Clamp16	1.153	80.00	80.00	1.44
Clamp17	1.153	80.00	80.00	1.44
Clamp18	1.153	80.00	80.00	1.44
Clamp19	1.153	80.00	80.00	1.44
Clamp20	1.153	80.00	80.00	1.44
Clamp21	1.153	80.00	80.00	1.44
Clamp22	1.153	80.00	80.00	1.44
Clamp23	1.153	80.00	80.00	1.44

*** Analysis Results for Load Case No. 2 "NESC Extreme" - Number of iterations in SABS 19

Equilibrium Joint Positions and Rotations for Load Case "NESC Extreme":

Joint Label	X-Displ (ft)	Y-Displ (ft)	Z-Displ (ft)	X-Rot (deg)	Y-Rot (deg)	Z-Rot (deg)	X-Pos (ft)	Y-Pos (ft)	Z-Pos (ft)
10255:9	0	0	0	0.0000	0.0000	0.0000	0	0	0
10255:t	0.005231	11.9	-0.6437	-8.5927	0.0033	0.0002	0.005231	11.9	149.4
10255:Arm1	0.005192	11.8	-0.6359	-8.5927	0.0033	0.0002	0.005192	11.8	148.7
10255:TopConn	0.005029	11.37	-0.6036	-8.5894	0.0033	0.0002	0.005029	11.37	145.8
10255:BotConn	0.004681	10.45	-0.5348	-8.4893	0.0033	0.0002	0.004681	10.45	139.7
10255:Arm2	0.004477	9.916	-0.4956	-8.3804	0.0032	0.0001	0.004477	9.916	136.1
10255:WVGDL3	0.004108	8.965	-0.4268	-8.1005	0.0032	0.0001	0.004108	8.965	129.6
10255:WVGDL2	0.003562	7.6	-0.3331	-7.5562	0.0031	0.0001	0.003562	7.6	119.7
10255:Arm3	0.003278	6.908	-0.2882	-7.2287	0.0030	0.0001	0.003278	6.908	114.3
10255:WVGDL1	0.00304	6.337	-0.2528	-6.9172	0.0029	0.0001	0.00304	6.337	109.7
10255:WVGDL0	0.002549	5.195	-0.187	-6.1765	0.0027	0.0001	0.002549	5.195	99.81
10255:Arm4	0.00221	4.432	-0.1474	-5.6929	0.0026	0.0001	0.00221	4.432	92.48
10255:WVGDL9	0.002094	4.175	-0.1347	-5.5294	0.0025	0.0001	0.002094	4.175	89.87
10255:WVGDL8	0.001675	3.266	-0.09303	-4.8829	0.0023	0.0000	0.001675	3.266	79.91
10255:WVGDL7	0.001297	2.471	-0.06113	-4.2192	0.0020	0.0000	0.001297	2.471	69.94
10255:WVGDL6	0.0009621	1.792	-0.03777	-3.5562	0.0018	0.0000	0.0009621	1.792	59.96
10255:WVGDL5	0.0006742	1.228	-0.02157	-2.9046	0.0015	0.0000	0.0006742	1.228	49.98
10255:WVGDL4	0.0004352	0.7752	-0.01105	-2.2759	0.0012	0.0000	0.0004352	0.7752	39.99
10255:WVGDL3	0.000247	0.4302	-0.004836	-1.6702	0.0009	0.0000	0.000247	0.4302	30
10255:WVGDL2	0.0001109	0.1889	-0.001656	-1.0888	0.0006	0.0000	0.0001109	0.1889	20
10255:WVGDL1	2.823e-005	0.04694	-0.0003799	-0.5322	0.0003	0.0000	2.823e-005	0.04694	10
Davit1:0	0.005201	11.81	-0.5092	-8.5927	0.0033	0.0002	0.005201	10.96	148.8
Davit1:End	0.005384	12.1	-0.9682	-8.5624	0.0033	0.0002	0.005384	1.248	151.5
Davit2:0	0.005182	11.79	-0.7626	-8.5927	0.0033	0.0002	0.005182	12.63	148.5
Davit2:End	0.005136	11.85	-2.278	-8.6674	0.0033	0.0002	0.005136	22.7	148.2
Davit3:0	0.004488	9.926	-0.3528	-8.3804	0.0032	0.0001	0.004488	8.947	136.3
Davit3:End	0.004765	10.37	-1.787	-8.2078	0.0032	0.0002	0.004765	-5.608	140.4
Davit4:0	0.004467	9.905	-0.6383	-8.3804	0.0032	0.0001	0.004467	10.88	136
Davit4:End	0.004414	10.04	-2.892	-8.6948	0.0032	0.0001	0.004414	26.02	135.7
Davit5:0	0.003288	6.917	-0.1363	-7.2287	0.0030	0.0001	0.003288	5.71	114.5
Davit5:End	0.003519	7.281	-1.709	-7.0444	0.0030	0.0001	0.003519	-8.926	118.3
Davit6:0	0.003268	6.898	-0.4402	-7.2287	0.0030	0.0001	0.003268	8.106	114.2
Davit6:End	0.003245	7.031	-2.391	-7.5532	0.0030	0.0001	0.003245	23.24	114.2
Davit7:0	0.002217	4.439	-0.007552	-5.6929	0.0026	0.0001	0.002217	3.03	92.62
Davit7:End	0.002389	4.705	-1.442	-5.4932	0.0026	0.0001	0.002389	-11.7	96.07
Davit8:0	0.002202	4.425	-0.2872	-5.6929	0.0026	0.0001	0.002202	5.835	92.34
Davit8:End	0.002208	4.551	-1.835	-6.0308	0.0026	0.0001	0.002208	20.96	92.79

Joint Support Reactions for Load Case "NESC Extreme":

Joint Label	X Force (kips)	Y Force (kips)	Z Comp. (kips)	Uplift Result. (%)	Result. Moment (ft-k)	X-M. Moment Usage (%)	Y-M. Moment Usage (%)	Z-M. Max. Usage (%)
10255:g	-0.05	0.0	-53.58	0.0	59.23	0.0	79.87	0.0
						0.0	6039.79	0.0
						0.0	-3.7	0.0
							-0.01	0.0

Detailed Steel Pole Usages for Load Case "NESC Extreme":

Element	Joint	Joint	Rel. Trans.	Long. Vert. Trans. Mom.	Long. Mom. Tors. Axial Tran. Long. P/A M/S. V/Q. T/R. Res. Max. At
---------	-------	-------	-------------	-------------------------	--

Label	Label Position	Dist. (ft)	Defl. (in)	Defl. (in)	Defl. (in)	(Local Mx) (ft-k)	(Local My) (ft-k)	Mom. (ft-k)	Force (kips)	Shear (kips)	Shear (kips)	(ksi)	(ksi)	(ksi)	(ksi)	(ksi)	Usage Pt. %
10255	10255:t	Origin	0.00	142.81	0.06	-7.72	-0.00	-0.00	-0.02	0.02	-0.00	-0.00	0.00	0.00	0.00	0.00	0.0
10255	10255:Arm1	End	0.70	141.55	0.06	-7.63	-0.00	-0.00	-0.02	0.02	-0.00	-0.00	0.00	0.00	0.00	0.00	0.0
10255	10255:Arm1	Origin	0.70	141.55	0.06	-7.63	-0.00	0.0	-0.83	1.67	-0.00	-0.04	0.06	0.16	0.00	0.30	0.5
10255	10255:TopConn	End	3.58	136.39	0.06	-7.24	-0.00	0.0	-0.83	1.67	-0.00	-0.04	0.74	0.04	0.00	0.78	1.2
10255	10255:TopConn	Origin	3.58	136.39	0.06	-7.24	-0.00	0.0	-1.51	22.05	-0.00	-0.07	0.00	2.15	0.00	3.73	5.7
10255	Tube 1	End	6.67	130.87	0.06	-6.83	-0.01	0.0	-1.51	22.05	-0.00	-0.07	7.64	0.54	0.00	7.76	11.9
10255	Tube 1	Origin	6.67	130.87	0.06	-6.83	-0.01	0.0	-1.76	22.24	-0.00	-0.08	7.64	0.55	0.00	7.77	12.0
10255	10255:BotConn	End	9.75	125.37	0.06	-6.42	-0.01	0.0	-1.76	22.24	-0.00	-0.19	13.64	0.22	0.00	13.84	21.3
10255	10255:BotConn	Origin	9.75	125.37	0.06	-6.42	-0.01	0.0	-4.20	9.23	-0.00	-0.18	15.54	0.21	0.00	15.72	24.2
10255	10255:Arm2	End	13.38	118.99	0.05	-5.95	-0.02	0.0	-4.20	9.23	-0.00	-0.18	15.54	0.21	0.00	15.72	24.2
10255	10255:Arm2	Origin	13.38	118.99	0.05	-5.95	-0.03	0.0	-10.21	20.39	-0.00	-0.44	17.44	0.46	0.00	17.89	27.5
10255	Tube 1	End	16.69	113.23	0.05	-5.53	-0.04	0.0	-10.21	20.39	-0.00	-0.42	21.79	0.45	0.00	22.22	34.2
10255	Tube 1	Origin	16.69	113.23	0.05	-5.53	-0.04	0.0	-10.53	20.58	-0.01	-0.44	21.79	0.45	0.00	22.24	34.2
10255	10255:WVGDI3	End	20.00	107.58	0.05	-5.12	-0.06	0.0	-11.53	20.58	-0.01	-0.42	25.57	0.44	0.00	26.01	40.0
10255	10255:WVGDI3	Origin	20.00	107.58	0.05	-5.12	-0.06	0.0	-11.24	21.08	-0.01	-0.45	25.57	0.45	0.00	26.04	40.1
10255	Tube 1	End	25.00	99.25	0.05	-4.54	-0.09	0.0	-11.24	21.08	-0.01	-0.43	30.49	0.43	0.00	30.93	47.6
10255	Tube 1	Origin	25.00	99.25	0.05	-4.54	-0.09	0.0	-11.78	21.38	-0.01	-0.45	30.49	0.43	0.00	30.95	47.6
10255	10255:WVGDI2	End	30.00	91.20	0.04	-4.00	-0.13	0.0	-12.50	21.87	-0.01	-0.46	34.52	0.42	0.00	34.98	53.8
10255	10255:WVGDI2	Origin	30.00	91.20	0.04	-4.00	-0.13	0.0	-12.82	22.03	-0.01	-0.46	34.52	0.42	0.00	34.98	53.8
10255	Tube 1	End	32.69	87.00	0.04	-3.72	-0.15	0.0	-12.82	22.03	-0.01	-0.44	36.42	0.41	0.00	36.87	56.7
10255	Tube 1	Origin	32.69	87.00	0.04	-3.72	-0.15	0.0	-12.50	21.87	-0.01	-0.44	36.42	0.41	0.00	36.88	56.7
10255	10255:Arm3	End	35.38	82.89	0.04	-3.46	-0.17	0.0	-12.82	22.03	-0.01	-0.46	38.13	0.40	0.00	38.58	59.4
10255	10255:Arm3	Origin	35.38	82.89	0.04	-3.46	-0.18	0.0	-19.23	33.09	-0.01	-0.67	39.36	0.61	0.00	40.04	61.6
10255	10255:WVGDI1	End	40.00	76.05	0.04	-3.03	-0.23	0.0	-19.23	33.09	-0.01	-0.64	44.48	0.58	0.00	45.13	69.4
10255	10255:WVGDI1	Origin	40.00	76.05	0.04	-3.03	-0.23	0.0	-20.19	33.61	-0.01	-0.64	44.48	0.59	0.00	45.16	69.5
10255	Tube 1	End	45.00	69.00	0.03	-2.62	-0.29	0.0	-20.19	33.61	-0.01	-0.65	49.18	0.57	0.00	49.83	76.7
10255	Tube 1	Origin	45.00	69.00	0.03	-2.62	-0.29	0.0	-20.94	33.88	-0.01	-0.67	49.18	0.57	0.00	49.86	76.7
10255	10255:WVGDI0	End	50.00	62.33	0.03	-2.24	-0.36	0.0	-20.94	33.88	-0.01	-0.65	53.09	0.56	0.00	53.77	82.7
10255	10255:WVGDI0	Origin	50.00	62.33	0.03	-2.24	-0.36	0.0	-21.64	34.28	-0.01	-0.66	53.33	0.56	0.00	54.01	83.1
10255	SpliceT	End	50.33	61.91	0.03	-2.22	-0.36	0.0	-22.38	34.46	-0.02	-0.68	53.33	0.56	0.00	54.03	83.1
10255	SpliceT	Origin	50.33	61.91	0.03	-2.22	-0.36	0.0	-22.38	34.46	-0.02	-0.68	53.33	0.56	0.00	54.03	83.1
10255	SpliceB	End	55.00	56.05	0.03	-1.91	-0.43	0.0	-23.32	34.72	-0.02	-0.51	42.33	0.40	0.00	42.84	65.9
10255	SpliceB	Origin	55.00	56.05	0.03	-1.91	-0.43	0.0	-23.32	34.72	-0.02	-0.51	42.33	0.40	0.00	42.84	65.9
10255	10255:Arm4	End	57.38	53.18	0.03	-1.77	-0.47	0.0	-30.06	45.55	-0.02	-0.60	43.33	0.39	0.00	43.83	67.4
10255	10255:Arm4	Origin	57.38	53.18	0.03	-1.77	-0.47	0.0	-30.06	45.55	-0.02	-0.60	43.33	0.39	0.00	43.83	67.4
10255	10255:WVGDI9	End	60.00	50.10	0.03	-1.62	-0.52	0.0	-30.06	45.55	-0.02	-0.63	45.77	0.50	0.00	46.41	71.4
10255	10255:WVGDI9	Origin	60.00	50.10	0.03	-1.62	-0.52	0.0	-31.16	46.02	-0.02	-0.65	45.77	0.51	0.00	46.43	71.4
10255	Tube 2	End	65.00	44.48	0.02	-1.35	-0.62	0.0	-31.16	46.02	-0.02	-0.63	48.82	0.49	0.00	49.45	76.1
10255	Tube 2	Origin	65.00	44.48	0.02	-1.35	-0.62	0.0	-32.26	46.32	-0.02	-0.65	48.82	0.49	0.00	49.47	76.1
10255	10255:WVGDI8	End	70.00	39.19	0.02	-1.12	-0.72	0.0	-32.26	46.32	-0.02	-0.63	51.38	0.48	0.00	52.05	80.1
10255	10255:WVGDI8	Origin	70.00	39.19	0.02	-1.12	-0.72	0.0	-33.69	46.86	-0.02	-0.66	51.38	0.48	0.00	52.05	80.1
10255	Tube 2	End	75.00	34.25	0.02	-0.91	-0.83	0.0	-33.69	46.86	-0.02	-0.63	53.57	0.47	0.00	54.24	83.4
10255	Tube 2	Origin	75.00	34.25	0.02	-0.91	-0.83	0.0	-34.87	47.16	-0.02	-0.66	53.57	0.47	0.00	54.24	83.4
10255	10255:WVGDI7	End	80.00	29.65	0.02	-0.73	-0.95	0.0	-34.87	47.16	-0.02	-0.64	55.41	0.45	0.00	56.05	86.2
10255	10255:WVGDI7	Origin	80.00	29.65	0.02	-0.73	-0.95	0.0	-36.37	47.70	-0.03	-0.64	56.98	0.45	0.00	57.63	88.7
10255	Tube 2	End	85.00	25.41	0.01	-0.58	-1.08	0.0	-36.37	47.70	-0.03	-0.64	56.98	0.45	0.00	57.63	88.7
10255	Tube 2	Origin	85.00	25.41	0.01	-0.58	-1.08	0.0	-37.61	48.01	-0.03	-0.66	56.98	0.45	0.00	57.65	88.7
10255	10255:WVGDI6	End	90.00	21.51	0.01	-0.45	-1.22	0.0	-37.61	48.01	-0.03	-0.64	58.30	0.43	0.00	58.94	90.7
10255	10255:WVGDI6	Origin	90.00	21.51	0.01	-0.45	-1.22	0.0	-39.10	48.54	-0.03	-0.67	58.30	0.44	0.00	58.97	90.7
10255	Tube 2	End	94.42	18.35	0.01	-0.36	-1.35	0.0	-39.10	48.54	-0.03	-0.65	59.29	0.43	0.00	59.95	92.2
10255	Tube 2	Origin	94.42	18.35	0.01	-0.36	-1.35	0.0	-40.24	48.82	-0.03	-0.67	59.29	0.43	0.00	59.97	92.2
10255	SpliceT	End	98.83	15.46	0.01	-0.28	-1.49	0.0	-40.24	48.82	-0.03	-0.65	60.13	0.42	0.00	60.79	93.5
10255	SpliceT	Origin	98.83	15.46	0.01	-0.28	-1.49	0.0	-41.11	49.00	-0.03	-0.67	60.13	0.42	0.00	60.81	93.5
10255	10255:WVGDI5	End	100.00	14.73	0.01	-0.26	-1.53	0.0	-41.11	49.00	-0.03	-0.63	58.76	0.40	0.00	59.40	91.4
10255	10255:WVGDI5	Origin	100.00	14.73	0.01	-0.26	-1.53	0.0	-42.92	49.47	-0.03	-0.66	58.76	0.40	0.00	59.42	91.4
10255	SpliceB	End	105.00	11.85	0.01	-0.19	-1.69	0.0	-42.92	49.47	-0.03	-0.64	59.45	0.39	0.00	60.09	92.5

10255	SpliceB	Origin	105.00	11.85	0.01	-0.19	3716.41	-1.69	0.0	-44.86	49.81	-0.04	-0.67	59.45	0.39	0.00	60.12	92.5	2
10255	10255:WVGD4	End	110.00	9.30	0.01	-0.13	3965.43	-1.87	0.0	-44.86	49.81	-0.04	-0.65	60.00	0.38	0.00	60.66	93.3	2
10255	10255:WVGD4	Origin	110.00	9.30	0.01	-0.13	3965.43	-1.87	0.0	-46.60	50.35	-0.04	-0.68	60.00	0.39	0.00	60.68	93.4	2
10255	Tube 3	End	115.00	7.07	0.00	-0.09	4217.18	-2.06	0.0	-46.60	50.35	-0.04	-0.66	60.45	0.38	0.00	61.11	94.0	2
10255	10255:WVGD3	Origin	115.00	7.07	0.00	-0.09	4217.18	-2.06	0.0	-48.07	50.68	-0.04	-0.68	60.45	0.38	0.00	61.13	94.0	2
10255	10255:WVGD3	End	120.00	5.16	0.00	-0.06	4470.56	-2.26	0.0	-48.07	50.68	-0.04	-0.66	60.79	0.37	0.00	61.48	94.6	2
10255	10255:WVGD3	End	125.00	3.56	0.00	-0.04	4726.71	-2.46	0.0	-49.87	51.23	-0.04	-0.69	60.79	0.37	0.00	61.73	95.0	2
10255	Tube 3	Origin	125.00	3.56	0.00	-0.04	4726.71	-2.46	0.0	-51.39	51.57	-0.04	-0.67	61.06	0.36	0.00	61.95	95.0	2
10255	10255:WVGD2	End	130.00	2.27	0.00	-0.02	4984.54	-2.68	0.0	-53.26	52.13	-0.05	-0.70	61.25	0.36	0.00	61.92	95.3	2
10255	10255:WVGD2	End	135.00	1.27	0.00	-0.01	5245.18	-2.91	0.0	-53.26	52.13	-0.05	-0.68	61.38	0.35	0.00	62.06	95.5	2
10255	Tube 3	Origin	135.00	1.27	0.00	-0.01	5245.18	-2.91	0.0	-54.84	52.48	-0.05	-0.70	61.38	0.36	0.00	62.08	95.5	2
10255	10255:WVGD1	End	140.00	0.56	0.00	-0.00	5507.55	-3.16	0.0	-56.76	53.05	-0.05	-0.69	61.45	0.35	0.00	62.14	95.6	2
10255	10255:WVGD1	Origin	140.00	0.56	0.00	-0.00	5507.55	-3.16	0.0	-56.76	53.05	-0.05	-0.71	61.45	0.35	0.00	62.16	95.6	2
10255	Tube 3	End	145.00	0.14	0.00	-0.00	5772.77	-3.41	0.0	-56.76	53.05	-0.05	-0.69	61.48	0.34	0.00	62.17	95.7	2
10255	Tube 3	Origin	145.00	0.14	0.00	-0.00	5772.77	-3.41	0.0	-58.40	53.40	-0.05	-0.71	61.48	0.34	0.00	62.19	95.7	2
10255	10255:g	End	150.00	0.00	0.00	0.00	6039.79	-3.68	0.0	-58.40	53.40	-0.05	-0.70	61.46	0.34	0.00	62.16	95.6	2

Detailed Tubular Davit Arm Usages for Load Case "NESC Extreme":

Element Label	Joint Label	Joint Position	Rel. Dist. (ft)	Trans. Defl. (in)	Long. Defl. (in)	Vert. Defl. (in)	Vert. Mom. (ft-k)	Horz. Tors. (ft-k)	Horz. Mom. (ft-k)	Axial Force (kips)	Shear (kips)	Horz. Shear (kips)	P/A (ksi)	M/S (ksi)	V/Q (ksi)	T/R (ksi)	Res. Usage %	Max. Pt.	At
Davit1	Davit1:0	Origin	0.00	141.67	0.06	-6.11	-1.55	0.00	-0.0	-0.80	0.20	-0.00	-0.12	1.09	0.00	0.00	1.21	1.9	1
Davit1	#Davit1:0	End	5.00	143.40	0.06	2.70	-0.58	0.00	-0.0	-0.80	0.20	-0.00	-0.15	0.67	0.00	0.00	0.82	1.3	1
Davit1	#Davit1:0	Origin	5.00	143.40	0.06	2.70	-0.58	0.00	0.0	-0.78	0.13	-0.00	-0.15	0.67	0.00	0.00	0.82	1.3	1
Davit1	#Davit1:1	End	7.54	144.28	0.06	7.16	-0.24	0.00	0.0	-0.78	0.13	-0.00	-0.17	0.39	0.00	0.00	0.56	0.9	1
Davit1	#Davit1:1	Origin	7.54	144.28	0.06	7.16	-0.24	0.00	0.0	-0.77	0.10	-0.00	-0.17	0.39	0.00	0.00	0.56	0.9	1
Davit1	Davit1:End	End	10.07	145.16	0.06	11.62	-0.00	0.00	0.0	-0.77	0.10	-0.00	-0.20	0.00	0.05	0.00	0.22	0.3	3
Davit2	Davit2:0	Origin	0.00	141.44	0.06	-9.15	-3.43	-0.00	-0.0	0.73	0.39	0.00	0.11	2.41	0.00	0.00	2.51	3.9	1
Davit2	#Davit2:0	End	5.00	141.84	0.06	-18.16	-1.50	-0.00	-0.0	0.73	0.39	0.00	0.14	1.74	0.00	0.00	1.88	2.9	1
Davit2	#Davit2:0	Origin	5.00	141.84	0.06	-18.16	-1.50	-0.00	-0.0	0.73	0.31	0.00	0.14	1.74	0.00	0.00	1.88	2.9	1
Davit2	#Davit2:1	End	7.54	142.04	0.06	-22.74	-0.70	-0.00	-0.0	0.73	0.31	0.00	0.16	1.12	0.00	0.00	1.28	2.0	1
Davit2	#Davit2:1	Origin	7.54	142.04	0.06	-22.74	-0.70	-0.00	0.0	0.72	0.28	0.00	0.16	1.12	0.00	0.00	1.28	2.0	1
Davit2	Davit2:End	End	10.07	142.24	0.06	-27.34	0.00	0.00	0.0	0.72	0.28	0.00	0.19	0.00	0.16	0.00	0.33	0.5	3
Davit3	Davit3:0	Origin	0.00	119.11	0.05	-4.23	-27.41	0.01	0.0	-5.77	1.99	-0.00	-0.38	4.97	0.00	0.00	5.35	8.2	1
Davit3	#Davit3:0	End	5.00	120.90	0.05	4.32	-17.48	0.00	0.0	-5.77	1.99	-0.00	-0.46	4.63	0.00	0.00	5.09	7.8	1
Davit3	#Davit3:0	Origin	5.00	120.90	0.05	4.32	-17.48	0.00	0.0	-5.71	1.80	-0.00	-0.46	4.63	0.00	0.00	5.09	7.8	1
Davit3	#Davit3:1	End	10.00	122.66	0.06	12.80	-8.47	0.00	0.0	-5.71	1.80	-0.00	-0.58	3.59	0.00	0.00	4.16	6.4	1
Davit3	#Davit3:1	Origin	10.00	122.66	0.06	12.80	-8.47	0.00	0.0	-5.68	1.68	-0.00	-0.57	3.59	0.00	0.00	4.16	6.4	1
Davit3	#Davit3:2	End	12.57	123.56	0.06	17.13	-4.15	0.00	0.0	-5.68	1.68	-0.00	-0.66	2.35	0.00	0.00	3.01	4.6	1
Davit3	#Davit3:2	Origin	12.57	123.56	0.06	17.13	-4.15	0.00	0.0	-5.65	1.62	-0.00	-0.66	2.35	0.00	0.00	3.01	4.6	1
Davit3	Davit3:End	End	15.13	124.45	0.06	21.45	-0.00	0.00	0.0	-5.65	1.62	-0.00	-0.78	0.00	0.46	0.00	1.12	1.7	3
Davit4	Davit4:0	Origin	0.00	118.86	0.05	-7.66	-48.99	-0.00	-0.0	5.05	3.45	0.00	0.33	8.88	0.00	0.00	9.22	14.2	1
Davit4	#Davit4:0	End	5.00	119.38	0.05	-16.48	-31.75	-0.00	-0.0	5.05	3.45	0.00	0.40	8.41	0.00	0.00	8.82	13.6	1
Davit4	#Davit4:0	Origin	5.00	119.38	0.05	-16.48	-31.75	-0.00	-0.0	5.05	3.23	0.00	0.40	8.41	0.00	0.00	8.82	13.6	1
Davit4	#Davit4:1	End	10.00	119.90	0.05	-25.42	-15.62	-0.00	-0.0	5.05	3.23	0.00	0.51	6.61	0.00	0.00	7.12	11.0	1
Davit4	#Davit4:1	Origin	10.00	119.90	0.05	-25.42	-15.62	-0.00	-0.0	5.06	3.08	0.00	0.51	6.61	0.00	0.00	7.12	11.0	1
Davit4	#Davit4:2	End	12.57	120.17	0.05	-30.05	-7.71	-0.00	-0.0	5.06	3.08	0.00	0.59	4.37	0.00	0.00	4.96	7.6	1
Davit4	#Davit4:2	Origin	12.57	120.17	0.05	-30.05	-7.71	-0.00	0.0	5.06	3.00	0.00	0.59	4.37	0.00	0.00	4.96	7.6	1
Davit4	Davit4:End	End	15.13	120.43	0.05	-34.71	-0.00	0.00	0.0	5.06	3.00	0.00	0.70	0.00	0.86	0.00	1.64	2.5	3
Davit5	Davit5:0	Origin	0.00	83.01	0.04	-1.64	-29.19	0.01	0.0	-5.73	2.11	-0.00	-0.38	5.29	0.00	0.00	5.67	8.7	1

Davit5	#Davit5:0	End	5.00	84.47	0.04	5.75	-18.66	0.00	0.0	-5.73	2.11	-0.00	-0.46	4.94	0.00	0.00	5.40	8.3	1
Davit5	#Davit5:0	Origin	5.00	84.47	0.04	5.75	-18.66	0.00	0.0	-5.68	1.92	-0.00	-0.45	4.94	0.00	0.00	5.40	8.3	1
Davit5	#Davit5:1	End	10.00	85.91	0.04	13.06	-9.07	0.00	0.0	-5.68	1.92	-0.00	-0.57	3.84	0.00	0.00	4.41	6.8	1
Davit5	#Davit5:1	Origin	10.00	85.91	0.04	13.06	-9.07	0.00	0.0	-5.64	1.80	-0.00	-0.57	3.84	0.00	0.00	4.41	6.8	1
Davit5	#Davit5:2	End	12.57	86.65	0.04	16.79	-4.45	0.00	0.0	-5.64	1.80	-0.00	-0.66	2.52	0.00	0.00	3.18	4.9	1
Davit5	#Davit5:2	Origin	12.57	86.65	0.04	16.79	-4.45	0.00	0.0	-5.62	1.73	-0.00	-0.66	2.52	0.00	0.00	3.17	4.9	1
Davit5	#Davit5:2	End	15.13	87.38	0.04	20.51	-0.00	0.00	0.0	-5.62	1.73	-0.00	-0.78	0.00	0.50	0.00	1.16	1.8	3
Davit6	#Davit6:0	Origin	0.00	82.78	0.04	-5.28	-50.51	-0.00	-0.0	4.98	3.55	0.00	0.33	9.16	0.00	0.00	9.49	14.6	1
Davit6	#Davit6:0	End	5.00	83.30	0.04	-12.89	-32.76	-0.00	-0.0	4.98	3.55	0.00	0.40	8.68	0.00	0.00	9.08	14.0	1
Davit6	#Davit6:0	Origin	5.00	83.30	0.04	-12.89	-32.76	-0.00	-0.0	4.99	3.33	0.00	0.40	8.68	0.00	0.00	9.08	14.0	1
Davit6	#Davit6:1	End	10.00	83.83	0.04	-20.63	-16.13	-0.00	-0.0	4.99	3.33	0.00	0.50	6.83	0.00	0.00	7.33	11.3	1
Davit6	#Davit6:1	Origin	10.00	83.83	0.04	-20.63	-16.13	-0.00	-0.0	4.99	3.33	0.00	0.50	6.83	0.00	0.00	7.33	11.3	1
Davit6	#Davit6:2	End	12.57	84.10	0.04	-24.65	-7.97	-0.00	-0.0	4.99	3.18	0.00	0.58	4.51	0.00	0.00	5.09	7.8	1
Davit6	#Davit6:2	Origin	12.57	84.10	0.04	-24.65	-7.97	-0.00	-0.0	5.00	3.10	0.00	0.58	4.51	0.00	0.00	5.09	7.8	1
Davit6	#Davit6:2	End	15.13	84.37	0.04	-28.70	-0.00	0.00	0.0	5.00	3.10	0.00	0.69	0.00	0.89	0.00	1.68	2.6	3
Davit7	#Davit7:0	Origin	0.00	53.27	0.03	-0.09	-31.53	0.01	0.0	-5.67	2.26	-0.00	-0.38	5.72	0.00	0.00	6.09	9.4	1
Davit7	#Davit7:0	End	5.00	54.34	0.03	5.73	-20.21	0.00	0.0	-5.67	2.26	-0.00	-0.45	5.36	0.00	0.00	5.81	8.9	1
Davit7	#Davit7:0	Origin	5.00	54.34	0.03	5.73	-20.21	0.00	0.0	-5.62	2.07	-0.00	-0.45	5.36	0.00	0.00	5.81	8.9	1
Davit7	#Davit7:1	End	10.00	55.39	0.03	11.47	-9.85	0.00	0.0	-5.62	2.07	-0.00	-0.57	4.17	0.00	0.00	4.74	7.3	1
Davit7	#Davit7:1	Origin	10.00	55.39	0.03	11.47	-9.85	0.00	0.0	-5.59	1.95	-0.00	-0.56	4.17	0.00	0.00	4.73	7.3	1
Davit7	#Davit7:2	End	12.57	55.93	0.03	14.39	-4.84	0.00	0.0	-5.59	1.95	-0.00	-0.65	2.74	0.00	0.00	3.39	5.2	1
Davit7	#Davit7:2	Origin	12.57	55.93	0.03	14.39	-4.84	0.00	0.0	-5.57	1.89	-0.00	-0.65	2.74	0.00	0.00	3.39	5.2	1
Davit7	#Davit7:2	End	15.13	56.46	0.03	17.30	-0.00	0.00	0.0	-5.57	1.89	-0.00	-0.77	0.00	0.54	0.00	1.21	1.9	3
Davit8	#Davit8:0	Origin	0.00	53.10	0.03	-3.45	-52.51	-0.00	-0.0	4.88	3.68	0.00	0.32	9.52	0.00	0.00	9.84	15.1	1
Davit8	#Davit8:0	End	5.00	53.60	0.03	-9.45	-34.10	-0.00	-0.0	4.88	3.68	0.00	0.39	9.04	0.00	0.00	9.43	14.5	1
Davit8	#Davit8:0	Origin	5.00	53.60	0.03	-9.45	-34.10	-0.00	-0.0	4.90	3.46	0.00	0.39	9.04	0.00	0.00	9.43	14.5	1
Davit8	#Davit8:1	End	10.00	54.10	0.03	-15.59	-16.81	-0.00	-0.0	4.90	3.46	0.00	0.49	7.12	0.00	0.00	7.61	11.7	1
Davit8	#Davit8:1	Origin	10.00	54.10	0.03	-15.59	-16.81	-0.00	-0.0	4.91	3.31	0.00	0.50	7.12	0.00	0.00	7.61	11.7	1
Davit8	#Davit8:2	End	12.57	54.36	0.03	-18.79	-8.30	-0.00	-0.0	4.91	3.31	0.00	0.57	4.70	0.00	0.00	5.27	8.1	1
Davit8	#Davit8:2	Origin	12.57	54.36	0.03	-18.79	-8.30	-0.00	-0.0	4.91	3.24	0.00	0.57	4.70	0.00	0.00	5.28	8.1	1
Davit8	#Davit8:2	End	15.13	54.62	0.03	-22.02	-0.00	0.00	0.0	4.91	3.24	0.00	0.68	0.00	0.93	0.00	1.74	2.7	3

Summary of Clamp Capacities and Usages for Load Case "NESC Extreme":

Clamp Label	Force (kips)	Input Holding Capacity (kips)	Factored Holding Capacity (kips)	Usage %
Clamp1	0.768	80.00	80.00	0.96
Clamp2	0.768	80.00	80.00	0.96
Clamp3	5.864	80.00	80.00	7.33
Clamp4	5.864	80.00	80.00	7.33
Clamp5	5.864	80.00	80.00	7.33
Clamp6	5.864	80.00	80.00	7.33
Clamp7	5.864	80.00	80.00	7.33
Clamp8	5.864	80.00	80.00	7.33
Clamp9	20.216	80.00	80.00	25.27
Clamp10	13.386	80.00	80.00	16.73
Clamp11	0.379	80.00	80.00	0.47
Clamp12	0.379	80.00	80.00	0.47
Clamp13	0.379	80.00	80.00	0.47
Clamp14	0.379	80.00	80.00	0.47
Clamp15	0.379	80.00	80.00	0.47
Clamp16	0.379	80.00	80.00	0.47

Clamp17	0.379	80.00	80.00	0.47
Clamp18	0.379	80.00	80.00	0.47
Clamp19	0.379	80.00	80.00	0.47
Clamp20	0.379	80.00	80.00	0.47
Clamp21	0.379	80.00	80.00	0.47
Clamp22	0.379	80.00	80.00	0.47
Clamp23	0.379	80.00	80.00	0.47

*** Overall summary for all load cases - Usage = Maximum Stress / Allowable Stress

Summary of Steel Pole Usages:

Steel Pole Maximum Label Usage %	Load Case Segment Number	Weight (lbs)
10255	95.68 NESC Extreme	37 30952.3

Base Plate Results by Bend Line:

Pole Label	Load Case	Bend Line #	Start X (ft)	Start Y (ft)	End X (ft)	End Y (ft)	Length (in)	Banding Stress (ksi)	Mon. Sum (ft-k)	Bolt #	Acting Max Load (kips)	Bolt Min Thickness (in)	Actual Thickness (in)	Usage %
10255	NESC Heavy	1	2.364	1.329	-0.017	2.704	32.990	37.315	153.881	6	100.212	2.366	3.000	62.19
10255	NESC Heavy	2	2.704	-0.017	1.329	2.364	32.990	13.980	57.649	4	86.023	1.448	3.000	23.30
10255	NESC Heavy	3	2.333	-0.375	2.333	0.375	9.010	1.519	1.711	1	4.558	0.477	3.000	2.53
10255	NESC Heavy	4	1.329	-2.364	2.704	0.017	32.990	12.039	49.645	4	-76.475	1.344	3.000	20.06
10255	NESC Heavy	5	-0.017	-2.704	2.364	-1.329	32.990	33.267	137.185	6	-90.316	2.234	3.000	55.44
10255	NESC Heavy	6	-1.500	-2.333	1.500	-2.333	36.011	37.577	169.146	5	-90.316	2.374	3.000	62.63
10255	NESC Heavy	7	-2.364	-1.329	0.017	-2.704	32.990	33.060	136.335	6	-90.111	2.227	3.000	55.10
10255	NESC Heavy	8	-2.704	0.017	-1.329	-2.364	32.990	11.887	49.019	4	-75.922	1.335	3.000	19.81
10255	NESC Heavy	9	-2.333	0.375	-2.333	-0.375	9.010	1.848	2.081	1	5.543	0.526	3.000	3.08
10255	NESC Heavy	10	-1.329	2.364	-2.704	-0.017	32.990	14.137	58.300	4	86.576	1.456	3.000	23.56
10255	NESC Heavy	11	0.017	2.704	-2.364	1.329	32.990	37.522	154.732	6	100.417	2.372	3.000	62.54
10255	NESC Heavy	12	1.500	2.333	-1.500	2.333	36.011	41.789	188.107	5	100.417	2.504	3.000	69.65
10255	NESC Heavy	13	1.671	2.053	-0.630	2.669	28.583	35.766	127.788	5	100.315	2.316	3.000	59.61
10255	NESC Heavy	14	2.312	1.103	0.707	2.708	27.239	27.419	93.359	4	100.008	2.028	3.000	45.70
10255	NESC Heavy	15	2.566	-0.246	2.053	1.671	23.810	4.443	13.223	2	58.063	0.816	3.000	7.40
10255	NESC Heavy	16	2.053	-1.671	2.566	0.246	23.810	3.783	11.260	2	-48.803	0.753	3.000	6.31
10255	NESC Heavy	17	0.707	-2.708	2.312	-1.103	27.239	24.132	82.166	4	-90.316	2.197	3.000	40.22
10255	NESC Heavy	18	-0.630	-2.669	1.671	-2.053	28.583	32.178	114.969	5	-90.316	2.193	3.000	53.63
10255	NESC Heavy	19	-1.671	-2.053	0.630	-2.669	28.583	32.072	114.591	5	-90.213	2.193	3.000	53.45
10255	NESC Heavy	20	-2.312	-1.103	-0.707	-2.708	27.239	23.915	81.428	4	-89.906	1.894	3.000	39.86
10255	NESC Heavy	21	-2.566	0.246	-2.053	-1.671	23.810	3.790	11.280	2	-47.962	0.754	3.000	6.32
10255	NESC Heavy	22	-2.053	1.671	-2.566	-0.246	23.810	4.569	13.599	2	58.904	0.828	3.000	7.62
10255	NESC Heavy	23	-0.707	2.708	-2.312	1.103	27.239	27.636	94.098	4	100.417	2.036	3.000	46.06
10255	NESC Heavy	24	0.630	2.669	-1.671	2.053	28.583	35.871	128.166	5	100.417	2.320	3.000	59.79
10255	NESC Extreme	1	2.364	1.329	-0.017	2.704	32.990	52.121	214.938	6	140.294	2.796	3.000	86.87
10255	NESC Extreme	2	2.704	-0.017	1.329	2.364	32.990	19.317	79.659	4	120.059	1.702	3.000	32.19
10255	NESC Extreme	3	2.333	-0.375	2.333	0.375	9.010	0.773	0.870	1	2.318	0.340	3.000	1.29
10255	NESC Extreme	4	1.329	-2.364	2.704	0.017	32.990	18.340	75.631	4	-115.292	1.659	3.000	30.57
10255	NESC Extreme	5	-0.017	-2.704	2.364	-1.329	32.990	50.105	206.623	6	-135.420	2.741	3.000	83.51
10255	NESC Extreme	6	-1.500	-2.333	1.500	-2.333	36.011	56.445	254.078	5	-135.420	2.910	3.000	94.07
10255	NESC Extreme	7	-2.364	-1.329	0.017	-2.704	32.990	50.042	206.364	6	-135.358	2.740	3.000	83.40
10255	NESC Extreme	8	-2.704	0.017	-1.329	-2.364	32.990	18.294	75.440	4	-115.124	1.657	3.000	30.49
10255	NESC Extreme	9	-2.333	0.375	-2.333	-0.375	9.010	0.873	0.983	1	2.618	0.362	3.000	1.45
10255	NESC Extreme	10	-1.329	2.364	-2.704	-0.017	32.990	19.365	79.858	4	120.228	1.704	3.000	32.28
10255	NESC Extreme	11	0.017	2.704	-2.364	1.329	32.990	52.184	215.197	6	140.356	2.798	3.000	86.97
10255	NESC Extreme	12	1.500	2.333	-1.500	2.333	36.011	58.503	263.343	5	140.356	2.962	3.000	97.50
10255	NESC Extreme	13	1.671	2.053	-0.630	2.669	28.583	50.089	178.963	5	140.325	2.741	3.000	83.48
10255	NESC Extreme	14	2.312	1.103	0.707	2.708	27.239	38.155	129.912	4	140.231	2.392	3.000	63.59
10255	NESC Extreme	15	2.566	-0.246	2.053	1.671	23.810	5.835	17.355	2	79.729	0.936	3.000	9.72
10255	NESC Extreme	16	2.053	-1.671	2.566	0.246	23.810	5.501	16.373	2	-75.049	0.908	3.000	9.17
10255	NESC Extreme	17	0.707	-2.708	2.312	-1.103	27.239	36.508	124.307	4	-135.420	2.340	3.000	60.85

10255	NESC Extreme	18	-0.630	-2.669	1.671	-2.053	28.583	48.316	172.630	5	-135.420	2.692	3.000	80.53
10255	NESC Extreme	19	-1.671	-2.053	0.630	-2.669	28.583	48.284	172.515	5	-135.389	2.691	3.000	80.47
10255	NESC Extreme	20	-2.312	-1.103	-0.707	-2.708	27.239	36.442	124.082	4	-135.296	2.338	3.000	60.74
10255	NESC Extreme	21	-2.566	0.246	-2.053	-1.671	23.810	5.503	16.379	2	-74.793	0.909	3.000	9.17
10255	NESC Extreme	22	-2.053	1.671	-2.566	-0.246	23.810	5.873	17.480	2	79.985	0.939	3.000	9.79
10255	NESC Extreme	23	-0.707	2.708	-2.312	1.103	27.239	38.221	130.137	4	140.356	2.394	3.000	63.70
10255	NESC Extreme	24	0.630	2.669	-1.671	2.053	28.583	50.121	179.078	5	140.356	2.742	3.000	83.53

Summary of Tubular Davit Usages:

Tubular Davit	Maximum Label Usage %	Load Case	Segment Number	Weight (lbs)
Davit1	11.05	NESC Heavy	1	182.3
Davit2	14.05	NESC Heavy	1	182.3
Davit3	28.23	NESC Heavy	1	575.0
Davit4	32.72	NESC Heavy	1	575.0
Davit5	28.51	NESC Heavy	1	575.0
Davit6	32.89	NESC Heavy	1	575.0
Davit7	28.91	NESC Heavy	1	575.0
Davit8	33.14	NESC Heavy	1	575.0

*** Maximum Stress Summary for Each Load Case

Summary of Maximum Usages by Load Case:

Load Case	Maximum Usage %	Element Label	Element Type
NESC Heavy	69.65	10255	Base Plate
NESC Extreme	97.50	10255	Base Plate

Summary of Steel Pole Usages by Load Case:

Load Case	Maximum Usage %	Steel Pole Segment Label	Number
NESC Heavy	68.37	10255	27
NESC Extreme	95.68	10255	37

Summary of Base Plate Usages by Load Case:

Load Case	Pole Band Label Line #	Length Vertical Load	X Moment	Y Moment	Bending Stress	Bolt #	Bolts Acting On Band Line	Max Bolt Load For Band Line	Minimum Plate Thickness	Usage %		
		(in)	(kips)	(ft-k)	(ksi)			(kips)	(in)			
NESC Heavy	10255	12	36.011	121.214	4170.162	-12.064	41.789	188.107	5	100.417	2.504	69.65
NESC Extreme	10255	12	36.011	59.228	6039.786	-3.676	58.503	263.343	5	140.356	2.962	97.50

Summary of Tubular Davit Usages by Load Case:

Load Case	Maximum Usage %	Tubular Davit Label	Segment Number
NESC Heavy	33.14	Davit8	1
NESC Extreme	15.15	Davit8	1

Summary of Insulator Usages:

Insulator		Insulator Maximum	Load Case Weight	
Label	Type	Usage %	(lbs)	
Clamp1	Clamp	1.96	NESC Heavy	0.0
Clamp2	Clamp	1.96	NESC Heavy	0.0
Clamp3	Clamp	10.09	NESC Heavy	0.0
Clamp4	Clamp	10.09	NESC Heavy	0.0
Clamp5	Clamp	10.09	NESC Heavy	0.0
Clamp6	Clamp	10.09	NESC Heavy	0.0
Clamp7	Clamp	10.09	NESC Heavy	0.0
Clamp8	Clamp	10.09	NESC Heavy	0.0
Clamp9	Clamp	25.27	NESC Extreme	0.0
Clamp10	Clamp	16.73	NESC Extreme	0.0
Clamp11	Clamp	1.44	NESC Heavy	0.0
Clamp12	Clamp	1.44	NESC Heavy	0.0
Clamp13	Clamp	1.44	NESC Heavy	0.0
Clamp14	Clamp	1.44	NESC Heavy	0.0
Clamp15	Clamp	1.44	NESC Heavy	0.0
Clamp16	Clamp	1.44	NESC Heavy	0.0
Clamp17	Clamp	1.44	NESC Heavy	0.0
Clamp18	Clamp	1.44	NESC Heavy	0.0
Clamp19	Clamp	1.44	NESC Heavy	0.0
Clamp20	Clamp	1.44	NESC Heavy	0.0
Clamp21	Clamp	1.44	NESC Heavy	0.0
Clamp22	Clamp	1.44	NESC Heavy	0.0
Clamp23	Clamp	1.44	NESC Heavy	0.0

Loads At Insulator Attachments For All Load Cases:

Load Insulator		Insulator	Structure		Structure		Structure		Structure	
Case	Label	Type	Attach Label	Attach Load X (kips)	Attach Load Y (kips)	Attach Load Z (kips)	Attach Load Res. (kips)	Attach	Attach	Attach
NESC Heavy	Clamp1	Clamp	David1:End	0.000	1.078	1.134	1.565			
NESC Heavy	Clamp2	Clamp	David2:End	0.000	1.078	1.134	1.565			
NESC Heavy	Clamp3	Clamp	David3:End	0.000	3.651	7.201	8.074			
NESC Heavy	Clamp4	Clamp	David4:End	0.000	3.651	7.201	8.074			
NESC Heavy	Clamp5	Clamp	David5:End	0.000	3.651	7.201	8.074			
NESC Heavy	Clamp6	Clamp	David6:End	0.000	3.651	7.201	8.074			
NESC Heavy	Clamp7	Clamp	David7:End	0.000	3.651	7.201	8.074			
NESC Heavy	Clamp8	Clamp	David8:End	0.000	3.651	7.201	8.074			
NESC Heavy	Clamp9	Clamp	10255:TopConn	0.000	6.545	8.457	10.694			
NESC Heavy	Clamp10	Clamp	10255:BotConn	0.000	-4.305	0.788	4.377			
NESC Heavy	Clamp11	Clamp	10255:WVG01	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp12	Clamp	10255:WVG02	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp13	Clamp	10255:WVG03	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp14	Clamp	10255:WVG04	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp15	Clamp	10255:WVG05	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp16	Clamp	10255:WVG06	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp17	Clamp	10255:WVG07	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp18	Clamp	10255:WVG08	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp19	Clamp	10255:WVG09	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp20	Clamp	10255:WVG10	0.000	0.084	1.150	1.153			
NESC Heavy	Clamp21	Clamp	10255:WVG11	0.000	0.084	1.150	1.153			

NESC Heavy	Clamp22	Clamp	10255:WVGDI2	0.000	0.084	1.150	1.153
NESC Heavy	Clamp23	Clamp	10255:WVGDI3	0.000	0.084	1.150	1.153
NESC Extreme	Clamp1	Clamp	David1:End	0.000	0.715	0.280	0.768
NESC Extreme	Clamp2	Clamp	David2:End	0.000	0.715	0.280	0.768
NESC Extreme	Clamp3	Clamp	David3:End	0.000	4.999	3.065	5.864
NESC Extreme	Clamp4	Clamp	David4:End	0.000	4.999	3.065	5.864
NESC Extreme	Clamp5	Clamp	David5:End	0.000	4.999	3.065	5.864
NESC Extreme	Clamp6	Clamp	David6:End	0.000	4.999	3.065	5.864
NESC Extreme	Clamp7	Clamp	David7:End	0.000	4.999	3.065	5.864
NESC Extreme	Clamp8	Clamp	David8:End	0.000	4.999	3.065	5.864
NESC Extreme	Clamp9	Clamp	10255:TopConn	0.000	19.914	3.483	20.216
NESC Extreme	Clamp10	Clamp	10255:BotConn	0.000	-13.385	0.189	13.386
NESC Extreme	Clamp11	Clamp	10255:WVGDI1	0.000	0.215	0.312	0.379
NESC Extreme	Clamp12	Clamp	10255:WVGDI2	0.000	0.215	0.312	0.379
NESC Extreme	Clamp13	Clamp	10255:WVGDI3	0.000	0.215	0.312	0.379
NESC Extreme	Clamp14	Clamp	10255:WVGDI4	0.000	0.215	0.312	0.379
NESC Extreme	Clamp15	Clamp	10255:WVGDI5	0.000	0.215	0.312	0.379
NESC Extreme	Clamp16	Clamp	10255:WVGDI6	0.000	0.215	0.312	0.379
NESC Extreme	Clamp17	Clamp	10255:WVGDI7	0.000	0.215	0.312	0.379
NESC Extreme	Clamp18	Clamp	10255:WVGDI8	0.000	0.215	0.312	0.379
NESC Extreme	Clamp19	Clamp	10255:WVGDI9	0.000	0.215	0.312	0.379
NESC Extreme	Clamp20	Clamp	10255:WVGDI10	0.000	0.215	0.312	0.379
NESC Extreme	Clamp21	Clamp	10255:WVGDI11	0.000	0.215	0.312	0.379
NESC Extreme	Clamp22	Clamp	10255:WVGDI12	0.000	0.215	0.312	0.379
NESC Extreme	Clamp23	Clamp	10255:WVGDI13	0.000	0.215	0.312	0.379

Overturning Moments For User Input Concentrated Loads:

Moments are static equivalents based on central axis of 0,0 (i.e. a single pole).

Load Case	Total	Total	Total	Transverse	Longitudinal
	Tran.	Long.	Vert.	Overturning	Overturning
	Load	Load	Load	Moment	Moment
	(kips)	(kips)	(kips)	(ft-k)	(ft-k)
NESC Heavy	27.394	0.000	69.669	3310.248	-0.000
NESC Extreme	40.748	0.000	26.678	4947.477	-0.000

*** Weight of structure (lbs):

Weight of Tubular Davit Arms: 3814.7
Weight of Steel Poles: 30952.3
Total: 34767.0

*** End of Report

Passive Pressure 2 =

$$P_{p2.top} := K_{p2} \cdot \gamma_{soil2} \cdot d_f = 1.5 \cdot \text{ksf}$$

$$P_{p2.bot} := K_{p2} \cdot \gamma_{soil2} \cdot D_f = 6 \cdot \text{ksf}$$

Active Pressure 2 =

$$P_{a2.top} := K_{a2} \cdot \gamma_{soil2} \cdot d_f = 0.167 \cdot \text{ksf}$$

$$P_{a2.bot} := K_{a2} \cdot \gamma_{soil2} \cdot D_f = 0.667 \cdot \text{ksf}$$

Area of Pressure 2 =

$$A_{p2} := (D_f - d_f) \cdot d_p = 120 \text{ft}^2$$

Forces 2 =

$$F_{p2A} := P_{p2.top} \cdot A_{p2} = 180 \cdot \text{kips}$$

$$F_{a2A} := P_{a2.top} \cdot A_{p2} = 20 \cdot \text{kips}$$

$$F_{p2B} := \frac{1}{2} \cdot (P_{p2.bot} - P_{p2.top}) \cdot A_{p2} = 270 \cdot \text{kips}$$

$$F_{a2B} := \frac{1}{2} \cdot (P_{a2.bot} - P_{a2.top}) \cdot A_{p2} = 30 \cdot \text{kips}$$

Ultimate Shear 2 =

$$S_{u2A} := F_{p2A} - F_{a2A} = 160 \cdot \text{kip}$$

$$S_{u2B} := F_{p2B} - F_{a2B} = 240 \cdot \text{kip}$$

Weight of Concrete Mat =

$$W_{Tmat} := \left(W_f^2 - \frac{d_p^2 \cdot \pi}{4} \right) \cdot T_f \cdot \gamma_{conc} = 315.44 \cdot \text{kip}$$

Weight of Concrete Caission =

$$W_{Tcaission} := \left(\frac{d_p^2 \cdot \pi}{4} \cdot L_p \right) \cdot \gamma_{conc} = 154.57 \cdot \text{kip}$$

Weight of Soil Above Mat =

$$W_{Ts} := \left[\left(W_f^2 - \frac{d_p^2 \cdot \pi}{4} \right) \cdot (d_f - T_f) \right] \cdot \gamma_{soil1} = 52.57 \cdot \text{kip}$$

Total Weight =

$$W_{tot} := W_{Tmat} + W_{Tcaission} + W_{Ts} + \text{Axial} = 588.581 \cdot \text{kips}$$

Overturning Moment =

$$M_{ot} := OM + \text{Shear} \cdot (d_f + L_{pag}) = 6971 \cdot \text{kip} \cdot \text{ft}$$

Resisting Moment =

$$M_r := (W_{tot}) \cdot \frac{W_f}{2} + S_{u1} \cdot T_f \cdot \frac{1}{3} + S_{u2A} \cdot \frac{(D_f - d_f)}{2} + S_{u2B} \cdot \frac{2(D_f - d_f)}{3} = 10748 \cdot \text{kip} \cdot \text{ft}$$

Factor of Safety Actual =

$$FS := \frac{M_r}{M_{ot}} = 1.54$$

Factor of Safety Required =

$$FS_{req} := 1.0$$

$$\text{Overturning_Check} := \text{if}(FS \geq FS_{req}, \text{"Okay"}, \text{"No Good"})$$

$$\text{Overturning_Check} = \text{"Okay"}$$

Bearing Pressure Check:

$$\text{Area of Mat} = A_{\text{mat}} := \frac{W_f^2}{4} - \frac{d_p^2 \cdot \pi}{4} = 525.735 \text{ ft}^2$$

$$\text{Section Modulus of Mat} = S_{\text{mat}} := \frac{W_f^3}{6} - \frac{d_p^3 \cdot \pi}{32} = 2254 \cdot \text{ft}^3$$

$$\text{Axial Force @ Base of Mat} = P_{\text{mat}} := W_{T_{\text{mat}}} + W_{T_s} = 368.014 \cdot \text{kips}$$

$$\text{Resisting Moment Capacity of Caissson} = M_{\text{cap}} := S_{u2A} \cdot \left[\frac{1}{2} \cdot (D_f - d_f) + d_f + L_{\text{pag}} \right] + S_{u2B} \cdot \left[\frac{2}{3} \cdot (D_f - d_f) + d_f + L_{\text{pag}} \right] = 5800 \cdot \text{kip-ft}$$

$$\text{Residual Moment @ Base of Mat} = M_{\text{mat}} := (OM - M_{\text{cap}}) + \text{Shear} \cdot (d_f + L_{\text{pag}}) - \left(S_{u1} \cdot T_f \cdot \frac{1}{3} \right) = 1085 \cdot \text{kip-ft}$$

$$\text{Maximum Pressure in Mat} = P_{\text{max}} := \frac{P_{\text{mat}}}{A_{\text{mat}}} + \frac{M_{\text{mat}}}{S_{\text{mat}}} = 1.182 \cdot \text{ksf}$$

$$\text{Max_Pressure_Check} := \text{if}(P_{\text{max}} < q_s, \text{"Okay"}, \text{"No Good"})$$

$$\text{Max_Pressure_Check} = \text{"Okay"}$$

$$\text{Minimum Pressure in Mat} = P_{\text{min}} := \frac{P_{\text{mat}}}{A_{\text{mat}}} - \frac{M_{\text{mat}}}{S_{\text{mat}}} = 0.218 \cdot \text{ksf}$$

$$\text{Min_Pressure_Check} := \text{if}((P_{\text{min}} \geq 0) \cdot (P_{\text{min}} < q_s), \text{"Okay"}, \text{"No Good"})$$

$$\text{Min_Pressure_Check} = \text{"Okay"}$$

$$\text{Distance to Resultant of Pressure Distribution} = X_p := \frac{\frac{P_{\text{max}}}{P_{\text{max}} - P_{\text{min}}} \cdot \frac{1}{3}}{\frac{W_f}{W_f}} = 9.814 \text{ ft}$$

$$\text{Distance to Kern} = X_k := \frac{W_f}{6} = 4 \text{ ft}$$

Since Resultant Force is Not in Kern, Area to which Pressure is Applied Must be Reduced.

$$\text{Eccentricity} = e := \frac{M_{\text{mat}}}{P_{\text{mat}}} = 2.949 \text{ ft}$$

$$\text{Adjusted Soil Pressure} = P_a := \frac{2 \cdot P_{\text{mat}}}{3 \cdot W_f \left(\frac{W_f}{2} - e \right)} = 1.129 \cdot \text{ksf}$$

$$q_{\text{adj}} := \text{if}(P_{\text{min}} < 0, P_a, P_{\text{max}}) = 1.182 \cdot \text{ksf}$$

$$\text{Pressure_Check} := \text{if}(q_{\text{adj}} < q_s, \text{"Okay"}, \text{"No Good"})$$

$$\text{Pressure_Check} = \text{"Okay"}$$

Product Description

This antenna is an ideal choice for dual band site upgrade for high traffic areas. It features 4 ports in 1900 MHz and 2 ports in 800 MHz.

Features/Benefits

- **Variable electrical downtilt** – provides enhanced precision in controlling intercell interference. The tilt is infield adjustable 0-10 deg.
- **High suppression of all upper sidelobes** (Typically < 18 dB)
- **Independent control of electrical downtilt** for 800 and PCS bands
- **Remote tilt** – AISG compatible
- **Low profile** for low visual impact
- **Quick and easy to adjust**
- **High front-to-back ratio**

Technical Specifications

Electrical Specifications

Frequency Range, MHz	806-869	1850-1995	1850-1995
Horizontal Beamwidth, deg	65	65	65
Vertical Beamwidth, deg	11.5	5.5	5.5
Electrical Downtilt, deg		0-10	
Gain, dBi (dBd)	15.5 (13.4)	18.0 (15.9)	18.0 (15.9)
1st Upper Sidelobe Suppression, dB, typ. @ T0° & T8°		>18	
Front-To-Back Ratio, dB, @ 180° ± 15°	>30	>27	>27
Polarization		Dual pol +/-45°	
Return Loss, dB		> 14	
Isolation between Ports, dB		>28	
3rd Order IMP @ 2 x 43 dBm, @ 2 min. duration		>110	
Cross Polar Discrimination (XPD) 0°, dB	>15	>20	>20
Cross Polar Discrimination (XPD) ± 60°, dB	>9.5	>11	>11
HBW Squint across same band ports, °		±5	
Impedance, Ohms		50	
Maximum Power Input, W		250	
Lightning Protection		Direct Ground	
Connector Type		(6) 7-16 DIN Female	

Mechanical Specifications

Dimensions - HxWxD, mm (in)	1829 x 302 x 178 (72.0 x 11.8 x 7)
Weight w/o Mtg Hardware, kg (lb)	25.8 (57)
Radome Material	ASA
Radome Color	Light Grey RAL7035
Mounting Hardware Material	Diecasted Aluminum and Galvanized Steel

Ordering Information

Mounting Hardware	APM40-2 Downtilt Kit
AISG System Cable	0.5 m, included
Mounting Pipe Diameter, mm (in)	60-120 (2.4-4.7)
Mounting Hardware Weight, kg (lb)	3.4 (7.5)