

G. Scott Shepherd, Sr. Property Specialist - SBA Communications

134 Flanders Rd., Suite 125, Westborough, MA 01581 508.251.0720 x 3807 - GShepherd@sbasite.com

February 9, 2022

Connecticut Siting Council Ten Franklin Square New Britain, CT 06051

RE: Tower Share Application

1021 Blue Hills Ave., Bloomfield, CT 06002

Latitude: 41.820119 Longitude: -72.696514

Dish Wireless Site# BOBDL00022A

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 1021 Blue Hills Ave., Bloomfield, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900/2100 MHz antennas and six (6) RRUs, at the 77-foot level of the existing 125-foot monopole tower, one (1) Fiber cables will also be installed. Dish Wireless LLC equipment cabinets will be placed within 7' x 5' lease area. Included are plans by B+T Group, dated January 7, 2022 Exhibit 10. Also included is a structural analysis prepared by TES, dated December 12, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment, attached as Exhibit 8. This facility was approved by the Town of Bloomfield zoning Board of Appeals December 1, 1997. Please see attached Exhibit 6.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to Noel Bishop, First Selectman for the Town of Westbrook, David Maiden-Building Official, as well as the tower owner (Crown Castle) and property owner (Toby Hill Farm LLC).

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.



- 1. The proposed modification will not result in an increase in the height of the existing structure. The top of the tower is 125-feet; Dish Wireless LLC proposed antennas will be located at a center line height of 77-feet.
- 2. The proposed modifications will not result in the increase of the site boundary as depicted on the attached site plan.
- 3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligent.
- 4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. As indicated in the attached power density calculations, the combined site operations will result in a total power density of 44.92% as evidenced by Exhibit 7.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully indicates that the shared use of this facility satisfies these criteria.

- A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit 8.
- B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this support tower in Bloomfield. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit 2, authorizing Dish Wireless LLC to file this application for shared use.
- C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 77-foot level of the existing 125-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit 7, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.
- D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.
- E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading.



Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing guyed tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Westbrook.

Sincerely,

Scott Shepherd
Site Development Specialist II
SBA COMMUNICATIONS CORPORATION
134 Flanders Rd., Suite 125
Westborough, MA 01581
508.251.0720 x3807 + T
508.366.2610 + F
508.868.6000 + C
GShepherd@sbasite.com

Attachments:

cc: Stanley D. Hawthorne, Town Manager / with attachments
Town of Bloomfield, 800 Bloomfield Ave, Bloomfield, CT 06002
William Lewis, Fire Marshall, Blue Hills Fire District / with attachments
1021 Blue Hills Ave., Bloomfield, CT 06002 (SBA address on file)
Jose Giner, Director, Planning & Zoning / with attachments
Town of Bloomfield, 800 Bloomfield Ave, Bloomfield, CT 06002



EXHIBIT LIST

Exhibit 1	Copy of Check	X
Exhibit 2	Letter of Intent to Allow Shared	X
	Use of the Existing SBA	
	Telecommunications Site	
Exhibit 3	Notification Receipts	x
Exhibit 4	Property Card	X
Exhibit 5	Property Map	X
Exhibit 6	Original Zoning Approval	Bloomfield Zoning Board of Appeals 12/1/97
Exhibit 7	EME Report	EBI Consulting 2/1/22
Exhibit 8	Structural Analysis	TES 12/14/21
Exhibit 9	Mount Analysis	B+T Group 12/21/21
Exhibit 10	Construction Drawings	B+T Group 1/7/22

EXHIBIT 1 Copy of check

EXHIBIT 2 Letter of Intent



February 9, 2022

Melanie A. Bachman Executive Director Connecticut Siting Council Ten Franklin Square New Britain, CT 06051

RE: Notice of Intent to Allow Shared Use of the Existing SBATelecommunications Site

Location: 1021 Blue Hills Ave, Bloomfield, CT

Dish Wireless Site No: BOBDL00022A

Site No: CT01725-A

Dear Ms. Bachman:

Please let the following serve as Evidence of Intent to allow Dish Wireless' shared use of the existing SBA telecommunications site at **1021 Blue Hills Ave**, **Bloomfield**, **CT**.

SBA Towers, LLC ("Owner") and Dish Wireless ("Tenant") are entering into a Site Lease Agreement. Tenant will be provided ground space within the existing site compound for its base station equipment and space at the height of 77' for antennas and associated equipment.

Thank you,


Rick Woods

Site Development Manager
SBA COMMUNICATIONS CORPORATION
134 Flanders Road, Suite 125
Westboro, MA 01581

508.251.0720 x3800 + T 508.366.2610 + F 508.614.0389 + C rwoods@sbasite.com

EXHIBIT 3

Fedex Labels



After printing this label:

- 1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
- 2. Fold the printed page along the horizontal line.
- 3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com.FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery,misdelivery,or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim.Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental,consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss.Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Page 1 of 2 **Detailed Tracking**



FedEx Tracking **Track Another Shipment** Help

775996123447

ADD NICKNAME





ON TIME

Scheduled delivery: Thursday, February 10, 2022 before 10:30 am



GET STATUS UPDATES

FROM SBA COMMUNICATIONS CORPORATION Sherri Knapik

> 134 Flanders Rd Suite 125 WESTBOROUGH, MA US 01581 508-614-0389

ACTUAL PICK UP

2/9/22 (?)

то Melanie A. Bachman Exec. Dir Connecticut Siting Council

> Ten Franklin Square NEW BRITAIN, CT US 06051 508-251-0720

MANAGE DELIVERY ✓

STANDARD TRANSIT

2/10/22 before 10:30 am ?

Travel History Shipment Facts **Travel History** Local Scan Time Wednesday, February 9, 2022 12:28 PM WESTBOROUGH, MA Picked up Tendered at FedEx Office 9:50 AM Shipment information sent to FedEx **Shipment Facts** TRACKING NUMBER SERVICE WEIGHT 775996123447 FedEx Priority Overnight 2 lbs / 0.91 kgs **TOTAL PIECES TOTAL SHIPMENT WEIGHT TERMS** 2 lbs / 0.91 kgs Shipper SHIPPER REFERENCE PACKAGING SPECIAL HANDLING SECTION 10-56-92009-6089 FedEx Pak Deliver Weekday

SHIPMENT-FACTS.COD-DETAIL

\$0.00



After printing this label:

- 1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
- 2. Fold the printed page along the horizontal line.
- 3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com.FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery,misdelivery,or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim.Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental,consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss.Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Page 1 of 2 **Detailed Tracking**



FedEx Tracking **Track Another Shipment** Help

> 775996159702 ADD NICKNAME

ON TIME

Scheduled delivery: Thursday, February 10, 2022 before 10:30 am



GET STATUS UPDATES

FROM SBA COMMUNICATIONS CORPORATION Sherri Knapik

> 134 Flanders Rd Suite 125 WESTBOROUGH, MA US 01581 508-614-0389

2/9/22 (?)

то Stanley D. Hawthorne Town of Bloomfield

Town Manager 800 Bloomfield Ave BLOOMFIELD, CT US 06002 508-251-0720

MANAGE DELIVERY ✓

2/10/22 before 10:30 am ?

Travel History Shipment Facts **Travel History** Local Scan Time Wednesday, February 9, 2022 12:28 PM WESTBOROUGH, MA Picked up Tendered at FedEx Office 9:52 AM Shipment information sent to FedEx **Shipment Facts** TRACKING NUMBER SERVICE WEIGHT 775996159702 FedEx Priority Overnight 0.5 lbs / 0.23 kgs **TOTAL PIECES TOTAL SHIPMENT WEIGHT TERMS** 0.5 lbs / 0.23 kgs Shipper SHIPPER REFERENCE PACKAGING SPECIAL HANDLING SECTION 10-56-92009-6089 FedEx Envelope Deliver Weekday **ACTUAL PICK UP** SHIPMENT-FACTS.COD-DETAIL STANDARD TRANSIT

\$0.00



After printing this label:

- 1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
- 2. Fold the printed page along the horizontal line.
- 3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com.FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery,misdelivery,or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim.Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental,consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss.Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Detailed Tracking Page 1 of 2



FedEx Tracking Track Another Shipment Help

775996181781

ADD NICKNAME



ON TIME

Scheduled delivery: Thursday, February 10, 2022 before 10:30 am



WESTBOROUGH, MA
GET STATUS UPDATES

FROM
SBA COMMUNICATIONS CORPORATION
Sherri Knapik

134 Flanders Rd Suite 125 WESTBOROUGH, MA US 01581 508-614-0389

2/9/22 (?)

то William Lewis Town of Bloomfield

Fire Marshall 1021 Blue Hills Ave BLOOMFIELD, CT US 06002 508-251-0720

MANAGE DELIVERY

2/10/22 before 10:30 am ?

Travel History Shipment Facts **Travel History** Local Scan Time Wednesday, February 9, 2022 12:28 PM WESTBOROUGH, MA Picked up Tendered at FedEx Office 9:54 AM Shipment information sent to FedEx **Shipment Facts** TRACKING NUMBER SERVICE WEIGHT 775996181781 FedEx Priority Overnight 0.5 lbs / 0.23 kgs **TOTAL PIECES TOTAL SHIPMENT WEIGHT TERMS** 0.5 lbs / 0.23 kgs Shipper SHIPPER REFERENCE PACKAGING SPECIAL HANDLING SECTION 10-56-92009-6089 FedEx Envelope Deliver Weekday **ACTUAL PICK UP** SHIPMENT-FACTS.COD-DETAIL STANDARD TRANSIT

\$0.00



After printing this label:

- 1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
- 2. Fold the printed page along the horizontal line.
- 3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com.FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery,misdelivery,or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim.Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental,consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss.Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Detailed Tracking Page 1 of 2



FedEx Tracking Track Another Shipment Help

775996204308
ADD NICKNAME



ON TIME

Scheduled delivery: Thursday, February 10, 2022 before 10:30 am



GET STATUS UPDATES

FROM
SBA COMMUNICATIONS CORPORATION
Sherri Knapik

134 Flanders Rd Suite 125 WESTBOROUGH, MA US 01581 508-614-0389

2/9/22 (?)

то Jose Giner Town of Bloomfield

Dir. Planning & Zoning 800 Bloomfield Ave BLOOMFIELD, CT US 06002 508-251-0720

MANAGE DELIVERY

2/10/22 before 10:30 am ?

Travel History Shipment Facts **Travel History** Local Scan Time Wednesday, February 9, 2022 12:28 PM WESTBOROUGH, MA Picked up Tendered at FedEx Office 9:55 AM Shipment information sent to FedEx **Shipment Facts** TRACKING NUMBER SERVICE WEIGHT 775996204308 FedEx Priority Overnight 0.5 lbs / 0.23 kgs **TOTAL PIECES TOTAL SHIPMENT WEIGHT TERMS** 0.5 lbs / 0.23 kgs Shipper SHIPPER REFERENCE PACKAGING SPECIAL HANDLING SECTION 10-56-92009-6089 FedEx Envelope Deliver Weekday **ACTUAL PICK UP** SHIPMENT-FACTS.COD-DETAIL STANDARD TRANSIT

\$0.00

EXHIBIT 4 Property Card

Map Block Lot

39-29

Building #

PID

7809

Account

Property Information

Property Location	1021 BLUE HILLS AVE		
Owner	BLUE HILLS FIRE DIST		
Co-Owner	BLUE HILLS AVE COR		
Mailing Address	ROCKWELL AVENUE		
Walling Address	BLOOMFIELD CT 06002		
Land Use	922 Mun Bldg Com		
Land Class	Е		
Zoning Code	GWB		
Census Tract	4712		

Site Index	С
Acreage	1.23
Utilities	
Lot Setting/Desc	
Fire District	В
Book / Page	0091/0376


Primary Construction Details

Year Built	1962	
Building Desc.	Commercial	
Building Style	Fire Station	
Building Grade	С	
Stories	1	
Occupancy	1.00	
Exterior Walls	Brick Veneer	
Exterior Walls 2	NA	
Roof Style	Gable	
Roof Cover	Arch Shingles	
Interior Walls	Drywall	
Interior Walls 2	Minimum	
Interior Floors 1	Vinyl/Asphalt	
Interior Floors 2	Concrete	

Heating Fuel	Gas
Heating Type	Hot Water
AC Type	42
Bedrooms	0
Full Bathrooms	0
Half Bathrooms	0
Extra Fixtures	0
Total Rooms	0
Bath Style	NA
Kitchen Style	NA
Bsmt Fin Area	0
Rec Rm Area	0
Bsmt Gar	0
Fireplaces	0

Photo





(*Industrial / Commercial Details)

,	
Building Use	Commercial
Building Condition	G
Sprinkler %	100
Heat / AC	HEAT/AC SPLIT
Frame Type	Masonry
Baths / Plumbing	Average
Ceiling / Wall	Sus Ceil & Wal
Rooms / Prtns	Average
Wall Height	12.00
First Floor Use	
Foundation	NA

Town of Bloomfield, CT

Property Listing Report

BLUE HILLS FIRE DIST

Map Block Lot

39-29

Building #

PID

7809

Account


Item	Appraise	ed Assessed	Subarea Type	Gross Area (sq ft)	Living Area (sq ft
Buildings	617000	431900	Office Area	3898	3898
Extras	0	0	First Floor	5346	5346
Improvements	0		Canopy	75	0
Outbuildings	85700	59990	Basement	868	0
Land	377100	263970			
	1079800	755860			
Outbuilding ar	nd Extra Feat	ures			
Type	I	Description			
Shed 288 S.F.					
Cell Shed	260 S.F.				
Cell Shed	2	00 S.F.			
Cell Shed	2	00 S.F.			
Paving	2	3120 S.F.			
			Total Area	10187	9244
Sales History					l
Owner of Record			Book/ Page Sale	e Date Sale Pri	

0091/0376

1900-01-01

0

EXHIBIT 5 Property Map





1 inch = 100 feet

This map is for informational purposes only. All information is subject to verification by any user. The Town of Bloomfield and its mapping contractors assume no legal responsibility for the information contained herein.

Parcels labeled by Unique ID

Google Maps 1021 Blue Hills Ave



Imagery ©2021 Maxar Technologies, U.S. Geological Survey, USDA Farm Service Agency, Map data ©2021

EXHIBIT 6 Zoning Approval

ZONING BOARD OF APPEALS

TOWN OF BLOOMFIELD

LOCATION: 1021 Blue 1/1/1/5 frence
Please type or print
OWNER OF RECORD: Blue Hills Fire District.
The foregoing application for / Variance; / Special Exception pursuant to Section w.5.46 m. of the Bloomfield Zoning Regulations, pertains to premises bounded and described as follows: (Type or attach written legal boundary description)
(See Attached Description)
Notary: MARK LE CAULT MY COMMISSION ENDIRES: 11/30/2001
Date Date Signature of Owner of Record
PLEASE NOTE REQUIREMENTS BELOW FOR RECORDING APPROVAL ON LAND RECORDS
To be completed by Zoning Board of Appeals following approval:
I hereby certify that the Zoning Board of Appeals, at a meeting held on <u>December 1, 1997</u> , approved <u>XX</u> / Variance and <u>XXX</u> / Special Exception of <u>Cordless Data Transfer, Inc.for a radio tower in the gateway zone</u>
to be located 12 feet from the property line, 1021 Blue Hills Ave., (Fire Dept.)
at the above premises, pursuant to Section $\frac{IV.S.4.b}{III-p}$ of the Bloomfield Zoning Regulations, subject to the following conditions (if any):
An 8-foot chain link fence shall be placed around the tower
(1, 1, 2, 3, 3, 3, 3, 3, 3, 3, 3, 3, 3, 3, 3, 3,

Secretary - ZBA

NOTE: PURSUANT TO SECTION 8-3d OF THE CONN. GENERAL STATUTES, THIS
VARIANCE/SPECIAL EXCEPTION WILL NOT BECOME EFFECTIVE UNTIL IT HAS
BEEN RECORDED ON THE LAND RECORDS OF THE TOWN OF BLOOMFIELD. IT IS
THE RESPONSIBILITY OF THE OWNER TO RECORD THIS FORM AND PAY THE
RECORDING FEE. (\$10.00 FOR THE FIRST PAGE, \$5.00 EACH ADDITIONAL PAGE)

Woodrow Dixon

*NO BUILDING PERMITS REQUIRED IN CONNECTION WITH THE ABOVE VARIANCE OR SPECIAL EXCEPTION MAY BE ISSUED UNTIL THIS APPROVAL HAS BEEN RECORDED.

EXHIBIT 7

EME Report



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOBDL00022B

1021 Blue Hills Avenue Bloomfield, Connecticut 06002

February I, 2022

EBI Project Number: 6222000572

Site Compliance Summary		
Compliance Status:	COMPLIANT	
Site total MPE% of FCC general population allowable limit:	44.92%	



February I, 2022

Dish Wireless

Emissions Analysis for Site: BOBDL00022B

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at 1021 Blue Hills Avenue in Bloomfield, Connecticut for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm²). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately 400 μ W/cm² and 467 μ W/cm², respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.



Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed Dish Wireless Wireless antenna facility located at 1021 Blue Hills Avenue in Bloomfield, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) 4 n66 channels (AWS Band 2190 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative



estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector A, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector B, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline of the proposed antennas is 77 feet above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 9) All calculations were done with respect to uncontrolled / general population threshold limits.



Dish Wireless Site Inventory and Power Data

Sector:	Α	Sector:	В	Sector:	С
Antenna #:	I	Antenna #:	I	Antenna #:	I
Make / Model:	JMA MX08FRO665- 21	Make / Model:	JMA MX08FRO665- 21	Make / Model:	JMA MX08FRO665- 21
Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz
Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd
Height (AGL):	77 feet	Height (AGL):	77 feet	Height (AGL):	77 feet
Channel Count:	12	Channel Count:	12	Channel Count:	12
Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts
ERP (W):	5,236.31	ERP (W):	5,236.31	ERP (W):	5,236.31
Antenna A1 MPE %:	4.69%	Antenna B1 MPE %:	4.69%	Antenna C1 MPE %:	4.69%

environmental | engineering | due diligence

Site Composite MPE %			
Carrier	MPE %		
Dish Wireless (Max at Sector A):	4.69%		
AT&T	8.35%		
Verizon	7.16%		
T-Mobile	17.27%		
Metro PCS	2.55%		
Clearwire	0.15%		
Sprint	2.32%		
Nextel	0.44%		
XM Sat Radio	0.16%		
Page Net	0.08%		
Blue Hills FD	1.75%		
Site Total MPE % :	44.92%		

Dish Wireless MPE % Per Sector				
Dish Wireless Sector A Total:	4.69%			
Dish Wireless Sector B Total:	4.69%			
Dish Wireless Sector C Total:	4.69%			
Site Total MPE % :	44.92%			

Dish Wireless Maximum MPE Power Values (Sector A)									
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (µW/cm²)	Frequency (MHz)	Allowable MPE (μW/cm²)	Calculated % MPE		
Dish Wireless 600 MHz n71	4	223.68	77.0	6.38	600 MHz n71	400	1.60%		
Dish Wireless 1900 MHz n70	4	542.70	77.0	15.48	1900 MHz n70	1000	1.55%		
Dish Wireless 2190 MHz n66	4	542.70	77.0	15.48	2190 MHz n66	1000	1.55%		
						Total:	4.69%		

[•] NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)		
Sector A:	4.69%		
Sector B:	4.69%		
Sector C:	4.69%		
Dish Wireless Maximum MPE % (Sector A):	4.69%		
Site Total:	44.92%		
Site Compliance Status:	COMPLIANT		

The anticipated composite MPE value for this site assuming all carriers present is **44.92**% of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

EXHIBIT 8 Structural Analysis



Phone (972) 483-0607, Fax (972) 975-9615 1320 Greenway Drive, Suite 600, Irving, Texas 75038

Structural Analysis Report

Existing 125 ft Nudd Corporation Self Supporting Tower

Customer Name: SBA Communications Corp

Customer Site Number: CT01725-A

Customer Site Name: Bloomfield

Carrier Name: Dish Wireless (App#: 176995, V1)

Carrier Site ID / Name: BOBDL00022B / 0

Site Location: 1021 Blue Hills Avenue

Bloomfield, Connecticut

Hartford County

Latitude: 41.820119

Longitude: -72.696514

Analysis Result:

Max Structural Usage: 97.6% [Pass]

Max Foundation Usage: 43.0% [Pass]

Additional Usage Caused by New Mount/Mount Modification: N/A

Report Prepared By: Sital Shrestha

Introduction

The purpose of this report is to summarize the analysis results on the 125 ft Nudd Corporation Self Supporting Tower to support the proposed antennas and transmission lines in addition to those currently installed. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

Sources of Information

Tower Drawings	Fred A. Nudd Corporation, Project# 97-5566A-1 dated March 11, 1998			
Foundation Drawing	Fred A. Nudd Corporation, drawing #97-5566-2 dated 12/18/1997			
Geotechnical Report	otechnical Report FDH Engineering Project #1206690EG1 dated 08/10/2012			
Modification Drawings	N/A			

Analysis Criteria

The rigorous analysis was performed in accordance with the requirements and stipulations of the TIA-222-G-2. In accordance with this standard, the structure was analyzed using **TESTowers**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

Wind Speed Used in the Analysis: Ultimate Design Wind Speed V_{ult} =125.0 mph (3-Sec. Gust)/

Nominal Design Wind Speed V_{asd} = 97.0 mph (3-Sec. Gust)

Wind Speed with Ice: 50 mph (3-Sec. Gust) with 1" radial ice concurrent

Operational Wind Speed: 60 mph + 0" Radial ice

Standard/Codes: TIA-222-G-2 / 2015 IBC / 2018 Connecticut State Building

Code

Exposure Category: B
Structure Class: II
Topographic Category: 1
Crest Height: 0 ft

Seismic Parameters: $S_S = 0.18, S_1 = 0.064$

This structural analysis is based upon the tower being classified as a Structure Class II; however, if a different classification is required subsequent to the date hereof, the tower classification will be changed to meet such requirement and a new structural analysis will be run.

Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

1 1 1 1 1 1 1 1 1 1	Items	Elevatio n (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
3	1		1	Cellwave PD455		(1) 7/8"	Blue Hills
133.0	2			Cellwave AS MONR 31		(1) 1/2"	Fire
133.0 1 Cellwave PD155 125.0 2 Cellwave PD1655 3 Ericsson AlR6449 B41 - Panel 3 RFS APXVAARA24 43-U-NA20 - Panel 3 AIR32 KRD901146-1_866A (Octa) - Panel 3 AIR32 KRD901146-1_866A (Octa) - Panel 3 Commscope SDX1926Q-43 12 3 Ericsson Radio 4449 B71+B85 RRU 13 3 Ericsson Radio 4449 B71+B85 RRU 13 3 Commscope - NHH-65B-R2B - Panel 15 3 Commscope - NHH-65B-R2B - Panel 15 3 Samsung - MT6407-77A - Panel 16 3 Samsung - RF4440d-13A RRU 19 3 Samsung - RF4440d-13A RRU 10 3 Samsung - RF4440d-13A RRU 10 3 Samsung - RF4440d-13A RRU 10 3 Samsung - RF4430d-25A RRU 1 RF5 - DB-C1-12C-24AB-0Z - OVP 2 Cal HPA-65R-BUU-HB - Panel 2 Cal HPA-65R-BUU-HB - Panel 2 Cal HPA-65R-BUH-HB - Panel 3 Ericsson RRUS 8448 BZ B66A 3 Ericsson RRUS 8449, BS, B12 3 Sector Frame w/ (3) 12.5' pipes 3 Firicsson RRUS 4449, BS, B12 3 Sector Frame w/ (3) 12.5' pipes 3 Commscope NHH-S-66B-RUBEAK - Panel 4 Cal HPA-65R-BUH-HB - Panel 5 Cal HPA-65R-BUH-HB - Panel 6 Powerwave LGP21901 Diplever 1 Cal DMP65R-BUBEAK - Panel 2 Cal HPA-65R-BUH-HB - Panel 3 Sector Frame w/ (3) 12.5' pipes 3 Ericsson RRUS 8448 BZ B66A 3 Ericsson RRUS 8449 BS, B12 3 Ericsson RRUS 84415 B30 1 Raycap DC6-48-60-18-8F - OVP 1 Raycap DC6-48-60-18-8F - OVP 1 Raycap DC6-48-60-18-8F - OVP 3 Raycap DC6-48-60-18-8F - OVP 4 Raycap DC6-48-60-18-8F - OVP 5 Raycap DC6-48-60-18-8F - OVP 4 Raycap DC6-48-60-18-8F - OVP 5 Raycap DC6-48-60-18-8F - OVP 5 Raycap DC6-48-6	3			Cellwave PD455			Bloomfield
Telephone Tele	4	133.0	1	Cellwave AS MONR 31		(4) //8"	Police Dept.
1	5	125.0	2	Cellwave PD455		(1) 1 1/4"	Blue Hills
Samuration Sam	6	125.0		Cellwave PD165S	1	(1) 1/2"	Fire
3	7	3		Ericsson AIR6449 B41 - Panel			
9	8		3	RFS APXVAARR24_43-U-NA20 - Panel	Reinforcement Kit	(9) 1 5/8"	
11	9		3	AIR32 KRD901146-1_B66A (Octa) - Panel		, ,	
12 3	10	125.0	3	Ericsson KRY 112 144/2		Hybrid (2) 1 5/8"	T-Mobile
13	11		3	Commscope SDX1926Q-43			
14	12		3	Ericsson Radio 4449 B71+B85 RRU			
15	13	13		Ericsson 4415 B25			
10.0 3 Samsung - MT6407-77A - Panel 3 Samsung - MT6407-77A - Panel 3 Antel - BXA-70063-4CF - Panel 3 Samsung - RF4440d-13A RRU 3 Samsung - RF4440d-13A RRU 20 3 Samsung - RT4401-48A RRU 21 Crossover plate, (12) VZWSMART-MSK1 Crossover plate, (12) VZWSMART-MSK7 Crossover & (3) 12.5' pipes] VZWSMART-MSK7 VZWSMART-MSK1 V	14		3	Commscope - NHH-65B-R2B - Panel			
10.0 3	15		3	Commscope - NHHSS-65B-R2B - Panel	, ,		
110.0 3 Samsung - RF4440d-13A RRU Crossover plate, (12) VZWSMART - MSK1 (2) 1/2" (18) 1 5/8" Verizon	16		3	Samsung - MT6407-77A - Panel	-		
18	17		3	Antel - BXA-70063-4CF - Panel	= : :	(2) 1/2"	Verizon
19	18	110.0	3	Samsung - RF4440d-13A RRU			
3 Samsung - RT4401-48A RRU 1 RFS - DB-C1-12C-24AB-OZ - OVP 2 Andrew GPS 2 Andrew GPS 2 Cci HPA-65R-BUU-H8 - Panel 25 1 Cci DMP65R-BU8EA-K - Panel 27 28 29 30 98.0 3 Ericsson RRUS 4419, B5, B12 3 Ericsson RRUS 4449, B5, B12 3 Raycap DC6-48-60-18-8C - OVP 3 Raycap DC6-48-60-18-8C - OVP 3 Samsung - RT4401-48A RRU 1 Raycap DC6-48-60-18-8C - OVP 3 Crossover & (3) 12.5' pipes] Crossover & (3) 12.5' pipes] Crossover & (3) 12.5' pipes] (4) 3/4" DC (12) 7/8" (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber (1) 3" Conduit (1) 4" Condu	19		3	Samsung - RF4439d-25A RRU	VZWSMART-MSK7 Crossover & (3) 12.5'		
21 1 RFS - DB-C1-12C-24AB-0Z - OVP pipes] 22 Andrew GPS 23 100.0 3 Ericsson Air 6449 N77D - Panel 24 2 Cci HPA-65R-BUU-H8 - Panel 25 1 Cci DMP65R-BUBEA-K - Panel 26 2 Cci DMP65R-BUBEA-K - Panel 27 6 Powerwave LGP21401 TMA 29 6 Powerwave LGP21901 Diplexer 30 12 Powerwave 7020.00 RET 3 Ericsson RRUS 8843 B2 B66A 3 Ericsson RRUS 4449, B5, B12 33 Ericsson RRUS 4449, B5, B12 33 Ericsson RRUS 44415 B30 34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-18-8C - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T	20		3	Samsung - RT4401-48A RRU			
22	21		1	RFS - DB-C1-12C-24AB-0Z - OVP			
24 2 Cci HPA-65R-BUU-H8 - Panel 25 1 Cci HPA-65R-BUU-H6 - Panel 26 2 Cci DMP65R-BU8EA-K - Panel 27 1 Cci DMP65R-BU6EA-K - Panel 28 6 Powerwave LGP21401 TMA 29 6 Powerwave LGP21901 Diplexer 31 12 Powerwave 7020.00 RET 31 3 Ericsson RRUS 8843 B2 B66A 32 3 Ericsson RRUS 4449, B5, B12 33 3 Ericsson RRUS 4415 B30 34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T (4) 3/4" DC (12) 7/8" (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) AT&T (4) 3/4" DC (12) 7/8" (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) AT&T (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) (2) 3/4" DC & (1) 1/2" Fiber) (3) Site Pro SFS-H-L	22		2	Andrew GPS	bibeol		
1	23	100.0	3	Ericsson Air 6449 N77D - Panel			
26 2 Cci DMP65R-BU8EA-K - Panel 27 1 Cci DMP65R-BU6EA-K - Panel 28 6 Powerwave LGP21401 TMA 29 6 Powerwave LGP21901 Diplexer 30 12 Powerwave 7020.00 RET 31 3 Ericsson RRUS 8843 B2 B66A 32 3 Ericsson RRUS 4449, B5, B12 33 3 Ericsson RRUS 4445 B30 34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T (3) Sector Frame w/ (3) Site Pro SFS-H-L (4) 3/4" DC (12) 7/8" (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) (1) 2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) (2) 3/4" DC & (1) 1/2" Fiber)	24		2	Cci HPA-65R-BUU-H8 - Panel			
27 1 Cci DMP65R-BU6EA-K - Panel 28 6 Powerwave LGP21401 TMA 29 6 Powerwave LGP21901 Diplexer 30 12 Powerwave 7020.00 RET 31 3 Ericsson RRUS 8843 B2 B66A 32 3 Ericsson RRUS 4449, B5, B12 33 Ericsson RRUS 4449, B5, B12 34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-0-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T (3) Sector Frame w/ (3) Site Pro SFR-K-L (3) Site Pro SFS-H-L (4) 3/4" DC (12) 7/8" (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) 1/2" Fiber)	25		1	Cci HPA-65R-BUU-H6 - Panel			
28 29 30 98.0 31 12 Powerwave LGP21901 Diplexer 31 3 Ericsson RRUS 8843 B2 B66A 32 3 Ericsson RRUS 4449, B5, B12 33 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T (3) Sector Frame w/ (3) Site Pro SFR-K-L (3) Site Pro SFS-H-L (4) 3/4" DC (12) 7/8" (1) 1/2" Fiber (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) 1/2" Fiber)	26		2	Cci DMP65R-BU8EA-K - Panel			
29 30 98.0 98.0 6	27		1	Cci DMP65R-BU6EA-K - Panel		(4) 5 (4) 5 5	
12 Powerwave 7020.00 RET (3) Sector Frame w/ (3) Site Pro SFR-K-L (1) 3"Conduit (Housing (2) 3) Sector Frame w/ (3) Site Pro SFS-H-L (1) 3"Conduit (Housing (2) 3) Site Pro SFS-H-L (1) 3"Conduit (1) 3"Conduit (1) 3"Conduit (1) 3"Conduit (1) 3"Conduit (1)	28		6	Powerwave LGP21401 TMA		, , .	
30 98.0 12 Powerwave 7020.00 RE1 (3) Site Pro SFR-K-L (1) 3"Conduit (Housing (2) 3/4" DC & (1) 1/2" Fiber) 31	29	29	6	Powerwave LGP21901 Diplexer	(3) Sector Frame w/	, , .	
31 3 Ericsson RRUS 8843 B2 B66A (3) Site Pro SFS-H-L (Housing (2) 3/4" DC & (1) 1/2" Fiber) 32 3 Ericsson RRUS 4449, B5, B12 33 Ericsson RRUS 4415 B30 34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-0-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 – BIAS-T	30	30 98.0 12 31 3 32 3 33 3 34 1		Powerwave 7020.00 RET	(3) Site Pro SFR-K-L	(1) 3"Conduit (Housing (2) 3/4" DC & (1)	AT&T
32 3 Ericsson RRUS 4449, B5, B12 33 3 Ericsson RRUS 44415 B30 34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-0-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T	31			Ericsson RRUS 8843 B2 B66A			
33 3 Ericsson RRUS 4415 B30 1/2" Fiber) 34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-0-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T	32			Ericsson RRUS 4449, B5, B12			
34 1 Raycap DC6-48-60-18-8F - OVP 35 1 Raycap DC6-48-60-0-18-8C-EV - OVP 36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 - BIAS-T	33			Ericsson RRUS 4415 B30			
36 1 Raycap DC6-48-60-18-8C - OVP 37 3 Kathrein 782 10253 – BIAS-T	34			Raycap DC6-48-60-18-8F - OVP			
37 3 Kathrein 782 10253 – BIAS-T	35			Raycap DC6-48-60-0-18-8C-EV - OVP	1		
	36		1 Raycap DC6-48-60-18-8C - OVP				
38 96.0 3 Ericsson Air 6419 N77G - Panel	37	3		Kathrein 782 10253 – BIAS-T			
	38	96.0	3	Ericsson Air 6419 N77G - Panel			

Items	Elevatio n (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmissio n Lines	Owner
39		3	Alcatel Lucent 1900MHz RRH			
40		3	Alcatel Lucent 800MHZ RRH			
41	87.0	3	Alcatel Lucent TD-RRH8x20-25	(3) Sector Frame	(1) 0.7"	Cariat
42	87.0	4	RFS ACU-A20-N	(3) Sector Frame	(3) 1 1/4"	Sprint
43		3	RFS APXVSPP18-C-A20 - Panel			
44	3		RFS APXVTM14-C-120 - Panel			
45	65.0	1	Nokia CS72188.01 LMU	(1) Standoff Mount	(1) ½"	AT&T

Proposed Carrier's Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier's final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner	
46		3	JMA Wireless MX08FRO665-21-Panel				
47	77.0	3	Fujitsu TA08025-B605-RRH	Commscope	(1) 1.411" Hybrid	Dish	
48	77.0		Fujitsu TA08025-B604-RRH	MTC3975083	(1) 1.411 Hybrid	Wireless	
49		1	Raycap RDIDC-9181-PF-48-OVP				

See the attached coax layout for the line placement considered in the analysis.

Analysis Results

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

Tower Component	Legs	Diagonals	Horizontals
Max. Usage:	97.6%	90.1%	41.1%
Pass/Fail	Pass	Pass	Pass

Foundations

	Compression (Kips)	Uplift (Kips)	Shear (Kips)
Analysis Reactions	309.0	276.7	26.2

The foundation has been investigated using the supplied documents and soils report and was found adequate. Therefore, no modification to the foundation will be required.

Operational Condition (Rigidity):

Operational characteristics of the tower are found to be within the limits prescribed by TIA-222 for the installed antennas. The maximum twist/sway at the elevation of the proposed equipment is 0.2655 degrees under the operational wind speed as specified in the Analysis Criteria.

Conclusions

Based on the analysis results, the existing structure and its foundation were found to be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the TIA-222 Standard under the design basic wind speed as specified in the Analysis Criteria.

Standard Conditions

- 1. This analysis was performed based on the information supplied to (TES) Tower Engineering Solutions, LLC. Verification of the information provided was not included in the Scope of Work for TES. The accuracy of the analysis is dependent on the accuracy of the information provided.
- 2. The structural analysis was performance based upon the evidence available at the time of this report. All information provided by the client is considered to be accurate.
- 3. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of TES. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed and/or ice loads are different from the minimum values recommended by the ANSI/TIA-222 standard or other codes, TES should be notified in writing and the applicable minimum values provided by the client.
- 4. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. TES has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, TES should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
- 5. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
- 6. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

Structure: CT01725-A-SBA

Site Name: Bloomfield Code: EIA/TIA-222-G

Type: Self Support Base Shape: Triangle Basic WS: 97.00

Height: 125.00 (ft) Base Width: 12.50 Basic Ice WS: 50.00

Base Elev: 0.00 (ft) **Top Width:** 3.50 **Operational WS:** 60.00 Page: 1



12/14/2021


			S	Section Properties			
Sect	Leg N	/leml	bers	Diagonal Members	Horizontal Members		
1	PST 8" DIA F			SAE 3.5X3.5X0.25			
2	PST 6" DIA F			SAE 3X3X0.25			
3	PST 6" DIA I			SAE 2.5X2.5X0.1875			
4	PST 5" DIA I			SAE 2.5X2.5X0.1875			
5	PST 3-1/2" D		PF	SAE 2X2X0.1875			
6	PST 2-1/2" D			SAE 1.5X1.5X0.1875			
7	PST 2-1/2" D			SOL 5/8" SOLID	SAE 1.5X1.5X0.1875		
			Disc	crete Appurtenances	<u> </u>	120.	.00
Attac	ch Forc	:e	Disc	rete Appultenance.	•		
Elev			Qty	Description			
125.			3	APXVAARR24_43-U-NA20		\$6	
125.	.00 125.	00	3	AIR32 KRD901146-1_B66A			
125.				KRY 112 144/1		100	
125.				Radio 4449 B71+B85 RRU		100.	00
125.			1	Lightning Rod			
125.	.00 125.	00	1	Beacon			
125.	.00 125.0	00	1	PD165S		\$5	
125.	.00 135.	00	1	Cellwave AS MONR 31		2.0	
125.			3	AIR6449 B41			
125.	.00 125.	00	3	SDX1926Q-43		80.0	nn
125.	.00 125.	00	3	4415 B25		00.0	
125.	.00 135.	00	3	PD455			
125.	.00 135.	00	3	PD455		1.2	
125.	.00 125.	00	1	Platform w/ HR		\$4	
125.	.00 125.	00	1	(3) HR w/ V-Brace Kits			
125.	.00 125.	00	1	PRK-FMA			
125.	.00 133.	00	1	Cellwave AS MONR 31		60.0	00
110.	.00 110.	.00	2	GPS			
110.	.00 110.	.00	3	NHH-65B-R2B			
110.	.00 110.	.00	3	NHHSS-65B-R2B		\$3	
110.	.00 110.	.00	3	MT6407-77A			
110.	.00 110.	.00	3	BXA-70063-4CF			
110.	.00 110.	.00	3	RF4440d-13A		40.0	00
110.	.00 110.	00	3	RF4439d-25A		40.0	00
110.	.00 110.	.00	1	DB-C1-12C-24AB-0Z			
110.	.00 110.	00	1	(3) 12.5' - 2.5" Horizontal Pi		0.0	
110.	.00 110.	.00	1	(3) SFS-H-L (V-Braces)		\$2	
110.	.00 110.	00	3	RT4401-48A			
110.	.00 110.	.00	3	Sector Frame			
100.	.00 100.0	00	3	Air 6449 N77D		20.0	00
98.	.00 98.	00	2	DMP65R-BU8EA-K			
98.		00	1	(3) SFS-H-L			
98.		00	3	Sector Frame		\$1	
98.				(3) SFR-K-L		31	
98.				HPA-65R-BUU-H8			
98.				HPA-65R-BUU-H6			
98.				LGP-21401			
98.				LGP-21903 Diplexer			
98.				7020.00 RET		and the same	
98.				8843 B2 B66A		and the same of th	
98.				4449 B5/B12		Z	
98.				4415 B30			

Structure: CT01725-A-SBA

Site Name: Bloomfield Code: EIA/TIA-222-G

Type:Self SupportBase Shape:TriangleBasic WS:97.00Height:125.00 (ft)Base Width:12.50Basic Ice WS:50.00

Base Elev: 0.00 (ft) Top Width: 3.50 Operational WS: 60.00 Page: 2



98.00	98.00	1	DC6-48-60-18-8F
98.00	98.00	1	DC6-48-60-0-18-8C-EV
98.00	98.00	1	DC6-48-60-18-8C
98.00	98.00	3	782 10253
98.00	98.00	1	(3) Stiff Arm Kit
98.00	98.00	1	DMP65R-BU6EA-K
96.00	96.00	3	Air 6419 N77G
87.00	87.00	3	Sector Frame
87.00	87.00	3	APXVTM14-C-120
87.00	87.00	3	800MHz Filter
87.00	87.00	3	1900MHz RRH
87.00	87.00	3	800MHZ RRH
87.00	87.00	3	TD-RRH8x20-25
87.00	87.00	4	ACU-A20-N
87.00	87.00	3	APXVSPP18-C-A20
77.00	77.00	3	MX08FRO665-21
77.00	77.00	3	TA08025-B604
77.00	77.00	3	TA08025-B605
77.00	77.00	1	RDIDC-9181-OF-48
77.00	77.00	3	MTC3975083
65.00	65.00	1	CS72188.01 LMU
65.00	65.00	1	Standoff Mount

	Linear Appurtenances													
Elev	Elev													
From (ft)	To (ft)	Qty	Description											
0.00	125.00	1	1 1/4" Coax											
0.00	125.00	9	1 5/8" Coax											
0.00	125.00	2	1 5/8" Hybrid											
0.00	125.00	2	1-1/4" Hybrid											
0.00	125.00	2	1/2" Coax											
0.00	125.00	1	7/8" Coax											
0.00	125.00	4	7/8" Coax											
0.00	125.00	1	Climbing Ladder											
0.00	125.00	1	W/G Ladder											
0.00	125.00	1	W/G Ladder											
0.00	110.00	18	1 5/8" Coax											
0.00	110.00	1	1 5/8" Fiber											
0.00	110.00	2	1/2" Coax											
0.00	110.00	1	W/G Ladder											
0.00	98.00	1	1/2" Fiber											
0.00	98.00	1	3" Conduit											
0.00	98.00	4	3/4" DC											
0.00	98.00	12	7/8" Coax											
0.00	98.00	1	W/G Ladder											
0.00	87.00	4	1 1/4" Coax											
0.00	87.00	1	W/G Ladder											
0.00	77.00	1	1.411" Hybrid											
0.00	77.00	1	W/G Ladder											
0.00	65.00	1	1/2" Coax											

Base Reactions Overturning

 Max Uplift:
 -276.67 (kips
 Moment:
 3189.52 (ft-kips)

 Max Down:
 309.05 (kips
 Total Down:
 43.24 (kips)

 Max Shear:
 26.16 (kips
 Total Shear:
 40.68 (kips)

Leg


Structure: CT01725-A-SBA

Site Name: Bloomfield Code: EIA/TIA-222-G 12/14/2021 97.00

Self Support Base Shape: Triangle Basic WS: Type: 50.00 **Base Width:** 12.50 **Basic Ice WS:** Height: 125.00 (ft)

Top Width: 3.50 **Operational WS:** 60.00 Page: 3 **Base Elev:** 0.00 (ft)






Structure: CT01725-A-SBA - Coax Line Placement

Type: Self Support 12/14/2021

Site Name: Bloomfield Height: 125.00 (ft) 4/2021 (((H))) ES

Page: 4



Loading Summary

Structure: CT01725-A-SBA **Code:** EIA/TIA-222-G 12/14/2021

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II Page: 5



Discrete Appurtenances Properties

	• •	-		lo Ice	lo	e						
Attach Elev			Weight	CaAa		CaAa	Len	Width	Depth		Orientation	
(ft)	Description ADVIVABBLE 40 HANGE	Qty	(lb)	(sf)	(lb)	(sf)	(in)	(in)	(in)	Ka	Factor	(ft)
	APXVAARR24_43-U-NA20	3	128.00	20.240	695.54		95.900	24.000	7.800	0.75	0.70	0.000
	AIR32 KRD901146-1_B66A	3	132.20	6.510	385.26	8.005	56.600	12.900	8.700	0.75	0.87	0.000
	KRY 112 144/1	3	11.00	0.410	25.09	1.031	6.900	6.100	2.700	0.75	0.67	0.000
	Radio 4449 B71+B85 RRU	3	70.00	1.650	166.38	2.376	15.000	13.200	9.300	0.75	0.67	0.000
	Lightning Rod	1	5.00	0.500	32.36	2.780	72.000	1.000	1.000	1.00	1.00	0.000
	Beacon	1	36.00	2.720	210.03	3.961	28.000	17.500	17.500	1.00	1.00	0.000
	PD165S	1	5.00	1.810	-	22.822	0.700	39.000	50.000	1.00	1.00	0.000
	Cellwave AS MONR 31	1	22.00	0.940		11.852	0.700	39.000	50.000	1.00	1.00	10.00
	AIR6449 B41	3	103.00	5.650	282.16	6.892	33.100	20.500	8.300	0.75	0.71	0.000
	SDX1926Q-43	3	6.10	0.300	43.70	0.692	6.900	5.500	8.200	0.75	0.67	0.000
	4415 B25	3	46.00	1.640	99.71	2.313	15.000	13.200	5.400	0.75	0.67	0.000
	PD455	3	24.00	6.020		15.970	258.000	2.800	2.800	1.00	1.00	10.00
	PD455	3	24.00	6.020		15.970	258.000	2.800	2.800	1.00	1.00	10.00
	Platform w/ HR	1	1800.0	56.000	4262.73		0.000	0.000	0.000	1.00	1.00	0.000
	(3) HR w/ V-Brace Kits	1	650.00	15.500	1717.18		0.000	0.000	0.000	0.75	1.00	0.000
	PRK-FMA	1	337.91	5.330		12.622	0.000	0.000	0.000	1.00	1.00	0.000
	Cellwave AS MONR 31	1	22.00	0.940		11.852	0.700	39.000	50.000	1.00	1.00	8.000
110.00		2	1.00	0.010	1.09	0.019	4.300	3.900	0.000	1.00	1.00	0.000
	NHH-65B-R2B	3	43.70	8.080	319.08	9.784	72.000	11.900	7.100	0.80	0.83	0.000
110.00	NHHSS-65B-R2B	3	43.70	8.080	319.08	9.784	72.000	11.900	7.100	0.80	0.83	0.000
110.00	MT6407-77A	3	79.40	4.690	243.58	5.931	35.100	16.100	5.500	0.80	0.70	0.000
110.00	BXA-70063-4CF	3	9.90	4.720	141.55	7.109	47.400	11.200	5.200	0.80	0.73	0.000
110.00	RF4440d-13A	3	84.40	1.880	150.66	2.592	15.000	15.000	10.000	0.80	0.67	0.000
110.00	RF4439d-25A	3	70.30	1.880	133.16	2.592	15.000	15.000	8.100	0.80	0.67	0.000
110.00	DB-C1-12C-24AB-0Z	1	32.00	4.060	179.26	5.122	29.500	16.500	12.500	1.00	1.00	0.000
110.00	(3) 12.5' - 2.5" Horizontal Pi	1	217.50	7.188	492.27	18.862	0.000	0.000	0.000	0.75	1.00	0.000
110.00	(3) SFS-H-L (V-Braces)	1	230.00	6.700	645.08	15.769	0.000	0.000	0.000	0.75	1.00	0.000
110.00	RT4401-48A	3	18.60	0.990	54.40	1.535	13.900	8.600	4.200	0.80	1.00	0.000
110.00	Sector Frame	3	500.00	18.450	1402.36	37.429	0.000	0.000	0.000	0.75	0.75	0.000
100.00	Air 6449 N77D	3	88.00	4.130	271.02	5.236	30.800	16.100	10.800	0.80	0.85	0.000
98.00	DMP65R-BU8EA-K	2	82.50	17.870	584.94	20.146	96.000	20.700	7.700	0.80	0.72	0.000
98.00	(3) SFS-H-L	1	230.00	6.700	636.84	15.588	0.000	0.000	0.000	0.75	1.00	0.000
98.00	Sector Frame	3	500.00	17.500	1384.43	35.144	0.000	0.000	0.000	0.75	0.75	0.000
98.00	(3) SFR-K-L	1	394.00	16.600	1311.16	32.016	0.000	0.000	0.000	0.75	1.00	0.000
98.00	HPA-65R-BUU-H8	2	68.00	12.980	453.09	15.060	92.400	14.800	7.400	0.80	0.79	0.000
98.00	HPA-65R-BUU-H6	1	51.00	9.660	379.18	11.418	72.000	14.800	9.000	0.80	0.85	0.000
98.00	LGP-21401	6	14.10	1.290	45.77	2.349	14.400	9.200	2.600	0.80	0.67	0.000
98.00	LGP-21903 Diplexer	6	5.50	0.230	15.24	0.696	4.000	6.000	3.000	0.80	0.67	0.000
98.00	7020.00 RET	12	2.20	0.400	15.16	1.013	4.900	8.300	2.400	0.80	0.67	0.000
98.00	8843 B2 B66A	3	72.00	1.640	131.35	2.269	14.900	13.200	10.900	0.80	0.67	0.000
98.00	4449 B5/B12	3	71.00	1.970	138.63	2.663	17.900	13.200	9.400	0.80	0.67	0.000
98.00	4415 B30	3	44.10	1.860	104.20	2.586	13.500	16.500	4.800	0.80	0.67	0.000
98.00	DC6-48-60-18-8F	1	31.80	2.200	110.13	3.527	24.000	11.000	18.500	0.80	0.67	0.000
	DC6-48-60-0-18-8C-EV	1	20.00	1.900	101.83	2.690	23.500	9.700	9.700	0.80	0.67	0.000
98.00	DC6-48-60-18-8C	1	20.00	1.900	101.83	2.690	23.500	9.700	9.700	0.80	0.67	0.000
	782 10253	3	2.90	0.120	8.12		2.900	4.200	1.800	0.80	0.67	0.000
	(3) Stiff Arm Kit	1	180.00	6.100		14.193	0.000	0.000	0.000	0.75	1.00	0.000
	DMP65R-BU6EA-K	1	79.40	12.710		14.565	71.200	20.700	7.700	0.80	0.72	0.000

Loading Summary

Structure: CT01725-A-SBA Code: EIA/TIA-222-G 12/14/2021

В Site Name: Bloomfield **Exposure:** Height: 125.00 (ft) Crest Height: 0.00

Site Class: D - Stiff Soil **Base Elev:** 0.000 (ft)



Gh:	0.85 Topography: 1 Struct Class: II							Page	lower engineering Solutions		
96.00 A	Air 6419 N77G	3	88.00	4.130	271.02 5.230	6 30.800	16.100	10.800	0.80	0.85	0.000
87.00 S	Sector Frame	3	450.00	18.000	895.75 29.462	2 0.000	0.000	0.000	0.75	0.75	0.000
87.00 A	APXVTM14-C-120	3	56.00	6.340	270.33 7.77	5 56.300	12.600	6.300	0.80	0.79	0.000
87.00 8	300MHz Filter	3	10.00	0.490	30.33 1.20	1 4.600	11.000	4.500	0.80	0.67	0.000
87.00 1	1900MHz RRH	3	60.00	2.770	165.71 4.37	7 25.000	11.100	11.400	0.80	0.67	0.000
87.00 8	BOOMHZ RRH	3	59.50	2.640	158.33 4.100	6 18.000	15.100	11.300	0.80	0.67	0.000
87.00 T	TD-RRH8x20-25	3	70.00	4.050	217.87 5.10	1 26.100	18.600	6.700	0.80	0.67	0.000
87.00 A	ACU-A20-N	4	1.00	0.140	6.44 0.510	6 4.000	2.000	3.500	0.80	0.67	0.000
87.00 A	APXVSPP18-C-A20	3	57.00	8.020	275.99 11.55	9 72.000	11.800	7.000	0.80	0.83	0.000
77.00 N	MX08FRO665-21	3	64.50	12.490	423.87 14.300	72.000	20.000	8.000	0.80	0.74	0.000
77.00 T	ΓA08025-B604	3	63.90	1.960	126.45 2.65	3 15.800	15.000	7.900	0.80	0.67	0.000
77.00 T	ΓA08025-B605	3	75.00	1.960	139.62 2.65	3 15.800	15.000	9.100	0.80	0.67	0.000
77.00 R	RDIDC-9181-OF-48	1	21.90	2.010	87.69 2.712	2 16.600	14.600	8.500	0.80	1.00	0.000
77.00 N	MTC3975083	3	414.00	10.600	913.89 27.056	0.000	0.000	0.000	0.75	0.75	0.000
65.00 C	CS72188.01 LMU	1	0.31	0.170	1.14 0.40	3 4.500	4.500	4.500	1.00	1.00	0.000
65.00 S	Standoff Mount	1	40.00	1.500	74.50 2.79	4 0.000	0.000	0.000	1.00	1.00	0.000

Totals: 161 15,797.42 48,554.91 Number of Appurtenances :

Loading Summary

Structure: CT01725-A-SBA **Code:** EIA/TIA-222-G 12/14/2021

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II Page: 7



Linear Appurtenances Properties

Elev. From	Elev. To			Width	Weight	Pct In	Spread On	Bundling	Cluster Dia	of	Spacing	Orientation	Ka
(ft)	(ft)	Description	Qty	(in)	(lb/ft)	Block	Faces	Arrangement	(in)	Zone	(in)	Factor	Override
0.00	125.00	1 1/4" Coax	1	1.55	0.66	100.00	2	Individual NR		N	1.00	1.00	
0.00	125.00	1 5/8" Coax	9	1.98	1.04	50.00	3	Block		Ν	0.50	1.00	
0.00	125.00	1 5/8" Hybrid	2	2.00	1.10	50.00	3	Block		Ν	0.50	1.00	
0.00	125.00	1-1/4" Hybrid	2	1.25	0.95	50.00	3	Block		N	0.50	1.00	
0.00	125.00	1/2" Coax	2	0.65	0.16	100.00	2	Individual NR		N	1.00	1.00	
0.00	125.00	7/8" Coax	1	1.11	0.52	100.00	2	Individual NR		N	1.00	1.00	
0.00	125.00	7/8" Coax	4	1.11	0.52	100.00	2	Individual IR		Ν	1.00	1.00	
0.00	125.00	Climbing Ladder	1	3.00	6.90	100.00	1	Individual NR		N	1.00	1.00	
0.00	125.00	W/G Ladder	1	3.00	6.00	100.00	3	Individual NR		N	1.00	1.00	
0.00	125.00	W/G Ladder	1	2.00	6.00	100.00	2	Individual NR		Ν	1.00	1.00	
0.00	110.00	1 5/8" Coax	18	1.98	1.04	50.00	3	Block		N	0.50	1.00	
0.00	110.00	1 5/8" Fiber	1	2.00	1.10	100.00	3	Individual NR		N	1.00	1.00	
0.00	110.00	1/2" Coax	2	0.65	0.16	100.00	3	Individual NR		Ν	1.00	1.00	
0.00	110.00	W/G Ladder	1	2.00	6.00	100.00	3	Individual NR		Ν	1.00	1.00	
0.00	98.00	1/2" Fiber	1	0.65	0.16	100.00	2	Individual IR		Υ	1.00	1.00	0
0.00	98.00	3" Conduit	1	3.00	1.61	100.00	2	Individual NR		N	1.00	1.00	
0.00	98.00	3/4" DC	4	0.75	0.40	50.00	2	Block		Ν	0.50	1.00	
0.00	98.00	7/8" Coax	12	1.11	0.52	66.60	2	Block		Ν	0.50	1.00	
0.00	98.00	W/G Ladder	1	2.00	6.00	100.00	2	Individual NR		N	1.00	1.00	
0.00	87.00	1 1/4" Coax	4	1.55	0.66	100.00	1	Individual IR		Ν	1.00	1.00	
0.00	87.00	W/G Ladder	1	2.00	6.00	100.00	1	Individual NR		N	1.00	1.00	
0.00	77.00	1.411" Hybrid	1	1.40	1.14	100.00	1	Individual NR		Ν	1.00	1.00	
0.00	77.00	W/G Ladder	1	3.00	6.00	100.00	1	Individual NR		N	1.00	1.00	
0.00	65.00	1/2" Coax	1	0.65	0.16	100.00	2	Individual NR		Ν	1.00	1.00	

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II



Load Case: 1.2D + 1.6W Normal Wind 1.2D + 1.6W 97 mph Wind at Normal To Face

Wind Load Factor: 1.60 Wind Importance Factor: 1.00

Dead Load Factor: 1.20 Ice Dead Load Factor: 0.00

Ice Importance Factor: 1.00

Sect Seq	Wind Height (ft)	F	rea	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	14.33 16	5.978	28.78	0.00	0.18	2.65	1.00	1.00	0.00	30.23	154.81	0.00	5,580.3	0.0	1562.59	2675.71	4,238.31
2	30.0	14.34 18	3.717	22.10	0.00	0.19	2.63	1.00	1.00	0.00	30.19	154.81	0.00	4,974.0	0.0	1551.12	2677.97	4,229.09
3	50.0	16.60 12	2.939	22.10	0.00	0.19	2.64	1.00	1.00	0.00	24.10	154.81	0.00	4,337.5	0.0	1433.70	3098.79	4,532.49
4	70.0	18.27 11	1.598	18.56	0.00	0.20	2.61	1.00	1.00	0.00	21.45	152.90	0.00	3,918.4	0.0	1392.04	3368.32	4,760.36
5	90.0	19.63 9	9.614	13.35	0.00	0.19	2.63	1.00	1.00	0.00	17.26	134.02	0.00	3,086.5	0.0	1213.66	3166.59	4,380.25
6	110.0	20.79 6	5.277	9.59	0.00	0.18	2.68	1.00	1.00	0.00	11.75	75.18	0.00	1,931.5	0.0	889.15	1955.32	2,844.47
7	122.5	21.44 1	1.223	3.24	0.00	0.24	2.47	1.00	1.00	0.00	3.14	13.15	0.00	452.6	0.0	226.28	355.78	582.06
														24,280.9	0.0	<u> </u>		25,567.03

Load Case: 1.2D + 1.6W 60° Wind 1.2D + 1.6W 97 mph Wind at 60° From Face

Wind Load Factor: 1.60

Dead Load Factor: 1.20

Wind Importance Factor: 1.00

Ice Dead Load Factor: 0.00 Ice Importance Factor: 1.00

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	14.33 16.97	8 28.78	0.00	0.18	2.65	0.80	1.00	0.00	26.83	154.81	0.00	5,580.3	0.0	1387.06	2675.71	4,062.78
2	30.0	14.34 18.71	7 22.10	0.00	0.19	2.63	0.80	1.00	0.00	26.45	154.81	0.00	4,974.0	0.0	1358.82	2677.97	4,036.80
3	50.0	16.60 12.93	9 22.10	0.00	0.19	2.64	0.80	1.00	0.00	21.51	154.81	0.00	4,337.5	0.0	1279.76	3098.79	4,378.54
4	70.0	18.27 11.59	8 18.56	0.00	0.20	2.61	0.80	1.00	0.00	19.13	152.90	0.00	3,918.4	0.0	1241.53	3368.32	4,609.85
5	90.0	19.63 9.61	4 13.35	0.00	0.19	2.63	0.80	1.00	0.00	15.33	134.02	0.00	3,086.5	0.0	1078.43	3166.59	4,245.01
6	110.0	20.79 6.27	7 9.59	0.00	0.18	2.68	0.80	1.00	0.00	10.50	75.18	0.00	1,931.5	0.0	794.16	1955.32	2,749.49
7	122.5	21.44 1.22	3 3.24	0.00	0.24	2.47	0.80	1.00	0.00	2.90	13.15	0.00	452.6	0.0	208.65	355.78	564.44
													24 280 9	0.0	<u>-</u>		24 646 90

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II



Load Case: 1.2D + 1.6W 90° Wind 1.2D + 1.6W 97 mph Wind at 90° From Face

Wind Load Factor: 1.60 Wind Importance Factor: 1.00

Dead Load Factor: 1.20
Ice Dead Load Factor: 0.00

Ice Importance Factor: 1.00

Sect Seq	Wind Height (ft)	qz (psf)	Total Flat Area (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	14.33	16.978	28.78	0.00	0.18	2.65	0.85	1.00	0.00	27.68	154.81	0.00	5,580.3	0.0	1430.95	2675.71	4,106.66
2	30.0	14.34	18.717	22.10	0.00	0.19	2.63	0.85	1.00	0.00	27.39	154.81	0.00	4,974.0	0.0	1406.90	2677.97	4,084.87
3	50.0	16.60	12.939	22.10	0.00	0.19	2.64	0.85	1.00	0.00	22.16	154.81	0.00	4,337.5	0.0	1318.24	3098.79	4,417.03
4	70.0	18.27	11.598	18.56	0.00	0.20	2.61	0.85	1.00	0.00	19.71	152.90	0.00	3,918.4	0.0	1279.16	3368.32	4,647.47
5	90.0	19.63	9.614	13.35	0.00	0.19	2.63	0.85	1.00	0.00	15.81	134.02	0.00	3,086.5	0.0	1112.24	3166.59	4,278.82
6	110.0	20.79	6.277	9.59	0.00	0.18	2.68	0.85	1.00	0.00	10.81	75.18	0.00	1,931.5	0.0	817.91	1955.32	2,773.23
7	122.5	21.44	1.223	3.24	0.00	0.24	2.47	0.85	1.00	0.00	2.96	13.15	0.00	452.6	0.0	213.06	355.78	568.84
														24,280.9	0.0	0		24,876.93

Load Case: 0.9D + 1.6W Normal Wind 0.9D + 1.6W 97 mph Wind at Normal To Face

Wind Load Factor: 1.60
Dead Load Factor: 0.90
Ice Dead Load Factor: 0.00

Ice Importance Factor: 1.00
Ice Importance Factor: 1.00

			Tot	tal	Total	Ice								Ice					
		Wind	Fla	at I	Round	Round					Ice	Eff	Linear	Linear	Total		Struct	Linear	Total
S	ect l	Height	qz Are	ea	Area	Area	Sol				Thick	Area	Area	Area	Weight	Weight	Force	Force	Force
s	eq	(ft)	(psf) (sq	ft)	(sqft)	(sqft)	Ratio	Cf	Df	Dr	(in)	(sqft)	(sqft)	(sqft)	(lb)	Ice (lb)	(lb)	(lb)	(lb)
	1	10.0	14.33 16.9	978	28.78	0.00	0.18	2.65	1.00	1.00	0.00	30.23	154.81	0.00	4,185.2	0.0	1562.59	2675.71	4,238.31
	2	30.0	14.34 18.	717	22.10	0.00	0.19	2.63	1.00	1.00	0.00	30.19	154.81	0.00	3,730.5	0.0	1551.12	2677.97	4,229.09
	3	50.0	16.60 12.9	939	22.10	0.00	0.19	2.64	1.00	1.00	0.00	24.10	154.81	0.00	3,253.1	0.0	1433.70	3098.79	4,532.49
	4	70.0	18.27 11.	598	18.56	0.00	0.20	2.61	1.00	1.00	0.00	21.45	152.90	0.00	2,938.8	0.0	1392.04	3368.32	4,760.36
	5	90.0	19.63 9.0	614	13.35	0.00	0.19	2.63	1.00	1.00	0.00	17.26	134.02	0.00	2,314.9	0.0	1213.66	3166.59	4,380.25
	6 1	110.0	20.79 6.2	277	9.59	0.00	0.18	2.68	1.00	1.00	0.00	11.75	75.18	0.00	1,448.7	0.0	889.15	1955.32	2,844.47
	7 1	122.5	21.44 1.3	223	3.24	0.00	0.24	2.47	1.00	1.00	0.00	3.14	13.15	0.00	339.5	0.0	226.28	355.78	582.06
															18,210.7	0.0	<u></u>		25,567.03

Structure: CT01725-A-SBA Code: EIA/TIA-222-G 12/14/2021

Site Name: Bloomfield **Exposure:** В Height: 125.00 (ft) Crest Height: 0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Struct Class: || Topography: 1



Page: 10

Load Case: 0.9D + 1.6W 60° Wind

0.9D + 1.6W 97 mph Wind at 60° From Face Wind Load Factor: 1.60 Wind Importance Factor: 1.00

Dead Load Factor: 0.90 Ice Dead Load Factor: 0.00

Ice Importance Factor: 1.00

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	14.33 16.97	8 28.78	0.00	0.18	2.65	0.80	1.00	0.00	26.83	154.81	0.00	4,185.2	0.0	1387.06	2675.71	4,062.78
2	30.0	14.34 18.71	7 22.10	0.00	0.19	2.63	0.80	1.00	0.00	26.45	154.81	0.00	3,730.5	0.0	1358.82	2677.97	4,036.80
3	50.0	16.60 12.93	9 22.10	0.00	0.19	2.64	0.80	1.00	0.00	21.51	154.81	0.00	3,253.1	0.0	1279.76	3098.79	4,378.54
4	70.0	18.27 11.59	8 18.56	0.00	0.20	2.61	0.80	1.00	0.00	19.13	152.90	0.00	2,938.8	0.0	1241.53	3368.32	4,609.85
5	90.0	19.63 9.61	4 13.35	0.00	0.19	2.63	0.80	1.00	0.00	15.33	134.02	0.00	2,314.9	0.0	1078.43	3166.59	4,245.01
6	110.0	20.79 6.27	7 9.59	0.00	0.18	2.68	0.80	1.00	0.00	10.50	75.18	0.00	1,448.7	0.0	794.16	1955.32	2,749.49
7	122.5	21.44 1.22	3 3.24	0.00	0.24	2.47	0.80	1.00	0.00	2.90	13.15	0.00	339.5	0.0	208.65	355.78	564.44
													18.210.7	0.0	<u></u>		24.646.90

0.9D + 1.6W 97 mph Wind at 90° From Face Load Case: 0.9D + 1.6W 90° Wind

Wind Load Factor: 1.60 Wind Importance Factor: 1.00 **Dead Load Factor:** 0.90

Ice Importance Factor: 1.00 Ice Dead Load Factor: 0.00

		Т	otal	Total	Ice								lce					
	Wind	ı	Flat	Round	Round					Ice	Eff	Linear	Linear	Total		Struct	Linear	Total
_	- 3		Area	Area	Area	Sol	٥,	ъ.		Thick	Area	Area	Area	3	-	Force	Force	Force
Seq	(ft)	(psf) (s	sqft)	(sqft)	(sqft)	Ratio	Cī	Df	Dr	(in)	(sqft)	(sqft)	(sqft)	(lb)	Ice (lb)	(lb)	(lb)	(lb)
1	10.0	14.33 1	6.978	28.78	0.00	0.18	2.65	0.85	1.00	0.00	27.68	154.81	0.00	4,185.2	0.0	1430.95	2675.71	4,106.66
2	30.0	14.34 1	8.717	22.10	0.00	0.19	2.63	0.85	1.00	0.00	27.39	154.81	0.00	3,730.5	0.0	1406.90	2677.97	4,084.87
3	50.0	16.60 1	2.939	22.10	0.00	0.19	2.64	0.85	1.00	0.00	22.16	154.81	0.00	3,253.1	0.0	1318.24	3098.79	4,417.03
4	70.0	18.27 1	1.598	18.56	0.00	0.20	2.61	0.85	1.00	0.00	19.71	152.90	0.00	2,938.8	0.0	1279.16	3368.32	4,647.47
5	90.0	19.63	9.614	13.35	0.00	0.19	2.63	0.85	1.00	0.00	15.81	134.02	0.00	2,314.9	0.0	1112.24	3166.59	4,278.82
6	110.0	20.79	6.277	9.59	0.00	0.18	2.68	0.85	1.00	0.00	10.81	75.18	0.00	1,448.7	0.0	817.91	1955.32	2,773.23
7	122.5	21.44	1.223	3.24	0.00	0.24	2.47	0.85	1.00	0.00	2.96	13.15	0.00	339.5	0.0	213.06	355.78	568.84
														18,210.7	0.	0		24,876.93

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II



Page: 11



Load Case: 1.2D + 1.0Di + 1.0Wi Normal Wind 1.2D + 1.0Di + 1.0Wi 50 mph Wind at Normal From Face

Wind Load Factor: 1.00 Wind Importance Factor: 1.00

Dead Load Factor: 1.20 Ice Dead Load Factor: 1.00

Ice Importance Factor: 1.00

Sect Seq	Wind Height (ft)		Total Flat Area (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	lce Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	3.81	16.978	58.69	29.91	0.30	2.31	1.00	1.00	1.77	52.06	251.99	65.08	15,359.	9778.7	388.55	983.84	1,372.39
2	30.0	3.81	18.717	54.01	31.91	0.33	2.23	1.00	1.00	1.98	51.54	262.30	72.64	16,237.	11263.6	371.90	1030.68	1,402.58
3	50.0	4.41	12.939	58.75	36.64	0.37	2.12	1.00	1.00	2.08	49.62	267.49	76.44	15,602.	11264.8	394.94	1206.77	1,519.23
4	70.0	4.86	11.598	53.95	35.39	0.41	2.05	1.00	1.00	2.16	46.07	268.07	72.59	15,100.	11181.6	390.15	1294.99	1,685.14
5	90.0	5.22	9.614	50.34	36.99	0.46	1.95	1.00	1.00	2.21	43.17	230.75	64.86	13,029.	9943.1	373.29	1083.38	1,456.67
6	110.0	5.52	6.277	44.25	34.66	0.52	1.88	1.00	1.00	2.26	37.05	140.34	41.36	8,582.6	6651.1	326.47	627.61	954.08
7	122.5	5.70	1.223	17.57	14.33	0.91	1.94	1.00	1.00	2.28	18.42	27.70	7.60	2,222.0	1769.4	173.23	23.19	196.43
														86.133.1	61852.2	-	•	8.586.51

Load Case: 1.2D + 1.0Di + 1.0Wi 60° Wind 1.2D + 1.0Di + 1.0Wi 50 mph Wind at 60° From Face Wind Load Factor: 1.00

Wind Load Factor: 1.00
Dead Load Factor: 1.20
Ice Dead Load Factor: 1.00

Wind Importance Factor: 1.00

Ice Importance Factor: 1.00

Total Total Ice Ice Wind Eff Flat Round Round Ice Linear Linear Total Struct Linear Total Sect Height Area Area Sol Thick Area Area Area Weight Weight **Force Force** Force Area αz Seq (ft) (psf) (sqft) (sqft) (sqft) Ratio Cf Df Dr (in) (sqft) (sqft) (sqft) (lb) Ice (lb) (lb) (lb) (lb) 1 10.0 3.81 16.978 58.69 29.91 0.30 2.31 0.80 1.00 1.77 48.67 251.99 65.08 15,359. 9778.7 363.21 983.84 1,347.05 2 30.0 3.81 18.717 54.01 31.91 0.33 2.23 0.80 1.00 1.98 47.79 262.30 72.64 16,237. 11263.6 344.89 1030.68 1,375.57 3 50.0 4.41 12.939 58.75 36.64 0.37 2.12 0.80 1.00 2.08 47.03 267.49 76.44 15,602. 11264.8 374.34 1206.77 1,581.11 70.0 4.86 11.598 53.95 35.39 0.41 2.05 0.80 1.00 2.16 43.75 268.07 72.59 15,100. 11181.6 370.51 1294.99 1,665.50 5 90.0 5.22 9.614 50.34 36.99 0.46 1.95 0.80 1.00 2.21 41.24 230.75 64.86 13,029. 9943.1 356.66 1083.38 1,440.04 110.0 5.52 6.277 44.25 34.66 2.26 35.80 140.34 41.36 6651.1 315.41 627.61 943.02 6 0.52 1.88 0.80 1.00 8,582.6 7 122.5 5.70 1.223 17.57 14.33 0.91 1.94 0.80 1.00 2.28 18.18 27.70 7.60 2,222.0 1769.4 170.93 23.19 194.13 86,133.1 61852.2 8,546.40

Structure: CT01725-A-SBA Code: EIA/TIA-222-G 12/14/2021

Site Name: Bloomfield **Exposure:** В Height: 125.00 (ft) Crest Height: 0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Struct Class: II Topography: 1



Load Case: 1.2D + 1.0Di + 1.0Wi 90° Wind 1.2D + 1.0Di + 1.0Wi 50 mph Wind at 90° From Face

Wind Load Factor: 1.00 Wind Importance Factor: 1.00

Dead Load Factor: 1.20 Ice Dead Load Factor: 1.00

Ice Importance Factor: 1.00

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	lce Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	3.81 16.978	58.69	29.91	0.30	2.31	0.85	1.00	1.77	49.52	251.99	65.08	15,359.	9778.7	369.54	983.84	1,353.38
2	30.0	3.81 18.71	7 54.01	31.91	0.33	2.23	0.85	1.00	1.98	48.73	262.30	72.64	16,237.	11263.6	351.64	1030.68	1,382.32
3	50.0	4.41 12.939	58.75	36.64	0.37	2.12	0.85	1.00	2.08	47.68	267.49	76.44	15,602.	11264.8	379.49	1206.77	1,586.26
4	70.0	4.86 11.59	8 53.95	35.39	0.41	2.05	0.85	1.00	2.16	44.33	268.07	72.59	15,100.	11181.6	375.42	1294.99	1,670.41
5	90.0	5.22 9.61	4 50.34	36.99	0.46	1.95	0.85	1.00	2.21	41.73	230.75	64.86	13,029.	9943.1	360.82	1083.38	1,444.20
6	110.0	5.52 6.27	7 44.25	34.66	0.52	1.88	0.85	1.00	2.26	36.11	140.34	41.36	8,582.6	6651.1	318.17	627.61	945.78
7	122.5	5.70 1.223	3 17.57	14.33	0.91	1.94	0.85	1.00	2.28	18.24	27.70	7.60	2,222.0	1769.4	171.51	23.19	194.70
													86,133.1	61852.2	<u>-</u>		8,577.05

1.0D + 1.0W 60 mph Wind at Normal To Face Load Case: 1.0D + 1.0W Normal Wind

Wind Load Factor: 1.00 Wind Importance Factor: 1.00 1.00 **Dead Load Factor:** 1.00 Ice Dead Load Factor: 0.00 Ice Importance Factor:

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	5.48 16.978	28.78	0.00	0.18	2.65	1.00	1.00	0.00	32.94	154.81	0.00	4,650.3	0.0	407.14	639.85	1,046.99
2	30.0	5.49 18.717	22.10	0.00	0.19	2.63	1.00	1.00	0.00	31.37	154.81	0.00	4,145.0	0.0	385.41	640.39	1,025.80
3	50.0	6.35 12.939	22.10	0.00	0.19	2.64	1.00	1.00	0.00	25.59	154.81	0.00	3,614.6	0.0	364.10	741.02	1,105.12
4	70.0	6.99 11.598	18.56	0.00	0.20	2.61	1.00	1.00	0.00	22.25	152.90	0.00	3,265.3	0.0	345.20	805.47	1,150.67
5	90.0	7.51 9.614	13.35	0.00	0.19	2.63	1.00	1.00	0.00	17.26	134.02	0.00	2,572.1	0.0	290.23	757.23	1,047.46
6	110.0	7.96 6.277	9.59	0.00	0.18	2.68	1.00	1.00	0.00	11.75	75.18	0.00	1,609.6	0.0	212.62	467.58	680.21
7	122.5	8.20 1.223	3.24	0.00	0.24	2.47	1.00	1.00	0.00	3.14	13.15	0.00	377.2	0.0	54.11	85.08	139.19
													20,234.1	0.0		•	6,195.43

Structure: CT01725-A-SBA Code: EIA/TIA-222-G 12/14/2021

Site Name: Bloomfield **Exposure:** В Height: 125.00 (ft) Crest Height: 0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Struct Class: II Topography: 1



Ice Importance Factor:

Load Case: 1.0D + 1.0W 60° Wind 1.0D + 1.0W 60 mph Wind at 60° From Face

> Wind Load Factor: 1.00 Wind Importance Factor: 1.00

Dead Load Factor: 1.00 Ice Dead Load Factor: 0.00

Ice Importance Factor: 1.00

1.00

1.00

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	5.48 16.978	28.78	0.00	0.18	2.65	0.80	1.00	0.00	29.54	154.81	0.00	4,650.3	0.0	365.16	639.85	1,005.01
2	30.0	5.49 18.717	22.10	0.00	0.19	2.63	0.80	1.00	0.00	27.63	154.81	0.00	4,145.0	0.0	339.43	640.39	979.82
3	50.0	6.35 12.939	22.10	0.00	0.19	2.64	0.80	1.00	0.00	23.01	154.81	0.00	3,614.6	0.0	327.28	741.02	1,068.30
4	70.0	6.99 11.598	18.56	0.00	0.20	2.61	0.80	1.00	0.00	19.93	152.90	0.00	3,265.3	0.0	309.20	805.47	1,114.68
5	90.0	7.51 9.614	13.35	0.00	0.19	2.63	0.80	1.00	0.00	15.33	134.02	0.00	2,572.1	0.0	257.89	757.23	1,015.12
6	110.0	7.96 6.277	9.59	0.00	0.18	2.68	0.80	1.00	0.00	10.50	75.18	0.00	1,609.6	0.0	189.91	467.58	657.49
7	122.5	8.20 1.223	3.24	0.00	0.24	2.47	0.80	1.00	0.00	2.90	13.15	0.00	377.2	0.0	49.90	85.08	134.98
													20,234.1	0.0	<u> </u>		5.975.40

1.0D + 1.0W 60 mph Wind at 90° From Face Load Case: 1.0D + 1.0W 90° Wind

Wind Load Factor: 1.00 Wind Importance Factor: **Dead Load Factor:** 1.00 Ice Dead Load Factor: 0.00

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (Ib)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	5.48 16.978	28.78	0.00	0.18	2.65	0.85	1.00	0.00	30.39	154.81	0.00	4,650.3	0.0	375.65	639.85	1,015.50
2	30.0	5.49 18.717	22.10	0.00	0.19	2.63	0.85	1.00	0.00	28.57	154.81	0.00	4,145.0	0.0	350.92	640.39	991.31
3	50.0	6.35 12.939	22.10	0.00	0.19	2.64	0.85	1.00	0.00	23.65	154.81	0.00	3,614.6	0.0	336.49	741.02	1,077.51
4	70.0	6.99 11.598	18.56	0.00	0.20	2.61	0.85	1.00	0.00	20.51	152.90	0.00	3,265.3	0.0	318.20	805.47	1,123.68
5	90.0	7.51 9.614	13.35	0.00	0.19	2.63	0.85	1.00	0.00	15.81	134.02	0.00	2,572.1	0.0	265.97	757.23	1,023.21
6	110.0	7.96 6.277	9.59	0.00	0.18	2.68	0.85	1.00	0.00	10.81	75.18	0.00	1,609.6	0.0	195.59	467.58	663.17
7	122.5	8.20 1.223	3.24	0.00	0.24	2.47	0.85	1.00	0.00	2.96	13.15	0.00	377.2	0.0	50.95	85.08	136.03
													20,234.1	0.0	_	•	6,030.41

Force/Stress Compression Summary

Structure: CT01725-A-SBA **Code**: EIA/TIA-222-G 12/14/2021

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II





4	
Page: 14	Tower Engineering So

	LEG MEMBERS														
Sect	Top Elev Member	Force (kips)	Load Case	Len (ft)	Bı X	racinç Y	g % Z	KL/R	Fy (ksi)	Mem Cap (kips)	Leg Use %	Controls			
1	20 PST - 8" DIA PIPE	-297.04	1.2D + 1.6W Normal Wind	9.76	100	100	100	39.83	55.00	365.98	81.2	Member X			
2	40 PST - 6" DIA PIPE	-255.31	1.2D + 1.6W Normal Wind	9.76	50	50	50	26.02	55.00	261.57	97.6	Member X			
3	60 PST - 6" DIA PIPE	-212.37	1.2D + 1.6W Normal Wind	6.51	100	100	100	34.70	55.00	250.72	84.7	Member X			
4	80 PST - 5" DIA PIPE	-160.24	1.2D + 1.6W Normal Wind	6.51	100	100	100	41.53	55.00	185.28	86.5	Member X			
5	100 PST - 3-1/2" DIA PIPE	-104.49	1.2D + 1.6W Normal Wind	4.88	100	100	100	43.70	55.00	113.77	91.8	Member X			
6	120 PST - 2-1/2" DIA PIPE	-48.50	1.2D + 1.6W Normal Wind	4.94	100	100	100	62.62	55.00	61.53	78.8	Member X			
7	125 PST - 2-1/2" DIA PIPE	-12.23	1.2D + 1.6W Normal Wind	2.50	100	100	100	31.68	55.00	77.81	15.7	Member X			

Splices

			Top Splic	e					Bottom Sp	lice			
Sect	Top Elev	Load Case	Force (kips)	Cap (kips)	Use %	Bolt Type	Num Bolts	Load Case	Force (kips)	Cap (kips)	Use %	Bolt Type	Num Bolts
1	20	1.2D + 1.6W Normal Wind	267.99	0.00	0.0			1.2D + 1.6W Normal Wind	309.50	0.00			
2	40	1.2D + 1.6W Normal Wind	221.53	0.00	0.0			1.2D + 1.6W Normal Wind	267.99	0.00		1/4 A325	8
3	60	1.2D + 1.6W Normal Wind	170.36	0.00	0.0			1.2D + 1.6W Normal Wind	221.53	0.00		1 A325	8
4	80	1.2D + 1.6W Normal Wind	112.40	0.00	0.0			1.2D + 1.6W Normal Wind	170.36	0.00		1 A325	8
5	100	1.2D + 1.6W Normal Wind	54.32	0.00	0.0			1.2D + 1.6W Normal Wind	112.40	0.00		1 A325	6
6	120	1.2D + 1.6W Normal Wind	15.09	0.00	0.0			1.2D + 1.6W Normal Wind	54.32	0.00		3/4 A325	6
7	125	1.2D + 1.0Di + 1.0Wi 90° Wind	5.16	0.00	0.0			1.2D + 1.6W Normal Wind	15.09	0.00		3/4 A325	4

				H	IORIZO	NIA	L MEI	MRF	रऽ								
Sect	Top Elev	Member	Force (kips)		Len (ft)	Br X	acing Y	ı % Z	KL/R	Fy (ksi)			Num Holes	Shear Cap (kips)	Сар	Use %	Controls
1	20										0.00	0	0				
2	40										0.00	0	0				
3	60										0.00	0	0				
4	80										0.00	0	0				
5	100										0.00	0	0				
6	120										0.00	0	0				
7	125	SAE - 1.5X1.5X0.1875	-4.15	1.2D + 1.6W Normal Wind	3.50	100	100	100	100.34	36.00	10.11	2	1	35.78	27.73	41	Member Z

					DIAGO	NAL	МЕМ	BER	S								
Sect	Top Elev	Member	Force (kips)	Load Case	Len (ft)	Br X	acing Y	ј % Z	KL/R	Fy (ksi)		Num Bolts	Num Holes	Shear Cap (kips)	Сар	Use %	Controls
1	20	SAE - 3.5X3.5X0	.25 -9.47	0.9D + 1.6W 90° Wind	14.99	50	50	50	129.60	36.00	22.62	1	1	12.43	13.0	76	Bolt Shear
2	40	SAE - 3X3X0.25	-9.91	1.2D + 1.6W 90° Wind	13.89	50	50	50	140.73	36.00	16.43	1	1	12.43	13.0	80	Bolt Shear
3	60	SAE - 2.5X2.5X0	.1875 -8.49	1.2D + 1.6W 90° Wind	10.51	50	50	50	127.44	36.00	12.43	1	1	12.43	9.79	87	Bolt Bear
4	80	SAE - 2.5X2.5X0	.1875 -8.81	1.2D + 1.6W 90° Wind	9.38	50	50	50	115.28	36.00	14.52	2	1	15.90	18.6	61	Member Z
5	100	SAE - 2X2X0.187	75 -6.67	1.2D + 1.6W 90° Wind	7.97	50	50	50	121.30	36.00	10.60	1	1	7.95	7.50	89	Bolt Bear
6	120	SAE - 1.5X1.5X0	.1875 -4.28	1.2D + 1.6W 90° Wind	6.88	50	50	50	140.97	36.00	6.02	1	1	7.95	7.50	71	Member Z
7	125	SOL - 5/8" SOLIE	-2.43	1.2D + 1.6W Normal Wind	4.30	50	50	50	148.89	36.00	3.13	0	0				T-Only

Force/Stress Tension Summary

Structure: CT01725-A-SBA **Code:** EIA/TIA-222-G 12/14/2021

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class:





Struct Class:	II	Page: 15
LEG MEMBERS		

						Mem		
	Top		Force		Fy	Cap	Leg	
Sect	Elev	Member	(kips)	Load Case	(ksi)	(kips)	Use %	Controls
1	20	PST - 8" DIA PIPE	277.74	0.9D + 1.6W 60° Wind	55	415.80	66.8	Member
2	40	PST - 6" DIA PIPE	239.49	0.9D + 1.6W 60° Wind	55	276.21	86.7	Member
3	60	PST - 6" DIA PIPE	196.74	0.9D + 1.6W 60° Wind	55	276.21	71.2	Member
4	80	PST - 5" DIA PIPE	148.86	0.9D + 1.6W 60° Wind	55	212.85	69.9	Member
5	100	PST - 3-1/2" DIA PIPE	94.99	0.9D + 1.6W 60° Wind	55	132.66	71.6	Member
6	120	PST - 2-1/2" DIA PIPE	42.98	0.9D + 1.6W 60° Wind	55	84.35	51.0	Member
7	125	PST - 2-1/2" DIA PIPE	4.36	0.9D + 1.6W Normal Wind	55	84.35	5.2	Member

Splices

				Bottom Splice									
Sect	Top Elev	Load Case	Force (kips)	Cap (kips)	Use %	Bolt Type	Num Bolts	Load Case	Force (kips) (•	Use %	Bolt Type	Num Bolts
1	20	0.9D + 1.6W 60° Wind	239.22	0.00	0.0			0.9D + 1.6W 60° Wind	277.7	0.00			
2	40	0.9D + 1.6W 60° Wind	196.44	0.00	0.0			0.9D + 1.6W 60° Wind	239.2 6	510.56	39.2	I 1/4 A32	5 8
3	60	0.9D + 1.6W 60° Wind	148.65	0.00	0.0			0.9D + 1.6W 60° Wind	196.4 4	124.08	46.3	1 A32	5 8
4	80	0.9D + 1.6W 60° Wind	94.81	0.00	0.0			0.9D + 1.6W 60° Wind	148.6 4	124.08	35.1	1 A32	5 8
5	100	0.9D + 1.6W 60° Wind	42.79	0.00	0.0			0.9D + 1.6W 60° Wind	94.81 3	318.06	29.8	1 A32	5 6
6	120	0.9D + 1.6W 60° Wind	5.98	0.00	0.0			0.9D + 1.6W 60° Wind	42.79 1	180.60	23.7	3/4 A32	5 6
7	125		0.00	0.00	0.0			0.9D + 1.6W 60° Wind	5.98 1	120.40	5.0	3/4 A32	5 4

	HORIZONTAL MEMBERS											
Sect	Top Elev	Member	Force (kips) Load	Fy Case (ksi)	Mem Cap (kips)	Num Bolts	Num Holes	Shear Cap (kips)	Bear Cap (kips)	B.S. Cap (kips)	Use % (Controls
1	20	-		36	0.00	0	0					
2	40	-		36	0.00	0	0					
3	60	-		36	0.00	0	0					
4	80	-		36	0.00	0	0					
5	100	-		36	0.00	0	0					
6	120	-		36	0.00	0	0					
7	125	SAE - 1.5X1.5X0.1875	2.01 1.2D + 1.6W	Normal Wi 36	15.92	2	1	35.78	27.73	13.18	15.2 E	Blck Shear

	DIAGONAL MEMBERS												
Sect	Top Elev	Member	Force (kips)	Load Case	Fy (ksi)	Mem Cap (kips)	Num Bolts	Num Holes	Shear Cap (kips)	Bear Cap (kips)	B.S. Cap (kips)	Use %	Controls
1	20	SAE - 3.5X3.5X0.25	9.03 0.9	D + 1.6W 90° Wind	36	54.76	1	1	12.43	13.05	16.79	72.6	Bolt Shear
2	40	SAE - 3X3X0.25	9.11 0.9	D + 1.6W 90° Wind	36	46.66	1	1	12.43	13.05	14.07	73.3	Bolt Shear
3	60	SAE - 2.5X2.5X0.1875	8.22 1.2	D + 1.6W 90° Wind	36	29.22	1	1	12.43	9.79	9.53	86.2	Blck Shear
4	80	SAE - 2.5X2.5X0.1875	8.51 1.2	D + 1.6W 90° Wind	36	29.22	2	1	15.90	18.60	13.66	62.3	Blck Shear
5	100	SAE - 2X2X0.1875	6.53 1.2	D + 1.6W 90° Wind	36	23.00	1	1	7.95	7.50	7.25	90.1	Blck Shear
6	120	SAE - 1.5X1.5X0.1875	4.29 1.2	D + 1.6W 90° Wind	36	17.17	1	1	7.95	7.50	5.21	82.3	Blck Shear
7	125	SOL - 5/8" SOLID	7.67 1.2	D + 1.6W Normal Wi	i 36	9.94	0	0				77.2	Member

Seismic Section Forces

Structure: CT01725-A-SBA Code: EIA/TIA-222-G

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II



12/14/2021



Page: 16

Load Case: 1.2D + 1.0E					
Dead Load Factor	1.20	Sds 0.192	Ss 0.1800	Fa 1.6000	Ke 0.0000
Seismic Load Factor	1.00	Sd1 0.102	S1 0.0640	Fv 2.4000	Kg 0.0000
Seismic Importance Factor	1.00	SA 0 192	R 3,0000	Vs 2.7686	f1 2.0301

	Elev	Wz				Lateral Fsz
Sect #	(ft)	(lb)	а	b	С	(lb)
1	10.00	4650.2	0.01	0.06	0.03	20.41
2	30.00	4145.0	0.11	0.07	0.04	46.79
3	50.00	3614.5	0.30	0.04	0.01	79.87
4	70.00	5179.7	0.59	-0.05	0.01	178.68
5	90.00	8912.8	0.98	-0.11	0.12	466.36
6	110.00	4641.1	1.46	0.42	0.50	455.86
7	122.50	4887.9	1.82	1.61	1.00	756.98

Load Case: 0.9D + 1.0E					
Dead Load Factor	0.90	Sds 0.192	Ss 0.1800	Fa 1.6000	Ke 0.0000
Seismic Load Factor	1.00	Sd1 0.102	S1 0.0640	Fv 2.4000	Kg 0.0000
Seismic Importance Factor	1.00	SA 0.192	R 3.0000	Vs 2.7686	f1 2.0301

	Elev	Wz				Lateral Fsz
Sect #	(ft)	(lb)	а	b	С	(lb)
1	10.00	4650.2	0.01	0.06	0.03	20.41
2	30.00	4145.0	0.11	0.07	0.04	46.79
3	50.00	3614.5	0.30	0.04	0.01	79.87
4	70.00	5179.7	0.59	-0.05	0.01	178.68
5	90.00	8912.8	0.98	-0.11	0.12	466.36
6	110.00	4641.1	1.46	0.42	0.50	455.86
7	122.50	4887.9	1.82	1.61	1.00	756.98

Support Forces Summary

Structure: CT01725-A-SBA **Code**: EIA/TIA-222-G 12/14/2021

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: ||



Gn:	0.85	ropograpny:	3	truct Clas	SS: II	Page: 17
Load	d Case	Node	FX (kips)	FY (kips)	FZ (kips)	(-) = Uplift (+) = Down
1.2D + 1.6	W Normal Wind	1	0.00	309.05	-26.16	
		1a	9.76	-132.91	-7.26	
		1b	-9.76	-132.91	-7.26	
12D + 16	W 60° Wind	1	-1.40	159.35	-13.13	
1.25 . 1.0	W GO Willia	1a	-12.04	157.73	5.35	
		1b	-20.99	-273.84	-12.10	
1.2D + 1.6	W 90° Wind	1	-1.63	14.43	-0.65	
		1a 1b	-19.77	264.59	10.47	
			-18.59 	-235.79	-9.81 	
0.9D + 1.6	W Normal Wind	1	0.00	304.65	-25.94	
		1a	9.93	-136.11	-7.37	
		1b	-9.93	-136.11	-7.37	
0.9D + 1.6	SW 60° Wind	1	-1.41	155.35	-12.92	
		1a	-11.86	153.75	5.24	
		1b	-21.16	-276.67	-12.20	
0.00 . 1.6	W 90° Wind	1	-1.64	10.83	-0.45	
U.9D + 1.0	ovv 90 vvina	1a	-1.64	260.32	10.35	
		1b	-18.76	-238.72	-9.91	
1.2D + 1.0	Di + 1.0Wi Normal Wind	1	0.00	139.47	-9.35	
		1a	2.26	-3.27	-1.80	
		1b	-2.26	-3.27	-1.80	
1.2D + 1.0	Di + 1.0Wi 60° Wind	1	-0.45	91.87	-5.27	
		1a	-4.77	90.99	2.25	
		1b	-5.98	-49.94	-3.44	
12D + 10	Di + 1.0Wi 90° Wind	1	-0.52	44.31	-1.21	
1.20 1 1.0	DIT 1.0VII 00 VVIII a	1a	-7.27	125.81	3.90	
		1b	-5.17	-37.20	-2.69	
1.2D + 1.0)E	1	0.00	33.38	0.71	
		1a	2.38	4.93	-1.34	
		1b	-2.38	4.93	-1.34	
0.9D + 1.0	E	1	0.00	29.72	0.92	
		1a	2.56	1.35	-1.45	
		1b	-2.56	1.35	-1.45	
1.0D + 1.0	W Normal Wind	1	0.00	82.35	-6.80	
		1a	1.88	-23.16	-1.49	
		1b	-1.88	-23.16	-1.49	
100:10						
1.00 + 1.0	W 60° Wind	1 1a	-0.34 -3.36	46.74 46.35	-3.69 1.55	
		1a 1b	-3.36 -4.61	-57.05	-2.65	
1.0D + 1.0	W 90° Wind	1	-0.40	12.01	-0.68	
		1a	-5.21	71.95	2.78	
		1b	-4.03	-47.93	-2.10	

Leg			Ove	erturning	
Max Uplift:	-276.67	(kips)	Moment:	3189.52	2 (ft-kips)
Max Down:	309.05	(kips)	Total Down:	43.24	4 (kips)
Max Shear:	26.16	(kips)	Total Shear:	40.68	8 (kips)

Analysis Summary

Structure: CT01725-A-SBA **Code:** EIA/TIA-222-G 12/14/2021

Site Name:BloomfieldExposure:BHeight:125.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: II Page: 19



Max Reactions

Leg	Ove	rturning	
Max Uplift: -276.67	(kips) Moment:	3189.52	(ft-kips)
Max Down: 309.05	(kips) Total Down:	43.24	(kips)
Max Shear: 26.16	(kips) Total Shear:	40.68	(kips)

Anchor Bolts

Bolt Size (in.): 1.50 Number Bolts: 8

Yield Strength (Ksi): 36.00 Tensile Strength (Ksi): 58.00

Detail Type: D Length: 1.00

Interaction Ratio: 0.69

Max Usages

Max Leg: 97.6% (1.2D + 1.6W Normal Wind - Sect 2)
Max Diag: 90.1% (1.2D + 1.6W 90° Wind - Sect 5)
Max Horiz: 41.1% (1.2D + 1.6W Normal Wind - Sect 7)

Max Deflection, Twist and Sway

Load Case	Elevation (ft)	Deflection (ft)	Twist (deg)	Sway (deg)
0.9D + 1.0E - Normal To Face	66.75	0.0332	0.0022	0.0619
	79.75	0.0490	0.0029	0.0825
	85.13	0.0567	0.0031	0.0862
	94.88	0.0727	0.0035	0.1011
	99.75	0.0818	0.0040	0.1218
	100.00	0.0823	0.0040	0.1238
	110.13	0.1034	0.0042	0.1289
	125.00	0.1387	-0.0043	0.1383
0.9D + 1.6W 97 mph Wind at 60° From Face	66.75	0.4669	0.1015	0.8246
	79.75	0.6756	0.1385	1.0888
	85.13	0.7755	0.1758	1.0941
	94.88	0.9764	0.2487	1.2512
	99.75	1.0854	0.2882	1.4442
	100.00	1.0918	0.2902	1.4624
	110.13	1.3390	0.5129	1.4876
	125.00	1.7325	0.8266	1.4088
0.9D + 1.6W 97 mph Wind at 90° From Face	66.75	0.4658	-0.0406	0.8213
	79.75	0.6746	-0.0519	1.0766
	85.13	0.7742	-0.0569	1.0926
	94.88	0.9742	-0.0686	1.2484
	99.75	1.0834	-0.0762	1.4239
	100.00	1.0896	-0.0765	1.4394
	110.13	1.3351	-0.0961	1.4591
	125.00	1.7227	-0.1131	0.9675

0.9D + 1.6W 97 mph Wind at Normal To Face	66.75	0.4754	0.0313	0.8392	
	79.75	0.6884	0.0390	1.1136	
	85.13	0.7904	0.0416	1.1167	
	94.88	0.9964	0.0476	1.2802	
	99.75	1.1095	0.0507	1.4836	
	100.00	1.1158	0.0506	1.5029	
	110.13	1.3720	0.0535	1.5323	
	125.00	1.7918	0.0575	2.3261	
1.0D + 1.0W 60 mph Wind at 60° From Face	66.75	0.1117	0.0116	0.1072	
1.0D + 1.0W 60 mph Wind at 60° From Face	79.75	0.1117 0.1617	0.0116	0.1972 0.2616	
	79.75 85.13	0.1857	0.0152	0.2610	
	94.88	0.1657	0.0179	0.2983	
	99.75				
	100.00	0.2601 0.2616	0.0265 0.0266	0.3480 0.3523	
	110.13	0.3208	0.0200	0.3530	
	125.00	0.4151	0.0408	0.3326	
		0.4101			
1.0D + 1.0W 60 mph Wind at 90° From Face	66.75	0.1119	-0.0096	0.1970	
	79.75	0.1619	-0.0123	0.2584	
	85.13	0.1858	-0.0134	0.2620	
	94.88	0.2338	-0.0161	0.2994	
	99.75	0.2599	-0.0179	0.3428	
	100.00	0.2613	-0.0180	0.3462	
	110.13	0.3202	-0.0225	0.3499	
	125.00	0.4131	-0.0265	0.2327	
1.0D + 1.0W 60 mph Wind at Normal To Face	66.75	0.1140	0.0072	0.2007	
'	79.75	0.1650	0.0090	0.2655	
	85.13	0.1894	0.0094	0.2673	
	94.88	0.2387	0.0105	0.3062	
	99.75	0.2653	0.0113	0.3523	
	100.00	0.2669	0.0113	0.3569	
	110.13	0.3281	0.0111	0.3668	
	125.00	0.4275	0.0111	0.5318	
4.2D + 4.0Di + 4.0Wi = 0 mah Wind at 600 From Face			0.0005	0.0700	
1.2D + 1.0Di + 1.0Wi 50 mph Wind at 60° From Face	66.75	0.1531	0.0225	0.2702	
	79.75 85.13	0.2215	0.0302 0.0371	0.3587 0.3576	
	94.88	0.2543 0.3201	0.0571	0.3376	
	99.75	0.3565	0.0509	0.4848	
	100.00	0.3586	0.0589	0.4848	
	110.13	0.4405	0.0389	0.4896	
	125.00	0.5712	0.0967	0.4699	
		0.5712	0.1042		
1.2D + 1.0Di + 1.0Wi 50 mph Wind at 90° From Face	66.75	0.1523	-0.0139	0.2686	
	79.75	0.2204	-0.0178	0.3528	
	85.13	0.2530	-0.0198	0.3573	
	94.88	0.3185	-0.0242	0.4088	
	99.75	0.3544	-0.0271	0.4743	
	100.00	0.3565	-0.0272	0.4789	
	110.13	0.4373	-0.0356	0.4808	
	125.00	0.5647	-0.0429	0.2150	
1.2D + 1.0Di + 1.0Wi 50 mph Wind at Normal From Face	66.75	0.1547	0.0095	0.2745	
	79.75	0.2244	0.0118	0.3611	
	85.13	0.2579	0.0121	0.3680	
	94.88	0.3260	0.0134	0.4234	
	99.75	0.3631	0.0144	0.4846	
	100.00	0.3652	0.0144	0.4915	
	110.13	0.4507	0.0130	0.5156	
	125.00	0.5914	0.0123	0.8556	
1.2D + 1.0E - Normal To Face	66.75	0.0333	0.0022	0.0622	
1.20 F 1.0L - NOITHAL TO FACE	79.75	0.0333	-0.0022	0.0822	
	85.13	0.0569	-0.0029	0.0826	
	94.88	0.0730	-0.0031	0.1016	
	99.75	0.0730	-0.0030	0.1010	
	100.00	0.0826	-0.0040	0.1220	
	110.13	0.1038	-0.0040	0.1295	
	125.00	0.1392	-0.0042	0.1233	

1.2D + 1.6W 97 mph Wind at 60° From Face	66.75	0.4684	0.1020	0.8279	
	79.75	0.6780	0.1391	1.0936	
	85.13	0.7784	0.1767	1.0989	
	94.88	0.9802	0.2500	1.2570	
	99.75	1.0897	0.2897	1.4517	
	100.00	1.0961	0.2917	1.4700	
	110.13	1.3445	0.5155	1.4949	
	125.00	1.7400	0.8309	1.4164	
1.2D + 1.6W 97 mph Wind at 90° From Face	66.75	0.4673	-0.0407	0.8246	
·	79.75	0.6770	-0.0522	1.0811	
	85.13	0.7770	-0.0572	1.0975	
	94.88	0.9779	-0.0689	1.2542	
	99.75	1.0876	-0.0766	1.4303	
	100.00	1.0939	-0.0769	1.4460	
	110.13	1.3406	-0.0965	1.4664	
	125.00	1.7302	-0.1137	0.9755	
1.2D + 1.6W 97 mph Wind at Normal To Face	66.75	0.4771	0.0315	0.8426	
·	79.75	0.6910	0.0392	1.1182	
	85.13	0.7934	0.0418	1.1218	
	94.88	1.0004	0.0478	1.2862	
	99.75	1.1139	0.0510	1.4902	
	100.00	1.1203	0.0509	1.5097	
	110.13	1.3777	0.0539	1.5401	
	125.00	1.7996	0.0579	2.3354	



Mat Foundation Design for Self Supporting Tower							
Site Name:		Structure Height (Ft.):	125				
Site Nmber:	CT01725-A-SBA	Engineer Name:	J. Tibbetts				
Engr. Number:	120504	Engineer Login ID:					

Foundation Info Obtained from: Drawings/Calculations **Analysis or Design? Analysis Number of Tower Legs:** 3 Legs **Base Reactions (Factored):** 0.00 (1). Individual Leg: 276.7 Axial Load (Kips): 309.0 Uplift Force (Kips): Shear Force (Kips): 26.2 (2). Tower Base: 40.7 Total Vertical Load (Kips): 43.2 Total Shear Force (Kips): 0 0 4.3' 3189.5 Moment (Kips-ft): **Foundation Geometries:** 27 Leg distance (Center-to-Center ft.): 12.5 Mods required -Yes/No ?: No Diameter of Pier (ft.): Round 3.0 Pier Height A. G. (ft.): 0.00 Tower center to mat center (ft): 1.01 Depth of Base BG (ft.): 4.3 4.3 Length of Pad (ft.): 29 Width of Pad (ft.): 29 Thickness of Pad (ft): 4.30 8 27 8 3.608 9.882 14.5 **Material Properties and Reabr Info:** Mat Center 29000 Concrete Strength (psi): 3000 Steel Elastic Modulus: ksi (W) 1.01 Vertical bar yield (ksi) 60 Tie steel yield (ksi): 29' 12.5 Vertical Rebar Size #: Tie / Stirrup Size #: 4 Qty. of Vertical Rebars: Tie Spacing (in): 12.0 Pad Rebar Yield (Ksi): Pad Steel Rebar Size (#): 60 8 8.29 7.217 Unit Weight of Concrete: Concrete Cover (in.): 150.0 pcf Rebar at the bottom of the concrete pad: 10.825 Qty. of Rebar in Pad (L): 27 Qty. of Rebar in Pad (W): 27 29' Rebar at the top of the concrete pad: Qty. of Rebar in Pad (L): 27 Qty. of Rebar in Pad (W): 27 **Soil Design Parameters:** Soil Unit Weight (pcf): 100.0 Soil Buoyant Weight: 50.0 Pcf Water Table B.G.S. (ft): 6.0 Unit Weight of Water: 62.4 pcf Ultimate Bearing Pressure (psf): 6000 Consider ties in concrete shear strength: Yes Consider Soil Lateral Resistance? Yes Enter soil C (psf) or Phi (deg.): 30.0 Deg. (W) Mat Center Depth to ignor lateral resistance 1.0 Ft. 29'

Allowable overstress %: 5.00% **TES Engr. Number:** 120504 Page 2/2 Date: 12/14/2021

	7.1	for				1 :
	у т					

Foundation Analysis and Design: Uplift Strength Reduction Factor:	0.75	Compr	ession Strength Reduction Factor:	0.75		
Total Dry Soil Volume (cu. Ft.):	0.08	Total D	Ory Soil Weight (Kips):	0.01		
Total Buoyant Soil Volume (cu. Ft.):	0.00	Total E	Buoyant Soil Weight (Kips):	0.00		
Total Effective Soil Weight (Kips):	0.01	Weigh	t from the Concrete Block at Top (K):	0.00		
Total Dry Concrete Volume (cu. Ft.):	3616.32	Total D	Dry Concrete Weight (Kips):	542.45		
Total Buoyant Concrete Volume (cu. Ft.):	0.00	Total E	Buoyant Concrete Weight (Kips):	0.00		
Total Effective Concrete Weight (Kips):	542.45	Total \	/ertical Load on Base (Kips):	585.69		
Check Soil Capacities:					Load/ Capacity Ratio	
Calculated Maxium Net Soil Pressure under the base (psf):	1708.90	<	Allowable Factored Soil Bearing (psf):	4500	0.38	OK!
Allowable Foundation Overturning Resistance (kips-ft.):	7706.0	>	Design Factored Momont (kips-ft):	3408	0.44	OK!
Factor of Safety Against Overturning (O. R. Moment/Design Moment):	2.26	OK!				
Check the capacities of Reinforceing Concrete:						
Strength reduction factor (Flexure and axial tension):	0.90	Streng	th reduction factor (Shear):	0.75		
Strength reduction factor (Axial compresion):	0.65	Wind I	oad Factor on Concrete Design:	1.00		
(1) Concrete Pier:					Load/ Capacity Ratio	
Vertical Steel Rebar Area (sq. in./each):	#N/A		Tie / Stirrup Area (sq. in./each):	0.20		
Calculated Moment Capacity (Mn,Kips-Ft):	#N/A	#N/A	Design Factored Moment (Mu, Kips-Ft)	0.1	#N/A	###
Calculated Shear Capacity (Kips):	77.9	>	Design Factored Shear (Kips):	26.2	0.34	OK!
Calculated Tension Capacity (Tn, Kips):	#N/A	#N/A	Design Factored Tension (Tu Kips):	276.7	#N/A	###
Calculated Compression Capacity (Pn, Kips):	#N/A	#N/A	Design Factored Axial Load (Pu Kips):	309.0	#N/A	###
Moment & Tension Strength Combination:	#N/A	#N/A	Check Tie Spacing (Design/Req'd):	#DIV/0!		
Pier Reinforcement Ratio:	#N/A		#N/A			
(2).Concrete Pad:						
One-Way Design Shear Capacity (L or W Direction, Kips):	1375.2	>	One-Way Factored Shear (L/W-Dir Kips	261.3	0.19	OK!
One-Way Design Shear Capacity (Diagonal Dir., Kips):	1226.1	>	One-Way Factored Shear (Dia. Dir, Kips	280.0	0.23	OK!
Lower Steel Pad Reinforcement Ratio (L or W-Direct.):	0.0013		Lower Steel Reinf. Ratio (Dia. Dir.):	0.0011		
Lower Steel Pad Moment Capacity (L or W-Dir. Kips-ft):	4547.5	>	Moment at Bottom (L-Direct. K-Ft):	1742.8	0.38	OK!
Lower Steel Pad Moment Capacity (Dia. Direction,K-ft):	4556.8	>	Moment at Bottom (Dia. Dir. K-Ft):	1694.2	0.37	OK!
Upper Steel Pad Reinforcement Ratio (L or W -Direction):	0.0013		Upper Steel Reinf. Ratio (Dia. Dir.):	0.0011		
Upper Steel Pad Moment Capacity (L or W-Dir., Kips-ft):	4547.5	>	Moment at the top (L-Dir Kips-Ft):	743.6	0.16	OK!
Upper Steel Pad Moment Capacity (Dia. Direction, K-ft):	4556.8	>	Moment at the top (Dia. Dir., K-Ft):	556.1	0.12	OK!
Punching Failure Capacity (Kips):	2088.1	>	Punch. Failure Factored Shear (K):	309.0	0.15	OK!

EXHIBIT 9

Antenna Mount Analysis

December 21, 2021

Sherri Knapik SBA Network Services. LLC. 134 Flanders Road, Suite 125 Westborough, MA 01581 (508) 251-0720 x 3805



B+T Group 1717 S. Boulder, Suite 300 Tulsa, OK 74119 (918) 587-4630 towersupport@btgrp.com

Subject: **Appurtenance Mount Analysis Report**

Carrier Designation: Dish Wireless Co-Locate

> Site Number: BOBDL00022B

SBA Network Services Designation: Site Number: CT01725-A

> Site Name: Bloomfield **Application Number:** 176995, v1

Engineering Firm Designation: Project Number: 101023.006.01

Site Data: 1021 Blue Hills Avenue, Bloomfield, CT, 06002, Hartford County

Latitude 41.82012°, Longitude -72.69651°

Self-Support Tower 8' Sector Mount

Dear Mr. Knapik,

B+T Group is pleased to submit this "Appurtenance Mount Analysis Report" to determine the structural integrity of the antenna mount on the above-mentioned structure.

The purpose of the analysis is to determine acceptability of the mount's stress level. Based on our analysis we have determined the stress level for the mount under the following load case to be:

Proposed Equipment Note: See Table 1 for the final loading configuration **Sufficient Capacity** (Passing at 52.1%)

This analysis utilizes an ultimate 3-second gust wind speed of 117 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

We appreciate the opportunity of providing our continuing professional services to you and SBA Network Services, LLC. If you have any questions or need further assistance on this or any other projects, please give us a call.

Mount structural analysis prepared by: Suman Rana, P.E.

Respectfully submitted by: B&T Engineering, Inc. COA: PEC.0001564 Expires: 02/10/2022 Mo. 23924

Chad E. Tuttle, P.E.

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Information

Table 2 - Documents Provided

3) ANALYSIS PROCEDURE

- 3.1) Analysis Method
- 3.2) Assumptions

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

5) RECOMMENDATIONS

6) APPENDIX A

RISA-3D Output

7) APPENDIX B

Additional Calculations

1) INTRODUCTION

The mount consists of Commscope sector mount (Part #MTC3975083) at 87 ft., attached to self-support tower at 1021 Blue Hills Avenue, Bloomfield, CT, 06002, Hartford County. The proposed antenna loading information was obtained from SBA Network Services, LLC. All information provided to us was assumed accurate and complete.

2) ANALYSIS CRITERIA

The structural analysis was performed for this mount in accordance with the ANSI/TIA-222-H-2017 Structural Standard for Antenna Supporting Structures and Antennas and Small Wind Turbine Support Structures using a 3-second gust wind speed of 117 mph with no ice and 50 mph with 1.5 inch escalated ice thickness. Exposure Category B, Topographic Category 1 and Risk Category II were used in this analysis. In addition, the sector mount has been analyzed for various live loading conditions consisting of a 250-lb man live load applied individually at the midpoint and cantilevered ends of horizontal members as well as a 500-pound man live load applied individually at mount pipe locations using a 3-second gust of 30 mph. The mount was analyzed under 30° increments in the wind direction. The analyzed loading is detailed in Table 1.

Table 1 - Proposed Equipment Information

Loading	RAD Center Elev. (ft.)	Position	osition Qty. Description		Note
			3	JMA Wireless MX08FRO665-21	1
Dropood	07	1	3	Fujitsu TA08025-B605	2
Proposed	87		3	Fujitsu TA08025-B604	
			1	Raycap RDIDC-9181-PF-48	3

Note:

- (1) Proposed Antenna to be installed on the Mount Pipe.
- (2) Proposed Equipment to be installed directly behind the Antenna.
- (3) Proposed Equipment to be installed on the Mount.

Table 2 - Documents Provided

Documents	Remarks	Reference	Source	
Collo App	Proposed Loading	Date: 10/22/2021	SBA Network Services, LLC	
RFDS	Proposed Loading	Date: 10/28/2021	SDA Network Services, ELC.	

3) ANALYSIS PROCEDURE

3.1) Analysis Method

RISA-3D (Version 19.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the mount and calculate member stresses and deflections for various loading cases. Selected output from the analysis is included in Appendix A.

Manufacturers drawing were used to create the model.

3.2) Assumptions

- 1. The mount was built in accordance with the manufacturer's specifications.
- 2. The mount has been maintained in accordance with the manufacturer's specifications and is free of damage.
- 3. The configuration of antennas and other appurtenances are as specified in Table 1.
- 4. All mount components have been assumed to be in sufficient condition to carry their full design capacity for the analysis.
- 5. Mount areas and weights are determined from field measurements, standard material properties, and/or manufacturer product data.

- 6. Serviceability with respect to antenna twist, tilt, roll or lateral translation is not checked and is left to the carrier or tower owner to ensure conformance.
- 7. All prior structural modifications, if any are assumed to be correctly installed and fully effective.
- 8. All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 9. The following material grades were assumed (Unless Noted Otherwise):

a) Connection Bolts : ASTM A325

b) Steel Pipe : ASTM A53 (GR. 35) c) HSS (Round) : ASTM 500 (GR. B-42) d) HSS (Rectangular) : ASTM 500 (GR. B-46) : ASTM A36 (GR. 36) e) Channel f) Steel Solid Rod : ASTM A36 (GR. 36) g) Steel Plate : ASTM A36 (GR. 36) h) Steel Angle : ASTM A36 (GR. 36) i) UNISTRUT : ASTM A570 (GR. 33)

This analysis may be affected if any assumptions are not valid or have been made in error. B+T Group should be notified to determine the effect on the structural integrity of the antenna mounting system.

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

Notes	Notes Component		% Capacity	Pass / Fail
-	Face Horizontals	87	10.2	Pass
-	Support Arm	87	29.5	Pass
-	Diagonals	87	30.9	Pass
-	Connection Plates	87	24.3	Pass
-	Verticals	87	52.1	Pass
-	Tieback	87	5.6	Pass
-	Mount Pipes	87	15.9	Pass


5) RECOMMENDATIONS

The CommScope sector mount, (Part # MTC3975083) has sufficient capacity to carry the proposed loads and is in compliance with the ANSI/TIA-222-H standard for the proposed loading. (Refer to the RISA output for the specific members).


APPENDIX A


(RISA-3D Output)







B+T Group	CT01725-A - Bloomfield	SP1
SP		Dec 19, 2021
101023.006.01		101023_006_01_Bloomfield











Company : B+T Group
Designer : SP
Job Number : 101023.006.01
Model Name : CT01725-A - Bloomfield

12/19/2021 4:02:21 PM

Checked By : ____

Node Coordinates

	loac ocoramates				
	Label	X [ft]	Y [ft]	Z [ft]	Detach From Diaphragm
1	1	-4	-2.354167	2.796875	
2	2	4	-2.354167	2.796875	
3	3	-4	0.145833	2.796875	
4	4	4	0.145833	2.796875	
5	5	0.467947	0	0.771833	
6	6	0.385368	0	0.677994	
7	7	2.091999	0.	2.61733	
8	8	2.00942	0.	2.523491	
9	9	2.332579	0.	2.890714	
10	10	2.25	0.145833	2.796875	
11	11	2.25	0.	2.796875	
12	12	0.	0	0.24008	
13	13	-0.467947	0	0.771833	
14	14	-0.385368	0	0.677994	
15	15	-2.091999	0.	2.61733	
16	16	-2.00942	0.	2.523491	
17	17	-2.332579	0.	2.890714	
18	18	-2.25	0.145833	2.796875	
19	19	-2.25	0.	2.796875	
20	20	0.467947	-2.5	0.771833	
21	21	0.385368	-2.5	0.677994	
22	22	2.091999	-2.5	2.61733	
23	23	2.00942	-2.5	2.523491	
24	24	2.332579	-2.5	2.890714	
25	25	2.25	-2.354167	2.796875	
26	26	2.25	-2.5	2.796875	
27	27	0.	-2.5	0.24008	
28	28	-0.467947	-2.5	0.771833	
29	29	-0.385368	-2.5	0.677994	
30	30	-2.091999	-2.5	2.61733	
31	31	-2.00942	-2.5	2.523491	
32	32	-2.332579	-2.5	2.890714	
33	33	-2.25	-2.354167	2.796875	
34	34	-2.25	-2.5	2.796875	
35	35	0.430236	0	0.72898	
36	36	2.047131	-2.5	2.566344	
37	37	2.047131	0.	2.566344	
38	38	0.430236	-2.5	0.72898	
39	39	-0.430236	0	0.72898	
40	40	-2.047131	-2.5	2.566344	
41	41	-2.047131	0.	2.566344	
42	42	-0.430236	-2.5	0.72898	
43	43	0.	0.145833	2.796875	
44	44	0.	0.145833	3.078125	
45	45	0.	-2.354167	2.796875	
46	46	0.	-2.354167	3.078125	
47	47	0.	2.895833	3.078125	
48	48	0.	-5.104167	3.078125	
49	49	3.666667	0.145833	2.796875	
50	50	3.666667	0.145833	3.078125	
51	51	3.666667	-2.354167	2.796875	



Checked By : ___

Node Coordinates (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Detach From Diaphragm
52	52	3.666667	-2.354167	3.078125	
53	53	3.666667	2.895833	3.078125	
54	54	3.666667	-5.104167	3.078125	
55	55	-3.666667	0.145833	2.796875	
56	56	-3.666667	0.145833	3.078125	
57	57	-3.666667	-2.354167	2.796875	
58	58	-3.666667	-2.354167	3.078125	
59	59	-3.666667	2.895833	3.078125	
60	60	-3.666667	-5.104167	3.078125	
61	61	0	0	0	
62	63	-2.75	0.145833	2.796875	
63	64	-3.118	0	-5.400534	

Node Boundary Conditions

	Node Label	X [k/in]	Y [k/in]	Z [k/in]
1	12	Reaction	Reaction	Reaction
2	27	Reaction	Reaction	Reaction
3	64	Reaction	Reaction	Reaction

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm. Coeff. [1e ⁵ °F ⁻¹]	Density [k/ft³]	Yield [ksi]	Ry	Fu [ksi]	Rt
1	A992	29000	11154	0.3	0.65	0.49	50	1.1	65	1.1
2	A36 Gr.36	29000	11154	0.3	0.65	0.49	36	1.5	58	1.2
3	A572 Gr.50	29000	11154	0.3	0.65	0.49	50	1.1	65	1.1
4	A500 Gr.B RND	29000	11154	0.3	0.65	0.527	42	1.4	58	1.3
5	A500 Gr.B Rect	29000	11154	0.3	0.65	0.527	46	1.4	58	1.3
6	A53 Gr.B	29000	11154	0.3	0.65	0.49	35	1.6	60	1.2
7	A1085	29000	11154	0.3	0.65	0.49	50	1.4	65	1.3
8	A529 Gr.50	29000	11154	0.3	0.65	0.49	50	1.1	65	1.1
9	A500 Gr.42	29000	11154	0.3	0.65	0.49	42	1.4	58	1.3
10	A500 Gr.46	29000	11154	0.3	0.65	0.49	46	1.4	58	1.3
11	A500 Gr.C	29000	11154	0.3	0.65	0.49	46	1.4	62	1.3

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rule	Area [in²]	lyy [in⁴]	Izz [in⁴]	J [in⁴]
1	MF-H1	PIPE_2.88x0.203	Beam	Pipe	A500 Gr.C	Typical	1.704	1.53	1.53	3.059
2	MF- SA1	1.9" ODx0.12"	Beam	Pipe	A500 Gr.B RND	Typical	0.671	0.267	0.267	0.534
3	MF-D1	1/2" SR	VBrace	BAR	A529 Gr.50	Typical	0.196	0.003	0.003	0.006
4	MF-CP1	PL5/8x3.5	Beam	RECT	A572 Gr.50	Typical	2.205	0.073	2.251	0.259
5	MF-V1	0.63" SR	Column	BAR	A529 Gr.50	Typical	0.312	0.008	0.008	0.015
6	MF-CP2	PL5/8x4.25	Beam	RECT	A572 Gr.50	Typical	2.656	0.086	3.998	0.314
7	Tieback	Pipe2.38X0.12	Beam	Pipe	A500 Gr.C	Typical	0.852	0.545	0.545	1.091
8	MF-P1	Pipe2.88x.12	Column	Pipe	A500 Gr.C	Typical	1.04	0.993	0.993	1.985

Member Primary Data

	Label	I Node	J Node	Rotate(deg)	Section/Shape	Туре	Design List	Material	Design Rule
1	1	1	2		MF-H1	Beam	Pipe	A500 Gr.C	Typical
2	2	3	4		MF-H1	Beam	Pipe	A500 Gr.C	Typical
3	3	12	5	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical



Company : B+T Group
Designer : SP
Job Number : 101023.006.01
Model Name : CT01725-A - Bloomfield

12/19/2021 4:02:21 PM Checked By : ___

Member Primary Data (Continued)

	Label	I Node	J Node	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rule
4	4	6	7		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
5	5	8	9	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
6	6	10	11	90	RIGID	None	None	RIGID	Typical
7	7	12	13	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical
8	8	14	15		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
9	9	16	17	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
10	10	18	19	90	RIGID	None	None	RIGID	Typical
11	11	27	20	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical
12	12	21	22		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
13	13	23	24	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
14	14	25	26	90	RIGID	None	None	RIGID	Typical
15	15	27	28	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical
16	16	29	30		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
17	17	31	32	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
18	18	33	34	90	RIGID	None	None	RIGID	Typical
19	19	37	36		MF-V1	Column	BAR	A529 Gr.50	Typical
20	20	35	38		MF-V1	Column	BAR	A529 Gr.50	Typical
21	21	35	36		MF-D1	VBrace	BAR	A529 Gr.50	Typical
22	22	37	38		MF-D1	VBrace	BAR	A529 Gr.50	Typical
23	23	41	40		MF-V1	Column	BAR	A529 Gr.50	Typical
24	24	39	42		MF-V1	Column	BAR	A529 Gr.50	Typical
25	25	39	40		MF-D1	VBrace	BAR	A529 Gr.50	Typical
26	26	41	42		MF-D1	VBrace	BAR	A529 Gr.50	Typical
27	27	43	44	90	RIGID	None	None	RIGID	Typical
28	28	45	46	90	RIGID	None	None	RIGID	Typical
29	29	47	48		MF-P1	Column	Pipe	A500 Gr.C	Typical
30	30	49	50	90	RIGID	None	None	RIGID	Typical
31	31	51	52	90	RIGID	None	None	RIGID	Typical
32	32	53	54		MF-P1	Column	Pipe	A500 Gr.C	Typical
33	33	55	56	90	RIGID	None	None	RIGID	Typical
34	34	57	58	90	RIGID	None	None	RIGID	Typical
35	35	59	60		MF-P1	Column	Pipe	A500 Gr.C	Typical
36	41	63	64		Tieback	Beam	Pipe	A500 Gr.C	Typical

Member Advanced Data

	Label	l Release	T/C Only	Physical	Deflection Ratio Options	Seismic DR
1	1			Yes		None
2	2			Yes	Default	None
3	3			Yes		None
4	4			Yes		None
5	5			Yes		None
6	6	0000X0		Yes	** NA **	None
7	7			Yes		None
8	8			Yes		None
9	9			Yes		None
10	10	0000X0		Yes	** NA **	None
11	11			Yes		None
12	12			Yes		None
13	13			Yes		None
14	14	0000X0		Yes	** NA **	None
15	15			Yes		None



Company : B+T Group
Designer : SP
Job Number : 101023.006.01
Model Name : CT01725-A - Bloomfield

12/19/2021 4:02:21 PM Checked By : ____

Member Advanced Data (Continued)

	Label	I Release	T/C Only	Physical	Deflection Ratio Options	Seismic DR
16	16			Yes		None
17	17			Yes		None
18	18	0000X0		Yes	** NA **	None
19	19			Yes	** NA **	None
20	20			Yes	** NA **	None
21	21			Yes	** NA **	None
22 23 24 25 26 27 28 29	22		Euler Buckling	Yes	** NA **	None
23	23			Yes	** NA **	None
24	24			Yes	** NA **	None
25	25			Yes	** NA **	None
26	26		Euler Buckling	Yes	** NA **	None
27	27			Yes	** NA **	None
28	28			Yes	** NA **	None
29	29			Yes	** NA **	None
30	30			Yes	** NA **	None
31	31			Yes	** NA **	None
32	32			Yes	** NA **	None
32 33 34	33			Yes	** NA **	None
34	34			Yes	** NA **	None
35 36	35			Yes	** NA **	None
36	41	BenPIN		Yes	Default	None

Hot Rolled Steel Design Parameters

	Label	Shape	Length [ft]	Lcomp top [ft]	Function
1	1	MF-H1	8	Lbyy	Lateral
2	2	MF-H1	8	Lbyy	Lateral
3	3	MF-CP1	0.708	Lbyy	Lateral
4	4	MF- SA1	2.583	Lbyy	Lateral
5	5	MF-CP2	0.489	Lbyy	Lateral
6	7	MF-CP1	0.708	Lbyy	Lateral
7	8	MF- SA1	2.583	Lbyy	Lateral
8	9	MF-CP2	0.489	Lbyy	Lateral
9	11	MF-CP1	0.708	Lbyy	Lateral
10	12	MF- SA1	2.583	Lbyy	Lateral
11	13	MF-CP2	0.489	Lbyy	Lateral
12	15	MF-CP1	0.708	Lbyy	Lateral
13	16	MF- SA1	2.583	Lbyy	Lateral
14	17	MF-CP2	0.489	Lbyy	Lateral
15	19	MF-V1	2.5	Lbyy	Lateral
16	20	MF-V1	2.5	Lbyy	Lateral
17	21	MF-D1	3.499	Lbyy	Lateral
18	22	MF-D1	3.499	Lbyy	Lateral
19	23	MF-V1	2.5	Lbyy	Lateral
20	24	MF-V1	2.5	Lbyy	Lateral
21	25	MF-D1	3.499	Lbyy	Lateral
22	26	MF-D1	3.499	Lbyy	Lateral
23	29	MF-P1	8	Lbyy	Lateral
24	32	MF-P1	8	Lbyy	Lateral
25	35	MF-P1	8	Lbyy	Lateral
26	41	Tieback	8.207	Lbyy	Lateral



Checked By : ___

Member Point Loads (BLC 1 : Dead)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Υ	-0.032	%15
2	32	Y	-0.032	%85
3	32	Υ	-0.075	%20
4	32	Υ	-0.064	%50
5	32	Υ	0	0
6	8	Υ	-0.022	%50
7	8	Y	0	0
8	8	Υ	0	0
9	8	Y	0	0
10	8	Υ	0	0

Member Point Loads (BLC 2: 0 Wind - No Ice)

	Member Label	Direction	Magnitude [k, k-ft] -0.126	Location [(ft, %)]
1	32	Z	-0.126	%15
2	32	Z	-0.126	%85
3	32	Z	-0.056	%20
4	32	Z	-0.056	%50
5	32	Z	0	0
6	8	Z	-0.057	%50
7	8	Z	0	0
8	8	Z	0	0
9	8	Z	0	0
10	8	Z	0	0

Member Point Loads (BLC 3: 90 Wind - No Ice)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	X	-0.051	%15
2	32	X	-0.051	%85
3	32	X	-0.034	%20
4	32	X	-0.029	%50
5	32	X	0	0
6	8	X	-0.032	%50
7	8	X	0	0
8	8	X	0	0
9	8	X	0	0
10	8	X	0	0

Member Point Loads (BLC 4: 0 Wind - Ice)

	Member Label	Direction	Magnitude [k, k-ft] -0.028	Location [(ft, %)]
1	32	Z	-0.028	%15
2	32	Z	-0.028	%85
3	32	Z	-0.01	%20
4	32	Z	-0.01	%50
5	32	Z	0	0
6	8	Z	-0.01	%50
7	8	Z	0	0
8	8	Z	0	0
9	8	Z	0	0
10	8	Z	0	0



12/19/2021 4:02:21 PM Checked By : ___

Member Point Loads (BLC 5 : 90 Wind - Ice)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	X	-0.013	%15
2	32	X	-0.013	%85
3	32	X	-0.006	%20
4	32	X	-0.005	%50
5	32	X	0	0
6	8	X	-0.006	%50
7	8	X	0	0
8	8	X	0	0
9	8	X	0	0
10	8	X	0	0

Member Point Loads (BLC 6 : 0 Wind - Service)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Z	-0.008	%15
2	32	Z	-0.008	%85
3	32	Z	-0.004	%20
4	32	Z	-0.004	%50
5	32	Z	0	0
6	8	Z	-0.004	%50
7	8	Z	0	0
8	8	Z	0	0
9	8	Z	0	0
10	8	Z	0	0

Member Point Loads (BLC 7: 90 Wind - Service)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	X	-0.003	%15
2	32	X	-0.003	%85
3	32	X	-0.002	%20
4	32	Х	-0.002	%50
5	32	X	0	0
6	8	X	-0.002	%50
7	8	X	0	0
8	8	X	0	0
9	8	X	0	0
10	8	X	0	0

Member Point Loads (BLC 8 : Ice)

	Member Label	Direction	Magnitude [k, k-ft] -0.164	Location [(ft, %)]
1	32	Υ	-0.164	%15
2	32	Y	-0.164	%85
3	32	Υ	-0.051	%20
4	32	Y	-0.049	%50
5	32	Υ	0	0
6	8	Y	-0.051	%50
7	8	Υ	0	0
8	8	Υ	0	0
9	8	Y	0	0
10	8	Y	0	0



Checked By:___

Member Point Loads (L	BLC 9 : 0 Seismic)
-----------------------	--------------------

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Z	-0.011	%15
2	32	Z	-0.011	%85
3	32	Z	-0.013	%20
4	32	Z	-0.011	%50
5	32	Z	0	0
6	8	Z	-0.004	%50
7	8	Z	0	0
8	8	Z	0	0
9	8	Z	0	0
10	8	Z	0	0

Member Point Loads (BLC 10 : 90 Seismic)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	X	-0.011	%15
2	32	X	-0.011	%85
3	32	X	-0.013	%20
4	32	X	-0.011	%50
5	32	X	0	0
6	8	X	-0.004	%50
7	8	X	0	0
8	8	X	0	0
9	8	X	0	0
10	8	X	0	0

Member Point Loads (BLC 15 : Maint LL 1)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	16	Υ	-0.25	%50

Member Point Loads (BLC 16 : Maint LL 2)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	8	Υ	-0.25	%50

Member Point Loads (BLC 17 : Maint LL 3)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	12	Υ	-0.25	%50

Member Point Loads (BLC 18 : Maint LL 4)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	4	Υ	-0.25	%50

Member Point Loads (BLC 19 : Maint LL 5)

	Member Label	Direction	Magnitude [k_k-ft]	Location [(ft %)]
1	1	Y	-0.25	%95

Member Point Loads (BLC 20 : Maint LL 6)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	2	Y	-0.25	%95



Checked By : ____

Member Distributed Loads (BLC 2: 0 Wind - No Ice)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Z	-0.008	-0.008	0	%100
2	2	Ζ	-0.008	-0.008	0	%100
3	3	Z	-0.002	-0.002	0	%100
4	4	Ζ	-0.005	-0.005	0	%100
5	5	Ζ	-0.002	-0.002	0	%100
6	7	Z	-0.002	-0.002	0	%100
7	8	Z	-0.005	-0.005	0	%100
8	9	Z	-0.002	-0.002	0	%100
9	11	Ζ	-0.002	-0.002	0	%100
10	12	Z	-0.005	-0.005	0	%100
11	13	Z	-0.002	-0.002	0	%100
12	15	Z	-0.002	-0.002	0	%100
13	16	Z	-0.005	-0.005	0	%100
14	17	Z	-0.002	-0.002	0	%100
15	19	Z	-0.002	-0.002	0	%100
16	20	Z	-0.002	-0.002	0	%100
17	21	Z	-0.001	-0.001	0	%100
18	22	Z	-0.001	-0.001	0	%100
19	23	Z	-0.002	-0.002	0	%100
20	24	Z	-0.002	-0.002	0	%100
21	25	Z	-0.001	-0.001	0	%100
22	26	Ζ	-0.001	-0.001	0	%100
23	29	Z	-0.008	-0.008	0	%100
24	32	Z	-0.008	-0.008	0	%100
25	35	Z	-0.008	-0.008	0	%100
26	41	Z	-0.007	-0.007	0	%100

Member Distributed Loads (BLC 3 : 90 Wind - No Ice)

	Member Label Direction Start Magnitude [k/ft, F, ksf, k-ft/ft] End Magnitude [k/ft, F, ksf, k-ft/ft] Start Location [(ft, %)] End Location [(ft, %)]								
1	1	Х	-0.008	-0.008	0	%100			
2	2	Х	-0.008	-0.008	0	%100			
3	3	X	-0.002	-0.002	0	%100			
4	4	X	-0.005	-0.005	0	%100			
5	5	X	-0.002	-0.002	0	%100			
6	7	X	-0.002	-0.002	0	%100			
7	8	X	-0.005	-0.005	0	%100			
8	9	X	-0.002	-0.002	0	%100			
9	11	Х	-0.002	-0.002	0	%100			
10	12	X	-0.005	-0.005	0	%100			
11	13	X	-0.002	-0.002	0	%100			
12	15	X	-0.002	-0.002	0	%100			
13		X	-0.005	-0.005	0	%100			
14	17	X	-0.002	-0.002	0	%100			
15	19	X	-0.002	-0.002	0	%100			
16	20	X	-0.002	-0.002	0	%100			
17	21	X	-0.001	-0.001	0	%100			
18	22	X	-0.001	-0.001	0	%100			
19	23	X	-0.002	-0.002	0	%100			
20	24	X	-0.002	-0.002	0	%100			
21	25	X	-0.001	-0.001	0	%100			
22	26	X	-0.001	-0.001	0	%100			



12/19/2021 4:02:21 PM Checked By : ___

Member Distributed Loads (BLC 3 : 90 Wind - No Ice) (Continued)

		Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
23	29	Х	-0.008	-0.008	0	%100
24	32	X	-0.008	-0.008	0	%100
25	35	Х	-0.008	-0.008	0	%100
26	41	Х	-0.007	-0.007	0	%100

Member Distributed Loads (BLC 4: 0 Wind - Ice)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Z	-0.002	-0.002	0	%100
2	2	Z	-0.002	-0.002	0	%100
3	3	Z	-0.004	-0.004	0	%100
4	4	Z	-0.002	-0.002	0	%100
5	5	Z	-0.004	-0.004	0	%100
6	7	Z	-0.004	-0.004	0	%100
7	8	Z	-0.002	-0.002	0	%100
8	9	Z	-0.004	-0.004	0	%100
9	11	Z	-0.004	-0.004	0	%100
10	12	Z	-0.002	-0.002	0	%100
11	13	Z	-0.004	-0.004	0	%100
12	15	Z	-0.004	-0.004	0	%100
13	16	Z	-0.002	-0.002	0	%100
14	17	Z	-0.004	-0.004	0	%100
15	19	Z	-0.002	-0.002	0	%100
16	20	Z	-0.002	-0.002	0	%100
17	21	Z	-0.002	-0.002	0	%100
18	22	Z	-0.002	-0.002	0	%100
19	23	Z	-0.002	-0.002	0	%100
20	24	Z	-0.002	-0.002	0	%100
21	25	Z	-0.002	-0.002	0	%100
22	26	Z	-0.002	-0.002	0	%100
23	29	Z	-0.002	-0.002	0	%100
24	32	Z	-0.002	-0.002	0	%100
25	35	Z	-0.002	-0.002	0	%100
26	41	Z	-0.002	-0.002	0	%100

Member Distributed Loads (BLC 5 : 90 Wind - Ice)

	Member Label Direction Start Magnitude [k/ft, F, ksf, k-ft/ft] End Magnitude [k/ft, F, ksf, k-ft/ft] Start Location [(ft, %)] End Location [(ft, %)]								
1	1	Χ	-0.002	-0.002	0	%100			
2	2	Χ	-0.002	-0.002	0	%100			
3	3	X	-0.004	-0.004	0	%100			
4	4	Χ	-0.002	-0.002	0	%100			
5	5	Χ	-0.004	-0.004	0	%100			
6	7	X	-0.004	-0.004	0	%100			
7	8	Χ	-0.002	-0.002	0	%100			
8	9	Χ	-0.004	-0.004	0	%100			
9	11	Χ	-0.004	-0.004	0	%100			
10	12	Χ	-0.002	-0.002	0	%100			
11	13	X	-0.004	-0.004	0	%100			
12	15	Χ	-0.004	-0.004	0	%100			
13	16	X	-0.002	-0.002	0	%100			
14	17	Х	-0.004	-0.004	0	%100			
15	19	X	-0.002	-0.002	0	%100			



12/19/2021 4:02:21 PM Checked By : ___

Member Distributed Loads (BLC 5 : 90 Wind - Ice) (Continued)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
15	19	Х	-0.002	-0.002	0	%100
16	20	Х	-0.002	-0.002	0	%100
17	21	Х	-0.002	-0.002	0	%100
18	22	Х	-0.002	-0.002	0	%100
19	23	Х	-0.002	-0.002	0	%100
20	24	Х	-0.002	-0.002	0	%100
21	25	Х	-0.002	-0.002	0	%100
22	26	Х	-0.002	-0.002	0	%100
23	29	Х	-0.002	-0.002	0	%100
24	32	Х	-0.002	-0.002	0	%100
25	35	X	-0.002	-0.002	0	%100
26	41	Х	-0.002	-0.002	0	%100

Member Distributed Loads (BLC 6 : 0 Wind - Service)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Z	-0.0003	-0.0003	0	%100
2	2	Z	-0.0003	-0.0003	0	%100
3	3	Z	-0.0002	-0.0002	0	%100
4	4	Z	-0.0002	-0.0002	0	%100
5	5	Z	-1e-04	-1e-04	0	%100
6	7	Z	-0.0002	-0.0002	0	%100
7	8	Z	-0.0002	-0.0002	0	%100
8	9	Z	-1e-04	-1e-04	0	%100
9	11	Z	-0.0002	-0.0002	0	%100
10	12	Z	-0.0002	-0.0002	0	%100
11	13	Z	-1e-04	-1e-04	0	%100
12	15	Z	-0.0002	-0.0002	0	%100
13	16	Z	-0.0002	-0.0002	0	%100
14	17	Z	-1e-04	-1e-04	0	%100
15	19	Ζ	-1e-04	-1e-04	0	%100
16	20	Z	-1e-04	-1e-04	0	%100
17	21	Z	-1e-04	-1e-04	0	%100
18	22	Ζ	-1e-04	-1e-04	0	%100
19	23	Z	-1e-04	-1e-04	0	%100
20	24	Ζ	-1e-04	-1e-04	0	%100
21	25	Z	-1e-04	-1e-04	0	%100
22	26	Ζ	-1e-04	-1e-04	0	%100
23	29	Z	-0.0003	-0.0003	0	%100
24	32	Z	-0.0003	-0.0003	0	%100
25	35	Z	-0.0003	-0.0003	0	%100
26	41	Z	-0.0002	-0.0002	0	%100

Member Distributed Loads (BLC 7: 90 Wind - Service)

	Member Label Direction Start Magnitude [k/ft, F, ksf, k-ft/ft] End Magnitude [k/ft, F, ksf, k-ft/ft] Start Location [(ft, %)] End Location [(ft, %)							
1	1	Χ	-0.0003	-0.0003	0	%100		
2	2	Χ	-0.0003	-0.0003	0	%100		
3	3	Χ	-0.0002	-0.0002	0	%100		
4	4	Χ	-0.0002	-0.0002	0	%100		
5	5	Χ	-1e-04	-1e-04	0	%100		
6	7	Χ	-0.0002	-0.0002	0	%100		
7	8	Χ	-0.0002	-0.0002	0	%100		



Company : B+T Group Designer : SP Job Number : 101023.006.01 Model Name : CT01725-A - Bloomfield

12/19/2021 4:02:21 PM

Checked By : ___

Member Distributed Loads (BLC 7 : 90 Wind - Service) (Continued)

	Member Label Direction Start Magnitude [k/ft, F, ksf, k-ft/ft] End Magnitude [k/ft, F, ksf, k-ft/ft] Start Location [(ft, %)] End Location [(ft, %)]							
7	8	Х	-0.0002	-0.0002	0	%100		
8	9	Χ	-1e-04	-1e-04	0	%100		
9	11	X	-0.0002	-0.0002	0	%100		
10	12	Χ	-0.0002	-0.0002	0	%100		
11	13	X	-1e-04	-1e-04	0	%100		
12	15	X	-0.0002	-0.0002	0	%100		
13	16	Χ	-0.0002	-0.0002	0	%100		
14	17	X	-1e-04	-1e-04	0	%100		
15	19	Χ	-1e-04	-1e-04	0	%100		
16	20	X	-1e-04	-1e-04	0	%100		
17	21	X	-1e-04	-1e-04	0	%100		
18	22	Χ	-1e-04	-1e-04	0	%100		
19	23	X	-1e-04	-1e-04	0	%100		
20	24	Χ	-1e-04	-1e-04	0	%100		
21	25	X	-1e-04	-1e-04	0	%100		
22	26	Χ	-1e-04	-1e-04	0	%100		
23	29	X	-0.0003	-0.0003	0	%100		
24	32	Χ	-0.0003	-0.0003	0	%100		
25	35	Χ	-0.0003	-0.0003	0	%100		
26	41	X	-0.0002	-0.0002	0	%100		

Member Distributed Loads (BLC 8 : Ice)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Υ	-0.009	-0.009	0	%100
2	2	Υ	-0.009	-0.009	0	%100
3	3	Y	-0.011	-0.011	0	%100
4	4	Υ	-0.007	-0.007	0	%100
5	5	Υ	-0.012	-0.012	0	%100
6	7	Υ	-0.011	-0.011	0	%100
7	8	Υ	-0.007	-0.007	0	%100
8	9	Υ	-0.012	-0.012	0	%100
9	11	Υ	-0.011	-0.011	0	%100
10	12	Υ	-0.007	-0.007	0	%100
11	13	Υ	-0.012	-0.012	0	%100
12	15	Υ	-0.011	-0.011	0	%100
13	16	Υ	-0.007	-0.007	0	%100
14	17	Υ	-0.012	-0.012	0	%100
15	19	Υ	-0.005	-0.005	0	%100
16	20	Υ	-0.005	-0.005	0	%100
17	21	Υ	-0.004	-0.004	0	%100
18	22	Υ	-0.004	-0.004	0	%100
19	23	Υ	-0.005	-0.005	0	%100
20	24	Υ	-0.005	-0.005	0	%100
21	25	Υ	-0.004	-0.004	0	%100
22	26	Υ	-0.004	-0.004	0	%100
23	29	Υ	-0.009	-0.009	0	%100
24	32	Υ	-0.009	-0.009	0	%100
25	35	Υ	-0.009	-0.009	0	%100
26	41	Υ	-0.008	-0.008	0	%100



Checked By : ____

Member Distributed Loads (BLC 9 : 0 Seismic)

	Member Label Direction Start Magnitude [k/ft, F, ksf, k-ft/ft] End Magnitude [k/ft, F, ksf, k-ft/ft] Start Location [(ft, %)] End Location [(ft, %)]												
1	1	Z	-0.001	-0.001	0	%100							
2	2	Z	-0.001	-0.001	0	%100							
3	3	Z	-0.001	-0.001	0	%100							
4	4	Z	-0.0004	-0.0004	0	%100							
5	5	Z	-0.001	-0.001	0	%100							
6	7	Z	-0.001	-0.001	0	%100							
7	8	Z	-0.0004	-0.0004	0	%100							
8	9	Z	-0.001	-0.001	0	%100							
9	11	Z	-0.001	-0.001	0	%100							
10	12	Z	-0.0004	-0.0004	0	%100							
11	13	Z	-0.001	-0.001	0	%100							
12	15	Z	-0.001	-0.001	0	%100							
13	16	Z	-0.0004	-0.0004	0	%100							
14	17	Z	-0.001	-0.001	0	%100							
15	19	Z	-0.0002	-0.0002	0	%100							
16	20	Z	-0.0002	-0.0002	0	%100							
17	21	Z	-0.0003	-0.0003	0	%100							
18	22	Z	-0.0003	-0.0003	0	%100							
19	23	Z	-0.0002	-0.0002	0	%100							
20	24	Z	-0.0002	-0.0002	0	%100							
21	25	Z	-0.0003	-0.0003	0	%100							
22	26	Z	-0.0003	-0.0003	0	%100							
23	29	Z	-0.0006	-0.0006	0	%100							
24	32	Z	-0.0006	-0.0006	0	%100							
25	35	Z	-0.0006	-0.0006	0	%100							
26	41	Z	-0.0005	-0.0005	0	%100							

Member Distributed Loads (BLC 10: 90 Seismic)

		D 0 0 0	Ctart Magrittade [Wit, 1, Koi, K Wit]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(it, 70)]	End Location [(II, %)]
1	1	Χ	-0.001	-0.001	0	%100
2	2	Χ	-0.001	-0.001	0	%100
3	3	Χ	-0.001	-0.001	0	%100
4	4	Χ	-0.0004	-0.0004	0	%100
5	5	Χ	-0.001	-0.001	0	%100
6	7	Χ	-0.001	-0.001	0	%100
7	8	X	-0.0004	-0.0004	0	%100
8	9	Χ	-0.001	-0.001	0	%100
9	11	Χ	-0.001	-0.001	0	%100
10	12	Χ	-0.0004	-0.0004	0	%100
11	13	Х	-0.001	-0.001	0	%100
12	15	Χ	-0.001	-0.001	0	%100
13	16	Χ	-0.0004	-0.0004	0	%100
14	17	Χ	-0.001	-0.001	0	%100
15	19	Х	-0.0002	-0.0002	0	%100
16	20	Χ	-0.0002	-0.0002	0	%100
17	21	Χ	-0.0003	-0.0003	0	%100
18	22	Χ	-0.0003	-0.0003	0	%100
19	23	Х	-0.0002	-0.0002	0	%100
20	24	Х	-0.0002	-0.0002	0	%100
21	25	Х	-0.0003	-0.0003	0	%100
22	26	Χ	-0.0003	-0.0003	0	%100



Checked By:___

Member Distributed Loads	(BLC 10 : 90 Seismic)	(Continued)
--------------------------	-----------------------	-------------

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
23	29	Х	-0.0006	-0.0006	0	%100
24	32	Х	-0.0006	-0.0006	0	%100
25	35	Х	-0.0006	-0.0006	0	%100
26	41	Х	-0.0005	-0.0005	0	%100

Node Loads and Enforced Displacements (BLC 11 : Live Load a)

	Node Label	L, D, M	Direction	Magnitude [(k, k-ft), (in, rad), (k*s²/ft, k*s²*ft)]
1	57	L	Υ	-0.5

Node Loads and Enforced Displacements (BLC 12 : Live Load b)

	Node Label	L, D, M	Direction	Magnitude [(k, k-ft), (in, rad), (k*s²/ft, k*s²*ft)]
1	45	L	Υ	-0.5

Node Loads and Enforced Displacements (BLC 13 : Live Load c)

	Node Label	L, D, M	Direction	Magnitude [(k, k-ft), (in, rad), (k*s²/ft, k*s²*ft)]
1	51	L	Υ	-0.5

Basic Load Cases

	BLC Description	Category	Y Gravity	Nodal	Point	Distributed
1	Dead	DĽ	-1		10	
2	0 Wind - No Ice	WLZ			10	26
3	90 Wind - No Ice	WLX			10	26
4	0 Wind - Ice	WLZ			10	26
5	90 Wind - Ice	WLX			10	26
6	0 Wind - Service	WLZ			10	26
7	90 Wind - Service	WLX			10	26
8	Ice	OL1			10	26
9	0 Seismic	ELZ			10	26
10	90 Seismic	ELX			10	26
11	Live Load a	LL		1		
12	Live Load b	LL		1		
13	Live Load c	LL		1		
14	Live Load d	LL				
15	Maint LL 1	LL			1	
16	Maint LL 2	LL			1	
17	Maint LL 3	LL			1	
18	Maint LL 4	LL			1	
19	Maint LL 5	LL			1	
20	Maint LL 6	LL			1	
21	Maint LL 7	LL				
22	Maint LL 8	LL				
23	Maint LL 9	LL				
24	Maint LL 10	LL				
25	Maint LL 11	LL				
26 27	Maint LL 12	LL				
	Maint LL 13	LL				
28	Maint LL 14	LL				
29	Maint LL 15	LL				



Company : B+T Group
Designer : SP
Job Number : 101023.006.01
Model Name : CT01725-A - Bloomfield

12/19/2021 4:02:21 PM

Checked By : ____

Load Combinations

Description	Solve	PDelta	BLC	Factor	BLC	Factor	BLC	Factor	BLC	Factor
1 1.4 Dead	Yes	Υ	1	1.4						
2 1.2 D + 1.0 - 0 W	Yes	Υ	1	1.2	2	1				
3 1.2 D + 1.0 - 30 W	Yes	Υ	1	1.2	2	0.866	3	0.5		
4 1.2 D + 1.0 - 60 W	Yes	Υ	1	1.2	3	0.866	2	0.5		
5 1.2 D + 1.0 - 90 W	Yes	Υ	1	1.2	3	1				
6 1.2 D + 1.0 - 120 W	Yes	Υ	1	1.2	3	0.866	2	-0.5		
7 1.2 D + 1.0 - 150 W	Yes	Υ	1	1.2	2	-0.866	3	0.5		
8 1.2 D + 1.0 - 180 W	Yes	Υ	1	1.2	2	-1				
9 1.2 D + 1.0 - 210 W	Yes	Y	1	1.2	2	-0.866	3	-0.5		
10 1.2 D + 1.0 - 240 W	Yes	Υ	1	1.2	3	-0.866	2	-0.5		
11 1.2 D + 1.0 - 270 W	Yes	Υ	1	1.2	3	-1				
12 1.2 D + 1.0 - 300 W	Yes	Υ	1	1.2	3	-0.866	2	0.5		
13 1.2 D + 1.0 - 330 W	Yes	Υ	1	1.2	2	0.866	3	-0.5		
14 1.2 D + 1.0 - 0 W/Ice	Yes	Υ	1	1.2	4	1			8	1
15 1.2 D + 1.0 - 30 W/Ice	Yes	Υ	1	1.2	4	0.866	5	0.5	8	1
16 1.2 D + 1.0 - 60 W/Ice	Yes	Υ	1	1.2	5	0.866	4	0.5	8	1
17 1.2 D + 1.0 - 90 W/Ice	Yes	Υ	1	1.2	5	1			8	1
18 1.2 D + 1.0 - 120 W/Ice	Yes	Υ	1	1.2	5	0.866	4	-0.5	8	1
19 1.2 D + 1.0 - 150 W/lce	Yes	Y	1	1.2	4	-0.866	5	0.5	8	1
20 1.2 D + 1.0 - 180 W/Ice	Yes	Υ	1	1.2	4	-1			8	1
21 1.2 D + 1.0 - 210 W/lce	Yes	Υ	1	1.2	4	-0.866	_ 5	-0.5	8	1
22 1.2 D + 1.0 - 240 W/lce	Yes	Υ	1	1.2	5	-0.866	4	-0.5	8	1
23 1.2 D + 1.0 - 270 W/lce	Yes	Υ	1	1.2	5	1			8	1
24 1.2 D + 1.0 - 300 W/lce	Yes	Υ	1	1.2	_ 5	-0.866	4	0.5	8	1
25 1.2 D + 1.0 - 330 W/lce	Yes	Υ	1	1.2	4	0.866	5	-0.5	8	1
26 1.2 D + 1.0 E - 0	Yes	Υ	1	1.2	9	1			_	
27 1.2 D + 1.0 E - 30	Yes	Υ	1	1.2	9	0.866	10	0.5		
28 1.2 D + 1.0 E - 60	Yes	Υ	1	1.2	10	0.866	9	0.5		
29 1.2 D + 1.0 E - 90	Yes	Y	1	1.2	10	1				
30 1.2 D + 1.0 E - 120	Yes	Υ	1	1.2	10	0.866	9	-0.5		
31 1.2 D + 1.0 E - 150	Yes	Υ	1	1.2	9	-0.866	10	0.5		
32 1.2 D + 1.0 E - 180	Yes	Y	1	1.2	9	-1				
33 1.2 D + 1.0 E - 210	Yes	Υ	1	1.2	9	-0.866	10	-0.5		
34 1.2 D + 1.0 E - 240	Yes	Υ	1	1.2	10	-0.866	9	-0.5		
35 1.2 D + 1.0 E - 270	Yes	Υ	1	1.2	10	-1		0.5		
36 1.2 D + 1.0 E - 300	Yes	Y	1	1.2	10	-0.866	9	0.5		
37 1.2 D + 1.0 E - 330	Yes	Y	1	1.2	9	0.866	10	-0.5	44	4.5
38 1.2 D + 1.5 LL a + Service - 0 W	Yes	Y	1	1.2	6	1	7	0.5	11	1.5
39 1.2 D + 1.5 LL a + Service - 30 W	Yes	Y	1	1.2	6	0.866	7	0.5	11	1.5
40 1.2 D + 1.5 LL a + Service - 60 W	Yes	Y	1	1.2	7	0.866	6	0.5	11	1.5
41 1.2 D + 1.5 LL a + Service - 90 W	Yes	Y	1	1.2	7	1		0.5	11	1.5
42 1.2 D + 1.5 LL a + Service - 120 W	_	Y	1	1.2	7	0.866	6	-0.5	11	1.5
43 1.2 D + 1.5 LL a + Service - 150 W	Yes	Y	1	1.2	6	-0.866	7	0.5	11	1.5
44 1.2 D + 1.5 LL a + Service - 180 W	Yes	Y	1	1.2	6	-1		0.5	11	1.5
45 1.2 D + 1.5 LL a + Service - 210 W	Yes	Y	1	1.2	6	-0.866	7	-0.5	11	1.5
46 1.2 D + 1.5 LL a + Service - 240 W	Yes	Y	1	1.2	7	-0.866	6	-0.5	11	1.5
47 1.2 D + 1.5 LL a + Service - 270 W	Yes	Y	1	1.2	7	-1	6	0.5	11	1.5
48 1.2 D + 1.5 LL a + Service - 300 W	Yes	Y	1	1.2	7	-0.866	6	0.5	11	1.5
49 1.2 D + 1.5 LL a + Service - 330 W	Yes	Y	1	1.2	6	0.866	7	-0.5	11	1.5
50 1.2 D + 1.5 LL b + Service - 0 W	Yes	Y	1	1.2	6	1	7	0.5	12	1.5
51 1.2 D + 1.5 LL b + Service - 30 W	Yes	Υ	1	1.2	6	0.866	7	0.5	12	1.5



Company : B+T Group
Designer : SP
Job Number : 101023.006.01
Model Name : CT01725-A - Bloomfield

12/19/2021 4:02:21 PM Checked By : ____

Load Combinations (Continued)

Description	Solve	PDelta	BLC	Factor	BLC	Factor	BLC	Factor	BLC	Factor
52 1.2 D + 1.5 LL b + Service - 60 W	Yes	Υ	1	1.2	7	0.866	6	0.5	12	1.5
53 1.2 D + 1.5 LL b + Service - 90 W	Yes	Y	1	1.2	7	1			12	1.5
54 1.2 D + 1.5 LL b + Service - 120 W	Yes	Υ	1	1.2	7	0.866	6	-0.5	12	1.5
55 1.2 D + 1.5 LL b + Service - 150 W	Yes	Υ	1	1.2	6	-0.866	7	0.5	12	1.5
56 1.2 D + 1.5 LL b + Service - 180 W	Yes	Υ	1	1.2	6	-1			12	1.5
57 1.2 D + 1.5 LL b + Service - 210 W	Yes	Υ	1	1.2	6	-0.866	7	-0.5	12	1.5
58 1.2 D + 1.5 LL b + Service - 240 W	Yes	Υ	1	1.2	7	-0.866	6	-0.5	12	1.5
59 1.2 D + 1.5 LL b + Service - 270 W	Yes	Υ	1	1.2	7	-1			12	1.5
60 1.2 D + 1.5 LL b + Service - 300 W	Yes	Υ	1	1.2	7	-0.866	6	0.5	12	1.5
61 1.2 D + 1.5 LL b + Service - 330 W	Yes	Υ	1	1.2	6	0.866	7	-0.5	12	1.5
62 1.2 D + 1.5 LL c + Service - 0 W	Yes	Υ	1	1.2	6	1			13	1.5
63 1.2 D + 1.5 LL c + Service - 30 W	Yes	Υ	1	1.2	6	0.866	7	0.5	13	1.5
64 1.2 D + 1.5 LL c + Service - 60 W	Yes	Y	1	1.2	7	0.866	6	0.5	13	1.5
65 1.2 D + 1.5 LL c + Service - 90 W	Yes	Υ	1	1.2	7	1			13	1.5
66 1.2 D + 1.5 LL c + Service - 120 W	Yes	Υ	1	1.2	7	0.866	6	-0.5	13	1.5
67 1.2 D + 1.5 LL c + Service - 150 W	Yes	Υ	1	1.2	6	-0.866	7	0.5	13	1.5
68 1.2 D + 1.5 LL c + Service - 180 W	Yes	Y	1	1.2	6	-1			13	1.5
69 1.2 D + 1.5 LL c + Service - 210 W	Yes	Υ	1	1.2	6	-0.866	7	-0.5	13	1.5
70 1.2 D + 1.5 LL c + Service - 240 W	Yes	Y	1	1.2	7	-0.866	6	-0.5	13	1.5
71 1.2 D + 1.5 LL c + Service - 270 W	Yes	Υ	1	1.2	7	-1			13	1.5
72 1.2 D + 1.5 LL c + Service - 300 W	Yes	Υ	1	1.2	7	-0.866	6	0.5	13	1.5
73 1.2 D + 1.5 LL c + Service - 330 W	Yes	Υ	1	1.2	6	0.866	7	-0.5	13	1.5
74 1.2 D + 1.5 LL d + Service - 0 W	Yes	Υ	1	1.2	6	1			14	1.5
75 1.2 D + 1.5 LL d + Service - 30 W	Yes	Υ	1	1.2	6	0.866	7	0.5	14	1.5
76 1.2 D + 1.5 LL d + Service - 60 W	Yes	Y	1	1.2	7	0.866	6	0.5	14	1.5
77 1.2 D + 1.5 LL d + Service - 90 W	Yes	Y	1	1.2	7	1			14	1.5
78 1.2 D + 1.5 LL d + Service - 120 W	Yes	Y	1	1.2	7	0.866	6	-0.5	14	1.5
79 1.2 D + 1.5 LL d + Service - 150 W	Yes	Υ	1	1.2	6	-0.866	7	0.5	14	1.5
80 1.2 D + 1.5 LL d + Service - 180 W	Yes	Y	1	1.2	6	-1	-	0.0	14	1.5
81 1.2 D + 1.5 LL d + Service - 210 W	Yes	Y	1	1.2	6	-0.866	7	-0.5	14	1.5
82 1.2 D + 1.5 LL d + Service - 240 W	Yes	Y	1	1.2	7	-0.866	6	-0.5	14	1.5
83 1.2 D + 1.5 LL d + Service - 270 W	Yes	Y	1	1.2	7	-1		0.0	14	1.5
84 1.2 D + 1.5 LL d + Service - 300 W	Yes	Y	1	1.2	7	-0.866	6	0.5	14	1.5
85 1.2 D + 1.5 LL d + Service - 330 W	Yes	Y	1	1.2	6	0.866	7	-0.5	14	1.5
86 1.2 D + 1.5 LL Maint (1)	Yes	Ý	1	1.2		3.000		0.0	15	1.5
87 1.2 D + 1.5 LL Maint (1)	Yes	Y	1	1.2					16	1.5
88 1.2 D + 1.5 LL Maint (3)	Yes	Y	1	1.2					17	1.5
89 1.2 D + 1.5 LL Maint (4)	Yes	Y	1	1.2					18	1.5
90 1.2 D + 1.5 LL Maint (4)	Yes	Y	1	1.2					19	1.5
91 1.2 D + 1.5 LL Maint (6)	Yes	Y	1	1.2					20	1.5
1.2 D 1 1.3 LL IVIAIII (0)	163			1.4					20	1.0

Envelope Node Reactions

	Node Label		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	12	max	0.788	41	0.899	19	0.57	13	0	91	0	91	0	91
2		min	-1.447	71	0.283	11	-1.944	19	0	1	0	1	0	1
3	27	max	1.439	65	0.828	24	1.751	14	0	91	0	91	0	91
4		min	-0.781	47	0.258	5	0.309	8	0	1	0	1	0	1
5	64	max	0.055	6	0.05	18	0.678	6	0	91	0	91	0	91
6		min	-0.055	12	0.002	12	-0.679	12	0	1	0	1	0	1
7	Totals:	max	0.674	5	1.751	17	0.898	2						
8		min	-0.674	11	0.613	12	-0.898	8						



Checked By : ____

Envelope AISC 15TH (360-16): LRFD Member Steel Code Checks

	Membe	r Shape o	Code Chec	kLoc[ft]LCS	hear Chec	ckLoc[ft]	DirLC	phi*Pnc [k]	phi*Pnt [k]	phi*Mn y-y [k-ft]	phi*Mn z-z [k-f	t] Cb Eqn
1	1	PIPE_2.88x0.203	0.102	7.66771	0.067	6.25	68	35.361	70.548	5.01	5.01	2.277 H1-1b
2	2	PIPE_2.88x0.203	0.095	6.25 8	0.058	1.75	6	35.361	70.548	5.01	5.01	1.494H1-1b
3	3	PL5/8x3.5	0.243	0.58367	0.079	0.583	y 38	84.578	99.225	1.302	7.235	1.444 H1-1b
4	4	1.9" ODx0.12"	0.269	0.13567	0.07	2.449	18	21.867	25.364	1.2	1.2	2.07 H1-1b
5	5	PL5/8x4.25	0.091	0.12767	0.04	0.362	y 24	110.629	119.531	1.556	10.583	1.37 H1-1b
6	7	PL5/8x3.5	0.188	0.58349	0.096	0	y 19	84.578	99.225	1.302	7.235	1.249H1-1b
7	8	1.9" ODx0.12"	0.217	1.29287	0.071	2.449	18	21.867	25.364	1.2	1.2	1.317 H1-1b
8	9	PL5/8x4.25	0.102	0.36213	0.049	0.127	y 18	110.629	119.531	1.556	10.583	1.426H1-1b
9	11	PL5/8x3.5	0.234	0.58367	0.079	0.583	y 45	84.578	99.225	1.302	7.18	1.003H1-1b
10	12	1.9" ODx0.12"	0.295	0.13566	0.059	2.449	20	21.867	25.364	1.2	1.2	2.067H1-1b
11	13	PL5/8x4.25	0.071	0.12768	0.04	0.362	y 44	110.629	119.531	1.556	10.583	1.825 H1-1b
12	15	PL5/8x3.5	0.186	0.58349	0.097	0	y 66	84.578	99.225	1.302	7.235	1.079H1-1b
13	16	1.9" ODx0.12"	0.234	0.13549	0.064	2.449	20	21.867	25.364	1.2	1.2	2.057 H1-1b
14	17	PL5/8x4.25	0.047	0.12743	0.046	0.362	y 68	110.629	119.531	1.556	10.583	1.899H1-1b
15	19	0.63" SR	0.395	2.5 65	0.006	2.5	66	1.941	14.028	0.147	0.147	2.23 H1-1a
16	20	0.63" SR	0.521	2.5 67	0.012	0	67	1.941	14.028	0.147	0.147	2.265H1-1a
17	21	1/2" SR	0.309	3.49916	0.008	3.499	48	0.393	8.836	0.074	0.074	2.078H1-1a
18	22	1/2" SR	0	3.49991	0.007	0	43	0.393	8.836	0.074	0.074	1 H1-1a
19	23	0.63" SR	0.302	2.5 49	0.007	0	6	1.941	14.028	0.147	0.147	1.84 H1-1a
20	24	0.63" SR	0.415	2.5 48	0.013	0	67	1.941	14.028	0.147	0.147	2.258H1-1a
21	25	1/2" SR	0.229	0 47	0.011	0	71	0.393	8.836	0.074	0.074	1.69 H1-1a
22	26	1/2" SR	0.003	0 67	0.01	0	6	0.393	8.836	0.074	0.074	1.452H1-1b*
23	29	Pipe2.88x.12	0.056	2.75 7	0.042	2.75	67	22.492	43.076	3.156	3.156	3 H1-1b
24	32	Pipe2.88x.12	0.159	5.25 62	0.046	5.25	62	22.492	43.076	3.156	3.156	3 H1-1b
25	35	Pipe2.88x.12	0.125	5.25 43	0.036	5.25	48	22.492	43.076	3.156	3.156	3 H1-1b
26	41	Pipe2.38X0.12	0.056	0 6	0.004	8.207	23	12.694	35.273	2.115	2.115	1.136H1-1b*

APPENDIX B

(Additional Calculations)



Address:

No Address at This Location

ASCE 7 Hazards Report

Standard: ASCE/SEI 7-16


Risk Category: ||


Soil Class: D - Default (see

Section 11.4.3)

Elevation: 120.07 ft (NAVD 88)

Latitude: 41.820119 **Longitude:** -72.696514





Wind

Results:

Wind Speed 117 Vmph
10-year MRI 75 Vmph
25-year MRI 84 Vmph
50-year MRI 90 Vmph
100-year MRI 97 Vmph

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2

Date Accessed: Fri Dec 17 2021

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2. Glazed openings need not be protected against wind-borne debris.




Seismic


Site Soil Class: D - Default (see Section 11.4.3)


Results:


S _s :	0.183	S _{D1} :	0.088
S_1 :	0.055	T _L :	6
F _a :	1.6	PGA:	0.098
F_{ν} :	2.4	PGA _M :	0.156
S _{MS} :	0.293	F _{PGA} :	1.6
S _{M1} :	0.131	l _e :	1
S _{DS} :	0.195	C _v :	0.7

Seismic Design Category B









Data Accessed: Fri Dec 17 2021

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.



Ice

Results:

Ice Thickness: 1.50 in.

Concurrent Temperature: 5 F

Gust Speed 50 mph

Data Source: Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

Date Accessed: Fri Dec 17 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

EXHIBIT 10

Construction Drawings

O E S M wireless.

DISH Wireless L.L.C. SITE ID:

BOBDL00022B

DISH Wireless L.L.C. SITE ADDRESS:

1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

CONNECTICUT CODE OF COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES

CODE TYPE

2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS 2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS MECHANICAL 2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

	SHEET INDEX						
SHEET NO.	SHEET TITLE						
T-1	TITLE SHEET						
LS1	SITE SURVEY						
A-1	OVERALL AND ENLARGED SITE PLAN						
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE						
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS						
A-4	EQUIPMENT DETAILS						
A-5	EQUIPMENT DETAILS						
A-6	EQUIPMENT DETAILS						
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES						
E-2	ELECTRICAL DETAILS						
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE						
G-1	GROUNDING PLANS AND NOTES						
G-2	GROUNDING DETAILS						
G-3	GROUNDING DETAILS						
RF-1	RF CABLE COLOR CODE						
GN-1	LEGEND AND ABBREVIATIONS						
GN-2	GENERAL NOTES						
GN-3	GENERAL NOTES						
GN-4	GENERAL NOTES						

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

TOWER SCOPE OF WORK:

- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
 INSTALL (3) PROPOSED SECTOR FRAMES
- INSTALL PROPOSED JUMPERS
 INSTALL (6) PROPOSED RRUS (2 PER SECTOR)
- INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
- INSTALL (1) PROPOSED HYBRID CABLE

GROUND SCOPE OF WORK:

- INSTALL (1) PROPOSED ICE BRIDGE
- INSTALL (1) PROPOSED PPC CABINET
- INSTALL 1) PROPOSED EQUIPMENT CABINET (1) PROPOSED POWER CONDUIT INSTALL
- (1) PROPOSED TELCO CONDUIT
- INSTALL (1) PROPOSED TELCO-FIBER BOX
- INSTALL (1) PROPOSED GPS UNIT
- INSTALL 1) PROPOSED SAFETY SWITCH (IF REQUIRED)
- INSTALL (1) PROPOSED FIBER NID (IF REQUIRED)
- INSTALL (1) PROPOSED METER SOCKET

SITE PHOTO





UNDERGROUND SERVICE ALERT CBYD 811 UTILITY NOTIFICATION CENTER OF CONNECTICUT (800) 922-4455 WWW.CBYD.COM

CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION

GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCFEDING WITH THE WORK.

PROJECT DIRECTORY

TOWER OWNER: SBA COMMUNICATAIONS CORP.

SITE DESIGNER: B+T GROUP

SITE ACQUISITION:

CONST. MANAGER:

RF ENGINEER:

DISH Wireless L.L.C.

LITTLETON, CO 80120

8051 CONGRESS AVENUE

BOCA RATON, FL 33487

1717 S. BOULDER AVE, SUITE 300

(800) 487-7483

TULSA, OK 74119

APRIL PARROTT

CHAD WILCOX

april.parrott@dish.com

chad.wilcox@dish.com

jared.robinson@dish.com

JARED ROBINSON

(918) 587-4630

5701 SOUTH SANTA FE DRIVE

DIRECTIONS FROM BRADLEY INTERNATIONAL AIRPORT:

SITE INFORMATION

BLUE HILLS FIRE DIST

BLOOMFIELD, CT 06002

SELF-SUPPORT TOWER

HARTFORD

LONGITUDE (NAD 83): 72° 41' 47.45" W

41° 49' 12 43" N 41.82011878

-72.69651356

130-2-14

ROCKWELL AVENUE

PROPERTY OWNER:

TOWER CO SITE ID:

LATITUDE (NAD 83):

ZONING JURISDICTION:

ZONING DISTRICT:

PARCEL NUMBER:

OCCUPANCY GROUP:

CONSTRUCTION TYPE:

TELEPHONE COMPANY: AT&T

TOWER APP NUMBER:


ADDRESS:

TOWER TYPE

COUNTY:

GET ON BRADLEY INTERNATIONAL AIRPORT CON IN EAST GRANBY FROM BRADLEY INTERNATIONAL AIRPORT, HEAD NORTH TOWARD BRADLEY INTERNATIONAL AIRPORT, SLIGHT LEFT ONTO BRADLEY INTERNATIONAL AIRPORT, CONTINUE STRAIGHT, KEEP RIGHT TO CONTINUE TOWARD BRADLEY INTERNATIONAL AIRPORT CON, TAKE CT_20 E AND I—91 S TO CT_218 W IN WINDSOR. TAKE EXIT 35B FROM I—91 S, CONTINUE ONTO BRADLEY INTERNATIONAL AIRPORT CON, CONTINUE ONTO CT_20 E/BRADLEY INTERNATIONAL AIRPORT CON, TAKE THE EXIT ONTO 1-91 S TOWARD HARTFORD, TAKE EXIT 35B FOR CT-218 TOWARD WINDSOR/BLOOMFIELD, CONTINUE ON CT-218 W TO YOUR DESTINATION IN BLOOMFIELD, USE ANY LANE TO TURN RIGHT ONTO CT-218 W, TURN RIGHT ONTO CT-187 N/BLUE HILLS AVE, TURN LEFT ONTO ROCKWELL AVE, TURN RIGHT AND ARRIVE AT

DIRECTIONS





5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:	
NGN		BLJ		BLJ		

RFDS REV #:

PRELIMINARY DOCUMENTS

	SUBMITTALS				
REV	DATE DESCRIPTION				
Α	12/21/21	ISSUED FOR REVIEW			
0	01/07/22	ISSUED FOR CONSTRUCTION			
	A&E PROJECT NUMBER				


101023.004.01


BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

> SHEET TITLE TITLE SHEET

SHEET NUMBER

T-1







5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487

EXISTING SELF-SUPPORT TOWER

WIDTH OF TOWER FACE IS NOT TO BE CONSIDERED TO SCALE

MANUFACTURER MODEL

RAYCAP

RDIDC-9181 -PF-48

SHARED

W/ALPHA

SHARED

W/ALPHA

3/4"=1'-0

TECH POS.

A2

A2

B2

B2

C2

C2

NO SCALE

5G

5G

--

5G

5G

5G

5G

--





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:	
NGN		BLJ		BLJ		

RFDS REV #:

PRELIMINARY DOCUMENTS

	SUBMITTALS					
REV	DATE	DESCRIPTION				
Α	12/21/21	ISSUED FOR REVIEW				
0	01/07/22	ISSUED FOR CONSTRUCTION				
		·				
	4055	DO IEST NUMBER				

A&E PROJECT NUMBER 101023.004.01

DISH Wireless L.L.C. ROJECT INFORMATION


BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002


SHEET TITLE


ELEVATION, ANTENNA LAYOUT AND SCHEDULE

SHEET NUMBER


A-2








DISH Wireless L.L.C. TEMPLATE VERSION 45 - 10/08/2021





DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING $\pm 24V$ AND $\pm 48V$ CONDUCTORS. RED MARKINGS SHALL IDENTIFY $\pm 24V$ AND BLUE MARKINGS SHALL IDENTIFY $\pm 48V$.

- CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
- 2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
- 3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
- 4. CONDUIT ROUGH—IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
- 5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
- 6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
- CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES.
 INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
- 8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
- INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250.
 THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL
 DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
- 10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
- 11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
- 12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
- 13. ALL TRENCHES IN COMPOUND TO BE HAND DUG



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:	
NGN		BLJ		BLJ		

RFDS REV #:

PRELIMINARY DOCUMENTS

	SUBMITTALS					
REV	DATE	DATE DESCRIPTION				
Α	12/21/21	ISSUED FOR REVIEW				
0	01/07/22	ISSUED FOR CONSTRUCTION				
		BB LEST NUMBER				

A&E PROJECT NUMBER

101023.004.01

DISH Wireless L.L.C

BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

SHEET TITLE


ELECTRICAL/FIBER ROUTE
PLAN AND NOTES


SHEET NUMBER

E-1

ELECTRICAL NOTES

UTILITY ROUTE PLAN





NOTES

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED SHORT CIRCUIT CALCULATIONS AND THE AIC RATINGS FOR EACH DEVICE IS ADEQUATE TO PROTECT THE QUIPMENT AND THE ELECTRICAL SYSTEM.

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED VOLTAGE DROP CALCULATIONS AND ALL BRANCH CIRCUIT AND FEEDERS COMPLY WITH THE NEC LISTED ON T-1) ARTICLE 210.19(A)(1) FPN NO. 4.

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(a) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

> #12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A #10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A #8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A #6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358.

0.5" CONDUIT - 0.122 SQ. IN AREA 0.75" CONDUIT - 0.213 SQ. IN AREA 2.0" CONDUIT - 1.316 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.

#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN #10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND

D.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, NCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.

#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN #10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND

D.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, NCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.

3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN #6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND

= 0.8544 SO IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES,

PPC ONE-LINE DIAGRAM

PROPOSED CHARLES PANEL SCHEDULE LOAD SERVED (WATTS) (WATTS) LOAD SERVED ABB/GE INFINITY RECTIFIER 1 30A ABB/GE INFINITY RECTIFIER 2 30A ARR/GE INFINITY 30A ABB/GE INFINITY 30A RÉCTIFIER 4 VOLTAGE AMPS 180 180 200A MCB, 1φ, 24 SPACE, 120/240V MB RATING: 65,000 AIC 11700 VOLTAGE AMPS 98 AMPS 98

PANEL SCHEDULE

NO SCALE

wireless

5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

	DRAWN BY:	CHECKED BY:	APPROVED BY
ı	NGN	BLJ	BLJ

RFDS REV #:

PRELIMINARY DOCUMENTS

	SUBMITTALS			
R	EV	DATE	DESCRIPTION	
	Α	12/21/21	ISSUED FOR REVIEW	
	0	01/07/22	ISSUED FOR CONSTRUCTION	

A&E PROJECT NUMBER

101023.004.01

BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

SHEET TITLE

ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE

SHEET NUMBER


E-3

MAX AMPS


NO SCALE

NOT USED

NO SCALE



NOTES



PROPOSED UPPER TOWER GROUND BUSS BAR

TYPICAL ANTENNA GROUNDING PLAN

EXOTHERMIC CONNECTION

GROUND ROD

MECHANICAL CONNECTION GROUND BUS BAR

 (\bullet)

TEST GROUND ROD WITH INSPECTION SLEEVE

---- #6 AWG STRANDED & INSULATED - · - #2 AWG SOLID COPPER TINNED

▲ BUSS BAR INSULATOR

GROUNDING LEGEND

- 1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY
- 2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM, GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
- 3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- (A) EXTERIOR GROUND RING: #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- TOWER GROUND RING: THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, B TOWER GROUND RING: THE GROUND RING SYSTEM SHALL BE INSTALLED ANDOND AN ANTENDED FOR THE TOWER AND THE AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- © INTERIOR GROUND RING: #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN
- D BOND TO INTERIOR GROUND RING: #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE
- $\underbrace{ \begin{array}{c} \text{GROUND ROD:} \\ \text{RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES.} \end{array} }_{\text{ROUND RING CONDUCTOR.}} \text{UL LISTED COPPER CLAD STEEL.} \\ \text{MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.} \\ \text{RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES.} \\ \text{GROUND RING CONDUCTOR.} \\ \end{array}$
- CELL REFERENCE GROUND BAR: POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (G) HATCH PLATE GROUND BAR: BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- H <u>Exterior cable entry port ground bars:</u> Located at the entrance to the cell site building. Bond to ground ring with a #2 awg solid tinned copper conductors with an exothermic weld and
- (I) TELCO GROUND BAR: BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- J FRAME BONDING: THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- K <u>Interior unit Bonds:</u> Metal frames, cabinets and individual metallic units located with the area of the interior ground ring require a #6 awg stranded green insulated copper bond to the
- L FENCE AND GATE GROUNDING: METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- M EXTERIOR UNIT BONDS: METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- N ICE BRIDGE SUPPORTS: EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED
- O DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR
- (P) TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO TOWER STEEL.

REFER TO DISH Wireless L.L.C. GROUNDING NOTES.

5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

ı	DRAWN	BY:	CHECKED	BY:	APPROVED	BY
ı	NGN		BLJ		BLJ	

RFDS REV #

PRELIMINARY DOCUMENTS

SUBMITTALS						
REV	DATE	DESCRIPTION				
Α	12/21/21	ISSUED FOR REVIEW				
0 01	01/07/22	ISSUED FOR CONSTRUCTION				
A&F PROJECT NUMBER						

101023.004.01

DISH Wireless L.L.C. PROJECT INFORMATION

BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

SHEET TITLE

GROUNDING PLANS AND NOTES


SHEET NUMBER


G-1


NO SCALE


GROUNDING KEY NOTES

NO SCALE











5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
NGN		BLJ		BLJ	

RFDS REV #:

PRELIMINARY DOCUMENTS

ı			SUBMITTALS					
1		REV	DATE	DESCRIPTION				
ı		Α	12/21/21	ISSUED FOR REVIEW				
ı		0	01/07/22	ISSUED FOR CONSTRUCTION				
ı								
ı								
ı								
ı								
ı								
ı		145 000 1507 11111050						

A&E PROJECT NUMBER

101023.004.01


BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

> SHEET TITLE RF

CABLE COLOR CODE

SHEET NUMBER

RF-1



dish wireless.

5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
NGN	7	BLJ		BLJ	

RFDS REV #:

PRELIMINARY DOCUMENTS

			SUBMITTALS				
	REV	DATE	DESCRIPTION				
П	Α	12/21/21	ISSUED FOR REVIEW				
	0	01/07/22	ISSUED FOR CONSTRUCTION				

A&E PROJECT NUMBER

101023.004.01

PROJECT INFORMATIO

BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

SHEET TITLE

LEGEND AND ABBREVIATIONS

SHEET NUMBER

GN-1

SITE ACTIVITY REQUIREMENTS:

- 1. NOTICE TO PROCEED NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
- 2. "LOOK UP" DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:

THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH WIReless L.L.C. AND DISH WIRELSS L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.

- 3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
- 4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH WIFELESS L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
- 5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
- 6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- 7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- 8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- 9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
- 10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- 11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
- 12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
- 13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH WIReless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
- 14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
- 15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
- 16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
- 17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
- 18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
- 19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
- 20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
- 22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:

CONTRACTOR: GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION

CARRIER:DISH Wireless L.L.C.

TOWER OWNER:TOWER OWNER

- 2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- 3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
- 4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
- 5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
- 6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
- 7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- 8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
- 9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- 10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION
- 11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS
- 12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
- 13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

1	DRAWN BY:	CHECKED BY:	APPROVED BY:
١	NGN	BLJ	BLJ

RFDS REV #:

PRELIMINARY DOCUMENTS

SUBMITTALS

REV DATE DESCRIPTION

A 12/21/21 ISSUED FOR REVIEW

O 01/07/22 ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

101023.004.01

BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-2

DISH Wireless L.L.C. TEMPLATE VERSION 45 - 10/08/2021

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

- 1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST—IN—PLACE CONCRETE.
- 2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
- 3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (1'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90'f AT TIME OF PLACEMENT.
- 4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
- 5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:

#4 BARS AND SMALLER 40 ksi

#5 BARS AND LARGER 60 ksi

- 6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
- CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
- CONCRETE EXPOSED TO EARTH OR WEATHER:
- #6 BARS AND LARGER 2"
- #5 BARS AND SMALLER 1-1/2"
- CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
- SLAB AND WALLS 3/4"
- BEAMS AND COLUMNS 1-1/2"
- 7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

- 1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
- 2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE FLIMINATED.
- 3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
- 4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
- 5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR—CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
- 6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
- 7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
- 8. TIE WRAPS ARE NOT ALLOWED
- 9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
- 12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
- 14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
- 15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

- . ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
- 17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
- 18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEFDED.
- 19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION—TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
- 20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE
- 21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
- 22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
- 23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- 24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY—COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS
- 25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY—COATED OR NON—CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- 26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- 27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
- 28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
- 29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
- 30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

ı	DRAWN	BY:	CHECKED	BY:	APPROVED	BY
ı	NGN	ı	BLJ		BLJ	

RFDS REV #:

PRELIMINARY DOCUMENTS

SUBMITTALS					
REV	DATE	DESCRIPTION			
Α	12/21/21	ISSUED FOR REVIEW			
0	01/07/22	ISSUED FOR CONSTRUCTION			
A&E PROJECT NUMBER					

101023.004.01

BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-3

DISH Wireless L.L.C. TEMPLATE VERSION 45 - 10/08/2021

101023.004.01_CT01725-A_Bloomfield_CT11162B SBA Dish CDs Dish Wireless_SST_12.13.21 Drawing1.dwg - SheetSN-3 - User: brandon.jones - Jan 07, 2022 -

GROUNDING NOTES:

- 1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
- 2. THE CONTRACTOR SHALL PERFORM IEEE FALL—OF—POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
- 3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
- 4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
- 5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
- 6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
- 7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
- 8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
- 9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
- 10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
- 11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
- 12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
- 13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
- 14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
- 15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
- 16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
- 17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
- 18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
- 19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
- 20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON—METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD—WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
- 21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC. PEC.0001564 Expires 2/10/22

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
NGN	1	BLJ		BLJ	

RFDS REV #:

PRELIMINARY DOCUMENTS

	SUBMITTALS							
	REV	DATE	DESCRIPTION					
П	Α	12/21/21	ISSUED FOR REVIEW					
П	0	01/07/22	ISSUED FOR CONSTRUCTION					
П								
П								
П								
	AA E DDO JEOT AUUNDED							

A&E PROJECT NUMBER

101023.004.01

DISH Wireless L.L. PROJECT INFORMAT

BOBDL00022B 1021 BLUE HILLS AVENUE BLOOMFIELD, CT 06002

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GN-4

DISH Wireless L.L.C. TEMPLATE VERSION 45 - 10/08/2021