Crown Castle
3530 Toringdon Way
Suite 300
Charlotte, NC 28277

Tel: 704-405-6600

www.crowncastle.com

March 21, 2014

Melanie A. Bachman
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: **Sprint PCS-Exempt Modification - Crown Site BU: 876316**
Sprint PCS Site ID: CT03XC021
Located at: 21 Acorn Road, Branford, CT 06405

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies ("R.C.S.A."), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Mr. James B. Cosgrove, First Selectman of the Town of Branford.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **21 Acorn Road, Branford, CT 06405**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint's operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes ("C.G.S.") § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint's additional antennas will be located at the same elevation on the existing tower.

2. There will be no proposed modifications to the ground and no extension of boundaries.

3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.

5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,

Jeff Barbadora
Real Estate Specialist

Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes
Tab 2: Exhibit-2: Structural Modification Report
Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mr. James B. Cosgrove, First Selectman
Town of Branford
1019 Main Street
Branford, CT 06405

Sprint

CROWN CASTLE

PROJECT:	2.5 EQUIPMENT DEPLOYMENT
SITE NAME:	SECONDINO PROPERTY
SITE CASCADE:	CT03XC021
SITE NUMBER:	876316
SITE ADDRESS:	21 ACORN ROAD BRANFORD, CT 06405
SITE TYPE:	MONOPOLE TOWER
MARKET:	SOUTHERN CONNECTICUT

SITE INFORMATION

TOWER OWNER:
CROWN CASTLE (GLOBAL SIGNAL)
2000 CORPORATE DRIVE
CANONSBURG, PA 15317

LATITUDE (NAD83):
41° 17' 35.06" N
41.293087°

LONGITUDE (NAD83):
72° 45' 46.4" W
-72.76289°

COUNTY:
NEW HAVEN

ZONING JURISDICTION:
TOWN OF BRANFORD

ZONING DISTRICT:
TBD

POWER COMPANY:
TBD

AAV PROVIDER:
TBD

SPRINT CM:
GARY WOOD
GARY.WOOD@SPRINT.COM

CROWN CASTLE CM:
HARRY ATHAN
(518) 380-0041
HTAMANAGEMENT@NYCAP.RR.COM

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRU'S TO TOWER
- INSTALL (27) JUMPER CABLES
- INSTALL (1) FIBER CABLE
- INSTALL (4) BATTERIES IN EXISTING BBU CABINET

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

APPLICABLE CODES

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

1. INTERNATIONAL BUILDING CODE (2012 IBC)
2. TIA-EIA-222-F OR LATEST EDITION
3. NFPA 780 – LIGHTNING PROTECTION CODE
4. 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
6. CT BUILDING CODE
7. LOCAL BUILDING CODE
8. CITY/COUNTY ORDINANCES

811 Know what's below. Call before you dig. www.call811.com

DRAWING INDEX

SHEET NO:	SHEET TITLE	REV
T-1	TITLE SHEET & PROJECT DATA	B
SP-1	SPRINT SPECIFICATIONS	B
SP-2	SPRINT SPECIFICATIONS	B
SP-3	SPRINT SPECIFICATIONS	B
A-1	SITE PLAN	B
A-2	TOWER ELEVATION & CABLE PLAN	B
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	B
A-4	COLOR CODING & NOTES	B
A-5	EQUIPMENT & MOUNTING DETAILS	B
A-6	CIVIL DETAILS	B
A-7	PLUMBING DIAGRAM	B
E-1	ELECTRICAL & GROUNDING PLAN	B
E-2	ELECTRICAL & GROUNDING DETAILS	B

PLANS PREPARED FOR:
Sprint
6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:
CROWN CASTLE

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:
SECONDINO PROPERTY

SITE CASCADE:
CT03XC021

SITE ADDRESS:
21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:
TITLE SHEET & PROJECT DATA

SHEET NUMBER:
T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:

1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY –GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – "NEC") AND NFPA 101 (LIFE SAFETY CODE).
5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
7. AMERICAN CONCRETE INSTITUTE (ACI)
8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
11. PORTLAND CEMENT ASSOCIATION (PCA)
12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
13. BRICK INDUSTRY ASSOCIATION (BIA)
14. AMERICAN WELDING SOCIETY (AWS)
15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
17. DOOR AND HARDWARE INSTITUTE (DHI)
18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.

B. COMPANY: SPRINT CORPORATION

C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.

D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.

E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.

F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.

G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.

B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.

C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 RECEIPT OF MATERIAL AND EQUIPMENT:

A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:

1 ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.

2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.

3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.

4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.

5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.

6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 DELIVERABLES:

A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.

B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 NOTICE TO PROCEED

A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.

B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

TOWER OWNER NOTIFICATION
ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 FUNCTIONAL REQUIREMENTS:

A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.

B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.

C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES

D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.

B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.

C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.

1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.

D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER

B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.

1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 – SUBMITTALS & TESTS

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 SUBMITTALS:

A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.

B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.

1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
5. CHEMICAL GROUNDING DESIGN

D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.

B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.

C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING;

1. AZIMUTH, DOWNTILT, AGL – UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
3. ALL AVAILABLE JURISDICTIONAL INFORMATION
4. PDF SCAN OF REDLINES PRODUCED IN FIELD
5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.

B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS – ANTENNALIGN ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT JOHN S. STEVENS No. 24705 LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
11. ALL AVAILABLE JURISDICTIONAL INFORMATION
12. PDF SCAN OF REDLINES PRODUCED IN FIELD

C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.

D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.

3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.

A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.

1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
2. STRUCTURAL BACKFILL COMPACTION REPORTS.
3. SITE RESISTANCE TO EARTH TEST.
4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".

B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;

1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS – PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
6. SITE LAYOUT – PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 – SUBMITTALS & TESTS

PART 1 – GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 WEEKLY REPORTS:

A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.

B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 PROJECT CONFERENCE CALLS:

A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 PROJECT TRACKING IN SMS:

A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

3.4 ADDITIONAL REPORTING:

A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 PROJECT PHOTOGRAPHS:

A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:

1. 1SHELTER AND TOWER OVERVIEW.
2. TOWER FOUNDATION(S) – FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
5. PHOTOS OF TOWER SECTION STACKING.
6. CONCRETE TESTING / SAMPLES.
7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
11. COAX CABLE ENTRY INTO SHELTER.
12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
25. ALL BTS GROUND CONNECTIONS.
26. ALL GROUND TEST WELLS.
27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
30. GPS ANTENNAS.
31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
32. DOGHOUSE/CABLE EXIT FROM ROOF.
33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
34. MASTER BUS BAR.
35. TELCO BOARD AND NIU.
36. ELECTRICAL DISTRIBUTION WALL.
37. CABLE ENTRY WITH SURGE SUPPRESSION.
38. ENTRANCE TO EQUIPMENT ROOM.
39. COAX WEATHERPROOFING-TOP AND BOTTOM OF TOWER.
40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
41. ANTENNA AND MAST GROUNDING.
42. LANDSCAPING – WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-3

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



2.5' 0 2.5' 5' 10'
(IN FEET)
SCALE: 24"x36" SHEET 1" = 5'-0"
SCALE: 11"x17" SHEET 1" = 10'-0"

OVERALL SITE PLAN | SCALE: AS NOTED | 1

INSTALL (3) NEW RECTIFIERS AND EQUIPMENT IN EXISTING CABINET INCLUDING BUT NOT LIMITED TO BASE BAND UNIT, CELL SITE ROUTER, SURGE ARRESTERS AND CONNECT POWER AND FIBER UNIT INSIDE EXISTING N.V. MMBS (SEE SHEET A-5 DETAIL 2)



1' 0 1' 2' 4'
(IN FEET)
SCALE: 24"x36" SHEET 1" = 2'-0"
SCALE: 11"x17" SHEET 1" = 4'-0"

SPRINT EQUIPMENT PLAN | SCALE: AS NOTED | 2

PLANS PREPARED FOR:

Sprint
6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

SITE PLAN

SHEET NUMBER:

A-1



NOTE:
SEE DETAIL 2 ON A-3 FOR ANTENNA LAYOUT

NOTE:
SPRINT TOWER TOP WORK CONTINGENT ON FOLLOWING: COMPLETION OF STRUCTURAL ANALYSIS PROVIDED BY CROWN CASTLE, COMPLETION OF ANTENNA/RRH MOUNTING ASSESSMENT (PROVIDED BY AE)

NOTE:
BASED ON THE ANALYSIS PROVIDED BY PAUL J FORD AND COMPANY, DATED 1/6/14, THE EXISTING STRUCTURE IS CAPABLE OF SUPPORTING THE PROPOSED EQUIPMENT CONFIGURATION. THE ANALYSIS INDICATES THE TOWER AND ITS FOUNDATION HAVE SUFFICIENT CAPACITY TO CARRY THE EXISTING, RESERVED, AND PROPOSED LOADS. NO MODIFICATIONS ARE REQUIRED AT THIS TIME.

NOTE:
CONTRACTOR SHALL NOT INSTALL THE 2.5 RRU'S SUCH THAT THEY IMPEDE CLIMBING ACCESS ON THE TOWER.

TOWER ELEVATION | NO SCALE | 1

DETAIL NOT USED | NO SCALE | 2

DETAIL NOT USED | NO SCALE | 3

DETAIL NOT USED | NO SCALE | 4

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

TOWER ELEVATION & CABLE PLAN

SHEET NUMBER:

A-2



EXISTING ANTENNA & RRU LAYOUT | NO SCALE | 1



THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.

NOTE:
SEE DETAIL 2 ON A-3
FOR ANTENNA LAYOUT

NOTE:
CONTRACTOR SHALL NOT INSTALL THE 2.5 RRU'S SUCH THAT THEY IMPEDE CLIMBING ACCESS ON THE TOWER.

NOTE:
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET

FINAL ANTENNA LAYOUT | NO SCALE | 2

DETAIL NOT USED | NO SCALE | 3



NOTES:

1. CUT DC CONDUCTORS TO LENGTH.
2. COIL FIBER CABLE AND SECURE AT SIDE OF RRU.
3. DO NO EXCEED BEND RADIUS.

NOTE:
CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.

NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS

TYPICAL ANTENNA & RRU MOUNTING DETAILS | NO SCALE | 4

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

ANTENNA LAYOUT & MOUNTING DETAILS

SHEET NUMBER:

A-3

NV CABLES				
BAND	INDICATOR		PORT	COLOR
800-1	YEL	GRN	NV-1	GRN
1900-1	YEL	RED	NV-2	BLU
1900-2	YEL	BRN	NV-3	BRN
1900-3	YEL	BLU	NV-4	WHT
1900-4	YEL	SLT	NV-5	RED
800-2	YEL	ORG	NV-6	SLT
SPARE	YEL	WHT	NV-7	PPL
2500	YEL	PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1		COLOR
YEL	WHT	GRN
YEL	WHT	BLU
YEL	WHT	BRN
YEL	WHT	WHT
YEL	WHT	RED
YEL	WHT	SLT
YEL	WHT	PPL
YEL	WHT	ORG

Figure 1: Antenna Orientation



NOTES:

1. ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.

2. THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.

3. A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.

4. THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.

5. SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.

6. HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.

7. HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.

8. INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Yellow	No Tape	No Tape
1	3	Brown	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Yellow	Yellow	No Tape
2	3	Brown	Brown	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Yellow	Yellow	Yellow
3	3	Brown	Brown	Brown
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL

Example – Sector 2, Cable 2, 800mhz Radio #1

Example – Sector 3, Cable 1, 1900mhz Radio #1

Example – Sector 1, Cable 4, 800 mhz Radio #1 and 1900mhz Radio #1

PLANS PREPARED FOR:
Sprint
6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:
CROWN CASTLE

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:
SECONDINO PROPERTY

SITE CASCADE:
CT03XC021

SITE ADDRESS:
21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:
COLOR CODING AND NOTES

SHEET NUMBER:
A-4

RRU: ALCATEL LUCENT TD-RRH8X20

COLOR: LIGHT GREY
WEIGHT: 70 LBS.



SIDE VIEW



FRONT VIEW



PLAN VIEW

NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN.

2.5 RRU'S | NO SCALE | 1



FRONT VIEW

NEW EQUIPMENT IN EXISTING CABINET | NO SCALE | 2

ANTENNA: RFS APXVTM14-C-I20

RADOME MATERIAL:	ASA
RADOME COLOR:	LIGHT GRAY
DIMENSIONS, HxWxD.in(mim):	56.3"x12.6"x6.3" (1430x320x160mm)
WEIGHT:	52.9 lbs
CONNECTORS:	(8) 4.1/9.5 DIN FEMALE (1) NF – CALIBRATION CONNECTOR



PLAN VIEW



2.5 ANTENNA | NO SCALE | 3

DETAIL NOT USED | NO SCALE | 4

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:

A-5

RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	**Hybrid cable** MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft
8 AWG Power	**Hybrid cable** MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
	MN: HB114-08U3M12-200F	200 ft
6 AWG Power	**Hybrid cable** MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	**Hybrid cable** MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	**Hybrid Jumper cable** MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	**Hybrid Jumper cable** MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	**Hybrid Jumper cable** MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	**Hybrid Jumper cable** MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.



4 AWG



B & 6 AWG



FIBER ONLY

2.5 CABLE CROSS SECTION DATA | NO SCALE | 1



FIBER JUNCTION BOX PENETRATION | NO SCALE | 2

DETAIL NOT USED | NO SCALE | 3

PLANS PREPARED FOR:
Sprint
6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:
CROWN CASTLE

ENGINEERING LICENSE:
STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:
SECONDINO PROPERTY

SITE CASCADE:
CT03XC021

SITE ADDRESS:
21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:
CIVIL DETAILS

SHEET NUMBER:
A-6



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLUMBING DIAGRAM | NO SCALE | 1

PLANS PREPARED FOR:

Sprint
6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER J53-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT · JOHN S. STEVENS · No. 24705 · LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

PLUMBING DIAGRAM

SHEET NUMBER:

A-7

PLAN NOT USED | NO SCALE | 1

LEGEND:

- G — EXISTING GROUND RING
- ■ CADWELD CONNECTION (EXOTHERMIC WELD)
- ▲ MECHANICAL CONNECTION
- ⊗ GROUND ROD
- ● CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN | NO SCALE | 2



NOTE:
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION.

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION) | NO SCALE | 3

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT
JOHN S. STEVENS
No. 24705
LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

ELECTRICAL & GROUNDING PLAN

SHEET NUMBER:

E-1

NOTES

CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
1	UTILITY SOURCE	METER/DISCONNECT	EXISTING
2	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
3	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
4	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
5	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

ELECTRICAL ONE–LINE DIAGRAM — NO SCALE — 1



NOTES

1. APPLY NO–OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR — NO SCALE — 2



TWO HOLE LUG — NO SCALE — 3

LEGEND:

- EXISTING GROUND RING
- CADWELD CONNECTION (EXOTHERMIC WELD)
- MECHANICAL CONNECTION
- GROUND ROD
- CABLE GROUND KIT

NOTE: USE #6 AWG BARE SOLID TINNED COPPER UNLESS NOTED OTHERWISE



GROUNDING RISER DIAGRAM — NO SCALE — 4

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353–000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:

STATE OF CONNECTICUT — JOHN S. STEVENS — No. 24705 — LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	02/20/14	MAP	B
ISSUED FOR REVIEW	01/10/14	MAP	A

SITE NAME:

SECONDINO PROPERTY

SITE CASCADE:

CT03XC021

SITE ADDRESS:

21 ACORN ROAD
BRANFORD, CT 06405

SHEET DESCRIPTION:

ELECTRICAL & GROUNDING DETAILS

SHEET NUMBER:

E-2

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street • Suite 600 • Columbus, Ohio 43215-3708

Date: **January 06, 2014**

Veronica Harris
Crown Castle
1200 McArthur Blvd
Mahwah, NJ 07430

Paul J. Ford and Company
250 East Broad Street, Suite 600
Columbus, Ohio 43215
614.221.6679

Subject: **Structural Analysis Report**

Carrier Designation:	***Sprint PCS* Co-Locate**	**Scenario 2.5B**
	Carrier Site Number:	CT03XC021
	Carrier Site Name:	SECONDINO PROPERTY
Crown Castle Designation:	**Crown Castle BU Number:**	876316
	Crown Castle Site Name:	SECONDINO PROPERTY
	Crown Castle JDE Job Number:	252021
	Crown Castle Work Order Number:	693423
	Crown Castle Application Number:	205526 Rev. 3
Engineering Firm Designation:	**Paul J. Ford Project Number:**	37514-0035
Site Data:	**21 Acorn Road, BRANFORD, New Haven County, CT** **Latitude *41° 17' 35.06"*, Longitude *-72° 45' 46.4"*** **147 Foot - Monopole Tower**	

Dear Veronica Harris,

Paul J. Ford is pleased to submit this **"Structural Analysis Report"** to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 606317, in accordance with application 205526, revision 3.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC5: Existing + Proposed Equipment **Sufficient Capacity**
Note: See Table I and Table II for the proposed and existing loading, respectively.

The structural analysis was performed for this tower in accordance with the requirements of the TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and the 2005 Connecticut Building Code using a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch ice thickness and 50 mph under service loads.

We at *Paul J. Ford* appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by:

Kevin Mahlum, EI
Structural Designer

tnxTower Report - version 6.1.3.1



JAN 0 7 2014

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street • Suite 600 • Columbus, Ohio 43215-3708

Date: **January 06, 2014**

Veronica Harris
Crown Castle
1200 McArthur Blvd
Mahwah, NJ 07430

Paul J. Ford and Company
250 East Broad Street, Suite 600
Columbus, Ohio 43215
614.221.6679

Subject: Structural Analysis Report

Carrier Designation:	***Sprint PCS* Co-Locate**	**Scenario 2.5B**
	Carrier Site Number:	CT03XC021
	Carrier Site Name:	SECONDINO PROPERTY
Crown Castle Designation:	**Crown Castle BU Number:**	876316
	Crown Castle Site Name:	SECONDINO PROPERTY
	Crown Castle JDE Job Number:	252021
	Crown Castle Work Order Number:	693423
	Crown Castle Application Number:	205526 Rev. 3
Engineering Firm Designation:	**Paul J. Ford Project Number:**	37514-0035
Site Data:	**21 Acorn Road, BRANFORD, New Haven County, CT** **Latitude *41° 17' 35.06"*, Longitude *-72° 45' 46.4"*** **147 Foot - Monopole Tower**	

Dear Veronica Harris,

Paul J. Ford is pleased to submit this **"Structural Analysis Report"** to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 606317, in accordance with application 205526, revision 3.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC5: Existing + Proposed Equipment **Sufficient Capacity**
Note: See Table I and Table II for the proposed and existing loading, respectively.

The structural analysis was performed for this tower in accordance with the requirements of the TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and the 2005 Connecticut Building Code using a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch ice thickness and 50 mph under service loads.

We at *Paul J. Ford* appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by:

Kevin Mahlum, EI
Structural Designer

TABLE OF CONTENTS

1) INTRODUCTION

This tower is a 147 ft Monopole tower designed by SUMMIT in August of 1997. The tower was originally designed for a wind speed of 90 mph per TIA/EIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of the TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and the 2005 Connecticut Building Code using a fastest mile wind speed of 85 mph with no ice, 37.6 mph with 0.75 inch ice thickness and 50 mph under service loads.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
147.0	147.0	3	alcatel lucent	800MHZ RRH	1	5/8	-
		3		TD-RRH8x20-25			
		3	rfs celwave	APXVTM14-C-120 w/ Pipe			

Table 2 - Existing Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
147.0	147.0	3	alcatel lucent	TME-800MHZ RRH	-	-	2
		3		1900MHz RRH (65MHz)	3	1-1/4	1
		3		800 EXTERNAL NOTCH FILTER			
		9	rfs celwave	ACU-A20-N			
		3		APXVSPP18-C-A20 w/ Pipe			
		1	tower mounts	Platform Mount [LP 712-1]			
	143.0	1		Miscellaneous (NA507-1)			
135.0	135.0	3	celwave	APXV18-206515L-03 w/ Pipe	6	1-5/8	1
		1	tower mounts	Pipe Mount [PM 601-3]			
126.0	126.0	1	tower mounts	Platform Mount [LP 712-1]	-	-	1
116.0	116.0	2	adc	ClearGain Dual Band 800/1900 MHz	12	1-5/8	1
		3	antel	BXA-171085-8BF-EDIN-2 w/ Pipe			
		3		BXA-70063-6CF-2 w/ Pipe			
		2		LPA-80063/6CF w/ Pipe			
		2		LPA-80080/4CF w/ Pipe			
		2	rfs celwave	APL868013 w/ Pipe			
		6		FD9R6004/2C-3L			
		1	tower mounts	Platform Mount [LP 712-1]			
106.0	108.0	6	ericsson	RRUS-11	1 12 1 2 1	3/8 1-1/4 Conduit 7/8 1/4	1
		3	kmw communications	AM-X-CD-14-65-00T-RET w/ Pipe			
		6	powerwave technologies	7770 w/ Pipe			
		12		LGP2140X			
		1	raycap	DC6-48-60-18-8F			
	106.0	1	tower mounts	Platform Mount [LP 712-1]			
80.0	81.0	1	kathreinscala	OG-860/1920/GPS-A	3	1/2	1
		2	lucent	KS24019-L112A			
	80.0	1	tower mounts	Side Arm Mount [SO 701-3]			

Notes:
1) Existing Equipment
2) Equipment To Be Removed

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	Dr. Clarence Welti, 12/16/1996	1529736	CCISITES
4-POST-MODIFICATION INSPECTION	PJF, 41708-0180, 03/15/2009	2417887	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	Summit, 2737, 09/29/1997	1632435	CCISITES
4-TOWER MANUFACTURER DRAWINGS	Summit, 2737-97, 09/29/1997	1632399	CCISITES

3.1) Analysis Method

tnxTower (version 6.1.3.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

1) Tower and structures were built in accordance with the manufacturer's specifications.
2) The tower and structures have been maintained in accordance with the manufacturer's specification.
3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
4) Monopole was reinforced in conformance with the referenced modification drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Paul J. Ford should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	147 - 105	Pole	TP29.141x22x0.25	1	-8.25	1075.85	53.7	Pass
L2	105 - 89.75	Pole	TP31.2343x28.0034x0.3125	2	-13.13	1471.82	77.4	Pass
L3	89.75 - 88.25	Pole	TP31.4893x31.2343x0.3125	3	-13.34	1464.66	80.6	Pass
L4	88.25 - 86	Pole	TP31.8719x31.4893x0.5085	4	-13.81	2314.39	54.3	Pass
L5	86 - 84.25	Pole	TP32.1695x31.8719x0.5063	5	-14.17	2304.61	56.6	Pass
L6	84.25 - 73.75	Pole	TP33.955x32.1695x0.455	6	-15.61	2207.19	66.4	Pass
L7	73.75 - 42.75	Pole	TP38.601x32.3223x0.537	7	-23.63	2922.04	77.5	Pass
L8	42.75 - 8.25	Pole	TP43.7172x36.6809x0.5757	8	-36.13	3650.30	86.7	Pass
L9	8.25 - 6.25	Pole	TP44.0573x43.7172x0.596	9	-36.79	3777.23	84.9	Pass
L10	6.25 - 0	Pole	TP45.12x44.0573x0.5918	10	-38.85	3837.49	86.7	Pass
							Summary	
						Pole (L10)	86.7	Pass
						Rating =	86.7	Pass

Table 5 - Tower Component Stresses vs. Capacity – LC5

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	87.4	Pass
1	Base Plate	0	65.6	Pass
1	Base Foundation Steel Interaction	0	53.9	Pass
1, 3	Base Foundation Soil Interaction	0	87.1	Pass

Structure Rating (max from all components) =	**87.4%**

Notes:

1) See additional documentation in “Appendix C – Additional Calculations” for calculations supporting the % capacity consumed.

2) Foundation Analysis Notes: According to the procedures prescribed and agreed to by the Crown Castle Engineering Foundation Committee, held in January 2010, the existing caisson foundation was analyzed using the methodology in the software ‘PLS-Caisson’ (Version 8.10, or newer, by Power Line Systems, Inc.). Per the methods in PLS-Caisson, the soil reactions of cohesive soils are calculated using 8CD independent of the depth of the soil layer. The depth of soil to be ignored at the top of the caisson is the greater of the geotechnical report’s recommendation, the frost depth of the site or half of the caisson diameter.

APPENDIX A

TNXTOWER OUTPUT

Tower Input Data

There is a pole section.
This tower is designed using the TIA/EIA-222-F standard.
The following design criteria apply:

Tower is located in New Haven County, Connecticut.
Basic wind speed of 85 mph.
Nominal ice thickness of 0.7500 in.
Ice thickness is considered to increase with height.
Ice density of 56 pcf.
A wind speed of 38 mph is used in combination with ice.
Deflections calculated using a wind speed of 50 mph.
A non-linear (P-delta) analysis was used.
Pressures are calculated at each section.
Stress ratio used in pole design is 1.333.
Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

	Consider Moments - Legs		Distribute Leg Loads As Uniform		Treat Feedline Bundles As Cylinder
	Consider Moments - Horizontals		Assume Legs Pinned		Use ASCE 10 X-Brace Ly Rules
	Consider Moments - Diagonals	√	Assume Rigid Index Plate		Calculate Redundant Bracing Forces
	Use Moment Magnification	√	Use Clear Spans For Wind Area		Ignore Redundant Members in FEA
√	Use Code Stress Ratios	√	Use Clear Spans For KL/r		SR Leg Bolts Resist Compression
√	Use Code Safety Factors - Guys		Retension Guys To Initial Tension		All Leg Panels Have Same Allowable
√	Escalate Ice	√	Bypass Mast Stability Checks		Offset Girt At Foundation
	Always Use Max Kz	√	Use Azimuth Dish Coefficients	√	Consider Feedline Torque
	Use Special Wind Profile	√	Project Wind Area of Appurt.		Include Angle Block Shear Check
	Include Bolts In Member Capacity		Autocalc Torque Arm Areas		Poles
	Leg Bolts Are At Top Of Section		SR Members Have Cut Ends	√	Include Shear-Torsion Interaction
	Secondary Horizontal Braces Leg		Sort Capacity Reports By Component		Always Use Sub-Critical Flow
	Use Diamond Inner Bracing (4 Sided)		Triangulate Diamond Inner Bracing		Use Top Mounted Sockets
	Add IBC .6D+W Combination		Use TIA-222-G Tension Splice Capacity Exemption		

Tapered Pole Section Geometry

Section	*Elevation*	*Section Length*	*Splice Length*	*Number of Sides*	*Top Diameter*	*Bottom Diameter*	*Wall Thickness*	*Bend Radius*	*Pole Grade*
	ft	*ft*	*ft*		*in*	*in*	*in*	*in*	
L1	147.00-105.00	42.00	3.75	18	22.0000	29.1410	0.2500	1.0000	A607-60 (60 ksi)
L2	105.00-89.75	19.00	0.00	18	28.0034	31.2343	0.3125	1.2500	A607-60 (60 ksi)
L3	89.75-88.25	1.50	0.00	18	31.2343	31.4893	0.3125	1.2500	Reinf 59.22 ksi (59 ksi)
L4	88.25-86.00	2.25	0.00	18	31.4893	31.8719	0.5085	2.0338	Reinf 57.17 ksi (57 ksi)
L5	86.00-84.25	1.75	0.00	18	31.8719	32.1695	0.5063	2.0252	Reinf 56.63 ksi (57 ksi)
L6	84.25-73.75	10.50	4.25	18	32.1695	33.9550	0.4550	1.8200	Reinf 58.30 ksi (58 ksi)
L7	73.75-42.75	35.25	4.75	18	32.3223	38.6010	0.5370	2.1481	Reinf 57.59 ksi (58 ksi)

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L8	42.75-8.25	39.25	0.00	18	36.6809	43.7172	0.5757	2.3026	Reinf 57.90 ksi (58 ksi)
L9	8.25-6.25	2.00	0.00	18	43.7172	44.0573	0.5960	2.3841	Reinf 57.44 ksi (57 ksi)
L10	6.25-0.00	6.25		18	44.0573	45.1200	0.5918	2.3670	Reinf 57.37 ksi (57 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in^2	I in^4	r in	C in	I/C in^3	J in^4	It/Q in^2	w in	w/t
L1	22.3394	17.2586	1031.4832	7.7212	11.1760	92.2945	2064.3237	8.6310	3.4320	13.728
	29.5905	22.9250	2417.5313	10.2563	14.8036	163.3067	4838.2436	11.4647	4.6888	18.755
L2	29.0829	27.4659	2660.7623	9.8303	14.2257	187.0387	5325.0257	13.7356	4.3786	14.012
	31.7161	30.6705	3704.9933	10.9772	15.8670	233.5029	7414.8618	15.3382	4.9472	15.831
L3	31.7161	30.6705	3704.9933	10.9772	15.8670	233.5029	7414.8618	15.3382	4.9472	15.831
	31.9751	30.9235	3797.4379	11.0678	15.9966	237.3905	7599.8725	15.4647	4.9921	15.975
L4	31.9751	49.9986	6062.9281	10.9982	15.9966	379.0139	12133.8339	25.0040	4.6472	9.14
	32.3636	50.6160	6290.3368	11.1340	16.1909	388.5095	12588.9506	25.3128	4.7146	9.272
L5	32.3636	50.4045	6264.9089	11.1348	16.1909	386.9390	12538.0613	25.2070	4.7184	9.319
	32.6658	50.8827	6444.9201	11.2404	16.3421	394.3749	12898.3205	25.4462	4.7707	9.423
L6	32.6658	45.8012	5820.0967	11.2587	16.3421	356.1409	11647.8516	22.9049	4.8610	10.684
	34.4788	48.3797	6859.4641	11.8925	17.2491	397.6699	13727.9542	24.1944	5.1753	11.374
L7	33.5896	54.1791	6915.4595	11.2838	16.4197	421.1676	13840.0186	27.0947	4.7436	8.833
	39.1965	64.8813	11876.4096	13.5127	19.6093	605.6516	23768.4465	32.4468	5.8486	10.891
L8	38.1114	65.9694	10864.7579	12.8173	18.6339	583.0647	21743.8119	32.9910	5.4427	9.455
	44.3916	78.8258	18535.2035	15.3152	22.2083	834.6056	37094.7960	39.4204	6.6811	11.606
L9	44.3916	81.5766	19163.9090	15.3080	22.2083	862.9151	38353.0344	40.7960	6.6452	11.149
	44.7369	82.2200	19620.9094	15.4287	22.3811	876.6732	39267.6364	41.1178	6.7051	11.25
L10	44.7369	81.6376	19485.7703	15.4303	22.3811	870.6351	38997.1804	40.8266	6.7126	11.344
	45.8160	83.6336	20950.2650	15.8075	22.9210	914.0221	41928.0969	41.8247	6.8996	11.66

Tower Elevation ft	Gusset Area (per face) ft^2	Gusset Thickness in	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
L1 147.00-105.00				1	1	1		
L2 105.00-89.75				1	1	1		
L3 89.75-88.25				1	1	1		
L4 88.25-86.00				1	1	1		
L5 86.00-84.25				1	1	1		
L6 84.25-73.75				1	1	1		
L7 73.75-				1	1	1		

Tower Elevation ft	Gusset Area (per face) ft^2	Gusset Thickness in	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
42.75								
L8 42.75-8.25				1	1	1		
L9 8.25-6.25				1	1	1		
L10 6.25-0.00				1	1	1		

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	Number Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
******										

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C_AA_A ft^2/ft	Weight plf
HB114-1-0813U4-M5J(1 1/4")	C	No	Inside Pole	147.00 - 0.00	3	No Ice	0.00	1.20
						1/2" Ice	0.00	1.20
						1" Ice	0.00	1.20
						2" Ice	0.00	1.20
						4" Ice	0.00	1.20
HB058-M12-XXXF(5/8")	C	No	CaAa (Out Of Face)	147.00 - 0.00	1	No Ice	0.08	0.24
						1/2" Ice	0.18	1.06
						1" Ice	0.28	2.49
						2" Ice	0.48	7.18
						4" Ice	0.88	23.89
***								
LDF7-50A (1-5/8 FOAM)	C	No	CaAa (Out Of Face)	135.00 - 0.00	1	No Ice	0.20	0.82
						1/2" Ice	0.30	2.33
						1" Ice	0.40	4.46
						2" Ice	0.60	10.54
						4" Ice	1.00	30.04
LDF7-50A (1-5/8 FOAM)	C	No	CaAa (Out Of Face)	135.00 - 0.00	5	No Ice	0.00	0.82
						1/2" Ice	0.00	2.33
						1" Ice	0.00	4.46
						2" Ice	0.00	10.54
						4" Ice	0.00	30.04
***								
LDF7-50A (1-5/8 FOAM)	C	No	Inside Pole	116.00 - 0.00	12	No Ice	0.00	0.82
						1/2" Ice	0.00	0.82
						1" Ice	0.00	0.82
						2" Ice	0.00	0.82
						4" Ice	0.00	0.82
***								
LDF2-50A(3/8")	C	No	Inside Pole	106.00 - 0.00	1	No Ice	0.00	0.08
						1/2" Ice	0.00	0.08
						1" Ice	0.00	0.08
						2" Ice	0.00	0.08
						4" Ice	0.00	0.08
LDF6-50A (1-1/4 FOAM)	C	No	Inside Pole	106.00 - 0.00	12	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
						2" Ice	0.00	0.66
						4" Ice	0.00	0.66
2" (Nominal) Conduit	C	No	Inside Pole	106.00 - 0.00	1	No Ice	0.00	0.72
						1/2" Ice	0.00	0.72
						1" Ice	0.00	0.72
						2" Ice	0.00	0.72
						4" Ice	0.00	0.72

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C_AA_A ft^2/ft	Weight plf
VXL5-50 (7/8 FOAM)	C	No	Inside Pole	106.00 - 0.00	2	No Ice	0.00	0.29
						1/2" Ice	0.00	0.29
						1" Ice	0.00	0.29
						2" Ice	0.00	0.29
						4" Ice	0.00	0.29
LDF1-50A (1/4 FOAM)	C	No	Inside Pole	106.00 - 0.00	1	No Ice	0.00	0.06
						1/2" Ice	0.00	0.06
						1" Ice	0.00	0.06
						2" Ice	0.00	0.06
						4" Ice	0.00	0.06
***								
LDF4RN-50A (1/2 FOAM)	C	No	Inside Pole	80.00 - 0.00	3	No Ice	0.00	0.15
						1/2" Ice	0.00	0.15
						1" Ice	0.00	0.15
						2" Ice	0.00	0.15
						4" Ice	0.00	0.15
***								
Aero MP3-05	C	No	CaAa (Out Of Face)	90.50 - 0.00	1	No Ice	0.35	0.00
						1/2" Ice	0.40	0.00
						1" Ice	0.66	0.00
						2" Ice	0.88	0.00
						4" Ice	1.32	0.00
******								

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A_R ft^2	A_F ft^2	C_AA_A In Face ft^2	C_AA_A Out Face ft^2	Weight K
L1	147.00-105.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	9.468	0.43
L2	105.00-89.75	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	4.561	0.43
L3	89.75-88.25	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.945	0.04
L4	88.25-86.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	1.417	0.06
L5	86.00-84.25	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	1.102	0.05
L6	84.25-73.75	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	6.613	0.30
L7	73.75-42.75	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	19.524	0.88
L8	42.75-8.25	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	21.728	0.98
L9	8.25-6.25	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	1.260	0.06
L10	6.25-0.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	3.936	0.18

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft^2	A_F ft^2	C_AA_A In Face ft^2	C_AA_A Out Face ft^2	Weight K
L1	147.00-105.00	A	0.880	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	22.143	1.07
L2	105.00-89.75	A	0.854	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	10.116	0.74
L3	89.75-88.25	A	0.845	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	1.795	0.07
L4	88.25-86.00	A	0.843	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	2.689	0.11
L5	86.00-84.25	A	0.840	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	2.087	0.08
L6	84.25-73.75	A	0.833	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	12.452	0.50
L7	73.75-42.75	A	0.803	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	36.762	1.48
L8	42.75-8.25	A	0.750	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	39.968	1.62
L9	8.25-6.25	A	0.750	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	2.221	0.09
L10	6.25-0.00	A	0.750	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	6.939	0.28

Feed Line Center of Pressure

Section	Elevation ft	CP_X in	CP_Z in	CP_X Ice in	CP_Z Ice in
L1	147.00-105.00	-0.2715	0.1567	-0.5308	0.3065
L2	105.00-89.75	-0.3478	0.2008	-0.6517	0.3763
L3	89.75-88.25	-0.6593	0.3806	-1.0284	0.5938
L4	88.25-86.00	-0.6606	0.3814	-1.0308	0.5952
L5	86.00-84.25	-0.6619	0.3822	-1.0333	0.5966
L6	84.25-73.75	-0.6659	0.3845	-1.0403	0.6006
L7	73.75-42.75	-0.6757	0.3901	-1.0672	0.6161
L8	42.75-8.25	-0.6898	0.3983	-1.0892	0.6288
L9	8.25-6.25	-0.6979	0.4030	-1.0782	0.6225
L10	6.25-0.00	-0.6996	0.4039	-1.0825	0.6250

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral ft / Vert ft	Azimuth Adjustment °	Placement ft		C_AA_A Front ft^2	C_AA_A Side ft^2	Weight K
APXVSPP18-C-A20 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice	8.50 9.15 9.77 11.03 13.68	6.95 8.13 9.02 10.84 14.85	0.08 0.15 0.23 0.41 0.91

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C_AA_A Front ft^2	C_AA_A Side ft^2	Weight K
						4" Ice			
APXVSPP18-C-A20 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.50 9.15 9.77 11.03 13.68	6.95 8.13 9.02 10.84 14.85	0.08 0.15 0.23 0.41 0.91
APXVSPP18-C-A20 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.50 9.15 9.77 11.03 13.68	6.95 8.13 9.02 10.84 14.85	0.08 0.15 0.23 0.41 0.91
800 EXTERNAL NOTCH FILTER	A	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.77 0.89 1.02 1.30 1.97	0.37 0.46 0.56 0.79 1.34	0.01 0.02 0.02 0.04 0.11
800 EXTERNAL NOTCH FILTER	B	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.77 0.89 1.02 1.30 1.97	0.37 0.46 0.56 0.79 1.34	0.01 0.02 0.02 0.04 0.11
800 EXTERNAL NOTCH FILTER	C	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.77 0.89 1.02 1.30 1.97	0.37 0.46 0.56 0.79 1.34	0.01 0.02 0.02 0.04 0.11
(3) ACU-A20-N	A	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.08 0.12 0.17 0.30 0.67	0.14 0.19 0.25 0.40 0.80	0.00 0.00 0.00 0.01 0.04
(3) ACU-A20-N	B	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.08 0.12 0.17 0.30 0.67	0.14 0.19 0.25 0.40 0.80	0.00 0.00 0.00 0.01 0.04
(3) ACU-A20-N	C	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.08 0.12 0.17 0.30 0.67	0.14 0.19 0.25 0.40 0.80	0.00 0.00 0.00 0.01 0.04
1900MHz RRH (65MHz)	A	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.70 2.94 3.18 3.70 4.85	2.77 3.01 3.26 3.78 4.93	0.06 0.08 0.11 0.18 0.35
1900MHz RRH (65MHz)	B	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.70 2.94 3.18 3.70 4.85	2.77 3.01 3.26 3.78 4.93	0.06 0.08 0.11 0.18 0.35
1900MHz RRH (65MHz)	C	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice	2.70 2.94 3.18 3.70	2.77 3.01 3.26 3.78	0.06 0.08 0.11 0.18

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C_AA_A Front ft^2	C_AA_A Side ft^2	Weight K
						2" Ice 4" Ice	4.85	4.93	0.35
800MHZ RRH	A	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.49 2.71 2.93 3.41 4.46	2.07 2.27 2.48 2.93 3.93	0.05 0.07 0.10 0.16 0.32
800MHZ RRH	B	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.49 2.71 2.93 3.41 4.46	2.07 2.27 2.48 2.93 3.93	0.05 0.07 0.10 0.16 0.32
800MHZ RRH	C	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.49 2.71 2.93 3.41 4.46	2.07 2.27 2.48 2.93 3.93	0.05 0.07 0.10 0.16 0.32
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.13 7.66 8.18 9.26 11.53	4.96 5.75 6.47 8.01 11.41	0.08 0.13 0.19 0.34 0.75
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.13 7.66 8.18 9.26 11.53	4.96 5.75 6.47 8.01 11.41	0.08 0.13 0.19 0.34 0.75
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.13 7.66 8.18 9.26 11.53	4.96 5.75 6.47 8.01 11.41	0.08 0.13 0.19 0.34 0.75
TD-RRH8x20-25	A	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.72 5.01 5.32 5.95 7.31	1.70 1.92 2.15 2.62 3.68	0.07 0.10 0.13 0.20 0.40
TD-RRH8x20-25	B	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.72 5.01 5.32 5.95 7.31	1.70 1.92 2.15 2.62 3.68	0.07 0.10 0.13 0.20 0.40
TD-RRH8x20-25	C	From Leg	4.00 0.00 0.00	0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.72 5.01 5.32 5.95 7.31	1.70 1.92 2.15 2.62 3.68	0.07 0.10 0.13 0.20 0.40
Platform Mount [LP 712-1]	C	None		0.0000	147.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	24.53 29.94 35.35 46.17 67.81	24.53 29.94 35.35 46.17 67.81	1.34 1.65 1.96 2.58 3.82
Miscellaneous (NA507-1)	C	From Leg	0.00 0.00 -4.00	0.0000	147.00	No Ice 1/2" Ice	4.80 6.70 8.60	4.80 6.70 8.60	0.25 0.29 0.34

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C_AA_A Front ft^2	C_AA_A Side ft^2	Weight K
						1" Ice	12.40	12.40	0.44
						2" Ice	20.00	20.00	0.64
						4" Ice			
***									
Celwave APXV18-206515L-03 w/Mount Pipe	A	From Face	0.50 0.00 0.00	0.0000	135.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	3.48 3.90 4.31 5.23 7.27	3.24 3.97 4.64 6.03 9.01	0.04 0.07 0.11 0.21 0.51
Celwave APXV18-206515L-03 w/Mount Pipe	B	From Face	0.50 0.00 0.00	0.0000	135.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	3.48 3.90 4.31 5.23 7.27	3.24 3.97 4.64 6.03 9.01	0.04 0.07 0.11 0.21 0.51
Celwave APXV18-206515L-03 w/Mount Pipe	C	From Face	0.50 0.00 0.00	0.0000	135.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	3.48 3.90 4.31 5.23 7.27	3.24 3.97 4.64 6.03 9.01	0.04 0.07 0.11 0.21 0.51
Pipe Mount [PM 601-3]	C	None		0.0000	135.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.39 5.48 6.57 8.75 13.11	4.39 5.48 6.57 8.75 13.11	0.20 0.24 0.28 0.36 0.53
***									
(4) 2.375" OD x 6' Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	126.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.43 1.92 2.29 3.06 4.70	1.43 1.92 2.29 3.06 4.70	0.03 0.04 0.05 0.09 0.23
(4) 2.375" OD x 6' Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	126.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.43 1.92 2.29 3.06 4.70	1.43 1.92 2.29 3.06 4.70	0.03 0.04 0.05 0.09 0.23
(4) 2.375" OD x 6' Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	126.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.43 1.92 2.29 3.06 4.70	1.43 1.92 2.29 3.06 4.70	0.03 0.04 0.05 0.09 0.23
Platform Mount [LP 712-1]	C	None		0.0000	126.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	24.53 29.94 35.35 46.17 67.81	24.53 29.94 35.35 46.17 67.81	1.34 1.65 1.96 2.58 3.82
***									
(2) LPA-80080/4CF w/ Mount Pipe	A	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	2.86 3.22 3.59 4.45 6.32	7.23 7.92 8.63 10.11 13.34	0.03 0.08 0.13 0.25 0.61
(2) LPA-80063/6CF w/ Mount Pipe	B	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice	10.58 11.24 11.87 13.16 15.87	10.67 11.93 12.91 14.92 19.16	0.05 0.14 0.25 0.48 1.09

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C_AA_A Front ft^2	C_AA_A Side ft^2	Weight K
						4" Ice			
(2) APL868013 w/ Mount Pipe	C	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	3.10 3.48 3.88 4.76 6.66	4.92 5.60 6.28 7.71 10.83	0.02 0.06 0.11 0.22 0.54
BXA-70063-6CF-2 w/ Mount Pipe	A	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.97 8.61 9.22 10.46 13.07	5.80 6.95 7.82 9.60 13.37	0.04 0.10 0.17 0.34 0.80
BXA-70063-6CF-2 w/ Mount Pipe	B	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.97 8.61 9.22 10.46 13.07	5.80 6.95 7.82 9.60 13.37	0.04 0.10 0.17 0.34 0.80
BXA-70063/6CF-2 w/ Mount Pipe	C	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.97 8.61 9.22 10.46 13.07	5.40 6.55 7.41 9.18 12.93	0.04 0.10 0.17 0.33 0.79
BXA-171085-8BF-EDIN-2 w/ Mount Pipe	A	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	3.18 3.56 3.97 4.86 6.77	3.35 3.97 4.60 5.90 8.89	0.03 0.06 0.10 0.19 0.49
BXA-171085-8BF-EDIN-2 w/ Mount Pipe	B	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	3.18 3.56 3.97 4.86 6.77	3.35 3.97 4.60 5.90 8.89	0.03 0.06 0.10 0.19 0.49
BXA-171085-8BF-EDIN-2 w/ Mount Pipe	C	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	3.18 3.56 3.97 4.86 6.77	3.35 3.97 4.60 5.90 8.89	0.03 0.06 0.10 0.19 0.49
(2) FD9R6004/2C-3L	A	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.37 0.45 0.54 0.75 1.28	0.08 0.14 0.20 0.34 0.74	0.00 0.01 0.01 0.02 0.06
(2) FD9R6004/2C-3L	B	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.37 0.45 0.54 0.75 1.28	0.08 0.14 0.20 0.34 0.74	0.00 0.01 0.01 0.02 0.06
(2) FD9R6004/2C-3L	C	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	0.37 0.45 0.54 0.75 1.28	0.08 0.14 0.20 0.34 0.74	0.00 0.01 0.01 0.02 0.06
(2) ClearGain Dual Band 800/1900 MHz	B	From Face	4.00 0.00 0.00	0.0000	116.00	No Ice 1/2" Ice 1" Ice	1.54 1.71 1.89 2.27	0.80 0.94 1.08 1.39	0.02 0.03 0.05 0.08

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C_AA_A Front ft^2	C_AA_A Side ft^2	Weight K
						2" Ice	3.14	2.11	0.18
						4" Ice			
Platform Mount [LP 712-1]	C	None		0.0000	116.00	No Ice	24.53	24.53	1.34
						1/2" Ice	29.94	29.94	1.65
						1" Ice	35.35	35.35	1.96
						2" Ice	46.17	46.17	2.58
						4" Ice	67.81	67.81	3.82
***									
(2) Powerwave Technologies 7770 w/ Mount Pipe	A	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	6.01	4.42	0.07
						1/2" Ice	6.46	5.08	0.12
						1" Ice	6.93	5.74	0.18
						2" Ice	7.89	7.13	0.32
						4" Ice	9.94	10.41	0.70
(2) Powerwave Technologies 7770 w/ Mount Pipe	B	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	6.01	4.42	0.07
						1/2" Ice	6.46	5.08	0.12
						1" Ice	6.93	5.74	0.18
						2" Ice	7.89	7.13	0.32
						4" Ice	9.94	10.41	0.70
(2) Powerwave Technologies 7770 w/ Mount Pipe	C	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	6.01	4.42	0.07
						1/2" Ice	6.46	5.08	0.12
						1" Ice	6.93	5.74	0.18
						2" Ice	7.89	7.13	0.32
						4" Ice	9.94	10.41	0.70
AM-X-CD-14-65-00T-RET w/ Mount Pipe	A	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	5.74	4.02	0.03
						1/2" Ice	6.20	4.63	0.08
						1" Ice	6.66	5.28	0.13
						2" Ice	7.62	6.68	0.25
						4" Ice	9.67	9.74	0.61
AM-X-CD-14-65-00T-RET w/ Mount Pipe	B	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	5.74	4.02	0.03
						1/2" Ice	6.20	4.63	0.08
						1" Ice	6.66	5.28	0.13
						2" Ice	7.62	6.68	0.25
						4" Ice	9.67	9.74	0.61
AM-X-CD-14-65-00T-RET w/ Mount Pipe	C	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	5.74	4.02	0.03
						1/2" Ice	6.20	4.63	0.08
						1" Ice	6.66	5.28	0.13
						2" Ice	7.62	6.68	0.25
						4" Ice	9.67	9.74	0.61
(4) Powerwave Technologies LGP2140X	A	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	1.23	0.37	0.02
						1/2" Ice	1.38	0.48	0.02
						1" Ice	1.54	0.60	0.03
						2" Ice	1.89	0.87	0.06
						4" Ice	2.69	1.51	0.14
(4) Powerwave Technologies LGP2140X	B	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	1.23	0.37	0.02
						1/2" Ice	1.38	0.48	0.02
						1" Ice	1.54	0.60	0.03
						2" Ice	1.89	0.87	0.06
						4" Ice	2.69	1.51	0.14
(4) Powerwave Technologies LGP2140X	C	From Face	4.00 0.00 2.00	0.0000	106.00	No Ice	1.23	0.37	0.02
						1/2" Ice	1.38	0.48	0.02
						1" Ice	1.54	0.60	0.03
						2" Ice	1.89	0.87	0.06
						4" Ice	2.69	1.51	0.14
DC6-48-60-18-8F	A	From Face	4.00 0.00	0.0000	106.00	No Ice	2.57	2.57	0.02
						1/2"	2.80	2.80	0.04

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C_AA_A Front ft^2	C_AA_A Side ft^2	Weight K
			2.00			Ice	3.04	3.04	0.07
						1" Ice	3.54	3.54	0.13
						2" Ice	4.66	4.66	0.30
						4" Ice			
(2) RRUS-11	A	From Face	4.00	0.0000	106.00	No Ice	3.25	1.37	0.05
			0.00			1/2"	3.49	1.55	0.07
			2.00			Ice	3.74	1.74	0.09
						1" Ice	4.27	2.14	0.15
						2" Ice	5.43	3.04	0.31
						4" Ice			
(2) RRUS-11	B	From Face	4.00	0.0000	106.00	No Ice	3.25	1.37	0.05
			0.00			1/2"	3.49	1.55	0.07
			2.00			Ice	3.74	1.74	0.09
						1" Ice	4.27	2.14	0.15
						2" Ice	5.43	3.04	0.31
						4" Ice			
(2) RRUS-11	C	From Face	4.00	0.0000	106.00	No Ice	3.25	1.37	0.05
			0.00			1/2"	3.49	1.55	0.07
			2.00			Ice	3.74	1.74	0.09
						1" Ice	4.27	2.14	0.15
						2" Ice	5.43	3.04	0.31
						4" Ice			
Platform Mount [LP 712-1]	C	None		0.0000	106.00	No Ice	24.53	24.53	1.34
						1/2"	29.94	29.94	1.65
						Ice	35.35	35.35	1.96
						1" Ice	46.17	46.17	2.58
						2" Ice	67.81	67.81	3.82
						4" Ice			
***									
KS24019-L112A	A	From Face	3.00	0.0000	80.00	No Ice	0.10	0.10	0.01
			0.00			1/2"	0.18	0.18	0.01
			1.00			Ice	0.26	0.26	0.01
						1" Ice	0.42	0.42	0.01
						2" Ice	0.74	0.74	0.02
						4" Ice			
Kathrein OG-860/1920/GPS-A	B	From Face	3.00	0.0000	80.00	No Ice	0.14	0.14	0.00
			0.00			1/2"	0.23	0.23	0.00
			1.00			Ice	0.33	0.33	0.01
						1" Ice	0.57	0.57	0.02
						2" Ice	1.17	1.17	0.05
						4" Ice			
KS24019-L112A	C	From Face	3.00	0.0000	80.00	No Ice	0.10	0.10	0.01
			0.00			1/2"	0.18	0.18	0.01
			1.00			Ice	0.26	0.26	0.01
						1" Ice	0.42	0.42	0.01
						2" Ice	0.74	0.74	0.02
						4" Ice			
Side Arm Mount [SO 701-3]	C	None		0.0000	80.00	No Ice	2.83	2.83	0.20
						1/2"	3.92	3.92	0.24
						Ice	5.01	5.01	0.28
						1" Ice	7.19	7.19	0.36
						2" Ice	11.55	11.55	0.53
						4" Ice			
******									

Tower Pressures - No Ice

G_H = 1.690

Section Elevation ft	z ft	K_Z	q_z psf	A_G ft²	Face	A_F ft²	A_R ft²	A_{leg} ft²	Leg %	C_AA_A In Face ft²	C_AA_A Out Face ft²
L1 147.00-105.00	125.27	1.464	27	89.497	A	0.000	89.497	89.497	100.00	0.000	0.000
					B	0.000	89.497		100.00	0.000	0.000
					C	0.000	89.497		100.00	0.000	9.468
L2 105.00-89.75	97.26	1.362	25	38.046	A	0.000	38.046	38.046	100.00	0.000	0.000
					B	0.000	38.046		100.00	0.000	0.000
					C	0.000	38.046		100.00	0.000	4.561
L3 89.75-88.25	89.00	1.328	25	3.920	A	0.000	3.920	3.920	100.00	0.000	0.000
					B	0.000	3.920		100.00	0.000	0.000
					C	0.000	3.920		100.00	0.000	0.945
L4 88.25-86.00	87.12	1.32	24	5.940	A	0.000	5.940	5.940	100.00	0.000	0.000
					B	0.000	5.940		100.00	0.000	0.000
					C	0.000	5.940		100.00	0.000	1.417
L5 86.00-84.25	85.12	1.311	24	4.670	A	0.000	4.670	4.670	100.00	0.000	0.000
					B	0.000	4.670		100.00	0.000	0.000
					C	0.000	4.670		100.00	0.000	1.102
L6 84.25-73.75	78.95	1.283	24	28.929	A	0.000	28.929	28.929	100.00	0.000	0.000
					B	0.000	28.929		100.00	0.000	0.000
					C	0.000	28.929		100.00	0.000	6.613
L7 73.75-42.75	58.15	1.176	22	92.587	A	0.000	92.587	92.587	100.00	0.000	0.000
					B	0.000	92.587		100.00	0.000	0.000
					C	0.000	92.587		100.00	0.000	19.524
L8 42.75-8.25	25.10	1	19	116.796	A	0.000	116.796	116.796	100.00	0.000	0.000
					B	0.000	116.796		100.00	0.000	0.000
					C	0.000	116.796		100.00	0.000	21.728
L9 8.25-6.25	7.25	1	18	7.315	A	0.000	7.315	7.315	100.00	0.000	0.000
					B	0.000	7.315		100.00	0.000	0.000
					C	0.000	7.315		100.00	0.000	1.260
L10 6.25-0.00	3.11	1	18	23.223	A	0.000	23.223	23.223	100.00	0.000	0.000
					B	0.000	23.223		100.00	0.000	0.000
					C	0.000	23.223		100.00	0.000	3.936

Tower Pressure - With Ice

G_H = 1.690

Section Elevation ft	z ft	K_Z	q_z psf	t_Z in	A_G ft²	Face	A_F ft²	A_R ft²	A_{leg} ft²	Leg %	C_AA_A In Face ft²	C_AA_A Out Face ft²
L1 147.00-105.00	125.27	1.464	5	0.8802	95.658	A	0.000	95.658	95.658	100.00	0.000	0.000
						B	0.000	95.658		100.00	0.000	0.000
						C	0.000	95.658		100.00	0.000	22.143
L2 105.00-89.75	97.26	1.362	5	0.8539	40.283	A	0.000	40.283	40.283	100.00	0.000	0.000
						B	0.000	40.283		100.00	0.000	0.000
						C	0.000	40.283		100.00	0.000	10.116
L3 89.75-88.25	89.00	1.328	5	0.8448	4.131	A	0.000	4.131	4.131	100.00	0.000	0.000
						B	0.000	4.131		100.00	0.000	0.000
						C	0.000	4.131		100.00	0.000	1.795
L4 88.25-86.00	87.12	1.32	5	0.8427	6.256	A	0.000	6.256	6.256	100.00	0.000	0.000
						B	0.000	6.256		100.00	0.000	0.000
						C	0.000	6.256		100.00	0.000	2.689
L5 86.00-84.25	85.12	1.311	5	0.8403	4.915	A	0.000	4.915	4.915	100.00	0.000	0.000
						B	0.000	4.915		100.00	0.000	0.000
						C	0.000	4.915		100.00	0.000	2.087
L6 84.25-73.75	78.95	1.283	5	0.8328	30.387	A	0.000	30.387	30.387	100.00	0.000	0.000
						B	0.000	30.387		100.00	0.000	0.000
						C	0.000	30.387		100.00	0.000	12.452
L7 73.75-42.75	58.15	1.176	4	0.8028	96.890	A	0.000	96.890	96.890	100.00	0.000	0.000
						B	0.000	96.890		100.00	0.000	0.000
						C	0.000	96.890		100.00	0.000	36.762
L8 42.75-8.25	25.10	1	4	0.7500	121.412	A	0.000	121.412	121.412	100.00	0.000	0.000
						B	0.000	121.412		100.00	0.000	0.000
						C	0.000	121.412		100.00	0.000	39.968
L9 8.25-6.25	7.25	1	4	0.7500	7.565	A	0.000	7.565	7.565	100.00	0.000	0.000
						B	0.000	7.565		100.00	0.000	0.000

Section Elevation ft	z ft	K_Z	q_z psf	t_Z in	A_G ft²	Face	A_F ft²	A_R ft²	A_{leg} ft²	Leg %	C_AA_A In Face ft²	C_AA_A Out Face ft²
L10 6.25-0.00	3.11	1	4	0.7500	24.005	C	0.000	7.565		100.00	0.000	2.221
						A	0.000	24.005	24.005	100.00	0.000	0.000
						B	0.000	24.005		100.00	0.000	0.000
						C	0.000	24.005		100.00	0.000	6.939

Tower Pressure - Service

G_H = 1.690

Section Elevation ft	z ft	K_Z	q_z psf	A_G ft²	Face	A_F ft²	A_R ft²	A_{leg} ft²	Leg %	C_AA_A In Face ft²	C_AA_A Out Face ft²
L1 147.00-105.00	125.27	1.464	9	89.497	A	0.000	89.497	89.497	100.00	0.000	0.000
					B	0.000	89.497		100.00	0.000	0.000
					C	0.000	89.497		100.00	0.000	9.468
L2 105.00-89.75	97.26	1.362	9	38.046	A	0.000	38.046	38.046	100.00	0.000	0.000
					B	0.000	38.046		100.00	0.000	0.000
					C	0.000	38.046		100.00	0.000	4.561
L3 89.75-88.25	89.00	1.328	8	3.920	A	0.000	3.920	3.920	100.00	0.000	0.000
					B	0.000	3.920		100.00	0.000	0.000
					C	0.000	3.920		100.00	0.000	0.945
L4 88.25-86.00	87.12	1.32	8	5.940	A	0.000	5.940	5.940	100.00	0.000	0.000
					B	0.000	5.940		100.00	0.000	0.000
					C	0.000	5.940		100.00	0.000	1.417
L5 86.00-84.25	85.12	1.311	8	4.670	A	0.000	4.670	4.670	100.00	0.000	0.000
					B	0.000	4.670		100.00	0.000	0.000
					C	0.000	4.670		100.00	0.000	1.102
L6 84.25-73.75	78.95	1.283	8	28.929	A	0.000	28.929	28.929	100.00	0.000	0.000
					B	0.000	28.929		100.00	0.000	0.000
					C	0.000	28.929		100.00	0.000	6.613
L7 73.75-42.75	58.15	1.176	7	92.587	A	0.000	92.587	92.587	100.00	0.000	0.000
					B	0.000	92.587		100.00	0.000	0.000
					C	0.000	92.587		100.00	0.000	19.524
L8 42.75-8.25	25.10	1	6	116.796	A	0.000	116.796	116.796	100.00	0.000	0.000
					B	0.000	116.796		100.00	0.000	0.000
					C	0.000	116.796		100.00	0.000	21.728
L9 8.25-6.25	7.25	1	6	7.315	A	0.000	7.315	7.315	100.00	0.000	0.000
					B	0.000	7.315		100.00	0.000	0.000
					C	0.000	7.315		100.00	0.000	1.260
L10 6.25-0.00	3.11	1	6	23.223	A	0.000	23.223	23.223	100.00	0.000	0.000
					B	0.000	23.223		100.00	0.000	0.000
					C	0.000	23.223		100.00	0.000	3.936

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice

Comb. No.	Description
14	Dead+Ice
15	Dead+Wind 0 deg+Ice
16	Dead+Wind 30 deg+Ice
17	Dead+Wind 60 deg+Ice
18	Dead+Wind 90 deg+Ice
19	Dead+Wind 120 deg+Ice
20	Dead+Wind 150 deg+Ice
21	Dead+Wind 180 deg+Ice
22	Dead+Wind 210 deg+Ice
23	Dead+Wind 240 deg+Ice
24	Dead+Wind 270 deg+Ice
25	Dead+Wind 300 deg+Ice
26	Dead+Wind 330 deg+Ice
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	147 - 105	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-15.74	-0.35	0.41
			Max. Mx	5	-8.27	-328.85	1.55
			Max. My	2	-8.27	-1.46	329.10
			Max. Vy	11	-15.12	328.81	-1.51
			Max. Vx	2	-15.15	-1.46	329.10
			Max. Torque	12			-2.41
L2	105 - 89.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-23.65	0.41	0.29
			Max. Mx	11	-13.15	709.13	-5.32
			Max. My	2	-13.15	-5.15	709.64
			Max. Vy	11	-21.09	709.13	-5.32
			Max. Vx	2	-21.11	-5.15	709.64
			Max. Torque	12			-2.40
L3	89.75 - 88.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-23.93	0.46	0.26
			Max. Mx	11	-13.36	740.86	-5.62
			Max. My	2	-13.36	-5.45	741.39
			Max. Vy	11	-21.23	740.86	-5.62
			Max. Vx	2	-21.25	-5.45	741.39
			Max. Torque	12			-2.36
L4	88.25 - 86	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-24.49	0.52	0.22
			Max. Mx	11	-13.83	788.87	-6.08
			Max. My	2	-13.83	-5.89	789.43
			Max. Vy	11	-21.45	788.87	-6.08
			Max. Vx	2	-21.47	-5.89	789.43
			Max. Torque	12			-2.35
L5	86 - 84.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-24.94	0.57	0.20
			Max. Mx	11	-14.19	826.56	-6.43
			Max. My	2	-14.19	-6.23	827.14
			Max. Vy	11	-21.63	826.56	-6.43
			Max. Vx	2	-21.65	-6.23	827.14
			Max. Torque	12			-2.34

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L6	84.25 - 73.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-26.73	0.76	0.09
			Max. Mx	11	-15.62	963.90	-7.72
			Max. My	2	-15.62	-7.44	964.53
			Max. Vy	11	-22.36	963.90	-7.72
			Max. Vx	2	-22.39	-7.44	964.53
			Max. Torque	12			-2.33
L7	73.75 - 42.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-36.24	1.71	-0.47
			Max. Mx	11	-23.64	1690.48	-13.96
			Max. My	2	-23.64	-13.41	1691.44
			Max. Vy	11	-25.18	1690.48	-13.96
			Max. Vx	2	-25.20	-13.41	1691.44
			Max. Torque	12			-2.28
L8	42.75 - 8.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-50.46	3.06	-1.24
			Max. Mx	11	-36.13	2738.40	-21.95
			Max. My	8	-36.13	22.48	-2739.88
			Max. Vy	11	-28.11	2738.40	-21.95
			Max. Vx	2	-28.13	-20.94	2739.73
			Max. Torque	12			-2.11
L9	8.25 - 6.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-51.19	3.13	-1.28
			Max. Mx	11	-36.80	2794.73	-22.35
			Max. My	8	-36.80	22.89	-2796.23
			Max. Vy	11	-28.24	2794.73	-22.35
			Max. Vx	2	-28.26	-21.31	2796.07
			Max. Torque	11			-1.97
L10	6.25 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-53.50	3.35	-1.41
			Max. Mx	11	-38.85	2972.52	-23.61
			Max. My	8	-38.85	24.17	-2974.12
			Max. Vy	11	-28.67	2972.52	-23.61
			Max. Vx	2	-28.69	-22.48	2973.92
			Max. Torque	11			-1.97

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	14	53.50	-0.00	0.00
	Max. H_x	11	38.87	28.65	-0.19
	Max. H_z	2	38.87	-0.19	28.68
	Max. M_x	2	2973.92	-0.19	28.68
	Max. M_z	5	2970.85	-28.65	0.19
	Max. Torsion	5	1.95	-28.65	0.19
	Min. Vert	8	38.86	0.19	-28.67
	Min. H_x	5	38.87	-28.65	0.19
	Min. H_z	8	38.86	0.19	-28.67
	Min. M_x	8	-2974.12	0.19	-28.67
	Min. M_z	11	-2972.52	28.65	-0.19
	Min. Torsion	11	-1.95	28.65	-0.19

Tower Mast Reaction Summary

Load Combination	Vertical K	$Shear_x$ K	$Shear_z$ K	Overturning Moment, M_x kip-ft	Overturning Moment, M_z kip-ft	Torque kip-ft

Load Combination	Vertical	$Shear_x$	$Shear_z$	Overturning Moment, M_x	Overturning Moment, M_z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	38.87	-0.00	0.00	0.26	0.81	0.00
Dead+Wind 0 deg - No Ice	38.87	0.19	-28.68	-2973.92	-22.48	0.39
Dead+Wind 30 deg - No Ice	38.87	14.50	-24.93	-2587.26	-1505.22	-0.63
Dead+Wind 60 deg - No Ice	38.87	24.91	-14.51	-1507.11	-2584.41	-1.49
Dead+Wind 90 deg - No Ice	38.87	28.65	-0.19	-23.05	-2970.85	-1.95
Dead+Wind 120 deg - No Ice	38.87	24.72	14.17	1467.31	-2561.16	-1.88
Dead+Wind 150 deg - No Ice	38.87	14.16	24.74	2564.56	-1464.86	-1.32
Dead+Wind 180 deg - No Ice	38.86	-0.19	28.67	2974.12	24.17	-0.40
Dead+Wind 210 deg - No Ice	38.87	-14.50	24.93	2587.80	1506.89	0.63
Dead+Wind 240 deg - No Ice	38.87	-24.91	14.51	1507.65	2586.08	1.49
Dead+Wind 270 deg - No Ice	38.87	-28.65	0.19	23.61	2972.52	1.95
Dead+Wind 300 deg - No Ice	38.87	-24.72	-14.17	-1466.75	2562.85	1.88
Dead+Wind 330 deg - No Ice	38.87	-14.16	-24.74	-2564.02	1466.55	1.31
Dead+Ice	53.50	0.00	-0.00	1.41	3.35	0.00
Dead+Wind 0 deg+Ice	53.50	0.04	-7.10	-755.65	-0.95	-0.01
Dead+Wind 30 deg+Ice	53.50	3.58	-6.17	-656.45	-378.45	-0.19
Dead+Wind 60 deg+Ice	53.50	6.16	-3.58	-380.96	-653.60	-0.31
Dead+Wind 90 deg+Ice	53.50	7.09	-0.04	-3.01	-752.68	-0.35
Dead+Wind 120 deg+Ice	53.50	6.12	3.52	376.14	-649.14	-0.30
Dead+Wind 150 deg+Ice	53.50	3.51	6.13	654.90	-370.72	-0.17
Dead+Wind 180 deg+Ice	53.50	-0.04	7.10	758.56	7.98	0.01
Dead+Wind 210 deg+Ice	53.50	-3.58	6.17	659.36	385.48	0.19
Dead+Wind 240 deg+Ice	53.50	-6.16	3.58	383.87	660.64	0.31
Dead+Wind 270 deg+Ice	53.50	-7.09	0.04	5.92	759.72	0.35
Dead+Wind 300 deg+Ice	53.50	-6.12	-3.52	-373.23	656.18	0.30
Dead+Wind 330 deg+Ice	53.50	-3.51	-6.13	-651.99	377.75	0.17
Dead+Wind 0 deg - Service	38.87	0.07	-9.92	-1029.86	-7.24	0.14
Dead+Wind 30 deg - Service	38.87	5.02	-8.63	-896.03	-520.85	-0.22
Dead+Wind 60 deg - Service	38.87	8.62	-5.02	-521.88	-894.67	-0.52
Dead+Wind 90 deg - Service	38.87	9.91	-0.07	-7.81	-1028.37	-0.68
Dead+Wind 120 deg - Service	38.87	8.55	4.90	508.39	-886.55	-0.66
Dead+Wind 150 deg - Service	38.87	4.90	8.56	888.49	-506.85	-0.46
Dead+Wind 180 deg - Service	38.87	-0.07	9.92	1030.39	8.92	-0.14
Dead+Wind 210 deg - Service	38.87	-5.02	8.63	896.56	522.52	0.22
Dead+Wind 240 deg - Service	38.87	-8.62	5.02	522.38	896.30	0.52
Dead+Wind 270 deg - Service	38.87	-9.91	0.07	8.34	1030.05	0.68
Dead+Wind 300 deg - Service	38.87	-8.55	-4.90	-507.88	888.27	0.66
Dead+Wind 330 deg - Service	38.87	-4.90	-8.56	-887.91	508.51	0.46

Solution Summary

	Sum of Applied Forces			Sum of Reactions			
Load Comb.	PX	PY	PZ	PX	PY	PZ	% Error
	K	K	K	K	K	K	
1	0.00	-38.87	0.00	0.00	38.87	0.00	0.000%
2	0.19	-38.87	-28.68	-0.19	38.87	28.68	0.004%
3	14.50	-38.87	-24.93	-14.50	38.87	24.93	0.000%
4	24.91	-38.87	-14.51	-24.91	38.87	14.51	0.000%
5	28.66	-38.87	-0.19	-28.65	38.87	0.19	0.002%
6	24.72	-38.87	14.17	-24.72	38.87	-14.17	0.000%
7	14.16	-38.87	24.74	-14.16	38.87	-24.74	0.000%
8	-0.19	-38.87	28.68	0.19	38.86	-28.67	0.010%
9	-14.50	-38.87	24.93	14.50	38.87	-24.93	0.000%
10	-24.91	-38.87	14.51	24.91	38.87	-14.51	0.000%
11	-28.66	-38.87	0.19	28.65	38.87	-0.19	0.002%
12	-24.72	-38.87	-14.17	24.72	38.87	14.17	0.000%
13	-14.16	-38.87	-24.74	14.16	38.87	24.74	0.000%
14	0.00	-53.50	0.00	-0.00	53.50	0.00	0.000%

Load Comb.	Sum of Applied Forces PX K	PY K	PZ K	Sum of Reactions PX K	PY K	PZ K	% Error
15	0.04	-53.50	-7.10	-0.04	53.50	7.10	0.002%
16	3.58	-53.50	-6.17	-3.58	53.50	6.17	0.002%
17	6.16	-53.50	-3.58	-6.16	53.50	3.58	0.002%
18	7.09	-53.50	-0.04	-7.09	53.50	0.04	0.002%
19	6.12	-53.50	3.52	-6.12	53.50	-3.52	0.002%
20	3.51	-53.50	6.13	-3.51	53.50	-6.13	0.002%
21	-0.04	-53.50	7.10	0.04	53.50	-7.10	0.002%
22	-3.58	-53.50	6.17	3.58	53.50	-6.17	0.002%
23	-6.16	-53.50	3.58	6.16	53.50	-3.58	0.002%
24	-7.09	-53.50	0.04	7.09	53.50	-0.04	0.002%
25	-6.12	-53.50	-3.52	6.12	53.50	3.52	0.002%
26	-3.51	-53.50	-6.13	3.51	53.50	6.13	0.002%
27	0.07	-38.87	-9.92	-0.07	38.87	9.92	0.004%
28	5.02	-38.87	-8.63	-5.02	38.87	8.63	0.001%
29	8.62	-38.87	-5.02	-8.62	38.87	5.02	0.001%
30	9.92	-38.87	-0.07	-9.91	38.87	0.07	0.004%
31	8.55	-38.87	4.90	-8.55	38.87	-4.90	0.002%
32	4.90	-38.87	8.56	-4.90	38.87	-8.56	0.001%
33	-0.07	-38.87	9.92	0.07	38.87	-9.92	0.004%
34	-5.02	-38.87	8.63	5.02	38.87	-8.63	0.001%
35	-8.62	-38.87	5.02	8.62	38.87	-5.02	0.002%
36	-9.92	-38.87	0.07	9.91	38.87	-0.07	0.004%
37	-8.55	-38.87	-4.90	8.55	38.87	4.90	0.001%
38	-4.90	-38.87	-8.56	4.90	38.87	8.56	0.002%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	6	0.00000001	0.00000001
2	Yes	14	0.00004540	0.00013125
3	Yes	18	0.00000001	0.00008334
4	Yes	18	0.00000001	0.00008607
5	Yes	15	0.00000001	0.00011153
6	Yes	18	0.00000001	0.00007774
7	Yes	18	0.00000001	0.00008303
8	Yes	13	0.00011078	0.00014750
9	Yes	18	0.00000001	0.00008472
10	Yes	18	0.00000001	0.00008211
11	Yes	15	0.00000001	0.00006623
12	Yes	18	0.00000001	0.00008390
13	Yes	18	0.00000001	0.00007849
14	Yes	6	0.00000001	0.00000001
15	Yes	14	0.00000001	0.00002478
16	Yes	14	0.00000001	0.00008102
17	Yes	14	0.00000001	0.00009071
18	Yes	14	0.00000001	0.00003019
19	Yes	14	0.00000001	0.00007361
20	Yes	14	0.00000001	0.00008773
21	Yes	14	0.00000001	0.00002449
22	Yes	14	0.00000001	0.00008809
23	Yes	14	0.00000001	0.00007943
24	Yes	14	0.00000001	0.00002906
25	Yes	14	0.00000001	0.00009184
26	Yes	14	0.00000001	0.00007654
27	Yes	13	0.00011572	0.00007419
28	Yes	15	0.00000001	0.00006914
29	Yes	15	0.00000001	0.00007635
30	Yes	13	0.00011572	0.00010192
31	Yes	14	0.00000001	0.00013747
32	Yes	15	0.00000001	0.00007379
33	Yes	13	0.00011572	0.00007015
34	Yes	15	0.00000001	0.00007265
35	Yes	14	0.00000001	0.00014995
36	Yes	13	0.00011572	0.00009270

37	Yes	15	0.00000001	0.00007624
38	Yes	14	0.00000001	0.00014101

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	147 - 105	31.604	34	1.8177	0.0044
L2	108.75 - 89.75	17.791	34	1.5444	0.0039
L3	89.75 - 88.25	12.125	34	1.2640	0.0023
L4	88.25 - 86	11.732	34	1.2355	0.0022
L5	86 - 84.25	11.157	34	1.2078	0.0021
L6	84.25 - 73.75	10.718	34	1.1860	0.0020
L7	78 - 42.75	9.225	34	1.0952	0.0017
L8	47.5 - 8.25	3.470	34	0.6755	0.0008
L9	8.25 - 6.25	0.101	34	0.1169	0.0001
L10	6.25 - 0	0.058	34	0.0886	0.0001

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
147.00	APXVSPP18-C-A20 w/ Mount Pipe	34	31.604	1.8177	0.0044	34886
135.00	Celwave APXV18-206515L-03 w/Mount Pipe	34	27.089	1.7514	0.0046	14535
126.00	(4) 2.375" OD x 6' Mount Pipe	34	23.774	1.6940	0.0046	8305
116.00	(2) LPA-80080/4CF w/ Mount Pipe	34	20.230	1.6153	0.0043	5625
106.00	(2) Powerwave Technologies 7770 w/ Mount Pipe	34	16.900	1.5137	0.0037	4240
80.00	KS24019-L112A	34	9.690	1.1251	0.0018	4303

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	147 - 105	91.020	9	5.2380	0.0125
L2	108.75 - 89.75	51.276	9	4.4537	0.0113
L3	89.75 - 88.25	34.958	9	3.6454	0.0066
L4	88.25 - 86	33.826	9	3.5633	0.0062
L5	86 - 84.25	32.168	9	3.4835	0.0059
L6	84.25 - 73.75	30.904	9	3.4207	0.0057
L7	78 - 42.75	26.600	9	3.1589	0.0048
L8	47.5 - 8.25	10.011	9	1.9487	0.0022
L9	8.25 - 6.25	0.291	9	0.3374	0.0003
L10	6.25 - 0	0.167	9	0.2556	0.0002

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
147.00	APXVSPP18-C-A20 w/ Mount Pipe	9	91.020	5.2380	0.0129	12319
135.00	Celwave APXV18-206515L-03 w/Mount Pipe	9	78.032	5.0484	0.0132	5132
126.00	(4) 2.375" OD x 6' Mount Pipe	9	68.495	4.8839	0.0132	2931
116.00	(2) LPA-80080/4CF w/ Mount Pipe	9	58.298	4.6578	0.0125	1983
106.00	(2) Powerwave Technologies 7770 w/ Mount Pipe	9	48.712	4.3653	0.0108	1493
80.00	KS24019-L112A	9	27.943	3.2452	0.0051	1503

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L_u ft	Kl/r	F_a ksi	A in^2	Actual P K	Allow. P_a K	Ratio $\frac{P}{P_a}$
L1	147 - 105 (1)	TP29.141x22x0.25	42.00	0.00	0.0	36.000	22.4191	-8.25	807.09	0.010
L2	105 - 89.75 (2)	TP31.2343x28.0034x0.3125	19.00	0.00	0.0	36.000	30.6705	-13.13	1104.14	0.012
L3	89.75 - 88.25 (3)	TP31.4893x31.2343x0.3125	1.50	0.00	0.0	35.532	30.9235	-13.34	1098.77	0.012
L4	88.25 - 86 (4)	TP31.8719x31.4893x0.5085	2.25	0.00	0.0	34.302	50.6160	-13.81	1736.23	0.008
L5	86 - 84.25 (5)	TP32.1695x31.8719x0.5063	1.75	0.00	0.0	33.978	50.8827	-14.17	1728.89	0.008
L6	84.25 - 73.75 (6)	TP33.955x32.1695x0.455	10.50	0.00	0.0	34.980	47.3360	-15.61	1655.81	0.009
L7	73.75 - 42.75 (7)	TP38.601x32.3223x0.537	35.25	0.00	0.0	34.554	63.4392	-23.63	2192.08	0.011
L8	42.75 - 8.25 (8)	TP43.7172x36.6809x0.5757	39.25	0.00	0.0	34.740	78.8258	-36.13	2738.41	0.013
L9	8.25 - 6.25 (9)	TP44.0573x43.7172x0.596	2.00	0.00	0.0	34.464	82.2200	-36.79	2833.63	0.013
L10	6.25 - 0 (10)	TP45.12x44.0573x0.5918	6.25	0.00	0.0	34.422	83.6336	-38.85	2878.84	0.013

Pole Bending Design Data

Section No.	Elevation ft	Size	Actual M_x kip-ft	Actual f_{bx} ksi	Allow. F_{bx} ksi	Ratio $\frac{f_{bx}}{F_{bx}}$	Actual M_y kip-ft	Actual f_{by} ksi	Allow. F_{by} ksi	Ratio $\frac{f_{by}}{F_{by}}$
L1	147 - 105 (1)	TP29.141x22x0.25	330.39	25.391	36.000	0.705	0.00	0.000	36.000	0.000
L2	105 - 89.75 (2)	TP31.2343x28.0034x0.3125	714.05	36.696	36.000	1.019	0.00	0.000	36.000	0.000
L3	89.75 - 88.25 (3)	TP31.4893x31.2343x0.3125	746.06	37.713	35.532	1.061	0.00	0.000	35.532	0.000
L4	88.25 - 86 (4)	TP31.8719x31.4893x0.5085	794.50	24.540	34.302	0.715	0.00	0.000	34.302	0.000
L5	86 - 84.25 (5)	TP32.1695x31.8719x0.5063	832.53	25.332	33.978	0.746	0.00	0.000	33.978	0.000
L6	84.25 - 73.75 (6)	TP33.955x32.1695x0.455	971.06	30.618	34.980	0.875	0.00	0.000	34.980	0.000
L7	73.75 - 42.75 (7)	TP38.601x32.3223x0.537	1703.51	35.316	34.554	1.022	0.00	0.000	34.554	0.000
L8	42.75 - 8.25 (8)	TP43.7172x36.6809x0.5757	2758.90	39.668	34.740	1.142	0.00	0.000	34.740	0.000
L9	8.25 - 6.25 (9)	TP44.0573x43.7172x0.596	2815.60	38.540	34.464	1.118	0.00	0.000	34.464	0.000

Section No.	Elevation ft	Size	Actual M_x kip-ft	Actual f_{bx} ksi	Allow. F_{bx} ksi	Ratio $\frac{f_{bx}}{F_{bx}}$	Actual M_y kip-ft	Actual f_{by} ksi	Allow. F_{by} ksi	Ratio $\frac{f_{by}}{F_{by}}$
L10	6.25 - 0 (10)	TP45.12x44.0573x0.5918	2994.57	39.315	34.422	1.142	0.00	0.000	34.422	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V K	Actual f_v ksi	Allow. F_v ksi	Ratio $\frac{f_v}{F_v}$	Actual T kip-ft	Actual f_{vt} ksi	Allow. F_{vt} ksi	Ratio $\frac{f_{vt}}{F_{vt}}$
L1	147 - 105 (1)	TP29.141x22x0.25	15.31	0.683	24.000	0.057	0.24	0.009	24.000	0.000
L2	105 - 89.75 (2)	TP31.2343x28.0034x0.3125	21.28	0.694	24.000	0.058	0.37	0.009	24.000	0.000
L3	89.75 - 88.25 (3)	TP31.4893x31.2343x0.3125	21.42	0.693	23.688	0.058	0.37	0.009	23.688	0.000
L4	88.25 - 86 (4)	TP31.8719x31.4893x0.5085	21.64	0.428	22.868	0.037	0.38	0.006	22.868	0.000
L5	86 - 84.25 (5)	TP32.1695x31.8719x0.5063	21.82	0.429	22.652	0.038	0.38	0.006	22.652	0.000
L6	84.25 - 73.75 (6)	TP33.955x32.1695x0.455	22.56	0.477	23.320	0.041	0.40	0.006	23.320	0.000
L7	73.75 - 42.75 (7)	TP38.601x32.3223x0.537	25.37	0.400	23.036	0.035	0.49	0.005	23.036	0.000
L8	42.75 - 8.25 (8)	TP43.7172x36.6809x0.5757	28.30	0.359	23.160	0.031	0.61	0.004	23.160	0.000
L9	8.25 - 6.25 (9)	TP44.0573x43.7172x0.596	28.42	0.346	22.976	0.030	0.61	0.004	22.976	0.000
L10	6.25 - 0 (10)	TP45.12x44.0573x0.5918	28.86	0.345	22.948	0.030	0.63	0.004	22.948	0.000

Pole Interaction Design Data

Section No.	Elevation ft	Ratio $\frac{P}{P_a}$	Ratio $\frac{f_{bx}}{F_{bx}}$	Ratio $\frac{f_{by}}{F_{by}}$	Ratio $\frac{f_v}{F_v}$	Ratio $\frac{f_{vt}}{F_{vt}}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	147 - 105 (1)	0.010	0.705	0.000	0.057	0.000	0.716 ✔	1.333	H1-3+VT ✔
L2	105 - 89.75 (2)	0.012	1.019	0.000	0.058	0.000	1.032 ✔	1.333	H1-3+VT ✔
L3	89.75 - 88.25 (3)	0.012	1.061	0.000	0.058	0.000	1.074 ✔	1.333	H1-3+VT ✔
L4	88.25 - 86 (4)	0.008	0.715	0.000	0.037	0.000	0.724 ✔	1.333	H1-3+VT ✔
L5	86 - 84.25 (5)	0.008	0.746	0.000	0.038	0.000	0.754 ✔	1.333	H1-3+VT ✔
L6	84.25 - 73.75 (6)	0.009	0.875	0.000	0.041	0.000	0.885 ✔	1.333	H1-3+VT ✔
L7	73.75 - 42.75 (7)	0.011	1.022	0.000	0.035	0.000	1.033 ✔	1.333	H1-3+VT ✔
L8	42.75 - 8.25 (8)	0.013	1.142	0.000	0.031	0.000	1.155 ✔	1.333	H1-3+VT ✔
L9	8.25 - 6.25 (9)	0.013	1.118	0.000	0.030	0.000	1.131 ✔	1.333	H1-3+VT ✔
L10	6.25 - 0 (10)	0.013	1.142	0.000	0.030	0.000	1.156 ✔	1.333	H1-3+VT ✔

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$SF*P_{allow}$ K	% Capacity	Pass Fail
L1	147 - 105	Pole	TP29.141x22x0.25	1	-8.25	1075.85	53.7	Pass
L2	105 - 89.75	Pole	TP31.2343x28.0034x0.3125	2	-13.13	1471.82	77.4	Pass
L3	89.75 - 88.25	Pole	TP31.4893x31.2343x0.3125	3	-13.34	1464.66	80.6	Pass
L4	88.25 - 86	Pole	TP31.8719x31.4893x0.5085	4	-13.81	2314.39	54.3	Pass
L5	86 - 84.25	Pole	TP32.1695x31.8719x0.5063	5	-14.17	2304.61	56.6	Pass
L6	84.25 - 73.75	Pole	TP33.955x32.1695x0.455	6	-15.61	2207.19	66.4	Pass
L7	73.75 - 42.75	Pole	TP38.601x32.3223x0.537	7	-23.63	2922.04	77.5	Pass
L8	42.75 - 8.25	Pole	TP43.7172x36.6809x0.5757	8	-36.13	3650.30	86.7	Pass
L9	8.25 - 6.25	Pole	TP44.0573x43.7172x0.596	9	-36.79	3777.23	84.9	Pass
L10	6.25 - 0	Pole	TP45.12x44.0573x0.5918	10	-38.85	3837.49	86.7	Pass
							Summary	
						Pole (L10)	86.7	Pass
						RATING =	**86.7**	**Pass**

APPENDIX B

BASE LEVEL DRAWING



APPENDIX C

ADDITIONAL CALCULATIONS

Section	1	2	3	4	5	6	7	8	9	10
Length (ft)	42.00	19.00	2.25	1.75	1.50	10.50	35.25	39.25	2.00	6.25
Number of Sides	18	18	18	18	18	18	18	18	18	18
Thickness (in)	0.2500	0.3125	0.3125	0.3125	0.3125	0.4550	0.5370	0.5757	0.5960	0.5918
Socket Length (ft)										
Top Dia (in)	22.0000	28.0034	31.2343	31.2343	31.2343	32.1695	32.3223	36.6809	43.7172	44.0573
Bot Dia (in)	29.1410	31.2343	32.1695	32.1695	32.1695	33.9550	38.6010	43.7172	44.0573	45.1200
Grade	A607-60	Reinf 59.22 ksi	Reinf 59.22 ksi	Reinf 59.22 ksi	Reinf 59.22 ksi	Reinf 56.63 ksi	Reinf 58.30 ksi	Reinf 57.59 ksi	Reinf 57.90 ksi	Reinf 57.37 ksi
Weight (K)	2.9	1.9	0.2	0.4	0.3	1.7	7.1	9.7	0.6	1.8



AXIAL 53 K
SHEAR 7 K
MOMENT 764 kip-ft
TORQUE 0 kip-ft
38 mph WIND - 0.7500 in ICE

AXIAL 39 K
SHEAR 29 K
MOMENT 2995 kip-ft
TORQUE 2 kip-ft
REACTIONS - 85 mph WIND

DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
APXVSPP18-C-A20 w/ Mount Pipe	147	BXA-171085-8BF-EDIN-2 w/ Mount Pipe	116
APXVSPP18-C-A20 w/ Mount Pipe	147	BXA-171085-8BF-EDIN-2 w/ Mount Pipe	116
APXVSPP18-C-A20 w/ Mount Pipe	147	BXA-171085-8BF-EDIN-2 w/ Mount Pipe	116
800 EXTERNAL NOTCH FILTER	147	(2) FD9R6004/2C-3L	116
800 EXTERNAL NOTCH FILTER	147	(2) FD9R6004/2C-3L	116
800 EXTERNAL NOTCH FILTER	147	(2) FD9R6004/2C-3L	116
(3) ACU-A20-N	147	(2) ClearGain Dual Band 800/1900 MHz	116
(3) ACU-A20-N	147	Platform Mount [LP 712-1]	116
(3) ACU-A20-N	147	(2) Powerwave Technologies 7770 w/ Mount Pipe	106
1900MHz RRH (65MHz)	147	(2) Powerwave Technologies 7770 w/ Mount Pipe	106
1900MHz RRH (65MHz)	147	(2) Powerwave Technologies 7770 w/ Mount Pipe	106
1900MHz RRH (65MHz)	147	AM-X-CD-14-65-00T-RET w/ Mount Pipe	106
800MHZ RRH	147	AM-X-CD-14-65-00T-RET w/ Mount Pipe	106
800MHZ RRH	147	AM-X-CD-14-65-00T-RET w/ Mount Pipe	106
800MHZ RRH	147	(4) Powerwave Technologies LGP2140X	106
APXVTM14-C-120 w/ Mount Pipe	147	(4) Powerwave Technologies LGP2140X	106
APXVTM14-C-120 w/ Mount Pipe	147	(4) Powerwave Technologies LGP2140X	106
APXVTM14-C-120 w/ Mount Pipe	147	DC6-48-60-18-8F	106
TD-RRH8x20-25	147	(2) RRUS-11	106
TD-RRH8x20-25	147	(2) RRUS-11	106
TD-RRH8x20-25	147	(2) RRUS-11	106
Platform Mount [LP 712-1]	147	Platform Mount [LP 712-1]	106
Miscellaneous (NA507-1)	147	KS24019-L112A	80
Celwave APXV18-206515L-03 w/Mount Pipe	135	Kathrein OG-860/1920/GPS-A	80
Celwave APXV18-206515L-03 w/Mount Pipe	135	KS24019-L112A	80
Celwave APXV18-206515L-03 w/Mount Pipe	135	Side Arm Mount [SO 701-3]	80
Pipe Mount [PM 601-3]	135		
(4) 2.375" OD x 6' Mount Pipe	126		
(4) 2.375" OD x 6' Mount Pipe	126		
(4) 2.375" OD x 6' Mount Pipe	126		
Platform Mount [LP 712-1]	126		
(2) LPA-80080/4CF w/ Mount Pipe	116		
(2) LPA-80063/6CF w/ Mount Pipe	116		
(2) APL868013 w/ Mount Pipe	116		
BXA-70063-6CF-2 w/ Mount Pipe	116		
BXA-70063-6CF-2 w/ Mount Pipe	116		
BXA-70063/6CF-2 w/ Mount Pipe	116		

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A607-60	60 ksi	75 ksi	Reinf 57.59 ksi	58 ksi	72 ksi
Reinf 59.22 ksi	59 ksi	75 ksi	Reinf 57.90 ksi	58 ksi	73 ksi
Reinf 57.17 ksi	57 ksi	72 ksi	Reinf 57.44 ksi	57 ksi	65 ksi
Reinf 56.63 ksi	57 ksi	65 ksi	Reinf 57.37 ksi	57 ksi	72 ksi
Reinf 58.30 ksi	58 ksi	73 ksi			

TOWER DESIGN NOTES

1. Tower is located in New Haven County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 86.7%

Paul J. Ford
250 East Broad Street, Suite 600
Columbus, Ohio 43215
Phone: 614.221.6679
FAX: 614.448.4118

Job: **Ex. 147 ft Monopole, Secondino, Property Branford, CT**			
Project: **PJF #37512-1569 (BU #876316)**			
Client: Crown Castle International	Drawn by: Kevin Mahlum	App'd:	
Code: TIA/EIA-222-F	Date: 01/06/14	Scale: NTS	
Path: G:\TOWER\375_Crown_Castle\2014\37514-0035 BU 876316\37514-0035 Reinforced.eri		Dwg No. E-1	

Square, Stiffened / Unstiffened Base Plate, Any Rod Material - Rev. F /G

Assumptions: 1) Rod groups at corners. Total # rods divisible by 4. Maximum total # of rods = 48 (12 per Corner).
2) Rod Spacing = Straight Center-to-Center distance between any (2) adjacent rods (same corner)
3) Clear space between bottom of leveling nut and top of concrete **not** exceeding (1)*(Rod Diameter)

Site Data

BU#:
Site Name:
App #:

Anchor Rod Data		
Qty:	16	
Diam:	2.25	in
Rod Material:	A615-J	
Yield, Fy:	75	ksi
Strength, Fu:	100	ksi
Bolt Circle:	52	in
Anchor Spacing:	6	in

Plate Data		
W=Side:	53	in
Thick:	3	in
Grade:	60	ksi
Clip Distance:	0	in

Stiffener Data (Welding at both sides)		
Configuration:	Unstiffened	
Weld Type:		**
Groove Depth:		in **
Groove Angle:		degrees
Fillet H. Weld:		<-- Disregard
Fillet V. Weld:		in
Width:		in
Height:		in
Thick:		in
Notch:		in
Grade:		ksi
Weld str.:		ksi

Pole Data		
Diam:	45.12	in
Thick:	0.4375	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round

Stress Increase Factor		
ASD ASIF:	1.333	

Base Reactions		
TIA Revision:	F	
Unfactored Moment, M:	2995	ft-kips
Unfactored Axial, P:	39	kips
Unfactored Shear, V:	29	kips

Anchor Rod Results

TIA F --> Maximum Rod Tension	170.4	Kips
Allowable Tension:	195.0	Kips
Anchor Rod Stress Ratio:	87.4%	**Pass**

Base Plate Results Flexural Check

Base Plate Stress:	39.4	ksi
Allowable PL Bending Stress:	60.0	ksi
Base Plate Stress Ratio:	65.6%	**Pass**

PL Ref. Data
Yield Line (in): 29.83
Max PL Length: 29.83

N/A - Unstiffened

Stiffener Results

Horizontal Weld :	N/A
Vertical Weld:	N/A
Plate Flex+Shear, fb/Fb+(fv/Fv)^2:	N/A
Plate Tension+Shear, ft/Ft+(fv/Fv)^2:	N/A
Plate Comp. (AISC Bracket):	N/A

Pole Results

Pole Punching Shear Check: N/A



** Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

PAUL J. FORD AND COMPANY
STRUCTURAL ENGINEERS
250 East Broad Street • Suite 600 • Columbus, Ohio 43215-3708

Job Number: 37514-0035
Site Number: 876316
Site Name: SECONDINO PROPERTY

By: KMM
Date: 1/6/2014

DRILLED PIER SOIL AND STEEL ANALYSIS - TIA/EIA-222-F

Unfactored Base Reactions from RISA

	Comp. (+)	Tension (-)	
Moment, M =	2995.0		k-ft
Shear, V =	29.0		kips
Axial Load, P =	39.0		kips
OTM =	3009.5	0.0	k-ft @ Ground

Safety Factors / Load Factors / Φ Factors

Tower Type =	Monopole DP
ACI Code =	ACI 318-02
Seismic Design Category =	D
Reference Standard =	TIA/EIA-222-F
Use 1.3 Load Factor?	Yes
Load Factor =	1.30

Drilled Pier Parameters

Diameter =	7	ft
Height Above Grade =	0.5	ft
Depth Below Grade =	22.5	ft
fc' =	3	ksi
εc =	0.003	in/in
Mat Ftdn. Cap Width =		ft
Mat Ftdn. Cap Length =		ft
Depth Below Grade =		ft

	Safety Factor	Φ Factor
Soil Lateral Resistance =	2.00	0.75
Skin Friction =	2.00	0.75
End Bearing =	2.00	0.75
Concrete Wt. Resist Uplift =	1.25	

Load Combinations Checked per TIA/EIA-222-F

1. Ult. Skin Friction/2.00 + Ult. End Bearing/2.00
 + Effective Soil Wt. - Buoyant Conc. Wt. ≥ Comp.
2. Ult. Skin Friction/2.00 + Buoyant Conc. Wt./1.25 ≥ Uplift
3. Ult. Skin Friction/1.50 + Buoyant Conc. Wt./1.50 ≥ Uplift

Steel Parameters

Number of Bars =	32	
Rebar Size =	#11	
Rebar Fy =	60	ksi
Rebar MOE =	29000	ksi
Tie Size =	#5	
Side Clear Cover to Ties =	4	in

Soil Parameters

Water Table Depth =	7.50	ft
Depth to Ignore Soil =	3.50	ft
Depth to Full Cohesion =	0	ft
Full Cohesion Starts at?	Ground	

Above Full Cohesion Lateral Resistance = 4(Cohesion)(Dia)(H)
Below Full Cohesion Lateral Resistance = 8(Cohesion)(Dia)(H)

Direct Embed Pole Shaft Parameters

Dia @ Grade =		in
Dia @ Depth Below Grade =		in
Number of Sides =		
Thickness =		in
Fy =		ksi
Backfill Condition =		

Maximum Capacity Ratios

Maximum Soil Ratio =	110.0%
Maximum Steel Ratio =	105.0%

Define Soil Layers

Note: Cohesion = Undrained Shear Strengh = Unconfined Compressive Strength / 2

Layer	Thickness ft	Unit Weight pcf	Cohesion psf	Friction Angle degrees	Soil Type	Ultimate End Bearing psf	Comp. Ult. Skin Friction psf	Tension Ult. Skin Friction psf	Depth ft
1	5	100	0	36	Sand				5
2	2.5	135	0	36	Sand				7.5
3	18.5	135	0	36	Sand	16000			26
4									
5									
6									
7									
8									
9									
10									
11									
12									

Soil Results: Overturning

Depth to COR =	15.92	ft, from Grade	Shear, V =	29.00	kips
Bending Moment, M =	3471.12	k-ft, from COR	Resisting Shear, Va =	33.31	kips
Resisting Moment, Ma =	3986.59	k-ft, from COR			

MOMENT RATIO = 87.1% OK **SHEAR RATIO = 87.1% OK**

Soil Results: Uplift

Uplift, T =	0.00	kips
Allowable Uplift Cap., Ta =	77.40	kips

UPLIFT RATIO = 0.0% OK

Soil Results: Compression

Compression, C =	39.00	kips
Allowable Comp. Cap., Ca =	285.27	kips

COMPRESSION RATIO = 13.7% OK

Steel Results (ACI 318-02):

Minimum Steel Area =	18.47	sq in	Axial Load, P =	70.75	kips @ 5.00 ft Below Grade
Actual Steel Area =	49.92	sq in	Moment, M =	3138.65	k-ft @ 5.00 ft Below Grade
			Allowable Moment, Ma =	5821.80	k-ft
Allowable Min Axial, Pa =	-2073.60	kips, Where Ma = 0 k-ft			
Allowable Max Axial, Pa =	6799.77	kips, Where Ma = 0 k-ft	**MOMENT RATIO =**	**53.9%**	**OK**

Moment Capacity of Drilled Concrete Shaft (Caisson) for TIA Rev F or G

Note: Shaft assumed to have ties, not spiral, transverse reinforcing

Site Data

BU#: *876316*
Site Name: *SECONDINO PROPERTY*
App #:

Enter Load Factors Below:		
For M (WL)	1.3	<---- Enter Factor
For P (DL)	1.3	<---- Enter Factor

Pier Properties

Concrete:

Pier Diameter =	7.0	ft
Concrete Area =	5541.8	in^2

Reinforcement:

Clear Cover to **Tie**=	4.00	in
Horiz. **Tie** Bar Size=	5	
Vert. Cage Diameter =	6.11	ft
Vert. Cage Diameter =	73.34	in
Vertical Bar Size =	11	
Bar Diameter =	1.41	in
Bar Area =	1.56	in^2
Number of Bars =	32	
As Total=	49.92	in^2
A s/ Aconc, Rho:	0.0090	0.90%

ACI 10.5 , ACI 21.10.4, and IBC 1810.
Min As for Flexural, Tension Controlled, Shafts:

(3)*(Sqrt(f'c)/Fy:	0.0027
200 / Fy:	0.0033

Minimum Rho Check:

Actual Req'd Min. Rho:	0.33%	Flexural
Provided Rho:	0.90%	**OK**

Ref. Shaft Max Axial Capacities, ϕ Max(Pn or Tn):		
Max Pu = (φ=0.65) Pn.		
Pn per ACI 318 (10-2)	8839.70	kips
at Mu=(ϕ=0.65)Mn=	5309.39	ft-kips
Max Tu, (φ=0.9) Tn =	2695.68	kips
at Mu=ϕ=(0.90)Mn=	0.00	ft-kips

Maximum Shaft Superimposed Forces

TIA Revision:	F	
Max. Service Shaft M:	3138.65	ft-kips **(* Note)**
Max. Service Shaft P:	70.75	kips
Max Axial Force Type:	Comp.	

(*) Note: Max Shaft Superimposed Moment does not necessarily equal to the shaft top reaction moment

Load Factor	**Shaft Factored Loads**		
1.30	Mu:	4080.245	ft-kips
1.30	Pu:	91.975	kips

Material Properties

Concrete Comp. strength, f'c =	3000	psi
Reinforcement yield strength, Fy =	60	ksi
Reinforcing Modulus of Elasticity, E =	29000	ksi
Reinforcement yield strain =	0.00207	
Limiting compressive strain =	0.003	

ACI 318 Code

Select Analysis ACI Code=	2002

Seismic Properties

Seismic Design Category =	D
Seismic Risk =	**High**

Solve (Run) <-- Press Upon Completing All Input

Results:

Governing Orientation Case: **2**



Case 1



Case 2

Dist. From Edge to Neutral Axis:	**17.10**	in
Extreme Steel Strain, ϵt:	**0.0108**	
	ϵt > 0.0050, Tension Controlled	
Reduction Factor,φ:	**0.900**	

Output Note: Negative Pu=Tension

For Axial Compression, φ Pn = Pu:	91.98	kips
Drilled Shaft Moment Capacity, φMn:	**7568.34**	ft-kips
Drilled Shaft Superimposed Mu:	**4080.25**	ft-kips

(Mu/φMn, Drilled Shaft Flexure CSR:	**53.9%**

EBI Consulting
environmental | engineering | due diligence

RADIO FREQUENCY FCC REGULATORY COMPLIANCE MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC021

Secondino Property

21 Acorn Road
Branford, CT 06405

March 6, 2014

EBI Project Number: 62140946

21 B Street · Burlington, MA 01803 · Tel: (781) 273.2500 · Fax: (781) 273.3311

EBI Consulting
environmental | engineering | due diligence

March 6, 2014

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT03XC021 - Secondino Property

Site Total: 92.246% - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 21 Acorn Road, Branford, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (µW/cm2). The number of µW/cm2 calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu W/cm^2$). The general population exposure limit for the cellular band (850 MHz Band) is approximately 567 $\mu W/cm^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands band is 1000 $\mu W/cm^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 21 Acorn Road, Branford, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

1) 3 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications was used in this direction.

6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTMM-C-120. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTMM-C-120 has a 15.9 dBd gain value at its main lobe at 2500 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.
7) The antenna mounting height centerline for the proposed antennas is **147 feet** above ground level (AGL).
8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC021 - Secondino Property
Site Addresss	21 Acorn Road, Branford, CT 06405
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Antenna Height Meters	Cable Size	Cable Loss (dB)	Additional Loss (dB)	Gain Factor	ERP	Power Density Value	Power Density Percentage
1a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	15.9	147	141	42.97732	1/2 "	0.5	3	17.378008	1042.6805	18.85467	1.88547%
1a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	195.44744	3.534254	0.62333%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	390.89489	7.068508	1.24665%
																	Sector total Power Density Value:		3.755%

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Antenna Height Meters	Cable Size	Cable Loss (dB)	Additional Loss (dB)	Gain Factor	ERP	Power Density Value	Power Density Percentage
2a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	15.9	147	141	42.97732	1/2 "	0.5	3	17.378008	1042.6805	18.85467	1.88547%
2a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	195.44744	3.534254	0.62333%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	390.89489	7.068508	1.24665%
																	Sector total Power Density Value:		3.755%

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Antenna Height Meters	Cable Size	Cable Loss (dB)	Additional Loss (dB)	Gain Factor	ERP	Power Density Value	Power Density Percentage
3a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	15.9	147	141	42.97732	1/2 "	0.5	3	17.378008	1042.6805	18.85467	1.88547%
3a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	195.44744	3.534254	0.62333%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	390.89489	7.068508	1.24665%
																	Sector total Power Density Value:		3.755%

Site Composite MPE %	
Carrier	MPE %
Sprint	11.266%
AT&T	46.910%
MetroPCS	3.630%
Verizon Wireless	27.060%
Nextel	3.380%
Total Site MPE %	**92.246%**

EBI Consulting
environmental | engineering | due diligence

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **11.266% (3.755% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **92.246%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803