CC CROWN CASTLE

Crown Castle 3 Corporate Park Drive, Suite 101 Clifton Park, NY 12065

September 11, 2018

Melanie A. Bachman Acting Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

RE: Notice of Exempt Modification for Sprint DO Macro: 841288 Sprint Site ID: CT52XC002 2 Kaechele Pl. Bridgeport, CT 06606 Latitude: 41° 13' 24''/Longitude: -73° 13' 0.4''

Dear Ms. Bachman:

Sprint currently maintains three (3) antennas at the 148-foot level of the existing 150-foot monopole tower at 2 Kaechele Pl. Bridgeport, CT. The tower is owned by Crown Castle. The property is owned by Southern New England Telecommunications. Sprint now intends to replace three (3) antennas with six (6) new antennas. These antennas would be installed at the 148-foot and 140-foot level of the tower. Sprint also intends to remove one (1) existing cabinet and pad and replace it with one (1) cabinet and pad. Also Sprint intends to install six (6) RRHs, four (4) hybrid cable and six (6) Coax cables.

This facility was approved by the Connecticut Siting Council, an email was sent on 09/11/18 to the City of Bridgeport Building Officials Office to ascertain the original zoning approval documents and date.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.S.C.A. § 16-50j-73, a copy of this letter is being sent to Dennis Buckley zoning administrator, City of Bridgeport, Mayor Joseph Peter Ganim, City of Bridgeport, as well as the property owner, and Crown Castle is the tower owner.

- 1. The proposed modifications will not result in an increase in the height of the existing tower.
- 2. The proposed modifications will not require the extension of the site boundary.
- 3. The proposed modification will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
- 4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communication Commission safety standard.

Melanie A. Bachman September 11, 2018 Page 2

- 5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
- 6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Jeffrey Barbadora.

Sincerely,

Jeffrey Barbadora Real Estate Specialist 12 Gill Street, Suite 5800, Woburn, MA 01801 781-729-0053 Jeff.Barbadora@crowncastle.com

Attachments:

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changesTab 2: Exhibit-2: Structural Modification ReportTab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Zoning Administrator Dennis Buckley
 City of Bridgeport
 45 Lyon Terrace, Room 210
 Bridgeport, CT 06604

Mayor Joseph Peter Ganim City of Bridgeport 999 Broad Street Bridgeport, CT 06604

Southern New England Telecommunications C/O Frontier Communications – Tax DPMT 401 Merrit 7 Norwalk, CT 06851

205 KAECHELE PL

Location	205 KAECHELE PL	Mblu	81/ 2602/ 9/ /
Acct#	R0148640	Owner	SOUTHERN NEW ENGLAND TEL
Assessment	\$104,120	Appraisal	\$148,730
PID	29859	Building Count	1

Current Value

Appraisal					
Valuation Year	Improvements	Land	Total		
2017	\$51,340	\$97,390	\$148,730		
	Assessment				
Valuation Year	Improvements	Land	Total		
2017	\$35,950	\$68,170	\$104,120		

Owner of Record

Owner	SOUTHERN NEW ENGLAND TEL	Sale Price	\$0
Co-Owner	C/O FRONTIER COMMUNICATIONS - TAX DPMT	Certificate	
Address	401 MERRITT 7	Book & Page	0/0
	NORWALK , CT 06851	Sale Date	
		Instrument	

Ownership History

Ownership History					
Owner	Sale Price	Certificate	Book & Page	Instrument	Sale Date
SOUTHERN NEW ENGLAND TEL	\$0		0/ 0		

Building Information

Building 1 : Sectior	1		
Year Built:			
Living Area:	0		Building Photo
Replacement Cost:	\$0		
Building Percent			
Good:			
Replacement Cost			
Less Depreciation:	\$0		
l	Building At	tributes	
Field		Description	
Style		Vacant Land	

Model	
Grade:	
Stories:	
Occupancy:	
Exterior Wall 1:	
Exterior Wall 2:	
Roof Structure:	
Roof Cover:	
Interior Wall 1:	
Interior Wall 2:	
Interior Flr 1:	
Interior Flr 2	
Heat Fuel:	
Heat Type:	
AC Type:	
Total Bedrooms	
Total Full Baths	
Total Half Baths	
Total Xtra Fixtrs:	
Total Rooms	
Bath Style:	
Kitchen Style:	
Fireplaces	
Fin Bsmt Area	
Fin Bsmt Quality	
Bsmt Garages	



(http://images.vgsi.com/photos2/BridgeportCTPhotos//\00\03 \05/86.JPG)

Building Layout

(http://images.vgsi.com/photos2/BridgeportCTPhotos//Sketches/

Building Sub-Areas (sq ft) <u>Legend</u>

No Data for Building Sub-Areas

Extra Features

Extra Features	Legend
No Data for Extra Features	

Land

Land Use		Land Line Valua	Land Line Valuation	
Use Code	499	Size (Acres)	0.15	
Description	Utility Vac Ln	Frontage	0	
Zone	RA	Depth	0	
Neighborhood	2080	Assessed Value	\$68,170	
Alt Land Appr	No	Appraised Value	\$97,390	
Category				

Outbuildings

>

Outbuildings						
Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
SHD3	Shed w/ Lt	СМ	Comm	384 SF	\$6,910	1
SHD3	Shed w/ Lt	СМ	Comm	384 SF	\$6,910	1
SHD3	Shed w/ Lt	СМ	Comm	576 SF	\$10,370	1
FN1	Fence, Chain	8	8 ft	350 LF	\$3,150	1
TWR	Tower			120 LF	\$24,000	1

Valuation History

Appraisal					
Valuation Year	Improvements	Land	Total		
2017	\$51,340	\$97,390	\$148,730		
2016	\$51,340	\$97,390	\$148,730		
2015	\$51,340	\$97,390	\$148,730		

Assessment					
Valuation Year	Improvements	Land	Total		
2017	\$35,950	\$68,170	\$104,120		
2016	\$35,950	\$68,170	\$104,120		
2015	\$35,950	\$68,170	\$104,120		

(c) 2016 Vision Government Solutions, Inc. All rights reserved.

Google Maps 205 Kaechele Pl



6QFM+88 Bridgeport, Connecticut



Sprint	PROJECT: SITE NAME: SITE CASCADE:	2.5 EQUIPMENT DEPLOYMEN BRIDGEPORT NORTH CT52XC002
	SITE NUMBER:	841288
	SITE ADDRESS:	2 KAECHELE PLACE BRIDGEPORT, CT 06606
	SITE TYPE:	MONOPOLE
CASILE	MARKET:	N. ENGLAND
	PRO IEGT DECODIDION	

SITE INFORMATION	AREA MAP	PROJECT DESCRIPTION		DRAWING
TOWER OWNER:	a sector a de la companya	SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.	SHEET NO.	SHEET
CROWN ATLANTIC COMPANY LLC 2000 CORPORATE DRIVE CANONSBURG, PA 15317 (704) 405-6555		REMOVE EXISTING CLEARWIRE CABINET AND PAD REMOVE EXISTING MOUNT INSTALL NEW MOUNT INSTALL NEW ELTEK CABINET AND PAD REMOVE (3) EXISTING PANEL ANTENNAS FROM TOWER REMOVE (3) EXISTING PANEL ANTENNAS FROM TOWER	T-1 SP-1 SP-2 SP-3	TITLE SHEET & PROJECT D SPRINT SPECIFICATIONS SPRINT SPECIFICATIONS SPRINT SPECIFICATIONS
LATITUDE (NAD83): 41°13′24.0″N 41.223333′	and a second sec	 INSTALL (3) INVV-65B-R4 PANEL ANTENNAS ON TOWER INSTALL (3) NOKIA/AAHC PANEL ANTENNAS ON TOWER INSTALL (3) 1900MHz 4x45W-65MHz RRHs ON TOWER INSTALL (6) RRH 2x50-B00MHz RRHs ON TOWER INSTALL (4) HYBRID CABLES 	A-1 A-2 A-3 A-4	SITE PLAN TOWER ELEVATION & CABLI ANTENNA LAYOUT & MOUN EQUIPMENT & MOUNTING D
LONGITUDE (NAD83): -73' 13' 00.4" W -73.216778'	and the second s	REMOVE (6) COAX	A-5 A-6 E-1	CIVIL DETAILS PLUMBING DIAGRAM ELECTRICAL & GROUNDING ELECTRICAL & GROUNDING
<u>COUNTY:</u> FAIRFIELD				
ZONING JURISDICTION: CITY OF BRIDGEPORT ZONING DISTRICT:		THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT, INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS, THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER		
DOWED COMPANY.	φ	STRUCTURAL ANALYSIS MUST INCLUDE BOTH STRUCTURE AND MOUNT.		
UNITED ILLUMINATING CO (800) 722–5584 SPRINT CONSTRUCTION: TBD CROWN PM: SCOTT WIATROSKI (201) 236–9228	EDCATION MAP	APPLICABLE CODES ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES. 1. INTERNATIONAL BUILDING CODE (2015 IBC) 2. TIA-222-G OR LATEST EDITION 3. NFPA 780 - LIGHTNING PROTECTION CODE 4. 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION 5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS 6. LOCAL BUILDING CODE 7. CITY/COUNTY ORDINANCES		
5	where a state of the state of t	Know what's below. Call before you dig. www.cdl811.com		

YMENT	6580 Sprint Parkway Overland Park, Kansas 66251				
	FROM ZERO TO INFINICY the solutions are endless 1033 Watervitet Shaker Rd Albany, NY 12205 Phone: 518-690-0790 Fax: 518-690-0793 www.infinity.com JOB NUMBER 526-103				
5					
	ENGINEERING LICENSE:				
IG INDEX	1 50 5 (ALLE 36) SIE				
ET TITLE REV.	NERIA Xalerere*=				
r data 1	0. No. 24705				
1	1 328 1 & 2018 AS				
1	ONAL ENUIT				
BLE PLAN 1	southin the				
UNTING DETAILS 1					
	DRAWING NOTICE:				
NG DETAILS 1	THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE				
NG DETAILS 1	WITHOUT THE EXPRESS WRITTEN CONSENT OF				
	DESCRIPTION DATE BY REV				
	STRUCTURAL UPDATED 09/12/18 RMS 1 ISSUED FOR CONSTRUCTION 08/10/18 RMS 0				
	CARRIER COMMENTS 06/27/18 SL B				
	BRIDGEPORT NORTH				
	SITE CASCADE:				
	CT52XC002				
	SITE ADDRESS:				
	2 KAECHELE PLACE				
	BRIDGEPORT, CT 06606				
	SHEET DESCRIPTION:				
	TITLE SHEET				
	& PROJECT DATA				
	SHEET NUMBER:				
	T_1				

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES. CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

- THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING
- 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
- 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT
- 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
- 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
- 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
- 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
- 7. AMERICAN CONCRETE INSTITUTE (ACI)
- 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
- 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
- 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
- 11. PORTLAND CEMENT ASSOCIATION (PCA)
- 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
- 13. BRICK INDUSTRY ASSOCIATION (BIA)
- 14. AMERICAN WELDING SOCIETY (AWS)
- 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
- 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
- 17. DOOR AND HARDWARE INSTITUTE (DHI)
- 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
- 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.
- 1.5 DEFINITIONS:
- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT' DRAWINGS.
 - DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE
- C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STACING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 - GENERAL

- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- PART 2 PRODUCTS (NOT USED) PART 3 - EXECUTION
- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - SHEET IN THE CONSTRUCTION DOCUMENTS.
 - EQUIPMENT AND UPON RECEIPT SHALL:
 - ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - AS REQUIRED IN AGREEMENT
 - SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND TO SITE

3.2 DELIVERABLES:

- NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.
- SECTION 01 300 CELL SITE CONSTRUCTION CO.
- PART 1 GENERAL
- THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

 - AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 NOTICE TO PROCEED

AND THE ISSUANCE OF THE WORK ORDER.

TOWER OWNER NOTIFICATION ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.

- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- **3.1 FUNCTIONAL REQUIREMENTS:**
 - PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - APPROVALS WHILE THE WORK IS BEING PERFORMED.
- D. DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:



^{1.15} USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

CONTINUE FROM SP-1

- 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
- 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
- 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
- INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
- 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
- 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
- 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
- 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
- 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES
- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
- 19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
- 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."
- 3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:
 - CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY ACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
- IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
- CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN
- 3.3 DELIVERABLES:
 - CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
 - B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 - 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 - 2. PROJECT PROGRESS REPORTS
 - CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD 3. NOTIFICATION).
 - 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

- 5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- 7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- 8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
- 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.
- SECTION 01 400 SUBMITTALS & TESTS
- PART 1 GENERAL
- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS:
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 - 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 - 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 - 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION
 - 5. CHEMICAL GROUNDING DESIGN
- D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - COAX SWEEPS AND FIBER TESTS PER CURRENT VERSION OF SPRINT'S 1. TS-0200 ANTENNA LINE ACCEPTANCE STANDARDS.
 - 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING
 - AZIMUTH, DOWNTILT, AGL UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
- 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

- DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
- 6. LIEN WAIVERS
- 7. FINAL PAYMENT APPLICATION
- 8. REQUIRED FINAL CONSTRUCTION PHOTOS
- (SPRINTS DOCUMENT REPOSITORY OF RECORD).
- 1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE
- 1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 REQUIREMENTS FOR TESTING:
- A. THIRD PARTY TESTING AGENCY:
 - SOIL, ROCK, AND GROUNDWATER CONDITIONS.

 - 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
- 3.2 REQUIRED TESTS:
 - A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

 - COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT
 - CONCRETE PAVING.

 - 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 - ACCEPTANCE STANDARDS.
 - 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 - 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

OR SPRINT REPRESENTATIVE.

EXISTING FACILITIES.

3.3 REQUIRED INSPECTIONS



CONTINUE FROM SP-2

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
- 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
- 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL
- 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE
- 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
- 2. STRUCTURAL BACKFILL COMPACTION REPORTS. 3. SITE RESISTANCE TO EARTH TEST,
- 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
- 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS
- 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS"
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
 - TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS NDICATING DEPTH.
- 2. CONDUITS, CONDUCTORS AND GROUNDING; PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD
- 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
- 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS: PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; ANTLENNA GROUND BAR, LQUIPMENI GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROFING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER (UNDODOLE TOWER/MONOPOLE.
- 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF:
- 6. SITE LAYOUT PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
- FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL
- 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
- 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY,

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 WEEKLY REPORTS:
- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS, THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
 - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 - 1. 1SHELTER AND TOWER OVERVIEW.
- 2. TOWER FOUNDATION(S) FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
- 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
- 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
- 5. PHOTOS OF TOWER SECTION STACKING.
- 6. CONCRETE TESTING / SAMPLES.
- 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION
- 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
- 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
- 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE
- 11. COAX CABLE ENTRY INTO SHELTER.
- 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
- 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
- 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
- 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
- 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
- 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
- 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL
- 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL
- 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- ALL CAD WELDS AND BEND RADII).
- 25. ALL BTS GROUND CONNECTIONS.
- 26, ALL GROUND TEST WELLS
- 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
- 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
- 30. GPS ANTENNAS
- 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
- 32. DOGHOUSE/CABLE EXIT FROM ROOF.
- ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
- 34. MASTER BUS BAR
- 35. TELCO BOARD AND NIU
- 36. ELECTRICAL DISTRIBUTION WALL
- 37. CABLE ENTRY WITH SURGE SUPPRESSION
- 38. ENTRANCE TO EQUIPMENT ROOM
- 39. COAX WEATHERPROOFING-TOP AND BOTTOM OF TOWER
- 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
- 41. ANTENNA AND MAST GROUNDING.
- 42. LANDSCAPING WHERE APPLICABLE

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

















SECTOR	ANTENNA MANUFACTURER	ANTENNA MODEL	RAD CENTER	AZIMUTH	RRH/ODU MAKE AND MODEL	
	COMMSCOPE	NNVV-65B-R4	140'	25°	(1) ALU ((2) AL	1900MHZ 4X45W-65MHZ .U 800MHZ 2x50-800
7	NOKIA	AAHC	140'	25°	INTE	GRATED 2.5 RADIO
1	COMMSCOPE	NNVV-65B-R4	140'	145°	(1) ALU : (2) AL	1900MHZ 4X45W-65MHZ U 800MHZ 2x50-800
2	NOKIA	AAHC	140'	145°	INTEGRATED 2.5 RADIO	
	ANDREW	VHLP2-18	140'	180*	(1) DRAGONWAVE HORIZON COM	
	COMMSCOPE	NNVV-65B-R4	140'	265°	(1) ALU ((2) AL	1900MHZ 4X45W-65MHZ .U 800MHZ 2x50-800
3	NOKIA	AAHC	140'	265°	INTEGRATED 2.5 RADIO	
	ANDREW	VHLP2-23	140'	300'	(1) DRAGON	WAVE HORIZON COMP
	117	FEEDER	CABLE	S		
	MANUFACTURER	MOL	DEL	LENGTH	QTY	
	RFS	HB114-13U3	M12-200F	200'±	(3)	
	RFS	HB114-21U3	M12-200F	200'±	(1)	





Hello Mr. Nelson,

I work for Crown Castle and have an inquiry regarding the original zoning documents for a cell tower and I am hoping your office can provide more information.

We are applying for CSC Zoning Approval for Sprint to modify their antennas and new requirements ask that we procure original zoning documents from the jurisdiction, if possible. However, if these documents are not available, please let me know.

The tower is located at 205 Kaechele Place Bridgeport, CT. 06851. I believe Southern New England Telecommunications owned the property and signed the lease at that time.

If you have any questions, please don't hesitate to call or e-mail me.

Thanks,

Kristian McKay Real Estate Specialist – East Area T: (704) 405-6612 | M: (704) 713-5728 | F: (724) 416-6496

CROWN CASTLE 3530 Toringdon Way, Suite 300, Charlotte, NC 28277 Crowncastle.com Hello Mr. Buckley,

I work for Crown Castle and have an inquiry regarding the original zoning documents for a cell tower and I am hoping your office can provide more information.

We are applying for CSC Zoning Approval for Sprint to modify their antennas and new requirements ask that we procure original zoning documents from the jurisdiction, if possible. However, if these documents are not available, please let me know.

The tower is located at 205 Kaechele Place Bridgeport, CT. 06851. I believe Southern New England Telecommunications owned the property and signed the lease at that time.

If you have any questions, please don't hesitate to call or e-mail me.

Thanks,

Kristian McKay Real Estate Specialist – East Area T: (704) 405-6612 | M: (704) 713-5728 | F: (724) 416-6496

CROWN CASTLE 3530 Toringdon Way, Suite 300, Charlotte, NC 28277 Crowncastle.com



Date: September 10, 2018

Timothy Howell Crown Castle 3530 Toringdon Way Suite 300 Charlotte, NC 28277	Paul J. Ford ar 250 East Broa Columbus, OH (614) 221-6679	nd Company d St., Suite 600 43215 }
Subject:	Structural Analysis Report	
Carrier Designation:	<i>Clearwire Corp</i> Co-Locate Carrier Site Number: Carrier Site Name:	CT52XC002 CT52XC002
Crown Castle Designation:	Crown Castle BU Number: Crown Castle Site Name: Crown Castle JDE Job Number: Crown Castle Work Order Number: Crown Castle Order Number:	841288 BRIDGEPORT NORTH 499049 1628084 436906 Rev. 1
Engineering Firm Designation:	Paul J. Ford and Company Project Number:	37518-0456.008.7805
Site Data:	2 Kaechele Place, BRIDGEPORT, Fairfield C Latitude <i>41° 13' 24.04''</i> , Longitude -73° <i>13' 0.</i> 150 Foot - Monopole Tower	ounty, CT 38″

Dear Timothy Howell,

Paul J. Ford and Company is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

Sufficient Capacity

This analysis has been performed in accordance with the ANSI/TIA-222-H Standard. This analysis utilizes an ultimate 3-second gust wind speed of 125 mph from the 2016 Connecticut State Building Code per section 1609.3 and Appendix N. Risk Category II, Exposure Category B and Topographic Category 1 with a maximum Topographic Factor, Kzt, of 1.0 were used in this analysis.

Respectfully submitted by:

Aaron E. Pike, E.I. Structural Designer apike@pauljford.com





Date: September 10, 2018

Timothy Howell Crown Castle 3530 Toringdon Way Suite 300 Charlotte, NC 28277	Paul J. Ford a 250 East Broa Columbus, OH (614) 221-667	nd Company d St., Suite 600 I 43215 9
Subject:	Structural Analysis Report	
Carrier Designation:	<i>Clearwire Corp</i> Co-Locate Carrier Site Number: Carrier Site Name:	CT52XC002 CT52XC002
Crown Castle Designation:	Crown Castle BU Number: Crown Castle Site Name: Crown Castle JDE Job Number: Crown Castle Work Order Number: Crown Castle Order Number:	841288 BRIDGEPORT NORTH 499049 1628084 436906 Rev. 1
Engineering Firm Designation:	Paul J. Ford and Company Project Number:	37518-0456.008.7805
Site Data:	2 Kaechele Place, BRIDGEPORT, Fairfield C Latitude <i>41° 13' 24.04"</i> , Longitude -73° <i>13' 0.</i> 150 Foot - Monopole Tower	ounty, CT 38″

Dear Timothy Howell,

Paul J. Ford and Company is pleased to submit this **"Structural Analysis Report"** to determine the structural integrity of the above mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

Sufficient Capacity

This analysis has been performed in accordance with the ANSI/TIA-222-H Standard. This analysis utilizes an ultimate 3-second gust wind speed of 125 mph from the 2016 Connecticut State Building Code per section 1609.3 and Appendix N. Risk Category II, Exposure Category B and Topographic Category 1 with a maximum Topographic Factor, Kzt, of 1.0 were used in this analysis.

Respectfully submitted by:

Aaron E. Pike, E.I. Structural Designer apike@pauljford.com

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment ConfigurationTable 2 - Other Considered Equipment

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

- 3.1) Analysis Method
- 3.2) Assumptions

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary) Table 5 – Tower Component Stresses vs. Capacity Table 6 - Microwave Dish Tilt (Sway) Results for 60 mph Rev H Service 4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 150 ft Monopole tower. All information on the monopole was obtained from the mapping referenced in Table 3 of this report.

2) ANALYSIS CRITERIA

Building Code:	2016 CSBC (2012 IBC)
TIA-222 Revision:	TIA-222-H
Risk Category:	II
Wind Speed:	125 mph
Exposure Category:	В
Topographic Factor:	1
Ice Thickness:	1.275 in
Wind Speed with Ice:	50 mph
Service Wind Speed:	60 mph

Table 1 - Proposed Equipment Configuration

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		1	andrew	VHLP2-18		
	143.0	1	andrew	VHLP2-23		
138.0 140.0		2	dragonwave	HORIZON COMPACT		1/2 1-1/4 1-5/8
		3	alcatel lucent	PCS 1900MHZ 4X45W- 65MHZ	2	
	140.0	6	alcatel lucent	RRH2X50-800	3	
	3	commscope	NNVV-65B-R4 w/ MP		1-0/0	
		3 nokia AAHC w/ Mount Pipe				
	120 0	1	clearwire	CW JUNCTION BOX		
	130.0	1	site pro	RMQP-496-HK		

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		3	cci antennas	HPA-65R-BUU-H6		
		6	cci antennas	TPX-070821		
		3	ericsson	RRUS 11		
		3	ericsson	RRUS 32		
		3	ericsson	RRUS 32 B2		
	154.0	3	ericsson	RRUS 32 B66	12	1-5/8
150.0	154.0	3	powerwave tech.	1001940	1	3/8
		6	powerwave tech.	7020.00	4	3/4
		3	powerwave tech.	7770.00		
		3	powerwave tech.	TT19-08BP111-001		
		3	quintel tech.	QS66512-2		
		2	raycap	DC6-48-60-18-8F		
	150.0	1	tower mounts	Platform Mount (LP 101-1)		
		3	ericsson	RRUS 11		
147.0	147.0	1	raycap	TME-DC6-48-60-18-8F		
		1	tower mounts	Pipe Mount [PM 601-3]		
		3	commscope	LNX-6515DS-A1M		
		3	ericsson	AIR -32 B2A/B66AA		
120.0	100.0	3	ericsson	AIR 21 B2A/B4P	13	1-5/8
120.0	120.0	3	ericsson	KRY 112 144/1	1	1-1/2
		3	ericsson	RRUS 11 B12		
		1	tower mounts	Platform Mount [LP 301-1]		
	103.0	1	gps	GPS_A		
		3	alcatel lucent	B13 RRH 4X30		
		3	alcatel lucent	B25 RRH2X60 PCS		
		3	alcatel lucent	B66A RRH4X45		
99.0	00.0	3	antel	BXA-171063/8CF w/ Mount Pipe	12 1	1-5/8 1/2
	99.0	3	antel	BXA-70063/4CF w/ MP	2	1-1/4
		2	commscope	RC2DC-3315-PF-48		
		6	CSS	X7CQAP-465-VR0 w/ MP		
		6	rfs celwave	FD9R6004/2C-3L		
		1	tower mounts	T-Arm Mount [TA 602-3]		

Table 2 - Other Considered Equipment

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	FDH, 08-09065E G1, 09/23/2008	5110784	CCISITES
4-POST-MODIFICATION INSPECTION	TEP, 25567.42283, 10/22/2014	5401472	CCISITES
4-POST-MODIFICATION INSPECTION	TEP, 25567_26102, 06/05/2015	5739992	CCISITES
4-POST-MODIFICATION INSPECTION	Crown Castle, 841288, 05/31/2017	6894091	CCISITES
4-POST-MODIFICATION INSPECTION	TEP, 25567.87194, 06/08/2018	7594134	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	FDH, 08-09065E NA, 09/23/2008	5110783	CCISITES
4-TOWER MAPPING	GPD, 2014777.841288.02, 04/11/2008	4710143	CCISITES

3.1) Analysis Method

tnxTower (version 8.0.4.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built and maintained in accordance with the manufacturer's specifications.
- 2) The configuration of antennas, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 3) Monopole was modified in conformance with the referenced modification drawings.
- 4) The monopole manufacturer drawings are not available at the time of this analysis. Therefore, we have assumed pole shaft and base plate steel yield strength(s) (Fy) as shown in the attached calculations. Anchor rods are assumed to be ASTM A615 #18J, 2.25" diam, (Fu = 100 ksi, Fy = 75 ksi).

This analysis may be affected if any assumptions are not valid or have been made in error. Paul J. Ford and Company should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Elevation (ft)	Component Type	Size	Critical Element	% Capacity	Pass / Fail
150 - 145	Pole	TP15.732x15x0.2188	Pole	22.4%	Pass
145 - 140	Pole	TP16.463x15.732x0.2188	Pole	35.9%	Pass
140 - 135	Pole	TP17.195x16.463x0.2188	Pole	56.1%	Pass
135 - 130	Pole	TP17.927x17.195x0.2188	Pole	75.1%	Pass
130 - 128.5	Pole	TP18.146x17.927x0.2188	Pole	80.4%	Pass
128.5 - 128.25	Pole + Reinf.	TP18.183x18.146x0.6688	Reinf. 12 Tension Rupture	40.5%	Pass
128.25 - 123.25	Pole + Reinf.	TP18.915x18.183x0.6438	Reinf. 12 Tension Rupture	49.9%	Pass
123.25 - 118.25	Pole + Reinf.	TP19.646x18.915x0.6188	Reinf. 12 Tension Rupture	60.0%	Pass
118.25 - 113.25	Pole + Reinf.	TP20.378x19.646x0.6063	Reinf. 12 Tension Rupture	71.3%	Pass
113.25 - 109	Pole + Reinf.	TP21x20.378x0.5938	Reinf. 12 Tension Rupture	80.4%	Pass
109 - 108.75	Pole + Reinf.	TP21.038x21x0.725	Reinf. 7 Tension Rupture	61.4%	Pass
108.75 - 104.17	Pole + Reinf.	TP21.729x21.038x0.7	Reinf. 7 Tension Rupture	68.4%	Pass
104.17 - 103.92	Pole + Reinf.	TP21.767x21.729x0.975	Reinf. 7 Tension Rupture	61.3%	Pass
103.92 - 103.17	Pole + Reinf.	TP21.88x21.767x0.95	Reinf. 7 Tension Rupture	62.3%	Pass
103.17 - 102.92	Pole + Reinf.	TP21.918x21.88x1.125	Reinf. 7 Tension Rupture	50.8%	Pass
102.92 - 102.42	Pole + Reinf.	TP21.994x21.918x1.1	Reinf. 7 Tension Rupture	51.4%	Pass
102.42 - 102.17	Pole + Reinf.	TP22.031x21.994x0.925	Reinf. 7 Tension Rupture	56.5%	Pass
102.17 - 100.92	Pole + Reinf.	TP22.22x22.031x0.925	Reinf. 7 Tension Rupture	58.0%	Pass
100.92 - 100.67	Pole + Reinf.	TP22.258x22.22x1	Reinf. 7 Tension Rupture	56.7%	Pass
100.67 - 99.58	Pole + Reinf.	TP22.422x22.258x1	Reinf. 7 Tension Rupture	58.0%	Pass
99.58 - 99.33	Pole + Reinf.	TP22.46x22.422x1.375	Reinf. 17 Tension Rupture	41.5%	Pass
99.33 - 95.25	Pole + Reinf.	TP23.076x22.46x1.325	Reinf. 17 Tension Rupture	45.6%	Pass
95.25 - 95	Pole + Reinf.	TP23.114x23.076x1.025	Reinf. 18 Tension Rupture	56.4%	Pass
95 - 90	Pole + Reinf.	TP23.869x23.114x1	Reinf. 18 Tension Rupture	62.2%	Pass
90 - 85	Pole + Reinf.	TP24.624x23.869x0.9625	Reinf. 18 Tension Rupture	67.8%	Pass
85 - 80.5	Pole + Reinf.	TP25.304x24.624x0.925	Reinf. 18 Tension Rupture	72.6%	Pass
80.5 - 80.25	Pole + Reinf.	TP25.341x25.304x1.3	Reinf. 6 Tension Rupture	60.2%	Pass
80.25 - 75.25	Pole + Reinf.	TP26.096x25.341x1.25	Reinf. 6 Tension Rupture	64.5%	Pass
75.25 - 73.58	Pole + Reinf.	TP26.348x26.096x1.225	Reinf. 6 Tension Rupture	66.0%	Pass
73.58 - 73.33	Pole + Reinf.	TP26.386x26.348x1.225	Reinf. 6 Tension Rupture	66.2%	Pass
73.33 - 72	Pole + Reinf.	TP27.04x26.386x1.2	Reinf. 6 Tension Rupture	67.3%	Pass
72 - 67	Pole + Reinf.	TP26.897x26.087x1.2625	Reinf. 6 Tension Rupture	69.0%	Pass
67 - 66.75	Pole + Reinf.	TP26.937x26.897x1.2625	Reinf. 6 Tension Rupture	69.2%	Pass
66.75 - 66.5	Pole + Reinf.	TP26.978x26.937x1.3625	Reinf. 5 Tension Rupture	60.2%	Pass
66.5 - 61.5	Pole + Reinf.	TP27.788x26.978x1.3125	Reinf. 5 Tension Rupture	63.3%	Pass
61.5 - 56.5	Pole + Reinf.	TP28.598x27.788x1.2625	Reinf. 5 Tension Rupture	66.2%	Pass
56.5 - 51.5	Pole + Reinf.	TP29.408x28.598x1.2375	Reinf. 5 Tension Rupture	69.1%	Pass
51.5 - 48.25	Pole + Reinf.	TP29.934x29.408x1.2125	Reinf. 5 Tension Rupture	70.9%	Pass
48.25 - 48	Pole + Reinf.	TP29.974x29.934x1.6375	Reinf. 2 Compression	62.3%	Pass
48 - 44.25	Pole + Reinf.	TP30.582x29.974x1.6125	Reinf. 2 Compression	64.0%	Pass
44.25 - 44	Pole + Reinf.	TP30.622x30.582x1.7125	Reinf. 2 Compression	60.4%	Pass

Elevation (ft)	Component Type	Size	Critical Element	% Capacity	Pass / Fail
44 - 43.08	Pole + Reinf.	TP30.771x30.622x1.7125	Reinf. 2 Compression	60.8%	Pass
43.08 - 42.83	Pole + Reinf.	TP30.812x30.771x1.7125	Reinf. 2 Compression	60.9%	Pass
42.83 - 37.83	Pole + Reinf.	TP31.622x30.812x1.6375	Reinf. 2 Compression	63.0%	Pass
37.83 - 34	Pole + Reinf.	TP32.89x31.622x1.6125	Reinf. 2 Compression	64.5%	Pass
34 - 29	Pole + Reinf.	TP32.462x31.617x1.7063	Reinf. 2 Compression	63.9%	Pass
29 - 24	Pole + Reinf.	TP33.306x32.462x1.6563	Reinf. 2 Compression	65.5%	Pass
24 - 23.75	Pole + Reinf.	TP33.348x33.306x1.6563	Reinf. 2 Compression	65.6%	Pass
23.75 - 23.5	Pole + Reinf.	TP33.391x33.348x1.6563	Reinf. 2 Compression	65.7%	Pass
23.5 - 18.5	Pole + Reinf.	TP34.235x33.391x1.6063	Reinf. 2 Compression	67.2%	Pass
18.5 - 13.5	Pole + Reinf.	TP35.08x34.235x1.5563	Reinf. 2 Compression	68.6%	Pass
13.5 - 11	Pole + Reinf.	TP35.502x35.08x1.5313	Reinf. 2 Compression	69.3%	Pass
11 - 10.75	Pole + Reinf.	TP35.544x35.502x1.2313	Reinf. 3 Tension Rupture	66.2%	Pass
10.75 - 6	Pole + Reinf.	TP36.347x35.544x1.2563	Reinf. 3 Tension Rupture	67.5%	Pass
6 - 5.75	Pole + Reinf.	TP36.389x36.347x1.5313	Reinf. 3 Tension Rupture	58.4%	Pass
5.75 - 3.25	Pole + Reinf.	TP36.811x36.389x1.5063	Reinf. 3 Tension Rupture	59.1%	Pass
3.25 - 3	Pole + Reinf.	TP36.853x36.811x1.1563	Reinf. 20 Compression	74.6%	Pass
3 - 0	Pole + Reinf.	TP37.36x36.853x1.1313	Reinf. 20 Compression	75.4%	Pass
				Summary	
			Pole	80.4%	Pass
			Reinforcement	80.4%	Pass

Table 5 - Tower Component Stresses vs. Capacity – LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	78.0	Pass
1	Base Plate	0	53.7	Pass
1	Base Foundation Steel	0	63.5	Pass
1	Base Foundation Soil Interaction	0	54.8	Pass
1	Flange Connection	109	86.7	Pass

Structure Rating (max from all components) =	86.7%

• All structural ratings are per TIA-222-H section 15.5

Notes:

1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

Dish Elevation ft	Dish	Dish Diameter ft	Dish Frequency GHz	Analysis Results Tilt at Service Wind deg	Analysis Results Twist at Service Wind deg
143.0	VHLP2-23	2.175		1.4577	0.0087
143.0	VHLP2-18	2.175		1.4577	0.0087

Table 6 - Microwave Dish Tilt (Sway) Results for 60 mph Rev H Service

4.1) Recommendations

The monopole and its foundation have sufficient capacity to carry the proposed loading configuration. No modifications are required at this time.



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT52XC002

Bridgeport North 2 Kaechele Place Bridgeport, CT 06606

August 29, 2018

EBI Project Number: 6218005889

Site Compliance Summary					
Compliance Status:	COMPLIANT				
Site total MPE% of					
FCC general	1/ 07 0/				
population	14.07 %				
allowable limit:					



August 29, 2018

SPRINT Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Emissions Analysis for Site: CT52XC002 - Bridgeport North

EBI Consulting was directed to analyze the proposed SPRINT facility located at **2 Kaechele Place**, **Bridgeport**, **CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm2). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

<u>General population/uncontrolled exposure</u> limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limits for the 850 MHz Band is approximately 567 μ W/cm². The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) as well as the 18 GHz and 23 GHz microwave bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



<u>Occupational/controlled exposure</u> limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over their exposure and can exercise control over the potential for exposure and can exercise through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **2 Kaechele Place**, **Bridgeport**, **CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 50 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 6) 1 microwave channel (18 GHz) was considered for Sector B of the proposed installation. This channel has a transmit power of 1 Watt.



- 7) 1 microwave channel (23 GHz) was considered for Sector C of the proposed installation. This channel has a transmit power of 1 Watt.
- 8) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 9) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 10) The antennas used in this modeling are the **Commscope NNVV-65B-R4 and the Nokia AAHC** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands and the **Commscope VHLP2-18** and **Commscope VHLP2-23** for microwave transmissions in the 18 GHz and 23 GHz bands respectively. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- The antenna mounting height centerlines of the proposed panel antennas are 140 feet above ground level (AGL) for Sectors A, B & C and 143 feet above ground level (AGL) for the microwave dishes on Sectors B & C.
- 12) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

Sector:	А	Sector:	В	Sector:	С	
Antenna #:	1	Antenna #:	1	Antenna #:	1	
Maka / Modaly	Commscope	Maka / Modali	Commscope	Maka / Modal	Commscope	
Wiake / Wiouei.	NNVV-65B-R4	IVIAKE / IVIOUEI.	NNVV-65B-R4	wiake / wiouei.	NNVV-65B-R4	
Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd	
Height (AGL):	140 feet	Height (AGL):	140 feet	Height (AGL):	140 feet	
Frequency Bands	850 MHz /	Frequency Bands	850 MHz /	Frequency Bands	850 MHz /	
Trequency Danus	1900 MHz (PCS)	Trequency Danus	1900 MHz (PCS)	Trequency Danus	1900 MHz (PCS)	
Channel Count	10	Channel Count	10	Channel Count	10	
Total TX	TX Z20 W-tt- Total TX 200 W-tt-		Total TX	290 Watta		
Power(W):	200 watts	Power(W):	200 watts	Power(W):	280 watts	
ERP (W):	7,378.61	ERP (W):	7,378.61	ERP (W):	7,378.61	
Antenna A1	1 92 0/	Antenna B1	1 97 0/	Antenna C1	1.82 %	
MPE%	1.02 70	MPE%	1.62 70	MPE%		
Antenna #:	2	Antenna #:	2	Antenna #:	2	
Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC	
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd	
Height (AGL):	140 feet	Height (AGL):	140 feet	Height (AGL):	140 feet	
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	
Channel Count	8	Channel Count	8	Channel Count	8	
Total TX	160 W-#-	Total TX	160 W-#-	Total TX	160 W-#-	
Power(W):	160 watts	Power(W):	160 watts	Power(W):	160 watts	
ERP (W):	5,118.23	ERP (W):	5,118.23	ERP (W):	5,118.23	
Antenna A2	1.02.0/	Antenna B2	1.02.0/	Antenna C2	1.02.0/	
MPE%	1.03 %	MPE%	1.03 %	MPE%	1.03 %	

Microwave Backhaul Data								
Antenna Type:	Gain (dBd)	Height (feet AGL):	Frequency Bands	Channel Count	Total TX Power(W)	ERP (W)	MPE %	Sector
Commscope VHLP2-18	36.85 dBd	143	18 GHz	1	1	4,841.72	0.10	В
Commscope VHLP2-23	38.55 dBd	143	23 GHz	1	1	7,161.43	0.14	С

Site Composite MPE%					
Carrier	MPE%				
SPRINT – Max (Sector C)	2.99 %				
Verizon Wireless	4.12 %				
Clearwire	0.17 %				
T-Mobile	5.03 %				
AT&T	2.56 %				
Site Total MPE %:	14.87 %				

SPRINT Sector A Total:	2.85 %
SPRINT Sector B Total:	2.95 %
SPRINT Sector C Total:	2.99 %
Site Total:	14.87 %



Sprint Maximum MPE Power Values (Sector C)

SPRINT _ Frequency Band / Technology (All Sectors)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (µW/cm ²)	Frequency (MHz)	Allowable MPE (µW/cm ²)	Calculated % MPE
Sprint 850 MHz CDMA	1	376.73	140	0.75	850 MHz	567	0.13%
Sprint 850 MHz LTE	2	941.82	140	3.77	850 MHz	567	0.67%
Sprint 1900 MHz (PCS) CDMA	5	511.82	140	5.12	1900 MHz (PCS)	1000	0.51%
Sprint 1900 MHz (PCS) LTE	2	1,279.56	140	5.12	1900 MHz (PCS)	1000	0.51%
Sprint 2500 MHz (BRS) LTE	8	639.78	140	10.25	2500 MHz (BRS)	1000	1.03%
Sprint 23 GHz Microwave	1	7,161.43	140	1.43	23 GHz	1000	0.14%
						Total:	2.99%



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	2.85 %
Sector B:	2.95 %
Sector C:	2.99 %
SPRINT Maximum	2.00.%
MPE % (Sector C):	2.99 %
Site Total:	14.87 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **14.87** % of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Delivered Wednesday 9/12/2018 at 10:47 am

DELIVERED

Signed for by: M.SCOTT



GET STATUS UPDATES OBTAIN PROOF OF DELIVERY

FROM

Kristian McKay STE 300 3530 Toringdon Way CHARLOTTE, NC US 28277 704 405-6612

то

SNET Frontier Communications. 401 Merrit 7 NORWALK, CT US 06851 800 921-8101

Travel History

Shipment Facts

23

?



Delivered Wednesday 9/12/2018 at 10:37 am



Signed for by: R.CABANAS



GET STATUS UPDATES

OBTAIN PROOF OF DELIVERY

FROM

Kristian McKay STE 300 3530 Toringdon Way CHARLOTTE, NC US 28277 704 405-6612 то

Margaret E. Morton Government Cente Mayor :Joseph Peter Ganim 999 Broad St. BRIDGEPORT, CT US 06604 203 576-7201

NY

MORE FROM FEDEX

LANGUAGE



Delivered Wednesday 9/12/2018 at 10:01 am

DELIVERED

Signed for by: S.BURTO



GET STATUS UPDATES

FROM

Kristian McKay STE 300 3530 Toringdon Way CHARLOTTE, NC US 28277 704 405-6612 то

Zoning Department Dennis Buckley Room 210 45 Lyon Terrace BRIDGEPORT, CT US 06604 203 581-5100

Shipment Facts

Travel History

MORE FROM FEDEX

LANGUAGE

