



1280 Route 46 West, Suite 9, Parsippany NJ, 07054

Melanie Bachman
Executive Director
CT Siting Council
10 Franklin Square
New Britain, CT 06051

Re: Notice of Exempt Modification Application
623 Pine St, Bridgeport CT 06605

Latitude: N41.1938
Longitude: W73.1644

Dear Ms. Bachman:

Sprint currently maintains 3 existing panel antennas, 3 microwave dishes and 3 remote radio units at the 118' centerline level of the existing lattice tower. Sprint proposes to swap 3 panel antennas and 3 remote radio unit at the 118' centerline on the tower. Sprint further proposes to add 6 remote radio heads, 4 hybrid cable and 48 Antenna to RRH jumper cables. Sprint is performing a new high-performance upgrade for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Please accept this letter as notification to the Council, pursuant to R.C.S.A. Section 16-50j-73, for construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter is being sent to Mayor Joseph Ganim of the City of Bridgeport as well as the City Planner for the City of Bridgeport and Radio Communications Corp, the owner of the tower.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower with proposed modifications to accommodate the revised antenna configuration as well as the latest CSC decision, tax sheet and tax map.

Existing Facility

CSC Summary Statement – CT52XC007 – 623 Pine St,
Bridgeport, CT 06605

The Communications Tower facility is located at 623 Pine St, Bridgeport CT and is owned by Radio Communications Corp, the Site coordinates are: N41.19385 W73.1644.

The existing facility consists of a 256' Lattice Tower. Sprint currently operates wireless communications equipment on a platform on a concrete slab at the facility and has 3 antennas, 2 microwave dishes and 3 RRU's mounted on at centerline of 118' feet.

Statutory Considerations

The planned modifications to the facility fall within the activities explicitly provided for in R.C.S.A. 16-50j-72(b)(2)

1. The height of the overall structure will be unaffected.
2. The proposed changes will not require an extension of the property boundaries.
3. The proposed additions will not increase the noise level at the existing facility by six decibels or more, or to levels that exceed state and/or local criteria
4. The changes will not increase the calculated “worst case” power density for the combined operations at the site to a level at or above the Federal Communications Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A Section §16-50j-72(b)(2).

Respectfully submitted,



Ryan G Bailey

Charles Cherundolo Consulting

856-625-1596

ryan@mackenzierealtyconsulting.com

Additional Recipients:

Mayor Joseph P Ganim – City of Bridgeport Mayor– Via FedEx

Thomas Gill - City Planner, City of Bridgeport - Via FedEx

Radio Communications Corp, owner of the tower – Via FedEx

Sprint[®]



"SPRINT MiMO UPGRADE"

CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

COM-EX
 Consultants

115 Route 46
 Suite E39
 Mountain Lakes, NJ 07046
 PHONE: 862.209.4300
 FAX: 862.209.4301



SCHEDULE OF REVISIONS

REV NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MiMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY: AM
CHECKED BY: NDB
SCALE: AS NOTED
JOB NO: 17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE ORIGINAL SEAL AND SIGNATURE OF A PROFESSIONAL ENGINEER

NICHOLAS D. BARILE
 PROFESSIONAL ENGINEER, CT LIC. No. 28643


CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:

TITLE SHEET

DRAWING SHEET: 1 OF 8

T-1



SITE LOCATION INFORMATION

SITE ID NUMBER: CT52XC007
 SITE NAME: BRIDGEPORT WEST
 SITE ADDRESS: 623 PINE STREET
 BRIDGEPORT, CT 06605
 PARCEL ID: 19 307 25
 CENSUS TRACT: 070300
 CENSUS BLOCK: 1046
 PROPERTY OWNER: ANDREW KNAPP
 APPLICANT: SPRINT CORPORATION
 217 ROUTE 17 N, 3RD FLOOR
 RUTHERFORD, NJ 07070
 COUNTY: NEW HAVEN COUNTY

SITE CHARACTERISTICS


LATITUDE: 41.193853
 LONGITUDE: -73.164447
 STRUCTURE TYPE: SELF-SUPPORT TOWER
 LOCATION OF PROPOSED EQUIPMENT: EXISTING EQUIPMENT ROOM
 STRUCTURE HEIGHT: ±256'-0" AGL
 ANTENNA (RAD CENTER): ±118'-0" AGL (ALPHA)
 ±118'-0" AGL (BETA)
 ±118'-0" AGL (GAMMA)

SHEET INDEX

SHEET NO.	SHEET DESCRIPTION
T-1	TITLE SHEET
C-1	ROOF PLAN & GENERAL NOTES
C-2	EXISTING & FINAL ANTENNA PLANS
C-3	ELEVATION, B.O.M., & FINAL EQUIPMENT PLAN
C-4	CONSTRUCTION DETAILS
C-5	CABLE COLOR CODING
E-1	GROUNDING DETAILS
E-2	DC POWER DETAILS & PANEL SCHEDULES

SCOPE OF WORK

THE APPLICANT PROPOSES TO REPLACE THREE (3) EXISTING ANTENNAS WITH SIX (6) NEW ANTENNAS, REMOVE THREE (3) EXISTING RRHs AND REPLACE WITH NINE (9) NEW RRHs ON EXISTING/PROPOSED MOUNTING HARDWARE, AS WELL AS REPLACE ONE (1) EQUIPMENT CABINET IN AN EXISTING BUILDING.



1 ROOF PLAN
C-1 SCALE: 3/16"=1'
(24"x36" SHEET SIZE)

- GENERAL NOTES:**
- SUBJECT PROPERTY IS KNOWN AS TAX PARCEL ID 19 307 25, CENSUS TRACT 070300, CENSUS BLOCK 1046 AS SHOWN THE OFFICIAL TAX MAP OF THE TOWN OF BRIDGEPORT, CT.
 - THE APPLICANT PROPOSES TO REPLACE THREE (3) EXISTING ANTENNAS WITH SIX (6) NEW ANTENNAS, REMOVE THREE (3) EXISTING RRHS AND REPLACE WITH NINE (9) NEW RRHS ON EXISTING/PROPOSED MOUNTING HARDWARE, AS WELL AS REPLACE ONE (1) EQUIPMENT CABINET IN AN EXISTING BUILDING.
 - CONTRACTOR SHALL NOT COMMENCE ANY WORK UNTIL HE OBTAINS, AT HIS OWN EXPENSE, ALL INSURANCE REQUIRED BY SPRINT, THE PROPERTY OWNER AND/OR PROPERTY MANAGEMENT COMPANY.
 - THIS SET OF PLANS HAS BEEN PREPARED FOR THE PURPOSES OF MUNICIPAL AND AGENCY REVIEW AND APPROVAL. THIS SET OF PLANS SHALL NOT BE UTILIZED AS CONSTRUCTION DOCUMENTS UNTIL ALL CONDITIONS OF APPROVAL HAVE BEEN SATISFIED AND EACH OF THE DRAWINGS HAVE BEEN REVISED TO INDICATED "ISSUED FOR CONSTRUCTION".
 - SITE INFORMATION SHOWN TAKEN FROM PLANS PREPARED BY URS CORPORATION AES FOR SPRINT'S INSTALLATION ON THIS FACILITY. DRAWINGS ENTITLED "SPRINT, SITE NAME: BRIDGEPORT WEST, SPRINT NUMBER: CT52XC007" DATED 10/28/09 REVISED 03/28/10. ADDITIONAL SITE INFORMATION WAS SUPPLEMENTED WITH A LIMITED SITE VISIT BY COM-EX CONSULTANTS ON 05/19/17.
 - THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES, ORDINANCES, LAWS AND REGULATIONS OF ALL MUNICIPALITIES, UTILITIES OR OTHER PUBLIC AUTHORITIES.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY OR MUNICIPAL AUTHORITIES.
 - THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER, IN WRITING, OF ANY CONFLICTS, ERRORS OR OMISSIONS PRIOR TO THE SUBMISSION OF BIDS OR PERFORMANCE OF WORK. MINOR OMISSIONS OR ERRORS IN THE BID DOCUMENTS SHALL NOT EXCUSE SAID CONTRACTOR FROM COMPLETING THIS PROJECT IN ACCORDANCE WITH THE OVERALL INTENT OF THESE DRAWINGS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING SITE IMPROVEMENTS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED AS A RESULT OF CONSTRUCTION OF THIS FACILITY.
 - THE SCOPE OF WORK FOR THIS PROJECT SHALL INCLUDE PROVIDING ALL MATERIALS, EQUIPMENT AND LABOR REQUIRED TO COMPLETE THIS PROJECT. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
 - THE CONTRACTOR SHALL VISIT THE PROJECT SITE PRIOR TO SUBMITTING A BID TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
 - CONTRACTOR SHALL VERIFY ANTENNA ELEVATION AND AZIMUTH WITH RF ENGINEERING PRIOR TO INSTALLATION.
 - ALL STRUCTURAL ELEMENTS SHALL BE HOT DIPPED GALVANIZED STEEL.
 - THE CONSTRUCTION CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ALL CONSTRUCTION MEANS AND METHODS. THE CONSTRUCTION CONTRACTOR IS ALSO RESPONSIBLE FOR ALL JOB SITE SAFETY.
 - CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, ANGLES AND EXISTING CONDITIONS AT THE SITE PRIOR TO FABRICATION AND/OR INSTALLATION OF ANY WORK IN THE CONTRACT AREA AND SUBMIT TO THE ENGINEER ANY DISCREPANCIES FROM THE DRAWINGS.
 - THE CONTRACTOR IS TO REVIEW ALL DRAWINGS AND SPECIFICATIONS IN THE CONTRACT DOCUMENT SET. THE CONTRACTOR SHALL COORDINATE ALL WORK SHOWN IN THE SET OF DRAWINGS. THE CONTRACTOR SHALL PROVIDE A COMPLETE SET OF DRAWINGS TO ALL SUBCONTRACTORS AND RELATED PARTIES. THE SUBCONTRACTOR SHALL EXAMINE ALL THE DRAWINGS AND SPECIFICATIONS FOR THE INFORMATION THAT EFFECTS THEIR WORK.
 - THE CONTRACTOR SHALL MAINTAIN A CURRENT SET OF DRAWINGS AND SPECIFICATIONS ON THE SITE AT ALL TIMES AND INSURE THE DISTRIBUTION OF NEW DRAWINGS TO SUBCONTRACTORS AND OTHER RELEVANT PARTIES AS SOON AS THEY ARE MADE AVAILABLE. OLD DRAWINGS SHALL BE MARKED VOID AND REMOVED FROM THE CONTRACT AREA CONTRACTOR FURNISH 3 SETS OF REDLINE "AS-BUILT" DRAWINGS TO SPRINT UPON COMPLETION OF THE WORK.
 - DETAILS ARE INTENDED TO SHOW END RESULT OF DESIGN. MINOR MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL INCLUDED AS PART OF THE WORK.
 - ALL MATERIAL PROVIDED BY IS TO BE REVIEWED BY THE CONTRACTOR AND ALL APPLICABLE SUB-CONTRACTOR PRIOR TO INSTALLATION. ANY DEFICIENCIES TO PROVIDE MATERIALS SHALL BE BROUGHT TO THE CONSTRUCTION MANAGERS ATTENTION IMMEDIATELY.
 - THE MATERIALS INSTALLED SHALL MEET REQUIREMENTS OF CONTRACTORS DOCUMENTS. NO SUBSTITUTIONS ARE ALLOWED.
 - THE CONTRACTOR SHALL COORDINATE ALL CIVIL, STRUCTURAL AND ELECTRICAL DRAWINGS FOR THE LOCATIONS OF ALL OPENINGS, RECESSES, BUILT-IN WORK, ETC..
 - THE CONTRACTOR SHALL RECEIVE CLARIFICATION IN WRITING AND SHALL RECEIVE IN WRITING AUTHORIZATION TO PROCEED BEFORE STARTING WORK ON ANY ITEMS NOT CLEARLY DEFINED OR IDENTIFIED BY THE CONTACT DOCUMENTS.
 - THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER OF ALL PRODUCTS OR ITEMS NOTED AS "EXISTING" WHICH ARE NOT FOUND TO BE IN THE FIELD.
 - ERECTION SHALL BE DONE IN A WORKMANLIKE MANNER BY COMPETENT EXPERIENCED WORKMEN IN ACCORDANCE WITH APPLICABLE CODES AND THE BEST-ACCEPTED PRACTICE. ALL MEMBERS SHALL BE LAND PLUMB AND TRUE AS INDICATED ON THE DRAWINGS.
 - THE CONTRACTOR SHALL COORDINATE HIS WORK AND SCHEDULE HIS ACTIVITIES AND WORKING HOURS IN ACCORDANCE WITH THE REQUIREMENTS OF THE PROPERTY OWNER AND/OR PROPERTY MANAGEMENT COMPANY.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING HIS WORK WITH THE WORK OF OTHERS AS IT MAY RELATE TO RADIO EQUIPMENT, ANTENNAS AND ANY OTHER PORTIONS OF THE WORK.
 - THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURE'S RECOMMENDATIONS UNLESS SPECIFICALLY INDICATED OR WHERE LOCAL CODES OR REGULATIONS MAY TAKE PRECEDENCE.
 - THE CONTRACTOR SHALL REPAIR ALL EXISTING SURFACES DAMAGED DURING CONSTRUCTION SUCH THAT THEY MATCH AND BLEND WITH ADJACENT SURFACES.
 - THE CONTRACTOR SHALL KEEP CONTRACT AREA CLEAN, HAZARD FREE AND DISPOSE OF ALL DEBRIS AND RUBBISH. LEAVE PREMISES IN CLEAN CONDITION AND FREE FROM PAINT SPOTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL ITEMS UNTIL COMPLETION OF CONSTRUCTION.
 - BEFORE FINAL ACCEPTANCE OF THE WORK, THE CONTRACTOR SHALL REMOVE ALL EQUIPMENT, TEMPORARY WORKS, UNUSED AND USELESS MATERIALS, RUBBISH AND TEMPORARY STRUCTURES.
 - DESIGN REQUIREMENTS PER INTERNATIONAL BUILDING CODE 2015 AND THE EIA/TIA-222-G STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND ANTENNA SUPPORTING STRUCTURES.

COM-EX Consultants
115 Route 46
Suite E39
Mountain Lakes, NJ 07046
PHONE: 862.209.4300
FAX: 862.209.4301

Sprint

Cherundolo Consulting

SCHEDULE OF REVISIONS

REV NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MIMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY: AM
CHECKED BY: NDB
SCALE: AS NOTED
JOB NO: 17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE OFFICIAL SEAL & SIGNATURE OF A PROFESSIONAL ENGINEER

Nicholas D. Barile

NICHOLAS D. BARILE
PROFESSIONAL ENGINEER, CT LIC. No. 28643



CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:


ROOF PLAN & GENERAL NOTES

DRAWING SHEET: 2 OF 8


C-1



1
C-2 EXISTING SECTOR 1, 2, & 3 ANTENNA PLAN
SCALE: 3/4"=1'



LOADING SHOWN ON THIS SET OF DRAWINGS IS BASED ON THE STRUCTURAL ANALYSIS PERFORMED BY DESTEK ENGINEERING, DATED 05/08/18 FOR THE SPRINT SITE CT52XC007. CONTRACTOR TO NOTIFY COM-EX AND SPRINT IN THE EVENT SITE CONDITIONS DIFFER FROM WHAT IS REPRESENTED IN THE STRUCTURAL ANALYSIS. NO SUBSTITUTIONS ARE PERMITTED WITHOUT ADDITIONAL ANALYSIS.



1A
C-2 FINAL SECTOR 1, 2, & 3 ANTENNA PLAN
SCALE: 3/4"=1'



SCHEDULE OF REVISIONS

REV NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MIMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY: AM
CHECKED BY: NDB
SCALE: AS NOTED
JOB NO: 17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE SIGNED SEAL & SIGNATURE OF A PROFESSIONAL ENGINEER

NICHOLAS D. BARILE
PROFESSIONAL ENGINEER, CT LIC. No. 28643

CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:
EXISTING & FINAL ANTENNA PLANS

DRAWING SHEET: 3 OF 8

C-2



SCHEDULE OF REVISIONS

REV NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MIMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY:	AM
CHECKED BY:	NDB
SCALE:	AS NOTED
JOB NO:	17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE SIGNED SEAL & SIGNATURE OF A PROFESSIONAL ENGINEER

NICHOLAS D. BARILE
PROFESSIONAL ENGINEER, CT LIC. No. 28643

CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:
ELEVATION, B.O.M., & FINAL EQUIPMENT PLAN

DRAWING SHEET: 4 OF 8

C-3

BILL OF MATERIALS

	DESCRIPTION	QUANTITY EACH	DIMENSIONS (HxWxD)	WEIGHT (LBS) EACH	MANUFACTURER: PART/ MODEL#	
ANTENNAS	800/1900MHz PANEL ANTENNA - SECTOR 1	1	72"x19.6"x7.8"	77.4 LBS W/OUT MOUNTING HARDWARE	COMMSCOPE: NNW-65B-R4	
	MIMO PANEL ANTENNA - SECTOR 1	1	25.6"x19.7"x9.6"	103.6 LBS W/OUT MOUNTING HARDWARE	NOKIA: 2.5G MAA-AAHC(64T64R)	
	800 MHz RRH	2	15.7"x12.9"x9.8"	53 LBS W/OUT MOUNTING HARDWARE	ALCATEL LUCENT	
	1900 MHz RRH	1	25.2"x11.8"x11.5"	N/A	ALCATEL LUCENT	
	800/1900MHz PANEL ANTENNA - SECTOR 2	1	72"x19.6"x7.8"	77.4 LBS W/OUT MOUNTING HARDWARE	COMMSCOPE: NNW-65B-R4	
	MIMO PANEL ANTENNA - SECTOR 2	1	25.6"x19.7"x9.6"	103.6 LBS W/OUT MOUNTING HARDWARE	NOKIA: 2.5G MAA-AAHC(64T64R)	
	800 MHz RRH	2	15.7"x12.9"x9.8"	53 LBS W/OUT MOUNTING HARDWARE	ALCATEL LUCENT	
	1900 MHz RRH	1	25.2"x11.8"x11.5"	N/A	ALCATEL LUCENT	
	800/1900MHz PANEL ANTENNA - SECTOR 3	1	72"x19.6"x7.8"	77.4 LBS W/OUT MOUNTING HARDWARE	COMMSCOPE: NNW-65B-R4	
	MIMO PANEL ANTENNA - SECTOR 3	1	25.6"x19.7"x9.6"	103.6 LBS W/OUT MOUNTING HARDWARE	NOKIA: 2.5G MAA-AAHC(64T64R)	
	800 MHz RRH	2	15.7"x12.9"x9.8"	53 LBS W/OUT MOUNTING HARDWARE	ALCATEL LUCENT	
	1900 MHz RRH	1	25.2"x11.8"x11.5"	N/A	ALCATEL LUCENT	
	DESCRIPTION	QUANTITY EACH	DIMENSIONS (LENGTH)	WEIGHT (LBS/FOOT)	MANUFACTURER: SIZE/PART/MODEL#	
EQUIP.	SECTOR 1 MIMO CABLE	1	±135'	2.39 LBS	RFS: 1-5/8" / HB158-21U6M48-200F	
	SECTOR 1 COAX CABLE JUMPERS	11	10'	N/A	LDF4-50 (OR EQUIVALENT)	
	SECTOR 1 R.E.T. CABLES	4	(3) 10' / (1) 2'	N/A	TBD	
	SECTOR 2 MIMO CABLE	1	±135'	2.39 LBS	RFS: 1-5/8" / HB158-21U6M48-200F	
	SECTOR 2 COAX CABLE JUMPERS	11	10'	N/A	LDF4-50 (OR EQUIVALENT)	
	SECTOR 2 R.E.T. CABLES	4	(3) 10' / (1) 2'	N/A	TBD	
	SECTOR 3 MIMO CABLE	1	±135'	2.39 LBS	RFS: 1-5/8" / HB158-21U6M48-200F	
	SECTOR 3 COAX CABLE JUMPERS	11	10'	N/A	LDF4-50 (OR EQUIVALENT)	
	SECTOR 3 R.E.T. CABLES	4	(3) 10' / (1) 2'	N/A	TBD	
		DESCRIPTION	QUANTITY EACH	DIMENSIONS (LENGTH)	WEIGHT	MANUFACTURER: PART/MODEL#
	EQUIP.	BTS CABINET	1	73.5"x38"x30"	505 LBS (1381 LBS FULLY LOADED)	ELTEK
		CABLING KIT	1	71.4"x12.1"x28.1"	180 LBS	ELTEK
BATTERY CABINET		1	73.5"x34.7"x16.5"	330 LBS (1386 LBS FULLY LOADED)	BCAB ELTEK	
GPS UNIT		1	5"x3.2"	.5 LBS W/OUT MOUNTING HARDWARE	PCTEL: GPS-TMG-HR-26N	

☉ OF EXISTING ANTENNAS (BY OTHERS)
ELEV.=±256'-0" AGL

☉ OF EXISTING T-MOBILE ANTENNAS
ELEV.=±180'-0" AGL

☉ OF PROPOSED ANTENNAS
ELEV.=±118'-0" AGL

☉ OF EXISTING VERIZON ANTENNAS
ELEV.=±110'-0" AGL

LOADING SHOWN ON THIS SET OF DRAWINGS IS BASED ON THE STRUCTURAL ANALYSIS PERFORMED BY DESTEK ENGINEERING, DATED 05/08/18 FOR THE SPRINT SITE CT52XC007. CONTRACTOR TO NOTIFY COM-EX AND SPRINT IN THE EVENT SITE CONDITIONS DIFFER FROM WHAT IS REPRESENTED IN THE STRUCTURAL ANALYSIS. NO SUBSTITUTIONS ARE PERMITTED WITHOUT ADDITIONAL ANALYSIS.

EXISTING SECTOR 3 ANTENNA BEYOND

1 C-2 1A C-2
EXISTING & FINAL SECTOR 1, 2, & 3 ANTENNA PLANS

INSTALL NEW CABLES IN EXISTING CABLE ROUTE

1 C-3
FINAL EQUIPMENT PLAN

GRADE
ELEV.=±0' AGL


1 C-3
ELEVATION
SCALE: 1/16"=1'
(24"x36" SHEET SIZE)


5 C-4
PROPOSED EQUIPMENT CABINET

EXISTING CW EQUIPMENT CABINET TO BE REMOVED


EXISTING TELCO BACKBOARD

2 C-3
FINAL EQUIPMENT PLAN (IN BUILDING)
SCALE: 3/16"=1'







1
C-4
800/1900MHz ANTENNA
COMMSCOPE: NNVV-65B-R4
SCALE: 1/2"=1'




2
C-4
MIMO ANTENNA/RRH
NOKIA: 2.5G MAA-AAHC(64T64R)
SCALE: N.T.S.



3
C-4
800MHz RRH DETAIL
SCALE: N.T.S.



4
C-4
1900MHz RRH DETAIL
SCALE: N.T.S.



5
C-4
ELTEK EQUIPMENT DETAIL
SCALE: N.T.S.

ELTEK ECAB STATS:
MECHANICAL SPECIFICATIONS
 HEIGHT: 73.5 IN. (1866 mm)
 WIDTH: 38 IN. (965 mm)
 DEPTH: 30 IN. (762 mm)
 WEIGHT: 1381 LBS.
CABLING KIT STATS:
MECHANICAL SPECIFICATIONS
 HEIGHT: 71.4 IN. (1813 mm)
 WIDTH: 12.1 IN. (306 mm)
 DEPTH: 28.1 IN. (713 mm)
 WEIGHT: 180 LBS.
ELTEK BCAB STATS:
MECHANICAL SPECIFICATIONS
 HEIGHT: 73.5 IN. (1866 mm)
 WIDTH: 16.5 IN. (419 mm)
 DEPTH: 34.7 IN. (881 mm)
 WEIGHT: 1386 LBS.

GPS-TMG-HR-26N, High Rejection 26dB With Enhanced Narrow Band Filtering

Antenna Element Electrical Specifications

Frequency Band	Antenna Gain	Nominal Impedance	VSWR	Polarization	Connector
1575.42 +/- 10 MHz	3.5 dBi	50 ohms	≤1.5:1	Right hand circular	N, female (one bottom fed)

Mechanical Specifications

Antenna Dimensions	Shipping Dimensions	Antenna Weight	Shipping Weight	Radome Color
5.0" H x 3.2" D (126 H x 81 mm)	7.5" L x 4.4" W x 3.8" D (190 L x 112 x 96 mm)	0.6 lbs (0.3 kg)	1.9 lbs (0.9 kg)	White


Environmental Specifications

Temperature Range	Humidity
-40° C to +85° C	95%

Mounting

All mounting options fit pipes of 1"-1.45" (25 mm-37 mm) maximum diameter.


Model	Options
GPS-TMG-HR-26N	Antenna Only. Does not include mounting hardware.
GPS-TMG-HR-26NCM	Includes red powder coated collar mount (GPS-TMG-MNT-R)



6
C-4
GPS UNIT DETAIL
SCALE: N.T.S.

Prepared By Mark Elliott	Revision Date March 13, 2018	Revision Number R1	
Approved By RAN Hardware & Antenna Teams	Approval Date Final-Macro Generated		

ALU 21-MIMO NNVV-65B-R4 wo Filters



7
C-4
MIMO SCHEMATIC
SCALE: N.T.S.



SCHEDULE OF REVISIONS

REV NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MIMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY: AM
CHECKED BY: NDB
SCALE: AS NOTED
JOB NO: 17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE PROPER SEAL & SIGNATURE OF A REGISTERED PROFESSIONAL ENGINEER

NICHOLAS D. BARILE
 PROFESSIONAL ENGINEER, CT LIC. No. 28643

CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:
CONSTRUCTION DETAILS

DRAWING SHEET: 5 OF 8

C-4



SCHEDULE OF REVISIONS

REV. NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MIMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY:	AM
CHECKED BY:	NDB
SCALE:	AS NOTED
JOB NO:	17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE SEAL & SIGNATURE OF A PROFESSIONAL ENGINEER

NICHOLAS D. BARILE
PROFESSIONAL ENGINEER, CT LIC. No. 28643

CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:

CABLE COLOR CODING





DRAWING SHEET: 6 OF 8

C-5

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Blue	No Tape	No Tape
1	3	Brown	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Blue	Blue	No Tape
2	3	Brown	Brown	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Blue	Blue	Blue
3	3	Brown	Brown	Brown
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL


NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL




1
C-5 COLOR CODING CHARTS
SCALE: NTS

CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.




1 TYPICAL POWER & GROUNDING ONE-LINE DIAGRAM
E-1 SCALE: N.T.S.




- LEGEND**
1. COPPER GROUND BAR, 7/16" X 4" X 20", NEWTON INSTRUMENT CO. CAT. NO. B-6142. HOLE CENTERS TO MATCH NEMA DOUBLE LUG CONFIGURATION.
 2. INSULATORS, NEWTON INSTRUMENT CAT. NO. 3061-4.
 3. 5/8" LOCKWASHERS, NEWTON INSTRUMENT CO. CAT. NO. 3015-8.
 4. WALL MOUNTING BRACKET, NEWTON INSTRUMENT CO. CAT. NO. A-6056.
 5. 5/8-11 X 1" H.C.S. BOLTS, NEWTON INSTRUMENT CO. CAT. NO. 3012-1

GROUND BAR SCHEDULE				
TYPE	QTY.	MANUFACTURER	CAT. NO.	REMARKS
MGB	2	HARGER	GB14420TMGB	OR EQUAL
CGB	3	HARGER	GB14412TMGB	OR EQUAL



- * - GROUND BARS AT THE BOTTOM OF TOWERS/MONOPOLES SHALL ONLY USE EXOTHERMIC WELDS.
- ATTACH "DO NOT DISCONNECT" LABELS TO GROUND BARS. CAN USE BRASS TAG "DO NOT DISCONNECT" AT EACH HYBRIFLEX GROUND POINT OR BACK-A-LITE PLATE LABEL ON GROUND BAR.
- CONNECT SEQUENCE- BOLT/WASHER/NO-OX/GROUND BAR/NO-OX/WASHER/LOCK-WASHER/NUT. THIS IS REPEATED FOR EACH LUG CONNECTION POINT.

3 TYPICAL GROUND BAR CONNECTION PLAN
E-1 SCALE: NTS



- NOTE:**
1. "DOUBLING UP" OR "STACKING" OF CONNECTIONS IS NOT PERMITTED.
 2. OXIDE INHIBITING COMPOUND TO BE USED AT ALL LOCATIONS.

4 TYPICAL GROUND BAR CONNECTION DETAIL
E-1 SCALE: NTS

- ELECTRICAL AND GROUNDING NOTES**
1. ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
 2. ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
 3. ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
 4. BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
 5. ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THHN INSULATION.
 6. RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
 7. WHERE CONDUIT BETWEEN BTS AND PROJECT OWNER CELL SITE PPC AND BETWEEN BTS AND PROJECT OWNER CELL SITE TELCO SERVICE CABINET ARE UNDERGROUND USE PVC, SCHEDULE 40 CONDUIT. ABOVE THE GROUND PORTION OF THESE CONDUITS SHALL BE PVC CONDUIT.
 8. ALL EQUIPMENT LOCATED OUTSIDE SHALL HAVE NEMA 3R ENCLOSURE.
 9. GROUNDING SHALL COMPLY WITH NEC ART. 250.
 10. GROUND HYBRIFLEX CABLE SHIELDS AT 3 LOCATIONS USING MANUFACTURER'S HYBRIFLEX CABLE GROUNDING KITS SUPPLIED BY PROJECT OWNER.
 11. USE #6 COPPER STRANDED WIRE WITH GREEN COLOR INSULATION FOR ABOVE GRADE GROUNDING (UNLESS OTHERWISE SPECIFIED) AND #2 SOLID TINNED BARE COPPER WIRE FOR BELOW GRADE GROUNDING AS INDICATED ON THE DRAWING.
 12. ALL GROUND CONNECTIONS TO BE BURNDY HYGROUND COMPRESSION TYPE CONNECTORS OR CADWELD EXOTHERMIC WELD. DO NOT ALLOW BARE COPPER WIRE TO BE IN CONTACT WITH GALVANIZED STEEL.
 13. ROUTE GROUNDING CONDUCTORS ALONG THE SHORTEST AND STRAIGHTEST PATH POSSIBLE, EXCEPT AS OTHERWISE INDICATED. GROUNDING LEADS SHOULD NEVER BE BENT AT RIGHT ANGLE. ALWAYS MAKE AT LEAST 12" RADIUS BENDS. #6 WIRE CAN BE BENT AT 6" RADIUS WHEN NECESSARY. BOND ANY METAL OBJECTS WITHIN 6 FEET OF PROJECT OWNER EQUIPMENT OR CABINET TO MASTER GROUND BAR OR GROUNDING RING.
 14. CONNECTIONS TO GROUND BARS SHALL BE MADE WITH TWO HOLE COMPRESSION TYPE COPPER LUGS. APPLY OXIDE INHIBITING COMPOUND TO ALL LOCATIONS.
 15. APPLY OXIDE INHIBITING COMPOUND TO ALL COMPRESSION TYPE GROUND CONNECTIONS.
 16. BOND ANTENNA MOUNTING BRACKETS, HYBRIFLEX CABLE GROUND KITS, AND RRHS TO EGB PLACED NEAR THE ANTENNA LOCATION.
 17. BOND ANTENNA EGB'S AND MGB TO GROUND RING.
 18. CONTRACTOR SHALL TEST COMPLETED GROUND SYSTEM AND RECORD RESULT FOR PROJECT CLOSE-OUT DOCUMENTATION. 5 OHMS MINIMUM RESISTANCE REQUIRED.
 19. CONTRACTOR SHALL CONDUCT ANTENNA, HYBRIFLEX CABLES, AND RRH RETURN-LOSS AND DISTANCE-TO-FAULT MEASUREMENTS (SWEEP TESTS) AND RECORD RESULTS FOR PROJECT CLOSE OUT.
 20. CONTRACTOR (CERTIFIED ELECTRICIAN) SHALL CHECK CAPACITY OF EXISTING SERVICE & PANEL ON SITE TO DETERMINE IF CAPACITY EXISTS TO ACCOMMODATE THE ADDED LOAD OF THIS PROJECT. ADVISE ENGINEER OF ANY DISCREPANCY.

COM-EX Consultants
115 Route 46
Suite E39
Mountain Lakes, NJ 07046
PHONE: 862.209.4300
FAX: 862.209.4301

Sprint

Cherundolo Consulting

SCHEDULE OF REVISIONS

REV NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MIMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY: AM
CHECKED BY: NDB
SCALE: AS NOTED
JOB NO.: 17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE ORIGINAL SEAL & SIGNATURE OF THE REGISTERED ENGINEER

Nicholas D. Barile
NICHOLAS D. BARILE
PROFESSIONAL ENGINEER, CT LIC. No. 28643


CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:

GROUNDING DETAILS

DRAWING SHEET: 7 OF 8


E-1



1 DC ONE-LINE DIAGRAM
E-2 SCALE: NTS

A/C PANEL SCHEDULE			
VOLTAGE:	240V/120	PANEL STATUS:	EXISTING
MAIN BREAKER:	200 AMP	MODEL NUMBER:	TBD
MOUNT:	ROOFTOP	PHASE:	1
ENCLOSURE:	NEMA 3R	BUSS RATING:	200 AMP
		NEUTRAL BAR:	YES
		N TO GROUND BOND:	YES
		INTERNAL TVSS:	YES
		WIRE:	3
		GROUND BAR:	YES

2 AC PANEL SCHEDULE
E-2 SCALE: NTS



CIRCUIT SCHEDULE			
NO.	FROM	TO	CONFIGURATION
1	UTILITY SOURCE	METER/DISCONNECT	EXISTING
2	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
3	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
4	TRANSFER & LOAD CENTER	EX. MMBS CABINET	(3) #2 AWG, (1) #8 GND IN 1-1/2" CONDUIT
5	TRANSFER & LOAD CENTER	EX. BBU CABINET	(2) #12 AWG, (1) #12 GND IN 3/4" CONDUIT

3 ELECTRICAL ONE-LINE DIAGRAM
E-2 SCALE: NTS

SCHEDULE OF REVISIONS

REV NO.	DATE	DESCRIPTION OF CHANGES
7		
6		
5	05/09/18	ISSUED AS FINAL
4	05/07/18	REVISED PER CLIENT COMMENTS
3	04/09/18	REVISED PER MIMO CONFIG.
2	12/21/17	ISSUED FOR CONSTRUCTION
1	09/27/17	REVISED PER RFDS
0	07/12/17	INITIAL SUBMISSION

DRAWN BY: AM
CHECKED BY: NDB
SCALE: AS NOTED
JOB NO: 17051-CHE

Documents prepared by Com-Ex Consultants, including this document, are to be used only for the specific project and specific use for which they were intended. Any extension of use to any other projects, by owner or by any other party, without the expressed written consent of Com-Ex Consultants, is done unlawfully and at the users own risk. If used in a way other than that specifically intended, user will hold Com-Ex Consultants, harmless from all claims and losses.

INFORMATION ON THIS SET OF DRAWINGS IS NOT FOR OFFICIAL USE UNLESS ACCOMPANIED BY THE ORIGINAL SEAL & SIGNATURE OF A PROFESSIONAL ENGINEER

NICHOLAS D. BARILE
PROFESSIONAL ENGINEER, CT LIC. No. 28643

CT52XC007
623 PINE STREET
BRIDGEPORT, CT 06605

DRAWING TITLE:
DC POWER
DETAILS & PANEL
SCHEDULES

DRAWING SHEET: 8 OF 8

E-2

**STRUCTURAL ANALYSIS REPORT – REVISION. 2
SELF-SUPPORT TOWER**



Prepared For:
**Com-Ex Consultants, LLC
115 Route 46 – Suite E39
Mountain Lakes, NJ 07046**



Structure Rating:

Tower:	Pass
Foundation:	Pass

Sincerely,
Destek Engineering, LLC

08-20-2018



Ahmet Colakoglu, PE
Connecticut Professional Engineer
License No: 27057

**Sprint Site ID: CT52XC007
623 Pine Street
Bridgeport, CT 06605
Fairfield County**

CONTENTS

1.0 - SUBJECT AND REFERENCES

1.1 - STRUCTURE

2.0 - EXISTING AND PROPOSED APPURTENANCES

3.0 - CODES AND LOADING

4.0 - STANDARD CONDITIONS FOR ENGINEERING SERVICES ON EXISTING
STRUCTURES

5.0 – ANALYSIS AND ASSUMPTIONS

6.0 – CONCLUSION AND RESULTS

APPENDICES

A – SOFTWARE OUTPUT

1.0 SUBJECT AND REFERENCES

The purpose of this analysis is to evaluate the structural capacity of the existing 248' self-support tower located at 623 Pine Street, Bridgeport, CT 06605 for the additions and alterations proposed by Sprint.

The structural analysis is based on the following documentation provided to Destek Engineering, LLC (Destek):

- Construction Drawings prepared by KM Consulting Engineers, dated 05/25/2018.
- Structural Analysis Report by Destek, dated 05/08/2018.
- Tower Structural Analysis Report by KM Consulting Engineers, dated 06/20/2017.
- Tower Structural Analysis Report by URS Corporation, dated 04/12/2010.
- Construction Drawings prepared by Com-Ex, dated 04/09/2018.
- Site Photographs provided by Com-Ex, dated 05/18/2017.

1.1 STRUCTURE AND EXISTING EQUIPMENT

The structure is a 3-sided, 248' tall self-support tower. It is formed by (12) 20' sections and (1) 8' section. The first 20 feet section is K-braced with pipe legs and pipe bracing. The rest of the tower has pipe legs which is X-braced with angle members. The tower is 27.8333' wide at the base with a constant taper down to 6.9' wide at 200' above grade. Please refer to the software output in Appendix A, for tower geometry, member sizes and other details.

2.0 EXISTING AND PROPOSED APPURTENANCES

Existing Configuration of Sprint Appurtenances:

Rad Center (Feet-AGL)	Antenna	Feedlines	Mount
118.0	(3) Panel Antennas (2) VHLP1-23-2WH (1) VHLP2.5-11-4WH	(6) 7/8" (3) 1/2"	(3) Pipe Mounts

Proposed and Final Configuration of Sprint Appurtenances:

Rad Center (Feet-AGL)	Antenna	Feedlines	Mount
118.0	(3) Commscope NNVV-65B-R4 (3) Nokia 2.5G MAA-AAHC(64T64R) (6) 800 MHz RRH (3) 1900 MHz RRH (2) VHLP1-23-2WH (1) VHLP2.5-11-4WH	(3) 1/2" (1) Hybriflex Cable	(3) New VFA-RRU Sector Mounts

Existing Appurtenances by Others:

Rad Center (Feet-AGL)	Antenna	Feedlines	Mount
256.0	(1) Yagi Antenna (4) Omni Antennas	(7) 1-1/4" (1) 1/2"	(1) Platform Mount
248.0	(1) Omni Antenna	(2) 7/8"	(1) Standoff Mount
180.0	(3) Ericsson AIR21 B2A/B4P Antennas (3) Ericsson AIR 3246 B66 Antennas (3) RFS APXVAARR24 43-U- NA20 (3) RRUS 32 B2 (3) Radio 4449 B12/B71 (3) Twin Style 1BX TMA	(18) 1-5/8" (1) 6x12 Hybrid	(3) Sector Mounts
110.0	(6) APL-866513-42T6 (3) 2x60 AWS RRH (2) Distribution Boxes (3) 2x60 700 RRH B13 (1) GPS (6) HBXX-6516DS-A2M (3) 2x60 PCS RRH B25 (3) 800 10734V01	(20) 1-5/8"	(3) Sector Mounts
100.0	(2) TV 65 Antennas	(1) 1-1/4"	(1) Standoff Mount

3.0 CODES AND LOADING

The tower was analyzed per *TIA/EIA-222-G* as referenced by the *2016 Connecticut State Building Code* with all of the adopted Addendums and Supplements. The following wind loading was used:

- Ultimate design wind speed 125 mph (nominal design wind speed 97 mph) without ice (V)
- Basic wind speed 50 mph with 0.75" escalating ice (V_i)
- Exposure Category D
- Topographic Category 1
- Risk Category II ($I_w = 1.0$)

The following load combinations were used with wind blowing at 0°, 30°, 45°, 60°, and 90° measured from a line normal to the face of the tower.

- $1.2 D + 1.6 W_o$
- $0.9 D + 1.6 W_o$
- $1.2 D + 1.0 D_i + 1.0 W_i + 1.0 T_i$

D: Dead load of structures and appurtenances

D_i : Weight of ice due to factored ice thickness (based upon t_i)

T_i : Load effects due to temperature

W_o : Wind load without ice (based upon V)

W_i : Wind load with ice (based upon V_i)

4.0 STANDARD CONDITIONS FOR ENGINEERING SERVICES ON EXISTING STRUCTURES

The analysis is based on the information provided and is assumed to be current and correct. Unless otherwise noted, the structure is assumed to be in good condition, free of defects and can achieve theoretical strength.

It is assumed that the structure has been maintained and shall be maintained during its service. The superstructure and the foundation system are assumed to be designed with proper engineering practice and fabricated, constructed and erected in accordance with the design documents. Destek will accept no liability which may arise due to any existing deficiency in design, material, fabrication, erection, construction, etc. or lack of maintenance.

The analysis does not include a qualification of the mounts attached on the structure or their connections. The analysis is performed to verify the capacity of the main structural members, which is the current practice in the tower industry.

The analysis results presented in this report are only applicable for the previously mentioned existing and proposed appurtenances. Any deviation of the appurtenances and placement, etc., will require Destek to generate an additional structural analysis.

5.0 ANALYSIS AND ASSUMPTIONS

The tower was analyzed by utilizing tnxTower, a 3-Dimensional finite element software, a product of Tower Numerics, Inc. Software output for this analysis is provided in Appendix-A of this report.

The connections of the tower are assumed to have as much capacity as the supporting member.

6.0 CONCLUSION AND RESULTS

Based on an analysis per *TIA/EIA-222-G*, the existing tower has **adequate** structural capacity for the proposed modifications by Sprint. For the aforementioned load combinations and as a maximum, the tower diagonals between 0' & 20' are stressed to **92.1%** of their structural capacities. The tower legs are stressed to 62.3% of their structural capacities.

Based on a reaction comparison, the existing tower foundation has **adequate** structural capacity to support the proposed installation by Sprint.

Reaction Comparison:

Maximums	Destek Analysis	Original Design Reactions*	Usage (%)
Compression (kip)	456.0	524.8*1.35=708.5	64.4
Uplift (kip)	378.0	460.5*1.35=621.7	60.8
Total Shear (kip)	90.0	93.1*1.35=125.7	71.6
Moment (kips-ft)	10296.0	11758.6*1.35=15874.1	64.9


*Design reactions multiplied with 1.35 as shown, in order to compare ASD reactions with LRFD reactions.

Therefore, the proposed additions and alterations by Sprint **can** be implemented as intended with the conditions outlined in this report.

Should you have any questions about this report, please contact us at (770) 693-0835.

APPENDIX A
SOFTWARE OUTPUT

Section	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13								
Legs		ROHN 3 EH	ROHN 4 EH	ROHN 5 EH		ROHN 6 EH		ROHN 8 EHS	ROHN 8 EH		P10x.5		ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 1.5 STD	ROHN 3 STD	27.8333	6.804	
Leg Grade																				6.9	0.5
Diagonals																				12 @ 4	1.4
Diagonal Grade																					
Top Girts																				4 @ 5	2.1
Horizontals																					
Red. Horizontals																					
Red. Diagonals																					
Red. Hips																					
Inner Bracing																					
Face Width (ft)																					
# Panels @ (ft)																					
Weight (K)																					



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
10' Yagi w/ (5) 6' Elements	256	NNVV-65B-R4 w/ Mount Pipe	118
Beacon	256	AAHC w/ Mount Pipe	118
2" Dia 10' Omni	256	AAHC w/ Mount Pipe	118
2" Dia 10' Omni	256	AAHC w/ Mount Pipe	118
2" Dia 10' Omni	256 - 239	(2) 800 MHz RRH	118
2" Dia 10' Omni	256	(2) 800 MHz RRH	118
Platform Mount [LP 102-1]	256	(2) 800 MHz RRH	118
2" Dia 10' Omni	248 - 238	RRH1900MHz	118
Side Arm Mount [SO 309-1]	248 - 238	RRH1900MHz	118
AIR 21 B2A/B4P w/ Mount Pipe	180	RRH1900MHz	118
AIR 21 B2A/B4P w/ Mount Pipe	180	Sector Mount [SM 703-3]	118
AIR 21 B2A/B4P w/ Mount Pipe	180	B25 RRH2x60 PCS	110
APXVAARR24_43-U-NA20 w/ Mount Pipe	180	800 10736V01	110
APXVAARR24_43-U-NA20 w/ Mount Pipe	180	800 10736V01	110
APXVAARR24_43-U-NA20 w/ Mount Pipe	180	800 10736V01	110
APXVAARR24_43-U-NA20 w/ Mount Pipe	180	800 10736V01	110
APXVAARR24_43-U-NA20 w/ Mount Pipe	180	CW JUNCTION BOX	110
AIR 3246 B66 w/ Mount Pipe	180	Sector Mount [SM 303-3]	110
AIR 3246 B66 w/ Mount Pipe	180	RRH2x60-AWS	110
AIR 3246 B66 w/ Mount Pipe	180	RRH2x60-AWS	110
AIR 3246 B66 w/ Mount Pipe	180	RRH2x60-AWS	110
Generic Style 1B - Twin AWS	180	RRH2x60-AWS	110
Generic Style 1B - Twin AWS	180	CW JUNCTION BOX	110
Generic Style 1B - Twin AWS	180	RRH2x60-700	110
Generic Style 1B - Twin AWS	180	RRH2x60-700	110
Generic Style 1B - Twin AWS	180	RRH2x60-700	110
RADIO 4449 B12/B71	180	RRH2x60-700	110
RADIO 4449 B12/B71	180	GPS	110
RADIO 4449 B12/B71	180	(2) HBXX-6516DS-A2M	110
RADIO 4449 B12/B71	180	(2) HBXX-6516DS-A2M	110
RRUS 32 B2	180	(2) HBXX-6516DS-A2M	110
RRUS 32 B2	180	(2) HBXX-6516DS-A2M	110
RRUS 32 B2	180	B25 RRH2x60 PCS	110
Sector Mount [SM 404-3]	180	B25 RRH2x60 PCS	110
VHLP1-23	121	(2) APL866513-42T6	110
VHLP1-23	121	(2) APL866513-42T6	110
VHLP2-5-11	121	(2) APL866513-42T6	110
NNVV-65B-R4 w/ Mount Pipe	118	TV 65 Antenna	100
NNVV-65B-R4 w/ Mount Pipe	118	Side Arm Mount [SO 309-1]	100
		TV 65 Antenna	100

SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	ROHN 3 STD	C	L3x3x1/4
B	L1 3/4x1 3/4x3/16		


MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi			

ALL REACTIONS ARE FACTORED

TOWER DESIGN NOTES

- Tower designed for Exposure D to the TIA-222-G Standard.
- Tower designed for a 97 mph basic wind in accordance with the TIA-222-G Standard.
- Tower is also designed for a 50 mph basic wind with 0.75 in ice. Ice is considered to increase $SHEAR_{AD}$ in thickness with height.
- Deflections are based upon a 60 mph wind.
- Tower Structure Class II.
- Topographic Category 1 with Crest Height of 0.00 ft
- TOWER RATING: 92.1%



Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:		Job: CT52XC007	
		Project: 1729061	Client: ComEx Consultants
Date: 08/20/18		Drawn by: Ahmet Colakoglu	App'd:
Code: TIA-222-G		Date: 08/20/18	Scale: NTS
Path: <small>\\FILESERVER\Destek\Projects\2017\29 - ComEx\061 - CT52XC007\Rev.2\Tmx\CT52XC007.dwg</small>		Dwg No. E-1	

Feed Line Plan 28'


Round

Flat

App In Face

App Out Face

Section @ 28'



Destek Engineering LLC
 1281 Kennestone Circle, Suite 100
 Marietta, GA 30066
 Phone: 770693-0835
 FAX:

Job: CT52XC007		
Project: 1729061		
Client: ComEx Consultants	Drawn by: Ahmet Colakoglu	App'd:
Code: TIA-222-G	Date: 08/20/18	Scale: NTS
Path: \\FILESERVER\Destek\Projects\2017\29 - ComEx\061 - CT52XC007\Rev.2\Tm\CT52XC007.dwg		Dwg No. E-7

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 1 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 256.00 ft above the ground line.

The base of the tower is set at an elevation of 8.00 ft above the ground line.

The face width of the tower is 6.60 ft at the top and 27.83 ft at the base.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Basic wind speed of 97 mph.

Structure Class II.

Exposure Category D.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 0.7500 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

<ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile √ Include Bolts In Member Capacity Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric 	<ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination √ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder 	<ul style="list-style-type: none"> Use ASCE 10 X-Brace Ly Rules √ Calculate Redundant Bracing Forces Ignore Redundant Members in FEA √ SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feed Line Torque √ Include Angle Block Shear Check Use TIA-222-G Bracing Resist. Exemption Use TIA-222-G Tension Splice Exemption <li style="background-color: #e0e0e0;">Poles Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known
--	--	--

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 2 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu



Triangular Tower

Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	256.00-248.00			6.60	1	8.00
T2	248.00-228.00			6.90	1	20.00
T3	228.00-208.00			6.90	1	20.00
T4	208.00-188.00			6.83	1	20.00
T5	188.00-168.00			8.92	1	20.00
T6	168.00-148.00			10.92	1	20.00
T7	148.00-128.00			12.92	1	20.00
T8	128.00-108.00			14.99	1	20.00
T9	108.00-88.00			17.08	1	20.00
T10	88.00-68.00			19.25	1	20.00
T11	68.00-48.00			21.25	1	20.00
T12	48.00-28.00			23.23	1	20.00
T13	28.00-8.00			25.33	1	20.00

Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	<i>ft</i>	<i>ft</i>				<i>in</i>	<i>in</i>
T1	256.00-248.00	4.00	X Brace	No	No	0.0000	0.0000
T2	248.00-228.00	4.00	X Brace	No	No	0.0000	0.0000

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	3 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	ft	ft				in	in
T3	228.00-208.00	4.00	X Brace	No	No	0.0000	0.0000
T4	208.00-188.00	5.00	X Brace	No	No	0.0000	0.0000
T5	188.00-168.00	6.67	X Brace	No	No	0.0000	0.0000
T6	168.00-148.00	6.67	X Brace	No	No	0.0000	0.0000
T7	148.00-128.00	6.67	X Brace	No	No	0.0000	0.0000
T8	128.00-108.00	10.00	X Brace	No	No	0.0000	0.0000
T9	108.00-88.00	10.00	X Brace	No	No	0.0000	0.0000
T10	88.00-68.00	10.00	X Brace	No	No	0.0000	0.0000
T11	68.00-48.00	10.00	X Brace	No	No	0.0000	0.0000
T12	48.00-28.00	10.00	X Brace	No	No	0.0000	0.0000
T13	28.00-8.00	20.00	K1 Down	No	Yes	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
ft						
T1 256.00-248.00	Pipe	ROHN 3 STD	A572-50 (50 ksi)	Equal Angle	L1 3/4x1 3/4x3/16	A572-50 (50 ksi)
T2 248.00-228.00	Pipe	ROHN 3 EH	A572-50 (50 ksi)	Equal Angle	L2x2x1/4	A572-50 (50 ksi)
T3 228.00-208.00	Pipe	ROHN 4 EH	A572-50 (50 ksi)	Equal Angle	L2x2x1/4	A572-50 (50 ksi)
T4 208.00-188.00	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Equal Angle	L2x2x1/4	A572-50 (50 ksi)
T5 188.00-168.00	Pipe	ROHN 6 EH	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x1/4	A572-50 (50 ksi)
T6 168.00-148.00	Pipe	ROHN 6 EH	A572-50 (50 ksi)	Equal Angle	L3x3x1/4	A572-50 (50 ksi)
T7 148.00-128.00	Pipe	ROHN 6 EH	A572-50 (50 ksi)	Equal Angle	L3x3x1/4	A572-50 (50 ksi)
T8 128.00-108.00	Pipe	ROHN 8 EHS	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T9 108.00-88.00	Pipe	ROHN 8 EH	A572-50 (50 ksi)	Equal Angle	L4x4x5/16	A572-50 (50 ksi)
T10 88.00-68.00	Pipe	P10x.5	A572-50 (50 ksi)	Equal Angle	L5x5x3/8	A572-50 (50 ksi)
T11 68.00-48.00	Pipe	P10x.5	A572-50 (50 ksi)	Equal Angle	L5x5x3/8	A572-50 (50 ksi)
T12 48.00-28.00	Pipe	P10x.5	A572-50 (50 ksi)	Equal Angle	L5x5x3/8	A572-50 (50 ksi)
T13 28.00-8.00	Pipe	P10x.5	A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
ft						
T1 256.00-248.00	Equal Angle	L3x3x1/4	A36 (36 ksi)	Solid Round		A36 (36 ksi)

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 4 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Tower Section Geometry (cont'd)

Tower Elevation	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
ft							
T13 28.00-8.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
ft						
T13 28.00-8.00	Solid Round		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation	Redundant Bracing Grade	Redundant Type	Redundant Size	K Factor
ft				
T13 28.00-8.00	A36 (36 ksi)	Horizontal (1) Diagonal (1) Hip (1) Hip Diagonal (1)	Pipe Pipe Pipe Pipe	ROHN 3 STD ROHN 3 STD ROHN 1.5 STD ROHN 1.5 STD
				1 1 1 1

Tower Section Geometry (cont'd)

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft ²	in					in	in	in
T1 256.00-248.00	0.00	0.0000	A36 (36 ksi)	1.03	1	1.05	36.0000	36.0000	36.0000
T2 248.00-228.00	0.00	0.0000	A36 (36 ksi)	1.03	1	1.05	36.0000	36.0000	36.0000
T3 228.00-208.00	0.00	0.0000	A36 (36 ksi)	1.03	1	1.05	36.0000	36.0000	36.0000
T4 208.00-188.00	0.00	0.0000	A36 (36 ksi)	1.03	1	1.05	36.0000	36.0000	36.0000
T5 188.00-168.00	0.00	0.0000	A36 (36 ksi)	1.03	1	1.05	36.0000	36.0000	36.0000
T6	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 5 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in	Double Angle Stitch Bolt Spacing Redundants in
ft	ft ²	in							
168.00-148.00			(36 ksi)						
T7	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000
148.00-128.00			(36 ksi)						
T8	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000
128.00-108.00			(36 ksi)						
T9	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000
108.00-88.00			(36 ksi)						
T10	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000
88.00-68.00			(36 ksi)						
T11	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000
68.00-48.00			(36 ksi)						
T12	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000
48.00-28.00			(36 ksi)						
T13	0.00	0.0000	A36	1.03	1	1.05	36.0000	36.0000	36.0000
28.00-8.00			(36 ksi)						

Tower Section Geometry (cont'd)

Tower Elevation	Calc K Single Angles	Calc K Solid Rounds	Legs	K Factors ¹							
				X Brace Diags	K Brace Diags	Single Diags	Girts	Horiz.	Sec. Horiz.	Inner Brace	
											X
ft				Y	Y	Y	Y	Y	Y	Y	
T1	Yes	Yes	1	1	1	1	1	1	1	1	1
256.00-248.00				1	1	1	1	1	1	1	1
T2	Yes	Yes	1	1	1	1	1	1	1	1	1
248.00-228.00				1	1	1	1	1	1	1	1
T3	Yes	Yes	1	1	1	1	1	1	1	1	1
228.00-208.00				1	1	1	1	1	1	1	1
T4	Yes	Yes	1	1	1	1	1	1	1	1	1
208.00-188.00				1	1	1	1	1	1	1	1
T5	Yes	Yes	1	1	1	1	1	1	1	1	1
188.00-168.00				1	1	1	1	1	1	1	1
T6	Yes	Yes	1	1	1	1	1	1	1	1	1
168.00-148.00				1	1	1	1	1	1	1	1
T7	Yes	Yes	1	1	1	1	1	1	1	1	1
148.00-128.00				1	1	1	1	1	1	1	1
T8	Yes	Yes	1	1	1	1	1	1	1	1	1
128.00-108.00				1	1	1	1	1	1	1	1
T9	Yes	Yes	1	1	1	1	1	1	1	1	1
108.00-88.00				1	1	1	1	1	1	1	1
T10	Yes	Yes	1	1	1	1	1	1	1	1	1
88.00-68.00				1	1	1	1	1	1	1	1
T11	Yes	Yes	1	1	1	1	1	1	1	1	1
68.00-48.00				1	1	1	1	1	1	1	1
T12	Yes	Yes	1	1	1	1	1	1	1	1	1
48.00-28.00				1	1	1	1	1	1	1	1
T13	Yes	Yes	1	1	1	1	1	1	1	1	1
28.00-8.00				1	1	1	1	1	1	1	1

¹Note: K factors are applied to member segment lengths. K-braces without inner supporting members will have the K factor in the out-of-plane direction applied to the overall length.

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	7 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T9 108.00-88.00	Flange	1.2500	8	0.8750	2	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T10 88.00-68.00	Flange	1.2500	8	0.8750	2	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T11 68.00-48.00	Flange	1.2500	8	0.8750	2	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T12 48.00-28.00	Flange	1.2500	12	0.8750	2	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T13 28.00-8.00	Flange	0.7500	0	0.6250	3	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	# Per Row	# Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
****Face A****												
LDF7-50A (1-5/8 FOAM)	A	No	Ar (CaAa)	110.00 - 18.00	0.0000	-0.4	18	9	1.9800	1.9800		0.82
LDF7-50A (1-5/8 FOAM)	A	No	Ar (CaAa)	110.00 - 18.00	0.0000	-0.5	2	2	1.9800	1.9800		0.82
LDF4-50A (1/2 FOAM)	A	No	Ar (CaAa)	121.00 - 18.00	0.0000	0.4	3	3	0.6300	0.6300		0.15
Face B												
Climbing Ladder	B	No	Ar (CaAa)	256.00 - 18.00	0.0000	0	1	1	0.2500	3.0000		7.90
LDF7-50A (1-5/8 FOAM)	B	No	Ar (CaAa)	180.00 - 18.00	0.0000	0.4	18	18	1.9800	1.9800		0.82
Face C												
LDF6-50A (1-1/4 FOAM)	C	No	Ar (CaAa)	100.00 - 18.00	0.0000	0	1	1	1.5500	1.5500		0.66
LDF5-50A (7/8 FOAM)	C	No	Ar (CaAa)	238.00 - 18.00	0.0000	0.45	2	2	1.0900	1.0900		0.33
LDF4-50A (1/2 FOAM)	C	No	Ar (CaAa)	256.00 - 18.00	0.0000	0.5	1	1	0.6300	0.6300		0.15
LDF6-50A (1-1/4 FOAM)	C	No	Ar (CaAa)	256.00 - 18.00	0.0000	0.4	6	6	1.5500	1.5500		0.66
LDF6-50A (1-1/4 FOAM)	C	No	Ar (CaAa)	256.00 - 18.00	0.0000	0.5	1	1	1.5500	1.5500		0.66

RFS HYBRIFLEX 1 1/4	A	No	Ar (CaAa)	121.00 - 18.00	0.0000	0.425	1	1	1.5400	1.5400		1.30
HCS 6X12 4AWG(1-5/8)	B	No	Ar (CaAa)	188.00 - 18.00	0.0000	0	1	1	1.6600	1.6600		2.40

Feed Line/Linear Appurtenances Section Areas

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	8 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Tower Section	Tower Elevation ft	Face	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight K
T1	256.00-248.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	2.400	0.000	0.06
		C	0.000	0.000	9.184	0.000	0.04
T2	248.00-228.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	6.000	0.000	0.16
		C	0.000	0.000	25.140	0.000	0.10
T3	228.00-208.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	6.000	0.000	0.16
		C	0.000	0.000	27.320	0.000	0.11
T4	208.00-188.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	6.000	0.000	0.16
		C	0.000	0.000	27.320	0.000	0.11
T5	188.00-168.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	52.088	0.000	0.38
		C	0.000	0.000	27.320	0.000	0.11
T6	168.00-148.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	80.600	0.000	0.50
		C	0.000	0.000	27.320	0.000	0.11
T7	148.00-128.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	80.600	0.000	0.50
		C	0.000	0.000	27.320	0.000	0.11
T8	128.00-108.00	A	0.000	0.000	12.379	0.000	0.06
		B	0.000	0.000	80.600	0.000	0.50
		C	0.000	0.000	27.320	0.000	0.11
T9	108.00-88.00	A	0.000	0.000	86.060	0.000	0.36
		B	0.000	0.000	80.600	0.000	0.50
		C	0.000	0.000	29.180	0.000	0.12
T10	88.00-68.00	A	0.000	0.000	86.060	0.000	0.36
		B	0.000	0.000	80.600	0.000	0.50
		C	0.000	0.000	30.420	0.000	0.12
T11	68.00-48.00	A	0.000	0.000	86.060	0.000	0.36
		B	0.000	0.000	80.600	0.000	0.50
		C	0.000	0.000	30.420	0.000	0.12
T12	48.00-28.00	A	0.000	0.000	86.060	0.000	0.36
		B	0.000	0.000	80.600	0.000	0.50
		C	0.000	0.000	30.420	0.000	0.12
T13	28.00-8.00	A	0.000	0.000	43.030	0.000	0.18
		B	0.000	0.000	40.300	0.000	0.25
		C	0.000	0.000	15.210	0.000	0.06

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight K
T1	256.00-248.00	A	1.838	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	5.341	0.000	0.15
		C		0.000	0.000	29.001	0.000	0.43
T2	248.00-228.00	A	1.828	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	13.311	0.000	0.37
		C		0.000	0.000	82.849	0.000	1.17
T3	228.00-208.00	A	1.812	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	13.247	0.000	0.37
		C		0.000	0.000	93.008	0.000	1.27
T4	208.00-188.00	A	1.794	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	13.177	0.000	0.37
		C		0.000	0.000	92.643	0.000	1.25
T5	188.00-168.00	A	1.775	0.000	0.000	0.000	0.00	

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	9 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
		B		0.000	0.000	133.113	0.000	2.33
		C		0.000	0.000	92.244	0.000	1.24
T6	168.00-148.00	A	1.754	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	205.892	0.000	3.48
		C		0.000	0.000	91.802	0.000	1.22
T7	148.00-128.00	A	1.731	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	205.577	0.000	3.44
		C		0.000	0.000	91.307	0.000	1.21
T8	128.00-108.00	A	1.704	0.000	0.000	31.200	0.000	0.51
		B		0.000	0.000	205.218	0.000	3.40
		C		0.000	0.000	90.743	0.000	1.19
T9	108.00-88.00	A	1.672	0.000	0.000	150.946	0.000	3.14
		B		0.000	0.000	204.800	0.000	3.36
		C		0.000	0.000	95.960	0.000	1.25
T10	88.00-68.00	A	1.635	0.000	0.000	150.049	0.000	3.10
		B		0.000	0.000	204.296	0.000	3.30
		C		0.000	0.000	98.933	0.000	1.28
T11	68.00-48.00	A	1.587	0.000	0.000	148.916	0.000	3.05
		B		0.000	0.000	203.659	0.000	3.23
		C		0.000	0.000	97.743	0.000	1.24
T12	48.00-28.00	A	1.521	0.000	0.000	147.358	0.000	2.98
		B		0.000	0.000	202.782	0.000	3.14
		C		0.000	0.000	96.105	0.000	1.18
T13	28.00-8.00	A	1.412	0.000	0.000	72.382	0.000	1.43
		B		0.000	0.000	100.661	0.000	1.49
		C		0.000	0.000	46.690	0.000	0.55

Feed Line Center of Pressure

Section	Elevation ft	CP _x in	CP _z in	CP _x Ice in	CP _z Ice in
T1	256.00-248.00	-5.2299	1.2434	-8.2117	2.8011
T2	248.00-228.00	-6.2797	1.6923	-10.4867	3.9458
T3	228.00-208.00	-6.6722	1.9501	-10.9904	4.3397
T4	208.00-188.00	-7.5638	2.1870	-12.5556	4.9139
T5	188.00-168.00	2.9272	7.8650	-5.7515	9.8441
T6	168.00-148.00	8.0812	10.8188	-2.2754	13.1172
T7	148.00-128.00	8.8243	11.9854	-2.5158	14.6481
T8	128.00-108.00	7.3889	11.5822	-4.2035	12.8018
T9	108.00-88.00	-4.6882	18.3619	-14.2925	17.6662
T10	88.00-68.00	-4.4365	18.1503	-14.1835	18.4934
T11	68.00-48.00	-4.6638	19.3061	-14.9331	19.8117
T12	48.00-28.00	-4.8720	20.3929	-15.5832	21.1057
T13	28.00-8.00	-4.7583	18.7835	-12.9360	17.6440

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T1	7	Climbing Ladder	248.00 -	0.6000	0.5435

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	10 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
			256.00		
T1	12	LDF4-50A (1/2 FOAM)	248.00 - 256.00	0.6000	0.5435
T1	13	LDF6-50A (1-1/4 FOAM)	248.00 - 256.00	0.6000	0.5435
T1	15	LDF6-50A (1-1/4 FOAM)	248.00 - 256.00	0.6000	0.5435
T2	7	Climbing Ladder	228.00 - 248.00	0.6000	0.5983
T2	11	LDF5-50A (7/8 FOAM)	228.00 - 238.00	0.6000	0.5983
T2	12	LDF4-50A (1/2 FOAM)	228.00 - 248.00	0.6000	0.5983
T2	13	LDF6-50A (1-1/4 FOAM)	228.00 - 248.00	0.6000	0.5983
T2	15	LDF6-50A (1-1/4 FOAM)	228.00 - 248.00	0.6000	0.5983
T3	7	Climbing Ladder	208.00 - 228.00	0.6000	0.5844
T3	11	LDF5-50A (7/8 FOAM)	208.00 - 228.00	0.6000	0.5844
T3	12	LDF4-50A (1/2 FOAM)	208.00 - 228.00	0.6000	0.5844
T3	13	LDF6-50A (1-1/4 FOAM)	208.00 - 228.00	0.6000	0.5844
T3	15	LDF6-50A (1-1/4 FOAM)	208.00 - 228.00	0.6000	0.5844
T4	7	Climbing Ladder	188.00 - 208.00	0.6000	0.6000
T4	11	LDF5-50A (7/8 FOAM)	188.00 - 208.00	0.6000	0.6000
T4	12	LDF4-50A (1/2 FOAM)	188.00 - 208.00	0.6000	0.6000
T4	13	LDF6-50A (1-1/4 FOAM)	188.00 - 208.00	0.6000	0.6000
T4	15	LDF6-50A (1-1/4 FOAM)	188.00 - 208.00	0.6000	0.6000
T5	7	Climbing Ladder	168.00 - 188.00	0.6000	0.6000
T5	8	LDF7-50A (1-5/8 FOAM)	168.00 - 180.00	0.6000	0.6000
T5	11	LDF5-50A (7/8 FOAM)	168.00 - 188.00	0.6000	0.6000
T5	12	LDF4-50A (1/2 FOAM)	168.00 - 188.00	0.6000	0.6000
T5	13	LDF6-50A (1-1/4 FOAM)	168.00 - 188.00	0.6000	0.6000
T5	15	LDF6-50A (1-1/4 FOAM)	168.00 - 188.00	0.6000	0.6000
T5	18	HCS 6X12 4AWG(1-5/8)	168.00 - 188.00	0.6000	0.6000
T6	7	Climbing Ladder	148.00 - 168.00	0.6000	0.6000
T6	8	LDF7-50A (1-5/8 FOAM)	148.00 - 168.00	0.6000	0.6000
T6	11	LDF5-50A (7/8 FOAM)	148.00 - 168.00	0.6000	0.6000
T6	12	LDF4-50A (1/2 FOAM)	148.00 - 168.00	0.6000	0.6000
T6	13	LDF6-50A (1-1/4 FOAM)	148.00 - 168.00	0.6000	0.6000
T6	15	LDF6-50A (1-1/4 FOAM)	148.00 - 168.00	0.6000	0.6000

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 11 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
			168.00		
T6	18	HCS 6X12 4AWG(1-5/8)	148.00 - 168.00	0.6000	0.6000
T7	7	Climbing Ladder	128.00 - 148.00	0.6000	0.6000
T7	8	LDF7-50A (1-5/8 FOAM)	128.00 - 148.00	0.6000	0.6000
T7	11	LDF5-50A (7/8 FOAM)	128.00 - 148.00	0.6000	0.6000
T7	12	LDF4-50A (1/2 FOAM)	128.00 - 148.00	0.6000	0.6000
T7	13	LDF6-50A (1-1/4 FOAM)	128.00 - 148.00	0.6000	0.6000
T7	15	LDF6-50A (1-1/4 FOAM)	128.00 - 148.00	0.6000	0.6000
T7	18	HCS 6X12 4AWG(1-5/8)	128.00 - 148.00	0.6000	0.6000
T8	2	LDF7-50A (1-5/8 FOAM)	108.00 - 110.00	0.6000	0.6000
T8	4	LDF7-50A (1-5/8 FOAM)	108.00 - 110.00	0.6000	0.6000
T8	5	LDF4-50A (1/2 FOAM)	108.00 - 121.00	0.6000	0.6000
T8	7	Climbing Ladder	108.00 - 128.00	0.6000	0.6000
T8	8	LDF7-50A (1-5/8 FOAM)	108.00 - 128.00	0.6000	0.6000
T8	11	LDF5-50A (7/8 FOAM)	108.00 - 128.00	0.6000	0.6000
T8	12	LDF4-50A (1/2 FOAM)	108.00 - 128.00	0.6000	0.6000
T8	13	LDF6-50A (1-1/4 FOAM)	108.00 - 128.00	0.6000	0.6000
T8	15	LDF6-50A (1-1/4 FOAM)	108.00 - 128.00	0.6000	0.6000
T8	17	RFS HYBRIFLEX 1 1/4	108.00 - 121.00	0.6000	0.6000
T8	18	HCS 6X12 4AWG(1-5/8)	108.00 - 128.00	0.6000	0.6000
T9	2	LDF7-50A (1-5/8 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	4	LDF7-50A (1-5/8 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	5	LDF4-50A (1/2 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	7	Climbing Ladder	88.00 - 108.00	0.6000	0.6000
T9	8	LDF7-50A (1-5/8 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	10	LDF6-50A (1-1/4 FOAM)	88.00 - 100.00	0.6000	0.6000
T9	11	LDF5-50A (7/8 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	12	LDF4-50A (1/2 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	13	LDF6-50A (1-1/4 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	15	LDF6-50A (1-1/4 FOAM)	88.00 - 108.00	0.6000	0.6000
T9	17	RFS HYBRIFLEX 1 1/4	88.00 - 108.00	0.6000	0.6000
T9	18	HCS 6X12 4AWG(1-5/8)	88.00 - 108.00	0.6000	0.6000
T10	2	LDF7-50A (1-5/8 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	4	LDF7-50A (1-5/8 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	5	LDF4-50A (1/2 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	7	Climbing Ladder	68.00 - 88.00	0.6000	0.6000
T10	8	LDF7-50A (1-5/8 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	10	LDF6-50A (1-1/4 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	11	LDF5-50A (7/8 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	12	LDF4-50A (1/2 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	13	LDF6-50A (1-1/4 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	15	LDF6-50A (1-1/4 FOAM)	68.00 - 88.00	0.6000	0.6000
T10	17	RFS HYBRIFLEX 1 1/4	68.00 - 88.00	0.6000	0.6000

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 12 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T10	18	HCS 6X12 4AWG(1-5/8)	68.00 - 88.00	0.6000	0.6000
T11	2	LDF7-50A (1-5/8 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	4	LDF7-50A (1-5/8 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	5	LDF4-50A (1/2 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	7	Climbing Ladder	48.00 - 68.00	0.6000	0.6000
T11	8	LDF7-50A (1-5/8 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	10	LDF6-50A (1-1/4 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	11	LDF5-50A (7/8 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	12	LDF4-50A (1/2 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	13	LDF6-50A (1-1/4 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	15	LDF6-50A (1-1/4 FOAM)	48.00 - 68.00	0.6000	0.6000
T11	17	RFS HYBRIFLEX 1 1/4	48.00 - 68.00	0.6000	0.6000
T11	18	HCS 6X12 4AWG(1-5/8)	48.00 - 68.00	0.6000	0.6000
T12	2	LDF7-50A (1-5/8 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	4	LDF7-50A (1-5/8 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	5	LDF4-50A (1/2 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	7	Climbing Ladder	28.00 - 48.00	0.6000	0.6000
T12	8	LDF7-50A (1-5/8 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	10	LDF6-50A (1-1/4 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	11	LDF5-50A (7/8 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	12	LDF4-50A (1/2 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	13	LDF6-50A (1-1/4 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	15	LDF6-50A (1-1/4 FOAM)	28.00 - 48.00	0.6000	0.6000
T12	17	RFS HYBRIFLEX 1 1/4	28.00 - 48.00	0.6000	0.6000
T12	18	HCS 6X12 4AWG(1-5/8)	28.00 - 48.00	0.6000	0.6000
T13	2	LDF7-50A (1-5/8 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	4	LDF7-50A (1-5/8 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	5	LDF4-50A (1/2 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	7	Climbing Ladder	18.00 - 28.00	0.6000	0.6000
T13	8	LDF7-50A (1-5/8 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	10	LDF6-50A (1-1/4 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	11	LDF5-50A (7/8 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	12	LDF4-50A (1/2 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	13	LDF6-50A (1-1/4 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	15	LDF6-50A (1-1/4 FOAM)	18.00 - 28.00	0.6000	0.6000
T13	17	RFS HYBRIFLEX 1 1/4	18.00 - 28.00	0.6000	0.6000
T13	18	HCS 6X12 4AWG(1-5/8)	18.00 - 28.00	0.6000	0.6000

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	Placement	$C_A A_A$ Front	$C_A A_A$ Side	Weight	
			ft ft ft	°	ft	ft ²	ft ²	K	
10' Yagi w/ (5) 6' Elements	A	From Leg	0.00	0.0000	256.00	No Ice	2.70	1.50	0.11
			0.00			1/2" Ice	4.50	2.00	0.19
			0.00			1" Ice	6.30	2.50	0.27
Beacon	B	From Leg	0.00	0.0000	256.00	No Ice	1.20	1.20	0.03
			0.00			1/2" Ice	1.39	1.39	0.04
			0.00			1" Ice	1.59	1.59	0.06
2" Dia 10' Omni	A	From Leg	0.00	0.0000	256.00	No Ice	2.00	2.00	0.01
			0.00			1/2" Ice	3.03	3.03	0.03

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	13 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	CAAA Front	CAAA Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
2" Dia 10' Omni	A	From Leg	0.00	0.00	0.0000	256.00	1" Ice	4.06	4.06	0.04
			0.00	0.00			No Ice	2.00	2.00	0.01
			0.00	0.00			1/2" Ice	3.03	3.03	0.03
			0.00	0.00			1" Ice	4.06	4.06	0.04
2" Dia 10' Omni	A	From Leg	0.00	0.00	0.0000	239.00 - 256.00	No Ice	2.00	2.00	0.01
			0.00	0.00			1/2" Ice	3.03	3.03	0.03
			0.00	0.00			1" Ice	4.06	4.06	0.04
			0.00	0.00			No Ice	2.00	2.00	0.01
2" Dia 10' Omni	A	From Leg	0.00	0.00	0.0000	256.00	1/2" Ice	3.03	3.03	0.03
			0.00	0.00			1" Ice	4.06	4.06	0.04
			0.00	0.00			No Ice	2.00	2.00	0.01
			0.00	0.00			1/2" Ice	3.03	3.03	0.03
Platform Mount [LP 102-1]	C	None	0.00	0.00	0.0000	256.00	1" Ice	4.06	4.06	0.04
			0.00	0.00			No Ice	59.70	59.70	3.78
			0.00	0.00			1/2" Ice	71.20	71.20	4.51
***						1" Ice	82.70	82.70	5.24	
2" Dia 10' Omni	A	From Leg	0.00	0.00	0.0000	238.00 - 248.00	No Ice	2.00	2.00	0.01
			0.00	0.00			1/2" Ice	3.03	3.03	0.03
			0.00	0.00			1" Ice	4.06	4.06	0.04
			0.00	0.00			No Ice	2.82	2.20	0.04
Side Arm Mount [SO 309-1]	A	From Leg	0.00	0.00	0.0000	248.00 - 238.00	1/2" Ice	4.07	3.16	0.06
			0.00	0.00			1" Ice	5.32	4.12	0.08
			0.00	0.00						
180' T-Mobile										
AIR 21 B2A/B4P w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	180.00	No Ice	6.16	5.55	0.10
			0.00	0.00			1/2" Ice	6.60	6.30	0.16
			0.00	0.00			1" Ice	7.03	7.00	0.22
AIR 21 B2A/B4P w/ Mount Pipe	B	From Leg	4.00	0.00	0.0000	180.00	No Ice	6.16	5.55	0.10
			0.00	0.00			1/2" Ice	6.60	6.30	0.16
			0.00	0.00			1" Ice	7.03	7.00	0.22
AIR 21 B2A/B4P w/ Mount Pipe	C	From Leg	4.00	0.00	0.0000	180.00	No Ice	6.16	5.55	0.10
			0.00	0.00			1/2" Ice	6.60	6.30	0.16
			0.00	0.00			1" Ice	7.03	7.00	0.22
APXVAARR24_43-U-NA20 w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	180.00	No Ice	20.48	11.02	0.16
			0.00	0.00			1/2" Ice	21.23	12.55	0.30
			0.00	0.00			1" Ice	21.99	14.10	0.44
APXVAARR24_43-U-NA20 w/ Mount Pipe	B	From Leg	4.00	0.00	0.0000	180.00	No Ice	20.48	11.02	0.16
			0.00	0.00			1/2" Ice	21.23	12.55	0.30
			0.00	0.00			1" Ice	21.99	14.10	0.44
APXVAARR24_43-U-NA20 w/ Mount Pipe	C	From Leg	4.00	0.00	0.0000	180.00	No Ice	20.48	11.02	0.16
			0.00	0.00			1/2" Ice	21.23	12.55	0.30
			0.00	0.00			1" Ice	21.99	14.10	0.44
AIR 3246 B66 w/ Mount Pipe	A	From Leg	4.00	0.00	0.0000	180.00	No Ice	8.18	6.56	0.20
			0.00	0.00			1/2" Ice	8.66	7.39	0.27
			0.00	0.00			1" Ice	9.12	8.13	0.35
AIR 3246 B66 w/ Mount Pipe	B	From Leg	4.00	0.00	0.0000	180.00	No Ice	8.18	6.56	0.20
			0.00	0.00			1/2" Ice	8.66	7.39	0.27
			0.00	0.00			1" Ice	9.12	8.13	0.35
AIR 3246 B66 w/ Mount Pipe	C	From Leg	4.00	0.00	0.0000	180.00	No Ice	8.18	6.56	0.20
			0.00	0.00			1/2" Ice	8.66	7.39	0.27
			0.00	0.00			1" Ice	9.12	8.13	0.35
Generic Style 1B - Twin AWS	A	From Leg	4.00	0.00	0.0000	180.00	No Ice	0.40	0.16	0.01
			0.00	0.00			1/2" Ice	0.49	0.22	0.01
			0.00	0.00			1" Ice	0.57	0.28	0.02
Generic Style 1B - Twin AWS	B	From Leg	4.00	0.00	0.0000	180.00	No Ice	0.40	0.16	0.01
			0.00	0.00			1/2" Ice	0.49	0.22	0.01
			0.00	0.00			1" Ice	0.57	0.28	0.02
Generic Style 1B - Twin AWS	C	From Leg	4.00	0.00	0.0000	180.00	No Ice	0.40	0.16	0.01
			0.00	0.00			1/2" Ice	0.49	0.22	0.01
			0.00	0.00			1" Ice	0.57	0.28	0.02

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	14 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	CAAA Front ft ²	CAAA Side ft ²	Weight K
RADIO 4449 B12/B71	A	From Leg	4.00 0.00 0.00	0.0000	180.00	No Ice 1.65 1/2" Ice 1.81 1" Ice 1.98	1.30 1.44 1.60	0.08 0.09 0.11
RADIO 4449 B12/B71	B	From Leg	4.00 0.00 0.00	0.0000	180.00	No Ice 1.65 1/2" Ice 1.81 1" Ice 1.98	1.30 1.44 1.60	0.08 0.09 0.11
RADIO 4449 B12/B71	C	From Leg	4.00 0.00 0.00	0.0000	180.00	No Ice 1.65 1/2" Ice 1.81 1" Ice 1.98	1.30 1.44 1.60	0.08 0.09 0.11
RRUS 32 B2	A	From Leg	4.00 0.00 0.00	0.0000	180.00	No Ice 2.73 1/2" Ice 2.95 1" Ice 3.18	1.67 1.86 2.05	0.05 0.07 0.10
RRUS 32 B2	B	From Leg	4.00 0.00 0.00	0.0000	180.00	No Ice 2.73 1/2" Ice 2.95 1" Ice 3.18	1.67 1.86 2.05	0.05 0.07 0.10
RRUS 32 B2	C	From Leg	4.00 0.00 0.00	0.0000	180.00	No Ice 2.73 1/2" Ice 2.95 1" Ice 3.18	1.67 1.86 2.05	0.05 0.07 0.10
Sector Mount [SM 404-3]	C	None		0.0000	180.00	No Ice 20.47 1/2" Ice 28.97 1" Ice 37.47	20.47 28.97 37.47	0.92 1.34 1.75
138' MetroPCS ***121' Clearwire*** ***110' Verizon***								
(2) APL866513-42T6	A	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 4.05 1/2" Ice 4.36 1" Ice 4.68	3.61 3.92 4.23	0.02 0.05 0.08
(2) APL866513-42T6	B	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 4.05 1/2" Ice 4.36 1" Ice 4.68	3.61 3.92 4.23	0.02 0.05 0.08
(2) APL866513-42T6	C	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 4.05 1/2" Ice 4.36 1" Ice 4.68	3.61 3.92 4.23	0.02 0.05 0.08
RRH2x60-AWS	A	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 3.50 1/2" Ice 3.76 1" Ice 4.03	2.10 2.34 2.58	0.06 0.08 0.11
RRH2x60-AWS	B	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 3.50 1/2" Ice 3.76 1" Ice 4.03	2.10 2.34 2.58	0.06 0.08 0.11
RRH2x60-AWS	C	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 3.50 1/2" Ice 3.76 1" Ice 4.03	2.10 2.34 2.58	0.06 0.08 0.11
CW JUNCTION BOX	A	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 1.20 1/2" Ice 1.34 1" Ice 1.48	0.60 0.70 0.81	0.00 0.01 0.02
RRH2x60-700	A	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 3.50 1/2" Ice 3.76 1" Ice 4.03	1.82 2.05 2.29	0.06 0.08 0.11
RRH2x60-700	B	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 3.50 1/2" Ice 3.76 1" Ice 4.03	1.82 2.05 2.29	0.06 0.08 0.11
RRH2x60-700	C	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 3.50 1/2" Ice 3.76 1" Ice 4.03	1.82 2.05 2.29	0.06 0.08 0.11
GPS	A	From Leg	4.00 0.00 0.00	0.0000	110.00	No Ice 0.33 1/2" Ice 0.48 1" Ice 0.65	0.33 0.48 0.65	0.01 0.01 0.02

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	15 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	CAAA Front	CAAA Side	Weight
			Horz	Lateral					
(2) HBXX-6516DS-A2M	A	From Leg	4.00	0.0000	110.00	No Ice	5.42	3.28	0.03
			0.00			1/2" Ice	5.76	3.61	0.07
			0.00			1" Ice	6.11	3.94	0.11
(2) HBXX-6516DS-A2M	B	From Leg	4.00	0.0000	110.00	No Ice	5.42	3.28	0.03
			0.00			1/2" Ice	5.76	3.61	0.07
			0.00			1" Ice	6.11	3.94	0.11
(2) HBXX-6516DS-A2M	C	From Leg	4.00	0.0000	110.00	No Ice	5.42	3.28	0.03
			0.00			1/2" Ice	5.76	3.61	0.07
			0.00			1" Ice	6.11	3.94	0.11
B25 RRH2x60 PCS	A	From Leg	4.00	0.0000	110.00	No Ice	2.14	1.31	0.05
			0.00			1/2" Ice	2.33	1.46	0.07
			0.00			1" Ice	2.53	1.63	0.09
B25 RRH2x60 PCS	B	From Leg	4.00	0.0000	110.00	No Ice	2.14	1.31	0.05
			0.00			1/2" Ice	2.33	1.46	0.07
			0.00			1" Ice	2.53	1.63	0.09
B25 RRH2x60 PCS	C	From Leg	4.00	0.0000	110.00	No Ice	2.14	1.31	0.05
			0.00			1/2" Ice	2.33	1.46	0.07
			0.00			1" Ice	2.53	1.63	0.09
800 10736V01	A	From Leg	4.00	0.0000	110.00	No Ice	11.39	5.17	0.04
			0.00			1/2" Ice	12.01	5.74	0.09
			0.00			1" Ice	12.63	6.32	0.15
800 10736V01	B	From Leg	4.00	0.0000	110.00	No Ice	11.39	5.17	0.04
			0.00			1/2" Ice	12.01	5.74	0.09
			0.00			1" Ice	12.63	6.32	0.15
800 10736V01	C	From Leg	4.00	0.0000	110.00	No Ice	11.39	5.17	0.04
			0.00			1/2" Ice	12.01	5.74	0.09
			0.00			1" Ice	12.63	6.32	0.15
CW JUNCTION BOX	A	From Leg	4.00	0.0000	110.00	No Ice	1.20	0.60	0.00
			0.00			1/2" Ice	1.34	0.70	0.01
			0.00			1" Ice	1.48	0.81	0.02
Sector Mount [SM 303-3]	C	None		0.0000	110.00	No Ice	43.57	43.57	1.88
						1/2" Ice	61.82	61.82	2.70
						1" Ice	80.07	80.07	3.53
100									
TV 65 Antenna	A	From Leg	1.00	0.0000	100.00	No Ice	3.88	3.44	0.04
			0.00			1/2" Ice	4.20	3.93	0.08
			0.00			1" Ice	4.54	4.43	0.12
TV 65 Antenna	A	From Leg	1.00	0.0000	100.00	No Ice	3.88	3.44	0.04
			0.00			1/2" Ice	4.20	3.93	0.08
			0.00			1" Ice	4.54	4.43	0.12
Side Arm Mount [SO 309-1]	A	From Leg	0.00	0.0000	100.00	No Ice	2.82	2.20	0.04
			0.00			1/2" Ice	4.07	3.16	0.06
			0.00			1" Ice	5.32	4.12	0.08
Sprint									
NNVV-65B-R4 w/ Mount Pipe	A	From Leg	2.00	0.0000	118.00	No Ice	12.51	7.41	0.10
			0.00			1/2" Ice	13.11	8.60	0.19
			0.00			1" Ice	13.67	9.50	0.29
NNVV-65B-R4 w/ Mount Pipe	B	From Leg	2.00	0.0000	118.00	No Ice	12.51	7.41	0.10
			0.00			1/2" Ice	13.11	8.60	0.19
			0.00			1" Ice	13.67	9.50	0.29
NNVV-65B-R4 w/ Mount Pipe	C	From Leg	2.00	0.0000	118.00	No Ice	12.51	7.41	0.10
			0.00			1/2" Ice	13.11	8.60	0.19
			0.00			1" Ice	13.67	9.50	0.29
AAHC w/ Mount Pipe	A	From Leg	2.00	0.0000	118.00	No Ice	4.41	2.69	0.12
			0.00			1/2" Ice	4.73	3.08	0.16
			0.00			1" Ice	5.06	3.49	0.20
AAHC w/ Mount Pipe	B	From Leg	2.00	0.0000	118.00	No Ice	4.41	2.69	0.12

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 16 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft ²	ft ²	K	
			0.00				1/2" Ice	4.73	3.08	0.16
			0.00				1" Ice	5.06	3.49	0.20
AAHC w/ Mount Pipe	C	From Leg	2.00		0.0000	118.00	No Ice	4.41	2.69	0.12
			0.00				1/2" Ice	4.73	3.08	0.16
			0.00				1" Ice	5.06	3.49	0.20
(2) 800 MHz RRH	A	From Leg	2.00		0.0000	118.00	No Ice	2.13	1.77	0.05
			0.00				1/2" Ice	2.32	1.95	0.07
			0.00				1" Ice	2.51	2.13	0.10
(2) 800 MHz RRH	B	From Leg	2.00		0.0000	118.00	No Ice	2.13	1.77	0.05
			0.00				1/2" Ice	2.32	1.95	0.07
			0.00				1" Ice	2.51	2.13	0.10
(2) 800 MHz RRH	C	From Leg	2.00		0.0000	118.00	No Ice	2.13	1.77	0.05
			0.00				1/2" Ice	2.32	1.95	0.07
			0.00				1" Ice	2.51	2.13	0.10
RRH1900MHz	A	From Leg	2.00		0.0000	118.00	No Ice	2.60	3.72	0.06
			0.00				1/2" Ice	2.84	4.10	0.10
			0.00				1" Ice	3.09	4.50	0.14
RRH1900MHz	B	From Leg	2.00		0.0000	118.00	No Ice	2.60	3.72	0.06
			0.00				1/2" Ice	2.84	4.10	0.10
			0.00				1" Ice	3.09	4.50	0.14
RRH1900MHz	C	From Leg	2.00		0.0000	118.00	No Ice	2.60	3.72	0.06
			0.00				1/2" Ice	2.84	4.10	0.10
			0.00				1" Ice	3.09	4.50	0.14
Sector Mount [SM 703-3]	C	None			0.0000	118.00	No Ice	25.30	25.30	1.04
							1/2" Ice	35.43	35.43	1.46
							1" Ice	45.56	45.56	1.88

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz	Lateral							Vert
			ft	ft	°	°	ft	ft	ft ²	K		
VHLP1-23	A	Paraboloid w/o Radome	From Leg	1.00		0.0000		121.00	1.27	No Ice	1.28	0.01
				0.00						1/2" Ice	1.45	0.02
				0.00						1" Ice	1.62	0.03
VHLP1-23	B	Paraboloid w/o Radome	From Leg	1.00		0.0000		121.00	1.27	No Ice	1.28	0.01
				0.00						1/2" Ice	1.45	0.02
				0.00						1" Ice	1.62	0.03
VHLP2.5-11	C	Paraboloid w/Shroud (HP)	From Leg	1.00		0.0000		121.00	2.92	No Ice	6.68	0.05
				0.00						1/2" Ice	7.07	0.08
				0.00						1" Ice	7.46	0.12

Load Combinations

<p style="text-align: center;">tnxTower</p> <p style="text-align: center;">Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:</p>	<p>Job</p> <p style="text-align: center;">CT52XC007</p>	<p>Page</p> <p style="text-align: center;">17 of 33</p>
	<p>Project</p> <p style="text-align: center;">1729061</p>	<p>Date</p> <p style="text-align: center;">15:15:01 08/20/18</p>
	<p>Client</p> <p style="text-align: center;">ComEx Consultants</p>	<p>Designed by</p> <p style="text-align: center;">Ahmet Colakoglu</p>

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.6 Wind 0 deg - No Ice
3	0.9 Dead+1.6 Wind 0 deg - No Ice
4	1.2 Dead+1.6 Wind 30 deg - No Ice
5	0.9 Dead+1.6 Wind 30 deg - No Ice
6	1.2 Dead+1.6 Wind 60 deg - No Ice
7	0.9 Dead+1.6 Wind 60 deg - No Ice
8	1.2 Dead+1.6 Wind 90 deg - No Ice
9	0.9 Dead+1.6 Wind 90 deg - No Ice
10	1.2 Dead+1.6 Wind 120 deg - No Ice
11	0.9 Dead+1.6 Wind 120 deg - No Ice
12	1.2 Dead+1.6 Wind 150 deg - No Ice
13	0.9 Dead+1.6 Wind 150 deg - No Ice
14	1.2 Dead+1.6 Wind 180 deg - No Ice
15	0.9 Dead+1.6 Wind 180 deg - No Ice
16	1.2 Dead+1.6 Wind 210 deg - No Ice
17	0.9 Dead+1.6 Wind 210 deg - No Ice
18	1.2 Dead+1.6 Wind 240 deg - No Ice
19	0.9 Dead+1.6 Wind 240 deg - No Ice
20	1.2 Dead+1.6 Wind 270 deg - No Ice
21	0.9 Dead+1.6 Wind 270 deg - No Ice
22	1.2 Dead+1.6 Wind 300 deg - No Ice
23	0.9 Dead+1.6 Wind 300 deg - No Ice
24	1.2 Dead+1.6 Wind 330 deg - No Ice
25	0.9 Dead+1.6 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T1	256 - 248	Leg	Max Tension	7	2.54	-0.03	-0.00
			Max. Compression	2	-5.84	0.06	0.00
			Max. Mx	2	-5.84	0.06	0.00

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	18 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T2	248 - 228	Diagonal	Max. My	8	-1.89	0.00	0.06
			Max. Vy	14	-1.18	0.00	0.00
			Max. Vx	8	1.23	0.00	-0.00
			Max Tension	16	1.73	0.00	0.00
			Max. Compression	16	-1.69	0.00	0.00
			Max. Mx	38	0.61	0.02	0.00
			Max. My	35	0.06	0.02	-0.00
			Max. Vy	37	0.03	0.02	0.00
			Max. Vx	35	0.00	0.00	0.00
			Max Tension	2	0.60	0.00	0.00
		Top Girt	Max. Compression	14	-0.62	0.00	0.00
			Max. Mx	26	-0.04	-0.11	0.00
			Max. My	32	-0.04	0.00	0.00
			Max. Vy	26	0.07	0.00	0.00
			Max. Vx	32	-0.00	0.00	0.00
			Max Tension	15	21.96	0.01	-0.06
			Max. Compression	2	-27.55	-0.01	0.09
			Max. Mx	8	17.26	-0.09	-0.00
			Max. My	2	10.11	0.00	0.10
			Max. Vy	8	0.07	-0.07	-0.00
Diagonal	Max. Vx	2	-0.07	0.01	0.07		
	Max Tension	16	3.19	0.00	0.00		
	Max. Compression	4	-3.20	0.00	0.00		
	Max. Mx	27	1.04	0.03	0.00		
	Max. My	8	-1.44	0.01	0.00		
	Max. Vy	27	-0.03	0.03	0.00		
	Max. Vx	8	0.00	0.00	0.00		
	Max Tension	15	52.14	0.07	0.00		
	Max. Compression	2	-61.11	-0.73	-0.04		
	Max. Mx	2	-61.11	-0.73	-0.04		
T3	228 - 208	Leg	Max. My	4	-2.88	0.04	0.42
			Max. Vy	2	0.22	-0.73	-0.04
			Max. Vx	24	0.14	0.04	-0.42
			Max Tension	16	4.50	0.00	0.00
			Max. Compression	4	-4.63	0.00	0.00
		Diagonal	Max. Mx	27	1.32	0.03	0.00
			Max. My	2	-3.81	0.00	0.00
			Max. Vy	27	-0.03	0.03	0.00
			Max. Vx	2	-0.00	0.00	0.00
			Max Tension	15	72.00	-0.41	-0.01
T4	208 - 188	Leg	Max. Compression	2	-84.36	0.35	0.03
			Max. Mx	2	-67.68	0.73	0.04
			Max. My	24	-3.97	-0.01	0.75
			Max. Vy	2	0.17	0.73	0.04
			Max. Vx	12	0.18	-0.01	-0.75
		Diagonal	Max Tension	16	3.02	0.00	0.00
			Max. Compression	2	-3.08	0.00	0.00
			Max. Mx	33	0.52	0.04	-0.01
			Max. My	27	-0.28	0.04	0.01
			Max. Vy	33	0.04	0.04	-0.01
T5	188 - 168	Leg	Max. Vx	27	-0.00	0.00	0.00
			Max Tension	15	93.29	-0.83	0.01
			Max. Compression	2	-111.14	0.72	-0.00
			Max. Mx	3	-88.87	1.19	-0.02
			Max. My	4	-5.86	-0.04	-1.09
		Diagonal	Max. Vy	22	-1.37	-1.17	0.01
			Max. Vx	4	-1.26	-0.02	-0.76
			Max Tension	16	5.64	0.00	0.00
			Max. Compression	16	-5.71	0.00	0.00
			Max. Mx	33	1.14	0.08	-0.01
Max. My	32	-0.95	0.06	-0.01			

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	19 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft			
T6	168 - 148	Leg	Max. Vy	33	0.06	0.08	-0.01			
			Max. Vx	27	-0.00	0.00	0.00			
			Max Tension	15	121.68	-0.62	0.03			
			Max. Compression	2	-143.82	0.73	-0.02			
			Max. Mx	2	-143.82	0.73	-0.02			
			Max. My	4	-7.46	-0.01	-0.74			
		Diagonal	Max. Vy	19	-0.11	0.71	0.06			
			Max. Vx	16	0.18	-0.01	0.74			
			Max Tension	20	6.28	0.00	0.00			
			Max. Compression	18	-6.53	0.00	0.00			
			Max. Mx	33	1.21	0.12	-0.02			
			Max. My	32	-1.00	0.10	-0.02			
			Max. Vy	33	0.08	0.12	-0.02			
			Max. Vx	32	0.00	0.00	0.00			
T7	148 - 128	Leg	Max Tension	15	149.62	-0.55	0.02			
			Max. Compression	2	-176.46	1.63	-0.02			
			Max. Mx	18	-174.36	1.65	0.24			
			Max. My	4	-9.69	0.04	-1.70			
			Max. Vy	19	-0.26	1.65	0.24			
			Max. Vx	4	0.38	0.04	-1.70			
		Diagonal	Max Tension	18	7.31	0.00	0.00			
			Max. Compression	18	-7.35	0.00	0.00			
			Max. Mx	33	1.70	0.15	0.02			
			Max. My	35	-0.50	0.14	0.02			
			Max. Vy	33	0.09	0.15	0.02			
			Max. Vx	35	-0.00	0.00	0.00			
			T8	128 - 108	Leg	Max Tension	15	175.67	-1.73	0.02
						Max. Compression	2	-209.74	2.67	-0.01
Max. Mx	3	-206.07				2.68	-0.01			
Max. My	4	-10.58				-0.09	-2.62			
Max. Vy	14	1.63				-2.58	0.02			
Max. Vx	16	1.70				-0.13	2.61			
Diagonal	Max Tension	6			10.82	0.00	0.00			
	Max. Compression	18			-11.63	0.00	0.00			
	Max. Mx	35			3.41	0.32	-0.04			
	Max. My	29			2.61	0.29	-0.05			
	Max. Vy	33			0.15	0.31	-0.04			
	Max. Vx	35			-0.01	0.00	0.00			
	T9	108 - 88			Leg	Max Tension	7	212.93	-0.89	-0.04
						Max. Compression	18	-254.64	2.48	0.25
Max. Mx			3	-226.86		2.68	-0.01			
Max. My			4	-16.16		0.03	-2.51			
Max. Vy			3	0.38		2.68	-0.01			
Max. Vx			24	-0.42		0.03	2.39			
Diagonal			Max Tension	20	13.37	0.00	0.00			
			Max. Compression	20	-13.61	0.00	0.00			
			Max. Mx	33	2.33	0.34	-0.05			
			Max. My	35	-0.14	0.29	0.05			
			Max. Vy	33	0.15	0.34	-0.05			
			Max. Vx	35	0.01	0.00	0.00			
			T10	88 - 68	Leg	Max Tension	7	253.44	-2.25	-0.07
						Max. Compression	18	-303.34	2.55	0.09
Max. Mx	18	-303.34				2.55	0.09			
Max. My	4	-16.94				0.03	-2.51			
Max. Vy	3	-0.23				2.51	0.03			
Max. Vx	24	0.39				0.03	2.39			
Diagonal	Max Tension	20			16.08	0.00	0.00			
	Max. Compression	20			-16.30	0.00	0.00			
	Max. Mx	33			2.54	0.53	-0.07			
	Max. My	29			-4.17	0.45	-0.07			
	Max. Vy	33			0.22	0.53	-0.07			

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	20 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft		
T11	68 - 48	Leg	Max. Vx	35	0.01	0.00	0.00		
			Max Tension	7	295.02	-2.09	-0.08		
			Max. Compression	18	-353.79	3.35	0.07		
			Max. Mx	18	-353.79	3.35	0.07		
			Max. My	16	-21.44	-0.24	3.43		
			Max. Vy	2	-0.35	3.31	0.02		
			Max. Vx	12	-0.61	-0.23	-3.24		
		Diagonal	Max Tension	20	18.04	0.00	0.00		
			Max. Compression	20	-18.44	0.00	0.00		
			Max. Mx	35	5.20	0.61	-0.07		
			Max. My	35	0.05	0.54	0.08		
			Max. Vy	33	0.24	0.61	-0.08		
			Max. Vx	35	0.01	0.00	0.00		
			T12	48 - 28	Leg	Max Tension	7	335.56	-2.90
Max. Compression	18	-403.71				-5.14	0.03		
Max. Mx	18	-403.71				-5.14	0.03		
Max. My	16	-26.42				-0.83	5.83		
Max. Vy	18	0.99				2.90	0.09		
Max. Vx	12	0.71				-0.15	-4.42		
Diagonal	Max Tension	20				19.27	0.00	0.00	
	Max. Compression	20			-19.67	0.00	0.00		
	Max. Mx	34			2.83	0.71	-0.09		
	Max. My	32			3.64	0.68	-0.10		
	Max. Vy	34			0.25	0.70	0.10		
	Max. Vx	32			-0.01	0.00	0.00		
	T13	28 - 8			Leg	Max Tension	7	342.73	3.13
Max. Compression						18	-416.45	-0.00	-0.00
Max. Mx			18	-415.72		15.28	-1.33		
Max. My			24	-26.93		1.35	-6.55		
Max. Vy			18	-2.13		15.28	-1.33		
Max. Vx			16	1.37		-0.83	5.83		
Diagonal			Max Tension	21		28.64	-0.12	-0.04	
			Max. Compression	20	-29.34	0.00	0.00		
			Max. Mx	20	12.06	-0.20	0.02		
			Max. My	20	-29.24	-0.02	-0.15		
			Max. Vy	33	0.08	-0.20	0.01		
			Max. Vx	20	-0.01	0.00	0.00		
			Horizontal	Max Tension	9	16.07	0.00	0.00	
Max. Compression				9	-16.19	-0.15	0.00		
Max. Mx				33	-2.19	-0.39	-0.01		
Max. My				10	2.72	-0.11	0.04		
Max. Vy				33	0.14	-0.39	-0.01		
Max. Vx				10	-0.00	-0.11	0.04		
Redund Horz 1 Bracing				Max Tension	18	7.23	0.00	0.00	
			Max. Compression	18	-7.23	0.00	0.00		
			Max. Mx	30	2.89	0.09	0.00		
			Max. My	10	7.08	0.00	0.00		
			Max. Vy	30	0.06	0.00	0.00		
	Redund Diag 1 Bracing	Max Tension	18	6.57	0.00	0.00			
		Max. Compression	18	-6.57	0.00	0.00			
Max. Mx		35	3.01	0.15	0.00				
Max. My		10	6.44	0.00	-0.00				
Max. Vy		35	-0.05	0.00	0.00				
Max. Vx		10	0.00	0.00	0.00				
Redund Hip 1 Bracing		Max Tension	1	0.00	0.00	0.00			
	Max. Compression	8	-0.09	0.00	0.00				
	Max. Mx	26	-0.02	0.05	0.00				
	Max. Vy	26	-0.03	0.00	0.00				

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 21 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
		Redund Hip Diagonal 1 Bracing	Max Tension	8	0.14	0.00	0.00
			Max. Compression	18	-0.07	0.00	0.00
			Max. Mx	33	0.05	0.20	0.00
			Max. My	18	0.05	0.00	0.00
			Max. Vy	33	-0.05	0.00	0.00
			Max. Vx	18	-0.00	0.00	0.00
		Inner Bracing	Max Tension	9	0.01	0.00	0.00
			Max. Compression	8	-0.03	0.00	0.00
			Max. Mx	26	-0.02	0.36	0.00
			Max. My	18	-0.00	0.00	0.00
			Max. Vy	26	0.11	0.00	0.00
			Max. Vx	18	-0.00	0.00	0.00

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg C	Max. Vert	18	455.92	47.94	-25.77
	Max. H _x	18	455.92	47.94	-25.77
	Max. H _z	5	-333.51	-34.89	22.43
	Min. Vert	7	-377.51	-42.02	22.21
	Min. H _x	7	-377.51	-42.02	22.21
	Min. H _z	18	455.92	47.94	-25.77
Leg B	Max. Vert	10	447.46	-47.53	-25.51
	Max. H _x	23	-368.14	41.57	21.93
	Max. H _z	23	-368.14	41.57	21.93
	Min. Vert	23	-368.14	41.57	21.93
	Min. H _x	10	447.46	-47.53	-25.51
	Min. H _z	10	447.46	-47.53	-25.51
Leg A	Max. Vert	2	446.43	-0.16	52.79
	Max. H _x	21	20.91	5.92	1.83
	Max. H _z	2	446.43	-0.16	52.79
	Min. Vert	15	-369.08	0.18	-45.84
	Min. H _x	9	21.64	-5.91	1.92
	Min. H _z	15	-369.08	0.18	-45.84

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	71.96	0.00	0.00	12.19	-4.96	-0.00
1.2 Dead+1.6 Wind 0 deg - No Ice	86.35	0.11	-86.97	-10067.14	-18.00	-7.95
0.9 Dead+1.6 Wind 0 deg - No Ice	64.76	0.11	-86.97	-10060.82	-16.48	-7.96
1.2 Dead+1.6 Wind 30 deg - No Ice	86.35	42.50	-73.56	-8555.41	-4953.19	78.74
0.9 Dead+1.6 Wind 30 deg - No Ice	64.76	42.50	-73.56	-8550.61	-4946.78	78.72
1.2 Dead+1.6 Wind 60 deg - No Ice	86.35	72.72	-42.08	-4812.10	-8340.22	82.87

<p style="text-align: center;">tnxTower</p> <p style="text-align: center;">Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:</p>	Job	CT52XC007	Page	22 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Ice						
0.9 Dead+1.6 Wind 60 deg - No Ice	64.76	72.72	-42.08	-4811.04	-8330.54	82.86
1.2 Dead+1.6 Wind 90 deg - No Ice	86.35	85.81	-0.11	2.43	-9564.27	75.20
0.9 Dead+1.6 Wind 90 deg - No Ice	64.76	85.81	-0.11	-1.23	-9553.54	75.20
1.2 Dead+1.6 Wind 120 deg - No Ice	86.35	77.37	44.64	5055.53	-8734.47	83.34
0.9 Dead+1.6 Wind 120 deg - No Ice	64.76	77.37	44.64	5046.93	-8724.43	83.34
1.2 Dead+1.6 Wind 150 deg - No Ice	86.35	38.89	67.67	7832.76	-4495.20	117.93
0.9 Dead+1.6 Wind 150 deg - No Ice	64.76	38.89	67.67	7821.26	-4489.19	117.93
1.2 Dead+1.6 Wind 180 deg - No Ice	86.35	-0.10	81.02	9429.91	5.51	8.10
0.9 Dead+1.6 Wind 180 deg - No Ice	64.76	-0.10	81.02	9416.82	7.01	8.11
1.2 Dead+1.6 Wind 210 deg - No Ice	86.35	-42.43	73.55	8584.10	4932.30	-79.04
0.9 Dead+1.6 Wind 210 deg - No Ice	64.76	-42.43	73.55	8571.95	4928.93	-79.02
1.2 Dead+1.6 Wind 240 deg - No Ice	86.35	-77.85	45.04	5173.10	8901.99	-82.88
0.9 Dead+1.6 Wind 240 deg - No Ice	64.76	-77.85	45.04	5164.37	8894.78	-82.86
1.2 Dead+1.6 Wind 270 deg - No Ice	86.35	-85.77	0.05	20.09	9547.27	-74.90
0.9 Dead+1.6 Wind 270 deg - No Ice	64.76	-85.77	0.05	16.41	9539.56	-74.89
1.2 Dead+1.6 Wind 300 deg - No Ice	86.35	-72.21	-41.66	-4693.13	8144.86	-83.50
0.9 Dead+1.6 Wind 300 deg - No Ice	64.76	-72.21	-41.66	-4692.19	8138.39	-83.49
1.2 Dead+1.6 Wind 330 deg - No Ice	86.35	-39.02	-67.60	-7795.29	4497.30	-117.93
0.9 Dead+1.6 Wind 330 deg - No Ice	64.76	-39.02	-67.60	-7791.14	4494.30	-117.94
1.2 Dead+1.0 Ice+1.0 Temp	211.83	-0.00	-0.00	162.16	7.07	-0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	211.83	0.02	-24.38	-2815.27	5.01	-16.94
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	211.83	12.73	-22.08	-2494.95	-1522.17	21.91
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	211.83	22.38	-12.96	-1362.96	-2621.77	35.37
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	211.83	24.92	-0.02	160.52	-2893.87	22.64
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	211.83	20.62	11.92	1573.72	-2426.33	23.35
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	211.83	11.25	19.58	2545.45	-1358.23	34.66
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	211.83	-0.02	23.52	3047.52	9.25	16.97
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	211.83	-12.72	22.08	2820.94	1534.36	-21.98
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	211.83	-23.12	13.39	1735.49	2716.44	-35.38
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	211.83	-24.91	0.01	163.83	2907.04	-22.57
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	211.83	-19.87	-11.49	-1200.77	2359.35	-23.37

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 23 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	211.83	-11.27	-19.56	-2217.71	1375.41	-34.67
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	71.96	0.03	-20.80	-2397.22	-7.86	-1.90
Dead+Wind 30 deg - Service	71.96	10.16	-17.59	-2035.87	-1187.24	18.83
Dead+Wind 60 deg - Service	71.96	17.39	-10.06	-1141.31	-1996.69	19.81
Dead+Wind 90 deg - Service	71.96	20.52	-0.03	9.27	-2289.25	17.98
Dead+Wind 120 deg - Service	71.96	18.50	10.67	1216.86	-2090.95	19.93
Dead+Wind 150 deg - Service	71.96	9.30	16.18	1880.59	-1077.94	28.20
Dead+Wind 180 deg - Service	71.96	-0.02	19.37	2262.24	-2.26	1.94
Dead+Wind 210 deg - Service	71.96	-10.15	17.59	2060.11	1175.18	-18.90
Dead+Wind 240 deg - Service	71.96	-18.62	10.77	1244.95	2123.86	-19.81
Dead+Wind 270 deg - Service	71.96	-20.51	0.01	13.49	2278.06	-17.91
Dead+Wind 300 deg - Service	71.96	-17.27	-9.96	-1112.87	1942.88	-19.96
Dead+Wind 330 deg - Service	71.96	-9.33	-16.16	-1854.31	1071.16	-28.20

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-71.96	0.00	-0.00	71.96	-0.00	0.000%
2	0.11	-86.35	-86.97	-0.11	86.35	86.97	0.001%
3	0.11	-64.76	-86.97	-0.11	64.76	86.97	0.001%
4	42.50	-86.35	-73.56	-42.50	86.35	73.56	0.001%
5	42.50	-64.76	-73.56	-42.50	64.76	73.56	0.001%
6	72.72	-86.35	-42.08	-72.72	86.35	42.08	0.001%
7	72.72	-64.76	-42.08	-72.72	64.76	42.08	0.001%
8	85.81	-86.35	-0.11	-85.81	86.35	0.11	0.001%
9	85.81	-64.76	-0.11	-85.81	64.76	0.11	0.001%
10	77.37	-86.35	44.64	-77.37	86.35	-44.64	0.001%
11	77.37	-64.76	44.64	-77.37	64.76	-44.64	0.001%
12	38.90	-86.35	67.67	-38.89	86.35	-67.67	0.001%
13	38.90	-64.76	67.67	-38.89	64.76	-67.67	0.001%
14	-0.10	-86.35	81.02	0.10	86.35	-81.02	0.001%
15	-0.10	-64.76	81.02	0.10	64.76	-81.02	0.001%
16	-42.43	-86.35	73.55	42.43	86.35	-73.55	0.001%
17	-42.43	-64.76	73.55	42.43	64.76	-73.55	0.001%
18	-77.85	-86.35	45.04	77.85	86.35	-45.04	0.001%
19	-77.85	-64.76	45.04	77.85	64.76	-45.04	0.001%
20	-85.77	-86.35	0.05	85.77	86.35	-0.05	0.001%
21	-85.77	-64.76	0.05	85.77	64.76	-0.05	0.001%
22	-72.21	-86.35	-41.66	72.21	86.35	41.66	0.001%
23	-72.21	-64.76	-41.66	72.21	64.76	41.66	0.001%
24	-39.02	-86.35	-67.60	39.02	86.35	67.60	0.001%
25	-39.02	-64.76	-67.60	39.02	64.76	67.60	0.001%
26	0.00	-211.83	0.00	0.00	211.83	0.00	0.000%
27	0.02	-211.83	-24.38	-0.02	211.83	24.38	0.000%
28	12.73	-211.83	-22.08	-12.73	211.83	22.08	0.000%
29	22.38	-211.83	-12.96	-22.38	211.83	12.96	0.000%
30	24.92	-211.83	-0.02	-24.92	211.83	0.02	0.000%
31	20.62	-211.83	11.92	-20.62	211.83	-11.92	0.000%
32	11.25	-211.83	19.58	-11.25	211.83	-19.58	0.000%
33	-0.02	-211.83	23.52	0.02	211.83	-23.52	0.000%
34	-12.72	-211.83	22.08	12.72	211.83	-22.08	0.000%
35	-23.12	-211.83	13.39	23.12	211.83	-13.39	0.000%
36	-24.91	-211.83	0.01	24.91	211.83	-0.01	0.000%
37	-19.87	-211.83	-11.49	19.87	211.83	11.49	0.000%

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	24 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
38	-11.27	-211.83	-19.56	11.27	211.83	19.56	0.000%
39	0.03	-71.96	-20.80	-0.03	71.96	20.80	0.000%
40	10.16	-71.96	-17.59	-10.16	71.96	17.59	0.000%
41	17.39	-71.96	-10.06	-17.39	71.96	10.06	0.000%
42	20.52	-71.96	-0.03	-20.52	71.96	0.03	0.000%
43	18.50	-71.96	10.67	-18.50	71.96	-10.67	0.000%
44	9.30	-71.96	16.18	-9.30	71.96	-16.18	0.000%
45	-0.02	-71.96	19.37	0.02	71.96	-19.37	0.000%
46	-10.15	-71.96	17.59	10.15	71.96	-17.59	0.000%
47	-18.62	-71.96	10.77	18.62	71.96	-10.77	0.000%
48	-20.51	-71.96	0.01	20.51	71.96	-0.01	0.000%
49	-17.27	-71.96	-9.96	17.27	71.96	9.96	0.000%
50	-9.33	-71.96	-16.16	9.33	71.96	16.16	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	6	0.0000001	0.0000001
2	Yes	11	0.0000001	0.00008534
3	Yes	11	0.0000001	0.00006340
4	Yes	11	0.0000001	0.00008548
5	Yes	11	0.0000001	0.00006363
6	Yes	11	0.0000001	0.00008547
7	Yes	11	0.0000001	0.00006372
8	Yes	11	0.0000001	0.00008437
9	Yes	11	0.0000001	0.00006281
10	Yes	11	0.0000001	0.00008476
11	Yes	11	0.0000001	0.00006299
12	Yes	11	0.0000001	0.00008654
13	Yes	11	0.0000001	0.00006446
14	Yes	11	0.0000001	0.00008625
15	Yes	11	0.0000001	0.00006433
16	Yes	11	0.0000001	0.00008541
17	Yes	11	0.0000001	0.00006359
18	Yes	11	0.0000001	0.00008462
19	Yes	11	0.0000001	0.00006290
20	Yes	11	0.0000001	0.00008442
21	Yes	11	0.0000001	0.00006288
22	Yes	11	0.0000001	0.00008570
23	Yes	11	0.0000001	0.00006392
24	Yes	11	0.0000001	0.00008656
25	Yes	11	0.0000001	0.00006446
26	Yes	8	0.0000001	0.00011342
27	Yes	12	0.0000001	0.00006670
28	Yes	12	0.0000001	0.00006650
29	Yes	12	0.0000001	0.00006565
30	Yes	12	0.0000001	0.00006513
31	Yes	12	0.0000001	0.00006620
32	Yes	12	0.0000001	0.00006736
33	Yes	12	0.0000001	0.00006845
34	Yes	12	0.0000001	0.00006831
35	Yes	12	0.0000001	0.00006720
36	Yes	12	0.0000001	0.00006492
37	Yes	12	0.0000001	0.00006401
38	Yes	12	0.0000001	0.00006502

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	25 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

39	Yes	11	0.00000001	0.00006777
40	Yes	11	0.00000001	0.00006761
41	Yes	11	0.00000001	0.00006717
42	Yes	11	0.00000001	0.00006637
43	Yes	11	0.00000001	0.00006732
44	Yes	11	0.00000001	0.00006774
45	Yes	11	0.00000001	0.00006758
46	Yes	11	0.00000001	0.00006744
47	Yes	11	0.00000001	0.00006719
48	Yes	11	0.00000001	0.00006621
49	Yes	11	0.00000001	0.00006703
50	Yes	11	0.00000001	0.00006776

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	256 - 248	5.496	39	0.2104	0.0325
T2	248 - 228	5.139	39	0.2093	0.0328
T3	228 - 208	4.278	47	0.1967	0.0322
T4	208 - 188	3.490	47	0.1728	0.0292
T5	188 - 168	2.809	47	0.1488	0.0248
T6	168 - 148	2.209	47	0.1309	0.0216
T7	148 - 128	1.681	47	0.1115	0.0190
T8	128 - 108	1.231	47	0.0909	0.0163
T9	108 - 88	0.876	47	0.0718	0.0150
T10	88 - 68	0.581	47	0.0565	0.0131
T11	68 - 48	0.351	47	0.0433	0.0113
T12	48 - 28	0.176	47	0.0291	0.0090
T13	28 - 8	0.059	43	0.0143	0.0064

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
256.00	10' Yagi w/ (5) 6' Elements	39	5.496	0.2104	0.0325	318560
250.33	2" Dia 10' Omni	39	5.243	0.2098	0.0327	282238
248.00	2" Dia 10' Omni	39	5.139	0.2093	0.0328	205584
244.67	2" Dia 10' Omni	39	4.991	0.2082	0.0329	154775
243.00	2" Dia 10' Omni	39	4.918	0.2075	0.0329	139151
239.00	2" Dia 10' Omni	47	4.743	0.2055	0.0328	112196
238.00	2" Dia 10' Omni	47	4.700	0.2048	0.0328	107013
180.00	AIR 21 B2A/B4P w/ Mount Pipe	47	2.561	0.1413	0.0234	64339
121.00	VHLP1-23	47	1.098	0.0839	0.0158	53617
118.00	NNVV-65B-R4 w/ Mount Pipe	47	1.044	0.0810	0.0156	60328
110.00	(2) APL866513-42T6	47	0.908	0.0736	0.0152	89145
100.00	TV 65 Antenna	47	0.751	0.0652	0.0143	84157

Maximum Tower Deflections - Design Wind

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	26 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	256 - 248	23.043	2	0.8800	0.1358
T2	248 - 228	21.552	2	0.8757	0.1372
T3	228 - 208	17.943	18	0.8240	0.1345
T4	208 - 188	14.634	18	0.7244	0.1221
T5	188 - 168	11.778	18	0.6242	0.1039
T6	168 - 148	9.258	18	0.5495	0.0903
T7	148 - 128	7.043	18	0.4680	0.0793
T8	128 - 108	5.157	18	0.3814	0.0683
T9	108 - 88	3.666	18	0.3010	0.0629
T10	88 - 68	2.432	18	0.2365	0.0548
T11	68 - 48	1.470	18	0.1811	0.0472
T12	48 - 28	0.734	18	0.1219	0.0377
T13	28 - 8	0.246	11	0.0598	0.0268

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
256.00	10' Yagi w/ (5) 6' Elements	2	23.043	0.8800	0.1358	79725
250.33	2" Dia 10' Omni	2	21.986	0.8776	0.1369	70604
248.00	2" Dia 10' Omni	2	21.552	0.8757	0.1372	51337
244.67	2" Dia 10' Omni	2	20.935	0.8714	0.1374	38335
243.00	2" Dia 10' Omni	2	20.627	0.8686	0.1374	34317
239.00	2" Dia 10' Omni	18	19.895	0.8601	0.1372	27457
238.00	2" Dia 10' Omni	18	19.715	0.8575	0.1370	26150
180.00	AIR 21 B2A/B4P w/ Mount Pipe	18	10.734	0.5928	0.0978	15386
121.00	VHLP1-23	18	4.596	0.3519	0.0661	12786
118.00	NNVV-65B-R4 w/ Mount Pipe	18	4.370	0.3396	0.0654	14377
110.00	(2) APL866513-42T6	18	3.802	0.3084	0.0635	21191
100.00	TV 65 Antenna	18	3.143	0.2734	0.0599	20038

Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load per Bolt K	Ratio Load Allowable	Allowable Ratio	Criteria
T1	256	Leg	A325N	1.0000	8	0.32	53.01	0.006	1	Bolt Tension
		Diagonal	A325N	0.8750	2	0.86	7.83	0.110	1	Member Block Shear
T2	248	Leg	A325N	1.0000	8	2.75	53.01	0.052	1	Bolt Tension
		Diagonal	A325N	0.8750	2	1.59	11.20	0.142	1	Member Block Shear
T3	228	Leg	A325N	1.0000	8	6.52	53.01	0.123	1	Bolt Tension
		Diagonal	A325N	0.8750	2	2.25	11.20	0.201	1	Member Block Shear
T4	208	Leg	A325N	1.0000	8	9.00	53.01	0.170	1	Bolt Tension
		Diagonal	A325N	0.8750	2	1.51	11.20	0.135	1	Member Block Shear
T5	188	Leg	A325N	1.0000	8	11.66	53.01	0.220	1	Bolt Tension
		Diagonal	A325N	0.8750	2	2.82	12.72	0.222	1	Member Block

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 27 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load per Bolt K	Ratio Load Allowable	Allowable Ratio	Criteria
T6	168	Leg Diagonal	A325N A325N	1.0000 0.8750	8 2	15.21 3.14	53.01 13.48	0.287 0.233	1 1	Shear Bolt Tension Member Block Shear
T7	148	Leg Diagonal	A325N A325N	1.0000 0.8750	8 2	18.70 3.66	53.01 13.48	0.353 0.271	1 1	Bolt Tension Member Block Shear
T8	128	Leg Diagonal	A325N A325N	1.0000 0.8750	8 2	21.89 5.41	53.01 22.51	0.413 0.240	1 1	Bolt Tension Member Block Shear
T9	108	Leg Diagonal	A325N A325N	1.2500 0.8750	8 2	26.62 6.69	82.83 18.76	0.321 0.356	1 1	Bolt Tension Member Block Shear
T10	88	Leg Diagonal	A325N A325N	1.2500 0.8750	8 2	31.68 8.15	82.83 24.35	0.382 0.335	1 1	Bolt Tension Bolt Shear
T11	68	Leg Diagonal	A325N A325N	1.2500 0.8750	8 2	36.88 9.22	82.83 24.35	0.445 0.379	1 1	Bolt Tension Bolt Shear
T12	48	Leg Diagonal	A325N A325N	1.2500 0.8750	12 2	27.96 9.84	82.83 24.35	0.338 0.404	1 1	Bolt Tension Bolt Shear
T13	28	Diagonal	A325N	0.6250	3	9.78	12.43	0.787	1	Bolt Shear

Compression Checks

Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	256 - 248	ROHN 3 STD	8.00	4.00	41.3	2.2285	-5.84	88.54	0.066 ¹
T2	248 - 228	ROHN 3 EH	20.00	4.00	K=1.00 42.2	3.0159	-27.55	119.12	0.231 ¹
T3	228 - 208	ROHN 4 EH	20.00	4.00	K=1.00 32.5	4.4074	-61.11	183.59	0.333 ¹
T4	208 - 188	ROHN 5 EH	20.04	5.01	K=1.00 32.7	6.1120	-84.36	254.37	0.332 ¹
T5	188 - 168	ROHN 6 EH	20.03	6.68	K=1.00 36.5	8.4049	-111.14	343.10	0.324 ¹
T6	168 - 148	ROHN 6 EH	20.03	6.68	K=1.00 36.5	8.4049	-143.82	343.10	0.419 ¹
T7	148 - 128	ROHN 6 EH	20.04	6.68	K=1.00 36.5	8.4049	-176.46	343.09	0.514 ¹
T8	128 - 108	ROHN 8 EHS	20.04	10.02	K=1.00 41.2	9.7193	-209.74	386.38	0.543 ¹
T9	108 - 88	ROHN 8 EH	20.04	10.02	K=1.00 41.8	12.7627	-254.64	505.52	0.504 ¹
T10	88 - 68	P10x.5	20.03	10.02	K=1.00 33.1	16.1007	-303.34	668.66	0.454 ¹
T11	68 - 48	P10x.5	20.03	10.02	K=1.00 33.1	16.1007	-353.79	668.66	0.529 ¹
T12	48 - 28	P10x.5	20.04	10.02	K=1.00 33.1	16.1007	-403.71	668.64	0.604 ¹

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job	CT52XC007	Page	28 of 33
	Project	1729061	Date	15:15:01 08/20/18
	Client	ComEx Consultants	Designed by	Ahmet Colakoglu

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	P10x.5	20.05	10.03	33.2 K=1.00	16.1007	-416.45	668.56	0.623 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	256 - 248	L1 3/4x1 3/4x3/16	7.91	3.57	123.6 K=0.99	0.6211	-1.69	9.18	0.184 ¹
T2	248 - 228	L2x2x1/4	7.98	3.56	111.9 K=1.02	0.9380	-3.20	16.89	0.189 ¹
T3	228 - 208	L2x2x1/4	7.92	3.49	110.3 K=1.03	0.9380	-4.63	17.35	0.267 ¹
T4	208 - 188	L2x2x1/4	10.00	4.62	136.7 K=0.96	0.9380	-3.04	11.35	0.268 ¹
T5	188 - 168	L2 1/2x2 1/2x1/4	12.51	5.86	137.8 K=0.96	1.1900	-5.71	14.15	0.403 ¹
T6	168 - 148	L3x3x1/4	14.24	6.74	132.6 K=0.97	1.4400	-6.53	18.49	0.353 ¹
T7	148 - 128	L3x3x1/4	16.09	7.67	147.1 K=0.95	1.4400	-7.32	15.04	0.487 ¹
T8	128 - 108	L4x4x3/8	19.35	9.30	136.5 K=0.96	2.8600	-11.63	34.67	0.335 ¹
T9	108 - 88	L4x4x5/16	21.22	10.25	147.1 K=0.95	2.4000	-13.61	25.07	0.543 ¹
T10	88 - 68	L5x5x3/8	23.04	11.04	130.5 K=0.98	3.6100	-16.30	47.85	0.341 ¹
T11	68 - 48	L5x5x3/8	24.84	11.94	138.9 K=0.96	3.6100	-18.44	42.28	0.436 ¹
T12	48 - 28	L5x5x3/8	26.75	12.91	147.9 K=0.94	3.6100	-19.67	37.29	0.528 ¹
T13	28 - 8	ROHN 3 STD	24.38	12.19	125.7 K=1.00	2.2285	-29.34	31.86	0.921 ¹

¹ P_u / φP_n controls

Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	25.33	12.22	126.0 K=1.00	2.2285	-16.19	31.71	0.511 ¹

¹ P_u / φP_n controls

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 29 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Top Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	256 - 248	L3x3x1/4	6.60	6.31	124.9 K=0.98	1.4400	-0.62	20.53	0.030 ¹

¹ P_u / φP_n controls

Redundant Horizontal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	6.33	5.89	60.7 K=1.00	2.2285	-7.23	59.47	0.122 ¹

¹ P_u / φP_n controls

Redundant Diagonal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	11.52	10.62	109.5 K=1.00	2.2285	-6.57	38.41	0.171 ¹

¹ P_u / φP_n controls

Redundant Hip (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 1.5 STD	6.33	6.33	122.1 K=1.00	0.7995	-0.09	11.82	0.008 ¹

¹ P_u / φP_n controls

Redundant Hip Diagonal (1) Design Data (Compression)

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 30 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Section No.	Elevation ft	Size	L ft	L _u ft	KL/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 1.5 STD	15.13	15.13	291.5 K=1.00	0.7995	-0.07	2.13	0.034 ¹
KL/R > 250 (C) - 268									

¹ P_u / φP_n controls

Inner Bracing Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	KL/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	12.67	12.67	130.6 K=1.00	2.2285	-0.03	29.50	0.001 ¹

¹ P_u / φP_n controls

Tension Checks

Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	KL/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	256 - 248	ROHN 3 STD	8.00	4.00	41.3	2.2285	2.54	100.28	0.025 ¹
T2	248 - 228	ROHN 3 EH	20.00	4.00	42.2	3.0159	21.96	135.72	0.162 ¹
T3	228 - 208	ROHN 4 EH	20.00	4.00	32.5	4.4074	52.14	198.34	0.263 ¹
T4	208 - 188	ROHN 5 EH	20.04	5.01	32.7	6.1120	72.00	275.04	0.262 ¹
T5	188 - 168	ROHN 6 EH	20.03	6.68	36.5	8.4049	93.29	378.22	0.247 ¹
T6	168 - 148	ROHN 6 EH	20.03	6.68	36.5	8.4049	121.68	378.22	0.322 ¹
T7	148 - 128	ROHN 6 EH	20.04	6.68	36.5	8.4049	149.62	378.22	0.396 ¹
T8	128 - 108	ROHN 8 EHS	20.04	10.02	41.2	9.7193	175.08	437.37	0.400 ¹
T9	108 - 88	ROHN 8 EH	20.04	10.02	41.8	12.7627	212.93	574.32	0.371 ¹
T10	88 - 68	P10x.5	20.03	10.02	33.1	16.1007	253.44	724.53	0.350 ¹
T11	68 - 48	P10x.5	20.03	10.02	33.1	16.1007	295.02	724.53	0.407 ¹
T12	48 - 28	P10x.5	20.04	10.02	33.1	16.1007	335.56	724.53	0.463 ¹
T13	28 - 8	P10x.5	20.05	10.03	33.2	16.1007	342.73	724.53	0.473 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	KL/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
-------------	-----------------	------	---------	----------------------	------	----------------------	---------------------	----------------------	---------------------------------

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 31 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	256 - 248	L1 3/4x1 3/4x3/16	7.91	3.57	85.6	0.3252	1.73	15.85	0.109 ¹
T2	248 - 228	L2x2x1/4	7.98	3.56	75.3	0.5160	3.19	25.16	0.127 ¹
T3	228 - 208	L2x2x1/4	7.92	3.49	73.9	0.5160	4.50	25.16	0.179 ¹
T4	208 - 188	L2x2x1/4	10.00	4.62	96.2	0.5160	3.02	25.16	0.120 ¹
T5	188 - 168	L2 1/2x2 1/2x1/4	12.51	5.86	95.6	0.7050	5.64	34.37	0.164 ¹
T6	168 - 148	L3x3x1/4	14.24	6.74	90.3	0.8925	6.28	43.51	0.144 ¹
T7	148 - 128	L3x3x1/4	16.09	7.67	102.3	0.8925	7.31	43.51	0.168 ¹
T8	128 - 108	L4x4x3/8	19.35	9.30	93.3	1.8637	10.82	90.86	0.119 ¹
T9	108 - 88	L4x4x5/16	21.22	10.25	101.7	1.5656	13.37	76.32	0.175 ¹
T10	88 - 68	L5x5x3/8	23.04	11.04	86.9	2.4262	16.08	118.28	0.136 ¹
T11	68 - 48	L5x5x3/8	24.84	11.94	93.8	2.4262	18.04	118.28	0.153 ¹
T12	48 - 28	L5x5x3/8	26.75	12.91	101.3	2.4262	19.27	118.28	0.163 ¹
T13	28 - 8	ROHN 3 STD	24.38	12.19	125.7	2.2285	28.64	100.28	0.286 ¹

¹ P_u / φP_n controls

Horizontal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	25.33	12.22	126.0	2.2285	16.07	100.28	0.160 ¹

¹ P_u / φP_n controls

Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T1	256 - 248	L3x3x1/4	6.60	6.31	81.4	1.4400	0.60	46.66	0.013 ¹

¹ P_u / φP_n controls

Redundant Horizontal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	6.33	5.89	60.7	2.2285	7.23	72.20	0.100 ¹

¹ P_u / φP_n controls

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 32 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Redundant Diagonal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	11.52	10.62	109.5	2.2285	6.57	72.20	0.091 ¹

¹ P_u / φP_n controls

Redundant Hip Diagonal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 1.5 STD	15.13	15.13	291.5	0.7995	0.14	25.90	0.005 ¹

¹ P_u / φP_n controls

Inner Bracing Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u K	φP _n K	Ratio $\frac{P_u}{\phi P_n}$
T13	28 - 8	ROHN 3 STD	12.67	12.67	130.6	2.2285	0.01	100.28	0.000 ¹

¹ P_u / φP_n controls

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	φP _{allow} K	% Capacity	Pass Fail
T1	256 - 248	Leg	ROHN 3 STD	3	-5.84	88.54	6.6	Pass
T2	248 - 228	Leg	ROHN 3 EH	21	-27.55	119.12	23.1	Pass
T3	228 - 208	Leg	ROHN 4 EH	54	-61.11	183.59	33.3	Pass
T4	208 - 188	Leg	ROHN 5 EH	87	-84.36	254.37	33.2	Pass
T5	188 - 168	Leg	ROHN 6 EH	114	-111.14	343.10	32.4	Pass
T6	168 - 148	Leg	ROHN 6 EH	135	-143.82	343.10	41.9	Pass
T7	148 - 128	Leg	ROHN 6 EH	156	-176.46	343.09	51.4	Pass
T8	128 - 108	Leg	ROHN 8 EHS	177	-209.74	386.38	54.3	Pass
T9	108 - 88	Leg	ROHN 8 EH	190	-254.64	505.52	50.4	Pass
T10	88 - 68	Leg	P10x.5	205	-303.34	668.66	45.4	Pass
T11	68 - 48	Leg	P10x.5	220	-353.79	668.66	52.9	Pass
T12	48 - 28	Leg	P10x.5	235	-403.71	668.64	60.4	Pass
T13	28 - 8	Leg	P10x.5	250	-416.45	668.56	62.3	Pass
T1	256 - 248	Diagonal	L1 3/4x1 3/4x3/16	12	-1.69	9.18	18.4	Pass
T2	248 - 228	Diagonal	L2x2x1/4	26	-3.20	16.89	18.9	Pass
T3	228 - 208	Diagonal	L2x2x1/4	59	-4.63	17.35	26.7	Pass
T4	208 - 188	Diagonal	L2x2x1/4	93	-3.04	11.35	26.8	Pass
T5	188 - 168	Diagonal	L2 1/2x2 1/2x1/4	120	-5.71	14.15	40.3	Pass

tnxTower Destek Engineering LLC 1281 Kennestone Circle, Suite 100 Marietta, GA 30066 Phone: 770693-0835 FAX:	Job CT52XC007	Page 33 of 33
	Project 1729061	Date 15:15:01 08/20/18
	Client ComEx Consultants	Designed by Ahmet Colakoglu

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	ϕP_{allow} K	% Capacity	Pass Fail
T6	168 - 148	Diagonal	L3x3x1/4	136	-6.53	18.49	35.3	Pass
T7	148 - 128	Diagonal	L3x3x1/4	157	-7.32	15.04	48.7	Pass
T8	128 - 108	Diagonal	L4x4x3/8	178	-11.63	34.67	33.5	Pass
T9	108 - 88	Diagonal	L4x4x5/16	193	-13.61	25.07	54.3	Pass
T10	88 - 68	Diagonal	L5x5x3/8	208	-16.30	47.85	34.1	Pass
T11	68 - 48	Diagonal	L5x5x3/8	223	-18.44	42.28	43.6	Pass
T12	48 - 28	Diagonal	L5x5x3/8	238	-19.67	37.29	52.8	Pass
T13	28 - 8	Diagonal	ROHN 3 STD	254	-29.34	31.86	92.1	Pass
T13	28 - 8	Horizontal	ROHN 3 STD	253	-16.19	31.71	51.1	Pass
T1	256 - 248	Top Girt	L3x3x1/4	4	-0.62	20.53	3.0	Pass
T13	28 - 8	Redund Horz 1 Bracing	ROHN 3 STD	255	-7.23	59.47	12.2	Pass
T13	28 - 8	Redund Diag 1 Bracing	ROHN 3 STD	275	-6.57	38.41	17.1	Pass
T13	28 - 8	Redund Hip 1 Bracing	ROHN 1.5 STD	278	-0.09	11.82	0.8	Pass
T13	28 - 8	Redund Hip Diagonal 1 Bracing	ROHN 1.5 STD	268	-0.07	2.13	3.4	Pass
T13	28 - 8	Inner Bracing	ROHN 3 STD	281	-0.02	29.50	0.2	Pass
							Summary	
						Leg (T13)	62.3	Pass
						Diagonal (T13)	92.1	Pass
						Horizontal (T13)	51.1	Pass
						Top Girt (T1)	3.0	Pass
						Redund Horz 1 Bracing (T13)	12.2	Pass
						Redund Diag 1 Bracing (T13)	17.1	Pass
						Redund Hip 1 Bracing (T13)	0.8	Pass
						Redund Hip Diagonal 1 Bracing (T13)	3.4	Pass
						Inner Bracing (T13)	0.2	Pass
						Bolt Checks	78.7	Pass
						RATING =	92.1	Pass



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT52XC007

Bridgeport West
623 Pine Street
Bridgeport, CT 06605

May 22, 2018

EBI Project Number: 6218003931

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	12.20 %



May 22, 2018

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT52XC007 – Bridgeport West**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **623 Pine Street, Bridgeport, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS), 2500 MHz (BRS), 11 GHz microwave and 23 GHz microwave bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **623 Pine Street, Bridgeport, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) 1 microwave backhaul channel (23 GHz) was considered for sectors A & B. 1 microwave backhaul channel (11 GHz) was considered for sector C. These channels have a transmit power of 1 Watt per channel.
- 7) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 8) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antennas used in this modeling are the **Commscope NNVV-65B-R4** and the **Nokia AAHC** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands and the **Andrew VHL P1-23** and **Andrew VHL P2.5-11** parabolic dishes for the microwave backhaul. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 10) The antenna mounting height centerlines of the proposed antennas are **118 feet** above ground level (AGL) for **Sector A**, **118 feet** above ground level (AGL) for **Sector B** and **118 feet** above ground level (AGL) for Sector C.
The antenna mounting height centerlines of the proposed microwave dishes are **121 feet** above ground level (AGL) for **Sector A**, **121feet** above ground level (AGL) for **Sector B** and **121 feet** above ground level (AGL) for Sector C.
- 11) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.

SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4	Make / Model:	Commscope NNVV-65B-R4
Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd	Gain:	12.75 / 15.05 dBd
Height (AGL):	118 feet	Height (AGL):	118 feet	Height (AGL):	118 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	6,248.42	ERP (W):	6,248.42	ERP (W):	6,248.42
Antenna A1 MPE%	2.04 %	Antenna B1 MPE%	2.04 %	Antenna C1 MPE%	2.04 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC	Make / Model:	Nokia AAHC
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd
Height (AGL):	118 feet	Height (AGL):	118 feet	Height (AGL):	118 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	5,118.23	ERP (W):	5,118.23	ERP (W):	5,118.23
Antenna A2 MPE%	1.47 %	Antenna B2 MPE%	1.47 %	Antenna C2 MPE%	1.47 %

Microwave Backhaul Data

Antenna Type:	Gain (dBd)	Height (feet AGL):	Frequency Bands	Channel Count	Total TX Power(W)	ERP (W)	MPE %	Sector
Andrew VHL P1-23	33.15 dBd	121	23 GHz	1	1	2,065.38	0.05	A
Andrew VHL P1-23	33.15 dBd	121	23 GHz	1	1	2,065.38	0.05	B
Andrew VHL P2.5-11	35.35 dBd	121	11 GHz	1	1	3,427.68	0.09	C

Site Composite MPE%	
Carrier	MPE%
SPRINT – Sector C	3.60 %
Clearwire	0.14 %
Verizon Wireless	3.44 %
T-Mobile	2.16 %
Unknown	1.58 %
MetroPCS	1.28 %
Site Total MPE %:	12.20 %

SPRINT Sector A Total:	3.56 %
SPRINT Sector B Total:	3.56 %
SPRINT Sector C Total:	3.60 %
Site Total:	12.20 %



Sprint Max Power Values (Sector C)

SPRINT _ Frequency Band / Technology (Sector C)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	376.73	118	1.08	850 MHz	567	0.19%
Sprint 850 MHz LTE	2	376.73	118	2.16	850 MHz	567	0.38%
Sprint 1900 MHz (PCS) CDMA	5	511.82	118	7.33	1900 MHz (PCS)	1000	0.73%
Sprint 1900 MHz (PCS) LTE	2	1,279.56	118	7.33	1900 MHz (PCS)	1000	0.73%
Sprint 2500 MHz (BRS) LTE	8	639.78	118	14.67	2500 MHz (BRS)	1000	1.47%
Sprint 11 GHz Microwave	1	3,427.68	121	0.93	11 GHz	1000	0.09%
						Total*:	3.60%

*NOTE: Totals may vary by 0.01% due to summing of remainders



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	3.56 %
Sector B:	3.56 %
Sector C:	3.60 %
SPRINT Maximum Total (Sector C):	3.60 %
Site Total:	12.20 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **12.20 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



City Of Bridgeport

City Of Bridgeport
 325 CONGRESS STREET
 BRIDGEPORT
 (203) - 576 - 7241 (ASSESS)

Bill Information



Taxpayer Information			
Bill #	2013-1-0015965 (REAL ESTATE)	Town Benefit	
Unique ID	0307--25-----	Elderly Benefit	
District/Flag			
Name	KNAPP ANDREW & LILLIAN &	Assessment	250,987
Care of/DBA	ROBERT KNAPP (SURV OF THEM)	Exemption	0
Address		Net	250,987
Detail Information	623 PINE ST		
Volume/Page		Mill Rate	Town 42.198

Bill Information As of 06/19/2018						
Installment	Due Date	Town/City	District	Other	Total Due	
Inst # 1	07/01/2014	5,295.58				
Inst # 2	01/01/2015	5,295.58				
Inst # 3						
Inst # 4						
Total Adjustments		0.00				
Total Installment + Adjustment		10,591.16				
Total Payments		10,591.16				
					Tax/ Princ/ Bond Due	0.00
					Interest Due	0.00
					Lien Due	0.00
					Fee Due	0.00
					Total Due Now	0.00
					Balance Due	0.00

*** Note: This is not a tax form, please contact your financial advisor for information regarding tax reporting. ***

Payment History						
Payment Date	Type	Tax/Principal/Bond	Interest	Lien	Fee	Total
12/31/2014	PAY	5,295.58	0.00	0.00	0.00	5,295.58
08/01/2014	PAY	5,295.58	0.00	0.00	0.00	5,295.58

*** Total payments made to taxes in 2017 \$0.00

BUILDING DEPARTMENT

City of Bridgeport, Connecticut

BUILDING PERMIT

Nº 3220



OCT 26 2010 20


Permission is hereby granted to Andrew Knapp
to erect Telecommunications
Located at 623 Pine St.

This permit is granted on condition that all city, state and federal rules, regulations and laws are complied with. A certificate of occupancy must be granted before the permitted work can be used or occupied. This permit expires six (6) months from date of issue if work is not commenced.

CALL OFFICE WHEN WORK IS STARTED - 203-576-7225

Special Conditions: _____

BRUCE A. NELSON, Deputy Building Official



PETER J. PAAJANEN, Building Official


ORIGIN ID:CBZA (973) 477-8032
STEVE SOFMAN
CHARLES CHERUNDOLO CONSULTING
1280 ROUTE 46 WEST
SUITE 9
PARISPPANY, NJ 07054
UNITED STATES US

SHP DATE: 23AUG18
ACTWGT: 1.00 LB
CAD: 111040781IN/ET4040
BILL SENDER

TO ANDREW KNAPP
RADIO COMMUNICATIONS CORP
24 ROCKDALE RD

WEST HAVEN CT 06516
(203) 933-2432 REF: CT53XC007 CSC REFLING
NAV DEPT
PO


552J1.03309/DCA5



TRK# 7730 4684 6880
0201

TUE - 28 AUG 4:30P
EXPRESS SAVER

SE EFBA 06516
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.


Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID:GBZA (973) 477-8032
STEVE SOFMAN
CHARLES CHERUNDOLLO CONSULTING
1280 ROUTE 46 WEST
SUITE 9
PARLISSANY, NJ 07054
UNITED STATES US

SHIP DATE: 23AUG18
ACTWGT: 1.00 LB
CAD: 111040781/NET/4040
BILL SENDER

TO **MAYOR GANIM**
CITY OF BRIDGEPORT
999 BROAD ST
MARGOARET E MORTON GOV CENTER
BRIDGEPORT CT 06604
(203) 576-7201 REF: CT52X007 CSC REFLING
INV/ DEPT
PO


552J1/3309/DCA5



TRK# 7730 4686 8130
0201

TUE - 28 AUG 4:30P
EXPRESS SAVER

SE BCCA
06604
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.


Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID: CEZA (973) 477-8032
STEVE SOFMAN
CHARLES CHERUNDOLLO CONSULTING
1280 ROUTE 46 WEST
SUITE 9
PARSONS, NJ 07054
UNITED STATES US

SHIP DATE: 23AUG18
ACTWGT: 1.00 LB
CAD: 11104078/IN/ET/4040
BILL SENDER

TO THOMAS GILL
CITY OF BRIDGEPORT
999 BROAD ST
MARGOARET E MORTON GOV CENTER
BRIDGEPORT CT 06604
(203) 576-7201
REF: CTSX0007 CSC REFLING
PO DEPT:

552J113309/DCA5



TRK# 7730 4687 6919
TUE - 28 AUG 4:30P
EXPRESS SAVER

SE BCCA
06604
CT-US BDL

After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.