




New Cingular Wireless PCS, LLC
500 Enterprise Drive
Rocky Hill, Connecticut 06067-3900
Phone: (860) 463-5511
Fax: (860) 513-7190

Douglas L. Culp
Real Estate Consultant

HAND DELIVERED

July 7, 2011

Ms. Linda Roberts
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, Connecticut 06051



Re: New Cingular Wireless PCS, LLC notice of intent to modify an existing telecommunications facility located 761 Federal Road Brookfield, CT (CL&P).

Dear Ms. Roberts:

In order to accommodate technological changes, implement Uniform Mobile Telecommunications System ("UMTS") and/or Long Term Evolution ("LTE") capabilities, and enhance system performance in the State of Connecticut, New Cingular Wireless PCS, LLC ("AT&T") plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the chief elected official of the municipality in which the affected cell site is located.

UMTS technology offers services to mobile computer and phone users anywhere in the world. Based on the Global System for Mobile ("GSM") communication standard, UMTS is the planned worldwide standard for mobile users. UMTS, fully implemented, gives computer and phone users high-speed access to the Internet as they travel. They have the same capabilities even when they roam, through both terrestrial wireless and satellite transmissions.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in AT&T's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

The changes to the facility do not constitute modifications as defined in Connecticut General


Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will be unaffected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound other than some enlarged equipment pads as may be noted in the attachments.
3. The proposed changes will not increase the noise level at the existing facility by six decibels or more.
4. Radio frequency power density may increase due to use of one or more GSM channel for UMTS transmissions. Moreover, LTE will utilize additional radio frequencies newly-licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons, New Cingular Wireless respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (860) 463-5511 with questions concerning this matter. Thank you for your consideration.

Sincerely,



Douglas L. Culp
Real Estate Consultant

Attachments

NEW CINGULAR WIRELESS PCS, LLC
Equipment Modification

761 Federal Road Brookfield, CT
Site Number CT2185
Exempt Modification

Tower Owner/Manager: CL&P

Equipment configuration: Power Mount

Current and/or approved: Three PowerWave P7770 antennas @ 97 ft
Six PowerWave TMA's @ 97 ft
Nine runs 1 ¼ inch coax to 97 ft
Equipment Shelter

Planned Modifications: Retain existing PowerWave P7770 Antenna's and TMA's @ 97 ft
Retain all Coax Cabling
Install six runs of 1 ¼ inch coax to 97 ft
Install three PowerWave Twin BP TMA's TT19-08BP111-001 @ 97 ft
Install three PowerWave P65-16 antennas or equivalent @ 97 ft

Power Density:

Worst-case calculations for existing wireless operations at the site, using standard parameters for other carriers, indicate a radio frequency electromagnetic radiation power density, measured at ground level beside the Tower, of approximately 41.6 % of the standard adopted by the FCC. As depicted in the second table below, the total radio frequency electromagnetic radiation power density following proposed modifications would be approximately 44.2 % of the standard.

Existing

Other Users							12.01
AT&T UMTS	97	1900 Band	1	500	0.0191	1.0000	1.91
AT&T UMTS	97	800 Band	2	500	0.0382	0.5867	6.51
AT&T GSM	97	800Band	11	296	0.1244	0.5867	21.21
Total							41.6%

* Data for other users are from Siting Council records.

Proposed

Company	Centerline Ht (feet)	Frequency (MHz)	Number of Channels	Power Per Channel (Watts)	Power Density (mW/cm ²)	Standard Limits (mW/cm ²)	Percent of Limit
Other Users							12.01
AT&T UMTS	97	800 Band	1	500	0.0191	0.5867	3.26
AT&T UMTS	97	1900 Band	2	500	0.0382	1.0000	3.82
AT&T GSM	97	880 - 894	11	296	0.1244	0.5867	21.21
AT&T LTE	97	740 - 746	1	500	0.0191	0.4933	3.87
Total							44.2%

* Data for other users are from Siting Council records.

Structural information:

The attached structural analysis demonstrates that the monopole and foundation have adequate structural capacity to accommodate the proposed modifications. (Centek dated 6-29-11).



CT2185

BROOKFIELD

CL&P STRUCT. NO.: 2683

761 FEDERAL ROAD

BROOKFIELD, CT 06804

SITE DIRECTIONS	FROM	800 INTERSTATE DRIVE EAST ARLING, CONNECTICUT	TO	781 FEDERAL ROAD BROOKFIELD, CONNECTICUT
1. Drive East on Interstate 84				
2. Turn left onto Capital Blvd				0.4 mi.
3. Turn left onto Capital Blvd				0.5 mi.
4. Turn right onto Capital Blvd				0.6 mi.
5. Turn right onto Capital Blvd				0.7 mi.
6. Turn right onto Capital Blvd				0.8 mi.
7. Turn right onto Capital Blvd				0.9 mi.
8. Turn right onto Capital Blvd				1.0 mi.
9. Turn right onto Capital Blvd				1.1 mi.
10. Turn right onto Capital Blvd				1.2 mi.
11. Turn right onto Capital Blvd				1.3 mi.
12. Turn right onto Capital Blvd				1.4 mi.
13. Turn right onto Capital Blvd				1.5 mi.
14. Turn right onto Capital Blvd				1.6 mi.
15. Turn right onto Capital Blvd				1.7 mi.
16. Turn right onto Capital Blvd				1.8 mi.
17. Turn right onto Capital Blvd				1.9 mi.
18. Turn right onto Capital Blvd				2.0 mi.
19. Turn right onto Capital Blvd				2.1 mi.
20. Turn right onto Capital Blvd				2.2 mi.
21. Turn right onto Capital Blvd				2.3 mi.
22. Turn right onto Capital Blvd				2.4 mi.
23. Turn right onto Capital Blvd				2.5 mi.
24. Turn right onto Capital Blvd				2.6 mi.
25. Turn right onto Capital Blvd				2.7 mi.
26. Turn right onto Capital Blvd				2.8 mi.
27. Turn right onto Capital Blvd				2.9 mi.
28. Turn right onto Capital Blvd				3.0 mi.
29. Turn right onto Capital Blvd				3.1 mi.
30. Turn right onto Capital Blvd				3.2 mi.
31. Turn right onto Capital Blvd				3.3 mi.
32. Turn right onto Capital Blvd				3.4 mi.
33. Turn right onto Capital Blvd				3.5 mi.
34. Turn right onto Capital Blvd				3.6 mi.
35. Turn right onto Capital Blvd				3.7 mi.
36. Turn right onto Capital Blvd				3.8 mi.
37. Turn right onto Capital Blvd				3.9 mi.
38. Turn right onto Capital Blvd				4.0 mi.
39. Turn right onto Capital Blvd				4.1 mi.
40. Turn right onto Capital Blvd				4.2 mi.
41. Turn right onto Capital Blvd				4.3 mi.
42. Turn right onto Capital Blvd				4.4 mi.
43. Turn right onto Capital Blvd				4.5 mi.
44. Turn right onto Capital Blvd				4.6 mi.
45. Turn right onto Capital Blvd				4.7 mi.
46. Turn right onto Capital Blvd				4.8 mi.
47. Turn right onto Capital Blvd				4.9 mi.
48. Turn right onto Capital Blvd				5.0 mi.
49. Turn right onto Capital Blvd				5.1 mi.
50. Turn right onto Capital Blvd				5.2 mi.
51. Turn right onto Capital Blvd				5.3 mi.
52. Turn right onto Capital Blvd				5.4 mi.
53. Turn right onto Capital Blvd				5.5 mi.
54. Turn right onto Capital Blvd				5.6 mi.
55. Turn right onto Capital Blvd				5.7 mi.
56. Turn right onto Capital Blvd				5.8 mi.
57. Turn right onto Capital Blvd				5.9 mi.
58. Turn right onto Capital Blvd				6.0 mi.
59. Turn right onto Capital Blvd				6.1 mi.
60. Turn right onto Capital Blvd				6.2 mi.
61. Turn right onto Capital Blvd				6.3 mi.
62. Turn right onto Capital Blvd				6.4 mi.
63. Turn right onto Capital Blvd				6.5 mi.
64. Turn right onto Capital Blvd				6.6 mi.
65. Turn right onto Capital Blvd				6.7 mi.
66. Turn right onto Capital Blvd				6.8 mi.
67. Turn right onto Capital Blvd				6.9 mi.
68. Turn right onto Capital Blvd				7.0 mi.
69. Turn right onto Capital Blvd				7.1 mi.
70. Turn right onto Capital Blvd				7.2 mi.
71. Turn right onto Capital Blvd				7.3 mi.
72. Turn right onto Capital Blvd				7.4 mi.
73. Turn right onto Capital Blvd				7.5 mi.
74. Turn right onto Capital Blvd				7.6 mi.
75. Turn right onto Capital Blvd				7.7 mi.
76. Turn right onto Capital Blvd				7.8 mi.
77. Turn right onto Capital Blvd				7.9 mi.
78. Turn right onto Capital Blvd				8.0 mi.
79. Turn right onto Capital Blvd				8.1 mi.
80. Turn right onto Capital Blvd				8.2 mi.
81. Turn right onto Capital Blvd				8.3 mi.
82. Turn right onto Capital Blvd				8.4 mi.
83. Turn right onto Capital Blvd				8.5 mi.
84. Turn right onto Capital Blvd				8.6 mi.
85. Turn right onto Capital Blvd				8.7 mi.
86. Turn right onto Capital Blvd				8.8 mi.
87. Turn right onto Capital Blvd				8.9 mi.
88. Turn right onto Capital Blvd				9.0 mi.
89. Turn right onto Capital Blvd				9.1 mi.
90. Turn right onto Capital Blvd				9.2 mi.
91. Turn right onto Capital Blvd				9.3 mi.
92. Turn right onto Capital Blvd				9.4 mi.
93. Turn right onto Capital Blvd				9.5 mi.
94. Turn right onto Capital Blvd				9.6 mi.
95. Turn right onto Capital Blvd				9.7 mi.
96. Turn right onto Capital Blvd				9.8 mi.
97. Turn right onto Capital Blvd				9.9 mi.
98. Turn right onto Capital Blvd				10.0 mi.
99. Turn right onto Capital Blvd				10.1 mi.
100. Turn right onto Capital Blvd				10.2 mi.
101. Turn right onto Capital Blvd				10.3 mi.
102. Turn right onto Capital Blvd				10.4 mi.
103. Turn right onto Capital Blvd				10.5 mi.
104. Turn right onto Capital Blvd				10.6 mi.
105. Turn right onto Capital Blvd				10.7 mi.
106. Turn right onto Capital Blvd				10.8 mi.
107. Turn right onto Capital Blvd				10.9 mi.
108. Turn right onto Capital Blvd				11.0 mi.
109. Turn right onto Capital Blvd				11.1 mi.
110. Turn right onto Capital Blvd				11.2 mi.
111. Turn right onto Capital Blvd				11.3 mi.
112. Turn right onto Capital Blvd				11.4 mi.
113. Turn right onto Capital Blvd				11.5 mi.
114. Turn right onto Capital Blvd				11.6 mi.
115. Turn right onto Capital Blvd				11.7 mi.
116. Turn right onto Capital Blvd				11.8 mi.
117. Turn right onto Capital Blvd				11.9 mi.
118. Turn right onto Capital Blvd				12.0 mi.
119. Turn right onto Capital Blvd				12.1 mi.
120. Turn right onto Capital Blvd				12.2 mi.
121. Turn right onto Capital Blvd				12.3 mi.
122. Turn right onto Capital Blvd				12.4 mi.
123. Turn right onto Capital Blvd				12.5 mi.
124. Turn right onto Capital Blvd				12.6 mi.
125. Turn right onto Capital Blvd				12.7 mi.
126. Turn right onto Capital Blvd				12.8 mi.
127. Turn right onto Capital Blvd				12.9 mi.
128. Turn right onto Capital Blvd				13.0 mi.
129. Turn right onto Capital Blvd				13.1 mi.
130. Turn right onto Capital Blvd				13.2 mi.
131. Turn right onto Capital Blvd				13.3 mi.
132. Turn right onto Capital Blvd				13.4 mi.
133. Turn right onto Capital Blvd				13.5 mi.
134. Turn right onto Capital Blvd				13.6 mi.
135. Turn right onto Capital Blvd				13.7 mi.
136. Turn right onto Capital Blvd				13.8 mi.
137. Turn right onto Capital Blvd				13.9 mi.
138. Turn right onto Capital Blvd				14.0 mi.
139. Turn right onto Capital Blvd				14.1 mi.
140. Turn right onto Capital Blvd				14.2 mi.
141. Turn right onto Capital Blvd				14.3 mi.
142. Turn right onto Capital Blvd				14.4 mi.
143. Turn right onto Capital Blvd				14.5 mi.
144. Turn right onto Capital Blvd				14.6 mi.
145. Turn right onto Capital Blvd				14.7 mi.
146. Turn right onto Capital Blvd				14.8 mi.
147. Turn right onto Capital Blvd				14.9 mi.
148. Turn right onto Capital Blvd				15.0 mi.
149. Turn right onto Capital Blvd				15.1 mi.
150. Turn right onto Capital Blvd				15.2 mi.
151. Turn right onto Capital Blvd				15.3 mi.
152. Turn right onto Capital Blvd				15.4 mi.
153. Turn right onto Capital Blvd				15.5 mi.
154. Turn right onto Capital Blvd				15.6 mi.
155. Turn right onto Capital Blvd				15.7 mi.
156. Turn right onto Capital Blvd				15.8 mi.
157. Turn right onto Capital Blvd				15.9 mi.
158. Turn right onto Capital Blvd				16.0 mi.
159. Turn right onto Capital Blvd				16.1 mi.
160. Turn right onto Capital Blvd				16.2 mi.
161. Turn right onto Capital Blvd				16.3 mi.
162. Turn right onto Capital Blvd				16.4 mi.
163. Turn right onto Capital Blvd				16.5 mi.
164. Turn right onto Capital Blvd				16.6 mi.
165. Turn right onto Capital Blvd				16.7 mi.
166. Turn right onto Capital Blvd				16.8 mi.
167. Turn right onto Capital Blvd				16.9 mi.
168. Turn right onto Capital Blvd				17.0 mi.
169. Turn right onto Capital Blvd				17.1 mi.
170. Turn right onto Capital Blvd				17.2 mi.
171. Turn right onto Capital Blvd				17.3 mi.
172. Turn right onto Capital Blvd				17.4 mi.
173. Turn right onto Capital Blvd				17.5 mi.
174. Turn right onto Capital Blvd				17.6 mi.
175. Turn right onto Capital Blvd				17.7 mi.
176. Turn right onto Capital Blvd				17.8 mi.
177. Turn right onto Capital Blvd				17.9 mi.
178. Turn right onto Capital Blvd				18.0 mi.
179. Turn right onto Capital Blvd				18.1 mi.
180. Turn right onto Capital Blvd				18.2 mi.
181. Turn right onto Capital Blvd				18.3 mi.
182. Turn right onto Capital Blvd				18.4 mi.
183. Turn right onto Capital Blvd				18.5 mi.
184. Turn right onto Capital Blvd				18.6 mi.
185. Turn right onto Capital Blvd				18.7 mi.
186. Turn right onto Capital Blvd				18.8 mi.
187. Turn right onto Capital Blvd				18.9 mi.
188. Turn right onto Capital Blvd				19.0 mi.
189. Turn right onto Capital Blvd				19.1 mi.
190. Turn right onto Capital Blvd				19.2 mi.
191. Turn right onto Capital Blvd				19.3 mi.
192. Turn right onto Capital Blvd				19.4 mi.
193. Turn right onto Capital Blvd				19.5 mi.
194. Turn right onto Capital Blvd				19.6 mi.
195. Turn right onto Capital Blvd				19.7 mi.
196. Turn right onto Capital Blvd				19.8 mi.
197. Turn right onto Capital Blvd				19.9 mi.
198. Turn right onto Capital Blvd				20.0 mi.
199. Turn right onto Capital Blvd				20.1 mi.
200. Turn right onto Capital Blvd				20.2 mi.
201. Turn right onto Capital Blvd				20.3 mi.
202. Turn right onto Capital Blvd				20.4 mi.
203. Turn right onto Capital Blvd				20.5 mi.
204. Turn right onto Capital Blvd				20.6 mi.
205. Turn right onto Capital Blvd				20.7 mi.
206. Turn right onto Capital Blvd				20.8 mi.
207. Turn right onto Capital Blvd				20.9 mi.
208. Turn right onto Capital Blvd				21.0 mi.
209. Turn right onto Capital Blvd				21.1 mi.
210. Turn right onto Capital Blvd				21.2 mi.
211. Turn right onto Capital Blvd				21.3 mi.
212. Turn right onto Capital Blvd				21.4 mi.
213. Turn right onto Capital Blvd				21.5 mi.
214. Turn right onto Capital Blvd				21.6 mi.
215. Turn right onto Capital Blvd				21.7 mi.
216. Turn right onto Capital Blvd				21.8 mi.
217. Turn right onto Capital Blvd				21.9 mi.
218. Turn right onto Capital Blvd				22.0 mi.
219. Turn right onto Capital Blvd				22.1 mi.
220. Turn right onto Capital Blvd				22.2 mi.
221. Turn right onto Capital Blvd				22.3 mi.
222. Turn right onto Capital Blvd				22.4 mi.
223. Turn right onto Capital Blvd				22.5 mi.
224. Turn right onto Capital Blvd				22.6 mi.
225. Turn right onto Capital Blvd				22.7 mi.
226. Turn right onto Capital Blvd				22.8 mi.
227. Turn right onto Capital Blvd				22.9 mi.
228. Turn right onto Capital Blvd				23.0 mi.
229. Turn right onto Capital Blvd				23.1 mi.
230. Turn right onto Capital Blvd				23.2 mi.
231. Turn right onto Capital Blvd				23.3 mi.
232. Turn right onto Capital Blvd				23.4 mi.
233. Turn right onto Capital Blvd				23.5 mi.
234. Turn right onto Capital Blvd				23.6 mi.
235. Turn right onto Capital Blvd				23.7 mi.
236. Turn right onto Capital Blvd				23.8 mi.
237. Turn right onto Capital Blvd				23.9 mi.
238. Turn right onto Capital Blvd				24.0 mi.
239. Turn right onto Capital Blvd				24.1 mi.
240. Turn right onto Capital Blvd				24.2 mi.
241. Turn right onto Capital Blvd				24.3 mi.
242. Turn right onto Capital Blvd				24.4 mi.
243. Turn right onto Capital Blvd				24.5 mi.
244. Turn right onto Capital Blvd				24.6 mi.
245. Turn right onto Capital Blvd				24.7 mi.
246. Turn right onto Capital Blvd				24.8 mi.
247. Turn right onto Capital Blvd				24.9 mi.
248. Turn right onto Capital Blvd				25.0 mi.
249. Turn right onto Capital Blvd				25.1 mi.
250. Turn right onto Capital Blvd				25.2 mi.
251. Turn right onto Capital Blvd				25.3 mi.
252. Turn right onto Capital Blvd				25.4 mi.
253. Turn right onto Capital Blvd				25.5 mi.
254. Turn right onto Capital Blvd				25.6 mi.
255. Turn right onto Capital Blvd				25.7 mi.
256. Turn right onto Capital Blvd				25.8 mi.
257. Turn right onto Capital Blvd				25.9 mi.
258. Turn right onto Capital Blvd				26.0 mi.
259. Turn right onto Capital Blvd				26.1 mi.
260. Turn right onto Capital Blvd				26.2 mi.
261. Turn right onto Capital Blvd				26.3 mi.
262. Turn right onto Capital Blvd				26.4 mi.
263. Turn right onto Capital Blvd				26.5 mi.
264. Turn right onto Capital Blvd				26.6 mi.
265. Turn right onto Capital Blvd				26.7 mi.
266. Turn right onto Capital Blvd				26.8 mi.
267. Turn right onto Capital Blvd				26.9 mi.
268. Turn right onto Capital Blvd				27.0 mi.
269. Turn right onto Capital Blvd				27.1 mi.
270. Turn right onto Capital Blvd				27.2 mi.
271. Turn right onto Capital Blvd				27.3 mi.
272. Turn right onto Capital Blvd				27.4 mi.
273. Turn right onto Capital Blvd				27.5 mi.
274. Turn right onto Capital Blvd				27.6 mi.
275. Turn right onto Capital Blvd				27.7 mi.
276. Turn right onto Capital Blvd				27.8 mi.
277. Turn right onto Capital Blvd				27.9 mi.
278. Turn right onto Capital Blvd				28.0 mi.
279. Turn right onto Capital Blvd				28.1 mi.
280. Turn right onto Capital Blvd				28.2 mi.
281. Turn right onto Capital Blvd				28.3 mi.
282. Turn right onto Capital Blvd				28.4 mi.
283. Turn right onto Capital Blvd				28.5 mi.
284. Turn right onto Capital Blvd				28.6 mi.
285. Turn right onto Capital Blvd				28.7 mi.
286. Turn right onto Capital Blvd				28.8 mi.
287. Turn right onto Capital Blvd				28.9 mi.
288. Turn right onto Capital Blvd				29.0 mi.
289. Turn right onto Capital Blvd				29.1 mi.
290. Turn right onto Capital Blvd				29.2 mi.
291. Turn right onto Capital Blvd				29.3 mi.
292. Turn right onto Capital Blvd				29.4 mi.
293. Turn right onto Capital Blvd				29.5 mi.
294. Turn right onto Capital Blvd				29.6 mi.
295. Turn right onto Capital Blvd				29.7 mi.
296. Turn right onto Capital Blvd				29.8 mi.
297. Turn right onto Capital Blvd				29.9 mi.
298. Turn right onto Capital Blvd				30.0 mi.
299. Turn right onto Capital Blvd				30.1 mi.
300. Turn right onto Capital Blvd				30.2 mi.
301. Turn right onto Capital Blvd				30.3 mi.
302. Turn right onto Capital Blvd				30.4 mi.
303. Turn right onto Capital Blvd				30.5 mi.
304. Turn right onto Capital Blvd				30.6 mi.
305. Turn right onto Capital Blvd				30.7 mi.
306. Turn right onto Capital Blvd				30.8 mi.
307. Turn right onto Capital Blvd				30.9 mi.
308. Turn right onto Capital Blvd				31.0 mi.
309. Turn right onto Capital Blvd				31.1 mi.
310. Turn right onto Capital Blvd				31.2 mi.
311. Turn right onto Capital Blvd				31.3 mi.
312. Turn right onto Capital Blvd				31.4 mi.
313. Turn right onto Capital Blvd				31.5 mi.

GENERAL NOTES

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE 2000 INTERNATIONAL BUILDING CODE AS AMENDED BY THE 2000 CONNECTICUT SUPPLEMENT, 2002 SUPPLEMENT, 2003 SUPPLEMENT, 2006 SUPPLEMENT, 2009 SUPPLEMENT, STEEL, ALUMINUM, WOOD, GLASS, PLASTER, CONCRETE, MASONRY, MECHANICAL, ELECTRICAL, PLUMBING, AND MECHANICAL, AND 2009 INTERNATIONAL CODES AND LOCAL CODES.
2. THE CONTRACTOR SHALL OBTAIN RECORD RING, ELECTRICAL, MECHANICAL, PLUMBING, AND RECORD DRAWINGS FROM THE FIELD POSITION POINT ARE PROVIDED BY SITE OWNER AS EARLY AS POSSIBLE. THE CONTRACTOR SHALL FIELD CHECK THESE RECORD DRAWINGS. THE CONTRACTOR SHALL FIELD CHECK THESE RECORD DRAWINGS IMMEDIATELY AFTER THE ENGINEER AND CONSULTANT SHALL HAVE ANY AFFICTED WORK.
3. CONTRACTOR SHALL REVIEW ALL DRAWINGS AND SPECIFICATIONS IN ALL WORK SHOWN IN THE SET OF DRAWINGS. THE COORDINATE ALL WORK SHOWN IN THE SET OF DRAWINGS. THE CONTRACTOR SHALL SUBMIT A COMPLETE SET OF DRAWINGS TO ALL CONTRACTORS SHALL EXAMINE ALL THE DRAWINGS AND SPECIFICATIONS TO ALL INFORMATION THAT AFFECTS THEIR WORK.
4. CONTRACTOR SHALL PROVIDE A COMPLETE BUILD-OUT WITH ALL MATERIALS AND FINISHES. THE CONTRACTOR SHALL PROVIDE AND PROVIDE ALL ITEMS AS SHOWN OR INDICATED ON THE DRAWINGS OR IN THE WRITTEN SPECIFICATIONS.
5. CONTRACTOR SHALL FURNISH ALL MATERIAL, LABOR AND EQUIPMENT FOR THE ENTIRE PROJECT. THE CONTRACTOR SHALL PROVIDE A COMPLETED JOB ALL IN ACCORDANCE WITH LOCAL AND STATE SPECIFICATIONS AND ALL OTHER AUTHORITIES HAVING JURISDICTION OVER THE WORK.
6. CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND ALL FEES REQUIRED FOR THE GENERAL CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL PERMITS SHALL BE PAID FOR BY THE RESPECTIVE SUBCONTRACTORS.
7. CONTRACTOR SHALL MAINTAIN A CURRENT SET OF DRAWINGS AND NEW DRAWINGS ON SITE AT ALL TIMES AND INSURE DISTRIBUTION OF NEW DRAWINGS TO ALL SUBCONTRACTORS. THE CONTRACTOR SHALL AS SOON AS THEY ARE MADE AVAILABLE ALL OLD DRAWINGS SHALL BE DESTROYED. THE CONTRACTOR SHALL THINGS FROM THE CONTRACT AREA TO THE OWNER. OWNER, COMPLETION OF PROJECT.
8. LOCATION OF EQUIPMENT, AND WORK SUPPLIED BY OTHERS THAT IS DETERMINED BY THE CONTRACTOR SHALL BE THE CONTRACTOR'S RESPONSIBILITY AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
9. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
10. DRAWINGS INDICATE THE MINIMUM STANDARDS, BUT IF ANY WORK IS REQUIRED TO BE SUBSTANDARD TO ANY STANDARDS, THE CONTRACTOR SHALL INCLUDE IN HIS WORK AND SHALL EXECUTE THE WORK IN ACCORDANCE WITH THE MINIMUM STANDARDS, THE CODES, RULES OR REGULATIONS WITH NO MODIFICATIONS, ETC.
11. ALL UTILITY WORK SHALL BE IN ACCORDANCE WITH LOCAL UTILITY COMPANY REQUIREMENTS AND SPECIFICATIONS.
12. ALL EQUIPMENT AND PRODUCTS PURCHASED ARE TO BE REVISED BY THE CONTRACTOR TO MEET THE REQUIREMENTS FOR CONSTRUCTION UNDER THESE TERMS AT NO COST TO OWNER OR CONSTRUCTION MANAGER.
13. ALL MATERIALS, EQUIPMENTS, AND "MISSED" ITEMS ARE TO BE PROVIDED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MATERIALS AND EQUIPMENTS TO BE PROVIDED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MATERIALS AND EQUIPMENTS TO BE PROVIDED BY THE CONTRACTOR.
14. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK SAFETY FROM THE TIME THE JOB IS AWARDED UNTIL ALL WORK IS COMPLETED AND ACCEPTED BY THE OWNER.
15. CONTRACTOR TO REVIEW ALL SHOP DRAWINGS AND SUBMIT COPY TO THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONTRACTOR'S INTENTIONS REGARDING THE CONSTRUCTION MANAGER FOR REVIEW.
16. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, AND LOCATIONS OF ALL STRUCTURES AT THE SITE PRIOR TO THE BEGINNING OF CONSTRUCTION. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, AND LOCATIONS OF ALL STRUCTURES AT THE SITE PRIOR TO THE BEGINNING OF CONSTRUCTION.
17. COORDINATION, LAYOUT, DIMENSIONING AND INSTALLATION OF CONDUIT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, AND LOCATIONS OF ALL STRUCTURES AT THE SITE PRIOR TO THE BEGINNING OF CONSTRUCTION.
18. ALL EQUIPMENT AND PRODUCTS PURCHASED ARE TO BE REVISED BY THE CONTRACTOR TO MEET THE REQUIREMENTS FOR CONSTRUCTION UNDER THESE TERMS AT NO COST TO OWNER OR CONSTRUCTION MANAGER.
19. ALL EQUIPMENT AND PRODUCTS PURCHASED ARE TO BE REVISED BY THE CONTRACTOR TO MEET THE REQUIREMENTS FOR CONSTRUCTION UNDER THESE TERMS AT NO COST TO OWNER OR CONSTRUCTION MANAGER.
20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
21. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
22. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
23. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
24. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
25. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
26. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
27. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
28. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
29. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
30. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
31. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
32. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
33. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
34. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
35. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
36. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
37. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
38. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
39. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
40. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
41. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
42. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
43. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
44. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
45. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
46. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
47. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
48. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
49. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
50. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
51. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
52. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
53. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
54. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
55. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
56. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
57. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
58. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
59. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE STABILITY OF THE EXISTING OPERATIONS, COORDINATE WORK WITH BUILDING/PROPERTY OWNER.
60. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION AND WORK OF THE SUBCONTRACTORS.
61. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION METHODS AND MATERIALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF WHATEVER PILING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY TO MAINTAIN THE ST

PROJECT SUMMARY


1. THE PROPOSED SCOPE OF WORK GENERALLY CONSISTS OF THE INSTALLATION OF ONE (1) LITE ANTENNA PER SECTOR FOR A TOTAL OF (3) LITE ANTENNAS TO THE EXISTING AT&T ANTENNA SITES. THE LITE ANTENNAS ARE TO BE INSTALLED WITHIN THE LITE BASEBAND EQUIPMENT LANT (RBS) WILL BE INSTALLED WITHIN THE EXISTING AIRCRAFT EQUIPMENT SHELTER.
2. ADDITIONALLY, (2) REMOTE RADIO UNITS (RRUs) PER SECTOR WILL BE INSTALLED. SOURCE AGREEMENTS WILL BE PURCHASED FOR BOTH AT&T RRU AND EQUIPMENT LOCATIONS. REFER TO THESE ACCOMPANYING DRAWINGS FOR FURTHER INFORMATION.

PROJECT INFORMATION

CT185
BROOKFIELD
CLAP STRUCTURE NO: 2693
7817 FEDERAL ROAD
BROOKFIELD, CT 06004
ATTN: MOBILITY
100 ENTERPRISE DRIVE SUITE 3A
ROCKY HILL, CT 06067
CONTEX ENGINEERING, INC.
63-2 NORTH BRANFORD RD.
BRANFORD, CT 06405
LATITUDE: 41°-28'-43.37" N
LONGITUDE: 72°-34'-28.89" W
GROUND ELEVATION: 4231' ASL


SHEET INDEX

REV	DESCRIPTION	SHEET NO.
1	TITLE SHEET	E-1
1	NOTES AND SPECIFICATIONS	E-1
1	PLANS AND ELEVATION	C-1
1	LIVE SYSTEM EQUIPMENT PLANS & DETAILS	C-2
1	ELECTRICAL DETAILS AND NOTES	E-1
1	ELECTRICAL DETAILS	E-2




AT&T MOBILITY SITE NUMBER: CT2185 CL&P STRUCT. NO.: 2683 SITE NAME: BROOKFIELD 174 HIGHLAND AVE BROOKFIELD, CT 06040		CENTEX Engineering 10000 N. CENTEX BLVD FORT WORTH, TX 76155 TEL: 817-440-5000 FAX: 817-440-5001 6425 WORTH BLVD IRVING, TX 75039 www.Centex.com		at&t 		RECEIVED BY: _____ DATE: _____ DRAWN BY: _____ DATE: _____ CHECKED BY: _____ DATE: _____ TITLE SHEET	
---	--	--	--	---	--	--	--







- NOTE:**
1. NUMBER OF GROUND BARS MAY VARY DEPENDING ON THE TYPE OF TOWER, LOCATION AND CONNECTION ORIENTATION. PROVIDE AS REQUIRED.
 2. A SEPARATE GROUND BAR TO BE USED FOR GPS ANTENNA IF REQUIRED.
- 1 ANTENNA CABLE GROUNDING - MONOPOLE**
E-2
NOT TO SCALE



- NOTE:**
1. WIRE MUST BE INSTALLED AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO CORE.
- 3 CONNECTION OF GROUND WIRES TO GROUND BAR**
E-2
NOT TO SCALE



- LEGEND**
1. TINNED COPPER GROUND BAR, 1/4" x 3/8" x 20".
 2. INSULATORS, NEWTON INSTRUMENT CO. HOLE CENTERS TO MATCH NEWA DOUBLE LUG.
 3. 3/8" LOCK WASHERS, NEWTON INSTRUMENT CO. CAT. NO. 3015-E.
 4. WALL MOUNTING BRACKET, NEWTON INSTRUMENT CO. CAT. NO. A-8056.
 5. STAINLESS STEEL SECURITY SCREWS.
- 2 GROUND BAR DETAIL**
E-2
NOT TO SCALE



- NOTE:**
1. DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.
- 4 ANTENNA CABLE GROUNDING DETAIL**
E-2
NOT TO SCALE



**Northeast
Utilities System**

107 Selden Street, Berlin, CT 06037

Northeast Utilities Service Company
P.O. Box 270
Hartford, CT 06141-0270
(203) 665-5000

July 7, 2011

Mr. Tim Burks
AT&T Wireless.
500 Enterprise Drive
Rocky Hill, CT 06067

RE: AT&T Antenna Site, CT-2185, 761 Federal Rd., Brookfield CT, structure 2683.

Dear Mr. Burks:

Based on our reviews of the site drawings, the structural analysis provided by Centek Engineering and, and the foundation analyses performed by Centek Engineering, we have reviewed for acceptance this modification

Since there are no outstanding structural issues to resolve at this time please contact Mr. Green (860-665-6926) to resolve any lease issues; once the lease amendment is secured you may contact Mr. Eriks Surmanis directly (860-665-5849) to begin these arrangements.

Sincerely,

Robert Gray

Transmission Line Engineering

ref: CT2185 LTE CD Rev 1 7-6-11 (2)
CT2185 LTE Structural 6-29-11

Structural Analysis of PCS
Mast and CL&P Pole

AT&T Site Ref: CT2185: Brookfield


CL&P Structure No. 2683
90' Electric Transmission Pole

761 Federal Road
Brookfield, CT

CEN TEK Project No. 11021.CO50

~~Date: June 15, 2011~~

Rev 1: June 29, 2011



Prepared for:
AT&T Mobility
500 Enterprise Drive, Suite 3A
Rocky Hill, CT 06067

Table of Contents

SECTION 1 - REPORT

- INTRODUCTION
- PRIMARY ASSUMPTIONS USED IN THE ANALYSIS
- ANALYSIS
- DESIGN BASIS
- RESULTS
- CONCLUSION

SECTION 2 - CONDITIONS & SOFTWARE

- STANDARD ENGINEERING CONDITIONS
- GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAMS
 - RISA 3-D
 - PLS POLE

SECTION 3 - DESIGN CRITERIA

- CRITERIA FOR DESIGN OF PCS FACILITIES ON OR EXTENDING ABOVE METAL ELECTRIC TRANSMISSION TOWERS
- NU DESIGN CRITERIA TABLE
- PCS SHAPE FACTOR CRITERIA
- WIRE LOADS SHEET

SECTION 4 - DRAWINGS

- EL-1 POLE AND MAST ELEVATION

SECTION 5 - EIA/TIA-222-F LOAD CALCULATIONS FOR MAST ANALYSIS

- MAST WIND & ICE LOAD

SECTION 6 - MAST ANALYSIS PER EIA/TIA-222F

- LOAD CASES AND COMBINATIONS (TIA/EIA LOADING)
- RISA 3-D ANALYSIS REPORT
- MAST CONNECTION TO CL&P TOWER ANALYSIS

**SECTION 7 - NECS/NU LOAD CALCULATIONS FOR OBTAINING
MAST REACTIONS APPLIED TO UTILITY STRUCTURE**

- MAST WIND LOAD

**SECTION 8 - MAST ANALYSIS PER NESC/NU FOR OBTAINING
REACTIONS APPLIED TO UTILITY STRUCTURE**

- LOAD CASES AND COMBINATIONS (NESC/NU LOADING)
- RISA 3-D ANALYSIS REPORT

**SECTION 9 - PLS POLE RESULTS FROM MAST REACTIONS
CALCULATED IN RISA WITH NESC/NU CRITERIA**

- COAX CABLE LOAD ON CL&P TOWER CALCULATION
- PLS REPORT
- ANCHOR BOLT ANALYSIS.

SECTION 10 - REFERENCE MATERIAL

- RFDS SHEET
- EQUIPMENT CUT SHEETS

Introduction

The purpose of this report is to analyze the existing mast and 90' CL&P pole located at 761 Federal Road in Brookfield, CT for the proposed antenna and equipment upgrade by AT&T.

The existing/proposed loads consist of the following:

- SPRINT (Existing to Remain):

Antennas: Three (3) EMS RR90-17-00DP panel antennas flush mounted on the existing mast with a RAD center elevation of 110-ft-8-in above grade level.

Coax Cables: Six (6) 1-1/4" Ø coax cables running on the exterior of the CL&P pole and pcs mast.

Mast: 12" Sch. 40 x 22' long pipe flange connected to a HSS16"x0.375" x 42' long pipe.

- AT&T (Existing to Remain):

Antennas: Three (3) Powerwave 7770 panel antennas and six (6) Powerwave LGP-21401 TMAs mounted on the proposed dual standoff mounts to the existing mast with a RAD center elevation of 97-ft above grade level.

Coax Cables: Nine (9) 1-1/4" Ø coax cables running on the exterior of the CL&P pole.

- AT&T (Proposed):

Antennas: Three (3) Powerwave P65-16-XLH-RR panel antennas and three (3) Powerwave TTAW-07BP111-001 TMAs mounted on the proposed dual standoff mount to the existing mast with a RAD center elevation of 97-ft above grade level.

Coax Cables: Six (6) 1-1/4" Ø coax cables running on the exterior of the CL&P pole.

Primary assumptions used in the analysis

- Allowable steel stresses are defined by AISC-ASD 9th edition for design of the PCS Mast and antenna supporting elements.
- ASCE Manual No. 72, "Design of Steel Transmission Pole Structures Second Edition", defines allowable steel stresses for evaluation of the CL&P utility pole.
- All utility pole members are adequately protected to prevent corrosion of steel members.
- All proposed antenna mounts are modeled as listed above.
- Pipe mast will be properly installed and maintained.
- No residual stresses exist due to incorrect pole erection.
- All bolts are appropriately tightened providing the necessary connection continuity.
- All welds conform to the requirements of AWS D1.1.
- Pipe mast and utility pole will be in plumb condition.
- Utility pole was properly installed and maintained and all members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
- Any deviation from the analyzed loading will require a new analysis for verification of structural adequacy.

A n a l y s i s

Structural analysis of the existing *Mast* was independently completed using the current version of RISA-3D computer program licensed to CENTEK Engineering, Inc.

The existing mast consisting of a 12" Sch. 40 x 22' long pipe conforming to ASTM A53 Grade B ($F_y = 35\text{ksi}$) flange connected to a HSS16"x0.375" x 42' long pipe conforming to ASTM A500 Grade B ($F_y = 42\text{ksi}$) connected at two points to the existing pole was analyzed for its ability to resist loads prescribed by the TIA/EIA standard. Section 5 of this report details these gravity and lateral wind loads. NESC prescribed loads were also applied to the mast in order to obtain reactions needed for analyzing the CL&P pole structure. These loads are developed in Section 7 of this report. Load cases and combinations used in RISA-3D for TIA/EIA loading and for NESC/NU loading are listed in report Sections 6 and 8, respectively.

An envelope solution was first made to determine maximum and minimum forces, stresses, and deflections to confirm the selected section as adequate. Additional analyses were then made to determine the NESC forces to be applied to the CL&P pole structure.

The RISA-3D program contains a library of all AISC shapes and corresponding section properties are computed and applied directly within the program. The program's Steel Code Check option was also utilized. The forces calculated in RISA-3D using NESC guidelines were then applied to the CL&P pole using PLS-Pole. Maximum usage for the pole was calculated considering the additional forces from the mast and associated appurtenances.

D e s i g n B a s i s

Our analysis was performed in accordance with TIA/EIA-222-F-1996, ASCE Manual No. 72 – "Design of Steel Transmission Pole Structures Second Edition", NESC C2-2007 and Northeast Utilities Design Criteria.

The CL&P pole structure, considering existing and future conductor and shield wire loading, with the pcs antenna mast was analyzed under two conditions:

▪ UTILITY POLE ANALYSIS

The purpose of this analysis is to determine the adequacy of the existing utility pole to support the proposed antenna loads. The loading and design requirements were analyzed in accordance with the NU Design Criteria Table, NESC C2-2007 ~ Construction Grade B, and ASCE Manual No. 72.

Load cases considered:

Load Case 1: NESC Heavy

Wind Pressure.....	4.0 psf
Vertical Overload Capacity Factor.....	1.50
Wind Overload Capacity Factor.....	2.50
Wire Tension Overload Capacity Factor.....	1.65

Load Case 2: NESC Extreme

Wind Speed.....	100 mph ⁽¹⁾
Radial Ice Thickness.....	0"

Note 1: NESC C2-2007, Section 25, Rule 250C: Extreme Wind Loading, 1.25 x Gust Response Factor (wind speed: 3-second gust)

MAST ASSEMBLY ANALYSIS

Mast, appurtenances and connections to the utility tower were analyzed and designed in accordance with the NU Design Criteria Table, TIA/EIA-222-F, and AISC-ASD standards.

Load cases considered:

Load Case 1:

Wind Speed..... 85 mph ⁽²⁾
 Radial Ice Thickness..... 0"

Load Case 2:

Wind Pressure..... 75% of 85 mph wind pressure
 Radial Ice Thickness..... 0.5"

| Note 2: Per NU Mast Design Criteria Exception 1.

Results

MAST ASSEMBLY

The existing mast was determined to be structurally adequate.

Member	Stress Ratio (% of capacity)	Result
12" Sch. 40 pipe x 22-ft long	51.0%	PASS
HSS 16"x0.375" pipe x 42-ft long	64.1%	PASS
5/8" Ø ASTM A325 Bolt	36.0% ⁽¹⁾	PASS

Note 1 – 1/3 increase in allowable stress not used per OTRM 059.

UTILITY POLE

This analysis finds that the subject utility pole is adequate to support the proposed antenna mast and related appurtenances. The pole stresses meet the requirements set forth by the ASCE Manual No. 72, "Design of Steel Transmission Pole Structures Second Edition", for the applied NESC Heavy and Hi-Wind load cases. The detailed analysis results are provided in Section 9 of this report. The analysis results are summarized as follows:

A maximum usage of **68.81%** occurs in the utility pole under the **NESC Heavy** loading condition.

POLE SECTION:

The utility pole was found to be within allowable limits.

Tower Section	Elevation	Stress Ratio (% of capacity)	Result
Tube Number 3	0'-20.67' (AGL)	68.81%	PASS

BASE PLATE:

The base plate was found to be within allowable limits from the PLS output based on 10 bend lines.

Tower Component	Design Limit	Stress Ratio (percentage of capacity)	Result
Base Plate	Bending	56.66%	PASS

▪ **FOUNDATION AND ANCHORS**

The existing foundation consists of a 10-ft square x 9-ft long reinforced concrete pier with (16) rock anchors. The base of the tower is connected to the foundation by means of (12) 2.25"Ø, ASTM A615-75 anchor bolts embedded approximately 8-ft into the concrete foundation structure. Foundation information was obtained from NUSCO drawing # 01039-60001.

Review of the foundation and anchor design consisted of verification of applied loads obtained from the tower design calculations and code checks of allowable stresses:

BASE REACTIONS:

From PLS-Pole analysis of CL&P pole based on NESC/NU prescribed loads.

Load Case	Shear	Axial	Moment
NESC Heavy Wind	24.4 kips	48.5 kips	1846.4 ft-kips
NESC Extreme Wind	25.2 kips	23.9 kips	1785.8 ft-kips

Note 1 – 10% increase applied to tower base reactions per OTRM 051

ANCHOR BOLTS:

The anchor bolts were found to be within allowable limits.

Tower Component	Design Limit	Stress Ratio (% of capacity)	Result
Anchor Bolts	Tension	34.36%	PASS

FOUNDATION:

The foundation was found to be within allowable limits.

Foundation	Design Limit	Allowable Load ⁽¹⁾	Proposed Loading ⁽²⁾	Result
Reinf. Conc. Pier w/ Rock Anchors	OTM ⁽³⁾	3234.5 ft-kips	2031.1 ft-kips	PASS

Note 1: Allowable Load taken from NUSCO drawing no. 01039-50002.

Note 2: 10% increase to PLS base reactions used in foundation analysis per OTRM 051.

Note 3: OTM denotes Overturning Moment

Conclusions and Recommendations

This analysis shows that the subject utility pole is adequate to support the proposed AT&T equipment upgrade.

The analysis is based, in part on the information provided to this office by Northeast Utilities and AT&T Mobility. If the existing conditions are different than the information in this report, CENTEK engineering, Inc. must be contacted for resolution of any potential issues.

Please feel free to call with any questions or comments.

Respectfully Submitted by:

Carlo F. Centore, PE
 Principal ~ Structural Engineer



Prepared by:

Timothy J. Lynn, EIT
 Structural Engineer

STANDARD CONDITIONS FOR FURNISHING OF
PROFESSIONAL ENGINEERING SERVICES ON
EXISTING STRUCTURES

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessarily limited to:

- Information supplied by the client regarding the structure itself, its foundations, the soil conditions, the antenna and feed line loading on the structure and its components, or other relevant information.
- Information from the field and/or drawings in the possession of CENTEK engineering, Inc. or generated by field inspections or measurements of the structure.
- It is the responsibility of the client to ensure that the information provided to CENTEK engineering, Inc. and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and are in an un-corroded condition and have not deteriorated. It is therefore assumed that its capacity has not significantly changed from the "as new" condition.
- All services will be performed to the codes specified by the client, and we do not imply to meet any other codes or requirements unless explicitly agreed in writing. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement. In the absence of information to the contrary, all work will be performed in accordance with the latest revision of ANSI/ASCE10 & ANSI/EIA-222.
- All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. CENTEK engineering, Inc. is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.

GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM ~ RISA - 3 D

RISA-3D Structural Analysis Program is an integrated structural analysis and design software package for buildings, bridges, tower structures, etc.

Modeling Features:

- Comprehensive CAD-like graphic drawing/editing capabilities that let you draw, modify and load elements as well as snap, move, rotate, copy, mirror, scale, split, merge, mesh, delete, apply, etc.
- Versatile drawing grids (orthogonal, radial, skewed)
- Universal snaps and object snaps allow drawing without grids
- Versatile general truss generator
- Powerful graphic select/unselect tools including box, line, polygon, invert, criteria, spreadsheet selection, with locking
- Saved selections to quickly recall desired selections
- Modification tools that modify single items or entire selections
- Real spreadsheets with cut, paste, fill, math, sort, find, etc.
- Dynamic synchronization between spreadsheets and views so you can edit or view any data in the plotted views or in the spreadsheets
- Simultaneous view of multiple spreadsheets
- Constant in-stream error checking and data validation
- Unlimited undo/redo capability
- Generation templates for grids, disks, cylinders, cones, arcs, trusses, tanks, hydrostatic loads, etc.
- Support for all units systems & conversions at any time
- Automatic interaction with RISASection libraries
- Import DXF, RISA-2D, STAAD and ProSteel 3D files
- Export DXF, SDNF and ProSteel 3D files

Analysis Features:

- Static analysis and P-Delta effects
- Multiple simultaneous dynamic and response spectra analysis using Gupta, CQC or SRSS mode combinations
- Automatic inclusion of mass offset (5% or user defined) for dynamic analysis
- Physical member modeling that does not require members to be broken up at intermediate joints
- State of the art 3 or 4 node plate/shell elements
- High-end automatic mesh generation — draw a polygon with any number of sides to create a mesh of well-formed quadrilateral (NOT triangular) elements.
- Accurate analysis of tapered wide flanges - web, top and bottom flanges may all taper independently
- Automatic rigid diaphragm modeling
- Area loads with one-way or two-way distributions
- Multiple simultaneous moving loads with standard AASHTO loads and custom moving loads for bridges, cranes, etc.
- Torsional warping calculations for stiffness, stress and design
- Automatic Top of Member offset modeling
- Member end releases & rigid end offsets
- Joint master-slave assignments
- Joints detachable from diaphragms
- Enforced joint displacements
- 1-Way members, for tension only bracing, slipping, etc.

- 1-Way springs, for modeling soils and other effects
- Euler members that take compression up to their buckling load, then turn off.
- Stress calculations on any arbitrary shape
- Inactive members, plates, and diaphragms allows you to quickly remove parts of structures from consideration
- Story drift calculations provide relative drift and ratio to height
- Automatic self-weight calculations for members and plates
- Automatic subgrade soil spring generator

Graphics Features:

- Unlimited simultaneous model view windows
- Extraordinary “true to scale” rendering, even when drawing
- High-speed redraw algorithm for instant refreshing
- Dynamic scrolling stops right where you want
- Plot & print virtually everything with color coding & labeling
- Rotate, zoom, pan, scroll and snap views
- Saved views to quickly restore frequent or desired views
- Full render or wire-frame animations of deflected model and dynamic mode shapes with frame and speed control
- Animation of moving loads with speed control
- High quality customizable graphics printing

Design Features:

- Designs concrete, hot rolled steel, cold formed steel and wood
- ACI 1999/2002, BS 8110-97, CSA A23.3-94, IS456:2000, EC 2-1992 with consistent bar sizes through adjacent spans
- Exact integration of concrete stress distributions using parabolic or rectangular stress blocks
- Concrete beam detailing (Rectangular, T and L)
- Concrete column interaction diagrams
- Steel Design Codes: AISC ASD 9th, LRFD 2nd & 3rd, HSS Specification, CAN/CSA-S16.1-1994 & 2004, BS 5950-1-2000, IS 800-1984, Euro 3-1993 including local shape databases
- AISI 1999 cold formed steel design
- NDS 1991/1997/2001 wood design, including Structural Composite Lumber, multi-ply, full sawn
- Automatic spectra generation for UBC 1997, IBC 2000/2003
- Generation of load combinations: ASCE, UBC, IBC, BOCA, SBC, ACI
- Unbraced lengths for physical members that recognize connecting elements and full lengths of members
- Automatic approximation of K factors
- Tapered wide flange design with either ASD or LRFD codes
- Optimization of member sizes for all materials and all design codes, controlled by standard or user-defined lists of available sizes and criteria such as maximum depths
- Automatic calculation of custom shape properties
- Steel Shapes: AISC, HSS, CAN, ARBED, British, Euro, Indian, Chilean
- Light Gage Shapes: AISI, SSMA, Dale / Incor, Dietrich, MarinoWARE
- Wood Shapes: Complete NDS species/grade database
- Full seamless integration with RISAfoot (Ver 2 or better) for advanced footing design and detailing
- Plate force summation tool

Results Features:

- Graphic presentation of color-coded results and plotted designs
- Color contours of plate stresses and forces with quadratic smoothing, the contours may also be animated
- Spreadsheet results with sorting and filtering of: reactions, member & joint deflections, beam & plate forces/stresses, optimized sizes, code designs, concrete reinforcing, material takeoffs, frequencies and mode shapes
- Standard and user-defined reports
- Graphic member detail reports with force/stress/deflection diagrams and detailed design calculations and expanded diagrams that display magnitudes at any dialed location
- Saved solutions quickly restore analysis and design results.

GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM ~ PLS-POLE

PLS-POLE provides all of the capabilities a structural engineer requires to design transmission, substation or communications structures. It does so using a simple easy to use graphical interface that rests upon our time tested finite element engine. Regardless of whether you want to model a simple wood pole or a guyed steel X-Frame; PLS-POLE can handle the job simply, reliably and efficiently.

Modeling Features:

- Structures are made of standard reusable components that are available in libraries. You can easily create your own libraries or get them from a manufacturer
- Structure models are built interactively using interactive menus and graphical commands
- Automatic generation of underlying finite element model of structure
- Steel poles can have circular, 4, 6, 8, 12, 16, or 18-sided, regular, elliptical or user input cross sections (flat-to-flat or tip-to-tip orientations)
- Steel and concrete poles can be selected from standard sizes available from manufacturers
- Automatic pole class selection
- Cross brace position optimizer
- Capability to specify pole ground line rotations
- Capability to model foundation displacements
- Can optionally model foundation stiffness
- Guys are easily handled (modeled as exact cable elements in nonlinear analysis)
- Powerful graphics module (members color-coded by stress usage)
- Graphical selection of joints and components allows graphical editing and checking
- Poles can be shown as lines, wire frames or can be rendered as 3-d polygon surfaces

Analysis Features:

- Automatic distribution of loads in 2-part suspension insulators (v-strings, horizontal vees, etc.)
- Design checks for ASCE, ANSI/TIA/EIA 222 (Revisions F and G) or other requirements
- Automatic calculation of dead and wind loads
- Automated loading on structure (wind, ice and drag coefficients) according to:
 - ASCE 74-1991
 - NESC 2002
 - NESC 2007
 - IEC 60826:2003
 - EN50341-1:2001 (CENELEC)
 - EN50341-3-9:2001 (UK NNA)
 - EN50341-3-17:2001 (Portugal NNA)
 - ESAA C(b)1-2003 (Australia)
 - TPNZ (New Zealand)
 - REE (Spain)
 - EIA/TIA 222-F
 - ANSI/TIA 222-G
 - CSA S37-01
- Automated microwave antenna loading as per EIA/TIA 222-F and ANSI/TIA 222-G
- Detects buckling by nonlinear analysis

CEN TEK Engineering, Inc.
Structural Analysis – 90-ft CL&P Pole # 2683
AT&T Antenna Upgrade – CT2185: Brookfield
Brookfield, CT
Rev 1 ~ June 29, 2011

Results Features:

- Detects buckling by nonlinear analysis
- Easy to interpret text, spreadsheet and graphics design summaries
- Automatic determination of allowable wind and weight spans
- Automatic determination of interaction diagrams between allowable wind and weight spans
- Automatic tracking of part numbers and costs

Criteria for Design of PCS Facilities On or
Extending Above Metal Electric Transmission
Towers & Analysis of Transmission Towers
Supporting PCS Masts ⁽¹⁾

Introduction

This criteria is the result from an evaluation of the methods and loadings specified by the separate standards, which are used in designing telecommunications towers and electric transmission towers. That evaluation is detailed elsewhere, but in summary; the methods and loadings are significantly different. This criteria specifies the manner in which the appropriate standard is used to design PCS facilities including masts and brackets (hereafter referred to as "masts"), and to evaluate the electric transmission towers to support PCS masts. The intent is to achieve an equivalent level of safety and security under the extreme design conditions expected in Connecticut and Massachusetts.

ANSI Standard TIA/EIA-222 covering the design of telecommunications structures specifies a working strength/allowable stress design approach. This approach applies the loads from extreme weather loading conditions, and designs the structure so that it does not exceed some defined percentage of failure strength (allowable stress).

ANSI Standard C2-2007 (National Electrical Safety Code) covering the design of electric transmission metal structures is based upon an ultimate strength/yield stress design approach. This approach applies a multiplier (overload capacity factor) to the loads possible from extreme weather loading conditions, and designs the structure so that it does not exceed its ultimate strength (yield stress).

Each standard defines the details of how loads are to be calculated differently. Most of the NU effort in "unifying" both codes was to establish what level of strength each approach would provide, and then increasing the appropriate elements of each to achieve a similar level of security under extreme weather loadings.

Two extreme weather conditions are considered. The first is an extreme wind condition (hurricane) based upon a 50-year recurrence (2% annual probability). The second is a winter condition combining wind and ice loadings.

The following sections describe the design criteria for any PCS mast extending above the top of an electric transmission tower, and the analysis criteria for evaluating the loads on the transmission tower from such a mast from the lower portions of such a mast, and loads on the pre-existing electric lower portions of such a mast, and loads on the pre-existing electric transmission tower and the conductors it supports.

| Note 1: Prepared from documentation provide from Northeast Utilities.

P C S M a s t

The PCS facility (mast, external cable/trays, including the initial and any planned future support platforms, antennas, etc. extending the full height above the top level of the electric transmission structure) shall be designed in accordance with the provisions of TIA/EIA Standard 222 with two exceptions:

1. An 85 mph extreme wind speed shall be used for locations in all counties throughout the NU system.
2. The stress increase of TIA Section 3.1.1.1 is disallowed. The combined wind and ice condition shall consider $\frac{1}{2}$ " radial ice in combination with the wind load ($0.75 W_i$) as specified in TIA section 2.3.16.

E L E C T R I C T R A N S M I S S I O N T O W E R

The electric transmission tower shall be analyzed using yield stress theory in accordance with the attached table titled "NU Design Criteria". This specifies uniform loadings (different from the TIA loadings) on the each of the following components of the installed facility:

- PCS mast for its total height above ground level, including the initial and planned future support platforms, antennas, etc. above the top of an electric transmission structure.
- Conductors are related devices and hardware.
- Electric transmission structure. The loads from the PCS facility and from the electric conductors shall be applied to the structure at conductor and PCS mast attachment points, where those load transfer to the tower.

The uniform loadings and factors specified for the above components in the table are based upon the National Electrical Safety Code 2007 Edition Extreme Wind (Rule 250C) and Combined Ice and Wind (Rule 250B-Heavy) Loadings. These provide equivalent loadings compared to TIA and its loads and factors with the exceptions noted above. (Note that the NESC does not require the projected wind surfaces of structures and equipment to be increased by the ice covering.)

In the event that the electric transmission tower is not sufficient to support the additional loadings of the PCS mast, reinforcement will be necessary to upgrade the strength of the overstressed members.

Northeast Utilities Overhead Transmission Standards

Attachment A

NU Design Criteria

			Basic Wind Speed	Pressure	Height Factor	Gust Factor	Load or Stress Factor	Force Coef - Shape Factor
			V (MPH)	Q (PSF)	Kz	Gh		
Ice Condition	TIA/EIA	Antenna Mount	TIA	TIA (75WI)	TIA	TIA	TIA - Section 3.1.1.1 - disallowed for connection design	TIA
	NESC Heavy	Tower/Pole Analysis with antennas extending above top of Tower/Pole (Yield Stress)	---	4	1.00	1.00	2.50	1.6 Flat Surfaces 1.3 Round Surfaces
		Tower/Pole Analysis with Antennas below top of Tower/Pole (on two faces)		4	1.00	1.00	2.50	1.6 Flat Surfaces 1.3 Round Surfaces
	Conductors:		Conductor loads provided by NU					
High Wind Condition	TIA/EIA	Antenna Mount	85	TIA	TIA	TIA	TIA - Section 3.1.1.1 - disallowed for connection design	TIA
	NESC Extreme Wind	Tower/Pole Analysis with antennas extending above top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250C: Extreme Wind Loading 1.25 x Gust Response Factor Height above ground level based on top of Mast/Antenna					1.6 Flat Surfaces 1.3 Round Surfaces
		Tower/Pole Analysis with Antennas below top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250C: Extreme Wind Loading Height above ground level based on top of Tower/Pole					1.6 Flat Surfaces 1.3 Round Surfaces
	Conductors:		Conductor loads provided by NU					
NESC Extreme Ice with Wind Condition*		Tower/Pole Analysis with antennas extending above top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250D: Extreme Ice with Wind Loading 4PSF Wind Load 1.25 x Gust Response Factor Height above ground level based on top of Mast/Antenna					1.6 Flat Surfaces 1.3 Round Surfaces
		Tower/Pole Analysis with Antennas below top of Tower/Pole	Use NESC C2-2007, Section 25, Rule 250D: Extreme Ice with Wind Loading 4PSF Wind Load Height above ground level based on top of Tower/Pole					1.6 Flat Surfaces 1.3 Round Surfaces
	Conductors:		Conductor loads provided by NU					
* Only for Structures Installed after 2007								

* Only for Structures Installed after 2007

Communication Antennas on Transmission Structures (CL&P & WMECo Only)

Northeast Utilities

Approved by: DEH (NU)

Design

OTRM 059

Page 7 of 9

Rev.0

11/17/2009

Northeast Utilities Overhead Transmission Standards

- 2) STEP 2 - The electric transmission structure analysis and evaluation shall be performed in accordance with NESC requirements and shall include the mast and antenna loads determined from NESC applied loading conditions (not TIA/EIA Loads) on the structure and mount as specified below, and shall include the wireless communication mast and antenna loads per NESC criteria)

The structure shall be analyzed using yield stress theory in accordance with Attachment A, "NU Design Criteria." This specifies uniform loadings (different from the TIA loadings) on each of the following components of the installed facility:

- a) Wireless communication mast for its total height above ground level, including the initial and any planned future equipment (Support Platforms, Antennas, TMA's etc.) above the top of an electric transmission structure.
- b) Conductors and related devices and hardware (wire loads will be provided by NU).
- c) Electric Transmission Structure
 - i) The loads from the wireless communication equipment components based on NESC and NU Criteria in Attachment A, and from the electric conductors shall be applied to the structure at conductor and wireless communication mast attachment points, where those loads transfer to the tower.
 - ii) Shape Factor Multiplier:

NESC Structure Shape	Cd
Polyround (for polygonal steel poles)	1.3
Flat	1.6
Open Lattice	3.2

- iii) When Coaxial Cables are mounted along side the pole structure, the shape multiplier shall be:

Mount Type	Cable Cd	Pole Cd
Coaxial Cables on outside periphery (One layer)	1.45	1.45
Coaxial Cables mounted on stand offs	1.6	1.3

- d) The uniform loadings and factors specified for the above components in Attachment A, "NU Design Criteria" are based upon the National Electric Safety Code 2007 Edition Extreme Wind (Rule 250C) and Combined Ice and Wind (Rule 250B-Heavy) Loadings. These provide equivalent loadings compared to the TIA and its loads and factors with the exceptions noted above.

Note: The NESC does not require ice load be included in the supporting structure. (Ice on conductors and shield wire only, and NU will provide these loads).

- e) Mast reaction loads shall be evaluated for local effects on the transmission structure members at the attachment points.

If the electric transmission structure is not sufficient to support the additional loadings of the wireless communication mast, reinforcement will be required to upgrade the strength of the overstressed members. Any reinforcement design will be reviewed by NU TL&CE to determine the feasibility of construction and its impact on the use of the structure as a transmission structure.

Communication Antennas on Transmission Structures (CL&P & WMECo Only)			
Northeast Utilities Approved by: DEH (NU)	Design	OTRM 059	Rev.0
		Page 3 of 9	11/17/2009

TITLE _____
 STRUCT CL&P #2683

06/05/2000

CONDUCTOR

	AHEAD	BACK
	LINNET ▼	LINNET ▼
	336	336
	26/7 ACSR	26/7 ACSR
DIAM =	0.720	0.720
WEIGHT =	0.462	0.462
TENSION (LBS)	AHEAD 4,000	BACK 4,000

LOADCASE	NESC HEAVY ▼
WIND (PSF)	4
ICE (IN)	0.50
OLF ANG	1.65
OLF WIND	2.50
OLF WT	1.50

STR	ANGLE	WIND SPAN	WGT SPAN	NESC HEAVY		
				H	L	V
BACK	7	243	345	1152	-6551	632
AHEAD	7	243	345	1153	6551	632
TOTALS	14.0	486	690	2305	0	1263

TITLE _____
 STRUCT CL&P #2683

06/05/2000

CONDUCTOR

	AHEAD	BACK
	LINNET	LINNET
	336	336
	26/7 ACSR	26/7 ACSR
DIAM =	0.720	0.720
WEIGHT =	0.462	0.462
TENSION (LBS)	AHEAD 2,904	BACK 2,904

LOADCASE	HI WIND
WIND (PSF)	20
ICE (IN)	0.00
OLF ANG	1.15
OLF WIND	1.15
OLF WT	1.15

STR	ANGLE	WIND SPAN	WGT SPAN	HI WIND		
				H	L	V
BACK	7	243	345	742	-3315	183
AHEAD	7	243	345	742	3315	183
TOTALS	14.0	486	690	1484	0	367

Wire Ld

TITLE _____
STRUCT CL&P #2683

06/05/2000

CONDUCTOR SHIELD WIRE

	AHEAD	BACK
	3/8 AW	3/8 AW
	0.000	0.000
	7 #8 Al Weld	7 #8 Al Weld
DIAM =	0.385	0.385
WEIGHT =	0.262	0.262
TENSION (LBS)	AHEAD 2,749	BACK 2,749

LOADCASE	HI WIND
WIND (PSF)	20
ICE (IN)	0.00
OLF ANG	1.15
OLF WIND	1.15
OLF WT	1.15

STR	ANGLE	WIND SPAN	WGT SPAN	H	HI WIND L	V
BACK	7	243	345	564	-3138	104
AHEAD	7	243	345	565	3138	104
TOTALS	14.0	486	690	1129	0	208

Wire Ld

TITLE _____
STRUCT CL&P #2683

06/05/2000

CONDUCTOR SHIELD WIRE

	AHEAD		BACK
	3/8 AW	▼	3/8 AW
	0.000		0.000
	7 #8 Al Weld		7 #8 Al Weld
DIAM =	0.385		0.385
WEIGHT =	0.262		0.262
TENSION (LBS)	AHEAD	4,200	BACK
		4,200	

LOADCASE	NESC HEAVY	▼
WIND (PSF)	4	
ICE (IN)	0.50	
OLF ANG	1.65	
OLF WIND	2.50	
OLF WT	1.50	

STR	ANGLE	WIND SPAN	WGT SPAN	NESC HEAVY		
				H	L	V
BACK	7	243	345	1125	-6878	420
AHEAD	7	243	345	1125	6878	420
TOTALS	14.0	486	690	2250	0	840

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

**Development of Design Heights, Exposure Coefficients,
 and Velocity Pressures Per TIA/EIA**

Wind Speeds

Basic Wind Speed	$V := 85$	mph	(User Input per NU Mast Design Criteria Exception 1)
Basic Wind Speed with Ice	$V_i := 74$	mph	(User Input per TIA/EIA-222-F Section 2.3.16)

Heights above ground level, z

Mast 1	$z_{mast1} := 103$	ft	(User Input)
Mast 2	$z_{mast2} := 71$	ft	(User Input)
Sprint	$z_{Sprint} := 110.67$	ft	(User Input)
AT&T	$z_{AT\&T} := 97$	ft	(User Input)
Coax Cable	$z_{coax} := 82$	ft	(User Input)

Exposure Coefficients, k_z

(per TIA/EIA-222-F Section 2.3.3)

Mast 1	$Kz_{mast1} := \left(\frac{z_{mast1}}{33} \right)^{\frac{2}{7}} = 1.384$
Mast 2	$Kz_{mast2} := \left(\frac{z_{mast2}}{33} \right)^{\frac{2}{7}} = 1.245$
Sprint	$Kz_{Sprint} := \left(\frac{z_{Sprint}}{33} \right)^{\frac{2}{7}} = 1.413$
AT&T	$Kz_{AT\&T} := \left(\frac{z_{AT\&T}}{33} \right)^{\frac{2}{7}} = 1.361$
Coax Cable	$Kz_{coax} := \left(\frac{z_{coax}}{33} \right)^{\frac{2}{7}} = 1.297$

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

Velocity Pressure without ice, qz

(per TIA/EIA-222-F Section 2.3.3)

Mast 1	$qz_{mast1} := 0.00256 \cdot Kz_{mast1} \cdot V^2 = 25.604$
Mast 2	$qz_{mast2} := 0.00256 \cdot Kz_{mast2} \cdot V^2 = 23.022$
Sprint	$qz_{Sprint} := 0.00256 \cdot Kz_{Sprint} \cdot V^2 = 26.135$
AT&T	$qz_{AT\&T} := 0.00256 \cdot Kz_{AT\&T} \cdot V^2 = 25.169$
Coax Cable	$qz_{coax} := 0.00256 \cdot Kz_{coax} \cdot V^2 = 23.989$

Velocity Pressure with ice, qzICE

(per TIA/EIA-222-F Section 2.3.3)

Mast 1	$qzICE_{mast1} := 0.00256 \cdot Kz_{mast1} \cdot V_i^2 = 19.406$
Mast 2	$qzICE_{mast2} := 0.00256 \cdot Kz_{mast2} \cdot V_i^2 = 17.449$
Sprint	$qzICE_{Sprint} := 0.00256 \cdot Kz_{Sprint} \cdot V_i^2 = 19.808$
AT&T	$qzICE_{AT\&T} := 0.00256 \cdot Kz_{AT\&T} \cdot V_i^2 = 19.076$
Coax Cable	$qzICE_{coax} := 0.00256 \cdot Kz_{coax} \cdot V_i^2 = 18.182$

TIA/EIA Common Factors:

Gust Response Factor =	$G_H := 1.69$	(User Input per TIA/EIA-222-F Section 2.3.4)
Gust Response Factor Multiplier =	$m := 1.25$	(User Input per TIA/EIA-222-F Section 2.3.4.4)
Radial Ice Thickness =	$Ir := 0.50$ in	(User Input per TIA/EIA-222-F Section 2.3.1)
Radial Ice Density =	$Id := 56.00$ pcf	(User Input)

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

Development of Wind & Ice Load on PCS Mast

Existing Upper Mast Data

Mast Shape =

(per TIA/EIA-222-F-1996 Criteria)

(Pipe 12 STD)

(User Input)

Mast Diameter =

Round

(User Input)

$D_{\text{mast}} := 12.8$ in

(User Input)

Mast Length =

$L_{\text{mast}} := 22.417$ ft

(User Input)

Mast Thickness =

$t_{\text{mast}} := 0.375$ in

(User Input)

Mast Aspect Ratio =

$$A_{r_{\text{mast}}} := \frac{12L_{\text{mast}}}{D_{\text{mast}}} = 21.0$$

Mast Force Coefficient =

$C_{a_{\text{mast}}} = 1.11$

(per TIA/EIA-222-F Table 3)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Mast Projected Surface Area =

$$A_{\text{mast}} := \frac{D_{\text{mast}}}{12} = 1.067$$

sf/ft

Total Mast Wind Force =

$$qz_{\text{mast}1} \cdot G_H \cdot C_{a_{\text{mast}}} \cdot A_{\text{mast}} = 51$$

plf

BLC 5

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Mast Projected Surface Area w/ Ice =

$$A_{\text{ICE}_{\text{mast}}} := \frac{(D_{\text{mast}} + 2 \cdot I_r)}{12} = 1.15$$

sf/ft

Total Mast Wind Force w/ Ice =

$$qz_{\text{ICE}_{\text{mast}1}} \cdot G_H \cdot C_{a_{\text{mast}}} \cdot A_{\text{ICE}_{\text{mast}}} = 42$$

plf

BLC 4

Gravity Loads (without ice)

Weight of the mast =

Self Weight

(Computed internally by Risa-3D)

plf

BLC 1

Gravity Loads (ice only)

Ice Area per Linear Foot =

$$A_{i_{\text{mast}}} := \frac{\pi}{4} \left[(D_{\text{mast}} + I_r \cdot 2)^2 - D_{\text{mast}}^2 \right] = 20.9$$

sq in

Weight of Ice on Mast =

$$W_{\text{ICE}_{\text{mast}}} := I_d \cdot \frac{A_{i_{\text{mast}}}}{144} = 8$$

plf

BLC 3

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

Development of Wind & Ice Load on PCS Mast

(per TIA/EIA-222-F-1996 Criteria)

Existing Lower Mast Data

Mast Shape =	HSS16.0x0.375	(User Input)
Mast Diameter =	Round	(User Input)
Mast Length =	$D_{mast} := 16.0$ in	(User Input)
Mast Thickness =	$L_{mast} := 41.583$ ft	(User Input)
Mast Aspect Ratio =	$t_{mast} := 0.375$ in	(User Input)
	$Ar_{mast} := \frac{12L_{mast}}{D_{mast}} = 31.2$	
Mast Force Coefficient =	$Ca_{mast} = 1.2$	(per TIA/EIA-222-F Table 3)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Mast Projected Surface Area =	$A_{mast} := \frac{D_{mast}}{12} = 1.333$	sf/ft
-------------------------------	---	-------

Total Mast Wind Force =

$qz_{mast2} \cdot G_H \cdot Ca_{mast} \cdot A_{mast} = 62$	plf	BLC 5
--	-----	--------------

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Mast Projected Surface Area w/ Ice =	$AICE_{mast} := \frac{(D_{mast} + 2 \cdot Ir)}{12} = 1.417$	sf/ft
--------------------------------------	---	-------

Total Mast Wind Force w/ Ice =

$qzICE_{mast2} \cdot G_H \cdot Ca_{mast} \cdot AICE_{mast} = 50$	plf	BLC 4
--	-----	--------------

Gravity Loads (without ice)

Weight of the mast =

Self Weight	(Computed internally by Risa-3D)	plf	BLC 1
-------------	----------------------------------	-----	--------------

Gravity Loads (Ice only)

Ice Area per Linear Foot =

$Ai_{mast} := \frac{\pi}{4} [(D_{mast} + Ir \cdot 2)^2 - D_{mast}^2] = 25.9$	sq in
--	-------

Weight of Ice on Mast =

$W_{ICE_{mast}} := Id \cdot \frac{Ai_{mast}}{144} = 10$	plf	BLC 3
---	-----	--------------

Development of Wind & Ice Load on Antennas

(per TIA/EIA-222-F-1996 Criteria)

Existing Antenna Data:

(Sprint)

Antenna Model =
 Antenna Shape =
 Antenna Height =
 Antenna Width =
 Antenna Thickness =
 Antenna Weight =
 Number of Antennas =
 Antenna Aspect Ratio =
 Antenna Force Coefficient =

RR90-17-XXDP

Flat (User Input)

$L_{ant} := 56.0$ in (User Input)

$W_{ant} := 8.0$ in (User Input)


$T_{ant} := 2.75$ in (User Input)

$WT_{ant} := 18.0$ lbs (User Input)

$N_{ant} := 3$ (User Input)

$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 7.0$

$Ca_{ant} = 1.4$ (per TIA/EIA-222-F-1996 Table 3)



Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 3.1$ sf

Antenna Projected Surface Area =

$A_{ant} := SA_{ant} \cdot N_{ant} = 9.3$ sf

Total Antenna Wind Force =

$F_{ant} := qz_{Sprint} \cdot G_H \cdot Ca_{ant} \cdot A_{ant} = 577$ lbs **BLC 5**

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 3.6$ sf

Antenna Projected Surface Area w/ Ice =

$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 10.7$ sf

Total Antenna Wind Force w/ Ice =

$F_{ant} := qz_{ICE} \cdot G_H \cdot Ca_{ant} \cdot A_{ICEant} = 501$ lbs **BLC 4**

Gravity Load (without ice)

Weight of All Antennas =

$WT_{ant} \cdot N_{ant} = 54$ lbs **BLC 2**

Gravity Loads (ice only)

Volume of Each Antenna =

$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 1232$ cu in

Volume of Ice on Each Antenna =

$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 692$ cu in

Weight of Ice on Each Antenna =

$W_{ICEant} := \frac{V_{ice}}{1728} \cdot Id = 22$ lbs

Weight of Ice on All Antennas =

$W_{ICEant} \cdot N_{ant} = 67$ lbs **BLC 3**

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

Development of Wind & Ice Load on Antenna Mounts

Mount Data:

Mount Type:

(per TIA/EIA-222-F-1996 Criteria)

(Sprint)

Microflex Universal Tri-Bracket

Mount Shape =

Flat (User Input)

Pipe Mount Length =

$L_{mnt} := 72$ in (User Input)

2 inch Pipe Mount Linear Weight =

$W_{mnt} := 3.66$ plf (User Input)

Pipe Mount Outside Diameter =

$D_{mnt} := 2.375$ in (User Input)

Number of Mounting Pipes =

$N_{mnt} := 3$ (User Input)

Tri Bracket Weight =

$W_{tb.mnt} := 197$ lbs (User Input)


Mount Aspect Ratio =

$$Ar_{mnt} := \frac{L_{mnt}}{D_{mnt}} = 30$$

Mount Force Coefficient =

$Ca_{mnt} = 2$

(per TIA/EIA-222-F Table 3)



Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Assumes Mount is Shielded by Antenna

Mount Projected Surface Area =

$A_{mnt} := 0.0$ sf

Total Mount Wind Force =

$F_{mnt} := qz_{Sprint} \cdot G_H \cdot Ca_{mnt} \cdot A_{mnt} = 0$ lbs **BLC 5**

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Assumes Mount is Shielded by Antenna

Mount Projected Surface Area w/ Ice =

$A_{ICEmnt} := 0.0$ sf

Total Mount Wind Force =

$F_{mnt} := qz_{ICE} \cdot G_H \cdot Ca_{mnt} \cdot A_{ICEmnt} = 0$ lbs **BLC 4**

Gravity Loads (without ice)

(per TIA/EIA-222-F-1996)

Weight Each Pipe Mount =

$$WT_{mnt} := W_{mnt} \cdot \frac{L_{mnt}}{12} = 22$$
 lbs

Weight of All Mounts =

$WT_{mnt} \cdot N_{mnt} + W_{tb.mnt} = 263$ lbs **BLC 2**

Gravity Loads (ice only)

(per TIA/EIA-222-F-1996)

Volume of Each Pipe =

$$V_{mnt} := \frac{\pi}{4} \cdot D_{mnt}^2 \cdot L_{mnt} = 319$$
 cu in

Volume of Ice on Each Pipe =

$$V_{ice} := \left[\frac{\pi}{4} \cdot (D_{mnt} + 1)^2 \cdot (L_{mnt} + 1) \right] - V_{mnt} = 334$$
 cu in

Weight of Ice each mount (incl. hardware) =

$$W_{ICEmnt} := \frac{V_{ice}}{1728} \cdot Id = 11$$
 lbs

Weight of Ice on All Mounts =

$W_{ICEmnt} \cdot N_{mnt} + 5 = 37$ lbs **BLC 3**

Development of Wind & Ice Load on Antennas

Existing Antenna Data:

Antenna Model =
 Antenna Shape =
 Antenna Height =
 Antenna Width =
 Antenna Thickness =
 Antenna Weight =
 Number of Antennas =
 Antenna Aspect Ratio =
 Antenna Force Coefficient =

(per TIA/EIA-222-F-1996 Criteria)

(AT&T)

Powerwave 7770.00

Flat (User Input)

$L_{ant} := 55$ in (User Input)

$W_{ant} := 11$ in (User Input)


$T_{ant} := 5$ in (User Input)

$WT_{ant} := 39$ lbs (User Input)

$N_{ant} := 3$ (User Input)

$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 5.0$

$Ca_{ant} = 1.4$ (per TIA/EIA-222-F-1996 Table 3)



Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 4.2$ sf

Antenna Projected Surface Area =

$A_{ant} := SA_{ant} \cdot N_{ant} = 12.6$ sf

Total Antenna Wind Force =

$F_{ant} := qz_{AT\&T} \cdot G_H \cdot Ca_{ant} \cdot A_{ant} = 751$ lbs **BLC 5**

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 4.7$ sf

Antenna Projected Surface Area w/ Ice =

$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 14$ sf

Total Antenna Wind Force w/ Ice =

$F_{ant} := qz_{ICE} \cdot G_H \cdot Ca_{ant} \cdot A_{ICEant} = 632$ lbs **BLC 4**

Gravity Load (without ice)

Weight of All Antennas =

$WT_{ant} \cdot N_{ant} = 117$ lbs **BLC 2**

Gravity Loads (ice only)

Volume of Each Antenna =

$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 3025$ cu in

Volume of Ice on Each Antenna =

$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} =$ cu in

Weight of Ice on Each Antenna =

$W_{ICEant} := \frac{V_{ice}}{1728} \cdot Id = 33$ lbs

Weight of Ice on All Antennas =

$W_{ICEant} \cdot N_{ant} = 98$ lbs **BLC 3**

Development of Wind & Ice Load on Antennas

Proposed Antenna Data:

Antenna Model =
Antenna Shape =
Antenna Height =
Antenna Width =
Antenna Thickness =
Antenna Weight =
Number of Antennas =
Antenna Aspect Ratio =
Antenna Force Coefficient =

(per TIA/EIA-222-F-1996 Criteria)

(AT&T)

Powerwave P65-16-XLH-RR

Flat (User Input)

$L_{ant} := 72$ in (User Input)

$W_{ant} := 12$ in (User Input)


$T_{ant} := 6$ in (User Input)

$WT_{ant} := 64$ lbs (User Input)

$N_{ant} := 3$ (User Input)

$Ar_{ant} := \frac{L_{ant}}{W_{ant}} = 6.0$

$Ca_{ant} = 1.4$ (per TIA/EIA-222-F-1996 Table 3)



Wind Load (without ice)

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 6$ sf

Antenna Projected Surface Area =

$A_{ant} := SA_{ant} \cdot N_{ant} = 18$ sf

Total Antenna Wind Force =

$F_{ant} := qz_{AT\&T} \cdot G_H \cdot Ca_{ant} \cdot A_{ant} = 1072$ lbs **BLC 5**

Wind Load (with ice)

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 6.6$ sf

Antenna Projected Surface Area w/ Ice =

$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 19.8$ sf

Total Antenna Wind Force w/ Ice =

$F_{i_{ant}} := qz_{ICE} \cdot G_H \cdot Ca_{ant} \cdot A_{ICEant} = 892$ lbs **BLC 4**

Gravity Load (without ice)

Weight of All Antennas =

$WT_{ant} \cdot N_{ant} = 192$ lbs **BLC 2**

Gravity Loads (Ice only)

Volume of Each Antenna =

$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 5184$ cu in

Volume of Ice on Each Antenna =

$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} =$ cu in

Weight of Ice on Each Antenna =

$W_{ICEant} := \frac{V_{ice}}{1728} \cdot Id = 47$ lbs

Weight of Ice on All Antennas =

$W_{ICEant} \cdot N_{ant} = 142$ lbs **BLC 3**

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

Development of Wind & Ice Load on TMA's

Existing TMA Data:

TMA Model =
 TMA Shape =
 TMA Height =
 TMA Width =
 TMA Thickness =
 TMA Weight =
 Number of TMA's =
 TMA Aspect Ratio =
 TMA Force Coefficient =

(per TIA/EIA-222-F-1996 Criteria)

(AT&T)

Powerwave LGP 21401

Flat

(User Input)

$L_{TMA} := 14.4$ in

(User Input)

$W_{TMA} := 9.2$ in

(User Input)

$T_{TMA} := 2.6$ in

(User Input)

$W_{TMA} := 14.1$ lbs

(User Input)


$N_{TMA} := 6$

(User Input)

$A_{rTMA} := \frac{L_{TMA}}{W_{TMA}} = 1.6$

$Ca_{TMA} = 1.4$

(per TIA/EIA-222-F Table 3)



Wind Load (without ice)

*Assumes Maximum Possible Wind Pressure
 Applied to All TMA's Simultaneously*

Surface Area for One TMA =

$SA_{TMA} := \frac{L_{TMA} \cdot W_{TMA}}{144} = 0.9$

sf

TMA Projected Surface Area =

$A_{TMA} := SA_{TMA} \cdot N_{TMA} = 5.5$

sf

Total TMA Wind Force =

$F_{TMA} := qz_{AT\&T} \cdot G_H \cdot Ca_{TMA} \cdot A_{TMA} = 329$

lbs

BLC 5

Wind Load (with ice)

*Assumes Maximum Possible Wind Pressure
 Applied to All TMA's Simultaneously*

Surface Area for One TMA w/ Ice =

$SA_{ICETMA} := \frac{(L_{TMA} + 1) \cdot (W_{TMA} + 1)}{144} = 1.1$

sf

TMA Projected Surface Area w/ Ice =

$A_{ICETMA} := SA_{ICETMA} \cdot N_{TMA} = 6.5$

sf

Total TMA Wind Force w/ Ice =

$F_{ITMA} := qz_{ICE} \cdot qz_{AT\&T} \cdot G_H \cdot Ca_{TMA} \cdot A_{ICETMA} = 295$

lbs

BLC 4

Gravity Load (without ice)

Weight of All TMA's =

$W_{TMA} \cdot N_{TMA} = 85$

lbs

BLC 2

Gravity Load (ice only)

Volume of Each TMA =

$V_{TMA} := L_{TMA} \cdot W_{TMA} \cdot T_{TMA} = 344$

cu in

Volume of Ice on Each TMA =

$V_{ice} := (L_{TMA} + 1) \cdot (W_{TMA} + 1) \cdot (T_{TMA} + 1) - V_{TMA} = 221$

cu in

Weight of Ice on Each TMA =

$W_{ICETMA} := \frac{V_{ice}}{1728} \cdot \rho_d = 7$

lbs

Weight of Ice on All TMA's

$W_{ICETMA} \cdot N_{TMA} = 43$

lbs

BLC 3

Development of Wind & Ice Load on TMA's

Proposed TMA Data:

TMA Model =
TMA Shape =
TMA Height =
TMA Width =
TMA Thickness =
TMA Weight =
Number of TMA's =
TMA Aspect Ratio =
TMA Force Coefficient =

(per TIA/EIA-222-F-1996 Criteria)

(AT&T)

Powerwave TTAW-07BP111-001

Flat (User Input)

$L_{TMA} := 9.9$ in (User Input)

$W_{TMA} := 6.7$ in (User Input)


$T_{TMA} := 5.4$ in (User Input)

$WT_{TMA} := 18$ lbs (User Input)

$N_{TMA} := 3$ (User Input)

$Ar_{TMA} := \frac{L_{TMA}}{W_{TMA}} = 1.5$

$Ca_{TMA} = 1.4$ (per TIA/EIA-222-F Table 3)



Wind Load (without ice)

*Assumes Maximum Possible Wind Pressure
Applied to All TMA's Simultaneously*

Surface Area for One TMA =

$SA_{TMA} := \frac{L_{TMA} \cdot W_{TMA}}{144} = 0.5$ sf

TMA Projected Surface Area =

$A_{TMA} := SA_{TMA} \cdot N_{TMA} = 1.4$ sf

Total TMA Wind Force =

$F_{TMA} := qz_{AT\&T} \cdot G_H \cdot Ca_{TMA} \cdot A_{TMA} = 82$ lbs **BLC 5**

Wind Load (with ice)

*Assumes Maximum Possible Wind Pressure
Applied to All TMA's Simultaneously*

Surface Area for One TMA w/ Ice =

$SA_{ICETMA} := \frac{(L_{TMA} + 1) \cdot (W_{TMA} + 1)}{144} = 0.6$ sf

TMA Projected Surface Area w/ Ice =

$A_{ICETMA} := SA_{ICETMA} \cdot N_{TMA} = 1.7$ sf

Total TMA Wind Force w/ Ice =

$F_{ITMA} := qz_{ICEAT\&T} \cdot G_H \cdot Ca_{TMA} \cdot A_{ICETMA} = 79$ lbs **BLC 4**

Gravity Load (without ice)

Weight of All TMA's =

$WT_{TMA} \cdot N_{TMA} = 54$ lbs **BLC 2**

Gravity Load (ice only)

Volume of Each TMA =

$V_{TMA} := L_{TMA} \cdot W_{TMA} \cdot T_{TMA} = 358$ cu in

Volume of Ice on Each TMA =

$V_{ice} := (L_{TMA} + 1) \cdot (W_{TMA} + 1) \cdot (T_{TMA} + 1) - V_{TMA} = 179$ cu in

Weight of Ice on Each TMA =

$W_{ICETMA} := \frac{V_{ice}}{1728} \cdot Id = 6$ lbs

Weight of Ice on All TMA's

$W_{ICETMA} \cdot N_{TMA} = 17$ lbs **BLC 3**

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

Development of Wind & Ice Load on Antenna Mounts

Mount Data:

Mount Type:

(per TIA/EIA-222-F-1996 Criteria)

(AT&T)

(3) Valmont Dual Standoff
 Mounts w/ Universal Tr-Bracket

Mount Shape =

Flat (User Input)

Mount Area =

$A_{mnt} := 4.0$ sq ft (User Input)

Mount Area w/ Ice =


$A_{ICE,mnt} := 4.6$ sq ft (User Input)

Mount Weight =

$WT_{mnt} := 610$ lbs (User Input)

Mount Weight w/ Ice =

$WT_{ICE,mnt} := 700$ lbs (User Input)



Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Mount Wind Force =

$F_{mnt} := qz_{AT\&T} \cdot G_H \cdot C_{a,mnt} \cdot A_{mnt} = 238$ lbs **BLC 5**

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Total Mount Wind Force w/ Ice =

$F_{i,mnt} := qz_{ICE} \cdot qz_{AT\&T} \cdot G_H \cdot C_{a,mnt} \cdot A_{ICE,mnt} = 208$ lbs **BLC 4**

Gravity Load (without ice)

Weight of Mount =

$WT_{mnt} = 610$ lbs **BLC 2**

Gravity Loads (ice only)

Weight of Ice on Mount =

$WT_{ICE,mnt} - WT_{mnt} = 90$ lbs **BLC 3**

Development of Wind & Ice Load on Coax Cables

Existing Coax Cable Data:

Coax Type =
 Shape =
 Coax Outside Diameter =
 Coax Cable Length =
 Weight of Coax per foot =
 Total Number of Coax =
 No. of Coax Projecting Outside Face of PCS Mast =

Coax aspect ratio,

Coax Cable Force Factor Coefficient =

per TIA/EIA-222-F-96 Criteria

(Sprint)

HELIAX 1-1/4"

Round (User Input)

$D_{\text{coax}} := 1.55$ in (User Input)

$L_{\text{coax}} := 64$ ft (User Input)


$Wt_{\text{coax}} := 0.66$ plf (User Input)

$N_{\text{coax}} := 6$ (User Input)

$NP_{\text{coax}} := 1$ (User Input)

$$Ar_{\text{coax}} := \frac{(L_{\text{coax}}^{12})}{D_{\text{coax}}} = 495.5$$

$Ca_{\text{coax}} = 1.2$ TIA/EIA-222-F-96 Table 3



Note: AT&T Existing/Proposed
 cables attached to CL&P Pole

Wind Load (without ice)

Coax projected surface area =

per TIA/EIA-222-F-96 Section 2.3.2

$$A_{\text{coax}} := \frac{(NP_{\text{coax}} D_{\text{coax}})}{12} = 0.1 \text{ ft}$$

Total Coax Wind Force =

$$F_{\text{coax}} := Ca_{\text{coax}} qz_{\text{coax}} G_H A_{\text{coax}} = 6 \text{ plf} \quad \text{BLC 5}$$

Wind Load (with ice)

per TIA/EIA-222-F-96 Section 2.3.2

Coax projected surface area w/ Ice =

$$A_{\text{ICE}_{\text{coax}}} := \frac{(NP_{\text{coax}} D_{\text{coax}} + 2 \cdot Ir)}{12} = 0.2 \text{ ft}$$

Total Coax Wind Force w/ Ice =

$$F_{\text{ICE}_{\text{coax}}} := Ca_{\text{coax}} qz_{\text{ICE}_{\text{coax}}} G_H A_{\text{ICE}_{\text{coax}}} = 8 \text{ plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of all cables w/o ice

$$WT_{\text{coax}} := Wt_{\text{coax}} N_{\text{coax}} = 4 \text{ plf} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Ice Area per Linear Foot =

$$Ai_{\text{coax}} := \frac{\pi}{4} \left[(D_{\text{coax}} + 2 \cdot Ir)^2 - D_{\text{coax}}^2 \right] = 3.2 \text{ sq in}$$

Ice Weight All Coax per foot =

$$WT_{\text{ICE}_{\text{coax}}} := N_{\text{coax}} \cdot Id \cdot \frac{Ai_{\text{coax}}}{144} = 8 \text{ plf} \quad \text{BLC 3}$$

Development of Wind & Ice Load on Brace Member

Member Data:

Shape =

Step Bolts

Round

(User Input)

Diameter =

$D_{mem} := 2.38$ in

(User Input)

Length =

$L_{mem} := 2$ ft

(User Input)


Spacing =

$Sp_{mem} := 1.25$ ft

(User Input)

Weight =

$Wt_{mem} := 3.66$ plf



Member Aspect Ratio =

$$Ar_{mem} := \frac{D_{mem}}{L_{mem} \cdot 12} = 0.1$$

Member Force Coefficient =

$Ca_{mem} = 1.4$

(per TIA/EIA-222-F-1996 Table 3)

Wind Load (without ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Member Projected Surface Area =

$$A_{mem} := \frac{D_{mem} \cdot L_{mem}}{12 \cdot Sp_{mem}} = 0.3$$

sf/ft

Total Member Wind Force =

$$F_{mem} := qz_{mast1} \cdot G_H \cdot Ca_{mem} \cdot A_{mem} = 19$$

lbs

BLC 5

Wind Load (with ice)

(per TIA/EIA-222-F-1996 Section 2.3.2)

Member Projected Surface Area w/ Ice =

$$A_{ICEmem} := \frac{(D_{mem} + 2 \cdot Ir) \cdot (L_{mem} + 2 \cdot Ir)}{12 \cdot Sp_{mem}} = 0.7$$

plf

Total Member Wind Force w/ Ice =

$$F_{I_{mem}} := qz_{ICE_{mast1}} \cdot G_H \cdot Ca_{mem} \cdot A_{ICEmem} = 31$$

lbs

BLC 4

Gravity Load (without ice)

Weight of Member =

$$\frac{Wt_{mem} \cdot L_{mem}}{Sp_{mem}} = 6$$

lbs

BLC 2

Gravity Loads (ice only)

Ice Area per Linear foot =

$$A_{i_{mem}} := \frac{1}{4} \cdot \pi \cdot \left[(D_{mem} + 2 \cdot Ir)^2 - D_{mem}^2 \right] = 4.5$$

sq in

Weight of Ice on Member =

$$W_{ICEmem} := Id \cdot \frac{A_{i_{mem}}}{144} \cdot \frac{L_{mem}}{Sp_{mem}} = 3$$

lbs

BLC 3

CEN TEK engineering, INC. Consulting Engineers 63-2 North Branford Road Branford, CT 06405 Ph. 203-488-0580 / Fax. 203-488-8587	Subject: Analysis of TIA/EIA Wind and Ice Loads for Analysis of Mast Only Tabulated Load Cases Location: Brookfield, CT Date: 6/15/11	Prepared by: T.J.L. Checked by: C.F.C. Job No. 11021.CO50
Load Case	Description	
1	Self Weight (Mast)	
2	Weight of Appurtenances	
3	Weight of Ice Only on PCS Structure ⁽¹⁾	
4	TIA/EIA Wind with Ice on PCS Structure ⁽¹⁾	
5	TIA/EIA Wind on PCS Structure ⁽¹⁾	
Footnotes: (1) PCS Structure includes: Mast and Appurtenances		

CENTEK engineering, INC. Consulting Engineers 63-2 North Branford Road Branford, CT 06405 Ph. 203-488-0580 / Fax. 203-488-8587														Subject: Analysis of TIA/EIA Wind and Ice Loads for Analysis of Mast Only Load Combinations Table Location: Brookfield, CT Date: 6/16/11 Prepared by: T.J.L. Checked by: C.F.C. Job No. 11021.CO50																	
Load Combination		Description										Envelope Wind																			
1		TIA/EIA Wind + Ice on PCS Structure										Soutlion Factor		1		1		1		2		1		3		1		4		1	
2		TIA/EIA Wind on PCS Structure										1		1		1		2		1		5		1							
Footnotes: (1) BLC = Basic Load Case (2) PCS Structure includes: Mast and Apputenances																															

Company : CENTEK Engineering, INC.
 Designer : elb, cfc
 Job Number : 11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

June 15, 2011
 2:35 PM
 Checked By: _____

Global

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation	Yes
Include Warping	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Vertical Axis	Y
Global Member Orientation Plane	XZ

Hot Rolled Steel Code	AISC 9th: ASD
Cold Formed Steel Code	AISI 1999: ASD
Wood Code	AF&PA NDS-97: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-02
Masonry Code	ACI 530-05/08: ASD
Aluminum Code	AA ADM1-05: ASD

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	PCA Load Contour
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections	Yes
Bad Framing Warnings	No
Unused Force Warnings	Yes

Seismic Code	UBC 1997
Seismic Base Elevation (ft)	Not Entered
Ct X	.035
Ct Z	.035
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	8.5
R Z	8.5
Ct Exp. X	.75
Ct Exp. Z	.75
Ca	.36
Cv	.54
Nv	1
SD1	1
SDS	1
S1	1
Occupancy Code	4
Seismic Zone	3
Use Group	I
Use Gravity Self Wt in Diaphragm Mass	Yes
Use Deck Self Wt in Diaphragm Mass	Yes
Use Lateral Self Wt in Diaphragm Mass	Yes
Seismic Detailing Code	None
Om X	1
Om Z	1
Rho X	1
Rho Z	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1E5 F)	Densi...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	58	1.2
3	A992	29000	11154	.3	.65	.49	50	1.1	58	1.2
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.3	58	1.1
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.2	58	1.1
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	58	1.2

Hot Rolled Steel Design Parameters

	Label	Shape	Len... [ft]	Lbyy[ft]	Lbzz[ft]	Lcomp top[ft]	Lcomp bot[ft]	Kyy	Kzz	Cm-...Cm-...	Cb	y s...	z s...	Funci...
1	M1	Existing...	41.583	30		30								Lateral
2	M2	Existing...	22.417	30		30								Lateral

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rules	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Existing Upper M...	PIPE 12.0	Beam	Pipe	A53 Gr. B	Typical	13.6	262	262	523
2	Existing Lower M...	HSS16X0.375	Beam	Pipe	A500 Gr.42	Typical	17.2	526	526	1050

Member Primary Data

	Label	I Joint	J Joint	K ...	Rotate(deg)	Section/Shape	Type	Design Li...	Material	Design Rules
1	M1	BOT CONN	SPLICE			Existing Lower Mast	Beam	Pipe	A500 Gr...	Typical
2	M2	SPLICE	TOP_MA...			Existing Upper Mast	Beam	Pipe	A53 Gr. B	Typical

Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Di...
1	BOT CONN	0	50	0	0	
2	TOP CONN	0	80	0	0	
3	SPLICE	0	91.583	0	0	
4	TOP MAST	0	114	0	0	
5	CL SPRINT	0	110.667	0	0	
6	CL_ATT	0	97	0	0	

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footi...
1	BOT CONN	Reaction	Reaction	Reaction		Reaction		
2	TOP CONN	Reaction	Reaction	Reaction		Reaction		

Joint Loads and Enforced Displacements (BLC 2 : Weight of Appurtenances)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...
1	CL SPRINT	L	Y	-.054
2	CL SPRINT	L	Y	-.263
3	CL ATT	L	Y	-.117
4	CL_ATT	L	Y	-.192
5	CL ATT	L	Y	-.085
6	CL_ATT	L	Y	-.054
7	CL_ATT	L	Y	-.61

Joint Loads and Enforced Displacements (BLC 3 : Weight of Ice Only on PCS Struct)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...
--	-------------	-------	-----------	--

Joint Loads and Enforced Displacements (BLC 3 : Weight of Ice Only on PCS Struct) (Continued)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...]
1	CL_SPRINT	L	Y	-.067
2	CL_SPRINT	L	Y	-.037
3	CL_ATT	L	Y	-.098
4	CL_ATT	L	Y	-.142
5	CL_ATT	L	Y	-.043
6	CL_ATT	L	Y	-.017
7	CL_ATT	L	Y	-.09

Joint Loads and Enforced Displacements (BLC 4 : TIA/EIA Wind with Ice on PCS Str)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...]
1	CL_SPRINT	L	X	.501
2	CL_ATT	L	X	.632
3	CL_ATT	L	X	.892
4	CL_ATT	L	X	.295
5	CL_ATT	L	X	.079
6	CL_ATT	L	X	.208

Joint Loads and Enforced Displacements (BLC 5 : TIA/EIA Wind on PCS Structure)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...]
1	CL_SPRINT	L	X	.577
2	CL_ATT	L	X	.751
3	CL_ATT	L	X	1.072
4	CL_ATT	L	X	.329
5	CL_ATT	L	X	.082
6	CL_ATT	L	X	.238

Member Point Loads

Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
No Data to Print ...			

Member Distributed Loads (BLC 2 : Weight of Appurtenances)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,...]	Start Location[ft,%]	End Location[ft,%]
1	M1	Y	-.004	-.004	0	0
2	M2	Y	-.004	-.004	0	0
3	M1	Y	-.006	-.006	36	0
4	M2	Y	-.006	-.006	0	10

Member Distributed Loads (BLC 3 : Weight of Ice Only on PCS Struct)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,...]	Start Location[ft,%]	End Location[ft,%]
1	M1	Y	-.01	-.01	0	0
2	M2	Y	-.008	-.008	0	0
3	M1	Y	-.008	-.008	0	0
4	M2	Y	-.008	-.008	0	0
5	M1	Y	-.003	-.003	36	0
6	M2	Y	-.003	-.003	0	10

Member Distributed Loads (BLC 4 : TIA/EIA Wind with Ice on PCS Str)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,...]	Start Location[ft,%]	End Location[ft,%]
1	M1	X	.05	.05	0	0
2	M2	X	.042	.042	0	0
3	M1	X	.008	.008	0	0
4	M2	X	.008	.008	0	0
5	M1	X	.031	.031	36	0

Member Distributed Loads (BLC 4 : TIA/EIA Wind with Ice on PCS Str) (Continued)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft,%]	End Location[ft,%]
6	M2	X	.031	.031	0	10

Member Distributed Loads (BLC 5 : TIA/EIA Wind on PCS Structure)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft,%]	End Location[ft,%]
1	M1	X	.062	.062	0	0
2	M2	X	.051	.051	0	0
3	M1	X	.006	.006	0	0
4	M2	X	.006	.006	0	0
5	M1	X	.019	.019	36	0
6	M2	X	.019	.019	0	10

Basic Load Cases

	BLC Description	Category	X Gr...	Y Gr...	Z Gr...	Joint Po...	Distrib...	Area(Me...	Surf...
1	Self Weight (PCS Mast)	None		-1					
2	Weight of Appurtenances	None				7	4		
3	Weight of Ice Only on PCS Struct	None				7	6		
4	TIA/EIA Wind with Ice on PCS Str	None				6	6		
5	TIA/EIA Wind on PCS Structure	None				6	6		

Load Combinations

	Description	Solve	PDel...	SR...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
1	TIA/EIA Wind + Ice on PCS Structure	Yes			1	1	2	1	3	1	4	1						
2	TIA/EIA Wind on PCS Structure	Yes			1	1	2	1	5	1								
3	Self Weight				1	1												

Envelope Member Section Forces

	Member	Sec		Axial[k]	LC	y Shear[k]	LC z Shear...	LC Torque[...	LC y-y Mo...	LC z-z Mom...	LC
1	M1	1	max	1.208	1	-2.039	1	0	1	0	1
2			min	.938	2	-2.23	2	0	1	0	1
3		2	max	.371	1	-2.642	1	0	1	0	1
4			min	.288	2	-2.936	2	0	1	0	1
5		3	max	-.362	2	-3.245	1	0	1	0	1
6			min	-.466	1	-3.643	2	0	1	0	1
7		4	max	4.332	1	5.33	2	0	1	0	1
8			min	3.246	2	4.814	1	0	1	0	1
9		5	max	3.445	1	4.517	2	0	1	0	1
10			min	2.562	2	4.038	1	0	1	0	1
11	M2	1	max	3.445	1	4.517	2	0	1	0	1
12			min	2.562	2	4.038	1	0	1	0	1
13		2	max	1.575	1	1.619	2	0	1	0	1
14			min	1.189	2	1.478	1	0	1	0	1
15		3	max	1.164	1	1.216	2	0	1	0	1
16			min	.881	2	1.061	1	0	1	0	1
17		4	max	.792	1	.896	2	0	1	0	1
18			min	.599	2	.781	1	0	1	0	1
19		5	max	0	1	0	1	0	1	0	1
20			min	0	1	0	1	0	1	0	1

Envelope Member Section Stresses

	Member	Sec		Axial[... LC	y Shear[ksi]	LC z Shear[ksi]	LC y-Top[ksi]	LC y-Bot[ksi]	LC z-Top[ksi]	LC z-Bot[ksi]	LC
1	M1	1	max	.07	1	-.237	1	0	1	0	1

Envelope Member Section Stresses (Continued)

	Member	Sec		Axial[... LC	y Shear[ksi]	LC z Shear[ksi]	LC y-Top[ksi]	LC y-Bot[ksi]	LC z-Top[ksi]	LC z-Bot[ksi]	LC
2			min	.055	2	-.259	2	0	1	0	1
3		2	max	.022	1	-.307	1	0	1	-4.44	1
4			min	.017	2	-.341	2	0	1	-4.901	2
5		3	max	-.021	2	-.377	1	0	1	-10.025	1
6			min	-.027	1	-.424	2	0	1	-11.143	2
7		4	max	.252	1	.62	2	0	1	-14.876	1
8			min	.189	2	.56	1	0	1	-16.629	2
9		5	max	.2	1	.525	2	0	1	-6.403	1
10			min	.149	2	.47	1	0	1	-7.241	2
11	M2	1	max	.253	1	.664	2	0	1	-10.244	1
12			min	.188	2	.594	1	0	1	-11.584	2
13		2	max	.116	1	.238	2	0	1	-4.123	1
14			min	.087	2	.217	1	0	1	-4.677	2
15		3	max	.086	1	.179	2	0	1	-2.069	1
16			min	.065	2	.156	1	0	1	-2.372	2
17		4	max	.058	1	.132	2	0	1	-.562	1
18			min	.044	2	.115	1	0	1	-.644	2
19		5	max	0	1	0	1	0	1	0	1
20			min	0	1	0	1	0	1	0	1

Envelope Joint Reactions

	Joint		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	BOT CONN	max	2.23	2	1.208	1	0	1	0	1	0	1	0	1
2		min	2.039	1	.938	2	0	1	0	1	0	1	0	1
3	TOP CONN	max	-8.662	1	5.636	1	0	1	0	1	0	1	0	1
4		min	-9.68	2	4.258	2	0	1	0	1	0	1	0	1
5	Totals:	max	-6.623	1	6.844	1	0	1						
6		min	-7.45	2	5.196	2	0	1						

Envelope Joint Displacements

Joint			X [in]	LC	Y [in]	LC	Z [in]	LC	X Rotation...	LC	Y Rotation...	LC	Z Rotation ...	LC
1	BOT CONN	max	0	1	0	2	0	1	0	1	0	1	3.847e-3	2
2		min	0	2	0	1	0	1	0	1	0	1	3.474e-3	1
3	TOP CONN	max	0	2	0	2	0	1	0	1	0	1	-7.651e-3	1
4		min	0	1	0	1	0	1	0	1	0	1	-8.513e-3	2
5	SPLICE	max	1.778	2	0	2	0	1	0	1	0	1	-1.425e-2	1
6		min	1.595	1	-.001	1	0	1	0	1	0	1	-1.592e-2	2
7	TOP MAST	max	7.043	2	-.002	2	0	1	0	1	0	1	-1.844e-2	1
8		min	6.294	1	-.002	1	0	1	0	1	0	1	-2.068e-2	2
9	CL SPRINT	max	6.216	2	-.002	2	0	1	0	1	0	1	-1.844e-2	1
10		min	5.556	1	-.002	1	0	1	0	1	0	1	-2.068e-2	2
11	CL ATT	max	2.922	2	-.001	2	0	1	0	1	0	1	-1.677e-2	1
12		min	2.617	1	-.002	1	0	1	0	1	0	1	-1.877e-2	2

Envelope AISC ASD Steel Code Checks

	Member	Shape	Code Check	Loc[ft]	L...Shear Ch...	Loc[ft]	...LC Fa...	Ft ...	Fb y-y [ksi]	Fb.....	AS...
1	M1	HSS16X0....	.641	29.888	2	.037	30.321	2 15...25.2	27.72	27...1.6	H2...
2	M2	PIPE 12.0	.510	0	2	.047	0	2 14...21	23.1	23.1...6	H1...

Company : CENTEK Engineering, INC.
Designer : elb, cfc
Job Number : 11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

June 15, 2011

2:38 PM

Checked By: _____

Joint Reactions

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	1	BOT_CONN	2.039	1.208	0	0	0	0
2	1	TOP_CONN	-8.662	5.636	0	0	0	0
3	1	Totals:	-6.623	6.844	0			
4	1	COG (ft):	X: 0	Y: 86.208	Z: 0			


Company : CENTEK Engineering, INC.
Designer : elb, cfc
Job Number : 11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

June 15, 2011
2:39 PM
Checked By: _____

Joint Reactions

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	2	BOT_CONN	2.23	.938	0	0	0	0
2	2	TOP_CONN	-9.68	4.258	0	0	0	0
3	2	Totals:	-7.45	5.196	0			
4	2	COG (ft):	X: 0	Y: 85.917	Z: 0			



Code Check	
	No Calc
	> 1.0
	90-1.0
	75-90
	.50-.75
	0-.50



Solution: Envelope

CEN TEK Engineering, INC.

elb, cfc


11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

Unity Check


June 15, 2011 at 2:35 PM

2185 EIA-TIA Loads.r3d




Loads: LC 1, TIA/EIA Wind + Ice on PCS Structure

CEN TEK Engineering, INC.		
elb, cfc	CL&P # 2683 - Mast	June 15, 2011 at 2:36 PM
11021.CO50 /AT&T 2185	LC # 1 Loads	2185 EIA-TIA Loads.r3d





Code Check	
	No Calc
	> 1.0
	.90-1.0
	.75-.90
	.50-.75
	0-.50



Results for LC 1, TIA/EIA Wind + Ice on PCS Structure
Z-moment Reaction units are k and k-ft

CENTEK Engineering, INC.	CL&P # 2683 - Mast LC # 1 Reactions and Deflected Shape	
elb, cfc		June 15, 2011 at 2:37 PM
11021.CO50 /AT&T 2185		2185 EIA-TIA Loads.r3d



Loads: LC 2, TIA/EIA Wind on PCS Structure

CEN TEK Engineering, INC.

elb, cfc


11021.CO50 /AT&T 2185

CL&P # 2683 - Mast


LC # 2 Loads

June 15, 2011 at 2:36 PM

2185 EIA-TIA Loads.r3d



Code Check	
	No Calc
	> 1.0
	90-1.0
	.75-.90
	.50-.75
	0-.50



Results for LC 2, TIA/EIA Wind on PCS Structure
Z-moment Reaction units are k and k-ft

CEN TEK Engineering, INC.

elb, cfc

11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

LC # 2 Reactions and Deflected Shape

June 15, 2011 at 2:38 PM

2185 EIA-TIA Loads.r3d

Mast Connection to CL&P Tower:

Reactions:

Moment =	Moment := 0-kips	(Input From Risa-3D)
Vertical =	Vertical := 4.3-kips	(Input From Risa-3D)
Horizontal x-dir =	Horizontal _x := 9.7-kips	(Input From Risa-3D)
Horizontal z-dir =	Horizontal _z := 9.7-kips	(Input From Risa-3D)

Bolt Data:

Bolt Type =	ASTM A325	(User Input)
Bolt Diameter =	D := 0.625-in	(User Input)
Number of Bolts =	N _b := 4	(User Input)
Allowable Tensile Strength =	F _t := 13.8-kips	(User Input)
Allowable Shear Strength =	F _v := 7.36-kips	(User Input)

$$\text{Shear Force} = f_v := \frac{\sqrt{\text{Horizontal}_z^2 + \text{Vertical}^2}}{N_b} = 2.7\text{-kips}$$

$$\text{Bolt Shear \% of Capacity} = \frac{f_v}{F_v} = 36.04\%$$

$$\text{Check Bolt Shear} = \text{Bolt_Shear} := \text{if} \left(\frac{f_v}{F_v} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Bolt_Shear = "OK"

$$\text{Tension Force} = f_t := \frac{\text{Horizontal}_x}{N_b} = 2.4\text{-kips}$$

$$\text{Bolt Tension \% of Capacity} = \frac{f_t}{F_t} = 17.57\%$$

$$\text{Check Bolt Tension} = \text{Bolt_Tension} := \text{if} \left(\frac{f_t}{F_t} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Bolt_Tension = "OK"

Basic Components

Heavy Wind Pressure =	p := 4.00	psf	(User Input NESC 2007 Figure 250-1 & Table 250-1)
Basic Windspeed =	V := 100	mph	(User Input NESC 2007 Figure 250-2(e))
Radial Ice Thickness =	Ir := 0.50	in	(User Input)
Radial Ice Density =	Id := 56.0	pcf	(User Input)

Factors for Extreme Wind Calculation

Elevation of Top of PCS Mast Above Grade =	TME := 114	ft	(User Input)
Multiplier Gust Response Factor =	m := 1.25		(User Input - Only for NESC Extreme wind case)
NESC Factor =	kv := 1.43		(User Input from NESC 2007 Table 250-3 equation)
Importance Factor =	I := 1.0		(User Input from NESC 2007 Section 250.C.2)
Velocity Pressure Coefficient =	$Kz := 2.01 \cdot \left(\frac{TME}{900} \right)^{\frac{9.5}{2}} = 1.301$		(NESC 2007 Table 250-2)
Exposure Factor =	$Es := 0.346 \left[\frac{33}{(0.67 \cdot TME)} \right]^{\frac{1}{7}} = 0.307$		(NESC 2007 Table 250-3)
Response Term =	$Bs := \frac{1}{\left(1 + 0.375 \cdot \frac{TME}{220} \right)} = 0.837$		(NESC 2007 Table 250-3)
Gust Response Factor =	$Grf := \frac{\left[1 + \left(2.7 \cdot Es \cdot Bs^{\frac{1}{2}} \right) \right]}{kv^2} = 0.86$		(NESC 2007 Table 250-3)
Wind Pressure =	$qz := 0.00256 \cdot Kz \cdot V^2 \cdot Grf \cdot I = 28.6$	psf	(NESC 2007 Section 250.C.2)

Shape Factors

Shape Factor for Round Members =	Cd _R := 1.3	(User Input)
Shape Factor for Flat Members =	Cd _F := 1.6	(User Input)
Shape Factor for Coax Cables Attached to Outside of Pole =	Cd _{coax} := 1.45	(User Input)

Overload Factors

NU Design Criteria Table

Overload Factors for Wind Loads:

NESC Heavy Loading =	2.5	(User Input)	Apply in Risa-3D Analysis
NESC Extreme Loading =	1.0	(User Input)	Apply in Risa-3D Analysis

Overload Factors for Vertical Loads:

NESC Heavy Loading =	1.5	(User Input)	Apply in Risa-3D Analysis
NESC Extreme Loading =	1.0	(User Input)	Apply in Risa-3D Analysis

Development of Wind & Ice Load on PCS Mast

Existing Upper PCS Mast Data:

(Pipe 12 STD)

Mast Shape =	Round	(User Input)
Mast Diameter =	$D_{\text{mast}} := 12.8$ in	(User Input)
Mast Length =	$L_{\text{mast}} := 22.417$ ft	(User Input)
Mast Thickness =	$t_{\text{mast}} := 0.375$ in	(User Input)

Wind Load (NESC Extreme)

Mast Projected Surface Area =	$A_{\text{mast}} := \frac{D_{\text{mast}}}{12} = 1.067$	sf/ft
-------------------------------	---	-------

Total Mast Wind Force (Above NU Structure) =	$qz \cdot C_d \cdot R \cdot A_{\text{mast}} \cdot m = 50$	plf BLC 5
--	---	------------------

Wind Load (NESC Heavy)

Mast Projected Surface Area w/ Ice =	$A_{\text{ICE mast}} := \frac{(D_{\text{mast}} + 2 \cdot I_r)}{12} = 1.15$	sf/ft
--------------------------------------	--	-------

Total Mast Wind Force w/ Ice =	$p \cdot C_d \cdot R \cdot A_{\text{ICE mast}} = 6$	plf BLC 4
--------------------------------	---	------------------

Gravity Loads (without ice)

Weight of the mast =	Self Weight (Computed internally by Risa-3D)	plf BLC 1
----------------------	--	------------------

Gravity Loads (ice only)

Ice Area per Linear Foot =	$A_{\text{mast}} := \frac{\pi}{4} \left[(D_{\text{mast}} + I_r \cdot 2)^2 - D_{\text{mast}}^2 \right] = 20.9$	sq in
----------------------------	--	-------

Weight of Ice on Mast =	$W_{\text{ICE mast}} := I_d \cdot \frac{A_{\text{mast}}}{144} = 8$	plf BLC 3
-------------------------	--	------------------

Development of Wind & Ice Load on PCS Mast

Existing Lower PCS Mast Data:

HSS16.0x0.375

Mast Shape = Round (User Input)
Mast Diameter = $D_{\text{mast}} := 16.0$ in (User Input)
Mast Length = $L_{\text{mast}} := 41.583$ ft (User Input)
Mast Thickness = $t_{\text{mast}} := 0.375$ in (User Input)

Wind Load (NESC Extreme)

Mast Projected Surface Area =

$$A_{\text{mast}} := \frac{D_{\text{mast}}}{12} = 1.333 \quad \text{sf/ft}$$

Total Mast Wind Force (Below NU Structure) =

$$qz \cdot C_d \cdot R \cdot A_{\text{mast}} = 50 \quad \text{plf} \quad \text{BLC 5}$$

Wind Load (NESE Heavy)

Mast Projected Surface Area w/ Ice =

$$A_{\text{ICE mast}} := \frac{(D_{\text{mast}} + 2 \cdot I_r)}{12} = 1.417 \quad \text{sf/ft}$$

Total Mast Wind Force w/ Ice =

$$p \cdot C_d \cdot R \cdot A_{\text{ICE mast}} = 7 \quad \text{plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of the mast =

Self Weight (Computed internally by Risa-3D) plf **BLC 1**

Gravity Loads (ice only)

Ice Area per Linear Foot =


$$A_{\text{ice mast}} := \frac{\pi}{4} \left[(D_{\text{mast}} + I_r \cdot 2)^2 - D_{\text{mast}}^2 \right] = 25.9 \quad \text{sq in}$$

Weight of Ice on Mast =

$$W_{\text{ICE mast}} := I_d \cdot \frac{A_{\text{ice mast}}}{144} = 10 \quad \text{plf} \quad \text{BLC 3}$$

Development of Wind & Ice Load on Antennas**Existing Antenna Data:**

Antenna Model =	RR90-17-XXDP	(Sprint)
Antenna Shape =	Flat	(User Input)
Antenna Height =	$L_{ant} := 56.0$	in (User Input)
Antenna Width =	$W_{ant} := 8.0$	in (User Input)
Antenna Thickness =	$T_{ant} := 2.75$	in (User Input)
Antenna Weight =	$WT_{ant} := 18.0$	lbs (User Input)
Number of Antennas =	$N_{ant} := 3$	(User Input)

**Wind Load (NESC Extreme)**

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 3.1 \quad \text{sf}$$

Antenna Projected Surface Area =

$$A_{ant} := SA_{ant} \cdot N_{ant} = 9.3 \quad \text{sf}$$

Total Antenna Wind Force =

$$F_{ant} := qz \cdot C_d \cdot F \cdot A_{ant} \cdot m = 535 \quad \text{lbs} \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

*Assumes Maximum Possible Wind Pressure
Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 3.6 \quad \text{sf}$$

Antenna Projected Surface Area w/ Ice =

$$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 10.7 \quad \text{sf}$$

Total Antenna Wind Force w/ Ice =

$$F_{ant} := p \cdot C_d \cdot F \cdot A_{ICEant} = 68 \quad \text{lbs} \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 54 \quad \text{lbs} \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each Antenna =

$$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 1232 \quad \text{cu in}$$

Volume of Ice on Each Antenna =

$$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 692 \quad \text{cu in}$$

Weight of Ice on Each Antenna =

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_d = 22 \quad \text{lbs}$$

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 67 \quad \text{lbs} \quad \text{BLC 3}$$

Development of Wind & Ice Load on Antenna Mounts**Mount Data:**

Mount Type:

(Sprint)

Microflex Universal Tri-Bracket

Mount Shape =

Flat

(User Input)

Pipe Mount Length =

 $L_{mnt} := 72$ in (User Input)

2 inch Pipe Mount Linear Weight =

 $W_{mnt} := 3.66$ plf (User Input)


Pipe Mount Outside Diameter =

 $D_{mnt} := 2.375$ in (User Input)

Number of Mounting Pipes =

 $N_{mnt} := 3$ (User Input)

Tri-Bracket Weight =

 $W_{tb.mnt} := 197$ lbs (User Input)**Wind Load (NESC Extreme)***Assumes Mount is Shielded by Antenna*

Mount Projected Surface Area =

 $A_{mnt} := 0.0$

sf

Total Mount Wind Force =

 $F_{mnt} := qz \cdot C_d F \cdot A_{mnt} \cdot m = 0$

lbs

BLC 5**Wind Load (NESC Heavy)***Assumes Mount is Shielded by Antenna*

Mount Projected Surface Area w/ Ice =

 $A_{ICEmnt} := 0.0$

sf

Total Mount Wind Force =

 $F_{mnt} := p \cdot C_d F \cdot A_{ICEmnt} = 0$

lbs

BLC 4**Gravity Loads (without ice)**

Weight Each Pipe Mount =

 $WT_{mnt} := W_{mnt} \cdot \frac{L_{mnt}}{12} = 22$

lbs

Weight of All Mounts =

 $WT_{mnt} \cdot N_{mnt} + W_{tb.mnt} = 263$

lbs

BLC 2**Gravity Load (ice only)**

Volume of Each Pipe =

 $V_{mnt} := \frac{\pi}{4} \cdot D_{mnt}^2 \cdot L_{mnt} = 319$

cu in

Volume of Ice on Each Pipe =

 $V_{ice} := \left[\frac{\pi}{4} \cdot (D_{mnt} + 1)^2 \cdot (L_{mnt} + 1) \right] - V_{mnt} = 334$

cu in

Weight of Ice each mount (incl. hardware) =

 $W_{ICEmnt} := \frac{V_{ice}}{1728} \cdot \rho = 11$

lbs

Weight of Ice on All Mounts =

 $W_{ICEmnt} \cdot N_{mnt} + 5 = 37$

lbs

BLC 3

Development of Wind & Ice Load on Antennas


Existing Antenna Data:

Antenna Model =
 Antenna Shape =
 Antenna Height =
 Antenna Width =
 Antenna Thickness =
 Antenna Weight =
 Number of Antennas =

(AT&T)

Powerwave 7770.00

Flat (User Input)
 $L_{ant} := 55$ in (User Input)
 $W_{ant} := 11.0$ in (User Input)
 $T_{ant} := 5$ in (User Input)
 $WT_{ant} := 39$ lbs (User Input)
 $N_{ant} := 3$ (User Input)



Wind Load (NESC Extreme)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 4.2 \quad sf$$

Antenna Projected Surface Area =

$$A_{ant} := SA_{ant} \cdot N_{ant} = 12.6 \quad sf$$

Total Antenna Wind Force =

$$F_{ant} := qz \cdot C_d \cdot A_{ant} \cdot m = 722 \quad lbs \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 4.7 \quad sf$$

Antenna Projected Surface Area w/ Ice =

$$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 14 \quad sf$$

Total Antenna Wind Force w/ Ice =

$$F_{ant} := p \cdot C_d \cdot A_{ICEant} = 90 \quad lbs \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 117 \quad lbs \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each Antenna =

$$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 3025 \quad cu \text{ in}$$

Volume of Ice on Each Antenna =

$$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1007 \quad cu \text{ in}$$

Weight of Ice on Each Antenna =

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot Id = 33 \quad lbs$$

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 98 \quad lbs \quad \text{BLC 3}$$

Development of Wind & Ice Load on Antennas

Proposed Antenna Data:

Antenna Model =
 Antenna Shape =
 Antenna Height =
 Antenna Width =
 Antenna Thickness =
 Antenna Weight =
 Number of Antennas =

(AT&T)

Powerwave P65-16-XLH-RR

Flat (User Input)


$L_{ant} := 72$ in (User Input)

$W_{ant} := 12$ in (User Input)

$T_{ant} := 6$ in (User Input)

$WT_{ant} := 64$ lbs (User Input)

$N_{ant} := 3$ (User Input)



Wind Load (NESC Extreme)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna =

$$SA_{ant} := \frac{L_{ant} \cdot W_{ant}}{144} = 6 \quad sf$$

Antenna Projected Surface Area =

$$A_{ant} := SA_{ant} \cdot N_{ant} = 18 \quad sf$$

Total Antenna Wind Force =

$$F_{ant} := qz \cdot Cd_F \cdot A_{ant} \cdot m = 1031 \quad lbs \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

*Assumes Maximum Possible Wind Pressure
 Applied to all Antennas Simultaneously*

Surface Area for One Antenna w/ Ice =

$$SA_{ICEant} := \frac{(L_{ant} + 1) \cdot (W_{ant} + 1)}{144} = 6.6 \quad sf$$

Antenna Projected Surface Area w/ Ice =

$$A_{ICEant} := SA_{ICEant} \cdot N_{ant} = 19.8 \quad sf$$

Total Antenna Wind Force w/ Ice =

$$F_{ant} := p \cdot Cd_F \cdot A_{ICEant} = 127 \quad lbs \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All Antennas =

$$WT_{ant} \cdot N_{ant} = 192 \quad lbs \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each Antenna =

$$V_{ant} := L_{ant} \cdot W_{ant} \cdot T_{ant} = 5184 \quad cu \text{ in}$$

Volume of Ice on Each Antenna =

$$V_{ice} := (L_{ant} + 1) \cdot (W_{ant} + 1) \cdot (T_{ant} + 1) - V_{ant} = 1459 \quad cu \text{ in}$$

Weight of Ice on Each Antenna =

$$W_{ICEant} := \frac{V_{ice}}{1728} \cdot \rho_{ice} = 47 \quad lbs$$

Weight of Ice on All Antennas =

$$W_{ICEant} \cdot N_{ant} = 142 \quad lbs \quad \text{BLC 3}$$

Subject:

Load Analysis of Pipe Mast on CL&P
 Structure #2683

Location:

Brookfield, CT

Rev. 0: 6/14/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 10021.CO50

Development of Wind & Ice Load on TMA's


Existing TMA Data:

TMA Model =
 TMA Shape =
 TMA Height =
 TMA Width =
 TMA Thickness =
 TMA Weight =
 Number of TMA's =

(AT&T)

Powerwave LGP 21401

Flat (User Input)
 $L_{TMA} := 14.4$ in (User Input)
 $W_{TMA} := 9.2$ in (User Input)
 $T_{TMA} := 2.6$ in (User Input)
 $WT_{TMA} := 14.1$ lbs (User Input)
 $N_{TMA} := 6$ (User Input)



Wind Load (NESC Extreme)

*Assumes Maximum Possible Wind Pressure
 Applied to All TMA's Simultaneously*

Surface Area for One TMA =

$$SA_{TMA} := \frac{L_{TMA} \cdot W_{TMA}}{144} = 0.9 \quad \text{sf}$$

TMA Projected Surface Area =

$$A_{TMA} := SA_{TMA} \cdot N_{TMA} = 5.5 \quad \text{sf}$$

Total TMA Wind Force =

$$F_{TMA} := qz \cdot C_d \cdot F \cdot A_{TMA} \cdot m = 316 \quad \text{lbs} \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

*Assumes Maximum Possible Wind Pressure
 Applied to All TMA's Simultaneously*

Surface Area for One TMA w/ Ice =

$$SA_{ICETMA} := \frac{(L_{TMA} + 1) \cdot (W_{TMA} + 1)}{144} = 1.1 \quad \text{sf}$$

TMA Projected Surface Area w/ Ice =

$$A_{ICETMA} := SA_{ICETMA} \cdot N_{TMA} = 6.5 \quad \text{sf}$$

Total TMA Wind Force w/ Ice =

$$F_{ITMA} := p \cdot C_d \cdot F \cdot A_{ICETMA} = 42 \quad \text{lbs} \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All TMA's =

$$WT_{TMA} \cdot N_{TMA} = 85 \quad \text{lbs} \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each TMA =

$$V_{TMA} := L_{TMA} \cdot W_{TMA} \cdot T_{TMA} = 344 \quad \text{cu in}$$

Volume of Ice on Each TMA =

$$V_{ice} := (L_{TMA} + 1) \cdot (W_{TMA} + 1) \cdot (T_{TMA} + 1) - V_{TMA} = 221 \quad \text{cu in}$$

Weight of Ice on Each TMA =

$$W_{ICETMA} := \frac{V_{ice}}{1728} \cdot \rho_{ice} = 7 \quad \text{lbs}$$

Weight of Ice on All TMA's

$$W_{ICETMA} \cdot N_{TMA} = 43 \quad \text{lbs} \quad \text{BLC 3}$$

Development of Wind & Ice Load on TMA's

Proposed TMA Data:

TMA Model =
 TMA Shape =
 TMA Height =
 TMA Width =
 TMA Thickness =
 TMA Weight =
 Number of TMA's =

(AT&T)

Powerwave TTAW-07BP111-001

Flat (User Input)


$L_{TMA} := 9.9$ in (User Input)

$W_{TMA} := 6.7$ in (User Input)

$T_{TMA} := 5.4$ in (User Input)

$WT_{TMA} := 18$ lbs (User Input)

$N_{TMA} := 3$ (User Input)



Wind Load (NESC Extreme)

*Assumes Maximum Possible Wind Pressure
 Applied to All TMA's Simultaneously*

Surface Area for One TMA =

$$SA_{TMA} := \frac{L_{TMA} \cdot W_{TMA}}{144} = 0.5 \quad sf$$

TMA Projected Surface Area =

$$A_{TMA} := SA_{TMA} \cdot N_{TMA} = 1.4 \quad sf$$

Total TMA Wind Force =

$$F_{TMA} := qz \cdot C_d \cdot F \cdot A_{TMA} \cdot m = 79 \quad lbs \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

*Assumes Maximum Possible Wind Pressure
 Applied to All TMA's Simultaneously*

Surface Area for One TMA w/ Ice =

$$SA_{ICETMA} := \frac{(L_{TMA} + 1) \cdot (W_{TMA} + 1)}{144} = 0.6 \quad sf$$

TMA Projected Surface Area w/ Ice =

$$A_{ICETMA} := SA_{ICETMA} \cdot N_{TMA} = 1.7 \quad sf$$

Total TMA Wind Force w/ Ice =

$$F_{iCTMA} := p \cdot C_d \cdot F \cdot A_{ICETMA} = 11 \quad lbs \quad \text{BLC 4}$$

Gravity Load (without ice)

Weight of All TMA's =

$$WT_{TMA} \cdot N_{TMA} = 54 \quad lbs \quad \text{BLC 2}$$

Gravity Load (ice only)

Volume of Each TMA =

$$V_{TMA} := L_{TMA} \cdot W_{TMA} \cdot T_{TMA} = 358 \quad cu \text{ in}$$

Volume of Ice on Each TMA =

$$V_{ice} := (L_{TMA} + 1)(W_{TMA} + 1)(T_{TMA} + 1) - V_{TMA} = 179 \quad cu \text{ in}$$

Weight of Ice on Each TMA =

$$W_{ICETMA} := \frac{V_{ice}}{1728} \cdot \rho_{ice} = 6 \quad lbs$$

Weight of Ice on All TMA's

$$W_{ICETMA} \cdot N_{TMA} = 17 \quad lbs \quad \text{BLC 3}$$

Development of Wind & Ice Load on Mounts

Mount Data:

(AT&T)

Mount Type =

(3) Valmont Dual Standoff Mounts
 w/ Universal Tri-Bracket

Mount Shape =

Flat (User Input)

Mount Area =

$A_{mnt} := 4.0$ sq ft (User Input)

Mount Area w/ Ice =


$A_{ICEmnt} := 4.6$ sq ft (User Input)

Mount Weight =

$WT_{mnt} := 610$ lbs (User Input)

Mount Weight w/ Ice =

$WT_{ICEmnt} := 700$ lbs (User Input)



Wind Load (NESC Extreme)

Total Mount Wind Force =

$$F_{mnt} := qz \cdot C_d \cdot F \cdot A_{mnt} \cdot m = 229$$

lbs **BLC 5**

Wind Load (NESC Heavy)

Total Mount Wind Force w/ Ice =

$$F_{mnt} := p \cdot C_d \cdot F \cdot A_{ICEmnt} = 29$$

lbs **BLC 4**

Gravity Load (without ice)

Weight of Mount =

$$WT_{mnt} = 610$$

lbs **BLC 2**

Gravity Load (ice only)

Weight of Ice on Mount =

$$WT_{ICEmnt} - WT_{mnt} = 90$$

lbs **BLC 3**


Development of Wind & Ice Load on Coax Cables

Existing Coax Cable Data:

Coax Type =
 Shape =
 Coax Outside Diameter =
 Coax Cable Length =
 Weight of Coax per foot =
 Total Number of Coax =
 No. of Coax Projecting Outside Face of PCS Mast =

(Sprint)

HELIAX 1-1/4"
 Round (User Input)
 $D_{coax} := 1.55$ in (User Input)
 $L_{coax} := 64$ ft (User Input)
 $Wt_{coax} := 0.66$ plf (User Input)
 $N_{coax} := 6$ (User Input)
 $NP_{coax} := 1$ (User Input)



Note: AT&T Existing/Proposed
 cables attached to CL&P Pole

Wind Load (NESC Extreme)

Coax projected surface area =

$$A_{coax} := \frac{(NP_{coax} D_{coax})}{12} = 0.1 \quad \text{sf/ft}$$

Total Coax Wind Force (Above NU Structure) =

$$F_{coax} := qz \cdot Cd_{coax} \cdot A_{coax} \cdot m = 7 \quad \text{plf} \quad \text{BLC 5}$$

Total Coax Wind Force (Below NU Structure) =

$$F_{coax} := qz \cdot Cd_{coax} \cdot A_{coax} = 5 \quad \text{plf} \quad \text{BLC 5}$$

Wind Load (NESC Heavy)

Coax projected surface area w/ Ice =

$$A_{ICE_{coax}} := \frac{(NP_{coax} D_{coax} + 2 \cdot l_r)}{12} = 0.2 \quad \text{sf/ft}$$

Total Coax Wind Force w/ Ice =

$$F_{i_{coax}} := p \cdot Cd_{coax} \cdot A_{ICE_{coax}} = 1 \quad \text{plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of all cables w/o ice

$$WT_{coax} := Wt_{coax} \cdot N_{coax} = 4 \quad \text{plf} \quad \text{BLC 2}$$

Gravity Load (ice only)

Ice Area per Linear Foot =

$$A_{i_{coax}} := \frac{\pi}{4} \left[(D_{coax} + 2 \cdot l_r)^2 - D_{coax}^2 \right] = 3.2 \quad \text{sq in}$$

Ice Weight All Coax per foot =

$$WT_{i_{coax}} := N_{coax} \cdot l_d \cdot \frac{A_{i_{coax}}}{144} = 8 \quad \text{plf} \quad \text{BLC 3}$$


Development of Wind & Ice Load on Brace Member

Member Data:

Shape =
 Diameter =
 Length =
 Spacing =
 Weight =

Step Bolts

Round (User Input)
 $D_{mem} := 2.38$ in (User Input)
 $L_{mem} := 2$ ft (User Input)
 $S_{p_{mem}} := 1.25$ ft (User Input)
 $W_{t_{mem}} := 3.66$ plf (User Input)



Wind Load (NESC Extreme)

Member Projected Surface Area =

$$A_{mem} := \frac{D_{mem} \cdot L_{mem}}{12 \cdot S_{p_{mem}}} = 0.317 \quad \text{sf/ft}$$

Total Member Wind Force =

$$q_z \cdot C_d \cdot R \cdot A_{mem} \cdot m = 15 \quad \text{plf} \quad \text{BLC 5}$$

Wind Load (NESE Heavy)

Member Projected Surface Area w/ Ice =

$$A_{ICE_{mem}} := \frac{(D_{mem} + 2 \cdot I_r) \cdot (L_{mem} + 2 \cdot I_r)}{12 \cdot S_{p_{mem}}} = 0.676 \quad \text{sf/ft}$$

Total Member Wind Force w/ Ice =

$$p \cdot C_d \cdot R \cdot A_{ICE_{mem}} = 4 \quad \text{plf} \quad \text{BLC 4}$$

Gravity Loads (without ice)

Weight of the Member =

$$\frac{W_{t_{mem}} \cdot L_{mem}}{S_{p_{mem}}} = 6 \quad \text{plf} \quad \text{BLC 2}$$

Gravity Loads (ice only)

Ice Area per Linear Foot =

$$A_{i_{mem}} := \frac{1}{4} \cdot \pi \cdot \left[(D_{mem} + 2 \cdot I_r)^2 - D_{mem}^2 \right] = 4.5 \quad \text{sq in}$$

Weight of Ice on Member =

$$W_{ICE_{mem}} := I_d \cdot \frac{A_{i_{mem}}}{144} \cdot \frac{L_{mem}}{S_{p_{mem}}} = 3 \quad \text{plf} \quad \text{BLC 3}$$

CENTEK engineering, INC. Consulting Engineers 63-2 North Branford Road Branford, CT 06405 Ph. 203-488-0580 / Fax. 203-488-8587	Subject: Analysis of NESC Heavy Wind and NESC Extreme Wind for Obtaining PCS Structure Reactions Applied to CL&P Pole Tabulated Load Cases Location: Brookfield, CT Date:6/15/11 Prepared by: T.J.L. Checked by: C.F.C. Job No. 11021.CO50
Load Case	Description
1	Self Weight (Mast)
2	Weight of Appurtenances
3	Weight of Ice Only on PCS Structure ⁽¹⁾
4	NESC Heavy Wind on PCS Structure ⁽¹⁾
5	NESC Extreme Wind on PCS Structure ⁽¹⁾
 Footnotes: (1) PCS Structure includes: Mast and Appurtenances	

CENTEK engineering, INC. Consulting Engineers 63-2 North Branford Road Branford, CT 06405 Ph. 203-488-0580 / Fax. 203-488-8587		Subject: Analysis of NESC Heavy Wind and NESC Extreme Wind for Obtaining PCS Structure Reactions Applied to CL&P Pole Load Combinations Table Location: Brookfield, CT Date: 6/15/11 Prepared by: T.J.L. Checked by: C.F.C. Job No. 11021.CO50									
Load Combination	Description	Envelope Solution	Wind Factor	P-Delta	BLC Factor	BLC Factor	BLC Factor	BLC Factor	BLC Factor	BLC Factor	BLC Factor
1	NESC Heavy Wind on PCS Structure	1	1	1	1.5	2	1.5	3	1.5	4	2.5
2	NESC Extreme Wind on PCS Structure	1	1	1	1	2	1	5	1		
Footnotes: (1) BLC = Basic Load Case (2) PCS Structure includes: Mast and Appurtenances											

Global

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation	Yes
Include Warping	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Vertical Axis	Y
Global Member Orientation Plane	XZ

Hot Rolled Steel Code	AISC 9th: ASD
Cold Formed Steel Code	AISI 1999: ASD
Wood Code	AF&PA NDS-97: ASD
Wood Temperature	< 100F
Concrete Code	ACI 318-02
Masonry Code	ACI 530-05/08: ASD
Aluminum Code	AA ADM1-05: ASD

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	PCA Load Contour
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections	Yes
Bad Framing Warnings	No
Unused Force Warnings	Yes

Seismic Code	UBC 1997
Seismic Base Elevation (ft)	Not Entered
Ct X	.035
Ct Z	.035
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	8.5
R Z	8.5
Ct Exp. X	.75
Ct Exp. Z	.75
Ca	.36
Cv	.54
Nv	1
SD1	1
SDS	1
S1	1
Occupancy Code	4
Seismic Zone	3
Use Group	I
Use Gravity Self Wt in Diaphragm Mass	Yes
Use Deck Self Wt in Diaphragm Mass	Yes
Use Lateral Self Wt in Diaphragm Mass	Yes
Seismic Detailing Code	None
Om X	1
Om Z	1
Rho X	1
Rho Z	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1E5 F)	Densi...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	58	1.2
3	A992	29000	11154	.3	.65	.49	50	1.1	58	1.2
4	A500 Gr.42	29000	11154	.3	.65	.49	42	1.3	58	1.1
5	A500 Gr.46	29000	11154	.3	.65	.49	46	1.2	58	1.1
6	A53 Gr. B	29000	11154	.3	.65	.49	35	1.5	58	1.2

Hot Rolled Steel Design Parameters

	Label	Shape	Lengt...	Lbyy[ft]	Lbzz[ft]	Lcomp top[ft]	Lcomp bot[ft]	Kyy	Kzz	Cm-...Cm-...	Cb	y s...	z s...	Funci...
1	M1	Existing...	41.583	30		30								Lateral
2	M2	Existing...	22.417	30		30								Lateral

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rules	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Existing Upper M...	PIPE 12.0	Beam	Pipe	A53 Gr. B	Typical	13.6	262	262	523
2	Existing Lower M...	HSS16X0.375	Beam	Pipe	A500 Gr.42	Typical	17.2	526	526	1050

Member Primary Data

	Label	I Joint	J Joint	K ...	Rotate(deg)	Section/Shape	Type	Design Li...	Material	Design Rules
1	M1	BOT CONN	SPLICE			Existing Lower Mast	Beam	Pipe	A500 Gr...	Typical
2	M2	SPLICE	TOP_MA...			Existing Upper Mast	Beam	Pipe	A53 Gr. B	Typical

Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Di...
1	BOT CONN	0	50	0	0	
2	TOP CONN	0	80	0	0	
3	SPLICE	0	91.583	0	0	
4	TOP MAST	0	114	0	0	
5	CL SPRINT	0	110.667	0	0	
6	CL_ATT	0	97	0	0	

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]	Footing
1	BOT CONN	Reaction	Reaction	Reaction		Reaction		
2	TOP_CONN	Reaction	Reaction	Reaction		Reaction		

Joint Loads and Enforced Displacements (BLC 2 : Weight of Appurtenances)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...
1	CL SPRINT	L	Y	-.054
2	CL SPRINT	L	Y	-.263
3	CL ATT	L	Y	-.117
4	CL_ATT	L	Y	-.192
5	CL ATT	L	Y	-.085
6	CL_ATT	L	Y	-.054
7	CL_ATT	L	Y	-.61

Joint Loads and Enforced Displacements (BLC 3 : Weight of Ice Only on PCS Struct)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...
--	-------------	-------	-----------	--

Joint Loads and Enforced Displacements (BLC 3 : Weight of Ice Only on PCS Struct) (Continued)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...]
1	CL SPRINT	L	Y	-.067
2	CL SPRINT	L	Y	-.037
3	CL ATT	L	Y	-.098
4	CL_ATT	L	Y	-.142
5	CL ATT	L	Y	-.043
6	CL_ATT	L	Y	-.017
7	CL_ATT	L	Y	-.09

Joint Loads and Enforced Displacements (BLC 4 : NESC Heavy Wind on PCS Structure)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...]
1	CL SPRINT	L	X	.068
2	CL_ATT	L	X	.09
3	CL ATT	L	X	.127
4	CL_ATT	L	X	.042
5	CL ATT	L	X	.011
6	CL_ATT	L	X	.029

Joint Loads and Enforced Displacements (BLC 5 : NESC Extreme Wind on PCS Structu)

	Joint Label	L,D,M	Direction	Magnitude[(k,k-ft), (in,rad), (k*s^2/ft, k*ft...]
1	CL SPRINT	L	X	.535
2	CL_ATT	L	X	.722
3	CL ATT	L	X	1.031
4	CL_ATT	L	X	.316
5	CL ATT	L	X	.079
6	CL_ATT	L	X	.229

Member Point Loads

Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
No Data to Print ...			

Member Distributed Loads (BLC 2 : Weight of Appurtenances)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,...]	Start Location[ft,%]	End Location[ft,%]
1	M1	Y	-.004	-.004	0	0
2	M2	Y	-.004	-.004	0	0
3	M1	Y	-.006	-.006	36	0
4	M2	Y	-.006	-.006	0	10

Member Distributed Loads (BLC 3 : Weight of Ice Only on PCS Struct)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,...]	Start Location[ft,%]	End Location[ft,%]
1	M1	Y	-.01	-.01	0	0
2	M2	Y	-.008	-.008	0	0
3	M1	Y	-.008	-.008	0	0
4	M2	Y	-.008	-.008	0	0
5	M1	Y	-.003	-.003	36	0
6	M2	Y	-.003	-.003	0	10

Member Distributed Loads (BLC 4 : NESC Heavy Wind on PCS Structure)

	Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,...]	Start Location[ft,%]	End Location[ft,%]
1	M1	X	.007	.007	0	0
2	M2	X	.006	.006	0	0
3	M1	X	.001	.001	0	0
4	M2	X	.001	.001	0	0
5	M1	X	.004	.004	36	0

Member Distributed Loads (BLC 4 : NESC Heavy Wind on PCS Structure) (Continued)

Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft,%]	End Location[ft,%]
6 M2	X	.004	.004	0	10

Member Distributed Loads (BLC 5 : NESC Extreme Wind on PCS Structure)

Member Label	Direction	Start Magnitude[k/ft,deg]	End Magnitude[k/ft,deg]	Start Location[ft,%]	End Location[ft,%]
1 M1	X	.05	.05	0	0
2 M2	X	.05	.05	0	0
3 M1	X	.005	.005	0	0
4 M2	X	.007	.007	0	0
5 M1	X	.015	.015	36	0
6 M2	X	.015	.015	0	10

Basic Load Cases

BLC Description	Category	X Gr...	Y Gr...	Z Gr...	Joint	Po...	Distrib...	Area(Me...	Surf...
1 Self Weight (PCS Mast)	None	-1							
2 Weight of Appurtenances	None				7		4		
3 Weight of Ice Only on PCS Struct	None				7		6		
4 NESC Heavy Wind on PCS Structure	None				6		6		
5 NESC Extreme Wind on PCS Structure	None				6		6		

Load Combinations

Description	Solve	PDel...	SR...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
1 NESC Heavy Wind on PCS Structure	Yes				1	1.5	2	1.5	3	1.5	4	2.5							
2 NESC Extreme Wind on PCS Structure	Yes				1	1	2	1	5	1									
3 Self Weight					1	1													

Envelope Member Section Forces

	Member	Sec		Axial[k]	LC	y Shear[k]	LC z Shear...	LC Torque[...	LC y-y Mo...	LC z-z Mom...	LC	
1	M1	1	max	1.812	1	- .712	1	0	1	0	1	
min			.938	2	-2.27	2	0	1	0	1	0	
3		2	max	.556	1	- .92	1	0	1	0	1	
min			.288	2	-2.842	2	0	1	0	1	26.571	
5		3	max	-.362	2	-1.128	1	0	1	0	1	
min			-.7	1	-3.414	2	0	1	0	1	59.086	
7		4	max	6.498	1	4.995	2	0	1	0	1	
min			3.246	2	1.674	1	0	1	0	1	86.882	
9		5	max	5.167	1	4.34	2	0	1	0	1	
min			2.562	2	1.41	1	0	1	0	1	28.352	
11		M2	1	max	5.167	1	4.34	2	0	1	0	1
min				2.562	2	1.41	1	0	1	0	1	38.158
13	2		max	2.362	1	1.559	2	0	1	0	1	
min			1.189	2	.508	1	0	1	0	1	12.191	
15		3	max	1.746	1	1.174	2	0	1	0	1	
min			.881	2	.366	1	0	1	0	1	15.413	
17		4	max	1.189	1	.854	2	0	1	0	1	
min			.599	2	.268	1	0	1	0	1	4.862	
19		5	max	0	1	0	1	0	1	0	1	
20			min	0	1	0	1	0	1	0	1	7.794

Envelope Member Section Stresses

Member	Sec	Axial[...]	LC	y Shear[ksi]	LC	z Shear[ksi]	LC	y-Top[ksi]	LC	y-Bot[ksi]	LC	z-Top[ksi]	LC	z-Bot[ksi]	LC
1	M1	1	max	.105	1	-.083	1	0	1	0	1	0	1	0	1

Envelope Member Section Stresses (Continued)

Member	Sec	Axial...	LC	y Shear[ksi]	LC	z Shear[ksi]	LC	y-Top[ksi]	LC	y-Bot[ksi]	LC	z-Top[ksi]	LC	z-Bot[ksi]	LC
2		min	.055	2	-.264	2	0	1	0	1	0	1	0	1	0
3	2	max	.032	1	-.107	1	0	1	-1.548	1	4.85	2	0	1	0
4		min	.017	2	-.33	2	0	1	-4.85	2	1.548	1	0	1	0
5	3	max	-.021	2	-.131	1	0	1	-3.49	1	10.784	2	0	1	0
6		min	-.041	1	-.397	2	0	1	-10.784	2	3.49	1	0	1	0
7	4	max	.378	1	.581	2	0	1	-5.174	1	15.857	2	0	1	0
8		min	.189	2	.195	1	0	1	-15.857	2	5.174	1	0	1	0
9	5	max	.3	1	.505	2	0	1	-2.225	1	6.964	2	0	1	0
10		min	.149	2	.164	1	0	1	-6.964	2	2.225	1	0	1	0
11	M2	1	max	.38	1	.638	2	0	1	-3.559	1	11.142	2	0	1
12		min	.188	2	.207	1	0	1	-11.142	2	3.559	1	0	1	0
13	2	max	.174	1	.229	2	0	1	-1.42	1	4.5	2	0	1	0
14		min	.087	2	.075	1	0	1	-4.5	2	1.42	1	0	1	0
15	3	max	.128	1	.173	2	0	1	-.712	1	2.276	2	0	1	0
16		min	.065	2	.054	1	0	1	-2.276	2	.712	1	0	1	0
17	4	max	.087	1	.126	2	0	1	-.193	1	.616	2	0	1	0
18		min	.044	2	.039	1	0	1	-.616	2	.193	1	0	1	0
19	5	max	0	1	0	1	0	1	0	1	0	1	0	1	0
20		min	0	1	0	1	0	1	0	1	0	1	0	1	0

Envelope Joint Reactions

Joint	X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1 BOT CONN	max	2.27	2	1.812	1	0	1	0	1	0	1	0
2	min	.712	1	.938	2	0	1	0	1	0	1	0
3 TOP CONN	max	-3.009	1	8.453	1	0	1	0	1	0	1	0
4	min	-8.981	2	4.258	2	0	1	0	1	0	1	0
5 Totals:	max	-2.297	1	10.265	1	0	1					
6	min	-6.711	2	5.196	2	0	1					

Envelope Joint Displacements

Joint	X [in]	LC	Y [in]	LC	Z [in]	LC	X Rotation...	LC	Y Rotation...	LC	Z Rotation ...	LC
1 BOT CONN	max	0	1	0	2	0	1	0	1	0	1	3.768e-3
2	min	0	2	0	1	0	1	0	1	0	1	1.21e-3
3 TOP CONN	max	0	2	0	2	0	1	0	1	0	1	-2.663e-3
4	min	0	1	0	1	0	1	0	1	0	1	-8.212e-3
5 SPLICE	max	1.71	2	0	2	0	1	0	1	0	1	-4.959e-3
6	min	.555	1	-.002	1	0	1	0	1	0	1	-1.53e-2
7 TOP MAST	max	6.77	2	-.002	2	0	1	0	1	0	1	-6.407e-3
8	min	2.188	1	-.003	1	0	1	0	1	0	1	-1.988e-2
9 CL SPRINT	max	5.975	2	-.002	2	0	1	0	1	0	1	-6.405e-3
10	min	1.932	1	-.003	1	0	1	0	1	0	1	-1.987e-2
11 CL ATT	max	2.809	2	-.001	2	0	1	0	1	0	1	-5.832e-3
12	min	.911	1	-.002	1	0	1	0	1	0	1	-1.805e-2

Envelope AISC ASD Steel Code Checks

Member	Shape	Code Check	Loc[ft]	L...Shear Ch...	Loc[ft]	...LC Fa...Ft ...	Fb y-y [ksi]	Fb.....	AS...
1	M1 HSS16X0....	.611	29.888	2	.035	30.321	2 15...25.2	27.72	27...1.6H2...
2	M2 PIPE 12.0	.491	0	2	.046	0	2 14... 21	23.1	23.1...1.6H1...

Company : CENTEK Engineering, INC.
Designer : elb, cfc
Job Number : 11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

June 15, 2011

2:43 PM

Checked By: _____

Joint Reactions

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	1	BOT_CONN	.712	1.812	0	0	0	0
2	1	TOP_CONN	-3.009	8.453	0	0	0	0
3	1	Totals:	-2.297	10.265	0			
4	1	COG (ft):	X: 0	Y: 86.208	Z: 0			



Company : CENTEK Engineering, INC.
Designer : elb, cfc
Job Number : 11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

June 15, 2011
2:44 PM
Checked By: _____

Joint Reactions

	LC	Joint Label	X [k]	Y [k]	Z [k]	MX [k-ft]	MY [k-ft]	MZ [k-ft]
1	2	BOT_CONN	2.27	.938	0	0	0	0
2	2	TOP_CONN	-8.981	4.258	0	0	0	0
3	2	Totals:	-6.711	5.196	0			
4	2	COG (ft):	X: 0	Y: 85.917	Z: 0			



Loads: LC 1, NESC Heavy Wind on PCS Structure

CEN TEK Engineering, INC.

elb, cfc


11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

LC # 1 Loads

June 15, 2011 at 2:42 PM

2185 NESC Loads.r3d



Results for LC 1, NESC Heavy Wind on PCS Structure
Z-moment Reaction units are k and k-ft

CEN TEK Engineering, INC.

elb, cfc



11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

LC # 1 Reactions

June 15, 2011 at 2:43 PM

2185 NESC Loads.r3d



Loads: LC 2, NESC Extreme Wind on PCS Structure

CEN TEK Engineering, INC.

elb, cfc



11021.CO50 /AT&T 2185

CL&P # 2683 - Mast

LC # 2 Loads

June 15, 2011 at 2:42 PM

2185 NESC Loads.r3d



Results for LC 2, NESC Extreme Wind on PCS Structure
Z-moment Reaction units are k and k-ft

CEN TEK Engineering, INC.	CL&P # 2683 - Mast LC # 2 Reactions	
elb, cfc		June 15, 2011 at 2:43 PM
11021.CO50 /AT&T 2185		2185 NESC Loads.r3d

Coax Cable on CL&P Pole

(Below 50-ft AGL)

Distance Between Coax Cable Attach Points =

Coaxial Cable Span =

$$\text{Coax}_{\text{Span}} := \begin{pmatrix} 10 \\ 10 \\ 10 \\ 10 \\ 10 \end{pmatrix} \cdot \text{ft} \quad (\text{User Input})$$

Diameter of Coax Cable =

$$D_{\text{coax1}} := 1.55 \cdot \text{in} \quad (\text{User Input})$$

Weight of Coax Cable =

$$W_{\text{coax1}} := 0.66 \cdot \text{plf} \quad (\text{User Input})$$

Number of Coax Cables =

$$N_{\text{coax1}} := 21 \quad (\text{User Input}) \quad 15 \text{ AT\&T Cables and } 6 \text{ Sprint Cables}$$

Number of Projected Coax Cables =

$$NP_{\text{coax1}} := 3 \quad (\text{User Input})$$

Extreme Wind Pressure =

$$q_z := 28.6 \cdot \text{psf} \quad (\text{User Input})$$

Heavy Wind Pressure =

$$p := 4 \cdot \text{psf} \quad (\text{User Input})$$

Radial Ice Thickness =

$$I_r := 0.5 \cdot \text{in} \quad (\text{User Input})$$

Radial Ice Density =

$$I_d := 56 \cdot \text{pcf} \quad (\text{User Input})$$

Shape Factor =

$$C_{d_{\text{coax}}} := 1.45 \quad (\text{User Input})$$

Overload Factor for NESC Heavy Wind Load =

$$OF_{\text{HW}} := 2.5 \quad (\text{User Input})$$

Overload Factor for NESC Extreme Wind Load =

$$OF_{\text{EW}} := 1.0 \quad (\text{User Input})$$

Overload Factor for NESC Heavy Vertical Load =

$$OF_{\text{HV}} := 1.5 \quad (\text{User Input})$$

Overload Factor for NESC Extreme Vertical Load =

$$OF_{\text{EV}} := 1.0 \quad (\text{User Input})$$

Wind Area with Ice =

$$A_{\text{ice}} := (NP_{\text{coax1}} \cdot D_{\text{coax1}} + 2 \cdot I_r) = 5.65 \cdot \text{in}$$

Wind Area without Ice =

$$A := (NP_{\text{coax1}} \cdot D_{\text{coax1}}) = 4.65 \cdot \text{in}$$

Ice Area per Liner Ft =

$$A_{i_{\text{coax1}}} := \frac{\pi}{4} \cdot \left[(D_{\text{coax1}} + 2 \cdot I_r)^2 - D_{\text{coax1}}^2 \right] = 0.022 \text{ft}^2$$

Weight of Ice on All Coax Cables =

$$W_{\text{ice}} := A_{i_{\text{coax1}}} \cdot I_d \cdot N_{\text{coax1}} = 26 \cdot \text{plf}$$

Heavy Vertical Load =

$$\text{HeavyVert} := \overrightarrow{\left[(N_{\text{coax1}} \cdot W_{\text{coax1}} + W_{\text{ice}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{HV}} \right]}$$

Heavy Transverse Load =

$$\text{HeavyTrans} := \overrightarrow{\left(p \cdot A_{\text{ice}} \cdot C_{d_{\text{coax}}} \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{HW}} \right)}$$

$$\text{HeavyVert} = \begin{pmatrix} 602 \\ 602 \\ 602 \\ 602 \\ 602 \end{pmatrix} \text{ lb}$$

$$\text{HeavyTrans} = \begin{pmatrix} 68 \\ 68 \\ 68 \\ 68 \\ 68 \end{pmatrix} \text{ lb}$$

Extreme Vertical Load =

$$\text{ExtremeVert} := \overrightarrow{\left[(N_{\text{coax1}} \cdot W_{\text{coax1}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{EV}} \right]}$$

Extreme Transverse Load =

$$\text{ExtremeTrans} := \overrightarrow{\left[(q_z \cdot A \cdot C_{d_{\text{coax}}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{EW}} \right]}$$

$$\text{ExtremeVert} = \begin{pmatrix} 139 \\ 139 \\ 139 \\ 139 \\ 139 \end{pmatrix} \text{ lb}$$

$$\text{ExtremeTrans} = \begin{pmatrix} 161 \\ 161 \\ 161 \\ 161 \\ 161 \end{pmatrix} \text{ lb}$$

Coax Cable on CL&P Pole

(Above 50-ft AGL)

Distance Between Coax Cable Attach Points =

Coaxial Cable Span =

$$\text{CoaxSpan} := \begin{pmatrix} 10 \\ 10 \\ 10 \\ 10 \end{pmatrix} \cdot \text{ft} \quad (\text{User Input})$$

Diameter of Coax Cable =

$$D_{\text{coax1}} := 1.55 \cdot \text{in} \quad (\text{User Input})$$

Weight of Coax Cable =

$$W_{\text{coax1}} := 0.66 \cdot \text{plf} \quad (\text{User Input})$$

Number of Coax Cables =

$$N_{\text{coax1}} := 15 \quad (\text{User Input}) \quad 15 \text{ AT\&T Cables}$$

Number of Projected Coax Cables =

$$NP_{\text{coax1}} := 2 \quad (\text{User Input}) \quad \text{Sprint Cables on PCS Mast}$$

Extreme Wind Pressure =

$$qz := 28.6 \cdot \text{psf} \quad (\text{User Input})$$

Heavy Wind Pressure =

$$p := 4 \cdot \text{psf} \quad (\text{User Input})$$

Radial Ice Thickness =

$$I_r := 0.5 \cdot \text{in} \quad (\text{User Input})$$

Radial Ice Density =

$$I_d := 56 \cdot \text{pcf} \quad (\text{User Input})$$

Shape Factor =

$$C_d_{\text{coax}} := 1.45 \quad (\text{User Input})$$

Overload Factor for NESC Heavy Wind Load =

$$OF_{\text{HW}} := 2.5 \quad (\text{User Input})$$

Overload Factor for NESC Extreme Wind Load =

$$OF_{\text{EW}} := 1.0 \quad (\text{User Input})$$

Overload Factor for NESC Heavy Vertical Load =

$$OF_{\text{HV}} := 1.5 \quad (\text{User Input})$$

Overload Factor for NESC Extreme Vertical Load =

$$OF_{\text{EV}} := 1.0 \quad (\text{User Input})$$

Wind Area with Ice =

$$A_{\text{ice}} := (NP_{\text{coax1}} \cdot D_{\text{coax1}} + 2 \cdot I_r) = 4.1 \cdot \text{in}$$

Wind Area without Ice =

$$A := (NP_{\text{coax1}} \cdot D_{\text{coax1}}) = 3.1 \cdot \text{in}$$

Ice Area per Liner Ft =

$$A_{i_{\text{coax1}}} := \frac{\pi}{4} \cdot \left[(D_{\text{coax1}} + 2 \cdot I_r)^2 - D_{\text{coax1}}^2 \right] = 0.022 \text{ft}^2$$

Weight of Ice on All Coax Cables =

$$W_{\text{ice}} := A_{i_{\text{coax1}}} \cdot I_d \cdot N_{\text{coax1}} = 19 \cdot \text{plf}$$

Heavy Vertical Load =

$$\text{Heavy}_{\text{Vert}} := \overrightarrow{[(N_{\text{coax1}} \cdot W_{\text{coax1}} + W_{\text{ice}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{HV}}]}$$

Heavy Transverse Load =

$$\text{Heavy}_{\text{Trans}} := \overrightarrow{(p \cdot A_{\text{ice}} \cdot C_{d_{\text{coax}}} \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{HW}})}$$

$$\text{Heavy}_{\text{Vert}} = \begin{pmatrix} 430 \\ 430 \\ 430 \\ 430 \end{pmatrix} \text{ lb}$$

$$\text{Heavy}_{\text{Trans}} = \begin{pmatrix} 50 \\ 50 \\ 50 \\ 50 \end{pmatrix} \text{ lb}$$

Extreme Vertical Load =


$$\text{Extreme}_{\text{Vert}} := \overrightarrow{[(N_{\text{coax1}} \cdot W_{\text{coax1}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{EV}}]}$$

Extreme Transverse Load =

$$\text{Extreme}_{\text{Trans}} := \overrightarrow{[(qz \cdot A \cdot C_{d_{\text{coax}}}) \cdot \text{CoaxSpan} \cdot \text{OF}_{\text{EW}}]}$$

$$\text{Extreme}_{\text{Vert}} = \begin{pmatrix} 99 \\ 99 \\ 99 \\ 99 \end{pmatrix} \text{ lb}$$

$$\text{Extreme}_{\text{Trans}} = \begin{pmatrix} 107 \\ 107 \\ 107 \\ 107 \end{pmatrix} \text{ lb}$$



Project Name : 11021.CO50 - Brookfield, CT
Project Notes: CL&P # 2683/ AT&T 2185
Project File : J:\Jobs\1102100.WI\CO-50 - CT2185 - 761 FEDERAL ROAD, BROOKFIELD, CT\Structural\Rev (1)\Calcs\PLS Pole\clip structure # 2683.pol
Date run : 11:32:47 AM Wednesday, June 29, 2011
by : PLS-POLE Version 11.11
Licensed to : Centek Engineering Inc

Successfully performed nonlinear analysis

The model has 0 warnings.

Loads from file: j:\jobs\1102100.wi\co-50 - ct2185 - 761 federal road, brookfield, ct\structural\rev (1)\calcs\pls pole\clip #2683.ica

*** Analysis Results:

Maximum element usage is 68.81% for Steel Pole "2683" in load case "NESC Heavy"
Maximum insulator usage is 12.42% for Clamp "Clamp21" in load case "NESC Extreme"

Summary of Joint Support Reactions For All Load Cases:

Load Case	Joint Label	Long. Force (kips)	Trans. Force (kips)	Vert. Force (kips)	Shear Force (kips)	Long. Moment (ft-k)	Trans. Moment (ft-k)	Vert. Moment (ft-k)	Bending Found. Usage %
NESC Heavy	2683:g	-0.09	-24.35	48.48	24.35	1846.38	-3.85	-0.01	1846.38 0.00
NESC Extreme	2683:g	-0.03	-25.20	23.90	25.20	1785.77	-1.17	-0.00	1785.78 0.00

Summary of Tip Deflections For All Load Cases:

Note: positive tip load results in positive rotation

Load Case	Joint Label	Long. Defl. (in)	Trans. Defl. (in)	Vert. Defl. (in)	Resultant Defl. (in)	Long. Rot. (deg)	Trans. Rot. (deg)	Twist (deg)
NESC Heavy	2683:t	0.05	35.66	-0.79	35.67	0.00	-3.28	0.00
NESC Extreme	2683:t	0.02	34.00	-0.71	34.01	0.00	-3.08	0.00

Tubes Summary:

Pole Label	Tube Num.	Weight (lbs)	Load Case	Maximum Usage %	Resultant Moment (ft-k)
2683	1	3397	NESC Heavy	46.32	534.31
2683	2	5750	NESC Heavy	59.51	1357.41
2683	3	3427	NESC Heavy	68.81	1846.38

*** Overall summary for all load cases - Usage = Maximum Stress / Allowable Stress

Summary of Steel Pole Usages:

Steel Pole Label	Maximum Usage %	Load Case	Segment Number	Weight (lbs)
2683	68.81	NESC Heavy	25	13920.9

Summary of Tubular Davit Usages:

Tubular Davit Label	Davit Maximum Usage %	Load Case	Segment Number	Weight (lbs)
Davit1	1.33	NESC Extreme	1	77.9
Davit2	8.45	NESC Heavy	1	77.9
Davit3	2.28	NESC Heavy	1	321.0
Davit4	4.98	NESC Heavy	1	321.0
Davit5	3.03	NESC Heavy	1	434.7
Davit6	7.08	NESC Heavy	1	434.7
Davit7	2.36	NESC Heavy	1	321.0

Davit8 5.04 NESC Heavy 1 321.0

*** Maximum Stress Summary for Each Load Case

Summary of Maximum Usages by Load Case:

Load Case	Maximum Element Usage %	Element Label	Element Type
NESC Heavy	68.81	2683 Steel Pole	
NESC Extreme	65.74	2683 Steel Pole	

Summary of Steel Pole Usages by Load Case:

Load Case	Maximum Steel Pole Segment Usage %	Label	Number
NESC Heavy	68.81	2683	25
NESC Extreme	65.74	2683	25

Summary of Base Plate Usages by Load Case:

Load Case	Pole Bend Length Vertical Label Line #	(in)	(kips)	Load Moment	X Moment (ft-k)	Y Bending Moment Stress (ksi)	Bolt Moment Acting On Sum Bend Line (ft-k)	# Bolts	Max Bolt Load For Bend Line (kips)	Minimum Plate Thickness (in)	Usage %
NESC Heavy	2683	6 30.544	48.478	1846.381	-3.851	31.165	118.987	6	83.720	2.258	56.66
NESC Extreme	2683	6 30.544	23.902	1785.775	-1.173	29.426	112.346	6	78.827	2.194	53.50

Summary of Tubular Davit Usages by Load Case:

Load Case	Maximum Tubular Davit Segment Usage %	Label	Number
NESC Heavy	8.45	Davit2	1
NESC Extreme	3.21	Davit2	1

Summary of Insulator Usages:

Insulator Label	Insulator Type	Maximum Usage %	Load Case Weight (lbs)
Clamp1	Clamp	3.00	NESC Heavy 0.0
Clamp2	Clamp	3.00	NESC Heavy 0.0
Clamp3	Clamp	3.29	NESC Heavy 0.0
Clamp4	Clamp	3.29	NESC Heavy 0.0
Clamp5	Clamp	3.29	NESC Heavy 0.0
Clamp6	Clamp	3.29	NESC Heavy 0.0
Clamp7	Clamp	3.29	NESC Heavy 0.0
Clamp8	Clamp	3.29	NESC Heavy 0.0
Clamp9	Clamp	0.76	NESC Heavy 0.0
Clamp10	Clamp	0.76	NESC Heavy 0.0
Clamp11	Clamp	0.76	NESC Heavy 0.0
Clamp12	Clamp	0.76	NESC Heavy 0.0
Clamp13	Clamp	0.76	NESC Heavy 0.0
Clamp14	Clamp	0.54	NESC Heavy 0.0
Clamp15	Clamp	0.54	NESC Heavy 0.0
Clamp16	Clamp	0.54	NESC Heavy 0.0
Clamp17	Clamp	0.54	NESC Heavy 0.0
Clamp21	Clamp	12.42	NESC Extreme 0.0
Clamp23	Clamp	3.07	NESC Extreme 0.0


*** Weight of structure (lbs): 2309.3
Weight of Tubular Davit Arms: 13920.9
Weight of Steel Poles:

Total: 16230.2

*** End of Report

* PLS-POLE *****
* POLE AND FRAME ANALYSIS AND DESIGN *
* Copyright Power Line Systems, Inc. 1999-2011 *

Project Name : 11021.CO50 - Brookfield, CT
Project Notes: CL&P # 2683/ AT&T 2185
Project File : J:\Jobs\1102100.W\CO-50 - CT2185 - 761 FEDERAL ROAD, BROOKFIELD, CT\Structural\Rev (1)\Calcs\PLS Pole\cl&p structure # 2683.pol
Date run : 11:32:46 AM Wednesday, June 29, 2011
by : PLS-POLE Version 11.11
Licensed to : Centek Engineering Inc
Successfully performed nonlinear analysis
The model has 0 warnings.



Modeling options:
Offset Arms from Pole/Mast: Yes
Offset Braces from Pole/Mast: Yes
Offset Guys from Pole/Mast: Yes
Offset Posts from Pole/Mast: Yes
Offset Strains from Pole/Mast: Yes
Use Alternate Convergence Process: No
Steel poles checked with ASCE/SEI 48-05

Default Modulus of Elasticity for Steel = 29000.00 (ksi)
Default Weight Density for Steel = 490.00 (lbs/ft^3)

Steel Pole Properties:

Steel Pole Property Label	Stock Length (ft)	Default Embedded Length (ft)	Base	Shape	Tip Diameter (in)	Base Diameter (in)	Taper (in/ft)	Default Drag Coef.	Tubes	Modulus of Elasticity Override (ksi)	Weight Density Override (lbs/ft^3)	Shape At Base	Strength Check Type	Distance From Tip (ft)	Ultimate Trans. Load (kips)	Ultimate Long. Load (kips)
CL&P2683	2683	90.00	0	Yes	8F	19.63	43.21	0	1.3	3 tubes	0	0	Calculated	0.000	0.0000	0.0000

Steel Tubes Properties:


Property No.	Pole Tube	Length	Thickness	Lap	Lap	Yield	Moment	Cap.	Tube	Center of	Calculated	Tube	Top	Tube	Bot.	1.5x	Diam.
		(ft)	(in)	(ft)	(in)	Stress	Cap	Override	Weight	Gravity	(in/ft)	Diameter	Diameter	Lap	Length		(ft)
						(ksi)	(in)	(ft-k)	(lbs)	(ft)	(in/ft)	(in)	(in)	(in)	(ft)		(ft)
CL&P2683	1	39	0.3125	4.167	0.000	65.000	0.000	3397	3397	20.92	0.27728	19.63	30.44	30.44	3.73		
CL&P2683	2	40.1667	0.375	5.250	0.000	65.000	0.000	5750	5750	21.18	0.27728	28.66	39.80	39.80	4.88		
CL&P2683	3	20.25	0.375	0.000	0.000	65.000	0.000	3427	3427	10.36	0.27728	37.59	43.20	43.20	0.00		

Base Plate Properties:

Property	Pole	Plate	Plate	Plate	Bend	Line	Hole	Steel	Steel	Bolt	Bolt	Num.	Bolt	Bolt
	Diam.	Shape	Thick.	Weight	Length	Override	Diam.	Density	Yield	Diam.	Pattern	Of	Cage	Cage
	(in)		(in)	(lbs)	(in)		(in)	(lbs/ft^3)	Stress	(in)	(in)	Diam.	Inertia	Inertia
									(ksi)			(in)	(in^4)	(in^4)
CL&P2683	58.250	8F	3.000	1347	0.000	38.750	0	490.00	55.000	2.250	51.750	12	28733.01	5839.56

Base Plate Bolt Coordinates for Property "CL&P2683":

Bolt X	Bolt Y	Bolt
Coord.	Coord.	Angle
		(deg)
0.5894	0.9357	0
0.4251	1	0
0.1425	1	0




Steel Pole Connectivity:

Pole Label	Tip Base Joint (ft)	X of Base (ft)	Y of Base (ft)	Inclin. About X (deg)	Inclin. About Y (deg)	Property Set	Attach Labels	Base Connect	Embed & Override (ft)
2683	0	0	0	0	0	CL&P2683	15 labels	Fixed	0.00

Relative Attachment Labels for Steel Pole "2683":

Joint Label	Distance From Origin/Top Joint (ft)	Global Z of Attach Joint (ft)
2683:WVGD1	0.00	5.00
2683:WVGD2	0.00	15.00
2683:WVGD3	0.00	25.00
2683:WVGD4	0.00	35.00
2683:WVGD5	0.00	45.00
2683:WVGD6	0.00	55.00
2683:WVGD7	0.00	65.00
2683:WVGD8	0.00	75.00

2683:TopConn 80.00
 2683:BotConn 50.00
 2683:WVG9 85.00
 2683:Arm1 88.92
 2683:Arm2 83.50
 2683:Arm3 70.50
 2683:Arm4 59.50



Transverse/Vertical (Y) Axis

Pole Steel Properties:

Warning: Capacities and usages printed in splices are listed for the inner tube except at the splice top which uses the outer tube. ??

Element Label	Joint Label	Joint Position	Rel. Dist. (ft)	Outer Diam. (in)	Area (in ²)	T-Moment Inertia (in ⁴)	L-Moment Inertia (in ⁴)	D/t	W/t	Fy (ksi)	Fa Min. (ksi)	ASCE Cap Trans. (ft-k)	ASCE Cap Long. (ft-k)
2683	2683:t	2683:t Ori	0.00	19.63	20.00	985.95	985.95	0.00	21.9	65.00	65.00	544.26	544.26
2683	2683:Arm1	2683:Arm1 End	1.08	19.92	20.31	1032.52	1032.52	0.00	22.3	65.00	65.00	561.40	561.40
2683	2683:Arm1	2683:Arm1 Ori	1.08	19.92	20.31	1032.52	1032.52	0.00	22.3	65.00	65.00	561.40	561.40
2683	2683:WVG9	2683:WVG9 End	5.00	21.01	21.43	1213.85	1213.85	0.00	23.7	65.00	65.00	625.85	625.85
2683	2683:WVG9	2683:WVG9 Ori	5.00	21.01	21.43	1213.85	1213.85	0.00	23.7	65.00	65.00	625.85	625.85
2683	2683:Arm2	2683:Arm2 End	6.50	21.43	21.87	1288.49	1288.49	0.00	24.3	65.00	65.00	651.44	651.44
2683	2683:Arm2	2683:Arm2 Ori	6.50	21.43	21.87	1288.49	1288.49	0.00	24.3	65.00	65.00	651.44	651.44
2683	2683:TopConn	2683:TopConn End	10.00	22.40	22.87	1474.42	1474.42	0.00	25.5	65.00	65.00	713.14	713.14
2683	2683:TopConn	2683:TopConn Ori	10.00	22.40	22.87	1474.42	1474.42	0.00	25.5	65.00	65.00	713.14	713.14
2683	2683:WVG8	2683:WVG8 End	15.00	23.78	24.31	1769.84	1769.84	0.00	27.4	65.00	65.00	806.14	806.14
2683	2683:WVG8	2683:WVG8 Ori	15.00	23.78	24.31	1769.84	1769.84	0.00	27.4	65.00	65.00	806.14	806.14
2683	2683:Arm3	2683:Arm3 End	19.50	25.03	25.60	2067.33	2067.33	0.00	29.0	65.00	65.00	894.70	894.70
2683	2683:Arm3	2683:Arm3 Ori	19.50	25.03	25.60	2067.33	2067.33	0.00	29.0	65.00	65.00	894.70	894.70

Davit Property Label	Stock Shape	Steel Thickness	Base Diameter or Depth (in)	Tip Diameter or Depth (in)	Taper Coef.	Drag Coef.	Modulus of Elasticity (ksi)	Strength Check Type	Vertical Capacity (lbs)	Long. Yield Capacity (lbs)	Tension Capacity (lbs)	Steel Density Override (lbs/ft^3)
2683	#2683:0		Tube 1 End	22.25	25.79	26.39	2264.58	0.00 30.0	65.00	65.00	951.09	951.09
2683	#2683:0		Tube 1 Ori	22.25	25.79	26.39	2264.58	0.00 30.0	65.00	65.00	951.09	951.09
2683	2683:WVGD7		2683:WVGD7 End	25.00	26.56	27.18	2474.00	0.00 31.1	65.00	65.00	1009.21	1009.21
2683	2683:WVGD7		2683:WVGD7 Ori	25.00	26.56	27.18	2474.00	0.00 31.1	65.00	65.00	1009.21	1009.21
2683	#2683:1		Tube 1 End	27.75	27.32	27.97	2695.95	0.00 32.1	65.00	65.00	1069.06	1069.06
2683	#2683:1		Tube 1 Ori	27.75	27.32	27.97	2695.95	0.00 32.1	65.00	65.00	1069.06	1069.06
2683	2683:Arm4		2683:Arm4 End	30.50	28.08	28.76	2930.78	0.00 33.1	65.00	64.24	1117.35	1117.35
2683	2683:Arm4		2683:Arm4 Ori	30.50	28.08	28.76	2930.78	0.00 33.1	65.00	64.24	1117.35	1117.35
2683	#2683:2		SpliceE End	34.83	29.28	30.00	3327.87	0.00 34.7	65.00	62.89	1191.09	1191.09
2683	#2683:2		SpliceE Ori	34.83	29.28	30.00	3327.87	0.00 34.7	65.00	62.89	1191.10	1191.10
2683	2683:WVGD6		2683:WVGD6 End	35.00	28.70	35.20	3734.31	0.00 27.6	65.00	65.00	1409.35	1409.35
2683	2683:WVGD6		2683:WVGD6 Ori	35.00	28.70	35.20	3734.31	0.00 27.6	65.00	65.00	1409.35	1409.35
2683	#2683:3		SpliceB End	39.00	29.81	36.58	4190.24	0.00 28.8	65.00	65.00	1522.59	1522.59
2683	#2683:3		SpliceB Ori	39.00	29.81	36.58	4190.24	0.00 28.8	65.00	65.00	1522.59	1522.59
2683	2683:BotConn		2683:BotConn End	40.00	30.09	36.93	4309.75	0.00 29.1	65.00	65.00	1551.58	1551.58
2683	2683:BotConn		2683:BotConn Ori	40.00	30.09	36.93	4309.75	0.00 29.1	65.00	65.00	1551.58	1551.58
2683	2683:WVGD5		2683:WVGD5 End	45.00	31.48	38.65	4941.47	0.00 30.6	65.00	65.00	1700.66	1700.66
2683	2683:WVGD5		2683:WVGD5 Ori	45.00	31.48	38.65	4941.47	0.00 30.6	65.00	65.00	1700.66	1700.66
2683	#2683:4		Tube 2 End	50.00	32.86	40.37	5632.09	0.00 32.2	65.00	65.00	1856.57	1856.57
2683	#2683:4		Tube 2 Ori	50.00	32.86	40.37	5632.09	0.00 32.2	65.00	65.00	1856.57	1856.57
2683	2683:WVGD4		2683:WVGD4 End	55.00	34.25	42.09	6384.24	0.00 33.7	65.00	63.72	1979.56	1979.56
2683	2683:WVGD4		2683:WVGD4 Ori	55.00	34.25	42.09	6384.24	0.00 33.7	65.00	63.72	1979.56	1979.56
2683	#2683:5		Tube 2 End	60.00	35.64	43.82	7200.54	0.00 35.2	65.00	62.42	2102.06	2102.06
2683	#2683:5		Tube 2 Ori	60.00	35.64	43.82	7200.54	0.00 35.2	65.00	62.42	2102.06	2102.06
2683	2683:WVGD3		2683:WVGD3 End	65.00	37.02	45.54	8083.61	0.00 36.8	65.00	61.12	2224.22	2224.22
2683	2683:WVGD3		2683:WVGD3 Ori	65.00	37.02	45.54	8083.61	0.00 36.8	65.00	61.12	2224.22	2224.22
2683	#2683:6		SpliceE End	69.75	38.34	47.18	8986.78	0.00 38.2	65.00	59.89	2339.57	2339.57
2683	#2683:6		SpliceE Ori	69.75	38.34	47.18	8986.78	0.00 38.2	65.00	59.89	2339.57	2339.57
2683	#2683:7		Tube 2 End	72.38	38.32	47.15	8971.06	0.00 38.2	65.00	59.91	2337.64	2337.64
2683	#2683:7		Tube 2 Ori	72.38	38.32	47.15	8971.06	0.00 38.2	65.00	59.91	2337.64	2337.64
2683	2683:WVGD2		2683:WVGD2 End	75.00	39.05	48.05	9497.27	0.00 39.0	65.00	59.23	2400.97	2400.97
2683	2683:WVGD2		2683:WVGD2 Ori	75.00	39.05	48.05	9497.27	0.00 39.0	65.00	59.23	2400.97	2400.97
2683	#2683:8		Tube 3 End	80.00	40.43	49.78	10555.72	0.00 40.5	65.00	57.93	2520.52	2520.52
2683	#2683:8		Tube 3 Ori	80.00	40.43	49.78	10555.72	0.00 40.5	65.00	57.93	2520.52	2520.52
2683	2683:WVGD1		2683:WVGD1 End	85.00	41.82	51.50	11690.03	0.00 42.0	65.00	56.63	2638.31	2638.31
2683	2683:WVGD1		2683:WVGD1 Ori	85.00	41.82	51.50	11690.03	0.00 42.0	65.00	56.63	2638.31	2638.31
2683	2683:g		2683:g End	90.00	43.20	53.22	12902.82	0.00 43.6	65.00	55.27	2751.00	2751.00

Tubular Davit Properties:

Davit Property Label	Stock Shape	Steel Thickness	Base Diameter or Depth (in)	Tip Diameter or Depth (in)	Taper Coef.	Drag Coef.	Modulus of Elasticity (ksi)	Strength Check Type	Vertical Capacity (lbs)	Long. Yield Capacity (lbs)	Tension Capacity (lbs)	Steel Density Override (lbs/ft^3)
ARM A	0	0.1875	10.76	6	0	1.3	29000	1 point Calculated	0	0	65	0
ARM B	0	0.25	18.5	9	0	1.3	29000	1 point Calculated	0	0	65	0
ARM C	0	0.25	18.5	9	0	1.3	29000	1 point Calculated	0	0	65	0

Intermediate Joints for Davit Property "ARM A":

Joint Horiz. Vert. Label Offset Offset (ft) (ft)
End 4.5 -1.5

Intermediate Joints for Davit Property "ARM B":

Joint Horiz. Vert. Label Offset Offset (ft) (ft)
End 8.67 -2

Intermediate Joints for Davit Property "ARM C":


Joint Horiz. Vert.

Label Offset Offset
(ft) (ft)

End 11.67 -3

Tubular Davit Arm Connectivity:

Davit Label	Attach Label	Property Set	Davit Azimuth (deg)
Davit1	2683:Arm1	ARM A	180
Davit2	2683:Arm1	ARM A	0
Davit3	2683:Arm2	ARM B	180
Davit4	2683:Arm2	ARM B	0
Davit5	2683:Arm3	ARM C	180
Davit6	2683:Arm3	ARM C	0
Davit7	2683:Arm4	ARM B	180
Davit8	2683:Arm4	ARM B	0



Transverse/Vertical (Y) Axis

Tubular Davit Arm Steel Properties:

Element Label	Joint Label	Joint Position (ft)	Rel. Outer Dist. (ft)	Area (in^2)	V-Moment Inertia (in^4)	H-Moment Inertia (in^4)	D/t Max.	W/t	Fy (ksi)	Min. (ksi)	Fa V-Mom. (ft-k)	ASCE Cap H-Mom. (ft-k)
Davit1	Davit1:O	Origin	0.00	10.76	6.23	87.04	57.39	0.0	65.00	65.00	87.64	87.64
Davit1	Davit1:End	End	4.74	6.00	3.42	14.47	32.00	0.0	65.00	65.00	26.13	26.13

Davit2	Davit2:0	Origin	0.00	10.76	6.23	87.04	87.04	57.39	0.0	65.00	65.00	87.64	87.64
Davit2	Davit2:End	End	4.74	6.00	3.42	14.47	14.47	32.00	0.0	65.00	65.00	26.13	26.13
Davit3	Davit3:0	Origin	0.00	18.50	14.33	596.86	596.86	74.00	0.0	65.00	65.00	349.51	349.51
Davit3	#Davit3:0	End	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit3	#Davit3:0	Origin	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit3	Davit3:End	End	8.90	9.00	6.87	65.82	65.82	36.00	0.0	65.00	65.00	79.23	79.23
Davit4	Davit4:0	Origin	0.00	18.50	14.33	596.86	596.86	74.00	0.0	65.00	65.00	349.51	349.51
Davit4	#Davit4:0	End	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit4	#Davit4:0	Origin	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit4	Davit4:End	End	8.90	9.00	6.87	65.82	65.82	36.00	0.0	65.00	65.00	79.23	79.23
Davit5	Davit5:0	Origin	0.00	18.50	14.33	596.86	596.86	74.00	0.0	65.00	65.00	349.51	349.51
Davit5	#Davit5:0	End	5.00	14.56	11.24	287.65	287.65	58.23	0.0	65.00	65.00	214.05	214.05
Davit5	#Davit5:0	Origin	5.00	14.56	11.24	287.65	287.65	58.23	0.0	65.00	65.00	214.05	214.05
Davit5	#Davit5:1	End	8.52	11.78	9.05	150.51	150.51	47.12	0.0	65.00	65.00	138.43	138.43
Davit5	#Davit5:1	Origin	8.52	11.78	9.05	150.51	150.51	47.12	0.0	65.00	65.00	138.43	138.43
Davit5	Davit5:End	End	12.05	9.00	6.87	65.82	65.82	36.00	0.0	65.00	65.00	79.23	79.23
Davit6	Davit6:0	Origin	0.00	18.50	14.33	596.86	596.86	74.00	0.0	65.00	65.00	349.51	349.51
Davit6	#Davit6:0	End	5.00	14.56	11.24	287.65	287.65	58.23	0.0	65.00	65.00	214.05	214.05
Davit6	#Davit6:0	Origin	5.00	14.56	11.24	287.65	287.65	58.23	0.0	65.00	65.00	214.05	214.05
Davit6	#Davit6:1	End	8.52	11.78	9.05	150.51	150.51	47.12	0.0	65.00	65.00	138.43	138.43
Davit6	#Davit6:1	Origin	8.52	11.78	9.05	150.51	150.51	47.12	0.0	65.00	65.00	138.43	138.43
Davit6	Davit6:End	End	12.05	9.00	6.87	65.82	65.82	36.00	0.0	65.00	65.00	79.23	79.23
Davit7	Davit7:0	Origin	0.00	18.50	14.33	596.86	596.86	74.00	0.0	65.00	65.00	349.51	349.51
Davit7	#Davit7:0	End	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit7	#Davit7:0	Origin	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit7	Davit7:End	End	8.90	9.00	6.87	65.82	65.82	36.00	0.0	65.00	65.00	79.23	79.23
Davit8	Davit8:0	Origin	0.00	18.50	14.33	596.86	596.86	74.00	0.0	65.00	65.00	349.51	349.51
Davit8	#Davit8:0	End	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit8	#Davit8:0	Origin	4.45	13.75	10.60	241.63	241.63	55.00	0.0	65.00	65.00	190.37	190.37
Davit8	Davit8:End	End	8.90	9.00	6.87	65.82	65.82	36.00	0.0	65.00	65.00	79.23	79.23

*** Insulator Data

Clamp Properties:

Label Stock Holding
Number Capacity
(lbs)

clamp clamp1 8e+004

Clamp Insulator Connectivity:

Clamp Label	Structure	Property	Min. Required	Set Vertical Load (uplift)	(lbs)
Clamp1	Davit1:End	clamp	No Limit		
Clamp2	Davit2:End	clamp	No Limit		
Clamp3	Davit3:End	clamp	No Limit		
Clamp4	Davit4:End	clamp	No Limit		
Clamp5	Davit5:End	clamp	No Limit		
Clamp6	Davit6:End	clamp	No Limit		
Clamp7	Davit7:End	clamp	No Limit		
Clamp8	Davit8:End	clamp	No Limit		
Clamp9	2683:WVGD1	clamp	No Limit		
Clamp10	2683:WVGD2	clamp	No Limit		
Clamp11	2683:WVGD3	clamp	No Limit		
Clamp12	2683:WVGD4	clamp	No Limit		
Clamp13	2683:WVGD5	clamp	No Limit		
Clamp14	2683:WVGD6	clamp	No Limit		

Clamp15	2683:WVGD7	clamp	No Limit
Clamp16	2683:WVGD8	clamp	No Limit
Clamp17	2683:WVGD9	clamp	No Limit
Clamp21	2683:TopConn	clamp	No Limit
Clamp23	2683:BotConn	clamp	No Limit


```

code from file: 4-vots\1102100 w\co-50 - ct2185 - 761 federal road. brookfield. ct\structure\rev 1\calcs\pls pole\cl&p #2683.1ca

```

Insulator dead and wind loads are already included in the point loads printed below.

Loading Method Parameters:

Structure Height Summary (used for calculating wind/ice adjust with height):

structure height summary for calculating wind height adjust 0.00 (ft) and structure Z coordinate that will be put on the centerline ground profile in PLS-CADD.

Z of ground for wind height adjust	0.00 (ft)
Ground elevation shift	0.00 (ft)
Z of ground with shift	0.00 (ft)
Z of structure top (highest joint)	90.42 (ft)
Structure height	90.42 (ft)
Structure height above ground	90.42 (ft)

Vector Load Cases:

[illegible]

Point Loads for Load Case "NESC Heavy":

Joint Label	Vertical Transverse		Longitudinal Load (lbs)	Load Comment
	Load (lbs)	Load (lbs)		
David1:End	840	2250	0	
David2:End	840	2250	0	
David3:End	1263	2305	0	
David4:End	1263	2305	0	
David5:End	1263	2305	0	
David6:End	1263	2305	0	
David7:End	1263	2305	0	
David8:End	1263	2305	0	
2683:TopConn	8453	3009	0	
2683:BotConn	1812	-712	0	
2683:WVG01	602	68	0	
2683:WVG02	602	68	0	
2683:WVG03	602	68	0	
2683:WVG04	602	68	0	
2683:WVG05	602	68	0	
2683:WVG06	430	50	0	
2683:WVG07	430	50	0	
2683:WVG08	430	50	0	
2683:WVG09	430	50	0	

Detailed pole Loading Data for Load Case "NESC Heavy":

Notes: Does not include loads from equipment, arms, guys, braces, etc. or user input loads.

Wind load is calculated for the undeformed shape of a pole.

[illegible]

Label	Joint	Joint	Top Z (ft)	Bottom Z (ft)	Average Elevation (ft)	Diameter (in)	Number	Coef.	Wind Pressure (psf)	Thickness (in)	Ice Load (lbs)	Vert. Load (lbs)	Wind Vertical Load (lbs)	Wind Load (lbs)	Wind Load (lbs)
2683	2683:t	2683:Arm1	90.00	88.92	89.46	19.775	9.36e+005	1.300	10.00	0.50	111.10	23.14	13.76	1.17	24.31
2683	2683:Arm1	2683:WVG09	88.92	85.00	86.96	20.468	9.69e+005	1.300	10.00	0.50	417.61	86.93	51.70	4.25	91.17
2683	2683:WVG09	2683:Arm2	85.00	83.50	84.25	21.219	1e+006	1.300	10.00	0.50	165.76	34.48	20.51	1.63	36.11
2683	2683:Arm2	2683:TopConn	83.50	80.00	81.75	21.913	1.04e+006	1.300	10.00	0.50	399.59	83.09	49.42	3.79	86.88
2683	2683:TopConn	2683:WVG08	80.00	75.00	77.50	23.091	1.09e+006	1.300	10.00	0.50	601.98	125.08	74.39	5.42	130.50
2683	2683:WVG08	2683:Arm3	75.00	70.50	72.75	24.408	1.16e+006	1.300	10.00	0.50	573.11	119.00	70.77	4.88	123.87
2683	2683:Arm3	2683:WVG07	70.50	67.75	69.13	25.413	1.2e+006	1.300	10.00	0.50	364.84	75.71	45.03	2.98	78.69
2683	2683:WVG07	2683:Arm4	65.00	62.25	63.63	26.176	1.24e+006	1.300	10.00	0.50	375.93	77.99	46.38	2.98	80.97
2683	2683:Arm4	2683:WVG06	62.25	59.50	60.88	27.701	1.31e+006	1.300	10.00	0.50	387.01	80.26	47.73	2.98	83.24
2683	2683:WVG06	2683:WVG05	55.00	51.00	53.00	28.994	1.36e+006	1.300	10.00	0.50	649.79	134.66	80.08	4.69	139.35
2683	2683:WVG05	2683:BotConn	51.00	45.00	48.00	29.259	1.39e+006	1.300	10.00	0.50	55.48	5.24	3.11	0.18	5.42
2683	2683:BotConn	2683:WVG04	45.00	40.00	42.50	30.784	1.46e+006	1.300	10.00	0.50	1008.34	174.27	103.64	5.42	179.68
2683	2683:WVG04	2683:WVG03	40.00	35.00	37.50	32.171	1.52e+006	1.300	10.00	0.50	1052.31	181.78	108.11	5.42	187.19
2683	2683:WVG03	2683:WVG02	35.00	30.00	32.50	34.943	1.65e+006	1.300	10.00	0.50	1096.28	189.29	112.58	5.42	194.70
2683	2683:WVG02	2683:WVG01	30.00	25.00	27.50	36.330	1.72e+006	1.300	10.00	0.50	1140.24	196.80	117.04	5.42	202.21
2683	2683:WVG01	2683:WVG00	25.00	20.25	22.63	37.682	1.78e+006	1.300	10.00	0.50	1123.96	193.91	115.33	5.15	199.06
2683	2683:WVG00	2683:WVG00	20.25	17.63	18.94	38.329	1.81e+006	1.300	10.00	0.50	1263.83	109.00	64.83	2.84	111.85
2683	2683:WVG00	2683:WVG00	17.63	15.00	16.31	38.682	1.83e+006	1.300	10.00	0.50	1288.06	110.01	65.43	2.84	112.85
2683	2683:WVG00	2683:WVG00	15.00	10.00	12.50	39.739	1.88e+006	1.300	10.00	0.50	1248.51	215.26	128.03	5.42	220.68
2683	2683:WVG00	2683:WVG00	10.00	5.00	7.50	41.125	1.95e+006	1.300	10.00	0.50	1292.33	222.77	132.49	5.42	228.19
2683	2683:WVG00	2683:WVG00	5.00	0.00	2.50	42.512	2.01e+006	1.300	10.00	0.50	1336.29	230.28	136.96	5.42	235.70

Point Loads for Load Case "NESC Extreme":

Joint Label	Vertical Load (lbs)	Transverse Load (lbs)	Longitudinal Load (lbs)	Load Comment
David1:End	208	1129	0	
David2:End	208	1129	0	
David3:End	367	1484	0	
David4:End	367	1484	0	
David5:End	367	1484	0	
David6:End	367	1484	0	
David7:End	367	1484	0	
David8:End	367	1484	0	
2683:TopConn	4258	8981	0	
2683:BotConn	938	-2270	0	
2683:WVG01	139	161	0	
2683:WVG02	139	161	0	
2683:WVG03	139	161	0	
2683:WVG04	139	161	0	
2683:WVG05	139	161	0	
2683:WVG06	99	107	0	
2683:WVG07	99	107	0	
2683:WVG08	99	107	0	
2683:WVG09	99	107	0	

Detailed Pole Loading Data for Load Case "NESC Extreme":


Notes: Does not include loads from equipment, arms, guys, braces, etc. or user input loads.
Wind load is calculated for the undeformed shape of a pole.

Pole Label	Top Joint	Bottom Joint	Section Top Z (ft)	Section Bottom Z (ft)	Section Average Elevation (ft)	Outer Diameter (in)	Reynolds Number	Coef.	Drag Adjusted Pressure (psf)	Adjusted Ice Thickness (in)	Pole Vert. Load (lbs)	Pole Wind Vertical Load (lbs)	Pole Ice Load (lbs)	Tran. Wind Load (lbs)	Long. Wind Load (lbs)
2683	2683:t	2683:Arm1	90.00	88.92	89.46	19.775	1.5e+006	1.000	25.60	0.00	74.07	45.56	0.00	0.00	45.56
2683	2683:Arm1	2683:WVG09	88.92	85.00	86.96	20.468	1.55e+006	1.000	25.60	0.00	278.40	171.18	0.00	0.00	171.18
2683	2683:WVG09	2683:Arm2	85.00	83.50	84.25	21.219	1.61e+006	1.000	25.60	0.00	110.50	67.91	0.00	0.00	67.91

2683	2683:Arm2	2683:TopConn	83.50	80.00	81.75	21.913	1.66e+006	1.000	25.60	0.00	266.39	163.63	0.00
2683	2683:TopConn	2683:WVGD8	80.00	75.00	77.50	23.091	1.75e+006	1.000	25.60	0.00	401.32	246.32	0.00
2683	2683:WVGD8	2683:Arm3	75.00	70.50	72.75	24.408	1.85e+006	1.000	25.60	0.00	382.07	234.34	0.00
2683	2683:Arm3	2683:WVGD7	70.50	67.75	69.13	25.413	1.93e+006	1.000	25.60	0.00	243.23	149.10	0.00
2683	2683:WVGD7	2683:Arm4	67.75	65.00	66.38	26.176	1.98e+006	1.000	25.60	0.00	250.62	153.58	0.00
2683	2683:Arm4	2683:WVGD6	65.00	62.25	63.63	26.938	2.04e+006	1.000	25.60	0.00	258.01	158.05	0.00
2683	2683:WVGD6	2683:BotConn	62.25	59.50	60.88	27.701	2.11e+006	1.000	25.60	0.00	265.40	162.52	0.00
2683	2683:BotConn	2683:WVGD5	59.50	55.17	57.33	28.683	2.17e+006	1.000	25.60	0.00	433.19	265.18	0.00
2683	2683:WVGD5	2683:Arm3	55.17	51.00	55.08	28.994	2.21e+006	1.000	25.60	0.00	36.98	10.31	0.00
2683	2683:Arm3	2683:WVGD4	55.00	51.00	53.00	29.259	2.22e+006	1.000	25.60	0.00	905.35	249.70	0.00
2683	2683:WVGD4	2683:BotConn	51.00	50.00	50.50	29.952	2.27e+006	1.000	25.60	0.00	125.15	63.90	0.00
2683	2683:BotConn	2683:WVGD3	50.00	45.00	47.50	30.784	2.33e+006	1.000	25.60	0.00	642.92	328.39	0.00
2683	2683:WVGD3	2683:Arm3	45.00	40.00	42.50	32.171	2.44e+006	1.000	25.60	0.00	672.23	343.18	0.00
2683	2683:Arm3	2683:WVGD2	40.00	35.00	37.50	33.557	2.54e+006	1.000	25.60	0.00	701.54	357.97	0.00
2683	2683:WVGD2	2683:BotConn	35.00	30.00	32.50	34.943	2.65e+006	1.000	25.60	0.00	730.85	372.76	0.00
2683	2683:BotConn	2683:WVGD1	30.00	25.00	27.50	36.330	2.75e+006	1.000	25.60	0.00	760.16	387.55	0.00
2683	2683:WVGD1	2683:Arm3	25.00	20.25	22.63	37.682	2.85e+006	1.000	25.60	0.00	749.30	381.87	0.00
2683	2683:Arm3	2683:WVGD0	20.25	17.63	18.94	38.329	2.91e+006	1.000	25.60	0.00	842.55	214.66	0.00
2683	2683:WVGD0	2683:BotConn	17.63	15.00	16.31	38.682	2.93e+006	1.000	25.60	0.00	858.71	216.64	0.00
2683	2683:BotConn	2683:WVGD0	15.00	10.00	12.50	39.739	3.01e+006	1.000	25.60	0.00	832.34	423.92	0.00
2683	2683:WVGD0	2683:Arm3	10.00	5.00	7.50	41.125	3.12e+006	1.000	25.60	0.00	861.55	438.71	0.00
2683	2683:Arm3	2683:WVGD0	5.00	0.00	2.50	42.512	3.22e+006	1.000	25.60	0.00	890.86	453.50	0.00

*** Analysis Results:

Maximum element usage is 68.81% for Steel Pole "2683" in load case "NESC Heavy"
Maximum insulator usage is 12.42% for Clamp "Clamp21" in load case "NESC Extreme"



*** Analysis Results for Load Case No. 1 "NESC Heavy" - Number of iterations in SAPS 14

Equilibrium Joint Positions and Rotations for Load Case "NESC Heavy":

Joint Label	X-Displ (ft)	Y-Displ (ft)	Z-Displ (ft)	X-Rot (deg)	Y-Rot (deg)	Z-Rot (deg)	X-Pos (ft)	Y-Pos (ft)	Z-Pos (ft)
2683:g	0	0	0	0.0000	0.0000	0.0000	0	0	0
2683:t	0.004583	2.972	-0.06623	-3.2789	0.0045	0.0001	0.004583	2.972	89.93
2683:Arm1	0.004498	2.91	-0.06447	-3.2789	0.0045	0.0001	0.004498	2.91	88.86
2683:WVGD9	0.004192	2.686	-0.05806	-3.2629	0.0045	0.0001	0.004192	2.686	84.94
2683:Arm2	0.004074	2.601	-0.05562	-3.2530	0.0045	0.0001	0.004074	2.601	83.44
2683:TopConn	0.003801	2.403	-0.05001	-3.2103	0.0045	0.0001	0.003801	2.403	79.95
2683:WVGD8	0.003415	2.127	-0.04225	-3.1142	0.0044	0.0001	0.003415	2.127	74.96

Joint Support Reactions for Load Case "NESC Heavy":														
Joint Label	X (kips)	X %	Y (kips)	Y %	Z Comp. Usage %	Uplift Result. Force %	Trans. Defl. (in)	Long. Defl. (in)	Rel. Trans. Dist. (ft)	Joint Position	Orig. End	Force Usage %	X-M. Moment Usage %	Y-M. Moment Usage %
2683:Arm3	0.003074	1.886	-0.03572	-2.9985	0.0043	0.0001	-0.003074	1.886	70.46	0.003074	1.886	70.46	0.003074	1.886
2683:WVGD7	0.002669	1.607	-0.02846	-2.8132	0.0041	0.0001	0.002669	1.607	64.97	0.002669	1.607	64.97	0.002669	1.607
2683:Arm4	0.002281	1.346	-0.02215	-2.5982	0.0039	0.0000	0.002281	1.346	59.48	0.002281	1.346	59.48	0.002281	1.346
2683:WVGD6	0.00198	1.15	-0.01771	-2.4006	0.0037	0.0000	0.00198	1.15	54.98	0.00198	1.15	54.98	0.00198	1.15
2683:BotConn	0.001664	0.949	-0.01354	-2.1893	0.0035	0.0000	0.001664	0.949	49.99	0.001664	0.949	49.99	0.001664	0.949
2683:WVGD5	0.00137	0.767	-0.01009	-1.9694	0.0032	0.0000	0.00137	0.767	44.99	0.00137	0.767	44.99	0.00137	0.767
2683:WVGD4	0.000851	0.4615	-0.005115	-1.5211	0.0026	0.0000	0.000851	0.4615	34.99	0.000851	0.4615	34.99	0.000851	0.4615
2683:WVGD3	0.000497	0.2341	-0.002221	-1.0773	0.0020	0.0000	0.000497	0.2341	25	0.000497	0.2341	25	0.000497	0.2341
2683:WVGD2	0.0001655	0.08346	-0.0007688	-0.6384	0.0012	0.0000	0.0001655	0.08346	15	0.0001655	0.08346	15	0.0001655	0.08346
2683:WVGD1	1.945e-005	0.009323	-0.0001657	-0.2066	0.0004	0.0000	1.945e-005	0.009323	5	1.945e-005	0.009323	5	1.945e-005	0.009323
David1:O	0.004503	2.911	-0.01698	-3.2789	0.0045	0.0001	0.004503	2.911	88.9	0.004503	2.911	88.9	0.004503	2.911
David1:End	0.004649	3.004	0.2379	3.2789	0.0045	0.0001	0.004649	3.004	90.66	0.004649	3.004	90.66	0.004649	3.004
David2:O	0.004434	2.908	-0.1119	-3.2789	0.0045	0.0001	0.004434	2.908	88.81	0.004434	2.908	88.81	0.004434	2.908
David2:End	0.004584	2.988	-0.3768	-3.2766	0.0045	0.0001	0.004584	2.988	90.04	0.004584	2.988	90.04	0.004584	2.988
David3:O	0.004079	2.602	-0.004961	-3.2530	0.0045	0.0001	0.004079	2.602	83.5	0.004079	2.602	83.5	0.004079	2.602
David3:End	0.004288	2.729	0.4814	3.2260	0.0045	0.0001	0.004288	2.729	85.98	0.004288	2.729	85.98	0.004288	2.729
David4:O	0.004069	2.599	-0.1063	-3.2530	0.0045	0.0001	0.004069	2.599	83.39	0.004069	2.599	83.39	0.004069	2.599
David4:End	0.004175	2.7	-0.6076	-3.3212	0.0045	0.0001	0.004175	2.7	84.89	0.004175	2.7	84.89	0.004175	2.7
David5:O	0.003079	1.888	0.01884	-2.9985	0.0043	0.0001	0.003079	1.888	70.52	0.003079	1.888	70.52	0.003079	1.888
David5:End	0.003367	2.059	0.6196	-2.9508	0.0043	0.0001	0.003367	2.059	74.12	0.003367	2.059	74.12	0.003367	2.059
David6:O	0.003069	1.885	-0.09028	-2.9985	0.0043	0.0001	0.003069	1.885	70.41	0.003069	1.885	70.41	0.003069	1.885
David6:End	0.003236	2.029	-0.7202	-3.1305	0.0043	0.0001	0.003236	2.029	72.78	0.003236	2.029	72.78	0.003236	2.029
David7:O	0.002285	1.348	0.03089	-2.5982	0.0039	0.0000	0.002285	1.348	59.53	0.002285	1.348	59.53	0.002285	1.348
David7:End	0.002457	1.447	0.4193	-2.5701	0.0039	0.0001	0.002457	1.447	61.92	0.002457	1.447	61.92	0.002457	1.447
David8:O	0.002276	1.345	-0.07519	-2.5982	0.0039	0.0000	0.002276	1.345	59.42	0.002276	1.345	59.42	0.002276	1.345
David8:End	0.002238	1.428	-0.4765	-2.6673	0.0039	0.0000	0.002238	1.428	61.02	0.002238	1.428	61.02	0.002238	1.428

Detailed Steel Pole Usages for Load Case "NESC Heavy":

Element Label	Joint Label	Rel. Trans. Dist. (ft)	Trans. Defl. (in)	Long. Defl. (in)	Vert. Defl. (in)	Trans. Moment (ft-k)	Long. Moment (ft-k)	Tors. Moment (ft-k)	Axial Force (kips)	Trans. Shear (kips)	Long. Shear (kips)	P/A (ksi)	M/S. (ksi)	V/Q. (ksi)	T/R. (ksi)	Res. Usage %	Max. At Usage Pt. %
2683	2683:t	Origin	0.00	35.66	0.05	-0.79	-0.00	-0.00	0.0	0.02	-0.00	-0.00	0.00	0.00	0.00	0.00	0.0
2683	2683:Arm1	End	1.08	34.92	0.05	-0.77	0.02	-0.00	0.0	0.02	-0.00	-0.00	0.00	0.00	0.00	0.01	0.0
2683	2683:Arm1	Origin	1.08	34.92	0.05	-0.77	6.93	-0.00	0.0	0.02	-0.00	-0.00	0.00	0.00	0.00	0.06	1.5
2683	2683:WVGD9	End	5.00	32.23	0.05	-0.70	25.33	-0.01	0.0	4.69	-0.00	-0.00	2.63	0.17	0.00	2.74	4.2
2683	2683:WVGD9	Origin	5.00	32.23	0.05	-0.70	25.33	-0.01	0.0	4.69	-0.00	-0.00	2.63	0.17	0.00	2.74	4.2
2683	2683:Arm2	End	6.50	31.21	0.05	-0.67	32.61	-0.02	0.0	4.85	-0.00	-0.00	2.63	0.18	0.00	2.78	4.3
2683	2683:Arm2	Origin	6.50	31.21	0.05	-0.67	42.20	-0.02	0.0	4.85	-0.00	-0.00	2.63	0.18	0.00	3.39	5.2
2683	2683:TopConn	End	10.00	28.84	0.05	-0.60	76.26	-0.05	0.0	9.73	-0.01	-0.29	4.21	0.35	0.00	4.54	7.0
2683	2683:TopConn	Origin	10.00	28.84	0.05	-0.60	76.26	-0.05	0.0	9.73	-0.01	-0.29	4.21	0.35	0.00	7.25	11.2
2683	2683:WVGD8	End	15.00	25.52	0.04	-0.51	142.94	-0.11	0.0	13.34	-0.01	-0.62	11.53	0.46	0.00	12.18	18.7
2683	2683:WVGD8	Origin	15.00	25.52	0.04	-0.51	142.94	-0.11	0.0	13.34	-0.01	-0.62	11.53	0.46	0.00	12.18	18.7
2683	2683:Arm3	End	19.50	22.63	0.04	-0.43	203.88	-0.17	0.0	16.26	-0.01	-0.64	14.82	0.44	0.00	15.47	23.8
2683	2683:Arm3	Origin	19.50	22.63	0.04	-0.43	218.28	-0.17	0.0	16.26	-0.01	-0.64	14.82	0.44	0.00	15.47	23.8
2683	Tube 1	End	22.25	20.93	0.03	-0.38	269.01	-0.23	0.0	20.39	-0.02	-0.77	18.39	0.55	0.00	19.19	29.5
2683	Tube 1	Origin	22.25	20.93	0.03	-0.38	269.01	-0.23	0.0	20.39	-0.02	-0.77	18.39	0.55	0.00	19.19	29.5
2683	2683:WVGD7	End	25.00	19.28	0.03	-0.34	319.93	-0.29	0.0	20.83	-0.02	-0.77	20.61	0.54	0.00	21.40	32.9
2683	2683:WVGD7	Origin	25.00	19.28	0.03	-0.34	319.93	-0.29	0.0	20.83	-0.02	-0.77	20.61	0.54	0.00	21.40	32.9
2683	Tube 1	End	27.75	17.69	0.03	-0.30	371.22	-0.36	0.0	21.72	-0.02	-0.80	20.81	0.54	0.00	21.43	33.0
2683	Tube 1	Origin	27.75	17.69	0.03	-0.30	371.22	-0.36	0.0	21.72	-0.02	-0.80	20.81	0.54	0.00	21.43	33.0
2683	2683:Arm4	End	30.50	16.16	0.03	-0.27	422.69	-0.43	0.0	22.20	-0.03	-0.79	22.58	0.53	0.00	23.39	36.0
2683	2683:Arm4	Origin	30.50	16.16	0.03	-0.27	422.69	-0.43	0.0	22.20	-0.03	-0.79	22.58	0.53	0.00	23.39	36.0
2683	SpliceT	End	34.83	13.88	0.02	-0.21	534.31	-0.57	0.0	26.11	-0.03	-0.91	24.86	0.65	0.00	25.79	40.2
2683	SpliceT	Origin	34.83	13.88	0.02	-0.21	534.31	-0.57	0.0	26.11	-0.03	-0.91	24.86	0.65	0.00	25.79	40.2
2683	2683:WVGD6	End	35.00	13.80	0.02	-0.21	538.24	-0.57	0.0	26.55	-0.03	-0.88	28.22	0.62	0.00	29.13	46.3
2683	2683:WVGD6	Origin	35.00	13.80	0.02	-0.21	538.24	-0.57	0.0	26.55	-0.03	-0.88	28.22	0.62	0.00	29.13	46.3
2683	SpliceB	End	39.00	11.85	0.02	-0.17	633.14	-0.71	0.0	27.76	-0.03	-0.79	24.83	0.54	0.00	25.64	39.4
2683	SpliceB	Origin	39.00	11.85	0.02	-0.17	633.14	-0.71	0.0	27.76	-0.03	-0.79	24.83	0.54	0.00	25.64	39.4
2683	SpliceB	End	39.00	11.85	0.02	-0.17	633.14	-0.71	0.0	27.76	-0.03	-0.79	24.83	0.54	0.00	27.81	42.8
2683	SpliceB	Origin	39.00	11.85	0.02	-0.17	633.14	-0.71	0.0	27.76	-0.03	-0.79	24.83	0.54	0.00	27.81	42.8

2683	2683:BotConn	End	40.00	11.39	0.02	-0.16	656.93	-0.75	0.0	-28.62	23.79	-0.04	-0.78	27.53	0.51	0.00	28.32	43.6	2
2683	2683:BotConn	Origin	40.00	11.39	0.02	-0.16	656.93	-0.75	0.0	-31.14	23.20	-0.04	-0.84	27.53	0.50	6.00	28.39	43.7	2
2683	2683:WVGDS	End	45.00	9.20	0.02	-0.12	772.95	-0.95	0.0	-31.14	23.20	-0.04	-0.81	29.56	0.48	0.00	30.37	46.7	2
2683	2683:WVGDS	Origin	45.00	9.20	0.02	-0.12	772.95	-0.95	0.0	-32.92	23.38	-0.04	-0.85	29.56	0.48	0.00	30.42	46.8	2
2683	Tube 2	End	50.00	7.25	0.01	-0.09	889.85	-1.17	0.0	-32.92	23.38	-0.04	-0.82	31.17	0.46	0.00	32.03	49.2	2
2683	Tube 2	Origin	50.00	7.25	0.01	-0.09	889.85	-1.17	0.0	-34.15	23.47	-0.05	-0.85	31.17	0.46	0.00	32.03	49.3	2
2683	2683:WVGDS	End	55.00	5.54	0.01	-0.06	1007.19	-1.42	0.0	-36.03	23.64	-0.05	-0.86	32.44	0.44	0.00	33.26	52.2	2
2683	2683:WVGDS	Origin	55.00	5.54	0.01	-0.06	1007.19	-1.42	0.0	-36.03	23.64	-0.05	-0.86	32.44	0.44	0.00	33.30	52.3	2
2683	Tube 2	End	60.00	4.06	0.01	-0.04	1125.37	-1.68	0.0	-37.35	23.72	-0.06	-0.85	33.44	0.43	0.00	34.30	54.9	2
2683	Tube 2	Origin	60.00	4.06	0.01	-0.04	1125.37	-1.68	0.0	-37.35	23.72	-0.06	-0.82	34.21	0.41	0.00	35.03	57.3	2
2683	2683:WVGDS	End	65.00	2.81	0.01	-0.03	1243.98	-1.98	0.0	-39.29	23.88	-0.06	-0.86	34.21	0.42	0.00	35.08	57.4	2
2683	2683:WVGDS	Origin	65.00	2.81	0.01	-0.03	1243.98	-1.98	0.0	-39.29	23.88	-0.06	-0.83	34.77	0.40	0.00	35.61	59.5	2
2683	SpliceT	End	69.75	1.84	0.00	-0.02	1357.41	-2.28	0.0	-40.64	23.94	-0.07	-0.86	34.77	0.40	0.00	35.64	59.5	2
2683	SpliceT	Origin	69.75	1.84	0.00	-0.02	1357.41	-2.28	0.0	-40.64	23.94	-0.07	-0.86	36.42	0.40	0.00	37.29	62.2	2
2683	Tube 2	End	72.38	1.39	0.00	-0.01	1420.26	-2.46	0.0	-42.03	23.99	-0.07	-0.89	36.42	0.40	0.00	37.32	62.3	2
2683	Tube 2	Origin	72.38	1.39	0.00	-0.01	1420.26	-2.46	0.0	-42.03	23.99	-0.07	-0.87	36.62	0.39	0.00	37.50	63.3	2
2683	2683:WVGDS	End	75.00	1.00	0.00	-0.01	1483.24	-2.65	0.0	-44.06	24.12	-0.07	-0.92	36.62	0.40	0.00	37.54	63.4	2
2683	2683:WVGDS	Origin	75.00	1.00	0.00	-0.01	1483.24	-2.65	0.0	-44.06	24.12	-0.07	-0.89	36.89	0.38	0.00	37.78	65.2	2
2683	Tube 3	End	80.00	0.44	0.00	-0.00	1603.84	-3.02	0.0	-45.56	24.19	-0.08	-0.92	36.89	0.38	0.00	37.81	65.3	2
2683	Tube 3	Origin	80.00	0.44	0.00	-0.00	1603.84	-3.02	0.0	-45.56	24.19	-0.08	-0.88	37.05	0.37	0.00	37.94	67.0	2
2683	2683:WVGDS	End	85.00	0.11	0.00	-0.00	1724.77	-3.42	0.0	-47.70	24.32	-0.09	-0.93	37.05	0.37	0.00	37.96	67.1	2
2683	2683:WVGDS	Origin	85.00	0.11	0.00	-0.00	1724.77	-3.42	0.0	-47.70	24.32	-0.09	-0.90	37.13	0.36	6.00	38.03	68.8	2
2683	2683:g	End	90.00	0.00	0.00	0.00	1846.38	-3.85	0.0	-47.70	24.32	-0.09	-0.90	37.13	0.36	6.00	38.03	68.8	2

Detailed Tubular Davit Arm Usages for Load Case "NESC Heavy":

Element Label	Joint Label	Joint Position	Rel. Dist. (ft)	Trans. Defl. (in)	Long. Defl. (in)	Vert. Defl. (in)	Horz. Mom. (ft-k)	Tors. Mom. (ft-k)	Axial Force (kips)	Vert. Shear (kips)	Horz. Shear (kips)	P/A (ksi)	M/S. (ksi)	V/Q. (ksi)	T/R. (ksi)	Res. (ksi)	Max. Usage Pt. %	
Davit1	Davit1:0	Origin	0.00	34.93	0.05	-0.20	0.00	0.0	-2.42	-0.00	-0.00	-0.39	0.00	0.00	0.00	0.39	0.6	
Davit1	Davit1:End	End	4.74	36.05	0.06	2.86	-0.00	0.00	0.0	-2.42	-0.00	-0.71	0.00	0.00	0.00	0.71	1.1	
Davit2	Davit2:0	Origin	0.00	34.90	0.05	-1.34	-6.90	0.00	0.0	1.94	1.45	0.00	0.31	5.12	0.47	0.00	5.49	8.4
Davit2	Davit2:End	End	4.74	35.86	0.06	-4.52	0.00	0.00	0.0	1.94	1.45	0.00	0.57	0.00	0.85	0.00	1.58	2.4
Davit3	Davit3:0	Origin	0.00	31.23	0.05	-0.06	-6.89	0.00	0.0	-2.66	0.89	-0.00	-0.19	1.28	0.12	0.00	1.48	2.3
Davit3	#Davit3:0	End	4.45	31.99	0.05	2.87	-2.95	0.00	0.0	-2.66	0.89	-0.00	-0.25	1.01	0.17	0.00	1.29	2.0
Davit3	#Davit3:0	Origin	4.45	31.99	0.05	2.87	-2.95	0.00	0.0	-2.59	0.66	-0.00	-0.24	1.01	0.12	0.00	1.27	2.0
Davit3	Davit3:End	End	8.90	32.75	0.05	5.78	-0.00	0.00	0.0	-2.59	0.66	-0.00	-0.38	0.00	0.19	0.00	0.50	0.8
Davit4	Davit4:0	Origin	0.00	31.19	0.05	-1.28	-16.47	-0.00	-0.0	2.00	1.97	0.00	0.14	3.06	0.28	0.00	3.24	5.0
Davit4	#Davit4:0	End	4.45	31.79	0.05	-4.27	-7.70	-0.00	-0.0	2.00	1.97	0.00	0.19	2.63	0.37	0.00	2.89	4.4
Davit4	#Davit4:0	Origin	4.45	31.79	0.05	-4.27	-7.70	-0.00	0.0	2.04	1.73	0.00	0.19	2.63	0.33	0.00	2.88	4.4
Davit4	Davit4:End	End	8.90	32.40	0.05	-7.29	0.00	0.00	0.0	2.04	1.73	0.00	0.30	0.00	0.50	0.00	0.92	1.4
Davit5	Davit5:0	Origin	0.00	22.65	0.04	0.23	-9.50	0.01	0.0	-2.72	0.97	-0.00	-0.19	1.77	0.14	0.00	1.97	3.0
Davit5	#Davit5:0	End	5.00	23.51	0.04	3.23	-4.65	0.00	0.0	-2.72	0.97	-0.00	-0.24	1.41	0.17	0.00	1.68	2.6
Davit5	#Davit5:0	Origin	5.00	23.51	0.04	3.23	-4.65	0.00	0.0	-2.65	0.73	-0.00	-0.24	1.41	0.13	0.00	1.66	2.6
Davit5	#Davit5:1	End	8.52	24.11	0.04	5.34	-2.06	0.00	0.0	-2.65	0.73	-0.00	-0.29	0.97	0.16	0.00	1.29	2.0
Davit5	#Davit5:1	Origin	8.52	24.11	0.04	5.34	-2.06	0.00	0.0	-2.60	0.58	-0.00	-0.29	0.97	0.13	0.00	1.27	2.0
Davit5	Davit5:End	End	12.05	24.71	0.04	7.43	-0.00	0.00	0.0	-2.60	0.58	-0.00	-0.38	0.00	0.17	0.00	0.48	0.7
Davit6	Davit6:0	Origin	0.00	22.62	0.04	-1.08	-23.88	-0.01	-0.0	1.91	2.18	0.00	0.13	4.44	0.30	0.00	4.60	7.1
Davit6	#Davit6:0	End	5.00	23.33	0.04	-4.18	-12.99	-0.00	-0.0	1.91	2.18	0.00	0.17	3.94	0.39	0.00	4.17	6.4
Davit6	#Davit6:0	Origin	5.00	23.33	0.04	-4.18	-12.99	-0.00	-0.0	1.97	1.92	0.00	0.17	3.94	0.34	0.00	4.16	6.4
Davit6	#Davit6:1	End	8.52	23.83	0.04	-6.40	-6.21	-0.00	-0.0	1.97	1.92	0.00	0.22	2.91	0.42	0.00	3.22	4.9
Davit6	#Davit6:1	Origin	8.52	23.83	0.04	-6.40	-6.21	-0.00	0.0	2.00	1.76	0.00	0.22	2.91	0.39	0.00	3.21	4.9
Davit6	Davit6:End	End	12.05	24.35	0.04	-8.64	0.00	0.00	0.0	2.00	1.76	0.00	0.29	0.00	0.51	0.00	0.93	1.4
Davit7	Davit7:0	Origin	0.00	16.17	0.03	0.37	-7.16	0.00	0.0	-2.65	0.92	-0.00	-0.18	1.33	0.13	0.00	1.53	2.4
Davit7	#Davit7:0	End	4.45	16.77	0.03	2.71	-3.08	0.00	0.0	-2.65	0.92	-0.00	-0.25	1.05	0.17	0.00	1.34	2.1
Davit7	#Davit7:0	Origin	4.45	16.77	0.03	2.71	-3.08	0.00	0.0	-2.59	0.69	-0.00	-0.24	1.05	0.13	0.00	1.31	2.0
Davit7	Davit7:End	End	8.90	17.36	0.03	5.03	-0.00	0.00	0.0	-2.59	0.69	-0.00	-0.38	0.00	0.20	0.00	0.51	0.8
Davit8	Davit8:0	Origin	0.00	16.14	0.03	-0.90	-16.68	-0.00	-0.0	1.98	1.99	0.00	0.14	3.10	0.28	0.00	3.28	5.0
Davit8	#Davit8:0	End	4.45	16.64	0.03	-3.29	-7.81	-0.00	-0.0	1.98	1.99	0.00	0.19	2.66	0.38	0.00	2.93	4.5
Davit8	#Davit8:0	Origin	4.45	16.64	0.03	-3.29	-7.81	-0.00	0.0	2.02	1.75	0.00	0.19	2.66	0.33	0.00	2.91	4.5

Devit8 Davit8:End End 8.90 17.14 0.03 -5.72 0.00 0.00 0.0 2.02 1.75 0.00 0.29 0.00 0.51 0.00 0.93 1.4 1

Summary of Clamp Capacities and Usages for Load Case "NESC Heavy":

Clamp Force Label	Input Holding Capacity (kips)	Factored Holding Capacity (kips)	Usage %
Clamp1 2.402	80.00	80.00	3.00
Clamp2 2.402	80.00	80.00	3.00
Clamp3 2.628	80.00	80.00	3.29
Clamp4 2.628	80.00	80.00	3.29
Clamp5 2.628	80.00	80.00	3.29
Clamp6 2.628	80.00	80.00	3.29
Clamp7 2.628	80.00	80.00	3.29
Clamp8 2.628	80.00	80.00	3.29
Clamp9 0.606	80.00	80.00	0.76
Clamp10 0.606	80.00	80.00	0.76
Clamp11 0.606	80.00	80.00	0.76
Clamp12 0.606	80.00	80.00	0.76
Clamp13 0.606	80.00	80.00	0.76
Clamp14 0.433	80.00	80.00	0.54
Clamp15 0.433	80.00	80.00	0.54
Clamp16 0.433	80.00	80.00	0.54
Clamp17 0.433	80.00	80.00	0.54
Clamp21 8.973	80.00	80.00	11.22
Clamp23 1.947	80.00	80.00	2.43

Equilibrium Joint Positions and Rotations for Load Case "NESC Extreme":

Joint Support Reactions for Load Case "NESC Extreme":

Centek Engineering Inc - clsp structure # 2683

2683	2683:Arm3	End	19.50	21.66	0.01	-0.38	190.35	-0.05	0.0	-6.96	15.62	-0.00	-0.27	13.83	0.48	0.00	14.13	21.7	2
2683	2683:Arm3	Origin	19.50	21.66	0.01	-0.38	199.78	-0.05	0.0	-8.73	16.87	-0.01	-0.34	14.52	0.59	0.00	14.89	22.9	2
2683	Tube 1	End	22.25	20.03	0.01	-0.34	251.68	-0.07	0.0	-8.73	18.87	-0.01	-0.33	17.20	0.57	0.00	17.56	27.0	2
2683	Tube 1	Origin	22.25	20.03	0.01	-0.34	251.68	-0.07	0.0	-9.01	19.02	-0.01	-0.34	17.20	0.57	0.00	17.57	27.0	2
2683	2683:WVGd7	End	25.00	18.45	0.01	-0.30	304.00	-0.09	0.0	-9.01	19.02	-0.01	-0.33	19.58	0.55	0.00	19.94	30.7	2
2683	2683:WVGd7	Origin	25.00	18.45	0.01	-0.30	304.00	-0.09	0.0	-9.39	19.29	-0.01	-0.35	19.58	0.56	0.00	19.95	30.7	2
2683	Tube 1	End	27.75	16.93	0.01	-0.27	357.04	-0.11	0.0	-9.39	19.29	-0.01	-0.34	21.71	0.55	0.00	22.07	33.9	2
2683	Tube 1	Origin	27.75	16.93	0.01	-0.27	357.04	-0.11	0.0	-9.68	19.44	-0.01	-0.35	21.71	0.55	0.00	22.08	34.0	2
2683	2683:Arm4	End	30.50	15.46	0.01	-0.23	410.51	-0.13	0.0	-9.68	19.44	-0.01	-0.34	23.60	0.54	0.00	23.96	37.3	2
2683	2683:Arm4	Origin	30.50	15.46	0.01	-0.23	416.71	-0.13	0.0	-11.32	22.68	-0.01	-0.39	23.96	0.62	0.00	24.38	37.9	2
2683	SpliceB	End	34.83	13.28	0.01	-0.19	514.97	-0.17	0.0	-11.32	22.68	-0.01	-0.38	27.19	0.60	0.00	27.59	43.9	2
2683	SpliceB	Origin	34.83	13.28	0.01	-0.19	514.97	-0.17	0.0	-11.59	22.80	-0.01	-0.39	27.19	0.60	0.00	27.60	43.9	2
2683	2683:WVGd6	End	35.00	13.20	0.01	-0.19	518.77	-0.17	0.0	-11.59	22.80	-0.01	-0.33	23.93	0.51	0.00	24.28	37.3	2
2683	2683:WVGd6	Origin	35.00	13.20	0.01	-0.19	518.77	-0.17	0.0	-12.19	23.05	-0.01	-0.35	23.93	0.52	0.00	24.29	37.4	2
2683	SpliceB	End	39.00	11.34	0.01	-0.15	610.96	-0.22	0.0	-12.19	23.05	-0.01	-0.33	26.09	0.50	0.00	26.43	40.7	2
2683	SpliceB	Origin	39.00	11.34	0.01	-0.15	610.96	-0.22	0.0	-12.75	23.20	-0.01	-0.35	26.09	0.50	0.00	26.45	40.7	2
2683	2683:BotConn	End	40.00	10.90	0.01	-0.14	634.16	-0.23	0.0	-12.75	23.20	-0.01	-0.35	26.57	0.50	0.00	26.93	41.4	2
2683	2683:BotConn	Origin	40.00	10.90	0.01	-0.14	634.16	-0.23	0.0	-14.20	21.15	-0.01	-0.38	26.57	0.45	0.00	26.97	41.5	2
2683	2683:WVGd5	End	45.00	8.81	0.01	-0.10	739.89	-0.29	0.0	-14.20	21.15	-0.01	-0.37	28.28	0.43	0.00	28.66	44.1	2
2683	2683:WVGd5	Origin	45.00	8.81	0.01	-0.10	739.89	-0.29	0.0	-15.07	21.61	-0.01	-0.39	28.28	0.44	0.00	28.68	44.1	2
2683	Tube 2	End	50.00	6.95	0.00	-0.07	847.96	-0.36	0.0	-15.07	21.61	-0.01	-0.37	29.69	0.42	0.00	30.07	46.3	2
2683	Tube 2	Origin	50.00	6.95	0.00	-0.07	847.96	-0.36	0.0	-15.84	21.93	-0.01	-0.39	29.69	0.43	0.00	30.09	46.3	2
2683	2683:WVGd4	End	55.00	5.31	0.00	-0.05	957.59	-0.43	0.0	-15.84	21.93	-0.01	-0.40	30.83	0.41	0.00	31.21	49.0	2
2683	2683:WVGd4	Origin	55.00	5.31	0.00	-0.05	957.59	-0.43	0.0	-16.77	22.41	-0.02	-0.40	30.83	0.42	0.00	31.24	49.0	2
2683	Tube 2	End	60.00	3.89	0.00	-0.03	1069.66	-0.51	0.0	-16.77	22.41	-0.02	-0.40	31.77	0.41	0.00	32.16	51.5	2
2683	Tube 2	Origin	60.00	3.89	0.00	-0.03	1069.66	-0.51	0.0	-17.60	22.75	-0.02	-0.40	31.77	0.41	0.00	32.18	51.6	2
2683	2683:WVGd3	End	65.00	2.70	0.00	-0.02	1183.39	-0.60	0.0	-17.60	22.75	-0.02	-0.39	32.53	0.40	0.00	32.52	53.9	2
2683	2683:WVGd3	Origin	65.00	2.70	0.00	-0.02	1183.39	-0.60	0.0	-18.57	23.24	-0.02	-0.41	32.53	0.40	0.00	32.94	53.9	2
2683	SpliceB	End	69.75	1.77	0.00	-0.01	1293.80	-0.69	0.0	-18.57	23.24	-0.02	-0.39	33.13	0.39	0.00	33.53	56.0	2
2683	SpliceB	Origin	69.75	1.77	0.00	-0.01	1293.80	-0.69	0.0	-19.43	23.50	-0.02	-0.41	33.13	0.39	0.00	33.54	56.0	2
2683	Tube 2	End	72.38	1.33	0.00	-0.01	1355.49	-0.75	0.0	-19.43	23.50	-0.02	-0.41	34.75	0.39	0.00	35.16	58.7	2
2683	Tube 2	Origin	72.38	1.33	0.00	-0.01	1355.49	-0.75	0.0	-20.33	23.69	-0.02	-0.43	34.75	0.40	0.00	35.18	58.7	2
2683	2683:WVGd2	End	75.00	0.96	0.00	-0.01	1417.68	-0.81	0.0	-20.33	23.69	-0.02	-0.42	34.98	0.39	0.00	35.41	59.8	2
2683	2683:WVGd2	Origin	75.00	0.96	0.00	-0.01	1417.68	-0.81	0.0	-21.37	24.12	-0.02	-0.44	34.98	0.40	0.00	35.43	59.8	2
2683	Tube 3	End	80.00	0.43	0.00	-0.00	1538.30	-0.92	0.0	-21.37	24.12	-0.02	-0.43	35.36	0.38	0.00	35.80	61.8	2
2683	Tube 3	Origin	80.00	0.43	0.00	-0.00	1538.30	-0.92	0.0	-22.31	24.48	-0.02	-0.45	35.36	0.39	0.00	35.82	61.8	2
2683	2683:WVGd1	End	85.00	0.11	0.00	-0.00	1660.71	-1.04	0.0	-22.31	24.48	-0.02	-0.43	35.65	0.38	0.00	36.09	63.7	2
2683	2683:WVGd1	Origin	85.00	0.11	0.00	-0.00	1660.71	-1.04	0.0	-23.41	25.01	-0.03	-0.45	35.65	0.38	0.00	36.12	63.8	2
2683	2683:g	End	90.00	0.00	0.00	0.00	1785.77	-1.17	0.0	-23.41	25.01	-0.03	-0.44	35.89	0.37	0.00	36.33	65.7	2

Detailed Tubular Davit Arm Usages for Load Case "NESC Extreme":

Element Label	Joint Label	Joint Position	Rel. Dist. (ft)	Trans. Defl. (in)	Long. Defl. (in)	Vert. Defl. (in)	Vert. Mom. (ft-k)	Horz. Mom. (ft-k)	Tors. Mom. (ft-k)	Axial Force (kips)	Horz. Shear (kips)	Vert. Shear (kips)	P/A (ksi)	M/S. (ksi)	V/Q. (ksi)	T/R. (ksi)	Res. Usage P.C. %	Max. A. (ksi)	
Davit1	Davit1:0	Origin	0.00	33.32	0.02	-0.15	0.91	0.00	0.0	-1.14	-0.19	-0.00	-0.18	0.68	0.06	0.00	0.86	1.3	1
Davit1	Davit1:End	End	4.74	34.37	0.02	2.73	-0.00	0.00	0.0	-1.14	-0.19	-0.00	-0.33	0.00	0.11	0.00	0.39	0.6	1
Davit2	Davit2:0	Origin	0.00	33.29	0.02	-1.22	-2.56	-0.00	0.0	1.02	0.54	0.00	0.16	1.90	0.17	0.00	2.09	3.2	1
Davit2	Davit2:End	End	4.74	34.19	0.02	-4.17	0.00	0.00	0.0	1.02	0.54	0.00	0.30	0.00	0.32	0.00	0.62	1.0	1
Davit3	Davit3:0	Origin	0.00	29.83	0.01	-0.02	-0.63	0.00	0.0	-1.59	0.14	-0.00	-0.11	0.12	0.02	0.00	0.23	0.4	1
Davit3	Davit3:0	End	4.45	30.55	0.02	2.74	-0.00	0.00	0.0	-1.59	0.14	-0.00	-0.15	0.00	0.03	0.00	0.16	0.2	1
Davit3	Davit3:0	Origin	4.45	30.55	0.02	2.74	-0.00	0.00	0.0	-1.55	0.00	-0.00	-0.15	0.00	0.00	0.00	0.15	0.2	1
Davit3	Davit3:End	End	8.90	31.26	0.02	5.51	-0.00	0.00	0.0	-1.55	0.00	-0.00	-0.22	0.00	0.00	0.00	0.22	0.3	1
Davit4	Davit4:0	Origin	0.00	29.80	0.01	-1.17	-6.81	-0.00	-0.0	1.36	0.85	0.00	0.09	1.27	0.12	0.00	1.38	2.1	1
Davit4	Davit4:0	End	4.45	30.37	0.02	-3.98	-3.04	-0.00	-0.0	1.36	0.85	0.00	0.13	1.04	0.16	0.00	1.20	1.8	1
Davit4	Davit4:0	Origin	4.45	30.37	0.02	-3.98	-3.04	-0.00	0.0	1.39	0.68	0.00	0.13	1.04	0.13	0.00	1.19	1.8	1
Davit4	Davit4:End	End	8.90	30.94	0.02	-6.80	0.00	0.00	0.0	1.39	0.68	0.00	0.20	0.00	0.20	0.00	0.40	0.6	1
Davit5	Davit5:0	Origin	0.00	21.68	0.01	0.24	-0.93	0.00	0.0	-1.62	0.19	-0.00	-0.11	0.17	0.03	0.00	0.29	0.5	1
Davit5	Davit5:0	End	5.00	22.50	0.01	3.13	0.02	0.00	0.0	-1.62	0.19	-0.00	-0.14	0.01	0.03	0.00	0.16	0.2	1
Davit5	Davit5:0	Origin	5.00	22.50	0.01	3.13	0.02	0.00	0.0	-1.57	0.04	-0.00	-0.14	0.01	0.01	0.00	0.15	0.2	1
Davit5	Davit5:1	End	8.52	23.08	0.01	5.17	0.17	0.00	0.0	-1.57	0.04	-0.00	-0.17	0.08	0.01	0.00	0.26	0.4	1
Davit5	Davit5:1	Origin	8.52	23.08	0.01	5.17	0.17	0.00	0.0	-1.54	-0.05	-0.00	-0.17	0.08	0.01	0.00	0.25	0.4	1
Davit5	Davit5:End	End	12.05	23.66	0.01	7.20	-0.00	0.00	0.0	-1.54	-0.05	-0.00	-0.22	0.00	0.01	0.00	0.23	0.3	1

Davit6	Davit6:O	Origin	0.00	21.65	0.01	-1.01	-10.30	-0.00	0.0	1.32	0.99	0.00	0.09	1.92	0.14	0.00	2.02	3.1	1
Davit6	#Davit6:0	End	5.00	22.33	0.01	-3.95	-5.36	-0.00	-0.0	1.32	0.99	0.00	0.12	1.63	0.18	0.00	1.77	2.7	1
Davit6	#Davit6:0	Origin	5.00	22.33	0.01	-3.95	-5.36	-0.00	-0.0	1.35	0.82	0.00	0.12	1.63	0.15	0.00	1.76	2.7	1
Davit6	#Davit6:1	End	8.52	22.81	0.01	-6.04	-2.48	-0.00	-0.0	1.35	0.82	0.00	0.15	1.17	0.18	0.00	1.35	2.1	1
Davit6	#Davit6:1	Origin	8.52	22.81	0.01	-6.04	-2.48	-0.00	0.0	1.37	0.70	0.00	0.15	1.17	0.16	0.00	1.34	2.1	1
Davit6	Davit6:End	End	12.05	23.29	0.01	-8.13	0.00	0.00	0.0	1.37	0.70	0.00	0.20	0.00	0.20	0.00	0.41	0.6	1
Davit7	Davit7:O	Origin	0.00	15.48	0.01	0.38	-0.78	0.00	0.0	-1.59	0.16	-0.00	-0.11	0.15	0.02	0.00	0.26	0.4	1
Davit7	#Davit7:0	End	4.45	16.05	0.01	2.62	-0.07	0.00	0.0	-1.59	0.16	-0.00	-0.15	0.03	0.03	0.00	0.18	0.3	1
Davit7	#Davit7:0	Origin	4.45	16.05	0.01	2.62	-0.07	0.00	0.0	-1.55	0.02	-0.00	-0.15	0.03	0.00	0.00	0.17	0.3	1
Davit7	Davit7:End	End	8.90	16.62	0.01	4.87	-0.00	0.00	0.0	-1.55	0.02	-0.00	-0.22	0.00	0.00	0.00	0.23	0.3	1
Davit8	Davit8:O	Origin	0.00	15.45	0.01	-0.84	-6.94	-0.00	-0.0	1.35	0.86	0.00	0.09	1.29	0.12	0.00	1.40	2.2	1
Davit8	#Davit8:0	End	4.45	15.92	0.01	-3.12	-3.11	-0.00	-0.0	1.35	0.86	0.00	0.13	1.06	0.16	0.00	1.22	1.9	1
Davit8	#Davit8:0	Origin	4.45	15.92	0.01	-3.12	-3.11	-0.00	0.0	1.38	0.70	0.00	0.13	1.06	0.13	0.00	1.21	1.9	1
Davit8	Davit8:End	End	8.90	16.40	0.01	-5.41	0.00	0.00	0.0	1.38	0.70	0.00	0.20	0.00	0.20	0.00	0.41	0.6	1

Summary of Clamp Capacities and Usages for Load Case "NESC Extreme":

Clamp Force Label	Input Holding Capacity (kips)	Factored Holding Capacity (kips)	Usage %
Clamp1	1.148	80.00	1.44
Clamp2	1.148	80.00	1.44
Clamp3	1.529	80.00	1.91
Clamp4	1.529	80.00	1.91
Clamp5	1.529	80.00	1.91
Clamp6	1.529	80.00	1.91
Clamp7	1.529	80.00	1.91
Clamp8	1.529	80.00	1.91
Clamp9	0.213	80.00	0.27
Clamp10	0.213	80.00	0.27
Clamp11	0.213	80.00	0.27
Clamp12	0.213	80.00	0.27
Clamp13	0.213	80.00	0.27
Clamp14	0.146	80.00	0.18
Clamp15	0.146	80.00	0.18
Clamp16	0.146	80.00	0.18
Clamp17	0.146	80.00	0.18
Clamp21	9.939	80.00	12.42
Clamp23	2.456	80.00	3.07

*** Overall summary for all load cases - Usage = Maximum Stress / Allowable Stress

Summary of Steel Pole Usages:

Steel Pole Maximum Load Case Segment Weight		
Label Usage %	Number	(lbs)
2683	68.81	NESC Heavy
	25	13920.9

Base Plate Results by Bend Line:

Pole Label	Load Case	Bend Line	#	Start X (ft)	Start Y (ft)	End X (ft)	End Y (ft)	End Length (in)	Bending Stress (ksi)	Bolt # Acting	Max Load (kips)	Bolt Min Plate Thickness (in)	Actual Thickness (in)	Usage %
2683	NESC Heavy	1	1.271	1.275	0.390	2.156	14.956	30.475	56.972	2	83.027	2.233	3.000	55.41
2683	NESC Heavy	2	0.390	-2.156	1.271	-1.275	14.956	27.584	51.566	2	-75.640	2.125	3.000	50.15
2683	NESC Heavy	3	-1.273	-1.800	1.273	-1.800	30.544	28.143	107.451	6	-75.640	2.146	3.000	51.17
2683	NESC Heavy	4	-1.271	-1.275	-0.390	-2.156	14.956	27.254	50.951	2	-74.948	2.112	3.000	49.55
2683	NESC Heavy	5	-0.390	2.156	-1.271	1.275	14.956	30.805	57.588	2	83.720	2.245	3.000	56.01
2683	NESC Heavy	6	1.273	1.800	-1.273	1.800	30.544	31.165	118.987	6	83.720	2.258	3.000	56.66
2683	NESC Heavy	7	1.381	1.537	0.097	2.069	16.676	28.936	60.317	3	83.257	2.176	3.000	52.61
2683	NESC Heavy	8	0.097	-2.069	1.381	-1.537	16.676	26.240	54.691	3	-75.640	2.072	3.000	47.71
2683	NESC Heavy	9	-1.381	-1.537	-0.097	-2.069	16.676	25.998	54.191	3	-75.178	2.063	3.000	47.27
2683	NESC Heavy	10	-0.097	2.069	-1.381	1.537	16.676	29.179	60.822	3	83.720	2.185	3.000	53.05
2683	NESC Extreme	1	1.271	1.275	0.390	2.156	14.956	28.820	53.879	2	78.616	2.172	3.000	52.40
2683	NESC Extreme	2	0.390	-2.156	1.271	-1.275	14.956	27.333	51.097	2	-74.843	2.115	3.000	49.70
2683	NESC Extreme	3	-1.273	-1.800	1.273	-1.800	30.544	27.936	106.659	6	-74.843	2.138	3.000	50.79
2683	NESC Extreme	4	-1.271	-1.275	-0.390	-2.156	14.956	27.232	50.910	2	-74.632	2.111	3.000	49.51
2683	NESC Extreme	5	-0.390	2.156	-1.271	1.275	14.956	28.921	54.066	2	78.827	2.175	3.000	52.58
2683	NESC Extreme	6	1.273	1.800	-1.273	1.800	30.544	29.426	112.346	6	78.827	2.194	3.000	53.50
2683	NESC Extreme	7	1.381	1.537	0.097	2.069	16.676	27.370	57.052	3	78.686	2.116	3.000	49.76
2683	NESC Extreme	8	0.097	-2.069	1.381	-1.537	16.676	25.995	54.186	3	-74.843	2.062	3.000	47.26
2683	NESC Extreme	9	-1.381	-1.537	-0.097	-2.069	16.676	25.921	54.032	3	-74.702	2.060	3.000	47.13
2683	NESC Extreme	10	-0.097	2.069	-1.381	1.537	16.676	27.444	57.206	3	78.827	2.119	3.000	49.90

Summary of Tubular Davit Usages:

Tubular Davit Maximum Load Case Segment Weight		
Label Usage %	Number	(lbs)
Davit1	1.33	NESC Extreme
	1	77.9
Davit2	8.45	NESC Heavy
	1	77.9
Davit3	2.28	NESC Heavy
	1	321.0
Davit4	4.98	NESC Heavy
	1	321.0
Davit5	3.03	NESC Heavy
	1	434.7
Davit6	7.08	NESC Heavy
	1	434.7
Davit7	2.36	NESC Heavy
	1	321.0
Davit8	5.04	NESC Heavy
	1	321.0

*** Maximum Stress Summary for Each Load Case

Summary of Maximum Usages by Load Case:

Load Case Maximum Element	Element	Type
Usage %	Label	
NESC Heavy	68.81	2683 Steel Pole
NESC Extreme	65.74	2683 Steel Pole

Summary of Steel Pole Usages by Load Case:

Load Case Maximum Steel Pole Segment		
Usage %	Label	Number

NESC Heavy	68.81	2683	25
NESC Extreme	65.74	2683	25

Summary of Base Plate Usages by Load Case:

Load Case	Pole Bend Length Label Line #	Vertical Load (in)	X Moment (kips)	Y Bending Moment (ft-k)	Stress (ksi)	Bolt Moment Acting On Sum Bend Line (ft-k)	# Bolts	Max Bolt Load For Bend Line (kips)	Minimum Plate Thickness (in)	Usage %
NESC Heavy	2683	6 30.544	48.478 1846.381	-3.851 31.165	118.987	6	83.720	2.258	56.66	
NESC Extreme	2683	6 30.544	23.902 1785.775	-1.173 29.426	112.346	6	78.827	2.194	53.50	

Summary of Tubular Davit Usages by Load Case:

Load Case	Maximum Tubular Davit Segment Usage %	Label	Number
NESC Heavy	8.45	Davit2	1
NESC Extreme	3.21	Davit2	1

Summary of Insulator Usages:

Insulator Label	Insulator Type	Maximum Usage %	Load Case Weight (lbs)
Clamp1	Clamp	3.00	NESC Heavy 0.0
Clamp2	Clamp	3.00	NESC Heavy 0.0
Clamp3	Clamp	3.29	NESC Heavy 0.0
Clamp4	Clamp	3.29	NESC Heavy 0.0
Clamp5	Clamp	3.29	NESC Heavy 0.0
Clamp6	Clamp	3.29	NESC Heavy 0.0
Clamp7	Clamp	3.29	NESC Heavy 0.0
Clamp8	Clamp	3.29	NESC Heavy 0.0
Clamp9	Clamp	0.76	NESC Heavy 0.0
Clamp10	Clamp	0.76	NESC Heavy 0.0
Clamp11	Clamp	0.76	NESC Heavy 0.0
Clamp12	Clamp	0.76	NESC Heavy 0.0
Clamp13	Clamp	0.76	NESC Heavy 0.0
Clamp14	Clamp	0.54	NESC Heavy 0.0
Clamp15	Clamp	0.54	NESC Heavy 0.0
Clamp16	Clamp	0.54	NESC Heavy 0.0
Clamp17	Clamp	0.54	NESC Heavy 0.0
Clamp21	Clamp	12.42	NESC Extreme 0.0
Clamp23	Clamp	3.07	NESC Extreme 0.0

Loads At Insulator Attachments For All Load Cases:

Load Case	Insulator Label	Insulator Type	Structure Attach Label	Structure Attach Load X (kips)	Structure Attach Load Y (kips)	Structure Attach Load Z (kips)
NESC Heavy	Clamp1	Clamp	Davit1:End	0.000	2.250	0.840
NESC Heavy	Clamp2	Clamp	Davit2:End	0.000	2.250	0.840
NESC Heavy	Clamp3	Clamp	Davit3:End	0.000	2.305	1.263
NESC Heavy	Clamp4	Clamp	Davit4:End	0.000	2.305	1.263
NESC Heavy	Clamp5	Clamp	Davit5:End	0.000	2.305	1.263
NESC Heavy	Clamp6	Clamp	Davit6:End	0.000	2.305	1.263
NESC Heavy	Clamp7	Clamp	Davit7:End	0.000	2.305	1.263
NESC Heavy	Clamp8	Clamp	Davit8:End	0.000	2.305	1.263
NESC Heavy	Clamp9	Clamp	2683:WVGD1	0.000	0.068	0.602
NESC Heavy	Clamp10	Clamp	2683:WVGD2	0.000	0.068	0.602
NESC Heavy	Clamp11	Clamp	2683:WVGD3	0.000	0.068	0.602
NESC Heavy	Clamp12	Clamp	2683:WVGD4	0.000	0.068	0.602
NESC Heavy	Clamp13	Clamp	2683:WVGD5	0.000	0.068	0.602
NESC Heavy	Clamp14	Clamp	2683:WVGD6	0.000	0.050	0.430

NESC Heavy	Clamp15	Clamp	2683:WVG7	0.000	0.050	0.430	0.433
NESC Heavy	Clamp16	Clamp	2683:WVG8	0.000	0.050	0.430	0.433
NESC Heavy	Clamp17	Clamp	2683:WVG9	0.000	0.050	0.430	0.433
NESC Heavy	Clamp21	Clamp	2683:TopConn	0.000	3.009	8.453	8.973
NESC Heavy	Clamp23	Clamp	2683:BotConn	0.000	-0.712	1.812	1.947
NESC Extreme	Clamp1	Clamp	Davit1:End	0.000	1.129	0.208	1.148
NESC Extreme	Clamp2	Clamp	Davit2:End	0.000	1.129	0.208	1.148
NESC Extreme	Clamp3	Clamp	Davit3:End	0.000	1.484	0.367	1.529
NESC Extreme	Clamp4	Clamp	Davit4:End	0.000	1.484	0.367	1.529
NESC Extreme	Clamp5	Clamp	Davit5:End	0.000	1.484	0.367	1.529
NESC Extreme	Clamp6	Clamp	Davit6:End	0.000	1.484	0.367	1.529
NESC Extreme	Clamp7	Clamp	Davit7:End	0.000	1.484	0.367	1.529
NESC Extreme	Clamp8	Clamp	Davit8:End	0.000	1.484	0.367	1.529
NESC Extreme	Clamp9	Clamp	2683:WVG1	0.000	0.161	0.139	0.213
NESC Extreme	Clamp10	Clamp	2683:WVG2	0.000	0.161	0.139	0.213
NESC Extreme	Clamp11	Clamp	2683:WVG3	0.000	0.161	0.139	0.213
NESC Extreme	Clamp12	Clamp	2683:WVG4	0.000	0.161	0.139	0.213
NESC Extreme	Clamp13	Clamp	2683:WVG5	0.000	0.161	0.139	0.213
NESC Extreme	Clamp14	Clamp	2683:WVG6	0.000	0.107	0.099	0.146
NESC Extreme	Clamp15	Clamp	2683:WVG7	0.000	0.107	0.099	0.146
NESC Extreme	Clamp16	Clamp	2683:WVG8	0.000	0.107	0.099	0.146
NESC Extreme	Clamp17	Clamp	2683:WVG9	0.000	0.107	0.099	0.146
NESC Extreme	Clamp21	Clamp	2683:TopConn	0.000	8.981	4.258	9.939
NESC Extreme	Clamp23	Clamp	2683:BotConn	0.000	-2.270	0.938	2.456

Overturning Moments For User Input Concentrated Loads:

Moments are static equivalents based on central axis of 0.0 (i.e. a single pole).

Load Case	Total Load (kips)	Total Long. Load (kips)	Total Vert. Load (kips)	Transverse Overturning Moment (ft-k)	Longitudinal Overturning Moment (ft-k)
NESC Heavy	21.167	0.000	24.253	1651.015	-0.000
NESC Extreme	19.106	0.000	8.905	1513.677	-0.000

*** Weight of structure (lbs):
 Weight of Tubular Davit Arms: 2309.3
 Weight of Steel Poles: 13920.9
 Total: 16230.2

*** End of Report

Subject:

Anchor Bolt Analysis
 CL&P Pole #2683

Location:

Brookfield, CT

Rev. 1: 6/29/11

Prepared by: T.J.L. Checked by: C.F.C.
 Job No. 11021.CO50

Anchor Bolt Analysis:

Input Data:

Bolt Force:

Maximum Tensile Force = $T_{Max} := 83.7 \text{ kips}$ (User Input from PLS-Pole)

Anchor Bolt Data:

Use ASTM A615 Grade 75

Number of Anchor Bolts = $N := 12$ (User Input)

Bolt "Column" Distance = $l := 3.0 \text{ in}$ (User Input)

Bolt Ultimate Strength = $F_u := 100 \text{ ksi}$ (User Input)

Bolt Yield Strength = $F_y := 75 \text{ ksi}$ (User Input)

Bolt Modulus = $E := 29000 \text{ ksi}$ (User Input)

Diameter of Anchor Bolts = $D := 2.25 \text{ in}$ (User Input)

Threads per Inch = $n := 4.5$ (User Input)

Anchor Bolt Analysis:

Calculated Anchor Bolt Properties:

Net Area of Bolt =

$$A_n := \frac{\pi}{4} \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 = 3.248 \text{ in}^2$$

Bolt Tension Check:

Allowable Tensile Force (Net Area) =

$$T_{ALL.Net} := 1.0 \cdot (A_n \cdot F_y) = 243.576 \text{ kips}$$

Bolt Tension % of Capacity =

$$\frac{T_{Max}}{T_{ALL.Net}} = 34.36\%$$

Condition1 =

$$\text{Condition1} := \text{if} \left(\frac{T_{Max}}{T_{ALL.Net}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Condition1 = "OK"

TTAW-07BP111-001 TMA Twin Dual Band AWS with 700 Bypass 13 dB AISG

ELECTRICAL SPECIFICATIONS

UL Frequency Range (MHz)	1710-1770 with 698-746 bypass
UL Rejection	>80 dB TX rejection, >25 dB rejection at 1700 and 1800 MHz
UL Gain(dB)	13
UL Return Loss	>18 dB
UL Noise Figure	<1.6 dB
UL Output 3rd Order Intercept Point(dBm)	>+23 (Input IP3 >+11)
UL Bypass Loss(dB)	<1.9
UL Max Input Power (dBm)	+14 dBm
DL Frequency Range (MHz)	2110-2170 with 698-746 bypass
DL Return Loss	>18 dB
DL Insertion Loss (dB)	<0.4
Intermodulation	<-155 dBc (2x43 dBm TX)
Input Voltage (V)	8.0-30V (AISG Mode 10-30V; Current Alarm Mode 8-17)
Alarm Functionality	AISG compatible or in case of no AISG command received, current alarm mode 170-190 mA
Power Consumption	<1.5 W
Power Handling, RMS	700: 500 W; AWS 300W
AISG Compatibility	AISG 1.1 fully upgradable to AISG 2.0 (AISG version only depended on loaded SW version) TTAW-07BP112-001 has AISG 2.0 loaded from factory

MECHANICAL SPECIFICATIONS

Dimension HxWxD mm(ft)	250x169x139 (9.9"x6.7"x5.4")
Weight(lbs)	<18 (<8 kg)
Colors	Off white (NCS 1502-R)
RF Connectors	Female 7/16 DIN, long neck
Mounting Kit	Mounting kit for pole and wall is included

ENVIRONMENTAL SPECIFICATIONS

Temperature Range	-40 to +65°C
Operational	ETS 300 019-1-4
Transportation	ETS 300 019-1-2
Storage	ETS 300 019-1-1
Lightning Protection	IEC 61312-1: 2 kA 8/20 µs, 3 kA 10/350 µs
Housing	Aluminium
MTBF	>1 million hours
Ingress Protection	IP67 minimum

APPROVAL AND TESTS

Safety	UL 60950; UL 1950, TUV
EMC	FCC part 15



*All specifications subject to change without notice. Contact your Powerwave representative for complete performance data.

P65-16-XLH-RR**Dual Broadband Antennas**POLARIZATION: Dual linear $\pm 45^\circ$

FREQUENCY (MHz): 698-894, 1710-2170

HORIZONTAL BEAM WIDTH ($^\circ$): 65, 65

GAIN (dBi/dBd): 15.5/13.4 17.5/15.4

TILT: 1-12, 0-8

LENGTH: 72"

ELECTRICAL SPECIFICATIONS*

	698-894		1710-2170		
Frequency range (MHz)	698-806	806-894	1710-1880	1850-1990	1900-2170
Frequency band (MHz)	14.8/12.7	15.5/13.4	16.9/14.8	17.2/15.1	17.5/15.4
Gain (dBi/dBd)	Dual Linear +/- 45		Dual Linear +/- 45		
Polarization	50		50		
Nominal Impedance (Ω)	< 1.5:1		< 1.5:1		
VSWR	66	65	60	63	63
Horizontal beam width, -3 dB ($^\circ$)	14.7	12.5	6.8	6.4	5.7
Vertical beam width, -3 dB ($^\circ$)	1 to 12		0 to 8		
Electrical down tilt ($^\circ$)	> 16	> 16	> 16		
Side lobe suppression, vertical 1st upper (dB)	> 16	> 16	> 16		
Isolation between inputs (dB)	> 30	> 30	> 30	> 30	
Inter band Isolation (dB)	> 40		> 40		
Tracking, horizontal plane $\pm 60^\circ$ (dB)	< 2		< 2	< 2	< 2
First null fill (dB)			> -20	> -20	> -20
Vertical beam squint ($^\circ$)	< 0.8	< 0.8	< 0.5	< 0.5	< 0.5
Front to back ratio (dB) $180^\circ \pm 30^\circ$ copolar	> 24	> 24	> 30	> 30	> 28
Front to back ratio (dB) $180^\circ \pm 30^\circ$ total power					
Cross polar discrimination (XPD) 0° (dB)	> 15	> 15	> 15	> 15	> 15
Cross polar discrimination (XPD) $\pm 60^\circ$ (dB)	> 10	> 10	> 10	> 10	> 10
Far field coupling					
IM3, 2xTx@43dBm (dBc)	< -153		< -153		
IM7, 2xTx@43dBm (dBc)					
Power handling, average per input (W)	500		250		
Power handling, average total (W)	1000		500		

MECHANICAL SPECIFICATIONS*

Connector	4 X 7/16 DIN Female, IP67
Connector position	Bottom
Dimensions, HxWxD, mm (ft)	72" x 12" x 6" (1829 x 305 x 152)
Mounting	Pre-mounted Tilt Brackets
Weight, with brackets, kg (lbs)	29 (64)
Weight, without brackets, kg (lbs)	24 (53)
Wind load, frontal/lateral/rear side 42 m/s Cd=1.6 (N)	1380
Maximum operational wind speed, m/s (mph)	100 (45)
Survival wind speed, m/s (mph)	150 (67)
Lightning protection	DC Ground
Operating Temperature	-40C to +60C
Radome material	PVC, IP55
Packet size, HxWxD, mm (ft)	87" x 16" x 10" (2225 x 400 x 225)
Radome colour	Light Grey
Shipping weight, kg (lbs)	34 (75)
RET	iRET AISGv1.1, MET and AISGv2.0
Brackets	7256.00, 7454.00



*All specifications subject to change without notice. Please contact your Powerwave representative for complete performance data.

ANTENNA PATTERNS*

For detailed patterns visit <http://www.powerwave.com/rpa/>.



New Cingular Wireless PCS, LLC
500 Enterprise Drive
Rocky Hill, Connecticut 06067-3900
Phone: (860) 463-5511
Fax: (860) 513-7190

Douglas L. Culp
Real Estate Consultant

July 7, 2011

Honorable Bill Davidson
Brookfield Town Hall
100 Pocono Road, #201
PO Box 5106
Brookfield, CT 06804

Re: Telecommunications Facility – 761 Federal Road Brookfield, CT


Dear First Selectman Davidson:

In order to accommodate technological changes, implement Uniform Mobile Telecommunications System (“UMTS”) and Long Term Evolution (“LTE”) capabilities, and enhance system performance in the State of Connecticut, New Cingular Wireless PCS, LLC (“AT&T”) will be changing its equipment configuration at certain cell sites.

As required by Regulations of Connecticut State Agencies (“R.C.S.A.”) Section 16-50j-73, the Connecticut Siting Council has been notified of the changes and will review AT&T’s proposal. Please accept this letter as notification under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The accompanying letter to the Siting Council fully describes Cingular’s proposal for the referenced cell site. However, if you have any questions or require any further information on our plans or the Siting Council’s procedures; please call me at (860) 463-5511 or Ms. Linda Roberts, Executive Director, Connecticut Siting Council at (860) 827-2935.

Sincerely,



Douglas L. Culp
Real Estate Consultant

Enclosure