



Crown Castle
3 Corporate Park Drive, Suite 101
Clifton Park, NY 12065

April 30, 2018

Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Notice of Exempt Modification for Sprint Crown Site BU: 845993
Sprint Site ID: CT54XC708
12 Nepaug Road, Burlington, Hartford County, CT 06013
Latitude: 41° 46' 56.86" / Longitude: -72° 59' 22.68"

Dear Ms. Bachman:

Sprint currently maintains (3) antennas at the 119-foot level of the existing 119.5-foot monopole at 12 Nepaug Road, Burlington, Connecticut 06013. The tower is owned by Crown Castle. The property is owned by American Tower. Sprint intends to install (3) antennas, (4) lines, and (12) RRHs.

The facility was approved by the Connecticut Siting Council's on February 18, 2004, Docket No. 268. This approval was given subject to the following conditions, listed below as represented in the original decision:

1. The tower shall be constructed no taller than necessary to provide the proposed telecommunications services, sufficient to accommodate the antennas of AT&T Wireless and other entities, both public and private, but such tower shall not exceed a height of 120 feet above ground level.
2. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plan shall be submitted to and approved by the Council prior to the commencement of facility construction and shall include:
 - a) a final site plan(s) of site development to include specifications for the tower, tower foundation, antennas, equipment building, access road, utility line, and landscaping; and
 - b) construction plans for site clearing, water drainage, and erosion and sedimentation control consistent with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended.
3. The Certificate Holder shall, prior to the commencement of operation, provide the Council worst-case modeling of electromagnetic radio frequency power density of all proposed entities' antennas at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65, August

1997. The Certificate Holder shall ensure a recalculated report of electromagnetic radio frequency power density is submitted to the Council if and when circumstances in operation cause a change in power density above the levels calculated and provided pursuant to this Decision and Order.

4. Upon the establishment of any new State or federal radio frequency standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.
5. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
6. The Certificate Holder shall provide reasonable space on the tower for no compensation for any municipal antennas, provided such antennas are compatible with the structural integrity of the tower.
7. If the facility does not initially provide wireless services within one year of completion of construction or ceases to provide wireless services for a period of one year, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made.
8. Any antenna that becomes obsolete and ceases to function shall be removed within 60 days after such antennas become obsolete and cease to function.
9. Unless otherwise approved by the Council, this Decision and Order shall be void if the facility authorized herein is not operational within one year of the effective date of this Decision and Order or within one year after all appeals to this Decision and Order have been resolved.

Sprint's proposed installation complied with all of the conditions referenced above.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.S.C.A. § 16-50j-73, a copy of this letter is being sent to Mr. Theodore Shafer, First-Selectman, Town of Burlington, Mr. Richard A. Miller, Chairman of the Town of Burlington's Planning & Zoning Commission, the property owner GLP Cell Site IV, LLC (American Tower), and Crown Castle is the tower owner.

1. The proposed modifications will not result in an increase in the height of the existing tower.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modification will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communication Commission safety standard.

Melanie A. Bachman

April 30, 2018

Page 3

5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Anne Marie Zsamba.

Sincerely,



Anne Marie Zsamba, Esq.

Real Estate Specialist

3 Corporate Park Drive, Suite 101, Clifton Park, NY 12065

(518) 350-3639

annemarie.zsamba.contractor@crowncastle.com

Attachments:

Tab A: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab B: Exhibit-2: Structural Modification Report

Tab C: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mr. Theodore Shafer, First-Selectman
Burlington Town Hall
200 Spielman Highway
Burlington, CT 06013
(860) 673-6789 ext.1

Planning & Zoning Commission
Mr. Richard A. Miller, Chair
Burlington Town Hall
200 Spielman Highway
Burlington, CT 06013
(860) 673-6789 ext.6

GLP Cell Site IV, LLC
C/O American Tower
29637 Network Place
Chicago, IL 60673-1296

DOCKET NO. 268 - AT&T Wireless PCS, LLC d/b/a AT&T Wireless application for a Certificate of Environmental Compatibility and Public Need for the construction, maintenance and operation of a wireless telecommunications facility located near Lyon and Nepaug Roads in Burlington, Connecticut.	} } } }	Connecticut Siting Council February 18, 2004
--	------------------	---

**Decision and Order:
Burlington Site CT-828**

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council (Council) finds that the effects associated with the construction, operation, and maintenance of a telecommunications facility including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not disproportionate either alone or cumulatively with other effects when compared to need, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the proposed site, located at the intersection of Lyon and Nepaug Roads, Burlington, Connecticut.

The facility shall be constructed, operated, and maintained substantially as specified in the Council's record in this matter, and subject to the following conditions:

1. The tower shall be constructed no taller than necessary to provide the proposed telecommunications services, sufficient to accommodate the antennas of AT&T Wireless and other entities, both public and private, but such tower shall not exceed a height of 120 feet above ground level.
2. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plan shall be submitted to and approved by the Council prior to the commencement of facility construction and shall include:
 - a) a final site plan(s) of site development to include specifications for the tower, tower foundation, antennas, equipment building, access road, utility line, and landscaping; and
 - b) construction plans for site clearing, water drainage, and erosion and sedimentation control consistent with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended.
3. The Certificate Holder shall, prior to the commencement of operation, provide the Council worst-case modeling of electromagnetic radio frequency power density of all proposed entities' antennas at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65, August 1997. The Certificate Holder shall ensure a recalculated report of electromagnetic radio frequency power density is submitted to the Council if and when circumstances in operation cause a change in power density above the levels calculated and provided pursuant to this Decision and Order.

4. Upon the establishment of any new State or federal radio frequency standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.
5. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
6. The Certificate Holder shall provide reasonable space on the tower for no compensation for any municipal antennas, provided such antennas are compatible with the structural integrity of the tower.
7. If the facility does not initially provide wireless services within one year of completion of construction or ceases to provide wireless services for a period of one year, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made.
8. Any antenna that becomes obsolete and ceases to function shall be removed within 60 days after such antennas become obsolete and cease to function.
9. Unless otherwise approved by the Council, this Decision and Order shall be void if the facility authorized herein is not operational within one year of the effective date of this Decision and Order or within one year after all appeals to this Decision and Order have been resolved.

Pursuant to General Statutes § 16-50p, we hereby direct that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below, and notice of issuance shall be published in The Hartford Courant.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of Connecticut State Agencies.

The parties and intervenors to this proceeding are:

Applicant

AT&T Wireless PCS, LLC
d/b/a AT&T Wireless

Intervenor

Sprint Spectrum, L.P.
d/b/a Sprint PCS

Its Representative

Christopher B. Fisher, Esq.
Cuddy & Feder LLP
90 Maple Avenue
White Plains, New York 10601

Its Representative

Thomas J. Regan, Esq.
Brown Rudnick Berlack Israels
CityPlace 1
185 Asylum Street
Hartford, CT 06103




Property Information

Property Location	12 NEPAUG RD
Owner	AT&T MOBILITY
Co-Owner	
Mailing Address	575 MOROSGO DRIVE SUITE 13-F ATLANTA GA 30324
Land Use	402V Ind Bldg Mdl-00
Land Class	I
Zoning Code	
Census Tract	4101

Neighborhood	
Acreage	0
Utilities	
Lot Setting/Desc	
Additional Info	

Photo



Sketch

Primary Construction Details

Year Built	
Stories	
Building Style	
Building Use	
Building Condition	
Floors	
Total Rooms	

Bedrooms	
Full Bathrooms	
Half Bathrooms	
Bath Style	
Kitchen Style	
Roof Style	
Roof Cover	

Exterior Walls	
Interior Walls	
Heating Type	
Heating Fuel	
AC Type	
Gross Bldg Area	
Total Living Area	



Cypress Rd

Lyon Rd

US 90

Pine Island

Spireman Hwy

Spireman Hwy

1

1

845993



Napang Rd

Lyon Rd

Spireman Hwy

Napang Rd


Charles W Rd

Yokning Rd

Napang Rd

Lyon Rd

Myra Ln



DRAWING NOTICE: THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE WRITTEN CONSENT OF SPRINT.

Table with columns: REVISION, DESCRIPTION, DATE, BY, REV. Includes rows for 'ISSUE BY CONTRACTOR' and 'ISSUE BY SPRINT'.

BURLINGTON-NEPAUG ROAD

PROJECT LOCATION: CT54XC708

THE ADDRESS: 12 NEPAUG ROAD, BURLINGTON, CT 06013

SUBJECT DESCRIPTION: SPRINT SPECIFICATIONS

SET NUMBER: SP-1

3.0 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS... PART 1 - GENERAL

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS: A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

1.3 PRECEDENCE SHOULD EXIST BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS DESCRIBING THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.4 MANUALLY RECOGNIZED CODES AND STANDARDS: A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:

- 1. 01-43-CORE WIRE REQUIREMENTS: PHYSICAL PROTECTION
2. 01-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
3. 01-1088 CODE: ELECTROMAGNETIC COMPATIBILITY AND ELECTROMAGNETIC SAFETY - GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - NEC) AND NFPA 701 (LIFE SAFETY CODE).
5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
6. INSTITUTE OF ELECTRIC AND ELECTRICAL ENGINEERS (IEEE)
7. AMERICAN CONCRETE INSTITUTE (ACI)
8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (ASHTO)
11. PORTLAND CEMENT ASSOCIATION (PCA)
12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
13. BRICK INDUSTRY ASSOCIATION (BIA)
14. AMERICAN WELDERING SOCIETY (AWS)
15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
17. DOOR AND HARDWARE INSTITUTE (DHI)
18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS: A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS. B. COMPANY: SPRINT CORPORATION. C. ENGINEER: ARCHITECT & ENGINEER AND ARCHITECT. D. DESIGN: THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT. E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A/E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK. F. OTHER: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT. G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED EQUIPMENT TO FURNISH THROUGH SPRINT REPRESENTATIVE IN CHANGE OF PROJECT.

1.6 THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL MATERIALS AND EQUIPMENT... PART 2 - PRODUCTS (NOT USED)

1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL BE THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO HANDLE THE PROJECT FOR SPRINT.

1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL STAFF AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEASUREMENTS, RECORDS, INSPECTIONS, AND SHALL MAINTAIN A COMPLETE SET OF RECORDS OF THE WORK. THE CONTRACTOR SHALL MAINTAIN A COMPLETE SET OF RECORDS OF THE WORK. THE CONTRACTOR SHALL MAINTAIN A COMPLETE SET OF RECORDS OF THE WORK.

1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED OF THE CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES.

1.10 USE OF JOB DGS: THE CONTRACTOR SHALL CONFER ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAKE AND SURVEY OF MATERIALS AND EQUIPMENT, PRELIMINARY PROFILES, AND WASTE SPECIFICATIONS TO THE LICENSEE UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 UTILITIES SERVICES: WHERE NECESSARY TO OBTAIN EXISTING UTILITIES, ELECTRICAL WIRING, AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS.

1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONSTRUCTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE OBTAINING AND PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY. 1.14 METHODS OF PROTECTION (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL FURNISH WORK AS DESCRIBED IN THE FOLLOWING REGULATION AND COMMENTS MOPS.

NOTE: IN SHORT-TERM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING 01-2012-001, 01-2013-002, 01-006, AND 01-015

1.15 USE OF ELECTRODYNAMIC PROJECT MANAGEMENT SYSTEMS: PART 3 - EXECUTION

3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 TESTING: REQUIREMENTS FOR THE TESTS BE THE CONTRACTOR SHALL BE AS NOTED HEREIN. ON THE CONSTRUCTION DRAWINGS AND IN THE SPECIFICATIONS. THESE SPECIFICATIONS, SHOULD CONTRACTOR CHOOSE TO ENGAGE ANY THIRD PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COMPLY WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 DIMENSIONS VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE PRODUCTION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.6 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.7 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.8 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.9 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.10 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.11 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.12 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.


3.13 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.14 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.15 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.16 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.

3.17 THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, MAINTENANCE, AND REPAIR OF ALL UTILITIES AND FACILITIES IDENTIFIED IN THE CONSTRUCTION DRAWINGS.



6800 Split-Pine Way
Orland Park, Illinois 60451



FROM ZERO TO INFINIGY
The solutions are endless
105 North...
Phone: 616-450-2776 | Fax: 616-450-2775
www.infinigy.com
25 SUMMIT SP-20



THESE DOCUMENTS ARE CONTRACTUAL AND ARE THE SOLE PROPERTY OF SPIN/PAUL AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPIN/PAUL.

REVISIONS	DESCRIPTION	DATE BY	REV
1	ISSUED FOR CONSTRUCTION	4/17/08	0

BURLINGTON-NEPAUG ROAD

CTS4X4C708

12 NEPAUG ROAD
BURLINGTON, CT 06013

SPRINT SPECIFICATIONS

SP-2

CONTINUE FROM SP-1

- PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
- PROVIDE GROUND BERS, TRENCH DE-CORROSION, AND ROUGH AND FINAL GROUND, AND COMPANION SURFACE REQUIREMENTS.
- MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL, AND TOWER BARRICADE.
- INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER, AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEMS.
- INSTALL ABOVE GROUND GROUNDING SYSTEMS.
- PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
- INSTALL "I-FRAMES", CHIMNEYS AND SHEDS AS INDICATED.
- ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
- PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
- PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
- INSTALL RIGID GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- INSTALL CELL SELL SITE BARRIERS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL ACTIVITIES THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
- PERFORM ANTENNA AND COAX SNEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
- REMOVE ON SITE OBTAINED THROUGHOUT HAND-OFF AND INTERFERE TO PLACED "ON AIR".

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, EXCESS MATERIAL, EXCESS WATER, EXCESS FUEL, EXCESS OIL, EXCESS FUEL, EXCESS FACILITIES, AND SUPPLIES MATERIALS.
- EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED ROOM CLEAN AND CLEAR OF DEBRIS.
- CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISORDER AND LOOSE ANY HAZARDOUS CONDITION.
- IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN AVOIDED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL SUBCONTRACTORS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
- CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE INTRODUCED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE MATERIALS TO THE HAZARD.

3.3 DELIVERABLES:

- CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER.
- PROVIDE BOOKKEEPING INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING: DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO S&S.
- ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
- PROJECT PROGRESS REPORTS.
- CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).

- POWER INSTALL DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- TELCO READY DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- FPIC (OR SHEETER) INSTALL DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- TOWER CONSTRUCTION START DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- SIS AND RAMP EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- NETWORK OPERATORS HANDOFF CHECKLIST (DOC WALK) COMPLETE (UPLOADED INTO S&S AND/OR FORWARD NOTIFICATION).
- CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- DATE CONSTRUCTION PROGRESS PHOTOS UPLOADED INTO S&S.

SECTION 01-400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- THE WORK THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONNECTION WITH THIS SECTION SHALL BE PERFORMED BY THE CONTRACTOR.
- RELATED DOCUMENTS
 - THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS WHEREIN.
- SUBMITTALS
 - THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL:
 - CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PILES, AND CONCRETE PILING.
 - CONCRETE BREAD TESTS AS SPECIFIED HEREIN.
 - SPECIAL FINISHES FOR WRECKER SPACES, IF ANY.
 - ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 - CHEMICAL GROUNDING DESIGN.
 - ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW ALL ALTERNATES AND APPROVE OR DENY THEM. ALL ALTERNATES WILL BE CONSIDERED "SUBMITTALS FOR APPROVAL" AND SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PRESENT DOCUMENTATION.
- CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - COAX SNEEPS AND FIBER TESTS PER CURRENT VERSION OF SPRINT'S 10-6000 ANTENNA USE ACCEPTANCE STANDARD.
 - ALL ANTENNA AND IDENTIFY USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 - ANTENNA ALIGNMENT REPORT - UPLOADED REPORT FROM ANTENNA ALIGNMENT TOOL CONFORM TO THE RF DATA SHEETS, GENSES AND FIBER TESTS.
 - SCHEMATIC DRAWING PHOTOGRAPHS OF TOWER TOP AND UNACCESSIBLE SCHEDULED EQUIPMENT.
 - ALL AVAILABLE JURISDICTIONAL INFORMATION.
 - PDF SCAN OF RECORDS PRODUCED IN FIELD.

6. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY UPDATING THE PLANS, ELEVATIONS, AND SECTION DRAWINGS. ALL AS-BUILT DRAWINGS SHALL BE SUBMITTED TO SPRINT AS "AS-BUILT" IDENTIFIED AS THE "AS-BUILT" CONDITION.

- FINAL PAYMENT APPLICATION
- REQUIRED FINAL CONSTRUCTION PHOTOS
- CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFERRED ITEMS
- ALL PLOT RIP TAGS INCLUDING DOCUMENT UPLOADED COMPLETE IN SIERRA (SPRINTS DOCUMENT REPOSITORY OF RECORDS).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE APP'S

1.6 INTERCOM: PERFORM ALL INTERCOM ACTIVITIES AS REQUIRED BY APPLICABLE APP'S

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

- THIRD PARTY TESTING AGENCY:
 - WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE CONTRACTOR SHALL SELECT A QUALIFIED TESTING AGENCY FROM A LOCAL LIST OF QUALIFIED TESTING AGENCIES. THE CONTRACTOR SHALL OBTAIN THROUGHOUT UNDERSTANDING OF THE LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
 - THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE. EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 - EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
 - EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
- REQUIRED TESTS:
 - CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 - FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT PAVS AND ANCHOR LOCATIONS.
 - TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PAVS AND ANCHOR LOCATIONS.
 - STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 - SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 - ANTENNA AND COAX SNEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 - GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 - ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.2 REQUIRED TESTS:

- SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - GROUNDING SYSTEM INSTALLATION PRIOR TO CABLE CONNECTION DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY AEE OR SPRINT REPRESENTATIVE.
 - FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR FOR SPIN/PAUL ANTENNA FOUNDATION.
 - CONSTRUCTION OF SCHEDULED MATERIALS AGGREGATE BASE FOR ROADS, PAVS, AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 - PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 - TOWER ERECTION STRUCTURE AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS PER THIRD PARTY AGENCY.
 - ANTENNA CENTER, BENCH IN, AND PER SUNLIGHT TOOL, SUNSHINE INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAI)

3.3 REQUIRED INSPECTIONS

- SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - GROUNDING SYSTEM INSTALLATION PRIOR TO CABLE CONNECTION DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY AEE OR SPRINT REPRESENTATIVE.
 - FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR FOR SPIN/PAUL ANTENNA FOUNDATION.
 - CONSTRUCTION OF SCHEDULED MATERIALS AGGREGATE BASE FOR ROADS, PAVS, AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 - PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 - TOWER ERECTION STRUCTURE AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS PER THIRD PARTY AGENCY.
 - ANTENNA CENTER, BENCH IN, AND PER SUNLIGHT TOOL, SUNSHINE INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAI)

7. ERECTION AND ANTENNA INSTALL DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).

- POWER INSTALL DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- TELCO READY DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- FPIC (OR SHEETER) INSTALL DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- TOWER CONSTRUCTION START DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- SIS AND RAMP EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- NETWORK OPERATORS HANDOFF CHECKLIST (DOC WALK) COMPLETE (UPLOADED INTO S&S AND/OR FORWARD NOTIFICATION).
- CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN S&S AND/OR FORWARD NOTIFICATION).
- DATE CONSTRUCTION PROGRESS PHOTOS UPLOADED INTO S&S.

SECTION 01-400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- THE WORK THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONNECTION WITH THIS SECTION SHALL BE PERFORMED BY THE CONTRACTOR.
- RELATED DOCUMENTS
 - THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - SPRINT STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS WHEREIN.
- SUBMITTALS
 - THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL:
 - CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PILES, AND CONCRETE PILING.
 - CONCRETE BREAD TESTS AS SPECIFIED HEREIN.
 - SPECIAL FINISHES FOR WRECKER SPACES, IF ANY.
 - ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 - CHEMICAL GROUNDING DESIGN.
 - ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW ALL ALTERNATES AND APPROVE OR DENY THEM. ALL ALTERNATES WILL BE CONSIDERED "SUBMITTALS FOR APPROVAL" AND SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:


- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PRESENT DOCUMENTATION.
- CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - COAX SNEEPS AND FIBER TESTS PER CURRENT VERSION OF SPRINT'S 10-6000 ANTENNA USE ACCEPTANCE STANDARD.
 - ALL ANTENNA AND IDENTIFY USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 - ANTENNA ALIGNMENT REPORT - UPLOADED REPORT FROM ANTENNA ALIGNMENT TOOL CONFORM TO THE RF DATA SHEETS, GENSES AND FIBER TESTS.
 - SCHEMATIC DRAWING PHOTOGRAPHS OF TOWER TOP AND UNACCESSIBLE SCHEDULED EQUIPMENT.
 - ALL AVAILABLE JURISDICTIONAL INFORMATION.
 - PDF SCAN OF RECORDS PRODUCED IN FIELD.

3.2 REQUIRED TESTS:


- SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - GROUNDING SYSTEM INSTALLATION PRIOR TO CABLE CONNECTION DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY AEE OR SPRINT REPRESENTATIVE.
 - FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR FOR SPIN/PAUL ANTENNA FOUNDATION.
 - CONSTRUCTION OF SCHEDULED MATERIALS AGGREGATE BASE FOR ROADS, PAVS, AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 - PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 - TOWER ERECTION STRUCTURE AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS PER THIRD PARTY AGENCY.
 - ANTENNA CENTER, BENCH IN, AND PER SUNLIGHT TOOL, SUNSHINE INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAI)

3.3 REQUIRED INSPECTIONS

- SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - GROUNDING SYSTEM INSTALLATION PRIOR TO CABLE CONNECTION DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY AEE OR SPRINT REPRESENTATIVE.
 - FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR FOR SPIN/PAUL ANTENNA FOUNDATION.
 - CONSTRUCTION OF SCHEDULED MATERIALS AGGREGATE BASE FOR ROADS, PAVS, AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 - PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 - TOWER ERECTION STRUCTURE AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS PER THIRD PARTY AGENCY.
 - ANTENNA CENTER, BENCH IN, AND PER SUNLIGHT TOOL, SUNSHINE INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAI)



PLANS PREPARED FOR:
INFINIGY
 FROM ZERO TO INFINITY
 THE NEW WIRELESS GENERATION
 1033 BRANTLEY DRIVE, SUITE 200
 OVERLAND PARK, KANSAS 66204
 PHONE: 913-888-2276 | FAX: 913-888-9733
 WWW.INFINIGY.COM
 JOB NUMBER: 154-00



DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR TRANSMITTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.


REVISION	DESCRIPTION	DATE	BY	REV

BURLINGTON-NERPAUG ROAD
 SITE PACKAGE:
CTS4XC708


12 NERPAUG ROAD
 BURLINGTON, CT 06013

SHEET DESCRIPTION:
EQUIPMENT & MOUNTING DETAILS



SHEET NUMBER:
A-4



800 MHz RRH
 NO SCALE
 2



2.5 RRH'S
 NO SCALE
 1



2.5 ANTENNA
 NO SCALE
 3



Date: January 12, 2018

Chanhdara Ratsavong
Crown Castle
3530 Toringdon Way Suite 300
Charlotte, NC 28277

Crown Castle
2000 Corporate Drive
Canonsburg, PA 15317
(724) 416-9056

Subject: Structural Analysis Report

Carrier Designation: *Sprint PCS Co-Locate*
Carrier Site Number: CT54XC708
Carrier Site Name: BURLINGTON-NEPAUG ROAD

Crown Castle Designation:
Crown Castle BU Number: 845993
Crown Castle Site Name: BURLINGTON-NEPAUG ROAD
Crown Castle JDE Job Number: 474268
Crown Castle Work Order Number: 1511579
Crown Castle Application Number: 418450 Rev. 0

Engineering Firm Designation: **Crown Castle Project Number:** 1511579

Site Data: 12 Nepaug Road, Burlington, Hartford County, CT
Latitude 41° 46' 56.86", Longitude -72° 59' 22.68"
120 Foot - Monopole Tower

Dear Chanhdara Ratsavong,

Crown Castle is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 1511579, in accordance with application 418450, revision 0.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment **Sufficient Capacity**
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

This analysis has been performed in accordance with the 2016 Connecticut State Building Code based upon an ultimate 3-second gust wind speed of 120 mph converted to a nominal 3-second gust wind speed of 93 mph per Section 1609.3 and Appendix N as required for use in the TIA-222-G Standard per Exception #5 of Section 1609.1.1. Exposure Category B and Risk Category II were used in this analysis.

All modifications and equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.


We at Crown Castle appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Luis Zarate/ KB

Respectfully submitted by:

Maham Barimani, P.E.
Senior Project Engineer

tnxTower Report - version 7.0.5.1



01-12-2018

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Components vs. Capacity – LC7

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 120 ft Monopole tower designed by Engineered Endeavors, Inc. and mapped by FDH in February of 2016. The original design and wind speed are unknown.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA-222-G Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a 3-second gust wind speed of 93 mph with no ice, 40 mph with 1 inch ice thickness and 60 mph under service loads, exposure category B.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
109.0	110.0	6	alcatel lucent	RRH2X50-800	3	1-1/4 7/8	-
		3	alcatel lucent	PCS 1900MHZ 4X45W 65MHZ			
		3	alcatel lucent	TD-RRH8X20-25			
		3	kmw communications	ETCR-654L12H6 w/ Mount Pipe			

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
119.0	119.0	6	powerwave technologies	7770.00 w/ Mount Pipe	12 2 2	1-5/8 7/8 1/2	1
		6	powerwave technologies	LGP13519			
		6	powerwave technologies	LGP21401			
		3	ericsson	RRUS-11			
		3	kmw communications	AM-X-CD-16-65-00T-RET w/ Mount Pipe			
		1	gps	GPS_A			
		1	raycap	DC6-48-60-18-8F			
		1	tower mounts	Platform Mount [LP 1201-1]			
109.0	109.0	6	andrew	950F85T2E-M w/ Mount Pipe	6	1-5/8	3
		1	tower mounts	Platform Mount [LP 1201-1]	-	-	1
99.0	99.0	6	commscope	JAHH-65B-R3B w/ Mount Pipe	2	1-5/8	2
		3	alcatel lucent	RRH4X45-AWS4 B66			
		3	nokia	AIRSCALE RRH 4T4R B5 160W			
		3	alcatel lucent	RRH2x60-700			
		2	rfs celwave	DB-T1-6Z-8AB-0Z			
		6	antel	LPA-80080/4CF			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
		1	tower mounts	w/ Mount Pipe Platform Mount [LP 1201-1]			
88.0	90.0	3	commscope	LNX-6515DS-A1M w/ Mount Pipe	7	1-5/8	1
		3	ericsson	ERICSSON AIR 21 B2A B4P w/ Mount Pipe			
	3	ericsson	ERICSSON AIR 21 B4A B2P w/ Mount Pipe				
	88.0	1	tower mounts	T-Arm Mount [TA 602-3]			

Notes:

- 1) Existing Equipment
- 2) Reserved Equipment
- 3) Equipment To Be Removed; Not Considered In This Analysis

Table 3 - Design Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
UNAVAILABLE						

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	Jaworski Geotech, Inc.	4551029	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	FDH Velocitel (Mapped)	6171674	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	URS	5072131	CCISITES
4-TOWER MANUFACTURER DRAWINGS	FDH Velocitel (Mapped)	6172249	CCISITES

3.1) Analysis Method

tnxTower (version 7.0.5.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	120 - 97	Pole	TP28.93x22.69x0.1875	1	-8.70	1079.70	17.6	Pass
L2	97 - 48	Pole	TP39.7x27.5729x0.25	2	-21.51	1957.24	54.3	Pass
L3	48 - 0	Pole	TP51.04x38.0569x0.3125	3	-33.84	3154.51	55.8	Pass
							Summary	
						Pole (L3)	55.8	Pass
						Rating =	55.8	Pass

Table 6 - Tower Component Stresses vs. Capacity – LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	48.6	Pass
1	Base Plate	0	63.6	Pass
1	Base Foundation (Structure)	0	49.2	Pass
1	Base Foundation (Soil Interaction)	0	47.5	Pass

Structure Rating (max from all components) =	63.6%
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.



EBI Consulting

environmental | engineering | due diligence

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT54XC708

Burlington-Nepaug Road
12 Nepaug Road
Burlington, CT 06013

April 24, 2018

EBI Project Number: 6218002919

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	19.42 %



April 24, 2018

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT54XC708 – Burlington-Nepaug Road**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **12 Nepaug Road, Burlington, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



EBI Consulting

environmental | engineering | due diligence

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **12 Nepaug Road, Burlington, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



EBI Consulting

environmental | engineering | due diligence

- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **KMW ETCR-654L12H6** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **110 feet** above ground level (AGL) for **Sector A**, **110 feet** above ground level (AGL) for **Sector B** and **110 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



EBI Consulting

environmental | engineering | due diligence

SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	KMW ETCR-654L12H6	Make / Model:	KMW ETCR-654L12H6	Make / Model:	KMW ETCR-654L12H6
Gain:	13.35 / 15.25/15.05 dBd	Gain:	13.35 / 15.25 / 15.05 dBd	Gain:	13.35 / 15.25 / 15.05 dBd
Height (AGL):	110 feet	Height (AGL):	110 feet	Height (AGL):	110 feet
Frequency Bands	850 MHz / 1900 MHz (PCS) / 2500 MHz (BRS)	Frequency Bands	850 MHz / 1900 MHz (PCS) / 2500 MHz (BRS)	Frequency Bands	850 MHz / 1900 MHz (PCS) / 2500 MHz (BRS)
Channel Count	18	Channel Count	18	Channel Count	18
Total TX Power(W):	380 Watts	Total TX Power(W):	380 Watts	Total TX Power(W):	380 Watts
ERP (W):	11,775.31	ERP (W):	11,775.31	ERP (W):	11,775.31
Antenna A1 MPE%	4.24 %	Antenna B1 MPE%	4.24 %	Antenna C1 MPE%	4.24 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	4.24 %
AT&T	2.52 %
T-Mobile	4.51 %
Verizon Wireless	8.15 %
Site Total MPE %:	19.42 %

SPRINT Sector A Total:	4.24 %
SPRINT Sector B Total:	4.24 %
SPRINT Sector C Total:	4.24 %
Site Total:	19.42 %

SPRINT Frequency Band / Technology Power Values (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	432.54	110	1.44	850 MHz	567	0.25%
Sprint 850 MHz LTE	2	432.54	110	2.88	850 MHz	567	0.51%
Sprint 1900 MHz (PCS) CDMA	5	535.94	110	8.91	1900 MHz (PCS)	1000	0.89%
Sprint 1900 MHz (PCS) LTE	2	1,339.86	110	8.91	1900 MHz (PCS)	1000	0.89%
Sprint 2500 MHz (BRS) LTE	8	639.78	110	17.01	2500 MHz (BRS)	1000	1.70%
Total:							4.24%



EBI Consulting

environmental | engineering | due diligence

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	4.24 %
Sector B:	4.24 %
Sector C:	4.24 %
SPRINT Maximum Total (per sector):	4.24 %
Site Total:	19.42 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **19.42 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Zsamba, Anne Marie (Contractor)

From: TrackingUpdates@fedex.com
Sent: Tuesday, May 1, 2018 10:14 AM
To: Zsamba, Anne Marie (Contractor)
Subject: FedEx Shipment 772108354044 Delivered

Your package has been delivered

Tracking # 772108354044



Ship date:
Mon,
4/30/2018
Rebecca
Alescio
Crown Castle
Clifton Park,
NY 12065
US



Delivery date:
Tue,
5/1/2018
10:12 am
Mr. Theodore
Shafer, First-
Selectman
Burlington
Town Hall
200 Spielman
Highway
BURLINGTON,
CT 06013
US

Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number: 772108354044
Status: Delivered:
05/01/2018 10:12
AM Signed for By:
M.TORRES
Invoice number: 982896
Reference: 1766.668
Signed for by: M.TORRES
Delivery location: Burlington, CT

Delivered to:	Receptionist/Front Desk
Service type:	FedEx Priority Overnight
Packaging type:	FedEx Pak
Number of pieces:	1
Weight:	1.00 lb.
Special handling/Services:	Adult Signature Required
	Deliver Weekday
Standard transit:	5/1/2018 by 10:30 am

 Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 9:13 AM CDT on 05/01/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above. Standard transit is the date and time the package is scheduled to be delivered by, based on the selected service, destination and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our [privacy policy](#). All rights reserved.

Thank you for your business.

ORIGIN ID: GFLA (518) 373-3547
REBECCA ALESCIO
CROWN CASTLE
3 CORPORATE PARK DRIVE
SUITE 101
CLIFTON PARK, NY 12065
UNITED STATES US


SHIP DATE: 30APR18
ACTWTG: 1.00 LB
CAD: 104924194/INFT3980

BILL SENDER

TO MR. THEODORE SHAFER, FIRST-SELECTMAN
BURLINGTON TOWN HALL
200 SPIELMAN HIGHWAY

BURLINGTON CT 06013

(860) 673-6789 X 1 REF: 1786688
NY 982896 DEPT.



J181118012801uv


552.02782B/DCA5

TRK# 7721 0835 4044
0201

TUE - 01 MAY 10:30A
PRIORITY OVERNIGHT

EB HFDA

ASR 06013
BDL CT-US



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Zsamba, Anne Marie (Contractor)

From: TrackingUpdates@fedex.com
Sent: Tuesday, May 1, 2018 10:13 AM
To: Zsamba, Anne Marie (Contractor)
Subject: FedEx Shipment 772108362281 Delivered

Your package has been delivered

Tracking # 772108362281



Ship date:
Mon,
4/30/2018
Rebecca
Alescio
Crown Castle
Clifton Park,
NY 12065
US

Delivery date:
Tue,
5/1/2018
10:12 am
Mr. Richard A
Miller, Chair
Burlington
Town Hall
200 Spielman
Highway
Planning &
Zoning
Commission
BURLINGTON,
CT 06013
US



Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number: 772108362281
Status: Delivered:
05/01/2018 10:12
AM Signed for By:
M.TORRES
Invoice number: 982896
Reference: 1766.668
Signed for by: M.TORRES

Delivery location: Burlington, CT
Delivered to: Receptionist/Front Desk
Service type: FedEx Priority Overnight
Packaging type: FedEx Pak
Number of pieces: 1
Weight: 1.00 lb.
Special handling/Services: Adult Signature Required
Deliver Weekday
Standard transit: 5/1/2018 by 10:30 am

 Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 9:13 AM EDT on 05/01/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above. Standard transit is the date and time the package is scheduled to be delivered by, based on the selected service, destination and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our [privacy policy](#). All rights reserved.

Thank you for your business.


ORIGIN ID: GFLA (519) 373-3547
REBECCA ALESCIO
CROWN CASTLE
3 CORPORATE PARK DRIVE
SUITE 101
CLIFTON PARK, NY 12065
UNITED STATES US

SHIP DATE: 30APR18
ACTWTG: 1.00 LB
CAD: 104924194MINET3980

BILL SENDER

TO MR. RICHARD A MILLER, CHAIR
BURLINGTON TOWN HALL
200 SPIELMAN HIGHWAY
PLANNING & ZONING COMMISSION
BURLINGTON CT 06013
(860) 673-6789 X 6 REF: 1766.638
INV: 962896 DEPT:

552.12/782B/DCA5



J19118012501uv


TRK# 7721 0836 2281
0201

TUE - 01 MAY 10:30A
PRIORITY OVERNIGHT

EB HFDA

CT-US

ASR 06013
BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Zsamba, Anne Marie (Contractor)

From: TrackingUpdates@fedex.com
Sent: Tuesday, May 1, 2018 9:30 AM
To: Zsamba, Anne Marie (Contractor)
Subject: FedEx Shipment 772108372639 Delivered



Your package has been delivered

Tracking # 772108372639

Ship date:
Mon,
4/30/2018
Rebecca
Alescio
Crown Castle
Clifton Park,
NY 12065
US

Delivery date:
Tue,
5/1/2018
8:28 am
C/O
American
Tower
GLP Cell Site
IV, LLC
FedEx Facility
875 WEST
DIVISION
CHICAGO, IL
60642
US



Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number: 772108372639
Status: Delivered:
05/01/2018
08:28 AM
Signed for By:
W.COLE
Invoice number: 982896
Reference: 1766.668
Signed for by: W.COLE

Delivery location: CHICAGO, IL
Delivered to: FedEx Location
Service type: FedEx Priority
Overnight
Packaging type: FedEx Pak
Number of pieces: 1
Weight: 1.00 lb.
Special handling/Services: Adult Signature
Required
Hold at Location
Standard transit: 5/1/2018 by
9:00 am

 Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 8:30 AM CDT on 05/01/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above. Standard transit is the date and time the package is scheduled to be delivered by, based on the selected service, destination and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our [privacy policy](#). All rights reserved.


Thank you for your business.

ORIGIN ID: GFLA (518) 373-3547
REBECCA ALESCIO
CROWN CASTLE
3 CORPORATE PARK DRIVE
SUITE 101
CLIFTON PARK NY 12065
UNITED STATES US


SHIP DATE: 30APR18
ACTWTG: 1.00 LB
CAD: 104924194/NET/3980
BILL SENDER

TO
C/O AMERICAN TOWER
GLP CELL SITE IV, LLC
29637 NETWORK PLACE

CHICAGO IL 60673
(312) 467-1262 REF: 1766968
INV: 962896 DEPT:



TRK# 7721 0837 2639
0201
TUE - 01 MAY 10:30A
PRIORITY OVERNIGHT
ASR
60673
IL-US
ORD



552.12/782B/DC/5

After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

CROWN CASTLE - ETA PROPERTY
3530 TORINGDON WAY, SUITE 300
CHARLOTTE, NC 28277

13834

DATE

4/30/18

32-67/1110

PAY TO THE ORDER OF

Connecticut State Council

100

\$ 625.00

VALID FOR 180 DAYS

DOLLARS



Member Since 01/01/18

JP Morgan Chase Bank, N.A.



www.chase.com

Sprint account # 845993
418450 474208

FOR

⑆013834⑆ ⑆11100061⑆

⑆451638118⑆

⑆

ORIGIN ID:GFLA (518) 373-3547
REBECCA ALESCIO
CROWN CASTLE
3 CORPORATE PARK DRIVE
SUITE 101
CLIFTON PARK, NY 12065
UNITED STATES US

SHIP DATE: 01MAY18
ACTWGT: 2.00 LB
CAD: 104924194IN/NET3980


BILL SENDER

TO **MELANIE BACHMAN**
CONNECTICUT SITING COUNCIL
10 FRANKLIN SQUARE

NEW BRITAIN CT 06051

(860) 827-2951 REF: 1755.6690
INV: 962896

DEPT:



J131118012601uv


552.02782B/DCA5

TRK# 7721 2140 8090
0201

WED - 02 MAY 10:30A
PRIORITY OVERNIGHT

EB MPEA

ASR 06051
CT-US BDL



CT54XC108 845993

After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.