

KENNETH C. BALDWIN

280 Trumbull Street
Hartford, CT 06103-3597
Main (860) 275-8200
Fax (860) 275-8299
kbaldwin@rc.com
Direct (860) 275-8345

Also admitted in Massachusetts
and New York

June 18, 2021

Via Electronic Mail

Melanie A. Bachman, Esq.
Executive Director/Staff Attorney
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: **Notice of Exempt Modification – Facility Modification
112 Munn Road (a/k/a 112 Windham Avenue), Colchester, Connecticut**

Dear Attorney Bachman:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains an existing wireless telecommunications facility at the above-referenced property address (the “Property”). The facility consists of antennas and remote radio heads attached to a tower and related equipment on the ground, near the base of the tower. The Connecticut State Police (“CSP”) filed and “Exempt” filing with the Siting Council in 1985 for the original Tower. Cellco’s use of the tower was approved the Council in May of 1990 (Metro Mobile CTS of New London, Inc.). A copy of the State’s correspondence with the Council and Cellco’s approval are included in Attachment 1.

Cellco now intends to modify its facility by removing six (6) existing antennas and installing six (6) new JAHH-65B-R3B antennas on Cellco’s existing antenna mounting structure. Cellco will also remove six (6) remote radio heads (“RRHs”) and install six (6) new RRHs behind its antennas. A set of project plans showing Cellco’s proposed facility modifications and the new antennas and RRH specifications are included in Attachment 2.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Colchester’s Chief Elected Official and Land Use Officer.

Melanie A. Bachman, Esq.
June 18, 2021
Page 2

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Cellco's replacement antennas and RRHs will be installed on Cellco's existing antenna mounting structure.
2. The proposed modifications will not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The installation of Cellco's new antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. A cumulative General Power Density table for the modified facility is included in Attachment 3. Cellco's modified facility will not provide Cellco's 5G wireless service at this time.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. According to the attached Structural Analysis ("SA") and Mount Analysis ("MA"), the existing tower, tower foundation and antenna mounting device, with certain modifications, can support Cellco's proposed modifications. Copies of the SA and MA are included in Attachment 4.

A copy of the parcel map and Property owner information is included in Attachment 5. A Certificate of Mailing verifying that this filing was sent to municipal officials and the property owner is included in Attachment 6.

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Melanie A. Bachman, Esq.
June 18, 2021
Page 3

Sincerely,

A handwritten signature in black ink, appearing to read "Kenneth C. Baldwin". The signature is fluid and cursive, with a long horizontal stroke at the end.

Kenneth C. Baldwin

Enclosures

Copy to:

Mary Bylone, Colchester First Selectman
Matthew Bordeaux, Colchester Town Planner
State of Connecticut, Property Owner
Aleksey Tyurin

ATTACHMENT 1



STATE OF CONNECTICUT
DEPARTMENT OF ENVIRONMENTAL PROTECTION



May 17, 1985

Ms. Gloria Dibble Pond, Chairperson
Connecticut Siting Council
One Central Park Plaza
New Britain, CT 06051

RECEIVED

MAY 21 1985

**CONNECTICUT
SITING COUNCIL**

Dear Ms. Dibble Pond:

Enclosed are sixteen copies of a Notice of Intent to erect an exempt telecommunications tower for the multiple use of specific agencies of the State of Connecticut.


This tower is to be located at Windham Avenue in Colchester with an anticipated height of 320 feet above ground level (AGL), replacing an existing tower of 180 feet AGL.

Please bill the Department of Environmental Protection, Planning and Development Bureau, 165 Capitol Avenue, Room 248, Hartford, CT 06106, for the \$50. filing fee.

If you have any questions or require additional information, please contact Mr. Richard Couch, Director of Planning and Development, Division of Conservation and Preservation in the Department of Environmental Protection, at 566-5026.

Thank you.

Sincerely,


Stanley J. Pac
Commissioner


SJP:RD:bc

enc. (16)

Phone: (203) 566-5026

165 Capitol Avenue • Hartford, Connecticut 06106

An Equal Opportunity Employer



STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

1 CENTRAL PARK PLAZA • NEW BRITAIN, CONN. 06051

PHONE: 827-2604

May 22, 1985

Re: Section 16-50v-1 of the Regulations of State Agencies
no fee is required for a Notice of Intent.

per Christopher S. Wood



STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

136 Main Street, Suite 401
New Britain, Connecticut 06051
Phone: 827-7682

Gloria Dibble Pond
Chairperson

COMMISSIONERS

Energy/Telecommunications

Peter G. Boucher
Leslie Carothers

Hazardous Waste/Low-level
Radioactive Waste

Frederick G. Adams
Bernard R. Sullivan

COUNCIL MEMBERS

Harry E. Covey
Mortimer A. Gelston
Daniel P. Lynch, Jr.
Paulann H. Sheets
William H. Smith
Colin C. Tait

Joel M. Rinebold
Executive Director

Stanley J. Modzelesky
Executive Assistant

**FILE
COPY**

May 1, 1990

Mr. David S. Malko, P.E.
Manager, Engineering & Regulatory Services
METRO MOBILE
50 Rockland Road
South Norwalk, CT 06854

RE: Metro Mobile CTS of New London, Inc., Notice of Intent to Install Cellular Antennas and Related Equipment on a tower Owned by the State of Connecticut, Department of Public Safety in the Town of Colchester, Connecticut.

Dear Mr. Malko:

At a meeting on April 30, 1990, the Connecticut Siting Council acknowledged your notice of intent to install cellular antennas and related equipment on an existing tower facility owned by the State of Connecticut, Department of Public Safety, in Colchester, Connecticut, pursuant to Section 16-50j-73 of the Regulations of State Agencies (RSA).

The proposed modifications are to be implemented as specified in your notices dated April 16 and 30, 1990. As proposed, the modifications are in compliance with the exception criteria specified in RSA 16-50j-72 as changes to an existing facility site that do not increase the tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary 6 decibels, and add radio frequency sending or receiving capability which increases the total radio frequency electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to Section 22a-162 of the Connecticut General Statutes.

The Council is pleased to note that the shared use of an existing tower meets the Council's long-term goal and the public interest to avoid proliferation of additional tower structures.

Please notify the Council upon completion of construction.

Very truly yours,



A handwritten signature in cursive script that reads "Gloria Dibble Pond". The signature is written in dark ink and is positioned above the printed name.

Gloria Dibble Pond
Chairperson

GDP/JMR/bd

4380E

ATTACHMENT 2



- NOTES:
1. COMPOUND PLAN IS BASED EXISTING DRAWINGS PROVIDED ON FILE WITH THE CT SITING COUNCIL AND A LIMITED DESIGN VISIT ON 7-10-17 FOR THE PURPOSE OF DETERMINING CABLE LENGTHS. A COMPOUND SURVEY WAS NOT PERFORMED.
 2. PLANS ARE DIAGRAMMATIC ONLY AND NOT TO BE SCALED.
 3. ELEVATION HEIGHTS ARE BASED ON EXISTING DRAWINGS ON FILE WITH THE CT SITING COUNCIL.
 4. REFER TO STRUCTURAL TOWER ANALYSIS AND MOUNT ANALYSIS BY OTHERS, UNDER SEPARATE COVER.

1 **COMPOUND PLAN**
Scale: 1" = 20'-0"

TOP OF TOWER
EL. 320'-0"± A.G.L.

NOTE: CONTRACTOR TO VERIFY VERIZON WIRELESS ANTENNA RAD CENTER AND PROVIDE FINAL CONFIRMATION TO VERIZON AND ON AIR ENGINEERING, LLC

EXISTING VERIZON WIRELESS ANTENNAS
EL. 220'-0"± A.G.L.

EXISTING VERIZON WIRELESS ANTENNA SECTOR, REFER TO A-3 FOR PROPOSED MODIFICATIONS


EXISTING AT&T ANTENNAS
EL. 200'-0"± A.G.L.

EXISTING 320 FT. SELF-SUPPORT LATTICE TOWER

EXISTING VERIZON WIRELESS (2) HYBRID & COAXIAL CABLES ROUTED UP TOWER

GRADE

2 **ELEVATION**
Scale: NTS



20 ALEXANDER DRIVE
WALLINGFORD, CT 06492

On Air Engineering, LLC
88 Foundry Pond Road
Cold Spring, NY 10516
201-456-4624
onair@optonline.net

LICENSURE



DAVID WEINPAHL, P.E.
CT LIC NO. 22144

SUBMITTALS

NO	DATE	REVISION
0	07.28.17	REVIEW
1	12.27.18	REVISED FOR MOUNT ANALYSIS
2	08.13.19	REVISED PER CTSP COMMENTS
3	03.04.21	REVISED PER CLIENT COMMENTS
4	06.15.21	REVISED PER ATTORNEY COMMENTS

NO	DATE	DESCRIPTION
DRAWN BY:	MF	
CHECKED BY:	DW	

PROJECT NAME:
**850-LTE
CARRIER ADD
CABLE DRAWINGS**

SITE NAME:
COLCHESTER CT

SITE ADDRESS:
**CT STATE POLICE TOWER
112 WINDHAM AVE.
COLCHESTER, CT 06415**

SHEET TITLE:
**COMPOUND PLAN
& ELEVATION**

SHEET NUMBER:
A-1



NO	DATE	REVISION
0	07.28.17	REVIEW
1	12.27.18	REVISED FOR MOUNT ANALYSIS
2	08.13.19	REVISED PER CTSP COMMENTS
3	03.04.21	REVISED PER CLIENT COMMENTS
4	06.15.21	REVISED PER ATTORNEY COMMENTS

NO	DATE	DESCRIPTION

DRAWN BY:	MF
CHECKED BY:	DW


PROJECT NAME:
**850-LTE
CARRIER ADD
CABLE DRAWINGS**

SITE NAME:
COLCHESTER CT

SITE ADDRESS:
CT STATE POLICE TOWER
112 WINDHAM AVE.
COLCHESTER, CT 06415

SHEET TITLE:
**EQUIPMENT PLAN
& ANTENNA PLANS**


SHEET NUMBER:




NOTES:

- CONTRACTOR TO INSTALL NEW AND/OR MODIFY EXISTING SHELTER CABLE ENTRY PORTS FOR THE PROJECT AS REQUIRED INCLUDING THE REMOVAL OF ANY EXISTING COAXIAL CABLES AS DIRECTED BY VERIZON WIRELESS.
- EQUIPMENT PLAN IS BASED ON LIMITED MEASUREMENTS FOR THE PURPOSE OF LOCATING THE PROPOSED OVP INSIDE. A DETAILED EQUIPMENT ROOM SURVEY WAS NOT PERFORMED.



1 **EQUIPMENT PLAN - BLDG. AT GRADE**
Scale: 1/4" = 1'-0"



2 **ANTENNA PLAN @ 220 FT. - EXISTING**
Scale: N.T.S.



3 **ANTENNA PLAN @ 220 FT. - PROPOSED**
Scale: 3/32" = 1'-0"



SECTOR: ALPHA

POSITION	EXISTING ANTENNA	PROPOSED		
		ANTENNA	RRH	OVP
1	850-CDMA	EXISTING TO REMAIN	-	-
2	700 PLACEHOLDER	REMOVE EXIST. LEAVE MAST	AWS/PCS RRH SEE NOTE 1	-
3	EXIST. (2) SBNHH ON 'SBS' BKT.	NEW (2) JAHH SEE NOTE 3	-	SEE NOTE 2
4	SPARE MAST	SPARE MAST	700/850 RRH SEE NOTE 1	-

NOTES:
 1. NEW RRH TO REPLACE EXISTING; MOUNT TO BACKSIDE OF SPARE ANTENNA MASTS; REFER TO 3/A-2
 2. EXISTING 12-CKT. OVP ON TOWER NEAR BETA TO REMAIN; USE FOR ALL HYBRID CABLE CONNECTIONS
 3. NEW (2) JAHH ANTENNAS ON 'SBS' MOUNTING BRACKET LOCATED ON EXISTING POS. 3 PIPE MAST



20 ALEXANDER DRIVE
WALLINGFORD, CT 06492



88 Foundry Pond Road
Cold Spring, NY 10516
201-456-4624
onair@optonline.net

LICENSURE



DAVID WEINPAAL, P.E.
CT LIC NO. 22144

SUBMITTALS

NO	DATE	REVISION
0	07.28.17	REVIEW
1	12.27.18	REVISED FOR MOUNT ANALYSIS
2	08.13.19	REVISED PER CTSP COMMENTS
3	03.04.21	REVISED PER CLIENT COMMENTS
4	06.15.21	REVISED PER ATTORNEY COMMENTS

NO DATE DESCRIPTION

DRAWN BY: MF
CHECKED BY: DW

PROJECT NAME:
850-LTE
CARRIER ADD
CABLE DRAWINGS

SITE NAME:
COLCHESTER CT

SITE ADDRESS:
CT STATE POLICE TOWER
112 WINDHAM AVE.
COLCHESTER, CT 06415



SHEET TITLE:
ANTENNA SECTOR
CONFIGURATIONS

SHEET NUMBER:

A-3

1 ANTENNA SECTOR CONFIGURATIONS - ALPHA

Scale: N.T.S.





SECTOR: BETA

POSITION	EXISTING ANTENNA	PROPOSED		
		ANTENNA	RRH	OVP
1	850-CDMA	EXISTING TO REMAIN	-	-
2	700 PLACEHOLDER	REMOVE EXIST. LEAVE MAST	AWS/PCS RRH SEE NOTE 1	-
3	EXIST. (2) SBNHH ON 'SBS' BKT.	NEW (2) JAHH SEE NOTE 3	-	SEE NOTE 2
4	SPARE MAST	SPARE MAST	700/850 RRH SEE NOTE 1	-

NOTES:
 1. NEW RRH TO REPLACE EXISTING; MOUNT TO BACKSIDE OF SPARE ANTENNA MASTS; REFER TO 3/A-2
 2. EXISTING 12-CKT. OVP ON TOWER NEAR BETA TO REMAIN; USE FOR ALL HYBRID CABLE CONNECTIONS
 3. NEW (2) JAHH ANTENNAS ON 'SBS' MOUNTING BRACKET LOCATED ON EXISTING POS. 3 PIPE MAST

2 ANTENNA SECTOR CONFIGURATIONS - BETA

Scale: N.T.S.



SECTOR: GAMMA

POSITION	EXISTING ANTENNA	PROPOSED		
		ANTENNA	RRH	OVP
1	850-CDMA	EXISTING TO REMAIN	-	-
2	700 PLACEHOLDER	REMOVE EXIST. LEAVE MAST	AWS/PCS RRH SEE NOTE 1	-
3	EXIST. (2) SBNHH ON 'SBS' BKT.	NEW (2) JAHH SEE NOTE 3	-	SEE NOTE 2
4	SPARE MAST	SPARE MAST	700/850 RRH SEE NOTE 1	-

NOTES:
 1. NEW RRH TO REPLACE EXISTING; MOUNT TO BACKSIDE OF SPARE ANTENNA MASTS; REFER TO 3/A-2
 2. EXISTING 12-CKT. OVP ON TOWER NEAR BETA TO REMAIN; USE FOR ALL HYBRID CABLE CONNECTIONS
 3. NEW (2) JAHH ANTENNAS ON 'SBS' MOUNTING BRACKET LOCATED ON EXISTING POS. 3 PIPE MAST


3 ANTENNA SECTOR CONFIGURATIONS - GAMMA

Scale: N.T.S.

GENERAL NOTES:

1. CONTRACTOR SHALL REFER TO THE LATEST VERIZON WIRELESS RFDS WHICH MAY INCLUDE ANTENNA SECTOR AZIMUTHS/ANTENNA CHANGES, ETC. THAT ARE REQUIRED AS PART OF THE PROJECT.
2. CONTRACTOR SHALL SECURE ALL CONTROL CABLES IN ACCORDANCE WITH INDUSTRY STANDARDS AND MANUFACTURERS INSTRUCTIONS. EXTERIOR CABLES MAY BE TAPED OR TIE-WRAPPED TO EXISTING SUPPORTS EVERY 4 FT. MAX. FOR HORIZONTAL RUNS. CONTRACTOR MAY USE HOISTING GRIPS AT TOP OF VERTICAL CABLE RUNS WHEN REQUIRED.
3. ALL CABLES SHALL BE ROUTED AND SECURED ON STRUCTURAL MEMBERS ONLY - DO NOT "LOOP" THE CABLES IN MID-AIR BETWEEN ANTENNAS
4. REFER TO RFDS FOR DETAILED PLUMBING DIAGRAM SHOWING ALL JUMPER AND OTHER CABLING CONNECTIONS AT ANTENNAS, RRH'S, DIPLEXERS OR OTHER DEVICES.


NOTE: ALL ANTENNAS VIEWED FROM REAR



BILL OF MATERIALS			
DESCRIPTION	QTY	LENGTH	COMMENTS
LOWER OVP	-	-	EXIST. (2) RACK MOUNT TO REMAIN
UPPER OVP	-	-	EXIST. 12-CKT. ON TOWER TO REMAIN
6x12 HYBRID CABLE	-	-	EXIST. (2) TO REMAIN
1x1 HYBRID CABLE	-	-	EXIST. (6) TO REMAIN
RET CONTROL CABLE	-	-	EXIST. TO REMAIN OR BE REMOVED; SEE DIAGRAM
1/2" JUMPER CABLE	-	-	SEE NOTE 2
AWS/PCS DUAL BAND RRH	3	-	B2/B66A TO REPLACE EXIST. AWS RRH
700/850 DUAL BAND RRH	3	-	B5/B13 TO REPLACE EXIST. 700 RRH
700/850 DIPLEXER	3	-	CBC78T-DS-43-2X
AWS ANTENNA	3	-	NEW AWS TO REPLACE EXISTING - SHARE WITH 700 & 850-LTE
700 ANTENNA	3	-	NEW 700 TO REPLACE EXISTING - SHARE WITH 1900 & 850-LTE
1900 ANTENNA	-	-	SHARED WITH NEW JAHH ANTENNAS
850-CDMA ANTENNA	-	-	EXISTING TO REMAIN - 1 PER SECTOR
850-LTE ANTENNA	-	-	SHARED WITH NEW JAHH ANTENNAS
SBS BRACKET	3	-	COMMSCOPE BSAMNT-SBS-2-2


- NOTES:
1. ITEMS SHOWN ARE FOR MAJOR DESIGN ELEMENTS ONLY. REFER TO VERIZON WIRELESS RFDS FOR ALL MANUFACTURER PART NUMBERS AND ACCESSORY ITEMS REQUIRED FOR A COMPLETE INSTALLATION.
 2. CONTRACTOR SHALL DETERMINE AND PROVIDE ALL REQUIRED PRE-FAB JUMPER QUANTITIES AND LENGTHS, KEEPING ALL LENGTHS TO A MINIMUM.

EXISTING 6x12 HYBRID CABLE (TYP. OF 2)



- NOTES:
1. 'RET' CONTROL FOR ALL JAHH ANTENNAS IS OVER RF JUMPERS; REMOVE EXIST. 'RET' CABLES FROM SBNHH ANTENNAS & RRH'S.

20 ALEXANDER DRIVE
WALLINGFORD, CT 06492



DAVID WEINPAAL, P.E.
CT LIC NO. 22144

SUBMITTALS		
NO	DATE	REVISION
0	07.28.17	REVIEW
1	12.27.18	REVISED FOR MOUNT ANALYSIS
2	08.13.19	REVISED PER CTSP COMMENTS
3	03.04.21	REVISED PER CLIENT COMMENTS
4	06.15.21	REVISED PER ATTORNEY COMMENTS

NO	DATE	DESCRIPTION
DRAWN BY:		MF
CHECKED BY:		DW

PROJECT NAME:
850-LTE CARRIER ADD CABLE DRAWINGS


SITE NAME:
COLCHESTER CT

SITE ADDRESS:
CT STATE POLICE TOWER
112 WINDHAM AVE.
COLCHESTER, CT 06415

SHEET TITLE:
RF PLUMBING DIAGRAM & B.O.M.

SHEET NUMBER:

JAHH-65B-R3B



8-port sector antenna, 2x 698–787, 2x 824–894 and 4x 1695–2360 MHz, 65° HPBW, 3x RET and low bands have diplexers. Internal SBT's on first LB(Port 1) and first HB(Port 5).

- Internal SBT on low and high band allow remote RET control from the radio over the RF jumper cable
- One RET for 700MHz, one RET for 850MHz, and one RET for both high bands to ensure same tilt level for 4x Rx or 4x MIMO
- Internal filter on low band and interleaved dipole technology providing for attractive, low wind load mechanical package
- Separate RS-485 RET input/output for low and high band

General Specifications

Antenna Type	Sector
Band	Multiband
Color	Light gray
Effective Projective Area (EPA), frontal	0.28 m ² 3.014 ft ²
Effective Projective Area (EPA), lateral	0.24 m ² 2.583 ft ²
Grounding Type	RF connector body grounded to reflector and mounting bracket
Performance Note	Outdoor usage Wind loading figures are validated by wind tunnel measurements described in white paper WP-112534-EN
Radome Material	Fiberglass, UV resistant
Radiator Material	Aluminum Low loss circuit board
Reflector Material	Aluminum
RF Connector Interface	4.3-10 Female
RF Connector Location	Bottom
RF Connector Quantity, high band	4
RF Connector Quantity, low band	4
RF Connector Quantity, total	8

Remote Electrical Tilt (RET) Information, General

RET Interface	8-pin DIN Female 8-pin DIN Male
RET Interface, quantity	2 female 2 male

Dimensions

Width	350 mm 13.78 in
--------------	-------------------


JAHH-65B-R3B

Length 1828 mm | 71.969 in

Depth 208 mm | 8.189 in

Array Layout

JAHH-65A-R3B JAHH-65B-R3B JAHH-65C-R3B



Array	Freq (MHz)	Conns	RET (SRET)	AISG RET UID
R1	698-798	1-2	1	ANXXXXXXXXXXXXXXXXX1
R2	824-894	3-4	2	ANXXXXXXXXXXXXXXXXX2
Y1	1695-2360	5-6	3	ANXXXXXXXXXXXXXXXXX3
Y2	1695-2360	7-8		

View from the front of the antenna

(Sizes of colored boxes are not true depictions of array sizes)

Electrical Specifications

Impedance 50 ohm

Operating Frequency Band 1695 – 2360 MHz | 698 – 787 MHz | 824 – 894 MHz

Polarization ±45°

Remote Electrical Tilt (RET) Information, Electrical

Protocol 3GPP/AISG 2.0 (Single RET)

Power Consumption, idle state, maximum 2 W

JAHH-65B-R3B

Power Consumption, normal conditions, maximum	13 W
Input Voltage	10–30 Vdc
Internal Bias Tee	Port 1 Port 5
Internal RET	High band (1) Low band (2)

Electrical Specifications

Frequency Band, MHz	698–787	824–894	1695–1880	1850–1990	1920–2200	2300–2360
Gain, dBi	14.5	15.8	18	18.4	18.5	18.8
Beamwidth, Horizontal, degrees	67	65	63	63	65	68
Beamwidth, Vertical, degrees	12.4	10.5	5.7	5.2	4.9	4.4
Beam Tilt, degrees	2–14	2–14	0–10	0–10	0–10	0–10
USLS (First Lobe), dB	18	18	20	20	21	23
Front-to-Back Ratio at 180°, dB	32	34	31	35	36	38
Isolation, Cross Polarization, dB	25	25	25	25	25	25
Isolation, Inter-band, dB	30	30	30	30	30	30
VSWR Return loss, dB	1.5 14.0	1.5 14.0	1.5 14.0	1.5 14.0	1.5 14.0	1.5 14.0
PIM, 3rd Order, 2 x 20 W, dBc	-153	-153	-153	-153	-153	-153
Input Power per Port at 50° C, maximum, watts	200	200	300	300	300	250

Electrical Specifications, BASTA

Frequency Band, MHz	698–787	824–894	1695–1880	1850–1990	1920–2200	2300–2360
Gain by all Beam Tilts, average, dBi	14.3	14.9	17.6	18.1	18.2	18.5
Gain by all Beam Tilts Tolerance, dB	±0.3	±0.5	±0.6	±0.4	±0.5	±0.6
Gain by Beam Tilt, average, dBi	2° 14.3 8° 14.3 14° 14.3	2° 15.0 8° 14.9 14° 15.4	0° 17.2 5° 17.6 10° 17.6	0° 17.6 5° 18.2 10° 18.2	0° 17.7 5° 18.3 10° 18.3	0° 17.9 5° 18.7 10° 18.7
Beamwidth, Horizontal Tolerance, degrees	±1.2	±1.4	±4	±2.4	±2.9	±2.7
Beamwidth, Vertical Tolerance, degrees	±0.9	±0.5	±0.3	±0.2	±0.3	±0.1
USLS, beampeak to 20° above beampeak, dB	18	17	17	18	19	18
Front-to-Back Total Power at 180° ± 30°, dB	25	24	26	29	27	29
CPR at Boresight, dB	22	23	20	21	21	24

JAHH-65B-R3B

CPR at Sector, dB	11	12	11	11	11	8
-------------------	----	----	----	----	----	---

Mechanical Specifications

Wind Loading at Velocity, frontal	301.0 N @ 150 km/h 67.7 lbf @ 150 km/h
Wind Loading at Velocity, lateral	254.0 N @ 150 km/h 57.1 lbf @ 150 km/h
Wind Loading at Velocity, maximum	143.4 lbf @ 150 km/h 638.0 N @ 150 km/h
Wind Speed, maximum	241 km/h 149.75 mph

Packaging and Weights

Width, packed	456 mm 17.953 in
Depth, packed	357 mm 14.055 in
Length, packed	1975 mm 77.756 in
Net Weight, without mounting kit	29.2 kg 64.375 lb
Weight, gross	42.5 kg 93.696 lb

Regulatory Compliance/Certifications

Agency	Classification
CHINA-ROHS	Above maximum concentration value
ISO 9001:2015	Designed, manufactured and/or distributed under this quality management system
ROHS	Compliant/Exempted



Included Products

BSAMNT-3 — Wide Profile Antenna Downtilt Mounting Kit for 2.4 - 4.5 in (60 - 115 mm) OD round members. Kit contains one scissor top bracket set and one bottom bracket set.

* Footnotes

Performance Note Severe environmental conditions may degrade optimum performance

SAMSUNG

Dual-Band Radio Unit AWS/PCS (B66/B2)

RFV01U-D1A

Samsung's RFV01U-D1A is a compact remote Radio Unit (RU) designed for deployments that require flexibility in installation and rapid onlining, without compromising on coverage, capacity or operational expenses.



The RFV01U-D1A RU targets dual-band support across Band 66 (AWS) and Band 2 (PCS), making it an ideal product for broad coverage footprints across multiple common mid-range frequencies.

The RU handles all Radio Frequency (RF) processing in a single, compact unit, and is designed to interface via CPRI with Samsung's CDU baseband offerings, in both distributed- and central-RAN configurations.

In addition to its minimal footprint and ease of installation, the RU is also designed to reduce cost of ownership through its integrated spectrum analyzer, which allows for remote RF monitoring, greatly reducing the need for on-site maintenance visits.

Features and Benefits

- Dual-band support for broad frequency coverage
- Minimal footprint reduces site costs
- Rapid, easy installation
- Flexibly deployable in any location
- Remote RF monitoring capability
- Convection cooled, silent operation
- Built-in Broadcast Auxiliary Services (BAS) filter ensures compliant AWS operation without impacting footprint

Key Technical Specifications

Duplex Type: FDD

Operating Frequencies:

B66: DL(2,110-2,180MHz)/UL(1,710-1,780MHz)

B2: DL(1,930-1,990MHz)/UL(1,850-1,910MHz)

Instantaneous Bandwidth:

70MHz(B66) + 60MHz(B2)

RF Chain: 4T4R/2T4R/2T2R

Output Power: Total 320W

DU-RU Interface: CPRI (10Gbps)

Dimensions: 380 x 380 x 255mm (36.8L)

Weight: 38.3kg

Input Power: -48V DC

Operating Temp.: -40 - 55°(w/o solar load)

Cooling: Natural convection

SAMSUNG

Dual-Band Radio Unit 700/850MHz (B13/B5) RFV01U-D2A

Samsung's RFV01U-D2A is a compact remote Radio Unit (RU) designed for deployments that require flexibility in installation and rapid onlining, without compromising on coverage, capacity or operational expenses.



The RFV01U-D2A RU targets dual-band support across Band 13 (700MHz) and Band 5 (850MHz), making it an ideal product for broad coverage footprints across multiple common low-end, long-range frequencies.

The RU handles all Radio Frequency (RF) processing in a single, compact unit, and is designed to interface via CPRI with Samsung's CDU baseband offerings, in both distributed- and central-RAN configurations.

In addition to its minimal footprint and ease of installation, the RU is also designed to reduce cost of ownership through its integrated spectrum analyzer, which allows for remote RF monitoring, greatly reducing the need for on-site maintenance visits.

Features and Benefits

- Dual-band support for broad frequency coverage
- Minimal footprint reduces site costs
- Rapid, easy installation
- Flexibly deployable in any location
- Remote RF monitoring capability
- Convection cooled, silent operation

Key Technical Specifications

Duplex Type: FDD
Operating Frequencies:
B13: DL(746-756MHz)/UL(777-787MHz)
B5: DL(869-894MHz)/UL(824-849MHz)
Instantaneous Bandwidth: 10MHz(B13) + 25MHz(B5)
RF Chain: 4T4R/2T4R/2T2R
Output Power: Total 320W
DU-RU Interface: CPRI (10Gbps)
Dimensions: 380 x 380 x 207mm (29.9L)
Weight: 31.9kg
Input Power: -48V DC
Operating Temp.: -40 - 55°(w/o solar load)
Cooling: Natural convection

ATTACHMENT 3

	General	Power	Density					
Site Name: Colchester								
Tower Height: Verizon @ 220ft								
CARRIER	# OF CHAN.	WATTS ERP	HEIGHT	CALC. POWER DENS	FREQ.	MAX. PERMISS. EXP.	FRACTION MPE	Total
*Antenna no. 2 (CSP/FBI)	1	330	320	154.665	0.0002	0.2000	0.01%	
*Antenna no. 3 (CSP)	1	1015	315	2141	0.0000	1.0000	0.00%	
*Antenna no. 4 (SHP)	1	398	294	151.355	0.0002	0.2000	0.01%	
*Antenna no. 5 (DEP)	1	175	292	44.72	0.0001	0.2000	0.01%	
*Antenna no. 6	1	100	257	153.935	0.0001	0.2000	0.00%	
*Antenna no. 7 (OEM)	1	178	243	45.2	0.0002	0.2000	0.01%	
*Antenna no. 8 (CSP)	1	330	227	42.04	0.0003	0.2000	0.02%	
*Antenna no. 9 (DEP)	1	125	138	75.5	0.0004	0.2000	0.02%	
*Antenna no. 10 (CSP)	1	569	97	2138	0.0000	1.0000	0.00%	
*Antenna no. 11 (CSP)	1	252	90	2133.2	0.0000	1.0000	0.00%	
*Antenna no. 12 (CSP)	1	5750	105	6795	0.0005	1.0000	0.00%	
*Antenna no. 13 (CSP)	1	1545	112	10567.5	0.0000	1.0000	0.00%	
*Antenna no. 14	5	200	320	867.4	0.0005	0.5783	0.01%	
*Antenna no. 15	5	200	320	867.5	0.0005	0.5783	0.01%	
*Antenna no. 18 (FBI)	1	473	100	453.625	0.0023	0.3024	0.08%	
*Antenna no. 31 (CTT)	1	10	100	406	0.0001	0.2707	0.00%	
*Eversource	4	124	145	217	0.0092	0.2000	0.46%	
*AT&T	2	414	200	850	0.0079	0.5667	0.14%	
*AT&T	2	656	200	1900	0.0125	1.0000	0.13%	
*AT&T	2	826	200	700	0.0158	0.4667	0.34%	
*AT&T	4	1250	200	1900	0.0478	1.0000	0.48%	
VZW 700	4	634	220	0.0046	751	0.5007	0.38%	
VZW CDMA	2	300	220	0.0019	878.49	0.5857	0.08%	
VZW Cellular	4	725	220	0.0053	874	0.5827	0.37%	
VZW PCS	4	1525	220	0.0096	1975	1.0000	0.45%	
VZW AWS	4	1493	220	0.0099	2120	1.0000	0.44%	
								3.44%
* Source: Siting Council								

ATTACHMENT 4



Submitted to
Eversource Energy
107 Selden Street
Berlin, CT 06037

Submitted by
AECOM
500 Enterprise Drive,
Suite 3B
Rocky Hill, CT 06067
May 21, 2020

Empire Telecom USA, LLC
16 Esquire Road
Billerica, MA 01862

Verizon Wireless
20 Alexander Drive
Wallingford, CT 06492

DETAILED STRUCTURAL ANALYSIS AND MODIFICATION OF AN EXISTING 320' SELF SUPPORTING LATTICE TOWER AND FOUNDATION FOR PROPOSED ANTENNA ARRANGEMENT



EVERSOURCE
ENERGY



verizon



Site Name : Connecticut State Police Tower # 50
AT&T Site Number : CT2284
Site Address: 112 Munn Road
Colchester, Connecticut

60626930 Revision 1
EVS-010 / VZ5-217 / EMP-008

TABLE OF CONTENTS

- 1. EXECUTIVE SUMMARY**
- 2. INTRODUCTION**
- 3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS**
- 4. FINDINGS AND EVALUATION**
- 5. CONCLUSIONS AND RECOMMENDATIONS**
- 6. DRAWINGS AND DATA**
 - REINFORCEMENT DRAWINGS SK-1 AND SK-2**
 - TNX TOWER INPUT / OUTPUT SUMMARY**
 - TNX TOWER FEEDLINE DISTRIBUTION CHART**
 - TNX TOWER FEEDLINE PLAN**
 - TNX TOWER DEFLECTION, TILT, AND TWIST**
 - TNX TOWER DETAILED OUTPUT**
 - ANCHOR BOLT ANALYSIS**
 - FOUNDATION ANALYSIS**
 - ANALYSIS UNDER TIA-222-F DESIGN CRITERIA (DESPP / CSP)**

1. EXECUTIVE SUMMARY

This report summarizes the structural analysis and modification of the 320' Self-supporting lattice tower located at 112 Munn Road in Colchester, Connecticut.

The structural analysis was conducted in accordance with the 2018 Connecticut State Building Code which include the TIA-222-H¹ Standard, 2018 International Building Code, the 2018 Connecticut State Building Code Amendments, the AISC² Load Resistance Factor Design (LRFD), the ASCE 7³ design Code, and the Connecticut State Police Requirements which include the TIA/EIA-222-F⁴.

The antenna loading considered in the analysis consists of all the existing antennas, transmission lines and ancillary items as outlined in the Introduction Section of this report.

The proposed Eversource, AT&T & Verizon Wireless (VZW) antenna upgrades are listed below:

Proposed Antennas	Carrier	Antenna Center Elevation
<u>Remove:</u>		
(6) SBNHH-1D65B Panel Antennas (3) Nokia 2x60-700 MHz RRH Units (3) Nokia 2x90-AWS RRH Units	VZW (Existing)	@ 220'
<u>Install:</u>		
(6) Commscope JAHH-65B-R3B Panels (2 per Sector) (3) Commscope BSAMNT-SBS-2-2 Panel Mounts for JAHH Panels (3) Samsung B2/B66A RRH-BR049 (RFV01U-D1A) RRH Units (3) Samsung B5/B13 RRH-BR04C (RFV01UD2A) RRH Units (3) Commscope CBC78T-DS-43-2X Diplexer Units	VZW (Proposed)	@ 220'
(2) CCI HPA-65R-BUU-H8 Panel Antennas (1 Alpha Sector, 1 Beta Sector) (1) CCI HPA-65R-BUU-H6 Panel Antenna (1 Gamma Sector) (3) Ericsson RRUS-11 RRH Units (3) Ericsson RRUS-32 B2 RRH Units (1) Raycap DC6 Surge Arrestor Unit (3) SitePro1 Sector Frame Stiff Arm Kit (Part # STK-U) attaching to Existing Mount Assembly	AT&T (Proposed)	@ 200'
(1) Telewave ANT220F2 Omni Antenna (Centerline Elevation @ 163') (1) SitePro1 Mount (Part # USF-4U – Mounted at Centerline Elevation 160') (1) RFS 7/8" Coaxial Cable (Proposed Feedline Length = 191')	Eversource (Proposed)	160' – 163'
(1) Telewave ANT220F2 Omni Antenna (Centerline Elevation @ 145') (1) SitePro1 Mount (Part # USF-4U – Mounted at Centerline Elevation 142') (1) RFS 7/8" Coaxial Cable (Proposed Feedline Length = 173')	Eversource (Proposed)	142' – 145'

1. TIA = Telecommunications Industry Association Structural Standard for Antenna Supporting Structures and Antennas (Version H); expected to be accepted State Standard prior to end of 2020.

2. AISC = American Institute of Steel Construction (15th Edition)

3. ASCE 7 = American Society of Civil Engineers - Standard 7 (2016 Edition)

4. TIA/EIA = Telecommunications Industry Association Structural Standard for Antenna Supporting Structures and Antennas (Version F)

1. EXECUTIVE SUMMARY *(continued)*:

The results of an initial structural analysis indicated that the existing tower did not have enough capacity for the proposed loading conditions above. The tower structure requires modifications shown on SK-1 and SK-2. **Once the modifications indicated on sheets SK-1 and SK-2 are performed, the modified structure, existing anchor bolts and previously modified foundation are considered structurally adequate with the existing and proposed antenna loading herein.**

Per the Department of Energy Services and Public Protection (DESPP) / Connecticut State Police (CSP) directive, required twist and sway for this location is permitted to be measured from service dishes. The maximum sway (deflection) after tower modification is 0.3642 degrees and the maximum twist (rotation) after tower modification is 0.2278 degrees. These combined figures, measured from CSP service dishes, are within the Connecticut State Police requirement of 0.75 degrees for combined twist (rotation) and sway (deflection) with the load classification specified herein.

The maximum structural capacity calculated, after the tower structure has been modified, is **95.5 %**

This analysis is based on:

- 1) The tower structure's theoretical capacity not including any assessment of the condition of the tower.
- 2) Tower geometry, structural member sizes, and antenna mount assembly taken from original construction drawings (Rohn File #: 43233AE) prepared by Rohn Industries, Inc., approved May 10, 2001.
- 3) Previous structural analysis and reinforcement by URS Corporation for Verizon Wireless, project number VZ5-122 / 36922280, signed and sealed July 13, 2012 with updated modification sketches signed and sealed December 18, 2013. (Note: Only foundation components have been constructed from this report).
- 5) Previous structural analysis and tower modification performed by AECOM on behalf of AT&T, project number 60529362 / SAI-095, signed and sealed on February 6, 2017 (Note: analysis herein has considered modifications as stated within this analysis to have been constructed/installed).
- 6) Proposed antenna inventory update to AT&T antennas via Radio Frequency Data Sheet (RFDS), Dated May 12, 2017, along with associated construction drawings date October 19, 2017, obtained via e-mail dated March 20, 2018, with a follow-up inventory change obtained via e-mail dated August 21, 2019.
- 7) Proposed antenna inventory update to Verizon Wireless (VZW) antenna via RFDS, dated December 8, 2018, obtained via e-mail dated December 20, 2018.
- 8) Tower climb and antenna inventory performed by Eastern Communications Incorporated (dated November 27, 2019), on behalf of the Connecticut State Police, obtained via e-mail dated December 19, 2019.
- 9) Proposed antenna inventory for Eversource, obtained via e-mail dated February 7, 2020.
- 10) Previous structural analysis and evaluation performed by AECOM on behalf of Eversource, project number 60626930 / EVS-010, signed and sealed on May 14, 2020.
- 11) Antenna inventory as specified in Sections 2 and 6 of this report

1. **EXECUTIVE SUMMARY** *(continued)*:

This report is only valid as per the assumptions and data utilized in this report for antenna inventory, mounts and associated cables. The user of this report shall field verify the antenna, cabling and mount configuration used, as well as the physical condition of the tower members, connections and foundations. Notify the engineer in writing immediately if any of the information in this report is found to be other than specified.

If you should have any questions, please contact Michael Egan at (860) 263-5817.

Sincerely,

AECOM,


Richard A. Sambor, P.E.
Senior Structural Engineer



RAS/mcd

cc: DJR – AECOM
CF/Book

2. INTRODUCTION

The subject tower is located at 112 Munn Road in Colchester, Connecticut. The structure is a 320' self-supporting lattice tower structure designed by Rohn Industries, Inc.

The tower geometry and structure member sizes were taken from the original construction drawings (Rohn File #: 43233AE) prepared by Rohn Industries, Inc., approved May 10, 2001.

The structural analysis was conducted in accordance with the following:

- 2018 International Building Code (compliant with the TIA-222-H design loads)
- 2015 International Building Code with 2018 Connecticut State Building Code amendments for a (Ultimate) wind speed of 140 mph (3-second gust)
- 2016 AISC Load Resistance Factor Design (LRFD)
- 2016 ASCE7 Minimum Design Loads for Buildings and Other Structures for the ice thickness referenced in the TIA-222-H Standard.
- Connecticut State Police Requirements for a wind velocity under 90 MPH (fastest mile) and 90 mph (fastest mile) concurrent with 0.5 ice, analyzed under the TIA/EIA-222-F design Standard

The inventory together with the proposed Eversource, AT&T & VZW antenna arrangement is summarized in the table below:

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) Lightning Rod	Tower (existing)	Leg Mount	329'	N/A
(1) Lighted Beacon	Tower (existing)	Tower Mount	325'	(1) 1/2" coax cable
(1) PD-128 Omni/Dipole Antenna	ECI-1 CSP-2 (existing)	6' Side Arm Mount	325'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) BA-1012 Omni Antenna	ECI-2 CSP-1 (existing)	6' Side Arm Mount	320'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) ANT450F6 Antenna	ECI-3 (existing)	Pipe Mounted to tower Leg	318'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) SC479-HF1LDF Omni Antenna	ECI-4 CSP-52 (existing)	6' Side Arm Mount	300'	(1) 1-5/8" coax cable (AVA7-50A)
(1) PD-340 Dipole Antenna	ECI-5 CSP-4 (existing)	6' Side Arm Mount	290'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) DB-809T3 Omni Antenna	ECI-6 CSP-14 (existing)	<i>Shared with ECI-7 Mount</i>	286'	(1) 1-5/8" coax cable (AVA7-50A)
(1) (inverted) SC479-HF1LDF (D00I-E6085) Omni Antenna	ECI-7 CSP-53 (existing)	6' Side Arm Mount @ 284'	283'	(1) 1-5/8" coax cable (AVA7-50A)
(1) PD-440 Dipole Antenna	ECI-8 DEHMS-6 (existing)	6' Side Arm Mount @ 260'	264'	(1) 7/8" coax cable (LCF78-50JA-A7)

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) SC479-HF1LDF Omni Antenna	ECI-10 DEP-5 (existing)	<i>Shared with below T-Frame Mount</i>	251'	(1) 1-5/8" coax cable (AVA7-50A)
(1) PD-1142 Omni Antenna	ECI-14 DEHMS-7 (existing)	6' Side Arm Mount	248'	(1) 7/8" coax cable (LCF78-50JA-A7)
(2) (inverted) SC479-HF1LDF Omni Antennas (1) TMA Unit @ 247' (EL.)	ECI-11,12,13 CSP-16,17 (existing)	(1)T-Arm Frame Mount @ 246'	245'	(2) 1-5/8" coax cable (AVA7-50A) (1) 1/2" coax cable
(1) 531-70 Dipole Antenna	ECI-15 CSP-8 (existing)	6' Side Arm Mount	238'	(1) 7/8" coax cable (LCF78-50JA-A7)
(6) JAHH-65B-R3B Panel Antennas (2 per Sector) (3) B2/B66A RRH-BR049 (RFV01U-D1A) RRH Unit (3) B5/B13 RRH-BR04C (RFV01U-D2A) RRH Unit (3) CBC78T-DS-43-2X Diplexer Units	VZW (Proposed)	(3) BSAMNT-SBS-2-2 Panel Mounts for JAHH Antennas Shared with Below Mount	220'	<i>See Below Cables</i>
(3) LNX-6512DS-VTM (2) OVP-RC3DC-3315-PF-48 OVP Units	VZW (existing)	(3) T-Arms (existing)	220'	(6) 1 5/8" coax cables (existing) (2) HB158-1-08U8-S8J18 Fiber Optic Cable
(2) CCI HPA-65R-BUU-H8 (1A, 1B) (1) CCI HPA-65R-BUU-H6 (1C) (3) RRUS-11 RRH Units (3) RRUS-32 B2 RRH Units (1) DC6-48-60-0-8C Surge Arrestor	AT&T (Proposed)	(3) SitePro1 STK-U Mount Stiff-Arm Kits added to Existing Mounts (indicated below)	200'	<i>See Below Cables</i>
(3) Powerwave 7770 Panel Antennas	AT&T (existing)	(3) T-Arm mounts with (1) Stiff-Arm connected to Tower Structure	200'	(6) 1 5/8" coax cables (1) Fiber Optic Cable & (2) DC Cables within 2" Flex Conduit
(1) 1151-3N Omni Antenna	ECI-50 NEU-32 (existing)	4' Side Arm Mount	179'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) DB586-Y Omni Antenna	ECI-51 NEU-48 (existing)	<i>Shared with Below Mount</i>	177'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) TTA Unit	ECI-52 NEU-49 (existing)	<i>Shared with Below Mount</i>	176'	(1) 1/2" coax cable (LDF4-50A)

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) (inverted) DB586-Y Omni Antenna	ECI-53 NEU-50 (existing)	6' Side Arm Mount @ 176'	175'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) Small Lighted Tower Beacon Light	ECI-54 Tower (existing)	Mounted to Leg	168'	(1) 3/8" coax cable
(1) Small Lighted Tower Beacon Light	ECI-55 Tower (existing)	Mounted to Leg	165'	(1) 3/8" coax cable
(1) Small Lighted Tower Beacon Light	ECI-56 Tower (existing)	Mounted to Leg	164'	(1) 3/8" coax cable
(1) Telewave ANT220F2 Omni Antenna	Eversource (Proposed)	(1) SitePro1 USF-4U Mount @ Elevation 160'	163'	(1) LCF78-50JA-A7
(1) ANT450F6 Antenna	ECI-57 CSP (existing)	Pipe Mounted to Leg	154'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) 6' Dish with Radome (PAR6-59W-PXA)	ECI-58 CSP (existing)	Pipe Mounted to Leg	154'	(1) EW63 elliptical cable
(1) Telewave ANT220F2 Omni Antenna	Eversource (Proposed)	(1) SitePro1 USF-4U Mount @ Elevation 160'	163'	(1) LCF78-50JA-A7
(1) PD-156S Yagi Antenna	ECI-60 "DEAD" Carrier (existing)	Shared with ECI-59 Mount	139'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) DB-212 Dipole Antenna	ECI-59 NEU-33 (existing)	4' Side Arm Mount	139'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) 3' Ice Shield (for ECI-61 Dish)	ECI-61 CSP (existing)	Pipe Mounted to Leg	117'	N/A

<i>Antenna Type</i>	<i>Carrier</i>	<i>Mount</i>	<i>Antenna Centerline Elevation</i>	<i>Cable</i>
(1) Ice Shield (for ECI-63 Dish)	ECI-63 CSP (existing)	Pipe Mounted to Leg	115'	N/A
(1) 3' Dish with Radome	ECI-61 CSP-13 (existing)	Pipe Mount to Leg	112'	(1) EW90 coax cable
(1) 8' "Drum" Dish Antenna w/ Shroud	ECI-63 CSP (existing)	Pipe mounted to Leg	107'	(1) EW63 Elliptical Cable
(1) PD-458 Omni Antenna	ECI-62 CTT-18 (existing)	4' Side Arm Mount	106'	(1) 7/8" coax cable (LCF78-50JA-A7)
(1) PD-688 Yagi Antenna	ECI-66 FBI-31 (existing)	Pipe Mount to Leg	94'	(1) 7/8" coax cable (LCF78-50JA-A7)

Notes: Antenna ID numbering (ECI-#) obtained from Tower Existing Inventory via tower climb, performed by Eastern Communications, Inc. dated November 27, 2019. CSP numbering and elevations provided by CSP inventory obtained via e-mail dated December 19, 2019.

This structural analysis of the communications tower was performed by AECOM, on behalf of AT&T, Eversource and Verizon Wireless (VZW). The purpose of this analysis was to investigate the structural integrity of the modified tower and the previously modified foundation for existing and proposed antenna loads in compliance with the 2018 Connecticut State Building Code and the forthcoming TIA-222-H Standard. This analysis was conducted to evaluate stress on the tower and the effect forces to the foundation of the tower resulting from existing and proposed antenna arrangements.

3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS

The structural analysis was done in accordance with, the TIA-222-H–Structural Standard for Antenna Towers and Antenna Supporting Structures and Antennas, the 2015 International Building Code with 2018 Connecticut State Building Code Amendments, the 2018 International Building Code (in compliance with the TIA-222-H Standard) and the American Institute of Steel Construction (AISC) Manual of Steel Construction – Load Resistance Factor Design (LRFD).

The structural analysis was conducted using TNX Tower version 8.0.5.0 and used the following conditions for this tower review (following the TIA-222-H Standard):

- Structure Class 3 – (Essential Communications)
 - NOTE: ASCE 7 and CT State Building Code Applied Risk Category 4 for design wind loads (see below)
- Topographic Category 3 – (Tower location on top of hill – rolling wind conditions considered)
 - Crest Height used for analysis: (approximate elevations listed below)
 - Tower Base Elevation = 590 feet
 - High point (2 mile Radius) = 637 feet (Ref. Peak of hill near Amston Lake)
 - Low Point (2 mile Radius) = 410 feet (Ref. Bench mark Elevation near local Cemetery)
 - “H” = (Avg of High/Low) – Base Elevation = $(637+410)/2 - 590 = \underline{66.5}$ feet
- Exposure Class C – (Open Terrain with scattered obstructions)
- Load Conditions:
 - Two load conditions were evaluated as shown which were compared to design stresses according to AISC and TIA-222-H Standard.

Basic Wind Speed:

- IBC 2018 w/ 2018 CT State Building Code Amendment:
 - (2018) IBC Section 1609.1.1 – Determination of Wind Loads – Exception 5 “Designs using TIA-222” applies for determination of Design Wind Load obtained as “V.ult” are to be converted to “V.asd” when applying the TIA-222-H design Standard (under Section 1609.3) for Basic Wind Speed.
 - (2018) CT State Building Code Amendment to the IBC Section 1609.3 wind loads are obtained from Appendix N of the State Building Code.
 - **V.ult = 140 mph** (3-Second Gust) Wind Design Parameter for the Town of Colchester, Connecticut for Risk Category four (IV) for essential communications (Connecticut State Police). NOTE: Because the State of Connecticut has not officially published the design wind-speeds, use of the State of Connecticut wind-speeds per municipality (indicated above).

LOAD CONDITION 1 = 140 MPH (3-SECOND GUST) WIND LOAD (WITHOUT ICE) + TOWER DEAD LOAD

Load Condition 2 = 50 mph (3-second gust) Wind Load (with ice) + Ice Load + Tower Dead Load

Ice thickness used for this analysis is **1.00 inch** (assumed to start at the base of the tower) and is considered to increase in thickness with height. The initial ice thickness for design is referenced in the Annex of TIA-222-H and follows the same design criteria as the ASCE 7 (2016) Standard.

The load condition below implements the design requirements of the Department of Energy Services and Public Protection (DESPP) / Connecticut State Police (CSP) for the tower structures deflection limits with the allowable limit of the combination of the tower’s sway (deflection) and twist (rotation) under the TIA/EIA-222-F design Standard. This design limit required the combined value of sway (deflection) and twist (rotation) to be under 0.75 degrees following the TIA/EIA-222-F design Standard.

3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS (cont.)

Load Condition 3 = 90 mph (fastest mile) Wind Load (with Ice) + Ice Load + Dead Load

Seismic event consideration factors/values for design:

- $S_s = 0.174$ (2018 CT State Building Code – Location Specific Value)
- $S_1 = 0.061$ (2018 CT State Building Code – Location Specific Value)
- Site Classification = “D”
- Seismic Design Category = “B” – (2018 International Building Code)
- $F_a = 1.6$ (Obtained from TIA-222-H Table 2-11 Considering above conditions)
- $F_v = 2.4$ (Obtained from TIA-222-H Table 2-12 Considering above conditions)

NOTE: TIA-222-H Section 9.8 require S_s values to be greater than 1.0 to be applied for analysis. Due to the S_s value below this threshold, the seismic base shear calculation is omitted from this structural analysis report.

Strength Limit State Load Combinations (TIA-222-H Section 2.3.2):

The structural analysis herein has considered the following load combinations within the analysis:

1. **1.2 Dead Load Tower structure + 1.0 Dead Load Guy Assemblies + 1.6 Wind load without ice**
2. 1.2 Dead Load Tower structure + 1.0 Dead Load Guy Assemblies + 1.0 Dead weight of ice due to factored ice thickness + 1.0 Concurrent wind load with factored ice thickness + 1.0 Load effects due to temperature
3. 1.2 Dead Load Tower structure + 1.0 Dead Load Guy Assemblies + 1.0 Earthquake Load

NOTE 1: The above **bolded** load combination is considered to create the governing design loads per the results of the analysis.

NOTE 2: The above “Dead Load Guy Assemblies” are not considered as part of the analysis and are considered as a value of zero.

NOTE 3: The “Load effects due to temperature” do not apply for structures that are self-sustaining (from the TIA-222-H Standard)

4. FINDINGS AND EVALUATION

Combined axial and bending stresses on the existing tower structure were evaluated to compare with strength design in accordance with AISC (LRFD). The results of an initial analysis indicated the existing tower did not have enough capacity to support the proposed loading conditions. The tower structure requires modifications shown on SK-1 and SK-2. Once the modifications indicated on sheets SK-1 and SK-2 are performed, the modified structure along with the existing foundation and anchor bolts are considered structurally adequate with the wind load classification specified with the existing and proposed antenna loading noted herein.

The combined values for the tower sway (deflection) and the tower twist (rotation) are permitted for the site and this loading conditions, as requested by the Department of Energy Services and Public Protection (DESPP) / Connecticut State Police (CSP). The tower deflection (sway) is 0.3642 degrees and the tower rotation (twist) 0.2278 degrees with a wind velocity of 90 mph with 0.5" ice measured from DESPP / CSP Service Dish antennas. The tower deflection and rotation ARE within the Connecticut State Police specification of 0.75 degrees of combined deflection (sway) and rotation (twist) for their requested criteria. The DESPP / CSP retains the right to update the requirements of tower Twist and Sway for this site and shall be coordinated with the Department prior to any antenna equipment installation.

Proposed Tower Component Stress vs. Capacity Summary

Component / (Section No.)	Controlling Component/ Elevation	Stress (% capacity)	Pass/Fail
Leg (T16)	ROHN 12 EH w/ L8x8x1/2 w/ (2) / Compression / 30' – 60'	64.9	Pass
Diagonal (T15)	ROHN 3 XXS (3.5" O.D.x0.600") / Compression / 60' – 80'	95.4	Pass
Horizontal (T16)	ROHN 3.5 EH (4.0" O.D.x0.318") / Compression	91.6	Pass
Top Grit (T1)	L1-3/4x1-3/4x3/16 / Compression / 300' – 320"	3.6	Pass
Redundant Horizontal Bracing (T17)	ROHN 1.5 STD (P1.9x0.145") / Compression / 0'-30'	95.5	Pass
Redundant Diagonal Bracing (T17)	ROHN 2 EH (P2.5x0.218") / Compression / 0'-30'	81.7	Pass
Inner Bracing (T17)	ROHN 3 STD (P3.2x0.216") / Compression / 0'-30'	0.6	Pass
Bolt Checks(T10)	@ Diagonal Connection (Member Bearing) (1) A325X 7/8" Dia. / 160' – 170'	93.5	Pass

4. FINDINGS AND EVALUATION (cont.)

Foundation Summary

Component	Required	Computed	% Capacity	Pass/Fail
Anchor Rod Capacity (TIA-222-H – 4.9.9 Addendum. 1)	Ratio < 1.0	0.53	53.0	Pass
Foundation – Drilled Pier Soil Failure Cone Uplift Capacity	1088.63 (Factored Resistance)	740.586	68.0	Pass
Foundation – Drilled Pier Bearing Capacity	1442.54 kip (Factored Resistance)	1296.83	89.9	Pass
Foundation – Drilled Pier Uplift Capacity	865.26 kip (Factored Resistance)	740.586	85.6	Pass
Structure Rating (Maximum from all Components) =			95.5	Pass

Maximum Deformations – Proposed Condition

TIA-222-H Section 2.8.2 - Limit State Deformations

1. A rotation of 4 degrees about the vertical axis (twist) or any horizontal axis (sway) of the structure
2. A horizontal displacement (in feet) of 3% of the height of the structure.

Load Case Description	Current		Allowable	
	Sway (degree)	Displacement (Feet)	Sway (degree)	Displacement (Feet)
Service Wind Load	0.5102	1.90	4.0	9.6

Tower Twist & Sway at Top Service Dish (Connecticut State Police Requirements – TIA/EIA-222-F):

Description	Current	Total	Allowable
Tower Twist (degrees)	0.3642	0.5920	0.750
Tower Sway (degrees)	0.2278		

NOTE: Above combined Twist and Sway results are from the maximum results of current DESPP / CSP Service Dish antennas as permitted from the Department. The DESPP / CSP reserves the right to update the requirements of tower Twist and Sway for this site and shall be coordinated with the Department prior to any antenna equipment installation.

5. CONCLUSIONS

The results of an initial structural analysis indicated that the existing tower did not have enough capacity for the proposed loading conditions above. The tower structure requires modifications shown on SK-1 and SK-2. **Once the modifications indicated on sheets SK-1 and SK-2 are performed, the modified structure, existing anchor bolts and previously modifies foundation are considered structurally adequate with the existing and proposed antenna loading herein.**

Per the Department of Energy Services and Public Protection (DESPP) / Connecticut State Police (CSP) directive, required twist and sway for this location is permitted to be measured from service dishes. The maximum sway (deflection) after tower modification is 0.3642 degrees and the maximum twist (rotation) after tower modification is 0.2278 degrees. These combined figures, measured from CSP service dishes, are within the Connecticut State Police requirement of 0.75 degrees for combined twist (rotation) and sway (deflection) with the load classification specified herein.

The maximum structural capacity calculated, after the tower structure has been modified, is **95.5 %**

Limitations/Assumptions:

This report is based on the following:

- 1) Tower inventory as listed in this report.
- 2) Tower is properly installed and maintained.
- 3) All members are as specified in the original design documents and are in good condition.
- 4) All required members are in place.
- 5) All bolts are in place and are properly tightened.
- 6) Tower is in plumb condition.
- 7) All member protective coatings are in good condition.
- 8) All tower members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
- 9) Foundations are in good condition without defects and were properly constructed to support original design loads as specified in the original design documents.

AECOM is not responsible for any modifications completed prior to or hereafter in which AECOM is not or was not directly involved. Modifications include but are not limited to:

- A. Adding antennas
- B. Removing/replacing antennas
- C. Adding coaxial cables

AECOM hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations, and conclusions are based upon information contained and set forth herein. If you are aware of any information which conflicts with that which is contained herein, or you are aware of any defects arising from original design, material, fabrication, or erection deficiencies, you should disregard this report and immediately contact AECOM. AECOM disclaims all liability for any representation, recommendation, or conclusion not expressly stated herein.

Ongoing and Periodic Inspection and Maintenance:

After the Contractor has successfully completed the installation and the work has been accepted, the owner will be responsible for the ongoing and periodic inspection and maintenance of the tower.

The tower owner shall refer to TIA-222-H Section 14 for recommendations for maintenance and inspection. The frequency of the inspection and maintenance intervals is to be determined by the owner based upon actual site and environmental conditions. It is recommended that a complete and thorough inspection of the entire tower structural system be performed at least yearly and more frequently as conditions warrant. It is also recommended that the structure be inspected after severe wind and/or ice storms or other extreme loading conditions

6. DRAWINGS AND DATA

REINFORCEMENT DRAWINGS SK-1 AND SK-2

GENERAL CONSTRUCTION NOTES

1. ALL WORK SHALL COMPLY WITH THE CONNECTICUT STATE BUILDING AND LIFE SAFETY CODES, SUPPLEMENTS AND AMENDMENTS.
2. CONTRACTOR IS TO REVIEW ALL DRAWINGS AND NOTES IN THE CONTRACT DOCUMENT SET. CONTRACTOR SHALL COORDINATE ALL WORK SHOWN IN THE SET OF DRAWINGS. THE CONTRACTOR SHALL PROVIDE A COMPLETE SET OF DRAWINGS TO ALL SUB-CONTRACTORS AND ALL RELATED PARTIES. THE SUB-CONTRACTORS SHALL EXAMINE ALL THE DRAWINGS AND SPECIFICATIONS FOR THE INFORMATION THAT AFFECTS THEIR WORK.
3. CONTRACTOR SHALL PROVIDE A COMPLETE BUILD-OUT WITH ALL FINISHES, STRUCTURAL, MECHANICAL, AND ELECTRICAL COMPONENTS AND PROVIDE ALL ITEMS AS SHOWN OR INDICATED ON DRAWINGS OR WRITTEN IN SPECIFICATIONS.
4. CONTRACTOR SHALL FURNISH ALL MATERIAL, LABOR AND EQUIPMENT TO COMPLETE THE WORK AND FURNISH A COMPLETED JOB ALL IN ACCORDANCE WITH LOCAL AND STATE GOVERNING AUTHORITIES AND OTHER AUTHORITIES HAVING LAWFUL JURISDICTION OVER THE WORK.
5. CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND ALL INSPECTIONS REQUIRED AND SHALL ALSO PAY FEES REQUIRED FOR THE GENERAL CONSTRUCTION AND ELECTRICAL SUB-CONTRACTORS SHALL PAY FOR THEIR PERMITS.
6. CONTRACTOR SHALL MAINTAIN A CURRENT SET OF DRAWINGS ON SITE AT ALL TIMES AND ENSURE THE DISTRIBUTION OF NEW DRAWINGS TO SUB-CONTRACTORS AND OTHER RELEVANT PARTIES AS SOON AS THEY ARE MADE AVAILABLE. ALL OLD DRAWINGS SHALL BE MARKED VOID AND REMOVED FROM THE CONTRACT AREA. CONTRACTOR SHALL FURNISH 'AS-BUILT' SET OF DRAWINGS TO OWNER UPON COMPLETION OF PROJECT.
7. INSTALLATION OF THIS WIRELESS COMMUNICATIONS EQUIPMENT SITE REQUIRES WORK IN THE IMMEDIATE VICINITY OF EXISTING OPERATING TELECOMMUNICATION SYSTEMS. THE CONTRACTOR SHALL PROVIDE AND COORDINATE THE METHODS OF PROTECTION WITH THE VARIOUS TELECOMMUNICATION CARRIERS AND THE TOWER OWNER. THERE SHALL BE NO INTERRUPTION OF OPERATION WITHOUT TIMELY COORDINATION WITH AND APPROVAL BY THE VARIOUS COMMUNICATIONS OPERATORS INCLUDING THE CONNECTICUT STATE POLICE.
8. THE REINFORCEMENT OF PORTIONS OF THIS TOWER STRUCTURE MAY AFFECT CRITICAL CONNECTICUT STATE POLICE ANTENNAS. NO MOVEMENT, ALTERATION, OR DISCONNECTION OF CONNECTICUT STATE POLICE ANTENNAS MAY OCCUR WITHOUT THE NOTIFICATION AND APPROVAL OF THE CONNECTICUT STATE POLICE. CONTACT THE NETWORK CONTROL CENTER AT 860-865-8008.
9. TOWER REINFORCING WORK AFFECTING CRITICAL CONNECTICUT STATE POLICE ANTENNAS MAY BE REQUIRED TO BE CONDUCTED AT TIMES AS DETERMINED BY THE REQUIREMENTS OF THE CONNECTICUT STATE POLICE.
10. IT SHALL BE MANDATORY TO USE STEEL MATERIALS PLANNED FOR CONSTRUCTION THAT ARE MANUFACTURED IN THE UNITED STATES OF AMERICA. MATERIAL SPECIFICATION DOCUMENTS SHALL BE MADE AVAILABLE TO VERIFY STEEL FABRICATION PRIOR TO PURCHASE AND IMPLEMENTATION. DEVIATIONS SHALL REQUIRE EXPRESSED WRITTEN PERMISSION FROM THE ENGINEER AND CONNECTICUT STATE POLICE.
11. ALL EQUIPMENT AND PRODUCTS PURCHASED ARE TO BE REVIEWED BY CONTRACTOR AND ALL APPLICABLE SUB-CONTRACTORS FOR ANY CONDITION PER MFR'S RECOMMENDATIONS. CONTRACTOR TO SUPPLY THESE ITEMS AT NO COST TO OWNER OR ARCHITECT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ON-SITE SAFETY FROM THE TIME THE JOB IS AWARDED UNTIL ALL WORK IS COMPLETE AND ACCEPTED BY THE OWNER.
13. SHOP DRAWINGS ARE REQUIRED. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, ANGLES, AND EXISTING CONDITIONS ON THE TOWER AND INCLUDE THE GATHERED INFORMATION ON THE SHOP DRAWINGS. NOTE ANY DISCREPANCIES ENCOUNTERED ON THE SHOP DRAWINGS. NO FABRICATION OR INSTALLATION OF STEEL SHALL OCCUR PRIOR TO THE RECEIPT AND APPROVAL OF SHOP DRAWINGS.
14. CONTRACTOR TO REVIEW ALL SHOP DRAWINGS AND SUBMIT COPY TO ARCHITECT FOR REVIEW. DRAWINGS MUST BEAR THE CHECKER'S INITIALS BEFORE SUBMITTAL TO THE ARCHITECT FOR REVIEW.
15. THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION PROCEDURE AND SEQUENCE, AND TO ENSURE THE SAFETY OF THE EXISTING STRUCTURE AND ITS COMPONENT PARTS DURING CONSTRUCTION. THIS INCLUDES THE ADDITION OF WHATEVER SHORING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY.
16. EXISTING DIMENSIONS OF STRUCTURE SHOWN ON THESE DOCUMENTS ARE BASED ON ORIGINAL TOWER CONSTRUCTION DRAWINGS PERFORMED BY ROHN INDUSTRIES, INC., DATED MAY 2001, AND ARE NOT GUARANTEED. CONTRACTOR SHALL TAKE FIELD DIMENSIONS AS NECESSARY TO ASSURE PROPER FIT OF ALL FINISHED WORK AND SHALL ASSUME FULL RESPONSIBILITY FOR THEIR ACCURACY. WHEN SHOP DRAWINGS BASED ON FIELD MEASUREMENT ARE SUBMITTED FOR REVIEW, DIMENSIONS ARE PROVIDED FOR THE ENGINEER'S REFERENCE ONLY.
17. CONTRACTOR TO VERIFY REQUIRED CLEARANCES INCLUDING BUT NOT LIMITED TO EXISTING BUILDINGS, EQUIPMENT PADS AND SHELTERS PRIOR TO COMMENCING WORK.
18. THE CONTRACTOR IS RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE DURING CONSTRUCTION. NO MEMBER OF THE TOWER SHALL BE LEFT DISCONNECTED FOR THE NEXT WORKING DAY. THE CONTRACTOR SHALL BE AWARE OF WEATHER AND WIND CONDITIONS AND NOT PERFORM MEMBER REPLACEMENT IN A WIND.

STRUCTURAL NOTES

STRUCTURAL STEEL MATERIAL NOTES:

STRUCTURAL STEEL BEAMS, CHANNELS, PLATES..... A36
 STRUCTURAL ANGLES:
 ANGLE SIZE 2-1/2"x2-1/2"x1/4" AND SMALLER A36
 ANGLE SIZE GREATER THAN 2-1/2"x2-1/2"x1/4" A 572-Gr. 50
 EXISTING TOWER LEG (ROHN LEG, HORIZONTAL, DIAGONAL PIPE MEMBERS).... A 572-Gr. 50
 STRUCTURAL STEEL SHALL CONFORM TO ALL THE REQUIREMENTS OF THE ASTM SPECIFICATION, AS REFERENCED IN THE CODE.

UNLESS OTHERWISE NOTED, ALL STEEL WILL BE GALVANIZED IN ACCORDANCE WITH ASTM 123 AFTER FABRICATION. TOUCH UP ALL DAMAGED GALVANIZED STEEL WITH APPROVED COLD ZINC, "GALVANOX", "DRY GALV", "ZINC-IT", OR APPROVED EQUIVALENT, IN ACCORDANCE WITH MANUFACTURERS GUIDELINES. TOUCH-UP DAMAGED NON GALVANIZED STEEL WITH SAME PAINT APPLIED IN SHOP OR FIELD.

SHOP AND ERECTION DRAWINGS SHALL BE SUBMITTED FOR ALL STRUCTURAL STEEL WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. SUBMIT 2 SETS OF PRINTS FOR THE ENGINEER REVIEW. REFER TO NOTE 13

MILL BEARING ENDS OF COLUMNS, STIFFENERS, AND OTHER BEARING SURFACES TO TRANSFER LOAD OVER ENTIRE CROSS SECTION.

THE OMISSION OF ANY MATERIAL THAT WAS SHOWN ON THE CONTRACT DRAWINGS SHALL NOT RELIEVE THE CONTRACTOR OF PROVIDING THE SAME.

CONNECTIONS / FIELD ASSEMBLY NOTES:

BOLTED CONNECTIONS: UNLESS OTHERWISE NOTED, ALL JOINTS ARE SLIP CRITICAL TYPE, REQUIRING 5/8", 7/8" & 1" DIA. A325X & A490X BOLTS, A563 NUTS AND F436 WASHERS, ALL GALVANIZED. BEVELED WASHERS SHALL BE USED ON BEAM FLANGES HAVING A SLOPE GREATER THAN 1:20.

STRUCTURE IS DESIGNED TO BE LEVEL AND PLUMB, SELF-SUPPORTING AND STABLE AFTER WORK IS COMPLETED.


COMMENCEMENT OF WORK WITHOUT NOTIFYING THE ENGINEER OF ANY DISCREPANCIES WILL BE CONSIDERED ACCEPTANCE OF PRECEDING WORK.

INSPECTIONS:

SPECIAL INSPECTIONS ARE REQUIRED PER THE CODE FOR STRUCTURAL STEEL WORK.

OWNER WILL SUPPLY THE SERVICES OF A SPECIAL INSPECTOR AND TESTING AGENTS AS REQUIRED. CONTRACTOR SHALL COORDINATE INSPECTIONS OF FABRICATOR'S AND ERECTOR'S WORK AND MATERIALS TO MEET THE REQUIREMENTS OF THE STATEMENT OF SPECIAL INSPECTIONS FOR THIS PROJECT.

COPIES OF TESTING AND INSPECTION REPORTS WILL BE PROVIDED TO THE CONNECTICUT STATE POLICE, BUILDING OFFICIAL, ENGINEER OF RECORD AND CONTRACTOR.



PROJECT NO. 60626930
Designed by: MCD
Drawn by: GAT
Checked by: MJE
Approved by: RAS

AECOM

500 ENTERPRISE DRIVE
 ROCKY HILL, CONNECTICUT
 (860)-529-8882

at&t **EVERSOURCE** **verizon**

SITE ADDRESS: 112 MUNN ROAD
 COLCHESTER, CONNECTICUT 06415


REV.	DATE:	DESCRIPTION
Scale: AS NOTED	Date: 05/21/20	
Job No.	File No.	

Dwg. No.
SK-1

Dwg. 1 of 2

STRUCTURAL NOTES

1. REFER TO STRUCTURAL NOTES ON SK-1 FOR STEEL GRADE REQUIREMENTS FOR MEMBERS. PROPOSED MEMBERS AS INDICATED SHALL HAVE A MINIMUM YIELD STRENGTH OF 50 KSI.
2. REINFORCEMENT OF TOWER IS REQUIRED FOR ALL 3 SIDES OF EXISTING TOWER STRUCTURE.
3. CONNECTION BOLTS FOR REPLACEMENT MEMBERS SHALL BE REPLACED IN KIND, UNLESS NOTED OTHERWISE. EXISTING BOLTS SHALL NOT BE RE-USED FOR CONNECTION REPLACEMENT MEMBERS. EXISTING BOLTS ARE ASSUMED A325X (CONNECTION NOT BEARING ON BOLT THREADS) AND SHALL BE FIELD VERIFIED BEFORE REPLACEMENT OF PROPOSED MEMBERS (INDICATED BELOW). THE ENGINEER SHALL BE NOTIFIED IF EXISTING BOLTS ARE NOT INSTALLED AS A325X IN PROPOSED REPLACEMENT MEMBER REGIONS.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE CONSTRUCTION SEQUENCING AND THE STRUCTURAL INTEGRITY OF THE TOWER DURING CONSTRUCTION.
5. CONTRACTOR SHALL COORDINATE WITH ROHN, INC. FOR THE REPLACEMENT OF MEMBERS INDICATED BELOW. DIAGONAL AND HORIZONTAL BOLTED CONNECTION PLATE SHALL CONFORM TO THE ORIGINAL SPECIFICATIONS AS ORIGINALLY DESIGNED FROM ROHN INC.
6. CONTRACTOR SHALL TAKE NOTE OF ANY EXISTING ANTENNA EQUIPMENT WITHIN THE LOCATION OF THE PROPOSED MEMBER REPLACEMENT AND COORDINATE WITH THE SPECIFIC CARRIER PRIOR TO INSTALLATION. CONTRACTOR SHALL BE RESPONSIBLE FOR ATTACHING THE EXISTING ANTENNA EQUIPMENT AS CLOSE TO EXISTING ELEVATION AFTER REPLACEMENT MEMBERS HAVE BEEN INSTALLED.



- REPLACE EXISTING DIAGONAL ROHN 3 EH (PIPE 3.5" O.D. x 0.3" (t)) WITH ROHN 3 XXS (PIPE 3.5" O.D. x 0.600" (t)) AT ELEVATION 100'-120'
- REPLACE EXISTING ROHN 3 STD (PIPE 3.5" O.D. x 0.216" (t)) WITH ROHN 3 XS (PIPE 3.5" O.D. x 0.300"(t)) AT ELEVATION 100'
- REPLACE EXISTING ROHN 3 EH (PIPE 3.5" O.D. x 0.300" (t)) WITH ROHN 3 XXS (PIPE 3.5" O.D. x 0.600"(t)) AT ELEVATION 80'
- REPLACE EXISTING DIAGONAL ROHN 3.5 EH (PIPE 4" O.D. x 0.318" (t)) WITH ROHN 4 STD (PIPE 4.5" O.D. x 0.237" (t)) AT ELEVATION 30'-60'
- REPLACE EXISTING ROHN 4 STD (PIPE 4.5" O.D. x 0.237" (t)) WITH ROHN 4 XS (PIPE 4.5" O.D. x 0.337"(t)) AT ELEVATION 30'
- REPLACE EXISTING DIAGONAL ROHN 3.5 EH (PIPE 4" O.D. x 0.318" (t)) WITH ROHN 4 STD (PIPE 4.5" O.D. x 0.237" (t)) AT ELEVATION 0'-30'

1 TOWER ELEVATION
 SK-2 SCALE: 1" = 40'-0"

PROJECT NO.
60626930
 Designed by:
MCD
 Drawn by:
GAT
 Checked by:
MJE
 Approved by:
RAS

AECOM
 500 ENTERPRISE DRIVE
 ROCKY HILL, CONNECTICUT
 (860)-529-8882


at&t **EVERSOURCE** **verizon**
 112 MUNN ROAD
 COLCHESTER, CONNECTICUT 06415

REV.	DATE:	DESCRIPTION
Scale:	AS NOTED	Date: 05/21/20
Job No.	File No.	

Dwg. No.
SK-2
 Dwg. 2 of 2

TNX TOWER INPUT / OUTPUT SUMMARY

Section	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	T15	T16	T17
Legs	ROHN 5 EH	ROHN 6 EH	ROHN 8 EH w/ angle 8x8x0.5	ROHN 10 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5	ROHN 12 EH w/ angle 8x8x0.5
Leg Grade	L1 3/4x1 3/4x3/16	L2x2x1/4	L2 1/2x2 1/2x1/4	L3x3x1/4	L4x4x3/8	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2
Diagonals	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36
Diagonal Grade	L1 3/4x1 3/4x3/16	L2x2x1/4	L2 1/2x2 1/2x1/4	L3x3x1/4	L4x4x3/8	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2
Top Girts	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Horizontals	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Red. Horizontals	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Red. Diagonals	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Red. Hips	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Inner Bracing	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Face Width (ft)	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69
# Panels @ (ft)	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4	5 @ 4
Weight (lb)	1442.1	348.7	2498.3	5997.7	9408.2	6484.4	6406.0	7298.6	3730.8	3785.3	9668.6	9975.3	9144.9	8975.5	11450.5	15115.4	17941.9



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod 5/8x4' (Lightning Rod)	329	PIROD 12' Lightweight T-Frame (ATI)	200
Dual Lights (Beacon)	327	PIROD 12' Lightweight T-Frame (ATI)	200
PD128-1 (ECI-1)	325	7770.00 (ATI)	200
6' Side Mount Standoff (ECI-1)	325	HPA-65R-BUU-H8 Panel (ATI)	200
BA1012-0 (ECI-2)	320	RRUS-32 (ATI)	200
6' Side Mount Standoff (ECI-2)	320	RRUS-11 (ATI)	200
ANT450F6 (ECI-3)	318	7770.00 (ATI)	200
4x4" Pipe Mount (ECI-3)	318	HPA-65R-BUU-H8 Panel (ATI)	200
SC479-HF1LDF (ECI-4)	300	RRUS-32 (ATI)	200
6' Side Mount Standoff (ECI-4)	300	RRUS-11 (ATI)	200
PD340-1 (ECI-5)	290	7770.00 (ATI)	200
6' Side Mount Standoff (ECI-5)	290	HPA-65R-BUU-H6 Panel (ATI)	200
DB809T3E-XC (ECI-6)	286	RRUS-32 (ATI)	200
6' Side Mount Standoff (ECI-7)	284	RRUS-11 (ATI)	200
SC479-HF1LDF(D001-E6085) (Inverted) (ECI-7)	283	DC6-48-60-0-8C Squid / Surge Arrestor (ATI)	200
PD440-2 (ECI-8)	264	STK-U Stiffener Side Arm Attachment (ATI)	200
6' Side Mount Standoff (ECI-8)	260	STK-U Stiffener Side Arm Attachment (ATI)	200
SC479-HF1LDF (ECI-10)	251	STK-U Stiffener Side Arm Attachment (ATI)	200
PD1142-1 (ECI-14)	248	STK-U Stiffener Side Arm Attachment (ATI)	200
6' Side Mount Standoff (ECI-14)	248	STK-U Stiffener Side Arm Attachment (ATI)	200
430-94C-09168-M-11048 TTA (ECI-11)	247	STK-U Stiffener Side Arm Attachment (ATI)	200
Sabre T-Boom (1) (ECI-10,11,12,13)	246	DB586-Y (ECI-50)	179
SC479-HF1LDF(D001-E6085) (Inverted) (ECI-13)	245	Pirot 4' Side Mount Standoff (1) (ECI-50)	179
SC479-HF1LDF(D001-E6085) (Inverted) (ECI-12)	245	DB586-Y (ECI-51)	177
6' Side Mount Standoff (ECI-15)	238	430-94C-09168-M-11048 TTA (ECI-52)	176
531-70HD Exposed Dipole Antenna (ECI-15)	238	Pirot 4' Side Mount Standoff (1) (ECI-53,52,51)	176
Valmont VFA-10-U V-Frame (Verizon)	232	DB586-Y (Inverted) (ECI-53)	175
Valmont VFA-10-U V-Frame (Verizon)	232	L-810 Obstruction Lighting (1) (ECI-54)	168
Valmont VFA-10-U V-Frame (Verizon)	232	L-810 Obstruction Lighting (1) (ECI-55)	165
JAHH-65B-R3B Panel Antenna (Verizon-AWS)	232	L-810 Obstruction Lighting (1) (ECI-56)	164
JAHH-65B-R3B Panel Antenna (Verizon-PCS)	232	Telewave ANT220F2 - Omni Antenna (Eversource (Proposed))	163
LNx-6512DS-VTM (Verizon-850)	232	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed) (Eversource (Proposed))	160
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2)) (Verizon-PCS/AWS)	232	5'3"x4" Pipe Mount (ECI-58a (Dish Support))	154
RFV01U-D1A RRH Unit (Verizon RRH)	232	Commscope PAR6-59W-PXA/A (ECI-58)	154
RFV01U-D2A RRH Unit (Verizon RRH)	232	ANT450F6 (ECI-57)	153
DB-B1-6C-12AB-0Z / DC-3315-PF-48 Dist. Box (Verizon)	232	5'3"x4" Pipe Mount (ECI-57)	153
JAHH-65B-R3B Panel Antenna (Verizon-AWS)	232	Telewave ANT220F2 - Omni Antenna (Eversource (Proposed))	145
JAHH-65B-R3B Panel Antenna (Verizon-PCS)	232	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed) (Eversource (Proposed))	142
LNx-6512DS-VTM (Verizon-850)	232	PD156S (ECI-60)	139
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2)) (Verizon-PCS/AWS)	232	DB212-1 (ECI-59)	139
RFV01U-D1A RRH Unit (Verizon RRH)	232	4' Side Mount Standoff (ECI-60 .59)	139
RFV01U-D2A RRH Unit (Verizon RRH)	232	3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-61a)	117
DB-B1-6C-12AB-0Z / DC-3315-PF-48 Dist. Box (Verizon)	232	8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-63a (Dish Ice Shield))	115
JAHH-65B-R3B Panel Antenna (Verizon-AWS)	232	5'3"x4" Pipe Mount (ECI-61a (Dish Support))	112
JAHH-65B-R3B Panel Antenna (Verizon-PCS)	232	Andrew 2' w/Radome (ECI-61)	112
LNx-6512DS-VTM (Verizon-850)	232	5'3"x4" Pipe Mount (ECI-63 (Dish Support))	107
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2)) (Verizon-PCS/AWS)	232	PA8-65 (ECI-63)	107
RFV01U-D1A RRH Unit (Verizon RRH)	232	PD458 (ECI-62)	106
RFV01U-D2A RRH Unit (Verizon RRH)	232	Pirot 4' Side Mount Standoff (1) (ECI-62)	106
CBC78T-DS-43-2X Diplexer (Verizon)	232	PD688S-4 (ECI-66)	94
CBC78T-DS-43-2X Diplexer (Verizon)	232	4'x4" Pipe Mount (ECI-66)	94
CBC78T-DS-43-2X Diplexer (Verizon)	232		
PIROD 12' Lightweight T-Frame (ATI)	200		

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi


TOWER DESIGN NOTES

1. Tower designed for Exposure C to the TIA-222-H Standard.
2. Tower designed for a 140 mph basic wind in accordance with the TIA-222-H Standard.
3. Tower is also designed for a 50 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Risk Category III.
6. Topographic Category 3 with Crest Height of 66.50 ft
7. P-Delta Displacement Effects are not applicable to this tower for this case (TIA-222-H Section 3.5)
8. TOWER RATING: 95.5%

ALL REACTIONS ARE FACTORED


MAX. CORNER REACTIONS AT BASE:
 DOWN: 942660 lb
 SHEAR: 129314 lb

UPLIFT: -740586 lb
 SHEAR: 106386 lb



AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job: 320' Rohn SSMVM
	Project: CSP Tower - Colchester, CT
	Client: VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"
	Code: TIA-222-H
Path:	Drawn by: MCD
Date: 05/18/20	Scale: NTS
Dwg No. E-1	

Section	T17	T16	T15	T14	T13	T12	T11	T10	T9	T8	T7	T6	T5	T4	T3	T2	T1	
Legs	A	ROHN 12 EH w/ angle 8x8x0.5	ROHN 10 EH w/ angle 8x8x0.5	ROHN 10 EH w/ angle 8x8x0.5	ROHN 10 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 6 EH	ROHN 5 EH										
Leg Grade																		
Diagonals		ROHN 4 EH	ROHN 3 XXS	ROHN 3 XXS	ROHN 3 XXS	L5x5x1/2	L4x4x3/8	L4x4x5/16	L3x3x1/4	L2x2x1/4	A36	L2x2x1/4	L2x2x1/4					
Diagonal Grade																		
Top Girts																		
Horizontals		ROHN 4 EH	ROHN 3.5 EH	ROHN 3.5 EH	ROHN 3.5 EH	ROHN 3 STD	ROHN 3 EH	ROHN 3 EH	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	ROHN 3 STD	
Red. Horizontals		P1.5x.145	ROHN 1.5 STD	ROHN 1.5 STD	ROHN 1.5 STD	ROHN 1.5 STD	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	P1.5x.145	
Red. Diagonals		ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	
Red. Hips																		
Inner Bracing																		
Face Width (ft)	40.89	36.8	33.14	30.47	27.97	25.39	23.21	21.3	20.26	19.22	17.09	15.09	13.08	11.04	8.85		6.81	
# Panels @ (ft)		2 @ 30	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20	3 @ 20
Weight (lb)	125382.3	17941.9	15115.4	11450.5	9675.5	9144.9	9675.3	9006.6	3795.3	3750.8	7298.6	6406.0	6494.4	5409.2	5907.7	2496.3	340.7	1442.1



SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	ROHN 12 EHS w Angle 8x8x0.625	D	N.A.
B	L1 3/4x1 3/4x3/16	E	ROHN 1.5 STD
C	L2 1/2x2 1/2x1/4		

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi

TOWER DESIGN NOTES


1. Tower designed for Exposure C to the TIA-222-H Standard.
2. Tower designed for a 140 mph basic wind in accordance with the TIA-222-H Standard.
3. Tower is also designed for a 50 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Risk Category III.
6. Topographic Category 3 with Crest Height of 66.50 ft
7. P-Delta Displacement Effects are not applicable to this tower for this case (TIA-222-H Section 3.5)
8. TOWER RATING: 95.5%

ALL REACTIONS ARE FACTORED


MAX. CORNER REACTIONS AT BASE:

DOWN: 942660 lb
SHEAR: 129314 lb

UPLIFT: -740586 lb
SHEAR: 106386 lb



TORQUE 151 kip-ft
50 mph WIND - 1.0000 in ICE



TORQUE 380 kip-ft
REACTIONS - 140 mph WIND


<p>AECOM</p> <p>500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	<p>Job: 320' Rohn SSVMW</p>		
	<p>Project: CSP Tower - Colchester, CT</p>		
	<p>Client: VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"</p>	<p>Drawn by: MCD</p>	<p>App'd:</p>
	<p>Code: TIA-222-H</p>	<p>Date: 05/18/20</p>	<p>Scale: NTS</p>
	<p>Path:</p>	<p>Dwg No. E-1</p>	

TNX TOWER FEEDLINE DISTRIBUTION CHART

Feed Line Distribution Chart

0' - 320'

— Round
 — Flat
 — App In Face
 — App Out Face
 — Truss Leg




AECOM			Job: 320' Rohn SSSVMW		
500 Enterprise Drive, Suite 3B			Project: CSP Tower - Colchester, CT		
Rocky Hill, CT			Client: VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"		
Phone: 860-263-5800			Code: TIA-222-H	Drawn by: MCD	App'd:
FAX: 860-812-2094			Path:	Date: 05/18/20	Scale: NTS
Dwg No. E-7					

TNX TOWER FEEDLINE PLAN




Feed Line Plan

— Round
 — Flat
 — App In Face
 — App Out Face



AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job: 320' Rohn SSVMW Project: CSP Tower - Colchester, CT Client: VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H" Code: TIA-222-H Path:	Drawn by: MCD Date: 05/18/20 App'd: Scale: NTS Dwg No. E-7
--------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------

TNX TOWER DEFLECTION, TILT, AND TWIST



<p>AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	Job: 320' Rohn SSVMW		
	Project: CSP Tower - Colchester, CT		
	Client: VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Drawn by: MCD	App'd:
	Code: TIA-222-H	Date: 05/18/20	Scale: NTS
	Path:	Dwg No. E-5	

TNX TOWER DETAILED OUTPUT

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	1 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 320.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 6.81 ft at the top and 40.69 ft at the base.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

Tower base elevation above sea level: 0.00 ft.

Basic wind speed of 140 mph.

Risk Category III.

Exposure Category C.

Simplified Topographic Factor Procedure for wind speed-up calculations is used.

Topographic Category: 3.

Crest Height: 66.50 ft.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

P-Delta Displacement Effects are not applicable to this tower for this case (TIA-222-H Section 3.5).

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

<ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile √ Include Bolts In Member Capacity Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) √ SR Members Have Cut Ends SR Members Are Concentric 	<ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks Use Azimuth Dish Coefficients Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination √ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs 	<ul style="list-style-type: none"> Use ASCE 10 X-Brace Ly Rules √ Calculate Redundant Bracing Forces Ignore Redundant Members in FEA √ SR Leg Bolts Resist Compression √ All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feed Line Torque √ Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption <li style="text-align: center;">Poles Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known
--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 2 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD



Triangular Tower

Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	320.00-304.00			6.81	1	16.00
T2	304.00-300.00			6.81	1	4.00
T3	300.00-280.00			6.81	1	20.00
T4	280.00-260.00			8.85	1	20.00
T5	260.00-240.00			11.04	1	20.00
T6	240.00-220.00			13.08	1	20.00
T7	220.00-200.00			15.09	1	20.00
T8	200.00-180.00			17.09	1	20.00
T9	180.00-170.00			19.22	1	10.00
T10	170.00-160.00			20.26	1	10.00
T11	160.00-140.00			21.30	1	20.00
T12	140.00-120.00			23.21	1	20.00
T13	120.00-100.00			25.39	1	20.00
T14	100.00-80.00			27.97	1	20.00
T15	80.00-60.00			30.47	1	20.00
T16	60.00-30.00			33.14	1	30.00
T17	30.00-0.00			36.80	1	30.00

Tower Section Geometry (cont'd)

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	3 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Tower Elevation ft	Diagonal Spacing ft	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset in	Bottom Girt Offset in
T1	320.00-304.00	4.00	X Brace	No	No	0.0000	0.0000
T2	304.00-300.00	4.00	X Brace	No	No	0.0000	0.0000
T3	300.00-280.00	5.00	X Brace	No	No	0.0000	0.0000
T4	280.00-260.00	6.67	X Brace	No	No	0.0000	0.0000
T5	260.00-240.00	6.67	X Brace	No	No	0.0000	0.0000
T6	240.00-220.00	6.67	X Brace	No	No	0.0000	0.0000
T7	220.00-200.00	10.00	X Brace	No	No	0.0000	0.0000
T8	200.00-180.00	10.00	X Brace	No	No	0.0000	0.0000
T9	180.00-170.00	10.00	X Brace	No	No	0.0000	0.0000
T10	170.00-160.00	10.00	X Brace	No	No	0.0000	0.0000
T11	160.00-140.00	10.00	X Brace	No	No	0.0000	0.0000
T12	140.00-120.00	10.00	X Brace	No	No	0.0000	0.0000
T13	120.00-100.00	20.00	K1 Down	No	Yes	0.0000	0.0000
T14	100.00-80.00	20.00	K1 Down	No	Yes	0.0000	0.0000
T15	80.00-60.00	20.00	K1 Down	No	Yes	0.0000	0.0000
T16	60.00-30.00	30.00	K2 Down	No	Yes	0.0000	0.0000
T17	30.00-0.00	30.00	K2 Down	No	Yes	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T1 320.00-304.00	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Equal Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)
T2 304.00-300.00	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Equal Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)
T3 300.00-280.00	Pipe	ROHN 6 EH	A572-50 (50 ksi)	Equal Angle	L2x2x1/4	A36 (36 ksi)
T4 280.00-260.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)
T5 260.00-240.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L3x3x1/4	A572-50 (50 ksi)
T6 240.00-220.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x5/16	A572-50 (50 ksi)
T7 220.00-200.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T8 200.00-180.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T9 180.00-170.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T10 170.00-160.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T11 160.00-140.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L5x5x1/2	A572-50 (50 ksi)
T12 140.00-120.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L5x5x1/2	A572-50 (50 ksi)
T13 120.00-100.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T14 100.00-80.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T15 80.00-60.00	Arbitrary Shape	ROHN 12 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T16 60.00-30.00	Arbitrary Shape	ROHN 12 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 4 EH	A572-50 (50 ksi)
T17 30.00-0.00	Arbitrary Shape	ROHN 12 EHS w Angle	A572-50	Pipe	ROHN 4 EH	A572-50

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 4 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
		8x8x0.625	(50 ksi)			(50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 320.00-304.00	Equal Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T3 300.00-280.00	Equal Angle	L2x2x1/4	A36 (36 ksi)	Solid Round		A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
T13 120.00-100.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T14 100.00-80.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3 EH	A572-50 (50 ksi)
T15 80.00-60.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T16 60.00-30.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3.5 EH	A572-50 (50 ksi)
T17 30.00-0.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 4 EH	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
T13 120.00-100.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T14 100.00-80.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T15 80.00-60.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T16 60.00-30.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T17 30.00-0.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	5 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section Geometry (cont'd)

Tower Elevation	Redundant Bracing Grade	Redundant Type	Redundant Size	K Factor
ft				
T13 120.00-100.00	A572-50 (50 ksi)	Horizontal (1) Diagonal (1) Hip (1)	Pipe Pipe Pipe	1 1 1
T14 100.00-80.00	A572-50 (50 ksi)	Hip Diagonal (1) Horizontal (1) Diagonal (1) Hip (1)	Pipe Pipe Pipe Pipe	1 1 1 1
T15 80.00-60.00	A572-50 (50 ksi)	Hip Diagonal (1) Horizontal (1) Diagonal (1) Hip (1)	Pipe Pipe Pipe Pipe	1 1 1 1
T16 60.00-30.00	A572-50 (50 ksi)	Hip Diagonal (1) Horizontal (1) Horizontal (2) Diagonal (1) Diagonal (2) Hip (1) Hip (2)	Pipe Pipe Pipe Pipe Pipe Pipe Pipe	1 1 1 1 1 1 1
T17 30.00-0.00	A572-50 (50 ksi)	Hip Diagonal (1) Hip Diagonal (2) Horizontal (1) Horizontal (2) Diagonal (1) Diagonal (2) Hip (1) Hip (2) Hip Diagonal (1) Hip Diagonal (2)	Pipe Pipe Pipe Pipe Pipe Pipe Pipe Pipe Pipe Pipe	1 1 1 1 1 1 1 1 1 1

Tower Section Geometry (cont'd)

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft ²	in					in	in	in
T1 320.00-304.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T2 304.00-300.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T3 300.00-280.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T4 280.00-260.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T5 260.00-240.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T6 240.00-220.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T7 220.00-200.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T8	0.00	0.0000	A36	1	1	1	36.0000	36.0000	36.0000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	8 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1	Flange	1.0000	0	0.6250	1	0.6250	0	0.0000	0	0.6250	0	0.6250	0	0.6250	0
320.00-304.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T2	Flange	1.0000	6	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
304.00-300.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T3	Flange	1.0000	8	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
300.00-280.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T4	Flange	1.0000	8	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
280.00-260.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T5	Flange	1.0000	8	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
260.00-240.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T6	Flange	1.0000	8	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
240.00-220.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T7	Flange	1.0000	12	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
220.00-200.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T8	Flange	1.0000	12	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
200.00-180.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T9	Flange	1.0000	12	0.8750	1	0.6250	0	0.0000	0	0.6250	0	0.6250	0	0.6250	0
180.00-170.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T10	Flange	1.0000	0	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
170.00-160.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T11	Flange	1.0000	12	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
160.00-140.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T12	Flange	1.0000	12	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
140.00-120.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T13	Flange	1.0000	12	0.7500	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
120.00-100.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T14	Flange	1.0000	16	0.7500	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
100.00-80.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T15	Flange	1.0000	16	0.7500	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
80.00-60.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T16	Flange	1.0000	16	0.8750	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
60.00-30.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T17 30.00-0.00	Flange	1.0000	24	0.8750	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
		A325N		A325X		A325N		A325N		A325N		A325X		A325N	

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
1 5/8 (AT&T)	A	No	No	Ar (CaAa)	200.00 - 5.00	0.0000	-0.42	6	6	1.9800	1.9800		1.04
1 5/8 (Verizon)	C	No	No	Ar (CaAa)	220.00 - 5.00	0.0000	-0.4	6	6	1.9800	1.9800		1.04
1 5/8" Hybriflex (VZW)	C	No	No	Ar (CaAa)	220.00 - 5.00	0.0000	-0.46	2	2	1.6000	1.6000		1.85
LC78-50JA-A	B	No	No	Ar (CaAa)	174.00 -	0.0000	0.48	1	1	1.0900	1.0900		0.28

Job	320' Rohn SSVMW	Page	10 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
HTS) AVA7-50 (1-5/8 LOW DENSL FOAM) (Cable # 16 HTS)	B	No	No	Ar (CaAa)	246.00 - 5.00	0.0000	0.38	1	1	1.9800	1.9800		0.72
HTS) AVA7-50 (1-5/8 LOW DENSL FOAM) (Cable # 17 HTS)	B	No	No	Ar (CaAa)	246.00 - 5.00	3.0000	0.38	1	1	1.9800	1.9800		0.72
HTS) LDF4-50A (1/2 FOAM) (Cable # 18 HTS)	B	No	No	Ar (CaAa)	246.00 - 5.00	6.0000	0.38	1	1	0.6300	0.6300		0.15
HTS) LC78-50JA-A 7 (Cable # 15 HTS)	B	No	No	Ar (CaAa)	235.00 - 5.00	0.0000	0.37	1	1	1.0900	1.0900		0.28
HTS) WE65 (Cable # 14 HTS)	B	No	No	Af (CaAa)	106.00 - 5.00	3.0000	0.37	1	1	1.5836	1.5836		0.53
HTS) LC78-50JA-A 7 (Cable # 13 HTS)	B	No	No	Ar (CaAa)	244.00 - 5.00	0.0000	0.36	1	1	1.0900	1.0900		0.28
HTS) LC78-50JA-A 7 (Cable #12 HTS)	B	No	No	Ar (CaAa)	262.00 - 5.00	0.0000	0.35	1	1	1.0900	1.0900		0.28
HTS) WE108 (Cable # 11 HTS)	B	No	No	Af (CaAa)	113.00 - 5.00	3.0000	0.35	1	1	1.0149	1.0149		0.35
HTS) LC78-50JA-A 7 (Cable # 10 HTS)	B	No	No	Ar (CaAa)	297.00 - 5.00	0.0000	0.34	1	1	1.0900	1.0900		0.28
HTS) LC78-50JA-A 7 (Cable # 9 HTS)	B	No	No	Ar (CaAa)	290.00 - 5.00	0.0000	0.33	1	1	1.0900	1.0900		0.28
HTS) 1/2 (Cable # 8 HTS)	B	No	No	Ar (CaAa)	284.00 - 5.00	3.0000	0.33	1	1	0.5800	0.5800		0.25
HTS) 1/2 (Cable # 6 HTS)	B	No	No	Ar (CaAa)	320.00 - 5.00	6.0000	0.33	1	1	0.5800	0.5800		0.25
HTS) LC78-50JA-A 7 (Cable # 4 HTS)	B	No	No	Ar (CaAa)	320.00 - 5.00	0.0000	0.32	1	1	1.0900	1.0900		0.28
HTS) 1/2 (Cable # 7 HTS)	B	No	No	Ar (CaAa)	284.00 - 5.00	3.0000	0.32	1	1	0.5800	0.5800		0.25
HTS) 1/2 (Cable # 5 HTS)	B	No	No	Ar (CaAa)	164.00 - 5.00	6.0000	0.32	1	1	0.5800	0.5800		0.25
HTS) LC78-50JA-A	B	No	No	Ar (CaAa)	316.50 -	0.0000	0.31	1	1	1.0900	1.0900		0.28

<p>tnxTower</p> <p>AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	<p>Job</p> <p>320' Rohn SSVMW</p>	<p>Page</p> <p>11 of 95</p>
	<p>Project</p> <p>CSP Tower - Colchester, CT</p>	<p>Date</p> <p>12:07:36 05/18/20</p>
	<p>Client</p> <p>VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"</p>	<p>Designed by</p> <p>MCD</p>

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	# Per Row	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
7 (Cable #3 HTS)					5.00								
LC78-50JA-A	B	No	No	Ar (CaAa)	318.00 - 5.00	0.0000	0.29	1	1	1.0900	1.0900		0.28
7 (Cable #1 HTS) * CSP Proposed Cables EW63 (CSP Dish @ 154')	B	No	No	Af (CaAa)	154.00 - 5.00	0.0000	0.29	1	1	1.5742	1.5742		0.51
1-5/8" Fiber Optic CaBLE (AT&T)	A	No	No	Ar (CaAa)	200.00 - 5.00	0.0000	-0.37	1	1	1.9800	1.9800		1.85
1/2 (AT&T) * Eversource LCF78-50J (7/8 FOAM) (Eversource) LCF78-50J (7/8 FOAM) (Eversource)	A	No	No	Ar (CaAa)	200.00 - 5.00	0.0000	-0.35	2	2	0.5800	0.5800		0.25
	B	No	No	Ar (CaAa)	163.00 - 5.00	0.0000	0.27	1	1	1.1000	1.1000		0.53
	B	No	No	Ar (CaAa)	145.00 - 5.00	0.0000	0.26	1	1	1.1000	1.1000		0.53

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight lb
T1	320.00-304.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	5.561	0.000	15.90
		C	0.000	0.000	0.000	0.000	0.00
T2	304.00-300.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	1.540	0.000	4.36
		C	0.000	0.000	0.000	0.000	0.00
T3	300.00-280.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	13.483	0.000	40.00
		C	0.000	0.000	0.000	0.000	0.00
T4	280.00-260.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	26.676	0.000	87.48
		C	0.000	0.000	0.000	0.000	0.00
T5	260.00-240.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	37.174	0.000	122.62
		C	0.000	0.000	0.000	0.000	0.00
T6	240.00-220.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	49.355	0.000	162.20
		C	0.000	0.000	0.000	0.000	0.00
T7	220.00-200.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	49.900	0.000	163.60
		C	0.000	0.000	30.160	0.000	198.80
T8	200.00-180.00	A	0.000	0.000	30.040	0.000	171.80
		B	0.000	0.000	49.900	0.000	163.60
		C	0.000	0.000	30.160	0.000	198.80
T9	180.00-170.00	A	0.000	0.000	15.020	0.000	85.90

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	12 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Tower Elevation ft	Face	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
T10	170.00-160.00	B	0.000	0.000	27.055	0.000	87.16
		C	0.000	0.000	15.080	0.000	99.40
		A	0.000	0.000	15.020	0.000	85.90
T11	160.00-140.00	B	0.000	0.000	29.412	0.000	94.29
		C	0.000	0.000	15.080	0.000	99.40
		A	0.000	0.000	30.040	0.000	171.80
T12	140.00-120.00	B	0.000	0.000	65.283	0.000	208.79
		C	0.000	0.000	30.160	0.000	198.80
		A	0.000	0.000	30.040	0.000	171.80
T13	120.00-100.00	B	0.000	0.000	71.886	0.000	228.48
		C	0.000	0.000	30.160	0.000	198.80
		A	0.000	0.000	30.040	0.000	171.80
T14	100.00-80.00	B	0.000	0.000	76.650	0.000	238.73
		C	0.000	0.000	30.160	0.000	198.80
		A	0.000	0.000	30.040	0.000	171.80
T15	80.00-60.00	B	0.000	0.000	83.818	0.000	254.48
		C	0.000	0.000	30.160	0.000	198.80
		A	0.000	0.000	30.040	0.000	171.80
T16	60.00-30.00	B	0.000	0.000	85.889	0.000	259.80
		C	0.000	0.000	30.160	0.000	198.80
		A	0.000	0.000	45.060	0.000	257.70
T17	30.00-0.00	B	0.000	0.000	128.833	0.000	389.70
		C	0.000	0.000	45.240	0.000	298.20
		A	0.000	0.000	37.550	0.000	214.75
		B	0.000	0.000	107.361	0.000	324.75
		C	0.000	0.000	37.700	0.000	248.50

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
T1	320.00-304.00	A	1.440	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	22.405	0.000	261.85
		C		0.000	0.000	0.000	0.000	0.00
T2	304.00-300.00	A	1.435	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	6.132	0.000	71.62
		C		0.000	0.000	0.000	0.000	0.00
T3	300.00-280.00	A	1.429	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	49.786	0.000	592.40
		C		0.000	0.000	0.000	0.000	0.00
T4	280.00-260.00	A	1.419	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	89.970	0.000	1098.70
		C		0.000	0.000	0.000	0.000	0.00
T5	260.00-240.00	A	1.408	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	118.862	0.000	1465.07
		C		0.000	0.000	0.000	0.000	0.00
T6	240.00-220.00	A	1.397	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	154.126	0.000	1898.59
		C		0.000	0.000	0.000	0.000	0.00
T7	220.00-200.00	A	1.385	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	155.138	0.000	1897.96
		C		0.000	0.000	84.362	0.000	1118.41
T8	200.00-180.00	A	1.372	0.000	0.000	85.834	0.000	1097.47
		B		0.000	0.000	154.148	0.000	1873.34
		C		0.000	0.000	84.196	0.000	1110.86
T9	180.00-170.00	A	1.361	0.000	0.000	42.830	0.000	545.46
		B		0.000	0.000	84.506	0.000	1014.93

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	13 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
T10	170.00-160.00	C	1.354	0.000	0.000	42.033	0.000	552.45
		A		0.000	0.000	42.771	0.000	543.21
		B		0.000	0.000	93.607	0.000	1112.03
T11	160.00-140.00	C	1.343	0.000	0.000	41.988	0.000	550.41
		A		0.000	0.000	85.358	0.000	1079.51
		B		0.000	0.000	204.733	0.000	2407.81
T12	140.00-120.00	C	1.329	0.000	0.000	83.838	0.000	1094.54
		A		0.000	0.000	85.111	0.000	1070.23
		B		0.000	0.000	223.633	0.000	2603.25
T13	120.00-100.00	C	1.315	0.000	0.000	83.653	0.000	1086.09
		A		0.000	0.000	84.874	0.000	1061.34
		B		0.000	0.000	234.150	0.000	2697.30
T14	100.00-80.00	C	1.303	0.000	0.000	83.474	0.000	1078.00
		A		0.000	0.000	84.672	0.000	1053.80
		B		0.000	0.000	250.822	0.000	2860.17
T15	80.00-60.00	C	1.295	0.000	0.000	83.322	0.000	1071.12
		A		0.000	0.000	84.548	0.000	1049.17
		B		0.000	0.000	256.871	0.000	2914.85
T16	60.00-30.00	C	1.298	0.000	0.000	83.229	0.000	1066.90
		A		0.000	0.000	126.883	0.000	1576.02
		B		0.000	0.000	385.783	0.000	4383.52
T17	30.00-0.00	C	1.303	0.000	0.000	124.889	0.000	1602.42
		A		0.000	0.000	105.842	0.000	1317.33
		B		0.000	0.000	322.322	0.000	3672.72
		C		0.000	0.000	104.154	0.000	1338.97

Feed Line Center of Pressure

Section	Elevation ft	CP_x in	CP_z in	CP_x Ice in	CP_z Ice in
T1	320.00-304.00	2.5585	0.7653	5.6337	1.5661
T2	304.00-300.00	2.9423	0.8782	6.2954	1.7537
T3	300.00-280.00	5.1025	1.7459	10.0743	3.1831
T4	280.00-260.00	5.9278	2.4135	13.9763	5.1940
T5	260.00-240.00	8.6793	3.7103	19.0753	7.4793
T6	240.00-220.00	11.2158	4.8855	24.0367	9.6748
T7	220.00-200.00	18.8855	10.7084	35.8552	18.7814
T8	200.00-180.00	10.5945	13.5306	20.1939	22.9916
T9	180.00-170.00	12.1987	14.8386	23.4962	25.3656
T10	170.00-160.00	13.6862	15.8268	26.6700	27.1187
T11	160.00-140.00	14.7151	15.8660	28.9029	27.6923
T12	140.00-120.00	16.8966	17.2119	32.9481	30.0279
T13	120.00-100.00	24.6974	23.3249	42.0482	36.3965
T14	100.00-80.00	28.6992	25.8171	47.7485	39.8986
T15	80.00-60.00	29.1100	26.0679	50.1565	41.7015
T16	60.00-30.00	31.4614	28.1866	54.0369	44.9527
T17	30.00-0.00	29.4550	26.5187	52.4688	43.8449

Shielding Factor Ka

Job	320' Rohn SSMW	Page	14 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T1	31		1/2 304.00 - 320.00	0.6000	0.6000
T1	32	LC78-50JA-A7	304.00 - 320.00	0.6000	0.6000
T1	35	LC78-50JA-A7	304.00 - 316.50	0.6000	0.6000
T1	36	LC78-50JA-A7	304.00 - 318.00	0.6000	0.6000
T2	31		1/2 300.00 - 304.00	0.6000	0.6000
T2	32	LC78-50JA-A7	300.00 - 304.00	0.6000	0.6000
T2	35	LC78-50JA-A7	300.00 - 304.00	0.6000	0.6000
T2	36	LC78-50JA-A7	300.00 - 304.00	0.6000	0.6000
T3	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	280.00 - 283.00	0.6000	0.6000
T3	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	280.00 - 284.00	0.6000	0.6000
T3	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	280.00 - 285.00	0.6000	0.6000
T3	28	LC78-50JA-A7	280.00 - 297.00	0.6000	0.6000
T3	29	LC78-50JA-A7	280.00 - 290.00	0.6000	0.6000
T3	30		1/2 280.00 - 284.00	0.6000	0.6000
T3	31		1/2 280.00 - 300.00	0.6000	0.6000
T3	32	LC78-50JA-A7	280.00 - 300.00	0.6000	0.6000
T3	33		1/2 280.00 - 284.00	0.6000	0.6000
T3	35	LC78-50JA-A7	280.00 - 300.00	0.6000	0.6000
T3	36	LC78-50JA-A7	280.00 - 300.00	0.6000	0.6000
T4	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	260.00 - 280.00	0.6000	0.6000
T4	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	260.00 - 280.00	0.6000	0.6000
T4	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	260.00 - 261.00	0.6000	0.6000
T4	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	260.00 - 280.00	0.6000	0.6000
T4	26	LC78-50JA-A7	260.00 - 262.00	0.6000	0.6000
T4	28	LC78-50JA-A7	260.00 - 280.00	0.6000	0.6000
T4	29	LC78-50JA-A7	260.00 - 280.00	0.6000	0.6000
T4	30		1/2 260.00 - 280.00	0.6000	0.6000
T4	31		1/2 260.00 - 280.00	0.6000	0.6000
T4	32	LC78-50JA-A7	260.00 - 280.00	0.6000	0.6000
T4	33		1/2 260.00 - 280.00	0.6000	0.6000
T4	35	LC78-50JA-A7	260.00 - 280.00	0.6000	0.6000

Job	320' Rohn SSMW	Page	15 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T4	36	LC78-50JA-A7	260.00 - 280.00	0.6000	0.6000
T5	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	240.00 - 260.00	0.6000	0.6000
T5	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	240.00 - 260.00	0.6000	0.6000
T5	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	240.00 - 260.00	0.6000	0.6000
T5	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	240.00 - 248.00	0.6000	0.6000
T5	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	240.00 - 260.00	0.6000	0.6000
T5	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	240.00 - 246.00	0.6000	0.6000
T5	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	240.00 - 246.00	0.6000	0.6000
T5	22	LDF4-50A (1/2 FOAM)	240.00 - 246.00	0.6000	0.6000
T5	25	LC78-50JA-A7	240.00 - 244.00	0.6000	0.6000
T5	26	LC78-50JA-A7	240.00 - 260.00	0.6000	0.6000
T5	28	LC78-50JA-A7	240.00 - 260.00	0.6000	0.6000
T5	29	LC78-50JA-A7	240.00 - 260.00	0.6000	0.6000
T5	30	1/2	240.00 - 260.00	0.6000	0.6000
T5	31	1/2	240.00 - 260.00	0.6000	0.6000
T5	32	LC78-50JA-A7	240.00 - 260.00	0.6000	0.6000
T5	33	1/2	240.00 - 260.00	0.6000	0.6000
T5	35	LC78-50JA-A7	240.00 - 260.00	0.6000	0.6000
T5	36	LC78-50JA-A7	240.00 - 260.00	0.6000	0.6000
T6	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	220.00 - 240.00	0.6000	0.6000
T6	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	220.00 - 240.00	0.6000	0.6000
T6	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	220.00 - 240.00	0.6000	0.6000
T6	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	220.00 - 240.00	0.6000	0.6000
T6	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	220.00 - 240.00	0.6000	0.6000
T6	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	220.00 - 240.00	0.6000	0.6000
T6	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	220.00 - 240.00	0.6000	0.6000
T6	22	LDF4-50A (1/2 FOAM)	220.00 - 240.00	0.6000	0.6000
T6	23	LC78-50JA-A7	220.00 - 235.00	0.6000	0.6000
T6	25	LC78-50JA-A7	220.00 - 240.00	0.6000	0.6000
T6	26	LC78-50JA-A7	220.00 - 240.00	0.6000	0.6000
T6	28	LC78-50JA-A7	220.00 - 240.00	0.6000	0.6000

Job	320' Rohn SSMW	Page	16 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T6	29	LC78-50JA-A7	220.00 - 240.00	0.6000	0.6000
T6	30	1/2	220.00 - 240.00	0.6000	0.6000
T6	31	1/2	220.00 - 240.00	0.6000	0.6000
T6	32	LC78-50JA-A7	220.00 - 240.00	0.6000	0.6000
T6	33	1/2	220.00 - 240.00	0.6000	0.6000
T6	35	LC78-50JA-A7	220.00 - 240.00	0.6000	0.6000
T6	36	LC78-50JA-A7	220.00 - 240.00	0.6000	0.6000
T7	2	1 5/8	200.00 - 220.00	0.6000	0.6000
T7	3	1 5/8" Hybriflex	200.00 - 220.00	0.6000	0.6000
T7	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	200.00 - 220.00	0.6000	0.6000
T7	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	200.00 - 220.00	0.6000	0.6000
T7	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	200.00 - 220.00	0.6000	0.6000
T7	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	200.00 - 220.00	0.6000	0.6000
T7	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	200.00 - 220.00	0.6000	0.6000
T7	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	200.00 - 220.00	0.6000	0.6000
T7	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	200.00 - 220.00	0.6000	0.6000
T7	22	LDF4-50A (1/2 FOAM)	200.00 - 220.00	0.6000	0.6000
T7	23	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T7	25	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T7	26	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T7	28	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T7	29	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T7	30	1/2	200.00 - 220.00	0.6000	0.6000
T7	31	1/2	200.00 - 220.00	0.6000	0.6000
T7	32	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T7	33	1/2	200.00 - 220.00	0.6000	0.6000
T7	35	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T7	36	LC78-50JA-A7	200.00 - 220.00	0.6000	0.6000
T8	1	1 5/8	180.00 - 200.00	0.6000	0.6000
T8	2	1 5/8	180.00 - 200.00	0.6000	0.6000
T8	3	1 5/8" Hybriflex	180.00 - 200.00	0.6000	0.6000

Job	320' Rohn SSMW	Page	17 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T8	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	180.00 - 200.00	0.6000	0.6000
T8	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	180.00 - 200.00	0.6000	0.6000
T8	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	180.00 - 200.00	0.6000	0.6000
T8	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	180.00 - 200.00	0.6000	0.6000
T8	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	180.00 - 200.00	0.6000	0.6000
T8	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	180.00 - 200.00	0.6000	0.6000
T8	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	180.00 - 200.00	0.6000	0.6000
T8	22	LDF4-50A (1/2 FOAM)	180.00 - 200.00	0.6000	0.6000
T8	23	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	25	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	26	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	28	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	29	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	30	1/2	180.00 - 200.00	0.6000	0.6000
T8	31	1/2	180.00 - 200.00	0.6000	0.6000
T8	32	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	33	1/2	180.00 - 200.00	0.6000	0.6000
T8	35	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	36	LC78-50JA-A7	180.00 - 200.00	0.6000	0.6000
T8	41	1-5/8" Fiber Optic CaBLE	180.00 - 200.00	0.6000	0.6000
T8	42	1/2	180.00 - 200.00	0.6000	0.6000
T9	1	1 5/8	170.00 - 180.00	0.6000	0.6000
T9	2	1 5/8	170.00 - 180.00	0.6000	0.6000
T9	3	1 5/8" Hybriflex	170.00 - 180.00	0.6000	0.6000
T9	4	LC78-50JA-A7	170.00 - 174.00	0.6000	0.6000
T9	5	LC78-50JA-A7	170.00 - 177.00	0.6000	0.6000
T9	6	LDF4-50A (1/2 FOAM)	170.00 - 174.00	0.6000	0.6000
T9	7	LC78-50JA-A7	170.00 - 176.00	0.6000	0.6000
T9	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	170.00 - 180.00	0.6000	0.6000
T9	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	170.00 - 180.00	0.6000	0.6000
T9	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	170.00 - 180.00	0.6000	0.6000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 18 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T9	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	170.00 - 180.00	0.6000	0.6000
T9	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	170.00 - 180.00	0.6000	0.6000
T9	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	170.00 - 180.00	0.6000	0.6000
T9	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	170.00 - 180.00	0.6000	0.6000
T9	22	LDF4-50A (1/2 FOAM)	170.00 - 180.00	0.6000	0.6000
T9	23	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	25	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	26	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	28	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	29	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	30	1/2	170.00 - 180.00	0.6000	0.6000
T9	31	1/2	170.00 - 180.00	0.6000	0.6000
T9	32	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	33	1/2	170.00 - 180.00	0.6000	0.6000
T9	35	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	36	LC78-50JA-A7	170.00 - 180.00	0.6000	0.6000
T9	41	1-5/8" Fiber Optic CaBLE	170.00 - 180.00	0.6000	0.6000
T9	42	1/2	170.00 - 180.00	0.6000	0.6000
T10	1	1 5/8	160.00 - 170.00	0.6000	0.6000
T10	2	1 5/8	160.00 - 170.00	0.6000	0.6000
T10	3	1 5/8" Hybriflex	160.00 - 170.00	0.6000	0.6000
T10	4	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	5	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	6	LDF4-50A (1/2 FOAM)	160.00 - 170.00	0.6000	0.6000
T10	7	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	160.00 - 170.00	0.6000	0.6000
T10	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	160.00 - 170.00	0.6000	0.6000
T10	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	160.00 - 170.00	0.6000	0.6000
T10	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	160.00 - 170.00	0.6000	0.6000
T10	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	160.00 - 170.00	0.6000	0.6000
T10	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	160.00 - 170.00	0.6000	0.6000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 19 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T10	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	160.00 - 170.00	0.6000	0.6000
T10	22	LDF4-50A (1/2 FOAM)	160.00 - 170.00	0.6000	0.6000
T10	23	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	25	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	26	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	28	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	29	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	30	1/2	160.00 - 170.00	0.6000	0.6000
T10	31	1/2	160.00 - 170.00	0.6000	0.6000
T10	32	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	33	1/2	160.00 - 170.00	0.6000	0.6000
T10	34	1/2	160.00 - 164.00	0.6000	0.6000
T10	35	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	36	LC78-50JA-A7	160.00 - 170.00	0.6000	0.6000
T10	41	1-5/8" Fiber Optic CaBLE	160.00 - 170.00	0.6000	0.6000
T10	42	1/2	160.00 - 170.00	0.6000	0.6000
T10	44	LCF78-50J (7/8 FOAM)	160.00 - 163.00	0.6000	0.6000
T11	1	1 5/8	140.00 - 160.00	0.6000	0.6000
T11	2	1 5/8	140.00 - 160.00	0.6000	0.6000
T11	3	1 5/8" Hybriflex	140.00 - 160.00	0.6000	0.6000
T11	4	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	5	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	6	LDF4-50A (1/2 FOAM)	140.00 - 160.00	0.6000	0.6000
T11	7	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	140.00 - 160.00	0.6000	0.6000
T11	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	140.00 - 160.00	0.6000	0.6000
T11	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	140.00 - 160.00	0.6000	0.6000
T11	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	140.00 - 160.00	0.6000	0.6000
T11	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	140.00 - 160.00	0.6000	0.6000
T11	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	140.00 - 160.00	0.6000	0.6000
T11	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	140.00 - 160.00	0.6000	0.6000

Job	320' Rohn SSMW	Page	20 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T11	22	LDF4-50A (1/2 FOAM)	140.00 - 160.00	0.6000	0.6000
T11	23	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	25	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	26	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	28	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	29	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	30	1/2	140.00 - 160.00	0.6000	0.6000
T11	31	1/2	140.00 - 160.00	0.6000	0.6000
T11	32	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	33	1/2	140.00 - 160.00	0.6000	0.6000
T11	34	1/2	140.00 - 160.00	0.6000	0.6000
T11	35	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	36	LC78-50JA-A7	140.00 - 160.00	0.6000	0.6000
T11	39	EW63	140.00 - 154.00	0.6000	0.6000
T11	41	1-5/8" Fiber Optic CaBLE	140.00 - 160.00	0.6000	0.6000
T11	42	1/2	140.00 - 160.00	0.6000	0.6000
T11	44	LCF78-50J (7/8 FOAM)	140.00 - 160.00	0.6000	0.6000
T11	45	LCF78-50J (7/8 FOAM)	140.00 - 145.00	0.6000	0.6000
T12	1	1 5/8	120.00 - 140.00	0.6000	0.6000
T12	2	1 5/8	120.00 - 140.00	0.6000	0.6000
T12	3	1 5/8" Hybriflex	120.00 - 140.00	0.6000	0.6000
T12	4	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	5	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	6	LDF4-50A (1/2 FOAM)	120.00 - 140.00	0.6000	0.6000
T12	7	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	8	LC78-50JA-A7	120.00 - 137.00	0.6000	0.6000
T12	9	LC78-50JA-A7	120.00 - 134.00	0.6000	0.6000
T12	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 140.00	0.6000	0.6000
T12	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 140.00	0.6000	0.6000
T12	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 140.00	0.6000	0.6000
T12	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 140.00	0.6000	0.6000

<i>Tower Section</i>	<i>Feed Line Record No.</i>	<i>Description</i>	<i>Feed Line Segment Elev.</i>	<i>K_a No Ice</i>	<i>K_a Ice</i>
T12	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 140.00	0.6000	0.6000
T12	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 140.00	0.6000	0.6000
T12	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	120.00 - 140.00	0.6000	0.6000
T12	22	LDF4-50A (1/2 FOAM)	120.00 - 140.00	0.6000	0.6000
T12	23	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	25	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	26	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	28	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	29	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	30	1/2	120.00 - 140.00	0.6000	0.6000
T12	31	1/2	120.00 - 140.00	0.6000	0.6000
T12	32	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	33	1/2	120.00 - 140.00	0.6000	0.6000
T12	34	1/2	120.00 - 140.00	0.6000	0.6000
T12	35	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	36	LC78-50JA-A7	120.00 - 140.00	0.6000	0.6000
T12	39	EW63	120.00 - 140.00	0.6000	0.6000
T12	41	1-5/8" Fiber Optic CaBLE	120.00 - 140.00	0.6000	0.6000
T12	42	1/2	120.00 - 140.00	0.6000	0.6000
T12	44	LCF78-50J (7/8 FOAM)	120.00 - 140.00	0.6000	0.6000
T12	45	LCF78-50J (7/8 FOAM)	120.00 - 140.00	0.6000	0.6000
T13	1	1 5/8	100.00 - 120.00	0.6000	0.6000
T13	2	1 5/8	100.00 - 120.00	0.6000	0.6000
T13	3	1 5/8" Hybriflex	100.00 - 120.00	0.6000	0.6000
T13	4	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	5	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	6	LDF4-50A (1/2 FOAM)	100.00 - 120.00	0.6000	0.6000
T13	7	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	8	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	9	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	0.6000	0.6000

Job	320' Rohn SSVMW	Page	22 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T13	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	0.6000	0.6000
T13	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	0.6000	0.6000
T13	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	0.6000	0.6000
T13	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	0.6000	0.6000
T13	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	0.6000	0.6000
T13	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	100.00 - 120.00	0.6000	0.6000
T13	22	LDF4-50A (1/2 FOAM)	100.00 - 120.00	0.6000	0.6000
T13	23	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	24	WE65	100.00 - 106.00	0.6000	0.6000
T13	25	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	26	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	27	WE108	100.00 - 113.00	0.6000	0.6000
T13	28	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	29	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	30	1/2	100.00 - 120.00	0.6000	0.6000
T13	31	1/2	100.00 - 120.00	0.6000	0.6000
T13	32	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	33	1/2	100.00 - 120.00	0.6000	0.6000
T13	34	1/2	100.00 - 120.00	0.6000	0.6000
T13	35	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	36	LC78-50JA-A7	100.00 - 120.00	0.6000	0.6000
T13	39	EW63	100.00 - 120.00	0.6000	0.6000
T13	41	1-5/8" Fiber Optic CaBLE	100.00 - 120.00	0.6000	0.6000
T13	42	1/2	100.00 - 120.00	0.6000	0.6000
T13	44	LCF78-50J (7/8 FOAM)	100.00 - 120.00	0.6000	0.6000
T13	45	LCF78-50J (7/8 FOAM)	100.00 - 120.00	0.6000	0.6000
T14	1	1 5/8	80.00 - 100.00	0.6000	0.6000
T14	2	1 5/8	80.00 - 100.00	0.6000	0.6000
T14	3	1 5/8" Hybriflex	80.00 - 100.00	0.6000	0.6000
T14	4	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	5	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	6	LDF4-50A (1/2 FOAM)	80.00 - 100.00	0.6000	0.6000
T14	7	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	8	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	9	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	12	LC78-50JA-A7	80.00 - 91.00	0.6000	0.6000

Job	320' Rohn SSMW	Page	23 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T14	13	LC78-50JA-A7	80.00 - 90.00	0.6000	0.6000
T14	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 100.00	0.6000	0.6000
T14	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 100.00	0.6000	0.6000
T14	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 100.00	0.6000	0.6000
T14	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 100.00	0.6000	0.6000
T14	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 100.00	0.6000	0.6000
T14	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 100.00	0.6000	0.6000
T14	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	80.00 - 100.00	0.6000	0.6000
T14	22	LDF4-50A (1/2 FOAM)	80.00 - 100.00	0.6000	0.6000
T14	23	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	24	WE65	80.00 - 100.00	0.6000	0.6000
T14	25	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	26	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	27	WE108	80.00 - 100.00	0.6000	0.6000
T14	28	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	29	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	30	1/2	80.00 - 100.00	0.6000	0.6000
T14	31	1/2	80.00 - 100.00	0.6000	0.6000
T14	32	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	33	1/2	80.00 - 100.00	0.6000	0.6000
T14	34	1/2	80.00 - 100.00	0.6000	0.6000
T14	35	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	36	LC78-50JA-A7	80.00 - 100.00	0.6000	0.6000
T14	39	EW63	80.00 - 100.00	0.6000	0.6000
T14	41	1-5/8" Fiber Optic CaBLE	80.00 - 100.00	0.6000	0.6000
T14	42	1/2	80.00 - 100.00	0.6000	0.6000
T14	44	LCF78-50J (7/8 FOAM)	80.00 - 100.00	0.6000	0.6000
T14	45	LCF78-50J (7/8 FOAM)	80.00 - 100.00	0.6000	0.6000
T15	1	1 5/8	60.00 - 80.00	0.6000	0.6000
T15	2	1 5/8	60.00 - 80.00	0.6000	0.6000
T15	3	1 5/8" Hybriflex	60.00 - 80.00	0.6000	0.6000
T15	4	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	5	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	6	LDF4-50A (1/2 FOAM)	60.00 - 80.00	0.6000	0.6000
T15	7	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	8	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	9	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	12	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	13	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	0.6000	0.6000
T15	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	0.6000	0.6000
T15	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	0.6000	0.6000
T15	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	0.6000	0.6000
T15	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	0.6000	0.6000
T15	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	0.6000	0.6000
T15	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	60.00 - 80.00	0.6000	0.6000
T15	22	LDF4-50A (1/2 FOAM)	60.00 - 80.00	0.6000	0.6000
T15	23	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000

Job	320' Rohn SSMW	Page	24 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T15	24	WE65	60.00 - 80.00	0.6000	0.6000
T15	25	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	26	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	27	WE108	60.00 - 80.00	0.6000	0.6000
T15	28	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	29	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	30	1/2	60.00 - 80.00	0.6000	0.6000
T15	31	1/2	60.00 - 80.00	0.6000	0.6000
T15	32	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	33	1/2	60.00 - 80.00	0.6000	0.6000
T15	34	1/2	60.00 - 80.00	0.6000	0.6000
T15	35	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	36	LC78-50JA-A7	60.00 - 80.00	0.6000	0.6000
T15	39	EW63	60.00 - 80.00	0.6000	0.6000
T15	41	1-5/8" Fiber Optic CaBLE	60.00 - 80.00	0.6000	0.6000
T15	42	1/2	60.00 - 80.00	0.6000	0.6000
T15	44	LCF78-50J (7/8 FOAM)	60.00 - 80.00	0.6000	0.6000
T15	45	LCF78-50J (7/8 FOAM)	60.00 - 80.00	0.6000	0.6000
T16	1	1 5/8	30.00 - 60.00	0.6000	0.6000
T16	2	1 5/8	30.00 - 60.00	0.6000	0.6000
T16	3	1 5/8" Hybriflex	30.00 - 60.00	0.6000	0.6000
T16	4	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	5	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	6	LDF4-50A (1/2 FOAM)	30.00 - 60.00	0.6000	0.6000
T16	7	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	8	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	9	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	12	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	13	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 60.00	0.6000	0.6000
T16	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 60.00	0.6000	0.6000
T16	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 60.00	0.6000	0.6000
T16	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 60.00	0.6000	0.6000
T16	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 60.00	0.6000	0.6000
T16	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 60.00	0.6000	0.6000
T16	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	30.00 - 60.00	0.6000	0.6000
T16	22	LDF4-50A (1/2 FOAM)	30.00 - 60.00	0.6000	0.6000
T16	23	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	24	WE65	30.00 - 60.00	0.6000	0.6000
T16	25	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	26	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	27	WE108	30.00 - 60.00	0.6000	0.6000
T16	28	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	29	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	30	1/2	30.00 - 60.00	0.6000	0.6000
T16	31	1/2	30.00 - 60.00	0.6000	0.6000
T16	32	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	33	1/2	30.00 - 60.00	0.6000	0.6000
T16	34	1/2	30.00 - 60.00	0.6000	0.6000
T16	35	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	36	LC78-50JA-A7	30.00 - 60.00	0.6000	0.6000
T16	39	EW63	30.00 - 60.00	0.6000	0.6000
T16	41	1-5/8" Fiber Optic CaBLE	30.00 - 60.00	0.6000	0.6000
T16	42	1/2	30.00 - 60.00	0.6000	0.6000
T16	44	LCF78-50J (7/8 FOAM)	30.00 - 60.00	0.6000	0.6000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 25 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T16	45	LCF78-50J (7/8 FOAM)	30.00 - 60.00	0.6000	0.6000
T17	1	1 5/8	5.00 - 30.00	0.6000	0.6000
T17	2	1 5/8	5.00 - 30.00	0.6000	0.6000
T17	3	1 5/8" Hybriflex	5.00 - 30.00	0.6000	0.6000
T17	4	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	5	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	6	LDF4-50A (1/2 FOAM)	5.00 - 30.00	0.6000	0.6000
T17	7	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	8	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	9	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	12	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	13	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	14	AVA7-50 (1-5/8 LOW DENS. FOAM)	5.00 - 30.00	0.6000	0.6000
T17	15	AVA7-50 (1-5/8 LOW DENS. FOAM)	5.00 - 30.00	0.6000	0.6000
T17	16	AVA7-50 (1-5/8 LOW DENS. FOAM)	5.00 - 30.00	0.6000	0.6000
T17	18	AVA7-50 (1-5/8 LOW DENS. FOAM)	5.00 - 30.00	0.6000	0.6000
T17	19	AVA7-50 (1-5/8 LOW DENS. FOAM)	5.00 - 30.00	0.6000	0.6000
T17	20	AVA7-50 (1-5/8 LOW DENS. FOAM)	5.00 - 30.00	0.6000	0.6000
T17	21	AVA7-50 (1-5/8 LOW DENS. FOAM)	5.00 - 30.00	0.6000	0.6000
T17	22	LDF4-50A (1/2 FOAM)	5.00 - 30.00	0.6000	0.6000
T17	23	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	24	WE65	5.00 - 30.00	0.6000	0.6000
T17	25	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	26	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	27	WE108	5.00 - 30.00	0.6000	0.6000
T17	28	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	29	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	30	1/2	5.00 - 30.00	0.6000	0.6000
T17	31	1/2	5.00 - 30.00	0.6000	0.6000
T17	32	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	33	1/2	5.00 - 30.00	0.6000	0.6000
T17	34	1/2	5.00 - 30.00	0.6000	0.6000
T17	35	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	36	LC78-50JA-A7	5.00 - 30.00	0.6000	0.6000
T17	39	EW63	5.00 - 30.00	0.6000	0.6000
T17	41	1-5/8" Fiber Optic CaBLE	5.00 - 30.00	0.6000	0.6000
T17	42	1/2	5.00 - 30.00	0.6000	0.6000
T17	44	LCF78-50J (7/8 FOAM)	5.00 - 30.00	0.6000	0.6000
T17	45	LCF78-50J (7/8 FOAM)	5.00 - 30.00	0.6000	0.6000

Discrete Tower Loads

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job		320' Rohn SSVMW		Page		26 of 95	
	Project		CSP Tower - Colchester, CT		Date		12:07:36 05/18/20	
	Client		VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"		Designed by		MCD	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft ²	ft ²	lb

* CSP Antenna Inventory -
via Eastern Communications

Climb/Mapping									
PD688S-4 (ECI-66)	C	From Leg	0.50	0.0000	94.00	No Ice	0.35	0.35	3.75
			0.00			1/2" Ice	0.63	0.63	4.88
			0.00			1" Ice	0.91	0.91	6.00
4'x4" Pipe Mount (ECI-66)	C	From Leg	0.00	0.0000	94.00	No Ice	1.03	1.03	44.00
			0.00			1/2" Ice	1.58	1.58	56.99
			0.00			1" Ice	1.84	1.84	73.03
Pirod 4' Side Mount Standoff (1) (ECI-62)	B	From Leg	0.00	0.0000	106.00	No Ice	2.72	2.72	50.00
			0.00			1/2" Ice	4.91	4.91	89.00
			0.00			1" Ice	7.10	7.10	128.00
PD458 (ECI-62)	B	From Leg	3.00	0.0000	106.00	No Ice	2.88	2.88	20.00
			0.00			1/2" Ice	4.34	4.34	46.22
			0.00			1" Ice	5.83	5.83	77.59
5'3"x4" Pipe Mount (ECI-63 (Dish Support))	A	From Leg	0.00	0.0000	107.00	No Ice	1.39	1.39	57.00
			0.00			1/2" Ice	2.21	2.21	73.81
			0.00			1" Ice	2.54	2.54	94.43
8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-63a (Dish Ice Shield))	A	From Leg	0.00	0.0000	115.00	No Ice	8.34	4.76	400.00
			0.00			1/2" Ice	11.01	6.71	756.25
			0.00			1" Ice	13.59	8.62	1103.65
3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-61a)	C	From Leg	0.00	0.0000	117.00	No Ice	8.34	4.76	400.00
			0.00			1/2" Ice	11.01	6.71	756.25
			0.00			1" Ice	13.59	8.62	1103.65
5'3"x4" Pipe Mount (ECI-61a (Dish Support))	C	From Leg	0.00	0.0000	112.00	No Ice	1.39	1.39	57.00
			0.00			1/2" Ice	2.21	2.21	73.81
			0.00			1" Ice	2.54	2.54	94.43
DB212-1 (ECI-59)	C	From Leg	6.00	0.0000	139.00	No Ice	4.40	4.40	31.00
			0.00			1/2" Ice	8.42	8.42	70.21
			0.00			1" Ice	12.45	12.45	134.11
4' Side Mount Standoff (ECI-60 & 59)	C	From Leg	0.00	0.0000	139.00	No Ice	6.50	6.50	100.00
			0.00			1/2" Ice	8.50	8.50	170.00
			0.00			1" Ice	10.50	10.50	240.00
PD156S (ECI-60)	C	From Leg	6.00	0.0000	139.00	No Ice	0.44	0.44	5.00
			0.00			1/2" Ice	0.79	0.79	6.50
			0.00			1" Ice	1.14	1.14	8.00
5'3"x4" Pipe Mount (ECI-58a (Dish Support))	C	From Leg	0.00	0.0000	154.00	No Ice	1.37	1.37	57.00
			0.00			1/2" Ice	2.21	2.21	73.81
			0.00			1" Ice	2.54	2.54	94.43
ANT450F6 (ECI-57)	A	From Leg	0.50	0.0000	153.00	No Ice	1.90	1.90	8.00
			0.00			1/2" Ice	2.73	2.73	22.34
			0.00			1" Ice	3.40	3.40	41.96
5'3"x4" Pipe Mount (ECI-57)	A	From Leg	0.00	0.0000	153.00	No Ice	1.37	1.37	57.00
			0.00			1/2" Ice	2.21	2.21	73.81
			0.00			1" Ice	2.54	2.54	94.43
L-810 Obstruction Lighting (1) (ECI-56)	A	From Leg	0.25	0.0000	164.00	No Ice	0.36	0.36	6.65
			0.00			1/2" Ice	0.52	0.52	12.44
			0.00			1" Ice	0.70	0.70	19.93
L-810 Obstruction Lighting (1) (ECI-54)	B	From Leg	0.25	0.0000	168.00	No Ice	0.36	0.36	6.65
			0.00			1/2" Ice	0.52	0.52	12.44
			0.00			1" Ice	0.70	0.70	19.93
L-810 Obstruction Lighting (1) (ECI-55)	C	From Leg	0.25	0.0000	165.00	No Ice	0.36	0.36	6.65
			0.00			1/2" Ice	0.52	0.52	12.44
			0.00			1" Ice	0.70	0.70	19.93
DB586-Y (inverted) (ECI-53)	B	From Leg	4.00	0.0000	175.00	No Ice	1.01	1.01	8.25
			0.00			1/2" Ice	1.28	1.28	16.59
			0.00			1" Ice	1.56	1.56	28.01

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	27 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	lb	
Pirod 4' Side Mount Standoff (1) (ECI-53,52,51)	B	From Leg	0.00	0.00	0.0000	176.00	No Ice 1/2" Ice 1" Ice	2.72 4.91 7.10	2.72 4.91 7.10	50.00 89.00 128.00
430-94C-09168-M-11048 TTA (ECI-52)	B	From Leg	2.00	0.00	0.0000	176.00	No Ice 1/2" Ice 1" Ice	1.63 1.81 1.99	0.95 1.09 1.24	30.00 37.44 52.22
DB586-Y (ECI-51)	B	From Leg	4.00	0.00	0.0000	177.00	No Ice 1/2" Ice 1" Ice	1.01 1.28 1.56	1.01 1.28 1.56	8.25 16.59 28.01
DB586-Y (ECI-50)	C	From Leg	3.00	0.00	0.0000	179.00	No Ice 1/2" Ice 1" Ice	1.01 1.28 1.56	1.01 1.28 1.56	8.25 16.59 28.01
Pirod 4' Side Mount Standoff (1) (ECI-50)	C	From Leg	0.00	0.00	0.0000	179.00	No Ice 1/2" Ice 1" Ice	2.72 4.91 7.10	2.72 4.91 7.10	50.00 89.00 128.00
531-70HD Exposed Dipole Antenna (ECI-15)	A	From Leg	6.00	0.00	0.0000	238.00	No Ice 1/2" Ice 1" Ice	5.91 7.68 9.47	5.91 7.68 9.47	50.00 79.03 125.80
6' Side Mount Standoff (ECI-15)	A	From Leg	0.00	0.00	0.0000	238.00	No Ice 1/2" Ice 1" Ice	6.50 8.50 10.50	6.50 8.50 10.50	100.00 170.00 240.00
PD1142-1 (ECI-14)	C	From Leg	6.00	0.00	0.0000	248.00	No Ice 1/2" Ice 1" Ice	1.32 3.21 5.12	1.32 3.21 5.12	10.00 23.85 49.42
6' Side Mount Standoff (ECI-14)	C	From Leg	0.00	0.00	0.0000	248.00	No Ice 1/2" Ice 1" Ice	6.50 8.50 10.50	6.50 8.50 10.50	100.00 170.00 240.00
SC479-HF1LDF(D00I-E6085)) (Inverted) (ECI-13)	B	From Leg	3.00	0.00	0.0000	245.00	No Ice 1/2" Ice 1" Ice	5.06 6.54 8.04	5.06 6.54 8.04	34.00 69.82 114.98
SC479-HF1LDF(D00I-E6085)) (Inverted) (ECI-12)	B	From Leg	3.00	0.00	0.0000	245.00	No Ice 1/2" Ice 1" Ice	5.06 6.54 8.04	5.06 6.54 8.04	34.00 69.82 114.98
Sabre T-Boom (1) (ECI-10,11,12,13)	B	From Leg	0.00	0.00	0.0000	246.00	No Ice 1/2" Ice 1" Ice	35.40 46.90 58.40	35.40 46.90 58.40	471.00 690.00 909.00
430-94C-09168-M-11048 TTA (ECI-11)	B	From Leg	2.00	0.00	0.0000	247.00	No Ice 1/2" Ice 1" Ice	1.63 1.81 1.99	0.95 1.09 1.24	30.00 37.44 52.22
SC479-HF1LDF (ECI-10)	B	From Leg	3.00	0.00	0.0000	251.00	No Ice 1/2" Ice 1" Ice	3.90 6.54 8.04	3.90 6.54 8.04	34.00 69.82 114.98
6' Side Mount Standoff (ECI-8)	B	From Leg	0.00	0.00	0.0000	260.00	No Ice 1/2" Ice 1" Ice	6.50 8.50 10.50	6.50 8.50 10.50	100.00 170.00 240.00
PD440-2 (ECI-8)	B	From Leg	6.00	0.00	0.0000	264.00	No Ice 1/2" Ice 1" Ice	1.38 2.48 3.59	1.38 2.48 3.59	19.00 24.70 30.40
SC479-HF1LDF(D00I-E6085)) (Inverted) (ECI-7)	C	From Leg	6.00	0.00	0.0000	283.00	No Ice 1/2" Ice 1" Ice	5.06 6.54 8.04	5.06 6.54 8.04	34.00 69.82 114.98
6' Side Mount Standoff (ECI-7)	C	From Leg	0.00	0.00	0.0000	284.00	No Ice 1/2" Ice 1" Ice	6.50 8.50 10.50	6.50 8.50 10.50	100.00 170.00 240.00
DB809T3E-XC (ECI-6)	C	From Leg	6.00	0.00	0.0000	286.00	No Ice 1/2" Ice 1" Ice	3.77 5.70 7.17	3.77 5.70 7.17	39.00 69.70 109.50

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	28 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft ²	ft ²	lb
PD340-1 (ECI-5)	A	From Leg	6.00	0.00	0.0000	290.00	No Ice 3.30	3.30	40.00
			0.00	0.00			1/2" Ice 5.94	5.94	52.00
			0.00	0.00			1" Ice 8.58	8.58	64.00
6' Side Mount Standoff (ECI-5)	A	From Leg	0.00	0.00	0.0000	290.00	No Ice 6.50	6.50	100.00
			0.00	0.00			1/2" Ice 8.50	8.50	170.00
			0.00	0.00			1" Ice 10.50	10.50	240.00
SC479-HF1LDF (ECI-4)	C	From Leg	6.00	0.00	0.0000	300.00	No Ice 3.82	3.82	34.00
			0.00	0.00			1/2" Ice 6.54	6.54	69.82
			0.00	0.00			1" Ice 8.04	8.04	114.98
6' Side Mount Standoff (ECI-4)	C	From Leg	0.00	0.00	0.0000	300.00	No Ice 6.50	6.50	100.00
			0.00	0.00			1/2" Ice 8.50	8.50	170.00
			0.00	0.00			1" Ice 10.50	10.50	240.00
ANT450F6 (ECI-3)	B	From Leg	5.00	0.00	0.0000	318.00	No Ice 1.90	1.90	8.00
			0.00	0.00			1/2" Ice 2.73	2.73	22.34
			0.00	0.00			1" Ice 3.40	3.40	41.96
4'x4" Pipe Mount (ECI-3)	B	From Leg	0.00	0.00	0.0000	318.00	No Ice 0.98	0.98	44.00
			0.00	0.00			1/2" Ice 1.58	1.58	56.99
			0.00	0.00			1" Ice 1.84	1.84	73.03
BA1012-0 (ECI-2)	A	From Leg	6.00	0.00	0.0000	320.00	No Ice 0.47	0.47	2.20
			0.00	0.00			1/2" Ice 0.96	0.96	6.61
			0.00	0.00			1" Ice 1.31	1.31	14.14
6' Side Mount Standoff (ECI-2)	A	From Leg	0.00	0.00	0.0000	320.00	No Ice 6.50	6.50	100.00
			0.00	0.00			1/2" Ice 8.50	8.50	170.00
			0.00	0.00			1" Ice 10.50	10.50	240.00
PD128-1 (ECI-1)	C	From Leg	6.00	0.00	0.0000	325.00	No Ice 1.00	1.00	13.00
			0.00	0.00			1/2" Ice 1.80	1.80	16.90
			0.00	0.00			1" Ice 2.60	2.60	20.80
6' Side Mount Standoff (ECI-1)	C	From Leg	0.00	0.00	0.0000	325.00	No Ice 6.50	6.50	100.00
			0.00	0.00			1/2" Ice 8.50	8.50	170.00
			0.00	0.00			1" Ice 10.50	10.50	240.00
Dual Lights (Beacon)	A	None			0.0000	327.00	No Ice 4.00	4.00	250.00
							1/2" Ice 4.80	4.80	400.00
							1" Ice 5.60	5.60	550.00
Lightning Rod 5/8x4' (Lightning Rod)	C	None			0.0000	329.00	No Ice 0.25	0.25	31.00
							1/2" Ice 0.66	0.66	33.82
							1" Ice 0.97	0.97	39.29
* VZW Proposed 12/07/2018									
Valmont VFA-10-U V-Frame (Verizon)	A	None			0.0000	232.00	No Ice 7.95	4.45	285.00
							1/2" Ice 8.33	4.74	343.57
							1" Ice 8.71	5.04	407.08
Valmont VFA-10-U V-Frame (Verizon)	B	None			0.0000	232.00	No Ice 7.95	4.45	285.00
							1/2" Ice 8.33	4.74	343.57
							1" Ice 8.71	5.04	407.08
Valmont VFA-10-U V-Frame (Verizon)	C	None			0.0000	232.00	No Ice 7.95	4.45	285.00
							1/2" Ice 8.33	4.74	343.57
							1" Ice 8.71	5.04	407.08
JAHH-65B-R3B Panel Antenna (Verizon-AWS)	A	From Leg	5.00	6.00	0.0000	232.00	No Ice 9.66	5.98	126.30
			0.00	0.00			1/2" Ice 10.22	6.44	184.38
			0.00	0.00			1" Ice 10.79	6.91	248.75
JAHH-65B-R3B Panel Antenna (Verizon-PCS)	A	From Leg	5.00	5.50	0.0000	232.00	No Ice 9.66	5.98	126.30
			0.00	0.00			1/2" Ice 10.22	6.44	184.38
			0.00	0.00			1" Ice 10.79	6.91	248.75
LNx-6512DS-VTM (Verizon-850)	A	From Leg	5.00	-3.00	0.0000	232.00	No Ice 5.61	3.30	30.00
			0.00	0.00			1/2" Ice 6.01	3.66	63.32
			0.00	0.00			1" Ice 6.41	4.04	102.51
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2))	A	From Leg	5.00	6.00	0.0000	232.00	No Ice 3.78	3.56	116.83
							1/2" Ice 4.84	4.62	175.06

Job	320' Rohn SSVMW	Page	29 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA}		Weight	
			Horz	Vert			Front	Side		
			ft	ft	°	ft	ft ²	ft ²	lb	
(Verizon-PCS/AWS)			0.00				1" Ice	5.64	5.41	240.44
RFV01U-D1A RRH Unit	A	From Leg	5.00		0.0000	232.00	No Ice	1.88	1.25	97.50
(Verizon RRH)			0.00				1/2" Ice	2.05	1.39	115.84
			0.00				1" Ice	2.22	1.54	136.97
RFV01U-D2A RRH Unit	A	From Leg	5.00		0.0000	232.00	No Ice	1.88	1.01	82.00
(Verizon RRH)			0.00				1/2" Ice	2.05	1.14	98.43
			0.00				1" Ice	2.22	1.28	117.53
DB-B1-6C-12AB-0Z /	A	From Leg	5.00		0.0000	232.00	No Ice	4.42	2.90	32.00
DC-3315-PF-48 Dist. Box			0.00				1/2" Ice	4.72	3.16	63.48
(Verizon)			0.00				1" Ice	5.02	3.43	98.72
JAHH-65B-R3B Panel	B	From Leg	5.00		0.0000	232.00	No Ice	9.66	5.98	126.30
Antenna			6.00				1/2" Ice	10.22	6.44	184.38
(Verizon-AWS)			0.00				1" Ice	10.79	6.91	248.75
JAHH-65B-R3B Panel	B	From Leg	5.00		0.0000	232.00	No Ice	9.66	5.98	126.30
Antenna			5.50				1/2" Ice	10.22	6.44	184.38
(Verizon-PCS)			0.00				1" Ice	10.79	6.91	248.75
LNx-6512DS-VTM	B	From Leg	5.00		0.0000	232.00	No Ice	5.61	3.30	30.00
(Verizon-850)			-3.00				1/2" Ice	6.01	3.66	63.32
			0.00				1" Ice	6.41	4.04	102.51
BSAMNT-SBS-2-2 (JAHH	B	From Leg	5.00		0.0000	232.00	No Ice	3.78	3.56	116.83
Antenna Bracket (for 2))			6.00				1/2" Ice	4.84	4.62	175.06
(Verizon-PCS/AWS)			0.00				1" Ice	5.64	5.41	240.44
RFV01U-D1A RRH Unit	B	From Leg	5.00		0.0000	232.00	No Ice	1.88	1.25	97.50
(Verizon RRH)			0.00				1/2" Ice	2.05	1.39	115.84
			0.00				1" Ice	2.22	1.54	136.97
RFV01U-D2A RRH Unit	B	From Leg	5.00		0.0000	232.00	No Ice	1.88	1.01	82.00
(Verizon RRH)			0.00				1/2" Ice	2.05	1.14	98.43
			0.00				1" Ice	2.22	1.28	117.53
DB-B1-6C-12AB-0Z /	B	From Leg	5.00		0.0000	232.00	No Ice	4.42	2.90	32.00
DC-3315-PF-48 Dist. Box			0.00				1/2" Ice	4.72	3.16	63.48
(Verizon)			0.00				1" Ice	5.02	3.43	98.72
JAHH-65B-R3B Panel	C	From Leg	5.00		0.0000	232.00	No Ice	9.66	5.98	126.30
Antenna			6.00				1/2" Ice	10.22	6.44	184.38
(Verizon-AWS)			0.00				1" Ice	10.79	6.91	248.75
JAHH-65B-R3B Panel	C	From Leg	5.00		0.0000	232.00	No Ice	9.66	5.98	126.30
Antenna			5.50				1/2" Ice	10.22	6.44	184.38
(Verizon-PCS)			0.00				1" Ice	10.79	6.91	248.75
LNx-6512DS-VTM	C	From Leg	5.00		0.0000	232.00	No Ice	5.61	3.30	30.00
(Verizon-850)			-3.00				1/2" Ice	6.01	3.66	63.32
			0.00				1" Ice	6.41	4.04	102.51
BSAMNT-SBS-2-2 (JAHH	C	From Leg	5.00		0.0000	232.00	No Ice	3.78	3.56	116.83
Antenna Bracket (for 2))			6.00				1/2" Ice	4.84	4.62	175.06
(Verizon-PCS/AWS)			0.00				1" Ice	5.64	5.41	240.44
RFV01U-D1A RRH Unit	C	From Leg	5.00		0.0000	232.00	No Ice	1.88	1.25	97.50
(Verizon RRH)			0.00				1/2" Ice	2.05	1.39	115.84
			0.00				1" Ice	2.22	1.54	136.97
RFV01U-D2A RRH Unit	C	From Leg	5.00		0.0000	232.00	No Ice	1.88	1.01	82.00
(Verizon RRH)			0.00				1/2" Ice	2.05	1.14	98.43
			0.00				1" Ice	2.22	1.28	117.53
CBC78T-DS-43-2X Diplexer	A	From Leg	5.00		0.0000	232.00	No Ice	0.37	0.51	22.00
(Verizon)			0.00				1/2" Ice	0.45	0.60	28.34
			0.00				1" Ice	0.53	0.70	36.37
CBC78T-DS-43-2X Diplexer	B	From Leg	5.00		0.0000	232.00	No Ice	0.37	0.51	22.00
(Verizon)			0.00				1/2" Ice	0.45	0.60	28.34
			0.00				1" Ice	0.53	0.70	36.37
CBC78T-DS-43-2X Diplexer	C	From Leg	5.00		0.0000	232.00	No Ice	0.37	0.51	22.00
(Verizon)			0.00				1/2" Ice	0.45	0.60	28.34

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	30 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight lb
			Horz Lateral ft	Vert ft					
				0.00			1" Ice 0.53	0.70	36.37
* VZW Proposed 12/07/2018									
*** EMP-005 AT&T									
Inventory 08/2019 Updates									
PiROD 12' Lightweight	A	None			0.0000	200.00	No Ice 10.20	10.20	253.00
T-Frame							1/2" Ice 16.20	16.20	355.00
(AT&T)							1" Ice 22.20	22.20	457.00
PiROD 12' Lightweight	B	None			0.0000	200.00	No Ice 10.20	10.20	253.00
T-Frame							1/2" Ice 16.20	16.20	355.00
(AT&T)							1" Ice 22.20	22.20	457.00
PiROD 12' Lightweight	C	None			0.0000	200.00	No Ice 10.20	10.20	253.00
T-Frame							1/2" Ice 16.20	16.20	355.00
(AT&T)							1" Ice 22.20	22.20	457.00
7770.00	A	From Leg	3.00		0.0000	200.00	No Ice 10.03	5.60	20.00
(AT&T)			-6.00				1/2" Ice 10.61	6.15	70.47
			0.00				1" Ice 11.20	6.71	130.07
HPA-65R-BUU-H8 Panel	A	From Leg	3.00		0.0000	200.00	No Ice 12.99	7.48	68.00
(AT&T)			6.00				1/2" Ice 13.69	8.06	140.41
			0.00				1" Ice 14.40	8.64	220.44
RRUS-32	A	From Leg	3.00		0.0000	200.00	No Ice 3.20	1.85	60.00
(AT&T)			6.00				1/2" Ice 3.46	2.08	81.11
			1.50				1" Ice 3.73	2.31	105.42
RRUS-11	A	From Leg	3.00		0.0000	200.00	No Ice 2.99	1.25	50.00
(AT&T)			6.00				1/2" Ice 3.23	1.41	69.57
			-1.50				1" Ice 3.47	1.59	92.08
7770.00	B	From Leg	3.00		0.0000	200.00	No Ice 10.03	5.60	20.00
(AT&T)			-6.00				1/2" Ice 10.61	6.15	70.47
			0.00				1" Ice 11.20	6.71	130.07
HPA-65R-BUU-H8 Panel	B	From Leg	3.00		0.0000	200.00	No Ice 12.99	7.48	68.00
(AT&T)			6.00				1/2" Ice 13.69	8.06	140.41
			0.00				1" Ice 14.40	8.64	220.44
RRUS-32	B	From Leg	3.00		0.0000	200.00	No Ice 3.20	1.85	60.00
(AT&T)			6.00				1/2" Ice 3.46	2.08	81.11
			1.50				1" Ice 3.73	2.31	105.42
RRUS-11	B	From Leg	3.00		0.0000	200.00	No Ice 2.99	1.25	50.00
(AT&T)			6.00				1/2" Ice 3.23	1.41	69.57
			-1.50				1" Ice 3.47	1.59	92.08
7770.00	C	From Leg	3.00		0.0000	200.00	No Ice 10.03	5.60	20.00
(AT&T)			-6.00				1/2" Ice 10.61	6.15	70.47
			0.00				1" Ice 11.20	6.71	130.07
HPA-65R-BUU-H6 Panel	C	From Leg	3.00		0.0000	200.00	No Ice 10.12	5.49	48.00
(AT&T)			6.00				1/2" Ice 10.69	5.94	105.33
			0.00				1" Ice 11.26	6.41	168.95
RRUS-32	B	From Leg	3.00		0.0000	200.00	No Ice 3.20	1.85	60.00
(AT&T)			6.00				1/2" Ice 3.46	2.08	81.11
			1.50				1" Ice 3.73	2.31	105.42
RRUS-11	B	From Leg	3.00		0.0000	200.00	No Ice 2.99	1.25	50.00
(AT&T)			6.00				1/2" Ice 3.23	1.41	69.57
			-1.50				1" Ice 3.47	1.59	92.08
DC6-48-60-0-8C Squid /	C	None			0.0000	200.00	No Ice 1.79	1.79	27.00
Surge Arrestor							1/2" Ice 2.02	2.02	47.39
(AT&T)							1" Ice 2.27	2.27	70.57
STK-U Stiffener Side Arm	A	None			0.0000	200.00	No Ice 0.07	4.01	63.79
Attachment							1/2" Ice 0.11	5.00	95.84
(AT&T)							1" Ice 0.16	6.01	138.17
STK-U Stiffener Side Arm	B	None			0.0000	200.00	No Ice 0.07	4.01	63.79
Attachment							1/2" Ice 0.11	5.00	95.84

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	31 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
			ft	ft	°	ft	ft ²	ft ²	lb
(AT&T)									
STK-U Stiffener Side Arm Attachment	C	None			0.0000	200.00	1" Ice 0.16 No Ice 0.07 1/2" Ice 0.11	6.01 4.01 5.00	138.17 63.79 95.84
(AT&T)									
STK-U Stiffener Side Arm Attachment	A	None			0.0000	200.00	1" Ice 0.16 No Ice 0.07 1/2" Ice 0.11	6.01 4.01 5.00	138.17 63.79 95.84
(AT&T)									
STK-U Stiffener Side Arm Attachment	B	None			0.0000	200.00	1" Ice 0.16 No Ice 0.07 1/2" Ice 0.11	6.01 4.01 5.00	138.17 63.79 95.84
(AT&T)									
STK-U Stiffener Side Arm Attachment	C	None			0.0000	200.00	1" Ice 0.16 No Ice 0.07 1/2" Ice 0.11	6.01 4.01 5.00	138.17 63.79 95.84
(AT&T)									
STK-U Stiffener Side Arm Attachment							1" Ice 0.16	6.01	138.17
*** EMP-005 AT&T Inventory 08/2019 Updates									
* Eversource Proposed									
Telewave ANT220F2 - Omni Antenna	C	From Leg	4.00		0.0000	163.00	No Ice 1.03 1/2" Ice 1.29 1" Ice 1.56	1.03 1.29 1.56	14.00 22.80 34.62
(Eversource (Proposed))			0.00				1" Ice 1.56	1.56	34.62
Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	C	From Leg	0.00		0.0000	160.00	No Ice 2.48 1/2" Ice 3.25 1" Ice 4.03	5.14 6.91 8.67	165.00 318.00 474.00
(Eversource (Proposed))			0.00				1" Ice 4.03	8.67	474.00
Telewave ANT220F2 - Omni Antenna	C	From Leg	4.00		0.0000	145.00	No Ice 1.03 1/2" Ice 1.29 1" Ice 1.56	1.03 1.29 1.56	14.00 22.80 34.62
(Eversource (Proposed))			0.00				1" Ice 1.56	1.56	34.62
Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	C	From Leg	0.00		0.0000	142.00	No Ice 2.48 1/2" Ice 3.25 1" Ice 4.03	5.14 6.91 8.67	165.00 318.00 474.00
(Eversource (Proposed))			0.00				1" Ice 4.03	8.67	474.00

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight
				Horz Lateral	Vert						
			ft	ft	°	°	ft	ft	ft ²	lb	
* CSP Inventory from HighTower Solutions											
Climb											
PA8-65 (ECI-63)	A	Paraboloid w/Shroud (HP)	From Leg	0.50		Worst		107.00	8.00	No Ice 50.27 1/2" Ice 51.29 1" Ice 52.31	285.00 548.30 811.60
Andrew 2' w/Radome (ECI-61)	C	Paraboloid w/Radome	From Leg	0.50		Worst		112.00	2.00	No Ice 3.14 1/2" Ice 3.41 1" Ice 3.68	70.00 282.00 494.00
* CSP Proposed											
Commscope											
PAR6-59W-PXA/A (ECI-58)	C	Paraboloid w/Radome	From Leg	0.50		Worst		154.00	6.00	No Ice 28.27 1/2" Ice 29.07 1" Ice 29.86	310.00 460.00 610.00

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 32 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

222-H Verification Constants

Constant	Value
K _d	0.85
Ice Thickness Importance Factor	1.15
Z _r	900
α	9.5
K _{zmin}	0.85
K _c	1
K _i	0.53
f	2
K _e	1

222-H Section Verification ArRr By Element

Section Elevation	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r	A _r w/Ice	A _r R _r	A _r R _r w/Ice
ft								ft ²	ft ²	ft ²	ft ²
T1 320.00-304.00	1	ROHN 5 EH	82.308	44.611	C	0.209	0.397	7.417	11.257	3.346	7.145
	1	ROHN 5 EH	82.308	44.611	A	0.209	0.397	7.417	11.257	3.346	7.145
	2	ROHN 5 EH	82.308	44.611	C	0.209	0.397	7.417	11.257	3.346	7.145
	2	ROHN 5 EH	82.308	44.611	B	0.209	0.397	7.417	11.257	3.346	7.145
	3	ROHN 5 EH	82.308	44.611	B	0.209	0.397	7.417	11.257	3.346	7.145
	3	ROHN 5 EH	82.308	44.611	A	0.209	0.397	7.417	11.257	3.346	7.145
								Sum:	14.835	22.513	6.692
								14.835	22.513	6.692	14.291
								14.835	22.513	6.692	14.291
T2 304.00-300.00	31	ROHN 5 EH	82.028	44.41	C	0.201	0.376	1.854	2.811	0.828	1.760
	31	ROHN 5 EH	82.028	44.41	A	0.201	0.376	1.854	2.811	0.828	1.760
	32	ROHN 5 EH	82.028	44.41	C	0.201	0.376	1.854	2.811	0.828	1.760
	32	ROHN 5 EH	82.028	44.41	B	0.201	0.376	1.854	2.811	0.828	1.760
	33	ROHN 5 EH	82.028	44.41	B	0.201	0.376	1.854	2.811	0.828	1.760
	33	ROHN 5 EH	82.028	44.41	A	0.201	0.376	1.854	2.811	0.828	1.760
								Sum:	3.709	5.622	1.656
								3.709	5.622	1.656	3.520
								3.709	5.622	1.656	3.520
T3 300.00-280.00	40	ROHN 6 EH	97.274	49.73	C	0.207	0.361	11.061	15.833	4.976	9.821
	40	ROHN 6 EH	97.274	49.73	A	0.207	0.361	11.061	15.833	4.976	9.821
	41	ROHN 6 EH	97.274	49.73	C	0.207	0.361	11.061	15.833	4.976	9.821
	41	ROHN 6 EH	97.274	49.73	B	0.207	0.361	11.061	15.833	4.976	9.821
	42	ROHN 6 EH	97.274	49.73	B	0.207	0.361	11.061	15.833	4.976	9.821
	42	ROHN 6 EH	97.274	49.73	A	0.207	0.361	11.061	15.833	4.976	9.821
								Sum:	22.122	31.667	9.951
								22.122	31.667	9.951	19.642
								22.122	31.667	9.951	19.642
T4 280.00-260.00					A			Sum:	0.000	0.000	0.000
					B				0.000	0.000	0.000
					C				0.000	0.000	0.000
T5 260.00-240.00					A			Sum:	0.000	0.000	0.000
					B				0.000	0.000	0.000
					C				0.000	0.000	0.000
T6 240.00-220.00					A			Sum:	0.000	0.000	0.000
					B				0.000	0.000	0.000
					C				0.000	0.000	0.000
T7				A			Sum:	0.000	0.000	0.000	

Job	320' Rohn SSVMW	Page	33 of 95
Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r	A _r w/Ice	A _r R _r	A _r R _r w/Ice	
ft								ft ²	ft ²	ft ²	ft ²	
220.00-200.00					B			0.000	0.000	0.000	0.000	
					C			0.000	0.000	0.000	0.000	
	T8				A		Sum:	0.000	0.000	0.000	0.000	
200.00-180.00					B			0.000	0.000	0.000	0.000	
					C			0.000	0.000	0.000	0.000	
	T9				A		Sum:	0.000	0.000	0.000	0.000	
180.00-170.00					B			0.000	0.000	0.000	0.000	
					C			0.000	0.000	0.000	0.000	
	T10				A		Sum:	0.000	0.000	0.000	0.000	
170.00-160.00					B			0.000	0.000	0.000	0.000	
					C			0.000	0.000	0.000	0.000	
	T11				A		Sum:	0.000	0.000	0.000	0.000	
160.00-140.00					B			0.000	0.000	0.000	0.000	
					C			0.000	0.000	0.000	0.000	
	T12				A		Sum:	0.000	0.000	0.000	0.000	
140.00-120.00					B			0.000	0.000	0.000	0.000	
					C			0.000	0.000	0.000	0.000	
	T13	214	ROHN 3 STD	47.3	29.584	C	0.131	0.181	7.130	12.487	3.797	7.135
120.00-100.00		215	ROHN 3 XXS	47.3	29.584	C	0.131	0.181	6.882	12.051	3.664	6.886
		216	ROHN 1.5 STD	25.677	21.861	C	0.131	0.181	0.930	2.218	0.526	1.267
		217	ROHN 2 STD	32.097	24.154	C	0.131	0.181	2.092	4.407	1.183	2.518
		218	ROHN 3 XXS	47.3	29.584	C	0.131	0.181	6.882	12.051	3.664	6.886
		219	ROHN 1.5 STD	25.677	21.861	C	0.131	0.181	0.930	2.218	0.526	1.267
		220	ROHN 2 STD	32.097	24.154	C	0.131	0.181	2.092	4.407	1.183	2.518
		221	ROHN 3 STD	47.3	29.584	B	0.131	0.181	7.130	12.487	3.797	7.135
		222	ROHN 3 XXS	47.3	29.584	B	0.131	0.181	6.882	12.051	3.664	6.886
		223	ROHN 1.5 STD	25.677	21.861	B	0.131	0.181	0.930	2.218	0.526	1.267
		224	ROHN 2 STD	32.097	24.154	B	0.131	0.181	2.092	4.407	1.183	2.518
		225	ROHN 3 XXS	47.3	29.584	B	0.131	0.181	6.882	12.051	3.664	6.886
		226	ROHN 1.5 STD	25.677	21.861	B	0.131	0.181	0.930	2.218	0.526	1.267
		227	ROHN 2 STD	32.097	24.154	B	0.131	0.181	2.092	4.407	1.183	2.518
		230	ROHN 3 STD	47.3	29.584	A	0.131	0.181	7.130	12.487	3.797	7.135
		231	ROHN 3 XXS	47.3	29.584	A	0.131	0.181	6.882	12.051	3.664	6.886
		232	ROHN 1.5 STD	25.677	21.861	A	0.131	0.181	0.930	2.218	0.526	1.267
		233	ROHN 2 STD	32.097	24.154	A	0.131	0.181	2.092	4.407	1.183	2.518
		234	ROHN 3 XXS	47.3	29.584	A	0.131	0.181	6.882	12.051	3.664	6.886
		235	ROHN 1.5 STD	25.677	21.861	A	0.131	0.181	0.930	2.218	0.526	1.267
		236	ROHN 2 STD	32.097	24.154	A	0.131	0.181	2.092	4.407	1.183	2.518
					A		Sum:	26.937	49.840	14.546	28.479	
					B			26.937	49.840	14.546	28.479	
					C			26.937	49.840	14.546	28.479	
	T14	247	ROHN 3 EH	47.038	29.305	C	0.122	0.17	7.883	13.751	4.196	7.837
100.00-80.00		248	ROHN 3 XXS	47.038	29.305	C	0.122	0.17	7.109	12.401	3.784	7.068
		249	P1.5x.145	25.535	21.625	C	0.122	0.17	1.033	2.448	0.584	1.395
		250	ROHN 2 EH	31.986	23.929	C	0.122	0.17	2.178	4.563	1.232	2.601
		251	ROHN 3 XXS	47.038	29.305	C	0.122	0.17	7.109	12.401	3.784	7.068
		252	P1.5x.145	25.535	21.625	C	0.122	0.17	1.033	2.448	0.584	1.395
		253	ROHN 2 EH	31.986	23.929	C	0.122	0.17	2.178	4.563	1.232	2.601
		254	ROHN 3 EH	47.038	29.305	B	0.122	0.17	7.883	13.751	4.196	7.837
		255	ROHN 3 XXS	47.038	29.305	B	0.122	0.17	7.109	12.401	3.784	7.068
		256	P1.5x.145	25.535	21.625	B	0.122	0.17	1.033	2.448	0.584	1.395
		257	ROHN 2 EH	31.986	23.929	B	0.122	0.17	2.178	4.563	1.232	2.601
		258	ROHN 3 XXS	47.038	29.305	B	0.122	0.17	7.109	12.401	3.784	7.068
		259	P1.5x.145	25.535	21.625	B	0.122	0.17	1.033	2.448	0.584	1.395
		260	ROHN 2 EH	31.986	23.929	B	0.122	0.17	2.178	4.563	1.232	2.601
		263	ROHN 3 EH	47.038	29.305	A	0.122	0.17	7.883	13.751	4.196	7.837
		264	ROHN 3 XXS	47.038	29.305	A	0.122	0.17	7.109	12.401	3.784	7.068
		265	P1.5x.145	25.535	21.625	A	0.122	0.17	1.033	2.448	0.584	1.395

<i>tnxTower</i> AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 34 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section Elevation <i>ft</i>	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r <i>ft²</i>	A _r w/Ice <i>ft²</i>	A _r R _r <i>ft²</i>	A _r R _r w/Ice <i>ft²</i>	
T15 80.00-60.00	266	ROHN 2 EH	31.986	23.929	A	0.122	0.17	2.178	4.563	1.232	2.601	
	267	ROHN 3 XXS	47.038	29.305	A	0.122	0.17	7.109	12.401	3.784	7.068	
	268	P1.5x.145	25.535	21.625	A	0.122	0.17	1.033	2.448	0.584	1.395	
	269	ROHN 2 EH	31.986	23.929	A	0.122	0.17	2.178	4.563	1.232	2.601	
					A		Sum:	28.523	52.577	15.395	29.965	
					B			28.523	52.577	15.395	29.965	
					C			28.523	52.577	15.395	29.965	
	280	ROHN 3 XXS	47.101	29.273	C	0.127	0.173	8.612	14.987	4.588	8.546	
	281	ROHN 3 XXS	47.101	29.273	C	0.127	0.173	7.336	12.766	3.908	7.280	
	282	ROHN 2 STD	31.961	23.866	C	0.127	0.173	1.402	2.932	0.793	1.672	
	283	ROHN 2 EH	32.029	23.89	C	0.127	0.173	2.253	4.705	1.274	2.683	
	284	ROHN 3 XXS	47.101	29.273	C	0.127	0.173	7.336	12.766	3.908	7.280	
	285	ROHN 2 STD	31.961	23.866	C	0.127	0.173	1.402	2.932	0.793	1.672	
	286	ROHN 2 EH	32.029	23.89	C	0.127	0.173	2.253	4.705	1.274	2.683	
	287	ROHN 3 XXS	47.101	29.273	B	0.127	0.173	8.612	14.987	4.588	8.546	
	288	ROHN 3 XXS	47.101	29.273	B	0.127	0.173	7.336	12.766	3.908	7.280	
	289	ROHN 2 STD	31.961	23.866	B	0.127	0.173	1.402	2.932	0.793	1.672	
	290	ROHN 2 EH	32.029	23.89	B	0.127	0.173	2.253	4.705	1.274	2.683	
	291	ROHN 3 XXS	47.101	29.273	B	0.127	0.173	7.336	12.766	3.908	7.280	
	292	ROHN 2 STD	31.961	23.866	B	0.127	0.173	1.402	2.932	0.793	1.672	
	293	ROHN 2 EH	32.029	23.89	B	0.127	0.173	2.253	4.705	1.274	2.683	
	296	ROHN 3 XXS	47.101	29.273	A	0.127	0.173	8.612	14.987	4.588	8.546	
	297	ROHN 3 XXS	47.101	29.273	A	0.127	0.173	7.336	12.766	3.908	7.280	
	298	ROHN 2 STD	31.961	23.866	A	0.127	0.173	1.402	2.932	0.793	1.672	
	299	ROHN 2 EH	32.029	23.89	A	0.127	0.173	2.253	4.705	1.274	2.683	
	300	ROHN 3 XXS	47.101	29.273	A	0.127	0.173	7.336	12.766	3.908	7.280	
	301	ROHN 2 STD	31.961	23.866	A	0.127	0.173	1.402	2.932	0.793	1.672	
	302	ROHN 2 EH	32.029	23.89	A	0.127	0.173	2.253	4.705	1.274	2.683	
					A		Sum:	30.595	55.793	16.540	31.817	
					B			30.595	55.793	16.540	31.817	
					C			30.595	55.793	16.540	31.817	
	T16 60.00-30.00	313	ROHN 3.5 EH	54.877	32.316	C	0.122	0.165	10.693	17.630	5.348	10.036
		314	ROHN 4 EH	61.736	34.766	C	0.122	0.165	12.823	20.219	6.052	11.509
315		ROHN 1.5 STD	26.067	22.026	C	0.122	0.165	0.790	1.870	0.447	1.065	
316		ROHN 2 XXS	32.583	24.354	C	0.122	0.165	2.081	4.356	1.176	2.479	
317		ROHN 2 EH	32.652	24.378	C	0.122	0.165	1.972	4.123	1.115	2.347	
318		ROHN 2.5 STD	39.443	26.804	C	0.122	0.165	3.288	6.256	1.853	3.561	
319		ROHN 4 EH	61.736	34.766	C	0.122	0.165	12.823	20.219	6.052	11.509	
320		ROHN 1.5 STD	26.067	22.026	C	0.122	0.165	0.790	1.870	0.447	1.065	
321		ROHN 2 XXS	32.583	24.354	C	0.122	0.165	2.081	4.356	1.176	2.479	
322		ROHN 2 EH	32.652	24.378	C	0.122	0.165	1.972	4.123	1.115	2.347	
323		ROHN 2.5 STD	39.443	26.804	C	0.122	0.165	3.288	6.256	1.853	3.561	
324		ROHN 3.5 EH	54.877	32.316	B	0.122	0.165	10.693	17.630	5.348	10.036	
325		ROHN 4 EH	61.736	34.766	B	0.122	0.165	12.823	20.219	6.052	11.509	
326		ROHN 1.5 STD	26.067	22.026	B	0.122	0.165	0.790	1.870	0.447	1.065	
327		ROHN 2 XXS	32.583	24.354	B	0.122	0.165	2.081	4.356	1.176	2.479	
328		ROHN 2 EH	32.652	24.378	B	0.122	0.165	1.972	4.123	1.115	2.347	
329		ROHN 2.5 STD	39.443	26.804	B	0.122	0.165	3.288	6.256	1.853	3.561	
330		ROHN 4 EH	61.736	34.766	B	0.122	0.165	12.823	20.219	6.052	11.509	
331		ROHN 1.5 STD	26.067	22.026	B	0.122	0.165	0.790	1.870	0.447	1.065	
332		ROHN 2 XXS	32.583	24.354	B	0.122	0.165	2.081	4.356	1.176	2.479	
333		ROHN 2 EH	32.652	24.378	B	0.122	0.165	1.972	4.123	1.115	2.347	
334		ROHN 2.5 STD	39.443	26.804	B	0.122	0.165	3.288	6.256	1.853	3.561	
339		ROHN 3.5 EH	54.877	32.316	A	0.122	0.165	10.693	17.630	5.348	10.036	
340		ROHN 4 EH	61.736	34.766	A	0.122	0.165	12.823	20.219	6.052	11.509	
341		ROHN 1.5 STD	26.067	22.026	A	0.122	0.165	0.790	1.870	0.447	1.065	
342		ROHN 2 XXS	32.583	24.354	A	0.122	0.165	2.081	4.356	1.176	2.479	
343		ROHN 2 EH	32.652	24.378	A	0.122	0.165	1.972	4.123	1.115	2.347	
344	ROHN 2.5 STD	39.443	26.804	A	0.122	0.165	3.288	6.256	1.853	3.561		
345	ROHN 4 EH	61.736	34.766	A	0.122	0.165	12.823	20.219	6.052	11.509		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 35 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section Elevation <i>ft</i>	Elem. Num.	Size	C	C w/Ice	F a c e	e	e w/Ice	A _r <i>ft²</i>	A _r w/Ice <i>ft²</i>	A _r R _r <i>ft²</i>	A _r R _r w/Ice <i>ft²</i>
T17 30.00-0.00	346	ROHN 1.5 STD	26.067	22.026	A	0.122	0.165	0.790	1.870	0.447	1.065
	347	ROHN 2 XXS	32.583	24.354	A	0.122	0.165	2.081	4.356	1.176	2.479
	348	ROHN 2 EH	32.652	24.378	A	0.122	0.165	1.972	4.123	1.115	2.347
	349	ROHN 2.5 STD	39.443	26.804	A	0.122	0.165	3.288	6.256	1.853	3.561
					A		Sum:	52.602	91.278	26.633	51.957
					B			52.602	91.278	26.633	51.957
					C			52.602	91.278	26.633	51.957
	364	ROHN 4 EH	64.741	36.51	C	0.117	0.158	13.402	21.161	6.136	12.028
	365	ROHN 4 EH	64.741	36.51	C	0.117	0.158	13.245	20.914	6.065	11.887
	366	P1.5x.145	27.335	23.151	C	0.117	0.158	0.887	2.103	0.501	1.196
	367	ROHN 2.5 EH	41.363	28.16	C	0.117	0.158	2.812	5.360	1.561	3.046
	368	ROHN 2.5 STD	41.363	28.16	C	0.117	0.158	2.470	4.708	1.371	2.676
	369	ROHN 2.5 STD	41.363	28.16	C	0.117	0.158	3.506	6.683	1.946	3.799
	370	ROHN 4 EH	64.741	36.51	C	0.117	0.158	13.245	20.914	6.065	11.887
	371	P1.5x.145	27.335	23.151	C	0.117	0.158	0.887	2.103	0.501	1.196
	372	ROHN 2.5 EH	41.363	28.16	C	0.117	0.158	2.812	5.360	1.561	3.046
	373	ROHN 2.5 STD	41.363	28.16	C	0.117	0.158	2.470	4.708	1.371	2.676
	374	ROHN 2.5 STD	41.363	28.16	C	0.117	0.158	3.506	6.683	1.946	3.799
	375	ROHN 4 EH	64.741	36.51	B	0.117	0.158	13.402	21.161	6.136	12.028
	376	ROHN 4 EH	64.741	36.51	B	0.117	0.158	13.245	20.914	6.065	11.887
	377	P1.5x.145	27.335	23.151	B	0.117	0.158	0.887	2.103	0.501	1.196
	378	ROHN 2.5 EH	41.363	28.16	B	0.117	0.158	2.812	5.360	1.561	3.046
	379	ROHN 2.5 STD	41.363	28.16	B	0.117	0.158	2.470	4.708	1.371	2.676
	380	ROHN 2.5 STD	41.363	28.16	B	0.117	0.158	3.506	6.683	1.946	3.799
	381	ROHN 4 EH	64.741	36.51	B	0.117	0.158	13.245	20.914	6.065	11.887
	382	P1.5x.145	27.335	23.151	B	0.117	0.158	0.887	2.103	0.501	1.196
	383	ROHN 2.5 EH	41.363	28.16	B	0.117	0.158	2.812	5.360	1.561	3.046
	384	ROHN 2.5 STD	41.363	28.16	B	0.117	0.158	2.470	4.708	1.371	2.676
	385	ROHN 2.5 STD	41.363	28.16	B	0.117	0.158	3.506	6.683	1.946	3.799
	390	ROHN 4 EH	64.741	36.51	A	0.117	0.158	13.402	21.161	6.136	12.028
	391	ROHN 4 EH	64.741	36.51	A	0.117	0.158	13.245	20.914	6.065	11.887
	392	P1.5x.145	27.335	23.151	A	0.117	0.158	0.887	2.103	0.501	1.196
	393	ROHN 2.5 EH	41.363	28.16	A	0.117	0.158	2.812	5.360	1.561	3.046
	394	ROHN 2.5 STD	41.363	28.16	A	0.117	0.158	2.470	4.708	1.371	2.676
	395	ROHN 2.5 STD	41.363	28.16	A	0.117	0.158	3.506	6.683	1.946	3.799
	396	ROHN 4 EH	64.741	36.51	A	0.117	0.158	13.245	20.914	6.065	11.887
	397	P1.5x.145	27.335	23.151	A	0.117	0.158	0.887	2.103	0.501	1.196
	398	ROHN 2.5 EH	41.363	28.16	A	0.117	0.158	2.812	5.360	1.561	3.046
	399	ROHN 2.5 STD	41.363	28.16	A	0.117	0.158	2.470	4.708	1.371	2.676
	400	ROHN 2.5 STD	41.363	28.16	A	0.117	0.158	3.506	6.683	1.946	3.799
				A		Sum:	59.240	100.698	29.025	57.236	
				B			59.240	100.698	29.025	57.236	
				C			59.240	100.698	29.025	57.236	

222-H Section Verification Tables - No Ice

Section Elevation <i>ft</i>	<i>z_{wind}</i> <i>ft</i>	<i>z_{ice}</i> <i>ft</i>	<i>K_z</i>	<i>K_h</i>	<i>K_{st}</i>	<i>t_z</i> <i>in</i>	<i>q_z</i> <i>psf</i>	<i>F a c e</i>	<i>e</i>	<i>A_rR_r</i> <i>ft²</i>
T1 320.00-304.00	312.00		1.608	11890.1	1		69	A	0.209	6.692
								B	0.209	6.692
								C	0.209	6.692

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 36 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section Elevation	z_{wind}	z_{ice}	K_z	K_h	K_{zt}	t_z	q_z	F a c e	e	$A_r R_r$
ft	ft	ft				in	psf			ft ²
T2 304.00-300.00	302.00		1.597	8801.76	1		68	A B C	0.201 0.201 0.201	1.656 1.656 1.656
T3 300.00-280.00	290.00		1.584	6135.24	1		68	A B C	0.207 0.207 0.207	9.951 9.951 9.951
T4 280.00-260.00	270.00		1.56	3362.03	1		67	A B C	0.237 0.237 0.237	0.000 0.000 0.000
T5 260.00-240.00	250.00		1.535	1842.35	1.001		66	A B C	0.219 0.219 0.219	0.000 0.000 0.000
T6 240.00-220.00	230.00		1.508	1009.58	1.001		64	A B C	0.223 0.223 0.223	0.000 0.000 0.000
T7 220.00-200.00	210.00		1.48	553.239	1.002		63	A B C	0.181 0.181 0.181	0.000 0.000 0.000
T8 200.00-180.00	190.00		1.449	303.168	1.003		62	A B C	0.187 0.187 0.187	0.000 0.000 0.000
T9 180.00-170.00	175.00		1.424	193.09	1.005		61	A B C	0.177 0.177 0.177	0.000 0.000 0.000
T10 170.00-160.00	165.00		1.406	142.937	1.007		60	A B C	0.171 0.171 0.171	0.000 0.000 0.000
T11 160.00-140.00	150.00		1.378	91.038	1.012		59	A B C	0.181 0.181 0.181	0.000 0.000 0.000
T12 140.00-120.00	130.00		1.337	49.888	1.021		58	A B C	0.173 0.173 0.173	0.000 0.000 0.000
T13 120.00-100.00	110.00		1.291	27.338	1.039		57	A B C	0.131 0.131 0.131	14.546 14.546 14.546
T14 100.00-80.00	90.00		1.238	14.981	1.072		57	A B C	0.122 0.122 0.122	15.395 15.395 15.395
T15 80.00-60.00	70.00		1.174	8.209	1.133		57	A B C	0.127 0.127 0.127	16.540 16.540 16.540
T16 60.00-30.00	45.00		1.07	3.87	1.293		59	A B C	0.122 0.122 0.122	26.633 26.633 26.633
T17 30.00-0.00	15.00		0.85	1.57	1.789		65	A B C	0.117 0.117 0.117	29.025 29.025 29.025

222-H Section Verification Tables - Ice

Section Elevation	z_{wind}	z_{ice}	K_z	K_h	K_{zt}	t_z	q_z	F a c e	e	$A_r R_r$
ft	ft	ft				in	psf			ft ²
T1 320.00-304.00	312.00	312.00	1.608	11890.1	1	1.4397	9	A B	0.397 0.397	24.226 24.226

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	37 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	z_{wind}	z_{ice}	K_z	K_h	K_{zt}	t_z	q_z	F_{ac}	e	A,R_r
ft	ft	ft				in	psf	e		ft ²
T2 304.00-300.00	302.00	302.00	1.597	8801.76	1	1.4350	9	C A B C	0.397 0.376 0.376 0.376	24.226 5.724 5.724 5.724
T3 300.00-280.00	290.00	290.00	1.584	6135.24	1	1.4293	9	A B C	0.361 0.361 0.361	30.809 30.809 30.809
T4 280.00-260.00	270.00	270.00	1.56	3362.03	1	1.4192	8	A B C	0.331 0.331 0.331	9.458 9.458 9.458
T5 260.00-240.00	250.00	250.00	1.535	1842.35	1.001	1.4084	8	A B C	0.307 0.307 0.307	10.777 10.777 10.777
T6 240.00-220.00	230.00	230.00	1.508	1009.58	1.001	1.3969	8	A B C	0.307 0.307 0.307	12.230 12.230 12.230
T7 220.00-200.00	210.00	210.00	1.48	553.239	1.002	1.3847	8	A B C	0.245 0.245 0.245	9.623 9.623 9.623
T8 200.00-180.00	190.00	190.00	1.449	303.168	1.003	1.3717	8	A B C	0.246 0.246 0.246	10.500 10.500 10.500
T9 180.00-170.00	175.00	175.00	1.424	193.09	1.005	1.3614	8	A B C	0.235 0.235 0.235	5.560 5.560 5.560
T10 170.00-160.00	165.00	165.00	1.406	142.937	1.007	1.3543	8	A B C	0.228 0.228 0.228	5.765 5.765 5.765
T11 160.00-140.00	150.00	150.00	1.378	91.038	1.012	1.3434	8	A B C	0.236 0.236 0.236	12.176 12.176 12.176
T12 140.00-120.00	130.00	130.00	1.337	49.888	1.021	1.3288	7	A B C	0.226 0.226 0.226	12.970 12.970 12.970
T13 120.00-100.00	110.00	110.00	1.291	27.338	1.039	1.3147	7	A B C	0.181 0.181 0.181	28.479 28.479 28.479
T14 100.00-80.00	90.00	90.00	1.238	14.981	1.072	1.3027	7	A B C	0.17 0.17 0.17	29.965 29.965 29.965
T15 80.00-60.00	70.00	70.00	1.174	8.209	1.133	1.2953	7	A B C	0.173 0.173 0.173	31.817 31.817 31.817
T16 60.00-30.00	45.00	45.00	1.07	3.87	1.293	1.2977	8	A B C	0.165 0.165 0.165	51.957 51.957 51.957
T17 30.00-0.00	15.00	15.00	0.85	1.57	1.789	1.3028	8	A B C	0.158 0.158 0.158	57.236 57.236 57.236

222-H Section Verification Tables - Service

Section Elevation	z_{wind}	z_{ice}	K_z	K_h	K_{zt}	t_z	q_z	F_{ac}	e	A,R_r
ft	ft	ft				in	psf	e		ft ²
T1 320.00-304.00	312.00		1.608	11890.1	1		13	A	0.209	6.692

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 38 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section Elevation	z_{wind}	z_{ice}	K_z	K_h	K_{zt}	t_z	q_z	F a c e	e	$A_e R_r$
ft	ft	ft				in	psf			ft ²
T2 304.00-300.00	302.00		1.597	8801.76	1		13	B C A	0.209 0.209 0.201	6.692 6.692 1.656
								B C	0.201 0.201	1.656 1.656
T3 300.00-280.00	290.00		1.584	6135.24	1		12	A B C	0.207 0.207 0.207	9.951 9.951 9.951
T4 280.00-260.00	270.00		1.56	3362.03	1		12	A B C	0.237 0.237 0.237	0.000 0.000 0.000
T5 260.00-240.00	250.00		1.535	1842.35	1.001		12	A B C	0.219 0.219 0.219	0.000 0.000 0.000
T6 240.00-220.00	230.00		1.508	1009.58	1.001		12	A B C	0.223 0.223 0.223	0.000 0.000 0.000
T7 220.00-200.00	210.00		1.48	553.239	1.002		12	A B C	0.181 0.181 0.181	0.000 0.000 0.000
T8 200.00-180.00	190.00		1.449	303.168	1.003		11	A B C	0.187 0.187 0.187	0.000 0.000 0.000
T9 180.00-170.00	175.00		1.424	193.09	1.005		11	A B C	0.177 0.177 0.177	0.000 0.000 0.000
T10 170.00-160.00	165.00		1.406	142.937	1.007		11	A B C	0.171 0.171 0.171	0.000 0.000 0.000
T11 160.00-140.00	150.00		1.378	91.038	1.012		11	A B C	0.181 0.181 0.181	0.000 0.000 0.000
T12 140.00-120.00	130.00		1.337	49.888	1.021		11	A B C	0.173 0.173 0.173	0.000 0.000 0.000
T13 120.00-100.00	110.00		1.291	27.338	1.039		11	A B C	0.131 0.131 0.131	14.546 14.546 14.546
T14 100.00-80.00	90.00		1.238	14.981	1.072		10	A B C	0.122 0.122 0.122	15.395 15.395 15.395
T15 80.00-60.00	70.00		1.174	8.209	1.133		10	A B C	0.127 0.127 0.127	16.540 16.540 16.540
T16 60.00-30.00	45.00		1.07	3.87	1.293		11	A B C	0.122 0.122 0.122	26.633 26.633 26.633
T17 30.00-0.00	15.00		0.85	1.57	1.789		12	A B C	0.117 0.117 0.117	29.025 29.025 29.025

Tower Pressures - No Ice

$$G_H = 0.850$$

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 39 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section Elevation ft	z ft	K _Z	q _z psf	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _{AA} In Face ft ²	C _{AA} Out Face ft ²
T1 320.00-304.00	312.00	1.608	69	116.377	A	9.512	14.835	14.835	60.93	0.000	0.000
					B	9.512	14.835		60.93	5.561	0.000
					C	9.512	14.835		60.93	0.000	0.000
T2 304.00-300.00	302.00	1.597	68	29.094	A	2.147	3.709	3.709	63.34	0.000	0.000
					B	2.147	3.709		63.34	1.540	0.000
					C	2.147	3.709		63.34	0.000	0.000
T3 300.00-280.00	290.00	1.584	68	167.656	A	12.596	22.122	22.122	63.72	0.000	0.000
					B	12.596	22.122		63.72	13.483	0.000
					C	12.596	22.122		63.72	0.000	0.000
T4 280.00-260.00	270.00	1.56	67	216.829	A	51.464	0.000	37.788	73.43	0.000	0.000
					B	51.464	0.000		73.43	26.676	0.000
					C	51.464	0.000		73.43	0.000	0.000
T5 260.00-240.00	250.00	1.535	66	259.126	A	56.868	0.000	37.778	66.43	0.000	0.000
					B	56.868	0.000		66.43	37.174	0.000
					C	56.868	0.000		66.43	0.000	0.000
T6 240.00-220.00	230.00	1.508	64	299.625	A	66.901	0.000	37.776	56.46	0.000	0.000
					B	66.901	0.000		56.46	49.355	0.000
					C	66.901	0.000		56.46	0.000	0.000
T7 220.00-200.00	210.00	1.48	63	339.725	A	61.588	0.000	37.775	61.34	0.000	0.000
					B	61.588	0.000		61.34	49.900	0.000
					C	61.588	0.000		61.34	30.160	0.000
T8 200.00-180.00	190.00	1.449	62	385.076	A	71.846	0.000	45.633	63.52	30.040	0.000
					B	71.846	0.000		63.52	49.900	0.000
					C	71.846	0.000		63.52	30.160	0.000
T9 180.00-170.00	175.00	1.424	61	208.387	A	36.864	0.000	22.815	61.89	15.020	0.000
					B	36.864	0.000		61.89	27.055	0.000
					C	36.864	0.000		61.89	15.080	0.000
T10 170.00-160.00	165.00	1.406	60	218.787	A	37.492	0.000	22.815	60.85	15.020	0.000
					B	37.492	0.000		60.85	29.412	0.000
					C	37.492	0.000		60.85	15.080	0.000
T11 160.00-140.00	150.00	1.378	59	467.070	A	84.562	0.000	45.617	53.94	30.040	0.000
					B	84.562	0.000		53.94	65.283	0.000
					C	84.562	0.000		53.94	30.160	0.000
T12 140.00-120.00	130.00	1.337	58	507.978	A	87.738	0.000	45.637	52.02	30.040	0.000
					B	87.738	0.000		52.02	71.886	0.000
					C	87.738	0.000		52.02	30.160	0.000
T13 120.00-100.00	110.00	1.291	57	555.591	A	45.673	26.937	45.673	62.90	30.040	0.000
					B	45.673	26.937		62.90	76.650	0.000
					C	45.673	26.937		62.90	30.160	0.000
T14 100.00-80.00	90.00	1.238	57	606.388	A	45.666	28.523	45.666	61.55	30.040	0.000
					B	45.666	28.523		61.55	83.818	0.000
					C	45.666	28.523		61.55	30.160	0.000
T15 80.00-60.00	70.00	1.174	57	662.098	A	53.708	30.595	53.708	63.71	30.040	0.000
					B	53.708	30.595		63.71	85.889	0.000
					C	53.708	30.595		63.71	30.160	0.000
T16 60.00-30.00	45.00	1.07	59	1088.08	A	80.523	52.602	80.523	60.49	45.060	0.000
				3	B	80.523	52.602		60.49	128.833	0.000
					C	80.523	52.602		60.49	45.240	0.000
T17 30.00-0.00	15.00	0.85	65	1202.12	A	81.480	59.240	81.480	57.90	37.550	0.000
				2	B	81.480	59.240		57.90	107.361	0.000
					C	81.480	59.240		57.90	37.700	0.000

Tower Pressure - With Ice

$G_H = 0.850$

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	40 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation <i>ft</i>	<i>z</i> <i>ft</i>	<i>Kz</i>	<i>qz</i> <i>psf</i>	<i>tz</i> <i>in</i>	<i>AG</i> <i>ft²</i>	<i>F</i> <i>a</i> <i>c</i> <i>e</i>	<i>AF</i> <i>ft²</i>	<i>AR</i> <i>ft²</i>	<i>Aleg</i> <i>ft²</i>	<i>Leg</i> <i>%</i>	<i>CAA</i> <i>In</i> <i>Face</i> <i>ft²</i>	<i>CAA</i> <i>Out</i> <i>Face</i> <i>ft²</i>
T1 320.00-304.00	312.00	1.608	9	1.4397	120.217	A	9.512	38.165	22.513	47.22	0.000	0.000
						B	9.512	38.165		47.22	22.405	0.000
						C	9.512	38.165		47.22	0.000	0.000
T2 304.00-300.00	302.00	1.597	9	1.4350	30.051	A	2.147	9.143	5.622	49.80	0.000	0.000
						B	2.147	9.143		49.80	6.132	0.000
						C	2.147	9.143		49.80	0.000	0.000
T3 300.00-280.00	290.00	1.584	9	1.4293	172.426	A	12.596	49.670	31.667	50.86	0.000	0.000
						B	12.596	49.670		50.86	49.786	0.000
						C	12.596	49.670		50.86	0.000	0.000
T4 280.00-260.00	270.00	1.56	8	1.4192	221.567	A	57.784	15.527	44.108	60.16	0.000	0.000
						B	57.784	15.527		60.16	89.970	0.000
						C	57.784	15.527		60.16	0.000	0.000
T5 260.00-240.00	250.00	1.535	8	1.4084	263.827	A	63.139	17.925	44.048	54.34	0.000	0.000
						B	63.139	17.925		54.34	118.862	0.000
						C	63.139	17.925		54.34	0.000	0.000
T6 240.00-220.00	230.00	1.508	8	1.3969	304.288	A	73.120	20.343	43.995	47.07	0.000	0.000
						B	73.120	20.343		47.07	154.126	0.000
						C	73.120	20.343		47.07	0.000	0.000
T7 220.00-200.00	210.00	1.48	8	1.3847	344.347	A	67.752	16.487	43.940	52.16	0.000	0.000
						B	67.752	16.487		52.16	155.138	0.000
						C	67.752	16.487		52.16	84.362	0.000
T8 200.00-180.00	190.00	1.449	8	1.3717	389.655	A	77.954	17.978	51.741	53.94	85.834	0.000
						B	77.954	17.978		53.94	154.148	0.000
						C	77.954	17.978		53.94	84.196	0.000
T9 180.00-170.00	175.00	1.424	8	1.3614	210.660	A	39.895	9.563	25.845	52.26	42.830	0.000
						B	39.895	9.563		52.26	84.506	0.000
						C	39.895	9.563		52.26	42.033	0.000
T10 170.00-160.00	165.00	1.406	8	1.3543	221.048	A	40.507	9.939	25.830	51.20	42.771	0.000
						B	40.507	9.939		51.20	93.607	0.000
						C	40.507	9.939		51.20	41.988	0.000
T11 160.00-140.00	150.00	1.378	8	1.3434	471.554	A	90.542	20.928	51.596	46.29	85.358	0.000
						B	90.542	20.928		46.29	204.733	0.000
						C	90.542	20.928		46.29	83.838	0.000
T12 140.00-120.00	130.00	1.337	7	1.3288	512.414	A	93.655	22.377	51.555	44.43	85.111	0.000
						B	93.655	22.377		44.43	223.633	0.000
						C	93.655	22.377		44.43	83.653	0.000
T13 120.00-100.00	110.00	1.291	7	1.3147	559.982	A	51.533	49.840	51.533	50.83	84.874	0.000
						B	51.533	49.840		50.83	234.150	0.000
						C	51.533	49.840		50.83	83.474	0.000
T14 100.00-80.00	90.00	1.238	7	1.3027	610.739	A	51.471	52.577	51.471	49.47	84.672	0.000
						B	51.471	52.577		49.47	250.822	0.000
						C	51.471	52.577		49.47	83.322	0.000
T15 80.00-60.00	70.00	1.174	7	1.2953	666.426	A	59.482	55.793	59.482	51.60	84.548	0.000
						B	59.482	55.793		51.60	256.871	0.000
						C	59.482	55.793		51.60	83.229	0.000
T16 60.00-30.00	45.00	1.07	8	1.2977	1094.584	A	89.196	91.278	89.196	49.42	126.883	0.000
						B	89.196	91.278		49.42	385.783	0.000
						C	89.196	91.278		49.42	124.889	0.000
T17 30.00-0.00	15.00	0.85	8	1.3028	1208.649	A	90.189	100.698	90.189	47.25	105.842	0.000
						B	90.189	100.698		47.25	322.322	0.000
						C	90.189	100.698		47.25	104.154	0.000

Tower Pressure - Service

$G_H = 0.850$

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 41 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section Elevation ft	z ft	K _Z	q _z psf	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _{AA} In Face ft ²	C _{AA} Out Face ft ²
T1 320.00-304.00	312.00	1.608	13	116.377	A	9.512	14.835	14.835	60.93	0.000	0.000
					B	9.512	14.835		60.93	5.561	0.000
					C	9.512	14.835		60.93	0.000	0.000
T2 304.00-300.00	302.00	1.597	13	29.094	A	2.147	3.709	3.709	63.34	0.000	0.000
					B	2.147	3.709		63.34	1.540	0.000
					C	2.147	3.709		63.34	0.000	0.000
T3 300.00-280.00	290.00	1.584	12	167.656	A	12.596	22.122	22.122	63.72	0.000	0.000
					B	12.596	22.122		63.72	13.483	0.000
					C	12.596	22.122		63.72	0.000	0.000
T4 280.00-260.00	270.00	1.56	12	216.829	A	51.464	0.000	37.788	73.43	0.000	0.000
					B	51.464	0.000		73.43	26.676	0.000
					C	51.464	0.000		73.43	0.000	0.000
T5 260.00-240.00	250.00	1.535	12	259.126	A	56.868	0.000	37.778	66.43	0.000	0.000
					B	56.868	0.000		66.43	37.174	0.000
					C	56.868	0.000		66.43	0.000	0.000
T6 240.00-220.00	230.00	1.508	12	299.625	A	66.901	0.000	37.776	56.46	0.000	0.000
					B	66.901	0.000		56.46	49.355	0.000
					C	66.901	0.000		56.46	0.000	0.000
T7 220.00-200.00	210.00	1.48	12	339.725	A	61.588	0.000	37.775	61.34	0.000	0.000
					B	61.588	0.000		61.34	49.900	0.000
					C	61.588	0.000		61.34	30.160	0.000
T8 200.00-180.00	190.00	1.449	11	385.076	A	71.846	0.000	45.633	63.52	30.040	0.000
					B	71.846	0.000		63.52	49.900	0.000
					C	71.846	0.000		63.52	30.160	0.000
T9 180.00-170.00	175.00	1.424	11	208.387	A	36.864	0.000	22.815	61.89	15.020	0.000
					B	36.864	0.000		61.89	27.055	0.000
					C	36.864	0.000		61.89	15.080	0.000
T10 170.00-160.00	165.00	1.406	11	218.787	A	37.492	0.000	22.815	60.85	15.020	0.000
					B	37.492	0.000		60.85	29.412	0.000
					C	37.492	0.000		60.85	15.080	0.000
T11 160.00-140.00	150.00	1.378	11	467.070	A	84.562	0.000	45.617	53.94	30.040	0.000
					B	84.562	0.000		53.94	65.283	0.000
					C	84.562	0.000		53.94	30.160	0.000
T12 140.00-120.00	130.00	1.337	11	507.978	A	87.738	0.000	45.637	52.02	30.040	0.000
					B	87.738	0.000		52.02	71.886	0.000
					C	87.738	0.000		52.02	30.160	0.000
T13 120.00-100.00	110.00	1.291	11	555.591	A	45.673	26.937	45.673	62.90	30.040	0.000
					B	45.673	26.937		62.90	76.650	0.000
					C	45.673	26.937		62.90	30.160	0.000
T14 100.00-80.00	90.00	1.238	10	606.388	A	45.666	28.523	45.666	61.55	30.040	0.000
					B	45.666	28.523		61.55	83.818	0.000
					C	45.666	28.523		61.55	30.160	0.000
T15 80.00-60.00	70.00	1.174	10	662.098	A	53.708	30.595	53.708	63.71	30.040	0.000
					B	53.708	30.595		63.71	85.889	0.000
					C	53.708	30.595		63.71	30.160	0.000
T16 60.00-30.00	45.00	1.07	11	1088.08	A	80.523	52.602	80.523	60.49	45.060	0.000
				3	B	80.523	52.602		60.49	128.833	0.000
					C	80.523	52.602		60.49	45.240	0.000
T17 30.00-0.00	15.00	0.85	12	1202.12	A	81.480	59.240	81.480	57.90	37.550	0.000
				2	B	81.480	59.240		57.90	107.361	0.000
					C	81.480	59.240		57.90	37.700	0.000

Tower Forces - No Ice - Wind Normal To Face

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	42 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	69	1	1	16.204	2618.40	163.65	C
			B	0.209	2.566		1	1	16.204			
			C	0.209	2.566		1	1	16.204			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	68	1	1	3.803	624.23	156.06	C
			B	0.201	2.592		1	1	3.803			
			C	0.201	2.592		1	1	3.803			
T3 300.00-280.00	40.00	2496.34	A	0.207	2.573	68	1	1	22.547	3795.03	189.75	C
			B	0.207	2.573		1	1	22.547			
			C	0.207	2.573		1	1	22.547			
T4 280.00-260.00	87.48	5067.66	A	0.237	2.476	67	1	1	51.464	8113.90	405.69	C
			B	0.237	2.476		1	1	51.464			
			C	0.237	2.476		1	1	51.464			
T5 260.00-240.00	122.62	5409.17	A	0.219	2.532	66	1	1	56.868	9259.42	462.97	C
			B	0.219	2.532		1	1	56.868			
			C	0.219	2.532		1	1	56.868			
T6 240.00-220.00	162.20	6484.36	A	0.223	2.52	64	1	1	66.901	10848.52	542.43	C
			B	0.223	2.52		1	1	66.901			
			C	0.223	2.52		1	1	66.901			
T7 220.00-200.00	362.40	6406.00	A	0.181	2.66	63	1	1	61.588	11384.48	569.22	C
			B	0.181	2.66		1	1	61.588			
			C	0.181	2.66		1	1	61.588			
T8 200.00-180.00	534.20	7298.65	A	0.187	2.641	62	1	1	71.846	13483.50	674.18	C
			B	0.187	2.641		1	1	71.846			
			C	0.187	2.641		1	1	71.846			
T9 180.00-170.00	272.46	3730.84	A	0.177	2.675	61	1	1	36.864	6897.89	689.79	C
			B	0.177	2.675		1	1	36.864			
			C	0.177	2.675		1	1	36.864			
T10 170.00-160.00	279.59	3785.29	A	0.171	2.694	60	1	1	37.492	7022.55	702.26	C
			B	0.171	2.694		1	1	37.492			
			C	0.171	2.694		1	1	37.492			
T11 160.00-140.00	579.39	9608.59	A	0.181	2.661	59	1	1	84.562	15179.59	758.98	C
			B	0.181	2.661		1	1	84.562			
			C	0.181	2.661		1	1	84.562			
T12 140.00-120.00	599.08	9975.29	A	0.173	2.69	58	1	1	87.738	15611.31	780.57	C
			B	0.173	2.69		1	1	87.738			
			C	0.173	2.69		1	1	87.738			
T13 120.00-100.00	609.33	9144.95	A	0.131	2.844	57	1	1	60.219	12324.59	616.23	C
			B	0.131	2.844		1	1	60.219			
			C	0.131	2.844		1	1	60.219			
T14 100.00-80.00	625.08	9675.54	A	0.122	2.876	57	1	1	61.061	12604.51	630.23	C
			B	0.122	2.876		1	1	61.061			
			C	0.122	2.876		1	1	61.061			
T15 80.00-60.00	630.40	11450.50	A	0.127	2.857	57	1	1	70.248	13907.81	695.39	C
			B	0.127	2.857		1	1	70.248			
			C	0.127	2.857		1	1	70.248			
T16 60.00-30.00	945.60	15115.36	A	0.122	2.876	59	1	1	107.156	22039.49	734.65	C
			B	0.122	2.876		1	1	107.156			
			C	0.122	2.876		1	1	107.156			
T17 30.00-0.00	788.00	17941.94	A	0.117	2.896	65	1	1	110.505	23685.38	789.51	C
			B	0.117	2.896		1	1	110.505			
			C	0.117	2.896		1	1	110.505			
Sum Weight:	6658.09	125382.28						OTM	25542.37 kip-ft	189400.61		

Tower Forces - No Ice - Wind 45 To Face

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	43 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z psf	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	69	0.825	1	14.539	2369.39	148.09	C
			B	0.209	2.566		0.825	1	14.539			
			C	0.209	2.566		0.825	1	14.539			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	68	0.825	1	3.427	567.84	141.96	C
			B	0.201	2.592		0.825	1	3.427			
			C	0.201	2.592		0.825	1	3.427			
T3 300.00-280.00	40.00	2496.34	A	0.207	2.573	68	0.825	1	20.343	3469.43	173.47	C
			B	0.207	2.573		0.825	1	20.343			
			C	0.207	2.573		0.825	1	20.343			
T4 280.00-260.00	87.48	5067.66	A	0.237	2.476	67	0.825	1	42.458	6852.42	342.62	C
			B	0.237	2.476		0.825	1	42.458			
			C	0.237	2.476		0.825	1	42.458			
T5 260.00-240.00	122.62	5409.17	A	0.219	2.532	66	0.825	1	46.916	7856.34	392.82	C
			B	0.219	2.532		0.825	1	46.916			
			C	0.219	2.532		0.825	1	46.916			
T6 240.00-220.00	162.20	6484.36	A	0.223	2.52	64	0.825	1	55.194	9233.67	461.68	C
			B	0.223	2.52		0.825	1	55.194			
			C	0.223	2.52		0.825	1	55.194			
T7 220.00-200.00	362.40	6406.00	A	0.181	2.66	63	0.825	1	50.810	9843.96	492.20	C
			B	0.181	2.66		0.825	1	50.810			
			C	0.181	2.66		0.825	1	50.810			
T8 200.00-180.00	534.20	7298.65	A	0.187	2.641	62	0.825	1	59.273	11733.17	586.66	C
			B	0.187	2.641		0.825	1	59.273			
			C	0.187	2.641		0.825	1	59.273			
T9 180.00-170.00	272.46	3730.84	A	0.177	2.675	61	0.825	1	30.413	6002.24	600.22	C
			B	0.177	2.675		0.825	1	30.413			
			C	0.177	2.675		0.825	1	30.413			
T10 170.00-160.00	279.59	3785.29	A	0.171	2.694	60	0.825	1	30.931	6114.55	611.46	C
			B	0.171	2.694		0.825	1	30.931			
			C	0.171	2.694		0.825	1	30.931			
T11 160.00-140.00	579.39	9608.59	A	0.181	2.661	59	0.825	1	69.763	13189.24	659.46	C
			B	0.181	2.661		0.825	1	69.763			
			C	0.181	2.661		0.825	1	69.763			
T12 140.00-120.00	599.08	9975.29	A	0.173	2.69	58	0.825	1	72.384	13566.16	678.31	C
			B	0.173	2.69		0.825	1	72.384			
			C	0.173	2.69		0.825	1	72.384			
T13 120.00-100.00	609.33	9144.95	A	0.131	2.844	57	0.825	1	52.226	11218.90	560.95	C
			B	0.131	2.844		0.825	1	52.226			
			C	0.131	2.844		0.825	1	52.226			
T14 100.00-80.00	625.08	9675.54	A	0.122	2.876	57	0.825	1	53.069	11498.90	574.95	C
			B	0.122	2.876		0.825	1	53.069			
			C	0.122	2.876		0.825	1	53.069			
T15 80.00-60.00	630.40	11450.50	A	0.127	2.857	57	0.825	1	60.850	12612.70	630.63	C
			B	0.127	2.857		0.825	1	60.850			
			C	0.127	2.857		0.825	1	60.850			
T16 60.00-30.00	945.60	15115.36	A	0.122	2.876	59	0.825	1	93.064	20007.96	666.93	C
			B	0.122	2.876		0.825	1	93.064			
			C	0.122	2.876		0.825	1	93.064			
T17 30.00-0.00	788.00	17941.94	A	0.117	2.896	65	0.825	1	96.246	21408.56	713.62	C
			B	0.117	2.896		0.825	1	96.246			
			C	0.117	2.896		0.825	1	96.246			
Sum Weight:	6658.09	125382.28						OTM	22326.02 kip-ft	167545.42		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	44 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Forces - No Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	69	0.8	1	14.302	2333.81	145.86	C
			B	0.209	2.566		0.8	1	14.302			
			C	0.209	2.566		0.8	1	14.302			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	68	0.8	1	3.373	559.79	139.95	C
			B	0.201	2.592		0.8	1	3.373			
			C	0.201	2.592		0.8	1	3.373			
T3 300.00-280.00	40.00	2496.34	A	0.207	2.573	68	0.8	1	20.028	3422.91	171.15	C
			B	0.207	2.573		0.8	1	20.028			
			C	0.207	2.573		0.8	1	20.028			
T4 280.00-260.00	87.48	5067.66	A	0.237	2.476	67	0.8	1	41.171	6672.21	333.61	C
			B	0.237	2.476		0.8	1	41.171			
			C	0.237	2.476		0.8	1	41.171			
T5 260.00-240.00	122.62	5409.17	A	0.219	2.532	66	0.8	1	45.494	7655.90	382.79	C
			B	0.219	2.532		0.8	1	45.494			
			C	0.219	2.532		0.8	1	45.494			
T6 240.00-220.00	162.20	6484.36	A	0.223	2.52	64	0.8	1	53.521	9002.97	450.15	C
			B	0.223	2.52		0.8	1	53.521			
			C	0.223	2.52		0.8	1	53.521			
T7 220.00-200.00	362.40	6406.00	A	0.181	2.66	63	0.8	1	49.270	9623.88	481.19	C
			B	0.181	2.66		0.8	1	49.270			
			C	0.181	2.66		0.8	1	49.270			
T8 200.00-180.00	534.20	7298.65	A	0.187	2.641	62	0.8	1	57.477	11483.12	574.16	C
			B	0.187	2.641		0.8	1	57.477			
			C	0.187	2.641		0.8	1	57.477			
T9 180.00-170.00	272.46	3730.84	A	0.177	2.675	61	0.8	1	29.491	5874.29	587.43	C
			B	0.177	2.675		0.8	1	29.491			
			C	0.177	2.675		0.8	1	29.491			
T10 170.00-160.00	279.59	3785.29	A	0.171	2.694	60	0.8	1	29.994	5984.84	598.48	C
			B	0.171	2.694		0.8	1	29.994			
			C	0.171	2.694		0.8	1	29.994			
T11 160.00-140.00	579.39	9608.59	A	0.181	2.661	59	0.8	1	67.649	12904.91	645.25	C
			B	0.181	2.661		0.8	1	67.649			
			C	0.181	2.661		0.8	1	67.649			
T12 140.00-120.00	599.08	9975.29	A	0.173	2.69	58	0.8	1	70.190	13274.00	663.70	C
			B	0.173	2.69		0.8	1	70.190			
			C	0.173	2.69		0.8	1	70.190			
T13 120.00-100.00	609.33	9144.95	A	0.131	2.844	57	0.8	1	51.085	11060.95	553.05	C
			B	0.131	2.844		0.8	1	51.085			
			C	0.131	2.844		0.8	1	51.085			
T14 100.00-80.00	625.08	9675.54	A	0.122	2.876	57	0.8	1	51.928	11340.96	567.05	C
			B	0.122	2.876		0.8	1	51.928			
			C	0.122	2.876		0.8	1	51.928			
T15 80.00-60.00	630.40	11450.50	A	0.127	2.857	57	0.8	1	59.507	12427.68	621.38	C
			B	0.127	2.857		0.8	1	59.507			
			C	0.127	2.857		0.8	1	59.507			
T16 60.00-30.00	945.60	15115.36	A	0.122	2.876	59	0.8	1	91.051	19717.74	657.26	C
			B	0.122	2.876		0.8	1	91.051			
			C	0.122	2.876		0.8	1	91.051			
T17 30.00-0.00	788.00	17941.94	A	0.117	2.896	65	0.8	1	94.209	21083.30	702.78	C
			B	0.117	2.896		0.8	1	94.209			
			C	0.117	2.896		0.8	1	94.209			
Sum Weight:	6658.09	125382.28						OTM	21866.54 kip-ft	164423.25		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 45 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Tower Forces - No Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z psf	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	69	0.85	1	14.777	2404.96	150.31	C
			B	0.209	2.566		0.85	1	14.777			
			C	0.209	2.566		0.85	1	14.777			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	68	0.85	1	3.481	575.90	143.97	C
			B	0.201	2.592		0.85	1	3.481			
			C	0.201	2.592		0.85	1	3.481			
T3 300.00-280.00	40.00	2496.34	A	0.207	2.573	68	0.85	1	20.658	3515.94	175.80	C
			B	0.207	2.573		0.85	1	20.658			
			C	0.207	2.573		0.85	1	20.658			
T4 280.00-260.00	87.48	5067.66	A	0.237	2.476	67	0.85	1	43.745	7032.63	351.63	C
			B	0.237	2.476		0.85	1	43.745			
			C	0.237	2.476		0.85	1	43.745			
T5 260.00-240.00	122.62	5409.17	A	0.219	2.532	66	0.85	1	48.338	8056.78	402.84	C
			B	0.219	2.532		0.85	1	48.338			
			C	0.219	2.532		0.85	1	48.338			
T6 240.00-220.00	162.20	6484.36	A	0.223	2.52	64	0.85	1	56.866	9464.36	473.22	C
			B	0.223	2.52		0.85	1	56.866			
			C	0.223	2.52		0.85	1	56.866			
T7 220.00-200.00	362.40	6406.00	A	0.181	2.66	63	0.85	1	52.350	10064.03	503.20	C
			B	0.181	2.66		0.85	1	52.350			
			C	0.181	2.66		0.85	1	52.350			
T8 200.00-180.00	534.20	7298.65	A	0.187	2.641	62	0.85	1	61.069	11983.22	599.16	C
			B	0.187	2.641		0.85	1	61.069			
			C	0.187	2.641		0.85	1	61.069			
T9 180.00-170.00	272.46	3730.84	A	0.177	2.675	61	0.85	1	31.334	6130.19	613.02	C
			B	0.177	2.675		0.85	1	31.334			
			C	0.177	2.675		0.85	1	31.334			
T10 170.00-160.00	279.59	3785.29	A	0.171	2.694	60	0.85	1	31.869	6244.27	624.43	C
			B	0.171	2.694		0.85	1	31.869			
			C	0.171	2.694		0.85	1	31.869			
T11 160.00-140.00	579.39	9608.59	A	0.181	2.661	59	0.85	1	71.877	13473.58	673.68	C
			B	0.181	2.661		0.85	1	71.877			
			C	0.181	2.661		0.85	1	71.877			
T12 140.00-120.00	599.08	9975.29	A	0.173	2.69	58	0.85	1	74.577	13858.33	692.92	C
			B	0.173	2.69		0.85	1	74.577			
			C	0.173	2.69		0.85	1	74.577			
T13 120.00-100.00	609.33	9144.95	A	0.131	2.844	57	0.85	1	53.368	11376.86	568.84	C
			B	0.131	2.844		0.85	1	53.368			
			C	0.131	2.844		0.85	1	53.368			
T14 100.00-80.00	625.08	9675.54	A	0.122	2.876	57	0.85	1	54.211	11656.85	582.84	C
			B	0.122	2.876		0.85	1	54.211			
			C	0.122	2.876		0.85	1	54.211			
T15 80.00-60.00	630.40	11450.50	A	0.127	2.857	57	0.85	1	62.192	12797.71	639.89	C
			B	0.127	2.857		0.85	1	62.192			
			C	0.127	2.857		0.85	1	62.192			
T16 60.00-30.00	945.60	15115.36	A	0.122	2.876	59	0.85	1	95.078	20298.18	676.61	C
			B	0.122	2.876		0.85	1	95.078			
			C	0.122	2.876		0.85	1	95.078			
T17 30.00-0.00	788.00	17941.94	A	0.117	2.896	65	0.85	1	98.283	21733.82	724.46	C
			B	0.117	2.896		0.85	1	98.283			
			C	0.117	2.896		0.85	1	98.283			
Sum Weight:	6658.09	125382.28						OTM	22785.50 kip-ft	170667.59		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 46 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Tower Forces - With Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 320.00-304.00	261.85	3479.11	A	0.397	2.071	9	1	1	33.738	619.55	38.72	C
			B	0.397	2.071		1	1	33.738			
			C	0.397	2.071		1	1	33.738			
T2 304.00-300.00	71.62	821.79	A	0.376	2.114	9	1	1	7.871	150.08	37.52	C
			B	0.376	2.114		1	1	7.871			
			C	0.376	2.114		1	1	7.871			
T3 300.00-280.00	592.40	5152.34	A	0.361	2.146	9	1	1	43.405	901.03	45.05	C
			B	0.361	2.146		1	1	43.405			
			C	0.361	2.146		1	1	43.405			
T4 280.00-260.00	1098.70	9553.22	A	0.331	2.217	8	1	1	67.242	1465.24	73.26	C
			B	0.331	2.217		1	1	67.242			
			C	0.331	2.217		1	1	67.242			
T5 260.00-240.00	1465.07	10434.30	A	0.307	2.277	8	1	1	73.915	1701.59	85.08	C
			B	0.307	2.277		1	1	73.915			
			C	0.307	2.277		1	1	73.915			
T6 240.00-220.00	1898.59	12452.94	A	0.307	2.277	8	1	1	85.350	2002.42	100.12	C
			B	0.307	2.277		1	1	85.350			
			C	0.307	2.277		1	1	85.350			
T7 220.00-200.00	3016.37	11683.11	A	0.245	2.454	8	1	1	77.376	2286.43	114.32	C
			B	0.245	2.454		1	1	77.376			
			C	0.245	2.454		1	1	77.376			
T8 200.00-180.00	4081.67	13202.41	A	0.246	2.449	8	1	1	88.454	2763.75	138.19	C
			B	0.246	2.449		1	1	88.454			
			C	0.246	2.449		1	1	88.454			
T9 180.00-170.00	2112.84	6756.36	A	0.235	2.484	8	1	1	45.455	1420.22	142.02	C
			B	0.235	2.484		1	1	45.455			
			C	0.235	2.484		1	1	45.455			
T10 170.00-160.00	2205.64	6858.43	A	0.228	2.504	8	1	1	46.272	1460.30	146.03	C
			B	0.228	2.504		1	1	46.272			
			C	0.228	2.504		1	1	46.272			
T11 160.00-140.00	4581.87	16563.91	A	0.236	2.479	8	1	1	102.718	3088.60	154.43	C
			B	0.236	2.479		1	1	102.718			
			C	0.236	2.479		1	1	102.718			
T12 140.00-120.00	4759.58	17156.52	A	0.226	2.51	7	1	1	106.625	3177.75	158.89	C
			B	0.226	2.51		1	1	106.625			
			C	0.226	2.51		1	1	106.625			
T13 120.00-100.00	4836.64	15024.43	A	0.181	2.661	7	1	1	80.012	2819.23	140.96	C
			B	0.181	2.661		1	1	80.012			
			C	0.181	2.661		1	1	80.012			
T14 100.00-80.00	4985.09	15674.17	A	0.17	2.698	7	1	1	81.435	2890.06	144.50	C
			B	0.17	2.698		1	1	81.435			
			C	0.17	2.698		1	1	81.435			
T15 80.00-60.00	5030.92	18017.30	A	0.173	2.689	7	1	1	91.299	3077.90	153.90	C
			B	0.173	2.689		1	1	91.299			
			C	0.173	2.689		1	1	91.299			
T16 60.00-30.00	7561.96	25360.00	A	0.165	2.717	8	1	1	141.153	4898.66	163.29	C
			B	0.165	2.717		1	1	141.153			
			C	0.165	2.717		1	1	141.153			
T17 30.00-0.00	6329.02	28872.58	A	0.158	2.743	8	1	1	147.426	5088.95	169.63	C
			B	0.158	2.743		1	1	147.426			
			C	0.158	2.743		1	1	147.426			
Sum Weight:	54889.82	217062.94						OTM	5235.09 kip-ft	39811.78		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	47 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Forces - With Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 320.00-304.00	261.85	3479.11	A	0.397	2.071	9	0.825	1	32.074	593.92	37.12	C
			B	0.397	2.071		0.825		32.074			
			C	0.397	2.071		0.825		32.074			
T2 304.00-300.00	71.62	821.79	A	0.376	2.114	9	0.825	1	7.495	144.22	36.05	C
			B	0.376	2.114		0.825		7.495			
			C	0.376	2.114		0.825		7.495			
T3 300.00-280.00	592.40	5152.34	A	0.361	2.146	9	0.825	1	41.201	866.38	43.32	C
			B	0.361	2.146		0.825		41.201			
			C	0.361	2.146		0.825		41.201			
T4 280.00-260.00	1098.70	9553.22	A	0.331	2.217	8	0.825	1	57.130	1303.47	65.17	C
			B	0.331	2.217		0.825		57.130			
			C	0.331	2.217		0.825		57.130			
T5 260.00-240.00	1465.07	10434.30	A	0.307	2.277	8	0.825	1	62.866	1522.94	76.15	C
			B	0.307	2.277		0.825		62.866			
			C	0.307	2.277		0.825		62.866			
T6 240.00-220.00	1898.59	12452.94	A	0.307	2.277	8	0.825	1	72.554	1799.00	89.95	C
			B	0.307	2.277		0.825		72.554			
			C	0.307	2.277		0.825		72.554			
T7 220.00-200.00	3016.37	11683.11	A	0.245	2.454	8	0.825	1	65.519	2087.01	104.35	C
			B	0.245	2.454		0.825		65.519			
			C	0.245	2.454		0.825		65.519			
T8 200.00-180.00	4081.67	13202.41	A	0.246	2.449	8	0.825	1	74.812	2539.17	126.96	C
			B	0.246	2.449		0.825		74.812			
			C	0.246	2.449		0.825		74.812			
T9 180.00-170.00	2112.84	6756.36	A	0.235	2.484	8	0.825	1	38.473	1305.41	130.54	C
			B	0.235	2.484		0.825		38.473			
			C	0.235	2.484		0.825		38.473			
T10 170.00-160.00	2205.64	6858.43	A	0.228	2.504	8	0.825	1	39.183	1344.00	134.40	C
			B	0.228	2.504		0.825		39.183			
			C	0.228	2.504		0.825		39.183			
T11 160.00-140.00	4581.87	16563.91	A	0.236	2.479	8	0.825	1	86.873	2835.33	141.77	C
			B	0.236	2.479		0.825		86.873			
			C	0.236	2.479		0.825		86.873			
T12 140.00-120.00	4759.58	17156.52	A	0.226	2.51	7	0.825	1	90.235	2917.89	145.89	C
			B	0.226	2.51		0.825		90.235			
			C	0.226	2.51		0.825		90.235			
T13 120.00-100.00	4836.64	15024.43	A	0.181	2.661	7	0.825	1	70.994	2670.36	133.52	C
			B	0.181	2.661		0.825		70.994			
			C	0.181	2.661		0.825		70.994			
T14 100.00-80.00	4985.09	15674.17	A	0.17	2.698	7	0.825	1	72.428	2740.95	137.05	C
			B	0.17	2.698		0.825		72.428			
			C	0.17	2.698		0.825		72.428			
T15 80.00-60.00	5030.92	18017.30	A	0.173	2.689	7	0.825	1	80.890	2905.71	145.29	C
			B	0.173	2.689		0.825		80.890			
			C	0.173	2.689		0.825		80.890			
T16 60.00-30.00	7561.96	25360.00	A	0.165	2.717	8	0.825	1	125.544	4627.43	154.25	C
			B	0.165	2.717		0.825		125.544			
			C	0.165	2.717		0.825		125.544			
T17 30.00-0.00	6329.02	28872.58	A	0.158	2.743	8	0.825	1	131.643	4784.58	159.49	C
			B	0.158	2.743		0.825		131.643			
			C	0.158	2.743		0.825		131.643			
Sum Weight:	54889.82	217062.94						OTM	4825.92 kip-ft	36987.74		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	48 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Tower Forces - With Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1 320.00-304.00	261.85	3479.11	A	0.397	2.071	9	0.8	1	31.836	590.25	36.89	C
			B	0.397	2.071		0.8	1	31.836			
			C	0.397	2.071		0.8	1	31.836			
T2 304.00-300.00	71.62	821.79	A	0.376	2.114	9	0.8	1	7.441	143.38	35.84	C
			B	0.376	2.114		0.8	1	7.441			
			C	0.376	2.114		0.8	1	7.441			
T3 300.00-280.00	592.40	5152.34	A	0.361	2.146	9	0.8	1	40.886	861.43	43.07	C
			B	0.361	2.146		0.8	1	40.886			
			C	0.361	2.146		0.8	1	40.886			
T4 280.00-260.00	1098.70	9553.22	A	0.331	2.217	8	0.8	1	55.686	1280.36	64.02	C
			B	0.331	2.217		0.8	1	55.686			
			C	0.331	2.217		0.8	1	55.686			
T5 260.00-240.00	1465.07	10434.30	A	0.307	2.277	8	0.8	1	61.287	1497.42	74.87	C
			B	0.307	2.277		0.8	1	61.287			
			C	0.307	2.277		0.8	1	61.287			
T6 240.00-220.00	1898.59	12452.94	A	0.307	2.277	8	0.8	1	70.726	1769.94	88.50	C
			B	0.307	2.277		0.8	1	70.726			
			C	0.307	2.277		0.8	1	70.726			
T7 220.00-200.00	3016.37	11683.11	A	0.245	2.454	8	0.8	1	63.825	2058.52	102.93	C
			B	0.245	2.454		0.8	1	63.825			
			C	0.245	2.454		0.8	1	63.825			
T8 200.00-180.00	4081.67	13202.41	A	0.246	2.449	8	0.8	1	72.863	2507.09	125.35	C
			B	0.246	2.449		0.8	1	72.863			
			C	0.246	2.449		0.8	1	72.863			
T9 180.00-170.00	2112.84	6756.36	A	0.235	2.484	8	0.8	1	37.476	1289.01	128.90	C
			B	0.235	2.484		0.8	1	37.476			
			C	0.235	2.484		0.8	1	37.476			
T10 170.00-160.00	2205.64	6858.43	A	0.228	2.504	8	0.8	1	38.171	1327.38	132.74	C
			B	0.228	2.504		0.8	1	38.171			
			C	0.228	2.504		0.8	1	38.171			
T11 160.00-140.00	4581.87	16563.91	A	0.236	2.479	8	0.8	1	84.609	2799.14	139.96	C
			B	0.236	2.479		0.8	1	84.609			
			C	0.236	2.479		0.8	1	84.609			
T12 140.00-120.00	4759.58	17156.52	A	0.226	2.51	7	0.8	1	87.894	2880.76	144.04	C
			B	0.226	2.51		0.8	1	87.894			
			C	0.226	2.51		0.8	1	87.894			
T13 120.00-100.00	4836.64	15024.43	A	0.181	2.661	7	0.8	1	69.705	2649.09	132.45	C
			B	0.181	2.661		0.8	1	69.705			
			C	0.181	2.661		0.8	1	69.705			
T14 100.00-80.00	4985.09	15674.17	A	0.17	2.698	7	0.8	1	71.141	2719.65	135.98	C
			B	0.17	2.698		0.8	1	71.141			
			C	0.17	2.698		0.8	1	71.141			
T15 80.00-60.00	5030.92	18017.30	A	0.173	2.689	7	0.8	1	79.403	2881.11	144.06	C
			B	0.173	2.689		0.8	1	79.403			
			C	0.173	2.689		0.8	1	79.403			
T16 60.00-30.00	7561.96	25360.00	A	0.165	2.717	8	0.8	1	123.314	4588.69	152.96	C
			B	0.165	2.717		0.8	1	123.314			
			C	0.165	2.717		0.8	1	123.314			
T17 30.00-0.00	6329.02	28872.58	A	0.158	2.743	8	0.8	1	129.388	4741.10	158.04	C
			B	0.158	2.743		0.8	1	129.388			
			C	0.158	2.743		0.8	1	129.388			
Sum Weight:	54889.82	217062.94						OTM	4767.46	36584.30		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	49 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z psf	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
ft	lb	lb							kip-ft			

Tower Forces - With Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z psf	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	261.85	3479.11	A	0.397	2.071	9	0.85	1	32.312	597.58	37.35	C
			B	0.397	2.071		0.85	1	32.312			
			C	0.397	2.071		0.85	1	32.312			
T2 304.00-300.00	71.62	821.79	A	0.376	2.114	9	0.85	1	7.549	145.05	36.26	C
			B	0.376	2.114		0.85	1	7.549			
			C	0.376	2.114		0.85	1	7.549			
T3 300.00-280.00	592.40	5152.34	A	0.361	2.146	9	0.85	1	41.516	871.33	43.57	C
			B	0.361	2.146		0.85	1	41.516			
			C	0.361	2.146		0.85	1	41.516			
T4 280.00-260.00	1098.70	9553.22	A	0.331	2.217	8	0.85	1	58.575	1326.58	66.33	C
			B	0.331	2.217		0.85	1	58.575			
			C	0.331	2.217		0.85	1	58.575			
T5 260.00-240.00	1465.07	10434.30	A	0.307	2.277	8	0.85	1	64.444	1548.46	77.42	C
			B	0.307	2.277		0.85	1	64.444			
			C	0.307	2.277		0.85	1	64.444			
T6 240.00-220.00	1898.59	12452.94	A	0.307	2.277	8	0.85	1	74.382	1828.06	91.40	C
			B	0.307	2.277		0.85	1	74.382			
			C	0.307	2.277		0.85	1	74.382			
T7 220.00-200.00	3016.37	11683.11	A	0.245	2.454	8	0.85	1	67.213	2115.49	105.77	C
			B	0.245	2.454		0.85	1	67.213			
			C	0.245	2.454		0.85	1	67.213			
T8 200.00-180.00	4081.67	13202.41	A	0.246	2.449	8	0.85	1	76.761	2571.25	128.56	C
			B	0.246	2.449		0.85	1	76.761			
			C	0.246	2.449		0.85	1	76.761			
T9 180.00-170.00	2112.84	6756.36	A	0.235	2.484	8	0.85	1	39.471	1321.81	132.18	C
			B	0.235	2.484		0.85	1	39.471			
			C	0.235	2.484		0.85	1	39.471			
T10 170.00-160.00	2205.64	6858.43	A	0.228	2.504	8	0.85	1	40.196	1360.61	136.06	C
			B	0.228	2.504		0.85	1	40.196			
			C	0.228	2.504		0.85	1	40.196			
T11 160.00-140.00	4581.87	16563.91	A	0.236	2.479	8	0.85	1	89.136	2871.51	143.58	C
			B	0.236	2.479		0.85	1	89.136			
			C	0.236	2.479		0.85	1	89.136			
T12 140.00-120.00	4759.58	17156.52	A	0.226	2.51	7	0.85	1	92.577	2955.01	147.75	C
			B	0.226	2.51		0.85	1	92.577			
			C	0.226	2.51		0.85	1	92.577			
T13 120.00-100.00	4836.64	15024.43	A	0.181	2.661	7	0.85	1	72.282	2691.62	134.58	C
			B	0.181	2.661		0.85	1	72.282			
			C	0.181	2.661		0.85	1	72.282			
T14 100.00-80.00	4985.09	15674.17	A	0.17	2.698	7	0.85	1	73.715	2762.25	138.11	C
			B	0.17	2.698		0.85	1	73.715			
			C	0.17	2.698		0.85	1	73.715			
T15 80.00-60.00	5030.92	18017.30	A	0.173	2.689	7	0.85	1	82.377	2930.31	146.52	C
			B	0.173	2.689		0.85	1	82.377			
			C	0.173	2.689		0.85	1	82.377			
T16	7561.96	25360.00	A	0.165	2.717	8	0.85	1	127.774	4666.18	155.54	C

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	50 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
60.00-30.00			B	0.165	2.717		0.85	1	127.774			
			C	0.165	2.717		0.85	1	127.774			
T17	6329.02	28872.58	A	0.158	2.743	8	0.85	1	133.898	4828.06	160.94	C
30.00-0.00			B	0.158	2.743		0.85	1	133.898			
			C	0.158	2.743		0.85	1	133.898			
Sum Weight:	54889.82	217062.94						OTM	4884.37 kip-ft	37391.17		

Tower Forces - Service - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1	15.90	1442.07	A	0.209	2.566	13	1	1	16.204	480.93	30.06	C
320.00-304.00			B	0.209	2.566		1	1	16.204			
			C	0.209	2.566		1	1	16.204			
T2	4.36	349.72	A	0.201	2.592	13	1	1	3.803	114.65	28.66	C
304.00-300.00			B	0.201	2.592		1	1	3.803			
			C	0.201	2.592		1	1	3.803			
T3	40.00	2496.34	A	0.207	2.573	12	1	1	22.547	697.05	34.85	C
300.00-280.00			B	0.207	2.573		1	1	22.547			
			C	0.207	2.573		1	1	22.547			
T4	87.48	5067.66	A	0.237	2.476	12	1	1	51.464	1490.31	74.52	C
280.00-260.00			B	0.237	2.476		1	1	51.464			
			C	0.237	2.476		1	1	51.464			
T5	122.62	5409.17	A	0.219	2.532	12	1	1	56.868	1700.71	85.04	C
260.00-240.00			B	0.219	2.532		1	1	56.868			
			C	0.219	2.532		1	1	56.868			
T6	162.20	6484.36	A	0.223	2.52	12	1	1	66.901	1992.59	99.63	C
240.00-220.00			B	0.223	2.52		1	1	66.901			
			C	0.223	2.52		1	1	66.901			
T7	362.40	6406.00	A	0.181	2.66	12	1	1	61.588	2091.03	104.55	C
220.00-200.00			B	0.181	2.66		1	1	61.588			
			C	0.181	2.66		1	1	61.588			
T8	534.20	7298.65	A	0.187	2.641	11	1	1	71.846	2476.56	123.83	C
200.00-180.00			B	0.187	2.641		1	1	71.846			
			C	0.187	2.641		1	1	71.846			
T9	272.46	3730.84	A	0.177	2.675	11	1	1	36.864	1266.96	126.70	C
180.00-170.00			B	0.177	2.675		1	1	36.864			
			C	0.177	2.675		1	1	36.864			
T10	279.59	3785.29	A	0.171	2.694	11	1	1	37.492	1289.86	128.99	C
170.00-160.00			B	0.171	2.694		1	1	37.492			
			C	0.171	2.694		1	1	37.492			
T11	579.39	9608.59	A	0.181	2.661	11	1	1	84.562	2788.09	139.40	C
160.00-140.00			B	0.181	2.661		1	1	84.562			
			C	0.181	2.661		1	1	84.562			
T12	599.08	9975.29	A	0.173	2.69	11	1	1	87.738	2867.38	143.37	C
140.00-120.00			B	0.173	2.69		1	1	87.738			
			C	0.173	2.69		1	1	87.738			
T13	609.33	9144.95	A	0.131	2.844	11	1	1	60.219	2263.70	113.19	C
120.00-100.00			B	0.131	2.844		1	1	60.219			
			C	0.131	2.844		1	1	60.219			
T14	625.08	9675.54	A	0.122	2.876	10	1	1	61.061	2315.11	115.76	C

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	51 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
100.00-80.00			B	0.122	2.876		1	1	61.061			
			C	0.122	2.876		1	1	61.061			
T15	630.40	11450.50	A	0.127	2.857	10	1	1	70.248	2554.50	127.72	C
80.00-60.00			B	0.127	2.857		1	1	70.248			
			C	0.127	2.857		1	1	70.248			
T16	945.60	15115.36	A	0.122	2.876	11	1	1	107.156	4048.07	134.94	C
60.00-30.00			B	0.122	2.876		1	1	107.156			
			C	0.122	2.876		1	1	107.156			
T17	788.00	17941.94	A	0.117	2.896	12	1	1	110.505	4350.38	145.01	C
30.00-0.00			B	0.117	2.896		1	1	110.505			
			C	0.117	2.896		1	1	110.505			
Sum Weight:	6658.09	125382.28						OTM	4691.46 kip-ft	34787.87		

Tower Forces - Service - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1	15.90	1442.07	A	0.209	2.566	13	0.825	1	14.539	435.19	27.20	C
320.00-304.00			B	0.209	2.566		0.825	1	14.539			
			C	0.209	2.566		0.825	1	14.539			
T2	4.36	349.72	A	0.201	2.592	13	0.825	1	3.427	104.30	26.07	C
304.00-300.00			B	0.201	2.592		0.825	1	3.427			
			C	0.201	2.592		0.825	1	3.427			
T3	40.00	2496.34	A	0.207	2.573	12	0.825	1	20.343	637.24	31.86	C
300.00-280.00			B	0.207	2.573		0.825	1	20.343			
			C	0.207	2.573		0.825	1	20.343			
T4	87.48	5067.66	A	0.237	2.476	12	0.825	1	42.458	1258.61	62.93	C
280.00-260.00			B	0.237	2.476		0.825	1	42.458			
			C	0.237	2.476		0.825	1	42.458			
T5	122.62	5409.17	A	0.219	2.532	12	0.825	1	46.916	1443.00	72.15	C
260.00-240.00			B	0.219	2.532		0.825	1	46.916			
			C	0.219	2.532		0.825	1	46.916			
T6	162.20	6484.36	A	0.223	2.52	12	0.825	1	55.194	1695.98	84.80	C
240.00-220.00			B	0.223	2.52		0.825	1	55.194			
			C	0.223	2.52		0.825	1	55.194			
T7	362.40	6406.00	A	0.181	2.66	12	0.825	1	50.810	1808.07	90.40	C
220.00-200.00			B	0.181	2.66		0.825	1	50.810			
			C	0.181	2.66		0.825	1	50.810			
T8	534.20	7298.65	A	0.187	2.641	11	0.825	1	59.273	2155.07	107.75	C
200.00-180.00			B	0.187	2.641		0.825	1	59.273			
			C	0.187	2.641		0.825	1	59.273			
T9	272.46	3730.84	A	0.177	2.675	11	0.825	1	30.413	1102.45	110.25	C
180.00-170.00			B	0.177	2.675		0.825	1	30.413			
			C	0.177	2.675		0.825	1	30.413			
T10	279.59	3785.29	A	0.171	2.694	11	0.825	1	30.931	1123.08	112.31	C
170.00-160.00			B	0.171	2.694		0.825	1	30.931			
			C	0.171	2.694		0.825	1	30.931			
T11	579.39	9608.59	A	0.181	2.661	11	0.825	1	69.763	2422.51	121.13	C
160.00-140.00			B	0.181	2.661		0.825	1	69.763			
			C	0.181	2.661		0.825	1	69.763			
T12	599.08	9975.29	A	0.173	2.69	11	0.825	1	72.384	2491.74	124.59	C

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	52 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation ft	Add Weight lb	Self Weight lb	F a c e	e	C _F	q _z psf	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
140.00-120.00			B	0.173	2.69		0.825	1	72.384			
			C	0.173	2.69		0.825	1	72.384			
T13	609.33	9144.95	A	0.131	2.844	11	0.825	1	52.226	2060.61	103.03	C
120.00-100.00			B	0.131	2.844		0.825	1	52.226			
			C	0.131	2.844		0.825	1	52.226			
T14	625.08	9675.54	A	0.122	2.876	10	0.825	1	53.069	2112.04	105.60	C
100.00-80.00			B	0.122	2.876		0.825	1	53.069			
			C	0.122	2.876		0.825	1	53.069			
T15	630.40	11450.50	A	0.127	2.857	10	0.825	1	60.850	2316.62	115.83	C
80.00-60.00			B	0.127	2.857		0.825	1	60.850			
			C	0.127	2.857		0.825	1	60.850			
T16	945.60	15115.36	A	0.122	2.876	11	0.825	1	93.064	3674.93	122.50	C
60.00-30.00			B	0.122	2.876		0.825	1	93.064			
			C	0.122	2.876		0.825	1	93.064			
T17	788.00	17941.94	A	0.117	2.896	12	0.825	1	96.246	3932.18	131.07	C
30.00-0.00			B	0.117	2.896		0.825	1	96.246			
			C	0.117	2.896		0.825	1	96.246			
Sum Weight:	6658.09	125382.28						OTM	4100.70 kip-ft	30773.65		

Tower Forces - Service - Wind 60 To Face

Section Elevation ft	Add Weight lb	Self Weight lb	F a c e	e	C _F	q _z psf	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
T1	15.90	1442.07	A	0.209	2.566	13	0.8	1	14.302	428.66	26.79	C
320.00-304.00			B	0.209	2.566		0.8	1	14.302			
			C	0.209	2.566		0.8	1	14.302			
T2	4.36	349.72	A	0.201	2.592	13	0.8	1	3.373	102.82	25.70	C
304.00-300.00			B	0.201	2.592		0.8	1	3.373			
			C	0.201	2.592		0.8	1	3.373			
T3	40.00	2496.34	A	0.207	2.573	12	0.8	1	20.028	628.70	31.43	C
300.00-280.00			B	0.207	2.573		0.8	1	20.028			
			C	0.207	2.573		0.8	1	20.028			
T4	87.48	5067.66	A	0.237	2.476	12	0.8	1	41.171	1225.51	61.28	C
280.00-260.00			B	0.237	2.476		0.8	1	41.171			
			C	0.237	2.476		0.8	1	41.171			
T5	122.62	5409.17	A	0.219	2.532	12	0.8	1	45.494	1406.19	70.31	C
260.00-240.00			B	0.219	2.532		0.8	1	45.494			
			C	0.219	2.532		0.8	1	45.494			
T6	162.20	6484.36	A	0.223	2.52	12	0.8	1	53.521	1653.61	82.68	C
240.00-220.00			B	0.223	2.52		0.8	1	53.521			
			C	0.223	2.52		0.8	1	53.521			
T7	362.40	6406.00	A	0.181	2.66	12	0.8	1	49.270	1767.65	88.38	C
220.00-200.00			B	0.181	2.66		0.8	1	49.270			
			C	0.181	2.66		0.8	1	49.270			
T8	534.20	7298.65	A	0.187	2.641	11	0.8	1	57.477	2109.14	105.46	C
200.00-180.00			B	0.187	2.641		0.8	1	57.477			
			C	0.187	2.641		0.8	1	57.477			
T9	272.46	3730.84	A	0.177	2.675	11	0.8	1	29.491	1078.95	107.90	C
180.00-170.00			B	0.177	2.675		0.8	1	29.491			
			C	0.177	2.675		0.8	1	29.491			
T10	279.59	3785.29	A	0.171	2.694	11	0.8	1	29.994	1099.26	109.93	C

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	53 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
170.00-160.00			B	0.171	2.694		0.8	1	29.994			
			C	0.171	2.694		0.8	1	29.994			
T11	579.39	9608.59	A	0.181	2.661	11	0.8	1	67.649	2370.29	118.51	C
160.00-140.00			B	0.181	2.661		0.8	1	67.649			
			C	0.181	2.661		0.8	1	67.649			
T12	599.08	9975.29	A	0.173	2.69	11	0.8	1	70.190	2438.08	121.90	C
140.00-120.00			B	0.173	2.69		0.8	1	70.190			
			C	0.173	2.69		0.8	1	70.190			
T13	609.33	9144.95	A	0.131	2.844	11	0.8	1	51.085	2031.60	101.58	C
120.00-100.00			B	0.131	2.844		0.8	1	51.085			
			C	0.131	2.844		0.8	1	51.085			
T14	625.08	9675.54	A	0.122	2.876	10	0.8	1	51.928	2083.03	104.15	C
100.00-80.00			B	0.122	2.876		0.8	1	51.928			
			C	0.122	2.876		0.8	1	51.928			
T15	630.40	11450.50	A	0.127	2.857	10	0.8	1	59.507	2282.64	114.13	C
80.00-60.00			B	0.127	2.857		0.8	1	59.507			
			C	0.127	2.857		0.8	1	59.507			
T16	945.60	15115.36	A	0.122	2.876	11	0.8	1	91.051	3621.63	120.72	C
60.00-30.00			B	0.122	2.876		0.8	1	91.051			
			C	0.122	2.876		0.8	1	91.051			
T17	788.00	17941.94	A	0.117	2.896	12	0.8	1	94.209	3872.44	129.08	C
30.00-0.00			B	0.117	2.896		0.8	1	94.209			
			C	0.117	2.896		0.8	1	94.209			
Sum Weight:	6658.09	125382.28						OTM	4016.30 kip-ft	30200.19		

Tower Forces - Service - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	q _z	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb				psf			ft ²	lb	plf	
T1	15.90	1442.07	A	0.209	2.566	13	0.85	1	14.777	441.73	27.61	C
320.00-304.00			B	0.209	2.566		0.85	1	14.777			
			C	0.209	2.566		0.85	1	14.777			
T2	4.36	349.72	A	0.201	2.592	13	0.85	1	3.481	105.78	26.44	C
304.00-300.00			B	0.201	2.592		0.85	1	3.481			
			C	0.201	2.592		0.85	1	3.481			
T3	40.00	2496.34	A	0.207	2.573	12	0.85	1	20.658	645.78	32.29	C
300.00-280.00			B	0.207	2.573		0.85	1	20.658			
			C	0.207	2.573		0.85	1	20.658			
T4	87.48	5067.66	A	0.237	2.476	12	0.85	1	43.745	1291.71	64.59	C
280.00-260.00			B	0.237	2.476		0.85	1	43.745			
			C	0.237	2.476		0.85	1	43.745			
T5	122.62	5409.17	A	0.219	2.532	12	0.85	1	48.338	1479.82	73.99	C
260.00-240.00			B	0.219	2.532		0.85	1	48.338			
			C	0.219	2.532		0.85	1	48.338			
T6	162.20	6484.36	A	0.223	2.52	12	0.85	1	56.866	1738.35	86.92	C
240.00-220.00			B	0.223	2.52		0.85	1	56.866			
			C	0.223	2.52		0.85	1	56.866			
T7	362.40	6406.00	A	0.181	2.66	12	0.85	1	52.350	1848.50	92.42	C
220.00-200.00			B	0.181	2.66		0.85	1	52.350			
			C	0.181	2.66		0.85	1	52.350			
T8	534.20	7298.65	A	0.187	2.641	11	0.85	1	61.069	2201.00	110.05	C

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 54 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section Elevation ft	Add Weight lb	Self Weight lb	F a c e	e	C _F	q _z psf	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
200.00-180.00			B	0.187	2.641		0.85	1	61.069			
			C	0.187	2.641		0.85	1	61.069			
T9	272.46	3730.84	A	0.177	2.675	11	0.85	1	31.334	1125.95	112.60	C
180.00-170.00			B	0.177	2.675		0.85	1	31.334			
			C	0.177	2.675		0.85	1	31.334			
T10	279.59	3785.29	A	0.171	2.694	11	0.85	1	31.869	1146.91	114.69	C
170.00-160.00			B	0.171	2.694		0.85	1	31.869			
			C	0.171	2.694		0.85	1	31.869			
T11	579.39	9608.59	A	0.181	2.661	11	0.85	1	71.877	2474.74	123.74	C
160.00-140.00			B	0.181	2.661		0.85	1	71.877			
			C	0.181	2.661		0.85	1	71.877			
T12	599.08	9975.29	A	0.173	2.69	11	0.85	1	74.577	2545.41	127.27	C
140.00-120.00			B	0.173	2.69		0.85	1	74.577			
			C	0.173	2.69		0.85	1	74.577			
T13	609.33	9144.95	A	0.131	2.844	11	0.85	1	53.368	2089.63	104.48	C
120.00-100.00			B	0.131	2.844		0.85	1	53.368			
			C	0.131	2.844		0.85	1	53.368			
T14	625.08	9675.54	A	0.122	2.876	10	0.85	1	54.211	2141.05	107.05	C
100.00-80.00			B	0.122	2.876		0.85	1	54.211			
			C	0.122	2.876		0.85	1	54.211			
T15	630.40	11450.50	A	0.127	2.857	10	0.85	1	62.192	2350.60	117.53	C
80.00-60.00			B	0.127	2.857		0.85	1	62.192			
			C	0.127	2.857		0.85	1	62.192			
T16	945.60	15115.36	A	0.122	2.876	11	0.85	1	95.078	3728.24	124.27	C
60.00-30.00			B	0.122	2.876		0.85	1	95.078			
			C	0.122	2.876		0.85	1	95.078			
T17	788.00	17941.94	A	0.117	2.896	12	0.85	1	98.283	3991.93	133.06	C
30.00-0.00			B	0.117	2.896		0.85	1	98.283			
			C	0.117	2.896		0.85	1	98.283			
Sum Weight:	6658.09	125382.28						OTM	4185.09 kip-ft	31347.11		

Force Totals

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M _x kip-ft	Sum of Overturning Moments, M _z kip-ft	Sum of Torques kip-ft
Leg Weight	73044.53					
Bracing Weight	52337.75					
Total Member Self-Weight	125382.28			41.10	-24.20	
Total Weight	140969.55			41.10	-24.20	
Wind 0 deg - No Ice		0.00	-219580.39	-31754.83	-24.20	302.27
Wind 30 deg - No Ice		100423.68	-173938.92	-25107.46	-14543.73	379.42
Wind 45 deg - No Ice		139812.83	-139812.83	-20167.72	-20233.01	380.12
Wind 60 deg - No Ice		168531.16	-97301.51	-14018.95	-24376.92	354.91
Wind 90 deg - No Ice		200847.37	0.00	41.10	-29063.25	235.30
Wind 120 deg - No Ice		190162.19	109790.19	15939.06	-27560.28	52.65
Wind 135 deg - No Ice		148643.66	148643.66	21549.52	-21532.61	-47.35
Wind 150 deg - No Ice		100423.68	173938.92	25189.66	-14543.73	-144.12
Wind 180 deg - No Ice		0.00	194603.03	28161.20	-24.20	-302.27
Wind 210 deg - No Ice		-100423.68	173938.92	25189.66	14495.33	-379.42
Wind 225 deg - No Ice		-139812.83	139812.83	20249.92	20184.62	-380.12
Wind 240 deg - No Ice		-190162.19	109790.19	15939.06	27511.88	-354.91

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 55 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M_x kip-ft	Sum of Overturning Moments, M_z kip-ft	Sum of Torques kip-ft
Wind 270 deg - No Ice		-200847.37	0.00	41.10	29014.86	-235.30
Wind 300 deg - No Ice		-168531.16	-97301.51	-14018.95	24328.53	-52.65
Wind 315 deg - No Ice		-139812.83	-139812.83	-20167.72	20184.62	47.35
Wind 330 deg - No Ice		-100423.68	-173938.92	-25107.46	14495.33	144.12
Member Ice	91680.66					
Total Weight Ice	296443.88			303.26	-322.75	
Wind 0 deg - Ice		0.00	-45928.95	-6228.73	-322.75	118.70
Wind 30 deg - Ice		21754.17	-37679.33	-5049.88	-3413.38	150.09
Wind 45 deg - Ice		30479.77	-30479.77	-4026.23	-4652.23	150.82
Wind 60 deg - Ice		36980.56	-21350.73	-2728.92	-5574.64	141.27
Wind 90 deg - Ice		43508.34	0.00	303.26	-6504.02	94.59
Wind 120 deg - Ice		39775.63	22964.47	3569.25	-5979.62	22.57
Wind 135 deg - Ice		31620.85	31620.85	4798.08	-4817.56	-17.04
Wind 150 deg - Ice		21754.17	37679.33	5656.40	-3413.38	-55.50
Wind 180 deg - Ice		0.00	42701.47	6367.62	-322.75	-118.70
Wind 210 deg - Ice		-21754.17	37679.33	5656.40	2767.89	-150.09
Wind 225 deg - Ice		-30479.77	30479.77	4632.74	4006.74	-150.82
Wind 240 deg - Ice		-39775.63	22964.47	3569.25	5334.12	-141.27
Wind 270 deg - Ice		-43508.34	0.00	303.26	5858.52	-94.59
Wind 300 deg - Ice		-36980.56	-21350.73	-2728.92	4929.15	-22.57
Wind 315 deg - Ice		-30479.77	-30479.77	-4026.23	4006.74	17.04
Wind 330 deg - Ice		-21754.17	-37679.33	-5049.88	2767.89	55.50
Total Weight	140969.55			41.10	-24.20	
Wind 0 deg - Service		0.00	-40331.09	-5837.99	10.85	55.52
Wind 30 deg - Service		18445.17	-31947.97	-4617.04	-2656.01	69.69
Wind 45 deg - Service		25679.91	-25679.91	-3709.74	-3700.98	69.82
Wind 60 deg - Service		30954.70	-17871.71	-2580.38	-4462.10	65.19
Wind 90 deg - Service		36890.33	0.00	2.08	-5322.86	43.22
Wind 120 deg - Service		34927.75	20165.55	2922.12	-5046.80	9.67
Wind 135 deg - Service		27301.90	27301.90	3952.61	-3939.68	-8.70
Wind 150 deg - Service		18445.17	31947.97	4621.21	-2656.01	-26.47
Wind 180 deg - Service		0.00	35743.41	5167.00	10.85	-55.52
Wind 210 deg - Service		-18445.17	31947.97	4621.21	2677.70	-69.69
Wind 225 deg - Service		-25679.91	25679.91	3713.91	3722.67	-69.82
Wind 240 deg - Service		-34927.75	20165.55	2922.12	5068.49	-65.19
Wind 270 deg - Service		-36890.33	0.00	2.08	5344.55	-43.22
Wind 300 deg - Service		-30954.70	-17871.71	-2580.38	4483.80	-9.67
Wind 315 deg - Service		-25679.91	-25679.91	-3709.74	3722.67	8.70
Wind 330 deg - Service		-18445.17	-31947.97	-4617.04	2677.70	26.47

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 45 deg - No Ice
7	0.9 Dead+1.0 Wind 45 deg - No Ice
8	1.2 Dead+1.0 Wind 60 deg - No Ice
9	0.9 Dead+1.0 Wind 60 deg - No Ice
10	1.2 Dead+1.0 Wind 90 deg - No Ice
11	0.9 Dead+1.0 Wind 90 deg - No Ice
12	1.2 Dead+1.0 Wind 120 deg - No Ice

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	56 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

<i>Comb. No.</i>	<i>Description</i>
13	0.9 Dead+1.0 Wind 120 deg - No Ice
14	1.2 Dead+1.0 Wind 135 deg - No Ice
15	0.9 Dead+1.0 Wind 135 deg - No Ice
16	1.2 Dead+1.0 Wind 150 deg - No Ice
17	0.9 Dead+1.0 Wind 150 deg - No Ice
18	1.2 Dead+1.0 Wind 180 deg - No Ice
19	0.9 Dead+1.0 Wind 180 deg - No Ice
20	1.2 Dead+1.0 Wind 210 deg - No Ice
21	0.9 Dead+1.0 Wind 210 deg - No Ice
22	1.2 Dead+1.0 Wind 225 deg - No Ice
23	0.9 Dead+1.0 Wind 225 deg - No Ice
24	1.2 Dead+1.0 Wind 240 deg - No Ice
25	0.9 Dead+1.0 Wind 240 deg - No Ice
26	1.2 Dead+1.0 Wind 270 deg - No Ice
27	0.9 Dead+1.0 Wind 270 deg - No Ice
28	1.2 Dead+1.0 Wind 300 deg - No Ice
29	0.9 Dead+1.0 Wind 300 deg - No Ice
30	1.2 Dead+1.0 Wind 315 deg - No Ice
31	0.9 Dead+1.0 Wind 315 deg - No Ice
32	1.2 Dead+1.0 Wind 330 deg - No Ice
33	0.9 Dead+1.0 Wind 330 deg - No Ice
34	1.2 Dead+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 45 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
39	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
40	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
41	1.2 Dead+1.0 Wind 135 deg+1.0 Ice+1.0 Temp
42	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
43	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
44	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
45	1.2 Dead+1.0 Wind 225 deg+1.0 Ice+1.0 Temp
46	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
47	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
48	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
49	1.2 Dead+1.0 Wind 315 deg+1.0 Ice+1.0 Temp
50	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
51	Dead+Wind 0 deg - Service
52	Dead+Wind 30 deg - Service
53	Dead+Wind 45 deg - Service
54	Dead+Wind 60 deg - Service
55	Dead+Wind 90 deg - Service
56	Dead+Wind 120 deg - Service
57	Dead+Wind 135 deg - Service
58	Dead+Wind 150 deg - Service
59	Dead+Wind 180 deg - Service
60	Dead+Wind 210 deg - Service
61	Dead+Wind 225 deg - Service
62	Dead+Wind 240 deg - Service
63	Dead+Wind 270 deg - Service
64	Dead+Wind 300 deg - Service
65	Dead+Wind 315 deg - Service
66	Dead+Wind 330 deg - Service

Maximum Member Forces

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	57 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft		
T1	320 - 304	Leg	Max Tension	29	5560.81	0.04	0.02		
			Max. Compression	24	-7158.84	-0.01	-0.00		
			Max. Mx	24	-1514.78	-0.14	-0.00		
			Max. My	3	328.15	-0.01	-0.17		
			Max. Vy	10	-475.10	0.00	0.00		
		Diagonal	Max. Vx	3	536.64	0.00	0.00		
			Max Tension	20	1340.49	0.00	0.00		
			Max. Compression	4	-1332.71	0.00	0.00		
			Max. Mx	40	327.23	0.02	-0.00		
			Max. My	20	-702.07	0.00	-0.00		
		Top Girt	Max. Vy	40	-20.09	0.02	-0.00		
			Max. Vx	20	0.12	0.00	-0.00		
			Max Tension	13	182.36	0.00	0.00		
			Max. Compression	8	-193.80	0.00	0.00		
			Max. Mx	34	-30.30	-0.05	0.00		
T2	304 - 300	Leg	Max. Vy	34	-32.08	0.00	0.00		
			Max Tension	29	7856.49	0.01	0.00		
			Max. Compression	24	-9868.54	0.32	-0.07		
			Max. Mx	24	-9868.54	0.32	-0.07		
			Max. My	2	-9841.92	0.09	0.31		
		Diagonal	Max. Vy	24	-137.12	0.32	-0.07		
			Max. Vx	2	-138.72	0.09	0.31		
			Max Tension	4	1557.70	0.00	0.00		
			Max. Compression	4	-1579.36	0.00	0.00		
			Max. Mx	40	332.57	0.02	-0.00		
		T3	300 - 280	Leg	Max. My	19	1290.15	0.00	-0.00
					Max. Vy	40	-20.08	0.02	-0.00
					Max. Vx	19	0.04	0.00	0.00
					Max Tension	29	21875.75	-0.16	-0.01
					Max. Compression	24	-27182.05	0.53	-0.00
Diagonal	Max. Mx			3	-26381.77	0.53	0.14		
	Max. My			32	-2347.87	-0.00	0.57		
	Max. Vy			2	331.75	0.31	-0.09		
	Max. Vx			16	-519.38	0.02	0.11		
	Max Tension			4	3067.24	0.00	0.00		
Top Girt	Max. Compression			2	-3094.91	0.00	0.00		
	Max. Mx			48	473.04	0.03	0.00		
	Max. My			35	403.14	0.03	0.00		
	Max. Vy			48	31.15	0.03	0.00		
	Max. Vx			35	-1.72	0.00	0.00		
T4	280 - 260	Leg	Max Tension	23	49.59	0.00	0.00		
			Max. Compression	28	-69.63	0.00	0.00		
			Max. Mx	34	-22.49	-0.07	0.00		
			Max. My	34	-20.76	0.00	0.00		
			Max. Vy	34	-38.34	0.00	0.00		
		Diagonal	Max. Vx	34	-1.13	0.00	0.00		
			Max Tension	29	40944.14	-0.33	0.00		
			Max. Compression	24	-51734.45	0.81	-0.11		
			Max. Mx	13	-50459.49	0.82	-0.03		
			Max. My	2	19430.11	-0.43	0.81		
		Top Girt	Max. Vy	3	-366.00	0.82	0.14		
			Max. Vx	20	-351.39	-0.02	0.55		
			Max Tension	10	4727.40	0.00	0.00		
			Max. Compression	12	-4796.71	0.00	0.00		
			Max. Mx	43	756.06	0.06	-0.01		
T5	260 - 240	Leg	Max. My	39	-1169.32	0.06	-0.01		
			Max. Vy	43	46.35	0.06	-0.01		
			Max. Vx	39	2.72	0.00	0.00		
			Max Tension	19	67823.87	-0.31	-0.36		
			Max. Compression	12	-87475.45	2.38	-0.08		
		Diagonal	Max. Mx	24	-86845.34	2.39	0.48		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	58 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T6	240 - 220	Diagonal	Max. My	20	-7153.89	-0.00	2.96
			Max. Vy	28	-751.44	-0.31	-0.05
			Max. Vx	4	-1317.00	-0.02	0.43
			Max Tension	26	8221.24	0.00	0.00
			Max. Compression	24	-8485.37	0.00	0.00
			Max. Mx	43	930.06	0.09	0.01
			Max. My	37	-1547.57	0.09	-0.01
		Leg	Max. Vy	43	63.73	0.09	0.01
			Max. Vx	37	3.58	0.00	0.00
			Max Tension	9	108740.08	-1.06	0.02
			Max. Compression	12	-140782.81	2.49	0.02
			Max. Mx	3	-137503.27	2.49	-0.28
			Max. My	20	-7376.21	-0.00	2.96
			Max. Vy	28	-2230.91	-1.11	-0.07
T7	220 - 200	Diagonal	Max. Vx	4	-2199.34	-0.06	-0.54
			Max Tension	32	13356.61	0.00	0.00
			Max. Compression	32	-13340.73	0.00	0.00
			Max. Mx	38	1495.90	0.17	-0.02
			Max. My	36	-1362.50	0.15	-0.02
			Max. Vy	38	102.65	0.17	-0.02
			Max. Vx	36	5.65	0.00	0.00
		Leg	Max Tension	9	154356.83	-1.00	-0.19
			Max. Compression	12	-197088.03	2.20	-0.05
			Max. Mx	3	-161869.85	2.49	-0.28
			Max. My	4	-12211.58	-0.12	-2.77
			Max. Vy	25	578.35	2.49	0.26
			Max. Vx	4	-854.09	-0.12	-2.77
			Max Tension	32	16638.54	0.00	0.00
T8	200 - 180	Diagonal	Max. Compression	2	-17336.79	0.00	0.00
			Max. Mx	37	1988.01	0.25	-0.04
			Max. My	36	2424.80	0.24	-0.04
			Max. Vy	37	126.22	0.25	-0.04
			Max. Vx	36	7.25	0.00	0.00
			Max Tension	9	211192.74	-2.14	-0.12
			Max. Compression	12	-268188.30	3.20	-0.03
		Leg	Max. Mx	12	-268188.30	3.20	-0.03
			Max. My	4	-16729.75	-0.10	-3.19
			Max. Vy	28	-2977.71	-1.80	0.05
			Max. Vx	4	-3090.13	0.04	0.16
			Max Tension	32	21122.30	0.00	0.00
			Max. Compression	2	-21398.23	0.00	0.00
			Max. Mx	38	2312.35	0.31	-0.05
T9	180 - 170	Diagonal	Max. My	44	-2458.59	0.27	0.05
			Max. Vy	38	140.95	0.31	-0.05
			Max. Vx	44	-8.18	0.00	0.00
			Max Tension	19	241098.72	-2.81	0.14
			Max. Compression	12	-305049.56	2.06	-0.02
			Max. Mx	12	-303785.50	3.20	-0.03
			Max. My	20	-18358.01	0.00	2.13
		Leg	Max. Vy	3	741.31	3.19	-0.14
			Max. Vx	25	791.51	-1.60	2.09
			Max Tension	26	22538.90	0.00	0.00
			Max. Compression	24	-22966.30	0.00	0.00
			Max. Mx	43	2494.57	0.34	0.05
			Max. My	44	-3782.64	0.32	0.05
			Max. Vy	43	147.90	0.34	0.05
T10	170 - 160	Leg	Max. Vx	44	-8.29	0.00	0.00
			Max Tension	19	271340.19	-2.03	0.04
			Max. Compression	12	-342203.08	7.46	-0.23
			Max. Mx	12	-342203.08	7.46	-0.23
			Max. My	4	-21164.18	0.15	-5.30

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	59 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft			
T11	160 - 140	Diagonal	Max. Vy	2	-1057.53	7.45	-0.48			
			Max. Vx	25	-940.41	-3.54	5.11			
			Max Tension	26	23244.04	0.00	0.00			
			Max. Compression	24	-23824.32	0.00	0.00			
			Max. Mx	43	2479.56	0.37	0.05			
			Max. My	36	-2815.73	0.33	-0.05			
		Leg	Max. Vy	43	155.08	0.37	0.05			
			Max. Vx	36	8.57	0.00	0.00			
			Max Tension	19	335017.11	-2.30	-0.26			
			Max. Compression	12	-421749.57	5.97	-0.06			
			Max. Mx	12	-379951.12	7.46	-0.23			
			Max. My	4	-22007.85	0.15	-5.30			
			Max. Vy	2	1312.06	7.45	-0.48			
			Max. Vx	15	-1005.34	-1.70	-4.73			
Diagonal	Max Tension	26	28272.93	0.00	0.00					
	Max. Compression	24	-29160.72	0.00	0.00					
	Max. Mx	43	2903.01	0.62	0.08					
	Max. My	45	4017.97	0.61	0.08					
	Max. Vy	43	241.62	0.62	0.08					
	Max. Vx	45	-12.19	0.00	0.00					
T12	140 - 120	Leg	Max Tension	19	399043.02	-2.97	0.08			
			Max. Compression	12	-502759.06	-2.50	0.32			
			Max. Mx	12	-462356.20	5.97	-0.06			
			Max. My	10	-27250.50	-1.05	6.96			
			Max. Vy	2	1033.46	3.06	-0.08			
			Max. Vx	20	-1140.32	-0.20	5.72			
		Diagonal	Max Tension	26	29995.87	0.00	0.00			
			Max. Compression	24	-30916.27	0.00	0.00			
			Max. Mx	42	4915.78	0.73	-0.10			
			Max. My	45	3076.63	0.73	0.11			
			Max. Vy	42	263.06	0.73	-0.10			
			Max. Vx	45	-14.93	0.00	0.00			
			T13	120 - 100	Leg	Max Tension	19	409801.75	0.50	0.18
						Max. Compression	12	-519177.58	-15.28	0.48
Max. Mx	12	-518428.83				22.21	-0.11			
Max. My	20	-32358.18				-2.48	14.26			
Max. Vy	24	4917.88				22.18	-0.86			
Max. Vx	20	-2837.45				-2.48	14.26			
Diagonal	Max Tension	27			48086.93	-0.23	-0.04			
	Max. Compression	24			-50783.82	0.00	0.00			
	Max. Mx	16			22512.75	-0.37	0.05			
	Max. My	26			-49411.20	-0.15	-0.19			
	Max. Vy	42			-131.63	-0.32	-0.00			
	Max. Vx	26			15.19	-0.15	-0.19			
	Horizontal	Max Tension			26	26754.51	-0.19	0.00		
		Max. Compression			25	-27066.70	-0.19	-0.03		
Max. Mx		43	-1338.96	-0.37	-0.01					
Max. My		2	3536.51	-0.11	0.06					
Max. Vy		43	136.22	-0.37	-0.01					
Max. Vx		2	-4.92	0.00	0.00					
Redund Horiz 1 Bracing	Max Tension	12	9017.86	0.00	0.00					
	Max. Compression	12	-9017.86	0.00	0.00					
	Max. Mx	34	1223.16	0.04	0.00					
	Max. Vy	34	-26.75	0.00	0.00					
Redund Diag 1 Bracing	Max Tension	12	8181.56	0.00	0.00					
	Max. Compression	12	-8181.56	0.00	0.00					
	Max. Mx	34	890.36	0.08	0.00					
Redund Hip 1	Max. Vy	34	-29.47	0.00	0.00					
	Max. Vx	34	-29.47	0.00	0.00					
	Max Tension	27	23.19	0.00	0.00					

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	60 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T14	100 - 80	Bracing	Max. Compression	10	-49.03	0.00	0.00
			Max. Mx	34	-20.79	0.04	0.00
			Max. Vy	34	26.75	0.00	0.00
		Redund Hip Diagonal 1 Bracing	Max Tension	2	98.62	0.00	0.00
			Max. Compression	18	-97.06	0.00	0.00
			Max. Mx	34	63.17	0.30	0.00
		Inner Bracing	Max. Vy	34	77.92	0.00	0.00
			Max Tension	27	7.51	0.00	0.00
			Max. Compression	2	-27.79	0.00	0.00
		Leg	Max. Mx	34	-19.45	0.34	0.00
			Max. Vy	34	-106.85	0.00	0.00
			Max Tension	19	464451.86	9.57	1.51
		Diagonal	Max. Compression	12	-589433.90	-17.70	-0.31
			Max. Mx	12	-588279.81	25.48	0.11
			Max. My	20	-36383.72	-2.71	14.87
			Max. Vy	12	4700.00	25.48	0.11
			Max. Vx	20	-2730.41	-2.71	14.87
			Max Tension	27	49547.23	-0.27	-0.04
			Max. Compression	24	-53199.63	0.00	0.00
			Max. Mx	26	18719.65	-0.42	0.05
			Max. My	26	-48713.47	-0.16	-0.18
			Max. Vy	43	143.17	-0.36	0.01
			Max. Vx	26	-14.36	-0.16	-0.18
			Horizontal	Max Tension	26	29223.73	-0.31
		Max. Compression		24	-30467.61	-0.36	-0.03
		Max. Mx		43	743.19	-0.53	-0.01
		Max. My		2	5687.95	-0.22	0.06
		Max. Vy		43	-177.28	-0.53	-0.01
		Redund Horz 1 Bracing	Max. Vx	2	-4.57	0.00	0.00
			Max Tension	12	10238.44	0.00	0.00
			Max. Compression	12	-10238.44	0.00	0.00
			Max. Mx	34	1367.05	0.05	0.00
			Max. Vy	34	29.23	0.00	0.00
			Max Tension	12	8683.21	0.00	0.00
		Redund Diag 1 Bracing	Max. Compression	12	-8683.21	0.00	0.00
			Max. Mx	34	927.65	0.11	0.00
			Max. Vy	34	37.97	0.00	0.00
		Redund Hip 1 Bracing	Max Tension	27	21.08	0.00	0.00
			Max. Compression	2	-48.04	0.00	0.00
			Max. Mx	34	-21.46	0.05	0.00
		Redund Hip Diagonal 1 Bracing	Max. Vy	34	-29.23	0.00	0.00
			Max Tension	2	91.43	0.00	0.00
			Max. Compression	18	-91.08	0.00	0.00
			Max. Mx	34	62.80	0.34	0.00
			Max. Vy	34	-84.96	0.00	0.00
Max Tension	27		4.00	0.00	0.00		
Inner Bracing	Max. Compression	2	-27.56	0.00	0.00		
	Max. Mx	34	-21.07	0.41	0.00		
	Max. Vy	34	-117.08	0.00	0.00		
Leg	Max Tension	19	520587.93	11.42	1.74		
	Max. Compression	12	-661019.72	-24.37	-0.29		
	Max. Mx	12	-660593.98	33.36	0.21		
	Max. My	20	-40983.33	-3.86	20.53		
	Max. Vy	12	6220.59	33.36	0.21		
	Max. Vx	20	-3474.39	-3.86	20.53		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	61 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft	
T16	60 - 30	Diagonal	Max Tension	27	48472.57	-0.30	-0.04	
			Max. Compression	24	-53145.46	0.00	0.00	
			Max. Mx	26	22470.42	-0.43	0.04	
			Max. My	26	-47627.31	-0.19	-0.16	
			Max. Vy	43	155.52	-0.41	0.00	
			Max. Vx	26	-12.66	0.00	0.00	
			Horizontal	Max Tension	27	29908.38	-0.49	0.00
				Max. Compression	24	-31433.58	-0.72	-0.03
				Max. Mx	43	750.31	-0.92	-0.01
				Max. My	2	6187.62	-0.54	0.05
				Max. Vy	43	-287.97	-0.92	-0.01
			Redund Horz 1 Bracing	Max. Vx	2	-3.32	0.00	0.00
		Max Tension		12	11487.45	0.00	0.00	
		Max. Compression		12	-11487.45	0.00	0.00	
		Redund Diag 1 Bracing	Max. Mx	34	1534.79	0.07	0.00	
			Max. Vy	34	38.83	0.00	0.00	
			Max Tension	12	9186.98	0.00	0.00	
		Redund Hip 1 Bracing	Max. Compression	12	-9186.98	0.00	0.00	
			Max. Mx	34	966.49	0.13	0.00	
			Max. Vy	34	-41.29	0.00	0.00	
		Redund Hip Diagonal 1 Bracing	Max Tension	27	15.69	0.00	0.00	
			Max. Compression	2	-47.06	0.00	0.00	
			Max. Mx	34	-25.16	0.06	0.00	
		Inner Bracing	Max. Vy	34	31.69	0.00	0.00	
			Max Tension	2	93.77	0.00	0.00	
			Max. Compression	47	-102.08	0.00	0.00	
		Leg	Max. Mx	34	76.38	0.48	0.00	
			Max. Vy	34	-113.44	0.00	0.00	
			Max Tension	1	0.00	0.00	0.00	
			Max. Compression	2	-31.26	0.00	0.00	
			Max. Mx	34	-27.89	0.48	0.00	
			Max. Vy	34	-127.12	0.00	0.00	
			Diagonal	Max Tension	19	576220.65	15.44	1.82
				Max. Compression	12	-733001.56	6.15	0.31
				Max. Mx	12	-723548.72	37.54	0.38
				Max. My	4	-46808.12	-5.58	-36.87
				Max. Vy	12	6843.83	37.54	0.38
				Max. Vx	4	5536.99	-5.58	-36.87
		Horizontal	Max Tension	27	68306.43	-0.37	-0.08	
			Max. Compression	24	-75010.27	0.00	0.00	
			Max. Mx	18	50379.42	-0.51	0.38	
			Max. My	26	-70968.42	0.25	-0.68	
Max. Vy	24		-113.76	-0.33	0.43			
Redund Horz 1 Bracing	Max. Vx	24	93.24	-0.33	0.43			
	Max Tension	10	34937.72	0.00	0.00			
	Max. Compression	25	-35097.16	-0.49	-0.04			
	Max. Mx	43	-1777.71	-0.88	-0.01			
	Max. My	3	-1810.63	-0.23	0.08			
	Max. Vy	43	246.92	-0.88	-0.01			
	Max. Vx	3	-4.74	0.00	0.00			
	Max Tension	12	12749.79	0.00	0.00			
	Max. Compression	12	-12749.79	0.00	0.00			
	Max. Mx	34	1733.48	0.03	0.00			
Redund Horz 2 Bracing	Max. Vy	34	23.02	0.00	0.00			
	Max Tension	12	12749.79	0.00	0.00			

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	62 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
			Max. Compression	12	-12749.79	0.00	0.00
			Max. Mx	34	1733.48	0.25	0.00
			Max. Vy	34	-92.06	0.00	0.00
		Redund Diag 1 Bracing	Max Tension	12	12866.07	0.00	0.00
			Max. Compression	12	-12866.07	0.00	0.00
			Max. Mx	34	1670.30	0.08	0.00
			Max. Vy	34	29.25	0.00	0.00
		Redund Diag 2 Bracing	Max Tension	12	8343.82	0.00	0.00
			Max. Compression	12	-8343.82	0.00	0.00
			Max. Mx	34	1007.32	0.26	0.00
			Max. Vy	34	70.87	0.00	0.00
		Redund Hip 1 Bracing	Max Tension	25	170.36	0.00	0.00
			Max. Compression	10	-175.83	0.00	0.00
			Max. Mx	34	-9.42	0.03	0.00
			Max. Vy	34	23.02	0.00	0.00
		Redund Hip 2 Bracing	Max Tension	25	70.64	0.00	0.00
			Max. Compression	10	-95.51	0.00	0.00
			Max. Mx	34	-26.66	0.16	0.00
			Max. Vy	34	56.40	0.00	0.00
		Redund Hip Diagonal 1 Bracing	Max Tension	2	355.70	0.00	0.00
			Max. Compression	26	-360.74	0.00	0.00
			Max. Mx	34	44.35	0.18	0.00
			Max. Vy	34	-50.73	0.00	0.00
		Redund Hip Diagonal 2 Bracing	Max Tension	8	121.92	0.00	0.00
			Max. Compression	24	-143.01	0.00	0.00
			Max. Mx	34	42.80	0.34	0.00
			Max. Vy	34	-75.86	0.00	0.00
		Inner Bracing	Max Tension	25	44.22	0.00	0.00
			Max. Compression	8	-60.20	0.00	0.00
			Max. Mx	34	-21.10	0.57	0.00
			Max. Vy	34	-138.41	0.00	0.00
T17	30 - 0	Leg	Max Tension	19	660100.96	14.44	5.02
			Max. Compression	12	-840602.01	4.53	0.39
			Max. Mx	12	-835570.26	33.50	0.55
			Max. My	4	-50787.04	-5.57	-36.86
			Max. Vy	12	3852.48	33.50	0.55
			Max. Vx	4	-5372.16	-5.57	-36.86
		Diagonal	Max Tension	27	69597.19	-0.30	-0.07
			Max. Compression	24	-73992.17	0.00	0.00
			Max. Mx	18	44073.53	-0.46	0.32
			Max. My	26	-71697.10	0.14	-0.62
			Max. Vy	47	114.83	-0.27	0.07
			Max. Vx	24	82.30	-0.35	0.40
		Horizontal	Max Tension	11	37602.54	0.00	0.00
			Max. Compression	24	-41666.25	-0.88	-0.06
			Max. Mx	43	75.18	-1.17	-0.02
			Max. My	2	10914.72	-0.59	0.11
			Max. Vy	43	-313.91	-1.17	-0.02
			Max. Vx	2	6.14	-0.59	0.11
		Redund Horz 1 Bracing	Max Tension	12	14642.70	0.00	0.00
			Max. Compression	12	-14642.70	0.00	0.00
			Max. Mx	34	2050.43	0.04	0.00
			Max. Vy	34	-25.64	0.00	0.00
		Redund Horz 2	Max Tension	12	14642.70	0.00	0.00

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	63 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
		Bracing	Max. Compression	12	-14642.70	0.00	0.00
			Max. Mx	34	2009.98	0.30	0.00
			Max. Vy	34	-97.22	0.00	0.00
		Redund Diag 1 Bracing	Max Tension	12	13622.05	0.00	0.00
			Max. Compression	12	-13622.05	0.00	0.00
			Max. Mx	34	1495.69	0.11	0.00
			Max. Vy	34	37.41	0.00	0.00
		Redund Diag 2 Bracing	Max Tension	12	9151.97	0.00	0.00
			Max. Compression	12	-9151.97	0.00	0.00
			Max. Mx	34	1256.86	0.30	0.00
			Max. Vy	34	-79.09	0.00	0.00
		Redund Hip 1 Bracing	Max Tension	25	147.06	0.00	0.00
			Max. Compression	10	-157.40	0.00	0.00
			Max. Mx	34	-13.27	0.04	0.00
			Max. Vy	34	-25.64	0.00	0.00
		Redund Hip 2 Bracing	Max Tension	25	61.66	0.00	0.00
			Max. Compression	10	-89.81	0.00	0.00
			Max. Mx	34	-29.27	0.19	0.00
			Max. Vy	34	-62.81	0.00	0.00
		Redund Hip Diagonal 1 Bracing	Max Tension	2	322.57	0.00	0.00
			Max. Compression	26	-327.41	0.00	0.00
			Max. Mx	34	60.79	0.28	0.00
			Max. Vy	34	-74.96	0.00	0.00
		Redund Hip Diagonal 2 Bracing	Max Tension	8	118.01	0.00	0.00
			Max. Compression	24	-140.44	0.00	0.00
			Max. Mx	34	57.40	0.54	0.00
			Max. Vy	34	-112.18	0.00	0.00
		Inner Bracing	Max Tension	25	40.14	0.00	0.00
			Max. Compression	8	-62.56	0.00	0.00
			Max. Mx	34	-26.37	0.71	0.00
			Max. Vy	34	-154.05	0.00	0.00

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Leg C	Max. Vert	24	941233.11	114498.12	-60257.08
	Max. H _x	24	941233.11	114498.12	-60257.08
	Max. H _z	7	-725346.34	-90380.52	51955.00
	Min. Vert	9	-739546.23	-94548.82	48798.33
	Min. H _x	9	-739546.23	-94548.82	48798.33
	Min. H _z	24	941233.11	114498.12	-60257.08
Leg B	Max. Vert	12	942660.34	-112367.47	-63996.74
	Max. H _x	29	-738475.81	92393.22	52494.45
	Max. H _z	33	-656038.05	75823.87	57870.91
	Min. Vert	29	-738475.81	92393.22	52494.45
	Min. H _x	12	942660.34	-112367.47	-63996.74
	Min. H _z	14	875188.89	-100782.77	-65284.11
Leg A	Max. Vert	2	939847.33	4301.48	129260.89

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	64 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
	Max. H _x	26	54988.22	16975.21	4988.02
	Max. H _z	2	939847.33	4301.48	129260.89
	Min. Vert	19	-740585.57	-4276.54	-106299.85
	Min. H _x	13	-401188.39	-18393.74	-58393.94
	Min. H _z	19	-740585.57	-4276.54	-106299.85

Tower Mast Reaction Summary

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	140969.55	0.00	0.00	41.10	-24.20	0.00
1.2 Dead+1.0 Wind 0 deg - No Ice	169163.46	-0.00	-219580.40	-31131.85	-29.04	302.27
0.9 Dead+1.0 Wind 0 deg - No Ice	126872.60	-0.00	-219580.40	-31144.18	-21.78	302.27
1.2 Dead+1.0 Wind 30 deg - No Ice	169163.46	100423.69	-173938.94	-24596.15	-14258.11	379.43
0.9 Dead+1.0 Wind 30 deg - No Ice	126872.60	100423.69	-173938.94	-24608.48	-14250.85	379.43
1.2 Dead+1.0 Wind 45 deg - No Ice	169163.46	139812.84	-139812.84	-19752.71	-19831.07	380.12
0.9 Dead+1.0 Wind 45 deg - No Ice	126872.60	139812.84	-139812.84	-19765.04	-19823.81	380.12
1.2 Dead+1.0 Wind 60 deg - No Ice	169163.46	168531.18	-97301.52	-13725.91	-23888.43	354.92
0.9 Dead+1.0 Wind 60 deg - No Ice	126872.60	168531.18	-97301.52	-13738.24	-23881.18	354.92
1.2 Dead+1.0 Wind 90 deg - No Ice	169163.46	200847.38	-0.00	49.32	-28487.17	235.31
0.9 Dead+1.0 Wind 90 deg - No Ice	126872.60	200847.38	-0.00	36.99	-28479.92	235.31
1.2 Dead+1.0 Wind 120 deg - No Ice	169163.46	190162.21	109790.20	15639.91	-27032.72	52.65
0.9 Dead+1.0 Wind 120 deg - No Ice	126872.60	190162.21	109790.20	15627.58	-27025.47	52.65
1.2 Dead+1.0 Wind 135 deg - No Ice	169163.46	148643.67	148643.67	21135.00	-21114.72	-47.35
0.9 Dead+1.0 Wind 135 deg - No Ice	126872.60	148643.67	148643.67	21122.67	-21107.46	-47.35
1.2 Dead+1.0 Wind 150 deg - No Ice	169163.46	100423.69	173938.94	24694.79	-14258.11	-144.12
0.9 Dead+1.0 Wind 150 deg - No Ice	126872.60	100423.69	173938.94	24682.46	-14250.85	-144.12
1.2 Dead+1.0 Wind 180 deg - No Ice	169163.46	0.00	194603.04	27599.78	-29.04	-302.27
0.9 Dead+1.0 Wind 180 deg - No Ice	126872.60	0.00	194603.04	27587.45	-21.78	-302.27
1.2 Dead+1.0 Wind 210 deg - No Ice	169163.46	-100423.69	173938.94	24694.79	14200.03	-379.43
0.9 Dead+1.0 Wind 210 deg - No Ice	126872.60	-100423.69	173938.94	24682.46	14207.29	-379.43
1.2 Dead+1.0 Wind 225 deg - No Ice	169163.46	-139812.84	139812.84	19851.35	19772.99	-380.12
0.9 Dead+1.0 Wind 225 deg - No Ice	126872.60	-139812.84	139812.84	19839.02	19780.25	-380.12
1.2 Dead+1.0 Wind 240 deg - No Ice	169163.46	-190162.21	109790.20	15639.91	26974.65	-354.92

<p style="text-align: center;">tnxTower</p> <p style="text-align: center;">AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	Job	320' Rohn SSMW	Page	65 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
No Ice						
0.9 Dead+1.0 Wind 240 deg - No Ice	126872.60	-190162.21	109790.20	15627.58	26981.91	-354.92
1.2 Dead+1.0 Wind 270 deg - No Ice	169163.46	-200847.38	0.00	49.32	28429.10	-235.31
0.9 Dead+1.0 Wind 270 deg - No Ice	126872.60	-200847.38	0.00	36.99	28436.36	-235.31
1.2 Dead+1.0 Wind 300 deg - No Ice	169163.46	-168531.18	-97301.52	-13725.91	23830.36	-52.65
0.9 Dead+1.0 Wind 300 deg - No Ice	126872.60	-168531.18	-97301.52	-13738.24	23837.62	-52.65
1.2 Dead+1.0 Wind 315 deg - No Ice	169163.46	-139812.84	-139812.84	-19752.71	19772.99	47.35
0.9 Dead+1.0 Wind 315 deg - No Ice	126872.60	-139812.84	-139812.84	-19765.04	19780.25	47.35
1.2 Dead+1.0 Wind 330 deg - No Ice	169163.46	-100423.69	-173938.93	-24596.15	14200.03	144.12
0.9 Dead+1.0 Wind 330 deg - No Ice	126872.60	-100423.69	-173938.93	-24608.48	14207.29	144.12
1.2 Dead+1.0 Ice+1.0 Temp	324637.79	0.00	0.00	311.48	-327.59	0.00
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	324637.79	0.00	-45928.95	-6042.34	-327.59	118.70
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	324637.79	21754.17	-37679.33	-4892.39	-3332.05	150.09
1.2 Dead+1.0 Wind 45 deg+1.0 Ice+1.0 Temp	324637.79	30479.77	-30479.77	-3896.82	-4535.89	150.82
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	324637.79	36980.56	-21350.74	-2635.49	-5431.90	141.27
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	324637.79	43508.34	0.00	311.48	-6336.50	94.59
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	324637.79	39775.64	22964.47	3488.39	-5830.16	22.57
1.2 Dead+1.0 Wind 135 deg+1.0 Ice+1.0 Temp	324637.79	31620.86	31620.86	4682.36	-4698.48	-17.04
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	324637.79	21754.17	37679.33	5515.35	-3332.05	-55.50
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	324637.79	0.00	42701.47	6205.42	-327.59	-118.70
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	324637.79	-21754.17	37679.33	5515.35	2676.86	-150.09
1.2 Dead+1.0 Wind 225 deg+1.0 Ice+1.0 Temp	324637.79	-30479.77	30479.77	4519.77	3880.70	-150.82
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	324637.79	-39775.64	22964.47	3488.39	5174.97	-141.27
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	324637.79	-43508.34	0.00	311.48	5681.32	-94.59
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	324637.79	-36980.56	-21350.74	-2635.49	4776.71	-22.57
1.2 Dead+1.0 Wind 315 deg+1.0 Ice+1.0 Temp	324637.79	-30479.77	-30479.77	-3896.82	3880.70	17.04
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp	324637.79	-21754.17	-37679.33	-4892.39	2676.86	55.50
Dead+Wind 0 deg - Service	140969.55	-0.00	-40331.09	-5686.05	-24.20	55.52
Dead+Wind 30 deg - Service	140969.55	18445.17	-31947.97	-4485.62	-2637.70	69.69
Dead+Wind 45 deg - Service	140969.55	25679.91	-25679.91	-3596.01	-3661.30	69.82
Dead+Wind 60 deg - Service	140969.55	30954.71	-17871.71	-2489.04	-4406.54	65.19
Dead+Wind 90 deg - Service	140969.55	36890.34	-0.00	41.10	-5251.20	43.22
Dead+Wind 120 deg - Service	140969.55	34927.75	20165.55	2904.68	-4984.06	9.67
Dead+Wind 135 deg - Service	140969.55	27301.90	27301.90	3913.98	-3897.08	-8.70
Dead+Wind 150 deg - Service	140969.55	18445.17	31947.97	4567.82	-2637.70	-26.47
Dead+Wind 180 deg - Service	140969.55	0.00	35743.42	5101.39	-24.20	-55.52

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	66 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead+Wind 210 deg - Service	140969.55	-18445.17	31947.97	4567.82	2589.30	-69.69
Dead+Wind 225 deg - Service	140969.55	-25679.91	25679.91	3678.21	3612.91	-69.82
Dead+Wind 240 deg - Service	140969.55	-34927.75	20165.55	2904.68	4935.66	-65.19
Dead+Wind 270 deg - Service	140969.55	-36890.34	0.00	41.10	5202.81	-43.22
Dead+Wind 300 deg - Service	140969.55	-30954.71	-17871.71	-2489.04	4358.14	-9.67
Dead+Wind 315 deg - Service	140969.55	-25679.91	-25679.91	-3596.01	3612.91	8.70
Dead+Wind 330 deg - Service	140969.55	-18445.17	-31947.97	-4485.62	2589.30	26.47

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
1	0.00	-140969.55	0.00	-0.00	140969.55	-0.00	0.000%
2	0.00	-169163.46	-219580.38	0.00	169163.46	219580.40	0.000%
3	0.00	-126872.60	-219580.38	0.00	126872.60	219580.40	0.000%
4	100423.68	-169163.46	-173938.92	-100423.69	169163.46	173938.94	0.000%
5	100423.68	-126872.60	-173938.92	-100423.69	126872.60	173938.94	0.000%
6	139812.83	-169163.46	-139812.83	-139812.84	169163.46	139812.84	0.000%
7	139812.83	-126872.60	-139812.83	-139812.84	126872.60	139812.84	0.000%
8	168531.16	-169163.46	-97301.51	-168531.18	169163.46	97301.52	0.000%
9	168531.16	-126872.60	-97301.51	-168531.18	126872.60	97301.52	0.000%
10	200847.37	-169163.46	0.00	-200847.38	169163.46	0.00	0.000%
11	200847.37	-126872.60	0.00	-200847.38	126872.60	0.00	0.000%
12	190162.19	-169163.46	109790.19	-190162.21	169163.46	-109790.20	0.000%
13	190162.19	-126872.60	109790.19	-190162.21	126872.60	-109790.20	0.000%
14	148643.66	-169163.46	148643.66	-148643.67	169163.46	-148643.67	0.000%
15	148643.66	-126872.60	148643.66	-148643.67	126872.60	-148643.67	0.000%
16	100423.68	-169163.46	173938.92	-100423.69	169163.46	-173938.94	0.000%
17	100423.68	-126872.60	173938.92	-100423.69	126872.60	-173938.94	0.000%
18	-0.00	-169163.46	194603.03	-0.00	169163.46	-194603.04	0.000%
19	-0.00	-126872.60	194603.03	-0.00	126872.60	-194603.04	0.000%
20	-100423.68	-169163.46	173938.92	100423.69	169163.46	-173938.94	0.000%
21	-100423.68	-126872.60	173938.92	100423.69	126872.60	-173938.94	0.000%
22	-139812.83	-169163.46	139812.83	139812.84	169163.46	-139812.84	0.000%
23	-139812.83	-126872.60	139812.83	139812.84	126872.60	-139812.84	0.000%
24	-190162.19	-169163.46	109790.19	190162.21	169163.46	-109790.20	0.000%
25	-190162.19	-126872.60	109790.19	190162.21	126872.60	-109790.20	0.000%
26	-200847.37	-169163.46	0.00	200847.38	169163.46	-0.00	0.000%
27	-200847.37	-126872.60	0.00	200847.38	126872.60	-0.00	0.000%
28	-168531.16	-169163.46	-97301.51	168531.18	169163.46	97301.52	0.000%
29	-168531.16	-126872.60	-97301.51	168531.18	126872.60	97301.52	0.000%
30	-139812.83	-169163.46	-139812.83	139812.84	169163.46	139812.84	0.000%
31	-139812.83	-126872.60	-139812.83	139812.84	126872.60	139812.84	0.000%
32	-100423.68	-169163.46	-173938.92	100423.69	169163.46	173938.93	0.000%
33	-100423.68	-126872.60	-173938.92	100423.69	126872.60	173938.93	0.000%
34	0.00	-324637.79	0.00	-0.00	324637.79	-0.00	0.000%
35	-0.00	-324637.79	-45928.95	-0.00	324637.79	45928.95	0.000%
36	21754.17	-324637.79	-37679.33	-21754.17	324637.79	37679.33	0.000%
37	30479.77	-324637.79	-30479.77	-30479.77	324637.79	30479.77	0.000%
38	36980.56	-324637.79	-21350.73	-36980.56	324637.79	21350.74	0.000%
39	43508.34	-324637.79	0.00	-43508.34	324637.79	-0.00	0.000%
40	39775.63	-324637.79	22964.47	-39775.64	324637.79	-22964.47	0.000%
41	31620.85	-324637.79	31620.85	-31620.86	324637.79	-31620.86	0.000%
42	21754.17	-324637.79	37679.33	-21754.17	324637.79	-37679.33	0.000%
43	0.00	-324637.79	42701.47	-0.00	324637.79	-42701.47	0.000%
44	-21754.17	-324637.79	37679.33	21754.17	324637.79	-37679.33	0.000%
45	-30479.77	-324637.79	30479.77	30479.77	324637.79	-30479.77	0.000%

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	67 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
46	-39775.63	-324637.79	22964.47	39775.64	324637.79	-22964.47	0.000%
47	-43508.34	-324637.79	0.00	43508.34	324637.79	-0.00	0.000%
48	-36980.56	-324637.79	-21350.73	36980.56	324637.79	21350.74	0.000%
49	-30479.77	-324637.79	-30479.77	30479.77	324637.79	30479.77	0.000%
50	-21754.17	-324637.79	-37679.33	21754.17	324637.79	37679.33	0.000%
51	0.00	-140969.55	-40331.09	0.00	140969.55	40331.09	0.000%
52	18445.17	-140969.55	-31947.97	-18445.17	140969.55	31947.97	0.000%
53	25679.91	-140969.55	-25679.91	-25679.91	140969.55	25679.91	0.000%
54	30954.70	-140969.55	-17871.71	-30954.71	140969.55	17871.71	0.000%
55	36890.33	-140969.55	0.00	-36890.34	140969.55	0.00	0.000%
56	34927.75	-140969.55	20165.55	-34927.75	140969.55	-20165.55	0.000%
57	27301.90	-140969.55	27301.90	-27301.90	140969.55	-27301.90	0.000%
58	18445.17	-140969.55	31947.97	-18445.17	140969.55	-31947.97	0.000%
59	-0.00	-140969.55	35743.41	-0.00	140969.55	-35743.42	0.000%
60	-18445.17	-140969.55	31947.97	18445.17	140969.55	-31947.97	0.000%
61	-25679.91	-140969.55	25679.91	25679.91	140969.55	-25679.91	0.000%
62	-34927.75	-140969.55	20165.55	34927.75	140969.55	-20165.55	0.000%
63	-36890.33	-140969.55	0.00	36890.34	140969.55	-0.00	0.000%
64	-30954.70	-140969.55	-17871.71	30954.71	140969.55	17871.71	0.000%
65	-25679.91	-140969.55	-25679.91	25679.91	140969.55	25679.91	0.000%
66	-18445.17	-140969.55	-31947.97	18445.17	140969.55	31947.97	0.000%

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	320 - 304	4.502	56	0.1021	0.0348
T2	304 - 300	4.157	56	0.1013	0.0353
T3	300 - 280	4.070	56	0.1007	0.0354
T4	280 - 260	3.645	56	0.0979	0.0365
T5	260 - 240	3.227	56	0.0962	0.0372
T6	240 - 220	2.812	56	0.0934	0.0353
T7	220 - 200	2.410	56	0.0891	0.0324
T8	200 - 180	2.030	56	0.0831	0.0299
T9	180 - 170	1.669	56	0.0769	0.0269
T10	170 - 160	1.497	56	0.0734	0.0252
T11	160 - 140	1.331	56	0.0696	0.0236
T12	140 - 120	1.034	56	0.0610	0.0215
T13	120 - 100	0.773	56	0.0516	0.0193
T14	100 - 80	0.556	56	0.0423	0.0161
T15	80 - 60	0.380	56	0.0326	0.0136
T16	60 - 30	0.247	51	0.0237	0.0113
T17	30 - 0	0.090	51	0.0108	0.0057

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
329.00	Lightning Rod 5/8x4'	56	4.502	0.1021	0.0348	Inf
327.00	Dual Lights	56	4.502	0.1021	0.0348	Inf

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	68 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

<i>Elevation</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
325.00	PD128-1	56	4.502	0.1021	0.0348	Inf
320.00	BA1012-0	56	4.502	0.1021	0.0348	Inf
318.00	ANT450F6	56	4.459	0.1020	0.0348	Inf
300.00	SC479-HF1LDF	56	4.070	0.1007	0.0354	375256
290.00	PD340-1	56	3.856	0.0992	0.0359	415459
286.00	DB809T3E-XC	56	3.772	0.0987	0.0361	512037
284.00	6' Side Mount Standoff	56	3.729	0.0984	0.0362	579229
283.00	SC479-HF1LDF(D00I-E6085) (Inverted)	56	3.708	0.0983	0.0363	615207
264.00	PD440-2	56	3.310	0.0965	0.0372	Inf
260.00	6' Side Mount Standoff	56	3.227	0.0962	0.0372	Inf
251.00	SC479-HF1LDF	56	3.039	0.0951	0.0367	757826
248.00	PD1142-1	56	2.977	0.0947	0.0364	611966
247.00	430-94C-09168-M-11048 TTA	56	2.956	0.0945	0.0362	575072
246.00	Sabre T-Boom (1)	56	2.935	0.0944	0.0361	542371
245.00	SC479-HF1LDF(D00I-E6085) (Inverted)	56	2.915	0.0942	0.0360	513190
238.00	531-70HD Exposed Dipole Antenna	56	2.771	0.0930	0.0350	358328
232.00	Valmont VFA-10-U V-Frame	56	2.649	0.0918	0.0341	269625
200.00	PiROD 12' Lightweight T-Frame	56	2.030	0.0831	0.0299	309773
179.00	DB586-Y	56	1.651	0.0765	0.0267	194869
177.00	DB586-Y	56	1.617	0.0759	0.0264	201627
176.00	PiROD 4' Side Mount Standoff (1)	56	1.599	0.0755	0.0262	206670
175.00	DB586-Y (inverted)	56	1.582	0.0752	0.0261	212421
168.00	L-810 Obstruction Lighting (1)	56	1.463	0.0726	0.0249	173985
165.00	L-810 Obstruction Lighting (1)	56	1.413	0.0715	0.0244	126642
164.00	L-810 Obstruction Lighting (1)	56	1.396	0.0711	0.0242	115480
163.00	Telewave ANT220F2 - Omni Antenna	56	1.380	0.0708	0.0240	106616
160.00	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	56	1.331	0.0696	0.0236	92189
154.00	Commscope PAR6-59W-PXA/A	56	1.237	0.0672	0.0228	101179
153.00	ANT450F6	56	1.222	0.0667	0.0227	104465
145.00	Telewave ANT220F2 - Omni Antenna	56	1.105	0.0633	0.0219	141121
142.00	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	56	1.062	0.0619	0.0217	159857
139.00	DB212-1	56	1.020	0.0606	0.0214	165857
117.00	3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	56	0.738	0.0502	0.0188	98877
115.00	8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	56	0.715	0.0493	0.0185	102064
112.00	Andrew 2' w/Radome	56	0.681	0.0479	0.0180	107643
107.00	PA8-65	56	0.627	0.0456	0.0172	118432
106.00	PiROD 4' Side Mount Standoff (1)	56	0.617	0.0451	0.0171	120855
94.00	PD688S-4	56	0.499	0.0394	0.0153	118773

Maximum Tower Deflections - Design Wind

<i>Section No.</i>	<i>Elevation ft</i>	<i>Horz. Deflection in</i>	<i>Gov. Load Comb.</i>	<i>Tilt °</i>	<i>Twist °</i>
T1	320 - 304	24.344	12	0.5518	0.1892
T2	304 - 300	22.476	12	0.5472	0.1921
T3	300 - 280	22.009	12	0.5443	0.1927
T4	280 - 260	19.714	12	0.5284	0.1987

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	69 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T5	260 - 240	17.455	12	0.5187	0.2026
T6	240 - 220	15.218	12	0.5035	0.1922
T7	220 - 200	13.047	12	0.4805	0.1765
T8	200 - 180	10.997	12	0.4485	0.1629
T9	180 - 170	9.044	12	0.4153	0.1462
T10	170 - 160	8.112	12	0.3964	0.1374
T11	160 - 140	7.216	12	0.3761	0.1283
T12	140 - 120	5.610	12	0.3299	0.1169
T13	120 - 100	4.196	12	0.2790	0.1049
T14	100 - 80	3.021	12	0.2289	0.0879
T15	80 - 60	2.066	12	0.1763	0.0737
T16	60 - 30	1.345	2	0.1281	0.0611
T17	30 - 0	0.488	2	0.0582	0.0307

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
329.00	Lightning Rod 5/8x4'	12	24.344	0.5518	0.1892	Inf
327.00	Dual Lights	12	24.344	0.5518	0.1892	Inf
325.00	PD128-1	12	24.344	0.5518	0.1892	Inf
320.00	BA1012-0	12	24.344	0.5518	0.1892	Inf
318.00	ANT450F6	12	24.111	0.5516	0.1896	Inf
300.00	SC479-HF1LDF	12	22.009	0.5443	0.1927	71765
290.00	PD340-1	12	20.854	0.5359	0.1952	79646
286.00	DB809T3E-XC	12	20.397	0.5327	0.1966	98660
284.00	6' Side Mount Standoff	12	20.169	0.5311	0.1973	112002
283.00	SC479-HF1LDF(D00I-E6085) (Inverted)	12	20.055	0.5304	0.1976	119890
264.00	PD440-2	12	17.905	0.5207	0.2027	280963
260.00	6' Side Mount Standoff	12	17.455	0.5187	0.2026	302902
251.00	SC479-HF1LDF	12	16.444	0.5129	0.1997	144185
248.00	PD1142-1	12	16.108	0.5106	0.1979	116254
247.00	430-94C-09168-M-11048 TTA	12	15.996	0.5098	0.1973	109203
246.00	Sabre T-Boom (1)	12	15.885	0.5089	0.1966	102958
245.00	SC479-HF1LDF(D00I-E6085) (Inverted)	12	15.773	0.5081	0.1959	97389
238.00	531-70HD Exposed Dipole Antenna	12	14.996	0.5016	0.1906	67608
232.00	Valmont VFA-10-U V-Frame	12	14.337	0.4954	0.1858	50456
200.00	PiROD 12' Lightweight T-Frame	12	10.997	0.4485	0.1629	58716
179.00	DB586-Y	12	8.949	0.4135	0.1454	36447
177.00	DB586-Y	12	8.761	0.4098	0.1436	37746
176.00	PiROD 4' Side Mount Standoff (1)	12	8.667	0.4079	0.1428	38715
175.00	DB586-Y (inverted)	12	8.574	0.4060	0.1419	39823
168.00	L-810 Obstruction Lighting (1)	12	7.929	0.3925	0.1355	32463
165.00	L-810 Obstruction Lighting (1)	12	7.658	0.3865	0.1327	23488
164.00	L-810 Obstruction Lighting (1)	12	7.568	0.3844	0.1318	21388
163.00	Telewave ANT220F2 - Omni Antenna	12	7.479	0.3824	0.1309	19724
160.00	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	12	7.216	0.3761	0.1283	17022
154.00	Commscope PAR6-59W-PXA/A	12	6.710	0.3630	0.1241	18690
153.00	ANT450F6	12	6.628	0.3608	0.1235	19302
145.00	Telewave ANT220F2 - Omni Antenna	12	5.992	0.3421	0.1193	26147
142.00	Sitepro1 USF-4U Mount Assembly	12	5.762	0.3348	0.1179	29662

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	70 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Elevation	Appurtenance	Gov. Load Comb.	Deflection	Tilt	Twist	Radius of Curvature
ft			in	°	°	ft
	(Ca = 1.4 assumed)					
139.00	DB212-1	12	5.535	0.3274	0.1164	30808
117.00	3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	12	4.005	0.2715	0.1025	18342
115.00	8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	12	3.880	0.2665	0.1009	18925
112.00	Andrew 2' w/Radome	12	3.698	0.2590	0.0983	19943
107.00	PA8-65	12	3.406	0.2466	0.0939	21908
106.00	Pirod 4' Side Mount Standoff (1)	12	3.350	0.2441	0.0930	22348
94.00	PD688S-4	12	2.710	0.2131	0.0831	21907

Bolt Design Data

Section No.	Elevation	Component Type	Bolt Grade	Bolt Size	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load per Bolt lb	Ratio Load Allowable	Allowable Ratio	Criteria	
	ft			in							
T1	320	Diagonal	A325X	0.6250	1	1340.49	5811.33	0.231	✓	1	Member Block Shear
T2	304	Leg	A325N	1.0000	6	1309.41	54517.00	0.024	✓	1	Bolt Tension
		Diagonal	A325X	0.6250	1	1557.70	5811.33	0.268	✓	1	Member Block Shear
T3	300	Leg	A325N	1.0000	8	2734.47	54517.00	0.050	✓	1	Bolt Tension
		Diagonal	A325X	0.6250	1	3067.24	9107.81	0.337	✓	1	Member Block Shear
T4	280	Leg	A325N	1.0000	8	5118.02	54517.00	0.094	✓	1	Bolt Tension
		Diagonal	A325X	0.7500	1	4727.40	11962.50	0.395	✓	1	Member Block Shear
T5	260	Leg	A325N	1.0000	8	8477.98	54517.00	0.156	✓	1	Bolt Tension
		Diagonal	A325X	0.7500	1	8221.24	14137.50	0.582	✓	1	Member Bearing
T6	240	Leg	A325N	1.0000	8	13592.50	54517.00	0.249	✓	1	Bolt Tension
		Diagonal	A325X	0.7500	1	13356.60	17671.90	0.756	✓	1	Member Bearing
T7	220	Leg	A325N	1.0000	12	12863.10	54517.00	0.236	✓	1	Bolt Tension
		Diagonal	A325X	0.7500	1	16638.50	21206.30	0.785	✓	1	Member Bearing
T8	200	Leg	A325N	1.0000	12	17599.40	54517.00	0.323	✓	1	Bolt Tension
		Diagonal	A325X	0.8750	1	21122.30	24862.50	0.850	✓	1	Member Bearing
T9	180	Leg	A325N	1.0000	12	20091.60	54517.00	0.369	✓	1	Bolt Tension
		Diagonal	A325X	0.8750	1	22538.90	24862.50	0.907	✓	1	Member Bearing
T10	170	Diagonal	A325X	0.8750	1	23244.00	24862.50	0.935	✓	1	Member Bearing
T11	160	Leg	A325N	1.0000	12	27918.10	54517.00	0.512	✓	1	Bolt Tension
		Diagonal	A325X	0.8750	1	29160.70	33824.30	0.862	✓	1	Bolt Shear
T12	140	Leg	A325N	1.0000	12	33253.60	54517.00	0.610	✓	1	Bolt Tension
		Diagonal	A325X	0.8750	1	30916.30	33824.30	0.914	✓	1	Bolt Shear
T13	120	Leg	A325N	1.0000	12	34033.10	54517.00	0.624	✓	1	Bolt Tension
		Diagonal	A325X	0.7500	3	16927.90	24850.50	0.681	✓	1	Bolt Shear
		Horizontal	A325X	0.7500	2	13533.40	24850.50	0.545	✓	1	Bolt Shear

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	71 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load per Bolt lb	Ratio Load Allowable	Allowable Ratio	Criteria	
T14	100	Leg	A325N	1.0000	16	28959.50	54517.00	0.531	✓	1	Bolt Tension
		Diagonal	A325X	0.7500	3	17733.20	24850.50	0.714	✓	1	Bolt Shear
		Horizontal	A325X	0.7500	2	15233.80	24850.50	0.613	✓	1	Bolt Shear
T15	80	Leg	A325N	1.0000	16	32451.30	54517.00	0.595	✓	1	Bolt Tension
		Diagonal	A325X	0.7500	3	17715.20	24850.50	0.713	✓	1	Bolt Shear
		Horizontal	A325X	0.7500	2	15716.80	24850.50	0.632	✓	1	Bolt Shear
T16	60	Leg	A325N	1.0000	16	35364.10	54517.00	0.649	✓	1	Bolt Tension
		Diagonal	A325X	0.8750	3	25003.40	33824.30	0.739	✓	1	Bolt Shear
		Horizontal	A325X	0.7500	2	17548.60	24850.50	0.706	✓	1	Bolt Shear
T17	30	Leg	A325N	1.0000	24	27162.40	54517.00	0.498	✓	1	Bolt Tension
		Diagonal	A325X	0.8750	3	24664.10	33824.30	0.729	✓	1	Bolt Shear
		Horizontal	A325X	0.7500	2	20833.10	24850.50	0.838	✓	1	Bolt Shear

Compression Checks

Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	320 - 304	ROHN 5 EH	16.00	4.00	26.1 K=1.00	6.1120	-7158.84	261674.00	0.027 ¹ ✓
T2	304 - 300	ROHN 5 EH	4.00	4.00	26.1 K=1.00	6.1120	-9868.54	261674.00	0.038 ¹ ✓
T3	300 - 280	ROHN 6 EH	20.03	5.01	27.4 K=1.00	8.4049	-27182.10	358043.00	0.076 ¹ ✓
T4	280 - 260	ROHN 8 EH w/ angle 8x8x0.5	20.04	6.68	27.0 K=1.00	20.5036	-51734.40	874859.00	0.059 ¹ ✓
T5	260 - 240	ROHN 8 EH w/ angle 8x8x0.5	20.03	6.68	27.0 K=1.00	20.5036	-87475.40	874884.00	0.100 ¹ ✓
T6	240 - 220	ROHN 8 EH w/ angle 8x8x0.5	20.03	6.68	27.0 K=1.00	20.5036	-140783.00	874888.00	0.161 ¹ ✓
T7	220 - 200	ROHN 8 EH w/ angle 8x8x0.5	20.03	10.02	40.4 K=1.00	20.5036	-197088.00	818638.00	0.241 ¹ ✓
T8	200 - 180	ROHN 10 EH w/ angle 8x8x0.5	20.04	10.02	34.6 K=1.00	23.8453	-268188.00	982914.00	0.273 ¹ ✓
T9	180 - 170	ROHN 10 EH w/ angle 8x8x0.5	10.02	10.02	34.6 K=1.00	23.8453	-305050.00	982929.00	0.310 ¹ ✓
T10	170 - 160	ROHN 10 EH w/ angle 8x8x0.5	10.02	10.02	34.6 K=1.00	23.8453	-342203.00	982929.00	0.348 ¹ ✓
T11	160 - 140	ROHN 10 EH w/ angle 8x8x0.5	20.03	10.02	34.6 K=1.00	23.8453	-421750.00	982978.00	0.429 ¹ ✓
T12	140 - 120	ROHN 10 EH w/ angle	20.04	10.02	34.6	23.8453	-502759.00	982899.00	0.512 ¹ ✓

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 72 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
		8x8x0.5			K=1.00				✓
T13	120 - 100	ROHN 10 EH w/ angle 8x8x0.5	20.06	10.03	34.7 K=1.00	23.8453	-519178.00	982763.00	0.528 ¹ ✓
T14	100 - 80	ROHN 10 EH w/ angle 8x8x0.5	20.05	10.03	34.7 K=1.00	23.8453	-589434.00	982792.00	0.600 ¹ ✓
T15	80 - 60	ROHN 12 EH w/ angle 8x8x0.5	20.06	10.03	29.9 K=1.00	26.9670	-661020.00	1136630.00	0.582 ¹ ✓
T16	60 - 30	ROHN 12 EH w/ angle 8x8x0.5	30.07	10.02	29.9 K=1.00	26.9670	-733002.00	1136700.00	0.645 ¹ ✓
T17	30 - 0	ROHN 12 EHS w Angle 8x8x0.625	30.08	10.03	30.2 K=1.00	33.3120	-840602.00	1402320.00	0.599 ¹ ✓

¹ P_u / φP_n controls

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	320 - 304	L1 3/4x1 3/4x3/16	7.90	3.56	124.4 K=1.00	0.6211	-1332.71	11479.60	0.116 ¹ ✓
T2	304 - 300	L1 3/4x1 3/4x3/16	7.90	3.56	124.4 K=1.00	0.6211	-1579.36	11479.60	0.138 ¹ ✓
T3	300 - 280	L2x2x1/4	9.94	4.68	143.7 K=1.00	0.9380	-3094.91	13009.80	0.238 ¹ ✓
T4	280 - 260	L2 1/2x2 1/2x1/4	12.59	5.83	142.4 K=1.00	1.1900	-4796.71	16785.10	0.286 ¹ ✓
T5	260 - 240	L3x3x1/4	14.38	6.72	136.3 K=1.00	1.4400	-8485.37	22180.60	0.383 ¹ ✓
T6	240 - 220	L4x4x5/16	16.19	7.64	116.9 K=1.01	2.4000	-13340.70	50268.80	0.265 ¹ ✓
T7	220 - 200	L4x4x3/8	19.37	9.30	141.7 K=1.00	2.8600	-17336.80	40783.20	0.425 ¹ ✓
T8	200 - 180	L4x4x3/8	21.20	10.21	155.6 K=1.00	2.8600	-21398.20	33828.90	0.633 ¹ ✓
T9	180 - 170	L4x4x3/8	22.13	10.68	162.6 K=1.00	2.8600	-22966.30	30962.40	0.742 ¹ ✓
T10	170 - 160	L4x4x3/8	23.06	11.15	169.7 K=1.00	2.8600	-23824.30	28413.70	0.838 ¹ ✓
T11	160 - 140	L5x5x1/2	24.84	12.01	146.6 K=1.00	4.7500	-29160.70	63217.20	0.461 ¹ ✓
T12	140 - 120	L5x5x1/2	26.78	13.03	159.0 K=1.00	4.7500	-30916.30	53762.80	0.575 ¹ ✓
T13	120 - 100	ROHN 3 XXS	24.42	12.21	139.9 K=1.00	5.4664	-50783.80	63081.40	0.805 ¹ ✓
T14	100 - 80	ROHN 3 XXS	25.15	12.58	144.1 K=1.00	5.4664	-53199.60	59442.80	0.895 ¹ ✓
T15	80 - 60	ROHN 3 XXS	25.98	12.99	148.9 K=1.00	5.4664	-53145.50	55698.10	0.954 ¹ ✓

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	73 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 4 EH	35.21	11.74	95.4 K=1.00	4.4074	-75010.30	101988.00	0.735 ¹ ✓
T17	30 - 0	ROHN 4 EH	36.27	12.09	98.2 K=1.00	4.4074	-73992.20	97939.00	0.755 ¹ ✓

¹ P_u / φP_n controls

Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 3 STD	25.39	12.22	126.1 K=1.00	2.2285	-27066.70	31679.40	0.854 ¹ ✓
T14	100 - 80	ROHN 3 EH	27.97	13.51	142.7 K=1.00	3.0159	-30467.60	33455.50	0.911 ¹ ✓
T15	80 - 60	ROHN 3 XXS	30.47	14.76	169.2 K=1.00	5.4664	-31433.60	43132.20	0.729 ¹ ✓
T16	60 - 30	ROHN 3.5 EH	33.14	16.04	147.3 K=1.00	3.6784	-35097.20	38300.30	0.916 ¹ ✓
T17	30 - 0	ROHN 4 EH	36.80	17.87	145.2 K=1.00	4.4074	-41666.30	47220.90	0.882 ¹ ✓

¹ P_u / φP_n controls

Top Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	320 - 304	L1 3/4x1 3/4x3/16	6.81	6.35	182.6 K=0.82	0.6211	-193.80	5333.23	0.036 ¹ ✓
T3	300 - 280	L2x2x1/4	6.81	6.35	166.0 K=0.85	0.9380	-69.63	9744.39	0.007 ¹ ✓

¹ P_u / φP_n controls

Redundant Horizontal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 1.5 STD	6.35	5.88	113.3 K=1.00	0.7995	-9017.86	14083.10	0.640 ¹

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	74 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T14	100 - 80	P1.5x.145	6.99	6.52	125.7 K=1.00	0.7995	-10238.40	11432.70	0.896 ¹ ✓
T15	80 - 60	ROHN 2 STD	7.62	7.09	108.0 K=1.00	1.0745	-11487.40	20598.10	0.558 ¹ ✓
T16	60 - 30	ROHN 1.5 STD	5.52	4.99	96.2 K=1.00	0.7995	-12749.80	18282.30	0.697 ¹ ✓
T17	30 - 0	P1.5x.145	6.13	5.60	108.0 K=1.00	0.7995	-14642.70	15339.00	0.955 ¹ ✓

¹ P_u / φP_n controls

Redundant Horizontal (2) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2 XXS	11.05	10.52	179.6 K=1.00	2.6559	-12749.80	18604.80	0.685 ¹ ✓
T17	30 - 0	ROHN 2.5 EH	12.27	11.74	152.4 K=1.00	2.2535	-14642.70	21919.90	0.668 ¹ ✓

¹ P_u / φP_n controls

Redundant Diagonal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 2 STD	11.52	10.57	161.1 K=1.00	1.0745	-8181.56	9352.65	0.875 ¹ ✓
T14	100 - 80	ROHN 2 EH	11.86	10.98	171.6 K=1.00	1.4807	-8683.21	11364.10	0.764 ¹ ✓
T15	80 - 60	ROHN 2 EH	12.18	11.36	177.4 K=1.00	1.4807	-9186.98	10626.30	0.865 ¹ ✓
T16	60 - 30	ROHN 2 EH	11.15	9.95	155.3 K=1.00	1.4807	-12866.10	13862.10	0.928 ¹ ✓
T17	30 - 0	ROHN 2.5 STD	11.41	10.31	130.6 K=1.00	1.7040	-13622.00	22579.60	0.603 ¹ ✓

¹ P_u / φP_n controls

Redundant Diagonal (2) Design Data (Compression)

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	75 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2.5 STD	14.46	13.72	173.8 K=1.00	1.7040	-8343.82	12742.30	0.655 ¹ ✓
T17	30 - 0	ROHN 2.5 STD	15.33	14.63	185.3 K=1.00	1.7040	-9151.97	11206.60	0.817 ¹ ✓

¹ P_u / φP_n controls

Redundant Hip (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 1.5 STD	6.35	6.35	122.3 K=1.00	0.7995	-49.03	12066.60	0.004 ¹ ✓
T14	100 - 80	ROHN 1.5 STD	6.99	6.99	134.8 K=1.00	0.7995	-48.04	9943.20	0.005 ¹ ✓
T15	80 - 60	ROHN 1.5 STD	7.62	7.62	146.8 K=1.00	0.7995	-47.06	8378.50	0.006 ¹ ✓
T16	60 - 30	ROHN 1.5 STD	5.52	5.52	106.5 K=1.00	0.7995	-175.83	15708.50	0.011 ¹ ✓
T17	30 - 0	ROHN 1.5 STD	6.13	6.13	118.2 K=1.00	0.7995	-157.40	12924.00	0.012 ¹ ✓

¹ P_u / φP_n controls

Redundant Hip (2) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2 STD	11.05	11.05	168.4 K=1.00	1.0745	-95.51	8559.02	0.011 ¹ ✓
T17	30 - 0	ROHN 2 STD	12.27	12.27	187.0 K=1.00	1.0745	-89.81	6941.18	0.013 ¹ ✓

¹ P_u / φP_n controls

Redundant Hip Diagonal (1) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 2.5 STD	15.15	15.15	191.9	1.7040	-97.06	10450.60	0.009 ¹

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	76 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T14	100 - 80	ROHN 2.5 STD	16.00	16.00	K=1.00 202.6	1.7040	-91.08	9375.46	0.010 ¹ ✓
T15	80 - 60	ROHN 3 STD	16.88	16.88	K=1.00 174.1	2.2285	-102.08	16617.70	0.006 ¹ ✓
T16	60 - 30	ROHN 2 STD	14.10	14.10	K=1.00 214.9	1.0745	-360.74	5254.92	0.069 ¹ ✓
T17	30 - 0	ROHN 2.5 STD	14.88	14.88	K=1.00 188.4	1.7040	-327.42	10840.00	0.030 ¹ ✓

¹ P_u / φP_n controls

Redundant Hip Diagonal (2) Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2 STD	17.91	17.91	K=1.00 273.1	1.0745	-143.01	3255.91	0.044 ¹ ✓
T17	30 - 0	KL/R > 250 (C) - 357 ROHN 2.5 STD	19.28	19.28	K=1.00 244.2	1.7040	-140.44	6453.40	0.022 ¹ ✓

¹ P_u / φP_n controls

Inner Bracing Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 3 STD	12.69	12.69	K=1.00 130.9	2.2285	-27.79	29370.40	0.001 ¹ ✓
T14	100 - 80	ROHN 3 STD	13.99	13.99	K=1.00 144.2	2.2285	-27.56	24201.90	0.001 ¹ ✓
T15	80 - 60	ROHN 3 STD	15.24	15.24	K=1.00 157.1	2.2285	-31.26	20393.40	0.002 ¹ ✓
T16	60 - 30	ROHN 3 STD	16.57	16.57	K=1.00 170.9	2.2285	-60.20	17239.70	0.003 ¹ ✓
T17	30 - 0	ROHN 3 STD	18.40	18.40	K=1.00 189.8	2.2285	-62.56	13981.00	0.004 ¹ ✓

¹ P_u / φP_n controls

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 77 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Tension Checks

Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	320 - 304	ROHN 5 EH	16.00	4.00	26.1	6.1120	5560.81	275039.00	0.020 ¹
T2	304 - 300	ROHN 5 EH	4.00	4.00	26.1	6.1120	7856.49	275039.00	0.029 ¹
T3	300 - 280	ROHN 6 EH	20.03	5.01	27.4	8.4049	21875.70	378222.00	0.058 ¹
T4	280 - 260	ROHN 8 EH w/ angle 8x8x0.5	20.04	6.68	27.0	20.5036	40944.10	922662.00	0.044 ¹
T5	260 - 240	ROHN 8 EH w/ angle 8x8x0.5	20.03	6.68	27.0	20.5036	67823.90	922662.00	0.074 ¹
T6	240 - 220	ROHN 8 EH w/ angle 8x8x0.5	20.03	6.68	27.0	20.5036	108740.00	922662.00	0.118 ¹
T7	220 - 200	ROHN 8 EH w/ angle 8x8x0.5	20.03	10.02	40.4	20.5036	154357.00	922662.00	0.167 ¹
T8	200 - 180	ROHN 10 EH w/ angle 8x8x0.5	20.04	10.02	34.6	23.8453	211193.00	1073040.00	0.197 ¹
T9	180 - 170	ROHN 10 EH w/ angle 8x8x0.5	10.02	10.02	34.6	23.8453	241099.00	1073040.00	0.225 ¹
T10	170 - 160	ROHN 10 EH w/ angle 8x8x0.5	10.02	10.02	34.6	23.8453	271340.00	1073040.00	0.253 ¹
T11	160 - 140	ROHN 10 EH w/ angle 8x8x0.5	20.03	10.02	34.6	23.8453	335017.00	1073040.00	0.312 ¹
T12	140 - 120	ROHN 10 EH w/ angle 8x8x0.5	20.04	10.02	34.6	23.8453	399043.00	1073040.00	0.372 ¹
T13	120 - 100	ROHN 10 EH w/ angle 8x8x0.5	20.06	10.03	34.7	23.8453	409802.00	1073040.00	0.382 ¹
T14	100 - 80	ROHN 10 EH w/ angle 8x8x0.5	20.05	10.03	34.7	23.8453	464452.00	1073040.00	0.433 ¹
T15	80 - 60	ROHN 12 EH w/ angle 8x8x0.5	20.06	10.03	29.9	26.9670	520588.00	1213520.00	0.429 ¹
T16	60 - 30	ROHN 12 EH w/ angle 8x8x0.5	30.07	10.02	29.9	26.9670	576221.00	1213520.00	0.475 ¹
T17	30 - 0	ROHN 12 EHS w Angle 8x8x0.625	30.08	10.03	30.2	33.3120	660101.00	1499040.00	0.440 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	320 - 304	L1 3/4x1 3/4x3/16	7.90	3.56	82.2	0.3604	1340.49	15675.30	0.086 ¹

<p>tnxTower</p> <p>AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	<p>Job</p> <p>320' Rohn SSVMW</p>	<p>Page</p> <p>78 of 95</p>
	<p>Project</p> <p>CSP Tower - Colchester, CT</p>	<p>Date</p> <p>12:07:36 05/18/20</p>
	<p>Client</p> <p>VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"</p>	<p>Designed by</p> <p>MCD</p>

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T2	304 - 300	L1 3/4x1 3/4x3/16	7.90	3.56	82.2	0.3604	1557.70	15675.30	0.099 ¹
T3	300 - 280	L2x2x1/4	9.94	4.68	94.6	0.5629	3067.24	24485.10	0.125 ¹
T4	280 - 260	L2 1/2x2 1/2x1/4	12.59	5.83	93.1	0.7284	4727.40	31687.00	0.149 ¹
T5	260 - 240	L3x3x1/4	14.38	6.72	88.5	0.9159	8221.24	44652.00	0.184 ¹
T6	240 - 220	L4x4x5/16	16.19	7.64	75.2	1.5949	13356.60	77752.40	0.172 ¹
T7	220 - 200	L4x4x3/8	19.37	9.30	92.1	1.8989	16638.50	92571.70	0.180 ¹
T8	200 - 180	L4x4x3/8	21.20	10.21	101.1	1.8637	21122.30	90857.80	0.232 ¹
T9	180 - 170	L4x4x3/8	22.13	10.68	105.6	1.8637	22538.90	90857.80	0.248 ¹
T10	170 - 160	L4x4x3/8	23.06	11.15	110.2	1.8637	23244.00	90857.80	0.256 ¹
T11	160 - 140	L5x5x1/2	24.84	12.01	94.8	3.1875	28272.90	155391.00	0.182 ¹
T12	140 - 120	L5x5x1/2	26.78	13.03	102.7	3.1875	29995.90	155391.00	0.193 ¹
T13	120 - 100	ROHN 3 XXS	24.42	12.21	139.9	5.4664	48086.90	245987.00	0.195 ¹
T14	100 - 80	ROHN 3 XXS	25.15	12.58	144.1	5.4664	49547.20	245987.00	0.201 ¹
T15	80 - 60	ROHN 3 XXS	25.98	12.99	148.9	5.4664	48472.60	245987.00	0.197 ¹
T16	60 - 30	ROHN 4 EH	35.21	11.74	95.4	4.4074	68306.40	198335.00	0.344 ¹
T17	30 - 0	ROHN 4 EH	36.27	12.09	98.2	4.4074	69597.20	198335.00	0.351 ¹

¹ P_u / φP_n controls

Horizontal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 3 STD	25.39	12.22	126.1	2.2285	26754.50	100281.00	0.267 ¹
T14	100 - 80	ROHN 3 EH	27.97	13.51	142.7	3.0159	29223.70	135717.00	0.215 ¹
T15	80 - 60	ROHN 3 XXS	30.47	14.76	169.2	5.4664	29908.40	245987.00	0.122 ¹
T16	60 - 30	ROHN 3.5 EH	33.14	16.04	147.3	3.6784	34937.70	165529.00	0.211 ¹

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	79 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T17	30 - 0	ROHN 4 EH	36.80	17.87	145.2	4.4074	37602.50	198335.00	0.190 ¹ ✓

¹ P_u / φP_n controls

Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	320 - 304	L1 3/4x1 3/4x3/16	6.81	6.35	141.8	0.6211	182.36	20123.40	0.009 ¹ ✓
T3	300 - 280	L2x2x1/4	6.81	6.35	125.1	0.9380	49.59	30391.20	0.002 ¹ ✓

¹ P_u / φP_n controls

Redundant Horizontal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 1.5 STD	6.35	5.88	113.3	0.7995	9017.86	35975.60	0.251 ¹ ✓
T14	100 - 80	P1.5x.145	6.99	6.52	125.7	0.7995	10238.40	35975.60	0.285 ¹ ✓
T15	80 - 60	ROHN 2 STD	7.62	7.09	108.0	1.0745	11487.40	48353.90	0.238 ¹ ✓
T16	60 - 30	ROHN 1.5 STD	5.52	4.99	96.2	0.7995	12749.80	35975.60	0.354 ¹ ✓
T17	30 - 0	P1.5x.145	6.13	5.60	108.0	0.7995	14642.70	35975.60	0.407 ¹ ✓

¹ P_u / φP_n controls

Redundant Horizontal (2) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2 XXS	11.05	10.52	179.6	2.6559	12749.80	119516.00	0.107 ¹ ✓
T17	30 - 0	ROHN 2.5 EH	12.27	11.74	152.4	2.2535	14642.70	101409.00	0.144 ¹

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	80 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
									✓

¹ P_u / φP_n controls

Redundant Diagonal (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 2 STD	11.52	10.57	161.1	1.0745	8181.56	48353.90	0.169 ¹ ✓
T14	100 - 80	ROHN 2 EH	11.86	10.98	171.6	1.4807	8683.21	66630.70	0.130 ¹ ✓
T15	80 - 60	ROHN 2 EH	12.18	11.36	177.4	1.4807	9186.98	66630.70	0.138 ¹ ✓
T16	60 - 30	ROHN 2 EH	11.15	9.95	155.3	1.4807	12866.10	66630.70	0.193 ¹ ✓
T17	30 - 0	ROHN 2.5 STD	11.41	10.31	130.6	1.7040	13622.00	76682.30	0.178 ¹ ✓

¹ P_u / φP_n controls

Redundant Diagonal (2) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2.5 STD	14.46	13.72	173.8	1.7040	8343.82	76682.30	0.109 ¹ ✓
T17	30 - 0	ROHN 2.5 STD	15.33	14.63	185.3	1.7040	9151.97	76682.30	0.119 ¹ ✓

¹ P_u / φP_n controls

Redundant Hip (1) Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 1.5 STD	6.35	6.35	122.3	0.7995	23.19	35975.60	0.001 ¹ ✓
T14	100 - 80	ROHN 1.5 STD	6.99	6.99	134.8	0.7995	21.08	35975.60	0.001 ¹ ✓

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	81 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L_u</i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in²</i>	<i>P_u</i> <i>lb</i>	ϕP_n <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T15	80 - 60	ROHN 1.5 STD	7.62	7.62	146.8	0.7995	15.69	35975.60	0.000 ¹
T16	60 - 30	ROHN 1.5 STD	5.52	5.52	106.5	0.7995	170.36	35975.60	0.005 ¹ ✓
T17	30 - 0	ROHN 1.5 STD	6.13	6.13	118.2	0.7995	147.06	35975.60	0.004 ¹ ✓

¹ $P_u / \phi P_n$ controls

Redundant Hip (2) Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L_u</i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in²</i>	<i>P_u</i> <i>lb</i>	ϕP_n <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2 STD	11.05	11.05	168.4	1.0745	70.64	48353.90	0.001 ¹ ✓
T17	30 - 0	ROHN 2 STD	12.27	12.27	187.0	1.0745	61.66	48353.90	0.001 ¹ ✓

¹ $P_u / \phi P_n$ controls

Redundant Hip Diagonal (1) Design Data (Tension)

Section No.	Elevation <i>ft</i>	Size	<i>L</i> <i>ft</i>	<i>L_u</i> <i>ft</i>	<i>Kl/r</i>	<i>A</i> <i>in²</i>	<i>P_u</i> <i>lb</i>	ϕP_n <i>lb</i>	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 2.5 STD	15.15	15.15	191.9	1.7040	98.62	76682.30	0.001 ¹ ✓
T14	100 - 80	ROHN 2.5 STD	16.00	16.00	202.6	1.7040	91.43	76682.30	0.001 ¹ ✓
T15	80 - 60	ROHN 3 STD	16.88	16.88	174.1	2.2285	93.77	100281.00	0.001 ¹ ✓
T16	60 - 30	ROHN 2 STD	14.10	14.10	214.9	1.0745	355.70	48353.90	0.007 ¹ ✓
T17	30 - 0	ROHN 2.5 STD	14.88	14.88	188.4	1.7040	322.57	76682.30	0.004 ¹ ✓

¹ $P_u / \phi P_n$ controls

Redundant Hip Diagonal (2) Design Data (Tension)

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	82 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T16	60 - 30	ROHN 2 STD	17.91	17.91	273.1	1.0745	121.93	48353.90	0.003 ¹
T17	30 - 0	ROHN 2.5 STD	19.28	19.28	244.2	1.7040	118.01	76682.30	0.002 ¹

¹ P_u / φP_n controls

Inner Bracing Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	120 - 100	ROHN 3 STD	12.69	12.69	130.9	2.2285	7.51	100281.00	0.000 ¹
T14	100 - 80	ROHN 3 STD	13.99	13.99	144.2	2.2285	4.00	100281.00	0.000 ¹
T16	60 - 30	ROHN 3 STD	16.57	16.57	170.9	2.2285	44.22	100281.00	0.000 ¹
T17	30 - 0	ROHN 3 STD	18.40	18.40	189.8	2.2285	40.14	100281.00	0.000 ¹

¹ P_u / φP_n controls

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	φP _{allow} lb	% Capacity	Pass Fail
T1	320 - 304	Leg	ROHN 5 EH	1	-7158.84	261674.00	2.7	Pass
		Leg	ROHN 5 EH	2	-7090.50	261674.00	2.7	Pass
		Leg	ROHN 5 EH	3	-7130.55	261674.00	2.7	Pass
T2	304 - 300	Leg	ROHN 5 EH	31	-9868.54	261674.00	3.8	Pass
		Leg	ROHN 5 EH	32	-9805.40	261674.00	3.7	Pass
		Leg	ROHN 5 EH	33	-9841.92	261674.00	3.8	Pass
T3	300 - 280	Leg	ROHN 6 EH	40	-27182.10	358043.00	7.6	Pass
		Leg	ROHN 6 EH	41	-26687.60	358043.00	7.5	Pass
		Leg	ROHN 6 EH	42	-26897.60	358043.00	7.5	Pass
T4	280 - 260	Leg	ROHN 8 EH w/ angle 8x8x0.5	70	-51734.40	874859.00	5.9	Pass
		Leg	ROHN 8 EH w/ angle 8x8x0.5	71	-51465.00	874859.00	5.9	Pass
		Leg	ROHN 8 EH w/ angle 8x8x0.5	72	-51519.70	874859.00	5.9	Pass
T5	260 - 240	Leg	ROHN 8 EH w/ angle 8x8x0.5	91	-86845.30	874884.00	9.9	Pass
		Leg	ROHN 8 EH w/ angle 8x8x0.5	92	-87475.40	874884.00	10.0	Pass
		Leg	ROHN 8 EH w/ angle 8x8x0.5	93	-86550.70	874884.00	9.9	Pass
T6	240 - 220	Leg	ROHN 8 EH w/ angle 8x8x0.5	112	-140010.00	874888.00	16.0	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	83 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
		Leg	ROHN 8 EH w/ angle 8x8x0.5	113	-140783.00	874888.00	24.9 (b) 16.1	Pass
		Leg	ROHN 8 EH w/ angle 8x8x0.5	114	-140046.00	874888.00	24.8 (b) 16.0	Pass
T7	220 - 200	Leg	ROHN 8 EH w/ angle 8x8x0.5	133	-196039.00	818638.00	24.9 (b) 23.9	Pass
		Leg	ROHN 8 EH w/ angle 8x8x0.5	134	-197088.00	818638.00	24.1	Pass
		Leg	ROHN 8 EH w/ angle 8x8x0.5	135	-196080.00	818638.00	24.0	Pass
T8	200 - 180	Leg	ROHN 10 EH w/ angle 8x8x0.5	148	-266720.00	982914.00	27.1	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	149	-268188.00	982914.00	32.3 (b) 27.3	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	150	-266654.00	982914.00	32.1 (b) 27.1	Pass
T9	180 - 170	Leg	ROHN 10 EH w/ angle 8x8x0.5	163	-303505.00	982929.00	32.3 (b) 30.9	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	164	-305050.00	982929.00	36.8 (b) 31.0	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	165	-303292.00	982929.00	36.7 (b) 30.9	Pass
T10	170 - 160	Leg	ROHN 10 EH w/ angle 8x8x0.5	172	-340647.00	982929.00	36.9 (b) 34.7	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	173	-342203.00	982929.00	34.8	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	174	-340344.00	982929.00	34.6	Pass
T11	160 - 140	Leg	ROHN 10 EH w/ angle 8x8x0.5	181	-420942.00	982978.00	42.8	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	182	-421750.00	982978.00	51.1 (b) 42.9	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	183	-419751.00	982978.00	51.0 (b) 42.7	Pass
T12	140 - 120	Leg	ROHN 10 EH w/ angle 8x8x0.5	196	-501945.00	982899.00	51.2 (b) 51.1	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	197	-502759.00	982899.00	60.8 (b) 51.2	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	198	-500535.00	982899.00	60.8 (b) 50.9	Pass
T13	120 - 100	Leg	ROHN 10 EH w/ angle 8x8x0.5	211	-518675.00	982763.00	61.0 (b) 52.8	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	212	-519178.00	982763.00	62.2 (b) 52.8	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	213	-517453.00	982763.00	62.2 (b) 52.7	Pass
T14	100 - 80	Leg	ROHN 10 EH w/ angle 8x8x0.5	244	-588739.00	982792.00	62.4 (b) 59.9	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	245	-589434.00	982792.00	60.0	Pass
		Leg	ROHN 10 EH w/ angle 8x8x0.5	246	-587426.00	982792.00	59.8	Pass
T15	80 - 60	Leg	ROHN 12 EH w/ angle 8x8x0.5	277	-660085.00	1136630.00	58.1	Pass
		Leg	ROHN 12 EH w/ angle 8x8x0.5	278	-661020.00	1136630.00	59.4 (b) 58.2	Pass
		Leg	ROHN 12 EH w/ angle 8x8x0.5	279	-658736.00	1136630.00	59.3 (b) 58.0	Pass
T16	60 - 30	Leg	ROHN 12 EH w/ angle 8x8x0.5	310	-731976.00	1136700.00	59.5 (b) 64.4	Pass
		Leg	ROHN 12 EH w/ angle 8x8x0.5	311	-733002.00	1136700.00	64.8 (b) 64.5	Pass
		Leg	ROHN 12 EH w/ angle 8x8x0.5	312	-730644.00	1136700.00	64.7 (b) 64.3	Pass
T17	30 - 0	Leg	ROHN 12 EHS w Angle 8x8x0.625	361	-839274.00	1402320.00	64.9 (b) 59.8	Pass
		Leg	ROHN 12 EHS w Angle 8x8x0.625	362	-840602.00	1402320.00	59.9	Pass
		Leg	ROHN 12 EHS w Angle	363	-837869.00	1402320.00	59.7	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	84 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail	
T1	320 - 304	Diagonal	8x8x0.625	7	-1318.90	11479.60	11.5	Pass	
			L1 3/4x1 3/4x3/16						22.8 (b)
			L1 3/4x1 3/4x3/16						11.5
			L1 3/4x1 3/4x3/16						22.8 (b)
			L1 3/4x1 3/4x3/16						11.4
			L1 3/4x1 3/4x3/16						22.4 (b)
			L1 3/4x1 3/4x3/16						11.3
			L1 3/4x1 3/4x3/16						22.4 (b)
			L1 3/4x1 3/4x3/16						11.6
			L1 3/4x1 3/4x3/16						23.1 (b)
			L1 3/4x1 3/4x3/16						11.6
			L1 3/4x1 3/4x3/16						23.1 (b)
			L1 3/4x1 3/4x3/16						9.4
			L1 3/4x1 3/4x3/16						18.5 (b)
			L1 3/4x1 3/4x3/16						9.4
			L1 3/4x1 3/4x3/16						18.5 (b)
			L1 3/4x1 3/4x3/16						9.2
			L1 3/4x1 3/4x3/16						18.0 (b)
			L1 3/4x1 3/4x3/16						9.1
			L1 3/4x1 3/4x3/16						18.0 (b)
			L1 3/4x1 3/4x3/16						9.7
			L1 3/4x1 3/4x3/16						19.2 (b)
			L1 3/4x1 3/4x3/16						9.7
			L1 3/4x1 3/4x3/16						19.2 (b)
			L1 3/4x1 3/4x3/16						7.4
			L1 3/4x1 3/4x3/16						14.7 (b)
			L1 3/4x1 3/4x3/16						7.4
			L1 3/4x1 3/4x3/16						14.7 (b)
			L1 3/4x1 3/4x3/16						7.2
			L1 3/4x1 3/4x3/16						14.1 (b)
L1 3/4x1 3/4x3/16	7.1								
L1 3/4x1 3/4x3/16	14.1 (b)								
L1 3/4x1 3/4x3/16	7.9								
L1 3/4x1 3/4x3/16	15.6 (b)								
L1 3/4x1 3/4x3/16	7.9								
L1 3/4x1 3/4x3/16	15.6 (b)								
L1 3/4x1 3/4x3/16	4.7								
L1 3/4x1 3/4x3/16	9.2 (b)								
L1 3/4x1 3/4x3/16	5.2								
L1 3/4x1 3/4x3/16	9.9 (b)								
L1 3/4x1 3/4x3/16	4.7								
L1 3/4x1 3/4x3/16	9.0 (b)								
L1 3/4x1 3/4x3/16	4.3								
L1 3/4x1 3/4x3/16	8.4 (b)								
L1 3/4x1 3/4x3/16	6.2								
L1 3/4x1 3/4x3/16	12.1 (b)								
L1 3/4x1 3/4x3/16	6.2								
L1 3/4x1 3/4x3/16	12.1 (b)								
L1 3/4x1 3/4x3/16	13.3								
L1 3/4x1 3/4x3/16	25.9 (b)								
L1 3/4x1 3/4x3/16	13.3								
L1 3/4x1 3/4x3/16	25.8 (b)								
L1 3/4x1 3/4x3/16	13.4								
L1 3/4x1 3/4x3/16	25.6 (b)								
L1 3/4x1 3/4x3/16	13.1								
L1 3/4x1 3/4x3/16	25.6 (b)								
L1 3/4x1 3/4x3/16	13.8								
L1 3/4x1 3/4x3/16	26.8 (b)								
L1 3/4x1 3/4x3/16	13.7								
L1 3/4x1 3/4x3/16	26.8 (b)								

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	85 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T3	300 - 280	Diagonal	L2x2x1/4	46	-2797.75	13009.80	21.5	Pass
							30.6 (b)	
		Diagonal	L2x2x1/4	47	-2936.33	13009.80	22.6	Pass
							30.4 (b)	
		Diagonal	L2x2x1/4	48	-2340.51	13009.80	18.0	Pass
							24.3 (b)	
		Diagonal	L2x2x1/4	49	-2234.06	13009.80	17.2	Pass
							24.4 (b)	
		Diagonal	L2x2x1/4	50	-3094.91	13009.80	23.8	Pass
							33.6 (b)	
		Diagonal	L2x2x1/4	51	-3084.02	13009.80	23.7	Pass
							33.7 (b)	
		Diagonal	L2x2x1/4	52	-2266.00	14300.60	15.8	Pass
							24.9 (b)	
		Diagonal	L2x2x1/4	53	-2279.03	14300.60	15.9	Pass
							24.8 (b)	
		Diagonal	L2x2x1/4	54	-2266.25	14300.60	15.8	Pass
							23.8 (b)	
		Diagonal	L2x2x1/4	55	-2181.75	14300.60	15.3	Pass
							23.9 (b)	
Diagonal	L2x2x1/4	56	-2578.62	14300.60	18.0	Pass		
					28.1 (b)			
Diagonal	L2x2x1/4	57	-2579.09	14300.60	18.0	Pass		
					28.1 (b)			
Diagonal	L2x2x1/4	58	-2108.38	15762.10	13.4	Pass		
					23.2 (b)			
Diagonal	L2x2x1/4	59	-2134.23	15762.10	13.5	Pass		
					23.1 (b)			
Diagonal	L2x2x1/4	60	-1704.75	15762.10	10.8	Pass		
					18.3 (b)			
Diagonal	L2x2x1/4	61	-1668.75	15762.10	10.6	Pass		
					18.3 (b)			
Diagonal	L2x2x1/4	62	-2122.00	15762.10	13.5	Pass		
					22.9 (b)			
Diagonal	L2x2x1/4	63	-2086.72	15762.10	13.2	Pass		
					23.0 (b)			
Diagonal	L2x2x1/4	64	-1982.10	17400.80	11.4	Pass		
					21.4 (b)			
Diagonal	L2x2x1/4	65	-2053.25	17400.80	11.8	Pass		
					21.3 (b)			
Diagonal	L2x2x1/4	66	-1454.62	17400.80	8.4	Pass		
					15.2 (b)			
Diagonal	L2x2x1/4	67	-1435.60	17400.80	8.3	Pass		
					15.2 (b)			
Diagonal	L2x2x1/4	68	-2006.53	17400.80	11.5	Pass		
					20.4 (b)			
Diagonal	L2x2x1/4	69	-1901.74	17400.80	10.9	Pass		
					20.5 (b)			
T4	280 - 260	Diagonal	L2 1/2x2 1/2x1/4	73	-4747.34	16785.10	28.3	Pass
							39.5 (b)	
		Diagonal	L2 1/2x2 1/2x1/4	74	-4796.71	16785.10	28.6	Pass
							39.4 (b)	
		Diagonal	L2 1/2x2 1/2x1/4	75	-4295.55	16785.10	25.6	Pass
							34.5 (b)	
		Diagonal	L2 1/2x2 1/2x1/4	76	-4203.96	16785.10	25.0	Pass
							34.6 (b)	
Diagonal	L2 1/2x2 1/2x1/4	77	-4701.76	16785.10	28.0	Pass		
					38.1 (b)			
Diagonal	L2 1/2x2 1/2x1/4	78	-4587.37	16785.10	27.3	Pass		
					38.2 (b)			
Diagonal	L2 1/2x2 1/2x1/4	79	-4203.19	18668.80	22.5	Pass		

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	86 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
		Diagonal	L2 1/2x2 1/2x1/4	80	-4332.74	18668.80	34.9 (b) 23.2	Pass
		Diagonal	L2 1/2x2 1/2x1/4	81	-3663.41	18668.80	34.8 (b) 19.6	Pass
		Diagonal	L2 1/2x2 1/2x1/4	82	-3524.49	18668.80	29.1 (b) 18.9	Pass
		Diagonal	L2 1/2x2 1/2x1/4	83	-4357.05	18668.80	29.2 (b) 23.3	Pass
		Diagonal	L2 1/2x2 1/2x1/4	84	-4254.45	18668.80	35.2 (b) 22.8	Pass
		Diagonal	L2 1/2x2 1/2x1/4	85	-3655.79	20825.20	35.3 (b) 17.6	Pass
		Diagonal	L2 1/2x2 1/2x1/4	86	-3836.85	20825.20	30.5 (b) 18.4	Pass
		Diagonal	L2 1/2x2 1/2x1/4	87	-2949.11	20825.20	30.3 (b) 14.2	Pass
		Diagonal	L2 1/2x2 1/2x1/4	88	-2823.74	20825.20	23.3 (b) 13.6	Pass
		Diagonal	L2 1/2x2 1/2x1/4	89	-3940.54	20825.20	23.4 (b) 18.9	Pass
		Diagonal	L2 1/2x2 1/2x1/4	90	-3847.13	20825.20	31.9 (b) 18.5	Pass
T5	260 - 240	Diagonal	L3x3x1/4	94	-8485.37	22180.60	32.0 (b) 38.3	Pass
		Diagonal	L3x3x1/4	95	-8264.06	22180.60	58.0 (b) 37.3	Pass
		Diagonal	L3x3x1/4	96	-7648.17	22180.60	58.2 (b) 34.5	Pass
		Diagonal	L3x3x1/4	97	-8138.74	22180.60	53.9 (b) 36.7	Pass
		Diagonal	L3x3x1/4	98	-6482.21	22180.60	53.7 (b) 29.2	Pass
		Diagonal	L3x3x1/4	99	-6230.89	22180.60	43.7 (b) 28.1	Pass
		Diagonal	L3x3x1/4	100	-6718.30	24277.90	43.8 (b) 27.7	Pass
		Diagonal	L3x3x1/4	101	-6691.15	24277.90	47.0 (b) 27.6	Pass
		Diagonal	L3x3x1/4	102	-6268.77	24277.90	47.0 (b) 25.8	Pass
		Diagonal	L3x3x1/4	103	-6423.37	24277.90	43.4 (b) 26.5	Pass
		Diagonal	L3x3x1/4	104	-6002.87	24277.90	43.4 (b) 24.7	Pass
		Diagonal	L3x3x1/4	105	-5804.19	24277.90	40.8 (b) 23.9	Pass
		Diagonal	L3x3x1/4	106	-5802.72	26649.70	40.9 (b) 21.8	Pass
		Diagonal	L3x3x1/4	107	-5806.88	26649.70	40.8 (b) 21.8	Pass
		Diagonal	L3x3x1/4	108	-5406.85	26649.70	40.8 (b) 20.3	Pass
		Diagonal	L3x3x1/4	109	-5414.35	26649.70	37.2 (b) 20.3	Pass
		Diagonal	L3x3x1/4	110	-5475.93	26649.70	37.1 (b) 20.5	Pass
		Diagonal	L3x3x1/4	111	-5331.36	26649.70	37.5 (b) 20.0	Pass
T6	240 - 220	Diagonal	L4x4x5/16	115	-13155.80	50268.80	37.5 (b) 26.2	Pass
							74.1 (b)	

<p>tnxTower</p> <p>AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	<p>Job</p> <p>320' Rohn SSVMW</p>	<p>Page</p> <p>87 of 95</p>
	<p>Project</p> <p>CSP Tower - Colchester, CT</p>	<p>Date</p> <p>12:07:36 05/18/20</p>
	<p>Client</p> <p>VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"</p>	<p>Designed by</p> <p>MCD</p>

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
		Diagonal	L4x4x5/16	116	-13074.70	50268.80	26.0	Pass
		Diagonal	L4x4x5/16	117	-13314.90	50268.80	74.2 (b) 26.5	Pass
		Diagonal	L4x4x5/16	118	-13340.70	50268.80	75.6 (b) 26.5	Pass
		Diagonal	L4x4x5/16	119	-10925.10	50268.80	75.4 (b) 21.7	Pass
		Diagonal	L4x4x5/16	120	-10926.30	50268.80	61.9 (b) 21.7	Pass
		Diagonal	L4x4x5/16	121	-12552.80	53365.30	61.9 (b) 23.5	Pass
		Diagonal	L4x4x5/16	122	-12154.00	53365.30	68.2 (b) 22.8	Pass
		Diagonal	L4x4x5/16	123	-12339.10	53365.30	68.3 (b) 23.1	Pass
		Diagonal	L4x4x5/16	124	-12659.20	53365.30	69.4 (b) 23.7	Pass
		Diagonal	L4x4x5/16	125	-10055.60	53365.30	69.2 (b) 18.8	Pass
		Diagonal	L4x4x5/16	126	-10103.10	53365.30	56.3 (b) 18.9	Pass
		Diagonal	L4x4x5/16	127	-10431.10	56723.40	56.3 (b) 18.4	Pass
		Diagonal	L4x4x5/16	128	-9855.64	56723.40	55.3 (b) 17.4	Pass
		Diagonal	L4x4x5/16	129	-9601.97	56723.40	55.5 (b) 16.9	Pass
		Diagonal	L4x4x5/16	130	-10289.20	56723.40	54.0 (b) 18.1	Pass
		Diagonal	L4x4x5/16	131	-7826.39	56723.40	53.9 (b) 13.8	Pass
		Diagonal	L4x4x5/16	132	-7675.05	56723.40	41.9 (b) 13.5	Pass
T7	220 - 200	Diagonal	L4x4x3/8	136	-17147.40	40783.20	42.0 (b) 42.0	Pass
		Diagonal	L4x4x3/8	137	-16367.70	40783.20	76.7 (b) 40.1	Pass
		Diagonal	L4x4x3/8	138	-16704.20	40783.20	76.9 (b) 41.0	Pass
		Diagonal	L4x4x3/8	139	-17336.80	40783.20	78.5 (b) 42.5	Pass
		Diagonal	L4x4x3/8	140	-13338.70	40783.20	78.3 (b) 32.7	Pass
		Diagonal	L4x4x3/8	141	-13530.20	40783.20	62.2 (b) 33.2	Pass
		Diagonal	L4x4x3/8	142	-15678.40	44725.40	62.2 (b) 35.1	Pass
		Diagonal	L4x4x3/8	143	-15344.20	44725.40	71.9 (b) 34.3	Pass
		Diagonal	L4x4x3/8	144	-15640.50	44725.40	72.1 (b) 35.0	Pass
		Diagonal	L4x4x3/8	145	-15848.00	44725.40	73.5 (b) 35.4	Pass
		Diagonal	L4x4x3/8	146	-12631.30	44725.40	73.3 (b) 28.2	Pass
		Diagonal	L4x4x3/8	147	-12632.50	44725.40	59.2 (b) 28.2	Pass
T8	200 - 180	Diagonal	L4x4x3/8	151	-21313.70	33828.90	59.2 (b) 63.0	Pass
		Diagonal	L4x4x3/8	152	-20973.10	33828.90	84.1 (b) 62.0	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	88 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
		Diagonal	L4x4x3/8	153	-21120.30	33828.90	84.3 (b) 62.4	Pass
		Diagonal	L4x4x3/8	154	-21398.20	33828.90	85.0 (b) 63.3	Pass
		Diagonal	L4x4x3/8	155	-16830.70	33828.90	84.7 (b) 49.8	Pass
		Diagonal	L4x4x3/8	156	-16829.00	33828.90	67.5 (b) 49.7	Pass
		Diagonal	L4x4x3/8	157	-20518.90	37111.10	67.5 (b) 55.3	Pass
		Diagonal	L4x4x3/8	158	-19714.90	37111.10	78.7 (b) 53.1	Pass
		Diagonal	L4x4x3/8	159	-20064.40	37111.10	78.9 (b) 54.1	Pass
		Diagonal	L4x4x3/8	160	-20719.40	37111.10	80.3 (b) 55.8	Pass
		Diagonal	L4x4x3/8	161	-15823.90	37111.10	80.1 (b) 42.6	Pass
		Diagonal	L4x4x3/8	162	-15967.10	37111.10	63.1 (b) 43.0	Pass
T9	180 - 170	Diagonal	L4x4x3/8	166	-22966.30	30962.40	63.1 (b) 74.2	Pass
		Diagonal	L4x4x3/8	167	-22534.80	30962.40	90.4 (b) 72.8	Pass
		Diagonal	L4x4x3/8	168	-22397.20	30962.40	90.7 (b) 72.3	Pass
		Diagonal	L4x4x3/8	169	-22892.30	30962.40	90.1 (b) 73.9	Pass
		Diagonal	L4x4x3/8	170	-17957.80	30962.40	89.9 (b) 58.0	Pass
		Diagonal	L4x4x3/8	171	-17951.40	30962.40	72.0 (b) 58.0	Pass
T10	170 - 160	Diagonal	L4x4x3/8	175	-23824.30	28413.70	72.0 (b) 83.8	Pass
		Diagonal	L4x4x3/8	176	-23363.10	28413.70	93.3 (b) 82.2	Pass
		Diagonal	L4x4x3/8	177	-23081.80	28413.70	93.5 (b) 81.2	Pass
		Diagonal	L4x4x3/8	178	-23668.70	28413.70	92.4 (b) 83.3	Pass
		Diagonal	L4x4x3/8	179	-18553.40	28413.70	92.1 (b) 65.3	Pass
		Diagonal	L4x4x3/8	180	-18545.10	28413.70	73.9 (b) 65.3	Pass
T11	160 - 140	Diagonal	L5x5x1/2	184	-29160.70	63217.20	73.9 (b) 46.1	Pass
		Diagonal	L5x5x1/2	185	-28558.00	63217.20	86.2 (b) 45.2	Pass
		Diagonal	L5x5x1/2	186	-27085.80	63217.20	85.3 (b) 42.8	Pass
		Diagonal	L5x5x1/2	187	-28339.20	63217.20	81.0 (b) 44.8	Pass
		Diagonal	L5x5x1/2	188	-23660.20	63217.20	83.8 (b) 37.4	Pass
		Diagonal	L5x5x1/2	189	-23066.40	63217.20	70.0 (b) 36.5	Pass
		Diagonal	L5x5x1/2	190	-26998.10	68040.50	68.8 (b) 39.7	Pass
		Diagonal	L5x5x1/2	191	-26846.20	68040.50	80.8 (b) 39.5	Pass
							80.9 (b)	

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	89 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T12	140 - 120	Diagonal	L5x5x1/2	192	-25958.60	68040.50	38.2	Pass
		Diagonal	L5x5x1/2	193	-26500.60	68040.50	78.3 (b)	Pass
		Diagonal	L5x5x1/2	194	-21501.90	68040.50	38.9	Pass
		Diagonal	L5x5x1/2	195	-21476.20	68040.50	78.3 (b)	Pass
		Diagonal	L5x5x1/2	199	-30916.30	53762.80	31.6	Pass
		Diagonal	L5x5x1/2	200	-30154.40	53762.80	64.6 (b)	Pass
		Diagonal	L5x5x1/2	201	-28057.70	53762.80	31.6	Pass
		Diagonal	L5x5x1/2	202	-29741.60	53762.80	64.6 (b)	Pass
		Diagonal	L5x5x1/2	203	-24921.80	53762.80	57.5	Pass
		Diagonal	L5x5x1/2	204	-23903.80	53762.80	91.4 (b)	Pass
		Diagonal	L5x5x1/2	205	-28372.50	58159.10	56.1	Pass
		Diagonal	L5x5x1/2	206	-28344.60	58159.10	90.5 (b)	Pass
		Diagonal	L5x5x1/2	207	-26408.70	58159.10	52.2	Pass
		Diagonal	L5x5x1/2	208	-26855.10	58159.10	84.3 (b)	Pass
T13	120 - 100	Diagonal	L5x5x1/2	209	-22530.30	58159.10	55.3	Pass
		Diagonal	L5x5x1/2	210	-22473.80	58159.10	87.9 (b)	Pass
		Diagonal	L5x5x1/2	215	-50783.80	63081.40	46.4	Pass
		Diagonal	ROHN 3 XXS	218	-49659.40	63081.40	73.7 (b)	Pass
		Diagonal	ROHN 3 XXS	222	-47760.80	63081.40	38.6	Pass
T14	100 - 80	Diagonal	ROHN 3 XXS	225	-49781.80	63081.40	67.9 (b)	Pass
		Diagonal	ROHN 3 XXS	231	-41491.90	63081.40	80.5	Pass
		Diagonal	ROHN 3 XXS	234	-40613.20	63081.40	78.7	Pass
		Diagonal	ROHN 3 XXS	248	-53199.60	59442.80	75.7	Pass
		Diagonal	ROHN 3 XXS	251	-51437.60	59442.80	78.9	Pass
		Diagonal	ROHN 3 XXS	255	-50772.90	59442.80	65.8	Pass
		Diagonal	ROHN 3 XXS	258	-52717.80	59442.80	64.4	Pass
T15	80 - 60	Diagonal	ROHN 3 XXS	264	-43783.30	59442.80	89.5	Pass
		Diagonal	ROHN 3 XXS	267	-43201.50	59442.80	86.5	Pass
		Diagonal	ROHN 3 XXS	281	-53145.50	55698.10	85.4 (b)	Pass
		Diagonal	ROHN 3 XXS	284	-50878.20	55698.10	48.8	Pass
		Diagonal	ROHN 3 XXS	288	-50034.90	55698.10	85.4 (b)	Pass
		Diagonal	ROHN 3 XXS	291	-52529.40	55698.10	38.7	Pass
T16	60 - 30	Diagonal	ROHN 3 XXS	297	-43005.40	55698.10	79.6 (b)	Pass
		Diagonal	ROHN 3 XXS	300	-42287.80	55698.10	67.7 (b)	Pass
		Diagonal	ROHN 4 EH	314	-75010.30	101988.00	38.6	Pass
		Diagonal	ROHN 4 EH	319	-71265.90	101988.00	67.9 (b)	Pass
		Diagonal	ROHN 4 EH	325	-70420.30	101988.00	69.9	Pass
		Diagonal	ROHN 4 EH	330	-74258.80	101988.00	70.2 (b)	Pass
		Diagonal	ROHN 4 EH	340	-61493.10	101988.00	69.0	Pass
		Diagonal	ROHN 4 EH	345	-60647.60	101988.00	69.4 (b)	Pass
		Diagonal	ROHN 4 EH	350	-74258.80	101988.00	72.8	Pass
		Diagonal	ROHN 4 EH	355	-74258.80	101988.00	73.2 (b)	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 90 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
							59.8 (b)	
T17	30 - 0	Diagonal	ROHN 4 EH	365	-73992.20	97939.00	75.5	Pass
		Diagonal	ROHN 4 EH	370	-71931.80	97939.00	73.4	Pass
		Diagonal	ROHN 4 EH	376	-69478.00	97939.00	70.9	Pass
		Diagonal	ROHN 4 EH	381	-72934.30	97939.00	74.5	Pass
		Diagonal	ROHN 4 EH	391	-57652.20	97939.00	58.9	Pass
		Diagonal	ROHN 4 EH	396	-56658.80	97939.00	57.9	Pass
T13	120 - 100	Horizontal	ROHN 3 STD	214	-27066.70	31679.40	85.4	Pass
		Horizontal	ROHN 3 STD	221	-26196.70	31679.40	82.7	Pass
		Horizontal	ROHN 3 STD	230	-21372.10	31679.40	67.5	Pass
T14	100 - 80	Horizontal	ROHN 3 EH	247	-30467.60	33455.50	91.1	Pass
		Horizontal	ROHN 3 EH	254	-30173.20	33455.50	90.2	Pass
		Horizontal	ROHN 3 EH	263	-24523.00	33455.50	73.3	Pass
T15	80 - 60	Horizontal	ROHN 3 XXS	280	-31433.60	43132.20	72.9	Pass
		Horizontal	ROHN 3 XXS	287	-30972.60	43132.20	71.8	Pass
		Horizontal	ROHN 3 XXS	296	-24572.60	43132.20	57.0	Pass
T16	60 - 30	Horizontal	ROHN 3.5 EH	313	-35097.20	38300.30	91.6	Pass
		Horizontal	ROHN 3.5 EH	324	-34544.40	38300.30	90.2	Pass
		Horizontal	ROHN 3.5 EH	339	-27287.90	38300.30	71.2	Pass
T17	30 - 0	Horizontal	ROHN 4 EH	364	-41666.30	47220.90	88.2	Pass
		Horizontal	ROHN 4 EH	375	-40964.30	47220.90	86.8	Pass
		Horizontal	ROHN 4 EH	390	-32007.60	47220.90	67.8	Pass
T1	320 - 304	Top Girt	L1 3/4x1 3/4x3/16	4	-193.63	5333.23	3.6	Pass
		Top Girt	L1 3/4x1 3/4x3/16	5	-193.80	5333.23	3.6	Pass
		Top Girt	L1 3/4x1 3/4x3/16	6	-193.13	5333.23	3.6	Pass
T3	300 - 280	Top Girt	L2x2x1/4	43	-69.39	9744.39	0.7	Pass
		Top Girt	L2x2x1/4	44	-68.56	9744.39	0.7	Pass
		Top Girt	L2x2x1/4	45	-69.63	9744.39	0.7	Pass
T13	120 - 100	Redund Horz 1 Bracing	ROHN 1.5 STD	216	-9009.14	14083.10	64.0	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	219	-9017.86	14083.10	64.0	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	223	-9017.86	14083.10	64.0	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	226	-8987.92	14083.10	63.8	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	232	-8987.92	14083.10	63.8	Pass
		Redund Horz 1 Bracing	ROHN 1.5 STD	235	-9009.14	14083.10	64.0	Pass
T14	100 - 80	Redund Horz 1 Bracing	P1.5x.145	249	-10226.40	11432.70	89.4	Pass
		Redund Horz 1 Bracing	P1.5x.145	252	-10238.40	11432.70	89.6	Pass
		Redund Horz 1 Bracing	P1.5x.145	256	-10238.40	11432.70	89.6	Pass
		Redund Horz 1 Bracing	P1.5x.145	259	-10203.60	11432.70	89.2	Pass
		Redund Horz 1 Bracing	P1.5x.145	265	-10203.60	11432.70	89.2	Pass
		Redund Horz 1 Bracing	P1.5x.145	268	-10226.40	11432.70	89.4	Pass
T15	80 - 60	Redund Horz 1 Bracing	ROHN 2 STD	282	-11471.20	20598.10	55.7	Pass
		Redund Horz 1 Bracing	ROHN 2 STD	285	-11487.40	20598.10	55.8	Pass
		Redund Horz 1 Bracing	ROHN 2 STD	289	-11487.40	20598.10	55.8	Pass
		Redund Horz 1 Bracing	ROHN 2 STD	292	-11447.80	20598.10	55.6	Pass
		Redund Horz 1 Bracing	ROHN 2 STD	298	-11447.80	20598.10	55.6	Pass

<p>tnxTower</p> <p>AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	Job	320' Rohn SSVMW	Page	91 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
		Bracing						
T16	60 - 30	Redund Horz 1	ROHN 2 STD	301	-11471.20	20598.10	55.7	Pass
		Bracing						
		Redund Horz 1	ROHN 1.5 STD	315	-12727.50	18282.30	69.6	Pass
		Bracing						
		Redund Horz 1	ROHN 1.5 STD	320	-12749.80	18282.30	69.7	Pass
		Bracing						
		Redund Horz 1	ROHN 1.5 STD	326	-12749.80	18282.30	69.7	Pass
T17	30 - 0	Bracing						
		Redund Horz 1	ROHN 1.5 STD	331	-12702.60	18282.30	69.5	Pass
		Bracing						
		Redund Horz 1	ROHN 1.5 STD	341	-12702.60	18282.30	69.5	Pass
		Bracing						
		Redund Horz 1	ROHN 1.5 STD	346	-12727.50	18282.30	69.6	Pass
		Bracing						
T16	60 - 30	Redund Horz 1	P1.5x.145	366	-14615.80	15339.00	95.3	Pass
		Bracing						
		Redund Horz 1	P1.5x.145	371	-14642.70	15339.00	95.5	Pass
		Bracing						
		Redund Horz 1	P1.5x.145	377	-14642.70	15339.00	95.5	Pass
		Bracing						
		Redund Horz 1	P1.5x.145	382	-14589.60	15339.00	95.1	Pass
T17	30 - 0	Bracing						
		Redund Horz 1	P1.5x.145	392	-14589.60	15339.00	95.1	Pass
		Bracing						
		Redund Horz 1	P1.5x.145	397	-14615.80	15339.00	95.3	Pass
		Bracing						
		Redund Horz 2	ROHN 2 XXS	316	-12727.50	18604.80	68.4	Pass
		Bracing						
T16	60 - 30	Redund Horz 2	ROHN 2 XXS	321	-12749.80	18604.80	68.5	Pass
		Bracing						
		Redund Horz 2	ROHN 2 XXS	327	-12749.80	18604.80	68.5	Pass
		Bracing						
		Redund Horz 2	ROHN 2 XXS	332	-12702.60	18604.80	68.3	Pass
		Bracing						
		Redund Horz 2	ROHN 2 XXS	342	-12702.60	18604.80	68.3	Pass
T17	30 - 0	Bracing						
		Redund Horz 2	ROHN 2 XXS	347	-12727.50	18604.80	68.4	Pass
		Bracing						
		Redund Horz 2	ROHN 2.5 EH	367	-14615.80	21919.90	66.7	Pass
		Bracing						
		Redund Horz 2	ROHN 2.5 EH	372	-14642.70	21919.90	66.8	Pass
		Bracing						
T16	60 - 30	Redund Horz 2	ROHN 2.5 EH	378	-14642.70	21919.90	66.8	Pass
		Bracing						
		Redund Horz 2	ROHN 2.5 EH	383	-14589.60	21919.90	66.6	Pass
		Bracing						
		Redund Horz 2	ROHN 2.5 EH	393	-14589.60	21919.90	66.6	Pass
		Bracing						
		Redund Horz 2	ROHN 2.5 EH	398	-14615.80	21919.90	66.7	Pass
T13	120 - 100	Bracing						
		Redund Diag 1	ROHN 2 STD	217	-8173.65	9352.65	87.4	Pass
		Bracing						
		Redund Diag 1	ROHN 2 STD	220	-8181.56	9352.65	87.5	Pass
		Bracing						
		Redund Diag 1	ROHN 2 STD	224	-8181.56	9352.65	87.5	Pass
		Bracing						
T16	60 - 30	Redund Diag 1	ROHN 2 STD	227	-8154.40	9352.65	87.2	Pass
		Bracing						
		Redund Diag 1	ROHN 2 STD	233	-8154.40	9352.65	87.2	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 92 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T14	100 - 80	Redund Diag 1 Bracing	ROHN 2 STD	236	-8173.65	9352.65	87.4	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	250	-8672.98	11364.10	76.3	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	253	-8683.21	11364.10	76.4	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	257	-8683.21	11364.10	76.4	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	260	-8653.66	11364.10	76.1	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	266	-8653.66	11364.10	76.1	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	269	-8672.98	11364.10	76.3	Pass
T15	80 - 60	Redund Diag 1 Bracing	ROHN 2 EH	283	-9174.00	10626.30	86.3	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	286	-9186.98	10626.30	86.5	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	290	-9186.98	10626.30	86.5	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	293	-9155.27	10626.30	86.2	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	299	-9155.27	10626.30	86.2	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	302	-9174.00	10626.30	86.3	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	317	-12843.60	13862.10	92.7	Pass
T16	60 - 30	Redund Diag 1 Bracing	ROHN 2 EH	322	-12866.10	13862.10	92.8	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	328	-12866.10	13862.10	92.8	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	333	-12818.50	13862.10	92.5	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	343	-12818.50	13862.10	92.5	Pass
		Redund Diag 1 Bracing	ROHN 2 EH	348	-12843.60	13862.10	92.7	Pass
		Redund Diag 1 Bracing	ROHN 2.5 STD	368	-13597.00	22579.60	60.2	Pass
		Redund Diag 1 Bracing	ROHN 2.5 STD	373	-13622.00	22579.60	60.3	Pass
T17	30 - 0	Redund Diag 1 Bracing	ROHN 2.5 STD	379	-13622.00	22579.60	60.3	Pass
		Redund Diag 1 Bracing	ROHN 2.5 STD	384	-13572.70	22579.60	60.1	Pass
		Redund Diag 1 Bracing	ROHN 2.5 STD	394	-13572.70	22579.60	60.1	Pass
		Redund Diag 1 Bracing	ROHN 2.5 STD	399	-13597.00	22579.60	60.2	Pass
		Redund Diag 2 Bracing	ROHN 2.5 STD	318	-8329.25	12742.30	65.4	Pass
		Redund Diag 2 Bracing	ROHN 2.5 STD	323	-8343.82	12742.30	65.5	Pass
		Redund Diag 2 Bracing	ROHN 2.5 STD	329	-8343.82	12742.30	65.5	Pass
T16	60 - 30	Redund Diag 2 Bracing	ROHN 2.5 STD	334	-8312.96	12742.30	65.2	Pass
		Redund Diag 2 Bracing	ROHN 2.5 STD	344	-8312.96	12742.30	65.2	Pass
		Redund Diag 2 Bracing	ROHN 2.5 STD	349	-8329.25	12742.30	65.4	Pass
		Redund Diag 2 Bracing	ROHN 2.5 STD	349	-8329.25	12742.30	65.4	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	93 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T17	30 - 0	Bracing Redund Diag 2	ROHN 2.5 STD	369	-9135.13	11206.60	81.5	Pass
		Bracing Redund Diag 2	ROHN 2.5 STD	374	-9151.97	11206.60	81.7	Pass
		Bracing Redund Diag 2	ROHN 2.5 STD	380	-9151.97	11206.60	81.7	Pass
		Bracing Redund Diag 2	ROHN 2.5 STD	385	-9118.79	11206.60	81.4	Pass
		Bracing Redund Diag 2	ROHN 2.5 STD	395	-9118.79	11206.60	81.4	Pass
		Bracing Redund Diag 2	ROHN 2.5 STD	400	-9135.13	11206.60	81.5	Pass
T13	120 - 100	Bracing Redund Hip 1	ROHN 1.5 STD	228	-48.78	12066.60	0.4	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	237	-40.74	12066.60	0.3	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	239	-49.03	12066.60	0.4	Pass
T14	100 - 80	Bracing Redund Hip 1	ROHN 1.5 STD	261	-48.04	9943.20	0.5	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	270	-41.45	9943.20	0.4	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	272	-47.92	9943.20	0.5	Pass
T15	80 - 60	Bracing Redund Hip 1	ROHN 1.5 STD	294	-47.06	8378.50	0.6	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	303	-39.79	8378.50	0.5	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	305	-46.57	8378.50	0.6	Pass
T16	60 - 30	Bracing Redund Hip 1	ROHN 1.5 STD	335	-171.63	15708.50	1.1	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	350	-144.13	15708.50	0.9	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	354	-175.83	15708.50	1.1	Pass
T17	30 - 0	Bracing Redund Hip 1	ROHN 1.5 STD	386	-152.91	12924.00	1.2	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	401	-125.52	12924.00	1.0	Pass
		Bracing Redund Hip 1	ROHN 1.5 STD	405	-157.40	12924.00	1.2	Pass
T16	60 - 30	Bracing Redund Hip 2	ROHN 2 STD	336	-93.41	8559.02	1.1	Pass
		Bracing Redund Hip 2	ROHN 2 STD	351	-78.61	8559.02	0.9	Pass
		Bracing Redund Hip 2	ROHN 2 STD	355	-95.51	8559.02	1.1	Pass
T17	30 - 0	Bracing Redund Hip 2	ROHN 2 STD	387	-87.63	6941.18	1.3	Pass
		Bracing Redund Hip 2	ROHN 2 STD	402	-73.06	6941.18	1.1	Pass
		Bracing Redund Hip 2	ROHN 2 STD	406	-89.81	6941.18	1.3	Pass
T13	120 - 100	Bracing Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	229	-97.06	10450.60	0.9	Pass
		Bracing Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	238	-80.65	10450.60	0.8	Pass
		Bracing Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	240	-96.74	10450.60	0.9	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	94 of 95
	Project	CSP Tower - Colchester, CT	Date	12:07:36 05/18/20
	Client	VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T14	100 - 80	Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	262	-91.08	9375.46	1.0	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	271	-79.56	9375.46	0.8	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	273	-88.18	9375.46	0.9	Pass
T15	80 - 60	Redund Hip Diagonal 1 Bracing	ROHN 3 STD	295	-102.08	16617.70	0.6	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 3 STD	304	-95.73	16617.70	0.6	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 3 STD	306	-102.08	16617.70	0.6	Pass
T16	60 - 30	Redund Hip Diagonal 1 Bracing	ROHN 2 STD	337	-348.86	5254.92	6.6	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 2 STD	352	-279.34	5254.92	5.3	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 2 STD	356	-360.74	5254.92	6.9	Pass
T17	30 - 0	Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	388	-315.32	10840.00	2.9	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	403	-249.57	10840.00	2.3	Pass
		Redund Hip Diagonal 1 Bracing	ROHN 2.5 STD	407	-327.42	10840.00	3.0	Pass
T16	60 - 30	Redund Hip Diagonal 2 Bracing	ROHN 2 STD	338	-141.61	3255.91	4.3	Pass
		Redund Hip Diagonal 2 Bracing	ROHN 2 STD	353	-141.12	3255.91	4.3	Pass
		Redund Hip Diagonal 2 Bracing	ROHN 2 STD	357	-143.01	3255.91	4.4	Pass
T17	30 - 0	Redund Hip Diagonal 2 Bracing	ROHN 2.5 STD	389	-139.41	6453.40	2.2	Pass
		Redund Hip Diagonal 2 Bracing	ROHN 2.5 STD	404	-139.16	6453.40	2.2	Pass
		Redund Hip Diagonal 2 Bracing	ROHN 2.5 STD	408	-140.44	6453.40	2.2	Pass
T13	120 - 100	Inner Bracing	ROHN 3 STD	241	-27.79	29370.40	0.4	Pass
		Inner Bracing	ROHN 3 STD	242	-23.51	29370.40	0.4	Pass
		Inner Bracing	ROHN 3 STD	243	-27.38	29370.40	0.4	Pass
T14	100 - 80	Inner Bracing	ROHN 3 STD	274	-27.56	24201.90	0.4	Pass
		Inner Bracing	ROHN 3 STD	275	-23.86	24201.90	0.4	Pass
		Inner Bracing	ROHN 3 STD	276	-26.46	24201.90	0.4	Pass
T15	80 - 60	Inner Bracing	ROHN 3 STD	307	-31.26	20393.40	0.4	Pass
		Inner Bracing	ROHN 3 STD	308	-28.68	20393.40	0.4	Pass
		Inner Bracing	ROHN 3 STD	309	-29.93	20393.40	0.4	Pass
T16	60 - 30	Inner Bracing	ROHN 3 STD	358	-59.87	17239.70	0.5	Pass
		Inner Bracing	ROHN 3 STD	359	-59.49	17239.70	0.5	Pass
		Inner Bracing	ROHN 3 STD	360	-60.20	17239.70	0.5	Pass
T17	30 - 0	Inner Bracing	ROHN 3 STD	409	-62.35	13981.00	0.5	Pass
		Inner Bracing	ROHN 3 STD	410	-62.04	13981.00	0.5	Pass
		Inner Bracing	ROHN 3 STD	411	-62.56	13981.00	0.6	Pass

Summary

Leg (T16)	64.9	Pass
Diagonal (T15)	95.4	Pass
Horizontal (T16)	91.6	Pass
Top Girt (T1)	3.6	Pass
Redund Horz 1	95.5	Pass

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 95 of 95
	Project CSP Tower - Colchester, CT	Date 12:07:36 05/18/20
	Client VZW-217/EMP-008/EVS-010/CSP 2020 Revision - "H"	Designed by MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
						Bracing (T17)		
						Redund Horz 2	68.5	Pass
						Bracing (T16)		
						Redund Diag 1	92.8	Pass
						Bracing (T16)		
						Redund Diag 2	81.7	Pass
						Bracing (T17)		
						Redund Hip 1 Bracing (T17)	1.2	Pass
						Redund Hip 2 Bracing (T17)	1.3	Pass
						Redund Hip Diagonal 1 Bracing (T16)	6.9	Pass
						Redund Hip Diagonal 2 Bracing (T16)	4.4	Pass
						Inner Bracing (T17)	0.6	Pass
						Bolt Checks	93.5	Pass
						RATING =	95.5	Pass

ANCHOR BOLT EVALUATION

Job	<u>320' Rohn SSMW - Colchester, CT</u>	Project No.	<u>EMP / VZW / EVS</u>	Sheet	<u>1</u> of <u>4</u>
Description	<u>Anchor Bolt Analysis (TIA-222-H) (Addendum 1)</u>	Computed by	<u>MCD</u>	Date	<u>05/18/20</u>
	<u>Proposed Inventory - Modification Analysis</u>	Checked by	<u> </u>	Date	<u> </u>

ANCHOR BOLT ANALYSIS

Input Data

Tower Reactions:

Uplift:	Uplift := 740.586·kips	<i>user input</i>
Shear:	Shear := 129.314·kips	<i>user input</i>
Compression:	Compression := 942.660·kips	<i>user input</i>

Anchor Bolt Data:

Use ASTM A354 Grade BC [ref. ROHN Drawing A971600, dated 9/23/1999]

Number of Anchor Bolts = N	$N := 24$	<i>user input</i>
Bolt Ultimate Strength:	$F_u := 125 \cdot \text{ksi}$	<i>user input</i>
Bolt Yield Strength:	$F_y := 109 \cdot \text{ksi}$	<i>user input</i>
Bolt Modulus:	$E := 29000 \cdot \text{ksi}$	<i>user input</i>
Thickness of Anchor Bolts	$D := 1.0 \cdot \text{in}$	<i>user input</i>
Threads per Inch:	$n := 8$	<i>user input</i>
Coefficient of Friction:	$\mu := 0.55$	<i>user input</i> (for baseplate with grout ASCE 10-15)
Length from top of pier to bottom of leveling nut:	$L_{ar} := 0 \cdot \text{in}$	<i>user input</i>
Bolt Modulus:	$E_{\text{WW}} := 29000 \cdot \text{ksi}$	<i>user input</i>

Job	<u>320' Rohn SSMW - Colchester, CT</u>	Project No.	<u>EMP / VZW / EVS</u>	Sheet	<u>2</u> of <u>4</u>
Description	<u>Anchor Bolt Analysis (TIA-222-H) (Addendum 1)</u>	Computed by	<u>MCD</u>	Date	<u>05/18/20</u>
	<u>Proposed Inventory - Modification Analysis</u>	Checked by	<u> </u>	Date	<u> </u>

Anchor Bolt Section Properties:

Gross Area of Bolt:

$$A_g := \frac{\pi}{4} \cdot D^2 \qquad A_g = 0.79 \cdot \text{in}^2$$

Net Area of Bolt:

$$A_n := \frac{\pi}{4} \cdot \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 \qquad A_n = 0.61 \cdot \text{in}^2$$

Net Diameter:

$$D_n := D - \frac{0.9743 \text{in}}{n} \qquad D_n = 0.88 \cdot \text{in}$$

Radius of Gyration of Bolt:

$$r := \frac{D_n}{4} \qquad r = 0.22 \cdot \text{in}$$

Plastic Section Modulus of Bolt:

$$Z_x := \frac{D_n^3}{6} \qquad Z_x = 0.11 \cdot \text{in}^3$$

Forces:

Tension Force:

$$T_u := \frac{\text{Uplift}}{N}$$

$$T_u = 30.86 \cdot \text{kip} \qquad T_{ub} := T_u$$

Resistance Factor for Flexure (TIA-222-H 4.9.9):

$$\phi_f := 0.9$$

Resistance Factor for Anchor Bolt (Compression (TIA-222-H 4.9.9 Addendum 1)):

$$\phi_c := 0.90$$

Compression Force:

$$P_{uc} := \frac{\text{Compression}}{N}$$

$$P_{uc} = 39.28 \cdot \text{kip} \qquad P_{ucb} := P_{uc}$$

Resistance Factor for Tension (TIA-222-H 4.9.9):

$$\phi_t := 0.75$$

Shear Force:

$$V_u := \frac{\text{Shear}}{N}$$

$$V_u = 5.39 \cdot \text{kip} \qquad V_{ub} := V_u$$

Resistance Factor for Shear (TIA-222-H 4.9.9):

$$\phi_v := 0.75$$

TIA-222-H 4.9.9 Calculate Equation Variables Strength Design:

Design Tensile Strength, R_{nt} :

$$R_{nt} := F_u \cdot A_n$$

$$R_{nt} = 75.72 \cdot \text{ft} \cdot \text{kip}$$

$$\phi_t \cdot R_{nt} = 56.79 \cdot \text{ft} \cdot \text{kip}$$

Design Compression Strength, R_{nc} :

$$R_{nc} := F_y \cdot A_g$$

$$R_{nc} = 85.61 \cdot \text{ft} \cdot \text{kip}$$

$$\phi_c \cdot R_{nc} = 77.05 \cdot \text{ft} \cdot \text{kip}$$

Design Shear Strength (Tension), R_{nv} :

$$R_{nv} := 0.5 \cdot F_u \cdot A_g$$

$$R_{nv} = 49.09 \cdot \text{ft} \cdot \text{kip}$$

$$\phi_v \cdot R_{nv} = 36.82 \cdot \text{ft} \cdot \text{kip}$$

Design Shear Strength (Compression), R_{nvc} :

$$R_{nvc} := 0.6 \cdot F_y \cdot 0.75 A_g$$

$$R_{nvc} = 38.52 \cdot \text{ft} \cdot \text{kip}$$

$$\phi_c \cdot R_{nvc} = 34.67 \cdot \text{ft} \cdot \text{kip}$$

NOTE: Per TIA-222-H The determination of capacity formulas are based on the existing constructed condition of exposed anchor rod from the top of the foundation to the bottom of the (base) leveling nut., Therefore the following equations next page), reflects for this tower site, the first formula shall be applied:

$l_{ar} = 3" - 1.75" \text{ (nut height)} = 1.25" < 1.0 \text{ Bolt Diameter}$, however bearing on grouted pad, therefore consider (1x(d)) anchor bolted considerations (TIA-222-H- Section 4.9.9 Addendum 1)

Job	<u>320' Rohn SSMW - Colchester, CT</u>	Project No.	<u>EMP / VZW / EVS</u>	Sheet	<u>4</u> of <u>4</u>
Description	<u>Anchor Bolt Analysis (TIA-222-H) (Addendum 1)</u>	Computed by	<u>MCD</u>	Date	<u>05/18/20</u>
	<u>Proposed Inventory - Modification Analysis</u>	Checked by	_____	Date	_____

TIA-222-H 4.9.9 Combined Shear and Tension:

$$\left[\frac{T_{ub}}{(\phi_t \cdot R_{nt})} \right]^2 + \left[\frac{V_{ub}}{(\phi_v \cdot R_{nv})} \right]^2 \leq 1$$

$$\left[\frac{T_{ub}}{(\phi_t \cdot R_{nt})} \right]^2 + \left(\frac{V_{ub}}{\phi_v \cdot R_{nv}} \right)^2 = 0.32$$

TIA-222-H 4.9.9 Combined Shear and Compression:

$$\left[\frac{P_{ucb}}{(\phi_c \cdot R_{nc})} \right] + \left(\frac{V_{ub}}{\phi_c \cdot R_{nvc}} \right)^2 \leq 1$$

$$\left[\frac{P_{ucb}}{(\phi_c \cdot R_{nc})} \right] + \left(\frac{V_{ub}}{\phi_c \cdot R_{nvc}} \right)^2 = 0.53$$

NOTE: Larger ratio number shown above Governs design Capacity.

Combined Shear and Tension/Compression Check:

$$\text{ShearAndTensionCheck} := \text{if} \left[\max \left[\left[\frac{V_{ub}}{(\phi_v \cdot R_{nv})} \right]^2 + \left[\frac{T_{ub}}{(\phi_t \cdot R_{nt})} \right]^2, \left[\frac{P_{ucb}}{(\phi_c \cdot R_{nc})} \right] + \left(\frac{V_{ub}}{\phi_c \cdot R_{nvc}} \right)^2 \right] \leq 1, \text{"OK"}, \text{"NO GOOD"} \right]$$

ShearAndTensionCheck = "OK"

FOUNDATION EVALUATION

Job	<u>320' Rohn SSVMW - Colchester, CT</u>	Project No.	<u>EMP / VZW / EVS</u>	Sheet	<u>1</u> of <u>2</u>
Description	<u>Evaluation of Drilled Pier Caisson</u>	Computed by	<u>MCD</u>	Date	<u>05/18/20</u>
	<u>Proposed Inventory - Modification Analysis</u>	Checked by		Date	

3 SIDED SELF SUPPORTING TOWER FOUNDATION DRILLED PIER

Compression:	Download := 942.660 kips	$\gamma_c := 150 \text{ pcf}$	Concrete unit weight	
Uplift:	uplift := 740.586 kips	$\gamma_w := 62.4 \text{ pcf}$	Water unit weight	
Depth Neglected for Skin Friction at the top	Depthunbond := 4 ft	$\gamma_s := 120 \text{ pcf}$	Soil unit weight	
Drill Caisson length	CaissonLength := 35.5 ft	Pier$\phi := 7.5 \text{ ft}$	Pier diameter	
Water Table Below grade:	Wd := 10 ft	Per BL Companies Report 9.13.2000	hg := 0.5 ft	Height of Pier Above grade
Ave allowable Shear at Depth of 4' to 10'	f1 := (380psf) · 2.0		SoilBearingCapacity = (6.7ksf) · 2.0	
Ave allowable Shear at Depth of 10' to 35'	f2 := (700psf) · 2.0		Allowable Bearing Pressure at Depth 35' x 2 for Ultimate Bearing Capacity (TIA-222-H)	

NOTE: Values indicated as "Allowable Stress" figures are increased, Per TIA-222-H Section 9.7 (Design Strength), Allowable values may be multiplied to obtain Design Strength values before applying reduction factors.

Loading:

$$\text{TotalDownload} := \text{Download} + 1.2 \cdot \left[\pi \cdot \frac{\text{Pier}\phi^2}{4} \cdot (\text{CaissonLength} \cdot \gamma_c) \right]$$

TotalDownload = 1224.96 kips

$$\text{Pierweight} := 0.9 \cdot \left[\pi \cdot \frac{\text{Pier}\phi^2}{4} \cdot [(\text{Wd} + \text{hg}) \cdot \gamma_c + (\text{CaissonLength} - \text{Wd} - \text{hg}) \cdot (\gamma_c - \gamma_w)] \right]$$

Pierweight = 149.7 kips

$$\text{SoilShear} := \pi \cdot \text{Pier}\phi \cdot [f1 \cdot (\text{Wd} - \text{Depthunbond}) + f2 \cdot (\text{CaissonLength} - \text{Wd} - \text{hg})]$$

SoilShear = 932.11 kips

Compression Capacity:

$$\text{TotalDownloadCapacity} := 0.75 \cdot \text{SoilShear} + 0.75 \cdot \text{SoilBearingCapacity} \cdot \left(\pi \cdot \frac{\text{Pier}\phi^2}{4} \right)$$

TotalDownloadCapacity = 1143.08 kips

NOTE: 0.75 reduction factor for foundation bearing (TIA-H Section 9.7)

Tension Capacity:

$$\text{TotalUpLiftCapacity} := 0.75 \cdot \text{SoilShear} + 0.75 \cdot \text{Pierweight}$$

TotalUpLiftCapacity = 811.36 kips

NOTE: 0.75 reduction factor for foundation uplift of caisson (TIA-H Section 9.7)

Job	<u>320' Rohn SSVMW - Colchester, CT</u>	Project No.	<u>EMP / VZW / EVS</u>	Sheet	<u>2</u> of <u>2</u>
Description	<u>Evaluation of Drilled Pier Caisson</u>	Computed by	<u>MCD</u>	Date	<u>05/18/20</u>
	<u>Proposed Inventory - Modification Analysis</u>	Checked by	<u> </u>	Date	<u> </u>

Check Cone Failure

$$\text{ConeFailureCapacity} := \frac{[(\text{CaissonLength} - \text{hg}) \cdot \tan(30 \cdot \text{deg}) \cdot 2 + \text{Pier}\phi]^2 \cdot \pi \cdot \text{CaissonLength} - \text{hg}}{4} \cdot \frac{\text{CaissonLength} - \text{hg}}{3} \cdot (69 \text{pcf})$$

NOTE: "69 pcf" is the approximate average of submerged soil (25 ft) and dry soil (10.5 ft) considered in uplifting failure cone.

$$\text{ConeFailureCapacity} = 1451.51 \cdot \text{kips}$$

$$\text{CheckConeFailureCapacity} := \text{if}(\text{uplift} < \text{ConeFailureCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckConeFailureCapacity} = \text{"Okay"}$$

$$\frac{\text{uplift}}{0.75 \text{ConeFailureCapacity}} = 68.0\%$$

Foundation Check (Previous foundation Mod. designed by URS dated 7/13/2012 (vz5-122)):

Add Concrete around existing caisson foundations

$$L_{\text{modification}} := 12 \text{ft} \quad \text{Depth}_{\text{modification}} := 4 \text{ft}$$

$$\text{Area}_{\text{modification}} := L_{\text{modification}}^2 - \pi \cdot \frac{\text{Pier}\phi^2}{4} \quad \text{Area}_{\text{modification}} = 99.82 \text{ft}^2$$

$$\text{Weight}_{\text{modification}} := \text{Area}_{\text{modification}} \cdot \text{Depth}_{\text{modification}} \cdot \gamma_c \quad \text{Weight}_{\text{modification}} = 59.89 \cdot \text{kip}$$

$$\text{SoilBearingCapacity}_{4\text{ft}} := (2 \text{kSF}) \cdot 2.0 \quad \text{Ultimate Soil Bearing Capacity at 4' Below --> Based on Boring Logs}$$

$$\text{TotalDownLoad}_2 := \text{TotalDownLoad} + 1.2 \text{Weight}_{\text{modification}} \quad \text{TotalDownLoad}_2 = 1296.83 \cdot \text{kip}$$

$$\text{TotalDownLoadCapacity}_2 := \text{TotalDownLoadCapacity} + 0.75(\text{Area}_{\text{modification}} \cdot \text{SoilBearingCapacity}_{4\text{ft}})$$

$$\text{TotalDownLoadCapacity}_2 = 1442.54 \cdot \text{kip}$$

$$\text{CheckDownLoadCapacity}_2 := \text{if}(\text{TotalDownLoad}_2 < \text{TotalDownLoadCapacity}_2, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckDownLoadCapacity}_2 = \text{"Okay"}$$

$$\frac{\text{TotalDownLoad}_2}{\text{TotalDownLoadCapacity}_2} = 89.9\%$$

$$\text{TotalUpLiftCapacity}_2 := \text{TotalUpLiftCapacity} + 0.9 \text{Weight}_{\text{modification}}$$

$$\text{TotalUpLiftCapacity}_2 = 865.26 \cdot \text{kips}$$


$$\text{CheckUpLiftCapacity}_2 := \text{if}(\text{uplift} < \text{TotalUpLiftCapacity}_2, \text{"Okay"}, \text{"No Good"})$$

$$\frac{\text{uplift}}{\text{TotalUpLiftCapacity}_2} = 85.59\%$$

$$\text{CheckUpLiftCapacity}_2 = \text{"Okay"}$$

ANALYSIS UNDER TIA-222-F DESIGN CRITERIA (DESPP / CSP)

Section	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	T15	T16	T17
Legs	ROHN 5 EH	ROHN 6 EH	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5
Leg Grade	L1 3/4x1 3/4x3/16	L2x2x1/4	L2 1/2x2 1/2x1/4	L3x3x1/4	L4x4x5/16	L4x4x3/8	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2
Diagonals	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36	A36
Diagonal Grade	L1 3/4x1 3/4x3/16	L2x2x1/4	L2 1/2x2 1/2x1/4	L3x3x1/4	L4x4x5/16	L4x4x3/8	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2	L5x5x1/2
Top Girts	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Horizontals	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Red. Horizontals	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Red. Diagonals	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Red. Hips	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Inner Bracing	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.	N.A.
Face Width (ft)	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69	40.69
# Panels @ (ft)	5 @ 4	4 @ 5	4 @ 5	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667
Weight (lb)	1442.1	348.7	2498.3	5997.7	8484.4	7298.6	3730.8	3785.3	9668.6	9975.3	15115.4	11450.5	9875.5	3047	33.14	33.14	17941.9



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod 5/8x4' (Lightning Rod)	329	CBC78T-DS-43-2X Diplexer (Verizon (Prev. Prop.))	232
Dual Lights (Beacon)	327	CBC78T-DS-43-2X Diplexer (Verizon (Prev. Prop.))	232
PD128-1 (ECI-1)	325	PIROD 12' Lightweight T-Frame (ATI)	200
6' Side Mount Standoff (ECI-1)	325	PIROD 12' Lightweight T-Frame (ATI)	200
BA1012-0 (ECI-2)	320	PIROD 12' Lightweight T-Frame (ATI)	200
6' Side Mount Standoff (ECI-2)	320	7770.00 (ATI)	200
ANT450F6 (ECI-3)	318	HPA-65R-BUJU-H8 Panel (ATI (Prev. Proposed))	200
4x4" Pipe Mount (ECI-3)	318	RRUS-32 (ATI (Prev. Proposed))	200
SC479-HF1LDF (ECI-4)	300	RRUS-11 (ATI (Prev. Proposed))	200
6' Side Mount Standoff (ECI-4)	300	7770.00 (ATI)	200
PD340-1 (ECI-5)	290	HPA-65R-BUJU-H8 Panel (ATI (Prev. Proposed))	200
6' Side Mount Standoff (ECI-5)	290	RRUS-32 (ATI (Prev. Proposed))	200
DB809T3E-XC (ECI-6)	286	RRUS-11 (ATI (Prev. Proposed))	200
6' Side Mount Standoff (ECI-7)	284	7770.00 (ATI)	200
SC479-HF1LDF(D001-E6085) (Inverted) (ECI-7)	283	HPA-65R-BUJU-H8 Panel (ATI (Prev. Proposed))	200
PD440-2 (ECI-8)	264	RRUS-32 (ATI (Prev. Proposed))	200
6' Side Mount Standoff (ECI-8)	260	RRUS-11 (ATI (Prev. Proposed))	200
SC479-HF1LDF (ECI-10)	251	7770.00 (ATI)	200
PD1142-1 (ECI-14)	248	HPA-65R-BUJU-H6 Panel (ATI (Prev. Proposed))	200
6' Side Mount Standoff (ECI-14)	248	RRUS-32 (ATI (Prev. Proposed))	200
430-94C-09168-M-11048 TTA (ECI-11)	247	RRUS-11 (ATI (Prev. Proposed))	200
Sabre T-Boom (1) (ECI-10, 11, 12, 13)	246	DC6-48-60-0-8C Squid / Surge Arrestor (ATI (Prev. Proposed))	200
SC479-HF1LDF(D001-E6085) (Inverted) (ECI-13)	245	STK-U Stiffener Side Arm Attachment (ATI)	200
SC479-HF1LDF(D001-E6085) (Inverted) (ECI-12)	245	STK-U Stiffener Side Arm Attachment (ATI)	200
6' Side Mount Standoff (ECI-15)	238	STK-U Stiffener Side Arm Attachment (ATI)	200
531-70HD Exposed Dipole Antenna (ECI-15)	238	STK-U Stiffener Side Arm Attachment (ATI)	200
Valmont VFA-10-U V-Frame (Verizon)	232	STK-U Stiffener Side Arm Attachment (ATI)	200
Valmont VFA-10-U V-Frame (Verizon)	232	Pirot 4' Side Mount Standoff (1) (ECI-50)	179
Valmont VFA-10-U V-Frame (Verizon)	232	DB586-Y (ECI-50)	179
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	232	DB586-Y (ECI-51)	177
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	232	Pirot 4' Side Mount Standoff (1) (ECI-53,52,51)	176
JAHH-65B-R3B Panel Antenna (Verizon-PCS (Prev. Prop.))	232	430-94C-09168-M-11048 TTA (ECI-52)	176
LNx-6512DS-VTM (Verizon-850)	232	DB586-Y (inverted) (ECI-53)	175
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2) (Verizon-PCS/AWS (Prev. Prop.))	232	L-810 Obstruction Lighting (1) (ECI-54)	168
RFV01U-D1A RRH Unit (Verizon RRH (Prev. Prop.))	232	L-810 Obstruction Lighting (1) (ECI-55)	165
RFV01U-D2A RRH Unit (Verizon RRH (Prev. Prop.))	232	L-810 Obstruction Lighting (1) (ECI-56)	164
DB-B1-6C-12AB-0Z / DC-3315-PF-48 Dist. Box (Verizon)	232	Telewave ANT220F2 - Omni Antenna (Eversource (Proposed #1))	163
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	232	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed) (Eversource (Proposed #1))	160
JAHH-65B-R3B Panel Antenna (Verizon-PCS (Prev. Prop.))	232	5'3"x4" Pipe Mount (ECI-58a (Dish Support))	154
LNx-6512DS-VTM (Verizon-850)	232	Commscope PAR6-59W-PXA/A (ECI-58)	154
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2) (Verizon-PCS/AWS (Prev. Prop.))	232	5'3"x4" Pipe Mount (ECI-57)	153
RFV01U-D1A RRH Unit (Verizon RRH (Prev. Prop.))	232	ANT450F6 (ECI-57)	153
DB-B1-6C-12AB-0Z / DC-3315-PF-48 Dist. Box (Verizon)	232	Telewave ANT220F2 - Omni Antenna (Eversource (Proposed #2))	145
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	232	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed) (Eversource (Proposed #1))	142
JAHH-65B-R3B Panel Antenna (Verizon-PCS (Prev. Prop.))	232	4' Side Mount Standoff (ECI-60 .59)	139
LNx-6512DS-VTM (Verizon-850)	232	PD156S (ECI-60)	139
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2) (Verizon-PCS/AWS (Prev. Prop.))	232	DB212-1 (ECI-59)	139
RFV01U-D1A RRH Unit (Verizon RRH (Prev. Prop.))	232	3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-61a)	117
DB-B1-6C-12AB-0Z / DC-3315-PF-48 Dist. Box (Verizon)	232	8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-63a (Dish Ice Shield))	115
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	232	5'3"x4" Pipe Mount (ECI-61a (Dish Support))	112
JAHH-65B-R3B Panel Antenna (Verizon-PCS (Prev. Prop.))	232	Andrew 2' w/Radome (ECI-61)	112
LNx-6512DS-VTM (Verizon-850)	232	5'3"x4" Pipe Mount (ECI-63 (Dish Support))	107
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2) (Verizon-PCS/AWS (Prev. Prop.))	232	PA8-65 (ECI-63)	107
RFV01U-D1A RRH Unit (Verizon RRH (Prev. Prop.))	232	Pirot 4' Side Mount Standoff (1) (ECI-62)	106
RFV01U-D2A RRH Unit (Verizon RRH (Prev. Prop.))	232	PD458 (ECI-62)	106
CBC78T-DS-43-2X Diplexer (Verizon (Prev. Prop.))	232	4'x4" Pipe Mount (ECI-66)	94
		PD688S-4 (ECI-66)	94

MATERIAL STRENGTH


GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi

TOWER DESIGN NOTES

1. Tower designed for a 90 mph basic wind in accordance with the TIA/EIA-222-F Standard.
2. Tower is also designed for a 90 mph basic wind with 0.50 in ice.
3. Deflections are based upon a 90 mph wind.


MAX. CORNER REACTIONS AT BASE:
 DOWN: 945667 lb
 SHEAR: 123290 lb

UPLIFT: -746402 lb
 SHEAR: 105013 lb



AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job: 320' Rohn SSMW Project: CSP Tower - Colchester, CT	Client: DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Drawn by: MCD	App'd:
	Code: TIA/EIA-222-F	Date: 05/18/20	Scale: NTS	
	Path:			
				Dwg No. E-1

Section	T17	T16	T15	T14	T13	T12	T11	T10	T9	T8	T7	T6	T5	T4	T3	T2	T1
Legs	A	ROHN 12 EH w/ angle 8x8x0.5	ROHN 10 EH w/ angle 8x8x0.5	ROHN 10 EH w/ angle 8x8x0.5	ROHN 10 EH w/ angle 8x8x0.5	ROHN 8 EH w/ angle 8x8x0.5	ROHN 6 EH	ROHN 5 EH									
Leg Grade																	
Diagonals		ROHN 4 EH	ROHN 3 XXS	ROHN 3 XXS	ROHN 3 XXS	ROHN 3 STD											
Diagonal Grade																	
Top Girts																	
Horizontals		ROHN 4 EH	ROHN 3.5 EH	ROHN 3.5 EH	ROHN 3.5 EH	ROHN 3 STD											
Red. Horizontals		P1.5x.145	ROHN 1.5 STD	ROHN 2 STD	ROHN 2 STD	E											
Red. Diagonals		ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD	ROHN 2.5 STD												
Red. Hips			ROHN 1.5 STD	ROHN 1.5 STD	ROHN 1.5 STD												
Inner Bracing			ROHN 3 STD	ROHN 3 STD	ROHN 3 STD												
Face Width (ft)	40.89	36.8	33.14	30.47	27.97	25.39	21.3	20.28	19.22	17.09	15.09	13.08	11.04	8.85			6.81
# Panels @ (ft)		2 @ 30	3 @ 20	3 @ 20	3 @ 20	3 @ 20	10 @ 10	10 @ 10	10 @ 10	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	9 @ 6.66667	4 @ 5	5 @ 4	5 @ 4
Weight (lb)	125382.3	17941.9	15115.4	11450.5	9675.5	9144.9	9006.6	3795.3	3750.8	7298.6	6406.0	6464.4	5409.2	5967.7	2496.3	340.7	1442.1



SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	ROHN 12 EHS w Angle 8x8x0.625	D	N.A.
B	L1 3/4x1 3/4x3/16	E	ROHN 1.5 STD
C	L2 1/2x2 1/2x1/4		

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi


TOWER DESIGN NOTES

1. Tower designed for a 90 mph basic wind in accordance with the TIA/EIA-222-F Standard.
2. Tower is also designed for a 90 mph basic wind with 0.50 in ice.
3. Deflections are based upon a 90 mph wind.


MAX. CORNER REACTIONS AT BASE:

DOWN: 945667 lb
SHEAR: 123290 lb

UPLIFT: -746402 lb
SHEAR: 105013 lb



TORQUE 629 kip-ft
90 mph WIND - 0.5000 in ICE






TORQUE 373 kip-ft
REACTIONS - 90 mph WIND

AECOM
500 Enterprise Drive, Suite 3B
Rocky Hill, CT
Phone: 860-263-5800
FAX: 860-812-2094

Job: **320' Rohn SSVMW**
Project: **CSP Tower - Colchester, CT**
Client: **DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied**
Code: **TIA/EIA-222-F**
Path: C:\Users\mcd\Documents\320' Rohn SSVMW\320' Rohn SSVMW.dwg

Drawn by: **MCD** App'd:
Date: **05/18/20** Scale: **NTS**
Dwg No. **E-1**



AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094		Job: 320' Rohn SSMW	
		Project: CSP Tower - Colchester, CT	
Client: DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied		Drawn by: MCD	App'd:
Code: TIA/EIA-222-F		Date: 05/18/20	Scale: NTS
Path:		Dwg No. E-5	

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	1 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 320.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 6.81 ft at the top and 40.69 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Basic wind speed of 90 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56 pcf.

A wind speed of 90 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 90 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile √ Include Bolts In Member Capacity Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) √ SR Members Have Cut Ends SR Members Are Concentric | <ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks Use Azimuth Dish Coefficients Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination √ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs | <ul style="list-style-type: none"> Use ASCE 10 X-Brace Ly Rules √ Calculate Redundant Bracing Forces Ignore Redundant Members in FEA √ SR Leg Bolts Resist Compression √ All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feed Line Torque √ Include Angle Block Shear Check Use TIA-222-G Bracing Resist. Exemption Use TIA-222-G Tension Splice Exemption <div style="background-color: #e0e0e0; text-align: center; padding: 2px; margin: 5px 0;">Poles</div> <ul style="list-style-type: none"> Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 2 of 41
	Project CSP Tower - Colchester, CT	Date 11:26:38 05/18/20
	Client DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by MCD



Triangular Tower

Tower Section Geometry

<i>Tower Section</i>	<i>Tower Elevation</i>	<i>Assembly Database</i>	<i>Description</i>	<i>Section Width</i>	<i>Number of Sections</i>	<i>Section Length</i>
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	320.00-304.00			6.81	1	16.00
T2	304.00-300.00			6.81	1	4.00
T3	300.00-280.00			6.81	1	20.00
T4	280.00-260.00			8.85	1	20.00
T5	260.00-240.00			11.04	1	20.00
T6	240.00-220.00			13.08	1	20.00
T7	220.00-200.00			15.09	1	20.00
T8	200.00-180.00			17.09	1	20.00
T9	180.00-170.00			19.22	1	10.00
T10	170.00-160.00			20.26	1	10.00
T11	160.00-140.00			21.30	1	20.00
T12	140.00-120.00			23.21	1	20.00
T13	120.00-100.00			25.39	1	20.00
T14	100.00-80.00			27.97	1	20.00
T15	80.00-60.00			30.47	1	20.00
T16	60.00-30.00			33.14	1	30.00
T17	30.00-0.00			36.80	1	30.00

Tower Section Geometry (cont'd)

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	3 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Tower Section	Tower Elevation ft	Diagonal Spacing ft	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset in	Bottom Girt Offset in
T1	320.00-304.00	4.00	X Brace	No	No	0.0000	0.0000
T2	304.00-300.00	4.00	X Brace	No	No	0.0000	0.0000
T3	300.00-280.00	5.00	X Brace	No	No	0.0000	0.0000
T4	280.00-260.00	6.67	X Brace	No	No	0.0000	0.0000
T5	260.00-240.00	6.67	X Brace	No	No	0.0000	0.0000
T6	240.00-220.00	6.67	X Brace	No	No	0.0000	0.0000
T7	220.00-200.00	10.00	X Brace	No	No	0.0000	0.0000
T8	200.00-180.00	10.00	X Brace	No	No	0.0000	0.0000
T9	180.00-170.00	10.00	X Brace	No	No	0.0000	0.0000
T10	170.00-160.00	10.00	X Brace	No	No	0.0000	0.0000
T11	160.00-140.00	10.00	X Brace	No	No	0.0000	0.0000
T12	140.00-120.00	10.00	X Brace	No	No	0.0000	0.0000
T13	120.00-100.00	20.00	K1 Down	No	Yes	0.0000	0.0000
T14	100.00-80.00	20.00	K1 Down	No	Yes	0.0000	0.0000
T15	80.00-60.00	20.00	K1 Down	No	Yes	0.0000	0.0000
T16	60.00-30.00	30.00	K2 Down	No	Yes	0.0000	0.0000
T17	30.00-0.00	30.00	K2 Down	No	Yes	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T1 320.00-304.00	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Equal Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)
T2 304.00-300.00	Pipe	ROHN 5 EH	A572-50 (50 ksi)	Equal Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)
T3 300.00-280.00	Pipe	ROHN 6 EH	A572-50 (50 ksi)	Equal Angle	L2x2x1/4	A36 (36 ksi)
T4 280.00-260.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L2 1/2x2 1/2x1/4	A36 (36 ksi)
T5 260.00-240.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L3x3x1/4	A572-50 (50 ksi)
T6 240.00-220.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x5/16	A572-50 (50 ksi)
T7 220.00-200.00	Arbitrary Shape	ROHN 8 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T8 200.00-180.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T9 180.00-170.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T10 170.00-160.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L4x4x3/8	A572-50 (50 ksi)
T11 160.00-140.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L5x5x1/2	A572-50 (50 ksi)
T12 140.00-120.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Equal Angle	L5x5x1/2	A572-50 (50 ksi)
T13 120.00-100.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T14 100.00-80.00	Arbitrary Shape	ROHN 10 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T15 80.00-60.00	Arbitrary Shape	ROHN 12 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T16 60.00-30.00	Arbitrary Shape	ROHN 12 EH w/ angle 8x8x0.5	A572-50 (50 ksi)	Pipe	ROHN 4 EH	A572-50 (50 ksi)
T17 30.00-0.00	Arbitrary Shape	ROHN 12 EHS w Angle	A572-50	Pipe	ROHN 4 EH	A572-50

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	4 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

<i>Tower Elevation</i> <i>ft</i>	<i>Leg Type</i>	<i>Leg Size</i>	<i>Leg Grade</i>	<i>Diagonal Type</i>	<i>Diagonal Size</i>	<i>Diagonal Grade</i>
		8x8x0.625	(50 ksi)			(50 ksi)

Tower Section Geometry (cont'd)

<i>Tower Elevation</i> <i>ft</i>	<i>Top Girt Type</i>	<i>Top Girt Size</i>	<i>Top Girt Grade</i>	<i>Bottom Girt Type</i>	<i>Bottom Girt Size</i>	<i>Bottom Girt Grade</i>
T1 320.00-304.00	Equal Angle	L1 3/4x1 3/4x3/16	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T3 300.00-280.00	Equal Angle	L2x2x1/4	A36 (36 ksi)	Solid Round		A36 (36 ksi)

Tower Section Geometry (cont'd)

<i>Tower Elevation</i> <i>ft</i>	<i>No. of Mid Girts</i>	<i>Mid Girt Type</i>	<i>Mid Girt Size</i>	<i>Mid Girt Grade</i>	<i>Horizontal Type</i>	<i>Horizontal Size</i>	<i>Horizontal Grade</i>
T13 120.00-100.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T14 100.00-80.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3 EH	A572-50 (50 ksi)
T15 80.00-60.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3 XXS	A572-50 (50 ksi)
T16 60.00-30.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 3.5 EH	A572-50 (50 ksi)
T17 30.00-0.00	None	Flat Bar		A36 (36 ksi)	Pipe	ROHN 4 EH	A572-50 (50 ksi)

Tower Section Geometry (cont'd)

<i>Tower Elevation</i> <i>ft</i>	<i>Secondary Horizontal Type</i>	<i>Secondary Horizontal Size</i>	<i>Secondary Horizontal Grade</i>	<i>Inner Bracing Type</i>	<i>Inner Bracing Size</i>	<i>Inner Bracing Grade</i>
T13 120.00-100.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T14 100.00-80.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T15 80.00-60.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T16 60.00-30.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)
T17 30.00-0.00	Pipe		A572-50 (50 ksi)	Pipe	ROHN 3 STD	A572-50 (50 ksi)

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	5 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Tower Section Geometry (cont'd)

Tower Elevation	Redundant Bracing Grade	Redundant Type	Redundant Size	K Factor
ft				
T13 120.00-100.00	A572-50 (50 ksi)	Horizontal (1) Diagonal (1) Hip (1)	Pipe Pipe Pipe	1 1 1
T14 100.00-80.00	A572-50 (50 ksi)	Hip Diagonal (1) Horizontal (1) Diagonal (1) Hip (1)	Pipe Pipe Pipe Pipe	1 1 1 1
T15 80.00-60.00	A572-50 (50 ksi)	Hip Diagonal (1) Horizontal (1) Diagonal (1) Hip (1)	Pipe Pipe Pipe Pipe	1 1 1 1
T16 60.00-30.00	A572-50 (50 ksi)	Hip Diagonal (1) Horizontal (1) Horizontal (2) Diagonal (1) Diagonal (2) Hip (1) Hip (2)	Pipe Pipe Pipe Pipe Pipe Pipe Pipe	1 1 1 1 1 1 1
T17 30.00-0.00	A572-50 (50 ksi)	Hip Diagonal (1) Hip Diagonal (2) Horizontal (1) Horizontal (2) Diagonal (1) Diagonal (2) Hip (1) Hip (2) Hip Diagonal (1) Hip Diagonal (2)	Pipe Pipe Pipe Pipe Pipe Pipe Pipe Pipe Pipe Pipe	1 1 1 1 1 1 1 1 1 1

Tower Section Geometry (cont'd)

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft ²	in					in	in	in
T1 320.00-304.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T2 304.00-300.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T3 300.00-280.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T4 280.00-260.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T5 260.00-240.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T6 240.00-220.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T7 220.00-200.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	36.0000	36.0000
T8	0.00	0.0000	A36	1	1	1	36.0000	36.0000	36.0000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	8 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1	Flange	1.0000	6	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
320.00-304.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T2	Flange	1.0000	8	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
304.00-300.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T3	Flange	1.0000	8	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
300.00-280.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T4	Flange	1.0000	8	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
280.00-260.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T5	Flange	1.0000	8	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
260.00-240.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T6	Flange	1.0000	12	0.7500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
240.00-220.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T7	Flange	1.0000	12	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
220.00-200.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T8	Flange	1.0000	12	0.8750	1	0.6250	0	0.0000	0	0.6250	0	0.6250	0	0.6250	0
200.00-180.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T9	Flange	1.0000	0	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
180.00-170.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T10	Flange	1.0000	12	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
170.00-160.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T11	Flange	1.0000	12	0.8750	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
160.00-140.00		A325N		A325X		A325N		A325N		A325N		A325N		A325N	
T12	Flange	1.0000	12	0.7500	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
140.00-120.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T13	Flange	1.0000	16	0.7500	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
120.00-100.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T14	Flange	1.0000	16	0.7500	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
100.00-80.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T15	Flange	1.0000	16	0.8750	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
80.00-60.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T16	Flange	1.0000	24	0.8750	3	0.6250	0	0.6250	0	0.6250	0	0.7500	2	0.6250	0
60.00-30.00		A325N		A325X		A325N		A325N		A325N		A325X		A325N	
T17 30.00-0.00	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
		A325N		A325N		A325N		A325N		A325N		A325N		A325N	

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
1 5/8 (AT&T)	A	Yes	No	Ar (CaAa)	200.00 - 5.00	0.0000	-0.42	6	6	1.9800	1.9800		1.04
1 5/8 (Verizon)	C	Yes	No	Ar (CaAa)	220.00 - 5.00	0.0000	-0.4	6	6	1.9800	1.9800		1.04
1 5/8" Hybriflex (VZW)	C	Yes	No	Ar (CaAa)	220.00 - 5.00	0.0000	-0.46	2	2	1.6000	1.6000		1.85
LC78-50JA-A	B	Yes	No	Ar (CaAa)	174.00 -	0.0000	0.48	1	1	1.0900	1.0900		0.28

Job	320' Rohn SSVMW	Page	9 of 41
Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
7 (Cable # 34 HTS)					5.00								
LC78-50JA-A	B	Yes	No	Ar (CaAa)	177.00 - 5.00	0.0000	0.47	1	1	1.0900	1.0900		0.28
7 (Cable # 33 HTS)													
LDF4-50A (1/2 FOAM)	B	Yes	No	Ar (CaAa)	174.00 - 5.00	3.0000	0.48	1	1	0.6300	0.6300		0.15
7 (Cable # 32 HTS)													
LC78-50JA-A	B	Yes	No	Ar (CaAa)	176.00 - 5.00	3.0000	0.47	1	1	1.0900	1.0900		0.28
7 (Cable # 31 HTS)													
LC78-50JA-A	B	Yes	No	Ar (CaAa)	137.00 - 5.00	3.0000	0.46	1	1	1.0900	1.0900		0.28
7 (Cable #30 HTS)													
LC78-50JA-A	B	Yes	No	Ar (CaAa)	134.00 - 5.00	3.0000	0.45	1	1	1.0900	1.0900		0.28
7 (Cable # 29 HTS)													
LC78-50JA-A	B	Yes	No	Ar (CaAa)	105.00 - 5.00	3.0000	0.44	1	1	1.0900	1.0900		0.28
7 (Cable # 28 HTS)													
LC78-50JA-A	B	Yes	No	Ar (CaAa)	103.30 - 5.00	3.0000	0.43	1	1	1.0900	1.0900		0.28
7 (Cable # 27 HTS)													
LC78-50JA-A	B	Yes	No	Ar (CaAa)	91.00 - 5.00	0.0000	0.43	1	1	1.0900	1.0900		0.28
7 (Cable #26 HTS)													
LC78-50JA-A	B	Yes	No	Ar (CaAa)	90.00 - 5.00	0.0000	0.42	1	1	1.0900	1.0900		0.28
7 (Cable #25 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	283.00 - 5.00	3.0000	0.41	1	1	1.9800	1.9800		0.72
7 (Cable #24 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	284.00 - 5.00	0.0000	0.41	1	1	1.9800	1.9800		0.72
7 (Cable # 21 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	261.00 - 5.00	0.0000	0.4	1	1	1.9800	1.9800		0.72
7 (Cable # 20 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	285.00 - 5.00	3.0000	0.4	1	1	1.9800	1.9800		0.72

Job	320' Rohn SSVMW	Page	10 of 41
Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
FOAM) (Cable #23 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	248.00 - 5.00	0.0000	0.39	1	1	1.9800	1.9800		0.72
(Cable # 19 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	285.00 - 5.00	3.0000	0.39	1	1	1.9800	1.9800		0.72
(Cable # 22 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	246.00 - 5.00	0.0000	0.38	1	1	1.9800	1.9800		0.72
(Cable # 16 HTS)													
AVA7-50 (1-5/8 LOW DENS. FOAM)	B	Yes	No	Ar (CaAa)	246.00 - 5.00	3.0000	0.38	1	1	1.9800	1.9800		0.72
(Cable # 17 HTS)													
LDF4-50A (1/2 FOAM)	B	Yes	No	Ar (CaAa)	246.00 - 5.00	6.0000	0.38	1	1	0.6300	0.6300		0.15
(Cable # 18 HTS)													
LC78-50JA-A7	B	Yes	No	Ar (CaAa)	235.00 - 5.00	0.0000	0.37	1	1	1.0900	1.0900		0.28
(Cable # 15 HTS)													
WE65 (Cable # 14 HTS)	B	Yes	No	Af (CfAe)	106.00 - 5.00	3.0000	0.37	1	1	1.5836	1.5836	5.1284	0.53
LC78-50JA-A7	B	Yes	No	Ar (CaAa)	244.00 - 5.00	0.0000	0.36	1	1	1.0900	1.0900		0.28
(Cable # 13 HTS)													
LC78-50JA-A7	B	Yes	No	Ar (CaAa)	262.00 - 5.00	0.0000	0.35	1	1	1.0900	1.0900		0.28
(Cable #12 HTS)													
WE108 (Cable # 11 HTS)	B	Yes	No	Af (CfAe)	113.00 - 5.00	3.0000	0.35	1	1	1.0149	1.0149	3.4851	0.35
LC78-50JA-A7	B	Yes	No	Ar (CaAa)	297.00 - 5.00	0.0000	0.34	1	1	1.0900	1.0900		0.28
(Cable # 10 HTS)													
LC78-50JA-A7	B	Yes	No	Ar (CaAa)	290.00 - 5.00	0.0000	0.33	1	1	1.0900	1.0900		0.28
(Cable # 9 HTS)													
1/2 (Cable # 8 HTS)	B	Yes	No	Ar (CaAa)	284.00 - 5.00	3.0000	0.33	1	1	0.5800	0.5800		0.25

<p style="text-align: center;">tnxTower</p> <p style="text-align: center;">AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	Job 320' Rohn SSVMW										Page 11 of 41	
	Project CSP Tower - Colchester, CT										Date 11:26:38 05/18/20	
	Client DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied										Designed by MCD	

Description	Face or Leg	Allow Shield	Exclude From Torque Calculation	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
1/2 (Cable # 6 HTS)	B	Yes	No	Ar (CaAa)	320.00 - 5.00	6.0000	0.33	1	1	0.5800	0.5800		0.25
LC78-50JA-A 7 (Cable # 4 HTS)	B	Yes	No	Ar (CaAa)	320.00 - 5.00	0.0000	0.32	1	1	1.0900	1.0900		0.28
1/2 (Cable # 7 HTS)	B	Yes	No	Ar (CaAa)	284.00 - 5.00	3.0000	0.32	1	1	0.5800	0.5800		0.25
1/2 (Cable # 5 HTS)	B	Yes	No	Ar (CaAa)	164.00 - 5.00	6.0000	0.32	1	1	0.5800	0.5800		0.25
LC78-50JA-A 7 (Cable #3 HTS)	B	Yes	No	Ar (CaAa)	316.50 - 5.00	0.0000	0.31	1	1	1.0900	1.0900		0.28
LC78-50JA-A 7 (Cable #1 HTS)	B	Yes	No	Ar (CaAa)	318.00 - 5.00	0.0000	0.29	1	1	1.0900	1.0900		0.28
LC78-50JA-A 7 (Cable #2 HTS) * CSP Proposed Cables EW63 (@ 145 Leg "C")	B	Yes	No	Ar (CaAa)	153.00 - 5.00	3.0000	0.29	1	1	1.0900	1.0900	5.0668	0.28
LC78-50JA-A 7 (@ 120 "eg "B")	B	Yes	No	Ar (CaAa)	120.00 - 5.00	0.0000	0.28	1	1	1.0900	1.0900		0.28
1-5/8" Fiber Optic CaBLE (AT&T)	A	Yes	No	Ar (CaAa)	200.00 - 5.00	0.0000	-0.37	1	1	1.9800	1.9800		1.85
1/2 (AT&T) * Eversource Proposed Cables	A	Yes	No	Ar (CaAa)	200.00 - 5.00	0.0000	-0.35	2	2	0.5800	0.5800		0.25
LDF5-50A (7/8 FOAM) (Eversource - Proposed)	B	Yes	No	Ar (CfAe)	163.00 - 5.00	0.0000	0.27	1	1	1.0900	1.0900		0.33
LDF5-50A (7/8 FOAM) (Eversource - Proposed)	B	No	No	Ar (CfAe)	145.00 - 5.00	0.0000	0.26	1	1	1.0900	1.0900		0.33

Feed Line/Linear Appurtenances Section Areas

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	12 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Tower Section	Tower Elevation ft	Face	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
T1	320.00-304.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	5.561	0.000	15.90
		C	0.000	0.000	0.000	0.000	0.00
T2	304.00-300.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	1.540	0.000	4.36
		C	0.000	0.000	0.000	0.000	0.00
T3	300.00-280.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	14.473	0.000	43.60
		C	0.000	0.000	0.000	0.000	0.00
T4	280.00-260.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	30.636	0.000	101.88
		C	0.000	0.000	0.000	0.000	0.00
T5	260.00-240.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	41.134	0.000	137.02
		C	0.000	0.000	0.000	0.000	0.00
T6	240.00-220.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	53.315	0.000	176.60
		C	0.000	0.000	0.000	0.000	0.00
T7	220.00-200.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	53.860	0.000	178.00
		C	0.000	0.000	30.160	0.000	198.80
T8	200.00-180.00	A	0.000	0.000	30.040	0.000	171.80
		B	0.000	0.000	53.860	0.000	178.00
		C	0.000	0.000	30.160	0.000	198.80
T9	180.00-170.00	A	0.000	0.000	15.020	0.000	85.90
		B	0.000	0.000	29.035	0.000	94.36
		C	0.000	0.000	15.080	0.000	99.40
T10	170.00-160.00	A	0.000	0.000	15.020	0.000	85.90
		B	0.273	0.000	31.062	0.000	100.89
		C	0.000	0.000	15.080	0.000	99.40
T11	160.00-140.00	A	0.000	0.000	30.040	0.000	171.80
		B	2.271	0.656	64.237	0.000	217.24
		C	0.000	0.000	30.160	0.000	198.80
T12	140.00-120.00	A	0.000	0.000	30.040	0.000	171.80
		B	3.633	2.624	68.379	0.000	240.48
		C	0.000	0.000	30.160	0.000	198.80
T13	120.00-100.00	A	0.000	0.000	30.040	0.000	171.80
		B	3.633	4.515	72.445	0.000	258.65
		C	0.000	0.000	30.160	0.000	198.80
T14	100.00-80.00	A	0.000	0.000	30.040	0.000	171.80
		B	3.633	6.954	78.189	0.000	283.28
		C	0.000	0.000	30.160	0.000	198.80
T15	80.00-60.00	A	0.000	0.000	30.040	0.000	171.80
		B	3.633	6.954	80.260	0.000	288.60
		C	0.000	0.000	30.160	0.000	198.80
T16	60.00-30.00	A	0.000	0.000	45.060	0.000	257.70
		B	5.450	10.432	120.390	0.000	432.90
		C	0.000	0.000	45.240	0.000	298.20
T17	30.00-0.00	A	0.000	0.000	37.550	0.000	214.75
		B	4.542	8.693	100.325	0.000	360.75
		C	0.000	0.000	37.700	0.000	248.50

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
T1	320.00-304.00	A	0.500	0.000	0.000	0.000	0.000	0.00

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSMW	Page	13 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
		B		0.000	0.000	11.411	0.000	67.73
		C		0.000	0.000	0.000	0.000	0.00
T2	304.00-300.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	3.140	0.000	18.65
		C		0.000	0.000	0.000	0.000	0.00
T3	300.00-280.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	27.673	0.000	172.33
		C		0.000	0.000	0.000	0.000	0.00
T4	280.00-260.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	54.936	0.000	363.24
		C		0.000	0.000	0.000	0.000	0.00
T5	260.00-240.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	72.134	0.000	482.98
		C		0.000	0.000	0.000	0.000	0.00
T6	240.00-220.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	92.815	0.000	622.93
		C		0.000	0.000	0.000	0.000	0.00
T7	220.00-200.00	A	0.500	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	93.860	0.000	629.19
		C		0.000	0.000	46.160	0.000	431.91
T8	200.00-180.00	A	0.500	0.000	0.000	48.747	0.000	409.29
		B		0.000	0.000	93.860	0.000	629.19
		C		0.000	0.000	46.160	0.000	431.91
T9	180.00-170.00	A	0.500	0.000	0.000	24.373	0.000	204.64
		B		0.000	0.000	51.135	0.000	339.23
		C		0.000	0.000	23.080	0.000	215.95
T10	170.00-160.00	A	0.500	0.000	0.000	24.373	0.000	204.64
		B		0.522	0.000	55.462	0.000	368.08
		C		0.000	0.000	23.080	0.000	215.95
T11	160.00-140.00	A	0.500	0.000	0.000	48.747	0.000	409.29
		B		4.354	0.934	115.537	0.000	797.38
		C		0.000	0.000	46.160	0.000	431.91
T12	140.00-120.00	A	0.500	0.000	0.000	48.747	0.000	409.29
		B		6.967	3.735	123.479	0.000	892.39
		C		0.000	0.000	46.160	0.000	431.91
T13	120.00-100.00	A	0.500	0.000	0.000	48.747	0.000	409.29
		B		6.967	6.682	131.275	0.000	968.58
		C		0.000	0.000	46.160	0.000	431.91
T14	100.00-80.00	A	0.500	0.000	0.000	48.747	0.000	409.29
		B		6.967	10.288	142.289	0.000	1070.83
		C		0.000	0.000	46.160	0.000	431.91
T15	80.00-60.00	A	0.500	0.000	0.000	48.747	0.000	409.29
		B		6.967	10.288	146.260	0.000	1094.60
		C		0.000	0.000	46.160	0.000	431.91
T16	60.00-30.00	A	0.500	0.000	0.000	73.120	0.000	613.93
		B		10.450	15.432	219.390	0.000	1641.90
		C		0.000	0.000	69.240	0.000	647.86
T17	30.00-0.00	A	0.500	0.000	0.000	60.933	0.000	511.61
		B		8.708	12.860	182.825	0.000	1368.25
		C		0.000	0.000	57.700	0.000	539.88

Feed Line Shielding

Section	Elevation ft	Face	A_R ft ²	A_R Ice ft ²	A_F ft ²	A_F Ice ft ²
T1	320.00-304.00	A	0.000	0.000	0.000	0.000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	14 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section	Elevation	Face	A_R	$A_{R, Ice}$	A_F	$A_{F, Ice}$
	ft		ft ²	ft ²	ft ²	ft ²
		B	0.000	0.509	0.434	0.891
		C	0.000	0.000	0.000	0.000
T2	304.00-300.00	A	0.000	0.000	0.000	0.000
		B	0.000	0.126	0.109	0.221
		C	0.000	0.000	0.000	0.000
T3	300.00-280.00	A	0.000	0.000	0.000	0.000
		B	0.000	1.010	1.056	2.020
		C	0.000	0.000	0.000	0.000
T4	280.00-260.00	A	0.000	0.000	0.000	0.000
		B	0.000	1.380	1.924	3.450
		C	0.000	0.000	0.000	0.000
T5	260.00-240.00	A	0.000	0.000	0.000	0.000
		B	0.000	1.718	2.939	5.155
		C	0.000	0.000	0.000	0.000
T6	240.00-220.00	A	0.000	0.000	0.000	0.000
		B	0.000	2.140	4.917	8.560
		C	0.000	0.000	0.000	0.000
T7	220.00-200.00	A	0.000	0.000	0.000	0.000
		B	0.000	1.535	3.524	6.141
		C	0.000	0.755	1.973	3.020
T8	200.00-180.00	A	0.000	0.749	1.906	2.994
		B	0.000	1.489	3.417	5.955
		C	0.000	0.732	1.913	2.928
T9	180.00-170.00	A	0.000	0.367	0.935	1.470
		B	0.000	0.796	1.808	3.184
		C	0.000	0.359	0.939	1.437
T10	170.00-160.00	A	0.000	0.364	0.926	1.455
		B	0.000	0.865	1.935	3.458
		C	0.000	0.356	0.930	1.423
T11	160.00-140.00	A	0.000	0.719	2.287	3.594
		B	0.000	1.843	5.117	9.213
		C	0.000	0.703	2.296	3.515
T12	140.00-120.00	A	0.000	0.709	2.256	3.545
		B	0.000	1.995	5.536	9.974
		C	0.000	0.693	2.265	3.467
T13	120.00-100.00	A	1.699	3.613	0.000	0.000
		B	4.527	11.083	0.000	0.000
		C	1.706	3.534	0.000	0.000
T14	100.00-80.00	A	1.627	3.459	0.000	0.000
		B	4.805	11.786	0.000	0.000
		C	1.633	3.383	0.000	0.000
T15	80.00-60.00	A	1.619	3.415	0.000	0.000
		B	4.893	11.924	0.000	0.000
		C	1.626	3.340	0.000	0.000
T16	60.00-30.00	A	2.737	5.703	0.000	0.000
		B	8.271	19.909	0.000	0.000
		C	2.748	5.577	0.000	0.000
T17	30.00-0.00	A	2.351	4.810	0.000	0.000
		B	7.104	16.793	0.000	0.000
		C	2.360	4.704	0.000	0.000

Feed Line Center of Pressure

Section	Elevation	CP_x	CP_z	CP_x, Ice	CP_z, Ice
	ft	in	in	in	in
T1	320.00-304.00	3.3623	0.9930	5.2035	1.4807

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	15 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section	Elevation	CP _X	CP _Z	CP _X	CP _Z
				Ice	Ice
	ft	in	in	in	in
T2	304.00-300.00	3.8443	1.1325	5.8879	1.6755
T3	300.00-280.00	7.0359	2.4105	9.9448	3.2627
T4	280.00-260.00	9.7443	3.9639	14.0090	5.4122
T5	260.00-240.00	13.4278	5.6935	18.7298	7.5687
T6	240.00-220.00	16.4445	7.0885	22.7219	9.3736
T7	220.00-200.00	26.9333	14.8331	34.9737	18.2835
T8	200.00-180.00	15.3584	18.2218	20.8177	21.8417
T9	180.00-170.00	17.5744	19.9875	23.9998	24.1236
T10	170.00-160.00	19.5707	21.3099	26.9587	25.8532
T11	160.00-140.00	20.4689	21.3261	28.6780	26.2438
T12	140.00-120.00	23.8729	23.3789	33.3841	28.8925
T13	120.00-100.00	34.1073	30.8927	44.7378	36.2306
T14	100.00-80.00	40.1488	34.6874	52.2964	40.6819
T15	80.00-60.00	41.1722	35.4519	54.6331	42.3668
T16	60.00-30.00	43.8332	37.7506	58.3746	45.3097
T17	30.00-0.00	41.4906	35.9230	56.6973	44.2658

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
			ft	ft	°	ft	ft ²	ft ²	lb
* CSP Antenna Inventory - via Eastern Communications									
Climb/Mapping									
PD688S-4 (ECI-66)	C	From Leg	0.50	0.0000	94.00	No Ice	0.35	0.35	3.75
			0.00			1/2" Ice	0.63	0.63	4.88
			0.00						
4'x4" Pipe Mount (ECI-66)	C	From Leg	0.00	0.0000	94.00	No Ice	1.32	1.32	44.00
			0.00			1/2" Ice	1.58	1.58	56.99
			0.00						
Pirol 4' Side Mount Standoff (1) (ECI-62)	B	From Leg	0.00	0.0000	106.00	No Ice	2.72	2.72	50.00
			0.00			1/2" Ice	4.91	4.91	89.00
			0.00						
PD458 (ECI-62)	B	From Leg	3.00	0.0000	106.00	No Ice	2.88	2.88	20.00
			0.00			1/2" Ice	4.34	4.34	46.22
			0.00						
5'3"x4" Pipe Mount (ECI-63 (Dish Support))	A	From Leg	0.00	0.0000	107.00	No Ice	1.88	1.88	57.00
			0.00			1/2" Ice	2.21	2.21	73.81
			0.00						
8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-63a (Dish Ice Shield))	A	From Leg	0.00	0.0000	115.00	No Ice	8.34	4.76	400.00
			0.00			1/2" Ice	11.01	6.71	756.25
			0.00						
3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0) (ECI-61a)	C	From Leg	0.00	0.0000	117.00	No Ice	8.34	4.76	400.00
			0.00			1/2" Ice	11.01	6.71	756.25
			0.00						
5'3"x4" Pipe Mount (ECI-61a (Dish Support))	C	From Leg	0.00	0.0000	112.00	No Ice	1.88	1.88	57.00
			0.00			1/2" Ice	2.21	2.21	73.81
			0.00						
DB212-1 (ECI-59)	C	From Leg	6.00	0.0000	139.00	No Ice	4.40	4.40	31.00
			0.00			1/2" Ice	8.42	8.42	70.21
			0.00						

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	16 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	lb	
4' Side Mount Standoff (ECI-60 & 59)	C	From Leg	0.00	0.00	0.0000	139.00	No Ice 1/2" Ice	6.50 8.50	6.50 8.50	100.00 170.00
PD156S (ECI-60)	C	From Leg	6.00	0.00	0.0000	139.00	No Ice 1/2" Ice	0.44 0.79	0.44 0.79	5.00 6.50
5'3"x4" Pipe Mount (ECI-58a (Dish Support))	C	From Leg	0.00	0.00	0.0000	154.00	No Ice 1/2" Ice	1.88 2.21	1.88 2.21	57.00 73.81
ANT450F6 (ECI-57)	A	From Leg	0.50	0.00	0.0000	153.00	No Ice 1/2" Ice	1.90 2.73	1.90 2.73	8.00 22.34
5'3"x4" Pipe Mount (ECI-57)	A	From Leg	0.00	0.00	0.0000	153.00	No Ice 1/2" Ice	1.88 2.21	1.88 2.21	57.00 73.81
L-810 Obstruction Lighting (1) (ECI-56)	A	From Leg	0.25	0.00	0.0000	164.00	No Ice 1/2" Ice	0.36 0.52	0.36 0.52	6.65 12.44
L-810 Obstruction Lighting (1) (ECI-54)	B	From Leg	0.25	0.00	0.0000	168.00	No Ice 1/2" Ice	0.36 0.52	0.36 0.52	6.65 12.44
L-810 Obstruction Lighting (1) (ECI-55)	C	From Leg	0.25	0.00	0.0000	165.00	No Ice 1/2" Ice	0.36 0.52	0.36 0.52	6.65 12.44
DB586-Y (inverted) (ECI-53)	B	From Leg	4.00	0.00	0.0000	175.00	No Ice 1/2" Ice	1.01 1.28	1.01 1.28	8.25 16.59
Pirod 4' Side Mount Standoff (1) (ECI-53,52,51)	B	From Leg	0.00	0.00	0.0000	176.00	No Ice 1/2" Ice	2.72 4.91	2.72 4.91	50.00 89.00
430-94C-09168-M-11048 TTA (ECI-52)	B	From Leg	2.00	0.00	0.0000	176.00	No Ice 1/2" Ice	1.63 1.81	0.95 1.09	30.00 37.44
DB586-Y (ECI-51)	B	From Leg	4.00	0.00	0.0000	177.00	No Ice 1/2" Ice	1.01 1.28	1.01 1.28	8.25 16.59
DB586-Y (ECI-50)	C	From Leg	3.00	0.00	0.0000	179.00	No Ice 1/2" Ice	1.01 1.28	1.01 1.28	8.25 16.59
Pirod 4' Side Mount Standoff (1) (ECI-50)	C	From Leg	0.00	0.00	0.0000	179.00	No Ice 1/2" Ice	2.72 4.91	2.72 4.91	50.00 89.00
531-70HD Exposed Dipole Antenna (ECI-15)	A	From Leg	6.00	0.00	0.0000	238.00	No Ice 1/2" Ice	5.91 7.68	5.91 7.68	50.00 79.03
6' Side Mount Standoff (ECI-15)	A	From Leg	0.00	0.00	0.0000	238.00	No Ice 1/2" Ice	6.50 8.50	6.50 8.50	100.00 170.00
PD1142-1 (ECI-14)	C	From Leg	6.00	0.00	0.0000	248.00	No Ice 1/2" Ice	1.32 3.21	1.32 3.21	10.00 23.85
6' Side Mount Standoff (ECI-14)	C	From Leg	0.00	0.00	0.0000	248.00	No Ice 1/2" Ice	6.50 8.50	6.50 8.50	100.00 170.00
SC479-HF1LDF(D00I-E6085) (Inverted) (ECI-13)	B	From Leg	3.00	0.00	0.0000	245.00	No Ice 1/2" Ice	5.06 6.54	5.06 6.54	34.00 69.82

Job	320' Rohn SSVMW	Page	17 of 41
Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft ²	ft ²	lb
SC479-HF1LDF(D001-E6085)	B	From Leg	3.00	0.0000	245.00	No Ice	5.06	5.06	34.00
) (Inverted)			0.00			1/2" Ice	6.54	6.54	69.82
(ECI-12)			0.00						
Sabre T-Boom (1)	B	From Leg	0.00	0.0000	246.00	No Ice	35.40	35.40	471.00
(ECI-10,11,12,13)			0.00			1/2" Ice	46.90	46.90	690.00
			0.00						
430-94C-09168-M-11048	B	From Leg	2.00	0.0000	247.00	No Ice	1.63	0.95	30.00
TTA			0.00			1/2" Ice	1.81	1.09	37.44
(ECI-11)			0.00						
SC479-HF1LDF	B	From Leg	3.00	0.0000	251.00	No Ice	5.06	5.06	34.00
(ECI-10)			0.00			1/2" Ice	6.54	6.54	69.82
			0.00						
6' Side Mount Standoff	B	From Leg	0.00	0.0000	260.00	No Ice	6.50	6.50	100.00
(ECI-8)			0.00			1/2" Ice	8.50	8.50	170.00
			0.00						
PD440-2	B	From Leg	6.00	0.0000	264.00	No Ice	1.38	1.38	19.00
(ECI-8)			0.00			1/2" Ice	2.48	2.48	24.70
			0.00						
SC479-HF1LDF(D001-E6085)	C	From Leg	6.00	0.0000	283.00	No Ice	5.06	5.06	34.00
) (Inverted)			0.00			1/2" Ice	6.54	6.54	69.82
(ECI-7)			0.00						
6' Side Mount Standoff	C	From Leg	0.00	0.0000	284.00	No Ice	6.50	6.50	100.00
(ECI-7)			0.00			1/2" Ice	8.50	8.50	170.00
			0.00						
DB809T3E-XC	C	From Leg	6.00	0.0000	286.00	No Ice	4.25	4.25	39.00
(ECI-6)			0.00			1/2" Ice	5.70	5.70	69.70
			0.00						
PD340-1	A	From Leg	6.00	0.0000	290.00	No Ice	3.30	3.30	40.00
(ECI-5)			0.00			1/2" Ice	5.94	5.94	52.00
			0.00						
6' Side Mount Standoff	A	From Leg	0.00	0.0000	290.00	No Ice	6.50	6.50	100.00
(ECI-5)			0.00			1/2" Ice	8.50	8.50	170.00
			0.00						
SC479-HF1LDF	C	From Leg	6.00	0.0000	300.00	No Ice	5.06	5.06	34.00
(ECI-4)			0.00			1/2" Ice	6.54	6.54	69.82
			0.00						
6' Side Mount Standoff	C	From Leg	0.00	0.0000	300.00	No Ice	6.50	6.50	100.00
(ECI-4)			0.00			1/2" Ice	8.50	8.50	170.00
			0.00						
ANT450F6	B	From Leg	5.00	0.0000	318.00	No Ice	1.90	1.90	8.00
(ECI-3)			0.00			1/2" Ice	2.73	2.73	22.34
			0.00						
4'x4" Pipe Mount	B	From Leg	0.00	0.0000	318.00	No Ice	1.32	1.32	44.00
(ECI-3)			0.00			1/2" Ice	1.58	1.58	56.99
			0.00						
BA1012-0	A	From Leg	6.00	0.0000	320.00	No Ice	0.47	0.47	2.20
(ECI-2)			0.00			1/2" Ice	0.96	0.96	6.61
			0.00						
6' Side Mount Standoff	A	From Leg	0.00	0.0000	320.00	No Ice	6.50	6.50	100.00
(ECI-2)			0.00			1/2" Ice	8.50	8.50	170.00
			0.00						
PD128-1	C	From Leg	6.00	0.0000	325.00	No Ice	1.00	1.00	13.00
(ECI-1)			0.00			1/2" Ice	1.80	1.80	16.90
			0.00						
6' Side Mount Standoff	C	From Leg	0.00	0.0000	325.00	No Ice	6.50	6.50	100.00
(ECI-1)			0.00			1/2" Ice	8.50	8.50	170.00
			0.00						

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	18 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
					°	ft	ft ²	ft ²	lb
Dual Lights (Beacon)	A	None			0.0000	327.00	No Ice 4.00 1/2" Ice 4.80	4.00 4.80	250.00 400.00
Lightning Rod 5/8x4' (Lightning Rod)	C	None			0.0000	329.00	No Ice 0.25 1/2" Ice 0.66	0.25 0.66	31.00 33.82
* VZW Proposed 12/07/2018									
Valmont VFA-10-U V-Frame (Verizon)	A	None			0.0000	232.00	No Ice 7.95 1/2" Ice 8.33	4.45 4.74	285.00 343.57
Valmont VFA-10-U V-Frame (Verizon)	B	None			0.0000	232.00	No Ice 7.95 1/2" Ice 8.33	4.45 4.74	285.00 343.57
Valmont VFA-10-U V-Frame (Verizon)	C	None			0.0000	232.00	No Ice 7.95 1/2" Ice 8.33	4.45 4.74	285.00 343.57
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	A	From Leg	5.00 6.00		0.0000	232.00	No Ice 9.66 1/2" Ice 10.22	5.98 6.44	126.30 184.38
JAHH-65B-R3B Panel Antenna (Verizon-PCS (Prev. Prop.))	A	From Leg	5.00 5.50		0.0000	232.00	No Ice 9.66 1/2" Ice 10.22	5.98 6.44	126.30 184.38
LNX-6512DS-VTM (Verizon-850)	A	From Leg	5.00 -3.00		0.0000	232.00	No Ice 5.61 1/2" Ice 6.01	3.30 3.66	30.00 63.32
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2)) (Verizon-PCS/AWS (Prev. Prop.))	A	From Leg	5.00 6.00		0.0000	232.00	No Ice 3.78 1/2" Ice 4.84	3.56 4.62	116.83 175.06
RFV01U-D1A RRH Unit (Verizon RRH (Prev. Prop.))	A	From Leg	5.00 0.00		0.0000	232.00	No Ice 2.19 1/2" Ice 2.39	1.46 1.62	97.50 115.84
RFV01U-D2A RRH Unit (Verizon RRH (Prev. Prop.))	A	From Leg	5.00 0.00		0.0000	232.00	No Ice 2.19 1/2" Ice 2.39	1.18 1.34	82.00 98.43
DB-B1-6C-12AB-0Z / DC-3315-PF-48 Dist. Box (Verizon)	A	From Leg	5.00 0.00		0.0000	232.00	No Ice 4.42 1/2" Ice 4.72	2.90 3.16	32.00 63.48
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	B	From Leg	5.00 6.00		0.0000	232.00	No Ice 9.66 1/2" Ice 10.22	5.98 6.44	126.30 184.38
JAHH-65B-R3B Panel Antenna (Verizon-PCS (Prev. Prop.))	B	From Leg	5.00 5.50		0.0000	232.00	No Ice 9.66 1/2" Ice 10.22	5.98 6.44	126.30 184.38
LNX-6512DS-VTM (Verizon-850)	B	From Leg	5.00 -3.00		0.0000	232.00	No Ice 5.61 1/2" Ice 6.01	3.30 3.66	30.00 63.32
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2)) (Verizon-PCS/AWS (Prev. Prop.))	B	From Leg	5.00 6.00		0.0000	232.00	No Ice 3.78 1/2" Ice 4.84	3.56 4.62	116.83 175.06
RFV01U-D1A RRH Unit (Verizon RRH (Prev. Prop.))	B	From Leg	5.00 0.00		0.0000	232.00	No Ice 2.19 1/2" Ice 2.39	1.46 1.62	97.50 115.84
DB-B1-6C-12AB-0Z / DC-3315-PF-48 Dist. Box (Verizon)	B	From Leg	5.00 0.00		0.0000	232.00	No Ice 4.42 1/2" Ice 4.72	2.90 3.16	32.00 63.48
JAHH-65B-R3B Panel Antenna (Verizon-AWS (Prev. Prop.))	C	From Leg	5.00 6.00		0.0000	232.00	No Ice 9.66 1/2" Ice 10.22	5.98 6.44	126.30 184.38
JAHH-65B-R3B Panel Antenna (Verizon-PCS (Prev. Prop.))	C	From Leg	5.00 5.50		0.0000	232.00	No Ice 9.66 1/2" Ice 10.22	5.98 6.44	126.30 184.38

Job	320' Rohn SSVMW	Page	19 of 41
Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			ft ft ft	°	ft	ft ²	ft ²	lb	
(Verizon-PCS (Prev. Prop.))			0.00						
LNx-6512DS-VTM	C	From Leg	5.00	0.0000	232.00	No Ice	5.61	3.30	30.00
(Verizon-850)			-3.00			1/2" Ice	6.01	3.66	63.32
			0.00						
BSAMNT-SBS-2-2 (JAHH Antenna Bracket (for 2))	C	From Leg	5.00	0.0000	232.00	No Ice	3.78	3.56	116.83
(Verizon-PCS/AWS (Prev. Prop.))			6.00			1/2" Ice	4.84	4.62	175.06
			0.00						
RFV01U-D1A RRH Unit	C	From Leg	5.00	0.0000	232.00	No Ice	2.19	1.46	97.50
(Verizon RRH (Prev. Prop.))			0.00			1/2" Ice	2.39	1.62	115.84
			0.00						
RFV01U-D2A RRH Unit	C	From Leg	5.00	0.0000	232.00	No Ice	2.19	1.18	82.00
(Verizon RRH (Prev. Prop.))			0.00			1/2" Ice	2.39	1.34	98.43
			0.00						
CBC78T-DS-43-2X Diplexer	A	From Leg	5.00	0.0000	232.00	No Ice	0.43	0.60	22.00
(Verizon (Prev. Prop.))			0.00			1/2" Ice	0.52	0.71	28.34
			0.00						
CBC78T-DS-43-2X Diplexer	B	From Leg	5.00	0.0000	232.00	No Ice	0.43	0.60	22.00
(Verizon (Prev. Prop.))			0.00			1/2" Ice	0.52	0.71	28.34
			0.00						
CBC78T-DS-43-2X Diplexer	C	From Leg	5.00	0.0000	232.00	No Ice	0.43	0.60	22.00
(Verizon (Prev. Prop.))			0.00			1/2" Ice	0.52	0.71	28.34
			0.00						
* VZW Proposed 12/07/2018									
*** EMP-005 AT&T									
Inventory 08/2019 Updates									
PiROD 12' Lightweight T-Frame (AT&T)	A	None		0.0000	200.00	No Ice	10.20	10.20	253.00
						1/2" Ice	16.20	16.20	355.00
PiROD 12' Lightweight T-Frame (AT&T)	B	None		0.0000	200.00	No Ice	10.20	10.20	253.00
						1/2" Ice	16.20	16.20	355.00
PiROD 12' Lightweight T-Frame (AT&T)	C	None		0.0000	200.00	No Ice	10.20	10.20	253.00
						1/2" Ice	16.20	16.20	355.00
7770.00 (AT&T)	A	From Leg	3.00	0.0000	200.00	No Ice	10.03	5.60	20.00
			-6.00			1/2" Ice	10.61	6.15	70.47
			0.00						
HPA-65R-BUU-H8 Panel (AT&T (Prev. Proposed))	A	From Leg	3.00	0.0000	200.00	No Ice	12.99	7.48	68.00
			6.00			1/2" Ice	13.69	8.06	140.41
			0.00						
RRUS-32 (AT&T (Prev. Proposed))	A	From Leg	3.00	0.0000	200.00	No Ice	3.20	1.85	60.00
			6.00			1/2" Ice	3.46	2.08	81.11
			1.50						
RRUS-11 (AT&T (Prev. Proposed))	A	From Leg	3.00	0.0000	200.00	No Ice	2.99	1.25	50.00
			6.00			1/2" Ice	3.23	1.41	69.57
			-1.50						
7770.00 (AT&T)	B	From Leg	3.00	0.0000	200.00	No Ice	10.03	5.60	20.00
			-6.00			1/2" Ice	10.61	6.15	70.47
			0.00						
HPA-65R-BUU-H8 Panel (AT&T (Prev. Proposed))	B	From Leg	3.00	0.0000	200.00	No Ice	12.99	7.48	68.00
			6.00			1/2" Ice	13.69	8.06	140.41
			0.00						
RRUS-32 (AT&T (Prev. Proposed))	B	From Leg	3.00	0.0000	200.00	No Ice	3.20	1.85	60.00
			6.00			1/2" Ice	3.46	2.08	81.11
			1.50						
RRUS-11	B	From Leg	3.00	0.0000	200.00	No Ice	2.99	1.25	50.00

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	20 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _{AA} Front ft ²	C _{AA} Side ft ²	Weight lb
(AT&T (Prev. Proposed))			6.00 -1.50		1/2" Ice	3.23	1.41	69.57
7770.00 (AT&T)	C	From Leg	3.00 -6.00 0.00	0.0000	200.00	No Ice 1/2" Ice	10.03 10.61	20.00 70.47
HPA-65R-BUU-H6 Panel (AT&T (Prev. Proposed))	C	From Leg	3.00 6.00 0.00	0.0000	200.00	No Ice 1/2" Ice	10.12 10.69	48.00 105.33
RRUS-32 (AT&T (Prev. Proposed))	B	From Leg	3.00 6.00 1.50	0.0000	200.00	No Ice 1/2" Ice	3.20 3.46	1.85 2.08 60.00 81.11
RRUS-11 (AT&T (Prev. Proposed))	B	From Leg	3.00 6.00 -1.50	0.0000	200.00	No Ice 1/2" Ice	2.99 3.23	1.25 1.41 50.00 69.57
DC6-48-60-0-8C Squid / Surge Arrestor (AT&T (Prev. Proposed))	C	None		0.0000	200.00	No Ice 1/2" Ice	1.79 2.02	1.79 2.02 27.00 47.39
STK-U Stiffener Side Arm Attachment (AT&T)	A	None		0.0000	200.00	No Ice 1/2" Ice	0.07 0.11	4.01 5.00 63.79 95.84
STK-U Stiffener Side Arm Attachment (AT&T)	B	None		0.0000	200.00	No Ice 1/2" Ice	0.07 0.11	4.01 5.00 63.79 95.84
STK-U Stiffener Side Arm Attachment (AT&T)	C	None		0.0000	200.00	No Ice 1/2" Ice	0.07 0.11	4.01 5.00 63.79 95.84
STK-U Stiffener Side Arm Attachment (AT&T)	A	None		0.0000	200.00	No Ice 1/2" Ice	0.07 0.11	4.01 5.00 63.79 95.84
STK-U Stiffener Side Arm Attachment (AT&T)	B	None		0.0000	200.00	No Ice 1/2" Ice	0.07 0.11	4.01 5.00 63.79 95.84
STK-U Stiffener Side Arm Attachment (AT&T)	C	None		0.0000	200.00	No Ice 1/2" Ice	0.07 0.11	4.01 5.00 63.79 95.84
*** EMP-005 AT&T Inventory 08/2019 Updates *EVS-010 Proposed Inventory								
Telewave ANT220F2 - Omni Antenna (Eversource (Proposed #1))	C	From Leg	4.00 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	1.03 1.29	1.03 1.29 14.00 22.80
Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed) (Eversource (Proposed #1))	C	From Leg	0.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice	2.48 3.25	5.14 6.91 165.00 318.00
Telewave ANT220F2 - Omni Antenna (Eversource (Proposed #2))	C	From Leg	4.00 0.00 0.00	0.0000	145.00	No Ice 1/2" Ice	1.03 1.29	1.03 1.29 14.00 22.80
Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed) (Eversource (Proposed #1))	C	From Leg	0.00 0.00 0.00	0.0000	142.00	No Ice 1/2" Ice	2.48 3.25	5.14 6.91 165.00 318.00

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	21 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				ft	°	°	ft	ft	ft ²	lb	
* CSP Inventory from HighTower Solutions											
Climb											
PA8-65 (ECI-63)	A	Paraboloid w/Shroud (HP)	From Leg	0.50 0.00 0.00	Worst		107.00	8.00	No Ice 1/2" Ice	50.27 51.29	285.00 548.30
Andrew 2' w/Radome (ECI-61)	C	Paraboloid w/Radome	From Leg	0.50 0.00 0.00	Worst		112.00	2.00	No Ice 1/2" Ice	3.14 3.41	70.00 282.00
* CSP Proposed											
Commscope PAR6-59W-PXA/A (ECI-58)	C	Paraboloid w/Radome	From Leg	0.50 0.00 0.00	Worst		154.00	6.00	No Ice 1/2" Ice	28.27 29.07	310.00 460.00

Tower Pressures - No Ice

$$G_H = 1.084$$

Section Elevation	z	Kz	qz	AG	F a c e	AF	AR	Aleg	Leg %	CAAA In Face	CAAA Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T1 320.00-304.00	312.00	1.9	39	116.377	A	9.512	14.835	14.835	60.93	0.000	0.000
					B	9.078	14.835		62.04	5.561	0.000
					C	9.512	14.835		60.93	0.000	0.000
T2 304.00-300.00	302.00	1.882	39	29.094	A	2.147	3.709	3.709	63.34	0.000	0.000
					B	2.038	3.709		64.53	1.540	0.000
					C	2.147	3.709		63.34	0.000	0.000
T3 300.00-280.00	290.00	1.861	39	167.656	A	12.596	22.122	22.122	63.72	0.000	0.000
					B	11.540	22.122		65.72	14.473	0.000
					C	12.596	22.122		63.72	0.000	0.000
T4 280.00-260.00	270.00	1.823	38	216.829	A	51.464	0.000	37.788	73.43	0.000	0.000
					B	49.540	0.000		76.28	30.636	0.000
					C	51.464	0.000		73.43	0.000	0.000
T5 260.00-240.00	250.00	1.783	37	259.126	A	56.868	0.000	37.778	66.43	0.000	0.000
					B	53.929	0.000		70.05	41.134	0.000
					C	56.868	0.000		66.43	0.000	0.000
T6 240.00-220.00	230.00	1.741	36	299.625	A	66.901	0.000	37.776	56.46	0.000	0.000
					B	61.984	0.000		60.94	53.315	0.000
					C	66.901	0.000		56.46	0.000	0.000
T7 220.00-200.00	210.00	1.697	35	339.725	A	61.588	0.000	37.775	61.34	0.000	0.000
					B	58.064	0.000		65.06	53.860	0.000
					C	59.614	0.000		63.37	30.160	0.000
T8 200.00-180.00	190.00	1.649	34	385.076	A	69.940	0.000	45.633	65.25	30.040	0.000
					B	68.429	0.000		66.69	53.860	0.000
					C	69.932	0.000		65.25	30.160	0.000
T9 180.00-170.00	175.00	1.611	33	208.387	A	35.928	0.000	22.815	63.50	15.020	0.000
					B	35.056	0.000		65.08	29.035	0.000
					C	35.925	0.000		63.51	15.080	0.000
T10 170.00-160.00	165.00	1.584	33	218.787	A	36.566	0.000	22.815	62.39	15.020	0.000
					B	35.557	0.273		63.68	31.062	0.000
					C	36.563	0.000		62.40	15.080	0.000

Job	320' Rohn SSMW	Page	22 of 41
Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation ft	z ft	K _Z	q _z psf	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _{AA} In Face ft ²	C _{AA} Out Face ft ²
T11 160.00-140.00	150.00	1.541	32	467.070	A	82.274	0.000	45.617	55.44	30.040	0.000
					B	80.101	2.271		55.38	64.237	0.000
					C	82.265	0.000		55.45	30.160	0.000
T12 140.00-120.00	130.00	1.48	31	507.978	A	85.482	0.000	45.637	53.39	30.040	0.000
					B	84.826	3.633		51.59	68.379	0.000
					C	85.473	0.000		53.39	30.160	0.000
T13 120.00-100.00	110.00	1.411	29	555.591	A	45.673	25.238	45.673	64.41	30.040	0.000
					B	50.188	26.044		59.91	72.445	0.000
					C	45.673	25.232		64.41	30.160	0.000
T14 100.00-80.00	90.00	1.332	28	606.388	A	45.666	26.897	45.666	62.93	30.040	0.000
					B	52.620	27.352		57.10	78.189	0.000
					C	45.666	26.890		62.94	30.160	0.000
T15 80.00-60.00	70.00	1.24	26	662.098	A	53.708	28.975	53.708	64.96	30.040	0.000
					B	60.663	29.334		59.68	80.260	0.000
					C	53.708	28.969		64.96	30.160	0.000
T16 60.00-30.00	45.00	1.093	23	1088.08	A	80.523	49.865	80.523	61.76	45.060	0.000
				3	B	90.955	49.781		57.22	120.390	0.000
					C	80.523	49.854		61.76	45.240	0.000
T17 30.00-0.00	15.00	1	21	1202.12	A	81.480	56.889	81.480	58.89	37.550	0.000
				2	B	90.173	56.677		55.48	100.325	0.000
					C	81.480	56.880		58.89	37.700	0.000

Tower Pressure - With Ice

$G_H = 1.084$

Section Elevation ft	z ft	K _Z	q _z psf	t _z in	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _{AA} In Face ft ²	C _{AA} Out Face ft ²
T1 320.00-304.00	312.00	1.9	39	0.5000	117.711	A	9.512	22.937	17.501	53.93	0.000	0.000
						B	8.622	22.428		56.37	11.411	0.000
						C	9.512	22.937		53.93	0.000	0.000
T2 304.00-300.00	302.00	1.882	39	0.5000	29.428	A	2.147	5.602	4.375	56.46	0.000	0.000
						B	1.925	5.476		59.12	3.140	0.000
						C	2.147	5.602		56.46	0.000	0.000
T3 300.00-280.00	290.00	1.861	39	0.5000	169.325	A	12.596	31.759	25.461	57.40	0.000	0.000
						B	10.576	30.749		61.61	27.673	0.000
						C	12.596	31.759		57.40	0.000	0.000
T4 280.00-260.00	270.00	1.823	38	0.5000	218.499	A	53.691	5.471	40.014	67.64	0.000	0.000
						B	50.241	4.091		73.65	54.936	0.000
						C	53.691	5.471		67.64	0.000	0.000
T5 260.00-240.00	250.00	1.783	37	0.5000	260.795	A	59.094	6.363	40.004	61.11	0.000	0.000
						B	53.939	4.645		68.28	72.134	0.000
						C	59.094	6.363		61.11	0.000	0.000
T6 240.00-220.00	230.00	1.741	36	0.5000	301.294	A	69.127	7.281	40.002	52.35	0.000	0.000
						B	60.567	5.141		60.88	92.815	0.000
						C	69.127	7.281		52.35	0.000	0.000
T7 220.00-200.00	210.00	1.697	35	0.5000	341.394	A	63.814	5.953	40.001	57.34	0.000	0.000
						B	57.672	4.418		64.42	93.860	0.000
						C	60.793	5.198		60.62	46.160	0.000
T8 200.00-180.00	190.00	1.649	34	0.5000	386.745	A	71.078	5.805	47.860	62.25	48.747	0.000
						B	68.118	5.064		65.40	93.860	0.000
						C	71.144	5.821		62.18	46.160	0.000
T9 180.00-170.00	175.00	1.611	33	0.5000	209.222	A	36.507	3.145	23.928	60.34	24.373	0.000
						B	34.792	2.716		63.79	51.135	0.000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSMW	Page 23 of 41
	Project CSP Tower - Colchester, CT	Date 11:26:38 05/18/20
	Client DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by MCD

Section Elevation ft	z ft	K _Z	q _z psf	t _z in	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
T10 170.00-160.00	165.00	1.584	33	0.5000	219.622	C	36.540	3.153	23.928	60.28	23.080	0.000
						A	37.151	3.306		59.14	24.373	0.000
						B	35.148	3.327		62.19	55.462	0.000
T11 160.00-140.00	150.00	1.541	32	0.5000	468.739	C	37.183	3.314	47.842	59.09	23.080	0.000
						A	83.193	7.070		53.00	48.747	0.000
						B	78.508	10.301		53.87	115.537	0.000
T12 140.00-120.00	130.00	1.48	31	0.5000	509.647	C	83.273	7.086	47.864	52.95	46.160	0.000
						A	86.420	7.711		50.85	48.747	0.000
						B	83.725	13.392		49.28	123.479	0.000
T13 120.00-100.00	110.00	1.411	29	0.5000	557.261	C	86.498	7.727	47.902	50.80	46.160	0.000
						A	47.902	32.034		59.93	48.747	0.000
						B	54.583	31.531		55.63	131.275	0.000
T14 100.00-80.00	90.00	1.332	28	0.5000	608.058	C	47.902	32.114	47.894	59.87	46.160	0.000
						A	47.894	34.297		58.27	48.747	0.000
						B	58.182	32.937		52.56	142.289	0.000
T15 80.00-60.00	70.00	1.24	26	0.5000	663.769	C	47.894	34.373	55.937	58.22	46.160	0.000
						A	55.937	36.906		60.25	48.747	0.000
						B	66.225	35.364		55.06	146.260	0.000
T16 60.00-30.00	45.00	1.093	23	0.5000	1090.588	C	55.937	36.981	83.865	60.20	46.160	0.000
						A	83.865	61.800		57.57	73.120	0.000
						B	99.296	58.044		53.30	219.390	0.000
T17 30.00-0.00	15.00	1	21	0.5000	1204.627	C	83.865	61.926	84.823	57.52	69.240	0.000
						A	84.823	70.341		54.67	60.933	0.000
						B	97.682	67.067		51.49	182.825	0.000
						C	84.823	70.447		54.63	57.700	0.000

Tower Pressure - Service

$G_H = 1.084$

Section Elevation ft	z ft	K _Z	q _z psf	A _G ft ²	F a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _A A _A In Face ft ²	C _A A _A Out Face ft ²
T1 320.00-304.00	312.00	1.9	39	116.377	A	9.512	14.835	14.835	60.93	0.000	0.000
					B	9.078	14.835		62.04	5.561	0.000
					C	9.512	14.835		60.93	0.000	0.000
T2 304.00-300.00	302.00	1.882	39	29.094	A	2.147	3.709	3.709	63.34	0.000	0.000
					B	2.038	3.709		64.53	1.540	0.000
					C	2.147	3.709		63.34	0.000	0.000
T3 300.00-280.00	290.00	1.861	39	167.656	A	12.596	22.122	22.122	63.72	0.000	0.000
					B	11.540	22.122		65.72	14.473	0.000
					C	12.596	22.122		63.72	0.000	0.000
T4 280.00-260.00	270.00	1.823	38	216.829	A	51.464	0.000	37.788	73.43	0.000	0.000
					B	49.540	0.000		76.28	30.636	0.000
					C	51.464	0.000		73.43	0.000	0.000
T5 260.00-240.00	250.00	1.783	37	259.126	A	56.868	0.000	37.778	66.43	0.000	0.000
					B	53.929	0.000		70.05	41.134	0.000
					C	56.868	0.000		66.43	0.000	0.000
T6 240.00-220.00	230.00	1.741	36	299.625	A	66.901	0.000	37.776	56.46	0.000	0.000
					B	61.984	0.000		60.94	53.315	0.000
					C	66.901	0.000		56.46	0.000	0.000
T7 220.00-200.00	210.00	1.697	35	339.725	A	61.588	0.000	37.775	61.34	0.000	0.000
					B	58.064	0.000		65.06	53.860	0.000
					C	59.614	0.000		63.37	30.160	0.000

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job 320' Rohn SSVMW	Page 24 of 41
	Project CSP Tower - Colchester, CT	Date 11:26:38 05/18/20
	Client DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by MCD

Section Elevation ft	z ft	K _Z	q _z psf	A _G ft ²	F _a c e	A _F ft ²	A _R ft ²	A _{leg} ft ²	Leg %	C _{AA} In Face ft ²	C _{AA} Out Face ft ²
T8 200.00-180.00	190.00	1.649	34	385.076	A	69.940	0.000	45.633	65.25	30.040	0.000
					B	68.429	0.000		66.69	53.860	0.000
					C	69.932	0.000		65.25	30.160	0.000
T9 180.00-170.00	175.00	1.611	33	208.387	A	35.928	0.000	22.815	63.50	15.020	0.000
					B	35.056	0.000		65.08	29.035	0.000
					C	35.925	0.000		63.51	15.080	0.000
T10 170.00-160.00	165.00	1.584	33	218.787	A	36.566	0.000	22.815	62.39	15.020	0.000
					B	35.557	0.273		63.68	31.062	0.000
					C	36.563	0.000		62.40	15.080	0.000
T11 160.00-140.00	150.00	1.541	32	467.070	A	82.274	0.000	45.617	55.44	30.040	0.000
					B	80.101	2.271		55.38	64.237	0.000
					C	82.265	0.000		55.45	30.160	0.000
T12 140.00-120.00	130.00	1.48	31	507.978	A	85.482	0.000	45.637	53.39	30.040	0.000
					B	84.826	3.633		51.59	68.379	0.000
					C	85.473	0.000		53.39	30.160	0.000
T13 120.00-100.00	110.00	1.411	29	555.591	A	45.673	25.238	45.673	64.41	30.040	0.000
					B	50.188	26.044		59.91	72.445	0.000
					C	45.673	25.232		64.41	30.160	0.000
T14 100.00-80.00	90.00	1.332	28	606.388	A	45.666	26.897	45.666	62.93	30.040	0.000
					B	52.620	27.352		57.10	78.189	0.000
					C	45.666	26.890		62.94	30.160	0.000
T15 80.00-60.00	70.00	1.24	26	662.098	A	53.708	28.975	53.708	64.96	30.040	0.000
					B	60.663	29.334		59.68	80.260	0.000
					C	53.708	28.969		64.96	30.160	0.000
T16 60.00-30.00	45.00	1.093	23	1088.08	A	80.523	49.865	80.523	61.76	45.060	0.000
				3	B	90.955	49.781		57.22	120.390	0.000
					C	80.523	49.854		61.76	45.240	0.000
T17 30.00-0.00	15.00	1	21	1202.12	A	81.480	56.889	81.480	58.89	37.550	0.000
				2	B	90.173	56.677		55.48	100.325	0.000
					C	81.480	56.880		58.89	37.700	0.000

Tower Forces - No Ice - Wind Normal To Face

Section Elevation ft	Add Weight lb	Self Weight lb	F _a c e	e	C _F	R _R	D _F	D _R	A _E ft ²	F lb	w plf	Ctrl. Face
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	0.592	1	1	18.299	2241.92	140.12	C
			B	0.205	2.578	0.592	1	1	17.854			
			C	0.209	2.566	0.592	1	1	18.299			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	0.591	1	1	4.337	540.67	135.17	C
			B	0.198	2.604	0.59	1	1	4.226			
			C	0.201	2.592	0.591	1	1	4.337			
T3 300.00-280.00	43.60	2496.34	A	0.207	2.573	0.592	1	1	25.689	3368.49	168.42	C
			B	0.201	2.593	0.591	1	1	24.604			
			C	0.207	2.573	0.592	1	1	25.689			
T4 280.00-260.00	101.88	5067.66	A	0.237	2.476	0.599	1	1	51.464	6475.59	323.78	C
			B	0.228	2.504	0.597	1	1	49.540			
			C	0.237	2.476	0.599	1	1	51.464			
T5 260.00-240.00	137.02	5409.17	A	0.219	2.532	0.595	1	1	56.868	7420.02	371.00	C
			B	0.208	2.569	0.592	1	1	53.929			
			C	0.219	2.532	0.595	1	1	56.868			
T6 240.00-220.00	176.60	6484.36	A	0.223	2.52	0.595	1	1	66.901	8684.36	434.22	C
			B	0.207	2.573	0.592	1	1	61.984			
			C	0.223	2.52	0.595	1	1	66.901			
T7 220.00-200.00	376.80	6406.00	A	0.181	2.66	0.587	1	1	61.588	9449.61	472.48	A
			B	0.171	2.696	0.585	1	1	58.064			

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	25 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T8 200.00-180.00	548.60	7298.65	C	0.175	2.68	0.586	1	1	59.614	11116.49	555.82	A
			A	0.182	2.659	0.587	1	1	69.940			
			B	0.178	2.672	0.586	1	1	68.429			
T9 180.00-170.00	279.66	3730.84	C	0.182	2.659	0.587	1	1	69.932	5639.47	563.95	A
			A	0.172	2.691	0.585	1	1	35.928			
			B	0.168	2.706	0.584	1	1	35.056			
T10 170.00-160.00	286.19	3785.29	C	0.172	2.691	0.585	1	1	35.925	5703.06	570.31	A
			A	0.167	2.709	0.584	1	1	36.566			
			B	0.164	2.721	0.584	1	1	35.716			
T11 160.00-140.00	587.84	9608.59	C	0.167	2.71	0.584	1	1	36.563	11939.98	597.00	A
			A	0.176	2.678	0.586	1	1	82.274			
			B	0.176	2.677	0.586	1	1	81.431			
T12 140.00-120.00	611.08	9975.29	C	0.176	2.678	0.586	1	1	82.265	12036.27	601.81	B
			A	0.168	2.705	0.584	1	1	85.482			
			B	0.174	2.685	0.585	1	1	86.953			
T13 120.00-100.00	629.25	9144.95	C	0.168	2.705	0.584	1	1	85.473	10038.38	501.92	B
			A	0.128	2.856	0.578	1	1	60.269			
			B	0.137	2.819	0.58	1	1	65.283			
T14 100.00-80.00	653.88	9675.54	C	0.128	2.856	0.578	1	1	60.265	9959.77	497.99	B
			A	0.12	2.886	0.577	1	1	61.193			
			B	0.132	2.839	0.579	1	1	68.454			
T15 80.00-60.00	659.20	11450.50	C	0.12	2.886	0.577	1	1	61.189	10022.40	501.12	B
			A	0.125	2.866	0.578	1	1	70.455			
			B	0.136	2.824	0.579	1	1	77.660			
T16 60.00-30.00	988.80	15115.36	C	0.125	2.866	0.578	1	1	70.451	13550.63	451.69	B
			A	0.12	2.886	0.577	1	1	109.311			
			B	0.129	2.849	0.579	1	1	119.755			
T17 30.00-0.00	824.00	17941.94	C	0.12	2.886	0.577	1	1	109.305	11890.73	396.36	B
			A	0.115	2.904	0.577	1	1	114.291			
			B	0.122	2.877	0.578	1	1	122.911			
Sum Weight:	6924.66	125382.28	C	0.115	2.904	0.577	1	114.286	20310.92 kip-ft	140077.83		

Tower Forces - No Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	0.592	0.825	1	16.635	2059.57	128.72	C
			B	0.205	2.578	0.592	0.825	1	16.265			
			C	0.209	2.566	0.592	0.825	1	16.635			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	0.591	0.825	1	3.962	499.48	124.87	C
			B	0.198	2.604	0.59	0.825	1	3.869			
			C	0.201	2.592	0.591	0.825	1	3.962			
T3 300.00-280.00	43.60	2496.34	A	0.207	2.573	0.592	0.825	1	23.485	3131.38	156.57	C
			B	0.201	2.593	0.591	0.825	1	22.584			
			C	0.207	2.573	0.592	0.825	1	23.485			
T4 280.00-260.00	101.88	5067.66	A	0.237	2.476	0.599	0.825	1	42.458	5562.01	278.10	C
			B	0.228	2.504	0.597	0.825	1	40.871			
			C	0.237	2.476	0.599	0.825	1	42.458			
T5 260.00-240.00	137.02	5409.17	A	0.219	2.532	0.595	0.825	1	46.916	6410.02	320.50	C
			B	0.208	2.569	0.592	0.825	1	44.491			
			C	0.219	2.532	0.595	0.825	1	46.916			
T6	176.60	6484.36	A	0.223	2.52	0.595	0.825	1	55.194	7529.72	376.49	C

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	26 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
240.00-220.00			B	0.207	2.573	0.592	0.825	1	51.137			
			C	0.223	2.52	0.595	0.825	1	55.194			
T7	376.80	6406.00	A	0.181	2.66	0.587	0.825	1	50.810	8356.58	417.83	A
220.00-200.00			B	0.171	2.696	0.585	0.825	1	47.903			
			C	0.175	2.68	0.586	0.825	1	49.182			
T8	548.60	7298.65	A	0.182	2.659	0.587	0.825	1	57.701	9910.75	495.54	A
200.00-180.00			B	0.178	2.672	0.586	0.825	1	56.454			
			C	0.182	2.659	0.587	0.825	1	57.694			
T9	279.66	3730.84	A	0.172	2.691	0.585	0.825	1	29.641	5027.13	502.71	A
180.00-170.00			B	0.168	2.706	0.584	0.825	1	28.921			
			C	0.172	2.691	0.585	0.825	1	29.638			
T10	286.19	3785.29	A	0.167	2.709	0.584	0.825	1	30.167	5085.97	508.60	A
170.00-160.00			B	0.164	2.721	0.584	0.825	1	29.494			
			C	0.167	2.71	0.584	0.825	1	30.164			
T11	587.84	9608.59	A	0.176	2.678	0.586	0.825	1	67.876	10604.71	530.24	A
160.00-140.00			B	0.176	2.677	0.586	0.825	1	67.413			
			C	0.176	2.678	0.586	0.825	1	67.869			
T12	611.08	9975.29	A	0.168	2.705	0.584	0.825	1	70.523	10711.27	535.56	B
140.00-120.00			B	0.174	2.685	0.585	0.825	1	72.109			
			C	0.168	2.705	0.584	0.825	1	70.515			
T13	629.25	9144.95	A	0.128	2.856	0.578	0.825	1	52.276	9253.52	462.68	B
120.00-100.00			B	0.137	2.819	0.58	0.825	1	56.500			
			C	0.128	2.856	0.578	0.825	1	52.272			
T14	653.88	9675.54	A	0.12	2.886	0.577	0.825	1	53.202	9177.18	458.86	B
100.00-80.00			B	0.132	2.839	0.579	0.825	1	59.245			
			C	0.12	2.886	0.577	0.825	1	53.198			
T15	659.20	11450.50	A	0.125	2.866	0.578	0.825	1	61.056	9187.25	459.36	B
80.00-60.00			B	0.136	2.824	0.579	0.825	1	67.044			
			C	0.125	2.866	0.578	0.825	1	61.052			
T16	988.80	15115.36	A	0.12	2.886	0.577	0.825	1	95.220	12437.16	414.57	B
60.00-30.00			B	0.129	2.849	0.579	0.825	1	103.837			
			C	0.12	2.886	0.577	0.825	1	95.213			
T17	824.00	17941.94	A	0.115	2.904	0.577	0.825	1	100.032	10870.66	362.36	B
30.00-0.00			B	0.122	2.877	0.578	0.825	1	107.130			
			C	0.115	2.904	0.577	0.825	1	100.027			
Sum Weight:	6924.66	125382.28						OTM	18087.31 kip-ft	125814.35		

Tower Forces - No Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1	15.90	1442.07	A	0.209	2.566	0.592	0.8	1	16.397	2033.52	127.10	C
320.00-304.00			B	0.205	2.578	0.592	0.8	1	16.038			
			C	0.209	2.566	0.592	0.8	1	16.397			
T2	4.36	349.72	A	0.201	2.592	0.591	0.8	1	3.908	493.60	123.40	C
304.00-300.00			B	0.198	2.604	0.59	0.8	1	3.818			
			C	0.201	2.592	0.591	0.8	1	3.908			
T3	43.60	2496.34	A	0.207	2.573	0.592	0.8	1	23.170	3097.50	154.88	C
300.00-280.00			B	0.201	2.593	0.591	0.8	1	22.296			
			C	0.207	2.573	0.592	0.8	1	23.170			
T4	101.88	5067.66	A	0.237	2.476	0.599	0.8	1	41.171	5431.49	271.57	C
280.00-260.00			B	0.228	2.504	0.597	0.8	1	39.632			
			C	0.237	2.476	0.599	0.8	1	41.171			

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	27 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T5 260.00-240.00	137.02	5409.17	A	0.219	2.532	0.595	0.8	1	45.494	6265.73	313.29	C
			B	0.208	2.569	0.592	0.8	1	43.143			
			C	0.219	2.532	0.595	0.8	1	45.494			
T6 240.00-220.00	176.60	6484.36	A	0.223	2.52	0.595	0.8	1	53.521	7364.78	368.24	C
			B	0.207	2.573	0.592	0.8	1	49.587			
			C	0.223	2.52	0.595	0.8	1	53.521			
T7 220.00-200.00	376.80	6406.00	A	0.181	2.66	0.587	0.8	1	49.270	8200.43	410.02	A
			B	0.171	2.696	0.585	0.8	1	46.451			
			C	0.175	2.68	0.586	0.8	1	47.692			
T8 200.00-180.00	548.60	7298.65	A	0.182	2.659	0.587	0.8	1	55.952	9738.50	486.92	A
			B	0.178	2.672	0.586	0.8	1	54.743			
			C	0.182	2.659	0.587	0.8	1	55.946			
T9 180.00-170.00	279.66	3730.84	A	0.172	2.691	0.585	0.8	1	28.743	4939.65	493.97	A
			B	0.168	2.706	0.584	0.8	1	28.044			
			C	0.172	2.691	0.585	0.8	1	28.740			
T10 170.00-160.00	286.19	3785.29	A	0.167	2.709	0.584	0.8	1	29.253	4997.82	499.78	A
			B	0.164	2.721	0.584	0.8	1	28.605			
			C	0.167	2.71	0.584	0.8	1	29.250			
T11 160.00-140.00	587.84	9608.59	A	0.176	2.678	0.586	0.8	1	65.820	10413.96	520.70	A
			B	0.176	2.677	0.586	0.8	1	65.411			
			C	0.176	2.678	0.586	0.8	1	65.812			
T12 140.00-120.00	611.08	9975.29	A	0.168	2.705	0.584	0.8	1	68.385	10521.98	526.10	B
			B	0.174	2.685	0.585	0.8	1	69.988			
			C	0.168	2.705	0.584	0.8	1	68.378			
T13 120.00-100.00	629.25	9144.95	A	0.128	2.856	0.578	0.8	1	51.134	9141.40	457.07	B
			B	0.137	2.819	0.58	0.8	1	55.246			
			C	0.128	2.856	0.578	0.8	1	51.130			
T14 100.00-80.00	653.88	9675.54	A	0.12	2.886	0.577	0.8	1	52.060	9065.38	453.27	B
			B	0.132	2.839	0.579	0.8	1	57.930			
			C	0.12	2.886	0.577	0.8	1	52.056			
T15 80.00-60.00	659.20	11450.50	A	0.125	2.866	0.578	0.8	1	59.713	9067.94	453.40	B
			B	0.136	2.824	0.579	0.8	1	65.527			
			C	0.125	2.866	0.578	0.8	1	59.709			
T16 60.00-30.00	988.80	15115.36	A	0.12	2.886	0.577	0.8	1	93.207	12278.10	409.27	B
			B	0.129	2.849	0.579	0.8	1	101.564			
			C	0.12	2.886	0.577	0.8	1	93.200			
T17 30.00-0.00	824.00	17941.94	A	0.115	2.904	0.577	0.8	1	97.995	10724.93	357.50	B
			B	0.122	2.877	0.578	0.8	1	104.876			
			C	0.115	2.904	0.577	0.8	1	97.990			
Sum Weight:	6924.66	125382.28						OTM	17769.65 kip-ft	123776.72		

Tower Forces - No Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	0.592	0.85	1	16.872	2085.62	130.35	C
			B	0.205	2.578	0.592	0.85	1	16.492			
			C	0.209	2.566	0.592	0.85	1	16.872			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	0.591	0.85	1	4.015	505.36	126.34	C
			B	0.198	2.604	0.59	0.85	1	3.920			
			C	0.201	2.592	0.591	0.85	1	4.015			
T3 300.00-280.00	43.60	2496.34	A	0.207	2.573	0.592	0.85	1	23.800	3165.25	158.26	C
			B	0.201	2.593	0.591	0.85	1	22.873			

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	28 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T4 280.00-260.00	101.88	5067.66	C	0.207	2.573	0.592	0.85	1	23.800			
			A	0.237	2.476	0.599	0.85	1	43.745	5692.52	284.63	C
			B	0.228	2.504	0.597	0.85	1	42.109			
T5 260.00-240.00	137.02	5409.17	C	0.237	2.476	0.599	0.85	1	43.745			
			A	0.219	2.532	0.595	0.85	1	48.338	6554.30	327.72	C
			B	0.208	2.569	0.592	0.85	1	45.839			
T6 240.00-220.00	176.60	6484.36	C	0.219	2.532	0.595	0.85	1	48.338			
			A	0.223	2.52	0.595	0.85	1	56.866	7694.67	384.73	C
			B	0.207	2.573	0.592	0.85	1	52.686			
T7 220.00-200.00	376.80	6406.00	C	0.223	2.52	0.595	0.85	1	56.866			
			A	0.181	2.66	0.587	0.85	1	52.350	8512.73	425.64	A
			B	0.171	2.696	0.585	0.85	1	49.354			
T8 200.00-180.00	548.60	7298.65	C	0.175	2.68	0.586	0.85	1	50.672			
			A	0.182	2.659	0.587	0.85	1	59.449	10082.99	504.15	A
			B	0.178	2.672	0.586	0.85	1	58.165			
T9 180.00-170.00	279.66	3730.84	C	0.182	2.659	0.587	0.85	1	59.443			
			A	0.172	2.691	0.585	0.85	1	30.539	5114.61	511.46	A
			B	0.168	2.706	0.584	0.85	1	29.797			
T10 170.00-160.00	286.19	3785.29	C	0.172	2.691	0.585	0.85	1	30.536			
			A	0.167	2.709	0.584	0.85	1	31.081	5174.13	517.41	A
			B	0.164	2.721	0.584	0.85	1	30.383			
T11 160.00-140.00	587.84	9608.59	C	0.167	2.71	0.584	0.85	1	31.078			
			A	0.176	2.678	0.586	0.85	1	69.933	10795.47	539.77	A
			B	0.176	2.677	0.586	0.85	1	69.416			
T12 140.00-120.00	611.08	9975.29	C	0.176	2.678	0.586	0.85	1	69.925			
			A	0.168	2.705	0.584	0.85	1	72.660	10900.55	545.03	B
			B	0.174	2.685	0.585	0.85	1	74.229			
T13 120.00-100.00	629.25	9144.95	C	0.168	2.705	0.584	0.85	1	72.652			
			A	0.128	2.856	0.578	0.85	1	53.418	9365.65	468.28	B
			B	0.137	2.819	0.58	0.85	1	57.755			
T14 100.00-80.00	653.88	9675.54	C	0.128	2.856	0.578	0.85	1	53.414			
			A	0.12	2.886	0.577	0.85	1	54.343	9288.98	464.45	B
			B	0.132	2.839	0.579	0.85	1	60.561			
T15 80.00-60.00	659.20	11450.50	C	0.12	2.886	0.577	0.85	1	54.340			
			A	0.125	2.866	0.578	0.85	1	62.398	9306.56	465.33	B
			B	0.136	2.824	0.579	0.85	1	68.560			
T16 60.00-30.00	988.80	15115.36	C	0.125	2.866	0.578	0.85	1	62.395			
			A	0.12	2.886	0.577	0.85	1	97.233	12596.23	419.87	B
			B	0.129	2.849	0.579	0.85	1	106.111			
T17 30.00-0.00	824.00	17941.94	C	0.12	2.886	0.577	0.85	1	97.226			
			A	0.115	2.904	0.577	0.85	1	102.069	11016.38	367.21	B
			B	0.122	2.877	0.578	0.85	1	109.385			
Sum Weight:	6924.66	125382.28	C	0.115	2.904	0.577	0.85	1	102.064			
								OTM	18404.97 kip-ft	127851.99		

Tower Forces - With Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	67.73	1985.82	A	0.276	2.363	0.609	1	1	23.476	2855.41	178.46	C
			B	0.264	2.397	0.605	1	1	22.201			
			C	0.276	2.363	0.609	1	1	23.476			
T2	18.65	476.76	A	0.263	2.398	0.605	1	1	5.538	694.62	173.66	C

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	29 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
304.00-300.00			B	0.251	2.433	0.602	1	1	5.223			
			C	0.263	2.398	0.605	1	1	5.538			
T3	172.33	3229.77	A	0.262	2.402	0.605	1	1	31.810	4352.18	217.61	C
300.00-280.00			B	0.244	2.455	0.6	1	1	29.037			
			C	0.262	2.402	0.605	1	1	31.810			
T4	363.24	6496.99	A	0.271	2.377	0.607	1	1	57.014	7802.06	390.10	C
280.00-260.00			B	0.249	2.442	0.602	1	1	52.702			
			C	0.271	2.377	0.607	1	1	57.014			
T5	482.98	7010.32	A	0.251	2.435	0.602	1	1	62.926	9030.67	451.53	C
260.00-240.00			B	0.225	2.516	0.596	1	1	56.707			
			C	0.251	2.435	0.602	1	1	62.926			
T6	622.93	8391.73	A	0.254	2.427	0.603	1	1	73.517	10614.03	530.70	C
240.00-220.00			B	0.218	2.537	0.594	1	1	63.622			
			C	0.254	2.427	0.603	1	1	73.517			
T7	1061.09	8127.65	A	0.204	2.582	0.591	1	1	67.334	11966.90	598.35	A
220.00-200.00			B	0.182	2.658	0.587	1	1	60.265			
			C	0.193	2.619	0.589	1	1	63.855			
T8	1470.38	9251.50	A	0.199	2.6	0.59	1	1	74.503	14178.21	708.91	C
200.00-180.00			B	0.189	2.632	0.588	1	1	71.097			
			C	0.199	2.599	0.59	1	1	74.579			
T9	759.82	4736.56	A	0.19	2.631	0.588	1	1	38.357	7224.25	722.43	C
180.00-170.00			B	0.179	2.667	0.586	1	1	36.385			
			C	0.19	2.631	0.588	1	1	38.395			
T10	788.67	4810.55	A	0.184	2.65	0.587	1	1	39.092	7351.99	735.20	C
170.00-160.00			B	0.175	2.681	0.586	1	1	37.096			
			C	0.184	2.649	0.587	1	1	39.129			
T11	1638.57	11942.62	A	0.193	2.621	0.589	1	1	87.357	15225.01	761.25	C
160.00-140.00			B	0.189	2.632	0.588	1	1	84.568			
			C	0.193	2.62	0.589	1	1	87.446			
T12	1733.59	12406.11	A	0.185	2.648	0.587	1	1	90.949	15273.51	763.68	C
140.00-120.00			B	0.191	2.628	0.589	1	1	91.607			
			C	0.185	2.647	0.587	1	1	91.037			
T13	1809.77	11165.81	A	0.143	2.796	0.58	1	1	66.498	13539.03	676.95	B
120.00-100.00			B	0.155	2.755	0.582	1	1	72.940			
			C	0.144	2.795	0.581	1	1	66.544			
T14	1912.02	11752.95	A	0.135	2.827	0.579	1	1	67.762	13516.19	675.81	B
100.00-80.00			B	0.15	2.772	0.581	1	1	77.333			
			C	0.135	2.826	0.579	1	1	67.807			
T15	1935.79	13749.55	A	0.14	2.809	0.58	1	1	77.342	13393.40	669.67	B
80.00-60.00			B	0.153	2.76	0.582	1	1	86.805			
			C	0.14	2.809	0.58	1	1	77.386			
T16	2903.69	18692.57	A	0.134	2.833	0.579	1	1	119.653	18002.40	600.08	B
60.00-30.00			B	0.144	2.793	0.581	1	1	132.997			
			C	0.134	2.832	0.579	1	1	119.727			
T17	2419.74	21738.94	A	0.129	2.851	0.578	1	1	125.512	15430.10	514.34	B
30.00-0.00			B	0.137	2.821	0.58	1	1	136.550			
			C	0.129	2.851	0.578	1	1	125.574			
Sum Weight:	20161.00	155966.19						OTM	25806.64 kip-ft	180449.97		

Tower Forces - With Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	30 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	67.73	1985.82	A	0.276	2.363	0.609	0.825	1	21.811	2687.48	167.97	C
			B	0.264	2.397	0.605	0.825	1	20.693			
			C	0.276	2.363	0.609	0.825	1	21.811			
T2 304.00-300.00	18.65	476.76	A	0.263	2.398	0.605	0.825	1	5.162	656.51	164.13	C
			B	0.251	2.433	0.602	0.825	1	4.886			
			C	0.263	2.398	0.605	0.825	1	5.162			
T3 300.00-280.00	172.33	3229.77	A	0.262	2.402	0.605	0.825	1	29.606	4130.77	206.54	C
			B	0.244	2.455	0.6	0.825	1	27.186			
			C	0.262	2.402	0.605	0.825	1	29.606			
T4 280.00-260.00	363.24	6496.99	A	0.271	2.377	0.607	0.825	1	47.618	6887.19	344.36	C
			B	0.249	2.442	0.602	0.825	1	43.910			
			C	0.271	2.377	0.607	0.825	1	47.618			
T5 260.00-240.00	482.98	7010.32	A	0.251	2.435	0.602	0.825	1	52.584	8021.65	401.08	C
			B	0.225	2.516	0.596	0.825	1	47.267			
			C	0.251	2.435	0.602	0.825	1	52.584			
T6 240.00-220.00	622.93	8391.73	A	0.254	2.427	0.603	0.825	1	61.419	9465.17	473.26	C
			B	0.218	2.537	0.594	0.825	1	53.023			
			C	0.254	2.427	0.603	0.825	1	61.419			
T7 220.00-200.00	1061.09	8127.65	A	0.204	2.582	0.591	0.825	1	56.166	10867.66	543.38	A
			B	0.182	2.658	0.587	0.825	1	50.172			
			C	0.193	2.619	0.589	0.825	1	53.217			
T8 200.00-180.00	1470.38	9251.50	A	0.199	2.6	0.59	0.825	1	62.065	12979.03	648.95	C
			B	0.189	2.632	0.588	0.825	1	59.176			
			C	0.199	2.599	0.59	0.825	1	62.129			
T9 180.00-170.00	759.82	4736.56	A	0.19	2.631	0.588	0.825	1	31.969	6615.39	661.54	C
			B	0.179	2.667	0.586	0.825	1	30.296			
			C	0.19	2.631	0.588	0.825	1	32.000			
T10 170.00-160.00	788.67	4810.55	A	0.184	2.65	0.587	0.825	1	32.591	6738.51	673.85	C
			B	0.175	2.681	0.586	0.825	1	30.945			
			C	0.184	2.649	0.587	0.825	1	32.622			
T11 160.00-140.00	1638.57	11942.62	A	0.193	2.621	0.589	0.825	1	72.798	13902.45	695.12	C
			B	0.189	2.632	0.588	0.825	1	70.829			
			C	0.193	2.62	0.589	0.825	1	72.873			
T12 140.00-120.00	1733.59	12406.11	A	0.185	2.648	0.587	0.825	1	75.826	13984.35	699.22	B
			B	0.191	2.628	0.589	0.825	1	76.955			
			C	0.185	2.647	0.587	0.825	1	75.900			
T13 120.00-100.00	1809.77	11165.81	A	0.143	2.796	0.58	0.825	1	58.115	12704.90	635.24	B
			B	0.155	2.755	0.582	0.825	1	63.388			
			C	0.144	2.795	0.581	0.825	1	58.162			
T14 100.00-80.00	1912.02	11752.95	A	0.135	2.827	0.579	0.825	1	59.381	12671.39	633.57	B
			B	0.15	2.772	0.581	0.825	1	67.151			
			C	0.135	2.826	0.579	0.825	1	59.426			
T15 80.00-60.00	1935.79	13749.55	A	0.14	2.809	0.58	0.825	1	67.553	12502.22	625.11	B
			B	0.153	2.76	0.582	0.825	1	75.215			
			C	0.14	2.809	0.58	0.825	1	67.597			
T16 60.00-30.00	2903.69	18692.57	A	0.134	2.833	0.579	0.825	1	104.977	16810.83	560.36	B
			B	0.144	2.793	0.581	0.825	1	115.621			
			C	0.134	2.832	0.579	0.825	1	105.051			
T17 30.00-0.00	2419.74	21738.94	A	0.129	2.851	0.578	0.825	1	110.668	14346.51	478.22	B
			B	0.137	2.821	0.58	0.825	1	119.456			
			C	0.129	2.851	0.578	0.825	1	110.731			
Sum Weight:	20161.00	155966.19						OTM	23582.53 kip-ft	165971.98		

Tower Forces - With Ice - Wind 60 To Face

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	31 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	67.73	1985.82	A	0.276	2.363	0.609	0.8	1	21.573	2663.49	166.47	C
			B	0.264	2.397	0.605	0.8	1	20.477			
			C	0.276	2.363	0.609	0.8	1	21.573			
T2 304.00-300.00	18.65	476.76	A	0.263	2.398	0.605	0.8	1	5.109	651.07	162.77	C
			B	0.251	2.433	0.602	0.8	1	4.838			
			C	0.263	2.398	0.605	0.8	1	5.109			
T3 300.00-280.00	172.33	3229.77	A	0.262	2.402	0.605	0.8	1	29.291	4099.15	204.96	C
			B	0.244	2.455	0.6	0.8	1	26.922			
			C	0.262	2.402	0.605	0.8	1	29.291			
T4 280.00-260.00	363.24	6496.99	A	0.271	2.377	0.607	0.8	1	46.275	6756.49	337.82	C
			B	0.249	2.442	0.602	0.8	1	42.654			
			C	0.271	2.377	0.607	0.8	1	46.275			
T5 260.00-240.00	482.98	7010.32	A	0.251	2.435	0.602	0.8	1	51.107	7877.50	393.88	C
			B	0.225	2.516	0.596	0.8	1	45.919			
			C	0.251	2.435	0.602	0.8	1	51.107			
T6 240.00-220.00	622.93	8391.73	A	0.254	2.427	0.603	0.8	1	59.691	9301.04	465.05	C
			B	0.218	2.537	0.594	0.8	1	51.509			
			C	0.254	2.427	0.603	0.8	1	59.691			
T7 220.00-200.00	1061.09	8127.65	A	0.204	2.582	0.591	0.8	1	54.571	10710.62	535.53	A
			B	0.182	2.658	0.587	0.8	1	48.731			
			C	0.193	2.619	0.589	0.8	1	51.697			
T8 200.00-180.00	1470.38	9251.50	A	0.199	2.6	0.59	0.8	1	60.288	12807.71	640.39	C
			B	0.189	2.632	0.588	0.8	1	57.473			
			C	0.199	2.599	0.59	0.8	1	60.351			
T9 180.00-170.00	759.82	4736.56	A	0.19	2.631	0.588	0.8	1	31.056	6528.40	652.84	C
			B	0.179	2.667	0.586	0.8	1	29.427			
			C	0.19	2.631	0.588	0.8	1	31.087			
T10 170.00-160.00	788.67	4810.55	A	0.184	2.65	0.587	0.8	1	31.662	6650.87	665.09	C
			B	0.175	2.681	0.586	0.8	1	30.067			
			C	0.184	2.649	0.587	0.8	1	31.692			
T11 160.00-140.00	1638.57	11942.62	A	0.193	2.621	0.589	0.8	1	70.719	13713.51	685.68	C
			B	0.189	2.632	0.588	0.8	1	68.866			
			C	0.193	2.62	0.589	0.8	1	70.791			
T12 140.00-120.00	1733.59	12406.11	A	0.185	2.648	0.587	0.8	1	73.665	13801.47	690.07	B
			B	0.191	2.628	0.589	0.8	1	74.862			
			C	0.185	2.647	0.587	0.8	1	73.737			
T13 120.00-100.00	1809.77	11165.81	A	0.143	2.796	0.58	0.8	1	56.917	12585.73	629.29	B
			B	0.155	2.755	0.582	0.8	1	62.024			
			C	0.144	2.795	0.581	0.8	1	56.964			
T14 100.00-80.00	1912.02	11752.95	A	0.135	2.827	0.579	0.8	1	58.184	12550.70	627.53	B
			B	0.15	2.772	0.581	0.8	1	65.696			
			C	0.135	2.826	0.579	0.8	1	58.228			
T15 80.00-60.00	1935.79	13749.55	A	0.14	2.809	0.58	0.8	1	66.154	12374.91	618.75	B
			B	0.153	2.76	0.582	0.8	1	73.560			
			C	0.14	2.809	0.58	0.8	1	66.198			
T16 60.00-30.00	2903.69	18692.57	A	0.134	2.833	0.579	0.8	1	102.880	16640.60	554.69	B
			B	0.144	2.793	0.581	0.8	1	113.138			
			C	0.134	2.832	0.579	0.8	1	102.954			
T17 30.00-0.00	2419.74	21738.94	A	0.129	2.851	0.578	0.8	1	108.548	14191.71	473.06	B
			B	0.137	2.821	0.58	0.8	1	117.014			
			C	0.129	2.851	0.578	0.8	1	108.610			
Sum Weight:	20161.00	155966.19						OTM	23264.97 kip-ft	163904.99		

Tower Forces - With Ice - Wind 90 To Face

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	32 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	67.73	1985.82	A	0.276	2.363	0.609	0.85	1	22.049	2711.47	169.47	C
			B	0.264	2.397	0.605	0.85	1	20.908			
			C	0.276	2.363	0.609	0.85	1	22.049			
T2 304.00-300.00	18.65	476.76	A	0.263	2.398	0.605	0.85	1	5.216	661.96	165.49	C
			B	0.251	2.433	0.602	0.85	1	4.934			
			C	0.263	2.398	0.605	0.85	1	5.216			
T3 300.00-280.00	172.33	3229.77	A	0.262	2.402	0.605	0.85	1	29.920	4162.40	208.12	C
			B	0.244	2.455	0.6	0.85	1	27.450			
			C	0.262	2.402	0.605	0.85	1	29.920			
T4 280.00-260.00	363.24	6496.99	A	0.271	2.377	0.607	0.85	1	48.960	7017.88	350.89	C
			B	0.249	2.442	0.602	0.85	1	45.166			
			C	0.271	2.377	0.607	0.85	1	48.960			
T5 260.00-240.00	482.98	7010.32	A	0.251	2.435	0.602	0.85	1	54.062	8165.80	408.29	C
			B	0.225	2.516	0.596	0.85	1	48.616			
			C	0.251	2.435	0.602	0.85	1	54.062			
T6 240.00-220.00	622.93	8391.73	A	0.254	2.427	0.603	0.85	1	63.147	9629.29	481.46	C
			B	0.218	2.537	0.594	0.85	1	54.537			
			C	0.254	2.427	0.603	0.85	1	63.147			
T7 220.00-200.00	1061.09	8127.65	A	0.204	2.582	0.591	0.85	1	57.762	11024.69	551.23	A
			B	0.182	2.658	0.587	0.85	1	51.614			
			C	0.193	2.619	0.589	0.85	1	54.736			
T8 200.00-180.00	1470.38	9251.50	A	0.199	2.6	0.59	0.85	1	63.842	13150.34	657.52	C
			B	0.189	2.632	0.588	0.85	1	60.879			
			C	0.199	2.599	0.59	0.85	1	63.908			
T9 180.00-170.00	759.82	4736.56	A	0.19	2.631	0.588	0.85	1	32.881	6702.37	670.24	C
			B	0.179	2.667	0.586	0.85	1	31.166			
			C	0.19	2.631	0.588	0.85	1	32.914			
T10 170.00-160.00	788.67	4810.55	A	0.184	2.65	0.587	0.85	1	33.519	6826.15	682.61	C
			B	0.175	2.681	0.586	0.85	1	31.824			
			C	0.184	2.649	0.587	0.85	1	33.551			
T11 160.00-140.00	1638.57	11942.62	A	0.193	2.621	0.589	0.85	1	74.878	14091.39	704.57	C
			B	0.189	2.632	0.588	0.85	1	72.791			
			C	0.193	2.62	0.589	0.85	1	74.955			
T12 140.00-120.00	1733.59	12406.11	A	0.185	2.648	0.587	0.85	1	77.986	14167.23	708.36	B
			B	0.191	2.628	0.589	0.85	1	79.048			
			C	0.185	2.647	0.587	0.85	1	78.062			
T13 120.00-100.00	1809.77	11165.81	A	0.143	2.796	0.58	0.85	1	59.312	12824.06	641.20	B
			B	0.155	2.755	0.582	0.85	1	64.753			
			C	0.144	2.795	0.581	0.85	1	59.359			
T14 100.00-80.00	1912.02	11752.95	A	0.135	2.827	0.579	0.85	1	60.578	12792.07	639.60	B
			B	0.15	2.772	0.581	0.85	1	68.606			
			C	0.135	2.826	0.579	0.85	1	60.623			
T15 80.00-60.00	1935.79	13749.55	A	0.14	2.809	0.58	0.85	1	68.951	12629.53	631.48	B
			B	0.153	2.76	0.582	0.85	1	76.871			
			C	0.14	2.809	0.58	0.85	1	68.995			
T16 60.00-30.00	2903.69	18692.57	A	0.134	2.833	0.579	0.85	1	107.073	16981.05	566.03	B
			B	0.144	2.793	0.581	0.85	1	118.103			
			C	0.134	2.832	0.579	0.85	1	107.147			
T17 30.00-0.00	2419.74	21738.94	A	0.129	2.851	0.578	0.85	1	112.789	14501.31	483.38	B
			B	0.137	2.821	0.58	0.85	1	121.898			
			C	0.129	2.851	0.578	0.85	1	112.851			
Sum Weight:	20161.00	155966.19						OTM	23900.09 kip-ft	168038.98		

Tower Forces - Service - Wind Normal To Face

Job	320' Rohn SSVMW	Page	33 of 41
Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	0.592	1	1	18.299	2241.92	140.12	C
			B	0.205	2.578	0.592	1	1	17.854			
			C	0.209	2.566	0.592	1	1	18.299			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	0.591	1	1	4.337	540.67	135.17	C
			B	0.198	2.604	0.59	1	1	4.226			
			C	0.201	2.592	0.591	1	1	4.337			
T3 300.00-280.00	43.60	2496.34	A	0.207	2.573	0.592	1	1	25.689	3368.49	168.42	C
			B	0.201	2.593	0.591	1	1	24.604			
			C	0.207	2.573	0.592	1	1	25.689			
T4 280.00-260.00	101.88	5067.66	A	0.237	2.476	0.599	1	1	51.464	6475.59	323.78	C
			B	0.228	2.504	0.597	1	1	49.540			
			C	0.237	2.476	0.599	1	1	51.464			
T5 260.00-240.00	137.02	5409.17	A	0.219	2.532	0.595	1	1	56.868	7420.02	371.00	C
			B	0.208	2.569	0.592	1	1	53.929			
			C	0.219	2.532	0.595	1	1	56.868			
T6 240.00-220.00	176.60	6484.36	A	0.223	2.52	0.595	1	1	66.901	8684.36	434.22	C
			B	0.207	2.573	0.592	1	1	61.984			
			C	0.223	2.52	0.595	1	1	66.901			
T7 220.00-200.00	376.80	6406.00	A	0.181	2.66	0.587	1	1	61.588	9449.61	472.48	A
			B	0.171	2.696	0.585	1	1	58.064			
			C	0.175	2.68	0.586	1	1	59.614			
T8 200.00-180.00	548.60	7298.65	A	0.182	2.659	0.587	1	1	69.940	11116.49	555.82	A
			B	0.178	2.672	0.586	1	1	68.429			
			C	0.182	2.659	0.587	1	1	69.932			
T9 180.00-170.00	279.66	3730.84	A	0.172	2.691	0.585	1	1	35.928	5639.47	563.95	A
			B	0.168	2.706	0.584	1	1	35.056			
			C	0.172	2.691	0.585	1	1	35.925			
T10 170.00-160.00	286.19	3785.29	A	0.167	2.709	0.584	1	1	36.566	5703.06	570.31	A
			B	0.164	2.721	0.584	1	1	35.716			
			C	0.167	2.71	0.584	1	1	36.563			
T11 160.00-140.00	587.84	9608.59	A	0.176	2.678	0.586	1	1	82.274	11939.98	597.00	A
			B	0.176	2.677	0.586	1	1	81.431			
			C	0.176	2.678	0.586	1	1	82.265			
T12 140.00-120.00	611.08	9975.29	A	0.168	2.705	0.584	1	1	85.482	12036.27	601.81	B
			B	0.174	2.685	0.585	1	1	86.953			
			C	0.168	2.705	0.584	1	1	85.473			
T13 120.00-100.00	629.25	9144.95	A	0.128	2.856	0.578	1	1	60.269	10038.38	501.92	B
			B	0.137	2.819	0.58	1	1	65.283			
			C	0.128	2.856	0.578	1	1	60.265			
T14 100.00-80.00	653.88	9675.54	A	0.12	2.886	0.577	1	1	61.193	9959.77	497.99	B
			B	0.132	2.839	0.579	1	1	68.454			
			C	0.12	2.886	0.577	1	1	61.189			
T15 80.00-60.00	659.20	11450.50	A	0.125	2.866	0.578	1	1	70.455	10022.40	501.12	B
			B	0.136	2.824	0.579	1	1	77.660			
			C	0.125	2.866	0.578	1	1	70.451			
T16 60.00-30.00	988.80	15115.36	A	0.12	2.886	0.577	1	1	109.311	13550.63	451.69	B
			B	0.129	2.849	0.579	1	1	119.755			
			C	0.12	2.886	0.577	1	1	109.305			
T17 30.00-0.00	824.00	17941.94	A	0.115	2.904	0.577	1	1	114.291	11890.73	396.36	B
			B	0.122	2.877	0.578	1	1	122.911			
			C	0.115	2.904	0.577	1	1	114.286			
Sum Weight:	6924.66	125382.28						OTM	20310.92 kip-ft	140077.83		

Tower Forces - Service - Wind 45 To Face

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	34 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	0.592	0.825	1	16.635	2059.57	128.72	C
			B	0.205	2.578	0.592	0.825	1	16.265			
			C	0.209	2.566	0.592	0.825	1	16.635			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	0.591	0.825	1	3.962	499.48	124.87	C
			B	0.198	2.604	0.59	0.825	1	3.869			
			C	0.201	2.592	0.591	0.825	1	3.962			
T3 300.00-280.00	43.60	2496.34	A	0.207	2.573	0.592	0.825	1	23.485	3131.38	156.57	C
			B	0.201	2.593	0.591	0.825	1	22.584			
			C	0.207	2.573	0.592	0.825	1	23.485			
T4 280.00-260.00	101.88	5067.66	A	0.237	2.476	0.599	0.825	1	42.458	5562.01	278.10	C
			B	0.228	2.504	0.597	0.825	1	40.871			
			C	0.237	2.476	0.599	0.825	1	42.458			
T5 260.00-240.00	137.02	5409.17	A	0.219	2.532	0.595	0.825	1	46.916	6410.02	320.50	C
			B	0.208	2.569	0.592	0.825	1	44.491			
			C	0.219	2.532	0.595	0.825	1	46.916			
T6 240.00-220.00	176.60	6484.36	A	0.223	2.52	0.595	0.825	1	55.194	7529.72	376.49	C
			B	0.207	2.573	0.592	0.825	1	51.137			
			C	0.223	2.52	0.595	0.825	1	55.194			
T7 220.00-200.00	376.80	6406.00	A	0.181	2.66	0.587	0.825	1	50.810	8356.58	417.83	A
			B	0.171	2.696	0.585	0.825	1	47.903			
			C	0.175	2.68	0.586	0.825	1	49.182			
T8 200.00-180.00	548.60	7298.65	A	0.182	2.659	0.587	0.825	1	57.701	9910.75	495.54	A
			B	0.178	2.672	0.586	0.825	1	56.454			
			C	0.182	2.659	0.587	0.825	1	57.694			
T9 180.00-170.00	279.66	3730.84	A	0.172	2.691	0.585	0.825	1	29.641	5027.13	502.71	A
			B	0.168	2.706	0.584	0.825	1	28.921			
			C	0.172	2.691	0.585	0.825	1	29.638			
T10 170.00-160.00	286.19	3785.29	A	0.167	2.709	0.584	0.825	1	30.167	5085.97	508.60	A
			B	0.164	2.721	0.584	0.825	1	29.494			
			C	0.167	2.71	0.584	0.825	1	30.164			
T11 160.00-140.00	587.84	9608.59	A	0.176	2.678	0.586	0.825	1	67.876	10604.71	530.24	A
			B	0.176	2.677	0.586	0.825	1	67.413			
			C	0.176	2.678	0.586	0.825	1	67.869			
T12 140.00-120.00	611.08	9975.29	A	0.168	2.705	0.584	0.825	1	70.523	10711.27	535.56	B
			B	0.174	2.685	0.585	0.825	1	72.109			
			C	0.168	2.705	0.584	0.825	1	70.515			
T13 120.00-100.00	629.25	9144.95	A	0.128	2.856	0.578	0.825	1	52.276	9253.52	462.68	B
			B	0.137	2.819	0.58	0.825	1	56.500			
			C	0.128	2.856	0.578	0.825	1	52.272			
T14 100.00-80.00	653.88	9675.54	A	0.12	2.886	0.577	0.825	1	53.202	9177.18	458.86	B
			B	0.132	2.839	0.579	0.825	1	59.245			
			C	0.12	2.886	0.577	0.825	1	53.198			
T15 80.00-60.00	659.20	11450.50	A	0.125	2.866	0.578	0.825	1	61.056	9187.25	459.36	B
			B	0.136	2.824	0.579	0.825	1	67.044			
			C	0.125	2.866	0.578	0.825	1	61.052			
T16 60.00-30.00	988.80	15115.36	A	0.12	2.886	0.577	0.825	1	95.220	12437.16	414.57	B
			B	0.129	2.849	0.579	0.825	1	103.837			
			C	0.12	2.886	0.577	0.825	1	95.213			
T17 30.00-0.00	824.00	17941.94	A	0.115	2.904	0.577	0.825	1	100.032	10870.66	362.36	B
			B	0.122	2.877	0.578	0.825	1	107.130			
			C	0.115	2.904	0.577	0.825	1	100.027			
Sum Weight:	6924.66	125382.28						OTM	18087.31 kip-ft	125814.35		

Tower Forces - Service - Wind 60 To Face

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	35 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	0.592	0.8	1	16.397	2033.52	127.10	C
			B	0.205	2.578	0.592	0.8	1	16.038			
			C	0.209	2.566	0.592	0.8	1	16.397			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	0.591	0.8	1	3.908	493.60	123.40	C
			B	0.198	2.604	0.59	0.8	1	3.818			
			C	0.201	2.592	0.591	0.8	1	3.908			
T3 300.00-280.00	43.60	2496.34	A	0.207	2.573	0.592	0.8	1	23.170	3097.50	154.88	C
			B	0.201	2.593	0.591	0.8	1	22.296			
			C	0.207	2.573	0.592	0.8	1	23.170			
T4 280.00-260.00	101.88	5067.66	A	0.237	2.476	0.599	0.8	1	41.171	5431.49	271.57	C
			B	0.228	2.504	0.597	0.8	1	39.632			
			C	0.237	2.476	0.599	0.8	1	41.171			
T5 260.00-240.00	137.02	5409.17	A	0.219	2.532	0.595	0.8	1	45.494	6265.73	313.29	C
			B	0.208	2.569	0.592	0.8	1	43.143			
			C	0.219	2.532	0.595	0.8	1	45.494			
T6 240.00-220.00	176.60	6484.36	A	0.223	2.52	0.595	0.8	1	53.521	7364.78	368.24	C
			B	0.207	2.573	0.592	0.8	1	49.587			
			C	0.223	2.52	0.595	0.8	1	53.521			
T7 220.00-200.00	376.80	6406.00	A	0.181	2.66	0.587	0.8	1	49.270	8200.43	410.02	A
			B	0.171	2.696	0.585	0.8	1	46.451			
			C	0.175	2.68	0.586	0.8	1	47.692			
T8 200.00-180.00	548.60	7298.65	A	0.182	2.659	0.587	0.8	1	55.952	9738.50	486.92	A
			B	0.178	2.672	0.586	0.8	1	54.743			
			C	0.182	2.659	0.587	0.8	1	55.946			
T9 180.00-170.00	279.66	3730.84	A	0.172	2.691	0.585	0.8	1	28.743	4939.65	493.97	A
			B	0.168	2.706	0.584	0.8	1	28.044			
			C	0.172	2.691	0.585	0.8	1	28.740			
T10 170.00-160.00	286.19	3785.29	A	0.167	2.709	0.584	0.8	1	29.253	4997.82	499.78	A
			B	0.164	2.721	0.584	0.8	1	28.605			
			C	0.167	2.71	0.584	0.8	1	29.250			
T11 160.00-140.00	587.84	9608.59	A	0.176	2.678	0.586	0.8	1	65.820	10413.96	520.70	A
			B	0.176	2.677	0.586	0.8	1	65.411			
			C	0.176	2.678	0.586	0.8	1	65.812			
T12 140.00-120.00	611.08	9975.29	A	0.168	2.705	0.584	0.8	1	68.385	10521.98	526.10	B
			B	0.174	2.685	0.585	0.8	1	69.988			
			C	0.168	2.705	0.584	0.8	1	68.378			
T13 120.00-100.00	629.25	9144.95	A	0.128	2.856	0.578	0.8	1	51.134	9141.40	457.07	B
			B	0.137	2.819	0.58	0.8	1	55.246			
			C	0.128	2.856	0.578	0.8	1	51.130			
T14 100.00-80.00	653.88	9675.54	A	0.12	2.886	0.577	0.8	1	52.060	9065.38	453.27	B
			B	0.132	2.839	0.579	0.8	1	57.930			
			C	0.12	2.886	0.577	0.8	1	52.056			
T15 80.00-60.00	659.20	11450.50	A	0.125	2.866	0.578	0.8	1	59.713	9067.94	453.40	B
			B	0.136	2.824	0.579	0.8	1	65.527			
			C	0.125	2.866	0.578	0.8	1	59.709			
T16 60.00-30.00	988.80	15115.36	A	0.12	2.886	0.577	0.8	1	93.207	12278.10	409.27	B
			B	0.129	2.849	0.579	0.8	1	101.564			
			C	0.12	2.886	0.577	0.8	1	93.200			
T17 30.00-0.00	824.00	17941.94	A	0.115	2.904	0.577	0.8	1	97.995	10724.93	357.50	B
			B	0.122	2.877	0.578	0.8	1	104.876			
			C	0.115	2.904	0.577	0.8	1	97.990			
Sum Weight:	6924.66	125382.28						OTM	17769.65 kip-ft	123776.72		

Tower Forces - Service - Wind 90 To Face

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	36 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	lb	lb							ft ²	lb	plf	
T1 320.00-304.00	15.90	1442.07	A	0.209	2.566	0.592	0.85	1	16.872	2085.62	130.35	C
			B	0.205	2.578	0.592	0.85	1	16.492			
			C	0.209	2.566	0.592	0.85	1	16.872			
T2 304.00-300.00	4.36	349.72	A	0.201	2.592	0.591	0.85	1	4.015	505.36	126.34	C
			B	0.198	2.604	0.59	0.85	1	3.920			
			C	0.201	2.592	0.591	0.85	1	4.015			
T3 300.00-280.00	43.60	2496.34	A	0.207	2.573	0.592	0.85	1	23.800	3165.25	158.26	C
			B	0.201	2.593	0.591	0.85	1	22.873			
			C	0.207	2.573	0.592	0.85	1	23.800			
T4 280.00-260.00	101.88	5067.66	A	0.237	2.476	0.599	0.85	1	43.745	5692.52	284.63	C
			B	0.228	2.504	0.597	0.85	1	42.109			
			C	0.237	2.476	0.599	0.85	1	43.745			
T5 260.00-240.00	137.02	5409.17	A	0.219	2.532	0.595	0.85	1	48.338	6554.30	327.72	C
			B	0.208	2.569	0.592	0.85	1	45.839			
			C	0.219	2.532	0.595	0.85	1	48.338			
T6 240.00-220.00	176.60	6484.36	A	0.223	2.52	0.595	0.85	1	56.866	7694.67	384.73	C
			B	0.207	2.573	0.592	0.85	1	52.686			
			C	0.223	2.52	0.595	0.85	1	56.866			
T7 220.00-200.00	376.80	6406.00	A	0.181	2.66	0.587	0.85	1	52.350	8512.73	425.64	A
			B	0.171	2.696	0.585	0.85	1	49.354			
			C	0.175	2.68	0.586	0.85	1	50.672			
T8 200.00-180.00	548.60	7298.65	A	0.182	2.659	0.587	0.85	1	59.449	10082.99	504.15	A
			B	0.178	2.672	0.586	0.85	1	58.165			
			C	0.182	2.659	0.587	0.85	1	59.443			
T9 180.00-170.00	279.66	3730.84	A	0.172	2.691	0.585	0.85	1	30.539	5114.61	511.46	A
			B	0.168	2.706	0.584	0.85	1	29.797			
			C	0.172	2.691	0.585	0.85	1	30.536			
T10 170.00-160.00	286.19	3785.29	A	0.167	2.709	0.584	0.85	1	31.081	5174.13	517.41	A
			B	0.164	2.721	0.584	0.85	1	30.383			
			C	0.167	2.71	0.584	0.85	1	31.078			
T11 160.00-140.00	587.84	9608.59	A	0.176	2.678	0.586	0.85	1	69.933	10795.47	539.77	A
			B	0.176	2.677	0.586	0.85	1	69.416			
			C	0.176	2.678	0.586	0.85	1	69.925			
T12 140.00-120.00	611.08	9975.29	A	0.168	2.705	0.584	0.85	1	72.660	10900.55	545.03	B
			B	0.174	2.685	0.585	0.85	1	74.229			
			C	0.168	2.705	0.584	0.85	1	72.652			
T13 120.00-100.00	629.25	9144.95	A	0.128	2.856	0.578	0.85	1	53.418	9365.65	468.28	B
			B	0.137	2.819	0.58	0.85	1	57.755			
			C	0.128	2.856	0.578	0.85	1	53.414			
T14 100.00-80.00	653.88	9675.54	A	0.12	2.886	0.577	0.85	1	54.343	9288.98	464.45	B
			B	0.132	2.839	0.579	0.85	1	60.561			
			C	0.12	2.886	0.577	0.85	1	54.340			
T15 80.00-60.00	659.20	11450.50	A	0.125	2.866	0.578	0.85	1	62.398	9306.56	465.33	B
			B	0.136	2.824	0.579	0.85	1	68.560			
			C	0.125	2.866	0.578	0.85	1	62.395			
T16 60.00-30.00	988.80	15115.36	A	0.12	2.886	0.577	0.85	1	97.233	12596.23	419.87	B
			B	0.129	2.849	0.579	0.85	1	106.111			
			C	0.12	2.886	0.577	0.85	1	97.226			
T17 30.00-0.00	824.00	17941.94	A	0.115	2.904	0.577	0.85	1	102.069	11016.38	367.21	B
			B	0.122	2.877	0.578	0.85	1	109.385			
			C	0.115	2.904	0.577	0.85	1	102.064			
Sum Weight:	6924.66	125382.28						OTM	18404.97 kip-ft	127851.99		

Force Totals

Job	320' Rohn SSMW	Page	37 of 41
Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M_x kip-ft	Sum of Overturning Moments, M_z kip-ft	Sum of Torques kip-ft
Leg Weight	73044.53					
Bracing Weight	52337.75					
Total Member Self-Weight	125382.28			41.98	-26.53	
Total Weight	141154.12			41.98	-26.53	
Wind 0 deg - No Ice		0.00	-161488.05	-24749.82	-26.53	303.50
Wind 30 deg - No Ice		74631.11	-129264.87	-19777.75	-11469.45	357.69
Wind 45 deg - No Ice		104103.50	-104103.50	-15916.14	-15984.65	356.42
Wind 60 deg - No Ice		125735.57	-72593.47	-11083.29	-19296.05	331.11
Wind 90 deg - No Ice		149262.21	0.00	41.98	-22912.38	233.92
Wind 120 deg - No Ice		139852.75	80744.03	12437.88	-21496.86	69.46
Wind 135 deg - No Ice		104103.50	104103.50	16000.10	-15984.65	-30.68
Wind 150 deg - No Ice		74631.11	129264.87	19861.71	-11469.45	-123.77
Wind 180 deg - No Ice		0.00	145186.94	22292.51	-26.53	-269.47
Wind 210 deg - No Ice		-74631.11	129264.87	19861.71	11416.40	-357.69
Wind 225 deg - No Ice		-104103.50	104103.50	16000.10	15931.60	-356.42
Wind 240 deg - No Ice		-139852.75	80744.03	12437.88	21443.80	-372.96
Wind 270 deg - No Ice		-149262.21	0.00	41.98	22859.32	-233.92
Wind 300 deg - No Ice		-125735.57	-72593.47	-11083.29	19243.00	-61.64
Wind 315 deg - No Ice		-104103.50	-104103.50	-15916.14	15931.60	30.68
Wind 330 deg - No Ice		-74631.11	-129264.87	-19777.75	11416.40	123.77
Member Ice	30583.91					
Total Weight Ice	190243.54			114.12	-109.31	
Wind 0 deg - Ice		0.00	-206349.69	-31163.36	-109.31	536.71
Wind 30 deg - Ice		96969.35	-167955.84	-25321.86	-14794.78	628.84
Wind 45 deg - Ice		135673.78	-135673.78	-20429.72	-20653.15	622.54
Wind 60 deg - Ice		164375.70	-94902.35	-14253.79	-24995.25	574.33
Wind 90 deg - Ice		193938.70	0.00	114.12	-29480.25	389.67
Wind 120 deg - Ice		178704.07	103174.85	15752.86	-27196.40	92.46
Wind 135 deg - Ice		135673.78	135673.78	20657.96	-20653.15	-77.82
Wind 150 deg - Ice		96969.35	167955.84	25550.10	-14794.78	-239.18
Wind 180 deg - Ice		0.00	189804.71	28849.93	-109.31	-489.31
Wind 210 deg - Ice		-96969.35	167955.84	25550.10	14576.16	-628.84
Wind 225 deg - Ice		-135673.78	135673.78	20657.96	20434.53	-622.54
Wind 240 deg - Ice		-178704.07	103174.85	15752.86	26977.79	-629.17
Wind 270 deg - Ice		-193938.70	0.00	114.12	29261.63	-389.67
Wind 300 deg - Ice		-164375.70	-94902.35	-14253.79	24776.64	-85.03
Wind 315 deg - Ice		-135673.78	-135673.78	-20429.72	20434.53	77.82
Wind 330 deg - Ice		-96969.35	-167955.84	-25321.86	14576.16	239.18
Total Weight	141154.12			41.98	-26.53	
Wind 0 deg - Service		0.00	-161488.05	-24790.25	11.77	303.50
Wind 30 deg - Service		74631.11	-129264.87	-19818.18	-11431.15	357.69
Wind 45 deg - Service		104103.50	-104103.50	-15956.57	-15946.35	356.42
Wind 60 deg - Service		125735.57	-72593.47	-11123.72	-19257.76	331.11
Wind 90 deg - Service		149262.21	0.00	1.55	-22874.08	233.92
Wind 120 deg - Service		139852.75	80744.03	12397.45	-21458.56	69.46
Wind 135 deg - Service		104103.50	104103.50	15959.67	-15946.35	-30.68
Wind 150 deg - Service		74631.11	129264.87	19821.28	-11431.15	-123.77
Wind 180 deg - Service		0.00	145186.94	22252.08	11.77	-269.47
Wind 210 deg - Service		-74631.11	129264.87	19821.28	11454.70	-357.69
Wind 225 deg - Service		-104103.50	104103.50	15959.67	15969.89	-356.42
Wind 240 deg - Service		-139852.75	80744.03	12397.45	21482.10	-372.96
Wind 270 deg - Service		-149262.21	0.00	1.55	22897.62	-233.92
Wind 300 deg - Service		-125735.57	-72593.47	-11123.72	19281.30	-61.64
Wind 315 deg - Service		-104103.50	-104103.50	-15956.57	15969.89	30.68
Wind 330 deg - Service		-74631.11	-129264.87	-19818.18	11454.70	123.77

<p>tnxTower</p> <p>AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094</p>	<p>Job</p> <p>320' Rohn SSVMW</p>	<p>Page</p> <p>38 of 41</p>
	<p>Project</p> <p>CSP Tower - Colchester, CT</p>	<p>Date</p> <p>11:26:38 05/18/20</p>
	<p>Client</p> <p>DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied</p>	<p>Designed by</p> <p>MCD</p>

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice+Temp
19	Dead+Wind 0 deg+Ice+Temp
20	Dead+Wind 30 deg+Ice+Temp
21	Dead+Wind 45 deg+Ice+Temp
22	Dead+Wind 60 deg+Ice+Temp
23	Dead+Wind 90 deg+Ice+Temp
24	Dead+Wind 120 deg+Ice+Temp
25	Dead+Wind 135 deg+Ice+Temp
26	Dead+Wind 150 deg+Ice+Temp
27	Dead+Wind 180 deg+Ice+Temp
28	Dead+Wind 210 deg+Ice+Temp
29	Dead+Wind 225 deg+Ice+Temp
30	Dead+Wind 240 deg+Ice+Temp
31	Dead+Wind 270 deg+Ice+Temp
32	Dead+Wind 300 deg+Ice+Temp
33	Dead+Wind 315 deg+Ice+Temp
34	Dead+Wind 330 deg+Ice+Temp
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
-------------	-----------------	------------------------	-----------------	-----------	------------

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	39 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	320 - 304	19.454	40	0.4432	0.2151
T2	304 - 300	17.954	40	0.4396	0.2161
T3	300 - 280	17.578	40	0.4373	0.2162
T4	280 - 260	15.733	40	0.4242	0.2161
T5	260 - 240	13.918	40	0.4162	0.2131
T6	240 - 220	12.123	40	0.4036	0.1996
T7	220 - 200	10.386	40	0.3847	0.1860
T8	200 - 180	8.745	40	0.3588	0.1740
T9	180 - 170	7.185	40	0.3321	0.1582
T10	170 - 160	6.440	40	0.3170	0.1494
T11	160 - 140	5.724	40	0.3008	0.1404
T12	140 - 120	4.440	40	0.2638	0.1282
T13	120 - 100	3.311	40	0.2231	0.1150
T14	100 - 80	2.372	40	0.1831	0.0951
T15	80 - 60	1.609	40	0.1411	0.0785
T16	60 - 30	1.033	35	0.1027	0.0641
T17	30 - 0	0.357	35	0.0467	0.0311

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
329.00	Lightning Rod 5/8x4'	40	19.454	0.4432	0.2151	Inf
327.00	Dual Lights	40	19.454	0.4432	0.2151	Inf
325.00	PD128-1	40	19.454	0.4432	0.2151	Inf
320.00	BA1012-0	40	19.454	0.4432	0.2151	Inf
318.00	ANT450F6	40	19.267	0.4430	0.2153	Inf
300.00	SC479-HF1LDF	40	17.578	0.4373	0.2162	92036
290.00	PD340-1	40	16.650	0.4304	0.2163	98167
286.00	DB809T3E-XC	40	16.282	0.4278	0.2162	119505
284.00	6' Side Mount Standoff	40	16.099	0.4265	0.2162	134046
283.00	SC479-HF1LDF(D00I-E6085) (Inverted)	40	16.007	0.4259	0.2162	142495
264.00	PD440-2	40	14.280	0.4179	0.2145	320715
260.00	6' Side Mount Standoff	40	13.918	0.4162	0.2131	340093
251.00	SC479-HF1LDF	40	13.106	0.4114	0.2079	158950
248.00	PD1142-1	40	12.837	0.4094	0.2057	128752
247.00	430-94C-09168-M-11048 TTA	40	12.747	0.4088	0.2050	121083
246.00	Sabre T-Boom (1)	40	12.658	0.4081	0.2042	114277
245.00	SC479-HF1LDF(D00I-E6085) (Inverted)	40	12.568	0.4073	0.2035	108196
238.00	531-70HD Exposed Dipole Antenna	40	11.946	0.4020	0.1981	77319
232.00	Valmont VFA-10-U V-Frame	40	11.418	0.3969	0.1938	60437
200.00	PIROD 12' Lightweight T-Frame	40	8.745	0.3588	0.1740	70113
179.00	DB586-Y	40	7.109	0.3307	0.1573	46303
177.00	DB586-Y	40	6.959	0.3277	0.1556	47875
176.00	Pirod 4' Side Mount Standoff (1)	40	6.884	0.3263	0.1548	49035
175.00	DB586-Y (inverted)	40	6.809	0.3247	0.1539	50353
168.00	L-810 Obstruction Lighting (1)	40	6.294	0.3139	0.1476	40655
165.00	L-810 Obstruction Lighting (1)	40	6.077	0.3091	0.1448	29413
164.00	L-810 Obstruction Lighting (1)	40	6.005	0.3074	0.1438	26784
163.00	Telewave ANT220F2 - Omni Antenna	40	5.934	0.3058	0.1429	24700
160.00	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	40	5.724	0.3008	0.1404	21311
154.00	Commscope PAR6-59W-PXA/A	40	5.319	0.2903	0.1360	23336

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	40 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

<i>Elevation</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
153.00	ANT450F6	40	5.254	0.2885	0.1354	24085
145.00	Telewave ANT220F2 - Omni Antenna	40	4.745	0.2736	0.1308	32397
142.00	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	40	4.561	0.2677	0.1293	36627
139.00	DB212-1	40	4.380	0.2618	0.1277	38042
117.00	3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	40	3.158	0.2171	0.1123	23125
115.00	8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	40	3.058	0.2131	0.1104	23826
112.00	Andrew 2' w/Radome	40	2.913	0.2072	0.1074	25047
107.00	PA8-65	40	2.680	0.1973	0.1022	27386
106.00	Pirot 4' Side Mount Standoff (1)	40	2.635	0.1953	0.1012	27907
94.00	PD688S-4	40	2.123	0.1705	0.0895	27305

Maximum Tower Deflections - Design Wind

<i>Section No.</i>	<i>Elevation ft</i>	<i>Horz. Deflection in</i>	<i>Gov. Load Comb.</i>	<i>Tilt °</i>	<i>Twist °</i>
T1	320 - 304	24.443	24	0.5583	0.3558
T2	304 - 300	22.552	24	0.5536	0.3566
T3	300 - 280	22.079	24	0.5505	0.3565
T4	280 - 260	19.756	24	0.5336	0.3549
T5	260 - 240	17.475	24	0.5231	0.3523
T6	240 - 220	15.221	24	0.5068	0.3321
T7	220 - 200	13.044	24	0.4826	0.3088
T8	200 - 180	10.989	24	0.4499	0.2873
T9	180 - 170	9.035	24	0.4165	0.2626
T10	170 - 160	8.103	24	0.3975	0.2489
T11	160 - 140	7.206	24	0.3773	0.2347
T12	140 - 120	5.596	24	0.3310	0.2154
T13	120 - 100	4.180	24	0.2801	0.1944
T14	100 - 80	3.001	24	0.2300	0.1616
T15	80 - 60	2.041	24	0.1774	0.1331
T16	60 - 30	1.316	19	0.1292	0.1086
T17	30 - 0	0.459	19	0.0589	0.0526

Critical Deflections and Radius of Curvature - Design Wind

<i>Elevation ft</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
329.00	Lightning Rod 5/8x4'	24	24.443	0.5583	0.3558	Inf
327.00	Dual Lights	24	24.443	0.5583	0.3558	Inf
325.00	PD128-1	24	24.443	0.5583	0.3558	Inf
320.00	BA1012-0	24	24.443	0.5583	0.3558	Inf
318.00	ANT450F6	24	24.207	0.5581	0.3560	Inf
300.00	SC479-HF1LDF	24	22.079	0.5505	0.3565	71385
290.00	PD340-1	24	20.910	0.5416	0.3559	74818
286.00	DB809T3E-XC	24	20.447	0.5381	0.3555	89487
284.00	6' Side Mount Standoff	24	20.216	0.5365	0.3553	99194

tnxTower AECOM 500 Enterprise Drive, Suite 3B Rocky Hill, CT Phone: 860-263-5800 FAX: 860-812-2094	Job	320' Rohn SSVMW	Page	41 of 41
	Project	CSP Tower - Colchester, CT	Date	11:26:38 05/18/20
	Client	DESPP Loads /VZW-217/EMP-008/EVS-010-"TIA-F" applied	Designed by	MCD

<i>Elevation</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
283.00	SC479-HF1LDF(D00I-E6085) (Inverted)	24	20.101	0.5357	0.3552	104743
264.00	PD440-2	24	17.929	0.5252	0.3540	227159
260.00	6' Side Mount Standoff	24	17.475	0.5231	0.3523	240427
251.00	SC479-HF1LDF	24	16.455	0.5168	0.3449	115341
248.00	PD1142-1	24	16.117	0.5143	0.3416	94350
247.00	430-94C-09168-M-11048 TTA	24	16.004	0.5134	0.3405	88954
246.00	Sabre T-Boom (1)	24	15.892	0.5125	0.3393	84141
245.00	SC479-HF1LDF(D00I-E6085) (Inverted)	24	15.780	0.5116	0.3381	79823
238.00	531-70HD Exposed Dipole Antenna	24	14.999	0.5047	0.3296	58178
232.00	Valmont VFA-10-U V-Frame	24	14.337	0.4982	0.3224	46568
200.00	PIROD 12' Lightweight T-Frame	24	10.989	0.4499	0.2873	55451
179.00	DB586-Y	24	8.941	0.4146	0.2613	37488
177.00	DB586-Y	24	8.753	0.4110	0.2586	38801
176.00	Pirod 4' Side Mount Standoff (1)	24	8.659	0.4091	0.2572	39761
175.00	DB586-Y (inverted)	24	8.566	0.4072	0.2559	40851
168.00	L-810 Obstruction Lighting (1)	24	7.920	0.3936	0.2460	32823
165.00	L-810 Obstruction Lighting (1)	24	7.648	0.3876	0.2416	23626
164.00	L-810 Obstruction Lighting (1)	24	7.558	0.3856	0.2401	21489
163.00	Telewave ANT220F2 - Omni Antenna	24	7.469	0.3835	0.2387	19799
160.00	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	24	7.206	0.3773	0.2347	17056
154.00	Commscope PAR6-59W-PXA/A	24	6.698	0.3642	0.2278	18694
153.00	ANT450F6	24	6.616	0.3619	0.2268	19300
145.00	Telewave ANT220F2 - Omni Antenna	24	5.979	0.3432	0.2196	26056
142.00	Sitepro1 USF-4U Mount Assembly (Ca = 1.4 assumed)	24	5.748	0.3359	0.2171	29510
139.00	DB212-1	24	5.521	0.3285	0.2146	30642
117.00	3' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	24	3.987	0.2726	0.1900	18410
115.00	8' Wide Ice Shield (for Dish Antennas) (Assume Ca=2.0)	24	3.863	0.2676	0.1869	18996
112.00	Andrew 2' w/Radome	24	3.680	0.2602	0.1820	20021
107.00	PA8-65	24	3.388	0.2477	0.1735	22000
106.00	Pirod 4' Side Mount Standoff (1)	24	3.331	0.2452	0.1717	22444
94.00	PD688S-4	24	2.689	0.2142	0.1521	22006

About AECOM

AECOM (NYSE: ACM) is a global provider of professional technical and management support services to a broad range of markets, including transportation, facilities, environmental, energy, water and government. With approximately 45,000 employees around the world, AECOM is a leader in all of the key markets that it serves. AECOM provides a blend of global reach, local knowledge, innovation, and collaborative technical excellence in delivering solutions that enhance and sustain the world's built, natural, and social environments. A Fortune 500 company, AECOM serves clients in more than 100 countries and has annual revenue in excess of \$6 billion.

More information on AECOM and its services can be found at www.aecom.com.

500 Enterprise Drive, Suite 3B
Rocky Hill, CT 06067
860-529-8882
Fax: 860-529-3991

Report Date: May 6, 2019

Client: On Air Engineering, LLC
88 Foundry Pond Road
Cold Spring, NY 10516
Attn: David Weinpahl, P.E.
(201) 456-4624

Structure: Existing 320-ft Self Support Tower

Carrier Site Name: Colchester CT

Mount Type: (3) 12 Foot Sector Frames

Site Address: 112 Windham Ave.

City, County, State: Colchester, New London County, CT

Latitude, Longitude: 41.59265, -72.3212

PJF Project: A42918-0031.002.8190

Paul J. Ford and Company is pleased to submit this "Mount Structural Analysis Report". The purpose of this analysis is to determine if the mount has sufficient capacity to support the equipment described herein. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point is not part of this document.

Analysis Criteria:

Reference Standard: 2018 Connecticut State Building Code with the ANSI/TIA-222-G-2005 Standard, "Structural Standard for Antenna Supporting Structures and Antennas", with ANSI/TIA-222-G-1-2007 and ANSI/TIA-222-G-2-2009 Addenda per Exception #5 of Section 1609.1.1.

Ultimate Wind Speed: 140 mph 3-second gust wind speed without ice

Nominal Wind Speed: 108 mph 3-second gust wind speed without ice

Ice Wind Speed: 50 mph 3-second gust wind speed with 0.75" ice

IBC Site Criteria: Risk Category IV, Topographic Category 3, Exposure Category C


Summary of Analysis Results:

Antenna Mount: **92.8%** **SUFFICIENT***

*Sufficient upon completion of the changes listed in the 'Recommendations' section of this report.


We at Paul J. Ford and Company appreciate the opportunity of providing our continuing professional services to you and On Air Engineering, LLC. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully Submitted by:
Paul J. Ford and Company



Steven Pozz
Structural Designer
Spozz@pauljford.com

D.S.



Columbus
250 E Broad St, Suite 600
Columbus, OH 43215
Phone 614.221.6679



Orlando
1801 Lee Rd, Suite 230
Winter Park, FL 32789
Phone 407.898.9039

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Reference Standard
Table 1 – Equipment Configuration

3) ANALYSIS PROCEDURE

Table 2 – Documents Provided
3.1) Analysis Method
3.2) Assumptions

4) ANALYSIS RESULTS

Table 3 - Mount Component Capacity
4.1) Recommendations

STANDARD CONDITIONS

APPENDIX A – WIRE FRAME AND RENDERED MODELS

APPENDIX B – SOFTWARE INPUT CALCULATIONS

APPENDIX C – SOFTWARE ANALYSIS OUPUT

APPENDIX D – SUPPLEMENTAL MODIFICATION INFORMATION

1) INTRODUCTION

The existing mounts under consideration are (3) 12 Sector Frames Sector Frames installed at the 220' elevation on a 320' Self Support tower. The existing mounts considered in this analysis are identified as a Rohn D930624 based on photos.

2) ANALYSIS CRITERIA

This analysis has been performed in accordance with the 2018 Connecticut State Building Code based upon an ultimate 3-second gust wind speed of 140 mph converted to a nominal 3-second gust wind speed of 108 mph per section 1609.3.1 as required for use in the ANSI/TIA-222-G-2005 Standard, "Structural Standard for Antenna Supporting Structures and Antennas", with ANSI/TIA-222-G-1-2007 and ANSI/TIA-222-G-2-2009 Addenda per Exception #5 of Section 1609.1.1. and 50 mph with 0.75 inch ice thickness. Risk Category IV, Exposure Category C and Topographic Category 3 with a maximum Topographic Factor, Crest Elevation of 66.5-ft.

In addition, the mounts have been analyzed for various live loading conditions consisting of a 250-pound man live load applied individually at the midpoint and cantilevered ends of horizontal members as well as a 250-pound man live load applied individually at mount pipe locations using a 3-second wind speed of 30 mph.

Table 1 – Equipment Configuration

Mounting Level (feet)	Center Line Elevation (feet)	Quantity	Manufacturer	Model	Status	Mount Type
220	220 +/-	1	Raycap	RVZDC-6627-PF-48	Proposed	Tower Mounted
		6	Commscope	JAHH-65B-R3B		
		3	Commscope	BSAMNT-SBS-2-2		
		3	Samsung	B2/B66A RRH-BR049		
		3	Samsung	B5/B13 RRH-BR04C		
		3	Commscope	CBC78T-DS-43-2X		
		3	Andrew	LNX-6512DS-VTM	Existing	(3) 12' Sector Frames
		3	Alcatel Lucent	RRH 2X60 700	Equipment to be removed	
		3	Alcatel Lucent	RRH 2X90 AWS		
		6	Andrew	SBNHH-1D65B		
		3	Amphenol	BXA-70063-6CF		

3) ANALYSIS PROCEDURE

Table 2 – Documents Provided

Document	Remarks	Reference	Source
Mount Manufacturer Drawings	Rohn, 01/04/1994	Model#: D930624 Rev. 05	On Air Engineering
Radio Frequency Data Sheet	Verizon, 12/07/2018	894053	On Air Engineering
Construction Drawings	On Air Engineering, 12/27/2018	Colchester CT	On Air Engineering
Site Photos	12/20/2018	-	On Air Engineering
Loading Confirmation	On Air Engineering, 05/01/2019	Emailed Redlines from David Weinpahl	On Air Engineering

3.1) Analysis Method

RISA-3D (version 15.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the mount and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix C.

3.2) Assumptions

- 1) *The analysis of the existing self support tower or the effect of the mount attachment to the tower is not within the current scope of work.*
- 2) *The antenna mounting system was properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer’s specifications and all bolts are tightened as specified by the manufacturer and AISC requirements.*
- 3) *The configuration of antennas, mounts, and other appurtenances are as specified in Table 1.*
- 4) *All member connections have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report. All U-Bolt connections have been properly tightened. This analysis will be required to be revised if the existing conditions in the field differ from those shown in the above referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.*
- 5) *Steel grades have been assumed as follows:*

a) Channel, Solid Round, Angle, Plate, Unistrut	ASTM A36 (GR 36)
b) Pipe	ASTM A53 (GR 35)
c) HSS (Rectangular)	ASTM 500 (GR B-46)
d) HSS (Round)	ASTM 500 (GR B-42)
e) Connection Bolts	ASTM A325
f) Threaded Rods	ASTM F1554 (GR 36)
- 6) *Proposed equipment is to be installed in the locations specified in Appendix A. Any changes to the proposed equipment locations will render this report invalid.*
- 7) *Mount has been modeled based on the photographs referenced in Table 2, indicating a match to the Rohn mount model D930624. Member information and dimensions not provided have been assumed to match those specified in the manufacturer drawings referenced in Table 3. No guarantee can be made as to the accuracy of these assumptions without a complete mount mapping.*

This analysis may be affected if any assumptions are not valid or have been made in error. Paul J Ford and Company should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 3 – Mount Component Capacity

Notes	Component	% Capacity	Pass / Fail
1	Mount Pipes	92.8	Pass
1	Face Horizontal	55.1	Pass
1	Standoff Members	34.5	Pass
1	Bracing Members	75.2	Pass
1	Tie Back	15.3	Pass
1	Mount to Tower Connection (bolts/welds)	15.9	Pass
Mount Rating (max from all components) =			92.8%

Notes:

1. See additional documentation in "Appendix C – Software analysis Output" for calculations supporting the % capacity consumed.

4.1) Recommendations

The mount will have sufficient capacity to carry the proposed loading configuration once the recommendations listed below are met and properly installed:



- Relocate existing tie-back mount connection location. See Appendix D for details.

STANDARD CONDITIONS FOR FURNISHING OF PROFESSIONAL ENGINEERING SERVICES ON EXISTING MOUNTS BY PAUL J. FORD AND COMPANY

- 1) It is the responsibility of the client to ensure that the information provided to Paul J. Ford and Company is accurate and complete. Paul J. Ford and Company will rely on the accuracy and completeness of such information in performing or furnishing services under this project.
- 2) If the existing conditions are not as represented on the referenced drawings and/or documents, Paul J. Ford and Company should be contacted immediately to evaluate the significance of the deviation.
- 3) The mount has been analyzed according to the minimum design loads recommended by the Reference Standard. If additional design loads are required, Paul J. Ford and Company should be made aware of this prior to the start of the project.
- 4) The standard of care for all Professional Engineering Services performed or furnished by Paul J. Ford and Company under this project will be the skill and care used by members of the Consultant's profession practicing under similar circumstances at the same time and in the same locality.
- 5) All Services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. Paul J. Ford and Company is not responsible for the conclusions, opinions and/or recommendations made by others based on the information supplied herein.


APPENDIX A

WIRE FRAME AND RENDERED MODELS




Envelope Only Solution

Paul J. Ford and Company	On Air- Colchester CT	SK - 1
PJF		May 6, 2019 at 5:14 PM
42918-0031.002.8190		37518-0031_WindLoad.r3d



Proposed: (typ. on all sectors)
- (1) B5/B13 RRH-BR04C

Proposed: (typ. on all sectors)
- (1) B2/B66A RRH-BR049



Proposed: (typ. on all sectors)
- (2) JAHH-65B-R3B
- (1) BSAMNT-SBS-2-2, &
- (1) CBC78T-DS-43-2X

Envelope Only Solution

Paul J. Ford and Company
PJF
42918-0031.002.8190

On Air- Colchester CT

SK - 2

May 6, 2019 at 5:14 PM

37518-0031_WindLoad.r3d

APPENDIX B

SOFTWARE INPUT CALCULATIONS

Mount Loading per TIA-222-G-2

Structure & Wind Speed

Structure Type = **Mount**
 Mount Type = **1 Sector**
 Mount Centerline, z = **220** ft
 Centerline Y Coordinate = **0** in

Wind Speed = **108** mph
 Service Wind Speed = **30** mph
 Const. Duration = **[]**
 Non-Op Wind Speed = **#N/A** mph
 Op Wind Speed = **30** mph
 Ice Wind Speed = **50** mph
 Ice Thickness = **0.75** in

Topo

Exposure Cat = **C**
 Structure Class = **II**
 Topographic Cat = **3**
 Crest Height = **66.5** ft

Velocity Pressure Coefficients

$Z_0 = 900$ ft
 $a = 9.50$
 $K_{zmin} = 0.85$
 $K_z = 1.49$ Calculated Value
 $K_z = 1.49$ Section 2.6.5.2
 $K_{zt} = 1.00$ Section 2.6.6.4
 $G_h = 1.00$ Section 2.6.7
 $K_d = 0.95$ Table 2-2
 $I = 1.00$ Table 2-3
 $q_z = 42.38$ psf Section 2.6.9.6

Ice Loading

$l_i = 1.00$ Table 2-3
 $l_{wi} = 1.00$ Table 2-3
 $q_z = 9.08$ psf Section 2.6.9.6
 $K_{iz} = 1.21$ Section 2.6.8
 $T_{iz} = 1.81$ in Section 2.6.8
 $h = []$ in Bar Grating Height
 $W_i = 8.46$ psf Grating Ice Weight

Wind Pressures

Pressure = **42.384** psf
 Ice Pressure = **9.084** psf

Antennas

Item	Status	Manufacturer	Antenna	Height (in)	Width (in)	Depth (in)	Flat or Round	Weight (lbs)	Sector / Face	Position	Assumed Spacing (in)	Override Spacing (in)	Max Equip C/L (ft)	Min Equip C/L (ft)	Equip C/L (ft)	Top Location (in)	Bottom Location (in)	Override Top Location (in)	Override Bottom Location (in)
1		COMMSCOPE	(2) JAHH-65B-R3B W/ BSAMNT-SBS-2-2	77	36	14.1	Flat	188.6	C	3	71.00	65	221.13	220.54	221	44.50	-20.50		
4		ANDREW	LNX-6512DS-VTM	48	11.9	7.1	Flat	20.5	C	1	42.00		222.08	219.58	221	33.00	-9.00		
7		SAMSUNG TELECOMMUNICATIONS	B5/B13 RRH-BR04C (RFV01U-D2A)	15	15	8.1	Flat	70.3	C	4	9.00		223.46	218.21	220	4.50	-4.50		
10		SAMSUNG TELECOMMUNICATIONS	B2/B66A RRH-BR049 (RFV01U-D1A)	15	15	10	Flat	84.4	C	2	9.00		223.46	218.21	220	4.50	-4.50		
13		COMMSCOPE	CBC78T-DS-43-2X	6.4	6.9	9.6	Flat	20.7	C	3	0.40		223.82	217.85	220	0.20	-0.20		

Dishes



Item	Status	Manufacturer	Microwave Dish	Dia (in)	Dish Type	Weight (lbs)	Sector / Face	Position	Assumed Spacing (in)	Override Spacing (in)	Max Equip C/L (ft)	Min Equip C/L (ft)	Equip C/L (ft)	Top Location (in)	Bottom Location (in)	Override Top Location (in)	Override Bottom Location (in)
------	--------	--------------	----------------	----------	-----------	--------------	---------------	----------	----------------------	-----------------------	--------------------	--------------------	----------------	-------------------	----------------------	----------------------------	-------------------------------

ASCE 7 Hazards Report

Address:
No Address at This Location

Standard: ASCE/SEI 7-10
Risk Category: IV
Soil Class: D - Stiff Soil

Elevation: 591.52 ft (NAVD 88)
Latitude: 41.5925
Longitude: -72.321111



Wind

Results:

Wind Speed:	139 Vmph
10-year MRI	78 Vmph
25-year MRI	88 Vmph
50-year MRI	96 Vmph
100-year MRI	105 Vmph

140 MPH PER JURISDICTION

Data Source: ASCE/SEI 7-10, Fig. 26.5-1B and Figs. CC-1–CC-4, incorporating errata of March 12, 2014

Date Accessed: Wed Dec 26 2018

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 3% probability of exceedance in 50 years (annual exceedance probability = 0.000588, MRI = 1,700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Mountainous terrain, gorges, ocean promontories, and special wind regions should be examined for unusual wind conditions.

Ice

Results:

Ice Thickness: 0.75 in.

Concurrent Temperature: 15 F

Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Wed Dec 26 2018

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.


The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.


In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

APPENDIX C

SOFTWARE ANALYSIS OUTPUT





Code Check (Env)	
Black	No Calc
Red	> 1.0
Magenta	.90-1.0
Green	.75-.90
Cyan	.50-.75
Blue	0-.50





Member Code Checks Displayed (Enveloped)
Envelope Only Solution

Paul J. Ford and Company	On Air- Colchester CT	SK - 3
PJF		May 6, 2019 at 5:14 PM
42918-0031.002.8190		37518-0031_WindLoad.r3d





Envelope Only Solution

Paul J. Ford and Company	On Air- Colchester CT	SK - 5
PJF		May 6, 2019 at 5:14 PM
42918-0031.002.8190		37518-0031_WindLoad.r3d



Envelope Only Solution

Paul J. Ford and Company	On Air- Colchester CT	SK - 6
PJF		May 6, 2019 at 5:14 PM
42918-0031.002.8190		37518-0031_WindLoad.r3d



Loads: BLC 1, Dead
Envelope Only Solution

Paul J. Ford and Company	On Air- Colchester CT	SK - 7
PJF		May 6, 2019 at 5:14 PM
42918-0031.002.8190		37518-0031_WindLoad.r3d



(Global) Model Settings

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation?	Yes
Increase Nailing Capacity for Wind?	Yes
Include Warping?	Yes
Trans Load Btwn Intersecting Wood Wall?	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Include P-Delta for Walls?	Yes
Automatically Iterate Stiffness for Walls?	No
Max Iterations for Wall Stiffness	3
Gravity Acceleration (in/sec^2)	386.4
Wall Mesh Size (in)	12
Eigensolution Convergence Tol. (1.E-)	4
Vertical Axis	Y
Global Member Orientation Plane	XZ
Static Solver	Sparse Accelerated
Dynamic Solver	Accelerated Solver

Hot Rolled Steel Code	AISC 14th(360-10): LRFD
Adjust Stiffness?	Yes(Iterative)
RISACONNECTION CODE	None
Cold Formed Steel Code	None
Wood Code	None
Wood Temperature	< 100F
Concrete Code	None
Masonry Code	None
Aluminum Code	None - Building

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parame Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections?	No
Use Cracked Sections Slab?	Yes
Bad Framing Warnings?	No
Unused Force Warnings?	No
Min 1 Bar Diam. Spacing?	No
Concrete Rebar Set	REBAR SET ASTMA615
Min % Steel for Column	1
Max % Steel for Column	0



(Global) Model Settings, Continued

Seismic Code	None
Seismic Base Elevation (in)	Not Entered
Add Base Weight?	No
Ct X	0
Ct Z	0
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	1
R Z	1

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1/E...)	Density[k/ft...]	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A53 Gr. B (35 ksi)	29000	11154	.3	.65	.49	35	1.5	60	1.2
2	A500 Gr. B (46ksi)	29000	11154	.3	.65	.49	46	1.5	58	1.2
3	A36 (36ksi)	29000	11154	.3	.65	.49	36	1.5	58	1.2

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(d...)	Section/Shape	Type	Design List	Material	Design Ru...
1	C4	A1	A4			PIPE 2.0	Column	Pipe	A53 Gr. B (35 ksi)	Typical
2	B2	B1	B2			PIPE 2.5	None	None	A53 Gr. B (35 ksi)	Typical
3	B1	B3	B4			PIPE 2.5	None	None	A53 Gr. B (35 ksi)	Typical
4	P1	D2	N32		90	PL 3.5 x 3/8	None	None	A36 (36ksi)	Typical
5	K1	E2	N59			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
6	RTFG	N38	N39			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
7	D1	N36A	N37			11 Gage	None	None	A53 Gr. B (35 ksi)	Typical
8	D2	N34B	N35B			11 Gage	None	None	A53 Gr. B (35 ksi)	Typical
9	E2	N34B	N37			16 Gage	None	None	A53 Gr. B (35 ksi)	Typical
10	E1	N36A	N39			16 Gage	None	None	A53 Gr. B (35 ksi)	Typical
11	M22	A3	N42			RIGID	None	None	RIGID	Typical
12	M23	A2	N41A			RIGID	None	None	RIGID	Typical
13	M19	N32	C2			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
14	M18	N32A	N33B		90	PL 3.5 x 3/8	None	None	A36 (36ksi)	Typical
15	M19A	N33B	N31			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
16	M19B	D2	N33		90	PL 3.5 x 3/8	None	None	A36 (36ksi)	Typical
17	M20	N41B	N42A			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
18	M21	N39A	N40			11 Gage	None	None	A53 Gr. B (35 ksi)	Typical
19	M22A	N37A	N38A			11 Gage	None	None	A53 Gr. B (35 ksi)	Typical
20	M23A	N38A	N39A			16 Gage	None	None	A53 Gr. B (35 ksi)	Typical
21	M24	N40	N41B			16 Gage	None	None	A53 Gr. B (35 ksi)	Typical
22	M25	N33	N31A			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
23	M26	N32A	N36		90	PL 3.5 x 3/8	None	None	A36 (36ksi)	Typical
24	M27A	N36	N34			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
25	C1	N35	N38B			PIPE 2.0	Column	Pipe	A53 Gr. B (35 ksi)	Typical
26	M26A	N37B	N40A			RIGID	None	None	RIGID	Typical
27	M27	N36B	N39B			RIGID	None	None	RIGID	Typical
28	C3	N41	N44			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
29	M29	N43	N46			RIGID	None	None	RIGID	Typical
30	M30	N42B	N45			RIGID	None	None	RIGID	Typical
31	C2	N47	N50			PIPE 2.0	None	None	A53 Gr. B (35 ksi)	Typical
32	M32	N49	N52			RIGID	None	None	RIGID	Typical
33	M33	N48	N51			RIGID	None	None	RIGID	Typical
34	M34	N56	N55			PIPE 3.5	None	None	A53 Gr. B (35 ksi)	Typical



Member Advanced Data

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Analysis ...	Inactive	Seismic Design ...
1	C4						Yes			None
2	B2						Yes			None
3	B1						Yes			None
4	P1						Yes			None
5	K1		BenPIN				Yes			None
6	RTFG	BenPIN	BenPIN				Yes			None
7	D1	BenPIN	BenPIN				Yes			None
8	D2	BenPIN	BenPIN				Yes			None
9	E2	BenPIN	BenPIN				Yes			None
10	E1	BenPIN	BenPIN				Yes			None
11	M22	OOOXOX					Yes		Exclude	None
12	M23	OOOXOX					Yes		Exclude	None
13	M19		BenPIN				Yes			None
14	M18						Yes			None
15	M19A		BenPIN				Yes			None
16	M19B						Yes			None
17	M20	BenPIN	BenPIN				Yes			None
18	M21	BenPIN	BenPIN				Yes			None
19	M22A	BenPIN	BenPIN				Yes			None
20	M23A	BenPIN	BenPIN				Yes			None
21	M24	BenPIN	BenPIN				Yes			None
22	M25		BenPIN				Yes			None
23	M26						Yes			None
24	M27A		BenPIN				Yes			None
25	C1						Yes			None
26	M26A	OOOXOX					Yes		Exclude	None
27	M27	OOOXOX					Yes		Exclude	None
28	C3						Yes			None
29	M29	OOOXOX					Yes		Exclude	None
30	M30	OOOXOX					Yes		Exclude	None
31	C2						Yes			None
32	M32	OOOXOX					Yes		Exclude	None
33	M33	OOOXOX					Yes		Exclude	None
34	M34						Yes			None

Hot Rolled Steel Design Parameters

	Label	Shape	Length[in]	Lbyy[in]	Lbzz[in]	Lcomp top[in]	Lcomp bot[in]	L-torqu...	Kyy	Kzz	Cb	Function
1	C4	PIPE 2.0	72			Lbyy						Lateral
2	B2	PIPE 2.5	144			Lbyy						Lateral
3	B1	PIPE 2.5	144			Lbyy						Lateral
4	P1	PL 3.5 x 3/8	3			Lbyy						Lateral
5	K1	PIPE 2.0	100.407			Lbyy						Lateral
6	RTFG	PIPE 2.0	42			Lbyy						Lateral
7	D1	11 Gage	42			Lbyy						Lateral
8	D2	11 Gage	42			Lbyy						Lateral
9	E2	16 Gage	51.146			Lbyy						Lateral
10	E1	16 Gage	51.004			Lbyy						Lateral
11	M19	PIPE 2.0	70.919									Lateral
12	M18	PL 3.5 x 3/8	3			Lbyy						Lateral
13	M19A	PIPE 2.0	70.919									Lateral
14	M19B	PL 3.5 x 3/8	3			Lbyy						Lateral
15	M20	PIPE 2.0	42			Lbyy						Lateral
16	M21	11 Gage	42			Lbyy						Lateral
17	M22A	11 Gage	42			Lbyy						Lateral



Company : Paul J. Ford and Company
 Designer : PJF
 Job Number : 42918-0031.002.8190
 Model Name : On Air- Colchester CT

May 6, 2019
 5:14 PM
 Checked By: _____

Envelope AISC 14th(360-10): LRFD Steel Code Checks (Continued)

Member	Shape	Code Check	Loc[in]	LC	Shear Check	Loc[in]	Dir	LC	phi*Pn...	phi*Pnt...	phi*Mn...	phi*Mn...	Cb	Eqn
24	RTFG	PIPE_2.0	.038	42	26	.209	0	7	27741...	32130	1.872	1.872	1..	H1-1b*
25	M22A	11 Gage	.033	21	8	.071	0	7	11644...	17008...	.622	.622	1..	H1-1b
26	M20	PIPE_2.0	.015	21	4	.205	0	7	27741...	32130	1.872	1.872	1..	H1-1b

PJF PAUL J. FORD & COMPANY

250 E Broad St, Ste 600 • Columbus, OH 43215
Phone 614.221.6679 www.pauljford.com

Project # **A42918-0031.002.8190**

By **STP**

Date: 05/06/19

v0.1, Effective 07/10/18

MOUNT TO TOWER CONNECTION CHECKS

REACTIONS


Px=	1.61	Kip
Py=	3.61	Kip
(Axial)Pz=	1.63	Kip
Mx=	0	Kip-in
My=	0	Kip-in
(Torque)Mz=	0	Kip-in
Number of Bolts	=	2

BOLT CHECKS

Tension Reaction	0.82	kip
Shear Reaction	1.98	kip
Bolt Type	A325N	
Bolt Diameter	0.625	in
Tensile Strength	20.7	kips
Shear Strength	12.4	kips
Reduced Tensile Strength	-	kips
Tensile Capacity Used	3.9%	Note: Tension reduction not required if tension or shear capacity < 30%
Shear Capacity Used	15.9%	


APPENDIX D

SUPPLEMENTAL MODIFICATION INFORMATION



Existing tieback mount connection to be relocated to adjacent mount pipe

Relocate RRH as needed to accommodate the Tieback



Envelope Only Solution

Paul J. Ford and Company
PJF
42918-0031.002.8190

On Air- Colchester CT

SK - 8
May 6, 2019 at 5:15 PM
37518-0031_WindLoad.r3d

ATTACHMENT 5



Town of Colchester, CT

Property Report

Map Block Lot

06-04/010-000

PID 5602

Building # 1

Section # 1

Account


C0515000

Property Information


Property Location	11 MUNN RD
Owner	CONNECTICUT STATE OF
Co-Owner	na
Mailing Address	165 CAPITOL AVE HARTFORD CT 06106
Land Use	901V State MDL-00
Land Class	E
Zoning Code	R60
Census Tract	

Neighborhood	
Acreage	0.53
Utilities	UNKNOWN
Lot Setting/Desc	UNKNOWN UNKNOWN
Additional Info	

Ph



Sketch



Primary Construction Details

Year Built	0
Stories	
Building Style	UNKNOWN
Building Use	Vacant
Building Condition	
Interior Floors 1	
Interior Floors 2	NA
Total Rooms	0
Basement Garages	
Occupancy	
Building Grade	

Bedrooms	0
Full Bathrooms	0
Half Bathrooms	0
Extra Fixtures	0
Bath Style	
Kitchen Style	
Roof Style	
Roof Cover	
AC Type	
Fireplaces	0

Exterior Walls	
Exterior Walls 2	NA
Interior Walls	
Interior Walls 2	NA
Heating Type	
Heating Fuel	
Sq. Ft. Basement	
Fin BSMT Quality	
Extra Kitchens	

ATTACHMENT 6



COLCHESTER
Certificate of Mailing — Firm

Name and Address of Sender Kenneth C. Baldwin, Esq. Robinson & Cole LLP 280 Trumbull Street Hartford, CT 06103		TOTAL NO. of Pieces Listed by Sender <p align="center">3</p>	TOTAL NO. of Pieces Received at Post Office™ <p align="center">3</p>	Affix Stamp Here <i>Postmark with Date of Receipt.</i> <div style="text-align: right;"> ZIP 06103 041L12203937 </div> <div align="center"> </div>	
		Postmaster, per (name of receiving employee) 			
USPS® Tracking Number Firm-specific Identifier	Address (Name, Street, City, State, and ZIP Code™)	Postage	Fee	Special Handling	Partial Airlift
1.	Mary Bylone, First Selectman Town of Colchester 127 Norwich Avenue Colchester, CT 06415				
2.	Matthew Bordeaux, Town Planner Town of Colchester 127 Norwich Avenue Colchester, CT 06415				
3.	State of Connecticut Attn: Brian Benito Department of Emergency Services and Public Protection 111 Country Club Road Middletown, CT 06457				
4.					
5.					
6.					