

280 Trumbull Street  
Hartford, CT 06103-3597  
Main (860) 275-8200  
Fax (860) 275-8299  
kbaldwin@rc.com  
Direct (860) 275-8345

RECEIVED  
JUN 14 2012

CONNECTICUT  
SITING COUNCIL

June 13, 2012

David Martin  
Siting Analyst  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

Re: **EM-VER-028-111227 – Cellco Partnership d/b/a Verizon Wireless  
48 Westchester Road, Colchester, Connecticut**


Dear Mr. Martin:

On January 17, 2012, the Siting Council acknowledged receipt of Cellco’s notice of intent to modify its telecommunications facility at 48 Westchester Road in Colchester. The modification involved the replacement of certain antennas and the installation of additional coax cables.

As a condition of this acknowledgement, Cellco was required to provide the Council with a letter stating that the recommendations specified in the structural report were implemented. Attached is a Tower Modification Certification Letter verifying that this condition has been satisfied. All construction associated with these modifications has now been completed.

If you have any questions please do not hesitate to contact me or Rachel Mayo.

Sincerely,



Kenneth C. Baldwin

Attachment

Copy to:

Sandy M. Carter  
Brian Ragozzine  
Mark Gauger



Law Offices

BOSTON

PROVIDENCE

HARTFORD

NEW LONDON

STAMFORD

WHITE PLAINS

NEW YORK CITY

ALBANY

SARASOTA

www.rc.com

Centered on Solutions<sup>SM</sup>

June 12, 2012

**Mr. Mark Gauger**  
Verizon Wireless  
99 East River Drive  
East Hartford, Connecticut 06108

**Re: Existing Telecommunications Facility Tower Modification Certification Letter**

**Project:** Verizon ~ Colchester 2  
48 Westchester Road  
Colchester, CT

**Tower Owner:** SBA Communications Corporation  
5900 Broken Sound Parkway NW  
Boca Raton, Florida 33487

**Engineer:** FDH Engineering  
2730 Rowland Ave Raleigh, NC 27615

**Centek Project No.:** 12005.CO8

Dear Mr. Gauger,


We are providing this "Existing Telecommunications Facility Tower Modification Certification Letter" with regard to the antenna upgrade by Verizon Wireless at the above referenced project.

The following are the basis for substantiating compliance with the design documents prepared by FDH Engineering:


- Review of the FDH structural analysis dated 11/12/2012.
- Field observations by Centek personnel of coax installation on 6/11/2012 which determined all coax lines were installed according to the recommendations of the structural analysis report prepared by FDH on 11/12/2012.

The work under this Contract has been reviewed and found, to the Engineer's best knowledge, information and belief, to be completed in general compliance with the documents referenced above.


Sincerely,



Carlo F. Centore, PE  
Principal ~ Structural Engineer



CC: Rachel Mayo, Tim Parks, Jim Smith



# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

[www.ct.gov/csc](http://www.ct.gov/csc)

January 17, 2012

Kenneth C. Baldwin, Esq.  
Robinson & Cole LLP  
280 Trumbull Street  
Hartford, CT 06103

RE: **EM-VER-028-111227**- Cellco Partnership d/b/a Verizon Wireless notice of intent to modify an existing telecommunications facility located at 48 Westchester Road, Colchester, Connecticut.

Dear Attorney Baldwin:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- The coax lines be installed in accordance with the recommendation made in the Structural Analysis Report prepared by FDH Engineering dated December 12, 2011 and stamped by Christopher Murphy; and
- Following the installation of the proposed equipment; Verizon shall provide documentation certifying that the installation complied with the engineer's recommendation.
- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Not less than 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated December 23, 2011. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase

tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,



Linda Roberts  
Executive Director

LR/CDM/laf

c: The Honorable Gregg B. Schuster, First Selectman, Town of Colchester  
Christopher Beauchemin, Town Planner, Town of Colchester  
Hollis Redding, SBA

280 Trumbull Street  
Hartford, CT 06103-3597  
Main (860) 275-8200  
Fax (860) 275-8299  
kbaldwin@rc.com  
Direct (860) 275-8345

December 23, 2011

Linda Roberts  
Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

Re: **Notice of Exempt Modification – Antenna Swap  
48 Westchester Road, Colchester, Connecticut**

Dear Ms. Roberts:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains fifteen (15) wireless telecommunications antennas at the 167-foot level of the existing 180-foot tower at the above-referenced address. The tower is owned by SBA. The Council approved Cellco’s use of the tower in 2000. Cellco now intends to modify its facility by removing all of its existing antennas, replacing them with six (6) model LPA-80080/4CF cellular antennas; six (6) model LPA-171085/8BF PCS antennas; and three (3) model BXA-70063/6CF LTE antennas. Cellco also intends to install three (3) additional coax cables inside the monopole. Attached behind Tab 1 are the specifications for the proposed replacement antennas.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Gregg Schuster, First Selectman of the Town of Colchester. A copy of this letter is also being sent to Margus Properties LLC, the owner of the property on which the tower is located.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the overall height of the existing tower. Cellco’s replacement antennas will be located at the 167-foot level of the existing 180-foot tower.



Law Offices

BOSTON

PROVIDENCE

HARTFORD

NEW LONDON

STAMFORD

WHITE PLAINS

NEW YORK CITY

ALBANY

SARASOTA

www.rc.com

11452195-v1

Linda Roberts  
December 23, 2011  
Page 2

2. The proposed modifications will not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundaries.


3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

4. The operation of the replacement antennas will not increase radio frequency (RF) power density levels at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative power density table for Cellco's modified facility is included behind Tab 2.

Also attached is a Structural Analysis confirming that the tower and foundation can support Cellco's proposed modifications. (See Tab 3).

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kenneth C. Baldwin

Enclosures

Copy to:

Gregg Schuster, Colchester First Selectman  
Margus Properties LLC  
Sandy M. Carter




## BXA-171085-8BF-EDIN-X


Replace "X" with desired electrical downtilt.

X-Pol | FET Panel | 85° | 16.4 dBi

Electrical Characteristics	1710-2170 MHz		
Frequency bands	1710-1880 MHz	1850-1990 MHz	1920-2170 MHz
Polarization	±45°	±45°	±45°
Horizontal beamwidth	88°	85°	80°
Vertical beamwidth	7°	7°	7°
Gain	13.5 dBd / 15.6 dBi	13.9 dBd / 16.0 dBi	14.3 dBd / 16.4 dBi
Electrical downtilt (X)	0, 2, 4		
Impedance	50Ω		
VSWR	≤1.5:1		
First upper sidelobe	< -17 dB		
Front-to-back isolation	> 30 dB		
In-band isolation	> 28 dB		
IM3 (20W carrier)	< -150 dBc		
Input power	300 W		
Lightning protection	Direct Ground		
Connector(s)	2 Ports / EDIN / Female / Bottom		
Operating temperature	-40° to +60° C / -40° to +140° F		
Mechanical Characteristics			
Dimensions Length x Width x Depth	1232 x 154 x 105 mm		48.5 x 6.1 x 4.1 in
Depth with t-brackets	133 mm		5.2 in
Weight without mounting brackets	4.8 kg		10.5 lbs
Survival wind speed	296 km/hr		184 mph
Wind area	Front: 0.19 m <sup>2</sup> Side: 0.14 m <sup>2</sup>	Front: 2.0 ft <sup>2</sup> Side: 1.5 ft <sup>2</sup>	
Wind load @ 161 km/hr (100 mph)	Front: 281 N Side: 223 N	Front: 63 lbf Side: 50 lbf	
Mounting Options	Part Number	Fits Pipe Diameter	Weight
2-Point Mounting Bracket Kit	26799997	50-102 mm 2.0-4.0 in	2.3 kg 5 lbs
2-Point Mounting & Downtilt Bracket Kit	26799999	50-102 mm 2.0-4.0 in	3.6 kg 8 lbs
Concealment Configurations	For concealment configurations, order BXA-171085-8BF-EDIN-X-FP		




**BXA-171085-8BF-EDIN-X**




Horizontal | 1710-1880 MHz

**BXA-171085-8BF-EDIN-0**




0° | Vertical | 1710-1880 MHz

**BXA-171085-8BF-EDIN-X**




Horizontal | 1850-1990 MHz

**BXA-171085-8BF-EDIN-0**




0° | Vertical | 1850-1990 MHz

**BXA-171085-8BF-EDIN-X**



Horizontal | 1920-2170 MHz

**BXA-171085-8BF-EDIN-0**




0° | Vertical | 1920-2170 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

**BXA-171085-8BF-EDIN-X**


X-Pol | FET Panel | 85° | 16.4 dBi

**BXA-171085-8BF-EDIN-2**




2° | Vertical | 1710-1880 MHz

**BXA-171085-8BF-EDIN-4**




4° | Vertical | 1710-1880 MHz

**BXA-171085-8BF-EDIN-2**




2° | Vertical | 1850-1990 MHz

**BXA-171085-8BF-EDIN-4**




4° | Vertical | 1850-1990 MHz

**BXA-171085-8BF-EDIN-2**



2° | Vertical | 1920-2170 MHz

**BXA-171085-8BF-EDIN-4**



4° | Vertical | 1920-2170 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.



## BXA-70063-6CF-EDIN-X

X-Pol | FET Panel | 63° | 14.5 dBd


Replace "X" with desired electrical downtilt.

Antenna is also available with NE connector(s). Replace "EDIN" with "NE" in the model number when ordering.

Electrical Characteristics	696-900 MHz		
Frequency bands	696-806 MHz	806-900 MHz	
Polarization	±45°		
Horizontal beamwidth	65°	63°	
Vertical beamwidth	13°	11°	
Gain	14.0 dBd (16.1 dBi)	14.5 dBd (16.6 dBi)	
Electrical downtilt (X)	0, 2, 3, 4, 5, 6, 8, 10		
Impedance	50Ω		
VSWR	≤1.35:1		
Upper sidelobe suppression (0°)	-18.3 dB	-18.2 dB	
Front-to-back ratio (+/-30°)	-33.4 dB	-36.3 dB	
Null fill	5% (-26.02 dB)		
Isolation between ports	< -25 dB		
Input power with EDIN connectors	500 W		
Input power with NE connectors	300 W		
Lightning protection	Direct Ground		
Connector(s)	2 Ports / EDIN or NE / Female / Center (Back)		
Mechanical Characteristics			
Dimensions Length x Width x Depth	1804 x 285 x 132 mm	71.0 x 11.2 x 5.2 in	
Depth with z-brackets	172 mm	6.8 in	
Weight without mounting brackets	7.9 kg	17 lbs	
Survival wind speed	> 201 km/hr	> 125 mph	
Wind area	Front: 0.51 m <sup>2</sup> Side: 0.24 m <sup>2</sup>	Front: 5.5 ft <sup>2</sup> Side: 2.6 ft <sup>2</sup>	
Wind load @ 161 km/hr (100 mph)	Front: 759 N Side: 391 N	Front: 169 lbf Side: 89 lbf	
Mounting Options	Part Number	Fits Pipe Diameter	Weight
3-Point Mounting & Downtilt Bracket Kit	36210008	40-115 mm 1.57-4.5 in	6.9 kg 15.2 lbs
Concealment Configurations	For concealment configurations, order BXA-70063-6CF-EDIN-X-FP		




**BXA-70063-6CF-EDIN-X**




Horizontal | 750 MHz

**BXA-70063-6CF-EDIN-0**




0° | Vertical | 750 MHz


**BXA-70063-6CF-EDIN-2**




2° | Vertical | 750 MHz



Horizontal | 850 MHz



0° | Vertical | 850 MHz




2° | Vertical | 850 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

**BXA-70063-6CF-EDIN-X**


X-Pol | FET Panel | 63° | 14.5 dBd

**BXA-70063-6CF-EDIN-3**




3° | Vertical | 750 MHz

**BXA-70063-6CF-EDIN-4**




4° | Vertical | 750 MHz


**BXA-70063-6CF-EDIN-5**




5° | Vertical | 750 MHz



3° | Vertical | 850 MHz




4° | Vertical | 850 MHz




5° | Vertical | 850 MHz

**BXA-70063-6CF-EDIN-6**




6° | Vertical | 750 MHz

**BXA-70063-6CF-EDIN-8**




8° | Vertical | 750 MHz


**BXA-70063-6CF-EDIN-10**




10° | Vertical | 750 MHz



6° | Vertical | 850 MHz



8° | Vertical | 850 MHz



10° | Vertical | 850 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.



## LPA-80080-4CF-EDIN-X

V-Pol | Log Periodic | 80° | 12.5 dBd

Replace "X" with desired electrical downtilt.

Antenna is also available with NE connector(s). Replace "EDIN" with "NE" in the model number when ordering.

Electrical Characteristics		
Frequency bands	806-960 MHz	
Polarization	Vertical	
Horizontal beamwidth	80°	
Vertical beamwidth	15°	
Gain	12.5 dBd (14.6 dBi)	
Electrical downtilt (X)	0, 2, 4, 5, 6, 8, 10, 12, 14	
Impedance	50Ω	
VSWR	≤1.4:1	
Upper sidelobe suppression (0°)	-14.2 dB	
Front-to-back ratio (+/-30°)	-34.7 dB	
Null fill	15% (-16.48 dB)	
Input power	500 W	
Lightning protection	Direct Ground	
Connector(s)	1 Port / EDIN or NE / Female / Center (Back)	
Mechanical Characteristics		
Dimensions Length x Width x Depth	1200 x 140 x 335 mm      47.2 x 5.5 x 13.2 in	
Depth of antenna with z-bracket	375 mm      14.8 in	
Weight without mounting brackets	5.4 kg      12 lbs	
Survival wind speed	> 201 km/hr      > 125 mph	
Wind area	Front: 0.17 m <sup>2</sup> Side: 0.40 m <sup>2</sup> Front: 1.8 ft <sup>2</sup> Side: 4.3 ft <sup>2</sup>	
Wind load @ 161 km/hr (100 mph)	Front: 254 N    Side: 574 N      Front: 57 lbf    Side: 129 lbf	
Mounting Options		
Part Number	Fits Pipe Diameter	Weight
2-Point Mounting & Downtilt Bracket Kit (0-20°)	21699999	50-102 mm    2.0-4.0 in      5.4 kg    12 lbs
Lock-Down Brace	If the lock-down brace is used, the maximum diameter of the mounting pipe is 88.9 mm or 3.5 in.	



Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.





FDH Engineering, Inc., 2730 Rowland Rd. Raleigh, NC 27615, Ph. 919.755.1012, Fax 919.755.1031

**Structural Analysis for  
SBA Network Services, Inc.**

**180' Monopole Tower**

**SBA Site Name: Colchester  
SBA Site ID: CT02218-S  
Verizon Site Name: Colchester 2**

**FDH Project Number 11-11220E S1 (R1)**

**Analysis Results**

Tower Components	76.0%	Sufficient
Foundation	78.5%	Sufficient

Prepared By:

Daniel Chang, EI  
Project Engineer

Reviewed By:

Christopher M Murphy, PE  
President  
CT PE License No. 25842

FDH Engineering, Inc.  
2730 Rowland Rd.  
Raleigh, NC 27615  
(919) 755-1012  
info@fdh-inc.com



December 12, 2011

*Prepared pursuant to TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures*

**TABLE OF CONTENTS**

EXECUTIVE SUMMARY .....3  
    Conclusions.....3  
    Recommendation .....3  
APPURTENANCE LISTING .....4  
RESULTS .....5  
GENERAL COMMENTS .....6  
LIMITATIONS.....6  
APPENDIX .....7

## EXECUTIVE SUMMARY

At the request of SBA Network Services, Inc., FDH Engineering, Inc. performed a structural analysis of the monopole located in Colchester, CT to determine whether the tower is structurally adequate to support both the existing and proposed loads pursuant to the *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA-222-F*. Information pertaining to the existing/proposed antenna loading, current tower geometry, geotechnical data, foundation dimensions, and member sizes was obtained from:

- Valmont Microflex Co., Inc. (Order No. 19487-99) Communication Pole Record Drawings dated November 3, 1999
- SBA Network Services, Inc.

The *basic design wind speed* per the *TIA/EIA-222-F* standards is 85 mph without ice and 38 mph with 3/4" radial ice. Ice is considered to increase in thickness with height.

## Conclusions

With the existing and proposed antennas from Verizon in place at 167 ft, the tower meets the requirements of the *TIA/EIA-222-F* standards provided the **Recommendation** listed below is satisfied. Furthermore, provided the foundation was designed and constructed to support the original design reactions (see Valmont Order No. 19487-99), the foundation should have the necessary capacity to support both the proposed and existing loading. For a more detailed description of the analysis of the tower, see the **Results** section of this report.

Our structural analysis has been performed assuming all information provided to FDH Engineering, Inc. is accurate (i.e., the steel data, tower layout, existing antenna loading, and proposed antenna loading) and that the tower has been properly erected and maintained per the original design drawings.

## Recommendation

To ensure the requirements of the *TIA/EIA-222-F* standards are met with the existing and proposed loading in place, we have the following recommendation:

1. The proposed coax should be installed inside the pole's shaft.

**APPURTENANCE LISTING**

The proposed and existing antennas with their corresponding cables/coax lines are shown in **Table 1**. *If the actual layout determined in the field deviates from the layout, FDH Engineering, Inc. should be contacted to perform a revised analysis.*

**Table 1 - Appurtenance Loading**

**Existing Loading:**

Antenna Elevation (ft)	Description	Coax and Lines <sup>1</sup>	Carrier	Mount Elevation (ft)	Mount Type
177	(3) EMS RR90-17-02DP w/ Mount Pipe	(6) 1 5/8	Omnipoint	177	(1) Low Profile Platform
167	(6) Allgon 7129.16 w/ Mount Pipe (3) Allgon 7125.18 w/ Mount Pipe (6) Decibel DB948F85T2E-M w/ Mount Pipe	(15) 1 5/8	Verizon	167	(1) Platform Mount w/ Handrails
157	(6) Powerwave 7770 w/ Mount Pipe (6) Powerwave LGP21401 TMAs (6) Diplexers	(12) 1 5/8	AT&T	157	(1) Low Profile Platform

<sup>1</sup> Coax installed the monopole's shaft unless otherwise noted.

**Proposed Loading:**

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
167	(3) Antel BXA-70063/6CF w/ Mount Pipe (6) Antel LPA-80080/4CF w/ Mount Pipe (6) Antel LPA-171080/8CF w/ Mount Pipe	(18) 1 5/8	Verizon	167	(1) Platform Mount w/ Handrails



**RESULTS**

The following yield strength of steel for individual members was used for analysis:

**Table 2 - Material Strength**

Member Type	Yield Strength
Tower Shaft Sections	65 ksi
Base Plate	60 ksi
Anchor Bolts	75 ksi

**Table 3** displays the summary of the ratio (as a percentage) of force in the member to their capacities. Values greater than 100% indicate locations where the maximum force in the member exceeds its capacity. *Note: Capacities up to 100% are considered acceptable.* **Table 4** displays the maximum foundation reactions.

If the assumptions outlined in this report differ from actual field conditions, FDH Engineering, Inc. should be contacted to perform a revised analysis. Furthermore, as no information pertaining to the allowable twist and sway requirements for the existing or proposed appurtenances was provided, deflection and rotation were not taken into consideration when performing this analysis.

See the **Appendix** for detailed modeling information

**Table 3 - Summary of Working Percentage of Structural Components**

Section No.	Elevation ft	Component Type	Size	% Capacity*	Pass Fail
L1	180.09 - 127.09	Pole	TP35.769x24.912x0.219	60.6	Pass
L2	127.09 - 92.92	Pole	TP42.339x34.2555x0.313	65.4	Pass
L3	92.92 - 45.92	Pole	TP51.345x40.4826x0.375	74.0	Pass
L4	45.92 - 0	Pole	TP60x49.144x0.438	76.0	Pass
		Anchor Bolts	(20) 2.25" Ø on 68.62" Ø BC	69.9	Pass
		Base Plate	74.62" Ø x 2.75" thk. PL	52.1	Pass

\* Capacities include 1/3 allowable stress increase per TIA/EIA-222-F.

**Table 4 - Maximum Base Reactions**

Base Reactions	Current Analysis (TIA/EIA-222-F)	Original Design (TIA/EIA-222-F)
Axial	44 k	47 k
Shear	35 k	39 k
Moment	3,958 k-ft	5,045 k-ft

## GENERAL COMMENTS


This engineering analysis is based upon the theoretical capacity of the structure. It is not a condition assessment of the tower and its foundation. It is the responsibility of SBA Network Services, Inc. to verify that the tower modeled and analyzed is the correct structure (with accurate antenna loading information) modeled. If there are substantial modifications to be made or the assumptions made in this analysis are not accurate, FDH Engineering, Inc. should be notified immediately to perform a revised analysis.

## LIMITATIONS

All opinions and conclusions are considered accurate to a reasonable degree of engineering certainty based upon the evidence available at the time of this report. All opinions and conclusions are subject to revision based upon receipt of new or additional/updated information. All services are provided exercising a level of care and diligence equivalent to the standard and care of our profession. No other warranty or guarantee, expressed or implied, is offered. Our services are confidential in nature and we will not release this report to any other party without the client's consent. The use of this engineering work is limited to the express purpose for which it was commissioned and it may not be reused, copied, or distributed for any other purpose without the written consent of FDH Engineering, Inc.

## APPENDIX

Section	1	2	3	4
Length (ft)	53.00	39.42	53.00	53.00
Number of Sides	16	16	16	16
Thickness (in)	0.2190	0.3130	0.3750	0.4380
Socket Length (ft)	5.25	6.00	7.08	49.1440
Top Dia (in)	24.9120	34.2555	40.4826	60.0000
Bot Dia (in)	35.7690	42.3390	51.3450	
Grade		A572-65		
Weight (K)	3.8	5.1	9.8	13.6



**DESIGNED APPURTENANCE LOADING**


TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod	180.09	(2) LPA-171080/8CF w/ Mount Pipe	167
RR90-17-02DP w/Mount Pipe	177	(2) LPA-171080/8CF w/ Mount Pipe	167
RR90-17-02DP w/Mount Pipe	177	(2) LPA-171080/8CF w/ Mount Pipe	167
RR90-17-02DP w/Mount Pipe	177	Platform Mount w/ Handrails	167
(3) Pipe Mount	177	(2) Powerwave 7770 w/ Mount Pipe	157
(3) Pipe Mount	177	(2) Powerwave 7770 w/ Mount Pipe	157
(3) Pipe Mount	177	(2) Powerwave 7770 w/ Mount Pipe	157
Low Profile Platform	177	(2) TMA - Powerwave LGP21401	157
BXA-70063/6CF W/Mount Pipe	167	(2) TMA - Powerwave LGP21401	157
BXA-70063/6CF W/Mount Pipe	167	(2) TMA - Powerwave LGP21401	157
BXA-70063/6CF W/Mount Pipe	167	(2) Diplexer	157
(2) LPA-80080/4CF W/Mount Pipe	167	(2) Diplexer	157
(2) LPA-80080/4CF W/Mount Pipe	167	(2) Diplexer	157
(2) LPA-80080/4CF W/Mount Pipe	167	Low Profile Platform	157

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower is located in New London County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 76%



<p><b>FDH Engineering, Inc.</b> 2730 Rowland Road, Suite 100 Raleigh, NC 27615 Phone: (919) 755-1012 FAX: (919) 755-1031</p>	<b>Job: Colchester, CT02218-S</b>		
	<b>Project: 11-11220E S1 (R1)</b>		
	Client: SBA	Drawn by: Daniel Chang	App'd:
	Code: TIA/EIA-222-F	Date: 12/12/11	Scale: NTS
Tower Analysis	Path:	Dwg No. E-1	