



10 Industrial Ave, Suite 3
Mahwah, NJ 07430
Phone: (908)447-4716
Kyle Richers
Real Estate Consultant

February 20th, 2015

Hand Delivered

Ms. Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

CC to Property Owner
Cromwell Fire District
1 West Street, Cromwell, CT 06416

RE: Sprint Spectrum L.P. notice of intent to modify an existing telecommunications facility located at 179 Shunpike Road, Cromwell, CT 06416. Known to Sprint Spectrum L.P. as site CT60XC931.

Dear Ms. Bachman:

In order to accommodate technological changes, implement Code Division Multiple Access (“CDMA”) and/or Long Term Evolution (“LTE”) capabilities, and enhance system performance in the state of Connecticut, Sprint Spectrum L.P. plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and its attachments is being sent to the chief elected official of the municipality in which affected cell site is located.

CDMA employs Spread-Spectrum technology and special coding scheme to allow multiple users to be multiplexed over the same physical channel.

LTE is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower to accommodate the revised antenna configuration.

The changes to the facility do not constitute modification as defined Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for the R.C.S.A. Section 16-50j-72(b)(2).

1. The height of the overall structure will not be affected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound.
3. The proposed changes will not increase the noise level at the existing facility by 6 decibels or more.
4. Radio Frequency power density may increase due to the use of one or more CDMA transmissions. Moreover, LTE will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons Sprint Spectrum L.P. respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (908)-447-4716 or email krichers@transcendwireless.com with questions concerning this matter. Thank you for your consideration.

Sincerely,

Kyle Richers
Real Estate Consultant

RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT60XC931

Cromwell- Rt. 372

179 Shunpike Road
Cromwell, CT 06416

February 19, 2015

EBI Project Number: 62151104

February 19, 2015

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT60XC931 - Cromwell- Rt. 372

Site Total: 91.01% - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at **179 Shunpike Road, Cromwell, CT**, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band (850 MHz Band) is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at **179 Shunpike Road, Cromwell, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 4 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation.
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXV9TM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXV9TM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **170 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT60XC931 - Cromwell- Rt. 372
Site Address	179 Shunpike Road, Cromwell, CT, 06416
Site Type	Self Support Tower

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	170	164	1/2 "	0.5	0	277.39	0.37%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	170	164	1/2 "	0.5	0	39.00	0.09%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	170	164	1/2 "	0.5	0	138.69	0.33%
Sector total Power Density Value:																0.79%

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	170	164	1/2 "	0.5	0	277.39	0.37%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	170	164	1/2 "	0.5	0	39.00	0.09%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	170	164	1/2 "	0.5	0	138.69	0.33%
Sector total Power Density Value:																0.79%

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	5.9	170	164	1/2 "	0.5	0	277.39	0.37%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	170	164	1/2 "	0.5	0	39.00	0.09%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	170	164	1/2 "	0.5	0	138.69	0.33%
Sector total Power Density Value:																0.79%

Site Composite MPE %	
Carrier	MPE %
Sprint	2.37%
AT&T	24.31%
T-Mobile	2.85%
Cromwell Police	2.13%
Cromwell Fire	2.18%
Cromwell Fire Alarm	3.63%
Clearwire	1.04%
Verizon Wireless	52.50%
Total Site MPE %	91.01%

Summary

All calculations performed for this analysis yielded results that were within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **2.37% (0.79% from sector 1, 0.79% from sector 2 and 0.79% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **91.01%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803

DETAILED STRUCTURAL ANALYSIS AND REINFORCEMENT OF AN EXISTING 170' SELF SUPPORTING LATTICE TOWER AND FOUNDATION FOR PROPOSED ANTENNA ARRANGEMENTS

Site ID: (Sprint) CT60XC931
 (T-Mobile) CT11059C
Site Name: (Sprint) Cromwell - Route 372
 (T-Mobile) Rocky Hill / I-91 / X23
Site Address: 179 Shunpike Road
 Cromwell, CT

prepared for



Transcend Wireless
10 Industrial Ave.
Suite 3
Mahwah, NJ. 07430



EBI Consulting
21 B Street
Burlington, MA 01803

prepared by



URS CORPORATION
500 ENTERPRISE DRIVE, SUITE 3B
ROCKY HILL, CT 06067
TEL. 860-529-8882

36931260.00000
TWS-027 Rev. 1

September 23, 2014

TABLE OF CONTENTS

- 1. EXECUTIVE SUMMARY**
- 2. INTRODUCTION**
- 3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS**
- 4. FINDINGS AND EVALUATION**
- 5. CONCLUSIONS AND RECOMMENDATIONS**
- 6. DRAWINGS AND DATA**
 - **TOWER REINFORCEMENT DRAWING SK-1**
 - **TNX TOWER INPUT / OUTPUT SUMMARY**
 - **TNX TOWER FEEDLINE DISTRIBUTION**
 - **TNX TOWER FEEDLINE PLAN**
 - **TNX TOWER DETAILED OUTPUT**
 - **ANCHOR BOLT ANALYSIS**
 - **FOUNDATION ANALYSIS**

1. EXECUTIVE SUMMARY

This report summarizes the structural analysis of the existing 170' self supporting lattice tower located at 179 Shunpike Road in Cromwell, Connecticut. The analysis was conducted in accordance with the 2005 Connecticut State Building Code which requires a three second gust wind speed of 100 mph which converts to an 80 mph fastest mile per 2003 IBC (Table 1609.3.1) and the TIA/EIA-222-F standard for a wind velocity of 85 mph (fastest mile). The wind speed from the Connecticut State Building Code governs the design at 85 mph (fastest mile) and 74 mph (fastest mile) concurrent with 1/2" ice. The antenna loading considered in the analysis consists of all existing and proposed antennas, transmission lines, and ancillary items as outlined in the Introduction Section of this report.

The proposed Sprint and T-Mobile antenna modifications are listed below:

Proposed Antenna and Mount	Carrier	Antenna Center Elevation
Install:		
(3) RFS APXV9TM14-ALU-I20 Panel Antennas	Sprint (Proposed)	@ 170'
(3) TD-RRH8x20-25 RRH Units		
(1) 1 1/4" Hybrid Cable		
(27) 8' Jumper Cables		
(3) 8' AISG Cables		
Install:		
(3) Commscope LNX-6515DS-VTM Panel Antennas	T-Mobile (Proposed)	@ 125'
(3) Ericsson RRUS_11 RRH Unit		
(3) 6' Antenna Pipe Mount		

The results of an initial analysis indicated the tower structure did not have sufficient capacity to support the proposed loadings without modification. The required modifications are shown in SK-1. **Once the modifications are performed, the tower, anchor bolts, and foundation are considered structurally adequate with the wind loading classification specified above and all the existing and proposed antenna loading. No installation of new antennas or equipment shall occur until the modifications have been completed.**

This analysis is based on:

- 1) The tower structure's theoretical capacity, not including any assessment of the condition of the tower.
- 2) Tower geometry, structural member sizes, and Foundation information taken from a tower report prepared by PiROD Inc., ENG. File No. A-116398, dated November 18, 1999.
- 3) Foundation modification drawings prepared by Tectonic, dated May 5, 2004.
- 4) Structural analysis and reinforcement performed by URS Corp. on behalf of Sprint and T-Mobile, project number 36922436, signed and sealed on September 9, 2013.
- 5) Structural analysis performed by URS Corp. on behalf of Verizon Wireless, project number VZ5-178 / 36917427, signed and sealed on August 12, 2014.
- 6) Structural analysis performed by URS Corp., on behalf of Sprint, project number TWS-027 / 36931260, signed and sealed on August 22, 2014.
- 7) T-Mobile RFDS dated July 17, 2014.
- 8) Previous structural analysis performed by URS Corporation, on behalf of T-Mobile, project number EBI-002 / 36931289, signed and sealed August 29, 2014.
- 9) Proposed additional antenna and mount configuration as specified in Section 2 of this report.


1. EXECUTIVE SUMMARY (continued)

This report is only valid as per the assumptions and data utilized in this report for antenna inventory, mounts and associated cables. The user of this report shall field verify the assumption of the antenna and mount configuration as well as the physical condition of the tower and connections. Notify the engineer in writing immediately if any of the information in this report is found to be other than specified.


If you should have any questions, please call.

Sincerely,

URS Corporation



Richard A. Sambor, P.E.
Senior Structural Engineer
RAS/mcd



2. INTRODUCTION

The subject tower is located at 179 Shunpike Road in Cromwell, Connecticut. The structure is a 170' self supporting lattice tower designed and manufactured by PiROD Inc.

The current inventory with proposed modification is summarized in the table below:

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) Tx Rx 101-90-08 antenna	Town (existing)	15' Mast pipe on 9 Arm Halo Mount	183'	(1) 7/8"
(1) 8 Bay Dipole (3" dia x 20')	Town (existing)	9 Arm Halo Mount	178'	(1) 7/8"
(1) 2 1/2" dia x 20' Whip	Town (existing)	9 Arm Halo Mount	178'	(1) 1 1/2"
(3) 2 1/2" dia x 15' Whip	Town (existing)	9 Arm Halo Mount	175'	(3) 7/8"
1 1/2" dia x 12' Whip	Town (existing)	9 Arm Halo Mount	174'	(1) 7/8"
(3) RFS APXV9TM14-ALU-I20 Panel Antennas (3) TD-RRH8x20-25 RRH Units	Sprint (Proposed)	See Mount Below	170'	(1) 1 1/4" Hybrid Cable (27) 8' Jumper Cables (3) 8' AISG Cables
(3) RFS APXVSP18-C-A20 Antennas (3) 1900 MHz RRH Units (3) 800 MHz RRH Units (3) 800 MHz Filters	Sprint (existing)	9 Arm Halo Mount	170'	(3) RFS HB114-1-0804-MSF Hybrid Cables
(1) Radiowaves HPD2-4.7 w/ Radome (1) Cambium PTP49600 Antenna	CPD (existing)	9 Arm Halo Mount	168'	(1) WB3176A – Copper Clad Outdoor Cable (2) 4' long 1/2" Jumper Cables
(1) SU-RA-HP-2.4 (1' x 1' Antenna)	Town (existing)	9 Arm Halo Mount	168'	(1) 3/8"
(3) APXV18-206517S	Unknown (existing)	Leg Mount	159'-6"	(6) 1 5/8"
(1) Sinclair SC420-HF1LDF Omni	CPD (existing)	Pipe mount	158'-6"	(1) 1 5/8" Low Density Foam Cable
(2) 3" dia x 20' Whip	Town (existing)	20' Platform	144'	(2) 7/8"
(1) 2 1/2" x 20' Whip	Town (existing)	20' Platform	144'	(1) 1/2"
2" dia x 15' Whip	Town (existing)	20' Platform	141'	(1) 1/2"
(1) 1.5" dia x 10' Whip	Town (existing)	20' Platform	139'	(1) 1/2"
(1) 3.5" dia x 9' Whip	Town (existing)	20' Platform	138'-6"	---
(3) Argus LLPX310R antennas (3) Samsung Remote Radio Heads U-RAS	Clearwire (existing)	20' Platform	134'	(6) CAT 5 cable

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(3) Andrew VHLP2.5 dish (2.5' dia.) (1) Andrew VHLP2 dish (2' dia.) (Gamma Sector)	Clearwire (existing)	20' Platform	134'	(4) 1/2"
(3) Commscope LNX-6515DS-VTM Panel Antennas (3) Ericsson RRUS_11 RRH Unit	T-Mobile (Proposed)	(3) Antenna Pipes attached with below	125'	See Below Cables
(6) Ericsson AIR21 B4A B2P Antennas (3) Twin PCS TMAs	T-Mobile (existing)	(3) Existing T-Frames	125'	(12) 1 5/8" (1) 1-5/8" Hybrid Cable
(6) Powerwave 7770 (12) TMA's (3) KMW AM-X-CD-16-65-00T-RET (6) RRU (1) Surge Suppressor	AT&T (existing)	(3) T-Frames	115'	(12) 1 5/8" (3) Optic Fiber & (6) DC Cables (Located within 3" dia Flex Conduit)
(1) HBX-6517DS-VTM_04DT_2110 Panel Antenna (Alpha Sector) (2) HBX-6517DS-VTM_02DT_2110 Panel Antennas (Beta & Gamma Sectors) (3) AWS RRH Units (1) DB-T1-6Z-8AB-0Z Distribution Box (1) LNX-6514DS-VTM_03DT_0850 Panel Antenna (Alpha Sector) (1) LNX-6514DS-VTM_04DT_0850 Panel Antenna (Beta Sector) (1) LNX-6514DS-VTM_05DT_0850 Panel Antenna (Gamma Sector) (2) SWCP 2x5514 antennas (Alpha & Gamma Sector) (1) BXA-70063-6CF-2 antenna (Beta Sector) (3) BXA-171063-12BF_2 antennas (6) FD9R6004/2C-3L Diplexers	Verizon (existing)	(3) T-Frames (PiROD part #800093)	101'	(1) 1 5/8" F.O Cable (12) 1 5/8"
(1) 3" x 2" x 22" Panel (1) TMA	AT&T (existing)	Pipe Mount	87'	(2) CAT 5

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) 3' Dish (1) TMA	AT&T (existing)	3' Stand-off	83'	(2) CAT 5
(1) 3" x 2" x 22" Panel (1) TMA	AT&T (existing)	3' Stand-off	80'	(2) CAT 5
(1) Camera	Unknown (existing)	Leg Mounted	30'	(2) 1/2" (estimated from photographs)
(1) 3' Yagi	Unknown (existing)	Leg Mounted	24'	(1) 1/2"

This structural analysis of the communications tower was performed by URS Corporation (URS) for Sprint and T-Mobile. The purpose of this analysis was to investigate the structural integrity of the reinforced tower with its existing and proposed antenna loads. This analysis was conducted to evaluate stress on the tower and the effect of forces to the foundation of the tower resulting from existing and proposed antenna arrangements.

3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS

The structural analysis was done in accordance with the Connecticut State Building Code, TIA/EIA-222-F - Structural Standard for Steel Antenna Towers and Antenna Supporting Structures, and the American Institute of Steel Construction (AISC) Manual of Steel Construction – Allowable Stress Design (ASD).

The analysis was conducted using TNX Tower 6.1.3.1. Two load conditions were evaluated as shown below which were compared to allowable stresses according to AISC and TIA/EIA.

Basic Wind Speed:

- Middlesex County; $v = 85$ mph (fastest mile) [Section 16 of TIA/EIA-222-F-1996]
- Cromwell; $v = 100$ mph (3 second gust) equivalent to 80 mph (fastest mile) [Appendix K, 2005 Connecticut State Building Code Supplement]

Loading Cases:

Load Condition 1 = 85 mph (fastest mile) Wind Load (without ice) + Tower Dead Load
 Load Condition 2 = 74 mph (fastest mile) Wind Load (with ice) + Ice Load + Tower Dead Load

Please note that wind pressure is a function of velocity squared. Under Load Condition 2, a 25 percent reduction in wind pressure is allowed by code to account for the unlikelihood of the full wind pressure and ice load occurring at the same time. The same results may be achieved by utilizing a lower wind pressure without taking the 25 percent reduction, as shown above.

The TIA/EIA standard permits a one-third increase in allowable stresses for towers and monopoles less than 700 feet tall. For the purposes of this analysis, in computing the load capacity the allowable stresses of the tower members were increased by one-third.

4. FINDINGS AND EVALUATION

The combined axial and bending stresses on the tower structure were evaluated to compare with the allowable stress in accordance with AISC. The results of an initial analysis indicated that the tower structure required modification. The required modifications are shown in SK-1 located in Section 6 of this report. This analysis indicated that once these modifications are performed, the tower, anchor bolts and foundation are considered structurally adequate with the wind load classification specified above and the proposed antenna loading. The table below summarizes the critical members for each tower component.

TABLE 1: Tower Component Stress vs. Capacity Summary:

Component/ (Section No.)	Existing Component Size	Controlling Component/Elevation	Percent Capacity	Pass/Fail
Tower Leg (T5)	PiROD Truss Leg	Compression 90'-100'	92.4 %	Pass
Diagonal (T7)	L3x3x3/8	Compression 60'-80'	88.5 %	Pass
Top Girt (T1)	7/8" SR	Compression 150'-170'	9.5 %	Pass
Bottom Girt (T1)	7/8" SR	Compression 150'-170'	4.4 %	Pass
Mid Girt (T4)	L3x3x3/16	Compression 100'-120'	34.8 %	Pass
Bolt Checks				
Tower Bolts	(1) 1" A325N Bolt / 140'	Member Bearing on Bolt	83.5 %	Pass
Anchor Bolts	(6) 1-1/4"	Tension	77.0 %	Pass

TABLE 2: Foundation Summary

Foundation	Component	Stress (% capacity/FOS)	Pass/Fail	Comments:
Previously Modified Drilled Concrete Caisson	Uplift	89.9 %/2.22	Pass	Min. F.O.S of 2.0 req'd per IBC 2003 Section 3108.4.2

5. CONCLUSIONS AND RECOMMENDATIONS

The results of an initial analysis indicated the tower structure did not have sufficient capacity to support the proposed loadings without modification. The required modifications are shown in SK-1. **Once the modifications are performed, the tower, anchor bolts, and foundation are considered structurally adequate with the wind loading classification specified above and all the existing and proposed antenna loading. No installation of new antennas or equipment shall occur until the modification have been completed.**

Limitations/Assumptions:

This report is based on the following:

1. Tower inventory as listed in this report.
2. Tower is properly installed and maintained.
3. All members are as specified in the original design documents and are in good condition.
4. All required members are in place.
5. All bolts are in place and are properly tightened.
6. Tower is in plumb condition.
7. All member protective coatings are in good condition.
8. All tower members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
9. Foundations were properly constructed to support original design loads as specified in the original design documents.
10. All coaxial cable is installed as specified in Section 6 of this report.

URS is not responsible for any changes/alterations completed prior to or hereafter in which URS is not or was not directly involved. Changes/alterations include but are not limited to:

- A. Adding antennas
- B. Removing/replacing antennas
- C. Adding coaxial cables

URS hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations, and conclusions are based upon information contained and set forth herein. If you are aware of any information which conflicts with that which is contained herein, or you are aware of any defects arising from original design, material, fabrication, or erection deficiencies, you should disregard this report and immediately contact URS. URS disclaims all liability for any representation, recommendation, or conclusion not expressly stated herein.

Ongoing and Periodic Inspection and Maintenance:

After the Contractor has successfully completed the installation and the work has been accepted, the owner will be responsible for the ongoing and periodic inspection and maintenance of the tower.

The owner shall refer to TIA/EIA-222-F for recommendations for maintenance and inspection. The frequency of the inspection and maintenance intervals is to be determined by the owner based upon actual site and environmental conditions. It is recommended that a complete and thorough inspection of the entire tower structural system be performed at least yearly and more frequently as conditions warrant. According to TIA/EIA-222-F section 14.1, Note 1: It is recommended that the structure be inspected after severe wind and/or ice storms or other extreme loading conditions.

6. DRAWINGS AND DATA

TOWER REINFORCEMENT DRAWING SK-1

STRUCTURAL NOTES

TOWER DESIGN CRITERIA:
THIS TOWER IS DESIGNED AND REINFORCED IN ACCORDANCE WITH THE 2005 CONNECTICUT STATE BUILDING CODE, THE
TOWER IS DESIGNED FOR 90 MPH (FASTEST MILE) WIND SPEED CONCURRENT WITH 1/2" RADIAL ICE. ALLOWABLE STEEL
STRESSES PER AISC ASD 9TH EDITION.

MATERIAL SPECIFICATIONS FOR REINFORCEMENT OF TOWER:
STRUCTURAL STEEL PLATES, ANGLES ASTM A36
SOLID ROUND (S.R.) ASTM A572 GRADE 50
PIPE COLUMNS ASTM A53 GRADE B
TUBE COLUMNS ASTM A500
WELDING ELECTRODES E70 (UNLESS NOTED OTHERWISE)
F=46.KSI

SHOP AND ERECTION DRAWINGS SHALL BE SUBMITTED FOR ALL STRUCTURAL STEEL WORK IN ACCORDANCE
WITH THE CONTRACT DOCUMENTS. SUBMIT 6 SETS OF PRINTS TO THE ARCHITECT FOR REVIEW.
THE OMISSION OF ANY MATERIAL THAT WAS SHOWN ON THE CONTRACT DRAWINGS SHALL NOT RELIEVE
THE CONTRACTOR OF PROVIDING SAME.

STRUCTURAL STEEL SHALL CONFORM TO THE CURRENT "AISC SPECIFICATION FOR THE DESIGN, FABRICATION,
AND ERECTION OF STEEL FOR BUILDINGS", AND THE "AISC CODE OF STANDARD PRACTICE FOR
STEEL BUILDINGS AND BRIDGES".

ALL WELDING SHALL BE DONE BY A CERTIFIED WELDER IN ACCORDANCE WITH A.W.S. STANDARDS.
CONNECTIONS SHALL CONFORM TO ALL REQUIREMENTS OF THE "AISC SPECIFICATION FOR THE DESIGN,
FABRICATION, AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS", LATEST EDITION, AND THE "SPECIFICATION
FOR STRUCTURAL STEEL JOINTS USING ASTM A325 OR A490 BOLTS".

BOLT HOLES SHALL BE PUNCHED OR DRILLED. FLAME CUT HOLES ARE NOT ACCEPTABLE.
ALL A-325/A490 BOLTS ARE TO BE TIGHTENED TO A SNUG TIGHT CONDITION AS DEFINED BY AISC SPECIFICATION.
USE LOCK NUT OR LOCKING DEVICE TO MATCH EXISTING.

ALL WELDING SHALL BE DONE USING E70XX ELECTRODES AND WELDING SHALL CONFORM TO AISC AND AWS D1.1
WHERE FILLET WELD SIZES ARE NOT SHOWN, PROVIDE THE MINIMUM SIZE PER TABLE J2.4 IN THE AISC
"AISC STEEL CONSTRUCTION", 9TH EDITION. AT THE COMPLETION ALL WELDING, ALL DAMAGE TO GALVANIZED
COATING SHALL BE REPAIRED.

USE PRECAUTIONS & PROCEDURES PER AWS D1.1 WHEN WELDING GALVANIZED METALS.
TOUCH-UP ALL DAMAGED GALVANIZED STEEL WITH APPROVED COLD ZINC "GALVANOX", "DRY GALV", ZINC-IT,
OR APPROVED EQUIVALENT ACCORDING WITH MANUFACTURER'S GUIDELINES. TOUCH-UP DAMAGED NON
GALVANIZED STEEL WITH SAME PAINT APPLIED IN SHOP OR FIELD.

ALL STEEL WORK SHALL BE GALVANIZED AND IN ACCORDANCE WITH THE SPECIFICATION ASTM A123 UNLESS
OTHERWISE NOTED. (AFTER FABRICATION)

COMMENCEMENT OF STRUCTURAL STEEL WORK WITHOUT NOTIFYING THE ENGINEER OF ANY DISCREPANCIES WILL
BE CONSIDERED ACCEPTANCE OF PRECEDING WORK.

SPECIAL INSPECTIONS REQUIRED PER THE 2005 CONNECTICUT STATE BUILDING CODE FOR STRUCTURAL STEEL WORK.
INSPECTION AND TESTING OF ALL WELDING AND HIGH STRENGTH BOLTING SHALL BE PERFORMED BY AN INDEPENDENT
TESTING LABORATORY. BE PAID BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. THE INSPECTOR SHALL
OBSERVE INSTALLATION OF BOLTS AND TEST NOT LESS THAN 20% OF THE BOLTS AND NOT LESS THAN TWO BOLTS,
SELECTED AT RANDOM, IN EACH CONNECTION.

FOUR COPIES OF ALL INSPECTION TEST REPORTS SHALL BE SUBMITTED TO THE ENGINEER WITHIN TEN (10) WORKING
DAYS OF THE DATE OF INSPECTION.


REINFORCEMENT NOTES:
EXISTING DIMENSIONS OF THE TOWER STRUCTURE WERE OBTAINED FROM MANUFACTURER'S ORIGINAL DESIGN DOCUMENTS.
PREPARED BY PIRD INC., ENG. FILE NO. A-116398, DATED NOVEMBER 18, 1999 AND ARE NOT GUARANTEED.
CONTRACTOR SHALL TAKE FIELD MEASUREMENTS NECESSARY TO ASSURE PROPER FIT OF ALL FINISHED WORK.

CONTRACTOR SHALL VISIT THE SITE PRIOR TO THE START OF WORK WITH SUFFICIENT RIGGING EQUIPMENT AND PERSONNEL
TO OBTAIN DETAILED FABRICATION MEASUREMENTS OF EXISTING TOWER STEEL MEMBERS TO BE REPLACED.
TOWER REINFORCING SHALL BE CONDUCTED BY FIELD CREWS EXPERIENCED IN THE ASSEMBLY AND ERECTION OF RADIO
ANTENNAS, TRANSMISSION LINES AND SUPPORT STRUCTURES. ALL SAFETY PROCEDURES, RIGGING AND ERECTION METHODS
SHALL BE STANDARD TO THE INDUSTRY AND IN COMPLIANCE WITH OSHA.

THE EXISTING COAXIAL CABLE AND ALL ACCESSORIES SHALL BE RELOCATED AND REINSTALLED BY THE CONTRACTOR WITHOUT
INTERUPTION IN SERVICE WHERE THEY ARE IN CONFLICT WITH TOWER REINFORCEMENT.
CONTRACTOR SHALL TAKE EXTREME CARE NOT TO DAMAGE THE EXISTING TOWER, THE EXISTING COMMUNICATION EQUIPMENT,
COAXIAL CABLE AND THEIR COMPONENTS. IN THE EVENT THAT THE EXISTING COMMUNICATION EQUIPMENT IS DAMAGED DURING
CONSTRUCTION THE CONTRACTOR SHALL REPAIR THE DAMAGE IMMEDIATELY (WITH THE APPROVAL OF THE COMMUNICATION
CARRIER) AT NO ADDITIONAL COST TO THE CONTRACT.

THE CONTRACTOR IS RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE DURING CONSTRUCTION. THE CONTRACTOR SHALL
BE AWARE OF WEATHER & WIND CONDITIONS AND NOT PERFORM TOWER MEMBER REPLACEMENT IN THE WIND.
ALL REINFORCEMENT SHOWN FOR DIAGONALS AND HORIZONTALS APPLY TO ALL SIDES OF THE TOWER.

- NOTES:**
1. ALL PROPOSED DIAGONAL MEMBERS SHALL BE INSTALLED PER PLAN BOLTS (THREADS EXCLUDED FROM SHEAR PLANE). SIZE SHALL MATCH EXISTING.
 2. REINFORCEMENT MAY REQUIRE REMOVAL OF EXISTING EQUIPMENT. CONTRACTOR SHALL COORDINATE WORK WITH OWNER.
 3. PROPOSED ANTENNAS AND APPURTENANCES SHALL NOT BE INSTALLED UNLESS REINFORCEMENT WORK HAS BEEN INSPECTED AND IS DEEMED COMPLETE.
 4. ANTENNAS AND APPURTENANCES NOT SHOWN FOR CLARITY.



1 TOWER REINFORCEMENT
SK-1 SCALE: 1" = 30'-0"

TNX TOWER INPUT/OUTPUT SUMMARY

DESIGNED APPURTENANCE LOADING

ELEVATION	TYPE	ELEVATION	TYPE	ELEVATION
183	101-80-08-01 (Municipal)	183	LUX-6515DS-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5
179.75	15" Mount Pipe (Municipal)	179.75	LUX-6515DS-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5
178	3" Dia 20" Omni (Municipal)	178	LUX-6515DS-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5
178	2.5" x 206" Whip (Municipal)	178	LUX-6515DS-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5
175	2.5" x 14" Omni (Municipal)	175	RRUS-11 (T-Mobile)	125.5
175	2.5" x 14" Omni (Municipal)	175	RRUS-11 (T-Mobile)	125.5
175	2.5" x 14" Omni (Municipal)	175	RRUS-11 (T-Mobile)	125.5
174	1.5" x 12" Omni (Municipal)	174	7770 (ATT)	115
170	APXVSP18-C-A20 (Sprint)	170	7770 (ATT)	115
170	APXVSP18-C-A20 (Sprint)	170	7770 (ATT)	115
170	APXVSP18-C-A20 (Sprint)	170	7770 (ATT)	115
170	Panasonic RRR 1900MHz (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	Panasonic RRR 1900MHz (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	Panasonic RRR 1900MHz (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	Panasonic RRR 1900MHz (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	Andrew 800MHz RRR (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	Andrew 800MHz RRR (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	Andrew 800MHz RRR (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	APXV9TM14-120 (Sprint)	170	(2) TMA (shielded) (ATT)	115
170	APXV9TM14-120 (Sprint)	170	PIROD 12' Lightweight T-Frame (ATT)	115
170	APXV9TM14-120 (Sprint)	170	PIROD 12' Lightweight T-Frame (ATT)	115
170	APXV9TM14-120 (Sprint)	170	PIROD 12' Lightweight T-Frame (ATT)	115
170	TD-RRH8x20-25 (Sprint)	170	7770 (ATT)	115
170	TD-RRH8x20-25 (Sprint)	170	7770 (ATT)	115
170	TD-RRH8x20-25 (Sprint)	170	7770 (ATT)	115
168	9 Arm Halo Mount (Municipal)	168	(2) REMOTE RADIO HEAD (RRH) (ATT)	115
168	SU-RA-HP-2.4 Antenna (Municipal)	168	Surge Suppressor (ATT)	115
168	HPD2-4.7	168	AM-X-CD-16-65-00T-RET (6) (ATT)	115
159.5	APXY18-206517S-C w/ mounting hardware	159.5	AM-X-CD-16-65-00T-RET (6) (ATT)	115
159.5	APXY18-206517S-C w/ mounting hardware	159.5	AM-X-CD-16-65-00T-RET (6) (ATT)	115
159.5	APXY18-206517S-C w/ mounting hardware	159.5	(2) REMOTE RADIO HEAD (RRH) (ATT)	101
158.5	SC420-HFLDF (Municipal)	158.5	RH_2X4D-AWS (Verizon - AWS)	101
144	3" Dia 20" Omni (Municipal)	144	RH_2X4D-AWS (Verizon - AWS)	101
144	3" Dia 20" Omni (Municipal)	144	BXA-171063-12BF (Verizon)	101
144	2.5" x 206" Whip (Municipal)	144	SWCP 2x5514 (Verizon)	101
141	2" Dia 15" Omni (Municipal)	141	BXA-171063-12BF (Verizon)	101
139	1.5" x 10" Omni (Municipal)	139	SWCP 2x5514 (Verizon)	101
138.5	9 Whip (Municipal)	138.5	PIROD 12' Lightweight T-Frame (Verizon)	101
134	Argus LLPX310R (Clearwire)	134	PIROD 12' Lightweight T-Frame (Verizon)	101
134	Argus LLPX310R (Clearwire)	134	(2) Diplexer (Verizon)	101
134	REMOTE RADIO HEAD (RRH) (Clearwire)	134	(2) Diplexer (Verizon)	101
134	REMOTE RADIO HEAD (RRH) (Clearwire)	134	(2) Diplexer (Verizon)	101
134	PIROD 20' Universal Platform (Municipal)	134	BXA-70063-6CF (Verizon)	101
134	Argus LLPX310R (Clearwire)	134	HX-6517DS-VTM (Verizon - AWS)	101
134	VHLP2.5-180 (Clearwire)	134	HX-6517DS-VTM (Verizon - AWS)	101
134	VHLP2.5-180 (Clearwire)	134	RH_2X4D-AWS (Verizon - AWS)	101
134	VHLP2-180 (Clearwire)	134	DB-11-62-84B-0Z (Verizon - AWS)	101
134	REMOTE RADIO HEAD (RRH) (Clearwire)	134	LNX-6514DS-T4M (Verizon - 650)	101
125.5	PIROD 10' Lightweight T-Frame (T-Mobile)	125.5	LNX-6514DS-T4M (Verizon - 650)	101
125.5	PIROD 10' Lightweight T-Frame (T-Mobile)	125.5	LUX-6514DS-T4M (Verizon - 650)	101
125.5	PIROD 10' Lightweight T-Frame (T-Mobile)	125.5	LUX-6514DS-T4M (Verizon - 650)	101
125.5	AIR B2AB4P (T-Mobile)	125.5	3"x2"x2" Panel	87
125.5	AIR B2AB4P (T-Mobile)	125.5	TMA	84.5
125.5	AIR B2AB4P (T-Mobile)	125.5	3" Stand-off	83.5
125.5	AIR B2AB4P (T-Mobile)	125.5	3" Stand-off	83.5
125.5	AIR B2AB4P (T-Mobile)	125.5	3" Dish	83
125.5	AIR B2AB4P (T-Mobile)	125.5	TMA	83
125.5	Twin PCS TMA (T-Mobile)	125.5	TMA	82.5
125.5	Twin PCS TMA (T-Mobile)	125.5	Camera	80
125.5	PCS TMA (T-Mobile)	125.5	PC9013N	30
125.5	LUX-6515DS-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5		24

SYMBOL LIST


MARK	SIZE	MARK	SIZE
A	Prod 105217 reinf w/ 1" dia bar		

MATERIAL STRENGTH


GRADE	Fu	Fy	GRADE	Fv	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi

TOWER DESIGN NOTES

- 1. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
- 2. Tower is also designed for a 74 mph basic wind with 0.50 in ice.
- 3. Deflections are based upon a 50 mph wind.
- 4. Weld together tower sections have flange connections.
- 5. Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications.
- 6. Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
- 7. Welds are fabricated with ER-70S-6 electrodes.
- 8. TOWER RATING: 92.4%



Section	Legs	Leg Grade	Diagonals	Diagonal Grade	Top Girts	Mid Girts	Bottom Girts	# Panels @ (n)	Weight (K)
17	Prod 105220 reinf w/ 1" dia bar	A572-50	L3 1/2x3 1/2x3/8	A36	N/A	N/A	N/A	15 @ 10	30.7
18	Prod 105219	L3 1/2x3 1/2x5/16	L3 1/2x3 1/2x5/16	N/A	N/A	N/A	N/A	8 @ 2.48958	12
19	Prod 105219 reinf w/ 1" dia bar	L3 1/2x3 1/2x3/8	L4x5/16						
20	Prod 105220 reinf w/ 1" dia bar	L4x5/16							
21	SR 1 3/4								
22	Prod 105244								
23	Prod 105216								
24	Prod 105217								
25	A								
26	Prod 105217								
27									
28									
29									
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
40									
41									
42									
43									
44									
45									
46									
47									
48									
49									
50									




TNX TOWER FEEDLINE DISTRIBUTION CHART

Feed Line Distribution Chart

0' - 170'


Round _____ Flat _____ App In Face _____ App Out Face _____ Truss Leg _____



URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job: PiROD U20'-0"x170' Lattice Tower		
	Project: TWS-027 Rev. 1 / Cromwell, CT Tower		
	Client: Sprint / T-Mobile (TWS-027)/(EBI-002)	Drawn by: MCD	App'd:
	Code: TIA/EIA-222-F	Date: 09/23/14	Scale: NTS
Path:			Dwg No. E-7

TNX TOWER FEEDLINE PLAN

Feed Line Plan



- (1) 1/2" (Town)
 - (2) 7/8" (Town)
 - (2) 1/2" (Town)
 - (3) 1/2" (existing)
 - (1) 1 5/8" Low Density (CPD)
 - (1) 3/8" (Town)
 - (1) 3/8" (CPD)
 - (1) 7/8" (Town)
 - (3) 7/8" (Town)
 - (1) 1 1/2" (Town)
 - (6) 1 5/8" (Existing)
 - (1) 7/8" (Town)
 - (1) 7/8" (Town)
 - (3) (existing) 1 1/4" Hybrid Cables (Sprint)
 - (1) Proposed 1 1/4" Hybrid Cable (Sprint)
- Leg "A"

- (6) Cat 5e (Clearwire)
 - (4) 1/2" (Clearwire)
- Face "B"

- (12) 1 5/8" (AT&T)
 - (12) 1 5/8" (Verizon)
 - (1) 1 5/8" Hybriflex (Verizon)
 - (2) 7/8" (existing)
- Leg "C"

- (4) Cat 5e (AT&T)
 - (2) Cat 5e (AT&T)
 - (6) RSS 8 - AWG (AT&T)
 - (3) FB-L98B-02 (10mm) F.O. (AT&T)
(located inside below)
 - (1) 3" Flex Conduit Tube (AT&T)
- Face "C"

- (12) 1 5/8" (T-Mobile)
 - (1) 1 5/8" Hybriflex (T-Mobile)
- Leg "B"

- (4) CATEGORY 5e (1 WIRE)
- (2) CATEGORY 5e (1 WIRE)
- (6) RSS 8 - AWG 2 (0.645") (AT&T)
- (3) FB-L98B-02 (10mm) F.O. (AT&T)

<p>URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991</p>	<p>Job: PiROD U20'-0"x170' Lattice Tower</p> <p>Project: TWS-027 Rev. 1 / Cromwell, CT Tower</p> <p>Client: Sprint / T-Mobile (TWS-027)/(EBI-002) Drawn by: MCD App'd:</p> <p>Code: TIA/EIA-222-F Date: 09/23/14 Scale: NTS</p> <p>Path: Dwg No. E-7</p>
---	---

TNX TOWER DETAILED OUTPUT

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 1 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 170.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 5.00 ft at the top and 20.00 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Basic wind speed of 85 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56 pcf.

A wind speed of 74 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

Weld together tower sections have flange connections..

Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications..

Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards..

Welds are fabricated with ER-70S-6 electrodes..

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|--|--|--|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity √ Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) Add IBC .6D+W Combination | <ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. Autocalc Torque Arm Areas √ SR Members Have Cut Ends √ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Use TIA-222-G Tension Splice Capacity Exemption | <ul style="list-style-type: none"> √ Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces √ Ignore Redundant Members in FEA √ SR Leg Bolts Resist Compression √ All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feedline Torque Include Angle Block Shear Check <li style="text-align: center;">Poles Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets |
|--|--|--|

Job	PIROD U20'-0"x170' Lattice Tower	Page	2 of 43
Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD



Triangular Tower

Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	170.00-150.00			5.00	1	20.00
T2	150.00-140.00		U6.0 105244	5.00	1	10.00
T3	140.00-120.00		U8.0 105216	6.00	1	20.00
T4	120.00-100.00		U10.0 105217 L3x3/16	8.00	1	20.00
T5	100.00-90.00		U12.0 105216	10.00	1	10.00
T6	90.00-80.00		U12.0 105216	11.00	1	10.00
T7	80.00-60.00		U14.0 105218	12.00	1	20.00
T8	60.00-40.00		U16.0 105219	14.00	1	20.00
T9	40.00-20.00		U18.0 105219	16.00	1	20.00
T10	20.00-0.00		U20.0 105219 L4x1/4	18.00	1	20.00

Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	<i>ft</i>	<i>ft</i>				<i>in</i>	<i>in</i>
T1	170.00-150.00	2.49	X Brace	No	No	0.0000	1.0000
T2	150.00-140.00	10.00	X Brace	No	No	0.0000	0.0000
T3	140.00-120.00	10.00	X Brace	No	No	0.0000	0.0000
T4	120.00-100.00	10.00	X Brace	No	No	0.0000	0.0000
T5	100.00-90.00	10.00	X Brace	No	No	0.0000	0.0000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 3 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Tower Section	Tower Elevation ft	Diagonal Spacing ft	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset in	Bottom Girt Offset in
T6	90.00-80.00	10.00	X Brace	No	No	0.0000	0.0000
T7	80.00-60.00	10.00	X Brace	No	No	0.0000	0.0000
T8	60.00-40.00	10.00	X Brace	No	No	0.0000	0.0000
T9	40.00-20.00	10.00	X Brace	No	No	0.0000	0.0000
T10	20.00-0.00	10.00	X Brace	No	No	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T1 170.00-150.00	Solid Round	1 3/4	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 150.00-140.00	Truss Leg	Pirod 105244	A572-50 (50 ksi)	Single Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T3 140.00-120.00	Truss Leg	Pirod 105216	A572-50 (50 ksi)	Single Angle	L3x3x3/16	A36 (36 ksi)
T4 120.00-100.00	Truss Leg	Pirod 105217	A572-50 (50 ksi)	Single Angle	L3x3x1/4	A36 (36 ksi)
T5 100.00-90.00	Truss Leg	Pirod 105217	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T6 90.00-80.00	Truss Leg	Pirod 105217 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T7 80.00-60.00	Truss Leg	Pirod 105218 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3x3x3/8	A36 (36 ksi)
T8 60.00-40.00	Truss Leg	Pirod 105219	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x5/16	A36 (36 ksi)
T9 40.00-20.00	Truss Leg	Pirod 105219 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x3/8	A36 (36 ksi)
T10 20.00-0.00	Truss Leg	Pirod 105220 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L4x4x5/16	A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 170.00-150.00	Solid Round	7/8	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 150.00-140.00	Single Angle	L3x3x3/16	A36 (36 ksi)	Single Angle		A36 (36 ksi)

Tower Section Geometry (cont'd)

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 6 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T2 150.00-140.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T3 140.00-120.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T4 120.00-100.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T5 100.00-90.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T6 90.00-80.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T7 80.00-60.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T8 60.00-40.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T9 40.00-20.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T10 20.00-0.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 170.00-150.00	Flange	0.7500	0	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T2 150.00-140.00	Flange	1.0000	6	1.0000	1	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T3 140.00-120.00	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T4 120.00-100.00	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	1.0000	1	0.6250	0	0.6250	0
T5 100.00-90.00	Flange	1.0000	6	1.0000	1	0.6250	0	0.0000	0	0.6250	0	0.6250	0	0.6250	0
T6 90.00-80.00	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T7 80.00-60.00	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T8 60.00-40.00	Flange	1.2500	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T9 40.00-20.00	Flange	1.2500	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T10 20.00-0.00	Flange	0.0000	0	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
CATEGORY	C	Yes	Ar (CfAe)	87.00 - 7.00	0.0000	0.48	4	2	1.0000	1.0000		0.21

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	7 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
5e (1 WIRE) CATEGORY	C	Yes	Ar (CfAe)	83.00 - 7.00	0.0000	0.45	2	1	1.0000	1.0000		0.21
5e (1 WIRE) 1/2 (Municipal)	A	No	Ar (Leg)	144.00 - 7.00	0.0000	0.125	1	1	0.5800	0.5800		0.25
7/8 (Municipal)	A	No	Ar (Leg)	144.00 - 7.00	0.0000	0.125	2	1	1.0000	1.1100		0.54
1/2 (Municipal)	A	No	Ar (Leg)	140.00 - 7.00	0.0000	0.13	2	1	0.5800	0.5800		0.25
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.14	3	1	1.0000	1.1100		0.54
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.14	1	1	1.1100	1.1100		0.54
FSJ2-50 (3/8 SUPERFLEX. FOAM)	A	No	Ar (Leg)	168.00 - 7.00	0.0000	0.12	1	1	0.4300	0.4300		0.08
FSJ2-50 (3/8 SUPERFLEX. FOAM)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.12	1	1	0.4300	0.4300		0.08
RG-11 590609 (1 1/2 FOAM)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.12	1	1	1.5000	1.5900		0.94
1 5/8 (T-Mobile)	B	No	Ar (Leg)	125.50 - 7.00	0.0000	0.1	12	3	1.5000	1.9800		1.04
1 5/8 (VZW)	C	No	Ar (Leg)	101.00 - 7.00	0.0000	0.12	12	6	1.5000	1.9800		1.04
1 5/8 (AT&T)	C	No	Ar (Leg)	115.00 - 7.00	0.0000	0.17	12	2	1.5000	1.9800		1.04
7/8	C	No	Ar (Leg)	170.00 - 7.00	0.0000	0.17	2	2	1.0000	1.1100		0.54
1 5/8	A	No	Ar (Leg)	160.00 - 7.00	0.0000	0.1	6	3	1.5000	1.9800		1.04
CATEGORY 5e (1 WIRE) (Clearwire)	B	Yes	Ar (CfAe)	134.00 - 7.00	-2.0000	0	6	6	1.0000	1.0000		0.21
1/2 (Clearwire)	B	Yes	Ar (CfAe)	134.00 - 7.00	-4.0000	0	4	4	0.5800	0.5800		0.25
FB-L98B-02 (10mm Fiber) (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	3.0000	0.4	3	3	0.3937	0.3937		0.03
RSS 8 - AWG 2 (0.645") (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	2.0000	0.43	6	6	0.6450	0.6450		0.30
3" Flex Conduit (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	4.0000	0.41	1	1	0.0000	3.0000		3.00
1/2	A	No	Ar (Leg)	30.00 - 7.00	0.0000	0.08	3	1	0.5800	0.5800		0.25
AVA7-50 (1-5/8 LOW DENS. FOAM) (CPD)	A	Yes	Ar (CfAe)	170.00 - 7.00	0.0000	0.38	1	1	1.5000	1.9800		0.72
1 5/8" Hybriflex (T-Mobile)	B	No	Ar (Leg)	125.00 - 7.00	0.0000	0.05	1	1	1.6250	1.6250		0.21
1 5/8" Hybriflex (VZW)	C	No	Ar (Leg)	101.00 - 7.00	0.0000	0.1	1	1	1.6250	1.6250		0.21
LDF6-50A (1-1/4 FOAM) (Sprint-FO)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.16	4	2	1.5500	1.5500		0.66
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.132	1	1	1.1100	1.1100		0.54
7/8	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.132	1	1	1.1100	1.1100		0.54

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 8 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Description	Face or Leg	Allow Shield	Component Type	Placement	Face Offset	Lateral Offset	# Per Row	#	Clear Spacing	Width or Diameter	Perimeter	Weight
				ft	in	(Frac FW)			in	in	in	plf
(Municipal)												

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation	Face	A _R	A _F	C _A A _A In Face	C _A A _A Out Face	Weight
	ft		ft ²	ft ²	ft ²	ft ²	K
T1	170.00-150.00	A	40.136	0.000	0.000	0.000	0.22
		B	33.136	0.000	0.000	0.000	0.00
		C	3.700	0.000	0.000	0.000	0.02
T2	150.00-140.00	A	25.105	0.000	0.000	0.000	0.14
		B	21.605	0.000	0.000	0.000	0.00
		C	1.850	0.000	0.000	0.000	0.01
T3	140.00-120.00	A	54.943	0.000	0.000	0.000	0.32
		B	64.985	0.000	0.000	0.000	0.10
		C	11.035	0.000	0.000	0.000	0.02
T4	120.00-100.00	A	81.377	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	67.119	0.000	0.000	0.000	0.29
T5	100.00-90.00	A	61.700	0.000	0.000	0.000	0.16
		B	44.365	0.000	0.000	0.000	0.15
		C	56.248	0.000	0.000	0.000	0.31
T6	90.00-80.00	A	61.700	0.000	0.000	0.000	0.16
		B	44.365	0.000	0.000	0.000	0.15
		C	58.981	0.000	0.000	0.000	0.32
T7	80.00-60.00	A	123.400	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T8	60.00-40.00	A	123.400	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T9	40.00-20.00	A	124.850	0.000	0.000	0.000	0.32
		B	90.180	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T10	20.00-0.00	A	82.095	0.000	0.000	0.000	0.21
		B	59.559	0.000	0.000	0.000	0.19
		C	79.437	0.000	0.000	0.000	0.42

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation	Face or Leg	Ice Thickness	A _R	A _F	C _A A _A In Face	C _A A _A Out Face	Weight
	ft		in	ft ²	ft ²	ft ²	ft ²	K
T1	170.00-150.00	A	0.500	58.953	3.517	0.000	0.000	0.60
		B		50.470	0.000	0.000	0.000	0.00
		C		3.517	3.517	0.000	0.000	0.07
T2	150.00-140.00	A	0.500	36.013	1.758	0.000	0.000	0.39
		B		31.771	0.000	0.000	0.000	0.00
		C		1.758	1.758	0.000	0.000	0.03
T3	140.00-120.00	A	0.500	82.393	3.517	0.000	0.000	0.87
		B		86.296	15.727	0.000	0.000	0.34
		C		11.727	3.517	0.000	0.000	0.07
T4	120.00-100.00	A	0.500	110.244	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88

Job	PIROD U20'-0"x170' Lattice Tower	Page	9 of 43
Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	$C_A A_A$ In Face ft ²	$C_A A_A$ Out Face ft ²	Weight K
T5	100.00-90.00	C	0.500	70.420	13.548	0.000	0.000	0.75
		A		77.925	1.758	0.000	0.000	0.44
		B		55.065	11.233	0.000	0.000	0.44
T6	90.00-80.00	C	0.500	59.479	8.446	0.000	0.000	0.79
		A		77.925	1.758	0.000	0.000	0.44
		B		55.065	11.233	0.000	0.000	0.44
T7	80.00-60.00	C	0.500	61.646	10.096	0.000	0.000	0.83
		A		155.850	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88
T8	60.00-40.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		155.850	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88
T9	40.00-20.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		159.100	3.517	0.000	0.000	0.90
		B		113.380	22.467	0.000	0.000	0.88
T10	20.00-0.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		105.527	2.286	0.000	0.000	0.60
		B		75.809	14.603	0.000	0.000	0.57
		C		83.823	14.043	0.000	0.000	1.12

Feed Line Shielding

Section	Elevation ft	Face	A_R ft ²	A_R Ice ft ²	A_F ft ²	A_F Ice ft ²
T1	170.00-150.00	A	0.239	0.771	0.000	0.000
		B	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	0.000
T2	150.00-140.00	A	0.000	0.106	0.184	0.277
		B	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	0.000
T3	140.00-120.00	A	0.000	0.145	0.289	0.435
		B	0.000	0.580	0.849	1.741
		C	0.000	0.000	0.000	0.000
T4	120.00-100.00	A	0.000	0.145	0.288	0.434
		B	0.000	0.828	1.212	2.484
		C	0.000	0.548	0.879	1.645
T5	100.00-90.00	A	0.000	0.057	0.114	0.171
		B	0.000	0.327	0.479	0.981
		C	0.000	0.289	0.463	0.867
T6	90.00-80.00	A	0.000	0.055	0.109	0.165
		B	0.000	0.314	0.459	0.942
		C	0.000	0.340	0.538	1.019
T7	80.00-60.00	A	0.000	0.105	0.208	0.314
		B	0.000	0.598	0.875	1.795
		C	0.000	0.739	1.163	2.216
T8	60.00-40.00	A	0.000	0.100	0.231	0.348
		B	0.000	0.570	0.973	1.994
		C	0.000	0.703	1.292	2.462
T9	40.00-20.00	A	0.000	0.096	0.223	0.336
		B	0.000	0.550	0.939	1.925
		C	0.000	0.679	1.247	2.377
T10	20.00-0.00	A	0.000	0.061	0.162	0.243
		B	0.000	0.348	0.679	1.393
		C	0.000	0.430	0.902	1.719

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 10 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Feed Line Center of Pressure

Section	Elevation	CP _x	CP _z	CP _x Ice	CP _z Ice
	ft	in	in	in	in
T1	170.00-150.00	-0.7973	-8.0376	-0.4853	-7.4212
T2	150.00-140.00	-0.4988	-6.6293	-0.3283	-6.3594
T3	140.00-120.00	1.4194	-7.8403	1.2494	-8.0075
T4	120.00-100.00	-0.3302	-2.7146	-0.0626	-4.2227
T5	100.00-90.00	-5.2784	0.3685	-4.0917	-1.7690
T6	90.00-80.00	-6.3856	0.8722	-4.8612	-1.5653
T7	80.00-60.00	-7.6460	1.3464	-5.9655	-1.3222
T8	60.00-40.00	-8.5419	1.4777	-6.6864	-1.5207
T9	40.00-20.00	-9.4077	1.2998	-7.3405	-2.1935
T10	20.00-0.00	-8.2989	0.8730	-6.4327	-2.3698

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
			ft	ft	°	ft	ft ²	ft ²	K
101-90-08-0-01 (Municipal)	A	From Leg	9.00	0.0000	183.00	No Ice	3.33	3.33	0.04
			2.00	0.0000		1/2" Ice	4.31	4.31	0.06
			0.00						
15' Mount Pipe (Municipal)	A	From Leg	9.00	0.0000	179.75	No Ice	4.50	4.50	0.09
			2.00	0.0000		1/2" Ice	6.03	6.03	0.12
			0.00						
3" Dia 20' Omni (Municipal)	B	From Face	9.00	0.0000	178.00	No Ice	6.00	6.00	0.06
			0.00	0.0000		1/2" Ice	8.03	8.03	0.10
			0.00						
2.5" x 20'6" Whip (Municipal)	C	From Face	9.00	0.0000	178.00	No Ice	5.14	5.14	0.15
			0.00	0.0000		1/2" Ice	7.24	7.24	0.19
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00	0.0000		1/2" Ice	4.93	4.93	0.06
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00	0.0000		1/2" Ice	4.93	4.93	0.06
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00	0.0000		1/2" Ice	4.93	4.93	0.06
			0.00						
1.5" x 12' Omni (Municipal)	A	From Face	9.00	0.0000	174.00	No Ice	1.50	1.50	0.06
			4.00	0.0000		1/2" Ice	2.52	2.52	0.07
			0.00						
9 Arm Halo Mount (Municipal)	C	None		0.0000	168.00	No Ice	62.60	62.60	3.60
				0.0000		1/2" Ice	80.40	80.40	4.80
SU-RA-HP-2.4 Antenna (Municipal)	B	From Face	9.00	0.0000	168.00	No Ice	0.80	0.37	0.00
			2.50	0.0000		1/2" Ice	0.93	0.47	0.01
			0.00						
PTP49600 (CPD)	C	From Leg	9.00	0.0000	168.00	No Ice	2.04	0.53	0.01
			0.00	0.0000		1/2" Ice	2.24	0.65	0.02

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	11 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	CAA Front	CAA Side	Weight	
			Horz Lateral	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
APXV18-206517S-C w/ mounting hardware	A	From Leg	0.00	1.00	0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00	0.00			1/2" Ice	5.53	5.39	0.09
			0.00							
APXV18-206517S-C w/ mounting hardware	B	From Leg	1.00	0.00	0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00	0.00			1/2" Ice	5.53	5.39	0.09
			0.00							
APXV18-206517S-C w/ mounting hardware	C	From Leg	1.00	0.00	0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00	0.00			1/2" Ice	5.53	5.39	0.09
			0.00							
SC420-HF1LDF (Municipal)	A	From Face	6.00	0.00	0.0000	158.50	No Ice	2.14	2.14	0.02
			0.00	0.00			1/2" Ice	3.02	3.02	0.03
			0.00							
3" Dia 20' Omni (Municipal)	C	From Face	6.00	0.00	0.0000	144.00	No Ice	6.00	6.00	0.06
			9.00	0.00			1/2" Ice	8.03	8.03	0.10
			0.00							
3" Dia 20' Omni (Municipal)	A	From Face	6.00	0.00	0.0000	144.00	No Ice	6.00	6.00	0.06
			-9.00	0.00			1/2" Ice	8.03	8.03	0.10
			0.00							
2.5" x 20'6" Whip (Municipal)	A	From Face	6.00	0.00	0.0000	144.00	No Ice	5.14	5.14	0.15
			9.00	0.00			1/2" Ice	7.24	7.24	0.19
			0.00							
2" Dia 15' Omni (Municipal)	B	From Face	6.00	0.00	0.0000	141.00	No Ice	3.20	3.20	0.04
			-5.00	0.00			1/2" Ice	4.83	4.83	0.06
			0.00							
1.5" x 10' Omni (Municipal)	B	From Face	6.00	0.00	0.0000	139.00	No Ice	1.50	1.50	0.06
			5.00	0.00			1/2" Ice	2.52	2.52	0.07
			0.00							
9' Whip (Municipal)	A	From Face	6.00	0.00	0.0000	138.50	No Ice	5.85	5.85	0.12
			0.00	0.00			1/2" Ice	7.66	7.66	0.17
			0.00							
PiROD 20' Universal Platform (Municipal)	C	None			0.0000	134.00	No Ice	33.10	33.10	2.27
							1/2" Ice	47.10	47.10	2.70
Argus LLPX310R (Clearwire)	A	From Face	6.00	0.00	0.0000	134.00	No Ice	4.86	3.46	0.03
			7.00	0.00			1/2" Ice	5.22	3.80	0.06
			0.00							
Argus LLPX310R (Clearwire)	B	From Face	6.00	0.00	0.0000	134.00	No Ice	4.86	3.46	0.03
			0.00	0.00			1/2" Ice	5.22	3.80	0.06
			0.00							
Argus LLPX310R (Clearwire)	C	From Face	6.00	0.00	0.0000	134.00	No Ice	4.86	3.46	0.03
			7.00	0.00			1/2" Ice	5.22	3.80	0.06
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	A	From Face	6.00	0.00	0.0000	134.00	No Ice	1.82	0.83	0.03
			7.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	B	From Face	6.00	0.00	0.0000	134.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	C	From Face	6.00	0.00	0.0000	134.00	No Ice	1.82	0.83	0.03
			7.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00							
(2) TMA (shielded) (AT&T)	A	From Leg	4.00	0.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			6.00	0.00			1/2" Ice	0.00	0.00	0.01
			0.00							
(2) TMA (shielded) (AT&T)	A	From Leg	4.00	0.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			-6.00	0.00			1/2" Ice	0.00	0.00	0.01

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	12 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
(2) TMA (shielded) (AT&T)	B	From Leg	0.00		0.0000	115.00	No Ice	0.00	0.00	0.01
			4.00				1/2" Ice	0.00	0.00	0.01
			6.00							
(2) TMA (shielded) (AT&T)	B	From Leg	0.00		0.0000	115.00	No Ice	0.00	0.00	0.01
			4.00				1/2" Ice	0.00	0.00	0.01
			-6.00							
(2) TMA (shielded) (AT&T)	C	From Leg	0.00		0.0000	115.00	No Ice	0.00	0.00	0.01
			4.00				1/2" Ice	0.00	0.00	0.01
			6.00							
(2) TMA (shielded) (AT&T)	C	From Leg	0.00		0.0000	115.00	No Ice	0.00	0.00	0.01
			4.00				1/2" Ice	0.00	0.00	0.01
			-6.00							
PiROD 12' Lightweight T-Frame (AT&T)	A	From Leg	0.00		0.0000	115.00	No Ice	10.20	10.20	0.25
			2.00				1/2" Ice	16.20	16.20	0.35
			0.00							
PiROD 12' Lightweight T-Frame (AT&T)	B	From Leg	0.00		0.0000	115.00	No Ice	10.20	10.20	0.25
			2.00				1/2" Ice	16.20	16.20	0.35
			0.00							
PiROD 12' Lightweight T-Frame (AT&T)	C	From Leg	0.00		0.0000	115.00	No Ice	10.20	10.20	0.25
			2.00				1/2" Ice	16.20	16.20	0.35
			0.00							
7770 (AT&T)	A	From Leg	0.00		0.0000	115.00	No Ice	10.03	5.60	0.02
			4.00				1/2" Ice	10.61	6.15	0.07
			6.00							
7770 (AT&T)	A	From Leg	0.00		0.0000	115.00	No Ice	10.03	5.60	0.02
			4.00				1/2" Ice	10.61	6.15	0.07
			-6.00							
7770 (AT&T)	B	From Leg	0.00		0.0000	115.00	No Ice	10.03	5.60	0.02
			4.00				1/2" Ice	10.61	6.15	0.07
			6.00							
7770 (AT&T)	B	From Leg	0.00		0.0000	115.00	No Ice	10.03	5.60	0.02
			4.00				1/2" Ice	10.61	6.15	0.07
			-6.00							
7770 (AT&T)	C	From Leg	0.00		0.0000	115.00	No Ice	10.03	5.60	0.02
			4.00				1/2" Ice	10.61	6.15	0.07
			6.00							
7770 (AT&T)	C	From Leg	0.00		0.0000	115.00	No Ice	10.03	5.60	0.02
			4.00				1/2" Ice	10.61	6.15	0.07
			-6.00							
AM-X-CD-16-65-00T-RET (6') (AT&T)	A	From Leg	0.00		0.0000	115.00	No Ice	8.26	4.64	0.05
			4.00				1/2" Ice	8.81	5.09	0.10
			0.00							
AM-X-CD-16-65-00T-RET (6') (AT&T)	B	From Leg	0.00		0.0000	115.00	No Ice	8.26	4.64	0.05
			4.00				1/2" Ice	8.81	5.09	0.10
			0.00							
AM-X-CD-16-65-00T-RET (6') (AT&T)	C	From Leg	0.00		0.0000	115.00	No Ice	8.26	4.64	0.05
			4.00				1/2" Ice	8.81	5.09	0.10
			0.00							
(2) REMOTE RADIO HEAD (RRH) (AT&T)	A	From Leg	0.00		0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00				1/2" Ice	2.00	0.97	0.04
			0.00							
(2) REMOTE RADIO HEAD (RRH) (AT&T)	B	From Leg	0.00		0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00				1/2" Ice	2.00	0.97	0.04
			0.00							
(2) REMOTE RADIO HEAD (RRH)	C	From Leg	0.00		0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00				1/2" Ice	2.00	0.97	0.04
			0.00							

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PiROD U20'-0"x170' Lattice Tower	Page	13 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			ft ft ft	°	ft	ft ²	ft ²	K	
(AT&T)			0.00						
Surge Suppressor (AT&T)	C	From Leg	0.00	0.0000	115.00	No Ice 1/2" Ice	0.80 0.94	0.80 0.94	0.03 0.04
BXA-171063-12BF (Verizon)	A	From Leg	4.00 0.00 0.00	0.0000	101.00	No Ice 1/2" Ice	4.73 5.18	3.57 4.01	0.02 0.04
SWCP 2x5514 (Verizon)	A	From Leg	4.00 -4.00 0.00	0.0000	101.00	No Ice 1/2" Ice	7.01 7.44	5.70 6.12	0.02 0.07
BXA-171063-12BF (Verizon)	B	From Leg	4.00 0.00 0.00	0.0000	101.00	No Ice 1/2" Ice	4.73 5.18	3.57 4.01	0.02 0.04
BXA-171063-12BF (Verizon)	C	From Leg	4.00 0.00 0.00	0.0000	101.00	No Ice 1/2" Ice	4.73 5.18	3.57 4.01	0.02 0.04
SWCP 2x5514 (Verizon)	C	From Leg	4.00 -4.00 0.00	0.0000	101.00	No Ice 1/2" Ice	7.01 7.44	5.70 6.12	0.02 0.07
PiROD 12' Lightweight T-Frame (Verizon)	A	From Leg	2.00 0.00 0.00	0.0000	101.00	No Ice 1/2" Ice	10.20 16.20	10.20 16.20	0.25 0.35
PiROD 12' Lightweight T-Frame (Verizon)	B	From Leg	2.00 0.00 0.00	0.0000	101.00	No Ice 1/2" Ice	10.20 16.20	10.20 16.20	0.25 0.35
PiROD 12' Lightweight T-Frame (Verizon)	C	From Leg	2.00 0.00 0.00	0.0000	101.00	No Ice 1/2" Ice	10.20 16.20	10.20 16.20	0.25 0.35
(2) Diplexer (Verizon)	A	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	0.23 0.30	0.17 0.24	0.01 0.01
(2) Diplexer (Verizon)	B	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	0.23 0.30	0.17 0.24	0.01 0.01
(2) Diplexer (Verizon)	C	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	0.23 0.30	0.17 0.24	0.01 0.01
BXA-70063-6CF (Verizon)	B	From Leg	4.00 -4.00 0.00	0.0000	101.00	No Ice 1/2" Ice	7.73 8.27	4.16 4.60	0.02 0.06
HBX-6517DS-VTM (Verizon - AWS)	A	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	5.24 5.71	3.24 3.69	0.01 0.04
HBX-6517DS-VTM (Verizon - AWS)	B	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	5.24 5.71	3.24 3.69	0.01 0.04
HBX-6517DS-VTM (Verizon - AWS)	C	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	5.24 5.71	3.24 3.69	0.01 0.04
RH_2X40-AWS (Verizon - AWS)	A	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	2.52 2.75	1.59 1.80	0.04 0.06
RH_2X40-AWS (Verizon - AWS)	B	From Leg	4.00 6.00 0.00	0.0000	101.00	No Ice 1/2" Ice	2.52 2.75	1.59 1.80	0.04 0.06
RH_2X40-AWS (Verizon - AWS)	C	From Leg	4.00 6.00	0.0000	101.00	No Ice 1/2" Ice	2.52 2.75	1.59 1.80	0.04 0.06

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	14 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA}		Weight
			Horz	Vert			Front	Side	
			ft	ft	°	ft	ft ²	ft ²	K
DB-T1-6Z-8AB-0Z (Verizon - AWS)	C	None		0.00	0.0000	101.00	No Ice 1/2" Ice	5.35 2.40	0.04 0.07
LNx-6514DS-T4M (Verizon - 850)	A	From Leg	4.00 -6.00 0.00		0.0000	101.00	No Ice 1/2" Ice	8.38 5.86	0.04 0.09
LNx-6514DS-T4M (Verizon - 850)	B	From Leg	4.00 -6.00 0.00		0.0000	101.00	No Ice 1/2" Ice	8.38 5.86	0.04 0.09
LNx-6514DS-T4M (Verizon - 850)	C	From Leg	4.00 -6.00 0.00		0.0000	101.00	No Ice 1/2" Ice	8.38 5.86	0.04 0.09
3"x2"x22" Panel	B	From Leg	2.00 0.00 0.00		0.0000	87.00	No Ice 1/2" Ice	0.65 0.81	0.05 0.05
TMA	B	From Leg	2.00 0.00 0.00		0.0000	84.50	No Ice 1/2" Ice	1.06 1.21	0.02 0.03
3' Stand-off	B	From Leg	1.50 0.00 0.00		0.0000	83.50	No Ice 1/2" Ice	1.00 1.20	0.05 0.07
3' Stand-off	A	From Leg	1.50 0.00 0.00		0.0000	83.50	No Ice 1/2" Ice	1.00 1.20	0.05 0.07
TMA	A	From Leg	2.00 0.00 0.00		0.0000	83.00	No Ice 1/2" Ice	1.06 1.21	0.02 0.03
TMA	B	From Leg	2.00 0.00 0.00		0.0000	82.50	No Ice 1/2" Ice	1.06 1.21	0.02 0.03
3"x2"x22" Panel	B	From Leg	2.00 0.00 0.00		0.0000	80.00	No Ice 1/2" Ice	0.65 0.81	0.05 0.05
Camera	A	From Leg	0.00 0.00 0.00		0.0000	30.00	No Ice 1/2" Ice	0.50 0.60	0.01 0.02
PC9013N	A	From Leg	1.00 0.00 0.00		0.0000	24.00	No Ice 1/2" Ice	0.46 0.52	0.00 0.00
APXVSP18-C-A20 (Sprint)	A	From Face	9.00 -1.00 0.00		0.0000	170.00	No Ice 1/2" Ice	8.40 8.95	5.28 5.74
APXVSP18-C-A20 (Sprint)	B	From Face	9.00 -1.00 0.00		0.0000	170.00	No Ice 1/2" Ice	8.40 8.95	5.28 5.74
APXVSP18-C-A20 (Sprint)	C	From Face	9.00 -1.00 0.00		0.0000	170.00	No Ice 1/2" Ice	8.40 8.95	5.28 5.74
Panasonic RRH 1900MHZ (Sprint)	A	From Face	8.00 0.00 0.00		0.0000	170.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30
Panasonic RRH 1900MHZ (Sprint)	B	From Face	8.00 0.00 0.00		0.0000	170.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30
Panasonic RRH 1900MHZ (Sprint)	C	From Face	8.00 0.00 0.00		0.0000	170.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	15 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft ²	ft ²	K
Andrew 800MHz RRH (Sprint)	A	From Face	8.00	0.00	0.0000	170.00	No Ice 2.36	1.97	0.06
			0.00	0.00			1/2" Ice 2.57	2.17	0.08
Andrew 800MHz RRH (Sprint)	B	From Face	8.00	0.00	0.0000	170.00	No Ice 2.36	1.97	0.06
			0.00	0.00			1/2" Ice 2.57	2.17	0.08
Andrew 800MHz RRH (Sprint)	C	From Face	8.00	0.00	0.0000	170.00	No Ice 2.36	1.97	0.06
			0.00	0.00			1/2" Ice 2.57	2.17	0.08
APXV9TM14-120 (Sprint)	A	From Face	9.00	-4.00	0.0000	170.00	No Ice 6.90	3.61	0.07
			0.00	0.00			1/2" Ice 7.35	3.97	0.11
APXV9TM14-120 (Sprint)	B	From Face	9.00	-4.00	0.0000	170.00	No Ice 6.90	3.61	0.07
			0.00	0.00			1/2" Ice 7.35	3.97	0.11
APXV9TM14-120 (Sprint)	C	From Face	9.00	-4.00	0.0000	170.00	No Ice 6.90	3.61	0.07
			0.00	0.00			1/2" Ice 7.35	3.97	0.11
TD-RRH8x20-25 (Sprint)	A	From Face	9.00	-4.00	0.0000	170.00	No Ice 4.32	1.41	0.07
			0.00	0.00			1/2" Ice 4.60	1.61	0.09
TD-RRH8x20-25 (Sprint)	B	From Face	9.00	-4.00	0.0000	170.00	No Ice 4.32	1.41	0.07
			0.00	0.00			1/2" Ice 4.60	1.61	0.09
TD-RRH8x20-25 (Sprint)	C	From Face	9.00	-4.00	0.0000	170.00	No Ice 4.32	1.41	0.07
			0.00	0.00			1/2" Ice 4.60	1.61	0.09
PiROD 10' Lightweight T-Frame (T-Mobile)	A	From Leg	2.00	0.00	0.0000	125.50	No Ice 9.30	9.30	0.25
			0.00	0.00			1/2" Ice 14.50	14.50	0.34
PiROD 10' Lightweight T-Frame (T-Mobile)	B	From Leg	2.00	0.00	0.0000	125.50	No Ice 9.30	9.30	0.25
			0.00	0.00			1/2" Ice 14.50	14.50	0.34
PiROD 10' Lightweight T-Frame (T-Mobile)	C	From Leg	2.00	0.00	0.0000	125.50	No Ice 9.30	9.30	0.25
			0.00	0.00			1/2" Ice 14.50	14.50	0.34
AIR B2A/B4P (T-Mobile)	A	From Leg	4.00	3.00	0.0000	125.50	No Ice 6.42	4.22	0.08
			0.00	0.00			1/2" Ice 6.86	4.64	0.12
AIR B2A/B4P (T-Mobile)	B	From Leg	4.00	3.00	0.0000	125.50	No Ice 6.42	4.22	0.08
			0.00	0.00			1/2" Ice 6.86	4.64	0.12
AIR B2A/B4P (T-Mobile)	C	From Leg	4.00	3.00	0.0000	125.50	No Ice 6.42	4.22	0.08
			0.00	0.00			1/2" Ice 6.86	4.64	0.12
AIR B2A/B4P (T-Mobile)	A	From Leg	4.00	-3.00	0.0000	125.50	No Ice 6.42	4.22	0.08
			0.00	0.00			1/2" Ice 6.86	4.64	0.12
AIR B2A/B4P (T-Mobile)	B	From Leg	4.00	-3.00	0.0000	125.50	No Ice 6.42	4.22	0.08
			0.00	0.00			1/2" Ice 6.86	4.64	0.12
AIR B2A/B4P (T-Mobile)	C	From Leg	4.00	-3.00	0.0000	125.50	No Ice 6.42	4.22	0.08
			0.00	0.00			1/2" Ice 6.86	4.64	0.12
Twin PCS TMA (T-Mobile)	A	From Leg	4.00	3.00	0.0000	125.50	No Ice 0.77	0.36	0.01
			0.00	0.00			1/2" Ice 0.96	0.52	0.02

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 17 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Truss-Leg Properties

Section Designation	Area <i>in</i> ²	Area Ice <i>in</i> ²	Self Weight <i>K</i>	Ice Weight <i>K</i>	Equiv. Diameter <i>in</i>	Equiv. Diameter Ice <i>in</i>	Leg Area <i>in</i> ²
Pirod 105244	1026.8606	1727.9786	0.56	0.21	7.1310	11.9999	3.6816
Pirod 105216	1998.0891	3357.4497	0.51	0.43	6.9378	11.6578	3.6816
Pirod 105217	2130.7479	3520.4599	0.62	0.44	7.3984	12.2238	5.3014
Pirod 105217	2130.7479	3520.4599	0.62	0.44	7.3984	12.2238	5.3014
Pirod 105217 reinf w/ 1" dia bar	2291.5652	3727.7657	0.79	0.46	7.9568	12.9436	7.6570
Pirod 105218 reinf w/ 1" dia bar	2425.8928	3907.6826	0.95	0.48	8.4232	13.5683	9.9280
Pirod 105219	2441.8688	3942.2854	0.94	0.49	8.4787	13.6885	9.4248
Pirod 105219 reinf w /1" dia bar	2571.0468	4121.6676	1.11	0.50	8.9272	14.3113	11.7803
Pirod 105220 reinf w/ 1" dia bar	2697.7688	4300.8949	1.29	0.51	9.3673	14.9337	14.2843

Tower Pressures - No Ice

$$G_H = 1.125$$

Section Elevation <i>ft</i>	<i>z</i> <i>ft</i>	<i>K_z</i>	<i>q_z</i> <i>psf</i>	<i>A_G</i> <i>ft</i> ²	<i>F_a</i> <i>c</i> <i>e</i>	<i>A_F</i> <i>ft</i> ²	<i>A_R</i> <i>ft</i> ²	<i>A_{leg}</i> <i>ft</i> ²	Leg % <i>ft</i> ²	<i>C_AA_A</i> In Face <i>ft</i> ²	<i>C_AA_A</i> Out Face <i>ft</i> ²
T1 170.00-150.00	160.00	1.57	29	102.917	A	0.000	52.765	5.833	11.06	0.000	0.000
					B	0.000	46.004		12.68	0.000	0.000
					C	0.000	16.568		35.21	0.000	0.000
T2 150.00-140.00	145.00	1.526	28	66.055	A	5.292	37.009	11.905	28.14	0.000	0.000
					B	5.476	33.509		30.54	0.000	0.000
					C	5.476	13.755		61.91	0.000	0.000
T3 140.00-120.00	130.00	1.48	27	162.111	A	10.178	78.107	23.165	26.24	0.000	0.000
					B	9.618	88.149		23.69	0.000	0.000
					C	10.467	34.200		51.86	0.000	0.000
T4 120.00-100.00	110.00	1.411	26	202.528	A	13.676	106.080	24.703	20.63	0.000	0.000
					B	12.753	113.432		19.58	0.000	0.000
					C	13.085	91.822		23.55	0.000	0.000
T5 100.00-90.00	95.00	1.353	25	116.264	A	6.447	74.051	12.351	15.34	0.000	0.000
					B	6.082	56.716		19.67	0.000	0.000
					C	6.098	68.599		16.54	0.000	0.000
T6 90.00-80.00	85.00	1.31	24	126.517	A	6.849	74.983	13.283	16.23	0.000	0.000
					B	6.499	57.648		20.71	0.000	0.000
					C	6.420	72.265		16.88	0.000	0.000
T7 80.00-60.00	70.00	1.24	23	283.450	A	14.936	151.524	28.124	16.90	0.000	0.000
					B	14.269	116.854		21.45	0.000	0.000
					C	13.982	150.334		17.12	0.000	0.000
T8 60.00-40.00	50.00	1.126	21	323.362	A	19.403	151.709	28.309	16.54	0.000	0.000
					B	18.662	117.039		20.86	0.000	0.000
					C	18.343	150.519		16.76	0.000	0.000
T9 40.00-20.00	30.00	I	18	363.756	A	21.437	154.657	29.807	16.93	0.000	0.000
					B	20.722	119.987		21.18	0.000	0.000
					C	20.414	152.017		17.29	0.000	0.000
T10 20.00-0.00	10.00	I	18	404.134	A	26.964	113.371	31.276	22.29	0.000	0.000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 18 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
					B	26.446	90.836		26.67	0.000	0.000
					C	26.223	110.713		22.84	0.000	0.000

Tower Pressure - With Ice

$G_H = 1.125$

Section Elevation	z	K _Z	q _z	t _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	in	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T1 170.00-150.00	160.00	1.57	22	0.5000	104.583	A	3.517	82.422	9.167	10.67	0.000	0.000
						B	0.000	74.710		12.27	0.000	0.000
						C	3.517	27.757		29.31	0.000	0.000
T2 150.00-140.00	145.00	1.526	21	0.5000	66.890	A	6.957	58.049	20.033	30.82	0.000	0.000
						B	5.476	53.914		33.73	0.000	0.000
						C	7.234	23.901		64.34	0.000	0.000
T3 140.00-120.00	130.00	1.48	21	0.5000	163.780	A	13.549	124.661	38.924	28.16	0.000	0.000
						B	24.452	128.129		25.51	0.000	0.000
						C	13.984	54.140		57.14	0.000	0.000
T4 120.00-100.00	110.00	1.411	20	0.5000	204.197	A	17.047	155.568	40.814	23.64	0.000	0.000
						B	33.947	154.770		21.63	0.000	0.000
						C	25.867	115.341		28.90	0.000	0.000
T5 100.00-90.00	95.00	1.353	19	0.5000	117.098	A	8.148	100.462	20.407	18.79	0.000	0.000
						B	16.813	77.332		21.68	0.000	0.000
						C	14.140	81.784		21.27	0.000	0.000
T6 90.00-80.00	85.00	1.31	18	0.5000	127.351	A	8.553	101.798	21.609	19.58	0.000	0.000
						B	17.250	78.679		22.53	0.000	0.000
						C	16.035	85.234		21.34	0.000	0.000
T7 80.00-60.00	70.00	1.24	17	0.5000	285.119	A	18.347	206.096	45.303	20.18	0.000	0.000
						B	35.816	159.883		23.15	0.000	0.000
						C	34.534	178.571		21.26	0.000	0.000
T8 60.00-40.00	50.00	1.126	16	0.5000	325.031	A	22.803	207.064	45.704	19.88	0.000	0.000
						B	40.107	160.874		22.74	0.000	0.000
						C	38.778	179.569		20.93	0.000	0.000
T9 40.00-20.00	30.00	1	14	0.5000	365.425	A	24.841	212.976	47.784	20.09	0.000	0.000
						B	42.203	166.803		22.86	0.000	0.000
						C	40.890	182.252		21.41	0.000	0.000
T10 20.00-0.00	10.00	1	14	0.5000	405.803	A	29.168	162.109	49.862	26.07	0.000	0.000
						B	40.336	132.104		28.92	0.000	0.000
						C	39.449	140.036		27.78	0.000	0.000

Tower Pressure - Service

$G_H = 1.125$

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T1 170.00-150.00	160.00	1.57	10	102.917	A	0.000	52.765	5.833	11.06	0.000	0.000
					B	0.000	46.004		12.68	0.000	0.000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	19 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	z	K _z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	ft ²		ft ²	ft ²	ft ²		ft ²	ft ²
T2 150.00-140.00	145.00	1.526	10	66.055	C	0.000	16.568		35.21	0.000	0.000
					A	5.292	37.009	11,905	28.14	0.000	0.000
					B	5.476	33.509		30.54	0.000	0.000
T3 140.00-120.00	130.00	1.48	9	162.111	C	5.476	13.755		61.91	0.000	0.000
					A	10.178	78.107	23.165	26.24	0.000	0.000
					B	9.618	88.149		23.69	0.000	0.000
T4 120.00-100.00	110.00	1.411	9	202.528	C	10.467	34.200		51.86	0.000	0.000
					A	13.676	106.080	24.703	20.63	0.000	0.000
					B	12.753	113.432		19.58	0.000	0.000
T5 100.00-90.00	95.00	1.353	9	116.264	C	13.085	91.822		23.55	0.000	0.000
					A	6.447	74.051	12.351	15.34	0.000	0.000
					B	6.082	56.716		19.67	0.000	0.000
T6 90.00-80.00	85.00	1.31	8	126.517	C	6.098	68.599		16.54	0.000	0.000
					A	6.849	74.983	13.283	16.23	0.000	0.000
					B	6.499	57.648		20.71	0.000	0.000
T7 80.00-60.00	70.00	1.24	8	283.450	C	6.420	72.265		16.88	0.000	0.000
					A	14.936	151.524	28.124	16.90	0.000	0.000
					B	14.269	116.854		21.45	0.000	0.000
T8 60.00-40.00	50.00	1.126	7	323.362	C	13.982	150.334		17.12	0.000	0.000
					A	19.403	151.709	28.309	16.54	0.000	0.000
					B	18.662	117.039		20.86	0.000	0.000
T9 40.00-20.00	30.00	1	6	363.756	C	18.343	150.519		16.76	0.000	0.000
					A	21.437	154.657	29.807	16.93	0.000	0.000
					B	20.722	119.987		21.18	0.000	0.000
T10 20.00-0.00	10.00	1	6	404.134	C	20.414	152.017		17.29	0.000	0.000
					A	26.964	113.371	31.276	22.29	0.000	0.000
					B	26.446	90.836		26.67	0.000	0.000
					C	26.223	110.713		22.84	0.000	0.000

Tower Forces - No Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	1	1	37.149	2.29	114.29	A
			B	0.447	1.978	0.672	1	1	30.910			
			C	0.161	2.732	0.583	1	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	1	1	34.128	1.93	193.38	A
			B	0.59	1.81	0.748	1	1	30.529			
			C	0.291	2.32	0.613	1	1	13.910			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	1	1	66.514	4.23	211.37	B
			B	0.603	1.802	0.755	1	1	76.214			
			C	0.276	2.363	0.609	1	1	31.285			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	1	1	93.057	5.25	262.50	B
			B	0.623	1.792	0.768	1	1	99.866			
			C	0.518	1.878	0.707	1	1	77.988			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	1	1	66.761	3.34	333.60	A
			B	0.54	1.853	0.719	1	1	46.850			
			C	0.642	1.784	0.781	1	1	59.641			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	1	1	65.589	3.19	318.69	A
			B	0.507	1.891	0.701	1	1	46.917			
			C	0.622	1.792	0.767	1	1	61.867			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	1	1	127.956	5.98	299.04	A
			B	0.463	1.953	0.679	1	1	93.629			
			C	0.58	1.818	0.741	1	1	125.437			
T8	1.26	4.45	A	0.529	1.865	0.713	1	127.543	5.57	278.60	A	

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	20 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
60.00-40.00			B	0.42	2.026	0.66	1	1	95.887			
			C	0.522	1.873	0.709	1	1	125.073			
T9	1.27	5.44	A	0.484	1.922	0.69	1	1	128.076	5.12	255.98	A
40.00-20.00			B	0.387	2.091	0.646	1	1	98.271			
			C	0.474	1.936	0.685	1	1	124.485			
T10	0.83	6.08	A	0.347	2.178	0.631	1	1	98.557	4.47	223.27	A
20.00-0.00			B	0.29	2.322	0.613	1	1	82.124			
			C	0.339	2.198	0.629	1	1	95.812			
Sum Weight:	7.61	30.71						OTM	3256.52 kip-ft	41.36		

Tower Forces - No Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.825	1	37.149	2.29	114.29	A
170.00-150.00			B	0.447	1.978	0.672	0.825	1	30.910			
			C	0.161	2.732	0.583	0.825	1	9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.825	1	33.202	1.88	188.14	A
150.00-140.00			B	0.59	1.81	0.748	0.825	1	29.570			
			C	0.291	2.32	0.613	0.825	1	12.952			
T3	0.44	2.09	A	0.545	1.849	0.721	0.825	1	64.733	4.13	206.70	B
140.00-120.00			B	0.603	1.802	0.755	0.825	1	74.531			
			C	0.276	2.363	0.609	0.825	1	29.454			
T4	0.91	2.80	A	0.591	1.81	0.748	0.825	1	90.664	5.13	256.63	B
120.00-100.00			B	0.623	1.792	0.768	0.825	1	97.634			
			C	0.518	1.878	0.707	0.825	1	75.698			
T5	0.62	1.48	A	0.692	1.776	0.814	0.825	1	65.632	3.28	327.96	A
100.00-90.00			B	0.54	1.853	0.719	0.825	1	45.785			
			C	0.642	1.784	0.781	0.825	1	58.574			
T6	0.63	1.76	A	0.647	1.782	0.783	0.825	1	64.390	3.13	312.87	A
90.00-80.00			B	0.507	1.891	0.701	0.825	1	45.780			
			C	0.622	1.792	0.767	0.825	1	60.743			
T7	1.26	4.33	A	0.587	1.812	0.746	0.825	1	125.342	5.86	292.93	A
80.00-60.00			B	0.463	1.953	0.679	0.825	1	91.132			
			C	0.58	1.818	0.741	0.825	1	122.990			
T8	1.26	4.45	A	0.529	1.865	0.713	0.825	1	124.147	5.42	271.18	A
60.00-40.00			B	0.42	2.026	0.66	0.825	1	92.621			
			C	0.522	1.873	0.709	0.825	1	121.863			
T9	1.27	5.44	A	0.484	1.922	0.69	0.825	1	124.325	4.97	248.49	A
40.00-20.00			B	0.387	2.091	0.646	0.825	1	94.645			
			C	0.474	1.936	0.685	0.825	1	120.912			
T10	0.83	6.08	A	0.347	2.178	0.631	0.825	1	93.838	4.25	212.58	A
20.00-0.00			B	0.29	2.322	0.613	0.825	1	77.496			
			C	0.339	2.198	0.629	0.825	1	91.223			
Sum Weight:	7.61	30.71						OTM	3190.95 kip-ft	40.35		

Tower Forces - No Ice - Wind 60 To Face

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 21 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C _F	R _R	D _F	D _R	A _E ft ²	F K	w plf	Ctrl. Face
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.8	1	37.149	2.29	114.29	A
			B	0.447	1.978	0.672	0.8	1	30.910			
			C	0.161	2.732	0.583	0.8	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.8	1	33.069	1.87	187.39	A
			B	0.59	1.81	0.748	0.8	1	29.433			
			C	0.291	2.32	0.613	0.8	1	12.815			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.8	1	64.478	4.12	206.03	B
			B	0.603	1.802	0.755	0.8	1	74.291			
			C	0.276	2.363	0.609	0.8	1	29.192			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.8	1	90.322	5.12	255.80	B
			B	0.623	1.792	0.768	0.8	1	97.316			
			C	0.518	1.878	0.707	0.8	1	75.371			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.8	1	65.471	3.27	327.16	A
			B	0.54	1.853	0.719	0.8	1	45.633			
			C	0.642	1.784	0.781	0.8	1	58.421			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.8	1	64.219	3.12	312.03	A
			B	0.507	1.891	0.701	0.8	1	45.617			
			C	0.622	1.792	0.767	0.8	1	60.583			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.8	1	124.968	5.84	292.06	A
			B	0.463	1.953	0.679	0.8	1	90.775			
			C	0.58	1.818	0.741	0.8	1	122.641			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.8	1	123.662	5.40	270.13	A
			B	0.42	2.026	0.66	0.8	1	92.154			
			C	0.522	1.873	0.709	0.8	1	121.404			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.8	1	123.789	4.95	247.41	A
			B	0.387	2.091	0.646	0.8	1	94.127			
			C	0.474	1.936	0.685	0.8	1	120.402			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.8	1	93.164	4.22	211.05	A
			B	0.29	2.322	0.613	0.8	1	76.835			
			C	0.339	2.198	0.629	0.8	1	90.567			
Sum Weight:	7.61	30.71						OTM	3181.59 kip-ft	40.20		

Tower Forces - No Ice - Wind 90 To Face

Section Elevation ft	Add Weight K	Self Weight K	F a c e	e	C _F	R _R	D _F	D _R	A _E ft ²	F K	w plf	Ctrl. Face
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.85	1	37.149	2.29	114.29	A
			B	0.447	1.978	0.672	0.85	1	30.910			
			C	0.161	2.732	0.583	0.85	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.85	1	33.334	1.89	188.89	A
			B	0.59	1.81	0.748	0.85	1	29.707			
			C	0.291	2.32	0.613	0.85	1	13.089			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.85	1	64.987	4.15	207.37	B
			B	0.603	1.802	0.755	0.85	1	74.772			
			C	0.276	2.363	0.609	0.85	1	29.715			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.85	1	91.006	5.15	257.47	B
			B	0.623	1.792	0.768	0.85	1	97.953			
			C	0.518	1.878	0.707	0.85	1	76.025			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.85	1	65.794	3.29	328.77	A
			B	0.54	1.853	0.719	0.85	1	45.937			
			C	0.642	1.784	0.781	0.85	1	58.726			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.85	1	64.561	3.14	313.70	A
			B	0.507	1.891	0.701	0.85	1	45.942			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	22 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T7 80.00-60.00	1.26	4.33	C	0.622	1.792	0.767	0.85	1	60.904	5.88	293.80	A
			A	0.587	1.812	0.746	0.85	1	125.715			
			B	0.463	1.953	0.679	0.85	1	91.488			
T8 60.00-40.00	1.26	4.45	C	0.58	1.818	0.741	0.85	1	123.340	5.44	272.24	A
			A	0.529	1.865	0.713	0.85	1	124.632			
			B	0.42	2.026	0.66	0.85	1	93.087			
T9 40.00-20.00	1.27	5.44	C	0.522	1.873	0.709	0.85	1	122.322	4.99	249.56	A
			A	0.484	1.922	0.69	0.85	1	124.860			
			B	0.387	2.091	0.646	0.85	1	95.163			
T10 20.00-0.00	0.83	6.08	C	0.474	1.936	0.685	0.85	1	121.422	4.28	214.10	A
			A	0.347	2.178	0.631	0.85	1	94.512			
			B	0.29	2.322	0.613	0.85	1	78.157			
Sum Weight:	7.61	30.71	C	0.339	2.198	0.629	0.85	1	91.878	40.49		
								OTM	3200.32 kip-ft			

Tower Forces - With Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	1	1	78.881	3.54	177.15	A
			B	0.714	1.778	0.83	1	1	62.028			
			C	0.299	2.299	0.616	1	1	20.604			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	1	1	65.006	3.16	316.37	A
			B	0.888	1.907	0.972	1	1	57.882			
			C	0.465	1.949	0.68	1	1	23.498			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	1	1	129.881	6.95	347.34	B
			B	0.932	1.972	1	1	1	152.582			
			C	0.416	2.033	0.658	1	1	49.621			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	1	1	162.417	8.14	407.09	B
			B	0.924	1.96	1	1	1	188.717			
			C	0.692	1.776	0.814	1	1	119.741			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	1	1	108.610	4.51	450.57	A
			B	0.804	1.819	0.9	1	1	86.385			
			C	0.819	1.831	0.912	1	1	88.747			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	1	1	105.559	4.06	405.79	A
			B	0.753	1.789	0.859	1	1	84.866			
			C	0.795	1.813	0.892	1	1	92.106			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	1	1	200.955	7.02	351.19	A
			B	0.686	1.776	0.81	1	1	165.364			
			C	0.747	1.786	0.855	1	1	187.195			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	1	1	193.648	6.04	302.22	A
			B	0.618	1.794	0.765	1	1	163.176			
			C	0.672	1.777	0.8	1	1	182.461			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	1	1	192.241	5.34	267.14	A
			B	0.572	1.824	0.737	1	1	165.109			
			C	0.611	1.798	0.76	1	1	179.432			
T10 20.00-0.00	2.30	8.52	A	0.471	1.94	0.683	1	1	139.939	4.24	211.79	A
			B	0.425	2.017	0.662	1	1	127.801			
			C	0.442	1.986	0.67	1	1	133.241			
Sum Weight:	21.02	45.71						OTM	4593.81 kip-ft	53.01		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	23 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Tower Forces - With Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.825	1	78.265	3.52	175.77	A
			B	0.714	1.778	0.83	0.825	1	62.028			
			C	0.299	2.299	0.616	0.825	1	19.988			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.825	1	63.789	3.10	310.45	A
			B	0.888	1.907	0.972	0.825	1	56.923			
			C	0.465	1.949	0.68	0.825	1	22.232			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.825	1	127.510	6.75	337.60	B
			B	0.932	1.972	1	0.825	1	148.302			
			C	0.416	2.033	0.658	0.825	1	47.174			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.825	1	159.433	7.89	394.28	B
			B	0.924	1.96	1	0.825	1	182.776			
			C	0.692	1.776	0.814	0.825	1	115.214			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	0.825	1	107.184	4.45	444.65	A
			B	0.804	1.819	0.9	0.825	1	83.443			
			C	0.819	1.831	0.912	0.825	1	86.273			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	0.825	1	104.062	4.00	400.04	A
			B	0.753	1.789	0.859	0.825	1	81.847			
			C	0.795	1.813	0.892	0.825	1	89.300			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	0.825	1	197.745	6.91	345.58	A
			B	0.686	1.776	0.81	0.825	1	159.096			
			C	0.747	1.786	0.855	0.825	1	181.152			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	0.825	1	189.657	5.92	295.99	A
			B	0.618	1.794	0.765	0.825	1	156.157			
			C	0.672	1.777	0.8	0.825	1	175.675			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	0.825	1	187.894	5.22	261.10	A
			B	0.572	1.824	0.737	0.825	1	157.723			
			C	0.611	1.798	0.76	0.825	1	172.276			
T10 20.00-0.00	2.30	8.52	A	0.471	1.94	0.683	0.825	1	134.834	4.08	204.06	A
			B	0.425	2.017	0.662	0.825	1	120.742			
			C	0.442	1.986	0.67	0.825	1	126.338			
Sum Weight:	21.02	45.71						OTM	4497.51 kip-ft	51.84		

Tower Forces - With Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.8	1	78.177	3.51	175.57	A
			B	0.714	1.778	0.83	0.8	1	62.028			
			C	0.299	2.299	0.616	0.8	1	19.901			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.8	1	63.615	3.10	309.60	A
			B	0.888	1.907	0.972	0.8	1	56.786			
			C	0.465	1.949	0.68	0.8	1	22.051			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.8	1	127.171	6.72	336.21	B
			B	0.932	1.972	1	0.8	1	147.691			
			C	0.416	2.033	0.658	0.8	1	46.824			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.8	1	159.007	7.85	392.45	B
			B	0.924	1.96	1	0.8	1	181.928			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	24 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T5 100.00-90.00	1.67	2.39	C	0.692	1.776	0.814	0.8	1	114.568	4.44	443.81	A
			A	0.928	1.966	1	0.8	1	106.980			
			B	0.804	1.819	0.9	0.8	1	83.022			
T6 90.00-80.00	1.71	2.70	C	0.819	1.831	0.912	0.8	1	85.919	3.99	399.21	A
			A	0.867	1.88	0.953	0.8	1	103.848			
			B	0.753	1.789	0.859	0.8	1	81.415			
T7 80.00-60.00	3.48	6.30	C	0.795	1.813	0.892	0.8	1	88.899	6.90	344.78	A
			A	0.787	1.807	0.886	0.8	1	197.286			
			B	0.686	1.776	0.81	0.8	1	158.201			
T8 60.00-40.00	3.48	6.58	C	0.747	1.786	0.855	0.8	1	180.289	5.90	295.10	A
			A	0.707	1.777	0.825	0.8	1	189.087			
			B	0.618	1.794	0.765	0.8	1	155.155			
T9 40.00-20.00	3.51	7.67	C	0.672	1.777	0.8	0.8	1	174.705	5.20	260.23	A
			A	0.651	1.781	0.786	0.8	1	187.273			
			B	0.572	1.824	0.737	0.8	1	156.668			
T10 20.00-0.00	2.30	8.52	C	0.611	1.798	0.76	0.8	1	171.254	4.06	202.96	A
			A	0.471	1.94	0.683	0.8	1	134.105			
			B	0.425	2.017	0.662	0.8	1	119.734			
Sum Weight:	21.02	45.71						OTM	4483.75 kip-ft	51.67		

Tower Forces - With Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.85	1	78.353	3.52	175.96	A
			B	0.714	1.778	0.83	0.85	1	62.028			
			C	0.299	2.299	0.616	0.85	1	20.076			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.85	1	63.963	3.11	311.30	A
			B	0.888	1.907	0.972	0.85	1	57.060			
			C	0.465	1.949	0.68	0.85	1	22.413			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.85	1	127.849	6.78	338.99	B
			B	0.932	1.972	1	0.85	1	148.914			
			C	0.416	2.033	0.658	0.85	1	47.523			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.85	1	159.860	7.92	396.11	B
			B	0.924	1.96	1	0.85	1	183.625			
			C	0.692	1.776	0.814	0.85	1	115.861			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	0.85	1	107.387	4.45	445.50	A
			B	0.804	1.819	0.9	0.85	1	83.863			
			C	0.819	1.831	0.912	0.85	1	86.626			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	0.85	1	104.276	4.01	400.86	A
			B	0.753	1.789	0.859	0.85	1	82.278			
			C	0.795	1.813	0.892	0.85	1	89.701			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	0.85	1	198.203	6.93	346.38	A
			B	0.686	1.776	0.81	0.85	1	159.991			
			C	0.747	1.786	0.855	0.85	1	182.015			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	0.85	1	190.227	5.94	296.88	A
			B	0.618	1.794	0.765	0.85	1	157.160			
			C	0.672	1.777	0.8	0.85	1	176.644			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	0.85	1	188.515	5.24	261.96	A
			B	0.572	1.824	0.737	0.85	1	158.778			
			C	0.611	1.798	0.76	0.85	1	173.298			
T10	2.30	8.52	A	0.471	1.94	0.683	0.85	1	135.564	4.10	205.17	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	25 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
20.00-0.00			B	0.425	2.017	0.662	0.85	1	121.751			
			C	0.442	1.986	0.67	0.85	1	127.324			
Sum Weight:	21.02	45.71						OTM	4511.26 kip-ft	52.01		

Tower Forces - Service - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	1	1	37.149	0.79	39.55	A
170.00-150.00			B	0.447	1.978	0.672	1	1	30.910			
			C	0.161	2.732	0.583	1	1	9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	1	1	34.128	0.67	66.92	A
150.00-140.00			B	0.59	1.81	0.748	1	1	30.529			
			C	0.291	2.32	0.613	1	1	13.910			
T3	0.44	2.09	A	0.545	1.849	0.721	1	1	66.514	1.46	73.14	B
140.00-120.00			B	0.603	1.802	0.755	1	1	76.214			
			C	0.276	2.363	0.609	1	1	31.285			
T4	0.91	2.80	A	0.591	1.81	0.748	1	1	93.057	1.82	90.83	B
120.00-100.00			B	0.623	1.792	0.768	1	1	99.866			
			C	0.518	1.878	0.707	1	1	77.988			
T5	0.62	1.48	A	0.692	1.776	0.814	1	1	66.761	1.15	115.43	A
100.00-90.00			B	0.54	1.853	0.719	1	1	46.850			
			C	0.642	1.784	0.781	1	1	59.641			
T6	0.63	1.76	A	0.647	1.782	0.783	1	1	65.589	1.10	110.27	A
90.00-80.00			B	0.507	1.891	0.701	1	1	46.917			
			C	0.622	1.792	0.767	1	1	61.867			
T7	1.26	4.33	A	0.587	1.812	0.746	1	1	127.956	2.07	103.47	A
80.00-60.00			B	0.463	1.953	0.679	1	1	93.629			
			C	0.58	1.818	0.741	1	1	125.437			
T8	1.26	4.45	A	0.529	1.865	0.713	1	1	127.543	1.93	96.40	A
60.00-40.00			B	0.42	2.026	0.66	1	1	95.887			
			C	0.522	1.873	0.709	1	1	125.073			
T9	1.27	5.44	A	0.484	1.922	0.69	1	1	128.076	1.77	88.58	A
40.00-20.00			B	0.387	2.091	0.646	1	1	98.271			
			C	0.474	1.936	0.685	1	1	124.485			
T10	0.83	6.08	A	0.347	2.178	0.631	1	1	98.557	1.55	77.25	A
20.00-0.00			B	0.29	2.322	0.613	1	1	82.124			
			C	0.339	2.198	0.629	1	1	95.812			
Sum Weight:	7.61	30.71						OTM	1126.82 kip-ft	14.31		

Tower Forces - Service - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.825	1	37.149	0.79	39.55	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 26 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
170.00-150.00			B	0.447	1.978	0.672	0.825		30.910			
			C	0.161	2.732	0.583	0.825		9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.825		33.202	0.65	65.10	A
150.00-140.00			B	0.59	1.81	0.748	0.825		29.570			
			C	0.291	2.32	0.613	0.825		12.952			
T3	0.44	2.09	A	0.545	1.849	0.721	0.825		64.733	1.43	71.52	B
140.00-120.00			B	0.603	1.802	0.755	0.825		74.531			
			C	0.276	2.363	0.609	0.825		29.454			
T4	0.91	2.80	A	0.591	1.81	0.748	0.825		90.664	1.78	88.80	B
120.00-100.00			B	0.623	1.792	0.768	0.825		97.634			
			C	0.518	1.878	0.707	0.825		75.698			
T5	0.62	1.48	A	0.692	1.776	0.814	0.825		65.632	1.13	113.48	A
100.00-90.00			B	0.54	1.853	0.719	0.825		45.785			
			C	0.642	1.784	0.781	0.825		58.574			
T6	0.63	1.76	A	0.647	1.782	0.783	0.825		64.390	1.08	108.26	A
90.00-80.00			B	0.507	1.891	0.701	0.825		45.780			
			C	0.622	1.792	0.767	0.825		60.743			
T7	1.26	4.33	A	0.587	1.812	0.746	0.825		125.342	2.03	101.36	A
80.00-60.00			B	0.463	1.953	0.679	0.825		91.132			
			C	0.58	1.818	0.741	0.825		122.990			
T8	1.26	4.45	A	0.529	1.865	0.713	0.825		124.147	1.88	93.84	A
60.00-40.00			B	0.42	2.026	0.66	0.825		92.621			
			C	0.522	1.873	0.709	0.825		121.863			
T9	1.27	5.44	A	0.484	1.922	0.69	0.825		124.325	1.72	85.98	A
40.00-20.00			B	0.387	2.091	0.646	0.825		94.645			
			C	0.474	1.936	0.685	0.825		120.912			
T10	0.83	6.08	A	0.347	2.178	0.631	0.825		93.838	1.47	73.56	A
20.00-0.00			B	0.29	2.322	0.613	0.825		77.496			
			C	0.339	2.198	0.629	0.825		91.223			
Sum Weight:	7.61	30.71						OTM	1104.14 kip-ft	13.96		

Tower Forces - Service - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.8		37.149	0.79	39.55	A
170.00-150.00			B	0.447	1.978	0.672	0.8		30.910			
			C	0.161	2.732	0.583	0.8		9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.8		33.069	0.65	64.84	A
150.00-140.00			B	0.59	1.81	0.748	0.8		29.433			
			C	0.291	2.32	0.613	0.8		12.815			
T3	0.44	2.09	A	0.545	1.849	0.721	0.8		64.478	1.43	71.29	B
140.00-120.00			B	0.603	1.802	0.755	0.8		74.291			
			C	0.276	2.363	0.609	0.8		29.192			
T4	0.91	2.80	A	0.591	1.81	0.748	0.8		90.322	1.77	88.51	B
120.00-100.00			B	0.623	1.792	0.768	0.8		97.316			
			C	0.518	1.878	0.707	0.8		75.371			
T5	0.62	1.48	A	0.692	1.776	0.814	0.8		65.471	1.13	113.20	A
100.00-90.00			B	0.54	1.853	0.719	0.8		45.633			
			C	0.642	1.784	0.781	0.8		58.421			
T6	0.63	1.76	A	0.647	1.782	0.783	0.8		64.219	1.08	107.97	A
90.00-80.00			B	0.507	1.891	0.701	0.8		45.617			
			C	0.622	1.792	0.767	0.8		60.583			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 27 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.8	1	124.968	2.02	101.06	A
			B	0.463	1.953	0.679	0.8	1	90.775			
			C	0.58	1.818	0.741	0.8	1	122.641			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.8	1	123.662	1.87	93.47	A
			B	0.42	2.026	0.66	0.8	1	92.154			
			C	0.522	1.873	0.709	0.8	1	121.404			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.8	1	123.789	1.71	85.61	A
			B	0.387	2.091	0.646	0.8	1	94.127			
			C	0.474	1.936	0.685	0.8	1	120.402			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.8	1	93.164	1.46	73.03	A
			B	0.29	2.322	0.613	0.8	1	76.835			
			C	0.339	2.198	0.629	0.8	1	90.567			
Sum Weight:	7.61	30.71						OTM	1100.90 kip-ft	13.91		

Tower Forces - Service - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.85	1	37.149	0.79	39.55	A
			B	0.447	1.978	0.672	0.85	1	30.910			
			C	0.161	2.732	0.583	0.85	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.85	1	33.334	0.65	65.36	A
			B	0.59	1.81	0.748	0.85	1	29.707			
			C	0.291	2.32	0.613	0.85	1	13.089			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.85	1	64.987	1.44	71.75	B
			B	0.603	1.802	0.755	0.85	1	74.772			
			C	0.276	2.363	0.609	0.85	1	29.715			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.85	1	91.006	1.78	89.09	B
			B	0.623	1.792	0.768	0.85	1	97.953			
			C	0.518	1.878	0.707	0.85	1	76.025			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.85	1	65.794	1.14	113.76	A
			B	0.54	1.853	0.719	0.85	1	45.937			
			C	0.642	1.784	0.781	0.85	1	58.726			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.85	1	64.561	1.09	108.55	A
			B	0.507	1.891	0.701	0.85	1	45.942			
			C	0.622	1.792	0.767	0.85	1	60.904			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.85	1	125.715	2.03	101.66	A
			B	0.463	1.953	0.679	0.85	1	91.488			
			C	0.58	1.818	0.741	0.85	1	123.340			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.85	1	124.632	1.88	94.20	A
			B	0.42	2.026	0.66	0.85	1	93.087			
			C	0.522	1.873	0.709	0.85	1	122.322			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.85	1	124.860	1.73	86.35	A
			B	0.387	2.091	0.646	0.85	1	95.163			
			C	0.474	1.936	0.685	0.85	1	121.422			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.85	1	94.512	1.48	74.08	A
			B	0.29	2.322	0.613	0.85	1	78.157			
			C	0.339	2.198	0.629	0.85	1	91.878			
Sum Weight:	7.61	30.71						OTM	1107.38 kip-ft	14.01		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 28 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Force Totals

Load Case	Vertical Forces <i>K</i>	Sum of Forces <i>X</i> <i>K</i>	Sum of Forces <i>Z</i> <i>K</i>	Sum of Overturning Moments, <i>M_x</i> <i>kip-ft</i>	Sum of Overturning Moments, <i>M_z</i> <i>kip-ft</i>	Sum of Torques <i>kip-ft</i>
Leg Weight	19.74					
Bracing Weight	10.97					
Total Member Self-Weight	30.71			-2.00	10.22	
Total Weight	51.55			-2.00	10.22	
Wind 0 deg - No Ice		-0.03	-59.60	-5708.32	12.35	-22.92
Wind 30 deg - No Ice		29.27	-50.81	-4890.66	-2805.15	-22.82
Wind 45 deg - No Ice		41.56	-41.28	-3973.98	-3999.37	-20.02
Wind 60 deg - No Ice		50.83	-29.04	-2795.45	-4898.94	-15.82
Wind 90 deg - No Ice		58.77	0.23	26.18	-5648.79	-5.72
Wind 120 deg - No Ice		51.69	30.08	2874.97	-4945.01	6.21
Wind 135 deg - No Ice		41.56	41.56	3993.08	-4000.25	11.52
Wind 150 deg - No Ice		29.55	50.94	4892.75	-2842.34	16.76
Wind 180 deg - No Ice		0.21	58.66	5652.84	-15.14	24.54
Wind 210 deg - No Ice		-29.36	50.86	4884.68	2840.92	23.16
Wind 225 deg - No Ice		-41.43	41.46	3982.65	4006.43	20.78
Wind 240 deg - No Ice		-51.57	29.98	2864.78	4952.07	18.07
Wind 270 deg - No Ice		-58.70	0.09	11.35	5659.73	7.95
Wind 300 deg - No Ice		-50.74	-29.22	-2816.52	4905.15	-3.95
Wind 315 deg - No Ice		-41.50	-41.41	-3988.74	4008.72	-9.92
Wind 330 deg - No Ice		-29.33	-50.88	-4897.98	2829.75	-16.05
Member Ice	15.00					
Total Weight Ice	85.61			-2.54	25.10	
Wind 0 deg - Ice		-0.02	-69.88	-6864.28	26.49	-19.54
Wind 30 deg - Ice		34.37	-59.62	-5870.13	-3357.00	-25.65
Wind 45 deg - Ice		48.70	-48.47	-4773.44	-4775.85	-25.79
Wind 60 deg - Ice		59.54	-34.13	-3360.98	-5848.07	-24.11
Wind 90 deg - Ice		68.91	0.18	19.71	-6761.26	-17.16
Wind 120 deg - Ice		60.58	35.16	3446.86	-5927.99	-5.57
Wind 135 deg - Ice		48.70	48.69	4786.02	-4776.18	1.27
Wind 150 deg - Ice		34.59	59.71	5869.30	-3386.36	8.22
Wind 180 deg - Ice		0.16	68.72	6767.76	5.09	20.94
Wind 210 deg - Ice		-34.44	59.65	5863.16	3419.61	25.93
Wind 225 deg - Ice		-48.60	48.61	4778.12	4815.41	26.40
Wind 240 deg - Ice		-60.49	35.08	3439.26	5967.79	26.20
Wind 270 deg - Ice		-68.86	0.07	8.47	6803.85	18.94
Wind 300 deg - Ice		-59.46	-34.27	-3377.31	5886.54	7.00
Wind 315 deg - Ice		-48.65	-48.57	-4784.82	4816.70	0.01
Wind 330 deg - Ice		-34.41	-59.67	-5875.67	3409.98	-7.66
Total Weight	51.55			-2.00	10.22	
Wind 0 deg - Service		-0.01	-20.62	-1978.70	2.07	-7.93
Wind 30 deg - Service		10.13	-17.58	-1695.77	-972.85	-7.90
Wind 45 deg - Service		14.38	-14.28	-1378.58	-1386.07	-6.93
Wind 60 deg - Service		17.59	-10.05	-970.79	-1697.34	-5.47
Wind 90 deg - Service		20.33	0.08	5.56	-1956.81	-1.98
Wind 120 deg - Service		17.89	10.41	991.30	-1713.28	2.15
Wind 135 deg - Service		14.38	14.38	1378.19	-1386.38	3.99
Wind 150 deg - Service		10.23	17.63	1689.49	-985.71	5.80
Wind 180 deg - Service		0.07	20.30	1952.50	-7.45	8.49
Wind 210 deg - Service		-10.16	17.60	1686.70	980.81	8.01
Wind 225 deg - Service		-14.34	14.35	1374.58	1384.10	7.19
Wind 240 deg - Service		-17.85	10.37	987.77	1711.31	6.25
Wind 270 deg - Service		-20.31	0.03	0.42	1956.18	2.75
Wind 300 deg - Service		-17.56	-10.11	-978.08	1695.07	-1.37
Wind 315 deg - Service		-14.36	-14.33	-1383.69	1384.89	-3.43
Wind 330 deg - Service		-10.15	-17.61	-1698.30	976.95	-5.55

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PiROD U20'-0"x170' Lattice Tower	Page	29 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice+Temp
19	Dead+Wind 0 deg+Ice+Temp
20	Dead+Wind 30 deg+Ice+Temp
21	Dead+Wind 45 deg+Ice+Temp
22	Dead+Wind 60 deg+Ice+Temp
23	Dead+Wind 90 deg+Ice+Temp
24	Dead+Wind 120 deg+Ice+Temp
25	Dead+Wind 135 deg+Ice+Temp
26	Dead+Wind 150 deg+Ice+Temp
27	Dead+Wind 180 deg+Ice+Temp
28	Dead+Wind 210 deg+Ice+Temp
29	Dead+Wind 225 deg+Ice+Temp
30	Dead+Wind 240 deg+Ice+Temp
31	Dead+Wind 270 deg+Ice+Temp
32	Dead+Wind 300 deg+Ice+Temp
33	Dead+Wind 315 deg+Ice+Temp
34	Dead+Wind 330 deg+Ice+Temp
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	30 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft		
T1	170 - 150	Leg	Max Tension	22	29.76	-0.04	0.05		
			Max. Compression	19	-35.99	-0.00	0.45		
			Max. Mx	24	-35.74	-0.38	-0.24		
			Max. My	19	-35.99	-0.00	0.45		
			Max. Vy	30	-3.91	0.05	-0.06		
		Diagonal	Max. Vx	19	-4.53	-0.00	0.45		
			Max Tension	26	3.41	0.00	0.00		
			Max. Compression	26	-3.46	0.00	0.00		
			Max. Mx	19	2.89	-0.00	0.00		
			Max. My	22	-2.08	-0.00	0.00		
		Top Girt	Max. Vy	19	0.01	-0.00	0.00		
			Max. Vx	21	0.00	0.00	0.00		
			Max Tension	7	0.30	0.00	0.00		
			Max. Compression	15	-0.33	0.00	0.00		
			Max. Mx	18	-0.01	0.01	0.00		
		Bottom Girt	Max. My	31	0.01	0.00	-0.00		
			Max. Vy	18	-0.01	0.00	0.00		
			Max. Vx	31	0.00	0.00	0.00		
			Max Tension	15	0.15	0.00	0.00		
			Max. Compression	13	-0.15	0.00	0.00		
T2	150 - 140	Leg	Max. Mx	18	-0.00	0.01	0.00		
			Max. My	31	-0.01	0.00	-0.00		
			Max. Vy	18	-0.01	0.00	0.00		
			Max. Vx	31	0.00	0.00	0.00		
			Max Tension	22	35.03	-0.42	0.02		
		Diagonal	Max. Compression	19	-41.87	2.80	0.28		
			Max. Mx	22	34.40	-3.29	0.23		
			Max. My	34	-3.47	-0.26	4.03		
			Max. Vy	27	0.63	-3.27	-0.36		
			Max. Vx	30	0.87	-1.76	-3.61		
		Top Girt	Max Tension	22	4.91	0.00	0.00		
			Max. Compression	30	-5.45	0.00	0.00		
			Max. Mx	22	4.33	0.05	0.00		
			Max. My	21	-4.23	-0.02	0.02		
			Max. Vy	22	0.02	0.05	0.00		
		T3	140 - 120	Leg	Max. Vx	21	-0.00	0.00	0.00
					Max Tension	5	0.42	0.00	0.00
					Max. Compression	2	-0.37	0.00	0.00
					Max. Mx	18	0.04	-0.02	0.00
					Max. My	30	0.22	0.00	0.00
T4	120 - 100	Leg	Max. Vy	18	0.02	0.00	0.00		
			Max. Vx	30	-0.00	0.00	0.00		
			Max Tension	32	70.49	-3.70	-0.17		
			Max. Compression	19	-84.43	3.69	0.03		
			Max. Mx	32	69.34	-4.52	-0.16		
		Diagonal	Max. My	31	-8.47	-0.42	-6.63		
			Max. Vy	27	0.69	-4.46	-0.05		
			Max. Vx	23	-0.99	-0.41	6.59		
			Max Tension	28	9.08	0.00	0.00		
			Max. Compression	29	-9.44	0.00	0.00		
T4	120 - 100	Leg	Max. Mx	19	5.84	0.11	0.01		
			Max. My	29	-7.63	-0.06	-0.02		
			Max. Vy	19	-0.03	0.11	0.01		
			Max. Vx	21	-0.00	0.00	0.00		
			Max Tension	32	117.19	-5.13	-0.02		
T4	120 - 100	Leg	Max. Compression	19	-138.35	3.39	0.04		
			Max. Mx	19	-109.85	6.13	0.00		
			Max. My	31	-11.38	-0.47	-7.36		
			Max. Vy	32	0.98	-4.27	-0.10		
			Max. Vx	31	1.72	-0.47	-7.36		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	31 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft		
T5	100 - 90	Diagonal	Max Tension	21	11.55	0.00	0.00		
			Max. Compression	29	-12.57	0.00	0.00		
			Max. Mx	19	7.08	0.13	0.01		
			Max. My	29	-12.53	-0.06	-0.05		
			Max. Vy	32	0.04	0.12	-0.00		
		Mid Girt	Max. Vx	29	0.01	0.00	0.00		
			Max Tension	32	3.92	0.00	0.00		
			Max. Compression	19	-3.17	0.00	0.00		
			Max. Mx	18	0.41	-0.07	0.00		
			Max. My	30	2.10	0.00	0.00		
		T6	90 - 80	Leg	Max. Vy	18	-0.03	0.00	0.00
					Max. Vx	30	-0.00	0.00	0.00
					Max Tension	32	144.94	-4.27	-0.10
					Max. Compression	19	-170.56	4.60	0.02
					Max. Mx	19	-170.56	4.60	0.02
Diagonal	Max. My			31	-12.60	-0.47	-7.36		
	Max. Vy			19	-0.25	4.60	0.02		
	Max. Vx			31	-0.49	-0.47	-7.36		
	Max Tension			28	13.49	0.00	0.00		
	Max. Compression			28	-13.72	0.00	0.00		
T7	80 - 60			Leg	Max. Mx	19	10.36	0.18	0.01
					Max. My	30	-0.61	0.09	-0.02
					Max. Vy	19	-0.05	0.18	0.01
					Max. Vx	30	-0.00	0.00	0.00
					Max Tension	32	173.18	-4.32	0.01
		Diagonal	Max. Compression	19	-202.06	5.78	0.05		
			Max. Mx	30	-201.28	5.78	-0.12		
			Max. My	31	-14.57	-0.00	-4.70		
			Max. Vy	27	0.39	-5.71	-0.06		
			Max. Vx	31	0.28	-0.00	-4.70		
		T8	60 - 40	Leg	Max Tension	32	225.41	-5.01	0.02
					Max. Compression	19	-261.48	5.55	0.01
					Max. Mx	30	-230.77	5.78	-0.12
					Max. My	34	-15.61	-0.08	5.19
					Max. Vy	22	-0.22	-5.69	0.11
Diagonal	Max. Vx			34	-0.21	-0.08	5.19		
	Max Tension			28	13.78	0.00	0.00		
	Max. Compression			28	-14.16	0.00	0.00		
	Max. Mx			19	10.54	0.15	0.01		
	Max. My			21	-13.53	0.02	0.02		
T9	40 - 20			Leg	Max. Vy	32	0.05	0.15	-0.01
					Max. Vx	21	-0.00	0.00	0.00
					Max Tension	32	273.18	-5.02	0.02
					Max. Compression	30	-317.16	5.46	-0.09
					Max. Mx	32	272.62	-6.90	-0.01
		Diagonal	Max. My	34	-20.30	0.06	5.99		
			Max. Vy	22	0.31	-6.89	0.07		
			Max. Vx	26	0.22	0.05	-5.96		
			Max Tension	28	13.88	0.00	0.00		
			Max. Compression	28	-14.24	0.00	0.00		
		Leg	Max. Mx	30	10.13	0.21	-0.01		
			Max. My	21	-13.64	0.00	0.03		
			Max. Vy	30	-0.06	0.21	-0.01		
			Max. Vx	21	-0.00	0.00	0.00		
			Max Tension	32	315.77	-3.05	0.03		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	32 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T10	20 - 0	Diagonal	Max. Compression	30	-370.16	-0.26	0.02
			Max. Mx	32	315.12	-11.58	0.02
			Max. My	31	-21.23	-0.76	-5.82
			Max. Vy	22	0.97	-11.56	-0.01
			Max. Vx	34	0.25	2.49	5.73
			Max Tension	28	15.13	0.00	0.00
			Max. Compression	28	-14.76	0.00	0.00
			Max. Mx	30	10.20	0.23	-0.02
			Max. My	28	-13.32	0.04	-0.03
			Max. Vy	32	0.07	0.21	-0.02
			Max. Vx	21	-0.00	0.00	0.00
			Max Tension	32	352.05	3.77	0.03
		Diagonal	Max. Compression	30	-419.98	-0.00	-0.00
			Max. Mx	30	-391.92	15.47	0.01
			Max. My	31	-30.36	9.54	-9.86
			Max. Vy	22	-1.65	-11.56	-0.01
			Max. Vx	34	1.08	9.55	9.85
			Max Tension	21	18.81	0.00	0.00
			Max. Compression	20	-16.65	0.00	0.00
			Max. Mx	32	7.51	0.29	-0.02
			Max. My	21	-16.35	0.13	0.04
Max. Vy	32	0.08	0.29	-0.02			
Max. Vx	21	-0.01	0.00	0.00			

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg C	Max. Vert	30	428.62	32.54	-19.68
	Max. H _x	30	428.62	32.54	-19.68
	Max. H _z	21	-350.34	-39.23	24.55
	Min. Vert	22	-363.26	-40.90	24.42
	Min. H _x	22	-363.26	-40.90	24.42
	Min. H _z	30	428.62	32.54	-19.68
Leg B	Max. Vert	24	426.83	-32.87	-19.16
	Max. H _x	32	-365.67	41.18	24.03
	Max. H _z	32	-365.67	41.18	24.03
	Min. Vert	32	-365.67	41.18	24.03
	Min. H _x	7	348.76	-32.95	-18.84
	Min. H _z	24	426.83	-32.87	-19.16
Leg A	Max. Vert	19	427.25	-0.58	37.97
	Max. H _x	31	28.06	3.86	-5.11
	Max. H _z	19	427.25	-0.58	37.97
	Min. Vert	27	-364.57	0.59	-47.70
	Min. H _x	23	27.41	-3.86	-5.18
	Min. H _z	27	-364.57	0.59	-47.70

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	Page	
		PiROD U20'-0"x170' Lattice Tower	33 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	51.55	0.00	0.00	-2.00	10.22	-0.00
Dead+Wind 0 deg - No Ice	51.55	-0.03	-59.60	-5731.31	12.45	-22.98
Dead+Wind 30 deg - No Ice	51.55	29.27	-50.81	-4910.48	-2816.44	-22.88
Dead+Wind 45 deg - No Ice	51.55	41.56	-41.28	-3990.12	-4015.51	-20.09
Dead+Wind 60 deg - No Ice	51.55	50.83	-29.04	-2806.84	-4918.74	-15.89
Dead+Wind 90 deg - No Ice	51.55	58.77	0.23	26.20	-5671.60	-5.78
Dead+Wind 120 deg - No Ice	51.55	51.69	30.08	2886.46	-4964.91	6.19
Dead+Wind 135 deg - No Ice	51.55	41.56	41.56	4009.14	-4016.39	11.54
Dead+Wind 150 deg - No Ice	51.55	29.55	50.94	4912.46	-2853.77	16.79
Dead+Wind 180 deg - No Ice	51.55	0.21	58.66	5675.66	-15.12	24.59
Dead+Wind 210 deg - No Ice	51.55	-29.36	50.86	4904.32	2852.48	23.21
Dead+Wind 225 deg - No Ice	51.55	-41.43	41.46	3998.63	4022.68	20.84
Dead+Wind 240 deg - No Ice	51.55	-51.57	29.98	2876.19	4972.05	18.14
Dead+Wind 270 deg - No Ice	51.55	-58.70	0.09	11.33	5682.58	8.01
Dead+Wind 300 deg - No Ice	51.55	-50.74	-29.22	-2827.93	4924.98	-3.93
Dead+Wind 315 deg - No Ice	51.55	-41.50	-41.41	-4004.87	4024.93	-9.94
Dead+Wind 330 deg - No Ice	51.55	-29.33	-50.88	-4917.75	2841.20	-16.08
Dead+Ice+Temp	85.61	0.00	0.00	-2.59	25.14	0.00
Dead+Wind 0 deg+Ice+Temp	85.61	-0.02	-69.88	-6905.93	26.68	-19.68
Dead+Wind 30 deg+Ice+Temp	85.61	34.37	-59.62	-5905.89	-3377.35	-25.79
Dead+Wind 45 deg+Ice+Temp	85.61	48.70	-48.47	-4802.60	-4804.84	-25.94
Dead+Wind 60 deg+Ice+Temp	85.61	59.54	-34.13	-3381.60	-5883.60	-24.27
Dead+Wind 90 deg+Ice+Temp	85.61	68.91	0.18	19.61	-6802.32	-17.29
Dead+Wind 120 deg+Ice+Temp	85.61	60.58	35.16	3467.54	-5963.93	-5.59
Dead+Wind 135 deg+Ice+Temp	85.61	48.70	48.69	4814.91	-4805.18	1.31
Dead+Wind 150 deg+Ice+Temp	85.61	34.59	59.71	5904.80	-3406.90	8.32
Dead+Wind 180 deg+Ice+Temp	85.61	0.16	68.72	6808.78	5.20	21.08
Dead+Wind 210 deg+Ice+Temp	85.61	-34.44	59.65	5898.58	3440.45	26.07
Dead+Wind 225 deg+Ice+Temp	85.61	-48.60	48.61	4806.92	4844.71	26.55
Dead+Wind 240 deg+Ice+Temp	85.61	-60.49	35.08	3459.87	6003.99	26.35
Dead+Wind 270 deg+Ice+Temp	85.61	-68.86	0.07	8.33	6845.13	19.07
Dead+Wind 300 deg+Ice+Temp	85.61	-59.46	-34.27	-3397.94	5922.26	7.02
Dead+Wind 315 deg+Ice+Temp	85.61	-48.65	-48.57	-4813.96	4845.92	-0.04
Dead+Wind 330 deg+Ice+Temp	85.61	-34.41	-59.67	-5911.38	3430.67	-7.76
Dead+Wind 0 deg - Service	51.55	-0.01	-20.62	-1984.53	11.00	-7.95
Dead+Wind 30 deg - Service	51.55	10.13	-17.58	-1700.49	-967.87	-7.93
Dead+Wind 45 deg - Service	51.55	14.38	-14.28	-1382.01	-1382.78	-6.95
Dead+Wind 60 deg - Service	51.55	17.59	-10.05	-972.56	-1695.31	-5.50
Dead+Wind 90 deg - Service	51.55	20.33	0.08	7.75	-1955.82	-1.99
Dead+Wind 120 deg - Service	51.55	17.89	10.41	997.47	-1711.29	2.14
Dead+Wind 135 deg - Service	51.55	14.38	14.38	1385.94	-1383.08	3.98
Dead+Wind 150 deg - Service	51.55	10.23	17.63	1698.51	-980.78	5.80
Dead+Wind 180 deg - Service	51.55	0.07	20.30	1962.60	1.46	8.51
Dead+Wind 210 deg - Service	51.55	-10.16	17.60	1695.71	993.74	8.05
Dead+Wind 225 deg - Service	51.55	-14.34	14.35	1382.32	1398.66	7.22
Dead+Wind 240 deg - Service	51.55	-17.85	10.37	993.93	1727.18	6.28
Dead+Wind 270 deg - Service	51.55	-20.31	0.03	2.60	1973.05	2.76
Dead+Wind 300 deg - Service	51.55	-17.56	-10.11	-979.87	1710.89	-1.36
Dead+Wind 315 deg - Service	51.55	-14.36	-14.33	-1387.13	1399.44	-3.43
Dead+Wind 330 deg - Service	51.55	-10.15	-17.61	-1703.02	989.84	-5.55

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-51.55	0.00	0.00	51.55	0.00	0.000%
2	-0.03	-51.55	-59.60	0.03	51.55	59.60	0.000%

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	34 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
3	29.27	-51.55	-50.81	-29.27	51.55	50.81	0.000%
4	41.56	-51.55	-41.28	-41.56	51.55	41.28	0.000%
5	50.83	-51.55	-29.04	-50.83	51.55	29.04	0.000%
6	58.77	-51.55	0.23	-58.77	51.55	-0.23	0.000%
7	51.69	-51.55	30.08	-51.69	51.55	-30.08	0.000%
8	41.56	-51.55	41.56	-41.56	51.55	-41.56	0.000%
9	29.55	-51.55	50.94	-29.55	51.55	-50.94	0.000%
10	0.21	-51.55	58.66	-0.21	51.55	-58.66	0.000%
11	-29.36	-51.55	50.86	29.36	51.55	-50.86	0.000%
12	-41.43	-51.55	41.46	41.43	51.55	-41.46	0.000%
13	-51.57	-51.55	29.98	51.57	51.55	-29.98	0.000%
14	-58.70	-51.55	0.09	58.70	51.55	-0.09	0.000%
15	-50.74	-51.55	-29.22	50.74	51.55	29.22	0.000%
16	-41.50	-51.55	-41.41	41.50	51.55	41.41	0.000%
17	-29.33	-51.55	-50.88	29.33	51.55	50.88	0.000%
18	0.00	-85.61	0.00	-0.00	85.61	0.00	0.000%
19	-0.02	-85.61	-69.88	0.02	85.61	69.88	0.000%
20	34.37	-85.61	-59.62	-34.37	85.61	59.62	0.000%
21	48.70	-85.61	-48.47	-48.70	85.61	48.47	0.000%
22	59.54	-85.61	-34.13	-59.54	85.61	34.13	0.000%
23	68.91	-85.61	0.18	-68.91	85.61	-0.18	0.000%
24	60.58	-85.61	35.16	-60.58	85.61	-35.16	0.000%
25	48.70	-85.61	48.69	-48.70	85.61	-48.69	0.000%
26	34.59	-85.61	59.71	-34.59	85.61	-59.71	0.000%
27	0.16	-85.61	68.72	-0.16	85.61	-68.72	0.000%
28	-34.44	-85.61	59.65	34.44	85.61	-59.65	0.000%
29	-48.60	-85.61	48.61	48.60	85.61	-48.61	0.000%
30	-60.49	-85.61	35.08	60.49	85.61	-35.08	0.000%
31	-68.86	-85.61	0.07	68.86	85.61	-0.07	0.000%
32	-59.46	-85.61	-34.27	59.46	85.61	34.27	0.000%
33	-48.65	-85.61	-48.57	48.65	85.61	48.57	0.000%
34	-34.41	-85.61	-59.67	34.41	85.61	59.67	0.000%
35	-0.01	-51.55	-20.62	0.01	51.55	20.62	0.000%
36	10.13	-51.55	-17.58	-10.13	51.55	17.58	0.000%
37	14.38	-51.55	-14.28	-14.38	51.55	14.28	0.000%
38	17.59	-51.55	-10.05	-17.59	51.55	10.05	0.000%
39	20.33	-51.55	0.08	-20.33	51.55	-0.08	0.000%
40	17.89	-51.55	10.41	-17.89	51.55	-10.41	0.000%
41	14.38	-51.55	14.38	-14.38	51.55	-14.38	0.000%
42	10.23	-51.55	17.63	-10.23	51.55	-17.63	0.000%
43	0.07	-51.55	20.30	-0.07	51.55	-20.30	0.000%
44	-10.16	-51.55	17.60	10.16	51.55	-17.60	0.000%
45	-14.34	-51.55	14.35	14.34	51.55	-14.35	0.000%
46	-17.85	-51.55	10.37	17.85	51.55	-10.37	0.000%
47	-20.31	-51.55	0.03	20.31	51.55	-0.03	0.000%
48	-17.56	-51.55	-10.11	17.56	51.55	10.11	0.000%
49	-14.36	-51.55	-14.33	14.36	51.55	14.33	0.000%
50	-10.15	-51.55	-17.61	10.15	51.55	17.61	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00000001
3	Yes	4	0.00000001	0.00000001

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	Page
	Project	Date
	Client	Designed by
	PiROD U20'-0"x170' Lattice Tower	35 of 43
	TWS-027 Rev. 1 / Cromwell, CT Tower	11:32:54 09/23/14
	Sprint / T-Mobile (TWS-027)/(EBI-002)	MCD

4	Yes	4	0.00000001	0.00000001
5	Yes	4	0.00000001	0.00000001
6	Yes	4	0.00000001	0.00000001
7	Yes	4	0.00000001	0.00000001
8	Yes	4	0.00000001	0.00000001
9	Yes	4	0.00000001	0.00000001
10	Yes	4	0.00000001	0.00000001
11	Yes	4	0.00000001	0.00000001
12	Yes	4	0.00000001	0.00000001
13	Yes	4	0.00000001	0.00000001
14	Yes	4	0.00000001	0.00000001
15	Yes	4	0.00000001	0.00000001
16	Yes	4	0.00000001	0.00000001
17	Yes	4	0.00000001	0.00000001
18	Yes	4	0.00000001	0.00000001
19	Yes	4	0.00000001	0.00000081
20	Yes	4	0.00000001	0.00000109
21	Yes	4	0.00000001	0.00000130
22	Yes	4	0.00000001	0.00000120
23	Yes	4	0.00000001	0.00000130
24	Yes	4	0.00000001	0.00000083
25	Yes	4	0.00000001	0.00000099
26	Yes	4	0.00000001	0.00000122
27	Yes	4	0.00000001	0.00000116
28	Yes	4	0.00000001	0.00000109
29	Yes	4	0.00000001	0.00000096
30	Yes	4	0.00000001	0.00000096
31	Yes	4	0.00000001	0.00000130
32	Yes	4	0.00000001	0.00000116
33	Yes	4	0.00000001	0.00000119
34	Yes	4	0.00000001	0.00000122
35	Yes	4	0.00000001	0.00000001
36	Yes	4	0.00000001	0.00000001
37	Yes	4	0.00000001	0.00000001
38	Yes	4	0.00000001	0.00000001
39	Yes	4	0.00000001	0.00000001
40	Yes	4	0.00000001	0.00000001
41	Yes	4	0.00000001	0.00000001
42	Yes	4	0.00000001	0.00000001
43	Yes	4	0.00000001	0.00000001
44	Yes	4	0.00000001	0.00000001
45	Yes	4	0.00000001	0.00000001
46	Yes	4	0.00000001	0.00000001
47	Yes	4	0.00000001	0.00000001
48	Yes	4	0.00000001	0.00000001
49	Yes	4	0.00000001	0.00000001
50	Yes	4	0.00000001	0.00000001

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	170 - 150	5.771	35	0.3279	0.0280
T2	150 - 140	4.409	35	0.2984	0.0346
T3	140 - 120	3.790	35	0.2780	0.0332
T4	120 - 100	2.702	35	0.2252	0.0194
T5	100 - 90	1.823	46	0.1785	0.0127
T6	90 - 80	1.464	46	0.1509	0.0107
T7	80 - 60	1.155	46	0.1305	0.0089

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	36 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T8	60 - 40	0.649	46	0.0966	0.0064
T9	40 - 20	0.293	46	0.0583	0.0040
T10	20 - 0	0.086	46	0.0265	0.0020

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
183.00	101-90-08-0-01	35	5.771	0.3279	0.0280	88849
179.75	15' Mount Pipe	35	5.771	0.3279	0.0280	88849
178.00	3" Dia 20' Omni	35	5.771	0.3279	0.0280	88849
175.00	2.5" x 14' Omni	35	5.771	0.3279	0.0280	88849
174.00	1.5" x 12' Omni	35	5.771	0.3279	0.0280	88849
170.00	APXVSP18-C-A20	35	5.771	0.3279	0.0280	88849
168.00	HPD2-4.7	35	5.631	0.3253	0.0289	88849
159.50	APXV18-206517S-C w/ mounting hardware	35	5.042	0.3135	0.0324	42309
158.50	SC420-HF1LDF	35	4.974	0.3121	0.0327	38630
144.00	3" Dia 20' Omni	35	4.032	0.2868	0.0343	23538
141.00	2" Dia 15' Omni	35	3.850	0.2803	0.0336	23984
139.00	1.5" x 10' Omni	35	3.731	0.2756	0.0327	24120
138.50	9' Whip	35	3.702	0.2743	0.0325	24128
134.00	VHLP2.5-180	35	3.443	0.2627	0.0298	23972
125.50	PIROD 10' Lightweight T-Frame	35	2.981	0.2396	0.0233	23558
115.00	(2) TMA (shielded)	46	2.463	0.2135	0.0167	22934
101.00	BXA-171063-12BF	46	1.862	0.1811	0.0129	22013
87.00	3"x2"x22" Panel	46	1.366	0.1440	0.0101	25066
84.50	TMA	46	1.288	0.1388	0.0097	27742
83.50	3' Stand-off	46	1.258	0.1369	0.0095	28975
83.00	3' Dish	46	1.243	0.1359	0.0094	29604
82.50	TMA	46	1.228	0.1350	0.0093	30229
80.00	3"x2"x22" Panel	46	1.155	0.1305	0.0089	32895
30.00	Camera	46	0.171	0.0414	0.0030	32720
24.00	PC9013N	46	0.116	0.0323	0.0024	33266

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	170 - 150	19.843	19	1.0972	0.1177
T2	150 - 140	15.281	19	1.0106	0.1336
T3	140 - 120	13.176	19	0.9488	0.1236
T4	120 - 100	9.436	30	0.7798	0.0756
T5	100 - 90	6.374	30	0.6219	0.0489
T6	90 - 80	5.118	30	0.5273	0.0403
T7	80 - 60	4.035	30	0.4569	0.0330
T8	60 - 40	2.263	30	0.3383	0.0223
T9	40 - 20	1.016	30	0.2040	0.0132
T10	20 - 0	0.296	30	0.0927	0.0064

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	37 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
183.00	101-90-08-0-01	19	19.843	1.0972	0.1177	30835
179.75	15' Mount Pipe	19	19.843	1.0972	0.1177	30835
178.00	3" Dia 20' Omni	19	19.843	1.0972	0.1177	30835
175.00	2.5" x 14' Omni	19	19.843	1.0972	0.1177	30835
174.00	1.5" x 12' Omni	19	19.843	1.0972	0.1177	30835
170.00	APXVSP18-C-A20	19	19.843	1.0972	0.1177	30835
168.00	HPD2-4.7	19	19.377	1.0895	0.1203	30835
159.50	APXV18-206517S-C w/ mounting hardware	19	17.410	1.0553	0.1299	14683
158.50	SC420-HF1LDF	19	17.181	1.0510	0.1308	13406
144.00	3" Dia 20' Omni	19	14.000	0.9760	0.1294	8016
141.00	2" Dia 15' Omni	19	13.380	0.9560	0.1253	8024
139.00	1.5" x 10' Omni	19	12.974	0.9414	0.1218	7973
138.50	9' Whip	19	12.874	0.9376	0.1208	7953
134.00	VHLP2.5-180	30	11.986	0.9011	0.1107	7714
125.50	PIROD 10' Lightweight T-Frame	30	10.400	0.8266	0.0887	7254
115.00	(2) TMA (shielded)	30	8.604	0.7409	0.0663	6817
101.00	BXA-171063-12BF	30	6.510	0.6310	0.0498	6415
87.00	3"x2"x22" Panel	30	4.777	0.5034	0.0380	7279
84.50	TMA	30	4.504	0.4856	0.0361	8017
83.50	3' Stand-off	30	4.397	0.4789	0.0354	8355
83.00	3' Dish	30	4.345	0.4757	0.0350	8527
82.50	TMA	30	4.292	0.4724	0.0347	8697
80.00	3"x2"x22" Panel	30	4.035	0.4569	0.0330	9417
30.00	Camera	30	0.592	0.1447	0.0096	9288
24.00	PC9013N	30	0.399	0.1128	0.0077	9439

Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria
T1	170	Diagonal	A325N	0.6250	1	3.46	6.44	0.537 ✓	1.333	Bolt Shear
T2	150	Leg	A325N	1.0000	6	5.84	34.56	0.169 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	4.91	8.16	0.602 ✓	1.333	Member Bearing
		Top Girt	A325N	1.0000	1	0.42	8.16	0.052 ✓	1.333	Member Bearing
T3	140	Leg	A325N	1.0000	6	8.57	34.56	0.248 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	9.08	8.16	1.114 ✓	1.333	Member Bearing
T4	120	Leg	A325N	1.0000	6	15.41	34.56	0.446 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	11.55	10.88	1.062 ✓	1.333	Member Bearing
		Mid Girt	A325N	1.0000	1	3.92	8.16	0.480 ✓	1.333	Member Bearing
T5	100	Leg	A325N	1.0000	6	24.16	34.56	0.699 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	13.49	13.59	0.992 ✓	1.333	Member Bearing
T6	90	Leg	A325N	1.0000	6	28.86	34.56	0.835 ✓	1.333	Bolt Tension

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	38 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria
T7	80	Diagonal	A325N	1.0000	1	13.38	13.59	0.984 ✓	1.333	Member Bearing
		Leg	A325N	1.0000	6	33.26	34.56	0.963 ✓	1.333	Bolt Tension
T8	60	Diagonal	A325N	1.0000	1	14.16	16.49	0.859 ✓	1.333	Bolt Shear
		Leg	A325N	1.2500	6	41.67	54.00	0.772 ✓	1.333	Bolt Tension
T9	40	Diagonal	A325N	1.2500	1	13.88	16.99	0.817 ✓	1.333	Member Bearing
		Leg	A325N	1.2500	6	49.37	54.00	0.914 ✓	1.333	Bolt Tension
T10	20	Diagonal	A325N	1.2500	1	15.13	20.39	0.742 ✓	1.333	Member Bearing
		Diagonal	A325N	1.2500	1	18.81	16.99	1.107 ✓	1.333	Member Bearing

Compression Checks

Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	1 3/4	20.00	2.49	68.3 K=1.00	21.253	2.4053	-35.99	51.12	0.704 ✓
T2	150 - 140	Pirod 105244	10.02	10.02	45.4 K=1.00	25.051	3.6816	-41.87	92.23	0.454 ✓
T3	140 - 120	Pirod 105216	20.03	10.02	45.4 K=1.00	25.051	3.6816	-84.43	92.23	0.915 ✓
T4	120 - 100	Pirod 105217	20.03	10.02	37.8 K=1.00	26.132	5.3014	-138.35	138.54	0.999 ✓
T5	100 - 90	Pirod 105217	10.02	10.02	37.8 K=1.00	26.132	5.3014	-170.56	138.54	1.231 ✓
T6	90 - 80	Pirod 105217 reinf w/ 1" dia bar	10.02	10.02	31.5 K=1.00	26.968	7.6570	-202.06	206.49	0.979 ✓
T7	80 - 60	Pirod 105218 reinf w/ 1" dia bar	20.03	10.02	27.6 K=1.00	27.439	9.9280	-261.48	272.41	0.960 ✓
T8	60 - 40	Pirod 105219	20.03	10.02	28.4 K=1.00	27.351	9.4248	-317.16	257.78	1.230 ✓
T9	40 - 20	Pirod 105219 reinf w /1" dia bar	20.03	10.02	25.4 K=1.00	27.705	11.7803	-370.16	326.37	1.134 ✓
T10	20 - 0	Pirod 105220 reinf w/ 1" dia bar	20.03	10.02	24.3 K=1.00	27.824	14.2843	-419.98	397.44	1.057 ✓

Truss-Leg Diagonal Data

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 39 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section No.	Elevation ft	Diagonal Size	L_d ft	Kl/r	F_a ksi	A in ²	Actual V K	Allow. V_a K	Stress Ratio
T2	150 - 140	0.5	1.48	121.0	10.193	0.1963	0.94	2.24	0.418
T3	140 - 120	0.5	1.48	121.0	10.133	0.1963	0.99	2.23	0.446
T4	120 - 100	0.5	1.47	120.0	10.279	0.1963	1.73	2.26	0.764
T5	100 - 90	0.5	1.47	120.0	10.279	0.1963	0.50	2.26	0.219
T6	90 - 80	0.5	1.46	118.8	10.452	0.1963	0.39	2.30	0.172
T7	80 - 60	0.5	1.44	117.8	10.592	0.1963	0.23	2.33	0.097
T8	60 - 40	0.625	1.45	94.4	13.671	0.3068	0.32	4.69	0.067
T9	40 - 20	0.625	1.44	93.7	16.133	0.3068	0.97	5.54	0.175
T10	20 - 0	0.625	1.42	93.0	13.845	0.3068	1.71	4.75	0.360

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L_u ft	Kl/r	F_a ksi	A in ²	Actual P K	Allow. P_a K	Ratio P/P_a
T1	170 - 150	7/8	5.59	2.71	111.6 K=0.75	12.001	0.6013	-3.46	7.22	0.480
T2	150 - 140	L2 1/2x2 1/2x3/16	11.42	5.02	121.8 K=1.00	10.024	0.9020	-5.45	9.04	0.602
T3	140 - 120	L3x3x3/16	12.50	5.67	115.6 K=1.01	10.799	1.0900	-9.44	11.77	0.802
T4	120 - 100	L3x3x1/4	13.80	6.37	129.1 K=1.00	8.961	1.4400	-12.57	12.90	0.974
T5	100 - 90	L3x3x5/16	14.50	6.74	137.3 K=1.00	7.920	1.7800	-13.72	14.10	0.973
T6	90 - 80	L3x3x5/16	15.24	7.12	145.1 K=1.00	7.090	1.7800	-13.75	12.62	1.090
T7	80 - 60	L3x3x3/8	16.80	7.92	162.0 K=1.00	5.691	2.1100	-14.16	12.01	1.179
T8	60 - 40	L3 1/2x3 1/2x5/16	18.45	8.73	151.8 K=1.00	6.480	2.0900	-14.22	13.54	1.050
T9	40 - 20	L3 1/2x3 1/2x3/8	19.30	9.17	160.1 K=1.00	5.825	2.4800	-14.76	14.45	1.021
T10	20 - 0	L4x4x5/16	21.03	10.04	152.3 K=1.00	6.437	2.4000	-16.65	15.45	1.078

Top Girt Design Data (Compression)

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 40 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P/P _a
T1	170 - 150	7/8	5.00	4.85	186.4 K=0.70	4.298	0.6013	-0.33	2.58	0.127
T2	150 - 140	L3x3x3/16	5.00	4.52	105.5 K=1.16	12.079	1.0900	-0.37	13.17	0.028

Bottom Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P/P _a
T1	170 - 150	7/8	5.00	4.85	186.4 K=0.70	4.298	0.6013	-0.15	2.58	0.059

Mid Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P/P _a
T4	120 - 100	L3x3x3/16	9.00	7.67	154.4 K=1.00	6.267	1.0900	-3.17	6.83	0.464

Tension Checks

Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P/P _a
T1	170 - 150	1 3/4	20.00	2.49	68.3	30.000	2.4053	29.76	72.16	0.412
T2	150 - 140	Pirod 105244	10.02	10.02	45.4	30.000	3.6816	35.03	110.45	0.317
T3	140 - 120	Pirod 105216	20.03	10.02	45.4	30.000	3.6816	70.49	110.45	0.638
T4	120 - 100	Pirod 105217	20.03	10.02	37.8	30.000	5.3014	117.19	159.04	0.737
T5	100 - 90	Pirod 105217	10.02	10.02	37.8	30.000	5.3014	144.94	159.04	0.911
T6	90 - 80	Pirod 105217 reinf w/ 1" dia bar	10.02	10.02	31.5	30.000	7.6570	173.18	229.71	0.754
T7	80 - 60	Pirod 105218 reinf w/ 1" dia bar	20.03	10.02	27.6	30.000	9.9280	225.41	297.84	0.757
T8	60 - 40	Pirod 105219	20.03	10.02	28.4	30.000	9.4248	273.19	282.74	0.966

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	41 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T9	40 - 20	Pirol 105219 reinf w /1" dia bar	20.03	10.02	25.4	30.000	11.7803	315.77	353.41	0.894
T10	20 - 0	Pirol 105220 reinf w/ 1" dia bar	20.03	10.02	24.3	30.000	14.2843	352.06	428.53	0.822

Truss-Leg Diagonal Data

Section No.	Elevation ft	Diagonal Size	L _d ft	Kl/r	F _a ksi	A in ²	Actual V K	Allow. V _a K	Stress Ratio
T2	150 - 140	0.5	1.48	121.0	10.193	0.1963	0.94	2.24	0.418
T3	140 - 120	0.5	1.48	121.0	10.133	0.1963	0.99	2.23	0.446
T4	120 - 100	0.5	1.47	120.0	10.279	0.1963	1.73	2.26	0.764
T5	100 - 90	0.5	1.47	120.0	10.279	0.1963	0.50	2.26	0.219
T6	90 - 80	0.5	1.46	118.8	10.452	0.1963	0.39	2.30	0.172
T7	80 - 60	0.5	1.44	117.8	10.592	0.1963	0.23	2.33	0.097
T8	60 - 40	0.625	1.45	94.4	13.671	0.3068	0.32	4.69	0.067
T9	40 - 20	0.625	1.44	93.7	16.133	0.3068	0.97	5.54	0.175
T10	20 - 0	0.625	1.42	93.0	13.845	0.3068	1.71	4.75	0.360

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.59	2.71	148.7	30.000	0.6013	3.41	18.04	0.189
T2	150 - 140	L2 1/2x2 1/2x3/16	11.42	5.02	80.1	21.600	0.9020	4.91	19.48	0.252
T3	140 - 120	L3x3x3/16	12.50	5.67	74.6	21.600	1.0900	9.08	23.54	0.386
T4	120 - 100	L3x3x1/4	13.80	6.37	84.3	21.600	1.4400	11.55	31.10	0.371
T5	100 - 90	L3x3x5/16	14.50	6.74	89.9	21.600	1.7800	13.49	38.45	0.351
T6	90 - 80	L3x3x5/16	15.24	7.12	94.9	21.600	1.7800	13.38	38.45	0.348

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 42 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T7	80 - 60	L3x3x3/8	16.01	7.54	101.2	21.600	2.1100	13.78	45.58	0.302
T8	60 - 40	L3 1/2x3 1/2x5/16	18.45	8.73	99.2	21.600	2.0900	13.88	45.14	0.307
T9	40 - 20	L3 1/2x3 1/2x3/8	20.16	9.59	109.8	21.600	2.4800	15.13	53.57	0.282
T10	20 - 0	L4x4x5/16	21.92	10.48	103.3	21.600	2.4000	18.81	51.84	0.363

Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	266.3	30.000	0.6013	0.30	18.04	0.016
T2	150 - 140	L3x3x3/16	5.00	4.52	62.0	21.600	1.0900	0.42	23.54	0.018

Bottom Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	266.3	30.000	0.6013	0.15	18.04	0.008

Mid Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T4	120 - 100	L3x3x3/16	9.00	7.67	102.2	21.600	1.0900	3.92	23.54	0.166

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
T1	170 - 150	Leg	1 3/4	3	-35.99	68.14	52.8	Pass
T2	150 - 140	Leg	Pirod 105244	60	-41.87	122.94	34.1	Pass
T3	140 - 120	Leg	Pirod 105216	72	-84.43	122.94	68.7	Pass

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 43 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail	
T4	120 - 100	Leg	Pirod 105217	87	-138.35	184.67	74.9	Pass	
T5	100 - 90	Leg	Pirod 105217	105	-170.56	184.67	92.4	Pass	
T6	90 - 80	Leg	Pirod 105217 reinf w/ 1" dia bar	114	-202.06	275.26	73.4	Pass	
T7	80 - 60	Leg	Pirod 105218 reinf w/ 1" dia bar	123	-261.48	363.13	72.0	Pass	
T8	60 - 40	Leg	Pirod 105219	136	-317.16	343.62	92.3	Pass	
T9	40 - 20	Leg	Pirod 105219 reinf w /1" dia bar	151	-370.16	435.06	85.1	Pass	
T10	20 - 0	Leg	Pirod 105220 reinf w/ 1" dia bar	166	-419.98	529.79	79.3	Pass	
T1	170 - 150	Diagonal	7/8	12	-3.46	9.62	36.0	Pass	
T2	150 - 140	Diagonal	L2 1/2x2 1/2x3/16	69	-5.45	12.05	45.2	Pass	
T3	140 - 120	Diagonal	L3x3x3/16	78	-9.44	15.69	60.2	Pass	
T4	120 - 100	Diagonal	L3x3x1/4	96	-12.57	17.20	73.1	Pass	
T5	100 - 90	Diagonal	L3x3x5/16	111	-13.72	18.79	73.0	Pass	
T6	90 - 80	Diagonal	L3x3x5/16	120	-13.75	16.82	81.7	Pass	
T7	80 - 60	Diagonal	L3x3x3/8	129	-14.16	16.01	88.5	Pass	
T8	60 - 40	Diagonal	L3 1/2x3 1/2x5/16	144	-14.22	18.05	78.8	Pass	
T9	40 - 20	Diagonal	L3 1/2x3 1/2x3/8	165	-14.76	19.26	76.6	Pass	
T10	20 - 0	Diagonal	L4x4x5/16	179	-16.65	20.59	80.9	Pass	
T1	170 - 150	Top Girt	7/8	6	-0.33	3.45	9.5	Pass	
T2	150 - 140	Top Girt	L3x3x3/16	61	-0.37	17.55	2.1	Pass	
T1	170 - 150	Bottom Girt	7/8	8	-0.15	3.45	4.4	Pass	
T4	120 - 100	Mid Girt	L3x3x3/16	88	-3.17	9.11	34.8	Pass	
							Summary		
							Leg (T5)	92.4	Pass
							Diagonal (T7)	88.5	Pass
							Top Girt (T1)	9.5	Pass
							Bottom Girt (T1)	4.4	Pass
							Mid Girt (T4)	34.8	Pass
							Bolt Checks	83.5	Pass
							RATING =	92.4	Pass

ANCHOR BOLT EVALUATION

Job	<u>170' Self-Supporting Lattice Tower - Cromwell, CT</u>	Project No.	<u>TWS-027 Rev. 1</u>	Sheet	<u>1</u>	of	<u>3</u>
Description	<u>Anchor Bolt Analysis</u>	Computed by	<u>MCD</u>	Date	<u>09/23/14</u>		
		Checked by	<u> </u>	Date	<u> </u>		

ANCHOR BOLT ANALYSIS

Input Data

Max Pier Reactions:

Uplift:	Uplift := 366 kips	<i>user input</i>
Shear:	Shear := 48 kips	<i>user input</i>
Compression:	Compression := 429 kips	<i>user input</i>

Anchor Bolt Data:

Use ASTM A687 Grade

Number of Anchor Bolts = N	$N := 6$	<i>user input</i>
Bolt Ultimate Strength:	$F_u := 150 \text{ ksi}$	<i>user input</i>
Bolt Yield Strength:	$F_y := 105 \text{ ksi}$	<i>user input</i>
Bolt Modulus:	$E := 29000 \text{ ksi}$	<i>user input</i>
Thickness of Anchor Bolts	$D := 1.25 \text{ in}$	<i>user input</i>
Threads per Inch:	$n := 7$	<i>user input</i>
Coefficient of Friction:	$\mu := 0.55$	<i>user input</i> (for baseplate with grout ASCE 10-97)

Job	170' Self-Supporting Lattice Tower - Cromwell, CT	Project No.	TWS-027 Rev. 1	Sheet	2	of	3
Description	Anchor Bolt Analysis	Computed by	MCD	Date	09/23/14		
		Checked by		Date			

Anchor Bolt Area:

Gross Area of Bolt:

$$A_g := \frac{\pi \cdot D^2}{4} \quad A_g = 1.227 \cdot \text{in}^2$$

Net Area of Bolt:

$$A_n := \frac{\pi}{4} \cdot \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 \quad A_n = 0.969 \cdot \text{in}^2$$

Check Tensile Forces:

Maximum Tensile Force (Gross Area):

$$\text{AllowableTension} := 1.33 \cdot (0.33 \cdot A_g \cdot F_u) \quad \text{AllowableTension} = 80.8 \cdot \text{kips}$$

Note: 1.33 increase allowed per TIA/EIA

Maximum Tensile Force (Net Area):

$$F_{\text{net.area}} := 1.33 \cdot (0.60 \cdot A_n \cdot F_y) \quad F_{\text{net.area}} = 81.2 \cdot \text{kips}$$

Note: 1.33 increase allowed per TIA/EIA

Applied Tension:

$$\text{MaxTension} := \frac{\text{Uplift}}{N} \quad \text{MaxTension} = 61.0 \cdot \text{kips}$$

Check Stresses:

$$\frac{\text{MaxTension}}{F_{\text{net.area}}} = 0.75$$

$$\text{Condition1} := \text{if} \left(\frac{\text{MaxTension}}{F_{\text{net.area}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Condition1 = "OK"

Job	170' Self-Supporting Lattice Tower - Cromwell, CT	Project No.	TWS-027 Rev. 1	Sheet	3 of 3
Description	Anchor Bolt Analysis	Computed by	MCD	Date	09/23/14
		Checked by		Date	

Check Anchor Bolt Area:

Based on the ASCE 10-97 Design of Latticed Steel Transmission Structures

Required Area:

$$A_{s1} := \frac{\text{Uplift}}{F_y} + \frac{\text{Shear}}{\mu \cdot 0.85 \cdot F_y} \quad A_{s1} = 4.5 \cdot \text{in}^2$$

$$A_{s2} := \left| \frac{\text{Shear} - (0.3 \cdot \text{Compression})}{\mu \cdot 0.85 \cdot F_y} \right| \quad A_{s2} = 1.6 \cdot \text{in}^2$$

Provided Area:

$$A_{\text{provided}} := A_n \cdot N \quad A_{\text{provided}} = 5.8 \cdot \text{in}^2$$

$$\text{Condition2} := \text{if} \left(\frac{A_{s1}}{A_{\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s1}}{A_{\text{provided}}} = 0.77$$

Condition2 = "OK"

$$\text{Condition3} := \text{if} \left(\frac{A_{s2}}{A_{\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s2}}{A_{\text{provided}}} = 0.28$$

Condition3 = "OK"

FOUNDATION EVALUATION

Job	<u>170' Self-Supporting Lattice Tower - Cromwell, CT</u>	Project No.	<u>TWS-027 Rev. 1</u>	Sheet	<u>1</u>	of	<u>2</u>
Description	<u>Drilled Pier Caisson Evaluation</u>	Computed by	<u>MCD</u>	Date	<u>09/23/14</u>		
		Checked by	<u> </u>	Date	<u> </u>		

FOUNDATION ANALYSIS

Input Data

Maximum Pier Reactions:

Compression: $C_t := 429$ kips *user input*
 Uplift: $U_t := 366$ kips *user input*

Material Properties:

Unit Weight of Concrete: $\gamma_c := 150$ pcf *user input*
 Unit Weight of Water: $\gamma_w := 62.4$ pcf *user input*
 Unit Weight of Soil: $\gamma_s := 100$ pcf *user input*

Foundation Dimensions:

Drilled Caisson Length: $C_{Length} := 41.5$ ft *user input*
 Diameter of Pier: $d_p := 5.5$ ft *user input*
 Extension of Pier Above Grade: $L_{pag} := 0.5$ ft *user input*
 Additional Concrete $Conc_{addl} := 5ft \cdot \left(13ft \cdot 13ft - \frac{\pi \cdot d_p^2}{4} \right)$
 $Conc_{addl} = 726.2$ ft³
 Allowable Soil Bearing Capacity (Allowable Bearing Pressure at Depth 41') $q_s := 6$ ksf *user input*
 Water Table Below Grade: $Wd := 41$ ft *user input*
 Average Allowable Shear: $fl := 859$ psf *user input*
 Depth Neglected for Skin Friction at Top: $Depthunbond := 4$ ft *user input*

Foundation reinforcement per drawings by Tectonic, dated May 5, 2004

Loading:

$$TotalDownLoad := C_t + \pi \cdot \frac{d_p^2}{4} \cdot [L_{pag} \cdot \gamma_c + [\gamma_c \cdot (C_{Length} - L_{pag})]]$$

$$TotalDownLoad = 576.9 \text{ kips}$$

$$PierWeight := \pi \cdot \frac{d_p^2}{4} \cdot [(Wd + L_{pag}) \cdot \gamma_c + (C_{Length} - Wd - L_{pag}) \cdot (\gamma_c - \gamma_w)] + Conc_{addl} \cdot \gamma_c$$

$$PierWeight = 256.8 \text{ kips}$$

$$SoilShear := \pi \cdot d_p \cdot [fl \cdot (C_{Length} - Depthunbond)]$$

$$SoilShear = 556.6 \text{ kips}$$

Job	170' Self-Supporting Lattice Tower - Cromwell, CT	Project No.	TWS-027 Rev. 1	Sheet	<u>2</u> of <u>2</u>
Description	Drilled Pier Caisson Evaluation	Computed by	MCD	Date	09/23/14
		Checked by		Date	

Compression Capacity:

$$\text{TotalDownLoadCapacity} := \text{SoilShear} + q_s \left(\pi \cdot \frac{d_p^2}{4} \right)$$

$$\text{TotalDownLoadCapacity} = 699.1 \text{ kips}$$

$$\text{CheckDownLoadCapacity} := \text{if}(\text{TotalDownLoad} < \text{TotalDownLoadCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckDownLoadCapacity} = \text{"Okay"}$$

Tension Capacity:

$$\text{TotalUpLiftCapacity} := \text{SoilShear} + \text{PierWeight}$$

$$\text{TotalUpLiftCapacity} = 813.4 \text{ kips}$$

$$\text{CheckUpLiftCapacity} := \text{if}(U_t < \text{TotalUpLiftCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckUpLiftCapacity} = \text{"Okay"}$$

$$\text{SafetyFactor}_{\text{provided}} := \frac{\text{TotalUpLiftCapacity}}{U_t}$$

$$\text{SafetyFactor}_{\text{provided}} = 2.22$$

Check Cone Failure:

$$\text{ConeFailureCapacity} := \frac{\left[(C_{\text{Length}} - L_{\text{pag}}) \cdot \tan(30\text{deg}) \cdot 2 + d_p \right]^2 \cdot \pi \cdot C_{\text{Length}} - L_{\text{pag}}}{4} \cdot \gamma_s$$

$$\text{ConeFailureCapacity} = 2997.25 \text{ kips}$$


$$\text{CheckConeFailureCapacity} := \text{if}(U_t < \text{ConeFailureCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckConeFailureCapacity} = \text{"Okay"}$$

$$\text{ConeSafetyFactor}_{\text{provided}} := \frac{\text{ConeFailureCapacity}}{U_t}$$

$$\text{ConeSafetyFactor}_{\text{provided}} = 8.19$$

Sprint®



PROJECT: 2.5 EQUIPMENT DEPLOYMENT

SITE NAME: CROMWELL - RT. 372

SITE CASCADE: CT60XC931-A

SITE ADDRESS: 179 SHUNPIKE ROAD
CROMWELL, CT 06416

SITE TYPE: 170'-0" SELF SUPPORT



6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski 2/05/2015
 Signature: Date:

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015

PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
TITLE SHEET

SCALE: NONE

PROJECT NUMBER	29431
SHEET NUMBER	T-1

SITE INFORMATION

PROPERTY OWNER:
 CROMWELL FIRE DEPARTMENT
 1 WEST STREET
 CROMWELL, CT 06416

SITE ADDRESS:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

GEOGRAPHIC COORDINATES:
 LATITUDE: 41° 37' 23.74" N (41.623261° N)
 LONGITUDE: -72° 40' 45.62" W (-72.679339° W)

ZONING JURISDICTION:
 CROMWELL

ZONING DISTRICT:
 A-25 RESIDENTIAL

POWER COMPANY:
 CONNECTICUT LIGHT AND POWER
 PH.: (800) 286-2000

AAV PROVIDER:
 AT#T
 PH.: (888) 949-0447

SPRINT CONSTRUCTION MANAGER:
 NAME: MIKE DELIA
 PHONE: (781) 316-6348
 E-MAIL: Michael.Delia@Sprint.com


EQUIPMENT SUPPLIER:
 ALCATEL-LUCENT
 600-700 MOUNTAIN AVENUE
 MURRAY HILL, NJ 07974
 PH.: (908) 508-8080

PLANS PREPARED BY:
 RAMAKER & ASSOCIATES, INC.
 CONTACT: KEITH BOHNSACK, PROJECT MANAGER
 PH.: (608) 643-4100
 EMAIL: kbohnsack@ramaker.com

AREA MAP



LOCATION MAP



PROJECT DESCRIPTION

- INSTALL (1) EQUIPMENT CABINET
- INSTALL NEW BATTERY STRING(S) IN EXISTING BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRH'S ON TOWER
- INSTALL (1) HYBRID CABLE AND (2) SECTOR JUMPERS
- INSTALL (27) ANTENNA / RRH JUMPERS

APPLICABLE CODES

- * ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.
1. INTERNATIONAL BUILDING CODE
 2. ANSI/TIA-222 STRUCTURAL STANDARD FOR ANTENNA STRUCTURES
 3. NFPA 780 - LIGHTNING PROTECTION CODE
 4. NATIONAL ELECTRIC CODE



SECTION 01 100 - SCOPE OF WORK

THE WORK:
THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

RELATED DOCUMENTS:
A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY AND COLLECTIVELY.
B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING.
1. EN-201 2-001 : (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS)
2. TS-0200 - (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)
3. EL-0568: (FIBER TESTING POLICY)
4. NP-312-201 : (EXTERIOR GROUNDING SYSTEM TESTING)
5. NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

PRECEDENCE:
SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

NATIONALLY RECOGNIZED CODES AND STANDARDS:
THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
C. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
G. AMERICAN CONCRETE INSTITUTE (ACI)
H. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
I. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
J. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
K. PORTLAND CEMENT ASSOCIATION (PCA)
L. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
M. BRICK INDUSTRY ASSOCIATION (BIA)
N. AMERICAN WELDING SOCIETY (AWS)
O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
P. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
Q. DOOR AND HARDWARE INSTITUTE (DHI)
R. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
S. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

DEFINITIONS:
A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND ITS OPERATING ENTITIES.
C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR, INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
F. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT.

SITE FAMILIARITY:
CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

POINT OF CONTACT:
COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

ON-SITE SUPERVISION:
THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

DRAWINGS REQUIRED AT JOBSITE:
THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
A. THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

USE OF JOB SITE:
THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

UTILITY SERVICES:
WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

PERMITS/FEE:
WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

CONTRACTOR:
CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:
CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

TEMPORARY UTILITIES AND FACILITIES:
THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

ACCESS TO WORK:
THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

DIMENSIONS:
VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

EXISTING CONDITIONS:
NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

FURNISHED MATERIALS:
COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

RECEIPT OF MATERIAL AND EQUIPMENT:
A. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
B. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
C. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
D. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

DELIVERABLES:
A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

SECTION 01 300 - CELL SITE CONSTRUCTION

NOTICE TO PROCEED:
A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S ISSUANCE OF THE WORK ORDER.
B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

GENERAL REQUIREMENTS FOR CONSTRUCTION:
A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

FUNCTIONAL REQUIREMENTS:
A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND BACKHAUL (FIBER, COPPER, OR MICROWAVE).
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- 18. CONDUCT ALL REQUIRED TESTS AND INSPECTIONS
- 19. PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
- 20. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING, INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS.

DELIVERABLES:
A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
1. PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUESTED BY SPRINT
2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLOAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL SITE PHOTOS
3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.
4. ALL REQUIRED TEST REPORTS.
5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:
a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION
b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD
c. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS
d. LIEN WAIVERS
e. FINAL PAYMENT APPLICATION
f. REQUIRED FINAL CONSTRUCTION PHOTOS
g. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
h. LISTS OF SUBCONTRACTORS
B. PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
2. PROJECT PROGRESS REPORTS.
3. PRE-CONSTRUCTION MEETING NOTES.

SECTION 01 400 - TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT CLOSEOUT

TESTS AND INSPECTIONS:
A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
1. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS
2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
3. CONCRETE BREAK TESTS
4. SITE RESISTANCE TO EARTH TEST
5. STRUCTURAL BACKFILL COMPACTION TESTS
6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION.

SUBMITTALS:
A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
B. UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
3. CHEMICAL GROUNDING SYSTEM .
4. REINFORCEMENT CERTIFICATIONS
5. STRUCTURAL BACKFILL TEST RESULTS
6. SWEEP AND FIBER TESTS
7. ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION
8. POST CONSTRUCTION HEIGHT VERIFICATION
9. ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS
C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

TESTING BY THIRD PARTY AGENCY:
A. EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED. AGENCY IS SUBJECT TO APPROVAL BY COMPANY.
1. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
B. REQUIRED THIRD PARTY TESTS:
1. SITE RESISTANCE TO EARTH TEST PER NP-312-201
2. CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED STANDARDS
3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS
4. REBAR PLACEMENT VERIFICATION WITH REPORT
5. TESTING TENSION STUDY FOR ROCK ANCHORS
6. ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION
C. REQUIRED TESTS BY CONTRACTOR
1. COAX SWEEP TESTS PER SPRINT STANDARD TS-0200
2. FIBER TESTS PER SPRINT STANDARD EL-0568
3. MICROWAVE LINK TESTS PER NP-760-500
4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN.



6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com



48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski 2/05/2015
Signature: Date:

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED

ISSUE PHASE FINAL DATE ISSUED 02.05.2015

PROJECT TITLE:
**CROMWELL - RT. 372
CT60XC931-A**

PROJECT INFORMATION:
179 SHUNPIKE ROAD
CROMWELL, CT 06416
MIDDLESEX COUNTY

SHEET TITLE:
SPRINT SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	29431
SHEET NUMBER	SP-1

5. POST CONSTRUCTION HEIGHT VERIFICATION AS REQUIRED HERewith IN THE TOWER INSTALLATION SPECIFICATIONS.
6. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED HERewith IN THE ASPHALT PAVING SPECIFICATIONS.
7. FIELD QUALITY CONTROL TESTING AS SPECIFIED HERewith IN THE CONCRETE PAVING SPECIFICATIONS.
8. TESTING REQUIRED HERewith UNDER SPECIFICATIONS FOR AGGREGATE BASE FOR ROADWAYS
9. ALL OTHER TESTS REQUIRED BY LOCAL JURISDICTION
- D. INSPECTIONS BY COMPANY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN INSPECTION ACTIVITIES, FINAL ACCEPTANCE / PUNCH WALK REVIEW, AND/OR AS A RESULT OF TESTING
- E. SPRINT RESERVES THE RIGHT TO INSPECT THE CONSTRUCTION SITE AT ANY TIME VIA SITE WALKS AND/OR PHOTO REVIEWS. CONTRACTOR SHALL GIVE SPRINT 24 HOURS NOTICE PRIOR TO THE COMMENCEMENT OF THE FOLLOWING CONSTRUCTION ACTIVITIES AND PHOTOGRAPHS OF THE IN-PROGRESS WORK.
 1. GROUNDING SYSTEM AND BURIED UTILITIES INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS, AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS, ASPHALT PAVING, AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE AND POST CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES. PRIOR TO CONSTRUCTION ACTIVITIES AND AFTER CONSTRUCTION IS COMPLETE, PROVIDE PHOTOGRAPHIC DOCUMENTATION OF ROOF, FLASHINGS, AND PARAPETS, BOTH BEFORE AND AFTER CONSTRUCTION IS COMPLETE.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. TOWER TOP AND INACCESSIBLE EQUIPMENT (RRUS, ANTENNAS, AND CABLING): PROVIDE PHOTOS OF THE BACKS OF ALL ANTENNAS, RRUS, COMBINERS, FILTERS, FIBER AND DC CABLING, CABLE COLOR CODING, EQUIPMENT GROUNDING AND CONNECTOR WATER PROOFING INCLUDING NAME PLATE AND SERIAL NUMBER FOR ALL SERIALIZED EQUIPMENT.

PROJECT CLOSEOUT:

- A. FINAL ACCEPTANCE PUNCH WALK AND INSPECTION: AS IDENTIFIED IN THE SCOPE OF SERVICES, SPRINT WILL CONDUCT A FINAL PUNCH WALK OR FINAL DESK TOP PHOTO REVIEW (SITE MODIFICATIONS). PUNCH WALKS MUST BE SCHEDULED IN ADVANCE AS REQUIRED. AT THE PUNCH WALK / REVIEW, SPRINT MAY IDENTIFY CRITICAL DEFICIENCIES WHICH MUST BE CORRECTED PRIOR TO PUTTING SITE ON AIR. MINOR DEFICIENCIES MUST BE CORRECTED WITHIN 30 DAYS EXCEPT AS OTHERWISE REQUIRED. VERIFICATIONS OF CORRECTIONS MAY BE MADE BY COMPANY DURING A REPEAT SITE WALK OR DESK TOP PHOTO REVIEW AT COMPANY'S SOLE DISCRETION.
- B. CLOSEOUT DOCUMENTATION: ALL CLOSEOUT DOCUMENTATION AND PHOTOGRAPHS SHALL BE UPLOADED PRIOR TO FINAL ACCEPTANCE. SPRINT WILL REVIEW CLOSEOUT DOCUMENTATION FOR PRESENCE AND CONTENT. CLOSEOUT DOCUMENTATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING AS APPLICABLE:
 1. COAX SWEEP TESTS:
 2. FIBER TESTS:
 3. JURISDICTION FINAL INSPECTION DOCUMENTATION
 4. REINFORCEMENT CERTIFICATION (MILL CERTIFICATION)
 5. CONCRETE MIX DESIGN AND PRODUCT DATA (TOWER FOUNDATION)
 6. LIEN WAIVERS AND RELEASES.
 7. POST -CONSTRUCTION HEIGHT VERIFICATION
 8. JURISDICTION CERTIFICATE OF OCCUPANCY
 9. ELECTRONIC ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 10. STRUCTURAL BACKFILL TEST RESULTS (IF APPLICABLE)
 11. CELL SITE UTILITY SETUP
 12. AS-BUILT REDLINE CONSTRUCTION DRAWINGS (PDF SCAN OF FIELD MARKS)
 13. AS-BUILT CONSTRUCTION DRAWINGS IN DWG AND PDF FORMATS
 14. LIST OF SUB CONTRACTORS
 15. APPROVED PERMITTING DOCUMENTS
- C. FINAL SITE PHOTOS UP-LOADED TO SITERRA. INCLUDE THE FOLLOWING AS APPLICABLE:
 - a. TOWER, ANTENNAS, RRUS, AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX/CABLE LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - b. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 - c. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 - d. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.

PROJECT PHOTOGRAPHS:

- A. PROVIDE PROJECT CLOSEOUT GENERAL ARRANGEMENT PHOTOS OF ALL NEW WORK. THE FOLLOWING LIST REPRESENTS MINIMUM REQUIREMENTS AND MINIMUM QUANTITY. ADDITIONAL PHOTOS MAY BE REQUIRED TO ADEQUATELY DOCUMENT THE WORK.
 1. ASR AND RF MPE SIGNAGE (IF NOT IN PLACE, SUPPLIER NOTIFIES EMS FIELD REPRESENTATIVE)
 2. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR)
 3. BACK OF ANTENNAS AND RRUS (1 EACH SECTOR) CLOSE UP SHOWING WEATHERPROOFING AND GROUNDING (AS REQUIRED). CLOSE-UP OF BACK SIDE OF EACH PERMANENT RRU SHOWING SERIAL NUMBER/BAR CODE.
 4. VIEW (1 EACH SECTOR) ALONG THE AZIMUTH AND TILT OF THE ANTENNAS
 5. TOP OF TOWER FROM GROUND, 1 EACH SECTOR
 6. MAINLINE HYBRID CABLE ROUTE DOWN TOWER SHOWING FASTENERS AND SUPPORT
 7. MAINLINE/HYBRID CABLE ROUTE ALONG ICE BRIDGE OR IN CABLE TRAY SHOWING FASTENERS AND SUPPORT
 8. GROUND MOUNTED RRU RACKS (FRONT AND BACK)
 9. FRONT, SIDE AND BACK ELEVATIONS OF ALL GROUND CABINETS
 10. VIEW OF COMPOUND FROM A DISTANCE
 11. VIEW OF EACH GROUND CABINET (POWER, RF, FIBER SPOOL, PPC POWER, PPC TELCO WITH DOOR OPEN)
 12. BACKHAUL FIBER MEET-ME-POINT AND CONDUIT ROUTE (MICROWAVE INSTALLATION IF NOT FIBER)
 13. AAV NETWORK INTERFACE DEVICE OR MICROWAVE RADIO INSTALLATION

DEFICIENCY CORRECTIONS:

CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIONS TO DEFICIENCIES IDENTIFIED THROUGH TESTING, REVIEW OF SUBMITTALS, INSPECTIONS AND CLOSEOUT REVIEWS.

SECTION 01 500 - PROJECT REPORTING

WEEKLY REPORTS:

- A. CONTRACTOR SHALL REPORT TO SPRINT AT MINIMUM ON A WEEKLY BASIS VIA SITERRA BY UPDATING ALL APPLICABLE POST END KEEPING MILESTONES WITH ACTUAL AND FORECASTED COMPLETION DATES.
- B. ADDITIONAL REQUIREMENTS FOR REPORTING MAY BE IDENTIFIED ELSEWHERE OR REQUIRED BY THE SCOPE OF SERVICES OR SPRINTS LOCAL MARKET CONSTRUCTION MANAGER. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

PROJECT CONFERENCE CALLS:

SPRINT MAY HOLD PERIODIC PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

FINAL PROJECT ACCEPTANCE: PRIOR TO SPRINTS FINAL PROJECT ACCEPTANCE. ALL REQUIRED MILESTONE ACTUALS MUST BE UPDATED IN SITERRA AND ALL REQUIRED REPORTING TASKS MUST BE COMPLETE.

SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO UNITS AND CABLE INSTALLATION

SUMMARY:

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRUS, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

ANTENNAS AND RRUS:

THE NUMBER AND TYPE OF ANTENNAS AND RRUS TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE:

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

JUMPERS AND CONNECTORS:

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRUS AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRUS AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE, MIN. LENGTH FOR JUMPER SHALL BE 10'-0".

REMOTE ELECTRICAL TILT (RET) CABLES:

MISCELLANEOUS:

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

ANTENNA INSTALLATION:

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.

B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

HYBRID CABLE INSTALLATION:

A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.

C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.

1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE INSTALLED INSIDE MONOPOLE WITH CABLE SUPPORT GRIPS AS REQUIRED BY THE MANUFACTURER.
2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
 - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH AT 18" O.C. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
 - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
4. CABLE INSTALLATION:
 - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
 - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSEOVERS.
 - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.
5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 (CURRENT VERSION).
7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.

B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.

1. COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CX5 SERIES OR EQUAL.
2. SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBS) AND RELATED EQUIPMENT

SUMMARY:

A. THIS SECTION SPECIFIES MMBS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).

B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRED BY THE APPLICABLE INSTALLATION MOPS.

C. COMPLY WITH MANUFACTURER'S INSTALLATION AND START-UP REQUIREMENTS.

DC CIRCUIT BREAKER LABELING

A. NEW DC CIRCUIT IS REQUIRED IN MMBS CABINET SHALL BE CLEARLY IDENTIFIED AS TO RRU BEING SERVICED.

SECTION 26 100 - BASIC ELECTRICAL REQUIREMENTS

SUMMARY:

THIS SECTION SPECIFIES BASIC ELECTRICAL REQUIREMENTS FOR SYSTEMS AND COMPONENTS

QUALITY ASSURANCE:

A. ALL EQUIPMENT FURNISHED UNDER DIVISION 26 SHALL CARRY UL LABELS AND LISTINGS WHERE SUCH LABELS AND LISTINGS ARE AVAILABLE IN THE INDUSTRY.

B. MANUFACTURERS OF EQUIPMENT SHALL HAVE A MINIMUM OF THREE YEARS EXPERIENCE WITH THEIR EQUIPMENT INSTALLED AND OPERATING IN THE FIELD IN A USE SIMILAR TO THE PROPOSED USE FOR THIS PROJECT.

C. MATERIALS AND EQUIPMENT: ALL MATERIALS AND EQUIPMENT SPECIFIED IN DIVISION 26 OF THE SAME TYPE SHALL BE OF THE SAME MANUFACTURER AND SHALL BE NEW, OF THE BEST QUALITY AND DESIGN, AND FREE FROM DEFECTS.

SUPPORTING DEVICES:

- A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
 1. ALLIED TUBE AND CONDUIT.
 2. B-LINE SYSTEM.
 3. UNISTRUT DIVERSIFIED PRODUCTS.
 4. THOMAS & BETTS.
- B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:
 1. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
 2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
 3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
 4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
 5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
 6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
 7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
 8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
 9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.



6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com



48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED

ISSUE PHASE: FINAL DATE ISSUED: 02.05.2015

PROJECT TITLE:

CROMWELL - RT. 372
CT60XC931-A

PROJECT INFORMATION:
179 SHUNPIKE ROAD
CROMWELL, CT 06416
MIDDLESEX COUNTY

SHEET TITLE:

SPRINT SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER: 29431
SHEET NUMBER: SP-2

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
 - 1. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
 - 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6-FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21 MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
 - 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY ROXTEC.
 - 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS. CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM:

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED

ISSUE PHASE	FINAL	DATE ISSUED	02.05.2015
-------------	-------	-------------	------------

PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
SPRINT SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	29431
SHEET NUMBER	SP-3



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




James R. Skowronski
 Signature: _____ Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015


PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
SITE PLAN




PROJECT NUMBER: 29431
 SHEET NUMBER: A-1



SITE PLAN
 SCALE: 1" = 15'

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.



(1) PROPOSED 1 1/4" HYBRID CABLE ROUTED W/EXISTING CABLES FROM FIBER DISTRIBUTION BOX TO ALPHA ANTENNA SECTOR (±315') AND HYBRID JUMPERS TO BETA AND GAMMA ANTENNA SECTORS. CONTRACTOR TO USE SNAP-INS AS REQUIRED, MAX 4'-0" O.C.

EQUIPMENT PLAN
 SCALE: 1" = 2.5'



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015


PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
EQUIPMENT PLAN



PROJECT NUMBER: 29431
 SHEET NUMBER: A-2



NOTE: A STRUCTURAL ANALYSIS AND REINFORCEMENT DESIGN FOR THE TOWER HAS BEEN COMPLETED BY URS CORPORATION, (DATED 09.23.2014) AND IS OUTSIDE THE PURVIEW OF RAMAKER & ASSOCIATES, INC. CONTRACTOR TO ENSURE ALL PROPOSED STRUCTURAL MODIFICATIONS AND SPRINT EQUIPMENT ARE INSTALLED IN ACCORDANCE WITH THE URS STRUCTURAL ANALYSIS AND REINFORCEMENT DESIGN.

BUILDING ELEVATION
 SCALE: 1" = 25'



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015


MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED

ISSUE PHASE: FINAL DATE ISSUED: 02.05.2015


PROJECT TITLE:
 CROMWELL - RT. 372
 CT60XC931-A

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY


SHEET TITLE:
 TOWER ELEVATION




PROJECT NUMBER: 29431
 SHEET NUMBER: A-3



ANTENNA & RRH MOUNTING DETAILS
 SCALE: NTS



EXISTING ANTENNA ARRAY
 SCALE: NTS



PROPOSED ANTENNA ARRAY
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski 2/05/2015
 Signature Date

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015

PROJECT TITLE:
 CROMWELL - RT. 372
 CT60XC931-A

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
 ANTENNA DETAILS

SCALE:
 AS NOTED

PROJECT NUMBER 29431
 SHEET NUMBER A-4

RFDS Sheet

General Site Information

Site ID	CT60XC931	Equipment Vendor	Alcatel-Lucent
Market	Southern Connecticut	Site ID	41.623261
Region	Northeast	Longitude	-72.679339
MLA	N/A	LL SITE ID	N/A
Structure Type	Self Support		
BTS Type			
Solution ID		Siterra SR Equipment type	
		Equipment Vendor	Alcatel-Lucent

Incremental Power Draw
 needed by added Equipment
40 amp

Base Equipment

BBU Kit	ALU BBU Kit	Top Hat	None
BBU Kit Qty	1	Top Hat Qty	N/A
Growth Cabinet	9929 MT-BTS	Top Hat Dimensions	N/A
Growth Cabinet Qty	1	Top Hat Weight (lbs)	N/A
Growth Cabinet Dimensions	63.65"x31.5"x35.5"		
Growth Cabinet Weight	1600 lbs		

RF Path Information

RRH	TD-RRH8x20-25
RRH Qty	3
RRH Dimensions	26.1"x18.6"x6.7"
RRH Weight. lbs.	70
RRH Mount Weight. Lbs.	10
Power and Fiber Cable	ALU Hybrid Cable
Cable Qty	1
Weight per foot. Lbs.	0.992
Diameter. Inches.	1.25
Length Ft.	315 (calculated as coax run & antenna height plus 20%)
Coax Jumper	0.625
Coax Jumper Qty	27
Coax Jumper Length. Feet.	8
Coax Jumper Weight	1.7
Coax Jumper Diameter. Inches	0.5
AISG Cable	Commscope ATCB-B01-006
AISG Cable Qty	3
AISG Diameter. Inches.	0.315
AISG Cable length.	8
Weight of entire AISG cable. Lbs.	1.3

Antenna Sector Information

	Sector 1	Sector 2	Sector 3
Antenna make/model	RFS APXV9TM14-ALU-120	RFS APXV9TM14-ALU-120	RFS APXV9TM14-ALU-120
Antenna qty	1	1	1
Antenna Dimensions. Inches	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"	56.3"x12.6"x6.3"
Antenna Weight. Lbs	55.12	55.12	55.12
Antenna Mounting Kit Weight. Lbs.	11.5	11.5	11.5
CL Height	170'-0"	170'-0"	170'-0"
Antenna Azimuth	90	175	260
Antenna Mechanical Downtilt	0	0	0
Antenna etilt	-2	-2	-2

*RFDS SHEET WAS GENERATED BY RAMAKER & ASSOCIATES FROM PLAN OF RECORD (POR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

NOTES:

- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS 1.9GHZ ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT 1.9GHZ AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT IS LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND 1.9GHZ AND 800MHZ ANTENNA.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015


PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY


SHEET TITLE:
RF DATA SHEET

SCALE:
 AS NOTED


PROJECT NUMBER: 29431
 SHEET NUMBER: A-5




TYPICAL FIBER DISTRIBUTION BOX DETAIL
 SCALE: NTS




RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL
 SCALE: NTS



8T8R DETAIL
 SCALE: NTS



BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL
 SCALE: NTS



RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015


PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
FIBER PLUMBING DIAGRAM

SCALE:
 AS NOTED

PROJECT NUMBER: 29431
 SHEET NUMBER: A-6



SECTOR COLOR CODING AND BANDING
 SCALE: NTS

2.5 Coaxial Cable Color Code (Radio#1)

Sector	Cable	Start at Connector Side	Wrap2	Wrap3	Wrap4	Wrap5
1 Alpha	1	Blue			Yellow	White
	2	Orange			Yellow	White
	3	Green			Yellow	White
	4	Brown			Yellow	White
	5	Slate			Yellow	White
	6	White			Yellow	White
	7	Red			Yellow	White
	8	Violet			Yellow	White
1	Calibration Cable	Yellow			Yellow	White
	Cable	Yellow			Yellow	White
2 Beta	1	Blue	Blue		Yellow	White
	2	Orange	Orange		Yellow	White
	3	Green	Green		Yellow	White
	4	Brown	Brown		Yellow	White
	5	Slate	Slate		Yellow	White
	6	White	White		Yellow	White
	7	Red	Red		Yellow	White
	8	Violet	Violet		Yellow	White
2	Calibration Cable	Yellow	Yellow		Yellow	White
	Cable	Yellow	Yellow		Yellow	White
3 Gamma	1	Blue	Blue	Blue	Yellow	White
	2	Orange	Orange	Orange	Yellow	White
	3	Green	Green	Green	Yellow	White
	4	Brown	Brown	Brown	Yellow	White
	5	Slate	Slate	Slate	Yellow	White
	6	White	White	White	Yellow	White
	7	Red	Red	Red	Yellow	White
	8	Violet	Violet	Violet	Yellow	White
3	Calibration Cable	Yellow	Yellow	Yellow	Yellow	White
	Cable	Yellow	Yellow	Yellow	Yellow	White

2.5 Coaxial Cable Color Code (Radio#2)

Sector	Cable	Start at Connector Side	Wrap2	Wrap3	Wrap4	Wrap5
1 Alpha	1	Blue			Yellow	Violet
	2	Orange			Yellow	Violet
	3	Green			Yellow	Violet
	4	Brown			Yellow	Violet
	5	Slate			Yellow	Violet
	6	White			Yellow	Violet
	7	Red			Yellow	Violet
	8	Violet			Yellow	Violet
1	Calibration Cable	Yellow			Yellow	Violet
	Cable	Yellow			Yellow	Violet
2 Beta	1	Blue	Blue		Yellow	Violet
	2	Orange	Orange		Yellow	Violet
	3	Green	Green		Yellow	Violet
	4	Brown	Brown		Yellow	Violet
	5	Slate	Slate		Yellow	Violet
	6	White	White		Yellow	Violet
	7	Red	Red		Yellow	Violet
	8	Violet	Violet		Yellow	Violet
2	Calibration Cable	Yellow	Yellow		Yellow	Violet
	Cable	Yellow	Yellow		Yellow	Violet
3 Gamma	1	Blue	Blue	Blue	Yellow	Violet
	2	Orange	Orange	Orange	Yellow	Violet
	3	Green	Green	Green	Yellow	Violet
	4	Brown	Brown	Brown	Yellow	Violet
	5	Slate	Slate	Slate	Yellow	Violet
	6	White	White	White	Yellow	Violet
	7	Red	Red	Red	Yellow	Violet
	8	Violet	Violet	Violet	Yellow	Violet
3	Calibration Cable	Yellow	Yellow	Yellow	Yellow	Violet
	Cable	Yellow	Yellow	Yellow	Yellow	Violet

2.5 COAXIAL CABLE COLOR CODE
 SCALE: NTS

CABLE MARKING NOTES

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE 1" SPACE BETWEEN EACH RING.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53585
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015

PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
CABLE COLOR CODING

SCALE:
 AS NOTED

PROJECT NUMBER: 29431
 SHEET NUMBER: A-7

Copyright 2014 - Ramaker & Associates, Inc. - All Rights Reserved
 DRAWN BY: SJS
 CHECKED BY: KAB
 C:\Users\steves\local settings\temp\AcPublish_696a2943_1_2_5_Equipment Deployment Drawings.dwg Printed by: steves on Feb 05, 2015 - 12:52pm

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE
MANUF:RFS

CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
Fiber Only	Varies	Use NV Hybriflex	5/8"
Hybriflex	<200'	8 AWG	1-1/4"
Hybriflex	225-300'	6 AWG	1-1/4"
Hybriflex	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE


FIBER ONLY (EXISTING DC POWER)	Hybrid cable	
MN-HB058-M12-050F	12x multi-mode fiber pairs, Top:Outdoor protected connectors, Bottom:LC	50 ft
MN-HB058-M12-075F	Connectors, 5/8 cable, 50 ft	75 ft
MN-HB058-M12-100F		100 ft
MN-HB058-M12-125F		125 ft
MN-HB058-M12-150F		150 ft
MN-HB058-M12-175F		175 ft
MN-HB058-M12-200F		200 ft
8 AWG Power	Hybrid cable	
MN-HB114-08U3M12-050F	3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 50 ft	50 ft
MN-HB114-08U3M12-075F		75 ft
MN-HB114-08U3M12-100F		100 ft
MN-HB114-08U3M12-125F		125 ft
MN-HB114-08U3M12-150F		150 ft
MN-HB114-08U3M12-175F		175 ft
MN-HB114-08U3M12-200F		200 ft
6 AWG Power	Hybrid cable	
MN-HB114-13U3M12-225F	3x 6 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 225 ft	225 ft
MN-HB114-13U3M12-250F		250 ft
MN-HB114-13U3M12-275F		275 ft
MN-HB114-13U3M12-300F		300 ft
4 AWG Power	Hybrid cable	
MN-HB114-21U3M12-325F	3x 4 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC connectors. 1 1/4 cable, 325 ft	325 ft
MN-HB114-21U3M12-350F		350 ft
MN-HB114-21U3M12-375F		375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE

FIBER ONLY	Hybrid Jumper cable	
MN-HBF012-M3-5F1	5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
MN-HBF012-M3-10F1		10 ft
MN-HBF012-M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		
8 AWG POWER	Hybrid Jumper cable	
MN-HBF058-08U1M3-5F1	5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft
MN-HBF058-08U1M3-10F1		10 ft
MN-HBF058-08U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		
6 AWG POWER	Hybrid Jumper cable	
MN-HBF058-13U1M3-5F1	5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 5/8 cable	5 ft
MN-HBF058-13U1M3-10F1		10 ft
MN-HBF058-13U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		
4 AWG POWER	Hybrid Jumper cable	
MN-HBF078-21U1M3-5F1	5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC connectors, 7/8 cable	5 ft
MN-HBF078-21U1M3-10F1		10 ft
MN-HBF078-21U1M3-15F1		15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'		
NOTIFY SPRINT CM OF ANY DISCREPANCY		


*NOTE: SPRINT CM TO CONFIRM HYBRID/FIBER RISER CABLE & HYBRID/FIBER JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.

HYBRID CABLE CROSS SECTION & DATA
SCALE: NTS




RFS: APXV9TM | 4-ALU- | 20

DIMENSIONS, HxWxD: 56.3" x 12.6" x 6.3"
 WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs.
 CONNECTOR: (9) XX" MINI-DIN FEMALE/BOTTOM



2.5 ANTENNA DETAIL
SCALE: NTS



ALCATEL-LUCENT: TD-RRH8x20
 HxWxD = (26.1" x 18.6" x 6.7")
 WEIGHT = 70 lbs.

2.5 RRH DETAIL
SCALE: NTS



6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53585
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com



48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015

PROJECT TITLE:
CROMWELL - RT. 372
CT60XC93 | -A


PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
ANTENNA & HYBRID CABLE
DETAILS

SCALE:
AS NOTED

PROJECT NUMBER	29431
SHEET NUMBER	A-8


This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.



NOTES:

1. LINE UP WHITE MARKINGS ON JUMPER AND RISER IP-MPO CONNECTORS AND SLIDE THE RISER CONNECTOR TO THE JUMPER CONNECTOR. PUSH THE WHITE MARK ON THE JUMPER CONNECTOR FLUSH AGAIN THE RED SEAL ON THE RISER CONNECTOR.
2. ROTATE THE BAYONET HOUSING CLOCKWISE UNTIL YOU HEAR A CLICK SOUND.


HYBRID BREAKOUT DETAIL
SCALE: NTS




CABLE ROUTE FROM CABINET
SCALE: NTS



EXISTING BBU CABINET
SCALE: NTS



EXISTING MMBS CABINET
SCALE: NTS



6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com



48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015

PROJECT TITLE:
CROMWELL - RT. 372
CT60XC931-A

PROJECT INFORMATION:
179 SHUNPIKE ROAD
CROMWELL, CT 06416
MIDDLESEX COUNTY


SHEET TITLE:
EQUIPMENT DETAILS

SCALE:
AS NOTED

PROJECT NUMBER: 29431
SHEET NUMBER: A-9

ALCATEL-LUCENT 9929 MULTI TECHNOLOGY BTS OUTDOOR CABINET

In order to help network operators to improve TCO for distributed radio based sites with extended battery backup requirements, Alcatel-Lucent proposes the 9929 Multi Technology Outdoor Cabinet for CDMA/LTE/WCDMA multi-standard configurations



9929 MT-BTS OUTDOOR CABINET

- The 9929 MT-BTS cabinet is designed to provide, in a single footprint, a full site support with a capability to host 3G and 4G Telecom equipment with internal power and battery support.
- The 9929 MT-BTS Outdoor Cabinet offers 17.5 U of user space capable of hosting 19" rack based telecom equipment and rectification. The 9929 MT-BTS supports distributed RF deployment scenarios with the hosting of Digital base band unit and transport equipment.
- The 9929 MT-BTS cabinet can host up of 2 strings of batteries.
- The 9929 MT-BTS is AC powered and can deliver up to 10.5kW of -48V DC power thanks to its internal N+1 redundant rectifier.
- The 19" modules could have either front-back or side-side cooling. The cabinet uses direct air-cooling (fresh air filter) technology on front door to provide 8000 W of cooling capacity. A wide temperature operating range (-40°C to +50°C full operation) allows the deployment of this cabinet in various locations.
- The 9929 MT-BTS cabinet is compliant with Zone 4 earthquake regulations.
- As an matter of example the following configuration is supported by the cabinet:
 - ✓ Distributed configuration: AC configuration with up to 10.5kW DC Power, up to 3 baseband units, 2U service aggregation router, 2U of microwave transport equipment, up to 2 battery of 190AH.

FEATURES

- Can host BBU(s) for CDMA/WCDMA/LTE
- Supports standard 19" Telecom equipment
- Uses Direct Air Cooling (no air conditioning) with fan speed control based upon temperature
- Support of up to two 190 Ah or up to two 145AH battery strings that can provide backup for 8 hours for up to 2375 W, or 4 hour backup for up to 4150
- Convenience AC outlet (2)

TECHNICAL SPECIFICATIONS

INTERFACE:

- CPRI (up to 9 RRH modules)
- Backhaul (Gigabit Ethernet or T1)
- External user alarms (up to 32 user alarms)
- AC Power input
- DC Power input for RRH (up to 9 RRH's)

PHYSICAL DIMENSIONS

- Height: 1617 mm (63.65 in)
- Width: 800 mm (31.5 in)
- Depth: 900 mm (35.5 in)

WEIGHT

- 197 kg (434 lbs) unloaded
- Up to 725 kg (1600 lbs) fully loaded

POWER

- Power supply:
 - 48 VDC
 - 230V AC (single phase or 3 phases)
- Rectifier:
 - up to 10.5kW DC -48V output power
 - Rectifier redundancy N+1

SUPPORTED TELECOM EQUIPMENT

- LTE 9926 BBU
- CDMA 9926 BBU
- WCDMA 9926 BBU
- SAR Aggregation router
- Microwave Indoor Unit

OPERATING ENVIRONMENT


- Outdoor temperature range: -40°C to +50°C
- Direct Air Cooling
- Enclosure:
 - IP55 (International Protection rating)
 - Zone 4 Earthquake

STANDARDS COMPLIANCY

- UL 60950-1 / CAN/CSA C22.2 No. 60950-1-07
- UL 50/50E CSA C22.2 No. 94.1- 07/94.2-07
- EN50272-2
- EIA-310-D

EMC & ENVIRONMENTAL CONDITIONS

- FCC Part 15 class B
- GR-63-CORE,
- GR-487-CORE,
- GR-1089-CORE

.....Alcatel-Lucent 
 AT THE SPEED OF IDEAS™

9929 Multi Technology Outdoor BTS
 ALCATEL-LUCENT DATA SHEET
 2

Alcatel-Lucent 

PROPOSED 9929 MT-BTS
 OUTDOOR CABINET
 SCALE: NTS

1



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski Signature: _____ Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015



PROJECT TITLE:
 CROMWELL - RT. 372
 CT60XC931-A

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
 EQUIPMENT DETAILS

SCALE:
 AS NOTED

PROJECT NUMBER	29431
SHEET NUMBER	A-10



- GROUNDING NOTES:**
1. CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
 2. ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.
 3. ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (GADWELD).
 4. ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.
 5. CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE.
 6. MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5 OHMS.
 7. WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BEAR METAL TO ENSURE PROPER CONTACT AND RESTORED/PAINTED TO ORIGINAL FINISH.
 8. GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

LEGEND:

---	EXISTING GROUND CABLE
---	PROPOSED GROUND CABLE
▲	MECHANICAL CONNECTION
■	EXOTHERMIC CONNECTION
—E—E—E—E—E—	PROPOSED ELECTRIC



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251



1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski 2/05/2015
 Signature: Date:

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015

PROJECT TITLE:
**CROMWELL - RT. 372
 CT60XC931-A**

PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY


SHEET TITLE:
**EQUIPMENT UTILITY &
 GROUNDING PLAN**

SCALE:
 AS NOTED


PROJECT NUMBER: 29431
 SHEET NUMBER: E-1

SYMBOL LEGEND

- ▲ MECHANICAL CONNECTION
- EXOTHERMIC CONNECTION




GROUNDING RISER DIAGRAM
 SCALE: NTS



- NOTES:**
1. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

GROUNDING CONDUCTOR INSTALLATION
 SCALE: NTS



TWO-HOLE LUG
 SCALE: NTS



6580 SPRINT PARKWAY
 OVERLAND PARK, KANSAS 66251




1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com



48 SPRUCE STREET
 OAKLAND, NJ 07346

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 2/05/2015

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED
ISSUE PHASE	FINAL	DATE ISSUED 02.05.2015

PROJECT TITLE:
 CROMWELL - RT. 372
 CT60XC931-A


PROJECT INFORMATION:
 179 SHUNPIKE ROAD
 CROMWELL, CT 06416
 MIDDLESEX COUNTY

SHEET TITLE:
 GROUNDING DETAILS

SCALE:
 AS NOTED

PROJECT NUMBER	29431
SHEET NUMBER	E-2

Copyright 2014 - Ramaker & Associates, Inc. - All Rights Reserved
 DRAWN BY: SJS
 CHECKED BY: KAB
 C:\Users\steves\local settings\temp\AcPublish_696a2943_2_5_Equipment Deployment Drawings.dwg
 Printed by: steves on Feb 05, 2015 - 12:53pm





A/C PANEL SCHEDULE

VOLTAGE:	240V/120	PANEL STATUS:	EXISTING	N TO GROUND BOND:	YES
MAIN BREAKER:	200 AMP	MODEL NUMBER:	TBD	INTERNAL TVSS:	YES
MOUNT:	SHELTER	PHASE:	1	WIRE:	3
ENCLOSURE TYPE:	NEMA 3R	BUSS RATING:	200 AMP	GROUND BAR:	YES
		NEUTRAL BAR:	YES		

CKT	DESCRIPTION	BREAKER AMPS	BREAKER POLES	BREAKER STATUS	PHASE A VA	PHASE B VA	BREAKER STATUS	BREAKER POLES	BREAKER AMPS	DESCRIPTION	CKT
1	SURGE	60	2	ON			OFF	1	10	SPARE	13
2							ON	1	15	GFI	14
3	RADIO 1	80	2	ON			ON	2	60	HVAC 1	15
4							ON	2	60	HVAC 2	16
5	RADIO 2	80	2	ON			ON	2	60	HVAC 2	17
6							ON	2	60	HVAC 2	18
7	NEW 2.5 CABINET	40	2	ON			OFF	2	30	SPARE	19
8							OFF	2	30	SPARE	20
9	BLANK (UNUSED)	-	-	-			-	-	-	BLANK (UNUSED)	21
10	BLANK (UNUSED)	-	-	-			-	-	-	BLANK (UNUSED)	22
11	BLANK (UNUSED)	-	-	-			-	-	-	BLANK (UNUSED)	23
12	BLANK (UNUSED)	-	-	-			-	-	-	BLANK (UNUSED)	24

AC PANEL SCHEDULE
SCALE: NTS



Sprint

6580 SPRINT PARKWAY
OVERLAND PARK, KANSAS 66251

RAMAKER & ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

Transcend Wireless

48 SPRUCE STREET
OAKLAND, NJ 07346

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

STATE OF CONNECTICUT
JAMES R. SKOWRONSKI
26266
LICENSED PROFESSIONAL ENGINEER

James R. Skowronski 2/05/2015
Signature Date

MARK	DATE	DESCRIPTION
A	2.5.15	FINAL CD'S ISSUED

ISSUE PHASE: FINAL DATE ISSUED: 02.05.2015

PROJECT TITLE:
**CROMWELL - RT. 372
CT60XC931-A**

PROJECT INFORMATION:
179 SHUNPIKE ROAD
CROMWELL, CT 06416
MIDDLESEX COUNTY

SHEET TITLE:
**DC POWER DETAILS
& PANEL SCHEDULES**

SCALE:
AS NOTED

PROJECT NUMBER: 29431
SHEET NUMBER: E-3

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.