

March 26, 2015

Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: **Notice of Exempt Modification – Facility Modification
179 Shunpike Road, Cromwell, Connecticut**

Dear Ms. Bachman:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains twelve (12) wireless telecommunications antennas at the 101-foot level on the existing 170-foot lattice tower at 179 Shunpike Road, Cromwell, Connecticut (the “Property”). The tower and the Property are owned by the Cromwell Fire District. Cellco’s use of the tower was approved by the Council in 2007. Cellco now intends to modify its facility by replacing three (3) of its existing antennas with three (3) model LNX-4514DS-VTM, 700 MHz antennas at the same level on the tower. Included in Attachment 1 are specifications for Cellco’s replacement antennas.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is also being sent to Anthony J. Salvatore, Acting Town Manager for the Town of Cromwell and the Cromwell Fire District.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Cellco’s replacement antennas are located at the 101-foot level of the 170-foot tower.

Robinson+Cole

Melanie A. Bachman
March 26, 2015
Page 2

2. The proposed modifications will not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundary.

3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.

4. The operation of the replacement antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. A cumulative General Power Density table for Cellco's modified facility is included in Attachment 2.

5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.

6. The tower and its foundation can support Cellco's proposed modifications. (See Structural Analysis dated January 7, 2015, included in Attachment 3). Please note that the attached January 7, 2015 Structural Analysis assumes that tower modifications described in a September 23, 2014 Structural Analysis, for Sprint and T-Mobile have been completed. A copy of the January 7, 2015 Structural Analysis is included in Attachment 4.

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kenneth C. Baldwin

Enclosures

Copy to:

Anthony J. Salvatore, Cromwell Acting Town Manager
Tim Parks

ATTACHMENT 1

Product Specifications

COMMScope®

LNX-4514DS-VTM

Andrew® Antenna, 698–896 MHz, 45° horizontal beamwidth, RET compatible

POWERED BY



Electrical Specifications

Frequency Band, MHz	698–806	806–896
Gain, dBi	15.5	16.4
Beamwidth, Horizontal, degrees	47	45
Beamwidth, Vertical, degrees	17.3	15.8
Beam Tilt, degrees	2–18	2–18
USLS, typical, dB	16	15
Front-to-Back Ratio at 180°, dB	32	28
Isolation, dB	30	30
VSWR Return Loss, dB	1.4 15.6	1.4 15.6
PIM, 3rd Order, 2 x 20 W, dBc	-153	-153
Input Power per Port, maximum, watts	500	500
Polarization	±45°	±45°

Mechanical Specifications

Color Radome Material	Light gray Fiberglass, UV resistant
Connector Interface Location Quantity	7-16 DIN Female Bottom 2
Wind Loading, maximum	586.4 N @ 150 km/h 131.8 lbf @ 150 km/h
Wind Speed, maximum	241.4 km/h 150.0 mph
Antenna Dimensions, L x W x D	1308.0 mm x 389.0 mm x 163.0 mm 51.5 in x 15.3 in x 6.4 in
Net Weight	13.3 kg 29.3 lb

Model with factory installed AISG 2.0 RET LNX-4514DS-A1M

ATTACHMENT 2

Site Name: Cromwell N Tower Height: 170Ft.	General			Power	Density				
	CARRIER	# OF CHAN.	WATTS ERP	HEIGHT	CALC. POWER DENS	FREQ.	MAX. PERMISS. EXP.	FRACTION MPE	Total
*AT&T UMTS	2	565	115	0.0307	880	0.5867	5.24%		
*AT&T UMTS	2	875	115	0.0476	1900	1.0000	4.76%		
*AT&T GSM	1	283	115	0.0077	880	0.5867	1.31%		
*AT&T GSM	4	525	115	0.0571	1900	1.0000	5.71%		
*AT&T LTE	1	1313	115	0.0357	734	0.4893	7.30%		
*T-Mobile PCS	2	953	125	0.0439	1900	1.0000	1.19%		
*T-Mobile AWS	4	477	125	0.0439	2100	1.0000	1.19%		
*T-Mobile LTE	1	445	125	0.0102	700	0.4667	0.47%		
*CR Police Dept	1	635	159	0.0090	635	0.4233	2.13%		
*CR Fire Dept	1	100	128	0.0022	46	0.2000	1.10%		
*CR Fire Dept	1	110	135	0.0022	154	0.2000	1.09%		
*CR Fire Alarm	1	500	127	0.0111	460	0.3067	3.63%		
*Clearwire	2	153	134	0.0061	2496	1.0000	0.61%		
*Clearwire	1	211	134	0.0042	11 GHz	1.0000	0.42%		
*Sprint CDMA/LTE	4	277	170	0.0138	1900	1.0000	1.38%		
*Sprint CDMA/LTE	1	39	170	0.0005	850	0.5667	0.09%		
*Sprint CDMA/LTE	2	139	170	0.0035	2500	1.0000	0.35%		
Verizon PCS	11	446	101	0.1729	1970	1.0000	17.29%		
Verizon Cellular	9	382	101	0.1212	869	0.5793	20.92%		
Verizon AWS	1	1918	101	0.0676	2145	1.0000	6.76%		
Verizon 700	1	690	101	0.0243	746	0.4973	4.89%	87.82%	
* Source: Siting Council									

ATTACHMENT 3

DETAILED STRUCTURAL ANALYSIS AND EVALUATION OF AN EXISTING 170' SELF SUPPORTING LATTICE TOWER AND FOUNDATION FOR PROPOSED ANTENNA ARRANGEMENT

Address: 179 Shunpike Road
Cromwell, CT

prepared for



Verizon Wireless
99 East River Drive
East Hartford, Connecticut 06108

prepared by



URS CORPORATION
500 ENTERPRISE DRIVE, SUITE 3B
ROCKY HILL, CT 06067
TEL. 860-529-8882

36928711.00000
VZ5-192

January 7, 2015

TABLE OF CONTENTS

- 1. EXECUTIVE SUMMARY**
- 2. INTRODUCTION**
- 3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS**
- 4. FINDINGS AND EVALUATION**
- 5. CONCLUSIONS AND RECOMMENDATIONS**
- 6. DRAWINGS AND DATA**
 - **TNX TOWER INPUT / OUTPUT SUMMARY**
 - **TNX TOWER FEEDLINE DISTRIBUTION**
 - **TNX TOWER FEEDLINE PLAN**
 - **TNX TOWER DETAILED OUTPUT**
 - **ANCHOR BOLT ANALYSIS**
 - **FOUNDATION ANALYSIS**

1. EXECUTIVE SUMMARY

This report summarizes the structural analysis of the existing 170' self supporting lattice tower located at 179 Shunpike Road in Cromwell, Connecticut. The analysis was conducted in accordance with the 2005 Connecticut State Building Code which requires a three second gust wind speed of 100 mph which converts to an 80 mph fastest mile per 2003 IBC (Table 1609.3.1) and the TIA/EIA-222-F standard for a wind velocity of 85 mph (fastest mile). The wind speed from the Connecticut State Building Code governs the design at 85 mph (fastest mile) and 74 mph (fastest mile) concurrent with ½ " ice. The antenna loading considered in the analysis consists of all existing and proposed antennas, transmission lines, and ancillary items as outlined in the Introduction Section of this report.

The proposed Verizon antenna modifications are listed below:

Proposed Antenna and Mount	Carrier	Antenna Center Elevation
<u>Remove:</u> (2) Swedcom SWCP2X5514 Panel Antennas (Alpha & Gamma Sectors) (1) Amphenol BXA-70063-6CF-2 Panel Antennas	Verizon (Remove)	@ 101'
<u>Install:</u> (3) Commscope LNX-4514DS-A1M_4DT_750 MHz Panel Antennas (700 MHz – LTE)	Verizon (Proposed)	@ 101'

The results of the analysis indicate that the existing tower and its foundation have the capacity to support the proposed loading conditions. **The tower and its foundation are considered structurally adequate with the wind load classification specified above and the proposed antenna loading.**

The analysis results presented herewith are based upon the completed construction of previous tower modifications proposed by URS Corporation's tower modification analysis report, project 36931260, signed and sealed on September 23, 2014. If the tower has not been modified to the specifications proposed by URS, please notify the engineer in writing immediately. No installation of new antennas or equipment shall occur until the modifications have been completed.

1. EXECUTIVE SUMMARY (continued)

This analysis is based on:


- 1) The tower structure's theoretical capacity, not including any assessment of the condition of the tower.
- 2) Tower geometry, structural member sizes, and Foundation information taken from a tower report prepared by PiROD Inc., ENG. File No. A-116398, dated November 18, 1999.
- 3) Foundation modification drawings prepared by Tectonic, dated May 5, 2004.
- 4) Structural analysis performed by URS Corp. on behalf of Verizon Wireless, project number VZ5-178 / 36917427, signed and sealed on August 12, 2014.
- 5) Structural analysis and reinforcement performed by URS Corp. on behalf of Sprint and T-Mobile, project number 36931250, signed and sealed on September 23, 2014.
- 6) Verizon proposed RFDS obtained via e-mail, Dated December 29, 2014
- 7) Proposed additional antenna and mount configuration as specified in Section 2 of this report.

This report is only valid as per the assumptions and data utilized in this report for antenna inventory, mounts and associated cables. The user of this report shall field verify the assumption of the antenna and mount configuration as well as the physical condition of the tower and connections. Notify the engineer in writing immediately if any of the information in this report is found to be other than specified.

If you should have any questions, please call.

Sincerely,

URS Corporation



Richard A. Sambor, P.E.
Senior Structural Engineer

RAS/mcd



2. INTRODUCTION

The subject tower is located at 179 Shunpike Road in Cromwell, Connecticut. The structure is a 170' self supporting lattice tower designed and manufactured by PiROD Inc.

The current inventory with proposed modification is summarized in the table below:

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) Tx Rx 101-90-08 antenna	Town (existing)	15' Mast pipe on 9 Arm Halo Mount	183'	(1) 7/8"
(1) 8 Bay Dipole (3" dia x 20')	Town (existing)	9 Arm Halo Mount	178'	(1) 7/8"
(1) 2 1/2" dia x 20' Whip	Town (existing)	9 Arm Halo Mount	178'	(1) 1 1/2"
(3) 2 1/2" dia x 15' Whip	Town (existing)	9 Arm Halo Mount	175'	(3) 7/8"
1 1/2" dia x 12' Whip	Town (existing)	9 Arm Halo Mount	174'	(1) 7/8"
(3) RFS APXV9TM14-ALU-I20 Panels (3) TD-RRH8x20-25 RRH Units (3) RFS APXVSP18-C-A20 Antennas (3) 1900 MHz RRHs (3) 800 MHz RRHs (3) 800 MHz Filters	Sprint (existing)	9 Arm Halo Mount	170'	(27) 8' Jumper Cables (3) 8' AISG Cables (4) RFS HB114-1-0804-MSF Hybrid Cables
(1) Radiowaves HPD2-4.7 w/ Radome (1) Cambium PTP49600 Antenna	CPD (existing)	9 Arm Halo Mount	168'	(1) WB3176A – Copper Clad Outdoor Cable (2) 4' long 1/2" Jumper Cables
(1) SU-RA-HP-2.4 (1' x 1' Antenna)	Town (existing)	9 Arm Halo Mount	168'	(1) 3/8"
(3) APXV18-206517S	Unknown (existing)	Leg Mount	159'-6"	(6) 1 5/8"
(1) Sinclair SC420-HF1LDF Omni	CPD (existing)	Pipe mount	158'-6"	(1) 1 5/8" Low Density Foam Cable
(2) 3" dia x 20' Whip	Town (existing)	20' Platform	144'	(2) 7/8"
(1) 2 1/2" x 20' Whip	Town (existing)	20' Platform	144'	(1) 1/2"
2" dia x 15' Whip	Town (existing)	20' Platform	141'	(1) 1/2"
(1) 1.5" dia x 10' Whip	Town (existing)	20' Platform	139'	(1) 1/2"
(1) 3.5" dia x 9' Whip	Town (existing)	20' Platform	138'-6"	---
(3) Argus LLPX310R antennas (3) Samsung Remote Radio Heads U-RAS (3) Andrew VHLP2.5 dish (2.5' dia.) (1) Andrew VHLP2 dish (2' dia.) (Gamma Sector)	Clearwire (existing)	20' Platform	134'	(6) CAT 5 cable (4) 1/2"

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(3) Commscope LNX-6515DS-VTM Panel Antennas (3) Ericsson RRUS_11 RRH Unit (6) Ericsson AIR21 B4A B2P Antennas (3) Twin PCS TMAs	T-Mobile (existing)	(3) Existing T-Frames	125'	(12) 1 5/8" (1) 1-5/8" Hybrid Cable
(6) Powerwave 7770 (12) TMA's (3) KMW AM-X-CD-16-65-00T-RET (6) RRU (1) Surge Suppressor	AT&T (existing)	(3) T-Frames	115'	(12) 1 5/8" (3) Optic Fiber & (6) DC Cables (Located within 3" dia Flex Conduit)
(3) LNX-4514DS-A1M Panel Antennas	Verizon (Proposed)	See Below Mount	101'	See Below Cables
(1) HBX-6517DS-VTM_04DT_2110 Panel Antenna (Alpha Sector) (2) HBX-6517DS-VTM_02DT_2110 Panel Antennas (Beta & Gamma Sectors) (3) AWS RRH Units (1) DB-T1-6Z-8AB-0Z Distribution Box (3) LNX-6514DS-VTM Panel Antennas (3) BXA-171063-12BF_2 antennas (6) FD9R6004/2C-3L Diplexers	Verizon (existing)	(3) T-Frames (PiROD part #800093)	101'	(1) 1 5/8" F.O Cable (12) 1 5/8"
(1) 3" x 2" x 22" Panel (1) TMA	AT&T (existing)	Pipe Mount	87'	(2) CAT 5
(1) 3' Dish (1) TMA	AT&T (existing)	3' Stand-off	83'	(2) CAT 5
(1) 3" x 2" x 22" Panel (1) TMA	AT&T (existing)	3' Stand-off	80'	(2) CAT 5
(1) Camera	Unknown (existing)	Leg Mounted	30'	(2) 1/2" (estimated from photographs)
(1) 3' Yagi	Unknown (existing)	Leg Mounted	24'	(1) 1/2"

This structural analysis of the communications tower was performed by URS Corporation (URS) for Verizon Wireless. The purpose of this analysis was to investigate the structural integrity of the previously reinforced tower with its existing and proposed antenna loads. This analysis was conducted to evaluate stress on the tower and the effect of forces to the foundation of the tower resulting from existing and proposed antenna arrangements.

The analysis results presented herewith are based upon the completed construction of previous tower modifications proposed by URS Corporation's tower modification analysis report, project 36931260, signed and sealed on September 23, 2014. If the tower has not been modified to the specifications proposed by URS, please notify the engineer in writing immediately. No installation of new antennas or equipment shall occur until the modifications have been completed.

3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS

The structural analysis was done in accordance with the Connecticut State Building Code, TIA/EIA-222-F - Structural Standard for Steel Antenna Towers and Antenna Supporting Structures, and the American Institute of Steel Construction (AISC) Manual of Steel Construction – Allowable Stress Design (ASD).

The analysis was conducted using TNX Tower 6.1.3.1. Two load conditions were evaluated as shown below which were compared to allowable stresses according to AISC and TIA/EIA.

Basic Wind Speed:

- Middlesex County; $v = 85$ mph (fastest mile) [Section 16 of TIA/EIA-222-F-1996]
- Cromwell; $v = 100$ mph (3 second gust) [Appendix K, 2005 Connecticut State Building Code Supplement]
equivalent to 80mph (fastest mile)

Loading Cases:

Load Condition 1 = 85 mph (fastest mile) Wind Load (without ice) + Tower Dead Load
Load Condition 2 = 74 mph (fastest mile) Wind Load (with ice) + Ice Load + Tower Dead Load

Please note that wind pressure is a function of velocity squared. Under Load Condition 2, a 25 percent reduction in wind pressure is allowed by code to account for the unlikelihood of the full wind pressure and ice load occurring at the same time. The same results may be achieved by utilizing a lower wind pressure without taking the 25 percent reduction, as shown above.

The TIA/EIA standard permits a one-third increase in allowable stresses for towers and monopoles less than 700 feet tall. For the purposes of this analysis, in computing the load capacity the allowable stresses of the tower members were increased by one-third.

4. FINDINGS AND EVALUATION

The combined axial and bending stresses on the tower structure were evaluated to compare with the allowable stress in accordance with AISC. The results of the analysis indicates that the calculated stresses on the structure with the proposed loading are within the allowable stresses. Additionally the anchor bolts and foundation components were found to be within allowable limits.

The table below summarizes the critical members for each tower component.

TABLE 1: Tower Component Stress vs. Capacity Summary:

Component/ (Section No.)	Existing Component Size	Controlling Component/Elevation	Percent Capacity	Pass/Fail
Tower Leg (T5)	PiROD Truss Leg	Compression 90'-100'	92.9 %	Pass
Diagonal (T7)	L3x3x3/8	Compression 60'-80'	88.6 %	Pass
Top Girt (T1)	7/8" SR	Compression 150'-170'	10.1 %	Pass
Bottom Girt (T1)	7/8" SR	Compression 150'-170'	4.5 %	Pass
Mid Girt (T4)	L3x3x3/16	Compression 100'-120'	35.1 %	Pass
Bolt Checks				
Tower Bolts	(1) 1" A325N Bolt / 140'	Member Bearing on Bolt	83.7 %	Pass
Anchor Bolts	(6) 1-1/4"	Tension	76.9 %	Pass

TABLE 2: Foundation Summary

Foundation	Component	Stress (% capacity/FOS)	Pass/Fail	Comments:
Previously Modified Drilled Concrete Caisson	Uplift	90.2 %/2.22	Pass	Min. F.O.S of 2.0 req'd per IBC 2003 Section 3108.4.2

The analysis results presented herewith are based upon the completed construction of previous tower modifications proposed by URS Corporation's tower modification analysis report, project 36931260, signed and sealed on September 23, 2014. If the tower has not been modified to the specifications proposed by URS, please notify the engineer in writing immediately. No installation of new antennas or equipment shall occur until the modifications have been completed.

5. CONCLUSIONS AND RECOMMENDATIONS

The results of the analysis indicate that the existing tower and its foundation have the capacity to support the proposed loading conditions. **The tower and its foundation are considered structurally adequate with the wind load classification and proposed antenna loading specified in the Executive Summary of this report.**

The analysis results presented herewith are based upon the completed construction of previous tower modifications proposed by URS Corporation's tower modification analysis report, project 36931260, signed and sealed on September 23, 2014. If the tower has not been modified to the specifications proposed by URS, please notify the engineer in writing immediately. No installation of new antennas or equipment shall occur until the modifications have been completed.

Limitations/Assumptions:

This report is based on the following:

1. Tower inventory as listed in this report.
2. Tower is properly installed and maintained.
3. All members are as specified in the original design documents and are in good condition.
4. All required members are in place.
5. All bolts are in place and are properly tightened.
6. Tower is in plumb condition.
7. All member protective coatings are in good condition.
8. All tower members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
9. Foundations were properly constructed to support original design loads as specified in the original design documents.
10. All coaxial cable is installed as specified in Section 6 of this report.

URS is not responsible for any changes/alterations completed prior to or hereafter in which URS is not or was not directly involved. Changes/alterations include but are not limited to:

- A. Adding antennas
- B. Removing/replacing antennas
- C. Adding coaxial cables

URS hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations, and conclusions are based upon information contained and set forth herein. If you are aware of any information which conflicts with that which is contained herein, or you are aware of any defects arising from original design, material, fabrication, or erection deficiencies, you should disregard this report and immediately contact URS. URS disclaims all liability for any representation, recommendation, or conclusion not expressly stated herein.

Ongoing and Periodic Inspection and Maintenance:


After the Contractor has successfully completed the installation and the work has been accepted, the owner will be responsible for the ongoing and periodic inspection and maintenance of the tower.

The owner shall refer to TIA/EIA-222-F for recommendations for maintenance and inspection. The frequency of the inspection and maintenance intervals is to be determined by the owner based upon actual site and environmental conditions. It is recommended that a complete and thorough inspection of the entire tower structural system be performed at least yearly and more frequently as conditions warrant. According to TIA/EIA-222-F section 14.1, Note 1: It is recommended that the structure be inspected after severe wind and/or ice storms or other extreme loading conditions.

6. DRAWINGS AND DATA

TNX TOWER INPUT/OUTPUT SUMMARY

Section	17	18	19	20	21	22	23	24	25	26	27	28	29	30
Legs	Preced 105220 w/ 1" dia bar	Preced 105219 w/ 1" dia bar	Preced 105218 w/ 1" dia bar	Preced 105217	Preced 105216	Preced 105215 w/ 1" dia bar	A	A572-50	L3x3x1/4	L3x3x1/4	L3x3x1/4	L3x3x1/4	L3x3x1/4	L3x3x1/4
Diagonals	Leading	L3 15x1 1/2x1/8	L3x3x1/4	L3x3x1/4	L3x3x1/4	L3x3x1/4	A36	L3x3x1/4	L3x3x1/4	L3x3x1/4	L3x3x1/4	L3x3x1/4	L3x3x1/4	
Top Girts														
Mid Girts														
Bottom Girts														
Face Vails (ft)	24													
# Panels @ (ft)														
Weight (K)	30.7													



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
101-80-00-01 (Municipal)	163	LNX-65150S-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5
15' Mount Pipe (Municipal)	178.75	LNX-65150S-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5
3" Dia 20' Omni (Municipal)	178	RRUS-11 (T-Mobile)	125.5
2.5" x 20" Whip (Municipal)	178	RRUS-11 (T-Mobile)	125.5
2.5" x 14' Omni (Municipal)	175	RRUS-11 (T-Mobile)	125.5
2.5" x 14' Omni (Municipal)	175	RRUS-11 (T-Mobile)	125.5
2.5" x 14' Omni (Municipal)	175	RRUS-11 (T-Mobile)	125.5
1.5" x 12' Omni (Municipal)	174	(2) TMA (shackled) (ATI)	115
APXV2P19-C-A30 (Sprink)	170	(2) TMA (shackled) (ATI)	115
APXV2P19-C-A30 (Sprink)	170	(2) TMA (shackled) (ATI)	115
APXV2P19-C-A30 (Sprink)	170	PROCO 12 Lightweight T-Frame (ATI)	115
APXV2P19-C-A30 (Sprink)	170	PROCO 12 Lightweight T-Frame (ATI)	115
Panasonic RRH 1000MHz (Sprink)	170	7770 (ATI)	115
Panasonic RRH 1000MHz (Sprink)	170	7770 (ATI)	115
Panasonic RRH 1000MHz (Sprink)	170	7770 (ATI)	115
Andrew 800MHz RRH (Sprink)	170	(2) REMOTE RADIO HEAD (RRH) (ATI)	115
Andrew 800MHz RRH (Sprink)	170	Burge Suppressor (ATI)	115
Andrew 800MHz RRH (Sprink)	170	7770 (ATI)	115
APXV2P19-C-A30 (Sprink)	170	7770 (ATI)	115
APXV2P19-C-A30 (Sprink)	170	7770 (ATI)	115
APXV2P19-C-A30 (Sprink)	170	7770 (ATI)	115
TD-RRH20-25 (Sprink)	170	(2) TMA (shackled) (ATI)	115
TD-RRH20-25 (Sprink)	170	(2) TMA (shackled) (ATI)	115
TD-RRH20-25 (Sprink)	170	(2) TMA (shackled) (ATI)	115
8 Arm Hub Mount (Municipal)	168	(2) TMA (shackled) (ATI)	115
SUHA-4P-2.4 Antenna (Municipal)	168	AXL-X-CD-16-65-001-RET (F) (ATI)	115
PTM6000 (CPO)	168	AXL-X-CD-16-65-001-RET (F) (ATI)	115
HFD0-4.7	168	(2) REMOTE RADIO HEAD (RRH) (ATI)	115
APXV18-205178-C w/ mounting hardware	168.5	(2) REMOTE RADIO HEAD (RRH) (ATI)	115
APXV18-205178-C w/ mounting hardware	168.5	BXA-171063-120F (Verizon - PCS)	101
APXV18-205178-C w/ mounting hardware	168.5	BXA-171063-120F (Verizon - PCS)	101
BC425-HF LDF (Municipal)	158.5	BXA-171063-120F (Verizon - PCS)	101
3" Dia 20' Omni (Municipal)	144	PROCO 12 Lightweight T-Frame (Verizon)	101
3" Dia 20' Omni (Municipal)	144	PROCO 12 Lightweight T-Frame (Verizon)	101
2.5" x 20" Whip (Municipal)	141	PROCO 12 Lightweight T-Frame (Verizon)	101
2" Dia 15' Omni (Municipal)	141	(2) Diplexer (Verizon - 800)	101
1.5" x 10' Omni (Municipal)	139	(2) Diplexer (Verizon - 800)	101
8" Whip (Municipal)	138.5	(2) Diplexer (Verizon - 800)	101
Alpha LLPQ10R (Cleanwire)	134	HGX-65170S-VTM (Verizon - AWS)	101
Alpha LLPQ10R (Cleanwire)	134	HGX-65170S-VTM (Verizon - AWS)	101
REMOTE RADIO HEAD (RRH) (Cleanwire)	134	HGX-65170S-VTM (Verizon - AWS)	101
REMOTE RADIO HEAD (RRH) (Cleanwire)	134	RH_2X40-AWS (Verizon - AWS)	101
PROCO 32 Universal Platform (Municipal)	134	RH_2X40-AWS (Verizon - AWS)	101
Alpha LLPQ10R (Cleanwire)	134	RH_2X40-AWS (Verizon - AWS)	101
WHLF2.5-100 (Cleanwire)	134	DS-T-42-8AM-02 (Verizon - AWS)	101
WHLF2.5-100 (Cleanwire)	134	LNX-65140S-A1M (Verizon - LTE)	101
WHLF2.5-100 (Cleanwire)	134	LNX-65140S-A1M (Verizon - LTE)	101
WHLF2.5-100 (Cleanwire)	134	LNX-65140S-A1M (Verizon - LTE)	101
REMOTE RADIO HEAD (RRH) (Cleanwire)	134	3'x2'x2" Panel	87
PROCO 12 Lightweight T-Frame (T-Mobile)	125.5	TMA	84.5
PROCO 12 Lightweight T-Frame (T-Mobile)	125.5	3' Stand-off	83.5
PROCO 12 Lightweight T-Frame (T-Mobile)	125.5	3' Stand-off	83.5
ARR 82A84P (T-Mobile)	125.5	TMA	82.5
ARR 82A84P (T-Mobile)	125.5	3'x2'x2" Panel	80
ARR 82A84P (T-Mobile)	125.5	Camera	30
ARR 82A84P (T-Mobile)	125.5	PC6013N	24
LNX-65150S-VTM w/ 6" 2" sch 40 Pipe Mount (T-Mobile)	125.5		

SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	Preced 105217 w/ 1" dia bar		

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-50	50 ksi	65 ksi	A36	36 ksi	58 ksi

TOWER DESIGN NOTES

1. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
2. Tower is also designed for a 74 mph basic wind with 0.50 in ice.
3. Deflections are based upon a 50 mph wind.
4. Weld together tower sections have flange connections.
5. Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications.
6. Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
7. Welds are fabricated with ER-70S-6 electrodes.
8. WELD RATING: 92.9%

MAX. CORNER REACTIONS AT BASE:




TNX TOWER FEEDLINE DISTRIBUTION CHART

Feed Line Distribution Chart

0' - 170'

— Round
 — Flat
 — App In Face
 — App Out Face
 — Truss Leg




URS Corporation		Job: PiROD U20'-0"x170' Lattice Tower	
500 Enterprise Drive, Suite 3B		Project: VZ5-192 / Cromwell, CT Tower	
Rocky Hill, CT 06067		Client: Verizon Wireless	Drawn by: MCD
Phone: 860-529-8882		Code: TIA/EIA-222-F	Date: 01/06/15
FAX: 860-529-3991		Path:	App'd: [Signature]
			Scale: NTS
			Dwg No. E-7

TNX TOWER FEEDLINE PLAN

Feed Line Plan

Round
Flat
App In Face
App Out Face
Truss-Leg



URS Corporation		Job: PiROD U20'-0"x170' Lattice Tower	
500 Enterprise Drive, Suite 3B		Project: VZ5-192 / Cromwell, CT Tower	
Rocky Hill, CT 06067		Client: Verizon Wireless	Drawn by: MCD
Phone: 860-529-8882		Code: TIA/EIA-222-F	Date: 01/06/15
FAX: 860-529-3991		Path:	Scale: NTS
			Dwg No. E-7

TNX TOWER DETAILED OUTPUT

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 1 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 170.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 5.00 ft at the top and 20.00 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Basic wind speed of 85 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56 pcf.

A wind speed of 74 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

Weld together tower sections have flange connections..

Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications..

Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards..

Welds are fabricated with ER-70S-6 electrodes..

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

<ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity √ Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) Add IBC .6D+W Combination 	<ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r Retension Guys To Initial Tension Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. Autocalc Torque Arm Areas √ SR Members Have Cut Ends √ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Use TIA-222-G Tension Splice Capacity Exemption 	<ul style="list-style-type: none"> √ Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces √ Ignore Redundant Members in FEA √ SR Leg Bolts Resist Compression √ All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feedline Torque Include Angle Block Shear Check Poles Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets
--	--	---

inxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 2 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD



Triangular Tower

Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	170.00-150.00			5.00	1	20.00
T2	150.00-140.00		U6.0 105244	5.00	1	10.00
T3	140.00-120.00		U8.0 105216	6.00	1	20.00
T4	120.00-100.00		U10.0 105217 L3x3/16	8.00	1	20.00
T5	100.00-90.00		U12.0 105216	10.00	1	10.00
T6	90.00-80.00		U12.0 105216	11.00	1	10.00
T7	80.00-60.00		U14.0 105218	12.00	1	20.00
T8	60.00-40.00		U16.0 105219	14.00	1	20.00
T9	40.00-20.00		U18.0 105219	16.00	1	20.00
T10	20.00-0.00		U20.0 105219 L4x1/4	18.00	1	20.00

Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	<i>ft</i>	<i>ft</i>				<i>in</i>	<i>in</i>
T1	170.00-150.00	2.49	X Brace	No	No	0.0000	1.0000
T2	150.00-140.00	10.00	X Brace	No	No	0.0000	0.0000
T3	140.00-120.00	10.00	X Brace	No	No	0.0000	0.0000
T4	120.00-100.00	10.00	X Brace	No	No	0.0000	0.0000
T5	100.00-90.00	10.00	X Brace	No	No	0.0000	0.0000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	3 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Tower Section	Tower Elevation ft	Diagonal Spacing ft	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset in	Bottom Girt Offset in
T6	90.00-80.00	10.00	X Brace	No	No	0.0000	0.0000
T7	80.00-60.00	10.00	X Brace	No	No	0.0000	0.0000
T8	60.00-40.00	10.00	X Brace	No	No	0.0000	0.0000
T9	40.00-20.00	10.00	X Brace	No	No	0.0000	0.0000
T10	20.00-0.00	10.00	X Brace	No	No	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T1 170.00-150.00	Solid Round	1 3/4	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 150.00-140.00	Truss Leg	Pirod 105244	A572-50 (50 ksi)	Single Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T3 140.00-120.00	Truss Leg	Pirod 105216	A572-50 (50 ksi)	Single Angle	L3x3x3/16	A36 (36 ksi)
T4 120.00-100.00	Truss Leg	Pirod 105217	A572-50 (50 ksi)	Single Angle	L3x3x1/4	A36 (36 ksi)
T5 100.00-90.00	Truss Leg	Pirod 105217	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T6 90.00-80.00	Truss Leg	Pirod 105217 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T7 80.00-60.00	Truss Leg	Pirod 105218 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3x3x3/8	A36 (36 ksi)
T8 60.00-40.00	Truss Leg	Pirod 105219	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x5/16	A36 (36 ksi)
T9 40.00-20.00	Truss Leg	Pirod 105219 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x3/8	A36 (36 ksi)
T10 20.00-0.00	Truss Leg	Pirod 105220 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L4x4x5/16	A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 170.00-150.00	Solid Round	7/8	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 150.00-140.00	Single Angle	L3x3x3/16	A36 (36 ksi)	Single Angle		A36 (36 ksi)

Tower Section Geometry (cont'd)

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	6 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T2	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
150.00-140.00														
T3	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
140.00-120.00														
T4	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
120.00-100.00														
T5	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
100.00-90.00														
T6	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
90.00-80.00														
T7	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
80.00-60.00														
T8	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
60.00-40.00														
T9	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
40.00-20.00														
T10	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
20.00-0.00														

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1	Flange	0.7500	0	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
170.00-150.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T2	Flange	1.0000	6	1.0000	1	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0
150.00-140.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T3	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
140.00-120.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T4	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	1.0000	1	0.6250	0	0.6250	0
120.00-100.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T5	Flange	1.0000	6	1.0000	1	0.6250	0	0.0000	0	0.6250	0	0.6250	0	0.6250	0
100.00-90.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T6	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
90.00-80.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T7	Flange	1.0000	6	1.0000	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
80.00-60.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T8	Flange	1.2500	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
60.00-40.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T9	Flange	1.2500	6	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
40.00-20.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	
T10	Flange	0.0000	0	1.2500	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
20.00-0.00		A325N		A325N		A325N		A325N		A325N		A325N		A325N	

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Shield Leg	Allow	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
CATEGORY	C	Yes	Ar (CfAe)	87.00 - 7.00	0.0000	0.48	4	2	1.0000	1.0000		0.21

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 7 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	# Per Row	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
5e (1 WIRE) CATEGORY 5e (1 WIRE)	C	Yes	Ar (CfAe)	83.00 - 7.00	0.0000	0.45	2	1	1.0000	1.0000		0.21
1/2 (Municipal)	A	No	Ar (Leg)	144.00 - 7.00	0.0000	0.125	1	1	0.5800	0.5800		0.25
7/8 (Municipal)	A	No	Ar (Leg)	144.00 - 7.00	0.0000	0.125	2	1	1.0000	1.1100		0.54
1/2 (Municipal)	A	No	Ar (Leg)	140.00 - 7.00	0.0000	0.13	2	1	0.5800	0.5800		0.25
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.14	3	1	1.0000	1.1100		0.54
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.14	1	1	1.1100	1.1100		0.54
FSJ2-50 (3/8 SUPERFLEX. FOAM)	A	No	Ar (Leg)	168.00 - 7.00	0.0000	0.12	1	1	0.4300	0.4300		0.08
FSJ2-50 (3/8 SUPERFLEX. FOAM)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.12	1	1	0.4300	0.4300		0.08
RG-11 590609 (1 1/2 FOAM)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.12	1	1	1.5000	1.5900		0.94
1 5/8 (T-Mobile)	B	No	Ar (Leg)	125.50 - 7.00	0.0000	0.1	12	3	1.5000	1.9800		1.04
1 5/8 (AT&T)	C	No	Ar (Leg)	115.00 - 7.00	0.0000	0.17	12	2	1.5000	1.9800		1.04
7/8	C	No	Ar (Leg)	170.00 - 7.00	0.0000	0.17	2	2	1.0000	1.1100		0.54
1 5/8	A	No	Ar (Leg)	160.00 - 7.00	0.0000	0.1	6	3	1.5000	1.9800		1.04
CATEGORY 5e (1 WIRE) (Clearwire)	B	Yes	Ar (CfAe)	134.00 - 7.00	-2.0000	0	6	6	1.0000	1.0000		0.21
1/2 (Clearwire)	B	Yes	Ar (CfAe)	134.00 - 7.00	-4.0000	0	4	4	0.5800	0.5800		0.25
FB-L98B-02 (10mm Fiber) (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	3.0000	0.4	3	3	0.3937	0.3937		0.03
RSS 8 - AWG 2 (0.645") (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	2.0000	0.43	6	6	0.6450	0.6450		0.30
3" Flex Conduit (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	4.0000	0.41	1	1	0.0000	3.0000		3.00
1/2	A	No	Ar (Leg)	30.00 - 7.00	0.0000	0.08	3	1	0.5800	0.5800		0.25
AVA7-50 (1-5/8 LOW DENSL FOAM) (CPD)	A	Yes	Ar (CfAe)	170.00 - 7.00	0.0000	0.38	1	1	1.5000	1.9800		0.72
1 5/8" Hybriflex (T-Mobile)	B	No	Ar (Leg)	125.00 - 7.00	0.0000	0.05	1	1	1.6250	1.6250		0.21
LDF6-50A (1-1/4 FOAM) (Sprint-FO)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.16	4	2	1.5500	1.5500		0.66
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.132	1	1	1.1100	1.1100		0.54
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.132	1	1	1.1100	1.1100		0.54
1 5/8 (VZW)	C	No	Ar (Leg)	101.00 - 7.00	0.0000	0.12	12	6	1.5000	1.9800		1.04
1 5/8" Hybriflex	C	No	Ar (Leg)	101.00 - 7.00	0.0000	0.1	1	1	1.6250	1.6250		0.21

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 8 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Description	Face or Leg	Allow or Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	# Per Row	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
(VZW)												

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
T1	170.00-150.00	A	40.136	0.000	0.000	0.000	0.22
		B	33.136	0.000	0.000	0.000	0.00
		C	3.700	0.000	0.000	0.000	0.02
T2	150.00-140.00	A	25.105	0.000	0.000	0.000	0.14
		B	21.605	0.000	0.000	0.000	0.00
		C	1.850	0.000	0.000	0.000	0.01
T3	140.00-120.00	A	54.943	0.000	0.000	0.000	0.32
		B	64.985	0.000	0.000	0.000	0.10
		C	11.035	0.000	0.000	0.000	0.02
T4	120.00-100.00	A	81.377	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	67.119	0.000	0.000	0.000	0.29
T5	100.00-90.00	A	61.700	0.000	0.000	0.000	0.16
		B	44.365	0.000	0.000	0.000	0.15
		C	56.248	0.000	0.000	0.000	0.31
T6	90.00-80.00	A	61.700	0.000	0.000	0.000	0.16
		B	44.365	0.000	0.000	0.000	0.15
		C	58.981	0.000	0.000	0.000	0.32
T7	80.00-60.00	A	123.400	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T8	60.00-40.00	A	123.400	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T9	40.00-20.00	A	124.850	0.000	0.000	0.000	0.32
		B	90.180	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T10	20.00-0.00	A	82.095	0.000	0.000	0.000	0.21
		B	59.559	0.000	0.000	0.000	0.19
		C	79.437	0.000	0.000	0.000	0.42

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _A A _A In Face ft ²	C _A A _A Out Face ft ²	Weight K
T1	170.00-150.00	A	0.500	58.953	3.517	0.000	0.000	0.60
		B		50.470	0.000	0.000	0.000	0.00
		C		3.517	3.517	0.000	0.000	0.07
T2	150.00-140.00	A	0.500	36.013	1.758	0.000	0.000	0.39
		B		31.771	0.000	0.000	0.000	0.00
		C		1.758	1.758	0.000	0.000	0.03
T3	140.00-120.00	A	0.500	82.393	3.517	0.000	0.000	0.87
		B		86.296	15.727	0.000	0.000	0.34
		C		11.727	3.517	0.000	0.000	0.07
T4	120.00-100.00	A	0.500	110.244	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 9 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AAA} In Face ft ²	C _{AAA} Out Face ft ²	Weight K
T5	100.00-90.00	C	0.500	70.420	13.548	0.000	0.000	0.75
		A		77.925	1.758	0.000	0.000	0.44
		B		55.065	11.233	0.000	0.000	0.44
T6	90.00-80.00	C	0.500	59.479	8.446	0.000	0.000	0.79
		A		77.925	1.758	0.000	0.000	0.44
		B		55.065	11.233	0.000	0.000	0.44
T7	80.00-60.00	C	0.500	61.646	10.096	0.000	0.000	0.83
		A		155.850	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88
T8	60.00-40.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		155.850	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88
T9	40.00-20.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		159.100	3.517	0.000	0.000	0.90
		B		113.380	22.467	0.000	0.000	0.88
T10	20.00-0.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		105.527	2.286	0.000	0.000	0.60
		B		75.809	14.603	0.000	0.000	0.57
		C		83.823	14.043	0.000	0.000	1.12

Feed Line Shielding

Section	Elevation ft	Face	A _R ft ²	A _R Ice ft ²	A _F ft ²	A _F Ice ft ²
T1	170.00-150.00	A	0.239	0.771	0.000	0.000
		B	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	0.000
T2	150.00-140.00	A	0.000	0.106	0.184	0.277
		B	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	0.000
T3	140.00-120.00	A	0.000	0.145	0.289	0.435
		B	0.000	0.580	0.849	1.741
		C	0.000	0.000	0.000	0.000
T4	120.00-100.00	A	0.000	0.145	0.288	0.434
		B	0.000	0.828	1.212	2.484
		C	0.000	0.548	0.879	1.645
T5	100.00-90.00	A	0.000	0.057	0.114	0.171
		B	0.000	0.327	0.479	0.981
		C	0.000	0.289	0.463	0.867
T6	90.00-80.00	A	0.000	0.055	0.109	0.165
		B	0.000	0.314	0.459	0.942
		C	0.000	0.340	0.538	1.019
T7	80.00-60.00	A	0.000	0.105	0.208	0.314
		B	0.000	0.598	0.875	1.795
		C	0.000	0.739	1.163	2.216
T8	60.00-40.00	A	0.000	0.100	0.231	0.348
		B	0.000	0.570	0.973	1.994
		C	0.000	0.703	1.292	2.462
T9	40.00-20.00	A	0.000	0.096	0.223	0.336
		B	0.000	0.550	0.939	1.925
		C	0.000	0.679	1.247	2.377
T10	20.00-0.00	A	0.000	0.061	0.162	0.243
		B	0.000	0.348	0.679	1.393
		C	0.000	0.430	0.902	1.719

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	10 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Feed Line Center of Pressure

Section	Elevation	CP _X		CP _Z	
		in	in	Ice	Ice
	ft				
T1	170.00-150.00	-0.7973	-8.0376	-0.4853	-7.4212
T2	150.00-140.00	-0.4988	-6.6293	-0.3283	-6.3594
T3	140.00-120.00	1.4194	-7.8403	1.2494	-8.0075
T4	120.00-100.00	-0.3302	-2.7146	-0.0626	-4.2227
T5	100.00-90.00	-5.2784	0.3685	-4.0917	-1.7690
T6	90.00-80.00	-6.3856	0.8722	-4.8612	-1.5653
T7	80.00-60.00	-7.6460	1.3464	-5.9655	-1.3222
T8	60.00-40.00	-8.5419	1.4777	-6.6864	-1.5207
T9	40.00-20.00	-9.4077	1.2998	-7.3405	-2.1935
T10	20.00-0.00	-8.2989	0.8730	-6.4327	-2.3698

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
101-90-08-0-01 (Municipal)	A	From Leg	9.00	0.0000	183.00	No Ice	3.33	3.33	0.04
			2.00			1/2" Ice	4.31	4.31	0.06
			0.00						
15' Mount Pipe (Municipal)	A	From Leg	9.00	0.0000	179.75	No Ice	4.50	4.50	0.09
			2.00			1/2" Ice	6.03	6.03	0.12
			0.00						
3" Dia 20' Omni (Municipal)	B	From Face	9.00	0.0000	178.00	No Ice	6.00	6.00	0.06
			0.00			1/2" Ice	8.03	8.03	0.10
			0.00						
2.5" x 20'6" Whip (Municipal)	C	From Face	9.00	0.0000	178.00	No Ice	5.14	5.14	0.15
			0.00			1/2" Ice	7.24	7.24	0.19
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00			1/2" Ice	4.93	4.93	0.06
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00			1/2" Ice	4.93	4.93	0.06
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00			1/2" Ice	4.93	4.93	0.06
			0.00						
1.5" x 12' Omni (Municipal)	A	From Face	9.00	0.0000	174.00	No Ice	1.50	1.50	0.06
			4.00			1/2" Ice	2.52	2.52	0.07
			0.00						
9 Arm Halo Mount (Municipal)	C	None		0.0000	168.00	No Ice	62.60	62.60	3.60
						1/2" Ice	80.40	80.40	4.80
SU-RA-HP-2.4 Antenna (Municipal)	B	From Face	9.00	0.0000	168.00	No Ice	0.80	0.37	0.00
			2.50			1/2" Ice	0.93	0.47	0.01
			0.00						
PTP49600 (CPD)	C	From Leg	9.00	0.0000	168.00	No Ice	2.04	0.53	0.01
			0.00			1/2" Ice	2.24	0.65	0.02

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job		PiROD U20'-0"x170' Lattice Tower					Page		11 of 43
	Project		VZ5-192 / Cromwell, CT Tower					Date		13:01:58 01/06/15
	Client		Verizon Wireless					Designed by		MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
APXV18-206517S-C w/ mounting hardware	A	From Leg	0.00	1.00	0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00	0.00			1/2" Ice	5.53	5.39	0.09
			0.00							
APXV18-206517S-C w/ mounting hardware	B	From Leg	1.00	1.00	0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00	0.00			1/2" Ice	5.53	5.39	0.09
			0.00							
APXV18-206517S-C w/ mounting hardware	C	From Leg	1.00	1.00	0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00	0.00			1/2" Ice	5.53	5.39	0.09
			0.00							
SC420-HF1LDF (Municipal)	A	From Face	6.00	6.00	0.0000	158.50	No Ice	2.14	2.14	0.02
			0.00	0.00			1/2" Ice	3.02	3.02	0.03
			0.00							
3" Dia 20' Omni (Municipal)	C	From Face	6.00	6.00	0.0000	144.00	No Ice	6.00	6.00	0.06
			9.00	9.00			1/2" Ice	8.03	8.03	0.10
			0.00							
3" Dia 20' Omni (Municipal)	A	From Face	6.00	6.00	0.0000	144.00	No Ice	6.00	6.00	0.06
			-9.00	-9.00			1/2" Ice	8.03	8.03	0.10
			0.00							
2.5" x 20'6" Whip (Municipal)	A	From Face	6.00	6.00	0.0000	144.00	No Ice	5.14	5.14	0.15
			9.00	9.00			1/2" Ice	7.24	7.24	0.19
			0.00							
2" Dia 15' Omni (Municipal)	B	From Face	6.00	6.00	0.0000	141.00	No Ice	3.20	3.20	0.04
			-5.00	-5.00			1/2" Ice	4.83	4.83	0.06
			0.00							
1.5" x 10' Omni (Municipal)	B	From Face	6.00	6.00	0.0000	139.00	No Ice	1.50	1.50	0.06
			5.00	5.00			1/2" Ice	2.52	2.52	0.07
			0.00							
9' Whip (Municipal)	A	From Face	6.00	6.00	0.0000	138.50	No Ice	5.85	5.85	0.12
			0.00	0.00			1/2" Ice	7.66	7.66	0.17
			0.00							
PiROD 20' Universal Platform (Municipal)	C	None			0.0000	134.00	No Ice	33.10	33.10	2.27
							1/2" Ice	47.10	47.10	2.70
Argus LLPX310R (Clearwire)	A	From Face	6.00	6.00	0.0000	134.00	No Ice	4.86	3.46	0.03
			7.00	7.00			1/2" Ice	5.22	3.80	0.06
			0.00							
Argus LLPX310R (Clearwire)	B	From Face	6.00	6.00	0.0000	134.00	No Ice	4.86	3.46	0.03
			0.00	0.00			1/2" Ice	5.22	3.80	0.06
			0.00							
Argus LLPX310R (Clearwire)	C	From Face	6.00	6.00	0.0000	134.00	No Ice	4.86	3.46	0.03
			7.00	7.00			1/2" Ice	5.22	3.80	0.06
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	A	From Face	6.00	6.00	0.0000	134.00	No Ice	1.82	0.83	0.03
			7.00	7.00			1/2" Ice	2.00	0.97	0.04
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	B	From Face	6.00	6.00	0.0000	134.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	C	From Face	6.00	6.00	0.0000	134.00	No Ice	1.82	0.83	0.03
			7.00	7.00			1/2" Ice	2.00	0.97	0.04
			0.00							
(2) TMA (shielded) (AT&T)	A	From Leg	4.00	4.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			6.00	6.00			1/2" Ice	0.00	0.00	0.01
			0.00							
(2) TMA (shielded) (AT&T)	A	From Leg	4.00	4.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			0.00	0.00			1/2" Ice	0.00	0.00	0.01
			-6.00	-6.00						

inxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job		PiROD U20'-0"x170' Lattice Tower					Page		12 of 43
	Project		VZ5-192 / Cromwell, CT Tower					Date		13:01:58 01/06/15
	Client		Verizon Wireless					Designed by		MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} _{Front}	C _{AA} _{Side}	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
(2) TMA (shielded) (AT&T)	B	From Leg	0.00	4.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			6.00	6.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
(2) TMA (shielded) (AT&T)	B	From Leg	4.00	4.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			-6.00	-6.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
(2) TMA (shielded) (AT&T)	C	From Leg	4.00	4.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			6.00	6.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
(2) TMA (shielded) (AT&T)	C	From Leg	4.00	4.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			-6.00	-6.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
PiROD 12' Lightweight T-Frame (AT&T)	A	From Leg	2.00	0.00	0.0000	115.00	No Ice	10.20	10.20	0.25
			0.00	0.00			1/2" Ice	16.20	16.20	0.35
			0.00	0.00						
PiROD 12' Lightweight T-Frame (AT&T)	B	From Leg	2.00	0.00	0.0000	115.00	No Ice	10.20	10.20	0.25
			0.00	0.00			1/2" Ice	16.20	16.20	0.35
			0.00	0.00						
PiROD 12' Lightweight T-Frame (AT&T)	C	From Leg	2.00	0.00	0.0000	115.00	No Ice	10.20	10.20	0.25
			0.00	0.00			1/2" Ice	16.20	16.20	0.35
			0.00	0.00						
7770 (AT&T)	A	From Leg	4.00	4.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			6.00	6.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	A	From Leg	4.00	4.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			-6.00	-6.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	B	From Leg	4.00	4.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			6.00	6.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	B	From Leg	4.00	4.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			-6.00	-6.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	C	From Leg	4.00	4.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			6.00	6.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	C	From Leg	4.00	4.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			-6.00	-6.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
AM-X-CD-16-65-00T-RET (6') (AT&T)	A	From Leg	4.00	4.00	0.0000	115.00	No Ice	8.26	4.64	0.05
			0.00	0.00			1/2" Ice	8.81	5.09	0.10
			0.00	0.00						
AM-X-CD-16-65-00T-RET (6') (AT&T)	B	From Leg	4.00	4.00	0.0000	115.00	No Ice	8.26	4.64	0.05
			0.00	0.00			1/2" Ice	8.81	5.09	0.10
			0.00	0.00						
AM-X-CD-16-65-00T-RET (6') (AT&T)	C	From Leg	4.00	4.00	0.0000	115.00	No Ice	8.26	4.64	0.05
			0.00	0.00			1/2" Ice	8.81	5.09	0.10
			0.00	0.00						
(2) REMOTE RADIO HEAD (RRH) (AT&T)	A	From Leg	0.00	0.00	0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00	0.00						
(2) REMOTE RADIO HEAD (RRH) (AT&T)	B	From Leg	0.00	0.00	0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00	0.00						
(2) REMOTE RADIO HEAD (RRH) (AT&T)	C	From Leg	0.00	0.00	0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00	0.00						

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	13 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A		Weight	
			Horz Lateral	Vert			Front	Side		
			ft	ft	°	ft	ft ²	ft ²	K	
(AT&T)			0.00							
Surge Suppressor	C	From Leg	0.00		0.0000	115.00	No Ice 1/2" Ice	0.80 0.94	0.80 0.94	0.03 0.04
(AT&T)			0.00							
3"x2"x22" Panel	B	From Leg	2.00		0.0000	87.00	No Ice 1/2" Ice	0.65 0.81	0.47 0.61	0.05 0.05
			0.00							
TMA	B	From Leg	2.00		0.0000	84.50	No Ice 1/2" Ice	1.06 1.21	0.45 0.57	0.02 0.03
			0.00							
3' Stand-off	B	From Leg	1.50		0.0000	83.50	No Ice 1/2" Ice	1.00 1.20	2.00 2.70	0.05 0.07
			0.00							
3' Stand-off	A	From Leg	1.50		0.0000	83.50	No Ice 1/2" Ice	1.00 1.20	2.00 2.70	0.05 0.07
			0.00							
TMA	A	From Leg	2.00		0.0000	83.00	No Ice 1/2" Ice	1.06 1.21	0.45 0.57	0.02 0.03
			0.00							
TMA	B	From Leg	2.00		0.0000	82.50	No Ice 1/2" Ice	1.06 1.21	0.45 0.57	0.02 0.03
			0.00							
3"x2"x22" Panel	B	From Leg	2.00		0.0000	80.00	No Ice 1/2" Ice	0.65 0.81	0.47 0.61	0.05 0.05
			0.00							
Camera	A	From Leg	0.00		0.0000	30.00	No Ice 1/2" Ice	0.50 0.60	0.50 0.60	0.01 0.02
			0.00							
PC9013N	A	From Leg	1.00		0.0000	24.00	No Ice 1/2" Ice	0.46 0.52	0.46 0.52	0.00 0.00
			0.00							
APXVSPP18-C-A20	A	From Face	9.00		0.0000	170.00	No Ice 1/2" Ice	8.40 8.95	5.28 5.74	0.06 0.11
(Sprint)			-1.00							
			0.00							
APXVSPP18-C-A20	B	From Face	9.00		0.0000	170.00	No Ice 1/2" Ice	8.40 8.95	5.28 5.74	0.06 0.11
(Sprint)			-1.00							
			0.00							
APXVSPP18-C-A20	C	From Face	9.00		0.0000	170.00	No Ice 1/2" Ice	8.40 8.95	5.28 5.74	0.06 0.11
(Sprint)			-1.00							
			0.00							
Panasonic RRH 1900MHZ	A	From Face	8.00		0.0000	170.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30	0.09 0.12
(Sprint)			0.00							
			0.00							
Panasonic RRH 1900MHZ	B	From Face	8.00		0.0000	170.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30	0.09 0.12
(Sprint)			0.00							
			0.00							
Panasonic RRH 1900MHZ	C	From Face	8.00		0.0000	170.00	No Ice 1/2" Ice	2.49 2.71	3.06 3.30	0.09 0.12
(Sprint)			0.00							
			0.00							
Andrew 800MHz RRH	A	From Face	8.00		0.0000	170.00	No Ice 1/2" Ice	2.36 2.57	1.97 2.17	0.06 0.08
(Sprint)			0.00							
			0.00							
Andrew 800MHz RRH	B	From Face	8.00		0.0000	170.00	No Ice 1/2" Ice	2.36 2.57	1.97 2.17	0.06 0.08
(Sprint)			0.00							
			0.00							
Andrew 800MHz RRH	C	From Face	8.00		0.0000	170.00	No Ice 1/2" Ice	2.36 2.57	1.97 2.17	0.06 0.08
(Sprint)			0.00							

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job		PiROD U20'-0"x170' Lattice Tower		Page		14 of 43	
	Project		VZ5-192 / Cromwell, CT Tower		Date		13:01:58 01/06/15	
	Client		Verizon Wireless		Designed by		MCD	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A Front	C _A A _A Side	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft ²	ft ²	K	
APXV9TM14-120 (Sprint)	A	From Face	0.00		0.0000	170.00	No Ice	7.27	5.33	0.10
			9.00				1/2" Ice	7.80	6.05	0.16
			-4.00							
APXV9TM14-120 (Sprint)	B	From Face	0.00		0.0000	170.00	No Ice	7.27	5.33	0.10
			9.00				1/2" Ice	7.80	6.05	0.16
			-4.00							
APXV9TM14-120 (Sprint)	C	From Face	0.00		0.0000	170.00	No Ice	7.27	5.33	0.10
			9.00				1/2" Ice	7.80	6.05	0.16
			-4.00							
TD-RRH8x20-25 (Sprint)	A	From Face	0.00		0.0000	170.00	No Ice	4.32	1.41	0.07
			9.00				1/2" Ice	4.60	1.61	0.09
			-4.00							
TD-RRH8x20-25 (Sprint)	B	From Face	0.00		0.0000	170.00	No Ice	4.32	1.41	0.07
			9.00				1/2" Ice	4.60	1.61	0.09
			-4.00							
TD-RRH8x20-25 (Sprint)	C	From Face	0.00		0.0000	170.00	No Ice	4.32	1.41	0.07
			9.00				1/2" Ice	4.60	1.61	0.09
			-4.00							
PiROD 10' Lightweight T-Frame (T-Mobile)	A	From Leg	0.00		0.0000	125.50	No Ice	9.30	9.30	0.25
			2.00				1/2" Ice	14.50	14.50	0.34
			0.00							
PiROD 10' Lightweight T-Frame (T-Mobile)	B	From Leg	0.00		0.0000	125.50	No Ice	9.30	9.30	0.25
			2.00				1/2" Ice	14.50	14.50	0.34
			0.00							
PiROD 10' Lightweight T-Frame (T-Mobile)	C	From Leg	0.00		0.0000	125.50	No Ice	9.30	9.30	0.25
			2.00				1/2" Ice	14.50	14.50	0.34
			0.00							
AIR B2A/B4P (T-Mobile)	A	From Leg	0.00		0.0000	125.50	No Ice	6.42	4.22	0.08
			4.00				1/2" Ice	6.86	4.64	0.12
			3.00							
AIR B2A/B4P (T-Mobile)	B	From Leg	0.00		0.0000	125.50	No Ice	6.42	4.22	0.08
			4.00				1/2" Ice	6.86	4.64	0.12
			3.00							
AIR B2A/B4P (T-Mobile)	C	From Leg	0.00		0.0000	125.50	No Ice	6.42	4.22	0.08
			4.00				1/2" Ice	6.86	4.64	0.12
			3.00							
AIR B2A/B4P (T-Mobile)	A	From Leg	0.00		0.0000	125.50	No Ice	6.42	4.22	0.08
			4.00				1/2" Ice	6.86	4.64	0.12
			-3.00							
AIR B2A/B4P (T-Mobile)	B	From Leg	0.00		0.0000	125.50	No Ice	6.42	4.22	0.08
			4.00				1/2" Ice	6.86	4.64	0.12
			-3.00							
AIR B2A/B4P (T-Mobile)	C	From Leg	0.00		0.0000	125.50	No Ice	6.42	4.22	0.08
			4.00				1/2" Ice	6.86	4.64	0.12
			-3.00							
Twin PCS TMA (T-Mobile)	A	From Leg	0.00		0.0000	125.50	No Ice	0.77	0.36	0.01
			4.00				1/2" Ice	0.96	0.52	0.02
			3.00							
Twin PCS TMA (T-Mobile)	B	From Leg	0.00		0.0000	125.50	No Ice	0.77	0.36	0.01
			4.00				1/2" Ice	0.96	0.52	0.02
			3.00							
Twin PCS TMA (T-Mobile)	C	From Leg	0.00		0.0000	125.50	No Ice	0.77	0.36	0.01
			4.00				1/2" Ice	0.96	0.52	0.02
			3.00							
LNX-6515DS-VTM w/ 6' 2" sch 40 Pipe Mount	A	From Leg	0.00		0.0000	125.50	No Ice	11.45	9.12	0.07
			4.00				1/2" Ice	12.06	10.21	0.15

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job		PiROD U20'-0"x170' Lattice Tower					Page		
	Project		VZ5-192 / Cromwell, CT Tower					Date		
	Client		Verizon Wireless					Designed by		
									15 of 43	
									13:01:58 01/06/15	
									MCD	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A Front	C _A A _A Side	Weight
			Horz	Lateral					
			ft	ft					
(T-Mobile)			0.00						
LNX-6515DS-VTM w/ 6' 2" sch 40 Pipe Mount	B	From Leg	4.00	0.0000	125.50	No Ice	11.45	9.12	0.07
(T-Mobile)			0.00			1/2" Ice	12.06	10.21	0.15
LNX-6515DS-VTM w/ 6' 2" sch 40 Pipe Mount	C	From Leg	4.00	0.0000	125.50	No Ice	11.45	9.12	0.07
(T-Mobile)			0.00			1/2" Ice	12.06	10.21	0.15
RRUS-11 (T-Mobile)	A	From Leg	4.00	0.0000	125.50	No Ice	3.26	1.38	0.05
(T-Mobile)			0.00			1/2" Ice	3.50	1.56	0.07
RRUS-11 (T-Mobile)	B	From Leg	4.00	0.0000	125.50	No Ice	3.26	1.38	0.05
(T-Mobile)			0.00			1/2" Ice	3.50	1.56	0.07
RRUS-11 (T-Mobile)	C	From Leg	4.00	0.0000	125.50	No Ice	3.26	1.38	0.05
(T-Mobile)			0.00			1/2" Ice	3.50	1.56	0.07
BXA-171063-12BF (Verizon - PCS)	A	From Leg	4.00	0.0000	101.00	No Ice	4.73	3.57	0.02
(Verizon - PCS)			0.00			1/2" Ice	5.18	4.01	0.04
BXA-171063-12BF (Verizon - PCS)	B	From Leg	4.00	0.0000	101.00	No Ice	4.73	3.57	0.02
(Verizon - PCS)			0.00			1/2" Ice	5.18	4.01	0.04
BXA-171063-12BF (Verizon - PCS)	C	From Leg	4.00	0.0000	101.00	No Ice	4.73	3.57	0.02
(Verizon - PCS)			0.00			1/2" Ice	5.18	4.01	0.04
PiROD 12' Lightweight T-Frame (Verizon)	A	From Leg	0.00	0.0000	101.00	No Ice	10.20	10.20	0.25
(Verizon)			0.00			1/2" Ice	16.20	16.20	0.35
PiROD 12' Lightweight T-Frame (Verizon)	B	From Leg	0.00	0.0000	101.00	No Ice	10.20	10.20	0.25
(Verizon)			0.00			1/2" Ice	16.20	16.20	0.35
PiROD 12' Lightweight T-Frame (Verizon)	C	From Leg	0.00	0.0000	101.00	No Ice	10.20	10.20	0.25
(Verizon)			0.00			1/2" Ice	16.20	16.20	0.35
(2) Diplexer (Verizon - 850)	A	From Leg	4.00	0.0000	101.00	No Ice	0.23	0.17	0.01
(Verizon - 850)			6.00			1/2" Ice	0.30	0.24	0.01
(2) Diplexer (Verizon - 850)	B	From Leg	4.00	0.0000	101.00	No Ice	0.23	0.17	0.01
(Verizon - 850)			6.00			1/2" Ice	0.30	0.24	0.01
(2) Diplexer (Verizon - 850)	C	From Leg	4.00	0.0000	101.00	No Ice	0.23	0.17	0.01
(Verizon - 850)			6.00			1/2" Ice	0.30	0.24	0.01
HBX-6517DS-VTM (Verizon - AWS)	A	From Leg	4.00	0.0000	101.00	No Ice	5.24	3.24	0.01
(Verizon - AWS)			6.00			1/2" Ice	5.71	3.69	0.04
HBX-6517DS-VTM (Verizon - AWS)	B	From Leg	4.00	0.0000	101.00	No Ice	5.24	3.24	0.01
(Verizon - AWS)			6.00			1/2" Ice	5.71	3.69	0.04
HBX-6517DS-VTM (Verizon - AWS)	C	From Leg	4.00	0.0000	101.00	No Ice	5.24	3.24	0.01
(Verizon - AWS)			6.00			1/2" Ice	5.71	3.69	0.04
RH_2X40-AWS (Verizon - AWS)	A	From Leg	4.00	0.0000	101.00	No Ice	2.52	1.59	0.04
(Verizon - AWS)			6.00			1/2" Ice	2.75	1.80	0.06
RH_2X40-AWS (Verizon - AWS)	B	From Leg	4.00	0.0000	101.00	No Ice	2.52	1.59	0.04
(Verizon - AWS)			6.00			1/2" Ice	2.75	1.80	0.06

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	16 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz Lateral	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
RH_2X40-AWS (Verizon - AWS)	C	From Leg	0.00	0.00	0.0000	101.00	No Ice	2.52	1.59	0.04
			4.00	4.00			1/2" Ice	2.75	1.80	0.06
			6.00	0.00						
DB-T1-6Z-8AB-0Z (Verizon - AWS)	C	None			0.0000	101.00	No Ice	5.35	2.40	0.04
							1/2" Ice	5.75	2.72	0.07
LNX-6514DS-T4M (Verizon - 850)	A	From Leg	4.00	0.00	0.0000	101.00	No Ice	8.38	5.41	0.04
			-6.00	0.00			1/2" Ice	8.93	5.86	0.09
			0.00							
LNX-6514DS-T4M (Verizon - 850)	B	From Leg	4.00	0.00	0.0000	101.00	No Ice	8.38	5.41	0.04
			-6.00	0.00			1/2" Ice	8.93	5.86	0.09
			0.00							
LNX-6514DS-T4M (Verizon - 850)	C	From Leg	4.00	0.00	0.0000	101.00	No Ice	8.38	5.41	0.04
			-6.00	0.00			1/2" Ice	8.93	5.86	0.09
			0.00							
LNX-4514DS-A1M (Verizon - LTE)	A	From Leg	4.00	0.00	0.0000	101.00	No Ice	8.93	5.27	0.06
			-4.00	0.00			1/2" Ice	9.42	5.96	0.12
			0.00							
LNX-4514DS-A1M (Verizon - LTE)	B	From Leg	4.00	0.00	0.0000	101.00	No Ice	8.93	5.27	0.06
			-4.00	0.00			1/2" Ice	9.42	5.96	0.12
			0.00							
LNX-4514DS-A1M (Verizon - LTE)	C	From Leg	4.00	0.00	0.0000	101.00	No Ice	8.93	5.27	0.06
			-4.00	0.00			1/2" Ice	9.42	5.96	0.12
			0.00							

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz Lateral	Vert							
			ft	ft	°	°	ft	ft	ft ²	K		
3' Dish	A	Paraboloid w/o Radome	From Leg	2.00	0.00	0.0000		83.00	3.00	No Ice	7.07	0.23
				0.00	0.00					1/2" Ice	7.47	0.27
				0.00								
VHLP2.5-180 (Clearwire)	A	Paraboloid w/o Radome	From Face	6.00	0.00	0.0000		134.00	2.50	No Ice	4.90	0.07
				0.00	0.00					1/2" Ice	5.24	0.10
				0.00								
VHLP2.5-180 (Clearwire)	A	Paraboloid w/o Radome	From Face	6.00	0.00	0.0000		134.00	2.50	No Ice	4.90	0.07
				-7.00	0.00					1/2" Ice	5.24	0.10
				0.00								
VHLP2.5-180 (Clearwire)	B	Paraboloid w/o Radome	From Face	6.00	0.00	0.0000		134.00	2.50	No Ice	4.90	0.07
				-7.00	0.00					1/2" Ice	5.24	0.10
				0.00								
VHLP2-180 (Clearwire)	C	Paraboloid w/o Radome	From Face	6.00	0.00	0.0000		134.00	2.00	No Ice	3.14	0.03
				0.00	0.00					1/2" Ice	3.41	0.04
				0.00								
HPD2-4.7	C	Paraboloid w/Radome	From Face	9.00	0.00	0.0000		168.00	2.00	No Ice	3.14	0.03
				0.00	0.00					1/2" Ice	3.41	0.04
				0.00								

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 17 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Truss-Leg Properties

Section Designation	Area <i>in</i> ²	Area Ice <i>in</i> ²	Self Weight <i>K</i>	Ice Weight <i>K</i>	Equiv. Diameter <i>in</i>	Equiv. Diameter Ice <i>in</i>	Leg Area <i>in</i> ²
Pirod 105244	1026.8606	1727.9786	0.56	0.21	7.1310	11.9999	3.6816
Pirod 105216	1998.0891	3357.4497	0.51	0.43	6.9378	11.6578	3.6816
Pirod 105217	2130.7479	3520.4599	0.62	0.44	7.3984	12.2238	5.3014
Pirod 105217	2130.7479	3520.4599	0.62	0.44	7.3984	12.2238	5.3014
Pirod 105217 reinf w/ 1" dia bar	2291.5652	3727.7657	0.79	0.46	7.9568	12.9436	7.6570
Pirod 105218 reinf w/ 1" dia bar	2425.8928	3907.6826	0.95	0.48	8.4232	13.5683	9.9280
Pirod 105219	2441.8688	3942.2854	0.94	0.49	8.4787	13.6885	9.4248
Pirod 105219 reinf w /1" dia bar	2571.0468	4121.6676	1.11	0.50	8.9272	14.3113	11.7803
Pirod 105220 reinf w/ 1" dia bar	2697.7688	4300.8949	1.29	0.51	9.3673	14.9337	14.2843

Tower Pressures - No Ice

$G_H = 1.125$

Section Elevation <i>ft</i>	<i>z</i> <i>ft</i>	K_z	q_z <i>psf</i>	A_G <i>ft</i> ²	<i>F a c e</i>	A_F <i>ft</i> ²	A_R <i>ft</i> ²	A_{leg} <i>ft</i> ²	Leg %	$C_A A_A$ In Face <i>ft</i> ²	$C_A A_A$ Out Face <i>ft</i> ²
T1 170.00-150.00	160.00	1.57	29	102.917	A	0.000	52.765	5.833	11.06	0.000	0.000
					B	0.000	46.004		12.68	0.000	0.000
					C	0.000	16.568		35.21	0.000	0.000
T2 150.00-140.00	145.00	1.526	28	66.055	A	5.292	37.009	11.905	28.14	0.000	0.000
					B	5.476	33.509		30.54	0.000	0.000
					C	5.476	13.755		61.91	0.000	0.000
T3 140.00-120.00	130.00	1.48	27	162.111	A	10.178	78.107	23.165	26.24	0.000	0.000
					B	9.618	88.149		23.69	0.000	0.000
					C	10.467	34.200		51.86	0.000	0.000
T4 120.00-100.00	110.00	1.411	26	202.528	A	13.676	106.080	24.703	20.63	0.000	0.000
					B	12.753	113.432		19.58	0.000	0.000
					C	13.085	91.822		23.55	0.000	0.000
T5 100.00-90.00	95.00	1.353	25	116.264	A	6.447	74.051	12.351	15.34	0.000	0.000
					B	6.082	56.716		19.67	0.000	0.000
					C	6.098	68.599		16.54	0.000	0.000
T6 90.00-80.00	85.00	1.31	24	126.517	A	6.849	74.983	13.283	16.23	0.000	0.000
					B	6.499	57.648		20.71	0.000	0.000
					C	6.420	72.265		16.88	0.000	0.000
T7 80.00-60.00	70.00	1.24	23	283.450	A	14.936	151.524	28.124	16.90	0.000	0.000
					B	14.269	116.854		21.45	0.000	0.000
					C	13.982	150.334		17.12	0.000	0.000
T8 60.00-40.00	50.00	1.126	21	323.362	A	19.403	151.709	28.309	16.54	0.000	0.000
					B	18.662	117.039		20.86	0.000	0.000
					C	18.343	150.519		16.76	0.000	0.000
T9 40.00-20.00	30.00	1	18	363.756	A	21.437	154.657	29.807	16.93	0.000	0.000
					B	20.722	119.987		21.18	0.000	0.000
					C	20.414	152.017		17.29	0.000	0.000
T10 20.00-0.00	10.00	1	18	404.134	A	26.964	113.371	31.276	22.29	0.000	0.000

inxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 18 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
					B	26.446	90.836		26.67	0.000	0.000
					C	26.223	110.713		22.84	0.000	0.000

Tower Pressure - With Ice

$G_H = 1.125$

Section Elevation	z	K _Z	q _z	t _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	in	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T1 170.00-150.00	160.00	1.57	22	0.5000	104.583	A	3.517	82.422	9.167	10.67	0.000	0.000
						B	0.000	74.710		12.27	0.000	0.000
						C	3.517	27.757		29.31	0.000	0.000
T2 150.00-140.00	145.00	1.526	21	0.5000	66.890	A	6.957	58.049	20.033	30.82	0.000	0.000
						B	5.476	53.914		33.73	0.000	0.000
						C	7.234	23.901		64.34	0.000	0.000
T3 140.00-120.00	130.00	1.48	21	0.5000	163.780	A	13.549	124.661	38.924	28.16	0.000	0.000
						B	24.452	128.129		25.51	0.000	0.000
						C	13.984	54.140		57.14	0.000	0.000
T4 120.00-100.00	110.00	1.411	20	0.5000	204.197	A	17.047	155.568	40.814	23.64	0.000	0.000
						B	33.947	154.770		21.63	0.000	0.000
						C	25.867	115.341		28.90	0.000	0.000
T5 100.00-90.00	95.00	1.353	19	0.5000	117.098	A	8.148	100.462	20.407	18.79	0.000	0.000
						B	16.813	77.332		21.68	0.000	0.000
						C	14.140	81.784		21.27	0.000	0.000
T6 90.00-80.00	85.00	1.31	18	0.5000	127.351	A	8.553	101.798	21.609	19.58	0.000	0.000
						B	17.250	78.679		22.53	0.000	0.000
						C	16.035	85.234		21.34	0.000	0.000
T7 80.00-60.00	70.00	1.24	17	0.5000	285.119	A	18.347	206.096	45.303	20.18	0.000	0.000
						B	35.816	159.883		23.15	0.000	0.000
						C	34.534	178.571		21.26	0.000	0.000
T8 60.00-40.00	50.00	1.126	16	0.5000	325.031	A	22.803	207.064	45.704	19.88	0.000	0.000
						B	40.107	160.874		22.74	0.000	0.000
						C	38.778	179.569		20.93	0.000	0.000
T9 40.00-20.00	30.00	1	14	0.5000	365.425	A	24.841	212.976	47.784	20.09	0.000	0.000
						B	42.203	166.803		22.86	0.000	0.000
						C	40.890	182.252		21.41	0.000	0.000
T10 20.00-0.00	10.00	1	14	0.5000	405.803	A	29.168	162.109	49.862	26.07	0.000	0.000
						B	40.336	132.104		28.92	0.000	0.000
						C	39.449	140.036		27.78	0.000	0.000

Tower Pressure - Service

$G_H = 1.125$

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T1 170.00-150.00	160.00	1.57	10	102.917	A	0.000	52.765	5.833	11.06	0.000	0.000
					B	0.000	46.004		12.68	0.000	0.000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	19 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section Elevation	z	Kz	qz	AG	F a c e	AF	AR	Aleg	Leg %	CAAA In Face ft²	CAAA Out Face ft²
ft	ft		psf	ft²	e	ft²	ft²	ft²			
T2 150.00-140.00	145.00	1.526	10	66.055	C	0.000	16.568		35.21	0.000	0.000
					A	5.292	37.009	11.905	28.14	0.000	0.000
					B	5.476	33.509		30.54	0.000	0.000
					C	5.476	13.755		61.91	0.000	0.000
T3 140.00-120.00	130.00	1.48	9	162.111	A	10.178	78.107	23.165	26.24	0.000	0.000
					B	9.618	88.149		23.69	0.000	0.000
					C	10.467	34.200		51.86	0.000	0.000
T4 120.00-100.00	110.00	1.411	9	202.528	A	13.676	106.080	24.703	20.63	0.000	0.000
					B	12.753	113.432		19.58	0.000	0.000
					C	13.085	91.822		23.55	0.000	0.000
T5 100.00-90.00	95.00	1.353	9	116.264	A	6.447	74.051	12.351	15.34	0.000	0.000
					B	6.082	56.716		19.67	0.000	0.000
					C	6.098	68.599		16.54	0.000	0.000
T6 90.00-80.00	85.00	1.31	8	126.517	A	6.849	74.983	13.283	16.23	0.000	0.000
					B	6.499	57.648		20.71	0.000	0.000
					C	6.420	72.265		16.88	0.000	0.000
T7 80.00-60.00	70.00	1.24	8	283.450	A	14.936	151.524	28.124	16.90	0.000	0.000
					B	14.269	116.854		21.45	0.000	0.000
					C	13.982	150.334		17.12	0.000	0.000
T8 60.00-40.00	50.00	1.126	7	323.362	A	19.403	151.709	28.309	16.54	0.000	0.000
					B	18.662	117.039		20.86	0.000	0.000
					C	18.343	150.519		16.76	0.000	0.000
T9 40.00-20.00	30.00	1	6	363.756	A	21.437	154.657	29.807	16.93	0.000	0.000
					B	20.722	119.987		21.18	0.000	0.000
					C	20.414	152.017		17.29	0.000	0.000
T10 20.00-0.00	10.00	1	6	404.134	A	26.964	113.371	31.276	22.29	0.000	0.000
					B	26.446	90.836		26.67	0.000	0.000
					C	26.223	110.713		22.84	0.000	0.000

Tower Forces - No Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	CF	RR	DF	DR	AG	F	w	Ctrl. Face
ft	K	K	e						ft²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	1	1	37.149	2.29	114.29	A
			B	0.447	1.978	0.672	1	1	30.910			
			C	0.161	2.732	0.583	1	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	1	1	34.128	1.93	193.38	A
			B	0.59	1.81	0.748	1	1	30.529			
			C	0.291	2.32	0.613	1	1	13.910			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	1	1	66.514	4.23	211.37	B
			B	0.603	1.802	0.755	1	1	76.214			
			C	0.276	2.363	0.609	1	1	31.285			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	1	1	93.057	5.25	262.50	B
			B	0.623	1.792	0.768	1	1	99.866			
			C	0.518	1.878	0.707	1	1	77.988			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	1	1	66.761	3.34	333.60	A
			B	0.54	1.853	0.719	1	1	46.850			
			C	0.642	1.784	0.781	1	1	59.641			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	1	1	65.589	3.19	318.69	A
			B	0.507	1.891	0.701	1	1	46.917			
			C	0.622	1.792	0.767	1	1	61.867			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	1	1	127.956	5.98	299.04	A
			B	0.463	1.953	0.679	1	1	93.629			
			C	0.58	1.818	0.741	1	1	125.437			
T8	1.26	4.45	A	0.529	1.865	0.713	1	1	127.543	5.57	278.60	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	20 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
60.00-40.00			B	0.42	2.026	0.66	1	1	95.887			
			C	0.522	1.873	0.709	1	1	125.073			
T9	1.27	5.44	A	0.484	1.922	0.69	1	1	128.076	5.12	255.98	A
40.00-20.00			B	0.387	2.091	0.646	1	1	98.271			
			C	0.474	1.936	0.685	1	1	124.485			
T10	0.83	6.08	A	0.347	2.178	0.631	1	1	98.557	4.47	223.27	A
20.00-0.00			B	0.29	2.322	0.613	1	1	82.124			
			C	0.339	2.198	0.629	1	1	95.812			
Sum Weight:	7.61	30.71						OTM	3256.52 kip-ft	41.36		

Tower Forces - No Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.825	1	37.149	2.29	114.29	A
170.00-150.00			B	0.447	1.978	0.672	0.825	1	30.910			
			C	0.161	2.732	0.583	0.825	1	9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.825	1	33.202	1.88	188.14	A
150.00-140.00			B	0.59	1.81	0.748	0.825	1	29.570			
			C	0.291	2.32	0.613	0.825	1	12.952			
T3	0.44	2.09	A	0.545	1.849	0.721	0.825	1	64.733	4.13	206.70	B
140.00-120.00			B	0.603	1.802	0.755	0.825	1	74.531			
			C	0.276	2.363	0.609	0.825	1	29.454			
T4	0.91	2.80	A	0.591	1.81	0.748	0.825	1	90.664	5.13	256.63	B
120.00-100.00			B	0.623	1.792	0.768	0.825	1	97.634			
			C	0.518	1.878	0.707	0.825	1	75.698			
T5	0.62	1.48	A	0.692	1.776	0.814	0.825	1	65.632	3.28	327.96	A
100.00-90.00			B	0.54	1.853	0.719	0.825	1	45.785			
			C	0.642	1.784	0.781	0.825	1	58.574			
T6	0.63	1.76	A	0.647	1.782	0.783	0.825	1	64.390	3.13	312.87	A
90.00-80.00			B	0.507	1.891	0.701	0.825	1	45.780			
			C	0.622	1.792	0.767	0.825	1	60.743			
T7	1.26	4.33	A	0.587	1.812	0.746	0.825	1	125.342	5.86	292.93	A
80.00-60.00			B	0.463	1.953	0.679	0.825	1	91.132			
			C	0.58	1.818	0.741	0.825	1	122.990			
T8	1.26	4.45	A	0.529	1.865	0.713	0.825	1	124.147	5.42	271.18	A
60.00-40.00			B	0.42	2.026	0.66	0.825	1	92.621			
			C	0.522	1.873	0.709	0.825	1	121.863			
T9	1.27	5.44	A	0.484	1.922	0.69	0.825	1	124.325	4.97	248.49	A
40.00-20.00			B	0.387	2.091	0.646	0.825	1	94.645			
			C	0.474	1.936	0.685	0.825	1	120.912			
T10	0.83	6.08	A	0.347	2.178	0.631	0.825	1	93.838	4.25	212.58	A
20.00-0.00			B	0.29	2.322	0.613	0.825	1	77.496			
			C	0.339	2.198	0.629	0.825	1	91.223			
Sum Weight:	7.61	30.71						OTM	3190.95 kip-ft	40.35		

Tower Forces - No Ice - Wind 60 To Face

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	21 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.8	1	37.149	2.29	114.29	A
			B	0.447	1.978	0.672	0.8	1	30.910			
			C	0.161	2.732	0.583	0.8	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.8	1	33.069	1.87	187.39	A
			B	0.59	1.81	0.748	0.8	1	29.433			
			C	0.291	2.32	0.613	0.8	1	12.815			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.8	1	64.478	4.12	206.03	B
			B	0.603	1.802	0.755	0.8	1	74.291			
			C	0.276	2.363	0.609	0.8	1	29.192			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.8	1	90.322	5.12	255.80	B
			B	0.623	1.792	0.768	0.8	1	97.316			
			C	0.518	1.878	0.707	0.8	1	75.371			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.8	1	65.471	3.27	327.16	A
			B	0.54	1.853	0.719	0.8	1	45.633			
			C	0.642	1.784	0.781	0.8	1	58.421			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.8	1	64.219	3.12	312.03	A
			B	0.507	1.891	0.701	0.8	1	45.617			
			C	0.622	1.792	0.767	0.8	1	60.583			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.8	1	124.968	5.84	292.06	A
			B	0.463	1.953	0.679	0.8	1	90.775			
			C	0.58	1.818	0.741	0.8	1	122.641			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.8	1	123.662	5.40	270.13	A
			B	0.42	2.026	0.66	0.8	1	92.154			
			C	0.522	1.873	0.709	0.8	1	121.404			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.8	1	123.789	4.95	247.41	A
			B	0.387	2.091	0.646	0.8	1	94.127			
			C	0.474	1.936	0.685	0.8	1	120.402			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.8	1	93.164	4.22	211.05	A
			B	0.29	2.322	0.613	0.8	1	76.835			
			C	0.339	2.198	0.629	0.8	1	90.567			
Sum Weight:	7.61	30.71						OTM	3181.59 kip-ft	40.20		

Tower Forces - No Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.85	1	37.149	2.29	114.29	A
			B	0.447	1.978	0.672	0.85	1	30.910			
			C	0.161	2.732	0.583	0.85	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.85	1	33.334	1.89	188.89	A
			B	0.59	1.81	0.748	0.85	1	29.707			
			C	0.291	2.32	0.613	0.85	1	13.089			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.85	1	64.987	4.15	207.37	B
			B	0.603	1.802	0.755	0.85	1	74.772			
			C	0.276	2.363	0.609	0.85	1	29.715			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.85	1	91.006	5.15	257.47	B
			B	0.623	1.792	0.768	0.85	1	97.953			
			C	0.518	1.878	0.707	0.85	1	76.025			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.85	1	65.794	3.29	328.77	A
			B	0.54	1.853	0.719	0.85	1	45.937			
			C	0.642	1.784	0.781	0.85	1	58.726			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.85	1	64.561	3.14	313.70	A
			B	0.507	1.891	0.701	0.85	1	45.942			

inxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	22 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T7 80.00-60.00	1.26	4.33	C	0.622	1.792	0.767	0.85	1	60.904	5.88	293.80	A
			A	0.587	1.812	0.746	0.85	1	125.715			
			B	0.463	1.953	0.679	0.85	1	91.488			
T8 60.00-40.00	1.26	4.45	C	0.58	1.818	0.741	0.85	1	123.340	5.44	272.24	A
			A	0.529	1.865	0.713	0.85	1	124.632			
			B	0.42	2.026	0.66	0.85	1	93.087			
T9 40.00-20.00	1.27	5.44	C	0.522	1.873	0.709	0.85	1	122.322	4.99	249.56	A
			A	0.484	1.922	0.69	0.85	1	124.860			
			B	0.387	2.091	0.646	0.85	1	95.163			
T10 20.00-0.00	0.83	6.08	C	0.474	1.936	0.685	0.85	1	121.422	4.28	214.10	A
			A	0.347	2.178	0.631	0.85	1	94.512			
			B	0.29	2.322	0.613	0.85	1	78.157			
Sum Weight:	7.61	30.71	C	0.339	2.198	0.629	0.85	1	91.878	40.49		
								OTM	3200.32			
									kip-ft			

Tower Forces - With Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	1	1	78.881	3.54	177.15	A
			B	0.714	1.778	0.83	1	1	62.028			
			C	0.299	2.299	0.616	1	1	20.604			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	1	1	65.006	3.16	316.37	A
			B	0.888	1.907	0.972	1	1	57.882			
			C	0.465	1.949	0.68	1	1	23.498			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	1	1	129.881	6.95	347.34	B
			B	0.932	1.972	1	1	1	152.582			
			C	0.416	2.033	0.658	1	1	49.621			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	1	1	162.417	8.14	407.09	B
			B	0.924	1.96	1	1	1	188.717			
			C	0.692	1.776	0.814	1	1	119.741			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	1	1	108.610	4.51	450.57	A
			B	0.804	1.819	0.9	1	1	86.385			
			C	0.819	1.831	0.912	1	1	88.747			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	1	1	105.559	4.06	405.79	A
			B	0.753	1.789	0.859	1	1	84.866			
			C	0.795	1.813	0.892	1	1	92.106			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	1	1	200.955	7.02	351.19	A
			B	0.686	1.776	0.81	1	1	165.364			
			C	0.747	1.786	0.855	1	1	187.195			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	1	1	193.648	6.04	302.22	A
			B	0.618	1.794	0.765	1	1	163.176			
			C	0.672	1.777	0.8	1	1	182.461			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	1	1	192.241	5.34	267.14	A
			B	0.572	1.824	0.737	1	1	165.109			
			C	0.611	1.798	0.76	1	1	179.432			
T10 20.00-0.00	2.30	8.52	A	0.471	1.94	0.683	1	1	139.939	4.24	211.79	A
			B	0.425	2.017	0.662	1	1	127.801			
			C	0.442	1.986	0.67	1	1	133.241			
Sum Weight:	21.02	45.71						OTM	4593.81	53.01		
									kip-ft			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 23 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Tower Forces - With Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.825	1	78.265	3.52	175.77	A
			B	0.714	1.778	0.83	0.825	1	62.028			
			C	0.299	2.299	0.616	0.825	1	19.988			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.825	1	63.789	3.10	310.45	A
			B	0.888	1.907	0.972	0.825	1	56.923			
			C	0.465	1.949	0.68	0.825	1	22.232			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.825	1	127.510	6.75	337.60	B
			B	0.932	1.972	1	0.825	1	148.302			
			C	0.416	2.033	0.658	0.825	1	47.174			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.825	1	159.433	7.89	394.28	B
			B	0.924	1.96	1	0.825	1	182.776			
			C	0.692	1.776	0.814	0.825	1	115.214			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	0.825	1	107.184	4.45	444.65	A
			B	0.804	1.819	0.9	0.825	1	83.443			
			C	0.819	1.831	0.912	0.825	1	86.273			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	0.825	1	104.062	4.00	400.04	A
			B	0.753	1.789	0.859	0.825	1	81.847			
			C	0.795	1.813	0.892	0.825	1	89.300			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	0.825	1	197.745	6.91	345.58	A
			B	0.686	1.776	0.81	0.825	1	159.096			
			C	0.747	1.786	0.855	0.825	1	181.152			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	0.825	1	189.657	5.92	295.99	A
			B	0.618	1.794	0.765	0.825	1	156.157			
			C	0.672	1.777	0.8	0.825	1	175.675			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	0.825	1	187.894	5.22	261.10	A
			B	0.572	1.824	0.737	0.825	1	157.723			
			C	0.611	1.798	0.76	0.825	1	172.276			
T10 20.00-0.00	2.30	8.52	A	0.471	1.94	0.683	0.825	1	134.834	4.08	204.06	A
			B	0.425	2.017	0.662	0.825	1	120.742			
			C	0.442	1.986	0.67	0.825	1	126.338			
Sum Weight:	21.02	45.71						OTM	4497.51 kip-ft	51.84		

Tower Forces - With Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.8	1	78.177	3.51	175.57	A
			B	0.714	1.778	0.83	0.8	1	62.028			
			C	0.299	2.299	0.616	0.8	1	19.901			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.8	1	63.615	3.10	309.60	A
			B	0.888	1.907	0.972	0.8	1	56.786			
			C	0.465	1.949	0.68	0.8	1	22.051			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.8	1	127.171	6.72	336.21	B
			B	0.932	1.972	1	0.8	1	147.691			
			C	0.416	2.033	0.658	0.8	1	46.824			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.8	1	159.007	7.85	392.45	B
			B	0.924	1.96	1	0.8	1	181.928			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 24 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T5 100.00-90.00	1.67	2.39	C	0.692	1.776	0.814	0.8	1	114.568	4.44	443.81	A
			A	0.928	1.966	1	0.8	1	106.980			
			B	0.804	1.819	0.9	0.8	1	83.022			
T6 90.00-80.00	1.71	2.70	C	0.819	1.831	0.912	0.8	1	85.919	3.99	399.21	A
			A	0.867	1.88	0.953	0.8	1	103.848			
			B	0.753	1.789	0.859	0.8	1	81.415			
T7 80.00-60.00	3.48	6.30	C	0.795	1.813	0.892	0.8	1	88.899	6.90	344.78	A
			A	0.787	1.807	0.886	0.8	1	197.286			
			B	0.686	1.776	0.81	0.8	1	158.201			
T8 60.00-40.00	3.48	6.58	C	0.747	1.786	0.855	0.8	1	180.289	5.90	295.10	A
			A	0.707	1.777	0.825	0.8	1	189.087			
			B	0.618	1.794	0.765	0.8	1	155.155			
T9 40.00-20.00	3.51	7.67	C	0.672	1.777	0.8	0.8	1	174.705	5.20	260.23	A
			A	0.651	1.781	0.786	0.8	1	187.273			
			B	0.572	1.824	0.737	0.8	1	156.668			
T10 20.00-0.00	2.30	8.52	C	0.611	1.798	0.76	0.8	1	171.254	4.06	202.96	A
			A	0.471	1.94	0.683	0.8	1	134.105			
			B	0.425	2.017	0.662	0.8	1	119.734			
Sum Weight:	21.02	45.71	C	0.442	1.986	0.67	0.8	1	125.352	51.67		
								OTM	4483.75 kip-ft			

Tower Forces - With Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.85	1	78.353	3.52	175.96	A
			B	0.714	1.778	0.83	0.85	1	62.028			
			C	0.299	2.299	0.616	0.85	1	20.076			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.85	1	63.963	3.11	311.30	A
			B	0.888	1.907	0.972	0.85	1	57.060			
			C	0.465	1.949	0.68	0.85	1	22.413			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.85	1	127.849	6.78	338.99	B
			B	0.932	1.972	1	0.85	1	148.914			
			C	0.416	2.033	0.658	0.85	1	47.523			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.85	1	159.860	7.92	396.11	B
			B	0.924	1.96	1	0.85	1	183.625			
			C	0.692	1.776	0.814	0.85	1	115.861			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	0.85	1	107.387	4.45	445.50	A
			B	0.804	1.819	0.9	0.85	1	83.863			
			C	0.819	1.831	0.912	0.85	1	86.626			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	0.85	1	104.276	4.01	400.86	A
			B	0.753	1.789	0.859	0.85	1	82.278			
			C	0.795	1.813	0.892	0.85	1	89.701			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	0.85	1	198.203	6.93	346.38	A
			B	0.686	1.776	0.81	0.85	1	159.991			
			C	0.747	1.786	0.855	0.85	1	182.015			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	0.85	1	190.227	5.94	296.88	A
			B	0.618	1.794	0.765	0.85	1	157.160			
			C	0.672	1.777	0.8	0.85	1	176.644			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	0.85	1	188.515	5.24	261.96	A
			B	0.572	1.824	0.737	0.85	1	158.778			
			C	0.611	1.798	0.76	0.85	1	173.298			
T10	2.30	8.52	A	0.471	1.94	0.683	0.85	1	135.564	4.10	205.17	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	25 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section Elevation	Add Weight	Self Weight	Face	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
20.00-0.00			B	0.425	2.017	0.662	0.85	1	121.751			
			C	0.442	1.986	0.67	0.85	1	127.324			
Sum Weight:	21.02	45.71						OTM	4511.26 kip-ft	52.01		

Tower Forces - Service - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	Face	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	1	1	37.149	0.79	39.55	A
170.00-150.00			B	0.447	1.978	0.672	1	1	30.910			
			C	0.161	2.732	0.583	1	1	9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	1	1	34.128	0.67	66.92	A
150.00-140.00			B	0.59	1.81	0.748	1	1	30.529			
			C	0.291	2.32	0.613	1	1	13.910			
T3	0.44	2.09	A	0.545	1.849	0.721	1	1	66.514	1.46	73.14	B
140.00-120.00			B	0.603	1.802	0.755	1	1	76.214			
			C	0.276	2.363	0.609	1	1	31.285			
T4	0.91	2.80	A	0.591	1.81	0.748	1	1	93.057	1.82	90.83	B
120.00-100.00			B	0.623	1.792	0.768	1	1	99.866			
			C	0.518	1.878	0.707	1	1	77.988			
T5	0.62	1.48	A	0.692	1.776	0.814	1	1	66.761	1.15	115.43	A
100.00-90.00			B	0.54	1.853	0.719	1	1	46.850			
			C	0.642	1.784	0.781	1	1	59.641			
T6	0.63	1.76	A	0.647	1.782	0.783	1	1	65.589	1.10	110.27	A
90.00-80.00			B	0.507	1.891	0.701	1	1	46.917			
			C	0.622	1.792	0.767	1	1	61.867			
T7	1.26	4.33	A	0.587	1.812	0.746	1	1	127.956	2.07	103.47	A
80.00-60.00			B	0.463	1.953	0.679	1	1	93.629			
			C	0.58	1.818	0.741	1	1	125.437			
T8	1.26	4.45	A	0.529	1.865	0.713	1	1	127.543	1.93	96.40	A
60.00-40.00			B	0.42	2.026	0.66	1	1	95.887			
			C	0.522	1.873	0.709	1	1	125.073			
T9	1.27	5.44	A	0.484	1.922	0.69	1	1	128.076	1.77	88.58	A
40.00-20.00			B	0.387	2.091	0.646	1	1	98.271			
			C	0.474	1.936	0.685	1	1	124.485			
T10	0.83	6.08	A	0.347	2.178	0.631	1	1	98.557	1.55	77.25	A
20.00-0.00			B	0.29	2.322	0.613	1	1	82.124			
			C	0.339	2.198	0.629	1	1	95.812			
Sum Weight:	7.61	30.71						OTM	1126.82 kip-ft	14.31		

Tower Forces - Service - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	Face	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.825	1	37.149	0.79	39.55	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 26 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
170.00-150.00			B	0.447	1.978	0.672	0.825	1	30.910			
			C	0.161	2.732	0.583	0.825	1	9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.825	1	33.202	0.65	65.10	A
150.00-140.00			B	0.59	1.81	0.748	0.825	1	29.570			
			C	0.291	2.32	0.613	0.825	1	12.952			
T3	0.44	2.09	A	0.545	1.849	0.721	0.825	1	64.733	1.43	71.52	B
140.00-120.00			B	0.603	1.802	0.755	0.825	1	74.531			
			C	0.276	2.363	0.609	0.825	1	29.454			
T4	0.91	2.80	A	0.591	1.81	0.748	0.825	1	90.664	1.78	88.80	B
120.00-100.00			B	0.623	1.792	0.768	0.825	1	97.634			
			C	0.518	1.878	0.707	0.825	1	75.698			
T5	0.62	1.48	A	0.692	1.776	0.814	0.825	1	65.632	1.13	113.48	A
100.00-90.00			B	0.54	1.853	0.719	0.825	1	45.785			
			C	0.642	1.784	0.781	0.825	1	58.574			
T6	0.63	1.76	A	0.647	1.782	0.783	0.825	1	64.390	1.08	108.26	A
90.00-80.00			B	0.507	1.891	0.701	0.825	1	45.780			
			C	0.622	1.792	0.767	0.825	1	60.743			
T7	1.26	4.33	A	0.587	1.812	0.746	0.825	1	125.342	2.03	101.36	A
80.00-60.00			B	0.463	1.953	0.679	0.825	1	91.132			
			C	0.58	1.818	0.741	0.825	1	122.990			
T8	1.26	4.45	A	0.529	1.865	0.713	0.825	1	124.147	1.88	93.84	A
60.00-40.00			B	0.42	2.026	0.66	0.825	1	92.621			
			C	0.522	1.873	0.709	0.825	1	121.863			
T9	1.27	5.44	A	0.484	1.922	0.69	0.825	1	124.325	1.72	85.98	A
40.00-20.00			B	0.387	2.091	0.646	0.825	1	94.645			
			C	0.474	1.936	0.685	0.825	1	120.912			
T10	0.83	6.08	A	0.347	2.178	0.631	0.825	1	93.838	1.47	73.56	A
20.00-0.00			B	0.29	2.322	0.613	0.825	1	77.496			
			C	0.339	2.198	0.629	0.825	1	91.223			
Sum Weight:	7.61	30.71						OTM	1104.14 kip-ft	13.96		

Tower Forces - Service - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.8	1	37.149	0.79	39.55	A
170.00-150.00			B	0.447	1.978	0.672	0.8	1	30.910			
			C	0.161	2.732	0.583	0.8	1	9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.8	1	33.069	0.65	64.84	A
150.00-140.00			B	0.59	1.81	0.748	0.8	1	29.433			
			C	0.291	2.32	0.613	0.8	1	12.815			
T3	0.44	2.09	A	0.545	1.849	0.721	0.8	1	64.478	1.43	71.29	B
140.00-120.00			B	0.603	1.802	0.755	0.8	1	74.291			
			C	0.276	2.363	0.609	0.8	1	29.192			
T4	0.91	2.80	A	0.591	1.81	0.748	0.8	1	90.322	1.77	88.51	B
120.00-100.00			B	0.623	1.792	0.768	0.8	1	97.316			
			C	0.518	1.878	0.707	0.8	1	75.371			
T5	0.62	1.48	A	0.692	1.776	0.814	0.8	1	65.471	1.13	113.20	A
100.00-90.00			B	0.54	1.853	0.719	0.8	1	45.633			
			C	0.642	1.784	0.781	0.8	1	58.421			
T6	0.63	1.76	A	0.647	1.782	0.783	0.8	1	64.219	1.08	107.97	A
90.00-80.00			B	0.507	1.891	0.701	0.8	1	45.617			
			C	0.622	1.792	0.767	0.8	1	60.583			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	27 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.8	1	124.968	2.02	101.06	A
			B	0.463	1.953	0.679	0.8	1	90.775			
			C	0.58	1.818	0.741	0.8	1	122.641			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.8	1	123.662	1.87	93.47	A
			B	0.42	2.026	0.66	0.8	1	92.154			
			C	0.522	1.873	0.709	0.8	1	121.404			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.8	1	123.789	1.71	85.61	A
			B	0.387	2.091	0.646	0.8	1	94.127			
			C	0.474	1.936	0.685	0.8	1	120.402			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.8	1	93.164	1.46	73.03	A
			B	0.29	2.322	0.613	0.8	1	76.835			
			C	0.339	2.198	0.629	0.8	1	90.567			
Sum Weight:	7.61	30.71						OTM	1100.90 kip-ft	13.91		

Tower Forces - Service - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K	e						ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.85	1	37.149	0.79	39.55	A
			B	0.447	1.978	0.672	0.85	1	30.910			
			C	0.161	2.732	0.583	0.85	1	9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.85	1	33.334	0.65	65.36	A
			B	0.59	1.81	0.748	0.85	1	29.707			
			C	0.291	2.32	0.613	0.85	1	13.089			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.85	1	64.987	1.44	71.75	B
			B	0.603	1.802	0.755	0.85	1	74.772			
			C	0.276	2.363	0.609	0.85	1	29.715			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.85	1	91.006	1.78	89.09	B
			B	0.623	1.792	0.768	0.85	1	97.953			
			C	0.518	1.878	0.707	0.85	1	76.025			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.85	1	65.794	1.14	113.76	A
			B	0.54	1.853	0.719	0.85	1	45.937			
			C	0.642	1.784	0.781	0.85	1	58.726			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.85	1	64.561	1.09	108.55	A
			B	0.507	1.891	0.701	0.85	1	45.942			
			C	0.622	1.792	0.767	0.85	1	60.904			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.85	1	125.715	2.03	101.66	A
			B	0.463	1.953	0.679	0.85	1	91.488			
			C	0.58	1.818	0.741	0.85	1	123.340			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.85	1	124.632	1.88	94.20	A
			B	0.42	2.026	0.66	0.85	1	93.087			
			C	0.522	1.873	0.709	0.85	1	122.322			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.85	1	124.860	1.73	86.35	A
			B	0.387	2.091	0.646	0.85	1	95.163			
			C	0.474	1.936	0.685	0.85	1	121.422			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.85	1	94.512	1.48	74.08	A
			B	0.29	2.322	0.613	0.85	1	78.157			
			C	0.339	2.198	0.629	0.85	1	91.878			
Sum Weight:	7.61	30.71						OTM	1107.38 kip-ft	14.01		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	28 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Force Totals

Load Case	Vertical Forces	Sum of Forces X	Sum of Forces Z	Sum of Overturning Moments, M _x	Sum of Overturning Moments, M _z	Sum of Torques
	K	K	K	kip-ft	kip-ft	kip-ft
Leg Weight	19.74					
Bracing Weight	10.97					
Total Member Self-Weight	30.71			-2.00	10.22	
Total Weight	51.76			-2.00	10.22	
Wind 0 deg - No Ice		-0.00	-59.80	-5735.38	9.52	-22.58
Wind 30 deg - No Ice		29.38	-51.00	-4915.51	-2819.50	-22.39
Wind 45 deg - No Ice		41.70	-41.43	-3995.12	-4018.20	-19.59
Wind 60 deg - No Ice		50.98	-29.16	-2811.44	-4920.96	-15.40
Wind 90 deg - No Ice		58.93	0.20	23.35	-5672.58	-5.44
Wind 120 deg - No Ice		51.82	30.15	2886.05	-4964.20	6.29
Wind 135 deg - No Ice		41.66	41.68	4010.21	-4015.07	11.49
Wind 150 deg - No Ice		29.61	51.09	4914.77	-2851.78	16.61
Wind 180 deg - No Ice		0.18	58.86	5679.91	-12.31	24.21
Wind 210 deg - No Ice		-29.47	51.04	4909.53	2855.27	22.73
Wind 225 deg - No Ice		-41.57	41.62	4003.79	4025.26	20.34
Wind 240 deg - No Ice		-51.73	30.10	2880.77	4974.09	17.65
Wind 270 deg - No Ice		-58.86	0.11	14.18	5683.52	7.67
Wind 300 deg - No Ice		-50.86	-29.30	-2827.60	4924.33	-4.03
Wind 315 deg - No Ice		-41.60	-41.53	-4005.88	4023.54	-9.89
Wind 330 deg - No Ice		-29.39	-51.04	-4920.00	2839.20	-15.90
Member Ice	15.00					
Total Weight Ice	85.94			-2.53	24.99	
Wind 0 deg - Ice		-0.00	-70.06	-6888.37	24.17	-19.30
Wind 30 deg - Ice		34.47	-59.78	-5892.08	-3369.80	-25.33
Wind 45 deg - Ice		48.82	-48.61	-4792.02	-4792.76	-25.47
Wind 60 deg - Ice		59.68	-34.24	-3374.92	-5867.95	-23.80
Wind 90 deg - Ice		69.06	0.16	17.52	-6782.93	-16.94
Wind 120 deg - Ice		60.70	35.23	3457.02	-5945.67	-5.50
Wind 135 deg - Ice		48.79	48.80	4801.52	-4789.97	1.25
Wind 150 deg - Ice		34.65	59.85	5889.08	-3395.34	8.13
Wind 180 deg - Ice		0.14	68.90	6791.88	7.18	20.70
Wind 210 deg - Ice		-34.54	59.81	5885.14	3432.19	25.61
Wind 225 deg - Ice		-48.72	48.75	4796.73	4832.10	26.08
Wind 240 deg - Ice		-60.63	35.19	3453.23	5987.45	25.89
Wind 270 deg - Ice		-69.00	0.09	10.68	6825.29	18.72
Wind 300 deg - Ice		-59.58	-34.34	-3387.44	5903.99	6.93
Wind 315 deg - Ice		-48.74	-48.68	-4800.29	4830.27	0.02
Wind 330 deg - Ice		-34.47	-59.81	-5895.42	3418.74	-7.56
Total Weight	51.76			-2.00	10.22	
Wind 0 deg - Service		-0.00	-20.69	-1988.06	1.09	-7.81
Wind 30 deg - Service		10.17	-17.65	-1704.37	-977.81	-7.75
Wind 45 deg - Service		14.43	-14.34	-1385.90	-1392.59	-6.78
Wind 60 deg - Service		17.64	-10.09	-976.32	-1704.96	-5.33
Wind 90 deg - Service		20.39	0.07	4.58	-1965.04	-1.88
Wind 120 deg - Service		17.93	10.43	995.13	-1719.92	2.18
Wind 135 deg - Service		14.42	14.42	1384.12	-1391.51	3.98
Wind 150 deg - Service		10.25	17.68	1697.11	-988.98	5.75
Wind 180 deg - Service		0.06	20.37	1961.86	-6.47	8.38
Wind 210 deg - Service		-10.20	17.66	1695.30	985.78	7.86
Wind 225 deg - Service		-14.38	14.40	1381.89	1390.62	7.04
Wind 240 deg - Service		-17.90	10.41	993.30	1718.93	6.11
Wind 270 deg - Service		-20.37	0.04	1.40	1964.41	2.65
Wind 300 deg - Service		-17.60	-10.14	-981.91	1701.71	-1.39
Wind 315 deg - Service		-14.39	-14.37	-1389.62	1390.02	-3.42
Wind 330 deg - Service		-10.17	-17.66	-1705.92	980.21	-5.50

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 29 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice+Temp
19	Dead+Wind 0 deg+Ice+Temp
20	Dead+Wind 30 deg+Ice+Temp
21	Dead+Wind 45 deg+Ice+Temp
22	Dead+Wind 60 deg+Ice+Temp
23	Dead+Wind 90 deg+Ice+Temp
24	Dead+Wind 120 deg+Ice+Temp
25	Dead+Wind 135 deg+Ice+Temp
26	Dead+Wind 150 deg+Ice+Temp
27	Dead+Wind 180 deg+Ice+Temp
28	Dead+Wind 210 deg+Ice+Temp
29	Dead+Wind 225 deg+Ice+Temp
30	Dead+Wind 240 deg+Ice+Temp
31	Dead+Wind 270 deg+Ice+Temp
32	Dead+Wind 300 deg+Ice+Temp
33	Dead+Wind 315 deg+Ice+Temp
34	Dead+Wind 330 deg+Ice+Temp
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	30 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft		
T1	170 - 150	Leg	Max Tension	22	30.17	-0.04	0.05		
			Max. Compression	19	-36.50	-0.00	0.46		
			Max. Mx	24	-36.25	-0.38	-0.25		
			Max. My	19	-36.50	-0.00	0.46		
			Max. Vy	30	-3.95	0.05	-0.06		
		Diagonal	Max. Vx	19	-4.58	-0.00	0.46		
			Max Tension	26	3.44	0.00	0.00		
			Max. Compression	26	-3.50	0.00	0.00		
			Max. Mx	19	2.92	-0.00	0.00		
			Max. My	22	-2.12	-0.00	0.00		
			Max. Vy	19	0.01	-0.00	0.00		
			Max. Vx	21	0.00	0.00	0.00		
		Top Girt	Max Tension	7	0.31	0.00	0.00		
			Max. Compression	15	-0.35	0.00	0.00		
			Max. Mx	18	-0.01	0.01	0.00		
			Max. My	31	0.01	0.00	-0.00		
			Max. Vy	18	-0.01	0.00	0.00		
		Bottom Girt	Max. Vx	31	0.00	0.00	0.00		
			Max Tension	15	0.15	0.00	0.00		
			Max. Compression	13	-0.16	0.00	0.00		
			Max. Mx	18	-0.00	0.01	0.00		
Max. My	31		-0.01	0.00	-0.00				
Max. Vy	18		-0.01	0.00	0.00				
Max. Vx	31		0.00	0.00	0.00				
T2	150 - 140	Leg	Max Tension	22	35.47	-0.43	0.02		
			Max. Compression	19	-42.40	2.82	0.28		
			Max. Mx	22	34.84	-3.32	0.23		
			Max. My	34	-3.52	-0.26	4.08		
			Max. Vy	27	0.64	-3.31	-0.36		
		Diagonal	Max. Vx	30	0.87	-1.77	-3.65		
			Max Tension	22	4.94	0.00	0.00		
			Max. Compression	30	-5.49	0.00	0.00		
			Max. Mx	22	4.36	0.05	0.00		
			Max. My	21	-4.26	-0.02	0.02		
			Max. Vy	22	0.02	0.05	0.00		
			Max. Vx	21	-0.00	0.00	0.00		
		Top Girt	Max Tension	5	0.43	0.00	0.00		
			Max. Compression	2	-0.38	0.00	0.00		
			Max. Mx	18	0.04	-0.02	0.00		
Max. My	30		0.22	0.00	0.00				
Max. Vy	18		0.02	0.00	0.00				
T3	140 - 120	Leg	Max. Vx	30	-0.00	0.00	0.00		
			Max Tension	32	71.11	-3.73	-0.17		
			Max. Compression	19	-85.15	3.71	0.03		
			Max. Mx	32	69.96	-4.54	-0.16		
			Max. My	31	-8.52	-0.42	-6.67		
		Diagonal	Max. Vy	27	0.69	-4.49	-0.05		
			Max. Vx	23	-0.99	-0.41	6.63		
			Max Tension	28	9.10	0.00	0.00		
			Max. Compression	29	-9.47	0.00	0.00		
			Max. Mx	19	5.86	0.11	0.01		
			Max. My	29	-7.66	-0.06	-0.02		
			Max. Vy	19	-0.03	0.11	0.01		
		T4	120 - 100	Leg	Max. Vx	21	-0.00	0.00	0.00
					Max Tension	32	117.90	-5.16	-0.02
					Max. Compression	19	-139.22	3.41	0.04
Max. Mx	19				-110.62	6.17	0.00		
Max. My	31				-11.48	-0.47	-7.40		
Max. Vy	27				1.00	-4.26	-0.07		
			Max. Vx	31	1.73	-0.47	-7.40		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	31 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T5	100 - 90	Diagonal	Max Tension	21	11.57	0.00	0.00
			Max. Compression	29	-12.59	0.00	0.00
			Max. Mx	19	7.10	0.13	0.01
			Max. My	29	-12.55	-0.06	-0.05
			Max. Vy	32	0.04	0.12	-0.00
			Max. Vx	29	0.01	0.00	0.00
		Mid Girt	Max Tension	32	3.95	0.00	0.00
			Max. Compression	19	-3.19	0.00	0.00
			Max. Mx	18	0.44	-0.07	0.00
			Max. My	30	2.12	0.00	0.00
			Max. Vy	18	0.03	0.00	0.00
			Max. Vx	30	0.00	0.00	0.00
		Leg	Max Tension	32	145.66	-4.29	-0.10
			Max. Compression	19	-171.52	4.62	0.02
			Max. Mx	19	-171.52	4.62	0.02
			Max. My	31	-12.69	-0.47	-7.40
			Max. Vy	24	-0.25	4.59	0.00
			Max. Vx	31	-0.49	-0.47	-7.40
Diagonal	Max Tension		28	13.51	0.00	0.00	
	Max. Compression		28	-13.76	0.00	0.00	
	Max. Mx		19	10.41	0.18	0.01	
	Max. My		30	-0.58	0.09	-0.02	
	Max. Vy		19	-0.05	0.18	0.01	
	Max. Vx		30	-0.00	0.00	0.00	
T6	90 - 80	Leg	Max Tension	32	173.97	-4.34	0.01
			Max. Compression	19	-203.14	5.81	0.05
			Max. Mx	30	-202.34	5.81	-0.12
			Max. My	31	-14.65	-0.00	-4.71
			Max. Vy	27	0.39	-5.74	-0.06
			Max. Vx	31	0.28	-0.00	-4.71
		Diagonal	Max Tension	28	13.40	0.00	0.00
			Max. Compression	28	-13.78	0.00	0.00
			Max. Mx	19	10.34	0.15	0.01
			Max. My	30	-0.75	0.08	-0.02
			Max. Vy	19	-0.05	0.15	0.01
			Max. Vx	30	0.00	0.00	0.00
		Leg	Max Tension	32	226.30	-5.04	0.02
			Max. Compression	19	-262.71	5.58	0.01
			Max. Mx	30	-231.92	5.81	-0.12
			Max. My	34	-15.65	-0.09	5.21
			Max. Vy	22	-0.21	-5.72	0.11
			Max. Vx	34	-0.21	-0.09	5.21
Diagonal	Max Tension		28	13.80	0.00	0.00	
	Max. Compression		28	-14.18	0.00	0.00	
	Max. Mx		19	10.58	0.15	0.01	
	Max. My		21	-13.55	0.02	0.02	
	Max. Vy		32	0.05	0.15	-0.01	
	Max. Vx		21	-0.00	0.00	0.00	
T7	80 - 60	Leg	Max Tension	32	274.16	-5.04	0.02
			Max. Compression	30	-318.50	5.48	-0.09
			Max. Mx	32	273.59	-6.92	-0.01
			Max. My	34	-20.31	0.06	6.01
			Max. Vy	22	0.31	-6.91	0.07
			Max. Vx	26	0.22	0.05	-5.98
		Diagonal	Max Tension	28	13.89	0.00	0.00
			Max. Compression	28	-14.26	0.00	0.00
			Max. Mx	30	10.17	0.21	-0.01
			Max. My	21	-13.66	0.00	0.03
			Max. Vy	30	-0.06	0.21	-0.01
			Max. Vx	21	-0.00	0.00	0.00
		Leg	Max Tension	32	316.80	-3.07	0.03

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	32 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T10	20 - 0	Diagonal	Max. Compression	30	-371.60	-0.23	0.01
			Max. Mx	32	316.15	-11.60	0.02
			Max. My	31	-21.24	-0.76	-5.84
			Max. Vy	22	0.97	-11.58	-0.01
			Max. Vx	34	0.25	2.48	5.75
			Max Tension	28	15.14	0.00	0.00
			Max. Compression	28	-14.77	0.00	0.00
			Max. Mx	30	10.23	0.23	-0.02
			Max. My	28	-13.34	0.04	-0.03
			Max. Vy	32	0.07	0.21	-0.02
		Leg	Max. Vx	21	-0.00	0.00	0.00
			Max Tension	32	353.13	3.75	0.03
			Max. Compression	30	-421.49	-0.00	-0.00
			Max. Mx	30	-393.39	15.49	0.01
			Max. My	31	-30.35	9.54	-9.89
			Max. Vy	22	-1.65	-11.58	-0.01
			Max. Vx	34	1.09	9.55	9.88
			Max Tension	21	18.83	0.00	0.00
			Max. Compression	20	-16.66	0.00	0.00
			Max. Mx	32	7.52	0.30	-0.02
Max. My	21	-16.36	0.13	0.04			
Max. Vy	32	0.08	0.30	-0.02			
Max. Vx	21	-0.01	0.00	0.00			

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg C	Max. Vert	30	430.14	32.65	-19.73
	Max. H _x	13	350.47	32.66	-19.46
	Max. H _z	21	-351.65	-39.32	24.59
	Min. Vert	22	-364.58	-41.00	24.46
	Min. H _x	22	-364.58	-41.00	24.46
	Min. H _z	30	430.14	32.65	-19.73
Leg B	Max. Vert	24	428.15	-32.95	-19.21
	Max. H _x	32	-366.75	41.26	24.07
	Max. H _z	32	-366.75	41.26	24.07
	Min. Vert	32	-366.75	41.26	24.07
	Min. H _x	7	350.12	-33.04	-18.89
	Min. H _z	24	428.15	-32.95	-19.21
Leg A	Max. Vert	19	428.78	-0.58	38.09
	Max. H _x	31	28.04	3.85	-5.12
	Max. H _z	19	428.78	-0.58	38.09
	Min. Vert	27	-365.88	0.58	-47.81
	Min. H _x	23	27.64	-3.86	-5.15
	Min. H _z	27	-365.88	0.58	-47.81

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
------------------	------------	----------------------	----------------------	---	---	---------------

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	33 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Load Combination	Vertical	Shear _x	Shear _y	Overturning Moment, M _x	Overturning Moment, M _y	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	51.76	0.00	0.00	-2.00	10.22	-0.00
Dead+Wind 0 deg - No Ice	51.76	-0.00	-59.80	-5758.69	9.61	-22.64
Dead+Wind 30 deg - No Ice	51.76	29.38	-51.00	-4935.61	-2830.94	-22.45
Dead+Wind 45 deg - No Ice	51.76	41.70	-41.43	-4011.49	-4034.56	-19.65
Dead+Wind 60 deg - No Ice	51.76	50.98	-29.16	-2822.99	-4941.03	-15.48
Dead+Wind 90 deg - No Ice	51.76	58.93	0.20	23.36	-5695.69	-5.50
Dead+Wind 120 deg - No Ice	51.76	51.82	30.15	2897.69	-4984.35	6.28
Dead+Wind 135 deg - No Ice	51.76	41.66	41.68	4026.49	-4031.41	11.51
Dead+Wind 150 deg - No Ice	51.76	29.61	51.09	4934.74	-2863.36	16.65
Dead+Wind 180 deg - No Ice	51.76	0.18	58.86	5703.04	-12.28	24.26
Dead+Wind 210 deg - No Ice	51.76	-29.47	51.04	4929.45	2866.99	22.79
Dead+Wind 225 deg - No Ice	51.76	-41.57	41.62	4019.99	4041.73	20.41
Dead+Wind 240 deg - No Ice	51.76	-51.73	30.10	2892.34	4994.33	17.73
Dead+Wind 270 deg - No Ice	51.76	-58.86	0.11	14.17	5706.68	7.73
Dead+Wind 300 deg - No Ice	51.76	-50.86	-29.30	-2839.16	4944.42	-4.01
Dead+Wind 315 deg - No Ice	51.76	-41.60	-41.53	-4022.22	4039.96	-9.91
Dead+Wind 330 deg - No Ice	51.76	-29.39	-51.04	-4940.04	2850.78	-15.94
Dead+Ice+Temp	85.94	0.00	0.00	-2.58	25.03	0.00
Dead+Wind 0 deg+Ice+Temp	85.94	-0.00	-70.06	-6930.56	24.35	-19.44
Dead+Wind 30 deg+Ice+Temp	85.94	34.47	-59.78	-5928.32	-3390.41	-25.48
Dead+Wind 45 deg+Ice+Temp	85.94	48.82	-48.61	-4821.57	-4822.13	-25.61
Dead+Wind 60 deg+Ice+Temp	85.94	59.68	-34.24	-3395.82	-5903.94	-23.96
Dead+Wind 90 deg+Ice+Temp	85.94	69.06	0.16	17.41	-6824.51	-17.07
Dead+Wind 120 deg+Ice+Temp	85.94	60.70	35.23	3477.96	-5982.06	-5.52
Dead+Wind 135 deg+Ice+Temp	85.94	48.79	48.80	4830.78	-4819.34	1.30
Dead+Wind 150 deg+Ice+Temp	85.94	34.65	59.85	5925.05	-3416.14	8.22
Dead+Wind 180 deg+Ice+Temp	85.94	0.14	68.90	6833.43	7.30	20.84
Dead+Wind 210 deg+Ice+Temp	85.94	-34.54	59.81	5921.04	3453.30	25.75
Dead+Wind 225 deg+Ice+Temp	85.94	-48.72	48.75	4825.92	4861.78	26.23
Dead+Wind 240 deg+Ice+Temp	85.94	-60.63	35.19	3474.12	6024.12	26.04
Dead+Wind 270 deg+Ice+Temp	85.94	-69.00	0.09	10.56	6867.10	18.86
Dead+Wind 300 deg+Ice+Temp	85.94	-59.58	-34.34	-3408.33	5940.17	6.95
Dead+Wind 315 deg+Ice+Temp	85.94	-48.74	-48.68	-4829.80	4859.86	-0.02
Dead+Wind 330 deg+Ice+Temp	85.94	-34.47	-59.81	-5931.60	3439.69	-7.66
Dead+Wind 0 deg - Service	51.76	-0.00	-20.69	-1994.01	10.02	-7.84
Dead+Wind 30 deg - Service	51.76	10.17	-17.65	-1709.18	-972.89	-7.78
Dead+Wind 45 deg - Service	51.76	14.43	-14.34	-1389.41	-1389.37	-6.80
Dead+Wind 60 deg - Service	51.76	17.64	-10.09	-978.15	-1703.03	-5.36
Dead+Wind 90 deg - Service	51.76	20.39	0.07	6.76	-1964.16	-1.89
Dead+Wind 120 deg - Service	51.76	17.93	10.43	1001.35	-1718.02	2.17
Dead+Wind 135 deg - Service	51.76	14.42	14.42	1391.95	-1388.28	3.97
Dead+Wind 150 deg - Service	51.76	10.25	17.68	1706.23	-984.10	5.75
Dead+Wind 180 deg - Service	51.76	0.06	20.37	1972.07	2.45	8.40
Dead+Wind 210 deg - Service	51.76	-10.20	17.66	1704.40	998.76	7.90
Dead+Wind 225 deg - Service	51.76	-14.38	14.40	1389.71	1405.25	7.07
Dead+Wind 240 deg - Service	51.76	-17.90	10.41	999.52	1734.89	6.13
Dead+Wind 270 deg - Service	51.76	-20.37	0.04	3.58	1981.39	2.66
Dead+Wind 300 deg - Service	51.76	-17.60	-10.14	-983.76	1717.62	-1.39
Dead+Wind 315 deg - Service	51.76	-14.39	-14.37	-1393.13	1404.64	-3.42
Dead+Wind 330 deg - Service	51.76	-10.17	-17.66	-1710.73	993.16	-5.51

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-51.76	0.00	0.00	51.76	0.00	0.000%
2	-0.00	-51.76	-59.80	0.00	51.76	59.80	0.000%

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	34 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
3	29.38	-51.76	-51.00	-29.38	51.76	51.00	0.000%
4	41.70	-51.76	-41.43	-41.70	51.76	41.43	0.000%
5	50.98	-51.76	-29.16	-50.98	51.76	29.16	0.000%
6	58.93	-51.76	0.20	-58.93	51.76	-0.20	0.000%
7	51.82	-51.76	30.15	-51.82	51.76	-30.15	0.000%
8	41.66	-51.76	41.68	-41.66	51.76	-41.68	0.000%
9	29.61	-51.76	51.09	-29.61	51.76	-51.09	0.000%
10	0.18	-51.76	58.86	-0.18	51.76	-58.86	0.000%
11	-29.47	-51.76	51.04	29.47	51.76	-51.04	0.000%
12	-41.57	-51.76	41.62	41.57	51.76	-41.62	0.000%
13	-51.73	-51.76	30.10	51.73	51.76	-30.10	0.000%
14	-58.86	-51.76	0.11	58.86	51.76	-0.11	0.000%
15	-50.86	-51.76	-29.30	50.86	51.76	29.30	0.000%
16	-41.60	-51.76	-41.53	41.60	51.76	41.53	0.000%
17	-29.39	-51.76	-51.04	29.39	51.76	51.04	0.000%
18	0.00	-85.94	0.00	-0.00	85.94	0.00	0.000%
19	-0.00	-85.94	-70.06	0.00	85.94	70.06	0.000%
20	34.47	-85.94	-59.78	-34.47	85.94	59.78	0.000%
21	48.82	-85.94	-48.61	-48.82	85.94	48.61	0.000%
22	59.68	-85.94	-34.24	-59.68	85.94	34.24	0.000%
23	69.06	-85.94	0.16	-69.06	85.94	-0.16	0.000%
24	60.70	-85.94	35.23	-60.70	85.94	-35.23	0.000%
25	48.79	-85.94	48.80	-48.79	85.94	-48.80	0.000%
26	34.65	-85.94	59.85	-34.65	85.94	-59.85	0.000%
27	0.14	-85.94	68.90	-0.14	85.94	-68.90	0.000%
28	-34.54	-85.94	59.81	34.54	85.94	-59.81	0.000%
29	-48.72	-85.94	48.75	48.72	85.94	-48.75	0.000%
30	-60.63	-85.94	35.19	60.63	85.94	-35.19	0.000%
31	-69.00	-85.94	0.09	69.00	85.94	-0.09	0.000%
32	-59.58	-85.94	-34.34	59.58	85.94	34.34	0.000%
33	-48.74	-85.94	-48.68	48.74	85.94	48.68	0.000%
34	-34.47	-85.94	-59.81	34.47	85.94	59.81	0.000%
35	-0.00	-51.76	-20.69	0.00	51.76	20.69	0.000%
36	10.17	-51.76	-17.65	-10.17	51.76	17.65	0.000%
37	14.43	-51.76	-14.34	-14.43	51.76	14.34	0.000%
38	17.64	-51.76	-10.09	-17.64	51.76	10.09	0.000%
39	20.39	-51.76	0.07	-20.39	51.76	-0.07	0.000%
40	17.93	-51.76	10.43	-17.93	51.76	-10.43	0.000%
41	14.42	-51.76	14.42	-14.42	51.76	-14.42	0.000%
42	10.25	-51.76	17.68	-10.25	51.76	-17.68	0.000%
43	0.06	-51.76	20.37	-0.06	51.76	-20.37	0.000%
44	-10.20	-51.76	17.66	10.20	51.76	-17.66	0.000%
45	-14.38	-51.76	14.40	14.38	51.76	-14.40	0.000%
46	-17.90	-51.76	10.41	17.90	51.76	-10.41	0.000%
47	-20.37	-51.76	0.04	20.37	51.76	-0.04	0.000%
48	-17.60	-51.76	-10.14	17.60	51.76	10.14	0.000%
49	-14.39	-51.76	-14.37	14.39	51.76	14.37	0.000%
50	-10.17	-51.76	-17.66	10.17	51.76	17.66	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00000001
3	Yes	4	0.00000001	0.00000001

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 35 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

4	Yes	4	0.00000001	0.00000001
5	Yes	4	0.00000001	0.00000001
6	Yes	4	0.00000001	0.00000001
7	Yes	4	0.00000001	0.00000001
8	Yes	4	0.00000001	0.00000001
9	Yes	4	0.00000001	0.00000001
10	Yes	4	0.00000001	0.00000001
11	Yes	4	0.00000001	0.00000001
12	Yes	4	0.00000001	0.00000001
13	Yes	4	0.00000001	0.00000001
14	Yes	4	0.00000001	0.00000001
15	Yes	4	0.00000001	0.00000001
16	Yes	4	0.00000001	0.00000001
17	Yes	4	0.00000001	0.00000001
18	Yes	4	0.00000001	0.00000001
19	Yes	4	0.00000001	0.00000083
20	Yes	4	0.00000001	0.00000113
21	Yes	4	0.00000001	0.00000134
22	Yes	4	0.00000001	0.00000123
23	Yes	4	0.00000001	0.00000134
24	Yes	4	0.00000001	0.00000086
25	Yes	4	0.00000001	0.00000101
26	Yes	4	0.00000001	0.00000126
27	Yes	4	0.00000001	0.00000120
28	Yes	4	0.00000001	0.00000112
29	Yes	4	0.00000001	0.00000099
30	Yes	4	0.00000001	0.00000098
31	Yes	4	0.00000001	0.00000134
32	Yes	4	0.00000001	0.00000120
33	Yes	4	0.00000001	0.00000123
34	Yes	4	0.00000001	0.00000125
35	Yes	4	0.00000001	0.00000001
36	Yes	4	0.00000001	0.00000001
37	Yes	4	0.00000001	0.00000001
38	Yes	4	0.00000001	0.00000001
39	Yes	4	0.00000001	0.00000001
40	Yes	4	0.00000001	0.00000001
41	Yes	4	0.00000001	0.00000001
42	Yes	4	0.00000001	0.00000001
43	Yes	4	0.00000001	0.00000001
44	Yes	4	0.00000001	0.00000001
45	Yes	4	0.00000001	0.00000001
46	Yes	4	0.00000001	0.00000001
47	Yes	4	0.00000001	0.00000001
48	Yes	4	0.00000001	0.00000001
49	Yes	4	0.00000001	0.00000001
50	Yes	4	0.00000001	0.00000001

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	170 - 150	5.810	35	0.3308	0.0276
T2	150 - 140	4.437	35	0.3008	0.0342
T3	140 - 120	3.813	35	0.2800	0.0328
T4	120 - 100	2.717	35	0.2267	0.0190
T5	100 - 90	1.833	46	0.1796	0.0123
T6	90 - 80	1.471	46	0.1518	0.0104
T7	80 - 60	1.161	46	0.1313	0.0087

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	36 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T8	60 - 40	0.652	46	0.0971	0.0063
T9	40 - 20	0.294	46	0.0586	0.0040
T10	20 - 0	0.087	46	0.0267	0.0020

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
183.00	101-90-08-0-01	35	5.810	0.3308	0.0276	87322
179.75	15' Mount Pipe	35	5.810	0.3308	0.0276	87322
178.00	3" Dia 20' Omni	35	5.810	0.3308	0.0276	87322
175.00	2.5" x 14' Omni	35	5.810	0.3308	0.0276	87322
174.00	1.5" x 12' Omni	35	5.810	0.3308	0.0276	87322
170.00	APXVSP18-C-A20	35	5.810	0.3308	0.0276	87322
168.00	HPD2-4.7	35	5.669	0.3281	0.0285	87322
159.50	APXV18-206517S-C w/ mounting hardware	35	5.075	0.3162	0.0320	41582
158.50	SC420-HF1LDF	35	5.007	0.3147	0.0323	37966
144.00	3" Dia 20' Omni	35	4.056	0.2890	0.0340	23165
141.00	2" Dia 15' Omni	35	3.873	0.2824	0.0332	23624
139.00	1.5" x 10' Omni	35	3.753	0.2776	0.0324	23769
138.50	9' Whip	35	3.724	0.2764	0.0321	23780
134.00	VHLP2.5-180	35	3.463	0.2646	0.0294	23648
125.50	PIROD 10' Lightweight T-Frame	35	2.998	0.2412	0.0229	23279
115.00	(2) TMA (shielded)	46	2.477	0.2149	0.0163	22716
101.00	BXA-171063-12BF	46	1.872	0.1822	0.0125	21889
87.00	3"x2"x22" Panel	46	1.373	0.1448	0.0098	24873
84.50	TMA	46	1.295	0.1396	0.0094	27539
83.50	3' Stand-off	46	1.265	0.1377	0.0093	28768
83.00	3' Dish	46	1.249	0.1367	0.0092	29395
82.50	TMA	46	1.234	0.1358	0.0091	30019
80.00	3"x2"x22" Panel	46	1.161	0.1313	0.0087	32680
30.00	Camera	46	0.172	0.0416	0.0029	32544
24.00	PC9013N	46	0.116	0.0325	0.0024	33089

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	170 - 150	19.947	19	1.1049	0.1169
T2	150 - 140	15.354	19	1.0169	0.1327
T3	140 - 120	13.236	19	0.9544	0.1228
T4	120 - 100	9.475	30	0.7837	0.0748
T5	100 - 90	6.400	30	0.6247	0.0481
T6	90 - 80	5.138	30	0.5296	0.0397
T7	80 - 60	4.051	30	0.4588	0.0325
T8	60 - 40	2.271	30	0.3397	0.0220
T9	40 - 20	1.020	30	0.2048	0.0131
T10	20 - 0	0.297	30	0.0930	0.0063

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 37 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
183.00	101-90-08-0-01	19	19.947	1.1049	0.1169	30304
179.75	15' Mount Pipe	19	19.947	1.1049	0.1169	30304
178.00	3" Dia 20' Omni	19	19.947	1.1049	0.1169	30304
175.00	2.5" x 14' Omni	19	19.947	1.1049	0.1169	30304
174.00	1.5" x 12' Omni	19	19.947	1.1049	0.1169	30304
170.00	APXVSP18-C-A20	19	19.947	1.1049	0.1169	30304
168.00	HPD2-4.7	19	19.478	1.0970	0.1195	30304
159.50	APXV18-206517S-C w/ mounting hardware	19	17.497	1.0623	0.1291	14430
158.50	SC420-HF1LDF	19	17.267	1.0579	0.1299	13176
144.00	3" Dia 20' Omni	19	14.065	0.9819	0.1286	7900
141.00	2" Dia 15' Omni	19	13.441	0.9616	0.1245	7916
139.00	1.5" x 10' Omni	19	13.033	0.9469	0.1209	7870
138.50	9' Whip	19	12.932	0.9430	0.1200	7852
134.00	VHLP2.5-180	19	12.038	0.9061	0.1099	7624
125.50	PiROD 10' Lightweight T-Frame	30	10.444	0.8309	0.0879	7183
115.00	(2) TMA (shielded)	30	8.640	0.7445	0.0655	6766
101.00	BXA-171063-12BF	30	6.536	0.6339	0.0490	6387
87.00	3"x2"x22" Panel	30	4.795	0.5056	0.0374	7236
84.50	TMA	30	4.521	0.4877	0.0356	7973
83.50	3' Stand-off	30	4.414	0.4810	0.0349	8310
83.00	3' Dish	30	4.361	0.4777	0.0345	8481
82.50	TMA	30	4.309	0.4745	0.0342	8651
80.00	3"x2"x22" Panel	30	4.051	0.4588	0.0325	9370
30.00	Camera	30	0.593	0.1453	0.0095	9251
24.00	PC9013N	30	0.400	0.1132	0.0076	9401

Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria
T1	170	Diagonal	A325N	0.6250	1	3.50	6.44	0.543 ✓	1.333	Bolt Shear
T2	150	Leg	A325N	1.0000	6	5.91	34.56	0.171 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	4.94	8.16	0.606 ✓	1.333	Member Bearing
		Top Girt	A325N	1.0000	1	0.43	8.16	0.052 ✓	1.333	Member Bearing
T3	140	Leg	A325N	1.0000	6	8.66	34.56	0.251 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	9.10	8.16	1.116 ✓	1.333	Member Bearing
T4	120	Leg	A325N	1.0000	6	15.53	34.56	0.449 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	11.57	10.88	1.064 ✓	1.333	Member Bearing
		Mid Girt	A325N	1.0000	1	3.95	8.16	0.484 ✓	1.333	Member Bearing
T5	100	Leg	A325N	1.0000	6	24.28	34.56	0.702 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	13.51	13.59	0.994 ✓	1.333	Member Bearing
T6	90	Leg	A325N	1.0000	6	28.99	34.56	0.839 ✓	1.333	Bolt Tension

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	38 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria
T7	80	Diagonal	A325N	1.0000	1	13.40	13.59	0.986 ✓	1.333	Member Bearing
		Leg	A325N	1.0000	6	33.39	34.56	0.966 ✓	1.333	Bolt Tension
T8	60	Diagonal	A325N	1.0000	1	14.18	16.49	0.860 ✓	1.333	Bolt Shear
		Leg	A325N	1.2500	6	41.83	54.00	0.775 ✓	1.333	Bolt Tension
T9	40	Diagonal	A325N	1.2500	1	13.89	16.99	0.818 ✓	1.333	Member Bearing
		Leg	A325N	1.2500	6	49.53	54.00	0.917 ✓	1.333	Bolt Tension
T10	20	Diagonal	A325N	1.2500	1	15.14	20.39	0.742 ✓	1.333	Member Bearing
		Diagonal	A325N	1.2500	1	18.83	16.99	1.108 ✓	1.333	Member Bearing

Compression Checks

Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	1 3/4	20.00	2.49	68.3 K=1.00	21.253	2.4053	-36.50	51.12	0.714 ✓
T2	150 - 140	Pirod 105244	10.02	10.02	45.4 K=1.00	25.051	3.6816	-42.40	92.23	0.460 ✓
T3	140 - 120	Pirod 105216	20.03	10.02	45.4 K=1.00	25.051	3.6816	-85.15	92.23	0.923 ✓
T4	120 - 100	Pirod 105217	20.03	10.02	37.8 K=1.00	26.132	5.3014	-139.22	138.54	1.005 ✓
T5	100 - 90	Pirod 105217	10.02	10.02	37.8 K=1.00	26.132	5.3014	-171.52	138.54	1.238 ✓
T6	90 - 80	Pirod 105217 reinf w/ 1" dia bar	10.02	10.02	31.5 K=1.00	26.968	7.6570	-203.13	206.49	0.984 ✓
T7	80 - 60	Pirod 105218 reinf w/ 1" dia bar	20.03	10.02	27.6 K=1.00	27.439	9.9280	-262.71	272.41	0.964 ✓
T8	60 - 40	Pirod 105219	20.03	10.02	28.4 K=1.00	27.351	9.4248	-318.51	257.78	1.236 ✓
T9	40 - 20	Pirod 105219 reinf w/ 1" dia bar	20.03	10.02	25.4 K=1.00	27.705	11.7803	-371.60	326.37	1.139 ✓
T10	20 - 0	Pirod 105220 reinf w/ 1" dia bar	20.03	10.02	24.3 K=1.00	27.824	14.2843	-421.49	397.44	1.061 ✓

Truss-Leg Diagonal Data

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 39 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Section No.	Elevation ft	Diagonal Size	L_d ft	Kl/r	F_a ksi	A in ²	Actual V K	Allow. V_a K	Stress Ratio
T2	150 - 140	0.5	1.48	121.0	10.193	0.1963	0.94	2.24	0.420
T3	140 - 120	0.5	1.48	121.0	10.133	0.1963	1.00	2.23	0.447
T4	120 - 100	0.5	1.47	120.0	10.279	0.1963	1.74	2.26	0.768
T5	100 - 90	0.5	1.47	120.0	10.279	0.1963	0.50	2.26	0.220
T6	90 - 80	0.5	1.46	118.8	10.452	0.1963	0.40	2.30	0.172
T7	80 - 60	0.5	1.44	117.8	10.592	0.1963	0.22	2.33	0.097
T8	60 - 40	0.625	1.45	94.4	13.671	0.3068	0.32	4.69	0.067
T9	40 - 20	0.625	1.44	93.7	16.133	0.3068	0.97	5.54	0.175
T10	20 - 0	0.625	1.42	93.0	13.845	0.3068	1.71	4.75	0.360

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L_u ft	Kl/r	F_a ksi	A in ²	Actual P K	Allow. P_o K	Ratio $\frac{P}{P_o}$
T1	170 - 150	7/8	5.59	2.71	111.6 K=0.75	12.001	0.6013	-3.50	7.22	0.485
T2	150 - 140	L2 1/2x2 1/2x3/16	11.42	5.02	121.8 K=1.00	10.024	0.9020	-5.49	9.04	0.607
T3	140 - 120	L3x3x3/16	12.50	5.67	115.6 K=1.01	10.799	1.0900	-9.47	11.77	0.804
T4	120 - 100	L3x3x1/4	13.80	6.37	129.1 K=1.00	8.961	1.4400	-12.59	12.90	0.976
T5	100 - 90	L3x3x5/16	14.50	6.74	137.3 K=1.00	7.920	1.7800	-13.76	14.10	0.976
T6	90 - 80	L3x3x5/16	15.24	7.12	145.1 K=1.00	7.090	1.7800	-13.78	12.62	1.092
T7	80 - 60	L3x3x3/8	16.80	7.92	162.0 K=1.00	5.691	2.1100	-14.18	12.01	1.181
T8	60 - 40	L3 1/2x3 1/2x5/16	18.45	8.73	151.8 K=1.00	6.480	2.0900	-14.24	13.54	1.051
T9	40 - 20	L3 1/2x3 1/2x3/8	19.30	9.17	160.1 K=1.00	5.825	2.4800	-14.77	14.45	1.023
T10	20 - 0	L4x4x5/16	21.03	10.04	152.3 K=1.00	6.437	2.4000	-16.66	15.45	1.079

Top Girt Design Data (Compression)

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 40 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	186.4 K=0.70	4.298	0.6013	-0.35	2.58	0.134 ✓
T2	150 - 140	L3x3x3/16	5.00	4.52	105.5 K=1.16	12.079	1.0900	-0.38	13.17	0.029 ✓

Bottom Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	186.4 K=0.70	4.298	0.6013	-0.16	2.58	0.060 ✓

Mid Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T4	120 - 100	L3x3x3/16	9.00	7.67	154.4 K=1.00	6.267	1.0900	-3.19	6.83	0.467 ✓

Tension Checks

Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	1 3/4	20.00	2.49	68.3	30.000	2.4053	30.17	72.16	0.418 ✓
T2	150 - 140	Pirod 105244	10.02	10.02	45.4	30.000	3.6816	35.47	110.45	0.321 ✓
T3	140 - 120	Pirod 105216	20.03	10.02	45.4	30.000	3.6816	71.11	110.45	0.644 ✓
T4	120 - 100	Pirod 105217	20.03	10.02	37.8	30.000	5.3014	117.90	159.04	0.741 ✓
T5	100 - 90	Pirod 105217	10.02	10.02	37.8	30.000	5.3014	145.66	159.04	0.916 ✓
T6	90 - 80	Pirod 105217 reinf w/ 1" dia bar	10.02	10.02	31.5	30.000	7.6570	173.97	229.71	0.757 ✓
T7	80 - 60	Pirod 105218 reinf w/ 1" dia bar	20.03	10.02	27.6	30.000	9.9280	226.31	297.84	0.760 ✓
T8	60 - 40	Pirod 105219	20.03	10.02	28.4	30.000	9.4248	274.16	282.74	0.970 ✓

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 41 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio $\frac{P}{P_a}$
T9	40 - 20	Pirod 105219 reinf w /1" dia bar	20.03	10.02	25.4	30.000	11.7803	316.80	353.41	0.896
T10	20 - 0	Pirod 105220 reinf w /1" dia bar	20.03	10.02	24.3	30.000	14.2843	353.13	428.53	0.824

Truss-Leg Diagonal Data

Section No.	Elevation ft	Diagonal Size	L _d ft	Kl/r	F _a ksi	A in ²	Actual V K	Allow. V _a K	Stress Ratio
T2	150 - 140	0.5	1.48	121.0	10.193	0.1963	0.94	2.24	0.420
T3	140 - 120	0.5	1.48	121.0	10.133	0.1963	1.00	2.23	0.447
T4	120 - 100	0.5	1.47	120.0	10.279	0.1963	1.74	2.26	0.768
T5	100 - 90	0.5	1.47	120.0	10.279	0.1963	0.50	2.26	0.220
T6	90 - 80	0.5	1.46	118.8	10.452	0.1963	0.40	2.30	0.172
T7	80 - 60	0.5	1.44	117.8	10.592	0.1963	0.22	2.33	0.097
T8	60 - 40	0.625	1.45	94.4	13.671	0.3068	0.32	4.69	0.067
T9	40 - 20	0.625	1.44	93.7	16.133	0.3068	0.97	5.54	0.175
T10	20 - 0	0.625	1.42	93.0	13.845	0.3068	1.71	4.75	0.360

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio $\frac{P}{P_a}$
T1	170 - 150	7/8	5.59	2.71	148.7	30.000	0.6013	3.44	18.04	0.191
T2	150 - 140	L2 1/2x2 1/2x3/16	11.42	5.02	80.1	21.600	0.9020	4.94	19.48	0.254
T3	140 - 120	L3x3x3/16	12.50	5.67	74.6	21.600	1.0900	9.10	23.54	0.387
T4	120 - 100	L3x3x1/4	13.80	6.37	84.3	21.600	1.4400	11.57	31.10	0.372
T5	100 - 90	L3x3x5/16	14.50	6.74	89.9	21.600	1.7800	13.51	38.45	0.351
T6	90 - 80	L3x3x5/16	15.24	7.12	94.9	21.600	1.7800	13.40	38.45	0.349

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 42 of 43
	Project VZ5-192 / Cromwell, CT Tower	Date 13:01:58 01/06/15
	Client Verizon Wireless	Designed by MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T7	80 - 60	L3x3x3/8	16.01	7.54	101.2	21.600	2.1100	13.80	45.58	0.303 ✓
T8	60 - 40	L3 1/2x3 1/2x5/16	18.45	8.73	99.2	21.600	2.0900	13.89	45.14	0.308 ✓
T9	40 - 20	L3 1/2x3 1/2x3/8	20.16	9.59	109.8	21.600	2.4800	15.14	53.57	0.283 ✓
T10	20 - 0	L4x4x5/16	21.92	10.48	103.3	21.600	2.4000	18.83	51.84	0.363 ✓

Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	266.3	30.000	0.6013	0.31	18.04	0.017 ✓
T2	150 - 140	L3x3x3/16	5.00	4.52	62.0	21.600	1.0900	0.43	23.54	0.018 ✓

Bottom Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	266.3	30.000	0.6013	0.15	18.04	0.008 ✓

Mid Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T4	120 - 100	L3x3x3/16	9.00	7.67	102.2	21.600	1.0900	3.95	23.54	0.168 ✓

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
T1	170 - 150	Leg	1 3/4	3	-36.50	68.14	53.6	Pass
T2	150 - 140	Leg	Pirod 105244	60	-42.40	122.94	34.5	Pass
T3	140 - 120	Leg	Pirod 105216	72	-85.15	122.94	69.3	Pass

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	43 of 43
	Project	VZ5-192 / Cromwell, CT Tower	Date	13:01:58 01/06/15
	Client	Verizon Wireless	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail	
T4	120 - 100	Leg	Pirod 105217	87	-139.22	184.67	75.4	Pass	
T5	100 - 90	Leg	Pirod 105217	105	-171.52	184.67	92.9	Pass	
T6	90 - 80	Leg	Pirod 105217 reinf w/ 1" dia bar	114	-203.13	275.26	73.8	Pass	
T7	80 - 60	Leg	Pirod 105218 reinf w/ 1" dia bar	123	-262.71	363.13	72.3	Pass	
T8	60 - 40	Leg	Pirod 105219	136	-318.51	343.62	92.7	Pass	
T9	40 - 20	Leg	Pirod 105219 reinf w/1" dia bar	151	-371.60	435.06	85.4	Pass	
T10	20 - 0	Leg	Pirod 105220 reinf w/ 1" dia bar	166	-421.49	529.79	79.6	Pass	
T1	170 - 150	Diagonal	7/8	12	-3.50	9.62	36.4	Pass	
T2	150 - 140	Diagonal	L2 1/2x2 1/2x3/16	69	-5.49	12.05	45.5	Pass	
T3	140 - 120	Diagonal	L3x3x3/16	78	-9.47	15.69	60.3	Pass	
T4	120 - 100	Diagonal	L3x3x1/4	96	-12.59	17.20	73.2	Pass	
T5	100 - 90	Diagonal	L3x3x5/16	111	-13.76	18.79	73.2	Pass	
T6	90 - 80	Diagonal	L3x3x5/16	120	-13.78	16.82	81.9	Pass	
T7	80 - 60	Diagonal	L3x3x3/8	129	-14.18	16.01	88.6	Pass	
T8	60 - 40	Diagonal	L3 1/2x3 1/2x5/16	144	-14.24	18.05	78.9	Pass	
T9	40 - 20	Diagonal	L3 1/2x3 1/2x3/8	165	-14.77	19.26	76.7	Pass	
T10	20 - 0	Diagonal	L4x4x5/16	179	-16.66	20.59	80.9	Pass	
T1	170 - 150	Top Girt	7/8	6	-0.35	3.45	10.1	Pass	
T2	150 - 140	Top Girt	L3x3x3/16	61	-0.38	17.55	2.1	Pass	
T1	170 - 150	Bottom Girt	7/8	8	-0.16	3.45	4.5	Pass	
T4	120 - 100	Mid Girt	L3x3x3/16	88	-3.19	9.11	35.1	Pass	
							Summary		
							Leg (T5)	92.9	Pass
							Diagonal (T7)	88.6	Pass
							Top Girt (T1)	10.1	Pass
							Bottom Girt (T1)	4.5	Pass
							Mid Girt (T4)	35.1	Pass
							Bolt Checks	83.7	Pass
							RATING =	92.9	Pass

ANCHOR BOLT EVALUATION

ANCHOR BOLT ANALYSIS

Input Data

Max Pier Reactions:

Uplift:	Uplift := 367-kips	<i>user input</i>
Shear:	Shear := 48-kips	<i>user input</i>
Compression:	Compression := 430-kips	<i>user input</i>

Anchor Bolt Data:

Use ASTM A687 Grade

Number of Anchor Bolts = N	$N_u := 6$	<i>user input</i>
Bolt Ultimate Strength:	$F_u := 150$ ksi	<i>user input</i>
Bolt Yield Strength:	$F_y := 105$ ksi	<i>user input</i>
Bolt Modulus:	$E := 29000$ ksi	<i>user input</i>
Thickness of Anchor Bolts	$D := 1.25$ in	<i>user input</i>
Threads per Inch:	$n := 7$	<i>user input</i>
Coefficient of Friction:	$\mu := 0.55$	<i>user input</i> (for baseplate with grout ASCE 10-97)

Anchor Bolt Area:

Gross Area of Bolt:

$$A_g := \frac{\pi}{4} \cdot D^2 \qquad A_g = 1.227 \cdot \text{in}^2$$

Net Area of Bolt:

$$A_n := \frac{\pi}{4} \cdot \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 \qquad A_n = 0.969 \cdot \text{in}^2$$

Check Tensile Forces:

Maximum Tensile Force (Gross Area):

$$\text{AllowableTension} := 1.33 \cdot (0.33 \cdot A_g \cdot F_u) \qquad \text{AllowableTension} = 80.8 \cdot \text{kips}$$

Note: 1.33 increase allowed per TIA/EIA

Maximum Tensile Force (Net Area):

$$F_{\text{net.area}} := 1.33 \cdot (0.60 \cdot A_n \cdot F_y) \qquad F_{\text{net.area}} = 81.2 \cdot \text{kips}$$

Note: 1.33 increase allowed per TIA/EIA

Applied Tension:

$$\text{MaxTension} := \frac{\text{Uplift}}{N} \qquad \text{MaxTension} = 61.2 \cdot \text{kips}$$

Check Stresses:

$$\frac{\text{MaxTension}}{F_{\text{net.area}}} = 0.75$$

$$\text{Condition1} := \text{if} \left(\frac{\text{MaxTension}}{F_{\text{net.area}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

$$\text{Condition1} = \text{"OK"}$$

Check Anchor Bolt Area:

Based on the ASCE 10-97 Design of Latticed Steel Transmission Structures

Required Area:

$$A_{s1} := \frac{\text{Uplift}}{F_y} + \frac{\text{Shear}}{\mu \cdot 0.85 \cdot F_y} \quad A_{s1} = 4.5 \cdot \text{in}^2$$

$$A_{s2} := \left| \frac{\text{Shear} - (0.3 \cdot \text{Compression})}{\mu \cdot 0.85 \cdot F_y} \right| \quad A_{s2} = 1.7 \cdot \text{in}^2$$

Provided Area:

$$A_{s\text{provided}} := A_n \cdot N \quad A_{s\text{provided}} = 5.8 \cdot \text{in}^2$$

$$\text{Condition2} := \text{if} \left(\frac{A_{s1}}{A_{s\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s1}}{A_{s\text{provided}}} = 0.77$$

Condition2 = "OK"

$$\text{Condition3} := \text{if} \left(\frac{A_{s2}}{A_{s\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s2}}{A_{s\text{provided}}} = 0.28$$

Condition3 = "OK"

FOUNDATION EVALUATION

FOUNDATION ANALYSIS

Input Data

Maximum Pier Reactions:

Compression: $C_t := 430 \cdot \text{kips}$ *user input*
 Uplift: $U_t := 367 \cdot \text{kips}$ *user input*

Material Properties:

Unit Weight of Concrete: $\gamma_c := 150 \text{pcf}$ *user input*
 Unit Weight of Water: $\gamma_w := 62.4 \text{pcf}$ *user input*
 Unit Weight of Soil: $\gamma_s := 100 \text{pcf}$ *user input*

Foundation Dimensions:

Drilled Caisson Length: $C_{\text{Length}} := 41.5 \cdot \text{ft}$ *user input*
 Diameter of Pier: $d_p := 5.5 \text{ft}$ *user input*
 Extension of Pier Above Grade: $L_{\text{pag}} := 0.5 \text{ft}$ *user input*

Allowable Soil Bearing Capacity (Allowable Bearing Pressure at Depth 41') $q_s := 6 \cdot \text{ksf}$ *user input*
 Water Table Below Grade: $Wd := 41 \cdot \text{ft}$ *user input*

Additional Concrete $\text{Conc}_{\text{addl}} := 5 \text{ft} \cdot \left(13 \text{ft} \cdot 13 \text{ft} - \frac{\pi \cdot d_p^2}{4} \right)$
 $\text{Conc}_{\text{addl}} = 726.2 \cdot \text{ft}^3$

Average Allowable Shear: $fl := 859 \cdot \text{psf}$ *user input*
 Depth Neglected for Skin Friction at Top: $\text{Depthunbond} := 4 \cdot \text{ft}$ *user input*

Foundation reinforcement per drawings by Tectonic, dated May 5, 2004

Loading:

$$\text{TotalDownload} := C_t + \pi \cdot \frac{d_p^2}{4} \cdot [L_{\text{pag}} \cdot \gamma_c + [\gamma_c \cdot (C_{\text{Length}} - L_{\text{pag}})]]$$

TotalDownload = 577.9 kips

$$\text{PierWeight} := \pi \cdot \frac{d_p^2}{4} \cdot [(Wd + L_{\text{pag}}) \cdot \gamma_c + (C_{\text{Length}} - Wd - L_{\text{pag}}) \cdot (\gamma_c - \gamma_w)] + \text{Conc}_{\text{addl}} \cdot \gamma_c$$

PierWeight = 256.8 kips

$$\text{SoilShear} := \pi \cdot d_p \cdot [fl \cdot (C_{\text{Length}} - \text{Depthunbond})]$$

SoilShear = 556.6 kips

Job	170' Self-Supporting Lattice Tower - Cromwell, CT	Project No.	VZ5-192	Sheet	2 of 2
Description	Drilled Pier Caisson Evaluation	Computed by	MCD	Date	01/06/15
		Checked by		Date	

Compression Capacity:

$$\text{TotalDownLoadCapacity} := \text{SoilShear} + q_s \left(\pi \cdot \frac{d_p^2}{4} \right)$$

$$\text{TotalDownLoadCapacity} = 699.1 \cdot \text{kips}$$

$$\text{CheckDownLoadCapacity} := \text{if}(\text{TotalDownLoad} < \text{TotalDownLoadCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckDownLoadCapacity} = \text{"Okay"}$$

Tension Capacity:

$$\text{TotalUpLiftCapacity} := \text{SoilShear} + \text{PierWeight}$$

$$\text{TotalUpLiftCapacity} = 813.4 \cdot \text{kips}$$

$$\text{CheckUpLiftCapacity} := \text{if}(U_t < \text{TotalUpLiftCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckUpLiftCapacity} = \text{"Okay"}$$

$$\text{SafetyFactor}_{\text{provided}} := \frac{\text{TotalUpLiftCapacity}}{U_t}$$

$$\text{SafetyFactor}_{\text{provided}} = 2.22$$

Check Cone Failure:

$$\text{ConeFailureCapacity} := \frac{[(C_{\text{Length}} - L_{\text{pag}}) \cdot \tan(30\text{deg}) \cdot 2 + d_p]^2 \cdot \pi \cdot C_{\text{Length}} - L_{\text{pag}}}{4 \cdot 3} \cdot \gamma_s$$

$$\text{ConeFailureCapacity} = 2997.25 \cdot \text{kips}$$

$$\text{CheckConeFailureCapacity} := \text{if}(U_t < \text{ConeFailureCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckConeFailureCapacity} = \text{"Okay"}$$

$$\text{ConeSafetyFactor}_{\text{provided}} := \frac{\text{ConeFailureCapacity}}{U_t}$$

$$\text{ConeSafetyFactor}_{\text{provided}} = 8.17$$

ATTACHMENT 4

DETAILED STRUCTURAL ANALYSIS AND REINFORCEMENT OF AN EXISTING 170' SELF SUPPORTING LATTICE TOWER AND FOUNDATION FOR PROPOSED ANTENNA ARRANGEMENTS

Site ID: (Sprint) CT60XC931
(T-Mobile) CT11059C
Site Name: (Sprint) Cromwell - Route 372
(T-Mobile) Rocky Hill / I-91 / X23
Site Address: 179 Shunpike Road
Cromwell, CT

prepared for



Transcend Wireless
10 Industrial Ave.
Suite 3
Mahwah, NJ. 07430



EBI Consulting
21 B Street
Burlington, MA 01803

prepared by



URS CORPORATION
500 ENTERPRISE DRIVE, SUITE 3B
ROCKY HILL, CT 06067
TEL. 860-529-8882

36931260.00000
TWS-027 Rev. 1

September 23, 2014

TABLE OF CONTENTS

- 1. EXECUTIVE SUMMARY**
- 2. INTRODUCTION**
- 3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS**
- 4. FINDINGS AND EVALUATION**
- 5. CONCLUSIONS AND RECOMMENDATIONS**
- 6. DRAWINGS AND DATA**
 - **TOWER REINFORCEMENT DRAWING SK-1**
 - **TNX TOWER INPUT / OUTPUT SUMMARY**
 - **TNX TOWER FEEDLINE DISTRIBUTION**
 - **TNX TOWER FEEDLINE PLAN**
 - **TNX TOWER DETAILED OUTPUT**
 - **ANCHOR BOLT ANALYSIS**
 - **FOUNDATION ANALYSIS**

1. EXECUTIVE SUMMARY

This report summarizes the structural analysis of the existing 170' self supporting lattice tower located at 179 Shunpike Road in Cromwell, Connecticut. The analysis was conducted in accordance with the 2005 Connecticut State Building Code which requires a three second gust wind speed of 100 mph which converts to an 80 mph fastest mile per 2003 IBC (Table 1609.3.1) and the TIA/EIA-222-F standard for a wind velocity of 85 mph (fastest mile). The wind speed from the Connecticut State Building Code governs the design at 85 mph (fastest mile) and 74 mph (fastest mile) concurrent with ½ " ice. The antenna loading considered in the analysis consists of all existing and proposed antennas, transmission lines, and ancillary items as outlined in the Introduction Section of this report.

The proposed Sprint and T-Mobile antenna modifications are listed below:

Proposed Antenna and Mount	Carrier	Antenna Center Elevation
Install:		
(3) RFS APXV9TM14-ALU-I20 Panel Antennas	Sprint (Proposed)	@ 170'
(3) TD-RRH8x20-25 RRH Units		
(1) 1 1/4" Hybrid Cable		
(27) 8' Jumper Cables		
(3) 8' AISG Cables		
Install:		
(3) Commscope LNX-6515DS-VTM Panel Antennas	T-Mobile (Proposed)	@ 125'
(3) Ericsson RRUS_11 RRH Unit		
(3) 6' Antenna Pipe Mount		

The results of an initial analysis indicated the tower structure did not have sufficient capacity to support the proposed loadings without modification. The required modifications are shown in SK-1. **Once the modifications are performed, the tower, anchor bolts, and foundation are considered structurally adequate with the wind loading classification specified above and all the existing and proposed antenna loading. No installation of new antennas or equipment shall occur until the modifications have been completed.**

This analysis is based on:

- 1) The tower structure's theoretical capacity, not including any assessment of the condition of the tower.
- 2) Tower geometry, structural member sizes, and Foundation information taken from a tower report prepared by PIROD Inc., ENG. File No. A-116398, dated November 18, 1999.
- 3) Foundation modification drawings prepared by Tectonic, dated May 5, 2004.
- 4) Structural analysis and reinforcement performed by URS Corp. on behalf of Sprint and T-Mobile, project number 36922436, signed and sealed on September 9, 2013.
- 5) Structural analysis performed by URS Corp. on behalf of Verizon Wireless, project number VZ5-178 / 36917427, signed and sealed on August 12, 2014.
- 6) Structural analysis performed by URS Corp., on behalf of Sprint, project number TWS-027 / 36931260, signed and sealed on August 22, 2014.
- 7) T-Mobile RFDS dated July 17, 2014.
- 8) Previous structural analysis performed by URS Corporation, on behalf of T-Mobile, project number EBI-002 / 36931289, signed and sealed August 29, 2014.
- 9) Proposed additional antenna and mount configuration as specified in Section 2 of this report.


1. EXECUTIVE SUMMARY (continued)

This report is only valid as per the assumptions and data utilized in this report for antenna inventory, mounts and associated cables. The user of this report shall field verify the assumption of the antenna and mount configuration as well as the physical condition of the tower and connections. Notify the engineer in writing immediately if any of the information in this report is found to be other than specified.

If you should have any questions, please call.

Sincerely,

URS Corporation



Richard A. Sambor, P.E.
Senior Structural Engineer
RAS/mcd



2. INTRODUCTION

The subject tower is located at 179 Shunpike Road in Cromwell, Connecticut. The structure is a 170' self supporting lattice tower designed and manufactured by PIROD Inc.

The current inventory with proposed modification is summarized in the table below:

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) Tx Rx 101-90-08 antenna	Town (existing)	15' Mast pipe on 9 Arm Halo Mount	183'	(1) 7/8"
(1) 8 Bay Dipole (3" dia x 20')	Town (existing)	9 Arm Halo Mount	178'	(1) 7/8"
(1) 2 1/2" dia x 20' Whip	Town (existing)	9 Arm Halo Mount	178'	(1) 1 1/2"
(3) 2 1/2" dia x 15' Whip	Town (existing)	9 Arm Halo Mount	175'	(3) 7/8"
1 1/2" dia x 12' Whip	Town (existing)	9 Arm Halo Mount	174'	(1) 7/8"
(3) RFS APXV9TM14-ALU-I20 Panel Antennas (3) TD-RRH8x20-25 RRH Units	Sprint (Proposed)	See Mount Below	170'	(1) 1 1/4" Hybrid Cable (27) 8' Jumper Cables (3) 8' AISG Cables
(3) RFS APXVSP18-C-A20 Antennas (3) 1900 MHz RRH Units (3) 800 MHz RRH Units (3) 800 MHz Filters	Sprint (existing)	9 Arm Halo Mount	170'	(3) RFS HB114-1-0804-MSF Hybrid Cables
(1) Radiowaves HPD2-4.7 w/ Radome (1) Cambium PTP49600 Antenna	CPD (existing)	9 Arm Halo Mount	168'	(1) WB3176A – Copper Clad Outdoor Cable (2) 4' long 1/2" Jumper Cables
(1) SU-RA-HP-2.4 (1' x 1' Antenna)	Town (existing)	9 Arm Halo Mount	168'	(1) 3/8"
(3) APXV18-206517S	Unknown (existing)	Leg Mount	159'-6"	(6) 1 5/8"
(1) Sinclair SC420-HF1LDF Omni	CPD (existing)	Pipe mount	158'-6"	(1) 1 5/8" Low Density Foam Cable
(2) 3" dia x 20' Whip	Town (existing)	20' Platform	144'	(2) 7/8"
(1) 2 1/2" x 20' Whip	Town (existing)	20' Platform	144'	(1) 1/2"
2" dia x 15' Whip	Town (existing)	20' Platform	141'	(1) 1/2"
(1) 1.5" dia x 10' Whip	Town (existing)	20' Platform	139'	(1) 1/2"
(1) 3.5" dia x 9' Whip	Town (existing)	20' Platform	138'-6"	---
(3) Argus LLPX310R antennas (3) Samsung Remote Radio Heads U-RAS	Clearwire (existing)	20' Platform	134'	(6) CAT 5 cable

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(3) Andrew VHLP2.5 dish (2.5' dia.) (1) Andrew VHLP2 dish (2' dia.) (Gamma Sector)	Clearwire (existing)	20' Platform	134'	(4) 1/2"
(3) Commscope LNX-6515DS-VTM Panel Antennas (3) Ericsson RRUS_11 RRH Unit	T-Mobile (Proposed)	(3) Antenna Pipes attached with below	125'	See Below Cables
(6) Ericsson AIR21 B4A B2P Antennas (3) Twin PCS TMAs	T-Mobile (existing)	(3) Existing T-Frames	125'	(12) 1 5/8" (1) 1-5/8" Hybrid Cable
(6) Powerwave 7770 (12) TMA's (3) KMW AM-X-CD-16-65-00T-RET (6) RRU (1) Surge Suppressor	AT&T (existing)	(3) T-Frames	115'	(12) 1 5/8" (3) Optic Fiber & (6) DC Cables (Located within 3" dia Flex Conduit)
(1) HBX-6517DS-VTM_04DT_2110 Panel Antenna (Alpha Sector) (2) HBX-6517DS-VTM_02DT_2110 Panel Antennas (Beta & Gamma Sectors) (3) AWS RRH Units (1) DB-T1-6Z-8AB-0Z Distribution Box (1) LNX-6514DS-VTM_03DT_0850 Panel Antenna (Alpha Sector) (1) LNX-6514DS-VTM_04DT_0850 Panel Antenna (Beta Sector) (1) LNX-6514DS-VTM_05DT_0850 Panel Antenna (Gamma Sector)	Verizon (existing)	(3) T-Frames (PiROD part #800093)	101'	(1) 1 5/8" F.O Cable (12) 1 5/8"
(2) SWCP 2x5514 antennas (Alpha & Gamma Sector) (1) BXA-70063-6CF-2 antenna (Beta Sector) (3) BXA-171063-12BF_2 antennas (6) FD9R6004/2C-3L Diplexers				
(1) 3" x 2" x 22" Panel (1) TMA	AT&T (existing)	Pipe Mount	87'	(2) CAT 5

Antenna Type	Carrier	Mount	Antenna Centerline Elevation	Cable
(1) 3' Dish (1) TMA	AT&T (existing)	3' Stand-off	83'	(2) CAT 5
(1) 3" x 2" x 22" Panel (1) TMA	AT&T (existing)	3' Stand-off	80'	(2) CAT 5
(1) Camera	Unknown (existing)	Leg Mounted	30'	(2) 1/2" (estimated from photographs)
(1) 3' Yagi	Unknown (existing)	Leg Mounted	24'	(1) 1/2"

This structural analysis of the communications tower was performed by URS Corporation (URS) for Sprint and T-Mobile. The purpose of this analysis was to investigate the structural integrity of the reinforced tower with its existing and proposed antenna loads. This analysis was conducted to evaluate stress on the tower and the effect of forces to the foundation of the tower resulting from existing and proposed antenna arrangements.

3. ANALYSIS METHODOLOGY AND LOADING CONDITIONS

The structural analysis was done in accordance with the Connecticut State Building Code, TIA/EIA-222-F - Structural Standard for Steel Antenna Towers and Antenna Supporting Structures, and the American Institute of Steel Construction (AISC) Manual of Steel Construction – Allowable Stress Design (ASD).

The analysis was conducted using TNX Tower 6.1.3.1. Two load conditions were evaluated as shown below which were compared to allowable stresses according to AISC and TIA/EIA.

Basic Wind Speed:

- Middlesex County; v = 85 mph (fastest mile) [Section 16 of TIA/EIA-222-F-1996]
- Cromwell; v = 100mph (3 second gust) [Appendix K, 2005 Connecticut State Building Code Supplement]
equivalent to 80mph (fastest mile)

Loading Cases:

Load Condition 1 = 85 mph (fastest mile) Wind Load (without ice) + Tower Dead Load
Load Condition 2 = 74 mph (fastest mile) Wind Load (with ice) + Ice Load + Tower Dead Load

Please note that wind pressure is a function of velocity squared. Under Load Condition 2, a 25 percent reduction in wind pressure is allowed by code to account for the unlikelihood of the full wind pressure and ice load occurring at the same time. The same results may be achieved by utilizing a lower wind pressure without taking the 25 percent reduction, as shown above.

The TIA/EIA standard permits a one-third increase in allowable stresses for towers and monopoles less than 700 feet tall. For the purposes of this analysis, in computing the load capacity the allowable stresses of the tower members were increased by one-third.

4. FINDINGS AND EVALUATION

The combined axial and bending stresses on the tower structure were evaluated to compare with the allowable stress in accordance with AISC. The results of an initial analysis indicated that the tower structure required modification. The required modifications are shown in SK-1 located in Section 6 of this report. This analysis indicated that once these modifications are performed, the tower, anchor bolts and foundation are considered structurally adequate with the wind load classification specified above and the proposed antenna loading. The table below summarizes the critical members for each tower component.

TABLE 1: Tower Component Stress vs. Capacity Summary:

Component/ (Section No.)	Existing Component Size	Controlling Component/Elevation	Percent Capacity	Pass/Fail
Tower Leg (T5)	PiROD Truss Leg	Compression 90'-100'	92.4 %	Pass
Diagonal (T7)	L3x3x3/8	Compression 60'-80'	88.5 %	Pass
Top Girt (T1)	7/8" SR	Compression 150'-170'	9.5 %	Pass
Bottom Girt (T1)	7/8" SR	Compression 150'-170'	4.4 %	Pass
Mid Girt (T4)	L3x3x3/16	Compression 100'-120'	34.8 %	Pass
Bolt Checks				
Tower Bolts	(1) 1" A325N Bolt / 140'	Member Bearing on Bolt	83.5 %	Pass
Anchor Bolts	(6) 1-1/4"	Tension	77.0 %	Pass

TABLE 2: Foundation Summary

Foundation	Component	Stress (% capacity/FOS)	Pass/Fail	Comments:
Previously Modified Drilled Concrete Caisson	Uplift	89.9 %/2.22	Pass	Min. F.O.S of 2.0 req'd per IBC 2003 Section 3108.4.2

5. CONCLUSIONS AND RECOMMENDATIONS

The results of an initial analysis indicated the tower structure did not have sufficient capacity to support the proposed loadings without modification. The required modifications are shown in SK-1. **Once the modifications are performed, the tower, anchor bolts, and foundation are considered structurally adequate with the wind loading classification specified above and all the existing and proposed antenna loading. No installation of new antennas or equipment shall occur until the modification have been completed.**

Limitations/Assumptions:

This report is based on the following:

1. Tower inventory as listed in this report.
2. Tower is properly installed and maintained.
3. All members are as specified in the original design documents and are in good condition.
4. All required members are in place.
5. All bolts are in place and are properly tightened.
6. Tower is in plumb condition.
7. All member protective coatings are in good condition.
8. All tower members were properly designed, detailed, fabricated, and installed and have been properly maintained since erection.
9. Foundations were properly constructed to support original design loads as specified in the original design documents.
10. All coaxial cable is installed as specified in Section 6 of this report.

URS is not responsible for any changes/alterations completed prior to or hereafter in which URS is not or was not directly involved. Changes/alterations include but are not limited to:

- A. Adding antennas
- B. Removing/replacing antennas
- C. Adding coaxial cables

URS hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations, and conclusions are based upon information contained and set forth herein. If you are aware of any information which conflicts with that which is contained herein, or you are aware of any defects arising from original design, material, fabrication, or erection deficiencies, you should disregard this report and immediately contact URS. URS disclaims all liability for any representation, recommendation, or conclusion not expressly stated herein.

Ongoing and Periodic Inspection and Maintenance:

After the Contractor has successfully completed the installation and the work has been accepted, the owner will be responsible for the ongoing and periodic inspection and maintenance of the tower.

The owner shall refer to TIA/EIA-222-F for recommendations for maintenance and inspection. The frequency of the inspection and maintenance intervals is to be determined by the owner based upon actual site and environmental conditions. It is recommended that a complete and thorough inspection of the entire tower structural system be performed at least yearly and more frequently as conditions warrant. According to TIA/EIA-222-F section 14.1, Note 1: It is recommended that the structure be inspected after severe wind and/or ice storms or other extreme loading conditions.

6. DRAWINGS AND DATA

TOWER REINFORCEMENT DRAWING SK-1

ASK FOR THE
URS CORPORATION AES
500 ENTERPRISE DRIVE
ROCKY HILL, CONNECTICUT
1-860-528-8882

Sprint
10 N. STATE STREET, SUITE 1
MIDDLEBURY, VT 05750

T-Mobile
330 COLONIAL AVENUE
STURBURY, CT 06370



ASCE PROJECT NUMBER	DATE BY
98312802 (TWS-023)	AWJ
DATE REVISION FOR	
1 9/27/14 106-07-02	

RELIEVE BY

CT160XC831
CT11059C

179 SHUNPIKE ROAD
CROMWELL, CT

SHEET NO.

REINFORCEMENT
DETAILS & NOTES

SHEET NUMBER
SK-1

STRUCTURAL NOTES

TOWER DESIGN INTENT:
THIS TOWER IS DESIGNED AND REINFORCED IN ACCORDANCE WITH THE 2005 CONNECTICUT STATE BUILDING CODE, THE INTERNATIONAL BUILDING CODE (LATEST EDITION), AND THE 2005 INTERNATIONAL CODE OF BULLETIN. ALLOWABLE STEEL STRESSES PER ASCE 9th EDITION.

MATERIAL SPECIFICATIONS FOR REINFORCEMENT OF TOWER:
 STRUCTURAL STEEL PLATES, ANGLES
 ASTM A36
 ASTM A572 GRADE 50
 SOLID ROUND (S.R.)
 ASTM A53 GRADE B
 THREADED BOLTS
 F-46, ISI
 WELDING ELECTRODES
 ASTM E 70

SHOP AND ERECTION DRAWINGS SHALL BE SUBMITTED FOR ALL STRUCTURAL STEEL WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. SUBMIT 4 SETS OF PRINTS TO THE ARCHITECT FOR REVIEW. THE CONTRACTOR OF PROVIDING SAME.

STRUCTURAL STEEL SHALL CONFORM TO THE CURRENT "AISC" SPECIFICATION FOR THE DESIGN, FABRICATION, AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS, AND THE "AISC CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES".

ALL WELDING SHALL BE DONE BY A CERTIFIED WELDER IN ACCORDANCE WITH A.W.S. STANDARDS.

CONNECTIONS SHALL CONFORM TO ALL REQUIREMENTS OF THE "AISC" SPECIFICATION FOR THE DESIGN, FABRICATION, AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS, LATEST EDITION, AND THE "SPECIFICATION FOR STRUCTURAL STEEL JOINTS USING ASTM A325 OR A490 BOLTS".

BOLT HOLES SHALL BE PUNCHED OR DRILLED. FLAME CUT HOLES ARE NOT ACCEPTABLE.

ALL A-325/A490 BOLTS ARE TO BE TIGHTENED TO A SNUG TIGHT CONDITION AS DEFINED BY AISC SPECIFICATION. USE LOCK NUT OR LOCKING DEVICE TO MATCH EXISTING.

ALL WELDING SHALL BE DONE USING ELECTRIC ARC WELDING. WELDING SHALL CONFORM TO AISC AND AWS D1.1 WELDING CODE REQUIREMENTS. WELDED JOINTS SHALL BE FIELD WELDED UNLESS OTHERWISE SPECIFIED. MANUAL STEEL CONSTRUCTION, 9TH EDITION, AT THE COMPLETION ALL WELDING, ALL DAMAGE TO GALVANIZED COATING SHALL BE REPAIRED.

USE PRECAUTIONS & PROCEDURES PER AWS D1.1 WHEN WELDING GALVANIZED METALS.

TOUCH-UP ALL DAMAGED GALVANIZED STEEL WITH APPROVED COLD ZINC, "GALVANOX", "TORY GALT", "ZINC-IT", OR EQUIVALENT. ALL REPAIRS SHALL BE IN ACCORDANCE WITH MANUFACTURERS' GUIDELINES. TOUCH-UP DAMAGED NON GALVANIZED STEEL WITH SAME PAINT APPLIED IN SHOP OR FIELD.

ALL STEEL WORK SHALL BE GALVANIZED AND IN ACCORDANCE WITH THE SPECIFICATION ASTM A123 UNLESS OTHERWISE NOTED. (AFTER FABRICATION)

COMPLETION OF STRUCTURAL STEEL WORK WITHOUT NOTIFYING THE ENGINEER OF ANY DISCREPANCIES WILL BE CONSIDERED ACCEPTANCE OF PRECEDING WORK.


SPECIAL INSPECTIONS REQUIRED PER THE 2005 CONNECTICUT STATE BUILDING CODE FOR STRUCTURAL STEEL WORK.

INSPECTION AND TESTING OF ALL WELDING AND HIGH STRENGTH BOLTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING AGENCY AS REQUIRED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. THE INSPECTOR SHALL BE PRESENT AT THE TIME OF INSPECTION. INSPECTIONS SHALL NOT BE LESS THAN 20% OF THE BOLTS AND NOT LESS THAN TWO BOLTS, SELECTED AT RANDOM, IN EACH CONNECTION.

FOUR COPIES OF ALL INSPECTION TEST REPORTS SHALL BE SUBMITTED TO THE ENGINEER WITHIN TEN (10) WORKING DAYS OF THE DATE OF INSPECTION.

REINFORCEMENT NOTES:
 EXISTING DIMENSIONS OF THE TOWER STRUCTURE WERE OBTAINED FROM MANUFACTURER'S ORIGINAL DESIGN DOCUMENTS, PREPARED BY PEROT INC. ENG. FILE NO. A-116398, DATED NOVEMBER 16, 1999 AND ARE NOT GUARANTEED. CONTRACTOR SHALL TAKE FIELD MEASUREMENTS NECESSARY TO ASSURE PROPER FIT OF ALL FINISHED WORK.
 CONTRACTOR SHALL VISIT THE SITE PRIOR TO THE START OF WORK WITH SUFFICIENT RIGGING EQUIPMENT AND PERSONNEL TO OBTAIN DETAILED FABRICATION MEASUREMENTS OF EXISTING TOWER STEEL MEMBERS TO BE REPLACED.
 TOWER REINFORCING SHALL BE CONDUCTED BY FIELD CREWS EXPERIENCED IN THE ASSEMBLY AND ERECTION OF RADIO ANTENNAS, TRANSMISSION LINES AND SUPPORT STRUCTURES. ALL SAFETY PROCEDURES, LOGGING AND ERECTION METHODS SHALL BE STANDARD TO THE INDUSTRY AND IN COMPLIANCE WITH OSHA.
 THE EXISTING COAXIAL CABLE AND ALL ACCESSORIES SHALL BE RELOCATED AND REINSTALLED BY THE CONTRACTOR WITHOUT INTERRUPTION IN SERVICE WHERE THEY ARE IN CONFLICT WITH TOWER REINFORCEMENT.
 CONTRACTOR SHALL TAKE EXTREME CARE NOT TO DAMAGE THE EXISTING TOWER. THE EXISTING COMMUNICATION EQUIPMENT, COAXIAL CABLE AND THEIR COMPONENTS IN THE EXISTING TOWER SHALL BE MAINTAINED AND REPAIRED AS NECESSARY DURING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR THE DAMAGE IMMEDIATELY (WITH THE APPROVAL OF THE COMMUNICATIONS COMPANY) AT NO ADDITIONAL COST TO THE CONTRACT.
 THE CONTRACTOR IS RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE DURING CONSTRUCTION. THE CONTRACTOR SHALL BE AWARE OF WEATHER & WIND CONDITIONS AND NOT PERFORM TOWER MEMBER REPLACEMENT IN THE WIND.
 ALL REINFORCEMENT SHOWN FOR DIAGONALS AND HORIZONTALS APPLY TO ALL SIDES OF THE TOWER.

- NOTES:**
1. ALL PROPOSED DIAGONAL MEMBERS SHALL BE INSTALLED WITH A325-A490 BOLTS (FLANGES EXCLUDING MATCH EXISTING). SIZE SHALL MATCH EXISTING.
 2. REINFORCEMENT MAY REQUIRE TEMPORARY REMOVAL OF EXISTING EQUIPMENT. CONTRACTOR SHALL COORDINATE WORK WITH OWNER.
 3. PROPOSED ANTENNAS AND APPURTENANCES SHALL NOT BE INSTALLED UNTIL ALL REINFORCEMENT WORK HAS BEEN COMPLETED AND IS DEEMED COMPLETE.
 4. ANTENNAS AND APPURTENANCES NOT SHOWN FOR CLARITY.



1 TOWER REINFORCEMENT
SCALE: 1" = 30'-0"
SK-1

TNX TOWER INPUT/OUTPUT SUMMARY

URS Corporation
 500 Enterprise Drive, Suite 3B
 Rocky Hill, CT 06087
 Phone: 860-528-8882
 FAX: 860-529-9901

PIROD 120'-0"x170' Lattice Tower
 Project: TWS-07 Rev. 1 / Conway, CT Tower
 Client: SCS/1, Middle (TWS-07) (EBI-002)
 Date: 09/23/14
 Drawn by: NTS
 Checked by: E-1



- TOWER DESIGN NOTES**
1. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard
 2. Tower is also designed for a 74 mph basic wind with 0.50 in ice
 3. Members are based upon a 50 mph wind.
 4. Wind against tower sections have range connections
 5. Connections are galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISI Specifications
 6. Tower members are "hot dipped" galvanized in accordance with ASTM A153 and ASTM A153 Standards.
 7. Voids are fabricated with ER-705-6 electrodes
 8. TOWER FATIGUE: 92.4%

MATERIAL STRENGTH


GRADE	F _y	F _u	GRADE	F _y	F _u
A572-50	50 KSI	65 KSI	A36	36 KSI	58 KSI

SYMBOL LIST

MARK	SIZE	MARK	SIZE
PLATE	1/4"	PLATE	1/4"
ANGLE	3"x3"x1/4"	ANGLE	3"x3"x1/4"
PIPE	4"	PIPE	4"

DESIGNED APERTURE LOADING

ELEVATION	TYPE	ELEVATION	TYPE
188.0	12" x 12" CHS (CHANGING)	188.0	12" x 12" CHS (CHANGING)
187.5	12" x 12" CHS (CHANGING)	187.5	12" x 12" CHS (CHANGING)
187.0	12" x 12" CHS (CHANGING)	187.0	12" x 12" CHS (CHANGING)
186.5	12" x 12" CHS (CHANGING)	186.5	12" x 12" CHS (CHANGING)
186.0	12" x 12" CHS (CHANGING)	186.0	12" x 12" CHS (CHANGING)
185.5	12" x 12" CHS (CHANGING)	185.5	12" x 12" CHS (CHANGING)
185.0	12" x 12" CHS (CHANGING)	185.0	12" x 12" CHS (CHANGING)
184.5	12" x 12" CHS (CHANGING)	184.5	12" x 12" CHS (CHANGING)
184.0	12" x 12" CHS (CHANGING)	184.0	12" x 12" CHS (CHANGING)
183.5	12" x 12" CHS (CHANGING)	183.5	12" x 12" CHS (CHANGING)
183.0	12" x 12" CHS (CHANGING)	183.0	12" x 12" CHS (CHANGING)
182.5	12" x 12" CHS (CHANGING)	182.5	12" x 12" CHS (CHANGING)
182.0	12" x 12" CHS (CHANGING)	182.0	12" x 12" CHS (CHANGING)
181.5	12" x 12" CHS (CHANGING)	181.5	12" x 12" CHS (CHANGING)
181.0	12" x 12" CHS (CHANGING)	181.0	12" x 12" CHS (CHANGING)
180.5	12" x 12" CHS (CHANGING)	180.5	12" x 12" CHS (CHANGING)
180.0	12" x 12" CHS (CHANGING)	180.0	12" x 12" CHS (CHANGING)
179.5	12" x 12" CHS (CHANGING)	179.5	12" x 12" CHS (CHANGING)
179.0	12" x 12" CHS (CHANGING)	179.0	12" x 12" CHS (CHANGING)
178.5	12" x 12" CHS (CHANGING)	178.5	12" x 12" CHS (CHANGING)
178.0	12" x 12" CHS (CHANGING)	178.0	12" x 12" CHS (CHANGING)
177.5	12" x 12" CHS (CHANGING)	177.5	12" x 12" CHS (CHANGING)
177.0	12" x 12" CHS (CHANGING)	177.0	12" x 12" CHS (CHANGING)
176.5	12" x 12" CHS (CHANGING)	176.5	12" x 12" CHS (CHANGING)
176.0	12" x 12" CHS (CHANGING)	176.0	12" x 12" CHS (CHANGING)
175.5	12" x 12" CHS (CHANGING)	175.5	12" x 12" CHS (CHANGING)
175.0	12" x 12" CHS (CHANGING)	175.0	12" x 12" CHS (CHANGING)
174.5	12" x 12" CHS (CHANGING)	174.5	12" x 12" CHS (CHANGING)
174.0	12" x 12" CHS (CHANGING)	174.0	12" x 12" CHS (CHANGING)
173.5	12" x 12" CHS (CHANGING)	173.5	12" x 12" CHS (CHANGING)
173.0	12" x 12" CHS (CHANGING)	173.0	12" x 12" CHS (CHANGING)
172.5	12" x 12" CHS (CHANGING)	172.5	12" x 12" CHS (CHANGING)
172.0	12" x 12" CHS (CHANGING)	172.0	12" x 12" CHS (CHANGING)
171.5	12" x 12" CHS (CHANGING)	171.5	12" x 12" CHS (CHANGING)
171.0	12" x 12" CHS (CHANGING)	171.0	12" x 12" CHS (CHANGING)
170.5	12" x 12" CHS (CHANGING)	170.5	12" x 12" CHS (CHANGING)
170.0	12" x 12" CHS (CHANGING)	170.0	12" x 12" CHS (CHANGING)




TNX TOWER FEEDLINE DISTRIBUTION CHART

Feed Line Distribution Chart

0' - 170'

Round _____ Flat _____ App In Face _____ App Out Face _____ Truss Leg _____




<p>URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991</p>	<p>Job: PIROD U20'-0"x170' Lattice Tower Project: TWS-027 Rev. 1 / Cronwell, CT Tower Client: Sprint / T-Mobile (TWS-027)/(EBI-002) Code: TIA/EIA-222-F Path: _____</p> <p>Drawn by: MCD Date: 09/23/14 Scale: NTS Dwg No: E-7</p>
---	--

TNX TOWER FEEDLINE PLAN

Feed Line Plan

Round _____ Flat _____ App In Face _____ App Out Face _____ Truss-Leg _____



- (1) 1/2" (Town)
 - (2) 7/8" (Town)
 - (2) 1/2" (Town)
 - (3) 1/2" (existing)
 - (1) 1 5/8" Low Density (CPD)
 - (1) 3/8" (Town)
 - (1) 3/8" (CPD)
 - (1) 7/8" (Town)
 - (3) 7/8" (Town)
 - (1) 1 1/2" (Town)
 - (6) 1 5/8" (Existing)
 - (1) 7/8" (Town)
 - (1) 7/8" (Town)
 - (3) (existing) 1 1/4" Hybrid Cables (Sprint)
 - (1) Proposed 1 1/4" Hybrid Cable (Sprint)
- Leg "A"

- (6) Cat 5e (Clearwire)
 - (4) 1/2" (Clearwire)
- Face "B"

- (12) 1 5/8" (AT&T)
 - (12) 1 5/8" (Verizon)
 - (1) 1 5/8" Hybriflex (Verizon)
 - (2) 7/8" (existing)
- Leg "C"

- (4) Cat 5e (AT&T)
 - (2) Cat 5e (AT&T)
 - (6) RSS 8 - AWG (AT&T)
 - (3) FB-L98B-02 (10mm) F.O. (AT&T)
(located inside below)
 - (1) 3" Flex Conduit Tube (AT&T)
- Face "C"

- (12) 1 5/8" (T-Mobile)
 - (1) 1 5/8" Hybriflex (T-Mobile)
- Leg "B"

URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job: PIROD U20'-0"x170' Lattice Tower
	Project: TWS-027 Rev. 1 / Cromwell, CT Tower
	Client: Sprint / T-Mobile (TWS-027)/(EBI-002)
	Code: TIA/EIA-222-F
	Path: _____
Drawn by: MCD	App'd: _____
Date: 09/23/14	Scale: NTS
Dwg No. E-7	_____

TNX TOWER DETAILED OUTPUT

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 1 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 170.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 5.00 ft at the top and 20.00 ft at the base.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Basic wind speed of 85 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56 pcf.

A wind speed of 74 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

Weld together tower sections have flange connections..

Connections use galvanized A325 bolts, nuts and locking devices. Installation per TIA/EIA-222 and AISC Specifications..

Tower members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards..

Welds are fabricated with ER-70S-6 electrodes..

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs	Distribute Leg Loads As Uniform	√ Treat Feedline Bundles As Cylinder
Consider Moments - Horizontals	Assume Legs Pinned	Use ASCE 10 X-Brace Ly Rules
Consider Moments - Diagonals	√ Assume Rigid Index Plate	Calculate Redundant Bracing Forces
Use Moment Magnification	√ Use Clear Spans For Wind Area	√ Ignore Redundant Members in FEA
√ Use Code Stress Ratios	√ Use Clear Spans For KL/r	√ SR Leg Bolts Resist Compression
√ Use Code Safety Factors - Guys	Retension Guys To Initial Tension	√ All Leg Panels Have Same Allowable
Escalate Ice	Bypass Mast Stability Checks	Offset Girt At Foundation
Always Use Max Kz	√ Use Azimuth Dish Coefficients	√ Consider Feedline Torque
Use Special Wind Profile	√ Project Wind Area of Appurt.	Include Angle Block Shear Check
Include Bolts In Member Capacity	Autocalc Torque Arm Areas	Poles
√ Leg Bolts Are At Top Of Section	√ SR-Members Have Cut-Ends	Include Shear-Torsion Interaction
√ Secondary Horizontal Braces Leg	√ Sort Capacity Reports By Component	Always Use Sub-Critical Flow
Use Diamond Inner Bracing (4 Sided)	Triangulate Diamond Inner Bracing	Use Top Mounted Sockets
Add IBC .6D+W Combination	Use TIA-222-G Tension Splice Capacity Exemption	

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 2 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD



Triangular Tower

Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	170.00-150.00			5.00	1	20.00
T2	150.00-140.00		U6.0 105244	5.00	1	10.00
T3	140.00-120.00		U8.0 105216	6.00	1	20.00
T4	120.00-100.00		U10.0 105217 L3x3/16	8.00	1	20.00
T5	100.00-90.00		U12.0 105216	10.00	1	10.00
T6	90.00-80.00		U12.0 105216	11.00	1	10.00
T7	80.00-60.00		U14.0 105218	12.00	1	20.00
T8	60.00-40.00		U16.0 105219	14.00	1	20.00
T9	40.00-20.00		U18.0 105219	16.00	1	20.00
T10	20.00-0.00		U20.0 105219 L4x1/4	18.00	1	20.00

Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	<i>ft</i>	<i>ft</i>				<i>in</i>	<i>in</i>
T1	170.00-150.00	2.49	X Brace	No	No	0.0000	1.0000
T2	150.00-140.00	10.00	X Brace	No	No	0.0000	0.0000
T3	140.00-120.00	10.00	X Brace	No	No	0.0000	0.0000
T4	120.00-100.00	10.00	X Brace	No	No	0.0000	0.0000
T5	100.00-90.00	10.00	X Brace	No	No	0.0000	0.0000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 3 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	ft	ft				in	in
T6	90.00-80.00	10.00	X Brace	No	No	0.0000	0.0000
T7	80.00-60.00	10.00	X Brace	No	No	0.0000	0.0000
T8	60.00-40.00	10.00	X Brace	No	No	0.0000	0.0000
T9	40.00-20.00	10.00	X Brace	No	No	0.0000	0.0000
T10	20.00-0.00	10.00	X Brace	No	No	0.0000	0.0000

Tower Section Geometry (cont'd)

Tower Elevation	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
ft						
T1 170.00-150.00	Solid Round	1 3/4	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 150.00-140.00	Truss Leg	Pirod 105244	A572-50 (50 ksi)	Single Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)
T3 140.00-120.00	Truss Leg	Pirod 105216	A572-50 (50 ksi)	Single Angle	L3x3x3/16	A36 (36 ksi)
T4 120.00-100.00	Truss Leg	Pirod 105217	A572-50 (50 ksi)	Single Angle	L3x3x1/4	A36 (36 ksi)
T5 100.00-90.00	Truss Leg	Pirod 105217	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T6 90.00-80.00	Truss Leg	Pirod 105217 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3x3x5/16	A36 (36 ksi)
T7 80.00-60.00	Truss Leg	Pirod 105218 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3x3x3/8	A36 (36 ksi)
T8 60.00-40.00	Truss Leg	Pirod 105219	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x5/16	A36 (36 ksi)
T9 40.00-20.00	Truss Leg	Pirod 105219 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L3 1/2x3 1/2x3/8	A36 (36 ksi)
T10 20.00-0.00	Truss Leg	Pirod 105220 reinf w/ 1" dia bar	A572-50 (50 ksi)	Single Angle	L4x4x5/16	A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
ft						
T1 170.00-150.00	Solid Round	7/8	A572-50 (50 ksi)	Solid Round	7/8	A572-50 (50 ksi)
T2 150.00-140.00	Single Angle	L3x3x3/16	A36 (36 ksi)	Single Angle		A36 (36 ksi)

Tower Section Geometry (cont'd)

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 6 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T2 150.00-140.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T3 140.00-120.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T4 120.00-100.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T5 100.00-90.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T6 90.00-80.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T7 80.00-60.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T8 60.00-40.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T9 40.00-20.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1
T10 20.00-0.00	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1	0.0000	1

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 170.00-150.00	Flange	0.7500	0	A325N		0.6250	1	A325N		0.6250	0	A325N		0.6250	0
T2 150.00-140.00	Flange	1.0000	6	A325N		1.0000	1	A325N		0.6250	0	A325N		0.6250	0
T3 140.00-120.00	Flange	1.0000	6	A325N		1.0000	1	A325N		0.6250	0	A325N		0.6250	0
T4 120.00-100.00	Flange	1.0000	6	A325N		1.0000	1	A325N		0.6250	0	A325N		0.6250	0
T5 100.00-90.00	Flange	1.0000	6	A325N		1.0000	1	A325N		0.0000	0	A325N		0.6250	0
T6 90.00-80.00	Flange	1.0000	6	A325N		1.0000	1	A325N		0.6250	0	A325N		0.6250	0
T7 80.00-60.00	Flange	1.0000	6	A325N		1.0000	1	A325N		0.6250	0	A325N		0.6250	0
T8 60.00-40.00	Flange	1.2500	6	A325N		1.2500	1	A325N		0.6250	0	A325N		0.6250	0
T9 40.00-20.00	Flange	1.2500	6	A325N		1.2500	1	A325N		0.6250	0	A325N		0.6250	0
T10 20.00-0.00	Flange	0.0000	0	A325N		1.2500	1	A325N		0.6250	0	A325N		0.6250	0

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
CATEGORY	C	Yes	Ar (CfAe)	87.00 - 7.00	0.0000	0.48	4	2	1.0000	1.0000		0.21

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	7 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
5e (1 WIRE) CATEGORY	C	Yes	Ar (CfAe)	83.00 - 7.00	0.0000	0.45	2	1	1.0000	1.0000		0.21
5e (1 WIRE) 1/2 (Municipal)	A	No	Ar (Leg)	144.00 - 7.00	0.0000	0.125	1	1	0.5800	0.5800		0.25
7/8 (Municipal)	A	No	Ar (Leg)	144.00 - 7.00	0.0000	0.125	2	1	1.0000	1.1100		0.54
1/2 (Municipal)	A	No	Ar (Leg)	140.00 - 7.00	0.0000	0.13	2	1	0.5800	0.5800		0.25
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.14	3	1	1.0000	1.1100		0.54
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.14	1	1	1.1100	1.1100		0.54
FSJ2-50 (3/8 SUPERFLEX. FOAM)	A	No	Ar (Leg)	168.00 - 7.00	0.0000	0.12	1	1	0.4300	0.4300		0.08
FSJ2-50 (3/8 SUPERFLEX. FOAM)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.12	1	1	0.4300	0.4300		0.08
RG-11 590609 (1 1/2 FOAM)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.12	1	1	1.5000	1.5900		0.94
1 5/8 (T-Mobile)	B	No	Ar (Leg)	125.50 - 7.00	0.0000	0.1	12	3	1.5000	1.9800		1.04
1 5/8 (VZW)	C	No	Ar (Leg)	101.00 - 7.00	0.0000	0.12	12	6	1.5000	1.9800		1.04
1 5/8 (AT&T)	C	No	Ar (Leg)	115.00 - 7.00	0.0000	0.17	12	2	1.5000	1.9800		1.04
7/8	C	No	Ar (Leg)	170.00 - 7.00	0.0000	0.17	2	2	1.0000	1.1100		0.54
1 5/8	A	No	Ar (Leg)	160.00 - 7.00	0.0000	0.1	6	3	1.5000	1.9800		1.04
CATEGORY 5e (1 WIRE) (Clearwire)	B	Yes	Ar (CfAe)	134.00 - 7.00	-2.0000	0	6	6	1.0000	1.0000		0.21
1/2 (Clearwire)	B	Yes	Ar (CfAe)	134.00 - 7.00	-4.0000	0	4	4	0.5800	0.5800		0.25
FB-L98B-02 (10mm Fiber) (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	3.0000	0.4	3	3	0.3937	0.3937		0.03
RSS 8 - AWG 2 (0.645") (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	2.0000	0.43	6	6	0.6450	0.6450		0.30
3" Flex Conduit (AT&T)	C	Yes	Ar (CfAe)	115.00 - 7.00	4.0000	0.41	1	1	0.0000	3.0000		3.00
1/2	A	No	Ar (Leg)	30.00 - 7.00	0.0000	0.08	3	1	0.5800	0.5800		0.25
AVA7-50 (1-5/8 LOW DENS. FOAM) (CPD)	A	Yes	Ar (CfAe)	170.00 - 7.00	0.0000	0.38	1	1	1.5000	1.9800		0.72
1 5/8" Hybriflex (T-Mobile)	B	No	Ar (Leg)	125.00 - 7.00	0.0000	0.05	1	1	1.6250	1.6250		0.21
1 5/8" Hybriflex (VZW)	C	No	Ar (Leg)	101.00 - 7.00	0.0000	0.1	1	1	1.6250	1.6250		0.21
LDF6-50A (1-1/4 FOAM) (Sprint-FO)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.16	4	2	1.5500	1.5500		0.66
7/8 (Municipal)	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.132	1	1	1.1100	1.1100		0.54
7/8	A	No	Ar (Leg)	170.00 - 7.00	0.0000	0.132	1	1	1.1100	1.1100		0.54

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 8 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Description	Face or Leg	Allow Shield	Component Type	Placement	Face Offset	Lateral Offset	#	# Per Row	Clear Spacing	Width or Diameter	Perimeter	Weight
				ft	in	(Frac FW)			in	in	in	plf
(Municipal)												

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation	Face	A _R	A _F	C _A A _A In Face	C _A A _A Out Face	Weight
	ft		ft ²	ft ²	ft ²	ft ²	K
T1	170.00-150.00	A	40.136	0.000	0.000	0.000	0.22
		B	33.136	0.000	0.000	0.000	0.00
		C	3.700	0.000	0.000	0.000	0.02
T2	150.00-140.00	A	25.105	0.000	0.000	0.000	0.14
		B	21.605	0.000	0.000	0.000	0.00
		C	1.850	0.000	0.000	0.000	0.01
T3	140.00-120.00	A	54.943	0.000	0.000	0.000	0.32
		B	64.985	0.000	0.000	0.000	0.10
		C	11.035	0.000	0.000	0.000	0.02
T4	120.00-100.00	A	81.377	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	67.119	0.000	0.000	0.000	0.29
T5	100.00-90.00	A	61.700	0.000	0.000	0.000	0.16
		B	44.365	0.000	0.000	0.000	0.15
		C	56.248	0.000	0.000	0.000	0.31
T6	90.00-80.00	A	61.700	0.000	0.000	0.000	0.16
		B	44.365	0.000	0.000	0.000	0.15
		C	58.981	0.000	0.000	0.000	0.32
T7	80.00-60.00	A	123.400	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T8	60.00-40.00	A	123.400	0.000	0.000	0.000	0.32
		B	88.730	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T9	40.00-20.00	A	124.850	0.000	0.000	0.000	0.32
		B	90.180	0.000	0.000	0.000	0.30
		C	122.210	0.000	0.000	0.000	0.65
T10	20.00-0.00	A	82.095	0.000	0.000	0.000	0.21
		B	59.559	0.000	0.000	0.000	0.19
		C	79.437	0.000	0.000	0.000	0.42

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation	Face or Leg	Ice Thickness	A _R	A _F	C _A A _A In Face	C _A A _A Out Face	Weight
	ft		in	ft ²	ft ²	ft ²	ft ²	K
T1	170.00-150.00	A	0.500	58.953	3.517	0.000	0.000	0.60
		B		50.470	0.000	0.000	0.000	0.00
		C		3.517	3.517	0.000	0.000	0.07
T2	150.00-140.00	A	0.500	36.013	1.758	0.000	0.000	0.39
		B		31.771	0.000	0.000	0.000	0.00
		C		1.758	1.758	0.000	0.000	0.03
T3	140.00-120.00	A	0.500	82.393	3.517	0.000	0.000	0.87
		B		86.296	15.727	0.000	0.000	0.34
		C		11.727	3.517	0.000	0.000	0.07
T4	120.00-100.00	A	0.500	110.244	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	9 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight K
T5	100.00-90.00	C	0.500	70.420	13.548	0.000	0.000	0.75
		A		77.925	1.758	0.000	0.000	0.44
		B		55.065	11.233	0.000	0.000	0.44
T6	90.00-80.00	C	0.500	59.479	8.446	0.000	0.000	0.79
		A		77.925	1.758	0.000	0.000	0.44
		B		55.065	11.233	0.000	0.000	0.44
T7	80.00-60.00	C	0.500	61.646	10.096	0.000	0.000	0.83
		A		155.850	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88
T8	60.00-40.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		155.850	3.517	0.000	0.000	0.87
		B		110.130	22.467	0.000	0.000	0.88
T9	40.00-20.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		159.100	3.517	0.000	0.000	0.90
		B		113.380	22.467	0.000	0.000	0.88
T10	20.00-0.00	C	0.500	128.959	21.605	0.000	0.000	1.72
		A		105.527	2.286	0.000	0.000	0.60
		B		75.809	14.603	0.000	0.000	0.57
		C		83.823	14.043	0.000	0.000	1.12

Feed Line Shielding

Section	Elevation ft	Face	A_R ft ²	A_R Ice ft ²	A_F ft ²	A_F Ice ft ²
T1	170.00-150.00	A	0.239	0.771	0.000	0.000
		B	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	0.000
T2	150.00-140.00	A	0.000	0.106	0.184	0.277
		B	0.000	0.000	0.000	0.000
		C	0.000	0.000	0.000	0.000
T3	140.00-120.00	A	0.000	0.145	0.289	0.435
		B	0.000	0.580	0.849	1.741
		C	0.000	0.000	0.000	0.000
T4	120.00-100.00	A	0.000	0.145	0.288	0.434
		B	0.000	0.828	1.212	2.484
		C	0.000	0.548	0.879	1.645
T5	100.00-90.00	A	0.000	0.057	0.114	0.171
		B	0.000	0.327	0.479	0.981
		C	0.000	0.289	0.463	0.867
T6	90.00-80.00	A	0.000	0.055	0.109	0.165
		B	0.000	0.314	0.459	0.942
		C	0.000	0.340	0.538	1.019
T7	80.00-60.00	A	0.000	0.105	0.208	0.314
		B	0.000	0.598	0.875	1.795
		C	0.000	0.739	1.163	2.216
T8	60.00-40.00	A	0.000	0.100	0.231	0.348
		B	0.000	0.570	0.973	1.994
		C	0.000	0.703	1.292	2.462
T9	40.00-20.00	A	0.000	0.096	0.223	0.336
		B	0.000	0.550	0.939	1.925
		C	0.000	0.679	1.247	2.377
T10	20.00-0.00	A	0.000	0.061	0.162	0.243
		B	0.000	0.348	0.679	1.393
		C	0.000	0.430	0.902	1.719

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 10 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Feed Line Center of Pressure

Section	Elevation	CP _X	CP _Z	CP _X	CP _Z
	ft	in	in	Ice in	Ice in
T1	170.00-150.00	-0.7973	-8.0376	-0.4853	-7.4212
T2	150.00-140.00	-0.4988	-6.6293	-0.3283	-6.3594
T3	140.00-120.00	1.4194	-7.8403	1.2494	-8.0075
T4	120.00-100.00	-0.3302	-2.7146	-0.0626	-4.2227
T5	100.00-90.00	-5.2784	0.3685	-4.0917	-1.7690
T6	90.00-80.00	-6.3856	0.8722	-4.8612	-1.5653
T7	80.00-60.00	-7.6460	1.3464	-5.9655	-1.3222
T8	60.00-40.00	-8.5419	1.4777	-6.6864	-1.5207
T9	40.00-20.00	-9.4077	1.2998	-7.3405	-2.1935
T10	20.00-0.00	-8.2989	0.8730	-6.4327	-2.3698

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement ft	C _A A _{Front} ft ²	C _A A _{Side} ft ²	Weight K
			Horz Lateral ft	Vert ft					
101-90-08-0-01 (Municipal)	A	From Leg	9.00	0.0000	183.00	No Ice	3.33	3.33	0.04
			2.00			1/2" Ice	4.31	4.31	0.06
			0.00						
15' Mount Pipe (Municipal)	A	From Leg	9.00	0.0000	179.75	No Ice	4.50	4.50	0.09
			2.00			1/2" Ice	6.03	6.03	0.12
			0.00						
3" Dia 20' Omni (Municipal)	B	From Face	9.00	0.0000	178.00	No Ice	6.00	6.00	0.06
			0.00			1/2" Ice	8.03	8.03	0.10
			0.00						
2.5" x 20'6" Whip (Municipal)	C	From Face	9.00	0.0000	178.00	No Ice	5.14	5.14	0.15
			0.00			1/2" Ice	7.24	7.24	0.19
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00			1/2" Ice	4.93	4.93	0.06
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00			1/2" Ice	4.93	4.93	0.06
			0.00						
2.5" x 14' Omni (Municipal)	C	From Face	9.00	0.0000	175.00	No Ice	3.50	3.50	0.03
			0.00			1/2" Ice	4.93	4.93	0.06
			0.00						
1.5" x 12' Omni (Municipal)	A	From Face	9.00	0.0000	174.00	No Ice	1.50	1.50	0.06
			4.00			1/2" Ice	2.52	2.52	0.07
			0.00						
9 Arm Halo Mount (Municipal)	C	None		0.0000	168.00	No Ice	62.60	62.60	3.60
						1/2" Ice	80.40	80.40	4.80
SU-RA-HP-2.4 Antenna (Municipal)	B	From Face	9.00	0.0000	168.00	No Ice	0.80	0.37	0.00
			2.50			1/2" Ice	0.93	0.47	0.01
			0.00						
PTP49600 (CPD)	C	From Leg	9.00	0.0000	168.00	No Ice	2.04	0.53	0.01
			0.00			1/2" Ice	2.24	0.65	0.02

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	11 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _A A _A		Weight	
			Horz	Lateral			Front	Side		
			ft	ft	°	ft	ft ²	ft ²	K	
APXV18-206517S-C w/ mounting hardware	A	From Leg	0.00		0.0000	159.50	No Ice	5.08	4.46	0.05
			1.00				1/2" Ice	5.53	5.39	0.09
			0.00							
APXV18-206517S-C w/ mounting hardware	B	From Leg	1.00		0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00				1/2" Ice	5.53	5.39	0.09
			0.00							
APXV18-206517S-C w/ mounting hardware	C	From Leg	1.00		0.0000	159.50	No Ice	5.08	4.46	0.05
			0.00				1/2" Ice	5.53	5.39	0.09
			0.00							
SC420-HF1LDF (Municipal)	A	From Face	6.00		0.0000	158.50	No Ice	2.14	2.14	0.02
			0.00				1/2" Ice	3.02	3.02	0.03
			0.00							
3" Dia 20' Omni (Municipal)	C	From Face	6.00		0.0000	144.00	No Ice	6.00	6.00	0.06
			9.00				1/2" Ice	8.03	8.03	0.10
			0.00							
3" Dia 20' Omni (Municipal)	A	From Face	6.00		0.0000	144.00	No Ice	6.00	6.00	0.06
			-9.00				1/2" Ice	8.03	8.03	0.10
			0.00							
2.5" x 20'6" Whip (Municipal)	A	From Face	6.00		0.0000	144.00	No Ice	5.14	5.14	0.15
			9.00				1/2" Ice	7.24	7.24	0.19
			0.00							
2" Dia 15' Omni (Municipal)	B	From Face	6.00		0.0000	141.00	No Ice	3.20	3.20	0.04
			-5.00				1/2" Ice	4.83	4.83	0.06
			0.00							
1.5" x 10' Omni (Municipal)	B	From Face	6.00		0.0000	139.00	No Ice	1.50	1.50	0.06
			5.00				1/2" Ice	2.52	2.52	0.07
			0.00							
9' Whip (Municipal)	A	From Face	6.00		0.0000	138.50	No Ice	5.85	5.85	0.12
			0.00				1/2" Ice	7.66	7.66	0.17
			0.00							
PiROD 20' Universal Platform (Municipal)	C	None			0.0000	134.00	No Ice	33.10	33.10	2.27
							1/2" Ice	47.10	47.10	2.70
Argus LLPX310R (Clearwire)	A	From Face	6.00		0.0000	134.00	No Ice	4.86	3.46	0.03
			7.00				1/2" Ice	5.22	3.80	0.06
			0.00							
Argus LLPX310R (Clearwire)	B	From Face	6.00		0.0000	134.00	No Ice	4.86	3.46	0.03
			0.00				1/2" Ice	5.22	3.80	0.06
			0.00							
Argus LLPX310R (Clearwire)	C	From Face	6.00		0.0000	134.00	No Ice	4.86	3.46	0.03
			7.00				1/2" Ice	5.22	3.80	0.06
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	A	From Face	6.00		0.0000	134.00	No Ice	1.82	0.83	0.03
			7.00				1/2" Ice	2.00	0.97	0.04
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	B	From Face	6.00		0.0000	134.00	No Ice	1.82	0.83	0.03
			0.00				1/2" Ice	2.00	0.97	0.04
			0.00							
REMOTE RADIO HEAD (RRH) (Clearwire)	C	From Face	6.00		0.0000	134.00	No Ice	1.82	0.83	0.03
			7.00				1/2" Ice	2.00	0.97	0.04
			0.00							
(2) TMA (shielded) (AT&T)	A	From Leg	4.00		0.0000	115.00	No Ice	0.00	0.00	0.01
			6.00				1/2" Ice	0.00	0.00	0.01
			0.00							
(2) TMA (shielded) (AT&T)	A	From Leg	4.00		0.0000	115.00	No Ice	0.00	0.00	0.01
			-6.00				1/2" Ice	0.00	0.00	0.01

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	12 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{A/A} Front	C _{A/A} Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft ²	ft ²	K	
(2) TMA (shielded) (AT&T)	B	From Leg	4.00	0.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			6.00	0.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
(2) TMA (shielded) (AT&T)	B	From Leg	4.00	0.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			-6.00	0.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
(2) TMA (shielded) (AT&T)	C	From Leg	4.00	0.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			6.00	0.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
(2) TMA (shielded) (AT&T)	C	From Leg	4.00	0.00	0.0000	115.00	No Ice	0.00	0.00	0.01
			-6.00	0.00			1/2" Ice	0.00	0.00	0.01
			0.00	0.00						
PiROD 12' Lightweight T-Frame (AT&T)	A	From Leg	2.00	0.00	0.0000	115.00	No Ice	10.20	10.20	0.25
			0.00	0.00			1/2" Ice	16.20	16.20	0.35
			0.00	0.00						
PiROD 12' Lightweight T-Frame (AT&T)	B	From Leg	2.00	0.00	0.0000	115.00	No Ice	10.20	10.20	0.25
			0.00	0.00			1/2" Ice	16.20	16.20	0.35
			0.00	0.00						
PiROD 12' Lightweight T-Frame (AT&T)	C	From Leg	2.00	0.00	0.0000	115.00	No Ice	10.20	10.20	0.25
			0.00	0.00			1/2" Ice	16.20	16.20	0.35
			0.00	0.00						
7770 (AT&T)	A	From Leg	4.00	0.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			6.00	0.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	A	From Leg	4.00	0.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			-6.00	0.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	B	From Leg	4.00	0.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			6.00	0.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	B	From Leg	4.00	0.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			-6.00	0.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	C	From Leg	4.00	0.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			6.00	0.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
7770 (AT&T)	C	From Leg	4.00	0.00	0.0000	115.00	No Ice	10.03	5.60	0.02
			-6.00	0.00			1/2" Ice	10.61	6.15	0.07
			0.00	0.00						
AM-X-CD-16-65-00T-RET (6') (AT&T)	A	From Leg	4.00	0.00	0.0000	115.00	No Ice	8.26	4.64	0.05
			0.00	0.00			1/2" Ice	8.81	5.09	0.10
			0.00	0.00						
AM-X-CD-16-65-00T-RET (6') (AT&T)	B	From Leg	4.00	0.00	0.0000	115.00	No Ice	8.26	4.64	0.05
			0.00	0.00			1/2" Ice	8.81	5.09	0.10
			0.00	0.00						
AM-X-CD-16-65-00T-RET (6') (AT&T)	C	From Leg	4.00	0.00	0.0000	115.00	No Ice	8.26	4.64	0.05
			0.00	0.00			1/2" Ice	8.81	5.09	0.10
			0.00	0.00						
(2) REMOTE RADIO HEAD (RRH) (AT&T)	A	From Leg	0.00	0.00	0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00	0.00						
(2) REMOTE RADIO HEAD (RRH) (AT&T)	B	From Leg	0.00	0.00	0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00	0.00						
(2) REMOTE RADIO HEAD (RRH)	C	From Leg	0.00	0.00	0.0000	115.00	No Ice	1.82	0.83	0.03
			0.00	0.00			1/2" Ice	2.00	0.97	0.04
			0.00	0.00						

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job		PIROD U20'-0"x170' Lattice Tower					Page		
	Project		TWS-027 Rev. 1 / Cromwell, CT Tower					Date		
	Client		Sprint / T-Mobile (TWS-027)/(EBI-002)					Designed by		
									13 of 43	
									11:32:54 09/23/14	
									MCD	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{1A} A ₁ Front	C _{1A} A ₂ Side	Weight
			Horz	Vert					
			Lateral		°	ft	ft ²	ft ²	K
			ft	ft					
			ft						
(AT&T)			0.00						
Surge Suppressor (AT&T)	C	From Leg	0.00		0.0000	115.00	No Ice	0.80	0.03
			0.00				1/2" Ice	0.94	0.04
			0.00						
BXA-171063-12BF (Verizon)	A	From Leg	4.00		0.0000	101.00	No Ice	4.73	0.02
			0.00				1/2" Ice	5.18	0.04
			0.00						
SWCP 2x5514 (Verizon)	A	From Leg	4.00		0.0000	101.00	No Ice	7.01	0.02
			-4.00				1/2" Ice	7.44	0.07
			0.00						
BXA-171063-12BF (Verizon)	B	From Leg	4.00		0.0000	101.00	No Ice	4.73	0.02
			0.00				1/2" Ice	5.18	0.04
			0.00						
BXA-171063-12BF (Verizon)	C	From Leg	4.00		0.0000	101.00	No Ice	4.73	0.02
			0.00				1/2" Ice	5.18	0.04
			0.00						
SWCP 2x5514 (Verizon)	C	From Leg	4.00		0.0000	101.00	No Ice	7.01	0.02
			-4.00				1/2" Ice	7.44	0.07
			0.00						
PiROD 12' Lightweight T-Frame (Verizon)	A	From Leg	2.00		0.0000	101.00	No Ice	10.20	0.25
			0.00				1/2" Ice	16.20	0.35
			0.00						
PiROD 12' Lightweight T-Frame (Verizon)	B	From Leg	2.00		0.0000	101.00	No Ice	10.20	0.25
			0.00				1/2" Ice	16.20	0.35
			0.00						
PiROD 12' Lightweight T-Frame (Verizon)	C	From Leg	2.00		0.0000	101.00	No Ice	10.20	0.25
			0.00				1/2" Ice	16.20	0.35
			0.00						
(2) Diplexer (Verizon)	A	From Leg	4.00		0.0000	101.00	No Ice	0.23	0.01
			6.00				1/2" Ice	0.30	0.01
			0.00						
(2) Diplexer (Verizon)	B	From Leg	4.00		0.0000	101.00	No Ice	0.23	0.01
			6.00				1/2" Ice	0.30	0.01
			0.00						
(2) Diplexer (Verizon)	C	From Leg	4.00		0.0000	101.00	No Ice	0.23	0.01
			6.00				1/2" Ice	0.30	0.01
			0.00						
BXA-70063-6CF (Verizon)	B	From Leg	4.00		0.0000	101.00	No Ice	7.73	0.02
			-4.00				1/2" Ice	8.27	0.06
			0.00						
HBX-6517DS-VTM (Verizon - AWS)	A	From Leg	4.00		0.0000	101.00	No Ice	5.24	0.01
			6.00				1/2" Ice	5.71	0.04
			0.00						
HBX-6517DS-VTM (Verizon - AWS)	B	From Leg	4.00		0.0000	101.00	No Ice	5.24	0.01
			6.00				1/2" Ice	5.71	0.04
			0.00						
HBX-6517DS-VTM (Verizon - AWS)	C	From Leg	4.00		0.0000	101.00	No Ice	5.24	0.01
			6.00				1/2" Ice	5.71	0.04
			0.00						
RH_2X40-AWS (Verizon - AWS)	A	From Leg	4.00		0.0000	101.00	No Ice	2.52	0.04
			6.00				1/2" Ice	2.75	0.06
			0.00						
RH_2X40-AWS (Verizon - AWS)	B	From Leg	4.00		0.0000	101.00	No Ice	2.52	0.04
			6.00				1/2" Ice	2.75	0.06
			0.00						
RH_2X40-AWS (Verizon - AWS)	C	From Leg	4.00		0.0000	101.00	No Ice	2.52	0.04
			6.00				1/2" Ice	2.75	0.06

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	14 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA}		Weight
			Horz	Lateral			Front	Side	
			ft	ft	°	ft	ft ²	ft ²	K
DB-T1-6Z-8AB-0Z (Verizon - AWS)	C	None		0.00	0.0000	101.00	No Ice 5.35 1/2" Ice 5.75	2.40 2.72	0.04 0.07
LNX-6514DS-T4M (Verizon - 850)	A	From Leg	4.00 -6.00 0.00	0.0000	101.00	No Ice 8.38 1/2" Ice 8.93	5.41 5.86	0.04 0.09	
LNX-6514DS-T4M (Verizon - 850)	B	From Leg	4.00 -6.00 0.00	0.0000	101.00	No Ice 8.38 1/2" Ice 8.93	5.41 5.86	0.04 0.09	
LNX-6514DS-T4M (Verizon - 850)	C	From Leg	4.00 -6.00 0.00	0.0000	101.00	No Ice 8.38 1/2" Ice 8.93	5.41 5.86	0.04 0.09	
3"x2"x22" Panel	B	From Leg	2.00 0.00 0.00	0.0000	87.00	No Ice 0.65 1/2" Ice 0.81	0.47 0.61	0.05 0.05	
TMA	B	From Leg	2.00 0.00 0.00	0.0000	84.50	No Ice 1.06 1/2" Ice 1.21	0.45 0.57	0.02 0.03	
3' Stand-off	B	From Leg	1.50 0.00 0.00	0.0000	83.50	No Ice 1.00 1/2" Ice 1.20	2.00 2.70	0.05 0.07	
3' Stand-off	A	From Leg	1.50 0.00 0.00	0.0000	83.50	No Ice 1.00 1/2" Ice 1.20	2.00 2.70	0.05 0.07	
TMA	A	From Leg	2.00 0.00 0.00	0.0000	83.00	No Ice 1.06 1/2" Ice 1.21	0.45 0.57	0.02 0.03	
TMA	B	From Leg	2.00 0.00 0.00	0.0000	82.50	No Ice 1.06 1/2" Ice 1.21	0.45 0.57	0.02 0.03	
3"x2"x22" Panel	B	From Leg	2.00 0.00 0.00	0.0000	80.00	No Ice 0.65 1/2" Ice 0.81	0.47 0.61	0.05 0.05	
Camera	A	From Leg	0.00 0.00 0.00	0.0000	30.00	No Ice 0.50 1/2" Ice 0.60	0.50 0.60	0.01 0.02	
PC9013N	A	From Leg	1.00 0.00 0.00	0.0000	24.00	No Ice 0.46 1/2" Ice 0.52	0.46 0.52	0.00 0.00	
APXVSPP18-C-A20 (Sprint)	A	From Face	9.00 -1.00 0.00	0.0000	170.00	No Ice 8.40 1/2" Ice 8.95	5.28 5.74	0.06 0.11	
APXVSPP18-C-A20 (Sprint)	B	From Face	9.00 -1.00 0.00	0.0000	170.00	No Ice 8.40 1/2" Ice 8.95	5.28 5.74	0.06 0.11	
APXVSPP18-C-A20 (Sprint)	C	From Face	9.00 -1.00 0.00	0.0000	170.00	No Ice 8.40 1/2" Ice 8.95	5.28 5.74	0.06 0.11	
Panasonic RRH 1900MHZ (Sprint)	A	From Face	8.00 0.00 0.00	0.0000	170.00	No Ice 2.49 1/2" Ice 2.71	3.06 3.30	0.09 0.12	
Panasonic RRH 1900MHZ (Sprint)	B	From Face	8.00 0.00 0.00	0.0000	170.00	No Ice 2.49 1/2" Ice 2.71	3.06 3.30	0.09 0.12	
Panasonic RRH 1900MHZ (Sprint)	C	From Face	8.00 0.00 0.00	0.0000	170.00	No Ice 2.49 1/2" Ice 2.71	3.06 3.30	0.09 0.12	

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	15 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment	Placement ft	C _A A ₁ Front ft ²	C _A A ₁ Side ft ²	Weight K
Andrew 800MHz RRH (Sprint)	A	From Face	8.00 0.00 0.00	0.0000	170.00	No Ice 1/2" Ice 2.36 2.57	1.97 2.17	0.06 0.08
Andrew 800MHz RRH (Sprint)	B	From Face	8.00 0.00 0.00	0.0000	170.00	No Ice 1/2" Ice 2.36 2.57	1.97 2.17	0.06 0.08
Andrew 800MHz RRH (Sprint)	C	From Face	8.00 0.00 0.00	0.0000	170.00	No Ice 1/2" Ice 2.36 2.57	1.97 2.17	0.06 0.08
APXV9TM14-120 (Sprint)	A	From Face	9.00 -4.00 0.00	0.0000	170.00	No Ice 1/2" Ice 6.90 7.35	3.61 3.97	0.07 0.11
APXV9TM14-120 (Sprint)	B	From Face	9.00 -4.00 0.00	0.0000	170.00	No Ice 1/2" Ice 6.90 7.35	3.61 3.97	0.07 0.11
APXV9TM14-120 (Sprint)	C	From Face	9.00 -4.00 0.00	0.0000	170.00	No Ice 1/2" Ice 6.90 7.35	3.61 3.97	0.07 0.11
TD-RRH8x20-25 (Sprint)	A	From Face	9.00 -4.00 0.00	0.0000	170.00	No Ice 1/2" Ice 4.32 4.60	1.41 1.61	0.07 0.09
TD-RRH8x20-25 (Sprint)	B	From Face	9.00 -4.00 0.00	0.0000	170.00	No Ice 1/2" Ice 4.32 4.60	1.41 1.61	0.07 0.09
TD-RRH8x20-25 (Sprint)	C	From Face	9.00 -4.00 0.00	0.0000	170.00	No Ice 1/2" Ice 4.32 4.60	1.41 1.61	0.07 0.09
PiROD 10' Lightweight T-Frame (T-Mobile)	A	From Leg	2.00 0.00 0.00	0.0000	125.50	No Ice 1/2" Ice 9.30 14.50	9.30 14.50	0.25 0.34
PiROD 10' Lightweight T-Frame (T-Mobile)	B	From Leg	2.00 0.00 0.00	0.0000	125.50	No Ice 1/2" Ice 9.30 14.50	9.30 14.50	0.25 0.34
PiROD 10' Lightweight T-Frame (T-Mobile)	C	From Leg	2.00 0.00 0.00	0.0000	125.50	No Ice 1/2" Ice 9.30 14.50	9.30 14.50	0.25 0.34
AIR B2A/B4P (T-Mobile)	A	From Leg	4.00 3.00 0.00	0.0000	125.50	No Ice 1/2" Ice 6.42 6.86	4.22 4.64	0.08 0.12
AIR B2A/B4P (T-Mobile)	B	From Leg	4.00 3.00 0.00	0.0000	125.50	No Ice 1/2" Ice 6.42 6.86	4.22 4.64	0.08 0.12
AIR B2A/B4P (T-Mobile)	C	From Leg	4.00 3.00 0.00	0.0000	125.50	No Ice 1/2" Ice 6.42 6.86	4.22 4.64	0.08 0.12
AIR B2A/B4P (T-Mobile)	A	From Leg	4.00 -3.00 0.00	0.0000	125.50	No Ice 1/2" Ice 6.42 6.86	4.22 4.64	0.08 0.12
AIR B2A/B4P (T-Mobile)	B	From Leg	4.00 -3.00 0.00	0.0000	125.50	No Ice 1/2" Ice 6.42 6.86	4.22 4.64	0.08 0.12
AIR B2A/B4P (T-Mobile)	C	From Leg	4.00 -3.00 0.00	0.0000	125.50	No Ice 1/2" Ice 6.42 6.86	4.22 4.64	0.08 0.12
Twin PCS TMA (T-Mobile)	A	From Leg	4.00 3.00 0.00	0.0000	125.50	No Ice 1/2" Ice 0.77 0.96	0.36 0.52	0.01 0.02

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	16 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral					
Twin PCS TMA (T-Mobile)	B	From Leg	4.00	0.0000	125.50	No Ice	0.77	0.36	0.01
			3.00			1/2" Ice	0.96	0.52	0.02
			0.00						
Twin PCS TMA (T-Mobile)	C	From Leg	4.00	0.0000	125.50	No Ice	0.77	0.36	0.01
			3.00			1/2" Ice	0.96	0.52	0.02
			0.00						
LNX-6515DS-VTM w/ 6' 2" sch 40 Pipe Mount (T-Mobile)	A	From Leg	4.00	0.0000	125.50	No Ice	11.45	9.12	0.07
			0.00			1/2" Ice	12.06	10.21	0.15
			0.00						
LNX-6515DS-VTM w/ 6' 2" sch 40 Pipe Mount (T-Mobile)	B	From Leg	4.00	0.0000	125.50	No Ice	11.45	9.12	0.07
			0.00			1/2" Ice	12.06	10.21	0.15
			0.00						
LNX-6515DS-VTM w/ 6' 2" sch 40 Pipe Mount (T-Mobile)	C	From Leg	4.00	0.0000	125.50	No Ice	11.45	9.12	0.07
			0.00			1/2" Ice	12.06	10.21	0.15
			0.00						
RRUS-11 (T-Mobile)	A	From Leg	4.00	0.0000	125.50	No Ice	3.26	1.38	0.05
			0.00			1/2" Ice	3.50	1.56	0.07
			0.00						
RRUS-11 (T-Mobile)	B	From Leg	4.00	0.0000	125.50	No Ice	3.26	1.38	0.05
			0.00			1/2" Ice	3.50	1.56	0.07
			0.00						
RRUS-11 (T-Mobile)	C	From Leg	4.00	0.0000	125.50	No Ice	3.26	1.38	0.05
			0.00			1/2" Ice	3.50	1.56	0.07
			0.00						

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight
				Horz	Lateral						
3' Dish	A	Paraboloid w/o Radome	From Leg	2.00	0.0000	83.00	3.00	No Ice	7.07	0.23	
				0.00				1/2" Ice	7.47	0.27	
				0.00							
VHLP2.5-180 (Clearwire)	A	Paraboloid w/o Radome	From Face	6.00	0.0000	134.00	2.50	No Ice	4.90	0.07	
				0.00				1/2" Ice	5.24	0.10	
				0.00							
VHLP2.5-180 (Clearwire)	A	Paraboloid w/o Radome	From Face	6.00	0.0000	134.00	2.50	No Ice	4.90	0.07	
				-7.00				1/2" Ice	5.24	0.10	
				0.00							
VHLP2.5-180 (Clearwire)	B	Paraboloid w/o Radome	From Face	6.00	0.0000	134.00	2.50	No Ice	4.90	0.07	
				-7.00				1/2" Ice	5.24	0.10	
				0.00							
VHLP2-180 (Clearwire)	C	Paraboloid w/o Radome	From Face	6.00	0.0000	134.00	2.00	No Ice	3.14	0.03	
				0.00				1/2" Ice	3.41	0.04	
				0.00							
HPD2-4.7	C	Paraboloid w/Radome	From Face	9.00	0.0000	168.00	2.00	No Ice	3.14	0.03	
				0.00				1/2" Ice	3.41	0.04	
				0.00							

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	17 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Truss-Leg Properties

Section Designation	Area	Area Ice	Self Weight	Ice Weight	Equiv. Diameter	Equiv. Diameter Ice	Leg Area
	in ²	in ²	K	K	in	in	in ²
Pirod 105244	1026.8606	1727.9786	0.56	0.21	7.1310	11.9999	3.6816
Pirod 105216	1998.0891	3357.4497	0.51	0.43	6.9378	11.6578	3.6816
Pirod 105217	2130.7479	3520.4599	0.62	0.44	7.3984	12.2238	5.3014
Pirod 105217	2130.7479	3520.4599	0.62	0.44	7.3984	12.2238	5.3014
Pirod 105217 reinf w/ 1" dia bar	2291.5652	3727.7657	0.79	0.46	7.9568	12.9436	7.6570
Pirod 105218 reinf w/ 1" dia bar	2425.8928	3907.6826	0.95	0.48	8.4232	13.5683	9.9280
Pirod 105219	2441.8688	3942.2854	0.94	0.49	8.4787	13.6885	9.4248
Pirod 105219 reinf w /1" dia bar	2571.0468	4121.6676	1.11	0.50	8.9272	14.3113	11.7803
Pirod 105220 reinf w/ 1" dia bar	2697.7688	4300.8949	1.29	0.51	9.3673	14.9337	14.2843

Tower Pressures - No Ice

$$G_H = 1.125$$

Section Elevation	z	K _Z	q _z	A _G	F a c e	A _F	A _R	A _{leg}	Leg %	C _{A A_I} In Face	C _{A A_O} Out Face
ft	ft		psf	ft ²		ft ²	ft ²	ft ²		ft ²	ft ²
T1 170.00-150.00	160.00	1.57	29	102.917	A	0.000	52.765	5.833	11.06	0.000	0.000
					B	0.000	46.004		12.68	0.000	0.000
					C	0.000	16.568		35.21	0.000	0.000
T2 150.00-140.00	145.00	1.526	28	66.055	A	5.292	37.009	11.905	28.14	0.000	0.000
					B	5.476	33.509		30.54	0.000	0.000
					C	5.476	13.755		61.91	0.000	0.000
T3 140.00-120.00	130.00	1.48	27	162.111	A	10.178	78.107	23.165	26.24	0.000	0.000
					B	9.618	88.149		23.69	0.000	0.000
					C	10.467	34.200		51.86	0.000	0.000
T4 120.00-100.00	110.00	1.411	26	202.528	A	13.676	106.080	24.703	20.63	0.000	0.000
					B	12.753	113.432		19.58	0.000	0.000
					C	13.085	91.822		23.55	0.000	0.000
T5 100.00-90.00	95.00	1.353	25	116.264	A	6.447	74.051	12.351	15.34	0.000	0.000
					B	6.082	56.716		19.67	0.000	0.000
					C	6.098	68.599		16.54	0.000	0.000
T6 90.00-80.00	85.00	1.31	24	126.517	A	6.849	74.983	13.283	16.23	0.000	0.000
					B	6.499	57.648		20.71	0.000	0.000
					C	6.420	72.265		16.88	0.000	0.000
T7 80.00-60.00	70.00	1.24	23	283.450	A	14.936	151.524	28.124	16.90	0.000	0.000
					B	14.269	116.854		21.45	0.000	0.000
					C	13.982	150.334		17.12	0.000	0.000
T8 60.00-40.00	50.00	1.126	21	323.362	A	19.403	151.709	28.309	16.54	0.000	0.000
					B	18.662	117.039		20.86	0.000	0.000
					C	18.343	150.519		16.76	0.000	0.000
T9 40.00-20.00	30.00	1	18	363.756	A	21.437	154.657	29.807	16.93	0.000	0.000
					B	20.722	119.987		21.18	0.000	0.000
					C	20.414	152.017		17.29	0.000	0.000
T10 20.00-0.00	10.00	1	18	404.134	A	26.964	113.371	31.276	22.29	0.000	0.000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	18 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	z	K _Z	q _z	A _G	F _a	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
					B	26.446	90.836		26.67	0.000	0.000
					C	26.223	110.713		22.84	0.000	0.000

Tower Pressure - With Ice

$G_H = 1.125$

Section Elevation	z	K _Z	q _z	t _z	A _G	F _a	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	in	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T1 170.00-150.00	160.00	1.57	22	0.5000	104.583	A	3.517	82.422	9.167	10.67	0.000	0.000
						B	0.000	74.710		12.27	0.000	0.000
						C	3.517	27.757		29.31	0.000	0.000
T2 150.00-140.00	145.00	1.526	21	0.5000	66.890	A	6.957	58.049	20.033	30.82	0.000	0.000
						B	5.476	53.914		33.73	0.000	0.000
						C	7.234	23.901		64.34	0.000	0.000
T3 140.00-120.00	130.00	1.48	21	0.5000	163.780	A	13.549	124.661	38.924	28.16	0.000	0.000
						B	24.452	128.129		25.51	0.000	0.000
						C	13.984	54.140		57.14	0.000	0.000
T4 120.00-100.00	110.00	1.411	20	0.5000	204.197	A	17.047	155.568	40.814	23.64	0.000	0.000
						B	33.947	154.770		21.63	0.000	0.000
						C	25.867	115.341		28.90	0.000	0.000
T5 100.00-90.00	95.00	1.353	19	0.5000	117.098	A	8.148	100.462	20.407	18.79	0.000	0.000
						B	16.813	77.332		21.68	0.000	0.000
						C	14.140	81.784		21.27	0.000	0.000
T6 90.00-80.00	85.00	1.31	18	0.5000	127.351	A	8.553	101.798	21.609	19.58	0.000	0.000
						B	17.250	78.679		22.53	0.000	0.000
						C	16.035	85.234		21.34	0.000	0.000
T7 80.00-60.00	70.00	1.24	17	0.5000	285.119	A	18.347	206.096	45.303	20.18	0.000	0.000
						B	35.816	159.883		23.15	0.000	0.000
						C	34.534	178.571		21.26	0.000	0.000
T8 60.00-40.00	50.00	1.126	16	0.5000	325.031	A	22.803	207.064	45.704	19.88	0.000	0.000
						B	40.107	160.874		22.74	0.000	0.000
						C	38.778	179.569		20.93	0.000	0.000
T9 40.00-20.00	30.00	1	14	0.5000	365.425	A	24.841	212.976	47.784	20.09	0.000	0.000
						B	42.203	166.803		22.86	0.000	0.000
						C	40.890	182.252		21.41	0.000	0.000
T10 20.00-0.00	10.00	1	14	0.5000	405.803	A	29.168	162.109	49.862	26.07	0.000	0.000
						B	40.336	132.104		28.92	0.000	0.000
						C	39.449	140.036		27.78	0.000	0.000

Tower Pressure - Service

$G_H = 1.125$

Section Elevation	z	K _Z	q _z	A _G	F _a	A _F	A _R	A _{leg}	Leg %	C _A A _A In Face	C _A A _A Out Face
ft	ft		psf	ft ²	e	ft ²	ft ²	ft ²		ft ²	ft ²
T1 170.00-150.00	160.00	1.57	10	102.917	A	0.000	52.765	5.833	11.06	0.000	0.000
					B	0.000	46.004		12.68	0.000	0.000

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 19 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation ft	z ft	K _Z	q _z psf	A _G ft ²	F _a c e	A _F ft ²	A _R ft ²	A _{wg} ft ²	Leg %	C _i A _i In Face ft ²	C _o A _o Out Face ft ²
T2 150.00-140.00	145.00	1.526	10	66.055	C	0.000	16.568	11.905	35.21	0.000	0.000
					A	5.292	37.009		28.14	0.000	0.000
					B	5.476	33.509		30.54	0.000	0.000
T3 140.00-120.00	130.00	1.48	9	162.111	C	5.476	13.755	23.165	61.91	0.000	0.000
					A	10.178	78.107		26.24	0.000	0.000
					B	9.618	88.149		23.69	0.000	0.000
T4 120.00-100.00	110.00	1.411	9	202.528	C	10.467	34.200	24.703	51.86	0.000	0.000
					A	13.676	106.080		20.63	0.000	0.000
					B	12.753	113.432		19.58	0.000	0.000
T5 100.00-90.00	95.00	1.353	9	116.264	C	13.085	91.822	12.351	23.55	0.000	0.000
					A	6.447	74.051		15.34	0.000	0.000
					B	6.082	56.716		19.67	0.000	0.000
T6 90.00-80.00	85.00	1.31	8	126.517	C	6.098	68.599	13.283	16.54	0.000	0.000
					A	6.849	74.983		16.23	0.000	0.000
					B	6.499	57.648		20.71	0.000	0.000
T7 80.00-60.00	70.00	1.24	8	283.450	C	6.420	72.265	28.124	16.88	0.000	0.000
					A	14.936	151.524		16.90	0.000	0.000
					B	14.269	116.854		21.45	0.000	0.000
T8 60.00-40.00	50.00	1.126	7	323.362	C	13.982	150.334	28.309	17.12	0.000	0.000
					A	19.403	151.709		16.54	0.000	0.000
					B	18.662	117.039		20.86	0.000	0.000
T9 40.00-20.00	30.00	1	6	363.756	C	18.343	150.519	29.807	16.76	0.000	0.000
					A	21.437	154.657		16.93	0.000	0.000
					B	20.722	119.987		21.18	0.000	0.000
T10 20.00-0.00	10.00	1	6	404.134	C	20.414	152.017	31.276	17.29	0.000	0.000
					A	26.964	113.371		22.29	0.000	0.000
					B	26.446	90.836		26.67	0.000	0.000
					C	26.223	110.713		22.84	0.000	0.000

Tower Forces - No Ice - Wind Normal To Face

Section Elevation ft	Add Weight K	Self Weight K	F _a c e	e	C _F	R _R	D _F	D _R	A _E ft ²	F K	w plf	Ctrl Face
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704			37.149	2.29	114.29	A
			B	0.447	1.978	0.672			30.910			
			C	0.161	2.732	0.583			9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779			34.128	1.93	193.38	A
			B	0.59	1.81	0.748			30.529			
			C	0.291	2.32	0.613			13.910			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721			66.514	4.23	211.37	B
			B	0.603	1.802	0.755			76.214			
			C	0.276	2.363	0.609			31.285			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748			93.057	5.25	262.50	B
			B	0.623	1.792	0.768			99.866			
			C	0.518	1.878	0.707			77.988			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814			66.761	3.34	333.60	A
			B	0.54	1.853	0.719			46.850			
			C	0.642	1.784	0.781			59.641			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783			65.589	3.19	318.69	A
			B	0.507	1.891	0.701			46.917			
			C	0.622	1.792	0.767			61.867			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746			127.956	5.98	299.04	A
			B	0.463	1.953	0.679			93.629			
			C	0.58	1.818	0.741			125.437			
T8	1.26	4.45	A	0.529	1.865	0.713			127.543	5.57	278.60	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	20 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _s	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
60.00-40.00			B	0.42	2.026	0.66			95.887			
			C	0.522	1.873	0.709			125.073			
T9	1.27	5.44	A	0.484	1.922	0.69			128.076	5.12	255.98	A
40.00-20.00			B	0.387	2.091	0.646			98.271			
			C	0.474	1.936	0.685			124.485			
T10	0.83	6.08	A	0.347	2.178	0.631			98.557	4.47	223.27	A
20.00-0.00			B	0.29	2.322	0.613			82.124			
			C	0.339	2.198	0.629			95.812			
Sum Weight:	7.61	30.71						OTM	3256.52 kip-ft	41.36		

Tower Forces - No Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _s	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.825		37.149	2.29	114.29	A
170.00-150.00			B	0.447	1.978	0.672	0.825		30.910			
			C	0.161	2.732	0.583	0.825		9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.825		33.202	1.88	188.14	A
150.00-140.00			B	0.59	1.81	0.748	0.825		29.570			
			C	0.291	2.32	0.613	0.825		12.952			
T3	0.44	2.09	A	0.545	1.849	0.721	0.825		64.733	4.13	206.70	B
140.00-120.00			B	0.603	1.802	0.755	0.825		74.531			
			C	0.276	2.363	0.609	0.825		29.454			
T4	0.91	2.80	A	0.591	1.81	0.748	0.825		90.664	5.13	256.63	B
120.00-100.00			B	0.623	1.792	0.768	0.825		97.634			
			C	0.518	1.878	0.707	0.825		75.698			
T5	0.62	1.48	A	0.692	1.776	0.814	0.825		65.632	3.28	327.96	A
100.00-90.00			B	0.54	1.853	0.719	0.825		45.785			
			C	0.642	1.784	0.781	0.825		58.574			
T6	0.63	1.76	A	0.647	1.782	0.783	0.825		64.390	3.13	312.87	A
90.00-80.00			B	0.507	1.891	0.701	0.825		45.780			
			C	0.622	1.792	0.767	0.825		60.743			
T7	1.26	4.33	A	0.587	1.812	0.746	0.825		125.342	5.86	292.93	A
80.00-60.00			B	0.463	1.953	0.679	0.825		91.132			
			C	0.58	1.818	0.741	0.825		122.990			
T8	1.26	4.45	A	0.529	1.865	0.713	0.825		124.147	5.42	271.18	A
60.00-40.00			B	0.42	2.026	0.66	0.825		92.621			
			C	0.522	1.873	0.709	0.825		121.863			
T9	1.27	5.44	A	0.484	1.922	0.69	0.825		124.325	4.97	248.49	A
40.00-20.00			B	0.387	2.091	0.646	0.825		94.645			
			C	0.474	1.936	0.685	0.825		120.912			
T10	0.83	6.08	A	0.347	2.178	0.631	0.825		93.838	4.25	212.58	A
20.00-0.00			B	0.29	2.322	0.613	0.825		77.496			
			C	0.339	2.198	0.629	0.825		91.223			
Sum Weight:	7.61	30.71						OTM	3190.95 kip-ft	40.35		

Tower Forces - No Ice - Wind 60 To Face

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 21 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _R	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.8		37.149	2.29	114.29	A
			B	0.447	1.978	0.672	0.8		30.910			
			C	0.161	2.732	0.583	0.8		9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.8		33.069	1.87	187.39	A
			B	0.59	1.81	0.748	0.8		29.433			
			C	0.291	2.32	0.613	0.8		12.815			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.8		64.478	4.12	206.03	B
			B	0.603	1.802	0.755	0.8		74.291			
			C	0.276	2.363	0.609	0.8		29.192			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.8		90.322	5.12	255.80	B
			B	0.623	1.792	0.768	0.8		97.316			
			C	0.518	1.878	0.707	0.8		75.371			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.8		65.471	3.27	327.16	A
			B	0.54	1.853	0.719	0.8		45.633			
			C	0.642	1.784	0.781	0.8		58.421			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.8		64.219	3.12	312.03	A
			B	0.507	1.891	0.701	0.8		45.617			
			C	0.622	1.792	0.767	0.8		60.583			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.8		124.968	5.84	292.06	A
			B	0.463	1.953	0.679	0.8		90.775			
			C	0.58	1.818	0.741	0.8		122.641			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.8		123.662	5.40	270.13	A
			B	0.42	2.026	0.66	0.8		92.154			
			C	0.522	1.873	0.709	0.8		121.404			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.8		123.789	4.95	247.41	A
			B	0.387	2.091	0.646	0.8		94.127			
			C	0.474	1.936	0.685	0.8		120.402			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.8		93.164	4.22	211.05	A
			B	0.29	2.322	0.613	0.8		76.835			
			C	0.339	2.198	0.629	0.8		90.567			
Sum Weight:	7.61	30.71						OTM	3181.59 kip-ft	40.20		

Tower Forces - No Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.85		37.149	2.29	114.29	A
			B	0.447	1.978	0.672	0.85		30.910			
			C	0.161	2.732	0.583	0.85		9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.85		33.334	1.89	188.89	A
			B	0.59	1.81	0.748	0.85		29.707			
			C	0.291	2.32	0.613	0.85		13.089			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.85		64.987	4.15	207.37	B
			B	0.603	1.802	0.755	0.85		74.772			
			C	0.276	2.363	0.609	0.85		29.715			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.85		91.006	5.15	257.47	B
			B	0.623	1.792	0.768	0.85		97.953			
			C	0.518	1.878	0.707	0.85		76.025			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.85		65.794	3.29	328.77	A
			B	0.54	1.853	0.719	0.85		45.937			
			C	0.642	1.784	0.781	0.85		58.726			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.85		64.561	3.14	313.70	A
			B	0.507	1.891	0.701	0.85		45.942			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	Page	
	PiROD U20'-0"x170' Lattice Tower		22 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD	

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T7 80.00-60.00	1.26	4.33	C	0.622	1.792	0.767	0.85		60.904	5.88	293.80	A
			A	0.587	1.812	0.746	0.85		125.715			
			B	0.463	1.953	0.679	0.85		91.488			
T8 60.00-40.00	1.26	4.45	C	0.58	1.818	0.741	0.85		123.340	5.44	272.24	A
			A	0.529	1.865	0.713	0.85		124.632			
			B	0.42	2.026	0.66	0.85		93.087			
T9 40.00-20.00	1.27	5.44	C	0.522	1.873	0.709	0.85		122.322	4.99	249.56	A
			A	0.484	1.922	0.69	0.85		124.860			
			B	0.387	2.091	0.646	0.85		95.163			
T10 20.00-0.00	0.83	6.08	C	0.474	1.936	0.685	0.85		121.422	4.28	214.10	A
			A	0.347	2.178	0.631	0.85		94.512			
			B	0.29	2.322	0.613	0.85		78.157			
Sum Weight:	7.61	30.71	C	0.339	2.198	0.629	0.85		91.878	40.49		
								OTM	3200.32 kip-ft			

Tower Forces - With Ice - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914			78.881	3.54	177.15	A
			B	0.714	1.778	0.83			62.028			
			C	0.299	2.299	0.616			20.604			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1			65.006	3.16	316.37	A
			B	0.888	1.907	0.972			57.882			
			C	0.465	1.949	0.68			23.498			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933			129.881	6.95	347.34	B
			B	0.932	1.972	1			152.582			
			C	0.416	2.033	0.658			49.621			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934			162.417	8.14	407.09	B
			B	0.924	1.96	1			188.717			
			C	0.692	1.776	0.814			119.741			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1			108.610	4.51	450.57	A
			B	0.804	1.819	0.9			86.385			
			C	0.819	1.831	0.912			88.747			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953			105.559	4.06	405.79	A
			B	0.753	1.789	0.859			84.866			
			C	0.795	1.813	0.892			92.106			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886			200.955	7.02	351.19	A
			B	0.686	1.776	0.81			165.364			
			C	0.747	1.786	0.855			187.195			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825			193.648	6.04	302.22	A
			B	0.618	1.794	0.765			163.176			
			C	0.672	1.777	0.8			182.461			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786			192.241	5.34	267.14	A
			B	0.572	1.824	0.737			165.109			
			C	0.611	1.798	0.76			179.432			
T10 20.00-0.00	2.30	8.52	A	0.471	1.94	0.683			139.939	4.24	211.79	A
			B	0.425	2.017	0.662			127.801			
			C	0.442	1.986	0.67			133.241			
Sum Weight:	21.02	45.71						OTM	4593.81 kip-ft	53.01		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	23 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Tower Forces - With Ice - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.825		78.265	3.52	175.77	A
			B	0.714	1.778	0.83	0.825		62.028			
			C	0.299	2.299	0.616	0.825		19.988			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.825		63.789	3.10	310.45	A
			B	0.888	1.907	0.972	0.825		56.923			
			C	0.465	1.949	0.68	0.825		22.232			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.825		127.510	6.75	337.60	B
			B	0.932	1.972	1	0.825		148.302			
			C	0.416	2.033	0.658	0.825		47.174			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.825		159.433	7.89	394.28	B
			B	0.924	1.96	1	0.825		182.776			
			C	0.692	1.776	0.814	0.825		115.214			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	0.825		107.184	4.45	444.65	A
			B	0.804	1.819	0.9	0.825		83.443			
			C	0.819	1.831	0.912	0.825		86.273			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	0.825		104.062	4.00	400.04	A
			B	0.753	1.789	0.859	0.825		81.847			
			C	0.795	1.813	0.892	0.825		89.300			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	0.825		197.745	6.91	345.58	A
			B	0.686	1.776	0.81	0.825		159.096			
			C	0.747	1.786	0.855	0.825		181.152			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	0.825		189.657	5.92	295.99	A
			B	0.618	1.794	0.765	0.825		156.157			
			C	0.672	1.777	0.8	0.825		175.675			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	0.825		187.894	5.22	261.10	A
			B	0.572	1.824	0.737	0.825		157.723			
			C	0.611	1.798	0.76	0.825		172.276			
T10 20.00-0.00	2.30	8.52	A	0.471	1.94	0.683	0.825		134.834	4.08	204.06	A
			B	0.425	2.017	0.662	0.825		120.742			
			C	0.442	1.986	0.67	0.825		126.338			
Sum Weight:	21.02	45.71						OTM	4497.51 kip-ft	51.84		

Tower Forces - With Ice - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.8		78.177	3.51	175.57	A
			B	0.714	1.778	0.83	0.8		62.028			
			C	0.299	2.299	0.616	0.8		19.901			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.8		63.615	3.10	309.60	A
			B	0.888	1.907	0.972	0.8		56.786			
			C	0.465	1.949	0.68	0.8		22.051			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.8		127.171	6.72	336.21	B
			B	0.932	1.972	1	0.8		147.691			
			C	0.416	2.033	0.658	0.8		46.824			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.8		159.007	7.85	392.45	B
			B	0.924	1.96	1	0.8		181.928			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	Page
	Project	Date
	Client	Designed by
	PIROD U20'-0"x170' Lattice Tower	24 of 43
	TWS-027 Rev. 1 / Cromwell, CT Tower	11:32:54 09/23/14
	Sprint / T-Mobile (TWS-027)/(EBI-002)	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T5 100.00-90.00	1.67	2.39	C	0.692	1.776	0.814	0.8		114.568	4.44	443.81	A
			A	0.928	1.966	1	0.8		106.980			
			B	0.804	1.819	0.9	0.8		83.022			
T6 90.00-80.00	1.71	2.70	C	0.819	1.831	0.912	0.8		85.919	3.99	399.21	A
			A	0.867	1.88	0.953	0.8		103.848			
			B	0.753	1.789	0.859	0.8		81.415			
T7 80.00-60.00	3.48	6.30	C	0.795	1.813	0.892	0.8		88.899	6.90	344.78	A
			A	0.787	1.807	0.886	0.8		197.286			
			B	0.686	1.776	0.81	0.8		158.201			
T8 60.00-40.00	3.48	6.58	C	0.747	1.786	0.855	0.8		180.289	5.90	295.10	A
			A	0.707	1.777	0.825	0.8		189.087			
			B	0.618	1.794	0.765	0.8		155.155			
T9 40.00-20.00	3.51	7.67	C	0.672	1.777	0.8	0.8		174.705	5.20	260.23	A
			A	0.651	1.781	0.786	0.8		187.273			
			B	0.572	1.824	0.737	0.8		156.668			
T10 20.00-0.00	2.30	8.52	C	0.611	1.798	0.76	0.8		171.254	4.06	202.96	A
			A	0.471	1.94	0.683	0.8		134.105			
			B	0.425	2.017	0.662	0.8		119.734			
Sum Weight:	21.02	45.71	C	0.442	1.986	0.67	0.8		125.352	51.67		
								OTM	4483.75 kip-ft			

Tower Forces - With Ice - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.67	1.49	A	0.822	1.834	0.914	0.85		78.353	3.52	175.96	A
			B	0.714	1.778	0.83	0.85		62.028			
			C	0.299	2.299	0.616	0.85		20.076			
T2 150.00-140.00	0.43	1.64	A	0.972	2.044	1	0.85		63.963	3.11	311.30	A
			B	0.888	1.907	0.972	0.85		57.060			
			C	0.465	1.949	0.68	0.85		22.413			
T3 140.00-120.00	1.28	3.77	A	0.844	1.855	0.933	0.85		127.849	6.78	338.99	B
			B	0.932	1.972	1	0.85		148.914			
			C	0.416	2.033	0.658	0.85		47.523			
T4 120.00-100.00	2.50	4.64	A	0.845	1.857	0.934	0.85		159.860	7.92	396.11	B
			B	0.924	1.96	1	0.85		183.625			
			C	0.692	1.776	0.814	0.85		115.861			
T5 100.00-90.00	1.67	2.39	A	0.928	1.966	1	0.85		107.387	4.45	445.50	A
			B	0.804	1.819	0.9	0.85		83.863			
			C	0.819	1.831	0.912	0.85		86.626			
T6 90.00-80.00	1.71	2.70	A	0.867	1.88	0.953	0.85		104.276	4.01	400.86	A
			B	0.753	1.789	0.859	0.85		82.278			
			C	0.795	1.813	0.892	0.85		89.701			
T7 80.00-60.00	3.48	6.30	A	0.787	1.807	0.886	0.85		198.203	6.93	346.38	A
			B	0.686	1.776	0.81	0.85		159.991			
			C	0.747	1.786	0.855	0.85		182.015			
T8 60.00-40.00	3.48	6.58	A	0.707	1.777	0.825	0.85		190.227	5.94	296.88	A
			B	0.618	1.794	0.765	0.85		157.160			
			C	0.672	1.777	0.8	0.85		176.644			
T9 40.00-20.00	3.51	7.67	A	0.651	1.781	0.786	0.85		188.515	5.24	261.96	A
			B	0.572	1.824	0.737	0.85		158.778			
			C	0.611	1.798	0.76	0.85		173.298			
T10	2.30	8.52	A	0.471	1.94	0.683	0.85		135.564	4.10	205.17	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	25 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
20.00-0.00			B	0.425	2.017	0.662	0.85		121.751			
			C	0.442	1.986	0.67	0.85		127.324			
Sum Weight:	21.02	45.71						OTM	4511.26 kip-ft	52.01		

Tower Forces - Service - Wind Normal To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704			37.149	0.79	39.55	A
170.00-150.00			B	0.447	1.978	0.672			30.910			
			C	0.161	2.732	0.583			9.663			
T2	0.16	1.12	A	0.64	1.785	0.779			34.128	0.67	66.92	A
150.00-140.00			B	0.59	1.81	0.748			30.529			
			C	0.291	2.32	0.613			13.910			
T3	0.44	2.09	A	0.545	1.849	0.721			66.514	1.46	73.14	B
140.00-120.00			B	0.603	1.802	0.755			76.214			
			C	0.276	2.363	0.609			31.285			
T4	0.91	2.80	A	0.591	1.81	0.748			93.057	1.82	90.83	B
120.00-100.00			B	0.623	1.792	0.768			99.866			
			C	0.518	1.878	0.707			77.988			
T5	0.62	1.48	A	0.692	1.776	0.814			66.761	1.15	115.43	A
100.00-90.00			B	0.54	1.853	0.719			46.850			
			C	0.642	1.784	0.781			59.641			
T6	0.63	1.76	A	0.647	1.782	0.783			65.589	1.10	110.27	A
90.00-80.00			B	0.507	1.891	0.701			46.917			
			C	0.622	1.792	0.767			61.867			
T7	1.26	4.33	A	0.587	1.812	0.746			127.956	2.07	103.47	A
80.00-60.00			B	0.463	1.953	0.679			93.629			
			C	0.58	1.818	0.741			125.437			
T8	1.26	4.45	A	0.529	1.865	0.713			127.543	1.93	96.40	A
60.00-40.00			B	0.42	2.026	0.66			95.887			
			C	0.522	1.873	0.709			125.073			
T9	1.27	5.44	A	0.484	1.922	0.69			128.076	1.77	88.58	A
40.00-20.00			B	0.387	2.091	0.646			98.271			
			C	0.474	1.936	0.685			124.485			
T10	0.83	6.08	A	0.347	2.178	0.631			98.557	1.55	77.25	A
20.00-0.00			B	0.29	2.322	0.613			82.124			
			C	0.339	2.198	0.629			95.812			
Sum Weight:	7.61	30.71						OTM	1126.82 kip-ft	14.31		

Tower Forces - Service - Wind 45 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.825		37.149	0.79	39.55	A

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PiROD U20'-0"x170' Lattice Tower	Page 26 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
170.00-150.00			B	0.447	1.978	0.672	0.825		30.910			
			C	0.161	2.732	0.583	0.825		9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.825		33.202	0.65	65.10	A
150.00-140.00			B	0.59	1.81	0.748	0.825		29.570			
			C	0.291	2.32	0.613	0.825		12.952			
T3	0.44	2.09	A	0.545	1.849	0.721	0.825		64.733	1.43	71.52	B
140.00-120.00			B	0.603	1.802	0.755	0.825		74.531			
			C	0.276	2.363	0.609	0.825		29.454			
T4	0.91	2.80	A	0.591	1.81	0.748	0.825		90.664	1.78	88.80	B
120.00-100.00			B	0.623	1.792	0.768	0.825		97.634			
			C	0.518	1.878	0.707	0.825		75.698			
T5	0.62	1.48	A	0.692	1.776	0.814	0.825		65.632	1.13	113.48	A
100.00-90.00			B	0.54	1.853	0.719	0.825		45.785			
			C	0.642	1.784	0.781	0.825		58.574			
T6	0.63	1.76	A	0.647	1.782	0.783	0.825		64.390	1.08	108.26	A
90.00-80.00			B	0.507	1.891	0.701	0.825		45.780			
			C	0.622	1.792	0.767	0.825		60.743			
T7	1.26	4.33	A	0.587	1.812	0.746	0.825		125.342	2.03	101.36	A
80.00-60.00			B	0.463	1.953	0.679	0.825		91.132			
			C	0.58	1.818	0.741	0.825		122.990			
T8	1.26	4.45	A	0.529	1.865	0.713	0.825		124.147	1.88	93.84	A
60.00-40.00			B	0.42	2.026	0.66	0.825		92.621			
			C	0.522	1.873	0.709	0.825		121.863			
T9	1.27	5.44	A	0.484	1.922	0.69	0.825		124.325	1.72	85.98	A
40.00-20.00			B	0.387	2.091	0.646	0.825		94.645			
			C	0.474	1.936	0.685	0.825		120.912			
T10	0.83	6.08	A	0.347	2.178	0.631	0.825		93.838	1.47	73.56	A
20.00-0.00			B	0.29	2.322	0.613	0.825		77.496			
			C	0.339	2.198	0.629	0.825		91.223			
Sum Weight:	7.61	30.71						OTM	1104.14 kip-ft	13.96		

Tower Forces - Service - Wind 60 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1	0.24	1.16	A	0.513	1.884	0.704	0.8		37.149	0.79	39.55	A
170.00-150.00			B	0.447	1.978	0.672	0.8		30.910			
			C	0.161	2.732	0.583	0.8		9.663			
T2	0.16	1.12	A	0.64	1.785	0.779	0.8		33.069	0.65	64.84	A
150.00-140.00			B	0.59	1.81	0.748	0.8		29.433			
			C	0.291	2.32	0.613	0.8		12.815			
T3	0.44	2.09	A	0.545	1.849	0.721	0.8		64.478	1.43	71.29	B
140.00-120.00			B	0.603	1.802	0.755	0.8		74.291			
			C	0.276	2.363	0.609	0.8		29.192			
T4	0.91	2.80	A	0.591	1.81	0.748	0.8		90.322	1.77	88.51	B
120.00-100.00			B	0.623	1.792	0.768	0.8		97.316			
			C	0.518	1.878	0.707	0.8		75.371			
T5	0.62	1.48	A	0.692	1.776	0.814	0.8		65.471	1.13	113.20	A
100.00-90.00			B	0.54	1.853	0.719	0.8		45.633			
			C	0.642	1.784	0.781	0.8		58.421			
T6	0.63	1.76	A	0.647	1.782	0.783	0.8		64.219	1.08	107.97	A
90.00-80.00			B	0.507	1.891	0.701	0.8		45.617			
			C	0.622	1.792	0.767	0.8		60.583			

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 27 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.8		124.968	2.02	101.06	A
			B	0.463	1.953	0.679	0.8		90.775			
			C	0.58	1.818	0.741	0.8		122.641			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.8		123.662	1.87	93.47	A
			B	0.42	2.026	0.66	0.8		92.154			
			C	0.522	1.873	0.709	0.8		121.404			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.8		123.789	1.71	85.61	A
			B	0.387	2.091	0.646	0.8		94.127			
			C	0.474	1.936	0.685	0.8		120.402			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.8		93.164	1.46	73.03	A
			B	0.29	2.322	0.613	0.8		76.835			
			C	0.339	2.198	0.629	0.8		90.567			
Sum Weight:	7.61	30.71						OTM	1100.90 kip-ft	13.91		

Tower Forces - Service - Wind 90 To Face

Section Elevation	Add Weight	Self Weight	F a c e	e	C _F	R _R	D _F	D _R	A _E	F	w	Ctrl. Face
ft	K	K							ft ²	K	plf	
T1 170.00-150.00	0.24	1.16	A	0.513	1.884	0.704	0.85		37.149	0.79	39.55	A
			B	0.447	1.978	0.672	0.85		30.910			
			C	0.161	2.732	0.583	0.85		9.663			
T2 150.00-140.00	0.16	1.12	A	0.64	1.785	0.779	0.85		33.334	0.65	65.36	A
			B	0.59	1.81	0.748	0.85		29.707			
			C	0.291	2.32	0.613	0.85		13.089			
T3 140.00-120.00	0.44	2.09	A	0.545	1.849	0.721	0.85		64.987	1.44	71.75	B
			B	0.603	1.802	0.755	0.85		74.772			
			C	0.276	2.363	0.609	0.85		29.715			
T4 120.00-100.00	0.91	2.80	A	0.591	1.81	0.748	0.85		91.006	1.78	89.09	B
			B	0.623	1.792	0.768	0.85		97.953			
			C	0.518	1.878	0.707	0.85		76.025			
T5 100.00-90.00	0.62	1.48	A	0.692	1.776	0.814	0.85		65.794	1.14	113.76	A
			B	0.54	1.853	0.719	0.85		45.937			
			C	0.642	1.784	0.781	0.85		58.726			
T6 90.00-80.00	0.63	1.76	A	0.647	1.782	0.783	0.85		64.561	1.09	108.55	A
			B	0.507	1.891	0.701	0.85		45.942			
			C	0.622	1.792	0.767	0.85		60.904			
T7 80.00-60.00	1.26	4.33	A	0.587	1.812	0.746	0.85		125.715	2.03	101.66	A
			B	0.463	1.953	0.679	0.85		91.488			
			C	0.58	1.818	0.741	0.85		123.340			
T8 60.00-40.00	1.26	4.45	A	0.529	1.865	0.713	0.85		124.632	1.88	94.20	A
			B	0.42	2.026	0.66	0.85		93.087			
			C	0.522	1.873	0.709	0.85		122.322			
T9 40.00-20.00	1.27	5.44	A	0.484	1.922	0.69	0.85		124.860	1.73	86.35	A
			B	0.387	2.091	0.646	0.85		95.163			
			C	0.474	1.936	0.685	0.85		121.422			
T10 20.00-0.00	0.83	6.08	A	0.347	2.178	0.631	0.85		94.512	1.48	74.08	A
			B	0.29	2.322	0.613	0.85		78.157			
			C	0.339	2.198	0.629	0.85		91.878			
Sum Weight:	7.61	30.71						OTM	1107.38 kip-ft	14.01		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	28 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Force Totals

Load Case	Vertical Forces	Sum of Forces X	Sum of Forces Z	Sum of Overturning Moments, M _x	Sum of Overturning Moments, M _y	Sum of Torques
	K	K	K	kip-ft	kip-ft	kip-ft
Leg Weight	19.74					
Bracing Weight	10.97					
Total Member Self-Weight	30.71			-2.00	10.22	
Total Weight	51.55			-2.00	10.22	
Wind 0 deg - No Ice		-0.03	-59.60	-5708.32	12.35	-22.92
Wind 30 deg - No Ice		29.27	-50.81	-4890.66	-2805.15	-22.82
Wind 45 deg - No Ice		41.56	-41.28	-3973.98	-3999.37	-20.02
Wind 60 deg - No Ice		50.83	-29.04	-2795.45	-4898.94	-15.82
Wind 90 deg - No Ice		58.77	0.23	26.18	-5648.79	-5.72
Wind 120 deg - No Ice		51.69	30.08	2874.97	-4945.01	6.21
Wind 135 deg - No Ice		41.56	41.56	3993.08	-4000.25	11.52
Wind 150 deg - No Ice		29.55	50.94	4892.75	-2842.34	16.76
Wind 180 deg - No Ice		0.21	58.66	5652.84	-15.14	24.54
Wind 210 deg - No Ice		-29.36	50.86	4884.68	2840.92	23.16
Wind 225 deg - No Ice		-41.43	41.46	3982.65	4006.43	20.78
Wind 240 deg - No Ice		-51.57	29.98	2864.78	4952.07	18.07
Wind 270 deg - No Ice		-58.70	0.09	11.35	5659.73	7.95
Wind 300 deg - No Ice		-50.74	-29.22	-2816.52	4905.15	-3.95
Wind 315 deg - No Ice		-41.50	-41.41	-3988.74	4008.72	-9.92
Wind 330 deg - No Ice		-29.33	-50.88	-4897.98	2829.75	-16.05
Member Ice	15.00					
Total Weight Ice	85.61			-2.54	25.10	
Wind 0 deg - Ice		-0.02	-69.88	-6864.28	26.49	-19.54
Wind 30 deg - Ice		34.37	-59.62	-5870.13	-3357.00	-25.65
Wind 45 deg - Ice		48.70	-48.47	-4773.44	-4775.85	-25.79
Wind 60 deg - Ice		59.54	-34.13	-3360.98	-5848.07	-24.11
Wind 90 deg - Ice		68.91	0.18	19.71	-6761.26	-17.16
Wind 120 deg - Ice		60.58	35.16	3446.86	-5927.99	-5.57
Wind 135 deg - Ice		48.70	48.69	4786.02	-4776.18	1.27
Wind 150 deg - Ice		34.59	59.71	5869.30	-3386.36	8.22
Wind 180 deg - Ice		0.16	68.72	6767.76	5.09	20.94
Wind 210 deg - Ice		-34.44	59.65	5863.16	3419.61	25.93
Wind 225 deg - Ice		-48.60	48.61	4778.12	4815.41	26.40
Wind 240 deg - Ice		-60.49	35.08	3439.26	5967.79	26.20
Wind 270 deg - Ice		-68.86	0.07	8.47	6803.85	18.94
Wind 300 deg - Ice		-59.46	-34.27	-3377.31	5886.54	7.00
Wind 315 deg - Ice		-48.65	-48.57	-4784.82	4816.70	0.01
Wind 330 deg - Ice		-34.41	-59.67	-5875.67	3409.98	-7.66
Total Weight	51.55			-2.00	10.22	
Wind 0 deg - Service		-0.01	-20.62	-1978.70	2.07	-7.93
Wind 30 deg - Service		10.13	-17.58	-1695.77	-972.85	-7.90
Wind 45 deg - Service		14.38	-14.28	-1378.58	-1386.07	-6.93
Wind 60 deg - Service		17.59	-10.05	-970.79	-1697.34	-5.47
Wind 90 deg - Service		20.33	0.08	5.56	-1956.81	-1.98
Wind 120 deg - Service		17.89	10.41	991.30	-1713.28	2.15
Wind 135 deg - Service		14.38	14.38	1378.19	-1386.38	3.99
Wind 150 deg - Service		10.23	17.63	1689.49	-985.71	5.80
Wind 180 deg - Service		0.07	20.30	1952.50	-7.45	8.49
Wind 210 deg - Service		-10.16	17.60	1686.70	980.81	8.01
Wind 225 deg - Service		-14.34	14.35	1374.58	1384.10	7.19
Wind 240 deg - Service		-17.85	10.37	987.77	1711.31	6.25
Wind 270 deg - Service		-20.31	0.03	0.42	1956.18	2.75
Wind 300 deg - Service		-17.56	-10.11	-978.08	1695.07	-1.37
Wind 315 deg - Service		-14.36	-14.33	-1383.69	1384.89	-3.43
Wind 330 deg - Service		-10.15	-17.61	-1698.30	976.95	-5.55

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 29 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Load Combinations

Comb No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 45 deg - No Ice
5	Dead+Wind 60 deg - No Ice
6	Dead+Wind 90 deg - No Ice
7	Dead+Wind 120 deg - No Ice
8	Dead+Wind 135 deg - No Ice
9	Dead+Wind 150 deg - No Ice
10	Dead+Wind 180 deg - No Ice
11	Dead+Wind 210 deg - No Ice
12	Dead+Wind 225 deg - No Ice
13	Dead+Wind 240 deg - No Ice
14	Dead+Wind 270 deg - No Ice
15	Dead+Wind 300 deg - No Ice
16	Dead+Wind 315 deg - No Ice
17	Dead+Wind 330 deg - No Ice
18	Dead+Ice+Temp
19	Dead+Wind 0 deg+Ice+Temp
20	Dead+Wind 30 deg+Ice+Temp
21	Dead+Wind 45 deg+Ice+Temp
22	Dead+Wind 60 deg+Ice+Temp
23	Dead+Wind 90 deg+Ice+Temp
24	Dead+Wind 120 deg+Ice+Temp
25	Dead+Wind 135 deg+Ice+Temp
26	Dead+Wind 150 deg+Ice+Temp
27	Dead+Wind 180 deg+Ice+Temp
28	Dead+Wind 210 deg+Ice+Temp
29	Dead+Wind 225 deg+Ice+Temp
30	Dead+Wind 240 deg+Ice+Temp
31	Dead+Wind 270 deg+Ice+Temp
32	Dead+Wind 300 deg+Ice+Temp
33	Dead+Wind 315 deg+Ice+Temp
34	Dead+Wind 330 deg+Ice+Temp
35	Dead+Wind 0 deg - Service
36	Dead+Wind 30 deg - Service
37	Dead+Wind 45 deg - Service
38	Dead+Wind 60 deg - Service
39	Dead+Wind 90 deg - Service
40	Dead+Wind 120 deg - Service
41	Dead+Wind 135 deg - Service
42	Dead+Wind 150 deg - Service
43	Dead+Wind 180 deg - Service
44	Dead+Wind 210 deg - Service
45	Dead+Wind 225 deg - Service
46	Dead+Wind 240 deg - Service
47	Dead+Wind 270 deg - Service
48	Dead+Wind 300 deg - Service
49	Dead+Wind 315 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	30 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft		
T1	170 - 150	Leg	Max Tension	22	29.76	-0.04	0.05		
			Max. Compression	19	-35.99	-0.00	0.45		
			Max. Mx	24	-35.74	-0.38	-0.24		
			Max. My	19	-35.99	-0.00	0.45		
			Max. Vy	30	-3.91	0.05	-0.06		
			Max. Vx	19	-4.53	-0.00	0.45		
		Diagonal	Max Tension	26	3.41	0.00	0.00		
			Max. Compression	26	-3.46	0.00	0.00		
			Max. Mx	19	2.89	-0.00	0.00		
			Max. My	22	-2.08	-0.00	0.00		
			Max. Vy	19	0.01	-0.00	0.00		
			Max. Vx	21	0.00	0.00	0.00		
		Top Girt	Max Tension	7	0.30	0.00	0.00		
			Max. Compression	15	-0.33	0.00	0.00		
			Max. Mx	18	-0.01	0.01	0.00		
			Max. My	31	0.01	0.00	-0.00		
			Max. Vy	18	-0.01	0.00	0.00		
			Max. Vx	31	0.00	0.00	0.00		
		Bottom Girt	Max Tension	15	0.15	0.00	0.00		
			Max. Compression	13	-0.15	0.00	0.00		
			Max. Mx	18	-0.00	0.01	0.00		
Max. My	31		-0.01	0.00	-0.00				
Max. Vy	18		-0.01	0.00	0.00				
Max. Vx	31		0.00	0.00	0.00				
T2	150 - 140	Leg	Max Tension	22	35.03	-0.42	0.02		
			Max. Compression	19	-41.87	2.80	0.28		
			Max. Mx	22	34.40	-3.29	0.23		
			Max. My	34	-3.47	-0.26	4.03		
			Max. Vy	27	0.63	-3.27	-0.36		
			Max. Vx	30	0.87	-1.76	-3.61		
		Diagonal	Max Tension	22	4.91	0.00	0.00		
			Max. Compression	30	-5.45	0.00	0.00		
			Max. Mx	22	4.33	0.05	0.00		
			Max. My	21	-4.23	-0.02	0.02		
			Max. Vy	22	0.02	0.05	0.00		
			Max. Vx	21	-0.00	0.00	0.00		
		Top Girt	Max Tension	5	0.42	0.00	0.00		
			Max. Compression	2	-0.37	0.00	0.00		
			Max. Mx	18	0.04	-0.02	0.00		
			Max. My	30	0.22	0.00	0.00		
			Max. Vy	18	0.02	0.00	0.00		
			Max. Vx	30	-0.00	0.00	0.00		
		T3	140 - 120	Leg	Max Tension	32	70.49	-3.70	-0.17
					Max. Compression	19	-84.43	3.69	0.03
					Max. Mx	32	69.34	-4.52	-0.16
Max. My	31				-8.47	-0.42	-6.63		
Max. Vy	27				0.69	-4.46	-0.05		
Max. Vx	23				-0.99	-0.41	6.59		
Diagonal	Max Tension			28	9.08	0.00	0.00		
	Max. Compression			29	-9.44	0.00	0.00		
	Max. Mx			19	5.84	0.11	0.01		
	Max. My			29	-7.63	-0.06	-0.02		
	Max. Vy			19	-0.03	0.11	0.01		
	Max. Vx			21	-0.00	0.00	0.00		
T4	120 - 100			Leg	Max Tension	32	117.19	-5.13	-0.02
					Max. Compression	19	-138.35	3.39	0.04
					Max. Mx	19	-109.85	6.13	0.00
		Max. My	31		-11.38	-0.47	-7.36		
		Max. Vy	32		0.98	-4.27	-0.10		
		Max. Vx	31		1.72	-0.47	-7.36		

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	31 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T5	100 - 90	Diagonal	Max Tension	21	11.55	0.00	0.00
			Max. Compression	29	-12.57	0.00	0.00
			Max. Mx	19	7.08	0.13	0.01
			Max. My	29	-12.53	-0.06	-0.05
			Max. Vy	32	0.04	0.12	-0.00
		Mid Girt	Max. Vx	29	0.01	0.00	0.00
			Max Tension	32	3.92	0.00	0.00
			Max. Compression	19	-3.17	0.00	0.00
			Max. Mx	18	0.41	-0.07	0.00
			Max. My	30	2.10	0.00	0.00
		Leg	Max. Vy	18	-0.03	0.00	0.00
			Max. Vx	30	-0.00	0.00	0.00
			Max Tension	32	144.94	-4.27	-0.10
			Max. Compression	19	-170.56	4.60	0.02
			Max. Mx	19	-170.56	4.60	0.02
Max. My	31		-12.60	-0.47	-7.36		
Max. Vy	19		-0.25	4.60	0.02		
Max. Vx	31		-0.49	-0.47	-7.36		
Diagonal	Max Tension		28	13.49	0.00	0.00	
	Max. Compression		28	-13.72	0.00	0.00	
	Max. Mx	19	10.36	0.18	0.01		
	Max. My	30	-0.61	0.09	-0.02		
	Max. Vy	19	-0.05	0.18	0.01		
T6	90 - 80	Leg	Max. Vx	30	-0.00	0.00	0.00
			Max Tension	32	173.18	-4.32	0.01
			Max. Compression	19	-202.06	5.78	0.05
			Max. Mx	30	-201.28	5.78	-0.12
			Max. My	31	-14.57	-0.00	-4.70
		Diagonal	Max. Vy	27	0.39	-5.71	-0.06
			Max. Vx	31	0.28	-0.00	-4.70
			Max Tension	28	13.38	0.00	0.00
			Max. Compression	28	-13.75	0.00	0.00
			Max. Mx	19	10.28	0.15	0.01
		Leg	Max. My	30	-0.77	0.08	-0.02
			Max. Vy	19	-0.05	0.15	0.01
			Max. Vx	30	0.00	0.00	0.00
			Max Tension	32	225.41	-5.01	0.02
			Max. Compression	19	-261.48	5.55	0.01
Max. Mx	30		-230.77	5.78	-0.12		
Max. My	34		-15.61	-0.08	5.19		
Max. Vy	22		-0.22	-5.69	0.11		
Max. Vx	34		-0.21	-0.08	5.19		
Diagonal	Max Tension		28	13.78	0.00	0.00	
	Max. Compression	28	-14.16	0.00	0.00		
	Max. Mx	19	10.54	0.15	0.01		
	Max. My	21	-13.53	0.02	0.02		
	Max. Vy	32	0.05	0.15	-0.01		
T7	80 - 60	Leg	Max. Vx	21	-0.00	0.00	0.00
			Max Tension	32	273.18	-5.02	0.02
			Max. Compression	30	-317.16	5.46	-0.09
			Max. Mx	32	272.62	-6.90	-0.01
			Max. My	34	-20.30	0.06	5.99
		Diagonal	Max. Vy	22	0.31	-6.89	0.07
			Max. Vx	26	0.22	0.05	-5.96
			Max Tension	28	13.88	0.00	0.00
			Max. Compression	28	-14.24	0.00	0.00
			Max. Mx	30	10.13	0.21	-0.01
		Leg	Max. My	21	-13.64	0.00	0.03
			Max. Vy	30	-0.06	0.21	-0.01
			Max. Vx	21	-0.00	0.00	0.00
			Max Tension	32	315.77	-3.05	0.03
			Max. Compression	32	-315.77	3.05	0.03

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	32 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
T10	20 - 0	Diagonal	Max. Compression	30	-370.16	-0.26	0.02
			Max. Mx	32	315.12	-11.58	0.02
			Max. My	31	-21.23	-0.76	-5.82
			Max. Vy	22	0.97	-11.56	-0.01
			Max. Vx	34	0.25	2.49	5.73
			Max Tension	28	15.13	0.00	0.00
			Max. Compression	28	-14.76	0.00	0.00
			Max. Mx	30	10.20	0.23	-0.02
			Max. My	28	-13.32	0.04	-0.03
			Max. Vy	32	0.07	0.21	-0.02
		Leg	Max. Vx	21	-0.00	0.00	0.00
			Max Tension	32	352.05	3.77	0.03
			Max. Compression	30	-419.98	-0.00	-0.00
			Max. Mx	30	-391.92	15.47	0.01
			Max. My	31	-30.36	9.54	-9.86
			Max. Vy	22	-1.65	-11.56	-0.01
			Max. Vx	34	1.08	9.55	9.85
			Max Tension	21	18.81	0.00	0.00
			Max. Compression	20	-16.65	0.00	0.00
			Max. Mx	32	7.51	0.29	-0.02
Diagonal	Max. My	21	-16.35	0.13	0.04		
	Max. Vy	32	0.08	0.29	-0.02		
	Max. Vx	21	-0.01	0.00	0.00		

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Leg C	Max. Vert	30	428.62	32.54	-19.68
	Max. H _x	30	428.62	32.54	-19.68
	Max. H _z	21	-350.34	-39.23	24.55
	Min. Vert	22	-363.26	-40.90	24.42
	Min. H _x	22	-363.26	-40.90	24.42
	Min. H _z	30	428.62	32.54	-19.68
Leg B	Max. Vert	24	426.83	-32.87	-19.16
	Max. H _x	32	-365.67	41.18	24.03
	Max. H _z	32	-365.67	41.18	24.03
	Min. Vert	32	-365.67	41.18	24.03
	Min. H _x	7	348.76	-32.95	-18.84
	Min. H _z	24	426.83	-32.87	-19.16
Leg A	Max. Vert	19	427.25	-0.58	37.97
	Max. H _x	31	28.06	3.86	-5.11
	Max. H _z	19	427.25	-0.58	37.97
	Min. Vert	27	-364.57	0.59	-47.70
	Min. H _x	23	27.41	-3.86	-5.18
	Min. H _z	27	-364.57	0.59	-47.70

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _y K	Overtuning Moment, M _x kip-ft	Overtuning Moment, M _y kip-ft	Torque kip-ft
------------------	------------	----------------------	----------------------	--	--	---------------

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 33 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Load Combination	Vertical	Shear _x	Shear _z	Overturning Moment, M _x	Overturning Moment, M _z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	51.55	0.00	0.00	-2.00	10.22	-0.00
Dead+Wind 0 deg - No Ice	51.55	-0.03	-59.60	-5731.31	12.45	-22.98
Dead+Wind 30 deg - No Ice	51.55	29.27	-50.81	-4910.48	-2816.44	-22.88
Dead+Wind 45 deg - No Ice	51.55	41.56	-41.28	-3990.12	-4015.51	-20.09
Dead+Wind 60 deg - No Ice	51.55	50.83	-29.04	-2806.84	-4918.74	-15.89
Dead+Wind 90 deg - No Ice	51.55	58.77	0.23	26.20	-5671.60	-5.78
Dead+Wind 120 deg - No Ice	51.55	51.69	30.08	2886.46	-4964.91	6.19
Dead+Wind 135 deg - No Ice	51.55	41.56	41.56	4009.14	-4016.39	11.54
Dead+Wind 150 deg - No Ice	51.55	29.55	50.94	4912.46	-2853.77	16.79
Dead+Wind 180 deg - No Ice	51.55	0.21	58.66	5675.66	-15.12	24.59
Dead+Wind 210 deg - No Ice	51.55	-29.36	50.86	4904.32	2852.48	23.21
Dead+Wind 225 deg - No Ice	51.55	-41.43	41.46	3998.63	4022.68	20.84
Dead+Wind 240 deg - No Ice	51.55	-51.57	29.98	2876.19	4972.05	18.14
Dead+Wind 270 deg - No Ice	51.55	-58.70	0.09	11.33	5682.58	8.01
Dead+Wind 300 deg - No Ice	51.55	-50.74	-29.22	-2827.93	4924.98	-3.93
Dead+Wind 315 deg - No Ice	51.55	-41.50	-41.41	-4004.87	4024.93	-9.94
Dead+Wind 330 deg - No Ice	51.55	-29.33	-50.88	-4917.75	2841.20	-16.08
Dead+Ice+Temp	85.61	0.00	0.00	-2.59	25.14	0.00
Dead+Wind 0 deg+Ice+Temp	85.61	-0.02	-69.88	-6905.93	26.68	-19.68
Dead+Wind 30 deg+Ice+Temp	85.61	34.37	-59.62	-5905.89	-3377.35	-25.79
Dead+Wind 45 deg+Ice+Temp	85.61	48.70	-48.47	-4802.60	-4804.84	-25.94
Dead+Wind 60 deg+Ice+Temp	85.61	59.54	-34.13	-3381.60	-5883.60	-24.27
Dead+Wind 90 deg+Ice+Temp	85.61	68.91	0.18	19.61	-6802.32	-17.29
Dead+Wind 120 deg+Ice+Temp	85.61	60.58	35.16	3467.54	-5963.93	-5.59
Dead+Wind 135 deg+Ice+Temp	85.61	48.70	48.69	4814.91	-4805.18	1.31
Dead+Wind 150 deg+Ice+Temp	85.61	34.59	59.71	5904.80	-3406.90	8.32
Dead+Wind 180 deg+Ice+Temp	85.61	0.16	68.72	6808.78	5.20	21.08
Dead+Wind 210 deg+Ice+Temp	85.61	-34.44	59.65	5898.58	3440.45	26.07
Dead+Wind 225 deg+Ice+Temp	85.61	-48.60	48.61	4806.92	4844.71	26.55
Dead+Wind 240 deg+Ice+Temp	85.61	-60.49	35.08	3459.87	6003.99	26.35
Dead+Wind 270 deg+Ice+Temp	85.61	-68.86	0.07	8.33	6845.13	19.07
Dead+Wind 300 deg+Ice+Temp	85.61	-59.46	-34.27	-3397.94	5922.26	7.02
Dead+Wind 315 deg+Ice+Temp	85.61	-48.65	-48.57	-4813.96	4845.92	-0.04
Dead+Wind 330 deg+Ice+Temp	85.61	-34.41	-59.67	-5911.38	3430.67	-7.76
Dead+Wind 0 deg - Service	51.55	-0.01	-20.62	-1984.53	11.00	-7.95
Dead+Wind 30 deg - Service	51.55	10.13	-17.58	-1700.49	-967.87	-7.93
Dead+Wind 45 deg - Service	51.55	14.38	-14.28	-1382.01	-1382.78	-6.95
Dead+Wind 60 deg - Service	51.55	17.59	-10.05	-972.56	-1695.31	-5.50
Dead+Wind 90 deg - Service	51.55	20.33	0.08	7.75	-1955.82	-1.99
Dead+Wind 120 deg - Service	51.55	17.89	10.41	997.47	-1711.29	2.14
Dead+Wind 135 deg - Service	51.55	14.38	14.38	1385.94	-1383.08	3.98
Dead+Wind 150 deg - Service	51.55	10.23	17.63	1698.51	-980.78	5.80
Dead+Wind 180 deg - Service	51.55	0.07	20.30	1962.60	1.46	8.51
Dead+Wind 210 deg - Service	51.55	-10.16	17.60	1695.71	993.74	8.05
Dead+Wind 225 deg - Service	51.55	-14.34	14.35	1382.32	1398.66	7.22
Dead+Wind 240 deg - Service	51.55	-17.85	10.37	993.93	1727.18	6.28
Dead+Wind 270 deg - Service	51.55	-20.31	0.03	2.60	1973.05	2.76
Dead+Wind 300 deg - Service	51.55	-17.56	-10.11	-979.87	1710.89	-1.36
Dead+Wind 315 deg - Service	51.55	-14.36	-14.33	-1387.13	1399.44	-3.43
Dead+Wind 330 deg - Service	51.55	-10.15	-17.61	-1703.02	989.84	-5.55

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-51.55	0.00	0.00	51.55	0.00	0.000%
2	-0.03	-51.55	-59.60	0.03	51.55	59.60	0.000%

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	34 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Load Comb	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
3	29.27	-51.55	-50.81	-29.27	51.55	50.81	0.000%
4	41.56	-51.55	-41.28	-41.56	51.55	41.28	0.000%
5	50.83	-51.55	-29.04	-50.83	51.55	29.04	0.000%
6	58.77	-51.55	0.23	-58.77	51.55	-0.23	0.000%
7	51.69	-51.55	30.08	-51.69	51.55	-30.08	0.000%
8	41.56	-51.55	41.56	-41.56	51.55	-41.56	0.000%
9	29.55	-51.55	50.94	-29.55	51.55	-50.94	0.000%
10	0.21	-51.55	58.66	-0.21	51.55	-58.66	0.000%
11	-29.36	-51.55	50.86	29.36	51.55	-50.86	0.000%
12	-41.43	-51.55	41.46	41.43	51.55	-41.46	0.000%
13	-51.57	-51.55	29.98	51.57	51.55	-29.98	0.000%
14	-58.70	-51.55	0.09	58.70	51.55	-0.09	0.000%
15	-50.74	-51.55	-29.22	50.74	51.55	29.22	0.000%
16	-41.50	-51.55	-41.41	41.50	51.55	41.41	0.000%
17	-29.33	-51.55	-50.88	29.33	51.55	50.88	0.000%
18	0.00	-85.61	0.00	-0.00	85.61	0.00	0.000%
19	-0.02	-85.61	-69.88	0.02	85.61	69.88	0.000%
20	34.37	-85.61	-59.62	-34.37	85.61	59.62	0.000%
21	48.70	-85.61	-48.47	-48.70	85.61	48.47	0.000%
22	59.54	-85.61	-34.13	-59.54	85.61	34.13	0.000%
23	68.91	-85.61	0.18	-68.91	85.61	-0.18	0.000%
24	60.58	-85.61	35.16	-60.58	85.61	-35.16	0.000%
25	48.70	-85.61	48.69	-48.70	85.61	-48.69	0.000%
26	34.59	-85.61	59.71	-34.59	85.61	-59.71	0.000%
27	0.16	-85.61	68.72	-0.16	85.61	-68.72	0.000%
28	-34.44	-85.61	59.65	34.44	85.61	-59.65	0.000%
29	-48.60	-85.61	48.61	-48.60	85.61	48.61	0.000%
30	-60.49	-85.61	35.08	60.49	85.61	-35.08	0.000%
31	-68.86	-85.61	0.07	68.86	85.61	-0.07	0.000%
32	-59.46	-85.61	-34.27	59.46	85.61	34.27	0.000%
33	-48.65	-85.61	-48.57	48.65	85.61	48.57	0.000%
34	-34.41	-85.61	-59.67	34.41	85.61	59.67	0.000%
35	-0.01	-51.55	-20.62	0.01	51.55	20.62	0.000%
36	10.13	-51.55	-17.58	-10.13	51.55	17.58	0.000%
37	14.38	-51.55	-14.28	-14.38	51.55	14.28	0.000%
38	17.59	-51.55	-10.05	-17.59	51.55	10.05	0.000%
39	20.33	-51.55	0.08	-20.33	51.55	-0.08	0.000%
40	17.89	-51.55	10.41	-17.89	51.55	-10.41	0.000%
41	14.38	-51.55	14.38	-14.38	51.55	-14.38	0.000%
42	10.23	-51.55	17.63	-10.23	51.55	-17.63	0.000%
43	0.07	-51.55	20.30	-0.07	51.55	-20.30	0.000%
44	-10.16	-51.55	17.60	10.16	51.55	-17.60	0.000%
45	-14.34	-51.55	14.35	14.34	51.55	-14.35	0.000%
46	-17.85	-51.55	10.37	17.85	51.55	-10.37	0.000%
47	-20.31	-51.55	0.03	20.31	51.55	-0.03	0.000%
48	-17.56	-51.55	-10.11	17.56	51.55	10.11	0.000%
49	-14.36	-51.55	-14.33	14.36	51.55	14.33	0.000%
50	-10.15	-51.55	-17.61	10.15	51.55	17.61	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	4	0.00000001	0.00000001
3	Yes	4	0.00000001	0.00000001

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	35 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

4	Yes	4	0.0000001	0.0000001
5	Yes	4	0.0000001	0.0000001
6	Yes	4	0.0000001	0.0000001
7	Yes	4	0.0000001	0.0000001
8	Yes	4	0.0000001	0.0000001
9	Yes	4	0.0000001	0.0000001
10	Yes	4	0.0000001	0.0000001
11	Yes	4	0.0000001	0.0000001
12	Yes	4	0.0000001	0.0000001
13	Yes	4	0.0000001	0.0000001
14	Yes	4	0.0000001	0.0000001
15	Yes	4	0.0000001	0.0000001
16	Yes	4	0.0000001	0.0000001
17	Yes	4	0.0000001	0.0000001
18	Yes	4	0.0000001	0.0000001
19	Yes	4	0.0000001	0.0000001
20	Yes	4	0.0000001	0.0000109
21	Yes	4	0.0000001	0.0000130
22	Yes	4	0.0000001	0.0000120
23	Yes	4	0.0000001	0.0000130
24	Yes	4	0.0000001	0.0000083
25	Yes	4	0.0000001	0.0000099
26	Yes	4	0.0000001	0.0000122
27	Yes	4	0.0000001	0.0000116
28	Yes	4	0.0000001	0.0000109
29	Yes	4	0.0000001	0.0000096
30	Yes	4	0.0000001	0.0000096
31	Yes	4	0.0000001	0.0000130
32	Yes	4	0.0000001	0.0000116
33	Yes	4	0.0000001	0.0000119
34	Yes	4	0.0000001	0.0000122
35	Yes	4	0.0000001	0.0000001
36	Yes	4	0.0000001	0.0000001
37	Yes	4	0.0000001	0.0000001
38	Yes	4	0.0000001	0.0000001
39	Yes	4	0.0000001	0.0000001
40	Yes	4	0.0000001	0.0000001
41	Yes	4	0.0000001	0.0000001
42	Yes	4	0.0000001	0.0000001
43	Yes	4	0.0000001	0.0000001
44	Yes	4	0.0000001	0.0000001
45	Yes	4	0.0000001	0.0000001
46	Yes	4	0.0000001	0.0000001
47	Yes	4	0.0000001	0.0000001
48	Yes	4	0.0000001	0.0000001
49	Yes	4	0.0000001	0.0000001
50	Yes	4	0.0000001	0.0000001

Maximum Tower Deflections - Service Wind

Section No.	Elevation <i>ft</i>	Horz Deflection <i>in</i>	Gov Load Comb	Tilt <i>°</i>	Twist <i>°</i>
T1	170 - 150	5.771	35	0.3279	0.0280
T2	150 - 140	4.409	35	0.2984	0.0346
T3	140 - 120	3.790	35	0.2780	0.0332
T4	120 - 100	2.702	35	0.2252	0.0194
T5	100 - 90	1.823	46	0.1785	0.0127
T6	90 - 80	1.464	46	0.1509	0.0107
T7	80 - 60	1.155	46	0.1305	0.0089

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job PIROD U20'-0"x170' Lattice Tower	Page 36 of 43
	Project TWS-027 Rev. 1 / Cromwell, CT Tower	Date 11:32:54 09/23/14
	Client Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by MCD

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb	Tilt °	Twist °
T8	60 - 40	0.649	46	0.0966	0.0064
T9	40 - 20	0.293	46	0.0583	0.0040
T10	20 - 0	0.086	46	0.0265	0.0020

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
183.00	101-90-08-0-01	35	5.771	0.3279	0.0280	88849
179.75	15' Mount Pipe	35	5.771	0.3279	0.0280	88849
178.00	3" Dia 20' Omni	35	5.771	0.3279	0.0280	88849
175.00	2.5" x 14' Omni	35	5.771	0.3279	0.0280	88849
174.00	1.5" x 12' Omni	35	5.771	0.3279	0.0280	88849
170.00	APXVSPP18-C-A20	35	5.771	0.3279	0.0280	88849
168.00	HPD2-4.7	35	5.631	0.3253	0.0289	88849
159.50	APXV18-206517S-C w/ mounting hardware	35	5.042	0.3135	0.0324	42309
158.50	SC420-HFILDF	35	4.974	0.3121	0.0327	38630
144.00	3" Dia 20' Omni	35	4.032	0.2868	0.0343	23538
141.00	2" Dia 15' Omni	35	3.850	0.2803	0.0336	23984
139.00	1.5" x 10' Omni	35	3.731	0.2756	0.0327	24120
138.50	9' Whip	35	3.702	0.2743	0.0325	24128
134.00	VHILP2.5-180	35	3.443	0.2627	0.0298	23972
125.50	PiROD 10' Lightweight T-Frame	35	2.981	0.2396	0.0233	23558
115.00	(2) TMA (shielded)	46	2.463	0.2135	0.0167	22934
101.00	BXA-171063-12BF	46	1.862	0.1811	0.0129	22013
87.00	3"x2"x22" Panel	46	1.366	0.1440	0.0101	25066
84.50	TMA	46	1.288	0.1388	0.0097	27742
83.50	3' Stand-off	46	1.258	0.1369	0.0095	28975
83.00	3' Dish	46	1.243	0.1359	0.0094	29604
82.50	TMA	46	1.228	0.1350	0.0093	30229
80.00	3"x2"x22" Panel	46	1.155	0.1305	0.0089	32895
30.00	Camera	46	0.171	0.0414	0.0030	32720
24.00	PC9013N	46	0.116	0.0323	0.0024	33266

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T1	170 - 150	19.843	19	1.0972	0.1177
T2	150 - 140	15.281	19	1.0106	0.1336
T3	140 - 120	13.176	19	0.9488	0.1236
T4	120 - 100	9.436	30	0.7798	0.0756
T5	100 - 90	6.374	30	0.6219	0.0489
T6	90 - 80	5.118	30	0.5273	0.0403
T7	80 - 60	4.035	30	0.4569	0.0330
T8	60 - 40	2.263	30	0.3383	0.0223
T9	40 - 20	1.016	30	0.2040	0.0132
T10	20 - 0	0.296	30	0.0927	0.0064

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	37 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt "	Twist °	Radius of Curvature ft
183.00	101-90-08-0-01	19	19.843	1.0972	0.1177	30835
179.75	15' Mount Pipe	19	19.843	1.0972	0.1177	30835
178.00	3" Dia 20' Omni	19	19.843	1.0972	0.1177	30835
175.00	2.5" x 14' Omni	19	19.843	1.0972	0.1177	30835
174.00	1.5" x 12' Omni	19	19.843	1.0972	0.1177	30835
170.00	APXVSP18-C-A20	19	19.843	1.0972	0.1177	30835
168.00	HPD2-4.7	19	19.377	1.0895	0.1203	30835
159.50	APXV18-206517S-C w/ mounting hardware	19	17.410	1.0553	0.1299	14683
158.50	SC420-HF1LDF	19	17.181	1.0510	0.1308	13406
144.00	3" Dia 20' Omni	19	14.000	0.9760	0.1294	8016
141.00	2" Dia 15' Omni	19	13.380	0.9560	0.1253	8024
139.00	1.5" x 10' Omni	19	12.974	0.9414	0.1218	7973
138.50	9' Whip	19	12.874	0.9376	0.1208	7953
134.00	VHLP2.5-180	30	11.986	0.9011	0.1107	7714
125.50	PIROD 10' Lightweight T-Frame	30	10.400	0.8266	0.0887	7254
115.00	(2) TMA (shielded)	30	8.604	0.7409	0.0663	6817
101.00	BXA-171063-12BF	30	6.510	0.6310	0.0498	6415
87.00	3"x2"x22" Panel	30	4.777	0.5034	0.0380	7279
84.50	TMA	30	4.504	0.4856	0.0361	8017
83.50	3' Stand-off	30	4.397	0.4789	0.0354	8355
83.00	3' Dish	30	4.345	0.4757	0.0350	8527
82.50	TMA	30	4.292	0.4724	0.0347	8697
80.00	3"x2"x22" Panel	30	4.035	0.4569	0.0330	9417
30.00	Camera	30	0.592	0.1447	0.0096	9288
24.00	PC9013N	30	0.399	0.1128	0.0077	9439

Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria
T1	170	Diagonal	A325N	0.6250	1	3.46	6.44	0.537 ✓	1.333	Bolt Shear
T2	150	Leg	A325N	1.0000	6	5.84	34.56	0.169 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	4.91	8.16	0.602 ✓	1.333	Member Bearing
		Top Girt	A325N	1.0000	1	0.42	8.16	0.052 ✓	1.333	Member Bearing
T3	140	Leg	A325N	1.0000	6	8.57	34.56	0.248 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	9.08	8.16	1.114 ✓	1.333	Member Bearing
T4	120	Leg	A325N	1.0000	6	15.41	34.56	0.446 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	11.55	10.88	1.062 ✓	1.333	Member Bearing
		Mid Girt	A325N	1.0000	1	3.92	8.16	0.480 ✓	1.333	Member Bearing
T5	100	Leg	A325N	1.0000	6	24.16	34.56	0.699 ✓	1.333	Bolt Tension
		Diagonal	A325N	1.0000	1	13.49	13.59	0.992 ✓	1.333	Member Bearing
T6	90	Leg	A325N	1.0000	6	28.86	34.56	0.835 ✓	1.333	Bolt Tension

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	38 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt K	Allowable Load K	Ratio Load Allowable	Allowable Ratio	Criteria
T7	80	Diagonal	A325N	1.0000	1	13.38	13.59	0.984 ✓	1.333	Member Bearing
		Leg	A325N	1.0000	6	33.26	34.56	0.963 ✓	1.333	Bolt Tension
T8	60	Diagonal	A325N	1.0000	1	14.16	16.49	0.859 ✓	1.333	Bolt Shear
		Leg	A325N	1.2500	6	41.67	54.00	0.772 ✓	1.333	Bolt Tension
T9	40	Diagonal	A325N	1.2500	1	13.88	16.99	0.817 ✓	1.333	Member Bearing
		Leg	A325N	1.2500	6	49.37	54.00	0.914 ✓	1.333	Bolt Tension
T10	20	Diagonal	A325N	1.2500	1	15.13	20.39	0.742 ✓	1.333	Member Bearing
		Diagonal	A325N	1.2500	1	18.81	16.99	1.107 ✓	1.333	Member Bearing

Compression Checks

Leg Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _n ft	Kl/r	F _n ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	1 3/4	20.00	2.49	68.3 K=1.00	21.253	2.4053	-35.99	51.12	0.704 ✓
T2	150 - 140	Pirod 105244	10.02	10.02	45.4 K=1.00	25.051	3.6816	-41.87	92.23	0.454 ✓
T3	140 - 120	Pirod 105216	20.03	10.02	45.4 K=1.00	25.051	3.6816	-84.43	92.23	0.915 ✓
T4	120 - 100	Pirod 105217	20.03	10.02	37.8 K=1.00	26.132	5.3014	-138.35	138.54	0.999 ✓
T5	100 - 90	Pirod 105217	10.02	10.02	37.8 K=1.00	26.132	5.3014	-170.56	138.54	1.231 ✓
T6	90 - 80	Pirod 105217 reinf w/ 1" dia bar	10.02	10.02	31.5 K=1.00	26.968	7.6570	-202.06	206.49	0.979 ✓
T7	80 - 60	Pirod 105218 reinf w/ 1" dia bar	20.03	10.02	27.6 K=1.00	27.439	9.9280	-261.48	272.41	0.960 ✓
T8	60 - 40	Pirod 105219	20.03	10.02	28.4 K=1.00	27.351	9.4248	-317.16	257.78	1.230 ✓
T9	40 - 20	Pirod 105219 reinf w/ 1" dia bar	20.03	10.02	25.4 K=1.00	27.705	11.7803	-370.16	326.37	1.134 ✓
T10	20 - 0	Pirod 105220 reinf w/ 1" dia bar	20.03	10.02	24.3 K=1.00	27.824	14.2843	-419.98	397.44	1.057 ✓

Truss-Leg Diagonal Data

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	39 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Diagonal Size	L_d ft	Kl/r	F_a ksi	A in ²	Actual V K	Allow. V_n K	Stress Ratio
T2	150 - 140	0.5	1.48	121.0	10.193	0.1963	0.94	2.24	0.418
T3	140 - 120	0.5	1.48	121.0	10.133	0.1963	0.99	2.23	0.446
T4	120 - 100	0.5	1.47	120.0	10.279	0.1963	1.73	2.26	0.764
T5	100 - 90	0.5	1.47	120.0	10.279	0.1963	0.50	2.26	0.219
T6	90 - 80	0.5	1.46	118.8	10.452	0.1963	0.39	2.30	0.172
T7	80 - 60	0.5	1.44	117.8	10.592	0.1963	0.23	2.33	0.097
T8	60 - 40	0.625	1.45	94.4	13.671	0.3068	0.32	4.69	0.067
T9	40 - 20	0.625	1.44	93.7	16.133	0.3068	0.97	5.54	0.175
T10	20 - 0	0.625	1.42	93.0	13.845	0.3068	1.71	4.75	0.360

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L_u ft	Kl/r	F_a ksi	A in ²	Actual P K	Allow. P_n K	Ratio $\frac{P}{P_n}$
T1	170 - 150	7/8	5.59	2.71	111.6 K=0.75	12.001	0.6013	-3.46	7.22	0.480
T2	150 - 140	L2 1/2x2 1/2x3/16	11.42	5.02	121.8 K=1.00	10.024	0.9020	-5.45	9.04	0.602
T3	140 - 120	L3x3x3/16	12.50	5.67	115.6 K=1.01	10.799	1.0900	-9.44	11.77	0.802
T4	120 - 100	L3x3x1/4	13.80	6.37	129.1 K=1.00	8.961	1.4400	-12.57	12.90	0.974
T5	100 - 90	L3x3x5/16	14.50	6.74	137.3 K=1.00	7.920	1.7800	-13.72	14.10	0.973
T6	90 - 80	L3x3x5/16	15.24	7.12	145.1 K=1.00	7.090	1.7800	-13.75	12.62	1.090
T7	80 - 60	L3x3x3/8	16.80	7.92	162.0 K=1.00	5.691	2.1100	-14.16	12.01	1.179
T8	60 - 40	L3 1/2x3 1/2x5/16	18.45	8.73	151.8 K=1.00	6.480	2.0900	-14.22	13.54	1.050
T9	40 - 20	L3 1/2x3 1/2x3/8	19.30	9.17	160.1 K=1.00	5.825	2.4800	-14.76	14.45	1.021
T10	20 - 0	L4x4x5/16	21.03	10.04	152.3 K=1.00	6.437	2.4000	-16.65	15.45	1.078

Top Girt Design Data (Compression)

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	40 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _n ksi	A in ²	Actual P K	Allow. P _n K	Ratio P P _n
T1	170 - 150	7/8	5.00	4.85	186.4 K=0.70	4,298	0.6013	-0.33	2.58	0.127 ✓
T2	150 - 140	L3x3x3/16	5.00	4.52	105.5 K=1.16	12,079	1.0900	-0.37	13.17	0.028 ✓

Bottom Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _n ksi	A in ²	Actual P K	Allow. P _n K	Ratio P P _n
T1	170 - 150	7/8	5.00	4.85	186.4 K=0.70	4,298	0.6013	-0.15	2.58	0.059 ✓

Mid Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _n ksi	A in ²	Actual P K	Allow. P _n K	Ratio P P _n
T4	120 - 100	L3x3x3/16	9.00	7.67	154.4 K=1.00	6,267	1.0900	-3.17	6.83	0.464 ✓

Tension Checks

Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _n ksi	A in ²	Actual P K	Allow. P _n K	Ratio P P _n
T1	170 - 150	1 3/4	20.00	2.49	68.3	30,000	2.4053	29.76	72.16	0.412 ✓
T2	150 - 140	Pirod 105244	10.02	10.02	45.4	30,000	3.6816	35.03	110.45	0.317 ✓
T3	140 - 120	Pirod 105216	20.03	10.02	45.4	30,000	3.6816	70.49	110.45	0.638 ✓
T4	120 - 100	Pirod 105217	20.03	10.02	37.8	30,000	5.3014	117.19	159.04	0.737 ✓
T5	100 - 90	Pirod 105217	10.02	10.02	37.8	30,000	5.3014	144.94	159.04	0.911 ✓
T6	90 - 80	Pirod 105217 reinf w/ 1" dia bar	10.02	10.02	31.5	30,000	7.6570	173.18	229.71	0.754 ✓
T7	80 - 60	Pirod 105218 reinf w/ 1" dia bar	20.03	10.02	27.6	30,000	9.9280	225.41	297.84	0.757 ✓
T8	60 - 40	Pirod 105219	20.03	10.02	28.4	30,000	9.4248	273.19	282.74	0.966 ✓

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	41 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P/P _a
T9	40 - 20	Pirod 105219 reinf w/ 1" dia bar	20.03	10.02	25.4	30.000	11.7803	315.77	353.41	0.894 ✓
T10	20 - 0	Pirod 105220 reinf w/ 1" dia bar	20.03	10.02	24.3	30.000	14.2843	352.06	428.53	0.822 ✓

Truss-Leg Diagonal Data

Section No.	Elevation ft	Diagonal Size	L _d ft	Kl/r	F _a ksi	A in ²	Actual V K	Allow. V _a K	Stress Ratio
T2	150 - 140	0.5	1.48	121.0	10.193	0.1963	0.94	2.24	0.418 ✓
T3	140 - 120	0.5	1.48	121.0	10.133	0.1963	0.99	2.23	0.446 ✓
T4	120 - 100	0.5	1.47	120.0	10.279	0.1963	1.73	2.26	0.764 ✓
T5	100 - 90	0.5	1.47	120.0	10.279	0.1963	0.50	2.26	0.219 ✓
T6	90 - 80	0.5	1.46	118.8	10.452	0.1963	0.39	2.30	0.172 ✓
T7	80 - 60	0.5	1.44	117.8	10.592	0.1963	0.23	2.33	0.097 ✓
T8	60 - 40	0.625	1.45	94.4	13.671	0.3068	0.32	4.69	0.067 ✓
T9	40 - 20	0.625	1.44	93.7	16.133	0.3068	0.97	5.54	0.175 ✓
T10	20 - 0	0.625	1.42	93.0	13.845	0.3068	1.71	4.75	0.360 ✓

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P/P _a
T1	170 - 150	7/8	5.59	2.71	148.7	30.000	0.6013	3.41	18.04	0.189 ✓
T2	150 - 140	L2 1/2x2 1/2x3/16	11.42	5.02	80.1	21.600	0.9020	4.91	19.48	0.252 ✓
T3	140 - 120	L3x3x3/16	12.50	5.67	74.6	21.600	1.0900	9.08	23.54	0.386 ✓
T4	120 - 100	L3x3x1/4	13.80	6.37	84.3	21.600	1.4400	11.55	31.10	0.371 ✓
T5	100 - 90	L3x3x5/16	14.50	6.74	89.9	21.600	1.7800	13.49	38.45	0.351 ✓
T6	90 - 80	L3x3x5/16	15.24	7.12	94.9	21.600	1.7800	13.38	38.45	0.348 ✓

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	42 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Size	L ft	L _w ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _n K	Ratio P P _n
T7	80 - 60	L3x3x3/8	16.01	7.54	101.2	21.600	2.1100	13.78	45.58	0.302
T8	60 - 40	L3 1/2x3 1/2x5/16	18.45	8.73	99.2	21.600	2.0900	13.88	45.14	0.307
T9	40 - 20	L3 1/2x3 1/2x3/8	20.16	9.59	109.8	21.600	2.4800	15.13	53.57	0.282
T10	20 - 0	L4x4x5/16	21.92	10.48	103.3	21.600	2.4000	18.81	51.84	0.363

Top Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _w ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	266.3	30.000	0.6013	0.30	18.04	0.016
T2	150 - 140	L3x3x3/16	5.00	4.52	62.0	21.600	1.0900	0.42	23.54	0.018

Bottom Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _w ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _a K	Ratio P P _a
T1	170 - 150	7/8	5.00	4.85	266.3	30.000	0.6013	0.15	18.04	0.008

Mid Girt Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _w ft	Kl/r	F _a ksi	A in ²	Actual P K	Allow. P _n K	Ratio P P _n
T4	120 - 100	L3x3x3/16	9.00	7.67	102.2	21.600	1.0900	3.92	23.54	0.166

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
T1	170 - 150	Leg	1 3/4	3	-35.99	68.14	52.8	Pass
T2	150 - 140	Leg	Pirod 105244	60	-41.87	122.94	34.1	Pass
T3	140 - 120	Leg	Pirod 105216	72	-84.43	122.94	68.7	Pass

tnxTower URS Corporation 500 Enterprise Drive, Suite 3B Rocky Hill, CT 06067 Phone: 860-529-8882 FAX: 860-529-3991	Job	PIROD U20'-0"x170' Lattice Tower	Page	43 of 43
	Project	TWS-027 Rev. 1 / Cromwell, CT Tower	Date	11:32:54 09/23/14
	Client	Sprint / T-Mobile (TWS-027)/(EBI-002)	Designed by	MCD

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
T4	120 - 100	Leg	Pirod 105217	87	-138.35	184.67	74.9	Pass
T5	100 - 90	Leg	Pirod 105217	105	-170.56	184.67	92.4	Pass
T6	90 - 80	Leg	Pirod 105217 reinf w/ 1" dia bar	114	-202.06	275.26	73.4	Pass
T7	80 - 60	Leg	Pirod 105218 reinf w/ 1" dia bar	123	-261.48	363.13	72.0	Pass
T8	60 - 40	Leg	Pirod 105219	136	-317.16	343.62	92.3	Pass
T9	40 - 20	Leg	Pirod 105219 reinf w/ 1" dia bar	151	-370.16	435.06	85.1	Pass
T10	20 - 0	Leg	Pirod 105220 reinf w/ 1" dia bar	166	-419.98	529.79	79.3	Pass
T1	170 - 150	Diagonal	7/8	12	-3.46	9.62	36.0	Pass
T2	150 - 140	Diagonal	L2 1/2x2 1/2x3/16	69	-5.45	12.05	45.2	Pass
T3	140 - 120	Diagonal	L3x3x3/16	78	-9.44	15.69	60.2	Pass
T4	120 - 100	Diagonal	L3x3x1/4	96	-12.57	17.20	73.1	Pass
T5	100 - 90	Diagonal	L3x3x5/16	111	-13.72	18.79	73.0	Pass
T6	90 - 80	Diagonal	L3x3x5/16	120	-13.75	16.82	81.7	Pass
T7	80 - 60	Diagonal	L3x3x3/8	129	-14.16	16.01	88.5	Pass
T8	60 - 40	Diagonal	L3 1/2x3 1/2x5/16	144	-14.22	18.05	78.8	Pass
T9	40 - 20	Diagonal	L3 1/2x3 1/2x3/8	165	-14.76	19.26	76.6	Pass
T10	20 - 0	Diagonal	L4x4x5/16	179	-16.65	20.59	80.9	Pass
T1	170 - 150	Top Girt	7/8	6	-0.33	3.45	9.5	Pass
T2	150 - 140	Top Girt	L3x3x3/16	61	-0.37	17.55	2.1	Pass
T1	170 - 150	Bottom Girt	7/8	8	-0.15	3.45	4.4	Pass
T4	120 - 100	Mid Girt	L3x3x3/16	88	-3.17	9.11	34.8	Pass
							Summary	
							Leg (T5)	92.4 Pass
							Diagonal (T7)	88.5 Pass
							Top Girt (T1)	9.5 Pass
							Bottom Girt (T1)	4.4 Pass
							Mid Girt (T4)	34.8 Pass
							Bolt Checks	83.5 Pass
							RATING =	92.4 Pass

ANCHOR BOLT EVALUATION

ANCHOR BOLT ANALYSIS

Input Data

Max Pier Reactions:

Uplift:	Uplift := 366-kips	<i>user input</i>
Shear:	Shear := 48-kips	<i>user input</i>
Compression:	Compression := 429-kips	<i>user input</i>

Anchor Bolt Data:

Use ASTM A687 Grade

Number of Anchor Bolts = N	$N_u = 6$	<i>user input</i>
Bolt Ultimate Strength:	$F_u = 150\text{-ksi}$	<i>user input</i>
Bolt Yield Strength:	$F_y = 105\text{-ksi}$	<i>user input</i>
Bolt Modulus:	$E = 29000\text{-ksi}$	<i>user input</i>
Thickness of Anchor Bolts	$D = 1.25\text{in}$	<i>user input</i>
Threads per Inch:	$n = 7$	<i>user input</i>
Coefficient of Friction:	$\mu = 0.55$	<i>user input</i> (for baseplate with grout ASCE 10-97)

Anchor Bolt Area:

Gross Area of Bolt:

$$A_g := \frac{\pi}{4} \cdot D^2 \qquad A_g = 1.227 \cdot \text{in}^2$$

Net Area of Bolt:

$$A_n := \frac{\pi}{4} \cdot \left(D - \frac{0.9743 \cdot \text{in}}{n} \right)^2 \qquad A_n = 0.969 \cdot \text{in}^2$$

Check Tensile Forces:

Maximum Tensile Force (Gross Area):

$$\text{AllowableTension} := 1.33 \cdot (0.33 \cdot A_g \cdot F_u) \qquad \text{AllowableTension} = 80.8 \text{ kips}$$

Note: 1.33 increase allowed per TIA/EIA

Maximum Tensile Force (Net Area):

$$F_{\text{net.area}} := 1.33 \cdot (0.60 \cdot A_n \cdot F_y) \qquad F_{\text{net.area}} = 81.2 \text{ kips}$$

Note: 1.33 increase allowed per TIA/EIA

Applied Tension:

$$\text{MaxTension} := \frac{\text{Uplift}}{N} \qquad \text{MaxTension} = 61.0 \text{ kips}$$

Check Stresses:

$$\frac{\text{MaxTension}}{F_{\text{net.area}}} = 0.75$$

$$\text{Condition1} := \text{if} \left(\frac{\text{MaxTension}}{F_{\text{net.area}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right)$$

Condition1 = "OK"

Check Anchor Bolt Area:

Based on the ASCE 10-97 Design of Latticed Steel Transmission Structures

Required Area:

$$A_{s1} := \frac{\text{Uplift}}{F_y} + \frac{\text{Shear}}{\mu \cdot 0.85 \cdot F_y} \quad A_{s1} = 4.5 \text{ in}^2$$

$$A_{s2} := \left| \frac{\text{Shear} - (0.3 \cdot \text{Compression})}{\mu \cdot 0.85 \cdot F_y} \right| \quad A_{s2} = 1.6 \text{ in}^2$$

Provided Area:

$$A_{s\text{provided}} := A_n \cdot N \quad A_{s\text{provided}} = 5.8 \text{ in}^2$$

$$\text{Condition2} := \text{if} \left(\frac{A_{s1}}{A_{s\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s1}}{A_{s\text{provided}}} = 0.77$$

Condition2 = "OK"

$$\text{Condition3} := \text{if} \left(\frac{A_{s2}}{A_{s\text{provided}}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right) \quad \frac{A_{s2}}{A_{s\text{provided}}} = 0.28$$

Condition3 = "OK"

FOUNDATION EVALUATION

Compression Capacity:

$$\text{TotalDownLoadCapacity} := \text{SoilShear} + q_s \left(\pi \cdot \frac{d_p^2}{4} \right)$$

$$\text{TotalDownLoadCapacity} = 699.1 \cdot \text{kips}$$

$$\text{CheckDownLoadCapacity} := \text{if}(\text{TotalDownLoad} < \text{TotalDownLoadCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckDownLoadCapacity} = \text{"Okay"}$$

Tension Capacity:

$$\text{TotalUpLiftCapacity} := \text{SoilShear} + \text{PierWeight}$$

$$\text{TotalUpLiftCapacity} = 813.4 \cdot \text{kips}$$

$$\text{CheckUpLiftCapacity} := \text{if}(U_t < \text{TotalUpLiftCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckUpLiftCapacity} = \text{"Okay"}$$

$$\text{SafetyFactor}_{\text{provided}} := \frac{\text{TotalUpLiftCapacity}}{U_t}$$

$$\text{SafetyFactor}_{\text{provided}} = 2.22$$

Check Cone Failure:

$$\text{ConeFailureCapacity} := \frac{[(C_{\text{Length}} - L_{\text{pag}}) \cdot \tan(30\text{deg}) \cdot 2 + d_p]^2 \cdot \pi \cdot C_{\text{Length}} - L_{\text{pag}}}{4} \cdot \gamma_s$$

$$\text{ConeFailureCapacity} = 2997.25 \cdot \text{kips}$$

$$\text{CheckConeFailureCapacity} := \text{if}(U_t < \text{ConeFailureCapacity}, \text{"Okay"}, \text{"No Good"})$$

$$\text{CheckConeFailureCapacity} = \text{"Okay"}$$

$$\text{ConeSafetyFactor}_{\text{provided}} := \frac{\text{ConeFailureCapacity}}{U_t}$$

$$\text{ConeSafetyFactor}_{\text{provided}} = 8.19$$

