



2255 Sewell Mill Road, Suite 130
Marietta, Georgia 30062
Phone: (678) 444-4463
Fax: (678) 444-4472
www.infinigy.com

October 9, 2014

Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051
Attn: Ms. Melanie Bachman, Executive Director

**Re: Notice of Exempt Modification Application
303 Boxwood Lane, Danbury, CT**

Dear Ms. Bachman,

On behalf of Sprint Nextel Corporation ("Sprint"), enclosed for filing are an original and two (2) copies of Sprint's Notice of Exempt Modification for Proposed Modifications to an Existing Telecommunications Facility located at the above-referenced site.

I also enclose herewith a check in the amount of \$625.00 representing the fee for the Notice of Exempt Modification.

If you have any questions, please feel free to contact me.

Thank you,

By: _____

A handwritten signature in black ink, appearing to read "David Weisman", is written over a horizontal line.

Name: David Weisman
Vertical Development LLC, an authorized representative of Sprint

Vertical Development LLC
20 Commercial Street
Branford, CT 06405
Phone – 401-743-9011
Fax – 401-633-6202
DWeisman@verticaldevelopmentllc.com

CC: Mr. Mark D. Boughton, Mayor
Danbury City Hall
155 Deer Hill Avenue
Danbury, CT 06810

siting.council@ct.gov (electronic copy)

Notice of Exempt Modification

303 Boxwood Lane, Danbury, CT

Sprint Corporation ("Sprint") submits this Notice of Exempt Modification to the Connecticut Siting Council ("Council") pursuant to Sections 16-50j-73 and 16-50j-72(b) of the Regulations of Connecticut State Agencies ("Regulations") in connection with Sprint's planned modification of antennas and associated equipment on an existing 100' self support tower located at 303 Boxwood Lane in the City of Danbury, CT. More particularly, Sprint plans to upgrade this site by adding 2.5 GHz technology to its facilities. The proposed modifications will not increase the tower height, cause a significant adverse change or alteration in the physical or environmental characteristics of the site, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six (6) decibels, add radio frequency sending or receiving capability which increases the total radio frequency electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the Federal Communications Commission pursuant to Section 704 of the Telecommunications Act of 1996, as amended, and the State Department of Energy and Environmental Protection, pursuant to Section 22a-162 of the Connecticut General Statutes, or impair the structural integrity of the facility, as determined in a certification provided by a professional engineer licensed in Connecticut.

To better meet the growing voice and data demands of its wireless customers, Sprint is upgrading their network nationwide to include 2.5 GHz technology, which will provide faster service and better overall performance. Pursuant to the 2.5 GHz technology upgrade at this site, Sprint will add panel antennas, install RRHs, and install related equipment to its equipment area within the fenced tower compound.

The 100' monopole tower located at 303 Boxwood Lane in the City of Danbury (lat. 41° 23' 41.93", long. -73° 29' 12.27") is owned by Western

Connecticut State University. It is located within a 5,625 square foot fenced compound. Sprint currently has three (3) antennas (one (1) per sector) with a centerline of 90' installed on the tower. Sprint's base station equipment is located adjacent to the base of the tower within the fenced compound. A site plan depicting this is attached.

Sprint plans to relocate three (3) panel antennas (one per sector) and six (6) RRHs (two (2) per sector) which will be connected and located behind the existing panel antennas. Sprint further plans to add three (3) RFS APXVTM14-C-120 panel antennas, one (1) per sector. Connected to each new RFS antenna will be one (1) ALU TD-RRH8X20 RRH, which will be located behind the new antenna. The height of the tower will not need to be increased. Sprint also plans to install eight (8) batteries in the existing BBU cabinet, 3 rectifiers in the existing equipment cabinet, and one (1) fiber transmission cable on the existing Ice Bridge all within Sprint's leased Premises. The compound's boundaries will not need to be extended. The proposed modifications will not cause a significant adverse change or alteration in the physical or environmental characteristics of the site, since it is already a telecommunications installation and the modifications will be compatible with this. Other than brief, construction-related noise, these modifications will not increase noise levels at the tower site boundary by six (6) decibels.

The proposed modifications will not add radio frequency sending or receiving capability which increases the total radio frequency electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the Federal Communications Commission pursuant to Section 704 of the Telecommunications Act of 1996, as amended, and the State Department of Energy and Environmental Protection, pursuant to Section 22a-162 of the Connecticut General Statutes. A radio frequency emissions analysis prepared by EBI Consulting indicated that the proposed final configuration (including other carriers on the tower) will emit 24.06% of the allowable FCC established general public limits sampled at the ground level (see the 2nd and the 6th page of Radio Frequency FCC Regulatory Compliance Maximum

Permissible Exposure (MPE) Assessment dated September 13, 2014). Emissions values for additional carriers were based upon values listed in Connecticut Siting Council active database (see the 2 and 6 page of Radio Frequency FCC Regulatory Compliance Maximum Permissible Exposure (MPE) Assessment dated September 13, 2014). The information used in the report was analyzed as a percentage of current Maximum Permissible Exposure (%MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1 (see the 2nd page of the Radio Frequency FCC Regulatory Compliance Maximum Permissible Exposure (MPE) assessment dated September 13, 2014).

The proposed modifications will not impair the structural integrity of the facility. Sprint commissioned Infinigy to perform a structural analysis of the tower to verify that it can support the proposed loading. The structure and foundation were found to meet the specified TIA requirements and deemed adequate to support the existing and proposed loading, and was rated at 98.4% (see the first page of Tower Analysis Report dated September 24, 2014.)

In conclusion, Sprint's proposed modifications do not constitute a modification subject to the Council's review because Sprint will not change the height of the tower, will not extend the boundaries of the compound, will not cause a significant adverse change or alteration in the physical or environmental characteristics of the site, will not increase the noise levels at the site, will not increase the total radio frequency electromagnetic radiation power density at the site to levels above applicable standards, and will not impair the structural integrity of the facility. Therefore, Sprint respectfully requests that the Council acknowledge that this Notice of Exempt Modification meets the Council's exemption criteria.

RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT43XC836

Danbury - W. CT University

303 Boxwood Lane
Danbury, CT 06810

September 13, 2014

EBI Project Number: 62144673

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at **303 Boxwood Lane, Danbury, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 5 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation.
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antennas used in this modeling are the RFS APXVSP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **90 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT43XC836 - Danbury - W. CT University
Site Address	303 Boxwood Lane, Danbury, CT, 06810
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	5	100	5.9	90	84	1/2"	0.5	0	346.74	1.77%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	90	84	1/2"	0.5	0	39.00	0.35%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	90	84	1/2"	0.5	0	138.69	1.25%
Sector total Power Density Value: 3.36%																

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	5	100	5.9	90	84	1/2"	0.5	0	346.74	1.77%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	90	84	1/2"	0.5	0	39.00	0.35%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	90	84	1/2"	0.5	0	138.69	1.25%
Sector total Power Density Value: 3.36%																

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	5	100	5.9	90	84	1/2"	0.5	0	346.74	1.77%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	90	84	1/2"	0.5	0	39.00	0.35%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	90	84	1/2"	0.5	0	138.69	1.25%
Sector total Power Density Value: 3.36%																

Site Composite MPE %	
Carrier	MPE %
Sprint	10.09%
Nextel	12.25%
T-Mobile	0.44%
W/CXI (WCSU)	1.28%
Total Site MPE %	24.06%

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **10.09% (3.36% from sector 1, 3.36% from sector 2 and 3.36% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **24.06%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803

Sprint



PROJECT: 2.5 EQUIPMENT DEPLOYMENT
 SITE NAME: DANBURY-W. CT UNIVERSITY
 SITE CASCADE: CT43XC836
 SITE ADDRESS: 303 BOXWOOD LANE
 DANBURY, CT 06810
 SITE TYPE: SELF SUPPORT TOWER
 MARKET: SOUTHERN CONNECTICUT

PLANS PREPARED FOR:
Sprint
 6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 333-000



DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		10/07/14	J.M.	0

SITE NAME:
DANBURY-W. CT UNIVERSITY

SITE CASCADE:
CT43XC836

SITE ADDRESS:
**303 BOXWOOD LANE
 DANBURY, CT 06810**

SHEET DESCRIPTION:
TITLE SHEET & PROJECT DATA

SHEET NUMBER:
T-1

SITE INFORMATION

PROPERTY OWNER:
 CT STATE UNIVERSITY SYSTEM. BOARD OF TRUSTEES MIDTOWN CAMPUS
 181 WHITE ST
 DANBURY, CT 06810

LATITUDE (NAD83):
 41° 23' 42" N
 41.395°

LONGITUDE (NAD83):
 73° 29' 12.2928" W
 -73.486748°

COUNTY:
 FAIRFIELD



ZONING JURISDICTION:
 DANBURY

ZONING DISTRICT:
 RA-40

POWER COMPANY:
 CONNECTICUT LIGHT & POWER
 (800) 266-2000

AAV PROVIDER:
 AT&T
 (800) 246-2020

SPRINT CONSTRUCTION MANAGER:
 GARY WOOD
 PHONE: (860) 940-9168
 gary.wood@sprint.com



PROJECT DESCRIPTION

SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.

- INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS CABINET
- INSTALL (8) NEW BATTERIES IN EXISTING SPRINT BATTERY CABINET
- INSTALL EXISTING SPRINT ANTENNA MOUNT, REPLACE WITH NEW SECTOR FRAMES
- INSTALL (3) PANEL ANTENNAS
- INSTALL (3) RRU'S NEAR ANTENNAS
- INSTALL (27) JUMPER CABLES
- INSTALL (1) FIBER CABLE

THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.

APPLICABLE CODES

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

- INTERNATIONAL BUILDING CODE (2012 IBC)
- TIA-EIA-222-G OR LATEST EDITION
- NFPA 780 - LIGHTNING PROTECTION CODE
- 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
- ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS
- CT BUILDING CODE
- LOCAL BUILDING CODE
- CITY/COUNTY ORDINANCES



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 7. AMERICAN CONCRETE INSTITUTE (ACI)
 - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 - 11. PORTLAND CEMENT ASSOCIATION (PCA)
 - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 13. BRICK INDUSTRY ASSOCIATION (BIA)
 - 14. AMERICAN WELDING SOCIETY (AWS)
 - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 17. DOOR AND HARDWARE INSTITUTE (DHI)
 - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 RECEIPT OF MATERIAL AND EQUIPMENT:

- A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
- B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 DELIVERABLES:

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 FUNCTIONAL REQUIREMENTS:

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	J.M.	0

SITE NAME:

DANBURY-W. CT UNIVERSITY

SITE CASCADE:

CT43XC836

SITE ADDRESS:

303 BOXWOOD LANE DANBURY, CT 06810

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
 19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."
- 3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:**
- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.
- 3.3 DELIVERABLES:**
- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 SUBMITTALS:
- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL
1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
- D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AZIMUTH, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
1. AZIMUTH, DOWNTILT, AZIMUTH - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AZIMUTH MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASHTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.

B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	JLM	0

SITE NAME:

DANBURY-W. CT UNIVERSITY

SITE CASCADE:

CT43XC836

SITE ADDRESS:

303 BOXWOOD LANE DANBURY, CT 06810

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING:
1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 WEEKLY REPORTS:
- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
 - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 1. SHELTER AND TOWER OVERVIEW.
 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 5. PHOTOS OF TOWER SECTION STACKING.
 6. CONCRETE TESTING / SAMPLES.
 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 11. COAX CABLE ENTRY INTO SHELTER.
 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 25. ALL BTS GROUND CONNECTIONS.
 26. ALL GROUND TEST WELLS.
 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 30. GPS ANTENNAS.
 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 34. MASTER BUS BAR.
 35. TELCO BOARD AND NIU.
 36. ELECTRICAL DISTRIBUTION WALL.
 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 38. ENTRANCE TO EQUIPMENT ROOM.
 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
 41. ANTENNA AND MAST GROUNDING.
 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:




6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:



1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 880-0790
Fax # (518) 690-0793
JOB NUMBER 333-000



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	JJM	0

SITE NAME:

DANBURY-W. CT UNIVERSITY

SITE CASCADE:

CT43XC836

SITE ADDRESS:

**303 BOXWOOD LANE
DANBURY, CT 06810**



SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:



SP-3

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	J.M.	0

SITE NAME:

DANBURY-W. CT UNIVERSITY

SITE CASCADE:

CT43XC836

SITE ADDRESS:


303 BOXWOOD LANE
DANBURY, CT 06810

SHEET DESCRIPTION:

SITE PLAN


SHEET NUMBER:

A-1





CABINET LINEUP PHOTO

SCALE: AS NOTED 1





EXISTING BATTERY CABINET PHOTO

SCALE: AS NOTED 2



MANUFACTURER: ALU
MODEL: 9928

N.V. MMBS CABINET



MANUFACTURER: TBD
MODEL: 60ECV2

BATTERY CABINET

EXISTING EQUIPMENT DETAIL

SCALE: AS NOTED 3

PLANS PREPARED FOR:


Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 333-000



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	J.M	0

SITE NAME:

DANBURY-W. CT UNIVERSITY

SITE CASCADE:

CT43XC836

SITE ADDRESS:

**303 BOXWOOD LANE
DANBURY, CT 06810**

SHEET DESCRIPTION:


EXISTING EQUIPMENT DETAILS

SHEET NUMBER:


A-1A

NOTE:
 BASED ON THE ANALYSIS PROVIDED BY INFINIGY, DATED 9/24/14, THE EXISTING STRUCTURE IS CAPABLE OF SUPPORTING THE PROPOSED EQUIPMENT CONFIGURATION. THE ANALYSIS INDICATES THE TOWER AND ITS FOUNDATION HAVE SUFFICIENT CAPACITY TO CARRY THE EXISTING, RESERVED, AND PROPOSED LOADS. NO MODIFICATIONS ARE REQUIRED AT THIS TIME.

NOTE:
 SEE DETAIL 2 ON A-3 FOR ANTENNA LAYOUT



PROPOSED SECTOR FRAME TO REPLACE EXISTING (SITE PRO P/N: VFA12-U OR APPROVED EQUAL) (SEE SHEET A-3 DETAIL 3) (TYP. OF (3) SECTORS)



PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.

1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	JLM	0

SITE NAME:

DANBURY-W. CT UNIVERSITY

SITE CASCADE:

CT43XC836

SITE ADDRESS:

**303 BOXWOOD LANE
 DANBURY, CT 06810**

SHEET DESCRIPTION:

BUILDING ELEVATION & CABLE PLAN

SHEET NUMBER:

A-2



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	J.M.	0

DANBURY-W. CT UNIVERSITY

CT43XC836


303 BOXWOOD LANE
 DANBURY, CT 06810

ANTENNA LAYOUT & MOUNTING DETAILS

A-3

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.


NOTE: JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET



EXISTING ANTENNA & RRU LAYOUT

NO SCALE


1



FINAL ANTENNA LAYOUT

NO SCALE


2



SECTOR FRAME DETAIL

NO SCALE

3



NOTES:

- CUT DC CONDUCTORS TO LENGTH.
- COIL FIBER CABLE AND SECURE AT SIDE OF RRU.
- DO NOT EXCEED BEND RADIUS.

NOTE: SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.

NOTE: THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS

TYPICAL ANTENNA & RRU MOUNTING DETAILS

NO SCALE


4

NV CABLES				
BAND	INDICATOR		PORT	COLOR
800-1	YEL	GRN	NV-1	GRN
1900-1	YEL	RED	NV-2	BLU
1900-2	YEL	BRN	NV-3	BRN
1900-3	YEL	BLU	NV-4	WHT
1900-4	YEL	SLT	NV-5	RED
800-2	YEL	ORG	NV-6	SLT
SPARE	YEL	WHT	NV-7	PPL
2500	YEL	PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL WHT	GRN	
YEL WHT	BLU	
YEL WHT	BRN	
YEL WHT	WHT	
YEL WHT	RED	
YEL WHT	SLT	
YEL WHT	PPL	
YEL WHT	ORG	

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2		No Tape	No Tape
	3	Brown	No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2			No Tape
	3	Brown	Brown	No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2			
	3	Brown	Brown	Brown
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

2.5 FREQUENCY	INDICATOR	ID
2500 -1	YEL	WHT
2500 -2	YEL	WHT
2500 -3	YEL	WHT
2500 -4	YEL	WHT
2500 -5	YEL	WHT
2500 -6	YEL	WHT
2500 -7	YEL	WHT
2500 -8	YEL	WHT



PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV

ISSUED FOR PERMIT: 10/07/14 J.M 0

SITE NAME: DANBURY-W. CT UNIVERSITY

SITE CASCADE: CT43XC836




SITE ADDRESS: 303 BOXWOOD LANE DANBURY, CT 06810

SHEET DESCRIPTION: COLOR CODING & NOTES

SHEET NUMBER: A-4


RRU: ALCATEL LUCENT TD-RRH8X20

COLOR: LIGHT GREY
WEIGHT: 70 LBS.



NOTES
COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN.

- DS3 SURGE PROTECTOR
- POWER INJECTOR 5-8
- POWER INJECTOR 1-4
- 7210 SAS-M 2
- 7210 SAS-M 1
- 7205 SAR-B
- LTE-BBU 2.5GHz
- LTE-BBU FDD
- CDMA MT-BBU GROWTH
- CDMA MT-BBU PRIMARY
- PDP1
- PDP2
- 15MHz SPLITTER
- ETHERNET HUB SEC-B
- PRIMARY PROTECTION T1
- SEC-B #1, #1 & #3
- RECTIFIER SHELF PRIMARY
- RECTIFIER SHELF 2.5GHz



FRONT VIEW

2.5 RRU'S

NO SCALE

1

2.5 EQUIPMENT IN EXISTING CABINET

NO SCALE

2

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV

ISSUED FOR PERMIT: 10/07/14 JLM 0

SITE NAME:
DANBURY-W. CT UNIVERSITY

SITE CASCADE:
CT43XC836


SITE ADDRESS:
**303 BOXWOOD LANE
DANBURY, CT 06810**

SHEET DESCRIPTION:
EQUIPMENT & MOUNTING DETAILS

SHEET NUMBER:
A-5

ANTENNA RFS APXVTM14-C-120


- RADOME MATERIAL: ASA
- RADOME COLOR: LIGHT GREY
- DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)
- WEIGHT: 52.9 lbs
- CONNECTORS: (8) 4.1/9.5 DIN FEMALE
(1) NF - CALIBRATION CONNECTOR



PLAN VIEW



SIDE VIEW




FRONT VIEW

2.5 ANTENNA

NO SCALE

3



INFINIGY ESTIMATES

*Riser Cable Length Estimate		
At Grade	74	Feet
Vertical Rise	89	Feet
At Sprint Centerline	0	Feet
Sub-Total	163	Feet
35% Buffer	25	Feet
Total	188	Feet

ABOVE LENGTH IS AN ESTIMATE AND SHOULD BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

** Hybrid/Fiber Jumper Length Estimate		
From Connector To RRU	25	Feet

ABOVE LENGTH IS AN ESTIMATE AND SHOULD BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

Coax Jumper Length Estimate		
From RRU to Antenna	5	Feet

ABOVE LENGTH IS AN ESTIMATE AND SHOULD BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

NOTE:
* & **: REFERENCE SHEET A-6, DETAIL 1 FOR CORRESPONDING PART NUMBERS.

CABLE LENGTH NOTE:
APPROXIMATE LENGTH OF NEW CABLE IS SHOWN IN CHART ON THIS SHEET. CONTRACTOR TO CONFIRM EXACT CABLE LENGTH REQUIRED PRIOR TO ORDERING MATERIALS.

CABLING SCHEMATIC

NO SCALE

4





RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 3/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE


Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.




FIBER JUNCTION BOX PENETRATION NO SCALE 2

IMPORTANT!! Line up white markings on jumper and riser IP-MPO connectors and slide the riser connector to the jumper connector. Push the white mark on the jumper connector flush again the red seal on the riser connector.




Seal (Riser end) White mark (Jumper end)

IMPORTANT!! Rotate the bayonet housing clock wise until you hear a click sound (means a good connection is in place).



INFORMATION BASED ON PROVIDED INFORMATION FROM ALCATEL-LUCENT 2.5 GHz UPGRADE INSTALLATION GUIDE.

HYBRIFLEX RISER/JUMPER CONNECTION DETAIL NO SCALE 3



2.5 HYBRID RISER CABLE (FIBER AND DC FEEDERS) **FIBER ONLY RISER CABLE** NO SCALE 4

2.5 CABLE CROSS SECTION DATA NO SCALE 1

TRUNK LINE DETAIL (TYP.) NO SCALE 4

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 333-000

ENGINEERING LICENSE:

DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT		10/07/14	JLM	0

SITE NAME:
DANBURY-W. CT UNIVERSITY

SITE CASCADE:
CT43XC836

SITE ADDRESS:
303 BOXWOOD LANE DANBURY, CT 06810

SHEET DESCRIPTION:
CIVIL DETAILS

SHEET NUMBER:
A-6



DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	J.M.	0


SITE NAME:
DANBURY-W. CT UNIVERSITY

SITE CASCADE:
CT43XC836


SITE ADDRESS:
 303 BOXWOOD LANE
 DANBURY, CT 06810

SHEET DESCRIPTION:
PLUMBING DIAGRAM


SHEET NUMBER:
A-7



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLANS PREPARED FOR:



PLANS PREPARED BY:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	JLM	0

SITE NAME:

DANBURY-W. CT UNIVERSITY

SITE CASCADE:

CT43XC836

SITE ADDRESS:

303 BOXWOOD LANE
DANBURY, CT 06810

SHEET DESCRIPTION:

ELECTRICAL & GROUNDING PLAN

SHEET NUMBER:

E-1


PLAN NOT USED

NO SCALE

1

LEGEND:


- ○ --- EXISTING GROUND RING
- CADWELD CONNECTION (EXOTHERMIC WELD)
- ▲ MECHANICAL CONNECTION
- ⊗ GROUND ROD
- CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2




NOTE: DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE

3


NOTES
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BATTERY CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

PLANS PREPARED FOR:
Sprint
 6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design-Build-Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 333-000



DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR PERMIT	10/07/14	JLM	0

SITE NAME:
DANBURY-W. CT UNIVERSITY

SITE CASCADE:
CT43XC836


SITE ADDRESS:
 303 BOXWOOD LANE
 DANBURY, CT 06810

SHEET DESCRIPTION:
ELECTRICAL & GROUNDING DETAILS


SHEET NUMBER:
E-2

ELECTRICAL ONE-LINE DIAGRAM


NO SCALE 1



NOTES
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.



TWO HOLE LUG NO SCALE 3



GROUNDING RISER DIAGRAM NO SCALE 4


INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR NO SCALE 2

Tower Analysis Report

September 24, 2014

Site Name	CT43XC836 Danbury-W. C.T. University
Infinigy Job Number	333-315
Client	Sprint
Proposed Carrier	Sprint
Site Location	303 Boxwood Lane, Danbury, CT 06810 Fairfield County 41° 23' 42.00" N NAD83 73° 29' 12.29" W NAD83
Structure Type	100' Self Supporting Tower
Structural Usage Ratio	98.4%
Overall Result	Pass

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA code requirements. The tower and foundations are therefore deemed adequate to support the existing and proposed loading as listed in this report.



Maxwell R. Becker, E.I.T.
Structural Engineer I

Contents

Introduction.....	3
Supporting Documentation.....	3
Analysis Code Requirements.....	3
Conclusion.....	3
Existing and Reserved Loading.....	4
Proposed Loading.....	4
Structure Usages.....	4
Foundation Reactions.....	4
Deflection, Twist, and Sway.....	5
Assumptions and Limitations.....	5
Calculations.....	Appended

Introduction

Infinigy Engineering has been requested to perform a structural analysis on the existing 100' Nudd Self Support tower. All supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The tower was analyzed using tnxTower version 6.1.3.1 tower analysis software.

Supporting Documentation

Design Drawings	Fred A. Nudd Drawing # 96-4992-1, dated January 21, 1997
Foundation Drawings	Fred A. Nudd Drawing # 96-4992-2, dated January 21, 1997
Mod Drawings	Centek Engineering project # 10106, date July 23, 2010
Construction Drawings	Infinigy Engineering Job # 333-315, dated May 13, 2014
Previous Analysis	KM Consulting Engineers Job # CT43XC836, dated December 6, 2013

Analysis Code Requirements

Wind Speed	100 mph (3-Second Gust)
Wind Speed w/ ice	40 mph (3-Second Gust) w/ 3/4" ice
TIA Revision	ANSI/TIA-222-G
Adopted IBC	2003 IBC w/ 2005 CT Supplement & 2013 CT Amendment
Structure Class	2
Exposure Category	B
Topographic Category	1
Calculated Crest Height	0 ft

Conclusion

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA code requirements. The tower and foundations are therefore deemed adequate to support the existing and proposed loading as listed in this report.

If you have any questions, require additional information, or actual conditions differ from those as detailed in this report please contact me via the information below:

Maxwell R. Becker, E.I.T.
 Structural Engineer I | Infinigy
 1033 Watervliet Shaker Road, Albany, NY 12205
 (O) (518) 690-0790 | (M) (518) 221-4665
mbecker@infinigy.com | www.infinigy.com

Existing and Reserved Loading

Mount Height (ft)	Qty.	Appurtenance	Mount Type	Coax & Lines	Carrier
98.0	8	Decibel DB844H90	Sector Frames	(16) 7/8" (6) 1-5/8"	--
	2	60"x12" Panel			
	2	72"x12" Panel			
96.0	1	2'x4' Grid Dish	Pipe	(1) 1-5/8"	
89.0	3	RFS APXVSP18-C-A20	Sector Frames	(3) 1-1/4" Hybriflex (1) 0.3"	Sprint
	6	Alcatel-Lucent 1900 MHz RRH			
	3	Alcatel-Lucent 800 MHz RRH			
83.0	3	RFS APX16PV-16PVL	Pipes	(12) 1-5/8"	T-Mobile
80.0	4	RFS ATMAA1412D-1A20 TMA			
65.0	1	Shively Labs 6810	Leg	(1) 1/2"	--
30.0	1	GPS	Side Arm	--	

Proposed Loading

Mount Height (ft)	Qty.	Appurtenance	Mount Type	Coax & Lines*	Carrier
89.0	3	RFS APXVTM14-C-120	Sector Frames	(1) 1-1/4" Hybrid	Sprint
	3	Alcatel-Lucent TD-RRH8X20			

* Proposed coax to be installed alongside existing coax.

Structure Usages

Leg (T7)	96.6	Pass
Diagonal (T12)	89.8	Pass
Horizontal (T1)	89.5	Pass
Secondary Horizontal (T11)	3.0	Pass
Top Girt (T7)	98.4	Pass
Bottom Girt (T1)	68.6	Pass
Bolt Checks	74.6	Pass
RATING =	98.4	Pass

Foundation Reactions

Reaction Data	Design Reactions	Analysis Reactions	Result
Moment (kip-ft)	--	995.9	
Shear (kip)	--	14.9	--
Axial (kip)	--	41.6	--

Tower base reactions are acceptable per rigorous structural analysis.

Deflection, Twist, and Sway

Antenna Elevation (ft)	Deflection (in)	Twist (°)	Sway (°)
89.0	4.04	0.04	0.44

*Per ANSI/TIA-222-G Section 2.8.2 maximum serviceability structural deflection limit is 3% of structure height.

*Per ANSI/TIA-222-G Section 2.8.2 maximum serviceability structural twist and sway limit is 4 degrees.

*Per ANSI/TIA-222-G Section 2.8.3 deflection, Twist, and sway values were calculated using a basic 3-second gust wind speed of 60 mph.

*It is the responsibility of the client to ensure their proposed and/or existing equipment will meet ANSI/TIA-222-G Annex D or other appropriate microwave signal degradation limits based on the provided values above.

Assumptions and Limitations


All engineering services are completed assuming all information provided to Infinigy Engineering is current and correct. If actual conditions differ from those described in this report we should be notified immediately to complete a revised evaluation.

It is the responsibility of the client to ensure that the information provided to Infinigy Engineering is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the design drawings and specifications that have been supplied.

All calculations are completed in accordance with generally accepted engineering principles and practices. Infinigy Engineering is not responsible the conclusions, opinions, and recommendations made by others based on the information we supply.

This report is an evaluation of the tower structure only and does not reflect adequacy of any existing antenna mounts, mount connections, or coax mounting attachments. These elements are assumed to be adequate for the purposes of this analysis and are assumed to have been installed per their manufacturer requirements.

Section	T14	T13	T12	T11	T10	T9	T8	T7	T6	T5	T4	T3	T2	T1
Legs	P5x.375 GR		A		P3x.3 GR									P2.5x.276 GR
Leg Grade	A500-42				A500M-61									A500-50
Diagonals	L2 1/2x2 1/2x3/16	L2x2x3/16			SR 3/4									SR 5/8
Diagonal Grade					A36									
Top Girts	N.A.													L1 1/2x1 1/2x3/16
Bottom Girts	N.A.													L1 1/2x1 1/2x3/16
Horizontals	N.A.													L1 1/2x1 1/2x3/16
Sec. Horizontals	N.A.													N.A.
# Panels @ (ft)	7.5													
Weight (lb)	6756.4	1760.4	6 @ 6.55556	4 @ 3.16667	2 @ 3.25	371.9	282.4	282.4	282.4	282.2	135.6	135.6	158.6	6 @ 3.27778
														772.2



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
Angle Sector Frame	98	APXVTM14-C-120 (Sprint)	89
Angle Sector Frame	98	APXVTM14-C-120 (Sprint)	89
Angle Sector Frame	98	APXVTM14-C-120 (Sprint)	89
(4) DB844H90	98	TD-RRH8X20 (Sprint)	89
(4) DB844H90	98	TD-RRH8X20 (Sprint)	89
(2) 60"x12" Panel	98	TD-RRH8X20 (Sprint)	89
(2) 72" x 12" Panel	98	APXVSPP18-C-A20 (Sprint)	89
Dish Pipe Mount	96	APX16PV-16PVL (T-Mobile)	83
2' x 4' Rectangular Grid Dish	96	APX16PV-16PVL (T-Mobile)	83
APXVSPP18-C-A20 (Sprint)	89	APX16PV-16PVL (T-Mobile)	83
APXVSPP18-C-A20 (Sprint)	89	Antenna Pipe Mount (T-Mobile)	81
(2) 1900 MHz RRH (Sprint)	89	Antenna Pipe Mount (T-Mobile)	81
(2) 1900 MHz RRH (Sprint)	89	(2) ATMAA1412D-1A20 TMA (T-Mobile)	80
(2) 1900 MHz RRH (Sprint)	89	(2) ATMAA1412D-1A20 TMA (T-Mobile)	80
800 MHz RRH (Sprint)	89	(2) ATMAA1412D-1A20 TMA (T-Mobile)	80
800 MHz RRH (Sprint)	89	6810	65
800 MHz RRH (Sprint)	89	Angle Side Arm (Sprint)	30
Pipe Sector Frame (Sprint)	89	GPS (Sprint)	30
Pipe Sector Frame (Sprint)	89		
Pipe Sector Frame (Sprint)	89		

SYMBOL LIST

MARK	SIZE	MARK	SIZE
A	P3x.3 GR w/ .75 TR	B	2L1 1/2x1 1/2x3/16x3/8

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A500-50	50 ksi	62 ksi	A500M-61	61 ksi	75 ksi
A36	36 ksi	58 ksi	A500-42	42 ksi	58 ksi

TOWER DESIGN NOTES


1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-G Standard.
3. Tower designed for a 100 mph basic wind in accordance with the TIA-222-G Standard.
4. Tower is also designed for a 40 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Structure Class II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 98.4%

ALL REACTIONS ARE FACTORED

MAX. CORNER REACTIONS AT BASE:

DOWN: 158753 lb
SHEAR: 10834 lb

UPLIFT: -145912 lb
SHEAR: 9960 lb



Infinigy Engineering
 2255 Sewell Mill Road, Suite 130
 Marietta, GA 30062
 Phone: (678) 444-4463
 FAX: (678)444-4472

Job: **333-315**
 Project: **CT43XC836 - Danbury-W. CT. University**
 Client: Sprint | Drawn by: MBecker | App'd:
 Code: TIA-222-G | Date: 09/24/14 | Scale: NTS
 Path: N:\Sprint2_8\Sprint Direct\Southern CT\CT43XC836\Structural\JOEJ Files\CT43XC836.en | Dwg No. E-1

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	1 of 24	
	Project	CT43XC836 - Danbury-W. CT. University		Date	15:17:04 09/24/14
	Client	Sprint		Designed by	MBecker

Tower Input Data

The main tower is a 3x free standing tower with an overall height of 100.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 3.50 ft at the top and 7.50 ft at the base.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Tower is located in Fairfield County, Connecticut.

Basic wind speed of 100 mph.

Structure Class II.

Exposure Category B.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 0.7500 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 40 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

Tension only take-up is 0.0313 in.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.


Stress ratio used in tower member design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

<ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile √ Include Bolts In Member Capacity √ Leg Bolts Are At Top Of Section √ Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) Add IBC .6D+W Combination 	<ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area √ Use Clear Spans For KL/r √ Retension Guys To Initial Tension Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. √ Autocalc Torque Arm Areas SR Members Have Cut Ends Sort Capacity Reports By Component √ Triangulate Diamond Inner Bracing Use TIA-222-G Tension Splice Capacity Exemption 	<ul style="list-style-type: none"> Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression √ All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feedline Torque √ Include Angle Block Shear Check <div style="text-align: center; background-color: #e0e0e0; padding: 2px;">Poles</div> <ul style="list-style-type: none"> Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets
--	---	--

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job 333-315	Page 2 of 24
	Project CT43XC836 - Danbury-W. CT. University	Date 15:17:04 09/24/14
	Client Sprint	Designed by MBecker



Triangular Tower

Tower Section Geometry

Tower Section	Tower Elevation	Assembly Database	Description	Section Width	Number of Sections	Section Length
	<i>ft</i>			<i>ft</i>		<i>ft</i>
T1	100.00-80.00			3.50	1	20.00
T2	80.00-76.00			3.50	1	4.00
T3	76.00-73.00			3.50	1	3.00
T4	73.00-70.00			3.50	1	3.00
T5	70.00-67.00			3.50	1	3.00
T6	67.00-64.00			3.50	1	3.00
T7	64.00-60.00			3.50	1	4.00
T8	60.00-53.17			3.50	1	6.83
T9	53.17-50.00			3.50	1	3.17
T10	50.00-46.83			3.50	1	3.17
T11	46.83-43.67			3.50	1	3.17
T12	43.67-40.00			3.50	1	3.67
T13	40.00-20.00			3.50	1	20.00
T14	20.00-0.00			5.50	1	20.00

Tower Section Geometry (cont'd)

Tower Section	Tower Elevation	Diagonal Spacing	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset	Bottom Girt Offset
	<i>ft</i>	<i>ft</i>				<i>in</i>	<i>in</i>
T1	100.00-80.00	3.28	TX Brace	No	Yes	1.9999	1.9999

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	3 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Tower Section	Tower Elevation ft	Diagonal Spacing ft	Bracing Type	Has K Brace End Panels	Has Horizontals	Top Girt Offset in	Bottom Girt Offset in
T2	80.00-76.00	3.00	TX Brace	No	Yes	12.0000	0.0000
T3	76.00-73.00	3.00	TX Brace	No	Yes	0.0000	0.0000
T4	73.00-70.00	3.00	TX Brace	No	Yes	0.0000	0.0000
T5	70.00-67.00	3.00	TX Brace	No	Yes	0.0000	0.0000
T6	67.00-64.00	3.00	TX Brace	No	Yes	0.0000	0.0000
T7	64.00-60.00	3.00	TX Brace	No	Yes	0.0000	12.0000
T8	60.00-53.17	3.25	TX Brace	No	Yes	3.9996	0.0000
T9	53.17-50.00	3.17	TX Brace	No	Yes	0.0000	0.0000
T10	50.00-46.83	3.17	TX Brace	No	Yes	0.0000	0.0000
T11	46.83-43.67	3.17	TX Brace	No	Yes	0.0000	0.0000
T12	43.67-40.00	3.17	TX Brace	No	Yes	0.0000	6.0002
T13	40.00-20.00	6.56	X Brace	No	No	1.9999	1.9999
T14	20.00-0.00	6.56	X Brace	No	No	1.9999	1.9999

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Type	Leg Size	Leg Grade	Diagonal Type	Diagonal Size	Diagonal Grade
T1 100.00-80.00	Pipe	P2.5x.276	A500-50 (50 ksi)	Solid Round	5/8	A36 (36 ksi)
T2 80.00-76.00	Pipe	P2.5x.276 GR	A500-50 (50 ksi)	Solid Round	5/8	A36 (36 ksi)
T3 76.00-73.00	Pipe	P2.5x.276 GR	A500-50 (50 ksi)	Solid Round	5/8	A36 (36 ksi)
T4 73.00-70.00	Pipe	P2.5x.276 GR	A500-50 (50 ksi)	Solid Round	5/8	A36 (36 ksi)
T5 70.00-67.00	Pipe	P2.5x.276 GR	A500-50 (50 ksi)	Solid Round	5/8	A36 (36 ksi)
T6 67.00-64.00	Pipe	P2.5x.276 GR	A500-50 (50 ksi)	Solid Round	1 1/4	A36 (36 ksi)
T7 64.00-60.00	Pipe	P2.5x.276 GR	A500-50 (50 ksi)	Solid Round	1 1/4	A36 (36 ksi)
T8 60.00-53.17	Pipe	P3x.3 GR	A500M-61 (61 ksi)	Solid Round	3/4	A36 (36 ksi)
T9 53.17-50.00	Pipe	P3x.3 GR	A500M-61 (61 ksi)	Solid Round	3/4	A36 (36 ksi)
T10 50.00-46.83	Pipe	P3x.3 GR	A500M-61 (61 ksi)	Solid Round	3/4	A36 (36 ksi)
T11 46.83-43.67	Pipe	P3x.3 GR w/ .75 TR	A500M-61 (61 ksi)	Solid Round	3/4	A36 (36 ksi)
T12 43.67-40.00	Pipe	P3x.3 GR w/ .75 TR	A500M-61 (61 ksi)	Solid Round	3/4	A36 (36 ksi)
T13 40.00-20.00	Pipe	P5x.375 GR	A500-42 (42 ksi)	Single Angle	L2x2x3/16	A36 (36 ksi)
T14 20.00-0.00	Pipe	P5x.375 GR	A500-42 (42 ksi)	Single Angle	L2 1/2x2 1/2x3/16	A36 (36 ksi)

Tower Section Geometry (cont'd)

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	4 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Tower Elevation ft	Top Girt Type	Top Girt Size	Top Girt Grade	Bottom Girt Type	Bottom Girt Size	Bottom Girt Grade
T1 100.00-80.00	Single Angle	L1 1/2x1 1/2x3/16	A36 (36 ksi)	Single Angle	L1 1/2x1 1/2x3/16	A36 (36 ksi)
T2 80.00-76.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T3 76.00-73.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T4 73.00-70.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T5 70.00-67.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T6 67.00-64.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T7 64.00-60.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T8 60.00-53.17	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T9 53.17-50.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T10 50.00-46.83	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T11 46.83-43.67	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Solid Round		A36 (36 ksi)
T12 43.67-40.00	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)

Tower Section Geometry (cont'd)

Tower Elevation ft	No. of Mid Girts	Mid Girt Type	Mid Girt Size	Mid Girt Grade	Horizontal Type	Horizontal Size	Horizontal Grade
T1 100.00-80.00	None	Flat Bar		A36 (36 ksi)	Single Angle	L1 1/2x1 1/2x3/16	A36 (36 ksi)
T2 80.00-76.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T3 76.00-73.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T4 73.00-70.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T5 70.00-67.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T6 67.00-64.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T7 64.00-60.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T8 60.00-53.17	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T9 53.17-50.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T10 50.00-46.83	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T11 46.83-43.67	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)
T12 43.67-40.00	None	Flat Bar		A36 (36 ksi)	Double Angle	2L1 1/2x1 1/2x3/16x3/8	A36 (36 ksi)

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job 333-315	Page 5 of 24
	Project CT43XC836 - Danbury-W. CT. University	Date 15:17:04 09/24/14
	Client Sprint	Designed by MBecker

Tower Section Geometry (cont'd)

Tower Elevation	Secondary Horizontal Type	Secondary Horizontal Size	Secondary Horizontal Grade	Inner Bracing Type	Inner Bracing Size	Inner Bracing Grade
ft						
T9 53.17-50.00	Double Angle	2L2 1/2x2 1/2x5/16x3/8	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T10 50.00-46.83	Double Angle	2L2 1/2x2 1/2x5/16x3/8	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T11 46.83-43.67	Double Angle	2L2 1/2x2 1/2x5/16x3/8	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)
T12 43.67-40.00	Double Angle	2L2 1/2x2 1/2x5/16x3/8	A36 (36 ksi)	Solid Round		A572-50 (50 ksi)

Tower Section Geometry (cont'd)

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A_f	Adjust. Factor A_r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
ft	ft ²	in						
T1 100.00-80.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T2 80.00-76.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T3 76.00-73.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T4 73.00-70.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T5 70.00-67.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T6 67.00-64.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T7 64.00-60.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T8 60.00-53.17	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T9 53.17-50.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T10 50.00-46.83	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T11 46.83-43.67	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T12 43.67-40.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T13 40.00-20.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt
T14 20.00-0.00	0.00	0.0000	A36 (36 ksi)	1	1	1	36.0000	Mid-Pt

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	7 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Tower Elevation ft	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U	Net Width Deduct in	U
T10 50.00-46.83	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T11 46.83-43.67	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T12 43.67-40.00	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T13 40.00-20.00	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75
T14 20.00-0.00	0.0000	1	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75	0.0000	0.75

Tower Section Geometry (cont'd)

Tower Elevation ft	Leg Connection Type	Leg		Diagonal		Top Girt		Bottom Girt		Mid Girt		Long Horizontal		Short Horizontal	
		Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.	Bolt Size in	No.
T1 100.00-80.00	Flange	0.7500	4	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T2 80.00-76.00	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T3 76.00-73.00	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T4 73.00-70.00	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T5 70.00-67.00	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T6 67.00-64.00	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T7 64.00-60.00	Flange	0.7500	4	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T8 60.00-53.17	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T9 53.17-50.00	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T10 50.00-46.83	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T11 46.83-43.67	Flange	0.7500	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T12 43.67-40.00	Flange	1.0000	4	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T13 40.00-20.00	Flange	1.0000	6	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0
T14 20.00-0.00	Flange	1.5000	4	0.6250	1	0.6250	0	0.6250	0	0.6250	0	0.6250	0	0.6250	0

Feed Line/Linear Appurtenances - Entered As Round Or Flat

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	8 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Face Offset in	Lateral Offset (Frac FW)	#	# Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf
7/8	A	No	Ar (CaAa)	98.00 - 10.00	0.0000	0.1	16	9	0.0000	1.1100		0.54
1 5/8	A	No	Ar (CaAa)	98.00 - 10.00	-2.0000	0.12	6	6	0.0000	1.9800		1.04
1 5/8	A	No	Ar (CaAa)	96.00 - 10.00	0.0000	0.22	1	1	0.0000	1.9800		1.04
1/2	A	No	Ar (CaAa)	65.00 - 10.00	0.0000	0.26	1	1	0.0000	0.5800		0.25
1 5/8	C	No	Ar (CaAa)	83.00 - 10.00	0.0000	0	12	6	0.0000	1.9800		1.04
(T-Mobile) 1 1/4" Hybriflex Cable (Sprint) 0.3" (Sprint) ***	B	No	Ar (CaAa)	89.00 - 10.00	0.0000	0.25	3	3	0.0000	1.5400		1.00
1-1/4" Hybrid (Sprint)	B	No	Ar (CaAa)	89.00 - 10.00	0.0000	-0.1	1	1	0.0000	1.2500		0.83

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight lb
T1	100.00-80.00	A	0.000	0.000	56.520	0.000	284.48
		B	0.000	0.000	5.909	0.000	37.20
		C	0.000	0.000	7.128	0.000	37.44
T2	80.00-76.00	A	0.000	0.000	12.648	0.000	63.68
		B	0.000	0.000	2.626	0.000	16.53
		C	0.000	0.000	9.504	0.000	49.92
T3	76.00-73.00	A	0.000	0.000	9.486	0.000	47.76
		B	0.000	0.000	1.970	0.000	12.40
		C	0.000	0.000	7.128	0.000	37.44
T4	73.00-70.00	A	0.000	0.000	9.486	0.000	47.76
		B	0.000	0.000	1.970	0.000	12.40
		C	0.000	0.000	7.128	0.000	37.44
T5	70.00-67.00	A	0.000	0.000	9.486	0.000	47.76
		B	0.000	0.000	1.970	0.000	12.40
		C	0.000	0.000	7.128	0.000	37.44
T6	67.00-64.00	A	0.000	0.000	9.544	0.000	48.01
		B	0.000	0.000	1.970	0.000	12.40
		C	0.000	0.000	7.128	0.000	37.44
T7	64.00-60.00	A	0.000	0.000	12.880	0.000	64.68
		B	0.000	0.000	2.626	0.000	16.53
		C	0.000	0.000	9.504	0.000	49.92
T8	60.00-53.17	A	0.000	0.000	22.003	0.000	110.49
		B	0.000	0.000	4.487	0.000	28.24
		C	0.000	0.000	16.236	0.000	85.28
T9	53.17-50.00	A	0.000	0.000	10.197	0.000	51.21
		B	0.000	0.000	2.079	0.000	13.09
		C	0.000	0.000	7.524	0.000	39.52
T10	50.00-46.83	A	0.000	0.000	10.197	0.000	51.21
		B	0.000	0.000	2.079	0.000	13.09
		C	0.000	0.000	7.524	0.000	39.52
T11	46.83-43.67	A	0.000	0.000	10.197	0.000	51.21
		B	0.000	0.000	2.079	0.000	13.09
		C	0.000	0.000	7.524	0.000	39.52
T12	43.67-40.00	A	0.000	0.000	11.807	0.000	59.29
		B	0.000	0.000	2.408	0.000	15.15
		C	0.000	0.000	8.712	0.000	45.76

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	9 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight lb
T13	40.00-20.00	A	0.000	0.000	64.400	0.000	323.40
		B	0.000	0.000	13.132	0.000	82.66
		C	0.000	0.000	47.520	0.000	249.60
T14	20.00-0.00	A	0.000	0.000	32.200	0.000	161.70
		B	0.000	0.000	6.566	0.000	41.33
		C	0.000	0.000	23.760	0.000	124.80

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight lb
T1	100.00-80.00	A	1.658	0.000	0.000	77.112	0.000	1148.41
		B		0.000	0.000	18.189	0.000	230.79
		C		0.000	0.000	6.318	0.000	116.32
T2	80.00-76.00	A	1.635	0.000	0.000	17.292	0.000	255.79
		B		0.000	0.000	8.014	0.000	100.81
		C		0.000	0.000	8.393	0.000	153.61
T3	76.00-73.00	A	1.627	0.000	0.000	12.950	0.000	191.09
		B		0.000	0.000	5.994	0.000	75.19
		C		0.000	0.000	6.287	0.000	114.86
T4	73.00-70.00	A	1.621	0.000	0.000	12.933	0.000	190.43
		B		0.000	0.000	5.979	0.000	74.82
		C		0.000	0.000	6.281	0.000	114.55
T5	70.00-67.00	A	1.614	0.000	0.000	12.915	0.000	189.73
		B		0.000	0.000	5.963	0.000	74.43
		C		0.000	0.000	6.274	0.000	114.22
T6	67.00-64.00	A	1.606	0.000	0.000	13.276	0.000	193.56
		B		0.000	0.000	5.947	0.000	74.03
		C		0.000	0.000	6.266	0.000	113.88
T7	64.00-60.00	A	1.598	0.000	0.000	18.677	0.000	268.86
		B		0.000	0.000	7.904	0.000	98.06
		C		0.000	0.000	8.344	0.000	151.30
T8	60.00-53.17	A	1.583	0.000	0.000	31.802	0.000	455.56
		B		0.000	0.000	13.428	0.000	165.70
		C		0.000	0.000	14.220	0.000	256.92
T9	53.17-50.00	A	1.569	0.000	0.000	14.689	0.000	209.38
		B		0.000	0.000	6.188	0.000	75.95
		C		0.000	0.000	6.575	0.000	118.35
T10	50.00-46.83	A	1.559	0.000	0.000	14.657	0.000	208.21
		B		0.000	0.000	6.165	0.000	75.38
		C		0.000	0.000	6.564	0.000	117.86
T11	46.83-43.67	A	1.548	0.000	0.000	14.622	0.000	206.97
		B		0.000	0.000	6.140	0.000	74.78
		C		0.000	0.000	6.553	0.000	117.35
T12	43.67-40.00	A	1.536	0.000	0.000	16.885	0.000	238.00
		B		0.000	0.000	7.077	0.000	85.79
		C		0.000	0.000	7.573	0.000	135.19
T13	40.00-20.00	A	1.486	0.000	0.000	91.051	0.000	1261.12
		B		0.000	0.000	37.856	0.000	450.14
		C		0.000	0.000	40.974	0.000	721.97
T14	20.00-0.00	A	1.331	0.000	0.000	43.919	0.000	575.10
		B		0.000	0.000	17.781	0.000	198.82
		C		0.000	0.000	19.974	0.000	337.64

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	10 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Feed Line Center of Pressure

Section	Elevation	CP _x	CP _z	CP _x	CP _z
	ft	in	in	Ice in	Ice in
T1	100.00-80.00	-0.8307	-1.2840	-0.3323	-0.7397
T2	80.00-76.00	-0.4035	-0.1615	-0.1212	-0.3890
T3	76.00-73.00	-0.3971	-0.1589	-0.1335	-0.3835
T4	73.00-70.00	-0.3971	-0.1589	-0.1338	-0.3832
T5	70.00-67.00	-0.3971	-0.1589	-0.1341	-0.3830
T6	67.00-64.00	-0.3873	-0.1664	-0.1509	-0.4133
T7	64.00-60.00	-0.3941	-0.1916	-0.1717	-0.4805
T8	60.00-53.17	-0.3981	-0.1935	-0.1690	-0.4870
T9	53.17-50.00	-0.3790	-0.1842	-0.1800	-0.4505
T10	50.00-46.83	-0.3790	-0.1842	-0.1804	-0.4505
T11	46.83-43.67	-0.3790	-0.1842	-0.1807	-0.4505
T12	43.67-40.00	-0.3759	-0.1827	-0.1831	-0.4438
T13	40.00-20.00	-0.4863	-0.2668	-0.2148	-0.6256
T14	20.00-0.00	-0.5042	-0.3024	-0.2344	-0.6208

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
T1	1	7/8	80.00 - 98.00	0.6000	0.4098
T1	2	1 5/8	80.00 - 98.00	0.5000	0.5000
T1	3	1 5/8	80.00 - 96.00	0.6000	0.4098
T1	5	1 5/8	80.00 - 83.00	0.6000	0.4098
T1	6	1 1/4" Hybriflex Cable	80.00 - 89.00	0.6000	0.4098
T1	7	0.3"	80.00 - 89.00	0.6000	0.4098
T1	9	1-1/4" Hybrid	80.00 - 89.00	0.6000	0.4098
T2	1	7/8	76.00 - 80.00	0.6000	0.4903
T2	2	1 5/8	76.00 - 80.00	0.5000	0.5000
T2	3	1 5/8	76.00 - 80.00	0.6000	0.4903
T2	5	1 5/8	76.00 - 80.00	0.6000	0.4903
T2	6	1 1/4" Hybriflex Cable	76.00 - 80.00	0.6000	0.4903
T2	7	0.3"	76.00 - 80.00	0.6000	0.4903
T2	9	1-1/4" Hybrid	76.00 - 80.00	0.6000	0.4903
T3	1	7/8	73.00 - 76.00	0.6000	0.4072
T3	2	1 5/8	73.00 - 76.00	0.5000	0.5000
T3	3	1 5/8	73.00 - 76.00	0.6000	0.4072
T3	5	1 5/8	73.00 - 76.00	0.6000	0.4072
T3	6	1 1/4" Hybriflex Cable	73.00 - 76.00	0.6000	0.4072
T3	7	0.3"	73.00 - 76.00	0.6000	0.4072
T3	9	1-1/4" Hybrid	73.00 - 76.00	0.6000	0.4072
T4	1	7/8	70.00 - 73.00	0.6000	0.4087
T4	2	1 5/8	70.00 - 73.00	0.5000	0.5000
T4	3	1 5/8	70.00 - 73.00	0.6000	0.4087
T4	5	1 5/8	70.00 - 73.00	0.6000	0.4087
T4	6	1 1/4" Hybriflex Cable	70.00 - 73.00	0.6000	0.4087
T4	7	0.3"	70.00 - 73.00	0.6000	0.4087
T4	9	1-1/4" Hybrid	70.00 - 73.00	0.6000	0.4087
T5	1	7/8	67.00 - 70.00	0.6000	0.4102
T5	2	1 5/8	67.00 - 70.00	0.5000	0.5000
T5	3	1 5/8	67.00 - 70.00	0.6000	0.4102
T5	5	1 5/8	67.00 - 70.00	0.6000	0.4102
T5	6	1 1/4" Hybriflex Cable	67.00 - 70.00	0.6000	0.4102

tnxTower

Infinigy Engineering
 2255 Sewell Mill Road, Suite 130
 Marietta, GA 30062
 Phone: (678) 444-4463
 FAX: (678)444-4472

Job	333-315	Page	11 of 24
Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
Client	Sprint	Designed by	MBecker

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T5	7	0.3"	67.00 - 70.00	0.6000	0.4102
T5	9	1-1/4" Hybrid	67.00 - 70.00	0.6000	0.4102
T6	1	7/8	64.00 - 67.00	0.6000	0.3746
T6	2	1 5/8	64.00 - 67.00	0.5000	0.5000
T6	3	1 5/8	64.00 - 67.00	0.6000	0.3746
T6	4	1/2	64.00 - 65.00	0.6000	0.3746
T6	5	1 5/8	64.00 - 67.00	0.6000	0.3746
T6	6	1 1/4" Hybriflex Cable	64.00 - 67.00	0.6000	0.3746
T6	7	0.3"	64.00 - 67.00	0.6000	0.3746
T6	9	1-1/4" Hybrid	64.00 - 67.00	0.6000	0.3746
T7	1	7/8	60.00 - 64.00	0.6000	0.3897
T7	2	1 5/8	60.00 - 64.00	0.5000	0.5000
T7	3	1 5/8	60.00 - 64.00	0.6000	0.3897
T7	4	1/2	60.00 - 64.00	0.6000	0.3897
T7	5	1 5/8	60.00 - 64.00	0.6000	0.3897
T7	6	1 1/4" Hybriflex Cable	60.00 - 64.00	0.6000	0.3897
T7	7	0.3"	60.00 - 64.00	0.6000	0.3897
T7	9	1-1/4" Hybrid	60.00 - 64.00	0.6000	0.3897
T8	1	7/8	53.17 - 60.00	0.6000	0.4298
T8	2	1 5/8	53.17 - 60.00	0.5000	0.5000
T8	3	1 5/8	53.17 - 60.00	0.6000	0.4298
T8	4	1/2	53.17 - 60.00	0.6000	0.4298
T8	5	1 5/8	53.17 - 60.00	0.6000	0.4298
T8	6	1 1/4" Hybriflex Cable	53.17 - 60.00	0.6000	0.4298
T8	7	0.3"	53.17 - 60.00	0.6000	0.4298
T8	9	1-1/4" Hybrid	53.17 - 60.00	0.6000	0.4298
T9	1	7/8	50.00 - 53.17	0.6000	0.2947
T9	2	1 5/8	50.00 - 53.17	0.5000	0.5000
T9	3	1 5/8	50.00 - 53.17	0.6000	0.2947
T9	4	1/2	50.00 - 53.17	0.6000	0.2947
T9	5	1 5/8	50.00 - 53.17	0.6000	0.2947
T9	6	1 1/4" Hybriflex Cable	50.00 - 53.17	0.6000	0.2947
T9	7	0.3"	50.00 - 53.17	0.6000	0.2947
T9	9	1-1/4" Hybrid	50.00 - 53.17	0.6000	0.2947
T10	1	7/8	46.83 - 50.00	0.6000	0.2971
T10	2	1 5/8	46.83 - 50.00	0.5000	0.5000
T10	3	1 5/8	46.83 - 50.00	0.6000	0.2971
T10	4	1/2	46.83 - 50.00	0.6000	0.2971
T10	5	1 5/8	46.83 - 50.00	0.6000	0.2971
T10	6	1 1/4" Hybriflex Cable	46.83 - 50.00	0.6000	0.2971
T10	7	0.3"	46.83 - 50.00	0.6000	0.2971
T10	9	1-1/4" Hybrid	46.83 - 50.00	0.6000	0.2971
T11	1	7/8	43.67 - 46.83	0.6000	0.2998
T11	2	1 5/8	43.67 - 46.83	0.5000	0.5000
T11	3	1 5/8	43.67 - 46.83	0.6000	0.2998
T11	4	1/2	43.67 - 46.83	0.6000	0.2998
T11	5	1 5/8	43.67 - 46.83	0.6000	0.2998
T11	6	1 1/4" Hybriflex Cable	43.67 - 46.83	0.6000	0.2998
T11	7	0.3"	43.67 - 46.83	0.6000	0.2998
T11	9	1-1/4" Hybrid	43.67 - 46.83	0.6000	0.2998
T12	1	7/8	40.00 - 43.67	0.6000	0.2786
T12	2	1 5/8	40.00 - 43.67	0.5000	0.5000
T12	3	1 5/8	40.00 - 43.67	0.6000	0.2786
T12	4	1/2	40.00 - 43.67	0.6000	0.2786
T12	5	1 5/8	40.00 - 43.67	0.6000	0.2786
T12	6	1 1/4" Hybriflex Cable	40.00 - 43.67	0.6000	0.2786
T12	7	0.3"	40.00 - 43.67	0.6000	0.2786
T12	9	1-1/4" Hybrid	40.00 - 43.67	0.6000	0.2786
T13	1	7/8	20.00 - 40.00	0.6000	0.5564
T13	2	1 5/8	20.00 - 40.00	0.5000	0.5000
T13	3	1 5/8	20.00 - 40.00	0.6000	0.5564
T13	4	1/2	20.00 - 40.00	0.6000	0.5564

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job 333-315	Page 12 of 24
	Project CT43XC836 - Danbury-W. CT. University	Date 15:17:04 09/24/14
	Client Sprint	Designed by MBecker

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K_a No Ice	K_a Ice
T13	5	1 5/8	20.00 - 40.00	0.6000	0.5564
T13	6	1 1/4" Hybriflex Cable	20.00 - 40.00	0.6000	0.5564
T13	7	0.3"	20.00 - 40.00	0.6000	0.5564
T13	9	1-1/4" Hybrid	20.00 - 40.00	0.6000	0.5564
T14	1	7/8	10.00 - 20.00	0.6000	0.6000
T14	2	1 5/8	10.00 - 20.00	0.5000	0.5000
T14	3	1 5/8	10.00 - 20.00	0.6000	0.6000
T14	4	1/2	10.00 - 20.00	0.6000	0.6000
T14	5	1 5/8	10.00 - 20.00	0.6000	0.6000
T14	6	1 1/4" Hybriflex Cable	10.00 - 20.00	0.6000	0.6000
T14	7	0.3"	10.00 - 20.00	0.6000	0.6000
T14	9	1-1/4" Hybrid	10.00 - 20.00	0.6000	0.6000

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment °	Placement ft	C_{AA} Front ft^2	C_{AA} Side ft^2	Weight lb	
Angle Sector Frame	A	From Leg	1.00	0.0000	98.00	No Ice	17.90	8.95	400.00
			0.00			1/2" Ice	22.20	13.00	510.00
			0.00			1" Ice	26.50	17.05	620.00
Angle Sector Frame	B	From Leg	1.00	0.0000	98.00	No Ice	17.90	8.95	400.00
			0.00			1/2" Ice	22.20	13.00	510.00
			0.00			1" Ice	26.50	17.05	620.00
Angle Sector Frame	C	From Leg	1.00	0.0000	98.00	No Ice	17.90	8.95	400.00
			0.00			1/2" Ice	22.20	13.00	510.00
			0.00			1" Ice	26.50	17.05	620.00
(4) DB844H90	A	From Leg	3.00	0.0000	98.00	No Ice	2.87	3.97	10.00
			0.00			1/2" Ice	3.18	4.34	36.27
			0.00			1" Ice	3.52	4.72	66.78
(4) DB844H90	B	From Leg	3.00	0.0000	98.00	No Ice	2.87	3.97	10.00
			0.00			1/2" Ice	3.18	4.34	36.27
			0.00			1" Ice	3.52	4.72	66.78
(2) 60"x12" Panel	C	From Leg	3.00	0.0000	98.00	No Ice	7.00	3.75	40.00
			0.00			1/2" Ice	7.47	4.13	79.89
			0.00			1" Ice	7.95	4.51	125.04
(2) 72" x 12" Panel	C	From Leg	3.00	0.0000	98.00	No Ice	8.40	4.70	45.00
			0.00			1/2" Ice	8.95	5.15	92.28
			0.00			1" Ice	9.51	5.60	145.59

Dish Pipe Mount	C	From Leg	1.00	0.0000	96.00	No Ice	2.09	2.09	54.66
			0.00			1/2" Ice	2.46	2.46	80.59
			0.00			1" Ice	2.85	2.85	110.49

APXVSP18-C-A20 (Sprint)	A	From Leg	3.00	0.0000	89.00	No Ice	8.26	5.28	57.00
			0.00			1/2" Ice	8.81	5.74	106.52
			0.00			1" Ice	9.36	6.20	162.12
APXVSP18-C-A20 (Sprint)	B	From Leg	3.00	0.0000	89.00	No Ice	8.26	5.28	57.00
			0.00			1/2" Ice	8.81	5.74	106.52
			0.00			1" Ice	9.36	6.20	162.12
APXVSP18-C-A20	C	From Leg	3.00	0.0000	89.00	No Ice	8.26	5.28	57.00

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	13 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
(Sprint)			0.00			1/2" Ice	8.81	5.74	106.52
			0.00			1" Ice	9.36	6.20	162.12
(2) 1900 MHz RRH (Sprint)	A	From Leg	3.00	0.0000	89.00	No Ice	2.73	1.45	44.09
			0.00			1/2" Ice	2.96	1.64	62.32
			0.00			1" Ice	3.20	1.84	83.43
(2) 1900 MHz RRH (Sprint)	B	From Leg	3.00	0.0000	89.00	No Ice	2.73	1.45	44.09
			0.00			1/2" Ice	2.96	1.64	62.32
			0.00			1" Ice	3.20	1.84	83.43
(2) 1900 MHz RRH (Sprint)	C	From Leg	3.00	0.0000	89.00	No Ice	2.73	1.45	44.09
			0.00			1/2" Ice	2.96	1.64	62.32
			0.00			1" Ice	3.20	1.84	83.43
800 MHz RRH (Sprint)	A	From Leg	3.00	0.0000	89.00	No Ice	2.25	2.40	64.00
			0.00			1/2" Ice	2.46	2.61	86.12
			0.00			1" Ice	2.68	2.83	111.30
800 MHz RRH (Sprint)	B	From Leg	3.00	0.0000	89.00	No Ice	2.25	2.40	64.00
			0.00			1/2" Ice	2.46	2.61	86.12
			0.00			1" Ice	2.68	2.83	111.30
800 MHz RRH (Sprint)	C	From Leg	3.00	0.0000	89.00	No Ice	2.25	2.40	64.00
			0.00			1/2" Ice	2.46	2.61	86.12
			0.00			1" Ice	2.68	2.83	111.30

APX16PV-16PVL (T-Mobile)	A	From Leg	1.00	0.0000	83.00	No Ice	6.80	3.31	46.95
			0.00			1/2" Ice	7.27	3.94	93.66
			0.00			1" Ice	7.75	4.58	147.19
APX16PV-16PVL (T-Mobile)	B	From Leg	1.00	0.0000	83.00	No Ice	6.80	3.31	46.95
			0.00			1/2" Ice	7.27	3.94	93.66
			0.00			1" Ice	7.75	4.58	147.19
APX16PV-16PVL (T-Mobile)	C	From Leg	1.00	0.0000	83.00	No Ice	6.80	3.31	46.95
			0.00			1/2" Ice	7.27	3.94	93.66
			0.00			1" Ice	7.75	4.58	147.19
(2) ATMAA1412D-1A20 TMA (T-Mobile)	A	From Leg	1.00	0.0000	80.00	No Ice	1.17	0.47	13.00
			0.00			1/2" Ice	1.31	0.57	20.62
			0.00			1" Ice	1.47	0.69	30.11
(2) ATMAA1412D-1A20 TMA (T-Mobile)	B	From Leg	1.00	0.0000	80.00	No Ice	1.17	0.47	13.00
			0.00			1/2" Ice	1.31	0.57	20.62
			0.00			1" Ice	1.47	0.69	30.11
Antenna Pipe Mount (T-Mobile)	A	From Leg	1.00	0.0000	81.00	No Ice	0.87	0.87	14.60
			0.00			1/2" Ice	1.12	1.12	25.30
			0.00			1" Ice	1.39	1.39	37.43
Antenna Pipe Mount (T-Mobile)	B	From Leg	1.00	0.0000	81.00	No Ice	0.87	0.87	14.60
			0.00			1/2" Ice	1.12	1.12	25.30
			0.00			1" Ice	1.39	1.39	37.43

6810	C	From Leg	1.00	0.0000	65.00	No Ice	22.30	22.30	354.00
			0.00			1/2" Ice	40.14	40.14	460.20
			0.00			1" Ice	57.98	57.98	566.40

Angle Side Arm (Sprint)	C	From Leg	1.00	0.0000	30.00	No Ice	6.30	2.14	150.00
			0.00			1/2" Ice	7.00	2.60	230.00
			0.00			1" Ice	7.70	3.06	310.00
GPS (Sprint)	C	From Leg	2.00	0.0000	30.00	No Ice	0.50	0.50	10.00
			0.00			1/2" Ice	0.63	0.63	15.96
			0.00			1" Ice	0.78	0.78	23.49

Pipe Sector Frame	A	From Leg	3.00	0.0000	89.00	No Ice	14.40	7.20	300.00

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job 333-315	Page 14 of 24
	Project CT43XC836 - Danbury-W. CT. University	Date 15:17:04 09/24/14
	Client Sprint	Designed by MBecker

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz Lateral	Vert					
			ft	ft	°	ft	ft ²	ft ²	lb
(Sprint)			0.00			1/2" Ice	19.50	10.50	415.00
			0.00			1" Ice	24.60	13.80	530.00
Pipe Sector Frame (Sprint)	B	From Leg	3.00		0.0000	No Ice	14.40	7.20	300.00
			0.00			1/2" Ice	19.50	10.50	415.00
			0.00			1" Ice	24.60	13.80	530.00
Pipe Sector Frame (Sprint)	C	From Leg	3.00		0.0000	No Ice	14.40	7.20	300.00
			0.00			1/2" Ice	19.50	10.50	415.00
			0.00			1" Ice	24.60	13.80	530.00
APXVTM14-C-120 (Sprint)	A	From Leg	3.00		0.0000	No Ice	6.53	3.38	52.90
			0.00			1/2" Ice	6.96	3.72	90.49
			0.00			1" Ice	7.40	4.07	132.96
APXVTM14-C-120 (Sprint)	B	From Leg	3.00		0.0000	No Ice	6.53	3.38	52.90
			0.00			1/2" Ice	6.96	3.72	90.49
			0.00			1" Ice	7.40	4.07	132.96
APXVTM14-C-120 (Sprint)	C	From Leg	3.00		0.0000	No Ice	6.53	3.38	52.90
			0.00			1/2" Ice	6.96	3.72	90.49
			0.00			1" Ice	7.40	4.07	132.96
TD-RRH8X20 (Sprint)	A	From Leg	3.00		0.0000	No Ice	4.32	1.41	66.14
			0.00			1/2" Ice	4.60	1.61	90.08
			0.00			1" Ice	4.89	1.83	117.36
TD-RRH8X20 (Sprint)	B	From Leg	3.00		0.0000	No Ice	4.32	1.41	66.14
			0.00			1/2" Ice	4.60	1.61	90.08
			0.00			1" Ice	4.89	1.83	117.36
TD-RRH8X20 (Sprint)	C	From Leg	3.00		0.0000	No Ice	4.32	1.41	66.14
			0.00			1/2" Ice	4.60	1.61	90.08
			0.00			1" Ice	4.89	1.83	117.36

Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight	
				Horz Lateral	Vert							
				ft	°	°	ft	ft	ft ²	lb		
2' x 4' Rectangular Grid Dish		Grid	None			0.0000		96.00	3.00	No Ice	7.07	40.00
				1/2" Ice	7.47		78.35					
				1" Ice	7.86		116.69					

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.6 Wind 0 deg - No Ice
3	1.2D+1.6W (pattern 1) 0 deg - No Ice
4	1.2D+1.6W (pattern 2) 0 deg - No Ice
5	0.9 Dead+1.6 Wind 0 deg - No Ice
6	1.2 Dead+1.6 Wind 30 deg - No Ice

<p style="text-align: center;">tnxTower</p> <p style="text-align: center;">Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472</p>	<p style="text-align: center;">Job</p> <p style="text-align: center;">333-315</p>	<p style="text-align: center;">Page</p> <p style="text-align: center;">15 of 24</p>
	<p style="text-align: center;">Project</p> <p style="text-align: center;">CT43XC836 - Danbury-W. CT. University</p>	<p style="text-align: center;">Date</p> <p style="text-align: center;">15:17:04 09/24/14</p>
	<p style="text-align: center;">Client</p> <p style="text-align: center;">Sprint</p>	<p style="text-align: center;">Designed by</p> <p style="text-align: center;">MBecker</p>

<i>Comb. No.</i>	<i>Description</i>
7	1.2D+1.6W (pattern 1) 30 deg - No Ice
8	1.2D+1.6W (pattern 2) 30 deg - No Ice
9	0.9 Dead+1.6 Wind 30 deg - No Ice
10	1.2 Dead+1.6 Wind 60 deg - No Ice
11	1.2D+1.6W (pattern 1) 60 deg - No Ice
12	1.2D+1.6W (pattern 2) 60 deg - No Ice
13	0.9 Dead+1.6 Wind 60 deg - No Ice
14	1.2 Dead+1.6 Wind 90 deg - No Ice
15	1.2D+1.6W (pattern 1) 90 deg - No Ice
16	1.2D+1.6W (pattern 2) 90 deg - No Ice
17	0.9 Dead+1.6 Wind 90 deg - No Ice
18	1.2 Dead+1.6 Wind 120 deg - No Ice
19	1.2D+1.6W (pattern 1) 120 deg - No Ice
20	1.2D+1.6W (pattern 2) 120 deg - No Ice
21	0.9 Dead+1.6 Wind 120 deg - No Ice
22	1.2 Dead+1.6 Wind 150 deg - No Ice
23	1.2D+1.6W (pattern 1) 150 deg - No Ice
24	1.2D+1.6W (pattern 2) 150 deg - No Ice
25	0.9 Dead+1.6 Wind 150 deg - No Ice
26	1.2 Dead+1.6 Wind 180 deg - No Ice
27	1.2D+1.6W (pattern 1) 180 deg - No Ice
28	1.2D+1.6W (pattern 2) 180 deg - No Ice
29	0.9 Dead+1.6 Wind 180 deg - No Ice
30	1.2 Dead+1.6 Wind 210 deg - No Ice
31	1.2D+1.6W (pattern 1) 210 deg - No Ice
32	1.2D+1.6W (pattern 2) 210 deg - No Ice
33	0.9 Dead+1.6 Wind 210 deg - No Ice
34	1.2 Dead+1.6 Wind 240 deg - No Ice
35	1.2D+1.6W (pattern 1) 240 deg - No Ice
36	1.2D+1.6W (pattern 2) 240 deg - No Ice
37	0.9 Dead+1.6 Wind 240 deg - No Ice
38	1.2 Dead+1.6 Wind 270 deg - No Ice
39	1.2D+1.6W (pattern 1) 270 deg - No Ice
40	1.2D+1.6W (pattern 2) 270 deg - No Ice
41	0.9 Dead+1.6 Wind 270 deg - No Ice
42	1.2 Dead+1.6 Wind 300 deg - No Ice
43	1.2D+1.6W (pattern 1) 300 deg - No Ice
44	1.2D+1.6W (pattern 2) 300 deg - No Ice
45	0.9 Dead+1.6 Wind 300 deg - No Ice
46	1.2 Dead+1.6 Wind 330 deg - No Ice
47	1.2D+1.6W (pattern 1) 330 deg - No Ice
48	1.2D+1.6W (pattern 2) 330 deg - No Ice
49	0.9 Dead+1.6 Wind 330 deg - No Ice
50	1.2 Dead+1.0 Ice+1.0 Temp
51	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
52	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
53	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
54	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
55	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
56	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
57	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
58	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
59	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
60	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
61	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
62	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
63	Dead+Wind 0 deg - Service
64	Dead+Wind 30 deg - Service
65	Dead+Wind 60 deg - Service
66	Dead+Wind 90 deg - Service
67	Dead+Wind 120 deg - Service
68	Dead+Wind 150 deg - Service

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	16 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

<i>Comb. No.</i>	<i>Description</i>
69	Dead+Wind 180 deg - Service
70	Dead+Wind 210 deg - Service
71	Dead+Wind 240 deg - Service
72	Dead+Wind 270 deg - Service
73	Dead+Wind 300 deg - Service
74	Dead+Wind 330 deg - Service

Maximum Tower Deflections - Service Wind

<i>Section No.</i>	<i>Elevation ft</i>	<i>Horz. Deflection in</i>	<i>Gov. Load Comb.</i>	<i>Tilt °</i>	<i>Twist °</i>
T1	100 - 80	5.059	71	0.4422	0.0458
T2	80 - 76	3.207	71	0.4201	0.0420
T3	76 - 73	2.840	71	0.4072	0.0411
T4	73 - 70	2.582	71	0.3949	0.0407
T5	70 - 67	2.332	71	0.3804	0.0403
T6	67 - 64	2.091	71	0.3636	0.0400
T7	64 - 60	1.867	71	0.3448	0.0397
T8	60 - 53.1667	1.574	71	0.3149	0.0348
T9	53.1667 - 50	1.138	71	0.2682	0.0272
T10	50 - 46.8334	0.963	71	0.2428	0.0243
T11	46.8334 - 43.6667	0.804	71	0.2148	0.0214
T12	43.6667 - 40	0.666	71	0.1843	0.0186
T13	40 - 20	0.531	71	0.1456	0.0148
T14	20 - 0	0.117	71	0.0592	0.0033

Critical Deflections and Radius of Curvature - Service Wind

<i>Elevation ft</i>	<i>Appurtenance</i>	<i>Gov. Load Comb.</i>	<i>Deflection in</i>	<i>Tilt °</i>	<i>Twist °</i>	<i>Radius of Curvature ft</i>
98.00	Angle Sector Frame	71	4.875	0.4416	0.0455	252848
96.00	2' x 4' Rectangular Grid Dish	71	4.690	0.4409	0.0452	252848
89.00	APXVSP18-C-A20	71	4.044	0.4363	0.0440	114931
83.00	APX16PV-16PVL	71	3.487	0.4272	0.0428	94449
81.00	Antenna Pipe Mount	71	3.300	0.4227	0.0423	71254
80.00	(2) ATMAA1412D-1A20 TMA	71	3.207	0.4201	0.0420	28418
65.00	6810	71	1.941	0.3515	0.0401	12287
30.00	Angle Side Arm	71	0.267	0.0833	0.0072	10589

Maximum Tower Deflections - Design Wind

<i>Section No.</i>	<i>Elevation ft</i>	<i>Horz. Deflection in</i>	<i>Gov. Load Comb.</i>	<i>Tilt °</i>	<i>Twist °</i>
T1	100 - 80	22.192	34	1.9333	0.2774
T2	80 - 76	14.108	37	1.8410	0.2556
T3	76 - 73	12.498	37	1.7848	0.2460
T4	73 - 70	11.373	37	1.7310	0.2436
T5	70 - 67	10.279	37	1.6675	0.2391

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job 333-315	Page 17 of 24
	Project CT43XC836 - Danbury-W. CT. University	Date 15:17:04 09/24/14
	Client Sprint	Designed by MBecker

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
T6	67 - 64	9.224	37	1.5937	0.2356
T7	64 - 60	8.245	37	1.5115	0.2341
T8	60 - 53.1667	6.964	37	1.3813	0.2115
T9	53.1667 - 50	5.035	37	1.1778	0.1687
T10	50 - 46.8334	4.257	37	1.0663	0.1495
T11	46.8334 - 43.6667	3.554	37	0.9437	0.1267
T12	43.6667 - 40	2.932	37	0.8098	0.0997
T13	40 - 20	2.339	34	0.6398	0.0664
T14	20 - 0	0.517	34	0.2608	0.0146

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
98.00	Angle Sector Frame	34	21.386	1.9312	0.2768	56175
96.00	2' x 4' Rectangular Grid Dish	34	20.579	1.9287	0.2761	56175
89.00	APXVSP18-C-A20	37	17.762	1.9103	0.2715	25534
83.00	APX16PV-16PVL	37	15.332	1.8719	0.2627	21108
81.00	Antenna Pipe Mount	37	14.517	1.8523	0.2582	18393
80.00	(2) ATMAA1412D-1A20 TMA	37	14.108	1.8410	0.2556	6721
65.00	6810	37	8.567	1.5406	0.2359	2763
30.00	Angle Side Arm	34	1.177	0.3660	0.0325	2322

Bolt Design Data

Section No.	Elevation ft	Component Type	Bolt Grade	Bolt Size in	Number Of Bolts	Maximum Load per Bolt lb	Allowable Load lb	Ratio Load/Allowable	Allowable Ratio	Criteria
T1	100	Leg	A325N	0.7500	4	0.46	29820.60	0.000	✓	1 Bolt Tension
T7	64	Leg	A325N	0.7500	4	14379.00	29820.60	0.482	✓	1 Bolt Tension
T12	43.6667	Leg	A325N	1.0000	4	32412.40	53014.40	0.611	✓	1 Bolt Tension
T13	40	Leg	A325N	1.0000	6	24078.40	53014.40	0.454	✓	1 Bolt Tension
		Diagonal	A325N	0.6250	1	3001.40	6830.86	0.439	✓	1 Member Block Shear
T14	20	Leg	A36	1.5000	4	35596.50	47712.90	0.746	✓	1 Bolt Tension
		Diagonal	A325N	0.6250	1	1644.63	7830.00	0.210	✓	1 Member Bearing

Compression Checks

Leg Design Data (Compression)

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	18 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	100 - 80	P2.5x.276	20.00	3.28	42.6 K=1.00	2.2535	-31983.50	88826.50	0.360 ¹
T2	80 - 76	P2.5x.276 GR	4.00	3.00	33.1 K=0.85	2.2535	-41373.10	93595.70	0.442 ¹
T3	76 - 73	P2.5x.276 GR	3.00	3.00	33.1 K=0.85	2.2535	-49159.60	93595.70	0.525 ¹
T4	73 - 70	P2.5x.276 GR	3.00	3.00	33.1 K=0.85	2.2535	-56676.60	93595.70	0.606 ¹
T5	70 - 67	P2.5x.276 GR	3.00	3.00	33.1 K=0.85	2.2535	-64252.30	93595.70	0.686 ¹
T6	67 - 64	P2.5x.276 GR	3.00	3.00	33.1 K=0.85	2.2535	-79929.30	93595.70	0.854 ¹
T7	64 - 60	P2.5x.276 GR	4.00	3.00	33.1 K=0.85	2.2535	-90404.00	93595.70	0.966 ¹
T8	60 - 53.1667	P3x.3 GR	6.83	3.25	29.2 K=0.85	3.0159	-108935.00	153470.00	0.710 ¹
T9	53.1667 - 50	P3x.3 GR	3.17	1.58	14.2 K=0.85	3.0159	-119589.00	162618.00	0.735 ¹
T10	50 - 46.8334	P3x.3 GR	3.17	1.58	14.2 K=0.85	3.0159	-130626.00	162618.00	0.803 ¹
T11	46.8334 - 43.6667	P3x.3 GR w/ .75 TR	3.17	1.58	14.2 K=0.85	3.0159	-141856.00	162618.00	0.872 ¹
T12	43.6667 - 40	P3x.3 GR w/ .75 TR	3.67	1.58	14.2 K=0.85	3.0159	-153963.00	162618.00	0.947 ¹
T13	40 - 20	P5x.375 GR	20.03	6.57	0.4 K=0.01	6.1114	-154086.00	231008.00	0.667 ¹
T14	20 - 0	P5x.375 GR	20.03	6.57	0.4 K=0.01	6.1114	-159113.00	231008.00	0.689 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T13	40 - 20	L2x2x3/16	7.60	3.63	112.9 K=1.02	0.7150	-3491.24	11837.70	0.295 ¹
T14	20 - 0	L2 1/2x2 1/2x3/16	9.71	4.64	114.4 K=1.02	0.9020	-1875.85	14675.40	0.128 ¹

¹ P_u / φP_n controls

Horizontal Design Data (Compression)

<p>tnxTower</p> <p>Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472</p>	Job 333-315	Page 19 of 24
	Project CT43XC836 - Danbury-W. CT. University	Date 15:17:04 09/24/14
	Client Sprint	Designed by MBecker

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	100 - 80	L1 1/2x1 1/2x3/16	3.50	3.26	133.4 K=1.00	0.5273	-5992.93	6697.95	0.895 ¹ ✓
T8	60 - 53.1667	2L1 1/2x1 1/2x3/16x3/8 2L 'a' > 18.5481 in - 149	3.50	3.21	84.3 K=1.00	1.0547	-12810.00	23505.80	0.545 ¹ ✓

¹ P_u / φP_n controls

Secondary Horizontal Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T9	53.1667 - 50	2L2 1/2x2 1/2x5/16x3/8	3.50	3.21	50.8 K=1.00	2.9300	-1718.66	82879.60	0.021 ¹ ✓
T10	50 - 46.8334	2L 'a' > 18.5544 in - 170 2L2 1/2x2 1/2x5/16x3/8	3.50	3.21	50.8 K=1.00	2.9300	-2367.78	82879.60	0.029 ¹ ✓
T11	46.8334 - 43.6667	2L 'a' > 18.5544 in - 185 2L2 1/2x2 1/2x5/16x3/8	3.50	3.21	50.8 K=1.00	2.9300	-2468.66	82879.60	0.030 ¹ ✓
T12	43.6667 - 40	2L 'a' > 18.5544 in - 200 2L2 1/2x2 1/2x5/16x3/8 2L 'a' > 18.5544 in - 218	3.50	3.21	50.8 K=1.00	2.9300	-1845.98	82879.60	0.022 ¹ ✓

¹ P_u / φP_n controls

Top Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	100 - 80	L1 1/2x1 1/2x3/16	3.50	3.26	133.4 K=1.00	0.5273	-3119.49	6697.95	0.466 ¹ ✓
T2	80 - 76	2L1 1/2x1 1/2x3/16x3/8	3.50	3.26	85.7 K=1.00	1.0547	-4382.27	23219.70	0.189 ¹ ✓
T3	76 - 73	2L 'a' > 18.8492 in - 65 2L1 1/2x1 1/2x3/16x3/8	3.50	3.26	85.7 K=1.00	1.0547	-8552.41	23219.70	0.368 ¹ ✓
T4	73 - 70	2L 'a' > 18.8492 in - 77 2L1 1/2x1 1/2x3/16x3/8	3.50	3.26	85.7 K=1.00	1.0547	-8196.18	23219.70	0.353 ¹ ✓
T5	70 - 67	2L 'a' > 18.8492 in - 89 2L1 1/2x1 1/2x3/16x3/8	3.50	3.26	85.7 K=1.00	1.0547	-8227.96	23219.70	0.354 ¹ ✓
T6	67 - 64	2L 'a' > 18.8492 in - 101 2L1 1/2x1 1/2x3/16x3/8	3.50	3.26	85.7	1.0547	-15207.50	23219.70	0.655 ¹

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	20 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
					K=1.00				✓
T7	64 - 60	2L 'a' > 18.8492 in - 113 2L1 1/2x1 1/2x3/16x3/8	3.50	3.26	85.7 K=1.00	1.0547	-22847.60	23219.70	0.984 ¹ ✓
T8	60 - 53.1667	2L 'a' > 18.8492 in - 125 2L1 1/2x1 1/2x3/16x3/8	3.50	3.21	84.3 K=1.00	1.0547	-5133.18	23505.80	0.218 ¹ ✓
T9	53.1667 - 50	2L 'a' > 18.5481 in - 141 2L1 1/2x1 1/2x3/16x3/8	3.50	3.21	84.3 K=1.00	1.0547	-11565.70	23505.80	0.492 ¹ ✓
T10	50 - 46.8334	2L 'a' > 18.5481 in - 161 2L1 1/2x1 1/2x3/16x3/8	3.50	3.21	84.3 K=1.00	1.0547	-10933.70	23505.80	0.465 ¹ ✓
T11	46.8334 - 43.6667	2L 'a' > 18.5481 in - 176 2L1 1/2x1 1/2x3/16x3/8	3.50	3.21	84.3 K=1.00	1.0547	-11144.60	23505.80	0.474 ¹ ✓
T12	43.6667 - 40	2L 'a' > 18.5481 in - 191 2L1 1/2x1 1/2x3/16x3/8	3.50	3.21	84.3 K=1.00	1.0547	-12063.20	23505.80	0.513 ¹ ✓
		2L 'a' > 18.5481 in - 206							✓

¹ P_u / φP_n controls

Bottom Girt Design Data (Compression)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	100 - 80	L1 1/2x1 1/2x3/16	3.50	3.26	133.4 K=1.00	0.5273	-4596.48	6697.95	0.686 ¹ ✓
T7	64 - 60	2L1 1/2x1 1/2x3/16x3/8	3.50	3.26	85.7 K=1.00	1.0547	-14122.30	23219.70	0.608 ¹ ✓
T12	43.6667 - 40	2L 'a' > 18.8492 in - 128 2L1 1/2x1 1/2x3/16x3/8	3.50	3.21	84.3 K=1.00	1.0547	-5821.61	23505.80	0.248 ¹ ✓
		2L 'a' > 18.5481 in - 209							✓

¹ P_u / φP_n controls

Tension Checks

Leg Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
-------------	-----------------	------	---------	----------------------	------	----------------------	----------------------	-----------------------	---------------------------------

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	21 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	100 - 80	P2.5x.276	20.00	3.28	42.6	2.2535	27257.10	101409.00	0.269 ¹
T2	80 - 76	P2.5x.276 GR	4.00	3.00	39.0	2.2535	27257.10	101409.00	0.269 ¹
T3	76 - 73	P2.5x.276 GR	3.00	3.00	39.0	2.2535	34551.30	101409.00	0.341 ¹
T4	73 - 70	P2.5x.276 GR	3.00	3.00	39.0	2.2535	41739.90	101409.00	0.412 ¹
T5	70 - 67	P2.5x.276 GR	3.00	3.00	39.0	2.2535	49866.60	101409.00	0.492 ¹
T6	67 - 64	P2.5x.276 GR	3.00	3.00	39.0	2.2535	49413.50	101409.00	0.487 ¹
T7	64 - 60	P2.5x.276 GR	4.00	3.00	39.0	2.2535	77251.80	101409.00	0.762 ¹
T8	60 - 53.1667	P3x.3 GR	6.83	3.25	34.3	3.0159	87714.40	165575.00	0.530 ¹
T9	53.1667 - 50	P3x.3 GR	3.17	1.58	16.7	3.0159	97708.10	165575.00	0.590 ¹
T10	50 - 46.8334	P3x.3 GR	3.17	1.58	16.7	3.0159	108176.00	165575.00	0.653 ¹
T11	46.8334 - 43.6667	P3x.3 GR w/ .75 TR	3.17	1.58	16.7	3.0159	118996.00	165575.00	0.719 ¹
T12	43.6667 - 40	P3x.3 GR w/ .75 TR	3.67	1.58	16.7	3.0159	144349.00	165575.00	0.872 ¹
T13	40 - 20	P5x.375 GR	20.03	6.57	42.9	6.1114	144470.00	231010.00	0.625 ¹
T14	20 - 0	P5x.375 GR	20.03	6.57	42.9	6.1114	146248.00	231010.00	0.633 ¹

¹ P_u / φP_n controls

Diagonal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T1	100 - 80	5/8	4.80	4.47	343.1	0.3068	7797.94	9940.20	0.784 ¹
T2	80 - 76	5/8	4.61	4.29	329.8	0.3068	8645.54	9940.20	0.870 ¹
T3	76 - 73	5/8	4.61	4.29	329.8	0.3068	7648.01	9940.20	0.769 ¹
T4	73 - 70	5/8	4.61	4.29	329.8	0.3068	8085.82	9940.20	0.813 ¹
T5	70 - 67	5/8	4.61	4.29	329.8	0.3068	7768.93	9940.20	0.782 ¹
T6	67 - 64	1 1/4	4.61	4.29	164.9	1.2272	15975.60	39760.80	0.402 ¹
T7	64 - 60	1 1/4	4.61	4.29	164.9	1.2272	18330.60	39760.80	0.461 ¹

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	22 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T8	60 - 53.1667	3/4	4.78	4.38	280.2	0.4418	12493.20	14313.90	0.873 ¹ ✓
T9	53.1667 - 50	3/4	4.72	4.33	276.9	0.4418	11564.60	14313.90	0.808 ¹ ✓
T10	50 - 46.8334	3/4	4.72	4.33	276.9	0.4418	11831.00	14313.90	0.827 ¹ ✓
T11	46.8334 - 43.6667	3/4	4.72	4.33	276.9	0.4418	12010.20	14313.90	0.839 ¹ ✓
T12	43.6667 - 40	3/4	4.72	4.33	276.9	0.4418	12852.70	14313.90	0.898 ¹ ✓
T13	40 - 20	L2x2x3/16	7.60	3.63	72.9	0.4308	3001.40	18739.00	0.160 ¹ ✓
T14	20 - 0	L2 1/2x2 1/2x3/16	9.71	4.64	73.4	0.5710	1644.63	24839.90	0.066 ¹ ✓

¹ P_u / φP_n controls

Secondary Horizontal Design Data (Tension)

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio $\frac{P_u}{\phi P_n}$
T9	53.1667 - 50	2L2 1/2x2 1/2x5/16x3/8	3.50	3.21	50.6	2.9300	72.59	94932.00	0.001 ¹ ✓
T10	50 - 46.8334	2L 'a' > 18.5544 in - 170 2L2 1/2x2 1/2x5/16x3/8	3.50	3.21	50.6	2.9300	177.62	94932.00	0.002 ¹ ✓
T11	46.8334 - 43.6667	2L 'a' > 18.5544 in - 185 2L2 1/2x2 1/2x5/16x3/8	3.50	3.21	50.6	2.9300	292.51	94932.00	0.003 ¹ ✓
T12	43.6667 - 40	2L 'a' > 18.5544 in - 200 2L2 1/2x2 1/2x5/16x3/8	3.50	3.21	50.6	2.9300	309.37	94932.00	0.003 ¹ ✓
		2L 'a' > 18.5544 in - 218							✓

¹ P_u / φP_n controls

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	φP _{allow} lb	% Capacity	Pass Fail
T1	100 - 80	Leg	P2.5x.276	1	-31983.50	88826.50	36.0	Pass
		Diagonal	5/8	15	7797.94	9940.20	78.4	Pass
		Horizontal	L1 1/2x1 1/2x3/16	53	-5992.93	6697.95	89.5	Pass
		Top Girt	L1 1/2x1 1/2x3/16	5	-3119.49	6697.95	46.6	Pass
		Bottom Girt	L1 1/2x1 1/2x3/16	8	-4596.48	6697.95	68.6	Pass
T2	80 - 76	Leg	P2.5x.276 GR	61	-41373.10	93595.70	44.2	Pass

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	23 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker


Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
T3	76 - 73	Diagonal	5/8	72	8645.54	9940.20	87.0	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	65	-4382.27	23219.70	18.9	Pass
		Leg	P2.5x.276 GR	73	-49159.60	93595.70	52.5	Pass
T4	73 - 70	Diagonal	5/8	84	7648.01	9940.20	76.9	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	77	-8552.41	23219.70	36.8	Pass
		Leg	P2.5x.276 GR	85	-56676.60	93595.70	60.6	Pass
T5	70 - 67	Diagonal	5/8	96	8085.82	9940.20	81.3	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	89	-8196.18	23219.70	35.3	Pass
		Leg	P2.5x.276 GR	97	-64252.30	93595.70	68.6	Pass
T6	67 - 64	Diagonal	5/8	108	7768.93	9940.20	78.2	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	101	-8227.96	23219.70	35.4	Pass
		Leg	P2.5x.276 GR	109	-79929.30	93595.70	85.4	Pass
T7	64 - 60	Diagonal	1 1/4	117	15975.60	39760.80	40.2	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	113	-15207.50	23219.70	65.5	Pass
		Leg	P2.5x.276 GR	121	-90404.00	93595.70	96.6	Pass
T8	60 - 53.1667	Diagonal	1 1/4	134	18330.60	39760.80	46.1	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	125	-22847.60	23219.70	98.4	Pass
		Bottom Girt	2L1 1/2x1 1/2x3/16x3/8	128	-14122.30	23219.70	60.8	Pass
T9	53.1667 - 50	Leg	P3x.3 GR	136	-108935.00	153470.00	71.0	Pass
		Diagonal	3/4	155	12493.20	14313.90	87.3	Pass
		Horizontal	2L1 1/2x1 1/2x3/16x3/8	149	-12810.00	23505.80	54.5	Pass
T10	50 - 46.8334	Top Girt	2L1 1/2x1 1/2x3/16x3/8	141	-5133.18	23505.80	21.8	Pass
		Leg	P3x.3 GR	157	-119589.00	162618.00	73.5	Pass
		Diagonal	3/4	167	11564.60	14313.90	80.8	Pass
T11	46.8334 - 43.6667	Secondary Horizontal	2L2 1/2x2 1/2x5/16x3/8	170	-1718.66	82879.60	2.1	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	161	-11565.70	23505.80	49.2	Pass
		Leg	P3x.3 GR	172	-130626.00	162618.00	80.3	Pass
T12	43.6667 - 40	Diagonal	3/4	182	11831.00	14313.90	82.7	Pass
		Secondary Horizontal	2L2 1/2x2 1/2x5/16x3/8	185	-2367.78	82879.60	2.9	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	176	-10933.70	23505.80	46.5	Pass
T13	40 - 20	Leg	P3x.3 GR w/ .75 TR	187	-141856.00	162618.00	87.2	Pass
		Diagonal	3/4	197	12010.20	14313.90	83.9	Pass
		Secondary Horizontal	2L2 1/2x2 1/2x5/16x3/8	200	-2468.66	82879.60	3.0	Pass
T14	20 - 0	Top Girt	2L1 1/2x1 1/2x3/16x3/8	191	-11144.60	23505.80	47.4	Pass
		Leg	P3x.3 GR w/ .75 TR	202	-153963.00	162618.00	94.7	Pass
		Diagonal	3/4	215	12852.70	14313.90	89.8	Pass
T13	40 - 20	Secondary Horizontal	2L2 1/2x2 1/2x5/16x3/8	218	-1845.98	82879.60	2.2	Pass
		Top Girt	2L1 1/2x1 1/2x3/16x3/8	206	-12063.20	23505.80	51.3	Pass
		Bottom Girt	2L1 1/2x1 1/2x3/16x3/8	209	-5821.61	23505.80	24.8	Pass
T14	20 - 0	Leg	P5x.375 GR	220	-154086.00	231008.00	66.7	Pass
		Diagonal	L2x2x3/16	236	-3491.24	11837.70	29.5	Pass
		Leg	P5x.375 GR	241	-159113.00	231008.00	68.9	Pass
		Diagonal	L2 1/2x2 1/2x3/16	248	-1875.85	14675.40	12.8	Pass
						43.9 (b)		
						68.9		Pass
						74.6 (b)		
						12.8		Pass
						21.0 (b)		
						Summary		
						Leg (T7)	96.6	Pass
						Diagonal (T12)	89.8	Pass
						Horizontal (T1)	89.5	Pass
						Secondary Horizontal (T11)	3.0	Pass
						Top Girt (T7)	98.4	Pass
						Bottom Girt (T1)	68.6	Pass
						Bolt Checks	74.6	Pass

tnxTower Infinigy Engineering 2255 Sewell Mill Road, Suite 130 Marietta, GA 30062 Phone: (678) 444-4463 FAX: (678)444-4472	Job	333-315	Page	24 of 24
	Project	CT43XC836 - Danbury-W. CT. University	Date	15:17:04 09/24/14
	Client	Sprint	Designed by	MBecker

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
RATING =							98.4	Pass

Program Version 6.1.3.1 - 7/25/2013 File:N:/Sprint/2.5/Sprint Direct/Southern CT/CT43XC836/Structural/JOEJ Files/CT43XC836.eri

Date:	9/24/2014
Site Name:	Danbury-W C.T. University
Client:	Sprint
Infinigy Job #:	333-315
Analysis/Design:	Analysis
Column Shape:	Circle
Footing Shape:	Square
Tower Type:	Self Support



(d) mat or raft or floating foundation

Infinigy Engineering PLLC
 Mat Calculations
 ACI 318-11

Loading Data		
TIA Code Revision:	ANSI/TIA-222-G	
Uplift/Leg:	145.9	kips
Compression/Leg:	158.8	kips
Total Axial:	16.286	kips
Total Shear:	14.931	kips
Overturning Moment:	995.9	k-ft
Vertical Tower Eccentricity:	0	ft
Tower Face Width:	7.5	ft
Diagonal Shear Width:	14.14	ft
Diagonal Shear Arm:	7.14	ft

Soil Data		
Soil Type:	Sand	
Water Table Depth:	10	ft
Soil Dry Unit Weight:	110	pcf
∅ Angle:	30	deg
Cohesion:	0	psf
Ultimate Skin Friction:	500	psf
Friction Coefficient:	0.35	
Ultimate Bearing Pressure:	15000	psf

Column Data		
Concrete Strength:	4000	psi
Column Diameter:	2	ft
Column Total Length:	4.25	ft
Column Height above ground:	0.25	ft
Vertical Rebar Strength:	60000	psi
Vertical Rebar Size:	#8	(#10) max.
Vertical Rebar Quantity:	8	(4) min.
Tie Rebar Strength:	60000	psi
Tie Rebar Size:	#4	(#3) max.
Tie Rebar Spacing:	8	in
Rebar Clear Distance:	3	in

Footing Data		
Concrete Strength:	4000	psi
Footing Length:	14.5	ft
Footing Width:	14.5	ft
Footing Thickness:	3	ft
Horizontal Rebar Strength:	60000	psi
Horizontal Rebar Size:	#8	
Horizontal Rebar Quantity:	15	
Rebar Clear Distance:	3	in
Dowel Strength:		psi
Dowel Size:		(#11) max.
Dowel Development Length:		in
Dowel Quantity:		

Concrete Strength Check		
Footing One-Way Shear Ratio:	8.77	%
Footing Two-Way Shear Ratio:	13.01	%
Footing Moment Ratio:	12.8	%
Column Tension Ratio:	42.75	%
Column Shear Strength Ratio:	5.08	%
Column Moment Ratio:	18.59	%
Column Tension Interaction Equation:	61.34	%

Soil Stability Check		
∅s Bearing:	0.75	
∅s Uplift:	0.75	
Uplift Ratio:	69.87	%
Bearing Ratio:	59.06	%
Sliding Ratio:	20.48	%
Toe Pressure Ratio:	0.07	%
Overturning Ratio:	98.92	%

October 7, 2014

Gary Wood
Construction Project Manager III
Southern Connecticut
9 Barnes Industrial Road South
Wallingford, CT 06492

RE: Sprint 2.5 Project Antenna and RRH Support Evaluation
Sprint Site Number: CT43XC836
Sprint Site Name: DANBURY-W. CT UNIVERSITY
Site Address: 303 Boxwood Lane, Danbury, CT 06810
Jurisdiction: Fairfield County

Dear Mr. Wood

Per your request, Infinigy Engineering has reviewed the adequacy of the antenna and RRH supports at the above referenced site for the Sprint 2.5 Project. The purpose of this review was to determine if the existing and/or proposed mounts to be used are in conformance with the governing International Building Code (2003) and the applicable industry standard TIA-222-G 2005 (Structural Standard for Antenna Supporting Structures and Antennas).

Based on a review of the information from the Tower Analysis Report (dated 09/24/14) provided by Infinigy Engineering (Project Number 333-315) and Infinigy Engineering Construction Drawings (dated 05/13/14), we have concluded that **the antenna and RRH supports are adequate** to support the Sprint 2.5 equipment to be deployed at this site.

This certification assumes that all structural members are in good condition and have not been altered from the manufacturer's original design. Prior to installation of any new antennas and/or RRHs, the contractor shall inspect the condition of all relevant members and connections. The contractor shall be responsible for the means and methods of construction.

Should there be any questions, please do not hesitate to contact us.

Sincerely,

Joseph R. Johnston, P.E.
Department Manager - Structural
Connecticut PE License Number: 29460

