

STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051 Phone: (860) 827-2935 Fax: (860) 827-2950 E-Mail: siting.council@ct.gov www.ct.gov/csc

VIA ELECTRONIC MAIL

September 4, 2019

Thomas J. Regan, Esq. Brown Rudnick, LLP 185 Asylum Street Hartford, CT 06103

RE:

EM-SPRINT-034-190820 – Sprint Corporation notice of intent to modify an existing telecommunications facility located at 24 Hospital Avenue, Danbury, Connecticut.

Dear Attorney Regan:

The Connecticut Siting Council (Council) is in receipt of your correspondence of September 3, 2019 submitted in response to the Council's August 27, 2019 notification of an incomplete request for exempt modification with regard to the above-referenced matter.

The submission renders the request for exempt modification complete and the Council will process the request in accordance with the Federal Communications Commission 60-day timeframe.

Thank you for your attention and cooperation.

Sincerely,

Melanie A. Bachman Executive Director

MAB/IN/emr

Robidoux, Evan

From:

Mercier, Carlene M. < CMercier@brownrudnick.com>

Sent:

Tuesday, September 03, 2019 1:28 PM

To:

CSC-DL Siting Council

Cc:

Regan, Thomas J.; Bachman, Melanie

Subject:

EM-SPRINT-034-190820 / Sprint Exempt Modification at Danbury Hospital -

Supplemental Filing

Attachments:

Sprint - Danbury Hospital - Completeness Response.PDF

Good Afternoon,

Attached please find Sprint's Supplemental Filing related to its Notice of Exempt Modification (EM-SPRINT-034-190820) at Danbury Hospital. A hard copy has been sent via overnight mail to the Siting Council as well as the cc's.

Please let me know if you have any questions.

Best Regards, Carlene

brownrudnick

Carlene M. Mercier

Paralegal

Brown Rudnick LLP City Place 1 185 Asylum Street Hartford, CT 06103 T: 860.509.6538 F: 860.509.6638 cmercier@brownrudnick.com www.brownrudnick.com

Please consider the environment before printing this e-mail

The information contained in this electronic message may be legally privileged and confidential under applicable law, and is intended only for the use of the individual or entity named above. If the recipient of this message is not the above-named intended recipient, you are hereby notified that any dissemination, copy or disclosure of this communication is strictly prohibited. If you have received this communication in error, please notify Brown Rudnick LLP, (617) 856-8200 (if dialing from outside the US, 001-(617)-856-8200) and purge the communication immediately without making any copy or distribution.

To the extent Brown Rudnick is a "data controller" of the "personal data" (as each term is defined in the European General Data Protection Regulation) you have provided to us in this and other communications between us, please see our privacy statement and summary <u>here</u> which sets out details of the data controller, the personal data we have collected, the purposes for which we use it (including any legitimate interests on which we rely), the persons to whom we may transfer the data and how we intend to transfer it outside the European Economic Area.

brownrudnick

THOMAS J. REGAN direct dial: (860) 509-6522 tregan@brownrudnick.com

September 3, 2019

VIA OVERNIGHT COURIER & E-MAIL (siting.council@ct.gov)

Melanie A. Bachman, Esq. Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

RE: EM-SPRINT-034-190820

Sprint's Notice of Exempt Modification / Supplemental Filing 24 Hospital Avenue, Danbury, CT 06810 41° 24' 17.9" N, 73° 26' 45.21" W

Dear Executive Director Bachman:

In response to the Connecticut Siting Council's August 27, 2019 request for additional information, Sprint Corporation ("Sprint") hereby submits the following two additional exhibits:

Exhibit F: Revised Structural Analysis Report dated August 30, 2019 confirming the host building's ability to support Sprint's proposed modifications; and

Exhibit G: Siting Council Decision – Docket 79 detailing the conditions of the original facility approval which include the requirements that the Facility "shall be constructed in accordance with all applicable federal, state and municipal laws and regulations" and "shall comply with any future radio frequency (RF) standards promulgated by state or federal regulatory agencies." Sprint's proposed modifications will comply with both of those requirements. All of the remaining conditions in the approval are specific to the certificate holder.

A copy of this Supplemental Filing (with exhibits) is being sent today via UPS to: Mark D. Boughton (Mayor for the City of Danbury), Sharon B. Calitro (Director of Planning and Zoning for the City of Danbury) and Charles Geyer (Network Director of Engineering, Plant Operations and Biomedical Engineering at Danbury Hospital [property owners] and signatory for Danbury



Hospital on the Letter of Authorization). Included as **Exhibit H** are the UPS verifications that the aforementioned individuals were sent a copy of this Supplemental Filing with exhibits.

Please let me know if you have any questions or need anything further.

Sincerely,

BROWN RUDNICK LLP

Enclosures

cc via UPS:

Mayor Mark D. Boughton City of Danbury 155 Deer Hill Avenue Danbury, CT 06810

Director Sharon B. Calitro Planning & Zoning City of Danbury 155 Deer Hill Avenue Danbury, CT 06810

Charles Geyer, Network Director of Engineering Danbury Hospital 24 Hospital Avenue Danbury, CT 06810

63486784

EXHIBIT F



Structural Analysis Report

August 30, 2019

Site Name	Danbury Hospital
Site Cascade	CT81XC007-CT03XC350
Client	JP Consulting
Proposed Carrier	Sprint
Infinigy Job Number	526-101
	24 Hospital Ave, Danbury, CT 06810
Site Location	41° 24' 17.90" N NAD83
	73° 26' 45.21" W NAD83
Mount Centerline	131.0, 155.0, 159.0 ft
Mount Classification	Pipe Mount and Pipe Standoff
Structural Usage	69.4%
Overall Result	Pass

Upon reviewing the results of this analysis, it is our opinion that the proposed structure meets the specified TIA code requirements. The pipe standoff, antenna pipe mount, anchors, and host building are therefore deemed adequate to support the existing and proposed loading as listed in this report.



Kevin Berger Jr.

Structural Analysis Report

August 30, 2019

Contents

Introduction	3
Supporting Documentation	3 _
Analysis Code Requirements	3
Conclusion	3
Existing and Reserved Loading	4
To Be Removed	4
Proposed Loading	5
Final Configuration Loading	5
Structure Usages	6
Mount Connection Reactions	6
Assumptions and Limitations	7
Calculations	Annended

Introduction

Infinigy Engineering has been requested to analyze a pipe standoff and antenna supporting structures. All supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The structure was analyzed using RISA 3D v. 17.0.2 software.

Supporting Documentation

Construction Drawings	Infinigy Engineering Job #526-101, dated March 25, 2019
Site Photos	Infinigy Engineering Job #526-101, dated November 26, 2018
Structural Analysis	Infinigy Engineering Job #195-036, dated June 17, 2015

Analysis Code Requirements

Wind Speed	93 mph (3-Second Gust, Vasd)/ 120 mph (3-Second Gust, Vult)
Wind Speed w/ ice	50 mph (3-Second Gust) w/ 0.75" ice
TIA Revision	ANSI/TIA-222-G
Adopted IBC	2015 IBC / 2018 Connecticut State Building Code
Structure Class	II
Exposure Category	С
Topographic Category	1
Calculated Crest Height	0 ft

Conclusion

Upon reviewing the results of this analysis, it is our opinion that the proposed structure meets the specified TIA code requirements. The pipe standoff, antenna pipe mount, anchors, and host building are therefore deemed adequate to support the existing and proposed loading as listed in this report.

If you have any questions, require additional information, or actual conditions differ from those as detailed in this report please contact me via the information below:

Kevin Berger Jr. | INFINIGY 1033 Watervliet Shaker Road, Albany, NY 12205 (518) 690-0790 | Structural@infinigy.com

Existing & Reserved Loading

Rad Center (ft)	Qty.	Appurtenance	Mount Type	Sector
\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	1	CCI HPA33R-CS4AA-K		
	1	Alcatel-Lucent 800 Mhz RRH		
159.0	2	Alcatel-Lucent 1900 Mhz RRH		
	1	Alcatel-Lucent 2500 Mhz RRH		
	4	Diplexers	Dina Mayort	A lanks
	1	CCI HPA33R-CS4AA-K	Pipe Mount	Alpha
Ì	1	Alcatel-Lucent 800 Mhz RRH		
131.0	2	Alcatel-Lucent 1900 Mhz RRH]	
	1	Alcatel-Lucent 2500 Mhz RRH		
	4	Diplexers	1	
	1	CCI HPA33R-CS4AA-K		
	1	Alcatel-Lucent 800 Mhz RRH		
155.0	2	Alcatel-Lucent 1900 Mhz RRH		
	1	Alcatel-Lucent 2500 Mhz RRH		
	4	Diplexers	Dina Mannet	Beta
	1	CCI HPA33R-CS4AA-K	Pipe Mount	
	1	Alcatel-Lucent 800 Mhz RRH		
131.0	2	Alcatel-Lucent 1900 Mhz RRH		
	1	Alcatel-Lucent 2500 Mhz RRH		
	4	Diplexers		
	2	CCI HPA33R-CS4AA-K		
	2	Alcatel-Lucent 800 Mhz RRH		
155.0	4	Alcatel-Lucent 1900 Mhz RRH	Pipe Mount	Gamma
	2	Alcatel-Lucent 2500 Mhz RRH		
	8	Diplexers		

To be Removed Loading

Rad Center (ft)	Qty.	Appurtenance	Mount Type	Sector
159.0	1	Alcatel-Lucent 2500 Mhz RRH		
139.0	4	Diplexers		A lmh o
131.0	1	Alcatel-Lucent 2500 Mhz RRH		Alpha
131.0 4		Diplexers		
155.0	1	Alcatel-Lucent 2500 Mhz RRH		
131.0 4		Diplexers		Beta
		Alcatel-Lucent 2500 Mhz RRH		Deta
		Diplexers		
155.0	2	Alcatel-Lucent 2500 Mhz RRH		Gamma
155.0	8	Diplexers		Gamma

Proposed Loading

Rad Center (ft)	Qty.	Appurtenance	Mount Type	Sector
159.0	1 _	NOKIA AAHC		A 11
131.0	1	NOKIA AAHC		Alpha
155.0	1	NOKIA AAHC		D-4-
131.0	1	NOKIA AAHC		Beta
155.0	2	NOKIA AAHC		Gamma

Final Configuration Loading

Rad Center (ft)	Qty.	Appurtenance	Mount Type	Sector
	1	CCI HPA33R-CS4AA-K		
159.0		NOKIA AAHC		
139.0	1	Alcatel-Lucent 800 Mhz RRH		
	2	Alcatel-Lucent 1900 Mhz RRH	Dina Mount	Almho
	1	CCI HPA33R-CS4AA-K	Pipe Mount	Alpha
131.0	1	NOKIA AAHC		
151.0	1	Alcatel-Lucent 800 Mhz RRH		
	2	Alcatel-Lucent 1900 Mhz RRH		
	1	CCI HPA33R-CS4AA-K	Pipe Mount	
155.0	1	NOKIA AAHC	Pipe Stand-off	
155.0	1	Alcatel-Lucent 800 Mhz RRH	Pipe Mount	
	2	Alcatel-Lucent 1900 Mhz RRH	ripe Mount	Beta
	1	CCI HPA33R-CS4AA-K		Beta
131.0	1	NOKIA AAHC	Ding Mount	
151.0	1	Alcatel-Lucent 800 Mhz RRH	Pipe Mount	
	2	Alcatel-Lucent 1900 Mhz RRH		
	2	CCI HPA33R-CS4AA-K	Pipe Mount	
155.0	2	NOKIA AAHC	Pipe Stand-off	Commo
155.0	2	Alcatel-Lucent 800 Mhz RRH	Dina Mount	Gamma
	4	Alcatel-Lucent 1900 Mhz RRH	Pipe Mount	

CT81XC007 Alpha/Beta Structure Usages

	Summary	
Mount Pipe	31.6%	Pass
Max Usage	31.6%	Pass

CT03XC350 Alpha/CT81XC007 Gamma Structure Usages

	Summary	
Mount Pipe	19.7%	Pass
X Bracing	65.8%	Pass
Support Pipe	60.0%	Pass
Horizontal Bracing	69.4%	Pass
Max Usage	69.4%	Pass

CT81XC007 Alpha/Beta Mount Connection Reactions

Reaction Data	Design Reactions	Analysis Reactions	Result
Max Tension (lbs)	12340.0	578.3	4.7%
Max Shear (lbs)	7770.0	839.7	10.8%
Unity Check	(948)	***	15.5%

^{*}Assumed (2) 1/2" A307 Anchors. Contractor to field to verify anchor diameters prior to proper installation.

- Anchor reactions are acceptable when compared to manufacturer's listed capacities.

CT03XC350 Alpha/CT81XC007 Gamma Mount Connection Reactions

Reaction Data	Design Reactions	Analysis Reactions	Result
Max Tension (lbs)	12340.0	5782.4	46.9%
Max Shear (lbs)	7770.0	3574.2	46.0%
Unity Check			92.6%

^{*}Assumed (2) 1/2" A307 Anchors. Contractor to field to verify anchor diameters prior to proper installation.

- Anchor reactions are acceptable when compared to manufacturer's listed capacities.

Structural Analysis Report


August 30, 2019

Assumptions and Limitations

Our structural calculations are completed assuming all information provided to Infinigy Engineering is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition of "like new" and all members, connections, anchors, and masonry to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report Infinigy Engineering should be notified immediately to complete a revised evaluation.


Our evaluation is completed using standard TIA, AISC, ACI, and ASCE methods and procedures. Our structural results are proprietary and should not be used by others as their own. Infinigy Engineering is not responsible for decisions made by others that are or are not based on our supplied assumptions and conclusions.

This report is an evaluation of the any rooftop mounted equipment and/or antenna supporting structures to be proposed or modified as shown in the referenced construction drawings. Applicable building element adequacy to support these structures is also evaluated when the applied forces increase significantly based on engineering judgment.



Envelope Only Solution

Infinigy Engineering, PLLC.		Final Configuration
KLB	CT81XC007 Alpha/Beta	Apr 12, 2019 at 4:27 PM
526-101		CT81XC007A-B.r3d



Site Name: CT03XC350/CT81XC007
Client: JP Consulting
Carrier: Sprint
Engineer: KLB
Date: 8/14/2019



INFINIGY WIND LOAD CALCULATOR 4.0.2

Site Information Inputs:

Adopted Building Code: 2015 IBC

Structure Load Standard: TIA-222-G

Antenna Load Standard: TIA-222-G

Structure Risk Category: II

Structure Type: Mount - Pipe

Number of Sectors: 6

Main Structure Shape: Round

Ro	oftop Input	5:
nofton Wind Speed-Up?	No	

Wind Loading Inputs:

72	will conding inputs	* · · · · · · · · · · · · · · · · · · ·
Design Wind Velocity:	93	mph (nominal 3-second gust)
Wind Centerline 1 (21):	131.0	ft
Side Face Angle (θ):	60	degrees
Exposure Category:	С	
Topographic Category:	1	

Wir	nd with No	lce
q _z (psf)	Gh	F _{ST} (psf)
28.18	1.00	33.81

Wind with Ice										
q _z (psf)	Gh	F _{st} (psf)								
8.15	1.00	21.48								

Ice Loading Inputs:

Is Ice Loading Needed?:	Yes	
Ice Wind Velocity:	50	mph (nominal 3-second gust)
Base Ice Thickness:	0.75	in

Appurtenances	Elevation (ft)	Total Quantity	Ка	Front Shape	Side Shape	q, (psf)	EPA (ft²)	Fz (lbs)	Fx (lbs)	Fz(60) (lbs)	Fx(30) (lbs)
CCI ANTENNAS HPA33R-CS4AA-K	131.0	2	1.00	Flat	Flat	28 18	7.23	203.83	105.65	130.20	179.29
CCI ANTENNAS HPA33R-CS4AA-K	155.0	2	1.00	Flat	Flat	29.19	7.23	211.18	109,46	134.89	185.75
CCI ANTENNAS HPA33R-CS4AA-K	159.0	2	1.00	Flat	Flat	29.35	7,23	212.31	110.05	135.62	186.75
NOKIA AAHC	131.0	1	1.00	Flat	Flat	28,18	4.21	118.68	58.41	73,48	103,62
NOKIA AAHC	131.0	1	1.00	Flat	Flat	28.18	4.21	118.68	58.41	73.48	103.62
NOKIA AAHC	155.0	2	1.00	Flat	Flat	29.19	4.21	122.96	60,52	76.13	107.35
NOKIA AAHC	159.0	2	1,00	Flat	Flat	29.35	4.21	123.62	60.85	76.54	107.93
ALCATEL LUCENT TME-800MHZ RRH	131.0	1	1.00	Flat	Flat	28.18	2.13	60.14	49.96	52.51	57.59
ALCATEL LUCENT TME-800MHZ RRH	131.0	1	1.00	Flat	Flat	28.18	2.13	60.14	49.96	52.51	57.59
ALCATEL LUCENT TME-800MHZ RRH	155.0	2	1,00	Flat	Flat	29.19	2.13	62.31	51.76	54-40	59.67
ALCATEL LUCENT TME-800MHZ RRH	159.0	2	1,00	Flat	Flat	29.35	2.13	62.64	52,04	54,69	59.99
ALCATEL LUCENT TME-1900MHZ RRH	131.0	1	1,00	Flat	Flat	28.18	2,49	70,21	91.82	86.41	75.61
ALCATEL LUCENT TME-1900MHZ RRH	131.0	1	1.00	Flat	Flat	28.18	2.49	70.21	91.82	86.41	75.61
ALCATEL LUCENT TME-1900MHZ RRH	131.0	2	1.00	Flat	Flat	28.18	2.49	70.21	91.82	86.41	75.61
ALCATEL LUCENT TME-1900MHZ RRH	155.0	6	1.00	Flat	Flat	29.19	2.49	72.74	95-13	89.53	78.34
ALCATEL LUCENT TME-1900MHZ RRH	159.0	2	1.00	Flat	Flat	29.35	2.49	73.13	95-64	90.01	78.76



Company Designer Job Number

Model Name

Infinigy Engineering, PLLC.

526-101

CT81XC007 Alpha/Beta

Apr 12, 2019 4:29 PM Checked By:_

Member Primary Data

	Label	1 Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	MP1	N1A	N1 -	- III. JURES VIII. S.		3.5" STD Pipe	Beam	None	A53 Gr.B	Typical
2	M2A	N3	N3A			RIGID	None	None	RIGID	Typical
3	M3	N4	N5			RIGID	None	None	RIGID	Typical

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[LB]
1	General		Till Control		
2	RIGID		2	6	0
3	Total General		2	6	0
4					
5	Hot Rolled Steel				
6	A53 Gr.B	PIPE 2.5	1	72	32.9
7	Total HR Steel		1	72	32.9

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed	Area(Me	Surface(P
1	Self Weight	DL		-1			5			,,
2	Wind Load AZI 000	WLZ					5		1	
3	Wind Load AZI 090	WLX					5		1	
4	Ice Weight	OL1					5	3		
5	Wind + Ice Load AZI	OL2					5		1	
6	Wind + Ice Load AZI	OL3					5		1	
7	Service Live 1	LL								
8	BLC 2 Transient Area	None						1		
9	BLC 3 Transient Area	None						3		
10	BLC 5 Transient Area	None						1		
11	BLC 6 Transient Area	None						3		

Load Combinations

	Description	Sol	PD.	SRBLC	Fact.	.BLC	Fact	BLC	Fact	BLCFac	BLC	Fact.	BLC	Fact.	BLC	Fact	BLC	Fact	BLC	Fact	BLC	Fact.
1		Yes			1.4	A										ALCO COLL						
2	1.2D + 1.6	Yes	Y	DL	1.2	WLZ	1.6															
3	1.2D + 1.6	Yes	Υ	DL	1.2	WLZ	1.386	W	.8													
4	1.2D + 1.6	Yes	Y	DL	1.2	WLZ	.8	W	1.386													
5	1.2D + 1.6	Yes	Y	DL	1.2			W	1.6													
6	1.2D + 1.6	-		DL	1.2	WLZ	8	W	1.386													
7	1.2D + 1.6	Yes	Y				-1.3		.8													
8	1.2D + 1.6	_					-1.6															
9	1.2D + 1.6	-		DL	1.2	WLZ	-1.3	W	8													
10	1.2D + 1.6	-		DL	1.2	WLZ			-1.3													
11	1.2D + 1.6	-	_	DL	1.2			W	-1.6													
12									-1.3													
13		-	-				1.386	W	8													
	0.9D + 1.6.,			DL		_	1.6															
-	0.9D + 1.6	_		DL			1.386															
	0.9D + 1.6	_		DL		WLZ			1.386													
	0.9D + 1.6		-	DL				W														
	+			DL					1.386													
	0.9D + 1.6	_		DL		_	-1.3		.8													
	0.9D + 1.6	-	_	DL		-	-1.6															
21	0.9D + 1.6	Yes	Y	DL	.9	WLZ	-1.3	W	8													



Company Designer Job Number Model Name

: Infinigy Engineering, PLLC, : KLB

526-101

CT81XC007 Alpha/Beta

Apr 12, 2019 4:29 PM Checked By:_

Load Combinations (Continued)

	Description Sol		BLC							Fact	BLC	Fact										
22	0.9D + 1.6 Yes	Y	DL	.9	WLZ	8	W	-1.3														
23	0.9D + 1.6 Yes	Y	DL	.9			W	-1.6														
24	0.9D + 1.6 Yes	Y	DL	.9	WLZ	.8	W	-1.3														
25	0.9D + 1.6 Yes	Υ	DL			1.386	W	8														
26	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1																
27	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1	OL2	1														
28	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1	OL2	.866	OL3	.5												
29	1.2D + 1.0 Yes	Y	DL	1.2	OL1					.866												
30	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1			OL3	1												
31	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1				.866												
	1.2D + 1.0 Yes		DL	1.2	OL1	1		866	OL3	.5												
33	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1	OL2	-1														
34	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1	OL2	866	OL3	5												
	1.2D + 1.0 Yes		DL	1.2	OL1	1	OL2	5	OL3	866												
36	1.2D + 1.0 Yes	Y	DL	1.2	OL1	1			OL3	-1												
37	1.2D + 1.0 Yes	Y	DL	1.2	OL1		OL2	.5	OL3	866												
	1.2D + 1.0 Yes			1.2				.866		5												
39	1.2D + 1.5 Yes	Y	DL	1.2	LL	1.5	WLZ	.104														
40	1.2D + 1.5 Yes	Y	DL	1.2	LL	1.5	WLZ	.09	W	.052												
41	1.2D + 1.5 Yes	Υ	DL	1.2	LL	1.5	WLZ	.052	W	.09												
42	1.2D + 1.5 Yes	Y				1.5				.104												
43	1.2D + 1.5 Yes	Y						052														
44	1.2D + 1.5 Yes	Υ	DL	1.2	LL	1.5	WLZ	09	W	.052												
45	1.2D + 1.5 Yes	Υ	DL	1.2	LL	1.5	WLZ	104														
46	1.2D + 1.5 Yes	Y	DL	1.2	LL	1.5	WLZ	09	W	052												
	1.2D + 1.5 Yes		DL	1.2	LL	1.5	WLZ	052	W	09												
	1.2D + 1.5 Yes			1.2					-	104												
	1.2D + 1.5 Yes							.052														
50	1.2D + 1.5 Yes	Y	DL	1.2	LL	1.5	WLZ	.09	W	052												

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	N3A	max	10.26	5	14.012	27	10.26	14	1.147	20	2.565	5	2.123	5
2		min	-10.26	11	3.903	20	-10.26	8	-4.202	27	-2.565	11	-2.123	11
3	N5	max	534.735	17	839.727	33	578.287	2	1063.788	20	133.684	17	1125.012	17
4		min	-534.735	23	245.838	14	-578.287	20	-1206.338	2	-133.684	23	-1125.012	23
5	Totals:	max	544.995	17	853.739	38	588.547	14						
6		min	-544.995	11	249.742	14	-588.547	8						

Envelope AISC 15th(360-16): LRFD Steel Code Checks

	Member	Shape	Code Check	Loc[in]	LC	Shear	Loc[in]	Dir LC phi*Pnc .	.phi*Pnt[phi*Mn yphi*Mn zCb Eqn
1	MP1	PIPE 2.5	.316	18	13	.037	18	20 37773.8	50715	3596.25 3596.25 1H1-1b






Envelope Only Solution

Infinigy Engineering, PLLC		Final Configuration
KLB	CT81XC007 Gamma/ CT03XC350 Alpha	Apr 12, 2019 at 4:17 PM
526-101		CT03XC350A-CT81XC007G.r3d







Member Code Checks Displayed (Enveloped) Envelope Only Solution

Infinigy Engineering, PLLC		Bending Check
KLB	CT81XC007 Gamma/ CT03XC350 Alpha	Apr 12, 2019 at 4:18 PM
526-101		CT03XC350A-CT81XC007G.r3d

Site Name: CT03XC350/CT81XC007
Client: JP Consulting
Carrier: Sprint
Engineer: KLB
Date: 8/14/2019



INFINIGY WIND LOAD CALCULATOR 4.0.2

Site Information Inputs:

Adopted Building Code:

Structure Load Standard:
Antenna Load Standard:

Structure Risk Category:

Structure Type:
Number of Sectors:

Main Structure Shape:

Round

2015 IBC

2114-222-G

III-222-G

Mount - Pipe

Mount - Pipe

Round

Rooftop Wind Speed-Up?: No

Wind Loading Inputs:

Design Wind Velocity:

93 mph (nominal 3-second gust)

Wind Centerline 1 (2₁):

155.0 ft

Side Face Angle (0):

Exposure Category:

C

Topographic Category:

1

Wie	nd with No	lce
q _z (psf)	Gh	F _{ST} (psf)
29.19	1.00	35.03

V	Vind with I	ce
q _z (psf)	Gh	F _{ST} (psf)
8.44	1.00	20.30

Ice Loading Inputs:

Is Ice Loading Needed?:

Ice Wind Velocity:

Base Ice Thickness:

0.75

Yes

mph (nominal 3-second gust)

								-			_
Appurtenances	Elevation (ft)	Total	Ka	Front	Side	q _z	EPA	Fz	Fx	Fz(60)	Fx(30)
		Quantity		Shape	Shape	(psf)	(ft ²)	(lbs)	(lbs)	(lbs)	(lbs)
CCI ANTENNAS HPA33R-CS4AA-K	131.0	2	1,00	Flat	Flat	28.18	7.23	203.83	105.65	130.20	179.29
CCI ANTENNAS HPA33R-CS4AA-K	155.0	1	1.00	Flat	Flat	29.19	7.23	211.18	109.46	134.89	185.75
CCI ANTENNAS HPA33R-CS4AA-K	155.0	1	1.00	Flat	Flat	29.19	7.23	211,18	109.46	134.89	185.75
CCI ANTENNAS HPA33R-CS4AA-K	159.0	2	1.00	Flat	Flat	29.35	7,23	212,31	110.05	135.62	186.75
NOKIA AAHC	155.0	1	1.00	Flat	Flat	29.19	4.21	122.96	60.52	76.13	107.35
NOKIA AAHC	155.0	1	1.00	Flat	Flat	29.19	4.21	122.96	60.52	76.13	107.35
NOKIA AAHC	131.0	2	1.00	Flat	Flat	28.18	4.21	118.68	58.41	73.48	103.62
NOKIA AAHC	159.0	2	1.00	Flat	Flat	29.35	4.21	123.62	60.85	76.54	107.93
ALCATEL LUCENT TME-800MHZ RRH	155.0	1	1.00	Flat	Flat	29.19	2.13	62.31	51.76	54.40	59.67
ALCATEL LUCENT TME-800MHZ RRH	155.0	1	1.00	Flat	Flat	29.19	2.13	62.31	51.76	54.40	59.67
ALCATEL LUCENT TME-800MHZ RRH	131.0	2	1.00	Flat	Flat	28.18	2-13	60-14	49.96	52.51	57.59
ALCATEL LUCENT TME-800MHZ RRH	159,0	2	1.00	Flat	Flat	29.35	2.13	62,64	52.04	54.69	59.99
ALCATEL LUCENT TME-1900MHZ RRH	155.0	1	1,00	Flat	Flat	29.19	2.49	72.74	95.13	89,53	78.34
ALCATEL LUCENT TME-1900MHZ RRH	155.0	1	1,00	Flat	Flat	29.19	2,49	72.74	95.13	89.53	78.34
ALCATEL LUCENT TME-1900MHZ RRH	155.0	1	1.00	Flat	Flat	29.19	2.49	72.74	95-13	89.53	78.34
ALCATEL LUCENT TME-1900MHZ RRH	155.0	1	1.00	Flat	Flat	29.19	2.49	72.74	95-13	89,53	78.34
ALCATEL LUCENT TME-1900MHZ RRH	131.0	4	1.00	Flat	Flat	28.18	2.49	70-21	91-82	86,41	75.61
ALCATEL LUCENT TME-1900MHZ RRH	159.0	2	1.00	Flat	Flat	29.35	2,49	73.13	95.64	90.01	78.76



Company Designer Job Number Model Name

Infinigy Engineering, PLLC KLB

526-101

CT81XC007 Gamma/ CT03XC350 Alpha

Apr 12, 2019 4:19 PM Checked By:_

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N5	N12			Horizontal 1	Beam	Pipe	A53 GR B	Typical
2	M2	N6	N13			Horizontal 1	Beam	Pipe	A53 GR B	Typical
3	M3	N1	N2			Pipe Mast	Beam	Pipe	A53 GR B	Typical
4	M5	N7	N8			Pipe Mount	Beam	Pipe	A53 GR B	Typical
5	M6	N14	N15			Pipe Mast	Beam	Pipe	A53 GR B	Typical
6	MP1	N23	N24			Pipe Mount	Beam	Pipe	A53 GR B	Typical
7	M10	N3	N19			RIGID	None	None	RIGID	Typical
8	M11	N4	N20			RIGID	None	None	RIGID	Typical
9	MP2	N35	N36			Pipe Mount	Beam	Pipe	A53 GR B	Typical
10	M16	N31	N33			RIGID	None	None	RIGID	Typical
11	M17	N32	N34			RIGID	None	None	RIGID	Typical
12	M18	N37	N14		180	L5x3x1/4	Beam	Single Angle	A36 Gr.36	Typical
13	M19	N38	N15		180	L5x3x1/4	Beam	Single Angle	A36 Gr.36	Typical
14	M20	N40	N39			Pipe Mast	Beam	Pipe	A53 GR B	Typical
15	M21	N37	N15			Angle Brace	Beam	Single Angle	A36 Gr.36	Typical
16	MP4	N46	N45			Pipe Mount	Beam	Pipe	A53 GR B	Typical
17	M23	N43	N41			Site Pro Stand	Beam	SquareTube	A53 GR B	Typical
18	M24	N44	N42			Site Pro Stand	Beam	SquareTube	A53 GR B	Typical
19	M25	N24A	N49			L4x4x4	Beam	Single Angle	A36 Gr.36	Typical
20	M26	N48	N50			L4x4x4	Beam	Single Angle	A36 Gr.36	Typical
21	M27	N23A	N51			L4x4x4	Beam	Single Angle	A36 Gr.36	Typical
22	M28	N47	N52			L4x4x4	Beam	Single Angle	A36 Gr.36	Typical
23	M29	N43	N73			Tieback	Beam	Single Angle	A36 Gr.36	Typical
24	M30	N85	N88			Mod Bracing	Beam	Single Angle	A36 Gr.36	Typical
25	M31	N87	N86			Mod Bracing	Beam	Single Angle	A36 Gr.36	Typical
26	M32	N91	N95			L4x4x4	Beam	Single Angle	A36 Gr.36	Typical
27	M33	N92	N96			L4x4x4	Beam	Single Angle	A36 Gr.36	Typical
28	M28A	N67	N11			RIGID	None	None	RIGID	Typical
29	M29A	N66	N68			RIGID	None	None	RIGID	Typical
30	MP3	N11B	N11A			Pipe Mount	Beam	Pipe	A53 GR B	Typical

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[LB]
1	General			2 26	2 12 9
2	RIGID		6	33.6	0
3	Total General		6	33.6	0
4					
5	Hot Rolled Steel				
6	A36 Gr.36	L1/2x1/2x1/8	1	71.8	6
7	A36 Gr.36	L3X3X3	1	36.5	11.3
8	A36 Gr.36	L4X4X4	8	833.4	456.1
9	A36 Gr.36	L5X3X4	2	96.7	53.2
10	A53 GR B	HSS3X3X3	2	44	23.6
11	A53 GR B	PIPE 2.0	5	341	98.6
12	A53 GR B	PIPE 2.5	2	309	141.1
13	A53 GR B	PIPE 4.0X	3	441	517.7
14	Total HR Steel		24	2173.3	1307.6

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed	Area(Me	Surface(P
1	Self Weight	DL		-1			14	1		
2	Wind Load AZI 000	WLZ					14		1	
3	Wind Load AZI 090	WLX					14		1	



Company Designer Job Number

: Infinigy Engineering, PLLC : KLB : 526-101

CT81XC007 Gamma/ CT03XC350 Alpha

Apr 12, 2019 4:19 PM Checked By:_

Basic Load Cases (Continued)

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed	Area(Me	Surface(P
4	Ice Weight	OL1					14	30		
5	Wind + Ice Load AZI	OL2					14		1	
6	Wind + Ice Load AZI	OL3					14		1	
7	BLC 2 Transient Area	None						24		
8	BLC 3 Transient Area	None						30		
9	BLC 5 Transient Area	None						24		
10	BLC 6 Transient Area	None						30		

Load Combinations

	a combinat	The second	9727037		0000	W/707 52	VANO AS	AND IN					90000		2-10-5							_
	Description Sol.		.BLC	Fact.	.BLC	Fact.	BLC	Fact.	BLC	Fact	BLC	Fact	BLC	Fact.	BLC	Fact	BLC	Fact	BLC	Fact	BLC	Fact.
1		Y		1.4																		
2	1.2D + 1.6 Yes		DL	1.2	WLZ	1.6																
3	1.2D + 1.6 Yes	Y	DL	1.2	WLZ	1.386	W	.8														
4	1.2D + 1.6 Yes							1.386														
5	1.2D + 1.6 Yes			1.2				1.6														
6	1.2D + 1.6 Yes	v				- 8		1.386														
7	1.2D + 1.6., Yes		-		-	-1.3	-															
8	1.2D + 1.6 Yes					-1.6		.0														
9	1.2D + 1.6 Yes					-1.3		0														_
	1.2D + 1.6 Yes							-1.3					-									
	1.2D + 1.6 Yes					0		-1.6		-		_	-				-					_
11	1.2D + 1.6 Yes		DL			-																
			DL					-1.3	-		-	_	_	_								
	1.2D + 1.6 Yes		DL			1.386	VV	8														
	0.9D + 1.6 Yes		DL			1.6			-													
	0.9D + 1.6 Yes		DL			1.386																
	0.9D + 1.6 Yes		DL		WLZ			1.386														
	0.9D + 1.6 Yes		DL	.9				1.6														
	0.9D + 1.6 Yes		DL					1.386														
	0.9D + 1.6 Yes		DL			-1.3		.8														
	0.9D + 1.6 Yes		DL	.9	WLZ	-1.6																
21	0.9D + 1.6 Yes	Y	DL	.9	WLZ	-1.3	W	8														
22	0.9D + 1.6 Yes	Y	DL					-1.3	,	1												
	0.9D + 1.6 Yes		DL	.9				-1.6														
	0.9D + 1.6 Yes		DL		WLZ			-1.3														
	0.9D + 1.6 Yes		DL			1.386																
	1.2D + 1.0 Yes		DL	1.2				.0									-					
	1.2D + 1.0 Yes		_	1.2			OL2	4			-											
	1.2D + 1.0 Yes			1.2				.866	OI 3	E .				_								
	1.2D + 1.0 Yes		-		_		OL2			1	-	_	-		-		-				-	
	1.2D + 1.0 Yes			1.2	_		OLZ			.866 1		-			-		-					
				1.2			01.0				-	_	-		-		-					
	1.2D + 1.0 Yes			1.2						.866	- 6				-							
	1.2D + 1.0 Yes			1.2				866	UL3	.5			_									
	1.2D + 1.0 Yes			1.2			OL2															
	1.2D + 1.0 Yes		_	1.2	_			866														
	1.2D + 1.0 Yes			1.2		1	OL2			866												
	1.2D + 1.0 Yes			1.2		1				-1												
	1.2D + 1.0 Yes			1.2						866												
	1.2D + 1.0 Yes		DL	1.2	OL1	1	OL2	.866	OL3	5												
39	1.2D + 1.5 Yes	Υ		1.2				.104		-200												
	1.2D + 1.5 Yes							.09		.052												
	1.2D + 1.5 Yes			1.2				.052														
	1.2D + 1.5 Yes			1.2		1.5				.104												
	1.2D + 1.5 Yes			1.2			WI 7	052											_			-
	1.2D + 1.5 Yes							09														
	1.2D + 1.5 Yes							104		.UUZ			\rightarrow									
45	1.20 1.3.108	I	UL	1.4		1.5	AALC	104														



Company Designer Job Number Model Name

: Infinigy Engineering, PLLC : KLB

526-101

CT81XC007 Gamma/ CT03XC350 Alpha

Apr 12, 2019 4:19 PM Checked By:_

Load Combinations (Continued)

	Description SolPD	SRBLC Factl	BLC FactBLC	CFactBLC	FactBLC Fact.	.BLC FactBLC F	actBLC Fact.	BLC Fact BLC Fact
46	1.2D + 1.5 Yes Y		LL 1.5 WL					
47	1.2D + 1.5 Yes Y	DL 1.2	LL 1.5 WL	Z052 W	09			
48	1.2D + 1.5 Yes Y		LL 1.5					
49	1.2D + 1.5Yes Y	DL 1.2	LL 1.5 WLZ	Z.052 W	09			
50	1.2D + 1.5Yes Y	DL 1.2	LL 1.5 WL	2 .09 W	052			

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [[b-ft]	LC
1	N49	max	630.25	24	258.932	20	Ō	50	Ò	50	Ó	50	Ö	50
2		min	-783.431	6	-749.26	27	0	1	.0	1	0	1	0	1
3	N50	max	1329.8	11	221.436	17	0	50	0	50	0	50	0	50
4		min	-859.445	17	-2074.86	36	0	1	0	1	0	1	0	1
5	N51	max	113.438	5	30.283	24	0	50	.0	50	0	50	0	50
6		min	-62.537	23	-47.921	6	0	1	0	1	0	1	0	1
7	N52	max	47.616	16	47.422	27	0	50	0	50	0	50	0	50
8		min	-79.807	10	6.064	19	0	1	0	1	0	1	0	1
9	N53	max	79.797	25	740.889	31	255.144	28	0	50	0	50	0	50
10		min	-454.694	32	-77.662	24	-114.543	21	0	1	0	1	0	1
11	N54	max	201.402	31	199.782	33	129.732	2	0	50	0	50	0	50
12		min	-41.136	24	32.306	25	-88.41	20	0	1	0	1	0	1
13	N57	max	1349.528	6	1502.11	2	4437.281	2	0	50	0	50	0	50
14		min	-1059.626	24	-659.549	20	-4277.661	20	0	1	0	1	0	1
15	N58	max	1354.274	17	3574.17	37	5782.383	2	0	50	0	50	0	50
16		min	-2050.319	11	-224.819	18	-5714.44	20	0	1	0	1	0	1
17	N93	max	223.972	15	810.221	32	2913.69	20	0	50	0	50	0	50
18		min	-330.068	9	-199.079	25	-3235.559	2	0	1	0	1	0	1
19	N94	max	409.585	4	1201.562	34	4115.353	20	0	50	0	50	0	50
20		min	-282.227	22	-448.69	15	-4267.492	2	0	1	0	1	0	1
21	N95	max	77.694	34	16.987	25	0	50	0	50	0	50	0	50
22		min	-2.209	16	-198.454	31	0	1	0	1	0	1	0	1
23	N96	max	107.812	10	120.796	15	0	50	0	50	0	50	0	50
24		min	-107.376	16	-334.245	34	0	1	0	1	0	1	0	1
25	N97	max	2554.66	5	2026.77	31	917.419	2	0	50	0	50	0	50
26		min	-2395.645	23	263.574	24	-852.163	20	0	1	0	1	0	1
27	Totals:	max	3943.231	5	5965.359	33	3991.986	14						
28		min	-3943.226	23	1691.152	14	-3991.99	8						

Envelope AISC 15th(360-16): LRFD Steel Code Checks

	Member	Shape	Code Check	Loc[in]	LC	Shear .	Loc[in]	Dir	LC	phi*Pnc	phi*Pnt [phi*Mn y	.phi*Mn zCl	e Egn
1	M26	L4X4X4	.694	0	27	.108	30			48730.6			6714.886 2.	
2	M31	L4X4X4	.658	106	3	.022	106	Z	2	5864.933	62532	3137.597	4118.705 1.	H2-1
3	M30	L4X4X4	.617	106	13	.021	106	z	2	5864.933	62532	3137.597	4145.077 1.	H2-1
4	M20	PIPE 4.0X	.600	82.8	2	.144	80.8		2	54393.7	130410	14516.25	14516.25 2.	H1-1b
5	M25	L4X4X4	.527	0	2	.041	30	z	6	48730.6	62532	3137.597	6714.886 2.	H2-1
6	M3	PIPE 4.0X	.468	82.8	2	.148	80.8		8	54393.7	130410	14516.25	14516.25 1.	H1-1b
7	M33	L4X4X4	.461	0	9	.042	29.6	У	34	43429.7	62532	3137.597	6593.561 1.	- H2-1
8	M19	L5X3X4	.364	0	27	.018	0	V	27	41950.4	62856	1574.351	5528.512 1.	H2-1
9	M21	L1/2x1/2x1/8	.306	71.7	32	.010	0	z	6	615.735	9618.75	105.339	279.779 2.	H2-1
10	M32	L4X4X4	.306	0	7	.029	29.6	V	32	43429.7	62532	3137.597	6714.886 2.	H2-1
11	M18	L5X3X4	.281	0	4	.023	0	z	4	41950.4	62856	1938.892	6808.638 1	H2-1
12	M2	PIPE 2.5	.271	24.1	28	.173	24.1		2	13723.0	50715	3596.25	3596.25 3	H1-1b
13	M27	L4X4X4	.215	0	30	.029	29.25	٧	31	24703.2	62532	3137.597	5769.819 1	- H2-1
14	MP4	PIPE 2.0	.197	57.75	28	.076	57.75	A	4	20866.7	32130	1871.625	1871.625 1	H1-1b
15	MP2	PIPE 2.0	.170	12	27	.048	64.5		30	20866.7	32130		1871.625 1.8	



Company Designer Job Number Model Name

: Infinigy Engineering, PLLC : KLB

526-101

CT81XC007 Gamma/ CT03XC350 Alpha

Apr 12, 2019 4:19 PM Checked By:_

Envelope AISC 15th(360-16): LRFD Steel Code Checks (Continued)

	Member	Shape	Code Check	Loc[in]	LC	Shear	.Loc[in]	Dir	LC	phi*Pnc	phi*Pnt (.phi*Mn v	phi*Mn zC	b Ean
16	MP1	PIPE 2.0	.142	64.5	31	.033	12			20866.7			1871.625 1	
17	M28	L4X4X4	.135	30.3	33	.007	0	z	34	24703.2	62532	3137.597	5209.715 1	H2-1
18	M1	PIPE 2.5	.127	24.1	3	.071	24.1		8	13723.0	50715	3596.25	3596.25 1	H1-1b
19	M24	HSS3X3X3	.079	0	29	.048	22	z	10	58412.63			5171.25 1	
20	M23	HSS3X3X3	.079	0	29	.041	22	V	4	58412.63			5171.25 1	
21	M5	PIPE 2.0	.048	53	13	.016	53		3	25429.3			1871.625 1	
22	MP3	PIPE 2.0	.036	13.5	8	.022	54		3	20866.7			1871.625 1	
23	M29	L3X3X3	.020	18.23	29	.014	36.4	v	29	25906.2	35316	1320.097	2676.532 1	H2-1
24	M6	PIPE_4.0X	.009	28.7	12	.027	53		4	122170	130410	14516.25	14516.25 1	H1-1b

EXHIBIT G

DOCKET NO. 79

AN APPLICATION OF METRO MOBILE CTS OF FAIRFIELD COUNTY, INC., FOR A CERTIFICATE OF ENVIRONMENTAL COMPATIBILITY AND PUBLIC NEED FOR CELLULAR TELEPHONE ANTENNAS AND ASSOCIATED : EQUIPMENT IN THE CITY OF DANBURY, CONNECTICUT. : SEPTEMBER 10, 1987

COUNCIL

: CONNECTICUT SITING

DECISION AND ORDER

Pursuant to the foregoing opinion, the Connecticut Siting Council hereby directs that a Certificate of Environmental Compatibility and Public Need, as provided by Section 16-50k of the General Statutes of Connecticut (CGS), be issued to Metro Mobile CTS of Fairfield County, Inc., for the construction, operation, and maintenance of cellular mobile telephone antennas in the City of Danbury, Connecticut.

The facility shall be constructed, operated, and maintained substantially as specified in the Council's record on this matter, and subject to the following conditions.

- The facility shall be constructed in accordance with all applicable federal, state, and municipal laws and regulations.
- The Certificate holder shall notify the Federal Aviation Administration of its intention to mount antennas on the Danbury Hospital, and provide it the opportunity to comment prior to initiation of construction. A copy of the notification to the Federal Aviation Administration shall be sent to the City of Danbury's Airport Administrator.

- 3. The Certificate holder or its successor shall notify the Council if and when directional antennas or any equipment other than that listed in this application is added to this facility.
- 4. If this facility does not provide or permanently ceases to provide cellular service following completion of construction, this Decision and Order shall be void, and the antennas and all associated equipment in this application shall be dismantled and removed or reapplication for any new use shall be made to the Council before any such new use is made.
- 5. Unless otherwise approved by the Council, this Decision and Order shall be void if all construction authorized herein is not completed within three years of the issuance of this Decision and Order, 'or within three years of the completion of any appeal taken in this Decision.
- 6. The certificate holder shall comply with any future radio frequency (RF) standards promulgated by state or federal regulatory agencies. Upon the establishment of any new governmental RF standards, the facility granted in this Decision shall be brought into compliance with such standards.

Pursuant to CGS Section 16-50p, we hereby direct that a copy of this Decision and Order be served on each person listed below. A notice of the issuance shall be published in the Danbury News-Times.

The parties to the proceeding are:

Metro Mobile CTS of Fairfield County, Inc. 50 Rockland Road South Norwalk, CT 06854 Attn: Peter Kelley, Vice President

Howard L. Slater, Esq.
Jennifer Young Gaudet, Esq.
Byrne, Slater, Sandler,
Shulman & Rouse, P.C.
330 Main Street
PO Box 3216
Hartford, CT 06103

Fleischman and Walsh, P.C. 1725 N Street, N.W. Washington, DC 20036 Attn: Richard Rubin, Esq. Jonathan Cohen, Esq.

SNET Cellular, Inc. c/o Peter J. Tyrrell Senior Attorney 227 Church Street New Haven, CT 06506 (its representatives)

(applicant)

(intervenor)

0198E

CERTIFICATION

The undersigned members of the Connecticut Siting Council hereby certify that they have heard the case in Docket 79 or read the record thereof, and that we voted as follows:

Dated at New Britain, Connecticut the 10th day of September, 1987.

Council Members	Vote Cast
Gloria Dibble Pond Chairperson	Yes
Commissioner Peter Boucher Designee: Kathy A. Geppert	Yes
Commissioner Leslie Carothers Designee: Brian Emerick	Absent
Owen In Clark	Yes
Fred Dooy	Yes
Mortimer A. Gelston	Yes
times g. Horsfall	Yes
William H. Smith	Yes
Od C. Vary	Yes

Pacifico 220 and 230 College Timeline August 30, 2019

	230 College	220 College
Signing of lease	9/5/2019	9/5/2019
Initial Plans	10/1/2019	11/1/2019
Final Plans	10/15/2019	12/1/2019
Possession	11/1/2019	Tenant is in Possession
Work Completion	2/28/2020	4/15/2020
Rent Commence	3/1/2020	4/15/2020
Days of Free Rent	120 days	45 days
Days of Free Rent	11/1/2019 to 2/28/2020	3/01/2020 to 4/15/2020

EXHIBIT H

Shipment Receipt

Transaction Date: 03 Sep 2019

Tracking Number:

1Z77X79X0190365224

(1) ADDRESS INFORMATION

Ship To:

City of Danbury Mayor Mark D. Boughton 155 Deer Hill Avenue

DANBURY CT 06810

BROWN RUDNICK LLP THOMAS J. REGAN 185 Asylum Street

Ship From:

Hartford CT 06103 Telephone:860-509-6522 email:tregan@brownrudnick.co BROWN RUDNICK LLP THOMAS J. REGAN 185 Asylum Street Hartford CT 06103

Return Address:

Telephone:860-509-6522 email:tregan@brownrudnick.com

2 PACKAGE INFORMATION

Ì		WEIGHT	DIMENSIONS / PACKAGING	DECLARED VALUE	REFERENCE NUMBERS
	1,	Letter (Letter billable)	UPS Letter		Client Matter Code - 080563.3289 Employee ID - 0825

UPS SHIPPING SERVICE AND SHIPPING OPTIONS

UPS Next Day Air

Guaranteed By:

10:30 AM Wednesday, Sep 4, 2019

Shipping Fees Subtotal:

26.36 USD Additional Shipping Options

Transportation

24.64 USD Quantum View Notify E-mail Notifications:

No Charge

Fuel Surcharge

1.72 USD

1 cteltelbaum@brownrudnick.com: Exception, Delivery

(4) PAYMENT INFORMATION

Bill Shipping Charges to:

Shipper's Account 77X79X

26,36 USD Shipping Charges:

A discount has been applied for this shipment.

Negotiated Charges:

10.55 USD

Subtotal Shipping Charges:

10.55 USD

Total Charges:

10.55 USD

Note: This document is not an invoice. Your final invoice may vary from the displayed reference rates.

^{*} For delivery and guarantee information, see the UPS Service Guide ({0}). To speak to a customer service representative, call 1-800-PICK-UPS for domestic services an 1-800-782-7892 for international services.

Shipment Receipt

Transaction Date: 03 Sep 2019

Tracking Number:

1Z77X79X0191264831

(1) ADDRESS INFORMATION

Ship To:

City of Danbury Director Sharon B. Calitro 155 Deer Hill Avenue DANBURY CT 06810

Ship From:

BROWN RUDNICK LLP THOMAS J. REGAN 185 Asylum Street Hartford CT 06103 Telephone:860-509-6522 email:tregan@brownrudnick.co BROWN RUDNICK LLP THOMAS J, REGAN 185 Asvlum Street

Return Address:

Telephone:860-509-6522 email:tregan@brownrudnick.com

2 PACKAGE INFORMATION

	WEIGHT	DIMENSIONS / PACKAGING	DECLARED VALUE	REFERENCE NUMBERS
1.	Letter (Letter billable)	UPS Letter		Client Matter Code - 080563.3289 Employee ID - 0825

(3) UPS SHIPPING SERVICE AND SHIPPING OPTIONS

Service:

UPS Next Day Air

Guaranteed By:

10:30 AM Wednesday, Sep 4, 2019

Shipping Fees Subtotal:

26.36 USD Additional Shipping Options

Transportation

24.64 USD Quantum View Notify E-mail Notifications:

No Charge

Fuel Surcharge

1.72 USD

1 cteltelbaum@brownrudnick.com: Exception, Delivery

PAYMENT INFORMATION

Bill Shipping Charges to:

Shipping Charges:

Shipper's Account 77X79X

A discount has been applied for this shipment.

Total Charges:

10.55 USD

26.36 USD

Subtotal Shipping Charges:

10.55 USD

10.55 USD

Note: This document is not an invoice. Your final invoice may vary from the displayed reference rates.

^{*} For delivery and guarantee information, see the UPS Service Guide ((0)). To speak to a customer service representative, call 1-800-PICK-UPS for domestic services an 1-800-782-7892 for international services.

Shipment Receipt

Transaction Date: 03 Sep 2019

Tracking Number:

1Z77X79X0191501440

(1) ADDRESS INFORMATION

Ship To:

Danbury Hospital Charles Geyer, Dir. of Engineering 24 Hospital Avenue DANBURY CT 06810

Ship From: BROWN RUDNICK LLP THOMAS J. REGAN 185 Asylum Street Hartford CT 06103 Telephone:860-509-6522

email:tregan@brownrudnick.co

BROWN RUDNICK LLP THOMAS J. REGAN 185 Asylum Street

Return Address:

Telephone:860-509-6522 email:tregan@brownrudnick.com

2 PACKAGE INFORMATION

	WEIGHT	DIMENSIONS / PACKAGING	DECLARED VALUE	REFERENCE NUMBERS
1.	Letter (Letter billable)	UPS Letter		Client Matter Code - 080563.3289 Employee ID - 0825

(3) UPS SHIPPING SERVICE AND SHIPPING OPTIONS

UPS Next Day Air

Guaranteed By:

10:30 AM Wednesday, Sep 4, 2019

Shipping Fees Subtotal:

26.36 USD Additional Shipping Options

Transportation

24.64 USD Quantum View Notify E-mail Notifications:

No Charge

Fuel Surcharge

1.72 USD

1 cteltelbaum@brownrudnick.com; Exception, Delivery

PAYMENT INFORMATION

Bill Shipping Charges to:

Shipping Charges:

Shipper's Account 77X79X

A discount has been applied for this shipment.

Negotiated Charges:

10.55 USD

26.36 USD

Subtotal Shipping Charges:

Total Charges:

10.55 USD 10.55 USD

Note: This document is not an invoice. Your final invoice may vary from the displayed reference rates.

^{*} For delivery and guarantee information, see the UPS Service Guide ({0}). To speak to a customer service representative, call 1-800-PICK-UPS for domestic services an 1-800-782-7892 for international services.