

February 8, 2024

Via Electronic Mail

Melanie A. Bachman, Esq.
Executive Director/Staff Attorney
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: **Notice of Exempt Modification – Facility Modification
49 Brainerd Road, Niantic (Town of East Lyme), Connecticut**

Dear Attorney Bachman:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains an existing wireless telecommunications facility at the above-referenced property address (the “Property”). The facility consists of antennas on an existing tower and related equipment on the ground, near the base of the tower. The tower and Cellco’s shared use of the tower were approved by the Siting Council (“Council”) in March of 2011 (Docket No. 396). A copy of the Docket No. 396 Decision and Order is included in Attachment 1.

Cellco now intends to modify its facility by removing twelve (12) antennas and six (6) remote radio heads (“RRHs”) and installing nine (9) new antennas and six (6) new RRHs on Cellco’s existing antenna platform and mounting assemblies. A set of project plans showing Cellco’s proposed facility modifications and the specifications for Cellco’s new antenna and RRHs are included in Attachment 2.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to East Lyme’s Chief Elected Official and Land Use Officer. A copy of the letter is being sent to the owner of the Property.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

28793415-v1

Melanie A. Bachman, Esq.

February 8, 2024

Page 2

1. The proposed modifications will not result in an increase in the height of the existing tower. Cellco's new antennas and RRHs will be installed at the same height on the tower.
2. The proposed modifications will not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The installation of Cellco's new antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) safety standard. Included in Attachment 3 is a Calculated Radio Frequency Emissions Report demonstrating that the proposed modified facility will comply with the FCC safety standards. The modified facility will be capable of providing Cellco's 5G wireless service.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. According to the attached Structural Analysis Report ("SA") and Antenna Mount Analysis Report ("MA"), the existing tower, tower foundation and antenna mounts, with certain modifications, can support Cellco's proposed modifications. Copies of the SA and MA are included in Attachment 4.

A copy of the parcel map and Property owner information is included in Attachment 5. A Certificate of Mailing verifying that this filing was sent to municipal officials and the property owner is included in Attachment 6.

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kenneth C. Baldwin

Enclosures

Copy to:

Daniel Cunningham, First Selectman
Gary Goeschel, II, Director of Planning
Double R Ranch LLC, Property Owner
Aleksy Tyurin

ATTACHMENT 1

DOCKET NO. 396 – SBA Towers II, LLC application for a Certificate of Environmental Compatibility and Public Need for the construction, maintenance and management of a telecommunications facility located at 49 Brainerd Road, Niantic (East Lyme), Connecticut. }

Connecticut

Siting

Council

March 3, 2011

Decision and Order

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council (Council) finds that the effects associated with the construction, maintenance, and management of a telecommunications facility, including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not disproportionate, either alone or cumulatively with other effects, when compared to need, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application, and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by General Statutes § 16-50k, be issued to SBA Towers II, LLC, hereinafter referred to as the Certificate Holder, for a telecommunications facility at the SBA Hybrid Site (i.e. approximately 310 feet to the south of the proposed location) at 49 Brainerd Road, East Lyme, Connecticut.

Unless otherwise approved by the Council, the facility shall be constructed, managed, and maintained substantially as specified in the Council’s record in this matter, and subject to the following conditions:

1. The tower shall be constructed as a monopole, no taller than necessary to provide the proposed telecommunications services, sufficient to accommodate the antennas of New Cingular Wireless PCS, LLC (AT&T), Cellco Partnership d/b/a Verizon Wireless (Cellco), and other entities, both public and private, but such tower shall not exceed a height of 170 feet above ground level. All commercial wireless telecommunications antennas shall be attached to the tower via T-arms.
2. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plan shall be served on the Town of East Lyme for comment, and all parties and intervenors as listed in the service list, and submitted to and approved by the Council prior to the commencement of facility construction and shall include:
 - a) a final site plan(s) of site development to include specifications for the tower, tower foundation, antennas, equipment compound, radio equipment, access road, utility line, and landscaping; and
 - b) construction plans for site clearing, grading, landscaping, water drainage, and erosion and sedimentation controls consistent with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended.
3. Prior to the commencement of operation, the Certificate Holder shall provide the Council worst-case modeling of the electromagnetic radio frequency power density of all proposed entities’ antennas at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65, August 1997. The Certificate Holder shall ensure a recalculated report of the electromagnetic radio frequency power density be submitted to the Council if and when circumstances in operation cause a change in power density above the levels calculated and provided pursuant to this Decision and Order.

4. Upon the establishment of any new State or federal radio frequency standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.
5. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
6. The Certificate Holder shall provide reasonable space on the tower for no compensation for any Town of East Lyme public safety services (police, fire and medical services), provided such use can be accommodated and is compatible with the structural integrity of the tower.
7. Unless otherwise approved by the Council, if the facility authorized herein is not fully constructed with at least one fully operational wireless telecommunications carrier providing wireless service within eighteen months from the date of the mailing of the Council's Findings of Fact, Opinion, and Decision and Order (collectively called "Final Decision"), this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made. The time between the filing and resolution of any appeals of the Council's Final Decision shall not be counted in calculating this deadline. Authority to monitor and modify this schedule, as necessary, is delegated to the Executive Director. The Certificate Holder shall provide written notice to the Executive Director of any schedule changes as soon as is practicable.
8. Any request for extension of the time period referred to in Condition 7 shall be filed with the Council not later than 60 days prior to the expiration date of this Certificate and shall be served on all parties and intervenors, as listed in the service list, and the Town of East Lyme. Any proposed modifications to this Decision and Order shall likewise be so served.
9. If the facility ceases to provide wireless services for a period of one year, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made.
10. Any nonfunctioning antenna, and associated antenna mounting equipment, on this facility shall be removed within 60 days of the date the antenna ceased to function.
11. In accordance with Section 16-50j-77 of the Regulations of Connecticut State Agencies, the Certificate Holder shall provide the Council with written notice two weeks prior to the commencement of site construction activities. In addition, the Certificate Holder shall provide the Council with written notice of the completion of site construction, and the commencement of site operation.
12. The Certificate Holder shall remit timely payments associated with annual assessments and invoices submitted by the Council for expenses attributable to the facility under Conn. Gen. Stat. §16-50v.
13. This Certificate may be transferred in accordance with Conn. Gen. Stat. §16-50k(b), provided both the Certificate Holder/transferor and the transferee are current with payments to the Council for their respective annual assessments and invoices under Conn. Gen. Stat. §16-50v. In addition, both the Certificate Holder/transferor and the transferee shall provide the Council a written agreement as to the entity responsible for any quarterly assessment charges under Conn. Gen. Stat. §16-50v(b)(2) that may be associated with this facility.

14. The Certificate Holder shall maintain the facility and associated equipment, including but not limited to, the tower, tower foundation, antennas, equipment compound, radio equipment, access road, utility line and landscaping in a reasonable physical and operational condition that is consistent with this Decision and Order and a Development and Management Plan to be approved by the Council.
15. If the Certificate Holder is a wholly-owned subsidiary of a corporation or other entity and is sold/transferred to another corporation or other entity, the Council shall be notified of such sale and/or transfer and of any change in contact information for the individual or representative responsible for management and operations of the Certificate Holder within 30 days of the sale and/or transfer.

Pursuant to General Statutes § 16-50p, the Council hereby directs that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below, and notice of issuance shall be published in The Day.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of Connecticut State Agencies.

The parties and intervenors to this proceeding are:

Applicant

SBA Towers II LLC

Its Representative

Carrie L. Larson, Esq.
Pullman & Comley, LLC
90 State House Square
Hartford, CT 06103-3702

Intervenor

Cellco Partnership d/b/a Verizon Wireless

Its Representative

Kenneth C. Baldwin, Esq.
Robinson & Cole LLP
280 Trumbull Street
Hartford, CT 06103-3597

Intervenor

Russell L. Brown

Its Representative

Russell L. Brown
41 Brainerd Road
Niantic, CT 06357

Party

Town of East Lyme

Its Representative

Edward B. O'Connell, Esq.
Waller, Smith & Palmer, P.C.
52 Eugene O'Neill Drive
P.O. Box 88
New London, CT 06320

Intervenor

New Cingular Wireless PCS, LLC

Party

Friends of the Pattagansett Trust

Intervenor

Joseph Raia

Its Representative

Daniel M. Laub, Esq.
Christopher B. Fisher, Esq.
Cuddy & Feder LLP
445 Hamilton Avenue, 14th floor
White Plain, NY 10601

Its Representative

Keith R. Ainsworth, Esq.
Evans Feldman & Ainsworth, LLC
261 Bradley Street
P.O. Box 1694
New Haven, CT 06507-1694

Its Representative

Joseph Raia
97 West Main Street, Unit 9
Niantic, CT 06357

ATTACHMENT 2



20 ALEXANDER DRIVE, 2nd FLOOR
WALLINGFORD, CT 06492

ROCKY NECK CT

49 BRAINERD ROAD
NIANTIC, CT 06357
NEW LONDON COUNTY

**PROJECT TYPE: UPGRADE TO EXISTING WIRELESS
TELECOMMUNICATIONS INSTALLATION ON EXISTING 170'± MONOPOLE**

SUPPORTING DOCUMENTS

(HARD FREQUENCY (RF) DESIGN DATE: 06/16/22)
ANTENNA MOUNT STRUCTURAL ANALYSIS DATE: 10/11/22 (BY COLLIER ENGINEERING & DESIGN)
ANTENNA SUPPORT STRUCTURE (170'± MONOPOLE) STRUCTURAL ANALYSIS DATE: 01/11/24
(BY SBA COMMUNICATIONS CORPORATION)



By Stephen Roth at 5:14:49 AM, 1/31/2024

SITE INFORMATION

VERIZON LOCATION CODE: 490808
ROCKY NECK CT
CT 07945
EAST VME 1
245417 V1
500122067
206259
49 BRAINERD ROAD
CHAPPEL ENGINEERING ASSOCIATES, LLC
40 BRAINERD ROAD
NIANTIC, CT 06357
SBA TOWERS V, LLC
800 CONGRESS AVENUE
SUITE 200
PHONE: 501 224 9520
NEW LONDON, MA
(R4) RESIDENTIAL
MONOPOLE
172'
175'
187'
CENTER OF EXISTING MONOPOLE
W 75°10'24" E 172' 22017 (RAD 25)
CHAPPEL ENGINEERING ASSOCIATES, LLC
201 BOSTON POST ROAD WEST, SUITE 101
MIDDLEBOROUGH, MA 01752


VERIZON LOCATION CODE: 490808
170'±
187'
CENTER OF EXISTING MONOPOLE
W 75°10'24" E 172' 22017 (RAD 25)
CHAPPEL ENGINEERING ASSOCIATES, LLC
201 BOSTON POST ROAD WEST, SUITE 101
MIDDLEBOROUGH, MA 01752

GENERAL NOTES

- CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS AND CONDITIONS ON JOB SITE. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS ARE AS SHOWN ON PLANS. CONTRACTOR SHALL NOTIFY ARCHITECT/ENGINEER IMMEDIATELY IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. FAILURE TO NOTIFY THE ARCHITECT/ENGINEER PLACES THE RESPONSIBILITY ON THE CONTRACTOR TO CORRECT THE DISCREPANCIES AT THE CONTRACTOR'S EXPENSE.
- NEW CONSTRUCTION SHALL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES
 - BUILDING CODE: 2022 CONNECTICUT STATE BUILDING CODE
 - STRUCTURAL CODE: TWEA-22-4 STRUCTURAL STANDARDS FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS

AT LEAST 24 HOURS PRIOR TO
BEGINNING THE CONTRACTOR IS
REQUIRED TO CALLING SBAE AT 811.

VICINITY MAP



DRIVING DIRECTIONS

FROM WALLINGFORD, TAKE CT 61 EAST TOWARD NIANTIC. TURN RIGHT ONTO BRAINERD ROAD. TURN RIGHT ONTO THE CT 1 SOUTH RAMP TOWARD OLD SANDHOCK. MERGE ONTO CT 15 SOUTH. USE LEFT LANE TO MERGE ONTO 161 NORTH (US 1 NORTH) TOWARD NEW LONDON. PROCEED TO FOLLOW US 161 NORTH. TAKE EXIT 72 TOWARD ROCKY NECK STATE PARK. CONTINUE ONTO ROCKY NECK CONNECTOR. USE ANY LANE TO TURN LEFT ONTO CT 155 (EASTWEST MAIN STREET). TURN RIGHT ONTO ALPHARETTA BEACH. TURN RIGHT ONTO BRAINERD ROAD. SITE IS LOCATED ON THE LEFT HAND SIDE.

SHEET INDEX

DWG.	DESCRIPTION	REV.
T01	TITLE SHEET	
GN01	GENERAL NOTES	
A01	SITE PLAN	
A02	COMPOUND PLAN	
A03	TOWER ELEVATIONS	
A04	ANTENNA PLANS & SITE DETAILS	
RF01	RF DATA	
RF02	RF FLOORING DIAGRAM	
RR01	RF COLOR CODE SPECIFICATIONS	
E01	GROUNDING NOTES & DETAILS	
MM01	MOUNT MODIFICATION DRAWINGS I	
MM02	MOUNT MODIFICATION DRAWINGS II	
MM03	MOUNT MODIFICATION DRAWINGS III	

DO NOT SCALE DRAWINGS

ALL PLANS, EXISTING DIMENSIONS AND CONDITIONS AT THE PROPOSED PROJECT SITE SHALL BE VERIFIED IN THE FIELD DURING THE CONSTRUCTION PHASE. THE PROJECT OWNERS SHALL BE RESPONSIBLE FOR VERIFYING THE EXISTING DIMENSIONS AND CONDITIONS. THE CONTRACTOR SHALL PROCEED WITH THE PROPOSED WORK AFFECTED BY SUCH DISCREPANCIES IN THE EVENT OF LACK OF SUCI INDICATION. SUCH DISCREPANCIES SHALL BECOME THE RESPONSIBILITY OF THE PREVAILING CONTRACTOR RESPONSIBLE FOR CONSTRUCTION.

PROJECT DESCRIPTION

- THIS IS AN UNMANNED AND RESTRICTED ACCESS EQUIPMENT INSTALLATION AND WILL BE USED TO TRANSMIT AND RECEIVE RADIO SIGNAL FOR THE PURPOSE OF PROVIDING PUBLIC WIRELESS TELECOMMUNICATIONS SERVICES.
- THIS FACILITY DOES NOT NOR WILL IT CONSUME UNRECOVERABLE ENERGY.
- NO PORTABLE WATER SUPPLY IS OR WILL BE PROVIDED AT THIS LOCATION.
- NO PORTABLE TOILETS WILL BE PROVIDED AT THIS LOCATION.
- NO SOLID WASTE IS OR WILL BE GENERATED AT THIS LOCATION.

SCOPE OF WORK

- REMOVE:
- 1. 6 ANTENNAS
 - 2. 1 JUNCTION BOX (JV)
- INSTALL:
- 1. 1 ANTENNA MOUNT REINFORCEMENTS
 - 2. 3 SIDE-RY-SIDE ANTENNA MOUNTS
 - 3. 6 ANTENNAS
 - 4. 1 JUNCTION BOX (JV)
 - 5. 1 JUNCTION BOX (JV)



20 ALEXANDER DRIVE, 2ND FLOOR
WALLINGFORD, CT 06492
(800) 747-7438



SBA COMMUNICATIONS CORP
135 PLAINFIELD ROAD, SUITE 105
PLAINFIELD, NJ 07054
(908) 352-4770



P.O. EXECUTIVE OFFICE
SBA COMMUNICATIONS CORP
135 PLAINFIELD ROAD, SUITE 105
PLAINFIELD, NJ 07054
(908) 442-7400
www.sbacommunications.com



DESIGNED BY: JRF
APPROVED BY: JRF

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	10/24/22	ISSUED FOR CONSTRUCTION	JRF
2	10/24/22	ISSUED FOR PERMIT	JRF

PROJECT NAME: S. BRIDGE
ROCKY NECK CT
49 BRAINERD ROAD
NIANTIC, CT 06357

V01 LOCATION CODE: 490808
180 LOCATION ID: 0000000000
PIECE PROJECT ID: 00000000

SHEET NO.
TITLE SHEET

SHEET NO.
T01



CHECKED BY:	JAF
APPROVED BY:	JAF
SUBMITTALS	
NO.	DESCRIPTION
1	1/2" DIA. IRIS AIR CONDITIONER CAS
2	1/2" DIA. IRIS AIR CONDITIONER CAS

PROJECT NAME & NUMBER
ROCKY NECK CT
40 IRANHEID FIELD
NANTUCKET, CT 06557

TYPE LOCATION CODE: **NEWBERRY**
SOS LOCATION ID: **NEWBERRY**
FACE PROJECT ID: **NEWBERRY**

RF DATA
RF DATA

SHEET NUMBER
RF01

EXISTING EQUIPMENT CONFIGURATION

SECTOR	EQUIPMENT MAKE & MODEL	QTY	AZIMUTH (TRUE NORTH)	ANTENNA RAD	BAND	MECHANICAL DOWNTILT	ELECTRICAL DOWNTILT	EQUIPMENT STATUS	H (ft)	W (ft)	D (ft)	WEIGHT (LBS)	HYBRID CABLE SIZE & QTY
ALPHA	SHOCON SC-E 804A 804D PANEL ANTENNAS	1	40°	147'x 64"	SWR			ERC	86.0	8.5	8.0	25.0	
	ANDREW SHAW-1328E PANEL ANTENNAS	1	40°	147'x 64"	1.8 700/MS	0°/0°	172°	ERC	72.6	11.9	7.1	49.5	
	ANDREW SHAW-1328E PANEL ANTENNAS	1	40°	147'x 64"	1.8 700/MS	0°/0°	172°	ERC	72.6	11.9	7.1	49.5	
	SHOCON SC-E 804A 804D PANEL ANTENNAS	1	40°	147'x 64"	SWR			ERC	86.0	8.5	8.0	25.0	
BETA	SHOCON SC-E 804A 804D PANEL ANTENNAS	1	135°	147'x 64"	SWR			ERC	86.0	8.5	8.0	25.0	
	ANDREW SHAW-1328E PANEL ANTENNAS	1	135°	147'x 64"	1.8 700/MS	0°/0°	72°	ERC	72.6	11.9	7.1	49.5	
	ANDREW SHAW-1328E PANEL ANTENNAS	1	135°	147'x 64"	1.8 700/MS	0°/0°	72°	ERC	72.6	11.9	7.1	49.5	
	SHOCON SC-E 804A 804D PANEL ANTENNAS	1	135°	147'x 64"	SWR		270°	ERC	86.0	8.5	8.0	25.0	ERS: (1) 1-3/4" COAXIAL CABLES FIB: (2) 6x7 FIBER CABLES
GAMMA	ANDREW SHAW-1328E PANEL ANTENNAS	1	200°	147'x 64"	1.8 700/MS	0°/0°	274°	ERC	42.2	5.5	1.2	5.4	
	ANDREW SHAW-1328E PANEL ANTENNAS	1	200°	147'x 64"	1.8 700/MS	0°/0°	274°	ERC	72.6	11.9	7.1	49.5	
	ANDREW SHAW-1328E PANEL ANTENNAS	1	200°	147'x 64"	1.8 700/MS	0°/0°	274°	ERC	72.6	11.9	7.1	49.5	
	ANDREW SHAW-1328E PANEL ANTENNAS	1	200°	147'x 64"	SWR			ERC	42.2	5.5	1.2	5.4	
ALL	ANDREW SHAW-1328E PANEL ANTENNAS	3	-	-	-	-	-	ERC	25.8	11.8	7.2	29.8	
	SHOCON SC-E 804A 804D PANEL ANTENNAS	2	-	-	-	-	-	ERC	79.8	18.5	12.8	26.6	

NOTES:
1. "SWR" DENOTES "SWITCHING TO REMARK".
2. "ERC" DENOTES "EQUIPMENT TO BE REMOVED".
3. "ERS" LISTED ARE WITHIN MOUNTING BRACKETS.
4. INFORMATION IS BASED ON PERS DATED 06/18/21.

FINAL EQUIPMENT CONFIGURATION

SECTOR	EQUIPMENT MAKE & MODEL	QTY	AZIMUTH (TRUE NORTH)	ANTENNA RAD	BAND	MECHANICAL DOWNTILT	ELECTRICAL DOWNTILT	EQUIPMENT STATUS	H (ft)	W (ft)	D (ft)	WEIGHT (LBS)	HYBRID CABLE SIZE & QTY
ALPHA	SHOCON SC-E 804A 804D PANEL ANTENNAS	1	40°	147'x 64"	SWR			ERC	86.0	8.5	8.0	25.0	
	ANDREW SHAW-1328E PANEL ANTENNAS	2	40°	147'x 64"	1.8 700/MS/1800/MS	0°/0°/0°	71°/71°/0°	ERC	28.8	15.8	5.5	97.3	
BETA	SHOCON SC-E 804A 804D PANEL ANTENNAS	1	135°	147'x 64"	SWR			ERC	86.0	8.5	8.0	25.0	
	ANDREW SHAW-1328E PANEL ANTENNAS	2	135°	147'x 64"	1.8 700/MS/1800/MS	0°/0°/0°	27°/127°/127°	ERC	28.8	15.8	5.5	97.3	
GAMMA	SHOCON SC-E 804A 804D PANEL ANTENNAS	1	200°	147'x 64"	SWR			ERC	86.0	8.5	8.0	25.0	
	ANDREW SHAW-1328E PANEL ANTENNAS	2	200°	147'x 64"	1.8 700/MS/1800/MS	0°/0°/0°	27°/127°/127°	ERC	28.8	15.8	5.5	97.3	
ALL	SHOCON SC-E 804A 804D PANEL ANTENNAS	3	-	-	-	-	-	ERC	15.0	15.0	10.0	74.7	
	SHOCON SC-E 804A 804D PANEL ANTENNAS	3	-	-	-	-	-	ERC	15.0	15.0	10.0	74.7	

NOTES:
1. "SWR" DENOTES "SWITCHING TO REMARK".
2. "ERC" DENOTES "EQUIPMENT TO BE REMOVED".
3. "ERS" LISTED ARE WITHIN MOUNTING BRACKETS.
4. INFORMATION IS BASED ON PERS DATED 06/18/21.

FEEDLINE SCHEDULE

SCHEDULE	FEEDLINES	LOCATION
A	<p>IRIS PERIS TO IRIS</p> <p>(1) 1/2" COAXIAL CABLE PER PERIS ANTENNA</p> <p>(2) 1-3/4" COAXIAL CABLES</p> <p>(3) 6x7 FIBER CABLES</p>	IRIS PERIS
B	<p>IRIS PERIS TO IRIS</p> <p>IRIS PERIS TO IRIS</p>	IRIS PERIS

NOTE:
EXISTING ANTENNAS, EQUIPMENT, FEEDLINE INVENTORY INUSED ON OBSERVED FIELD CONDITIONS. PERIS AND FEEDLINE CABLES SHOWN WITHIN MOUNTING BRACKETS.



30 ALEXANDER DRIVE, 2ND FLOOR
 WESTPORT, CT 06897
 (203) 743-7328



800 COMMERCIAL CORP
 134 HANOVER ROAD, SUITE 105
 WESTPORT, CT 06897
 (203) 267-6729



CHAPPELL ASSOCIATES, LLC
 ALL EXECUTIVE CORP.
 1000 WEST MAIN STREET, SUITE 101
 WESTPORT, CT 06897
 (203) 447-7300
 www.chapellassociates.com



DATE: 01/14/14
 APPROVED BY: [Signature]
 PROJECT: WALK & AVENUE


REV	DATE	DESCRIPTION	BY
1	07/29/10	ISSUED FOR CONSTRUCTION	ONE
2	07/29/10	ISSUED FOR REVISION	ONE

ROCKY NECK CT
 40 BRANNEID ROAD
 NANTUCKET, CT 06857

VIEW LOCATION CODE: 40000
 4000 LOCATION ID: 0000000000
 TITLE PROJECT ID: 0000000000

RF COLOR CODE SPECIFICATIONS

RF03



Color	Quantity	Notes
Blue	100	700 Alpha
Purple	100	AWS Alpha
Green	100	PCS Alpha
Brown	100	850 Alpha
Yellow	100	Alpha Spare
White	100	Alpha Spare
Blue	100	700 Beta
Purple	100	AWS Beta
Green	100	PCS Beta
Brown	100	850 Beta
Yellow	100	Beta Spare
White	100	Beta Spare

CABLE NOTE:
 SEE EXISTING SCHEDULE A & B ON SHEET (RF01)
 FOR EXISTING & PROPOSED CABLE QUANTITIES.

HYBRID CABLE COLOR CODE SPECIFICATIONS
 SCALE: N/A

LINE COLOR CODE SPECIFICATIONS
 SCALE: N/A

10/15/13

20 ASHENBERG DRIVE, 2ND FLOOR
ROCKY HAVEN, MD 21773
(301) 711-7328

151 COMMUNICATIONS CENTER
150 WILSON AVENUE, SUITE 125
METHUEN, MA 01841
(978) 281-9725

811 EXECUTIVE COURT
201 BOSTON PORT ROAD WEST, SUITE 101
ROCKY HAVEN, MD 21773
(301) 401-7400
www.champell-engineers.com

GROUNDING GENERAL NOTES

- ALL EXTERIOR CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED. MINIMUM BUSHING SHALL BE 1/2" (Ø) FINISH.
- ALL WIRE-TO-WIRE CONNECTIONS SHALL BE THREE-CLAMP, 1/2" W/ COMPRESSION RING (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø).
- METHODS AND ANTENNA MOUNTS WITH 1/2" AWG. EMT, STEEL STRAPPED CONDUITS.
- CONDUIT GROUND CONNECTIONS TO EXISTING GROUNDING SYSTEM, ATTACH TO WALLS, PAVEMENT, CABLE TRAY OR WITH A CLAMP OR IN ACCORDANCE WITH, TERRESTRIAL, WLL, SCALE, ETC. TO ACHIEVE 100% W/ GROUND CONNECTION.
- CONNECT TO FIELD GROUND USING C-TP (Ø) (Ø) (Ø).
- CONNECT TO EXISTING GROUNDING SYSTEM.
- COMPRESSION WIRE CONNECTIONS ARE TO BE REPLACED BY EXTREMITY (Ø) (Ø) (Ø) CONNECTIONS.
- ALL GROUND CONNECTIONS BELOW 10' SHALL BE EXTREMITY (Ø) (Ø) (Ø).
- ALL GROUND CONNECTIONS ABOVE 10' SHALL BE EXTREMITY (Ø) (Ø) (Ø) OR EXTREMITY (Ø) (Ø) (Ø).
- ALL EXTERIOR CONNECTIONS TO THE GROUND BARS SHALL START AT THE TOP IN A VERTICAL MANNER.
- ALL EXTERIOR GROUND CONNECTIONS SHALL BE COVERED WITH A COMPRESSION RESISTANT MATERIAL.
- USE OF THE METHOD OF THE PROTECTION GROUNDING CONDUCTIVE SHALL BE AROUND BUSHING OF BUSHES AND/OR WELDED CONNECTIONS.
- ALL WIRE-TO-WIRE CONNECTIONS SHALL BE THREE-CLAMP, 1/2" W/ COMPRESSION RING (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø).
- ALL WIRE-TO-WIRE CONNECTIONS SHALL BE THREE-CLAMP, 1/2" W/ COMPRESSION RING (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø).
- ALL WIRE-TO-WIRE CONNECTIONS SHALL BE THREE-CLAMP, 1/2" W/ COMPRESSION RING (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø).
- ALL WIRE-TO-WIRE CONNECTIONS SHALL BE THREE-CLAMP, 1/2" W/ COMPRESSION RING (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø).
- ALL WIRE-TO-WIRE CONNECTIONS SHALL BE THREE-CLAMP, 1/2" W/ COMPRESSION RING (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø) AND/OR COMPRESSION WIRE (Ø).

LEGEND

GROUNDING SYMBOLS

⊗ GROUND BUS/ROD (REGARDLESS) WILL
○ GROUND ROD
◡ COMBINED TYPE CONNECTION
● COMPRESSION TYPE CONNECTION
○ GROUNDING WIRE
⊕ REFERENCE TO OTHER NUMBER

ABBREVIATIONS

AWG AMERICAN WIRE GAUGE
CWP COPPER WIRE
ECCS ELECTRICAL COMMUNICATIONS SYSTEM
PCS PERSONAL COMMUNICATION SYSTEM
RFW RADIO FREQUENCY
TYP. TYPICAL
WLD. GALVANIZED STEEL
ELECTRICAL METALLIC TUBING
DWD DRAWING
INT. INTERIOR GROUND BARS (HALO)
GEN. GENERATOR
GR. GROUND
COG. COIL GROUND BAR EXTERNAL
COGE COIL GROUND BAR EXTERNAL
MGR. MASTER GROUND BAR
PVC. RING (SCH. 40) POLYVINYL CHLORIDE CONDUIT
ETH. ETHYLENE BUTYL RUBBER
ETH. ETHYLENE BUTYL RUBBER

TYP. ANTENNA GROUNDING RISER

NOTE: ANTENNA GROUNDING RISERS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.

STATE OF CONNECTICUT PROFESSIONAL ENGINEER
JAMES A. FITZGERALD, No. 22687
C. ERECT: 06/12/2014
APPROVED BY: [Signature]
DATE: 06/12/2014

ROCKY NECK CT
46 HUNTERSHEAD ROAD
NAVAHO, CT 06379

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	10/24/2013	ISSUED FOR CONSTRUCTION	ME
2	10/24/2013	ISSUED FOR CONSTRUCTION	ME

TYP. INTERIOR EXTERIOR GROUND BAR

NOTES:

- ALL MATERIALS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.
- ALL CONNECTIONS SHALL BE FABRICATED BY WOODEN & INSTALLED BY CONTRACTOR.

CONN. OF GROUND WIRE TO GROUND BAR (LOWER)

NOTES:

- DO NOT INSTALL CABLE GROUND KIT AT A BUSHING OR THROUGH A CONDUIT.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.

INSTALLATION OF GROUND WIRE TO GROUND BAR

NOTES:

- DO NOT INSTALL CABLE GROUND KIT AT A BUSHING OR THROUGH A CONDUIT.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.

GROUND BAR CONNECTION

NOTES:

- "BOUNCE UP" OR "BOUNCE" OF CONNECTION IS NOT PERMITTED.
- USE SERRATED COPPER TO BE USED AT ALL LOCATIONS.

TYP. GROUND BAR CONNECTION

GROUNDING NOTES & DETAILS

GROUNDING NOTES & DETAILS

E01

TYP. EQUIPMENT GROUND CONNECTION

NOTES:

- DO NOT INSTALL CABLE GROUND KIT AT A BUSHING OR THROUGH A CONDUIT.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.

CONN. OF CABLE GROUND KIT TO ANTENNA CABLE

NOTES:

- DO NOT INSTALL CABLE GROUND KIT AT A BUSHING OR THROUGH A CONDUIT.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.

GROUND BAR DETAILS

MASTER GROUND BAR (MGR)

EQUIPMENT GROUND BAR (EGR)

NOTES:

- DO NOT INSTALL CABLE GROUND KIT AT A BUSHING OR THROUGH A CONDUIT.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.
- CONDUITS SHALL BE 2x 1/2" EMT, GALV. STEEL THROD COPPER UNLESS OTHERWISE NOTED.



25 FARMERS ROAD, 2ND FLOOR
 SUITE 200
 BRANFORD, CT 06405
 (800) 741-7338



SBA COMMUNICATIONS CORP.
 124 JAMES ROAD, SUITE 125
 BRANFORD, CT 06405
 (860) 251-0720



CHAPPELL ENGINEERING
 ASSOCIATES, LLC
 231 EXECUTIVE CENTER
 SUITE 200A
 BRANFORD, CT 06405
 (860) 481-7400
 www.chappell-engineering.com



DATE: 11/14/17
 APPROVED BY: [Signature]

NO.	DATE	DESCRIPTION	BY
1	11/14/17	ISSUED FOR CONSTRUCTION	AM
2	11/14/17	ISSUED FOR CONSTRUCTION	AM

PROJECT NAME & NUMBER
ROCKY NECK CT
 48 BRANFORD ROAD
 BRANFORD, CT 06405


VENDOR LOCATION CODE
 0000000000
 PROJECT ID:
 0000000000

SHEET TITLE
MOUNT MODIFICATION DRAWINGS

SHEET NUMBER
MM01

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	PRICE	TOTAL
1
2
3
4
5
6
7
8
9
10

THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL, STATE, AND FEDERAL AGENCIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL, STATE, AND FEDERAL AGENCIES.



verizon

MOUNT MODIFICATION DRAWINGS
 EXISTING TLE50 PLATFORM
 TOWER OWNER: SBA COMMUNICATIONS
 TOWER OWNER SITE NUMBER: CT11794
 CARRIER SITE NAME: ROCKY NECK CT
 CARRIER SITE NUMBER: 600124867
 FLZE ID: 2495329

49 BRAINERD ROAD
 NIANCTIC, CT 06457
 NEW LONDON COUNTY
 LATITUDE: 41.507585° N
 LONGITUDE: 72.423917° W

DESIGN CRITERIA

DESIGN INDEX

DESIGN SUBMITTALS

REVISIONS

APPROVED BY: [Signature]

verizon

PHOTO CREDIT PHOTO

REVISIONS

DESIGN CRITERIA

DESIGN INDEX

DESIGN SUBMITTALS

REVISIONS

APPROVED BY: [Signature]



PROPOSED SOLUTION VIEW

PROPOSED SOLUTION VIEW

DATE: 10/18/18

SCALE: AS SHOWN

PROJECT: 18-000000

CLIENT: VERIZON

LOCATION: 154 PLAINFIELD ROAD, WESTPORT, MA 01891

DATE: 10/18/18

SCALE: AS SHOWN

PROJECT: 18-000000

CLIENT: VERIZON

LOCATION: 154 PLAINFIELD ROAD, WESTPORT, MA 01891

PROPOSED SOLUTION VIEW

PROPOSED SOLUTION VIEW

DATE: 10/18/18

SCALE: AS SHOWN

PROJECT: 18-000000

CLIENT: VERIZON

LOCATION: 154 PLAINFIELD ROAD, WESTPORT, MA 01891

DATE: 10/18/18

SCALE: AS SHOWN

PROJECT: 18-000000

CLIENT: VERIZON

LOCATION: 154 PLAINFIELD ROAD, WESTPORT, MA 01891

ROCKY NECK CT

154 PLAINFIELD ROAD
WESTPORT, MA 01891

FOR VERIFICATION ONLY

DATE: 10/18/18

SCALE: AS SHOWN

PROJECT: 18-000000

CLIENT: VERIZON

LOCATION: 154 PLAINFIELD ROAD, WESTPORT, MA 01891

FOR REFERENCE ONLY

FOR REFERENCE ONLY

DATE: 10/18/18

SCALE: AS SHOWN

PROJECT: 18-000000

CLIENT: VERIZON

LOCATION: 154 PLAINFIELD ROAD, WESTPORT, MA 01891

FOR REFERENCE ONLY

FOR REFERENCE ONLY

DATE: 10/18/18

SCALE: AS SHOWN

PROJECT: 18-000000

CLIENT: VERIZON

LOCATION: 154 PLAINFIELD ROAD, WESTPORT, MA 01891

MM02

FOR REFERENCE ONLY

FOR REFERENCE ONLY



20 ALDERSBURY DRIVE, 2ND FLOOR
MANTIC, CT 06357
(860) 741-7233



SBA COMMUNICATIONS CORP.
134 BARNBERG ROAD, SUITE 125
MANTIC, CT 06357
(860) 251-0720



CHapel Hill CONSTRUCTION
CORPORATION, LLC
P.O. BOX 1000
MANTIC, CT 06357
(860) 481-7100
www.chapelhillconstruction.com



DATE: 01/27/16
APPROVED BY: [Signature]




REV	DATE	DESCRIPTION	BY
1	01/27/16	ISSUED FOR CONSTRUCTION	MM
2	01/27/16	ISSUED FOR REVIEW	MM

PROJECT NAME & ADDRESS
ROCKY NECK CT
49 BARNBERG ROAD
MANTIC, CT 06357

YOUR LOCATION CODE: 000000
SBA LOCATION ID: 0000000000
FLICE PROJECT ID: 0000000000

PROJECT TITLE:
MOUNT MODIFICATION
DRAWINGS II

SHEET NUMBER:
MM03




C-band 64T64R

Gen 2

SAMSUNG

Gen 2 : Higher conducted power ratio with reduced size/volume/weight vs Gen 1 and also SOC embedded for flexibility to support new features



※ Preliminary Design: External appearance and mechanical design can be subject to change

Gen 2. 64T64R C-band MMU Dimensions	
Size (WxHxD)	400 x 734 x 140 mm (15.75 x 28.90 x 5.51 inch)
Weight	26kg (57.3 lb)

Item	Gen 2 64T64R (MT6413-77A)
Air Technology	NR n77/7DD
Frequency	3700 – 3980 MHz
IBW	200 MHz
OBW	200 MHz
Carrier Bandwidth	200MHz (ready)/400/600/800/1000 MHz
# of Carriers	2 carriers
Layer	DL : 16L, UL : 16RX (8L)
RF Chain	64T64R
Antenna Configuration	4V16H with 192 AE
EIRP	80.5 dBm @320W (55 dBm + 25.5 dB)
Conductive Power	320W
Spectrum Analyzer	TX/RX support
RX Sensitivity	Typical -97.8dBm @1Rx, 18.36MHz with 30MHz, 51RRS)
Modulation	DL 256QAM support, (DL 1024QAM with 1-2dB power back-off)
Function Split	DL/UL option 7-2x
Input Power	-48 VDC (-38 VDC to -57 VDC)
Power Consumption	1,287W (100% load, room temp.)
Size (WHD)	400 x 734 x 140 mm (15.75 x 28.90 x 5.51 inch)
Volume	41.1L
Weight	26kg (57.3 lb)
Operating Temperature	-40°C - 55°C (w/o solar load)
Cooling	Natural convection 3GPP 38.104
Unwanted Emission	FCC 47 CFR 27.53 : < -130dBm/MHz < -40 dBm/MHz @ above 4 GHz < -50 dBm /MHz @ 4,040 ~ 4,050 MHz < -60 dBm /MHz @ above 4,050 MHz
Optic Interface	15km, 4 ports (25Gbps x 4), SFP28, single mode, Bi-di (Option: Duplex)
Mounting Options	Pole, wall
NB-IoT	Not support
External Alarm	4RX
Fronthaul Interface	eCPRI


MX06FRO660-03

NWAV™ X-Pol Hex-Port Antenna

X-Pol Hex-Port 6 ft 60° Fast Roll Off antenna with independent tilt on 700 & 850 MHz:

2 ports 698-798, 824-894 MHz and 4 ports 1695-2180 MHz

- Fast Roll Off (FRO™) azimuth beam pattern improves Intra- and Inter-cell SINR
- Compatible with dual band 700/850 MHz radios with independent low band EDT without external diplexers
- Fully integrated (iRETs) with independent RET control for low and high bands for ease of network optimization
- SON-Ready array spacing supports beamforming capabilities
- Suitable for LTE/CDMA/PCS/UMTS/GSM air interface technologies
- Integrated Smart Bias-Ts reduce leasing costs



NWAV

Fast Roll-Off antennas increase data throughput without compromising coverage



The horizontal beam produced by Fast Roll-Off (FRO) technology increases the Signal to Interference & Noise Ratio (SINR) by eliminating overlap between sectors.

Non-FRO antenna

Large traditional antenna pattern overlap creates harmful interference.

JMA FRO antenna

JMA's FRO antenna pattern minimizes overlap, thereby minimizing interference.



LTE throughput	SINR	Speed (bps/Hz)	Speed increase	CQI
Excellent	>18	>4.5	333+%	8-10
Good	15-18	3.3-4.5	277%	6-7
Fair	10-15	2-3.3	160%	4-6
Poor	<10	<2	0%	1-3


The LTE radio automatically selects the best throughput based on measured SINR.

Electrical specification (minimum/maximum)	Ports 1, 2		Ports 3, 4, 5, 6		
Frequency bands, MHz	698-798	824-894	1695-1880	1850-1990	1920-2180
Polarization	± 45°		± 45°		
Average gain over all tilts, dBi	14.4	14.0	17.6	18.0	18.2
Horizontal beamwidth (HBW), degrees	60.5	53.0	55.0	55.0	55.5
Front-to-back ratio, co-polar power @180°± 30°, dB	>24	>24.0	>25.0	>25.0	>25.0
X-Pol discrimination (CPR) at boresight, dB	>15.0	>14.2	>18	>18	>15
Sector power ratio, percent	<3.5	<3.0	<3.7	<3.8	<3.6
Vertical beamwidth (VBW), degrees ¹	13.1	11.8	6.0	5.5	5.5
Electrical downtilt (EDT) range, degrees	2-14	2-14	0-9		
First upper side lobe (USLS) suppression, dB ¹	≤-15.0	≤-16.5	≤-16.0	≤-16.0	≤-16.0
Cross-polar isolation, port-to-port, dB ¹	25	25	25	25	25
Max VSWR / return loss, dB	1.5:1 / -14.0		1.5:1 / -14.0		
Max passive intermodulation (PIM), 2x20W carrier, dBc	-153		-153		
Max input power per any port, watts	300		250		
Total composite power all ports, watts	1500				

¹ Typical value over frequency and tilt

Mechanical specifications

Dimensions height/width/depth, inches (mm)	71.3/ 15.4/ 10.7 (1811/ 392/ 273)
Shipping dimensions length/width/height, inches (mm)	82/ 20/ 15 (2083/ 508/ 381)
No. of RF input ports, connector type, and location	6 x 4.3-10 female, bottom
RF connector torque	96 lbf-in (10.85 N·m or 8 lbf-ft)
Net antenna weight, lb (kg)	60 (27.0)
Shipping weight, lb (kg)	90 (41.0)
Antenna mounting and downtilt kit included with antenna	91900318
Net weight of the mounting and downtilt kit, lb (kg)	18 (8.18)
Range of mechanical up/down tilt	-2° to 14°
Rated wind survival speed, mph (km/h)	150 (241)
Frontal, lateral, and rear wind loading @ 150 km/h, lbf (N)	154 (685), 73 (325), 158 (703)
Equivalent flat plate @ 100 mph and Cd=2, sq ft	2.6



Ordering information


Antenna model	Description
MX06FRO660-03	6F X-Pol HEX FRO 60° independent tilt 700/850 RET, 4.3-10 & SBT
Optional accessories	
AISG cables	M/F cables for AISG connections
PCU-1000 RET controller	Stand-alone controller for RET control and configurations

Remote electrical tilt (RET 1000) information

RET location	Integrated into antenna
RET interface connector type	8-pin AISG connector per IEC 60130-9
RET connector torque	Min 0.5 N·m to max 1.0 N·m (hand pressure & finger tight)
RET interface connector quantity	2 pairs of AISG male/female connectors
RET interface connector location	Bottom of the antenna
Total no. of internal RETs (low bands)	2
Total no. of internal RETs (high bands)	1
RET input operating voltage, vdc	10-30
RET max power consumption, idle state, W	≤ 2.0
RET max power consumption, normal operating conditions, W	≤ 13.0
RET communication protocol	AISG 2.0 / 3GPP

RET and RF connector topology

Each RET device can be controlled either via the designated external AISG connector or RF port as shown below:




Array topology

3 sets of radiating arrays

R1/R2: 698-894 MHz
 B1: 1695-2180 MHz
 B2: 1695-2180 MHz

Band	RF port
1695-2180	3-4
698-894	1-2
1695-2180	5-6



SAMSUNG

AWS/PCS MACRO RADIO

DUAL-BAND AND HIGH POWER FOR MACRO COVERAGE

Samsung's future proof dual-band radio is designed to help effectively increase the coverage areas in wireless networks. This AWS/PCS 4T4R dual-band radio has 4Tx/4Rx to 2Tx/2Rx RF chains options and a total output power of 320W, making it ideal for macro sites.

Model Code RF4439d-25A



Homepage
samsungnetworks.com




Youtube
www.youtube.com/samsung5g

Points of Differentiation

Continuous Migration


Samsung's AWS/PCS macro radio can support each incumbent CPRI interface as well as advanced eCPRI interfaces. This feature provides installable options for both legacy LTE networks and added NR networks.



O-RAN Compliant

A standardized O-RAN radio can help in implementing cost-effective networks, which are capable of sending more data without compromising additional investments.


Samsung's state-of-the-art O-RAN technology will help accelerate the effort toward constructing a solid O-RAN ecosystem.



Optimum Spectrum Utilization

The number of required carriers varies according to site (region). Supporting many carriers is essential for using all frequencies that the operator has available.

The new AWS/PCS dual-band radio can support up to 3 carriers in the PCS (1.9GHz) band and 4 carriers in the AWS (2.1GHz) band, respectively.



Brand New Features in a Compact Size

Samsung's AWS/PCS macro radio offers several features, such as dual connectivity for baseband for both CDU and vDU, O-RAN capability, more carriers and an enlarged PCS spectrum, combined into an incumbent radio volume of 36.8L.



Technical Specifications

Item	Specification
Tech	LTE / NR
Brand	B25(PCS), B66(AWS)
Frequency Band	DL: 1930 – 1995MHz, UL: 1850 – 1915MHz DL: 2110 – 2200MHz, UL: 1710 – 1780MHz
RF Power	(B25) 4 × 40W or 2 × 60W (B66) 4 × 60W or 2 × 80W
IBW/OBW	(B25) 65MHz / 30MHz (B66) DL 90MHz, UL 70MHz / 60MHz
Installation	Pole, Wall
Size/Weight	14.96 x 14.96 x 10.04inch (36.8L) / 74.7lb

700/850 4T4R Macro 320W ORU - New Filter (RF4461d-13A)

SAMSUNG

Specifications



Item	Specification
Air Interface	LTE, NR(HW resource ready)
Band	Band13 (700MHz) DL: 869-894MHz UL: 824-849MHz 25MHz 25MHz
Frequency	Band5 (850MHz) DL: 869-894MHz UL: 824-849MHz 25MHz 25MHz
IBW	10MHz
OBW	10MHz
Carrier Bandwidth	LTE/NR 5*/10MHz
# of carriers	2C*
Total # of carriers	4C + B13 (SDL) 1C 4T4R/2T4R/2T2R/1T2R
RF Chain	2T2R-2T2R bi-sector Total: 320W
RF Output Power	4 x 40W or 2 x 80W
Spectrum Analyzer	TX/RX Support
RX Sensitivity	Typ. -104.5dBm @1Rx (25RBs 5MHz)
Modulation	256QAM support, (1024QAM with 1~2dB power back-off) -48VDC (-38VDC to -57VDC)
Input Power	1,165 Watt @ 100% RF load, room temperature
Power Consumption	380 x 380 x 260 mm (14.96 x 14.96 x 10.23 inch)
Size (WHD)	37.5 L
Volume	
Weight (w/o Solar Shield & finger guard)	35.9 kg (79.1 lb)
Operating Temperature	-40°C (-40°F) ~ 55°C (131°F) (Without solar load)
Cooling	Natural convection
Unwanted Emission	3GPP 36.104 FCC 47 CFR 27.53 (i)
CPRI Cascade	Not supported
Optic Interface	20km, 2 ports (9.8Gbps x 2), SFP+, single mode, Duplex (Option: Bi-d)
RET & TMA Interface	AISG 3.0
Bias-T	4 ports (2 ports per band)
Mounting Options	Pole, wall
NB-IoT	Support
PIM Cancellation	25A+2GB or 2GB+2IE or 4GB
# of antenna port	4
External Alarm	4
Fronthaul Interface	Opt. 8 CPRI / Opt. 7-2x selectable (not simultaneous support)
CPRI compression	Not Support

* 5MHz supporting in B13(700MHz) depends on 3Gpp std. and UE capability.
External filters in interposer and victim sides for Mexican boarder to support 5MHz service need to be considered
** Finger guard is not needed.

ATTACHMENT 3



C Squared Systems, LLC
65 Dartmouth Drive
Auburn, NH 03032
(603) 644-2800
support@csquaredsystems.com

Calculated Radio Frequency Emissions Report



Rocky Neck CT
49 Brainerd Road, Niantic, CT 06357

February 7, 2024

Table of Contents

1. Introduction.....	1
2. FCC Guidelines for Evaluating RF Radiation Exposure Limits	1
3. RF Exposure Prediction Methods	2
4. Antenna Inventory.....	3
5. Calculation Results.....	4
6. Conclusion.....	6
7. Statement of Certification.....	6
Attachment A: References.....	7
Attachment B: FCC Limits for Maximum Permissible Exposure (MPE)	8
Attachment C: Verizon Antenna Model Data Sheets and Electrical Patterns.....	10

List of Figures

Figure 1: Graph of General Population % MPE vs. Distance.....	4
Figure 2: Graph of FCC Limits for Maximum Permissible Exposure (MPE).....	9

List of Tables

Table 1: Proposed Antenna Inventory	3
Table 2: Maximum Percent of General Population Exposure Values	5
Table 4: FCC Limits for Maximum Permissible Exposure	8

1. Introduction

The purpose of this report is to investigate compliance with applicable FCC regulations for the proposed modification of Verizon's antenna arrays to be mounted at 147' on an existing monopole tower located at 49 Brainerd Road in Niantic, CT. The coordinates of the tower are 41° 18' 27.29" N, 72° 13' 26.11" W.

Verizon is proposing the following:

- 1) Install nine (9) multi-band antennas, three (3) per sector to support its commercial LTE and 5G network.

This report considers the planned antenna configuration for Verizon¹ as well as existing antenna configuration for AT&T², and T-Mobile³ to derive the resulting % MPE of its proposed modification.

2. FCC Guidelines for Evaluating RF Radiation Exposure Limits

In 1985, the FCC established rules to regulate radio frequency (RF) exposure from FCC licensed antenna facilities. In 1996, the FCC updated these rules, which were further amended in August 1997 by OET Bulletin 65 Edition 97-01. These new rules include Maximum Permissible Exposure (MPE) limits for transmitters operating between 300 kHz and 100 GHz. The FCC MPE limits are based upon those recommended by the National Council on Radiation Protection and Measurements (NCRP), developed by the Institute of Electrical and Electronics Engineers, Inc., (IEEE) and adopted by the American National Standards Institute (ANSI).

The FCC general population/uncontrolled limits set the maximum exposure to which most people may be subjected. General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure.

Public exposure to radio frequencies is regulated and enforced in units of milliwatts per square centimeter (mW/cm²). The general population exposure limits for the various frequency ranges are defined in the attached "FCC Limits for Maximum Permissible Exposure (MPE)" in Attachment C of this report.

Higher exposure limits are permitted under the occupational/controlled exposure category, but only for persons who are exposed as a consequence of their employment and who have been made fully aware of the potential for exposure, and they must be able to exercise control over their exposure. General population/uncontrolled limits are five times more stringent than the levels that are acceptable for occupational, or radio frequency trained individuals. Attachment C contains excerpts from OET Bulletin 65 and defines the Maximum Exposure Limit.

Finally, it should be noted that the MPE limits adopted by the FCC for both general population/uncontrolled exposure and for occupational/controlled exposure incorporate a substantial margin of safety and have been established to be well below levels generally accepted as having the potential to cause adverse health effects.

¹ As referenced to Verizon's Radio Frequency Design Sheet updated 08/16/2023.

² As referenced to AT&T's Connecticut Siting Council Notice of Exempt Modification – 49 Brainerd Road, Niantic, Connecticut, dated March 15, 2023.

³ As referenced to T-Mobile's Connecticut Siting Council Exempt Modification Application – 49 Brainerd Road, East Lyme, Connecticut, dated June 2, 2022

3. RF Exposure Prediction Methods

The emission field calculation results displayed in the following figures were generated using the following formula as outlined in FCC bulletin OET 65:

$$\text{Power Density} = \left(\frac{\text{GRF}^2 \times 1.64 \times \text{ERP}}{4\pi \times R^2} \right) \times \text{Off Beam Loss}$$

Where:

EIRP = Effective Isotropic Radiated Power

R = Radial Distance = $\sqrt{H^2 + V^2}$

H = Horizontal Distance from antenna in meters

V = Vertical Distance from radiation center of antenna in meters

Off Beam Loss is determined by the selected antenna patterns

Ground reflection factor (GRF) of 1.6

These calculations assume that the antennas are operating at 100 percent capacity, that all antenna channels are transmitting simultaneously, and that the radio transmitters are operating at full power. Obstructions (trees, buildings, etc.) that would normally attenuate the signal are not taken into account. The calculations assume even terrain in the area of study and do not take into account actual terrain elevations which could attenuate the signal. As a result, the predicted signal levels reported below are much higher than the actual signal levels will be from the final installations.

4. Antenna Inventory

Table 1 below outlines Verizon’s proposed antenna configuration for the site. The associated data sheets and antenna patterns for these specific antenna models are included in Attachments C.

Operator	Sector / Call Sign	TX Freq (MHz)	Power at Antenna (Watts)	Ant Gain (dBi)	Power EIRP (Watts)	Antenna Model	Beam Width	Mech. Tilt	Length (ft)	Antenna Centerline Height (ft)
Verizon	Alpha / 40°	700	160	14.4	4407	MX06FRO660-03	60.5	0	5.94	147
		850	160	14.0	4019		53.0			
		1900	160	18.0	10095		55.0			
		2100	240	18.2	15857		55.5			
		3700	320	25.5	113540	MT6413-77A	-	0	2.46	147
	Beta / 135°	700	160	14.4	4407	MX06FRO660-03	60.5	0	5.94	147
		850	160	14.0	4019		53.0			
		1900	160	18.0	10095		55.0			
		2100	240	18.2	15857		55.5			
		3700	320	25.5	113540	MT6413-77A	-	0	2.46	147
	Gamma / 280°	700	160	14.4	4407	MX06FRO660-03	60.5	0	5.94	147
		850	160	14.0	4019		53.0			
		1900	160	18.0	10095		55.0			
		2100	240	18.2	15857		55.5			
3700		320	25.5	113540	MT6413-77A	-	0	2.46	147	

Table 1: Proposed Antenna Inventory⁴⁵

⁴ Antenna heights are in reference to Verizon’s Radio Frequency Design Sheet updated 08/16/2023.

⁵ Transmit power assumes 0 dB of cable loss.

5. Calculation Results

The calculated power density results are shown in Figure 1 below. For completeness, the calculations for this analysis range from 0 feet horizontal distance (directly below the antennas) to a value of 3,000 feet horizontal distance from the site. In addition to the other worst-case scenario considerations that were previously mentioned, the power density calculations to each horizontal distance point away from the antennas was completed using a local maximum off beam antenna gain (within ± 5 degrees of the true mathematical angle) to incorporate a realistic worst-case scenario.




Figure 1: Graph of General Population % MPE vs. Distance

The highest percent of MPE (10.06% of the General Population limit) is calculated to occur at a horizontal distance of 663 feet from antennas. Please note that the percent of MPE calculations close to the site take into account off beam loss, which is determined from the vertical pattern of the antennas used. Therefore, RF power density levels may increase as the distance from the site increases. At distances of approximately 1500 feet and beyond, one would now be in the main beam of the antenna pattern and off beam loss is no longer considered. Beyond this point, RF levels become calculated solely on distance from the site and the percent of MPE decreases significantly as distance from the site increases.

Table 2 below lists percent of MPE values as well as the associated parameters that were included in the calculations. The highest percent of MPE value was calculated to occur at a horizontal distance of 663 feet from the site (reference Figure 1).

As stated in Section 3, all calculations assume that the antennas are operating at 100 percent capacity, that all antenna channels are transmitting simultaneously, and that the radio transmitters are operating at full power. Obstructions (trees, buildings etc.) that would normally attenuate the signal are not taken into account. In addition, a six foot height offset was considered in this analysis to account for average human height. As a result, the predicted signal levels are significantly higher than the actual signal levels will be from the final configuration. The results presented in Figure 1 and Table 2 assume level ground elevation from the base of the tower out to the horizontal distances calculated.

Carrier	Number of Transmitters	Power out of Base Station Per Transmitter (Watts)	Antenna Height (Feet)	Distance to the Base of Antennas (Feet)	Power Density (mW/cm ²)	Limit (mW/cm ²)	% MPE
AT&T LTE 1900 MHz	1	160.0	168.0	663	0.000235	1.000	0.02%
AT&T LTE 2100 MHz	1	160.0	168.0	663	0.000251	1.000	0.03%
AT&T LTE 2300 MHz	4	18.8	168.0	663	0.000059	1.000	0.01%
AT&T LTE 700 MHz	4	30.0	168.0	663	0.000522	0.467	0.11%
AT&T LTE 700 MHz	4	30.0	168.0	663	0.000810	0.467	0.17%
AT&T LTE 850 MHz	4	30.0	168.0	663	0.001001	0.567	0.18%
T-Mobile GSM 1900 MHz	4	30.0	160.0	663	0.000081	1.000	0.01%
T-Mobile LTE 1900 MHz	2	60.0	160.0	663	0.000081	1.000	0.01%
T-Mobile LTE 2100 MHz	2	60.0	160.0	663	0.000114	1.000	0.01%
T-Mobile LTE 700 MHz	1	140.0	160.0	663	0.000961	0.400	0.24%
T-Mobile LTE 700 MHz	2	30.0	160.0	663	0.000442	0.467	0.09%
T-Mobile LTE/5G 2500 MHz	1	240.0	140.0	663	0.039707	1.000	3.97%
Verizon 5G 3700 MHz	1	320.0	147.0	663	0.038319	1.000	3.83%
Verizon LTE 1900 MHz	1	160.0	147.0	663	0.003100	1.000	0.31%
Verizon LTE 2100 MHz	1	240.0	147.0	663	0.004757	1.000	0.48%
Verizon LTE 750 MHz	1	160.0	147.0	663	0.001209	0.500	0.24%
Verizon LTE 850/5G MHz	1	160.0	147.0	663	0.001963	0.567	0.35%
						Total	10.06%

Table 2: Maximum Percent of General Population Exposure Values⁶⁷⁸

⁶ Frequencies listed are representative of the operating band and are not the specific operating frequency.

⁷ The total % MPE listed is a summation of each unrounded contribution. Therefore, summing each rounded value may not reflect the total value listed in the table.

⁸ In the case where antenna pattern data was unavailable from the manufacturer, generic antenna pattern was used based on the frequency, bandwidth and gain of the antenna.

6. Conclusion

The above analysis verifies that RF exposure levels from the site with Verizon's proposed antenna configuration will be well below the maximum permissible levels as outlined by the FCC in the OET Bulletin 65 Ed. 97-01. Using the conservative calculation methods and parameters detailed above, the maximum cumulative percent of MPE in consideration of all transmitters is calculated to be **10.06%** of the FCC limit (General Population/Uncontrolled). This maximum cumulative percent of MPE value is calculated to occur 663 feet away from the site.


7. Statement of Certification

I certify to the best of my knowledge that the statements in this report are true and accurate. The calculations follow guidelines set forth in ANSI/IEEE Std. C95.3, ANSI/IEEE Std. C95.1 and FCC OET Bulletin 65 Edition 97-01.



Report Prepared By: Ram Acharya
RF Engineer
C Squared Systems, LLC

February 6, 2024
Date



Reviewed/Approved By: Martin Lavin
Senior RF Engineer
C Squared Systems, LLC

February 7, 2024
Date

Attachment A: References

OET Bulletin 65 - Edition 97-01 - August 1997 Federal Communications Commission Office of Engineering & Technology

IEEE C95.1-2005, IEEE Standard Safety Levels With Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz IEEE-SA Standards Board

IEEE C95.3-2002 (R2008), IEEE Recommended Practice for Measurements and Computations of Radio Frequency Electromagnetic Fields With Respect to Human Exposure to Such Fields, 100 kHz-300 GHz IEEE-SA Standards Board

Attachment B: FCC Limits for Maximum Permissible Exposure (MPE)

(A) Limits for Occupational/Controlled Exposure⁹

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f ²)*	6
30-300	61.4	0.163	1.0	6
300-1500	-	-	f/300	6
1500-100,000	-	-	5	6

(B) Limits for General Population/Uncontrolled Exposure¹⁰

Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (E) (A/m)	Power Density (S) (mW/cm ²)	Averaging Time E ² , H ² or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f ²)*	30
30-300	27.5	0.073	0.2	30
300-1500	-	-	f/1500	30
1500-100,000	-	-	1.0	30

f = frequency in MHz * Plane-wave equivalent power density

Table 3: FCC Limits for Maximum Permissible Exposure

⁹ Occupational/controlled limits apply in situations in which persons are exposed as a consequence of their employment provided those persons are fully aware of the potential for exposure and can exercise control over their exposure. Limits for occupational/controlled exposure also apply in situations when an individual is transient through a location where occupational/controlled limits apply provided he or she is made aware of the potential for exposure.

¹⁰ General population/uncontrolled exposures apply in situations in which the general public may be exposed, or in which persons that are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over their exposure.








Figure 2: Graph of FCC Limits for Maximum Permissible Exposure (MPE)

Attachment C: Verizon Antenna Model Data Sheets and Electrical Patterns

<p>750 MHz</p> <p>Manufacturer: JMA Model #: MX06FRO660-03 Frequency Band: 698-798 MHz Gain: 14.4 dBi Vertical Beamwidth: 13.1° Horizontal Beamwidth: 60.5° Polarization: ±45° Dimensions (L x W x D): 71.3" x 15.4" x 10.7"</p>	 <p>A polar plot radiation pattern for 750 MHz. The plot shows a main lobe centered at 0 degrees with a peak gain of approximately 14.4 dBi. The horizontal beamwidth is 60.5 degrees, and the vertical beamwidth is 13.1 degrees. The plot includes concentric circles representing gain levels and radial lines for angles from 0 to 180 degrees.</p>
<p>885 MHz</p> <p>Manufacturer: JMA Model #: MX06FRO660-03 Frequency Band: 824-894 MHz Gain: 14.0 dBi Vertical Beamwidth: 11.8° Horizontal Beamwidth: 53.0° Polarization: ±45° Dimensions (L x W x D): 71.3" x 15.4" x 10.7"</p>	 <p>A polar plot radiation pattern for 885 MHz. The plot shows a main lobe centered at 0 degrees with a peak gain of approximately 14.0 dBi. The horizontal beamwidth is 53.0 degrees, and the vertical beamwidth is 11.8 degrees. The plot includes concentric circles representing gain levels and radial lines for angles from 0 to 180 degrees.</p>

<p>1900 MHz</p> <p>Manufacturer: JMA Model #: MX06FRO660-03 Frequency Band: 1850-1990 MHz Gain: 18.0 dBi Vertical Beamwidth: 5.5° Horizontal Beamwidth: 55.0° Polarization: ±45° Dimensions (L x W x D): 71.3" x 15.4" x 10.7"</p>	 <p>A polar plot showing the radiation pattern for 1900 MHz. The plot is circular with concentric rings representing gain levels and radial lines representing angles from 0 to 180 degrees. The main beam is centered at 0 degrees, extending to approximately 150 degrees on the gain scale. There are several smaller side lobes extending outwards.</p>
<p>2100 MHz</p> <p>Manufacturer: JMA Model #: MX06FRO660-03 Frequency Band: 1920-2180 MHz Gain: 18.2 dBi Vertical Beamwidth: 5.5° Horizontal Beamwidth: 55.5° Polarization: ±45° Dimensions (L x W x D): 71.3" x 15.4" x 10.7"</p>	 <p>A polar plot showing the radiation pattern for 2100 MHz. The plot is circular with concentric rings representing gain levels and radial lines representing angles from 0 to 180 degrees. The main beam is centered at 0 degrees, extending to approximately 150 degrees on the gain scale. There are several smaller side lobes extending outwards.</p>

ATTACHMENT 4

SBA Communications Corporation
8051 Congress Avenue
Boca Raton, FL 33487-1307

T + 561 995 7670
F + 561 995 7626

sbsite.com



Structural Analysis Report

Client: Verizon

Client Site ID / Name: Rocky Neck CT / 5000122067
Application #: 243517, v1

SBA Site ID / Name: CT11794-S / East Lyme 1

170 ft Monopole

49 Brainerd Road
Niantic, Connecticut 06357
Lat: 41.307583, Long: -72.223917

Project number: CT11794-VZW-011124

Analysis Results

Tower	82.8%	Pass
Foundation	93.0%	Pass

Change in tower stress due to mount modification / replacement	N/A
--	-----

Prepared by:

Serge Berthomieux
Structural Engineer I
561-226-9365
SBerthomieux@sbsite.com

Reviewed by:

Anantha (Shan) Shanubhogue, P.E.
Senior Manager, Structural Engineering
561-981-7390
SShanubhogue@sbsite.com

January 11, 2024



01/11/24

SBA Communications Corporation
8051 Congress Avenue
Boca Raton, FL 33487-1307

T + 561 995 7670
F + 561 995 7626

sbsite.com



Structural Analysis Report

Client: Verizon

Client Site ID / Name: Rocky Neck CT / 5000122067
Application #: 243517, v1

SBA Site ID / Name: CT11794-S / East Lyme 1

170 ft Monopole

49 Brainerd Road
Niantic, Connecticut 06357
Lat: 41.307583, Long: -72.223917

Project number: CT11794-VZW-011124

Analysis Results

Tower	82.8%	Pass
Foundation	93.0%	Pass

Change in tower stress due to mount modification / replacement	N/A
--	-----

Prepared by:

Serge Berthomieux
Structural Engineer I
561-226-9365
SBerthomieux@sbsite.com

Reviewed by:

Anantha (Shan) Shanubhogue, P.E.
Senior Manager, Structural Engineering
561-981-7390
SShanubhogue@sbsite.com

January 11, 2024

Table of Contents

Introduction..... 3

Analysis Criteria 3

Appurtenance Loading 4

 Existing Loading: 4

 Proposed Loading: 5

Analysis Results 6

 Tower 6

 Foundation 6

Conclusions 7

Installation Requirements 7

Assumptions and Limitations 8

 Assumptions 8

 Limitations 8

Appendix 9

 Tower Geometry 9

 Coax Layout 9

 TESPole Report 9

 Foundation Analysis Report 9



Introduction

The purpose of this report is to summarize the analysis results on the 170 ft Monopole to support the proposed antennas and transmissions lines in addition to those currently installed.

Table 1 List of Documents Used

Item	Document
Tower design/drawings	Sabre Towers & Poles, Job# 42498, Dated 04/06/2011
Foundation drawings	Sabre Towers & Poles, Job# 42498, Dated 04/06/2011
Geotechnical report	Tower Engineering Professionals, Project #: 103196.01, Dated 03/18/2011.
Modification drawings	N/A
Carrier MA	Colliers Engineering & Design, Project # 21781129 (Rev. 3), Dated 10/11/2023
Latest SA	SBAE, Project # CT11794-DW-082323, Dated 08/24/2023

Analysis Criteria

Table 2 Code Related Data

Jurisdiction (State/County/City)	Connecticut/NEW LONDON/Niantic
Governing Codes	ANSI/TIA/EIA 222-H, 2021 IBC / 2022 CSBC
Ultimate Wind Speed (3-Sec gust)	126.0 mph
Wind Speed with Ice (3-Sec gust)	50 mph
Service Wind Speed (3-Sec gust)	60 mph
Ice Thickness	1.00"
Risk Category	II
Exposure Category	C
Topographic Category	1
Crest Height	0 ft
Ground Elevation	13.5 ft.
Seismic Parameter S_s	0.195
Seismic Parameter S_1	0.053

This structural analysis is based upon the tower being classified as a risk category II; however, if a different classification is required subsequent to the date hereof, the tower classification will be changed to meet such requirement and a new structural analysis will be run.

Appurtenance Loading

Existing Loading:

Table 3 Existing Appurtenances

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	171.75	3	Ericsson AIR 6419 B77G - Panel	(3) Reinforced T-Arms	(1) 2" Conduit housing (1) 3/8" Fiber & (2) 0.64" Fiber (1) 1/2" Fiber (4) 0.64" DC Power (6) 1 5/8" (1) 1.5" Fiber	AT&T
2	170.0	6	Ericsson RRUS-12 RRU			
3		3	Ericsson RRUS-32 RRU			
4		6	Ericsson RRUS A2 RRU			
5		3	Raycap DC6-48-60-18-8F			
6		3	CCI DTMAPB7819VG12A TMA			
7		1	CCI TPA65R-BU4DA-K - Panel			
8		1	CCI TPA65R-BU6DA-K - Panel			
9		1	CCI TPA65R-BU8DA-K - Panel			
10		3	Ericsson 8843 B2 B66A RRU			
11		1	CCI OPA65R-BU4DA - Panel			
12		1	Commscope NNHH-65B-R4 - Panel			
13		1	Commscope OPA65R-BU8DA - Panel			
14		3	Ericsson RRUS 4478 B14 RRU			
15		3	Ericsson 4449 B5/B12 RRU			
16	168.75	3	Ericsson AIR 6449 B77D - Panel	(3) Modified T-Arm w/ Site Pro 1: PRK-1245L and PRK-SFS-L	(7) 1 5/8" (3) 1 5/8" Fiber (2) 1.9" Fiber	T-Mobile
17	160.0	3	Ericsson KRY 112 144/1 TMA			
18		3	Ericsson AIR 6419 B41 - Panel			
19		3	Commscope VV-65A-R1 - Panel			
20		3	RFS APXVAALL24_43-U-NA20 - Panel			
21		3	Ericsson 4449 B71 + B85 RRU			
22	3	Ericsson 4460 B25/B66A RRU				
23	147.0	3	Samsung MT6407-77A - Panel	Low Profile Platform Mofidied	(12) 1 5/8" (2) 1-1/4" Hybriflex	Verizon
24		3	Samsung RF4440d-13A			
25		1	Raycap 12 OVP			
27		6	JMA Wireless MX06FRO660-03 - Panel			
28		3	Samsung B2/B66A RRH ORAN (RF4439d-25A) RRU			
31	135.0	3	Commscope FFVV-65B-R2 - Panel	Platform w/HRK Commscope: MC-PK8-DSH	(1) 1.60" Hybrid	Dish Wireless
32		3	Samsung RF4450t-71A RRU			
33		3	Samsung RF4451d-70A RRU			
34		1	Raycap RDIDC-9181-PF-48			

Proposed Loading:

Information pertaining to proposed antennas and transmission lines were based upon the Application #: 243517, v1 from Verizon and is listed in Table 4.

Table 4 Proposed Appurtenances

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
26	147.0	3	Samsung MT6413-77A - Panel	Low Profile Platform Mofidied	(2) 1-1/4" Hybriflex (12) 1 5/8"	Verizon
27		6	JMA Wireless MX06FRO660-03 - Panel			
28		3	Samsung B2/B66A RRH ORAN (RF4439d-25A) RRU			
29		3	Samsung RF4461d-13A RRU			
30		1	Raycap RVZDC-6627-PF-48 OVP			



Analysis Results

Tower

The results of the structural analysis are shown below in table 5. Additional information for the tower analysis is provided within the Appendix.

Table 5 Tower Analysis Summary

	Pole shafts	Anchor Bolts	Base Plate
Max. Usage:	82.8%	81.1%	48.8%
Pass/Fail	Pass	Pass	Pass

Foundation

The results of the foundation analysis are shown below in table 6. Additional information for the foundation analysis is provided within the Appendix.

Table 6 Foundation Analysis Summary

Structural Component	Max Usage (%)	Analysis Result
Foundation	93.0%	Pass



Conclusions

Based on the analysis results, the existing tower and foundation were found to be **sufficient** to safely support the equipment listed in this analysis. No modification to the tower and foundation is needed at this time.

Installation Requirements

This analysis was performed under the assumption that the carrier will place the proposed equipment and feed lines at the installation height listed in Table 4 and in accordance with the coax layout shown. TMAs and RRUs are to be installed on existing mounts behind tenant's antennas unless otherwise noted. No equipment is to be installed directly in the climbing path. All equipment is to be installed per mount manufacturer specifications. In case site conditions do not allow for the required installation parameters to be met the carrier must notify SBA Communications Corporation engineers for approval of an alternative placement.

Assumptions and Limitations

Assumptions

This analysis was completed based on the following assumptions:

- Tower and foundation were built in accordance to manufacturer specifications.
- Tower and foundation has been properly maintained in accordance with the manufacturer's specifications
- All existing structural members were assumed to be in good condition with no physical damage or deterioration associated with corrosion
- Welds and bolts are assumed able to carry their intended original design loads.
- The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Table 3 and 4.
- This analysis may be affected if any assumptions are not valid or have been made in error. SBA should be notified to determine the effect on the structural integrity of the tower.

Limitations

The computer generated analysis performed by the tower software is limited to theoretical capacities of the towers structural members and does not account for any missing or damaged members or connections. The tower and foundation are assumed to have been properly designed, fabricated, installed and maintained, barring any conflicting findings from the most recent inspection.

SBA Communications Corporation has used its due diligence to verify the information provided to perform this analysis. It is unreasonable to perform a more detailed inspection of a tower and its components. This report is not a condition assessment of the tower or foundation.

Appendix

Usage Diagram - Max Ratio 82.83% at 0.0ft

Structure: CT11794-S
Site Name: East Lyme 1
Height: 169.00 (ft)
Base Elev: 1.000 (ft)

Code: EIA/TIA-222-H
Exposure: C
Gh: 1.1

1/11/2024



Page: 1


Dead Load Factor: 1.20
Wind Load Factor: 1.00

Load Case : 1.2D + 1.0W 126 mph Wind



Iterations: 26

Copyright © 2024 by Tower Engineering Solutions, LLC. All rights reserved.



Structure: CT11794-S

Type: Tapered
Site Name: East Lyme 1
Height: 169.00 (ft)
Base Elev: 1.00 (ft)

Base Shape: 18 Sided
Taper: 0.27302

1/11/2024




Page: 2

Shaft Properties

Seq	Length (ft)	Top (in)	Bottom (in)	Thick (in)	Joint Type	Taper	Grade (ksi)
1	53.25	45.60	60.14	0.438		0.27302	65
2	53.50	33.71	48.32	0.438	Slip	0.27302	65
3	53.50	21.22	35.83	0.375	Slip	0.27302	65
4	23.75	16.00	22.48	0.188	Slip	0.27302	65

Discrete Appurtenances

Attach Elev (ft)	Force Elev (ft)	Qty	Description	Carrier
169.00	169.00	6	Ericsson RRUS-12 RRU	AT&T
169.00	169.00	3	Ericsson RRUS 32 RRU	AT&T
169.00	169.00	6	Ericsson RRUS A2 RRU	AT&T
169.00	169.00	3	Raycap DC6-48-60-18-8F	AT&T
169.00	169.00	3	Reinforced T-Arms	AT&T
169.00	169.00	3	CCI DTMAPB7819VG12A	AT&T
169.00	167.75	3	Ericsson AIR 6449 B77D	AT&T
169.00	170.75	3	Ericsson AIR 6419 B77G	AT&T
169.00	169.00	1	CCI TPA65R-BU4DA-K	AT&T
169.00	169.00	1	CCI TPA65R-BU6DA-K	AT&T
169.00	169.00	1	CCI TPA65R-BU8DA-K	AT&T
169.00	169.00	3	Ericsson 8843 B2 B66A	AT&T
169.00	169.00	1	CCI OPA65R-BU4DA	AT&T
169.00	169.00	1	Commscope	AT&T
169.00	169.00	1	Commscope	AT&T
169.00	169.00	3	Ericsson RRUS 4478 B14	AT&T
169.00	169.00	3	Ericsson 4449 B5/B12	AT&T
169.00	169.00	12	mount pipe	T-Mobile
159.00	159.00	12	mount pipe	T-Mobile
159.00	159.00	3	Ericsson KRY 112 144/1	T-Mobile
159.00	159.00	1	PRK-1245L	T-Mobile
159.00	159.00	1	PRK-SFS-L	T-Mobile
159.00	159.00	3	T-Arm	T-Mobile
159.00	159.00	3	Ericsson AIR 6419 B41	T-Mobile
159.00	159.00	3	Commscope VV-65A-R1	T-Mobile
159.00	159.00	3	RFS	T-Mobile
159.00	159.00	3	Ericsson 4449 B71 + B85	T-Mobile
159.00	159.00	3	Ericsson 4460 B25/B66A	T-Mobile
146.00	146.00	6	JMA Wireless	Verizon
146.00	146.00	3	Samsung B2/B66A RRH	Verizon
146.00	146.00	1	Mods	Verizon
146.00	146.00	1	Low Profile Platform	Verizon
146.00	146.00	12	mount pipe	Verizon
146.00	146.00	3	Samsung MT6413-77A	Verizon
146.00	146.00	3	Samsung RF4461d-13A	Verizon
146.00	146.00	1	Raycap	Verizon
146.00	146.00	3	Antenna Bracket JWA	Verizon
134.00	134.00	3	Commscope	Dish Wireless
134.00	134.00	3	Samsung RF4450t-71A	Dish Wireless
134.00	134.00	3	Samsung RF4451d-70A	Dish Wireless
134.00	134.00	1	Raycap	Dish Wireless
134.00	134.00	1	Platform w/HRK	Dish Wireless



Linear Appurtenances

Elev From (ft)	Elev To (ft)	Placement	Description	Carrier
169.00	169.00		Ericsson RRUS-12 RRU	AT&T
169.00	169.00		Ericsson RRUS 32 RRU	AT&T
169.00	169.00		Ericsson RRUS A2 RRU	AT&T
169.00	169.00		Raycap DC6-48-60-18-8F	AT&T
169.00	169.00		Reinforced T-Arms	AT&T
169.00	169.00		CCI DTMAPB7819VG12A	AT&T
169.00	167.75		Ericsson AIR 6449 B77D	AT&T
169.00	170.75		Ericsson AIR 6419 B77G	AT&T
169.00	169.00		CCI TPA65R-BU4DA-K	AT&T
169.00	169.00		CCI TPA65R-BU6DA-K	AT&T
169.00	169.00		CCI TPA65R-BU8DA-K	AT&T
169.00	169.00		Ericsson 8843 B2 B66A	AT&T
169.00	169.00		CCI OPA65R-BU4DA	AT&T
169.00	169.00		Commscope	AT&T
169.00	169.00		Commscope	AT&T
169.00	169.00		Ericsson RRUS 4478 B14	AT&T
169.00	169.00		Ericsson 4449 B5/B12	AT&T
169.00	169.00		mount pipe	T-Mobile
159.00	159.00		mount pipe	T-Mobile
159.00	159.00		Ericsson KRY 112 144/1	T-Mobile
159.00	159.00		PRK-1245L	T-Mobile
159.00	159.00		PRK-SFS-L	T-Mobile
159.00	159.00		T-Arm	T-Mobile
159.00	159.00		Ericsson AIR 6419 B41	T-Mobile
159.00	159.00		Commscope VV-65A-R1	T-Mobile
159.00	159.00		RFS	T-Mobile
159.00	159.00		Ericsson 4449 B71 + B85	T-Mobile
159.00	159.00		Ericsson 4460 B25/B66A	T-Mobile
146.00	146.00		JMA Wireless	Verizon
146.00	146.00		Samsung B2/B66A RRH	Verizon
146.00	146.00		Mods	Verizon
146.00	146.00		Low Profile Platform	Verizon
146.00	146.00		mount pipe	Verizon
146.00	146.00		Samsung MT6413-77A	Verizon
146.00	146.00		Samsung RF4461d-13A	Verizon
146.00	146.00		Raycap	Verizon
146.00	146.00		Antenna Bracket JWA	Verizon
134.00	134.00		Commscope	Dish Wireless
134.00	134.00		Samsung RF4450t-71A	Dish Wireless
134.00	134.00		Samsung RF4451d-70A	Dish Wireless
134.00	134.00		Raycap	Dish Wireless
134.00	134.00		Platform w/HRK	Dish Wireless

Structure: CT11794-S

Type: Tapered	Base Shape: 18 Sided	1/11/2024
Site Name: East Lyme 1	Taper: 0.27302	
Height: 169.00 (ft)		Page: 3
Base Elev: 1.00 (ft)		



0.00	169.00	Inside	0.64" DC Power	AT&T
0.00	169.00	Inside	0.64" Fiber	AT&T
0.00	169.00	Inside	1 5/8" Coax	AT&T
0.00	169.00	Inside	1.5" Fiber	AT&T
0.00	169.00	Inside	1/2" Fiber	AT&T
0.00	169.00	Inside	2" Conduit	AT&T
0.00	169.00	Inside	3/8" Fiber	AT&T
0.00	169.00	Outside	Safety Cable	
0.00	169.00	Outside	Step bolts	
0.00	159.00	Inside	1 5/8" Coax	T-Mobile
0.00	159.00	Inside	1 5/8" Fiber	T-Mobile
0.00	159.00	Inside	1.9" Fiber	T-Mobile
0.00	146.00	Inside	1 5/8" Coax	Verizon
0.00	146.00	Inside	1-1/4" Hybriflex	Verizon
0.00	134.00	Inside	1.60" Hybrid	Dish Wireless

Anchor Bolts

Qty	Specifications	Grade (ksi)	Arrangement
20	2.25" 18J	75.0	Radial

Base Plate

Thickness (in)	Specifications (in)	Grade (ksi)	Geometry
2.7500	72.8	50.0	Round

Reactions

Load Case	Moment (FT-Kips)	Shear (Kips)	Axial (Kips)
1.2D + 1.0W 126 mph Wind	5582.2	43.5	60.4
0.9D + 1.0W 126 mph Wind	5498.2	43.5	45.3
1.2D + 1.0Di + 1.0Wi 50 mph Wind	1246.1	10.3	62.2
1.2D + 1.0Ev + 1.0Eh	120.6	0.8	62.7
0.9D + 1.0Ev + 1.0Eh	119.2	0.8	47.4
1.0D + 1.0W 60 mph Wind	1125.1	8.8	50.4


Structure: CT11794-S - Coax Line Placement

Type: Monopole
Site Name: East Lyme 1
Height: 169.00 (ft)

1/11/2024



Page: 4



Shaft Properties

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 5

Sec. No.	Shape	Length (ft)	Thick (in)	Fy (ksl)	Joint Type	Overlap (in)	Weight (lb)
1	18	53.250	0.4375	65		0.00	13,193
2	18	53.500	0.4375	65	Slip	81.00	10,258
3	18	53.500	0.3750	65	Slip	60.00	6,099
4	18	23.750	0.1875	65	Slip	39.00	916
Total Shaft Weight:							30,466

Bottom

Top

Sec. No.	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Taper
1	60.14	0.00	82.90	37333.61	22.83	137.46	45.60	53.25	62.71	16162.5	16.97	104.2	0.273018
2	48.32	46.50	66.49	19259.46	18.06	110.44	33.71	100.00	46.21	6464.05	12.18	77.06	0.273018
3	35.83	95.00	42.20	6701.10	15.44	95.54	21.22	148.50	24.81	1362.38	8.57	56.59	0.273018
4	22.48	145.2	13.27	833.42	19.73	119.92	16.00	169.00	9.41	297.27	13.64	85.33	0.273018

Load Summary

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
1	169.00	Ericsson RRUS-12 RRU	6	58.00	3.15	0.67	117.87	3.618	0.67	0.00	0.00
2	169.00	Ericsson RRUS 32 RRU	3	77.00	3.87	0.67	148.61	3.836	0.67	0.00	0.00
3	169.00	Ericsson RRUS A2 RRU	6	22.00	1.86	0.67	47.30	2.517	0.67	0.00	0.00
4	169.00	Raycap DC6-48-60-18-8F	3	32.80	1.47	0.67	74.53	1.942	0.67	0.00	0.00
5	169.00	Reinforced T-Arms	3	450.00	14.00	1.00	662.06	22.247	1.00	0.00	0.00
6	169.00	CCI DTMAP7819VG12A TMA	3	19.18	1.14	0.67	36.39	1.659	0.67	0.00	0.00
7	169.00	Ericsson AIR 6449 B77D	3	88.00	4.13	0.85	175.35	4.697	0.85	0.00	-1.25
8	169.00	Ericsson AIR 6419 B77G	3	66.10	3.80	0.76	131.05	4.337	0.76	0.00	1.75
9	169.00	CCI TPA65R-BU4DA-K	1	67.50	12.87	0.72	269.05	13.865	0.72	0.00	0.00
10	169.00	CCI TPA65R-BU6DA-K	1	67.50	12.87	0.72	269.05	13.865	0.72	0.00	0.00
11	169.00	CCI TPA65R-BU8DA-K	1	82.50	17.87	0.72	350.22	19.083	0.72	0.00	0.00
12	169.00	Ericsson 8843 B2 B66A RRU	3	72.00	1.64	0.67	103.62	1.975	0.67	0.00	0.00
13	169.00	CCI OPA65R-BU4DA	1	43.00	4.96	0.94	138.89	5.605	0.94	0.00	0.00
14	169.00	Commscope NNHH-65B-R4	1	79.00	12.27	1.00	259.63	13.253	1.00	0.00	0.00
15	169.00	Commscope OPA65R-BU8DA	1	79.00	17.87	1.00	322.17	19.083	1.00	0.00	0.00
16	169.00	Ericsson RRUS 4478 B14 RRU	3	59.40	1.65	0.67	87.39	2.000	0.67	0.00	0.00
17	169.00	Ericsson 4449 B5/B12 RRU	3	71.00	1.97	0.67	107.04	2.340	0.67	0.00	0.00
18	169.00	mount pipe	12	30.00	1.36	1.00	44.14	2.161	1.00	0.00	0.00
19	159.00	mount pipe	12	30.00	1.38	1.00	44.05	2.188	1.00	0.00	0.00
20	159.00	Ericsson KRY 112 144/1 TMA	3	11.00	0.41	0.70	18.23	0.729	0.70	0.00	0.00
21	159.00	PRK-1245L	1	464.91	9.50	1.00	682.68	16.175	1.00	0.00	0.00
22	159.00	PRK-SFS-L	1	394.00	16.60	1.00	879.74	24.764	1.00	0.00	0.00
23	159.00	T-Arm	3	400.00	8.00	1.00	587.36	12.684	1.00	0.00	0.00
24	159.00	Ericsson AIR 6419 B41	3	133.20	6.53	0.70	237.07	7.239	0.70	0.00	0.00
25	159.00	Commscope VV-65A-R1	3	29.50	7.90	0.74	138.13	8.740	0.74	0.00	0.00
26	159.00	RFS APXVAALL24_43-U-NA20	3	122.80	20.24	0.73	398.08	21.499	0.73	0.00	0.00
27	159.00	Ericsson 4449 B71 + B85 RRU	3	73.20	1.97	0.67	111.94	2.352	0.67	0.00	0.00
28	159.00	Ericsson 4460 B25/B66A RRU	3	72.00	1.64	0.67	103.43	1.973	0.67	0.00	0.00
29	146.00	JMA Wireless MX06FRO660-03	6	60.00	9.87	0.87	226.48	10.759	0.88	0.00	0.00
30	146.00	Samsung B2/B66A RRR ORAN	3	74.71	1.87	0.84	108.33	2.231	0.85	0.00	0.00
31	146.00	Mods	1	465.04	13.79	1.00	789.02	20.195	1.00	0.00	0.00
32	146.00	Low Profile Platform	1	1250.00	14.69	1.00	1975.71	22.877	1.00	0.00	0.00
33	146.00	mount pipe	12	30.00	1.47	1.00	47.42	2.289	1.00	0.00	0.00
34	146.00	Samsung MT6413-77A	3	57.30	3.79	0.69	119.24	4.323	0.71	0.00	0.00
35	146.00	Samsung RF4461d-13A RRU	3	72.50	1.87	0.67	133.28	2.537	0.67	0.00	0.00
36	146.00	Raycap RVZDC-6627-PF-48 OVP	1	32.00	4.06	1.00	108.32	4.741	1.00	0.00	0.00
37	146.00	Antenna Bracket JWA Wireless:	3	28.00	0.00	1.00	44.26	0.000	1.00	0.00	0.00
38	134.00	Commscope FV-65B-R2	3	70.80	12.27	0.73	246.89	13.229	0.75	0.00	0.00
39	134.00	Samsung RF4450t-71A RRU	3	94.58	2.06	0.67	158.34	2.658	0.67	0.00	0.00
40	134.00	Samsung RF4451d-70A RRU	3	61.30	1.88	0.67	102.63	2.425	0.67	0.00	0.00
41	134.00	Raycap RDIDC-9181-PF-48	1	21.85	2.01	1.00	49.87	2.641	1.00	0.00	0.00
42	134.00	Platform w/HRK Commscope:	1	1736.00	34.19	1.00	3238.97	53.871	1.00	0.00	0.00
Totals:			136	13,411.41			25,410.25				

Linear Appurtenances

Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
Bottom Elev. (ft)	Top Elev. (ft)	Description		Exposed Width	Exposed						
0.00	169.00	(4) 0.64" DC Power		0.00	Inside						
0.00	169.00	(2) 0.64" Fiber		0.00	Inside						
0.00	169.00	(6) 1 5/8" Coax		0.00	Inside						
0.00	169.00	(1) 1.5" Fiber		0.00	Inside						
0.00	169.00	(1) 1/2" Fiber		0.00	Inside						
0.00	169.00	(1) 2" Conduit		0.00	Inside						
0.00	169.00	(1) 3/8" Fiber		0.00	Inside						
0.00	169.00	(1) Safety Cable		0.38	Outside						
0.00	169.00	(1) Step bolts		0.63	Outside						
0.00	159.00	(7) 1 5/8" Coax		0.00	Inside						
0.00	159.00	(3) 1 5/8" Fiber		0.00	Inside						
0.00	159.00	(2) 1.9" Fiber		0.00	Inside						
0.00	146.00	(12) 1 5/8" Coax		0.00	Inside						
0.00	146.00	(2) 1-1/4" Hybriflex		0.00	Inside						
0.00	134.00	(1) 1.60" Hybrid		0.00	Inside						

Shaft Section Properties

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 8

Increment Length: 5 (ft)

Elev (ft)	Description	Thick (in)	Dia (in)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	Fpy (ksi)	S (in ³)	Weight (lb)
0.00		0.4375	60.140	82.901	37333.6	22.83	137.46	74.6	1222.	0.0
5.00		0.4375	58.775	81.006	34830.8	22.28	134.34	75.2	1167.	1394.4
10.00		0.4375	57.410	79.110	32442.5	21.73	131.22	75.8	1113.	1362.1
15.00		0.4375	56.045	77.215	30165.9	21.18	128.10	76.5	1060.	1329.8
20.00		0.4375	54.680	75.319	27998.4	20.63	124.98	77.1	1008.	1297.6
25.00		0.4375	53.315	73.424	25937.3	20.08	121.86	77.8	958.2	1265.3
30.00		0.4375	51.949	71.528	23979.9	19.53	118.74	78.4	909.2	1233.1
35.00		0.4375	50.584	69.633	22123.5	18.98	115.62	79.1	861.4	1200.8
40.00		0.4375	49.219	67.737	20365.5	18.43	112.50	79.7	815.0	1168.6
45.00		0.4375	47.854	65.842	18703.2	17.88	109.38	80.4	769.8	1136.3
46.50	Bot - Section 2	0.4375	47.445	65.273	18222.8	17.71	108.44	80.6	756.5	334.6
50.00		0.4375	46.489	63.946	17133.9	17.33	106.26	81.0	725.9	1553.4
53.25	Top - Section 1	0.4375	46.477	63.929	17120.2	17.32	106.23	0.0	0.0	1414.2
55.00		0.4375	45.999	63.266	16592.7	17.13	105.14	81.3	710.5	378.7
60.00		0.4375	44.634	61.370	15145.5	16.58	102.02	81.9	668.3	1060.3
65.00		0.4375	43.269	59.475	13785.0	16.03	98.90	82.5	627.5	1028.0
70.00		0.4375	41.904	57.579	12508.5	15.48	95.78	82.5	587.9	995.8
75.00		0.4375	40.539	55.683	11313.4	14.93	92.66	82.5	549.7	963.5
80.00		0.4375	39.174	53.788	10196.9	14.38	89.54	82.5	512.7	931.3
85.00		0.4375	37.808	51.892	9156.4	13.83	86.42	82.5	477.0	899.0
90.00		0.4375	36.443	49.997	8189.2	13.28	83.30	82.5	442.6	866.8
95.00	Bot - Section 3	0.4375	35.078	48.101	7292.7	12.73	80.18	82.5	409.5	834.5
100.00	Top - Section 2	0.3750	34.463	40.572	5956.5	14.79	91.90	0.0	0.0	1506.4
105.00		0.3750	33.098	38.947	5269.1	14.15	88.26	82.5	313.6	676.5
110.00		0.3750	31.733	37.323	4636.8	13.51	84.62	82.5	287.8	648.8
115.00		0.3750	30.368	35.698	4057.3	12.87	80.98	82.5	263.1	621.2
120.00		0.3750	29.003	34.073	3528.1	12.23	77.34	82.5	239.6	593.5
125.00		0.3750	27.638	32.448	3047.1	11.58	73.70	82.5	217.2	565.9
130.00		0.3750	26.273	30.824	2611.9	10.94	70.06	82.5	195.8	538.3
134.00		0.3750	25.181	29.524	2295.2	10.43	67.15	82.5	179.5	410.7
135.00		0.3750	24.908	29.199	2220.3	10.30	66.42	82.5	175.6	99.9
140.00		0.3750	23.543	27.574	1869.9	9.66	62.78	82.5	156.4	483.0
145.00		0.3750	22.177	25.949	1558.4	9.02	59.14	82.5	138.4	455.3
145.25	Bot - Section 4	0.3750	22.109	25.868	1543.8	8.99	58.96	82.5	137.5	22.0
146.00		0.3750	21.904	25.624	1500.6	8.89	58.41	82.5	134.9	99.4
148.50	Top - Section 3	0.1875	21.597	12.741	737.8	18.90	115.18	0.0	0.0	324.6
150.00		0.1875	21.187	12.497	696.3	18.51	113.00	79.6	64.7	64.4
155.00		0.1875	19.822	11.685	569.1	17.23	105.72	81.1	56.6	205.7
159.00		0.1875	18.730	11.035	479.4	16.20	99.89	82.3	50.4	154.6
160.00		0.1875	18.457	10.872	458.5	15.95	98.44	82.5	48.9	37.3
165.00		0.1875	17.092	10.060	363.2	14.66	91.16	82.5	41.9	178.1
169.00		0.1875	16.000	9.410	297.3	13.64	85.33	82.5	36.6	132.5

30466.3

Wind Loading - Shaft

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 9



Load Case: 1.2D + 1.0W 126 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.00



Iterations 26

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.85	32.803	36.08	591.02	0.730	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	32.803	36.08	577.61	0.730	0.000	5.00	25.156	18.36	662.6	0.0	1673.2
10.00		1.00	0.85	32.803	36.08	564.19	0.730	0.000	5.00	24.579	17.94	647.4	0.0	1634.5
15.00		1.00	0.86	33.208	36.53	554.17	0.730	0.000	5.00	24.001	17.52	640.0	0.0	1595.8
20.00		1.00	0.91	35.165	38.68	556.37	0.730	0.000	5.00	23.423	17.10	661.4	0.0	1557.1
25.00		1.00	0.95	36.782	40.46	554.81	0.730	0.000	5.00	22.846	16.68	674.8	0.0	1518.4
30.00		1.00	0.99	38.169	41.99	550.71	0.730	0.000	5.00	22.268	16.26	682.5	0.0	1479.7
35.00		1.00	1.02	39.390	43.33	544.75	0.730	0.000	5.00	21.691	15.83	686.1	0.0	1441.0
40.00		1.00	1.05	40.483	44.53	537.35	0.730	0.000	5.00	21.113	15.41	686.3	0.0	1402.3
45.00		1.00	1.07	41.476	45.62	528.82	0.730	0.000	5.00	20.536	14.99	683.9	0.0	1363.6
46.50 Bot - Section 2		1.00	1.08	41.757	45.93	526.06	0.730	0.000	1.50	6.048	4.42	202.8	0.0	401.5
50.00		1.00	1.10	42.387	46.63	519.34	0.730	0.000	3.50	14.169	10.34	482.3	0.0	1864.1
53.25 Top - Section 1		1.00	1.11	42.942	47.24	512.75	0.730	0.000	3.25	12.904	9.42	444.9	0.0	1697.0
55.00		1.00	1.12	43.230	47.55	518.95	0.730	0.000	1.75	6.847	5.00	237.7	0.0	454.5
60.00		1.00	1.14	44.015	48.42	508.10	0.730	0.000	5.00	19.173	14.00	677.7	0.0	1272.3
65.00		1.00	1.16	44.751	49.23	496.66	0.730	0.000	5.00	18.596	13.57	668.2	0.0	1233.6
70.00		1.00	1.18	45.444	49.99	484.71	0.730	0.000	5.00	18.018	13.15	657.5	0.0	1194.9
75.00		1.00	1.19	46.100	50.71	472.29	0.730	0.000	5.00	17.440	12.73	645.6	0.0	1156.2
80.00		1.00	1.21	46.723	51.40	459.46	0.730	0.000	5.00	16.863	12.31	632.7	0.0	1117.5
85.00		1.00	1.23	47.316	52.05	446.25	0.730	0.000	5.00	16.285	11.89	618.8	0.0	1078.8
90.00		1.00	1.24	47.882	52.67	432.70	0.730	0.000	5.00	15.708	11.47	604.0	0.0	1040.1
95.00 Bot - Section 3		1.00	1.25	48.424	53.27	418.85	0.730	0.000	5.00	15.130	11.05	588.3	0.0	1001.4
100.00 Top - Section 2		1.00	1.27	48.945	53.84	404.70	0.730	0.000	5.00	14.870	10.86	584.4	0.0	1807.7
105.00		1.00	1.28	49.445	54.39	399.35	0.730	0.000	5.00	14.292	10.43	567.5	0.0	811.8
110.00		1.00	1.29	49.927	54.92	384.74	0.730	0.000	5.00	13.715	10.01	549.8	0.0	778.6
115.00		1.00	1.31	50.392	55.43	369.90	0.730	0.000	5.00	13.137	9.59	531.6	0.0	745.4
120.00		1.00	1.32	50.842	55.93	354.84	0.730	0.000	5.00	12.560	9.17	512.8	0.0	712.2
125.00		1.00	1.33	51.277	56.41	339.59	0.730	0.000	5.00	11.982	8.75	493.4	0.0	679.1
130.00		1.00	1.34	51.699	56.87	324.14	0.730	0.000	5.00	11.405	8.33	473.5	0.0	645.9
134.00 Appurtenance(s)		1.00	1.35	52.028	57.23	311.65	0.730	0.000	4.00	8.708	6.36	363.8	0.0	492.8
135.00		1.00	1.35	52.109	57.32	308.51	0.730	0.000	1.00	2.119	1.55	88.7	0.0	119.9
140.00		1.00	1.36	52.506	57.76	292.71	0.730	0.000	5.00	10.249	7.48	432.1	0.0	579.6
145.00		1.00	1.37	52.893	58.18	276.75	0.730	0.000	5.00	9.672	7.06	410.8	0.0	546.4
145.25 Bot - Section 4		1.00	1.37	52.912	58.20	275.95	0.730	0.000	0.25	0.468	0.34	19.9	0.0	26.4
146.00 Appurtenance(s)		1.00	1.37	52.969	58.27	273.54	0.730	0.000	0.75	1.420	1.04	60.4	0.0	119.3
148.50 Top - Section 3		1.00	1.38	53.157	58.47	265.49	0.730	0.000	2.50	4.641	3.39	198.1	0.0	389.6
150.00		1.00	1.38	53.269	58.60	265.34	0.730	0.000	1.50	2.715	1.98	116.1	0.0	77.3
155.00		1.00	1.39	53.636	59.00	249.09	0.730	0.000	5.00	8.675	6.33	373.6	0.0	246.9
159.00 Appurtenance(s)		1.00	1.40	53.922	59.31	236.00	0.730	0.000	4.00	6.525	4.76	282.5	0.0	185.5
160.00		1.00	1.40	53.993	59.39	232.71	0.730	0.000	1.00	1.573	1.15	68.2	0.0	44.7
165.00		1.00	1.41	54.342	59.78	216.20	0.730	0.000	5.00	7.520	5.49	328.2	0.0	213.7
169.00 Appurtenance(s)		1.00	1.42	54.615	60.08	202.89	0.730	0.000	4.00	5.600	4.09	245.6	0.0	159.0
Totals:									169.00			19,186.6		36,559.6

Discrete Appurtenance Forces

Structure: CT11794-S

Code: TIA-222-H

1/11/2024

Site Name: East Lyme 1

Exposure: C

Height: 169.00 (ft)

Crest Height: 0.00

Base Elev: 1.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 10



Load Case: 1.2D + 1.0W 126 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.00



Iterations 26

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	Orient Factor x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)	
1	169.00	Ericsson RRUS A2 RRU	6	54.615	60.076	0.50	0.75	5.61	158.40	0.000	0.000	336.90	0.00	0.00	
2	169.00	Ericsson AIR 6449 B77D	3	54.530	59.983	0.64	0.75	7.90	316.80	0.000	-1.250	473.78	0.00	-592.23	
3	169.00	Ericsson AIR 6419 B77G	3	54.733	60.206	0.57	0.75	6.50	237.96	0.000	1.750	391.22	0.00	684.63	
4	169.00	CCI TPA65R-BU4DA-K	1	54.615	60.076	0.54	0.75	6.95	81.00	0.000	0.000	417.52	0.00	0.00	
5	169.00	CCI TPA65R-BU6DA-K	1	54.615	60.076	0.54	0.75	6.95	81.00	0.000	0.000	417.52	0.00	0.00	
6	169.00	CCI TPA65R-BU8DA-K	1	54.615	60.076	0.54	0.75	9.65	99.00	0.000	0.000	579.72	0.00	0.00	
7	169.00	Ericsson 8843 B2 B66A	3	54.615	60.076	0.50	0.75	2.47	259.20	0.000	0.000	148.53	0.00	0.00	
8	169.00	Ericsson RRUS-12 RRU	6	54.615	60.076	0.50	0.75	9.50	417.60	0.000	0.000	570.56	0.00	0.00	
9	169.00	Ericsson RRUS 32 RRU	3	54.615	60.076	0.50	0.75	5.83	277.20	0.000	0.000	350.49	0.00	0.00	
10	169.00	mount pipe	12	54.615	60.076	0.75	0.75	12.24	432.00	0.000	0.000	735.33	0.00	0.00	
11	169.00	Ericsson 4449 B5/B12	3	54.615	60.076	0.50	0.75	2.97	255.60	0.000	0.000	178.41	0.00	0.00	
12	169.00	Commscope	1	54.615	60.076	0.75	0.75	13.40	94.80	0.000	0.000	805.17	0.00	0.00	
13	169.00	Commscope	1	54.615	60.076	0.75	0.75	9.20	94.80	0.000	0.000	552.85	0.00	0.00	
14	169.00	CCI OPA65R-BU4DA	1	54.615	60.076	0.70	0.75	3.50	51.60	0.000	0.000	210.08	0.00	0.00	
15	169.00	Raycap DC6-48-60-18-8F	3	54.615	60.076	0.50	0.75	2.22	118.08	0.000	0.000	133.13	0.00	0.00	
16	169.00	Ericsson RRUS 4478 B14	3	54.615	60.076	0.54	0.80	2.65	213.84	0.000	0.000	159.39	0.00	0.00	
17	169.00	CCI DTMAPB7819VG12A	3	54.615	60.076	0.50	0.75	1.72	69.05	0.000	0.000	103.24	0.00	0.00	
18	169.00	Reinforced T-Arms	3	54.615	60.076	0.75	0.75	31.50	1620.00	0.000	0.000	1892.41	0.00	0.00	
19	159.00	Ericsson 4460 B25/B66A	3	53.922	59.314	0.54	0.80	2.64	259.20	0.000	0.000	156.42	0.00	0.00	
20	159.00	Ericsson 4449 B71 + B85	3	53.922	59.314	0.54	0.80	3.17	263.52	0.000	0.000	187.89	0.00	0.00	
21	159.00	RFS	3	53.922	59.314	0.58	0.80	35.46	442.08	0.000	0.000	2103.32	0.00	0.00	
22	159.00	Commscope VV-65A-R1	3	53.922	59.314	0.59	0.80	14.03	106.20	0.000	0.000	832.21	0.00	0.00	
23	159.00	T-Arm	3	53.922	59.314	0.75	0.75	18.00	1440.00	0.000	0.000	1067.66	0.00	0.00	
24	159.00	PRK-SFS-L	1	53.922	59.314	1.00	1.00	16.60	472.80	0.000	0.000	984.62	0.00	0.00	
25	159.00	PRK-1245L	1	53.922	59.314	1.00	1.00	9.50	557.89	0.000	0.000	563.49	0.00	0.00	
26	159.00	Ericsson KRY 112 144/1	3	53.922	59.314	0.52	0.75	0.65	39.60	0.000	0.000	38.30	0.00	0.00	
27	159.00	mount pipe	12	53.922	59.314	0.75	0.75	12.42	432.00	0.000	0.000	736.69	0.00	0.00	
28	159.00	Ericsson AIR 6419 B41	3	53.922	59.314	0.56	0.80	10.97	479.52	0.000	0.000	650.70	0.00	0.00	
29	146.00	JMA Wireless	6	52.969	58.266	0.65	0.75	38.64	432.00	0.000	0.000	2251.45	0.00	0.00	
30	146.00	mount pipe	12	52.969	58.266	0.75	0.75	13.23	432.00	0.000	0.000	770.85	0.00	0.00	
31	146.00	Samsung B2/B66A RRH	3	52.969	58.266	0.63	0.75	3.53	268.96	0.000	0.000	205.93	0.00	0.00	
32	146.00	Mods	1	52.969	58.266	1.00	1.00	13.79	558.05	0.000	0.000	803.48	0.00	0.00	
33	146.00	Samsung RF4461d-13A	3	52.969	58.266	0.50	0.75	2.82	261.00	0.000	0.000	164.25	0.00	0.00	
34	146.00	Samsung MT6413-77A	3	52.969	58.266	0.52	0.75	5.88	206.28	0.000	0.000	342.83	0.00	0.00	
35	146.00	Raycap	1	52.969	58.266	0.75	0.75	3.04	38.40	0.000	0.000	177.42	0.00	0.00	
36	146.00	Antenna Bracket JWA	3	52.969	58.266	1.00	1.00	0.00	100.80	0.000	0.000	0.00	0.00	0.00	
37	146.00	Low Profile Platform	1	52.969	58.266	1.00	1.00	14.69	1500.00	0.000	0.000	855.92	0.00	0.00	
38	134.00	Platform w/HRK	1	52.028	57.230	0.67	0.67	22.91	2083.20	0.000	0.000	1310.99	0.00	0.00	
39	134.00	Raycap	1	52.028	57.230	0.75	0.75	1.51	26.22	0.000	0.000	86.27	0.00	0.00	
40	134.00	Samsung RF4451d-70A	3	52.028	57.230	0.50	0.75	2.83	220.68	0.000	0.000	162.20	0.00	0.00	
41	134.00	Samsung RF4450t-71A	3	52.028	57.230	0.50	0.75	3.11	340.49	0.000	0.000	177.73	0.00	0.00	
42	134.00	Commscope	3	52.028	57.230	0.55	0.75	20.15	254.88	0.000	0.000	1153.39	0.00	0.00	
Totals:								16,093.69							24,240.29

Total Applied Force Summary


Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 11

Load Case: 1.2D + 1.0W 126 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 26

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		662.63	1923.49	0.00	0.00
10.00		647.42	1884.79	0.00	0.00
15.00		640.01	1846.09	0.00	0.00
20.00		661.41	1807.38	0.00	0.00
25.00		674.77	1768.68	0.00	0.00
30.00		682.52	1729.98	0.00	0.00
35.00		686.08	1691.28	0.00	0.00
40.00		686.35	1652.58	0.00	0.00
45.00		683.94	1613.88	0.00	0.00
46.50		202.80	476.62	0.00	0.00
50.00		482.27	2039.31	0.00	0.00
53.25		444.95	1859.68	0.00	0.00
55.00		237.68	542.05	0.00	0.00
60.00		677.66	1522.59	0.00	0.00
65.00		668.24	1483.89	0.00	0.00
70.00		657.51	1445.19	0.00	0.00
75.00		645.62	1406.49	0.00	0.00
80.00		632.67	1367.79	0.00	0.00
85.00		618.75	1329.09	0.00	0.00
90.00		603.95	1290.39	0.00	0.00
95.00		588.33	1251.69	0.00	0.00
100.00		584.43	2057.92	0.00	0.00
105.00		567.47	1062.03	0.00	0.00
110.00		549.85	1028.85	0.00	0.00
115.00		531.60	995.68	0.00	0.00
120.00		512.77	962.51	0.00	0.00
125.00		493.37	929.34	0.00	0.00
130.00		473.46	896.17	0.00	0.00
134.00	(11) attachments	3254.38	3618.52	0.00	0.00
135.00		88.67	168.63	0.00	0.00
140.00		432.14	823.22	0.00	0.00
145.00		410.79	790.05	0.00	0.00
145.25		19.90	38.63	0.00	0.00
146.00	(33) attachments	5632.56	3953.33	0.00	0.00
148.50		198.10	468.24	0.00	0.00
150.00		116.15	124.49	0.00	0.00
155.00		373.65	404.19	0.00	0.00
159.00	(35) attachments	7603.81	4804.23	0.00	0.00
160.00		68.22	59.63	0.00	0.00
165.00		328.16	288.22	0.00	0.00
169.00	(57) attachments	8701.88	5096.56	0.00	92.40
	Totals:	43,426.92	60,503.37	0.00	92.40

Linear Appurtenance Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 12



Load Case: 1.2D + 1.0W 126 mph Wind	Iterations 26
Dead Load Factor 1.20	
Wind Load Factor 1.00	



Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.017	0.000	32.803	0.00	1.64
5.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.017	0.000	32.803	0.00	6.24
10.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.017	0.000	32.803	0.00	1.64
10.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.017	0.000	32.803	0.00	6.24
15.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	33.208	0.00	1.64
15.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	33.208	0.00	6.24
20.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	35.165	0.00	1.64
20.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	35.165	0.00	6.24
25.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	36.782	0.00	1.64
25.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	36.782	0.00	6.24
30.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.019	0.000	38.169	0.00	1.64
30.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.019	0.000	38.169	0.00	6.24
35.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.019	0.000	39.390	0.00	1.64
35.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.019	0.000	39.390	0.00	6.24
40.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.020	0.000	40.483	0.00	1.64
40.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.020	0.000	40.483	0.00	6.24
45.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.020	0.000	41.476	0.00	1.64
45.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.020	0.000	41.476	0.00	6.24
46.50	Safety Cable	Yes	1.50	0.000	0.38	0.05	0.00	0.021	0.000	41.757	0.00	0.49
46.50	Step bolts	Yes	1.50	0.000	0.63	0.08	0.00	0.021	0.000	41.757	0.00	1.87
50.00	Safety Cable	Yes	3.50	0.000	0.38	0.11	0.00	0.021	0.000	42.387	0.00	1.15
50.00	Step bolts	Yes	3.50	0.000	0.63	0.18	0.00	0.021	0.000	42.387	0.00	4.37
53.25	Safety Cable	Yes	3.25	0.000	0.38	0.10	0.00	0.022	0.000	42.942	0.00	1.06
53.25	Step bolts	Yes	3.25	0.000	0.63	0.17	0.00	0.022	0.000	42.942	0.00	4.06
55.00	Safety Cable	Yes	1.75	0.000	0.38	0.06	0.00	0.022	0.000	43.230	0.00	0.57
55.00	Step bolts	Yes	1.75	0.000	0.63	0.09	0.00	0.022	0.000	43.230	0.00	2.18
60.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.022	0.000	44.015	0.00	1.64
60.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.022	0.000	44.015	0.00	6.24
65.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.023	0.000	44.751	0.00	1.64
65.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.023	0.000	44.751	0.00	6.24
70.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.023	0.000	45.444	0.00	1.64
70.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.023	0.000	45.444	0.00	6.24
75.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.024	0.000	46.100	0.00	1.64
75.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.024	0.000	46.100	0.00	6.24
80.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.025	0.000	46.723	0.00	1.64
80.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.025	0.000	46.723	0.00	6.24
85.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.026	0.000	47.316	0.00	1.64
85.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.026	0.000	47.316	0.00	6.24
90.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.027	0.000	47.882	0.00	1.64
90.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.027	0.000	47.882	0.00	6.24
95.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.028	0.000	48.424	0.00	1.64
95.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.028	0.000	48.424	0.00	6.24
100.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.029	0.000	48.945	0.00	1.64
100.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.029	0.000	48.945	0.00	6.24
105.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.029	0.000	49.445	0.00	1.64
105.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.029	0.000	49.445	0.00	6.24
110.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.031	0.000	49.927	0.00	1.64

Linear Appurtenance Segment Forces (Factored)


Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 13



Load Case: 1.2D + 1.0W 126 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.00



Iterations 26

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
110.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.031	0.000	49.927	0.00	6.24
115.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.032	0.000	50.392	0.00	1.64
115.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.032	0.000	50.392	0.00	6.24
120.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.034	0.000	50.842	0.00	1.64
120.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.034	0.000	50.842	0.00	6.24
125.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.035	0.000	51.277	0.00	1.64
125.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.035	0.000	51.277	0.00	6.24
130.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.037	0.000	51.699	0.00	1.64
130.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.037	0.000	51.699	0.00	6.24
134.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.039	0.000	52.028	0.00	1.31
134.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.039	0.000	52.028	0.00	4.99
135.00	Safety Cable	Yes	1.00	0.000	0.38	0.03	0.00	0.040	0.000	52.109	0.00	0.33
135.00	Step bolts	Yes	1.00	0.000	0.63	0.05	0.00	0.040	0.000	52.109	0.00	1.25
140.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.041	0.000	52.506	0.00	1.64
140.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.041	0.000	52.506	0.00	6.24
145.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.044	0.000	52.893	0.00	1.64
145.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.044	0.000	52.893	0.00	6.24
145.25	Safety Cable	Yes	0.25	0.000	0.38	0.01	0.00	0.045	0.000	52.912	0.00	0.08
145.25	Step bolts	Yes	0.25	0.000	0.63	0.01	0.00	0.045	0.000	52.912	0.00	0.31
146.00	Safety Cable	Yes	0.75	0.000	0.38	0.02	0.00	0.045	0.000	52.969	0.00	0.25
146.00	Step bolts	Yes	0.75	0.000	0.63	0.04	0.00	0.045	0.000	52.969	0.00	0.94
148.50	Safety Cable	Yes	2.50	0.000	0.38	0.08	0.00	0.046	0.000	53.157	0.00	0.82
148.50	Step bolts	Yes	2.50	0.000	0.63	0.13	0.00	0.046	0.000	53.157	0.00	3.12
150.00	Safety Cable	Yes	1.50	0.000	0.38	0.05	0.00	0.046	0.000	53.269	0.00	0.49
150.00	Step bolts	Yes	1.50	0.000	0.63	0.08	0.00	0.046	0.000	53.269	0.00	1.87
155.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.049	0.000	53.636	0.00	1.64
155.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.049	0.000	53.636	0.00	6.24
159.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.052	0.000	53.922	0.00	1.31
159.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.052	0.000	53.922	0.00	4.99
160.00	Safety Cable	Yes	1.00	0.000	0.38	0.03	0.00	0.053	0.000	53.993	0.00	0.33
160.00	Step bolts	Yes	1.00	0.000	0.63	0.05	0.00	0.053	0.000	53.993	0.00	1.25
165.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.056	0.000	54.342	0.00	1.64
165.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.056	0.000	54.342	0.00	6.24
169.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.060	0.000	54.615	0.00	1.31
169.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.060	0.000	54.615	0.00	4.99
Totals:											0.0	266.3

Calculated Forces


Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 14

Load Case: 1.2D + 1.0W 126 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 26

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-60.42	-43.54	0.00	-5582.1	0.00	5582.17	5562.36	1454.92	7206.86	6836.50	0.00	0.000	0.000	0.828
5.00	-58.34	-43.09	0.00	-5364.4	0.00	5364.48	5482.35	1421.65	6881.06	6582.98	0.11	-0.209	0.000	0.826
10.00	-56.30	-42.65	0.00	-5149.0	0.00	5149.04	5400.13	1388.39	6562.80	6331.40	0.45	-0.423	0.000	0.825
15.00	-54.29	-42.20	0.00	-4935.8	0.00	4935.82	5315.71	1355.12	6252.07	6081.95	1.01	-0.644	0.000	0.823
20.00	-52.33	-41.73	0.00	-4724.8	0.00	4724.82	5229.08	1321.85	5948.87	5834.81	1.80	-0.872	0.000	0.821
25.00	-50.40	-41.23	0.00	-4516.1	0.00	4516.18	5140.25	1288.59	5653.22	5590.18	2.84	-1.107	0.000	0.819
30.00	-48.51	-40.72	0.00	-4310.0	0.00	4310.02	5049.20	1255.32	5365.09	5348.24	4.13	-1.349	0.000	0.817
35.00	-46.66	-40.20	0.00	-4106.4	0.00	4106.42	4955.95	1222.05	5084.51	5109.18	5.68	-1.599	0.000	0.814
40.00	-44.85	-39.67	0.00	-3905.4	0.00	3905.43	4860.49	1188.79	4811.46	4873.19	7.49	-1.856	0.000	0.812
45.00	-43.14	-39.06	0.00	-3707.0	0.00	3707.09	4762.82	1155.52	4545.94	4640.45	9.58	-2.122	0.000	0.809
46.50	-42.58	-38.94	0.00	-3648.5	0.00	3648.50	4733.09	1145.54	4467.75	4571.29	10.26	-2.206	0.000	0.808
50.00	-40.43	-38.51	0.00	-3512.2	0.00	3512.20	4662.94	1122.25	4287.96	4411.15	11.95	-2.402	0.000	0.806
53.25	-38.49	-38.09	0.00	-3387.0	0.00	3387.03	4662.03	1121.95	4285.67	4409.10	13.65	-2.588	0.000	0.778
55.00	-37.84	-37.95	0.00	-3320.3	0.00	3320.38	4626.54	1110.31	4197.18	4329.70	14.62	-2.691	0.000	0.776
60.00	-36.17	-37.38	0.00	-3130.6	0.00	3130.63	4523.67	1077.04	3949.44	4105.38	17.58	-2.968	0.000	0.772
65.00	-34.54	-36.80	0.00	-2943.7	0.00	2943.76	4418.66	1043.78	3709.24	3885.01	20.84	-3.253	0.000	0.767
70.00	-32.94	-36.23	0.00	-2759.7	0.00	2759.74	4277.83	1010.51	3476.57	3640.10	24.40	-3.547	0.000	0.767
75.00	-31.39	-35.67	0.00	-2578.5	0.00	2578.58	4137.00	977.25	3251.43	3403.17	28.28	-3.851	0.000	0.767
80.00	-29.88	-35.11	0.00	-2400.2	0.00	2400.24	3996.18	943.98	3033.84	3174.21	32.48	-4.164	0.000	0.765
85.00	-28.40	-34.55	0.00	-2224.7	0.00	2224.71	3855.35	910.71	2823.78	2953.23	37.01	-4.486	0.000	0.762
90.00	-26.96	-34.01	0.00	-2051.9	0.00	2051.94	3714.52	877.45	2621.25	2740.21	41.88	-4.818	0.000	0.758
95.00	-25.57	-33.47	0.00	-1881.9	0.00	1881.92	3573.69	844.18	2426.26	2535.17	47.10	-5.160	0.000	0.751
100.00	-23.37	-32.84	0.00	-1714.5	0.00	1714.59	3014.30	712.04	2013.83	2107.62	52.69	-5.511	0.000	0.823
105.00	-22.15	-32.32	0.00	-1550.4	0.00	1550.40	2893.59	683.53	1855.77	1941.32	58.64	-5.870	0.000	0.809
110.00	-20.97	-31.81	0.00	-1388.8	0.00	1388.83	2772.88	655.01	1704.17	1781.85	64.99	-6.267	0.000	0.789
115.00	-19.82	-31.31	0.00	-1229.8	0.00	1229.80	2652.17	626.50	1559.02	1629.21	71.76	-6.669	0.000	0.765
120.00	-18.71	-30.81	0.00	-1073.2	0.00	1073.27	2531.46	597.98	1420.34	1483.41	78.94	-7.072	0.000	0.734
125.00	-17.64	-30.33	0.00	-919.19	0.00	919.19	2410.75	569.47	1288.11	1344.44	86.55	-7.474	0.000	0.694
130.00	-16.63	-29.84	0.00	-767.54	0.00	767.54	2290.04	540.95	1162.35	1212.31	94.57	-7.868	0.000	0.643
134.00	-13.42	-26.16	0.00	-648.17	0.00	648.17	2193.47	518.14	1066.39	1111.53	101.27	-8.176	0.000	0.592
135.00	-13.16	-26.10	0.00	-622.01	0.00	622.01	2169.33	512.44	1043.04	1087.01	102.99	-8.255	0.000	0.581
140.00	-12.26	-25.63	0.00	-491.51	0.00	491.51	2048.62	483.93	930.19	968.55	111.80	-8.612	0.000	0.516
145.00	-11.47	-25.13	0.00	-363.38	0.00	363.38	1927.91	455.41	823.80	856.92	120.96	-8.937	0.000	0.433
145.25	-11.42	-25.11	0.00	-357.10	0.00	357.10	1921.88	453.99	818.65	851.51	121.43	-8.953	0.000	0.428
146.00	-8.36	-18.95	0.00	-338.26	0.00	338.26	1903.77	449.71	803.30	835.41	122.83	-9.001	0.000	0.411
148.50	-7.89	-18.69	0.00	-290.90	0.00	290.90	907.84	223.60	397.18	399.56	127.57	-9.150	0.000	0.744
150.00	-7.70	-18.60	0.00	-262.86	0.00	262.86	895.57	219.32	382.13	386.55	130.44	-9.237	0.000	0.696
155.00	-7.25	-18.21	0.00	-169.87	0.00	169.87	853.23	205.07	334.07	344.13	140.33	-9.679	0.000	0.510
159.00	-3.79	-9.90	0.00	-97.05	0.00	97.05	817.77	193.66	297.94	311.31	148.52	-9.946	0.000	0.319
160.00	-3.72	-9.84	0.00	-87.14	0.00	87.14	807.76	190.81	289.23	302.92	150.60	-10.001	0.000	0.295
165.00	-3.47	-9.47	0.00	-37.97	0.00	37.97	747.41	176.55	247.62	259.13	161.14	-10.195	0.000	0.154
169.00	0.00	-8.70	0.00	-0.09	0.00	0.09	699.12	165.15	216.66	226.56	169.67	-10.254	0.000	0.003

Wind Loading - Shaft

Structure: CT11794-S
Site Name: East Lyme 1
Height: 169.00 (ft)
Base Elev: 1.000 (ft)
Gh: 1.1

Topography: 1

Code: TIA-222-H
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

1/11/2024

Page: 15



Load Case: 0.9D + 1.0W 126 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.00



Iterations 25

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.85	32.803	36.08	591.02	0.730	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	32.803	36.08	577.61	0.730	0.000	5.00	25.156	18.36	662.6	0.0	1254.9
10.00		1.00	0.85	32.803	36.08	564.19	0.730	0.000	5.00	24.579	17.94	647.4	0.0	1225.9
15.00		1.00	0.86	33.208	36.53	554.17	0.730	0.000	5.00	24.001	17.52	640.0	0.0	1196.9
20.00		1.00	0.91	35.165	38.68	556.37	0.730	0.000	5.00	23.423	17.10	661.4	0.0	1167.8
25.00		1.00	0.95	36.782	40.46	554.81	0.730	0.000	5.00	22.846	16.68	674.8	0.0	1138.8
30.00		1.00	0.99	38.169	41.99	550.71	0.730	0.000	5.00	22.268	16.26	682.5	0.0	1109.8
35.00		1.00	1.02	39.390	43.33	544.75	0.730	0.000	5.00	21.691	15.83	686.1	0.0	1080.8
40.00		1.00	1.05	40.483	44.53	537.35	0.730	0.000	5.00	21.113	15.41	686.3	0.0	1051.7
45.00		1.00	1.07	41.476	45.62	528.82	0.730	0.000	5.00	20.536	14.99	683.9	0.0	1022.7
46.50 Bot - Section 2		1.00	1.08	41.757	45.93	526.06	0.730	0.000	1.50	6.048	4.42	202.8	0.0	301.2
50.00		1.00	1.10	42.387	46.63	519.34	0.730	0.000	3.50	14.169	10.34	482.3	0.0	1398.1
53.25 Top - Section 1		1.00	1.11	42.942	47.24	512.75	0.730	0.000	3.25	12.904	9.42	444.9	0.0	1272.8
55.00		1.00	1.12	43.230	47.55	518.95	0.730	0.000	1.75	6.847	5.00	237.7	0.0	340.8
60.00		1.00	1.14	44.015	48.42	508.10	0.730	0.000	5.00	19.173	14.00	677.7	0.0	954.2
65.00		1.00	1.16	44.751	49.23	496.66	0.730	0.000	5.00	18.596	13.57	668.2	0.0	925.2
70.00		1.00	1.18	45.444	49.99	484.71	0.730	0.000	5.00	18.018	13.15	657.5	0.0	896.2
75.00		1.00	1.19	46.100	50.71	472.29	0.730	0.000	5.00	17.440	12.73	645.6	0.0	867.2
80.00		1.00	1.21	46.723	51.40	459.46	0.730	0.000	5.00	16.863	12.31	632.7	0.0	838.1
85.00		1.00	1.23	47.316	52.05	446.25	0.730	0.000	5.00	16.285	11.89	618.8	0.0	809.1
90.00		1.00	1.24	47.882	52.67	432.70	0.730	0.000	5.00	15.708	11.47	604.0	0.0	780.1
95.00 Bot - Section 3		1.00	1.25	48.424	53.27	418.85	0.730	0.000	5.00	15.130	11.05	588.3	0.0	751.1
100.00 Top - Section 2		1.00	1.27	48.945	53.84	404.70	0.730	0.000	5.00	14.870	10.86	584.4	0.0	1355.7
105.00		1.00	1.28	49.445	54.39	399.35	0.730	0.000	5.00	14.292	10.43	567.5	0.0	608.8
110.00		1.00	1.29	49.927	54.92	384.74	0.730	0.000	5.00	13.715	10.01	549.8	0.0	583.9
115.00		1.00	1.31	50.392	55.43	369.90	0.730	0.000	5.00	13.137	9.59	531.6	0.0	559.1
120.00		1.00	1.32	50.842	55.93	354.84	0.730	0.000	5.00	12.560	9.17	512.8	0.0	534.2
125.00		1.00	1.33	51.277	56.41	339.59	0.730	0.000	5.00	11.982	8.75	493.4	0.0	509.3
130.00		1.00	1.34	51.699	56.87	324.14	0.730	0.000	5.00	11.405	8.33	473.5	0.0	484.4
134.00 Appurtenance(s)		1.00	1.35	52.028	57.23	311.65	0.730	0.000	4.00	8.708	6.36	363.8	0.0	369.6
135.00		1.00	1.35	52.109	57.32	308.51	0.730	0.000	1.00	2.119	1.55	88.7	0.0	89.9
140.00		1.00	1.36	52.506	57.76	292.71	0.730	0.000	5.00	10.249	7.48	432.1	0.0	434.7
145.00		1.00	1.37	52.893	58.18	276.75	0.730	0.000	5.00	9.672	7.06	410.8	0.0	409.8
145.25 Bot - Section 4		1.00	1.37	52.912	58.20	275.95	0.730	0.000	0.25	0.468	0.34	19.9	0.0	19.8
146.00 Appurtenance(s)		1.00	1.37	52.969	58.27	273.54	0.730	0.000	0.75	1.420	1.04	60.4	0.0	89.5
148.50 Top - Section 3		1.00	1.38	53.157	58.47	265.49	0.730	0.000	2.50	4.641	3.39	198.1	0.0	292.2
150.00		1.00	1.38	53.269	58.60	265.34	0.730	0.000	1.50	2.715	1.98	116.1	0.0	58.0
155.00		1.00	1.39	53.636	59.00	249.09	0.730	0.000	5.00	8.675	6.33	373.6	0.0	185.1
159.00 Appurtenance(s)		1.00	1.40	53.922	59.31	236.00	0.730	0.000	4.00	6.525	4.76	282.5	0.0	139.2
160.00		1.00	1.40	53.993	59.39	232.71	0.730	0.000	1.00	1.573	1.15	68.2	0.0	33.5
165.00		1.00	1.41	54.342	59.78	216.20	0.730	0.000	5.00	7.520	5.49	328.2	0.0	160.3
169.00 Appurtenance(s)		1.00	1.42	54.615	60.08	202.89	0.730	0.000	4.00	5.600	4.09	245.6	0.0	119.3
Totals:									169.00			19,186.6		27,419.7

Discrete Appurtenance Forces

Structure: CT11794-S
Site Name: East Lyme 1
Height: 169.00 (ft)
Base Elev: 1.000 (ft)
Gh: 1.1

Topography: 1

Code: TIA-222-H
Exposure: C
Crest Height: 0.00
Site Class: D - Stiff Soil
Struct Class: II

1/11/2024


Page: 16



Load Case: 0.9D + 1.0W 126 mph Wind

Dead Load Factor 0.90

Wind Load Factor 1.00



Iterations 25

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	Orient Factor x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)	
1	169.00	Ericsson RRUS A2 RRU	6	54.615	60.076	0.50	0.75	5.61	118.80	0.000	0.000	336.90	0.00	0.00	
2	169.00	Ericsson AIR 6449 B77D	3	54.530	59.983	0.64	0.75	7.90	237.60	0.000	-1.250	473.78	0.00	-592.23	
3	169.00	Ericsson AIR 6419 B77G	3	54.733	60.206	0.57	0.75	6.50	178.47	0.000	1.750	391.22	0.00	684.63	
4	169.00	CCI TPA65R-BU4DA-K	1	54.615	60.076	0.54	0.75	6.95	60.75	0.000	0.000	417.52	0.00	0.00	
5	169.00	CCI TPA65R-BU6DA-K	1	54.615	60.076	0.54	0.75	6.95	60.75	0.000	0.000	417.52	0.00	0.00	
6	169.00	CCI TPA65R-BU8DA-K	1	54.615	60.076	0.54	0.75	9.65	74.25	0.000	0.000	579.72	0.00	0.00	
7	169.00	Ericsson 8843 B2 B66A	3	54.615	60.076	0.50	0.75	2.47	194.40	0.000	0.000	148.53	0.00	0.00	
8	169.00	Ericsson RRUS-12 RRU	6	54.615	60.076	0.50	0.75	9.50	313.20	0.000	0.000	570.56	0.00	0.00	
9	169.00	Ericsson RRUS 32 RRU	3	54.615	60.076	0.50	0.75	5.83	207.90	0.000	0.000	350.49	0.00	0.00	
10	169.00	mount pipe	12	54.615	60.076	0.75	0.75	12.24	324.00	0.000	0.000	735.33	0.00	0.00	
11	169.00	Ericsson 4449 B5/B12	3	54.615	60.076	0.50	0.75	2.97	191.70	0.000	0.000	178.41	0.00	0.00	
12	169.00	Commscope	1	54.615	60.076	0.75	0.75	13.40	71.10	0.000	0.000	805.17	0.00	0.00	
13	169.00	Commscope	1	54.615	60.076	0.75	0.75	9.20	71.10	0.000	0.000	552.85	0.00	0.00	
14	169.00	CCI OPA65R-BU4DA	1	54.615	60.076	0.70	0.75	3.50	38.70	0.000	0.000	210.08	0.00	0.00	
15	169.00	Raycap DC6-48-60-18-8F	3	54.615	60.076	0.50	0.75	2.22	88.56	0.000	0.000	133.13	0.00	0.00	
16	169.00	Ericsson RRUS 4478 B14	3	54.615	60.076	0.54	0.80	2.65	160.38	0.000	0.000	159.39	0.00	0.00	
17	169.00	CCI DTMA65R7819VG12A	3	54.615	60.076	0.50	0.75	1.72	51.79	0.000	0.000	103.24	0.00	0.00	
18	169.00	Reinforced T-Arms	3	54.615	60.076	0.75	0.75	31.50	1215.00	0.000	0.000	1892.41	0.00	0.00	
19	159.00	Ericsson 4460 B25/B66A	3	53.922	59.314	0.54	0.80	2.64	194.40	0.000	0.000	156.42	0.00	0.00	
20	159.00	Ericsson 4449 B71 + B85	3	53.922	59.314	0.54	0.80	3.17	197.64	0.000	0.000	187.89	0.00	0.00	
21	159.00	RFS	3	53.922	59.314	0.58	0.80	35.46	331.56	0.000	0.000	2103.32	0.00	0.00	
22	159.00	Commscope VV-65A-R1	3	53.922	59.314	0.59	0.80	14.03	79.65	0.000	0.000	832.21	0.00	0.00	
23	159.00	T-Arm	3	53.922	59.314	0.75	0.75	18.00	1080.00	0.000	0.000	1067.66	0.00	0.00	
24	159.00	PRK-SFS-L	1	53.922	59.314	1.00	1.00	16.60	354.60	0.000	0.000	984.62	0.00	0.00	
25	159.00	PRK-1245L	1	53.922	59.314	1.00	1.00	9.50	418.42	0.000	0.000	563.49	0.00	0.00	
26	159.00	Ericsson KRY 112 144/1	3	53.922	59.314	0.52	0.75	0.65	29.70	0.000	0.000	38.30	0.00	0.00	
27	159.00	mount pipe	12	53.922	59.314	0.75	0.75	12.42	324.00	0.000	0.000	736.69	0.00	0.00	
28	159.00	Ericsson AIR 6419 B41	3	53.922	59.314	0.56	0.80	10.97	359.64	0.000	0.000	650.70	0.00	0.00	
29	146.00	JMA Wireless	6	52.969	58.266	0.65	0.75	38.64	324.00	0.000	0.000	2251.45	0.00	0.00	
30	146.00	mount pipe	12	52.969	58.266	0.75	0.75	13.23	324.00	0.000	0.000	770.85	0.00	0.00	
31	146.00	Samsung B2/B66A RRH	3	52.969	58.266	0.63	0.75	3.53	201.72	0.000	0.000	205.93	0.00	0.00	
32	146.00	Mds	1	52.969	58.266	1.00	1.00	13.79	418.54	0.000	0.000	803.48	0.00	0.00	
33	146.00	Samsung RF4461d-13A	3	52.969	58.266	0.50	0.75	2.82	195.75	0.000	0.000	164.25	0.00	0.00	
34	146.00	Samsung MT6413-77A	3	52.969	58.266	0.52	0.75	5.88	154.71	0.000	0.000	342.83	0.00	0.00	
35	146.00	Raycap	1	52.969	58.266	0.75	0.75	3.04	28.80	0.000	0.000	177.42	0.00	0.00	
36	146.00	Antenna Bracket JWA	3	52.969	58.266	1.00	1.00	0.00	75.60	0.000	0.000	0.00	0.00	0.00	
37	146.00	Low Profile Platform	1	52.969	58.266	1.00	1.00	14.69	1125.00	0.000	0.000	855.92	0.00	0.00	
38	134.00	Platform w/HRK	1	52.028	57.230	0.67	0.67	22.91	1562.40	0.000	0.000	1310.99	0.00	0.00	
39	134.00	Raycap	1	52.028	57.230	0.75	0.75	1.51	19.67	0.000	0.000	86.27	0.00	0.00	
40	134.00	Samsung RF4451d-70A	3	52.028	57.230	0.50	0.75	2.83	165.51	0.000	0.000	162.20	0.00	0.00	
41	134.00	Samsung RF4450t-71A	3	52.028	57.230	0.50	0.75	3.11	255.37	0.000	0.000	177.73	0.00	0.00	
42	134.00	Commscope	3	52.028	57.230	0.55	0.75	20.15	191.16	0.000	0.000	1153.39	0.00	0.00	
Totals:									12,070.27						24,240.29

Total Applied Force Summary


Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 17

Load Case: 0.9D + 1.0W 126 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.00



Iterations 25

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		662.63	1442.61	0.00	0.00
10.00		647.42	1413.59	0.00	0.00
15.00		640.01	1384.56	0.00	0.00
20.00		661.41	1355.54	0.00	0.00
25.00		674.77	1326.51	0.00	0.00
30.00		682.52	1297.49	0.00	0.00
35.00		686.08	1268.46	0.00	0.00
40.00		686.35	1239.44	0.00	0.00
45.00		683.94	1210.41	0.00	0.00
46.50		202.80	357.46	0.00	0.00
50.00		482.27	1529.48	0.00	0.00
53.25		444.95	1394.76	0.00	0.00
55.00		237.68	406.54	0.00	0.00
60.00		677.66	1141.94	0.00	0.00
65.00		668.24	1112.92	0.00	0.00
70.00		657.51	1083.89	0.00	0.00
75.00		645.62	1054.87	0.00	0.00
80.00		632.67	1025.84	0.00	0.00
85.00		618.75	996.81	0.00	0.00
90.00		603.95	967.79	0.00	0.00
95.00		588.33	938.76	0.00	0.00
100.00		584.43	1543.44	0.00	0.00
105.00		567.47	796.52	0.00	0.00
110.00		549.85	771.64	0.00	0.00
115.00		531.60	746.76	0.00	0.00
120.00		512.77	721.88	0.00	0.00
125.00		493.37	697.00	0.00	0.00
130.00		473.46	672.13	0.00	0.00
134.00	(11) attachments	3254.38	2713.89	0.00	0.00
135.00		88.67	126.47	0.00	0.00
140.00		432.14	617.42	0.00	0.00
145.00		410.79	592.54	0.00	0.00
145.25		19.90	28.97	0.00	0.00
146.00	(33) attachments	5632.56	2965.00	0.00	0.00
148.50		198.10	351.18	0.00	0.00
150.00		116.15	93.37	0.00	0.00
155.00		373.65	303.15	0.00	0.00
159.00	(35) attachments	7603.81	3603.17	0.00	0.00
160.00		68.22	44.73	0.00	0.00
165.00		328.16	216.17	0.00	0.00
169.00	(57) attachments	8701.88	3822.42	0.00	92.40
	Totals:	43,426.92	45,377.53	0.00	92.40

Linear Appurtenance Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 18

Load Case: 0.9D + 1.0W 126 mph Wind

Dead Load Factor 0.90

Wind Load Factor 1.00



Iterations 25

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.017	0.000	32.803	0.00	1.23
5.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.017	0.000	32.803	0.00	4.68
10.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.017	0.000	32.803	0.00	1.23
10.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.017	0.000	32.803	0.00	4.68
15.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	33.208	0.00	1.23
15.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	33.208	0.00	4.68
20.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	35.165	0.00	1.23
20.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	35.165	0.00	4.68
25.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	36.782	0.00	1.23
25.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	36.782	0.00	4.68
30.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.019	0.000	38.169	0.00	1.23
30.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.019	0.000	38.169	0.00	4.68
35.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.019	0.000	39.390	0.00	1.23
35.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.019	0.000	39.390	0.00	4.68
40.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.020	0.000	40.483	0.00	1.23
40.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.020	0.000	40.483	0.00	4.68
45.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.020	0.000	41.476	0.00	1.23
45.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.020	0.000	41.476	0.00	4.68
46.50	Safety Cable	Yes	1.50	0.000	0.38	0.05	0.00	0.021	0.000	41.757	0.00	0.37
46.50	Step bolts	Yes	1.50	0.000	0.63	0.08	0.00	0.021	0.000	41.757	0.00	1.40
50.00	Safety Cable	Yes	3.50	0.000	0.38	0.11	0.00	0.021	0.000	42.387	0.00	0.86
50.00	Step bolts	Yes	3.50	0.000	0.63	0.18	0.00	0.021	0.000	42.387	0.00	3.28
53.25	Safety Cable	Yes	3.25	0.000	0.38	0.10	0.00	0.022	0.000	42.942	0.00	0.80
53.25	Step bolts	Yes	3.25	0.000	0.63	0.17	0.00	0.022	0.000	42.942	0.00	3.04
55.00	Safety Cable	Yes	1.75	0.000	0.38	0.06	0.00	0.022	0.000	43.230	0.00	0.43
55.00	Step bolts	Yes	1.75	0.000	0.63	0.09	0.00	0.022	0.000	43.230	0.00	1.64
60.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.022	0.000	44.015	0.00	1.23
60.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.022	0.000	44.015	0.00	4.68
65.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.023	0.000	44.751	0.00	1.23
65.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.023	0.000	44.751	0.00	4.68
70.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.023	0.000	45.444	0.00	1.23
70.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.023	0.000	45.444	0.00	4.68
75.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.024	0.000	46.100	0.00	1.23
75.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.024	0.000	46.100	0.00	4.68
80.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.025	0.000	46.723	0.00	1.23
80.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.025	0.000	46.723	0.00	4.68
85.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.026	0.000	47.316	0.00	1.23
85.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.026	0.000	47.316	0.00	4.68
90.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.027	0.000	47.882	0.00	1.23
90.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.027	0.000	47.882	0.00	4.68
95.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.028	0.000	48.424	0.00	1.23
95.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.028	0.000	48.424	0.00	4.68
100.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.029	0.000	48.945	0.00	1.23
100.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.029	0.000	48.945	0.00	4.68
105.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.029	0.000	49.445	0.00	1.23
105.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.029	0.000	49.445	0.00	4.68
110.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.031	0.000	49.927	0.00	1.23

Linear Appurtenance Segment Forces (Factored)


Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 19



Load Case: 0.9D + 1.0W 126 mph Wind

Dead Load Factor 0.90

Wind Load Factor 1.00



Iterations 25

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
110.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.031	0.000	49.927	0.00	4.68
115.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.032	0.000	50.392	0.00	1.23
115.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.032	0.000	50.392	0.00	4.68
120.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.034	0.000	50.842	0.00	1.23
120.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.034	0.000	50.842	0.00	4.68
125.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.035	0.000	51.277	0.00	1.23
125.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.035	0.000	51.277	0.00	4.68
130.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.037	0.000	51.699	0.00	1.23
130.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.037	0.000	51.699	0.00	4.68
134.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.039	0.000	52.028	0.00	0.98
134.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.039	0.000	52.028	0.00	3.74
135.00	Safety Cable	Yes	1.00	0.000	0.38	0.03	0.00	0.040	0.000	52.109	0.00	0.25
135.00	Step bolts	Yes	1.00	0.000	0.63	0.05	0.00	0.040	0.000	52.109	0.00	0.94
140.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.041	0.000	52.506	0.00	1.23
140.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.041	0.000	52.506	0.00	4.68
145.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.044	0.000	52.893	0.00	1.23
145.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.044	0.000	52.893	0.00	4.68
145.25	Safety Cable	Yes	0.25	0.000	0.38	0.01	0.00	0.045	0.000	52.912	0.00	0.06
145.25	Step bolts	Yes	0.25	0.000	0.63	0.01	0.00	0.045	0.000	52.912	0.00	0.23
146.00	Safety Cable	Yes	0.75	0.000	0.38	0.02	0.00	0.045	0.000	52.969	0.00	0.18
146.00	Step bolts	Yes	0.75	0.000	0.63	0.04	0.00	0.045	0.000	52.969	0.00	0.70
148.50	Safety Cable	Yes	2.50	0.000	0.38	0.08	0.00	0.046	0.000	53.157	0.00	0.61
148.50	Step bolts	Yes	2.50	0.000	0.63	0.13	0.00	0.046	0.000	53.157	0.00	2.34
150.00	Safety Cable	Yes	1.50	0.000	0.38	0.05	0.00	0.046	0.000	53.269	0.00	0.37
150.00	Step bolts	Yes	1.50	0.000	0.63	0.08	0.00	0.046	0.000	53.269	0.00	1.40
155.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.049	0.000	53.636	0.00	1.23
155.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.049	0.000	53.636	0.00	4.68
159.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.052	0.000	53.922	0.00	0.98
159.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.052	0.000	53.922	0.00	3.74
160.00	Safety Cable	Yes	1.00	0.000	0.38	0.03	0.00	0.053	0.000	53.993	0.00	0.25
160.00	Step bolts	Yes	1.00	0.000	0.63	0.05	0.00	0.053	0.000	53.993	0.00	0.94
165.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.056	0.000	54.342	0.00	1.23
165.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.056	0.000	54.342	0.00	4.68
169.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.060	0.000	54.615	0.00	0.98
169.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.060	0.000	54.615	0.00	3.74
Totals:											0.0	199.7

Calculated Forces

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 20

Load Case: 0.9D + 1.0W 126 mph Wind

Iterations 25

Dead Load Factor 0.90
Wind Load Factor 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-45.30	-43.51	0.00	-5498.2	0.00	5498.20	5562.36	1454.92	7206.86	6836.50	0.00	0.000	0.000	0.813
5.00	-43.70	-43.00	0.00	-5280.6	0.00	5280.66	5482.35	1421.65	6881.06	6582.98	0.11	-0.205	0.000	0.811
10.00	-42.13	-42.51	0.00	-5065.6	0.00	5065.65	5400.13	1388.39	6562.80	6331.40	0.44	-0.417	0.000	0.809
15.00	-40.59	-42.01	0.00	-4853.1	0.00	4853.12	5315.71	1355.12	6252.07	6081.95	0.99	-0.634	0.000	0.807
20.00	-39.08	-41.49	0.00	-4643.0	0.00	4643.07	5229.08	1321.85	5948.87	5834.81	1.78	-0.858	0.000	0.804
25.00	-37.60	-40.94	0.00	-4435.6	0.00	4435.65	5140.25	1288.59	5653.22	5590.18	2.80	-1.089	0.000	0.802
30.00	-36.15	-40.39	0.00	-4230.9	0.00	4230.94	5049.20	1255.32	5365.09	5348.24	4.07	-1.326	0.000	0.799
35.00	-34.72	-39.82	0.00	-4029.0	0.00	4029.01	4955.95	1222.05	5084.51	5109.18	5.59	-1.571	0.000	0.797
40.00	-33.33	-39.25	0.00	-3829.9	0.00	3829.92	4860.49	1188.79	4811.46	4873.19	7.37	-1.824	0.000	0.794
45.00	-32.03	-38.62	0.00	-3633.6	0.00	3633.69	4762.82	1155.52	4545.94	4640.45	9.42	-2.085	0.000	0.791
46.50	-31.59	-38.48	0.00	-3575.7	0.00	3575.77	4733.09	1145.54	4467.75	4571.29	10.09	-2.167	0.000	0.790
50.00	-29.95	-38.03	0.00	-3441.1	0.00	3441.10	4662.94	1122.25	4287.96	4411.15	11.75	-2.359	0.000	0.788
53.25	-28.48	-37.60	0.00	-3317.5	0.00	3317.50	4662.03	1121.95	4285.67	4409.10	13.42	-2.541	0.000	0.760
55.00	-27.97	-37.43	0.00	-3251.7	0.00	3251.70	4626.54	1110.31	4197.18	4329.70	14.37	-2.642	0.000	0.758
60.00	-26.68	-36.83	0.00	-3064.5	0.00	3064.54	4523.67	1077.04	3949.44	4105.38	17.28	-2.913	0.000	0.754
65.00	-25.43	-36.23	0.00	-2880.3	0.00	2880.39	4418.66	1043.78	3709.24	3885.01	20.48	-3.192	0.000	0.748
70.00	-24.20	-35.63	0.00	-2699.2	0.00	2699.24	4277.83	1010.51	3476.57	3640.10	23.97	-3.480	0.000	0.748
75.00	-23.01	-35.05	0.00	-2521.0	0.00	2521.07	4137.00	977.25	3251.43	3403.17	27.77	-3.777	0.000	0.748
80.00	-21.84	-34.46	0.00	-2345.8	0.00	2345.85	3996.18	943.98	3033.84	3174.21	31.89	-4.083	0.000	0.746
85.00	-20.70	-33.89	0.00	-2173.5	0.00	2173.54	3855.35	910.71	2823.78	2953.23	36.33	-4.398	0.000	0.743
90.00	-19.60	-33.32	0.00	-2004.1	0.00	2004.10	3714.52	877.45	2621.25	2740.21	41.11	-4.722	0.000	0.738
95.00	-18.52	-32.77	0.00	-1837.5	0.00	1837.50	3573.69	844.18	2426.26	2535.17	46.22	-5.056	0.000	0.731
100.00	-16.84	-32.15	0.00	-1673.6	0.00	1673.67	3014.30	712.04	2013.83	2107.62	51.70	-5.399	0.000	0.802
105.00	-15.90	-31.61	0.00	-1512.9	0.00	1512.94	2893.59	683.53	1855.77	1941.32	57.53	-5.749	0.000	0.787
110.00	-14.98	-31.08	0.00	-1354.9	0.00	1354.91	2772.88	655.01	1704.17	1781.85	63.75	-6.136	0.000	0.768
115.00	-14.08	-30.57	0.00	-1199.5	0.00	1199.51	2652.17	626.50	1559.02	1629.21	70.37	-6.528	0.000	0.744
120.00	-13.22	-30.07	0.00	-1046.6	0.00	1046.66	2531.46	597.98	1420.34	1483.41	77.41	-6.922	0.000	0.713
125.00	-12.39	-29.58	0.00	-896.33	0.00	896.33	2410.75	569.47	1288.11	1344.44	84.85	-7.314	0.000	0.675
130.00	-11.61	-29.09	0.00	-748.46	0.00	748.46	2290.04	540.95	1162.35	1212.31	92.70	-7.698	0.000	0.625
134.00	-9.29	-25.52	0.00	-632.11	0.00	632.11	2193.47	518.14	1066.39	1111.53	99.26	-7.998	0.000	0.575
135.00	-9.08	-25.45	0.00	-606.58	0.00	606.58	2169.33	512.44	1043.04	1087.01	100.94	-8.075	0.000	0.565
140.00	-8.38	-24.99	0.00	-479.32	0.00	479.32	2048.62	483.93	930.19	968.55	109.56	-8.423	0.000	0.502
145.00	-7.79	-24.51	0.00	-354.40	0.00	354.40	1927.91	455.41	823.80	856.92	118.52	-8.740	0.000	0.421
145.25	-7.75	-24.49	0.00	-348.27	0.00	348.27	1921.88	453.99	818.65	851.51	118.98	-8.756	0.000	0.416
146.00	-5.65	-18.48	0.00	-329.90	0.00	329.90	1903.77	449.71	803.30	835.41	120.35	-8.803	0.000	0.400
148.50	-5.30	-18.24	0.00	-283.69	0.00	283.69	907.84	223.60	397.18	399.56	124.98	-8.948	0.000	0.723
150.00	-5.13	-18.14	0.00	-256.33	0.00	256.33	895.57	219.32	382.13	386.55	127.80	-9.033	0.000	0.676
155.00	-4.79	-17.75	0.00	-165.63	0.00	165.63	853.23	205.07	334.07	344.13	137.46	-9.464	0.000	0.494
159.00	-2.48	-9.66	0.00	-94.63	0.00	94.63	817.77	193.66	297.94	311.31	145.48	-9.724	0.000	0.310
160.00	-2.43	-9.59	0.00	-84.97	0.00	84.97	807.76	190.81	289.23	302.92	147.51	-9.778	0.000	0.286
165.00	-2.25	-9.23	0.00	-37.03	0.00	37.03	747.41	176.55	247.62	259.13	157.81	-9.967	0.000	0.149
169.00	0.00	-8.70	0.00	-0.09	0.00	0.09	699.12	165.15	216.66	226.56	166.16	-10.025	0.000	0.003

Wind Loading - Shaft

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 21



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 24

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.85	5.165	5.68	0.00	1.200	0.705	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	5.165	5.68	0.00	1.200	0.843	5.00	25.859	31.03	176.3	315.0	1988.2
10.00		1.00	0.85	5.165	5.68	0.00	1.200	0.896	5.00	25.325	30.39	172.7	327.3	1961.8
15.00		1.00	0.86	5.229	5.75	0.00	1.200	0.930	5.00	24.776	29.73	171.0	332.0	1927.8
20.00		1.00	0.91	5.537	6.09	0.00	1.200	0.956	5.00	24.220	29.06	177.0	333.2	1890.3
25.00		1.00	0.95	5.792	6.37	0.00	1.200	0.976	5.00	23.660	28.39	180.9	332.1	1850.5
30.00		1.00	0.99	6.011	6.61	0.00	1.200	0.994	5.00	23.096	27.72	183.2	329.6	1809.3
35.00		1.00	1.02	6.203	6.82	0.00	1.200	1.009	5.00	22.531	27.04	184.5	326.0	1767.1
40.00		1.00	1.05	6.375	7.01	0.00	1.200	1.022	5.00	21.965	26.36	184.8	321.7	1724.0
45.00		1.00	1.07	6.531	7.18	0.00	1.200	1.034	5.00	21.397	25.68	184.5	316.6	1680.2
46.50 Bot - Section 2		1.00	1.08	6.576	7.23	0.00	1.200	1.037	1.50	6.307	7.57	54.7	94.5	496.0
50.00		1.00	1.10	6.675	7.34	0.00	1.200	1.044	3.50	14.778	17.73	130.2	221.7	2085.8
53.25 Top - Section 1		1.00	1.11	6.762	7.44	0.00	1.200	1.051	3.25	13.473	16.17	120.3	203.4	1900.4
55.00		1.00	1.12	6.807	7.49	0.00	1.200	1.054	1.75	7.155	8.59	64.3	108.8	563.2
60.00		1.00	1.14	6.931	7.62	0.00	1.200	1.063	5.00	20.059	24.07	183.5	304.4	1576.7
65.00		1.00	1.16	7.047	7.75	0.00	1.200	1.072	5.00	19.489	23.39	181.3	297.7	1531.3
70.00		1.00	1.18	7.156	7.87	0.00	1.200	1.080	5.00	18.918	22.70	178.7	290.7	1485.6
75.00		1.00	1.19	7.259	7.99	0.00	1.200	1.087	5.00	18.346	22.02	175.8	283.4	1439.7
80.00		1.00	1.21	7.357	8.09	0.00	1.200	1.094	5.00	17.775	21.33	172.6	275.9	1393.5
85.00		1.00	1.23	7.451	8.20	0.00	1.200	1.101	5.00	17.202	20.64	169.2	268.2	1347.0
90.00		1.00	1.24	7.540	8.29	0.00	1.200	1.107	5.00	16.630	19.96	165.5	260.3	1300.4
95.00 Bot - Section 3		1.00	1.25	7.625	8.39	0.00	1.200	1.113	5.00	16.057	19.27	161.6	252.2	1253.7
100.00 Top - Section 2		1.00	1.27	7.707	8.48	0.00	1.200	1.118	5.00	15.802	18.96	160.8	249.2	2056.9
105.00		1.00	1.28	7.786	8.56	0.00	1.200	1.124	5.00	15.229	18.27	156.5	240.9	1052.6
110.00		1.00	1.29	7.862	8.65	0.00	1.200	1.129	5.00	14.656	17.59	152.1	232.4	1011.0
115.00		1.00	1.31	7.935	8.73	0.00	1.200	1.134	5.00	14.082	16.90	147.5	223.7	969.1
120.00		1.00	1.32	8.006	8.81	0.00	1.200	1.139	5.00	13.509	16.21	142.8	215.0	927.2
125.00		1.00	1.33	8.075	8.88	0.00	1.200	1.143	5.00	12.935	15.52	137.9	206.1	885.2
130.00		1.00	1.34	8.141	8.96	0.00	1.200	1.148	5.00	12.361	14.83	132.8	197.1	843.0
134.00 Appurtenance(s)		1.00	1.35	8.193	9.01	0.00	1.200	1.151	4.00	9.475	11.37	102.5	151.9	644.7
135.00		1.00	1.35	8.206	9.03	0.00	1.200	1.152	1.00	2.311	2.77	25.0	37.6	157.5
140.00		1.00	1.36	8.268	9.09	0.00	1.200	1.156	5.00	11.213	13.46	122.4	178.8	758.4
145.00		1.00	1.37	8.329	9.16	0.00	1.200	1.160	5.00	10.639	12.77	117.0	169.6	716.0
145.25 Bot - Section 4		1.00	1.37	8.332	9.17	0.00	1.200	1.161	0.25	0.517	0.62	5.7	8.5	34.9
146.00 Appurtenance(s)		1.00	1.37	8.341	9.18	0.00	1.200	1.161	0.75	1.566	1.88	17.2	25.6	144.9
148.50 Top - Section 3		1.00	1.38	8.371	9.21	0.00	1.200	1.163	2.50	5.126	6.15	56.6	82.9	472.5
150.00		1.00	1.38	8.388	9.23	0.00	1.200	1.164	1.50	3.006	3.61	33.3	48.9	126.2
155.00		1.00	1.39	8.446	9.29	0.00	1.200	1.168	5.00	9.649	11.58	107.6	153.5	400.4
159.00 Appurtenance(s)		1.00	1.40	8.491	9.34	0.00	1.200	1.171	4.00	7.305	8.77	81.9	116.7	302.3
160.00		1.00	1.40	8.502	9.35	0.00	1.200	1.172	1.00	1.769	2.12	19.8	28.8	73.5
165.00		1.00	1.41	8.557	9.41	0.00	1.200	1.175	5.00	8.500	10.20	96.0	134.4	348.1
169.00 Appurtenance(s)		1.00	1.42	8.600	9.46	0.00	1.200	1.178	4.00	6.386	7.66	72.5	101.4	260.4
Totals:									169.00			5,260.6		45,157.3

Discrete Appurtenance Forces

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 22



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind	Iterations 24
Dead Load Factor 1.20	
Wind Load Factor 1.00	

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	Orient Factor x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	169.00	Ericsson RRUS A2 RRU	6	8.600	9.460	0.50	0.75	7.59	253.78	0.000	0.000	71.80	0.00	0.00
2	169.00	Ericsson AIR 6449 B77D	3	8.587	9.446	0.64	0.75	8.98	578.85	0.000	-1.250	84.84	0.00	-106.05
3	169.00	Ericsson AIR 6419 B77G	3	8.619	9.481	0.57	0.75	7.42	364.70	0.000	1.750	70.31	0.00	123.05
4	169.00	CCI TPA65R-BU4DA-K	1	8.600	9.460	0.54	0.75	7.49	214.25	0.000	0.000	70.83	0.00	0.00
5	169.00	CCI TPA65R-BU6DA-K	1	8.600	9.460	0.54	0.75	7.49	214.25	0.000	0.000	70.83	0.00	0.00
6	169.00	CCI TPA65R-BU8DA-K	1	8.600	9.460	0.54	0.75	10.30	275.92	0.000	0.000	97.48	0.00	0.00
7	169.00	Ericsson 8843 B2 B66A	3	8.600	9.460	0.50	0.75	2.98	318.07	0.000	0.000	28.17	0.00	0.00
8	169.00	Ericsson RRUS-12 RRU	6	8.600	9.460	0.50	0.75	10.91	776.81	0.000	0.000	103.18	0.00	0.00
9	169.00	Ericsson RRUS 32 RRU	3	8.600	9.460	0.50	0.75	5.78	492.03	0.000	0.000	54.70	0.00	0.00
10	169.00	mount pipe	12	8.600	9.460	0.75	0.75	19.45	-4798.35	0.000	0.000	184.00	0.00	0.00
11	169.00	Ericsson 4449 B5/B12	3	8.600	9.460	0.50	0.75	3.53	322.91	0.000	0.000	33.36	0.00	0.00
12	169.00	Commscope	1	8.600	9.460	0.75	0.75	14.31	337.97	0.000	0.000	135.40	0.00	0.00
13	169.00	Commscope	1	8.600	9.460	0.75	0.75	9.94	275.43	0.000	0.000	94.03	0.00	0.00
14	169.00	CCI OPA65R-BU4DA	1	8.600	9.460	0.70	0.75	3.95	145.39	0.000	0.000	37.38	0.00	0.00
15	169.00	Raycap DC6-48-60-18-8F	3	8.600	9.460	0.50	0.75	2.93	190.18	0.000	0.000	27.70	0.00	0.00
16	169.00	Ericsson RRUS 4478 B14	3	8.600	9.460	0.54	0.80	3.22	269.62	0.000	0.000	30.42	0.00	0.00
17	169.00	CCI DTMABP7819VG12A	3	8.600	9.460	0.50	0.75	2.50	98.72	0.000	0.000	23.67	0.00	0.00
18	169.00	Reinforced T-Arms	3	8.600	9.460	0.75	0.75	50.06	2166.19	0.000	0.000	473.54	0.00	0.00
19	159.00	Ericsson 4460 B25/B66A	3	8.491	9.340	0.54	0.80	3.17	317.50	0.000	0.000	29.64	0.00	0.00
20	159.00	Ericsson 4449 B71 + B85	3	8.491	9.340	0.54	0.80	3.78	204.55	0.000	0.000	35.33	0.00	0.00
21	159.00	RFS	3	8.491	9.340	0.58	0.80	37.67	1267.92	0.000	0.000	351.82	0.00	0.00
22	159.00	Commscope VV-65A-R1	3	8.491	9.340	0.59	0.80	15.52	432.08	0.000	0.000	144.98	0.00	0.00
23	159.00	T-Arm	3	8.491	9.340	0.75	0.75	28.54	1762.08	0.000	0.000	266.56	0.00	0.00
24	159.00	PRK-SFS-L	1	8.491	9.340	1.00	1.00	24.76	778.54	0.000	0.000	231.31	0.00	0.00
25	159.00	PRK-1245L	1	8.491	9.340	1.00	1.00	16.17	680.57	0.000	0.000	151.08	0.00	0.00
26	159.00	Ericsson KRY 112 144/1	3	8.491	9.340	0.52	0.75	1.15	52.00	0.000	0.000	10.72	0.00	0.00
27	159.00	mount pipe	12	8.491	9.340	0.75	0.75	19.69	-4799.37	0.000	0.000	183.93	0.00	0.00
28	159.00	Ericsson AIR 6419 B41	3	8.491	9.340	0.56	0.80	12.16	791.14	0.000	0.000	113.59	0.00	0.00
29	146.00	JMA Wireless	6	8.341	9.175	0.66	0.75	42.61	1538.27	0.000	0.000	390.92	0.00	0.00
30	146.00	mount pipe	12	8.341	9.175	0.75	0.75	20.60	-16999.0	0.000	0.000	189.04	0.00	0.00
31	146.00	Samsung B2/B66A RRH	3	8.341	9.175	0.64	0.75	4.27	353.66	0.000	0.000	39.15	0.00	0.00
32	146.00	Mds	1	8.341	9.175	1.00	1.00	20.19	-152.93	0.000	0.000	185.29	0.00	0.00
33	146.00	Samsung RF4461d-13A	3	8.341	9.175	0.50	0.75	3.82	526.14	0.000	0.000	35.09	0.00	0.00
34	146.00	Samsung MT6413-77A	3	8.341	9.175	0.53	0.75	6.91	392.11	0.000	0.000	63.37	0.00	0.00
35	146.00	Raycap	1	8.341	9.175	0.75	0.75	3.56	103.32	0.000	0.000	32.62	0.00	0.00
36	146.00	Antenna Bracket JWA	3	8.341	9.175	1.00	1.00	0.00	-4266.43	0.000	0.000	0.00	0.00	0.00
37	146.00	Low Profile Platform	1	8.341	9.175	1.00	1.00	22.88	1975.71	0.000	0.000	209.90	0.00	0.00
38	134.00	Platform w/HRK	1	8.193	9.012	0.67	0.67	36.09	3122.17	0.000	0.000	325.28	0.00	0.00
39	134.00	Raycap	1	8.193	9.012	0.75	0.75	1.98	26.59	0.000	0.000	17.85	0.00	0.00
40	134.00	Samsung RF4451d-70A	3	8.193	9.012	0.50	0.75	3.66	296.06	0.000	0.000	32.95	0.00	0.00
41	134.00	Samsung RF4450t-71A	3	8.193	9.012	0.50	0.75	4.01	583.02	0.000	0.000	36.11	0.00	0.00
42	134.00	Commscope	3	8.193	9.012	0.56	0.75	22.32	783.16	0.000	0.000	201.19	0.00	0.00
Totals:									-7,734.46			4,969.39		

Total Applied Force Summary

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 23



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 24

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		176.32	2250.66	0.00	0.00
10.00		172.68	2225.59	0.00	0.00
15.00		171.02	2192.52	0.00	0.00
20.00		177.03	2155.64	0.00	0.00
25.00		180.89	2116.47	0.00	0.00
30.00		183.24	2075.75	0.00	0.00
35.00		184.48	2033.90	0.00	0.00
40.00		184.83	1991.19	0.00	0.00
45.00		184.47	1947.79	0.00	0.00
46.50		54.75	576.33	0.00	0.00
50.00		130.21	2273.36	0.00	0.00
53.25		120.26	2074.65	0.00	0.00
55.00		64.29	657.09	0.00	0.00
60.00		183.52	1845.17	0.00	0.00
65.00		181.28	1800.01	0.00	0.00
70.00		178.70	1754.55	0.00	0.00
75.00		175.80	1708.81	0.00	0.00
80.00		172.62	1662.82	0.00	0.00
85.00		169.19	1616.61	0.00	0.00
90.00		165.52	1570.20	0.00	0.00
95.00		161.63	1523.60	0.00	0.00
100.00		160.76	2327.02	0.00	0.00
105.00		156.52	1322.93	0.00	0.00
110.00		152.10	1281.41	0.00	0.00
115.00		147.51	1239.76	0.00	0.00
120.00		142.76	1197.97	0.00	0.00
125.00		137.87	1156.07	0.00	0.00
130.00		132.84	1114.06	0.00	0.00
134.00	(11) attachments	715.85	5672.65	0.00	0.00
135.00		25.03	210.41	0.00	0.00
140.00		122.38	1023.12	0.00	0.00
145.00		116.97	980.81	0.00	0.00
145.25		5.68	48.15	0.00	0.00
146.00	(33) attachments	1162.63	-16344.57	0.00	0.00
148.50		56.63	561.76	0.00	0.00
150.00		33.29	179.77	0.00	0.00
155.00		107.57	579.14	0.00	0.00
159.00	(35) attachments	1600.83	1932.37	0.00	0.00
160.00		19.85	92.75	0.00	0.00
165.00		96.01	444.31	0.00	0.00
169.00	(57) attachments	1764.16	2834.09	0.00	17.00
	Totals:	10,229.96	45,906.67	0.00	17.00


Linear Appurtenance Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 24

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	Safety Cable	Yes	5.00	0.000	0.38	0.86	0.00	0.017	0.000	5.165	0.00	7.27
5.00	Step bolts	Yes	5.00	0.000	0.63	0.97	0.00	0.017	0.000	5.165	0.00	12.80
10.00	Safety Cable	Yes	5.00	0.000	0.38	0.90	0.00	0.017	0.000	5.165	0.00	7.91
10.00	Step bolts	Yes	5.00	0.000	0.63	1.01	0.00	0.017	0.000	5.165	0.00	13.48
15.00	Safety Cable	Yes	5.00	0.000	0.38	0.93	0.00	0.018	0.000	5.229	0.00	8.34
15.00	Step bolts	Yes	5.00	0.000	0.63	1.04	0.00	0.018	0.000	5.229	0.00	13.95
20.00	Safety Cable	Yes	5.00	0.000	0.38	0.95	0.00	0.018	0.000	5.537	0.00	8.67
20.00	Step bolts	Yes	5.00	0.000	0.63	1.06	0.00	0.018	0.000	5.537	0.00	14.31
25.00	Safety Cable	Yes	5.00	0.000	0.38	0.97	0.00	0.018	0.000	5.792	0.00	8.94
25.00	Step bolts	Yes	5.00	0.000	0.63	1.08	0.00	0.018	0.000	5.792	0.00	14.60
30.00	Safety Cable	Yes	5.00	0.000	0.38	0.99	0.00	0.019	0.000	6.011	0.00	9.18
30.00	Step bolts	Yes	5.00	0.000	0.63	1.09	0.00	0.019	0.000	6.011	0.00	14.85
35.00	Safety Cable	Yes	5.00	0.000	0.38	1.00	0.00	0.019	0.000	6.203	0.00	9.38
35.00	Step bolts	Yes	5.00	0.000	0.63	1.10	0.00	0.019	0.000	6.203	0.00	15.07
40.00	Safety Cable	Yes	5.00	0.000	0.38	1.01	0.00	0.020	0.000	6.375	0.00	9.57
40.00	Step bolts	Yes	5.00	0.000	0.63	1.11	0.00	0.020	0.000	6.375	0.00	15.27
45.00	Safety Cable	Yes	5.00	0.000	0.38	1.02	0.00	0.020	0.000	6.531	0.00	9.73
45.00	Step bolts	Yes	5.00	0.000	0.63	1.12	0.00	0.020	0.000	6.531	0.00	15.44
46.50	Safety Cable	Yes	1.50	0.000	0.38	0.31	0.00	0.021	0.000	6.576	0.00	2.93
46.50	Step bolts	Yes	1.50	0.000	0.63	0.34	0.00	0.021	0.000	6.576	0.00	4.65
50.00	Safety Cable	Yes	3.50	0.000	0.38	0.72	0.00	0.021	0.000	6.675	0.00	6.92
50.00	Step bolts	Yes	3.50	0.000	0.63	0.79	0.00	0.021	0.000	6.675	0.00	10.92
53.25	Safety Cable	Yes	3.25	0.000	0.38	0.67	0.00	0.022	0.000	6.762	0.00	6.48
53.25	Step bolts	Yes	3.25	0.000	0.63	0.74	0.00	0.022	0.000	6.762	0.00	10.21
55.00	Safety Cable	Yes	1.75	0.000	0.38	0.36	0.00	0.022	0.000	6.807	0.00	3.51
55.00	Step bolts	Yes	1.75	0.000	0.63	0.40	0.00	0.022	0.000	6.807	0.00	5.51
60.00	Safety Cable	Yes	5.00	0.000	0.38	1.04	0.00	0.022	0.000	6.931	0.00	10.15
60.00	Step bolts	Yes	5.00	0.000	0.63	1.15	0.00	0.022	0.000	6.931	0.00	15.89
65.00	Safety Cable	Yes	5.00	0.000	0.38	1.05	0.00	0.023	0.000	7.047	0.00	10.28
65.00	Step bolts	Yes	5.00	0.000	0.63	1.16	0.00	0.023	0.000	7.047	0.00	16.03
70.00	Safety Cable	Yes	5.00	0.000	0.38	1.06	0.00	0.023	0.000	7.156	0.00	10.39
70.00	Step bolts	Yes	5.00	0.000	0.63	1.16	0.00	0.023	0.000	7.156	0.00	16.15
75.00	Safety Cable	Yes	5.00	0.000	0.38	1.06	0.00	0.024	0.000	7.259	0.00	10.50
75.00	Step bolts	Yes	5.00	0.000	0.63	1.17	0.00	0.024	0.000	7.259	0.00	16.26
80.00	Safety Cable	Yes	5.00	0.000	0.38	1.07	0.00	0.025	0.000	7.357	0.00	10.60
80.00	Step bolts	Yes	5.00	0.000	0.63	1.17	0.00	0.025	0.000	7.357	0.00	16.37
85.00	Safety Cable	Yes	5.00	0.000	0.38	1.08	0.00	0.026	0.000	7.451	0.00	10.70
85.00	Step bolts	Yes	5.00	0.000	0.63	1.18	0.00	0.026	0.000	7.451	0.00	16.48
90.00	Safety Cable	Yes	5.00	0.000	0.38	1.08	0.00	0.027	0.000	7.540	0.00	10.79
90.00	Step bolts	Yes	5.00	0.000	0.63	1.18	0.00	0.027	0.000	7.540	0.00	16.58
95.00	Safety Cable	Yes	5.00	0.000	0.38	1.09	0.00	0.028	0.000	7.625	0.00	10.88
95.00	Step bolts	Yes	5.00	0.000	0.63	1.19	0.00	0.028	0.000	7.625	0.00	16.67
100.00	Safety Cable	Yes	5.00	0.000	0.38	1.09	0.00	0.029	0.000	7.707	0.00	10.97
100.00	Step bolts	Yes	5.00	0.000	0.63	1.19	0.00	0.029	0.000	7.707	0.00	16.76
105.00	Safety Cable	Yes	5.00	0.000	0.38	1.09	0.00	0.029	0.000	7.786	0.00	11.05
105.00	Step bolts	Yes	5.00	0.000	0.63	1.20	0.00	0.029	0.000	7.786	0.00	16.85
110.00	Safety Cable	Yes	5.00	0.000	0.38	1.10	0.00	0.031	0.000	7.862	0.00	11.13


Linear Appurtenance Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 24

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
110.00	Step bolts	Yes	5.00	0.000	0.63	1.20	0.00	0.031	0.000	7.862	0.00	16.93
115.00	Safety Cable	Yes	5.00	0.000	0.38	1.10	0.00	0.032	0.000	7.935	0.00	11.21
115.00	Step bolts	Yes	5.00	0.000	0.63	1.21	0.00	0.032	0.000	7.935	0.00	17.01
115.00	Step bolts	Yes	5.00	0.000	0.63	1.21	0.00	0.034	0.000	8.006	0.00	11.28
120.00	Safety Cable	Yes	5.00	0.000	0.38	1.11	0.00	0.034	0.000	8.006	0.00	17.09
120.00	Step bolts	Yes	5.00	0.000	0.63	1.21	0.00	0.035	0.000	8.075	0.00	11.35
125.00	Safety Cable	Yes	5.00	0.000	0.38	1.11	0.00	0.035	0.000	8.075	0.00	17.17
125.00	Step bolts	Yes	5.00	0.000	0.63	1.22	0.00	0.035	0.000	8.075	0.00	17.17
130.00	Safety Cable	Yes	5.00	0.000	0.38	1.11	0.00	0.037	0.000	8.141	0.00	11.42
130.00	Step bolts	Yes	5.00	0.000	0.63	1.22	0.00	0.037	0.000	8.141	0.00	17.24
134.00	Safety Cable	Yes	4.00	0.000	0.38	0.89	0.00	0.039	0.000	8.193	0.00	9.18
134.00	Step bolts	Yes	4.00	0.000	0.63	0.98	0.00	0.039	0.000	8.193	0.00	13.84
135.00	Safety Cable	Yes	1.00	0.000	0.38	0.22	0.00	0.040	0.000	8.206	0.00	2.30
135.00	Step bolts	Yes	1.00	0.000	0.63	0.24	0.00	0.040	0.000	8.206	0.00	3.46
140.00	Safety Cable	Yes	5.00	0.000	0.38	1.12	0.00	0.041	0.000	8.268	0.00	11.55
140.00	Step bolts	Yes	5.00	0.000	0.63	1.23	0.00	0.041	0.000	8.268	0.00	17.38
145.00	Safety Cable	Yes	5.00	0.000	0.38	1.13	0.00	0.044	0.000	8.329	0.00	11.61
145.00	Step bolts	Yes	5.00	0.000	0.63	1.23	0.00	0.044	0.000	8.329	0.00	17.45
145.25	Safety Cable	Yes	0.25	0.000	0.38	0.06	0.00	0.045	0.000	8.332	0.00	0.58
145.25	Step bolts	Yes	0.25	0.000	0.63	0.06	0.00	0.045	0.000	8.332	0.00	0.87
146.00	Safety Cable	Yes	0.75	0.000	0.38	0.17	0.00	0.045	0.000	8.341	0.00	1.74
146.00	Step bolts	Yes	0.75	0.000	0.63	0.18	0.00	0.045	0.000	8.341	0.00	2.62
148.50	Safety Cable	Yes	2.50	0.000	0.38	0.56	0.00	0.046	0.000	8.371	0.00	5.83
148.50	Step bolts	Yes	2.50	0.000	0.63	0.62	0.00	0.046	0.000	8.371	0.00	8.75
150.00	Safety Cable	Yes	1.50	0.000	0.38	0.34	0.00	0.046	0.000	8.388	0.00	3.50
150.00	Step bolts	Yes	1.50	0.000	0.63	0.37	0.00	0.046	0.000	8.388	0.00	5.25
155.00	Safety Cable	Yes	5.00	0.000	0.38	1.13	0.00	0.049	0.000	8.446	0.00	11.73
155.00	Step bolts	Yes	5.00	0.000	0.63	1.24	0.00	0.049	0.000	8.446	0.00	17.58
159.00	Safety Cable	Yes	4.00	0.000	0.38	0.91	0.00	0.052	0.000	8.491	0.00	9.42
159.00	Step bolts	Yes	4.00	0.000	0.63	0.99	0.00	0.052	0.000	8.491	0.00	14.10
160.00	Safety Cable	Yes	1.00	0.000	0.38	0.23	0.00	0.053	0.000	8.502	0.00	2.36
160.00	Step bolts	Yes	1.00	0.000	0.63	0.25	0.00	0.053	0.000	8.502	0.00	3.53
165.00	Safety Cable	Yes	5.00	0.000	0.38	1.14	0.00	0.056	0.000	8.557	0.00	11.85
165.00	Step bolts	Yes	5.00	0.000	0.63	1.24	0.00	0.056	0.000	8.557	0.00	17.70
169.00	Safety Cable	Yes	4.00	0.000	0.38	0.91	0.00	0.060	0.000	8.600	0.00	9.51
169.00	Step bolts	Yes	4.00	0.000	0.63	1.00	0.00	0.060	0.000	8.600	0.00	14.20
Totals:											0.0	900.0

Calculated Forces

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 26

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 24

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-62.25	-10.26	0.00	-1246.0	0.00	1246.08	5562.36	1454.92	7206.86	6836.50	0.00	0.000	0.000	0.194
5.00	-59.99	-10.13	0.00	-1194.8	0.00	1194.81	5482.35	1421.65	6881.06	6582.98	0.03	-0.047	0.000	0.192
10.00	-57.75	-10.00	0.00	-1144.1	0.00	1144.18	5400.13	1388.39	6562.80	6331.40	0.10	-0.094	0.000	0.191
15.00	-55.55	-9.87	0.00	-1094.1	0.00	1094.17	5315.71	1355.12	6252.07	6081.95	0.22	-0.143	0.000	0.190
20.00	-53.39	-9.74	0.00	-1044.8	0.00	1044.81	5229.08	1321.85	5948.87	5834.81	0.40	-0.194	0.000	0.189
25.00	-51.27	-9.60	0.00	-996.12	0.00	996.12	5140.25	1288.59	5653.22	5590.18	0.63	-0.246	0.000	0.188
30.00	-49.18	-9.45	0.00	-948.14	0.00	948.14	5049.20	1255.32	5365.09	5348.24	0.92	-0.299	0.000	0.187
35.00	-47.14	-9.30	0.00	-900.90	0.00	900.90	4955.95	1222.05	5084.51	5109.18	1.26	-0.354	0.000	0.186
40.00	-45.14	-9.15	0.00	-854.41	0.00	854.41	4860.49	1188.79	4811.46	4873.19	1.66	-0.410	0.000	0.185
45.00	-43.19	-8.97	0.00	-808.68	0.00	808.68	4762.82	1155.52	4545.94	4640.45	2.12	-0.468	0.000	0.183
46.50	-42.61	-8.94	0.00	-795.22	0.00	795.22	4733.09	1145.54	4467.75	4571.29	2.27	-0.487	0.000	0.183
50.00	-40.33	-8.82	0.00	-763.94	0.00	763.94	4662.94	1122.25	4287.96	4411.15	2.65	-0.529	0.000	0.182
53.25	-38.25	-8.70	0.00	-735.28	0.00	735.28	4662.03	1121.95	4285.67	4409.10	3.02	-0.570	0.000	0.175
55.00	-37.59	-8.65	0.00	-720.06	0.00	720.06	4626.54	1110.31	4197.18	4329.70	3.23	-0.592	0.000	0.174
60.00	-35.74	-8.49	0.00	-676.79	0.00	676.79	4523.67	1077.04	3949.44	4105.38	3.89	-0.652	0.000	0.173
65.00	-33.93	-8.32	0.00	-634.35	0.00	634.35	4418.66	1043.78	3709.24	3885.01	4.60	-0.714	0.000	0.171
70.00	-32.17	-8.16	0.00	-592.74	0.00	592.74	4277.83	1010.51	3476.57	3640.10	5.38	-0.777	0.000	0.170
75.00	-30.45	-7.99	0.00	-551.96	0.00	551.96	4137.00	977.25	3251.43	3403.17	6.23	-0.842	0.000	0.170
80.00	-28.78	-7.83	0.00	-512.00	0.00	512.00	3996.18	943.98	3033.84	3174.21	7.15	-0.909	0.000	0.169
85.00	-27.16	-7.67	0.00	-472.86	0.00	472.86	3855.35	910.71	2823.78	2953.23	8.14	-0.977	0.000	0.167
90.00	-25.58	-7.50	0.00	-434.53	0.00	434.53	3714.52	877.45	2621.25	2740.21	9.20	-1.048	0.000	0.166
95.00	-24.05	-7.34	0.00	-397.01	0.00	397.01	3573.69	844.18	2426.26	2535.17	10.34	-1.120	0.000	0.163
100.00	-21.72	-7.16	0.00	-360.29	0.00	360.29	3014.30	712.04	2013.83	2107.62	11.55	-1.194	0.000	0.178
105.00	-20.39	-7.01	0.00	-324.47	0.00	324.47	2893.59	683.53	1855.77	1941.32	12.84	-1.269	0.000	0.174
110.00	-19.11	-6.85	0.00	-289.43	0.00	289.43	2772.88	655.01	1704.17	1781.85	14.21	-1.352	0.000	0.169
115.00	-17.86	-6.70	0.00	-255.16	0.00	255.16	2652.17	626.50	1559.02	1629.21	15.67	-1.436	0.000	0.163
120.00	-16.66	-6.55	0.00	-221.64	0.00	221.64	2531.46	597.98	1420.34	1483.41	17.22	-1.519	0.000	0.156
125.00	-15.50	-6.41	0.00	-188.87	0.00	188.87	2410.75	569.47	1288.11	1344.44	18.86	-1.602	0.000	0.147
130.00	-14.38	-6.26	0.00	-156.84	0.00	156.84	2290.04	540.95	1162.35	1212.31	20.58	-1.683	0.000	0.136
134.00	-8.73	-5.38	0.00	-131.80	0.00	131.80	2193.47	518.14	1066.39	1111.53	22.02	-1.746	0.000	0.123
135.00	-8.51	-5.36	0.00	-126.42	0.00	126.42	2169.33	512.44	1043.04	1087.01	22.39	-1.762	0.000	0.120
140.00	-7.49	-5.21	0.00	-99.64	0.00	99.64	2048.62	483.93	930.19	968.55	24.27	-1.834	0.000	0.107
145.00	-6.51	-5.07	0.00	-73.59	0.00	73.59	1927.91	455.41	823.80	856.92	26.23	-1.900	0.000	0.089
145.25	-6.46	-5.06	0.00	-72.33	0.00	72.33	1921.88	453.99	818.65	851.51	26.33	-1.903	0.000	0.088
146.00	-6.50	-3.90	0.00	-68.53	0.00	68.53	1903.77	449.71	803.30	835.41	26.63	-1.913	0.000	0.086
148.50	-5.94	-3.83	0.00	-58.79	0.00	58.79	907.84	223.60	397.18	399.56	27.64	-1.943	0.000	0.154
150.00	-5.75	-3.79	0.00	-53.05	0.00	53.05	895.57	219.32	382.13	386.55	28.25	-1.961	0.000	0.144
155.00	-5.17	-3.67	0.00	-34.09	0.00	34.09	853.23	205.07	334.07	344.13	30.36	-2.050	0.000	0.105
159.00	-3.30	-2.00	0.00	-19.40	0.00	19.40	817.77	193.66	297.94	311.31	32.10	-2.103	0.000	0.066
160.00	-3.21	-1.98	0.00	-17.40	0.00	17.40	807.76	190.81	289.23	302.92	32.54	-2.114	0.000	0.062
165.00	-2.77	-1.87	0.00	-7.50	0.00	7.50	747.41	176.55	247.62	259.13	34.78	-2.153	0.000	0.033
169.00	0.00	-1.76	0.00	-0.02	0.00	0.02	699.12	165.15	216.66	226.56	36.59	-2.165	0.000	0.000

Seismic Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 27

Load Case: 1.2D + 1.0Ev + 1.0Eh

Gust Response Factor 1.10


Dead Load Factor 1.20 **Seismic Load Factor** 1.00

Wind Load Factor 0.00 **Structure Frequency (f1)** 0.30

Sds 0.21

Sd1 0.08

SA 0.03



Iterations 22

Ss 0.20

S1 0.05

Seismic Importance Factor 1.00


Top Elev (ft)	Description	Wz (lb)	Hz (lb)	Vertical Ev (lb)	Lateral Fs (lb)	R: 1.50
0.00		0.00	0.00	0.00	0.00	
5.00		1644.6	2.50	68.42	0.01	
10.00		1612.3	7.50	67.07	0.07	
15.00		1580.1	12.50	65.73	0.20	
20.00		1547.8	17.50	64.39	0.37	
25.00		1515.6	22.50	63.05	0.59	
30.00		1483.3	27.50	61.71	0.84	
35.00		1451.1	32.50	60.37	1.12	
40.00		1418.8	37.50	59.02	1.42	
45.00		1386.6	42.50	57.68	1.75	
46.50	Bot - Section 2	409.70	45.75	17.04	0.18	
50.00		1728.6	48.25	71.91	3.50	
53.25	Top - Section 1	1576.8	51.63	65.60	3.33	
55.00		466.31	54.13	19.40	0.32	
60.00		1310.5	57.50	54.52	2.86	
65.00		1278.2	62.50	53.18	3.21	
70.00		1246.0	67.50	51.84	3.56	
75.00		1213.7	72.50	50.49	3.90	
80.00		1181.5	77.50	49.15	4.22	
85.00		1149.2	82.50	47.81	4.52	
90.00		1117.0	87.50	46.47	4.81	
95.00	Bot - Section 3	1084.7	92.50	45.13	5.07	
100.00	Top - Section 2	1756.6	97.50	73.08	14.76	
105.00		926.73	102.50	38.55	4.54	
110.00		899.09	107.50	37.40	4.70	
115.00		871.45	112.50	36.25	4.84	
120.00		843.80	117.50	35.10	4.95	
125.00		816.16	122.50	33.95	5.03	
130.00		788.52	127.50	32.80	5.09	
134.00	Appurtenance(s)	3048.8	132.00	126.83	81.48	
135.00		148.64	134.50	6.18	0.20	
140.00		726.63	137.50	30.23	5.02	
145.00		698.99	142.50	29.08	4.99	
145.25	Bot - Section 4	34.22	145.13	1.42	0.01	
146.00	Appurtenance(s)	3300.5	145.63	137.30	116.23	
148.50	Top - Section 3	403.31	147.25	16.78	1.77	
150.00		111.61	149.25	4.64	0.14	
155.00		363.05	152.50	15.10	1.54	
159.00	Appurtenance(s)	4024.5	157.00	167.42	200.86	
160.00		52.18	159.50	2.17	0.03	
165.00		252.61	162.50	10.51	0.85	
169.00	Appurtenance(s)	4257.0	167.00	177.09	254.29	
Totals:		51,727.8		2,151.9	757.1	Total Wind: 43,426.9

Calculated Forces

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 28



Load Case: 1.2D + 1.0Ev + 1.0Eh		Iterations 22
Gust Response Factor 1.10	Sds 0.21	Ss 0.20
Dead Load Factor 1.20	Seismic Load Factor 1.00	S1 0.05
Wind Load Factor 0.00	Structure Frequency (f1) 0.30	SA 0.03
		Seismic Importance Factor 1.00




Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-62.66	-0.76	0.00	-120.61	0.00	120.61	5562.36	1454.92	7206.86	6836.50	0.00	0.00	0.00	0.029
5.00	-60.66	-0.76	0.00	-116.82	0.00	116.82	5482.35	1421.65	6881.06	6582.98	0.00	0.00	0.00	0.029
10.00	-58.71	-0.77	0.00	-113.00	0.00	113.00	5400.13	1388.39	6562.80	6331.40	0.01	-0.01	-0.01	0.029
15.00	-56.80	-0.77	0.00	-109.16	0.00	109.16	5315.71	1355.12	6252.07	6081.95	0.02	-0.02	-0.02	0.029
20.00	-54.93	-0.78	0.00	-105.29	0.00	105.29	5229.08	1321.85	5948.87	5834.81	0.04	-0.04	-0.04	0.029
25.00	-53.10	-0.78	0.00	-101.41	0.00	101.41	5140.25	1288.59	5653.22	5590.18	0.06	-0.06	-0.06	0.028
30.00	-51.30	-0.78	0.00	-97.51	0.00	97.51	5049.20	1255.32	5365.09	5348.24	0.09	-0.09	-0.09	0.028
35.00	-49.55	-0.79	0.00	-93.59	0.00	93.59	4955.95	1222.05	5084.51	5109.18	0.12	-0.12	-0.12	0.028
40.00	-47.84	-0.79	0.00	-89.66	0.00	89.66	4860.49	1188.79	4811.46	4873.19	0.17	-0.17	-0.17	0.028
45.00	-46.17	-0.79	0.00	-85.72	0.00	85.72	4762.82	1155.52	4545.94	4640.45	0.21	-0.21	-0.21	0.028
46.50	-45.68	-0.79	0.00	-84.54	0.00	84.54	4733.09	1145.54	4467.75	4571.29	0.23	-0.23	-0.23	0.028
50.00	-43.56	-0.79	0.00	-81.77	0.00	81.77	4662.94	1122.25	4287.96	4411.15	0.27	-0.27	-0.27	0.028
53.25	-41.64	-0.79	0.00	-79.20	0.00	79.20	4662.03	1121.95	4285.67	4409.10	0.30	-0.30	-0.30	0.027
55.00	-41.08	-0.79	0.00	-77.83	0.00	77.83	4626.54	1110.31	4197.18	4329.70	0.33	-0.33	-0.33	0.027
60.00	-39.50	-0.79	0.00	-73.88	0.00	73.88	4523.67	1077.04	3949.44	4105.38	0.39	-0.39	-0.39	0.027
65.00	-37.96	-0.79	0.00	-69.94	0.00	69.94	4418.66	1043.78	3709.24	3885.01	0.47	-0.47	-0.47	0.027
70.00	-36.47	-0.79	0.00	-66.00	0.00	66.00	4277.83	1010.51	3476.57	3640.10	0.55	-0.55	-0.55	0.027
75.00	-35.01	-0.79	0.00	-62.07	0.00	62.07	4137.00	977.25	3251.43	3403.17	0.64	-0.64	-0.64	0.027
80.00	-33.59	-0.78	0.00	-58.14	0.00	58.14	3996.18	943.98	3033.84	3174.21	0.73	-0.73	-0.73	0.027
85.00	-32.21	-0.78	0.00	-54.22	0.00	54.22	3855.35	910.71	2823.78	2953.23	0.84	-0.84	-0.84	0.027
90.00	-30.88	-0.78	0.00	-50.32	0.00	50.32	3714.52	877.45	2621.25	2740.21	0.95	-0.95	-0.95	0.027
95.00	-29.58	-0.77	0.00	-46.43	0.00	46.43	3573.69	844.18	2426.26	2535.17	1.07	-1.07	-1.07	0.027
100.00	-27.45	-0.76	0.00	-42.55	0.00	42.55	3014.30	712.04	2013.83	2107.62	1.20	-1.20	-1.20	0.029
105.00	-26.35	-0.76	0.00	-38.75	0.00	38.75	2893.59	683.53	1855.77	1941.32	1.34	-1.34	-1.34	0.029
110.00	-25.28	-0.75	0.00	-34.97	0.00	34.97	2772.88	655.01	1704.17	1781.85	1.49	-1.49	-1.49	0.029
115.00	-24.25	-0.75	0.00	-31.20	0.00	31.20	2652.17	626.50	1559.02	1629.21	1.65	-1.65	-1.65	0.028
120.00	-23.25	-0.75	0.00	-27.45	0.00	27.45	2531.46	597.98	1420.34	1483.41	1.82	-1.82	-1.82	0.028
125.00	-22.29	-0.74	0.00	-23.71	0.00	23.71	2410.75	569.47	1288.11	1344.44	2.01	-2.01	-2.01	0.027
130.00	-21.36	-0.74	0.00	-19.99	0.00	19.99	2290.04	540.95	1162.35	1212.31	2.20	-2.20	-2.20	0.026
134.00	-17.62	-0.65	0.00	-17.04	0.00	17.04	2193.47	518.14	1066.39	1111.53	2.36	-2.36	-2.36	0.023
135.00	-17.44	-0.65	0.00	-16.39	0.00	16.39	2169.33	512.44	1043.04	1087.01	2.40	-2.40	-2.40	0.023
140.00	-16.59	-0.64	0.00	-13.15	0.00	13.15	2048.62	483.93	930.19	968.55	2.62	-2.62	-2.62	0.022
145.00	-15.77	-0.64	0.00	-9.95	0.00	9.95	1927.91	455.41	823.80	856.92	2.84	-2.84	-2.84	0.020
145.25	-15.73	-0.64	0.00	-9.79	0.00	9.79	1921.88	453.99	818.65	851.51	2.85	-2.85	-2.85	0.020
146.00	-11.64	-0.50	0.00	-9.31	0.00	9.31	1903.77	449.71	803.30	835.41	2.88	-2.88	-2.88	0.017
148.50	-11.15	-0.50	0.00	-8.05	0.00	8.05	907.84	223.60	397.18	399.56	3.00	-3.00	-3.00	0.032
150.00	-11.02	-0.50	0.00	-7.30	0.00	7.30	895.57	219.32	382.13	386.55	3.07	-3.07	-3.07	0.031
155.00	-10.60	-0.50	0.00	-4.79	0.00	4.79	853.23	205.07	334.07	344.13	3.31	-3.31	-3.31	0.026
159.00	-5.63	-0.28	0.00	-2.79	0.00	2.79	817.77	193.66	297.94	311.31	3.52	-3.52	-3.52	0.016
160.00	-5.57	-0.28	0.00	-2.51	0.00	2.51	807.76	190.81	289.23	302.92	3.57	-3.57	-3.57	0.015
165.00	-5.27	-0.28	0.00	-1.11	0.00	1.11	747.41	176.55	247.62	259.13	3.83	-3.83	-3.83	0.011
169.00	0.00	-0.25	0.00	0.00	0.00	0.00	699.12	165.15	216.66	226.56	4.04	-4.04	-4.04	0.000

Seismic Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 0.9D + 1.0Ev + 1.0Eh				Iterations 22
Gust Response Factor	1.10	Sds	0.21	Ss 0.20
Dead Load Factor	0.90	Seismic Load Factor	1.00	S1 0.05
Wind Load Factor	0.00	Structure Frequency (f1)	0.30	SA 0.03
			Seismic Importance Factor	1.00



Top Elev (ft)	Description	Wz (lb)	Hz (lb)	Vertical Ev (lb)	Lateral Fs (lb)	R: 1.50
0.00		0.00	0.00	0.00	0.00	
5.00		1582.0	2.50	65.81	0.01	
10.00		1549.8	7.50	64.47	0.07	
15.00		1517.5	12.50	63.13	0.19	
20.00		1485.3	17.50	61.79	0.35	
25.00		1453.0	22.50	60.45	0.55	
30.00		1420.8	27.50	59.11	0.79	
35.00		1388.5	32.50	57.76	1.05	
40.00		1356.3	37.50	56.42	1.34	
45.00		1324.0	42.50	55.08	1.64	
46.50	Bot - Section 2	390.93	45.75	16.26	0.17	
50.00		1684.8	48.25	70.09	3.41	
53.25	Top - Section 1	1536.1	51.63	63.91	3.25	
55.00		444.41	54.13	18.49	0.30	
60.00		1247.9	57.50	51.92	2.66	
65.00		1215.7	62.50	50.57	2.98	
70.00		1183.4	67.50	49.23	3.30	
75.00		1151.2	72.50	47.89	3.60	
80.00		1118.9	77.50	46.55	3.89	
85.00		1086.7	82.50	45.21	4.15	
90.00		1054.4	87.50	43.87	4.40	
95.00	Bot - Section 3	1022.2	92.50	42.52	4.62	
100.00	Top - Section 2	1694.0	97.50	70.47	14.10	
105.00		864.17	102.50	35.95	4.05	
110.00		836.52	107.50	34.80	4.18	
115.00		808.88	112.50	33.65	4.28	
120.00		781.24	117.50	32.50	4.35	
125.00		753.59	122.50	31.35	4.40	
130.00		725.95	127.50	30.20	4.43	
134.00	Appurtenance(s)	2998.7	132.00	124.75	80.96	
135.00		136.46	134.50	5.68	0.17	
140.00		665.71	137.50	27.69	4.33	
145.00		638.07	142.50	26.54	4.27	
145.25	Bot - Section 4	31.18	145.13	1.30	0.01	
146.00	Appurtenance(s)	3291.4	145.63	136.92	118.71	
148.50	Top - Section 3	383.65	147.25	15.96	1.65	
150.00		99.81	149.25	4.15	0.11	
155.00		323.72	152.50	13.47	1.26	
159.00	Appurtenance(s)	3993.0	157.00	166.11	203.07	
160.00		48.45	159.50	2.02	0.03	
165.00		233.97	162.50	9.73	0.75	
169.00	Appurtenance(s)	4242.1	167.00	176.47	259.33	
Totals:		49,765.3		2,070.2	757.1	Total Wind: 43,426.9

Calculated Forces

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 0.9D + 1.0Ev + 1.0Eh		Iterations 22
Gust Response Factor 1.10	Sds 0.21	Ss 0.20
Dead Load Factor 0.90	Seismic Load Factor 1.00	S1 0.05
Wind Load Factor 0.00	Structure Frequency (f1) 0.30	SA 0.03
	Seismic Importance Factor 1.00	



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-47.45	-0.76	0.00	-119.17	0.00	119.17	5562.36	1454.92	7206.86	6836.50	0.00	0.00	0.00	0.026
5.00	-45.94	-0.76	0.00	-115.38	0.00	115.38	5482.35	1421.65	6881.06	6582.98	0.00	0.00	0.00	0.026
10.00	-44.46	-0.77	0.00	-111.57	0.00	111.57	5400.13	1388.39	6562.80	6331.40	0.01	-0.01	0.026	0.026
15.00	-43.01	-0.77	0.00	-107.74	0.00	107.74	5315.71	1355.12	6252.07	6081.95	0.02	-0.01	0.026	0.026
20.00	-41.60	-0.77	0.00	-103.90	0.00	103.90	5229.08	1321.85	5948.87	5834.81	0.04	-0.02	0.026	0.026
25.00	-40.21	-0.77	0.00	-100.05	0.00	100.05	5140.25	1288.59	5653.22	5590.18	0.06	-0.02	0.026	0.026
30.00	-38.85	-0.78	0.00	-96.18	0.00	96.18	5049.20	1255.32	5365.09	5348.24	0.09	-0.03	0.026	0.026
35.00	-37.53	-0.78	0.00	-92.30	0.00	92.30	4955.95	1222.05	5084.51	5109.18	0.12	-0.04	0.026	0.026
40.00	-36.23	-0.78	0.00	-88.40	0.00	88.40	4860.49	1188.79	4811.46	4873.19	0.16	-0.04	0.026	0.026
45.00	-34.96	-0.78	0.00	-84.51	0.00	84.51	4762.82	1155.52	4545.94	4640.45	0.21	-0.05	0.026	0.026
46.50	-34.59	-0.78	0.00	-83.34	0.00	83.34	4733.09	1145.54	4467.75	4571.29	0.22	-0.05	0.026	0.026
50.00	-32.99	-0.78	0.00	-80.60	0.00	80.60	4662.94	1122.25	4287.96	4411.15	0.26	-0.05	0.025	0.025
53.25	-31.53	-0.78	0.00	-78.07	0.00	78.07	4662.03	1121.95	4285.67	4409.10	0.30	-0.06	0.024	0.024
55.00	-31.11	-0.78	0.00	-76.71	0.00	76.71	4626.54	1110.31	4197.18	4329.70	0.32	-0.06	0.024	0.024
60.00	-29.91	-0.78	0.00	-72.83	0.00	72.83	4523.67	1077.04	3949.44	4105.38	0.39	-0.07	0.024	0.024
65.00	-28.75	-0.78	0.00	-68.94	0.00	68.94	4418.66	1043.78	3709.24	3885.01	0.46	-0.07	0.024	0.024
70.00	-27.62	-0.77	0.00	-65.06	0.00	65.06	4277.83	1010.51	3476.57	3640.10	0.54	-0.08	0.024	0.024
75.00	-26.51	-0.77	0.00	-61.19	0.00	61.19	4137.00	977.25	3251.43	3403.17	0.63	-0.09	0.024	0.024
80.00	-25.44	-0.77	0.00	-57.32	0.00	57.32	3996.18	943.98	3033.84	3174.21	0.72	-0.09	0.024	0.024
85.00	-24.40	-0.77	0.00	-53.47	0.00	53.47	3855.35	910.71	2823.78	2953.23	0.83	-0.10	0.024	0.024
90.00	-23.39	-0.77	0.00	-49.63	0.00	49.63	3714.52	877.45	2621.25	2740.21	0.94	-0.11	0.024	0.024
95.00	-22.41	-0.76	0.00	-45.81	0.00	45.81	3573.69	844.18	2426.26	2535.17	1.06	-0.12	0.024	0.024
100.00	-20.79	-0.75	0.00	-42.00	0.00	42.00	3014.30	712.04	2013.83	2107.62	1.19	-0.13	0.027	0.027
105.00	-19.96	-0.74	0.00	-38.26	0.00	38.26	2893.59	683.53	1855.77	1941.32	1.32	-0.14	0.027	0.027
110.00	-19.15	-0.74	0.00	-34.54	0.00	34.54	2772.88	655.01	1704.17	1781.85	1.47	-0.15	0.026	0.026
115.00	-18.37	-0.74	0.00	-30.83	0.00	30.83	2652.17	626.50	1559.02	1629.21	1.63	-0.16	0.026	0.026
120.00	-17.62	-0.74	0.00	-27.13	0.00	27.13	2531.46	597.98	1420.34	1483.41	1.80	-0.17	0.025	0.025
125.00	-16.89	-0.73	0.00	-23.46	0.00	23.46	2410.75	569.47	1288.11	1344.44	1.98	-0.18	0.024	0.024
130.00	-16.19	-0.73	0.00	-19.80	0.00	19.80	2290.04	540.95	1162.35	1212.31	2.17	-0.19	0.023	0.023
134.00	-13.35	-0.64	0.00	-16.88	0.00	16.88	2193.47	518.14	1066.39	1111.53	2.33	-0.19	0.021	0.021
135.00	-13.22	-0.64	0.00	-16.25	0.00	16.25	2169.33	512.44	1043.04	1087.01	2.37	-0.20	0.021	0.021
140.00	-12.57	-0.63	0.00	-13.05	0.00	13.05	2048.62	483.93	930.19	968.55	2.58	-0.21	0.020	0.020
145.00	-11.95	-0.63	0.00	-9.87	0.00	9.87	1927.91	455.41	823.80	856.92	2.80	-0.21	0.018	0.018
145.25	-11.92	-0.63	0.00	-9.72	0.00	9.72	1921.88	453.99	818.65	851.51	2.81	-0.21	0.018	0.018
146.00	-8.82	-0.50	0.00	-9.24	0.00	9.24	1903.77	449.71	803.30	835.41	2.85	-0.22	0.016	0.016
148.50	-8.45	-0.50	0.00	-8.00	0.00	8.00	907.84	223.60	397.18	399.56	2.96	-0.22	0.029	0.029
150.00	-8.36	-0.50	0.00	-7.25	0.00	7.25	895.57	219.32	382.13	386.55	3.03	-0.22	0.028	0.028
155.00	-8.04	-0.50	0.00	-4.76	0.00	4.76	853.23	205.07	334.07	344.13	3.27	-0.23	-0.023	-0.023
159.00	-4.27	-0.28	0.00	-2.78	0.00	2.78	817.77	193.66	297.94	311.31	3.47	-0.24	0.014	0.014
160.00	-4.22	-0.28	0.00	-2.50	0.00	2.50	807.76	190.81	289.23	302.92	3.52	-0.24	0.013	0.013
165.00	-4.00	-0.28	0.00	-1.11	0.00	1.11	747.41	176.55	247.62	259.13	3.78	-0.25	0.010	0.010
169.00	0.00	-0.26	0.00	0.00	0.00	0.00	699.12	165.15	216.66	226.56	3.99	-0.25	0.000	0.000

Wind Loading - Shaft

Structure: CT11794-S

Code: TIA-222-H

1/11/2024

Site Name: East Lyme 1

Exposure: C

Height: 169.00 (ft)

Crest Height: 0.00

Base Elev: 1.000 (ft)

Site Class: D - Stiff Soil

Gh: 1.1

Topography: 1

Struct Class: II

Page: 31



Load Case: 1.0D + 1.0W 60 mph Wind

Iterations 24

Dead Load Factor 1.00

Wind Load Factor 1.00



Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.85	6.655	7.32	281.44	0.730	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	6.655	7.32	275.05	0.730	0.000	5.00	25.156	18.36	134.4	0.0	1394.4
10.00		1.00	0.85	6.655	7.32	268.66	0.730	0.000	5.00	24.579	17.94	131.4	0.0	1362.1
15.00		1.00	0.86	6.737	7.41	263.89	0.730	0.000	5.00	24.001	17.52	129.9	0.0	1329.8
20.00		1.00	0.91	7.134	7.85	264.94	0.730	0.000	5.00	23.423	17.10	134.2	0.0	1297.6
25.00		1.00	0.95	7.463	8.21	264.20	0.730	0.000	5.00	22.846	16.68	136.9	0.0	1265.3
30.00		1.00	0.99	7.744	8.52	262.24	0.730	0.000	5.00	22.268	16.26	138.5	0.0	1233.1
35.00		1.00	1.02	7.992	8.79	259.40	0.730	0.000	5.00	21.691	15.83	139.2	0.0	1200.8
40.00		1.00	1.05	8.214	9.03	255.88	0.730	0.000	5.00	21.113	15.41	139.3	0.0	1168.6
45.00		1.00	1.07	8.415	9.26	251.82	0.730	0.000	5.00	20.536	14.99	138.8	0.0	1136.3
46.50 Bot - Section 2		1.00	1.08	8.472	9.32	250.51	0.730	0.000	1.50	6.048	4.42	41.1	0.0	334.6
50.00		1.00	1.10	8.600	9.46	247.31	0.730	0.000	3.50	14.169	10.34	97.8	0.0	1553.4
53.25 Top - Section 1		1.00	1.11	8.712	9.58	244.17	0.730	0.000	3.25	12.904	9.42	90.3	0.0	1414.2
55.00		1.00	1.12	8.771	9.65	247.12	0.730	0.000	1.75	6.847	5.00	48.2	0.0	378.7
60.00		1.00	1.14	8.930	9.82	241.95	0.730	0.000	5.00	19.173	14.00	137.5	0.0	1060.3
65.00		1.00	1.16	9.079	9.99	236.51	0.730	0.000	5.00	18.596	13.57	135.6	0.0	1028.0
70.00		1.00	1.18	9.220	10.14	230.81	0.730	0.000	5.00	18.018	13.15	133.4	0.0	995.8
75.00		1.00	1.19	9.353	10.29	224.90	0.730	0.000	5.00	17.440	12.73	131.0	0.0	963.5
80.00		1.00	1.21	9.480	10.43	218.79	0.730	0.000	5.00	16.863	12.31	128.4	0.0	931.3
85.00		1.00	1.23	9.600	10.56	212.50	0.730	0.000	5.00	16.285	11.89	125.5	0.0	899.0
90.00		1.00	1.24	9.715	10.69	206.05	0.730	0.000	5.00	15.708	11.47	122.5	0.0	866.8
95.00 Bot - Section 3		1.00	1.25	9.825	10.81	199.45	0.730	0.000	5.00	15.130	11.05	119.4	0.0	834.5
100.00 Top - Section 2		1.00	1.27	9.930	10.92	192.72	0.730	0.000	5.00	14.870	10.86	118.6	0.0	1506.4
105.00		1.00	1.28	10.032	11.03	190.17	0.730	0.000	5.00	14.292	10.43	115.1	0.0	676.5
110.00		1.00	1.29	10.130	11.14	183.21	0.730	0.000	5.00	13.715	10.01	111.6	0.0	648.8
115.00		1.00	1.31	10.224	11.25	176.14	0.730	0.000	5.00	13.137	9.59	107.9	0.0	621.2
120.00		1.00	1.32	10.315	11.35	168.97	0.730	0.000	5.00	12.560	9.17	104.0	0.0	593.5
125.00		1.00	1.33	10.404	11.44	161.71	0.730	0.000	5.00	11.982	8.75	100.1	0.0	565.9
130.00		1.00	1.34	10.489	11.54	154.35	0.730	0.000	5.00	11.405	8.33	96.1	0.0	538.3
134.00 Appurtenance(s)		1.00	1.35	10.556	11.61	148.41	0.730	0.000	4.00	8.708	6.36	73.8	0.0	410.7
135.00		1.00	1.35	10.572	11.63	146.91	0.730	0.000	1.00	2.119	1.55	18.0	0.0	99.9
140.00		1.00	1.36	10.653	11.72	139.39	0.730	0.000	5.00	10.249	7.48	87.7	0.0	483.0
145.00		1.00	1.37	10.731	11.80	131.79	0.730	0.000	5.00	9.672	7.06	83.3	0.0	455.3
145.25 Bot - Section 4		1.00	1.37	10.735	11.81	131.41	0.730	0.000	0.25	0.468	0.34	4.0	0.0	22.0
146.00 Appurtenance(s)		1.00	1.37	10.747	11.82	130.26	0.730	0.000	0.75	1.420	1.04	12.3	0.0	99.4
148.50 Top - Section 3		1.00	1.38	10.785	11.86	126.42	0.730	0.000	2.50	4.641	3.39	40.2	0.0	324.6
150.00		1.00	1.38	10.808	11.89	126.35	0.730	0.000	1.50	2.715	1.98	23.6	0.0	64.4
155.00		1.00	1.39	10.882	11.97	118.62	0.730	0.000	5.00	8.675	6.33	75.8	0.0	205.7
159.00 Appurtenance(s)		1.00	1.40	10.940	12.03	112.38	0.730	0.000	4.00	6.525	4.76	57.3	0.0	154.6
160.00		1.00	1.40	10.955	12.05	110.82	0.730	0.000	1.00	1.573	1.15	13.8	0.0	37.3
165.00		1.00	1.41	11.025	12.13	102.95	0.730	0.000	5.00	7.520	5.49	66.6	0.0	178.1
169.00 Appurtenance(s)		1.00	1.42	11.081	12.19	96.61	0.730	0.000	4.00	5.600	4.09	49.8	0.0	132.5
Totals:									169.00			3,892.7		30,466.3

Discrete Appurtenance Forces

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.0D + 1.0W 60 mph Wind	Iterations 24
Dead Load Factor 1.00	
Wind Load Factor 1.00	

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	Orient Factor x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	169.00	Ericsson RRUS A2 RRU	6	11.081	12.189	0.50	0.75	5.61	132.00	0.000	0.000	68.35	0.00	0.00
2	169.00	Ericsson AIR 6449 B77D	3	11.064	12.170	0.64	0.75	7.90	264.00	0.000	-1.250	96.13	0.00	-120.16
3	169.00	Ericsson AIR 6419 B77G	3	11.105	12.215	0.57	0.75	6.50	198.30	0.000	1.750	79.37	0.00	138.90
4	169.00	CCI TPA65R-BU4DA-K	1	11.081	12.189	0.54	0.75	6.95	67.50	0.000	0.000	84.71	0.00	0.00
5	169.00	CCI TPA65R-BU6DA-K	1	11.081	12.189	0.54	0.75	6.95	67.50	0.000	0.000	84.71	0.00	0.00
6	169.00	CCI TPA65R-BU8DA-K	1	11.081	12.189	0.54	0.75	9.65	82.50	0.000	0.000	117.62	0.00	0.00
7	169.00	Ericsson 8843 B2 B66A	3	11.081	12.189	0.50	0.75	2.47	216.00	0.000	0.000	30.13	0.00	0.00
8	169.00	Ericsson RRUS-12 RRU	6	11.081	12.189	0.50	0.75	9.50	348.00	0.000	0.000	115.76	0.00	0.00
9	169.00	Ericsson RRUS 32 RRU	3	11.081	12.189	0.50	0.75	5.83	231.00	0.000	0.000	71.11	0.00	0.00
10	169.00	mount pipe	12	11.081	12.189	0.75	0.75	12.24	360.00	0.000	0.000	149.19	0.00	0.00
11	169.00	Ericsson 4449 B5/B12	3	11.081	12.189	0.50	0.75	2.97	213.00	0.000	0.000	36.20	0.00	0.00
12	169.00	Commscope	1	11.081	12.189	0.75	0.75	13.40	79.00	0.000	0.000	163.36	0.00	0.00
13	169.00	Commscope	1	11.081	12.189	0.75	0.75	9.20	79.00	0.000	0.000	112.17	0.00	0.00
14	169.00	CCI OPA65R-BU4DA	1	11.081	12.189	0.70	0.75	3.50	43.00	0.000	0.000	42.62	0.00	0.00
15	169.00	Raycap DC6-48-60-18-8F	3	11.081	12.189	0.50	0.75	2.22	98.40	0.000	0.000	27.01	0.00	0.00
16	169.00	Ericsson RRUS 4478 B14	3	11.081	12.189	0.54	0.80	2.65	178.20	0.000	0.000	32.34	0.00	0.00
17	169.00	CCI DTMABP7819VG12A	3	11.081	12.189	0.50	0.75	1.72	57.54	0.000	0.000	20.95	0.00	0.00
18	169.00	Reinforced T-Arms	3	11.081	12.189	0.75	0.75	31.50	1350.00	0.000	0.000	383.95	0.00	0.00
19	159.00	Ericsson 4460 B25/B66A	3	10.940	12.034	0.54	0.80	2.64	216.00	0.000	0.000	31.74	0.00	0.00
20	159.00	Ericsson 4449 B71 + B85	3	10.940	12.034	0.54	0.80	3.17	219.60	0.000	0.000	38.12	0.00	0.00
21	159.00	RFS	3	10.940	12.034	0.58	0.80	35.46	368.40	0.000	0.000	426.74	0.00	0.00
22	159.00	Commscope VV-65A-R1	3	10.940	12.034	0.59	0.80	14.03	88.50	0.000	0.000	168.84	0.00	0.00
23	159.00	T-Arm	3	10.940	12.034	0.75	0.75	18.00	1200.00	0.000	0.000	216.62	0.00	0.00
24	159.00	PRK-SFS-L	1	10.940	12.034	1.00	1.00	16.60	394.00	0.000	0.000	199.77	0.00	0.00
25	159.00	PRK-1245L	1	10.940	12.034	1.00	1.00	9.50	464.91	0.000	0.000	114.32	0.00	0.00
26	159.00	Ericsson KRY 112 144/1	3	10.940	12.034	0.52	0.75	0.65	33.00	0.000	0.000	7.77	0.00	0.00
27	159.00	mount pipe	12	10.940	12.034	0.75	0.75	12.42	360.00	0.000	0.000	149.46	0.00	0.00
28	159.00	Ericsson AIR 6419 B41	3	10.940	12.034	0.56	0.80	10.97	399.60	0.000	0.000	132.02	0.00	0.00
29	146.00	JMA Wireless	6	10.747	11.821	0.65	0.75	38.64	360.00	0.000	0.000	456.79	0.00	0.00
30	146.00	mount pipe	12	10.747	11.821	0.75	0.75	13.23	360.00	0.000	0.000	156.40	0.00	0.00
31	146.00	Samsung B2/B66A RRH	3	10.747	11.821	0.63	0.75	3.53	224.13	0.000	0.000	41.78	0.00	0.00
32	146.00	Mods	1	10.747	11.821	1.00	1.00	13.79	465.04	0.000	0.000	163.02	0.00	0.00
33	146.00	Samsung RF4461d-13A	3	10.747	11.821	0.50	0.75	2.82	217.50	0.000	0.000	33.32	0.00	0.00
34	146.00	Samsung MT6413-77A	3	10.747	11.821	0.52	0.75	5.88	171.90	0.000	0.000	69.56	0.00	0.00
35	146.00	Raycap	1	10.747	11.821	0.75	0.75	3.04	32.00	0.000	0.000	36.00	0.00	0.00
36	146.00	Antenna Bracket JWA	3	10.747	11.821	1.00	1.00	0.00	84.00	0.000	0.000	0.00	0.00	0.00
37	146.00	Low Profile Platform	1	10.747	11.821	1.00	1.00	14.69	1250.00	0.000	0.000	173.66	0.00	0.00
38	134.00	Platform w/HRK	1	10.556	11.611	0.67	0.67	22.91	1736.00	0.000	0.000	265.99	0.00	0.00
39	134.00	Raycap	1	10.556	11.611	0.75	0.75	1.51	21.85	0.000	0.000	17.50	0.00	0.00
40	134.00	Samsung RF4451d-70A	3	10.556	11.611	0.50	0.75	2.83	183.90	0.000	0.000	32.91	0.00	0.00
41	134.00	Samsung RF4450t-71A	3	10.556	11.611	0.50	0.75	3.11	283.74	0.000	0.000	36.06	0.00	0.00
42	134.00	Commscope	3	10.556	11.611	0.55	0.75	20.15	212.40	0.000	0.000	234.01	0.00	0.00
Totals:									13,411.41			4,918.07		

Total Applied Force Summary


Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 33

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 24

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		134.44	1602.91	0.00	0.00
10.00		131.35	1570.65	0.00	0.00
15.00		129.85	1538.40	0.00	0.00
20.00		134.19	1506.15	0.00	0.00
25.00		136.90	1473.90	0.00	0.00
30.00		138.48	1441.65	0.00	0.00
35.00		139.20	1409.40	0.00	0.00
40.00		139.25	1377.15	0.00	0.00
45.00		138.76	1344.90	0.00	0.00
46.50		41.15	397.18	0.00	0.00
50.00		97.85	1699.42	0.00	0.00
53.25		90.27	1549.74	0.00	0.00
55.00		48.22	451.71	0.00	0.00
60.00		137.49	1268.82	0.00	0.00
65.00		135.58	1236.57	0.00	0.00
70.00		133.40	1204.32	0.00	0.00
75.00		130.99	1172.07	0.00	0.00
80.00		128.36	1139.82	0.00	0.00
85.00		125.54	1107.57	0.00	0.00
90.00		122.53	1075.32	0.00	0.00
95.00		119.37	1043.07	0.00	0.00
100.00		118.57	1714.93	0.00	0.00
105.00		115.13	885.02	0.00	0.00
110.00		111.56	857.38	0.00	0.00
115.00		107.86	829.74	0.00	0.00
120.00		104.03	802.09	0.00	0.00
125.00		100.10	774.45	0.00	0.00
130.00		96.06	746.81	0.00	0.00
134.00	(11) attachments	660.28	3015.43	0.00	0.00
135.00		17.99	140.52	0.00	0.00
140.00		87.68	686.02	0.00	0.00
145.00		83.35	658.38	0.00	0.00
145.25		4.04	32.19	0.00	0.00
146.00	(33) attachments	1142.78	3294.44	0.00	0.00
148.50		40.19	390.20	0.00	0.00
150.00		23.56	103.74	0.00	0.00
155.00		75.81	336.83	0.00	0.00
159.00	(35) attachments	1542.72	4003.52	0.00	0.00
160.00		13.84	49.70	0.00	0.00
165.00		66.58	240.18	0.00	0.00
169.00	(57) attachments	1765.51	4247.14	0.00	18.75
	Totals:	8,810.81	50,419.47	0.00	18.75

Linear Appurtenance Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 34

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00

Wind Load Factor 1.00



Iterations 24

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.017	0.000	6.655	0.00	1.37
5.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.017	0.000	6.655	0.00	5.20
10.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.017	0.000	6.655	0.00	1.37
10.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.017	0.000	6.655	0.00	5.20
15.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	6.737	0.00	1.37
15.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	6.737	0.00	5.20
20.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	7.134	0.00	1.37
20.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	7.134	0.00	5.20
25.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.018	0.000	7.463	0.00	1.37
25.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.018	0.000	7.463	0.00	5.20
30.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.019	0.000	7.744	0.00	1.37
30.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.019	0.000	7.744	0.00	5.20
35.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.019	0.000	7.992	0.00	1.37
35.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.019	0.000	7.992	0.00	5.20
40.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.020	0.000	8.214	0.00	1.37
40.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.020	0.000	8.214	0.00	5.20
45.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.020	0.000	8.415	0.00	1.37
45.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.020	0.000	8.415	0.00	5.20
46.50	Safety Cable	Yes	1.50	0.000	0.38	0.05	0.00	0.021	0.000	8.472	0.00	0.41
46.50	Step bolts	Yes	1.50	0.000	0.63	0.08	0.00	0.021	0.000	8.472	0.00	1.56
50.00	Safety Cable	Yes	3.50	0.000	0.38	0.11	0.00	0.021	0.000	8.600	0.00	0.96
50.00	Step bolts	Yes	3.50	0.000	0.63	0.18	0.00	0.021	0.000	8.600	0.00	3.64
53.25	Safety Cable	Yes	3.25	0.000	0.38	0.10	0.00	0.022	0.000	8.712	0.00	0.89
53.25	Step bolts	Yes	3.25	0.000	0.63	0.17	0.00	0.022	0.000	8.712	0.00	3.38
55.00	Safety Cable	Yes	1.75	0.000	0.38	0.06	0.00	0.022	0.000	8.771	0.00	0.48
55.00	Step bolts	Yes	1.75	0.000	0.63	0.09	0.00	0.022	0.000	8.771	0.00	1.82
60.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.022	0.000	8.930	0.00	1.37
60.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.022	0.000	8.930	0.00	5.20
65.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.023	0.000	9.079	0.00	1.37
65.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.023	0.000	9.079	0.00	5.20
70.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.023	0.000	9.220	0.00	1.37
70.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.023	0.000	9.220	0.00	5.20
75.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.024	0.000	9.353	0.00	1.37
75.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.024	0.000	9.353	0.00	5.20
80.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.025	0.000	9.480	0.00	1.37
80.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.025	0.000	9.480	0.00	5.20
85.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.026	0.000	9.600	0.00	1.37
85.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.026	0.000	9.600	0.00	5.20
90.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.027	0.000	9.715	0.00	1.37
90.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.027	0.000	9.715	0.00	5.20
95.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.028	0.000	9.825	0.00	1.37
95.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.028	0.000	9.825	0.00	5.20
100.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.029	0.000	9.930	0.00	1.37
100.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.029	0.000	9.930	0.00	5.20
105.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.029	0.000	10.032	0.00	1.37
105.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.029	0.000	10.032	0.00	5.20
110.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.031	0.000	10.130	0.00	1.37

Linear Appurtenance Segment Forces (Factored)

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 35

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 24

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
110.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.031	0.000	10.130	0.00	5.20
115.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.032	0.000	10.224	0.00	1.37
115.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.032	0.000	10.224	0.00	5.20
120.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.034	0.000	10.315	0.00	1.37
120.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.034	0.000	10.315	0.00	5.20
125.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.035	0.000	10.404	0.00	1.37
125.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.035	0.000	10.404	0.00	5.20
130.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.037	0.000	10.489	0.00	1.37
130.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.037	0.000	10.489	0.00	5.20
134.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.039	0.000	10.556	0.00	1.09
134.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.039	0.000	10.556	0.00	4.16
135.00	Safety Cable	Yes	1.00	0.000	0.38	0.03	0.00	0.040	0.000	10.572	0.00	0.27
135.00	Step bolts	Yes	1.00	0.000	0.63	0.05	0.00	0.040	0.000	10.572	0.00	1.04
140.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.041	0.000	10.653	0.00	1.37
140.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.041	0.000	10.653	0.00	5.20
145.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.044	0.000	10.731	0.00	1.37
145.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.044	0.000	10.731	0.00	5.20
145.25	Safety Cable	Yes	0.25	0.000	0.38	0.01	0.00	0.045	0.000	10.735	0.00	0.07
145.25	Step bolts	Yes	0.25	0.000	0.63	0.01	0.00	0.045	0.000	10.735	0.00	0.26
146.00	Safety Cable	Yes	0.75	0.000	0.38	0.02	0.00	0.045	0.000	10.747	0.00	0.20
146.00	Step bolts	Yes	0.75	0.000	0.63	0.04	0.00	0.045	0.000	10.747	0.00	0.78
148.50	Safety Cable	Yes	2.50	0.000	0.38	0.08	0.00	0.046	0.000	10.785	0.00	0.68
148.50	Step bolts	Yes	2.50	0.000	0.63	0.13	0.00	0.046	0.000	10.785	0.00	2.60
150.00	Safety Cable	Yes	1.50	0.000	0.38	0.05	0.00	0.046	0.000	10.808	0.00	0.41
150.00	Step bolts	Yes	1.50	0.000	0.63	0.08	0.00	0.046	0.000	10.808	0.00	1.56
155.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.049	0.000	10.882	0.00	1.37
155.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.049	0.000	10.882	0.00	5.20
159.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.052	0.000	10.940	0.00	1.09
159.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.052	0.000	10.940	0.00	4.16
160.00	Safety Cable	Yes	1.00	0.000	0.38	0.03	0.00	0.053	0.000	10.955	0.00	0.27
160.00	Step bolts	Yes	1.00	0.000	0.63	0.05	0.00	0.053	0.000	10.955	0.00	1.04
165.00	Safety Cable	Yes	5.00	0.000	0.38	0.16	0.00	0.056	0.000	11.025	0.00	1.37
165.00	Step bolts	Yes	5.00	0.000	0.63	0.26	0.00	0.056	0.000	11.025	0.00	5.20
169.00	Safety Cable	Yes	4.00	0.000	0.38	0.13	0.00	0.060	0.000	11.081	0.00	1.09
169.00	Step bolts	Yes	4.00	0.000	0.63	0.21	0.00	0.060	0.000	11.081	0.00	4.16
Totals:											0.0	221.9

Calculated Forces

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 36

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 24

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-50.42	-8.83	0.00	-1125.0	0.00	1125.07	5562.36	1454.92	7206.86	6836.50	0.00	0.000	0.000	0.174
5.00	-48.81	-8.73	0.00	-1080.9	0.00	1080.93	5482.35	1421.65	6881.06	6582.98	0.02	-0.042	0.000	0.173
10.00	-47.23	-8.63	0.00	-1037.2	0.00	1037.27	5400.13	1388.39	6562.80	6331.40	0.09	-0.085	0.000	0.173
15.00	-45.68	-8.54	0.00	-994.11	0.00	994.11	5315.71	1355.12	6252.07	6081.95	0.20	-0.130	0.000	0.172
20.00	-44.17	-8.43	0.00	-951.43	0.00	951.43	5229.08	1321.85	5948.87	5834.81	0.36	-0.176	0.000	0.172
25.00	-42.69	-8.33	0.00	-909.26	0.00	909.26	5140.25	1288.59	5653.22	5590.18	0.57	-0.223	0.000	0.171
30.00	-41.24	-8.22	0.00	-867.62	0.00	867.62	5049.20	1255.32	5365.09	5348.24	0.83	-0.272	0.000	0.170
35.00	-39.83	-8.11	0.00	-826.52	0.00	826.52	4955.95	1222.05	5084.51	5109.18	1.14	-0.322	0.000	0.170
40.00	-38.44	-8.00	0.00	-785.98	0.00	785.98	4860.49	1188.79	4811.46	4873.19	1.51	-0.374	0.000	0.169
45.00	-37.10	-7.87	0.00	-746.00	0.00	746.00	4762.82	1155.52	4545.94	4640.45	1.93	-0.427	0.000	0.169
46.50	-36.69	-7.84	0.00	-734.20	0.00	734.20	4733.09	1145.54	4467.75	4571.29	2.07	-0.444	0.000	0.168
50.00	-34.99	-7.76	0.00	-706.74	0.00	706.74	4662.94	1122.25	4287.96	4411.15	2.41	-0.484	0.000	0.168
53.25	-33.44	-7.67	0.00	-681.54	0.00	681.54	4662.03	1121.95	4285.67	4409.10	2.75	-0.521	0.000	0.162
55.00	-32.98	-7.64	0.00	-668.12	0.00	668.12	4626.54	1110.31	4197.18	4329.70	2.94	-0.542	0.000	0.161
60.00	-31.71	-7.52	0.00	-629.92	0.00	629.92	4523.67	1077.04	3949.44	4105.38	3.54	-0.597	0.000	0.160
65.00	-30.46	-7.40	0.00	-592.32	0.00	592.32	4418.66	1043.78	3709.24	3885.01	4.20	-0.655	0.000	0.159
70.00	-29.25	-7.28	0.00	-555.31	0.00	555.31	4277.83	1010.51	3476.57	3640.10	4.92	-0.714	0.000	0.159
75.00	-28.08	-7.17	0.00	-518.89	0.00	518.89	4137.00	977.25	3251.43	3403.17	5.70	-0.775	0.000	0.159
80.00	-26.93	-7.05	0.00	-483.05	0.00	483.05	3996.18	943.98	3033.84	3174.21	6.54	-0.838	0.000	0.159
85.00	-25.82	-6.94	0.00	-447.77	0.00	447.77	3855.35	910.71	2823.78	2953.23	7.45	-0.903	0.000	0.158
90.00	-24.74	-6.83	0.00	-413.06	0.00	413.06	3714.52	877.45	2621.25	2740.21	8.44	-0.970	0.000	0.157
95.00	-23.69	-6.72	0.00	-378.91	0.00	378.91	3573.69	844.18	2426.26	2535.17	9.49	-1.039	0.000	0.156
100.00	-21.97	-6.60	0.00	-345.29	0.00	345.29	3014.30	712.04	2013.83	2107.62	10.61	-1.109	0.000	0.171
105.00	-21.07	-6.49	0.00	-312.30	0.00	312.30	2893.59	683.53	1855.77	1941.32	11.81	-1.182	0.000	0.168
110.00	-20.21	-6.39	0.00	-279.83	0.00	279.83	2772.88	655.01	1704.17	1781.85	13.10	-1.262	0.000	0.164
115.00	-19.38	-6.29	0.00	-247.86	0.00	247.86	2652.17	626.50	1559.02	1629.21	14.46	-1.343	0.000	0.160
120.00	-18.57	-6.20	0.00	-216.39	0.00	216.39	2531.46	597.98	1420.34	1483.41	15.91	-1.424	0.000	0.153
125.00	-17.79	-6.10	0.00	-185.41	0.00	185.41	2410.75	569.47	1288.11	1344.44	17.45	-1.505	0.000	0.145
130.00	-17.04	-6.01	0.00	-154.90	0.00	154.90	2290.04	540.95	1162.35	1212.31	19.06	-1.584	0.000	0.135
134.00	-14.04	-5.27	0.00	-130.87	0.00	130.87	2193.47	518.14	1066.39	1111.53	20.42	-1.647	0.000	0.124
135.00	-13.89	-5.26	0.00	-125.60	0.00	125.60	2169.33	512.44	1043.04	1087.01	20.77	-1.663	0.000	0.122
140.00	-13.20	-5.17	0.00	-99.30	0.00	99.30	2048.62	483.93	930.19	968.55	22.55	-1.735	0.000	0.109
145.00	-12.54	-5.07	0.00	-73.46	0.00	73.46	1927.91	455.41	823.80	856.92	24.40	-1.800	0.000	0.092
145.25	-12.51	-5.07	0.00	-72.19	0.00	72.19	1921.88	453.99	818.65	851.51	24.49	-1.804	0.000	0.091
146.00	-9.25	-3.83	0.00	-68.39	0.00	68.39	1903.77	449.71	803.30	835.41	24.78	-1.813	0.000	0.087
148.50	-8.86	-3.78	0.00	-58.82	0.00	58.82	907.84	223.60	397.18	399.56	25.74	-1.843	0.000	0.157
150.00	-8.76	-3.76	0.00	-53.16	0.00	53.16	895.57	219.32	382.13	386.55	26.32	-1.861	0.000	0.148
155.00	-8.42	-3.68	0.00	-34.37	0.00	34.37	853.23	205.07	334.07	344.13	28.32	-1.950	0.000	0.110
159.00	-4.47	-2.00	0.00	-19.64	0.00	19.64	817.77	193.66	297.94	311.31	29.98	-2.004	0.000	0.069
160.00	-4.42	-1.99	0.00	-17.64	0.00	17.64	807.76	190.81	289.23	302.92	30.40	-2.015	0.000	0.064
165.00	-4.18	-1.92	0.00	-7.69	0.00	7.69	747.41	176.55	247.62	259.13	32.53	-2.055	0.000	0.035
169.00	0.00	-1.77	0.00	-0.02	0.00	0.02	699.12	165.15	216.66	226.56	34.26	-2.067	0.000	0.000

Final Analysis Summary

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 37



Reactions

Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)
1.2D + 1.0W 126 mph Wind	43.5	0.00	60.42	0.00	0.00	5582.17
0.9D + 1.0W 126 mph Wind	43.5	0.00	45.30	0.00	0.00	5498.20
1.2D + 1.0Di + 1.0Wi 50 mph Wind	10.3	0.00	62.25	0.00	0.00	1246.08
1.2D + 1.0Ev + 1.0Eh	0.8	0.00	62.66	0.00	0.00	120.61
0.9D + 1.0Ev + 1.0Eh	0.8	0.00	47.45	0.00	0.00	119.17
1.0D + 1.0W 60 mph Wind	8.8	0.00	50.42	0.00	0.00	1125.07

Max Stresses


Load Case	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Elev (ft)	Stress Ratio
1.2D + 1.0W 126 mph Wind	-60.42	-43.54	0.00	-5582.1	0.00	-5582.1	5562.36	1454.9	7206.86	6836.50	0.00	0.828
0.9D + 1.0W 126 mph Wind	-45.30	-43.51	0.00	-5498.2	0.00	-5498.2	5562.36	1454.9	7206.86	6836.50	0.00	0.813
1.2D + 1.0Di + 1.0Wi 50 mph Wind	-62.25	-10.26	0.00	-1246.0	0.00	-1246.0	5562.36	1454.9	7206.86	6836.50	0.00	0.194
1.2D + 1.0Ev + 1.0Eh	-11.15	-0.50	0.00	-8.05	0.00	-8.05	907.84	223.60	397.18	399.56	148.50	0.032
0.9D + 1.0Ev + 1.0Eh	-8.45	-0.50	0.00	-8.00	0.00	-8.00	907.84	223.60	397.18	399.56	148.50	0.029
1.0D + 1.0W 60 mph Wind	-50.42	-8.83	0.00	-1125.0	0.00	-1125.0	5562.36	1454.9	7206.86	6836.50	0.00	0.174

Base Plate Summary

Structure: CT11794-S	Code: TIA-222-H	1/11/2024
Site Name: East Lyme 1	Exposure: C	
Height: 169.00 (ft)	Crest Height: 0.00	
Base Elev: 1.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Struct Class: II	Page: 38



Reactions	Base Plate	Anchor Bolts
Original Design	Yield (ksi): 50.00	Bolt Circle: 66.75
Moment (kip-ft): 6776.67	Width (in): 72.75	Number Bolts: 20.00
Axial (kip): 62.81	Style: Round	Bolt Type: 2.25" 18J
Shear (kip): 55.54	Polygon Sides: 0.00	Bolt Diameter (in): 2.25
Analysis (1.2D + 1.0W)	Clip Length (in): 0.00	Yield (ksi): 75.00
Moment (kip-ft): 5582.17	Effective Len (in): 16.23	Ultimate (ksi): 100.00
Axial (kip): 60.42	Moment (kip-in): 673.32	Arrangement: Radial
Shear (kip): 43.54	Allow Stress (ksi): 67.50	Cluster Dist (in): 0.00
	Applied Stress (ksi): 33.08	Start Angle (deg): 0.00
	Stress Ratio: 0.49	Compression
		Force (kip): 203.73
		Allowable (kip): 268.39
		Ratio: 0.76
		Tension
		Force (kip): 197.69
		Allowable (kip): 243.75
		Ratio: 0.81

	Monopole Mat Foundation Design		Date 1/11/2024	
	Customer Name:	Verizon	TIA Standard:	TIA-222-H
	Site Name:	East Lyme 1	Structure Height (Ft.):	170
	Site Number:	CT11794-S	Engineer Name:	S. Berthomieu
	Engr. Number:		Engineer Login ID:	

Foundation Info Obtained from:

Structure Type:

Analysis or Design?

Base Reactions (Factored):

Axial Load (Kips):
Uplift Force (Kips):

Drawings/Calculations	Monopole
	Analysis
60.4	Shear Force (Kips): 43.5
0.0	Moment (Kips-ft): 5582.2

Foundation Geometries:


Diameter of Pier (ft.):
Pier Height A. G. (ft.):
Length of Pad (ft.):

8.0	Mod's required -Yes/No ?:	No
1.00	Depth of Base BG (ft.):	5.5
30	Thickness of Pad (ft.):	2.00
	Width of Pad (ft.):	30.0
Final Length of pad (ft)	Final width of pad (ft):	30.0

Material Properties and Rebar Info:

Concrete Strength (psi):
Vertical bar yield (ksi)
Vertical Rebar Size #:
Qty. of Vertical Rebars:
Pad Rebar Yield (Ksi):
Concrete Cover (in.):
Rebar at the bottom of the concrete pad:
Qty. of Rebar in Pad (L):
Rebar at the top of the concrete pad:
Qty. of Rebar in Pad (L):

4000	Steel Elastic Modulus:	29000	ksi
60	Tie steel yield (ksi):	60	
9	Tie / Stirrup Size #:	4	
48	Tie Spacing (in):	12.0	
60	Pad Steel Rebar Size (#):	8	
3	Unit Weight of Concrete:	150.0	pcf
54	Qty. of Rebar in Pad (W):	54	
54	Qty. of Rebar in Pad (W):	54	



Soil Design Parameters:

Soil Unit Weight (pcf):
Water Table B.G.S. (ft):
Ultimate Bearing Pressure (psf):
Consider Friction for O.T.M. (Y/N):
Consider soil hor. resist. for OTM.:

124.0	Soil Buoyant Weight:	61.6	Pcf
99.0	Unit Weight of Water:	62.4	pcf
20000	Ultimate Skin Friction:	0	Psf
No	Consider Friction for bearing (Y/N):	No	
No	Reduction factor on the maximum soil bearing pressure:	1.00	
	Angle from Top of Pad:	30	
	Angle from Bottm of Pad:	25	
	Angle from Bottm of Pad:	25	

Foundation Analysis and Design:

Total Dry Soil Volume (cu. Ft.):
Total Buoyant Soil Volume (cu. Ft.):
Total Effective Soil Weight (Kips):
Total Dry Concrete Volume (cu. Ft.):
Total Buoyant Concrete Volume (cu. Ft.):
Total Effective Concrete Weight (Kips):

Uplift Strength Reduction Factor:	0.75	Compression Strength Reduction Factor:	0.75
2974.07	Total Dry Soil Weight (Kips):	368.78	
0.00	Total Buoyant Soil Weight (Kips):	0.00	
368.78	Weight from the Concrete Block at Top (K):	0.00	
2026.19	Total Dry Concrete Weight (Kips):	303.93	
0.00	Total Buoyant Concrete Weight (Kips):	0.00	
303.93	Total Vertical Load on Base (Kips):	733.11	

Check Soil Capacities:

Calculated Maxium Net Soil Pressure under the base (psf):
Allowable Foundation Overturning Resistance (kips-ft.):
Factor of Safety Against Overturning (O. R. Moment/Design Moment):

2304	<	Allowable Factored Soil Bearing (psf):	15000	0.15	OK!
9987.6	>	Design Factored Momont (kips-ft):	5865	0.59	OK!
1.70	OK!				

Load/
Capacity
Ratio

Check the capacities of Reinforcing Concrete:

Strength reduction factor (Flexure and axial tension):	0.90	Strength reduction factor (Shear):	0.75	
Strength reduction factor (Axial compression):	0.65	Wind Load Factor on Concrete Design:	1.00	

(1) Concrete Pier:

Vertical Steel Rebar Area (sq. in./each):	1.00	Tie / Stirrup Area (sq. in./each):	0.20			
Calculated Moment Capacity (Mn,Kips-Ft):	9280.8	>	Design Factored Moment (Mu, Kips-Ft)	5778.0	0.62	OK!
Calculated Shear Capacity (Kips):	840.3	>	Design Factored Shear (Kips):	43.5	0.05	OK!
Calculated Tension Capacity (Tn, Kips):	2592.0	>	Design Factored Tension (Tu Kips):	0.0	0.00	OK!
Calculated Compression Capacity (Pn, Kips):	12712.3	>	Design Factored Axial Load (Pu Kips):	60.4	0.00	OK!
Moment & Axial Strength Combination:	0.62	OK!	Check Tie Spacing (Design/Required):		1	OK!
Pier Reinforcement Ratio:	0.007		Reinforcement Ratio is satisfied per ACI			

(2) Concrete Pad:

One-Way Design Shear Capacity (L-Direction, Kips):	700.1	>	One-Way Factored Shear (L-D. Kips):	327.2	0.47	OK!
One-Way Design Shear Capacity (W-Direction, Kips):	700.1	>	One-Way Factored Shear (W-D., Kips)	327.2	0.47	OK!
One-Way Design Shear Capacity (Corner-Corner, Kips):	723.7	>	One-Way Factored Shear (C-C, Kips):	329.9	0.46	OK!
Lower Steel Pad Reinforcement Ratio (L-Direct.):	0.0058	OK!	Lower Steel Pad Reinf. Ratio (W-Direc	0.0058		
Lower Steel Pad Moment Capacity (L-Direction, Kips-ft):	3734.7	>	Moment at Bottom (L-Dir. K-Ft):	1946.6	0.52	OK!
Lower Steel Pad Moment Capacity (W-Direction, Kips-ft):	3734.7	>	Moment at Bottom (W-Dir. K-Ft):	1946.6	0.52	OK!
Lower Steel Pad Moment Capacity (Corner-Corner,K-ft):	5215.6	>	Moment at Bottom (C-C Dir. K-Ft):	2752.9	0.53	OK!
Upper Steel Pad Reinforcement Ratio (L-Direct.):	0.0058	OK!	Upper Steel Reinf. Ratio (W-Dir.):	0.0058		
Upper Steel Pad Moment Capacity (L-Direc. Kips-ft):	3734.7	>	Moment at the top (L-Dir K-Ft):	938.8	0.25	OK!
Upper Steel Pad Moment Capacity (W-Direc. Kips-ft):	3734.7	>	Moment at the top (W-Dir K-Ft):	938.8	0.25	OK!
Upper Steel Pad Moment Capacity (Corner-Corner. K-ft):	5215.6	>	Moment at the top (C-C Dir. K-Ft):	879.3	0.17	OK!

(3) Check Punching Shear Capacity due to Moment in the Pier:

Moment transferred by punching shear:	2232.9	k-ft.	Max. factored shear stress $v_{u,cb}$:	4.3	Psi
Max. factored shear stress $v_{u,AB}$:	18.0	Psi	Factored shear Strength ϕv_n :	189.7	Psi
Max. factored shear stress v_u :	18.0	Psi	Check Usage of Punching Shear Capacity:	0.09	OK!

(4) Check Bending Capacity of the Pad Within the Effective Slab Width:

Overturning moment to be transferred by flexure:	1674.7	k-ft.	Effective Width for resisting OT moment:	14.0	ft.
Calculated number of Rebar in Effective width:	26		Actual number of Rebar in Effective width:	26	
Steel Pad Moment Capacity (L-Direc. Kips-ft):	1795.1	k-ft.	Check Usage of the Flexure Capacity:	0.93	OK!



Colliers Engineering & Design, Architecture, Landscape Architecture, Surveying CT, P.C.
1055 Washington Boulevard
Stamford, CT 06901
203.324.0800
peter.albano@collierseng.com

Post-Modification Antenna Mount Analysis Report and PMI Requirements

Mount Fix

SMART Tool Project #: 10210188
Colliers Engineering & Design Project #: 21781129 (Rev. 3)

October 11, 2023

Site Information

Site ID: 5000122067-VZW / ROCKY NECK CT
Site Name: ROCKY NECK CT
Carrier Name: Verizon Wireless
Address: 49 Brainerd Road
Niantic, Connecticut 06357
New London County
Latitude: 41.307583°
Longitude: -72.223917°

Structure Information

Tower Type: 170-Ft Monopole
Mount Type: 12.50-Ft Platform

FUZE ID # 2505529

Analysis Results

Platform: **56.8% Pass w/ Modifications ***

***Antennas and equipment to be installed in compliance with PMI Requirements of this mount analysis.**

***Contractor PMI Requirements:

**Included at the end of this MA report
Available & Submitted via portal at <https://pmi.vzwsmart.com>
For additional questions and support, please reach out to:
pmisupport@colliersengineering.com**

Report Prepared By: Grant Walters



Executive Summary:

The objective of this report is to summarize the analysis results of the antenna support mount including the proposed modifications at the subject facility for the final wireless telecommunications configuration, per the applicable codes and standards.

This analysis is inclusive of the mount structure only and does not address the structural capacity of the supporting structure. This mounting frame was not analyzed as an anchor attachment point for fall protection. All climbing activities are required to have a fall protection plan completed by a competent person.

Sources of Information:

Document Type	Remarks
<i>Radio Frequency Data Sheet (RFDS)</i>	<i>RFDS Site ID: 656767 Dated August 16, 2023</i>
<i>Mount Mapping</i>	<i>Structural Components Site ID: 2505529 Dated September 10, 2021</i>
<i>Previous Mount Analysis</i>	<i>Colliers Engineering & Design Project #: 21781129 (Rev 3), Dated October 31, 2022</i>
<i>Mount Modification Drawings</i>	<i>Colliers Engineering & Design Project #: 21781129 (Rev 3), Dated October 11, 2023</i>

Analysis Criteria:

Codes and Standards:	ANSI/TIA-222-H 2022 Connecticut State Building Code (CSBC),	Effective October 1, 2022
Wind Parameters:	Basic Wind Speed (Ultimate 3-sec. Gust), V_{ULT} : Ice Wind Speed (3-sec. Gust): Design Ice Thickness: Risk Category: Exposure Category: Topographic Category: Topographic Feature Considered: Topographic Method: Ground Elevation Factor, K_e :	130 mph 50 mph 1.00 in II C 1 N/A N/A 1.000
Seismic Parameters:	S_s : S_1 :	0.198 g 0.053 g
Maintenance Parameters:	Wind Speed (3-sec. Gust): Maintenance Live Load, L_v : Maintenance Live Load, L_m :	30 mph 250 lbs. 500 lbs.
Analysis Software:	RISA-3D (V17)	

Final Loading Configuration:

The following equipment has been considered for the analysis of the mount:

Mount Elevation (ft)	Equipment Elevation (ft)	Quantity	Manufacturer	Model	Status
145.00	147.00	6	JMA Wireless	MX06FRO660-03	Added
		3	Samsung	MT6413-77A	
		3	Samsung	RF4439d-25A	
		3	Samsung	RF4461d-13A	
		1	Raycap	RVZDC-6627-PF-48	

The recent mount mapping reported existing OVP units. It is acceptable to install up to any three (3) of the OVP model numbers listed below as required at any location other than the mount face without affecting the structural capacity of the mount. If OVP units are installed on the mount face, a mount re-analysis may be required unless replacing an existing OVP.

Model Number	Ports	AKA
DB-B1-6C-24AB-0Z	6	OVP-6
RVZDC-6627-PF-48	12	OVP-12

Standard Conditions:

1. All engineering services are performed on the basis that the information provided to Colliers Engineering & Design and used in this analysis is current and correct. The existing equipment loading has been applied at locations determined from the supplied documentation. Any deviation from the loading locations specified in this report shall be communicated to Colliers Engineering & Design to verify deviation will not adversely impact the analysis.
2. Mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer's specifications.

Obvious safety and structural issues/deficiencies noticed at the time of the mount mapping and reported in the Mount Mapping Report are assumed to be corrected and documented as part of the PMI process and are not considered in the mount analysis.

The mount analysis and the mount mapping are not a condition assessment of the mount. Proper maintenance and condition assessments are still required post analysis.

3. For mount analyses completed from other data sources (including new replacement mounts) and not specifically mapped in accordance with the NSTD-446 Standard, the mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer's specifications.
4. All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
5. The mount was checked up to, and including, the bolts that fasten it to the mount collar/attachment and threaded rod connections in collar members if applicable. Local deformation and interaction between the mount collar/attachment and the supporting tower structure are outside the scope of this analysis.

6. All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. Colliers Engineering & Design is not responsible for the conclusion, opinions, and recommendations made by others based on the information supplied.
7. Structural Steel Grades have been assumed as follows, if applicable, unless otherwise noted in this analysis:
 - o Channel, Solid Round, Angle, Plate ASTM A36 (Gr. 36)
 - o HSS (Rectangular) ASTM 500 (Gr. B-46)
 - o Pipe ASTM A53 (Gr. B-35)
 - o Threaded Rod F1554 (Gr. 36)
 - o Bolts ASTM A325
8. Any mount modifications listed under Sources of Information are assumed to have been installed per the design specifications.

Discrepancies between in-field conditions and the assumptions listed above may render this analysis invalid unless explicitly approved by Colliers Engineering & Design.

Analysis Results:

Component	Utilization %	Pass/Fail
Standoff Horizontal	23.1 %	Pass
Platform Crossmember	56.8 %	Pass
Corner Plate	44.9 %	Pass
Grating Support	36.4 %	Pass
Cross Arm Plate	23.3 %	Pass
Face Horizontal	15.5 %	Pass
Mount Pipe	37.2 %	Pass
Mount Pipe 2.5	29.8 %	Pass
Support Rail Angle	31.5 %	Pass
Support Rail	15.6 %	Pass
Kicker	9.0 %	Pass
Mount Connection	30.8 %	Pass
Structure Rating – (Controlling Utilization of all Components)		56.8%

BASELINE mount weight per SBA agreement: 1486.88 lbs

Increase in mount weight due to Verizon loading change per SBA agreement: 465.04 lbs

The weights listed above include 3 sector(s).

Mount Steel (EPA)a per ANSI/TIA-222-H Section 2.6.11.2:

Ice Thickness (In)	Mount Pipes Excluded		Mount Pipes Included	
	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)
0	29.8	29.8	49.0	49.0
0.5	39.4	39.4	66.3	66.3
1	47.1	47.1	81.7	81.7

Notes:

- (EPA)a values listed above may be used in the absence of more precise information
- (EPA)a values in the table above include 3 sector(s).
- Ka factors included in (EPA)a calculations

Requirements:

The existing mount will be **SUFFICIENT** for the final loading configuration (attachment 2) **after the modifications detailed in attachment 3 are successfully completed.**

ANSI/ASSP rigging plan review services compliant with the requirements of ANSI/TIA 322 are available for a Construction Class IV site or other, if required. Separate review fees will apply.

Attachments:

1. **Contractor Required PMI Report Deliverables**
2. Antenna Placement Diagrams
3. Mount Modification Drawings
4. Mount Photos
5. Mount Mapping Report (for reference only)
6. Analysis Calculations

Mount Desktop – Post Modification Inspection (PMI) Report Requirements

Documents & Photos Required from Contractor – Mount Modification

Electronic pdf version of this can be downloaded at <https://pmi.vzwsmart.com>
For additional questions and support, please reach out to pmisupport@colliersengineering.com

MDG #: 5000122067

SMART Project #: 10210188

Fuze Project ID: 2505529

Purpose – to upload the proper documentation to the SMART Tool in order to allow the SMART Tool engineering vendor to complete the required Mount Desktop review of the Post Modification Inspection Report.

- Contractor is responsible for making certain the photos provided as noted below provide confirmation that the modification was completed in accordance with the modification drawings.
- Contractor shall relay any data that can impact the performance of the mount or the mount modification, this includes safety issues.

Base Requirements:

- If installation of the modification will cause damage to the structure, the climbing facility, or safety climb if present or any installed system, SMART Tool vendor to be notified prior to install. Any special photos outside of the standard requirements will be indicated on the drawings.
- Provide “as built drawings” showing contractor’s name, preparer’s signature, and date. Any deviations from the drawings (proposed modification) shall be shown. NOTE: If loading is different than what is conveyed in the post-modification passing mount analysis (MA) contact the SMART Tool vendor immediately.
- Each photo shall be time and date stamped.
- Photos should be high resolution.
- Contractor shall ensure that the safety climb wire rope is not adversely impacted by the install of the modification components. This may involve the install of wire rope guides, or other items to protect the wire rope. If there is conflict, contact the SMART Tool engineer for recommendations.
- The PMI can be accessed at the following portal: <https://pmi.vzwsmart.com>

Photo Requirements:

- Photos taken at ground level
 - Photo of Gate Signs showing the tower owner, site name, and number.
 - Overall tower structure after installation of the modifications.
 - Photos of the mount after installation of the modifications; if the mounts are at different rad elevations, pictures must be provided for all elevations that the modifications were installed
- Photos taken at Mount Elevation
 - Photos showing the safety climb wire rope above and below the mount prior to modification.
 - Photos showing the climbing facility and safety climb if present.

- Photos showing each individual sector after installation of modifications. Each entire sector must be in one photo to show the interconnection of members.
 - These photos shall also certify that the placement and geometry of the equipment on the mount is as depicted in the antenna placement diagram in this form.
- Photos that show the model number of each antenna and piece of equipment installed per sector.
- Photos of each installed modification per the modification drawings; pictures shall also include connection hardware (U-bolts, bolts, nuts, all-threaded rods, etc.)
- Photos showing the distances (relative distance between collars) of the installed modifications from the appropriate reference locations shown in the modification drawings.
- Photos showing the installed modifications onto the tower (i.e. ring/collar mounts, tie-backs, V-bracing kits, etc.); if the existing mount elevation needs to be changed according to the modification drawings, an elevation measurement shall be provided before the elevation change.

Material Certification:

- Materials utilized must be as per specification on the drawings or the equivalent as validated by the SMART Tool vendor.
 - If the materials are as specified on the drawings
 - The contractor shall provide the packing list, or the materials certifications for the materials utilized to perform the mount modification
 - Commscope, Metrosite, Perfect Vision, Sabre, and Site Pro have all agreed to support Verizon vendors with the necessary material certifications
 - If seeking permission to use an equivalent
 - It is required that the SMART Tool engineering vendor approval of such is included in the contractor submission package. There may be an additional charge for approval if the equivalent submission doesn't meet specifications as prescribed in the drawings.

All hardware has been properly installed, and the existing hardware was inspected.

The material utilized was as specified on the SMART Tool engineering vendor Mount Modification Drawings and included in the material certification folder is a packing list or invoice for these materials.

OR

The material utilized was approved by a SMART Tool engineering vendor as an "equivalent" and this approval is included as part of the contractor submission.

Antenna & Equipment Placement and Geometry Confirmation:

The contractor certifies that the photos support and the equipment on the mount is as depicted on the sketch and table included in this form and with the mount analysis provided.

OR

- The contractor notes that the equipment on the mount is not in accordance with the sketch and has noted the differences below and provided photo documentation of any alterations.

Comments:

Was the mount modification completed in conjunction with the equipment change / installation?

- Yes No

Special Instructions / Validation as required from the MA or Mod Drawings:

Issue:

Response:

Special Instruction Confirmation:

- The contractor has read and acknowledges the above special instructions.

Comments:

Contractor certifies that the climbing facility / safety climb was not damaged prior to starting work:

- Yes No

Contractor certifies no new damage created during the current installation:

- Yes No

Contractor to certify the condition of the safety climb and verify no damage when leaving the site:

- Safety Climb in Good Condition Safety Climb Damaged

Comments:

--

Certifying Individual:

Company:	
Employee Name:	
Contact Phone:	
Email:	
Date:	

Structure: 5000122067-VZW - ROCKY NECK CT

Sector: A

9/27/2023


Structure Type: Monopole

10210188



Mount Elev: 145.00

Page: 1



Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A2	MT6413-77A	28.9	15.8	145.5	1	a	Front	30	0	Added	
A1	MX06FRO660-03	71.3	15.4	74	2	a	Front	30	8	Added	
A1	MX06FRO660-03	71.3	15.4	74	2	b	Front	30	-8	Added	
R4	RF4461d-13A	15	15	74	2	a	Behind	24	0	Added	
R3	RF4439d-25A	15	15	29	3	a	Behind	24	0	Added	
M101A	RVZDC-6627-PF-48	29.5	16.5			Member				Added	

Structure: 5000122067-VZW - ROCKY NECK CT


Sector: B
 Structure Type: Monopole
 Mount Elev: 145.00

10210188

9/27/2023



Page: 2



Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A2	MT6413-77A	28.9	15.8	145.5	1	a	Front	30	0	Added	
A1	MX06FRO660-03	71.3	15.4	74	2	a	Front	30	8	Added	
A1	MX06FRO660-03	71.3	15.4	74	2	b	Front	30	-8	Added	
R4	RF4461d-13A	15	15	74	2	a	Behind	24	0	Added	
R3	RF4439d-25A	15	15	29	3	a	Behind	24	0	Added	

Structure: 5000122067-VZW - ROCKY NECK CT

Sector: C

9/27/2023


Structure Type: Monopole

10210188



Mount Elev: 145.00

Page: 3




Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A2	MT6413-77A	28.9	15.8	145.5	1	a	Front	30	0	Added	
A1	MX06FRO660-03	71.3	15.4	74	2	a	Front	30	8	Added	
A1	MX06FRO660-03	71.3	15.4	74	2	b	Front	30	-8	Added	
R4	RF4461d-13A	15	15	74	2	a	Behind	24	0	Added	
R3	RF4439d-25A	15	15	29	3	a	Behind	24	0	Added	

pending S&S


Replace this page with mount modification drawings.



Mount Azimuth (Degree) for Each Sector			Tower Leg Azimuth (Degree) for Each Sector			Sector B													
Sector A:	30.00	Deg	Leg A:		Deg	Ant _{1a}													
Sector B:	150.00	Deg	Leg B:		Deg	Ant _{1b}	Swecom SC-E 6014 re	8.00	8.50	43.00	1-5/8"	146.208	21.50	13.50	130.00	35			
Sector C:	270.00	Deg	Leg C:		Deg	Ant _{1c}													
Sector D:		Deg	Leg D:		Deg	Ant _{2a}	B66a RRH4x45	12.00	7.00	25.50	jumpers	145.958	32.50	-7.00	130.00	36			
Climbing Facility Information						Ant _{2b}	SBNHH-1D65B	12.00	7.00	72.00	jumpers	145.333	40.00	9.50	130.00	36			
Location:	0.00	Deg	N/A			Ant _{2c}													
Climbing Facility	Corrosion Type:	Good condition.				Ant _{3a}	813 RRH 4x30	12.00	7.00	20.50	jumpers	145.833	34.00	-7.00	130.00	36			
	Access:	Climbing path was obstructed.				Ant _{3b}	SBNHH-1D65B	12.00	7.00	72.00	jumpers	145.583	37.00	8.50	130.00	36			
	Condition:	Good condition.				Ant _{3c}													
						Ant _{4a}													
						Ant _{4b}	Swecom SC-E 6014 re	8.00	8.50	43.00	1-5/8"	146.208	21.50	13.50	130.00	36			
						Ant _{4c}													
						Ant _{5a}													
						Ant _{5b}													
						Ant _{5c}													
						Ant on Standoff													
						Ant on Standoff													
						Ant on Tower	RRFDC-3315-PF-48	14.00	9.00	19.00	1.5" Hyb	149							154
						Ant on Tower													
						Sector C													
						Ant _{1a}													
						Ant _{1b}	LPA 80080-4CF E-DIN	6.00	13.00	47.00	1-5/8"	145.458	35.50	16.50	270	37			
						Ant _{1c}													
						Ant _{2a}	B66a RRH4x45	12.00	7.00	25.50	jumpers	145.875	33.50	-7.00	270	38			
						Ant _{2b}	SBNHH-1D65B	12.00	7.00	72.00	jumpers	145.583	37.00	8.50	270	38			
						Ant _{2c}													
						Ant _{3a}	813 RRH 4x30	12.00	7.00	20.50	jumpers	146.083	31.00	-7.00	270	38			
						Ant _{3b}	SBNHH-1D65B	12.00	7.00	72.00	jumpers	145.417	39.00	9.00	270	38			
						Ant _{3c}													
						Ant _{4a}													
						Ant _{4b}	LPA 80080-4CF E-DIN	6.00	13.00	47.00	1-5/8"	145.042	35.50	16.50	270	38			
						Ant _{4c}													
						Ant _{5a}													
						Ant _{5b}													
						Ant _{5c}													
						Ant on Standoff													
						Ant on Standoff													
						Ant on Tower	RRFDC-3315-PF-48	14.00	9.00	19.00	1.5" Hyb	149							156
						Ant on Tower													
						Sector D													
						Ant _{1a}													
						Ant _{1b}													
						Ant _{1c}													
						Ant _{2a}													
						Ant _{2b}													
						Ant _{2c}													
						Ant _{3a}													
						Ant _{3b}													
						Ant _{3c}													
						Ant _{4a}													
						Ant _{4b}													
						Ant _{4c}													
						Ant _{5a}													
						Ant _{5b}													
						Ant _{5c}													
						Ant on Standoff													
						Ant on Standoff													
						Ant on Tower													
						Ant on Tower													



For T-Arms/Platforms on monopoles, record the weld size from the main standoff member to the plate bolting into the collar. See below for reference.



Observed Safety and Structural Issues During the Mount Mapping		
Issue #	Description of Issue	Photo #
1		
2		
3		
4		
5		
6		
7		
8		

Observed Obstructions to Tower Lighting System			
If the tower lighting system is being obstructed by the carrier's equipment (for example: a light nested by the antennas), please provide photos and fill in the information below.			Photo #
Description of Obstruction:			
Type of Light:	Photo #	Additional Comments:	
Lighting Technology:	Photo #		
Elevation (AGL) at base of light (Ft.):	Photo #		
Is a service loop available?	Photo #		
Is beacon installed on an extension?	Photo #		

- Mapping Notes**
1. Please report any visible structural or safety issues observed on the antenna mounts (Damaged members, loose connections, tilting mounts, safety climb issues, etc.)
 2. If the thickness of the existing pipes or tubing can't be obtained from a general tool (such as Caliper), please use an ultrasonic measurement tool (thickness gauge) to measure the thickness.
 3. Please create all required detail sketches of the mounts and insert them into the "Sketches" tab.
 4. Please measure and enter the bolt sizes and types under the Members Box in the spreadsheet of the mount type.
 5. Take and label the photos of the tower, mounts, connections, antennas and all measurements. Minimum 50 photos are required.
 6. Please measure and report the size and length of all existing antenna mounting pipes.
 7. Please measure and report the antenna information for all sectors.
 8. Don't delete or rearrange any sheet or contents of any sheet from this mapping form.

- Standard Conditions**
1. Obvious safety and structural issues/deficiencies noticed at the time of the mount mapping are to be reported in this mapping. However, this mount mapping is not a condition assessment of the mount.





Antenna Mount Mapping Form (PATENT PENDING)

FCC #
1279239



Tower Owner:	SBA	Mapping Date:	9/10/2021
Site Name:	ROCKY NECK CT	Tower Type:	Monopole
Site Number or ID:	2505529	Tower Height (FT):	170
Mapping Contractor:	Structural Components	Mount Elevation (FT):	144

This antenna mapping form is the property of TES and under PATENT PENDING. The information contained herein is considered confidential in nature and is to be used only for the specific customer it was intended for. Reproduction, transmission, publication, modification or disclosure by any method is prohibited except by express written permission of TES. All means and methods are the responsibility of the contractor and the work shall be compliant with ANSI/ASSE A 10.48, OSHA, FCC, FAA and other safety requirements that may apply. TES is not warranting the usability of the safety climb as it must be assessed prior to each use in compliance with OSHA requirements.

Please Insert Sketches of the Antenna Mount






Pipe mount connections
 C6.375" x 2.5" x 0.375 tf x 0.25" tw x 8" Tall
 (4) 1/2" u-bolts
 6-1/2" C-C / 4-1/2" C-C



SK - 1




Sept 27, 2023 at 2:54 PM

5000122067-VZW_MT_LO_H.r3d



Member Code Checks Displayed (Enveloped)
Results for LC 1, 1.2D+1.0Wo (0 Deg)

		SK - 2
		Sept 27, 2023 at 2:55 PM
		5000122067-VZW_MT_LO_H.r3d



Member Shear Checks Displayed (Enveloped)
Results for LC 1, 1.2D+1.0Wo (0 Deg)

	SK - 3
	Sept 27, 2023 at 2:55 PM
	5000122067-VZW_MT_LO_H.r3d



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area (Me...	Surface (...
1	Antenna D	None					75		
2	Antenna Di	None					75		
3	Antenna Wo (0 Deg)	None					75		
4	Antenna Wo (30 Deg)	None					75		
5	Antenna Wo (60 Deg)	None					75		
6	Antenna Wo (90 Deg)	None					75		
7	Antenna Wo (120 Deg)	None					75		
8	Antenna Wo (150 Deg)	None					75		
9	Antenna Wo (180 Deg)	None					75		
10	Antenna Wo (210 Deg)	None					75		
11	Antenna Wo (240 Deg)	None					75		
12	Antenna Wo (270 Deg)	None					75		
13	Antenna Wo (300 Deg)	None					75		
14	Antenna Wo (330 Deg)	None					75		
15	Antenna Wi (0 Deg)	None					75		
16	Antenna Wi (30 Deg)	None					75		
17	Antenna Wi (60 Deg)	None					75		
18	Antenna Wi (90 Deg)	None					75		
19	Antenna Wi (120 Deg)	None					75		
20	Antenna Wi (150 Deg)	None					75		
21	Antenna Wi (180 Deg)	None					75		
22	Antenna Wi (210 Deg)	None					75		
23	Antenna Wi (240 Deg)	None					75		
24	Antenna Wi (270 Deg)	None					75		
25	Antenna Wi (300 Deg)	None					75		
26	Antenna Wi (330 Deg)	None					75		
27	Antenna Wm (0 Deg)	None					75		
28	Antenna Wm (30 Deg)	None					75		
29	Antenna Wm (60 Deg)	None					75		
30	Antenna Wm (90 Deg)	None					75		
31	Antenna Wm (120 Deg)	None					75		
32	Antenna Wm (150 Deg)	None					75		
33	Antenna Wm (180 Deg)	None					75		
34	Antenna Wm (210 Deg)	None					75		
35	Antenna Wm (240 Deg)	None					75		
36	Antenna Wm (270 Deg)	None					75		
37	Antenna Wm (300 Deg)	None					75		
38	Antenna Wm (330 Deg)	None					75		
39	Structure D	None		-1					3
40	Structure Di	None						61	3
41	Structure Wo (0 Deg)	None						122	
42	Structure Wo (30 Deg)	None						122	
43	Structure Wo (60 Deg)	None						122	
44	Structure Wo (90 Deg)	None						122	
45	Structure Wo (120 Deg)	None						122	
46	Structure Wo (150 Deg)	None						122	
47	Structure Wo (180 Deg)	None						122	
48	Structure Wo (210 Deg)	None						122	
49	Structure Wo (240 Deg)	None						122	
50	Structure Wo (270 Deg)	None						122	
51	Structure Wo (300 Deg)	None						122	
52	Structure Wo (330 Deg)	None						122	
53	Structure Wi (0 Deg)	None						122	
54	Structure Wi (30 Deg)	None						122	
55	Structure Wi (60 Deg)	None						122	
56	Structure Wi (90 Deg)	None						122	



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Basic Load Cases (Continued)

BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	DistributedArea(Me... Surface(...
57 Structure Wi (120 Deg)	None						122
58 Structure Wi (150 Deg)	None						122
59 Structure Wi (180 Deg)	None						122
60 Structure Wi (210 Deg)	None						122
61 Structure Wi (240 Deg)	None						122
62 Structure Wi (270 Deg)	None						122
63 Structure Wi (300 Deg)	None						122
64 Structure Wi (330 Deg)	None						122
65 Structure Wm (0 Deg)	None						122
66 Structure Wm (30 Deg)	None						122
67 Structure Wm (60 Deg)	None						122
68 Structure Wm (90 Deg)	None						122
69 Structure Wm (120 Deg)	None						122
70 Structure Wm (150 Deg)	None						122
71 Structure Wm (180 Deg)	None						122
72 Structure Wm (210 Deg)	None						122
73 Structure Wm (240 Deg)	None						122
74 Structure Wm (270 Deg)	None						122
75 Structure Wm (300 Deg)	None						122
76 Structure Wm (330 Deg)	None						122
77 Lm1	None					1	
78 Lm2	None					1	
79 Lv1	None					1	
80 Lv2	None					1	
81 Antenna Ev	None					75	
82 Antenna Eh (0 Deg)	None					50	
83 Antenna Eh (90 Deg)	None					50	
84 Structure Ev	ELY		-042				3
85 Structure Eh (0 Deg)	ELZ			-106			3
86 Structure Eh (90 Deg)	ELX	.106					3
87 BLC 39 Transient Area Loads	None						30
88 BLC 40 Transient Area Loads	None						30
89 BLC 84 Transient Area Loads	None						30
90 BLC 85 Transient Area Loads	None						30
91 BLC 86 Transient Area Loads	None						30

Load Combinations

Description	Solve	PDelta	S...	B...	Fa...	B...	Fa...	B...	Fa...	BLCFa...	BLC Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
1 1.2D+1.0Wo (0 Deg)	Yes	Y	1	1.2	39	1.2	3	1	41	1									
2 1.2D+1.0Wo (30 D...	Yes	Y	1	1.2	39	1.2	4	1	42	1									
3 1.2D+1.0Wo (60 D...	Yes	Y	1	1.2	39	1.2	5	1	43	1									
4 1.2D+1.0Wo (90 D...	Yes	Y	1	1.2	39	1.2	6	1	44	1									
5 1.2D+1.0Wo (120 ...	Yes	Y	1	1.2	39	1.2	7	1	45	1									
6 1.2D+1.0Wo (150 ...	Yes	Y	1	1.2	39	1.2	8	1	46	1									
7 1.2D+1.0Wo (180 ...	Yes	Y	1	1.2	39	1.2	9	1	47	1									
8 1.2D+1.0Wo (210 ...	Yes	Y	1	1.2	39	1.2	10	1	48	1									
9 1.2D+1.0Wo (240 ...	Yes	Y	1	1.2	39	1.2	11	1	49	1									
10 1.2D+1.0Wo (270 ...	Yes	Y	1	1.2	39	1.2	12	1	50	1									
11 1.2D+1.0Wo (300 ...	Yes	Y	1	1.2	39	1.2	13	1	51	1									
12 1.2D+1.0Wo (330 ...	Yes	Y	1	1.2	39	1.2	14	1	52	1									
13 1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	15	1	53	1					
14 1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	16	1	54	1					
15 1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	17	1	55	1					
16 1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	18	1	56	1					
17 1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	19	1	57	1					



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Load Combinations (Continued)

Description	Solve	PDelta	S	B	Fa	B	Fa	B	Fa	B	Fa	B	Fa	B	Fa	B	Fa	B	Fa	B	Fa	B	Fa
18	1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	20	1	58	1								
19	1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	21	1	59	1								
20	1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	22	1	60	1								
21	1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	23	1	61	1								
22	1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	24	1	62	1								
23	1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	25	1	63	1								
24	1.2D + 1.0Di + 1.0...	Yes	Y	1	1.2	39	1.2	2	1	40	1	26	1	64	1								
25	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	27	1	65	1										
26	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	28	1	66	1										
27	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	29	1	67	1										
28	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	30	1	68	1										
29	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	31	1	69	1										
30	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	32	1	70	1										
31	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	33	1	71	1										
32	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	34	1	72	1										
33	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	35	1	73	1										
34	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	36	1	74	1										
35	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	37	1	75	1										
36	1.2D + 1.5Lm1 + 1...	Yes	Y	1	1.2	39	1.2	77	1.5	38	1	76	1										
37	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	27	1	65	1										
38	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	28	1	66	1										
39	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	29	1	67	1										
40	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	30	1	68	1										
41	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	31	1	69	1										
42	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	32	1	70	1										
43	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	33	1	71	1										
44	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	34	1	72	1										
45	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	35	1	73	1										
46	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	36	1	74	1										
47	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	37	1	75	1										
48	1.2D + 1.5Lm2 + 1...	Yes	Y	1	1.2	39	1.2	78	1.5	38	1	76	1										
49	1.2D + 1.5Lv1	Yes	Y	1	1.2	39	1.2	79	1.5														
50	1.2D + 1.5Lv2	Yes	Y	1	1.2	39	1.2	80	1.5														
51	1.4D	Yes	Y	1	1.4	39	1.4																
52	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	1	83		E...	1	E...					
53	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	.866	83	.5	E...	.866	E...	.5				
54	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	.5	83	.866	E...	.5	E...	.866				
55	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82		83	1	E...		E...	1				
56	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	-5	83	.866	E...	-5	E...	.866				
57	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	-8...	83	.5	E...	-8...	E...	.5				
58	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	-1	83		E...	-1	E...					
59	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	-8...	83	-5	E...	-8...	E...	-5				
60	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	-5	83	-8...	E...	-5	E...	-8...				
61	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82		83	-1	E...		E...	-1				
62	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	.5	83	-8...	E...	.5	E...	-8...				
63	1.2D + 1.0Ev + 1.0...	Yes	Y	1	1.2	39	1.2	81	1	ELY	1	82	.866	83	-5	E...	.866	E...	-5				
64	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	1	83		E...	1	E...					
65	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	.866	83	.5	E...	.866	E...	.5				
66	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	.5	83	.866	E...	.5	E...	.866				
67	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82		83	1	E...		E...	1				
68	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	-5	83	.866	E...	-5	E...	.866				
69	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	-8...	83	.5	E...	-8...	E...	.5				
70	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	-1	83		E...	-1	E...					
71	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	-8...	83	-5	E...	-8...	E...	-5				
72	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	-5	83	-8...	E...	-5	E...	-8...				
73	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82		83	-1	E...		E...	-1				
74	0.9D - 1.0Ev + 1.0...	Yes	Y	1	.9	39	.9	81	-1	ELY	-1	82	.5	83	-8...	E...	.5	E...	-8...				



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Load Combinations (Continued)

	Description	Solve	PDelta	S...	B...	Fa...	B...	Fa...	B...	Fa...	BLCFa...	BLCFa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
75	0.9D - 1.0Ev + 1.0...	Yes	Y		1	.9	.39	.9	.81	-1	ELY	-1	.82	.866	.83	-5	E...	.866	E...	-5

Joint Coordinates and Temperatures

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap.
1	N144A	-0.	0	-1.5	0	
2	N145	-2.541667	0	-3	0	
3	N146	2.315104	0.166667	-3	0	
4	N147	-2.315104	0.166667	-3	0	
5	N148A	-0.	0	-3	0	
6	N149	-0.	0	-6.6875	0	
7	N150	0	0	0	0	
8	N151	2.315104	0	-3	0	
9	N152	-2.315104	0	-3	0	
10	N153	2.541667	0	-3	0	
11	N154	-0.166667	0	-3	0	
12	N155	0.166667	0	-3	0	
13	N156	-2.541667	0	-3.21875	0	
14	N157	2.541667	0	-3.21875	0	
15	N158	2.458333	0	-3.363088	0	
16	N159	0.571615	0	-6.590523	0	
17	N160	-2.458333	0	-3.363088	0	
18	N161	-0.571615	0	-6.590523	0	
19	N162	2.584629	0	-3.436004	0	
20	N163	-2.584629	0	-3.436004	0	
21	N164	-0.515625	0	-6.6875	0	
22	N165	0.515625	0	-6.6875	0	
23	N166	0.715429	0	-6.673554	0	
24	N167	-0.715429	0	-6.673554	0	
25	N168	-0.	0	-6.604167	0	
26	N169	0.234238	0.166667	-6.604167	0	
27	N170	0.234238	0	-6.604167	0	
28	N171	-0.234238	0.166667	-6.604167	0	
29	N172	-0.234238	0	-6.604167	0	
30	N173	-1.299038	0	0.75	0	
31	N174	-1.327243	0	3.701148	0	
32	N175	-3.755628	0.166667	-0.504939	0	
33	N176	-1.440524	0.166667	3.504939	0	
34	N177	-2.598076	0	1.5	0	
35	N178	-5.791545	0	3.34375	0	
36	N180	-3.755628	0	-0.504939	0	
37	N181	-1.440524	0	3.504939	0	
38	N182	-3.86891	0	-0.701148	0	
39	N183	-2.514743	0	1.644338	0	
40	N184	-2.68141	0	1.355662	0	
41	N185	-1.516686	0	3.810523	0	
42	N186	-4.058353	0	-0.591773	0	
43	N187	-4.141686	0	-0.447435	0	
44	N188	-5.993368	0	2.800229	0	
45	N189	-1.683353	0	3.810523	0	
46	N190	-5.421753	0	3.790294	0	
47	N191	-4.267982	0	-0.520352	0	
48	N192	-1.683353	0	3.956357	0	
49	N193	-5.533732	0	3.790294	0	
50	N194	-6.049357	0	2.897206	0	
51	N195	-6.137182	0	2.717198	0	



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap.
52	N196	-5.421753	0	3.956357	0	
53	N197	-5.719376	0	3.302083	0	
54	N198	-5.836495	0.166667	3.099228	0	
55	N199	-5.836495	0	3.099228	0	
56	N200	-5.602257	0.166667	3.504939	0	
57	N201	-5.602257	0	3.504939	0	
58	N202	1.299038	0	0.75	0	
59	N203	3.86891	0	-0.701148	0	
60	N204	1.440524	0.166667	3.504939	0	
61	N205	3.755628	0.166667	-0.504939	0	
62	N206	2.598076	0	1.5	0	
63	N207	5.791545	0	3.34375	0	
64	N209	1.440524	0	3.504939	0	
65	N210	3.755628	0	-0.504939	0	
66	N211	1.327243	0	3.701148	0	
67	N212	2.68141	0	1.355662	0	
68	N213	2.514743	0	1.644338	0	
69	N214	4.058353	0	-0.591773	0	
70	N215	1.516686	0	3.810523	0	
71	N216	1.683353	0	3.810523	0	
72	N217	5.421753	0	3.790294	0	
73	N218	4.141686	0	-0.447435	0	
74	N219	5.993368	0	2.800229	0	
75	N220	1.683353	0	3.956357	0	
76	N221	4.267982	0	-0.520352	0	
77	N222	6.049357	0	2.897206	0	
78	N223	5.533732	0	3.790294	0	
79	N224	5.421753	0	3.956357	0	
80	N225	6.137182	0	2.717198	0	
81	N226	5.719376	0	3.302083	0	
82	N227	5.602257	0.166667	3.504939	0	
83	N228	5.602257	0	3.504939	0	
84	N229	5.836495	0.166667	3.099228	0	
85	N230	5.836495	0	3.099228	0	
86	N230A	6.25	0	3.956357	0	
87	N231	-6.25	0	3.956357	0	
88	N231A	5.875	0	3.956357	0	
89	N232	5.875	0	4.206357	0	
90	N233	5.875	4	4.206357	0	
91	N234	5.875	-4	4.206357	0	
92	N235	1.875	0	3.956357	0	
93	N236	1.875	0	4.206357	0	
94	N237	1.875	4.666667	4.206357	0	
95	N238	1.875	-3.333333	4.206357	0	
96	N239	-2.125	0	3.956357	0	
97	N240	-2.125	0	4.206357	0	
98	N241	-2.125	4.666667	4.206357	0	
99	N242	-2.125	-3.333333	4.206357	0	
100	N243	-5.833333	0	3.956357	0	
101	N244	-5.833333	0	4.206357	0	
102	N245	-5.833333	4	4.206357	0	
103	N246	-5.833333	-4	4.206357	0	
104	N247	0.301305	0	-7.390837	0	
105	N248	6.551305	0	3.43448	0	
106	N249	0.467972	0	-7.102162	0	
107	N250	0.684478	0	-7.227162	0	
108	N251	0.684478	4	-7.227162	0	



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
109	N252	0.684478	-4	-7.227162	0	
110	N253	2.467972	0	-3.63806	0	
111	N254	2.684478	0	-3.76306	0	
112	N255	2.684478	4.666667	-3.76306	0	
113	N256	2.684478	-3.333333	-3.76306	0	
114	N257	4.467972	0	-0.173959	0	
115	N258	4.684478	0	-0.298959	0	
116	N259	4.684478	4.666667	-0.298959	0	
117	N260	4.684478	-3.333333	-0.298959	0	
118	N261	6.363805	0	3.109721	0	
119	N262	6.580312	0	2.984721	0	
120	N263	6.580312	4	2.984721	0	
121	N264	6.580312	-4	2.984721	0	
122	N265	-6.551305	0	3.43448	0	
123	N266	-0.301305	0	-7.390837	0	
124	N267	-6.342972	0	3.073637	0	
125	N268	-6.559478	0	2.948637	0	
126	N269	-6.559478	4	2.948637	0	
127	N270	-6.559478	-4	2.948637	0	
128	N271	-4.342972	0	-0.390465	0	
129	N272	-4.559478	0	-0.515465	0	
130	N273	-4.559478	4.666667	-0.515465	0	
131	N274	-4.559478	-3.333333	-0.515465	0	
132	N275	-2.342972	0	-3.854567	0	
133	N276	-2.559478	0	-3.979567	0	
134	N277	-2.559478	4.666667	-3.979567	0	
135	N278	-2.559478	-3.333333	-3.979567	0	
136	N279	-0.405472	0	-7.210415	0	
137	N280	-0.621978	0	-7.335415	0	
138	N281	-0.621978	4	-7.335415	0	
139	N282	-0.621978	-4	-7.335415	0	
140	N140	-0	0	-2.25	0	
141	N141	.25	0	-2.25	0	
142	N142	.25	-1	-2.25	0	
143	N143	.25	2	-2.25	0	
144	N144	1.154948	3.5	-5.590523	0	
145	N145A	-1.154948	3.5	-5.590523	0	
146	N146A	-1.098958	3.5	-5.6875	0	
147	N147A	1.098958	3.5	-5.6875	0	
148	N148	1.294275	3.5	-5.670964	0	
149	N149A	-1.294275	3.5	-5.670964	0	
150	N162A	6.25	3.5	3.956357	0	
151	N163A	-6.25	3.5	3.956357	0	
152	N164A	5.875	3.5	3.956357	0	
153	N165A	5.875	3.5	4.206357	0	
154	N166A	1.875	3.5	3.956357	0	
155	N167A	1.875	3.5	4.206357	0	
156	N168A	-5.833333	3.5	3.956357	0	
157	N169A	-5.833333	3.5	4.206357	0	
158	N170A	0.301305	3.5	-7.390837	0	
159	N171A	6.551305	3.5	3.43448	0	
160	N172A	0.467972	3.5	-7.102162	0	
161	N173A	0.684478	3.5	-7.227162	0	
162	N174A	2.467972	3.5	-3.63806	0	
163	N175A	2.684478	3.5	-3.76306	0	
164	N176A	4.467972	3.5	-0.173959	0	
165	N177A	4.684478	3.5	-0.298959	0	



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Joint Coordinates and Temperatures (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Temp [F]	Detach From Diap...
166	N178A	6.363805	3.5	3.109721	0	
167	N179	6.580312	3.5	2.984721	0	
168	N180A	-6.551305	3.5	3.43448	0	
169	N181A	-0.301305	3.5	-7.390837	0	
170	N182A	-6.342972	3.5	3.073637	0	
171	N183A	-6.559478	3.5	2.948637	0	
172	N184A	-4.342972	3.5	-0.390465	0	
173	N185A	-4.559478	3.5	-0.515465	0	
174	N186A	-2.342972	3.5	-3.854567	0	
175	N187A	-2.559478	3.5	-3.979567	0	
176	N188A	-0.405472	3.5	-7.210415	0	
177	N189A	-0.621978	3.5	-7.335415	0	
178	N190A	-2.125	3.5	3.956357	0	
179	N191A	-2.125	3.5	4.206357	0	
180	N192A	-0.	-3	-1.5	0	
181	N193A	-0.	0	-4.5	0	
182	N194A	-1.299038	-3	.75	0	
183	N195A	-3.897114	0	2.25	0	
184	N196A	1.299038	-3	.75	0	
185	N197A	3.897114	0	2.25	0	
186	N187B	-5.419009	3.5	1.795047	0	
187	N188B	-4.264061	3.5	3.795476	0	
188	N189B	-4.37604	3.5	3.795476	0	
189	N190B	-5.474999	3.5	1.892024	0	
190	N191B	-5.558336	3.5	1.714607	0	
191	N192B	-4.264061	3.5	3.956357	0	
192	N194B	4.264061	3.5	3.795476	0	
193	N195B	5.419009	3.5	1.795047	0	
194	N196B	5.474999	3.5	1.892024	0	
195	N197B	4.37604	3.5	3.795476	0	
196	N198A	4.264061	3.5	3.956357	0	
197	N199A	5.558336	3.5	1.714607	0	

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design ...	A [in ²]	I _{yy} [in ⁴]	I _{zz} [in ⁴]	J [in ⁴]
1	Face Horizontal	PIPE 3.0	Beam	Pipe	A53 Gr.B	Typical	2.07	2.85	2.85	5.69
2	Standoff Horizontal	HSS4X4X3	Beam	SquareTube	A500 Gr.B Rect	Typical	2.58	6.21	6.21	10
3	Corner Plate	PL3/8x6	Beam	BAR	A36 Gr.36	Typical	2.25	.026	6.75	.101
4	Platform Crossmember	L3X3X3	Beam	Single Angle	A36 Gr.36	Typical	1.09	.948	.948	.014
5	Grating Support	L2x2x3	Beam	Single Angle	A36 Gr.36	Typical	.722	.271	.271	.009
6	Mount Pipe	PIPE 2.0	Column	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25
7	Cross Arm Plate	PL3/8x6	Beam	BAR	A36 Gr.36	Typical	2.25	.026	6.75	.101
8	Mount Pipe 2.5	PIPE 2.5	Column	Pipe	A53 Gr.B	Typical	1.61	1.45	1.45	2.89
9	Support Rail	PIPE 2.5	Beam	Pipe	A53 Gr.B	Typical	1.61	1.45	1.45	2.89
10	Support Rail Angle	L3X3X4	Beam	Single Angle	A36 Gr.36	Typical	1.44	1.23	1.23	.031
11	Kicker	LL3x3x3x3	Beam	Double Angl...	A36 Gr.36	Typical	2.18	4.09	1.9	.027

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (/1...	Density[k/ft^3]	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
2	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A500 Gr.B RND	29000	11154	.3	.65	.527	42	1.4	58	1.3
5	A500 Gr.B Rect	29000	11154	.3	.65	.527	46	1.4	58	1.3



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Hot Rolled Steel Properties (Continued)

	Label	E [ksil]	G [ksil]	Nu	Therm (/1...	Density[k/ft^3]	Yield[ksil]	Rv	Fulksil	Rt
6	A53 Gr.B	29000	11154	.3	.65	.49	35	1.6	60	1.2
7	A1085	29000	11154	.3	.65	.49	50	1.4	65	1.3
8	Q235	29000	11154	.3	.65	.49	35	1.5	58	1.2

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M100	N144A	N149			Standoff Horizontal	Beam	SquareTube	A500 Gr.B...	Typical
2	M101	N153	N155		180	Platform Crossme...	Beam	Single Angle	A36 Gr.36	Typical
3	M102	N154	N145		180	Platform Crossme...	Beam	Single Angle	A36 Gr.36	Typical
4	M103	N164	N165			Corner Plate	Beam	BAR	A36 Gr.36	Typical
5	M104	N147	N152			RIGID	None	None	RIGID	Typical
6	M105	N146	N151			RIGID	None	None	RIGID	Typical
7	M106	N169	N146			Grating Support	Beam	Single Angle	A36 Gr.36	Typical
8	M107	N147	N171			Grating Support	Beam	Single Angle	A36 Gr.36	Typical
9	M108	N171	N172			RIGID	None	None	RIGID	Typical
10	M109	N154	N148A			RIGID	None	None	RIGID	Typical
11	M110	N148A	N155			RIGID	None	None	RIGID	Typical
12	M111	N153	N157			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
13	M112	N157	N158			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
14	M113	N158	N162			RIGID	None	None	RIGID	Typical
15	M114	N165	N159			Corner Plate	Beam	BAR	A36 Gr.36	Typical
16	M115	N159	N166			RIGID	None	None	RIGID	Typical
17	M116	N145	N156			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
18	M117	N156	N160			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
19	M118	N160	N163			RIGID	None	None	RIGID	Typical
20	M119	N164	N161			Corner Plate	Beam	BAR	A36 Gr.36	Typical
21	M120	N161	N167			RIGID	None	None	RIGID	Typical
22	M121	N172	N168			RIGID	None	None	RIGID	Typical
23	M122	N168	N170			RIGID	None	None	RIGID	Typical
24	M123	N169	N170			RIGID	None	None	RIGID	Typical
25	M124	N173	N178			Standoff Horizontal	Beam	SquareTube	A500 Gr.B...	Typical
26	M125	N182	N184		180	Platform Crossme...	Beam	Single Angle	A36 Gr.36	Typical
27	M126	N183	N174		180	Platform Crossme...	Beam	Single Angle	A36 Gr.36	Typical
28	M127	N193	N194			Corner Plate	Beam	BAR	A36 Gr.36	Typical
29	M128	N176	N181			RIGID	None	None	RIGID	Typical
30	M129	N175	N180			RIGID	None	None	RIGID	Typical
31	M130	N198	N175			Grating Support	Beam	Single Angle	A36 Gr.36	Typical
32	M131	N176	N200			Grating Support	Beam	Single Angle	A36 Gr.36	Typical
33	M132	N200	N201			RIGID	None	None	RIGID	Typical
34	M133	N183	N177			RIGID	None	None	RIGID	Typical
35	M134	N177	N184			RIGID	None	None	RIGID	Typical
36	M135	N182	N186			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
37	M136	N186	N187			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
38	M137	N187	N191			RIGID	None	None	RIGID	Typical
39	M138	N194	N188			Corner Plate	Beam	BAR	A36 Gr.36	Typical
40	M139	N188	N195			RIGID	None	None	RIGID	Typical
41	M140	N174	N185			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
42	M141	N185	N189			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
43	M142	N189	N192			RIGID	None	None	RIGID	Typical
44	M143	N193	N190			Corner Plate	Beam	BAR	A36 Gr.36	Typical
45	M144	N190	N196			RIGID	None	None	RIGID	Typical
46	M145	N201	N197			RIGID	None	None	RIGID	Typical
47	M146	N197	N199			RIGID	None	None	RIGID	Typical
48	M147	N198	N199			RIGID	None	None	RIGID	Typical
49	M148	N202	N207			Standoff Horizontal	Beam	SquareTube	A500 Gr.B...	Typical



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
50	M149	N211	N213		180	Platform Crossme...	Beam	Single Angle	A36 Gr.36	Typical
51	M150	N212	N203		180	Platform Crossme...	Beam	Single Angle	A36 Gr.36	Typical
52	M151	N222	N223			Corner Plate	Beam	BAR	A36 Gr.36	Typical
53	M152	N205	N210			RIGID	None	None	RIGID	Typical
54	M153	N204	N209			RIGID	None	None	RIGID	Typical
55	M154	N227	N204			Grating Support	Beam	Single Angle	A36 Gr.36	Typical
56	M155	N205	N229			Grating Support	Beam	Single Angle	A36 Gr.36	Typical
57	M156	N229	N230			RIGID	None	None	RIGID	Typical
58	M157	N212	N206			RIGID	None	None	RIGID	Typical
59	M158	N206	N213			RIGID	None	None	RIGID	Typical
60	M159	N211	N215			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
61	M160	N215	N216			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
62	M161	N216	N220			RIGID	None	None	RIGID	Typical
63	M162	N223	N217			Corner Plate	Beam	BAR	A36 Gr.36	Typical
64	M163	N217	N224			RIGID	None	None	RIGID	Typical
65	M164	N203	N214			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
66	M165	N214	N218			Cross Arm Plate	Beam	BAR	A36 Gr.36	Typical
67	M166	N218	N221			RIGID	None	None	RIGID	Typical
68	M167	N222	N219			Corner Plate	Beam	BAR	A36 Gr.36	Typical
69	M168	N219	N225			RIGID	None	None	RIGID	Typical
70	M169	N230	N226			RIGID	None	None	RIGID	Typical
71	M170	N226	N228			RIGID	None	None	RIGID	Typical
72	M171	N227	N228			RIGID	None	None	RIGID	Typical
73	M172	N231	N230A			Face Horizontal	Beam	Pipe	A53 Gr.B	Typical
74	M173	N231A	N232			RIGID	None	None	RIGID	Typical
75	MP1A	N233	N234			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
76	M175	N235	N236			RIGID	None	None	RIGID	Typical
77	MP2A	N237	N238			Mount Pipe 2.5	Column	Pipe	A53 Gr.B	Typical
78	M177	N239	N240			RIGID	None	None	RIGID	Typical
79	MP3A	N241	N242			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
80	M179	N243	N244			RIGID	None	None	RIGID	Typical
81	MP4A	N245	N246			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
82	M181	N248	N247			Face Horizontal	Beam	Pipe	A53 Gr.B	Typical
83	M182	N249	N250			RIGID	None	None	RIGID	Typical
84	MP1C	N251	N252			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
85	M184	N253	N254			RIGID	None	None	RIGID	Typical
86	MP2C	N255	N256			Mount Pipe 2.5	Column	Pipe	A53 Gr.B	Typical
87	M186	N257	N258			RIGID	None	None	RIGID	Typical
88	MP3C	N259	N260			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
89	M188	N261	N262			RIGID	None	None	RIGID	Typical
90	MP4C	N263	N264			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
91	M190	N266	N265			Face Horizontal	Beam	Pipe	A53 Gr.B	Typical
92	M191	N267	N268			RIGID	None	None	RIGID	Typical
93	MP1B	N269	N270			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
94	M193	N271	N272			RIGID	None	None	RIGID	Typical
95	MP2B	N273	N274			Mount Pipe 2.5	Column	Pipe	A53 Gr.B	Typical
96	M195	N275	N276			RIGID	None	None	RIGID	Typical
97	MP3B	N277	N278			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
98	M197	N279	N280			RIGID	None	None	RIGID	Typical
99	MP4B	N281	N282			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
100	M100A	N140	N141			RIGID	None	None	RIGID	Typical
101	M101A	N143	N142			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
102	M102A	N146A	N147A		90	Support Rail Angle	Beam	Single Angle	A36 Gr.36	Typical
103	M103A	N147A	N144			RIGID	None	None	RIGID	Typical
104	M104A	N144	N148			RIGID	None	None	RIGID	Typical
105	M105A	N146A	N145A			RIGID	None	None	RIGID	Typical
106	M106A	N145A	N149A			RIGID	None	None	RIGID	Typical



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
107	M116A	N163A	N162A			Support Rail	Beam	Pipe	A53 Gr.B	Typical
108	M117A	N164A	N165A			RIGID	None	None	RIGID	Typical
109	M118A	N166A	N167A			RIGID	None	None	RIGID	Typical
110	M119A	N168A	N169A			RIGID	None	None	RIGID	Typical
111	M120A	N171A	N170A			Support Rail	Beam	Pipe	A53 Gr.B	Typical
112	M121A	N172A	N173A			RIGID	None	None	RIGID	Typical
113	M122A	N174A	N175A			RIGID	None	None	RIGID	Typical
114	M123A	N176A	N177A			RIGID	None	None	RIGID	Typical
115	M124A	N178A	N179			RIGID	None	None	RIGID	Typical
116	M125A	N181A	N180A			Support Rail	Beam	Pipe	A53 Gr.B	Typical
117	M126A	N182A	N183A			RIGID	None	None	RIGID	Typical
118	M127A	N184A	N185A			RIGID	None	None	RIGID	Typical
119	M128A	N186A	N187A			RIGID	None	None	RIGID	Typical
120	M129A	N188A	N189A			RIGID	None	None	RIGID	Typical
121	M131A	N190A	N191A			RIGID	None	None	RIGID	Typical
122	M132A	N192A	N193A			Kicker	Beam	Double Angle ...	A36 Gr.36	Typical
123	M133A	N194A	N195A			Kicker	Beam	Double Angle ...	A36 Gr.36	Typical
124	M134A	N196A	N197A			Kicker	Beam	Double Angle ...	A36 Gr.36	Typical
125	M125B	N189B	N190B		90	Support Rail Angle	Beam	Single Angle	A36 Gr.36	Typical
126	M126B	N190B	N187B			RIGID	None	None	RIGID	Typical
127	M127B	N187B	N191B			RIGID	None	None	RIGID	Typical
128	M128B	N189B	N188B			RIGID	None	None	RIGID	Typical
129	M129B	N188B	N192B			RIGID	None	None	RIGID	Typical
130	M130A	N196B	N197B		90	Support Rail Angle	Beam	Single Angle	A36 Gr.36	Typical
131	M131B	N197B	N194B			RIGID	None	None	RIGID	Typical
132	M132B	N194B	N198A			RIGID	None	None	RIGID	Typical
133	M133B	N196B	N195B			RIGID	None	None	RIGID	Typical
134	M134B	N195B	N199A			RIGID	None	None	RIGID	Typical

Member Advanced Data

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rati...A...	Inactive	Seismic ...
1	M100						Yes			None
2	M101						Yes	Default		None
3	M102						Yes	Default		None
4	M103						Yes	** NA **		None
5	M104						Yes	** NA **		None
6	M105						Yes	Default		None
7	M106	OOOOOX	OOOOOX				Yes	Default		None
8	M107	OOOOOX	OOOOOX				Yes	Default		None
9	M108						Yes	** NA **		None
10	M109						Yes	** NA **		None
11	M110						Yes			None
12	M111						Yes			None
13	M112						Yes	** NA **		None
14	M113		BenPIN				Yes	** NA **		None
15	M114						Yes	** NA **		None
16	M115		BenPIN				Yes	** NA **		None
17	M116						Yes			None
18	M117						Yes	** NA **		None
19	M118		BenPIN				Yes	** NA **		None
20	M119						Yes	** NA **		None
21	M120		BenPIN				Yes	** NA **		None
22	M121						Yes	** NA **		None
23	M122						Yes	** NA **		None
24	M123						Yes	** NA **		None



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rati... A...	Inactive	Seismic ...
25	M124						Yes			None
26	M125						Yes	Default		None
27	M126						Yes	Default		None
28	M127						Yes	Default		None
29	M128						Yes	** NA **		None
30	M129						Yes	** NA **		None
31	M130	OOOOOX	OOOOOX				Yes	Default		None
32	M131	OOOOOX	OOOOOX				Yes	Default		None
33	M132						Yes	** NA **		None
34	M133						Yes	** NA **		None
35	M134						Yes	** NA **		None
36	M135						Yes	** NA **		None
37	M136						Yes			None
38	M137		BenPIN				Yes	** NA **		None
39	M138						Yes	** NA **		None
40	M139		BenPIN				Yes	** NA **		None
41	M140						Yes			None
42	M141						Yes			None
43	M142		BenPIN				Yes	** NA **		None
44	M143						Yes			None
45	M144		BenPIN				Yes	** NA **		None
46	M145						Yes	** NA **		None
47	M146						Yes	** NA **		None
48	M147						Yes	** NA **		None
49	M148						Yes	** NA **		None
50	M149						Yes	Default		None
51	M150						Yes	Default		None
52	M151						Yes	Default		None
53	M152						Yes	** NA **		None
54	M153						Yes	** NA **		None
55	M154	OOOOOX	OOOOOX				Yes	Default		None
56	M155	OOOOOX	OOOOOX				Yes	Default		None
57	M156						Yes	** NA **		None
58	M157						Yes	** NA **		None
59	M158						Yes	** NA **		None
60	M159						Yes	** NA **		None
61	M160						Yes			None
62	M161		BenPIN				Yes	** NA **		None
63	M162						Yes	** NA **		None
64	M163		BenPIN				Yes	** NA **		None
65	M164						Yes	** NA **		None
66	M165						Yes	** NA **		None
67	M166		BenPIN				Yes	** NA **		None
68	M167						Yes	** NA **		None
69	M168		BenPIN				Yes	** NA **		None
70	M169						Yes	** NA **		None
71	M170						Yes	** NA **		None
72	M171						Yes	** NA **		None
73	M172						Yes	** NA **		None
74	M173						Yes	** NA **		None
75	MP1A						Yes	** NA **		None
76	M175						Yes	** NA **		None
77	MP2A						Yes	** NA **		None
78	M177						Yes	** NA **		None
79	MP3A						Yes	** NA **		None
80	M179						Yes	** NA **		None
81	MP4A						Yes	** NA **		None



Company Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rati...A...	Inactive	Seismic...
82	M181						Yes			None
83	M182						Yes	** NA **		None
84	MP1C						Yes	** NA **		None
85	M184						Yes	** NA **		None
86	MP2C						Yes	** NA **		None
87	M186						Yes	** NA **		None
88	MP3C						Yes	** NA **		None
89	M188						Yes	** NA **		None
90	MP4C						Yes	** NA **		None
91	M190						Yes	** NA **		None
92	M191						Yes	** NA **		None
93	MP1B						Yes	** NA **		None
94	M193						Yes	** NA **		None
95	MP2B						Yes	** NA **		None
96	M195						Yes	** NA **		None
97	MP3B						Yes	** NA **		None
98	M197						Yes	** NA **		None
99	MP4B						Yes	** NA **		None
100	M100A						Yes	** NA **		None
101	M101A						Yes	Default		None
102	M102A						Yes	** NA **		None
103	M103A						Yes	** NA **		None
104	M104A		000000				Yes	** NA **		None
105	M105A						Yes	** NA **		None
106	M106A		000000				Yes	** NA **		None
107	M116A						Yes	** NA **		None
108	M117A						Yes	** NA **		None
109	M118A						Yes	** NA **		None
110	M119A						Yes	** NA **		None
111	M120A						Yes	** NA **		None
112	M121A						Yes	** NA **		None
113	M122A						Yes	** NA **		None
114	M123A						Yes	** NA **		None
115	M124A						Yes	** NA **		None
116	M125A						Yes	** NA **		None
117	M126A						Yes	** NA **		None
118	M127A						Yes	** NA **		None
119	M128A						Yes	** NA **		None
120	M129A						Yes	** NA **		None
121	M131A						Yes			None
122	M132A	BenPIN	BenPIN				Yes			None
123	M133A	BenPIN	BenPIN				Yes			None
124	M134A	BenPIN	BenPIN				Yes			None
125	M125B						Yes	Default		None
126	M126B						Yes	** NA **		None
127	M127B		000000				Yes	** NA **		None
128	M128B						Yes	** NA **		None
129	M129B		000000				Yes	** NA **		None
130	M130A						Yes	Default		None
131	M131B						Yes	** NA **		None
132	M132B		000000				Yes	** NA **		None
133	M133B						Yes	** NA **		None
134	M134B		000000				Yes	** NA **		None



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 1 : Antenna D)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	Y	-39	1
2	MP2A	My	-.024	1
3	MP2A	Mz	.022	1
4	MP2A	Y	-39	4
5	MP2A	My	-.024	4
6	MP2A	Mz	.022	4
7	MP2B	Y	-39	1
8	MP2B	My	-.02	1
9	MP2B	Mz	-.026	1
10	MP2B	Y	-39	4
11	MP2B	My	-.02	4
12	MP2B	Mz	-.026	4
13	MP2C	Y	-39	1
14	MP2C	My	.031	1
15	MP2C	Mz	.009	1
16	MP2C	Y	-39	4
17	MP2C	My	.031	4
18	MP2C	Mz	.009	4
19	MP2A	Y	-39	1
20	MP2A	My	-.015	1
21	MP2A	Mz	-.029	1
22	MP2A	Y	-39	4
23	MP2A	My	-.015	4
24	MP2A	Mz	-.029	4
25	MP2B	Y	-39	1
26	MP2B	My	.03	1
27	MP2B	Mz	-.012	1
28	MP2B	Y	-39	4
29	MP2B	My	.03	4
30	MP2B	Mz	-.012	4
31	MP2C	Y	-39	1
32	MP2C	My	-.018	1
33	MP2C	Mz	.027	1
34	MP2C	Y	-39	4
35	MP2C	My	-.018	4
36	MP2C	Mz	.027	4
37	MP1A	Y	-28.65	1.5
38	MP1A	My	-.014	1.5
39	MP1A	Mz	-.002	1.5
40	MP1A	Y	-28.65	3.5
41	MP1A	My	-.014	3.5
42	MP1A	Mz	-.002	3.5
43	MP1B	Y	-28.65	1.5
44	MP1B	My	.004	1.5
45	MP1B	Mz	-.014	1.5
46	MP1B	Y	-28.65	3.5
47	MP1B	My	.004	3.5
48	MP1B	Mz	-.014	3.5
49	MP1C	Y	-28.65	1.5
50	MP1C	My	.005	1.5
51	MP1C	Mz	.013	1.5
52	MP1C	Y	-28.65	3.5
53	MP1C	My	.005	3.5
54	MP1C	Mz	.013	3.5
55	MP3A	Y	-74.7	2
56	MP3A	My	.037	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 1 : Antenna D) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
57	MP3A	Mz	.006	2
58	MP3B	Y	-74.7	2
59	MP3B	My	-.01	2
60	MP3B	Mz	.036	2
61	MP3C	Y	-74.7	2
62	MP3C	My	-.013	2
63	MP3C	Mz	-.035	2
64	MP2A	Y	-79.1	2
65	MP2A	My	.039	2
66	MP2A	Mz	.007	2
67	MP2B	Y	-79.1	2
68	MP2B	My	-.01	2
69	MP2B	Mz	.038	2
70	MP2C	Y	-79.1	2
71	MP2C	My	-.014	2
72	MP2C	Mz	-.037	2
73	M101A	Y	-32	1
74	M101A	My	0	1
75	M101A	Mz	0	1

Member Point Loads (BLC 2 : Antenna Di)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	Y	-82.894	1
2	MP2A	My	-.05	1
3	MP2A	Mz	.047	1
4	MP2A	Y	-82.894	4
5	MP2A	My	-.05	4
6	MP2A	Mz	.047	4
7	MP2B	Y	-82.894	1
8	MP2B	My	-.043	1
9	MP2B	Mz	-.054	1
10	MP2B	Y	-82.894	4
11	MP2B	My	-.043	4
12	MP2B	Mz	-.054	4
13	MP2C	Y	-82.894	1
14	MP2C	My	.066	1
15	MP2C	Mz	.02	1
16	MP2C	Y	-82.894	4
17	MP2C	My	.066	4
18	MP2C	Mz	.02	4
19	MP2A	Y	-82.894	1
20	MP2A	My	-.031	1
21	MP2A	Mz	-.062	1
22	MP2A	Y	-82.894	4
23	MP2A	My	-.031	4
24	MP2A	Mz	-.062	4
25	MP2B	Y	-82.894	1
26	MP2B	My	.064	1
27	MP2B	Mz	-.026	1
28	MP2B	Y	-82.894	4
29	MP2B	My	.064	4
30	MP2B	Mz	-.026	4
31	MP2C	Y	-82.894	1
32	MP2C	My	-.038	1
33	MP2C	Mz	.058	1
34	MP2C	Y	-82.894	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 2 : Antenna Di) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
35	MP2C	Mv	-.038	4
36	MP2C	Mz	.058	4
37	MP1A	Y	-29.939	1.5
38	MP1A	My	-.015	1.5
39	MP1A	Mz	-.003	1.5
40	MP1A	Y	-29.939	3.5
41	MP1A	Mv	-.015	3.5
42	MP1A	Mz	-.003	3.5
43	MP1B	Y	-29.939	1.5
44	MP1B	Mv	.004	1.5
45	MP1B	Mz	-.014	1.5
46	MP1B	Y	-29.939	3.5
47	MP1B	Mv	.004	3.5
48	MP1B	Mz	-.014	3.5
49	MP1C	Y	-29.939	1.5
50	MP1C	Mv	.005	1.5
51	MP1C	Mz	.014	1.5
52	MP1C	Y	-29.939	3.5
53	MP1C	Mv	.005	3.5
54	MP1C	Mz	.014	3.5
55	MP3A	Y	-45.144	2
56	MP3A	Mv	.022	2
57	MP3A	Mz	.004	2
58	MP3B	Y	-45.144	2
59	MP3B	Mv	-.006	2
60	MP3B	Mz	.022	2
61	MP3C	Y	-45.144	2
62	MP3C	My	-.008	2
63	MP3C	Mz	-.021	2
64	MP2A	Y	-45.622	2
65	MP2A	Mv	.022	2
66	MP2A	Mz	.004	2
67	MP2B	Y	-45.622	2
68	MP2B	My	-.006	2
69	MP2B	Mz	.022	2
70	MP2C	Y	-45.622	2
71	MP2C	Mv	-.008	2
72	MP2C	Mz	-.021	2
73	M101A	Y	-88.375	1
74	M101A	Mv	0	1
75	M101A	Mz	0	1

Member Point Loads (BLC 3 : Antenna Wo (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	0	1
2	MP2A	Z	-118.763	1
3	MP2A	Mx	-.068	1
4	MP2A	X	0	4
5	MP2A	Z	-118.763	4
6	MP2A	Mx	-.068	4
7	MP2B	X	0	1
8	MP2B	Z	-91.58	1
9	MP2B	Mx	.06	1
10	MP2B	X	0	4
11	MP2B	Z	-91.58	4
12	MP2B	Mx	.06	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 3 : Antenna Wo (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
13	MP2C	X	0	1
14	MP2C	Z	-93.085	1
15	MP2C	Mx	-.023	1
16	MP2C	X	0	4
17	MP2C	Z	-93.085	4
18	MP2C	Mx	-.023	4
19	MP2A	X	0	1
20	MP2A	Z	-118.763	1
21	MP2A	Mx	.088	1
22	MP2A	X	0	4
23	MP2A	Z	-118.763	4
24	MP2A	Mx	.088	4
25	MP2B	X	0	1
26	MP2B	Z	-91.58	1
27	MP2B	Mx	.028	1
28	MP2B	X	0	4
29	MP2B	Z	-91.58	4
30	MP2B	Mx	.028	4
31	MP2C	X	0	1
32	MP2C	Z	-93.085	1
33	MP2C	Mx	-.065	1
34	MP2C	X	0	4
35	MP2C	Z	-93.085	4
36	MP2C	Mx	-.065	4
37	MP1A	X	0	1.5
38	MP1A	Z	-94.11	1.5
39	MP1A	Mx	.008	1.5
40	MP1A	X	0	3.5
41	MP1A	Z	-94.11	3.5
42	MP1A	Mx	.008	3.5
43	MP1B	X	0	1.5
44	MP1B	Z	-40.881	1.5
45	MP1B	Mx	.02	1.5
46	MP1B	X	0	3.5
47	MP1B	Z	-40.881	3.5
48	MP1B	Mx	.02	3.5
49	MP1C	X	0	1.5
50	MP1C	Z	-43.828	1.5
51	MP1C	Mx	-.021	1.5
52	MP1C	X	0	3.5
53	MP1C	Z	-43.828	3.5
54	MP1C	Mx	-.021	3.5
55	MP3A	X	0	2
56	MP3A	Z	-77.653	2
57	MP3A	Mx	-.007	2
58	MP3B	X	0	2
59	MP3B	Z	-54.353	2
60	MP3B	Mx	-.026	2
61	MP3C	X	0	2
62	MP3C	Z	-55.643	2
63	MP3C	Mx	.026	2
64	MP2A	X	0	2
65	MP2A	Z	-93.715	2
66	MP2A	Mx	-.008	2
67	MP2B	X	0	2
68	MP2B	Z	-66.533	2
69	MP2B	Mx	-.032	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 3 : Antenna Wo (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
70	MP2C	X	0	2
71	MP2C	Z	-68.038	2
72	MP2C	Mx	.032	2
73	M101A	X	0	1
74	M101A	Z	-150.79	1
75	M101A	Mx	0	1

Member Point Loads (BLC 4 : Antenna Wo (30 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	58.074	1
2	MP2A	Z	-100.588	1
3	MP2A	Mx	-.093	1
4	MP2A	X	58.074	4
5	MP2A	Z	-100.588	4
6	MP2A	Mx	-.093	4
7	MP2B	X	45.79	1
8	MP2B	Z	-79.31	1
9	MP2B	Mx	.028	1
10	MP2B	X	45.79	4
11	MP2B	Z	-79.31	4
12	MP2B	Mx	.028	4
13	MP2C	X	53.615	1
14	MP2C	Z	-92.865	1
15	MP2C	Mx	.02	1
16	MP2C	X	53.615	4
17	MP2C	Z	-92.865	4
18	MP2C	Mx	.02	4
19	MP2A	X	58.074	1
20	MP2A	Z	-100.588	1
21	MP2A	Mx	.053	1
22	MP2A	X	58.074	4
23	MP2A	Z	-100.588	4
24	MP2A	Mx	.053	4
25	MP2B	X	45.79	1
26	MP2B	Z	-79.31	1
27	MP2B	Mx	.06	1
28	MP2B	X	45.79	4
29	MP2B	Z	-79.31	4
30	MP2B	Mx	.06	4
31	MP2C	X	53.615	1
32	MP2C	Z	-92.865	1
33	MP2C	Mx	-.089	1
34	MP2C	X	53.615	4
35	MP2C	Z	-92.865	4
36	MP2C	Mx	-.089	4
37	MP1A	X	44.496	1.5
38	MP1A	Z	-77.069	1.5
39	MP1A	Mx	-.015	1.5
40	MP1A	X	44.496	3.5
41	MP1A	Z	-77.069	3.5
42	MP1A	Mx	-.015	3.5
43	MP1B	X	20.44	1.5
44	MP1B	Z	-35.404	1.5
45	MP1B	Mx	.02	1.5
46	MP1B	X	20.44	3.5
47	MP1B	Z	-35.404	3.5



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 4 : Antenna Wo (30 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
48	MP1B	Mx	.02	3.5
49	MP1C	X	35.764	1.5
50	MP1C	Z	-61.946	1.5
51	MP1C	Mx	-.023	1.5
52	MP1C	X	35.764	3.5
53	MP1C	Z	-61.946	3.5
54	MP1C	Mx	-.023	3.5
55	MP3A	X	37.706	2
56	MP3A	Z	-65.309	2
57	MP3A	Mx	.013	2
58	MP3B	X	27.177	2
59	MP3B	Z	-47.071	2
60	MP3B	Mx	-.026	2
61	MP3C	X	33.884	2
62	MP3C	Z	-58.689	2
63	MP3C	Mx	.022	2
64	MP2A	X	45.551	2
65	MP2A	Z	-78.896	2
66	MP2A	Mx	.016	2
67	MP2B	X	33.266	2
68	MP2B	Z	-57.619	2
69	MP2B	Mx	-.032	2
70	MP2C	X	41.092	2
71	MP2C	Z	-71.173	2
72	MP2C	Mx	.026	2
73	M101A	X	65.781	1
74	M101A	Z	-113.936	1
75	M101A	Mx	0	1

Member Point Loads (BLC 5 : Antenna Wo (60 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	88.337	1
2	MP2A	Z	-51.001	1
3	MP2A	Mx	-.083	1
4	MP2A	X	88.337	4
5	MP2A	Z	-51.001	4
6	MP2A	Mx	-.083	4
7	MP2B	X	90.601	1
8	MP2B	Z	-52.308	1
9	MP2B	Mx	-.012	1
10	MP2B	X	90.601	4
11	MP2B	Z	-52.308	4
12	MP2B	Mx	-.012	4
13	MP2C	X	102.851	1
14	MP2C	Z	-59.381	1
15	MP2C	Mx	.068	1
16	MP2C	X	102.851	4
17	MP2C	Z	-59.381	4
18	MP2C	Mx	.068	4
19	MP2A	X	88.337	1
20	MP2A	Z	-51.001	1
21	MP2A	Mx	.005	1
22	MP2A	X	88.337	4
23	MP2A	Z	-51.001	4
24	MP2A	Mx	.005	4
25	MP2B	X	90.601	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 5 : Antenna Wo (60 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
26	MP2B	Z	-52.308	1
27	MP2B	Mx	.086	1
28	MP2B	X	90.601	4
29	MP2B	Z	-52.308	4
30	MP2B	Mx	.086	4
31	MP2C	X	102.851	1
32	MP2C	Z	-59.381	1
33	MP2C	Mx	-.088	1
34	MP2C	X	102.851	4
35	MP2C	Z	-59.381	4
36	MP2C	Mx	-.088	4
37	MP1A	X	53.079	1.5
38	MP1A	Z	-30.645	1.5
39	MP1A	Mx	-.023	1.5
40	MP1A	X	53.079	3.5
41	MP1A	Z	-30.645	3.5
42	MP1A	Mx	-.023	3.5
43	MP1B	X	57.512	1.5
44	MP1B	Z	-33.205	1.5
45	MP1B	Mx	.023	1.5
46	MP1B	X	57.512	3.5
47	MP1B	Z	-33.205	3.5
48	MP1B	Mx	.023	3.5
49	MP1C	X	81.502	1.5
50	MP1C	Z	-47.055	1.5
51	MP1C	Mx	-.008	1.5
52	MP1C	X	81.502	3.5
53	MP1C	Z	-47.055	3.5
54	MP1C	Mx	-.008	3.5
55	MP3A	X	54.808	2
56	MP3A	Z	-31.644	2
57	MP3A	Mx	.024	2
58	MP3B	X	56.749	2
59	MP3B	Z	-32.764	2
60	MP3B	Mx	-.023	2
61	MP3C	X	67.249	2
62	MP3C	Z	-38.826	2
63	MP3C	Mx	.007	2
64	MP2A	X	66.645	2
65	MP2A	Z	-38.478	2
66	MP2A	Mx	.029	2
67	MP2B	X	68.909	2
68	MP2B	Z	-39.785	2
69	MP2B	Mx	-.028	2
70	MP2C	X	81.16	2
71	MP2C	Z	-46.858	2
72	MP2C	Mx	.008	2
73	M101A	X	105.61	1
74	M101A	Z	-60.974	1
75	M101A	Mx	0	1

Member Point Loads (BLC 6 : Antenna Wo (90 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	90.471	1
2	MP2A	Z	0	1
3	MP2A	Mx	-.055	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 6 : Antenna Wo (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
4	MP2A	X	90.471	4
5	MP2A	Z	0	4
6	MP2A	Mx	-.055	4
7	MP2B	X	117.654	1
8	MP2B	Z	0	1
9	MP2B	Mx	-.061	1
10	MP2B	X	117.654	4
11	MP2B	Z	0	4
12	MP2B	Mx	-.061	4
13	MP2C	X	116.149	1
14	MP2C	Z	0	1
15	MP2C	Mx	.093	1
16	MP2C	X	116.149	4
17	MP2C	Z	0	4
18	MP2C	Mx	.093	4
19	MP2A	X	90.471	1
20	MP2A	Z	0	1
21	MP2A	Mx	-.034	1
22	MP2A	X	90.471	4
23	MP2A	Z	0	4
24	MP2A	Mx	-.034	4
25	MP2B	X	117.654	1
26	MP2B	Z	0	1
27	MP2B	Mx	.091	1
28	MP2B	X	117.654	4
29	MP2B	Z	0	4
30	MP2B	Mx	.091	4
31	MP2C	X	116.149	1
32	MP2C	Z	0	1
33	MP2C	Mx	-.053	1
34	MP2C	X	116.149	4
35	MP2C	Z	0	4
36	MP2C	Mx	-.053	4
37	MP1A	X	38.709	1.5
38	MP1A	Z	0	1.5
39	MP1A	Mx	-.019	1.5
40	MP1A	X	38.709	3.5
41	MP1A	Z	0	3.5
42	MP1A	Mx	-.019	3.5
43	MP1B	X	91.939	1.5
44	MP1B	Z	0	1.5
45	MP1B	Mx	.012	1.5
46	MP1B	X	91.939	3.5
47	MP1B	Z	0	3.5
48	MP1B	Mx	.012	3.5
49	MP1C	X	88.991	1.5
50	MP1C	Z	0	1.5
51	MP1C	Mx	.015	1.5
52	MP1C	X	88.991	3.5
53	MP1C	Z	0	3.5
54	MP1C	Mx	.015	3.5
55	MP3A	X	53.403	2
56	MP3A	Z	0	2
57	MP3A	Mx	.026	2
58	MP3B	X	76.702	2
59	MP3B	Z	0	2
60	MP3B	Mx	-.01	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 6 : Antenna Wo (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
61	MP3C	X	75.412	2
62	MP3C	Z	0	2
63	MP3C	Mx	-013	2
64	MP2A	X	65.424	2
65	MP2A	Z	0	2
66	MP2A	Mx	.032	2
67	MP2B	X	92.606	2
68	MP2B	Z	0	2
69	MP2B	Mx	-012	2
70	MP2C	X	91.101	2
71	MP2C	Z	0	2
72	MP2C	Mx	-016	2
73	M101A	X	131.562	1
74	M101A	Z	0	1
75	M101A	Mx	0	1

Member Point Loads (BLC 7 : Antenna Wo (120 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	80.614	1
2	MP2A	Z	46.542	1
3	MP2A	Mx	-.023	1
4	MP2A	X	80.614	4
5	MP2A	Z	46.542	4
6	MP2A	Mx	-.023	4
7	MP2B	X	101.891	1
8	MP2B	Z	58.827	1
9	MP2B	Mx	-.091	1
10	MP2B	X	101.891	4
11	MP2B	Z	58.827	4
12	MP2B	Mx	-.091	4
13	MP2C	X	88.337	1
14	MP2C	Z	51.001	1
15	MP2C	Mx	.083	1
16	MP2C	X	88.337	4
17	MP2C	Z	51.001	4
18	MP2C	Mx	.083	4
19	MP2A	X	80.614	1
20	MP2A	Z	46.542	1
21	MP2A	Mx	-.065	1
22	MP2A	X	80.614	4
23	MP2A	Z	46.542	4
24	MP2A	Mx	-.065	4
25	MP2B	X	101.891	1
26	MP2B	Z	58.827	1
27	MP2B	Mx	.061	1
28	MP2B	X	101.891	4
29	MP2B	Z	58.827	4
30	MP2B	Mx	.061	4
31	MP2C	X	88.337	1
32	MP2C	Z	51.001	1
33	MP2C	Mx	-.005	1
34	MP2C	X	88.337	4
35	MP2C	Z	51.001	4
36	MP2C	Mx	-.005	4
37	MP1A	X	37.956	1.5
38	MP1A	Z	21.914	1.5



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 7 : Antenna Wo (120 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
39	MP1A	Mx	-.021	1.5
40	MP1A	X	37.956	3.5
41	MP1A	Z	21.914	3.5
42	MP1A	Mx	-.021	3.5
43	MP1B	X	79.621	1.5
44	MP1B	Z	45.969	1.5
45	MP1B	Mx	-.012	1.5
46	MP1B	X	79.621	3.5
47	MP1B	Z	45.969	3.5
48	MP1B	Mx	-.012	3.5
49	MP1C	X	53.079	1.5
50	MP1C	Z	30.645	1.5
51	MP1C	Mx	.023	1.5
52	MP1C	X	53.079	3.5
53	MP1C	Z	30.645	3.5
54	MP1C	Mx	.023	3.5
55	MP3A	X	48.189	2
56	MP3A	Z	27.822	2
57	MP3A	Mx	.026	2
58	MP3B	X	66.426	2
59	MP3B	Z	38.351	2
60	MP3B	Mx	.01	2
61	MP3C	X	54.808	2
62	MP3C	Z	31.644	2
63	MP3C	Mx	-.024	2
64	MP2A	X	58.922	2
65	MP2A	Z	34.019	2
66	MP2A	Mx	.032	2
67	MP2B	X	80.199	2
68	MP2B	Z	46.303	2
69	MP2B	Mx	.012	2
70	MP2C	X	66.645	2
71	MP2C	Z	38.478	2
72	MP2C	Mx	-.029	2
73	M101A	X	130.588	1
74	M101A	Z	75.395	1
75	M101A	Mx	0	1

Member Point Loads (BLC 8 : Antenna Wo (150 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	53.615	1
2	MP2A	Z	92.865	1
3	MP2A	Mx	.02	1
4	MP2A	X	53.615	4
5	MP2A	Z	92.865	4
6	MP2A	Mx	.02	4
7	MP2B	X	52.308	1
8	MP2B	Z	90.601	1
9	MP2B	Mx	-.086	1
10	MP2B	X	52.308	4
11	MP2B	Z	90.601	4
12	MP2B	Mx	-.086	4
13	MP2C	X	45.235	1
14	MP2C	Z	78.35	1
15	MP2C	Mx	.055	1
16	MP2C	X	45.235	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 8 : Antenna Wo (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
17	MP2C	Z	78.35	4
18	MP2C	Mx	.055	4
19	MP2A	X	53.615	1
20	MP2A	Z	92.865	1
21	MP2A	Mx	-.089	1
22	MP2A	X	53.615	4
23	MP2A	Z	92.865	4
24	MP2A	Mx	-.089	4
25	MP2B	X	52.308	1
26	MP2B	Z	90.601	1
27	MP2B	Mx	.012	1
28	MP2B	X	52.308	4
29	MP2B	Z	90.601	4
30	MP2B	Mx	.012	4
31	MP2C	X	45.235	1
32	MP2C	Z	78.35	1
33	MP2C	Mx	.034	1
34	MP2C	X	45.235	4
35	MP2C	Z	78.35	4
36	MP2C	Mx	.034	4
37	MP1A	X	35.764	1.5
38	MP1A	Z	61.946	1.5
39	MP1A	Mx	-.023	1.5
40	MP1A	X	35.764	3.5
41	MP1A	Z	61.946	3.5
42	MP1A	Mx	-.023	3.5
43	MP1B	X	33.205	1.5
44	MP1B	Z	57.512	1.5
45	MP1B	Mx	-.023	1.5
46	MP1B	X	33.205	3.5
47	MP1B	Z	57.512	3.5
48	MP1B	Mx	-.023	3.5
49	MP1C	X	19.355	1.5
50	MP1C	Z	33.523	1.5
51	MP1C	Mx	.019	1.5
52	MP1C	X	19.355	3.5
53	MP1C	Z	33.523	3.5
54	MP1C	Mx	.019	3.5
55	MP3A	X	33.884	2
56	MP3A	Z	58.689	2
57	MP3A	Mx	.022	2
58	MP3B	X	32.764	2
59	MP3B	Z	56.749	2
60	MP3B	Mx	.023	2
61	MP3C	X	26.701	2
62	MP3C	Z	46.248	2
63	MP3C	Mx	-.026	2
64	MP2A	X	41.092	2
65	MP2A	Z	71.173	2
66	MP2A	Mx	.026	2
67	MP2B	X	39.785	2
68	MP2B	Z	68.909	2
69	MP2B	Mx	.028	2
70	MP2C	X	32.712	2
71	MP2C	Z	56.659	2
72	MP2C	Mx	-.032	2
73	M101A	X	80.202	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 8 : Antenna Wo (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
74	M101A	Z	138.914	1
75	M101A	Mx	0	1

Member Point Loads (BLC 9 : Antenna Wo (180 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	0	1
2	MP2A	Z	118.763	1
3	MP2A	Mx	.068	1
4	MP2A	X	0	4
5	MP2A	Z	118.763	4
6	MP2A	Mx	.068	4
7	MP2B	X	0	1
8	MP2B	Z	91.58	1
9	MP2B	Mx	-.06	1
10	MP2B	X	0	4
11	MP2B	Z	91.58	4
12	MP2B	Mx	-.06	4
13	MP2C	X	0	1
14	MP2C	Z	93.085	1
15	MP2C	Mx	.023	1
16	MP2C	X	0	4
17	MP2C	Z	93.085	4
18	MP2C	Mx	.023	4
19	MP2A	X	0	1
20	MP2A	Z	118.763	1
21	MP2A	Mx	-.088	1
22	MP2A	X	0	4
23	MP2A	Z	118.763	4
24	MP2A	Mx	-.088	4
25	MP2B	X	0	1
26	MP2B	Z	91.58	1
27	MP2B	Mx	-.028	1
28	MP2B	X	0	4
29	MP2B	Z	91.58	4
30	MP2B	Mx	-.028	4
31	MP2C	X	0	1
32	MP2C	Z	93.085	1
33	MP2C	Mx	.065	1
34	MP2C	X	0	4
35	MP2C	Z	93.085	4
36	MP2C	Mx	.065	4
37	MP1A	X	0	1.5
38	MP1A	Z	94.11	1.5
39	MP1A	Mx	-.008	1.5
40	MP1A	X	0	3.5
41	MP1A	Z	94.11	3.5
42	MP1A	Mx	-.008	3.5
43	MP1B	X	0	1.5
44	MP1B	Z	40.881	1.5
45	MP1B	Mx	-.02	1.5
46	MP1B	X	0	3.5
47	MP1B	Z	40.881	3.5
48	MP1B	Mx	-.02	3.5
49	MP1C	X	0	1.5
50	MP1C	Z	43.828	1.5
51	MP1C	Mx	.021	1.5



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 9 : Antenna Wo (180 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
52	MP1C	X	0	3.5
53	MP1C	Z	43.828	3.5
54	MP1C	Mx	.021	3.5
55	MP3A	X	0	2
56	MP3A	Z	77.653	2
57	MP3A	Mx	.007	2
58	MP3B	X	0	2
59	MP3B	Z	54.353	2
60	MP3B	Mx	.026	2
61	MP3C	X	0	2
62	MP3C	Z	55.643	2
63	MP3C	Mx	-.026	2
64	MP2A	X	0	2
65	MP2A	Z	93.715	2
66	MP2A	Mx	.008	2
67	MP2B	X	0	2
68	MP2B	Z	66.533	2
69	MP2B	Mx	.032	2
70	MP2C	X	0	2
71	MP2C	Z	68.038	2
72	MP2C	Mx	-.032	2
73	M101A	X	0	1
74	M101A	Z	150.79	1
75	M101A	Mx	0	1

Member Point Loads (BLC 10 : Antenna Wo (210 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-58.074	1
2	MP2A	Z	100.588	1
3	MP2A	Mx	.093	1
4	MP2A	X	-58.074	4
5	MP2A	Z	100.588	4
6	MP2A	Mx	.093	4
7	MP2B	X	-45.79	1
8	MP2B	Z	79.31	1
9	MP2B	Mx	-.028	1
10	MP2B	X	-45.79	4
11	MP2B	Z	79.31	4
12	MP2B	Mx	-.028	4
13	MP2C	X	-53.615	1
14	MP2C	Z	92.865	1
15	MP2C	Mx	-.02	1
16	MP2C	X	-53.615	4
17	MP2C	Z	92.865	4
18	MP2C	Mx	-.02	4
19	MP2A	X	-58.074	1
20	MP2A	Z	100.588	1
21	MP2A	Mx	-.053	1
22	MP2A	X	-58.074	4
23	MP2A	Z	100.588	4
24	MP2A	Mx	-.053	4
25	MP2B	X	-45.79	1
26	MP2B	Z	79.31	1
27	MP2B	Mx	-.06	1
28	MP2B	X	-45.79	4
29	MP2B	Z	79.31	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 10 : Antenna Wo (210 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
30	MP2B	Mx	-.06	4
31	MP2C	X	-53.615	1
32	MP2C	Z	92.865	1
33	MP2C	Mx	.089	1
34	MP2C	X	-53.615	4
35	MP2C	Z	92.865	4
36	MP2C	Mx	.089	4
37	MP1A	X	-44.496	1.5
38	MP1A	Z	77.069	1.5
39	MP1A	Mx	.015	1.5
40	MP1A	X	-44.496	3.5
41	MP1A	Z	77.069	3.5
42	MP1A	Mx	.015	3.5
43	MP1B	X	-20.44	1.5
44	MP1B	Z	35.404	1.5
45	MP1B	Mx	-.02	1.5
46	MP1B	X	-20.44	3.5
47	MP1B	Z	35.404	3.5
48	MP1B	Mx	-.02	3.5
49	MP1C	X	-35.764	1.5
50	MP1C	Z	61.946	1.5
51	MP1C	Mx	.023	1.5
52	MP1C	X	-35.764	3.5
53	MP1C	Z	61.946	3.5
54	MP1C	Mx	.023	3.5
55	MP3A	X	-37.706	2
56	MP3A	Z	65.309	2
57	MP3A	Mx	-.013	2
58	MP3B	X	-27.177	2
59	MP3B	Z	47.071	2
60	MP3B	Mx	.026	2
61	MP3C	X	-33.884	2
62	MP3C	Z	58.689	2
63	MP3C	Mx	-.022	2
64	MP2A	X	-45.551	2
65	MP2A	Z	78.896	2
66	MP2A	Mx	-.016	2
67	MP2B	X	-33.266	2
68	MP2B	Z	57.619	2
69	MP2B	Mx	.032	2
70	MP2C	X	-41.092	2
71	MP2C	Z	71.173	2
72	MP2C	Mx	-.026	2
73	M101A	X	-65.781	1
74	M101A	Z	113.936	1
75	M101A	Mx	0	1

Member Point Loads (BLC 11 : Antenna Wo (240 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-88.337	1
2	MP2A	Z	51.001	1
3	MP2A	Mx	.083	1
4	MP2A	X	-88.337	4
5	MP2A	Z	51.001	4
6	MP2A	Mx	.083	4
7	MP2B	X	-90.601	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 11 : Antenna Wo (240 Deg)) (Continued)

	Member Label	Direction	Magnitude(lb.k-ft)	Location(ft.%)
8	MP2B	Z	52.308	1
9	MP2B	Mx	.012	1
10	MP2B	X	-90.601	4
11	MP2B	Z	52.308	4
12	MP2B	Mx	.012	4
13	MP2C	X	-102.851	1
14	MP2C	Z	59.381	1
15	MP2C	Mx	-.068	1
16	MP2C	X	-102.851	4
17	MP2C	Z	59.381	4
18	MP2C	Mx	-.068	4
19	MP2A	X	-88.337	1
20	MP2A	Z	51.001	1
21	MP2A	Mx	-.005	1
22	MP2A	X	-88.337	4
23	MP2A	Z	51.001	4
24	MP2A	Mx	-.005	4
25	MP2B	X	-90.601	1
26	MP2B	Z	52.308	1
27	MP2B	Mx	-.086	1
28	MP2B	X	-90.601	4
29	MP2B	Z	52.308	4
30	MP2B	Mx	-.086	4
31	MP2C	X	-102.851	1
32	MP2C	Z	59.381	1
33	MP2C	Mx	.088	1
34	MP2C	X	-102.851	4
35	MP2C	Z	59.381	4
36	MP2C	Mx	.088	4
37	MP1A	X	-53.079	1.5
38	MP1A	Z	30.645	1.5
39	MP1A	Mx	.023	1.5
40	MP1A	X	-53.079	3.5
41	MP1A	Z	30.645	3.5
42	MP1A	Mx	.023	3.5
43	MP1B	X	-57.512	1.5
44	MP1B	Z	33.205	1.5
45	MP1B	Mx	-.023	1.5
46	MP1B	X	-57.512	3.5
47	MP1B	Z	33.205	3.5
48	MP1B	Mx	-.023	3.5
49	MP1C	X	-81.502	1.5
50	MP1C	Z	47.055	1.5
51	MP1C	Mx	.008	1.5
52	MP1C	X	-81.502	3.5
53	MP1C	Z	47.055	3.5
54	MP1C	Mx	.008	3.5
55	MP3A	X	-54.808	2
56	MP3A	Z	31.644	2
57	MP3A	Mx	-.024	2
58	MP3B	X	-56.749	2
59	MP3B	Z	32.764	2
60	MP3B	Mx	.023	2
61	MP3C	X	-67.249	2
62	MP3C	Z	38.826	2
63	MP3C	Mx	-.007	2
64	MP2A	X	-66.645	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 11 : Antenna Wo (240 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
65	MP2A	Z	38.478	2
66	MP2A	Mx	-.029	2
67	MP2B	X	-68.909	2
68	MP2B	Z	39.785	2
69	MP2B	Mx	.028	2
70	MP2C	X	-81.16	2
71	MP2C	Z	46.858	2
72	MP2C	Mx	-.008	2
73	M101A	X	-105.61	1
74	M101A	Z	60.974	1
75	M101A	Mx	0	1

Member Point Loads (BLC 12 : Antenna Wo (270 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-90.471	1
2	MP2A	Z	0	1
3	MP2A	Mx	.055	1
4	MP2A	X	-90.471	4
5	MP2A	Z	0	4
6	MP2A	Mx	.055	4
7	MP2B	X	-117.654	1
8	MP2B	Z	0	1
9	MP2B	Mx	.061	1
10	MP2B	X	-117.654	4
11	MP2B	Z	0	4
12	MP2B	Mx	.061	4
13	MP2C	X	-116.149	1
14	MP2C	Z	0	1
15	MP2C	Mx	-.093	1
16	MP2C	X	-116.149	4
17	MP2C	Z	0	4
18	MP2C	Mx	-.093	4
19	MP2A	X	-90.471	1
20	MP2A	Z	0	1
21	MP2A	Mx	.034	1
22	MP2A	X	-90.471	4
23	MP2A	Z	0	4
24	MP2A	Mx	.034	4
25	MP2B	X	-117.654	1
26	MP2B	Z	0	1
27	MP2B	Mx	-.091	1
28	MP2B	X	-117.654	4
29	MP2B	Z	0	4
30	MP2B	Mx	-.091	4
31	MP2C	X	-116.149	1
32	MP2C	Z	0	1
33	MP2C	Mx	.053	1
34	MP2C	X	-116.149	4
35	MP2C	Z	0	4
36	MP2C	Mx	.053	4
37	MP1A	X	-38.709	1.5
38	MP1A	Z	0	1.5
39	MP1A	Mx	.019	1.5
40	MP1A	X	-38.709	3.5
41	MP1A	Z	0	3.5
42	MP1A	Mx	.019	3.5



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 12 : Antenna Wo (270 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
43	MP1B	X	-91.939	1.5
44	MP1B	Z	0	1.5
45	MP1B	Mx	-.012	1.5
46	MP1B	X	-91.939	3.5
47	MP1B	Z	0	3.5
48	MP1B	Mx	-.012	3.5
49	MP1C	X	-88.991	1.5
50	MP1C	Z	0	1.5
51	MP1C	Mx	-.015	1.5
52	MP1C	X	-88.991	3.5
53	MP1C	Z	0	3.5
54	MP1C	Mx	-.015	3.5
55	MP3A	X	-53.403	2
56	MP3A	Z	0	2
57	MP3A	Mx	-.026	2
58	MP3B	X	-76.702	2
59	MP3B	Z	0	2
60	MP3B	Mx	.01	2
61	MP3C	X	-75.412	2
62	MP3C	Z	0	2
63	MP3C	Mx	.013	2
64	MP2A	X	-65.424	2
65	MP2A	Z	0	2
66	MP2A	Mx	-.032	2
67	MP2B	X	-92.606	2
68	MP2B	Z	0	2
69	MP2B	Mx	.012	2
70	MP2C	X	-91.101	2
71	MP2C	Z	0	2
72	MP2C	Mx	.016	2
73	M101A	X	-131.562	1
74	M101A	Z	0	1
75	M101A	Mx	0	1

Member Point Loads (BLC 13 : Antenna Wo (300 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-80.614	1
2	MP2A	Z	-46.542	1
3	MP2A	Mx	.023	1
4	MP2A	X	-80.614	4
5	MP2A	Z	-46.542	4
6	MP2A	Mx	.023	4
7	MP2B	X	-101.891	1
8	MP2B	Z	-58.827	1
9	MP2B	Mx	.091	1
10	MP2B	X	-101.891	4
11	MP2B	Z	-58.827	4
12	MP2B	Mx	.091	4
13	MP2C	X	-88.337	1
14	MP2C	Z	-51.001	1
15	MP2C	Mx	-.083	1
16	MP2C	X	-88.337	4
17	MP2C	Z	-51.001	4
18	MP2C	Mx	-.083	4
19	MP2A	X	-80.614	1
20	MP2A	Z	-46.542	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 13 : Antenna Wo (300 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
21	MP2A	Mx	.065	1
22	MP2A	X	-80.614	4
23	MP2A	Z	-46.542	4
24	MP2A	Mx	.065	4
25	MP2B	X	-101.891	1
26	MP2B	Z	-58.827	1
27	MP2B	Mx	-.061	1
28	MP2B	X	-101.891	4
29	MP2B	Z	-58.827	4
30	MP2B	Mx	-.061	4
31	MP2C	X	-88.337	1
32	MP2C	Z	-51.001	1
33	MP2C	Mx	.005	1
34	MP2C	X	-88.337	4
35	MP2C	Z	-51.001	4
36	MP2C	Mx	.005	4
37	MP1A	X	-37.956	1.5
38	MP1A	Z	-21.914	1.5
39	MP1A	Mx	.021	1.5
40	MP1A	X	-37.956	3.5
41	MP1A	Z	-21.914	3.5
42	MP1A	Mx	.021	3.5
43	MP1B	X	-79.621	1.5
44	MP1B	Z	-45.969	1.5
45	MP1B	Mx	.012	1.5
46	MP1B	X	-79.621	3.5
47	MP1B	Z	-45.969	3.5
48	MP1B	Mx	.012	3.5
49	MP1C	X	-53.079	1.5
50	MP1C	Z	-30.645	1.5
51	MP1C	Mx	-.023	1.5
52	MP1C	X	-53.079	3.5
53	MP1C	Z	-30.645	3.5
54	MP1C	Mx	-.023	3.5
55	MP3A	X	-48.189	2
56	MP3A	Z	-27.822	2
57	MP3A	Mx	-.026	2
58	MP3B	X	-66.426	2
59	MP3B	Z	-38.351	2
60	MP3B	Mx	-.01	2
61	MP3C	X	-54.808	2
62	MP3C	Z	-31.644	2
63	MP3C	Mx	.024	2
64	MP2A	X	-58.922	2
65	MP2A	Z	-34.019	2
66	MP2A	Mx	-.032	2
67	MP2B	X	-80.199	2
68	MP2B	Z	-46.303	2
69	MP2B	Mx	-.012	2
70	MP2C	X	-66.645	2
71	MP2C	Z	-38.478	2
72	MP2C	Mx	.029	2
73	M101A	X	-130.588	1
74	M101A	Z	-75.395	1
75	M101A	Mx	0	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 14 : Antenna Wo (330 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-53.615	1
2	MP2A	Z	-92.865	1
3	MP2A	Mx	-.02	1
4	MP2A	X	-53.615	4
5	MP2A	Z	-92.865	4
6	MP2A	Mx	-.02	4
7	MP2B	X	-52.308	1
8	MP2B	Z	-90.601	1
9	MP2B	Mx	.086	1
10	MP2B	X	-52.308	4
11	MP2B	Z	-90.601	4
12	MP2B	Mx	.086	4
13	MP2C	X	-45.235	1
14	MP2C	Z	-78.35	1
15	MP2C	Mx	-.055	1
16	MP2C	X	-45.235	4
17	MP2C	Z	-78.35	4
18	MP2C	Mx	-.055	4
19	MP2A	X	-53.615	1
20	MP2A	Z	-92.865	1
21	MP2A	Mx	.089	1
22	MP2A	X	-53.615	4
23	MP2A	Z	-92.865	4
24	MP2A	Mx	.089	4
25	MP2B	X	-52.308	1
26	MP2B	Z	-90.601	1
27	MP2B	Mx	-.012	1
28	MP2B	X	-52.308	4
29	MP2B	Z	-90.601	4
30	MP2B	Mx	-.012	4
31	MP2C	X	-45.235	1
32	MP2C	Z	-78.35	1
33	MP2C	Mx	-.034	1
34	MP2C	X	-45.235	4
35	MP2C	Z	-78.35	4
36	MP2C	Mx	-.034	4
37	MP1A	X	-35.764	1.5
38	MP1A	Z	-61.946	1.5
39	MP1A	Mx	.023	1.5
40	MP1A	X	-35.764	3.5
41	MP1A	Z	-61.946	3.5
42	MP1A	Mx	.023	3.5
43	MP1B	X	-33.205	1.5
44	MP1B	Z	-57.512	1.5
45	MP1B	Mx	.023	1.5
46	MP1B	X	-33.205	3.5
47	MP1B	Z	-57.512	3.5
48	MP1B	Mx	.023	3.5
49	MP1C	X	-19.355	1.5
50	MP1C	Z	-33.523	1.5
51	MP1C	Mx	-.019	1.5
52	MP1C	X	-19.355	3.5
53	MP1C	Z	-33.523	3.5
54	MP1C	Mx	-.019	3.5
55	MP3A	X	-33.884	2
56	MP3A	Z	-58.689	2
57	MP3A	Mx	-.022	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 14 : Antenna Wo (330 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
58	MP3B	X	-32.764	2
59	MP3B	Z	-56.749	2
60	MP3B	Mx	-.023	2
61	MP3C	X	-26.701	2
62	MP3C	Z	-46.248	2
63	MP3C	Mx	.026	2
64	MP2A	X	-41.092	2
65	MP2A	Z	-71.173	2
66	MP2A	Mx	-.026	2
67	MP2B	X	-39.785	2
68	MP2B	Z	-68.909	2
69	MP2B	Mx	-.028	2
70	MP2C	X	-32.712	2
71	MP2C	Z	-56.659	2
72	MP2C	Mx	.032	2
73	M101A	X	-80.202	1
74	M101A	Z	-138.914	1
75	M101A	Mx	0	1

Member Point Loads (BLC 15 : Antenna Wi (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	0	1
2	MP2A	Z	-40.002	1
3	MP2A	Mx	-.023	1
4	MP2A	X	0	4
5	MP2A	Z	-40.002	4
6	MP2A	Mx	-.023	4
7	MP2B	X	0	1
8	MP2B	Z	-31.145	1
9	MP2B	Mx	.02	1
10	MP2B	X	0	4
11	MP2B	Z	-31.145	4
12	MP2B	Mx	.02	4
13	MP2C	X	0	1
14	MP2C	Z	-31.636	1
15	MP2C	Mx	-.008	1
16	MP2C	X	0	4
17	MP2C	Z	-31.636	4
18	MP2C	Mx	-.008	4
19	MP2A	X	0	1
20	MP2A	Z	-40.002	1
21	MP2A	Mx	.03	1
22	MP2A	X	0	4
23	MP2A	Z	-40.002	4
24	MP2A	Mx	.03	4
25	MP2B	X	0	1
26	MP2B	Z	-31.145	1
27	MP2B	Mx	.01	1
28	MP2B	X	0	4
29	MP2B	Z	-31.145	4
30	MP2B	Mx	.01	4
31	MP2C	X	0	1
32	MP2C	Z	-31.636	1
33	MP2C	Mx	-.022	1
34	MP2C	X	0	4
35	MP2C	Z	-31.636	4



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 15 : Antenna Wi (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
36	MP2C	Mx	-.022	4
37	MP1A	X	0	1.5
38	MP1A	Z	-15.943	1.5
39	MP1A	Mx	.001	1.5
40	MP1A	X	0	3.5
41	MP1A	Z	-15.943	3.5
42	MP1A	Mx	.001	3.5
43	MP1B	X	0	1.5
44	MP1B	Z	-7.482	1.5
45	MP1B	Mx	.004	1.5
46	MP1B	X	0	3.5
47	MP1B	Z	-7.482	3.5
48	MP1B	Mx	.004	3.5
49	MP1C	X	0	1.5
50	MP1C	Z	-7.95	1.5
51	MP1C	Mx	-.004	1.5
52	MP1C	X	0	3.5
53	MP1C	Z	-7.95	3.5
54	MP1C	Mx	-.004	3.5
55	MP3A	X	0	2
56	MP3A	Z	-16.608	2
57	MP3A	Mx	-.001	2
58	MP3B	X	0	2
59	MP3B	Z	-12.004	2
60	MP3B	Mx	-.006	2
61	MP3C	X	0	2
62	MP3C	Z	-12.259	2
63	MP3C	Mx	.006	2
64	MP2A	X	0	2
65	MP2A	Z	-16.615	2
66	MP2A	Mx	-.001	2
67	MP2B	X	0	2
68	MP2B	Z	-12.194	2
69	MP2B	Mx	-.006	2
70	MP2C	X	0	2
71	MP2C	Z	-12.439	2
72	MP2C	Mx	.006	2
73	M101A	X	0	1
74	M101A	Z	-32.563	1
75	M101A	Mx	0	1

Member Point Loads (BLC 16 : Antenna Wi (30 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	19.575	1
2	MP2A	Z	-33.905	1
3	MP2A	Mx	-.031	1
4	MP2A	X	19.575	4
5	MP2A	Z	-33.905	4
6	MP2A	Mx	-.031	4
7	MP2B	X	15.573	1
8	MP2B	Z	-26.973	1
9	MP2B	Mx	.01	1
10	MP2B	X	15.573	4
11	MP2B	Z	-26.973	4
12	MP2B	Mx	.01	4
13	MP2C	X	18.122	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 16 : Antenna Wi (30 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
14	MP2C	Z	-31.389	1
15	MP2C	Mx	.007	1
16	MP2C	X	18.122	4
17	MP2C	Z	-31.389	4
18	MP2C	Mx	.007	4
19	MP2A	X	19.575	1
20	MP2A	Z	-33.905	1
21	MP2A	Mx	.018	1
22	MP2A	X	19.575	4
23	MP2A	Z	-33.905	4
24	MP2A	Mx	.018	4
25	MP2B	X	15.573	1
26	MP2B	Z	-26.973	1
27	MP2B	Mx	.02	1
28	MP2B	X	15.573	4
29	MP2B	Z	-26.973	4
30	MP2B	Mx	.02	4
31	MP2C	X	18.122	1
32	MP2C	Z	-31.389	1
33	MP2C	Mx	-.03	1
34	MP2C	X	18.122	4
35	MP2C	Z	-31.389	4
36	MP2C	Mx	-.03	4
37	MP1A	X	7.565	1.5
38	MP1A	Z	-13.102	1.5
39	MP1A	Mx	-.003	1.5
40	MP1A	X	7.565	3.5
41	MP1A	Z	-13.102	3.5
42	MP1A	Mx	-.003	3.5
43	MP1B	X	3.741	1.5
44	MP1B	Z	-6.48	1.5
45	MP1B	Mx	.004	1.5
46	MP1B	X	3.741	3.5
47	MP1B	Z	-6.48	3.5
48	MP1B	Mx	.004	3.5
49	MP1C	X	6.177	1.5
50	MP1C	Z	-10.698	1.5
51	MP1C	Mx	-.004	1.5
52	MP1C	X	6.177	3.5
53	MP1C	Z	-10.698	3.5
54	MP1C	Mx	-.004	3.5
55	MP3A	X	8.083	2
56	MP3A	Z	-.14	2
57	MP3A	Mx	.003	2
58	MP3B	X	6.002	2
59	MP3B	Z	-10.395	2
60	MP3B	Mx	-.006	2
61	MP3C	X	7.327	2
62	MP3C	Z	-12.691	2
63	MP3C	Mx	.005	2
64	MP2A	X	8.095	2
65	MP2A	Z	-14.02	2
66	MP2A	Mx	.003	2
67	MP2B	X	6.097	2
68	MP2B	Z	-10.56	2
69	MP2B	Mx	-.006	2
70	MP2C	X	7.37	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 16 : Antenna Wi (30 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
71	MP2C	Z	-12.764	2
72	MP2C	Mx	.005	2
73	M101A	X	14.405	1
74	M101A	Z	-24.951	1
75	M101A	Mx	0	1

Member Point Loads (BLC 17 : Antenna Wi (60 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	X	29.914	1
2	MP2A	Z	-17.271	1
3	MP2A	Mx	-.028	1
4	MP2A	X	29.914	4
5	MP2A	Z	-17.271	4
6	MP2A	Mx	-.028	4
7	MP2B	X	30.651	1
8	MP2B	Z	-17.697	1
9	MP2B	Mx	-.004	1
10	MP2B	X	30.651	4
11	MP2B	Z	-17.697	4
12	MP2B	Mx	-.004	4
13	MP2C	X	34.643	1
14	MP2C	Z	-20.001	1
15	MP2C	Mx	.023	1
16	MP2C	X	34.643	4
17	MP2C	Z	-20.001	4
18	MP2C	Mx	.023	4
19	MP2A	X	29.914	1
20	MP2A	Z	-17.271	1
21	MP2A	Mx	.002	1
22	MP2A	X	29.914	4
23	MP2A	Z	-17.271	4
24	MP2A	Mx	.002	4
25	MP2B	X	30.651	1
26	MP2B	Z	-17.697	1
27	MP2B	Mx	.029	1
28	MP2B	X	30.651	4
29	MP2B	Z	-17.697	4
30	MP2B	Mx	.029	4
31	MP2C	X	34.643	1
32	MP2C	Z	-20.001	1
33	MP2C	Mx	-.03	1
34	MP2C	X	34.643	4
35	MP2C	Z	-20.001	4
36	MP2C	Mx	-.03	4
37	MP1A	X	9.289	1.5
38	MP1A	Z	-5.363	1.5
39	MP1A	Mx	-.004	1.5
40	MP1A	X	9.289	3.5
41	MP1A	Z	-5.363	3.5
42	MP1A	Mx	-.004	3.5
43	MP1B	X	9.994	1.5
44	MP1B	Z	-5.77	1.5
45	MP1B	Mx	.004	1.5
46	MP1B	X	9.994	3.5
47	MP1B	Z	-5.77	3.5
48	MP1B	Mx	.004	3.5



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 17 : Antenna Wi (60 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
49	MP1C	X	13.807	1.5
50	MP1C	Z	-7.971	1.5
51	MP1C	Mx	-.001	1.5
52	MP1C	X	13.807	3.5
53	MP1C	Z	-7.971	3.5
54	MP1C	Mx	-.001	3.5
55	MP3A	X	11.924	2
56	MP3A	Z	-6.885	2
57	MP3A	Mx	.005	2
58	MP3B	X	12.308	2
59	MP3B	Z	-7.106	2
60	MP3B	Mx	-.005	2
61	MP3C	X	14.383	2
62	MP3C	Z	-8.304	2
63	MP3C	Mx	.001	2
64	MP2A	X	12.028	2
65	MP2A	Z	-6.944	2
66	MP2A	Mx	.005	2
67	MP2B	X	12.396	2
68	MP2B	Z	-7.157	2
69	MP2B	Mx	-.005	2
70	MP2C	X	14.389	2
71	MP2C	Z	-8.307	2
72	MP2C	Mx	.001	2
73	M101A	X	23.325	1
74	M101A	Z	-13.467	1
75	M101A	Mx	0	1

Member Point Loads (BLC 18 : Antenna Wi (90 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	30.784	1
2	MP2A	Z	0	1
3	MP2A	Mx	-.019	1
4	MP2A	X	30.784	4
5	MP2A	Z	0	4
6	MP2A	Mx	-.019	4
7	MP2B	X	39.641	1
8	MP2B	Z	0	1
9	MP2B	Mx	-.02	1
10	MP2B	X	39.641	4
11	MP2B	Z	0	4
12	MP2B	Mx	-.02	4
13	MP2C	X	39.15	1
14	MP2C	Z	0	1
15	MP2C	Mx	.031	1
16	MP2C	X	39.15	4
17	MP2C	Z	0	4
18	MP2C	Mx	.031	4
19	MP2A	X	30.784	1
20	MP2A	Z	0	1
21	MP2A	Mx	-.012	1
22	MP2A	X	30.784	4
23	MP2A	Z	0	4
24	MP2A	Mx	-.012	4
25	MP2B	X	39.641	1
26	MP2B	Z	0	1



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 18 : Antenna Wi (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
27	MP2B	Mx	.031	1
28	MP2B	X	39.641	4
29	MP2B	Z	0	4
30	MP2B	Mx	.031	4
31	MP2C	X	39.15	1
32	MP2C	Z	0	1
33	MP2C	Mx	-.018	1
34	MP2C	X	39.15	4
35	MP2C	Z	0	4
36	MP2C	Mx	-.018	4
37	MP1A	X	7.137	1.5
38	MP1A	Z	0	1.5
39	MP1A	Mx	-.004	1.5
40	MP1A	X	7.137	3.5
41	MP1A	Z	0	3.5
42	MP1A	Mx	-.004	3.5
43	MP1B	X	15.597	1.5
44	MP1B	Z	0	1.5
45	MP1B	Mx	.002	1.5
46	MP1B	X	15.597	3.5
47	MP1B	Z	0	3.5
48	MP1B	Mx	.002	3.5
49	MP1C	X	15.129	1.5
50	MP1C	Z	0	1.5
51	MP1C	Mx	.003	1.5
52	MP1C	X	15.129	3.5
53	MP1C	Z	0	3.5
54	MP1C	Mx	.003	3.5
55	MP3A	X	11.816	2
56	MP3A	Z	0	2
57	MP3A	Mx	.006	2
58	MP3B	X	16.42	2
59	MP3B	Z	0	2
60	MP3B	Mx	-.002	2
61	MP3C	X	16.166	2
62	MP3C	Z	0	2
63	MP3C	Mx	-.003	2
64	MP2A	X	12.014	2
65	MP2A	Z	0	2
66	MP2A	Mx	.006	2
67	MP2B	X	16.434	2
68	MP2B	Z	0	2
69	MP2B	Mx	-.002	2
70	MP2C	X	16.189	2
71	MP2C	Z	0	2
72	MP2C	Mx	-.003	2
73	M101A	X	28.81	1
74	M101A	Z	0	1
75	M101A	Mx	0	1

Member Point Loads (BLC 19 : Antenna Wi (120 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	27.397	1
2	MP2A	Z	15.818	1
3	MP2A	Mx	-.008	1
4	MP2A	X	27.397	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 19 : Antenna Wi (120 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
5	MP2A	Z	15.818	4
6	MP2A	Mx	-.008	4
7	MP2B	X	34.33	1
8	MP2B	Z	19.82	1
9	MP2B	Mx	-.031	1
10	MP2B	X	34.33	4
11	MP2B	Z	19.82	4
12	MP2B	Mx	-.031	4
13	MP2C	X	29.914	1
14	MP2C	Z	17.271	1
15	MP2C	Mx	.028	1
16	MP2C	X	29.914	4
17	MP2C	Z	17.271	4
18	MP2C	Mx	.028	4
19	MP2A	X	27.397	1
20	MP2A	Z	15.818	1
21	MP2A	Mx	-.022	1
22	MP2A	X	27.397	4
23	MP2A	Z	15.818	4
24	MP2A	Mx	-.022	4
25	MP2B	X	34.33	1
26	MP2B	Z	19.82	1
27	MP2B	Mx	.02	1
28	MP2B	X	34.33	4
29	MP2B	Z	19.82	4
30	MP2B	Mx	.02	4
31	MP2C	X	29.914	1
32	MP2C	Z	17.271	1
33	MP2C	Mx	-.002	1
34	MP2C	X	29.914	4
35	MP2C	Z	17.271	4
36	MP2C	Mx	-.002	4
37	MP1A	X	6.885	1.5
38	MP1A	Z	3.975	1.5
39	MP1A	Mx	-.004	1.5
40	MP1A	X	6.885	3.5
41	MP1A	Z	3.975	3.5
42	MP1A	Mx	-.004	3.5
43	MP1B	X	13.508	1.5
44	MP1B	Z	7.799	1.5
45	MP1B	Mx	-.002	1.5
46	MP1B	X	13.508	3.5
47	MP1B	Z	7.799	3.5
48	MP1B	Mx	-.002	3.5
49	MP1C	X	9.289	1.5
50	MP1C	Z	5.363	1.5
51	MP1C	Mx	.004	1.5
52	MP1C	X	9.289	3.5
53	MP1C	Z	5.363	3.5
54	MP1C	Mx	.004	3.5
55	MP3A	X	10.616	2
56	MP3A	Z	6.129	2
57	MP3A	Mx	.006	2
58	MP3B	X	14.221	2
59	MP3B	Z	8.21	2
60	MP3B	Mx	.002	2
61	MP3C	X	11.924	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 19 : Antenna Wi (120 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
62	MP3C	Z	6.885	2
63	MP3C	Mx	-.005	2
64	MP2A	X	10.772	2
65	MP2A	Z	6.219	2
66	MP2A	Mx	.006	2
67	MP2B	X	14.232	2
68	MP2B	Z	8.217	2
69	MP2B	Mx	.002	2
70	MP2C	X	12.028	2
71	MP2C	Z	6.944	2
72	MP2C	Mx	-.005	2
73	M101A	X	28.201	1
74	M101A	Z	16.282	1
75	M101A	Mx	0	1

Member Point Loads (BLC 20 : Antenna Wi (150 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	18.122	1
2	MP2A	Z	31.389	1
3	MP2A	Mx	.007	1
4	MP2A	X	18.122	4
5	MP2A	Z	31.389	4
6	MP2A	Mx	.007	4
7	MP2B	X	17.697	1
8	MP2B	Z	30.651	1
9	MP2B	Mx	-.029	1
10	MP2B	X	17.697	4
11	MP2B	Z	30.651	4
12	MP2B	Mx	-.029	4
13	MP2C	X	15.392	1
14	MP2C	Z	26.66	1
15	MP2C	Mx	.019	1
16	MP2C	X	15.392	4
17	MP2C	Z	26.66	4
18	MP2C	Mx	.019	4
19	MP2A	X	18.122	1
20	MP2A	Z	31.389	1
21	MP2A	Mx	-.03	1
22	MP2A	X	18.122	4
23	MP2A	Z	31.389	4
24	MP2A	Mx	-.03	4
25	MP2B	X	17.697	1
26	MP2B	Z	30.651	1
27	MP2B	Mx	.004	1
28	MP2B	X	17.697	4
29	MP2B	Z	30.651	4
30	MP2B	Mx	.004	4
31	MP2C	X	15.392	1
32	MP2C	Z	26.66	1
33	MP2C	Mx	.012	1
34	MP2C	X	15.392	4
35	MP2C	Z	26.66	4
36	MP2C	Mx	.012	4
37	MP1A	X	6.177	1.5
38	MP1A	Z	10.698	1.5
39	MP1A	Mx	-.004	1.5



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 20 : Antenna Wi (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
40	MP1A	X	6.177	3.5
41	MP1A	Z	10.698	3.5
42	MP1A	Mx	-.004	3.5
43	MP1B	X	5.77	1.5
44	MP1B	Z	9.994	1.5
45	MP1B	Mx	-.004	1.5
46	MP1B	X	5.77	3.5
47	MP1B	Z	9.994	3.5
48	MP1B	Mx	-.004	3.5
49	MP1C	X	3.568	1.5
50	MP1C	Z	6.181	1.5
51	MP1C	Mx	.004	1.5
52	MP1C	X	3.568	3.5
53	MP1C	Z	6.181	3.5
54	MP1C	Mx	.004	3.5
55	MP3A	X	7.327	2
56	MP3A	Z	12.691	2
57	MP3A	Mx	.005	2
58	MP3B	X	7.106	2
59	MP3B	Z	12.308	2
60	MP3B	Mx	.005	2
61	MP3C	X	5.908	2
62	MP3C	Z	10.233	2
63	MP3C	Mx	-.006	2
64	MP2A	X	7.37	2
65	MP2A	Z	12.764	2
66	MP2A	Mx	.005	2
67	MP2B	X	7.157	2
68	MP2B	Z	12.396	2
69	MP2B	Mx	.005	2
70	MP2C	X	6.007	2
71	MP2C	Z	10.404	2
72	MP2C	Mx	-.006	2
73	M101A	X	17.22	1
74	M101A	Z	29.826	1
75	M101A	Mx	0	1

Member Point Loads (BLC 21 : Antenna Wi (180 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	0	1
2	MP2A	Z	40.002	1
3	MP2A	Mx	.023	1
4	MP2A	X	0	4
5	MP2A	Z	40.002	4
6	MP2A	Mx	.023	4
7	MP2B	X	0	1
8	MP2B	Z	31.145	1
9	MP2B	Mx	-.02	1
10	MP2B	X	0	4
11	MP2B	Z	31.145	4
12	MP2B	Mx	-.02	4
13	MP2C	X	0	1
14	MP2C	Z	31.636	1
15	MP2C	Mx	.008	1
16	MP2C	X	0	4
17	MP2C	Z	31.636	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 21 : Antenna Wi (180 Deg)) (Continued)

	Member Label	Direction	Magnitude(lb.k-ft)	Location(fft. %)
18	MP2C	Mx	.008	4
19	MP2A	X	0	1
20	MP2A	Z	40.002	1
21	MP2A	Mx	-.03	1
22	MP2A	X	0	4
23	MP2A	Z	40.002	4
24	MP2A	Mx	-.03	4
25	MP2B	X	0	1
26	MP2B	Z	31.145	1
27	MP2B	Mx	-.01	1
28	MP2B	X	0	4
29	MP2B	Z	31.145	4
30	MP2B	Mx	-.01	4
31	MP2C	X	0	1
32	MP2C	Z	31.636	1
33	MP2C	Mx	.022	1
34	MP2C	X	0	4
35	MP2C	Z	31.636	4
36	MP2C	Mx	.022	4
37	MP1A	X	0	1.5
38	MP1A	Z	15.943	1.5
39	MP1A	Mx	-.001	1.5
40	MP1A	X	0	3.5
41	MP1A	Z	15.943	3.5
42	MP1A	Mx	-.001	3.5
43	MP1B	X	0	1.5
44	MP1B	Z	7.482	1.5
45	MP1B	Mx	-.004	1.5
46	MP1B	X	0	3.5
47	MP1B	Z	7.482	3.5
48	MP1B	Mx	-.004	3.5
49	MP1C	X	0	1.5
50	MP1C	Z	7.95	1.5
51	MP1C	Mx	.004	1.5
52	MP1C	X	0	3.5
53	MP1C	Z	7.95	3.5
54	MP1C	Mx	.004	3.5
55	MP3A	X	0	2
56	MP3A	Z	16.608	2
57	MP3A	Mx	.001	2
58	MP3B	X	0	2
59	MP3B	Z	12.004	2
60	MP3B	Mx	.006	2
61	MP3C	X	0	2
62	MP3C	Z	12.259	2
63	MP3C	Mx	-.006	2
64	MP2A	X	0	2
65	MP2A	Z	16.615	2
66	MP2A	Mx	.001	2
67	MP2B	X	0	2
68	MP2B	Z	12.194	2
69	MP2B	Mx	.006	2
70	MP2C	X	0	2
71	MP2C	Z	12.439	2
72	MP2C	Mx	-.006	2
73	M101A	X	0	1
74	M101A	Z	32.563	1



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 21 : Antenna Wi (180 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
75	M101A	Mx	0	1

Member Point Loads (BLC 22 : Antenna Wi (210 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-19.575	1
2	MP2A	Z	33.905	1
3	MP2A	Mx	.031	1
4	MP2A	X	-19.575	4
5	MP2A	Z	33.905	4
6	MP2A	Mx	.031	4
7	MP2B	X	-15.573	1
8	MP2B	Z	26.973	1
9	MP2B	Mx	-.01	1
10	MP2B	X	-15.573	4
11	MP2B	Z	26.973	4
12	MP2B	Mx	-.01	4
13	MP2C	X	-18.122	1
14	MP2C	Z	31.389	1
15	MP2C	Mx	-.007	1
16	MP2C	X	-18.122	4
17	MP2C	Z	31.389	4
18	MP2C	Mx	-.007	4
19	MP2A	X	-19.575	1
20	MP2A	Z	33.905	1
21	MP2A	Mx	-.018	1
22	MP2A	X	-19.575	4
23	MP2A	Z	33.905	4
24	MP2A	Mx	-.018	4
25	MP2B	X	-15.573	1
26	MP2B	Z	26.973	1
27	MP2B	Mx	-.02	1
28	MP2B	X	-15.573	4
29	MP2B	Z	26.973	4
30	MP2B	Mx	-.02	4
31	MP2C	X	-18.122	1
32	MP2C	Z	31.389	1
33	MP2C	Mx	.03	1
34	MP2C	X	-18.122	4
35	MP2C	Z	31.389	4
36	MP2C	Mx	.03	4
37	MP1A	X	-7.565	1.5
38	MP1A	Z	13.102	1.5
39	MP1A	Mx	.003	1.5
40	MP1A	X	-7.565	3.5
41	MP1A	Z	13.102	3.5
42	MP1A	Mx	.003	3.5
43	MP1B	X	-3.741	1.5
44	MP1B	Z	6.48	1.5
45	MP1B	Mx	-.004	1.5
46	MP1B	X	-3.741	3.5
47	MP1B	Z	6.48	3.5
48	MP1B	Mx	-.004	3.5
49	MP1C	X	-6.177	1.5
50	MP1C	Z	10.698	1.5
51	MP1C	Mx	.004	1.5
52	MP1C	X	-6.177	3.5



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 22 : Antenna Wi (210 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
53	MP1C	Z	10.698	3.5
54	MP1C	Mx	.004	3.5
55	MP3A	X	-8.083	2
56	MP3A	Z	14	2
57	MP3A	Mx	-.003	2
58	MP3B	X	-6.002	2
59	MP3B	Z	10.395	2
60	MP3B	Mx	.006	2
61	MP3C	X	-7.327	2
62	MP3C	Z	12.691	2
63	MP3C	Mx	-.005	2
64	MP2A	X	-8.095	2
65	MP2A	Z	14.02	2
66	MP2A	Mx	-.003	2
67	MP2B	X	-6.097	2
68	MP2B	Z	10.56	2
69	MP2B	Mx	.006	2
70	MP2C	X	-7.37	2
71	MP2C	Z	12.764	2
72	MP2C	Mx	-.005	2
73	M101A	X	-14.405	1
74	M101A	Z	24.951	1
75	M101A	Mx	0	1

Member Point Loads (BLC 23 : Antenna Wi (240 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-29.914	1
2	MP2A	Z	17.271	1
3	MP2A	Mx	.028	1
4	MP2A	X	-29.914	4
5	MP2A	Z	17.271	4
6	MP2A	Mx	.028	4
7	MP2B	X	-30.651	1
8	MP2B	Z	17.697	1
9	MP2B	Mx	.004	1
10	MP2B	X	-30.651	4
11	MP2B	Z	17.697	4
12	MP2B	Mx	.004	4
13	MP2C	X	-34.643	1
14	MP2C	Z	20.001	1
15	MP2C	Mx	-.023	1
16	MP2C	X	-34.643	4
17	MP2C	Z	20.001	4
18	MP2C	Mx	-.023	4
19	MP2A	X	-29.914	1
20	MP2A	Z	17.271	1
21	MP2A	Mx	-.002	1
22	MP2A	X	-29.914	4
23	MP2A	Z	17.271	4
24	MP2A	Mx	-.002	4
25	MP2B	X	-30.651	1
26	MP2B	Z	17.697	1
27	MP2B	Mx	-.029	1
28	MP2B	X	-30.651	4
29	MP2B	Z	17.697	4
30	MP2B	Mx	-.029	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 23 : Antenna Wi (240 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb. k-ft]	Location[ft. %]
31	MP2C	X	-34.643	1
32	MP2C	Z	20.001	1
33	MP2C	Mx	.03	1
34	MP2C	X	-34.643	4
35	MP2C	Z	20.001	4
36	MP2C	Mx	.03	4
37	MP1A	X	-9.289	1.5
38	MP1A	Z	5.363	1.5
39	MP1A	Mx	.004	1.5
40	MP1A	X	-9.289	3.5
41	MP1A	Z	5.363	3.5
42	MP1A	Mx	.004	3.5
43	MP1B	X	-9.994	1.5
44	MP1B	Z	5.77	1.5
45	MP1B	Mx	-.004	1.5
46	MP1B	X	-9.994	3.5
47	MP1B	Z	5.77	3.5
48	MP1B	Mx	-.004	3.5
49	MP1C	X	-13.807	1.5
50	MP1C	Z	7.971	1.5
51	MP1C	Mx	.001	1.5
52	MP1C	X	-13.807	3.5
53	MP1C	Z	7.971	3.5
54	MP1C	Mx	.001	3.5
55	MP3A	X	-11.924	2
56	MP3A	Z	6.885	2
57	MP3A	Mx	-.005	2
58	MP3B	X	-12.308	2
59	MP3B	Z	7.106	2
60	MP3B	Mx	.005	2
61	MP3C	X	-14.383	2
62	MP3C	Z	8.304	2
63	MP3C	Mx	-.001	2
64	MP2A	X	-12.028	2
65	MP2A	Z	6.944	2
66	MP2A	Mx	-.005	2
67	MP2B	X	-12.396	2
68	MP2B	Z	7.157	2
69	MP2B	Mx	.005	2
70	MP2C	X	-14.389	2
71	MP2C	Z	8.307	2
72	MP2C	Mx	-.001	2
73	M101A	X	-23.325	1
74	M101A	Z	13.467	1
75	M101A	Mx	0	1

Member Point Loads (BLC 24 : Antenna Wi (270 Deg))

	Member Label	Direction	Magnitude[lb. k-ft]	Location[ft. %]
1	MP2A	X	-30.784	1
2	MP2A	Z	0	1
3	MP2A	Mx	.019	1
4	MP2A	X	-30.784	4
5	MP2A	Z	0	4
6	MP2A	Mx	.019	4
7	MP2B	X	-39.641	1
8	MP2B	Z	0	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 24 : Antenna Wi (270 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
9	MP2B	Mx	.02	1
10	MP2B	X	-39.641	4
11	MP2B	Z	0	4
12	MP2B	Mx	.02	4
13	MP2C	X	-39.15	1
14	MP2C	Z	0	1
15	MP2C	Mx	-.031	1
16	MP2C	X	-39.15	4
17	MP2C	Z	0	4
18	MP2C	Mx	-.031	4
19	MP2A	X	-30.784	1
20	MP2A	Z	0	1
21	MP2A	Mx	.012	1
22	MP2A	X	-30.784	4
23	MP2A	Z	0	4
24	MP2A	Mx	.012	4
25	MP2B	X	-39.641	1
26	MP2B	Z	0	1
27	MP2B	Mx	-.031	1
28	MP2B	X	-39.641	4
29	MP2B	Z	0	4
30	MP2B	Mx	-.031	4
31	MP2C	X	-39.15	1
32	MP2C	Z	0	1
33	MP2C	Mx	.018	1
34	MP2C	X	-39.15	4
35	MP2C	Z	0	4
36	MP2C	Mx	.018	4
37	MP1A	X	-7.137	1.5
38	MP1A	Z	0	1.5
39	MP1A	Mx	.004	1.5
40	MP1A	X	-7.137	3.5
41	MP1A	Z	0	3.5
42	MP1A	Mx	.004	3.5
43	MP1B	X	-15.597	1.5
44	MP1B	Z	0	1.5
45	MP1B	Mx	-.002	1.5
46	MP1B	X	-15.597	3.5
47	MP1B	Z	0	3.5
48	MP1B	Mx	-.002	3.5
49	MP1C	X	-15.129	1.5
50	MP1C	Z	0	1.5
51	MP1C	Mx	-.003	1.5
52	MP1C	X	-15.129	3.5
53	MP1C	Z	0	3.5
54	MP1C	Mx	-.003	3.5
55	MP3A	X	-11.816	2
56	MP3A	Z	0	2
57	MP3A	Mx	-.006	2
58	MP3B	X	-16.42	2
59	MP3B	Z	0	2
60	MP3B	Mx	.002	2
61	MP3C	X	-16.166	2
62	MP3C	Z	0	2
63	MP3C	Mx	.003	2
64	MP2A	X	-12.014	2
65	MP2A	Z	0	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 24 : Antenna Wi (270 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
66	MP2A	Mx	-.006	2
67	MP2B	X	-16.434	2
68	MP2B	Z	0	2
69	MP2B	Mx	.002	2
70	MP2C	X	-16.189	2
71	MP2C	Z	0	2
72	MP2C	Mx	.003	2
73	M101A	X	-28.81	1
74	M101A	Z	0	1
75	M101A	Mx	0	1

Member Point Loads (BLC 25 : Antenna Wi (300 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-27.397	1
2	MP2A	Z	-15.818	1
3	MP2A	Mx	.008	1
4	MP2A	X	-27.397	4
5	MP2A	Z	-15.818	4
6	MP2A	Mx	.008	4
7	MP2B	X	-34.33	1
8	MP2B	Z	-19.82	1
9	MP2B	Mx	.031	1
10	MP2B	X	-34.33	4
11	MP2B	Z	-19.82	4
12	MP2B	Mx	.031	4
13	MP2C	X	-29.914	1
14	MP2C	Z	-17.271	1
15	MP2C	Mx	-.028	1
16	MP2C	X	-29.914	4
17	MP2C	Z	-17.271	4
18	MP2C	Mx	-.028	4
19	MP2A	X	-27.397	1
20	MP2A	Z	-15.818	1
21	MP2A	Mx	.022	1
22	MP2A	X	-27.397	4
23	MP2A	Z	-15.818	4
24	MP2A	Mx	.022	4
25	MP2B	X	-34.33	1
26	MP2B	Z	-19.82	1
27	MP2B	Mx	-.02	1
28	MP2B	X	-34.33	4
29	MP2B	Z	-19.82	4
30	MP2B	Mx	-.02	4
31	MP2C	X	-29.914	1
32	MP2C	Z	-17.271	1
33	MP2C	Mx	.002	1
34	MP2C	X	-29.914	4
35	MP2C	Z	-17.271	4
36	MP2C	Mx	.002	4
37	MP1A	X	-6.885	1.5
38	MP1A	Z	-3.975	1.5
39	MP1A	Mx	.004	1.5
40	MP1A	X	-6.885	3.5
41	MP1A	Z	-3.975	3.5
42	MP1A	Mx	.004	3.5
43	MP1B	X	-13.508	1.5



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 25 : Antenna Wi (300 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
44	MP1B	Z	-7.799	1.5
45	MP1B	Mx	.002	1.5
46	MP1B	X	-13.508	3.5
47	MP1B	Z	-7.799	3.5
48	MP1B	Mx	.002	3.5
49	MP1C	X	-9.289	1.5
50	MP1C	Z	-5.363	1.5
51	MP1C	Mx	-.004	1.5
52	MP1C	X	-9.289	3.5
53	MP1C	Z	-5.363	3.5
54	MP1C	Mx	-.004	3.5
55	MP3A	X	-10.616	2
56	MP3A	Z	-6.129	2
57	MP3A	Mx	-.006	2
58	MP3B	X	-14.221	2
59	MP3B	Z	-8.21	2
60	MP3B	Mx	-.002	2
61	MP3C	X	-11.924	2
62	MP3C	Z	-6.885	2
63	MP3C	Mx	.005	2
64	MP2A	X	-10.772	2
65	MP2A	Z	-6.219	2
66	MP2A	Mx	-.006	2
67	MP2B	X	-14.232	2
68	MP2B	Z	-8.217	2
69	MP2B	Mx	-.002	2
70	MP2C	X	-12.028	2
71	MP2C	Z	-6.944	2
72	MP2C	Mx	.005	2
73	M101A	X	-28.201	1
74	M101A	Z	-16.282	1
75	M101A	Mx	0	1

Member Point Loads (BLC 26 : Antenna Wi (330 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-18.122	1
2	MP2A	Z	-31.389	1
3	MP2A	Mx	-.007	1
4	MP2A	X	-18.122	4
5	MP2A	Z	-31.389	4
6	MP2A	Mx	-.007	4
7	MP2B	X	-17.697	1
8	MP2B	Z	-30.651	1
9	MP2B	Mx	.029	1
10	MP2B	X	-17.697	4
11	MP2B	Z	-30.651	4
12	MP2B	Mx	.029	4
13	MP2C	X	-15.392	1
14	MP2C	Z	-26.66	1
15	MP2C	Mx	-.019	1
16	MP2C	X	-15.392	4
17	MP2C	Z	-26.66	4
18	MP2C	Mx	-.019	4
19	MP2A	X	-18.122	1
20	MP2A	Z	-31.389	1
21	MP2A	Mx	.03	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 26 : Antenna Wi (330 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
22	MP2A	X	-18.122	4
23	MP2A	Z	-31.389	4
24	MP2A	Mx	.03	4
25	MP2B	X	-17.697	1
26	MP2B	Z	-30.651	1
27	MP2B	Mx	-.004	1
28	MP2B	X	-17.697	4
29	MP2B	Z	-30.651	4
30	MP2B	Mx	-.004	4
31	MP2C	X	-15.392	1
32	MP2C	Z	-26.66	1
33	MP2C	Mx	-.012	1
34	MP2C	X	-15.392	4
35	MP2C	Z	-26.66	4
36	MP2C	Mx	-.012	4
37	MP1A	X	-6.177	1.5
38	MP1A	Z	-10.698	1.5
39	MP1A	Mx	.004	1.5
40	MP1A	X	-6.177	3.5
41	MP1A	Z	-10.698	3.5
42	MP1A	Mx	.004	3.5
43	MP1B	X	-5.77	1.5
44	MP1B	Z	-9.994	1.5
45	MP1B	Mx	.004	1.5
46	MP1B	X	-5.77	3.5
47	MP1B	Z	-9.994	3.5
48	MP1B	Mx	.004	3.5
49	MP1C	X	-3.568	1.5
50	MP1C	Z	-6.181	1.5
51	MP1C	Mx	-.004	1.5
52	MP1C	X	-3.568	3.5
53	MP1C	Z	-6.181	3.5
54	MP1C	Mx	-.004	3.5
55	MP3A	X	-7.327	2
56	MP3A	Z	-12.691	2
57	MP3A	Mx	-.005	2
58	MP3B	X	-7.106	2
59	MP3B	Z	-12.308	2
60	MP3B	Mx	-.005	2
61	MP3C	X	-5.908	2
62	MP3C	Z	-10.233	2
63	MP3C	Mx	.006	2
64	MP2A	X	-7.37	2
65	MP2A	Z	-12.764	2
66	MP2A	Mx	-.005	2
67	MP2B	X	-7.157	2
68	MP2B	Z	-12.396	2
69	MP2B	Mx	-.005	2
70	MP2C	X	-6.007	2
71	MP2C	Z	-10.404	2
72	MP2C	Mx	.006	2
73	M101A	X	-17.22	1
74	M101A	Z	-29.826	1
75	M101A	Mx	0	1

Member Point Loads (BLC 27 : Antenna Wm (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 27 : Antenna Wm (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	0	1
2	MP2A	Z	-6.325	1
3	MP2A	Mx	-.004	1
4	MP2A	X	0	4
5	MP2A	Z	-6.325	4
6	MP2A	Mx	-.004	4
7	MP2B	X	0	1
8	MP2B	Z	-4.877	1
9	MP2B	Mx	.003	1
10	MP2B	X	0	4
11	MP2B	Z	-4.877	4
12	MP2B	Mx	.003	4
13	MP2C	X	0	1
14	MP2C	Z	-4.957	1
15	MP2C	Mx	-.001	1
16	MP2C	X	0	4
17	MP2C	Z	-4.957	4
18	MP2C	Mx	-.001	4
19	MP2A	X	0	1
20	MP2A	Z	-6.325	1
21	MP2A	Mx	.005	1
22	MP2A	X	0	4
23	MP2A	Z	-6.325	4
24	MP2A	Mx	.005	4
25	MP2B	X	0	1
26	MP2B	Z	-4.877	1
27	MP2B	Mx	.002	1
28	MP2B	X	0	4
29	MP2B	Z	-4.877	4
30	MP2B	Mx	.002	4
31	MP2C	X	0	1
32	MP2C	Z	-4.957	1
33	MP2C	Mx	-.003	1
34	MP2C	X	0	4
35	MP2C	Z	-4.957	4
36	MP2C	Mx	-.003	4
37	MP1A	X	0	1.5
38	MP1A	Z	-5.012	1.5
39	MP1A	Mx	.000435	1.5
40	MP1A	X	0	3.5
41	MP1A	Z	-5.012	3.5
42	MP1A	Mx	.000435	3.5
43	MP1B	X	0	1.5
44	MP1B	Z	-2.177	1.5
45	MP1B	Mx	.001	1.5
46	MP1B	X	0	3.5
47	MP1B	Z	-2.177	3.5
48	MP1B	Mx	.001	3.5
49	MP1C	X	0	1.5
50	MP1C	Z	-2.334	1.5
51	MP1C	Mx	-.001	1.5
52	MP1C	X	0	3.5
53	MP1C	Z	-2.334	3.5
54	MP1C	Mx	-.001	3.5
55	MP3A	X	0	2
56	MP3A	Z	-4.135	2
57	MP3A	Mx	-.000359	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 27 : Antenna Wm (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
58	MP3B	X	0	2
59	MP3B	Z	-2.895	2
60	MP3B	Mx	-.001	2
61	MP3C	X	0	2
62	MP3C	Z	-2.963	2
63	MP3C	Mx	.001	2
64	MP2A	X	0	2
65	MP2A	Z	-4.991	2
66	MP2A	Mx	-.000433	2
67	MP2B	X	0	2
68	MP2B	Z	-3.543	2
69	MP2B	Mx	-.002	2
70	MP2C	X	0	2
71	MP2C	Z	-3.623	2
72	MP2C	Mx	.002	2
73	M101A	X	0	1
74	M101A	Z	-8.03	1
75	M101A	Mx	0	1

Member Point Loads (BLC 28 : Antenna Wm (30 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	3.093	1
2	MP2A	Z	-5.357	1
3	MP2A	Mx	-.005	1
4	MP2A	X	3.093	4
5	MP2A	Z	-5.357	4
6	MP2A	Mx	-.005	4
7	MP2B	X	2.439	1
8	MP2B	Z	-4.224	1
9	MP2B	Mx	.002	1
10	MP2B	X	2.439	4
11	MP2B	Z	-4.224	4
12	MP2B	Mx	.002	4
13	MP2C	X	2.855	1
14	MP2C	Z	-4.945	1
15	MP2C	Mx	.001	1
16	MP2C	X	2.855	4
17	MP2C	Z	-4.945	4
18	MP2C	Mx	.001	4
19	MP2A	X	3.093	1
20	MP2A	Z	-5.357	1
21	MP2A	Mx	.003	1
22	MP2A	X	3.093	4
23	MP2A	Z	-5.357	4
24	MP2A	Mx	.003	4
25	MP2B	X	2.439	1
26	MP2B	Z	-4.224	1
27	MP2B	Mx	.003	1
28	MP2B	X	2.439	4
29	MP2B	Z	-4.224	4
30	MP2B	Mx	.003	4
31	MP2C	X	2.855	1
32	MP2C	Z	-4.945	1
33	MP2C	Mx	-.005	1
34	MP2C	X	2.855	4
35	MP2C	Z	-4.945	4



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 28 : Antenna Wm (30 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
36	MP2C	Mx	-.005	4
37	MP1A	X	2.37	1.5
38	MP1A	Z	-4.104	1.5
39	MP1A	Mx	-.000811	1.5
40	MP1A	X	2.37	3.5
41	MP1A	Z	-4.104	3.5
42	MP1A	Mx	-.000811	3.5
43	MP1B	X	1.089	1.5
44	MP1B	Z	-1.885	1.5
45	MP1B	Mx	.001	1.5
46	MP1B	X	1.089	3.5
47	MP1B	Z	-1.885	3.5
48	MP1B	Mx	.001	3.5
49	MP1C	X	1.905	1.5
50	MP1C	Z	-3.299	1.5
51	MP1C	Mx	-.001	1.5
52	MP1C	X	1.905	3.5
53	MP1C	Z	-3.299	3.5
54	MP1C	Mx	-.001	3.5
55	MP3A	X	2.008	2
56	MP3A	Z	-3.478	2
57	MP3A	Mx	.000687	2
58	MP3B	X	1.447	2
59	MP3B	Z	-2.507	2
60	MP3B	Mx	-.001	2
61	MP3C	X	1.804	2
62	MP3C	Z	-3.125	2
63	MP3C	Mx	.001	2
64	MP2A	X	2.426	2
65	MP2A	Z	-4.202	2
66	MP2A	Mx	.00083	2
67	MP2B	X	1.772	2
68	MP2B	Z	-3.068	2
69	MP2B	Mx	-.002	2
70	MP2C	X	2.188	2
71	MP2C	Z	-3.79	2
72	MP2C	Mx	.001	2
73	M101A	X	3.503	1
74	M101A	Z	-6.068	1
75	M101A	Mx	0	1

Member Point Loads (BLC 29 : Antenna Wm (60 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	X	4.704	1
2	MP2A	Z	-2.716	1
3	MP2A	Mx	-.004	1
4	MP2A	X	4.704	4
5	MP2A	Z	-2.716	4
6	MP2A	Mx	-.004	4
7	MP2B	X	4.825	1
8	MP2B	Z	-2.786	1
9	MP2B	Mx	-.000656	1
10	MP2B	X	4.825	4
11	MP2B	Z	-2.786	4
12	MP2B	Mx	-.000656	4
13	MP2C	X	5.477	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 29 : Antenna Wm (60 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
14	MP2C	Z	-3.162	1
15	MP2C	Mx	.004	1
16	MP2C	X	5.477	4
17	MP2C	Z	-3.162	4
18	MP2C	Mx	.004	4
19	MP2A	X	4.704	1
20	MP2A	Z	-2.716	1
21	MP2A	Mx	.000247	1
22	MP2A	X	4.704	4
23	MP2A	Z	-2.716	4
24	MP2A	Mx	.000247	4
25	MP2B	X	4.825	1
26	MP2B	Z	-2.786	1
27	MP2B	Mx	.005	1
28	MP2B	X	4.825	4
29	MP2B	Z	-2.786	4
30	MP2B	Mx	.005	4
31	MP2C	X	5.477	1
32	MP2C	Z	-3.162	1
33	MP2C	Mx	-.005	1
34	MP2C	X	5.477	4
35	MP2C	Z	-3.162	4
36	MP2C	Mx	-.005	4
37	MP1A	X	2.827	1.5
38	MP1A	Z	-1.632	1.5
39	MP1A	Mx	-.001	1.5
40	MP1A	X	2.827	3.5
41	MP1A	Z	-1.632	3.5
42	MP1A	Mx	-.001	3.5
43	MP1B	X	3.063	1.5
44	MP1B	Z	-1.768	1.5
45	MP1B	Mx	.001	1.5
46	MP1B	X	3.063	3.5
47	MP1B	Z	-1.768	3.5
48	MP1B	Mx	.001	3.5
49	MP1C	X	4.34	1.5
50	MP1C	Z	-2.506	1.5
51	MP1C	Mx	-.000435	1.5
52	MP1C	X	4.34	3.5
53	MP1C	Z	-2.506	3.5
54	MP1C	Mx	-.000435	3.5
55	MP3A	X	2.919	2
56	MP3A	Z	-1.685	2
57	MP3A	Mx	.001	2
58	MP3B	X	3.022	2
59	MP3B	Z	-1.745	2
60	MP3B	Mx	-.001	2
61	MP3C	X	3.581	2
62	MP3C	Z	-2.068	2
63	MP3C	Mx	.000359	2
64	MP2A	X	3.549	2
65	MP2A	Z	-2.049	2
66	MP2A	Mx	.002	2
67	MP2B	X	3.67	2
68	MP2B	Z	-2.119	2
69	MP2B	Mx	-.001	2
70	MP2C	X	4.322	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 29 : Antenna Wm (60 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
71	MP2C	Z	-2.495	2
72	MP2C	Mx	.000433	2
73	M101A	X	5.624	1
74	M101A	Z	-3.247	1
75	M101A	Mx	0	1

Member Point Loads (BLC 30 : Antenna Wm (90 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	4.818	1
2	MP2A	Z	0	1
3	MP2A	Mx	-.003	1
4	MP2A	X	4.818	4
5	MP2A	Z	0	4
6	MP2A	Mx	-.003	4
7	MP2B	X	6.266	1
8	MP2B	Z	0	1
9	MP2B	Mx	-.003	1
10	MP2B	X	6.266	4
11	MP2B	Z	0	4
12	MP2B	Mx	-.003	4
13	MP2C	X	6.185	1
14	MP2C	Z	0	1
15	MP2C	Mx	.005	1
16	MP2C	X	6.185	4
17	MP2C	Z	0	4
18	MP2C	Mx	.005	4
19	MP2A	X	4.818	1
20	MP2A	Z	0	1
21	MP2A	Mx	-.002	1
22	MP2A	X	4.818	4
23	MP2A	Z	0	4
24	MP2A	Mx	-.002	4
25	MP2B	X	6.266	1
26	MP2B	Z	0	1
27	MP2B	Mx	.005	1
28	MP2B	X	6.266	4
29	MP2B	Z	0	4
30	MP2B	Mx	.005	4
31	MP2C	X	6.185	1
32	MP2C	Z	0	1
33	MP2C	Mx	-.003	1
34	MP2C	X	6.185	4
35	MP2C	Z	0	4
36	MP2C	Mx	-.003	4
37	MP1A	X	2.061	1.5
38	MP1A	Z	0	1.5
39	MP1A	Mx	-.001	1.5
40	MP1A	X	2.061	3.5
41	MP1A	Z	0	3.5
42	MP1A	Mx	-.001	3.5
43	MP1B	X	4.896	1.5
44	MP1B	Z	0	1.5
45	MP1B	Mx	.000634	1.5
46	MP1B	X	4.896	3.5
47	MP1B	Z	0	3.5
48	MP1B	Mx	.000634	3.5



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 30 : Antenna Wm (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
49	MP1C	X	4.739	1.5
50	MP1C	Z	0	1.5
51	MP1C	Mx	.00081	1.5
52	MP1C	X	4.739	3.5
53	MP1C	Z	0	3.5
54	MP1C	Mx	.00081	3.5
55	MP3A	X	2.844	2
56	MP3A	Z	0	2
57	MP3A	Mx	.001	2
58	MP3B	X	4.085	2
59	MP3B	Z	0	2
60	MP3B	Mx	-.000529	2
61	MP3C	X	4.016	2
62	MP3C	Z	0	2
63	MP3C	Mx	-.000687	2
64	MP2A	X	3.484	2
65	MP2A	Z	0	2
66	MP2A	Mx	.002	2
67	MP2B	X	4.932	2
68	MP2B	Z	0	2
69	MP2B	Mx	-.000638	2
70	MP2C	X	4.852	2
71	MP2C	Z	0	2
72	MP2C	Mx	-.00083	2
73	M101A	X	7.006	1
74	M101A	Z	0	1
75	M101A	Mx	0	1

Member Point Loads (BLC 31 : Antenna Wm (120 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	4.293	1
2	MP2A	Z	2.479	1
3	MP2A	Mx	-.001	1
4	MP2A	X	4.293	4
5	MP2A	Z	2.479	4
6	MP2A	Mx	-.001	4
7	MP2B	X	5.426	1
8	MP2B	Z	3.133	1
9	MP2B	Mx	-.005	1
10	MP2B	X	5.426	4
11	MP2B	Z	3.133	4
12	MP2B	Mx	-.005	4
13	MP2C	X	4.704	1
14	MP2C	Z	2.716	1
15	MP2C	Mx	.004	1
16	MP2C	X	4.704	4
17	MP2C	Z	2.716	4
18	MP2C	Mx	.004	4
19	MP2A	X	4.293	1
20	MP2A	Z	2.479	1
21	MP2A	Mx	-.003	1
22	MP2A	X	4.293	4
23	MP2A	Z	2.479	4
24	MP2A	Mx	-.003	4
25	MP2B	X	5.426	1
26	MP2B	Z	3.133	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 31 : Antenna Wm (120 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
27	MP2B	Mx	.003	1
28	MP2B	X	5.426	4
29	MP2B	Z	3.133	4
30	MP2B	Mx	.003	4
31	MP2C	X	4.704	1
32	MP2C	Z	2.716	1
33	MP2C	Mx	-.000247	1
34	MP2C	X	4.704	4
35	MP2C	Z	2.716	4
36	MP2C	Mx	-.000247	4
37	MP1A	X	2.021	1.5
38	MP1A	Z	1.167	1.5
39	MP1A	Mx	-.001	1.5
40	MP1A	X	2.021	3.5
41	MP1A	Z	1.167	3.5
42	MP1A	Mx	-.001	3.5
43	MP1B	X	4.24	1.5
44	MP1B	Z	2.448	1.5
45	MP1B	Mx	-.000634	1.5
46	MP1B	X	4.24	3.5
47	MP1B	Z	2.448	3.5
48	MP1B	Mx	-.000634	3.5
49	MP1C	X	2.827	1.5
50	MP1C	Z	1.632	1.5
51	MP1C	Mx	.001	1.5
52	MP1C	X	2.827	3.5
53	MP1C	Z	1.632	3.5
54	MP1C	Mx	.001	3.5
55	MP3A	X	2.566	2
56	MP3A	Z	1.482	2
57	MP3A	Mx	.001	2
58	MP3B	X	3.537	2
59	MP3B	Z	2.042	2
60	MP3B	Mx	.000528	2
61	MP3C	X	2.919	2
62	MP3C	Z	1.685	2
63	MP3C	Mx	-.001	2
64	MP2A	X	3.138	2
65	MP2A	Z	1.812	2
66	MP2A	Mx	.002	2
67	MP2B	X	4.271	2
68	MP2B	Z	2.466	2
69	MP2B	Mx	.000638	2
70	MP2C	X	3.549	2
71	MP2C	Z	2.049	2
72	MP2C	Mx	-.002	2
73	M101A	X	6.954	1
74	M101A	Z	4.015	1
75	M101A	Mx	0	1

Member Point Loads (BLC 32 : Antenna Wm (150 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	X	2.855	1
2	MP2A	Z	4.945	1
3	MP2A	Mx	.001	1
4	MP2A	X	2.855	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 32 : Antenna Wm (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
5	MP2A	Z	4.945	4
6	MP2A	Mx	.001	4
7	MP2B	X	2.786	1
8	MP2B	Z	4.825	1
9	MP2B	Mx	-.005	1
10	MP2B	X	2.786	4
11	MP2B	Z	4.825	4
12	MP2B	Mx	-.005	4
13	MP2C	X	2.409	1
14	MP2C	Z	4.172	1
15	MP2C	Mx	.003	1
16	MP2C	X	2.409	4
17	MP2C	Z	4.172	4
18	MP2C	Mx	.003	4
19	MP2A	X	2.855	1
20	MP2A	Z	4.945	1
21	MP2A	Mx	-.005	1
22	MP2A	X	2.855	4
23	MP2A	Z	4.945	4
24	MP2A	Mx	-.005	4
25	MP2B	X	2.786	1
26	MP2B	Z	4.825	1
27	MP2B	Mx	.000657	1
28	MP2B	X	2.786	4
29	MP2B	Z	4.825	4
30	MP2B	Mx	.000657	4
31	MP2C	X	2.409	1
32	MP2C	Z	4.172	1
33	MP2C	Mx	.002	1
34	MP2C	X	2.409	4
35	MP2C	Z	4.172	4
36	MP2C	Mx	.002	4
37	MP1A	X	1.905	1.5
38	MP1A	Z	3.299	1.5
39	MP1A	Mx	-.001	1.5
40	MP1A	X	1.905	3.5
41	MP1A	Z	3.299	3.5
42	MP1A	Mx	-.001	3.5
43	MP1B	X	1.768	1.5
44	MP1B	Z	3.063	1.5
45	MP1B	Mx	-.001	1.5
46	MP1B	X	1.768	3.5
47	MP1B	Z	3.063	3.5
48	MP1B	Mx	-.001	3.5
49	MP1C	X	1.031	1.5
50	MP1C	Z	1.785	1.5
51	MP1C	Mx	.001	1.5
52	MP1C	X	1.031	3.5
53	MP1C	Z	1.785	3.5
54	MP1C	Mx	.001	3.5
55	MP3A	X	1.804	2
56	MP3A	Z	3.125	2
57	MP3A	Mx	.001	2
58	MP3B	X	1.745	2
59	MP3B	Z	3.022	2
60	MP3B	Mx	.001	2
61	MP3C	X	1.422	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 32 : Antenna Wm (150 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
62	MP3C	Z	2.463	2
63	MP3C	Mx	-.001	2
64	MP2A	X	2.188	2
65	MP2A	Z	3.79	2
66	MP2A	Mx	.001	2
67	MP2B	X	2.119	2
68	MP2B	Z	3.67	2
69	MP2B	Mx	.001	2
70	MP2C	X	1.742	2
71	MP2C	Z	3.017	2
72	MP2C	Mx	-.002	2
73	M101A	X	4.271	1
74	M101A	Z	7.398	1
75	M101A	Mx	0	1

Member Point Loads (BLC 33 : Antenna Wm (180 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	X	0	1
2	MP2A	Z	6.325	1
3	MP2A	Mx	.004	1
4	MP2A	X	0	4
5	MP2A	Z	6.325	4
6	MP2A	Mx	.004	4
7	MP2B	X	0	1
8	MP2B	Z	4.877	1
9	MP2B	Mx	-.003	1
10	MP2B	X	0	4
11	MP2B	Z	4.877	4
12	MP2B	Mx	-.003	4
13	MP2C	X	0	1
14	MP2C	Z	4.957	1
15	MP2C	Mx	.001	1
16	MP2C	X	0	4
17	MP2C	Z	4.957	4
18	MP2C	Mx	.001	4
19	MP2A	X	0	1
20	MP2A	Z	6.325	1
21	MP2A	Mx	-.005	1
22	MP2A	X	0	4
23	MP2A	Z	6.325	4
24	MP2A	Mx	-.005	4
25	MP2B	X	0	1
26	MP2B	Z	4.877	1
27	MP2B	Mx	-.002	1
28	MP2B	X	0	4
29	MP2B	Z	4.877	4
30	MP2B	Mx	-.002	4
31	MP2C	X	0	1
32	MP2C	Z	4.957	1
33	MP2C	Mx	.003	1
34	MP2C	X	0	4
35	MP2C	Z	4.957	4
36	MP2C	Mx	.003	4
37	MP1A	X	0	1.5
38	MP1A	Z	5.012	1.5
39	MP1A	Mx	-.000435	1.5



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 33 : Antenna Wm (180 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
40	MP1A	X	0	3.5
41	MP1A	Z	5.012	3.5
42	MP1A	Mx	-.000435	3.5
43	MP1B	X	0	1.5
44	MP1B	Z	2.177	1.5
45	MP1B	Mx	-.001	1.5
46	MP1B	X	0	3.5
47	MP1B	Z	2.177	3.5
48	MP1B	Mx	-.001	3.5
49	MP1C	X	0	1.5
50	MP1C	Z	2.334	1.5
51	MP1C	Mx	.001	1.5
52	MP1C	X	0	3.5
53	MP1C	Z	2.334	3.5
54	MP1C	Mx	.001	3.5
55	MP3A	X	0	2
56	MP3A	Z	4.135	2
57	MP3A	Mx	.000359	2
58	MP3B	X	0	2
59	MP3B	Z	2.895	2
60	MP3B	Mx	.001	2
61	MP3C	X	0	2
62	MP3C	Z	2.963	2
63	MP3C	Mx	-.001	2
64	MP2A	X	0	2
65	MP2A	Z	4.991	2
66	MP2A	Mx	.000433	2
67	MP2B	X	0	2
68	MP2B	Z	3.543	2
69	MP2B	Mx	.002	2
70	MP2C	X	0	2
71	MP2C	Z	3.623	2
72	MP2C	Mx	-.002	2
73	M101A	X	0	1
74	M101A	Z	8.03	1
75	M101A	Mx	0	1

Member Point Loads (BLC 34 : Antenna Wm (210 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-3.093	1
2	MP2A	Z	5.357	1
3	MP2A	Mx	.005	1
4	MP2A	X	-3.093	4
5	MP2A	Z	5.357	4
6	MP2A	Mx	.005	4
7	MP2B	X	-2.439	1
8	MP2B	Z	4.224	1
9	MP2B	Mx	-.002	1
10	MP2B	X	-2.439	4
11	MP2B	Z	4.224	4
12	MP2B	Mx	-.002	4
13	MP2C	X	-2.855	1
14	MP2C	Z	4.945	1
15	MP2C	Mx	-.001	1
16	MP2C	X	-2.855	4
17	MP2C	Z	4.945	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 34 : Antenna Wm (210 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
18	MP2C	Mx	-.001	4
19	MP2A	X	-3.093	1
20	MP2A	Z	5.357	1
21	MP2A	Mx	-.003	1
22	MP2A	X	-3.093	4
23	MP2A	Z	5.357	4
24	MP2A	Mx	-.003	4
25	MP2B	X	-2.439	1
26	MP2B	Z	4.224	1
27	MP2B	Mx	-.003	1
28	MP2B	X	-2.439	4
29	MP2B	Z	4.224	4
30	MP2B	Mx	-.003	4
31	MP2C	X	-2.855	1
32	MP2C	Z	4.945	1
33	MP2C	Mx	.005	1
34	MP2C	X	-2.855	4
35	MP2C	Z	4.945	4
36	MP2C	Mx	.005	4
37	MP1A	X	-2.37	1.5
38	MP1A	Z	4.104	1.5
39	MP1A	Mx	.000811	1.5
40	MP1A	X	-2.37	3.5
41	MP1A	Z	4.104	3.5
42	MP1A	Mx	.000811	3.5
43	MP1B	X	-1.089	1.5
44	MP1B	Z	1.885	1.5
45	MP1B	Mx	-.001	1.5
46	MP1B	X	-1.089	3.5
47	MP1B	Z	1.885	3.5
48	MP1B	Mx	-.001	3.5
49	MP1C	X	-1.905	1.5
50	MP1C	Z	3.299	1.5
51	MP1C	Mx	.001	1.5
52	MP1C	X	-1.905	3.5
53	MP1C	Z	3.299	3.5
54	MP1C	Mx	.001	3.5
55	MP3A	X	-2.008	2
56	MP3A	Z	3.478	2
57	MP3A	Mx	-.000687	2
58	MP3B	X	-1.447	2
59	MP3B	Z	2.507	2
60	MP3B	Mx	.001	2
61	MP3C	X	-1.804	2
62	MP3C	Z	3.125	2
63	MP3C	Mx	-.001	2
64	MP2A	X	-2.426	2
65	MP2A	Z	4.202	2
66	MP2A	Mx	-.00083	2
67	MP2B	X	-1.772	2
68	MP2B	Z	3.068	2
69	MP2B	Mx	.002	2
70	MP2C	X	-2.188	2
71	MP2C	Z	3.79	2
72	MP2C	Mx	-.001	2
73	M101A	X	-3.503	1
74	M101A	Z	6.068	1



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 34 : Antenna Wm (210 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
75	M101A	Mx	0	1

Member Point Loads (BLC 35 : Antenna Wm (240 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-4.704	1
2	MP2A	Z	2.716	1
3	MP2A	Mx	.004	1
4	MP2A	X	-4.704	4
5	MP2A	Z	2.716	4
6	MP2A	Mx	.004	4
7	MP2B	X	-4.825	1
8	MP2B	Z	2.786	1
9	MP2B	Mx	.000656	1
10	MP2B	X	-4.825	4
11	MP2B	Z	2.786	4
12	MP2B	Mx	.000656	4
13	MP2C	X	-5.477	1
14	MP2C	Z	3.162	1
15	MP2C	Mx	-.004	1
16	MP2C	X	-5.477	4
17	MP2C	Z	3.162	4
18	MP2C	Mx	-.004	4
19	MP2A	X	-4.704	1
20	MP2A	Z	2.716	1
21	MP2A	Mx	-.000247	1
22	MP2A	X	-4.704	4
23	MP2A	Z	2.716	4
24	MP2A	Mx	-.000247	4
25	MP2B	X	-4.825	1
26	MP2B	Z	2.786	1
27	MP2B	Mx	-.005	1
28	MP2B	X	-4.825	4
29	MP2B	Z	2.786	4
30	MP2B	Mx	-.005	4
31	MP2C	X	-5.477	1
32	MP2C	Z	3.162	1
33	MP2C	Mx	.005	1
34	MP2C	X	-5.477	4
35	MP2C	Z	3.162	4
36	MP2C	Mx	.005	4
37	MP1A	X	-2.827	1.5
38	MP1A	Z	1.632	1.5
39	MP1A	Mx	.001	1.5
40	MP1A	X	-2.827	3.5
41	MP1A	Z	1.632	3.5
42	MP1A	Mx	.001	3.5
43	MP1B	X	-3.063	1.5
44	MP1B	Z	1.768	1.5
45	MP1B	Mx	-.001	1.5
46	MP1B	X	-3.063	3.5
47	MP1B	Z	1.768	3.5
48	MP1B	Mx	-.001	3.5
49	MP1C	X	-4.34	1.5
50	MP1C	Z	2.506	1.5
51	MP1C	Mx	.000435	1.5
52	MP1C	X	-4.34	3.5



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 35 : Antenna Wm (240 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
53	MP1C	Z	2.506	3.5
54	MP1C	Mx	.000435	3.5
55	MP3A	X	-2.919	2
56	MP3A	Z	1.685	2
57	MP3A	Mx	-.001	2
58	MP3B	X	-3.022	2
59	MP3B	Z	1.745	2
60	MP3B	Mx	.001	2
61	MP3C	X	-3.581	2
62	MP3C	Z	2.068	2
63	MP3C	Mx	-.000359	2
64	MP2A	X	-3.549	2
65	MP2A	Z	2.049	2
66	MP2A	Mx	-.002	2
67	MP2B	X	-3.67	2
68	MP2B	Z	2.119	2
69	MP2B	Mx	.001	2
70	MP2C	X	-4.322	2
71	MP2C	Z	2.495	2
72	MP2C	Mx	-.000433	2
73	M101A	X	-5.624	1
74	M101A	Z	3.247	1
75	M101A	Mx	0	1

Member Point Loads (BLC 36 : Antenna Wm (270 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	X	-4.818	1
2	MP2A	Z	0	1
3	MP2A	Mx	.003	1
4	MP2A	X	-4.818	4
5	MP2A	Z	0	4
6	MP2A	Mx	.003	4
7	MP2B	X	-6.266	1
8	MP2B	Z	0	1
9	MP2B	Mx	.003	1
10	MP2B	X	-6.266	4
11	MP2B	Z	0	4
12	MP2B	Mx	.003	4
13	MP2C	X	-6.185	1
14	MP2C	Z	0	1
15	MP2C	Mx	-.005	1
16	MP2C	X	-6.185	4
17	MP2C	Z	0	4
18	MP2C	Mx	-.005	4
19	MP2A	X	-4.818	1
20	MP2A	Z	0	1
21	MP2A	Mx	.002	1
22	MP2A	X	-4.818	4
23	MP2A	Z	0	4
24	MP2A	Mx	.002	4
25	MP2B	X	-6.266	1
26	MP2B	Z	0	1
27	MP2B	Mx	-.005	1
28	MP2B	X	-6.266	4
29	MP2B	Z	0	4
30	MP2B	Mx	-.005	4



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 36 : Antenna Wm (270 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
31	MP2C	X	-6.185	1
32	MP2C	Z	0	1
33	MP2C	Mx	.003	1
34	MP2C	X	-6.185	4
35	MP2C	Z	0	4
36	MP2C	Mx	.003	4
37	MP1A	X	-2.061	1.5
38	MP1A	Z	0	1.5
39	MP1A	Mx	.001	1.5
40	MP1A	X	-2.061	3.5
41	MP1A	Z	0	3.5
42	MP1A	Mx	.001	3.5
43	MP1B	X	-4.896	1.5
44	MP1B	Z	0	1.5
45	MP1B	Mx	-.000634	1.5
46	MP1B	X	-4.896	3.5
47	MP1B	Z	0	3.5
48	MP1B	Mx	-.000634	3.5
49	MP1C	X	-4.739	1.5
50	MP1C	Z	0	1.5
51	MP1C	Mx	-.00081	1.5
52	MP1C	X	-4.739	3.5
53	MP1C	Z	0	3.5
54	MP1C	Mx	-.00081	3.5
55	MP3A	X	-2.844	2
56	MP3A	Z	0	2
57	MP3A	Mx	-.001	2
58	MP3B	X	-4.085	2
59	MP3B	Z	0	2
60	MP3B	Mx	.000529	2
61	MP3C	X	-4.016	2
62	MP3C	Z	0	2
63	MP3C	Mx	.000687	2
64	MP2A	X	-3.484	2
65	MP2A	Z	0	2
66	MP2A	Mx	-.002	2
67	MP2B	X	-4.932	2
68	MP2B	Z	0	2
69	MP2B	Mx	.000638	2
70	MP2C	X	-4.852	2
71	MP2C	Z	0	2
72	MP2C	Mx	.00083	2
73	M101A	X	-7.006	1
74	M101A	Z	0	1
75	M101A	Mx	0	1

Member Point Loads (BLC 37 : Antenna Wm (300 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-4.293	1
2	MP2A	Z	-2.479	1
3	MP2A	Mx	.001	1
4	MP2A	X	-4.293	4
5	MP2A	Z	-2.479	4
6	MP2A	Mx	.001	4
7	MP2B	X	-5.426	1
8	MP2B	Z	-3.133	1



Company Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 37 : Antenna Wm (300 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft, %]
9	MP2B	Mx	.005	1
10	MP2B	X	-5.426	4
11	MP2B	Z	-3.133	4
12	MP2B	Mx	.005	4
13	MP2C	X	-4.704	1
14	MP2C	Z	-2.716	1
15	MP2C	Mx	-.004	1
16	MP2C	X	-4.704	4
17	MP2C	Z	-2.716	4
18	MP2C	Mx	-.004	4
19	MP2A	X	-4.293	1
20	MP2A	Z	-2.479	1
21	MP2A	Mx	.003	1
22	MP2A	X	-4.293	4
23	MP2A	Z	-2.479	4
24	MP2A	Mx	.003	4
25	MP2B	X	-5.426	1
26	MP2B	Z	-3.133	1
27	MP2B	Mx	-.003	1
28	MP2B	X	-5.426	4
29	MP2B	Z	-3.133	4
30	MP2B	Mx	-.003	4
31	MP2C	X	-4.704	1
32	MP2C	Z	-2.716	1
33	MP2C	Mx	.000247	1
34	MP2C	X	-4.704	4
35	MP2C	Z	-2.716	4
36	MP2C	Mx	.000247	4
37	MP1A	X	-2.021	1.5
38	MP1A	Z	-1.167	1.5
39	MP1A	Mx	.001	1.5
40	MP1A	X	-2.021	3.5
41	MP1A	Z	-1.167	3.5
42	MP1A	Mx	.001	3.5
43	MP1B	X	-4.24	1.5
44	MP1B	Z	-2.448	1.5
45	MP1B	Mx	.000634	1.5
46	MP1B	X	-4.24	3.5
47	MP1B	Z	-2.448	3.5
48	MP1B	Mx	.000634	3.5
49	MP1C	X	-2.827	1.5
50	MP1C	Z	-1.632	1.5
51	MP1C	Mx	-.001	1.5
52	MP1C	X	-2.827	3.5
53	MP1C	Z	-1.632	3.5
54	MP1C	Mx	-.001	3.5
55	MP3A	X	-2.566	2
56	MP3A	Z	-1.482	2
57	MP3A	Mx	-.001	2
58	MP3B	X	-3.537	2
59	MP3B	Z	-2.042	2
60	MP3B	Mx	-.000528	2
61	MP3C	X	-2.919	2
62	MP3C	Z	-1.685	2
63	MP3C	Mx	.001	2
64	MP2A	X	-3.138	2
65	MP2A	Z	-1.812	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 37 : Antenna Wm (300 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
66	MP2A	Mx	-.002	2
67	MP2B	X	-4.271	2
68	MP2B	Z	-2.466	2
69	MP2B	Mx	-.000638	2
70	MP2C	X	-3.549	2
71	MP2C	Z	-2.049	2
72	MP2C	Mx	.002	2
73	M101A	X	-6.954	1
74	M101A	Z	-4.015	1
75	M101A	Mx	0	1

Member Point Loads (BLC 38 : Antenna Wm (330 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	-2.855	1
2	MP2A	Z	-4.945	1
3	MP2A	Mx	-.001	1
4	MP2A	X	-2.855	4
5	MP2A	Z	-4.945	4
6	MP2A	Mx	-.001	4
7	MP2B	X	-2.786	1
8	MP2B	Z	-4.825	1
9	MP2B	Mx	.005	1
10	MP2B	X	-2.786	4
11	MP2B	Z	-4.825	4
12	MP2B	Mx	.005	4
13	MP2C	X	-2.409	1
14	MP2C	Z	-4.172	1
15	MP2C	Mx	-.003	1
16	MP2C	X	-2.409	4
17	MP2C	Z	-4.172	4
18	MP2C	Mx	-.003	4
19	MP2A	X	-2.855	1
20	MP2A	Z	-4.945	1
21	MP2A	Mx	.005	1
22	MP2A	X	-2.855	4
23	MP2A	Z	-4.945	4
24	MP2A	Mx	.005	4
25	MP2B	X	-2.786	1
26	MP2B	Z	-4.825	1
27	MP2B	Mx	-.000657	1
28	MP2B	X	-2.786	4
29	MP2B	Z	-4.825	4
30	MP2B	Mx	-.000657	4
31	MP2C	X	-2.409	1
32	MP2C	Z	-4.172	1
33	MP2C	Mx	-.002	1
34	MP2C	X	-2.409	4
35	MP2C	Z	-4.172	4
36	MP2C	Mx	-.002	4
37	MP1A	X	-1.905	1.5
38	MP1A	Z	-3.299	1.5
39	MP1A	Mx	.001	1.5
40	MP1A	X	-1.905	3.5
41	MP1A	Z	-3.299	3.5
42	MP1A	Mx	.001	3.5
43	MP1B	X	-1.768	1.5



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 38 : Antenna Wm (330 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
44	MP1B	Z	-3.063	1.5
45	MP1B	Mx	.001	1.5
46	MP1B	X	-1.768	3.5
47	MP1B	Z	-3.063	3.5
48	MP1B	Mx	.001	3.5
49	MP1C	X	-1.031	1.5
50	MP1C	Z	-1.785	1.5
51	MP1C	Mx	-.001	1.5
52	MP1C	X	-1.031	3.5
53	MP1C	Z	-1.785	3.5
54	MP1C	Mx	-.001	3.5
55	MP3A	X	-1.804	2
56	MP3A	Z	-3.125	2
57	MP3A	Mx	-.001	2
58	MP3B	X	-1.745	2
59	MP3B	Z	-3.022	2
60	MP3B	Mx	-.001	2
61	MP3C	X	-1.422	2
62	MP3C	Z	-2.463	2
63	MP3C	Mx	.001	2
64	MP2A	X	-2.188	2
65	MP2A	Z	-3.79	2
66	MP2A	Mx	-.001	2
67	MP2B	X	-2.119	2
68	MP2B	Z	-3.67	2
69	MP2B	Mx	-.001	2
70	MP2C	X	-1.742	2
71	MP2C	Z	-3.017	2
72	MP2C	Mx	.002	2
73	M101A	X	-4.271	1
74	M101A	Z	-7.398	1
75	M101A	Mx	0	1

Member Point Loads (BLC 77 : Lm1)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	M172	Y	-500	%97

Member Point Loads (BLC 78 : Lm2)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	M172	Y	-500	%65

Member Point Loads (BLC 79 : Lv1)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	M172	Y	-250	0

Member Point Loads (BLC 80 : Lv2)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	M172	Y	-250	%50

Member Point Loads (BLC 81 : Antenna Ev)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	Y	-1.647	1
2	MP2A	My	-.001	1
3	MP2A	Mz	.000939	1



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Point Loads (BLC 81 : Antenna Ev) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft,%]
4	MP2A	Y	-1.647	4
5	MP2A	My	-.001	4
6	MP2A	Mz	.000939	4
7	MP2B	Y	-1.647	1
8	MP2B	My	-.000848	1
9	MP2B	Mz	-.001	1
10	MP2B	Y	-1.647	4
11	MP2B	My	-.000848	4
12	MP2B	Mz	-.001	4
13	MP2C	Y	-1.647	1
14	MP2C	My	.001	1
15	MP2C	Mz	.000398	1
16	MP2C	Y	-1.647	4
17	MP2C	My	.001	4
18	MP2C	Mz	.000398	4
19	MP2A	Y	-1.647	1
20	MP2A	My	-.00062	1
21	MP2A	Mz	-.001	1
22	MP2A	Y	-1.647	4
23	MP2A	My	-.00062	4
24	MP2A	Mz	-.001	4
25	MP2B	Y	-1.647	1
26	MP2B	My	.001	1
27	MP2B	Mz	-.000511	1
28	MP2B	Y	-1.647	4
29	MP2B	My	.001	4
30	MP2B	Mz	-.000511	4
31	MP2C	Y	-1.647	1
32	MP2C	My	-.00075	1
33	MP2C	Mz	.001	1
34	MP2C	Y	-1.647	4
35	MP2C	My	-.00075	4
36	MP2C	Mz	.001	4
37	MP1A	Y	-1.21	1.5
38	MP1A	My	-.000596	1.5
39	MP1A	Mz	-.000105	1.5
40	MP1A	Y	-1.21	3.5
41	MP1A	My	-.000596	3.5
42	MP1A	Mz	-.000105	3.5
43	MP1B	Y	-1.21	1.5
44	MP1B	My	.000157	1.5
45	MP1B	Mz	-.000584	1.5
46	MP1B	Y	-1.21	3.5
47	MP1B	My	.000157	3.5
48	MP1B	Mz	-.000584	3.5
49	MP1C	Y	-1.21	1.5
50	MP1C	My	.000207	1.5
51	MP1C	Mz	.000569	1.5
52	MP1C	Y	-1.21	3.5
53	MP1C	My	.000207	3.5
54	MP1C	Mz	.000569	3.5
55	MP3A	Y	-3.155	2
56	MP3A	My	.002	2
57	MP3A	Mz	.000274	2
58	MP3B	Y	-3.155	2
59	MP3B	My	-.000408	2
60	MP3B	Mz	.002	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 81 : Antenna Ev) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
61	MP3C	Y	-3.155	2
62	MP3C	My	-.00054	2
63	MP3C	Mz	-.001	2
64	MP2A	Y	-3.341	2
65	MP2A	Mv	.002	2
66	MP2A	Mz	.00029	2
67	MP2B	Y	-3.341	2
68	MP2B	My	-.000432	2
69	MP2B	Mz	.002	2
70	MP2C	Y	-3.341	2
71	MP2C	Mv	-.000571	2
72	MP2C	Mz	-.002	2
73	M101A	Y	-1.352	1
74	M101A	Mv	0	1
75	M101A	Mz	0	1

Member Point Loads (BLC 82 : Antenna Eh (0 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft. %]
1	MP2A	Z	-4.118	1
2	MP2A	Mx	-.002	1
3	MP2A	Z	-4.118	4
4	MP2A	Mx	-.002	4
5	MP2B	Z	-4.118	1
6	MP2B	Mx	.003	1
7	MP2B	Z	-4.118	4
8	MP2B	Mx	.003	4
9	MP2C	Z	-4.118	1
10	MP2C	Mx	-.000996	1
11	MP2C	Z	-4.118	4
12	MP2C	Mx	-.000996	4
13	MP2A	Z	-4.118	1
14	MP2A	Mx	.003	1
15	MP2A	Z	-4.118	4
16	MP2A	Mx	.003	4
17	MP2B	Z	-4.118	1
18	MP2B	Mx	.001	1
19	MP2B	Z	-4.118	4
20	MP2B	Mx	.001	4
21	MP2C	Z	-4.118	1
22	MP2C	Mx	-.003	1
23	MP2C	Z	-4.118	4
24	MP2C	Mx	-.003	4
25	MP1A	Z	-3.025	1.5
26	MP1A	Mx	.000263	1.5
27	MP1A	Z	-3.025	3.5
28	MP1A	Mx	.000263	3.5
29	MP1B	Z	-3.025	1.5
30	MP1B	Mx	.001	1.5
31	MP1B	Z	-3.025	3.5
32	MP1B	Mx	.001	3.5
33	MP1C	Z	-3.025	1.5
34	MP1C	Mx	-.001	1.5
35	MP1C	Z	-3.025	3.5
36	MP1C	Mx	-.001	3.5
37	MP3A	Z	-7.888	2
38	MP3A	Mx	-.000685	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 82 : Antenna Eh (0 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
39	MP3B	Z	-7.888	2
40	MP3B	Mx	-.004	2
41	MP3C	Z	-7.888	2
42	MP3C	Mx	.004	2
43	MP2A	Z	-8.353	2
44	MP2A	Mx	-.000725	2
45	MP2B	Z	-8.353	2
46	MP2B	Mx	-.004	2
47	MP2C	Z	-8.353	2
48	MP2C	Mx	.004	2
49	M101A	Z	-3.379	1
50	M101A	Mx	0	1

Member Point Loads (BLC 83 : Antenna Eh (90 Deg))

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
1	MP2A	X	4.118	1
2	MP2A	Mx	-.003	1
3	MP2A	X	4.118	4
4	MP2A	Mx	-.003	4
5	MP2B	X	4.118	1
6	MP2B	Mx	-.002	1
7	MP2B	X	4.118	4
8	MP2B	Mx	-.002	4
9	MP2C	X	4.118	1
10	MP2C	Mx	.003	1
11	MP2C	X	4.118	4
12	MP2C	Mx	.003	4
13	MP2A	X	4.118	1
14	MP2A	Mx	-.002	1
15	MP2A	X	4.118	4
16	MP2A	Mx	-.002	4
17	MP2B	X	4.118	1
18	MP2B	Mx	.003	1
19	MP2B	X	4.118	4
20	MP2B	Mx	.003	4
21	MP2C	X	4.118	1
22	MP2C	Mx	-.002	1
23	MP2C	X	4.118	4
24	MP2C	Mx	-.002	4
25	MP1A	X	3.025	1.5
26	MP1A	Mx	-.001	1.5
27	MP1A	X	3.025	3.5
28	MP1A	Mx	-.001	3.5
29	MP1B	X	3.025	1.5
30	MP1B	Mx	.000392	1.5
31	MP1B	X	3.025	3.5
32	MP1B	Mx	.000392	3.5
33	MP1C	X	3.025	1.5
34	MP1C	Mx	.000517	1.5
35	MP1C	X	3.025	3.5
36	MP1C	Mx	.000517	3.5
37	MP3A	X	7.888	2
38	MP3A	Mx	.004	2
39	MP3B	X	7.888	2
40	MP3B	Mx	-.001	2
41	MP3C	X	7.888	2



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Point Loads (BLC 83 : Antenna Eh (90 Deg)) (Continued)

	Member Label	Direction	Magnitude[lb.k-ft]	Location[ft.%]
42	MP3C	Mx	-0.001	2
43	MP2A	X	8.353	2
44	MP2A	Mx	.004	2
45	MP2B	X	8.353	2
46	MP2B	Mx	-0.001	2
47	MP2C	X	8.353	2
48	MP2C	Mx	-0.001	2
49	M101A	X	3.379	1
50	M101A	Mx	0	1

Member Distributed Loads (BLC 40 : Structure Di)

	Member Label	Direction	Start Magnitude[lb/ft.]	End Magnitude[lb/ft.]	Start Location[ft.%]	End Location[ft.%]
1	M100	Y	-9.656	-9.656	0	%100
2	M101	Y	-7.653	-7.653	0	%100
3	M102	Y	-7.653	-7.653	0	%100
4	M103	Y	-10.159	-10.159	0	%100
5	M106	Y	-5.65	-5.65	0	%100
6	M107	Y	-5.65	-5.65	0	%100
7	M111	Y	-10.159	-10.159	0	%100
8	M112	Y	-10.159	-10.159	0	%100
9	M114	Y	-10.159	-10.159	0	%100
10	M116	Y	-10.159	-10.159	0	%100
11	M117	Y	-10.159	-10.159	0	%100
12	M119	Y	-10.159	-10.159	0	%100
13	M124	Y	-9.656	-9.656	0	%100
14	M125	Y	-7.653	-7.653	0	%100
15	M126	Y	-7.653	-7.653	0	%100
16	M127	Y	-10.159	-10.159	0	%100
17	M130	Y	-5.65	-5.65	0	%100
18	M131	Y	-5.65	-5.65	0	%100
19	M135	Y	-10.159	-10.159	0	%100
20	M136	Y	-10.159	-10.159	0	%100
21	M138	Y	-10.159	-10.159	0	%100
22	M140	Y	-10.159	-10.159	0	%100
23	M141	Y	-10.159	-10.159	0	%100
24	M143	Y	-10.159	-10.159	0	%100
25	M148	Y	-9.656	-9.656	0	%100
26	M149	Y	-7.653	-7.653	0	%100
27	M150	Y	-7.653	-7.653	0	%100
28	M151	Y	-10.159	-10.159	0	%100
29	M154	Y	-5.65	-5.65	0	%100
30	M155	Y	-5.65	-5.65	0	%100
31	M159	Y	-10.159	-10.159	0	%100
32	M160	Y	-10.159	-10.159	0	%100
33	M162	Y	-10.159	-10.159	0	%100
34	M164	Y	-10.159	-10.159	0	%100
35	M165	Y	-10.159	-10.159	0	%100
36	M167	Y	-10.159	-10.159	0	%100
37	M172	Y	-6.601	-6.601	0	%100
38	MP1A	Y	-5.007	-5.007	0	%100
39	MP2A	Y	-5.716	-5.716	0	%100
40	MP3A	Y	-5.007	-5.007	0	%100
41	MP4A	Y	-5.007	-5.007	0	%100
42	M181	Y	-6.601	-6.601	0	%100
43	MP1C	Y	-5.007	-5.007	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 40 : Structure Di) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
44	MP2C	Y	-5.716	-5.716	0	%100
45	MP3C	Y	-5.007	-5.007	0	%100
46	MP4C	Y	-5.007	-5.007	0	%100
47	M190	Y	-6.601	-6.601	0	%100
48	MP1B	Y	-5.007	-5.007	0	%100
49	MP2B	Y	-5.716	-5.716	0	%100
50	MP3B	Y	-5.007	-5.007	0	%100
51	MP4B	Y	-5.007	-5.007	0	%100
52	M101A	Y	-5.007	-5.007	0	%100
53	M102A	Y	-7.653	-7.653	0	%100
54	M116A	Y	-5.716	-5.716	0	%100
55	M120A	Y	-5.716	-5.716	0	%100
56	M125A	Y	-5.716	-5.716	0	%100
57	M132A	Y	-10.674	-10.674	0	%100
58	M133A	Y	-10.674	-10.674	0	%100
59	M134A	Y	-10.674	-10.674	0	%100
60	M125B	Y	-7.653	-7.653	0	%100
61	M130A	Y	-7.653	-7.653	0	%100

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
1	M100	X	0	0	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	-18.764	-18.764	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	-18.764	-18.764	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	-30.36	-30.36	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	-4.215	-4.215	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	-4.215	-4.215	0	%100
13	M111	X	0	0	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	-7.731	-7.731	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	-8.143	-8.143	0	%100
19	M116	X	0	0	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	-7.731	-7.731	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	-8.143	-8.143	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	-14.715	-14.715	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	-4.691	-4.691	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	-4.691	-4.691	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	-7.59	-7.59	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	-4.215	-4.215	0	%100
35	M131	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft...	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
36	M131	Z	-16.859	-16.859	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	-22.77	-22.77	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	-7.731	-7.731	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	-8.143	-8.143	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	-22.77	-22.77	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	-30.923	-30.923	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	-32.57	-32.57	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	-14.715	-14.715	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	-4.691	-4.691	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	-4.691	-4.691	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	-7.59	-7.59	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	-16.859	-16.859	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	-4.215	-4.215	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	-22.77	-22.77	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	-30.923	-30.923	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	-32.57	-32.57	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	-22.77	-22.77	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	-7.731	-7.731	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	-8.143	-8.143	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	-15.575	-15.575	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	-12.018	-12.018	0	%100
77	MP2A	X	0	0	0	%100
78	MP2A	Z	-14.548	-14.548	0	%100
79	MP3A	X	0	0	0	%100
80	MP3A	Z	-12.018	-12.018	0	%100
81	MP4A	X	0	0	0	%100
82	MP4A	Z	-12.018	-12.018	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	-3.894	-3.894	0	%100
85	MP1C	X	0	0	0	%100
86	MP1C	Z	-12.018	-12.018	0	%100
87	MP2C	X	0	0	0	%100
88	MP2C	Z	-14.548	-14.548	0	%100
89	MP3C	X	0	0	0	%100
90	MP3C	Z	-12.018	-12.018	0	%100
91	MP4C	X	0	0	0	%100
92	MP4C	Z	-12.018	-12.018	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 41 : Structure Wo (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
93	M190	X	0	0	0	%100
94	M190	Z	-3.894	-3.894	0	%100
95	MP1B	X	0	0	0	%100
96	MP1B	Z	-12.018	-12.018	0	%100
97	MP2B	X	0	0	0	%100
98	MP2B	Z	-14.548	-14.548	0	%100
99	MP3B	X	0	0	0	%100
100	MP3B	Z	-12.018	-12.018	0	%100
101	MP4B	X	0	0	0	%100
102	MP4B	Z	-12.018	-12.018	0	%100
103	M101A	X	0	0	0	%100
104	M101A	Z	-9.827	-9.827	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	-18.466	-18.466	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	-14.548	-14.548	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	-3.637	-3.637	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	-3.637	-3.637	0	%100
113	M132A	X	0	0	0	%100
114	M132A	Z	-19.259	-19.259	0	%100
115	M133A	X	0	0	0	%100
116	M133A	Z	-21.251	-21.251	0	%100
117	M134A	X	0	0	0	%100
118	M134A	Z	-21.251	-21.251	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	-4.616	-4.616	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	-4.616	-4.616	0	%100

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	2.452	2.452	0	%100
2	M100	Z	-4.248	-4.248	0	%100
3	M101	X	7.037	7.037	0	%100
4	M101	Z	-12.188	-12.188	0	%100
5	M102	X	7.037	7.037	0	%100
6	M102	Z	-12.188	-12.188	0	%100
7	M103	X	11.385	11.385	0	%100
8	M103	Z	-19.72	-19.72	0	%100
9	M106	X	6.322	6.322	0	%100
10	M106	Z	-10.95	-10.95	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	3.795	3.795	0	%100
14	M111	Z	-6.573	-6.573	0	%100
15	M112	X	11.596	11.596	0	%100
16	M112	Z	-20.085	-20.085	0	%100
17	M114	X	12.214	12.214	0	%100
18	M114	Z	-21.155	-21.155	0	%100
19	M116	X	3.795	3.795	0	%100
20	M116	Z	-6.573	-6.573	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
24	M119	Z	0	0	0	%100
25	M124	X	2.452	2.452	0	%100
26	M124	Z	-4.248	-4.248	0	%100
27	M125	X	7.037	7.037	0	%100
28	M125	Z	-12.188	-12.188	0	%100
29	M126	X	7.037	7.037	0	%100
30	M126	Z	-12.188	-12.188	0	%100
31	M127	X	11.385	11.385	0	%100
32	M127	Z	-19.72	-19.72	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	6.322	6.322	0	%100
36	M131	Z	-10.95	-10.95	0	%100
37	M135	X	3.795	3.795	0	%100
38	M135	Z	-6.573	-6.573	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	3.795	3.795	0	%100
44	M140	Z	-6.573	-6.573	0	%100
45	M141	X	11.596	11.596	0	%100
46	M141	Z	-20.085	-20.085	0	%100
47	M143	X	12.214	12.214	0	%100
48	M143	Z	-21.155	-21.155	0	%100
49	M148	X	9.81	9.81	0	%100
50	M148	Z	-16.991	-16.991	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	6.322	6.322	0	%100
58	M154	Z	-10.95	-10.95	0	%100
59	M155	X	6.322	6.322	0	%100
60	M155	Z	-10.95	-10.95	0	%100
61	M159	X	15.18	15.18	0	%100
62	M159	Z	-26.293	-26.293	0	%100
63	M160	X	11.596	11.596	0	%100
64	M160	Z	-20.085	-20.085	0	%100
65	M162	X	12.214	12.214	0	%100
66	M162	Z	-21.155	-21.155	0	%100
67	M164	X	15.18	15.18	0	%100
68	M164	Z	-26.293	-26.293	0	%100
69	M165	X	11.596	11.596	0	%100
70	M165	Z	-20.085	-20.085	0	%100
71	M167	X	12.214	12.214	0	%100
72	M167	Z	-21.155	-21.155	0	%100
73	M172	X	5.841	5.841	0	%100
74	M172	Z	-10.116	-10.116	0	%100
75	MP1A	X	6.009	6.009	0	%100
76	MP1A	Z	-10.408	-10.408	0	%100
77	MP2A	X	7.274	7.274	0	%100
78	MP2A	Z	-12.599	-12.599	0	%100
79	MP3A	X	6.009	6.009	0	%100
80	MP3A	Z	-10.408	-10.408	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 42 : Structure Wo (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
81	MP4A	X	6.009	6.009	0	%100
82	MP4A	Z	-10.408	-10.408	0	%100
83	M181	X	5.841	5.841	0	%100
84	M181	Z	-10.116	-10.116	0	%100
85	MP1C	X	6.009	6.009	0	%100
86	MP1C	Z	-10.408	-10.408	0	%100
87	MP2C	X	7.274	7.274	0	%100
88	MP2C	Z	-12.599	-12.599	0	%100
89	MP3C	X	6.009	6.009	0	%100
90	MP3C	Z	-10.408	-10.408	0	%100
91	MP4C	X	6.009	6.009	0	%100
92	MP4C	Z	-10.408	-10.408	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	6.009	6.009	0	%100
96	MP1B	Z	-10.408	-10.408	0	%100
97	MP2B	X	7.274	7.274	0	%100
98	MP2B	Z	-12.599	-12.599	0	%100
99	MP3B	X	6.009	6.009	0	%100
100	MP3B	Z	-10.408	-10.408	0	%100
101	MP4B	X	6.009	6.009	0	%100
102	MP4B	Z	-10.408	-10.408	0	%100
103	M101A	X	4.914	4.914	0	%100
104	M101A	Z	-8.511	-8.511	0	%100
105	M102A	X	6.925	6.925	0	%100
106	M102A	Z	-11.994	-11.994	0	%100
107	M116A	X	5.455	5.455	0	%100
108	M116A	Z	-9.449	-9.449	0	%100
109	M120A	X	5.455	5.455	0	%100
110	M120A	Z	-9.449	-9.449	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	9.961	9.961	0	%100
114	M132A	Z	-17.254	-17.254	0	%100
115	M133A	X	9.961	9.961	0	%100
116	M133A	Z	-17.254	-17.254	0	%100
117	M134A	X	10.957	10.957	0	%100
118	M134A	Z	-18.979	-18.979	0	%100
119	M125B	X	6.925	6.925	0	%100
120	M125B	Z	-11.994	-11.994	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	12.743	12.743	0	%100
2	M100	Z	-7.357	-7.357	0	%100
3	M101	X	4.063	4.063	0	%100
4	M101	Z	-2.346	-2.346	0	%100
5	M102	X	4.063	4.063	0	%100
6	M102	Z	-2.346	-2.346	0	%100
7	M103	X	6.573	6.573	0	%100
8	M103	Z	-3.795	-3.795	0	%100
9	M106	X	14.6	14.6	0	%100
10	M106	Z	-8.429	-8.429	0	%100
11	M107	X	3.65	3.65	0	%100



Member Distributed Loads (BLC 43 : Structure Wo (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
12	M107	Z	-2.107	-2.107	0	%100
13	M111	X	19.72	19.72	0	%100
14	M111	Z	-11.385	-11.385	0	%100
15	M112	X	26.78	26.78	0	%100
16	M112	Z	-15.461	-15.461	0	%100
17	M114	X	28.206	28.206	0	%100
18	M114	Z	-16.285	-16.285	0	%100
19	M116	X	19.72	19.72	0	%100
20	M116	Z	-11.385	-11.385	0	%100
21	M117	X	6.695	6.695	0	%100
22	M117	Z	-3.865	-3.865	0	%100
23	M119	X	7.052	7.052	0	%100
24	M119	Z	-4.071	-4.071	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	16.25	16.25	0	%100
28	M125	Z	-9.382	-9.382	0	%100
29	M126	X	16.25	16.25	0	%100
30	M126	Z	-9.382	-9.382	0	%100
31	M127	X	26.293	26.293	0	%100
32	M127	Z	-15.18	-15.18	0	%100
33	M130	X	3.65	3.65	0	%100
34	M130	Z	-2.107	-2.107	0	%100
35	M131	X	3.65	3.65	0	%100
36	M131	Z	-2.107	-2.107	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	6.695	6.695	0	%100
40	M136	Z	-3.865	-3.865	0	%100
41	M138	X	7.052	7.052	0	%100
42	M138	Z	-4.071	-4.071	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	6.695	6.695	0	%100
46	M141	Z	-3.865	-3.865	0	%100
47	M143	X	7.052	7.052	0	%100
48	M143	Z	-4.071	-4.071	0	%100
49	M148	X	12.743	12.743	0	%100
50	M148	Z	-7.357	-7.357	0	%100
51	M149	X	4.063	4.063	0	%100
52	M149	Z	-2.346	-2.346	0	%100
53	M150	X	4.063	4.063	0	%100
54	M150	Z	-2.346	-2.346	0	%100
55	M151	X	6.573	6.573	0	%100
56	M151	Z	-3.795	-3.795	0	%100
57	M154	X	3.65	3.65	0	%100
58	M154	Z	-2.107	-2.107	0	%100
59	M155	X	14.6	14.6	0	%100
60	M155	Z	-8.429	-8.429	0	%100
61	M159	X	19.72	19.72	0	%100
62	M159	Z	-11.385	-11.385	0	%100
63	M160	X	6.695	6.695	0	%100
64	M160	Z	-3.865	-3.865	0	%100
65	M162	X	7.052	7.052	0	%100
66	M162	Z	-4.071	-4.071	0	%100
67	M164	X	19.72	19.72	0	%100
68	M164	Z	-11.385	-11.385	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 43 : Structure Wo (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
69	M165	X	26.78	26.78	0	%100
70	M165	Z	-15.461	-15.461	0	%100
71	M167	X	28.206	28.206	0	%100
72	M167	Z	-16.285	-16.285	0	%100
73	M172	X	3.372	3.372	0	%100
74	M172	Z	-1.947	-1.947	0	%100
75	MP1A	X	10.408	10.408	0	%100
76	MP1A	Z	-6.009	-6.009	0	%100
77	MP2A	X	12.599	12.599	0	%100
78	MP2A	Z	-7.274	-7.274	0	%100
79	MP3A	X	10.408	10.408	0	%100
80	MP3A	Z	-6.009	-6.009	0	%100
81	MP4A	X	10.408	10.408	0	%100
82	MP4A	Z	-6.009	-6.009	0	%100
83	M181	X	13.488	13.488	0	%100
84	M181	Z	-7.787	-7.787	0	%100
85	MP1C	X	10.408	10.408	0	%100
86	MP1C	Z	-6.009	-6.009	0	%100
87	MP2C	X	12.599	12.599	0	%100
88	MP2C	Z	-7.274	-7.274	0	%100
89	MP3C	X	10.408	10.408	0	%100
90	MP3C	Z	-6.009	-6.009	0	%100
91	MP4C	X	10.408	10.408	0	%100
92	MP4C	Z	-6.009	-6.009	0	%100
93	M190	X	3.372	3.372	0	%100
94	M190	Z	-1.947	-1.947	0	%100
95	MP1B	X	10.408	10.408	0	%100
96	MP1B	Z	-6.009	-6.009	0	%100
97	MP2B	X	12.599	12.599	0	%100
98	MP2B	Z	-7.274	-7.274	0	%100
99	MP3B	X	10.408	10.408	0	%100
100	MP3B	Z	-6.009	-6.009	0	%100
101	MP4B	X	10.408	10.408	0	%100
102	MP4B	Z	-6.009	-6.009	0	%100
103	M101A	X	8.511	8.511	0	%100
104	M101A	Z	-4.914	-4.914	0	%100
105	M102A	X	3.998	3.998	0	%100
106	M102A	Z	-2.308	-2.308	0	%100
107	M116A	X	3.15	3.15	0	%100
108	M116A	Z	-1.818	-1.818	0	%100
109	M120A	X	12.599	12.599	0	%100
110	M120A	Z	-7.274	-7.274	0	%100
111	M125A	X	3.15	3.15	0	%100
112	M125A	Z	-1.818	-1.818	0	%100
113	M132A	X	18.404	18.404	0	%100
114	M132A	Z	-10.625	-10.625	0	%100
115	M133A	X	16.679	16.679	0	%100
116	M133A	Z	-9.629	-9.629	0	%100
117	M134A	X	18.404	18.404	0	%100
118	M134A	Z	-10.625	-10.625	0	%100
119	M125B	X	15.992	15.992	0	%100
120	M125B	Z	-9.233	-9.233	0	%100
121	M130A	X	3.998	3.998	0	%100
122	M130A	Z	-2.308	-2.308	0	%100

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	19.62	19.62	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	0	0	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	0	0	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	0	0	0	%100
9	M106	X	12.644	12.644	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	12.644	12.644	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	30.36	30.36	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	23.192	23.192	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	24.428	24.428	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	30.36	30.36	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	23.192	23.192	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	24.428	24.428	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	4.905	4.905	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	14.073	14.073	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	14.073	14.073	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	22.77	22.77	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	12.644	12.644	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	0	0	0	%100
37	M135	X	7.59	7.59	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	23.192	23.192	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	24.428	24.428	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	7.59	7.59	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	0	0	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	0	0	0	%100
49	M148	X	4.905	4.905	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	14.073	14.073	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	14.073	14.073	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	22.77	22.77	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
58	M154	Z	0	0	0	%100
59	M155	X	12.644	12.644	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	7.59	7.59	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	0	0	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	0	0	0	%100
67	M164	X	7.59	7.59	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	23.192	23.192	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	24.428	24.428	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	0	0	0	%100
75	MP1A	X	12.018	12.018	0	%100
76	MP1A	Z	0	0	0	%100
77	MP2A	X	14.548	14.548	0	%100
78	MP2A	Z	0	0	0	%100
79	MP3A	X	12.018	12.018	0	%100
80	MP3A	Z	0	0	0	%100
81	MP4A	X	12.018	12.018	0	%100
82	MP4A	Z	0	0	0	%100
83	M181	X	11.681	11.681	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	12.018	12.018	0	%100
86	MP1C	Z	0	0	0	%100
87	MP2C	X	14.548	14.548	0	%100
88	MP2C	Z	0	0	0	%100
89	MP3C	X	12.018	12.018	0	%100
90	MP3C	Z	0	0	0	%100
91	MP4C	X	12.018	12.018	0	%100
92	MP4C	Z	0	0	0	%100
93	M190	X	11.681	11.681	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	12.018	12.018	0	%100
96	MP1B	Z	0	0	0	%100
97	MP2B	X	14.548	14.548	0	%100
98	MP2B	Z	0	0	0	%100
99	MP3B	X	12.018	12.018	0	%100
100	MP3B	Z	0	0	0	%100
101	MP4B	X	12.018	12.018	0	%100
102	MP4B	Z	0	0	0	%100
103	M101A	X	9.827	9.827	0	%100
104	M101A	Z	0	0	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	0	0	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	0	0	0	%100
109	M120A	X	10.911	10.911	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	10.911	10.911	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	21.915	21.915	0	%100
114	M132A	Z	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 44 : Structure Wo (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
115	M133A	X	19.923	19.923	0	%100
116	M133A	Z	0	0	0	%100
117	M134A	X	19.923	19.923	0	%100
118	M134A	Z	0	0	0	%100
119	M125B	X	13.849	13.849	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	13.849	13.849	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	12.743	12.743	0	%100
2	M100	Z	7.357	7.357	0	%100
3	M101	X	4.063	4.063	0	%100
4	M101	Z	2.346	2.346	0	%100
5	M102	X	4.063	4.063	0	%100
6	M102	Z	2.346	2.346	0	%100
7	M103	X	6.573	6.573	0	%100
8	M103	Z	3.795	3.795	0	%100
9	M106	X	3.65	3.65	0	%100
10	M106	Z	2.107	2.107	0	%100
11	M107	X	14.6	14.6	0	%100
12	M107	Z	8.429	8.429	0	%100
13	M111	X	19.72	19.72	0	%100
14	M111	Z	11.385	11.385	0	%100
15	M112	X	6.695	6.695	0	%100
16	M112	Z	3.865	3.865	0	%100
17	M114	X	7.052	7.052	0	%100
18	M114	Z	4.071	4.071	0	%100
19	M116	X	19.72	19.72	0	%100
20	M116	Z	11.385	11.385	0	%100
21	M117	X	26.78	26.78	0	%100
22	M117	Z	15.461	15.461	0	%100
23	M119	X	28.206	28.206	0	%100
24	M119	Z	16.285	16.285	0	%100
25	M124	X	12.743	12.743	0	%100
26	M124	Z	7.357	7.357	0	%100
27	M125	X	4.063	4.063	0	%100
28	M125	Z	2.346	2.346	0	%100
29	M126	X	4.063	4.063	0	%100
30	M126	Z	2.346	2.346	0	%100
31	M127	X	6.573	6.573	0	%100
32	M127	Z	3.795	3.795	0	%100
33	M130	X	14.6	14.6	0	%100
34	M130	Z	8.429	8.429	0	%100
35	M131	X	3.65	3.65	0	%100
36	M131	Z	2.107	2.107	0	%100
37	M135	X	19.72	19.72	0	%100
38	M135	Z	11.385	11.385	0	%100
39	M136	X	26.78	26.78	0	%100
40	M136	Z	15.461	15.461	0	%100
41	M138	X	28.206	28.206	0	%100
42	M138	Z	16.285	16.285	0	%100
43	M140	X	19.72	19.72	0	%100
44	M140	Z	11.385	11.385	0	%100
45	M141	X	6.695	6.695	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
46	M141	Z	3.865	3.865	0	%100
47	M143	X	7.052	7.052	0	%100
48	M143	Z	4.071	4.071	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	16.25	16.25	0	%100
52	M149	Z	9.382	9.382	0	%100
53	M150	X	16.25	16.25	0	%100
54	M150	Z	9.382	9.382	0	%100
55	M151	X	26.293	26.293	0	%100
56	M151	Z	15.18	15.18	0	%100
57	M154	X	3.65	3.65	0	%100
58	M154	Z	2.107	2.107	0	%100
59	M155	X	3.65	3.65	0	%100
60	M155	Z	2.107	2.107	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	6.695	6.695	0	%100
64	M160	Z	3.865	3.865	0	%100
65	M162	X	7.052	7.052	0	%100
66	M162	Z	4.071	4.071	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	6.695	6.695	0	%100
70	M165	Z	3.865	3.865	0	%100
71	M167	X	7.052	7.052	0	%100
72	M167	Z	4.071	4.071	0	%100
73	M172	X	3.372	3.372	0	%100
74	M172	Z	1.947	1.947	0	%100
75	MP1A	X	10.408	10.408	0	%100
76	MP1A	Z	6.009	6.009	0	%100
77	MP2A	X	12.599	12.599	0	%100
78	MP2A	Z	7.274	7.274	0	%100
79	MP3A	X	10.408	10.408	0	%100
80	MP3A	Z	6.009	6.009	0	%100
81	MP4A	X	10.408	10.408	0	%100
82	MP4A	Z	6.009	6.009	0	%100
83	M181	X	3.372	3.372	0	%100
84	M181	Z	1.947	1.947	0	%100
85	MP1C	X	10.408	10.408	0	%100
86	MP1C	Z	6.009	6.009	0	%100
87	MP2C	X	12.599	12.599	0	%100
88	MP2C	Z	7.274	7.274	0	%100
89	MP3C	X	10.408	10.408	0	%100
90	MP3C	Z	6.009	6.009	0	%100
91	MP4C	X	10.408	10.408	0	%100
92	MP4C	Z	6.009	6.009	0	%100
93	M190	X	13.488	13.488	0	%100
94	M190	Z	7.787	7.787	0	%100
95	MP1B	X	10.408	10.408	0	%100
96	MP1B	Z	6.009	6.009	0	%100
97	MP2B	X	12.599	12.599	0	%100
98	MP2B	Z	7.274	7.274	0	%100
99	MP3B	X	10.408	10.408	0	%100
100	MP3B	Z	6.009	6.009	0	%100
101	MP4B	X	10.408	10.408	0	%100
102	MP4B	Z	6.009	6.009	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 45 : Structure Wo (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
103	M101A	X	8.511	8.511	0	%100
104	M101A	Z	4.914	4.914	0	%100
105	M102A	X	3.998	3.998	0	%100
106	M102A	Z	2.308	2.308	0	%100
107	M116A	X	3.15	3.15	0	%100
108	M116A	Z	1.818	1.818	0	%100
109	M120A	X	3.15	3.15	0	%100
110	M120A	Z	1.818	1.818	0	%100
111	M125A	X	12.599	12.599	0	%100
112	M125A	Z	7.274	7.274	0	%100
113	M132A	X	18.404	18.404	0	%100
114	M132A	Z	10.625	10.625	0	%100
115	M133A	X	18.404	18.404	0	%100
116	M133A	Z	10.625	10.625	0	%100
117	M134A	X	16.679	16.679	0	%100
118	M134A	Z	9.629	9.629	0	%100
119	M125B	X	3.998	3.998	0	%100
120	M125B	Z	2.308	2.308	0	%100
121	M130A	X	15.992	15.992	0	%100
122	M130A	Z	9.233	9.233	0	%100

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	2.452	2.452	0	%100
2	M100	Z	4.248	4.248	0	%100
3	M101	X	7.037	7.037	0	%100
4	M101	Z	12.188	12.188	0	%100
5	M102	X	7.037	7.037	0	%100
6	M102	Z	12.188	12.188	0	%100
7	M103	X	11.385	11.385	0	%100
8	M103	Z	19.72	19.72	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	6.322	6.322	0	%100
12	M107	Z	10.95	10.95	0	%100
13	M111	X	3.795	3.795	0	%100
14	M111	Z	6.573	6.573	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	3.795	3.795	0	%100
20	M116	Z	6.573	6.573	0	%100
21	M117	X	11.596	11.596	0	%100
22	M117	Z	20.085	20.085	0	%100
23	M119	X	12.214	12.214	0	%100
24	M119	Z	21.155	21.155	0	%100
25	M124	X	9.81	9.81	0	%100
26	M124	Z	16.991	16.991	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	6.322	6.322	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
34	M130	Z	10.95	10.95	0	%100
35	M131	X	6.322	6.322	0	%100
36	M131	Z	10.95	10.95	0	%100
37	M135	X	15.18	15.18	0	%100
38	M135	Z	26.293	26.293	0	%100
39	M136	X	11.596	11.596	0	%100
40	M136	Z	20.085	20.085	0	%100
41	M138	X	12.214	12.214	0	%100
42	M138	Z	21.155	21.155	0	%100
43	M140	X	15.18	15.18	0	%100
44	M140	Z	26.293	26.293	0	%100
45	M141	X	11.596	11.596	0	%100
46	M141	Z	20.085	20.085	0	%100
47	M143	X	12.214	12.214	0	%100
48	M143	Z	21.155	21.155	0	%100
49	M148	X	2.452	2.452	0	%100
50	M148	Z	4.248	4.248	0	%100
51	M149	X	7.037	7.037	0	%100
52	M149	Z	12.188	12.188	0	%100
53	M150	X	7.037	7.037	0	%100
54	M150	Z	12.188	12.188	0	%100
55	M151	X	11.385	11.385	0	%100
56	M151	Z	19.72	19.72	0	%100
57	M154	X	6.322	6.322	0	%100
58	M154	Z	10.95	10.95	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	3.795	3.795	0	%100
62	M159	Z	6.573	6.573	0	%100
63	M160	X	11.596	11.596	0	%100
64	M160	Z	20.085	20.085	0	%100
65	M162	X	12.214	12.214	0	%100
66	M162	Z	21.155	21.155	0	%100
67	M164	X	3.795	3.795	0	%100
68	M164	Z	6.573	6.573	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	5.841	5.841	0	%100
74	M172	Z	10.116	10.116	0	%100
75	MP1A	X	6.009	6.009	0	%100
76	MP1A	Z	10.408	10.408	0	%100
77	MP2A	X	7.274	7.274	0	%100
78	MP2A	Z	12.599	12.599	0	%100
79	MP3A	X	6.009	6.009	0	%100
80	MP3A	Z	10.408	10.408	0	%100
81	MP4A	X	6.009	6.009	0	%100
82	MP4A	Z	10.408	10.408	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	6.009	6.009	0	%100
86	MP1C	Z	10.408	10.408	0	%100
87	MP2C	X	7.274	7.274	0	%100
88	MP2C	Z	12.599	12.599	0	%100
89	MP3C	X	6.009	6.009	0	%100
90	MP3C	Z	10.408	10.408	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 46 : Structure Wo (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
91	MP4C	X	6.009	6.009	0	%100
92	MP4C	Z	10.408	10.408	0	%100
93	M190	X	5.841	5.841	0	%100
94	M190	Z	10.116	10.116	0	%100
95	MP1B	X	6.009	6.009	0	%100
96	MP1B	Z	10.408	10.408	0	%100
97	MP2B	X	7.274	7.274	0	%100
98	MP2B	Z	12.599	12.599	0	%100
99	MP3B	X	6.009	6.009	0	%100
100	MP3B	Z	10.408	10.408	0	%100
101	MP4B	X	6.009	6.009	0	%100
102	MP4B	Z	10.408	10.408	0	%100
103	M101A	X	4.914	4.914	0	%100
104	M101A	Z	8.511	8.511	0	%100
105	M102A	X	6.925	6.925	0	%100
106	M102A	Z	11.994	11.994	0	%100
107	M116A	X	5.455	5.455	0	%100
108	M116A	Z	9.449	9.449	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	5.455	5.455	0	%100
112	M125A	Z	9.449	9.449	0	%100
113	M132A	X	9.961	9.961	0	%100
114	M132A	Z	17.254	17.254	0	%100
115	M133A	X	10.957	10.957	0	%100
116	M133A	Z	18.979	18.979	0	%100
117	M134A	X	9.961	9.961	0	%100
118	M134A	Z	17.254	17.254	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	6.925	6.925	0	%100
122	M130A	Z	11.994	11.994	0	%100

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	0	0	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	18.764	18.764	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	18.764	18.764	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	30.36	30.36	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	4.215	4.215	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	4.215	4.215	0	%100
13	M111	X	0	0	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	7.731	7.731	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	8.143	8.143	0	%100
19	M116	X	0	0	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
22	M117	Z	7.731	7.731	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	8.143	8.143	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	14.715	14.715	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	4.691	4.691	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	4.691	4.691	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	7.59	7.59	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	4.215	4.215	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	16.859	16.859	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	22.77	22.77	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	7.731	7.731	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	8.143	8.143	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	22.77	22.77	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	30.923	30.923	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	32.57	32.57	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	14.715	14.715	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	4.691	4.691	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	4.691	4.691	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	7.59	7.59	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	16.859	16.859	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	4.215	4.215	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	22.77	22.77	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	30.923	30.923	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	32.57	32.57	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	22.77	22.77	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	7.731	7.731	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	8.143	8.143	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	15.575	15.575	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	12.018	12.018	0	%100
77	MP2A	X	0	0	0	%100
78	MP2A	Z	14.548	14.548	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 47 : Structure Wo (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
79	MP3A	X	0	0	0	%100
80	MP3A	Z	12.018	12.018	0	%100
81	MP4A	X	0	0	0	%100
82	MP4A	Z	12.018	12.018	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	3.894	3.894	0	%100
85	MP1C	X	0	0	0	%100
86	MP1C	Z	12.018	12.018	0	%100
87	MP2C	X	0	0	0	%100
88	MP2C	Z	14.548	14.548	0	%100
89	MP3C	X	0	0	0	%100
90	MP3C	Z	12.018	12.018	0	%100
91	MP4C	X	0	0	0	%100
92	MP4C	Z	12.018	12.018	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	3.894	3.894	0	%100
95	MP1B	X	0	0	0	%100
96	MP1B	Z	12.018	12.018	0	%100
97	MP2B	X	0	0	0	%100
98	MP2B	Z	14.548	14.548	0	%100
99	MP3B	X	0	0	0	%100
100	MP3B	Z	12.018	12.018	0	%100
101	MP4B	X	0	0	0	%100
102	MP4B	Z	12.018	12.018	0	%100
103	M101A	X	0	0	0	%100
104	M101A	Z	9.827	9.827	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	18.466	18.466	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	14.548	14.548	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	3.637	3.637	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	3.637	3.637	0	%100
113	M132A	X	0	0	0	%100
114	M132A	Z	19.259	19.259	0	%100
115	M133A	X	0	0	0	%100
116	M133A	Z	21.251	21.251	0	%100
117	M134A	X	0	0	0	%100
118	M134A	Z	21.251	21.251	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	4.616	4.616	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	4.616	4.616	0	%100

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-2.452	-2.452	0	%100
2	M100	Z	4.248	4.248	0	%100
3	M101	X	-7.037	-7.037	0	%100
4	M101	Z	12.188	12.188	0	%100
5	M102	X	-7.037	-7.037	0	%100
6	M102	Z	12.188	12.188	0	%100
7	M103	X	-11.385	-11.385	0	%100
8	M103	Z	19.72	19.72	0	%100
9	M106	X	-6.322	-6.322	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
10	M106	Z	10.95	10.95	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	-3.795	-3.795	0	%100
14	M111	Z	6.573	6.573	0	%100
15	M112	X	-11.596	-11.596	0	%100
16	M112	Z	20.085	20.085	0	%100
17	M114	X	-12.214	-12.214	0	%100
18	M114	Z	21.155	21.155	0	%100
19	M116	X	-3.795	-3.795	0	%100
20	M116	Z	6.573	6.573	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	-2.452	-2.452	0	%100
26	M124	Z	4.248	4.248	0	%100
27	M125	X	-7.037	-7.037	0	%100
28	M125	Z	12.188	12.188	0	%100
29	M126	X	-7.037	-7.037	0	%100
30	M126	Z	12.188	12.188	0	%100
31	M127	X	-11.385	-11.385	0	%100
32	M127	Z	19.72	19.72	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	-6.322	-6.322	0	%100
36	M131	Z	10.95	10.95	0	%100
37	M135	X	-3.795	-3.795	0	%100
38	M135	Z	6.573	6.573	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	-3.795	-3.795	0	%100
44	M140	Z	6.573	6.573	0	%100
45	M141	X	-11.596	-11.596	0	%100
46	M141	Z	20.085	20.085	0	%100
47	M143	X	-12.214	-12.214	0	%100
48	M143	Z	21.155	21.155	0	%100
49	M148	X	-9.81	-9.81	0	%100
50	M148	Z	16.991	16.991	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	-6.322	-6.322	0	%100
58	M154	Z	10.95	10.95	0	%100
59	M155	X	-6.322	-6.322	0	%100
60	M155	Z	10.95	10.95	0	%100
61	M159	X	-15.18	-15.18	0	%100
62	M159	Z	26.293	26.293	0	%100
63	M160	X	-11.596	-11.596	0	%100
64	M160	Z	20.085	20.085	0	%100
65	M162	X	-12.214	-12.214	0	%100
66	M162	Z	21.155	21.155	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 48 : Structure Wo (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
67	M164	X	-15.18	-15.18	0	%100
68	M164	Z	26.293	26.293	0	%100
69	M165	X	-11.596	-11.596	0	%100
70	M165	Z	20.085	20.085	0	%100
71	M167	X	-12.214	-12.214	0	%100
72	M167	Z	21.155	21.155	0	%100
73	M172	X	-5.841	-5.841	0	%100
74	M172	Z	10.116	10.116	0	%100
75	MP1A	X	-6.009	-6.009	0	%100
76	MP1A	Z	10.408	10.408	0	%100
77	MP2A	X	-7.274	-7.274	0	%100
78	MP2A	Z	12.599	12.599	0	%100
79	MP3A	X	-6.009	-6.009	0	%100
80	MP3A	Z	10.408	10.408	0	%100
81	MP4A	X	-6.009	-6.009	0	%100
82	MP4A	Z	10.408	10.408	0	%100
83	M181	X	-5.841	-5.841	0	%100
84	M181	Z	10.116	10.116	0	%100
85	MP1C	X	-6.009	-6.009	0	%100
86	MP1C	Z	10.408	10.408	0	%100
87	MP2C	X	-7.274	-7.274	0	%100
88	MP2C	Z	12.599	12.599	0	%100
89	MP3C	X	-6.009	-6.009	0	%100
90	MP3C	Z	10.408	10.408	0	%100
91	MP4C	X	-6.009	-6.009	0	%100
92	MP4C	Z	10.408	10.408	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	-6.009	-6.009	0	%100
96	MP1B	Z	10.408	10.408	0	%100
97	MP2B	X	-7.274	-7.274	0	%100
98	MP2B	Z	12.599	12.599	0	%100
99	MP3B	X	-6.009	-6.009	0	%100
100	MP3B	Z	10.408	10.408	0	%100
101	MP4B	X	-6.009	-6.009	0	%100
102	MP4B	Z	10.408	10.408	0	%100
103	M101A	X	-4.914	-4.914	0	%100
104	M101A	Z	8.511	8.511	0	%100
105	M102A	X	-6.925	-6.925	0	%100
106	M102A	Z	11.994	11.994	0	%100
107	M116A	X	-5.455	-5.455	0	%100
108	M116A	Z	9.449	9.449	0	%100
109	M120A	X	-5.455	-5.455	0	%100
110	M120A	Z	9.449	9.449	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	-9.961	-9.961	0	%100
114	M132A	Z	17.254	17.254	0	%100
115	M133A	X	-9.961	-9.961	0	%100
116	M133A	Z	17.254	17.254	0	%100
117	M134A	X	-10.957	-10.957	0	%100
118	M134A	Z	18.979	18.979	0	%100
119	M125B	X	-6.925	-6.925	0	%100
120	M125B	Z	11.994	11.994	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	0	0	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-12.743	-12.743	0	%100
2	M100	Z	7.357	7.357	0	%100
3	M101	X	-4.063	-4.063	0	%100
4	M101	Z	2.346	2.346	0	%100
5	M102	X	-4.063	-4.063	0	%100
6	M102	Z	2.346	2.346	0	%100
7	M103	X	-6.573	-6.573	0	%100
8	M103	Z	3.795	3.795	0	%100
9	M106	X	-14.6	-14.6	0	%100
10	M106	Z	8.429	8.429	0	%100
11	M107	X	-3.65	-3.65	0	%100
12	M107	Z	2.107	2.107	0	%100
13	M111	X	-19.72	-19.72	0	%100
14	M111	Z	11.385	11.385	0	%100
15	M112	X	-26.78	-26.78	0	%100
16	M112	Z	15.461	15.461	0	%100
17	M114	X	-28.206	-28.206	0	%100
18	M114	Z	16.285	16.285	0	%100
19	M116	X	-19.72	-19.72	0	%100
20	M116	Z	11.385	11.385	0	%100
21	M117	X	-6.695	-6.695	0	%100
22	M117	Z	3.865	3.865	0	%100
23	M119	X	-7.052	-7.052	0	%100
24	M119	Z	4.071	4.071	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	-16.25	-16.25	0	%100
28	M125	Z	9.382	9.382	0	%100
29	M126	X	-16.25	-16.25	0	%100
30	M126	Z	9.382	9.382	0	%100
31	M127	X	-26.293	-26.293	0	%100
32	M127	Z	15.18	15.18	0	%100
33	M130	X	-3.65	-3.65	0	%100
34	M130	Z	2.107	2.107	0	%100
35	M131	X	-3.65	-3.65	0	%100
36	M131	Z	2.107	2.107	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	-6.695	-6.695	0	%100
40	M136	Z	3.865	3.865	0	%100
41	M138	X	-7.052	-7.052	0	%100
42	M138	Z	4.071	4.071	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	-6.695	-6.695	0	%100
46	M141	Z	3.865	3.865	0	%100
47	M143	X	-7.052	-7.052	0	%100
48	M143	Z	4.071	4.071	0	%100
49	M148	X	-12.743	-12.743	0	%100
50	M148	Z	7.357	7.357	0	%100
51	M149	X	-4.063	-4.063	0	%100
52	M149	Z	2.346	2.346	0	%100
53	M150	X	-4.063	-4.063	0	%100
54	M150	Z	2.346	2.346	0	%100
55	M151	X	-6.573	-6.573	0	%100
56	M151	Z	3.795	3.795	0	%100
57	M154	X	-3.65	-3.65	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
58	M154	Z	2.107	2.107	0	%100
59	M155	X	-14.6	-14.6	0	%100
60	M155	Z	8.429	8.429	0	%100
61	M159	X	-19.72	-19.72	0	%100
62	M159	Z	11.385	11.385	0	%100
63	M160	X	-6.695	-6.695	0	%100
64	M160	Z	3.865	3.865	0	%100
65	M162	X	-7.052	-7.052	0	%100
66	M162	Z	4.071	4.071	0	%100
67	M164	X	-19.72	-19.72	0	%100
68	M164	Z	11.385	11.385	0	%100
69	M165	X	-26.78	-26.78	0	%100
70	M165	Z	15.461	15.461	0	%100
71	M167	X	-28.206	-28.206	0	%100
72	M167	Z	16.285	16.285	0	%100
73	M172	X	-3.372	-3.372	0	%100
74	M172	Z	1.947	1.947	0	%100
75	MP1A	X	-10.408	-10.408	0	%100
76	MP1A	Z	6.009	6.009	0	%100
77	MP2A	X	-12.599	-12.599	0	%100
78	MP2A	Z	7.274	7.274	0	%100
79	MP3A	X	-10.408	-10.408	0	%100
80	MP3A	Z	6.009	6.009	0	%100
81	MP4A	X	-10.408	-10.408	0	%100
82	MP4A	Z	6.009	6.009	0	%100
83	M181	X	-13.488	-13.488	0	%100
84	M181	Z	7.787	7.787	0	%100
85	MP1C	X	-10.408	-10.408	0	%100
86	MP1C	Z	6.009	6.009	0	%100
87	MP2C	X	-12.599	-12.599	0	%100
88	MP2C	Z	7.274	7.274	0	%100
89	MP3C	X	-10.408	-10.408	0	%100
90	MP3C	Z	6.009	6.009	0	%100
91	MP4C	X	-10.408	-10.408	0	%100
92	MP4C	Z	6.009	6.009	0	%100
93	M190	X	-3.372	-3.372	0	%100
94	M190	Z	1.947	1.947	0	%100
95	MP1B	X	-10.408	-10.408	0	%100
96	MP1B	Z	6.009	6.009	0	%100
97	MP2B	X	-12.599	-12.599	0	%100
98	MP2B	Z	7.274	7.274	0	%100
99	MP3B	X	-10.408	-10.408	0	%100
100	MP3B	Z	6.009	6.009	0	%100
101	MP4B	X	-10.408	-10.408	0	%100
102	MP4B	Z	6.009	6.009	0	%100
103	M101A	X	-8.511	-8.511	0	%100
104	M101A	Z	4.914	4.914	0	%100
105	M102A	X	-3.998	-3.998	0	%100
106	M102A	Z	2.308	2.308	0	%100
107	M116A	X	-3.15	-3.15	0	%100
108	M116A	Z	1.818	1.818	0	%100
109	M120A	X	-12.599	-12.599	0	%100
110	M120A	Z	7.274	7.274	0	%100
111	M125A	X	-3.15	-3.15	0	%100
112	M125A	Z	1.818	1.818	0	%100
113	M132A	X	-18.404	-18.404	0	%100
114	M132A	Z	10.625	10.625	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 49 : Structure Wo (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
115	M133A	X	-16.679	-16.679	0	%100
116	M133A	Z	9.629	9.629	0	%100
117	M134A	X	-18.404	-18.404	0	%100
118	M134A	Z	10.625	10.625	0	%100
119	M125B	X	-15.992	-15.992	0	%100
120	M125B	Z	9.233	9.233	0	%100
121	M130A	X	-3.998	-3.998	0	%100
122	M130A	Z	2.308	2.308	0	%100

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-19.62	-19.62	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	0	0	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	0	0	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	0	0	0	%100
9	M106	X	-12.644	-12.644	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	-12.644	-12.644	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	-30.36	-30.36	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	-23.192	-23.192	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	-24.428	-24.428	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	-30.36	-30.36	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	-23.192	-23.192	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	-24.428	-24.428	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	-4.905	-4.905	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	-14.073	-14.073	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	-14.073	-14.073	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	-22.77	-22.77	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	-12.644	-12.644	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	0	0	0	%100
37	M135	X	-7.59	-7.59	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	-23.192	-23.192	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	-24.428	-24.428	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	-7.59	-7.59	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
46	M141	Z	0	0	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	0	0	0	%100
49	M148	X	-4.905	-4.905	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	-14.073	-14.073	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	-14.073	-14.073	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	-22.77	-22.77	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	0	0	0	%100
59	M155	X	-12.644	-12.644	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	-7.59	-7.59	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	0	0	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	0	0	0	%100
67	M164	X	-7.59	-7.59	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	-23.192	-23.192	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	-24.428	-24.428	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	0	0	0	%100
75	MP1A	X	-12.018	-12.018	0	%100
76	MP1A	Z	0	0	0	%100
77	MP2A	X	-14.548	-14.548	0	%100
78	MP2A	Z	0	0	0	%100
79	MP3A	X	-12.018	-12.018	0	%100
80	MP3A	Z	0	0	0	%100
81	MP4A	X	-12.018	-12.018	0	%100
82	MP4A	Z	0	0	0	%100
83	M181	X	-11.681	-11.681	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	-12.018	-12.018	0	%100
86	MP1C	Z	0	0	0	%100
87	MP2C	X	-14.548	-14.548	0	%100
88	MP2C	Z	0	0	0	%100
89	MP3C	X	-12.018	-12.018	0	%100
90	MP3C	Z	0	0	0	%100
91	MP4C	X	-12.018	-12.018	0	%100
92	MP4C	Z	0	0	0	%100
93	M190	X	-11.681	-11.681	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	-12.018	-12.018	0	%100
96	MP1B	Z	0	0	0	%100
97	MP2B	X	-14.548	-14.548	0	%100
98	MP2B	Z	0	0	0	%100
99	MP3B	X	-12.018	-12.018	0	%100
100	MP3B	Z	0	0	0	%100
101	MP4B	X	-12.018	-12.018	0	%100
102	MP4B	Z	0	0	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 50 : Structure Wo (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
103	M101A	X	-9.827	-9.827	0	%100
104	M101A	Z	0	0	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	0	0	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	0	0	0	%100
109	M120A	X	-10.911	-10.911	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	-10.911	-10.911	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	-21.915	-21.915	0	%100
114	M132A	Z	0	0	0	%100
115	M133A	X	-19.923	-19.923	0	%100
116	M133A	Z	0	0	0	%100
117	M134A	X	-19.923	-19.923	0	%100
118	M134A	Z	0	0	0	%100
119	M125B	X	-13.849	-13.849	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	-13.849	-13.849	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-12.743	-12.743	0	%100
2	M100	Z	-7.357	-7.357	0	%100
3	M101	X	-4.063	-4.063	0	%100
4	M101	Z	-2.346	-2.346	0	%100
5	M102	X	-4.063	-4.063	0	%100
6	M102	Z	-2.346	-2.346	0	%100
7	M103	X	-6.573	-6.573	0	%100
8	M103	Z	-3.795	-3.795	0	%100
9	M106	X	-3.65	-3.65	0	%100
10	M106	Z	-2.107	-2.107	0	%100
11	M107	X	-14.6	-14.6	0	%100
12	M107	Z	-8.429	-8.429	0	%100
13	M111	X	-19.72	-19.72	0	%100
14	M111	Z	-11.385	-11.385	0	%100
15	M112	X	-6.695	-6.695	0	%100
16	M112	Z	-3.865	-3.865	0	%100
17	M114	X	-7.052	-7.052	0	%100
18	M114	Z	-4.071	-4.071	0	%100
19	M116	X	-19.72	-19.72	0	%100
20	M116	Z	-11.385	-11.385	0	%100
21	M117	X	-26.78	-26.78	0	%100
22	M117	Z	-15.461	-15.461	0	%100
23	M119	X	-28.206	-28.206	0	%100
24	M119	Z	-16.285	-16.285	0	%100
25	M124	X	-12.743	-12.743	0	%100
26	M124	Z	-7.357	-7.357	0	%100
27	M125	X	-4.063	-4.063	0	%100
28	M125	Z	-2.346	-2.346	0	%100
29	M126	X	-4.063	-4.063	0	%100
30	M126	Z	-2.346	-2.346	0	%100
31	M127	X	-6.573	-6.573	0	%100
32	M127	Z	-3.795	-3.795	0	%100
33	M130	X	-14.6	-14.6	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
34	M130	Z	-8.429	-8.429	0	%100
35	M131	X	-3.65	-3.65	0	%100
36	M131	Z	-2.107	-2.107	0	%100
37	M135	X	-19.72	-19.72	0	%100
38	M135	Z	-11.385	-11.385	0	%100
39	M136	X	-26.78	-26.78	0	%100
40	M136	Z	-15.461	-15.461	0	%100
41	M138	X	-28.206	-28.206	0	%100
42	M138	Z	-16.285	-16.285	0	%100
43	M140	X	-19.72	-19.72	0	%100
44	M140	Z	-11.385	-11.385	0	%100
45	M141	X	-6.695	-6.695	0	%100
46	M141	Z	-3.865	-3.865	0	%100
47	M143	X	-7.052	-7.052	0	%100
48	M143	Z	-4.071	-4.071	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	-16.25	-16.25	0	%100
52	M149	Z	-9.382	-9.382	0	%100
53	M150	X	-16.25	-16.25	0	%100
54	M150	Z	-9.382	-9.382	0	%100
55	M151	X	-26.293	-26.293	0	%100
56	M151	Z	-15.18	-15.18	0	%100
57	M154	X	-3.65	-3.65	0	%100
58	M154	Z	-2.107	-2.107	0	%100
59	M155	X	-3.65	-3.65	0	%100
60	M155	Z	-2.107	-2.107	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	-6.695	-6.695	0	%100
64	M160	Z	-3.865	-3.865	0	%100
65	M162	X	-7.052	-7.052	0	%100
66	M162	Z	-4.071	-4.071	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	-6.695	-6.695	0	%100
70	M165	Z	-3.865	-3.865	0	%100
71	M167	X	-7.052	-7.052	0	%100
72	M167	Z	-4.071	-4.071	0	%100
73	M172	X	-3.372	-3.372	0	%100
74	M172	Z	-1.947	-1.947	0	%100
75	MP1A	X	-10.408	-10.408	0	%100
76	MP1A	Z	-6.009	-6.009	0	%100
77	MP2A	X	-12.599	-12.599	0	%100
78	MP2A	Z	-7.274	-7.274	0	%100
79	MP3A	X	-10.408	-10.408	0	%100
80	MP3A	Z	-6.009	-6.009	0	%100
81	MP4A	X	-10.408	-10.408	0	%100
82	MP4A	Z	-6.009	-6.009	0	%100
83	M181	X	-3.372	-3.372	0	%100
84	M181	Z	-1.947	-1.947	0	%100
85	MP1C	X	-10.408	-10.408	0	%100
86	MP1C	Z	-6.009	-6.009	0	%100
87	MP2C	X	-12.599	-12.599	0	%100
88	MP2C	Z	-7.274	-7.274	0	%100
89	MP3C	X	-10.408	-10.408	0	%100
90	MP3C	Z	-6.009	-6.009	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 51 : Structure Wo (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
91	MP4C	X	-10.408	-10.408	0	%100
92	MP4C	Z	-6.009	-6.009	0	%100
93	M190	X	-13.488	-13.488	0	%100
94	M190	Z	-7.787	-7.787	0	%100
95	MP1B	X	-10.408	-10.408	0	%100
96	MP1B	Z	-6.009	-6.009	0	%100
97	MP2B	X	-12.599	-12.599	0	%100
98	MP2B	Z	-7.274	-7.274	0	%100
99	MP3B	X	-10.408	-10.408	0	%100
100	MP3B	Z	-6.009	-6.009	0	%100
101	MP4B	X	-10.408	-10.408	0	%100
102	MP4B	Z	-6.009	-6.009	0	%100
103	M101A	X	-8.511	-8.511	0	%100
104	M101A	Z	-4.914	-4.914	0	%100
105	M102A	X	-3.998	-3.998	0	%100
106	M102A	Z	-2.308	-2.308	0	%100
107	M116A	X	-3.15	-3.15	0	%100
108	M116A	Z	-1.818	-1.818	0	%100
109	M120A	X	-3.15	-3.15	0	%100
110	M120A	Z	-1.818	-1.818	0	%100
111	M125A	X	-12.599	-12.599	0	%100
112	M125A	Z	-7.274	-7.274	0	%100
113	M132A	X	-18.404	-18.404	0	%100
114	M132A	Z	-10.625	-10.625	0	%100
115	M133A	X	-18.404	-18.404	0	%100
116	M133A	Z	-10.625	-10.625	0	%100
117	M134A	X	-16.679	-16.679	0	%100
118	M134A	Z	-9.629	-9.629	0	%100
119	M125B	X	-3.998	-3.998	0	%100
120	M125B	Z	-2.308	-2.308	0	%100
121	M130A	X	-15.992	-15.992	0	%100
122	M130A	Z	-9.233	-9.233	0	%100

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-2.452	-2.452	0	%100
2	M100	Z	-4.248	-4.248	0	%100
3	M101	X	-7.037	-7.037	0	%100
4	M101	Z	-12.188	-12.188	0	%100
5	M102	X	-7.037	-7.037	0	%100
6	M102	Z	-12.188	-12.188	0	%100
7	M103	X	-11.385	-11.385	0	%100
8	M103	Z	-19.72	-19.72	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	-6.322	-6.322	0	%100
12	M107	Z	-10.95	-10.95	0	%100
13	M111	X	-3.795	-3.795	0	%100
14	M111	Z	-6.573	-6.573	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	-3.795	-3.795	0	%100
20	M116	Z	-6.573	-6.573	0	%100
21	M117	X	-11.596	-11.596	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
22	M117	Z	-20.085	-20.085	0	%100
23	M119	X	-12.214	-12.214	0	%100
24	M119	Z	-21.155	-21.155	0	%100
25	M124	X	-9.81	-9.81	0	%100
26	M124	Z	-16.991	-16.991	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	-6.322	-6.322	0	%100
34	M130	Z	-10.95	-10.95	0	%100
35	M131	X	-6.322	-6.322	0	%100
36	M131	Z	-10.95	-10.95	0	%100
37	M135	X	-15.18	-15.18	0	%100
38	M135	Z	-26.293	-26.293	0	%100
39	M136	X	-11.596	-11.596	0	%100
40	M136	Z	-20.085	-20.085	0	%100
41	M138	X	-12.214	-12.214	0	%100
42	M138	Z	-21.155	-21.155	0	%100
43	M140	X	-15.18	-15.18	0	%100
44	M140	Z	-26.293	-26.293	0	%100
45	M141	X	-11.596	-11.596	0	%100
46	M141	Z	-20.085	-20.085	0	%100
47	M143	X	-12.214	-12.214	0	%100
48	M143	Z	-21.155	-21.155	0	%100
49	M148	X	-2.452	-2.452	0	%100
50	M148	Z	-4.248	-4.248	0	%100
51	M149	X	-7.037	-7.037	0	%100
52	M149	Z	-12.188	-12.188	0	%100
53	M150	X	-7.037	-7.037	0	%100
54	M150	Z	-12.188	-12.188	0	%100
55	M151	X	-11.385	-11.385	0	%100
56	M151	Z	-19.72	-19.72	0	%100
57	M154	X	-6.322	-6.322	0	%100
58	M154	Z	-10.95	-10.95	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	-3.795	-3.795	0	%100
62	M159	Z	-6.573	-6.573	0	%100
63	M160	X	-11.596	-11.596	0	%100
64	M160	Z	-20.085	-20.085	0	%100
65	M162	X	-12.214	-12.214	0	%100
66	M162	Z	-21.155	-21.155	0	%100
67	M164	X	-3.795	-3.795	0	%100
68	M164	Z	-6.573	-6.573	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	-5.841	-5.841	0	%100
74	M172	Z	-10.116	-10.116	0	%100
75	MP1A	X	-6.009	-6.009	0	%100
76	MP1A	Z	-10.408	-10.408	0	%100
77	MP2A	X	-7.274	-7.274	0	%100
78	MP2A	Z	-12.599	-12.599	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 52 : Structure Wo (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
79	MP3A	X	-6.009	-6.009	0	%100
80	MP3A	Z	-10.408	-10.408	0	%100
81	MP4A	X	-6.009	-6.009	0	%100
82	MP4A	Z	-10.408	-10.408	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	-6.009	-6.009	0	%100
86	MP1C	Z	-10.408	-10.408	0	%100
87	MP2C	X	-7.274	-7.274	0	%100
88	MP2C	Z	-12.599	-12.599	0	%100
89	MP3C	X	-6.009	-6.009	0	%100
90	MP3C	Z	-10.408	-10.408	0	%100
91	MP4C	X	-6.009	-6.009	0	%100
92	MP4C	Z	-10.408	-10.408	0	%100
93	M190	X	-5.841	-5.841	0	%100
94	M190	Z	-10.116	-10.116	0	%100
95	MP1B	X	-6.009	-6.009	0	%100
96	MP1B	Z	-10.408	-10.408	0	%100
97	MP2B	X	-7.274	-7.274	0	%100
98	MP2B	Z	-12.599	-12.599	0	%100
99	MP3B	X	-6.009	-6.009	0	%100
100	MP3B	Z	-10.408	-10.408	0	%100
101	MP4B	X	-6.009	-6.009	0	%100
102	MP4B	Z	-10.408	-10.408	0	%100
103	M101A	X	-4.914	-4.914	0	%100
104	M101A	Z	-8.511	-8.511	0	%100
105	M102A	X	-6.925	-6.925	0	%100
106	M102A	Z	-11.994	-11.994	0	%100
107	M116A	X	-5.455	-5.455	0	%100
108	M116A	Z	-9.449	-9.449	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	-5.455	-5.455	0	%100
112	M125A	Z	-9.449	-9.449	0	%100
113	M132A	X	-9.961	-9.961	0	%100
114	M132A	Z	-17.254	-17.254	0	%100
115	M133A	X	-10.957	-10.957	0	%100
116	M133A	Z	-18.979	-18.979	0	%100
117	M134A	X	-9.961	-9.961	0	%100
118	M134A	Z	-17.254	-17.254	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	-6.925	-6.925	0	%100
122	M130A	Z	-11.994	-11.994	0	%100

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	0	0	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	-4.103	-4.103	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	-4.103	-4.103	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	-5.595	-5.595	0	%100
9	M106	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
10	M106	Z	-1.03	-1.03	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	-1.03	-1.03	0	%100
13	M111	X	0	0	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	-1.397	-1.397	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	-1.458	-1.458	0	%100
19	M116	X	0	0	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	-1.397	-1.397	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	-1.458	-1.458	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	-3.479	-3.479	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	-1.026	-1.026	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	-1.026	-1.026	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	-1.399	-1.399	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	-1.03	-1.03	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	-4.118	-4.118	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	-4.128	-4.128	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	-1.397	-1.397	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	-1.458	-1.458	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	-4.128	-4.128	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	-5.587	-5.587	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	-5.831	-5.831	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	-3.479	-3.479	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	-1.026	-1.026	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	-1.026	-1.026	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	-1.399	-1.399	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	-4.118	-4.118	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	-1.03	-1.03	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	-4.128	-4.128	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	-5.587	-5.587	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	-5.831	-5.831	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 53 : Structure Wi (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
67	M164	X	0	0	0	%100
68	M164	Z	-4.128	-4.128	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	-1.397	-1.397	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	-1.458	-1.458	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	-4.356	-4.356	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	-3.514	-3.514	0	%100
77	MP2A	X	0	0	0	%100
78	MP2A	Z	-3.888	-3.888	0	%100
79	MP3A	X	0	0	0	%100
80	MP3A	Z	-3.514	-3.514	0	%100
81	MP4A	X	0	0	0	%100
82	MP4A	Z	-3.514	-3.514	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	-1.089	-1.089	0	%100
85	MP1C	X	0	0	0	%100
86	MP1C	Z	-3.514	-3.514	0	%100
87	MP2C	X	0	0	0	%100
88	MP2C	Z	-3.888	-3.888	0	%100
89	MP3C	X	0	0	0	%100
90	MP3C	Z	-3.514	-3.514	0	%100
91	MP4C	X	0	0	0	%100
92	MP4C	Z	-3.514	-3.514	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	-1.089	-1.089	0	%100
95	MP1B	X	0	0	0	%100
96	MP1B	Z	-3.514	-3.514	0	%100
97	MP2B	X	0	0	0	%100
98	MP2B	Z	-3.888	-3.888	0	%100
99	MP3B	X	0	0	0	%100
100	MP3B	Z	-3.514	-3.514	0	%100
101	MP4B	X	0	0	0	%100
102	MP4B	Z	-3.514	-3.514	0	%100
103	M101A	X	0	0	0	%100
104	M101A	Z	-2.885	-2.885	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	-4.029	-4.029	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	-3.888	-3.888	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	-.972	-.972	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	-.972	-.972	0	%100
113	M132A	X	0	0	0	%100
114	M132A	Z	-3.668	-3.668	0	%100
115	M133A	X	0	0	0	%100
116	M133A	Z	-4.577	-4.577	0	%100
117	M134A	X	0	0	0	%100
118	M134A	Z	-4.577	-4.577	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	-1.007	-1.007	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	-1.007	-1.007	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	.58	.58	0	%100
2	M100	Z	-1.004	-1.004	0	%100
3	M101	X	1.539	1.539	0	%100
4	M101	Z	-2.665	-2.665	0	%100
5	M102	X	1.539	1.539	0	%100
6	M102	Z	-2.665	-2.665	0	%100
7	M103	X	2.098	2.098	0	%100
8	M103	Z	-3.634	-3.634	0	%100
9	M106	X	1.544	1.544	0	%100
10	M106	Z	-2.675	-2.675	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	.688	.688	0	%100
14	M111	Z	-1.192	-1.192	0	%100
15	M112	X	2.095	2.095	0	%100
16	M112	Z	-3.629	-3.629	0	%100
17	M114	X	2.186	2.186	0	%100
18	M114	Z	-3.787	-3.787	0	%100
19	M116	X	.688	.688	0	%100
20	M116	Z	-1.192	-1.192	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	.58	.58	0	%100
26	M124	Z	-1.004	-1.004	0	%100
27	M125	X	1.539	1.539	0	%100
28	M125	Z	-2.665	-2.665	0	%100
29	M126	X	1.539	1.539	0	%100
30	M126	Z	-2.665	-2.665	0	%100
31	M127	X	2.098	2.098	0	%100
32	M127	Z	-3.634	-3.634	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	1.544	1.544	0	%100
36	M131	Z	-2.675	-2.675	0	%100
37	M135	X	.688	.688	0	%100
38	M135	Z	-1.192	-1.192	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	.688	.688	0	%100
44	M140	Z	-1.192	-1.192	0	%100
45	M141	X	2.095	2.095	0	%100
46	M141	Z	-3.629	-3.629	0	%100
47	M143	X	2.186	2.186	0	%100
48	M143	Z	-3.787	-3.787	0	%100
49	M148	X	2.319	2.319	0	%100
50	M148	Z	-4.017	-4.017	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	1.544	1.544	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
58	M154	Z	-2.675	-2.675	0	%100
59	M155	X	1.544	1.544	0	%100
60	M155	Z	-2.675	-2.675	0	%100
61	M159	X	2.752	2.752	0	%100
62	M159	Z	-4.766	-4.766	0	%100
63	M160	X	2.095	2.095	0	%100
64	M160	Z	-3.629	-3.629	0	%100
65	M162	X	2.186	2.186	0	%100
66	M162	Z	-3.787	-3.787	0	%100
67	M164	X	2.752	2.752	0	%100
68	M164	Z	-4.766	-4.766	0	%100
69	M165	X	2.095	2.095	0	%100
70	M165	Z	-3.629	-3.629	0	%100
71	M167	X	2.186	2.186	0	%100
72	M167	Z	-3.787	-3.787	0	%100
73	M172	X	1.633	1.633	0	%100
74	M172	Z	-2.829	-2.829	0	%100
75	MP1A	X	1.757	1.757	0	%100
76	MP1A	Z	-3.043	-3.043	0	%100
77	MP2A	X	1.944	1.944	0	%100
78	MP2A	Z	-3.367	-3.367	0	%100
79	MP3A	X	1.757	1.757	0	%100
80	MP3A	Z	-3.043	-3.043	0	%100
81	MP4A	X	1.757	1.757	0	%100
82	MP4A	Z	-3.043	-3.043	0	%100
83	M181	X	1.633	1.633	0	%100
84	M181	Z	-2.829	-2.829	0	%100
85	MP1C	X	1.757	1.757	0	%100
86	MP1C	Z	-3.043	-3.043	0	%100
87	MP2C	X	1.944	1.944	0	%100
88	MP2C	Z	-3.367	-3.367	0	%100
89	MP3C	X	1.757	1.757	0	%100
90	MP3C	Z	-3.043	-3.043	0	%100
91	MP4C	X	1.757	1.757	0	%100
92	MP4C	Z	-3.043	-3.043	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	1.757	1.757	0	%100
96	MP1B	Z	-3.043	-3.043	0	%100
97	MP2B	X	1.944	1.944	0	%100
98	MP2B	Z	-3.367	-3.367	0	%100
99	MP3B	X	1.757	1.757	0	%100
100	MP3B	Z	-3.043	-3.043	0	%100
101	MP4B	X	1.757	1.757	0	%100
102	MP4B	Z	-3.043	-3.043	0	%100
103	M101A	X	1.443	1.443	0	%100
104	M101A	Z	-2.498	-2.498	0	%100
105	M102A	X	1.511	1.511	0	%100
106	M102A	Z	-2.617	-2.617	0	%100
107	M116A	X	1.458	1.458	0	%100
108	M116A	Z	-2.525	-2.525	0	%100
109	M120A	X	1.458	1.458	0	%100
110	M120A	Z	-2.525	-2.525	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	1.985	1.985	0	%100
114	M132A	Z	-3.439	-3.439	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 54 : Structure Wi (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
115	M133A	X	1.985	1.985	0	%100
116	M133A	Z	-3.439	-3.439	0	%100
117	M134A	X	2.44	2.44	0	%100
118	M134A	Z	-4.226	-4.226	0	%100
119	M125B	X	1.511	1.511	0	%100
120	M125B	Z	-2.617	-2.617	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	3.013	3.013	0	%100
2	M100	Z	-1.739	-1.739	0	%100
3	M101	X	.888	.888	0	%100
4	M101	Z	-.513	-.513	0	%100
5	M102	X	.888	.888	0	%100
6	M102	Z	-.513	-.513	0	%100
7	M103	X	1.211	1.211	0	%100
8	M103	Z	-.699	-.699	0	%100
9	M106	X	3.567	3.567	0	%100
10	M106	Z	-2.059	-2.059	0	%100
11	M107	X	.892	.892	0	%100
12	M107	Z	-.515	-.515	0	%100
13	M111	X	3.575	3.575	0	%100
14	M111	Z	-2.064	-2.064	0	%100
15	M112	X	4.838	4.838	0	%100
16	M112	Z	-2.793	-2.793	0	%100
17	M114	X	5.05	5.05	0	%100
18	M114	Z	-2.915	-2.915	0	%100
19	M116	X	3.575	3.575	0	%100
20	M116	Z	-2.064	-2.064	0	%100
21	M117	X	1.21	1.21	0	%100
22	M117	Z	-.698	-.698	0	%100
23	M119	X	1.262	1.262	0	%100
24	M119	Z	-.729	-.729	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	3.553	3.553	0	%100
28	M125	Z	-2.052	-2.052	0	%100
29	M126	X	3.553	3.553	0	%100
30	M126	Z	-2.052	-2.052	0	%100
31	M127	X	4.845	4.845	0	%100
32	M127	Z	-2.797	-2.797	0	%100
33	M130	X	.892	.892	0	%100
34	M130	Z	-.515	-.515	0	%100
35	M131	X	.892	.892	0	%100
36	M131	Z	-.515	-.515	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	1.21	1.21	0	%100
40	M136	Z	-.698	-.698	0	%100
41	M138	X	1.262	1.262	0	%100
42	M138	Z	-.729	-.729	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	1.21	1.21	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
46	M141	Z	-.698	-.698	0	%100
47	M143	X	1.262	1.262	0	%100
48	M143	Z	-.729	-.729	0	%100
49	M148	X	3.013	3.013	0	%100
50	M148	Z	-1.739	-1.739	0	%100
51	M149	X	.888	.888	0	%100
52	M149	Z	-.513	-.513	0	%100
53	M150	X	.888	.888	0	%100
54	M150	Z	-.513	-.513	0	%100
55	M151	X	1.211	1.211	0	%100
56	M151	Z	-.699	-.699	0	%100
57	M154	X	.892	.892	0	%100
58	M154	Z	-.515	-.515	0	%100
59	M155	X	3.567	3.567	0	%100
60	M155	Z	-2.059	-2.059	0	%100
61	M159	X	3.575	3.575	0	%100
62	M159	Z	-2.064	-2.064	0	%100
63	M160	X	1.21	1.21	0	%100
64	M160	Z	-.698	-.698	0	%100
65	M162	X	1.262	1.262	0	%100
66	M162	Z	-.729	-.729	0	%100
67	M164	X	3.575	3.575	0	%100
68	M164	Z	-2.064	-2.064	0	%100
69	M165	X	4.838	4.838	0	%100
70	M165	Z	-2.793	-2.793	0	%100
71	M167	X	5.05	5.05	0	%100
72	M167	Z	-2.915	-2.915	0	%100
73	M172	X	.943	.943	0	%100
74	M172	Z	-.544	-.544	0	%100
75	MP1A	X	3.043	3.043	0	%100
76	MP1A	Z	-1.757	-1.757	0	%100
77	MP2A	X	3.367	3.367	0	%100
78	MP2A	Z	-1.944	-1.944	0	%100
79	MP3A	X	3.043	3.043	0	%100
80	MP3A	Z	-1.757	-1.757	0	%100
81	MP4A	X	3.043	3.043	0	%100
82	MP4A	Z	-1.757	-1.757	0	%100
83	M181	X	3.772	3.772	0	%100
84	M181	Z	-2.178	-2.178	0	%100
85	MP1C	X	3.043	3.043	0	%100
86	MP1C	Z	-1.757	-1.757	0	%100
87	MP2C	X	3.367	3.367	0	%100
88	MP2C	Z	-1.944	-1.944	0	%100
89	MP3C	X	3.043	3.043	0	%100
90	MP3C	Z	-1.757	-1.757	0	%100
91	MP4C	X	3.043	3.043	0	%100
92	MP4C	Z	-1.757	-1.757	0	%100
93	M190	X	.943	.943	0	%100
94	M190	Z	-.544	-.544	0	%100
95	MP1B	X	3.043	3.043	0	%100
96	MP1B	Z	-1.757	-1.757	0	%100
97	MP2B	X	3.367	3.367	0	%100
98	MP2B	Z	-1.944	-1.944	0	%100
99	MP3B	X	3.043	3.043	0	%100
100	MP3B	Z	-1.757	-1.757	0	%100
101	MP4B	X	3.043	3.043	0	%100
102	MP4B	Z	-1.757	-1.757	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 55 : Structure Wi (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
103	M101A	X	2.498	2.498	0	%100
104	M101A	Z	-1.443	-1.443	0	%100
105	M102A	X	.872	.872	0	%100
106	M102A	Z	-.504	-.504	0	%100
107	M116A	X	.842	.842	0	%100
108	M116A	Z	-.486	-.486	0	%100
109	M120A	X	3.367	3.367	0	%100
110	M120A	Z	-1.944	-1.944	0	%100
111	M125A	X	.842	.842	0	%100
112	M125A	Z	-.486	-.486	0	%100
113	M132A	X	3.964	3.964	0	%100
114	M132A	Z	-2.288	-2.288	0	%100
115	M133A	X	3.177	3.177	0	%100
116	M133A	Z	-1.834	-1.834	0	%100
117	M134A	X	3.964	3.964	0	%100
118	M134A	Z	-2.288	-2.288	0	%100
119	M125B	X	3.49	3.49	0	%100
120	M125B	Z	-2.015	-2.015	0	%100
121	M130A	X	.872	.872	0	%100
122	M130A	Z	-.504	-.504	0	%100

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	4.638	4.638	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	0	0	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	0	0	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	0	0	0	%100
9	M106	X	3.089	3.089	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	3.089	3.089	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	5.504	5.504	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	4.19	4.19	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	4.373	4.373	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	5.504	5.504	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	4.19	4.19	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	4.373	4.373	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	1.16	1.16	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	3.077	3.077	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	3.077	3.077	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	4.196	4.196	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	3.089	3.089	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F....]	Start Location[ft.%]	End Location[ft.%]
34	M130	Z	0	0	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	0	0	0	%100
37	M135	X	1.376	1.376	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	4.19	4.19	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	4.373	4.373	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	1.376	1.376	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	0	0	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	0	0	0	%100
49	M148	X	1.16	1.16	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	3.077	3.077	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	3.077	3.077	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	4.196	4.196	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	0	0	0	%100
59	M155	X	3.089	3.089	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	1.376	1.376	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	0	0	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	0	0	0	%100
67	M164	X	1.376	1.376	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	4.19	4.19	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	4.373	4.373	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	0	0	0	%100
75	MP1A	X	3.514	3.514	0	%100
76	MP1A	Z	0	0	0	%100
77	MP2A	X	3.888	3.888	0	%100
78	MP2A	Z	0	0	0	%100
79	MP3A	X	3.514	3.514	0	%100
80	MP3A	Z	0	0	0	%100
81	MP4A	X	3.514	3.514	0	%100
82	MP4A	Z	0	0	0	%100
83	M181	X	3.267	3.267	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	3.514	3.514	0	%100
86	MP1C	Z	0	0	0	%100
87	MP2C	X	3.888	3.888	0	%100
88	MP2C	Z	0	0	0	%100
89	MP3C	X	3.514	3.514	0	%100
90	MP3C	Z	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 56 : Structure Wi (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
91	MP4C	X	3.514	3.514	0	%100
92	MP4C	Z	0	0	0	%100
93	M190	X	3.267	3.267	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	3.514	3.514	0	%100
96	MP1B	Z	0	0	0	%100
97	MP2B	X	3.888	3.888	0	%100
98	MP2B	Z	0	0	0	%100
99	MP3B	X	3.514	3.514	0	%100
100	MP3B	Z	0	0	0	%100
101	MP4B	X	3.514	3.514	0	%100
102	MP4B	Z	0	0	0	%100
103	M101A	X	2.885	2.885	0	%100
104	M101A	Z	0	0	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	0	0	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	0	0	0	%100
109	M120A	X	2.916	2.916	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	2.916	2.916	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	4.88	4.88	0	%100
114	M132A	Z	0	0	0	%100
115	M133A	X	3.971	3.971	0	%100
116	M133A	Z	0	0	0	%100
117	M134A	X	3.971	3.971	0	%100
118	M134A	Z	0	0	0	%100
119	M125B	X	3.022	3.022	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	3.022	3.022	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	3.013	3.013	0	%100
2	M100	Z	1.739	1.739	0	%100
3	M101	X	.888	.888	0	%100
4	M101	Z	.513	.513	0	%100
5	M102	X	.888	.888	0	%100
6	M102	Z	.513	.513	0	%100
7	M103	X	1.211	1.211	0	%100
8	M103	Z	.699	.699	0	%100
9	M106	X	.892	.892	0	%100
10	M106	Z	.515	.515	0	%100
11	M107	X	3.567	3.567	0	%100
12	M107	Z	2.059	2.059	0	%100
13	M111	X	3.575	3.575	0	%100
14	M111	Z	2.064	2.064	0	%100
15	M112	X	1.21	1.21	0	%100
16	M112	Z	.698	.698	0	%100
17	M114	X	1.262	1.262	0	%100
18	M114	Z	.729	.729	0	%100
19	M116	X	3.575	3.575	0	%100
20	M116	Z	2.064	2.064	0	%100
21	M117	X	4.838	4.838	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
22	M117	Z	2.793	2.793	0	%100
23	M119	X	5.05	5.05	0	%100
24	M119	Z	2.915	2.915	0	%100
25	M124	X	3.013	3.013	0	%100
26	M124	Z	1.739	1.739	0	%100
27	M125	X	.888	.888	0	%100
28	M125	Z	.513	.513	0	%100
29	M126	X	.888	.888	0	%100
30	M126	Z	.513	.513	0	%100
31	M127	X	1.211	1.211	0	%100
32	M127	Z	.699	.699	0	%100
33	M130	X	3.567	3.567	0	%100
34	M130	Z	2.059	2.059	0	%100
35	M131	X	.892	.892	0	%100
36	M131	Z	.515	.515	0	%100
37	M135	X	3.575	3.575	0	%100
38	M135	Z	2.064	2.064	0	%100
39	M136	X	4.838	4.838	0	%100
40	M136	Z	2.793	2.793	0	%100
41	M138	X	5.05	5.05	0	%100
42	M138	Z	2.915	2.915	0	%100
43	M140	X	3.575	3.575	0	%100
44	M140	Z	2.064	2.064	0	%100
45	M141	X	1.21	1.21	0	%100
46	M141	Z	.698	.698	0	%100
47	M143	X	1.262	1.262	0	%100
48	M143	Z	.729	.729	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	3.553	3.553	0	%100
52	M149	Z	2.052	2.052	0	%100
53	M150	X	3.553	3.553	0	%100
54	M150	Z	2.052	2.052	0	%100
55	M151	X	4.845	4.845	0	%100
56	M151	Z	2.797	2.797	0	%100
57	M154	X	.892	.892	0	%100
58	M154	Z	.515	.515	0	%100
59	M155	X	.892	.892	0	%100
60	M155	Z	.515	.515	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	1.21	1.21	0	%100
64	M160	Z	.698	.698	0	%100
65	M162	X	1.262	1.262	0	%100
66	M162	Z	.729	.729	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	1.21	1.21	0	%100
70	M165	Z	.698	.698	0	%100
71	M167	X	1.262	1.262	0	%100
72	M167	Z	.729	.729	0	%100
73	M172	X	.943	.943	0	%100
74	M172	Z	.544	.544	0	%100
75	MP1A	X	3.043	3.043	0	%100
76	MP1A	Z	1.757	1.757	0	%100
77	MP2A	X	3.367	3.367	0	%100
78	MP2A	Z	1.944	1.944	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 57 : Structure Wi (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
79	MP3A	X	3.043	3.043	0	%100
80	MP3A	Z	1.757	1.757	0	%100
81	MP4A	X	3.043	3.043	0	%100
82	MP4A	Z	1.757	1.757	0	%100
83	M181	X	.943	.943	0	%100
84	M181	Z	.544	.544	0	%100
85	MP1C	X	3.043	3.043	0	%100
86	MP1C	Z	1.757	1.757	0	%100
87	MP2C	X	3.367	3.367	0	%100
88	MP2C	Z	1.944	1.944	0	%100
89	MP3C	X	3.043	3.043	0	%100
90	MP3C	Z	1.757	1.757	0	%100
91	MP4C	X	3.043	3.043	0	%100
92	MP4C	Z	1.757	1.757	0	%100
93	M190	X	3.772	3.772	0	%100
94	M190	Z	2.178	2.178	0	%100
95	MP1B	X	3.043	3.043	0	%100
96	MP1B	Z	1.757	1.757	0	%100
97	MP2B	X	3.367	3.367	0	%100
98	MP2B	Z	1.944	1.944	0	%100
99	MP3B	X	3.043	3.043	0	%100
100	MP3B	Z	1.757	1.757	0	%100
101	MP4B	X	3.043	3.043	0	%100
102	MP4B	Z	1.757	1.757	0	%100
103	M101A	X	2.498	2.498	0	%100
104	M101A	Z	1.443	1.443	0	%100
105	M102A	X	.872	.872	0	%100
106	M102A	Z	.504	.504	0	%100
107	M116A	X	.842	.842	0	%100
108	M116A	Z	.486	.486	0	%100
109	M120A	X	.842	.842	0	%100
110	M120A	Z	.486	.486	0	%100
111	M125A	X	3.367	3.367	0	%100
112	M125A	Z	1.944	1.944	0	%100
113	M132A	X	3.964	3.964	0	%100
114	M132A	Z	2.288	2.288	0	%100
115	M133A	X	3.964	3.964	0	%100
116	M133A	Z	2.288	2.288	0	%100
117	M134A	X	3.177	3.177	0	%100
118	M134A	Z	1.834	1.834	0	%100
119	M125B	X	.872	.872	0	%100
120	M125B	Z	.504	.504	0	%100
121	M130A	X	3.49	3.49	0	%100
122	M130A	Z	2.015	2.015	0	%100

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	.58	.58	0	%100
2	M100	Z	1.004	1.004	0	%100
3	M101	X	1.539	1.539	0	%100
4	M101	Z	2.665	2.665	0	%100
5	M102	X	1.539	1.539	0	%100
6	M102	Z	2.665	2.665	0	%100
7	M103	X	2.098	2.098	0	%100
8	M103	Z	3.634	3.634	0	%100
9	M106	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
10	M106	Z	0	0	0	%100
11	M107	X	1.544	1.544	0	%100
12	M107	Z	2.675	2.675	0	%100
13	M111	X	.688	.688	0	%100
14	M111	Z	1.192	1.192	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	.688	.688	0	%100
20	M116	Z	1.192	1.192	0	%100
21	M117	X	2.095	2.095	0	%100
22	M117	Z	3.629	3.629	0	%100
23	M119	X	2.186	2.186	0	%100
24	M119	Z	3.787	3.787	0	%100
25	M124	X	2.319	2.319	0	%100
26	M124	Z	4.017	4.017	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	1.544	1.544	0	%100
34	M130	Z	2.675	2.675	0	%100
35	M131	X	1.544	1.544	0	%100
36	M131	Z	2.675	2.675	0	%100
37	M135	X	2.752	2.752	0	%100
38	M135	Z	4.766	4.766	0	%100
39	M136	X	2.095	2.095	0	%100
40	M136	Z	3.629	3.629	0	%100
41	M138	X	2.186	2.186	0	%100
42	M138	Z	3.787	3.787	0	%100
43	M140	X	2.752	2.752	0	%100
44	M140	Z	4.766	4.766	0	%100
45	M141	X	2.095	2.095	0	%100
46	M141	Z	3.629	3.629	0	%100
47	M143	X	2.186	2.186	0	%100
48	M143	Z	3.787	3.787	0	%100
49	M148	X	.58	.58	0	%100
50	M148	Z	1.004	1.004	0	%100
51	M149	X	1.539	1.539	0	%100
52	M149	Z	2.665	2.665	0	%100
53	M150	X	1.539	1.539	0	%100
54	M150	Z	2.665	2.665	0	%100
55	M151	X	2.098	2.098	0	%100
56	M151	Z	3.634	3.634	0	%100
57	M154	X	1.544	1.544	0	%100
58	M154	Z	2.675	2.675	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	.688	.688	0	%100
62	M159	Z	1.192	1.192	0	%100
63	M160	X	2.095	2.095	0	%100
64	M160	Z	3.629	3.629	0	%100
65	M162	X	2.186	2.186	0	%100
66	M162	Z	3.787	3.787	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 58 : Structure Wi (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
67	M164	X	.688	.688	0	%100
68	M164	Z	1.192	1.192	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	1.633	1.633	0	%100
74	M172	Z	2.829	2.829	0	%100
75	MP1A	X	1.757	1.757	0	%100
76	MP1A	Z	3.043	3.043	0	%100
77	MP2A	X	1.944	1.944	0	%100
78	MP2A	Z	3.367	3.367	0	%100
79	MP3A	X	1.757	1.757	0	%100
80	MP3A	Z	3.043	3.043	0	%100
81	MP4A	X	1.757	1.757	0	%100
82	MP4A	Z	3.043	3.043	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	1.757	1.757	0	%100
86	MP1C	Z	3.043	3.043	0	%100
87	MP2C	X	1.944	1.944	0	%100
88	MP2C	Z	3.367	3.367	0	%100
89	MP3C	X	1.757	1.757	0	%100
90	MP3C	Z	3.043	3.043	0	%100
91	MP4C	X	1.757	1.757	0	%100
92	MP4C	Z	3.043	3.043	0	%100
93	M190	X	1.633	1.633	0	%100
94	M190	Z	2.829	2.829	0	%100
95	MP1B	X	1.757	1.757	0	%100
96	MP1B	Z	3.043	3.043	0	%100
97	MP2B	X	1.944	1.944	0	%100
98	MP2B	Z	3.367	3.367	0	%100
99	MP3B	X	1.757	1.757	0	%100
100	MP3B	Z	3.043	3.043	0	%100
101	MP4B	X	1.757	1.757	0	%100
102	MP4B	Z	3.043	3.043	0	%100
103	M101A	X	1.443	1.443	0	%100
104	M101A	Z	2.498	2.498	0	%100
105	M102A	X	1.511	1.511	0	%100
106	M102A	Z	2.617	2.617	0	%100
107	M116A	X	1.458	1.458	0	%100
108	M116A	Z	2.525	2.525	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	1.458	1.458	0	%100
112	M125A	Z	2.525	2.525	0	%100
113	M132A	X	1.985	1.985	0	%100
114	M132A	Z	3.439	3.439	0	%100
115	M133A	X	2.44	2.44	0	%100
116	M133A	Z	4.226	4.226	0	%100
117	M134A	X	1.985	1.985	0	%100
118	M134A	Z	3.439	3.439	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	1.511	1.511	0	%100
122	M130A	Z	2.617	2.617	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	0	0	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	4.103	4.103	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	4.103	4.103	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	5.595	5.595	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	1.03	1.03	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	1.03	1.03	0	%100
13	M111	X	0	0	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	1.397	1.397	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	1.458	1.458	0	%100
19	M116	X	0	0	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	1.397	1.397	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	1.458	1.458	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	3.479	3.479	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	1.026	1.026	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	1.026	1.026	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	1.399	1.399	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	1.03	1.03	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	4.118	4.118	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	4.128	4.128	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	1.397	1.397	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	1.458	1.458	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	4.128	4.128	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	5.587	5.587	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	5.831	5.831	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	3.479	3.479	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	1.026	1.026	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	1.026	1.026	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	1.399	1.399	0	%100
57	M154	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude(lb/ft....	End Magnitude(lb/ft.F...	Start Location(ft.%)	End Location(ft.%)
58	M154	Z	4.118	4.118	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	1.03	1.03	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	4.128	4.128	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	5.587	5.587	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	5.831	5.831	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	4.128	4.128	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	1.397	1.397	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	1.458	1.458	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	4.356	4.356	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	3.514	3.514	0	%100
77	MP2A	X	0	0	0	%100
78	MP2A	Z	3.888	3.888	0	%100
79	MP3A	X	0	0	0	%100
80	MP3A	Z	3.514	3.514	0	%100
81	MP4A	X	0	0	0	%100
82	MP4A	Z	3.514	3.514	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	1.089	1.089	0	%100
85	MP1C	X	0	0	0	%100
86	MP1C	Z	3.514	3.514	0	%100
87	MP2C	X	0	0	0	%100
88	MP2C	Z	3.888	3.888	0	%100
89	MP3C	X	0	0	0	%100
90	MP3C	Z	3.514	3.514	0	%100
91	MP4C	X	0	0	0	%100
92	MP4C	Z	3.514	3.514	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	1.089	1.089	0	%100
95	MP1B	X	0	0	0	%100
96	MP1B	Z	3.514	3.514	0	%100
97	MP2B	X	0	0	0	%100
98	MP2B	Z	3.888	3.888	0	%100
99	MP3B	X	0	0	0	%100
100	MP3B	Z	3.514	3.514	0	%100
101	MP4B	X	0	0	0	%100
102	MP4B	Z	3.514	3.514	0	%100
103	M101A	X	0	0	0	%100
104	M101A	Z	2.885	2.885	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	4.029	4.029	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	3.888	3.888	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	.972	.972	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	.972	.972	0	%100
113	M132A	X	0	0	0	%100
114	M132A	Z	3.668	3.668	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 59 : Structure Wi (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
115	M133A	X	0	0	0	%100
116	M133A	Z	4.577	4.577	0	%100
117	M134A	X	0	0	0	%100
118	M134A	Z	4.577	4.577	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	1.007	1.007	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	1.007	1.007	0	%100

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-0.58	-0.58	0	%100
2	M100	Z	1.004	1.004	0	%100
3	M101	X	-1.539	-1.539	0	%100
4	M101	Z	2.665	2.665	0	%100
5	M102	X	-1.539	-1.539	0	%100
6	M102	Z	2.665	2.665	0	%100
7	M103	X	-2.098	-2.098	0	%100
8	M103	Z	3.634	3.634	0	%100
9	M106	X	-1.544	-1.544	0	%100
10	M106	Z	2.675	2.675	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	-0.688	-0.688	0	%100
14	M111	Z	1.192	1.192	0	%100
15	M112	X	-2.095	-2.095	0	%100
16	M112	Z	3.629	3.629	0	%100
17	M114	X	-2.186	-2.186	0	%100
18	M114	Z	3.787	3.787	0	%100
19	M116	X	-0.688	-0.688	0	%100
20	M116	Z	1.192	1.192	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	-0.58	-0.58	0	%100
26	M124	Z	1.004	1.004	0	%100
27	M125	X	-1.539	-1.539	0	%100
28	M125	Z	2.665	2.665	0	%100
29	M126	X	-1.539	-1.539	0	%100
30	M126	Z	2.665	2.665	0	%100
31	M127	X	-2.098	-2.098	0	%100
32	M127	Z	3.634	3.634	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	-1.544	-1.544	0	%100
36	M131	Z	2.675	2.675	0	%100
37	M135	X	-0.688	-0.688	0	%100
38	M135	Z	1.192	1.192	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	-0.688	-0.688	0	%100
44	M140	Z	1.192	1.192	0	%100
45	M141	X	-2.095	-2.095	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F....]	Start Location[ft.%]	End Location[ft.%]
46	M141	Z	3.629	3.629	0	%100
47	M143	X	-2.186	-2.186	0	%100
48	M143	Z	3.787	3.787	0	%100
49	M148	X	-2.319	-2.319	0	%100
50	M148	Z	4.017	4.017	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	-1.544	-1.544	0	%100
58	M154	Z	2.675	2.675	0	%100
59	M155	X	-1.544	-1.544	0	%100
60	M155	Z	2.675	2.675	0	%100
61	M159	X	-2.752	-2.752	0	%100
62	M159	Z	4.766	4.766	0	%100
63	M160	X	-2.095	-2.095	0	%100
64	M160	Z	3.629	3.629	0	%100
65	M162	X	-2.186	-2.186	0	%100
66	M162	Z	3.787	3.787	0	%100
67	M164	X	-2.752	-2.752	0	%100
68	M164	Z	4.766	4.766	0	%100
69	M165	X	-2.095	-2.095	0	%100
70	M165	Z	3.629	3.629	0	%100
71	M167	X	-2.186	-2.186	0	%100
72	M167	Z	3.787	3.787	0	%100
73	M172	X	-1.633	-1.633	0	%100
74	M172	Z	2.829	2.829	0	%100
75	MP1A	X	-1.757	-1.757	0	%100
76	MP1A	Z	3.043	3.043	0	%100
77	MP2A	X	-1.944	-1.944	0	%100
78	MP2A	Z	3.367	3.367	0	%100
79	MP3A	X	-1.757	-1.757	0	%100
80	MP3A	Z	3.043	3.043	0	%100
81	MP4A	X	-1.757	-1.757	0	%100
82	MP4A	Z	3.043	3.043	0	%100
83	M181	X	-1.633	-1.633	0	%100
84	M181	Z	2.829	2.829	0	%100
85	MP1C	X	-1.757	-1.757	0	%100
86	MP1C	Z	3.043	3.043	0	%100
87	MP2C	X	-1.944	-1.944	0	%100
88	MP2C	Z	3.367	3.367	0	%100
89	MP3C	X	-1.757	-1.757	0	%100
90	MP3C	Z	3.043	3.043	0	%100
91	MP4C	X	-1.757	-1.757	0	%100
92	MP4C	Z	3.043	3.043	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	-1.757	-1.757	0	%100
96	MP1B	Z	3.043	3.043	0	%100
97	MP2B	X	-1.944	-1.944	0	%100
98	MP2B	Z	3.367	3.367	0	%100
99	MP3B	X	-1.757	-1.757	0	%100
100	MP3B	Z	3.043	3.043	0	%100
101	MP4B	X	-1.757	-1.757	0	%100
102	MP4B	Z	3.043	3.043	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 60 : Structure Wi (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
103	M101A	X	-1.443	-1.443	0	%100
104	M101A	Z	2.498	2.498	0	%100
105	M102A	X	-1.511	-1.511	0	%100
106	M102A	Z	2.617	2.617	0	%100
107	M116A	X	-1.458	-1.458	0	%100
108	M116A	Z	2.525	2.525	0	%100
109	M120A	X	-1.458	-1.458	0	%100
110	M120A	Z	2.525	2.525	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	-1.985	-1.985	0	%100
114	M132A	Z	3.439	3.439	0	%100
115	M133A	X	-1.985	-1.985	0	%100
116	M133A	Z	3.439	3.439	0	%100
117	M134A	X	-2.44	-2.44	0	%100
118	M134A	Z	4.226	4.226	0	%100
119	M125B	X	-1.511	-1.511	0	%100
120	M125B	Z	2.617	2.617	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-3.013	-3.013	0	%100
2	M100	Z	1.739	1.739	0	%100
3	M101	X	-.888	-.888	0	%100
4	M101	Z	.513	.513	0	%100
5	M102	X	-.888	-.888	0	%100
6	M102	Z	.513	.513	0	%100
7	M103	X	-1.211	-1.211	0	%100
8	M103	Z	.699	.699	0	%100
9	M106	X	-3.567	-3.567	0	%100
10	M106	Z	2.059	2.059	0	%100
11	M107	X	-.892	-.892	0	%100
12	M107	Z	.515	.515	0	%100
13	M111	X	-3.575	-3.575	0	%100
14	M111	Z	2.064	2.064	0	%100
15	M112	X	-4.838	-4.838	0	%100
16	M112	Z	2.793	2.793	0	%100
17	M114	X	-5.05	-5.05	0	%100
18	M114	Z	2.915	2.915	0	%100
19	M116	X	-3.575	-3.575	0	%100
20	M116	Z	2.064	2.064	0	%100
21	M117	X	-1.21	-1.21	0	%100
22	M117	Z	.698	.698	0	%100
23	M119	X	-1.262	-1.262	0	%100
24	M119	Z	.729	.729	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	-3.553	-3.553	0	%100
28	M125	Z	2.052	2.052	0	%100
29	M126	X	-3.553	-3.553	0	%100
30	M126	Z	2.052	2.052	0	%100
31	M127	X	-4.845	-4.845	0	%100
32	M127	Z	2.797	2.797	0	%100
33	M130	X	-.892	-.892	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft...]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
34	M130	Z	.515	.515	0	%100
35	M131	X	-.892	-.892	0	%100
36	M131	Z	.515	.515	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	-1.21	-1.21	0	%100
40	M136	Z	.698	.698	0	%100
41	M138	X	-1.262	-1.262	0	%100
42	M138	Z	.729	.729	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	-1.21	-1.21	0	%100
46	M141	Z	.698	.698	0	%100
47	M143	X	-1.262	-1.262	0	%100
48	M143	Z	.729	.729	0	%100
49	M148	X	-3.013	-3.013	0	%100
50	M148	Z	1.739	1.739	0	%100
51	M149	X	-.888	-.888	0	%100
52	M149	Z	.513	.513	0	%100
53	M150	X	-.888	-.888	0	%100
54	M150	Z	.513	.513	0	%100
55	M151	X	-1.211	-1.211	0	%100
56	M151	Z	.699	.699	0	%100
57	M154	X	-.892	-.892	0	%100
58	M154	Z	.515	.515	0	%100
59	M155	X	-3.567	-3.567	0	%100
60	M155	Z	2.059	2.059	0	%100
61	M159	X	-3.575	-3.575	0	%100
62	M159	Z	2.064	2.064	0	%100
63	M160	X	-1.21	-1.21	0	%100
64	M160	Z	.698	.698	0	%100
65	M162	X	-1.262	-1.262	0	%100
66	M162	Z	.729	.729	0	%100
67	M164	X	-3.575	-3.575	0	%100
68	M164	Z	2.064	2.064	0	%100
69	M165	X	-4.838	-4.838	0	%100
70	M165	Z	2.793	2.793	0	%100
71	M167	X	-5.05	-5.05	0	%100
72	M167	Z	2.915	2.915	0	%100
73	M172	X	-.943	-.943	0	%100
74	M172	Z	.544	.544	0	%100
75	MP1A	X	-3.043	-3.043	0	%100
76	MP1A	Z	1.757	1.757	0	%100
77	MP2A	X	-3.367	-3.367	0	%100
78	MP2A	Z	1.944	1.944	0	%100
79	MP3A	X	-3.043	-3.043	0	%100
80	MP3A	Z	1.757	1.757	0	%100
81	MP4A	X	-3.043	-3.043	0	%100
82	MP4A	Z	1.757	1.757	0	%100
83	M181	X	-3.772	-3.772	0	%100
84	M181	Z	2.178	2.178	0	%100
85	MP1C	X	-3.043	-3.043	0	%100
86	MP1C	Z	1.757	1.757	0	%100
87	MP2C	X	-3.367	-3.367	0	%100
88	MP2C	Z	1.944	1.944	0	%100
89	MP3C	X	-3.043	-3.043	0	%100
90	MP3C	Z	1.757	1.757	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 61 : Structure Wi (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
91	MP4C	X	-3.043	-3.043	0	%100
92	MP4C	Z	1.757	1.757	0	%100
93	M190	X	-.943	-.943	0	%100
94	M190	Z	.544	.544	0	%100
95	MP1B	X	-3.043	-3.043	0	%100
96	MP1B	Z	1.757	1.757	0	%100
97	MP2B	X	-3.367	-3.367	0	%100
98	MP2B	Z	1.944	1.944	0	%100
99	MP3B	X	-3.043	-3.043	0	%100
100	MP3B	Z	1.757	1.757	0	%100
101	MP4B	X	-3.043	-3.043	0	%100
102	MP4B	Z	1.757	1.757	0	%100
103	M101A	X	-2.498	-2.498	0	%100
104	M101A	Z	1.443	1.443	0	%100
105	M102A	X	-.872	-.872	0	%100
106	M102A	Z	.504	.504	0	%100
107	M116A	X	-.842	-.842	0	%100
108	M116A	Z	.486	.486	0	%100
109	M120A	X	-3.367	-3.367	0	%100
110	M120A	Z	1.944	1.944	0	%100
111	M125A	X	-.842	-.842	0	%100
112	M125A	Z	.486	.486	0	%100
113	M132A	X	-3.964	-3.964	0	%100
114	M132A	Z	2.288	2.288	0	%100
115	M133A	X	-3.177	-3.177	0	%100
116	M133A	Z	1.834	1.834	0	%100
117	M134A	X	-3.964	-3.964	0	%100
118	M134A	Z	2.288	2.288	0	%100
119	M125B	X	-3.49	-3.49	0	%100
120	M125B	Z	2.015	2.015	0	%100
121	M130A	X	-.872	-.872	0	%100
122	M130A	Z	.504	.504	0	%100

Member Distributed Loads (BLC 62 : Structure Wi (270 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-4.638	-4.638	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	0	0	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	0	0	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	0	0	0	%100
9	M106	X	-3.089	-3.089	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	-3.089	-3.089	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	-5.504	-5.504	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	-4.19	-4.19	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	-4.373	-4.373	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	-5.504	-5.504	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	-4.19	-4.19	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 62 : Structure Wi (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
22	M117	Z	0	0	0	%100
23	M119	X	-4.373	-4.373	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	-1.16	-1.16	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	-3.077	-3.077	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	-3.077	-3.077	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	-4.196	-4.196	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	-3.089	-3.089	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	0	0	0	%100
37	M135	X	-1.376	-1.376	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	-4.19	-4.19	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	-4.373	-4.373	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	-1.376	-1.376	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	0	0	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	0	0	0	%100
49	M148	X	-1.16	-1.16	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	-3.077	-3.077	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	-3.077	-3.077	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	-4.196	-4.196	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	0	0	0	%100
59	M155	X	-3.089	-3.089	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	-1.376	-1.376	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	0	0	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	0	0	0	%100
67	M164	X	-1.376	-1.376	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	-4.19	-4.19	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	-4.373	-4.373	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	0	0	0	%100
75	MP1A	X	-3.514	-3.514	0	%100
76	MP1A	Z	0	0	0	%100
77	MP2A	X	-3.888	-3.888	0	%100
78	MP2A	Z	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 62 : Structure Wi (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
79	MP3A	X	-3.514	-3.514	0	%100
80	MP3A	Z	0	0	0	%100
81	MP4A	X	-3.514	-3.514	0	%100
82	MP4A	Z	0	0	0	%100
83	M181	X	-3.267	-3.267	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	-3.514	-3.514	0	%100
86	MP1C	Z	0	0	0	%100
87	MP2C	X	-3.888	-3.888	0	%100
88	MP2C	Z	0	0	0	%100
89	MP3C	X	-3.514	-3.514	0	%100
90	MP3C	Z	0	0	0	%100
91	MP4C	X	-3.514	-3.514	0	%100
92	MP4C	Z	0	0	0	%100
93	M190	X	-3.267	-3.267	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	-3.514	-3.514	0	%100
96	MP1B	Z	0	0	0	%100
97	MP2B	X	-3.888	-3.888	0	%100
98	MP2B	Z	0	0	0	%100
99	MP3B	X	-3.514	-3.514	0	%100
100	MP3B	Z	0	0	0	%100
101	MP4B	X	-3.514	-3.514	0	%100
102	MP4B	Z	0	0	0	%100
103	M101A	X	-2.885	-2.885	0	%100
104	M101A	Z	0	0	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	0	0	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	0	0	0	%100
109	M120A	X	-2.916	-2.916	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	-2.916	-2.916	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	-4.88	-4.88	0	%100
114	M132A	Z	0	0	0	%100
115	M133A	X	-3.971	-3.971	0	%100
116	M133A	Z	0	0	0	%100
117	M134A	X	-3.971	-3.971	0	%100
118	M134A	Z	0	0	0	%100
119	M125B	X	-3.022	-3.022	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	-3.022	-3.022	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-3.013	-3.013	0	%100
2	M100	Z	-1.739	-1.739	0	%100
3	M101	X	-.888	-.888	0	%100
4	M101	Z	-.513	-.513	0	%100
5	M102	X	-.888	-.888	0	%100
6	M102	Z	-.513	-.513	0	%100
7	M103	X	-1.211	-1.211	0	%100
8	M103	Z	-.699	-.699	0	%100
9	M106	X	-.892	-.892	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft...	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
10	M106	Z	- .515	- .515	0	%100
11	M107	X	-3.567	-3.567	0	%100
12	M107	Z	-2.059	-2.059	0	%100
13	M111	X	-3.575	-3.575	0	%100
14	M111	Z	-2.064	-2.064	0	%100
15	M112	X	-1.21	-1.21	0	%100
16	M112	Z	- .698	- .698	0	%100
17	M114	X	-1.262	-1.262	0	%100
18	M114	Z	- .729	- .729	0	%100
19	M116	X	-3.575	-3.575	0	%100
20	M116	Z	-2.064	-2.064	0	%100
21	M117	X	-4.838	-4.838	0	%100
22	M117	Z	-2.793	-2.793	0	%100
23	M119	X	-5.05	-5.05	0	%100
24	M119	Z	-2.915	-2.915	0	%100
25	M124	X	-3.013	-3.013	0	%100
26	M124	Z	-1.739	-1.739	0	%100
27	M125	X	- .888	- .888	0	%100
28	M125	Z	- .513	- .513	0	%100
29	M126	X	- .888	- .888	0	%100
30	M126	Z	- .513	- .513	0	%100
31	M127	X	-1.211	-1.211	0	%100
32	M127	Z	- .699	- .699	0	%100
33	M130	X	-3.567	-3.567	0	%100
34	M130	Z	-2.059	-2.059	0	%100
35	M131	X	- .892	- .892	0	%100
36	M131	Z	- .515	- .515	0	%100
37	M135	X	-3.575	-3.575	0	%100
38	M135	Z	-2.064	-2.064	0	%100
39	M136	X	-4.838	-4.838	0	%100
40	M136	Z	-2.793	-2.793	0	%100
41	M138	X	-5.05	-5.05	0	%100
42	M138	Z	-2.915	-2.915	0	%100
43	M140	X	-3.575	-3.575	0	%100
44	M140	Z	-2.064	-2.064	0	%100
45	M141	X	-1.21	-1.21	0	%100
46	M141	Z	- .698	- .698	0	%100
47	M143	X	-1.262	-1.262	0	%100
48	M143	Z	- .729	- .729	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	-3.553	-3.553	0	%100
52	M149	Z	-2.052	-2.052	0	%100
53	M150	X	-3.553	-3.553	0	%100
54	M150	Z	-2.052	-2.052	0	%100
55	M151	X	-4.845	-4.845	0	%100
56	M151	Z	-2.797	-2.797	0	%100
57	M154	X	- .892	- .892	0	%100
58	M154	Z	- .515	- .515	0	%100
59	M155	X	- .892	- .892	0	%100
60	M155	Z	- .515	- .515	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	-1.21	-1.21	0	%100
64	M160	Z	- .698	- .698	0	%100
65	M162	X	-1.262	-1.262	0	%100
66	M162	Z	- .729	- .729	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 63 : Structure Wi (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
67	M164	X	0	0	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	-1.21	-1.21	0	%100
70	M165	Z	-.698	-.698	0	%100
71	M167	X	-1.262	-1.262	0	%100
72	M167	Z	-.729	-.729	0	%100
73	M172	X	-.943	-.943	0	%100
74	M172	Z	-.544	-.544	0	%100
75	MP1A	X	-3.043	-3.043	0	%100
76	MP1A	Z	-1.757	-1.757	0	%100
77	MP2A	X	-3.367	-3.367	0	%100
78	MP2A	Z	-1.944	-1.944	0	%100
79	MP3A	X	-3.043	-3.043	0	%100
80	MP3A	Z	-1.757	-1.757	0	%100
81	MP4A	X	-3.043	-3.043	0	%100
82	MP4A	Z	-1.757	-1.757	0	%100
83	M181	X	-.943	-.943	0	%100
84	M181	Z	-.544	-.544	0	%100
85	MP1C	X	-3.043	-3.043	0	%100
86	MP1C	Z	-1.757	-1.757	0	%100
87	MP2C	X	-3.367	-3.367	0	%100
88	MP2C	Z	-1.944	-1.944	0	%100
89	MP3C	X	-3.043	-3.043	0	%100
90	MP3C	Z	-1.757	-1.757	0	%100
91	MP4C	X	-3.043	-3.043	0	%100
92	MP4C	Z	-1.757	-1.757	0	%100
93	M190	X	-3.772	-3.772	0	%100
94	M190	Z	-2.178	-2.178	0	%100
95	MP1B	X	-3.043	-3.043	0	%100
96	MP1B	Z	-1.757	-1.757	0	%100
97	MP2B	X	-3.367	-3.367	0	%100
98	MP2B	Z	-1.944	-1.944	0	%100
99	MP3B	X	-3.043	-3.043	0	%100
100	MP3B	Z	-1.757	-1.757	0	%100
101	MP4B	X	-3.043	-3.043	0	%100
102	MP4B	Z	-1.757	-1.757	0	%100
103	M101A	X	-2.498	-2.498	0	%100
104	M101A	Z	-1.443	-1.443	0	%100
105	M102A	X	-.872	-.872	0	%100
106	M102A	Z	-.504	-.504	0	%100
107	M116A	X	-.842	-.842	0	%100
108	M116A	Z	-.486	-.486	0	%100
109	M120A	X	-.842	-.842	0	%100
110	M120A	Z	-.486	-.486	0	%100
111	M125A	X	-3.367	-3.367	0	%100
112	M125A	Z	-1.944	-1.944	0	%100
113	M132A	X	-3.964	-3.964	0	%100
114	M132A	Z	-2.288	-2.288	0	%100
115	M133A	X	-3.964	-3.964	0	%100
116	M133A	Z	-2.288	-2.288	0	%100
117	M134A	X	-3.177	-3.177	0	%100
118	M134A	Z	-1.834	-1.834	0	%100
119	M125B	X	-.872	-.872	0	%100
120	M125B	Z	-.504	-.504	0	%100
121	M130A	X	-3.49	-3.49	0	%100
122	M130A	Z	-2.015	-2.015	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	- .58	- .58	0	%100
2	M100	Z	-1.004	-1.004	0	%100
3	M101	X	-1.539	-1.539	0	%100
4	M101	Z	-2.665	-2.665	0	%100
5	M102	X	-1.539	-1.539	0	%100
6	M102	Z	-2.665	-2.665	0	%100
7	M103	X	-2.098	-2.098	0	%100
8	M103	Z	-3.634	-3.634	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	-1.544	-1.544	0	%100
12	M107	Z	-2.675	-2.675	0	%100
13	M111	X	- .688	- .688	0	%100
14	M111	Z	-1.192	-1.192	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	- .688	- .688	0	%100
20	M116	Z	-1.192	-1.192	0	%100
21	M117	X	-2.095	-2.095	0	%100
22	M117	Z	-3.629	-3.629	0	%100
23	M119	X	-2.186	-2.186	0	%100
24	M119	Z	-3.787	-3.787	0	%100
25	M124	X	-2.319	-2.319	0	%100
26	M124	Z	-4.017	-4.017	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	-1.544	-1.544	0	%100
34	M130	Z	-2.675	-2.675	0	%100
35	M131	X	-1.544	-1.544	0	%100
36	M131	Z	-2.675	-2.675	0	%100
37	M135	X	-2.752	-2.752	0	%100
38	M135	Z	-4.766	-4.766	0	%100
39	M136	X	-2.095	-2.095	0	%100
40	M136	Z	-3.629	-3.629	0	%100
41	M138	X	-2.186	-2.186	0	%100
42	M138	Z	-3.787	-3.787	0	%100
43	M140	X	-2.752	-2.752	0	%100
44	M140	Z	-4.766	-4.766	0	%100
45	M141	X	-2.095	-2.095	0	%100
46	M141	Z	-3.629	-3.629	0	%100
47	M143	X	-2.186	-2.186	0	%100
48	M143	Z	-3.787	-3.787	0	%100
49	M148	X	- .58	- .58	0	%100
50	M148	Z	-1.004	-1.004	0	%100
51	M149	X	-1.539	-1.539	0	%100
52	M149	Z	-2.665	-2.665	0	%100
53	M150	X	-1.539	-1.539	0	%100
54	M150	Z	-2.665	-2.665	0	%100
55	M151	X	-2.098	-2.098	0	%100
56	M151	Z	-3.634	-3.634	0	%100
57	M154	X	-1.544	-1.544	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
58	M154	Z	-2.675	-2.675	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	-.688	-.688	0	%100
62	M159	Z	-1.192	-1.192	0	%100
63	M160	X	-2.095	-2.095	0	%100
64	M160	Z	-3.629	-3.629	0	%100
65	M162	X	-2.186	-2.186	0	%100
66	M162	Z	-3.787	-3.787	0	%100
67	M164	X	-.688	-.688	0	%100
68	M164	Z	-1.192	-1.192	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	-1.633	-1.633	0	%100
74	M172	Z	-2.829	-2.829	0	%100
75	MP1A	X	-1.757	-1.757	0	%100
76	MP1A	Z	-3.043	-3.043	0	%100
77	MP2A	X	-1.944	-1.944	0	%100
78	MP2A	Z	-3.367	-3.367	0	%100
79	MP3A	X	-1.757	-1.757	0	%100
80	MP3A	Z	-3.043	-3.043	0	%100
81	MP4A	X	-1.757	-1.757	0	%100
82	MP4A	Z	-3.043	-3.043	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	-1.757	-1.757	0	%100
86	MP1C	Z	-3.043	-3.043	0	%100
87	MP2C	X	-1.944	-1.944	0	%100
88	MP2C	Z	-3.367	-3.367	0	%100
89	MP3C	X	-1.757	-1.757	0	%100
90	MP3C	Z	-3.043	-3.043	0	%100
91	MP4C	X	-1.757	-1.757	0	%100
92	MP4C	Z	-3.043	-3.043	0	%100
93	M190	X	-1.633	-1.633	0	%100
94	M190	Z	-2.829	-2.829	0	%100
95	MP1B	X	-1.757	-1.757	0	%100
96	MP1B	Z	-3.043	-3.043	0	%100
97	MP2B	X	-1.944	-1.944	0	%100
98	MP2B	Z	-3.367	-3.367	0	%100
99	MP3B	X	-1.757	-1.757	0	%100
100	MP3B	Z	-3.043	-3.043	0	%100
101	MP4B	X	-1.757	-1.757	0	%100
102	MP4B	Z	-3.043	-3.043	0	%100
103	M101A	X	-1.443	-1.443	0	%100
104	M101A	Z	-2.498	-2.498	0	%100
105	M102A	X	-1.511	-1.511	0	%100
106	M102A	Z	-2.617	-2.617	0	%100
107	M116A	X	-1.458	-1.458	0	%100
108	M116A	Z	-2.525	-2.525	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	-1.458	-1.458	0	%100
112	M125A	Z	-2.525	-2.525	0	%100
113	M132A	X	-1.985	-1.985	0	%100
114	M132A	Z	-3.439	-3.439	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 64 : Structure Wi (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
115	M133A	X	-2.44	-2.44	0	%100
116	M133A	Z	-4.226	-4.226	0	%100
117	M134A	X	-1.985	-1.985	0	%100
118	M134A	Z	-3.439	-3.439	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	-1.511	-1.511	0	%100
122	M130A	Z	-2.617	-2.617	0	%100

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	0	0	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	-0.999	-0.999	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	-0.999	-0.999	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	-1.617	-1.617	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	-0.224	-0.224	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	-0.224	-0.224	0	%100
13	M111	X	0	0	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	-0.412	-0.412	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	-0.434	-0.434	0	%100
19	M116	X	0	0	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	-0.412	-0.412	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	-0.434	-0.434	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	-0.784	-0.784	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	-0.25	-0.25	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	-0.25	-0.25	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	-0.404	-0.404	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	-0.224	-0.224	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	-0.898	-0.898	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	-1.213	-1.213	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	-0.412	-0.412	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	-0.434	-0.434	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	-1.213	-1.213	0	%100
45	M141	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
46	M141	Z	-1.647	-1.647	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	-1.734	-1.734	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	-0.784	-0.784	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	-0.25	-0.25	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	-0.25	-0.25	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	-0.404	-0.404	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	-0.898	-0.898	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	-0.224	-0.224	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	-1.213	-1.213	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	-1.647	-1.647	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	-1.734	-1.734	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	-1.213	-1.213	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	-0.412	-0.412	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	-0.434	-0.434	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	-0.829	-0.829	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	-0.64	-0.64	0	%100
77	MP2A	X	0	0	0	%100
78	MP2A	Z	-0.775	-0.775	0	%100
79	MP3A	X	0	0	0	%100
80	MP3A	Z	-0.64	-0.64	0	%100
81	MP4A	X	0	0	0	%100
82	MP4A	Z	-0.64	-0.64	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	-0.207	-0.207	0	%100
85	MP1C	X	0	0	0	%100
86	MP1C	Z	-0.64	-0.64	0	%100
87	MP2C	X	0	0	0	%100
88	MP2C	Z	-0.775	-0.775	0	%100
89	MP3C	X	0	0	0	%100
90	MP3C	Z	-0.64	-0.64	0	%100
91	MP4C	X	0	0	0	%100
92	MP4C	Z	-0.64	-0.64	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	-0.207	-0.207	0	%100
95	MP1B	X	0	0	0	%100
96	MP1B	Z	-0.64	-0.64	0	%100
97	MP2B	X	0	0	0	%100
98	MP2B	Z	-0.775	-0.775	0	%100
99	MP3B	X	0	0	0	%100
100	MP3B	Z	-0.64	-0.64	0	%100
101	MP4B	X	0	0	0	%100
102	MP4B	Z	-0.64	-0.64	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 65 : Structure Wm (0 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
103	M101A	X	0	0	0	%100
104	M101A	Z	-523	-523	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	-983	-983	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	-775	-775	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	-194	-194	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	-194	-194	0	%100
113	M132A	X	0	0	0	%100
114	M132A	Z	-1.026	-1.026	0	%100
115	M133A	X	0	0	0	%100
116	M133A	Z	-1.132	-1.132	0	%100
117	M134A	X	0	0	0	%100
118	M134A	Z	-1.132	-1.132	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	-246	-246	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	-246	-246	0	%100

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	.131	.131	0	%100
2	M100	Z	-226	-226	0	%100
3	M101	X	.375	.375	0	%100
4	M101	Z	-.649	-.649	0	%100
5	M102	X	.375	.375	0	%100
6	M102	Z	-.649	-.649	0	%100
7	M103	X	.606	.606	0	%100
8	M103	Z	-1.05	-1.05	0	%100
9	M106	X	.337	.337	0	%100
10	M106	Z	-.583	-.583	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	.202	.202	0	%100
14	M111	Z	-.35	-.35	0	%100
15	M112	X	.618	.618	0	%100
16	M112	Z	-1.07	-1.07	0	%100
17	M114	X	.65	.65	0	%100
18	M114	Z	-1.127	-1.127	0	%100
19	M116	X	.202	.202	0	%100
20	M116	Z	-.35	-.35	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	.131	.131	0	%100
26	M124	Z	-226	-226	0	%100
27	M125	X	.375	.375	0	%100
28	M125	Z	-.649	-.649	0	%100
29	M126	X	.375	.375	0	%100
30	M126	Z	-.649	-.649	0	%100
31	M127	X	.606	.606	0	%100
32	M127	Z	-1.05	-1.05	0	%100
33	M130	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
34	M130	Z	0	0	0	%100
35	M131	X	.337	.337	0	%100
36	M131	Z	-.583	-.583	0	%100
37	M135	X	.202	.202	0	%100
38	M135	Z	-.35	-.35	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	.202	.202	0	%100
44	M140	Z	-.35	-.35	0	%100
45	M141	X	.618	.618	0	%100
46	M141	Z	-1.07	-1.07	0	%100
47	M143	X	.65	.65	0	%100
48	M143	Z	-1.127	-1.127	0	%100
49	M148	X	.522	.522	0	%100
50	M148	Z	-.905	-.905	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	.337	.337	0	%100
58	M154	Z	-.583	-.583	0	%100
59	M155	X	.337	.337	0	%100
60	M155	Z	-.583	-.583	0	%100
61	M159	X	.808	.808	0	%100
62	M159	Z	-1.4	-1.4	0	%100
63	M160	X	.618	.618	0	%100
64	M160	Z	-1.07	-1.07	0	%100
65	M162	X	.65	.65	0	%100
66	M162	Z	-1.127	-1.127	0	%100
67	M164	X	.808	.808	0	%100
68	M164	Z	-1.4	-1.4	0	%100
69	M165	X	.618	.618	0	%100
70	M165	Z	-1.07	-1.07	0	%100
71	M167	X	.65	.65	0	%100
72	M167	Z	-1.127	-1.127	0	%100
73	M172	X	.311	.311	0	%100
74	M172	Z	-.539	-.539	0	%100
75	MP1A	X	.32	.32	0	%100
76	MP1A	Z	-.554	-.554	0	%100
77	MP2A	X	.387	.387	0	%100
78	MP2A	Z	-.671	-.671	0	%100
79	MP3A	X	.32	.32	0	%100
80	MP3A	Z	-.554	-.554	0	%100
81	MP4A	X	.32	.32	0	%100
82	MP4A	Z	-.554	-.554	0	%100
83	M181	X	.311	.311	0	%100
84	M181	Z	-.539	-.539	0	%100
85	MP1C	X	.32	.32	0	%100
86	MP1C	Z	-.554	-.554	0	%100
87	MP2C	X	.387	.387	0	%100
88	MP2C	Z	-.671	-.671	0	%100
89	MP3C	X	.32	.32	0	%100
90	MP3C	Z	-.554	-.554	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 66 : Structure Wm (30 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
91	MP4C	X	.32	.32	0	%100
92	MP4C	Z	-.554	-.554	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	.32	.32	0	%100
96	MP1B	Z	-.554	-.554	0	%100
97	MP2B	X	.387	.387	0	%100
98	MP2B	Z	-.671	-.671	0	%100
99	MP3B	X	.32	.32	0	%100
100	MP3B	Z	-.554	-.554	0	%100
101	MP4B	X	.32	.32	0	%100
102	MP4B	Z	-.554	-.554	0	%100
103	M101A	X	.262	.262	0	%100
104	M101A	Z	-.453	-.453	0	%100
105	M102A	X	.369	.369	0	%100
106	M102A	Z	-.639	-.639	0	%100
107	M116A	X	.291	.291	0	%100
108	M116A	Z	-.503	-.503	0	%100
109	M120A	X	.291	.291	0	%100
110	M120A	Z	-.503	-.503	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	.53	.53	0	%100
114	M132A	Z	-.919	-.919	0	%100
115	M133A	X	.53	.53	0	%100
116	M133A	Z	-.919	-.919	0	%100
117	M134A	X	.584	.584	0	%100
118	M134A	Z	-1.011	-1.011	0	%100
119	M125B	X	.369	.369	0	%100
120	M125B	Z	-.639	-.639	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	.679	.679	0	%100
2	M100	Z	-.392	-.392	0	%100
3	M101	X	.216	.216	0	%100
4	M101	Z	-.125	-.125	0	%100
5	M102	X	.216	.216	0	%100
6	M102	Z	-.125	-.125	0	%100
7	M103	X	.35	.35	0	%100
8	M103	Z	-.202	-.202	0	%100
9	M106	X	.778	.778	0	%100
10	M106	Z	-.449	-.449	0	%100
11	M107	X	.194	.194	0	%100
12	M107	Z	-.112	-.112	0	%100
13	M111	X	1.05	1.05	0	%100
14	M111	Z	-.606	-.606	0	%100
15	M112	X	1.426	1.426	0	%100
16	M112	Z	-.823	-.823	0	%100
17	M114	X	1.502	1.502	0	%100
18	M114	Z	-.867	-.867	0	%100
19	M116	X	1.05	1.05	0	%100
20	M116	Z	-.606	-.606	0	%100
21	M117	X	.357	.357	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F....]	Start Location[ft.%]	End Location[ft.%]
22	M117	Z	-.206	-.206	0	%100
23	M119	X	.376	.376	0	%100
24	M119	Z	-.217	-.217	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	.865	.865	0	%100
28	M125	Z	-.5	-.5	0	%100
29	M126	X	.865	.865	0	%100
30	M126	Z	-.5	-.5	0	%100
31	M127	X	1.4	1.4	0	%100
32	M127	Z	-.808	-.808	0	%100
33	M130	X	.194	.194	0	%100
34	M130	Z	-.112	-.112	0	%100
35	M131	X	.194	.194	0	%100
36	M131	Z	-.112	-.112	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	.357	.357	0	%100
40	M136	Z	-.206	-.206	0	%100
41	M138	X	.376	.376	0	%100
42	M138	Z	-.217	-.217	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	.357	.357	0	%100
46	M141	Z	-.206	-.206	0	%100
47	M143	X	.376	.376	0	%100
48	M143	Z	-.217	-.217	0	%100
49	M148	X	.679	.679	0	%100
50	M148	Z	-.392	-.392	0	%100
51	M149	X	.216	.216	0	%100
52	M149	Z	-.125	-.125	0	%100
53	M150	X	.216	.216	0	%100
54	M150	Z	-.125	-.125	0	%100
55	M151	X	.35	.35	0	%100
56	M151	Z	-.202	-.202	0	%100
57	M154	X	.194	.194	0	%100
58	M154	Z	-.112	-.112	0	%100
59	M155	X	.778	.778	0	%100
60	M155	Z	-.449	-.449	0	%100
61	M159	X	1.05	1.05	0	%100
62	M159	Z	-.606	-.606	0	%100
63	M160	X	.357	.357	0	%100
64	M160	Z	-.206	-.206	0	%100
65	M162	X	.376	.376	0	%100
66	M162	Z	-.217	-.217	0	%100
67	M164	X	1.05	1.05	0	%100
68	M164	Z	-.606	-.606	0	%100
69	M165	X	1.426	1.426	0	%100
70	M165	Z	-.823	-.823	0	%100
71	M167	X	1.502	1.502	0	%100
72	M167	Z	-.867	-.867	0	%100
73	M172	X	.18	.18	0	%100
74	M172	Z	-.104	-.104	0	%100
75	MP1A	X	.554	.554	0	%100
76	MP1A	Z	-.32	-.32	0	%100
77	MP2A	X	.671	.671	0	%100
78	MP2A	Z	-.387	-.387	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 67 : Structure Wm (60 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
79	MP3A	X	.554	.554	0	%100
80	MP3A	Z	-.32	-.32	0	%100
81	MP4A	X	.554	.554	0	%100
82	MP4A	Z	-.32	-.32	0	%100
83	M181	X	.718	.718	0	%100
84	M181	Z	-.415	-.415	0	%100
85	MP1C	X	.554	.554	0	%100
86	MP1C	Z	-.32	-.32	0	%100
87	MP2C	X	.671	.671	0	%100
88	MP2C	Z	-.387	-.387	0	%100
89	MP3C	X	.554	.554	0	%100
90	MP3C	Z	-.32	-.32	0	%100
91	MP4C	X	.554	.554	0	%100
92	MP4C	Z	-.32	-.32	0	%100
93	M190	X	.18	.18	0	%100
94	M190	Z	-.104	-.104	0	%100
95	MP1B	X	.554	.554	0	%100
96	MP1B	Z	-.32	-.32	0	%100
97	MP2B	X	.671	.671	0	%100
98	MP2B	Z	-.387	-.387	0	%100
99	MP3B	X	.554	.554	0	%100
100	MP3B	Z	-.32	-.32	0	%100
101	MP4B	X	.554	.554	0	%100
102	MP4B	Z	-.32	-.32	0	%100
103	M101A	X	.453	.453	0	%100
104	M101A	Z	-.262	-.262	0	%100
105	M102A	X	.213	.213	0	%100
106	M102A	Z	-.123	-.123	0	%100
107	M116A	X	.168	.168	0	%100
108	M116A	Z	-.097	-.097	0	%100
109	M120A	X	.671	.671	0	%100
110	M120A	Z	-.387	-.387	0	%100
111	M125A	X	.168	.168	0	%100
112	M125A	Z	-.097	-.097	0	%100
113	M132A	X	.98	.98	0	%100
114	M132A	Z	-.566	-.566	0	%100
115	M133A	X	.888	.888	0	%100
116	M133A	Z	-.513	-.513	0	%100
117	M134A	X	.98	.98	0	%100
118	M134A	Z	-.566	-.566	0	%100
119	M125B	X	.852	.852	0	%100
120	M125B	Z	-.492	-.492	0	%100
121	M130A	X	.213	.213	0	%100
122	M130A	Z	-.123	-.123	0	%100

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	1.045	1.045	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	0	0	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	0	0	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	0	0	0	%100
9	M106	X	.673	.673	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.]	End Magnitude[lb/ft.]	Start Location[ft.%]	End Location[ft.%]
10	M106	Z	0	0	0	%100
11	M107	X	.673	.673	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	1.617	1.617	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	1.235	1.235	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	1.301	1.301	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	1.617	1.617	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	1.235	1.235	0	%100
22	M117	Z	0	0	0	%100
23	M119	X	1.301	1.301	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	.261	.261	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	.749	.749	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	.749	.749	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	1.213	1.213	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	.673	.673	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	0	0	0	%100
37	M135	X	.404	.404	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	1.235	1.235	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	1.301	1.301	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	.404	.404	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	0	0	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	0	0	0	%100
49	M148	X	.261	.261	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	.749	.749	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	.749	.749	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	1.213	1.213	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	0	0	0	%100
59	M155	X	.673	.673	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	.404	.404	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	0	0	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 68 : Structure Wm (90 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
67	M164	X	.404	.404	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	1.235	1.235	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	1.301	1.301	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	0	0	0	%100
75	MP1A	X	.64	.64	0	%100
76	MP1A	Z	0	0	0	%100
77	MP2A	X	.775	.775	0	%100
78	MP2A	Z	0	0	0	%100
79	MP3A	X	.64	.64	0	%100
80	MP3A	Z	0	0	0	%100
81	MP4A	X	.64	.64	0	%100
82	MP4A	Z	0	0	0	%100
83	M181	X	.622	.622	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	.64	.64	0	%100
86	MP1C	Z	0	0	0	%100
87	MP2C	X	.775	.775	0	%100
88	MP2C	Z	0	0	0	%100
89	MP3C	X	.64	.64	0	%100
90	MP3C	Z	0	0	0	%100
91	MP4C	X	.64	.64	0	%100
92	MP4C	Z	0	0	0	%100
93	M190	X	.622	.622	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	.64	.64	0	%100
96	MP1B	Z	0	0	0	%100
97	MP2B	X	.775	.775	0	%100
98	MP2B	Z	0	0	0	%100
99	MP3B	X	.64	.64	0	%100
100	MP3B	Z	0	0	0	%100
101	MP4B	X	.64	.64	0	%100
102	MP4B	Z	0	0	0	%100
103	M101A	X	.523	.523	0	%100
104	M101A	Z	0	0	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	0	0	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	0	0	0	%100
109	M120A	X	.581	.581	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	.581	.581	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	1.167	1.167	0	%100
114	M132A	Z	0	0	0	%100
115	M133A	X	1.061	1.061	0	%100
116	M133A	Z	0	0	0	%100
117	M134A	X	1.061	1.061	0	%100
118	M134A	Z	0	0	0	%100
119	M125B	X	.738	.738	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	.738	.738	0	%100
122	M130A	Z	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	.679	.679	0	%100
2	M100	Z	.392	.392	0	%100
3	M101	X	.216	.216	0	%100
4	M101	Z	.125	.125	0	%100
5	M102	X	.216	.216	0	%100
6	M102	Z	.125	.125	0	%100
7	M103	X	.35	.35	0	%100
8	M103	Z	.202	.202	0	%100
9	M106	X	.194	.194	0	%100
10	M106	Z	.112	.112	0	%100
11	M107	X	.778	.778	0	%100
12	M107	Z	.449	.449	0	%100
13	M111	X	1.05	1.05	0	%100
14	M111	Z	.606	.606	0	%100
15	M112	X	.357	.357	0	%100
16	M112	Z	.206	.206	0	%100
17	M114	X	.376	.376	0	%100
18	M114	Z	.217	.217	0	%100
19	M116	X	1.05	1.05	0	%100
20	M116	Z	.606	.606	0	%100
21	M117	X	1.426	1.426	0	%100
22	M117	Z	.823	.823	0	%100
23	M119	X	1.502	1.502	0	%100
24	M119	Z	.867	.867	0	%100
25	M124	X	.679	.679	0	%100
26	M124	Z	.392	.392	0	%100
27	M125	X	.216	.216	0	%100
28	M125	Z	.125	.125	0	%100
29	M126	X	.216	.216	0	%100
30	M126	Z	.125	.125	0	%100
31	M127	X	.35	.35	0	%100
32	M127	Z	.202	.202	0	%100
33	M130	X	.778	.778	0	%100
34	M130	Z	.449	.449	0	%100
35	M131	X	.194	.194	0	%100
36	M131	Z	.112	.112	0	%100
37	M135	X	1.05	1.05	0	%100
38	M135	Z	.606	.606	0	%100
39	M136	X	1.426	1.426	0	%100
40	M136	Z	.823	.823	0	%100
41	M138	X	1.502	1.502	0	%100
42	M138	Z	.867	.867	0	%100
43	M140	X	1.05	1.05	0	%100
44	M140	Z	.606	.606	0	%100
45	M141	X	.357	.357	0	%100
46	M141	Z	.206	.206	0	%100
47	M143	X	.376	.376	0	%100
48	M143	Z	.217	.217	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	.865	.865	0	%100
52	M149	Z	.5	.5	0	%100
53	M150	X	.865	.865	0	%100
54	M150	Z	.5	.5	0	%100
55	M151	X	1.4	1.4	0	%100
56	M151	Z	.808	.808	0	%100
57	M154	X	.194	.194	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg)) (Continued)

Member Label	Direction	Start Magnitude[lb/ft...]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
58	M154	Z	.112	.112	0 %100
59	M155	X	.194	.194	0 %100
60	M155	Z	.112	.112	0 %100
61	M159	X	0	0	0 %100
62	M159	Z	0	0	0 %100
63	M160	X	.357	.357	0 %100
64	M160	Z	.206	.206	0 %100
65	M162	X	.376	.376	0 %100
66	M162	Z	.217	.217	0 %100
67	M164	X	0	0	0 %100
68	M164	Z	0	0	0 %100
69	M165	X	.357	.357	0 %100
70	M165	Z	.206	.206	0 %100
71	M167	X	.376	.376	0 %100
72	M167	Z	.217	.217	0 %100
73	M172	X	.18	.18	0 %100
74	M172	Z	.104	.104	0 %100
75	MP1A	X	.554	.554	0 %100
76	MP1A	Z	.32	.32	0 %100
77	MP2A	X	.671	.671	0 %100
78	MP2A	Z	.387	.387	0 %100
79	MP3A	X	.554	.554	0 %100
80	MP3A	Z	.32	.32	0 %100
81	MP4A	X	.554	.554	0 %100
82	MP4A	Z	.32	.32	0 %100
83	M181	X	.18	.18	0 %100
84	M181	Z	.104	.104	0 %100
85	MP1C	X	.554	.554	0 %100
86	MP1C	Z	.32	.32	0 %100
87	MP2C	X	.671	.671	0 %100
88	MP2C	Z	.387	.387	0 %100
89	MP3C	X	.554	.554	0 %100
90	MP3C	Z	.32	.32	0 %100
91	MP4C	X	.554	.554	0 %100
92	MP4C	Z	.32	.32	0 %100
93	M190	X	.718	.718	0 %100
94	M190	Z	.415	.415	0 %100
95	MP1B	X	.554	.554	0 %100
96	MP1B	Z	.32	.32	0 %100
97	MP2B	X	.671	.671	0 %100
98	MP2B	Z	.387	.387	0 %100
99	MP3B	X	.554	.554	0 %100
100	MP3B	Z	.32	.32	0 %100
101	MP4B	X	.554	.554	0 %100
102	MP4B	Z	.32	.32	0 %100
103	M101A	X	.453	.453	0 %100
104	M101A	Z	.262	.262	0 %100
105	M102A	X	.213	.213	0 %100
106	M102A	Z	.123	.123	0 %100
107	M116A	X	.168	.168	0 %100
108	M116A	Z	.097	.097	0 %100
109	M120A	X	.168	.168	0 %100
110	M120A	Z	.097	.097	0 %100
111	M125A	X	.671	.671	0 %100
112	M125A	Z	.387	.387	0 %100
113	M132A	X	.98	.98	0 %100
114	M132A	Z	.566	.566	0 %100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 69 : Structure Wm (120 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
115	M133A	X	.98	.98	0	%100
116	M133A	Z	.566	.566	0	%100
117	M134A	X	.888	.888	0	%100
118	M134A	Z	.513	.513	0	%100
119	M125B	X	.213	.213	0	%100
120	M125B	Z	.123	.123	0	%100
121	M130A	X	.852	.852	0	%100
122	M130A	Z	.492	.492	0	%100

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	.131	.131	0	%100
2	M100	Z	.226	.226	0	%100
3	M101	X	.375	.375	0	%100
4	M101	Z	.649	.649	0	%100
5	M102	X	.375	.375	0	%100
6	M102	Z	.649	.649	0	%100
7	M103	X	.606	.606	0	%100
8	M103	Z	1.05	1.05	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	.337	.337	0	%100
12	M107	Z	.583	.583	0	%100
13	M111	X	.202	.202	0	%100
14	M111	Z	.35	.35	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	.202	.202	0	%100
20	M116	Z	.35	.35	0	%100
21	M117	X	.618	.618	0	%100
22	M117	Z	1.07	1.07	0	%100
23	M119	X	.65	.65	0	%100
24	M119	Z	1.127	1.127	0	%100
25	M124	X	.522	.522	0	%100
26	M124	Z	.905	.905	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	.337	.337	0	%100
34	M130	Z	.583	.583	0	%100
35	M131	X	.337	.337	0	%100
36	M131	Z	.583	.583	0	%100
37	M135	X	.808	.808	0	%100
38	M135	Z	1.4	1.4	0	%100
39	M136	X	.618	.618	0	%100
40	M136	Z	1.07	1.07	0	%100
41	M138	X	.65	.65	0	%100
42	M138	Z	1.127	1.127	0	%100
43	M140	X	.808	.808	0	%100
44	M140	Z	1.4	1.4	0	%100
45	M141	X	.618	.618	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg)) (Continued)

Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
46	M141	Z	1.07	1.07	0 %100
47	M143	X	.65	.65	0 %100
48	M143	Z	1.127	1.127	0 %100
49	M148	X	.131	.131	0 %100
50	M148	Z	.226	.226	0 %100
51	M149	X	.375	.375	0 %100
52	M149	Z	.649	.649	0 %100
53	M150	X	.375	.375	0 %100
54	M150	Z	.649	.649	0 %100
55	M151	X	.606	.606	0 %100
56	M151	Z	1.05	1.05	0 %100
57	M154	X	.337	.337	0 %100
58	M154	Z	.583	.583	0 %100
59	M155	X	0	0	0 %100
60	M155	Z	0	0	0 %100
61	M159	X	.202	.202	0 %100
62	M159	Z	.35	.35	0 %100
63	M160	X	.618	.618	0 %100
64	M160	Z	1.07	1.07	0 %100
65	M162	X	.65	.65	0 %100
66	M162	Z	1.127	1.127	0 %100
67	M164	X	.202	.202	0 %100
68	M164	Z	.35	.35	0 %100
69	M165	X	0	0	0 %100
70	M165	Z	0	0	0 %100
71	M167	X	0	0	0 %100
72	M167	Z	0	0	0 %100
73	M172	X	.311	.311	0 %100
74	M172	Z	.539	.539	0 %100
75	MP1A	X	.32	.32	0 %100
76	MP1A	Z	.554	.554	0 %100
77	MP2A	X	.387	.387	0 %100
78	MP2A	Z	.671	.671	0 %100
79	MP3A	X	.32	.32	0 %100
80	MP3A	Z	.554	.554	0 %100
81	MP4A	X	.32	.32	0 %100
82	MP4A	Z	.554	.554	0 %100
83	M181	X	0	0	0 %100
84	M181	Z	0	0	0 %100
85	MP1C	X	.32	.32	0 %100
86	MP1C	Z	.554	.554	0 %100
87	MP2C	X	.387	.387	0 %100
88	MP2C	Z	.671	.671	0 %100
89	MP3C	X	.32	.32	0 %100
90	MP3C	Z	.554	.554	0 %100
91	MP4C	X	.32	.32	0 %100
92	MP4C	Z	.554	.554	0 %100
93	M190	X	.311	.311	0 %100
94	M190	Z	.539	.539	0 %100
95	MP1B	X	.32	.32	0 %100
96	MP1B	Z	.554	.554	0 %100
97	MP2B	X	.387	.387	0 %100
98	MP2B	Z	.671	.671	0 %100
99	MP3B	X	.32	.32	0 %100
100	MP3B	Z	.554	.554	0 %100
101	MP4B	X	.32	.32	0 %100
102	MP4B	Z	.554	.554	0 %100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 70 : Structure Wm (150 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
103	M101A	X	.262	.262	0	%100
104	M101A	Z	.453	.453	0	%100
105	M102A	X	.369	.369	0	%100
106	M102A	Z	.639	.639	0	%100
107	M116A	X	.291	.291	0	%100
108	M116A	Z	.503	.503	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	.291	.291	0	%100
112	M125A	Z	.503	.503	0	%100
113	M132A	X	.53	.53	0	%100
114	M132A	Z	.919	.919	0	%100
115	M133A	X	.584	.584	0	%100
116	M133A	Z	1.011	1.011	0	%100
117	M134A	X	.53	.53	0	%100
118	M134A	Z	.919	.919	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	.369	.369	0	%100
122	M130A	Z	.639	.639	0	%100

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	0	0	0	%100
2	M100	Z	0	0	0	%100
3	M101	X	0	0	0	%100
4	M101	Z	.999	.999	0	%100
5	M102	X	0	0	0	%100
6	M102	Z	.999	.999	0	%100
7	M103	X	0	0	0	%100
8	M103	Z	1.617	1.617	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	.224	.224	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	.224	.224	0	%100
13	M111	X	0	0	0	%100
14	M111	Z	0	0	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	.412	.412	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	.434	.434	0	%100
19	M116	X	0	0	0	%100
20	M116	Z	0	0	0	%100
21	M117	X	0	0	0	%100
22	M117	Z	.412	.412	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	.434	.434	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	.784	.784	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	.25	.25	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	.25	.25	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	.404	.404	0	%100
33	M130	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
34	M130	Z	.224	.224	0	%100
35	M131	X	0	0	0	%100
36	M131	Z	.898	.898	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	1.213	1.213	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	.412	.412	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	.434	.434	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	1.213	1.213	0	%100
45	M141	X	0	0	0	%100
46	M141	Z	1.647	1.647	0	%100
47	M143	X	0	0	0	%100
48	M143	Z	1.734	1.734	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	.784	.784	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	.25	.25	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	.25	.25	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	.404	.404	0	%100
57	M154	X	0	0	0	%100
58	M154	Z	.898	.898	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	.224	.224	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	1.213	1.213	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	1.647	1.647	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	1.734	1.734	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	1.213	1.213	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	.412	.412	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	.434	.434	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	.829	.829	0	%100
75	MP1A	X	0	0	0	%100
76	MP1A	Z	.64	.64	0	%100
77	MP2A	X	0	0	0	%100
78	MP2A	Z	.775	.775	0	%100
79	MP3A	X	0	0	0	%100
80	MP3A	Z	.64	.64	0	%100
81	MP4A	X	0	0	0	%100
82	MP4A	Z	.64	.64	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	.207	.207	0	%100
85	MP1C	X	0	0	0	%100
86	MP1C	Z	.64	.64	0	%100
87	MP2C	X	0	0	0	%100
88	MP2C	Z	.775	.775	0	%100
89	MP3C	X	0	0	0	%100
90	MP3C	Z	.64	.64	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 71 : Structure Wm (180 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
91	MP4C	X	0	0	0	%100
92	MP4C	Z	.64	.64	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	.207	.207	0	%100
95	MP1B	X	0	0	0	%100
96	MP1B	Z	.64	.64	0	%100
97	MP2B	X	0	0	0	%100
98	MP2B	Z	.775	.775	0	%100
99	MP3B	X	0	0	0	%100
100	MP3B	Z	.64	.64	0	%100
101	MP4B	X	0	0	0	%100
102	MP4B	Z	.64	.64	0	%100
103	M101A	X	0	0	0	%100
104	M101A	Z	.523	.523	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	.983	.983	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	.775	.775	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	.194	.194	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	.194	.194	0	%100
113	M132A	X	0	0	0	%100
114	M132A	Z	1.026	1.026	0	%100
115	M133A	X	0	0	0	%100
116	M133A	Z	1.132	1.132	0	%100
117	M134A	X	0	0	0	%100
118	M134A	Z	1.132	1.132	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	.246	.246	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	.246	.246	0	%100

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-.131	-.131	0	%100
2	M100	Z	.226	.226	0	%100
3	M101	X	-.375	-.375	0	%100
4	M101	Z	.649	.649	0	%100
5	M102	X	-.375	-.375	0	%100
6	M102	Z	.649	.649	0	%100
7	M103	X	-.606	-.606	0	%100
8	M103	Z	1.05	1.05	0	%100
9	M106	X	-.337	-.337	0	%100
10	M106	Z	.583	.583	0	%100
11	M107	X	0	0	0	%100
12	M107	Z	0	0	0	%100
13	M111	X	-.202	-.202	0	%100
14	M111	Z	.35	.35	0	%100
15	M112	X	-.618	-.618	0	%100
16	M112	Z	1.07	1.07	0	%100
17	M114	X	-.65	-.65	0	%100
18	M114	Z	1.127	1.127	0	%100
19	M116	X	-.202	-.202	0	%100
20	M116	Z	.35	.35	0	%100
21	M117	X	0	0	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft...]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
22	M117	Z	0	0	0	%100
23	M119	X	0	0	0	%100
24	M119	Z	0	0	0	%100
25	M124	X	-.131	-.131	0	%100
26	M124	Z	.226	.226	0	%100
27	M125	X	-.375	-.375	0	%100
28	M125	Z	.649	.649	0	%100
29	M126	X	-.375	-.375	0	%100
30	M126	Z	.649	.649	0	%100
31	M127	X	-.606	-.606	0	%100
32	M127	Z	1.05	1.05	0	%100
33	M130	X	0	0	0	%100
34	M130	Z	0	0	0	%100
35	M131	X	-.337	-.337	0	%100
36	M131	Z	.583	.583	0	%100
37	M135	X	-.202	-.202	0	%100
38	M135	Z	.35	.35	0	%100
39	M136	X	0	0	0	%100
40	M136	Z	0	0	0	%100
41	M138	X	0	0	0	%100
42	M138	Z	0	0	0	%100
43	M140	X	-.202	-.202	0	%100
44	M140	Z	.35	.35	0	%100
45	M141	X	-.618	-.618	0	%100
46	M141	Z	1.07	1.07	0	%100
47	M143	X	-.65	-.65	0	%100
48	M143	Z	1.127	1.127	0	%100
49	M148	X	-.522	-.522	0	%100
50	M148	Z	.905	.905	0	%100
51	M149	X	0	0	0	%100
52	M149	Z	0	0	0	%100
53	M150	X	0	0	0	%100
54	M150	Z	0	0	0	%100
55	M151	X	0	0	0	%100
56	M151	Z	0	0	0	%100
57	M154	X	-.337	-.337	0	%100
58	M154	Z	.583	.583	0	%100
59	M155	X	-.337	-.337	0	%100
60	M155	Z	.583	.583	0	%100
61	M159	X	-.808	-.808	0	%100
62	M159	Z	1.4	1.4	0	%100
63	M160	X	-.618	-.618	0	%100
64	M160	Z	1.07	1.07	0	%100
65	M162	X	-.65	-.65	0	%100
66	M162	Z	1.127	1.127	0	%100
67	M164	X	-.808	-.808	0	%100
68	M164	Z	1.4	1.4	0	%100
69	M165	X	-.618	-.618	0	%100
70	M165	Z	1.07	1.07	0	%100
71	M167	X	-.65	-.65	0	%100
72	M167	Z	1.127	1.127	0	%100
73	M172	X	-.311	-.311	0	%100
74	M172	Z	.539	.539	0	%100
75	MP1A	X	-.32	-.32	0	%100
76	MP1A	Z	.554	.554	0	%100
77	MP2A	X	-.387	-.387	0	%100
78	MP2A	Z	.671	.671	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 72 : Structure Wm (210 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
79	MP3A	X	-.32	-.32	0	%100
80	MP3A	Z	.554	.554	0	%100
81	MP4A	X	-.32	-.32	0	%100
82	MP4A	Z	.554	.554	0	%100
83	M181	X	-.311	-.311	0	%100
84	M181	Z	.539	.539	0	%100
85	MP1C	X	-.32	-.32	0	%100
86	MP1C	Z	.554	.554	0	%100
87	MP2C	X	-.387	-.387	0	%100
88	MP2C	Z	.671	.671	0	%100
89	MP3C	X	-.32	-.32	0	%100
90	MP3C	Z	.554	.554	0	%100
91	MP4C	X	-.32	-.32	0	%100
92	MP4C	Z	.554	.554	0	%100
93	M190	X	0	0	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	-.32	-.32	0	%100
96	MP1B	Z	.554	.554	0	%100
97	MP2B	X	-.387	-.387	0	%100
98	MP2B	Z	.671	.671	0	%100
99	MP3B	X	-.32	-.32	0	%100
100	MP3B	Z	.554	.554	0	%100
101	MP4B	X	-.32	-.32	0	%100
102	MP4B	Z	.554	.554	0	%100
103	M101A	X	-.262	-.262	0	%100
104	M101A	Z	.453	.453	0	%100
105	M102A	X	-.369	-.369	0	%100
106	M102A	Z	.639	.639	0	%100
107	M116A	X	-.291	-.291	0	%100
108	M116A	Z	.503	.503	0	%100
109	M120A	X	-.291	-.291	0	%100
110	M120A	Z	.503	.503	0	%100
111	M125A	X	0	0	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	-.53	-.53	0	%100
114	M132A	Z	.919	.919	0	%100
115	M133A	X	-.53	-.53	0	%100
116	M133A	Z	.919	.919	0	%100
117	M134A	X	-.584	-.584	0	%100
118	M134A	Z	1.011	1.011	0	%100
119	M125B	X	-.369	-.369	0	%100
120	M125B	Z	.639	.639	0	%100
121	M130A	X	0	0	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-.679	-.679	0	%100
2	M100	Z	.392	.392	0	%100
3	M101	X	-.216	-.216	0	%100
4	M101	Z	.125	.125	0	%100
5	M102	X	-.216	-.216	0	%100
6	M102	Z	.125	.125	0	%100
7	M103	X	-.35	-.35	0	%100
8	M103	Z	.202	.202	0	%100
9	M106	X	-.778	-.778	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F....]	Start Location[ft.%]	End Location[ft.%]
10	M106	Z	.449	.449	0	%100
11	M107	X	-.194	-.194	0	%100
12	M107	Z	.112	.112	0	%100
13	M111	X	-1.05	-1.05	0	%100
14	M111	Z	.606	.606	0	%100
15	M112	X	-1.426	-1.426	0	%100
16	M112	Z	.823	.823	0	%100
17	M114	X	-1.502	-1.502	0	%100
18	M114	Z	.867	.867	0	%100
19	M116	X	-1.05	-1.05	0	%100
20	M116	Z	.606	.606	0	%100
21	M117	X	-.357	-.357	0	%100
22	M117	Z	.206	.206	0	%100
23	M119	X	-.376	-.376	0	%100
24	M119	Z	.217	.217	0	%100
25	M124	X	0	0	0	%100
26	M124	Z	0	0	0	%100
27	M125	X	-.865	-.865	0	%100
28	M125	Z	.5	.5	0	%100
29	M126	X	-.865	-.865	0	%100
30	M126	Z	.5	.5	0	%100
31	M127	X	-1.4	-1.4	0	%100
32	M127	Z	.808	.808	0	%100
33	M130	X	-.194	-.194	0	%100
34	M130	Z	.112	.112	0	%100
35	M131	X	-.194	-.194	0	%100
36	M131	Z	.112	.112	0	%100
37	M135	X	0	0	0	%100
38	M135	Z	0	0	0	%100
39	M136	X	-.357	-.357	0	%100
40	M136	Z	.206	.206	0	%100
41	M138	X	-.376	-.376	0	%100
42	M138	Z	.217	.217	0	%100
43	M140	X	0	0	0	%100
44	M140	Z	0	0	0	%100
45	M141	X	-.357	-.357	0	%100
46	M141	Z	.206	.206	0	%100
47	M143	X	-.376	-.376	0	%100
48	M143	Z	.217	.217	0	%100
49	M148	X	-.679	-.679	0	%100
50	M148	Z	.392	.392	0	%100
51	M149	X	-.216	-.216	0	%100
52	M149	Z	.125	.125	0	%100
53	M150	X	-.216	-.216	0	%100
54	M150	Z	.125	.125	0	%100
55	M151	X	-.35	-.35	0	%100
56	M151	Z	.202	.202	0	%100
57	M154	X	-.194	-.194	0	%100
58	M154	Z	.112	.112	0	%100
59	M155	X	-.778	-.778	0	%100
60	M155	Z	.449	.449	0	%100
61	M159	X	-1.05	-1.05	0	%100
62	M159	Z	.606	.606	0	%100
63	M160	X	-.357	-.357	0	%100
64	M160	Z	.206	.206	0	%100
65	M162	X	-.376	-.376	0	%100
66	M162	Z	.217	.217	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 73 : Structure Wm (240 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
67	M164	X	-1.05	-1.05	0	%100
68	M164	Z	.606	.606	0	%100
69	M165	X	-1.426	-1.426	0	%100
70	M165	Z	.823	.823	0	%100
71	M167	X	-1.502	-1.502	0	%100
72	M167	Z	.867	.867	0	%100
73	M172	X	-.18	-.18	0	%100
74	M172	Z	.104	.104	0	%100
75	MP1A	X	-.554	-.554	0	%100
76	MP1A	Z	.32	.32	0	%100
77	MP2A	X	-.671	-.671	0	%100
78	MP2A	Z	.387	.387	0	%100
79	MP3A	X	-.554	-.554	0	%100
80	MP3A	Z	.32	.32	0	%100
81	MP4A	X	-.554	-.554	0	%100
82	MP4A	Z	.32	.32	0	%100
83	M181	X	-.718	-.718	0	%100
84	M181	Z	.415	.415	0	%100
85	MP1C	X	-.554	-.554	0	%100
86	MP1C	Z	.32	.32	0	%100
87	MP2C	X	-.671	-.671	0	%100
88	MP2C	Z	.387	.387	0	%100
89	MP3C	X	-.554	-.554	0	%100
90	MP3C	Z	.32	.32	0	%100
91	MP4C	X	-.554	-.554	0	%100
92	MP4C	Z	.32	.32	0	%100
93	M190	X	-.18	-.18	0	%100
94	M190	Z	.104	.104	0	%100
95	MP1B	X	-.554	-.554	0	%100
96	MP1B	Z	.32	.32	0	%100
97	MP2B	X	-.671	-.671	0	%100
98	MP2B	Z	.387	.387	0	%100
99	MP3B	X	-.554	-.554	0	%100
100	MP3B	Z	.32	.32	0	%100
101	MP4B	X	-.554	-.554	0	%100
102	MP4B	Z	.32	.32	0	%100
103	M101A	X	-.453	-.453	0	%100
104	M101A	Z	.262	.262	0	%100
105	M102A	X	-.213	-.213	0	%100
106	M102A	Z	.123	.123	0	%100
107	M116A	X	-.168	-.168	0	%100
108	M116A	Z	.097	.097	0	%100
109	M120A	X	-.671	-.671	0	%100
110	M120A	Z	.387	.387	0	%100
111	M125A	X	-.168	-.168	0	%100
112	M125A	Z	.097	.097	0	%100
113	M132A	X	-.98	-.98	0	%100
114	M132A	Z	.566	.566	0	%100
115	M133A	X	-.888	-.888	0	%100
116	M133A	Z	.513	.513	0	%100
117	M134A	X	-.98	-.98	0	%100
118	M134A	Z	.566	.566	0	%100
119	M125B	X	-.852	-.852	0	%100
120	M125B	Z	.492	.492	0	%100
121	M130A	X	-.213	-.213	0	%100
122	M130A	Z	.123	.123	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg))

Member Label	Direction	Start Magnitude[lb/ft...	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-1.045	-1.045	0 %100
2	M100	Z	0	0	0 %100
3	M101	X	0	0	0 %100
4	M101	Z	0	0	0 %100
5	M102	X	0	0	0 %100
6	M102	Z	0	0	0 %100
7	M103	X	0	0	0 %100
8	M103	Z	0	0	0 %100
9	M106	X	-0.673	-0.673	0 %100
10	M106	Z	0	0	0 %100
11	M107	X	-0.673	-0.673	0 %100
12	M107	Z	0	0	0 %100
13	M111	X	-1.617	-1.617	0 %100
14	M111	Z	0	0	0 %100
15	M112	X	-1.235	-1.235	0 %100
16	M112	Z	0	0	0 %100
17	M114	X	-1.301	-1.301	0 %100
18	M114	Z	0	0	0 %100
19	M116	X	-1.617	-1.617	0 %100
20	M116	Z	0	0	0 %100
21	M117	X	-1.235	-1.235	0 %100
22	M117	Z	0	0	0 %100
23	M119	X	-1.301	-1.301	0 %100
24	M119	Z	0	0	0 %100
25	M124	X	-0.261	-0.261	0 %100
26	M124	Z	0	0	0 %100
27	M125	X	-0.749	-0.749	0 %100
28	M125	Z	0	0	0 %100
29	M126	X	-0.749	-0.749	0 %100
30	M126	Z	0	0	0 %100
31	M127	X	-1.213	-1.213	0 %100
32	M127	Z	0	0	0 %100
33	M130	X	-0.673	-0.673	0 %100
34	M130	Z	0	0	0 %100
35	M131	X	0	0	0 %100
36	M131	Z	0	0	0 %100
37	M135	X	-0.404	-0.404	0 %100
38	M135	Z	0	0	0 %100
39	M136	X	-1.235	-1.235	0 %100
40	M136	Z	0	0	0 %100
41	M138	X	-1.301	-1.301	0 %100
42	M138	Z	0	0	0 %100
43	M140	X	-0.404	-0.404	0 %100
44	M140	Z	0	0	0 %100
45	M141	X	0	0	0 %100
46	M141	Z	0	0	0 %100
47	M143	X	0	0	0 %100
48	M143	Z	0	0	0 %100
49	M148	X	-0.261	-0.261	0 %100
50	M148	Z	0	0	0 %100
51	M149	X	-0.749	-0.749	0 %100
52	M149	Z	0	0	0 %100
53	M150	X	-0.749	-0.749	0 %100
54	M150	Z	0	0	0 %100
55	M151	X	-1.213	-1.213	0 %100
56	M151	Z	0	0	0 %100
57	M154	X	0	0	0 %100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
58	M154	Z	0	0	0	%100
59	M155	X	-673	-673	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	-404	-404	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	0	0	0	%100
64	M160	Z	0	0	0	%100
65	M162	X	0	0	0	%100
66	M162	Z	0	0	0	%100
67	M164	X	-404	-404	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	-1.235	-1.235	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	-1.301	-1.301	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	0	0	0	%100
74	M172	Z	0	0	0	%100
75	MP1A	X	-64	-64	0	%100
76	MP1A	Z	0	0	0	%100
77	MP2A	X	-775	-775	0	%100
78	MP2A	Z	0	0	0	%100
79	MP3A	X	-64	-64	0	%100
80	MP3A	Z	0	0	0	%100
81	MP4A	X	-64	-64	0	%100
82	MP4A	Z	0	0	0	%100
83	M181	X	-622	-622	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	-64	-64	0	%100
86	MP1C	Z	0	0	0	%100
87	MP2C	X	-775	-775	0	%100
88	MP2C	Z	0	0	0	%100
89	MP3C	X	-64	-64	0	%100
90	MP3C	Z	0	0	0	%100
91	MP4C	X	-64	-64	0	%100
92	MP4C	Z	0	0	0	%100
93	M190	X	-622	-622	0	%100
94	M190	Z	0	0	0	%100
95	MP1B	X	-64	-64	0	%100
96	MP1B	Z	0	0	0	%100
97	MP2B	X	-775	-775	0	%100
98	MP2B	Z	0	0	0	%100
99	MP3B	X	-64	-64	0	%100
100	MP3B	Z	0	0	0	%100
101	MP4B	X	-64	-64	0	%100
102	MP4B	Z	0	0	0	%100
103	M101A	X	-523	-523	0	%100
104	M101A	Z	0	0	0	%100
105	M102A	X	0	0	0	%100
106	M102A	Z	0	0	0	%100
107	M116A	X	0	0	0	%100
108	M116A	Z	0	0	0	%100
109	M120A	X	-581	-581	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	-581	-581	0	%100
112	M125A	Z	0	0	0	%100
113	M132A	X	-1.167	-1.167	0	%100
114	M132A	Z	0	0	0	%100



Company
Designer
Job Number
Model Name

Sept 27, 2023
2:55 PM
Checked By: _____

Member Distributed Loads (BLC 74 : Structure Wm (270 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
115	M133A	X	-1.061	-1.061	0	%100
116	M133A	Z	0	0	0	%100
117	M134A	X	-1.061	-1.061	0	%100
118	M134A	Z	0	0	0	%100
119	M125B	X	-.738	-.738	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	-.738	-.738	0	%100
122	M130A	Z	0	0	0	%100

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg))

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-.679	-.679	0	%100
2	M100	Z	-.392	-.392	0	%100
3	M101	X	-.216	-.216	0	%100
4	M101	Z	-.125	-.125	0	%100
5	M102	X	-.216	-.216	0	%100
6	M102	Z	-.125	-.125	0	%100
7	M103	X	-.35	-.35	0	%100
8	M103	Z	-.202	-.202	0	%100
9	M106	X	-.194	-.194	0	%100
10	M106	Z	-.112	-.112	0	%100
11	M107	X	-.778	-.778	0	%100
12	M107	Z	-.449	-.449	0	%100
13	M111	X	-1.05	-1.05	0	%100
14	M111	Z	-.606	-.606	0	%100
15	M112	X	-.357	-.357	0	%100
16	M112	Z	-.206	-.206	0	%100
17	M114	X	-.376	-.376	0	%100
18	M114	Z	-.217	-.217	0	%100
19	M116	X	-1.05	-1.05	0	%100
20	M116	Z	-.606	-.606	0	%100
21	M117	X	-1.426	-1.426	0	%100
22	M117	Z	-.823	-.823	0	%100
23	M119	X	-1.502	-1.502	0	%100
24	M119	Z	-.867	-.867	0	%100
25	M124	X	-.679	-.679	0	%100
26	M124	Z	-.392	-.392	0	%100
27	M125	X	-.216	-.216	0	%100
28	M125	Z	-.125	-.125	0	%100
29	M126	X	-.216	-.216	0	%100
30	M126	Z	-.125	-.125	0	%100
31	M127	X	-.35	-.35	0	%100
32	M127	Z	-.202	-.202	0	%100
33	M130	X	-.778	-.778	0	%100
34	M130	Z	-.449	-.449	0	%100
35	M131	X	-.194	-.194	0	%100
36	M131	Z	-.112	-.112	0	%100
37	M135	X	-1.05	-1.05	0	%100
38	M135	Z	-.606	-.606	0	%100
39	M136	X	-1.426	-1.426	0	%100
40	M136	Z	-.823	-.823	0	%100
41	M138	X	-1.502	-1.502	0	%100
42	M138	Z	-.867	-.867	0	%100
43	M140	X	-1.05	-1.05	0	%100
44	M140	Z	-.606	-.606	0	%100
45	M141	X	-.357	-.357	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F....]	Start Location[ft.%]	End Location[ft.%]
46	M141	Z	-.206	-.206	0	%100
47	M143	X	-.376	-.376	0	%100
48	M143	Z	-.217	-.217	0	%100
49	M148	X	0	0	0	%100
50	M148	Z	0	0	0	%100
51	M149	X	-.865	-.865	0	%100
52	M149	Z	-.5	-.5	0	%100
53	M150	X	-.865	-.865	0	%100
54	M150	Z	-.5	-.5	0	%100
55	M151	X	-1.4	-1.4	0	%100
56	M151	Z	-.808	-.808	0	%100
57	M154	X	-.194	-.194	0	%100
58	M154	Z	-.112	-.112	0	%100
59	M155	X	-.194	-.194	0	%100
60	M155	Z	-.112	-.112	0	%100
61	M159	X	0	0	0	%100
62	M159	Z	0	0	0	%100
63	M160	X	-.357	-.357	0	%100
64	M160	Z	-.206	-.206	0	%100
65	M162	X	-.376	-.376	0	%100
66	M162	Z	-.217	-.217	0	%100
67	M164	X	0	0	0	%100
68	M164	Z	0	0	0	%100
69	M165	X	-.357	-.357	0	%100
70	M165	Z	-.206	-.206	0	%100
71	M167	X	-.376	-.376	0	%100
72	M167	Z	-.217	-.217	0	%100
73	M172	X	-.18	-.18	0	%100
74	M172	Z	-.104	-.104	0	%100
75	MP1A	X	-.554	-.554	0	%100
76	MP1A	Z	-.32	-.32	0	%100
77	MP2A	X	-.671	-.671	0	%100
78	MP2A	Z	-.387	-.387	0	%100
79	MP3A	X	-.554	-.554	0	%100
80	MP3A	Z	-.32	-.32	0	%100
81	MP4A	X	-.554	-.554	0	%100
82	MP4A	Z	-.32	-.32	0	%100
83	M181	X	-.18	-.18	0	%100
84	M181	Z	-.104	-.104	0	%100
85	MP1C	X	-.554	-.554	0	%100
86	MP1C	Z	-.32	-.32	0	%100
87	MP2C	X	-.671	-.671	0	%100
88	MP2C	Z	-.387	-.387	0	%100
89	MP3C	X	-.554	-.554	0	%100
90	MP3C	Z	-.32	-.32	0	%100
91	MP4C	X	-.554	-.554	0	%100
92	MP4C	Z	-.32	-.32	0	%100
93	M190	X	-.718	-.718	0	%100
94	M190	Z	-.415	-.415	0	%100
95	MP1B	X	-.554	-.554	0	%100
96	MP1B	Z	-.32	-.32	0	%100
97	MP2B	X	-.671	-.671	0	%100
98	MP2B	Z	-.387	-.387	0	%100
99	MP3B	X	-.554	-.554	0	%100
100	MP3B	Z	-.32	-.32	0	%100
101	MP4B	X	-.554	-.554	0	%100
102	MP4B	Z	-.32	-.32	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 75 : Structure Wm (300 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft.]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
103	M101A	X	-.453	-.453	0	%100
104	M101A	Z	-.262	-.262	0	%100
105	M102A	X	-.213	-.213	0	%100
106	M102A	Z	-.123	-.123	0	%100
107	M116A	X	-.168	-.168	0	%100
108	M116A	Z	-.097	-.097	0	%100
109	M120A	X	-.168	-.168	0	%100
110	M120A	Z	-.097	-.097	0	%100
111	M125A	X	-.671	-.671	0	%100
112	M125A	Z	-.387	-.387	0	%100
113	M132A	X	-.98	-.98	0	%100
114	M132A	Z	-.566	-.566	0	%100
115	M133A	X	-.98	-.98	0	%100
116	M133A	Z	-.566	-.566	0	%100
117	M134A	X	-.888	-.888	0	%100
118	M134A	Z	-.513	-.513	0	%100
119	M125B	X	-.213	-.213	0	%100
120	M125B	Z	-.123	-.123	0	%100
121	M130A	X	-.852	-.852	0	%100
122	M130A	Z	-.492	-.492	0	%100

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg))

	Member Label	Direction	Start Magnitude[lb/ft.]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
1	M100	X	-.131	-.131	0	%100
2	M100	Z	-.226	-.226	0	%100
3	M101	X	-.375	-.375	0	%100
4	M101	Z	-.649	-.649	0	%100
5	M102	X	-.375	-.375	0	%100
6	M102	Z	-.649	-.649	0	%100
7	M103	X	-.606	-.606	0	%100
8	M103	Z	-1.05	-1.05	0	%100
9	M106	X	0	0	0	%100
10	M106	Z	0	0	0	%100
11	M107	X	-.337	-.337	0	%100
12	M107	Z	-.583	-.583	0	%100
13	M111	X	-.202	-.202	0	%100
14	M111	Z	-.35	-.35	0	%100
15	M112	X	0	0	0	%100
16	M112	Z	0	0	0	%100
17	M114	X	0	0	0	%100
18	M114	Z	0	0	0	%100
19	M116	X	-.202	-.202	0	%100
20	M116	Z	-.35	-.35	0	%100
21	M117	X	-.618	-.618	0	%100
22	M117	Z	-1.07	-1.07	0	%100
23	M119	X	-.65	-.65	0	%100
24	M119	Z	-1.127	-1.127	0	%100
25	M124	X	-.522	-.522	0	%100
26	M124	Z	-.905	-.905	0	%100
27	M125	X	0	0	0	%100
28	M125	Z	0	0	0	%100
29	M126	X	0	0	0	%100
30	M126	Z	0	0	0	%100
31	M127	X	0	0	0	%100
32	M127	Z	0	0	0	%100
33	M130	X	-.337	-.337	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
34	M130	Z	-583	-583	0	%100
35	M131	X	-337	-337	0	%100
36	M131	Z	-583	-583	0	%100
37	M135	X	-808	-808	0	%100
38	M135	Z	-1.4	-1.4	0	%100
39	M136	X	-618	-618	0	%100
40	M136	Z	-1.07	-1.07	0	%100
41	M138	X	-.65	-.65	0	%100
42	M138	Z	-1.127	-1.127	0	%100
43	M140	X	-808	-808	0	%100
44	M140	Z	-1.4	-1.4	0	%100
45	M141	X	-618	-618	0	%100
46	M141	Z	-1.07	-1.07	0	%100
47	M143	X	-.65	-.65	0	%100
48	M143	Z	-1.127	-1.127	0	%100
49	M148	X	-.131	-.131	0	%100
50	M148	Z	-.226	-.226	0	%100
51	M149	X	-.375	-.375	0	%100
52	M149	Z	-.649	-.649	0	%100
53	M150	X	-.375	-.375	0	%100
54	M150	Z	-.649	-.649	0	%100
55	M151	X	-.606	-.606	0	%100
56	M151	Z	-1.05	-1.05	0	%100
57	M154	X	-.337	-.337	0	%100
58	M154	Z	-.583	-.583	0	%100
59	M155	X	0	0	0	%100
60	M155	Z	0	0	0	%100
61	M159	X	-.202	-.202	0	%100
62	M159	Z	-.35	-.35	0	%100
63	M160	X	-.618	-.618	0	%100
64	M160	Z	-1.07	-1.07	0	%100
65	M162	X	-.65	-.65	0	%100
66	M162	Z	-1.127	-1.127	0	%100
67	M164	X	-.202	-.202	0	%100
68	M164	Z	-.35	-.35	0	%100
69	M165	X	0	0	0	%100
70	M165	Z	0	0	0	%100
71	M167	X	0	0	0	%100
72	M167	Z	0	0	0	%100
73	M172	X	-.311	-.311	0	%100
74	M172	Z	-.539	-.539	0	%100
75	MP1A	X	-.32	-.32	0	%100
76	MP1A	Z	-.554	-.554	0	%100
77	MP2A	X	-.387	-.387	0	%100
78	MP2A	Z	-.671	-.671	0	%100
79	MP3A	X	-.32	-.32	0	%100
80	MP3A	Z	-.554	-.554	0	%100
81	MP4A	X	-.32	-.32	0	%100
82	MP4A	Z	-.554	-.554	0	%100
83	M181	X	0	0	0	%100
84	M181	Z	0	0	0	%100
85	MP1C	X	-.32	-.32	0	%100
86	MP1C	Z	-.554	-.554	0	%100
87	MP2C	X	-.387	-.387	0	%100
88	MP2C	Z	-.671	-.671	0	%100
89	MP3C	X	-.32	-.32	0	%100
90	MP3C	Z	-.554	-.554	0	%100



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 76 : Structure Wm (330 Deg)) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
91	MP4C	X	-32	-32	0	%100
92	MP4C	Z	-554	-554	0	%100
93	M190	X	-311	-311	0	%100
94	M190	Z	-539	-539	0	%100
95	MP1B	X	-32	-32	0	%100
96	MP1B	Z	-554	-554	0	%100
97	MP2B	X	-387	-387	0	%100
98	MP2B	Z	-671	-671	0	%100
99	MP3B	X	-32	-32	0	%100
100	MP3B	Z	-554	-554	0	%100
101	MP4B	X	-32	-32	0	%100
102	MP4B	Z	-554	-554	0	%100
103	M101A	X	-262	-262	0	%100
104	M101A	Z	-453	-453	0	%100
105	M102A	X	-369	-369	0	%100
106	M102A	Z	-639	-639	0	%100
107	M116A	X	-291	-291	0	%100
108	M116A	Z	-503	-503	0	%100
109	M120A	X	0	0	0	%100
110	M120A	Z	0	0	0	%100
111	M125A	X	-291	-291	0	%100
112	M125A	Z	-503	-503	0	%100
113	M132A	X	-53	-53	0	%100
114	M132A	Z	-919	-919	0	%100
115	M133A	X	-584	-584	0	%100
116	M133A	Z	-1.011	-1.011	0	%100
117	M134A	X	-53	-53	0	%100
118	M134A	Z	-919	-919	0	%100
119	M125B	X	0	0	0	%100
120	M125B	Z	0	0	0	%100
121	M130A	X	-369	-369	0	%100
122	M130A	Z	-639	-639	0	%100

Member Distributed Loads (BLC 87 : BLC 39 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M130	Y	-1.664	-4.227	0	.832
2	M130	Y	-4.227	-6.899	.832	1.665
3	M130	Y	-6.899	-8.187	1.665	2.497
4	M130	Y	-8.187	-6.544	2.497	3.329
5	M130	Y	-6.544	-3.463	3.329	4.162
6	M131	Y	-3.462	-6.572	0	.832
7	M131	Y	-6.572	-8.261	.832	1.665
8	M131	Y	-8.261	-7.048	1.665	2.497
9	M131	Y	-7.048	-4.428	2.497	3.329
10	M131	Y	-4.428	-1.883	3.329	4.162
11	M106	Y	-1.879	-4.428	0	.832
12	M106	Y	-4.428	-7.042	.832	1.665
13	M106	Y	-7.042	-8.256	1.665	2.497
14	M106	Y	-8.256	-6.578	2.497	3.329
15	M106	Y	-6.578	-3.47	3.329	4.162
16	M107	Y	-3.463	-6.545	0	.832
17	M107	Y	-6.545	-8.189	.832	1.665
18	M107	Y	-8.189	-6.9	1.665	2.497
19	M107	Y	-6.9	-4.227	2.497	3.329
20	M107	Y	-4.227	-1.665	3.329	4.162
21	M154	Y	-1.879	-4.428	0	.832



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 87 : BLC 39 Transient Area Loads) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
22	M154	Y	-4.428	-7.042	.832	1.665
23	M154	Y	-7.042	-8.256	1.665	2.497
24	M154	Y	-8.256	-6.578	2.497	3.329
25	M154	Y	-6.578	-3.47	3.329	4.162
26	M155	Y	-3.463	-6.545	0	.832
27	M155	Y	-6.545	-8.189	.832	1.665
28	M155	Y	-8.189	-6.9	1.665	2.497
29	M155	Y	-6.9	-4.227	2.497	3.329
30	M155	Y	-4.227	-1.665	3.329	4.162

Member Distributed Loads (BLC 88 : BLC 40 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
1	M130	Y	-3.224	-8.193	0	.832
2	M130	Y	-8.193	-13.372	.832	1.665
3	M130	Y	-13.372	-15.868	1.665	2.497
4	M130	Y	-15.868	-12.683	2.497	3.329
5	M130	Y	-12.683	-6.712	3.329	4.162
6	M131	Y	-6.71	-12.737	0	.832
7	M131	Y	-12.737	-16.011	.832	1.665
8	M131	Y	-16.011	-13.659	1.665	2.497
9	M131	Y	-13.659	-8.581	2.497	3.329
10	M131	Y	-8.581	-3.649	3.329	4.162
11	M106	Y	-3.642	-8.582	0	.832
12	M106	Y	-8.582	-13.647	.832	1.665
13	M106	Y	-13.647	-16.001	1.665	2.497
14	M106	Y	-16.001	-12.749	2.497	3.329
15	M106	Y	-12.749	-6.725	3.329	4.162
16	M107	Y	-6.711	-12.684	0	.832
17	M107	Y	-12.684	-15.87	.832	1.665
18	M107	Y	-15.87	-13.372	1.665	2.497
19	M107	Y	-13.372	-8.192	2.497	3.329
20	M107	Y	-8.192	-3.228	3.329	4.162
21	M154	Y	-3.642	-8.582	0	.832
22	M154	Y	-8.582	-13.647	.832	1.665
23	M154	Y	-13.647	-16.001	1.665	2.497
24	M154	Y	-16.001	-12.749	2.497	3.329
25	M154	Y	-12.749	-6.725	3.329	4.162
26	M155	Y	-6.711	-12.684	0	.832
27	M155	Y	-12.684	-15.87	.832	1.665
28	M155	Y	-15.87	-13.372	1.665	2.497
29	M155	Y	-13.372	-8.192	2.497	3.329
30	M155	Y	-8.192	-3.228	3.329	4.162

Member Distributed Loads (BLC 89 : BLC 84 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[ft.%]	End Location[ft.%]
1	M130	Y	-.07	-.179	0	.832
2	M130	Y	-.179	-.292	.832	1.665
3	M130	Y	-.292	-.346	1.665	2.497
4	M130	Y	-.346	-.277	2.497	3.329
5	M130	Y	-.277	-.147	3.329	4.162
6	M131	Y	-.146	-.278	0	.832
7	M131	Y	-.278	-.35	.832	1.665
8	M131	Y	-.35	-.298	1.665	2.497
9	M131	Y	-.298	-.187	2.497	3.329
10	M131	Y	-.187	-.08	3.329	4.162
11	M106	Y	-.08	-.187	0	.832



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 89 : BLC 84 Transient Area Loads) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
12	M106	Y	-.187	-.298	.832	1.665
13	M106	Y	-.298	-.349	1.665	2.497
14	M106	Y	-.349	-.278	2.497	3.329
15	M106	Y	-.278	-.147	3.329	4.162
16	M107	Y	-.147	-.277	0	.832
17	M107	Y	-.277	-.346	.832	1.665
18	M107	Y	-.346	-.292	1.665	2.497
19	M107	Y	-.292	-.179	2.497	3.329
20	M107	Y	-.179	-.07	3.329	4.162
21	M154	Y	-.08	-.187	0	.832
22	M154	Y	-.187	-.298	.832	1.665
23	M154	Y	-.298	-.349	1.665	2.497
24	M154	Y	-.349	-.278	2.497	3.329
25	M154	Y	-.278	-.147	3.329	4.162
26	M155	Y	-.147	-.277	0	.832
27	M155	Y	-.277	-.346	.832	1.665
28	M155	Y	-.346	-.292	1.665	2.497
29	M155	Y	-.292	-.179	2.497	3.329
30	M155	Y	-.179	-.07	3.329	4.162

Member Distributed Loads (BLC 90 : BLC 85 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M130	Z	-.176	-.446	0	.832
2	M130	Z	-.446	-.728	.832	1.665
3	M130	Z	-.728	-.864	1.665	2.497
4	M130	Z	-.864	-.691	2.497	3.329
5	M130	Z	-.691	-.366	3.329	4.162
6	M131	Z	-.366	-.694	0	.832
7	M131	Z	-.694	-.872	.832	1.665
8	M131	Z	-.872	-.744	1.665	2.497
9	M131	Z	-.744	-.467	2.497	3.329
10	M131	Z	-.467	-.199	3.329	4.162
11	M106	Z	-.198	-.468	0	.832
12	M106	Z	-.468	-.743	.832	1.665
13	M106	Z	-.743	-.872	1.665	2.497
14	M106	Z	-.872	-.694	2.497	3.329
15	M106	Z	-.694	-.366	3.329	4.162
16	M107	Z	-.366	-.691	0	.832
17	M107	Z	-.691	-.865	.832	1.665
18	M107	Z	-.865	-.728	1.665	2.497
19	M107	Z	-.728	-.446	2.497	3.329
20	M107	Z	-.446	-.176	3.329	4.162
21	M154	Z	-.198	-.468	0	.832
22	M154	Z	-.468	-.743	.832	1.665
23	M154	Z	-.743	-.872	1.665	2.497
24	M154	Z	-.872	-.694	2.497	3.329
25	M154	Z	-.694	-.366	3.329	4.162
26	M155	Z	-.366	-.691	0	.832
27	M155	Z	-.691	-.865	.832	1.665
28	M155	Z	-.865	-.728	1.665	2.497
29	M155	Z	-.728	-.446	2.497	3.329
30	M155	Z	-.446	-.176	3.329	4.162

Member Distributed Loads (BLC 91 : BLC 86 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[ft.%]	End Location[ft.%]
1	M130	X	.176	.446	0	.832



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Distributed Loads (BLC 91 : BLC 86 Transient Area Loads) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F....]	Start Location[ft.%]	End Location[ft.%]
2	M130	X	.446	.728	.832	1.665
3	M130	X	.728	.864	1.665	2.497
4	M130	X	.864	.691	2.497	3.329
5	M130	X	.691	.366	3.329	4.162
6	M131	X	.366	.694	0	.832
7	M131	X	.694	.872	.832	1.665
8	M131	X	.872	.744	1.665	2.497
9	M131	X	.744	.467	2.497	3.329
10	M131	X	.467	.199	3.329	4.162
11	M106	X	.198	.468	0	.832
12	M106	X	.468	.743	.832	1.665
13	M106	X	.743	.872	1.665	2.497
14	M106	X	.872	.694	2.497	3.329
15	M106	X	.694	.366	3.329	4.162
16	M107	X	.366	.691	0	.832
17	M107	X	.691	.865	.832	1.665
18	M107	X	.865	.728	1.665	2.497
19	M107	X	.728	.446	2.497	3.329
20	M107	X	.446	.176	3.329	4.162
21	M154	X	.198	.468	0	.832
22	M154	X	.468	.743	.832	1.665
23	M154	X	.743	.872	1.665	2.497
24	M154	X	.872	.694	2.497	3.329
25	M154	X	.694	.366	3.329	4.162
26	M155	X	.366	.691	0	.832
27	M155	X	.691	.865	.832	1.665
28	M155	X	.865	.728	1.665	2.497
29	M155	X	.728	.446	2.497	3.329
30	M155	X	.446	.176	3.329	4.162

Member Area Loads (BLC 39 : Structure D)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[ksf]
1	N176	N200	N198	N175	Y	Two Way	-.005
2	N147	N171	N169	N146	Y	Two Way	-.005
3	N205	N229	N227	N204	Y	Two Way	-.005

Member Area Loads (BLC 40 : Structure Di)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[ksf]
1	N176	N200	N198	N175	Y	Two Way	-.01
2	N147	N171	N169	N146	Y	Two Way	-.01
3	N205	N229	N227	N204	Y	Two Way	-.01

Member Area Loads (BLC 84 : Structure Ev)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[ksf]
1	N176	N200	N198	N175	Y	Two Way	-.00022
2	N147	N171	N169	N146	Y	Two Way	-.00022
3	N205	N229	N227	N204	Y	Two Way	-.00022

Member Area Loads (BLC 85 : Structure Eh (0 Deg))

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[ksf]
1	N176	N200	N198	N175	Z	Two Way	-.000549
2	N147	N171	N169	N146	Z	Two Way	-.000549
3	N205	N229	N227	N204	Z	Two Way	-.000549



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Member Area Loads (BLC 86 : Structure Eh (90 Deg))

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[ksf]
1	N176	N200	N198	N175	X	Two Way	.000549
2	N147	N171	N169	N146	X	Two Way	.000549
3	N205	N229	N227	N204	X	Two Way	.000549

Envelope AISC 15th(360-16): LRFD Steel Code Checks

Member	Shape	Code Check	L...	LC	Shear C...	Loc...	phi*P...	phi*P...	phi*M...	phi*M...	Eqn		
1	M100	HSS4X4...	.230	2...	13	.075	2.9...	y 23	95848..	106812	12.662	12.662	... H1-1b
2	M101	L3X3X3	.545	2...	14	.468	.223	z 8	26973..	35316	1.32	2.833	... H2-1
3	M102	L3X3X3	.567	0	13	.429	2.1...	z 7	26973..	35316	1.32	2.833	... H2-1
4	M103	PL3/8x6	.292	.5...	1	.247	.516	y 23	36639..	72900	.57	9.113	... H1-1b
5	M106	L2x2x3	.351	4...	8	.027	0	y 19	9823...	23392...	.558	1.075	... H2-1
6	M107	L2x2x3	.307	0	6	.028	4.1...	y 19	9823...	23392...	.558	1.075	... H2-1
7	M111	PL3/8x6	.221	0	4	.216	0	y 18	70677..	72900	.57	9.113	... H1-1b
8	M112	PL3/8x6	.224	.1...	8	.106	0	y 14	71601..	72900	.57	9.113	... H1-1b
9	M114	PL3/8x6	.095	.1...	1	.320	0	y 24	72311..	72900	.57	9.113	... H1-1b
10	M116	PL3/8x6	.206	0	9	.218	0	y 17	70677..	72900	.57	9.113	... H1-1b
11	M117	PL3/8x6	.204	.1...	7	.111	0	y 13	71601..	72900	.57	9.113	... H1-1b
12	M119	PL3/8x6	.099	.1...	1	.217	0	y 2	72311..	72900	.57	9.113	... H1-1b
13	M124	HSS4X4...	.231	2...	21	.073	2.9...	y 19	95848..	106812	12.662	12.662	... H1-1b
14	M125	L3X3X3	.551	2...	22	.489	.223	z 4	26973..	35316	1.32	2.833	... H2-1
15	M126	L3X3X3	.568	0	21	.453	2.1...	z 3	26973..	35316	1.32	2.833	... H2-1
16	M127	PL3/8x6	.309	.5...	9	.247	.516	y 19	36639..	72900	.57	9.113	... H1-1b
17	M130	L2x2x3	.364	4...	4	.027	0	y 15	9823...	23392...	.558	1.075	... H2-1
18	M131	L2x2x3	.320	0	3	.029	4.1...	y 15	9823...	23392...	.558	1.076	... H2-1
19	M135	PL3/8x6	.195	0	12	.219	0	y 14	70677..	72900	.57	9.113	... H1-1b
20	M136	PL3/8x6	.233	.1...	4	.107	0	y 22	71601..	72900	.57	9.113	... H1-1b
21	M138	PL3/8x6	.100	.1...	9	.319	0	y 20	72311..	72900	.57	9.113	... H1-1b
22	M140	PL3/8x6	.185	0	5	.217	0	y 15	70677..	72900	.57	9.113	... H1-1b
23	M141	PL3/8x6	.217	.1...	3	.111	0	y 21	71601..	72900	.57	9.113	... H1-1b
24	M143	PL3/8x6	.105	.1...	9	.241	0	y 49	72311..	72900	.57	9.113	... H1-1b
25	M148	HSS4X4...	.230	2...	17	.102	2.9...	y 27	95848..	106812	12.662	12.662	... H1-1b
26	M149	L3X3X3	.549	2...	18	.463	.223	z 11	26973..	35316	1.32	2.833	... H2-1
27	M150	L3X3X3	.567	0	17	.442	2.1...	z 11	26973..	35316	1.32	2.833	... H2-1
28	M151	PL3/8x6	.305	.5...	5	.267	.516	y 27	36639..	72900	.57	9.113	... H1-1b
29	M154	L2x2x3	.345	4...	12	.027	0	y 23	9823...	23392...	.558	1.075	... H2-1
30	M155	L2x2x3	.318	0	10	.028	4.1...	y 23	9823...	23392...	.558	1.075	... H2-1
31	M159	PL3/8x6	.220	0	8	.218	0	y 22	70677..	72900	.57	9.113	... H1-1b
32	M160	PL3/8x6	.219	.1...	11	.107	0	y 18	71601..	72900	.57	9.113	... H1-1b
33	M162	PL3/8x6	.097	.1...	5	.449	0	y 28	72311..	72900	.57	9.113	... H1-1b
34	M164	PL3/8x6	.200	0	1	.216	0	y 23	70677..	72900	.57	9.113	... H1-1b
35	M165	PL3/8x6	.214	.1...	11	.111	0	y 17	71601..	72900	.57	9.113	... H1-1b
36	M167	PL3/8x6	.103	.1...	5	.212	0	y 6	72311..	72900	.57	9.113	... H1-1b
37	M172	PIPE 3.0	.155	8...	39	.068	7.9...	8	28250..	65205	5.749	5.749	... H1-1b
38	MP1A	PIPE 2.0	.267	4	4	.078	4	6	14916..	32130	1.872	1.872	... H1-1b
39	MP2A	PIPE 2.5	.298	4...	4	.111	4.6...	11	30038..	50715	3.596	3.596	... H1-1b
40	MP3A	PIPE 2.0	.372	4...	10	.089	1.9...	8	14916..	32130	1.872	1.872	... H1-1b
41	MP4A	PIPE 2.0	.263	4	10	.073	4	12	14916..	32130	1.872	1.872	... H1-1b
42	M181	PIPE 3.0	.143	8...	6	.072	4.1...	3	28250..	65205	5.749	5.749	... H1-1b
43	MP1C	PIPE 2.0	.253	4	12	.079	4	2	14916..	32130	1.872	1.872	... H1-1b
44	MP2C	PIPE 2.5	.284	4...	12	.113	4.6...	7	30038..	50715	3.596	3.596	... H1-1b
45	MP3C	PIPE 2.0	.357	4...	6	.091	1.9...	4	14916..	32130	1.872	1.872	... H1-1b
46	MP4C	PIPE 2.0	.251	4	6	.075	4	8	14916..	32130	1.872	1.872	... H1-1b
47	M190	PIPE 3.0	.151	8...	2	.064	7.9...	12	28250..	65205	5.749	5.749	... H1-1b
48	MP1B	PIPE 2.0	.267	4	8	.082	.5	5	14916..	32130	1.872	1.872	... H1-1b
49	MP2B	PIPE 2.5	.294	4...	8	.113	4.6...	3	30038..	50715	3.596	3.596	... H1-1b



Company :
 Designer :
 Job Number :
 Model Name :

Sept 27, 2023
 2:55 PM
 Checked By: _____

Envelope AISC 15th(360-16): LRFD Steel Code Checks (Continued)

Member	Shape	Code Check	L	LC	Shear C	Loc	phi*P	phi*P	phi*M	phi*M	Eqn
50	MP3B PIPE 2.0	.364	4	2	.089	1.9	1214916	32130	1.872	1.872	H1-1b
51	MP4B PIPE 2.0	.247	4	2	.074	4	414916	32130	1.872	1.872	H1-1b
52	M101A PIPE 2.0	.097	2	6	.019	2	628843	32130	1.872	1.872	H1-1b
53	M102A L3X3X4	.315	0	3	.030	0	1041921	46656	1.688	3.756	H2-1
54	M116A PIPE 2.5	.156	2	10	.083	10	614558	50715	3.596	3.596	H1-1b
55	M120A PIPE 2.5	.149	8	5	.086	10	214558	50715	3.596	3.596	H1-1b
56	M125A PIPE 2.5	.151	8	2	.091	10	1014558	50715	3.596	3.596	H1-1b
57	M132A LL3x3x3	.090	0	13	.006	0	1047907	70632	5.543	3.751	H1-1
58	M133A LL3x3x3	.090	0	21	.006	4.2	647907	70632	5.543	3.751	H1-1
59	M134A LL3x3x3	.089	0	17	.006	4.2	247907	70632	5.543	3.751	H1-1
60	M125B L3X3X4	.311	0	11	.029	0	1141921	46656	1.688	3.756	H2-1
61	M130A L3X3X4	.309	0	7	.029	0	241921	46656	1.688	3.756	H2-1

Envelope Joint Reactions

Joint	X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC		
1	N144A	max	1192.191	10	309.675	7	4798.638	1	.139	7	1.806	4	.238	22
2		min	-1179.179	4	-791.422	1	-2312.267	7	-.593	1	-1.779	10	-.012	3
3	N173	max	4189.451	9	268.778	3	1100.481	3	.466	19	1.534	12	.599	9
4		min	-2068.204	3	-832.303	9	-2342.265	9	-.086	37	-1.508	6	-.245	3
5	N202	max	1870.427	11	243.08	11	1187.418	11	.332	5	1.664	8	.098	10
6		min	-4006.857	5	-931.231	29	-2403.945	5	-.312	47	-1.639	2	-.918	28
7	N192A	max	44.784	10	3063.455	13	-114.781	7	0	75	0	4	0	10
8		min	-44.835	4	92.815	7	-3014.987	13	0	1	0	10	0	4
9	N194A	max	-42.356	3	3058.307	21	1504.867	21	0	6	0	12	0	12
10		min	-2606.627	21	26.937	3	24.453	3	0	12	0	6	0	6
11	N196A	max	2589.405	17	3038.531	17	1495.12	17	0	8	0	8	0	8
12		min	88.689	11	80.445	11	51.209	11	0	2	0	2	0	2
13	Totals:	max	5044.312	10	6522.643	20	4859.8	1						
14		min	-5044.315	4	2206.464	65	-4859.793	7						


I. Mount-to-Tower Connection Check

Custom Orientation Required

Tower Connection Bolt Checks


Bolt Orientation

Bolt Quantity per Reaction:	4
d_x (in) (Delta X of typ. bolt config. sketch):	6
d_y (in) (Delta Y of typ. bolt config. sketch):	6
Bolt Type:	A325N
Bolt Diameter (in):	0.625
Required Tensile Strength / bolt (kips):	2.5
Required Shear Strength / bolt (kips):	0.3
Tensile Capacity / bolt (kips):	20.7
Shear Capacity / bolt (kips):	12.4
Bolt Overall Utilization:	11.9%



Tower Connection Baseplate Checks


Connecting Standoff Member Shape:	Rect Tube
Weld Stiffener Configuration:	No Stiffeners
Plate Width, D_x (in):	10
Plate Height, D_y (in):	10
W_1 (in):	4
W_2 (in):	4
Member Thickness (in):	0.1875
Stiffener location a_1 (in):	
Stiffener location b_1 (in):	
Stiffener location a_2 (in):	
Stiffener location b_2 (in):	
F_y (ksi, plate):	36
Plate Thickness (in):	0.5
Length of Yield Line, L_y (in):	6.29
Bolt Eccentricity, e (in):	1.59
M_u (kip-in):	3.93
$\Phi * M_n$ (kip-in):	12.73
Plate Bending Utilization:	30.8%



Tower Connection Weld Checks

Weld Shape:
Weld Stiffener Configuration:
Weld Size (1/16 in):
W1 (in):
W2 (in):
Weld Total Length (in):
 Z_x (in³/in):
 Z_y (in³/in):
 J_p (in⁴/in):
 c_x (in)
 c_y (in)
Required combined strength (kip/in):
Weld Capacity (kip/in):
Weld Utilization:

Yes
Rectangle
None
4
4
4
16.00
21.33
21.33
85.33
2.1875
2.1875
0.84
5.57
15.1%






MOUNT MODIFICATION DRAWINGS
EXISTING 12.50' PLATFORM

TOWER OWNER: SBA COMMUNICATIONS
TOWER OWNER SITE NUMBER: CT11794

CARRIER SITE NAME: ROCKY NECK CT
CARRIER SITE NUMBER: 5000122067
FUZE ID: 2505529

49 BRAINERD ROAD
NIANTIC, CT 06357
NEW LONDON COUNTY

LATITUDE: 41.307583° N
LONGITUDE: 72.223917° W



www.colliersengineering.com

Colliers Engineering & Design, Inc. is an Equal Opportunity Employer. Minorities and women are encouraged to apply. All offers of employment are contingent upon the successful completion of a background check. Colliers Engineering & Design, Inc. is an Equal Opportunity Employer.



FOR YOUR PROTECTION, CALL 811 BEFORE YOU DIG

STAMPED: 21281139

NO.	DATE	DESCRIPTION	BY
1	01/11/2023	ISSUED FOR PERMIT	PA
2	01/11/2023	ISSUED FOR PERMIT	PA
3	01/11/2023	ISSUED FOR PERMIT	PA
4	01/11/2023	ISSUED FOR PERMIT	PA
5	01/11/2023	ISSUED FOR PERMIT	PA
6	01/11/2023	ISSUED FOR PERMIT	PA
7	01/11/2023	ISSUED FOR PERMIT	PA
8	01/11/2023	ISSUED FOR PERMIT	PA
9	01/11/2023	ISSUED FOR PERMIT	PA
10	01/11/2023	ISSUED FOR PERMIT	PA




COLLIERS ENGINEERING & DESIGN, INC.
REGISTERED PROFESSIONAL ENGINEER
LICENSE NO. 21281139
STATE OF CONNECTICUT

UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE REGISTERED PROFESSIONAL ENGINEER, NO OTHER PERSON SHALL BE PERMITTED TO SEAL THIS DRAWING.

SITE NAME:

ROCKY NECK CT
5000122067
49 BRAINERD ROAD
NIANTIC, CT 06357
NEW LONDON COUNTY



TITLE SHEET

ST-1

NOTE: DO NOT SCALE DRAWING FOR CONSTRUCTION

SHEET	DESCRIPTION
ST-1	TITLE SHEET
SC0M-1	BILL OF MATERIALS
SC0M-1	GENERAL NOTES
SC1-1	FOUNDING FACILITY DETAIL
35-1	MODIFICATION DETAILS
35-2	FOUNDING PHOTO
	SPECIFICATION SHEETS

APPLICANT/LESSEE	PROJECT INFORMATION
COMPANY: VERIZON WIRELESS CLIENT REPRESENTATIVE	VERIZON WIRELESS CLIENT REPRESENTATIVE
COMPANY: VERIZON WIRELESS PROJECT MANAGER	VERIZON WIRELESS PROJECT MANAGER
COMPANY: COLLIER ENGINEERING & DESIGN CONTACT: PETER ALBANO PHONE: 856.797.0412 E-MAIL: PETER.ALBANO@COLLIERSENG.COM	COLLIERS ENGINEERING & DESIGN PETER ALBANO 856.797.0412 PETER.ALBANO@COLLIERSENG.COM
CONTRACTOR PMI REQUIREMENTS	HITTS/PHI/VZWSHART.COM PROJECT #: 5000122067 ANALYSIS DATE: 10/11/2023
PHI LOCATION: PROJECT #: VZM LOCATION CODE (MDO): ANALYSIS DATE:	
PHI REQUIREMENTS BREACHED WITHIN MOUNT MODIFICATION REPORT	

DESIGN CRITERIA
WIND LOADS BASIC WIND SPEED (3 SECOND GUST), V = 130 MPH TOPOGRAPHIC METHOD: II TOPOGRAPHIC CONSIDERED: NO MEAN BASE ELEVATION (AMSL) = 13.5'
ICE LOADS ICE WIND SPEED (3 SECOND GUST), V = 50 MPH ICE THICKNESS = 1.00 IN
SEISMIC LOADS SEISMIC DESIGN CATEGORY: B SHORT TERM MCBR GROUND MOTION, S _w = J198 LONG TERM MCBR GROUND MOTION, S _w = 003

**COPYRIGHT ©2023
COLLIERS ENGINEERING & DESIGN
ALL RIGHTS RESERVED**
THE DRAWING AND ALL THE INFORMATION CONTAINED HEREIN IS THE PROPERTY OF COLLIER ENGINEERING & DESIGN, INC. AND WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THE DRAWING MAY NOT BE COPIED, REPRODUCED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT OF COLLIER ENGINEERING & DESIGN.

BILL OF MATERIALS

SECTION 1 - VZWSMART KITS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS)	WEIGHT (LBS)
1		VZWSMART-PLK1	SUPPORT RAIL KIT	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE STRUCTURAL STEEL NOTES ON SHEET SGN-L1.	504	504
1		VZWSMART-PLK5	KICKER KIT	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE STRUCTURAL STEEL NOTES ON SHEET SGN-L1.	291	291
1		VZWSMART-PLK7	HONOROLE COLLAR MOUNT ASSEMBLY		150	150
1		VZWSMART-HSK6	BACK TO BACK CROSSOVER PLATE		34	34
3	VZWSMART	VZWSMART-P40-27BX066	96" LONG, PIPE 2.5 SC-H40 (2.875" O.D. X 0.208" THK)		44	132
1		VZWSMART-P40-23BX048	48" LONG, PIPE 2 SC-H40 (2.375" O.D. X 0.154" THK)		15	15

SECTION 2 - OTHER REQUIRED PARTS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS)	WEIGHT (LBS)
3	SITE PRO 1	SP219-4	2.708" TO 3.102" PIPE MOUNT ASSEMBLY	OR EOR APPROVED EQUAL, CONTACT EOR FOR APPROVAL OF SUBSTITUTION.	13	39
1			1/2" 1429 GRA.2 U-BOLTS			

SECTION 3 - REQUIRED SAFETY CLIMB PARTS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS)	WEIGHT (LBS)
1	PERFECT VISION	H42-050-06	STANDOFF CLAMP BRACKET	OR EOR APPROVED EQUIVALENT		
1	PERFECT VISION	PV-CHK-CG-90	WIRE ROPE GUIDE	OR EOR APPROVED EQUIVALENT		
					TOTAL:	1165

NOTES:

- THE MANUFACTURERS LISTED ARE THE APPROVED VENDORS FOR THE VZW MOUNT KITS. EACH MANUFACTURER WILL BE AWARE OF WHICH KITS HAVE BEEN THROUGH THE VZW APPROVAL PROCESS AND THEY ARE IN TURN APPROVED TO SELL. PLEASE NOTE THAT THE MATERIAL UTILIZED ON THE MOUNT MODIFICATIONS WILL BE REVIEWED AS A PART OF THE DESKTOP PMI COMPLETED BY THE SMART TOOL VENDOR. IT WILL BE REQUIRED THAT THE VZW KITS SPECIFIED ARE UTILIZED IN THE MODIFICATIONS.
- ALL MATERIALS REQUIRED FOR THE DESIGNED MODIFICATIONS BUT NOT LISTED IN THIS SHEET ARE ASSUMED TO BE PROVIDED BY THE CONTRACTOR.

VZWSMART KITS - APPROVED VENDORS

COMMSCOPE			
CONTACT	SALVADOR ANGUANO		
PHONE	(817) 394-7192		
EMAIL	SALVADOR.ANGUANO@COMMSCOPE.COM		
WEBSITE	WWW.COMMSCOPE.COM		
METROSITE FABRICATORS, LLC			
CONTACT	KENT BAUER		
PHONE	(706) 335-7045 (O), (706) 982-3788 (H)		
EMAIL	KENT@METROSITELLC.COM		
WEBSITE	METROSITEFABRICATORS.COM		

PERFECTVISION			
CONTACT	WIRELESS SALES		
PHONE	(841) 887-6733		
EMAIL	WWW.PERFECTVISION.COM		
WEBSITE	WIRELESSALES@PERFECTVISION.COM		
SABRE INDUSTRIES, INC.			
CONTACT	ANGIE WEBER		
PHONE	(866) 498-8937		
EMAIL	AKWELCH@SABREINDUSTRIES.COM		
WEBSITE	WWW.SABREITSOLUTIONS.COM		

SITE PRO 1			
CONTACT	PAULA BOSWELL		
PHONE	(972) 236-8943		
EMAIL	PAULA.BOSWELL@VALMONT.COM		
WEBSITE	WWW.SITEPRO1.COM		
NEWAVE			
CONTACT	NEWAVE SALES TEAM		
PHONE	(917) 374-4742		
EMAIL	SALES@NEWAVETC.COM		
WEBSITE	WWW.NEWAVETC.COM		

BETTER METAL, LLC			
CONTACT	DAVID STARBERY		
PHONE	(415) 542-9990 (O), (415) 611-3550 (H)		
EMAIL	DLS@BETTERMETAL.COM		
WEBSITE	WWW.BETTERMETAL.COM		



Engineering & Design
www.collimengineering.com



DATE	DESCRIPTION	BY	CHK



SITE NAME:
ROCKY NECK CT
500022007
49 BRAINERD ROAD
MANTIC, CT 06357
NEW LONDON COUNTY

CONTACT
PHONE
EMAIL
WEBSITE

BILL OF MATERIALS
SBO-M-1

GENERAL NOTES

1. THESE MODIFICATIONS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE TELECOMMUNICATIONS INDUSTRY STANDARD TIA-222-H FOR BIRDS AND SERVICES PROVIDED BY THE CONTRACTOR SHALL CONFORM TO THE ABOVE REFERENCED CODES.
2. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT DAMAGE TO EXISTING STRUCTURES, ANY DAMAGE TO EXISTING STRUCTURES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. DAMAGE DUE TO OTHER CAUSES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
3. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS BEFORE BEGINNING WORK. CORRECTIVE MATERIAL AND REPAIRS OF SHOP DRAWINGS, ANY DISCREPANCIES BETWEEN FIELD CONDITIONS AND THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ENGINEER. IF THE CONTRACTOR DISCOVERS ANY EXISTING CONDITIONS THAT ARE NOT REPRESENTED ON THESE DRAWINGS, OR ANY CONDITIONS THAT WOULD INTERFERE WITH THE INSTALLATION OF THE MODIFICATIONS, NOTIFY THE ENGINEER IMMEDIATELY.
4. IT IS ASSUMED THAT ANY STRUCTURAL MODIFICATION WORK SPECIFIED ON THESE PLANS WILL BE ACCOMPLISHED BY KNOWLEDGEABLE WORKMEN WITH TOWER CONSTRUCTION EXPERIENCE.
5. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION METHODS, MEANS, TECHNIQUES, SEQUENCES, AND PROCEDURES.
6. ALL CONSTRUCTION MEANS AND METHODS, INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE WORK. THE CONTRACTOR SHALL VERIFY AND SHALL MEET ALL THE LATEST REQUIREMENTS AND STANDARDS FOR ALL MATERIALS AND METHODS. ALL RIGGING PLANS SHALL ADHERE TO ANSB/TIA-322 (LATEST EDITION) INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLAS IV CONSTRUCTION.
7. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PROGRAMS IN ACCORDANCE WITH APPLICABLE SAFETY CODES.
8. WORK SHALL ONLY BE PERFORMED DURING DRY DAYS (WINDS LESS THAN 30 MPH). THE STRUCTURE SHOWN ON THE DRAWINGS IS CONTRACTUALLY SOUND ONLY. IN THE COMPLETED FORM, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRENGTH AND STABILITY OF THE STRUCTURE DURING ERECTION. CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORT, SHORING, BRACING AND ANY OTHER STRUCTURAL SYSTEMS AS REQUIRED TO RESIST ALL FORCES THAT MAY OCCUR DURING ERECTION. CONTRACTOR SHALL VERIFY THE STRENGTH OF ALL TEMPORARY SUPPORTS, BRACINGS AND OTHER STRUCTURAL SYSTEMS REQUIRED DURING CONSTRUCTION SHALL REMAIN THE CONTRACTOR'S PROPERTY AFTER THEIR USE.
9. ALL INSTALLATIONS PERFORMED ON THIS STRUCTURE SHALL BE COMPLETED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE STANDARD FOR INSTALLATION, ALTERATION AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, ANS/TIA-322.
10. CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER SUPERVISION OF OWNER. ALL FENCE, STONE, GEO-FABRIC, GROUNDING, AND SURROUNDING GRADE SHALL BE REPLACED AND REPAIRED AS REQUIRED TO ACHIEVE OWNER APPROVAL. POSITIVE DRAINAGE AWAY FROM TOWER SITE SHALL BE MAINTAINED.
11. CONNECTIONS BETWEEN ITEMS SUPPORTED BY THE STRUCTURE AND THE STRUCTURE NOT SPECIFICALLY DETAILED IN THE CONTRACT DOCUMENTS SHALL BE DESIGNED, COORDINATED AND INSPECTED BY A PROFESSIONAL ENGINEER. ALL CALCULATIONS DURING SHOP DRAWING REVIEW, SIGNED AND SEALED CALCULATIONS DURING SHOP DRAWING REVIEW.
12. DO NOT SCALE DRAWINGS.
13. DO NOT USE THESE DRAWINGS FOR ANY OTHER SITE.
14. ALL MATERIAL UTILIZED FOR THIS PROJECT MUST BE NEW AND FREE OF ANY DEFECTS. ANY MATERIAL SUBSTITUTIONS, INCLUDING BUT NOT LIMITED TO ALTERED SIZE AND STRENGTHS, MUST BE APPROVED BY THE OWNER AND ENGINEER IN WRITING.
15. THE MOUNT UNDER NO CIRCUMSTANCES SHOULD BE USED AS A TIE OFF POINT.

STRUCTURAL STEEL


1. DESIGN, DETAILING, FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING PUBLICATIONS EXCEPT AS SPECIFICALLY INDICATED IN THE CONTRACT DOCUMENTS.
 - a. AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) MANUAL OF STEEL CONSTRUCTION (15TH EDITION)
 - b. SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS
 - c. AISC CODE OF STANDARD PRACTICE
2. STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING UNLESS OTHERWISE SHOWN:
 - CHANNELS, ANGLES, PLATES, ETC. ASTM A36 (GR 36)
 - STEEL PIPE ASTM A53 (GR 35)
 - BOLTS ASTM A325
 - NUTS ASTM A563
 - LOCKING STRUCTURAL GRADE
3. ALL SUBSTITUTIONS PROPOSED BY THE CONTRACTOR SHALL BE APPROVED IN WRITING BY THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO ENGINEER FOR VERIFYING THE SUBSTITUTE IS SUITABLE FOR USE AND MEETS ORIGINAL DESIGN CRITERIA. DIFFERENCES FROM THE ORIGINAL DESIGN, INCLUDING MAINTENANCE, REPAIR AND REPLACEMENT, SHALL BE NOTED, ESTIMATE OF COSTS/CREDITS ASSOCIATED WITH THE SUBSTITUTION INCLUDING RE-DESIGN COSTS AND COSTS TO SUB-CONTRACTORS SHALL BE PROVIDED TO THE ENGINEER. CONTRACTOR SHALL PROVIDE ADDITIONAL DOCUMENTATION AND/OR SPECIFICATIONS TO THE ENGINEER AS REQUESTED.
4. PROVIDE STRUCTURAL STEEL SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION.
 - a. SUBMIT SHOP DRAWINGS TO
 - FTEP: ALBANO@COLLUSERSING.COM
 - b. PROVIDE MASER CONSULTING PROJECT # AND MASER CONSULTING PROJECT ENGINEER CONTACT IN THE BODY OF THE EMAIL.
5. DRILL NO HOLES IN ANY NEW OR EXISTING STRUCTURAL STEEL MEMBERS OTHER THAN THOSE SHOWN ON STRUCTURAL DRAWINGS WITHOUT THE APPROVAL OF THE ENGINEER OF RECORD.
6. GALVANIZED ASTM A325 BOLTS SHALL NOT BE RE-USED.
7. ALL NEW STEEL SHALL BE HOT DIPPED GALVANIZED FOR RUL WEATHER PROTECTION. IN ADDITION ALL NEW STEEL SHALL BE PAINTED TO MATCH EXISTING STEEL. CONTRACTOR SHALL OBTAIN WRITTEN PERMISSION TO PROTECT STEEL BY ANY OTHER MEANS.
8. ALL BOLT ASSEMBLIES FOR STRUCTURAL MEMBERS REPRESENTED IN THIS DRAWING REQUIRE LOCKING DEVICES TO BE INSTALLED IN ACCORDANCE WITH TIA-222-H SECTION 4.9.2 REQUIREMENTS.
9. WHERE CONNECTIONS ARE NOT FULLY DETAILED ON THESE DRAWINGS, FABRICATOR SHALL DESIGN CONNECTIONS TO RESIST LOADS AND FORCES WHERE SHOWN ON DRAWINGS, AND AS OUTLINED IN SPECIFICATIONS. FOR MEMBERS BEING REPLACED, PROVIDE NEW BOLTS AND MATCH EXISTING SIZE AND GRADE MAINTAIN AISC REQUIREMENTS FOR MINIMUM BOLT DISTANCE AND SPACING.
10. ALL PROPOSED AND/OR REPLACED BOLTS SHALL BE OF SUFFICIENT LENGTH SUCH THAT THE END OF THE BOLT IS AT LEAST FLUSH WITH THE FACE OF THE NUT. IT IS NOT PERMITTED FOR THE BOLT END TO BE BELOW THE FACE OF THE NUT AFTER TIGHTENING IS COMPLETED.
11. GALVANIZED ASTM A325 BOLTS SHALL NOT BE RE-USED.
12. ALL NEW STEEL SHALL BE HOT DIPPED GALVANIZED FOR RUL WEATHER PROTECTION BY ANY OTHER MEANS.
13. ALL EXISTING PAINTED/GALVANIZED SURFACES DAMAGED DURING REBAR INCLUDING AREAS UNDER STRENGTHENING PLATES SHALL BE WHITE BUSHED CLEAN, REPAIRED BY COLD GALVANIZING (ZINCA OR ZINC COAT), AND REPAINTED TO MATCH THE EXISTING FINISH (IF APPLICABLE).
14. ALL HOLES IN STEEL MEMBERS SHALL BE SIZED 1/16" LARGER THAN THE BOLT DIAMETER. STANDARD HOLES SHALL BE USED UNLESS NOTED OTHERWISE.

BOLT SCHEDULE (IN.)

BOLT DIAMETER	STANDARD HOLE	SHORT SLOT	MIN. EDGE DISTANCE	SPACING
1/2	9/16	9/16 x 1 1/16	7/8	1 1/2
5/8	1 1/16	1 1/16 x 7/8	1 1/8	1 7/8
3/4	1 3/16	1 3/16 x 1	1 1/4	2 1/4
7/8	1 5/16	1 5/16 x 1 1/8	1 1/2	2 5/8
1	1 11/16	1 11/16 x 1 5/16	1 3/4	3


WORKABLE GAGES (IN.)

LEG	GAGE
4	2 1/2
3	2
2 1/2	1 3/4
2	1 1/8



TYP. BOLT ASSEMBLY

- NOTES:**
1. ALL DIMENSIONS REPRESENTED IN THE ABOVE TABLES ARE AISC MINIMUM REQUIREMENTS. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS IN FIELD AND NOTIFY ENGINEER IF DISTANCES ARE LESS THAN THOSE PROVIDED.
 2. THE DIMENSIONS PROVIDED ARE MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS OF PROPOSED MEMBERS REPRESENTED IN THESE DRAWINGS MAY VARY FROM THESE MINIMUM REQUIREMENTS.
 3. SHORTSLOT HOLES SHALL ONLY BE SHOWN AS SPECIFIED IN THE DRAWINGS.
 4. MATCH EXISTING GAGES WHEN DISTANCES ARE COMPROMISED.



Colliers Engineering & Design
www.colliersengineering.com

verizon

811
Call before you dig
1-800-4-A-DAWG

REGISTERED PROFESSIONAL ENGINEER
STATE OF CONNECTICUT
No. 21181129

Professional Engineer Seal for Robert A. Alano, No. 21181129, State of Connecticut.

THIS DOCUMENT IS UNCLASSIFIED UNLESS THEY ARE UNDER THE DIRECTION OF THE NATIONAL ARCHIVES.


SITE NAME:
ROCKY NECK CT
500022067
49 BRAINERD ROAD
MANTIC, CT 06357
NEW LONDON COUNTY

STANDARD
100% Magnification
Drawing is to be used
for construction only.
Colliers Engineering & Design

GENERAL NOTES

SCN-1


NOTE: DO NOT SCALE DRAWINGS FOR CONSTRUCTION



1 CLIMBING FACILITY LOCATION
SCALE: N.T.S.

STRUCTURAL NOTES:

- PER THE MOUNT MAPPING COMPLETED BY STRUCTURAL COMPONENTS, LLC ON 9/10/2021, THE SAFETY CLIMB AND CLIMBING FACILITIES UP TO THE VERIZON MOUNT ELEVATION (145'-07") ARE IN GOOD CONDITION. COLLIER ENGINEERING & DESIGN DOES NOT WARRANT THIS INFORMATION.
- INSTALL SHALL NOT CAUSE HARM TO THE STRUCTURE, CLIMBING FACILITY, SAFETY CLIMB, OR ANY SYSTEM INSTALLED ON THE STRUCTURE. TIMELY NOTICE AND DOCUMENTATION SHALL BE PROVIDED BY CONTRACTORS TO THE EOR (OF STRUCTURAL DESIGN) IF AN OBSTRUCTION WAS REQUIRED TO MEET THE RF SYSTEM DESIGN REQUIREMENTS AND PERFORMANCES.



ITEM #	QTY	PART NUMBER	DESCRIPTIONS
A	1	H4-0601-06	STAY-IN-PLACE MONORAIL BRACKET (PERFECT VISION OR EOR APPROVED EQ)
B	1	PV-CHX-CG-80	WIRE ROPE GUIDE (PERFECT VISION OR EOR APPROVED EQ)

2 PROPOSED WIRE ROPE GUIDE ATTACHMENT - PLAN VIEW
SCALE: N.T.S.

NOTE: CONTRACTOR SHALL ENSURE THAT WIRE ROPE GUIDE DOES NOT PUSH THE WIRE ROPE OUTSIDE OF THE VERTICAL PLANE OF THE SAFETY CLIMB. CONTRACT EOR WITH PHOTOS OF SAFETY CLIMB AND COLLAR FOR FURTHER DIRECTION IF NEEDED.



CLIMBING FACILITY PHOTO


MOUNT MODIFICATION SCHEDULE

NO.	ELEVATION	QUANTITY	DESCRIPTION	NOTES
1		1	PROPOSED SUPPORT RAIL KIT (PART #: VZVSMART-PLK1)	RADIO AND/OR THE POSITION SHALL BE ADJUSTED VERTICALLY AS NEEDED IN ORDER TO ACHIEVE INSTALLATION OF HORIZONTAL AS SHOWN FOR SHALL BE NOTIFIED IF EQUIPMENT NEEDS TO BE RELOCATED TO ANOTHER MOUNT PIPE.
2		1	PROPOSED KICKER KIT (PART #: VZVSMART-PLK5)	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE SHEET SIZE. CONNECT OTHER END OF KICKER KIT TO MONOPILE COLLAR MOUNT ASSEMBLY (PART #: VZVSMART-PLK7).
3	145'-0"	3	PROPOSED 96" LONG, PIPE 25 SCH40 (PART #: VZVSMART-P40-25BX096)	CONNECT NEW MOUNT PIPES TO EXISTING FACE HORIZONTAL WITH CROSSOVER PLATES (SIT E PRO 1 PART #: SP115-H).
4		1	PROPOSED 48" LONG, PIPE 3 SCH40 (PART #: VZVSMART-P40-25BX048)	CONNECT NEW 60" PIPE TO EXISTING STANDOFF HORIZONTAL WITH CROSSOVER PLATES (PART #: VZVSMART-P40A OR APPROVED EQUAL). CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE STRUCTURAL STEEL NOTES ON SHEET SS-1.
5		3	RELOCATED MOUNT PIPE	CONNECT RELOCATED MOUNT PIPES TO EXISTING FACE HORIZONTAL WITH EXISTING CROSSOVER PLATES AND NEW 1/2" DIA 3/8" X 10" BOLTS.


GENERAL NOTES:
 A. THREADED ROD FROM PROPOSED KITS SHALL BE TRIMMED TO EXTEND NO MORE THAN 1" BEYOND THE LOCK NUT. TREAT ALL CUT ENDS WITH (2) COATS OF COLD GALVANIZATION (ZINCA OR ZINC NOTE).
 B. MOUNT REBARS NOT SHOWN FOR CLARITY U.N.O.

LEGEND:

- PROPOSED
- RELOCATED
- EXISTING



1 PROPOSED ISOMETRIC VIEW
SCALE: N.T.S.



2 PROPOSED STANDOFF SIDE ELEVATION VIEW
SCALE: N.T.S.

Collins Engineering & Design
 www.collinsengineering.com
 1000 Main Street, Suite 100, Wallingford, CT 06495
 Phone: 203-261-1111
 Fax: 203-261-1112
 Email: info@collinsengineering.com

verizon

811
 Call before you dig
 1-800-4-A-DAWG
 www.811.com

NO.	REVISION	DATE	BY	CHK	APP
1	ISSUED FOR PERMIT	11/11/2019			
2	REVISED PER PERMIT COMMENTS	11/11/2019			
3	REVISED PER PERMIT COMMENTS	11/11/2019			
4	REVISED PER PERMIT COMMENTS	11/11/2019			
5	REVISED PER PERMIT COMMENTS	11/11/2019			

Bo Allen

STATE OF CONNECTICUT
 DEPARTMENT OF CONSTRUCTION
 REGISTERED PROFESSIONAL ENGINEER
 LICENSE NO. 12345


SITE NAME:
 ROCKY NECK CT
 500022067
 49 BRAINERD ROAD
 NIANATIC, CT 06357
 NEW LONDON COUNTY

Collins Engineering & Design
 1000 Main Street, Suite 100
 Wallingford, CT 06495
 Phone: 203-261-1111
 Fax: 203-261-1112
 Email: info@collinsengineering.com

MODIFICATION DETAILS
 SS-1



MOUNT PHOTO 1



MOUNT PHOTO 2



MOUNT PHOTO 3



MOUNT PHOTO 4

Collien Engineering & Design
www.collienengineering.com

INCORPORATING THE BEST OF BOTH WORLDS
 ENGINEERING AND DESIGN
 48 BRANDED ROAD
 MIDDLETOWN, CT 06457
 (860) 346-1100
 FAX (860) 346-1101



811 Call Before You Dig
 ANYONE WHO DIGGERS MUST CALL 811 AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO IDENTIFY AND MARK ALL UTILITIES.
 811 IS THE NATIONAL RELAY CENTER FOR THE PUBLIC TO REPORT ANY UNIDENTIFIED UTILITIES.
 www.811.org

NO.	DATE	DESCRIPTION	BY	CHKD.
1	05/10/2021	ISSUED FOR PERMIT	SAJ	SAJ
2	05/10/2021	REVISION	SAJ	SAJ
3	05/10/2021	REVISION	SAJ	SAJ
4	05/10/2021	REVISION	SAJ	SAJ
5	05/10/2021	REVISION	SAJ	SAJ
6	05/10/2021	REVISION	SAJ	SAJ
7	05/10/2021	REVISION	SAJ	SAJ
8	05/10/2021	REVISION	SAJ	SAJ
9	05/10/2021	REVISION	SAJ	SAJ
10	05/10/2021	REVISION	SAJ	SAJ

STATE OF CONNECTICUT
 DEPARTMENT OF CONSTRUCTION
 55 STATE STREET, SUITE 300
 HARTFORD, CT 06103
 (860) 424-3200
 www.ct.gov/dco

THIS IS A PRELIMINARY PERMIT. THE PERMITTEE SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS FROM THE LOCAL GOVERNMENT.


SITE NAME:
 ROCKY NECK CT
 5000122067
 48 BRANDED ROAD
 MIDDLETOWN, CT 06457
 NEW LONDON COUNTY

Collien Engineering & Design
 48 BRANDED ROAD
 MIDDLETOWN, CT 06457
 (860) 346-1100
 FAX (860) 346-1101

DATE: 05/10/2021
 TIME: 07:38
 MOUNT PHOTOS
 SS-2

PARTS LIST

ITEM	QTY	PART NO.	PART DESCRIPTION	LENGTH	UNIT WT.	NET WT.
1	1	X-SP219	SMALL SUPPORT CROSS PLATE	8 1/4 In	8.61	8.61
2	2	X-UB1306	1/2" X 3-5/8" X 6" X 3" U-BOLT (HDG.)		0.66	1.31
3	2	X-UB1300	1/2" X 3" X 5" X 2" U-BOLT (HDG.)		0.66	1.31
4	8	G12FW	1/2" HDG USS FLATWASHER		0.03	0.27
5	8	G12LW	1/2" HDG LOCKWASHER		0.01	0.11
6	8	G12NUT	1/2" HDG HEAVY 2H HEX NUT		0.07	0.57
TOTAL WT. #					12.61	



TOLERANCE NOTES

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:
 GAWED, SHEARED AND GAS CUT EDGES (± 0.007)
 DRILLED AND GAS CUT HOLES (± 0.009) - NO CORNING OF HOLES
 BEARING SURFACES (± 0.005)
 ALL OTHER MACHINING (± 0.007)
 ALL OTHER ASSEMBLY (± 0.0007)

PROPRIETARY NOTE: DIMENSIONS SHOWN IN THIS DRAWING ARE PROPRIETARY INFORMATION AS AN INVENTION OF THE COMPANY AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT THE CONSENT OF THE COMPANY IS STRICTLY PROHIBITED.

FOR REFERENCE ONLY

DESCRIPTION
 2-7/8" TO 3-1/2"
 PIPE MOUNT ASSEMBLY

SLIDE PRO
 A Valmont COMPANY

Engineering
 4000 W. 11th St.
 1-800-763-7446
 Phoenix, AZ
 Salem, OR
 Dallas, TX

Locations:
 New York, NY
 Atlanta, GA
 Phoenix, AZ
 Dallas, TX


REV	A	REDRAWN IN INV. UPDATED VIEWS & TABLE	CPD	BY	KCB	DATE	8-21-2012
DESCRIPTION OF REVISIONS		REVISION HISTORY					
CLASS	81	CLASS	451B	CLASS	SLUB	CLASS	SLUB
DRAWN BY	BMC	6/9/2009	ENG. APPROVAL				
CHECKED BY	CUSTOMER	CEK	2/18/2013				
PART NO.	SP219-H						
DWG. NO.	SP219-H						
PAGE	1 OF 1						

FOR REFERENCE
 ONLY

ISSUED BY: SK
 CHECKED BY: BT/KW
 REV: 05/24/2009 BY: DAK
 DESIGNED BY: SK 05/09/20

SHEET TITLE:
 VZWSMART-MSK6
 BACK TO BACK
 CROSSOVER

SHEET NUMBER:
 VZWSMART-MSK6
 REV #:
 0



ISOMETRIC VIEW
 BACK TO BACK CROSSOVER


ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	2	PL375-8512	PL 3/8" X B 1/2" X 1'-0" A36	MSK6-F2	20.7
2	4	WCP	PL 1/2" X 2" X B 5/8" A36 BENT PLATE	MSK6-F1	9.6
3	4	---	THREADED ROD 5/8" DIA. X 10" F1554-36 HDG		
4	16	NUT-625	5/8" HDG HEX NUT		2
5	16	FW-625	5/8" HDG USS FLAT WASHER		1
6	16	LW-625	5/8" HDG LOCK WASHER		0
7	8	---	BOLT 5/8" X 6" SAE GRADE 5 ALL THREAD		1
				GALVANIZED WT	34

VZWSMART-MSK6 (VZWSMART-MSK6 - BACK TO BACK CROSSOVER)

NOTES:
 1. HOT-DIPPED GALVANIZED PER ASTM A123.


FOR REFERENCE
 ONLY

DRAWN BY: HMA	CHECKED BY: HMA
REV. 1	DESCRIPTION: VZWSMART-PLK1 SUPPORT RAIL KIT
REV. 2	DATE: 05/06/20
REV. 3	
REV. 4	
REV. 5	
SHEET TITLE: VZWSMART-PLK1 SUPPORT RAIL KIT	
SHEET NUMBER: VZWSMART-PLK1	REV. F: 0




NOTES:
 1. HOT-DIPPED GALVANIZED PER ASTM A123.

ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	PST2875-12.5	2.5" PST (2.875" O.D. X 0.203" THK.) X 12'-6" AS3 GR-B	PLK1-F1	292
2	3	L33375-3	L 3" X 3" X 3/8" X 3'-0" A36	PLK1-F1	66
3	3	CBP-L	CORNER BENT PLATE BRACKET	PLK1-F2	28
4	3	CBP-R	CORNER BENT PLATE BRACKET	PLK1-F2	28
5	60	MS02-625-300-500	RU-BOLT 5/8" X 3" LW, X 5" LL, A36 (OR EQUIV.)	RBC-1	82
6	24		BOLT 5/8" X 2" A325		9
7	12	PL375-857	PL 3/8" X B 1/2" X 7'-0" A36	PLK1-F3	77
8	144	FW-625	5/8" HDG USS FLAT WASHER		12
9	144	LW-625	5/8" HDG LOCK WASHER		3
10	144	NUT-625	5/8" HDG HEX NUT		17
				GALVANIZED WT	504



FOR REFERENCE ONLY

DRAWN BY: MM	CHECKED BY: MM/AM
REV	DESCRIPTION
1	MM 05/08/20
2	
3	
4	
5	
SHEET TITLE:	
VZWSMART-PLK5 KICKER KIT	
SHEET NUMBER:	REV #:
VZWSMART-PLK5	0




ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	BRKW-XXX	BRACKET WELDMENT A36	PLK5-F3	43.8
2	3	BRKW-XXXX	BRACKET WELDMENT A36	PLK5-F2	35.7
3	6	L331675-B	L 3" X 3" X 3/16" X 8'-0" A36	PLK5-F4	102.9
4	3	PL-KI	PL 5/8" X 6" X 9" A36	PLK5-F1	29.0
5	12		THREADODD ROD 5/8" DIA. X 1'-0" F1554-36 110G		
6	6		BOLT 5/8" X 2" A325		
7	12		BOLT 5/8" X 2 1/2" A325		
8	42	FW-625	5/8" HDG USS FLAT WASHER		3
9	42	LW-625	5/8" HDG LOCK WASHER		1
10	42	NUT-625	5/8" HDG HEX NUT		5
GALVANIZED WT					291

- NOTES:
- ALL HOLES ARE 11/16" DIA. UNO
 - HOT-DIPPED GALVANIZED PER ASTM A123.
 - FT UP TO 6" SQ. TUBING OR 4 1/2" O.D. PIPE


FOR REFERENCE
 ONLY

DRAWN BY: BT
 CHECKED BY: MIA/KW
 REV DESCRIPTION BY DATE
 1 LABEL ISSUE BT 06/11/20

SHEET TITLE:
 VZWSMART-PLK7
 MONOPOLE COLLAR
 JOINT ASSEMBLY
 REV #:
 VZWSMART-PLK7 0



PLAN VIEW
 MONOPOLE COLLAR MOUNT ASSEMBLY




FRONT VIEW

- NOTES:
 1. FIT 1/2" TO 45° DIA MONOPOLE.
 2. HOT-DIPPED GALVANIZED PER ASTM A123.

ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	CM-1245	COLLAR MOUNT ASSEMBLY	PLK7-F1	147
2	6		THREADED ROD 5/8" X 4'-0" A193-B7		
3	12	FW-625	5/8" HDG USS FLAT WASHER		1
4	12	LW-625	5/8" HDG LOCK WASHER		0
5	12	NUT-625	5/8" HDG HEX NUT		1
GALVANIZED WT					150

ATTACHMENT 5



Tighe & Bond

49 BRAINERD RD

2/6/2024 1:35:39


1"=500'

Property Information

Parcel ID	07.4 21
Address	49 BRAINERD RD
Total Assessed Parcel	440990



The information depicted on this map is for planning purposes only. It is not adequate for legal boundary definition, regulatory interpretation, or parcel-level analyses.



49 BRAINERD RD

Location 49 BRAINERD RD

Mblu 07.4/ 21/ / /

Acct# 005680

Owner DOUBLE R RANCH LLC

Assessment \$440,990

Appraisal \$776,300

PID 5939

Building Count 1

Current Value

Appraisal			
Valuation Year	Improvements	Land	Total
2021	\$340,400	\$435,900	\$776,300

Assessment			
Valuation Year	Improvements	Land	Total
2021	\$238,280	\$202,710	\$440,990

Owner of Record

Owner DOUBLE R RANCH LLC
Co-Owner
Address 468 PEQUOT AVE
NEW LONDON, CT 06320

Sale Price \$1,200,000
Certificate
Book & Page 1103/0411
Sale Date 11/09/2023
Instrument 00

Ownership History

Ownership History					
Owner	Sale Price	Certificate	Book & Page	Instrument	Sale Date
SAMUELSEN CHRISTOPHER TR	\$0		1087/0241	04	09/20/2022
SAMUELSEN CHRISTOPHER	\$0		0831/0222	04	07/10/2009
SAMUELSEN CHRISTOPHER &	\$0		0788/0266	04	10/24/2007
SAMUELSEN CHRISTOPHER	\$560,000		0748/0207	07	07/13/2006

Building Information

Building 1 : Section 1

Year Built: 1890
Living Area: 2,485
Replacement Cost: \$423,858
Building Percent Good: 67

ATTACHMENT 6

Certificate of Mailing — Firm



Name and Address of Sender

Kenneth C. Baldwin, Esq.
 Robinson & Cole LLP
 280 Trumbull Street
 Hartford, CT 06103

TOTAL NO.
 of Pieces Listed by Sender

3

TOTAL NO.
 of Pieces Received at Post Office™

3

Postmaster, per (name of receiving employee)

[Signature]

Affix Stamp Here
 Postmark with Date of Receipt.



USPS® Tracking Number
 Firm-specific Identifier

Address
 (Name, Street, City, State, and ZIP Code™)

1. Daniel Cunningham, First Selectman
 Town of East Lyme
 108 Pennsylvania Avenue
 Niantic, CT 06357
 2. Gary Goeschel, II, Director of Planning
 Town of East Lyme
 108 Pennsylvania Avenue
 Niantic, CT 06357
 3. Double R Ranch LLC
 468 Pequot Avenue
 New London, CT 06320

Parcel Airlift

Special Handling

Fee

Postage

