



STATE OF CONNECTICUT
CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: siting.council@ct.gov

www.ct.gov/csc

February 7, 2013

Patricia Masterson
Site Acquisition Manager
Goodman Networks
Two Willow Street, Suite 101
Southborough, MA 01745

RE: **EM-SPRINT-047-130109** – Sprint Spectrum L.P. notice of intent to modify an existing telecommunications facility located at 160 Plantation Road, East Windsor, Connecticut.

Dear Ms. Masterson:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:

- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Within 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated January 9, 2013. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,

Linda Roberts
Executive Director

LR/CDM/jb

c: The Honorable Denise Sabotka Menard, First Selectman, Town of East Windsor
Laurie Whitten, Town Planner, Town of East Windsor
Dean Rasmussen





Goodman Networks
Network Knowledge... Delivered.

January 9, 2013

Linda Roberts
Executive Director
Connecticut Siting Counsel
Ten Franklin Square
New Britain, CT 06051
Linda Roberts, Executive Director

Re: Notice of Exempt Modification – Antenna Swap
160 Plantation Road, East Windsor, Connecticut

RECEIVED
JAN - 9 2013

Dear Ms. Roberts:

**CONNECTICUT
SITING COUNCIL**

Sprint is planning to consolidate multiple network technologies into one seamless network with the goal of increasing efficiency and enhancing network coverage, call quality and data speeds for customers across Connecticut. Pursuant §16-50j-73 to of the Regulations of Connecticut State Agencies (RCSA), please accept this letter and attachments as notification of Sprint's intent to make exempt modifications, under RCSA §16-50j-72(b)(2), to its existing telecommunications facility at 160 Plantation Road, East Windsor, Connecticut. In accordance with RCSA §16-50j-73, a copy of this letter was sent to Denise Menard, the First Selectman of the Town of East Windsor.

Sprint currently maintains six (6) antennas at 126 feet on the existing 135 foot water tower at the address referenced above. Sprint intends to replace its existing six (6) CDMA antennas with three (3) Multimodal antennas at their same current height of 126 feet. Sprint will a be replacing its existing six (6) lines of coaxial cable with three (3) smaller lines of Hybriflex cable and installing six (6) RRH's. Sprint will also be swapping three (3) existing ground cabinets with three (3) new cabinets and adding one (1) fiber junction box. This work will result in a net reduction of antennas, from six (6) to three (3), and will not increase the height of the tower or the size compound. Please find included with this letter compound, elevation and overhead drawings which depict Sprint's proposed modifications.

Sprint's planned modifications fall squarely within the activities permitted in RCSA §16-50j-72(b)(2) in that:

1. The proposed modifications will not increase the existing tower height;
2. The proposed modifications will not extend the boundaries of the site by any dimension;

3. The proposed modifications will not increase the noise levels at the existing facility by six (6) decibels or more;
4. The proposed modifications will not increase the total radio frequency electromagnetic radiation power density to or above the standards adopted by the Federal Communications Commission. Please find included with this letter a Radio Frequency Emissions Analysis Report.

Also included with this letter is a Structural Assessment confirming that the foundation and tower are sufficient to support Sprint's proposed modifications.

For the foregoing reasons, Sprint respectfully submits that its proposed modifications to the existing tower located at the address referenced above constitute an exempt modification under RSCA §16-50j-72(b)(2).

Please do not hesitate to contact me at (214) 478-3516 or dtorres@goodmannetworks.com if you have any questions. Thank you for your consideration.

Respectfully,

A handwritten signature in black ink, appearing to read 'David Torres', with a horizontal line extending to the right.

David Torres
Goodman Networks

Attachments

Copy to:

Denise Menard, First Selectman, Town of East Windsor

**RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS**

Sprint Existing Facility

Site ID: CT03XC202

**Rasmussen Water Tank
160 Plantation Road
East Windsor, CT 06016**

October 19, 2012

October 19, 2012

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Emissions Values for Site: **CT03XC202 – Rasmussen Water Tank**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 160 Plantation Road, East Windsor, CT, for the purpose of determining whether the emissions from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the PCS band is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 160 Plantation Road, East Windsor, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 3 CDMA Carriers (1900 MHz) were considered for each sector of the proposed installation.
- 2) 1 CDMA Carrier (850 MHz) was considered for each sector of the proposed installation
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The actual gain in this direction was used per the manufactures supplied specifications.
- 5) The antenna used in this modeling is the APXVSPP18-C-A20. This is based on feedback from the carrier with regards to anticipated antenna selection. This antenna has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.

- 6) The antenna mounting height centerline of the proposed antennas is **126 feet** above ground level (AGL)
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC158 - Long Hill SBA
Site Address	1825 South Main Street, Middletown, CT, 06457
Site Type	Monopole

Sector 1																	
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBi)	Antenna Height (ft)	Antenna analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	146	140	1/2"	0.5	0	1386.9474	25.43958	2.543958%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	146	140	1/2"	0.5	0	389.96892	7.152863	1.26153%
Sector total Power Density Value:													3.805%				

Sector 2																	
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBi)	Antenna Height (ft)	Antenna analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	146	140	1/2"	0.5	0	1386.9474	25.43958	2.543958%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	146	140	1/2"	0.5	0	389.96892	7.152863	1.26153%
Sector total Power Density Value:													3.805%				

Sector 3																	
Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBi)	Antenna Height (ft)	Antenna analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	146	140	1/2"	0.5	0	1386.9474	25.43958	2.543958%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	146	140	1/2"	0.5	0	389.96892	7.152863	1.26153%
Sector total Power Density Value:													3.805%				

Site Composite MPE %	
Carrier	MPE %
Sprint	11.416%
T-Mobile	3.754%
Nextel	4.130%
Clearwire	0.860%
Verizon Wireless	16.790%
Pocket	5.060%
AT&T	11.708%
Total Site MPE %	53.710%


Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public exposure to RF Emissions.

The anticipated Maximum Composite contributions from the Sprint facility are **20.733% (6.911% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **37.883%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803



November 29, 2012

John Szilezy
Alcatel-Lucent
Site Acquisition Manager
600 Mountain Avenue, Murray Hill, NJ 07974
john.szilezy@alcatel-lucent.com

SUBJECT: STRUCTURAL ASSESSMENT

**SITE: RASMUSSEN WATER TANK (CT03XC202)
160 PLANTATION ROAD
EAST WINDSOR, HARTFORD COUNTY, CONNECTICUT 06016
RAMAKER & ASSOCIATES PROJECT NUMBER: 23001**

Dear Mr. Szilezy:

This structural assessment is a review of the loading condition changes at the above referenced site. Ramaker & Associates, Inc. (RAMAKER) was specifically tasked to investigate loading changes associated with the Alcatel-Lucent (ALU) project associated with the construction/installation of new Sprint (SPRINT) equipment. Assuming the conditions outlined below, it is the finding of RAMAKER that no further assessment is required and that the structure(s) will adequately support the proposed SPRINT modifications.

In order to complete the structural assessment, RAMAKER utilized records and information gathered in order to prepare this report's findings, including:

- 1) Construction drawings by RAMAKER, job number 23001, dated October 25, 2012,
- 2) Two site visits conducted by RAMAKER,
- 3) Construction drawings by DiCesare Bentley, job number 09-083.37, dated October 15, 2010,
- 4) Structural Analysis by SEA Consultants, job number 96261.02, dated November 5, 1996,
- 5) Previously procured data by RAMAKER during other site due diligence activities, or
- 6) Were assumed (noted as such on existing loading)

RAMAKER understands that the current SPRINT antenna loading consists of:

- (6) CDMA panel antennas (2 per sector)

RAMAKER understands that the proposed interim SPRINT antenna loading will consist of:

- (6) CDMA panel antennas (2 per sector)
- (1) RFS APVX9ERR18-C-A20 panel antennas (1 in Alpha)
- (2) RFS APXVSP18-C-A20 3G panel antenna (1 each in Beta and Gamma sectors)
- (3) ALU 800 MHz RRH Units (1 per sector)
- (3) ALU 1900 MHz RRH Units (1 per sector)

RAMAKER understands that the proposed final SPRINT antenna loading will consist of:

- (2) RFS APVX9ERR18-C-A20 panel antennas (1 in Alpha)
- (1) RFS APXVSP18-C-A20 3G panel antenna (1 each in Beta and Gamma sectors)
- (3) ALU 800 MHz RRH Units (1 per sector)
- (3) ALU 1900 MHz RRH Units (1 per sector)

To summarize our findings, SPRINT currently has a total of six (6) panel antennas installed at the site. These antennas are mounted to pipe mounts that are attached to the existing catwalk railing and to the

water tower roof. ALU is proposing to remove all six (6) of the existing antennas and install one (1) RFS APVX9ERR18-C-A20 panel antennas (1 in Alpha) and two (2) RFS APXVSP18-C-A20 3G panel antenna (1 each in Beta and Gamma sectors) at a centerline elevation of 126-feet. The proposed antennas shall be mounted to new pipe mounts. ALU is also proposing to install three (3) ALU 1900 MHz RRH Units (1 per sector) and three (3) ALU 800 MHz RRH Units (1 per sector) that will be mounted along with the proposed antennas. The existing CDMA panel antennas shall remain as is for the interim phase, then shall be removed for the final antenna configuration.

By engineering calculation and inspection, the proposed antenna and RRH mounting structure is capable of supporting the proposed Sprint Network Vision equipment without causing an overstress condition in the antenna and RRH mounting structure.

This assessment is inclusive of the entire antenna and RRH mounting structure, including pipe mounts, mounting hardware, and all other aspects of the mounting structure that will support the Sprint Network Vision equipment deployment.

New pipe mounts are required for the additional antennas and they shall be installed as outlined in the RAMAKER construction drawings (see detail 1/S-1). During the interim period, before the existing antennas are removed, the existing handrail will experience increased dead and wind loads from what are currently present. However, these load increases are not anticipated to have a significant effect on the structural adequacy of the existing handrail. Therefore, it is RAMAKER's assessment that the proposed mounts, handrail, and water tower structure will adequately support the proposed antenna configuration.

ALU is also proposing to remove one (1) bts cabinet, one (1) battery backup cabinet, and one (1) DC power plant from the existing ground-level steel platform. These are to be replaced by the proposed one (1) 9928 MM-BTS cabinet and two (2) 60ECv2 battery backup cabinets. In addition, one (1) proposed fiber/power distribution box is to be installed on a new H-frame which will be mounted to the platform. It is RAMAKER's assessment that the existing platform will adequately support the proposed equipment configuration.

In review of the information presented above, it is the finding of RAMAKER that no further assessment is required and the structure will provide adequate support for the modifications proposed by ALU on behalf of SPRINT.

The recommendations contained within this report were developed using general project information provided as previously described. All recommendations pertain only to the proposed antenna installation activities as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

1. Missing, corroding, and/or deteriorating members,
2. Improper manufacturing and/or construction, or
3. Improper maintenance.


The loading configuration used in the analysis is based on information provided by ALU, who is responsible for verifying that the existing loading on the structure is consistent with the loading applied to the structure within this report. If you are aware of any information contrary to that contained herein, or if you are aware of any defects arising from the original design, material, fabrication and erection deficiencies, you should disregard this report and immediately contact RAMAKER. RAMAKER is not liable for any representation, recommendation, or conclusion not expressly stated herein.


If you have any questions or comments, please do not hesitate to contact our office.

Sincerely,

RAMAKER & ASSOCIATES, INC.


Ryan Nelson, EIT
Engineering Technician


James R. Skowronski, P.E.
Supervising Engineer





1120 Dallas Street Sauk City, WI 53583
 (608) 643-4100
 FAX (608) 643-7999
 e-mail: ramaker@ramaker.com

JOB Rasmussen Water Tank (CT03XC202)
 SHEET NO _____ OF _____
 CALCULATED BY RJN DATE 11/27/2012
 CHECKED BY _____ DATE _____
 SCALE _____ nts

Wind Loads ASCE/SEI 7-05

6.5.10 Velocity Pressure

$q_z = 0.00256 K_z K_{zt} K_d V^2 I$

Occupancy	II	Table 1-1
Exposure	C	Exposure Category
V	98 mph	Basic Wind Speed (Figure 6-1 generally 90)
z	126 ft	Height above ground level to the center of the antenna
I	1.15	Importance Factor (6.5.5, Table 6-1)
K_z	1.33	Velocity Pressure Exposure Coefficient (Table 6-3 page 79)
K_{zt}	1.00	Topographic Factor (6.5.7.2)
K_d	0.95	Wind Directionality Factor (Table 6-4)

State Connecticut
 County Hartford

$q_z = 35.6$ psf

Wind Load on Antenna Panel ASCE/SEI 7-05

Antenna Model: **RFS APXVSPPI8-C**

$F = 234.3$ lbs

Wind Load on Pipe Mount ASCE/SEI 7-05

Pipe Size: **3-in Ø Std. Pipe**

$W = 11.9$ lbs/ft

Pipe Flexural Strength AISC 13th Edition

L	14.0 ft	Total pipe mount length
L_1	14.0 ft	Length between supports
L_2	3.5 ft	Length above antenna load
L_3	10.5 ft	Length from the bottom of the pipe mount to the center of the antenna


$M_{Max} = 0.91$ kip-ft **$R_1 = 0.26$ kip**
 $R_2 = 0.14$ kip

* From AISC, Table 3-15 *

3-in Ø Std. Pipe

Flexural Strength 3.83 kip-ft

$3.83 > 0.91$ OK



* Lengths are estimated based on photographs *

Notes:



1120 Dallas Street Sauk City, WI 53583
 (608) 643-4100
 FAX (608) 643-7999
 e-mail: ramaker@ramaker.com

JOB Rasmussen Water Tank (CT03XC202)
 SHEET NO _____ OF _____
 CALCULATED BY RJN DATE 11/27/2012
 CHECKED BY _____ DATE _____
 SCALE _____ nts

Wind Load on Antenna Panel ASCE/SEI 7-05

Antenna Model: **RFS APXVSP18-C**
 Height 72.0 in
 Width 11.8 in
 Depth 7.0 in
 Weight 64.5 lbs

6.5.10 Velocity Pressure

$$q_z = 0.00256 K_z K_{zt} K_d V^2 I$$

Occupancy	II	Table 1-1
Exposure	C	Exposure Category
V	98 mph	Basic Wind Speed (Figure 6-1 generally 90)
z	126 ft	Height above ground level to the center of the antenna
I	1.00	Importance Factor (6.5.5, Table 6-1)
K _z	1.33	Velocity Pressure Exposure Coefficient (Table 6-3 page 79)
K _{zt}	1.00	Topographic Factor (6.5.7.2)
K _d	0.95	Wind Directionality Factor (Table 6-4)

q_z = 30.9 psf




6.5.15 Design Wind Loads on Other Structures

$$F = q_z G C_f A_f$$

q _z	30.9 psf	
G	0.85	Rigid Structure ASCE 7-05
h/D	10.3	Height of structure / Least horizontal dimension of cross-section
C _f	1.51	Force Coefficients (Figure 6-21, Square, normal)
A _f	5.90 ft ²	Projected area normal to the wind
Increase	1.00	Rooftop Structures < 60ft (6.5.15.1)

F = 234.3 lbs

Notes:



DRIVING DIRECTIONS:
 FROM BRADLEY INTERNATIONAL AIRPORT, CT:
 DEPART TERMINAL RD TOWARD BRADLEY FIELD CONNECTOR. KEEP RIGHT ONTO BRADLEY FIELD CONNECTOR. ROAD NAME CHANGES TO CT-20 E. TAKE CT-20 E TO RAMP AT I-91 SOUTH TOWARD HARTFORD. NORTH OF HARTFORD. TAKE EXIT 35 AT I-29 I. TAKE I-29 I EAST TO EXIT 4 AT US-5/JOHN FITCH BLVD. TAKE US-5 NORTH TO SULLIVAN AVE. TAKE SULLIVAN AVE. EAST TO RYE ST. TAKE RYE ST. NORTH TO WINDSORVILLE RD. TAKE WINDSORVILLE RD. NORTH TO PLANTATION RD. TAKE PLANTATION RD. WEST. SITE IS AT WATER TANK ON LEFT (SOUTH) SIDE OF ROAD.

CODE COMPLIANCE

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL COVERING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

- INTERNATIONAL BUILDING CODE 2009
- ACCESSIBILITY CODE IBC 2009, CHAPTER 11 & ICC/ANSI A117.1-2003
- 2008 NATIONAL ELECTRIC CODE
- FIRE/LIFE SAFETY CODE- IFC 2009
- ENERGY CODE IECC 2009

PROJECT NOTES

- THIS IS AN UNMANNED TELECOMMUNICATIONS FACILITY CONSISTING OF BTS EQUIPMENT AND ANTENNAS.
- SIGNALS FROM THE ANTENNA SHALL NOT INTERFERE WITH ANY EXISTING COMMUNICATION SITES. ALL ITEMS SHOWN HEREON ARE EXISTING UNLESS OTHERWISE NOTED.
- THE PROPOSED ANTENNAS ARE ATTACHED TO EITHER BUILDING OR ANTENNA FRAME OR TO BOTH.
- THE PROPOSED WORK WILL HAVE NO EFFECT ON STRUCTURAL STABILITY. ALL WORK SHALL BE PERFORMED IN STRICT ADHERENCE WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS.
- REFERENCE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES FOR GENERAL REQUIREMENTS.
- THIS IS AN UNMANNED FACILITY- NO SOLID WASTE. THE SITE WILL CREATE NO TRASH, THUS REQUIRES NO DUMPSTER.
- EQUIPMENT IS UNMANNED AND NOT FOR HUMAN HABITATION. HANDICAP ACCESS IS THEREFORE NOT REQUIRED.
- OWNER & TENANT MAY, FROM TIME TO TIME AT TENANT'S OPTION, REPLACE THIS EXHIBIT WITH AN EXHIBIT SETTING FORTH THE LEGAL DESCRIPTION OF THE SITE, OR WITH ENGINEERED OR AS-BUILT DRAWING DEPICTING THE SITE OR ILLUSTRATING STRUCTURAL MODIFICATIONS OR CONSTRUCTION PLANS OF THE SITE. ANY VISUAL OR TEXTUAL REPRESENTATION OF THE EQUIPMENT LOCATED WITHIN THE SITE CONTAINED IN THESE OTHER DOCUMENTS IS ILLUSTRATIVE ONLY, AND DOES NOT LIMIT THE RIGHTS OF SPRINT AS PROVIDED FOR IN THE AGREEMENT. THE LOCATIONS OF ANY ACCESS AND UTILITY EASEMENTS ARE ILLUSTRATIVE ONLY. ACTUAL LOCATIONS MAY BE DETERMINED BY TENANT AND/OR THE SERVICING UTILITY COMPANY IN COMPLIANCE WITH LOCAL LAWS AND REGULATIONS.

PROJECT DESCRIPTION

APPLICANT PROPOSED TO INSTALL ANTENNAS AND WEATHERPROOF EQUIPMENT CABINETS FOR AN UNMANNED PERSONAL COMMUNICATIONS SYSTEM WIRELESS CALL SITE AT AN EXISTING TELECOMMUNICATIONS FACILITY. PROPOSED FACILITY IS NOT STAFFED AND IS VISITED ONCE A MONTH FOR MAINTENANCE PURPOSES ONLY; THEREFORE, SANITARY, SEWER, GAS, POTABLE WATER AND PLUMBING ARE NOT REQUIRED.

TO OBTAIN LOCATION OF PARTICIPANTS' UNDERGROUND FACILITIES BEFORE YOU DIG IN CONNECTICUT
CALL BEFORE YOU DIG 811 OR 1-800-922-4455

CONNECTICUT PUBLIC ACT 87-71 REQUIRES MIN. 2 WORKING DAYS NOTICE BEFORE YOU EXCAVATE.

DO NOT SCALE DRAWINGS:
 CONTRACTOR SHALL VERIFY ALL PLANS & EXISTING DIMENSIONS & CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

APPROVALS

CONSTRUCTION PROJECT MANAGER: _____

SITE ACQUISITION: _____

SPRINT REPRESENTATIVE: _____

RF ENGINEER: _____

LANDLORD/ OWNER: _____

CONSTRUCTION DRAWINGS

Sprint

RASMUSSEN WATER TANK CT03XC202

160 PLANTATION ROAD
 EAST WINDSOR, CT 06016
 HARTFORD COUNTY

WATER TANK

SHEET INDEX

GENERAL:		STRUCTURAL:	
T-1	TITLE SHEET	S-1	STRUCTURAL DETAILS
SP-1	SPECIFICATIONS	UTILITY & GROUNDING:	
SP-2	SPECIFICATIONS	E-1	UTILITY & GROUNDING SITE PLAN & NOTES
SP-3	SPECIFICATIONS	E-2	UTILITY DETAILS
SITE:		E-3	GROUNDING DETAILS & NOTES
C-1	OVERALL SITE PLAN	E-4	GROUNDING DETAILS
A-1	EQUIPMENT PLAN	E-5	GROUNDING DETAILS
A-2	SITE ELEVATION & NOTES		
A-3	ANTENNA DETAILS & COAX SCHEDULE		
A-4	ANTENNA PLUMBING DIAGRAM & SPECIFICATIONS		
A-5	RF INFORMATION & COAX COLOR CODING		
A-6	EQUIPMENT DETAILS & SPECIFICATIONS		
A-7	EQUIPMENT DETAILS & SPECIFICATIONS		

PROJECT INFORMATION

APPLICANT ID:	TELEPHONE COMPANY:
SITE NAME: RASMUSSEN WATER TANK	AT&T
SITE #: CT03XC202	PH.: (800) 288-2020
PROPERTY LANDLORD:	HOSPITAL:
DEAN & CAREN RASMUSSEN	MANCHESTER MEMORIAL HOSPITAL
44 MAIN STREET	71 HAYNES STREET
P.O. BOX 542	MANCHESTER, CT 06040
EAST WINDSOR, CT 06016	PH.: (860) 646-1222
SITE MANAGEMENT:	FIRE HOUSE:
GLOBAL TOWER PARTNERS	WAREHOUSE POINT FIRE DEPARTMENT
SITE NAME: RASMUSSEN	89 BRIDGE STREET
SITE #: US-CT-9016	EAST WINDSOR, CT 06088
SITE ADDRESS:	PH.: (860) 623-5596
160 PLANTATION ROAD	APPLICANT:
EAST WINDSOR, CT 06016	SPRINT
HARTFORD COUNTY	6391 SPRINT PARKWAY
ZONING CLASSIFICATION: A-1 AGRICULTURE	OVERLAND PARK, KS 66251
SITE DATA:	PLANS PREPARED BY:
LATITUDE: 41°52'32.29" N (41.87563611°)	RAMAKER & ASSOCIATES, INC.
LONGITUDE: 72°33'53.27" W (-72.56479722°)	1120 DALLAS STREET
GROUND ELEVATION: 167 FT AMSL	SAUK CITY, WI 53583
POWER COMPANY:	CONTACT: KEITH BOHNSACK, P.E., PROJECT MANAGER
CONNECTICUT LIGHT & POWER	PH.: (608) 643-4100
PH.: (800) 286-2000	FAX: (608) 643-7999

Sprint
 6391 Sprint Parkway
 Overland Park, KS 66251

Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.
 1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

**NETWORK VISION
 MMBTS LAUNCH
 NORTHERN CT MARKET**

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

JAMES R. SKOWRONSKI
 No. 29268
 LICENSED PROFESSIONAL ENGINEER

Signature: _____ Date: 1/08/2013

MARK	DATE	DESCRIPTION
C	1/08/13	FINAL CDS ISSUED
B	10/25/12	FINAL PRELIM CDS
A	10/03/12	90% CD REVIEW
ISSUE PHASE	FINAL	DATE ISSUED 01/08/13

**RASMUSSEN WATER TANK
 SITE #: CT03XC202**

PROJECT INFORMATION:
 160 PLANTATION ROAD
 EAST WINDSOR, CT 06016
 HARTFORD COUNTY

SHEET TITLE:
TITLE SHEET

SCALE: NONE

PROJECT NUMBER: 23001
 SHEET NUMBER: T-1

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01100 - SCOPE OF WORK

PART 1 - GENERAL

- 1.1 THE WORK: These Standard Construction Specifications in conjunction with the other Contract Documents and the Construction Drawings describe the Work to be performed by the Contractor.
- 1.3 PRECEDENCE: Should conflicts occur between the Standard Construction Specifications for Wireless Sites including the Standard Construction Details for Wireless Sites and the Construction Drawings, information on the Construction Drawings shall take precedence. Notify Company designated representative of conflicts prior to construction.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. The Work shall comply with applicable national codes and standards, latest edition, and portions thereof, included but not limited to the following:
 1. GR-63-CORE NEBS Requirements: Physical Protection
 2. GR-78-CORE Generic Requirements for the Physical Design and Manufacture of Telecommunications Equipment.
 3. National Fire Protection Association Codes and Standards (NFPA) including NFPA 70 (National Electrical Code - "NEC") and NFPA 101 (Life Safety Code).
 4. American Society for Testing of Materials (ASTM)
 5. Institute of Electronic and Electrical Engineers (IEEE)
 6. American Concrete Institute (ACI)
 7. American Wire Producers Association (AWPA)
 8. Concrete Reinforcing Steel Institute (CRSI)
 9. American Association of State Highway and Transportation Officials (AASHTO)
 10. Portland Cement Association (PCA)
 11. National Concrete Masonry Association (NCMA)
 12. Brick Industry Association (BIA)
 13. American Welding Society (AWS)
 14. National Roofing Contractors Association (NRCA)
 15. Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 16. Door and Hardware Institute (DHI)
 17. Occupational Safety and Health Act (OSHA)
 18. Applicable building codes including Uniform Building Code, Southern Building Code, BOCA, and the International Building Code.

SECTION 01300 - CELL SITE CONSTRUCTION

3.1 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. Contractor shall keep the site free from accumulating waste material, debris, and trash. At the completion of the work, Contractor shall remove from the site all remaining rubbish, implements, temporary facilities, and surplus materials.
- B. Equipment rooms shall at all times be maintained "broom clean" and clear of debris.
- C. Contractor shall take all reasonable precautions to discover and locate any Hazardous Condition.
 1. In the event Contractor encounters any hazardous condition which has not been abated or otherwise mitigated, Contractor and all other persons shall immediately stop Work in the affected area and notify Company in writing. The Work in the affected area shall not be resumed except by written notification by Company.
 2. Contractor agrees to use care while on the Site and shall not take any action that will or may result in or cause the hazardous condition to be further released in the environment, or to further expose individuals to the hazard.
- D. Contractor's activities shall be restricted to the project limits. Should areas outside the project limits be affected by Contractor's activities, Contractor shall immediately return them to original condition
- E. Conduct testing as required herein.

DIVISION 2 - SITE CONSTRUCTION

SECTION 02300 - EARTHWORK

PART 3 - EXECUTION

- 3.4 TRENCHING AND BACKFILLING: The Contractor shall perform all excavation of every description and of whatever substances encountered, to the depths indicated on the Construction Drawings or as otherwise specified.
 - A. Protection of Existing Utilities: The Contractor shall check with the local utilities and the respective utility locator companies prior to starting excavation operations in each respective area to ascertain the locations of known utility lines. The locations, number and types of existing utility lines detailed on the Construction Drawings are approximate and do not represent exact information. The Contractor shall be responsible for repairing all lines damaged during excavation and all associated operations. All utility lines uncovered during the excavation operations, shall be protected from damage during excavation and associated operations. All repairs shall be approved by the utility company.
 - B. Hand Digging: Unless approved in writing otherwise, all digging within an existing cell site compound is to be done by hand.
 - C. During excavation, material suitable for backfilling shall be stockpiled in an orderly manner a sufficient distance from the banks of the trench to avoid

overloading and to prevent slides or cave-ins. All excavated materials not required or suitable for backfill shall be removed and disposed of at the Contractor's expense.

- D. Grading shall be done as may be necessary to prevent surface water from flowing into trenches or other excavations, and any water accumulating therein shall be removed by pumping or by other approved method.
- E. Sheeting and shoring shall be done as necessary for the protection of the work and for the safety of personnel. Unless otherwise indicated, excavation shall be by open cut, except that short sections of a trench may be tunneled if, the conduit can be safely and properly installed and backfill can be properly tamped in such tunnel sections. Earth excavation shall comprise all materials and shall include clay, silt, sand, muck, gravel, hardpan, loose shale, and loose stone.
- F. Trenches shall be of necessary width for the proper laying of the conduit or cable, and the banks shall be as nearly vertical as practicable. The bottom of the trenches shall be accurately graded to provide uniform bearing and support for each section of the conduit or cable on undisturbed soil at every point along its entire length. Except where rock is encountered, care shall be taken not to excavate below the depths indicated. Where rock excavations are necessary, the rock shall be excavated to a minimum over depth of 6 inches below the trench depths indicated on the Construction Drawings or specified. Over depths in the rock excavation and unathorized over depths shall be thoroughly back filled and tamped to the appropriate grade. Whenever wet or otherwise unstable soil that is incapable of properly supporting the conduit or cable is encountered in the bottom of the trench, such soil shall be removed to a minimum over depth of 6 inches and the trench backfilled to the proper grade with earth of other suitable material, as hereinafter specified.
- G. Backfilling of Trenches. Trenches shall not be backfilled until all specified tests have been performed and accepted. Where compacted backfill is not indicated the trenches shall be carefully backfilled with select material such as excavated soils that are free of roots, sod, rubbish or stones, deposited in 6 inch layers and thoroughly and carefully rammed until the conduit or cable has a cover of not less than 1 foot. The remainder of the backfill material shall be granular in nature and shall not contain roots, sod, rubbish, or stones of 2-1/2 inch maximum dimension. Backfill shall be carefully placed in the trench and in 1 foot layers and each layer tamped. Settling the backfill with water will be permitted. The surface shall be graded to a reasonable uniformity and the mounding over the trenches left in a uniform and neat condition.
- H. Except as otherwise required, compacted backfill shall be used under concrete pads, walkways, concrete paving, and asphalt concrete paving. The first 1 foot cover shall be of select materials such as excavated soils that are free of roots, sod, rubbish, or stones. The Company may reject any onsite or borrow materials which are considered unsuitable for the intended use of the fill.
 1. All fills shall be compacted to a dry density equal to at least 90 percent of the maximum dry density determined in accordance with ASTM D1557. The maximum density and optimum moisture content shall be determined by the Contractor on basis of laboratory tests conducted on the materials used in the fill.
 2. Adequacy of compaction shall be determined on the basis of in-place density determinations that shall be conducted by the Contractor while the fills are being placed. The results of these tests shall be the basis on which satisfactory completion of the work is judged. If the fills fail to meet the specified densities, the Contractor shall remove and recompact the soils until the specified densities are achieved.
- I. REMOVAL OF WATER: The Contractor shall provide and maintain adequate dewatering equipment to remove and dispose of all surface and ground water entering excavations and other parts of the work. Each excavation shall be kept dry during sub-grade preparation and continually thereafter until the construction to be provided therein is completed to the extent that no damage from hydrostatic pressure, flotation, or other cause will result. Ground water level shall be maintained at least 12 inches below the bottom of each excavation. Removal of water shall be in accordance with all state, federal, and local regulations. Contractor shall submit water removal plan to the Company.
- J. UNAUTHORIZED EXCAVATION: Except where otherwise authorized, indicated, or specified, all material excavated below the bottom of concrete structures which will be supported by the sub-grade shall be replaced with concrete placed monolithic with the concrete above. Material excavated below structures supported on piers shall be replaced with approved material. The material shall be compacted to a density equal to or greater than the density of the adjacent undisturbed soil.
- K. STRUCTURE EXCAVATION: Excavation for structures shall be done to lines and elevations indicated on the Construction Drawings and to the limits required to perform the construction work.
 - A. Excavated materials free of trash, rocks, roots, and other foreign materials, and which meet the specified requirements, may be used as required for the fills, embankments, and backfills constructed under these specifications.
 - B. Sub-grades for structures and trench bottoms which are otherwise solid, but which become soft on top due to construction operations, shall be reinforced with one or more layers of crushed rock or gravel.
 - C. STABILIZATION: Sub-grades for structures and the bottom of trenches shall be firm, dense, and thoroughly compacted.
 - A. Trench sub-grades which run beneath roads, or pass through structural backfill, shall be compacted to 95 percent of maximum density as determined by ASTM D1557.
 - B. Sub-grades for structures and trench bottoms which are otherwise solid, but which become soft on top due to construction operations, shall be reinforced with one or more layers of crushed rock or gravel.
 - D. STRUCTURE BACKFILL: Backfill around and outside of structures shall be deposited in layers not to exceed 6 inches in uncompacted thickness and mechanically compacted, using acceptable compaction techniques, to at least 95 percent of maximum density as determined by ASTM D1557, with a moisture content of plus or minus 3 percent of optimum, as determined by ASTM D698 when that test is appropriate, or to 70 percent relative density as determined by ASTM D4253 and D4254 when those tests are appropriate. Compaction of structure backfill by rolling will be permitted provided the desired compaction is obtained and damage to the structure is prevented. Compaction of structure backfill by inundation with water will not be permitted.
 - A. Material for structure backfill shall be composed of earth only and shall contain no wood, grass, roots, broken concrete, stones, trash, or debris of any kind.
 - B. No backfill shall be deposited or compacted in water.

C. All backfill material shall consist of loose earth having a moisture content such that the required density of the compacted soil will be obtained with the compaction method used. Moisture content shall be distributed uniformly, and water for correction of moisture content shall be added sufficiently in advance so proper moisture distribution and compaction will be obtained. Granular material shall be wet, not just damp, when compacted.

D. Particular care shall be taken to compact structure backfill which will be beneath pipes, drives, roads, or other surface construction or structures. In addition, wherever a trench will pass through structure backfill, the structure backfill shall be placed and compacted to an elevation at least 12 inches above the top of the pipe before the trench is excavated.

3.18 DISPOSITION OF MATERIALS: Excess excavated earth and construction material shall be removed from the job site and legally disposed of by the Contractor.

DIVISION 3 - CONCRETE

SECTION 03300 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

Contact engineer or construction manager for complete concrete specifications if such work is required.

SECTION 03600 - GROUT

PART 1- GENERAL

Contact engineer or construction manager for complete grout specifications if such work is required.

DIVISION 5 - METALS

SECTION 05120 - ICE BRIDGE AND OTHER STRUCTURAL STEEL

PART 2 - PRODUCTS

- 2.1 ICE BRIDGE MATERIALS:
 - A. Ice Bridge posts shall be fabricated of 3-inch schedule 40 galvanized steel, ASTM A-53, Grade B (seamless). Posts shall be installed a minimum of 3 feet 6 inches below finish grade and backfilled with 3000 p.s.i concrete. Post tops shall be capped with steel pipe caps. Maximum horizontal separation between posts shall be 8 feet on center.
 - B. Ice Bridge material shall be McNichols "Grip Strut" 10 diamond plank, 24 inches wide and 3 inches deep; part number 103014 or approved equal.
 - C. Ice Bridge components shall be hot dip galvanized and connected in an electrically continuous fashion per the manufacturer's recommendations. Any site penetrations or saw cuts to galvanized metal shall be treated with two coats of a zinc rich cold galvanizing paint as per ASTM A 780 standards.

2.2 STRUCTURAL STEEL MATERIALS: Conform to the latest edition of applicable standards and to all applicable codes and requirements of local authorities having jurisdiction, whichever is more stringent. All structural steel shall be in accordance with the latest applicable requirements of AISC, ASTM, ACI, CRSI, AWS and all other applicable standards.

- 2.3 All steel shall be galvanized in accordance with ASTM A36 unless noted on the construction drawings.
- 2.4 Rolled steel shapes, plates, and bars shall be no less than 3/16 inches in thickness and shall comply with ASTM A-36 as a minimum.
- 2.5 Steel pipe shall comply with ASTM A-501 or ASTM A-53, Type E or S, Grade B. A-500 Grade B steel may be substituted.
- 2.6 Steel tube shall comply with ASTM A-500, Grade B.
- 2.7 Galvanized steel grating shall be a minimum 3/4 inch x 1/8 inch at 3 /16 inches on center.
- 2.8 Galvanized checkered plate shall be a minimum 3/16 inch.

PART 3 - EXECUTION

- 3.1 ICE BRIDGE:
 - A. The Contractor is responsible for installing an Ice Bridge and support posts between the BTS radio equipment and the tower. At no point shall the Ice Bridge structure be mechanically connected to the tower. Cabling supports shall be designed to accept snap-in type hangers and accommodate a minimum coax or waveguide bending radius of 20 inches.
 - B. Each tier shall be vertically and horizontally aligned with the cable entry ports on the shelter consisting of three tiers capable of holding 5 runs of 1-5/8 inch coaxial cable each for a total of 15 coaxial cables. The cover shall be aligned to allow for easy access to the cabling and be of sufficient width and durability to prevent damage to the cable that might otherwise be caused by falling ice, bolts, nuts or hand tools. The entire structure, including cover, shall be sufficiently rigid to prevent cable damage caused by movement of the structure. Cover shall continue to within 2 inches of shelter wall and waveguide ladder.
 - C. Provision shall be made to ground the Ice Bridge structure as specified in Division 16.

3.2 STRUCTURAL STEEL FABRICATION: All shop fabrication and assembly of structural steel shall be in accordance with AISC specifications and as indicated on the approved shop drawings. All materials shall be properly marked for field assembly and for identification as to the location for which it is intended. Materials shall be fabricated and delivered in an order to expedite erection and minimize field handling of materials.

3.3 WELDING:

- A. Welding shall be performed by a certified welder and shall conform to requirements for shielded metal arc welding of the Standard Code for Arc and Gas Welding of the American Welding Society (AWS D1.1)
- B. Electrodes shall comply with AWS Code and shall be classified E-70 electrodes as a minimum. Where finishing is required, complete the assembly, including welding of units, before the start of finishing operations. Provide finish surfaces of exposed members that are free from markings, burrs and other defects.
- C. Welded construction shall comply with AWS Code for procedures, appearance and quality of welds and methods used in correcting welded work. Assemble and weld

built-up sections by methods that will produce correct dimensions without warp.

3.4 CONNECTIONS:

- A. Contractor shall provide all hardware required to complete field erection of structure as indicated by Contract Documents or these specifications.
 - B. High strength threaded fasteners shall be installed in accordance with AISC Specifications for Structural Joints Using ASTM A-325 or A-490 Bolts. Use A-325N bearing-type connection bolts unless noted otherwise.
 - C. Grating and plates shall be fastened with saddle clips. The necessary holes to complete all phases of construction shall be provided and called out on the approved shop drawings. All holes shall be drilled or punched perpendicular to metal surfaces, flame cut or burned holes will not be permitted.
 - D. All unfinished threaded fasteners shall comply with ASTM A-307, Grade A, regular low-carbon steel bolts and nuts with hexagonal heads.
 - E. All high strength threaded fasteners shall be heavy hexagonal bolts and nuts with hardened washers, all from quenched and tempered medium carbon steel complying with ASTM A-325.
- 3.5 REPAIR: Repair all damaged galvanized steel with "Galvanox," "Dry Galv.," or "Zinc-It.," or approved equal, per the manufacturer's instructions.

SECTION 07500 - ROOF CUTTING, PATCHING AND REPAIR

PART 1 - GENERAL

- 1.4 SUBMITTALS:
 - A. Pre-Construction Roof Condition Analysis Reports: Complete a roof inspection and report prior to the installation of Sprint equipment on any rooftop build requiring roof penetration. At a minimum inspect all areas impacted by the addition of the Sprint equipment. Roof inspection reports should be uploaded into SMS using task # 234.
 - B. New Roofing Material Product Data: Submit manufacturer's product data and installation instructions for each material and product used.
 - C. Shop Drawings: Provide large scale shop drawings for installation of all parts of the work. Provide plans, and details of seams, connections and accessory items. Show layouts of tapered insulation and locations of drains. Show interfaces and relationships to work of other trades.
 - D. Certifications and Warranty:
 1. Upon completion of work of this Section, submit certification by existing roof manufacturer acknowledging that all work performed is acceptable and that the entire roof remains under warranty.
 2. Maintain existing warranty if applicable. Take no action which would void existing warranty.

PART 2 - PRODUCTS

- 2.1 MATERIALS:
 - A. Existing Roof Materials and Compatibility: Furnish specific product acceptable to manufacturer of roofing membrane which will not compromise the roofing manufacturer's warranty.
 - B. Substrate Board: Glass-mat, water-resistant gypsum ASTM C 1177 or match existing.
 - C. Vapor Retarder: Match existing.
 - D. Insulation: Extruded polystyrene board insulation, or match existing.
 - E. Tapered Insulation: Fabricated to provide proper drainage.
 - F. Recovery Board over Insulation: Match existing, mechanically fastened.
 - G. Membrane and Flashing: Match existing.
 - H. Sheet Metal Accessories: Follow SMACNA and NRCA recommendations. Materials and finishes to match existing.
 - I. Ballast: Match existing.
 - J. Walkway Protection Board: Compatible with membrane.

PART 3 - EXECUTION

- 3.1 INSTALLATION:
 - A. Inspect substrate and report unsatisfactory conditions in writing. Beginning work on site means Contractor's acceptance of existing roof conditions.
 - B. Comply with roof system manufacturer's instructions and recommendations on any penetrations, repairs, etc.
 - C. Install insulation with tightly butted joints and neatly fitted around penetrations.
 - D. Where applicable, distribute ballast uniformly to 10 pounds per square foot or more as required by Factory Mutual. Obtain approval of ballast weight from the building owner before loading roof.
 - E. Install walkway protection over an additional layer of membrane at locations indicated and where required to provide access to roof mounted equipment.
 - F. Restore or replace damaged components. Protect work from damage.

SECTION 07840 - FIRESTOPPING

PART 1 - GENERAL

- 1.5 QUALITY ASSURANCE:
 - A. Comply with governing codes and regulations. Provide products of acceptable manufacturers which have been in satisfactory use in similar service for three years. Use experienced installers. Deliver, handle, and store materials in accordance with manufacturer's instructions.
 - B. Fire Performance: ASTM E 119, ASTM E 814, and local regulations.

Sprint

6391 Sprint Parkway
 Overland Park, KS 66251

Alcatel-Lucent



1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

NETWORK VISION MMBTS LAUNCH NORTHERN CT MARKET

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



C	1/08/13	FINAL CDS ISSUED
B	10/25/12	FINAL PRELIM CDS
A	10/03/12	90% CD REVIEW

MARK	DATE	DESCRIPTION	ISSUE NUMBER	DATE ISSUED
FINAL				01/08/13

PROJECT TITLE:
RASMUSSEN WATER TANK
 SITE #: CT03XC202

PROJECT INFORMATION:
 160 PLANTATION ROAD
 EAST WINDSOR, CT 06016
 HARTFORD COUNTY

SHEET TITLE:
SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	23001
SHEET NUMBER	SP-1

SECTION 09910 - PAINTING

PART 2 - PRODUCTS

2.1 MATERIALS:

A.Manufacturers: Benjamin Moore, ICI Devco Coatings, PPG, Sherwin Williams or approved equal. Provide premium grade, professional-quality products for coating systems.

B.PAINT SCHEDULE:

- Interior Gypsum Drywall and Ceilings: One coat latex primer plus two coats latex eggshell finish.
- Exterior and Interior Steel Doors, Frames and Ferrous Metals: One coat rust-inhibiting primer, plus two coats alkylid enamel semi-gloss finish.
- Exterior Antennae: One coat of primer and two finish coats. Paint for antennae shall be non-metallic based and contain no metallic particles. Submit MSDS sheet to the Owner for approval. Provide colors and patterns as required to mask appearance of antennae on adjacent building surfaces and as acceptable to the Owner. Refer to antenna manufacturer's instructions whenever possible.

SECTION 11007 - ANTENNA ASSEMBLY AND INSTALLATION

PART 2 - PRODUCTS

2.1 MATERIALS: Panel and Microwave Antennas: Refer to the Drawings for types and quantities. The following paragraphs outline the materials used for an Omni site and a sectored site.

B.Sectored Site:

- ESMR (Enhanced Specialized Mobile Radio) Panels: Located per project requirements.
- Microwave: High performance type, located per project requirements.
- GPS: Located on the south side of obstructions.

C.Antenna Mounts:

- Ballast mounts for rooftop applications shall be Valmont/Microfect No. 31-99540 (12 foot separation) or approved equal.
- Facade-mounted antennas shall comply with site-specific mounting requirements indicated on the Drawings.

D.Surge Arrestors:

- Refer to the drawings for types and quantities. All surge arrestors shall be models that are approved by the Company before installation.
- All surge arrestors for ESMS antennas shall terminate in 7/16 DIN connectors with MALE connectors toward the antenna and FEMALE toward equipment.
- All surge arrestors for GPS and microwave antennas shall be Type N with MALE connectors toward the antenna and FEMALE toward equipment.
- Surge arrestors shall be mounted on a trapeze or other grounding arrangement to ensure that surge currents are properly grounded.

E.Cross-Band Couplers: Refer to drawings for types and quantities. All couplers shall be models that are approved by the Company before installation.

F.Tower-Mounted Amplifiers (TMA or TTA): Refer to drawings for types, quantities, and mounting methods. All tower-mounted amplifiers shall be models that are approved by the Company before installation.

G.Low Noise Amplifiers (LNA): Refer to drawings for types, quantities, and mounting methods. All LNAs amplifiers shall be models that are approved by the Company before installation.

H.Connect antenna, coax, GPS, etc. to grounding system as indicated on the site plans and as indicated in Division 16.

PART 3 - EXECUTION

3.4 ANTENNA INSTALLATION:

A.The Contractor shall assemble all antennas onsite in accordance with the instructions supplied by the manufacturer. Antenna height, azimuth, and feed orientation information shall be a designated on the Construction Drawings. Azimuth delineation will be determined by appropriate RF Engineer.

B.Remote tilt antenna assemblies are to be completely assembled on the ground, run through their full range of motion using the controller and full cable assembly before being placed on the tower. Once installed, they are to be run through this process again prior to the tower crew leaving the site.

C.The serial numbers, azimuths, and downtilts are to be recorded and the information left on site for the RF and start up crew to use at the time of hand over to Field Operations.

D.The Contractor shall install all antennas and side struts in accordance with the Construction Drawings and the manufacturer's recommendations.

E.The Contractor shall position the antenna on tower pipe mounts so that the bottom strut is level. The pipe mounts shall be plumb.

F.Antenna Mounting Requirements: Refer to the Job Specifications for site specific antenna mounting details such as radiation centerlines, azimuths and antenna mount designs. Provide U-bolts and brackets to fasten antennas to side arms on pipe mounts. All mounts and mounting hardware shall be hot dipped galvanized or stainless steel material. All antenna installations shall conform to the following specifications.

- Panel Antennas: Panel antennas shall be fastened to the vertical pipe mounts on the sector head frame supplied with the tower. Adjust pipe mounts, as necessary, on the sector headframe to provide 12 feet of horizontal separation between the outer most panel antennas unless otherwise specified. If necessary, raise or lower the headframe to achieve the correct radiation centerline as per the Drawings.

G.Ballast Mounts: Install ballast mounts in accordance with manufacturer's

specifications and per the Construction Drawings and Details.

H.All unused antenna ports shall be terminated with a terminating load.

I. GPS antennas shall be installed at a location identified on the construction drawings. Effort should be made to locate GPS antennas on either the shelter or the ice bridge.

3.5 Coaxial Cables and Waveguide Installation:

A.The Contractor shall route, test, and install all coaxial cables as indicated on the Construction Drawings and in accordance with the manufacturer's recommendations.

B.The routing of the coax shall be checked for interference with other tower appurtenances before installation and vertical waveguide/coax hangers shall be installed on the tower waveguide ladder.

C.The coax shall be hoisted, connected to the antenna feed, secured to the hangers, and oriented to provide the correct entrance plane to the equipment cabinet. The waveguide/coax shall then be cut to the appropriate length to reach the equipment.

D.The waveguide/coax shall be grounded in accordance with the Construction Drawings and the Company grounding specifications Division 16.

E.The waveguide/coax shall be routed in accordance with the structural requirements. If possible, coax shall be routed on the inside of monopoles or down the waveguide ladder in a manner that will prevent obstruction of the climbing ladder. Additionally, the waveguide/coax shall be positioned in the best possible location to protect it from damage. The bending radius of the coax shall not be less than the manufacturer's specifications.

F.Extreme care shall be taken to avoid damage to the waveguide/coax during handling and installation. The Company will furnish to the Contractor port assignments, if applicable, prior to waveguide installation.

1. Waveguide Ladder (Lattice towers only): Waveguide ladders shall be used to support all coaxial cable, microwave waveguide cable and any baseband cable on the tower. One ladder, 18 cables wide, shall be mounted on the tower per the tower structural requirements. The rungs on the waveguide ladders shall be spaced a maximum of 4 feet apart.

2. Ice Bridge: An Ice Bridge will be installed between the tower and the shelter to support all cabling. Use stainless steel snap-in type hangers to support cables on the Ice Bridge. Provide a drip loop in all cabling between the base of the tower and the Ice Bridge. Install in accordance with manufacturer's specifications.

3. Fastening Cables: Waveguide and coaxial cable lines shall be raised on the tower using properly sized split type, lace-up hoisting socks attached to each cable every 200ft. All cables shall be permanently fastened to the tower using a hoisting sock at the top of the tower. Use stainless steel snap in type cable hangers at each wave guide ladder rung (on lattice towers only). Do not drill holes in tower members, use angle member adapters and stainless steel butterfly clips, to attach cabling to tower. Make sure that there is no strain on any cable connector due to the cable weight.

4. Jumpers: Jumpers between the feed lines and antennas or tower top amplifiers shall consist of 1/2 inch foam dielectric, outdoor rated coaxial cable. Do not use Superflex outdoors. Secure jumpers to the side arms or head frames using stainless steel tie wraps or stainless steel butterfly clips. Be certain that there is no strain on any connector due to the weight of the jumper cable, or its method of installation.

5. Bending Radius: Cables shall not exceed the minimum bending radius as determined by the cable manufacturer.

6. Cable Installation:

a. Inspect cable prior to use for shipping damage, notify the Company Representative of any damage. Any cable ends cut shall be covered to protect them from weather and entry of foreign matter. If using bulk cable, field attach antenna connector before hoisting cable.

b. Cable Routing: Cable installation shall be planned to ensure that the lines will be properly routed in a neat and orderly manner. Avoid twisting and crossovers in the building, along the tower face, and waveguide raceways. Secure cable at maximum spacing of 4 feet on center making sure that the cable weight is equally distributed and no strain is placed on connectors or antennas.

c. Hoist cable using proper hoisting grips. Hoist slowly and carefully. Prevent kinking and snags when around tower members. Bend cable slowly at the maximum practical bend radius consistent with good installation practice. Avoid using minimum cable bends.

7. Termination at Shelter and Entry Plate:

a. All cabling shall enter the building through the waveguide entry plate and be properly weather sealed with a cable boot fabricated for the size of the cable. Cable boots are not to be cut to fit in the field. Coaxial cables shall be terminated within 18 inches inside the shelter and fitted with a surge suppressor.

b. Coax Port Assignments for Shelter Sites: The coax will be installed and marked per the Antenna Transmission Line Acceptance Standards and the Detail - Coax Port Assignments.

8. Grounding of transmission lines: All transmission lines shall be grounded in accordance with the Company grounding standards.

9. Labeling Coaxial Cables: All cables shall be marked with 2 inch UV resistant colored tape and stencil tagged per the latest version of the RF Antenna Transmission Line Acceptance Standards. All coaxial cables shall be at the top, bottom, both sides of the entry port and all locations where the cable penetrates a wall, ceiling or floor. Antenna locations should be determined from the reference point of standing in the center of the tower looking out. Labeling should be adherent with industry standard for T1 transmit and receive.

10. Cable Connections:

a. Use only cable connectors recommended by the cable manufacturer.

b. Connectors for all main station antenna cables shall be 7/16 DIN.

c. Connectors for GPS antennas shall be Type N.

d. Connectors for microwave antennas, unless otherwise noted, shall be Type N.

e. Install and tighten connectors per manufacturer's instructions.

f. All exterior connectors, connector splices, jumpers, ground kits, etc., shall be weatherproofed using connector/splice weather proofing kits. Weatherproofing shall be installed in strict accordance with manufacturer's instructions.

3.6 WEATHERPROOFING CONNECTORS AND GROUND KITS:

A.All connectors and ground kits shall be weatherproofed using butyl rubber weatherproofing and tape. This installation must be done in accordance with the manufacturer's recommendation or as shown on the construction drawings (whichever is greater). If no direction is provided, weatherproofing must be done per Sprint Standard Construction Specification for Wireless Sites Section 11007-3.6 A-D.

SECTION 11008 - BASE TRANSCEIVER STATIONS (BTS) AND RELATED EQUIPMENT INSTALLATION

PART 3 - EXECUTION

3.1 GENERAL: The Contractor shall install the BTS and associated equipment at the locations shown on the Construction Drawings and in accordance with the manufacturer's recommendations. Minimum requirements for performance of the work are:

A. Contractor shall be responsible for all services associated with the delivery, bolt-down and installation of Sprint Nextel's radio equipment.

B. Equipment installation procedures shall fully comply and strictly adhere to original equipment manufacturer's installation instructions. Contractor shall immediately cease any work if inconsistencies are found between Sprint Nextel Standards and the manufacturer's documentation. Contractor shall seek guidance from Sprint Nextel or its designated project representative for resolution.

C. Contractor shall provide a fully functioning and operable radio system at the wireless facility. Contractor shall complete and provide all documentation of the Work.

3.1 CONTRACTOR PROVIDED MATERIAL: Contractor shall obtain by any means necessary the original equipment manufacturer specifications and strictly adhere to them. Contractor shall provide all required tools, test equipment, materials, labor, and equipment including anchor kits and external mounting hardware for positioning and securing final bolt-down of the radio equipment. Contractor shall furnish all necessary grounding products to successfully bond the radio equipment to the site ground ring or shelter grounding system in accordance with the construction drawings.

3.2 WORK SCHEDULING: Contractor shall provide and coordinate scheduling of licensed electrician qualified to perform the work of connecting the power and grounding to the radio equipment along with any other connections or installations of radio equipment requiring a licensed electrician per the manufacturer specifications.

3.3 MISC WORKS:

A. Contractor shall remove radio equipment from crates, wrapping, or pallets and properly dispose of all packaging materials. Contractor shall verify the proper radio equipment is being installed at the correct site. The equipment is assigned a site specific asset number and must be installed at the designated location.

B. Contractor shall measure equipment platform, pad, interior space or shelter space and verify exact equipment layout in accordance with the construction drawings and set the radio equipment accordingly. Contractor shall set equipment cabinets and racks in the locations indicated on the construction drawings or as otherwise directed by Sprint Nextel or its designated project representative in writing.

C. Contractor shall install batteries, rectifiers, additional RF carriers, EV-DO cards, amplifiers, circuit packs, and all other radio equipment for the site as required by the manufacturer specifications.

D. Contractor shall ensure GPS is installed and ready for connection to the BTS. Contractor shall install or coordinate for the installation of the Global Positioning System (GPS) antenna via the construction contractor and as specified by the manufacturer as applicable.

E. Contractor shall procure and install:

1. DC wiring with conduit or cable tray as indicated between power supply cabinets and radio cabinets as shown on the Construction Drawings.

2. AC wiring from Load center to power supply or radio cabinet in conduit or cable tray as indicated in the manufacturer specifications.

3. Circuit breakers in spare sockets in the Load Center as indicated in the manufacturer specifications.

4. Alarm cabling from radio equipment to telco alarm terminal strip in conduit or cable tray. Contractor shall be responsible to extend conduit or cable tray as necessary to successfully complete the work.

5. T1 and alarm cables extending conduit or cable tray as necessary to successfully complete the work.

6. Jumpers from the coax main line feeds to the radio equipment. Contractor is to perform Sweep testing of lines or coordinate with construction contractor to perform this activity.

F. Contractor shall energize the equipment according to manufacturer specifications and conduct functionality tests of the AC and DC power systems correcting any deficiencies in the work as applicable.

DIVISION 16 - ELECTRICAL

SECTION 16000 - BASIC ELECTRICAL REQUIREMENTS

PART 1 - GENERAL

1.4 CODES AND STANDARDS:

A.The codes and standards referenced in Division 16 shall be the most current revision, regardless of the actual year indicated hereinafter, except as otherwise required by Division 1.

B.The entire electrical installation shall comply fully with the requirements of all authorities having jurisdiction.

C.The Work shall comply with applicable requirements of the following:

- U.S. National Electrical Code (NEC).
- U.S. National Fire Protection Association (NFPA) codes and standards.
- U.S. Occupational Safety and Health Act (OSHA).
- Other Codes and Standards as referenced in the individual technical sections of Division 16.

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT: All materials and equipment specified in Division 16 of the same type shall be of the same manufacturer and shall be new, of the best quality and design, and free from defects.

2.2 FIRESTOPPING MATERIAL:

A.Firestopping Material: Subject to compliance with requirements. Provide one or more of the following:

- Spec Seal PEN 300 Sealant by STI
- Spec Seal "Type SSP100" Firestop Mastic/Putty by STI
- Spec Seal "Type SSB" Firestop Pillows by STI
- Similar products by Nelson or 3M

PART 3 - EXECUTION

3.1 INSTALLATION:

A.Verify all dimensions by field measurements.

B.Sequence, coordinate, and integrate installations of materials and equipment for efficient flow of the Work. Give particular attention to large equipment requiring positioning prior to the closing of a structure.

C.All cutting and channeling shall be accomplished in a neat and workmanlike manner, without the removal of excess materials. Contractor shall patch, replace and repair all cut and channeled areas with material similar to adjacent construction.

D.Coordinate connection of systems with exterior underground and overhead utilities and services. Comply with requirements of governing regulations, franchised service companies and controlling agencies. Provide required connection for each service.

E.Coordinate location of all equipment, boards, lights, outlets, switches, boxes, conduits, electrical trays with other services and utilities. Locate all equipment, fixtures and conduits to clear windows, door openings and other services and utilities. Route conduits so as to clear valves and other similar obstructions requiring access. Follow manufacturer's recommendations for installation methods not otherwise specified.

F.Equipment shall be installed at locations shown on the drawings. Any changes to locations of installed equipment, facilities, or other appurtenances shall be noted as "Red-Lines" and submitted with "As-Built" package upon project completion. All changes require appropriate Project Manager pre-approval

G.Working spaces and accessibility shall not be less than specified in the National Electrical Code for all voltages and equipment specified.

3.4 FIRESTOPPING: Apply firestopping material as recommended by the manufacturer to maintain the fire resistance rating of the barrier being penetrated. Utilize suitable templates or dams to properly retain material in large openings.

3.5 SUPPORTING DEVICES:

A.Install supporting devices to fasten electrical components securely and permanently in accordance with NEC.

B.Coordinate with the building structural system and with other trades.

C.Raceway supports shall conform to the manufacturer's recommendations for selection and installation of supports.

D.The strength of each support shall be adequate to carry the present and future load multiplied by a safety factor of at least four. Where this determination results in a safety allowance of less than 200 pounds, provide additional strength until there is a minimum of 200 pounds safety allowance in the strength of each support.

E.Install individual and multiple (trapeze) raceway hangers and riser clamps as necessary to support the raceways. Provide U-bolts, clamps, attachments, and other hardware necessary for hanger assembly and for securing hanger rods and conduits.

F.Support parallel runs of horizontal raceways together on trapeze-type hangers.

Sprint

6391 Sprint Parkway
Overland Park, KS 66251


Alcatel-Lucent

R
RAMAKER
& ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: James R. Skowronski
Date: 1/08/2013

MARK	DATE	DESCRIPTION
C	1/08/13	FINAL CDs ISSUED
B	1/02/12	FINAL PRELIM CDs
A	1/03/12	90% CD REVIEW

ISSUE PHASE	DATE ISSUED
FINAL	01/08/13

RASMUSSEN WATER TANK
SITE #: CT03XC202

PROJECT INFORMATION:
160 PLANTATION ROAD
EAST WINDSOR, CT 06016
HARTFORD COUNTY

SHEET TITLE:
SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER: 23001
SHEET NUMBER: SP-2

Copyright 2012 - Ramaker & Associates, Inc. - All Rights Reserved
 DRAWN BY: TDN
 CHECKED BY: KAB
 C:\Users\tnelson\local settings\temp\AcF\publish_665223001 Rasmussen Water Tank Vision Project CDs.dwg Printed by: T Nelson on Jan 08, 2013 - 9:45am
 This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.

- G. Support miscellaneous electrical components as required to produce the same structural safety factors as specified for raceway supports. Install metal channel racks for mounting cabinets, panelboards, disconnects, control enclosures, pull boxes, junction boxes, transformers and other devices.
- H. In open overhead spaces, cast boxes threaded to raceways need not be supported separately except where used for fixture support. Support sheet metal boxes directly from the building structure or by bar hangers. Where bar hangers are used, attach the bar to raceways on opposite sides of the box and support the raceway with a listed type of fastener not more than 24" (600 mm) from the box.
- I. Install conduit sealing fittings for conduit penetrations of concrete wall exterior or below grade as specified or required by code.
- J. Unless otherwise indicated on the drawings, fasten electrical items and their supporting hardware securely to the structure in accordance with the following:
 1. Fasten by means of wood screws on wood,
 2. Toggle bolts on hollow masonry units,
 3. Concrete inserts or expansion bolts on concrete or solid masonry,
 4. Machine screws, welded threaded studs, or spring-tension clamps on steel,
 5. Explosive devices for attaching hangers to structure shall not be permitted.
 6. Do not weld conduit, pipe straps, or items other than threaded studs to steel structures.
 7. In partitions of light steel construction, use sheet metal screws.
- K. Ensure that the load applied by any fastener does not exceed 25 percent of the proof test load.
- L. Use vibration and shock-resistant fasteners for attachments to concrete slabs.

SECTION 16001 - ELECTRICAL MATERIALS AND EQUIPMENT

PART 2 - PRODUCTS

- 2.1 DISCONNECT SWITCHES:**
- A. Furnish and install externally operated, quick-make, quick-break, safety, fused and non-fused heavy duty disconnect switches where shown on the drawings and where required by NEC. Switches shall be safety type as manufactured by Square "D", I-T-E, Cutler-Hammer/Westinghouse, GE, or approved equal.
 - B. Switches shall be rated for horsepower of motors controlled. Indoor switches shall be mounted in NEMA 1 enclosures, except as indicated. Switches located exterior to building shall be mounted in NEMA 3R enclosures except as indicated. Switches utilized as service entrance equipment shall be so labeled.
 - C. Disconnect switches shall be provided at all equipment.
 - D. Furnish Class R fuse kits for all fused switches utilizing RK-1 or RK-5 fuses.

- 2.2 CIRCUIT BREAKERS FOR INSTALLATION INTO PANELBOARDS:**
- A. For application in panelboards, provide circuit breakers of the same manufacturer as the Original Equipment Manufacturer (OEM) panel, integral to the cabinet.
 - B. Circuit breaker configuration (bolt-on or clip-on) shall match that of breakers installed and shipped with the cabinet.
 - C. Amps Interrupting Capacity (AIC) of field supplied and installed circuit breakers shall not be less than the printed withstand and interrupting rating of the load center.

- 2.3 SEPARATELY ENCLOSED CIRCUIT BREAKERS:**
- A. Furnish and install where indicated molded case circuit breakers, trip indicating, trip free, thermal magnetic type with electrical characteristics and ratings as indicated. Short circuit withstand and interrupting rating shall be as required by the fault current indicated.
 - B. Provide NEMA 1 enclosures indoor, NEMA 3R outdoor enclosure except as otherwise indicated. Circuit breaker handles shall be lockable in the OFF position.
 - C. Provide service entrance label where indicated.
 - D. Provide equipment by Square "D", General Electric, Siemens, or Cutler-Hammer/Westinghouse.

- 2.7 CABLE TRAY:**
- A. Furnish and install a complete cable tray system as indicated on the drawings and as manufactured by B-Line Systems, Inc., Square "D" Company or approved equal.
 - B. Cable tray, fittings and accessories shall be steel, hot-dipped galvanized after fabrication or aluminum as indicated.
 - C. Cable tray shall be ladder-type, trough-type, channel-type, or as indicated.
 - D. Cable tray system shall be furnished with all dimensions, covers, necessary tees, crosses, risers, elbows, connectors, hangers, etc. of same material as cable tray and as shown on drawings and as required by cable tray manufacturer.
 - E. Barriers shall be installed in cable tray to separate cables of different systems such as low and high voltage, telephone, data, etc. Barriers shall be of same material as cable tray.
 - F. Cable tray shall be installed level and, plumb in accordance with manufacturer's instructions.

- 2.9 COMMUNICATION CABLING FOR CELL SITE T1 CIRCUITS:**
- A. This specification applies to the T1 circuit to be installed by this Contractor between the Network Interface Unit (NIU) and the Company radio equipment.
 - B. In indoor locations and in underground conduits in dry climates cabling shall be PVC-insulated tinned solid copper 24 - 24 AWG twisted pairs, UL Type CMR, with overall braided shield and PVC jacket, except as otherwise recommended by the manufacturer.
 - C. In underground conduits in wet climates, provide Outdoor plant cable, gel filled,

- 24 - 24AWG twisted pairs.
- D. Exception: In all cases for installations in Lucent BTS markets, utilize the T1 cable shipped with the BTS, whenever the cable length is sufficient for the installation.
- E. Adhere to Bellcore standards for cable color coding.

- 2.12 GROUNDING ELECTRODES AND CONDUCTORS:**
- A. Comply with Exhibit C - Cell Site Grounding Design.
 - B. Equipment Grounding Conductor:
 1. Bare copper conductor or insulated green wire ground as specified herein.

- 2.13 BOXES AND COVERS:**
- A. Pull and junction boxes shall be sized in accordance with NEC requirements and shall be installed so that the conductors in them are accessible without removing any part of the structure.
 - B. Interior switch and outlet boxes flush mounted in finished areas shall be code gauge pressed plated steel, Midland Ross or approved equal, suitable for the device to be installed. Covers shall be as hereinafter specified in paragraph "Device Plates in Finished Areas."
 - C. Device and pull boxes surface-mounted above accessible ceilings and within unfinished enclosed Mechanical rooms shall be as specified above sized for the conductors within and shall have pressed plated steel screw attached covers.
 - D. Interior switch, pull, junction and outlet boxes surface mounted in unfinished industrial areas shall be (cast aluminum or) plated cast alloy, threaded, suitable for the device to be installed, Crouse-Hinds FS/FD series or approved equal. Covers shall be screw attached plated iron alloy suitable for the box and device. Switch plate covers shall be "guarded" style.

- E. Pull boxes exterior to the building and in interior industrial areas shall be plated cast alloy, heavy duty, weatherproof, dust proof, with gasket, plated iron alloy cover and stainless steel cover screws, Crouse-Hinds WAB series or equal.
- F. Conduit outlet bodies shall be plated cast alloy with similar gasketed covers. Outlet bodies shall be of the configuration and size suitable for the application. Provide Crouse-Hinds Form 8 or equal.
- G. Exterior switch and outlet boxes shall be recessed mounted except as noted, cast aluminum or plated cast alloy with wet location, Crouse-Hinds series WLRD covers, or equal. Masonry boxes mounted recessed in exterior wall shall be furnished with weatherproof covers.
- H. Manufacturer for boxes and covers shall be Hoffman, Square "D", Crouse-Hinds, Cooper, Adale, Appleton, O-Z Gedney, Raco, or approved equal.

- 2.21 LIGHTNING PROTECTION:**
- A. Comply with the latest revisions of Exhibit D - Cell Site Lightning - Surge Protection and Exhibit C - Cell Site Grounding Design.

- 2.26 SURGE SUPPRESSION**
- A. Except as otherwise required, surge suppression devices are Company furnished materials

PART 3 - EXECUTION

- 3.1 GROUNDING:**
- A. Electrical services, circuits and systems, enclosures and equipment shall be grounded in accordance with Article 250 of the National Electrical Code.
 - B. Grounding shall be provided as indicated for feeder, branch circuit, control, and instrument circuits.
 - C. Equipment Grounding Conductor: Furnish and install a separate insulated green wire grounding conductor with circuit conductors for all feeders and branch circuits.
 - D. Furnish and install an insulated green wire grounding conductor in non-metallic raceways unless designated otherwise for telephone or data cables.
 - E. Telephone and communication system services, circuits, enclosures and equipment shall be grounded in accordance with paragraph 800-33 and paragraph 800-40 of the National Electrical Code.
 - F. Separately derived AC systems that are required to be grounded by the NEC shall be grounded in accordance with paragraph 250-26 of the NEC.
 - G. Furnish and install insulated copper ground conductors in conduit from main electrical service equipment or electrical room ground bus and connect to main metallic water service entrance (if available) with ground clamps. Connect ground conductor to the street side of water main where a dielectric main water fitting is installed.
 - H. Furnish and install ground fault protection where required by code and as required by the specifications and drawings. Installation of ground fault protection shall be in accordance with NEC.

- 3.3 CONDUIT AND CONDUCTOR INSTALLATION:**
- A. Conduit and conductors shall be sized as required by NEC and shall be installed continuous and complete from outlet to outlet, panels and junction boxes.
 1. In order to closely follow the lines of the structure, maintain close proximity to the structure and keep conduits in tight envelopes. Changes in direction to route around obstacles shall be made with conduit outlet bodies in exposed locations except as otherwise indicated, and in accordance with good construction practice.
 2. Other changes in direction shall be made with trade elbows, keeping conduits grouped in tight envelopes following the lines of the structure and maintaining close proximity to the structure except as otherwise indicated, and in accordance with good construction practice.
 3. Route conduits according to the envelopes, areas, details and sections, if any, identified on the drawings.
 - B. Conduits shall be fastened securely in place with approved non-perforated straps

- and hangers. Explosive devices for attaching hangers to structure will not be permitted. Conduits shall be concealed in finished areas. Conduit shall be exposed in unfinished areas.
- C. Conduit shall be installed in a neat and workmanlike manner, parallel and perpendicular to structure wall and ceiling lines. Conduit shall be installed as required by the design of the structure and placed in concrete forms so as not to interfere with reinforcing or strength of slabs, joists or beams. Conduit shall clear all pipes and ducts and depressions in floors. Permission of Engineer shall be obtained as to location of conduit in reinforced concrete slabs, joists and beams.

- D. All conduit shall be fished to clear obstructions. Ends of conduits shall be temporarily capped to prevent concrete, plaster or dirt from entering.
- E. Conduits shall be rigidly clamped to boxes by galvanized malleable iron bushing on inside and galvanized malleable iron locknut on outside and inside.
- F. EMT conduits (if allowed) shall have approved EMT threaded type box connectors and couplings. Set screw connectors and couplings shall not be acceptable.

- G. Conductors shall be pulled in accordance with accepted good practice. Where more than one conductor is installed in the same conduit all conductors within the conduit shall be pulled simultaneously. Pull shall not deform conductors. Approved type lubricant may be used in pulling conductors where required.
- H. Splices and taps shall be kept to a minimum and made in accordance with the NEC.

- I. Where conduit crosses an expansion joint, an expansion and deflection fitting shall be installed in the conduit.
- J. Conduit Entrance Seals:
 1. All conduits penetrating new concrete walls exterior or below grade shall be sealed at penetrations with conduit entrance seal, Type FSK by O-Z/Gedney or approved equal.
 2. All conduit penetrating existing concrete walls exterior or below grade shall be sealed on both sides with O-Z/Gedney Type CSML seals.

- K. Conduits and cables passing through all floors, fire rated walls, and smoke partitions shall be sealed in accordance with NEC-300-21. Furnish and install O-Z/Gedney fire seal fittings or approved equal at those locations. At the Contractor's option, Specified Technologies Inc. Model PEN200, UL-Listed fire resistant silicone foam sealant installed in accordance with the manufacturer's recommendations may be utilized. All unused openings and sleeves shall be sealed as herein specified.

- L. A #16 gauge (1.3 mm2) steel pull wire shall be left in all empty conduits.

- M. PVC conduits shall be installed using fittings, solvents, glues, and methodology as recommended by the manufacturer.
- N. Provide adequate length of conductors within electrical enclosures and train the conductors to terminal points with no excess. Do not bend conductors sharper than eight times the cable outside diameter. Make terminations so there is no bare conductor at the terminal. Bundle multiple conductors, with conductors larger than No. 10 AWG in individual circuit bundles.

- O. Tighten electrical connectors and terminals, including screws and bolts, in accordance with the manufacturer's published torque tightening values. Where manufacturer's torquing requirements are not indicated, tighten connectors and terminals to comply with tightening torques specified in UL 486A and 486B.

- P. Utilize flexible liquid tight conduit for final connection in exterior, damp wet, or corrosive locations, and elsewhere as indicated on the drawings.

Sprint

6391 Sprint Parkway
Overland Park, KS 66251

Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

**NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET**

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski 1/08/2013
Signature Date

MARK	DATE	DESCRIPTION
C	1/08/13	FINAL CDs ISSUED
B	10/25/12	FINAL PRELIM CDs
A	10/03/12	90% CD REVIEW

PROJECT TITLE:
**RASMUSSEN WATER TANK
SITE #: CT03XC202**


PROJECT INFORMATION:
160 PLANTATION ROAD
EAST WINDSOR, CT 06016
HARTFORD COUNTY

SHEET TITLE:
SPECIFICATIONS

SCALE: NONE


PROJECT NUMBER	23001
SHEET NUMBER	SP-3

Copyright 2012 - Ramaker & Associates, Inc. - All Rights Reserved
 DRAWN BY: TDN CHECKED BY: KAB
 C:\Users\jnelson\local settings\temp\AcPublish_6652123001 Rasmussen Water Tank Vision Project CDs.dwg Printed by: Tnelson on Jan 08, 2013 - 9:45am



GENERAL NOTES:

1. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES ORDINANCES, LAWS, AND REGULATIONS OF ALL MUNICIPALITIES, UTILITIES COMPANY, OR OTHER PUBLIC AUTHORITIES.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY, OR MUNICIPAL AUTHORITIES.
3. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER, IN WRITING, OF ANY CONFLICTS, ERRORS OR OMISSIONS PRIOR TO THE SUBMISSION OF BIDS OR PERFORMANCE OF WORK. MINOR OMISSIONS OR ERRORS IN THE BID DOCUMENTS SHALL NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR THE OVERALL INTENT OF THESE DRAWINGS.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING SITE IMPROVEMENTS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED AS A RESULT OF CONSTRUCTION OF THE FACILITY.
5. THE SCOPE OF WORK FOR THIS PROJECT SHALL INCLUDE PROVIDING ALL MATERIALS, EQUIPMENT, AND LABOR REQUIRED TO COMPLETE THIS PROJECT. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
6. THE CONTRACTOR SHALL VISIT THE PROJECT SITE PRIOR TO SUBMITTING A BID TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
7. CONTRACTOR SHALL VERIFY ANTENNA ELEVATION AND AZIMUTH WITH RF ENGINEERING PRIOR TO INSTALLATION.
8. TRANSMITTER EQUIPMENT AND ANTENNAS ARE DESIGNED TO MEET ANSI/EIA/TIA 222-G REQUIREMENTS.
9. ALL STRUCTURAL ELEMENTS SHALL BE HOT DIPPED GALVANIZED STEEL.
10. CONTRACTOR SHALL MAKE A UTILITY "ONE-CALL" TO LOCATE ALL UTILITIES PRIOR TO EXCAVATING.
11. IF ANY UNDERGROUND UTILITIES OR STRUCTURES EXIST BENEATH THE PROJECT AREA, CONTRACTOR MUST LOCATE IT AND CONTACT THE APPLICANT & THE OWNER'S REPRESENTATIVE.
12. OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION BY TECHNICIANS APPROXIMATELY 2 TIMES PER MONTH.
13. RAMAKER & ASSOCIATES HAS NOT PERFORMED A STRUCTURAL ANALYSIS FOR THIS PROJECT. PRIOR TO THE INSTALLATION OF THE PROPOSED EQUIPMENT OR MODIFICATION OF THE EXISTING STRUCTURE, A STRUCTURAL ANALYSIS SHALL BE PERFORMED BY SPRINT'S AGENT TO CERTIFY THAT THE EXISTING/PROPOSED COMMUNICATION STRUCTURE AND COMPONENTS ARE STRUCTURALLY ADEQUATE TO SUPPORT ALL EXISTING AND PROPOSED ANTENNAS, COAXIAL CABLES, AND OTHER APPURTENANCES.
14. PROPERTY LINE INFORMATION WAS PREPARED USING DEEDS, TAX MAPS, AND PLANS OF RECORD AND SHOULD NOT BE CONSTRUED AS AN ACCURATE BOUNDARY SURVEY.
15. THIS PLAN IS SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD.
16. THE PROPOSED FACILITY WILL CAUSE ONLY A "DE MINIMIS" INCREASE IN STORMWATER RUNOFF; THEREFORE, NO DRAINAGE STRUCTURES ARE PROPOSED.
17. NO SIGNIFICANT NOISE, SMOKE, DUST, OR ODOR WILL RESULT FROM THIS FACILITY.
18. THE FACILITY IS UNMANNED AND NOT INTENDED FOR HUMAN HABITATION (NO HANDICAP ACCESS REQUIRED).
19. POWER TO THE FACILITY WILL BE MONITORED BY A SEPARATE METER.



NOTE:
 PROPOSED PCTEL GPS ANTENNA MODEL #:
 GPS-TMG-HR-2G HCM TO REPLACE EXISTING GPS ANTENNA. SEE DETAIL 3/S-1

SITE PLAN
 SCALE: 1" = 10'-0"



Sprint
 6391 Sprint Parkway
 Overland Park, KS 66251


Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

**NETWORK VISION
 MMBTS LAUNCH
 NORTHERN CT MARKET**

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.




James R. Skowronski 1/08/2013
 Signature Date

MARK	DATE	DESCRIPTION
C	1/08/13	FINAL CDs ISSUED
B	10/25/12	FINAL PRELIM CDs
A	10/03/12	90% CD REVIEW

ISSUE PHASE: FINAL DATE ISSUED: 01/08/13
 PROJECT TITLE:
**RASMUSSEN WATER TANK
 SITE #: CT03XC202**



PROJECT INFORMATION:
 160 PLANTATION ROAD
 EAST WINDSOR, CT 06016
 HARTFORD COUNTY

OVERALL SITE PLAN



PROJECT NUMBER: 23001
 SHEET NUMBER: C-1

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.



Sprint
 6391 Sprint Parkway
 Overland Park, KS 66251

Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.
 1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

**NETWORK VISION
 MMBTS LAUNCH
 NORTHERN CT MARKET**

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 1/08/2013


MARK	DATE	DESCRIPTION
C	1/08/13	FINAL CDS ISSUED
E	1/02/12	FINAL PRELIM CDS
A	1/03/12	90% CD REVIEW

ISSUE PHASE: FINAL DATE ISSUED: 01/08/13

**RASMUSSEN WATER TANK
 SITE #: CT03XC202**

PROJECT INFORMATION:
 160 PLANTATION ROAD
 EAST WINDSOR, CT 06016
 HARTFORD COUNTY


SHEET TITLE:
EQUIPMENT PLAN



PROJECT NUMBER: 23001
 SHEET NUMBER: A-1

NOTES:

- I. SCOPE**
 A. THIS SECTION COVERS THE SPECIFICATIONS FOR ANTENNA AND COAXIAL CABLE INSTALLATION OF: ANTENNAS, COAXIAL CONNECTIONS, AND ICE BRIDGE.
 B. REFERENCE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES FOR GENERAL REQUIREMENTS.
- II. ANTENNAS:**
 A. ANTENNAS SHALL BE PLUMB AND INSTALLED SO THAT THE ENTIRE WHIP EXTENDS ABOVE VERTICAL PIPE MOUNT. DIRECTIONAL ANTENNAS SHALL BE ORIENTED TO PROPER AZIMUTH, PROVIDED ON THE RF SPECIFICATION SHEET. NOTE: THE ANTENNA MAY BE ORIENTED USING THE REFLECTOR AS THE REFERENCE, ADJUSTING ITS AZIMUTH 180 DEGREES FROM MAXIMUM ANTENNA RADIATION.
 B. MICROWAVE ANTENNAS (DISHS) SHALL BE ASSEMBLED PER MANUFACTURER'S DRAWINGS. STIFF ARMS AND RADOMES SHALL BE INSTALLED WITH POLARIZATION PROVIDED BY RF SPECIFICATION SHEET. IF PATH IS NOT READY TO ALIGN, DISH SHOULD BE POINTED TOWARD CALCULATED AZIMUTH, OR DIRECTION OF FIELD STAKE DENOTING OPPOSITE END. 2 STIFF ARMS SHALL BE PROVIDED FOR MICROWAVE DISHS 6'-0" IN DIAMETER OR GREATER.
 C. A TRANSIT SHALL BE USED TO PROPERLY ALIGN CELLULAR AND MICROWAVE ANTENNAS.
- III. COAXIAL CABLE:**
 A. COAXIAL CABLE SHALL BE SUPPORTED WITH SNAP-IN HANGERS. SNAP-IN HANGERS SHOULD BE USED EVERY 3 FEET THE ENTIRE HEIGHT OF THE TOWER. ANGLE ADAPTERS OR ROUND MEMBER ADAPTERS WITH BUTTERFLY CLAMPS SHALL BE USED ELSEWHERE, I.E. SIDEARMS, PLATFORMS, AND MICROWAVE MOUNTS.
 B. COAXIAL CABLE SHALL ALSO BE SUPPORTED WITH HOISTING GRIPS, INSTALLED AT MAXIMUM INTERVALS OF 200 FEET. HOISTING GRIPS SHALL BE ATTACHED WITH SHACKLES, BOLTED IN THE 7/8" HOLE OF WAVEGUIDE LADDER.
 C. ALL JUMPERS USED BETWEEN COAXIAL CABLE AND ANTENNA SHALL BE SUPPORTED WITHIN 18 INCHES OF ANTENNA, USING BUTTERFLY CLAMPS WITH ANGLE ADAPTERS OR ROUND MEMBER ADAPTERS AROUND PIPES. CELLULAR ANTENNAS TYPICALLY USE 6' JUMPERS; MICROWAVE DISHS USE 3' JUMPERS.
 D. COAXIAL CABLE SHALL BE NEATLY BENT WHEN REQUIRED, USING A MINIMUM BENDING RADIUS OF 10 TIMES THE DIAMETER OF THE COAXIAL CABLE. DRIP LOOPS SHOULD BEGIN AT THE ICE BRIDGE. THE END IN THE COAXIAL CABLE SHOULD BE AT A LOWER HEIGHT THAN THE ENTRY PORT.
 E. COAXIAL CABLE SHALL BE SUPPORTED WITH SNAP-IN HANGERS ON THE WAVEGUIDE LADDER UNDER ICE BRIDGE. COAXIAL CABLE SHOULD BE NEATLY CUT 1/4" INSIDE BUILDING AND TERMINATED AT THE QUARTER WAVE SHORTS.
 F. CONNECTORS WILL NORMALLY BE PROVIDED FIRST OFF REEL FROM FACTORY. CONNECTORS TERMINATED IN BUILDING SHALL BE NEATLY INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
 G. COAXIAL CABLES SHOULD BE LABELED WITH TAGS INSIDE THE BUILDING.
 H. USE 2" WIDE COLORED TAPE TO INDICATE SECTORS. CONTRACTOR TO USE SECTOR COLOR CODING AS INDICATED IN THESE DRAWINGS OR AS PROVIDED BY SPRINT.
- IV. CONNECTORS:**
 A. ALL CONNECTIONS AND GROUNDING KITS SHALL BE WEATHERPROOFED USING COLD SHRINK OR ANDREW APPROVED WEATHER STRIPPING. NOTE: NO PORTION OF CONNECTOR SHALL BE EXPOSED TO THE ELEMENTS.
 B. COAXIAL CABLE SHALL BE GROUNDED USING GROUNDING KITS AT THE TOP (BELOW THE BEND), BOTTOM (ABOVE THE BEND ON TOWER GROUND BAR), AND ON BUILDING GROUND BAR BEFORE ENTRY INTO WAVEGUIDE PORTS. 4" CABLE BOOTS SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.
 C. GROUNDING KITS SHALL BE NEATLY INSTALLED SO THAT THE JUMPER RUNS IN THE SAME DIRECTION AS THE COAXIAL AND GROUND BAR. JUMPER WIRE SHOULD RUN IN A DIRECT PATH TO THE GROUND BAR/TOWER LADDER, BUT HAVE ADEQUATE SLACK FOR EXPANSION, CONTRACTION, AND REPAIR. NON-OXIDE GREASE SHOULD BE APPLIED BETWEEN LUG AND BARTOWER.
 D. TOWER GROUND BAR SHALL BE INSTALLED ON THE ANGLE BEHIND THE FIRST DIAGONAL WAVEGUIDE LADDER RUNG, ABOVE 8'-6". GROUND BAR SHALL BE ISOLATED FROM ANGLE USING NEWTON BUSHINGS PROVIDED.



TOP OF EXISTING WATER TANK @ ± 135'-0" AGL

Sprint

6391 Sprint Parkway
 Overland Park, KS 66251


Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

**NETWORK VISION
 MMBTS LAUNCH
 NORTHERN CT MARKET**

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



James R. Skowronski
 Signature: _____ Date: 1/08/2013


MARK	DATE	DESCRIPTION
C	1/08/13	FINAL CD'S ISSUED
B	10/25/12	FINAL PRELIM CD'S
A	10/03/12	90% CD REVIEW

ISSUE PHASE: FINAL DATE ISSUED: 01/08/13




**RASMUSSEN WATER TANK
 SITE #: CT03XC202**

PROJECT INFORMATION:
 160 PLANTATION ROAD
 EAST WINDSOR, CT 06016
 HARTFORD COUNTY

SITE ELEVATION & NOTES



PROJECT NUMBER: 23001
 SHEET NUMBER: A-2



Sprint
 6391 Sprint Parkway
 Overland Park, KS 66251

Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.
 1120 Dallas Street, Sauk City, WI 53583
 Phone: 608-643-4100 Fax: 608-643-7999
 www.Ramaker.com

**NETWORK VISION
 MMBTS LAUNCH
 NORTHERN CT MARKET**

Professional Engineer Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

JAMES R. SKOWRONSKI
 No. 26266
 LICENSED PROFESSIONAL ENGINEER

Signature: *James R. Skowronski* Date: 1/08/2013

ANTENNA AND COAXIAL CABLE SCHEDULE

SECTOR	POS.	AZIMUTH	ANTENNA CENTERLINE	ANTENNA STATUS	TECH.	ANTENNA MAKE/ MODEL	MECH. DOWNTILT (°)	ELEC. DOWNTILT (°)	RRHs	CABLE SIZE	CABLE LENGTH
ALPHA	A-1	0°	126'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
	A-2	0°	126'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
	A-3	50°	126'-0"	PROPOSED	MULTIMODAL	RFS #APXV9ERR18-C-A20	(0) 1900, (0) 800	(-1) 1900, (-8) 800	(1) 1900, (1) 800	(1) 1/4" HYBRIFLEX HYBRID CABLE RFS #HB114-1-08U4-M5J	± 200'-0"
BETA	B-1	120°	126'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
	B-2	120°	126'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
	B-3	150°	126'-0"	PROPOSED	MULTIMODAL	RFS #APXV5PP18-C-A20	(0) 1900, (0) 800	(0) 1900, (-6) 800	(1) 1900, (1) 800	(1) 1/4" HYBRIFLEX HYBRID CABLE RFS #HB114-1-08U4-M5J	± 190'-0"
GAMMA	G-1	240°	126'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
	G-2	250°	126'-0"	PROPOSED	MULTIMODAL	RFS #APXV5PP18-C-A20	(0) 1900, (0) 800	(-3) 1900, (-8) 800	(1) 1900, (1) 800	(1) 1/4" HYBRIFLEX HYBRID CABLE RFS #HB114-1-08U4-M5J	± 200'-0"
	G-3	240°	126'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-

**RASMUSSEN WATER TANK
 SITE #: CT03XC202**

PROJECT INFORMATION:
 160 PLANTATION ROAD
 EAST WINDSOR, CT 06016
 HARTFORD COUNTY

SHEET TITLE:
**ANTENNA DETAILS
 & COAX SCHEDULE**

SCALE: NONE

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.

EM-SPRINT-047-130109

160 Plantation Road

East Windsor



RECEIVED
JUL 10 2014

1 Robbins Road
Westford, MA 01886

July 9, 2014

CONNECTICUT
SITING COUNCIL

State of Connecticut
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Notification of Construction Completion on telecommunication facilities

To whom it may concern:

Alcatel Lucent hereby acknowledges that the list of attached sites have completed construction per the approval granted on the specified date. Please advise if further information is needed..

Very truly yours,

Martha Powers

Martha Powers
Lead Development Manager
Alcatel-Lucent
Sprint Vision Project
1 Robbins Road
Westford, MA 01886

Cc: FST, Siterra

EM/TS #	Address	Town	Sprint ID	Decision Date
EM-SPRINT-062-130912	1065 Wintergreen Avenue	Hamden	CT03XC003	10/15/2013
EM-SPRINT-NEXTEL-060-130118	10 Tanner Marsh Road	Guilford	CT03XC022	2/14/2013
EM-SPRINT-004-130822	181 Montevideo Road	Avon	CT03XC053	9/6/2013
EM-SPRINT-NEXTEL-155-130214	1358 New Britain Ave.	West Hartford	CT03XC057	3/1/2013
EM-SPRINT-NEXTEL-164-130201	440 Hayden Station Road	Windsor	CT03XC065	3/8/2013
EM-SPRINT-NEXTEL-132-130201	59 McGuire Road	South Windsor	CT03XC066	3/1/2013
EM-SPRINT-NEXTEL-054-130201	299 Paxton Way	Glastonbury	CT03XC081	3/1/2013
EM-SPRINT-NEXTEL-094-130214	36 Prospect Street	Newington	CT03XC084	3/1/2013
EM-SPRINT-110-130725	10 Sparks Street	Plainville	CT03XC086	8/8/2013
EM-SPRINT-007-130314	260 Beckley Road	Kensington	CT03XC088	4/5/2013
EM-SPRINT-NEXTEL-155-130201	570 New Park Avenue	West Hartford	CT03XC091	3/1/2013
EM-SPRINT-NEXTEL-106-130201	430 Middlesex Turnpike	Old Saybrook	CT03XC102	3/1/2013
EM-SPRINT-NEXTEL-105-130201	30 Short Hills Road	Old Lyme	CT03XC104	3/1/2013
EM-SPRINT-NEXTEL-152-130201	41 Manitock Hill Road	Waterford	CT03XC105	3/1/2013
EM-SPRINT-NEXTEL-045-130201	93 Roxbury Road	East Lyme	CT03XC110	3/1/2013
EM-SPRINT-152-130114	45R Fargo Road	Waterford	CT03XC112	2/14/2013
EM-SPRINT-NEXTEL-027-130201	48 Cow Hill Road	Clinton	CT03XC156	3/1/2013
EM-SPRINT-NEXTEL-082-130201	238 Meridan Road	Middlefield	CT03XC160	3/8/2013
EM-SPRINT-047-130109	160 Plantation Road	East Windsor	CT03XC202	2/7/2013
EM-SPRINT-NEXTEL-077-130214	53 Slater Street	Manchester	CT03XC211	3/1/2013
EM-SPRINT-142-130109	497 Old Post Road	Tolland	CT03XC212	2/7/2013
EM-SPRINT-NEXTEL-042-130222	94 East High Street	East Hampton	CT03XC335	3/8/2013
EM-SPRINT-057-121226	Butternut Hollow Road	Greenwich	CT03XC343	1/11/2013
EM-SPRINT-158-130213	515 Boston Post Road	Westport	CT03XC355	3/1/2013
EM-SPRINT-046-130402	206 Everett Road	Easton	CT03XC362	4/19/2013
EM-SPRINT-085-130322	474 MAIN STREET	MONROE	CT03XC365	4/5/2013
EM-SPRINT-086-131011	57 Cook Drive	Montville	CT03XC365	10/25/2013
EM-SPRINT-118-130322	76 EAST RIDGE	RIDGEFIELD	CT03XC370	4/5/2013
EM-SPRINT-097-131230	20 Barnabas Road	Newtown	CT03XC383	1/21/2014
EM-SPRINT-051-130207	3965 Congress Street	Fairfield	CT03XC385	3/1/2013
EM-SPRINT-NEXTEL-094-130214	123 Costello Road	Newington	CT23XC555	3/1/2013
EM-SPRINT-119-131008	699 Old Main Street	Rocky Hill	CT23XC556	10/25/2013
EM-SPRINT-077-131008	60 Adams Street	Manchester	CT23XC557	10/25/2013
EM-SPRINT-NEXTEL-080-130123	462 West Main Street	Meriden	CT25XC840	2/14/2013
EM-SPRINT-096-130920	18 Hilltop View Lane	New Milford	CT33XC095	10/4/2013
EM-SPRINT-157-130213	237 Godfrey Road	Weston	CT33XC522	3/1/2013
EM-SPRINT-018-131008	20 Vale Road	Brookfield	CT33XC525	10/25/2013
EM-SPRINT-077-130528	595 Keeney Street	Manchester	CT33XC538	6/14/2013
EM-SPRINT-NEXTEL-129-130214	400 Main Street	Somers	CT33XC554	3/1/2013
EM-SPRINT-047-130322	15 CHAMBERLAIN	BROADBROOK	CT33XC565	4/5/2013
EM-SPRINT-004-130502	277 Huckleberry Road	Avon	CT33XC589	5/17/2013

EM-SPRINT-143-130604	218 Wheeler Road	Torrington	CT33XC592	6/28/2013
EM-SPRINT-140-130724	583 Chapel Street	Thomaston	CT33XC603	8/8/2013
EM-SPRINT-103-130920	Charles Marshall Drive	Norwalk	CT33XC802	10/4/2013
EM-SPRINT-NEXTEL-064-130214	439-455 Homestead Ave.	Hartford	CT43XC805	3/1/2013
EM-SPRINT-064-130311	99 Meadow Street	Hartford	CT43XC806	4/5/2013
EM-SPRINT-083-131127	290 Preston Ave.	Middletown	CT43XC816	12/16/2013
EM-SPRINT-128-130920	530 Bushy Hill Road	Simsbury	CT43XC825	10/4/2013
EM-SPRINT-164-130405A	340 Bloomfield Avenue	Windsor	CT43XC826	4/19/2013
EM-SPRINT-077-130109	239 Middle Turnpike	Manchester	CT43XC827	2/13/2013
EM-SPRINT-165-130118	2-4 Volunteer Drive	Windsor Locks	CT43XC828	2/14/2013
EM-SPRINT-NEXTEL-139-130214	44 Fyler Place	Suffield	CT43XC829	3/8/2013
EM-SPRINT-111-130712	171 Town Hill Road	Plymouth	CT54XC712	7/26/2013
EM-SPRINT-009-130322	38 Spring Hill Road	Bethel	CT54XC749	4/5/2013
EM-SPRINT-154-131011	315 Spencer Plains Road	Westbrook	CT54XC758	10/25/2013
EM-SPRINT-023-130405	14 Canton Springs Road	Canton	CT54XC760	4/19/2013
EM-SPRINT-104-130606	153 Old Salem Road	Norwich	CT54XC775	6/28/2013
EM-SPRINT-164-130405B	99 Day Hill Road	Windsor	CT54XC787	4/19/2013
EM-SPRINT-132-130920	300 Governor's Highway	South Windsor	CT60XC014	10/4/2013
EM-SPRINT-094-130108	605 Willard Avenue	Newington	CT60XC018	1/25/2013
EM-SPRINT-146-130506	197 South Street	Vernon	CT60XC935	5/24/2013
EM-SPRINT-146-130311	777 Talcottville Road	Vernon	CT70XC147	4/5/2013
EM-SPRINT-126-130531	62 Birdseye Road	Shelton	CT73XC004	6/21/2013