

March 16th, 2018

Melanie Bachman, Executive Director Connecticut Siting Council 10 FranklinSquare New Britain, CT 06051

> RE: Notice of Exempt Modification – Antenna Swap for wireless facility located at 160 Plantation Road, East Windsor, CONNECTICUT - CT03XC202 (lat. 41° 52' 32.29" N, long. -72° 33' 53.27" W)

Dear Ms. Bachman:

Sprint Spectrum, LP ("Sprint") currently maintains wireless telecommunications antennas at the (126-foot level) on an existing (135-foot water tower) at the above-referenced address. The water tower is owned by Dean & Caren Rasmussen, and managed by American Tower Corporation.

Sprint's proposed work involves antenna replacement and tower work. Sprint intends to replace three (3) antennas and add three (3) RRHs on the tower. All the proposed work is contained within the existing fenced area. Please refer to the attached drawings for site plans prepared by Infinigy Engineering.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to ROBERT MAYNARD, FIRST SELECTMAN, and LAURIE WHITTEN, TOWN PLANNER of the Town of EAST WINDSOR. A copy of this letter is also being sent to DEAN & CAREN RASMUSSEN the owner of the property on which the tower is located, and JUSTINE PAUL the manager for AMERICAN TOWER CORPORATION who manages the site.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b).

- 1. The proposed modifications will not result in an increase in the height of the existing tower.
- 2. The antennas work is a one-for-one replacement of facility components.
- 3. The proposed modifications will include the addition of ground base equipment as

32 Clinton Street, Saratoga Springs, NY 12866 Office 518-306-1733 – Fax 518-306-1711 www.airosmithdevelopment.com





depicted on the attached drawings; however, the proposed equipment will not require an extension of the site boundaries.

- 4. The proposed modifications will not increase noise levels at the facility by six decibels or more.
- 5. The additional ground based equipment will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b).

If you have any questions or require any additional information regarding this request, please do not hesitate to give me a call at (518) 350-4222 or email me to <u>aperkowski@airosmithdevelopment.com</u>

Kind Regards,

Arthur Perkowski Airosmith Development Inc. 32 Clinton Street Saratoga Springs, NY 12866 518-306-1711 desk & fax 518-871-3707 cell aperkowski@airosmithdevelopment.com

Attachment

CC: DEAN & CAREN RASMUSSEN (Land/TOWER Owner) ROBERT MAYNARD (1st Selectman, EAST WINDSOR, CT) JUSTINE PAUL (Manager/American Tower Corporation) LAURIE WHITTEN (Town Planner / EAST WINDSOR CT)











Parcel ID 016 50 001C

Account

Property Information

| Owner | PLANTATION PROPERTIES LLC | | | |
|-----------------|---|--|--|--|
| Address | 50 PLANTATION RD | | | |
| Mailing Address | P O BOX 542 BROAD BROOK , CT 060160542 | | | |
| Land Use | - Commercial Vacant Land | | | |
| Land Class | Commercial | | | |
| Previous MBL | 40-50 001C | | | |

| Census Tract | 4842000 |
|-------------------|---------|
| Neighborhood | F |
| Zoning | A-1 |
| Acreage | 0.78 |
| Utilities | |
| Lot Setting/ Desc | I |

PARCEL VALUATIONS (Assessed value = 70% of Appraised Value)



| Appraised | Assessed |
|-----------|-----------|
| | |
| | |
| | |
| | |
| | |
| 267424 | 0 |
| | |
| | Appraised |

Construction Details

| Storles | 0 |
|---------------------------|---|
| Building Style | |
| Building Use | |
| Building Condition | |
| Total Rooms | |
| Bedrooms | 0 |
| Full Bathrooms | 0 |
| Half Bathrooms | |
| Bath Style | |
| Kitchen Style | |
| Roof Style | |
| Roof Cover | |
| | |

EXTERIOR WALLS:

| Primary | 0 | | | |
|-----------------|---|--|--|--|
| Secondary | | | | |
| INTERIOR WALLS: | | | | |
| Primary | | | | |
| Secondary | | | | |
| FLOORS: | | | | |
| Primary | | | | |
| Secondary | | | | |
| HEATING/AC: | | | | |
| Heating Type | | | | |
| Heating Fuel | | | | |
| АС Туре | | | | |

BUILDING AREA:

| Effective Building Area | | |
|-------------------------|---|--|
| Gross Building Area | | |
| Total Living Area | 0 | |

SALES HISTORY:

| Sale Date | 09/27/2001 | | |
|------------|------------|--|--|
| Sale Price | 1 | | |
| Book/ Page | 0231/0053 | | |





RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT03XC202

Rasmussen Water Tank 160 Plantation Road East Windsor, CT 06016

August 31, 2017

EBI Project Number: 6217003875

| Site Compliance Summary | | | |
|-------------------------|-----------|--|--|
| Compliance Status: | COMPLIANT | | |
| Site total MPE% of | | | |
| FCC general | 8 19 % | | |
| population | 0.45 /0 | | |
| allowable limit: | | | |



August 31, 2017

SPRINT Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Emissions Analysis for Site: CT03XC202 – Rasmussen Water Tank

EBI Consulting was directed to analyze the proposed SPRINT facility located at **160 Plantation Road**, **East Windsor, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm2). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

<u>General population/uncontrolled exposure</u> limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limits for the 850 MHz Band is approximately 567 μ W/cm². The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



<u>Occupational/controlled exposure</u> limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over their exposure and can exercise control over the potential for exposure and can exercise control over the potentia

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **160 Plantation Road, East Windsor, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20 for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **126 feet** above ground level (AGL) for **Sector A**, **126 feet** above ground level (AGL) for **Sector B** and **126 feet** above ground level (AGL) for **Sector C**.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

| Sector: | А | Sector: | В | Sector: | С |
|-----------------------|-----------------------------|-----------------------|-----------------------------|-----------------------|-----------------------------|
| Antenna #: | 1 | Antenna #: | 1 | Antenna #: | 1 |
| Make / Model: | RFS APXVSPP18-C-A20 | Make / Model: | RFS APXVSPP18-C-A20 | Make / Model: | RFS APXVSPP18-C-A20 |
| Gain: | 13.4 / 15.9 dBd | Gain: | 13.4 / 15.9 dBd | Gain: | 13.4 / 15.9 dBd |
| Height (AGL): | 126 feet | Height (AGL): | 126 feet | Height (AGL): | 126 feet |
| Frequency Bands | 850 MHz / 1900 MHz (PCS) | Frequency Bands | 850 MHz / 1900 MHz (PCS) | Frequency Bands | 850 MHz / 1900 MHz (PCS) |
| Channel Count | 10 | Channel Count | 10 | Channel Count | 10 |
| Total TX Power(W): | 220 Watts | Total TX Power(W): | 220 Watts | Total TX Power(W): | 220 Watts |
| ERP (W): | 7,537.38 | ERP (W): | 7,537.38 | ERP (W): | 7,537.38 |
| Antenna A1 MPE% | 2.13 % | Antenna B1 MPE% | 2.13 % | Antenna C1 MPE% | 2.13 % |
| Antenna #: | 2 | Antenna #: | 2 | Antenna #: | 2 |
| Make / Model: | RFS APXVTM14-C-I20 | Make / Model: | RFS APXVTM14-C-I20 | Make / Model: | RFS APXVTM14-C-I20 |
| Gain: | 15.9 dBd | Gain: | 15.9 dBd | Gain: | 15.9 dBd |
| Height (AGL): | 126 feet | Height (AGL): | 126 feet | Height (AGL): | 126 feet |
| Frequency Bands | 2500 MHz (BRS) | Frequency Bands | 2500 MHz (BRS) | Frequency Bands | 2500 MHz (BRS) |
| Channel Count | 8 | Channel Count | 8 | Channel Count | 8 |
| Total TX Power(W): | 160 Watts | Total TX Power(W): | 160 Watts | Total TX Power(W): | 160 Watts |
| ERP (W): | 6,224.72 | ERP (W): | 6,224.72 | ERP (W): | 6,224.72 |
| Antenna A2 MPE% | 1.55 % | Antenna B2 MPE% | 1.55 % | Antenna C2 MPE% | 1.55 % |

| Site Composite MPE% | | | | |
|-------------------------|--------|--|--|--|
| Carrier | MPE% | | | |
| SPRINT – Max per sector | 3.69 % | | | |
| AT&T | 4.64 % | | | |
| Clearwire | 0.13 % | | | |
| T-Mobile | 0.03 % | | | |
| Site Total MPE %: | 8.49 % | | | |

| SPRINT Sector A Total: | 3.69 % |
|------------------------|--------|
| SPRINT Sector B Total: | 3.69 % |
| SPRINT Sector C Total: | 3.69 % |
| Site Total: | 8.49 % |

| SPRINT _ Max Values per Frequency Band / Technology Per Sector | # Channels | Watts ERP (Per Channel) | Height (feet) | Total Power Density (µW/cm ²) | Frequency (MHz) | Allowable MPE (µW/cm ²) | Calculated % MPE |
|--|---------------|----------------------------|------------------|---|--------------------|---|---------------------|
| Sprint 850 MHz CDMA | 1 | 437.55 | 126 | 1.09 | 850 MHz | 567 | 0.19% |
| Sprint 850 MHz LTE | 2 | 437.55 | 126 | 2.18 | 850 MHz | 567 | 0.39% |
| Sprint 1900 MHz (PCS) CDMA | 5 | 622.47 | 126 | 7.77 | 1900 MHz (PCS) | 1000 | 0.78% |
| Sprint 1900 MHz (PCS) LTE | 2 | 1,556.18 | 126 | 7.77 | 1900 MHz (PCS) | 1000 | 0.78% |
| Sprint 2500 MHz (BRS) LTE | 8 | 778.09 | 126 | 15.54 | 2500 MHz (BRS) | 1000 | 1.55% |
| | | | | | | Total*: | 3.69% |

*NOTE: Totals may vary by 0.01% due to summing of remainders



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

| SPRINT Sector | Power Density Value (%) |
|-------------------------|-------------------------|
| Sector A: | 3.69 % |
| Sector B: | 3.69 % |
| Sector C: | 3.69 % |
| SPRINT Maximum | 3.69 % |
| Total (per sector): | |
| | |
| Site Total: | 8.49 % |
| | |
| Site Compliance Status: | COMPLIANT |

The anticipated composite MPE value for this site assuming all carriers present is **8.49** % of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

FROM ZERO TO INFINIGY the solutions are endless

1033 WATERVLIET SHAKER RD, ALBANY, NY 12205

Structural Analysis Report

March 1, 2018

| Site Name | CT03XC2020 |
|----------------------|---|
| Infinigy Job Number | 526-104 |
| Client | Airosmith |
| Proposed Carrier | Sprint |
| Site Location | 160 Plantation Road East Windsor, CT 06016 41° 52' 32.29" N NAD83 72° 33' 53.27" W NAD83 |
| Structure Type | 135' Water Tank |
| Overturning Increase | 7.36% |
| Overall Result | Pass |

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA and AWWA code requirements. The water tank is therefore deemed adequate to support the existing and proposed loading as listed in this report.



Nathaniel R Ober, E.I.T. Northeast Structural Region Lead

INFINIGY8

NC NH

NM

MATN

MD

WA

TX

AZ CA

CO

GA

March 1, 2018

Contents

| Introduction | 3 |
|-----------------------------|----------|
| Supporting Documentation | 3 |
| Analysis Code Requirements | 3 |
| Conclusion | 3 |
| Final Configuration | 4 |
| Structure Usages | 4 |
| Assumptions and Limitations | 4 |
| Calculations | Appended |

March 1, 2018

Introduction

Infinigy Engineering has been requested to perform a structural analysis on the existing 135' water tank. All supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The tank was analyzed using proprietary structural analysis software.

Supporting Documentation

| Proposed Loading | Infinigy Job #526-104, dated November 9, 2017 |
|------------------|---|

| Wind Speed | 95 mph (3-Second Gust, V _{ASD}) / 123 mph (3-Second Gust, V _{ULT}) |
|-------------------------|--|
| Wind Speed w/ ice | 40 mph (3-Second Gust) w/ 3/4" ice |
| TIA Revision | ANSI/TIA222-G |
| Water Tank Code | ANSI/AWWA D103-09 |
| Adopted IBC | 2015 IBC |
| Structure Class | 3 |
| Exposure Category | С |
| Topographic Category | 1 |
| Calculated Crest Height | 0 ft |

Analysis Code Requirements

Conclusion

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA and AWWA code requirements. The water tank is therefore deemed adequate to support the existing and proposed loading as listed in this report.

If you have any questions, require additional information, or actual conditions differ from those as detailed in this report please contact me via the information below:

Nathaniel R Ober E.I.T. Northeast Structural Region Lead | Infinigy 1033 Watervliet Shaker Road, Albany, NY 12205 (O) (518) 690-0790 | (M) (303) 704-0322 nober@infinigy.com | www.infinigy.com

March 1, 2018

| Mount Height (ft) | Qty. | Appurtenance | Mount Type | Coax & Cables | Carrier |
|-------------------------|-------------|----------------------|---------------|------------------|---------|
| 130.0 | 1 | 4' Dish | | | |
| | 3 | RFS APXV9ERR18-C-A20 | | | |
| | 3 | RFS APXVTM14-C-I20 | | | |
| 126.0 | 3 | ALU 1900 MHz RRH | Pipe | (4) Hybrid | Sprint |
| | 3 | ALU 800 MHz RRH | | | |
| | 3 | ALU TD-RRH8x20-25 | | | |
| | 3 | 8' Panel Antennas | | | |
| 115.0 | 6 5' Panels | | Pipe | | |
| | 6 | Radio | | | |

Final Configuration

Structure Usages

Overturning Moment Increase:

7.36%

Assumptions and Limitations

Our structural calculations are completed assuming all information provided to Infinigy Engineering is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition of "like new" and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report Infinigy Engineering should be notified immediately to complete a revised evaluation.

Our evaluation is completed using standard TIA, AISC, ACI, and ASCE methods and procedures. Our structural results are proprietary and should not be used by others as their own. Infinigy Engineering is not responsible for decisions made by others that are or are not based on our supplied assumptions and conclusions.

This report is an evaluation of the tower structure only and does not reflect adequacy of any existing antenna mounts, mount connections, or coax mounting attachments. These elements are assumed to be adequate for the purposes of this analysis and are assumed to have been installed per their manufacturer requirements.

| Site Name: Client: Carrier: Engineer: | CT03XC202 Airosmith Sprint | | | | | INFINIGY8 |
|--|----------------------------------|-----------------------------|----------------------|------------|-----------------------|-------------------------------------|
| Date: | 3/1/2018 | | | | | the solutions are endless |
| bute. | 5/1/2010 | | | | | INFINIGY WIND LOAD CALCULATOR 3.0.2 |
| Si | te Information Input | s: | Ro | oftop Inpu | ts: | |
| Adopted Building Code: | 2012 IBC | Rooftop Wind S | peed-Up?: | No |] | |
| Structure Load Standard: | AWWA D100-11 | | | | | |
| Antenna Load Standard: | TIA-222-G | | | | | |
| Structure Risk Category: | III | | | | | |
| Structure Type: | Mount - Pipe | | | | | |
| Number of Sectors: | 3 | | | | | |
| Structure Shape 1: | Round | | | | | |
| | | | | | | |
| · | Wind Loading Inputs | : | Wi | nd with No | lce | |
| Design Wind Velocity: | 95 | mph (nominal 3-second gust) | q _z (psf) | Gh | F _{ST} (psf) | |
| Wind Centerline 1 (z ₁): | 126.0 | ft | 35.51 | 1.00 | 21.31 | |
| Side Face Angle (θ): | 60 | degrees | | | | |
| Exposure Category: | С | | | | | |
| Topographic Category: | 1 | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Ice Loading Inputs: Is Ice Loading Needed?: No

| Input Appurtenance Informat | ion and Load Placem | ients: |
|-----------------------------|---------------------|--------|
| | | |

| Appurtopanco Namo | Flouration (ft) | Total | Ka | Front | Side | qz | EPA | Fz | Fx | Fz(60) | Fx(30) |
|------------------------------|-----------------|----------|------|-------|-------|-------|--------------------|--------|--------|--------|--------|
| Appurtenance Name | Elevation (It) | Quantity | Νd | Shape | Shape | (psf) | (ft ²) | (lbs) | (lbs) | (lbs) | (lbs) |
| RFS APXVTM14-C-I20 | 126.0 | 3 | 1.00 | Flat | Flat | 33.73 | 6.34 | 213.95 | 121.69 | 144.75 | 190.88 |
| RFS APXV9ERR18-C-A20 | 126.0 | 3 | 1.00 | Flat | Flat | 33.73 | 8.02 | 270.69 | 195.93 | 214.62 | 252.00 |
| Alcatel Lucent TD-RRH8x20-25 | 126.0 | 3 | 1.00 | Flat | Flat | 33.73 | 3.70 | 124.95 | 43.65 | 63.97 | 104.63 |
| Alcatel-Lucent 800 MHz RRH | 126.0 | 3 | 1.00 | Flat | Flat | 33.73 | 2.13 | 71.99 | 59.81 | 62.85 | 68.95 |
| Alcatel-Lucent 1900 MHz RRH | 126.0 | 3 | 1.00 | Flat | Flat | 33.73 | 2.31 | 78.01 | 80.12 | 79.59 | 78.53 |
| 8' Panel | 115.0 | 3 | 1.00 | Flat | Flat | 33.09 | 9.91 | 327.96 | 225.02 | 250.75 | 302.23 |
| 5' Panel | 115.0 | 6 | 1.00 | Flat | Flat | 33.09 | 5.65 | 186.90 | 124.09 | 139.79 | 171.20 |
| Radio | 115.0 | 6 | 1.00 | Flat | Flat | 33.09 | 3.20 | 105.89 | 66.18 | 76.11 | 95.96 |
| 4' Dish | 130.0 | 1 | 1.00 | Flat | Round | 33.96 | 19.20 | 651.95 | 72.44 | 217.32 | 507.07 |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |

| Date: | 3/1/2018 | |
|-------------------------|-----------|-----|
| Site Name: | CT03XC202 | |
| Client: | Airosmith | |
| Carrier: | Sprint | |
| Infinigy Job #: | 526-104 | |
| Analysis/Design: | Analysis | |
| Wind Speed, 3 sec gust: | 95 | mph |

| Tank Overturning Moment - ANSI/AWWA D103-09 | | | | | | | | | |
|---|------------------------|-------------|------------------|-----------------|-----------|-------------|-------------|----------------------------|--|
| | Zone 1: 0 ft to 35 ft | | | | | | | | |
| Name | Qty | Length (ft) | Height (ft) I kz | (ft) qz (ft) | pw (psf) | Area (sqft) | Force (lbs) | Overturning Moment (ft*lb) | |
| Tower Leg | 4.00 | 35.35 | 17.50 1.15 0. | 38 23.30 | 30.00 | 35.00 | 1050.00 | 73500.00 | |
| Diagonals | 8.00 | 49.49 | 17.50 1.15 0. | 38 23.30 | 18.00 | 2.92 | 52.50 | 7350.00 | |
| Center Column | 1.00 | 35.00 | 17.50 1.15 0. | 38 23.30 | 18.00 | 87.50 | 1575.00 | 27562.50 | |
| Strut Zone 1-2 | 1.00 | 35.00 | 35.00 1.15 1. | 26.96 | 30.00 | 23.33 | 700.00 | 24500.00 | |
| | Zone 2: 35 ft to 70 ft | | | | | | | | |
| Name | Qty | Length (ft) | Height (ft) I kz | (ft) qz (ft) | pw (psf) | Area (sqft) | Force (lbs) | Overturning Moment (ft*lb) | |
| Tower Leg | 4.00 | 35.35 | 52.50 1.15 1. | 11 29.36 | 30.00 | 35.00 | 1050.00 | 220500.00 | |
| Diagonals | 8.00 | 43.01 | 52.50 1.15 1. | 11 29.36 | 18.00 | 2.92 | 52.50 | 22050.00 | |
| Center Column | 1.00 | 35.00 | 52.50 1.15 1. | 11 29.36 | 18.00 | 87.50 | 1575.00 | 82687.50 | |
| Top Horizontal | 1.00 | 25.00 | 70.00 1.15 1. | 17 31.19 | 18.72 | 16.67 | 311.94 | 21836.10 | |
| | | | | Zone 3: 70 ft t | o 105 ft | | | | |
| Name | Qty | Length (ft) | Height (ft) I kz | (ft) qz (ft) | pw (psf) | Area (sqft) | Force (lbs) | Overturning Moment (ft*lb) | |
| Tower Leg | 4.00 | 35.35 | 87.50 1.15 1. | 23 32.69 | 32.69 | 35.00 | 1144.32 | 400511.67 | |
| Diagonals | 8.00 | 38.08 | 87.50 1.15 1. | 23 32.69 | 19.62 | 2.92 | 57.22 | 40051.17 | |
| Center Column | 1.00 | 35.00 | 87.50 1.15 1. | 23 32.69 | 19.62 | 87.50 | 1716.48 | 150191.88 | |
| Handrail | 1.00 | 20.00 | 105.00 1.15 1. | 28 33.97 | 33.97 | 20.00 | 679.48 | 71345.75 | |
| | | | | Zone 4: 105 ft | to 135 ft | | | | |
| Name | Midpoint Height | Area (ft^2) | Height (ft) I kz | (ft) qz (ft) | pw (psf) | Area (sqft) | Force (lbs) | Overturning Moment (ft*lb) | |
| Tank Bell | 120.00 | 450.00 | 120.00 1.15 1. | 32 34.94 | 20.97 | 450.00 | 9434.55 | 1132146.58 | |

| Tank Overturning Moment | Tank + Antennas/Coax | |
|----------------------------|----------------------|----|
| (ft*lb) | | |
| 2274233.14 | 2441639.94 | |
| Overturning Moment Percent | | |
| Increase | 7.36 | ОК |

| | PROJECT: | 2.5 EQUIPMENT DEPLOY |
|---------------|---------------|---|
| | SITE NAME: | RASMUSSEN WATER TA |
| | SITE CASCADE: | CT03XC202 |
| SDrint | SITE ADDRESS: | 160 PLANTATION ROAD EAST WINDSOR, CT 060 |
| | SITE TYPE: | WATER TANK |
| | MARKET: | NORTHERN CONNECTIO |
| | | |

| SITE INFORMATION | AREA MAP | PROJECT DESCRIPTION | | DRAWING |
|--------------------------------------|--|---|-----------|-------------------------|
| PROPERTY OWNER: | Lenox Becker. Northampton | SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY. | SHEET NO. | SHEET |
| DEAN & CAREN RASMUSSEN | Stockbridge | INSTALL 2.5 EQUIPMENT INSIDE EXISTING N.V. MMBS CABINET | T-1 | TITLE SHEET & PROJECT D |
| PO BOX 542 | Dreat Holocke | | SP-1 | SPRINT SPECIFICATIONS |
| EAST WINDSOR, CT 06016 | Barrington Barrington | INSTALL (4) NEW BATTERIES INSIDE EXISTING BBU CABINET | | |
| LATITUDE (NAD83): | (i) Chicopee Charlton (ii) | INSTALL (3) PANEL ANTENNAS | SP-2 | SPRINT SPECIFICATIONS |
| 41° 52' 32.29" N | Springried Southridge | INSTALL (3) RRH'S TO TOWER | SP-3 | SPRINT SPECIFICATIONS |
| 41.87563611 | Weber | | A-1 | SITE PLAN |
| | Salisbury | INSTALL (27) JUMPER CABLES | A-2 | TOWER ELEVATION & CABLE |
| LONGITUDE (NAD85): | | INSTALL (2) HYBRID CABLE | A-3 | ANTENNA LAYOUT & MOUNT |
| -72 55 55.27 W -72.56479722 | Sharen | | A-4 | EQUIPMENT & MOUNTING D |
| | Conneal | | A-5 | CIVIL DETAILS |
| COUNTY: | Torrington Torrington Manufield Brooklyn | | A-6 | PLUMBING DIAGRAM |
| HARTFORD | Hartford | | A-7 | COLOR CODING & NOTES |
| | Printed Printed Windham Painfield | | F_1 | FLECTRICAL & GROUNDING |
| ZUNING JURISDICTION: | Washington | THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING | E-2 | ELECTRICAL & GROUNDING |
| TOWN OF EAST WINDSOR | | UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN | | |
| ZONING DISTRICT: | Middletown | INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT | | |
| ZONE A-1 | | FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL | | |
| (AGRICULTURAL/RESIDENTIAL) | | STRUCTURAL ANALYSIS MUST INCLUDE BOTH STRUCTURE AND MOUNT. | | |
| POWER COMPANY: | LOCATION MAP | APPLICABLE CODES | | |
| CONNECTICUT LIGHT AND POWER | | | | |
| PHONE: (800) 922-4455 | No And | ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING | | |
| AAV PROVIDER: | | CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. | | |
| | | NOT CONFORMING TO THESE CODES. | | |
| PHONE: (800) 331-0500 | | | | |
| PROJECT MANAGER: | inter 1 | 2. TIA-222-G OR LATEST EDITION | | |
| | | 3. NFPA 780 - LIGHTNING PROTECTION CODE | | |
| (315)719–2928 | | 5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, | | |
| TBURKHOLDER@AIROSMITHDEVELOPMENT.COM | Plantation Re D | MOST RECENT EDITIONS | | |
| | | | | |
| | SIL | 7. EGGNE BOIEDING GODE | | |
| | | 8. CITY/COUNTY ORDINANCES | | |
| | | 8. CITY/COUNTY ORDINANCES | | |
| | Since the Monte and State of the State of th | 8. CITY/COUNTY ORDINANCES | | |
| | Since the second | 8. CITY/COUNTY ORDINANCES | | |
| | Since the second | 8. CITY/COUNTY ORDINANCES | | |
| | | 8. CITY/COUNTY ORDINANCES | | |
| | Since the second | 8. CITY/COUNTY ORDINANCES | | |
| | Since the second | 8. CITY/COUNTY ORDINANCES | | |
| | And a second sec | 8. CITY/COUNTY ORDINANCES | | |

| | | | PLANS PREPARED FOR | | | |
|----------------|------|-----|--|---|-----------|---------------------------------------|
| YMENT NK | | | Sprint | | Ņ | |
| 16 | | | PLANS PREPARED BY: FROM ZERO TO the solution: 033 Watervliet Shaker Rd Phone: 518-690-0790 Faa www.infingy. JOB NUMER 526- | Albany, :: 518-69 :: 518-69 :: 104 | | S Y SS 2205 93 |
| CUT | | | PROJECT MANAGER: AIROSSN 32 CLINTON ST. SARATOCA SPRINGS, NY OFFICE#, (518) 306-37 | 12866 40 | EN | IT |
| G INDEX | | | ENGINEERING LICENSE: | | | |
| ET TITLE | REV. | | | | | |
| DATA | 0 | | | | | |
| | 0 | ł | | | | |
| | 0 | 11 | | | | |
| | 0 | | | | | |
| | | II. | | | | |
| | 0 | ۱L | | | | |
| INTING DETAILS | 0 | İ٢ | DRAWING NOTICE: | | | |
| DETAILS | 0 | | THESE DOCUMENTS ARE CONFI | DENTIAL A | | ARE |
| | 0 | ł | REPRODUCED, DISSEMINATED C | OR REDIST | RIBUT | FED |
| 1 | 0 | 11 | WITHOUT THE EXPRESS WRITT SPRINT. | 'EN CONS | ENT C | DF |
| | | 1L | | | | |
| G DETAILS | 0 | ł٢ | - REVISIONS: | DATE | ΒY | REV. |
| G DETAILS | 0 | łĒ | | | | |
| | | 11- | | | | |
| | | lt | | | | |
| | | ١F. | | 03/05/19 | ETC | |
| | | ۱Ë | JULE FOR FERMIT | 00/00/10 | LIU | Ū |
| | | | RASMUSSEN TANK | WAT | ΈR | ł |
| | | 1L | | | | |
| | | ł٢ | SILE NUMBER: | | | |
| | | | CT03XC2 | 202 | | |
| | | ١Ē | SITE ADDRESS: | | | |
| | | | 160 PLANTATIC EAST WINDSOR | N RO CT 0 | AD 601 |) 6 |
| | | ĪĒ | SHEET DESCRIPTION: | | | |
| | | | TITLE SHE & PROJECT I | EET DATA | | |
| | | ĪĒ | SHEET NUMBER | | | _ |
| | | | T-1 | | | |
| | · | | | | | |

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION ANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 7. AMERICAN CONCRETE INSTITUTE (ACI)
 - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 - 11. PORTLAND CEMENT ASSOCIATION (PCA)
 - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 13. BRICK INDUSTRY ASSOCIATION (BIA)
 - 14. AMERICAN WELDING SOCIETY (AWS)
 - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 17. DOOR AND HARDWARE INSTITUTE (DHI)
 - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.
- 1.5 DEFINITIONS:
- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT
- G. CONSTRUCTION MANAGER ALL PROJECTS RELATED COMMUNICATION TO FLOW HROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT ...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
- A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
- B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE
- C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES, PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS, DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
- EQUIPMENT AND UPON RECEIPT SHALL:
 - 1 ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
- 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 DELIVERABLES

- COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY
- IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY В. COMPANY
- UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 - CELL SITE CONSTRUCTION CO. PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY

CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.

- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 FUNCTIONAL REQUIREMENTS:
 - PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:



CONTINUE FROM SP-1

- 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION
- 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
- 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL
- 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
- 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
- 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
- 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
- 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
- 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS
- 19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
- 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."
- 3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:
 - CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
- 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
- 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS. PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
- 2. PROJECT PROGRESS REPORTS.
- 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

- 5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- 7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- 8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- 9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
- 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

- PART 1 GENERAL
- 1.1 The work: These standard construction specifications in conjunction with the other contract documents and the construction drawings describe the WORK TO BE PERFORMED BY THE CONTRACTOR
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 - 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 - 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 - 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS
 - 5. CHEMICAL GROUNDING DESIGN
 - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.
- 1.4 TESTS AND INSPECTIONS:
- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING
 - 1. COAX SWEEPS AND FIBER TESTS PER CURRENT VERSION OF SPRINT'S TS-0200 ANTENNA LINE ACCEPTANCE STANDARDS.
- 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING
- AZIMUTH, DOWNTILT, AGL UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
- 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

- CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
- 6. LIEN WAIVERS
- 7. FINAL PAYMENT APPLICATION
- 8. REQUIRED FINAL CONSTRUCTION PHOTOS
- 9 . CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT
- (SPRINTS DOCUMENT REPOSITORY OF RECORD).
- 1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE
- 1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 REQUIREMENTS FOR TESTING:
 - A. THIRD PARTY TESTING AGENCY:
 - WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
 - REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 - 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT ESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
 - 4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
- 3.2 REQUIRED TESTS:
 - A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT
 - 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 - 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 - 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN
 - 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 - 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 - 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

OR SPRINT REPRESENTATIVE.

OR SPRINT REPRESENTATIVE.

3.3 REQUIRED INSPECTIONS



CONTINUE FROM SP-2

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
- 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
- 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF
- 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING
- CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
- 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
- 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
- 3. SITE RESISTANCE TO EARTH TEST.
- 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
- 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HERFIN
- 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS"
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING
- 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH
- 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING
- 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
- 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET .: PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROPORING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
- 6. SITE LAYOUT PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
- 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL: CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
- 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN
- 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

- PART 1 GENERAL
- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 WEEKLY REPORTS
 - CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS
- 3.3 PROJECT TRACKING IN SMS:
- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING
- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
 - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL BE LEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A NIMUM THE FOLLOWING AS APPLICABLE:
 - 1. 1SHELTER AND TOWER OVERVIEW.
 - 2. TOWER FOUNDATION(S) FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS)
 - 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 - 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 - 5. PHOTOS OF TOWER SECTION STACKING.
 - 6. CONCRETE TESTING / SAMPLES.
 - 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 - 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 - 9. SHELTER FOUNDATION -- FORMS AND STEEL BEFORE POURING.
 - 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE
 - 11. COAX CABLE ENTRY INTO SHELTER.
 - 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 - 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND | FVFL
 - 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 - 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER
 - 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 - 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 - 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 - 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 - 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
 - 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- 24. FENCE GROUND-RING TRENCH WITH GROU ALL CAD WELDS AND BEND RADII).
- 25. ALL BTS GROUND CONNECTIONS
- 26. ALL GROUND TEST WELLS.
- 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.

- 30. GPS ANTENNAS
- 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
- 32. DOGHOUSE/CABLE EXIT FROM ROOF
- 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
- 34. MASTER BUS BAR.
- 35. TELCO BOARD AND NIU.
- 36. ELECTRICAL DISTRIBUTION WALL.
- 37. CABLE ENTRY WITH SURGE SUPPRESSION
- 38. ENTRANCE TO EQUIPMENT ROOM.
- 39. COAX WEATHERPROOFING-TOP AND BOTTOM OF TOWER.
- 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER
- 41. ANTENNA AND MAST GROUNDING
- 42. LANDSCAPING WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

| ND-WIRE | BEFORE | BACKFILL | (SHOW |
|---------|--------|----------|-------|
|---------|--------|----------|-------|

28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.

29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.



PLANS PREPARED FOR:







| | | | | SITE | LOA | ADING | CHART | |
|----------|-----------------------|--------------------|--------|---------|------|--------------------|--------------------------------------|---------------------------|
| SECTOR | EXISTING/ PROPOSED | ANTENNA MODEL # | VENDOR | AZIMUTH | QTY. | REMAIN/ REMOVED | RRH (QTY/MODEL) | CABLE |
| | PROPOSED | APXVTM14-C-120 | RFS | 30* | 1 | - | (1) TD-RRH8X20-25 W/ SOLAR SHIELD | SEE SHEET A-5 DETAIL 1 |
| ALPHA | FXISTING | APXV9FRR18-C-A20 | RES | 50° | 1 | REMAIN | (1) 800 MHz RRH | EXISTING |
| EXISTING | NI AVSENTIO O NEO | 1 | | | 1.2 | (1) 1900 MHz RRH | HYBRID CABLE | |
| | PROPOSED | APXVTM14-C-120 | RFS | 150° | 1 | - | (1) TD-RRH8X20-25 W/ SOLAR SHIELD | SEE SHEET A-5 DETAIL 1 |
| BETA | FXISTING | APXVSPP18-C-420 | RFS | 150* | 1 | REMAIN | (1) 800 MHz RRH | EXISTING |
| | EXISTING | AI XV3I I 10-0-A20 | 1110 | /00 | | | (1) 1900 MHz RRH | HYBRID CABLE |
| | FXISTING | APXVSPP18-C-A20 | RFS | 250° | 1 | REMAIN | (1) 800 MHz RRH | EXISTING |
| GAMMA | | 100 | 200 | | 1.2 | (1) 1900 MHz RRH | COAX | |
| | PROPOSED | APXVTM14-C-120 | RFS | 270* | 1 | - | (1) TD-RRH8X20-25 W/ | EXISTING HYBRID_CABLE |

TRODEOT COOTE.

INSTALL: (3) PANEL ANTENNAS AND (3) RRH'S

* PROPOSED CABLE LENGTH WAS DETERMINED USING THE SUM OF THE RAD CENTER OF ANTENNAS, AND DISTANCE FROM EXISTING EQUIPMENT AREA TO TOWER BASE WITH AN ADDITIONAL 20' BUFFER. LENGTH TO BE VERIFIED IN FIELD PRIOR TO ORDERING MATERIALS.

SITE LOADING CHART

| | | | | PLANS PREPARED FOR: | | | |
|--------|---------|-------|---|--|--|------------------------------------|---------------------------|
| | | | | Sprir | nt) | V | |
| | | | | PLANS PREPARED BY: FROM ZERO the solution 1033 Watervliet Shaker Phone: 518-690-0790 www.infi JOB NUMBER | TO INFIN vitions are en Rd Albany, Fax: 518-67 nigy.com 2 526-104 | NIG ndles | Y 55 2 2 0 5 3 3 |
| | | | | PROJECT MANAGER: AIROS 32 CLINTU SARATOGA SPRI OFFICE#, (518 | ON ST. NGS, NY 12866 3) 306-3740 | | T |
| | | | | ENGINEERING LICENSE: - | | | |
| | NO | SCALE | 3 | | | | |
| | RA[| | | DRAWING NOTICE: THESE DOCUMENTS ARE THE SOLE PROPERTY OF S REPRODUCED, DISSEMINA WITHOUT THE EXPRESS | CONFIDENTIAL A PRINT AND MA' ATED OR REDIST WRITTEN CONS | AND AI Y NOT RIBUTI ENT O | RE BE ED F |
| ±222* | ±126' A | AGL | | | DATE | BY | REV. |
| ±193'* | ±126' / | AGL | | ISSUED FOR PERMIT | 03/05/18 | ETC | 0 |
| ±222'* | ±126' / | AGL | | RASMUSSI TA | EN WAT NK | ÈR | |
| | | | | CT032 | KC202 | | |
| | |] | | 160 PLANTA EAST WINDS | TION RO OR, CT 0 | AD 6010 | 6 |
| | | | | TOWER EL & CABL | LEVATIO E PLAN | N | |
| | NO | SCALE | 4 | A | -2 | | |



| RATION PLA | NS ARE BASED ON | | PLANS PREPARED FOR: |
|--|--|-------------|--|
| NLY. CONTR PRIOR TO C | AND ARE FOR CONCEP ACTOR TO VERIFY FIEL ONSTRUCTION. | D | |
| <u>NOTE</u> : JUMPERS ANTENNA | FROM 2.5 RRH TO THE CANNOT EXCEED 15 FE | 2.5 ET | Sprint 🦉 |
| -EXISTING (PANEL AN ANEL AN O') EXISTING (MODAL PA REMAIN EA EXISTING (1900 MHz REMAIN EA STALL FIBER FROM | CARRIER TENNA (TYP.) (1) SPRINT MULTI INEL ANTENNA TO ACH SECTOR (1) SPRINT RCH TO ACH SECTOR (2) AND POWER BREAKOUT BREAKOUT RCH'S | | PLANS PREPARED BY: INFINICY FROM ZERO TO INFINIGY the solutions are endless 1033 Watervliet Shaker Rd Albany, NY 12205 Phone: 518-690-0790 Fax: 518-690-0793 www.infinigy.com JOB NUMBER 526-104 PROJECT MANAGER: AREOSAL |
| LINDER TO | кк <i>п</i> | | SARATOGA SPRINGS, NY 12866 OFFICE#. (518) 306-3740 |
| EXISTING WA TANK LEG (| NTER TYP.) N | | ENGINEERING LICENSE: |
| | 0° = TRUE NORTH | | |
| | NO SCALE | 2 | |
| | | | |
| RE COILED (E ARE TO B IED INTO EX INCTION BOX | UP ON NV RRHS AT IE USED TO POWER UP ISTING DC BREAKERS LOCATED AT EQUIPMEN POSITION RRH ON MOU | / <i>T.</i> | DRAWING NOTICE: THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT. |
| ANTENNA | SUCH THAT THE RRH ERE WITH THE EXISTING | 3 | |
| AGRAM IS F SES ONLY. TO PASSING ITENNA AND | OR CONCEPTUAL CONTRACTOR IS TO 3 STRUCTURAL ANALYS RRH MOUNTING DETA | IS | |
| DC CONDUC FIBER CABL OF RRH. | TORS TO LENGTH. | | SITE NAME: RASMUSSEN WATER TANK |
| O EXCEED | BEND RADIUS. | | CT03XC202 |
| | | | SITE ADDRESS: 160 PLANTATION ROAD EAST WINDSOR, CT 06016 SHEET DESCRIPTION: |
| | | | ANTENNA LAYOUT & MOUNTING DETAILS |
| | NO SCALE | 4 | A_3 |
| | NU JUALE | 1 | |



| | | PLANS PREPARED FOR: | | | |
|----------|---|---|---|----------------------------------|--------------------------|
| | | Sprint | | Ņ | |
| | | PLANS PREPARED BY: INFORM ZERO TO the solutions 1033 Waterviet Shaker Rd I Phone: 518-690-0790 Fax www.infinigy.c JOB NUMBER 526- | INFIN are ei Albany, 518-69 om 104 | NIG ndle | Y SS 2205 93 |
| | | PROJECT MANAGER: AIROSN 32 CLINTON ST. SARATOGA SPRINGS, IN: OFFICE#. (518) 306-37 ENGINEERING LICENSE: | OPM 12866 40 | | IT |
| | | | | | |
| NO SCALE | 2 | | | | |
| | | DRAWING NOTICE: THESE DOCUMENTS ARE CONFI THE SOLE PROPERTY OF SPRINT REPRODUCED, DISSEMINATED C WITHOUT THE EXPRESS WRITT SPRINT. | DENTIAL A AND MA PR REDIST EN CONS | AND A Y NOT RIBUT ENT C | ARE I BE TED DF |
| | | REVISIONS: | DATE | BY | REV. |
| | | ISSUED FOR PERMIT | 03/05/18 | ETC | 0 |
| | | RASMUSSEN TANK | WAT | ER | |
| | | CT03XC2 | 202 | | |
| | | SITE ADDRESS: 160 PLANTATIO EAST WINDSOR, SHEET DESCRIPTION: | N RO CT 0 | 0AD 601 | 6 |
| | | EQUIPMEN' MOUNTING DI | T & ETAII | LS | |
| NO SCALE | 4 | A-4 | | | |



| 0.D. HOLES X (4) D 2.5 HYBRIFLEX C | FOR ABLES O.D. HOLES X 2 IGHT CONDUIT T | FOR O BTS | Sprir | nt 🎾 |
|---------------------------------------|--|--------------|--|---|
| ÓO | | | FROM ZERO the solution Phone: 518-690-0790 www.infi JOB NUMBER | TO INFINIGY tions cre endless Rd Albany, NY 12205 Fax: 518-690-0793 nigy.com 2:526-104 |
| | | | PROJECT MANAGER: AIROS 32 CLINIT SARATOGA SPRII OFFICE#. (518 | VELOPMENT VELOPMENT DN ST. (05, NY 12866 3) 306-3740 |
| | | | | |
| | NO SCALE | 2 | | |
| | | | DRAWING NOTICE: THESE DOCUMENTS ARE THE SOLE PROPERTY OF S REPRODUCED, DISSEMINJ WITHOUT THE EXPRESS SPRI | CONFIDENTIAL AND ARE PRINT AND MAY NOT BE ATED OR REDISTRIBUTED WRITTEN CONSENT OF NT. |
| | | | REVISIONS: DESCRIPTION | DATE BY REV. |
| | | | ISSUED FOR PERMIT | 03/05/18 ETC 0 EN WATER |
| | | | | NK |
| | | | CT032 | TION DOAD |
| | | | 160 PLANTA EAST WINDS | TION ROAD OR, CT 06016 |
| | | | | ETAILS |
| | NO SCALE | 3 | A | -5 |





ALU 2.5 ALU SCENARIO 1



RF 2.5 ALU SCENARIO 1

PLUMBING DIAGRAM



A-6

NO SCALE

1

| | | NV CABLES | | |
|--------|-------|-----------|------|-------|
| BAND | INDIC | ATOR | PORT | COLOR |
| 800-1 | YEL | GRN | NV-1 | GRN |
| 1900-1 | YEL | RED | NV-2 | BLU |
| 1900-2 | YEL | BRN | NV-3 | BRN |
| 1900-3 | YEL | BLU | NV-4 | WHT |
| 1900-4 | YEL | SLT | NV-5 | RED |
| 800-2 | YEL | ORG | NV-6 | SLT |
| SPARE | YEL | WHT | NV-7 | PPL |
| 2500 | YEL | PPL | NV-8 | ORG |

| HYBRID | | | |
|--------|-------|--|--|
| HYBRID | COLOR | | |
| 1 | GRN | | |
| 2 | BLU | | |
| 3 | BRN | | |
| 4 | WHT | | |
| 5 | RED | | |
| 6 | SLT | | |
| 7 | PPL | | |
| 8 | ORG | | |

| 2.5 Ban | d |
|--------------|-------|
| 2500 Radio 1 | COLOR |
| YEL WHT | GRN |
| YEL WHT | BLU |
| YEL WHT | BRN |
| YEL WHT | WHT |
| YEL WHT | RED |
| YEL WHT | SLT |
| YEL WHT | PPL |
| YEL WHT | ORG |

Figure 1: Antenna Orientation



NOTES:

1. ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.

2. THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.

3. A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.

4. THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.

5. SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.

6. HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.

7. HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.

8. INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

| Sector | Cable | ble First Ring Ring | | Third Ring | | |
|---------|-------|---------------------|---------|------------|--|--|
| 1 Alpha | 1 | Green | No Tape | No Tape | | |
| 1 | 2 | Blue | No Tape | No Tape | | |
| 1 | 3 | Brown | No Tape | No Tape | | |
| 1 | 4 | White | No Tape | No Tape | | |
| 1 | 5 | Red | No Tape | No Tape | | |
| 1 | 6 | Grey | No Tape | No Tape | | |
| 1 | 7 | Purple | No Tape | No Tape | | |
| 1 | 8 | Orange | No Tape | No Tape | | |
| 2 Beta | 1 | Green | Green | No Tape | | |
| 2 | 2 | Blue | | No Tape | | |
| 2 | 3 | Brown | Brown | No Tape | | |
| 2 | 4 | White | White | No Tape | | |
| 2 | 5 | Red | Red | No Tape | | |
| 2 | 6 | Grey | Grey | No Tape | | |
| 2 | 7 | Purple | Purple | No Tape | | |
| 2 | 8 | Orange | Orange | No Tape | | |
| 3 Gamma | 1 | Green | Green | Green | | |
| 3 | 2 | Bue | | | | |
| 3 | 3 | Brown | Brown | Brown | | |
| 3 | 4 | White | White | White | | |
| 3 | 5 | Red | Red | Red | | |
| 3 | 6 | Grey | Grey | Grey | | |
| 3 | 7 | Purple | Purple | Purple | | |
| 3 | 8 | Orange | Orange | Orange | | |

| NV | | 2023.001 |
|-----------|-----------|----------|
| FREQUENCY | INDICATOR | ID |
| 800-1 | YEL | GRN |
| 1900-1 | YEL | RED |
| 1900-2 | YEL | BRN |
| 1900-3 | YEL | BLU |
| 1900-4 | YEL | SLT |
| 800-1 | YEL | ORG |
| RESERVED | YEL | WHT |
| RESERVED | YEL | PPL |

| 2.5 FREQUENCY | IN | ID | |
|------------------|-----|-----|-----|
| 2500 -1 | YEL | WHT | GRN |
| 2500 - 2 | YEL | WHT | RED |
| 2500 -3 | YEL | WHT | BRN |
| 2500 -4 | YEL | WHT | BLU |
| 2500 -5 | YEL | WHT | SLT |
| 2500 -6 | YEL | WHT | ORG |
| 2500 -7 | YEL | WHT | WHT |
| 2500 -8 | YEL | WHT | PPL |



Example – Sector 2, Cable





COLOR CODING & NOTES

| | | | PLANS PREPA | ARED FOR: | | | |
|---------|--------------|----|--|---|--|----------------------------------|------------------------------------|
| | | | Sp | rint | | Ņ | |
| | | | FROM | ZERO TO the solution liet Shaker Rd I sogoorgo Fa www.infinigy. JOB NUMBER 526 | INFIN Albany, x: 518-65 com -104 | NIG ndle | Y 57 53 2205 93 |
| | | | | AGGER: OSA 32 CLINTON ST. ARATOGA SPRINGS, N OFFICE#. (518) 306-33 | Y 12866 7740 | EN | IT |
| | | | | 3 LICENSE: | | | |
| | | | DRAWING NC THESE DOCU THE SOLE PR REPRODUCEI WITHOUT T | IMENTS ARE CONF OPERTY OF SPRIN D, DISSEMINATED THE EXPRESS WRIT SPRINT. | IDENTIAL / F AND MA` OR REDIST TEN CONS | AND A (NOT RIBU1 ENT (| ARE "BE TED DF |
| | | þ | REVISIONS: | CRIPTION | DATE | BY | REV. |
| 2, 800r | mhz Radio #1 | | ISSUED FOR PERM | IT | 03/05/18 | ETC | 0 |
| | | b | RASN | MUSSEN TANK | WAT | ΈF | ર |
| 1, 1900 | mhz Radio #1 | ш- | | CT03XC | 202 | | |
| | | | SITE ADDRES | LANTATIC | ON RO , CT 0 | AD 601 |) 6 |
| 4, 800 | mhz Radio #1 | þ | | RIPTION: OLOR COI & NOTE | DING S | | |
| Radio # | NO SCALE | | - SHEET NUMB | A-7 | 1 | | |
| | NO SUALL | ' | | 1 | | | |



| | | | PLANS PREPARED FOR: |
|---|--|---|---|
| | | | Sprint 🎾 |
| | | | PLANS PREPARED BY: FROM ZERO TO INFINIGY the solutions are enalless 1033 Watervliet Shaker Rd Albany, NY 1220 Phone: 518-690-0790 Fax: 518-690-0793 www.infinigy.com JOB NUMBER 526-104 |
| | | | PROJECT MANAGER: AIROSSMITH DEVELOPMENT 32 CLINTON ST. SARATOGA SPRINGS, NY 12866 OFFICE#. (518) 306-3740 |
| | | | |
| | NO SCALE | 1 | |
| | | | DRAWING NOTICE: THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT. |
| | | | REVISIONS: DESCRIPTION DATE BY REV |
| | | | |
| | | | ISSUED FOR PERMIT 03/05/18 ETC 0 |
| | | | RASMUSSEN WATER TANK |
| | | | |
| | | | C103XC202 |
| ALL (2) HYL TING SPRINT TO PROPOS | BRID CABLES FROM TFIBER JUNCTION SED RRH UNIT | | SITE ADDRESS: 160 PLANTATION ROAD EAST WINDSOR, CT 06016 |
| ALL (2) HY TING SPRINT TO PROPOS | BRID CABLES FROM T FIBER JUNCTION SED RRH UNIT | | SITE ADDRESS: 160 PLANTATION ROAD EAST WINDSOR, CT 06016 SHEET DESCRIPTION: ELECTRICAL & GROUNDING PLAN |



| | | | PLANS PREPARED FOR: | | | |
|---------|--------------------------------|------------|--|--|-----------------------------------|------------------------------|
| | | | Sprin | t | Ņ | |
| | EXISTING BBU CABINET | | PLANS PREPARED BY: INFINITION FROM ZERO TO the solution Phone: 518:690-0790 www.infinity JOB NUMBER ST PROJECT MANAGER: | C INFIN ons are e d I Albany, Fax: 518-6 gy.com 526-104 | NIG ndle | y ss 2205 93 |
| | | | AIROSL SARATOGA SPRING OFFICE#. (518) 30 ENGINEERING LICENSE: | MIT 'ELOPM ST. 5, NY 12866 06-3740 | | IT |
| LEGEND | NO SCALE | 1 | | | | |
| - G | EXISTING GROUND R | ring Dn | | | | |
| | MECHANICAL CONNE | CTION | | | | |
| ⊗ ● | GROUND ROD CABLE GROUND KIT | | THESE DOCUMENTS ARE CO THE SOLE PROPERTY OF SPR REPRODUCED, DISSEMINATE WITHOUT THE EXPRESS W SPRINT | ONFIDENTIAL INT AND MA ED OR REDIST RITTEN CONS | AND A Y NOT RIBUT SENT C | ARE BE FED DF |
| | | | REVISIONS: DESCRIPTION | DATE | BY | REV. |
| L | | | | | | |
| | · | | ISSUED FOR PERMIT | 03/05/18 | ETC | 0 |
| | | | RASMUSSEN TAN | N WAT K | TER | |
| | | | SITE NUMBER: | C202 | | |
| | BARS (TYP) | JND | SITE ADDRESS: 160 PLANTAT EAST WINDSO | ION RC PR, CT 0 | 0AE 0601 | 6 |
| | | | SHEET DESCRIPTION: ELECTRIC GROUNDING | CAL & DETAI | ILS | |
| AR I | | | | <u></u> | | |
| | NO SCALE | 4 | <u> </u> | <u></u> | | |
| | | | | | - | |