

Crown Castle 3530 Toringdon Way Suite 300 Charlotte, NC 28277 Tel: 704-405-6600

www.crowncastle.com

March 21, 2014

Melanie A. Bachman Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

RE: Sprint PCS-Exempt Modification - Crown Site BU: 876348

Sprint PCS Site ID: CT03XC221

Located at: Bright Meadow Boulevard, Enfield, CT 06082

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies ("R.C.S.A."), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to The Honorable Scott R. Kaupin, Mayor for the Town of Enfield.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **Bright Meadow Boulevard**, **Enfield**, **CT 06082**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint's operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes ("C.G.S.") § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

- 1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint's additional antennas will be located at the same elevation on the existing tower.
- 2. There will be no proposed modifications to the ground and no extension of boundaries.
- 3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

- 4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
- 5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,

Jeff Barbadora

Real Estate Specialist

Jeff Barbla

Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: The Honorable Scott R. Kaupin, Mayor

Town of Enfield 820 Enfield Street

Enfield, CT 06082-2997



CROWN

PROJECT:

2.5 EQUIPMENT DEPLOYMENT

SITE NAME:

ENFIELD

SITE CASCADE:

CT03XC221

SITE NUMBER:

876348

Know what's below. Call before you dig.

SITE ADDRESS:

BRIGHT MEADOW BLVD.

ENFIELD, CT 06082

SITE TYPE:

MONOPOLE TOWER

MARKET:

NORTHERN CONNECTICUT

PROJECT DESCRIPTION DRAWING INDEX AREA MAP SITE INFORMATION SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY. SHEET NO: SHEET TITLE **TOWER OWNER:** outh st CROWN ATLANTIC COMPANY LLC 2000 CORPORATE DRIVE CANONSBURG, PA 15317 (704) 405-6555 T-1 TITLE SHEET & PROJECT DATA INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS Wolf Swamp Rd Conn INSTALL (3) PANEL ANTENNAS SPRINT SPECIFICATIONS SPRINT SPECIFICATIONS INSTALL (3) RRU'S TO TOWER SP-3 SPRINT SPECIFICATIONS LATITUDE (NAD83): INSTALL (27) JUMPER CABLES 42" 1" 14.91" N 42.020809" SITE PLAN SITE INSTALL (1) FIBER CABLE TOWER ELEVATION & CABLE PLAN A-2 ANTENNA LAYOUT & MOUNTING DETAILS A-3 INSTALL (4) BATTERIES IN EXISTING BBU CABINET LONGITUDE (NAD83): A-4 COLOR CODING AND NOTES 72° 35′ 6.59″ W -72.585164° A-5 EQUIPMENT & MOUNTING DETAILS CIVIL DETAILS A-6 PLUMBING DIAGRAM A-7 **COUNTY:** HARTFORD 1901 ELECTRICAL & GROUNDING PLAN THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT. ELECTRICAL & GROUNDING DETAILS Hazardvill E-2 **ZONING JURISDICTION:** TOWN OF BRUNSWICK TFORD CONNECTIC Copyright © and (P) 1988 2010 Microsoft Corporation Nand/or its suppliers. All rights reserved.

LOCATION MAP ZONING DISTRICT: APPLICABLE CODES POWER COMPANY: CONNECTICUT LIGHT & POWER ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN nen si (860) 947-2000 ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADDPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES. **AAV PROVIDER:** INTERNATIONAL BUILDING CODE (2012 IBC)
TIA-EIA-222-F OR LATEST EDITION
NPPA 780 - LIGHTNING PROTECTION CODE
2011 NATIONAL ELECTRIC CODE OR LATEST EDITION
ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES,
MOST RECENT EDITIONS (800) 246-8464 SPRINT CM: PETER CULBERT (603) 203-6446 CT BUILDING CODE LOCAL BUILDING CODE (603) 969-0686 PETER, CULBERT OSPRINT, COM SITE 8. CITY/COUNTY ORDINANCES CROWN CASTLE CM: JASON D'AMICO JASON.D'AMICO CROWNCASTLE.COM




PLANS PREPARED BY:

INFINIGY Build.

1033 Watervliet Shaker Rd Albany, NY 12205 Office # (518) 690-0790 Fax # (518) 690-0793

JOB NUMBER 353-000





- DRAWING NOTICE

В

В

В

В

В

В

В

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE
THE SOLE PROPERTY OF SPRINT AND MAY NOT BE
REPRODUCED, DISSEMINATED OR REDISTRIBUTED
WITHOUT THE EXPRESS WRITTEN CONSENT OF

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENTS	2/12/14	MAP	B
ISSUED FOR REVIEW	12/31/13	MER	A

SITE NAME:

ENFIELD

SITE CASCADE:

CT03XC221

TE ADDRESS:

BRIGHT MEADOW BLVD. ENFIELD, CT 06082

SHEET DESCRIPTION:

TITLE SHEET & PROJECT DATA

SHEET NUMBER:

T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED
- 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
- 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
- 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
- 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
- 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
- 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
- 7. AMERICAN CONCRETE INSTITUTE (ACI)
- 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
- 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
- 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
- 11. PORTLAND CEMENT ASSOCIATION (PCA)
- 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
- 13. BRICK INDUSTRY ASSOCIATION (BIA)
- 14. AMERICAN WELDING SOCIETY (AWS)
- 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
- 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
- 17. DOOR AND HARDWARE INSTITUTE (DHI)
- 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
- 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDMDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED. CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER ALL PROJECTS RELATED COMMUNICATION TO FLOW ROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION, ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM
- A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
- B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE
- C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE.
 SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION.
 CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE, USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
- A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
- B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
- 1 ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
- 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
- 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION
- 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF
- 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
- 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE

3.2 DELIVERABLES:

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 - CELL SITE CONSTRUCTION CO.

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 - PRODUCTS (NOT USED)

3.1 FUNCTIONAL REQUIREMENTS:

PART 3 - EXECUTION

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

W

PLANS PREPARED FOR:

6580 Sprint Parkway Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervillet Sheker Rd Albany, NY 12205 Office # (518) 690-0790 Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER





DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	1		Sound
DESCRIPTION	DATE	BY	REV
		_	_
	_	\vdash	H
REVISED PER COMMENTS	2/12/14	MAP	В
ISSUED FOR REVIEW	12/31/13	MER	A

ENFIELD

CT03XC221

SITE ADDRESS:

BRIGHT MEADOW BLVD. ENFIELD, CT 06082

SHEET DESCRIPTION: =

SPRINT SPECIFICATIONS

SP-

CONTINUE FROM SP-1

- 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
- PREPARE GROUND SITES; PROVIDE DE—GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
- 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
- 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
- 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
- 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
- 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
- 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
- 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND I ANDI ORDS.
- PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
- 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND—OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED 'BROOM CLEAN' AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
- IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
- CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
- 2. PROJECT PROGRESS REPORTS.
- 3. CIML CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

- LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
- CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 SUBMITTALS

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL
 - CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 - 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 - 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 - 5. CHEMICAL GROUNDING DESIGN
- D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
- 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE—FOR—THE—PURPOSE ANTENNA ALIGNMENT TOOL.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING;
 - . AZIMUTH, DOWNTILT, AGL UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
- 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS—BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS—BUILT" CONDITION.

- 6. LIEN WAIVERS
- 7. FINAL PAYMENT APPLICATION
- 8. REQUIRED FINAL CONSTRUCTION PHOTOS
- 9 . CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
- ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).
- 1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPB
- 1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 REQUIREMENTS FOR TESTING:
 - A. THIRD PARTY TESTING AGENCY:
 - WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
 - THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 - 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
 - 4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOILOWING:
 - CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
- 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT BANKS
- 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
- 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
- 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
- SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
- ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
- 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
- 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
- GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
- FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
- COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
- 4. PRE— AND POST—CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
- 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
- ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS — ANTENNALIGN ALIGNMENT TOOL (AAT)

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Build.
Deliver.

1033 Watervliet Shaker Rd Albany, NY 12205 Office # (518) 690-0790 Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:





- DRAWING NOTICE: •

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

			_
DESCRIPTION	DATE	BY	REV
REVISED PER COMMENTS	2/12/14	MAP	В
ISSUED FOR REVIEW	12/31/13	MER	A

SITE NAME:

ENFIELD

CITE CARCADE

CT03XC221

SITE ADDRESS:

BRIGHT MEADOW BLVD. ENFIELD, CT 06082

SHEET DESCRIPTION: =

SPRINT SPECIFICATIONS

HEET NUMBER:

SP-2

CONTINUE FROM SP-2

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP
- B. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
- 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF
- 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
- 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
- 2. STRUCTURAL BACKFILL COMPACTION REPORTS
- 3. SITE RESISTANCE TO EARTH TEST.
- 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
- 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS
- 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
- 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS
- 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD
- 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS — PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
- 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; ANTENNA GROUND BAR, EQUIPMENT GROUND BAY, AND MASTER GROUND BAY, ANTENNAS; ONE PHOTOS OF GPS ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING — TOP AND BOTTOM; PHOTOS OF COAX GROUNDING—TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO
- 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION: PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF:
- 6. SITE LAYOUT PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
- 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
- 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN
- 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 WEEKLY REPORTS:

- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 PROJECT CONFERENCE CALLS:

A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS

3.3 PROJECT TRACKING IN SMS:

A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 PROJECT PHOTOGRAPHS:

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
- 1. 1SHELTER AND TOWER OVERVIEW.
- 2. TOWER FOUNDATION(S) FORMS AND STEEL BEFORE POUR (EACH ANCHOR
- 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON
- 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS)
- 5. PHOTOS OF TOWER SECTION STACKING.
- 6. CONCRETE TESTING / SAMPLES.
- 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
- 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
- 9. SHELTER FOUNDATION -- FORMS AND STEEL BEFORE POURING
- 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
- 11. COAX CABLE ENTRY INTO SHELTER.
- 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS
- 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT
- 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
- 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
- 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
- 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
- 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL
- 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 25. ALL BTS GROUND CONNECTIONS
- 26. ALL GROUND TEST WELLS.
- 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
- 2B. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
- 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
- 30. GPS ANTENNAS.
- 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
- 32. DOGHOUSE/CABLE EXIT FROM ROOF.
- 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
- 34. MASTER BUS BAR.
- 35. TELCO BOARD AND NIU
- 36. ELECTRICAL DISTRIBUTION WALL.
- 37. CABLE ENTRY WITH SURGE SUPPRESSION.
- 38. ENTRANCE TO EQUIPMENT ROOM.
- 39. COAX WEATHERPROOFING-TOP AND BOTTOM OF TOWER.
- 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
- 41. ANTENNA AND MAST GROUNDING.
- 42. LANDSCAPING WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.



PLANS PREPARED BY: -

MI A PARTNER

Albany, NY 12205 Office # (518) 690-0790

JOB NUMBER 353-000



RAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF

PREVISIONS: DESCRIPTION	DATE	BY	REV
REVISED PER COMMENTS	2/12/14	MAP	В
ISSUED FOR REVIEW	12/31/13	MER	A

SITE NAME:

ENFIELD

SITE CASCADE:

CT03XC221


BRIGHT MEADOW BLVD. ENFIELD, CT 06082


SHEET DESCRIPTION: -


SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2








		NV CABLE	5	
BAND	INDIC	INDICATOR		COLOR
800-1	YEL	GRN	NV-1	GRN
1900-1	YEL	RED	NV-2	BLU
1900-2	YEL	BRN	NV-3	BRN
1900-3	YEL	BLU	NV-4	WHT
1900-4	YEL	SLT	NV-5	RED
800-2	YEL	ORG	NV-6	SLT
SPARE	YEL	WHT	NV-7	PP
2500	YEL	PPL	NV-8	ORG

HYBR	ID
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	REO
6	SLT
7	Pitt
8	ORG

Figure 1: Antenna Orientation



- 1. ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- 2. THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- 3. A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO
- 4. THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- 5. SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- 6. HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- 7. HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- 8. INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Gille	No Tape	No Tape
1	3	L Skiller	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
ī	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Blue -	Blue	No Tape
2	3	10 - 21		No Tape
2	4	White	White	No Tape
2	5	Redeva	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Blue	Blue	自加度
3	3	To the same		
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple :
3	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	HPU.

2.5 FREQUENCY	IN	DICATOR	ID
2500 -1	YEL	WHT	GRN.
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PEL







PLANS PREPARED BY:

1033 Watervliet Shaker Rd Albany, NY 12205 Office # (518) 690-0790 Fax # (518) 690-0793

JOB NUMBER 353-000



THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

- REV	ISIONS:			
	DESCRIPTION	DATE	BY	REV
REVISE	D PER COMMENTS	2/12/14	MAP	8
	FOR REVIEW	12/31/13	MER	A

SITE NAME:

ENFIELD

CT03XC221

BRIGHT MEADOW BLVD. ENFIELD, CT 06082

COLOR CODING AND NOTES

- SHEET NUMBER:

A-4




Example - Sector 2, Cable 2, 800mhz Radio #1



Example - Sector 3, Cable 1, 1900mhz Radio #1




Example - Sector 1, Cable 4, 800 mhz Radio #1 and 1900mhz Radio #1





RFS HYBRIFLEX RISER CABLE SCHEDULE



RFS HYBRIFLEX JUMPER CABLE SCHEDULE

It, 3x multi-mode fiber pairs, Outdoor & 1C connectors, 1/2 cable


Hybrid Jumper cable


MN: HBF012-M3-SF1

MN: HBF012-M3-10F1

ë	MN; HBF012-M3-15F1	15 It
Œ	MN: HBF012-M3-20F1	20 fc
	MN: H8F012-M3-25F1	25 lt
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN:HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x mulii-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 fl
0	MN: HBF058-08U1M3-10F1	10 lt
3	MN:HBF058-08U1M3-15F1	15 ft
20	MN: HBF058-08U1M3-20F1	20 ft
	MN:HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs. Outdoor & IC Connectors, 5/8 cable MN:HBF058-13U1M3-10F1 MN:HBF058-13U1M3-15F1 MN:HBF058-13U1M3-20F1	10 ft 15 ft 20 ft
	MN: HBF058-13U1M3-25FL MN: HBF058-13U1M3-30FL	25 ft 30 ft
AWG Power	Hybrid Jumpor cable MN: H8F078-21U1M3-5F1 5 It. 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
ď.	MN: HBF078-21U1M3-10FL	10 ft
š	MN: HBF078-21U1M3-15F1	15 ft
₹ 7	M N: HBF078-21U1M3-20F1	20 It
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE
AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF
HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.







5 ft

10 ft

8 & 6 AWG



FIBER ONLY



FIBER JUNCTION BOX PENETRATION

NO SCALE



- PLANS PREPARED BY:

1033 Watervliet Shaker Rd Albany, NY 12205 Office # (518) 690-0790 Fax # (518) 690-0793

JOB NUMBER 353-000

MI A PARTNER:



- ENGINEERING LICENSE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:			
DESCRIPTION	DATE	BY	RE\
	-		
REVISED PER COMMENTS	2/12/14	MAP	В
ISSUED FOR REVIEW	12/31/13	MER	A

ENFIELD

- SITE CASCADE: -

CT03XC221

- SITE ADDRESS: -

BRIGHT MEADOW BLVD. ENFIELD, CT 06082

- SHEET DESCRIPTION: -

CIVIL DETAILS

- SHEET NUMBER: •


A-6

2.5 CABLE CROSS SECTION DATA


NO SCALE

DETAIL NOT USED


NO SCALE



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1



PLANS PREPARED BY:

INFINIGY Build.

1033 Watervliet Shaker Rd Albany, NY 12205 Office # (518) 690-0790 Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNE



ENGINEERING LICENSE:



- DRAWING NOTICE

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENTS	2/12/14	MAP	В
ISSUED FOR REVIEW	12/31/13	MER	Α

- SITE NAM

ENFIELD

SITE CASCADE:

CT03XC221

SITE ADDRESS:

BRIGHT MEADOW BLVD. ENFIELD, CT 06082

SHEET DESCRIPTION:

PLUMBING DIAGRAM

SHEET NUMBER: -

A-7

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

NFINIGY Bailgn. Deliver.

33 Watervliet Shaker Ro Albany, NY 12205 Office # (518) 690-0790 Fax # (518) 690-0793

JOB NUMBER 353-000

CROYUN CASTLE

No. 24705

OF CONNECTION OF CO

- DRAWING NOTE

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:			T
DESCRIPTION	DATE	BY	RE
	_	-	-
REVISED PER COMMENTS	2/12/14	MAP	В
ISSUED FOR REVIEW	12/31/13	MER	A

- SITE NAME

ENFIELD

SITE CASCADE:

CT03XC221

SITE ADDRESS: •


BRIGHT MEADOW BLVD. ENFIELD, CT 06082


- SHEET DESCRIPTION: -

ELECTRICAL & GROUNDING PLAN

SHEET NUMBER: -

E-1







RADIO FREQUENCY FCC REGULATORY COMPLIANCE MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC221

Enfield

Bright Meadow Boulevard Enfield, CT 06082

March 19, 2014

EBI Project Number: 62141237



March 19, 2014

Sprint Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site: CT03XC221 - Enfield

Site Total: 68.506% - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at Bright Meadow Boulevard, Enfield, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm2). The number of μ W/cm2 calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limit for the cellular band (850 MHz Band) is approximately 567 μ W/cm², and the general population exposure limit for the 1900 MHz and 2500 MHz bands band is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at Bright Meadow Boulevard, Enfield, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 3 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications was used in this direction.



- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTMM-C-120. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTMM-C-120 has a 15.9 dBd gain value at its main lobe at 2500 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.
- 7) The antenna mounting height centerline for the proposed antennas is **147 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

	Site ID		03XC221 - Enfi																
	Site Addresss	Bright Meadow		field, CT 06082															
	Site Type		Monopole																
	Sector 1																		
						Power			Antenna Gain										
						Out Per			in direction			Antenna						Power	Power
Antenna						Channel	Number of	Composite	of sample	Antenna	analysis	Height		Cable Loss	Additional			Density	Density
	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power		Height (ft)	height	_	Cable Size			Gain Factor	ERP	Value	Percentage
1a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	15.9	147	141	42.97732	1/2 "	0.5	3		1042.6805	18.85467	1.88547%
1a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722		3.534254	0.62333%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	390.89489	7.068508	1.24665%
	Sector total Power Density Value: 3.755%																		
	Sector 2																		
						Power			Antenna Gain										
						Out Per			in direction		1	Antenna		0.1.1.1	A dates and			Power	Power
Antenna	Antonna Mako	Antonna Madal	Padio Tuno	Fraguency Band	Tochnology	Channel (Matte)	Number of	Composite	of sample		analysis	Height	Cable Size	Cable Loss (dB)		Gain Factor	ERP	Density	Density
Number 2a	Antenna Make RFS	Antenna Model APXVSPP18-C-A20	Radio Type RRH	Frequency Band 1900 MHz	Technology CDMA / LTE	(Watts)	Channels 3	Power 60	point (dBd) 15.9	147	height 141	Meters 42.97732	1/2 "	0.5	3		1042.6805	Value 18.85467	Percentage 1.88547%
2a 2a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722		3.534254	0.62333%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	390.89489	7.068508	1.24665%
20	11.13	Al AVIIVIIVITA C 120	Iddi	2500 141112	CDIVIA / ETE	20		40	13.4	147	171	42.57752	,	0.0	ensity Value:	3.7723722	3.755%	7.000500	1.2400370
								6							,				
								Sector	13										ı
						Power			Antenna Gain										
						Out Per			in direction			Antenna						Power	Power
Antenna						Channel	Number of	Composite	of sample	Antenna	analysis	Height		Cable Loss	Additional			Density	Density
Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power	point (dBd)	Height (ft)	height		Cable Size	(dB)	Loss (dB)	Gain Factor	ERP	Value	Percentage
3a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	15.9	147	141	42.97732	1/2 "	0.5	3	17.378008	1042.6805	18.85467	1.88547%
3a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722	195.44744	3.534254	0.62333%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	147	141	42.97732	1/2 "	0.5	3	9.7723722		7.068508	1.24665%
	3B RFS APXVTMM14-C-120 RRH 2500 MHz CDMA / LTE 20 2 40 13.4 147 141 42.97732 1/2" 0.5 3 9.7723722 390.89489 7.068508 1.24665% Sector total Power Density Value: 3.755%																		

Site C	Site Composite MPE %								
Carrier	MPE %								
Sprint	11.266%								
AT&T	23.030%								
MetroPCS	10.620%								
Clearwire	0.860%								
Nextel	3.540%								
Verizon Wireless	18.100%								
XM Satellite Radio	1.090%								
Total Site MPE %	68.506%								



Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are 11.266% (3.755% from each sector) of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **68.506**% of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan

RF Engineering Director

EBI Consulting

21 B Street

Burlington, MA 01803



Date: January 06, 2014

Timothy Liebrock Crown Castle 11 Grandview Circle Suite 220 Canonsburg, PA 15317

Paul J Ford and Company 250 E. Broad Street Suite 600 Columbus, OH 43215 614.221.6679

Subject:

Structural Analysis Report

Carrier Designation:

Sprint PCS Co-Locate Carrier Site Number: Carrier Site Name:

Scenario 2.5A CT03XC221

ENFIELD

Crown Castle Designation:

Crown Castle BU Number: Crown Castle Site Name:

876348 **ENFIELD**

Crown Castle JDE Job Number: Crown Castle Work Order Number:

252879 694127

Crown Castle Application Number:

208037 Rev. 3

Engineering Firm Designation:

Paul J Ford and Company Project Number: 37513-0644 R2

Site Data:

Bright Meadow Blvd., ENFIELD, Hartford County, CT

Latitude 42° 1' 14.91", Longitude -72° 35' 6.59"

147.5 Foot - Monopole Tower

Dear Timothy Liebrock,

Paul J Ford and Company is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 606419, in accordance with application 208037, revision 3.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC11: Existing + Reserved + Proposed Equipment

Sufficient Capacity


Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 CT State Building Code based upon a fastest mile wind speed of 80 mph with no ice, 37.6 mph with 1 inch ice thickness and 50 mph under service loads.

We at Paul J Ford and Company appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:

Nick Parente, E.I. Structural Designer





Date: January 06, 2014

Timothy Liebrock Crown Castle 11 Grandview Circle Suite 220 Canonsburg, PA 15317 Paul J Ford and Company 250 E. Broad Street Suite 600 Columbus, OH 43215 614.221.6679

Subject: Structural Analysis Report

Carrier Designation:Sprint PCS Co-LocateScenario 2.5ACarrier Site Number:CT03XC221

Carrier Site Name: ENFIELD

Crown Castle Designation: Crown Castle BU Number: 876348

Crown Castle Site Name:ENFIELDCrown Castle JDE Job Number:252879Crown Castle Work Order Number:694127

Crown Castle Application Number: 208037 Rev. 3

Engineering Firm Designation: Paul J Ford and Company Project Number: 37513-0644_R2

Site Data: Bright Meadow Blvd., ENFIELD, Hartford County, CT

Latitude 42° 1' 14.91", Longitude -72° 35' 6.59"

147.5 Foot - Monopole Tower

Dear Timothy Liebrock,

Paul J Ford and Company is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 606419, in accordance with application 208037, revision 3.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC11: Existing + Reserved + Proposed Equipment

Sufficient Capacity

Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.

The analysis has been performed in accordance with the TIA/EIA-222-F standard and the 2005 CT State Building Code based upon a fastest mile wind speed of 80 mph with no ice, 37.6 mph with 1 inch ice thickness and 50 mph under service loads.

We at *Paul J Ford and Company* appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Respectfully submitted by:

Nick Parente, E.I. Structural Designer

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information Table 2 - Existing Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided 3.1) Analysis Method 3.2) Assumptions

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)
Table 5 - Tower Components vs. Capacity

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 147.5 ft Monopole tower designed by SUMMIT in September of 1998. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 80 mph with no ice, 37.6 mph with 1 inch ice thickness and 50 mph under service loads.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Flevation	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
		3	alcatel lucent	TD-RRH8x20-25			
147.0	147.0	3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe	1	5/8	-

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
147.0	147.0	3	rfs celwave	APXVSPP18-C-A20 w/ Mount Pipe	3	1-1/4	1
		1	tower mounts	Platform Mount [LP 712-1]			
		3	alcatel lucent	800MHz 2X50W RRH W/FILTER			
145.0	145.0	3	alcatel lucent	PCS 1900MHz 4x45W- 65MHz	-	-	1
		1	tower mounts	Side Arm Mount [SO 102-3]			
		3	antel	BXA-70063-4CF-EDIN-X w/ Mount Pipe			
		1	rfs celwave	DB-T1-6Z-8AB-0Z	1	1-5/8	2
		3	alcatel lucent	RRH2X40-AWS	. '	1-5/6	
132.0	0 134.0	3	antel	BXA-171063-12BF-EDIN-X w/ Mount Pipe			
		3	antel	BXA-171063-8BF-EDIN-2 w/ Mount Pipe			
	3		antel	BXA-70063-6CF-FDIN-2 18 1-		1-5/8	1
	132.0	1	tower mounts	Platform Mount [LP 712-1]			
127.0	129.0	12	decibel	DB844H90E-XY w/ Mount Pipe	12	7/8	3
	127.0	1	tower mounts	Platform Mount [LP 712-1]			
		3	ericsson	RRU-11			
119.0	119.0		raycap	DC6-48-60-18-8F	_	-	1
		1	tower mounts	Pipe Mount [PM 601-3]			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
		1	andrew	SBNH-1D6565C w/ Mount Pipe			
	1 cor	kmw communications	AM-X-CD-14-65-00T-RET w/ Mount Pipe				
117.0	119.0	1	kmw communications	AM-X-CD-16-65-00T-RET w/ Mount Pipe	1 2	3/8 3/4	1
		3	powerwave technologies	7770.00 w/ Mount Pipe	18	1-5/8	
		6	powerwave technologies	LGP21401			
	117.0	1	tower mounts	Platform Mount [LP 712-1]			
107.0	107.0	3	rfs celwave	APXV18-206517S-C	6	1 5/0	1
107.0	107.0	1	tower mounts	Pipe Mount [PM 601-3]	0	1-5/8	'
	50.0	1	symmetricom	58532A			
49.0	49.0	1	tower mounts	Side Arm Mount [SO 701-1]	1	1/2	1

Notes:

- 1) 2) 3)
- Existing Equipment Reserved Equipment Equipment to be Removed

3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

Document	Remarks	Reference	Source					
GEOTECHNICAL REPORTS	FDH, 120604EG1, 8/20/12	1532963	CCISITES					
TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	PJF, 29298-598, 9/15/98	1613614	CCISITES					
TOWER MANUFACTURER DRAWINGS	Summit, 3960, 9/11/98	1613591	CCISITES					
TOWER REINFORCEMENT DESIGN/DRAWINGS/DATA	PJF, 37513-0644, 2/27/13	3667620	CCISITES					

3.1) Analysis Method

tnxTower (version 6.1.3.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) Monopole was reinforced in conformance with the referenced modification drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Paul J Ford and Company should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	147.5 - 108.5	Pole	TP29.41x22x0.25	1	-8.42	1083.24	49.4	Pass
L2	108.5 - 72.25	Pole	TP35.798x28.1975x0.25	2	-13.60	1431.15	88.5	Pass
L3	72.25 - 48	Pole	TP39.9048x34.4429x0.3125	3	-19.19	2041.56	87.3	Pass
L4	48 - 35.75	Pole	TP42.232x39.9048x0.3853	4	-20.73	2265.57	83.9	Pass
L5	35.75 - 0	Pole	TP48.4x40.4641x0.375	5	-31.20	2971.67	84.9	Pass
							Summary	
						Pole (L2)	88.5	Pass
						Rating =	88.5	Pass

Table 5 - Tower Component Stresses vs. Capacity - LC11

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail	
1	Anchor Rods	0	78.5	Pass	
1	Base Plate	0	70.8	Pass	
1	Base Foundation (Steel)	0	46.3	Pass	
1	Base Foundation Soil Interaction	0	58.0	Pass	

Structure Rating (max from all components) = 88.5%
--

Notes:

See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

APPENDIX A TNXTOWER OUTPUT

Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

- 1) Tower is located in Hartford County, Connecticut.
- 2) Basic wind speed of 80 mph.
- 3) Nominal ice thickness of 1.0000 in.
- 4) Ice thickness is considered to increase with height.
- 5) Ice density of 56.00 pcf.
- 6) A wind speed of 38 mph is used in combination with ice.
- 7) Deflections calculated using a wind speed of 50 mph.
- 8) A non-linear (P-delta) analysis was used.
- 9) Pressures are calculated at each section.
- 10) Stress ratio used in pole design is 1.333.
- 11) Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification

- √ Use Code Stress Ratios
- √ Use Code Safety Factors Guys
 - Escalate Ice
 Always Use Max Kz
 Use Special Wind Profile
 Include Bolts In Member Capacity
 Leg Bolts Are At Top Of Section
 Secondary Horizontal Braces Leg
 Use Diamond Inner Bracing (4 Sided)
 Add IBC .6D+W Combination
- Distribute Leg Loads As Uniform Assume Legs Pinned
- √ Assume Rigid Index Plate
- √ Use Clear Špans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension
- √ Bypass Mast Stability Checks
- √ Use Azimuth Dish Coefficients
- √ Project Wind Area of Appurt.
- √ Autocalc Torque Arm Areas
 SR Members Have Cut Ends
 Sort Capacity Reports By Component
 Triangulate Diamond Inner Bracing
 Use TIA-222-G Tension Splice
 Capacity Exemption

Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation

- √ Consider Feedline Torque Include Angle Block Shear Check Poles
- ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets

Tapered Pole Section Geometry

Section	Elevation	Section Length	Splice Length	Number of	Top Diameter	Bottom Diameter	Wall Thickness	Bend Radius	Pole Grade
	ft	ft	ft	Sides	in	in	in	in	
L1	147.5000- 108.5000	39.0000	3.75	18	22.0000	29.4100	0.2500	1.0000	A572-60 (60 ksi)
L2	108.5000- 72.2500	40.0000	4.50	18	28.1975	35.7980	0.2500	1.0000	A607-65 (65 ksi)
L3	72.2500- 48.0000	28.7500	0.00	18	34.4429	39.9048	0.3125	1.2500	A607-65 (65 ksi)
L4	48.0000- 35.7500	12.2500	5.25	18	39.9048	42.2320	0.3852	1.5410	Reinf 56.71 ksi (57 ksi)
L5	35.7500- 0.0000	41.0000		18	40.4641	48.4000	0.3750	1.5000	A607-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia.	Area	1	r	С	I/C	J	It/Q	W	w/t
	in	in²	in⁴	in	in	in ³	in⁴	in²	in	
L1	22.3394	17.2586	1031.4832	7.7212	11.1760	92.2945	2064.3237	8.6310	3.4320	13.728
	29.8637	23.1385	2485.6899	10.3518	14.9403	166.3751	4974.6504	11.5714	4.7362	18.945
L2	29.3560	22.1763	2188.3323	9.9214	14.3243	152.7703	4379.5441	11.0903	4.5228	18.091
	36.3502	28.2073	4503.2898	12.6195	18.1854	247.6324	9012.5051	14.1063	5.8604	23.442
L3	35.8424	33.8531	4982.1874	12.1163	17.4970	284.7450	9970.9304	16.9298	5.5120	17.638

tnxTower Report - version 6.1.3.1

Section	Tip Dia.	Area	1.	r	С	I/C	J	It/Q	W	w/t
	in	in²	in⁴	in	in	in ³	in⁴	in²	in	
	40.5204	39.2706	7777.2418	14.0553	20.2716	383.6517	15564.717 1	19.6390	6.4732	20.714
L4	40.5204	48.3238	9535.0287	14.0294	20.2716	470.3634	19082.603 8	24.1665	6.3452	16.47
	42.8835	51.1695	11320.672 4	14.8556	21.4539	527.6754	22656.240 9	25.5896	6.7548	17.534
L5	42.1202	47.7161	9688.4702	14.2316	20.5558	471.3260	19389.688 8	23.8626	6.4617	17.231
	49.1466	57.1618	16656.270 3	17.0489	24.5872	677.4366	33334.457 4	28.5863	7.8584	20.956

Feed Line/Linear Appurtenances - Entered As Area

Description	Face or	Allow Shield	Component	Placement	Total Number		C_AA_A	Weight
	or Leg	SHEID	Туре	ft	Nulliber		ft²/ft	plf
HB114-1-08U4-M5J(1	C	No	Inside Pole	147.0000 - 0.0000	3	No Ice	0.0000	1.08
1/4")						1/2" Ice	0.0000	1.08
,						1" Ice	0.0000	1.08
						2" Ice	0.0000	1.08
						4" Ice	0.0000	1.08
HB058-M12-	С	No	Inside Pole	147.0000 - 0.0000	1	No Ice	0.0000	0.24
XXXF(5/8")	·				•	1/2" Ice	0.0000	0.24
7000 (6,0)						1" Ice	0.0000	0.24
						2" Ice	0.0000	0.24
						4" lce	0.0000	0.24

LDF7-50A (1-5/8	Α	No	Inside Pole	132.0000 - 0.0000	1	No Ice	0.0000	0.82
FOAM)						1/2" Ice	0.0000	0.82
						1" Ice	0.0000	0.82
						2" Ice	0.0000	0.82
						4" Ice	0.0000	0.82
LDF7-50A (1-5/8	Α	No	Inside Pole	132.0000 - 0.0000	18	No Ice	0.0000	0.82
FOAM)						1/2" Ice	0.0000	0.82
						1" Ice	0.0000	0.82
						2" Ice	0.0000	0.82
						4" Ice	0.0000	0.82

LDF7-50A (1-5/8	В	No	Inside Pole	117.0000 - 0.0000	18	No Ice	0.0000	0.82
FOAM)	_					1/2" Ice	0.0000	0.82
. 3,)						1" lce	0.0000	0.82
						2" lce	0.0000	0.82
						4" lce	0.0000	0.82
WR-VG86ST-BRD	В	No	Inside Pole	117.0000 - 0.0000	2	No Ice	0.0000	0.88
(3/4")	-	140	maide i die	117.0000 - 0.0000	_	1/2" lce	0.0000	0.88
(3/4)						1" Ice	0.0000	0.88
						2" lce	0.0000	0.88
						4" Ice	0.0000	0.88
FB-L98B-002-75000(В	No	Inside Pole	117.0000 - 0.0000	1	No Ice	0.0000	0.06
3/8")	ь	INO	IIISIUE FUIE	117.0000 - 0.0000	ı	1/2" Ice	0.0000	0.06
3/6)						1" Ice	0.0000	0.06
						2" Ice	0.0000	0.06
						4" Ice	0.0000	0.06
***						1 100	0.0000	0.00
LDF7-50A (1-5/8	С	No		107.0000 - 0.0000	1	No Ice	0.1980	0.82
FOAM)			Face)			1/2" Ice	0.2980	2.33
						1" Ice	0.3980	4.46
						2" Ice	0.5980	10.54
						4" Ice	0.9980	30.04
1-5/8 FOAM	С	No	CaAa (Out Of	107.0000 - 0.0000	5	No Ice	0.0000	0.82
			Face)			1/2" Ice	0.0000	2.33
			,			1" Ice	0.0000	4.46
						2" Ice	0.0000	10.54
						4" Ice	0.0000	30.04
***	_		Leath But	40.0000 0.0000		NI. I.	0.0000	0.45
I DE 4 FOA /4 /0 FOA ***								
LDF4-50A (1/2 FOAM)	С	No	Inside Pole	49.0000 - 0.0000	1	No Ice 1/2" Ice	0.0000 0.0000	0.15 0.15

Description	Face or	Allow Shield	Component Type	Placement	Total Number		$C_A A_A$	Weight
	Leg			ft			ft²/ft	plf
						1" Ice	0.0000	0.15
						2" Ice	0.0000	0.15
***						4" Ice	0.0000	0.15
Aero MP3-03	С	No	CaAa (Out Of	49.0000 - 39.0000	1	No Ice	0.2625	0.00
			Face)			1/2" Ice	0.3736	0.00
			,			1" Ice	0.4847	0.00
						2" Ice	0.7069	0.00
						4" Ice	1.1514	0.00

Feed Line/Linear Appurtenances Section Areas

Tower	Tower	Face	A_R	A_F	C_AA_A	C_AA_A	Weight
Sectio	Elevation				In Face	Out Face	•
n	ft		ft²	ft ²	ft ²	ft ²	K
L1	147.5000-	Α	0.000	0.000	0.000	0.000	0.37
	108.5000	В	0.000	0.000	0.000	0.000	0.14
		С	0.000	0.000	0.000	0.000	0.13
L2	108.5000-	Α	0.000	0.000	0.000	0.000	0.56
	72.2500	В	0.000	0.000	0.000	0.000	0.60
		С	0.000	0.000	0.000	6.880	0.30
L3	72.2500-48.0000	Α	0.000	0.000	0.000	0.000	0.38
		В	0.000	0.000	0.000	0.000	0.40
		С	0.000	0.000	0.000	5.064	0.20
L4	48.0000-35.7500	Α	0.000	0.000	0.000	0.000	0.19
		В	0.000	0.000	0.000	0.000	0.20
		С	0.000	0.000	0.000	4.788	0.10
L5	35.7500-0.0000	Α	0.000	0.000	0.000	0.000	0.56
		В	0.000	0.000	0.000	0.000	0.59
		С	0.000	0.000	0.000	7.079	0.31

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower	Tower	Face	lce	A_R	A_F	$C_A A_A$	$C_A A_A$	Weight
Sectio	Elevation	or	Thickness			In Face	Out Face	-
n	ft	Leg	in	ft ²	ft ²	ft ²	f t²	K
L1	147.5000-	Α	1.176	0.000	0.000	0.000	0.000	0.37
	108.5000	В		0.000	0.000	0.000	0.000	0.14
		С		0.000	0.000	0.000	0.000	0.13
L2	108.5000-	Α	1.128	0.000	0.000	0.000	0.000	0.56
	72.2500	В		0.000	0.000	0.000	0.000	0.60
		С		0.000	0.000	0.000	15.053	1.28
L3	72.2500-48.0000	Α	1.074	0.000	0.000	0.000	0.000	0.38
		В		0.000	0.000	0.000	0.000	0.40
		С		0.000	0.000	0.000	10.785	0.85
L4	48.0000-35.7500	Α	1.029	0.000	0.000	0.000	0.000	0.19
		В		0.000	0.000	0.000	0.000	0.20
		С		0.000	0.000	0.000	9.366	0.39
L5	35.7500-0.0000	Α	1.000	0.000	0.000	0.000	0.000	0.56
		В		0.000	0.000	0.000	0.000	0.59
		С		0.000	0.000	0.000	14.435	1.12

Feed Line Center of Pressure

Section	Elevation	CP _X	CPz	CP _X	CPz
				lce	Ice
	ft	in	in	in	in
L1	147.5000-	0.0000	0.0000	0.0000	0.0000
	108.5000				
L2	108.5000-72.2500	-0.2314	0.1336	-0.4417	0.2550
L3	72.2500-48.0000	-0.2551	0.1473	-0.4820	0.2783
L4	48.0000-35.7500	-0.4540	0.2621	-0.7771	0.4487
L5	35.7500-0.0000	-0.2443	0.1410	-0.4547	0.2625

Discrete Tower Loads											
Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustmen t	Placement		C _A A _A Front	C _A A _A Side	Weight		
			ft ft ft	٥	ft		ft ²	ft ²	K		
TD-RRH8x20-25	Α	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.7198 5.0138 5.3165 5.9478 7.3141	1.7027 1.9196 2.1453 2.6224 3.6805	0.07 0.10 0.13 0.20 0.40		
TD-RRH8x20-25	В	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.7198 5.0138 5.3165 5.9478 7.3141	1.7027 1.9196 2.1453 2.6224 3.6805	0.07 0.10 0.13 0.20 0.40		
TD-RRH8x20-25	С	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.7198 5.0138 5.3165 5.9478 7.3141	1.7027 1.9196 2.1453 2.6224 3.6805	0.07 0.10 0.13 0.20 0.40		
APXVTM14-C-120 w/ Mount Pipe	Α	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.1342 7.6618 8.1830 9.2563 11.5262	4.9591 5.7544 6.4723 8.0099 11.4120	0.08 0.13 0.19 0.34 0.75		
APXVTM14-C-120 w/ Mount Pipe	В	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.1342 7.6618 8.1830 9.2563 11.5262	4.9591 5.7544 6.4723 8.0099 11.4120	0.08 0.13 0.19 0.34 0.75		
APXVTM14-C-120 w/ Mount Pipe	С	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.1342 7.6618 8.1830 9.2563 11.5262	4.9591 5.7544 6.4723 8.0099 11.4120	0.08 0.13 0.19 0.34 0.75		
APXVSPP18-C-A20 w/ Mount Pipe	Α	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.4975 9.1490 9.7672 11.0311 13.6786	6.9458 8.1266 9.0212 10.8440 14.8507	0.08 0.15 0.23 0.41 0.91		
APXVSPP18-C-A20 w/ Mount Pipe	В	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.4975 9.1490 9.7672 11.0311 13.6786	6.9458 8.1266 9.0212 10.8440 14.8507	0.08 0.15 0.23 0.41 0.91		
APXVSPP18-C-A20 w/ Mount Pipe	С	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.4975 9.1490 9.7672 11.0311 13.6786	6.9458 8.1266 9.0212 10.8440 14.8507	0.08 0.15 0.23 0.41 0.91		
(2) 6' x 2.375" Pipe Mount	Α	From Face	4.0000 0.00 0.00	0.00	147.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.4250 1.9250 2.2939 3.0596 4.7022	1.4250 1.9250 2.2939 3.0596 4.7022	0.02 0.03 0.05 0.09 0.23		
(2) 6' x 2.375" Pipe Mount	В	From Face	4.0000 0.00	0.00	147.0000	No Ice 1/2"	1.4250 1.9250	1.4250 1.9250	0.02 0.03		

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustmen t	Placement		C _A A _A Front	C _A A _A Side	Weight
	_		Vert		. .		r.2	e-2	14
			ft ft	۰	ft		ft ²	ft ²	K
			ft			laa	2 2020	2 2020	0.05
			0.00			Ice 1" Ice	2.2939 3.0596	2.2939 3.0596	0.05 0.09
						2" Ice	4.7022	4.7022	0.23
						4" Ice			
(3) 6' x 2.375" Pipe Mount	С	From Face	4.0000	0.00	147.0000	No Ice	1.4250	1.4250	0.02
			0.00			1/2''	1.9250	1.9250	0.03
			0.00			Ice 1" Ice	2.2939 3.0596	2.2939 3.0596	0.05 0.09
						2" Ice	3.0596 4.7022	3.0596 4.7022	0.09
						4" Ice	4.7022	4.7022	0.25
Platform Mount [LP 712-1]	С	None		0.00	147.0000	No Ice	24.5300	24.5300	1.34
						1/2''	29.9400	29.9400	1.65
						Ice	35.3500	35.3500	1.96
						1" Ice	46.1700	46.1700	2.58
						2" lce 4" lce	67.8100	67.8100	3.82
*** PCS 1900MHz 4x45W-	Α	From Face	1.0000	0.00	145.0000	No Ice	2.7087	2.6111	0.06
65MHz			0.00			1/2"	2.9477	2.8475	80.0
			0.00			Ice	3.1953	3.0925	0.11
						1" Ice	3.7164	3.6084	0.17
						2" Ice 4" Ice	4.8623	4.7439	0.35
PCS 1900MHz 4x45W-	В	From Face	1.0000	0.00	145.0000	No Ice	2.7087	2.6111	0.06
65MHz	Ь	1 TOTT I ACC	0.00	0.00	143.0000	1/2"	2.9477	2.8475	0.08
55 <u>-</u>			0.00			lce	3.1953	3.0925	0.11
						1" Ice	3.7164	3.6084	0.17
						2" Ice 4" Ice	4.8623	4.7439	0.35
PCS 1900MHz 4x45W-	С	From Face	1.0000	0.00	145.0000	No Ice	2.7087	2.6111	0.06
65MHz			0.00			1/2''	2.9477	2.8475	80.0
			0.00			Ice	3.1953	3.0925	0.11
						1" Ice	3.7164	3.6084	0.17
						2" Ice 4" Ice	4.8623	4.7439	0.35
800MHz 2X50W RRH	Α	From Face	1.0000	0.00	145.0000	No Ice	2.4014	2.2536	0.06
W/FILTER			0.00			1/2''	2.6131	2.4602	0.09
			0.00			Ice	2.8335	2.6753	0.11
						1" Ice 2" Ice	3.3002 4.3372	3.1316 4.1479	0.17 0.34
						4" Ice	4.5572	4.1473	0.54
800MHz 2X50W RRH	В	From Face	1.0000	0.00	145.0000	No Ice	2.4014	2.2536	0.06
W/FILTER			0.00			1/2''	2.6131	2.4602	0.09
			0.00			Ice	2.8335	2.6753	0.11
						1" Ice 2" Ice	3.3002	3.1316 4.1479	0.17
						4" Ice	4.3372	4.14/3	0.34
800MHz 2X50W RRH	С	From Face	1.0000	0.00	145.0000	No Ice	2.4014	2.2536	0.06
W/FILTER			0.00			1/2"	2.6131	2.4602	0.09
			0.00			Ice	2.8335	2.6753	0.11
						1" Ice	3.3002	3.1316	0.17
						2" Ice 4" Ice	4.3372	4.1479	0.34
Side Arm Mount [SO 102-	С	None		0.00	145.0000	No Ice	3.0000	3.0000	0.08
3]	•			0.00		1/2"	3.4800	3.4800	0.11
•						Ice	3.9600	3.9600	0.14
						1" Ice	4.9200	4.9200	0.20
						2" Ice 4" Ice	6.8400	6.8400	0.32
***						4 108			

BXA-70063-4CF-EDIN-X	Α	From Face	4.0000	0.00	132.0000	No Ice	5.3988	3.6927	0.03
								-	

			Lateral Vert	t					
			ft ft ft	٥	ft		ft ²	ft ²	K
w/ Mount Pipe			0.00			1/2''	5.8435	4.2947	0.07
			2.00			Ice	6.2986	4.9133	0.12
						1" Ice	7.2405	6.2583	0.23
						2" Ice 4" Ice	9.2612	9.2851	0.58
BXA-70063-4CF-EDIN-X	В	From Face	4.0000	0.00	132.0000	No Ice	5.3988	3.6927	0.03
w/ Mount Pipe			0.00			1/2''	5.8435	4.2947	0.07
			2.00			Ice	6.2986	4.9133	0.12
						1" Ice	7.2405	6.2583	0.23
DV4 70000 405 FBIN V	•		4.0000		400 0000	2" Ice 4" Ice	9.2612	9.2851	0.58
BXA-70063-4CF-EDIN-X	С	From Face	4.0000	0.00	132.0000	No Ice	5.3988	3.6927	0.03
w/ Mount Pipe			0.00 2.00			1/2'' Ice	5.8435 6.2986	4.2947 4.9133	0.07 0.12
			2.00			1" Ice	7.2405	6.2583	0.12
						2" Ice	9.2612	9.2851	0.58
						4" Ice	5.2012	3.2031	0.50
BXA-171063-12BF-EDIN-X	Α	From Face	4.0000	0.00	132.0000	No Ice	5.0373	5.2974	0.04
w/ Mount Pipe			0.00			1/2"	5.5919	6.4695	0.08
•			2.00			Ice	6.1129	7.3603	0.14
						1" Ice	7.1769	9.1623	0.27
						2" Ice 4" Ice	9.4492	12.9662	0.68
BXA-171063-12BF-EDIN-X	В	From Face	4.0000	0.00	132.0000	No Ice	5.0373	5.2974	0.04
w/ Mount Pipe			0.00			1/2''	5.5919	6.4695	0.08
			2.00			Ice	6.1129	7.3603	0.14
						1" Ice	7.1769	9.1623	0.27
DV4 474000 40DE EDIN V	•		4.0000		400 0000	2" Ice 4" Ice	9.4492	12.9662	0.68
BXA-171063-12BF-EDIN-X w/ Mount Pipe	С	From Face	4.0000 0.00	0.00	132.0000	No Ice 1/2"	5.0373 5.5919	5.2974 6.4695	0.04 0.08
w/ Mount Fipe			2.00			Ice	6.1129	7.3603	0.08
			2.00			1" Ice	7.1769	9.1623	0.27
						2" Ice 4" Ice	9.4492	12.9662	0.68
RRH2X40-AWS	Α	From Face	4.0000	0.00	132.0000	No Ice	2.9764	1.5960	0.04
			0.00			1/2''	3.2363	1.8239	0.06
			2.00			Ice	3.5048	2.0605	0.08
						1" Ice	4.0678	2.5596	0.14
DD1101/40 AMA	_		4.0000		400 0000	2" Ice 4" Ice	5.2975	3.6614	0.29
RRH2X40-AWS	В	From Face	4.0000	0.00	132.0000	No Ice	2.9764	1.5960	0.04
			0.00 2.00			1/2'' Ice	3.2363 3.5048	1.8239 2.0605	0.06 0.08
			2.00			1" Ice	4.0678	2.5596	0.14
						2" Ice	5.2975	3.6614	0.29
						4" Ice			
RRH2X40-AWS	С	From Face	4.0000	0.00	132.0000	No Ice	2.9764	1.5960	0.04
			0.00			1/2''	3.2363	1.8239	0.06
			2.00			Ice	3.5048	2.0605	0.08
						1" Ice	4.0678	2.5596	0.14
						2" Ice 4" Ice	5.2975	3.6614	0.29
DB-T1-6Z-8AB-0Z	Α	From Face	4.0000	0.00	132.0000	No Ice	5.6000	2.3333	0.04
			0.00			1/2''	5.9154	2.5580	0.08
			2.00			Ice 1" Ice	6.2395 6.9136	2.7914 3.2840	0.12 0.21
						2" Ice	8.3654	4.3728	0.45
						4" Ice	0.0004	1.0720	0.40
BXA-171063-8BF-EDIN-2	Α	From Face	4.0000	0.00	132.0000	No Ice	3.1789	3.3530	0.03
w/ Mount Pipe			0.00			1/2''	3.5550	3.9709	0.06
			2.00			Ice	3.9637	4.5951	0.10
						1" Ice 2" Ice	4.8533 6.7671	5.8933 8.8855	0.19 0.49
						4" Ice	0.7071	0.0000	0.43

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustmen t	Placement		C _A A _A Front	C _A A _A Side	Weight
			Vert ft ft ft	۰	ft		ft²	ft ²	K
BXA-171063-8BF-EDIN-2 w/ Mount Pipe	В	From Face	4.0000 0.00 2.00	0.00	132.0000	No Ice 1/2" Ice	3.1789 3.5550 3.9637	3.3530 3.9709 4.5951	0.03 0.06 0.10
						1" Ice 2" Ice 4" Ice	4.8533 6.7671	5.8933 8.8855	0.19 0.49
BXA-171063-8BF-EDIN-2 w/ Mount Pipe	С	From Face	4.0000 0.00	0.00	132.0000	No Ice 1/2"	3.1789 3.5550	3.3530 3.9709	0.03 0.06
			2.00			Ice	3.9637	4.5951	0.10
						1" Ice 2" Ice 4" Ice	4.8533 6.7671	5.8933 8.8855	0.19 0.49
BXA-70063-6CF-EDIN-2	Α	From Face	4.0000	0.00	132.0000	No Ice	7.9686	5.8008	0.04
w/ Mount Pipe			0.00			1/2''	8.6091	6.9529	0.10
			2.00			lce	9.2158	7.8191	0.17
						1" Ice 2" Ice 4" Ice	10.4591 13.0655	9.6015 13.3662	0.34 0.80
BXA-70063-6CF-EDIN-2	В	From Face	4.0000	0.00	132.0000	No Ice	7.9686	5.8008	0.04
w/ Mount Pipe			0.00			1/2''	8.6091	6.9529	0.10
			2.00			Ice 1" Ice	9.2158 10.4591	7.8191 9.6015	0.17 0.34
						2" lce 4" lce	13.0655	13.3662	0.80
BXA-70063-6CF-EDIN-2	С	From Face	4.0000	0.00	132.0000	No Ice	7.9686	5.8008	0.04
w/ Mount Pipe			0.00			1/2''	8.6091	6.9529	0.10
			2.00			Ice 1" Ice	9.2158 10.4591	7.8191 9.6015	0.17 0.34
						2" lce 4" lce	13.0655	13.3662	0.80
Platform Mount [LP 712-1]	С	None		0.00	132.0000	No Ice	24.5300	24.5300	1.34
						1/2''	29.9400	29.9400	1.65
						Ice	35.3500	35.3500	1.96
						1" Ice 2" Ice 4" Ice	46.1700 67.8100	46.1700 67.8100	2.58 3.82

7770.00 w/ Mount Pipe	Α	From Face	4.0000	0.00	117.0000	No Ice	6.1194	4.2543	0.06
			0.00 2.00			1/2" Ice	6.6258 7.1283	5.0137 5.7109	0.10 0.16
			2.00			1" Ice	8.1643	7.1553	0.10
						2" Ice 4" Ice	10.3599	10.4117	0.66
7770.00 w/ Mount Pipe	В	From Face	4.0000	0.00	117.0000	No Ice	6.1194	4.2543	0.06
			0.00			1/2"	6.6258	5.0137	0.10
			2.00			Ice 1" Ice	7.1283 8.1643	5.7109 7.1553	0.16 0.29
						2" lce 4" lce	10.3599	10.4117	0.66
7770.00 w/ Mount Pipe	С	From Face	4.0000	0.00	117.0000	No Ice	6.1194	4.2543	0.06
			0.00			1/2''	6.6258	5.0137	0.10
			2.00			Ice	7.1283	5.7109	0.16
						1" Ice 2" Ice 4" Ice	8.1643 10.3599	7.1553 10.4117	0.29 0.66
SBNH-1D6565C w/ Mount	Α	From Face	4.0000	0.00	117.0000	No Ice	11.5561	9.7151	0.10
Pipe			0.00			1/2"	12.2227	11.1857	0.19
			2.00			Ice	12.8929	12.5942	0.28
						1" Ice	14.2911	14.8689	0.51
AM-X-CD-14-65-00T-RET	В	From Face	4.0000	0.00	117.0000	2" Ice 4" Ice No Ice	17.4280 5.7442	19.6184 4.0153	1.15 0.03
w/ Mount Pipe	ی	. Tom Face	0.00	0.00	117.0000	1/2"	6.1977	4.6330	0.03
			2.00			Ice	6.6606	5.2765	0.13

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustmen t	Placement		C _A A _A Front	C _A A _A Side	Weight
			ft ft ft	۰	ft		ft ²	ft ²	K
						1" Ice 2" Ice 4" Ice	7.6178 9.6678	6.6779 9.7441	0.25 0.61
AM-X-CD-16-65-00T-RET w/ Mount Pipe	С	From Face	4.0000 0.00 2.00	0.00	117.0000	No Ice 1/2" Ice 1" Ice 2" Ice	8.4975 9.1490 9.7672 11.0311 13.6786	6.3042 7.4790 8.3676 10.1785	0.07 0.14 0.21 0.38 0.87
(2) LGP21401	Α	From Face	4.0000 0.00	0.00	117.0000	4" Ice No Ice 1/2"	1.2880 1.4453	14.0237 0.2326 0.3134	0.01 0.02
			2.00			Ice 1" Ice 2" Ice 4" Ice	1.6112 1.9690 2.7882	0.4028 0.6076 1.1210	0.03 0.05 0.14
(2) LGP21401	В	From Face	4.0000 0.00 2.00	0.00	117.0000	No Ice 1/2" Ice	1.2880 1.4453 1.6112	0.2326 0.3134 0.4028	0.01 0.02 0.03
(2) I CD24404	С	From Face	4.0000	0.00	117.0000	1" Ice 2" Ice 4" Ice	1.9690 2.7882 1.2880	0.6076 1.1210 0.2326	0.05 0.14 0.01
(2) LGP21401	C	From Face	0.00 2.00	0.00	117.0000	No Ice 1/2" Ice 1" Ice 2" Ice	1.4453 1.6112 1.9690 2.7882	0.2326 0.3134 0.4028 0.6076 1.1210	0.01 0.02 0.03 0.05 0.14
(2) 6' x 2.375" Pipe Mount	Α	From Face	4.0000 0.00 0.00	0.00	117.0000	4" Ice No Ice 1/2" Ice 1" Ice 2" Ice	1.4250 1.9250 2.2939 3.0596 4.7022	1.4250 1.9250 2.2939 3.0596 4.7022	0.02 0.03 0.05 0.09 0.23
(2) 6' x 2.375" Pipe Mount	В	From Face	4.0000 0.00 0.00	0.00	117.0000	4" Ice No Ice 1/2" Ice	1.4250 1.9250 2.2939	1.4250 1.9250 2.2939	0.02 0.03 0.05
						1" Ice 2" Ice 4" Ice	3.0596 4.7022	3.0596 4.7022	0.09 0.23
(2) 6' x 2.375" Pipe Mount	С	From Face	4.0000 0.00 0.00	0.00	117.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.4250 1.9250 2.2939 3.0596 4.7022	1.4250 1.9250 2.2939 3.0596 4.7022	0.02 0.03 0.05 0.09 0.23
Platform Mount [LP 712-1]	С	None		0.00	117.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	24.5300 29.9400 35.3500 46.1700 67.8100	24.5300 29.9400 35.3500 46.1700 67.8100	1.34 1.65 1.96 2.58 3.82
RRU-11	Α	From Face	1.0000 0.00 0.00	0.00	119.0000	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	1.9116 2.1019 2.3009 2.7248 3.6763	1.4717 1.6452 1.8274 2.2176 3.1016	0.04 0.06 0.08 0.12 0.25
RRU-11	В	From Face	1.0000 0.00 0.00	0.00	119.0000	No Ice 1/2" Ice 1" Ice 2" Ice	1.9116 2.1019 2.3009 2.7248 3.6763	1.4717 1.6452 1.8274 2.2176 3.1016	0.04 0.06 0.08 0.12 0.25
RRU-11	С	From Face	1.0000	0.00	119.0000	4" Ice No Ice	1.9116	1.4717	0.04

tnxTower Report - version 6.1.3.1

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustmen t	Placement		C _A A _A Front	C _A A _A Side	Weight
			ft ft ft	۰	ft		ft ²	ft ²	K
			0.00			1/2''	2.1019	1.6452	0.06
			0.00			Ice	2.3009	1.8274	0.08
						1" Ice 2" Ice 4" Ice	2.7248 3.6763	2.2176 3.1016	0.12 0.25
DC6-48-60-18-8F	Α	From Face	1.0000	0.00	119.0000	No Ice	2.5667	2.5667	0.02
			0.00			1/2"	2.7978	2.7978	0.04
			0.00			Ice	3.0377	3.0377	0.07
						1" Ice	3.5432	3.5432	0.13
						2" Ice	4.6580	4.6580	0.30
						4" Ice			
Pipe Mount [PM 601-3]	С	None		0.00	119.0000	No Ice	4.3900	4.3900	0.20
						1/2''	5.4800	5.4800	0.24
						Ice	6.5700	6.5700	0.28
						1" Ice 2" Ice	8.7500 13.1100	8.7500 13.1100	0.36 0.53
***						4" Ice	13.1100	13.1100	0.55
APXV18-206517S-C	Α	From Face	1.0000	0.00	107.0000	No Ice	5.1667	3.0375	0.03
74 XV 10 200017 0 0	,,	1 10111 1 400	0.00	0.00	107.0000	1/2"	5.6182	3.4693	0.05
			0.00			Ice	6.0772	3.9086	0.09
			0.00			1" Ice	7.0173	4.8093	0.17
						2" Ice	9.1225	6.6995	0.40
						4" Ice			
APXV18-206517S-C	В	From Face	1.0000	0.00	107.0000	No Ice	5.1667	3.0375	0.03
			0.00			1/2''	5.6182	3.4693	0.05
			0.00			Ice	6.0772	3.9086	0.09
						1" Ice	7.0173	4.8093	0.17
						2" Ice 4" Ice	9.1225	6.6995	0.40
APXV18-206517S-C	С	From Face	1.0000	0.00	107.0000	No Ice	5.1667	3.0375	0.03
			0.00			1/2"	5.6182	3.4693	0.05
			0.00			Ice	6.0772	3.9086	0.09
						1" Ice	7.0173	4.8093	0.17
						2" Ice 4" Ice	9.1225	6.6995	0.40
Pipe Mount [PM 601-3]	С	None		0.00	107.0000	No Ice	4.3900	4.3900	0.20
Tipe Modrit [TiM 001-5]	C	None		0.00	107.0000	1/2"	5.4800	5.4800	0.24
						Ice	6.5700	6.5700	0.28
						1" Ice	8.7500	8.7500	0.36
						2" Ice	13.1100	13.1100	0.53
***						4" Ice			0.00
58532A	Α	From Face	2.0000	0.00	49.0000	No Ice	0.2209	0.2209	0.00
			0.00	2.00		1/2"	0.2897	0.2897	0.00
			1.00			Ice	0.3672	0.3672	0.01
						1" Ice	0.5481	0.5481	0.02
						2" Ice 4" Ice	1.0137	1.0137	0.06
Side Arm Mount [SO 701-	Α	From Face	1.0000	0.00	49.0000	No Ice	0.8500	1.6700	0.07
1]	, ,	. 10 1 400	0.00	0.00	10.0000	1/2"	1.1400	2.3400	0.08
٠1			0.00			Ice	1.4300	3.0100	0.09
			3.00			1" Ice	2.0100	4.3500	0.12
						2" Ice	3.1700	7.0300	0.18
						4" Ice			-

Tower Pressures - No Ice

 $G_H = 1.690$

Section	Z	K_Z	q_z	A_G	F	A_F	A_R	A_{leg}	Leg	$C_A A_A$	C_AA_A
Elevation					а				%	In	Out
					С					Face	Face
ft	ft		psf	ft ²	е	ft ²	f t²	ft ²		f t²	ft ²
L1 147.5000-	127.2746	1.471	24.07	83.541	Α	0.000	83.541	83.541	100.00	0.000	0.000
108.5000					В	0.000	83.541		100.00	0.000	0.000
					С	0.000	83.541		100.00	0.000	0.000
L2 108.5000-	89.9920	1.332	21.78	97.736	Α	0.000	97.736	97.736	100.00	0.000	0.000
72.2500					В	0.000	97.736		100.00	0.000	0.000
					С	0.000	97.736		100.00	0.000	6.880
L3 72.2500-	59.8774	1.186	19.42	75.986	Α	0.000	75.986	75.986	100.00	0.000	0.000
48.0000					В	0.000	75.986		100.00	0.000	0.000
					С	0.000	75.986		100.00	0.000	5.064
L4 48.0000-	41.8172	1.07	17.53	41.924	Α	0.000	41.924	41.924	100.00	0.000	0.000
35.7500					В	0.000	41.924		100.00	0.000	0.000
					С	0.000	41.924		100.00	0.000	4.788
L5 35.7500-	17.4163	1	16.38	133.88	Α	0.000	133.884	133.884	100.00	0.000	0.000
0.0000				4	В	0.000	133.884		100.00	0.000	0.000
					С	0.000	133.884		100.00	0.000	7.079

Tower Pressure - With Ice

 $G_H = 1.690$

Section	Z	Κz	qz	t∠	A_{G}	F	A_F	A_R	A_{leg}	Leg	$C_A A_A$	$C_A A_A$
Elevation						а				%	In	Out
						С			0		Face	Face
ft	ft		psf	in	ft ²	е	ft ²	ft ²	ft ²		ft [∠]	ft ²
L1 147.5000-	127.2746	1.471	5.32	1.1758	91.184	Α	0.000	91.184	91.184	100.00	0.000	0.000
108.5000						В	0.000	91.184		100.00	0.000	0.000
						С	0.000	91.184		100.00	0.000	0.000
L2 108.5000-	89.9920	1.332	4.81	1.1279	104.840	Α	0.000	104.840	104.840	100.00	0.000	0.000
72.2500						В	0.000	104.840		100.00	0.000	0.000
						С	0.000	104.840		100.00	0.000	15.053
L3 72.2500-	59.8774	1.186	4.29	1.0741	80.545	Α	0.000	80.545	80.545	100.00	0.000	0.000
48.0000						В	0.000	80.545		100.00	0.000	0.000
						С	0.000	80.545		100.00	0.000	10.785
L4 48.0000-	41.8172	1.07	3.87	1.0288	44.024	Α	0.000	44.024	44.024	100.00	0.000	0.000
35.7500						В	0.000	44.024		100.00	0.000	0.000
						С	0.000	44.024		100.00	0.000	9.366
L5 35.7500-	17.4163	1	3.62	1.0000	140.014	Α	0.000	140.014	140.014	100.00	0.000	0.000
0.0000						В	0.000	140.014		100.00	0.000	0.000
						С	0.000	140.014		100.00	0.000	14.435

Tower Pressure - Service

 $G_H = 1.690$

Section	Z	Kz	q_z	A_{G}	F	A_F	A_R	A_{leg}	Leg	C_AA_A	C_AA_A
Elevation					а				%	In	Out
					С					Face	Face
ft	ft		psf	ft ²	е	ft ²	ft²	ft ²		ft ²	ft ²
L1 147.5000-	127.2746	1.471	9.40	83.541	Α	0.000	83.541	83.541	100.00	0.000	0.000
108.5000					В	0.000	83.541		100.00	0.000	0.000
					С	0.000	83.541		100.00	0.000	0.000
L2 108.5000-	89.9920	1.332	8.51	97.736	Α	0.000	97.736	97.736	100.00	0.000	0.000
72.2500					В	0.000	97.736		100.00	0.000	0.000
					С	0.000	97.736		100.00	0.000	6.880
L3 72.2500-	59.8774	1.186	7.59	75.986	Α	0.000	75.986	75.986	100.00	0.000	0.000
48.0000					В	0.000	75.986		100.00	0.000	0.000
					С	0.000	75.986		100.00	0.000	5.064
L4 48.0000-	41.8172	1.07	6.85	41.924	Α	0.000	41.924	41.924	100.00	0.000	0.000
35.7500					В	0.000	41.924		100.00	0.000	0.000
					С	0.000	41.924		100.00	0.000	4.788
L5 35.7500-	17.4163	1	6.40	133.88	Α	0.000	133.884	133.884	100.00	0.000	0.000
0.0000				4	В	0.000	133.884		100.00	0.000	0.000
					С	0.000	133.884		100.00	0.000	7.079

Load Combinations

Comb.	Description	
No.		
1	Dead Only	
2	Dead+Wind 0 deg - No Ice	
3	Dead+Wind 30 deg - No Ice	
4	Dead+Wind 60 deg - No Ice	
5	Dead+Wind 90 deg - No Ice	
6	Dead+Wind 120 deg - No Ice	
7	Dead+Wind 150 deg - No Ice	
8	Dead+Wind 180 deg - No Ice	
9	Dead+Wind 210 deg - No Ice	
10	Dead+Wind 240 deg - No Ice	
11	Dead+Wind 270 deg - No Ice	
12	Dead+Wind 300 deg - No Ice	
13	Dead+Wind 330 deg - No Ice	
14	Dead+lce	
15	Dead+Wind 0 deg+lce	
16	Dead+Wind 30 deg+lce	
17	Dead+Wind 60 deg+lce	
18	Dead+Wind 90 deg+lce	
19	Dead+Wind 120 deg+lce	
20	Dead+Wind 150 deg+lce	
21	Dead+Wind 180 deg+lce	
22	Dead+Wind 210 deg+lce	
23	Dead+Wind 240 deg+lce	
24	Dead+Wind 270 deg+lce	
25	Dead+Wind 300 deg+lce	
26	Dead+Wind 330 deg+lce	
27	Dead+Wind 0 deg - Service	
28	Dead+Wind 30 deg - Service	
29	Dead+Wind 60 deg - Service	
30	Dead+Wind 90 deg - Service	
31	Dead+Wind 120 deg - Service	
32	Dead+Wind 150 deg - Service	
33	Dead+Wind 180 deg - Service	
34	Dead+Wind 210 deg - Service	
35	Dead+Wind 240 deg - Service	
36	Dead+Wind 270 deg - Service	
37	Dead+Wind 300 deg - Service	
38	Dead+Wind 330 deg - Service	

Maximum Member Forces

Sectio	Elevation	Component	Condition	Gov.	Force	Major Axis	Minor Axis
n No.	ft	Type		Load Comb.	К	Moment kip-ft	Moment kip-ft
L1	147.5 - 108.5	Pole	Max Tension	24	0.00	-0.00	0.00
			Max. Compression	14	-18.39	1.62	0.11
			Max. Mx	11	-8.42	306.85	1.34
			Max. My	8	-8.43	-0.90	-304.91
			Max. Vy	11	-14.64	306.85	1.34
			Max. Vx	8	14.59	-0.90	-304.91
			Max. Torque	8			-1.60
L2	108.5 - 72.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-26.27	2.99	-0.62
			Max. Mx	11	-13.60	891.38	3.50
			Max. My	8	-13.61	-2.90	-887.44
			Max. Vy	11	-17.80	891.38	3.50
			Max. Vx	8	17.74	-2.90	-887.44
			Max. Torque	8			-1.64
L3	72.25 - 48	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-33.99	4.56	-1.22
			Max. Mx	11	-19.19	1432.25	5.28
			Max. My	8	-19.19	-4.34	-1426.46

Sectio	Elevation	Component	Condition	Gov.	Force	Major Axis	Minor Axis
n	ft	Type		Load		Moment	Moment
No.				Comb.	K	kip-ft	kip-ft
			Max. Vy	11	-19.81	1432.25	5.28
			Max. Vx	8	19.77	-4.34	-1426.46
			Max. Torque	8			-1.82
L4	48 - 35.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-35.98	4.85	-1.39
			Max. Mx	11	-20.74	1572.54	5.61
			Max. My	8	-20.74	-4.65	-1566.44
			Max. Vy	11	-20.28	1572.54	5.61
			Max. Vx	8	20.24	-4.65	-1566.44
			Max. Torque	8			-1.84
L5	35.75 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-49.41	6.68	-2.44
			Max. Mx	11	-31.20	2455.63	7.50
			Max. My	8	-31.20	-6.39	-2447.77
			Max. Vy	11	-22.70	2455.63	7.50
			Max. Vx	8	22.66	-6.39	-2447.77
			Max. Torque	8			-1.91

Maximum Reactions

Location	Condition	Gov.	Vertical	Horizontal, X	Horizontal, Z
		Load	K	K	K
		Comb.			
Pole	Max. Vert	24	49.41	6.34	0.00
	Max. H _x	11	31.22	22.67	0.05
	Max. H _z	2	31.22	0.05	22.64
	Max. M _x	2	2447.07	0.05	22.64
	Max. M _z	5	2452.69	-22.67	-0.05
	Max. Torsion	2	1.90	0.05	22.64
	Min. Vert	1	31.22	0.00	0.00
	Min. H _x	5	31.22	-22.67	-0.05
	Min. H _z	8	31.22	-0.05	-22.64
	Min. M _x	8	-2447.77	-0.05	-22.64
	Min. M _z	11	-2455.63	22.67	0.05
	Min. Torsion	8	-1.91	-0.05	-22.64

Tower Mast Reaction Summary

Load Combination	Vertical	Shear _x	Shearz	Overturning Moment, M _x	Overturning Moment, M _z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	31.22	0.00	0.00	0.34	1.41	0.00
Dead+Wind 0 deg - No Ice	31.22	-0.05	-22.64	-2447.07	9.32	-1.90
Dead+Wind 30 deg - No Ice	31.22	11.29	-19.58	-2115.26	-1218.84	-1.72
Dead+Wind 60 deg - No Ice	31.22	19.61	-11.27	-1216.55	-2120.01	-1.08
Dead+Wind 90 deg - No Ice	31.22	22.67	0.05	8.21	-2452.69	-0.15
Dead+Wind 120 deg - No Ice	31.22	19.66	11.36	1230.84	-2127.81	0.82
Dead+Wind 150 deg - No Ice	31.22	11.38	19.63	2123.77	-1232.42	1.58
Dead+Wind 180 deg - No Ice	31.22	0.05	22.64	2447.77	-6.39	1.91
Dead+Wind 210 deg - No Ice	31.22	-11.29	19.58	2115.97	1221.77	1.72
Dead+Wind 240 deg - No Ice	31.22	-19.61	11.27	1217.27	2122.94	1.08
Dead+Wind 270 deg - No Ice	31.22	-22.67	-0.05	-7.50	2455.63	0.14
Dead+Wind 300 deg - No Ice	31.22	-19.66	-11.36	-1230.14	2130.75	-0.83
Dead+Wind 330 deg - No Ice	31.22	-11.38	-19.63	-2123.08	1235.35	-1.57
Dead+Ice	49.41	-0.00	0.00	2.44	6.68	-0.00
Dead+Wind 0 deg+Ice	49.41	-0.00	-6.34	-724.53	7.96	-0.58
Dead+Wind 30 deg+lce	49.41	3.17	-5.49	-626.56	-356.41	-0.50
Dead+Wind 60 deg+lce	49.41	5.49	-3.16	-360.01	-623.46	-0.28
Dead+Wind 90 deg+lce	49.41	6.34	0.00	3.66	-721.61	0.01
Dead+Wind 120 deg+lce	49.41	5.50	3.17	367.02	-624.65	0.30
Dead+Wind 150 deg+lce	49.41	3.18	5.49	632.70	-358.47	0.51
Dead+Wind 180 deg+lce	49.41	0.00	6.34	729.47	5.58	0.58
Dead+Wind 210 deg+lce	49.41	-3.17	5.49	631.51	369.94	0.50
Dead+Wind 240 deg+lce	49.41	-5.49	3.16	364.96	637.00	0.28

tnxTower Report - version 6.1.3.1

Load Combination	Vertical	Shear _x	Shearz	Overturning Moment, M _x	Overturning Moment, Mz	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead+Wind 270 deg+lce	49.41	-6.34	-0.00	1.29	735.14	-0.01
Dead+Wind 300 deg+lce	49.41	-5.50	-3.17	-362.07	638.19	-0.30
Dead+Wind 330 deg+lce	49.41	-3.18	-5.49	-627.75	372.01	-0.51
Dead+Wind 0 deg - Service	31.22	-0.02	-8.84	-957.01	4.55	-0.75
Dead+Wind 30 deg - Service	31.22	4.41	-7.65	-827.21	-475.87	-0.68
Dead+Wind 60 deg - Service	31.22	7.66	-4.40	-475.67	-828.38	-0.43
Dead+Wind 90 deg - Service	31.22	8.86	0.02	3.43	-958.53	-0.06
Dead+Wind 120 deg - Service	31.22	7.68	4.44	481.69	-831.45	0.33
Dead+Wind 150 deg - Service	31.22	4.45	7.67	830.99	-481.19	0.62
Dead+Wind 180 deg - Service	31.22	0.02	8.84	957.71	-1.59	0.75
Dead+Wind 210 deg - Service	31.22	-4.41	7.65	827.92	478.83	0.68
Dead+Wind 240 deg - Service	31.22	-7.66	4.40	476.37	831.34	0.42
Dead+Wind 270 deg - Service	31.22	-8.86	-0.02	-2.72	961.49	0.06
Dead+Wind 300 deg - Service	31.22	-7.68	-4.44	-480.99	834.41	-0.33
Dead+Wind 330 deg - Service	31.22	-4.45	-7.67	-830.29	484.15	-0.62

Solution Summary

	Sun	n of Applied Force	es		Sum of Reactio	ns	
Load	PX	PY	PZ	PX	PY	PZ	% Error
Comb.	K	K	K	K	K	K	
1	0.00	-31.22	0.00	0.00	31.22	0.00	0.000%
2	-0.05	-31.22	-22.64	0.05	31.22	22.64	0.000%
3	11.29	-31.22	-19.58	-11.29	31.22	19.58	0.000%
4	19.61	-31.22	-11.27	-19.61	31.22	11.27	0.000%
5	22.67	-31.22	0.05	-22.67	31.22	-0.05	0.000%
6	19.66	-31.22	11.36	-19.66	31.22	-11.36	0.000%
7	11.38	-31.22	19.63	-11.38	31.22	-19.63	0.000%
8	0.05	-31.22	22.64	-0.05	31.22	-22.64	0.000%
9	-11.29	-31.22	19.58	11.29	31.22	-19.58	0.000%
10	-19.61	-31.22	11.27	19.61	31.22	-11.27	0.000%
11	-22.67	-31.22	-0.05	22.67	31.22	0.05	0.000%
12	-19.66	-31.22	-11.36	19.66	31.22	11.36	0.000%
13	-11.38	-31.22	-19.63	11.38	31.22	19.63	0.000%
14	0.00	-49.41	0.00	0.00	49.41	-0.00	0.000%
15	-0.00	-49.41	-6.34	0.00	49.41	6.34	0.000%
16	3.17	-49.41	-5.49	-3.17	49.41	5.49	0.000%
17	5.49	-49.41	-3.16	-5.49	49.41	3.16	0.000%
18	6.34	-49.41	0.00	-6.34	49.41	-0.00	0.000%
19	5.50	-49.41	3.17	-5.50	49.41	-3.17	0.000%
20	3.18	-49.41	5.49	-3.18	49.41	-5.49	0.000%
21	0.00	-49.41	6.34	-0.00	49.41	-6.34	0.000%
22	-3.17	-49.41	5.49	3.17	49.41	-5.49	0.000%
23	-5.49	-49.41	3.16	5.49	49.41	-3.16	0.000%
24	-6.34	-49.41	-0.00	6.34	49.41	0.00	0.000%
25	-5.50	-49.41	-3.17	5.50	49.41	3.17	0.000%
26	-3.18	-49.41	-5.49	3.18	49.41	5.49	0.000%
27	-0.02	-31.22	-8.84	0.02	31.22	8.84	0.000%
28	4.41	-31.22	-7.65	-4.41	31.22	7.65	0.000%
29	7.66	-31.22	-4.40	-7.66	31.22	4.40	0.000%
30	8.86	-31.22	0.02	-8.86	31.22	-0.02	0.000%
31	7.68	-31.22	4.44	-7.68	31.22	-4.44	0.000%
32	4.45	-31.22	7.67	-4.45	31.22	-7.67	0.000%
33	0.02	-31.22	8.84	-0.02	31.22	-8.84	0.000%
34	-4.41	-31.22	7.65	4.41	31.22	-7.65	0.000%
35	-7.66	-31.22	4.40	7.66	31.22	-4.40	0.000%
36	-8.86	-31.22	-0.02	8.86	31.22	0.02	0.000%
37	-7.68	-31.22	-4.44	7.68	31.22	4.44	0.000%
38	-4.45	-31.22	-7.67	4.45	31.22	7.67	0.000%

Maximum	Tower	Deflections	- Sarvica	Wind
IVIAXIIIIUIII	iowei	Dellections	- Sei vice	vviiiu

Section No.	Elevation	Horz. Deflection	Gov. Load	Tilt	Twist
	ft	in	Comb.	0	0
L1	147.5 - 108.5	39.52	37	2.29	0.01
L2	112.25 - 72.25	23.25	37	2.03	0.00
L3	76.75 - 48	10.49	37	1.33	0.00
L4	48 - 35.75	4.03	37	0.78	0.00
L5	41 - 0	2.98	37	0.66	0.00

Critical Deflections and Radius of Curvature - Service Wind

Elevation	Appurtenance	Gov. Load	Deflection	Tilt	Twist	Radius of Curvature
ft		Comb.	in	0	o	ft
147.0000	TD-RRH8x20-25	37	39.28	2.29	0.01	26681
145.0000	PCS 1900MHz 4x45W-65MHz	37	38.32	2.28	0.01	26681
132.0000	BXA-70063-4CF-EDIN-X w/	37	32.14	2.22	0.01	8606
	Mount Pipe					
119.0000	RRU-11	37	26.18	2.12	0.00	4679
117.0000	7770.00 w/ Mount Pipe	37	25.30	2.09	0.00	4372
107.0000	APXV18-206517S-C	37	21.07	1.95	0.00	3553
49.0000	58532A	37	4.20	0.80	0.00	3031

Maximum Tower Deflections - Design Wind

Section	Elevation	Horz.	Gov.	Tilt	Twist
No.		Deflection	Load		
	ft	in	Comb.	0	٥
L1	147.5 - 108.5	100.68	12	5.83	0.01
L2	112.25 - 72.25	59.29	12	5.19	0.01
L3	76.75 - 48	26.76	12	3.39	0.01
L4	48 - 35.75	10.30	12	1.99	0.00
L5	41 - 0	7.61	12	1.69	0.00

Critical Deflections and Radius of Curvature - Design Wind

Elevation	Appurtenance	Gov. Load	Deflection	Tilt	Twist	Radius of Curvature
ft		Comb.	in	٥	٥	ft
147.0000	TD-RRH8x20-25	12	100.07	5.83	0.01	10679
145.0000	PCS 1900MHz 4x45W-65MHz	12	97.63	5.81	0.01	10679
132.0000	BXA-70063-4CF-EDIN-X w/	12	81.89	5.66	0.01	3443
	Mount Pipe					
119.0000	RRU-11	12	66.75	5.40	0.01	1869
117.0000	7770.00 w/ Mount Pipe	12	64.50	5.34	0.01	1746
107.0000	APXV18-206517S-C	12	53.73	4.98	0.01	1416
49.0000	58532A	12	10.73	2.03	0.00	1191

Compression Checks

	Pole Design Data									
Section No.	Elevation	Size	L	Lu	KI/r	Fa	Α	Actual P	Allow. Pa	Ratio P
	ft		ft	ft		ksi	in ²	K	ĸ	$\frac{P_a}{P_a}$
L1	147.5 - 108.5 (1)	TP29.41x22x0.25	39.0000	0.0000	0.0	36.00	22.5731	-8.42	812.63	0.010
L2	108.5 - 72.25	TP35.798x28.1975x0.25	40.0000	0.0000	0.0	39.00	27.5289	-13.60	1073.63	0.013

tnxTower Report - version 6.1.3.1

Section No.	Elevation	Size	L	Lu	KI/r	Fa	Α	Actual P	Allow. Pa	Ratio P
	ft		ft	ft		ksi	in²	K	ĸ	Pa
	(2)									
L3	72.25 - 48 (3)	TP39.9048x34.4429x0.312 5	28.7500	0.0000	0.0	39.00	39.2706	-19.19	1531.55	0.013
L4 L5	48 - 35.75 (4) 35.75 - 0 (5)	TP42.232x39.9048x0.3853 TP48.4x40.4641x0.375	12.2500 41.0000	0.0000	0.0	34.03 39.00	49.9499 57.1618	-20.73 -31.20	1699.60 2229.31	0.012 0.014

Pole Bending Design Data

Section No.	Elevation	Size	Actual M _x	Actual f _{bx}	Allow.	Ratio f _{bx}	Actual M _y	Actual f _{by}	Allow.	Ratio f _{by}
	ft		kip-ft	ksi	ksi	F_{bx}	kip-ft	ksi	ksi	F_{by}
L1	147.5 - 108.5 (1)	TP29.41x22x0.25	307.58	23.31	36.00	0.648	0.00	0.00	36.00	0.000
L2	108.5 - 72.25 (2)	TP35.798x28.1975x0.25	893.51	45.47	39.00	1.166	0.00	0.00	39.00	0.000
L3	72.25 - 48 (3)	TP39.9048x34.4429x0.31 25	1435.4 9	44.90	39.00	1.151	0.00	0.00	39.00	0.000
L4	48 - 35.75 (4)	TP42.232x39.9048x0.385	1576.0 1	37.62	34.03	1.106	0.00	0.00	34.03	0.000
L5	35.75 - 0 (5)	TP48.4x40.4641x0.375	2460.3 6	43.58	39.00	1.117	0.00	0.00	39.00	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V K	Actual f _v ksi	Allow. F _v ksi	Ratio f _v	Actual T kip-ft	Actual f _{vt} ksi	Allow. F _{vt} ksi	Ratio f _{vt} F _{vt}
	147.5 - 108.5	TP29.41x22x0.25	14.69	0.65	24.00	0.054	0.65	0.02	24.00	0.001
	(1)	11 25.41%22%0.25	14.00	0.00	24.00	0.004	0.00	0.02	24.00	0.001
L2	108.5 - 72.25	TP35.798x28.1975x0.25	17.84	0.65	26.00	0.050	0.69	0.02	26.00	0.001
	(2)									
L3	72.25 - 48 (3)	TP39.9048x34.4429x0.31	19.84	0.51	26.00	0.039	0.74	0.01	26.00	0.000
		25								
L4	48 - 35.75 (4)	TP42.232x39.9048x0.385	20.32	0.41	22.68	0.036	0.76	0.01	22.68	0.000
		3								
L5	35.75 - 0 (5)	TP48.4x40.4641x0.375	22.73	0.40	26.00	0.031	0.83	0.01	26.00	0.000


Pole Interaction Design Data

Section No.	Elevation	Ratio P	Ratio f _{bx}	Ratio f _{by}	Ratio f _v	Ratio f _{vt}	Comb. Stress	Allow. Stress	Criteria
	ft	Pa	F _{bx}	F_{by}	F_{v}	F_{vt}	Ratio	Ratio	
L1	147.5 - 108.5 (1)	0.010	0.648	0.000	0.054	0.001	0.659	1.333	H1-3+VT 🖊
L2	108.5 - 72.25 (2)	0.013	1.166	0.000	0.050	0.001	1.179	1.333	H1-3+VT 🖊
L3	72.25 - 48 (3)	0.013	1.151	0.000	0.039	0.000	1.164	1.333	H1-3+VT 🖊
L4	48 - 35.75 (4)	0.012	1.106	0.000	0.036	0.000	1.118	1.333	H1-3+VT 🗸
L5	35.75 - 0 (5)	0.014	1.117	0.000	0.031	0.000	1.132	1.333	H1-3+VT 🖊


Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
L1	147.5 - 108.5	Pole	TP29.41x22x0.25	1	-8.42	1083.24	49.4	Pass
L2	108.5 - 72.25	Pole	TP35.798x28.1975x0.25	2	-13.60	1431.15	88.5	Pass
L3	72.25 - 48	Pole	TP39.9048x34.4429x0.3125	3	-19.19	2041.56	87.3	Pass
L4	48 - 35.75	Pole	TP42.232x39.9048x0.3853	4	-20.73	2265.57	83.9	Pass
L5	35.75 - 0	Pole	TP48.4x40.4641x0.375	5	-31.20	2971.67	84.9	Pass
							Summary	
						Pole (L2)	88.5	Pass
						RATING =	88.5	Pass

APPENDIX B BASE LEVEL DRAWING



APPENDIX C ADDITIONAL CALCULATIONS



DESIGNED APPURTENANCE LOADING


TYPE	ELEVATION	TYPE	ELEVATION
TD-RRH8x20-25	147	BXA-171063-8BF-EDIN-2 w/ Mount	132
TD-RRH8x20-25	147	Pipe	
TD-RRH8x20-25	147	BXA-171063-8BF-EDIN-2 w/ Mount	132
APXVTM14-C-120 w/ Mount Pipe	147	Pipe	
APXVTM14-C-120 w/ Mount Pipe	147	BXA-70063-6CF-EDIN-2 w/ Mount Pipe	132
APXVTM14-C-120 w/ Mount Pipe	147	BXA-70063-6CF-EDIN-2 w/ Mount	132
APXVSPP18-C-A20 w/ Mount Pipe	147	Pipe	132
APXVSPP18-C-A20 w/ Mount Pipe	147	BXA-70063-6CF-EDIN-2 w/ Mount	132
APXVSPP18-C-A20 w/ Mount Pipe	147	Pipe	
(2) 6' x 2.375" Pipe Mount	147	Platform Mount [LP 712-1]	132
(2) 6' x 2.375" Pipe Mount	147	RRU-11	119
(3) 6' x 2.375" Pipe Mount	147	RRU-11	119
Platform Mount [LP 712-1]	147	RRU-11	119
PCS 1900MHz 4x45W-65MHz	145	DC6-48-60-18-8F	119
PCS 1900MHz 4x45W-65MHz	145	Pipe Mount [PM 601-3]	119
PCS 1900MHz 4x45W-65MHz	145	AM-X-CD-16-65-00T-RET w/ Mount	117
800MHz 2X50W RRH W/FILTER	145	Pipe	
800MHz 2X50W RRH W/FILTER	145	(2) LGP21401	117
800MHz 2X50W RRH W/FILTER	145	(2) LGP21401	117
Side Arm Mount [SO 102-3]	145	(2) LGP21401	117
BXA-70063-4CF-EDIN-X w/ Mount	132	(2) 6' x 2.375" Pipe Mount	117
Pipe		(2) 6' x 2.375" Pipe Mount	117
BXA-70063-4CF-EDIN-X w/ Mount	132	(2) 6' x 2.375" Pipe Mount	117
Pipe		Platform Mount [LP 712-1]	117
BXA-70063-4CF-EDIN-X w/ Mount Pipe	132	7770.00 w/ Mount Pipe	117
BXA-171063-12BF-EDIN-X w/ Mount	132	7770.00 w/ Mount Pipe	117
Pipe	132	7770.00 w/ Mount Pipe	117
BXA-171063-12BF-EDIN-X w/ Mount	132	SBNH-1D6565C w/ Mount Pipe	117
Pipe		AM-X-CD-14-65-00T-RET w/ Mount	117
BXA-171063-12BF-EDIN-X w/ Mount	132	Pipe	
Pipe		APXV18-206517S-C	107
RRH2X40-AWS	132	APXV18-206517S-C	107
RRH2X40-AWS	132	APXV18-206517S-C	107
RRH2X40-AWS	132	Pipe Mount [PM 601-3]	107
DB-T1-6Z-8AB-0Z	132	58532A	49
BXA-171063-8BF-EDIN-2 w/ Mount Pipe	132	Side Arm Mount [SO 701-1]	49

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-60	60 ksi	75 ksi	Reinf 56.71 ksi	57 ksi	71 ksi
A607-65	65 ksi	80 ksi			•

TOWER DESIGN NOTES

- Tower is located in Hartford County, Connecticut.
 Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
 Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to
- increase in thickness with height.
- 4. Deflections are based upon a 50 mph wind.
- 5. TOWER RATING: 88.5%





Paul J Ford and Company 250 E. Broad Street Suite 600 Columbus, OH 43215

Phone: 614.221.6679 FAX: 614.448.4105

^{lob:} 147' MP; Enfield, CT; Enfield					
Project: PJF 37513-064	14_R2_LC11 (BU 876348)				
Client: Crown Castle	Drawn by: Nick Parente, E.I.	App'd:			
	Date: 01/07/14	Scale: NTS			
Path:		Dwg No. F.			



Date: 1/7/2014 PJF Project: 37513-0644_R2 Client Ref. # BU 876348 Site Name: Enfield Description: 147.5' MP Owner: Crown Castle

v4.4 - Effective 7-12-13

Engineer: NZP

Asymmetric Anchor Rod Analysis

Moment = 2460 Axial = 31.0 kips Shear = 23.0 kips Anchor Qty = 15

TIA Ref. ASIF = 1.3333 Max Ratio = 105.0%

Base Plate Location = N/A Threads = N/A

for BP, Rev. G Sect. 4.9.9 for FP, Rev. G

** For Post Installed Anchors: Check anchors for embedment, epoxy/grout bond, and capacity based on proof load. **

	Nominal Anchor Dia,				Location,	Anchor	Area Override,		Max Net Compressio	Max Net Tension,	Load for Capacity	Capacity Override,	Capacity,	Capacity
Item	in	Spec	Fy, ksi	Fu, ksi	degrees	Circle, in	in ²	Area, in ²	n, kips	kips	Calc, kips	kips	kips	Ratio
1	2.250	#18J A615 Gr 75	75	100	32.4	55.00	0.00	3.98	153.53	149.04	149.04	0.00	195.00	76.4%
2	2.250	#18J A615 Gr 75	75	100	45.0	55.00	0.00	3.98	152.08	147.59	147.59	0.00	195.00	75.7%
3	2.250	#18J A615 Gr 75	75	100	57.6	55.00	0.00	3.98	150.69	146.21	146.21	0.00	195.00	75.0%
4	2.250	#18J A615 Gr 75	75	100	122.4	55.00	0.00	3.98	153.33	148.84	148.84	0.00	195.00	76.3%
5	2.250	#18J A615 Gr 75	75	100	135.0	55.00	0.00	3.98	155.51	151.02	151.02	0.00	195.00	77.4%
6	2.250	#18J A615 Gr 75	75	100	147.6	55.00	0.00	3.98	157.58	153.09	153.09	0.00	195.00	78.5%
7	2.250	#18J A615 Gr 75	75	100	212.4	55.00	0.00	3.98	157.58	153.09	153.09	0.00	195.00	78.5%
8	2.250	#18J A615 Gr 75	75	100	225.0	55.00	0.00	3.98	155.51	151.02	151.02	0.00	195.00	77.4%
9	2.250	#18J A615 Gr 75	75	100	237.6	55.00	0.00	3.98	153.33	148.84	148.84	0.00	195.00	76.3%
10	2.250	#18J A615 Gr 75	75	100	302.4	55.00	0.00	3.98	150.69	146.21	146.21	0.00	195.00	75.0%
11	2.250	#18J A615 Gr 75	75	100	315.0	55.00	0.00	3.98	152.08	147.59	147.59	0.00	195.00	75.7%
12	2.250	#18J A615 Gr 75	75	100	327.6	55.00	0.00	3.98	153.53	149.04	149.04	0.00	195.00	76.4%
13	1.750	A193 Gr B7	105	125	0.0	60.40	0.00	2.41	103.24	100.52	100.52	0.00	132.29	76.0%
14	1.750	A193 Gr B7	105	125	110.0	60.40	0.00	2.41	100.31	97.59	97.59	0.00	132.29	73.8%
15	1.750	A193 Gr B7	105	125	250.0	60.40	0.00	2.41	100.31	97.59	97.59	0.00	132.29	73.8%
	54.98													

Square, Stiffened / Unstiffened Base Plate, Any Rod Material - Rev. F /G

Assumptions: 1) Rod groups at corners. Total # rods divisible by 4. Maximum total # of rods = 48 (12 per Corner).

- 2) Rod Spacing = Straight Center-to-Center distance between any (2) adjacent rods (same corner)
- 3) Clear space between bottom of leveling nut and top of concrete **not** exceeding (1)*(Rod Diameter)

Site Data

BU#: Site Name: App #:

 7.66 //:					
Anchor Rod Data					
Qty:	12				
Diam:	2.25	in			
Rod Material:	A615-J				
Yield, Fy:	75	ksi			
Strength, Fu:	100	ksi			
Bolt Circle:	55	in			
Anchor Spacing:	6	in			

Base Reactions				
TIA Revision:	F			
Unfactored Moment, M:	2135.9	ft-kips		
Unfactored Axial, P:	26.9	kips		
Unfactored Shear, V:	20	kips		

Reactions adjusted to account for additional anchor rods

Anchor Rod Results

TIA F --> Maximum Rod Tension 153.1 Kips 195.0 Kips Allowable Tension: Anchor Rod Stress Ratio: 78.5% Pass

Plate Data					
W=Side:	52	in			
Thick:	3	in			
Grade:	50	ksi			
Clip Distance:	4	in			

Base Plate Results	Flexural Check
Base Plate Stress:	35.4 ksi
Allowable PL Bending Stress:	50.0 ksi
Base Plate Stress Ratio:	70.8% Pass

PL Ref. Data			
Yield Line (in):			
25.14			
Max PL Length:			
25.14			

Stiffener Data (Welding at both sides)

Configuration: Unstiffened

N/A - Unstiffened

Stiffener Results

Horizontal Weld: N/A Vertical Weld: N/A Plate Flex+Shear, fb/Fb+(fv/Fv)^2: N/A Plate Tension+Shear, ft/Ft+(fv/Fv)^2: N/A Plate Comp. (AISC Bracket): N/A

Pole Results

weia rype:		^ ^
Groove Depth:		in **
Groove Angle:		degrees
Fillet H. Weld:		< Disregard
Fillet V. Weld:		in
Width:		in
Height:		in
Thick:		in
Notch:		in
Grade:		ksi
Weld str.:		ksi
	•	•
Pole Data		

Pole Data		
Diam:	48.4	in
Thick:	0.375	in
Grade:	65	ksi
# of Sides:	18	"0" IF Round

Stress Increase Factor				
ASD ASIF:	1.333			

Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

Foundation Loads:

Pole weight or tower leg compression = 31 (kips)

Horizontal load at top of pier = 23 (kips)

Overturning moment at top of pier= 2460 (ft-kips)

Design criteria:

Safety factor against overturning = 1.5

Soil Properties:

Soil density = $\frac{115}{\text{Allowable soil bearing}} = \frac{3.25}{\text{Constant}} = \frac{3.25}{\text{Constant}} = \frac{4}{\text{Constant}} = \frac{115}{\text{Constant}} = \frac{115}{\text{Cons$

Dimensions:

Pier shape (round or square) ("R" or "S") Pier width = 8 (ft) Pier height above grade = (ft) depth to bottom of footing = (ft) Footing thickness = (ft) Footing width = 23.5 (ft) Footing length = 23.5 (ft)

Concrete:

 $\begin{array}{c} \text{Concrete strength} = & \mathbf{3} \\ \text{Rebar strength} = & \mathbf{60} \\ \text{ultimate load factor} = & \mathbf{1.3} \end{array} \text{(ksi)}$


Reinforcing Steel:

minimum cover over rebar = size of pad rebar = quantity of pad rebar = 23 inches #9 bar (ea direction)

Reinforcing Steel:

size of vert rebar in pier= #11 bar
vertical rebar quantity = 24
size of pier ties = #5 bar
minimum cover over rebar = 3 inches

Total volume of concrete = 79.1 cu yd



Summary of a	nalysis results
Maximum Net Soil Bearing = 1.807 ksf Allowable Net Soil Bearing = 3.25 ksf Soil Bearing Stress Ratio = 0.56 Okay	Ult Bending Shear Capacity = 110 psi Ult Bending Shear Stress = 24 psi Bending Shear Stress Ratio = 0.22 Okay
Ftg Overturning Resistance = 6319 ft-kips Overturning Moment = 2460 ft-kips Required Overturning Safety Factor = 1.5 Overturning Safety Factor = 2.569 Ratio = 0.58 Okay	Pad Bending Moment Capacity= 3142 ft-k Pad Bending Moment = 909 ft-k Bending Moment Stress Ratio = 0.29 OK

Page 1 01/06/14 03:23 PM

			000000					0									
				00	00			00									
00000		000000		00		00000		00		00	00	0 0000000000		0 00000			
00	0	00	00	00		00	00	00		00	00	00	00	00	00	00	
00		00	00	00		00	00	00		00	00	00	00	00	00	00	
000	000	00	00	00		00	00	00		00	00	00	00	00	00	00	
	00	0000	000	00		00	00	00		00	00	00	00	00	00	00	
0	00	00		00	00	00	00	00	0	00	00	00	00	00	00	00	
00000		00		000	000	000	000	0.0	00	000	200	00	00	00	00	00	(TM)

spColumn v4.80 (TM)

Computer program for the Strength Design of Reinforced Concrete Sections Copyright © 1988-2011, STRUCTUREPOINT, LLC. All rights reserved

Licensee stated above acknowledges that STRUCTUREPOINT (SP) is not and cannot be responsible for either the accuracy or adequacy of the material supplied as input for processing by the spColumn computer program. Furthermore, STRUCTUREPOINT neither makes any warranty expressed nor implied with respect to the correctness of the output prepared by the spColumn program. Although STRUCTUREPOINT has endeavored to produce spColumn error free the program is not and cannot be certified infallible. The final and only responsibility for analysis, design and engineering documents is the licensee's. Accordingly, STRUCTUREPOINT disclaims all responsibility in contract, negligence or other tort for any analysis, design or engineering documents prepared in connection with the use of the spColumn program.

STRUCTUREPOINT - spColumn v4.80 (TM) Page Licensed to: Paul J. Ford and Company. License ID: 60478-1036166-4-1E6CD-22701 01/06/14 03:23 PM

2

 $\texttt{G:\TOWER}\ 375_Crown_Castle\ 2013\ 37513-0644\ BU\ 876348\ \ WO\ 694127\ BU\ 876348\ \ (Phas...\ 37513-0644_R2.collabel{eq:BURCAST}$

General Information:

File Name: G:\TOWER\375_Crown_Castle\2013\37513-0644 BU 876348\WO 694127 BU 876...\37513-0644_R2.col

Project: 37513-0644 BP

Column: Engineer: ACI 318-11 Code: Units: English

Run Option: Investigation Slenderness: Not considered Run Axis: X-axis Column Type: Architectural

Material Properties:

f'c = 3 ksi

fy = 60 ksi Es = 29000 ksi = 3122.02 ksi Ec

Ultimate strain = 0.003 in/in Beta1 = 0.85

Section: =======

> Rectangular: Width = 96 in Depth = 96 in

Gross section area, Ag = 9216 in^2

Ix = 7.07789e+006 in^4 rx = 27.7128 in Iy = 7.07789e+006 in^4
ry = 27.7128 in
Yo = 0 in

Xo = 0 in

Reinforcement:

=========

Bar Set: ASTM A615

Size D	iam (in) Are	ea (in^2)	Size Di	.am (in) Are	ea (in^2)	Size Dia	am (in) Are	a (in^2)
# 3	0.38	0.11	# 4	0.50	0.20	# 5	0.63	0.31
# 6	0.75	0.44	# 7	0.88	0.60	# 8	1.00	0.79
# 9	1.13	1.00	# 10	1.27	1.27	# 11	1.41	1.56
# 14	1.69	2.25	# 18	2.26	4.00			

Confinement: Tied; #5 ties with #10 bars, #5 with larger bars.

phi(a) = 0.8, phi(b) = 0.9, phi(c) = 0.65

Layout: Rectangular

Pattern: All Sides Equal (Cover to transverse reinforcement)

Total steel area: As = 37.44 in^2 at rho = 0.41% (Note: rho < 0.50%) Minimum clear spacing = 13.15 in

24 #11 Cover = 3 in

Factored Loads and Moments with Corresponding Capacities:

	Pu	Mux	PhiMnx	PhiMn/Mu	NA depth	Dt depth	eps_t	Phi
No.	kip	k-ft	k-ft		in	in		
1	31.00	3422.25	7385.66	2.158	11.89	91.67	0.02013	0.900

*** End of output ***