



Filed by:  
Kri Pelletier, Property Specialist - SBA Communications  
134 Flanders Rd., Suite 125, Westborough, MA 01581  
508.251.0720 x 3804 - kpelletier@sbsite.com

September 15, 2017

Melanie A. Bachman  
Acting Executive Director  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

**Notice of Exempt Modification**

**188 Moody Rd., Enfield, CT**

**42 0 7.2 N**

**-72 31 18.1 W**

**Sprint #: CT33XC257\_2.5**

Dear Ms. Bachman:

Sprint currently maintains antennas at the 168-foot level of the existing 188-foot Monopole Tower at 188 Moody Road in Enfield, CT. The tower is owned by SBA 2012 TC Assets, LLC. The property is owned by Troiano Realty Corporation. Sprint now intends to remove (6) existing cell antennas and install (3) newer technology cell antennas at the 168-foot level of the tower.

Please note: previous approval was given by the Siting Council on 2/14/14 under EM-SPRINT-049-140124. A Notification of Construction Not Complete was sent 7/29/15. Sprint now intends to resume construction. The proposed full scope of work is as follows:

Remove:

(6) CDMA Panel Antennas

Remove and Replace: None

Install:

(3) RFS APXVTM14-C-120 – Panel Antennas

(3) Alcatel-Lucent TD-RRH8x20-25 – RRU

Existing Equipment to Remain (Including entitlements):

(1) RFS APXV9ERR18-C-A20 – Panel Antennas

(2) RFS APXVSP18-C-A20 – Panel Antennas

(4) ACU-A20-N – RET

(3) Alcatel-Lucent 1900MHz RRU

(3) Alcatel-Lucent 800 MHz RRH

(3) Alcatel-Lucent 800 MHz Filter

(3) 1-1/4" Fiber

(1) 0.7" Fiber



This facility was approved by Enfield's Planning and Zoning Commission on February 3, 2000. Special Use Permit File PH 2157 was granted under Section 14 and Section 16 allowing construction of a 180' high monopole not to interfere with existing or proposed public safety communications, commercial television and radio signals or other forms of communication transmissions. All generators installed were ordered to comply with all state and local noise regulations and the tower was to be maintained in a manner to blend in with the surroundings. On January 24, 2008, Council granted approval under Petition 844 (T-Mobile) to extend the tower by ten feet. This modification complies with all conditions.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16.50j-72(b)(2). In accordance with R.C.S.A. § 16.50j-73, a copy of this letter is being sent to the Town of Enfield's Town Manager, Bryan Chodkowski, and Director of Planning, Roger O'Brien, as well as to the property owner, Troiano Realty Corporation. (Separate notice is not being sent to tower owner, as it belongs to SBA.)

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. §16.50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modification will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modification will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-referenced telecommunication facility constitute an exempt modifications under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

Kri Pelletier  
Property Specialist  
SBA COMMUNICATIONS CORPORATION  
134 Flanders Rd., Suite 125  
Westborough, MA 01581  
508.251.0720 x3804 + T - 508.366.2610 + F  
203.446.7700 + C - kpelletier@sbsite.com

#### Attachments

cc: Bryan Chodkowski, Town Manager / with attachments  
*Town of Enfield, 820 Enfield St., Enfield, CT 06082*  
Roger J. O'Brien, Director of Planning / with attachments  
*Town of Enfield, 820 Enfield St., Enfield, CT 06082*  
Troiano Realty Corporation / with attachments  
*777 Enfield Street, Enfield, CT 06082*



**POWER DENSITY**

**SPRINT Site Inventory and Power Data by Antenna**

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APXV9ERR18-C-A20	Make / Model:	RFS APXVSP18-C-A20	Make / Model:	RFS APXVSP18-C-A20
Gain:	11.9 / 14.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	168 feet	Height (AGL):	168 feet	Height (AGL):	168 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	5,873.76	ERP (W):	7,537.38	ERP (W):	7,537.38
Antenna A1 MPE%:	0.90 %	Antenna B1 MPE%:	1.17 %	Antenna C1 MPE%:	1.17 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVTM14-C-D0	Make / Model:	RFS APXVTM14-C-D0	Make / Model:	RFS APXVTM14-C-D0
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	168 feet	Height (AGL):	168 feet	Height (AGL):	168 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%:	0.85 %	Antenna B2 MPE%:	0.85 %	Antenna C2 MPE%:	0.85 %

Site Composite MPE%	
Carrier	MPE%
SPRINT - Max per sector (Sectors B&C)	2.02 %
AT&T	3.23 %
MetroPCS	0.34 %
Nextel	0.19 %
Clearwire	0.05 %
T-Mobile	0.62 %
Site Total MPE %:	6.46 %

SPRINT Sector A Total:	1.75 %
SPRINT Sector B Total:	2.02 %
SPRINT Sector C Total:	2.02 %
Site Total:	6.46 %


ORIGIN ID: BFEA (508) 614-0389  
RICK WOODS  
SBA NETWORK SERVICES INC  
134 FLANDERS ROAD  
SUITE 125  
WESTBOROUGH, MA 01581  
UNITED STATES US

SHIP DATE: 15SEP17  
ACT/WT: 1.00 LB  
CAD: 105943304/NET3920  
BILL SENDER

TO  
**BRYAN CHODKOWSKI, TOWN MANAGER**  
**TOWN OF ENFIELD**  
**820 ENFIELD STREET**

**ENFIELD CT 06082**  
INV: (508) 251-0720 X 3804 REF: 1056920096099  
PO: DEPT:

549J1/FF19/104C



J172017062901uv

TRK# 0201  
**7702 6654 2954**

**MON - 18 SEP 10:30A**  
**PRIORITY OVERNIGHT**

**SE QCWA**

CT-US **BDL**  
**06082**



**After printing this label:**

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

**Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.**

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.


ORIGIN ID: BFEA (508) 614-0389  
RICK WOODS  
SEA NETWORK SERVICES INC  
134 FLANDERS ROAD  
SUITE 125  
WESTBOROUGH, MA 01581  
UNITED STATES US

SHIP DATE: 15SEP17  
ACT/WT: 1.00 LB  
CAD: 105843304/NET3920  
BILL SENDER

TO ROGER O'BRIEN, DIRECTOR OF PLANNING  
TOWN OF ENFIELD  
820 ENFIELD STREET

ENFIELD CT 06082  
(508) 251-0720 X 3804 REF: 1056920096089  
INV. DEPT.  
PO.

549J1/FF19/104C



J172017062901uv

TRK# 7702 6655 6413  
0201

MON - 18 SEP 10:30A  
PRIORITY OVERNIGHT

SE QCWA

06082  
CT-US BDL



**After printing this label:**

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

**Warning:** Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.


ORIGIN ID:BBFA (508) 614-0389  
RICK WOODS  
SBA NETWORK SERVICES INC  
134 FLANDERS ROAD  
SUITE 125  
WESTBOROUGH MA 01581  
UNITED STATES US

SHIP DATE: 18SEP17  
ACT WGT: 1.00 LB  
CAD: 105843304/NET3920  
BILL SENDER

TO **PRESIDENT / MANAGER**  
**TROIANO REALTY CORPORATION**  
**777 ENFIELD STREET**

**ENFIELD CT 06082**  
(508) 251-0720 X 3804 REF: 1058920096089  
NY DEPT:  
PO

549J1/FF19/104C



J172017062901uv

TRK# 7702 6656 7899  
0201

MON - 18 SEP 10:30A  
PRIORITY OVERNIGHT

**SE QCWA**

06082  
CT-US BDL



**After printing this label:**

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

**Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.**

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

**188 MOODY RD**

**Location** 188 MOODY RD **Mblu** 100/ / 0012/ /  
**Acct#** 001600020130 **Owner** TROIANO REALTY CORP  
**Assessment** \$1,312,310 **Appraisal** \$1,874,720  
**PID** 2238 **Building Count** 1  
**Fire District** 3

**Current Value**

Appraisal			
Valuation Year	Improvements	Land	Total
2016	\$1,168,800	\$705,920	\$1,874,720
Assessment			
Valuation Year	Improvements	Land	Total
2016	\$818,160	\$494,150	\$1,312,310

**Owner of Record**

**Owner** TROIANO REALTY CORP **Sale Price** \$0  
**Co-Owner** **Certificate** 1  
**Address** 0777 ENFIELD ST **Book & Page** 305/ 468  
 ENFIELD, CT 06082 **Sale Date**

**Ownership History**

Ownership History				
Owner	Sale Price	Certificate	Book & Page	Sale Date
TROIANO REALTY CORP	\$0	1	305/ 468	

**Building Information**

**Building 1 : Section 1**

**Year Built:** 1965  
**Living Area:** 10,980  
**Replacement Cost:** \$490,290  
**Building Percent Good:** 37  
**Replacement Cost Less Depreciation:** \$181,410

**Building Photo**


Building Attributes	
Field	Description
STYLE	Industrial Flex Bldg

MODEL	Ind/Comm
Grade	Average
Stories:	1
Occupancy	3
Exterior Wall 1	Pre-finish Metl
Exterior Wall 2	
Roof Structure	Gable
Roof Cover	Metal/Tin
Interior Wall 1	Minim/Masonry
Interior Wall 2	
Interior Floor 1	Vinyl/Asphalt
Interior Floor 2	
Heating Fuel	Gas
Heating Type	Forced Air-Duc
AC Type	None
Bldg Use	Industrial
Total Rooms	
Total Bedrms	
Total Baths	
Total H Bths	
Extra Fixtures	
1st Floor Use:	
Heat/AC	None
Frame Type	Steel
Baths/Plumbing	Average
Ceiling/Wall	None
Rooms/Prtns	Average
Wall Height	15
% Cornn Wall	



(http://images.vgsi.com/photos2/EnfieldCTPhotos//\00\01\95\47.JPG)

**Building Layout**



Building Sub-Areas (sq ft)			Legend
Code	Description	Gross Area	Living Area
BAS	First Floor	10,980	10,980
SLB	Slab	10,980	0
ULP	Uncvrd Loading Platform	450	0
		22,410	10,980

**Extra Features**

Extra Features		Legend
No Data for Extra Features		

**Land**

**Land Use**

Use Code 301  
 Description Industrial  
 Zone I-1  
 Neighborhood C500  
 Alt Land Appr No  
 Category

**Land Line Valuation**

Size (Acres) 15.1  
 Frontage  
 Depth  
 Assessed Value \$494,150  
 Appraised Value \$705,920



**Outbuildings**

Outbuildings						Legend
Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
PAV1	Paving	AS	Asphalt	32200 S.F.	\$5,540	1
TNK2	Tank - Oil			500000 GALS	\$240,000	1
FN2	FENCE-6' CHAIN			900 L.F.	\$1,220	1
TWR5	Cell Twr5 Carriers			1 UNITS	\$740,630	1

**Valuation History**

Appraisal			
Valuation Year	Improvements	Land	Total
2016	\$1,168,800	\$705,920	\$1,874,720
2015	\$1,180,530	\$705,920	\$1,886,450
2014	\$1,180,530	\$705,920	\$1,886,450

Assessment			
Valuation Year	Improvements	Land	Total
2016	\$818,160	\$494,150	\$1,312,310
2015	\$826,370	\$494,150	\$1,320,520
2014	\$826,370	\$494,150	\$1,320,520

(c) 2016 Vision Government Solutions, Inc. All rights reserved.



## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT33XC257

Claryville Nextel  
188 Moody Road  
Enfield, CT 06082

**September 7, 2017**

**EBI Project Number: 6217003985**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>6.46 %</b>



September 7, 2017

SPRINT

Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

## Emissions Analysis for Site: **CT33XC257 – Claryville Nextel**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **188 Moody Road, Enfield, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 850 MHz Band is approximately  $567 \mu\text{W}/\text{cm}^2$ . The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **188 Moody Road, Enfield, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **RFS APXVSP18-C-A20**, **RFS APXV9ERR18-C-A20** and the **RFS APXVTM14-C-I20** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **168 feet** above ground level (AGL) for **Sector A**, **168 feet** above ground level (AGL) for **Sector B** and **168 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



## SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	<b>1</b>	Antenna #:	<b>1</b>	Antenna #:	<b>1</b>
Make / Model:	RFS APXV9ERR18-C-A20	Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20
Gain:	11.9 / 14.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	<b>168 feet</b>	Height (AGL):	<b>168 feet</b>	Height (AGL):	<b>168 feet</b>
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	5,873.76	ERP (W):	7,537.38	ERP (W):	7,537.38
Antenna A1 MPE%	<b>0.90 %</b>	Antenna B1 MPE%	<b>1.17 %</b>	Antenna C1 MPE%	<b>1.17 %</b>
Antenna #:	<b>2</b>	Antenna #:	<b>2</b>	Antenna #:	<b>2</b>
Make / Model:	RFS APXVTM14-C-I20	Make / Model:	RFS APXVTM14-C-I20	Make / Model:	RFS APXVTM14-C-I20
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	<b>168 feet</b>	Height (AGL):	<b>168 feet</b>	Height (AGL):	<b>168 feet</b>
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	<b>0.85 %</b>	Antenna B2 MPE%	<b>0.85 %</b>	Antenna C2 MPE%	<b>0.85 %</b>

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector (Sectors B&C)	<b>2.02 %</b>
AT&T	3.23 %
MetroPCS	0.34 %
Nextel	0.19 %
Clearwire	0.06 %
T-Mobile	0.62 %
<b>Site Total MPE %:</b>	<b>6.46 %</b>

SPRINT Sector A Total:	1.75 %
SPRINT Sector B Total:	2.02 %
SPRINT Sector C Total:	2.02 %
<b>Site Total:</b>	<b>6.46 %</b>

SPRINT _ Max Values per Frequency Band / Technology (Sectors B & C)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	168	0.60	850 MHz	567	0.11%
Sprint 850 MHz LTE	2	437.55	168	1.20	850 MHz	567	0.21%
Sprint 1900 MHz (PCS) CDMA	5	622.47	168	4.26	1900 MHz (PCS)	1000	0.43%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	168	4.26	1900 MHz (PCS)	1000	0.43%
Sprint 2500 MHz (BRS) LTE	8	778.09	168	8.53	2500 MHz (BRS)	1000	0.85%
<b>Total*:</b>						<b>2.02%</b>	

\*NOTE: Totals may vary by 0.01% due to summing of remainders



## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	1.75 %
Sector B:	2.02 %
Sector C:	2.02 %
SPRINT Maximum Total (per sector):	2.02 %
Site Total:	6.46 %
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **6.46 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Tower Engineering Solutions**

Phone (972) 483-0607, Fax (972) 975-9615  
8445 Freepoint Parkway, Suite 375, Irving, Texas 75063

---

## Structural Analysis Report

**Existing 188 ft SUMMIT Monopole**  
**Customer Name: SBA Communications Corp**  
**Customer Site Number: CT46124-A**  
**Customer Site Name: Enfield-Moody Rd.**  
**Carrier Name: Sprint Nextel**  
**Carrier Site ID / Name: CT33XC257 / Enfield-Moody Rd.**  
**Site Location: 188 Moody Rd**  
**Enfield, Connecticut**  
**Hartford County**  
**Latitude: 42.002000**  
**Longitude: -72.521694**

### Analysis Result:

**Max Structural Usage: 75.9% [Pass]**  
**Max Foundation Usage: 73.1% [Pass]**  
**Report Prepared By: Vipul Patel**





## Introduction

The purpose of this report is to summarize the analysis results on the 188 ft SUMMIT Monopole to support the proposed antennas and transmission lines in addition to those currently installed. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

## Sources of Information

<b>Tower Drawings</b>	Summit, Job # 29200-155, dated 2/12/00
<b>Foundation Drawing</b>	Summit, Job # 29200-155, dated 2/12/00
<b>Geotechnical Report</b>	Tectonic, Project # 1170.C054, dated 9/17/98
<b>Modification Drawings</b>	Paul J. Ford and Company, Project #A29208-0031 dated March 14, 2008 FDH Engineering, Project #1335291400 dated February 20, 2015 Tower Engineering Solutions, Job #19423 dated June 1, 2016

## Analysis Criteria

The rigorous analysis was performed in accordance with the requirements and stipulations of the ANSI/TIA/EIA 222-G. In accordance with this standard, the structure was analyzed using **TESPoles**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

<b>Wind Speed Used in the Analysis:</b> <b>(based on 2012 IBC)</b>	Ultimate Design Wind Speed $V_{ult} = 121.0$ mph (3-Sec. Gust)/ Nominal Design Wind Speed $V_{asd} = 94.0$ mph (3-Sec. Gust)
<b>Wind Speed with Ice:</b>	50 mph (3-Sec. Gust) with 1" radial ice concurrent
<b>Operational Wind Speed:</b>	60 mph + 0" Radial ice
<b>Standard/Codes:</b>	ANSI/TIA/EIA 222-G / 2012 IBC / 2016 Connecticut State Building Code
<b>Exposure Category:</b>	C
<b>Structure Class:</b>	II
<b>Topographic Category:</b>	1
<b>Crest Height:</b>	0 ft
<b>Seismic Parameters:</b>	$S_S = 0.175$ , $S_1 = 0.064$

## Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	187.0	3	Kathrein 782 11054 - Bias T	Low Profile Platform	(18) 1 5/8"	T-Mobile
2		3	RFS APX16PV-16-PVL-E - Panel			
3		3	RFS APXV18-209014 - Panel			
4		3	Commscope LNX-6515DS-A1M - Panel			
5		12	Ericsson KRY 112 114-1 - TMA			
6	168.0	1	RFS APXV9ERR18-C-A20 - Panel	Low Profile Platform	(3) 1-1/4" Fiber (1) 0.7" Fiber	Sprint
7		2	RFS APXVSP18-C-A20 - Panel			
8		3	RFS APXVTM14-C-120 - Panel			
9		4	ACU-A20-N - RET			
10		3	Alcatel-Lucent 1900MHz RRU			
11		3	Alcatel-Lucent 800 MHz RRH			
12		3	Alcatel-Lucent TD-RRH8x20-25 - RRU			
13		3	Alcatel-Lucent 800 MHz Filter			
14	158.0	3	Powerwave 7770 - Panel	(3) T-Arm	(9) 1 5/8" (1) 3" Innerduct <sup>1</sup>	AT&T
15		1	Raycap DC-48-60-18-8F			
16		6	Powerwave LGP21401 - TMA			
17		2	Powerwave P65-17-XLH-RR - Panel			
18		6	Ericsson RRUS-11			
19		1	Andrew SBNH-1D6565C - Panel			
20	148.0	3	Kathrein 742 213 - Panel	Flush Mount	(6) 1 5/8"	Metro PCS <sup>2</sup>

1. (1) 3/8" Fiber and (2) 5/8" DC Power cables are considered to be installed inside (1) 3" innerduct.

2. Lines considered to be installed outside of pole shaft.

## Proposed Carrier's Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier's final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	168.0	1	RFS APXV9ERR18-C-A20 - Panel	Low Profile Platform	(3) 1-1/4" Fiber (1) 0.7" Fiber	Sprint
2		2	RFS APXVSP18-C-A20 - Panel			
3		3	RFS APXVTM14-C-120 - Panel			
4		4	ACU-A20-N - RET			
5		3	Alcatel-Lucent 1900MHz RRU			
6		3	Alcatel-Lucent 800 MHz RRH			
7		3	Alcatel-Lucent TD-RRH8x20-25 - RRU			
8		3	Alcatel-Lucent 800 MHz Filter			

All transmission lines are considered running inside of the pole shafts.

## **Analysis Results**

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

	Pole shafts	Anchor Bolts	Base Plate	Flange Bolts	Flange Plate	Reinforcement
Max. Usage:	<b>62.0%</b>	<b>57.9%</b>	<b>70.2%</b>	<b>30.5%</b>	<b>9.3%</b>	<b>75.9%</b>
Pass/Fail	<b>Pass</b>	<b>Pass</b>	<b>Pass</b>	<b>Pass</b>	<b>Pass</b>	<b>Pass</b>

## **Foundations**

	Moment (Kip-Ft)	Shear (Kips)
Analysis Reactions	3587.5	28.0

The foundation has been investigated using the supplied documents and soils report and was found adequate. Therefore, no modification to the foundation will be required.

## **Operational Condition (Rigidity):**

Operational characteristics of the tower are found to be within the limits prescribed by ANSI/TIA/EIA 222-G for the installed antennas. The maximum twist/sway at the elevation of the proposed equipment is 1.6510 degrees under the operational wind speed as specified in the Analysis Criteria.

## **Conclusions**

Based on the analysis results, the existing structure and its foundation were found to be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the ANSI/TIA-222-G standards and the 2012 IBC under the design basic wind speed specified in the Analysis Criteria.

## Standard Conditions

1. This analysis was performed based on the information supplied to **(TES) Tower Engineering Solutions, LLC**. Verification of the information provided was not included in the Scope of Work for **TES**. The accuracy of the analysis is dependent on the accuracy of the information provided.
2. The analysis is based on the presumption that the tower members and components along with any existing reinforcement items have been correctly and properly designed, manufactured, installed and maintained.
3. All the existing structural members were assumed to be in good condition with no physical damage or deterioration associated with corrosion.
4. An initial tension of 10% of the break strength on all the existing guy wires was assumed in all the structural analyses of guyed towers unless different values were provided by the client. **TES** cannot take responsibility for the deviations in the analysis results because of differences in the initial tension forces of the existing guy wires.
5. Secondary component or connection secondary components, welds and bolts are assumed to be able to carry their intended original design loads. **TES** cannot take responsibility for verification of the adequacy on the connections, bolts and welds present in the structure.
6. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of **TES**. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed and/or ice loads are different from the minimum values recommended by the EIA/TIA-222 standard or other codes, **TES** should be notified in writing and the applicable minimum values provided by the client.
7. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. **TES** has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, **TES** should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
8. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
9. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

# Usage Diagram - Max Ratio 62.02% at 35.0ft

**Structure:** CT46124-A-SBA  
**Site Name:** Enfield-Moody Rd.  
**Height:** 188.00 (ft)  
**Base Elev:** 0.000 (ft)

**Code:** EIA/TIA-222-G  
**Exposure:** C  
**Gh:** 1.1


7/31/2017



Page: 1


**Dead Load Factor:** 1.20  
**Wind Load Factor:** 1.60

**Load Case : 1.2D + 1.6W 94 mph Wind**



**Iterations:** 29

*Copyright © 2017 by Tower Engineering Solutions, LLC. All rights reserved.*



## Structure: CT46124-A-SBA

**Type:** Custom  
**Site Name:** Enfield-Moody Rd.  
**Height:** 188.00 (ft)  
**Base Elev:** 0.00 (ft)

**Base Shape:** 18 Sided  
**Taper:** 0.16603

7/31/2017

Page: 2



### Shaft Properties

Seq	Length (ft)	Top (in)	Bottom (in)	Thick (in)	Joint Type	Taper	Grade (ksi)
1	49.00	43.60	51.74	0.438		0.16603	65
2	49.00	37.17	45.31	0.375	Slip	0.16603	65
3	49.00	30.45	38.59	0.313	Slip	0.16603	65
4	45.50	24.00	31.55	0.219	Slip	0.16603	65
5	10.00	22.34	24.00	0.188	Butt	0.00000	65

### Discrete Appurtenances


Attach Elev (ft)	Force Elev (ft)	Qty	Description	Carrier
187.00	187.00	3	APX16PV-16-PVL-E	T-Mobile
187.00	187.00	12	KRY 112 144-1	T-Mobile
187.00	187.00	3	APXV18-209014	T-Mobile
187.00	187.00	3	LNx-6515DS-A1M	T-Mobile
187.00	187.00	3	782 11054	T-Mobile
184.00	184.00	1	Low Profile Platform	T-Mobile
168.50	168.50	1	Low Profile Platform	Sprint
168.00	168.00	2	APXVSP18-C-A20	Sprint
168.00	168.00	3	800 MHz Filters	Sprint
168.00	168.00	3	APXVTM14-C-120	Sprint
168.00	168.00	3	1900 MHz RRH	Sprint
168.00	168.00	3	800 MHz RRH	Sprint
168.00	168.00	3	TD-RRH8x20-25	Sprint
168.00	168.00	4	ACU-A20-N	Sprint
168.00	168.00	1	APXV9ERR18-C-A20	Sprint
158.00	158.00	3	T-Arm	AT&T
158.00	158.00	2	P65-17-XLH-RR	AT&T
158.00	158.00	6	LGP21401	AT&T
158.00	158.00	6	RRUS-11	AT&T
158.00	158.00	3	7770	AT&T
158.00	158.00	1	DC-48-60-18-8F	AT&T
158.00	158.00	1	SBNH-1D6565C	AT&T
148.00	148.00	1	Flush Mount	Metro PCS
148.00	148.00	3	742 213	Metro PCS

### Linear Appurtenances

Elev From (ft)	Elev To (ft)	Placement	Description	Carrier
0.00	187.00	Inside	1 5/8" Coax	T-Mobile
0.00	168.00	Inside	0.7" Fiber	Sprint
0.00	168.00	Inside	1-1/4" Fiber	Sprint
0.00	158.00	Inside	1 5/8" Coax	AT&T
0.00	158.00	Inside	3" Innerduct	AT&T
0.00	158.00	Inside	3/8" Fiber	AT&T
0.00	158.00	Inside	5/8" DC	AT&T
0.00	148.00	Outside	1 5/8" Coax	Metro PCS
90.25	107.25	Outside	1.25" Reinforcing plate	
46.50	79.25	Outside	1.25" Reinforcing plate	
0.00	35.50	Outside	1.25" Reinforcing plate	

### Anchor Bolts

Qty	Specifications	Grade (ksi)	Arrangement
16	2.25" 18J	75.0	Cluster



**Structure: CT46124-A-SBA**

**Type:** Custom  
**Site Name:** Enfield-Moody Rd.  
**Height:** 188.00 (ft)  
**Base Elev:** 0.00 (ft)

**Base Shape:** 18 Sided  
**Taper:** 0.00000

7/31/2017

Page: 3



**Base Plate**

Thickness (in)	Specifications (in)	Grade (ksi)	Geometry
3.2500	57.0	50.0	Clipped

**Reactions**


Load Case	Moment (FT-Kips)	Shear (Kips)	Axial (Kips)
1.2D + 1.6W 94 mph Wind	3587.5	28.0	49.0
0.9D + 1.6W 94 mph Wind	3541.5	28.0	36.7
1.2D + 1.0Di + 1.0Wi 50 mph Wind	1239.7	9.4	84.3
1.2D + 1.0E	205.2	1.6	49.0
0.9D + 1.0E	202.4	1.6	36.8
1.0D + 1.0W 60 mph Wind	906.8	7.1	40.9

# Structure: CT46124-A-SBA - Coax Line Placement

**Type:** Monopole  
**Site Name:** Enfield-Moody Rd.  
**Height:** 188.00 (ft)

7/31/2017

Page: 4





## Shaft Properties

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 5

Sec. No.	Shape	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Overlap (in)	Weight (lb)
1	18	49.000	0.4375	65		0.00	10,936
2	18	49.000	0.3750	65	Slip	69.00	8,110
3	18	49.000	0.3125	65	Slip	57.00	5,657
4	18	45.500	0.2188	65	Slip	48.00	2,963
5	18	10.000	0.1875	65	Flange	0.00	482
<b>Total Shaft Weight:</b>							<b>28,148</b>

Bottom

Top

Sec. No.	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Taper
1	51.74	0.00	71.24	23688.52	19.44	118.26	43.60	49.00	59.94	14111.8	16.16	99.67	0.166026
2	45.31	43.25	53.48	13643.07	19.89	120.83	37.17	92.25	43.80	7493.55	16.07	99.13	0.166026
3	38.59	87.50	37.96	7026.65	20.36	123.48	30.45	136.50	29.89	3431.02	15.77	97.45	0.166026
4	31.55	132.5	21.76	2699.58	24.02	144.21	24.00	178.00	16.51	1180.03	17.93	109.6	0.166026
5	24.00	178.0	14.17	1015.22	21.16	128.00	22.34	188.00	14.17	1015.22	21.16	119.1	0.000000

### Additional Steel

Elev From (ft)	Elev To (ft)	Qty	Description	Fy (ksi)	Fu (ksi)	Offset (in)	Intermediate Connectors		Termination Connectors			
							Description	Spacing (in)	Description	Spacing (in)	Lower Qty	Upper Qty
0.00	32.83	3	PLT 6"X1-1/4"(1.25" Hole	65	80	0.00	AJM20&sleeve	21.00	AJM20&sleeve	3.00		11
48.92	76.83	3	PLT 5.5"x1 1/4"(1.25"hol	65	80	0.00	AJM20&sleeve	21.00	AJM20&sleeve	3.00	10	10
91.92	105.5	3	PLT 4.5"x 1-1/4"(1.25"ho	65	80	0.00	AJM20&sleeve	24.00	AJM20&sleeve	3.00	7	7

## Load Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 6

### Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
1	187.00	APX16PV-16-PVL-E	3	39.60	6.03	0.62	230.62	7.534	0.62	0.00	0.00
2	187.00	KRY 112 144-1	12	11.00	0.41	0.67	25.70	1.058	0.67	0.00	0.00
3	187.00	APXV18-209014	3	18.70	3.58	0.74	153.48	4.893	0.74	0.00	0.00
4	187.00	LNX-6515DS-A1M	3	49.80	11.47	0.80	362.69	15.923	0.80	0.00	0.00
5	187.00	782 11054	3	1.80	0.22	0.67	5.18	0.893	0.67	0.00	0.00
6	184.00	Low Profile Platform	1	1500.00	22.00	1.00	3281.24	46.035	1.00	0.00	0.00
7	168.50	Low Profile Platform	1	1500.00	22.00	1.00	3265.63	45.824	1.00	0.00	0.00
8	168.00	APXVSP18-C-A20	2	57.00	8.02	0.83	290.10	11.787	0.83	0.00	0.00
9	168.00	800 MHz Filters	3	54.00	2.94	0.67	155.87	4.579	0.67	0.00	0.00
10	168.00	APXVTM14-C-120	3	56.00	6.34	0.79	287.79	7.875	0.79	0.00	0.00
11	168.00	1900 MHz RRH	3	44.00	2.94	0.67	134.92	4.579	0.67	0.00	0.00
12	168.00	800 MHz RRH	3	54.00	2.94	0.67	155.87	4.579	0.67	0.00	0.00
13	168.00	TD-RRH8x20-25	3	70.00	4.05	0.67	230.02	5.176	0.67	0.00	0.00
14	168.00	ACU-A20-N	4	1.00	0.14	1.00	6.79	0.540	1.00	0.00	0.00
15	168.00	APXV9ERR18-C-A20	1	62.00	8.02	0.83	306.73	11.787	0.83	0.00	0.00
16	158.00	T-Arm	3	300.00	8.00	0.67	580.69	17.356	0.67	0.00	0.00
17	158.00	P65-17-XLH-RR	2	59.00	11.44	0.75	349.31	15.775	0.75	0.00	0.00
18	158.00	LGP21401	6	17.50	1.26	0.67	48.20	2.369	0.67	0.00	0.00
19	158.00	RRUS-11	6	50.70	2.52	0.67	179.64	3.419	0.67	0.00	0.00
20	158.00	7770	3	35.00	5.50	0.73	230.43	6.960	0.73	0.00	0.00
21	158.00	DC-48-60-18-8F	1	31.80	1.47	1.00	114.66	2.408	1.00	0.00	0.00
22	158.00	SBNH-1D6565C	1	66.10	11.47	0.80	374.21	15.827	0.80	0.00	0.00
23	148.00	Flush Mount	1	150.00	5.00	1.00	317.32	9.648	1.00	0.00	0.00
24	148.00	742 213	3	22.00	5.12	0.72	188.84	6.883	0.72	0.00	0.00
<b>Totals:</b>			<b>74</b>	<b>6,321.80</b>			<b>18,790.36</b>				

### Linear Appurtenances

Bottom Elev. (ft)	Top Elev. (ft)	Description	Exposed Width	Exposed
0.00	187.00	(18) 1 5/8" Coax	0.00	Inside
0.00	168.00	(1) 0.7" Fiber	0.00	Inside
0.00	168.00	(3) 1-1/4" Fiber	0.00	Inside
0.00	158.00	(9) 1 5/8" Coax	0.00	Inside
0.00	158.00	(1) 3" Innerduct	0.00	Inside
0.00	158.00	(1) 3/8" Fiber	0.00	Inside
0.00	158.00	(2) 5/8" DC	0.00	Inside
0.00	148.00	(6) 1 5/8" Coax	2.00	Outside
90.25	107.25	(3) 1.25" Reinforcing plate	1.00	Outside
46.50	79.25	(3) 1.25" Reinforcing plate	1.00	Outside
0.00	35.50	(3) 1.25" Reinforcing plate	1.00	Outside

## Shaft Section Properties

**Structure:** CT46124-A-SBA      **Code:** EIA/TIA-222-G      7/31/2017  
**Site Name:** Enfield-Moody Rd.      **Exposure:** C  
**Height:** 188.00 (ft)      **Crest Height:** 0.00  
**Base Elev:** 0.000 (ft)      **Site Class:** D - Stiff Soil  
**Gh:** 1.1      **Topography:** 1      **Struct Class:** II      **Page:** 7



**Increment Length:** 5 (ft)

Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in^2)	Ix (in^4)	W/t Ratio	D/t Ratio	Fy (ksi)	Fb (ksi)	Weight (lb)	Additional Reinforcing			
											Area (in^2)	Ixp (in^4)	Iyp (in^4)	Weight (lb)
0.00	RB1	0.4375	51.740	71.237	23688.5	19.44	118.26	65	79	0.0	22.50	7932.5	7932.5	
5.00		0.4375	50.910	70.085	22557.1	19.11	116.37	65	79	1202.2	22.50	7687.0	7687.0	382.8
10.00		0.4375	50.080	68.932	21462.3	18.77	114.47	65	79	1182.6	22.50	7445.4	7445.4	382.8
15.00		0.4375	49.250	67.779	20403.5	18.44	112.57	65	80	1163.0	22.50	7207.7	7207.7	382.8
20.00		0.4375	48.419	66.627	19380.1	18.10	110.67	65	80	1143.4	22.50	6973.8	6973.8	382.8
25.00		0.4375	47.589	65.474	18391.6	17.77	108.78	65	81	1123.8	22.50	6743.8	6743.8	382.8
30.00		0.4375	46.759	64.321	17437.2	17.43	106.88	65	81	1104.2	22.50	6517.7	6517.7	382.8
32.83	RT1	0.4375	46.289	63.669	16911.9	17.25	105.80	65	81	616.3	22.50	6391.4	6391.4	216.7
35.00		0.4375	45.929	63.168	16516.4	17.10	104.98	65	81	468.3				
40.00		0.4375	45.099	62.016	15628.6	16.77	103.08	65	82	1064.9				
43.25	Bot - Section 2	0.4375	44.559	61.267	15069.0	16.55	101.85	65	82	681.7				
45.00		0.4375	44.269	60.863	14773.3	16.43	101.19	65	82	681.1				
48.92	RB2	0.4375	43.618	59.959	14124.9	16.17	99.70	65	82	1509.4	20.63	5392.4	5392.4	275.1
49.00	Top - Section 1	0.3750	44.355	52.345	12791.9	19.45	118.28	65	79	30.6	20.63	5389.3	5389.3	5.6
50.00		0.3750	44.189	52.147	12647.5	19.37	117.84	65	79	177.8	20.63	5350.3	5350.3	70.2
55.00		0.3750	43.359	51.159	11942.2	18.98	115.62	65	79	878.8	20.63	5157.6	5157.6	350.9
60.00		0.3750	42.528	50.171	11263.5	18.59	113.41	65	80	862.0	20.63	4968.5	4968.5	350.9
65.00		0.3750	41.698	49.183	10611.1	18.20	111.20	65	80	845.2	20.63	4782.8	4782.8	350.9
70.00		0.3750	40.868	48.195	9984.4	17.81	108.98	65	80	828.4	20.63	4600.8	4600.8	350.9
75.00		0.3750	40.038	47.207	9382.8	17.42	106.77	65	81	811.6	20.63	4422.3	4422.3	350.9
76.83	RT2	0.3750	39.734	46.846	9168.9	17.27	105.96	65	81	292.8	20.63	4357.8	4357.8	128.4
80.00		0.3750	39.208	46.219	8805.9	17.03	104.55	65	81	501.9				
85.00		0.3750	38.378	45.231	8253.2	16.63	102.34	65	82	778.0				
87.50	Bot - Section 3	0.3750	37.963	44.737	7985.7	16.44	101.23	65	82	382.7				
90.00		0.3750	37.548	44.243	7724.1	16.24	100.13	65	82	699.7				
91.92	RB3	0.3750	37.229	43.864	7527.1	16.09	99.28	65	82	532.1	16.88	3240.8	3240.8	110.2
92.25	Top - Section 2	0.3125	37.799	37.181	6601.2	19.92	120.96	65	78	91.0	16.88	3231.8	3231.8	18.9
95.00		0.3125	37.343	36.728	6362.9	19.66	119.50	65	78	345.8	16.88	3157.0	3157.0	157.9
100.00		0.3125	36.512	35.904	5944.5	19.19	116.84	65	79	617.9	16.88	3023.3	3023.3	287.1
105.00		0.3125	35.682	35.081	5544.9	18.72	114.18	65	79	603.9	16.88	2892.5	2892.5	287.1
105.58	RT3	0.3125	35.586	34.986	5499.7	18.67	113.88	65	79	69.1	16.88	2877.5	2877.5	33.3
110.00		0.3125	34.852	34.258	5163.6	18.25	111.53	65	80	520.7				
115.00		0.3125	34.022	33.434	4800.1	17.79	108.87	65	80	575.9				
120.00		0.3125	33.192	32.611	4454.2	17.32	106.21	65	81	561.8				
125.00		0.3125	32.362	31.788	4125.2	16.85	103.56	65	82	547.8				
130.00		0.3125	31.532	30.964	3812.9	16.38	100.90	65	82	533.8				
132.50	Bot - Section 4	0.3125	31.117	30.553	3662.8	16.15	99.57	65	82	261.7				
135.00		0.3125	30.702	30.141	3516.8	15.91	98.24	65	83	442.1				
136.50	Top - Section 3	0.2188	30.890	21.300	2531.6	23.48	141.18	65	74	262.4				
140.00		0.2188	30.309	20.896	2390.4	23.01	138.52	65	74	251.3				
145.00		0.2188	29.479	20.320	2197.9	22.35	134.73	65	75	350.6				
148.00		0.2188	28.981	19.974	2087.6	21.94	132.45	65	76	205.7				
150.00		0.2188	28.649	19.743	2016.1	21.68	130.94	65	76	135.1				
155.00		0.2188	27.819	19.167	1844.6	21.01	127.14	65	77	331.0				
158.00		0.2188	27.321	18.821	1746.6	20.61	124.87	65	77	193.9				
160.00		0.2188	26.988	18.590	1683.1	20.34	123.35	65	77	127.3				
165.00		0.2188	26.158	18.014	1531.4	19.67	119.55	65	78	311.4				
168.00		0.2188	25.660	17.668	1444.8	19.27	117.28	65	79	182.1				
168.50		0.2188	25.577	17.610	1430.7	19.20	116.90	65	79	30.0				
170.00		0.2188	25.328	17.437	1389.0	19.00	115.76	65	79	89.4				

Increment Length: 5 (ft)

Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in^2)	Ix (in^4)	W/t Ratio	D/t Ratio	Fy (ksi)	Fb (ksi)	Weight (lb)	Additional Reinforcing			
											Area (in^2)	Ixp (in^4)	Iyp (in^4)	Weight (lb)
175.00		0.2188	24.498	16.861	1255.7	18.33	111.97	65	80	291.8				
178.00	Top - Section 4	0.2188	24.000	16.515	1180.0	17.93	109.69	65	80	170.4				
178.00	Bot - Section 5	0.1875	24.000	14.171	1015.2	20.92	128.00	65	77					
180.00		0.1875	24.000	14.171	1015.2	21.16	128.00	65	77	96.4				
184.00		0.1875	24.000	14.171	1015.2	21.16	128.00	65	77	192.9				
185.00		0.1875	24.000	14.171	1015.2	21.16	128.00	65	77	48.2				
187.00		0.1875	24.000	14.171	1015.2	21.16	128.00	65	77	96.4				
188.00		0.1875	24.000	14.171	1015.2	21.16	128.00	65	77	48.2				
<b>Total Weight</b>										<b>28148.4</b>	<b>5642.0</b>			


## Wind Loading - Shaft

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	<b>7/31/2017</b>
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



**Load Case:** 1.2D + 1.6W 94 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.60



**Iterations** 29

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	18.266	20.09	379.43	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	18.266	20.09	373.34	0.650	0.000	5.00	21.715	14.11	453.8	0.0	1442.7
10.00		1.00	0.85	18.266	20.09	367.25	0.650	0.000	5.00	21.364	13.89	446.4	0.0	1419.1
15.00		1.00	0.85	18.266	20.09	361.17	0.650	0.000	5.00	21.013	13.66	439.1	0.0	1395.6
20.00		1.00	0.90	19.381	21.32	365.76	0.650	0.000	5.00	20.662	13.43	458.1	0.0	1372.1
25.00		1.00	0.95	20.313	22.34	368.03	0.650	0.000	5.00	20.310	13.20	472.0	0.0	1348.5
30.00		1.00	0.98	21.108	23.22	368.62	0.650	0.000	5.00	19.959	12.97	482.0	0.0	1325.0
32.83	RT1	1.00	1.00	21.512	23.66	368.39	0.650	0.000	2.83	11.141	7.24	274.2	0.0	739.5
35.00		1.00	1.01	21.804	23.98	367.99	0.650	0.000	2.17	8.467	5.50	211.2	0.0	561.9
40.00		1.00	1.04	22.426	24.67	366.46	0.650	0.000	5.00	19.257	12.52	494.0	0.0	1277.9
43.25	Bot - Section 2	1.00	1.06	22.798	25.08	365.06	0.650	0.000	3.25	12.329	8.01	321.5	0.0	818.0
45.00		1.00	1.07	22.989	25.29	364.20	0.650	0.000	1.75	6.688	4.35	175.9	0.0	817.3
48.92	RB2	1.00	1.09	23.397	25.74	362.02	0.650	0.000	3.92	14.825	9.64	396.8	0.0	1811.3
49.00	Top - Section 1	1.00	1.09	23.405	25.75	361.97	0.650	0.000	0.08	0.300	0.20	8.0	0.0	36.7
50.00		1.00	1.09	23.504	25.85	367.60	0.650	0.000	1.00	3.746	2.44	100.7	0.0	213.3
55.00		1.00	1.12	23.981	26.38	364.33	0.650	0.000	5.00	18.520	12.04	508.1	0.0	1054.6
60.00		1.00	1.14	24.424	26.87	360.64	0.650	0.000	5.00	18.169	11.81	507.7	0.0	1034.4
65.00		1.00	1.16	24.839	27.32	356.59	0.650	0.000	5.00	17.818	11.58	506.3	0.0	1014.2
70.00		1.00	1.17	25.230	27.75	352.23	0.650	0.000	5.00	17.467	11.35	504.1	0.0	994.1
75.00		1.00	1.19	25.599	28.16	347.59	0.650	0.000	5.00	17.115	11.13	501.2	0.0	973.9
76.83	RT2	1.00	1.20	25.729	28.30	345.83	0.650	0.000	1.83	6.176	4.01	181.8	0.0	351.4
80.00		1.00	1.21	25.949	28.54	342.70	0.650	0.000	3.17	10.588	6.88	314.3	0.0	602.3
85.00		1.00	1.22	26.282	28.91	337.60	0.650	0.000	5.00	16.413	10.67	493.5	0.0	933.6
87.50	Bot - Section 3	1.00	1.23	26.443	29.09	334.97	0.650	0.000	2.50	8.075	5.25	244.3	0.0	459.2
90.00		1.00	1.24	26.600	29.26	332.29	0.650	0.000	2.50	8.119	5.28	247.1	0.0	839.6
91.92	RB3	1.00	1.24	26.719	29.39	330.20	0.650	0.000	1.92	6.176	4.01	188.8	0.0	638.5
92.25	Top - Section 2	1.00	1.24	26.739	29.41	329.84	0.650	0.000	0.33	1.056	0.69	32.3	0.0	109.2
95.00		1.00	1.25	26.905	29.60	332.36	0.650	0.000	2.75	8.743	5.68	269.1	0.0	415.0
100.00		1.00	1.27	27.197	29.92	326.73	0.650	0.000	5.00	15.624	10.16	486.1	0.0	741.5
105.00		1.00	1.28	27.478	30.23	320.94	0.650	0.000	5.00	15.273	9.93	480.1	0.0	724.6
105.58	RT3	1.00	1.28	27.510	30.26	320.26	0.650	0.000	0.58	1.749	1.14	55.0	0.0	83.0
110.00		1.00	1.29	27.748	30.52	315.02	0.650	0.000	4.42	13.172	8.56	418.1	0.0	624.9
115.00		1.00	1.30	28.009	30.81	308.96	0.650	0.000	5.00	14.570	9.47	466.9	0.0	691.0
120.00		1.00	1.32	28.261	31.09	302.77	0.650	0.000	5.00	14.219	9.24	459.7	0.0	674.2
125.00		1.00	1.33	28.505	31.36	296.47	0.650	0.000	5.00	13.868	9.01	452.2	0.0	657.4
130.00		1.00	1.34	28.742	31.62	290.06	0.650	0.000	5.00	13.516	8.79	444.4	0.0	640.6
132.50	Bot - Section 4	1.00	1.34	28.857	31.74	286.82	0.650	0.000	2.50	6.627	4.31	218.8	0.0	314.0
135.00		1.00	1.35	28.971	31.87	283.55	0.650	0.000	2.50	6.631	4.31	219.8	0.0	530.5
136.50	Top - Section 3	1.00	1.35	29.038	31.94	281.57	0.650	0.000	1.50	3.937	2.56	130.8	0.0	314.8
140.00		1.00	1.36	29.193	32.11	281.00	0.650	0.000	3.50	9.063	5.89	302.7	0.0	301.5
145.00		1.00	1.37	29.410	32.35	274.31	0.650	0.000	5.00	12.648	8.22	425.5	0.0	420.7
148.00	Appurtenance(s)	1.00	1.37	29.537	32.49	270.26	0.650	0.000	3.00	7.420	4.82	250.7	0.0	246.8
150.00		1.00	1.38	29.621	32.58	267.54	0.650	0.000	2.00	4.877	3.17	165.2	0.0	162.2
155.00		1.00	1.39	29.826	32.81	260.69	0.650	0.000	5.00	11.946	7.76	407.6	0.0	397.2
158.00	Appurtenance(s)	1.00	1.39	29.946	32.94	256.54	0.650	0.000	3.00	6.999	4.55	239.8	0.0	232.7
160.00		1.00	1.40	30.026	33.03	253.75	0.650	0.000	2.00	4.596	2.99	157.9	0.0	152.8
165.00		1.00	1.41	30.221	33.24	246.75	0.650	0.000	5.00	11.243	7.31	388.7	0.0	373.7

## Wind Loading - Shaft

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II
		<b>Page:</b> 10



168.00 Appurtenance(s)	1.00	1.41	30.336	33.37	242.51	0.650	0.000	3.00	6.577	4.28	228.3	0.0	218.5
168.50 Appurtenance(s)	1.00	1.41	30.355	33.39	241.80	0.650	0.000	0.50	1.084	0.70	37.6	0.0	36.0
170.00	1.00	1.42	30.411	33.45	239.67	0.650	0.000	1.50	3.231	2.10	112.4	0.0	107.3
175.00	1.00	1.42	30.598	33.66	232.52	0.650	0.000	5.00	10.541	6.85	369.0	0.0	350.1
178.00 Top - Section 4	1.00	1.43	30.707	33.78	228.20	0.650	0.000	3.00	6.156	4.00	216.2	0.0	204.4
180.00	1.00	1.43	30.780	33.86	228.47	0.650	0.000	2.00	4.062	2.64	143.0	0.0	115.7
184.00 Appurtenance(s)	1.00	1.44	30.922	34.01	229.00	0.650	0.000	4.00	8.123	5.28	287.4	0.0	231.5
185.00	1.00	1.44	30.958	34.05	229.13	0.650	0.000	1.00	2.031	1.32	71.9	0.0	57.9
187.00 Appurtenance(s)	1.00	1.44	31.028	34.13	229.39	0.650	0.000	2.00	4.062	2.64	144.2	0.0	115.7
188.00	1.00	1.45	31.063	34.17	229.52	0.650	0.000	1.00	2.031	1.32	72.2	0.0	57.9
<b>Totals:</b>							<b>188.00</b>			<b>17,084.4</b>		<b>33,778.1</b>	

## Discrete Appurtenance Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 11

**Load Case:** 1.2D + 1.6W 94 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.60



**Iterations** 29

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	187.00	LNx-6515DS-A1M	3	31.028	34.131	0.64	0.80	22.02	179.28	0.000	0.000	1202.62	0.00	0.00
2	187.00	APXV18-209014	3	31.028	34.131	0.59	0.80	6.36	67.32	0.000	0.000	347.21	0.00	0.00
3	187.00	782 11054	3	31.028	34.131	0.54	0.80	0.35	6.48	0.000	0.000	19.32	0.00	0.00
4	187.00	KRY 112 144-1	12	31.028	34.131	0.54	0.80	2.64	158.40	0.000	0.000	144.01	0.00	0.00
5	187.00	APX16PV-16-PVL-E	3	31.028	34.131	0.50	0.80	8.97	142.56	0.000	0.000	489.99	0.00	0.00
6	184.00	Low Profile Platform	1	30.922	34.015	1.00	1.00	22.00	1800.00	0.000	0.000	1197.32	0.00	0.00
7	168.50	Low Profile Platform	1	30.355	33.390	1.00	1.00	22.00	1800.00	0.000	0.000	1175.34	0.00	0.00
8	168.00	APXV9ERR18-C-A20	1	30.336	33.369	0.66	0.80	5.33	74.40	0.000	0.000	284.32	0.00	0.00
9	168.00	ACU-A20-N	4	30.336	33.369	0.80	0.80	0.45	4.80	0.000	0.000	23.92	0.00	0.00
10	168.00	TD-RRH8x20-25	3	30.336	33.369	0.54	0.80	6.51	252.00	0.000	0.000	347.70	0.00	0.00
11	168.00	800 MHz RRH	3	30.336	33.369	0.54	0.80	4.73	194.40	0.000	0.000	252.41	0.00	0.00
12	168.00	1900 MHz RRH	3	30.336	33.369	0.54	0.80	4.73	158.40	0.000	0.000	252.41	0.00	0.00
13	168.00	APXVTM14-C-120	3	30.336	33.369	0.63	0.80	12.02	201.60	0.000	0.000	641.79	0.00	0.00
14	168.00	800 MHz Filters	3	30.336	33.369	0.54	0.80	4.73	194.40	0.000	0.000	252.41	0.00	0.00
15	168.00	APXVSP18-C-A20	2	30.336	33.369	0.66	0.80	10.65	136.80	0.000	0.000	568.64	0.00	0.00
16	158.00	T-Arm	3	29.946	32.941	0.50	0.75	12.06	1080.00	0.000	0.000	635.63	0.00	0.00
17	158.00	SBNH-1D6565C	1	29.946	32.941	0.64	0.80	7.34	79.32	0.000	0.000	386.90	0.00	0.00
18	158.00	P65-17-XLH-RR	2	29.946	32.941	0.60	0.80	13.73	141.60	0.000	0.000	723.54	0.00	0.00
19	158.00	LGP21401	6	29.946	32.941	0.54	0.80	4.05	126.00	0.000	0.000	213.57	0.00	0.00
20	158.00	RRUS-11	6	29.946	32.941	0.54	0.80	8.10	365.04	0.000	0.000	427.14	0.00	0.00
21	158.00	7770	3	29.946	32.941	0.58	0.80	9.64	126.00	0.000	0.000	507.87	0.00	0.00
22	158.00	DC-48-60-18-8F	1	29.946	32.941	0.80	0.80	1.18	38.16	0.000	0.000	61.98	0.00	0.00
23	148.00	742 213	3	29.537	32.491	0.58	0.80	8.85	79.20	0.000	0.000	459.93	0.00	0.00
24	148.00	Flush Mount	1	29.537	32.491	1.00	1.00	5.00	180.00	0.000	0.000	259.93	0.00	0.00
<b>Totals:</b>									<b>7,586.16</b>			<b>10,875.91</b>		

## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 12

**Load Case:** 1.2D + 1.6W 94 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.60



**Iterations** 29

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		453.76	1666.46	0.00	0.00
10.00		446.42	1642.93	0.00	0.00
15.00		439.09	1619.39	0.00	0.00
20.00		458.10	1595.86	0.00	0.00
25.00		471.97	1572.33	0.00	0.00
30.00		481.96	1548.79	0.00	0.00
32.83		274.19	866.19	0.00	0.00
35.00		211.19	659.07	0.00	0.00
40.00		494.03	1501.72	0.00	0.00
43.25		321.53	963.50	0.00	0.00
45.00		175.89	895.62	0.00	0.00
48.92		396.80	1986.76	0.00	0.00
49.00		8.04	40.27	0.00	0.00
50.00		100.73	258.10	0.00	0.00
55.00		508.09	1278.39	0.00	0.00
60.00		507.67	1258.22	0.00	0.00
65.00		506.31	1238.05	0.00	0.00
70.00		504.14	1217.87	0.00	0.00
75.00		501.23	1197.70	0.00	0.00
76.83		181.80	433.32	0.00	0.00
80.00		314.31	744.21	0.00	0.00
85.00		493.49	1157.36	0.00	0.00
87.50		244.27	571.11	0.00	0.00
90.00		247.08	951.51	0.00	0.00
91.92		188.78	724.48	0.00	0.00
92.25		32.31	123.97	0.00	0.00
95.00		269.10	538.06	0.00	0.00
100.00		486.11	965.26	0.00	0.00
105.00		480.09	948.45	0.00	0.00
105.58		55.04	108.93	0.00	0.00
110.00		418.15	822.70	0.00	0.00
115.00		466.86	914.82	0.00	0.00
120.00		459.71	898.01	0.00	0.00
125.00		452.23	881.20	0.00	0.00
130.00		444.43	864.39	0.00	0.00
132.50		218.76	425.89	0.00	0.00
135.00		219.78	642.36	0.00	0.00
136.50		130.77	381.99	0.00	0.00
140.00		302.66	458.18	0.00	0.00
145.00		425.54	644.54	0.00	0.00
148.00	(4) attachments	970.59	640.28	0.00	0.00
150.00		165.25	236.72	0.00	0.00
155.00		407.59	583.56	0.00	0.00
158.00	(22) attachments	3196.41	2300.61	0.00	0.00
160.00		157.86	203.02	0.00	0.00
165.00		388.70	499.30	0.00	0.00



## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 13

168.00	(22) attachments	2851.86	1510.73	0.00	0.00
168.50	(1) attachments	1212.98	1847.24	0.00	0.00
170.00		112.40	141.03	0.00	0.00
175.00		368.96	462.44	0.00	0.00
178.00		216.25	271.82	0.00	0.00
180.00		143.02	160.66	0.00	0.00
184.00	(1) attachments	1484.68	2121.31	0.00	0.00
185.00		71.92	80.33	0.00	0.00
187.00	(24) attachments	2347.32	714.70	0.00	0.00
188.00		72.17	57.86	0.00	0.00
<b>Totals:</b>		<b>27,960.36</b>	<b>49,039.58</b>	<b>0.00</b>	<b>0.00</b>

## Linear Appurtenance Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 14

**Load Case:** 1.2D + 1.6W 94 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.60



**Iterations** 29

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.062	0.000	18.266	0.00	37.44
5.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.062	0.000	18.266	0.00	0.00
10.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.063	0.000	18.266	0.00	37.44
10.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.063	0.000	18.266	0.00	0.00
15.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.064	0.000	18.266	0.00	37.44
15.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.064	0.000	18.266	0.00	0.00
20.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.065	0.000	19.381	0.00	37.44
20.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.065	0.000	19.381	0.00	0.00
25.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.066	0.000	20.313	0.00	37.44
25.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.066	0.000	20.313	0.00	0.00
30.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.067	0.000	21.108	0.00	37.44
30.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.067	0.000	21.108	0.00	0.00
32.83	1 5/8" Coax	Yes	2.83	0.000	1.98	0.47	0.00	0.068	0.000	21.512	0.00	21.19
32.83	1.25" Reinforcing	Yes	2.83	0.000	1.25	0.29	0.00	0.068	0.000	21.512	0.00	0.00
35.00	1 5/8" Coax	Yes	2.17	0.000	1.98	0.36	0.00	0.069	0.000	21.804	0.00	16.25
35.00	1.25" Reinforcing	Yes	2.17	0.000	1.25	0.23	0.00	0.069	0.000	21.804	0.00	0.00
40.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.046	0.000	22.426	0.00	37.44
40.00	1.25" Reinforcing	Yes	0.50	0.000	1.25	0.05	0.00	0.046	0.000	22.426	0.00	0.00
43.25	1 5/8" Coax	Yes	3.25	0.000	1.98	0.54	0.00	0.043	0.000	22.798	0.00	24.34
45.00	1 5/8" Coax	Yes	1.75	0.000	1.98	0.29	0.00	0.044	0.000	22.989	0.00	13.10
48.92	1 5/8" Coax	Yes	3.92	0.000	1.98	0.65	0.00	0.062	0.000	23.397	0.00	29.35
48.92	1.25" Reinforcing	Yes	2.42	0.000	1.25	0.25	0.00	0.062	0.000	23.397	0.00	0.00
49.00	1 5/8" Coax	Yes	0.08	0.000	1.98	0.01	0.00	0.073	0.000	23.405	0.00	0.60
49.00	1.25" Reinforcing	Yes	0.08	0.000	1.25	0.01	0.00	0.073	0.000	23.405	0.00	0.00
50.00	1 5/8" Coax	Yes	1.00	0.000	1.98	0.17	0.00	0.072	0.000	23.504	0.00	7.49
50.00	1.25" Reinforcing	Yes	1.00	0.000	1.25	0.10	0.00	0.072	0.000	23.504	0.00	0.00
55.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.073	0.000	23.981	0.00	37.44
55.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.073	0.000	23.981	0.00	0.00
60.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.074	0.000	24.424	0.00	37.44
60.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.074	0.000	24.424	0.00	0.00
65.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.076	0.000	24.839	0.00	37.44
65.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.076	0.000	24.839	0.00	0.00
70.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.077	0.000	25.230	0.00	37.44
70.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.077	0.000	25.230	0.00	0.00
75.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.079	0.000	25.599	0.00	37.44
75.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.079	0.000	25.599	0.00	0.00
76.83	1 5/8" Coax	Yes	1.83	0.000	1.98	0.30	0.00	0.080	0.000	25.729	0.00	13.70
76.83	1.25" Reinforcing	Yes	1.83	0.000	1.25	0.19	0.00	0.080	0.000	25.729	0.00	0.00
80.00	1 5/8" Coax	Yes	3.17	0.000	1.98	0.52	0.00	0.073	0.000	25.949	0.00	23.74
80.00	1.25" Reinforcing	Yes	2.42	0.000	1.25	0.25	0.00	0.073	0.000	25.949	0.00	0.00
85.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.050	0.000	26.282	0.00	37.44
87.50	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.051	0.000	26.443	0.00	18.72
90.00	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.052	0.000	26.600	0.00	18.72
91.92	1 5/8" Coax	Yes	1.92	0.000	1.98	0.32	0.00	0.081	0.000	26.719	0.00	14.38
91.92	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.17	0.00	0.081	0.000	26.719	0.00	0.00
92.25	1 5/8" Coax	Yes	0.33	0.000	1.98	0.05	0.00	0.086	0.000	26.739	0.00	2.47
92.25	1.25" Reinforcing	Yes	0.33	0.000	1.25	0.03	0.00	0.086	0.000	26.739	0.00	0.00

## Linear Appurtenance Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II




Page: 15

**Load Case:** 1.2D + 1.6W 94 mph Wind

**Dead Load Factor** 1.20

**Wind Load Factor** 1.60



**Iterations** 29

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
95.00	1 5/8" Coax	Yes	2.75	0.000	1.98	0.45	0.00	0.085	0.000	26.905	0.00	20.59
95.00	1.25" Reinforcing	Yes	2.75	0.000	1.25	0.29	0.00	0.085	0.000	26.905	0.00	0.00
100.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.086	0.000	27.197	0.00	37.44
100.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.086	0.000	27.197	0.00	0.00
105.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.088	0.000	27.478	0.00	37.44
105.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.088	0.000	27.478	0.00	0.00
105.58	1 5/8" Coax	Yes	0.58	0.000	1.98	0.10	0.00	0.089	0.000	27.510	0.00	4.34
105.58	1.25" Reinforcing	Yes	0.58	0.000	1.25	0.06	0.00	0.089	0.000	27.510	0.00	0.00
110.00	1 5/8" Coax	Yes	4.42	0.000	1.98	0.73	0.00	0.069	0.000	27.748	0.00	33.10
110.00	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.17	0.00	0.069	0.000	27.748	0.00	0.00
115.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.057	0.000	28.009	0.00	37.44
120.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.058	0.000	28.261	0.00	37.44
125.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.059	0.000	28.505	0.00	37.44
130.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.061	0.000	28.742	0.00	37.44
132.50	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.062	0.000	28.857	0.00	18.72
135.00	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.063	0.000	28.971	0.00	18.72
136.50	1 5/8" Coax	Yes	1.50	0.000	1.98	0.25	0.00	0.064	0.000	29.038	0.00	11.23
140.00	1 5/8" Coax	Yes	3.50	0.000	1.98	0.58	0.00	0.064	0.000	29.193	0.00	26.21
145.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.065	0.000	29.410	0.00	37.44
148.00	1 5/8" Coax	Yes	3.00	0.000	1.98	0.49	0.00	0.067	0.000	29.537	0.00	22.46
<b>Totals:</b>											<b>0.0</b>	<b>1,108.2</b>



## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Page:</b> 17
	<b>Struct Class:</b> II	



160.00	-6.81	-10.07	0.00	-163.78	0.00	163.78	1296.30	648.15	1425.45	713.78	99.37	-6.216	0.000	0.235
165.00	-6.34	-9.64	0.00	-113.41	0.00	113.41	1268.86	634.43	1351.65	676.83	105.93	-6.333	0.000	0.173
168.00	-5.15	-6.64	0.00	-84.48	0.00	84.48	1252.00	626.00	1307.87	654.91	109.92	-6.388	0.000	0.133
168.50	-3.45	-5.23	0.00	-81.16	0.00	81.16	1249.16	624.58	1300.61	651.27	110.59	-6.396	0.000	0.127
170.00	-3.32	-5.11	0.00	-73.31	0.00	73.31	1240.60	620.30	1278.90	640.40	112.60	-6.419	0.000	0.117
175.00	-2.89	-4.69	0.00	-47.76	0.00	47.76	1211.52	605.76	1207.28	604.54	119.34	-6.481	0.000	0.081
178.00	-2.65	-4.45	0.00	-33.68	0.00	33.68	1193.69	596.84	1164.89	583.31	123.41	-6.509	0.000	0.060
178.00	-2.65	-4.45	0.00	-33.68	0.00	33.68	975.84	487.92	954.81	478.11	123.41	-6.509	0.000	0.073
180.00	-2.50	-4.29	0.00	-24.79	0.00	24.79	975.84	487.92	954.81	478.11	126.14	-6.523	0.000	0.054
184.00	-0.56	-2.57	0.00	-7.63	0.00	7.63	975.84	487.92	954.81	478.11	131.60	-6.541	0.000	0.017
185.00	-0.49	-2.49	0.00	-5.06	0.00	5.06	975.84	487.92	954.81	478.11	132.97	-6.543	0.000	0.011
187.00	-0.05	-0.08	0.00	-0.08	0.00	0.08	975.84	487.92	954.81	478.11	135.70	-6.544	0.000	0.000
188.00	0.00	-0.07	0.00	0.00	0.00	0.00	975.84	487.92	954.81	478.11	137.07	-6.544	0.000	0.000


## Wind Loading - Shaft

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



**Load Case:** 0.9D + 1.6W 94 mph Wind

**Dead Load Factor** 0.90  
**Wind Load Factor** 1.60



**Iterations** 29

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	18.266	20.09	379.43	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	18.266	20.09	373.34	0.650	0.000	5.00	21.715	14.11	453.8	0.0	1082.0
10.00		1.00	0.85	18.266	20.09	367.25	0.650	0.000	5.00	21.364	13.89	446.4	0.0	1064.3
15.00		1.00	0.85	18.266	20.09	361.17	0.650	0.000	5.00	21.013	13.66	439.1	0.0	1046.7
20.00		1.00	0.90	19.381	21.32	365.76	0.650	0.000	5.00	20.662	13.43	458.1	0.0	1029.0
25.00		1.00	0.95	20.313	22.34	368.03	0.650	0.000	5.00	20.310	13.20	472.0	0.0	1011.4
30.00		1.00	0.98	21.108	23.22	368.62	0.650	0.000	5.00	19.959	12.97	482.0	0.0	993.7
32.83	RT1	1.00	1.00	21.512	23.66	368.39	0.650	0.000	2.83	11.141	7.24	274.2	0.0	554.6
35.00		1.00	1.01	21.804	23.98	367.99	0.650	0.000	2.17	8.467	5.50	211.2	0.0	421.5
40.00		1.00	1.04	22.426	24.67	366.46	0.650	0.000	5.00	19.257	12.52	494.0	0.0	958.4
43.25	Bot - Section 2	1.00	1.06	22.798	25.08	365.06	0.650	0.000	3.25	12.329	8.01	321.5	0.0	613.5
45.00		1.00	1.07	22.989	25.29	364.20	0.650	0.000	1.75	6.688	4.35	175.9	0.0	613.0
48.92	RB2	1.00	1.09	23.397	25.74	362.02	0.650	0.000	3.92	14.825	9.64	396.8	0.0	1358.5
49.00	Top - Section 1	1.00	1.09	23.405	25.75	361.97	0.650	0.000	0.08	0.300	0.20	8.0	0.0	27.5
50.00		1.00	1.09	23.504	25.85	367.60	0.650	0.000	1.00	3.746	2.44	100.7	0.0	160.0
55.00		1.00	1.12	23.981	26.38	364.33	0.650	0.000	5.00	18.520	12.04	508.1	0.0	790.9
60.00		1.00	1.14	24.424	26.87	360.64	0.650	0.000	5.00	18.169	11.81	507.7	0.0	775.8
65.00		1.00	1.16	24.839	27.32	356.59	0.650	0.000	5.00	17.818	11.58	506.3	0.0	760.7
70.00		1.00	1.17	25.230	27.75	352.23	0.650	0.000	5.00	17.467	11.35	504.1	0.0	745.6
75.00		1.00	1.19	25.599	28.16	347.59	0.650	0.000	5.00	17.115	11.13	501.2	0.0	730.4
76.83	RT2	1.00	1.20	25.729	28.30	345.83	0.650	0.000	1.83	6.176	4.01	181.8	0.0	263.6
80.00		1.00	1.21	25.949	28.54	342.70	0.650	0.000	3.17	10.588	6.88	314.3	0.0	451.7
85.00		1.00	1.22	26.282	28.91	337.60	0.650	0.000	5.00	16.413	10.67	493.5	0.0	700.2
87.50	Bot - Section 3	1.00	1.23	26.443	29.09	334.97	0.650	0.000	2.50	8.075	5.25	244.3	0.0	344.4
90.00		1.00	1.24	26.600	29.26	332.29	0.650	0.000	2.50	8.119	5.28	247.1	0.0	629.7
91.92	RB3	1.00	1.24	26.719	29.39	330.20	0.650	0.000	1.92	6.176	4.01	188.8	0.0	478.9
92.25	Top - Section 2	1.00	1.24	26.739	29.41	329.84	0.650	0.000	0.33	1.056	0.69	32.3	0.0	81.9
95.00		1.00	1.25	26.905	29.60	332.36	0.650	0.000	2.75	8.743	5.68	269.1	0.0	311.2
100.00		1.00	1.27	27.197	29.92	326.73	0.650	0.000	5.00	15.624	10.16	486.1	0.0	556.1
105.00		1.00	1.28	27.478	30.23	320.94	0.650	0.000	5.00	15.273	9.93	480.1	0.0	543.5
105.58	RT3	1.00	1.28	27.510	30.26	320.26	0.650	0.000	0.58	1.749	1.14	55.0	0.0	62.2
110.00		1.00	1.29	27.748	30.52	315.02	0.650	0.000	4.42	13.172	8.56	418.1	0.0	468.6
115.00		1.00	1.30	28.009	30.81	308.96	0.650	0.000	5.00	14.570	9.47	466.9	0.0	518.3
120.00		1.00	1.32	28.261	31.09	302.77	0.650	0.000	5.00	14.219	9.24	459.7	0.0	505.7
125.00		1.00	1.33	28.505	31.36	296.47	0.650	0.000	5.00	13.868	9.01	452.2	0.0	493.1
130.00		1.00	1.34	28.742	31.62	290.06	0.650	0.000	5.00	13.516	8.79	444.4	0.0	480.4
132.50	Bot - Section 4	1.00	1.34	28.857	31.74	286.82	0.650	0.000	2.50	6.627	4.31	218.8	0.0	235.5
135.00		1.00	1.35	28.971	31.87	283.55	0.650	0.000	2.50	6.631	4.31	219.8	0.0	397.8
136.50	Top - Section 3	1.00	1.35	29.038	31.94	281.57	0.650	0.000	1.50	3.937	2.56	130.8	0.0	236.1
140.00		1.00	1.36	29.193	32.11	281.00	0.650	0.000	3.50	9.063	5.89	302.7	0.0	226.1
145.00		1.00	1.37	29.410	32.35	274.31	0.650	0.000	5.00	12.648	8.22	425.5	0.0	315.6
148.00	Appurtenance(s)	1.00	1.37	29.537	32.49	270.26	0.650	0.000	3.00	7.420	4.82	250.7	0.0	185.1
150.00		1.00	1.38	29.621	32.58	267.54	0.650	0.000	2.00	4.877	3.17	165.2	0.0	121.6
155.00		1.00	1.39	29.826	32.81	260.69	0.650	0.000	5.00	11.946	7.76	407.6	0.0	297.9
158.00	Appurtenance(s)	1.00	1.39	29.946	32.94	256.54	0.650	0.000	3.00	6.999	4.55	239.8	0.0	174.5
160.00		1.00	1.40	30.026	33.03	253.75	0.650	0.000	2.00	4.596	2.99	157.9	0.0	114.6
165.00		1.00	1.41	30.221	33.24	246.75	0.650	0.000	5.00	11.243	7.31	388.7	0.0	280.2

## Wind Loading - Shaft

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 19

168.00 Appurtenance(s)	1.00	1.41	30.336	33.37	242.51	0.650	0.000	3.00	6.577	4.28	228.3	0.0	163.9
168.50 Appurtenance(s)	1.00	1.41	30.355	33.39	241.80	0.650	0.000	0.50	1.084	0.70	37.6	0.0	27.0
170.00	1.00	1.42	30.411	33.45	239.67	0.650	0.000	1.50	3.231	2.10	112.4	0.0	80.5
175.00	1.00	1.42	30.598	33.66	232.52	0.650	0.000	5.00	10.541	6.85	369.0	0.0	262.6
178.00 Top - Section 4	1.00	1.43	30.707	33.78	228.20	0.650	0.000	3.00	6.156	4.00	216.2	0.0	153.3
180.00	1.00	1.43	30.780	33.86	228.47	0.650	0.000	2.00	4.062	2.64	143.0	0.0	86.8
184.00 Appurtenance(s)	1.00	1.44	30.922	34.01	229.00	0.650	0.000	4.00	8.123	5.28	287.4	0.0	173.6
185.00	1.00	1.44	30.958	34.05	229.13	0.650	0.000	1.00	2.031	1.32	71.9	0.0	43.4
187.00 Appurtenance(s)	1.00	1.44	31.028	34.13	229.39	0.650	0.000	2.00	4.062	2.64	144.2	0.0	86.8
188.00	1.00	1.45	31.063	34.17	229.52	0.650	0.000	1.00	2.031	1.32	72.2	0.0	43.4
<b>Totals:</b>							<b>188.00</b>			<b>17,084.4</b>		<b>25,333.6</b>	

## Discrete Appurtenance Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 20

**Load Case:** 0.9D + 1.6W 94 mph Wind

**Dead Load Factor** 0.90  
**Wind Load Factor** 1.60



**Iterations** 29

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	187.00	LNx-6515DS-A1M	3	31.028	34.131	0.64	0.80	22.02	134.46	0.000	0.000	1202.62	0.00	0.00
2	187.00	APXV18-209014	3	31.028	34.131	0.59	0.80	6.36	50.49	0.000	0.000	347.21	0.00	0.00
3	187.00	782 11054	3	31.028	34.131	0.54	0.80	0.35	4.86	0.000	0.000	19.32	0.00	0.00
4	187.00	KRY 112 144-1	12	31.028	34.131	0.54	0.80	2.64	118.80	0.000	0.000	144.01	0.00	0.00
5	187.00	APX16PV-16-PVL-E	3	31.028	34.131	0.50	0.80	8.97	106.92	0.000	0.000	489.99	0.00	0.00
6	184.00	Low Profile Platform	1	30.922	34.015	1.00	1.00	22.00	1350.00	0.000	0.000	1197.32	0.00	0.00
7	168.50	Low Profile Platform	1	30.355	33.390	1.00	1.00	22.00	1350.00	0.000	0.000	1175.34	0.00	0.00
8	168.00	APXV9ERR18-C-A20	1	30.336	33.369	0.66	0.80	5.33	55.80	0.000	0.000	284.32	0.00	0.00
9	168.00	ACU-A20-N	4	30.336	33.369	0.80	0.80	0.45	3.60	0.000	0.000	23.92	0.00	0.00
10	168.00	TD-RRH8x20-25	3	30.336	33.369	0.54	0.80	6.51	189.00	0.000	0.000	347.70	0.00	0.00
11	168.00	800 MHz RRH	3	30.336	33.369	0.54	0.80	4.73	145.80	0.000	0.000	252.41	0.00	0.00
12	168.00	1900 MHz RRH	3	30.336	33.369	0.54	0.80	4.73	118.80	0.000	0.000	252.41	0.00	0.00
13	168.00	APXVTM14-C-120	3	30.336	33.369	0.63	0.80	12.02	151.20	0.000	0.000	641.79	0.00	0.00
14	168.00	800 MHz Filters	3	30.336	33.369	0.54	0.80	4.73	145.80	0.000	0.000	252.41	0.00	0.00
15	168.00	APXVSP18-C-A20	2	30.336	33.369	0.66	0.80	10.65	102.60	0.000	0.000	568.64	0.00	0.00
16	158.00	T-Arm	3	29.946	32.941	0.50	0.75	12.06	810.00	0.000	0.000	635.63	0.00	0.00
17	158.00	SBNH-1D6565C	1	29.946	32.941	0.64	0.80	7.34	59.49	0.000	0.000	386.90	0.00	0.00
18	158.00	P65-17-XLH-RR	2	29.946	32.941	0.60	0.80	13.73	106.20	0.000	0.000	723.54	0.00	0.00
19	158.00	LGP21401	6	29.946	32.941	0.54	0.80	4.05	94.50	0.000	0.000	213.57	0.00	0.00
20	158.00	RRUS-11	6	29.946	32.941	0.54	0.80	8.10	273.78	0.000	0.000	427.14	0.00	0.00
21	158.00	7770	3	29.946	32.941	0.58	0.80	9.64	94.50	0.000	0.000	507.87	0.00	0.00
22	158.00	DC-48-60-18-8F	1	29.946	32.941	0.80	0.80	1.18	28.62	0.000	0.000	61.98	0.00	0.00
23	148.00	742 213	3	29.537	32.491	0.58	0.80	8.85	59.40	0.000	0.000	459.93	0.00	0.00
24	148.00	Flush Mount	1	29.537	32.491	1.00	1.00	5.00	135.00	0.000	0.000	259.93	0.00	0.00
<b>Totals:</b>									<b>5,689.62</b>			<b>10,875.91</b>		



## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II




Page: 21

**Load Case:** 0.9D + 1.6W 94 mph Wind

**Dead Load Factor** 0.90

**Wind Load Factor** 1.60



**Iterations** 29

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		453.76	1249.85	0.00	0.00
10.00		446.42	1232.20	0.00	0.00
15.00		439.09	1214.55	0.00	0.00
20.00		458.10	1196.89	0.00	0.00
25.00		471.97	1179.24	0.00	0.00
30.00		481.96	1161.59	0.00	0.00
32.83		274.19	649.64	0.00	0.00
35.00		211.19	494.30	0.00	0.00
40.00		494.03	1126.29	0.00	0.00
43.25		321.53	722.62	0.00	0.00
45.00		175.89	671.72	0.00	0.00
48.92		396.80	1490.07	0.00	0.00
49.00		8.04	30.20	0.00	0.00
50.00		100.73	193.57	0.00	0.00
55.00		508.09	958.79	0.00	0.00
60.00		507.67	943.66	0.00	0.00
65.00		506.31	928.53	0.00	0.00
70.00		504.14	913.40	0.00	0.00
75.00		501.23	898.28	0.00	0.00
76.83		181.80	324.99	0.00	0.00
80.00		314.31	558.16	0.00	0.00
85.00		493.49	868.02	0.00	0.00
87.50		244.27	428.34	0.00	0.00
90.00		247.08	713.63	0.00	0.00
91.92		188.78	543.36	0.00	0.00
92.25		32.31	92.98	0.00	0.00
95.00		269.10	403.54	0.00	0.00
100.00		486.11	723.94	0.00	0.00
105.00		480.09	711.33	0.00	0.00
105.58		55.04	81.70	0.00	0.00
110.00		418.15	617.03	0.00	0.00
115.00		466.86	686.12	0.00	0.00
120.00		459.71	673.51	0.00	0.00
125.00		452.23	660.90	0.00	0.00
130.00		444.43	648.30	0.00	0.00
132.50		218.76	319.42	0.00	0.00
135.00		219.78	481.77	0.00	0.00
136.50		130.77	286.49	0.00	0.00
140.00		302.66	343.64	0.00	0.00
145.00		425.54	483.41	0.00	0.00
148.00	(4) attachments	970.59	480.21	0.00	0.00
150.00		165.25	177.54	0.00	0.00
155.00		407.59	437.67	0.00	0.00
158.00	(22) attachments	3196.41	1725.46	0.00	0.00
160.00		157.86	152.26	0.00	0.00
165.00		388.70	374.48	0.00	0.00

## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 22

168.00	(22) attachments	2851.86	1133.05	0.00	0.00
168.50	(1) attachments	1212.98	1385.43	0.00	0.00
170.00		112.40	105.77	0.00	0.00
175.00		368.96	346.83	0.00	0.00
178.00		216.25	203.86	0.00	0.00
180.00		143.02	120.49	0.00	0.00
184.00	(1) attachments	1484.68	1590.99	0.00	0.00
185.00		71.92	60.25	0.00	0.00
187.00	(24) attachments	2347.32	536.02	0.00	0.00
188.00		72.17	43.40	0.00	0.00
<b>Totals:</b>		<b>27,960.36</b>	<b>36,779.69</b>	<b>0.00</b>	<b>0.00</b>

## Linear Appurtenance Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 23

**Load Case:** 0.9D + 1.6W 94 mph Wind

**Dead Load Factor** 0.90  
**Wind Load Factor** 1.60



**Iterations** 29

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.062	0.000	18.266	0.00	28.08
5.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.062	0.000	18.266	0.00	0.00
10.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.063	0.000	18.266	0.00	28.08
10.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.063	0.000	18.266	0.00	0.00
15.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.064	0.000	18.266	0.00	28.08
15.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.064	0.000	18.266	0.00	0.00
20.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.065	0.000	19.381	0.00	28.08
20.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.065	0.000	19.381	0.00	0.00
25.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.066	0.000	20.313	0.00	28.08
25.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.066	0.000	20.313	0.00	0.00
30.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.067	0.000	21.108	0.00	28.08
30.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.067	0.000	21.108	0.00	0.00
32.83	1 5/8" Coax	Yes	2.83	0.000	1.98	0.47	0.00	0.068	0.000	21.512	0.00	15.89
32.83	1.25" Reinforcing	Yes	2.83	0.000	1.25	0.29	0.00	0.068	0.000	21.512	0.00	0.00
35.00	1 5/8" Coax	Yes	2.17	0.000	1.98	0.36	0.00	0.069	0.000	21.804	0.00	12.19
35.00	1.25" Reinforcing	Yes	2.17	0.000	1.25	0.23	0.00	0.069	0.000	21.804	0.00	0.00
40.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.046	0.000	22.426	0.00	28.08
40.00	1.25" Reinforcing	Yes	0.50	0.000	1.25	0.05	0.00	0.046	0.000	22.426	0.00	0.00
43.25	1 5/8" Coax	Yes	3.25	0.000	1.98	0.54	0.00	0.043	0.000	22.798	0.00	18.25
45.00	1 5/8" Coax	Yes	1.75	0.000	1.98	0.29	0.00	0.044	0.000	22.989	0.00	9.83
48.92	1 5/8" Coax	Yes	3.92	0.000	1.98	0.65	0.00	0.062	0.000	23.397	0.00	22.01
48.92	1.25" Reinforcing	Yes	2.42	0.000	1.25	0.25	0.00	0.062	0.000	23.397	0.00	0.00
49.00	1 5/8" Coax	Yes	0.08	0.000	1.98	0.01	0.00	0.073	0.000	23.405	0.00	0.45
49.00	1.25" Reinforcing	Yes	0.08	0.000	1.25	0.01	0.00	0.073	0.000	23.405	0.00	0.00
50.00	1 5/8" Coax	Yes	1.00	0.000	1.98	0.17	0.00	0.072	0.000	23.504	0.00	5.62
50.00	1.25" Reinforcing	Yes	1.00	0.000	1.25	0.10	0.00	0.072	0.000	23.504	0.00	0.00
55.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.073	0.000	23.981	0.00	28.08
55.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.073	0.000	23.981	0.00	0.00
60.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.074	0.000	24.424	0.00	28.08
60.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.074	0.000	24.424	0.00	0.00
65.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.076	0.000	24.839	0.00	28.08
65.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.076	0.000	24.839	0.00	0.00
70.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.077	0.000	25.230	0.00	28.08
70.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.077	0.000	25.230	0.00	0.00
75.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.079	0.000	25.599	0.00	28.08
75.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.079	0.000	25.599	0.00	0.00
76.83	1 5/8" Coax	Yes	1.83	0.000	1.98	0.30	0.00	0.080	0.000	25.729	0.00	10.28
76.83	1.25" Reinforcing	Yes	1.83	0.000	1.25	0.19	0.00	0.080	0.000	25.729	0.00	0.00
80.00	1 5/8" Coax	Yes	3.17	0.000	1.98	0.52	0.00	0.073	0.000	25.949	0.00	17.80
80.00	1.25" Reinforcing	Yes	2.42	0.000	1.25	0.25	0.00	0.073	0.000	25.949	0.00	0.00
85.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.050	0.000	26.282	0.00	28.08
87.50	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.051	0.000	26.443	0.00	14.04
90.00	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.052	0.000	26.600	0.00	14.04
91.92	1 5/8" Coax	Yes	1.92	0.000	1.98	0.32	0.00	0.081	0.000	26.719	0.00	10.78
91.92	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.17	0.00	0.081	0.000	26.719	0.00	0.00
92.25	1 5/8" Coax	Yes	0.33	0.000	1.98	0.05	0.00	0.086	0.000	26.739	0.00	1.85
92.25	1.25" Reinforcing	Yes	0.33	0.000	1.25	0.03	0.00	0.086	0.000	26.739	0.00	0.00

## Linear Appurtenance Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II




Page: 24

**Load Case:** 0.9D + 1.6W 94 mph Wind

**Dead Load Factor** 0.90

**Wind Load Factor** 1.60



**Iterations** 29

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
95.00	1 5/8" Coax	Yes	2.75	0.000	1.98	0.45	0.00	0.085	0.000	26.905	0.00	15.44
95.00	1.25" Reinforcing	Yes	2.75	0.000	1.25	0.29	0.00	0.085	0.000	26.905	0.00	0.00
100.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.086	0.000	27.197	0.00	28.08
100.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.086	0.000	27.197	0.00	0.00
105.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.088	0.000	27.478	0.00	28.08
105.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.088	0.000	27.478	0.00	0.00
105.58	1 5/8" Coax	Yes	0.58	0.000	1.98	0.10	0.00	0.089	0.000	27.510	0.00	3.26
105.58	1.25" Reinforcing	Yes	0.58	0.000	1.25	0.06	0.00	0.089	0.000	27.510	0.00	0.00
110.00	1 5/8" Coax	Yes	4.42	0.000	1.98	0.73	0.00	0.069	0.000	27.748	0.00	24.82
110.00	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.17	0.00	0.069	0.000	27.748	0.00	0.00
115.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.057	0.000	28.009	0.00	28.08
120.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.058	0.000	28.261	0.00	28.08
125.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.059	0.000	28.505	0.00	28.08
130.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.061	0.000	28.742	0.00	28.08
132.50	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.062	0.000	28.857	0.00	14.04
135.00	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.063	0.000	28.971	0.00	14.04
136.50	1 5/8" Coax	Yes	1.50	0.000	1.98	0.25	0.00	0.064	0.000	29.038	0.00	8.42
140.00	1 5/8" Coax	Yes	3.50	0.000	1.98	0.58	0.00	0.064	0.000	29.193	0.00	19.66
145.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.065	0.000	29.410	0.00	28.08
148.00	1 5/8" Coax	Yes	3.00	0.000	1.98	0.49	0.00	0.067	0.000	29.537	0.00	16.85
<b>Totals:</b>											<b>0.0</b>	<b>831.2</b>

## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II




Page: 25

**Load Case:** 0.9D + 1.6W 94 mph Wind

**Iterations** 29

**Dead Load Factor** 0.90

**Wind Load Factor** 1.60



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-36.74	-28.01	0.00	-3541.4	0.00	3541.49	5035.03	2517.52	10606.9	5311.37	0.00	0.000	0.000	0.505
5.00	-35.42	-27.65	0.00	-3401.4	0.00	3401.44	4978.38	2489.19	10316.4	5165.91	0.08	-0.156	0.000	0.497
10.00	-34.11	-27.29	0.00	-3263.1	0.00	3263.18	4920.91	2460.46	10028.2	5021.57	0.33	-0.313	0.000	0.488
15.00	-32.83	-26.94	0.00	-3126.7	0.00	3126.72	4862.63	2431.31	9742.31	4878.39	0.74	-0.470	0.000	0.479
20.00	-31.56	-26.55	0.00	-2992.0	0.00	2992.03	4803.53	2401.76	9458.77	4736.42	1.32	-0.628	0.000	0.470
25.00	-30.31	-26.15	0.00	-2859.2	0.00	2859.26	4743.61	2371.81	9177.73	4595.68	2.06	-0.786	0.000	0.460
30.00	-29.11	-25.71	0.00	-2728.5	0.00	2728.51	4682.88	2341.44	8899.25	4456.24	2.97	-0.944	0.000	0.450
32.83	-28.42	-25.47	0.00	-2655.7	0.00	2655.74	4648.14	2324.07	8742.80	4377.90	3.56	-1.034	0.000	0.445
32.83	-28.42	-25.47	0.00	-2655.7	0.00	2655.74	4648.14	2324.07	8742.80	4377.90	3.56	-1.034	0.000	0.445
35.00	-27.87	-25.32	0.00	-2600.4	0.00	2600.47	4621.33	2310.66	8623.42	4318.12	4.04	-1.104	0.000	0.608
40.00	-26.68	-24.89	0.00	-2473.8	0.00	2473.87	4558.96	2279.48	8350.33	4181.37	5.31	-1.322	0.000	0.598
43.25	-25.91	-24.60	0.00	-2392.9	0.00	2392.99	4517.98	2258.99	8174.32	4093.24	6.27	-1.466	0.000	0.590
45.00	-25.19	-24.46	0.00	-2349.9	0.00	2349.95	4495.78	2247.89	8080.06	4046.03	6.82	-1.545	0.000	0.587
48.92	-23.68	-24.06	0.00	-2254.0	0.00	2254.07	4445.67	2222.84	7870.19	3940.94	8.16	-1.719	0.000	0.418
49.00	-23.64	-24.05	0.00	-2252.1	0.00	2252.14	3699.57	1849.78	6681.20	3345.56	8.19	-1.721	0.000	0.446
50.00	-23.41	-23.99	0.00	-2228.0	0.00	2228.09	3689.91	1844.95	6638.39	3324.13	8.55	-1.754	0.000	0.476
55.00	-22.40	-23.52	0.00	-2108.1	0.00	2108.14	3641.14	1820.57	6425.47	3217.51	10.48	-1.925	0.000	0.462
60.00	-21.40	-23.04	0.00	-1990.5	0.00	1990.55	3591.55	1795.77	6214.50	3111.87	12.59	-2.096	0.000	0.448
65.00	-20.43	-22.56	0.00	-1875.3	0.00	1875.34	3541.14	1770.57	6005.55	3007.24	14.87	-2.265	0.000	0.434
70.00	-19.47	-22.08	0.00	-1762.5	0.00	1762.54	3489.91	1744.96	5798.71	2903.67	17.33	-2.433	0.000	0.420
75.00	-18.55	-21.57	0.00	-1652.1	0.00	1652.16	3437.87	1718.94	5594.07	2801.19	19.97	-2.600	0.000	0.405
76.83	-18.21	-21.40	0.00	-1612.6	0.00	1612.68	3418.62	1709.31	5519.73	2763.97	20.98	-2.661	0.000	0.399
76.83	-18.21	-21.40	0.00	-1612.6	0.00	1612.68	3418.62	1709.31	5519.73	2763.97	20.98	-2.661	0.000	0.399
80.00	-17.60	-21.12	0.00	-1544.8	0.00	1544.83	3385.02	1692.51	5391.70	2699.86	22.78	-2.766	0.000	0.578
85.00	-16.69	-20.63	0.00	-1439.2	0.00	1439.25	3331.35	1665.67	5191.69	2599.71	25.81	-3.008	0.000	0.559
87.50	-16.23	-20.40	0.00	-1387.6	0.00	1387.67	3304.20	1652.10	5092.60	2550.09	27.41	-3.129	0.000	0.549
90.00	-15.50	-20.14	0.00	-1336.6	0.00	1336.67	3276.86	1638.43	4994.13	2500.78	29.08	-3.251	0.000	0.539
91.92	-14.95	-19.94	0.00	-1298.0	0.00	1298.00	3255.72	1627.86	4918.94	2463.13	30.41	-3.344	0.000	0.372
92.25	-14.84	-19.91	0.00	-1291.4	0.00	1291.42	2609.22	1304.61	4017.17	2011.57	30.64	-3.355	0.000	0.399
95.00	-14.41	-19.65	0.00	-1236.6	0.00	1236.66	2587.46	1293.73	3934.74	1970.29	32.60	-3.447	0.000	0.424
100.00	-13.65	-19.17	0.00	-1138.3	0.00	1138.39	2547.26	1273.63	3786.04	1895.83	36.30	-3.625	0.000	0.402
105.00	-12.94	-18.66	0.00	-1042.5	0.00	1042.57	2506.24	1253.12	3638.92	1822.16	40.19	-3.798	0.000	0.380
105.58	-12.84	-18.62	0.00	-1031.7	0.00	1031.74	2501.42	1250.71	3621.96	1813.67	40.65	-3.818	0.000	0.377
105.58	-12.84	-18.62	0.00	-1031.7	0.00	1031.74	2501.42	1250.71	3621.96	1813.67	40.65	-3.818	0.000	0.377
110.00	-12.19	-18.20	0.00	-949.44	0.00	949.44	2464.40	1232.20	3493.46	1749.33	44.25	-3.967	0.000	0.548
115.00	-11.46	-17.74	0.00	-858.42	0.00	858.42	2421.75	1210.87	3349.75	1677.36	48.54	-4.216	0.000	0.517
120.00	-10.75	-17.27	0.00	-769.72	0.00	769.72	2378.28	1189.14	3207.87	1606.32	53.08	-4.457	0.000	0.484
125.00	-10.06	-16.81	0.00	-683.35	0.00	683.35	2333.99	1167.00	3067.90	1536.23	57.87	-4.689	0.000	0.449
130.00	-9.41	-16.34	0.00	-599.29	0.00	599.29	2288.89	1144.45	2929.94	1467.15	62.89	-4.910	0.000	0.413
132.50	-9.08	-16.11	0.00	-558.44	0.00	558.44	2266.03	1133.02	2861.73	1432.99	65.49	-5.018	0.000	0.394
135.00	-8.60	-15.86	0.00	-518.16	0.00	518.16	2239.33	1119.66	2789.52	1396.83	68.14	-5.123	0.000	0.375
136.50	-8.30	-15.72	0.00	-494.37	0.00	494.37	1414.34	707.17	1783.76	893.21	69.76	-5.184	0.000	0.560
140.00	-7.93	-15.41	0.00	-439.34	0.00	439.34	1397.90	698.95	1729.39	865.98	73.61	-5.320	0.000	0.513
145.00	-7.44	-14.97	0.00	-362.27	0.00	362.27	1373.73	686.86	1652.26	827.36	79.30	-5.558	0.000	0.444
148.00	-7.03	-13.97	0.00	-317.36	0.00	317.36	1358.83	679.41	1606.31	804.35	82.83	-5.690	0.000	0.400
150.00	-6.84	-13.80	0.00	-289.43	0.00	289.43	1348.73	674.37	1575.83	789.09	85.23	-5.773	0.000	0.372
155.00	-6.42	-13.37	0.00	-220.41	0.00	220.41	1322.92	661.46	1500.20	751.22	91.37	-5.953	0.000	0.299
158.00	-5.02	-10.02	0.00	-180.30	0.00	180.30	1307.05	653.52	1455.24	728.70	95.13	-6.045	0.000	0.252

## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II
		<b>Page:</b> 26



160.00	-4.87	-9.85	0.00	-160.27	0.00	160.27	1296.30	648.15	1425.45	713.78	97.67	-6.101	0.000	0.229
165.00	-4.53	-9.43	0.00	-111.03	0.00	111.03	1268.86	634.43	1351.65	676.83	104.11	-6.215	0.000	0.168
168.00	-3.71	-6.47	0.00	-82.74	0.00	82.74	1252.00	626.00	1307.87	654.91	108.03	-6.269	0.000	0.129
168.50	-2.46	-5.12	0.00	-79.50	0.00	79.50	1249.16	624.58	1300.61	651.27	108.69	-6.277	0.000	0.124
170.00	-2.37	-5.00	0.00	-71.83	0.00	71.83	1240.60	620.30	1278.90	640.40	110.66	-6.300	0.000	0.114
175.00	-2.06	-4.59	0.00	-46.85	0.00	46.85	1211.52	605.76	1207.28	604.54	117.28	-6.361	0.000	0.079
178.00	-1.88	-4.36	0.00	-33.07	0.00	33.07	1193.69	596.84	1164.89	583.31	121.28	-6.388	0.000	0.058
178.00	-1.88	-4.36	0.00	-33.07	0.00	33.07	975.84	487.92	954.81	478.11	121.28	-6.388	0.000	0.071
180.00	-1.77	-4.20	0.00	-24.36	0.00	24.36	975.84	487.92	954.81	478.11	123.95	-6.402	0.000	0.053
184.00	-0.36	-2.55	0.00	-7.56	0.00	7.56	975.84	487.92	954.81	478.11	129.31	-6.420	0.000	0.016
185.00	-0.31	-2.47	0.00	-5.01	0.00	5.01	975.84	487.92	954.81	478.11	130.65	-6.421	0.000	0.011
187.00	-0.04	-0.08	0.00	-0.08	0.00	0.08	975.84	487.92	954.81	478.11	133.34	-6.423	0.000	0.000
188.00	0.00	-0.07	0.00	0.00	0.00	0.00	975.84	487.92	954.81	478.11	134.68	-6.423	0.000	0.000

## Wind Loading - Shaft


<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 27

**Load Case:** 1.2D + 1.0Di + 1.0Wi 50 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.00



**Iterations** 29

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	5.168	5.68	0.00	1.200	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	5.168	5.68	0.00	1.200	1.656	5.00	23.095	27.71	157.6	545.3	1987.9
10.00		1.00	0.85	5.168	5.68	0.00	1.200	1.775	5.00	22.843	27.41	155.8	576.5	1995.6
15.00		1.00	0.85	5.168	5.68	0.00	1.200	1.848	5.00	22.553	27.06	153.9	591.5	1987.1
20.00		1.00	0.90	5.483	6.03	0.00	1.200	1.902	5.00	22.247	26.70	161.0	599.5	1971.6
25.00		1.00	0.95	5.747	6.32	0.00	1.200	1.945	5.00	21.931	26.32	166.4	603.5	1952.0
30.00		1.00	0.98	5.972	6.57	0.00	1.200	1.981	5.00	21.610	25.93	170.4	604.7	1929.7
32.83	RT1	1.00	1.00	6.087	6.70	0.00	1.200	1.999	2.83	12.084	14.50	97.1	342.2	1081.7
35.00		1.00	1.01	6.169	6.79	0.00	1.200	2.012	2.17	9.194	11.03	74.9	262.1	824.1
40.00		1.00	1.04	6.345	6.98	0.00	1.200	2.039	5.00	20.956	25.15	175.5	601.9	1879.8
43.25	Bot - Section 2	1.00	1.06	6.450	7.10	0.00	1.200	2.055	3.25	13.442	16.13	114.4	389.9	1207.9
45.00		1.00	1.07	6.504	7.15	0.00	1.200	2.063	1.75	7.290	8.75	62.6	212.9	1030.2
48.92	RB2	1.00	1.09	6.620	7.28	0.00	1.200	2.080	3.92	16.184	19.42	141.4	474.4	2285.7
49.00	Top - Section 1	1.00	1.09	6.622	7.28	0.00	1.200	2.081	0.08	0.328	0.39	2.9	9.7	46.4
50.00		1.00	1.09	6.650	7.32	0.00	1.200	2.085	1.00	4.094	4.91	35.9	120.8	334.2
55.00		1.00	1.12	6.785	7.46	0.00	1.200	2.105	5.00	20.274	24.33	181.6	599.2	1653.8
60.00		1.00	1.14	6.910	7.60	0.00	1.200	2.123	5.00	19.939	23.93	181.9	593.7	1628.1
65.00		1.00	1.16	7.028	7.73	0.00	1.200	2.140	5.00	19.602	23.52	181.8	587.5	1601.8
70.00		1.00	1.17	7.138	7.85	0.00	1.200	2.156	5.00	19.264	23.12	181.5	580.9	1575.0
75.00		1.00	1.19	7.243	7.97	0.00	1.200	2.171	5.00	18.925	22.71	180.9	573.8	1547.7
76.83	RT2	1.00	1.20	7.280	8.01	0.00	1.200	2.176	1.83	6.840	8.21	65.7	209.0	560.4
80.00		1.00	1.21	7.342	8.08	0.00	1.200	2.185	3.17	11.742	14.09	113.8	359.1	961.4
85.00		1.00	1.22	7.436	8.18	0.00	1.200	2.198	5.00	18.245	21.89	179.1	558.6	1492.1
87.50	Bot - Section 3	1.00	1.23	7.482	8.23	0.00	1.200	2.205	2.50	8.994	10.79	88.8	277.3	736.5
90.00		1.00	1.24	7.526	8.28	0.00	1.200	2.211	2.50	9.041	10.85	89.8	279.5	1119.2
91.92	RB3	1.00	1.24	7.560	8.32	0.00	1.200	2.216	1.92	6.885	8.26	68.7	213.5	852.0
92.25	Top - Section 2	1.00	1.24	7.565	8.32	0.00	1.200	2.217	0.33	1.178	1.41	11.8	36.7	145.9
95.00		1.00	1.25	7.612	8.37	0.00	1.200	2.223	2.75	9.762	11.71	98.1	302.9	717.9
100.00		1.00	1.27	7.695	8.46	0.00	1.200	2.234	5.00	17.486	20.98	177.6	542.1	1283.5
105.00		1.00	1.28	7.774	8.55	0.00	1.200	2.245	5.00	17.144	20.57	175.9	533.2	1257.9
105.58	RT3	1.00	1.28	7.783	8.56	0.00	1.200	2.247	0.58	1.966	2.36	20.2	61.7	144.7
110.00		1.00	1.29	7.851	8.64	0.00	1.200	2.256	4.42	14.834	17.80	153.7	463.3	1088.2
115.00		1.00	1.30	7.925	8.72	0.00	1.200	2.266	5.00	16.458	19.75	172.2	514.8	1205.8
120.00		1.00	1.32	7.996	8.80	0.00	1.200	2.276	5.00	16.115	19.34	170.1	505.3	1179.5
125.00		1.00	1.33	8.065	8.87	0.00	1.200	2.285	5.00	15.772	18.93	167.9	495.6	1153.0
130.00		1.00	1.34	8.132	8.95	0.00	1.200	2.294	5.00	15.428	18.51	165.6	485.7	1126.3
132.50	Bot - Section 4	1.00	1.34	8.165	8.98	0.00	1.200	2.298	2.50	7.584	9.10	81.7	240.4	554.4
135.00		1.00	1.35	8.197	9.02	0.00	1.200	2.303	2.50	7.591	9.11	82.1	241.0	771.5
136.50	Top - Section 3	1.00	1.35	8.216	9.04	0.00	1.200	2.305	1.50	4.513	5.42	48.9	143.7	458.5
140.00		1.00	1.36	8.260	9.09	0.00	1.200	2.311	3.50	10.411	12.49	113.5	330.3	631.8
145.00		1.00	1.37	8.321	9.15	0.00	1.200	2.319	5.00	14.581	17.50	160.1	461.6	882.3
148.00	Appurtenance(s)	1.00	1.37	8.357	9.19	0.00	1.200	2.324	3.00	8.582	10.30	94.7	273.2	520.0
150.00		1.00	1.38	8.381	9.22	0.00	1.200	2.327	2.00	5.652	6.78	62.5	180.5	342.6
155.00		1.00	1.39	8.439	9.28	0.00	1.200	2.335	5.00	13.891	16.67	154.7	440.6	837.8
158.00	Appurtenance(s)	1.00	1.39	8.473	9.32	0.00	1.200	2.339	3.00	8.168	9.80	91.4	260.5	493.2
160.00		1.00	1.40	8.495	9.34	0.00	1.200	2.342	2.00	5.376	6.45	60.3	172.0	324.7
165.00		1.00	1.41	8.551	9.41	0.00	1.200	2.349	5.00	13.201	15.84	149.0	419.2	792.8

## Wind Loading - Shaft

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Page:</b> 28
	<b>Struct Class:</b> II	



168.00 Appurtenance(s)	1.00	1.41	8.583	9.44	0.00	1.200	2.353	3.00	7.754	9.30	87.8	247.6	466.1
168.50 Appurtenance(s)	1.00	1.41	8.588	9.45	0.00	1.200	2.354	0.50	1.280	1.54	14.5	41.2	77.2
170.00	1.00	1.42	8.604	9.46	0.00	1.200	2.356	1.50	3.820	4.58	43.4	122.5	229.8
175.00	1.00	1.42	8.657	9.52	0.00	1.200	2.363	5.00	12.510	15.01	143.0	397.2	747.4
178.00 Top - Section 4	1.00	1.43	8.688	9.56	0.00	1.200	2.367	3.00	7.339	8.81	84.2	234.4	438.8
180.00	1.00	1.43	8.709	9.58	0.00	1.200	2.370	2.00	4.852	5.82	55.8	156.4	272.2
184.00 Appurtenance(s)	1.00	1.44	8.749	9.62	0.00	1.200	2.375	4.00	9.707	11.65	112.1	313.6	545.1
185.00	1.00	1.44	8.759	9.63	0.00	1.200	2.376	1.00	2.427	2.91	28.1	78.4	136.3
187.00 Appurtenance(s)	1.00	1.44	8.779	9.66	0.00	1.200	2.379	2.00	4.855	5.83	56.3	157.1	272.8
188.00	1.00	1.45	8.789	9.67	0.00	1.200	2.380	1.00	2.428	2.91	28.2	78.6	136.4
<b>Totals:</b>							<b>188.00</b>					<b>6,248.7</b>	<b>53,476.5</b>



## Discrete Appurtenance Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 29

**Load Case:** 1.2D + 1.0Di + 1.0Wi 50 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.00



**Iterations** 29

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	187.00	LNx-6515DS-A1M	3	8.779	9.657	0.64	0.80	30.57	920.55	0.000	0.000	295.23	0.00	0.00
2	187.00	APXV18-209014	3	8.779	9.657	0.59	0.80	8.69	471.65	0.000	0.000	83.91	0.00	0.00
3	187.00	782 11054	3	8.779	9.657	0.54	0.80	1.44	10.02	0.000	0.000	13.87	0.00	0.00
4	187.00	KRY 112 144-1	12	8.779	9.657	0.54	0.80	6.80	297.55	0.000	0.000	65.69	0.00	0.00
5	187.00	APX16PV-16-PVL-E	3	8.779	9.657	0.50	0.80	11.21	715.61	0.000	0.000	108.26	0.00	0.00
6	184.00	Low Profile Platform	1	8.749	9.624	1.00	1.00	46.03	3281.24	0.000	0.000	443.03	0.00	0.00
7	168.50	Low Profile Platform	1	8.588	9.447	1.00	1.00	45.82	3265.63	0.000	0.000	432.91	0.00	0.00
8	168.00	APXV9ERR18-C-A20	1	8.583	9.441	0.66	0.80	7.83	267.23	0.000	0.000	73.90	0.00	0.00
9	168.00	ACU-A20-N	4	8.583	9.441	0.80	0.80	1.73	22.77	0.000	0.000	16.32	0.00	0.00
10	168.00	TD-RRH8x20-25	3	8.583	9.441	0.54	0.80	8.32	732.06	0.000	0.000	78.58	0.00	0.00
11	168.00	800 MHz RRH	3	8.583	9.441	0.54	0.80	7.36	435.22	0.000	0.000	69.51	0.00	0.00
12	168.00	1900 MHz RRH	3	8.583	9.441	0.54	0.80	7.36	373.26	0.000	0.000	69.51	0.00	0.00
13	168.00	APXVTM14-C-120	3	8.583	9.441	0.63	0.80	14.93	896.98	0.000	0.000	140.97	0.00	0.00
14	168.00	800 MHz Filters	3	8.583	9.441	0.54	0.80	7.36	435.22	0.000	0.000	69.51	0.00	0.00
15	168.00	APXVSP18-C-A20	2	8.583	9.441	0.66	0.80	15.65	503.99	0.000	0.000	147.79	0.00	0.00
16	158.00	T-Arm	3	8.473	9.320	0.50	0.75	26.16	1562.07	0.000	0.000	243.86	0.00	0.00
17	158.00	SBNH-1D6565C	1	8.473	9.320	0.64	0.80	10.13	321.53	0.000	0.000	94.41	0.00	0.00
18	158.00	P65-17-XLH-RR	2	8.473	9.320	0.60	0.80	18.93	598.22	0.000	0.000	176.43	0.00	0.00
19	158.00	LGP21401	6	8.473	9.320	0.54	0.80	7.62	258.60	0.000	0.000	71.02	0.00	0.00
20	158.00	RRUS-11	6	8.473	9.320	0.54	0.80	11.00	1138.67	0.000	0.000	102.49	0.00	0.00
21	158.00	7770	3	8.473	9.320	0.58	0.80	12.19	712.28	0.000	0.000	113.64	0.00	0.00
22	158.00	DC-48-60-18-8F	1	8.473	9.320	0.80	0.80	1.93	103.32	0.000	0.000	17.95	0.00	0.00
23	148.00	742 213	3	8.357	9.193	0.58	0.80	11.89	579.73	0.000	0.000	109.34	0.00	0.00
24	148.00	Flush Mount	1	8.357	9.193	1.00	1.00	9.65	272.32	0.000	0.000	88.69	0.00	0.00
<b>Totals:</b>									<b>18,175.73</b>			<b>3,126.82</b>		

## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 30

**Load Case:** 1.2D + 1.0Di + 1.0Wi 50 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.00



**Iterations** 29

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		157.55	2357.67	0.00	0.00
10.00		155.83	2377.54	0.00	0.00
15.00		153.85	2376.80	0.00	0.00
20.00		161.03	2367.02	0.00	0.00
25.00		166.38	2352.04	0.00	0.00
30.00		170.36	2333.63	0.00	0.00
32.83		97.09	1311.41	0.00	0.00
35.00		74.87	1000.86	0.00	0.00
40.00		175.51	2238.71	0.00	0.00
43.25		114.44	1438.25	0.00	0.00
45.00		62.59	1154.41	0.00	0.00
48.92		141.42	2593.37	0.00	0.00
49.00		2.87	53.01	0.00	0.00
50.00		35.94	417.25	0.00	0.00
55.00		181.58	2071.47	0.00	0.00
60.00		181.87	2047.80	0.00	0.00
65.00		181.84	2023.42	0.00	0.00
70.00		181.51	1998.41	0.00	0.00
75.00		180.93	1972.87	0.00	0.00
76.83		65.73	716.26	0.00	0.00
80.00		113.80	1222.50	0.00	0.00
85.00		179.09	1856.83	0.00	0.00
87.50		88.82	919.07	0.00	0.00
90.00		89.81	1301.97	0.00	0.00
91.92		68.70	1014.01	0.00	0.00
92.25		11.77	174.26	0.00	0.00
95.00		98.09	954.95	0.00	0.00
100.00		177.61	1715.94	0.00	0.00
105.00		175.93	1691.51	0.00	0.00
105.58		20.20	195.02	0.00	0.00
110.00		153.73	1436.33	0.00	0.00
115.00		172.17	1575.49	0.00	0.00
120.00		170.09	1549.88	0.00	0.00
125.00		167.90	1524.08	0.00	0.00
130.00		165.61	1498.07	0.00	0.00
132.50		81.74	740.40	0.00	0.00
135.00		82.13	957.67	0.00	0.00
136.50		48.94	570.32	0.00	0.00
140.00		113.51	892.95	0.00	0.00
145.00		160.15	1255.95	0.00	0.00
148.00	(4) attachments	292.70	1596.44	0.00	0.00
150.00		62.53	417.19	0.00	0.00
155.00		154.73	1024.19	0.00	0.00
158.00	(22) attachments	911.15	5299.72	0.00	0.00
160.00		60.29	375.00	0.00	0.00
165.00		148.99	918.46	0.00	0.00

## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 31

168.00	(22) attachments	753.93	4208.25	0.00	0.00
168.50	(1) attachments	447.42	3354.03	0.00	0.00
170.00		43.38	263.51	0.00	0.00
175.00		142.95	859.69	0.00	0.00
178.00		84.17	506.17	0.00	0.00
180.00		55.77	317.08	0.00	0.00
184.00	(1) attachments	555.13	3916.16	0.00	0.00
185.00		28.06	158.78	0.00	0.00
187.00	(24) attachments	623.22	2733.11	0.00	0.00
188.00		28.16	136.45	0.00	0.00
<b>Totals:</b>		<b>9,375.56</b>	<b>84,333.61</b>	<b>0.00</b>	<b>0.00</b>

## Linear Appurtenance Segment Forces (Factored)


<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 32

**Load Case:** 1.2D + 1.0Di + 1.0Wi 50 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.00



**Iterations** 29

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.21	0.00	0.062	0.000	5.168	0.00	140.52
5.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	1.90	0.00	0.062	0.000	5.168	0.00	42.86
10.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.30	0.00	0.063	0.000	5.168	0.00	148.50
10.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.00	0.00	0.063	0.000	5.168	0.00	47.08
15.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.37	0.00	0.064	0.000	5.168	0.00	153.52
15.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.06	0.00	0.064	0.000	5.168	0.00	49.78
20.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.41	0.00	0.065	0.000	5.483	0.00	157.25
20.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.11	0.00	0.065	0.000	5.483	0.00	51.80
25.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.45	0.00	0.066	0.000	5.747	0.00	160.24
25.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.14	0.00	0.066	0.000	5.747	0.00	53.44
30.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.48	0.00	0.067	0.000	5.972	0.00	162.75
30.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.17	0.00	0.067	0.000	5.972	0.00	54.82
32.83	1 5/8" Coax	Yes	2.83	0.000	1.98	1.41	0.00	0.068	0.000	6.087	0.00	92.83
32.83	1.25" Reinforcing	Yes	2.83	0.000	1.25	1.24	0.00	0.068	0.000	6.087	0.00	31.42
35.00	1 5/8" Coax	Yes	2.17	0.000	1.98	1.09	0.00	0.069	0.000	6.169	0.00	71.58
35.00	1.25" Reinforcing	Yes	2.17	0.000	1.25	0.95	0.00	0.069	0.000	6.169	0.00	24.31
40.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.52	0.00	0.046	0.000	6.345	0.00	166.84
40.00	1.25" Reinforcing	Yes	0.50	0.000	1.25	0.22	0.00	0.046	0.000	6.345	0.00	5.71
43.25	1 5/8" Coax	Yes	3.25	0.000	1.98	1.65	0.00	0.043	0.000	6.450	0.00	109.19
45.00	1 5/8" Coax	Yes	1.75	0.000	1.98	0.89	0.00	0.044	0.000	6.504	0.00	59.00
48.92	1 5/8" Coax	Yes	3.92	0.000	1.98	2.01	0.00	0.062	0.000	6.620	0.00	133.12
48.92	1.25" Reinforcing	Yes	2.42	0.000	1.25	1.09	0.00	0.062	0.000	6.620	0.00	28.43
49.00	1 5/8" Coax	Yes	0.08	0.000	1.98	0.04	0.00	0.073	0.000	6.622	0.00	2.72
49.00	1.25" Reinforcing	Yes	0.08	0.000	1.25	0.04	0.00	0.073	0.000	6.622	0.00	0.94
50.00	1 5/8" Coax	Yes	1.00	0.000	1.98	0.51	0.00	0.072	0.000	6.650	0.00	34.03
50.00	1.25" Reinforcing	Yes	1.00	0.000	1.25	0.45	0.00	0.072	0.000	6.650	0.00	11.78
55.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.58	0.00	0.073	0.000	6.785	0.00	171.56
55.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.27	0.00	0.073	0.000	6.785	0.00	59.71
60.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.59	0.00	0.074	0.000	6.910	0.00	172.89
60.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.29	0.00	0.074	0.000	6.910	0.00	60.46
65.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.61	0.00	0.076	0.000	7.028	0.00	174.12
65.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.30	0.00	0.076	0.000	7.028	0.00	61.15
70.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.62	0.00	0.077	0.000	7.138	0.00	175.27
70.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.32	0.00	0.077	0.000	7.138	0.00	61.80
75.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.63	0.00	0.079	0.000	7.243	0.00	176.36
75.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.33	0.00	0.079	0.000	7.243	0.00	62.41
76.83	1 5/8" Coax	Yes	1.83	0.000	1.98	0.97	0.00	0.080	0.000	7.280	0.00	64.69
76.83	1.25" Reinforcing	Yes	1.83	0.000	1.25	0.85	0.00	0.080	0.000	7.280	0.00	22.92
80.00	1 5/8" Coax	Yes	3.17	0.000	1.98	1.68	0.00	0.073	0.000	7.342	0.00	112.46
80.00	1.25" Reinforcing	Yes	2.42	0.000	1.25	1.13	0.00	0.073	0.000	7.342	0.00	30.49
85.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.66	0.00	0.050	0.000	7.436	0.00	178.35
87.50	1 5/8" Coax	Yes	2.50	0.000	1.98	1.33	0.00	0.051	0.000	7.482	0.00	89.41
90.00	1 5/8" Coax	Yes	2.50	0.000	1.98	1.33	0.00	0.052	0.000	7.526	0.00	89.64
91.92	1 5/8" Coax	Yes	1.92	0.000	1.98	1.03	0.00	0.081	0.000	7.560	0.00	68.97
91.92	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.79	0.00	0.081	0.000	7.560	0.00	21.46
92.25	1 5/8" Coax	Yes	0.33	0.000	1.98	0.18	0.00	0.086	0.000	7.565	0.00	11.86
92.25	1.25" Reinforcing	Yes	0.33	0.000	1.25	0.16	0.00	0.086	0.000	7.565	0.00	4.24

## Linear Appurtenance Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 33

**Load Case:** 1.2D + 1.0Di + 1.0Wi 50 mph Wind

**Dead Load Factor** 1.20  
**Wind Load Factor** 1.00



**Iterations** 29

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
95.00	1 5/8" Coax	Yes	2.75	0.000	1.98	1.47	0.00	0.085	0.000	7.612	0.00	99.08
95.00	1.25" Reinforcing	Yes	2.75	0.000	1.25	1.31	0.00	0.085	0.000	7.612	0.00	35.51
100.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.69	0.00	0.086	0.000	7.695	0.00	180.99
100.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.38	0.00	0.086	0.000	7.695	0.00	65.04
105.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.70	0.00	0.088	0.000	7.774	0.00	181.79
105.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	2.39	0.00	0.088	0.000	7.774	0.00	65.50
105.58	1 5/8" Coax	Yes	0.58	0.000	1.98	0.31	0.00	0.089	0.000	7.783	0.00	21.10
105.58	1.25" Reinforcing	Yes	0.58	0.000	1.25	0.28	0.00	0.089	0.000	7.783	0.00	7.60
110.00	1 5/8" Coax	Yes	4.42	0.000	1.98	2.39	0.00	0.069	0.000	7.851	0.00	161.39
110.00	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.80	0.00	0.069	0.000	7.851	0.00	22.02
115.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.71	0.00	0.057	0.000	7.925	0.00	183.31
120.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.72	0.00	0.058	0.000	7.996	0.00	184.02
125.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.73	0.00	0.059	0.000	8.065	0.00	184.71
130.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.74	0.00	0.061	0.000	8.132	0.00	185.38
132.50	1 5/8" Coax	Yes	2.50	0.000	1.98	1.37	0.00	0.062	0.000	8.165	0.00	92.85
135.00	1 5/8" Coax	Yes	2.50	0.000	1.98	1.37	0.00	0.063	0.000	8.197	0.00	93.01
136.50	1 5/8" Coax	Yes	1.50	0.000	1.98	0.82	0.00	0.064	0.000	8.216	0.00	55.86
140.00	1 5/8" Coax	Yes	3.50	0.000	1.98	1.93	0.00	0.064	0.000	8.260	0.00	130.65
145.00	1 5/8" Coax	Yes	5.00	0.000	1.98	2.76	0.00	0.065	0.000	8.321	0.00	187.25
148.00	1 5/8" Coax	Yes	3.00	0.000	1.98	1.66	0.00	0.067	0.000	8.357	0.00	112.56
<b>Totals:</b>											<b>0.0</b>	<b>6,114.3</b>

## Calculated Forces

**Structure:** CT46124-A-SBA  
**Site Name:** Enfield-Moody Rd.  
**Height:** 188.00 (ft)  
**Base Elev:** 0.000 (ft)  
**Gh:** 1.1

**Topography:** 1

**Code:** EIA/TIA-222-G  
**Exposure:** C  
**Crest Height:** 0.00  
**Site Class:** D - Stiff Soil  
**Struct Class:** II

7/31/2017




Page: 34

**Load Case:** 1.2D + 1.0Di + 1.0Wi 50 mph Wind

**Iterations** 29

**Dead Load Factor** 1.20

**Wind Load Factor** 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-84.33	-9.42	0.00	-1239.6	0.00	1239.68	5035.03	2517.52	10606.9	5311.37	0.00	0.000	0.000	0.188
5.00	-81.96	-9.34	0.00	-1192.6	0.00	1192.60	4978.38	2489.19	10316.4	5165.91	0.03	-0.055	0.000	0.185
10.00	-79.58	-9.25	0.00	-1145.9	0.00	1145.92	4920.91	2460.46	10028.2	5021.57	0.12	-0.110	0.000	0.182
15.00	-77.19	-9.17	0.00	-1099.6	0.00	1099.66	4862.63	2431.31	9742.31	4878.39	0.26	-0.165	0.000	0.179
20.00	-74.82	-9.07	0.00	-1053.8	0.00	1053.82	4803.53	2401.76	9458.77	4736.42	0.46	-0.220	0.000	0.175
25.00	-72.46	-8.97	0.00	-1008.4	0.00	1008.46	4743.61	2371.81	9177.73	4595.68	0.72	-0.276	0.000	0.172
30.00	-70.12	-8.84	0.00	-963.63	0.00	963.63	4682.88	2341.44	8899.25	4456.24	1.04	-0.332	0.000	0.169
32.83	-68.80	-8.77	0.00	-938.63	0.00	938.63	4648.14	2324.07	8742.80	4377.90	1.25	-0.364	0.000	0.167
32.83	-68.80	-8.77	0.00	-938.63	0.00	938.63	4648.14	2324.07	8742.80	4377.90	1.25	-0.364	0.000	0.167
35.00	-67.79	-8.74	0.00	-919.61	0.00	919.61	4621.33	2310.66	8623.42	4318.12	1.42	-0.388	0.000	0.228
40.00	-65.55	-8.63	0.00	-875.89	0.00	875.89	4558.96	2279.48	8350.33	4181.37	1.87	-0.466	0.000	0.224
43.25	-64.10	-8.54	0.00	-847.85	0.00	847.85	4517.98	2258.99	8174.32	4093.24	2.20	-0.517	0.000	0.221
45.00	-62.94	-8.52	0.00	-832.90	0.00	832.90	4495.78	2247.89	8080.06	4046.03	2.40	-0.545	0.000	0.220
48.92	-60.35	-8.38	0.00	-799.51	0.00	799.51	4445.67	2222.84	7870.19	3940.94	2.87	-0.606	0.000	0.157
49.00	-60.29	-8.39	0.00	-798.84	0.00	798.84	3699.57	1849.78	6681.20	3345.56	2.88	-0.607	0.000	0.167
50.00	-59.87	-8.38	0.00	-790.45	0.00	790.45	3689.91	1844.95	6638.39	3324.13	3.01	-0.619	0.000	0.179
55.00	-57.79	-8.24	0.00	-748.53	0.00	748.53	3641.14	1820.57	6425.47	3217.51	3.69	-0.680	0.000	0.174
60.00	-55.74	-8.09	0.00	-707.33	0.00	707.33	3591.55	1795.77	6214.50	3111.87	4.43	-0.740	0.000	0.169
65.00	-53.71	-7.94	0.00	-666.87	0.00	666.87	3541.14	1770.57	6005.55	3007.24	5.24	-0.800	0.000	0.164
70.00	-51.71	-7.78	0.00	-627.17	0.00	627.17	3489.91	1744.96	5798.71	2903.67	6.11	-0.860	0.000	0.158
75.00	-49.73	-7.61	0.00	-588.26	0.00	588.26	3437.87	1718.94	5594.07	2801.19	7.04	-0.919	0.000	0.153
76.83	-49.01	-7.55	0.00	-574.34	0.00	574.34	3418.62	1709.31	5519.73	2763.97	7.40	-0.941	0.000	0.151
76.83	-49.01	-7.55	0.00	-574.34	0.00	574.34	3418.62	1709.31	5519.73	2763.97	7.40	-0.941	0.000	0.151
80.00	-47.78	-7.47	0.00	-550.39	0.00	550.39	3385.02	1692.51	5391.70	2699.86	8.04	-0.979	0.000	0.218
85.00	-45.92	-7.31	0.00	-513.03	0.00	513.03	3331.35	1665.67	5191.69	2599.71	9.11	-1.065	0.000	0.211
87.50	-45.00	-7.24	0.00	-494.75	0.00	494.75	3304.20	1652.10	5092.60	2550.09	9.68	-1.108	0.000	0.208
90.00	-43.69	-7.15	0.00	-476.65	0.00	476.65	3276.86	1638.43	4994.13	2500.78	10.27	-1.151	0.000	0.204
91.92	-42.68	-7.08	0.00	-462.92	0.00	462.92	3255.72	1627.86	4918.94	2463.13	10.74	-1.185	0.000	0.141
92.25	-42.50	-7.08	0.00	-460.59	0.00	460.59	2609.22	1304.61	4017.17	2011.57	10.82	-1.189	0.000	0.151
95.00	-41.54	-6.99	0.00	-441.13	0.00	441.13	2587.46	1293.73	3934.74	1970.29	11.52	-1.221	0.000	0.161
100.00	-39.83	-6.82	0.00	-406.17	0.00	406.17	2547.26	1273.63	3786.04	1895.83	12.83	-1.285	0.000	0.153
105.00	-38.13	-6.63	0.00	-372.06	0.00	372.06	2506.24	1253.12	3638.92	1822.16	14.21	-1.347	0.000	0.144
105.58	-37.94	-6.62	0.00	-368.22	0.00	368.22	2501.42	1250.71	3621.96	1813.67	14.37	-1.354	0.000	0.144
105.58	-37.94	-6.62	0.00	-368.22	0.00	368.22	2501.42	1250.71	3621.96	1813.67	14.37	-1.354	0.000	0.144
110.00	-36.50	-6.48	0.00	-338.94	0.00	338.94	2464.40	1232.20	3493.46	1749.33	15.65	-1.407	0.000	0.209
115.00	-34.92	-6.32	0.00	-306.53	0.00	306.53	2421.75	1210.87	3349.75	1677.36	17.17	-1.496	0.000	0.197
120.00	-33.36	-6.16	0.00	-274.92	0.00	274.92	2378.28	1189.14	3207.87	1606.32	18.78	-1.582	0.000	0.185
125.00	-31.84	-5.99	0.00	-244.12	0.00	244.12	2333.99	1167.00	3067.90	1536.23	20.49	-1.665	0.000	0.173
130.00	-30.34	-5.82	0.00	-214.14	0.00	214.14	2288.89	1144.45	2929.94	1467.15	22.27	-1.744	0.000	0.159
132.50	-29.60	-5.73	0.00	-199.61	0.00	199.61	2266.03	1133.02	2861.73	1432.99	23.20	-1.782	0.000	0.152
135.00	-28.64	-5.63	0.00	-185.28	0.00	185.28	2239.33	1119.66	2789.52	1396.83	24.14	-1.820	0.000	0.145
136.50	-28.07	-5.58	0.00	-176.83	0.00	176.83	1414.34	707.17	1783.76	893.21	24.71	-1.842	0.000	0.218
140.00	-27.17	-5.47	0.00	-157.29	0.00	157.29	1397.90	698.95	1729.39	865.98	26.08	-1.890	0.000	0.201
145.00	-25.91	-5.30	0.00	-129.93	0.00	129.93	1373.73	686.86	1652.26	827.36	28.11	-1.976	0.000	0.176
148.00	-24.33	-4.97	0.00	-114.03	0.00	114.03	1358.83	679.41	1606.31	804.35	29.37	-2.023	0.000	0.160
150.00	-23.91	-4.91	0.00	-104.09	0.00	104.09	1348.73	674.37	1575.83	789.09	30.22	-2.053	0.000	0.150
155.00	-22.89	-4.74	0.00	-79.54	0.00	79.54	1322.92	661.46	1500.20	751.22	32.40	-2.118	0.000	0.123
158.00	-17.62	-3.64	0.00	-65.32	0.00	65.32	1307.05	653.52	1455.24	728.70	33.75	-2.151	0.000	0.103

## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 35

160.00	-17.25	-3.57	0.00	-58.05	0.00	58.05	1296.30	648.15	1425.45	713.78	34.65	-2.171	0.000	0.095
165.00	-16.33	-3.40	0.00	-40.18	0.00	40.18	1268.86	634.43	1351.65	676.83	36.95	-2.213	0.000	0.072
168.00	-12.16	-2.48	0.00	-29.98	0.00	29.98	1252.00	626.00	1307.87	654.91	38.35	-2.232	0.000	0.056
168.50	-8.82	-1.91	0.00	-28.74	0.00	28.74	1249.16	624.58	1300.61	651.27	38.58	-2.235	0.000	0.051
170.00	-8.56	-1.86	0.00	-25.88	0.00	25.88	1240.60	620.30	1278.90	640.40	39.28	-2.243	0.000	0.047
175.00	-7.71	-1.68	0.00	-16.60	0.00	16.60	1211.52	605.76	1207.28	604.54	41.64	-2.265	0.000	0.034
178.00	-7.20	-1.58	0.00	-11.56	0.00	11.56	1193.69	596.84	1164.89	583.31	43.07	-2.275	0.000	0.026
178.00	-7.20	-1.58	0.00	-11.56	0.00	11.56	975.84	487.92	954.81	478.11	43.07	-2.275	0.000	0.032
180.00	-6.89	-1.51	0.00	-8.40	0.00	8.40	975.84	487.92	954.81	478.11	44.02	-2.279	0.000	0.025
184.00	-3.00	-0.80	0.00	-2.36	0.00	2.36	975.84	487.92	954.81	478.11	45.94	-2.285	0.000	0.008
185.00	-2.84	-0.77	0.00	-1.56	0.00	1.56	975.84	487.92	954.81	478.11	46.41	-2.286	0.000	0.006
187.00	-0.14	-0.03	0.00	-0.03	0.00	0.03	975.84	487.92	954.81	478.11	47.37	-2.286	0.000	0.000
188.00	0.00	-0.03	0.00	0.00	0.00	0.00	975.84	487.92	954.81	478.11	47.85	-2.286	0.000	0.000


## Seismic Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 36

<b>Load Case:</b> 1.2D + 1.0E					<b>Iterations</b> 26
<b>Gust Response Factor</b>	1.10			<b>Sds</b> 0.19	<b>Ss</b> 0.17
<b>Dead Load Factor</b>	1.20	<b>Seismic Load Factor</b>	1.00	<b>Sd1</b> 0.10	<b>S1</b> 0.06
<b>Wind Load Factor</b>	0.00	<b>Structure Frequency</b>	0.26	<b>SA</b> 0.03	<b>Seismic Importance Factor</b> 1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00	RB1	0.00	0.00	0.00	0.00	0.00	
5.00		1202.2	0.00	0.03	0.01	21.45	
10.00		1182.6	0.01	0.05	0.03	31.04	
15.00		1163.0	0.01	0.06	0.03	35.78	
20.00		1143.3	0.02	0.06	0.04	38.07	
25.00		1123.7	0.03	0.07	0.04	39.09	
30.00		1104.1	0.05	0.07	0.04	39.46	
32.83	RT1	616.26	0.06	0.07	0.04	22.29	
35.00		468.28	0.07	0.07	0.04	17.08	
40.00		1064.9	0.09	0.07	0.04	39.61	
43.25	Bot - Section 2	681.69	0.10	0.07	0.04	25.68	
45.00		681.08	0.11	0.07	0.04	25.83	
48.92	RB2	1509.4	0.13	0.07	0.03	58.13	
49.00	Top - Section 1	30.57	0.13	0.07	0.03	1.18	
50.00		177.78	0.13	0.07	0.03	6.87	
55.00		878.82	0.16	0.07	0.03	34.54	
60.00		862.01	0.19	0.06	0.02	34.15	
65.00		845.20	0.23	0.06	0.02	33.22	
70.00		828.39	0.26	0.05	0.02	31.45	
75.00		811.58	0.30	0.05	0.01	28.49	
76.83	RT2	292.84	0.32	0.04	0.01	9.83	
80.00		501.94	0.34	0.03	0.01	15.13	
85.00		777.96	0.39	0.02	0.01	17.60	
87.50	Bot - Section 3	382.68	0.41	0.02	0.01	6.83	
90.00		699.67	0.43	0.01	0.01	8.72	
91.92	RB3	532.12	0.45	0.00	0.01	4.24	
92.25	Top - Section 2	91.00	0.46	0.00	0.01	0.65	
95.00		345.80	0.48	-0.01	0.01	0.09	
100.00		617.88	0.53	-0.03	0.01	-7.82	
105.00		603.87	0.59	-0.05	0.01	-14.83	
105.58	RT3	69.14	0.60	-0.05	0.01	-1.78	
110.00		520.72	0.65	-0.07	0.02	-17.72	
115.00		575.85	0.71	-0.09	0.03	-23.20	
120.00		561.85	0.77	-0.11	0.05	-24.20	
125.00		547.84	0.84	-0.12	0.06	-23.25	
130.00		533.83	0.90	-0.12	0.09	-20.57	
132.50	Bot - Section 4	261.66	0.94	-0.12	0.10	-9.26	
135.00		442.05	0.97	-0.12	0.12	-13.92	
136.50	Top - Section 3	262.37	1.00	-0.11	0.13	-7.55	
140.00		251.27	1.05	-0.09	0.16	-5.37	
145.00		350.62	1.12	-0.06	0.20	-2.91	
148.00	Appurtenance(s)	421.66	1.17	-0.02	0.23	0.43	
150.00		135.15	1.20	0.01	0.26	1.06	
155.00		331.00	1.28	0.10	0.32	8.92	
158.00	Appurtenance(s)	1823.9	1.33	0.17	0.37	72.81	
160.00		127.30	1.37	0.23	0.40	6.26	



## Seismic Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 37

165.00		311.39	1.46	0.40	0.49	23.20
168.00	Appurtenance(s)	1196.1	1.51	0.52	0.55	109.15
168.50	Appurtenance(s)	1530.0	1.52	0.55	0.56	144.06
170.00		89.44	1.55	0.62	0.60	9.22
175.00		291.77	1.64	0.90	0.72	39.35
178.00	Top - Section 4	170.35	1.69	1.10	0.81	26.49
180.00		96.44	1.73	1.25	0.87	16.39
184.00	Appurtenance(s)	1692.8	1.81	1.59	1.00	339.47
185.00		48.22	1.83	1.68	1.03	10.05
187.00	Appurtenance(s)	558.14	1.87	1.88	1.10	125.51
188.00		48.22	1.89	1.98	1.14	11.25
<b>Totals:</b>		<b>34,470.2</b>				<b>1,397.7</b>
						<b>Total Wind: 27,960.4</b>


Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required

## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



<b>Load Case: 1.2D + 1.0E</b>										<b>Iterations</b> 26
<b>Gust Response Factor</b> 1.10					<b>Sds</b> 0.19					<b>Ss</b> 0.17
<b>Dead Load Factor</b> 1.20			<b>Seismic Load Factor</b> 1.00			<b>Sd1</b> 0.10		<b>S1</b> 0.06		
<b>Wind Load Factor</b> 0.00			<b>Structure Frequency</b> 0.26			<b>SA</b> 0.03		<b>Seismic Importance Factor</b> 1.00		



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-49.04	-1.57	0.00	-205.20	0.00	205.20	5035.03	2517.52	10606.9	5311.37	0.00	0.00	0.00	0.036
5.00	-47.37	-1.56	0.00	-197.34	0.00	197.34	4978.38	2489.19	10316.4	5165.91	0.00	-0.01	0.036	
10.00	-45.73	-1.53	0.00	-189.54	0.00	189.54	4920.91	2460.46	10028.2	5021.57	0.02	-0.02	0.035	
15.00	-44.11	-1.51	0.00	-181.87	0.00	181.87	4862.63	2431.31	9742.31	4878.39	0.04	-0.03	0.034	
20.00	-42.51	-1.47	0.00	-174.35	0.00	174.35	4803.53	2401.76	9458.77	4736.42	0.08	-0.04	0.034	
25.00	-40.94	-1.44	0.00	-166.98	0.00	166.98	4743.61	2371.81	9177.73	4595.68	0.12	-0.05	0.033	
30.00	-39.39	-1.40	0.00	-159.78	0.00	159.78	4682.88	2341.44	8899.25	4456.24	0.17	-0.05	0.032	
32.83	-38.53	-1.38	0.00	-155.81	0.00	155.81	4648.14	2324.07	8742.80	4377.90	0.21	-0.06	0.032	
32.83	-38.53	-1.38	0.00	-155.81	0.00	155.81	4648.14	2324.07	8742.80	4377.90	0.21	-0.06	0.032	
35.00	-37.87	-1.37	0.00	-152.81	0.00	152.81	4621.33	2310.66	8623.42	4318.12	0.23	-0.06	0.032	
40.00	-36.36	-1.34	0.00	-145.95	0.00	145.95	4558.96	2279.48	8350.33	4181.37	0.31	-0.08	0.043	
43.25	-35.40	-1.31	0.00	-141.61	0.00	141.61	4517.98	2258.99	8174.32	4093.24	0.36	-0.09	0.042	
45.00	-34.51	-1.29	0.00	-139.31	0.00	139.31	4495.78	2247.89	8080.06	4046.03	0.40	-0.09	0.042	
48.92	-32.52	-1.23	0.00	-134.25	0.00	134.25	4445.67	2222.84	7870.19	3940.94	0.48	-0.10	0.030	
49.00	-32.48	-1.23	0.00	-134.15	0.00	134.15	3699.57	1849.78	6681.20	3345.56	0.48	-0.10	0.032	
50.00	-32.22	-1.23	0.00	-132.92	0.00	132.92	3689.91	1844.95	6638.39	3324.13	0.50	-0.10	0.034	
55.00	-30.94	-1.20	0.00	-126.78	0.00	126.78	3641.14	1820.57	6425.47	3217.51	0.61	-0.11	0.034	
60.00	-29.68	-1.17	0.00	-120.80	0.00	120.80	3591.55	1795.77	6214.50	3111.87	0.74	-0.12	0.033	
65.00	-28.45	-1.13	0.00	-114.97	0.00	114.97	3541.14	1770.57	6005.55	3007.24	0.87	-0.13	0.032	
70.00	-27.23	-1.10	0.00	-109.30	0.00	109.30	3489.91	1744.96	5798.71	2903.67	1.02	-0.14	0.031	
75.00	-26.03	-1.08	0.00	-103.78	0.00	103.78	3437.87	1718.94	5594.07	2801.19	1.17	-0.15	0.030	
76.83	-25.60	-1.07	0.00	-101.81	0.00	101.81	3418.62	1709.31	5519.73	2763.97	1.23	-0.16	0.030	
76.83	-25.60	-1.07	0.00	-101.81	0.00	101.81	3418.62	1709.31	5519.73	2763.97	1.23	-0.16	0.030	
80.00	-24.85	-1.06	0.00	-98.42	0.00	98.42	3385.02	1692.51	5391.70	2699.86	1.34	-0.16	0.044	
85.00	-23.69	-1.04	0.00	-93.14	0.00	93.14	3331.35	1665.67	5191.69	2599.71	1.52	-0.18	0.043	
87.50	-23.12	-1.03	0.00	-90.55	0.00	90.55	3304.20	1652.10	5092.60	2550.09	1.62	-0.19	0.043	
90.00	-22.17	-1.02	0.00	-87.96	0.00	87.96	3276.86	1638.43	4994.13	2500.78	1.72	-0.20	0.042	
91.92	-21.45	-1.02	0.00	-86.00	0.00	86.00	3255.72	1627.86	4918.94	2463.13	1.80	-0.20	0.029	
92.25	-21.32	-1.02	0.00	-85.66	0.00	85.66	2609.22	1304.61	4017.17	2011.57	1.81	-0.20	0.031	
95.00	-20.78	-1.02	0.00	-82.86	0.00	82.86	2587.46	1293.73	3934.74	1970.29	1.93	-0.21	0.034	
100.00	-19.82	-1.02	0.00	-77.75	0.00	77.75	2547.26	1273.63	3786.04	1895.83	2.16	-0.22	0.032	
105.00	-18.87	-1.02	0.00	-72.65	0.00	72.65	2506.24	1253.12	3638.92	1822.16	2.39	-0.23	0.031	
105.58	-18.76	-1.02	0.00	-72.06	0.00	72.06	2501.42	1250.71	3621.96	1813.67	2.42	-0.23	0.031	
105.58	-18.76	-1.02	0.00	-72.06	0.00	72.06	2501.42	1250.71	3621.96	1813.67	2.42	-0.23	0.031	
110.00	-17.94	-1.02	0.00	-67.54	0.00	67.54	2464.40	1232.20	3493.46	1749.33	2.65	-0.25	0.046	
115.00	-17.02	-1.02	0.00	-62.43	0.00	62.43	2421.75	1210.87	3349.75	1677.36	2.91	-0.26	0.044	
120.00	-16.13	-1.02	0.00	-57.32	0.00	57.32	2378.28	1189.14	3207.87	1606.32	3.20	-0.28	0.042	
125.00	-15.24	-1.02	0.00	-52.20	0.00	52.20	2333.99	1167.00	3067.90	1536.23	3.50	-0.30	0.041	
130.00	-14.38	-1.02	0.00	-47.07	0.00	47.07	2288.89	1144.45	2929.94	1467.15	3.82	-0.32	0.038	
132.50	-13.95	-1.02	0.00	-44.52	0.00	44.52	2266.03	1133.02	2861.73	1432.99	3.99	-0.32	0.037	
135.00	-13.31	-1.02	0.00	-41.96	0.00	41.96	2239.33	1119.66	2789.52	1396.83	4.16	-0.33	0.036	
136.50	-12.93	-1.02	0.00	-40.43	0.00	40.43	1414.34	707.17	1783.76	893.21	4.27	-0.34	0.054	
140.00	-12.47	-1.02	0.00	-36.86	0.00	36.86	1397.90	698.95	1729.39	865.98	4.52	-0.35	0.051	
145.00	-11.83	-1.02	0.00	-31.75	0.00	31.75	1373.73	686.86	1652.26	827.36	4.89	-0.37	0.047	
148.00	-11.18	-1.02	0.00	-28.69	0.00	28.69	1358.83	679.41	1606.31	804.35	5.13	-0.38	0.044	
150.00	-10.95	-1.02	0.00	-26.66	0.00	26.66	1348.73	674.37	1575.83	789.09	5.29	-0.39	0.042	
155.00	-10.36	-1.01	0.00	-21.57	0.00	21.57	1322.92	661.46	1500.20	751.22	5.71	-0.41	0.037	

## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 39

158.00	-8.06	-0.92	0.00	-18.55	0.00	18.55	1307.05	653.52	1455.24	728.70	5.96	-0.41	0.032
160.00	-7.86	-0.91	0.00	-16.72	0.00	16.72	1296.30	648.15	1425.45	713.78	6.14	-0.42	0.029
165.00	-7.36	-0.89	0.00	-12.15	0.00	12.15	1268.86	634.43	1351.65	676.83	6.59	-0.43	0.024
168.00	-5.85	-0.77	0.00	-9.50	0.00	9.50	1252.00	626.00	1307.87	654.91	6.86	-0.44	0.019
168.50	-4.01	-0.61	0.00	-9.11	0.00	9.11	1249.16	624.58	1300.61	651.27	6.91	-0.44	0.017
170.00	-3.86	-0.60	0.00	-8.20	0.00	8.20	1240.60	620.30	1278.90	640.40	7.05	-0.44	0.016
175.00	-3.40	-0.56	0.00	-5.21	0.00	5.21	1211.52	605.76	1207.28	604.54	7.51	-0.45	0.011
178.00	-3.13	-0.53	0.00	-3.54	0.00	3.54	1193.69	596.84	1164.89	583.31	7.80	-0.45	0.009
178.00	-3.13	-0.53	0.00	-3.54	0.00	3.54	975.84	487.92	954.81	478.11	7.80	-0.45	0.011
180.00	-2.97	-0.51	0.00	-2.49	0.00	2.49	975.84	487.92	954.81	478.11	7.98	-0.45	0.008
184.00	-0.85	-0.15	0.00	-0.45	0.00	0.45	975.84	487.92	954.81	478.11	8.37	-0.45	0.002
185.00	-0.77	-0.14	0.00	-0.30	0.00	0.30	975.84	487.92	954.81	478.11	8.46	-0.46	0.001
187.00	-0.06	-0.01	0.00	-0.01	0.00	0.01	975.84	487.92	954.81	478.11	8.65	-0.46	0.000
188.00	0.00	-0.01	0.00	0.00	0.00	0.00	975.84	487.92	954.81	478.11	8.75	-0.46	0.000


## Seismic Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 40

<b>Load Case:</b> 0.9D + 1.0E					<b>Iterations</b> 26
<b>Gust Response Factor</b>	1.10			<b>Sds</b> 0.19	<b>Ss</b> 0.17
<b>Dead Load Factor</b>	0.90	<b>Seismic Load Factor</b>	1.00	<b>Sd1</b> 0.10	<b>S1</b> 0.06
<b>Wind Load Factor</b>	0.00	<b>Structure Frequency</b>	0.26	<b>SA</b> 0.03	<b>Seismic Importance Factor</b> 1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00	RB1	0.00	0.00	0.00	0.00	0.00	
5.00		1202.2	0.00	0.03	0.01	21.45	
10.00		1182.6	0.01	0.05	0.03	31.04	
15.00		1163.0	0.01	0.06	0.03	35.78	
20.00		1143.3	0.02	0.06	0.04	38.07	
25.00		1123.7	0.03	0.07	0.04	39.09	
30.00		1104.1	0.05	0.07	0.04	39.46	
32.83	RT1	616.26	0.06	0.07	0.04	22.29	
35.00		468.28	0.07	0.07	0.04	17.08	
40.00		1064.9	0.09	0.07	0.04	39.61	
43.25	Bot - Section 2	681.69	0.10	0.07	0.04	25.68	
45.00		681.08	0.11	0.07	0.04	25.83	
48.92	RB2	1509.4	0.13	0.07	0.03	58.13	
49.00	Top - Section 1	30.57	0.13	0.07	0.03	1.18	
50.00		177.78	0.13	0.07	0.03	6.87	
55.00		878.82	0.16	0.07	0.03	34.54	
60.00		862.01	0.19	0.06	0.02	34.15	
65.00		845.20	0.23	0.06	0.02	33.22	
70.00		828.39	0.26	0.05	0.02	31.45	
75.00		811.58	0.30	0.05	0.01	28.49	
76.83	RT2	292.84	0.32	0.04	0.01	9.83	
80.00		501.94	0.34	0.03	0.01	15.13	
85.00		777.96	0.39	0.02	0.01	17.60	
87.50	Bot - Section 3	382.68	0.41	0.02	0.01	6.83	
90.00		699.67	0.43	0.01	0.01	8.72	
91.92	RB3	532.12	0.45	0.00	0.01	4.24	
92.25	Top - Section 2	91.00	0.46	0.00	0.01	0.65	
95.00		345.80	0.48	-0.01	0.01	0.09	
100.00		617.88	0.53	-0.03	0.01	-7.82	
105.00		603.87	0.59	-0.05	0.01	-14.83	
105.58	RT3	69.14	0.60	-0.05	0.01	-1.78	
110.00		520.72	0.65	-0.07	0.02	-17.72	
115.00		575.85	0.71	-0.09	0.03	-23.20	
120.00		561.85	0.77	-0.11	0.05	-24.20	
125.00		547.84	0.84	-0.12	0.06	-23.25	
130.00		533.83	0.90	-0.12	0.09	-20.57	
132.50	Bot - Section 4	261.66	0.94	-0.12	0.10	-9.26	
135.00		442.05	0.97	-0.12	0.12	-13.92	
136.50	Top - Section 3	262.37	1.00	-0.11	0.13	-7.55	
140.00		251.27	1.05	-0.09	0.16	-5.37	
145.00		350.62	1.12	-0.06	0.20	-2.91	
148.00	Appurtenance(s)	421.66	1.17	-0.02	0.23	0.43	
150.00		135.15	1.20	0.01	0.26	1.06	
155.00		331.00	1.28	0.10	0.32	8.92	
158.00	Appurtenance(s)	1823.9	1.33	0.17	0.37	72.81	
160.00		127.30	1.37	0.23	0.40	6.26	

## Seismic Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 41

165.00		311.39	1.46	0.40	0.49	23.20
168.00	Appurtenance(s)	1196.1	1.51	0.52	0.55	109.15
168.50	Appurtenance(s)	1530.0	1.52	0.55	0.56	144.06
170.00		89.44	1.55	0.62	0.60	9.22
175.00		291.77	1.64	0.90	0.72	39.35
178.00	Top - Section 4	170.35	1.69	1.10	0.81	26.49
180.00		96.44	1.73	1.25	0.87	16.39
184.00	Appurtenance(s)	1692.8	1.81	1.59	1.00	339.47
185.00		48.22	1.83	1.68	1.03	10.05
187.00	Appurtenance(s)	558.14	1.87	1.88	1.10	125.51
188.00		48.22	1.89	1.98	1.14	11.25
<b>Totals:</b>		<b>34,470.2</b>				<b>1,397.7</b>
						<b>Total Wind: 27,960.4</b>

Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required


## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	<b>7/31/2017</b>
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 42

<b>Load Case: 0.9D + 1.0E</b>							<b>Iterations</b> 26
<b>Gust Response Factor</b>	1.10				<b>Sds</b>	0.19	<b>Ss</b> 0.17
<b>Dead Load Factor</b>	0.90	<b>Seismic Load Factor</b>	1.00	<b>Sd1</b>	0.10		<b>S1</b> 0.06
<b>Wind Load Factor</b>	0.00	<b>Structure Frequency</b>	0.26	<b>SA</b>	0.03	<b>Seismic Importance Factor</b>	1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-36.78	-1.57	0.00	-202.39	0.00	202.39	5035.03	2517.52	10606.9	5311.37	0.00	0.00	0.00	0.034
5.00	-35.53	-1.56	0.00	-194.53	0.00	194.53	4978.38	2489.19	10316.4	5165.91	0.00	-0.01	0.033	
10.00	-34.30	-1.53	0.00	-186.75	0.00	186.75	4920.91	2460.46	10028.2	5021.57	0.02	-0.02	0.033	
15.00	-33.08	-1.50	0.00	-179.10	0.00	179.10	4862.63	2431.31	9742.31	4878.39	0.04	-0.03	0.032	
20.00	-31.89	-1.47	0.00	-171.61	0.00	171.61	4803.53	2401.76	9458.77	4736.42	0.08	-0.04	0.032	
25.00	-30.71	-1.43	0.00	-164.28	0.00	164.28	4743.61	2371.81	9177.73	4595.68	0.12	-0.04	0.031	
30.00	-29.54	-1.39	0.00	-157.13	0.00	157.13	4682.88	2341.44	8899.25	4456.24	0.17	-0.05	0.030	
32.83	-28.89	-1.37	0.00	-153.19	0.00	153.19	4648.14	2324.07	8742.80	4377.90	0.20	-0.06	0.030	
32.83	-28.89	-1.37	0.00	-153.19	0.00	153.19	4648.14	2324.07	8742.80	4377.90	0.20	-0.06	0.030	
35.00	-28.40	-1.36	0.00	-150.21	0.00	150.21	4621.33	2310.66	8623.42	4318.12	0.23	-0.06	0.041	
40.00	-27.27	-1.32	0.00	-143.41	0.00	143.41	4558.96	2279.48	8350.33	4181.37	0.30	-0.08	0.040	
43.25	-26.55	-1.30	0.00	-139.11	0.00	139.11	4517.98	2258.99	8174.32	4093.24	0.36	-0.08	0.040	
45.00	-25.88	-1.28	0.00	-136.84	0.00	136.84	4495.78	2247.89	8080.06	4046.03	0.39	-0.09	0.040	
48.92	-24.39	-1.22	0.00	-131.84	0.00	131.84	4445.67	2222.84	7870.19	3940.94	0.47	-0.10	0.028	
49.00	-24.36	-1.22	0.00	-131.74	0.00	131.74	3699.57	1849.78	6681.20	3345.56	0.47	-0.10	0.030	
50.00	-24.16	-1.21	0.00	-130.52	0.00	130.52	3689.91	1844.95	6638.39	3324.13	0.49	-0.10	0.032	
55.00	-23.21	-1.18	0.00	-124.46	0.00	124.46	3641.14	1820.57	6425.47	3217.51	0.60	-0.11	0.032	
60.00	-22.26	-1.15	0.00	-118.56	0.00	118.56	3591.55	1795.77	6214.50	3111.87	0.72	-0.12	0.031	
65.00	-21.33	-1.12	0.00	-112.82	0.00	112.82	3541.14	1770.57	6005.55	3007.24	0.86	-0.13	0.030	
70.00	-20.42	-1.09	0.00	-107.24	0.00	107.24	3489.91	1744.96	5798.71	2903.67	1.00	-0.14	0.029	
75.00	-19.52	-1.06	0.00	-101.81	0.00	101.81	3437.87	1718.94	5594.07	2801.19	1.15	-0.15	0.029	
76.83	-19.20	-1.05	0.00	-99.87	0.00	99.87	3418.62	1709.31	5519.73	2763.97	1.21	-0.16	0.028	
76.83	-19.20	-1.05	0.00	-99.87	0.00	99.87	3418.62	1709.31	5519.73	2763.97	1.21	-0.16	0.028	
80.00	-18.64	-1.04	0.00	-96.55	0.00	96.55	3385.02	1692.51	5391.70	2699.86	1.32	-0.16	0.041	
85.00	-17.77	-1.02	0.00	-91.37	0.00	91.37	3331.35	1665.67	5191.69	2599.71	1.50	-0.18	0.040	
87.50	-17.34	-1.01	0.00	-88.82	0.00	88.82	3304.20	1652.10	5092.60	2550.09	1.59	-0.19	0.040	
90.00	-16.63	-1.00	0.00	-86.29	0.00	86.29	3276.86	1638.43	4994.13	2500.78	1.69	-0.19	0.040	
91.92	-16.08	-1.00	0.00	-84.36	0.00	84.36	3255.72	1627.86	4918.94	2463.13	1.77	-0.20	0.028	
92.25	-15.99	-1.00	0.00	-84.03	0.00	84.03	2609.22	1304.61	4017.17	2011.57	1.78	-0.20	0.029	
95.00	-15.59	-1.00	0.00	-81.28	0.00	81.28	2587.46	1293.73	3934.74	1970.29	1.90	-0.21	0.032	
100.00	-14.86	-1.00	0.00	-76.28	0.00	76.28	2547.26	1273.63	3786.04	1895.83	2.12	-0.22	0.031	
105.00	-14.15	-1.00	0.00	-71.28	0.00	71.28	2506.24	1253.12	3638.92	1822.16	2.35	-0.23	0.030	
105.58	-14.07	-1.00	0.00	-70.70	0.00	70.70	2501.42	1250.71	3621.96	1813.67	2.38	-0.23	0.029	
105.58	-14.07	-1.00	0.00	-70.70	0.00	70.70	2501.42	1250.71	3621.96	1813.67	2.38	-0.23	0.029	
110.00	-13.45	-1.00	0.00	-66.28	0.00	66.28	2464.40	1232.20	3493.46	1749.33	2.60	-0.24	0.043	
115.00	-12.77	-1.00	0.00	-61.27	0.00	61.27	2421.75	1210.87	3349.75	1677.36	2.86	-0.26	0.042	
120.00	-12.09	-1.00	0.00	-56.26	0.00	56.26	2378.28	1189.14	3207.87	1606.32	3.14	-0.28	0.040	
125.00	-11.43	-1.00	0.00	-51.25	0.00	51.25	2333.99	1167.00	3067.90	1536.23	3.44	-0.29	0.038	
130.00	-10.78	-1.00	0.00	-46.23	0.00	46.23	2288.89	1144.45	2929.94	1467.15	3.76	-0.31	0.036	
132.50	-10.46	-1.00	0.00	-43.73	0.00	43.73	2266.03	1133.02	2861.73	1432.99	3.92	-0.32	0.035	
135.00	-9.98	-1.00	0.00	-41.22	0.00	41.22	2239.33	1119.66	2789.52	1396.83	4.09	-0.33	0.034	
136.50	-9.70	-1.00	0.00	-39.72	0.00	39.72	1414.34	707.17	1783.76	893.21	4.19	-0.33	0.051	
140.00	-9.35	-1.00	0.00	-36.23	0.00	36.23	1397.90	698.95	1729.39	865.98	4.44	-0.34	0.049	
145.00	-8.87	-1.00	0.00	-31.22	0.00	31.22	1373.73	686.86	1652.26	827.36	4.81	-0.36	0.044	
148.00	-8.39	-1.00	0.00	-28.22	0.00	28.22	1358.83	679.41	1606.31	804.35	5.04	-0.37	0.041	
150.00	-8.21	-1.00	0.00	-26.23	0.00	26.23	1348.73	674.37	1575.83	789.09	5.20	-0.38	0.039	
155.00	-7.77	-0.99	0.00	-21.24	0.00	21.24	1322.92	661.46	1500.20	751.22	5.61	-0.40	0.034	

## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 43

158.00	-6.05	-0.90	0.00	-18.28	0.00	18.28	1307.05	653.52	1455.24	728.70	5.86	-0.41	0.030
160.00	-5.89	-0.90	0.00	-16.47	0.00	16.47	1296.30	648.15	1425.45	713.78	6.03	-0.41	0.028
165.00	-5.52	-0.87	0.00	-11.99	0.00	11.99	1268.86	634.43	1351.65	676.83	6.47	-0.42	0.022
168.00	-4.39	-0.75	0.00	-9.37	0.00	9.37	1252.00	626.00	1307.87	654.91	6.74	-0.43	0.018
168.50	-3.00	-0.60	0.00	-9.00	0.00	9.00	1249.16	624.58	1300.61	651.27	6.79	-0.43	0.016
170.00	-2.90	-0.59	0.00	-8.10	0.00	8.10	1240.60	620.30	1278.90	640.40	6.92	-0.43	0.015
175.00	-2.55	-0.55	0.00	-5.15	0.00	5.15	1211.52	605.76	1207.28	604.54	7.38	-0.44	0.011
178.00	-2.35	-0.52	0.00	-3.50	0.00	3.50	1193.69	596.84	1164.89	583.31	7.66	-0.44	0.008
178.00	-2.35	-0.52	0.00	-3.50	0.00	3.50	975.84	487.92	954.81	478.11	7.66	-0.44	0.010
180.00	-2.23	-0.50	0.00	-2.46	0.00	2.46	975.84	487.92	954.81	478.11	7.85	-0.45	0.007
184.00	-0.64	-0.15	0.00	-0.45	0.00	0.45	975.84	487.92	954.81	478.11	8.22	-0.45	0.002
185.00	-0.58	-0.14	0.00	-0.29	0.00	0.29	975.84	487.92	954.81	478.11	8.31	-0.45	0.001
187.00	-0.04	-0.01	0.00	-0.01	0.00	0.01	975.84	487.92	954.81	478.11	8.50	-0.45	0.000
188.00	0.00	-0.01	0.00	0.00	0.00	0.00	975.84	487.92	954.81	478.11	8.59	-0.45	0.000


## Wind Loading - Shaft

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Load Case: 1.0D + 1.0W 60 mph Wind

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



Iterations 27

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	1.00	0.85	7.442	8.19	242.19	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.85	7.442	8.19	238.30	0.650	0.000	5.00	21.715	14.11	115.5	0.0	1202.2
10.00		1.00	0.85	7.442	8.19	234.42	0.650	0.000	5.00	21.364	13.89	113.7	0.0	1182.6
15.00		1.00	0.85	7.442	8.19	230.53	0.650	0.000	5.00	21.013	13.66	111.8	0.0	1163.0
20.00		1.00	0.90	7.896	8.69	233.46	0.650	0.000	5.00	20.662	13.43	116.7	0.0	1143.4
25.00		1.00	0.95	8.276	9.10	234.91	0.650	0.000	5.00	20.310	13.20	120.2	0.0	1123.8
30.00		1.00	0.98	8.600	9.46	235.29	0.650	0.000	5.00	19.959	12.97	122.7	0.0	1104.2
32.83	RT1	1.00	1.00	8.765	9.64	235.14	0.650	0.000	2.83	11.141	7.24	69.8	0.0	616.3
35.00		1.00	1.01	8.883	9.77	234.89	0.650	0.000	2.17	8.467	5.50	53.8	0.0	468.3
40.00		1.00	1.04	9.137	10.05	233.91	0.650	0.000	5.00	19.257	12.52	125.8	0.0	1064.9
43.25	Bot - Section 2	1.00	1.06	9.288	10.22	233.02	0.650	0.000	3.25	12.329	8.01	81.9	0.0	681.7
45.00		1.00	1.07	9.366	10.30	232.47	0.650	0.000	1.75	6.688	4.35	44.8	0.0	681.1
48.92	RB2	1.00	1.09	9.532	10.49	231.07	0.650	0.000	3.92	14.825	9.64	101.0	0.0	1509.4
49.00	Top - Section 1	1.00	1.09	9.536	10.49	231.04	0.650	0.000	0.08	0.300	0.20	2.0	0.0	30.6
50.00		1.00	1.09	9.576	10.53	234.64	0.650	0.000	1.00	3.746	2.44	25.7	0.0	177.8
55.00		1.00	1.12	9.770	10.75	232.55	0.650	0.000	5.00	18.520	12.04	129.4	0.0	878.8
60.00		1.00	1.14	9.951	10.95	230.20	0.650	0.000	5.00	18.169	11.81	129.3	0.0	862.0
65.00		1.00	1.16	10.120	11.13	227.61	0.650	0.000	5.00	17.818	11.58	128.9	0.0	845.2
70.00		1.00	1.17	10.279	11.31	224.83	0.650	0.000	5.00	17.467	11.35	128.4	0.0	828.4
75.00		1.00	1.19	10.430	11.47	221.87	0.650	0.000	5.00	17.115	11.13	127.6	0.0	811.6
76.83	RT2	1.00	1.20	10.483	11.53	220.74	0.650	0.000	1.83	6.176	4.01	46.3	0.0	292.8
80.00		1.00	1.21	10.572	11.63	218.75	0.650	0.000	3.17	10.588	6.88	80.0	0.0	501.9
85.00		1.00	1.22	10.708	11.78	215.49	0.650	0.000	5.00	16.413	10.67	125.7	0.0	778.0
87.50	Bot - Section 3	1.00	1.23	10.774	11.85	213.81	0.650	0.000	2.50	8.075	5.25	62.2	0.0	382.7
90.00		1.00	1.24	10.838	11.92	212.10	0.650	0.000	2.50	8.119	5.28	62.9	0.0	699.7
91.92	RB3	1.00	1.24	10.886	11.97	210.77	0.650	0.000	1.92	6.176	4.01	48.1	0.0	532.1
92.25	Top - Section 2	1.00	1.24	10.894	11.98	210.53	0.650	0.000	0.33	1.056	0.69	8.2	0.0	91.0
95.00		1.00	1.25	10.962	12.06	212.14	0.650	0.000	2.75	8.743	5.68	68.5	0.0	345.8
100.00		1.00	1.27	11.081	12.19	208.55	0.650	0.000	5.00	15.624	10.16	123.8	0.0	617.9
105.00		1.00	1.28	11.195	12.31	204.86	0.650	0.000	5.00	15.273	9.93	122.2	0.0	603.9
105.58	RT3	1.00	1.28	11.208	12.33	204.42	0.650	0.000	0.58	1.749	1.14	14.0	0.0	69.1
110.00		1.00	1.29	11.305	12.44	201.07	0.650	0.000	4.42	13.172	8.56	106.5	0.0	520.7
115.00		1.00	1.30	11.412	12.55	197.21	0.650	0.000	5.00	14.570	9.47	118.9	0.0	575.9
120.00		1.00	1.32	11.514	12.67	193.26	0.650	0.000	5.00	14.219	9.24	117.1	0.0	561.8
125.00		1.00	1.33	11.614	12.78	189.24	0.650	0.000	5.00	13.868	9.01	115.2	0.0	547.8
130.00		1.00	1.34	11.710	12.88	185.14	0.650	0.000	5.00	13.516	8.79	113.2	0.0	533.8
132.50	Bot - Section 4	1.00	1.34	11.757	12.93	183.07	0.650	0.000	2.50	6.627	4.31	55.7	0.0	261.7
135.00		1.00	1.35	11.803	12.98	180.99	0.650	0.000	2.50	6.631	4.31	56.0	0.0	442.1
136.50	Top - Section 3	1.00	1.35	11.831	13.01	179.73	0.650	0.000	1.50	3.937	2.56	33.3	0.0	262.4
140.00		1.00	1.36	11.894	13.08	179.36	0.650	0.000	3.50	9.063	5.89	77.1	0.0	251.3
145.00		1.00	1.37	11.982	13.18	175.09	0.650	0.000	5.00	12.648	8.22	108.4	0.0	350.6
148.00	Appurtenance(s)	1.00	1.37	12.034	13.24	172.51	0.650	0.000	3.00	7.420	4.82	63.8	0.0	205.7
150.00		1.00	1.38	12.068	13.27	170.77	0.650	0.000	2.00	4.877	3.17	42.1	0.0	135.1
155.00		1.00	1.39	12.152	13.37	166.39	0.650	0.000	5.00	11.946	7.76	103.8	0.0	331.0
158.00	Appurtenance(s)	1.00	1.39	12.201	13.42	163.75	0.650	0.000	3.00	6.999	4.55	61.1	0.0	193.9
160.00		1.00	1.40	12.233	13.46	161.97	0.650	0.000	2.00	4.596	2.99	40.2	0.0	127.3
165.00		1.00	1.41	12.313	13.54	157.50	0.650	0.000	5.00	11.243	7.31	99.0	0.0	311.4



## Wind Loading - Shaft

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 45

168.00 Appurtenance(s)	1.00	1.41	12.360	13.60	154.79	0.650	0.000	3.00	6.577	4.28	58.1	0.0	182.1	
168.50 Appurtenance(s)	1.00	1.41	12.367	13.60	154.34	0.650	0.000	0.50	1.084	0.70	9.6	0.0	30.0	
170.00	1.00	1.42	12.390	13.63	152.98	0.650	0.000	1.50	3.231	2.10	28.6	0.0	89.4	
175.00	1.00	1.42	12.466	13.71	148.42	0.650	0.000	5.00	10.541	6.85	94.0	0.0	291.8	
178.00 Top - Section 4	1.00	1.43	12.511	13.76	145.66	0.650	0.000	3.00	6.156	4.00	55.1	0.0	170.4	
180.00	1.00	1.43	12.540	13.79	145.83	0.650	0.000	2.00	4.062	2.64	36.4	0.0	96.4	
184.00 Appurtenance(s)	1.00	1.44	12.599	13.86	146.17	0.650	0.000	4.00	8.123	5.28	73.2	0.0	192.9	
185.00	1.00	1.44	12.613	13.87	146.25	0.650	0.000	1.00	2.031	1.32	18.3	0.0	48.2	
187.00 Appurtenance(s)	1.00	1.44	12.642	13.91	146.42	0.650	0.000	2.00	4.062	2.64	36.7	0.0	96.4	
188.00	1.00	1.45	12.656	13.92	146.50	0.650	0.000	1.00	2.031	1.32	18.4	0.0	48.2	
<b>Totals:</b>							<b>188.00</b>					<b>4,350.4</b>	<b>28,148.4</b>	

## Discrete Appurtenance Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 46

**Load Case:** 1.0D + 1.0W 60 mph Wind

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations** 27

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)	
1	187.00	LNx-6515DS-A1M	3	12.642	13.906	0.64	0.80	22.02	149.40	0.000	0.000	306.24	0.00	0.00	
2	187.00	APXV18-209014	3	12.642	13.906	0.59	0.80	6.36	56.10	0.000	0.000	88.41	0.00	0.00	
3	187.00	782 11054	3	12.642	13.906	0.54	0.80	0.35	5.40	0.000	0.000	4.92	0.00	0.00	
4	187.00	KRY 112 144-1	12	12.642	13.906	0.54	0.80	2.64	132.00	0.000	0.000	36.67	0.00	0.00	
5	187.00	APX16PV-16-PVL-E	3	12.642	13.906	0.50	0.80	8.97	118.80	0.000	0.000	124.77	0.00	0.00	
6	184.00	Low Profile Platform	1	12.599	13.858	1.00	1.00	22.00	1500.00	0.000	0.000	304.88	0.00	0.00	
7	168.50	Low Profile Platform	1	12.367	13.604	1.00	1.00	22.00	1500.00	0.000	0.000	299.29	0.00	0.00	
8	168.00	APXV9ERR18-C-A20	1	12.360	13.596	0.66	0.80	5.33	62.00	0.000	0.000	72.40	0.00	0.00	
9	168.00	ACU-A20-N	4	12.360	13.596	0.80	0.80	0.45	4.00	0.000	0.000	6.09	0.00	0.00	
10	168.00	TD-RRH8x20-25	3	12.360	13.596	0.54	0.80	6.51	210.00	0.000	0.000	88.54	0.00	0.00	
11	168.00	800 MHz RRH	3	12.360	13.596	0.54	0.80	4.73	162.00	0.000	0.000	64.27	0.00	0.00	
12	168.00	1900 MHz RRH	3	12.360	13.596	0.54	0.80	4.73	132.00	0.000	0.000	64.27	0.00	0.00	
13	168.00	APXVTM14-C-120	3	12.360	13.596	0.63	0.80	12.02	168.00	0.000	0.000	163.43	0.00	0.00	
14	168.00	800 MHz Filters	3	12.360	13.596	0.54	0.80	4.73	162.00	0.000	0.000	64.27	0.00	0.00	
15	168.00	APXVSP18-C-A20	2	12.360	13.596	0.66	0.80	10.65	114.00	0.000	0.000	144.80	0.00	0.00	
16	158.00	T-Arm	3	12.201	13.421	0.50	0.75	12.06	900.00	0.000	0.000	161.86	0.00	0.00	
17	158.00	SBNH-1D6565C	1	12.201	13.421	0.64	0.80	7.34	66.10	0.000	0.000	98.52	0.00	0.00	
18	158.00	P65-17-XLH-RR	2	12.201	13.421	0.60	0.80	13.73	118.00	0.000	0.000	184.24	0.00	0.00	
19	158.00	LGP21401	6	12.201	13.421	0.54	0.80	4.05	105.00	0.000	0.000	54.38	0.00	0.00	
20	158.00	RRUS-11	6	12.201	13.421	0.54	0.80	8.10	304.20	0.000	0.000	108.77	0.00	0.00	
21	158.00	7770	3	12.201	13.421	0.58	0.80	9.64	105.00	0.000	0.000	129.32	0.00	0.00	
22	158.00	DC-48-60-18-8F	1	12.201	13.421	0.80	0.80	1.18	31.80	0.000	0.000	15.78	0.00	0.00	
23	148.00	742 213	3	12.034	13.238	0.58	0.80	8.85	66.00	0.000	0.000	117.12	0.00	0.00	
24	148.00	Flush Mount	1	12.034	13.238	1.00	1.00	5.00	150.00	0.000	0.000	66.19	0.00	0.00	
<b>Totals:</b>									<b>6,321.80</b>						<b>2,769.44</b>

## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II




Page: 47

**Load Case:** 1.0D + 1.0W 60 mph Wind

**Dead Load Factor** 1.00

**Wind Load Factor** 1.00



**Iterations** 27

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		115.55	1388.72	0.00	0.00
10.00		113.68	1369.11	0.00	0.00
15.00		111.81	1349.50	0.00	0.00
20.00		116.65	1329.88	0.00	0.00
25.00		120.18	1310.27	0.00	0.00
30.00		122.73	1290.66	0.00	0.00
32.83		69.82	721.82	0.00	0.00
35.00		53.78	549.23	0.00	0.00
40.00		125.80	1251.44	0.00	0.00
43.25		81.88	802.92	0.00	0.00
45.00		44.79	746.35	0.00	0.00
48.92		101.04	1655.64	0.00	0.00
49.00		2.05	33.56	0.00	0.00
50.00		25.65	215.08	0.00	0.00
55.00		129.38	1065.32	0.00	0.00
60.00		129.27	1048.51	0.00	0.00
65.00		128.93	1031.70	0.00	0.00
70.00		128.37	1014.89	0.00	0.00
75.00		127.63	998.08	0.00	0.00
76.83		46.29	361.10	0.00	0.00
80.00		80.03	620.18	0.00	0.00
85.00		125.66	964.46	0.00	0.00
87.50		62.20	475.93	0.00	0.00
90.00		62.92	792.92	0.00	0.00
91.92		48.07	603.73	0.00	0.00
92.25		8.23	103.31	0.00	0.00
95.00		68.52	448.38	0.00	0.00
100.00		123.78	804.38	0.00	0.00
105.00		122.25	790.37	0.00	0.00
105.58		14.02	90.78	0.00	0.00
110.00		106.48	685.59	0.00	0.00
115.00		118.88	762.35	0.00	0.00
120.00		117.06	748.35	0.00	0.00
125.00		115.15	734.34	0.00	0.00
130.00		113.17	720.33	0.00	0.00
132.50		55.70	354.91	0.00	0.00
135.00		55.96	535.30	0.00	0.00
136.50		33.30	318.32	0.00	0.00
140.00		77.07	381.82	0.00	0.00
145.00		108.36	537.12	0.00	0.00
148.00	(4) attachments	247.15	533.56	0.00	0.00
150.00		42.08	197.27	0.00	0.00
155.00		103.79	486.30	0.00	0.00
158.00	(22) attachments	813.93	1917.17	0.00	0.00
160.00		40.20	169.18	0.00	0.00
165.00		98.98	416.09	0.00	0.00

## Total Applied Force Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 48

168.00	(22) attachments	726.20	1258.94	0.00	0.00
168.50	(1) attachments	308.87	1539.37	0.00	0.00
170.00		28.62	117.52	0.00	0.00
175.00		93.95	385.37	0.00	0.00
178.00		55.07	226.51	0.00	0.00
180.00		36.42	133.88	0.00	0.00
184.00	(1) attachments	378.06	1767.76	0.00	0.00
185.00		18.31	66.94	0.00	0.00
187.00	(24) attachments	597.72	595.58	0.00	0.00
188.00		18.38	48.22	0.00	0.00
<b>Totals:</b>		<b>7,119.83</b>	<b>40,866.32</b>	<b>0.00</b>	<b>0.00</b>

## Linear Appurtenance Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 49

**Load Case:** 1.0D + 1.0W 60 mph Wind

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



**Iterations** 27

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.062	0.000	7.442	0.00	31.20
5.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.062	0.000	7.442	0.00	0.00
10.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.063	0.000	7.442	0.00	31.20
10.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.063	0.000	7.442	0.00	0.00
15.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.064	0.000	7.442	0.00	31.20
15.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.064	0.000	7.442	0.00	0.00
20.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.065	0.000	7.896	0.00	31.20
20.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.065	0.000	7.896	0.00	0.00
25.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.066	0.000	8.276	0.00	31.20
25.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.066	0.000	8.276	0.00	0.00
30.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.067	0.000	8.600	0.00	31.20
30.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.067	0.000	8.600	0.00	0.00
32.83	1 5/8" Coax	Yes	2.83	0.000	1.98	0.47	0.00	0.068	0.000	8.765	0.00	17.66
32.83	1.25" Reinforcing	Yes	2.83	0.000	1.25	0.29	0.00	0.068	0.000	8.765	0.00	0.00
35.00	1 5/8" Coax	Yes	2.17	0.000	1.98	0.36	0.00	0.069	0.000	8.883	0.00	13.54
35.00	1.25" Reinforcing	Yes	2.17	0.000	1.25	0.23	0.00	0.069	0.000	8.883	0.00	0.00
40.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.046	0.000	9.137	0.00	31.20
40.00	1.25" Reinforcing	Yes	0.50	0.000	1.25	0.05	0.00	0.046	0.000	9.137	0.00	0.00
43.25	1 5/8" Coax	Yes	3.25	0.000	1.98	0.54	0.00	0.043	0.000	9.288	0.00	20.28
45.00	1 5/8" Coax	Yes	1.75	0.000	1.98	0.29	0.00	0.044	0.000	9.366	0.00	10.92
48.92	1 5/8" Coax	Yes	3.92	0.000	1.98	0.65	0.00	0.062	0.000	9.532	0.00	24.46
48.92	1.25" Reinforcing	Yes	2.42	0.000	1.25	0.25	0.00	0.062	0.000	9.532	0.00	0.00
49.00	1 5/8" Coax	Yes	0.08	0.000	1.98	0.01	0.00	0.073	0.000	9.536	0.00	0.50
49.00	1.25" Reinforcing	Yes	0.08	0.000	1.25	0.01	0.00	0.073	0.000	9.536	0.00	0.00
50.00	1 5/8" Coax	Yes	1.00	0.000	1.98	0.17	0.00	0.072	0.000	9.576	0.00	6.24
50.00	1.25" Reinforcing	Yes	1.00	0.000	1.25	0.10	0.00	0.072	0.000	9.576	0.00	0.00
55.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.073	0.000	9.770	0.00	31.20
55.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.073	0.000	9.770	0.00	0.00
60.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.074	0.000	9.951	0.00	31.20
60.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.074	0.000	9.951	0.00	0.00
65.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.076	0.000	10.120	0.00	31.20
65.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.076	0.000	10.120	0.00	0.00
70.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.077	0.000	10.279	0.00	31.20
70.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.077	0.000	10.279	0.00	0.00
75.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.079	0.000	10.430	0.00	31.20
75.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.079	0.000	10.430	0.00	0.00
76.83	1 5/8" Coax	Yes	1.83	0.000	1.98	0.30	0.00	0.080	0.000	10.483	0.00	11.42
76.83	1.25" Reinforcing	Yes	1.83	0.000	1.25	0.19	0.00	0.080	0.000	10.483	0.00	0.00
80.00	1 5/8" Coax	Yes	3.17	0.000	1.98	0.52	0.00	0.073	0.000	10.572	0.00	19.78
80.00	1.25" Reinforcing	Yes	2.42	0.000	1.25	0.25	0.00	0.073	0.000	10.572	0.00	0.00
85.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.050	0.000	10.708	0.00	31.20
87.50	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.051	0.000	10.774	0.00	15.60
90.00	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.052	0.000	10.838	0.00	15.60
91.92	1 5/8" Coax	Yes	1.92	0.000	1.98	0.32	0.00	0.081	0.000	10.886	0.00	11.98
91.92	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.17	0.00	0.081	0.000	10.886	0.00	0.00
92.25	1 5/8" Coax	Yes	0.33	0.000	1.98	0.05	0.00	0.086	0.000	10.894	0.00	2.06
92.25	1.25" Reinforcing	Yes	0.33	0.000	1.25	0.03	0.00	0.086	0.000	10.894	0.00	0.00

## Linear Appurtenance Segment Forces (Factored)

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II




Page: 50

**Load Case:** 1.0D + 1.0W 60 mph Wind

**Dead Load Factor** 1.00

**Wind Load Factor** 1.00



**Iterations** 27

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
95.00	1 5/8" Coax	Yes	2.75	0.000	1.98	0.45	0.00	0.085	0.000	10.962	0.00	17.16
95.00	1.25" Reinforcing	Yes	2.75	0.000	1.25	0.29	0.00	0.085	0.000	10.962	0.00	0.00
100.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.086	0.000	11.081	0.00	31.20
100.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.086	0.000	11.081	0.00	0.00
105.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.088	0.000	11.195	0.00	31.20
105.00	1.25" Reinforcing	Yes	5.00	0.000	1.25	0.52	0.00	0.088	0.000	11.195	0.00	0.00
105.58	1 5/8" Coax	Yes	0.58	0.000	1.98	0.10	0.00	0.089	0.000	11.208	0.00	3.62
105.58	1.25" Reinforcing	Yes	0.58	0.000	1.25	0.06	0.00	0.089	0.000	11.208	0.00	0.00
110.00	1 5/8" Coax	Yes	4.42	0.000	1.98	0.73	0.00	0.069	0.000	11.305	0.00	27.58
110.00	1.25" Reinforcing	Yes	1.67	0.000	1.25	0.17	0.00	0.069	0.000	11.305	0.00	0.00
115.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.057	0.000	11.412	0.00	31.20
120.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.058	0.000	11.514	0.00	31.20
125.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.059	0.000	11.614	0.00	31.20
130.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.061	0.000	11.710	0.00	31.20
132.50	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.062	0.000	11.757	0.00	15.60
135.00	1 5/8" Coax	Yes	2.50	0.000	1.98	0.41	0.00	0.063	0.000	11.803	0.00	15.60
136.50	1 5/8" Coax	Yes	1.50	0.000	1.98	0.25	0.00	0.064	0.000	11.831	0.00	9.36
140.00	1 5/8" Coax	Yes	3.50	0.000	1.98	0.58	0.00	0.064	0.000	11.894	0.00	21.84
145.00	1 5/8" Coax	Yes	5.00	0.000	1.98	0.82	0.00	0.065	0.000	11.982	0.00	31.20
148.00	1 5/8" Coax	Yes	3.00	0.000	1.98	0.49	0.00	0.067	0.000	12.034	0.00	18.72
<b>Totals:</b>											<b>0.0</b>	<b>923.5</b>

# Calculated Forces

**Structure:** CT46124-A-SBA  
**Site Name:** Enfield-Moody Rd.  
**Height:** 188.00 (ft)  
**Base Elev:** 0.000 (ft)  
**Gh:** 1.1

**Code:** EIA/TIA-222-G  
**Exposure:** C  
**Crest Height:** 0.00  
**Site Class:** D - Stiff Soil  
**Struct Class:** II


7/31/2017  
 Page: 51



**Load Case:** 1.0D + 1.0W 60 mph Wind

**Iterations** 27

**Dead Load Factor** 1.00  
**Wind Load Factor** 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-40.86	-7.13	0.00	-906.84	0.00	906.84	5035.03	2517.52	10606.9	5311.37	0.00	0.000	0.000	0.134
5.00	-39.47	-7.04	0.00	-871.18	0.00	871.18	4978.38	2489.19	10316.4	5165.91	0.02	-0.040	0.000	0.132
10.00	-38.10	-6.96	0.00	-835.96	0.00	835.96	4920.91	2460.46	10028.2	5021.57	0.08	-0.080	0.000	0.129
15.00	-36.74	-6.87	0.00	-801.18	0.00	801.18	4862.63	2431.31	9742.31	4878.39	0.19	-0.120	0.000	0.127
20.00	-35.41	-6.77	0.00	-766.85	0.00	766.85	4803.53	2401.76	9458.77	4736.42	0.34	-0.161	0.000	0.125
25.00	-34.09	-6.67	0.00	-732.99	0.00	732.99	4743.61	2371.81	9177.73	4595.68	0.53	-0.201	0.000	0.122
30.00	-32.80	-6.56	0.00	-699.63	0.00	699.63	4682.88	2341.44	8899.25	4456.24	0.76	-0.242	0.000	0.119
32.83	-32.08	-6.50	0.00	-681.06	0.00	681.06	4648.14	2324.07	8742.80	4377.90	0.91	-0.265	0.000	0.118
32.83	-32.08	-6.50	0.00	-681.06	0.00	681.06	4648.14	2324.07	8742.80	4377.90	0.91	-0.265	0.000	0.118
35.00	-31.52	-6.47	0.00	-666.95	0.00	666.95	4621.33	2310.66	8623.42	4318.12	1.04	-0.283	0.000	0.161
40.00	-30.27	-6.36	0.00	-634.63	0.00	634.63	4558.96	2279.48	8350.33	4181.37	1.36	-0.339	0.000	0.158
43.25	-29.46	-6.28	0.00	-613.97	0.00	613.97	4517.98	2258.99	8174.32	4093.24	1.61	-0.376	0.000	0.157
45.00	-28.71	-6.25	0.00	-602.97	0.00	602.97	4495.78	2247.89	8080.06	4046.03	1.75	-0.396	0.000	0.155
48.92	-27.05	-6.15	0.00	-578.46	0.00	578.46	4445.67	2222.84	7870.19	3940.94	2.09	-0.441	0.000	0.111
49.00	-27.02	-6.15	0.00	-577.97	0.00	577.97	3699.57	1849.78	6681.20	3345.56	2.10	-0.441	0.000	0.118
50.00	-26.80	-6.13	0.00	-571.82	0.00	571.82	3689.91	1844.95	6638.39	3324.13	2.19	-0.450	0.000	0.126
55.00	-25.73	-6.02	0.00	-541.16	0.00	541.16	3641.14	1820.57	6425.47	3217.51	2.69	-0.494	0.000	0.123
60.00	-24.68	-5.90	0.00	-511.08	0.00	511.08	3591.55	1795.77	6214.50	3111.87	3.23	-0.537	0.000	0.119
65.00	-23.65	-5.77	0.00	-481.61	0.00	481.61	3541.14	1770.57	6005.55	3007.24	3.81	-0.581	0.000	0.115
70.00	-22.63	-5.65	0.00	-452.74	0.00	452.74	3489.91	1744.96	5798.71	2903.67	4.44	-0.624	0.000	0.111
75.00	-21.63	-5.52	0.00	-424.48	0.00	424.48	3437.87	1718.94	5594.07	2801.19	5.12	-0.667	0.000	0.107
76.83	-21.27	-5.48	0.00	-414.37	0.00	414.37	3418.62	1709.31	5519.73	2763.97	5.38	-0.683	0.000	0.106
76.83	-21.27	-5.48	0.00	-414.37	0.00	414.37	3418.62	1709.31	5519.73	2763.97	5.38	-0.683	0.000	0.106
80.00	-20.64	-5.41	0.00	-396.99	0.00	396.99	3385.02	1692.51	5391.70	2699.86	5.84	-0.710	0.000	0.153
85.00	-19.68	-5.29	0.00	-369.94	0.00	369.94	3331.35	1665.67	5191.69	2599.71	6.62	-0.772	0.000	0.148
87.50	-19.20	-5.23	0.00	-356.72	0.00	356.72	3304.20	1652.10	5092.60	2550.09	7.03	-0.803	0.000	0.146
90.00	-18.40	-5.16	0.00	-343.65	0.00	343.65	3276.86	1638.43	4994.13	2500.78	7.46	-0.834	0.000	0.143
91.92	-17.80	-5.11	0.00	-333.73	0.00	333.73	3255.72	1627.86	4918.94	2463.13	7.80	-0.858	0.000	0.099
92.25	-17.70	-5.11	0.00	-332.05	0.00	332.05	2609.22	1304.61	4017.17	2011.57	7.86	-0.861	0.000	0.106
95.00	-17.25	-5.04	0.00	-318.00	0.00	318.00	2587.46	1293.73	3934.74	1970.29	8.36	-0.885	0.000	0.112
100.00	-16.44	-4.92	0.00	-292.80	0.00	292.80	2547.26	1273.63	3786.04	1895.83	9.31	-0.930	0.000	0.107
105.00	-15.65	-4.79	0.00	-268.21	0.00	268.21	2506.24	1253.12	3638.92	1822.16	10.31	-0.975	0.000	0.101
105.58	-15.56	-4.78	0.00	-265.43	0.00	265.43	2501.42	1250.71	3621.96	1813.67	10.43	-0.980	0.000	0.100
105.58	-15.56	-4.78	0.00	-265.43	0.00	265.43	2501.42	1250.71	3621.96	1813.67	10.43	-0.980	0.000	0.100
110.00	-14.87	-4.67	0.00	-244.31	0.00	244.31	2464.40	1232.20	3493.46	1749.33	11.36	-1.018	0.000	0.146
115.00	-14.10	-4.56	0.00	-220.94	0.00	220.94	2421.75	1210.87	3349.75	1677.36	12.46	-1.082	0.000	0.138
120.00	-13.35	-4.44	0.00	-198.15	0.00	198.15	2378.28	1189.14	3207.87	1606.32	13.62	-1.145	0.000	0.129
125.00	-12.62	-4.32	0.00	-175.96	0.00	175.96	2333.99	1167.00	3067.90	1536.23	14.85	-1.204	0.000	0.120
130.00	-11.90	-4.20	0.00	-154.35	0.00	154.35	2288.89	1144.45	2929.94	1467.15	16.15	-1.261	0.000	0.110
132.50	-11.54	-4.14	0.00	-143.84	0.00	143.84	2266.03	1133.02	2861.73	1432.99	16.81	-1.289	0.000	0.105
135.00	-11.01	-4.08	0.00	-133.48	0.00	133.48	2239.33	1119.66	2789.52	1396.83	17.50	-1.316	0.000	0.100
136.50	-10.69	-4.04	0.00	-127.36	0.00	127.36	1414.34	707.17	1783.76	893.21	17.91	-1.332	0.000	0.150
140.00	-10.30	-3.97	0.00	-113.20	0.00	113.20	1397.90	698.95	1729.39	865.98	18.90	-1.367	0.000	0.138
145.00	-9.77	-3.85	0.00	-93.36	0.00	93.36	1373.73	686.86	1652.26	827.36	20.37	-1.428	0.000	0.120
148.00	-9.24	-3.60	0.00	-81.80	0.00	81.80	1358.83	679.41	1606.31	804.35	21.28	-1.462	0.000	0.109
150.00	-9.04	-3.56	0.00	-74.61	0.00	74.61	1348.73	674.37	1575.83	789.09	21.89	-1.483	0.000	0.101
155.00	-8.55	-3.45	0.00	-56.82	0.00	56.82	1322.92	661.46	1500.20	751.22	23.47	-1.530	0.000	0.082
158.00	-6.66	-2.58	0.00	-46.49	0.00	46.49	1307.05	653.52	1455.24	728.70	24.44	-1.554	0.000	0.069

## Calculated Forces

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 52

160.00	-6.49	-2.54	0.00	-41.32	0.00	41.32	1296.30	648.15	1425.45	713.78	25.10	-1.568	0.000	0.063
165.00	-6.07	-2.43	0.00	-28.62	0.00	28.62	1268.86	634.43	1351.65	676.83	26.75	-1.598	0.000	0.047
168.00	-4.84	-1.67	0.00	-21.33	0.00	21.33	1252.00	626.00	1307.87	654.91	27.76	-1.612	0.000	0.036
168.50	-3.31	-1.32	0.00	-20.49	0.00	20.49	1249.16	624.58	1300.61	651.27	27.93	-1.614	0.000	0.034
170.00	-3.19	-1.29	0.00	-18.51	0.00	18.51	1240.60	620.30	1278.90	640.40	28.44	-1.619	0.000	0.031
175.00	-2.81	-1.18	0.00	-12.07	0.00	12.07	1211.52	605.76	1207.28	604.54	30.14	-1.635	0.000	0.022
178.00	-2.58	-1.12	0.00	-8.52	0.00	8.52	1193.69	596.84	1164.89	583.31	31.17	-1.642	0.000	0.017
178.00	-2.58	-1.12	0.00	-8.52	0.00	8.52	975.84	487.92	954.81	478.11	31.17	-1.642	0.000	0.020
180.00	-2.45	-1.08	0.00	-6.27	0.00	6.27	975.84	487.92	954.81	478.11	31.86	-1.646	0.000	0.016
184.00	-0.69	-0.65	0.00	-1.94	0.00	1.94	975.84	487.92	954.81	478.11	33.24	-1.650	0.000	0.005
185.00	-0.63	-0.63	0.00	-1.29	0.00	1.29	975.84	487.92	954.81	478.11	33.59	-1.651	0.000	0.003
187.00	-0.05	-0.02	0.00	-0.02	0.00	0.02	975.84	487.92	954.81	478.11	34.28	-1.651	0.000	0.000
188.00	0.00	-0.02	0.00	0.00	0.00	0.00	975.84	487.92	954.81	478.11	34.63	-1.651	0.000	0.000



## Final Analysis Summary

<b>Structure:</b> CT46124-A-SBA	<b>Code:</b> EIA/TIA-222-G	7/31/2017
<b>Site Name:</b> Enfield-Moody Rd.	<b>Exposure:</b> C	
<b>Height:</b> 188.00 (ft)	<b>Crest Height:</b> 0.00	
<b>Base Elev:</b> 0.000 (ft)	<b>Site Class:</b> D - Stiff Soil	
<b>Gh:</b> 1.1	<b>Topography:</b> 1	<b>Struct Class:</b> II



Page: 53

### Reactions

Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)
1.2D + 1.6W 94 mph Wind	28.0	0.00	49.00	0.00	0.00	3587.49
0.9D + 1.6W 94 mph Wind	28.0	0.00	36.74	0.00	0.00	3541.49
1.2D + 1.0Di + 1.0Wi 50 mph Wind	9.4	0.00	84.33	0.00	0.00	1239.68
1.2D + 1.0E	1.6	0.00	49.04	0.00	0.00	205.20
0.9D + 1.0E	1.6	0.00	36.78	0.00	0.00	202.39
1.0D + 1.0W 60 mph Wind	7.1	0.00	40.86	0.00	0.00	906.84

### Max Stresses

Load Case	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Elev (ft)	Stress Ratio
1.2D + 1.6W 94 mph Wind	-37.33	-25.53	0.00	-2642.7	0.00	-2642.7	4621.33	2310.6	8623.42	4318.12	35.00	0.620
0.9D + 1.6W 94 mph Wind	-27.87	-25.32	0.00	-2600.4	0.00	-2600.4	4621.33	2310.6	8623.42	4318.12	35.00	0.608
1.2D + 1.0Di + 1.0Wi 50 mph Wind	-67.79	-8.74	0.00	-919.61	0.00	-919.61	4621.33	2310.6	8623.42	4318.12	35.00	0.228
1.2D + 1.0E	-12.93	-1.02	0.00	-40.43	0.00	-40.43	1414.34	707.17	1783.76	893.21	136.50	0.054
0.9D + 1.0E	-9.70	-1.00	0.00	-39.72	0.00	-39.72	1414.34	707.17	1783.76	893.21	136.50	0.051
1.0D + 1.0W 60 mph Wind	-31.52	-6.47	0.00	-666.95	0.00	-666.95	4621.33	2310.6	8623.42	4318.12	35.00	0.161

### Additional Steel Summary

Elev From (ft)	Elev To (ft)	Member	Intermediate Connectors			Lower Termination				Upper Termination				Max Member			
			VQ/I (lb/in)	Vu (kips)	phi Vn (kips)	MQ/I (kips)	phi Vn (kips)	Num Reqd	Num Actual	MQ/I (kips)	phi Vn (kips)	Num Reqd	Num Actual	Pu (kips)	phi Pn (kips)	phi Tn (kips)	Ratio
0.0	32.8	(3) PLT-6"X1-1/4"(1.25" Hole	-196.3	-4.12	37.1	270.5	37.1	8	0	247.7	37.1	7	11	270.53	404.8	356.25	0.759
48.9	76.8	(3) PLT-5.5"x1 1/4"(1.25"hol	-226.3	-4.75	37.1	221.1	37.1	6	10	205.4	37.1	6	10	236.07	371.1	318.75	0.741
91.9	105.6	(3) PLT-4.5"x 1-1/4"(1.25"ho	-234.5	-5.63	37.1	162.2	37.1	5	7	156.2	37.1	5	7	172.56	296.2	243.75	0.708

**SPECIAL CONSTRUCTION NOTE:**

SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:  
 \* COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).  
 \* COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).  
 \* GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.  
 \* SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.



**NOTE:**

OWNER AND TENANT MAY, FROM TIME TO TIME AT TENANT'S OPTION, REPLACE THIS EXHIBIT WITH AN EXHIBIT SETTING FORTH THE LEGAL DESCRIPTION OF THE SITE, OR WITH ENGINEERED OR AS-BUILT DRAWING DEPICTING THE SITE OR ILLUSTRATING STRUCTURAL MODIFICATIONS OR CONSTRUCTION PLANS OF THE SITE. ANY VISUAL OR TEXTUAL REPRESENTATION OF THE EQUIPMENT LOCATED WITHIN THE SITE CONTAINED IN THESE OTHER DOCUMENTS IS ILLUSTRATIVE ONLY, AND DOES NOT LIMIT THE RIGHTS OF SPRINT AS PROVIDED FOR IN THE AGREEMENT. THE LOCATIONS OF ANY ACCESS AND UTILITY EASEMENTS ARE ILLUSTRATIVE ONLY. ACTUAL LOCATIONS MAY BE DETERMINED BY TENANT AND/OR THE SERVICING UTILITY COMPANY IN COMPLIANCE WITH LOCAL LAWS AND REGULATIONS.

**NOTE:**

REV1 CDs COMPLETED BY AEG ENGINEERING GROUP. HDG REVISED TO BRING CT CODES UP TO DATE AND WERE NOT ENGAGED TO RE-WALK SITE NOR CONFIRM EXISTING CONDITIONS

**PROJECT:** 2.5 EQUIPMENT DEPLOYMENT  
**SITE NAME:** CLARYVILLE NEXTEL  
**SITE CASCADE:** CT33XC257  
**MARKET:** NORTHERN CONNECTICUT  
**SBA SITE ID:** CT46124, ENFIELD-MOODY ROAD  
**SITE ADDRESS:** 188 MOODY ROAD  
 ENFIELD, CT 06082  
**SITE TYPE:** 188' MONOPOLE



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495  
 TEL: (800) 357-7641




SBA COMMUNICATIONS CORP.  
 134 FLANDERS ROAD, SUITE 125  
 WESTBOROUGH, MA 01581 TEL: (508) 251-0720

**PLANS PREPARED BY:**



1600 OSGOOD STREET  
 BUILDING 20 NORTH, SUITE 3090  
 N. ANDOVER, MA 01845 TEL: (978) 557-5533  
 FAX: (978) 336-5586



**SITE INFORMATION**

**PROPERTY OWNER:**  
 TROIANO REALTY CORP.  
 777 ENFIELD STREET  
 ENFIELD, CT 06082

**TOWER OWNER:**  
 SBA 2012 TC ASSETS, LLC  
 5900 BROKEN SOUND PARKWAY, NW  
 BOCA RATON, FL 33487-2797  
 RSM: STEPHAN ROTH  
 PHONE: 561-226-9523  
 SROTH@SBASITES.COM

**LATITUDE (NAD83):**  
**GOOGLE EARTH 2-C CONFIRMATION**  
 42° 00' 07.23" N  
 42.002011°

**LONGITUDE (NAD83):**  
**GOOGLE EARTH 2-C CONFIRMATION**  
 -72° 31' 18.25" W  
 -72.521692°

**COUNTY:**  
 HARTFORD

**ZONING JURISDICTION:**  
 TOWN OF ENFIELD

**ZONING DISTRICT:**  
 I-1 - INDUSTRIAL 1

**POWER COMPANY:**  
 CT LIGHT & POWER

**AAV PROVIDER:**  
 AT&T

**SPRINT CONSTRUCTION MANAGER:**  
 MICHAEL DELIA  
 PHONE: 781-316-6348  
 michael.delia@sprint.com

**EQUIPMENT SUPPLIER:**  
 ALCATEL-LUCENT  
 600 MOUNTAIN AVENUE  
 MURRAY HILL, NJ 07974

**AREA MAP**



LOCATION MAP GOOGLE EARTH 2-C CONFIRMATION

**PROJECT DESCRIPTION**

SPRINT EQUIPMENT MODIFICATIONS REQUIRED TO SUPPORT MODERNIZATION OF AN EXISTING WIRELESS COMMUNICATIONS FACILITY AND UTILIZATION OF FCC BROADBAND SPECTRUM LICENSE FOR 2.5GHZ FREQUENCY, INCLUDING INSTALLATION OF:

GROUND-LEVEL RAN EQUIPMENT, CONSISTING OF:  
 \* RETROFIT EXISTING MMBTS CABINET WITH (1) RECTIFIER SHELF, (3) RECTIFIERS, 2.5 RADIO ACCESS NETWORK (RAN) EQUIPMENT & BBU KIT  
 \* INSTALL (1) ADDITIONAL BATTERY STRING INSIDE EXISTING BATTERY BACKUP (BBU) CABINET

TOWER-TOP EQUIPMENT, INCLUDING INSTALLATION OF:  
 \* (3) PANEL ANTENNAS  
 \* (3) REMOTE RADIO HEADS (RRH)  
 \* (1) HYBRID CABLE (AND ASSOCIATED FIBER, DC POWER, COAXIAL CABLE JUMPERS AND ANTENNA REMOTE ELECTRICAL-TILT (RET) CABLE

**SPECIAL ZONING NOTE:**  
 BASED ON INFORMATION PROVIDED BY SPRINT REGULATORY COMPLIANCE PROFESSIONALS AND LEGAL COUNSEL, THIS TELECOMMUNICATIONS EQUIPMENT DEPLOYMENT IS CONSIDERED AND ELIGIBLE FACILITY UNDER THE TAX RELIEF ACT OF 2012, 47 USC 1455(A), AND IS SUBJECT TO AN EXPEDITED ELIGIBLE FACILITIES REQUEST/REVIEW AND ZONING PRE-EMPTION FOR LOCAL DISCRETIONARY PERMITS (VARIANCE, SPECIAL PERMIT, SITE PLAN REVIEW, ADMINISTRATIVE REVIEW).

**GENERAL NOTES**

- THIS IS AN UNMANNED TELECOMMUNICATION FACILITY AND NOT FOR HUMAN HABITATION:  
 - ADA COMPLIANCE NOT REQUIRED.  
 - POTABLE WATER OR SANITARY SERVICE IS NOT REQUIRED.  
 - NO OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES REQUIRED.
- CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON JOB SITE. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. FAILURE TO NOTIFY THE ARCHITECT/ENGINEER PLACE THE RESPONSIBILITY ON THE CONTRACTOR TO CORRECT THE DISCREPANCIES AT THE CONTRACTOR'S EXPENSE.
- NEW CONSTRUCTION WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES.  
 BUILDING CODE: IBC 2012 WITH 2016 CT STATE BUILDING CODE AMENDMENTS  
 ELECTRICAL CODE: 2014 NATIONAL ELECTRICAL CODE  
 STRUCTURAL CODE: TIA/EIA-222-G STRUCTURAL STANDARDS FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS.



**DRAWING INDEX**

SHEET NO:	SHEET TITLE	REV	CHK	BY
T-1	TITLE SHEET	2	BB	AN
SP-1	OUTLINE SPECIFICATIONS	2	BB	AN
SP-2	OUTLINE SPECIFICATIONS	2	BB	AN
SP-3	OUTLINE SPECIFICATIONS	2	BB	AN
A-1	COMPOUND PLAN	2	BB	AN
A-2	ELEVATION AND ANTENNA PLANS	2	BB	AN
A-3	RF DATA SHEET	2	BB	AN
A-4	RAN WIRING DIAGRAM	2	BB	AN
A-5	EQUIPMENT DETAILS	2	BB	AN
A-6	EQUIPMENT DETAILS	2	BB	AN
S-1	STRUCTURAL DETAILS	2	BB	AN
E-1	ONE LINE DIAGRAM	2	BB	AN
E-2	GROUNDING DETAILS AND NOTES	2	BB	AN

**APPROVALS**

THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.

SPRINT: \_\_\_\_\_ DATE: \_\_\_\_\_  
 CONSTRUCTION MANAGER: \_\_\_\_\_ DATE: \_\_\_\_\_  
 LEASING/SITE ACQUISITION: \_\_\_\_\_ DATE: \_\_\_\_\_  
 RF ENGINEER: \_\_\_\_\_ DATE: \_\_\_\_\_  
 LANDLORD/TOWER OWNER: \_\_\_\_\_ DATE: \_\_\_\_\_

CHECKED BY: BB

APPROVED BY: DJC

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
 CT33XC257  
 SITE NAME:  
 CLARYVILLE  
 NEXTEL  
 SITE ADDRESS:  
 188 MOODY ROAD  
 ENFIELD, CT 06082

SHEET TITLE

TITLE SHEET

SHEET NUMBER

T-1





CONTINUED FROM SP-2:

**MATERIALS:**

- A. MANUFACTURERS: BENJAMIN MOORE, ICI DEVOE COATINGS, PPG, SHERWIN WILLIAMS OR APPROVED EQUAL. PROVIDE PREMIUM GRADE, PROFESSIONAL-QUALITY PRODUCTS FOR COATING SYSTEMS.

**PAINT SCHEDULE:**

- A. EXTERIOR ANTENNAE AND ANTENNA MOUNTING HARDWARE: ONE COAT OF PRIMER AND TWO FINISH COATS. PAINT FOR ANTENNAE SHALL BE NON-METALLIC BASED AND CONTAIN NO METALLIC PARTICLES. PROVIDE COLORS AND PATTERNS AS REQUIRED TO MASK APPEARANCE OF ANTENNAE ON ADJACENT BUILDING SURFACES AND AS ACCEPTABLE TO THE OWNER. REFER TO ANTENNA MANUFACTURER'S INSTRUCTIONS WHENEVER POSSIBLE.
- B. ROOF TOP CONSTRUCTION: TOUCH UP - PREPARE SURFACES TO BE REPAIRED. FOLLOW INDUSTRY STANDARDS AND REQUIREMENTS OF OWNER TO MATCH EXISTING COATING AND FINISH.

**PAINTING APPLICATION:**

- INSPECT SURFACES, REPORT UNSATISFACTORY CONDITIONS IN WRITING; BEGINNING WORK MEANS ACCEPTANCE OF SUBSTRATE.
- COMPLY WITH MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS FOR PREPARATION, PRIMING AND COATING WORK. COORDINATE WITH WORK OF OTHER SECTIONS.
- MATCH APPROVED MOCK-UPS FOR COLOR, TEXTURE, AND PATTERN. RE-COAT OR REMOVE AND REPLACE WORK WHICH DOES NOT MATCH OR SHOWS LOSS OF ADHESION.
- CLEAN UP, TOUCH UP AND PROTECT WORK.

**TOUCHUP PAINTING:**

- GALVANIZING DAMAGE AND ALL BOLTS AND NUTS SHALL BE TOUCHED UP AFTER TOWER ERECTION WITH "GALVANOX," "DRY GALV," OR "ZINC-IT."
- FIELD TOUCHUP PAINT SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.
- ALL METAL COMPONENTS SHALL BE HANDLED WITH CARE TO PREVENT DAMAGE TO THE COMPONENTS, THEIR PRESERVATIVE TREATMENT, OR THEIR PROTECTIVE COATINGS.

**SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO HEADS AND CABLE INSTALLATION**

**SUMMARY:**

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRH'S, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

**ANTENNAS AND RRH'S:**

THE NUMBER AND TYPE OF ANTENNAS AND RRH'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

**HYBRID CABLE:**

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

**JUMPERS AND CONNECTORS:**

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRH'S AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRH'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE. DO NOT USE SUPERFLEX OUTDOORS. JUMPERS SHALL BE FACTORY FABRICATED IN APPROPRIATE LENGTHS WITH A MAXIMUM OF 4 FEET EXCESS PER JUMPER AND HAVE CONNECTORS AT EACH END, MANUFACTURED BY SUPPLIER. IF JUMPERS ARE FIELD FABRICATED, FOLLOW MANUFACTURER'S REQUIREMENTS FOR INSTALLATION OF CONNECTORS

**REMOTE ELECTRICAL TILT (RET) CABLES:**

**MISCELLANEOUS:**

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

**ANTENNA INSTALLATION:**

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

- A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.
- B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

**HYBRID CABLES INSTALLATION:**

- A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.
- C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.
  - FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE PERMANENTLY FASTENED TO THE COAX LADDER AT 4'-0" OC USING NON-MAGNETIC STAINLESS STEEL CLIPS.
  - FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBTS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
    - FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH @ 18" OC. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
    - DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
  - FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
  - CABLE INSTALLATION:
    - INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
    - CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS.
    - HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURERS RECOMMENDED MAXIMUM BEND RADIUS.

- GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
- HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 REV 4.
- HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1

**WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:**

- A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.
- B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.
  - COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
  - SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
  - 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
  - OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

**SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBTS) AND RELATED EQUIPMENT**

**SUMMARY:**

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

**DC CIRCUIT BREAKER LABELING**

- A. LABEL CIRCUIT BREAKERS ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1.

**SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE TRANSCIEVER STATIONS (MMBTS) AND RELATED EQUIPMENT**

**SUMMARY:**

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

**SUPPORTING DEVICES:**

- A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
  - ALLIED TUBE AND CONDUIT
  - B-LINE SYSTEM
  - UNISTRUT DIVERSIFIED PRODUCTS
  - THOMAS & BETTS
- B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:
  - EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
  - POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
  - FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
  - TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
  - CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
  - MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
  - EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
  - DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
  - IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.

**SUPPORTING DEVICES:**

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
- D. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
- E. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

**ELECTRICAL IDENTIFICATION:**

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

**SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT**

**CONDUIT:**

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR ENCASED RUNS IN CONCRETE. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6- FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRE BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

**HUBS AND BOXES:**

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
  - CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL.
  - CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROTEXC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKETED COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

**SUPPLEMENTAL GROUNDING SYSTEM**

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM AS INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS AS INDICATED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

**EXISTING STRUCTURE:**

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

**CONDUIT AND CONDUCTOR INSTALLATION:**

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.

1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495  
TEL: (800) 357-7641

SBA COMMUNICATIONS CORP.  
134 FLANDERS ROAD, SUITE 125  
WESTBOROUGH, MA 01581 TEL: (508) 251-0720

PLANS PREPARED BY:

1600 OSGOOD STREET  
BUILDING 20 NORTH, SUITE 3090  
N. ANDOVER, MA 01845 TEL: (978) 557-5533  
FAX: (978) 336-5586

Blank space for stamp or signature.

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
CT33XC257

SITE NAME:  
CLARYVILLE  
NEXTTEL



SITE ADDRESS:  
188 MOODY ROAD  
ENFIELD, CT 06082

SHEET TITLE


OUTLINE  
SPECIFICATIONS

SHEET NUMBER

SP-3




SOURCE: SPRINT SITE VISIT 12.27.13



**COMPOUND PLAN**  
SCALE: 3/16"=1'-0"

1  
A-1



**RAN EQUIPMENT PHOTO DETAIL**  
SCALE: N.T.S.

2  
A-1

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
CT33XC257  
SITE NAME:  
CLARYVILLE  
NEXTEL  
SITE ADDRESS:  
188 MOODY ROAD  
ENFIELD, CT 06082

SHEET TITLE  
COMPOUND PLAN

SHEET NUMBER  
A-1

**SPECIAL CONSTRUCTION NOTE:**  
 SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:  
 • COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).  
 • COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).  
 • GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.  
 • SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

**NOTE:**  
 SPRINT RAD CENTER SHOWN IN RED TEXT BASED ON SBA-PROVIDED COLLOCATION APPLICATION, EQUIPMENT DATABASE, AND STRUCTURAL ANALYSIS. THE SBA-PROVIDED ANTENNA RAD CENTER SHALL SUPERSEDE ANY CONFLICTING INFORMATION DERIVED FROM THE SPRINT NV 2.5 RFDS.

**NOTE:**  
 EXISTING AZIMUTHS FROM SPRINT SITE AUDIT DATED 09/04/13



1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495  
 TEL: (800) 357-7641






SBA COMMUNICATIONS CORP.  
 134 FLANDERS ROAD, SUITE 125  
 WESTBOROUGH, MA 01581 TEL: (508) 251-0720


PLANS PREPARED BY:



1600 OSGOOD STREET  
 BUILDING 20 NORTH, SUITE 3090  
 N. ANDOVER, MA 01845 TEL: (978) 557-5553  
 FAX: (978) 336-5586




**EXISTING PARTIAL ELEVATION PHOTO DETAIL**  
 SCALE: N.T.S.




**ANTENNA STATUS LEGEND:**

EMPTY - EMPTY PIPE  
 (E) - EXISTING  
 (P) - INSTALL  
 NV - SPRINT ANTENNA  
 2.5 - SPRINT ANTENNA

**SPECIAL INSTALLATION NOTE:**  
 JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY



**NOTES:**  
 GROUND EQUIPMENT NOT SHOWN FOR CLARITY



CHECKED BY: BB

APPROVED BY: DJC

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
 CT33XC257  
 SITE NAME:  
 CLARYVILLE  
 NEXTEL  
 SITE ADDRESS:  
 188 MOODY ROAD  
 ENFIELD, CT 06082

SHEET TITLE  
 ELEVATION AND  
 ANTENNA PLANS

SHEET NUMBER  
 A-2



### RFDS Sheet

#### General Site Information

Site ID	CT33XC257	Equipment Vendor	ALU
Market	Northern Connecticut	Latitude	42.00201
Region	East	Longitude	-72.5222193
MLA	SBA	LL SITE ID	CT2000
Structure Type	OTHER		
BTS Type	STANDARD		
Solution ID	MP_4G_LTE_05533	Siterra SR Equipment type	Outdoor Macro
		Equipment Vendor	ALU
		Incremental Power Draw needed by added Equipment	0

#### Base Equipment

BBU Kit	ALU BBU Kit	Top Hat	None
BBU Kit Qty	1	Top Hat Qty	NA
		Top Hat Dimenstions	NA
		Top Hat Weight (lbs)	NA
Growth Cabinet	NA		
Growth Cabinet Qty			
Growth Cabinet Dimensions			
Growth Cabinet Weight			

#### RF Path Information

RRH	TD-RRH8x20-25	
RRH Qty	3	
RRH Dimensions	26.1in x 18.6 x 6.7 in	
RRH Weight. lbs.	70	
RRH Mount Weight. Lbs.	TBD	
Power and Fiber Cable	ALU Fiber only	(** A&E SEE DETAIL 1/A-5)
Cable Qty	1	
Weight per foot. Lbs.	0.12	
Diameter. Inches.	1.25	
Length Ft.	201.6 (** A&E 200)	(calculated as antenna height plus 20%)
Coax Jumper		
Coax Jumper Qty	27	
Coax Jumper Length. Feet.	8 (** A&E 15)	
Coax Jumper Weight	TBD	
Coax Jumper Diameter. Inches	0.5	
AISG Cable	Commscope ATCB-B01-006	
AISG Cable Qty	3	
AISG Diameter. Inches.	0.315	
AISG Cable length.	8 (** A&E 15)	
Weight of entire AISG cable. Lbs.	1.3	

#### Antenna Sector Information

	Sector 1	Sector 2	Sector 3
Antenna make/model	RFS APXVTM14-C-I20	RFS APXVTM14-C-I20	RFS APXVTM14-C-I20
Antenna qty	1	1	1
Antenna Dimensions. Inches	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3
Antenna Weight. Lbs	56	56	56
Antenna Mounting Kit Weight. Lbs.	~11 lb estimate. TBD.	~11 lb estimate. TBD.	~11 lb estimate. TBD.
CL Height	168 (*SBA 168.0)	168 (*SBA 168.0)	#N/A(*SBA 168.0)
Antenna Azimuth	0	130	240
Antenna Mechanical Downtilt	0	0	0
Antenna etilt	-2	-2	-2

Sprint RFDS Sheet

2/12/2014

Confidential

Comments in Red Text provided by A&E Vendor.

IMPORTANT CONSTRUCTION NOTE: General Contractor/Tower Crew shall verify that the latest RF Data Sheet is used for equipment installation.

\* Note: Antenna Rad Center based on SBA-Provided Collocation Application, Equipment Database, and Structural Analysis. The SBA-Provided Antenna Rad Center shall supersede any conflicting information derived from the Sprint NV 2.5 or ALU Database.

\*\* Note: Sprint/ALU CM shall confirm Tower Top Coax Jumper Lngth and Power and Fiber Cable Length before preparing BOM. Recommended Power and Fiber Cable Length based on NV 2.5 Equipment Audit plus 20 Feet for (2) 10-foot coils at each end of the fiber trunk.

#### SPRINT CONSTRUCTION STANDARDS:

GENERAL CONTRACTOR SHALL ADHERE TO THE FOLLOWING SPRINT CONSTRUCTION STANDARDS.

- CONSTRUCTION STANDARDS: INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES - (CURRENT VERSION), INCLUDING EXHIBITS A-M.
- CONSTRUCTION SPECIFICATIONS: CONSTRUCTION STANDARDS EXHIBIT A - STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES (CURRENT VERSION).
- GROUNDING STANDARDS: EXTERIOR GROUNDING SYSTEM DESIGN. GROUNDING STANDARDS (SUPPLEMENT): ANTI-THEFT UPDATE TO SPRINT GROUNDING 082412 AND SPRINT ENGINEERING LETTER EL-0504 DATED 04.20.12.
- WEATHER PROOFING STANDARDS: EXCERPT FROM CONSTRUCTION STANDARDS EXHIBIT A, SECTION 3.6 WEATHERPROOFING CONNECTORS AND GROUND KITS.
- COLOR CODING: SPRINT NEXTEL ANT AND LINE COLOR CODING PER SPRINT TS-Q200 CURRENT VERSION.
- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND CL HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT IN RFDS, HALT ANTENNA WORK FOR WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING SPRINT-PROVIDED CONTACT INFORMATION FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHz ANTENNA AT SAME CL AS 1.9GHz ANTENNA AND EMAIL CORRECT CL HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILD DRAWING WITH CORRECT CL HEIGHT. ALSO EMAIL CORRECT 1900MHz AND 800MHz ANTENNA CL HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHz, 1.9GHz, AND 2.5GHz. TEST INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST INSURE THAT NO OBJECT IS LOCATED IN FRONT OF ANTENNA. THIS MEANS NO OBJECT IS TO BE LOCATED 45 DEGREES LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHz ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREES. DOWNTILT AND ROLL(LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILTS SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL. [HTTP://WWW.3ZTELECOM.COM/ANTENNA-ALIGNMENT-TOOL/](http://www.3ztelecom.com/antenna-alignment-tool/).



1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495  
TEL: (800) 357-7641




SBA COMMUNICATIONS CORP.  
134 FLANDERS ROAD, SUITE 125  
WESTBOROUGH, MA 01581 TEL: (508) 251-0720

PLANS PREPARED BY:



1600 OSGOOD STREET  
BUILDING 20 NORTH, SUITE 3090  
N. ANDOVER, MA 01845 TEL: (978) 557-5533  
FAX: (978) 336-5586



CHECKED BY: BB

APPROVED BY: DJC

#### SUBMITTALS

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
CT33XC257  
SITE NAME:  
CLARYVILLE  
NEXTEL  
SITE ADDRESS:  
188 MOODY ROAD  
ENFIELD, CT 06082


SHEET TITLE

RF DATA SHEET


SHEET NUMBER

A-3






**ALU 2.5 ALU SCENARIO 1**  
SCALE: N.T.S.




**RAN WIRING DIAGRAM: ALU EQUIPMENT**  
SCALE: N.T.S.

**NOTE:**  
GENERAL CONTRACTOR/TOWER CREW SHALL VERIFY THAT THE LATEST RF DATA SHEET IS USED FOR EQUIPMENT INSTALLATION.



**RFS 2.5 ALU SCENARIO 1**  
SCALE: N.T.S.

**DC POWER INSTALLATION NOTE (FIBER-ONLY SCENARIO):**  
USE SPARE DC CABLES COILED UP AT TOWER TOP NV ARRAY TO POWER UP 2.5 RRH. INSIDE EXISTING FIBER DISTRIBUTION BOX, TIE SPARE DC CONNECTORS INTO EXISTING DC BREAKER PANEL PER APPROVED DC WIRING CONNECTIVITY OPTION (BASED ON NV HYBRIFLEX CABLE LENGTH). CONSULT WITH SPRINT CM TO DETERMINE APPROPRIATE DC CONNECTIVITY OPTION, PLUMBING DIAGRAM AND DC BREAKER SIZE.



CHECKED BY: BB

APPROVED BY: DJC

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
CT33XC257  
SITE NAME:  
CLARYVILLE  
NEXTEL  
SITE ADDRESS:  
188 MOODY ROAD  
ENFIELD, CT 06082

SHEET TITLE

RAN WIRING  
DIAGRAM

SHEET NUMBER

A-4

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE			
CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
MANUF: RFS			
FIBER ONLY	VARIABLE	USE NV HYBRIFLEX	5/8"
HYBRIFLEX	<200'	8 AWG	1-1/4"
HYBRIFLEX	225-300'	6 AWG	1-1/4"
HYBRIFLEX	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE


Power Type	Hybrid cable	Length
Fiber Only (Existing DC Power)	MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
8 AWG Power	MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
6 AWG Power	MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE


Power Type	Hybrid Jumper cable	Length
Fiber Only	MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
8 AWG Power	MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
6 AWG Power	MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
4 AWG Power	MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft

\* NOTE: SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.

2.5 FIBER ONLY CABLE X-SECTION AND DATA



MANUF: ALCATEL-LUCENT  
MODEL: TD-RRH8x20-25  
LENGTH: 26.1  
WIDTH: 18.6  
DEPTH: 6.7  
WEIGHT: 70 LBS  
AREA: 3.5 SF




2.5 RRH'S

SCALE: N.T.S.



MANUF: RFS  
MODEL: APXVTM14-C-120  
LENGTH: 56.3  
WIDTH: 12.6  
DEPTH: 6.3  
WEIGHT: 70 LBS  
AREA: 4.9 SF



2.5 ANTENNA SPECIFICATIONS

SCALE: N.T.S.




1 INTERNATIONAL BLVD, SUITE 800  
MAHWAH, NJ 07495  
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.  
134 FLANDERS ROAD, SUITE 125  
WESTBOROUGH, MA 01581 TEL: (508) 251-0720



1600 OSGOOD STREET  
BUILDING 20 NORTH, SUITE 3090  
N. ANDOVER, MA 01845 TEL: (978) 557-5553  
FAX: (978) 336-5586



CHECKED BY: BB


APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL


SITE NUMBER:  
CT33XC257  
SITE NAME:  
CLARYVILLE  
NEXTTEL  
SITE ADDRESS:  
188 MOODY ROAD  
ENFIELD, CT 06082

SHEET TITLE  
EQUIPMENT DETAILS

SHEET NUMBER  
A-5



*Derek J. Creaser*  
PROFESSIONAL ENGINEER



FRONT VIEW

**EXISTING MMBTS OUTDOOR CABINET WITH 2.5 EQUIPMENT**

SCALE: N.T.S.

1  
A-6

INSTALL (1) BATTERY STRING IN  
EXISTING BATTERY CABINET IN  
AVAILABLE EMPTY BAY



FRONT VIEW

**EXISTING 2.5 POWER BBU CABINET**

SCALE: N.T.S.

2  
A-6

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL



SITE NUMBER:  
CT33XC257  
SITE NAME:  
CLARYVILLE  
NEXTEL  
SITE ADDRESS:  
188 MOODY ROAD  
ENFIELD, CT 06082

SHEET TITLE

EQUIPMENT  
DETAILS

SHEET NUMBER

A-6



- INSTALLATION NOTES:**
1. CONTRACTOR TO ENSURE THAT RRH MOUNTING DOES NOT INTERFERE WITH CLIMBING LADDER, CABLE CLIMB, OR COAX PORTS. MONOPOLE: COLLAR-MOUNT RRH CLUSTER SHALL PROVIDE OPENING BETWEEN ADJACENT RRH AT LEAST 30" WIDE CENTERED ON THE EXISTING SAFETY-CLIMB AND 30" DEEP FROM THE FACE OF THE POLE. SELF-SUPPORT: RRH LEG-MOUNT OR FACE-MOUNT SHALL PROVIDE AN UNOBSTRUCTED VERTICAL CLIMBING PASSAGE AT LEAST 30" WIDE AND 30" DEEP CENTERED ON THE LEG WITH THE CLIMBING PEGS.
  2. CONTRACTOR TO VERIFY DIAMETER OF EXISTING MONOPOLE BEFORE ORDERING PARTS.
  3. CONTRACTOR TO VERIFY IN FIELD SIZE OF EXISTING MOUNTING PIPE TO BE 2 1/2" STD (2.88 O.D.) PIPE MAST (6'-0" LONG).
  4. VERIFY EXACT RRH AND ANTENNA MODEL & AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION.
  5. ROTATE EXISTING ANTENNA FRAME AS NEEDED TO ACCOMMODATE INSTALL ANTENNAS.
  6. RRH PLACEMENT FOR REFERENCE ONLY. CONTRACTOR SHALL PLACE RRH IN CORRECT ORDER MATCHING INSTALL ANTENNA PLACEMENT AND ENSURE THAT THERE IS ENOUGH CLEARANCE FOR RRHS TO BE PLACED ON THE INSIDE ON THE ANTENNA FRAME.
  7. INSTALL EQUIPMENT TO BE MOUNTED PER MANUFACTURERS SPECIFICATIONS.

- SPECIAL CONSTRUCTION NOTE:**  
 SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
- \* COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).
  - \* COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
  - \* GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
  - \* SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

**2.5 ANTENNA AND RRH MOUNTING DETAIL**  
 SCALE: N.T.S.

**2.5 ANTENNA AND RRH PHOTO DETAIL AND EQUIPMENT SCHEMATIC**  
 SCALE: N.T.S.

**Sprint**

1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495  
 TEL: (800) 357-7641

**SBA**

SBA COMMUNICATIONS CORP.  
 134 FLANDERS ROAD, SUITE 125  
 WESTBOROUGH, MA 01581 TEL: (508) 251-0720

PLANS PREPARED BY:

**Hudson Design Group**

1600 OSGOOD STREET  
 BUILDING 20 NORTH, SUITE 3090  
 N. ANDOVER, MA 01845 TEL: (978) 557-5553  
 FAX: (978) 336-5586

STATE OF CONNECTICUT  
 DEREK J. CREASER  
 LICENSED PROFESSIONAL ENGINEER

CHECKED BY: BB  
 APPROVED BY: DJC


**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
 CT33XC257  
 SITE NAME:  
 CLARYVILLE  
 NEXTEL  
 SITE ADDRESS:  
 188 MOODY ROAD  
 ENFIELD, CT 06082

SHEET TITLE  
 STRUCTURAL  
 DETAILS

SHEET NUMBER  
 S-1




**SPECIAL WORK NOTE:**

- G.C. TO FURNISH AND INSTALL ALL COMPONENTS TO UPGRADE EXISTING ELECTRICAL SERVICE, CONDUIT, CONDUCTOR, PPC AND MCB IN ACCORDANCE WITH SPRINT CONSTRUCTION STANDARDS NV 2.5 ADDENDUM "ENGINEERING NOTICE 2013-002 (POWER UPGRADES) REV.0" (OR CURRENT VERSION)
- G.C. TO FURNISH AND INSTALL UPGRADE THE EXISTING MMBTS BREAKER, CONDUCTOR, AND CONDUIT TO A MINIMUM NEC RATING FOR A 100-AMP, 240V CIRCUIT.
- FOR NEW OR REPAIRED GROUNDING EQUIPMENT, REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):  
 -ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-12 (OR CURRENT VERSION)  
 -SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION)
- USE SPARE DC CABLES COILED UP AT TOWER TOP NV ARRAY TO POWER UP 2.5 RRH. INSIDE EXISTING FIBER DISTRIBUTION BOX, TIE SPARE DC CONDUCTORS INTO EXISTING DC BREAKER PANEL PER APPROVED DC WIRING CONNECTIVITY OPTION (BASED ON NV HYBRIFLEX CABLE LENGTH). CONSULT WITH SPRINT CM TO DETERMINE APPROPRIATE DC CONNECTIVITY OPTION, PLUMBING DIAGRAM AND DC BREAKER SIZE.

**ELECTRICAL NOTES**

- ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
- THE ELECTRICAL CONTRACTOR SHALL COORDINATE ALL CONDUIT ROUTING WITH LOCAL UTILITY COMPANIES AND SPRINT CONSTRUCTION MANAGER.
- ALL CONDUITS ROUTED BELOW GRADE SHALL TRANSITION TO RIGID GALVANIZED ELBOWS WITH RIGID GALVANIZED STEEL CONDUIT ABOVE GRADE.
- ALL METAL CONDUITS SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
- GENERAL CONTRACTOR SHALL PROVIDE ALL DIRECT BURIED CONDUITS WITH PLASTIC WARNING TAPE IDENTIFYING CONTENTS. TAPE COLORS SHALL BE ORANGE FOR TELEPHONE AND RED FOR ELECTRIC.
- ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
- THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIALS DESCRIBED BY DRAWINGS AND SPECIFICATIONS INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM.
- GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND IS RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS.
- ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
- BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
- ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THIN INSULATION.
- RUN ELECTRICAL CONDUIT OR CABLE BETWEEN ELECTRICAL UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE PPC AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE. COORDINATE INSTALLATION WITH UTILITY COMPANY.
- RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
- FIBER OPTIC CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 770-OPTICAL FIBER CABLES AND RACEWAYS.
- COMMUNICATIONS CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 800-COMMUNICATIONS SYSTEMS.

**TYPICAL POWER & GROUNDING ONE-LINE** 1  
 SCALE: N.T.S. E-1



**EXISTING PPC BREAKER PANEL**  
 SCALE: N.T.S.




1 INTERNATIONAL BLVD, SUITE 800  
 MAHWAH, NJ 07495  
 TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.  
 134 FLANDERS ROAD, SUITE 125  
 WESTBOROUGH, MA 01581 TEL: (508) 251-0720

PLANS PREPARED BY:

1600 OSGOOD STREET  
 BUILDING 20 NORTH SUITE 3090  
 W. ANDOVER, MA 01845 TEL: (978) 537-5553 FAX: (978) 336-9386



CHECKED BY: BB

APPROVED BY: DJC

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL


SITE NUMBER:  
 CT33XC257

SITE NAME:  
 CLARYVILLE  
 NEXTEL

SITE ADDRESS:  
 188 MOODY ROAD  
 ENFIELD, CT 06082

SHEET TITLE  
 ONE LINE DIAGRAM

SHEET NUMBER  
 E-1



**SYMBOL LEGEND**


- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- CABLE GROUNDING KIT

UNLESS NOTED OTHERWISE, ALL BONDING CONDUCTORS ARE 2# SOLID TINNED BCW.

NOTE: HYBRIFLEX (FIBER & POWER) AND HYBRIFLEX (FIBER-ONLY) SHOWN. REFER TO RAN EQUIPMENT RFDS FOR SITE-SPECIFIC SCENARIO.


**2.5 RAN EQUIPMENT GROUNDING SCHEMATIC** 1  
SCALE: N.T.S. E-2

- PROTECTIVE GROUNDING SYSTEMS GENERAL NOTES:**
- GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250—GROUNDING AND BONDING.
  - GROUNDING SHALL BE IN ACCORDANCE WITH SPRINT SSEO DOCUMENTS 3.018.02.004 "BONDING, GROUNDING AND TRANSIENT PROTECTION FOR CELL SITES" AND 3.018.10.002 "SITE RESISTANCE TO EARTH TESTING".
  - PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
  - GROUND CONNECTIONS: CLEAN SURFACES THOROUGHLY BEFORE APPLYING GROUND LUGS OR CLAMPS. IF SURFACE IS COATED, REMOVE THE COATING, APPLY A NON-CORROSIVE APPROVED COMPOUND TO CLEAN SURFACE AND INSTALL LUGS OR CLAMPS. WHERE GALVANIZING IS REMOVED FROM METAL, IT SHALL BE PAINTED OR TOUCHED UP WITH "GALVAMOX" OR EQUAL.
  - ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
  - ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
  - ALL GROUND WIRES SHALL BE #2 SOLID TINNED BCW UNLESS NOTED OTHERWISE.
  - PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
  - GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
  - EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 SOLID TINNED BCW EQUIPMENT CABINETS WILL HAVE (2) CONNECTIONS.
  - GROUND HYBRIFLEX SHIELD AT TOP, BOTTOM AND AT TRANSITION TO HYBRIFLEX JUMPER CABLES AT EQUIPMENT CABINET ENTRANCE USING MANUFACTURER'S GUIDELINES. WHEN HYBRIFLEX CABLE EXCEEDS 200', GROUND AT INTERVALS NOT EXCEEDING 100'.
  - THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
  - EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL OTHERWISE. THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES, LONG BARREL LUGS OR DOUBLE CRIMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH AN ANTI-OXIDANT (THOMAS BETTS KOPR-SHIELD) BEFORE MAKING THE CRIMP CONNECTIONS THE CONTRACTOR SHALL FOLLOW MANUFACTURER'S RECOMMENDED TORQUES ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS.
  - AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING. CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
  - THE MASTER GROUND BAR (MGB) SHALL BE MADE OF BARE 1/4"x2" COPPER (FOR OUTDOOR APPLICATIONS IT SHALL BE TINNED COPPER) AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE SECURING THE MGB SHALL ELECTRICAL INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENED.
  - ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
  - ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH SPRINT CONSTRUCTION MANAGER.
  - FOR NEW OR REPAIRED GROUNDING EQUIPMENT. REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):  
-ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-12 (OR CURRENT VERSION)  
-SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION)



- NOTES**
- APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
  - IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

**INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR** 2  
SCALE: N.T.S. E-2



**TWO HOLE LUG** 3  
SCALE: N.T.S. E-2



CHECKED BY: BB

APPROVED BY: DJC

**SUBMITTALS**

REV.	DATE	DESCRIPTION	BY
2	09/11/17	REVISED-CODE UPDATE	AN
1	02/27/14	ISSUED FOR REVIEW	AAB
0	12/25/13	ISSUED FOR BP	AL

SITE NUMBER:  
CT33XC257

SITE NAME:  
CLARYVILLE  
NEXTTEL

SITE ADDRESS:  
188 MOODY ROAD  
ENFIELD, CT 06082

SHEET TITLE  
**GROUNDING DETAILS AND NOTES**

SHEET NUMBER  
E-2