

May 2nd, 2018

Melanie Bachman, Executive Director Connecticut Siting Council 10 FranklinSquare New Britain, CT 06051

> RE: Notice of Exempt Modification – Antenna Swap & Additional Ground Based Equipment for wireless facility located at 6 MAIN STREET, ESSEX, CONNECTICUT - CT03XC162 (41° 21' 4.608" N, -72° 24' 22.284" W)

Dear Ms. Bachman:

Sprint Spectrum, LP ("Sprint") currently maintains wireless telecommunications antennas at the (118-foot level) on an existing (124.5-foot tower) at the above-referenced address. Sprint intends to remove six (6) antennas from the tower and replace them with a total of three (3) antennas. Sprint also intents on adding Nine (9) new RRHs and relocating three (3) RRHs from the ground to the tower. All the proposed work is contained within the existing fenced area. Please refer to the attached drawings for site plans prepared by Infinigy Engineering.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to NORMAN NEEDLEMAN, FIRST SELECTMAN, and JOHN GUSZKOWSKI, TOWN PLANNER of the Town of ESSEX. A copy of this letter is also being sent to MACBETH VENTURES, LLC the owner of the property and tower.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b).

- 1. The proposed modifications will not result in an increase in the height of the existing tower.
- 2. The antennas work is a one-for-one replacement of facility components.
- The proposed modifications will include the addition of ground base equipment as depicted on the attached drawings; however, the proposed equipment will not require an extension of the site boundaries.





- 4. The proposed modifications will not increase noise levels at the facility by six decibels or more.
- 5. The additional ground based equipment will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b).

If you have any questions or require any additional information regarding this request, please do not hesitate to give me a call at (518) 871-3707 or email me to <u>aperkowski@airosmithdevelopment.com</u>

Kind Regards,

Arthur Perkowski Airosmith Development Inc. 32 Clinton Street Saratoga Springs, NY 12866 518-306-1711 desk & fax 518-871-3707 cell aperkowski@airosmithdevelopment.com

Attachment

CC: MACBETH VENTURES, LLC. NORMAN NEEDLEMAN JOHN GUSZKOWSKI





÷

NIOTGA FIRANES

0867

Postmark

Here

05/02/2018

(TO3×CIGA

se for Instruction

17



6 MAIN ST CTBK

Location	6 MAIN ST CTBK	Mblu	33/ 028/ / /
Acct#	00200100	Owner	MACBETH VENTURES LLC
Assessment	\$2,396,000	Appraisal	\$3,422,700
PID	1860	Building Count	3

Current Value

Appraisal		
Valuation Year	Total	
2015	\$3,422,700	
Assessment		
Valuation Year	Total	
2015	\$2,396,000	

Owner of Record

Owner	MACBETH VENTURES LLC	Sale Price	\$1,250,000
Co-Owner	C/O HT PARTNER LLC	Certificate	
Address	6 MAIN ST SUITE 112	Book & Page	180/ 285
CENTERBROOK, CT 06409	CENTERBROOK, CT 06409	Sale Date	05/26/1999
		Instrument	07

Ownership History

Ownership History					
Owner	Sale Price	Certificate	Book & Page	Instrument	Sale Date
MACBETH VENTURES LLC	\$1,250,000		180/ 285	07	05/26/1999

Building Information

MODEL

Building 1 : Section 1

Year Built:	1910	
Living Area:	18,575	
Building Percent	46	
Good:		
Building Attributes		
Field	Description	
STYLE	Office	

Comm/Ind

Stories:	2 Stories
Occupancy	2
Ext Wall 1	Brick
Exterior Wall 2	Asbestos
Roof Structure	Flat
Roof Cover	Tar + Gravel
Interior Wall 1	Drywall
Interior Wall 2	
Interior Floor 1	Carpet
Interior Floor 2	Hardwood
Heating Fuel	Oil
Heating Type	Hot Water
АС Туре	Central
Bldg Use	Commercial MDL-94
Total Rooms	
Total Bedrms	
Total Baths	
Heat/AC	Heat/AC Packag
Frame Type	Masonry
Baths/Plumbing	Average
Ceiling/Wall	CEIL & WALLS
Rooms/Prtns	Average
Wall Height	10

Building Photo



(http://images.vgsi.com/photos/EssexCTPhotos//\01\00\28/11.

Building Layout



Building Sub-Areas (sq ft) Legen			<u>Legend</u>
Code	Description	Gross Area	Living Area
BAS	First Floor	11,375	11,375
FUS	Full Upper Story	7,200	7,200
FOP	Open Porch	66	0
РТО	Patio	2,226	0
UAT	Unfinished Attic	270	0
UBM	Basement	10,987	0
		32,124	18,575

Building 2 : Section 1

Good:		
Building Percent	46	
Living Area:	1,742	
Year Built:	1910	

Building Attributes : Bldg 2 of 3		
Field	Description	
STYLE	Office	

MODEL	Comm/Ind
Stories:	1 Story
Occupancy	1
Ext Wall 1	Brick
Exterior Wall 2	
Roof Structure	Flat
Roof Cover	Tar + Gravel
Interior Wall 1	Drywall
Interior Wall 2	
Interior Floor 1	Carpet
Interior Floor 2	
Heating Fuel	Oil
Heating Type	Forced Air
АС Туре	None/partial
Bldg Use	Commercial MDL-94
Total Rooms	
Total Bedrms	
Total Baths	
Heat/AC	Heat Only
Frame Type	Masonry
Baths/Plumbing	Average
Ceiling/Wall	CEIL & WALLS
Rooms/Prtns	Light
Wall Height	12

Building Photo



(http://images.vgsi.com/photos/EssexCTPhotos//\01\00\28/12.

Building Layout



Building Sub-Areas (sq ft) Legend			<u>Legend</u>
Code	Description	Gross Area	Living Area
BAS	First Floor	1,742	1,742
		1,742	1,742

Building 3 : Section 1

Year Built:	1910
Living Area:	11,932
Building Percent	46
Good:	
Building	g Attributes : Bldg 3 of 3
Field	Description
STYLE	Office
MODEL	Comm/Ind
Stories:	1 Story
Occupancy	12
Ext Wall 1	Brick
Exterior Wall 2	

Roof Structure	Flat
Roof Cover	Tar + Gravel
Interior Wall 1	Drywall
Interior Wall 2	
Interior Floor 1	Carpet
Interior Floor 2	
Heating Fuel	Oil
Heating Type	Forced Air
АС Туре	Central
Bldg Use	Commercial MDL-94
Total Rooms	
Total Bedrms	
Total Baths	
Heat/AC	Heat/AC Packag
Frame Type	Masonry
Baths/Plumbing	Average
Ceiling/Wall	CEIL & WALLS
Rooms/Prtns	Average
Wall Height	10

Building Photo



 $(http://images.vgsi.com/photos/EssexCTPhotos//\01\00\28/13.$

Building Layout



Building Sub-Areas (sq ft) Legen			
Code	Description	Gross Area	Living Area
BAS	First Floor	11,932	11,932
		11,932	11,932

►

•

Extra Features

	Legend			
Code	Description	Sub Code	Sub Description	Size
SPR1	Sprinklers-Wet			11000 S.F.
SPR1	Sprinklers-Wet			20575 S.F.
ELV1	Elevator-Pass			3 STOPS
GEN	Generator			1 UNITS

Land

Land Use

Land Line Valuation

 Use Code
 200

 Description
 Commercial MDL-94

 Zone
 CML

 Neighborhood
 CI4

 Size (Acres)
 8.52

 Depth
 \$965,700

 Appraised Value
 \$91,379,600

Outbuildings

Outbuildings				Legend
Code	Description	Sub Code	Sub Description	Size
CELL	Cell Tower			1 UNITS
SHD1	Shed-utility			180 S.F.
FGR1	Garage-Ave			1350 S.F.
SHD1	Shed-utility			1000 S.F.
PAV1	Paving			10000 S.F.
SHD1	Shed-utility			180 S.F.
SHD1	Shed-utility			48 S.F.

Valuation History

Appraisal		
Valuation Year	Total	
2015	\$3,422,700	

Assessment			
Valuation Year	Total		
2015	\$2,396,000		

(c) 2016 Vision Government Solutions, Inc. All rights reserved.



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT03XC162

EE Dickenson Witchhazel 6 Main Street Essex, CT 06426

April 30, 2018

EBI Project Number: 6218003105

Site Compliance Summary			
Compliance Status:	COMPLIANT		
Site total MPE% of			
FCC general	19 00 %		
population	10.09 %		
allowable limit:			



April 30, 2018

SPRINT Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Emissions Analysis for Site: CT03XC162 – EE Dickenson Witchhazel

EBI Consulting was directed to analyze the proposed SPRINT facility located at **6 Main Street, Essex, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm2). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

<u>General population/uncontrolled exposure</u> limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limits for the 850 MHz Band is approximately 567 μ W/cm². The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



<u>Occupational/controlled exposure</u> limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over their exposure and can exercise control over the potential for exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **6 Main Street**, **Essex**, **CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the KMW ETCR-654L12H6 for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **118 feet** above ground level (AGL) for **Sector A**, **118 feet** above ground level (AGL) for **Sector B** and **118 feet** above ground level (AGL) for **Sector C**.
- 10) Emissions for additional carriers were calculated based upon known configurations for these carriers in this geographic area. The listing of all active carriers on this facility was taken from the Connecticut Siting Council site database.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

G i		G	D	G	G
Sector:	A	Sector:	В	Sector:	<u> </u>
Antenna #:	1	Antenna #:	1	Antenna #:	1
Maka / Modali	KMW	Maka / Modali	KMW	Maka / Modaly	KMW
Wake / Wiodel.	ETCR-654L12H6	Wake / Wiodel.	ETCR-654L12H6	Wake / Wouei.	ETCR-654L12H6
Coint	13.35 / 15.25/15.05	Coint	13.35 / 15.25 / 15.05	Coint	13.35 / 15.25 / 15.05
Gam:	dBd	Gam:	dBd	Gam:	dBd
Height (AGL):	118 feet	Height (AGL):	118 feet	Height (AGL):	118 feet
	850 MHz /		850 MHz /		850 MHz /
Frequency Bands	1900 MHz (PCS) /	Frequency Bands	1900 MHz (PCS) /	Frequency Bands	1900 MHz (PCS) /
	2500 MHz (BRS)		2500 MHz (BRS)		2500 MHz (BRS)
Channel Count	18	Channel Count	18	Channel Count	18
Total TX	280 W-#-	Total TX	200 W-#-	Total TX	200 W-#-
Power(W):	580 watts	Power(W):	580 watts	Power(W):	580 watts
ERP (W):	11,775.31	ERP (W):	11,775.31	ERP (W):	11,775.31
Antenna A1	266.0/	Antenna B1	266.0/	Antenna C1	266.0/
MPE%	3.00 %	MPE%	3.00 %	MPE%	3.00 %

Site Composite MPE%			
Carrier	MPE%		
SPRINT – Max per sector	3.66 %		
AT&T	6.75 %		
Verizon Wireless	7.68 %		
Site Total MPE %:	18.09 %		

SPRINT Sector A Total:	3.66 %
SPRINT Sector B Total:	3.66 %
SPRINT Sector C Total:	3.66 %
Site Total:	18.09 %

SPRINT _ Frequency Band / Technology Max Power Values (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (µW/cm ²)	Frequency (MHz)	Allowable MPE (µW/cm ²)	Calculated % MPE
Sprint 850 MHz CDMA	1	432.54	118	1.24	850 MHz	567	0.22%
Sprint 850 MHz LTE	2	432.54	118	2.48	850 MHz	567	0.44%
Sprint 1900 MHz (PCS) CDMA	5	535.94	118	7.68	1900 MHz (PCS)	1000	0.77%
Sprint 1900 MHz (PCS) LTE	2	1,339.86	118	7.68	1900 MHz (PCS)	1000	0.77%
Sprint 2500 MHz (BRS) LTE	8	639.78	118	14.67	2500 MHz (BRS)	1000	1.47%
						Total:	3.66%



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	3.66 %
Sector B:	3.66 %
Sector C:	3.66 %
SPRINT Maximum	3 66 %
Total (per sector):	5.00 %
Site Total:	18.09 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **18.09** % of the allowable FCC established general population limit sampled at the ground level. Emissions for additional carriers were calculated based upon known configurations for these carriers in this geographic area. The listing of all active carriers on this facility was taken from the Connecticut Siting Council site database.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

FROM ZERO TO INFINIGY the solutions are endless

1033 WATERVLIET SHAKER RD, ALBANY, NY 12205

Water Tank Analysis Report

January 19, 2018

Sprint Site Number:	CT03XC162
Sprint Site Name:	EE Dickenson Witchhazel
Infinigy Job Number	526-104
Client	Airosmith Development
Proposed Carrier	Sprint
	6 Main Street, Essex, CT 06426
Site Address:	41° 21'4.61" N NAD83
	72° 24' 22.28" W NAD83
Structure Type	124.5' Water Tank
Overall Result	Pass

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA and AWWA code requirements. The water tank is therefore deemed adequate to support the existing and proposed loading as listed in this report.



Nathaniel R. Ober, E.I.T. Northeast Structural Region Lead

AZ	СА	CO	FL	GA	IL	MD	NC	NH	NJ	NY	TN	TX	WA
					11	VFIN	١G	Y8					

Contents

Introduction	3
Supporting Documentation	3
Analysis Code Requirements	3
Conclusion	3
Existing Loading	4
To be Removed	4
Proposed Loading	4
Final Configuration	4
Results and Conclusion	5
Assumptions and Limitations	5
Calculations	Appended

Introduction

Infinigy Engineering has been requested to perform a structural analysis on the existing 124.5' water tank. All supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site.

Supporting Documentation

Tower Mapping	Infinigy Engineering, dated December 12, 2017
Previous Analysis	Clough, Harbour & Associates LLP, dated November 25, 1996
Proposed Loading	Infinigy Construction Drawings, dated September 27, 2017

Wind Speed	101 mph (3-Second Gust)
Wind Speed w/ ice	50 mph (3-Second Gust) w/ 3/4" ice
TIA Revision	ANSI/TIA222-G
Water Tank Code	ANSI/AWWA D103-09
Adopted IBC	2012 IBC / 2016 Connecticut State Building Code
Structure Class	2
Exposure Category	С
Topographic Category	1
Calculated Crest Height	0 ft

Analysis Code Requirements

Conclusion

Upon reviewing the results of this analysis, it is our opinion that the structure meets the specified TIA and AWWA code requirements. The water tank is therefore deemed adequate to support the existing and proposed loading as listed in this report.

If you have any questions, require additional information, or actual conditions differ from those as detailed in this report please contact me via the information below:

Joe Johnstone, P.E. Professional Engineer 1033 Waterliet Shaker Road, Albany, NY 12205 (O) (518) 690-0790 | (M) (518) 221-4665 jjohnston@infinigy.com | www.infinigy.com

Existing Loading

Mount Height (ft)	Qty.	Appurtenance	Mount Type	Coax& Lines	Carrier
118.0	3	Allen Telecom DB980H90E-M	Pipe Mount	-	-

To Be Removed Loading

Mount Height (ft)	Qty.	Appurtenance	Mount Type	Coax& Lines	Carrier
118.0	3	Allen Telecom DB980H90E-M	Pipe Mount	-	Sprint

Proposed Loading

Mount Height (ft)	Qty.	Appurtenance	Mount Type	Coax& Lines	Carrier
	3	KMW ETCR-654L12H6			
110.0	3	Alcatel-Lucent TD-RRH8x20-25	Dina Maunt		Somint
118.0	6	Alcatel-Lucent RRH-2x50-800	Pipe Mount	-	Sprint
	3	Alcatel-Lucent 1900 MHz RRH			

Final Configuration

Mount Height (ft)	Qty.	Appurtenance	Mount Type	Coax& Lines	Carrier
	3	KMW ETCR-654L12H6			
112.0	3	Alcatel-Lucent TD-RRH8x20-25	Dina Maunt		Conint
118.0	6	Alcatel-Lucent RRH-2x50-800	Pipe Mount	-	Sprint
	3	Alcatel-Lucent 1900 MHz RRH			

Results and Conclusion

We have completed the structural analysis of the subject water tank and have found it to be adequate within the scope of this analysis to support the proposed antenna loading. Since the additional projected wind area increases the overturning moment of the water tank by 9.4%, which is less than 10% maximum increase permitted by 2012 IBC section 3403.4 before a complete structural analysis of the existing facility is required.

Assumptions and Limitations

Our structural calculations are completed assuming all information provided to Infinigy Engineering is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition of "like new" and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report Infinigy Engineering should be notified immediately to complete a revised evaluation.

Our evaluation is completed using standard TIA, AISC, ACI, and ASCE methods and procedures. Our structural results are proprietary and should not be used by others as their own. Infinigy Engineering is not responsible for decisions made by others that are or are not based on our supplied assumptions and conclusions.

This report is an evaluation of the tower structure only and does not reflect adequacy of any existing antenna mounts, mount connections, or coax mounting attachments. These elements are assumed to be adequate for the purposes of this analysis and are assumed to have been installed per their manufacturer requirements.



COMPARISON OF OVERTURNING MOMENTS

Site Name:	EE Dickenson Witchhazel
Job Number:	526-104
Engineer:	DVA
Date:	12/21/2017

WT Members	Quantity	Member Area (ft ²)	Centerline (ft)	Pw (psf)	Fa (lb)	Moment (lb-ft)
WT Bowl	1	556.0	112	20.5	11397.9	1276563.6
Legs	4	171.0	164	22.2	3798.5	2491828.7
Horizontals at 36 ft	2	13.3	36	53.8	717.5	51656.9
Horizontals at 70 ft	2	12.3	70	61.9	763.4	106872.1
Diagonals at 18 ft	4	21.2	18	18.0	381.6	27475.2
Diagonals at 54 ft	4	20.8	54	18.0	373.5	80676.0
Diagonals at 88 ft	4	19.8	88	19.5	384.8	135459.6
Standpipe	1	298.5	49.75	18.0	5373.0	267306.8
Climbing Ladder 1	1	41.8	61.25	60.2	2517.5	154196.8
Climbing Ladder 2	1	11.7	115	68.7	801.7	92191.3
Catwalk	1	73.7	107.8	67.8	4997.1	538688.7

WT Overturning Moment = 5,247,875

Appurtenance Model/Description	Quantity	Effective Area (ft ²)	Centerline (ft)	q _z (psf)	Fa (lb)	Moment (lb-ft)
Powerwave XCM-800/1900-90-12.51	6	5.45	107.75	32.19	105.3	68062.2
Powerwave LPG21401	6	0.55	107.75	32.19	10.7	6902.9
Amphenol LPA80063/6CFEDIN	4	9.88	108.5	32.24	191.0	82912.8
Commscope SBNHH-1D65B	6	8.20	109	32.27	158.8	103845.8
Alcatel Lucent B13 RRH 4x30	3	2.46	109	32.27	47.6	15566.1
Alcatel Lucent B66a RRH 4x45	3	2.54	109	32.27	49.1	16064.2
Andrew SBNH-1D4545A	3	7.24	107.5	32.18	139.9	45108.5
Ericsson RRUS-11	5	2.78	107.5	32.18	53.8	28896.7
Ericsson RRUS-12	1	3.15	107.5	32.18	60.7	6527.6
10"x10"x6.5" Box	2	0.83	110.5	32.37	16.2	3576.4
14.5"x16"x6.5" Box	1	1.87	110.5	32.37	36.2	4005.6
KMW ETCR-654L12H6	3	15.71	118	32.82	103.1	36492.7
Alcatel-Lucent TD-RRH8x20-25	3	3.70	118	32.82	24.3	8606.3
Alcatel-Lucent RRH-2x50-800	6	1.73	118	32.82	11.4	8054.5
Alcatel-Lucent 1900 MHz RRH	3	2.31	118	32.82	15.2	5372.9
Empty Mount Pipe	1	0.95	107.5	32.18	18.3	1971.8

Appurtenances Overturning Moment = 441,967

Feedline Model/Description	Quantity Exposed to Wind	Width (in)	Height (ft)	q _z (psf)	Fa (lb)	Moment (lb-ft)
(30) 1-5/8" Coax	6.0	2.0	106.5	28.3	715.7	41690.9
(1) 3" Coax	1.0	3.0	106.5	28.3	180.7	10528.0

Feedlines Overturning Moment = 52,219

WT Overturning Moment = 5,247,875 lb-ft

Overturning Moment Due to Appurtances & Feedlines = 494,186 lb-ft

Overturning Moment Percentage Increase = 9.4%



1033 Watervliet Shaker Road Albany, NY 12205 <u>Structural@infinigy.com</u> Office: 518.690.0790

TOWER MAPPING REPORT

EE Dickenson Witchhazel WT CT03XC162 124'-6" Water Tank

> Job #: 173586E Date: 12/12/2017



FROM ZERO TO INFINIGY the solutions are endless

TOWER MAPPING

Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page	of_15_

Page Title	Initials	Page # (s)	Notes
Checklist and Notes	DJN	1	
Ladder & Waveguides	DJN	2-3	
Tower Elevation	DJN	4	
Base & Foundation Details	DJN	5-6	
Plan at Base	DJN	7	
Plan at Horizontals	DJN	8	
Tank Elevation	DJN	9	
Plan at Catwalk	DJN	10	
Plan at Top of Tower	DJN	10	
Catwalk Details	DJN	11	
Transmission Cables	DJN	12	
Antenna and Mount Details	DJN	13-14	
Photo Log	DJN	15	

SITE INFORMATION

SITE NAME:	EE Dick	EE Dickenson Witchhazel WT				
SITE NUMBER:	CT03X0	CT03XC162				
SITE CONTACT:	Cristine	Volkman				
GATE COMBO:	DNR					
ADDRESS:	6 Railro	oad Ave				
	Essex, (CT 06429				
LAT/LONG:	N 41.35	5128°	W 72.406	519°		
TOWER TAG:	N/A					
FCC ID:	CNR					
TELCO PROVIDER & METER #: AT&T		AT&T F10 ESSXC	T&T F10 ESSXCTSN			
POWER PROVIDER:		CNR				
POWER METER # & CARRIE	R:	89 251 839 - Sprint				
		89 638 066 - Cin	89 638 066 - Cingular			
		89 133 578 - AT	&т			
		89 252 171 - Ver	rizon			
CARRIERS:	Verizon					
	AT&T					
Cingula		ir				
LIGHTING MANUFACTURER AND CONTROLLE			N/A			
ADDITIONAL NOTES:						
	1					

SAFETY:

EQUIPMENT INSPECTION (INITIAL):	DK, ТВ
TOWER CONDITION FROM GROUND:	ОК
SAFETY CABLE CONDITION FROM GROUND:	N/A
NEAREST EMS/FIRE DEPARTMENT OR HOSPITAL:	0.3 miles to Essex Fire Dept.
PRECLIMB INSPECTION PERFORMED (SIGN):	Douglas Kosiba



LADDER

Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 2	of_15_



Description	#	Height	Width	Step	Rail (type & size)	Rung (type & size)	Safety (type & size)
Ladder	1	15' - 110'	14"	11"	PL 2"x ⁷ / ₁₆ "	Bar 5⁄8"x5⁄8"	N/A
Ladder	2	107' - 124'6"	14"	11"	PL 2"x ⁷ / ₁₆ "	Bar 5⁄8"x5⁄8"	N/A



WAVEGUIDE

Site Na	me	EE Dickenson Witchhazel WT
Job #		173586E
Client #	ŧ	CTO3XC162
Date		2/ 2/20 7
Page	3	_of15



#	Height	Width	Step	Rail (type & size)	Rung (type & size)	Holes (size & spacing)
1	7'8" - 106'6"	24"	18"	(2) Pipe on A leg	C 2"x2"x ¹ ⁄ ₈ "	Alternating between rungs (13) ¾"Ø & ¾"Ø @ 2" C-C
2	7'8" - 106'6"	24"	18"	(2) Pipe on B leg	C 2"x2"x ¹ ⁄ ₈ "	Alternating between rungs (13) ¾"Ø & ¾"Ø @ 2" C-C



Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 4	of_15

TOWER ELEVATION





Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 5	of_15_

RISER BASE & FOUNDATION DETAILS





Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 6	_of_15_

LEG BASE & FOUNDATION DETAILS





PLAN VIEW AT BASE

Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 7	of_15_





Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 8	of_15_

PLAN VIEW AT HORIZONTALS





Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 9	of_15_

ELEVATION VIEW AT TANK





PLAN VIEW AT CATWALK

Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 10	of_15_





CATWALK DETAILS

Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page	of_15_





Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 2	of_15





Coax #	Туре	Size	Elevation	Antenna	Carrier	Notes
1-12	FH	11⁄4	7'0" - 107'6"	1,4-6,9,13-15	AT&T	
13	Flex	2¼″Ø	7'0" - 107'6"	18,22-24	AT&T	
14-19	FH	15/8	7'0" - 107'6"	2-3,7,10,12	Verizon	
20-21	FH	11⁄4	7'0" - 107'6"	16,19-20,25	Verizon	
22	MC	1"Ø	0'0" - 106'6"	-	Water Authority	
23	SM	³⁄8"Ø	0'0" - 117'6"	-	Water Authority	
24	MC	1"Ø	0'0" - 117'6"	-	Water Authority	
25-30	FH	15%	5'0" - 115'0"	8,11,17,21,26-27	Sprint	



Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XCI62
Date	2/ 2/20 7
Page 3	of_15_

ANTENNA AND MOUNT DETAILS

Ant #	Eleva ^{© Mnt}	ation ∉ Ant	Location Circumferencial distance from ladder (Tank: 82'-0")	Coax	Antenna/TMA/RRU (etc)	Mount (off railing typ.)
1	107'-6"	107'-9"	2'-3"	1-13	Powerwave AXCM-800/1900-90-12.51/16.5 (Panel) (2) Powerwave LPG21401 (TMA)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7½"
2	107'-6"	108'-6"	5'-0"	14-21	Amphenol LPA80063/6CFEDIN (Panel)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7"
3	107'-6"	109'-0"	10'-0"	14-21	Commscope SBNHH-1D65B (Panel) (1) Alcatel Lucent B66a RRH 4x45 (RRH)	(1) P 2.4"Øx4' (1) P 2.4"Øx7', SO: 7" (1) P 2.4"Øx2'-6"
4	107'-6"	107'-9"	12'-3"	1-13	Powerwave AXCM-800/1900-90-12.51/16.5 (Panel)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7½"
5	107'-6"	109'-0"	15'-2"	1-13	Commscope SBNHH-1D65B (Panel) (1) Alcatel Lucent B13 RRH 4x30 (RRH) (1) 10"x10"x6¼" Box	(1) P 2.4"Øx4' (1) P 2.4"Øx7', SO: 8"
6	107'-6"	107'-6"	17'-6"	1-13	Andrew SBNH-1D4545A (Panel) (2) Ericsson RRUS 11 B12 (RRU)	(1) P 2.4"Øx4' (1) P 2.9"Øx10', SO: 6"
7	107'-6"	108'-6"	20'-0"	14-21	Amphenol LPA80063/6CFEDIN (Panel)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7"
8	115'-0"	115'-0"	24'-8"	25-30	Allen Telecom DB980H90E-M (Panel)	P 2.4"Øx5'-4", SO: 6¼" off tank wall
9	107'-6"	107'-9"	29'-3"	1-13	Powerwave AXCM-800/1900-90-12.51/16.5 (Panel) (2) Powerwave LPG21401 (TMA)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7½"
10	107'-6"	109'-0"	31'-9"	14-21	Amphenol LPA80080/6CFEDIN (Panel) (1) Raycap RRFDC-3315-PF-48 (SP)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7"
11	115'-0"	115'-0"	34'-7"	25-30	Allen Telecom DB980H90E-M (Panel)	P 2.4"Øx5'-4", SO: 6¼" off tank wall
12	107'-6"	109'-0"	37'-3"	14-21	Commscope SBNHH-1D65B (Panel) (1) Alcatel Lucent B66a RRH 4x45 (RRH)	(1) P 2.4"Øx4' (1) P 2.4"Øx7', SO: 7" (1) P 2.4"Øx2'-6"
13	107'-6"	107'-9"	40'-0"	1-13	Powerwave AXCM-800/1900-90-12.51/16.5 (Panel)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7½"
14	107'-6"	109'-0"	42'-7"	1-13	Commscope SBNHH-1D65B (Panel) (1) Alcatel Lucent B13 RRH 4x30 (RRH)	(1) P 2.4"Øx4' (1) P 2.4"Øx7', SO: 8"
15	107'-6"	107'-6"	44'-7"	1-13	Andrew SBNH-1D4545A (Panel) (2) Ericsson RRUS 11 B12 (RRU)	(1) P 2.4"Øx4' (1) P 2.9"Øx10', SO: 6"
16	107'-6"	109'-0"	47'-6"	14-21	Amphenol LPA80080/6CFEDIN (Panel)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7"
17	115'-0"	115'-0"	54'-3"	25-30	Allen Telecom DB980H90E-M (Panel)	P 2.4"Øx5'-4", SO: 6¼" off tank wall
18	107'-6"	107'-9"	56'-8"	1-13	Powerwave AXCM-800/1900-90-12.51/16.5 (Panel) (2) Powerwave LPG21401 (TMA)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7½"
19	107'-6"	108'-6"	59'-3"	14-21	Amphenol LPA80063/6CFEDIN (Panel) (1) Raycap RRFDC-3315-PF-48 (SP)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7"



Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XC162
Date	2/ 2/20 7
Page 4	of_15_

ANTENNA AND MOUNT DETAILS

Ant #	Eleva ^{© Mnt}	ation ∉ Ant	Location Circumferencial distance from ladder (Tank: 82'-0")	Coax	Antenna/TMA/RRU (etc)	Mount (off railing typ.)
20	107'-6"	109'-0"	64'-3"	14-21	Commscope SBNHH-1D65B (Panel) (1) Alcatel Lucent B66a RRH 4x45 (RRH)	(1) P 2.4"Øx4' (1) P 2.4"Øx7', SO: 7" (1) P 2.4"Øx2'-6"
21	115'-0"	115'-0"	64'-2"	25-30	Allen Telecom DB980H90E-M (Panel)	P 2.4"Øx5'-4", SO: 6¼" off tank wall
22	107'-6"	107'-9"	67'-2"	1-13	Powerwave AXCM-800/1900-90-12.51/16.5 (Panel)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7½"
23	107'-6"	109'-0"	69'-9"	1-13	Commscope SBNHH-1D65B (Panel) (1) Alcatel Lucent B13 RRH 4x30 (RRH)	(1) P 2.4"Øx4' (1) P 2.4"Øx7', SO: 8"
24	107'-6"	107'-6"	72'-4"	1-13	Andrew SBNH-1D4545A (Panel) (1) Ericsson RRUS 11 B12 (RRU) (1) Ericsson RRUS 12 B4 (RRU)	(1) P 2.4"Øx4' (1) P 2.9"Øx10', SO: 6"
25	107'-6"	108'-6"	75'-0"	14-21	Amphenol LPA80063/6CFEDIN (Panel)	(1) P 2.4"Øx4' (1) P 2.4"Øx6', SO: 7"
26	115'-0"	115'-0"	2'-6"	25-30	Allen Telecom DB980H90E-M (Panel)	P 2.4"Øx5'-4", SO: 6¼" off tank wall
27	115'-0"	115'-0"	74'-2"	25-30	Allen Telecom DB980H90E-M (Panel)	P 2.4"Øx5'-4", SO: 6¼" off tank wall

MISCELLANEOUS MOUNT DETAILS

ltem	Elevation	Location Circumferencial distance from ladder (Tank: 1057")	Coax	Details
Empty Mount Pipe	107'-6"	34'-9"	-	P 2.4"Øx4', SO: 4"
10"x10"x6¼" Box	110'-6"	42'-7"	1-13	(2) Unistrut on the inside of rail
14¼"x16"x6¼" Box	110'-6"	46'-2"	1-13	(2) Unistrut on the inside of rail
10"x10"x6¼" Box	110'-6"	71'-0"	1-13	(2) Unistrut on the inside of rail



Site Name	EE Dickenson Witchhazel WT
Job #	173586E
Client #	CTO3XCI62
Date	2/ 2/20 7
Page 15	of_15_

PHOTO LOG

РНОТО #	PHOTO DESCRIPTION
1-4	Site Signs and Tower Legs
5-7	Shelter
8-14	Tower Elevations
15-27	Up Tower Photos
28-36	Compound and Equipment
37-64	Tower up to Catwalk
65-117	Tower at Catwalk
118-120	Top of Tank
121-124	Surrounding Area
125	Top of Tank
126-150	Foundation Photos
151-155	Site Access and Tank



1033 WATERVLIET SHAKER RD, ALBANY, NY 12205

January 18, 2018

Terri Burkholder

Project Manager Airosmith Development tburkholder@asdwireless.com www.airosmithdevelopment.com

RE: Sprint Project DO Macro Upgrade Mount Analysis

Sprint Site Number:	CT03XC162
Sprint Site Name:	EE Dickenson Witchhazel
Site Address:	6 Main Street, Essex, CT 06426
Building Code:	2012 IBC / 2016 Connecticut State Building Code
Design Standard:	ANSI/TIA-222-G
Result:	45.0%
Usage:	Pass

Dear Ms. Burkholder:

At your request, Infinigy Engineering, PLLC has reviewed the existing Sprint water tank mounted equipment supports at the above referenced site for adequacy to support the existing and proposed loads for the referenced project. This evaluation is based on a review of the information from the RFDS (dated 04/22/2017) provided by Sprint and Construction Drawings (dated 09/27/17) provided by Infinigy Engineering, PLLC.

This evaluation assumes that all structural members are in good condition, have not been altered from the manufacturer's original design, and have been installed per the manufacturer's requirements. Prior to installation of any new appurtenances, the contractor shall inspect the condition of all relevant members and connections and shall tighten all connections. The contractor is responsible for the means and methods of construction and shall notify Infinigy Engineering, PLLC immediately if any field conditions differ from those listed above.

INFINIGY8

Should there be any questions, please do not hesitate to contact us at (518) 690-0790.

Sincerely,

AT CA

Joseph R. Johnston, P.E. VP Structural Engineering/Principal <u>structural@infinigy.com</u> Connecticut P.E. License Number: PEN.0029460 KC/RJL





INFINIGY WIND LOAD CALCULATOR 3.0.2

Client: Airosmith Carrier: Sprint Engineer: RJL Date: 12/11/2017

CT03XC162

Sit	e Information Inpu	its:
Adopted Building Code:	2012 IBC	
Structure Load Standard:	TIA-222-G	
Antenna Load Standard:	TIA-222-G	
Structure Risk Category:	III	
Structure Type:	Water Tank	
Number of Sectors:	3	
Structure Shape 1:	Round	
v	/ind Loading Input	s:

Design Wind Velocity:

Wind Centerline 1 (z₁):

Side Face Angle (0)

Exposure Category:

Topographic Category:

Site Name:

Rooftop Inputs: Rooftop Wind Speed-Up?: No

Wind with No Ice									
q _z (psf)	F _{ST} (psf)								
45.98	1.00	55.17							

Wind with Ice										
q _z (psf)	Gh	F _{ST} (psf)								
7.97	1.00	26.53								

	Ice Loading Inputs	:
Is Ice Loading Needed?:	Yes	
Ice Wind Velocity:	50	mph (nominal 3-second gust)
Base Ice Thickness:	0.75	in

112

118.0

60

С

1

ft

degrees

mph (nominal 3-second gust)

Input Appurtenance Information and Load Placements:

Appurtenance Name	Elevation (ft)	Total Quantity	Ка	Front Shape	Side Shape	q _z (psf)	EPA (ft ²)	Fz (lbs)	Fx (lbs)	Fz(60) (lbs)	Fx(30) (lbs)
KMW ETCR-654L12H6	118.0	3	1.00	Flat	Flat	45.98	15.71	722.13	275.95	387.49	610.58
ALU TD-RRH8x20-25	118.0	3	1.00	Flat	Flat	45.98	4.03	185.28	70.15	98.94	156.50
ALU RRH-2x50-800	118.0	3	1.00	Flat	Flat	45.98	1.73	79.69	61.30	65.90	75.09
ALU RRH-2x50-800	118.0	3	1.00	Flat	Flat	45.98	1.73	79.69	61.30	65.90	75.09
						I	I		I		1



Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Туре	Design List	Material	Design Rules
1	M1	N1	N2			RIGID	None	None	RIGID	Typical
2	M2	N3	N4			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
3	M3	N5	N6			RIGID	None	None	RIGID	Typical
4	M4	N7	N8			RIGID	None	None	RIGID	Typical
5	M5	N9	N10			Mount Pipe	Column	Pipe	A53 Gr.B	Typical
6	M6	N11	N12			RIGID	None	None	RIGID	Typical

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[K]
1	General			• • •	
2	RIGID		4	28	0
3	Total General		4	28	0
4					
5	Hot Rolled Steel				
6	A53 Gr.B	PIPE 2.0	2	240	0
7	Total HR Steel		2	240	0

Basic Load Cases

	BLC Description	Category	X Gravi	Y Gravi	Z Gravity	Joint	Point	Distrib	Area(M	Surfac
1	Self Weight	DĹ		-1	-		5		•	
2	Wind Load AZI 000	WLZ					5		1	
3	Wind Load AZI 090	WLX					5		1	
4	Ice Weight	OL1					5	6		
5	Wind + Ice Load AZI 000	OL2					5		1	
6	Wind + Ice Load AZI 090	OL3					5		1	
7	Service Live 1	LL								
8	Seismic Load AZI 000	ELZ					5			
9	Seismic Load AZI 090	ELX					5			
10	BLC 2 Transient Area Loads	None						2		
11	BLC 3 Transient Area Loads	None						6		
12	BLC 5 Transient Area Loads	None						2		
13	BLC 6 Transient Area Loads	None						6		

Load Combinations

	Description	SI	PDelta	SRSS BL	CFa	В	Fa	. В	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa
1	1.4D	Yes	Υ	DI	. 1.4																		
2 1	.2D + 1.6W AZI 000)Yes	Υ	DI	. 1.2	W	1.6																
3 1	.2D + 1.6W AZI 030)Yes	Y	DI	. 1.2	W	1.3	.W	.8														
4 1	.2D + 1.6W AZI 060)Yes	Y	DI	. 1.2	W	.8	W	.1.3														
5 1	.2D + 1.6W AZI 090)Yes	Y	DI	. 1.2			W	1.6														
6 1	.2D + 1.6W AZI 120)Yes	Υ	DI	. 1.2	W	8	W	.1.3														
7 1	.2D + 1.6W AZI 150)Yes	Υ	DI	. 1.2	W	1	.W	.8														
8 1	.2D + 1.6W AZI 180)Yes	Y	DI	. 1.2	W	-1.6																
9 1	.2D + 1.6W AZI 210)Yes	Υ	DI	. 1.2	W	-1	.W	8														
10 1	.2D + 1.6W AZI 240)Yes	Y	DI	. 1.2	W	8	W	1														
11 1	.2D + 1.6W AZI 270)Yes	Υ	DI	. 1.2			W	1.6														
12 1	.2D + 1.6W AZI 300)Yes	Υ	DI	. 1.2	W	.8	W	1														
13 1	.2D + 1.6W AZI 330)Yes	Y	DI	. 1.2	W	1.3	.W	8														
14 0	.9D + 1.6W AZI 000)Yes	Y	DI	9	W	1.6																
15 0	.9D + 1.6W AZI 030)Yes	Y	DI	9	W	1.3	W	.8														
16 0	.9D + 1.6W AZI 060)Yes	Y	DI	9	W	.8	W	.1.3														

Load Combinations (Continued)

	Description	S	PDelta	aSRSS BLC	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa	В	Fa
17 0	.9D + 1.6W A7I	090 Yes	Y	DI	.9			W	1.6														
18 0	9D + 1.6W AZI	120 Yes	Ŷ	DI	9	W	- 8	W	.1.3														
19 0	9D + 1 6W AZI	150 Yes	Ý		9	W.,	-1	W.,	8														
20 0	9D + 1.6W AZI	180 Yes	V		 a	W	-16		1.0														
20 0.	0D + 1.6W AZI	210 Ves	V		0	W/	_1	w	0														
21 0.	$\frac{.90 + 1.000 \text{ AZI}}{.00 + 1.600 \text{ AZI}}$	240 Vos	I V		.9	10/	0	10/	1														
22 0.	<u>.9D + 1.0W AZI</u>	240 103	I V		.9	vv	0	VV	1.6														
23 0.	<u>.9D + 1.6W AZI</u>	270 res	Y		.9	14/	-	VV	-1.0														
24 0.	<u>.9D + 1.6W AZI</u>	300 res	Y	DL	.9	VV	.8	VV	1														
25 0.	<u>.9D + 1.6W AZI</u>	330 Yes	Y	DL	.9	VV	.1.3	VV	8														
26	<u> 1.2D + 1.0Di</u>	Yes	Y	DL	1.2	O	. 1																
27 1.3	.2D + 1.0Di + 1.0Wi	AZYes	Y	DL	1.2	O	1	O	. 1														
28 1.3	.2D + 1.0Di + 1.0Wi	AZYes	Y	DL	1.2	O	. 1	O	866	O	.5												
29 1.3	2D + 1.0Di + 1.0Wi	AZYes	Y	DL	1.2	O	. 1	O	.5	O	.866												
30 1.3	2D + 1.0Di + 1.0Wi	AZYes	Y	DL	1.2	O	. 1			O	1												
31 1.3	2D + 1.0Di + 1.0Wi	AZYes	Y	DL	1.2	O	. 1	O	5	O	.866												
32 1.3	2D + 1.0Di + 1.0Wi	AZYes	Y	DL	1.2	O	. 1	O	8	O	.5												
33 1.3	2D + 1.0Di + 1.0Wi	AZYes	Y	DI	1.2	0	1	0	-1														
34 1.3	2D + 1.0Di + 1.0Wi	AZYes	Ý	DI	12	0	. 1	0	8	0	- 5												
35 1	2D + 1.0Di + 1.0Wi	AZ. Yes	Y		12	0.	. 1	0.	- 5	0	8.												
36 1	2D + 1.0Di + 1.0Wi	AZ Yes	V		12	0	1			0	_1												
37 1	2D + 1 0Di + 1 0Wi	AZ Ves	V		1.2	0	1	0	5	0	- 8												
30 1	2D + 1 0Di + 1 0Mi	A7 Ves			1.2	0	1	0	866	0	5												
20 1.	2D + 1.6D + 1.000	(30 Vac	T V		1.2	11	4 5	0 W	000	0	5												
39 1.	2D + 1.5L + 1.000L	(30	Y		1.2		1.5	VV	.002	14/	044												
40 1.	2D + 1.5L + 1.000L	(30Yes	Y	DL	1.2		1.5	VV		VV	.041												
41 1.	<u>2D + 1.5L + 1.0VVL</u>	(30Yes	Y	DL	1.2		1.5	VV	.041	VV	.071												
42 1.3	2D + 1.5L + 1.0WL	(30Yes	Y	DL	1.2	LL	1.5			VV	.082												
43 1.3	.2D + 1.5L + 1.0WL	(30Yes	Y	DL	1.2		1.5	W	0	W	.071												
44 1.3	.2D + 1.5L + 1.0WL	(30Yes	Y	DL	1.2	LL	1.5	W	0	W	.041												
45 1.3	2D + 1.5L + 1.0WL	(30Yes	Y	DL	1.2	LL	1.5	W	0														
46 1.3	2D + 1.5L + 1.0WL	(30Yes	Y	DL	1.2	LL	1.5	W	0	W	0												
47 1.3	2D + 1.5L + 1.0WL	(30Yes	Y	DL	1.2	LL	1.5	W	0	W	0												
48 1.3	2D + 1.5L + 1.0WL	(30Yes	Y	DL	1.2	LL	1.5			W	0												
49 1.3	2D + 1.5L + 1.0WL	(30Yes	Ŷ	DI	12	11	15	W	.041	W	0												
50 1.3	2D + 1.5L + 1.0WL	(30. Yes	Ý		12	11	1.5	W.,	.071	W	0												
51 (1	2+0.2Sds) + 1.0 F	AZ Yes	V		12	FI 7	1 1																
52 (1	2+0.2Sds) + 1.0 E	AZ Yes	V		12	FI 7	7 866	F	5														
52 (1	2+0.28ds) + 1.0 E	Δ7 Ves	V		1.2	FI 7	5	F	866														
53 (1	(2+0.25ds) + 1.0 E	AZ Vos	I V		1.2		5	E	.000														
54 (1	2 ± 0.25 (0	AZ Mar	Y		1.2	E1 -	-	E	966														
50 (1	2+0.25 ds $+ 1.0$ E	AZ Mar	Y		1.2		5	E	.000														
50 (1	.2+0.25 (AZres	Y		1.2		0	E	.5														
5/ (1	.2+0.25uS) + 1.0 E	AZYes	Y	DL	1.2		-1	-	-														
58 (1	.2+0.2Sds) + 1.0 E	AZYes	Y	DL	1.2	ELZ	8	E	5														
59 (1	.2+0.2Sds) + 1.0 E	AZYes	Y	DL	1.2	ELZ	45	E	8														
60 (1	.2+0.2Sds) + 1.0 E	AZYes	Y	DL	1.2			E	-1														
61 (1	.2+0.2Sds) + 1.0 E	AZYes	Y	DL	1.2	ELZ	.5	E	8														
62 (1	.2+0.2Sds) + 1.0 E	AZYes	Y	DL	1.2	ELZ	2.866	E	5														
63 (0).9-0.2Sds) + 1.0E /	AZI Yes	Y	DL	.864	ELZ	1																
64 (0).9-0.2Sds) + 1.0E /	AZIYes	Y	DL	.864	ELZ	Z.866	E	.5														
65 (0).9-0.2Sds) + 1.0E /	AZIYes	Y	DI	.864	ELZ	.5	E	.866														
66 (0).9-0.2Sds) + 1.0E /	AZIYes	Ý		.864			E	1														
67 (0).9-0.2Sds) + 1.0F	AZIYes	Y		.864	EL7	- 5	Ε	.866														
68 (0	(9-0.2Sds) + 1.0E/		V		864	FI 7	8	F	5														
60 (0	19-0 2Sds) + 1 0E /	AZI Vas	V		864	FI 7	7 1		.5														
70 (0	(9.0.28ds) + 1.0E7				864	EL 2	- 1	F	E														
70 (0	1.0 - 0.20 (1.0 E / 1.0 E / $1.$		Y		.004 064		0	E	5 °									-		-			
71 (0	1.9 - 0.25 us + 1.0 E		Y	DL	.004		5	C	0														
72 (0	1.9 - 0.25 ds + 1.0 E A	∠iYes	Y	DL	.004		-	E	-1			-											
73 (0	0.9-0.2Sds) + 1.0E /	₩∠IYes	Y		.864	ELZ	4.5	E	8														

Load Combinations (Continued)

	Description	SI	PDelta	SRSS BLC	Fa	В	Fa B	. Fa	. B	Fa	B F	- a E	3	Fa	В	Fa	В	Fa	В	Fa	В	Fa
74	(0.9-0.2Sds) + 1.0E AZI .	.Yes	Y	DL	.864	ELZ	.866 E	5														

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	N1	max	387.326	17	494.9	27	874.761	2	791.561	14	225.94	17	378.598	11
2		min	-387.326	23	104.658	69	-874.761	20	-939.92	8	-225.94	23	-378.598	5
3	N5	max	341.491	5	413.672	33	752.152	14	243.481	14	199.203	5	55.804	11
4		min	-341.491	11	64.638	63	-752.152	8	-335.137	8	-199.203	11	-55.804	5
5	N7	max	151.901	5	216.701	27	171.211	2	223.617	14	88.609	5	219.479	11
6		min	-151.901	11	59.782	69	-171.211	20	-308.362	8	-88.609	11	-219.479	5
7	N11	max	219.331	17	305.251	33	258.87	14	301.107	20	127.943	17	293.038	17
8		min	-219.331	23	89.639	63	-258.87	8	-428.175	2	-127.943	23	-293.038	23
9	Totals:	max	1100.05	17	1430.524	33	2056.994	2						
10		min	-1100.05	23	318.717	63	-2056.994	8						

Envelope AISC 14th(360-10): LRFD Steel Code Checks

	Member Shape	Code Check	Loc[in]	LC	Shear C	.Loc [Dir L	C phi*Pnc	.phi*Pnt.	phi*Mn y-y	phi*Mn	. Cb	Eqn
1	M2 PIPE	.450	12.5	2	.089	12.5	2	<u>9836.597</u>	32130	1871.625	<mark>;</mark> 1871.625	1	H1
2	M5 PIPE	.191	107.5	8	.025	107.5	8	3 9836.597	32130	1871.625	<mark>5</mark> 1871.625	1	H1

			PROJECT: DO) MACR(O UPGRADE
	2 C		SITE NAME: EE		SON WITCH
<form></form>			SITE CASCADE: CT	03XC16	2
	SDr		SITE ADDRESS: 6 N ES	/AIN STI SEX, CT	REET 06426
STE NORMATION NORTHERNOUNCLUMBRATION STE NORMATION NORMATION NORMATION STE NORMATION NORMATION NORMATION NORMATI			SITE TYPE: WA		NK
STE INFORMATION AREA MAP PROJECT DESCRIPTION DAMANG STRUCTS OWNER:			MARKET: NO	RTHERI	
SITE INFORMATION AREA MAP PROJECT DESCRIPTION DRAWN STRUTCHE OWNER: best owners, Lid best ow					
STRUCTURE OWNER: Merror METRORS, LLG BERX, CT 0468 FUNCTION DEALUMING LATINDE (MADB3): 1/ 4 31: 5165007 STRUCTURE CONTROL (STRUCTURE) SHEET NO. SHEET NO. LONGULE (MADB3): 1/ 4 31: 5165007 SHEET NO. SHEET NO. SHEET NO. LONGULE (MADB3): 1/ 4 31: 5165007 SHEET NO. SHEET NO. SHEET NO. LONGULE (MADB3): 1/ 4 31: 5165007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 56: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 56: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 56: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 56: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 56: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 56: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 56: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 52: 50007 SHEET NO. SHEET NO. SHEET NO. COUNTY: 1/ 50: 50007 S	SITE INFORMATION				
		ODED MAP	PROJECT DESCRIPTION		DRAWIN
	STRUCTURE OWNER:		SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED	SHEET NO	EUCE
Hessex to besex Line Line Line Line Line Line Line Line	MACBETH VENTURES, LLC 6 RAILROAD AVE	Canileid Woods		T-1	
	ESSEX, CT 06426		REMOVE (6) EXISTING PANEL ANTENNAS	1-1	TILE SHEET & PROJECT
	LATITUDE (NAD83):	NO. TOMAR	INSTALL (3) PANEL ANTENNAS	SP-1	SPRINT SPECIFICATIONS
	41° 21' 4.608" N 41.35128000°		INSTALL (9) RRH'S NEAR ANTENNAS	SP-2 SP-3	SPRINT SPECIFICATIONS
		Inde Cove	· RELOCATE (3) RRH'S TO WATER TANK		0000 0141
	LONGITUDE (NAD83): 72' 24' 22.284" W	Natural Mra Preserve	INSTALL (24) JUMPER CABLES	A-1 A-2	TOWER ELEVATION
COUNTY ESSEX COUNTY ZONING_UNISDICTION: CONNECTOURS TRING COUNCIL ZONING_UNISDICTION: CONNECTOURS TRING COUNCIL ZONING_UNISDICTION: COUNTY ZONING: COUNTY RECORCOUND	-72.40619000*	A STANCE	· REMOVE (6) EXISTING COAX CABLE	A-3	ANTENNA LAYOUT & MOUN
	COUNTY:	A A A A A A A A A A A A A A A A A A A	INSTALL (4) HYBRID CABLES	A-5	CIVIL DETAILS
	ESSEX COUNTY		 INSTALL 2.5 EQUIPMENT INSIDE EXISTING N.V. MMBS CABINET 	A-6	PLUMBING DIAGRAM
	ZONING JURISDICTION:	Children and the second		E-1	ELECTRICAL & GROUNDING
ZONING_DISTRICT: CNL POWER_COMPANY: NNO PHONE: (800) 642-4272 AXY PROVIDER: VENZOM PHONE: (800) 670-4645 PROJECT_MANAGER: NROGON THE COMPANY: VENZOM PHONE: (800) 670-4645 PROJECT_MANAGER: NROGON THE COMPANY: NROGON THE COMPANY: PROVIDER: VENZOM PHONE: (800) 670-4645 PROJECT_MANAGER: NROGON THE COMPANY: PROVIDER: VENZOM PHONE: (800) 670-4645 PROJECT_MANAGER: NROGON THE COMPANY: PROVIDER:	CONNECTICUT SITING COUNCIL		THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN	E2	ELECTRICAL & GROUNDING
	ZONING DISTRICT:		SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT INFINIGY HAS INCORPORATED THIS SCOPE OF WORK PROVIDED BY SPRINT	!	
POWER COMPANY: NIMO PHONE: (600) 642-4272 AAV PROVIDER: VERIZON PROVE: (600) 570-6464 PROJECT MANAGER: ARIOSMITH DEVELOPMENT TERR BURKHOLDER @ARROSMITHDEVELOPMENT.COM (315)719-2828 TBURKHOLDER@ARROSMITHDEVELOPMENT.COM	CML	anna (N)	PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL	ii	
NHO PHONE: (800) 642-4272 AAV PROVIDER: VERIZOM PPROME: (800) 670-6464 PROJECT MANAGER: AROSMIT PREVEDENMENT TERRI BURKHOLDER BURKHOLDERGARIOSMITHDEVELOPMENT.COM TERRI BURKHOLDERGARIOSMITHDEVELOPMENT.COM	POWER COMPANY:	Interference Control of Control o	ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUN	т	
AL WORK SHALL BE PERFORMED AND ANTERIALS INSTALL IN COLLINING VERIZION PHONE: (300) 870–6464 PROJECT MANAGER: ARGOMITH DEVELOPMENT TERRI BURKHOLDER BURKHOLDER TERRI BURKHOLDER BAROSMITHDEVELOPMENT.COM CENTERBROOK @ G G G G G G G G G G G G G G G G G G	NIMO PHONE: (800) 642-4272		APPLICABLE CODES		
A V PROVIDER: VERIZON PHONE: (800) 870-6464 PROLECT MANAGER: ARCOMIT DEFLOPMENT TERRI BURKHOLDER@AIROSMITHDEVELOPMENT.COM TBURKHOLDER TBURK			ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING		
PHONE: (800) 870-6464 PROJECT MANAGER: AROSMITH DEVELOPMENT.COM UTERNATIONAL RECENT BUILDING CODE (2015 IBC) TBURKHOLDER@AROSMITH DEVELOPMENT.COM UTERNATIONAL RECENT BUILDING CODE (2015 IBC) UTERNATIONAL RECENT BUILDING CODE	AAV PROVIDER: VERIZON		CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK		
PROJECT MANAGER: AIROSMITH DEVELOPMENT TERRI BURKHOLDER@AIROSMITHDEVELOPMENT.COM (319)719-2328 TBURKHOLDER@AIROSMITHDEVELOPMENT.COM (319)719-2328 TBURKHOLDER@AIROSMITHDEVELOPMENT.COM (319)719-2328 (319)719-23	PHONE: (800) 870-6464	E Essex Town	1. INTERNATIONAL BUILDING CODE (2015 IBC)		
CENTERBROOK IN COLOR BUILDING CODE OF LATEST EDITION (313)719-2928 TBURKHOLDERGAIROSMITHDEVELOPMENT.COM	PROJECT MANAGER:		2. TA-222-G OR LATEST EDITION 3. NFPA 780 - LIGHTNING PROTECTION CODE		
CENTERBROOK BEAR SMITH DEVELOPMENT.COM	TERRI BURKHOLDER		4. 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION 5. ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES		
CITY/COUNTY ORDINANCES	TBURKHOLDER CAIROSMITHDEVELOPMENT.COM		6. NY BUILDING CODE		
the second secon		ester the second	7. LOCAL BUILDING CODE 8. CITY/COUNTY ORDINANCES		
Know what's below. Call before you dig.					
Know what's below. Call before you dig.					
know what's below. Call before you dig.		andrew	e con		
Know what's below. Call before you dig.		Hourse Hourse	1110		
Know what's below. Call before you dig.					
WWW.coll811.com			Know what's below.		
			Vali before you dig. www.coil811.com		

HAZEL		Sprin	t	V	
		FROM ZERO TO the solution 1033 Watervilet Shaker Rd Phone: 518-690-0700 F WWW.infing; JOB NUMBER: 52	INF INF I Alban ax: 518 7.com 6-104	Y INI enc y, NY -690-	GY Iless (122)
CUT		AIROS SALANCER 32 CLINTON ST SARATOGA SPRINGS, OFFICE#. (618) 309- ENGINEERING LICENSE:	Y 12868 3740	ME	H
G INDEX		Stor S. STE		•	
TITLE	REV	EST PLASTO	de	S	
DATA	0	Feel An	18 *	1111	
		APR 497 20	in a	Ξ	a
	0	TOT CENSE?	1		
	0	MASSIONAL EN	Sin		
	0	Whit has period a sal	erte.		
NTING DETAILS	0	DRAWING NOTICE:			
DETAILS	0	THESE DOCUMENTS ARE CONF	DENTIAL	AND	ARE
	0	THE SOLE PROPERTY OF SPRINT REPRODUCED, DISSEMINATED (AND MA	Y NO	T BE
DI ANI		WITHOUT THE EXPRESS WRIT SPRINT.	TEN CON	SENT	OF
DETAILS	0	REVISIONS:			_
		DESCRIPTION	DATE	BY	REV.
				-	
		ISSUED FOR PERMIT	1/25/18	JOL	0
		SITE NAME:			
		EE DICKEN WITCHHA	SON ZEL		
		CT03XC1	62		
		6 MAIN STR ESSEX, CT 0	EET 5426		
	-	SHEET DESCRIPTION: TITLE SHEI & PROJECT D	ET ATA		
				-	Ē

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
- 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
- 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
- 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
- NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
- 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
- 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
- 7. AMERICAN CONCRETE INSTITUTE (ACI)
- 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
- 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
- 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
- 11. PORTLAND CEMENT ASSOCIATION (PCA)
- 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
- 13. BRICK INDUSTRY ASSOCIATION (BIA)
- 14. AMERICAN WELDING SOCIETY (AWS)
- 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
- 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
- 17. DOOR AND HARDWARE INSTITUTE (DHI)
- 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
- 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.
- 1.5 DEFINITIONS:
- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS,
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND 'A&E'. THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK, NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS, AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF 'AS-BUILT DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
- C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUTS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193

- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HAVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICIAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIMDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS, DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1 ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO STEE.

3.2 DELIVERABLES:

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 - CELL SITE CONSTRUCTION CO. PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:



CONTINUE FROM SP-1

- 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
- PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
- MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
- 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
- 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
- 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
- 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
- 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
- 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
- 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS
- 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS
- 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
- 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND
- 19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
- 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."
- 3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:
 - CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
- 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTTFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
- CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.
- 3.3 DELIVERABLES:
- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED
- 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
- 2. PROJECT PROGRESS REPORTS.
- 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

- 5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
- 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

- PART 1 GENERAL
- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS:
- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 - 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 - 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 - 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY,
- ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
- 5. CHEMICAL GROUNDING DESIGN
- D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO STRE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE
- COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE 1. ACCEPTANCE STANDARDS.
- AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE
- AZIMUTH, DOWNTILT, AGL UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS 1.
- 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMEN
- 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

- 5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
- 6. LIEN WAIVERS
- 7. FINAL PAYMENT APPLICATION
 - 8. REQUIRED FINAL CONSTRUCTION PHOTOS
 - 9 . CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT
 - 10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).
 - 1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE
 - 1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE
 - PART 2 PRODUCTS (NOT USED)
 - PART 3 EXECUTION
 - 3.1 REQUIREMENTS FOR TESTING:
 - A. THIRD PARTY TESTING AGENCY:
 - WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITION
 - 2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 - 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
 - 4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
 - 3.2 REQUIRED TESTS.
 - A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE
 - CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 - ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT
 - 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING
 - TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 - 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 - 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN
 - 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS
 - 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 - 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

OR SPRINT REPRESENTATIVE.

EXISTING FACILITIES.

3.3 REQUIRED INSPECTIONS



CONTINUE FROM SP-2

- VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
- 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
- 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF
- 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY DIDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
- 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
- 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
- 3. SITE RESISTANCE TO EARTH TEST
- 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
- 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
- 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING:
- TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
- 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD
- 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDULT STUB OUTS: PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
- 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAR REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S): PHOTOS OF EACH SECTOR OF ANTENNAS: ONE PHOTOSGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
- 6. SITE LAYOUT PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
- FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
- 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN
- 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

- PART 1 GENERAL
- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- PART 2 PRODUCTS (NOT USED)
- PART 3 EXECUTION
- 3.1 WEEKLY REPORTS:
- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL CONFLICTION DATE.
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
- 1. 1SHELTER AND TOWER OVERVIEW.
- 2. TOWER FOUNDATION(S) FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
- 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
- 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
- 5. PHOTOS OF TOWER SECTION STACKING.
- 6. CONCRETE TESTING / SAMPLES.
- 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
- 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
- 9. SHELTER FOUNDATION -- FORMS AND STEEL BEFORE POURING.
- 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
- 11. COAX CABLE ENTRY INTO SHELTER.
- 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
- 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
- 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
- 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
- 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
- 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
- 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
- 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL
- 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 25. ALL BTS GROUND CONNECTIONS.
- 26. ALL GROUND TEST WELLS.
- 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
- 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
- 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 - 30. GPS ANTENNAS.
- 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
- 32. DOGHOUSE/CABLE EXIT FROM ROOF.
- 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
- 34. MASTER BUS BAR.
- 35. TELCO BOARD AND NIU.
- 36. ELECTRICAL DISTRIBUTION WALL,
- 37. CABLE ENTRY WITH SURGE SUPPRESSION.
- 38. ENTRANCE TO EQUIPMENT ROOM.
- 39. COAX WEATHERPROOFING-TOP AND BOTTOM OF TOWER.
- 40. COAX GROUNDING -- TOP AND BOTTOM OF TOWER.
- 41. ANTENNA AND MAST GROUNDING.
- 42. LANDSCAPING WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.





PLANS PREPARED FOR











-





