



Goodmar
Network Knowledge

EM-SPRINT-052-121213

December 13, 2012

Linda Roberts
Executive Director
Connecticut Siting Counsel
Ten Franklin Square
New Britain, CT 06051
Linda Roberts, Executive Director

ORIGINAL

Re: Notice of Exempt Modification – Antenna Swap
319-321 New Britain Avenue, Farmington, Connecticut

RECEIVED
DEC 13 2012
CONNECTICUT
SITING COUNCIL

Dear Ms. Roberts:

Sprint is planning to consolidate multiple network technologies into one seamless network with the goal of increasing efficiency and enhancing network coverage, call quality and data speeds for customers across Connecticut. Pursuant §16-50j-73 to of the Regulations of Connecticut State Agencies (RCSA), please accept this letter and attachments as notification of Sprint's intent to make exempt modifications, under RCSA §16-50j-72(b)(2), to its existing telecommunications facility at 319-321 New Britain Avenue in Farmington, Connecticut. In accordance with RCSA §16-50j-73, a copy of this letter is sent to Jeffrey J. Hogan, Town Counsel Chair for the Town of Farmington.

Sprint currently maintains eleven (11) antennas at 170 feet on the existing 190 foot tower at the address referenced above. Sprint intends to replace its existing six (6) CDMA antennas with three (3) Multimodal antennas at their same current height of 170 feet. Sprint will be replacing its existing six (6) lines of coaxial cable with three (3) smaller lines of Hybriflex cable and installing six (6) RRH's. Sprint will also be swapping three (3) existing ground cabinets with three new cabinets and adding one (1) fiber junction box. This work will result in a net reduction of antennas, from eleven (11) to eight (8), and will not increase the height of the tower or the size compound. Please find included with this letter compound, elevation and overhead drawings which depict Sprint's proposed modifications.

Sprint's planned modifications fall squarely within the activities permitted in RCSA §16-50j-72(b)(2) in that:

1. The proposed modifications will not increase the existing tower height;
2. The proposed modifications will not extend the boundaries of the site by any dimension;

3. The proposed modifications will not increase the noise levels at the existing facility by six (6) decibels or more;
4. The proposed modifications will not increase the total radio frequency electromagnetic radiation power density to or above the standards adopted by the Federal Communications Commission. Please find included with this letter a Radio Frequency Emissions Analysis Report.

Also included with this letter is a Structural Assessment confirming that the foundation and tower are sufficient to support Sprint's proposed modifications.

For the foregoing reasons, Sprint respectfully submits that its proposed modifications to the existing tower located at the address referenced above constitute an exempt modification under RSCA §16-50j-72(b)(2).

Please do not hesitate to contact me at (214) 478-3516 or dtorres@goodmannetworks.com if you have any questions. Thank you for your consideration.

Respectfully,



David Torres
Goodman Networks

Attachments

Copy to:

Jeffrey J. Hogan, Town Counsel Chair, Town of Farmington



EBI Consulting

environmental | engineering | due diligence

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

Sprint Existing Facility

Site ID: CT33XC534

Unionville Police Department
319 - 321 New Britain Avenue
Farmington, CT 06032

October 29, 2012

October 29, 2012

Sprint

Attn: RF Engineering Manager

1 International Boulevard, Suite 800

Mahwah, NJ 07495

Re: Emissions Values for Site: **CT33XC534 – Unionville Police Department**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 319 - 321 New Britain Avenue, Farmington, CT, for the purpose of determining whether the emissions from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band is approximately 567 $\mu\text{W}/\text{cm}^2$, and the general population exposure limit for the PCS band is 1000 $\mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 319 - 321 New Britain Avenue, Farmington, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 CDMA Carriers (1900 MHz) were considered for each sector of the proposed installation.
- 2) 1 CDMA Carrier (850 MHz) was considered for each sector of the proposed installation
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The actual gain in this direction was used per the manufactures supplied specifications.
- 5) The antenna used in this modeling is the APXVSP18-C-A20. This is based on feedback from the carrier with regards to anticipated antenna selection. This antenna has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.

- 6) The antenna mounting height centerline of the proposed antennas is **170 feet** above ground level (AGL)
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT33XCS34 - Unionville Police Department
Site Address	319 - 321 New Britain Avenue, Farmington, CT, 06032
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBi)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	170	164	1/2 "	0.5	0	1386.9474	18.53866	1.85387%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	170	164	1/2 "	0.5	0	389.96892	5.212527	0.91932%

Sector total Power Density Value: 2.773%

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBi)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	170	164	1/2 "	0.5	0	1386.9474	18.53866	1.85387%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	170	164	1/2 "	0.5	0	389.96892	5.212527	0.91932%

Sector total Power Density Value: 2.773%

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBi)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	170	164	1/2 "	0.5	0	1386.9474	18.53866	1.85387%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	170	164	1/2 "	0.5	0	389.96892	5.212527	0.91932%

Sector total Power Density Value: 2.773%

Site Composite MPE %	
Carrier	MPE %
Sprint	8.320%
Town	2.190%
Emergency	8.030%
Public Works	35.670%
Cleanwire	0.630%
Pocket	3.470%
AT&T	17.150%
T-Mobile	3.150%
Total Site MPE %	78.810%



EBI Consulting

environmental | engineering | due diligence

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public exposure to RF Emissions.

The anticipated Maximum Composite contributions from the Sprint facility are **8.320% (2.773% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **78.610%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government

Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803



RAMAKER
& ASSOCIATES, INC.

UNIONVILLE/POLICE DEPT. (CT33XC534)

**PREPARED FOR:
SPRINT**

**PREPARED BY:
RAMAKER & ASSOCIATES, INC.
JOB NUMBER: 23009**

**STRUCTURAL ASSESSMENT
190-FOOT MONOPOLE TOWER**

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 ▲ Fax: 608-643-7999
www.ramaker.com

MATCHLINE SEE SHEET 0209

STRUCTURAL ASSESSMENT

SITE: Unionville/Police Dept. (CT33XC534)
319-321 New Britain Avenue
Farmington, Hartford County, Connecticut 06032


PREPARED FOR: Alcatel-Lucent
600 Mountain Avenue
Murray Hill, New Jersey 07974

CONTACT PERSON: Alcatel-Lucent
John Szilezy
Site Acquisition Manager
john.szilezy@alcatel-lucent.com

PREPARED BY: Ramaker & Associates, Inc.
1120 Dallas Street
Sauk City, Wisconsin 53583
Telephone: (608) 643-4100
Facsimile: (608) 643-7999


RAMAKER JOB NUMBER: 23009

DATE OF REPORT ISSUANCE: November 16, 2012



Thomas E. Moore
Structural Engineer

11/16/12
Date



James R. Skowronski, P.E.
Supervising Engineer

11/16/12
Date




TABLE OF CONTENTS

EXECUTIVE SUMMARY3

INTRODUCTION4

 2.1 PROJECT INFORMATION

 2.2 PURPOSE OF REPORT

 2.3 SCOPE OF SERVICES

MODEL DEVELOPMENT5

 3.1 INTRODUCTION

 3.2 EXISTING STRUCTURE INFORMATION

 3.3 EXISTING TOWER LOADS

 3.4 PROPOSED TOWER LOADS

 3.5 WIND AND ICE LOAD

ANALYSIS RESULTS7

 4.1 ANALYSIS RESULTS

 4.2 BASE REACTIONS

LIMITATIONS8

REFERENCES9

LIST OF APPENDICES

A. TOWER FIGURES

B. TOWER CALCULATIONS

SECTION 1

EXECUTIVE SUMMARY

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (Ramaker & Associates) for Alcatel-Lucent (ALU) on behalf of Sprint, who intends to install additional equipment on an existing 190-foot monopole tower. The tower site is located in Farmington, Hartford County, Connecticut.

ALU is proposing to install three (3) RFS APXVSPP18-C-A20 3G panel antennas on the existing Platform at a centerline elevation of 170 feet AGL. ALU is also proposing to install three (3) ALU 1900 MHz RRH units and three (3) ALU 800 MHz RRH units on a new collar mount directly below the existing Platform. The proposed equipment shall be fed with three (3) 1-1/4 inch fiber/power hybrid cables that were assumed to be routed up the inside of the tower. The six (6) existing CDMA panel antennas and their corresponding coax at 170 feet AGL shall remain during the interim phase, and then shall be removed for the final antenna layout.

Results of our analysis show that the tower will be stressed to a maximum of 93.3 percent of capacity under proposed loading conditions. Proposed model foundation reactions were found to be less than the modified original design reactions. The foundation was also analyzed under proposed loading conditions and determined to provide adequate strength.

In summary, the tower will pass the TIA-222-G code requirements under proposed loading conditions.

SECTION 2

INTRODUCTION

2.1 PROJECT INFORMATION

This report summarizes the structural analysis conducted by Ramaker & Associates, Inc. (Ramaker & Associates) for ALU, who intends to install additional equipment on an existing tower.

2.2 PURPOSE OF REPORT

The analysis activities of this report were conducted for the purposes of creating and analyzing a model of the subject structure under the required loading conditions. Base reactions from the resulting model were also determined for tower foundation and support development. Recommendations regarding the analysis results, loading configuration, and structural modifications are also provided.

2.3 SCOPE OF SERVICES

Ramaker & Associates developed a finite element model (FEM) of the tower, using tnxTower, for member force, joint deflection, and structure reaction determinations. Subsequently, this report was drafted to provide our engineering recommendations. All information contained herein is valid only for the described structure configuration and loading conditions. Ramaker & Associates reserves the right to modify our recommendations should alterations to the tower loading occur.

SECTION 3

MODEL DEVELOPMENT

3.1 INTRODUCTION

Ramaker & Associates, Inc. developed a FEM of the tower superstructure using the below referenced tower analysis, and site photos. Required static loads consisting of the antenna configuration, wind forces, ice loads, and linear appurtenances (including cable loads) were then applied to the FEM. As a result, all member forces, allowable capacities, and base reactions were computed. Additionally, potentially overstressed members were identified.

3.2 EXISTING STRUCTURE INFORMATION

Tower information was gathered from the structural analysis by Bay State Design, site ID CT-HFD0073A, dated March 29, 2010. The structural analysis by Malouf Engineering, project ID CT00937M-07V0, and dated September 27, 2007, was also used.

3.3 EXISTING TOWER LOADS

Ramaker & Associates understands that the existing antenna, cable, and appurtenance configurations are as shown in the following chart:

Elevation	Appurtenance	Mount	Coax
190	(2) 10' Omni	(3) 5' Standoff	(4) 7/8
	(2) Kathrein Scala PR-850		
185	3' Yagi	5' Standoff	(2) 7/8
180	10' Omni	5' Standoff	(1) 7/8
170	** (6) Decibel DB980F90E-M **	15' Low Profile Platform	** (6) 1-5/8 **
	(3) Argus LLPX310R-V1		(3) 5/16
	(3) Samsung RRH-P4		
160	(6) RFS APX16DWV-16DWVS-C	13' Low Profile Platform	(12) 1-1/4 Exterior
	(6) TMAs		
	(6) Vacant Pipe Mounts		—
150	(3) Kathrein Scala 800 10121	(3) 3' Standoff	(6) 1-5/8
	(6) Powerwave LGP214nn		
140	(3) Kathrein Scala 712 213V01	(3) 2' Standoff	(6) 1-5/8
113	(3) 10' Omni	(3) 5' Standoff	(3) 1/2
90	(3) 18' Omni	(3) 5' Standoff	(3) 1/2

UNIONVILLE/POLICE DEPT. (CT33XC534)

The six (6) existing CDMA panel antennas and their corresponding coax at 170 feet AGL shall remain during the interim phase, and then shall be removed for the final antenna layout.

3.4 PROPOSED TOWER LOADS

Ramaker & Associates understands that the total antenna loading for the tower will consist of the aforementioned existing antennas and the following proposed antennas:

Elevation	Appurtenance	Mount	Coax
170	(3) RFS APXVSP18-C-A20	Existing 15' Low Profile Platform	(3) 1-1/4 Fiber/Power
	(3) ALU 1900MHz RRH	New Collar Mount	
	(3) ALU 800MHz RRH		

The proposed fiber/power hybrid cables were assumed to be routed up the inside of the tower.

3.5 WIND AND ICE LOAD

Wind forces used in model development are in compliance with the TIA-222-G Standard. These guidelines call for an analysis to be performed, which assumes a basic wind speed (fastest mile) of 98 miles-per-hour (mph) without ice in Hartford County, per the ATC website. The tower is also analyzed for a 50 mph basic wind speed with 1-inch of radial ice. The tower was analyzed using the following parameters: Structure Class II, Topographic Category 1, and Exposure Category C.

SECTION 4

ANALYSIS RESULTS

4.1 ANALYSIS RESULTS

The tower superstructure was analyzed with the combined existing and proposed antenna loading with and without radial ice. The computed maximum tower member stress capacities are as follows:

Component Type	Percent Capacity
Section 1	14.8
Section 2	43.6
Section 3	55.2
Section 4	68.9
Section 5	80.4
Section 6	93.3
Base Plate	74.2
Anchor Bolts	81.7
RATING	93.3

4.2 BASE REACTIONS

The computed maximum reactions under the corresponding maximum moment are as follows:

Load Type	Original Design	Original Design*1.35	Proposed Model
Total Axial (k)	46.1	62.24	56.78
Total Shear (k)	36.7	49.55	44.35
Total Moment (k-ft)	4673.6	6309.36	5352.35

The TIA-222-G code in Section 15.5.1 specifies to multiply original ASD reactions by 1.35 when comparing them with reactions determined using the TIA-222-G code. Proposed model foundation reactions were found to be less than the modified original design reactions. The foundation was also analyzed under proposed loading conditions and determined to provide adequate strength.

SECTION 5

LIMITATIONS

The recommendations contained within this report were developed using general project information provided by the owner, tower manufacturer, general field observations, reference information and laboratory testing data, as applicable. All recommendations pertain only to the proposed tower construction, location, and loading as described in this report. Ramaker & Associates assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

1. Missing, corroding, and/or deteriorating members
2. Improper manufacturing and/or construction
3. Improper maintenance

Ramaker & Associates assumes no responsibility for modifications completed prior to or hereafter in which Ramaker & Associates was not directly involved. These modifications include but are not limited to the following:

1. Replacing or strengthening bracing members
2. Reinforcing or extending vertical members
3. Installing or removing antenna mounting gates or side arms
4. Changing loading configurations

Furthermore, Ramaker & Associates hereby states that this document represents the entire report and that it assumes no liability for any factual changes that may occur after the date of this report. All representations, recommendations and conclusions are based on the information contained and set forth herein. If you are aware of any information contrary to that contained herein, or if you are aware of any defects arising from the original design, material, fabrication and erection deficiencies, you should disregard this report and immediately contact Ramaker & Associates. Ramaker & Associates isn't liable for any representation, recommendation, or conclusion not expressly stated herein.

The tower owner is responsible for verifying that the existing loading on the tower is consistent with the loading applied to the tower within this report.


SECTION 6

REFERENCES

1. 2009 International Building Code.
2. Telecommunications Industries Association, Structural Standard for Antenna Supporting Structures and Antennas, TIA Standard ANSI/TIA-222-G 2005, Washington, D.C.

APPENDIX A
TOWER FIGURES

Section	Length (ft)	Number of Sides	Thickness (in)	Socket Length (ft)	Top Dia (in)	Bot Dia (in)	Grade	Weight (lb)
1	25.75	18	0.2500	2.92	19.5625	26.0000		1568.6
2	37.50	18	0.3125	3.83	24.7700	34.0052		3680.0
3	37.50	18	0.3750	4.67	32.4370	41.0625	A572-65	5524.7
4	37.50	18	0.3750	5.50	39.2383	49.0052		6644.3
5	37.50	18	0.3750	6.25	46.8227	56.0104		7752.3
6	37.50	18	0.3750	53.7291	62.0781			8737.5
								33905.3



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod 2"x15"	197.5	1900MHz 4x40W RRH (Sprint)	170
5' Standoff (Farmington)	190	(2) APX16DWV-16DWVS-C w/Mount Pipe (T-Mobile)	160
5' Standoff (Farmington)	190	(2) APX16DWV-16DWVS-C w/Mount Pipe (T-Mobile)	160
5' Standoff (Farmington)	190	(2) TMA (T-Mobile)	160
6' x 3" Pipe Mount (Farmington)	190	(2) TMA (T-Mobile)	160
10' Omni (Farmington)	190	(2) TMA (T-Mobile)	160
10' Omni (Farmington)	190	PiROD 13' Low Profile Platform (T-Mobile)	160
PR-850 (Farmington)	190	(2) 6' x 3" Pipe Mount (T-Mobile)	160
PR-850 (Farmington)	185	(2) 6' x 3" Pipe Mount (T-Mobile)	160
5' Standoff (Farmington)	185	(2) APX16DWV-16DWVS-C w/Mount Pipe (T-Mobile)	160
3' Yagi (Farmington)	180	VHLP2 (Clearwire)	174
5' Standoff (Farmington)	180	VHLP2 (Clearwire)	174
10' Omni (Farmington)	174	1900MHz 4x40W RRH (Sprint)	170
VHLP2.5 (Clearwire)	170	1900MHz 4x40W RRH (Sprint)	170
800MHz 2x50W RRH (Sprint)	170	800MHz 2x50W RRH (Sprint)	170
800MHz 2x50W RRH (Sprint)	170	800MHz 2x50W RRH (Sprint)	170
800MHz 2x50W RRH (Sprint)	170	(2) DB980F90E-M w/Mount Pipe (Sprint)	170
(2) DB980F90E-M w/Mount Pipe (Sprint)	170	(2) DB980F90E-M w/Mount Pipe (Sprint)	170
(2) DB980F90E-M w/Mount Pipe (Sprint)	170	LLPX310R-V1 w/Mount Pipe (Clearwire)	170
LLPX310R-V1 w/Mount Pipe (Clearwire)	170	LLPX310R-V1 w/Mount Pipe (Clearwire)	170
LLPX310R-V1 w/Mount Pipe (Clearwire)	170	LLPX310R-V1 w/Mount Pipe (Clearwire)	170
RRH-P4 (Clearwire)	170	RRH-P4 (Clearwire)	170
RRH-P4 (Clearwire)	170	RRH-P4 (Clearwire)	170
PIROD 15' Low Profile Platform (Sprint)	170	APXVSP18-C-A20 w/Mount Pipe (Sprint)	170
APXVSP18-C-A20 w/Mount Pipe (Sprint)	170	APXVSP18-C-A20 w/Mount Pipe (Sprint)	170
APXVSP18-C-A20 w/Mount Pipe (Sprint)	170	APXVSP18-C-A20 w/Mount Pipe (Sprint)	170


MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for Exposure C to the TIA-222-G Standard.
3. Tower designed for a 98 mph basic wind in accordance with the TIA-222-G Standard.
4. Tower is also designed for a 50 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Structure Class II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 93.3%

ALL REACTIONS
ARE FACTORED




 RAMAKER & ASSOCIATES, INC. Consulting Engineers	Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999		Job: CT33XC534 Project: 23009 Client: Sprint Code: TIA-222-G Path: \\23000\23009\Structural\Risk\23009.eri	
	Drawn by: tmoore Date: 11/16/12		App'd: NT Scale: NT	
	Dwg No. E			

TIA-222-G - 98 mph/50 mph 1.0000 in Ice Exposure C

Leg Capacity —

Leg Compression (lb)



Ramaker & Associates, Inc.

1120 Dallas Street
Sauk City, WI 53583
Phone: (608) 643-4100
FAX: (608) 643-7999

Job: **CT33XC534**

Project: **23009**

Client: **Sprint**

Drawn by: **tmoore**

App'd:

Code: **TIA-222-G**

Date: **11/16/12**

Scale: **NT**

Path: **J:\23000\23009\Structural\Risk\23009.eri**



Dwg No. **E**


Vx

Vz

Mx

Mz





Ramaker & Associates, Inc.

1120 Dallas Street
Sauk City, WI 53583
Phone: (608) 643-4100
FAX: (608) 643-7999

Job: CT33XC534

Project: 23009

Client: Sprint

Drawn by: tmoore

App'd:

Code: TIA-222-G

Date: 11/16/12

Scale: NT

Path: I:\23000\23009\Structural\Risal\23009.eri

Dwg No. E

Reading Distribution Chart

0' - 190'31/32"

Round

Flat

App In Face

App Out Face


Truss Leg

Face A

Face B

Face C

Elevation (ft)



Ramaker & Associates, Inc.

1120 Dallas Street
Sauk City, WI 53583
Phone: (608) 643-4100
FAX: (608) 643-7999

Job: **CT33XC534**

Project: **23009**

Client: **Sprint**

Drawn by: **tmoore**

App'd:

Code: **TIA-222-G**

Date: **11/16/12**

Scale: **NT**

Path: **I:\23000\23009\Structural\RIse\23009.eri**


Dwg No. **E**

Stress Distribution Chart


0' - 190'31/32"

■ > 100% ■ 90%-100% ■ 75%-90% ■ 50%-75% ■ < 50% Overstress


Face A



Face B



Face C



Elevation (ft)



Ramaker & Associates, Inc.

1120 Dallas Street
Sauk City, WI 53583
Phone: (608) 643-4100
FAX: (608) 643-7999

Job: **CT33XC534**

Project: **23009**

Client: **Sprint** Drawn by: **tmoore** App'd:

Code: **TIA-222-G** Date: **11/16/12** Scale: **NT**

Path: **I:\23000\23009\Structural\Risal23009.eri** Dwg No. **E**

APPENDIX B

TOWER CALCULATIONS

Search Results

Latitude: 41.7498

Longitude: -72.8727

**ASCE 7-10 Wind Speeds
(3-sec peak gust MPH*):**

Risk Category I: 110

Risk Category II: 120

Risk Category III-IV: 129

MRI 10 Year: 76**


MRI 25 Year: 86**

MRI 50 Year: 91**

MRI 100 Year: 98**

ASCE 7-05: 98

ASCE 7-93: 79



*MPH(Miles per hour)

**MRI Mean Recurrence Interval (years)

Users should consult with local building officials
to determine if there are community-specific wind speed
requirements that govern.

WIND SPEED WEB SITE DISCLAIMER:

While the information presented on this web site is believed to be correct, ATC assumes no responsibility or liability for its accuracy. The material presented in the wind speed report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the wind speed report provided by this web site. Users of the information from this web site assume all liability arising from such use. Use of the output of this web site does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site(s) described by latitude/longitude location in the wind speed report.

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	1 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Tower Input Data

There is a pole section.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Tower is located in Hartford County, Connecticut.

Basic wind speed of 98 mph.

Structure Class II.

Exposure Category C.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.

Local bending stresses due to climbing loads, feedline supports, and appurtenance mounts are not considered.

Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	190.08-164.33	25.75	2.92	18	19.5625	26.0000	0.2500	1.0000	A572-65 (65 ksi)
L2	164.33-129.75	37.50	3.83	18	24.7700	34.0052	0.3125	1.2500	A572-65 (65 ksi)
L3	129.75-96.08	37.50	4.67	18	32.4370	41.0625	0.3750	1.5000	A572-65 (65 ksi)
L4	96.08-63.25	37.50	5.50	18	39.2383	49.0052	0.3750	1.5000	A572-65 (65 ksi)
L5	63.25-31.25	37.50	6.25	18	46.8227	56.0104	0.3750	1.5000	A572-65 (65 ksi)
L6	31.25-0.00	37.50		18	53.7291	62.0781	0.3750	1.5000	A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	I/Q in ²	w in	w/t
L1	19.8643	15.3245	722.1042	6.8559	9.9377	72.6627	1445.1586	7.6637	3.0030	12.012
	26.4011	20.4326	1711.6544	9.1412	13.2080	129.5922	3425.5610	10.2183	4.1360	16.544
L2	25.8823	24.2588	1833.2875	8.6824	12.5832	145.6937	3668.9873	12.1317	3.8095	12.19
	34.5298	33.4190	4792.9419	11.9609	17.2746	277.4553	9592.1904	16.7127	5.4349	17.392
L3	33.8319	38.1618	4956.1779	11.3820	16.4780	300.7757	9918.8773	19.0845	5.0489	13.464

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	2 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	I/Q in ²	w in	w/t
L4	41.6960	48.4283	10128.8154	14.4441	20.8597	485.5674	20270.9586	24.2188	6.5670	17.512
	41.0787	46.2571	8826.6493	13.7965	19.9331	442.8142	17664.9129	23.1329	6.2459	16.656
	49.7612	57.8821	17293.9433	17.2637	24.8946	694.6853	34610.6424	28.9466	7.9649	21.24
L5	48.9134	55.2844	15068.4724	16.4889	23.7859	633.5031	30156.7722	27.6475	7.5808	20.215
	56.8745	66.2201	25895.8205	19.7506	28.4533	910.1169	51825.7153	33.1163	9.1978	24.528
L6	55.9710	63.5048	22839.1491	18.9407	27.2944	836.7705	45708.3505	31.7584	8.7963	23.457
	63.0358	73.4421	35326.2160	21.9046	31.5357	1120.1981	70698.9151	36.7281	10.2658	27.375

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A _f	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
ft	ft ²	in						
L1 190.08-164.33				1	1	1		
L2 164.33-129.75				1	1	1		
L3 129.75-96.08				1	1	1		
L4 96.08-63.25				1	1	1		
L5 63.25-31.25				1	1	1		
L6 31.25-0.00				1	1	1		

Monopole Base Plate Data

Base Plate Data

Base plate is square	
Base plate is grouted	
Anchor bolt grade	A687
Anchor bolt size	1.2500 in
Number of bolts	44
Embedment length	51.5000 in
f _c	4 ksi
Grout space	2.0000 in
Base plate grade	A572-50
Base plate thickness	1.5000 in
Bolt circle diameter	68.0000 in
Outer diameter	74.0000 in
Inner diameter	62.0000 in
Base plate type	Stiffened Plate
Bolts per stiffener	1
Stiffener thickness	0.5000 in
Stiffener height	10.0000 in

Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number	Number Per Row	Clear Spacing in	Width or Diameter in	Perimeter in	Weight plf

Feed Line/Linear Appurtenances - Entered As Area

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	3 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		$C_A A_A$ ft ² /ft	Weight plf
Climbing Ladder (Af)	C	No	CaAa (Out Of Face)	190.00 - 0.00	1	No Ice	0.30	7.90
						1/2" Ice	0.41	9.01
						1" Ice	0.52	10.46
7/8	A	No	Inside Pole	190.00 - 0.00	4	No Ice	0.00	0.54
						1/2" Ice	0.00	0.54
						1" Ice	0.00	0.54
7/8	A	No	Inside Pole	185.00 - 0.00	2	No Ice	0.00	0.54
						1/2" Ice	0.00	0.54
						1" Ice	0.00	0.54
7/8	A	No	Inside Pole	180.00 - 0.00	1	No Ice	0.00	0.54
						1/2" Ice	0.00	0.54
						1" Ice	0.00	0.54
1 1/4 (Sprint)	A	No	Inside Pole	170.00 - 0.00	3	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
1 5/8 (Sprint)	A	No	Inside Pole	170.00 - 0.00	6	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
5/16 (Clearwire)	A	No	Inside Pole	170.00 - 0.00	3	No Ice	0.00	0.09
						1/2" Ice	0.00	0.09
						1" Ice	0.00	0.09
1 1/4	A	No	CaAa (Out Of Face)	160.00 - 0.00	1	No Ice	0.16	0.66
						1/2" Ice	0.25	1.91
						1" Ice	0.35	3.78
1 1/4	A	No	CaAa (Out Of Face)	160.00 - 0.00	5	No Ice	0.00	0.66
						1/2" Ice	0.00	1.91
						1" Ice	0.00	3.78
1 1/4	B	No	CaAa (Out Of Face)	160.00 - 0.00	1	No Ice	0.16	0.66
						1/2" Ice	0.25	1.91
						1" Ice	0.35	3.78
1 1/4	B	No	CaAa (Out Of Face)	160.00 - 0.00	5	No Ice	0.00	0.66
						1/2" Ice	0.00	1.91
						1" Ice	0.00	3.78

1 5/8 (ATT)	A	No	Inside Pole	150.00 - 0.00	6	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
1 5/8	A	No	Inside Pole	140.00 - 0.00	6	No Ice	0.00	1.04
						1/2" Ice	0.00	1.04
						1" Ice	0.00	1.04
1/2	A	No	Inside Pole	113.00 - 0.00	3	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
						1" Ice	0.00	0.25
1/2	A	No	Inside Pole	90.00 - 0.00	3	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
						1" Ice	0.00	0.25

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A_R ft ²	A_F ft ²	$C_A A_A$ In Face ft ²	$C_A A_A$ Out Face ft ²	Weight lb
L1	190.08-164.33	A	0.000	0.000	0.000	0.000	134.37
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	7.701	202.79
L2	164.33-129.75	A	0.000	0.000	0.000	4.689	734.41
		B	0.000	0.000	0.000	4.689	119.79
		C	0.000	0.000	0.000	10.374	273.18

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	4 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Tower Section	Tower Elevation ft	Face	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
L3	129.75-96.08	A	0.000	0.000	0.000	5.219	979.36
		B	0.000	0.000	0.000	5.219	133.33
		C	0.000	0.000	0.000	10.101	265.99
L4	96.08-63.25	A	0.000	0.000	0.000	5.089	987.23
		B	0.000	0.000	0.000	5.089	130.01
		C	0.000	0.000	0.000	9.849	259.36
L5	63.25-31.25	A	0.000	0.000	0.000	4.960	966.72
		B	0.000	0.000	0.000	4.960	126.72
		C	0.000	0.000	0.000	9.600	252.80
L6	31.25-0.00	A	0.000	0.000	0.000	4.844	944.06
		B	0.000	0.000	0.000	4.844	123.75
		C	0.000	0.000	0.000	9.375	246.88

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A_R ft ²	A_F ft ²	C_{AA} In Face ft ²	C_{AA} Out Face ft ²	Weight lb
L1	190.08-164.33	A	2.365	0.000	0.000	0.000	0.000	134.37
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	21.193	426.01
L2	164.33-129.75	A	2.321	0.000	0.000	0.000	18.998	2920.28
		B		0.000	0.000	0.000	18.998	2305.67
		C		0.000	0.000	0.000	28.550	573.88
L3	129.75-96.08	A	2.261	0.000	0.000	0.000	20.850	3330.24
		B		0.000	0.000	0.000	20.850	2484.22
		C		0.000	0.000	0.000	27.469	549.85
L4	96.08-63.25	A	2.183	0.000	0.000	0.000	19.934	3169.92
		B		0.000	0.000	0.000	19.934	2312.69
		C		0.000	0.000	0.000	26.343	524.23
L5	63.25-31.25	A	2.073	0.000	0.000	0.000	18.933	2956.84
		B		0.000	0.000	0.000	18.933	2116.84
		C		0.000	0.000	0.000	25.126	496.04
L6	31.25-0.00	A	1.857	0.000	0.000	0.000	17.797	2696.05
		B		0.000	0.000	0.000	17.797	1875.73
		C		0.000	0.000	0.000	23.768	463.61

Feed Line Center of Pressure

Section	Elevation ft	CP_x in	CP_z in	CP_x Ice in	CP_z Ice in
L1	190.08-164.33	-0.3314	0.1913	-0.6457	0.3728
L2	164.33-129.75	-0.1689	0.0975	-0.1774	0.1024
L3	129.75-96.08	-0.1554	0.0897	-0.1416	0.0818
L4	96.08-63.25	-0.1597	0.0922	-0.1530	0.0883
L5	63.25-31.25	-0.1629	0.0941	-0.1619	0.0935
L6	31.25-0.00	-0.1652	0.0954	-0.1682	0.0971

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	5 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	K _a No Ice	K _a Ice
---------------	----------------------	-------------	-------------------------	-----------------------	--------------------

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _A A _A Front ft ²	C _A A _A Side ft ²	Weight lb
Lightning Rod 2"x15'	A	From Face	0.00 0.00 0.00	0.0000	197.50	No Ice 1/2" Ice 1" Ice	3.00 4.53 6.07	3.00 4.53 6.07	80.00 103.14 135.79
5' Standoff (Farmington)	A	From Face	2.50 0.00 0.00	0.0000	190.00	No Ice 1/2" Ice 1" Ice	3.26 5.89 8.52	3.26 5.89 8.52	60.00 107.00 154.00
5' Standoff (Farmington)	B	From Face	2.50 0.00 0.00	0.0000	190.00	No Ice 1/2" Ice 1" Ice	3.26 5.89 8.52	3.26 5.89 8.52	60.00 107.00 154.00
5' Standoff (Farmington)	C	From Face	2.50 0.00 0.00	0.0000	190.00	No Ice 1/2" Ice 1" Ice	3.26 5.89 8.52	3.26 5.89 8.52	60.00 107.00 154.00
6' x 3" Pipe Mount (Farmington)	B	From Face	5.00 0.00 0.00	0.0000	190.00	No Ice 1/2" Ice 1" Ice	1.93 2.29 2.67	1.93 2.29 2.67	45.50 60.68 80.03
10' Omni (Farmington)	A	From Face	5.00 0.00 5.00	0.0000	190.00	No Ice 1/2" Ice 1" Ice	2.50 3.53 4.58	2.50 3.53 4.58	30.00 48.64 73.79
10' Omni (Farmington)	C	From Face	5.00 0.00 5.00	0.0000	190.00	No Ice 1/2" Ice 1" Ice	2.50 3.53 4.58	2.50 3.53 4.58	30.00 48.64 73.79

5' Standoff (Farmington)	A	From Face	2.50 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 1" Ice	3.26 5.89 8.52	3.26 5.89 8.52	60.00 107.00 154.00
3' Yagi (Farmington)	A	From Face	5.00 0.00 0.00	0.0000	185.00	No Ice 1/2" Ice 1" Ice	2.00 5.05 8.11	2.00 5.05 8.11	30.95 55.21 99.83

5' Standoff (Farmington)	A	From Face	2.50 0.00 0.00	0.0000	180.00	No Ice 1/2" Ice 1" Ice	3.26 5.89 8.52	3.26 5.89 8.52	60.00 107.00 154.00
10' Omni (Farmington)	A	From Face	5.00 0.00 0.00	0.0000	180.00	No Ice 1/2" Ice 1" Ice	2.50 3.53 4.58	2.50 3.53 4.58	30.00 48.64 73.79

APXVSPPI8-C-A20 w/Mount Pipe (Sprint)	A	From Face	4.00 2.00 0.00	0.0000	170.00	No Ice 1/2" Ice 1" Ice	8.56 9.21 9.83	6.95 8.13 9.03	82.55 147.99 225.42
APXVSPPI8-C-A20 w/Mount Pipe (Sprint)	B	From Face	4.00 2.00 0.00	0.0000	170.00	No Ice 1/2" Ice 1" Ice	8.56 9.21 9.83	6.95 8.13 9.03	82.55 147.99 225.42
APXVSPPI8-C-A20 w/Mount Pipe (Sprint)	C	From Face	4.00 2.00 0.00	0.0000	170.00	No Ice 1/2" Ice 1" Ice	8.56 9.21 9.83	6.95 8.13 9.03	82.55 147.99 225.42
1900MHz 4x40W RRH	A	From Face	4.00	0.0000	170.00	No Ice	2.71	2.61	59.50

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	6 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _{AA} Front ft ²	C _{AA} Side ft ²	Weight lb
(Sprint)			2.00			1/2" Ice	2.95	2.84	82.62
			0.00			1" Ice	3.20	3.09	108.98
1900MHz 4x40W RRH (Sprint)	B	From Face	4.00	0.0000	170.00	No Ice	2.71	2.61	59.50
			2.00			1/2" Ice	2.95	2.84	82.62
			0.00			1" Ice	3.20	3.09	108.98
1900MHz 4x40W RRH (Sprint)	C	From Face	4.00	0.0000	170.00	No Ice	2.71	2.61	59.50
			2.00			1/2" Ice	2.95	2.84	82.62
			0.00			1" Ice	3.20	3.09	108.98
800MHz 2x50W RRH (Sprint)	A	From Face	4.00	0.0000	170.00	No Ice	2.40	2.25	64.00
			2.00			1/2" Ice	2.61	2.46	86.12
			0.00			1" Ice	2.83	2.68	111.30
800MHz 2x50W RRH (Sprint)	B	From Face	4.00	0.0000	170.00	No Ice	2.40	2.25	64.00
			2.00			1/2" Ice	2.61	2.46	86.12
			0.00			1" Ice	2.83	2.68	111.30
800MHz 2x50W RRH (Sprint)	C	From Face	4.00	0.0000	170.00	No Ice	2.40	2.25	64.00
			2.00			1/2" Ice	2.61	2.46	86.12
			0.00			1" Ice	2.83	2.68	111.30
(2) DB980F90E-M w/Mount Pipe (Sprint)	A	From Face	4.00	0.0000	170.00	No Ice	4.37	3.95	34.05
			0.00			1/2" Ice	4.96	5.04	70.69
			0.00			1" Ice	5.47	5.85	117.91
(2) DB980F90E-M w/Mount Pipe (Sprint)	B	From Face	4.00	0.0000	170.00	No Ice	4.37	3.95	34.05
			0.00			1/2" Ice	4.96	5.04	70.69
			0.00			1" Ice	5.47	5.85	117.91
(2) DB980F90E-M w/Mount Pipe (Sprint)	C	From Face	4.00	0.0000	170.00	No Ice	4.37	3.95	34.05
			0.00			1/2" Ice	4.96	5.04	70.69
			0.00			1" Ice	5.47	5.85	117.91
LLPX310R-V1 w/Mount Pipe (Clearwire)	A	From Face	4.00	0.0000	170.00	No Ice	5.09	3.00	43.98
			0.00			1/2" Ice	5.50	3.54	80.25
			0.00			1" Ice	5.93	4.10	124.49
LLPX310R-V1 w/Mount Pipe (Clearwire)	B	From Face	4.00	0.0000	170.00	No Ice	5.09	3.00	43.98
			0.00			1/2" Ice	5.50	3.54	80.25
			0.00			1" Ice	5.93	4.10	124.49
LLPX310R-V1 w/Mount Pipe (Clearwire)	C	From Face	4.00	0.0000	170.00	No Ice	5.09	3.00	43.98
			0.00			1/2" Ice	5.50	3.54	80.25
			0.00			1" Ice	5.93	4.10	124.49
RRH-P4 (Clearwire)	A	From Face	4.00	0.0000	170.00	No Ice	3.17	2.08	60.00
			0.00			1/2" Ice	3.42	2.29	83.06
			0.00			1" Ice	3.68	2.52	109.33
RRH-P4 (Clearwire)	B	From Face	4.00	0.0000	170.00	No Ice	3.17	2.08	60.00
			0.00			1/2" Ice	3.42	2.29	83.06
			0.00			1" Ice	3.68	2.52	109.33
RRH-P4 (Clearwire)	C	From Face	4.00	0.0000	170.00	No Ice	3.17	2.08	60.00
			0.00			1/2" Ice	3.42	2.29	83.06
			0.00			1" Ice	3.68	2.52	109.33
PiROD 15' Low Profile Platform (Sprint)	C	None		0.0000	170.00	No Ice	17.30	17.30	1500.00
						1/2" Ice	22.10	22.10	2030.00
						1" Ice	26.90	26.90	2560.00

(2) 6' x 3" Pipe Mount (T-Mobile)	A	From Face	4.00	0.0000	160.00	No Ice	1.93	1.93	45.50
			5.00			1/2" Ice	2.29	2.29	60.68
			0.00			1" Ice	2.67	2.67	80.03
(2) 6' x 3" Pipe Mount (T-Mobile)	B	From Face	4.00	0.0000	160.00	No Ice	1.93	1.93	45.50
			5.00			1/2" Ice	2.29	2.29	60.68
			0.00			1" Ice	2.67	2.67	80.03
(2) 6' x 3" Pipe Mount (T-Mobile)	C	From Face	4.00	0.0000	160.00	No Ice	1.93	1.93	45.50
			5.00			1/2" Ice	2.29	2.29	60.68
			0.00			1" Ice	2.67	2.67	80.03

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	7 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _{AA} Front ft ²	C _{AA} Side ft ²	Weight lb
(2) APX16DWV-16DWVS-C w/Mount Pipe (T-Mobile)	A	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1" Ice	7.31 7.78 8.27	3.34 3.99 4.64	57.85 102.64 156.66
(2) APX16DWV-16DWVS-C w/Mount Pipe (T-Mobile)	B	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1" Ice	7.31 7.78 8.27	3.34 3.99 4.64	57.85 102.64 156.66
(2) APX16DWV-16DWVS-C w/Mount Pipe (T-Mobile)	C	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1" Ice	7.31 7.78 8.27	3.34 3.99 4.64	57.85 102.64 156.66
(2) TMA (T-Mobile)	A	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1" Ice	1.40 1.56 1.73	0.70 0.82 0.95	5.00 15.34 27.81
(2) TMA (T-Mobile)	B	From Face	4.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1" Ice	1.40 1.56 1.73	0.70 0.82 0.95	5.00 15.34 27.81
(2) TMA (T-Mobile)	C	From Face	0.00 0.00 0.00	0.0000	160.00	No Ice 1/2" Ice 1" Ice	1.40 1.56 1.73	0.70 0.82 0.95	5.00 15.34 27.81
PiROD 13' Low Profile Platform (T-Mobile)	C	None	0.00	0.0000	160.00	No Ice 1/2" Ice 1" Ice	15.70 20.10 24.50	15.70 20.10 24.50	1300.00 1765.00 2230.00

3' Standoff (AT&T)	A	From Face	1.50 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	2.00 3.70 5.40	2.00 3.70 5.40	38.00 67.00 96.00
3' Standoff (AT&T)	B	From Face	1.50 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	2.00 3.70 5.40	2.00 3.70 5.40	38.00 67.00 96.00
3' Standoff (AT&T)	C	From Face	1.50 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	2.00 3.70 5.40	2.00 3.70 5.40	38.00 67.00 96.00
800 10121 w/Mount Pipe (AT&T)	A	From Face	3.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	5.80 6.35 6.87	4.72 5.56 6.29	72.60 118.97 175.23
800 10121 w/Mount Pipe (AT&T)	B	From Face	3.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	5.80 6.35 6.87	4.72 5.56 6.29	72.60 118.97 175.23
800 10121 w/Mount Pipe (AT&T)	C	From Face	3.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	5.80 6.35 6.87	4.72 5.56 6.29	72.60 118.97 175.23
(2) LGP214nn (AT&T)	A	From Face	3.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	1.30 1.45 1.62	0.23 0.31 0.40	14.10 21.30 30.39
(2) LGP214nn (AT&T)	B	From Face	3.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	1.30 1.45 1.62	0.23 0.31 0.40	14.10 21.30 30.39
(2) LGP214nn (AT&T)	C	From Face	3.00 0.00 0.00	0.0000	150.00	No Ice 1/2" Ice 1" Ice	1.30 1.45 1.62	0.23 0.31 0.40	14.10 21.30 30.39

2' Standoff	A	From Face	1.00 0.00 0.00	0.0000	140.00	No Ice 1/2" Ice 1" Ice	1.80 3.30 4.80	1.80 3.30 4.80	33.00 59.00 85.00
2' Standoff	B	From Face	1.00 0.00 0.00	0.0000	140.00	No Ice 1/2" Ice 1" Ice	1.80 3.30 4.80	1.80 3.30 4.80	33.00 59.00 85.00
2' Standoff	C	From Face	1.00	0.0000	140.00	No Ice	1.80	1.80	33.00

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	8 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft		C _{AA} Front ft ²	C _{AA} Side ft ²	Weight lb
742 213V01 w/Mount Pipe	A	From Face	0.00	0.0000	140.00	1/2" Ice	3.30	3.30	59.00
			0.00			1" Ice	4.80	4.80	85.00
			2.00			No Ice	5.31	4.65	45.35
			0.00			1/2" Ice	5.85	5.96	86.56
742 213V01 w/Mount Pipe	B	From Face	0.00	0.0000	140.00	1" Ice	6.37	6.86	139.43
			2.00			No Ice	5.31	4.65	45.35
			0.00			1/2" Ice	5.85	5.96	86.56
			0.00			1" Ice	6.37	6.86	139.43
742 213V01 w/Mount Pipe	C	From Face	2.00	0.0000	140.00	No Ice	5.31	4.65	45.35
			0.00			1/2" Ice	5.85	5.96	86.56
			0.00			1" Ice	6.37	6.86	139.43
			0.00			1" Ice	6.37	6.86	139.43

5' Standoff	A	From Face	2.50	0.0000	113.00	No Ice	3.26	3.26	60.00
			0.00			1/2" Ice	5.89	5.89	107.00
			0.00			1" Ice	8.52	8.52	154.00
5' Standoff	B	From Face	2.50	0.0000	113.00	No Ice	3.26	3.26	60.00
			0.00			1/2" Ice	5.89	5.89	107.00
			0.00			1" Ice	8.52	8.52	154.00
5' Standoff	C	From Face	2.50	0.0000	113.00	No Ice	3.26	3.26	60.00
			0.00			1/2" Ice	5.89	5.89	107.00
			0.00			1" Ice	8.52	8.52	154.00
10' Omni	A	From Face	5.00	0.0000	113.00	No Ice	2.50	2.50	30.00
			0.00			1/2" Ice	3.53	3.53	48.64
			5.00			1" Ice	4.58	4.58	73.79
10' Omni	B	From Face	5.00	0.0000	113.00	No Ice	2.50	2.50	30.00
			0.00			1/2" Ice	3.53	3.53	48.64
			5.00			1" Ice	4.58	4.58	73.79
10' Omni	C	From Face	5.00	0.0000	113.00	No Ice	2.50	2.50	30.00
			0.00			1/2" Ice	3.53	3.53	48.64
			5.00			1" Ice	4.58	4.58	73.79

5' Standoff	A	From Face	2.50	0.0000	90.00	No Ice	3.26	3.26	60.00
			0.00			1/2" Ice	5.89	5.89	107.00
			0.00			1" Ice	8.52	8.52	154.00
5' Standoff	B	From Face	2.50	0.0000	90.00	No Ice	3.26	3.26	60.00
			0.00			1/2" Ice	5.89	5.89	107.00
			0.00			1" Ice	8.52	8.52	154.00
5' Standoff	C	From Face	2.50	0.0000	90.00	No Ice	3.26	3.26	60.00
			0.00			1/2" Ice	5.89	5.89	107.00
			0.00			1" Ice	8.52	8.52	154.00
18' Omni	A	From Face	5.00	0.0000	90.00	No Ice	5.40	5.40	50.00
			0.00			1/2" Ice	7.23	7.23	88.89
			9.00			1" Ice	9.08	9.08	139.24
18' Omni	B	From Face	5.00	0.0000	90.00	No Ice	5.40	5.40	50.00
			0.00			1/2" Ice	7.23	7.23	88.89
			9.00			1" Ice	9.08	9.08	139.24
18' Omni	C	From Face	5.00	0.0000	90.00	No Ice	5.40	5.40	50.00
			0.00			1/2" Ice	7.23	7.23	88.89
			9.00			1" Ice	9.08	9.08	139.24

Dishes

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	9 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert ft	Azimuth Adjustment °	3 dB Beam Width °	Elevation ft	Outside Diameter ft	Aperture Area ft ²	Weight lb
PR-850 (Farmington)	A	Grid	From Face	5.00 0.00 0.00	0.0000		190.00	4.65	No Ice 17.00 1/2" Ice 17.61 1" Ice 18.22	38.00 91.75 145.50
PR-850 (Farmington)	B	Grid	From Face	5.00 0.00 0.00	0.0000		190.00	4.65	No Ice 17.00 1/2" Ice 17.61 1" Ice 18.22	38.00 91.75 145.50

VHLP2.5 (Clearwire)	C	Paraboloid w/Shroud (HP)	From Face	6.00 0.00 0.00	0.0000		174.00	2.92	No Ice 6.68 1/2" Ice 7.07 1" Ice 7.46	48.00 76.00 104.00
VHLP2 (Clearwire)	B	Paraboloid w/Shroud (HP)	From Face	6.00 0.00 0.00	0.0000		174.00	2.18	No Ice 3.72 1/2" Ice 4.01 1" Ice 4.30	27.00 54.00 81.00

Force Totals

Load Case	Vertical Forces lb	Sum of Forces X lb	Sum of Forces Z lb	Sum of Overturning Moments, M _x lb-ft	Sum of Overturning Moments, M _y lb-ft	Sum of Torques lb-ft
Leg Weight	33905.31					
Bracing Weight	0.00					
Total Member Self-Weight	33905.31					
Total Weight	47319.45			219.44	1692.21	
Wind 0 deg - No Ice		53.95	-27637.44	-3191907.42	-7695.73	-2659.05
Wind 30 deg - No Ice		13782.41	-23964.95	-2769535.48	-1588207.80	-2431.84
Wind 60 deg - No Ice		23924.75	-13946.39	-1618567.15	-2763178.03	-2345.17
Wind 90 deg - No Ice		27685.70	-37.58	-6638.59	-3201693.70	-1124.14
Wind 120 deg - No Ice		23919.56	13792.78	1591788.39	-2762015.31	532.77
Wind 150 deg - No Ice		13761.19	23861.29	2751583.86	-1585131.05	2224.07
Wind 180 deg - No Ice		-86.32	27569.53	3180282.57	16712.13	2759.05
Wind 210 deg - No Ice		-13832.46	23905.04	2759196.22	1600915.43	2324.69
Wind 240 deg - No Ice		-23954.66	13875.34	1606154.87	2771507.33	2126.28
Wind 270 deg - No Ice		-27719.57	61.48	10597.60	3210971.57	1146.15
Wind 300 deg - No Ice		-23941.43	-13856.34	-1602899.10	2769464.44	-413.87
Wind 330 deg - No Ice		-13711.30	-23960.22	-2768712.59	1579219.46	-2138.93
Member Ice	21688.57					
Total Weight Ice	112195.47			-11731.89	-9281.07	
Wind 0 deg - Ice		19.22	-15885.02	-1856450.91	-12624.69	-2648.67
Wind 30 deg - Ice		7930.76	-13755.98	-1608995.01	-929633.44	-2653.73
Wind 60 deg - Ice		13976.13	-7837.58	-913638.49	-1649273.50	-2155.14
Wind 90 deg - Ice		16024.95	138.88	14766.69	-1881270.52	-1033.54
Wind 120 deg - Ice		13884.22	7993.76	920528.30	-1631754.51	112.45
Wind 150 deg - Ice		8084.96	13731.04	1581232.38	-959264.94	1306.65
Wind 180 deg - Ice		-30.74	16025.82	1860014.85	-3931.56	2684.29
Wind 210 deg - Ice		-8110.34	13746.62	1583943.61	945119.18	3260.74
Wind 240 deg - Ice		-13896.72	8023.17	925645.09	1615367.66	2536.22
Wind 270 deg - Ice		-16037.01	174.16	20905.55	1864807.40	1041.37
Wind 300 deg - Ice		-13982.07	-7805.51	-908058.14	1631744.93	-529.14
Wind 330 deg - Ice		-7905.44	-13754.30	-1608701.93	906664.60	-1921.49
Total Weight	47319.45			219.44	1692.21	
Wind 0 deg - Service		18.10	-9269.23	-1071077.52	-2669.64	-435.73
Wind 30 deg - Service		4622.44	-8037.52	-929419.64	-532752.17	-552.29
Wind 60 deg - Service		8024.04	-4677.43	-543400.32	-926821.41	-786.54
Wind 90 deg - Service		9285.41	-12.60	-2781.13	-1073893.67	-640.34

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	10 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Load Case	Vertical Forces <i>lb</i>	Sum of Forces <i>X</i> <i>lb</i>	Sum of Forces <i>Z</i> <i>lb</i>	Sum of Overturning Moments, <i>M_x</i> <i>lb-ft</i>	Sum of Overturning Moments, <i>M_z</i> <i>lb-ft</i>	Sum of Torques <i>lb-ft</i>
Wind 120 deg - Service		8022.30	4625.91	533309.82	-926431.45	-277.40
Wind 150 deg - Service		4615.32	8002.76	922289.64	-531720.27	219.29
Wind 180 deg - Service		-28.95	9246.45	1066069.43	5516.42	469.27
Wind 210 deg - Service		-4639.22	8017.43	924842.72	536836.94	516.35
Wind 240 deg - Service		-8034.07	4653.60	538128.14	929437.74	713.12
Wind 270 deg - Service		-9296.77	20.62	2999.66	1076828.14	647.72
Wind 300 deg - Service		-8029.63	-4647.23	-538145.47	928752.58	317.27
Wind 330 deg - Service		-4598.59	-8035.94	-929143.66	529560.40	-190.73

Load Combinations

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.6 Wind 0 deg - No Ice
3	0.9 Dead+1.6 Wind 0 deg - No Ice
4	1.2 Dead+1.6 Wind 30 deg - No Ice
5	0.9 Dead+1.6 Wind 30 deg - No Ice
6	1.2 Dead+1.6 Wind 60 deg - No Ice
7	0.9 Dead+1.6 Wind 60 deg - No Ice
8	1.2 Dead+1.6 Wind 90 deg - No Ice
9	0.9 Dead+1.6 Wind 90 deg - No Ice
10	1.2 Dead+1.6 Wind 120 deg - No Ice
11	0.9 Dead+1.6 Wind 120 deg - No Ice
12	1.2 Dead+1.6 Wind 150 deg - No Ice
13	0.9 Dead+1.6 Wind 150 deg - No Ice
14	1.2 Dead+1.6 Wind 180 deg - No Ice
15	0.9 Dead+1.6 Wind 180 deg - No Ice
16	1.2 Dead+1.6 Wind 210 deg - No Ice
17	0.9 Dead+1.6 Wind 210 deg - No Ice
18	1.2 Dead+1.6 Wind 240 deg - No Ice
19	0.9 Dead+1.6 Wind 240 deg - No Ice
20	1.2 Dead+1.6 Wind 270 deg - No Ice
21	0.9 Dead+1.6 Wind 270 deg - No Ice
22	1.2 Dead+1.6 Wind 300 deg - No Ice
23	0.9 Dead+1.6 Wind 300 deg - No Ice
24	1.2 Dead+1.6 Wind 330 deg - No Ice
25	0.9 Dead+1.6 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	11 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Comb. No.	Description
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial lb	Major Axis Moment lb-ft	Minor Axis Moment lb-ft
L1	190.08 - 164.33	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-18205.91	4262.44	3578.06
			Max. Mx	20	-4727.38	109465.52	-22.20
			Max. My	2	-4757.22	-86.95	103669.06
			Max. Vy	20	-11068.53	109465.52	-22.20
			Max. Vx	2	-10931.79	-86.95	103669.06
			Max. Torque	7			4489.35
L2	164.33 - 129.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-42102.91	2653.92	5684.84
			Max. Mx	20	-12340.15	690554.76	-3445.80
			Max. My	2	-12372.49	-2821.09	679783.81
			Max. Vy	20	-22432.83	690554.76	-3445.80
			Max. Vx	2	-22291.39	-2821.09	679783.81
			Max. Torque	6			3736.39
L3	129.75 - 96.08	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-60082.69	102.65	7627.70
			Max. Mx	20	-20516.21	1532004.37	-6907.46
			Max. My	2	-20542.44	-5535.48	1516235.89
			Max. Vy	20	-28921.89	1532004.37	-6907.46
			Max. Vx	2	-28779.22	-5535.48	1516235.89
			Max. Torque	6			3728.58
L4	96.08 - 63.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-80222.70	-2818.94	9663.13
			Max. Mx	20	-30486.03	2578795.22	-10344.56
			Max. My	2	-30504.79	-8176.18	2558088.45
			Max. Vy	20	-35474.85	2578795.22	-10344.56
			Max. Vx	2	-35333.18	-8176.18	2558088.45
			Max. Torque	6			3717.99
L5	63.25 - 31.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-99915.95	-5865.92	11621.22
			Max. Mx	20	-41653.67	3762498.84	-13713.17
			Max. My	2	-41664.13	-10713.63	3736974.55
			Max. Vy	20	-40086.63	3762498.84	-13713.17
			Max. Vx	2	-39948.13	-10713.63	3736974.55
			Max. Torque	15			-3919.73
L6	31.25 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-124567.70	-9385.54	13653.01
			Max. Mx	20	-56755.77	5352321.79	-17702.35
			Max. My	2	-56756.01	-13664.47	5321134.64
			Max. Vy	20	-44386.59	5352321.79	-17702.35
			Max. Vx	2	-44254.98	-13664.47	5321134.64
			Max. Torque	15			-4343.18

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	12 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical lb	Horizontal, X lb	Horizontal, Z lb
Pole	Max. Vert	30	124567.70	-16024.97	-138.88
	Max. H _x	21	42587.50	44351.31	-98.36
	Max. H _z	3	42587.50	-86.33	44219.91
	Max. M _x	2	5321134.64	-86.33	44219.91
	Max. M _z	8	5338203.28	-44297.12	60.13
	Max. Torsion	3	4191.83	-86.33	44219.91
	Min. Vert	7	42587.50	-38279.60	22314.22
	Min. H _x	9	42587.50	-44297.12	60.13
	Min. H _z	15	42587.50	138.11	-44111.26
	Min. M _x	14	-5301469.91	138.11	-44111.26
	Min. M _z	20	-5352321.79	44351.31	-98.36
	Min. Torsion	15	-4343.21	138.11	-44111.26

Tower Mast Reaction Summary

Load Combination	Vertical lb	Shear _x lb	Shear _z lb	Overturning Moment, M _x lb-ft	Overturning Moment, M _z lb-ft	Torque lb-ft
Dead Only	47319.45	0.00	0.00	218.25	1695.30	0.01
1.2 Dead+1.6 Wind 0 deg - No Ice	56783.34	86.33	-44219.91	-5321134.64	-13665.24	-4186.92
0.9 Dead+1.6 Wind 0 deg - No Ice	42587.50	86.33	-44219.91	-5263210.97	-14010.51	-4191.83
1.2 Dead+1.6 Wind 30 deg - No Ice	56783.34	22051.86	-38343.92	-4617069.55	-2648232.72	-3832.14
0.9 Dead+1.6 Wind 30 deg - No Ice	42587.50	22051.86	-38343.92	-4566802.95	-2619923.70	-3833.25
1.2 Dead+1.6 Wind 60 deg - No Ice	56783.34	38279.60	-22314.22	-2698547.24	-4607041.20	-3695.48
0.9 Dead+1.6 Wind 60 deg - No Ice	42587.50	38279.60	-22314.22	-2669124.05	-4557338.85	-3693.13
1.2 Dead+1.6 Wind 90 deg - No Ice	56783.34	44297.12	-60.13	-11254.38	-5338203.28	-1779.76
0.9 Dead+1.6 Wind 90 deg - No Ice	42587.50	44297.12	-60.13	-11169.26	-5280489.80	-1774.05
1.2 Dead+1.6 Wind 120 deg - No Ice	56783.34	38271.29	22068.44	2653411.74	-4605162.90	827.30
0.9 Dead+1.6 Wind 120 deg - No Ice	42587.50	38271.29	22068.44	2624452.86	-4555490.71	834.84
1.2 Dead+1.6 Wind 150 deg - No Ice	56783.34	22017.91	38178.06	4586797.72	-2643162.73	3492.21
0.9 Dead+1.6 Wind 150 deg - No Ice	42587.50	22017.91	38178.06	4536806.68	-2614909.52	3499.67
1.2 Dead+1.6 Wind 180 deg - No Ice	56783.34	-138.11	44111.26	5301469.91	27340.28	4338.28
0.9 Dead+1.6 Wind 180 deg - No Ice	42587.50	-138.11	44111.26	5243684.15	26461.72	4343.21
1.2 Dead+1.6 Wind 210 deg - No Ice	56783.34	-22131.93	38248.06	4599517.04	2668170.84	3664.99
0.9 Dead+1.6 Wind 210 deg - No Ice	42587.50	-22131.93	38248.06	4549358.24	2638544.12	3665.89
1.2 Dead+1.6 Wind 240 deg - No Ice	56783.34	-38327.45	22200.55	2677518.73	4619586.65	3358.79
0.9 Dead+1.6 Wind 240 deg - No Ice	42587.50	-38327.45	22200.55	2648242.12	4568673.77	3356.17
1.2 Dead+1.6 Wind 270 deg - No Ice	56783.34	-44351.31	98.36	17702.69	5352321.79	1818.74
0.9 Dead+1.6 Wind 270 deg - No Ice	42587.50	-44351.31	98.36	17410.81	5293366.64	1813.05
1.2 Dead+1.6 Wind 300 deg - No Ice	56783.34	-38306.28	-22170.15	-2672273.97	4616210.72	-640.72
0.9 Dead+1.6 Wind 300 deg - No Ice	42587.50	-38306.28	-22170.15	-2643185.35	4565331.21	-648.18
1.2 Dead+1.6 Wind 330 deg - No Ice	56783.34	-21938.08	-38336.35	-4615761.35	2631703.22	-3363.41
0.9 Dead+1.6 Wind 330 deg - No Ice	42587.50	-21938.08	-38336.35	-4565503.87	2602558.26	-3370.80
1.2 Dead+1.0 Ice+1.0 Temp	124567.70	0.00	-0.01	-13653.01	-9385.54	0.73
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	124567.70	19.22	-15885.04	-2093979.40	-13416.59	-2628.14
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	124567.70	7930.77	-13756.00	-1814897.54	-1047304.69	-2650.08
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	124567.70	13976.15	-7837.59	-1029970.96	-1860481.52	-2174.95
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	124567.70	16024.97	138.88	17069.07	-2121488.73	-1065.33
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	124567.70	13884.24	7993.77	1037772.92	-1840052.26	78.84
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	124567.70	8084.97	13731.05	1782265.10	-1081863.86	1279.06
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	124567.70	-30.74	16025.84	2097816.16	-3376.92	2663.81
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	124567.70	-8110.35	13746.64	1785429.97	1067875.44	3254.68
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	124567.70	-13896.74	8023.18	1043717.18	1823513.90	2550.60
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	124567.70	-16037.03	174.16	24159.22	2104884.70	1074.18

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	Page
	CT33XC534	13 of 18
	Project	Date
	23009	17:49:22 11/16/12
	Client	Designed by
	Sprint	tmoore

Load Combination	Vertical	Shear _x	Shear _y	Overturning Moment, M _x	Overturning Moment, M _y	Torque
	lb	lb	lb	lb-ft	lb-ft	lb-ft
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	124567.70	-13982.09	-7805.52	-1023564.97	1842630.21	-487.50
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp	124567.70	-7905.45	-13754.32	-1814597.05	1023127.91	-1889.36
Dead+Wind 0 deg - Service	47319.45	18.10	-9269.23	-1109167.29	-1506.79	-433.32
Dead+Wind 30 deg - Service	47319.45	4622.44	-8037.52	-962390.55	-550755.81	-552.12
Dead+Wind 60 deg - Service	47319.45	8024.04	-4677.43	-562433.77	-959137.25	-788.54
Dead+Wind 90 deg - Service	47319.45	9285.41	-12.60	-2189.45	-1111570.79	-644.40
Dead+Wind 120 deg - Service	47319.45	8022.30	4625.91	553330.83	-958727.41	-282.22
Dead+Wind 150 deg - Service	47319.45	4615.32	8002.76	956377.42	-549685.61	214.93
Dead+Wind 180 deg - Service	47319.45	-28.95	9246.45	1105369.06	7035.68	466.55
Dead+Wind 210 deg - Service	47319.45	-4639.22	8017.43	959041.21	557583.08	516.33
Dead+Wind 240 deg - Service	47319.45	-8034.07	4653.60	558358.88	964422.65	715.61
Dead+Wind 270 deg - Service	47319.45	-9296.77	20.62	3843.08	1117191.65	652.09
Dead+Wind 300 deg - Service	47319.45	-8029.63	-4647.23	-556950.75	963711.70	322.16
Dead+Wind 330 deg - Service	47319.45	-4598.59	-8035.94	-962103.38	549983.77	-186.62

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
1	0.00	-47319.45	0.00	0.00	47319.45	0.00	0.000%
2	86.33	-56783.34	-44219.91	-86.33	56783.34	44219.91	0.000%
3	86.33	-42587.50	-44219.91	-86.33	42587.50	44219.91	0.000%
4	22051.86	-56783.34	-38343.92	-22051.86	56783.34	38343.92	0.000%
5	22051.86	-42587.50	-38343.92	-22051.86	42587.50	38343.92	0.000%
6	38279.60	-56783.34	-22314.22	-38279.60	56783.34	22314.22	0.000%
7	38279.60	-42587.50	-22314.22	-38279.60	42587.50	22314.22	0.000%
8	44297.12	-56783.34	-60.13	-44297.12	56783.34	60.13	0.000%
9	44297.12	-42587.50	-60.13	-44297.12	42587.50	60.13	0.000%
10	38271.29	-56783.34	22068.44	-38271.29	56783.34	-22068.44	0.000%
11	38271.29	-42587.50	22068.44	-38271.29	42587.50	-22068.44	0.000%
12	22017.91	-56783.34	38178.06	-22017.91	56783.34	-38178.06	0.000%
13	22017.91	-42587.50	38178.06	-22017.91	42587.50	-38178.06	0.000%
14	-138.11	-56783.34	44111.26	138.11	56783.34	-44111.26	0.000%
15	-138.11	-42587.50	44111.26	138.11	42587.50	-44111.26	0.000%
16	-22131.93	-56783.34	38248.06	22131.93	56783.34	-38248.06	0.000%
17	-22131.93	-42587.50	38248.06	22131.93	42587.50	-38248.06	0.000%
18	-38327.45	-56783.34	22200.55	38327.45	56783.34	-22200.55	0.000%
19	-38327.45	-42587.50	22200.55	38327.45	42587.50	-22200.55	0.000%
20	-44351.31	-56783.34	98.36	44351.31	56783.34	-98.36	0.000%
21	-44351.31	-42587.50	98.36	44351.31	42587.50	-98.36	0.000%
22	-38306.28	-56783.34	-22170.15	38306.28	56783.34	22170.15	0.000%
23	-38306.28	-42587.50	-22170.15	38306.28	42587.50	22170.15	0.000%
24	-21938.08	-56783.34	-38336.35	21938.08	56783.34	38336.35	0.000%
25	-21938.08	-42587.50	-38336.35	21938.08	42587.50	38336.35	0.000%
26	0.00	-124567.70	0.00	-0.00	124567.70	0.01	0.000%
27	19.22	-124567.70	-15885.02	-19.22	124567.70	15885.04	0.000%
28	7930.76	-124567.70	-13755.98	-7930.77	124567.70	13756.00	0.000%
29	13976.13	-124567.70	-7837.58	-13976.15	124567.70	7837.59	0.000%
30	16024.95	-124567.70	138.88	-16024.97	124567.70	-138.88	0.000%
31	13884.22	-124567.70	7993.76	-13884.24	124567.70	-7993.77	0.000%
32	8084.96	-124567.70	13731.04	-8084.97	124567.70	-13731.05	0.000%
33	-30.74	-124567.70	16025.82	30.74	124567.70	-16025.84	0.000%
34	-8110.34	-124567.70	13746.62	8110.35	124567.70	-13746.64	0.000%
35	-13896.72	-124567.70	8023.17	13896.74	124567.70	-8023.18	0.000%
36	-16037.01	-124567.70	174.16	16037.03	124567.70	-174.16	0.000%
37	-13982.07	-124567.70	-7805.51	13982.09	124567.70	7805.52	0.000%
38	-7905.44	-124567.70	-13754.30	7905.45	124567.70	13754.32	0.000%

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	14 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX lb	PY lb	PZ lb	PX lb	PY lb	PZ lb	
39	18.10	-47319.45	-9269.23	-18.10	47319.45	9269.23	0.000%
40	4622.44	-47319.45	-8037.52	-4622.44	47319.45	8037.52	0.000%
41	8024.04	-47319.45	-4677.43	-8024.04	47319.45	4677.43	0.000%
42	9285.41	-47319.45	-12.60	-9285.41	47319.45	12.60	0.000%
43	8022.30	-47319.45	4625.91	-8022.30	47319.45	-4625.91	0.000%
44	4615.32	-47319.45	8002.76	-4615.32	47319.45	-8002.76	0.000%
45	-28.95	-47319.45	9246.45	28.95	47319.45	-9246.45	0.000%
46	-4639.22	-47319.45	8017.43	4639.22	47319.45	-8017.43	0.000%
47	-8034.07	-47319.45	4653.60	8034.07	47319.45	-4653.60	0.000%
48	-9296.77	-47319.45	20.62	9296.77	47319.45	-20.62	0.000%
49	-8029.63	-47319.45	-4647.23	8029.63	47319.45	4647.23	0.000%
50	-4598.59	-47319.45	-8035.94	4598.59	47319.45	8035.94	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	6	0.00000001	0.00000894
3	Yes	5	0.00000001	0.00008085
4	Yes	6	0.00000001	0.00013677
5	Yes	6	0.00000001	0.00003989
6	Yes	7	0.00000001	0.00000710
7	Yes	6	0.00000001	0.00004473
8	Yes	6	0.00000001	0.00000952
9	Yes	5	0.00000001	0.00008552
10	Yes	6	0.00000001	0.00014199
11	Yes	6	0.00000001	0.00004171
12	Yes	6	0.00000001	0.00013725
13	Yes	6	0.00000001	0.00004024
14	Yes	6	0.00000001	0.00001283
15	Yes	5	0.00000001	0.00011547
16	Yes	6	0.00000001	0.00014879
17	Yes	6	0.00000001	0.00004399
18	Yes	6	0.00000001	0.00013793
19	Yes	6	0.00000001	0.00004005
20	Yes	6	0.00000001	0.00000737
21	Yes	5	0.00000001	0.00006648
22	Yes	6	0.00000001	0.00014461
23	Yes	6	0.00000001	0.00004238
24	Yes	6	0.00000001	0.00014622
25	Yes	6	0.00000001	0.00004326
26	Yes	5	0.00000001	0.00003064
27	Yes	7	0.00000001	0.00006258
28	Yes	7	0.00000001	0.00011080
29	Yes	7	0.00000001	0.00012361
30	Yes	7	0.00000001	0.00006121
31	Yes	7	0.00000001	0.00011528
32	Yes	7	0.00000001	0.00011370
33	Yes	7	0.00000001	0.00006290
34	Yes	7	0.00000001	0.00012402
35	Yes	7	0.00000001	0.00011219
36	Yes	7	0.00000001	0.00006105
37	Yes	7	0.00000001	0.00011572
38	Yes	7	0.00000001	0.00011780
39	Yes	5	0.00000001	0.00000916

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	15 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

40	Yes	5	0.00000001	0.00003746
41	Yes	5	0.00000001	0.00004933
42	Yes	5	0.00000001	0.00001284
43	Yes	5	0.00000001	0.00003876
44	Yes	5	0.00000001	0.00003848
45	Yes	5	0.00000001	0.00001020
46	Yes	5	0.00000001	0.00004580
47	Yes	5	0.00000001	0.00003805
48	Yes	5	0.00000001	0.00001255
49	Yes	5	0.00000001	0.00004456
50	Yes	5	0.00000001	0.00004238

Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	190.08 - 164.33	32.849	48	1.4576	0.0105
L2	167.25 - 129.75	25.963	48	1.4089	0.0054
L3	133.58 - 96.08	16.697	48	1.1820	0.0025
L4	100.75 - 63.25	9.484	48	0.8950	0.0013
L5	68.75 - 31.25	4.419	48	0.5986	0.0007
L6	37.5 - 0	1.345	48	0.3214	0.0003

Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
197.50	Lightning Rod 2"x15'	48	32.849	1.4576	0.0113	63479
190.00	PR-850	48	32.825	1.4575	0.0113	63479
185.00	5' Standoff	48	31.301	1.4511	0.0100	62479
180.00	5' Standoff	48	29.782	1.4434	0.0087	31487
174.00	VHLP2.5	48	27.973	1.4306	0.0073	19738
170.00	APXVSPP18-C-A20 w/Mount Pipe	48	26.778	1.4189	0.0065	15821
160.00	(2) 6' x 3" Pipe Mount	48	23.849	1.3745	0.0048	11260
150.00	3' Standoff	48	21.026	1.3111	0.0038	8921
140.00	2' Standoff	48	18.338	1.2348	0.0031	7387
113.00	5' Standoff	48	11.938	1.0051	0.0019	6337
90.00	5' Standoff	48	7.569	0.7957	0.0012	6353

Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	190.08 - 164.33	157.133	20	6.9677	0.0493
L2	167.25 - 129.75	124.275	20	6.7438	0.0253
L3	133.58 - 96.08	79.977	20	5.6646	0.0119
L4	100.75 - 63.25	45.448	20	4.2908	0.0068
L5	68.75 - 31.25	21.182	20	2.8699	0.0038

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	16 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L6	37.5 - 0	6.447	20	1.5407	0.0018

Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
197.50	Lightning Rod 2"x15'	20	157.133	6.9677	0.0535	13991
190.00	PR-850	20	157.016	6.9673	0.0534	13991
185.00	5' Standoff	20	149.748	6.9389	0.0471	13771
180.00	5' Standoff	20	142.502	6.9042	0.0410	6939
174.00	VHLP2.5	20	133.866	6.8453	0.0342	4348
170.00	APXVSPP18-C-A20 w/Mount Pipe	20	128.164	6.7906	0.0301	3483
160.00	(2) 6' x 3" Pipe Mount	20	114.175	6.5814	0.0223	2452
150.00	3' Standoff	20	100.685	6.2801	0.0173	1923
140.00	2' Standoff	20	87.831	5.9166	0.0142	1580
113.00	5' Standoff	20	57.200	4.8183	0.0087	1342
90.00	5' Standoff	20	36.274	3.8152	0.0056	1337

Base Plate Design Data

Plate Thickness in	Number of Anchor Bolts	Anchor Bolt Size in	Actual Allowable Ratio Bolt Tension lb	Actual Allowable Ratio Bolt Compression lb	Actual Allowable Ratio Plate Stress ksi	Actual Allowable Ratio Stiffener Stress ksi	Controlling Condition	Ratio
1.5000	44	1.2500	84576.69 103543.70 0.82	87156.50 171882.55 0.51	33.374 45.000 0.74	15.570 45.000 0.35	Bolt T	0.82 ✓

Compression Checks

Pole Design Data

Section No.	Elevation ft	Size	L ft	L _u ft	Kl/r	A in ²	P _u lb	φP _n lb	Ratio P _u / φP _n
L1	190.08 - 164.33 (1)	TP26x19.5625x0.25	25.75	0.00	0.0	19.8534	-4727.38	1475010.00	0.003
L2	164.33 - 129.75 (2)	TP34.0052x24.77x0.3125	37.50	0.00	0.0	32.4834	-12340.10	2384690.00	0.005
L3	129.75 - 96.08 (3)	TP41.0625x32.437x0.375	37.50	0.00	0.0	47.1498	-20516.20	3454030.00	0.006
L4	96.08 - 63.25 (4)	TP49.0052x39.2383x0.375	37.50	0.00	0.0	56.1771	-30486.00	3903670.00	0.008
L5	63.25 - 31.25 (5)	TP56.0104x46.8227x0.375	37.50	0.00	0.0	64.3974	-41653.70	4253940.00	0.010
L6	31.25 - 0 (6)	TP62.0781x53.7291x0.375	37.50	0.00	0.0	73.4421	-56755.80	4574150.00	0.012

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	17 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Pole Bending Design Data

Section No.	Elevation ft	Size	M_{ux} lb-ft	ϕM_{ux} lb-ft	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	M_{uy} lb-ft	ϕM_{uy} lb-ft	Ratio $\frac{M_{uy}}{\phi M_{uy}}$
L1	190.08 - 164.33 (1)	TP26x19.5625x0.25	109465.83	757278.33	0.145	0.00	757278.33	0.000
L2	164.33 - 129.75 (2)	TP34.0052x24.77x0.3125	690563.33	1603258.33	0.431	0.00	1603258.33	0.000
L3	129.75 - 96.08 (3)	TP41.0625x32.437x0.375	1532016.67	2809108.33	0.545	0.00	2809108.33	0.000
L4	96.08 - 63.25 (4)	TP49.0052x39.2383x0.375	2578816.67	3788350.00	0.681	0.00	3788350.00	0.000
L5	63.25 - 31.25 (5)	TP56.0104x46.8227x0.375	3762525.00	4737116.67	0.794	0.00	4737116.67	0.000
L6	31.25 - 0 (6)	TP62.0781x53.7291x0.375	5352350.00	5814041.33	0.921	0.00	5814041.33	0.000

Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V_u lb	ϕV_n lb	Ratio $\frac{V_u}{\phi V_n}$	Actual T_u lb-ft	ϕT_n lb-ft	Ratio $\frac{T_u}{\phi T_n}$
L1	190.08 - 164.33 (1)	TP26x19.5625x0.25	11069.00	737503.00	0.015	2667.87	1516408.33	0.002
L2	164.33 - 129.75 (2)	TP34.0052x24.77x0.3125	22433.10	1192350.00	0.019	2716.62	3210450.00	0.001
L3	129.75 - 96.08 (3)	TP41.0625x32.437x0.375	28922.10	1727020.00	0.017	2513.13	5625091.33	0.000
L4	96.08 - 63.25 (4)	TP49.0052x39.2383x0.375	35475.00	1951840.00	0.018	2298.63	7585966.67	0.000
L5	63.25 - 31.25 (5)	TP56.0104x46.8227x0.375	40086.80	2126970.00	0.019	2077.10	9485833.33	0.000
L6	31.25 - 0 (6)	TP62.0781x53.7291x0.375	44386.70	2287070.00	0.019	1829.31	11642333.33	0.000

Pole Interaction Design Data

Section No.	Elevation ft	Ratio $\frac{P_u}{\phi P_n}$	Ratio $\frac{M_{ux}}{\phi M_{ux}}$	Ratio $\frac{M_{uy}}{\phi M_{uy}}$	Ratio $\frac{V_u}{\phi V_n}$	Ratio $\frac{T_u}{\phi T_n}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	190.08 - 164.33 (1)	0.003	0.145	0.000	0.015	0.002	0.148 ✓	1.000	4.8.2 ✓
L2	164.33 - 129.75 (2)	0.005	0.431	0.000	0.019	0.001	0.436 ✓	1.000	4.8.2 ✓
L3	129.75 - 96.08 (3)	0.006	0.545	0.000	0.017	0.000	0.552 ✓	1.000	4.8.2 ✓
L4	96.08 - 63.25 (4)	0.008	0.681	0.000	0.018	0.000	0.689 ✓	1.000	4.8.2 ✓
L5	63.25 - 31.25 (5)	0.010	0.794	0.000	0.019	0.000	0.804 ✓	1.000	4.8.2 ✓
L6	31.25 - 0 (6)	0.012	0.921	0.000	0.019	0.000	0.933 ✓	1.000	4.8.2 ✓

Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
-------------	-----------------	-------------------	------	---------------------	---------	------------------------	------------	--------------

tnxTower Ramaker & Associates, Inc. 1120 Dallas Street Sauk City, WI 53583 Phone: (608) 643-4100 FAX: (608) 643-7999	Job	CT33XC534	Page	18 of 18
	Project	23009	Date	17:49:22 11/16/12
	Client	Sprint	Designed by	tmoore

Section No.	Elevation ft	Component Type	Size	Critical Element	P lb	ϕP_{allow} lb	% Capacity	Pass Fail
L1	190.08 - 164.33	Pole	TP26x19.5625x0.25	1	-4727.38	1475010.00	14.8	Pass
L2	164.33 - 129.75	Pole	TP34.0052x24.77x0.3125	2	-12340.10	2384690.00	43.6	Pass
L3	129.75 - 96.08	Pole	TP41.0625x32.437x0.375	3	-20516.20	3454030.00	55.2	Pass
L4	96.08 - 63.25	Pole	TP49.0052x39.2383x0.375	4	-30486.00	3903670.00	68.9	Pass
L5	63.25 - 31.25	Pole	TP56.0104x46.8227x0.375	5	-41653.70	4253940.00	80.4	Pass
L6	31.25 - 0	Pole	TP62.0781x53.7291x0.375	6	-56755.80	4574150.00	93.3	Pass
							Summary	
							Pole (L6)	93.3 Pass
							Base Plate	81.7 Pass
							RATING =	93.3 Pass


VICINITY MAP



AERIAL VIEW OF SITE



GENERAL LOCATION



DRIVING DIRECTIONS:

TAKE I-84 WEST TO EXIT 39 FOR ROUTE 4 WEST. FOLLOW ROUTE 4 INTO UNIONVILLE AND TAKE A LEFT ONTO ROUTE 177 SOUTH OVER THE BRIDGE AND TAKE A LEFT ONTO NEW BRITAIN AVE. THE SITE IS ABOUT A MILE DOWN ON THE LEFT BEHIND THE FARMINGTON POLICE DEPARTMENT

CODE COMPLIANCE

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL COVERING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.

1. INTERNATIONAL BUILDING CODE 2009
2. ACCESSIBILITY CODE IBC 2009, CHAPTER 11 # ICC/ANSI A117.1-2003
3. 2008 NATIONAL ELECTRIC CODE
4. FIRE/LIFE SAFETY CODE- IFC 2009
5. ENERGY CODE IECC 2009

PROJECT NOTES

1. THIS IS AN UNMANNED TELECOMMUNICATIONS FACILITY CONSISTING OF BTS EQUIPMENT AND ANTENNAS.
2. SIGNALS FROM THE ANTENNA SHALL NOT INTERFERE WITH ANY EXISTING COMMUNICATION SITES. ALL ITEMS SHOWN HEREON ARE EXISTING UNLESS OTHERWISE NOTED.
3. THE PROPOSED ANTENNAS ARE ATTACHED TO EITHER BUILDING OR ANTENNA FRAME OR TO BOTH.
4. THE PROPOSED WORK WILL HAVE NO EFFECT ON STRUCTURAL STABILITY. ALL WORK SHALL BE PERFORMED IN STRICT ADHERENCE WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS.
5. REFERENCE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES FOR GENERAL REQUIREMENTS.
6. THIS IS AN UNMANNED FACILITY- NO SOLID WASTE. THE SITE WILL CREATE NO TRASH, THUS REQUIRES NO DUMPSTER.
7. EQUIPMENT IS UNMANNED AND NOT FOR HUMAN HABITATION. HANDICAP ACCESS IS THEREFORE NOT REQUIRED.
8. OWNER & TENANT MAY, FROM TIME TO TIME AT TENANT'S OPTION, REPLACE THIS EXHIBIT WITH AN EXHIBIT SETTING FORTH THE LEGAL DESCRIPTION OF THE SITE, OR WITH ENGINEERED OR AS-BUILT DRAWING DEPICTING THE SITE OR ILLUSTRATING STRUCTURAL MODIFICATIONS OR CONSTRUCTION PLANS OF THE SITE. ANY VISUAL OR TEXTUAL REPRESENTATION OF THE EQUIPMENT LOCATED WITHIN THE SITE CONTAINED IN THESE OTHER DOCUMENTS IS ILLUSTRATIVE ONLY, AND DOES NOT LIMIT THE RIGHTS OF SPRINT AS PROVIDED FOR IN THE AGREEMENT. THE LOCATIONS OF ANY ACCESS AND UTILITY EASEMENTS ARE ILLUSTRATIVE ONLY. ACTUAL LOCATIONS MAY BE DETERMINED BY TENANT AND/OR THE SERVICING UTILITY COMPANY IN COMPLIANCE WITH LOCAL LAWS AND REGULATIONS.

PROJECT DESCRIPTION

APPLICANT PROPOSED TO INSTALL ANTENNAS AND WEATHERPROOF EQUIPMENT CABINETS FOR AN UNMANNED PERSONAL COMMUNICATIONS SYSTEM WIRELESS CALL SITE AT AN EXISTING TELECOMMUNICATIONS FACILITY. PROPOSED FACILITY IS NOT STAFFED AND IS VISITED ONCE A MONTH FOR MAINTENANCE PURPOSES ONLY; THEREFORE, SANITARY, SEWER, GAS, POTABLE WATER AND PLUMBING ARE NOT REQUIRED.



TO OBTAIN LOCATION OF PARTICIPANTS' UNDERGROUND FACILITIES BEFORE YOU DIG IN CONNECTICUT

CALL BEFORE YOU DIG 811 OR 1-800-922-4455

CONNECTICUT PUBLIC ACT 87-71 REQUIRES MIN. 2 WORKING DAYS NOTICE BEFORE YOU EXCAVATE.

DO NOT SCALE DRAWINGS:

CONTRACTOR SHALL VERIFY ALL PLANS & EXISTING DIMENSIONS & CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

APPROVALS

CONSTRUCTION
PROJECT MANAGER:

SITE ACQUISITION:

SPRINT
REPRESENTATIVE:

RF ENGINEER:

LANDLORD/ OWNER:

CONSTRUCTION DRAWINGS

Sprint®



UNIONVILLE/POLICE DEPT.
SITE#: CT33XC534
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

MONOPOLE SHEET INDEX

GENERAL:		STRUCTURAL:	
T-1	TITLE SHEET	S-1	STRUCTURAL DETAILS
SP-1	SPECIFICATIONS	UTILITY & GROUNDING:	
SP-2	SPECIFICATIONS	F-1	UTILITY & GROUNDING SITE PLAN & NOTES
SP-3	SPECIFICATIONS	F-2	UTILITY DETAILS
SITE:		F-3	GROUNDING DETAILS & NOTES
C-1	OVERALL SITE PLAN	F-4	GROUNDING DETAILS
A-1	EQUIPMENT PLAN	F-5	GROUNDING DETAILS
A-2	SITE ELEVATION & NOTES		
A-3	ANTENNA DETAILS & COAX SCHEDULE		
A-4	ANTENNA PLUMBING DIAGRAM & SPECIFICATIONS		
A-5	RF INFORMATION & COAX COLOR CODING		
A-6	EQUIPMENT DETAILS & SPECIFICATIONS		
A-7	EQUIPMENT DETAILS & SPECIFICATIONS		

PROJECT INFORMATION

APPLICANT ID: SITE NAME: UNIONVILLE/POLICE DEPARTMENT SITE #: CT33XC534		HOSPITAL UNIVERSITY OF CONNECTICUT HEALTH CENTER / JOHN DEMPSEY HOSPITAL 263 FARMINGTON AVENUE FARMINGTON, CT 06030 PH.: (860) 679-2000	
PROPERTY LANDLORD: TOWN OF FARMINGTON 1 MONTEITH DRIVE FARMINGTON, CT 06032 CONTACT: JEFFREY OLLENDORF PH.: (860) 675-2325		FIRE HOUSE TOWN OF FARMINGTON FIRE DEPARTMENT 1 MONTEITH DRIVE FARMINGTON, CT 06032 PH.: (860) 675-2322	
SITE ADDRESS: 319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY ZONING CLASSIFICATION: CR		APPLICANT: SPRINT 6391 SPRINT PARKWAY OVERLAND PARK, KS 66251	
SITE DATA: LATITUDE: 41°-44'-59.38" N (41.749828°) LONGITUDE: 72°-52'-21.72" W (-72.8727°) GROUND ELEVATION: 194 FT AMSL		PLANS PREPARED BY: RAMAKER & ASSOCIATES, INC. 1120 DALLAS STREET SAUK CITY, WI 53583 CONTACT: KEITH BOHNSACK, P.E., PROJECT MANAGER PH.: (608) 643-4100 FAX: (608) 643-7999	
POWER COMPANY: CONNECTICUT LIGHT & POWER PH.: (800) 286-2000		TELEPHONE COMPANY: AT&T PH.: (800) 288-2020	

Sprint®



6391 Sprint Parkway
Overland Park, KS 66251

Alcatel-Lucent



RAMAKER & ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 10/25/2012

A 10/25 FINAL PRELIM CD'S		
MARK	DATE	DESCRIPTION
ISSUE	FINAL PRELIMS	DATE ISSUED 10/25/2012
PROJECT TITLE: UNIONVILLE / POLICE DEPARTMENT SITE#: CT33XC534		
PROJECT INFORMATION: 319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY		
SHEET TITLE: TITLE SHEET		
SCALE: NONE		
PROJECT NUMBER	23009	
SHEET NUMBER	T-1	

DIVISION 1 - GENERAL REQUIREMENTS

SECTION 01100 - SCOPE OF WORK

PART 1 - GENERAL

- 1.1 THE WORK: These Standard Construction Specifications in conjunction with the other Contract Documents and the Construction Drawings describe the Work to be performed by the Contractor.
- 1.3 PRECEDENCE: Should conflicts occur between the Standard Construction Specifications for Wireless Sites including the Standard Construction Details for Wireless Sites and the Construction Drawings, information on the Construction Drawings shall take precedence. Notify Company designated representative of conflicts prior to construction.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
- A. The Work shall comply with applicable national codes and standards, latest edition, and portions thereof, included but not limited to the following:
 - 1. GR-63-CORE NEBS Requirements: Physical Protection
 - 2. GR-78-CORE Generic Requirements for the Physical Design and Manufacture of Telecommunications Equipment.
 - 3. National Fire Protection Association Codes and Standards (NFPA) including NFPA 70 (National Electrical Code - "NEC") and NFPA 101 (Life Safety Code).
 - 4. American Society for Testing of Materials (ASTM)
 - 5. Institute of Electronic and Electrical Engineers (IEEE)
 - 6. American Concrete Institute (ACI)
 - 7. American Wire Producers Association (AWPA)
 - 8. Concrete Reinforcing Steel Institute (CRSI)
 - 9. American Association of State Highway and Transportation Officials (AASHTO)
 - 10. Portland Cement Association (PCA)
 - 11. National Concrete Masonry Association (NCMA)
 - 12. Brick Industry Association (BIA)
 - 13. American Welding Society (AWS)
 - 14. National Roofing Contractors Association (NRCA)
 - 15. Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 - 16. Door and Hardware Institute (DHI)
 - 17. Occupational Safety and Health Act (OSHA)
 - 18. Applicable building codes including Uniform Building Code, Southern Building Code, BOCA, and the International Building Code.

SECTION 01300 - CELL SITE CONSTRUCTION

3.1 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. Contractor shall keep the site free from accumulating waste material, debris, and trash. At the completion of the work, Contractor shall remove from the site all remaining rubbish, implements, temporary facilities, and surplus materials.
- B. Equipment rooms shall at all times be maintained "broom clean" and clear of debris.
- C. Contractor shall take all reasonable precautions to discover and locate any Hazardous Condition.
- 1. In the event Contractor encounters any hazardous condition which has not been abated or otherwise mitigated, Contractor and all other persons shall immediately stop Work in the affected area and notify Company in writing. The Work in the affected area shall not be resumed except by written notification by Company.
 - 2. Contractor agrees to use care while on the Site and shall not take any action that will or may result in or cause the hazardous condition to be further released in the environment, or to further expose individuals to the hazard.
- D. Contractor's activities shall be restricted to the project limits. Should areas outside the project limits be affected by Contractor's activities, Contractor shall immediately return them to original condition
- E. Conduct testing as required herein.

DIVISION 2 - SITE CONSTRUCTION

SECTION 02300 - EARTHWORK

PART 3 - EXECUTION

- 3.4 TRENCHING AND BACKFILLING: The Contractor shall perform all excavation of every description and of whatever substances encountered, to the depths indicated on the Construction Drawings or as otherwise specified.
- A. Protection of Existing Utilities: The Contractor shall check with the local utilities and the respective utility locator companies prior to starting excavation operations in each respective area to ascertain the locations of known utility lines. The locations, number and types of existing utility lines detailed on the Construction Drawings are approximate and do not represent exact information. The Contractor shall be responsible for repairing all lines damaged during excavation and all associated operations. All utility lines uncovered during the excavation operations, shall be protected from damage during excavation and associated operations. All repairs shall be approved by the utility company.
- B. Hand Digging: Unless approved in writing otherwise, all digging within an existing cell site compound is to be done by hand.
- C. During excavation, material suitable for backfilling shall be stockpiled in an orderly manner a sufficient distance from the banks of the trench to avoid

overloading and to prevent slides or cave-ins. All excavated materials not required or suitable for backfill shall be removed and disposed of at the Contractor's expense.

- D. Grading shall be done as may be necessary to prevent surface water from flowing into trenches or other excavations, and any water accumulating therein shall be removed by pumping or by other approved method.
- E. Sheet piling and shoring shall be done as necessary for the protection of the work and for the safety of personnel. Unless otherwise indicated, excavation shall be by open cut, except that short sections of a trench may be tunneled if, the conduit can be safely and properly installed and backfill can be properly tamped in such tunnel sections. Earth excavation shall comprise all materials and shall include clay, silt, sand, muck, gravel, hardpan, loose shale, and loose stone.

F. Trenches shall be of necessary width for the proper laying of the conduit or cable, and the banks shall be as nearly vertical as practicable. The bottom of the trenches shall be accurately graded to provide uniform bearing and support for each section of the conduit or cable on undisturbed soil at every point along its entire length. Except where rock is encountered, care shall be taken not to excavate below the depths indicated. Where rock excavations are necessary, the rock shall be excavated to a minimum over depth of 6 inches below the trench depths indicated on the Construction Drawings or specified. Over depths in the rock excavation and unauthorized over depths shall be thoroughly back filled and tamped to the appropriate grade. Whenever wet or otherwise unstable soil that is incapable of properly supporting the conduit or cable is encountered in the bottom of the trench, such solid shall be removed to a minimum over depth of 6 inches and the trench backfilled to the proper grade with earth of other suitable material, as hereinafter specified.

G. Backfilling of Trenches. Trenches shall not be backfilled until all specified tests have been performed and accepted. Where compacted backfill is not indicated the trenches shall be carefully backfilled with select material such as excavated soils that are free of roots, sod, rubbish or stones, deposited in 6 inch layers and thoroughly and carefully rammed until the conduit or cable has a cover of not less than 1 foot. The remainder of the backfill material shall be granular in nature and shall not contain roots, sod, rubbing, or stones of 2-1/2 inch maximum dimension. Backfill shall be carefully placed in the trench and in 1 foot layers and each layer tamped. Settling the backfill with water will be permitted. The surface shall be graded to a reasonable uniformity and the mounding over the trenches left in a uniform and neat condition.

H. Except as otherwise required, compacted backfill shall be used under concrete pads, walkways, concrete paving, and asphalt concrete paving. The first 1 foot cover shall be of select materials such as excavated soils that are free of roots, sod, rubbish, or stones. The Company may reject any onsite or borrow materials which are considered unsuitable for the intended use of the fill.

- I. All fills shall be compacted to a dry density equal to at least 90 percent of the maximum dry density determined in accordance with ASTM D1557. The maximum density and optimum moisture content shall be determined by the Contractor on basis of laboratory tests conducted on the materials used in the fill.
- J. Adequacy of compaction shall be determined on the basis of in-place density determinations that shall be conducted by the Contractor while the fills are being placed. The results of these tests shall be the basis on which satisfactory completion of the work is judged. If the fills fail to meet the specified densities, the Contractor shall remove and recompact the soils until the specified densities are achieved.

3.6 REMOVAL OF WATER: The Contractor shall provide and maintain adequate dewatering equipment to remove and dispose of all surface and ground water entering excavations and other parts of the work. Each excavation shall be kept dry during sub-grade preparation and continually thereafter until the construction to be provided therein is completed to the extent that no damage from hydrostatic pressure, flotation, or other cause will result. Ground water level shall be maintained at least 12 inches below the bottom of each excavation. Removal of water shall be in accordance with all state, federal, and local regulations. Contractor shall submit water removal plan to the Company.

3.10 UNAUTHORIZED EXCAVATION: Except where otherwise authorized, indicated, or specified, all material excavated below the bottom of concrete structures which will be supported by the sub-grade shall be replaced with concrete placed monolithic with the concrete above. Material excavated below structures supported on piers shall be replaced with approved material. The material shall be compacted to a density equal to or greater than the density of the adjacent undisturbed soil.

3.11 STRUCTURE EXCAVATION: Excavation for structures shall be done to lines and elevations indicated on the Construction Drawings and to the limits required to perform the construction work.

A. Excavated materials free of trash, rocks, roots, and other foreign materials, and which meet the specified requirements, may be used as required for the fills, embankments, and backfills constructed under these specifications.

3.12 STABILIZATION: Sub-grades for structures and the bottom of trenches shall be firm, dense, and thoroughly compacted.

A. Trench sub-grades which run beneath roads, or pass through structural backfill, shall be compacted to 95 percent of maximum density as determined by ASTM D1557.

B. Sub-grades for structures and trench bottoms which are otherwise solid, but which become soft on top due to construction operations, shall be reinforced with one or more layers of crushed rock or gravel.

3.13 STRUCTURE BACKFILL: Backfill around and outside of structures shall be deposited in layers not to exceed 6 inches in uncompacted thickness and mechanically compacted, using acceptable compaction techniques, to at least 95 percent of maximum density as determined by ASTM D1557, with a moisture content of plus or minus 3 percent of optimum, as determined by ASTM D698 when that test is appropriate, or to 70 percent relative density as determined by ASTM D4253 and D4254 when those tests are appropriate. Compaction of structure backfill by rolling will be permitted provided the desired compaction is obtained and damage to the structure is prevented. Compaction of structure backfill by inundation with water will not be permitted.

A. Material for structure backfill shall be composed of earth only and shall contain no wood, grass, roots, broken concrete, stones, trash, or debris of any kind.

B. No backfill shall be deposited or compacted in water.

C. All backfill material shall consist of loose earth having a moisture content such that the required density of the compacted soil will be obtained with the compaction method used. Moisture content shall be distributed uniformly, and water for correction of moisture content shall be added sufficiently in advance so proper moisture distribution and compaction will be obtained. Granular material shall be wet, not just damp, when compacted.

D. Particular care shall be taken to compact structure backfill which will be beneath pipes, drives, roads, or other surface construction or structures. In addition, wherever a trench will pass through structure backfill, the structure backfill shall be placed and compacted to an elevation at least 12 inches above the top of the pipe before the trench is excavated.

3.18 DISPOSITION OF MATERIALS: Excess excavated earth and construction material shall be removed from the job site and legally disposed of by the Contractor.

DIVISION 3 - CONCRETE

SECTION 03300 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

Contact engineer or construction manager for complete concrete specifications if such work is required.

SECTION 03600 - GROUT

PART 1- GENERAL

Contact engineer or construction manager for complete grout specifications if such work is required.

DIVISION 5 - METALS

SECTION 05120 - ICE BRIDGE AND OTHER STRUCTURAL STEEL

PART 2 - PRODUCTS

2.1 ICE BRIDGE MATERIALS:

A. Ice Bridge posts shall be fabricated of 3-inch schedule 40 galvanized steel, ASTM A-53, Grade B (seamless). Posts shall be installed a minimum of 3 feet 6 inches below finish grade and backfilled with 3000 p.s.i. concrete. Post tops shall be capped with steel pipe caps. Maximum horizontal separation between posts shall be 8 feet on center.

B. Ice Bridge material shall be McNichols "Grip Strut" 10 diamond plank, 24 inches wide and 3 inches deep; part number 103014 or approved equal.

C. Ice Bridge components shall be hot dip galvanized and connected in an electrically continuous fashion per the manufacturer's recommendations. Any site penetrations or saw cuts to galvanized metal shall be treated with two coats of a zinc rich cold galvanizing paint as per ASTM A 780 standards.

2.2 STRUCTURAL STEEL MATERIALS: Conform to the latest edition of applicable standards and to all applicable codes and requirements of local authorities having jurisdiction, whichever is more stringent. All structural steel shall be in accordance with the latest applicable requirements of AISC, ASTM, ACI, CRSI, AWS and all other applicable standards.

2.3 All steel shall be galvanized in accordance with ASTM A36 unless noted on the construction drawings.

2.4 Rolled steel shapes, plates and bars shall be no less than 3/16 inches in thickness and shall comply with ASTM A-36 as a minimum.

2.5 Steel pipe shall comply with ASTM A-501 or ASTM A-53, Type E or S, Grade B. A-500 Grade B steel may be substituted.

2.6 Steel tube shall comply with ASTM A-500, Grade B.

2.7 Galvanized steel grating shall be a minimum 3/4 inch x 1/8 inch at 3 /16 inches on center.

2.8 Galvanized checkered plate shall be a minimum 3/16 inch.

PART 3 - EXECUTION

3.1 ICE BRIDGE:

A. The Contractor is responsible for installing an Ice Bridge and support posts between the BTS radio equipment and the tower. At no point shall the Ice Bridge structure be mechanically connected to the tower. Cabling supports shall be designed to accept snap-in type hangers and accommodate a minimum coax or waveguide bending radius of 20 inches.

B. Each tier shall be vertically and horizontally aligned with the cable entry ports on the shelter consisting of three tiers capable of holding 5 runs of 1-5/8 inch coaxial cable each for a total of 15 coaxial cables. The cover shall be aligned to allow for easy access to the cabling and be of sufficient width and durability to prevent damage to the cable that might otherwise be caused by falling ice, bolts, nuts or hand tools. The entire structure, including cover, shall be sufficiently rigid to prevent cable damage caused by movement of the structure. Cover shall continue to within 2 inches of shelter wall and waveguide ladder.

C. Provision shall be made to ground the Ice Bridge structure as specified in Division 16.

3.2 STRUCTURAL STEEL FABRICATION: All shop fabrication and assembly of structural steel shall be in accordance with AISC specifications and as indicated on the approved shop drawings. All materials shall be properly marked for field assembly and for identification as to the location for which it is intended. Materials shall be fabricated and delivered in an order to expedite erection and minimize field handling of materials.

3.3 WELDING:

A. Welding shall be performed by a certified welder and shall conform to requirements for shielded metal arc welding of the Standard Code for Arc and Gas Welding of the American Welding Society (AWS D1.1)

B. Electrodes shall comply with AWS Code and shall be classified E-70 electrodes as a minimum. Where finishing is required, complete the assembly, including welding of units, before the start of finishing operations. Provide finish surfaces of exposed members that are free from markings, burrs and other defects.

C. Welded construction shall comply with AWS Code for procedures, appearance and quality of welds and methods used in correcting welded work. Assemble and weld

built-up sections by methods that will produce correct dimensions without warp.

3.4 CONNECTIONS:

A. Contractor shall provide all hardware required to complete field erection of structure as indicated by Contract Documents or these specifications.

B. High strength threaded fasteners shall be installed in accordance with AISC Specifications for Structural Joints Using ASTM A-325 or A-490 Bolts. Use A-325N bearing-type connection bolts unless noted otherwise.

C. Grating and plates shall be fastened with saddle clips. The necessary holes to complete all phases of construction shall be provided and called out on the approved shop drawings. All holes shall be drilled or punched perpendicular to metal surfaces, flame cut or burned holes will not be permitted.

D. All unfinished threaded fasteners shall comply with ASTM A-307, Grade A, regular low-carbon steel bolts and nuts with hexagonal heads.

E. All high strength threaded fasteners shall be heavy hexagonal bolts and nuts with hardened washers, all from quenched and tempered medium carbon steel complying with ASTM A-325.

3.5 REPAIR: Repair all damaged galvanized steel with "Galvanox," "Dry Galv," or "Zinc-It," or approved equal, per the manufacturer's instructions.

SECTION 07500 - ROOF CUTTING, PATCHING AND REPAIR

PART 1 - GENERAL

1.4 SUBMITTALS:

A. Pre-Construction Roof Condition Analysis Reports: Complete a roof inspection and report prior to the installation of Sprint equipment on any rooftop build requiring roof penetration. At a minimum inspect all areas impacted by the addition of the Sprint equipment.

Roof inspection reports should be uploaded into SMS using task # 234.

B. New Roofing Material Product Data: Submit manufacturer's product data and installation instructions for each material and product used.

C. Shop Drawings: Provide large scale shop drawings for installation of all parts of the work. Provide plans, and details of seams, connections and accessory items. Show layouts of tapered insulation and locations of drains. Show interfaces and relationships to work of other trades.

D. Certification and Warranty:

- 1. Upon completion of work of this Section, submit certification by existing roof manufacturer acknowledging that all work performed is acceptable and that the entire roof remains under warranty.
- 2. Maintain existing warranty if applicable. Take no action which would void existing warranty.

PART 2 - PRODUCTS

2.1 MATERIALS:

A. Existing Roof Materials and Compatibility: Furnish specific product acceptable to manufacturer of roofing membrane which will not compromise the roofing manufacturer's warranty.

B. Substrate Board: Glass-mat, water-resistant gypsum ASTM C 1177 or match existing.

C. Vapor Retarder: Match existing.

D. Insulation: Extruded polystyrene board insulation, or match existing.

E. Tapered Insulation: Fabricated to provide proper drainage.

F. Recovery Board over Insulation: Match existing, mechanically fastened.

G. Membrane and Flashing: Match existing.

H. Sheet Metal Accessories: Follow SMACNA and NRCA recommendations. Materials and finishes to match existing.

I. Ballast: Match existing.

J. Walkway Protection Board: Compatible with membrane.

PART 3 - EXECUTION

3.1 INSTALLATION:

A. Inspect substrate and report unsatisfactory conditions in writing. Beginning work on site means Contractor's acceptance of existing roof conditions.

B. Comply with roof system manufacturer's instructions and recommendations on any penetrations, repairs, etc.

C. Install insulation with tightly butted joints and neatly fitted around penetrations.

D. Where applicable, distribute ballast uniformly to 10 pounds per square foot or more as required by Factory Mutual. Obtain approval of ballast weight from the building owner before loading roof.

E. Install walkway protection over an additional layer of membrane at locations indicated and where required to provide access to roof mounted equipment.

F. Restore or replace damaged components. Protect work from damage.

SECTION 07840 - FIRESTOPPING

PART 1 - GENERAL


1.5 QUALITY ASSURANCE:

A. Comply with governing codes and regulations. Provide products of acceptable manufacturers which have been in satisfactory use in similar service for three years. Use experienced installers. Deliver, handle, and store materials in accordance with manufacturer's instructions.

B. Fire Performance: ASTM E 119, ASTM E 814, and local regulations.



6391 Sprint Parkway
Overland Park, KS 66251





1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.





12/11/2012
Date:

A	10/25	FINAL PRELIM CDS
MARK	DATE	DESCRIPTION
ISSUE	FINAL PRELIMS	DATE ISSUED 10/25/2012
PHASE		
PROJECT TITLE: <div>UNIONVILLE / POLICE DEPARTMENT SITE#: CT33XC534</div>		
PROJECT INFORMATION: 319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY		
SHEET TITLE: <div>SPECIFICATIONS</div>		
SCALE: NONE		
PROJECT NUMBER	23009	
SHEET NUMBER	SP-1	

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.

SECTION 09910 - PAINTING

PART 2 - PRODUCTS

2.1 MATERIALS:

A.Manufacturers: Benjamin Moore, ICI Devco Coatings, PPG, Sherwin Williams or approved equal. Provide premium grade, professional-quality products for coating systems.

B.PAINT SCHEDULE:

- Interior Gypsum Drywall Walls and Ceilings: One coat latex primer plus two coats latex eggshell finish.
- Exterior and Interior Steel Doors, Frames and Ferrous Metals: One coat rust-inhibiting primer, plus two coats alkyd enamel semi-gloss finish.
- Exterior Antennae: One coat of primer and two finish coats. Paint for antennae shall be non-metallic based and contain no metallic particles. Submit MSDS sheet to the Owner for approval. Provide colors and patterns as required to mask appearance of antennae on adjacent building surfaces and as acceptable to the Owner. Refer to antenna manufacturer's instructions whenever possible.

SECTION 11007 - ANTENNA ASSEMBLY AND INSTALLATION

PART 2 - PRODUCTS

2.1 MATERIALS: Panel and Microwave Antennas: Refer to the Drawings for types and quantities. The following paragraphs outline the materials used for an Omni site and a sectored site.

B.Sectored Site:

- ESMR (Enhanced Specialized Mobile Radio) Panels: Located per project requirements.
- Microwave: High performance type, located per project requirements.
- GPS: Located on the south side of obstructions.

C.Antenna Mounts:

- Ballast mounts for rooftop applications shall be Valmont/Microflect No. 31-99540 (12 foot separation) or approved equal.
- Facade-mounted antennas shall comply with site-specific mounting requirements indicated on the Drawings.

D.Surge Arrestors:

- Refer to the drawings for types and quantities. All surge arrestors shall be models that are approved by the Company before installation.
- All surge arrestors for ESMR antennas shall terminate in 7/16 DIN connectors with MALE connectors toward the antenna and FEMALE toward equipment.
- All surge arrestors for GPS and microwave antennas shall be Type N with MALE connectors toward the antenna and FEMALE toward equipment.
- Surge arrestors shall be mounted on a trapeze or other grounding arrangement to ensure that surge currents are properly grounded.

E.Cross-Band Couplers: Refer to drawings for types and quantities. All couplers shall be models that are approved by the Company before installation.

F.Tower-Mounted Amplifiers (TMA or TTA): Refer to drawings for types, quantities, and mounting methods. All tower-mounted amplifiers shall be models that are approved by the Company before installation.

G.Low Noise Amplifiers (LNA): Refer to drawings for types, quantities, and mounting methods. All LNAs amplifiers shall be models that are approved by the Company before installation.

H.Connect antenna, coax, GPS, etc. to grounding system as indicated on the site plans and as indicated in Division 16.

PART 3 - EXECUTION

3.4 ANTENNA INSTALLATION:

A.The Contractor shall assemble all antennas onsite in accordance with the instructions supplied by the manufacturer. Antenna height, azimuth, and feed orientation information shall be a designated on the Construction Drawings. Azimuth delineation will be determined by appropriate RF Engineer.

B.Remote tilt antenna assemblies are to be completely assembled on the ground, run through their full range of motion using the controller and full cable assembly before being placed on the tower. Once installed, they are to be run through this process again prior to the tower crew leaving the site.

C.The serial numbers, azimuths, and downtilts are to be recorded and the information left on site for the RF and start up crew to use at the time of hand over to Field Operations.

D.The Contractor shall install all antennas and side struts in accordance with the Construction Drawings and the manufacturer's recommendations.

E.The Contractor shall position the antenna on tower pipe mounts so that the bottom strut is level. The pipe mounts shall be plumb.

F. Antenna Mounting Requirements: Refer to the Job Specifications for site specific antenna mounting details such as radiation centerlines, azimuths and antenna mount designs. Provide U-bolts and brackets to fasten antennas to side arms on pipe mounts. All mounts and mounting hardware shall be hot dipped galvanized or stainless steel material. All antenna installations shall conform to the following specifications.

- Panel Antennas: Panel antennas shall be fastened to the vertical pipe mounts on the sector head frame supplied with the tower. Adjust pipe mounts, as necessary, on the sector headframe to provide 12 feet of horizontal separation between the outer most panel antennas unless otherwise specified. If necessary, raise or lower the headframe to achieve the correct radiation centerline as per the Drawings.

G.Ballast Mounts: Install ballast mounts in accordance with manufacturer's

specifications and per the Construction Drawings and Details.

H.All unused antenna ports shall be terminated with a terminating load.

I. GPS antennas shall be installed at a location identified on the construction drawings. Effort should be made to locate GPS antennas on either the shelter or the ice bridge.

3.5 Coaxial Cables and Waveguide Installation:

A.The Contractor shall route, test, and install all coaxial cables as indicated on the Construction Drawings and in accordance with the manufacturer's recommendations.

B.The routing of the coax shall be checked for interference with other tower appurtenances before installation and vertical waveguide/coax hangers shall be installed on the tower waveguide ladder.

C.The coax shall be hoisted, connected to the antenna feed, secured to the hangers, and oriented to provide the correct entrance plane to the equipment cabinet. The waveguide/coax shall then be cut to the appropriate length to reach the equipment.

D.The waveguide/coax shall be grounded in accordance with the Construction Drawings and the Company grounding specifications Division 16.

E.The waveguide/coax shall be routed in accordance with the structural requirements. If possible, coax shall be routed on the inside of monopoles or down the waveguide ladder in a manner that will prevent obstruction of the climbing ladder. Additionally, the waveguide/coax shall be positioned in the best possible location to protect it from damage. The bending radius of the coax shall not be less than the manufacturer's specifications.

F.Extreme care shall be taken to avoid damage to the waveguide/coax during handling and installation. The Company will furnish to the Contractor port assignments, if applicable, prior to waveguide installation.

1. Waveguide Ladder (Lattice towers only: Waveguide ladders shall be used to support all coaxial cable, microwave waveguide cable and any baseband cable on the tower). One ladder, 18 cables wide, shall be mounted on the tower per the tower structural requirements. The rungs on the waveguide ladders shall be spaced a maximum of 4 feet apart.

2. Ice Bridge: An Ice Bridge will be installed between the tower and the shelter to support all cabling. Use stainless steel snap-in type hangers to support cables on the Ice Bridge. Provide a drip loop in all cabling between the base of the tower and the Ice Bridge. Install in accordance with manufacturer's specifications.

3. Fastening Cables: Waveguide and coaxial cable lines shall be raised on the tower using properly sized split type, lace-up hoisting socks attached to each cable every 200ft. All cables shall be permanently fastened to the tower using a hoisting sock at the top of the tower. Use stainless steel snap in type cable hangers at each wave guide ladder rung (on lattice towers only). Do not drill holes in tower members, use angle member adapters and stainless steel butterfly clips, to attach cabling to tower. Make sure that there is no strain on any cable connector due to the cable weight.

4. Jumpers: Jumpers between the feed lines and antennas or tower top amplifiers shall consist of 1/2 inch foam dielectric, outdoor rated coaxial cable. Do not use Superflex outdoors. Secure jumpers to the side arms or head frames using stainless steel tie wraps or stainless steel butterfly clips. Be certain that there is no strain on any connector due to the weight of the jumper cable, or its method of installation.

5. Bending Radius: Cables shall not exceed the minimum bending radius as determined by the cable manufacturer.

6. Cable Installation:

a. Inspect cable prior to use for shipping damage, notify the Company Representative of any damage. Any cable ends cut shall be covered to protect them from weather and entry of foreign matter. If using bulk cable, field attach antenna connector before hoisting cable.

b. Cable Routing: Cable installation shall be planned to ensure that the lines will be properly routed in a neat and orderly manner. Avoid twisting and crossovers in the building, along the tower face, and waveguide raceways. Secure cable at maximum spacing of 4 feet on center making sure that the cable weight is equally distributed and no strain is placed on connectors or antennas.

c. Hoist cable using proper hoisting grips. Hoist slowly and carefully. Prevent kinking and snags when around tower members. Bend cable slowly at the maximum practical bend radius consistent with good installation practice. Avoid using minimum cable bends.

7. Termination at Shelter and Entry Plate:

a. All cabling shall enter the building through the waveguide entry plate and be properly weather sealed with a cable boot fabricated for the size of the cable. Cable boots are not to be cut to fit in the field. Coaxial cables shall be terminated within 18 inches inside the shelter and fitted with a surge suppressor.

b. Coax Port Assignments for Shelter Sites: The coax will be installed and marked per the Antenna Transmission Line Acceptance Standards and the Detail - Coax Port Assignments.

8. Grounding of transmission lines: All transmission lines shall be grounded in accordance with the Company grounding standards.

9. Labeling Coaxial Cables: All cables shall be marked with 2 inch UV resistant colored tape and stencil tagged per the latest version of the RF Antenna Transmission Line Acceptance Standards. All coaxial cables shall be at the top, bottom, both sides of the entry port and all locations where the cable penetrates a wall, ceiling or floor. Antenna locations should be determined from the reference point of standing in the center of the tower looking out. Labeling should be adherent with industry standard for T1 transmit and receive.

10. Cable Connections:

a. Use only cable connectors recommended by the cable manufacturer.

b. Connectors for all main station antenna cables shall be 7/16 DIN.

c. Connectors for GPS antennas shall be Type N.

d. Connectors for microwave antennas, unless otherwise noted, shall be Type N.

e. Install and tighten connectors per manufacturer's instructions.

f. All exterior connectors, connector splices, jumpers, ground kits, etc., shall be weatherproofed using connector/splice weather proofing kits. Weatherproofing shall be installed in strict accordance with manufacturer's instructions.

3.6 WEATHERPROOFING CONNECTORS AND GROUND KITS:

A.All connectors and ground kits shall be weatherproofed using butyl rubber weatherproofing and tape. This installation must be done in accordance with the manufacturer's recommendation or as shown on the construction drawings (whichever is greater). If no direction is provided, weatherproofing must be done per Sprint Standard Construction Specification for Wireless Sites Section 11007-3.6 A-D.

SECTION 11008 - BASE TRANSCEIVER STATIONS (BTS) AND RELATED EQUIPMENT INSTALLATION

PART 3 - EXECUTION

3.1 GENERAL: The Contractor shall install the BTS and associated equipment at the locations shown on the Construction Drawings and in accordance with the manufacturer's recommendations. Minimum requirements for performance of the work are:

A. Contractor shall be responsible for all services associated with the delivery, bolt-down and installation of Sprint Nextel's radio equipment.

B. Equipment installation procedures shall fully comply and strictly adhere to original equipment manufacturer's installation instructions. Contractor shall immediately cease any work if inconsistencies are found between Sprint Nextel Standards and the manufacturer's documentation. Contractor shall seek guidance from Sprint Nextel or its designated project representative for resolution.

C. Contractor shall provide a fully functioning and operable radio system at the wireless facility. Contractor shall complete and provide all documentation of the Work.

3.1 CONTRACTOR PROVIDED MATERIAL: Contractor shall obtain by any means necessary the original equipment manufacturer specifications and strictly adhere to them. Contractor shall provide all required tools, test equipment, materials, labor, and equipment including anchor kits and external mounting hardware for positioning and securing final bolt-down of the radio equipment. Contractor shall furnish all necessary grounding products to successfully bond the radio equipment to the site ground ring or shelter grounding system in accordance with the construction drawings.

3.2 WORK SCHEDULING: Contractor shall provide and coordinate scheduling of licensed electrician qualified to perform the work of connecting the power and grounding to the radio equipment along with any other connections or installations of radio equipment requiring a licensed electrician per the manufacturer specifications.

3.3 MISC WORKS:

A. Contractor shall remove radio equipment from crates, wrapping, or pallets and properly dispose of all packaging materials. Contractor shall verify the proper radio equipment is being installed at the correct site. The equipment is assigned a site specific asset number and must be installed at the designated location.

B. Contractor shall measure equipment platform, pad, interior space or shelter space and verify exact equipment layout in accordance with the construction drawings and set the radio equipment accordingly. Contractor shall set equipment cabinets and racks in the locations indicated on the construction drawings or as otherwise directed by Sprint Nextel or its designated project representative in writing.

C. Contractor shall install batteries, rectifiers, additional RF carriers, EV-DO cards, amplifiers, circuit packs, and all other radio equipment for the site as required by the manufacturer specifications.

D. Contractor shall ensure GPS is installed and ready for connection to the BTS. Contractor shall install or coordinate for the installation of the Global Positioning System (GPS) antenna via the construction contractor and as specified by the manufacturer as applicable.

E. Contractor shall procure and install:

- DC wiring with conduit or cable tray as indicated between power supply cabinets and radio cabinets as shown on the Construction Drawings.
- AC wiring from Load center to power supply or radio cabinet in conduit or cable tray as indicated in the manufacturer specifications.
- Circuit breakers in spare sockets in the Load Center as indicated in the manufacturer specifications.
- Alarm cabling from radio equipment to telco alarm terminal strip in conduit or cable tray. Contractor shall be responsible to extend conduit or cable tray as necessary to successfully complete the work.
- T1 and alarm cables extending conduit or cable tray as necessary to successfully complete the work.

6. Jumpers from the coax main line feeds to the radio equipment. Contractor is to perform Sweep testing of lines or coordinate with construction contractor to perform this activity.

F. Contractor shall energize the equipment according to manufacturer specifications and conduct functionality tests of the AC and DC power systems correcting any deficiencies in the work as applicable.

DIVISION 16 - ELECTRICAL

SECTION 16000 - BASIC ELECTRICAL REQUIREMENTS

PART 1 - GENERAL

1.4 CODES AND STANDARDS:

A.The codes and standards referenced in Division 16 shall be the most current revision, regardless of the actual year indicated hereinafter, except as otherwise required by Division 1.

B.The entire electrical installation shall comply fully with the requirements of all authorities having jurisdiction.

C.The Work shall comply with applicable requirements of the following:

- U.S. National Electrical Code (NEC),
- U.S. National Fire Protection Association (NFPA) codes and standards,
- U.S. Occupational Safety and Health Act (OSHA),
- Other Codes and Standards as referenced in the individual technical sections of Division 16.

PART 2 - PRODUCTS

2.1 MATERIALS AND EQUIPMENT: All materials and equipment specified in Division 16 of the same type shall be of the same manufacturer and shall be new, of the best quality and design, and free from defects.

2.2 FIRESTOPPING MATERIAL:

A.Firestopping Material: Subject to compliance with requirements. Provide one or more of the following:

- Spec Seal PEN 300 Sealant by STI
- Spec Seal "Type SSP100" Firestop Mastic/Putty by STI
- Spec Seal "Type SSB" Firestop Pillows by STI
- Similar products by Nelson or 3M

PART 3 - EXECUTION

3.3 INSTALLATION:

A.Verify all dimensions by field measurements.

B.Sequence, coordinate, and integrate installations of materials and equipment for efficient flow of the Work. Give particular attention to large equipment requiring positioning prior to the closing of a structure.

C.All cutting and channeling shall be accomplished in a neat and workmanlike manner, without the removal of excess materials. Contractor shall patch, replace and repair all cut and channeled areas with material similar to adjacent construction.

D.Coordinate connection of systems with exterior underground and overhead utilities and services. Comply with requirements of governing regulations, franchised service companies and controlling agencies. Provide required connection for each service.

E.Coordinate location of all equipment, boards, lights, outlets, switches, boxes, conduits, electrical trays with other services and utilities. Locate all equipment, fixtures and conduits to clear windows, door openings and other services and utilities. Route conduits so as to clear valves and other similar obstructions requiring access. Follow manufacturer's recommendations for installation methods not otherwise specified.

F.Equipment shall be installed at locations shown on the drawings. Any changes to locations of installed equipment, facilities, or other appurtenances shall be noted as "Red-Lines" and submitted with "As-Built" package upon project completion. All changes require appropriate Project Manager pre-approval

G.Working spaces and accessibility shall not be less than specified in the National Electrical Code for all voltages and equipment specified.

3.4 FIRESTOPPING: Apply firestopping material as recommended by the manufacturer to maintain the fire resistance rating of the barrier being penetrated. Utilize suitable templates or dams to properly retain material in large openings.

3.5 SUPPORTING DEVICES:

A.Install supporting devices to fasten electrical components securely and permanently in accordance with NEC.

B.Coordinate with the building structural system and with other trades.

C.Raceway supports shall conform to the manufacturer's recommendations for selection and installation of supports.

D.The strength of each support shall be adequate to carry the present and future load multiplied by a safety factor of at least four. Where this determination results in a safety allowance of less than 200 pounds, provide additional strength until there is a minimum of 200 pounds safety allowance in the strength of each support.

E.Install individual and multiple (trapeze) raceway hangers and riser clamps as necessary to support the raceways. Provide U-bolts, clamps, attachments, and other hardware necessary for hanger assembly and for securing hanger rods and conduits.

F.Support parallel runs of horizontal raceways together on trapeze-type hangers.



6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S
ISSUE	PHASE	DATE ISSUED
	FINAL	10/25/2012

PROJECT TITLE:
UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534

PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:

SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	23009
SHEET NUMBER	SP-2

- G.Support miscellaneous electrical components as required to produce the same structural safety factors as specified for raceway supports. Install metal channel racks for mounting cabinets, panelboards, disconnects, control enclosures, pull boxes, junction boxes, transformers and other devices.
- H.In open overhead spaces, cast boxes threaded to raceways need not be supported separately except where used for fixture support. Support sheet metal boxes directly from the building structure or by bar hangers. Where bar hangers are used, attach the bar to raceways on opposite sides of the box and support the raceway with a listed type of fastener not more than 24" (600 mm) from the box.
- I. Install conduit sealing fittings for conduit penetrations of concrete wall exterior or below grade as specified or required by code.
- J.Unless otherwise indicated on the drawings, fasten electrical items and their supporting hardware securely to the structure in accordance with the following:
1. Fasten by means of wood screws on wood,
 2. Toggle bolts on hollow masonry units,
 3. Concrete inserts or expansion bolts on concrete or solid masonry,
 4. Machine screws, welded threaded studs, or spring-tension clamps on steel,
 5. Explosive devices for attaching hangers to structure shall not be permitted.
 6. Do not weld conduit, pipe straps, or items other than threaded studs to steel structures.
 7. In partitions of light steel construction, use sheet metal screws.
- K.Ensure that the load applied by any fastener does not exceed 25 percent of the proof test load.
- L. Use vibration and shock-resistant fasteners for attachments to concrete slabs.

SECTION 16001 - ELECTRICAL MATERIALS AND EQUIPMENT

PART 2 - PRODUCTS

2.1 DISCONNECT SWITCHES:

- A.Furnish and install externally operated, quick-make, quick-break, safety, fused and non-fused heavy duty disconnect switches where shown on the drawings and where required by NEC. Switches shall be safety type as manufactured by Square "D", I-T-E, Cutler-Hammer/Westinghouse, GE, or approved equal.
- B.Switches shall be rated for horsepower of motors controlled. Indoor switches shall be mounted in NEMA 1 enclosures, except as indicated. Switches located exterior to building shall be mounted in NEMA 3R enclosures except as indicated. Switches utilized as service entrance equipment shall be so labeled.
- C.Disconnect switches shall be provided at all equipment.
- D.Furnish Class R fuse kits for all fused switches utilizing RK-1 or RK-5 fuses.

2.2 CIRCUIT BREAKERS FOR INSTALLATION INTO PANELBOARDS:

- A.For application in panelboards, provide circuit breakers of the same manufacturer as the Original Equipment Manufacturer (OEM) panel, integral to the cabinet.
- B.Circuit breaker configuration (bolt-on or clip-on) shall match that of breakers installed and shipped with the cabinet.
- C.Amps Interrupting Capacity (AIC) of field supplied and installed circuit breakers shall not be less than the printed withstand and interrupting rating of the load center.

2.3 SEPARATELY ENCLOSED CIRCUIT BREAKERS:

- A.Furnish and install where indicated molded case circuit breakers, trip indicating, trip free, thermal magnetic type with electrical characteristics and ratings as indicated. Short circuit withstand and interrupting rating shall be as required by the fault current indicated.
- B.Provide NEMA 1 enclosures indoor, NEMA 3R outdoor enclosure except as otherwise indicated. Circuit breaker handles shall be lockable in the OFF position.
- C.Provide service entrance label where indicated.
- D.Provide equipment by Square "D", General Electric, Siemens, or Cutler-Hammer/Westinghouse.

2.7 CABLE TRAY:

- A.Furnish and install a complete cable tray system as indicated on the drawings and as manufactured by B-Line Systems, Inc., Square "D" Company or approved equal.
- B.Cable tray, fittings and accessories shall be steel, hot-dipped galvanized after fabrication or aluminum as indicated.
- C.Cable tray shall be ladder-type, trough-type, channel-type, or as indicated.
- D.Cable tray system shall be furnished with all dimensions, covers, necessary tees, crosses, risers, elbows, connectors, hangers, etc. of same material as cable tray and as shown on drawings and as required by cable tray manufacturer.
- E.Barriers shall be installed in cable tray to separate cables of different systems such as low and high voltage, telephone, data, etc. Barriers shall be of same material as cable tray.
- F.Cable tray shall be installed level and, plumb in accordance with manufacturer's instructions.

2.9 COMMUNICATION CABLING FOR CELL SITE T1 CIRCUITS:

- A.This specification applies to the T1 circuit to be installed by this Contractor between the Network Interface Unit (NIU) and the Company radio equipment.
- B.In indoor locations and in underground conduits in dry climates cabling shall be PVC-insulated tinned solid copper 24 - 24 AWG twisted pairs, UL Type CMR, with overall braided shield and PVC jacket, except as otherwise recommended by the manufacturer.
- C.In underground conduits in wet climates, provide Outdoor plant cable, gel filled,

24 - 24AWG twisted pairs.

D.Exception: In all cases for installations in Lucent BTS markets, utilize the T1 cable shipped with the BTS, whenever the cable length is sufficient for the installation.

E. Adhere to Bellcore standards for cable color coding.

2.12 GROUNDING ELECTRODES AND CONDUCTORS:

- A.Comply with Exhibit C - Cell Site Grounding Design.
- B.Equipment Grounding Conductor:
1. Bare copper conductor or insulated green wire ground as specified herein.

2.13 BOXES AND COVERS:

- A.Pull and junction boxes shall be sized in accordance with NEC requirements and shall be installed so that the conductors in them are accessible without removing any part of the structure.
- B.Interior switch and outlet boxes flush mounted in finished areas shall be code gauge pressed plated steel, Midland Ross or approved equal, suitable for the device to be installed. Covers shall be as hereinafter specified in paragraph "Device Plates in Finished Areas."
- C.Device and pull boxes surface-mounted above accessible ceilings and within unfinished enclosed Mechanical rooms shall be as specified above sized for the conductors within and shall have pressed plated steel screw attached covers.
- D.Interior switch, pull, junction and outlet boxes surface mounted in unfinished industrial areas shall be (cast aluminum or) plated cast alloy, threaded, suitable for the device to be installed, Crouse-Hinds FS/FD series or approved equal. Covers shall be screw attached plated iron alloy suitable for the box and device. Switch plate covers shall be "guarded" style.
- E.Pull boxes exterior to the building and in interior industrial areas shall be plated cast alloy, heavy duty, weatherproof, dust proof, with gasket, plated iron alloy cover and stainless steel cover screws, Crouse-Hinds WAB series or equal.
- F.Conduit outlet bodies shall be plated cast alloy with similar gasketed covers. Outlet bodies shall be of the configuration and size suitable for the application. Provide Crouse-Hinds Form 8 or equal.
- G.Exterior switch and outlet boxes shall be recessed mounted except as noted, cast aluminum or plated cast alloy with wet location, Crouse-Hinds series WLRD covers, or equal. Masonry boxes mounted recessed in exterior wall shall be furnished with weatherproof covers.
- H.Manufacturer for boxes and covers shall be Hoffman, Square "D", Crouse-Hinds, Cooper, Adalet, Appleton, O-Z Gedney, Raco, or approved equal.

2.21 LIGHTNING PROTECTION:

- A.Comply with the latest revisions of Exhibit D - Cell Site Lightning - Surge Protection and Exhibit C - Cell Site Grounding Design.

2.26 SURGE SUPPRESSION

- A.Except as otherwise required, surge suppression devices are Company furnished materials

PART 3 - EXECUTION

3.1 GROUNDING:

- A.Electrical services, circuits and systems, enclosures and equipment shall be grounded in accordance with Article 250 of the National Electrical Code.
- B.Grounding shall be provided as indicated for feeder, branch circuit, control, and instrument circuits.
- C.Equipment Grounding Conductor: Furnish and install a separate insulated green wire grounding conductor with circuit conductors for all feeders and branch circuits.
- D.Furnish and install an insulated green wire grounding conductor in non-metallic raceways unless designated otherwise for telephone or data cables.
- E.Telephone and communication system services, circuits, enclosures and equipment shall be grounded in accordance with paragraph 800-33 and paragraph 800-40 of the National Electrical Code.
- F.Separately derived AC systems that are required to be grounded by the NEC shall be grounded in accordance with paragraph 250-26 of the NEC.

G.Furnish and install insulated copper ground conductors in conduit from main electrical service equipment or electrical room ground bus and connect to main metallic water service entrance (if available) with ground clamps. Connect ground conductor to the street side of water main where a dielectric main water fitting is installed.

H.Furnish and install ground fault protection where required by code and as required by the specifications and drawings. Installation of ground fault protection shall be in accordance with NEC.

3.3 CONDUIT AND CONDUCTOR INSTALLATION:

- A.Conduit and conductors shall be sized as required by NEC and shall be installed continuous and complete from outlet to outlet, panels and junction boxes.
1. In order to closely follow the lines of the structure, maintain close proximity to the structure and keep conduits in tight envelopes. Changes in direction to route around obstacles shall be made with conduit outlet bodies in exposed locations except as otherwise indicated, and in accordance with good construction practice.
 2. Other changes in direction shall be made with trade elbows, keeping conduits grouped in tight envelopes following the lines of the structure and maintaining close proximity to the structure except as otherwise indicated, and in accordance with good construction practice.
 3. Route conduits according to the envelopes, areas, details and sections, if any, identified on the drawings.
- B.Conduits shall be fastened securely in place with approved non-perforated straps

and hangers. Explosive devices for attaching hangers to structure will not be permitted. Conduits shall be concealed in finished areas. Conduit shall be exposed in unfinished areas.

C.Conduit shall be installed in a neat and workmanlike manner, parallel and perpendicular to structure wall and ceiling lines. Conduit shall be installed as required by the design of the structure and placed in concrete forms so as not to interfere with reinforcing or strength of slabs, joists or beams. Conduit shall clear all pipes and ducts and depressions in floors. Permission of Engineer shall be obtained as to location of conduit in reinforced concrete slabs, joists and beams.

D.All conduit shall be fished to clear obstructions. Ends of conduits shall be temporarily capped to prevent concrete, plaster or dirt from entering.

E.Conduits shall be rigidly clamped to boxes by galvanized malleable iron bushing on inside and galvanized malleable iron locknut on outside and inside.

F.EMT conduits (if allowed) shall have approved EMT threaded type box connectors and couplings. Set screw connectors and couplings shall not be acceptable.

G.Conductors shall be pulled in accordance with accepted good practice. Where more than one conductor is installed in the same conduit all conductors within the conduit shall be pulled simultaneously. Pull shall not deform conductors. Approved type lubricant may be used in pulling conductors where required.

H.Splices and taps shall be kept to a minimum and made in accordance with the NEC.

I. Where conduit crosses an expansion joint, an expansion and deflection fitting shall be installed in the conduit.

J. Conduit Entrance Seals:

1. All conduits penetrating new concrete walls exterior or below grade shall be sealed at penetrations with conduit entrance seal, Type FSK by O-Z/Gedney or approved equal.
2. All conduit penetrating existing concrete walls exterior or below grade shall be sealed on both sides with O-Z/Gedney Type CSML seals.

K.Conduits and cables passing through all floors, fire rated walls, and smoke partitions shall be sealed in accordance with NEC-300-21. Furnish and install O-Z/Gedney fire seal fittings or approved equal at those locations. At the Contractor's option, Specified Technologies Inc. Model PEN200, UL-Listed fire resistant silicone foam sealant installed in accordance with the manufacturer's recommendations may be utilized. All unused openings and sleeves shall be sealed as herein specified.

L. A #16 gauge (1.3 mm2) steel pull wire shall be left in all empty conduits.

M.PVC conduits shall be installed using fittings, solvents, glues, and methodology as recommended by the manufacturer.

N.Provide adequate length of conductors within electrical enclosures and train the conductors to terminal points with no excess. Do not bend conductors sharper than eight times the cable outside diameter. Make terminations so there is no bare conductor at the terminal. Bundle multiple conductors, with conductors larger than No. 10 AWG in individual circuit bundles.

O.Tighten electrical connectors and terminals, including screws and bolts, in accordance with the manufacturer's published torque tightening values. Where manufacturer's torquing requirements are not indicated, tighten connectors and terminals to comply with tightening torques specified in UL 486A and 486B.

P.Utilize flexible liquid tight conduit for final connection in exterior, damp wet, or corrosive locations, and elsewhere as indicated on the drawings.



6391 Sprint Parkway
Overland Park, KS 66251

Alcatel•Lucent







RAMAKER
& ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.





Signature:


12/11/2012

Date:

A	10/25	FINAL PRELIM CD'S
MARK	DATE	DESCRIPTION
ISSUE PHASE	FINAL PRELIM'S	DATE ISSUED 10/25/2012
PROJECT TITLE: UNIONVILLE / POLICE DEPARTMENT SITE#: CT33XC534		
PROJECT INFORMATION: 319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY		
SHEET TITLE: SPECIFICATIONS		
SCALE: NONE		
PROJECT NUMBER	23009	
SHEET NUMBER	SP-3	


I:\23000\23009\CAD\Telecom\Working\23009 Vision Project-CT.dwg Printed by: steves on Dec 11, 2012 - 1:39pm

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.



GENERAL NOTES:

1. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES ORDINANCES, LAWS, AND REGULATIONS OF ALL MUNICIPALITIES, UTILITIES COMPANY, OR OTHER PUBLIC AUTHORITIES.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY, OR MUNICIPAL AUTHORITIES.
3. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER, IN WRITING, OF ANY CONFLICTS, ERRORS OR OMISSIONS PRIOR TO THE SUBMISSION OF BIDS OR PERFORMANCE OF WORK. MINOR OMISSIONS OR ERRORS IN THE BID DOCUMENTS SHALL NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR THE OVERALL INTENT OF THESE DRAWINGS.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING SITE IMPROVEMENTS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED AS A RESULT OF CONSTRUCTION OF THE FACILITY.
5. THE SCOPE OF WORK FOR THIS PROJECT SHALL INCLUDE PROVIDING ALL MATERIALS, EQUIPMENT, AND LABOR REQUIRED TO COMPLETE THIS PROJECT. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
6. THE CONTRACTOR SHALL VISIT THE PROJECT SITE PRIOR TO SUBMITTING A BID TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
7. CONTRACTOR SHALL VERIFY ANTENNA ELEVATION AND AZIMUTH WITH RF ENGINEERING PRIOR TO INSTALLATION.
8. TRANSMITTER EQUIPMENT AND ANTENNAS ARE DESIGNED TO MEET ANSI/EI/ATA 222-G REQUIREMENTS.
9. ALL STRUCTURAL ELEMENTS SHALL BE HOT DIPPED GALVANIZED STEEL.
10. CONTRACTOR SHALL MAKE A UTILITY "ONE-CALL" TO LOCATE ALL UTILITIES PRIOR TO EXCAVATING.
11. IF ANY UNDERGROUND UTILITIES OR STRUCTURES EXIST BENEATH THE PROJECT AREA, CONTRACTOR MUST LOCATE IT AND CONTACT THE APPLICANT & THE OWNER'S REPRESENTATIVE.
12. OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION BY TECHNICIANS APPROXIMATELY 2 TIMES PER MONTH.
13. RAMAKER & ASSOCIATES HAS NOT PERFORMED A STRUCTURAL ANALYSIS FOR THIS PROJECT. PRIOR TO THE INSTALLATION OF THE PROPOSED EQUIPMENT OR MODIFICATION OF THE EXISTING STRUCTURE, A STRUCTURAL ANALYSIS SHALL BE PERFORMED BY SPRINT'S AGENT TO CERTIFY THAT THE EXISTING/PROPOSED COMMUNICATION STRUCTURE AND COMPONENTS ARE STRUCTURALLY ADEQUATE TO SUPPORT ALL EXISTING AND PROPOSED ANTENNAS, COAXIAL CABLES, AND OTHER APPURTENANCES.
14. PROPERTY LINE INFORMATION WAS PREPARED USING DEEDS, TAX MAPS, AND PLANS OF RECORD AND SHOULD NOT BE CONSTRUED AS AN ACCURATE BOUNDARY SURVEY.
15. THIS PLAN IS SUBJECT TO ALL EASEMENTS AND RESTRICTIONS OF RECORD.
16. THE PROPOSED FACILITY WILL CAUSE ONLY A "DE MINIMIS" INCREASE IN STORMWATER RUNOFF; THEREFORE, NO DRAINAGE STRUCTURES ARE PROPOSED.
17. NO SIGNIFICANT NOISE, SMOKE, DUST, OR ODOR WILL RESULT FROM THIS FACILITY.
18. THE FACILITY IS UNMANNED AND NOT INTENDED FOR HUMAN HABITATION (NO HANDICAP ACCESS REQUIRED).
19. POWER TO THE FACILITY WILL BE MONITORED BY A SEPARATE METER.



SITE PLAN
SCALE: 1" = 7.5'



Sprint
6391 Sprint Parkway
Overland Park, KS 66251

Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.
1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

**NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET**

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S
ISSUE	DATE	DESCRIPTION
PHASE	10/25/2012	FINAL PRELIM'S
PROJECT TITLE:		
UNIONVILLE / POLICE DEPARTMENT		
SITE#: CT33XC534		


PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
OVERALL SITE PLAN

0 3.75' 7.5' 15'


11" x 17" - 1" = 7.5'
22" x 34" - 1" = 3.75'

PROJECT NUMBER: 23009
SHEET NUMBER: C-1



EXISTING EQUIPMENT PLAN
SCALE: 1" = 5'

1



PROPOSED EQUIPMENT PLAN
SCALE: 1" = 5'

2



6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION MMBTS LAUNCH NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012


MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S

ISSUE PHASE	DATE ISSUED
FINAL PRELIMS	10/25/2012

PROJECT TITLE:
UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534

PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
EQUIPMENT PLAN



11" x 17" - 1" = 5'
22" x 34" - 1" = 2.5'


PROJECT NUMBER: 23009

SHEET NUMBER: A-1

NOTES:

- I. SCOPE
- A. THIS SECTION COVERS THE SPECIFICATIONS FOR ANTENNA AND COAXIAL CABLE INSTALLATION OF: ANTENNAS, COAXIAL, CONNECTIONS, AND ICE BRIDGE.
- B. REFERENCE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES FOR GENERAL REQUIREMENTS.
- II. ANTENNAS:
- A. ANTENNAS SHALL BE PLUMB AND INSTALLED SO THAT THE ENTIRE WHIP EXTENDS ABOVE VERTICAL PIPE MOUNT. DIRECTIONAL ANTENNAS SHALL BE ORIENTED TO PROPER AZIMUTH, PROVIDED ON THE RF SPECIFICATION SHEET. NOTE: THE ANTENNA MAY BE ORIENTED USING THE REFLECTOR AS THE REFERENCE, ADJUSTING ITS AZIMUTH 180 DEGREES FROM MAXIMUM ANTENNA RADIATION.
- B. MICROWAVE ANTENNAS (DISHES) SHALL BE ASSEMBLED PER MANUFACTURER'S DRAWINGS. STIFF ARMS AND RADOMES SHALL BE INSTALLED WITH POLARIZATION PROVIDED BY RF SPECIFICATION SHEET. IF PATH IS NOT READY TO ALIGN, DISH SHOULD BE POINTED TOWARD CALCULATED AZIMUTH, OR DIRECTION OF FIELD STAKE DENOTING OPPOSITE END. 2 STIFF ARMS SHALL BE PROVIDED FOR MICROWAVE DISHES 6'-0" IN DIAMETER OR GREATER.
- C. A TRANSIT SHALL BE USED TO PROPERLY ALIGN CELLULAR AND MICROWAVE ANTENNAS.
- III. COAXIAL CABLE:
- A. COAXIAL CABLE SHALL BE SUPPORTED WITH SNAP-IN HANGERS. SNAP-IN HANGERS SHOULD BE USED EVERY 3 FEET THE ENTIRE HEIGHT OF THE TOWER. ANGLE ADAPTERS OR ROUND MEMBER ADAPTERS WITH BUTTERFLY CLAMPS SHALL BE USED ELSEWHERE, I.E. SIDEARMS, PLATFORMS, AND MICROWAVE MOUNTS.
- B. COAXIAL CABLE SHALL ALSO BE SUPPORTED WITH HOISTING GRIPS, INSTALLED AT MAXIMUM INTERVALS OF 200 FEET. HOISTING GRIPS SHALL BE ATTACHED WITH SHACKLES, BOLTED IN THE 7/16" HOLE OF WAVEGUIDE LADDER.
- C. ALL JUMPERS USED BETWEEN COAXIAL CABLE AND ANTENNA SHALL BE SUPPORTED WITHIN 18 INCHES OF ANTENNA, USING BUTTERFLY CLAMPS WITH ANGLE ADAPTERS OR ROUND MEMBER ADAPTERS AROUND PIPES. CELLULAR ANTENNAS TYPICALLY USE 6' JUMPERS; MICROWAVE DISHES USE 3' JUMPERS.
- D. COAXIAL CABLE SHALL BE NEATLY BENT WHEN REQUIRED, USING A MINIMUM BENDING RADIUS OF 10 TIMES THE DIAMETER OF THE COAXIAL CABLE. DRIP LOOPS SHOULD BEGIN AT THE ICE BRIDGE. THE END IN THE COAXIAL CABLE SHOULD BE AT A LOWER HEIGHT THAN THE ENTRY PORT.
- E. COAXIAL CABLE SHALL BE SUPPORTED WITH SNAP-IN HANGERS ON THE WAVEGUIDE LADDER UNDER ICE BRIDGE. COAXIAL CABLE SHOULD BE NEATLY CUT 1/6" INSIDE BUILDING AND TERMINATED AT THE QUARTER WAVE SHORTS.
- F. CONNECTORS WILL NORMALLY BE PROVIDED FIRST OFF REEL FROM FACTORY. CONNECTORS TERMINATED IN BUILDING SHALL BE NEATLY INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
- G. COAXIAL CABLES SHOULD BE LABELED WITH TAGS INSIDE THE BUILDING.
- H. USE 2" WIDE COLORED TAPE TO INDICATE SECTORS. CONTRACTOR TO USE SECTOR COLOR CODING AS INDICATED IN THESE DRAWINGS OR AS PROVIDED BY SPRINT.
- I. ALL EXCEPTIONS NEED TO BE VERIFIED WITH THE PROJECT MANAGER.
- IV. CONNECTORS:
- A. ALL CONNECTIONS AND GROUNDING KITS SHALL BE WEATHERPROOFED USING COLD SHRINK OR ANDREW APPROVED WEATHER STRIPPING. NOTE: NO PORTION OF CONNECTOR SHALL BE EXPOSED TO THE ELEMENTS.
- B. COAXIAL CABLE SHALL BE GROUNDED USING GROUNDING KITS AT THE TOP (BELOW THE BEND), BOTTOM (ABOVE THE BEND ON TOWER GROUND BAR), AND ON BUILDING GROUND BAR BEFORE ENTRY INTO WAVEGUIDE PORTS. 4" CABLE BOOTS SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.
- C. GROUNDING KITS SHALL BE NEATLY INSTALLED SO THAT THE JUMPER RUNS IN THE SAME DIRECTION AS THE COAXIAL AND GROUND BAR. JUMPER WIRE SHOULD RUN IN A DIRECT PATH TO THE GROUND BAR/ TOWER LADDER, BUT HAVE ADEQUATE SLACK FOR EXPANSION, CONTRACTION, AND REPAIR. NON-OXIDE GREASE SHOULD BE APPLIED BETWEEN LUG AND BAR/TOWER.
- D. TOWER GROUND BAR SHALL BE INSTALLED ON THE ANGLE BEHIND THE FIRST DIAGONAL WAVEGUIDE LADDER RUNG, ABOVE 8'-6". GROUND BAR SHALL BE ISOLATED FROM ANGLE USING NEWTON BUSHINGS PROVIDED.

INSTALL ADDITIONAL COLLAR MOUNT WITHIN SPRINT LEASE RAD FOR MOUNTING (1) 1900 & (1) 800 MHZ RRH UNITS AT EACH SECTOR, SEE DETAIL 2/5-1



ELEVATION
SCALE: 1" = 20'

Sprint

6391 Sprint Parkway
Overland Park, KS 66251


Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

**NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET**

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Ramaker* Date: 12/11/2012

A	10/25	FINAL PRELIM CD'S
MARK	DATE	DESCRIPTION
ISSUE	DATE	
PHASE	ISSUED	10/25/2012

PROJECT TITLE:
**UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534**


PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
**SITE ELEVATION
& NOTES**

0 10' 20' 40'

11" x 17" - 1" = 20'
22" x 34" - 1" = 10'

PROJECT NUMBER: 23009
SHEET NUMBER: A-2



ANTENNA AND COAXIAL CABLE SCHEDULE											
SECTOR	POS.	AZIMUTH	ANTENNA CENTERLINE	ANTENNA STATUS	TECH.	ANTENNA MAKE/ MODEL	MECH. DOWNTILT (°)	ELEC. DOWNTILT (°)	RRHs	CABLE SIZE	CABLE LENGTH
BETA	B-1	90°	170'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
	B-2	90°	170'-0"	EX. TO REMAIN	CLEARWIRE	-	-	-	-	-	-
	B-3	90°	170'-0"	PROPOSED	MULTIMODAL	RFS/ APXV5PP18-C-A20	1900 (0), 800 (0)	1900 (-1), 800 (-5)	(1) 1900, (1) 800	(1) 1 1/4" HYBRIFLEX HYBRID CABLE RFS #HB114-1-0813U4-M5F	± 225'-0"
	B-4	90°	170'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
GAMMA	G-1	210°	170'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
	G-2	210°	170'-0"	EX. TO REMAIN	MULTIMODAL	RFS/ APXV9EER18-C-A20	1900 (0), 800 (0)	1900 (0), 800 (-2)	(1) 1900, (1) 800	(1) 1 1/4" HYBRIFLEX HYBRID CABLE RFS #HB114-1-0813U4-M5F	± 225'-0"
	G-3	210°	170'-0"	EX. TO REMAIN	CLEARWIRE	-	-	-	-	-	-
	G-4	210°	170'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-
ALPHA	A-1	330°	170'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	-	-
	A-2	330°	170'-0"	EX. TO REMAIN	CLEARWIRE	-	-	-	-	-	-
	A-3	340°	170'-0"	PROPOSED	MULTIMODAL	RFS/ APXV5PP18-C-A20	1900 (0), 800 (0)	1900 (-1), 800 (-8)	(1) 1900, (1) 800	(1) 1 1/4" HYBRIFLEX HYBRID CABLE RFS #HB114-1-0813U4-M5F	± 225'-0"
	A-4	330°	170'-0"	EX. TO BE REMOVED	CDMA	-	-	-	-	EX. TO BE REMOVED	-

6391 Sprint Parkway
Overland Park, KS 66251

1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

**NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET**

Certification & Seal:
I hereby certify that the plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

Signature: *James R. Skowron* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S
ISSUE	DATE	DESCRIPTION
PHASE	DATE	DESCRIPTION

PROJECT TITLE:
**UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534**


PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
**ANTENNA DETAILS
& COAX SCHEDULE**

SCALE: NONE

PROJECT NUMBER	23009
SHEET NUMBER	A-3

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.



TOWER TOP SCENARIO 124



Power Feed Polarity Definition:
IF wires are BLACK AND BLACK/WHITE STRIPE:
Black= -48VDC Feed (Battery)
Black/White Stripe= Return

IF wires are RED AND BLACK:
Red= -48VDC Feed (Battery)
Black= Return

NOTE: For power feed use the same Hybriflex OEM color designator as the fiber.

MM Pair 1= F1= Green= P1(Green)
MM Pair 2= F2= Blue= P2(Blue)
MM Pair 3= F3= Red= P3(Red)
MM Pair 4= F4= Yellow= P4(Yellow)
MM Pair 5= F5= Orange= (No P5 power feed)

2 HYBRIFLEX OEM COLOR CODE
BD1 SCALE: N.T.S.



ANTENNA PLUMBING DIAGRAM
SCALE: NTS

RFS

Product Data Sheet APXV9ERR18-C

Triple Band Dual Polarized Antenna, 806-1995, 80deg, 14-17dBi, 1.8m, VET, 0-10deg, 0.5m AISG Cable

Product Description

This antenna is an ideal choice for dual band site upgrade for high traffic areas. It features 4 ports in 1900 MHz and 2 ports in 800 MHz.

Features/Benefits

- Variable electrical downtilt - provides enhanced precision in controlling intercell interference. The tilt is infield adjustable 0-10 deg.
- High suppression of all upper sidelobes (Typically < 18 dB)
- Independent control of electrical downtilt for 800 and PCS bands
- Low profile for low visual impact
- Quick and easy to adjust
- High front-to-back ratio
- AISG compatible remote tilt available - Add suffix -A20 to the model number

Technical Specifications

Electrical Specifications

	806-869	1850-1995	1850-1995
Frequency Range, MHz	806	80	80
Horizontal Beamwidth, deg	11.5	5.5	5.5
Vertical Beamwidth, deg		0-10	
Electrical Downtilt, deg	14 (11.9)	17 (14.9)	17 (14.9)
Gain, dBi (dBd)		>18	
1st Upper Sidelobe Suppression, dB, typ. @ 10° & 18°	>30	>27	>27
Front-to-Back Ratio, dB, @ 180° ± 15°	>30	Dual pol +/-45°	>27
Polarization		>14	
Return Loss, dB		>28	
Isolation between Ports, dB		>110	
3rd Order IMP @ 2 x 43 dBm, @ 2 min. duration	>20	>20	>20
Cross Polar Discrimination (XPD) 0°, dB	>5	>11	>11
Cross Polar Discrimination (XPD) ± 60°, dB	>5	>5	>5
HBW Squint across same band ports, °	50	50	50
Impedance, Ohms		250	
Maximum Power Input, W		Direct Ground	
Lightning Protection		(6) 7-16 DIN Female	
Connector Type			

Mechanical Specifications

Dimensions - HxWxD, mm (in)	1829 x 302 x 200 (72.0 x 11.8 x 7.9)
Weight w/o Mtg Hardware, kg (lb)	28.2 (62)
Rated Wind Speed, km/h (mph)	241 (150)
Radome Material	ASA
Radome Color	Light Grey RAL7035
Mounting Hardware Material	Decasted Aluminum and Galvanized Steel

Ordering Information

Mounting Hardware	APM40-2 Downtilt Kit
AISG System Cable	0.5 m, included
Mounting Pipe Diameter, mm (in)	60-120 (2.4-4.7)
Mounting Hardware Weight, kg (lb)	3.4 (7.5)

ANTENNA SPECIFICATIONS
SCALE: NTS

Product Data Sheet APXV5PP18-C

Triple Band Dual Polarized Antenna, 806-1995, 65deg, 16-18dBi, 1.8m, VET, 0-10deg, 0.5m AISG Cable

Product Description

This antenna is an ideal choice for dual band site upgrade for high traffic areas. It features 4 ports in 1900 MHz and 2 ports in 800 MHz.

Features/Benefits

- Variable electrical downtilt – provides enhanced precision in controlling intercell interference. The tilt is infield adjustable 0-10 deg.
- High suppression of all upper sidelobes (Typically < 18 dB)
- Independent control of electrical downtilt for 800 and PCS bands
- Low profile for low visual impact
- Quick and easy to adjust
- High front-to-back ratio
- AISG compatible remote tilt available – Add suffix -A20 to the model number

Technical Specifications

Electrical Specifications

	806-869	1850-1995	1850-1995
Frequency Range, MHz	65	65	65
Horizontal Beamwidth, deg	11.5	5.5	5.5
Vertical Beamwidth, deg	0-10	0-10	0-10
Electrical Downtilt, deg	15.5 (13.4)	18.0 (15.9)	18.0 (15.9)
Gain, dBi (dBd)	>27	>18	>18
1st Upper Sidelobe Suppression, dB, typ. @ 10° & 18°	>30	>27	>27
Front-to-Back Ratio, dB, @ 180° ± 15°	>30	Dual pol +/-45°	>27
Polarization	>14	>14	>14
Return Loss, dB	>28	>28	>28
Isolation between Ports, dB	>110	>110	>110
3rd Order IMP @ 2 x 43 dBm, @ 2 min. duration	>15	>11	>11
Cross Polar Discrimination (XPD) 0°, dB	>5	>11	>11
Cross Polar Discrimination (XPD) ± 60°, dB	>5	>5	>5
HBW Squint across same band ports, °	50	50	50
Impedance, Ohms	250	250	250
Maximum Power Input, W	Direct Ground	Direct Ground	Direct Ground
Lightning Protection	(6) 7-16 DIN Female	(6) 7-16 DIN Female	(6) 7-16 DIN Female
Connector Type			

Mechanical Specifications

Dimensions - HxWxD, mm (in)	1829 x 302 x 178 (72.0 x 11.8 x 7)
Weight w/o Mtg Hardware, kg (lb)	25.8 (57)
Rated Wind Speed, km/h (mph)	241 (150)
Radome Material	ASA
Radome Color	Light Grey RAL7035
Mounting Hardware Material	Decasted Aluminum and Galvanized Steel

Ordering Information

Mounting Hardware	APM40-2 Downtilt Kit
AISG System Cable	0.5 m, included
Mounting Pipe Diameter, mm (in)	60-120 (2.4-4.7)
Mounting Hardware Weight, kg (lb)	3.4 (7.5)

Sprint
6391 Sprint Parkway
Overland Park, KS 66251

Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.
1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

**NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET**

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.

STATE OF CONNECTICUT
JAMES R. SKOWRONSKI
PROFESSIONAL ENGINEER
12/11/2012

PROJECT TITLE: UNIONVILLE / POLICE DEPARTMENT SITE#: CT33XC534

PROJECT INFORMATION: 319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

SHEET TITLE: ANTENNA PLUMBING DIAGRAM & SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER: 23009
SHEET NUMBER: A-4


Market	Northern Connecticut		
	Cascade ID	CT33XC534	
	SECTOR 1	SECTOR 2	SECTOR 3
Split sector present	NO	NO	NO
1900MHz_Azimuth	340	90	210
1900MHz_No_of_Antennas	1	1	1
1900MHz_RADCenter(ft)	170	170	170
1900MHz_Antenna Make	RF5	RF5	RF5
1900MHz_Antenna Model	APXVSP18-C-A20	APXVSP18-C-A20	APXV9ERR18-C-A20
1900MHz_Horizontal_Beamwidth	65	65	80
1900MHz_Vertical_Beamwidth	5.5	5.5	5.5
1900MHz_AntennaHeight (ft)	6	6	6
1900MHz_AntennaGain(dBd)	15.9	15.9	14.9
1900MHz_E_Tilt	-1	-1	0
1900MHz_M_Tilt	0	0	0
1900MHz_Carrier_Forecast_Year_2013	2	2	2
1900MHz_RRH Manufacturer	ALU	ALU	ALU
1900MHz_RRH Model	RRH 1900 4X45 65MHz	RRH 1900 4X45 65MHz	RRH 1900 4X45 65MHz
1900MHz_RRH Count	1	1	1
1900MHz_RRH Location	Top of the Pole/Tower	Top of the Pole/Tower	Top of the Pole/Tower
1900MHz Combiner Model	No Combiner needed	No Combiner needed	No Combiner needed
1900MHz_Top_Jumper #1_Length (RRH or Combiner-to-Antenna, ft)	10	10	10
1900MHz_Top_Jumper #1_Cable_Model (RRH or Combiner-to-Antenna)	LCF12-50J	LCF12-50J	LCF12-50J
1900MHz_Top_Jumper #2_Length (RRH-to-Combiner, ft)	N/A	N/A	N/A
1900MHz_Top_Jumper #2_Cable_Model (RRH-to-Combiner)	N/A	N/A	LCF12-50J
1900MHz_Main_Coax_Cable_Length (ft)	N/A	N/A	N/A
1900MHz_Main_Coax_Cable_Model	N/A	N/A	N/A
1900MHz_Bottom_Jumper #1_Length (Ground-based-RRH-OR_Combiner-to-Main-Coax, ft)	0	0	0
1900MHz_Bottom_Jumper #1_Cable_Model (Ground-based-RRH-OR_Combiner-to-Main-Coax)	0	0	0
1900MHz_Bottom_Jumper #2_Length (Ground-based-Combiner-to-Main-Coax)	0	0	0
1900MHz_Bottom_Jumper #2_Cable_Model (Ground-based-Combiner-to-Main-Coax)	0	0	0
800MHz_Azimuth	340	90	210
800MHz_No_of_Antennas	0	0	0
800MHz_RADCenter(ft)	170	170	170
800MHz_AntennaMake	RF5	RF5	RF5
800MHz_AntennaModel	APXVSP18-C-A20 (Shared w/1900)	APXVSP18-C-A20 (Shared w/1900)	APXV9ERR18-C-A20 (Shared w/1900)
800MHz_Horizontal_Beamwidth	65	65	80
800MHz_Vertical_Beamwidth	11.5	11.5	10.5
800MHz_AntennaHeight (ft)	6	6	6
800MHz_AntennaGain (dBd)	13.4	13.4	11.9
800MHz_E_Tilt	-8	-5	-2
800MHz_M_Tilt	0	0	0
800MHz_RRH Manufacturer	ALU	ALU	ALU
800MHz_RRH Model	800 MHz RRH 2x50W	800 MHz RRH 2x50W	800 MHz RRH 2x50W
800MHz_RRH Count	1	1	1
800MHz_RRH Location	Top of the Pole/Tower	Top of the Pole/Tower	Top of the Pole/Tower
800MHz_Top_Jumper #1_Length (RRH or Combiner-to-Antenna, ft)	10	10	10
800MHz_Top_Jumper_Cable_Model (RRH or Combiner-to-Antenna)	LCF12-50J	LCF12-50J	LCF12-50J
800MHz_Main_Coax_Cable_Length (ft)	N/A	N/A	N/A

RF INFORMATION
SCALE: NTS

1

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Blue	No Tape	No Tape
1	3	Brown	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Slate	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Blue	Blue	No Tape
2	3	Brown	Brown	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Slate	Slate	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Blue	Blue	Blue
3	3	Brown	Brown	Brown
3	4	White	White	White
3	5	Red	Red	Red
3	6	Slate	Slate	Slate
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange

Frequency	Indicator	ID
800 #1	Yellow	Green
1900 #1	Yellow	Red
1900 #2	Yellow	Brown
Reserved	Yellow	Blue
Reserved	Yellow	Slate
Reserved	Yellow	Orange
Reserved	Yellow	White
1600 #1	Yellow	Purple



COLOR CODING CHARTS
SCALE: NTS

2



6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION MMBTS LAUNCH NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012


A	10/25	FINAL PRELIM CD'S
MARK	DATE	DESCRIPTION
ISSUE	DATE	ISSUED
PHASE	10/25/2012	FINAL PRELIM'S

PROJECT TITLE:
UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534
PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
RF INFORMATION &
COAX COLOR CODING


SCALE: NONE

PROJECT NUMBER: 23009
SHEET NUMBER: A-5



FRONT VIEW

REAR VIEW



BOTTOM VIEW

BOTTOM VIEW -
CLEARANCE
FOR FRONT DOOR


Cabinets	Configuration	Shipped Weight including pallet (estimate)	Maximum Installed Weight (estimate)	Reference Dimensions (Width x Depth x Height)
9928 Distributed Base Station Outdoor Cabinet with Integrated Power	Half loaded <ul style="list-style-type: none">CDMAOne BBUOne 7210One SAR 8Three DC-DC convertors	470 kg (1033 lbs)	430 kg (945 lbs)	900 mm x 960 mm x 1925 mm (35.4 inches x 37.8 inches x 75.8 inches)
	Fully loaded <ul style="list-style-type: none">CDMAFour BBUsTwo 7210sOne SAR 8Six DC-DC convertors8 Injectors	529 kg (1162 lbs)	489 kg (1074 lbs)	

9928 DISTRIBUTED BASE STATION
OUTDOOR CABINET DETAIL
SCALE: NTS

1



FRONT VIEW
GOECv2 BATTERY CABINET
(FRONT DOOR REMOVED)



REAR VIEW
GOECv2 BATTERY CABINET
(REAR PANEL REMOVED)

General Specifications


Cabinet Dimensions:	Height: 60 in. (152.4 cm)
	Width: 31 in. (78.7 cm)
	Depth: 30 in. (76.2 cm)
Approximate Weight:	425 lbs., (Empty)
Cabinet Operating Temperature Range:	-40°C to 46°C

BATTERY CABINET DETAILS
SCALE: NTS

2




6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION MMBTS LAUNCH NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared
by me or under my direct supervision and that I am a duly Licensed
Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S

ISSUE	DATE	DATE
PHASE	FINAL PRELIMS	ISSUED 10/25/2012

PROJECT TITLE:
UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534
PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
EQUIPMENT DETAILS
& SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER	23009
SHEET NUMBER	A-6

1900MHz 4X40W Remote Radio Head (RRH)

Capacity & Features

CDMA / LTE Multi technology RRH 65MHz bandwidth (PCS A-G Band)

- Sprint is free to deploy any combination of CDMA (1XRTT or EVDO) and LTE carriers in Sprint's spectrum up to 160 Watts of RF power.
- E.g. "A block" and "G block" both with 4 branch MIMO (4Tx & 4Rx)

2 CPRI Optical Connections for multi-carrier LTE and CDMA (1X & DO)

Power Supply: -48 VDC



Power Consumption: 700W Typical

Dimensions:

- Size: 282 x 271.5 x 637mm (11.1" x 10.69" x 25.1")
- Volume: 49 Liter
56 liters with solar shield & mounting OD

Weight: 27 kg (59.5 lbs)

Operating Temp range -40°C/+55°C



Alcatel-Lucent's 65MHz RRH satisfies Sprint's requirements.

3 | Sprint RAN Solution | January 2011

Alcatel-Lucent - Confidential
Solely for authorized persons having a need to know
Proprietary - Use pursuant to Company Instruction

Alcatel-Lucent

800MHz 2X50W Remote Radio Head (RRH)

Simultaneous CDMA & LTE Multi technology RRH 862-869 MHz

- Any combination of CDMA and LTE carriers supported by 100W RF Power

2 CPRI-like Optical Connections for daisy chaining

Software Switchable External Filter for use before

Public Safety is cleared

Dimensions: w/o Filter w/ Filter

- Height: 480 mm (19") 480 mm (19")
- Width: 330 mm (13") 330 mm (13")
- Depth: 218 mm (8.6") 310 (12.2")
- Weight: 24 kg (53 lbs) 29 kg (64 lbs)
- 49 liters, <29kg


Power Supply: -48 VDC

Power Consumption: <400W Typical


Operating Temp range -40°C to +55°C

Option to mount on Ground at tower base

Front/Top View



Bottom View



Alcatel-Lucent's 800 RRH satisfies Sprint's requirements.

2 | Sprint RAN Solution | January 2011

Alcatel-Lucent - Confidential
Solely for authorized persons having a need to know
Proprietary - Use pursuant to Company Instruction

Alcatel-Lucent

RRH UNIT DETAILS

SCALE: NTS

1

Product Data Sheet HB114-1-0813U4-M5F

HYBRIFLEX™ RRH Hybrid Feeder Cabling Solution, 1-1/4", Multi-Mode Fiber

Product Description

RFS' HYBRIFLEX Remote Radio Head (RRH) hybrid feeder cabling solution combines optical fiber and DC power for RRHs in a single lightweight aluminum corrugated cable, making it the world's most innovative solution for RRH deployments.

It was developed to reduce installation complexity and costs at Cellular sites. HYBRIFLEX allows mobile operators deploying an RRH architecture to standardize the RRH installation process and eliminate the need for and cost of cable grounding. HYBRIFLEX combines optical fiber (multi-mode or single-mode) and power in a single corrugated cable. It eliminates the need for junction boxes and can connect multiple RRHs with a single feeder. Standard RFS CELLFLEX® accessories can be used with HYBRIFLEX cable. Both pre-connectorized and on-site options are available.

Features/Benefits

- Aluminum corrugated armor with outstanding bending characteristics - minimizes installation time and enables mechanical protection and shielding
- Outer conductor grounding - Eliminates typical grounding requirements and saves on installation costs
- Lightweight solution and compact design - Decreases tower loading
- Robust cabling - Eliminates need for expensive cable trays and ducts
- Installation of tight bundled fiber optic cable pairs directly to the RRH - Reduces CAPEX and wind load by eliminating need for interconnection
- Optical fiber and power cables housed in single corrugated cable - Saves CAPEX by standardizing RRH cable installation and reducing installation requirements
- Outdoor polyethylene jacket - Ensures long-lasting cable protection

Technical Specifications

Structure

Outer Conductor Armor:	Corrugated Aluminum	[mm (in)]	36.0 (1.42)
Jacket:	Flame Retardant, Polyethylene, PE	[mm (in)]	39.0 (1.54)
UV-Protection:	Individual and External Jacket	Yes	
Standards (Meets or exceeds)			UL1569

Mechanical Properties

Weight, Approximate	[kg/m (lb/ft)]	1.78 (1.20)
Minimum Bending Radius, Single Bending	[mm (in)]	200 (8)
Minimum Bending Radius, Repeated Bending	[mm (in)]	500 (20)
Recommended Maximum Clamp Spacing	[m (ft)]	1.0 / 1.2 (3.25 / 4.0)

Electrical Properties

DC-Resistance Outer Conductor Armor	[Ω/km (Ω/1000ft)]	0.9 (0.27)
DC-Resistance Power Cable, 8.4mm (8AWG)	[Ω/km (Ω/1000ft)]	2.1 (0.64)

Fiber Optic Properties

Version		Multi-mode
Quantity, Fiber Count		5 pairs
Core/Clad	[μm]	50/125
Primary Coating (Acrylate)	[μm]	245
Buffer Diameter, Nominal	[μm]	900
Secondary Protection, Jacket, Nominal	[mm (in)]	2.0 (0.08)
Standards (Meets or exceeds)		UL94-V0, UL1666 RoHS Compliant

DC Power Cable Properties

Size	[mm² (AWG)]	8.4 (8)
Quantity, Wire Count		4 (2 pairs)
Size	[mm² (AWG)]	13.3 (6)
Quantity, Wire Count		4 (2 pairs)
Type		UV protected
Strands		19
Primary Jacket Diameter, Nominal	[mm (in)]	6.1 (0.24)
Standards (Meets or exceeds)		NFPA 130, RoHS Compliant ICEA S-95-658 UL Type XHHW-2, UL 44 UL-LS Limited Smoke, UL VW-1 IEEE-383 (1974), IEEE1202/FT4

Environment

Installation Temperature	[°C (°F)]	-30 to +65 (-22 to 149)
Operation Temperature	[°C (°F)]	-40 to +65 (-40 to 149)

* This data is provisional and subject to change.

RFS




Figure 1: HYBRIFLEX Series (Typical)




Figure 2: Construction Detail

HYBRID CABLE SPECIFICATIONS

SCALE: NTS

2



6391 Sprint Parkway
Overland Park, KS 66251




1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION MMBTS LAUNCH NORTHERN CT MARKET

Certification & Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CDS

ISSUE PHASE	FINAL PRELIMS	DATE ISSUED	10/25/2012
-------------	---------------	-------------	------------

PROJECT TITLE:
**UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534**

PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
**EQUIPMENT DETAILS
& SPECIFICATIONS**

SCALE: NONE


PROJECT NUMBER	23009
SHEET NUMBER	A-7

STRUCTURAL NOTES


- DESIGN REQUIREMENTS PER INTERNATIONAL BUILDING CODE 2009 AND THE TIA-222-G STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND ANTENNA SUPPORTING STRUCTURES.
- INFORMATION SHOWN ON THESE DRAWINGS WAS OBTAINED BY FIELD MEASUREMENTS AND FROM THE EXISTING STRUCTURAL DRAWINGS. THE GENERAL CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND NOTIFY THE ARCHITECT/ENGINEER OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIALS OR PROCEEDING WITH CONSTRUCTION.
- THE GENERAL CONTRACTOR AND HIS SUB-CONSULTANTS SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS WHICH MAY BE REQUIRED FOR THE WORK.
- STRUCTURAL STEEL SHALL CONFORM TO THE LATEST EDITION OF THE AISC SPECIFICATIONS FOR STRUCTURAL STEEL BUILDINGS- ALLOWABLE STRESS DESIGN AND PLASTIC DESIGN INCLUDING THE COMMENTARY AND THE AISC CODE FOR STANDARD PRACTICE.
- STRUCTURAL STEEL PLATES AND SHAPES SHALL CONFORM TO ASTM A992. ALL STRUCTURAL STEEL PIPES SHALL CONFORM TO ASTM A53 GRADE B. ALL STRUCTURAL STEEL COMPONENTS AND FABRICATED ASSEMBLIES SHALL BE HOT DIP GALVANIZED AFTER FABRICATION.
- WELDING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF AMERICAN WELDING SOCIETY (AWS) STRUCTURAL WELDING CODE- STEEL WELD ELECTRODES SHALL BE E70XX.
- ALL COAXIAL CABLE CONNECTORS AND TRANSMITTER EQUIPMENT SHALL BE AS SPECIFIED BY THE OWNER AND IS NOT INCLUDED IN THESE CONSTRUCTION DOCUMENTS. THE CONTRACTOR SHALL FURNISH ALL CONNECTION HARDWARE REQUIRED TO SECURE THE CABLES. CONNECTION HARDWARE SHALL BE STAINLESS STEEL.
- ALL THREADED STRUCTURAL FASTENERS FOR ANTENNA SUPPORT ASSEMBLIES SHALL CONFORM TO ASTM A307 OR ASTM A36. ALL STRUCTURAL FASTENERS FOR STRUCTURAL STEEL FRAMING SHALL CONFORM TO ASTM A325. FASTENERS SHALL BE $\frac{3}{8}$ " MIN. DIAMETER BEARING TYPE CONNECTIONS WITH THREADS INCLUDED IN THE SHEAR PLANE. ALL EXPOSED FASTENERS, NUTS, AND WASHERS SHALL BE GALVANIZED UNLESS OTHERWISE NOTED. CONCRETE EXPANSION ANCHORS SHALL BE HILTI KWIK BOLTS UNLESS OTHERWISE NOTED.
- LUMBER (IF APPLICABLE) SHALL COMPLY WITH THE REQUIREMENTS OF AMERICAN INSTITUTE OF TIMBER CONSTRUCTION AND THE NATIONAL FOREST PRODUCTS ASSOCIATION'S NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION. ALL LUMBER SHALL BE PRESSURE TREATED AND SHALL BE STRUCTURAL GRADE NO. 2 OR BETTER.
- IF APPLICABLE, ROOF PROTECTION PADS UNDER THE CONCRETE PAVERS AND WAVEGUIDE SUPPORTS SHALL BE 0.30" THICK RUBBER FIRESTONE PROTECTION PADS. THE ROOF PROTECTION PADS SHALL EXTEND A MINIMUM OF TWO INCHES BEYOND THE PERIMETER OF THE PAVERS AND THE WOOD SLEEPERS AND SHALL BE PLACED WITH A MINIMUM $\frac{1}{2}$ " SPACE BETWEEN ADJACENT PADS TO FACILITATE DRAINAGE. PROVIDE A 28 LB. INORGANIC PAD DIRECTLY ON THE ROOF. REMOVE ALL LOOSE STONES PRIOR TO PLACING THE SEPARATOR SHEET.
- NORTH ARROW SHOWN ON PLANS REFERS TO TRUE NORTH. CONTRACTOR SHALL VERIFY TRUE NORTH AND INFORM CONSTRUCTION MANAGER OF ANY DISCREPANCY BEFORE STARTING CONSTRUCTION.

NOTE:


FINAL ANTENNA MOUNT DESIGN AND/OR MODIFICATIONS PENDING STRUCTURAL ANALYSIS.



ANTENNA MOUNTING DETAIL
SCALE: NTS




FIBER BOX MOUNTING FRAME
SCALE: NTS



PART NUMBER	DESCRIPTION	PIPE	U-BOLT	WEIGHT
MTC3286B	RRU MOUNT BASE KIT	-	-	89.16 LBS
MTC328635	RRU MOUNT WITH 3 1/2" PIPE	MT54772	GUB-4355	229.95 LBS

RRH MOUNTING DETAIL
SCALE: NTS



GPS MOUNTING DETAIL
SCALE: NTS



6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer in the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S
ISSUE	DATE	DESCRIPTION
PHASE	FINAL PRELIMS	DATE ISSUED 10/25/2012

PROJECT TITLE:
UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534
PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
STRUCTURAL DETAILS

SCALE: NONE

PROJECT NUMBER: 23009
SHEET NUMBER: S-1


GENERAL NOTES:

1. OBTAIN PERMITS AND PAY FEES RELATED TO ELECTRICAL WORK PERFORMED ON THIS PROJECT. DELIVER COPIES OF ALL PERMITS TO SPRINT.
2. SCHEDULE AND ATTEND INSPECTIONS RELATED TO ELECTRICAL WORK REQUIRED BY JURISDICTION HAVING AUTHORITY. CORRECT AND PAY FOR ANY WORK REQUIRED TO PASS ANY FAILED INSPECTION.
3. REDLINED AS-BUILTS ARE TO BE DELIVERED TO SPRINT REPRESENTATIVE.
4. PROVIDE TWO COPIES OF OPERATION AND MAINTENANCE MANUALS IN THREE-RING BINDER.
5. FURNISH AND INSTALL THE COMPLETE ELECTRICAL SYSTEM, TELCO SYSTEM, AND THE GROUNDING SYSTEM AS SHOWN ON THESE DRAWINGS.
6. ALL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH ALL APPLICABLE BUILDING CODES AND LOCAL ORDINANCES, INSTALLED IN A NEAT MANNER AND SHALL BE SUBJECT TO APPROVAL BY SPRINT.
7. CONDUCT A PRE-CONSTRUCTION SITE VISIT AND VERIFY EXISTING SITE CONDITIONS AFFECTING THIS WORK. REPORT ANY OMISSIONS OR DISCREPANCIES FOR CLARIFICATION PRIOR TO THE START OF CONSTRUCTION.
8. PROTECT ADJACENT STRUCTURES AND FINISHES FROM DAMAGE. REPAIR TO ORIGINAL CONDITION ANY DAMAGED AREA.
9. REMOVE DEBRIS ON A DAILY BASIS. DEBRIS NOT REMOVED IN A TIMELY FASHION WILL BE REMOVED BY OTHERS AND THE RESPONSIBLE SUBCONTRACTOR SHALL BE CHARGED ACCORDINGLY. REMOVAL OF DEBRIS SHALL BE COORDINATED WITH THE SITE OWNERS REPRESENTATIVE. DEBRIS SHALL BE REMOVED FROM THE PROPERTY AND DISPOSED OF LEGALLY. USE OF THE PROPERTY'S DUMPSTER IS PROHIBITED.
10. CONTRACTOR TO CONFIRM AVAILABLE CAPACITY AT EXISTING UTILITY PEDESTAL AND ADVISE ENGINEER OF SERVICE SIZE AND FAULT CURRENT LEVEL.
11. IF PEDESTAL DOES NOT HAVE ADEQUATE CAPACITY, CONTRACTOR TO SUBMIT COST QUOTATION TO UPGRADE. UPON APPROVAL OF SUBMITTED COST QUOTATION, THE CONTRACTOR SHALL PROVIDE NEW SERVICE AND/OR UPGRADE SERVICE. FEEDERS AND EQUIPMENT/ELECTRODE GROUNDING CONDUCTORS SIZE ACCORDINGLY.
12. CONTRACTOR SHALL VERIFY SEPARATION DIMENSION BETWEEN POWER COMPANY ELECTRICAL CONDUITS AND LP GAS PIPES AS PER UTILITY COMPANY. LOCAL CODES, NEC, NFPA, AND GAS TANK MANUFACTURER'S SPECIFICATION.
13. CONTRACTOR SHALL VERIFY THAT THE TOTAL NUMBER OF SERVICE ENTRANCE DISCONNECTS IN THE EXISTING UTILITY COMPANY PEDESTAL MUST NOT EXCEED SIX. IF THE NEW SERVICE ADDED EXCEEDS THIS VALUE, CONTRACTOR MUST COORDINATE WITH THE UTILITY COMPANY AND AUTHORITY HAVING JURISDICTION. THE RUNNING OF AN ADDITIONAL EXCLUSIVE AND DEDICATED SERVICE LATERAL SET FOR THE NEW LOAD ADDED TO THE COMPOUND AS PER NEC ARTICLE 230-2(B).
14. THE EQUIPMENT/PROTECTIONS MUST BE RATED FOR STANDARD AIC RATE HIGHER THAN INCOMING EQUIPMENT AND/OR UTILITY COMPANY AIC RATE.

ELECTRICAL NOTES:

1. REFERENCE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES FOR GENERAL ELECTRICAL REQUIREMENTS.
2. WIRING SHALL BE AWG STRANDED COPPER WITH THHN OR EQUIVALENT INSULATION. #12 MINIMUM INSTALLED IN 1/2" MINIMUM CONDUIT. SIGNAL WIRING SHALL BE INSULATED #22 AWG. NO BX OR ROMEX CABLE IS PERMITTED. CONDUITS SHALL BE SURFACE MOUNTED.
3. WIRING DEVICES AND EQUIPMENT SHALL BE UL LISTED SPECIFICATIONS GRADE.
4. MATERIALS SHALL BE NEW AND CONFORM TO THE APPLICABLE STANDARDS ESTABLISHED FOR EACH ITEM BY THE ORGANIZATIONS LISTED BELOW:
 - AMERICAN SOCIETY FOR TESTING MATERIALS (ASTM)
 - UNDERWRITER'S LABORATORY (UL)
 - NATIONAL ELECTRICAL MANUFACTURING ASSOCIATION (NEMA)
 - AMERICAN STANDARDS ASSOCIATION (ASA)
 - NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
5. INSTALLATION OF MATERIALS SHALL COMPLY WITH REGULATIONS OF:
 - THE NATIONAL ELECTRIC CODE (NFPA 70)
 - THE NATIONAL ELECTRICAL SAFETY CODE (ANSI C-2)
 - THE LIFE SAFETY CODE (NFPA 101)
 - LOCAL BUILDING CODES
6. THE ENTIRE SYSTEM SHALL BE SOLIDLY GROUNDING USING LOCKOUTS AND BONDING NUTS ON CONDUITS AND PROPERLY BONDED GROUND CONDUCTOR. RECEPTACLES AND EQUIPMENT BRANCH CIRCUITS SHALL BE GROUNDING WITH A FULL-SIZED EQUIPMENT GROUNDING CONDUCTOR RUN IN THE CIRCUITS CONDUIT.
7. OUTLET AND JUNCTION BOXES SHALL BE ZINC-COATED OR CADMIUM PLATED STEEL NOT LESS THAN 4" SQUARE AND SUITABLE FOR THE TYPE SERVICE AND OUTLET. OUTLET AND JUNCTION BOXES SHALL BE SURFACE MOUNTED AND LABELED WITH BRANCH CIRCUIT BREAKER NUMBER.
8. LABEL ALL EQUIPMENT SERVED FROM SPRINT PANEL BOARD WITH PHENOLIC LABELS SIZED IN RELATION TO USAGE.
9. INDOOR CONDUCTORS SHALL BE INSTALLED IN EMT UNLESS NOTED OTHERWISE. OUTDOOR CONDUCTORS SHALL BE INSTALLED IN RIGID GALVANIZED STEEL UNLESS NOTED OTHERWISE. WHERE EMT IS USED, IT SHALL BE WITH ONLY LISTED COMPRESSION FITTINGS. NO SET SCREW FITTINGS SHALL BE ALLOWED.
10. CONTRACTOR TO PROVIDE AND INSTALL ENGRAVED LABEL ON THE SPRINT METER SOCKET ENCLOSURE.
11. CONTRACTOR IS TO OBTAIN ALL PERMITS, PAY PERMIT FEES, AND BE RESPONSIBLE FOR SCHEDULING INSPECTIONS. THE CONTRACTOR IS TO OBTAIN LOCAL POWER AND TELEPHONE COMPANY APPROVAL & COORDINATE WITH UTILITY COMPANIES SERVICE ENTRANCE REQUIREMENTS.

LEGEND:	
---	EXISTING GROUND CABLE
---	PROPOSED GROUND CABLE
▲	MECHANICAL CONNECTION
■	EXOTHERMIC CONNECTION
⊕	UTILITY POLE
---	EASEMENT
—E—E—	PROPOSED ELECTRIC
—T—T—	PROPOSED TELCO
—FO—	PROPOSED FIBER
—FO _x —	EXISTING FIBER
—OHEx—	OVERHEAD ELECTRIC
—E _x —E _x —	ELECTRIC LINE
—T _x —T _x —	TELEPHONE LINE



- NOTES:
1. REFERENCE DETAIL 1/E-3 FOR TYPICAL ANTENNA GROUNDING SCHEMATIC.
 2. GPS SURGE SUPPRESSOR MODEL #: K524577 TO BE ADDED AT BTS AND GROUNDED TO THE MAIN BUSS BAR
 3. ONLY VELCRO STRAPS TO BE USED ON ALL FIBER CABLES.

UTILITY & GROUNDING SITE PLAN
SCALE: 1" = 5'

NOTE:
UTILITY/GROUNDING LINES ARE SHOWN FOR SCHEMATIC PURPOSES ONLY & DO NOT REPRESENT THE EXACT LOCATION OF THE RUN. CONTRACTOR SHALL FIELD VERIFY PROPOSED & EXISTING SERVICE LOCATIONS. NOTIFY CONSTRUCTION/ PROJECT MANAGER IMMEDIATELY OF ANY DISCREPANCIES.

TO OBTAIN LOCATION OF PARTICIPANTS' UNDERGROUND FACILITIES BEFORE YOU DIG IN CONNECTICUT
CALL BEFORE YOU DIG 811 OR 1-800-922-4455
CONNECTICUT PUBLIC ACT 87-71 REQUIRES MIN. 2 WORKING DAYS NOTICE BEFORE YOU EXCAVATE.



Sprint
6391 Sprint Parkway
Overland Park, KS 66251

Alcatel-Lucent

RAMAKER & ASSOCIATES, INC.
1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com


**NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET**

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer in the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

A	10/25	FINAL PRELIM CD'S
MARK	DATE	DESCRIPTION
ISSUE	FINAL PRELIM'S	DATE ISSUED 10/25/2012
PHASE		
PROJECT TITLE:		
UNIONVILLE / POLICE DEPARTMENT SITE#: CT33XC534		
PROJECT INFORMATION: 319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY		
SHEET TITLE:		
UTILITY & GROUNDING SITE PLAN & NOTES		
0 2.5' 5' 10'		
1 1/4" x 17" - 1" = 5' 22" x 34" - 1" = 2.5'		
PROJECT NUMBER		23009
SHEET NUMBER		E-1



- KEY NOTES:
- 1. CONTRACTOR TO USE EXISTING 100A, 2 POLE BREAKER IN EXISTING PPC. VERIFY EXISTING CONDUCTORS ARE (3) #3 AWG OR LARGER. IF NOT, CONTRACTOR TO REPLACE UNDERSIZED ITEM(S).
NOTE: #1 AWG REQUIRED IF TERMINALS ON EACH END OF INPUT CONDUCTORS ARE NOT MARKED "75° C".
 - 2. CONTRACTOR TO PROVIDE (1) 2" EMPTY CONDUIT WITH HEAVY DUTY PULLSTRING FROM EXISTING PPC TO EXISTING BTS.
 - 3. CONTRACTOR TO PROVIDE (1) 2" SEAL-TIGHT CONDUIT WITH (2) #3 DLO.
 - 4. (2) PROPOSED 1½" PVC CONDUITS (1 POWER, 1 FIBER). GALVANIZED STEEL OR LIQUID-TIGHT FLEXIBLE CONDUITS ACCEPTABLE AT CM'S DISCRETION. LIQUID-TIGHT CONDUIT LENGTHS NOT TO EXCEED 6'-0".

SINGLE LINE DIAGRAM
SCALE: NTS

MAIN: 200 AMP MAIN BREAKER

VOLTAGE: 240/ 120

LOCATION: PPC CABINET

ELECTRICAL PANEL SCHEDULE

PHASE: 1

WIRE: 3

MOUNT: SURFACE

CIRCUIT	LOAD DESCRIPTION	BREAKER		PHASE		BREAKER		LOAD DESCRIPTION	CIRCUIT
		AMPS	POLES	A	B	POLES	AMPS		
1	SUB PANEL	100	2	■	■	60	2	AC SURGE PROTECTOR	7
2				■	■				8
3	UNIT #1	80	2	■	■	80	2	UNIT #3	9
4				■	■				10
5	UNIT #2	80	2	■	■	1	15	TELCO GFI	11
6				■	■	1	10	FAN	12

EXISTING PANEL SCHEDULE
SCALE: NTS

DIAGRAM
TBD

NOTE:
INSTALLER MUST ENSURE THAT ANY EXISTING ALARMS ARE TRANSFERRED TO NEW EQUIPMENT. MONITORED, AND IN PROPER WORKING ORDER DURING MM-BTS INSTALLATION.

STANDARD ALARM BLOCK TEMPLATE
WIRING DIAGRAM
SCALE: NTS




6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S
ISSUE	DATE	DESCRIPTION
PHASE	10/25/2012	FINAL PRELIM'S

PROJECT TITLE:
UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534

PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
UTILITY DETAILS


SCALE: NONE

PROJECT NUMBER: 23009
SHEET NUMBER: E-2

GROUNDING SPECIFICATIONS:

1. REFERENCE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND SPRINT EXTERIOR GROUNDING SYSTEM DESIGN (REV 06/29/05) FOR GENERAL GROUNDING REQUIREMENTS.
2. GROUNDING SHALL COMPLY WITH ARTICLE 250 OF THE NATIONAL ELECTRICAL CODE. ALL GROUNDING DEVICES SHALL BE U.L. APPROVED OR LISTED FOR THEIR INTENDED USE.
3. GROUND WIRES SHALL BE TINNED #2 AWG BARE SOLID COPPER UNLESS NOTED OTHERWISE.
4. GROUNDING CONNECTIONS SHALL BE EXOTHERMIC (CADWELD) NOTED OTHERWISE. CLEAN SURFACES TO SHINE METAL. WHERE GROUND WIRES ARE CADWELD TO GALVANIZED SURFACES. SPRAY CADWELD WITH GALVANIZING PAINT.
5. ROUTE GROUNDING CONDUCTORS ALONG THE SHORTEST AND STRAIGHTEST PATH POSSIBLE. BEND GROUNDING LEADS WITH A MINIMUM 8" RADIUS.
6. PRIOR TO INSTALLING LUGS ON GROUND WIRES, APPLY THOMAS & BETSS KOPR-SHIELD (TM OF JET LUBE, INC.). PRIOR TO BOLTING GROUND WIRE LUGS TO GROUND BARS, APPLY KOPR-SHIELD OR EQUAL.
7. WHERE BARE COPPER GROUND WIRES ARE ROUTED FROM ANY CONNECTION ABOVE GRADE TO GROUND RING, INSTALL WIRE IN 3/4" PVC SLEEVE, FROM 1'-0" MIN. ABOVE GRADE AND SEAL TOP WITH SILICONE MATERIAL.
8. PREPARE ALL BONDING SURFACES FOR GROUNDING CONNECTIONS BY REMOVING ALL PAINT AND CORROSION DOWN TO SHINY METAL. FOLLOWING CONNECTION, APPLY APPROPRIATE ANTI-OXIDIZATION PAINT.
9. GROUNDING WIRE CONNECTIONS SHALL BE 3-CRIMP C-TAP COMPRESSION TYPE. SPLIT BOLTS ARE NOT ACCEPTABLE.
10. GROUND RODS SHALL BE COPPER CLAD STEEL 3/8" x 10' SPACE NOT LESS THAN 10' O.C.
11. CONNECTORS SHALL BE CRIMPED USING HYDRAULIC CRIMPING TOOLS.
12. SURFACE CONNECTIONS SHALL BE MADE TO BARE METAL. PAINTED SURFACES SHALL BE FILED TO ENSURE PROPER CONTACT. APPLY NON-OXIDIZING AGENT TO CONNECTIONS.
13. COPPER BUSES SHALL BE CLEANED, POLISHED AND A NON-OXIDIZING AGENT APPLIED. NO FINGERPRINTS OR DISCOLORED COPPER WILL BE PERMITTED.
14. GROUNDING CONDUCTORS SHALL BE RUN THROUGH PVC SLEEVE WHERE ROUTED THROUGH WALLS, FLOORS, AND CEILINGS. ENDS OF CONDUIT SHALL BE GROUNDED. SEAL BOTH ENDS OF CONDUIT WITH SILICONE CAULK.
15. HARDWARE (I.E. NUTS, BOLTS, WASHERS, ETC.) TO BE STAINLESS STEEL.
16. EXOTHERMIC WELDS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.

17. THE ENTIRE SYSTEM SHALL BE SOLIDLY GROUNDDED USING LOCKNUTS AND BONDING NUTS ON CONDUITS AND PROPERLY BONDED GROUND CONDUCTORS, RECEPTACLES AND EQUIPMENT BRANCH CIRCUITS SHALL BE GROUNDDED WITH A FULL SIZED EQUIPMENT GROUNDING CONDUCTOR RUN IN THE CIRCUITS CONDUIT.
18. INSTALL GROUND BUSHINGS ON ALL METALLIC CONDUITS AND BOND TO THE EQUIPMENT GROUND BUS IN THE PANEL BOARD.
19. GROUND BARS (SECTOR, COLLECTOR, MASTER) SHALL BE MIN. BARE 1/4" x 4" COPPER AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE SECURING THE MASTER GROUND BAR (MGB) SHALL ELECTRICALLY INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENED.
20. APPLY THOMAS & BETSS KOPR-SHIELD OR APPROVED EQUIVALENT PRIOR TO MAKING MECHANICAL CONNECTIONS. CONNECTIONS SHALL BE MADE WITH STAINLESS STEEL BOLTS, NUTS AND LOCK WASHERS 3/8" DIAMETER, MIN. WHERE GALVANIZING IS REMOVED FROM METAL IT SHALL BE PAINTED OR TOUCHED UP WITH 'GALVONOX' OR EQUAL.
21. ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANELS, FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE WITH STAINLESS STEEL SELF-TAPPING SCREWS.
22. ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTOR AND PVC CONDUITS SHALL BE PVC TYPE (NON-CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
23. ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
24. THE CONTRACTOR SHALL ENGAGE AN INDEPENDENT ELECTRICAL TESTING FIRM TO TEST AND VERIFY THAT RESISTANCE TO EARTH DOES NOT EXCEED 5.0 OHMS. PROVIDE A COPY OF TESTING REPORT, INCLUDING THE METHOD AND INSTRUMENTS USED TO VERIFY RESISTANCE TO SPRINT REPRESENTATIVE.
25. COAX CABLE SHALL BE GROUNDDED AT ANTENNA LEVEL WITHIN 5' OF ANTENNA. COAX WILL ADDITIONALLY BE GROUNDDED AT THE BASE OF THE TOWER 18" BEFORE THE CABLE REACHES A HORIZONTAL PLANE. IF EQUIPMENT CABINET IS MORE THAN 15' FROM THE TOWER AN ADDITIONAL GROUND KIT WILL BE ADDED 24" BEFORE CABLE ENTERS CABINET.
26. ALL COAX GROUND KITS WILL BE ANDREW 'COMPACT SURE GROUND' OR APPROVED EQUIVALENT.
27. VERIFY THE GROUNDING CONTINUITY BETWEEN THE TOWER BASE AND THE NEW SPRINT CABINET GROUND BAR. CONTRACTOR SHALL ENSURE THAT ALL METALLIC OBJECTS WITHIN 6' FROM CABINET HAVE GROUNDING CONTINUITY. THE CONTRACTOR SHALL CORRECT ANY DEFECTS BE ADDING GROUNDING CONDUCTOR TO ENSURE CONTINUITY.
28. GROUNDING CONDUCTORS SHALL BE COPPER ONLY. EITHER SOLID OR STRANDED CONDUCTORS ARE PERMITTED. ALL EXTERNAL BURIED CONDUCTORS MUST BE BARE. EQUIPMENT GROUND LEADS IN CABLE TRAYS MUST BE GREEN INSULATED.
29. CONTRACTOR TO PROVIDE GROUND WIRES, BARS, AND CONNECTIONS AS SHOWN ON GROUNDING RISER DIAGRAM.



6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S

ISSUE	DATE	DATE
PHASE	FINAL PRELIM'S	ISSUED 10/25/2012





PROJECT TITLE:
UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534
PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
GROUNDING DETAIL & NOTES

SCALE: NONE

PROJECT NUMBER: 23009

SHEET NUMBER: E-3



6391 Sprint Parkway
Overland Park, KS 66251



1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION MMBTS LAUNCH NORTHERN CT MARKET

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION
A	10/25	FINAL PRELIM CD'S
ISSUE	FINAL PRELIMS	DATE ISSUED 10/25/2012





PROJECT TITLE:
**UNIONVILLE /
POLICE DEPARTMENT
SITE#: CT33XC534**


PROJECT INFORMATION:
319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:
GROUNDING DETAILS


SCALE: NONE


PROJECT NUMBER: 23009
SHEET NUMBER: E-4





6391 Sprint Parkway
Overland Park, KS 66251






1120 Dallas Street, Sauk City, WI 53583
Phone: 608-643-4100 Fax: 608-643-7999
www.Ramaker.com

NETWORK VISION
MMBTS LAUNCH
NORTHERN CT MARKET

Certification & Seal:



I hereby certify that this engineering calculation, or report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer, holding the laws of the State of Connecticut.

Signature: *James R. Skowronski* Date: 12/11/2012

MARK	DATE	DESCRIPTION	ISSUE
A	10/25	FINAL PRELIM CDS	FINAL PRELIM'S
			DATE
			10/25/2012
			ISSUED

PROJECT TITLE: UNIONVILLE / POLICE DEPARTMENT
SITE#: CT33XC534
PROJECT INFORMATION: 319-321 NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE: GROUNDING DETAILS

SCALE: NONE

PROJECT NUMBER 23009
SHEET NUMBER E-5

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.