

1280 Route 46 West, Suite 9, Parsippany NJ, 07054

Ms. Melanie Bachman, Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

Re: Notice of Exempt Modification Application 319-321 New Britain Ave., Farmington, CT 06032

December 6, 2017

Dear Ms. Bachman:

Sprint Spectrum Realty Company, L.P. ("Sprint"), is submitting to the Connecticut Siting Council for a Notice of Exempt Modification for Proposed Modifications to an Existing Telecommunications Facility located at the above-referenced site. Sprint currently maintains 3 existing panel antenna and 3 parabolic dishes at the 170' level of the Tower. Sprint proposes to add 3 panel antennas and 6 remote radio unit at 170' tower level as well as 1 fiber cable, 1 new battery string in existing ground based battery cabinet, new 2.5 MHz radio equipment in existing ground based radio cabinet and remove existing antenna platform with new Valmont RMQP-484 platform with HRK 12 Handrail kit.

The Sprint Tower Share was initially approved on 2/20/2002 by CT Siting Council. The building permit was approved on 2/22/2002 by Farmington Building Department. The structural and construction documents enclosed have been revised to reflect the current reality of the installations on the Tower.

If you have any questions, please feel free to contact me.

Thank you,

By: Paul F. Sagristano

Paul F. Sagristano Cherundolo Consulting 917.841.0247 psagristano@lrivassoc.com



1280 Route 46 West, Suite 9, Parsippany NJ, 07054

Ms. Melanie Bachman Executive Director CT Siting Council 10 Franklin Square New Britain, CT 06051

December 6, 2017

Re: Notice of Exempt Modification – Existing Sprint Telecommunication Facility 319-321 New Britain Ave. Farmington, CT 06032

Latitude: N41.74972 Longitude: W72.8725

Dear Ms. Bachman:

Sprint currently maintains 3 existing panel antenna and 3 parabolic dishes at the 170' level of the Tower. Sprint proposes to add 3 panel antennas and 6 remote radio unit at 170' tower level as well as 1 fiber cable, 1 new battery string in existing ground based battery cabinet, new 2.5 MHz radio equipment in existing ground based radio cabinet and remove existing antenna platform with new Valmont RMQP-484 platform with HRK 12 Handrail kit. Sprint is performing a new high-performance upgrade for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

The initial Sprint tower share was approved on 2/20/2002 by CT Siting Council and the building permit was approved by the Farmington Building Department on February 22, 2002. A copy of these approvals are attached.

Please accept this letter as notification to the Council, pursuant to R.C.S.A. Section 16-50j-73, for construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter is being sent to Kathleen A. Eagen, Town Administrator for Farmington, the property owner William Warner, Town Planner for Farmington and Michael Guliano, the Fire Marshall for Farmington.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower with proposed modifications to accommodate the revised antenna configuration.

Existing Facility

The Fairfield facility is located at 319-321 New Britain Ave., Farmington, CT, the Site coordinates are: N41. 74972, W – 72.8725. The facility is owned by the Town of Farmington Fire Department, The existing facility consists of a 190' Monopole. Sprint currently operates wireless communications equipment on a concrete slab at the facility and has 3 antennas and 3 Parabolic dishes mounted on at a centerline of 170' feet.

Statutory Considerations

The planned modifications to the facility fall within the activities explicitly provided for in R.C.S.A. 16-50j-72(b)(2)

- 1. The height of the overall structure will be unaffected.
- 2. The proposed changes will not require an extension of the property boundaries.
- 3. The proposed additions will not increase the noise level at the existing facility by

six decibels or more, or to levels that exceed state and/or local criteria

- 4. The changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the Federal Communications Commission safety standard.
- 5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
- 6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A Section §16-50j-72(b)(2).

Respectfully submitted,

Paul F. Sagristano

Paul F. Sagristano Charles Cherundolo Consulting 917-841-0247 psagristano@lrivassoc.com

PFS/mtf

Additional Recipients:

Town of Farmington - Kathleen A. Eagen - Town Manager - Via Fed Ex Town of Farmington Fire Dept. – Michael Guliano – Fire Marshall - Via Fed Ex Town of Famington – Town Planner – William Warner – Via Fed Ex



December 7,2017

Dear Customer:

The following is the proof-of-delivery for tracking number 770912317372.

Delivery Information:

Status: Delivered to: Receptionist/Front Desk

Delivery date:

Signed for by: K.SACCU Delivery location: 1 MONTIETH DR

FARMINGTON, CT 06032

Dec 7, 2017 13:29

Service type: FedEx Express Saver

Special Handling: Deliver Weekday

Direct Signature Required



Shipping Information:

 Tracking number:
 770912317372
 Ship date:
 Dec 6, 2017

 Weight:
 0.5 lbs/0.2 kg

Recipient:

Reference

Kathleen A. Eagen, Town Manager
Town of Farmington

1 Monteith Drive

FARMINGTON, CT 06032 US

Thank you for choosing FedEx.

Shipper:

Paul Sagristano

CCC

4 Davis Road West

Suite 5

OLD LYME, CT 06371 US

CT33XC534 CSC to Town Mgr,



December 7,2017

Dear Customer:

The following is the proof-of-delivery for tracking number **770912342650**.

Delivery Information:

Status: Delivered to: Receptionist/Front Desk

Delivery date:

Signed for by: K.SACCU Delivery location: 1 MONTIETH DR


FARMINGTON, CT 06032

Dec 7, 2017 13:29

Service type: FedEx Express Saver

Special Handling: Deliver Weekday

Direct Signature Required



Shipping Information:

Tracking number: 770912342650 **Ship date:** Dec 6, 2017

Weight: 0.5 lbs/0.2 kg

Recipient:

Reference

William Warner, Town Planner

Town of Farmington
1 Monteith Drive

FARMINGTON, CT 06032 US

1 ARMING 1014, 01 00032 00

Thank you for choosing FedEx.

Shipper:

Paul Sagristano

CCC

4 Davis Road West

Suite 5

OLD LYME, CT 06371 US

CT33XC534 CSC to Town Planner



December 7,2017

Dear Customer:

The following is the proof-of-delivery for tracking number 770912370260.

Delivery Information:

Status: Delivered to: Receptionist/Front Desk

Delivery date:

Signed for by: K.SACCU Delivery location: 1 MONTIETH DR

FARMINGTON, CT 06032

Dec 7, 2017 13:29

Service type: FedEx Express Saver

Special Handling: Deliver Weekday

Direct Signature Required



Shipping Information:

Tracking number: 770912370260 **Ship date:** Dec 6, 2017

Weight: 0.5 lbs/0.2 kg

Recipient:

Michael Guliano, Fire Marshall

Town of Farmington

1 Monteith Drive

FARMINGTON, CT 06032 US

Reference

ve 4 Davis Road West

Suite 5

CCC


Shipper:

Paul Sagristano

OLD LYME, CT 06371 US

CT33XC534 CSC to Fire Marshall

Thank you for choosing FedEx.





The Assessor's office is responsible for the maintenance of records on the ownership of properties. Assessments are computed at 70% of the estimated market value of real property at the time of the last revaluation which was 2012.





Information on the Property Records for the Municipality of Farmington was last updated on 12/4/2017.

Parcel Information

| Location: | 319 NEW BRITAIN AV | Property Use: | Office | Primary Use: | Office Building |
|--------------------------|--------------------|-------------------|----------|-------------------|-----------------|
| Unique ID: | 13200319321 | Map Block Lot: | 0035 1-8 | Acres: | 13.20 |
| 490 Acres: | 0.00 | Zone: | CR | Volume / Page: | 0571/0159 |
| Developers Map / Lot: | | Census: | 4603-00 | | |

Value Information

| | Appraised Value | 70% Assessed Value |
|-----------------------|-----------------|--------------------|
| Land | 2,790,000 | 1,953,000 |
| Buildings | 9,146,914 | 6,402,840 |
| Detached Outbuildings | 0 | 0 |
| Total | 11,936,914 | 8,355,840 |


Owner's Information

Owner's Data

FAMINGTON TOWN OF
NEW POLICE/COMMUNITY CENTER
1 MONTEITH DR
FARMINGTON CT 06032

Building 1

Photo Not Available



| Category: | Office | Use: | Office Building | GLA: | 24,758 |
|-----------|--------|----------------|-----------------|---------------------|--------|
| Stories: | 2.00 | Construction: | Fire Proof | Year Built: | 2001 |
| Heating: | | Fuel: | | Cooling Percent: | 0 |
| Siding: | | Roof Material: | | Beds/Units: | 0 |

Special Features

| Elevator, Comm Elec Pass | 1 |
|--------------------------|-------|
| Wet Sprinklers | 13238 |
| Wet Sprinklers | 24758 |
| Wet Sprinklers | 2250 |

Attached Components

| Туре: | Year Built: | Area: |
|-------------------|-------------|-------|
| Commercial Canopy | 2001 | 220 |
| Commercial Canopy | 2001 | 128 |
| Commercial Canopy | 2001 | 210 |
| Commercial Canopy | 2001 | 68 |

Building 2



STATE OF CONNECTICUT

CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051 Phone: (860) 827-2935 Fax: (860) 827-2950 E-Mail: siting.council@po.state.ct.us Web Site: www.state.ct.us/csc/index.htm

February 20, 2002

Thomas J. Regan, Esq.
Brown, Rudnick, Freed & Gesmer, P.C.
185 Asylum Street, CityPlace I
Hartford, CT 06103-3402

RE:

TS-SPRINT-052-020118 - Sprint Spectrum, L.P. d/b/a Sprint PCS request for an order to approve tower sharing at an existing telecommunications facility located at 319-321 New Britain Avenue, Farmington, Connecticut.

Dear Attorney Regan:

At a public meeting held February 14, 2002, the Connecticut Siting Council (Council) ruled that the shared use of this existing tower site is technically, legally, environmentally, and economically feasible and meets public safety concerns, and therefore, in compliance with General Statutes § 16-50aa, the Council has ordered the shared use of this facility to avoid the unnecessary proliferation of tower structures. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Any additional change to this facility may require an explicit request to this agency pursuant to General Statutes § 16-50a or notice pursuant to Regulations of Connecticut State Agencies Section 16-50j-73, as applicable. Such request or notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Any deviation from this format may result in the Council implementing enforcement proceedings pursuant to General Statutes § 16-50u including, without limitation, imposition of expenses resulting from such failure and of civil penalties in an amount not less than one thousand dollars per day for each day of construction or operation in material violation.

This decision applies only to this request for tower sharing and is not applicable to any other request or construction.

The proposed shared use is to be implemented as specified in your letters dated January 18, 2002, January 28, 2002, and February 4, 2002.

Thank you for your attention and cooperation.

Very truly yours,

Mature A. Halther Mortimer A. Gelston

Chairman

MAG/RKE/laf

c: Honorable Arline B. Whitaker, Chairman Town Council, Town of Farmington Jeffrey Ollendorf, Town Planner, Town of Farmington Michael Whalen, Chief of Police, Farmington Police Department

TOWN OF FARMINGTON
**** BUILDING PERMIT **** PERMITH: 37515 3: 22-Feb-2002 EST. COST: 300,000.00 BUILD FEES: .00 WAIVED DEV SEW PER: LOT#: MISC SEW: . 00 R: TOWN OF FARMINGTON D: * 0319 NEW BRITAIN AV *********** E & ADDRESS OF APPLICANT DESCRIPTION OF WORK TO BE DONE INT POS Commercial Tower SPRING ST 06096 DSOR LOCKS, GT Lot Area: No.Stories: Height: d.Area; : ALL WORK TO BE DONE IN ACCORDANCE WITH THE APPLICATION AND PLANS APPROVED BY THE BUILDING DEPARTMENT. ZONE DEV.PERMIT CBYD # FEC 2002 0801499 12.0 PLB HTG/AC SPRINKLER SEWER AS BUILT TOWN OF FARMINGTON PERMITH: 37516 **** BUILDING PERMIT **** EST. COST: 50.000.00 BUILD FEES: .00 WAIVED 1: 22-Feb-2002 .00 DEV SEW PER: MISC SEW: R: TOWN OF FARMINGTON LOT#: 0:* 0319 NEW BRITAIN AV * TOTAL FEE: 宋宋宋宋宋宋宋宋宋宋宋宋 DESCRIPTION OF WORK TO BE DONE & ADDRESS OF APPLICANT and the same and the same specified when their control was able to the same and the same and the same and the same and Commercial NT POS Antenna SPRING ST SOR LOCKS, CT 06096 1.Area: Lot Area: No.Stories: Height: . ALL WORK TO BE DONE IN ACCORDANCE WITH THE APPLICATION AND PLANS APPROVED BY THE BUILDING DEPARTMENT. ZONE DEV.PERMIT CBYD # FEE 2002 0801499 12.0

PLB_____ HTG/AC____ SPRINKLER___ SEWER___ AS BUILT____



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT33XC534

Unionville/Police Dept. 319-321 New Britain Avenue Farmington, CT 06032

November 7, 2017

EBI Project Number: 6217004930

| Site Compliance Summary | | | | |
|-------------------------|----------------|--|--|--|
| Compliance Status: | COMPLIANT | | | |
| Site total MPE% of | | | | |
| FCC general | 9.62 % | | | |
| population | 9.02 /0 | | | |
| allowable limit: | | | | |



November 7, 2017

SPRINT Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Emissions Analysis for Site: CT33XC534 – Unionville/Police Dept.

EBI Consulting was directed to analyze the proposed SPRINT facility located at **319-321 New Britain Avenue, Farmington, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm2). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limits for the 850 MHz Band is approximately 567 μ W/cm². The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **319-321 New Britain Avenue, Farmington, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the RFS APXVSPP18-C-A20, RFS APXV9ERR18-C-A20 and the Commscope DT465B-2XR for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **170 feet** above ground level (AGL) for **Sector A**, **170 feet** above ground level (AGL) for **Sector B** and **170 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

| Sector: | A | Sector: | В | Sector: | C |
|-----------------------|-----------------------------|-----------------------|-----------------------------|-----------------------|-----------------------------|
| Antenna #: | 1 | Antenna #: | 1 | Antenna #: | 1 |
| Make / Model: | RFS APXVSPP18-C-A20 | Make / Model: | RFS APXVSPP18-C-A20 | Make / Model: | RFS APXV9ERR18-C-A20 |
| Gain: | 13.4 / 15.9 dBd | Gain: | 13.4 / 15.9 dBd | Gain: | 13.4 / 15.9 dBd |
| Height (AGL): | 170 feet | Height (AGL): | 170 feet | Height (AGL): | 170 feet |
| Frequency Bands | 850 MHz / 1900 MHz (PCS) | Frequency Bands | 850 MHz / 1900 MHz (PCS) | Frequency Bands | 850 MHz / 1900 MHz (PCS) |
| Channel Count | 10 | Channel Count | 10 | Channel Count | 10 |
| Total TX Power(W): | 220 Watts | Total TX Power(W): | 220 Watts | Total TX Power(W): | 220 Watts |
| ERP (W): | 7,537.38 | ERP (W): | 7,537.38 | ERP (W): | 5,873.76 |
| Antenna A1 MPE% | 1.15 % | Antenna B1 MPE% | 1.15 % | Antenna C1 MPE% | 0.88 % |
| Antenna #: | 2 | Antenna #: | 2 | Antenna #: | 2 |
| Make / Model: | Commscope DT465B-2XR | Make / Model: | Commscope DT465B-2XR | Make / Model: | Commscope DT465B- 2XR |
| Gain: | 15.05 dBd | Gain: | 15.05 dBd | Gain: | 15.05 dBd |
| Height (AGL): | 170 feet | Height (AGL): | 170 feet | Height (AGL): | 170 feet |
| Frequency Bands | 2500 MHz (BRS) | Frequency Bands | 2500 MHz (BRS) | Frequency Bands | 2500 MHz (BRS) |
| Channel Count | 8 | Channel Count | 8 | Channel Count | 8 |
| Total TX Power(W): | 160 Watts | Total TX Power(W): | 160 Watts | Total TX Power(W): | 160 Watts |
| ERP (W): | 5,118.23 | ERP (W): | 5,118.23 | ERP (W): | 5,118.23 |
| Antenna A2 MPE% | 0.68 % | Antenna B2 MPE% | 0.68 % | Antenna C2 MPE% | 0.68 % |

| Site Composite MPE% | | | | | |
|-------------------------|--------|--|--|--|--|
| Carrier | MPE% | | | | |
| SPRINT – Max per sector | 1.83 % | | | | |
| Town | 0.23 % | | | | |
| Emergency | 0.89 % | | | | |
| Public Works | 4.04 % | | | | |
| Clearwire | 0.07 % | | | | |
| AT&T | 1.86 % | | | | |
| T-Mobile | 0.70 % | | | | |
| Site Total MPE %: | 9.62 % | | | | |

| SPRINT Sector A Total: | 1.83 % |
|------------------------|--------|
| SPRINT Sector B Total: | 1.83 % |
| SPRINT Sector C Total: | 1.56 % |
| | |
| Site Total: | 9.62 % |

| SPRINT _ Max Values per Frequency Band / Technology (Sectors A & B) | # Channels | Watts ERP (Per Channel) | Height (feet) | Total Power Density (µW/cm²) | Frequency (MHz) | Allowable MPE (µW/cm²) | Calculated % MPE |
|---|---------------|----------------------------|---------------|------------------------------|-----------------|------------------------------|---------------------|
| Sprint 850 MHz CDMA | 1 | 437.55 | 170 | 0.58 | 850 MHz | 567 | 0.10% |
| Sprint 850 MHz LTE | 2 | 437.55 | 170 | 1.17 | 850 MHz | 567 | 0.21% |
| Sprint 1900 MHz (PCS) CDMA | 5 | 622.47 | 170 | 4.16 | 1900 MHz (PCS) | 1000 | 0.42% |
| Sprint 1900 MHz (PCS) LTE | 2 | 1,556.18 | 170 | 4.16 | 1900 MHz (PCS) | 1000 | 0.42% |
| Sprint 2500 MHz (BRS) LTE | 8 | 639.78 | 170 | 6.84 | 2500 MHz (BRS) | 1000 | 0.68% |
| | | | | | | Total: | 1.83% |



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

| SPRINT Sector | Power Density Value (%) |
|-------------------------|-------------------------|
| Sector A: | 1.83 % |
| Sector B: | 1.83 % |
| Sector C: | 1.56 % |
| SPRINT Maximum | 1.83 % |
| Total (Sectors A & B): | 1.63 % |
| | |
| Site Total: | 9.62 % |
| | |
| Site Compliance Status: | COMPLIANT |

The anticipated composite MPE value for this site assuming all carriers present is **9.62** % of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



October 19, 2017

Tom Jupin Charles Cherundolo Consulting, Inc. 1280 Rt. 46 West Parsippany, NJ 07054

Ramaker & Associates, Inc. 855 Community Drive Sauk City, WI 53583

SUBJECT:

STRUCTURAL ASSESSMENT

190-FOOT MONOPOLE TOWER

CARRIER:

SPRINT

SITE:

UNIONVILLE/POLICE DEPARTMENT (CT33XC534-B)

319-321 NEW BRITAIN AVENUE

FARMINGTON, HARTFORD COUNTY, CONNECTICUT 06032

RAMAKER & ASSOCIATES PROJECT NUMBER: 23009

RESULTS:

TOWER:

93.5%

PASS WITH MODIFICATIONS

FOUNDATION:

92.1%

PASS

Dear Tom Jupin:

Ramaker & Associates, Inc. (RAMAKER) respectfully submits this mount and structural assessment for the above mentioned site. The purpose of this report is to determine the structural integrity of the structure(s) with the proposed loading configurations. Engineering recommendations regarding the analysis results are provided in the following pages.

RAMAKER developed a finite element model of the tower using tnxTower analysis software. Also, RAMAKER developed a finite element model of the mount(s) using RISA analysis software. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the tower loading occur.

If you have any questions or comments, please do not hesitate to contact our office.

Sincerely,

RAMAKER & ASSOCIATES, INC.

Thomas E. Moore Project Engineer

James R. Skowronski, P.E.

Supervising Engineer

ANALYSIS CRITERIA

| State Building Code | 2016 CT State Building Code |
|----------------------------------|-----------------------------|
| Adopted Building Code | 2012 IBC |
| Referenced Standard | TIA-222-G |
| Risk Category | ll . |
| Ultimate Design Wind Speed, Vult | 125 mph (3 sec. gust) |
| Nominal Design Wind Speed, Vasd | 97 mph (3 sec. gust) |
| Design Wind Speed w/ Ice | 40 mph (3 sec. gust) |
| Ice Thickness | 1.0 inch |
| Exposure Category | С |
| Topographic Category | 1 |
| Crest Height | N/A |

SUPPORTING DOCUMENTATION

- Tower drawings by Pirod Inc., drawing number 157375-B, dated April 19, 2002
- Structural analysis by RAMAKER, site number 23009, dated November 16, 2012
- Structural analysis by Bay State Design, site number CT-HFD0073A, dated March 10, 2010
- Structural analysis by Malouf Engineering, job number CT00937M-07V0, dated September 28, 2007
- Construction drawings by RAMAKER, project number 23009
- Site visit(s) conducted by RAMAKER
- Other pertinent data procured or assumed by RAMAKER during site due diligence activities

TOWER LOADING

RAMAKER understands that the loading to be used for this analysis will consist of the antenna equipment, mount, and cable configurations as shown in the following chart:

| Elevation | Appurtenance | Mount | Coax | Owner | Status |
|-----------|------------------------------|----------------------------|-----------------------|---------------------------------------|----------|
| | (2) 10' Omni | | | | |
| 190 | (1) Kathrein Scala PR-850 | (3) Standoff | (4) 7/8 | | Existing |
| | (1) Andrew 2' Dish w/ Shroud | | | | |
| 185 | (2) 3' Yagi | (2) Standoff | (2) 7/8 | | Existing |
| 180 | (1) 5' Omni | (2) Standoff (1) 7/8 | | | Existing |
| 175 | (3) ALU 1900MHz 4x40W RRH | (1) 6 11 44 | (0) 1 1 / / | | |
| 1/3 | (3) ALU 800MHz 2x50W RRH | (1) Collar Mount | (3) 1-1/4 | Sprint | |
| | (3) Argus LLPX310R | | | | |
| | (3) Samsung RRH | | | Clearwire | Existing |
| | (2) RFS APXVSPP18-C-A20 | | | | |
| | (1) RFS APXV9ERR18-C-A20 | | (6) 1-5/8 | | |
| 170 | (1) Andrew VHLP2-18 | (1) Platform w/Handrail | (3) 5/16 | | |
| | (1) Andrew VHLP800-11 | | (2) 1-1/4 | | |
| | (3) Commscope DT465B-2XR | | | | |
| | (3) ALU RRH-2x50-800 | | | | Proposed |
| | (3) ALU TD-RRH8X20 | | | | |
| | (6) 5' Panel Antenna | | | | |
| 160 | (3) 7' Panel Antenna | (1) LP Platform | (12) 1-1/4 (1) 1/2 | T-Mobile | Existing |
| | (3) RRH | | (1) 1/2 | | |
| | (3) Powerwave P65-17-XLH-RR | | | | |
| | (3) Kathrein Scala 800 10121 | | | Sprint Clearwire Sprint T-Mobile AT&T | |
| 150 | (3) Powerwave LGP214nn | (3) T-Arm | (6) 1-5/8 | | Existing |
| | (3) Ericsson RRUS-11 | | | | |
| | (1) Raycap DC6-48-60-18-8F | | | | |
| 113 | (3) 6' Omni | (3) Standoff | (3) 1/2 | | Existing |
| 90 | (3) 18' Omni | (3) Standoff | (3) 1/2 | | Existing |

TOWER RESULTS

The maximum tower member stress capacities under the loading conditions previously described are as follows:

| Component Type | Percent Capacity | Pass/Fail |
|----------------|------------------|-----------|
| Pole | 93.5 | Pass |
| Reinforcement | 91.8 | Pass |
| Anchor Rod | 86.6 | Pass |
| Base Plate | | Pass |
| RATING | 93.5 | PASS |

Results of the analysis show that the modified tower will be stressed to a maximum of 93.5 percent of capacity. Therefore, the modified tower will pass the TIA-222-G analysis requirements under proposed loading conditions.

DISH TWIST/SWAY RESULTS

The twist/sway results for a 60 mph service wind speed are as follows:

| Elevation | Dish | Deflection (in) | Tilt (deg) | Twist (deg) |
|-----------|-----------------------------|-----------------|------------|-------------|
| 192 | (1) Andrew 2' Dish w/Shroud | 34.429 | 1.6225 | 0.0137 |
| 190 | (1) Kathrein Scala PR-850 | 34.402 | 1.6225 | 0.0137 |
| 176 | (1) Andrew VHLP2-18 | 29.668 | 1.6008 | 0.0104 |
| 176 | (1) Andrew VHLP800-11 | 29.668 | 1.6008 | 0.0104 |

FOUNDATION RESULTS

The maximum foundation stress capacities are as follows:

| Component Type | Percent Capacity | Pass/Fail |
|------------------|------------------|-----------|
| Soil Interaction | 91.6 | Pass |
| Structural | 92.1 | Pass |
| RATING | 92.1 | PASS |

The foundations were analyzed utilizing the previous Malouf analysis and geotechnical report referenced above. Results of the analysis show that the existing foundation will be stressed to a maximum of 92.1 percent of capacity. Therefore, the existing foundation will pass the TIA-222-G analysis requirements under proposed loading conditions.

LIMITATIONS

The recommendations contained within this report were developed using the supporting documentation as previously described. All recommendations pertain only to the proposed antenna installation activities as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

- Missing, corroding, and/or deteriorating members
- Improper manufacturing and/or construction
- İmproper maintenance

RAMAKER assumes no responsibility for modifications completed prior to or hereafter in which RAMAKER was not directly involved. These modifications include but are not limited to the following:

- Replacing or strengthening bracing members
- Reinforcing or extending vertical members
- Installing or removing antenna mounting gates or side arms
- Changing loading configurations

The tower owner is responsible for verifying that the existing loading on the structure is consistent with the loading applied to the structure within this report. If there is any information contrary to that contained herein, or if there are any defects arising from the original design, material, fabrication and erection deficiencies, this report should be disregarded and RAMAKER should be contacted immediately. RAMAKER is not liable for any representation, recommendation, or conclusion not expressly stated herein.

This analysis pertains only to the tower structure, and no analyses or conclusions were made regarding the antenna and equipment mounting structure(s). Analysis and certification of the antenna and equipment mounting structure(s) is performed and submitted separately.



October 17, 2017

Tom Jupin Charles Cherundolo Consulting, Inc. 1280 Rt. 46 West Parsippany, NJ 07054

Ramaker & Associates, Inc. 855 Community Drive Sauk City, WI 53583

SUBJECT: MOUNT ASSESSMENT

CARRIER: SPRINT

SITE: **UNIONVILLE/POLICE DEPARTMENT (CT33XC534-B)**

319-321 NEW BRITAIN AVENUE

FARMINGTON, HARTFORD COUNTY, CONNECTICUT 06032

RAMAKER & ASSOCIATES PROJECT NUMBER: 23009

RESULTS: MOUNT: PASS WITH REPLACEMENT

Dear Tom Jupin:

Ramaker & Associates, Inc. (RAMAKER) respectfully submits this mount assessment for the above mentioned site. The purpose of this report is to determine the structural integrity of the mounting structure with the proposed loading configurations. Engineering recommendations regarding the analysis results are provided in the following pages.

RAMAKER developed a finite element model of the mount(s) using RISA analysis software. All information contained herein is valid only for the described structure configuration and loading conditions. RAMAKER reserves the right to modify our recommendations should alterations to the mount loading occur.

If you have any questions or comments, please do not hesitate to contact our office.

Sincerely,

RAMAKER & ASSOCIATES, INC.

Kali L. Phillips

Kali L. Phillips Structural Designer

Supervising Engineer

ANALYSIS CRITERIA

| State Building Code | 2016 CT State Building Code |
|--|-----------------------------|
| Adopted Building Code | 2012 IBC |
| Referenced Standard | TIA-222-G |
| Risk Category | II |
| Ultimate Design Wind Speed, V _{ult} | 125 mph (3 sec. gust) |
| Nominal Design Wind Speed, Vasd | 97 mph (3 sec. gust) |
| Design Wind Speed w/ Ice | 40 mph (3 sec. gust) |
| Ice Thickness | 1 inch |
| Exposure Category | С |
| Topographic Category | 1 |
| Crest Height | N/A |

SUPPORTING DOCUMENTATION

- Structural analysis by RAMAKER, job number 23009, dated January 17, 2013
- Construction drawings by RAMAKER, job number 23009, dated May 13, 2014
- Construction drawings by RAMAKER, project number 23009
- Site visit(s) conducted by RAMAKER
- Other pertinent data procured or assumed by RAMAKER during site due diligence activities

MOUNT LOADING

RAMAKER understands that the loading to be used for this analysis will consist of the antennas and equipment configurations as shown in the following chart(s):

| Antenna Mount – Alpha Sector | | | | | | | |
|------------------------------|----------|--------------------------|----------------------|----------|--|--|--|
| Elevation | Position | Appurtenance | Mount Type | Status | | | |
| | 1 | | | | | | |
| | | (1) Andrew VHLP2-18 | | | | | |
| | 2 | (1) Argus LLPX310R | | Existing | | | |
| 170 | | (1) Samsung RRH | Multi-Sector | | | | |
| 170 | 3 | (1) RFS APXVSPP18-C-A20 | Platform w/ Handrail | Existing | | | |
| | | (1) Commscope DT465B-2XR | | | | | |
| | 4 | (1) ALU TD-RRH8X20 | | Proposed | | | |
| | | (1) ALU 800MHz 2x50W RRH | | | | | |

| Antenna Mount — Beta Sector | | | | | | | |
|-----------------------------|--|--------------------------|----------------------|----------|--|--|--|
| Elevation | Elevation Position Appurtenance Mount Type | | | | | | |
| | 1 | | | | | | |
| | | (1) Andrew VHLP800-11 | Multi-Sector | | | | |
| | 2 | (1) Argus LLPX310R | | Existing | | | |
| 170 | | (1) Samsung RRH | | | | | |
| 170 | 3 | (1) RFS APXVSPP18-C-A20 | Platform w/ Handrail | Existing | | | |
| | | (1) Commscope DT465B-2XR | | | | | |
| | 4 | (1) ALU TD-RRH8X20 | | Proposed | | | |
| | | (1) ALU 800MHz 2x50W RRH | | | | | |

| | Antenna Mount — Gamma Sector | | | | | | | | |
|-----------|--|--------------------------|--------------------------------------|-------------|--|--|--|--|--|
| Elevation | Elevation Position Appurtenance Mount Type | | | | | | | | |
| | 1 | | | | | | | | |
| | 2 | (1) RFS APXV9ERR18-C-A20 | | Existing | | | | | |
| | 3 | (1) Argus LLPX310R | | Fullation a | | | | | |
| 170 | 3 | (1) Samsung RRH | Multi-Sector Platform w/ Handrail | Existing | | | | | |
| | | (1) Commscope DT465B-2XR | | | | | | | |
| | 4 | (1) ALU TD-RRH8X20 | | Proposed | | | | | |
| | (1) ALU 800MHz 2×50W RRH | | | | | | | | |

| Collar Mount | | | | | |
|-------------------------------|---------------------------|------------|--|--|--|
| Elevation Appurtenance Status | | | | | |
| 175 | (3) ALU 800MHz 2x50W RRH | Fullations | | | |
| | (3) ALU 1900MHz 4x45W RRH | Existing | | | |

MOUNT RESULTS

By engineering calculation and inspection, the *proposed* antenna and equipment mounting structure(s) are capable of supporting the proposed loading configurations without causing an overstress condition in the antenna and equipment mounting structure(s). The existing antenna and equipment mounting structure(s) shall be removed and replaced with the proposed antenna and equipment mounting structure(s) prior to antenna and equipment installation. See attached details for the proposed mounting structures.

LIMITATIONS

The recommendations contained within this report were developed using the supporting documentation as previously described. All recommendations pertain only to the proposed antenna installation activities as described in this report. RAMAKER assumes no responsibility for failures caused by factors beyond our control. These include but are not limited to the following:

- Missing, corroding, and/or deteriorating members
- Improper manufacturing and/or construction
- Improper maintenance
- Member grades less than assumed grades show below:


| Assumed Steel Member Grades | | | | | |
|-----------------------------|------------------------|--|--|--|--|
| Angles/Plates | ASTM A36, 36 ksi | | | | |
| Pipes | ASTM A53 Gr. B, 35 ksi | | | | |
| HSS (Square Tube) | ASTM A36, 36 ksi | | | | |

Charles Cherundolo Consulting, Inc. is responsible for verifying that the loading on the structure is consistent with the loading applied to the structure within this report. If there is any information contrary to that contained herein, or if there are any defects arising from the original design, material, fabrication and erection deficiencies, this report should be disregarded and RAMAKER should be contacted immediately. RAMAKER is not liable for any representation, recommendation, or conclusion not expressly stated herein.


This analysis pertains only to the mounting structure, and no analyses or conclusions were made regarding the supporting structure. Analysis and certification of the supporting structure is performed and submitted separately.


ATTACHMENTS

- Mount Details
- Analysis Figures
- Analysis Calculations



| | | | PARTS LIST | | | |
|------|-----|----------|---|------------|----------|---------|
| ITEM | QTY | PART NO. | PART DESCRIPTION | LENGTH | UNIT WT. | NET WT. |
| 1 | 3 | X-LWRM | RING MOUNT WELDMENT | | 68.81 | 206.42 |
| 2 | 9 | G58R-48 | 5/8" x 48" THREADED ROD (HDG.) | | 0.40 | 3.59 |
| 2 | 9 | G58R-24 | 5/8" x 24" THREADED ROD (HDG.) | | 0.40 | 3.59 |
| 3 | 3 | X-SV196 | LOW PROFILE PLATFORM CORNER | | 212.10 | 636.31 |
| 4 | 12 | A58234 | 5/8" x 2-3/4" HDG A325 HEX BOLT | 2.75 | 0.36 | 4.27 |
| 5 | 12 | A58FW | 5/8" HDG A325 FLATWASHER | | 0.03 | 0.41 |
| 6 | 30 | G58LW | 5/8" HDG LOCKWASHER | | 0.03 | 0.78 |
| 7 | 30 | A58NUT | 5/8" HDG A325 HEX NUT | | 0.13 | 3.90 |
| 8 | 3 | P3150 | 3-1/2" X 150" SCH 40 GALVANIZED PIPE | 150.000 in | 94.80 | 284.40 |
| 9 | 36 | X-UB1306 | 1/2" X 3-5/8" X 6" X 3" U-BOLT (HDG.) | | 0.26 | 9.25 |
| 10 | 120 | G12FW | 1/2" HDG USS FLATWASHER | | 0.03 | 4.09 |
| 11 | 120 | G12LW | 1/2" HDG LOCKWASHER | | 0.01 | 1.67 |
| 12 | 120 | G12NUT | 1/2" HDG HEAVY 2H HEX NUT | | 0.07 | 8.60 |
| 13 | 12 | X-SP219 | SMALL SUPPORT CROSS PLATE | 8.250 in | 8.61 | 103.33 |
| 14 | 24 | X-UB1212 | 1/2" X 2-1/2" X 4-1/2" X 2" U-BOLT (HDG.) | | 0.26 | 6.17 |
| 15 | 12 | В | ANTENNA MOUNTING PIPE | С | D | E |





| 2-3/8" O.D. VERTICAL MOUNTING PIPES | | | | | | |
|-------------------------------------|--------------|-------------|------------------|-----------------|--------------|--|
| ASSEMBLY NO. "A" | PART NO. "B" | LENGTH, "C" | UNIT WEIGHT, "D" | NET WEIGHT, "E" | TOTAL WEIGHT | |
| RMQP-463 | P263 | 63" | 20.18 | 242.16 | 1591.11 | |
| RMQP-472 | P272 | 72" | 23.07 | 276.84 | 1625.79 | |
| RMQP-484 | P284 | 84" | 26.91 | 322.92 | 1671.87 | |
| RMQP-496 | P296 | 96" | 30.76 | 369.12 | 1718.07 | |
| RMQP-4126 | P2126 | 126" | 40.75 | 489.00 | 1837.95 | |

TOLERANCE NOTE

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE: SAWED, SHEARED AND GAS CUT EDGES (± 0.030") DRILLED AND GAS CUT HOLES (± 0.030") - NO CONING OF HOLES LASER CUT EDGES AND HOLES (± 0.010") - NO CONING OF HOLES BENDS ARE ± 1/2 DEGREE - ALL OTHER MACHINING (± 0.030") ALL OTHER ASSEMBLY (± 0.060")

PROPRIETARY NOTE

PROPRIETARY NOTE

THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF
VALMONT INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT
THE CONSIGNT OF VALMONT INDUSTRIES IS STRICTLY PROHIBITED.

DESCRIPTION

LOW PROFILE CO-LOCATION PLATFORM FOR 12 ANTENNAS WITH 12' 6" FACE WIDTH FOR 12" - 38" DIAMETER POLES




Engineering Support Team: 1-888-753-7446

Locations: New York, NY Atlanta, GA Los Angeles, CA Plymouth, IN Salem, OR Dallas, TX

| • | | | | | |
|-------------------------------|----------|------------|------|-----------|-----------|
| CUSTOMER SEE ASSEMBLY NO. "A" | | PD NO. | | RAWN BY | |
| SEE ASSEMBLY NO. "A" | | CUSTOMER | emb | 1/20/2012 | CEK |
| DMOD 4VV | DWG. NO. | KED BY | CHEC | OVAL | NG. APPRO |
| RMQP-4XX | | C 7/9/2015 | BM | | |

| Α | ADDED 10' 6" ANTENNA MOUNTING PIPES | | CEK | 7/9/2015 |
|-----|-------------------------------------|-----|-----|----------|
| REV | DESCRIPTION OF REVISIONS | CPD | BY | DATE |
| | DEVISION HISTORY | | | |



TOLERANCE NOTE

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE: SAWED, SHEARED AND GAS CUT EDGES (± 0.030") DRILLED AND GAS CUT HOLES (± 0.030") - NO CONING OF HOLES LASER CUT EDGES AND HOLES (± 0.010") - NO CONING OF HOLES BENDS ARE ± 1/2 DEGREE - ALL OTHER MACHINING (± 0.030") ALL OTHER ASSEMBLY (± 0.060")

CEK 7/9/2015 CPD BY DATE

A ADDED 10' 6" ANTENNA MOUNTING PIPES

DESCRIPTION OF REVISIONS

REVISION HISTORY

REV

PROPRIETARY NOTE

PROPRIETARY NOTE


THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF
VALMONT INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT
THE CONSENT OF VALMONT INDUSTRIES IS STRICTLY PROHIBITED.

DESCRIPTION LOW PROFILE CO-LOCATION PLATFORM FOR 12 ANTENNAS WITH 12' 6" FACE WIDTH


FOR 12" - 38" DIAMETER POLES

Locations: New York, NY Atlanta, GA Los Angeles, CA Plymouth, IN Salem, OR Dallas, TX Engineering Support Team: 1-888-753-7446

| | | | | | _ | | |
|---|------------|-----------|--------|-----------------|----------|----------------------|----|
| | DRAWN BY | | CPD NO | . DRAWING USAGE | PART NO. | | L |
| | CEK | 1/20/2012 | semb | CUSTOMER | | SEE ASSEMBLY NO. "A" | ٥ |
| ĺ | ENG. APPRO | | | ECKED BY | DWG. NO. | RMQP-4XX | 7 |
| | | | BI | MC 7/9/2015 | | THING! - TAN | '` |



| I | PARTS LIST | | | | | | | | |
|---------------|------------|----------------------|----------|---|--------|-------------|---------|--|--|
| I | ITEM | QTY | PART NO. | PART DESCRIPTION | LENGTH | UNIT WT. | NET WT. | | |
| Ī | 1 | 3 | P2150 | 2-3/8" OD X 150" SCH 40 GALVANIZED PIPE | 150 in | 48.06 | 144.17 | | |
| 2 3 X-AHCP AN | | | | ANGLE HANDRAIL CORNER PLATE | | 12.92 | 38.76 | | |
| 3 12 SCX1 | | | SCX1 | CROSSOVER PLATE 2-3/8" X 2-3/8" | | 3.71 | 44.50 | | |
| | 4 | 120 G12FW | | 1/2" HDG USS FLATWASHER | | 0.03 | 4.08 | | |
| I | 5 | 5 60 X-UB1212 1/2" > | | 1/2" X 2-1/2" X 4-1/2" X 2" U-BOLT (HDG.) | | 0.73 | 43.90 | | |
| 6 120 G12LW | | | G12LW | 1/2" HDG LOCKWASHER | | 0.01 | 1.67 | | |
| | 7 | 120 | G12NUT | 1/2" HDG HEAVY 2H HEX NUT | | 0.07 | 8.58 | | |
| | | | - | | - | TOTAL WT. # | 261.72 | | |



| TOLERANCE NOTES |
|--------------------------|
| TOLERANCES ON DIMENSIONS |

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE: SAWED, SHEARED AND GAS CUT EDGES (± 0.030")

DRILLED AND GAS CUT HOLES (± 0.030") - NO CONING OF HOLES LASER CUT EDGES AND HOLES (± 0.010") - NO CONING OF HOLES BENDS ARE ± 1/2 DEGREE

ALL OTHER MACHINING (± 0.030")

ALL OTHER ASSEMBLY (± 0.060")

PROPRIETARY NOTE: THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF VALMONT INDUSTRIES AND CONSIDERED A TRADE SECRET, ANY USE OR DISOLOSURE WITHOUT THE CONSENT OF VALMONT INDUSTRIES IS STRICTLY PROHISITED.

HANDRAIL KIT FOR 12'-6" FACE

DESCRIPTION





Engineering Support Team: 1-888-753-7446

Locations: New York, NY Atlanta, GA Los Angeles, CA Plymouth, IN Salem, OR Dallas, TX

| | CPD N | D. | KC8 5/30/2012 | ENG. APPROVAL | HRK12 | o } ~ |
|---|-------|-----|---------------|---------------|-------|----------|
| 1 | CLASS | SUB | DRAWING USAGE | CHECKED BY | | ПĘ |
| | 81 | 01 | CUSTOMER | BMC 7/14/2014 | HRK12 | |
| | | | | | • | |

| | | | | | ΙA |
|-----|--------------------------|-----|-----|-----------|----------|
| Α | REPLACED HCP WITH X-AHCP | | CEK | 7/10/2014 | L |
| REV | DESCRIPTION OF REVISIONS | CPD | BY | DATE | 먎 |
| | REVISION HISTORY | | | | IN V/ |







855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 Job: Unionville Police Dept.

Project: 23009

By: KLP

Date: 10/17/17

Wind Load on Antennas TIA-222-G

 $q_z = 0.00256 K_z K_{zt} K_d V^2 I$

 $F = q_z G_h C_a A_a$

Occupancy: II Classification of Structures (Table 2-1)

Exposure: B Exposure Category

V: 97 mph Basic Wind Speed (Annex B)

z: 170 ft Height above ground level to the center of the antenna

I: 1.00 Importance Factor (Table 2-3)

K_z: 1.15 Velocity Pressure Coefficient (2.6.5.2)

K_{zt}: 1.00 Topographic Factor (2.6.6.4)

K_d: 0.95 Wind Direction Probability Factor (Table 2-2)

q₂: 26.2 psf Velocity Pressure at Height z

G_h: 1.00 Strength Design of Appurtenances and their Connections

Mount & Antenna Wind Loads

| Appurtenance | Height | Width | h/D | Shape | C_a | A_f | Force | Force |
|---------------------------|--------|-------|------|---------|-------|-------|-------|-------|
| | in | in | | | | sq ft | lb | plf |
| LLPX310R | 42.4 | 11.8 | 3.6 | Flat | 1.248 | 3.48 | 113.8 | |
| APXVSPP18-C-A20 | 72.0 | 11.9 | 6.1 | Flat | 1.358 | 5.95 | 211.7 | |
| APXV9ERR18-C-A20 | 72.0 | 11.9 | 6.1 | Flat | 1.358 | 5.95 | 211.7 | |
| DT465B-2XR | 71.9 | 13.8 | 5.2 | Flat | 1.320 | 6.89 | 238.6 | |
| RRH | 16.1 | 11.6 | 1.4 | Flat | 1.200 | 1.30 | 40.8 | |
| TD-RRH8x20 | 26.1 | 18.6 | 1.4 | Flat | 1.200 | 3.37 | 106.1 | |
| VHLP2-18 | 26.1 | 0.0 | 1.0 | Generic | 1.262 | 3.72 | 122.9 | |
| VHLP800-11 | 35.0 | 0.0 | 1.0 | Generic | 1.262 | 6.68 | 221.0 | |
| 800MHz 2x50W RRH | 19.0 | 13.0 | 1.5 | Flat | 1.200 | 1.72 | 54.0 | |
| Pipe3STD x 12.5 ft | 150.0 | 3.5 | 42.9 | Round | 1.200 | 3.65 | 114.7 | 9.2 |
| Pipe3STD x 10 ft | 120.0 | 3.5 | 34.3 | Round | 1.200 | 2.92 | 91.8 | 9.2 |
| Pipe2STD x 7 ft | 84.0 | 2.4 | 35.4 | Round | 1.200 | 1.39 | 43.6 | 6.2 |
| L2X2X3/16 x 4.138 ft | 49.7 | 2.0 | 24.8 | Flat | 1.994 | 0.69 | 36.1 | 8.7 |
| HSS4X4X1/4 x 6.5 ft | 78.0 | 4.0 | 19.5 | Flat | 1.817 | 2.17 | 103.2 | 15.9 |
| HSS4X4X1/4 x 2.713 ft | 32.6 | 4.0 | 8.1 | Flat | 1.438 | 0.90 | 34.1 | 12.6 |
| PL 6x1/4 x 1.289 ft | 15.5 | 6.0 | 2.6 | Flat | 1.203 | 0.64 | 20.3 | 15.8 |
| Pipe3STD x 7 ft | 84.0 | 3.5 | 24.0 | Round | 1.178 | 2.04 | 63.0 | 9.0 |
| Pipe2STD x 12.5 ft | 150.0 | 2.4 | 63.2 | Round | 1.200 | 2.47 | 77.8 | 6.2 |
| L2-1/2X2-1/2X1/4 x 1.3 ft | 15.6 | 2.5 | 6.2 | Flat | 1.366 | 0.27 | 9.7 | 7.5 |



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 Job: Unionville Police Dept.

Project: 23009

By: KLP

Date: 10/17/17

Wind Load on Antennas TIA-222-G

 $q_z = 0.00256 K_z K_{zt} K_d V^2 I$

 $F = q_z G_h C_a A_a$

Occupancy: II Classification of Structures (Table 2-1)

Exposure: B Exposure Category

V: 97 mph Basic Wind Speed (Annex B)

z: 170 ft Height above ground level to the center of the antenna

I: 1.00 Importance Factor (Table 2-3)

K_z: 1.15 Velocity Pressure Coefficient (2.6.5.2)

K_{zt}: 1.00 Topographic Factor (2.6.6.4)

K_d: 0.95 Wind Direction Probability Factor (Table 2-2)

q₂: 26.2 psf Velocity Pressure at Height z

G_h: 1.00 Strength Design of Appurtenances and their Connections

Mount & Antenna Wind Loads

| Appurtenance | Height | Depth | h/D | Shape | C_a | A_f | Force | Force |
|---------------------------|--------|-------|------|---------|-------|-------|-------|-------|
| | in | in | | | | sq ft | lb | plf |
| LLPX310R | 42.4 | 4.5 | 9.4 | Flat | 1.479 | 1.33 | 51.7 | |
| APXVSPP18-C-A20 | 72.0 | 7.0 | 10.3 | Flat | 1.509 | 3.50 | 138.7 | |
| APXV9ERR18-C-A20 | 72.0 | 7.9 | 9.1 | Flat | 1.470 | 3.95 | 152.3 | |
| DT465B-2XR | 71.9 | 8.2 | 8.8 | Flat | 1.459 | 4.09 | 156.6 | |
| RRH | 16.1 | 5.3 | 3.0 | Flat | 1.224 | 0.59 | 19.0 | |
| TD-RRH8x20 | 26.1 | 6.7 | 3.9 | Flat | 1.262 | 1.21 | 40.2 | |
| VHLP2-18 | 26.1 | 0.0 | 1.0 | Generic | 0.625 | 3.72 | 60.9 | |
| VHLP800-11 | 35.0 | 0.0 | 1.0 | Generic | 0.625 | 6.68 | 109.5 | |
| 800MHz 2x50W RRH | 19.0 | 12.2 | 1.6 | Flat | 1.200 | 1.61 | 50.6 | |
| | | | | | | | | |
| Pipe3STD x 12.5 ft | 150.0 | 3.5 | 42.9 | Round | 1.200 | 3.65 | 114.7 | 9.2 |
| Pipe3STD x 10 ft | 120.0 | 3.5 | 34.3 | Round | 1.200 | 2.92 | 91.8 | 9.2 |
| Pipe2STD x 7 ft | 84.0 | 2.4 | 35.4 | Round | 1.200 | 1.39 | 43.6 | 6.2 |
| L2X2X3/16 x 4.138 ft | 49.7 | 2.0 | 24.8 | Flat | 1.994 | 0.69 | 36.1 | 8.7 |
| HSS4X4X1/4 x 6.5 ft | 78.0 | 4.0 | 19.5 | Flat | 1.817 | 2.17 | 103.2 | 15.9 |
| HSS4X4X1/4 x 2.713 ft | 32.6 | 4.0 | 8.1 | Flat | 1.438 | 0.90 | 34.1 | 12.6 |
| PL 6x1/4 x 1.289 ft | 15.5 | 0.3 | 61.9 | Flat | 2.000 | 0.03 | 1.4 | 1.1 |
| Pipe3STD x 7 ft | 84.0 | 3.5 | 24.0 | Round | 1.178 | 2.04 | 63.0 | 9.0 |
| Pipe2STD x 12.5 ft | 150.0 | 2.4 | 63.2 | Round | 1.200 | 2.47 | 77.8 | 6.2 |
| L2-1/2X2-1/2X1/4 x 1.3 ft | 15.6 | 2.5 | 6.2 | Flat | 1.366 | 0.27 | 9.7 | 7.5 |
| | | | | | | | | |



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 Job: Unionville Police Dept.

Project: 23009

By: KLP

Date: 10/17/17

Ice Wind Load on Antennas TIA-222-G

 $q_z = 0.00256 K_z K_{zt} K_d V^2 I$

 $F = q_z G_h C_a A_a$

Occupancy: II Classification of Structures (Table 2-1)

Exposure: B Exposure Category

V_i: 40 mph Basic Wind Speed (Annex B)

z: 170 ft Height above ground level to the center of the antenna

I: 1.00 Importance Factor (Table 2-3)

K_z: 1.15 Velocity Pressure Coefficient (2.6.5.2)

K_{zt}: 1.00 Topographic Factor (2.6.6.4)

K_d: 0.95 Wind Direction Probability Factor (Table 2-2)

q₂: 4.47 psf Velocity Pressure at Height z

G_h: 1.00 Strength Design of Appurtenances and their Connections

 K_{iz} : 1.18 Height Escalation Factor for Ice Thickness

t_{iz}: 2.36 in Factored Thickness of Radial Glaze Ice at Height z

Mount & Antenna Ice Wind Loads

| Appurtenance | Height | Width | h/D | Shape | C_a | A_f | Force | Force |
|---------------------------|--------|-------|------|---------|-------|-------|-------|-------|
| | in | in | | | | sq ft | lb | plf |
| LLPX310R | 47.1 | 16.5 | 2.9 | Flat | 1.216 | 5.41 | 29.4 | |
| APXVSPP18-C-A20 | 76.7 | 16.6 | 4.6 | Flat | 1.294 | 8.85 | 51.2 | |
| APXV9ERR18-C-A20 | 76.7 | 16.6 | 4.6 | Flat | 1.294 | 8.85 | 51.2 | |
| DT465B-2XR | 76.6 | 18.5 | 4.1 | Flat | 1.273 | 9.85 | 56.1 | |
| RRH | 20.8 | 16.3 | 1.3 | Flat | 1.200 | 2.36 | 12.7 | |
| TD-RRH8x20 | 30.8 | 23.3 | 1.3 | Flat | 1.200 | 4.99 | 26.8 | |
| VHLP2-18 | 30.8 | 4.7 | 1.0 | Generic | 1.262 | 5.18 | 29.2 | |
| VHLP800-11 | 39.7 | 4.7 | 1.0 | Generic | 1.262 | 8.60 | 48.6 | |
| 800MHz 2x50W RRH | 23.7 | 17.7 | 1.3 | Flat | 1.200 | 2.92 | 15.7 | |
| | | | | | | | | |
| Pipe3STD x 12.5 ft | 154.7 | 8.2 | 18.8 | Round | 1.063 | 8.82 | 42.0 | 3.3 |
| Pipe3STD x 10 ft | 124.7 | 8.2 | 15.2 | Round | 0.982 | 7.11 | 31.3 | 3.0 |
| Pipe2STD x 7 ft | 88.7 | 7.1 | 12.5 | Round | 0.923 | 4.37 | 18.0 | 2.4 |
| L2X2X3/16 x 4.138 ft | 54.4 | 6.7 | 8.1 | Flat | 1.437 | 2.53 | 16.3 | 3.6 |
| HSS4X4X1/4 x 6.5 ft | 82.7 | 8.7 | 9.5 | Flat | 1.483 | 5.00 | 33.2 | 4.8 |
| HSS4X4X1/4 x 2.713 ft | 37.3 | 8.7 | 4.3 | Flat | 1.279 | 2.25 | 12.9 | 4.2 |
| PL 6x1/4 x 1.289 ft | 20.2 | 10.7 | 1.9 | Flat | 1.200 | 1.50 | 8.1 | 4.8 |
| Pipe3STD x 7 ft | 88.7 | 8.2 | 10.8 | Round | 0.884 | 5.06 | 20.0 | 2.7 |
| Pipe2STD x 12.5 ft | 154.7 | 7.1 | 21.8 | Round | 1.130 | 7.61 | 38.5 | 3.0 |
| L2-1/2X2-1/2X1/4 x 1.3 ft | 20.3 | 7.2 | 2.8 | Flat | 1.214 | 1.02 | 5.5 | 3.3 |
| | | | | | | | | |



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 Job: Unionville Police Dept.

Project: 23009

By: KLP

Date: 10/17/17

Ice Wind Load on Antennas TIA-222-G

 $q_z = 0.00256 K_z K_{zt} K_d V^2 I$

 $F = q_z G_h C_a A_a$

Occupancy: II Classification of Structures (Table 2-1)

Exposure: B Exposure Category

V_i: 40 mph Basic Wind Speed (Annex B)

z: 170 ft Height above ground level to the center of the antenna

I: 1.00 Importance Factor (Table 2-3)

K_z: 1.15 Velocity Pressure Coefficient (2.6.5.2)

K_{zt}: 1.00 Topographic Factor (2.6.6.4)

K_d: 0.95 Wind Direction Probability Factor (Table 2-2)

q₂: 4.47 psf Velocity Pressure at Height z

G_h: 1.00 Strength Design of Appurtenances and their Connections

 K_{iz} : 1.18 Height Escalation Factor for Ice Thickness

t_{iz}: 2.36 in Factored Thickness of Radial Glaze Ice at Height z

Mount & Antenna Ice Wind Loads

| Appurtenance | Height | Depth | h/D | Shape | C_a | A_f | Force | Force |
|---------------------------|--------|-------|------|---------|-------|-------|-------|-------|
| | in | in | | | | sq ft | lb | plf |
| LLPX310R | 47.1 | 9.2 | 5.1 | Flat | 1.316 | 3.02 | 17.8 | |
| APXVSPP18-C-A20 | 76.7 | 11.7 | 6.5 | Flat | 1.380 | 6.24 | 38.6 | |
| APXV9ERR18-C-A20 | 76.7 | 12.6 | 6.1 | Flat | 1.359 | 6.72 | 40.9 | |
| DT465B-2XR | 76.6 | 12.9 | 5.9 | Flat | 1.353 | 6.87 | 41.6 | |
| RRH | 20.8 | 10.0 | 2.1 | Flat | 1.200 | 1.45 | 7.8 | |
| TD-RRH8x20 | 30.8 | 11.4 | 2.7 | Flat | 1.209 | 2.44 | 13.2 | |
| VHLP2-18 | 30.8 | 4.7 | 1.0 | Generic | 0.625 | 5.18 | 14.5 | |
| VHLP800-11 | 39.7 | 4.7 | 1.0 | Generic | 0.625 | 8.60 | 24.1 | |
| 800MHz 2x50W RRH | 23.7 | 16.9 | 1.4 | Flat | 1.200 | 2.78 | 15.0 | |
| | | | | | | | | |
| Pipe3STD x 12.5 ft | 154.7 | 8.2 | 18.8 | Round | 1.063 | 8.82 | 42.0 | 3.3 |
| Pipe3STD x 10 ft | 124.7 | 8.2 | 15.2 | Round | 0.982 | 7.11 | 31.3 | 3.0 |
| Pipe2STD x 7 ft | 88.7 | 7.1 | 12.5 | Round | 0.923 | 4.37 | 18.0 | 2.4 |
| L2X2X3/16 x 4.138 ft | 54.4 | 6.7 | 8.1 | Flat | 1.437 | 2.53 | 16.3 | 3.6 |
| HSS4X4X1/4 x 6.5 ft | 82.7 | 8.7 | 9.5 | Flat | 1.483 | 5.00 | 33.2 | 4.8 |
| HSS4X4X1/4 x 2.713 ft | 37.3 | 8.7 | 4.3 | Flat | 1.279 | 2.25 | 12.9 | 4.2 |
| PL 6x1/4 x 1.289 ft | 20.2 | 5.0 | 4.1 | Flat | 1.270 | 0.70 | 4.0 | 2.3 |
| Pipe3STD x 7 ft | 88.7 | 8.2 | 10.8 | Round | 0.884 | 5.06 | 20.0 | 2.7 |
| Pipe2STD x 12.5 ft | 154.7 | 7.1 | 21.8 | Round | 1.130 | 7.61 | 38.5 | 3.0 |
| L2-1/2X2-1/2X1/4 x 1.3 ft | 20.3 | 7.2 | 2.8 | Flat | 1.214 | 1.02 | 5.5 | 3.3 |
| | | | | | | | | |



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 Job: Unionville Police Dept.

Project: 23009

By: KLP

Date: 10/17/17

Ice Load on Antennas TIA-222-G

Ice Weight: Ice Density 56 pcf t_i: 1.00 Design Ice Thickness Occupancy: Classification of Structures (Table 2-1) Ш Exposure: В **Exposure Category** V_i : Basic Wind Speed (Annex B) 40 mph 170 ft Height above ground level to the center of the antenna z: 1.00 Importance Factor (Table 2-3) 1: K_{iz}: 1.18 Height Escalation Factor for Ice Thickness K_{zt}: 1.00 Topographic Factor (2.6.6.4) 2.36 in Factored Thickness of Radial Glaze Ice at Height z t_{iz}:

Platform Grating:

Expanded

Ice Load:

11.0 psf

Mount & Antenna Ice Wind Loads

| Appurtenance | Height | Width | Depth | Diam. | Area | Perim. | Ice W | eight |
|---------------------------|--------|-------|-------|-------|--------|--------|-------|-------|
| | in | in | in | in | sq in | in | lb | plf |
| LLPX310R | 47.1 | 16.5 | 9.2 | 12.65 | 111.08 | 42.10 | 152.6 | |
| APXVSPP18-C-A20 | 76.7 | 16.6 | 11.7 | 13.80 | 119.60 | 47.22 | 279.1 | |
| APXV9ERR18-C-A20 | 76.7 | 16.6 | 12.6 | 14.28 | 123.11 | 49.01 | 287.3 | |
| DT465B-2XR | 76.6 | 18.5 | 12.9 | 16.05 | 136.27 | 53.43 | 317.5 | |
| RRH | 20.8 | 16.3 | 10.0 | 12.75 | 111.85 | 43.23 | 58.4 | |
| TD-RRH8x20 | 30.8 | 23.3 | 11.4 | 19.77 | 163.79 | 60.03 | 138.5 | |
| VHLP2-18 | - | - | - | - | - | - | 154.2 | |
| VHLP800-11 | - | - | - | - | - | - | 180.0 | |
| 800MHz 2x50W RRH | 23.7 | 17.7 | 16.9 | 17.83 | 149.41 | 59.83 | 92.0 | |
| | | | | | | | | |
| Pipe3STD x 12.5 ft | 154.7 | 8.2 | 8.2 | 3.50 | 43.35 | 18.40 | 210.7 | 16.9 |
| Pipe3STD x 10 ft | 124.7 | 8.2 | 8.2 | 3.50 | 43.35 | 18.40 | 168.6 | 16.9 |
| Pipe2STD x 7 ft | 88.7 | 7.1 | 7.1 | 2.38 | 35.02 | 14.86 | 95.3 | 13.6 |
| .2X2X3/16 x 4.138 ft | 54.4 | 6.7 | 6.7 | 2.83 | 38.38 | 17.43 | 61.8 | 14.9 |
| HSS4X4X1/4 x 6.5 ft | 82.7 | 8.7 | 8.7 | 5.19 | 55.87 | 31.69 | 141.2 | 21.7 |
| HSS4X4X1/4 x 2.713 ft | 37.3 | 8.7 | 8.7 | 5.19 | 55.87 | 31.69 | 58.9 | 21.7 |
| PL 6x1/4 x 1.289 ft | 20.2 | 10.7 | 5.0 | 6.01 | 61.90 | 21.93 | 31.0 | 24.1 |
| Pipe3STD x 7 ft | 88.7 | 8.2 | 8.2 | 3.50 | 43.35 | 18.40 | 118.0 | 16.9 |
| Pipe2STD x 12.5 ft | 154.7 | 7.1 | 7.1 | 2.38 | 35.02 | 14.86 | 170.2 | 13.6 |
| L2-1/2X2-1/2X1/4 x 1.3 ft | 20.3 | 7.2 | 7.2 | 3.54 | 43.61 | 19.43 | 22.0 | 17.0 |



Oct 18, 2017 3:07 PM Checked By:_

Hot Rolled Steel Properties

| | Label | E [ksi] | G [ksi] | Nu | Therm (\1E | .Density[k/ft | Yield[ksi] | Ry | Fu[ksi] | Rt |
|---|------------|---------|---------|----|------------|---------------|------------|-----|---------|-----|
| 1 | A36 Gr.36 | 29000 | 11154 | .3 | .65 | .49 | 36 | 1.5 | 58 | 1.2 |
| 2 | A572 Gr.50 | 29000 | 11154 | .3 | .65 | .49 | 50 | 1.1 | 65 | 1.1 |
| 3 | A992 | 29000 | 11154 | .3 | .65 | .49 | 50 | 1.1 | 65 | 1.1 |
| 4 | A500 Gr.42 | 29000 | 11154 | .3 | .65 | .49 | 42 | 1.4 | 58 | 1.3 |
| 5 | A500 Gr.46 | 29000 | 11154 | .3 | .65 | .49 | 46 | 1.4 | 58 | 1.3 |
| 6 | A53 Gr. B | 29000 | 11154 | .3 | .65 | .49 | 35 | 1.5 | 60 | 1.2 |

Hot Rolled Steel Section Sets

| | Label | Shape | Type | Design List | Material | Design R | A [in2] | lyy [in4] | Izz [in4] | J [in4] |
|---|--------------|------------|------|--------------|-----------|----------|---------|-----------|-----------|---------|
| 1 | HSS4x4x1/4 | HSS4x4x4 | Beam | SquareTube | A36 Gr.36 | Typical | 3.37 | 7.8 | 7.8 | 12.8 |
| 2 | L2x2x3/16 | L2x2x3 | Beam | Single Angle | A36 Gr.36 | Typical | .722 | .271 | .271 | .009 |
| 3 | L2.5x2.5x1/4 | L2.5x2.5x4 | Beam | Single Angle | A36 Gr.36 | Typical | 1.19 | .692 | .692 | .026 |
| 4 | Pipe 3.0 | PIPE 3.0 | Beam | Pipe | A53 Gr. B | Typical | 2.07 | 2.85 | 2.85 | 5.69 |
| 5 | Pipe 2.0 | PIPE 2.0 | Beam | Pipe . | A53 Gr. B | Typical | 1.02 | .627 | .627 | 1.25 |
| 6 | PL 6x1/2 | 1/2 x 6 | Beam | Pipe | A36 Gr.36 | Typical | 3 | 9 | .063 | .237 |

Member Primary Data

| | Label | I Joint | J Joint | K Joint | Rotate(deg) | Section/Shape | Туре | Design List | Material | Design Rules |
|----|-------|---------|---------|---------|-------------|---------------|------|--------------|-----------|--------------|
| 1 | H3 | N1 | N2 | | , ,, | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 2 | H1 | N3 | N4 | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 3 | PL2 | N5 | N6 | | 90 | PL 6x1/2 | Beam | Pipe | A36 Gr.36 | Typical |
| 4 | H2 | N7 | N8 | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 5 | PL3 | N9 | N10 | | 90 | PL 6x1/2 | Beam | Pipe | A36 Gr.36 | Typical |
| 6 | PL1 | N11 | N12 | | 90 | PL 6x1/2 | Beam | Pipe | A36 Gr.36 | Typical |
| 7 | SA1 | N90 | N14 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 8 | SA3 | N15 | N91 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 9 | SA2 | N17 | N94 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 10 | A1 | N19 | N20 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 11 | A2 | N20 | N21 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 12 | C1 | N27 | N22 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 13 | B2 | N25 | N23 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 14 | B1 | N24 | N25 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 15 | C2 | N26 | N27 | | | HSS4x4x1/4 | Beam | SquareTube | A36 Gr.36 | Typical |
| 16 | L5 | N32 | N33 | | | L2x2x3/16 | Beam | Single Angle | | Typical |
| 17 | L4 | N34 | N35 | | 270 | L2x2x3/16 | Beam | Single Angle | | Typical |
| 18 | L2 | N36 | N37 | | 270 | L2x2x3/16 | Beam | Single Angle | A36 Gr.36 | Typical |
| 19 | L3 | N38 | N39 | | 270 | L2x2x3/16 | Beam | Single Angle | A36 Gr.36 | Typical |
| 20 | MP5 | N68 | N56 | | | Pipe_2.0 | Beam | | A53 Gr. B | Typical |
| 21 | MP7 | N72 | N60 | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 22 | L6 | N78 | N79A | | 270 | L2x2x3/16 | Beam | Single Angle | A36 Gr.36 | Typical |
| 23 | L1 | N80 | N81 | | 270 | L2x2x3/16 | Beam | Single Angle | A36 Gr.36 | Typical |
| 24 | MP8 | N59 | N58 | | | Pipe_2.0 | Beam | Pipe | A53 Gr. B | Typical |
| 25 | MP6 | N57A | N56A | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 26 | MP1 | N62 | N64 | | | Pipe_2.0 | Beam | Pipe | A53 Gr. B | Typical |
| 27 | MP2 | N65 | N63 | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 28 | MP4 | N74 | N73 | | | Pipe_2.0 | Beam | Pipe | A53 Gr. B | Typical |
| 29 | MP3 | N77 | N76 | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 30 | MP9 | N84 | N82 | | | Pipe_2.0 | Beam | | A53 Gr. B | Typical |
| 31 | MP11 | N85 | N83 | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 32 | MP12 | N93 | N92 | | | Pipe_2.0 | Beam | Pipe | A53 Gr. B | Typical |
| 33 | MP10 | N96 | N95 | | | Pipe 3.0 | Beam | Pipe | A53 Gr. B | Typical |
| 34 | TH3 | N77A | N78A | | | Pipe_2.0 | Beam | Pipe | A53 Gr. B | Typical |
| 35 | TH1 | N79B | N80B | | | Pipe_2.0 | Beam | Pipe | A53 Gr. B | Typical |



Oct 18, 2017 3:07 PM Checked By:_

Member Primary Data (Continued)

| | Label | I Joint | J Joint | K Joint | Rotate(deg) | Section/Shape | Type | Design List | Material | Design Rules |
|----|-------|---------|---------|---------|-------------|---------------|------|--------------|-----------|--------------|
| 36 | TH2 | N83A | N84A | | | Pipe 2.0 | Beam | Pipe | A53 Gr. B | Typical |
| 37 | AN1 | N87 | N88 | | 180 | L2.5x2.5x1/4 | Beam | Single Angle | A36 Gr.36 | Typical |
| 38 | M40 | N87 | N101 | | | RIGID | None | None | RIGID | Typical |
| 39 | M41 | N88 | N102 | | | RIGID | None | None | RIGID | Typical |
| 40 | AN2 | N100A | N101A | | 180 | L2.5x2.5x1/4 | Beam | Single Angle | A36 Gr.36 | Typical |
| 41 | M41A | N100A | N102A | | | RIGID | None | None | RIGID | Typical |
| 42 | M42 | N101A | N103 | | | RIGID | None | None | RIGID | Typical |
| 43 | AN3 | N104 | N105 | | 180 | L2.5x2.5x1/4 | Beam | Single Angle | A36 Gr.36 | Typical |
| 44 | M44 | N104 | N106 | | | RIGID | None | None | RIGID | Typical |
| 45 | M45 | N105 | N107 | | | RIGID | None | None | RIGID | Typical |

Basic Load Cases

| | BLC Description | Category | X Gravity | Y Gravity | 7 Gravity | Joint | Point | Distributed | Area(Me | Surface(P |
|----|-----------------------|----------|-----------|-----------|-----------|-------|-------|-------------|---------|-----------|
| 1 | Dead Load | None | 7. 0.4 | -1 | | | 29 | | 3 | |
| 2 | Antenna Wind 0 | None | | | | | 58 | | | |
| 3 | Antenna Wind 30 | None | | | | | 58 | | | |
| 4 | Antenna Wind 45 | None | | | | | 58 | | | |
| 5 | Antenna Wind 60 | None | | | | | 58 | | | |
| 6 | Antenna Wind 90 | None | | | | | 58 | | | |
| 7 | Antenna Wind 120 | None | | | | | 58 | | | |
| 8 | Antenna Wind 135 | None | | | | | 58 | | | |
| 9 | Antenna Wind 150 | None | | | | | 58 | | | |
| 10 | Antenna Wind 180 | None | | | | | 58 | | | |
| 11 | Antenna Wind 210 | None | | | | | 58 | | | |
| 12 | Antenna Wind 225 | None | | | | | 58 | | | |
| 13 | Antenna Wind 240 | None | | | | | 58 | | | |
| 14 | Antenna Wind 270 | None | | | | | 58 | | | |
| 15 | Antenna Wind 300 | None | | | | | 58 | | | |
| 16 | Antenna Wind 315 | None | | | | | 58 | | | |
| 17 | Antenna Wind 330 | None | | | | | 58 | | | |
| 18 | Antenna Ice Dead Load | None | | | | | 29 | | | |
| 19 | Antenna Wind w/Ice 0 | None | | | | | 58 | | | |
| 20 | Antenna Wind w/Ice 30 | None | | | | | 58 | | | |
| 21 | Antenna Wind w/Ice 45 | None | | | | | 58 | | | |
| 22 | Antenna Wind w/Ice 60 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 90 | None | | | | | 58 | | | |
| 24 | Antenna Wind w/Ice 1 | None | | | | | 58 | | | |
| 25 | Antenna Wind w/Ice 1 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 1 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 1 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 2 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 2 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 2 | None | | | | | 58 | | | |
| 31 | Antenna Wind w/Ice 2 | None | | | | | 58 | | | |
| 32 | Antenna Wind w/Ice 3 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 3 | None | | | | | 58 | | | |
| | Antenna Wind w/Ice 3 | None | | | | | 58 | | | |
| 35 | Member Wind 0 | None | | | | | | 78 | | |
| 36 | Member Wind 30 | None | | | | | | 78 | | |
| 37 | Member Wind 45 | None | | | | | | 78 | | |
| 38 | Member Wind 60 | None | | | | | | 78 | | |
| 39 | Member Wind 90 | None | | | | | | 78 | | |
| 40 | Member Wind 120 | None | | | | | | 78 | | |
| 41 | Member Wind 135 | None | | | | | | 78 | | |
| 42 | Member Wind 150 | None | | | | | | 78 | | |



: Ramaker & Associates : KLP : 23009

Company : Ramaker & Associates
Designer : KLP
Job Number : 23009
Model Name : Unionville / Police Dept. (CT33XC534-B)

Oct 18, 2017 3:07 PM Checked By:_

Basic Load Cases (Continued)

| | BLC Description | Category | X Gravity | Y Gravity | Z Gravity | Joint | Point | Distributed | Area(Me | Surface(P |
|----|----------------------|----------|-----------|-----------|-----------|-------|-------|-------------|---------|-----------|
| 43 | Member Wind 180 | None | | | | | | 78 | | |
| 44 | Member Wind 210 | None | | | | | | 78 | | |
| 45 | Member Wind 225 | None | | | | | | 78 | | |
| 46 | Member Wind 240 | None | | | | | | 78 | | |
| 47 | Member Wind 270 | None | | | | | | 78 | | |
| 48 | Member Wind 300 | None | | | | | | 78 | | |
| 49 | Member Wind 315 | None | | | | | | 78 | | |
| 50 | Member Wind 330 | None | | | | | | 78 | | |
| 51 | Member Ice Dead Load | None | | | | | | 39 | 3 | |
| 52 | Member Wind w/Ice 0 | None | | | | | | 78 | | |
| 53 | Member Wind w/Ice 30 | None | | | | | | 78 | | |
| 54 | Member Wind w/Ice 45 | None | | | | | | 78 | | |
| 55 | Member Wind w/Ice 60 | None | | | | | | 78 | | |
| 56 | Member Wind w/Ice 90 | None | | | | | | 78 | | |
| 57 | Member Wind w/Ice 1 | None | | | | | | 78 | | |
| 58 | Member Wind w/Ice 1 | None | | | | | | 78 | | |
| 59 | Member Wind w/Ice 1 | None | | | | | | 78 | | |
| 60 | Member Wind w/Ice 1 | None | | | | | | 78 | | |
| 61 | Member Wind w/Ice 2 | None | | | | | | 78 | | |
| 62 | Member Wind w/Ice 2 | None | | | | | | 78 | | |
| 63 | Member Wind w/Ice 2 | None | | | | | | 78 | | |
| 64 | Member Wind w/Ice 2 | None | | | | | | 78 | | |
| 65 | Member Wind w/Ice 3 | None | | | | | | 78 | | |
| 66 | Member Wind w/Ice 3 | None | | | | | | 78 | | |
| 67 | Member Wind w/Ice 3 | None | | | | | | 78 | | |
| 68 | Live Load - Area | None | | | | | | | 3 | |
| 69 | Live Load - Point 1 | None | | | | | 3 | | | |
| 70 | Live Load - Point 2 | None | | | | | 1 | | | |
| 71 | Live Load - Point 3 | None | | | | | 1 | | | |
| 72 | Railing Dist. LL z | None | | | | | | 3 | | |
| 73 | Railing Dist. LL x | None | | | | | | 3 | | |
| 74 | Railing Point LL z | None | | | | | 3 | | | |
| 75 | Railing Point LL x | None | | | | | 3 | | | |
| 76 | BLC 1 Transient Area | None | | | | | | 43 | | |
| 77 | BLC 51 Transient Are | None | | | | | | 45 | | |
| 78 | BLC 68 Transient Are | None | | | | | | 45 | | |

Load Combinations

| | Description | So | P | S | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa |
|----|-----------------------|-----|---|---|-----|-----|-----|-----|-----|-----|-----|----|-----|----|-----|----|-----|----|-----|----|-----|----|-----|----|
| 1 | 1.4D | Yes | Υ | | 1 | 1.4 | | | | | | | | | | | | | | | | | | |
| 2 | 0.9D + 1.6 (0-Wind) | Yes | Υ | | 1 | .9 | 2 | 1.6 | 35 | 1.6 | | | | | | | | | | | | | | |
| 3 | 0.9D + 1.6 (30-Wind) | Yes | Υ | | 1 | .9 | 3 | 1.6 | 36 | 1.6 | | | | | | | | | | | | | | |
| 4 | 0.9D + 1.6 (45-Wind) | Yes | Υ | | 1 | .9 | 4 | 1.6 | 37 | 1.6 | | | | | | | | | | | | | | |
| 5 | 0.9D + 1.6 (60-Wind) | Yes | Υ | | 1 | .9 | 5 | 1.6 | 38 | 1.6 | | | | | | | | | | | | | | |
| 6 | 0.9D + 1.6 (90-Wind) | Yes | Υ | | 1 | .9 | 6 | 1.6 | 39 | 1.6 | | | | | | | | | | | | | | |
| 7 | 0.9D + 1.6 (120-Wind) | Yes | Υ | | 1 | .9 | 7 | 1.6 | 40 | 1.6 | | | | | | | | | | | | | | |
| 8 | 0.9D + 1.6 (135-Wind) | Yes | Υ | | 1 | .9 | 8 | 1.6 | 41 | 1.6 | | | | | | | | | | | | | | |
| 9 | 0.9D + 1.6 (150-Wind) | Yes | Υ | | 1 | .9 | 9 | 1.6 | 42 | 1.6 | | | | | | | | | | | | | | |
| 10 | 0.9D + 1.6 (180-Wind) | Yes | Υ | | 1 | .9 | 10 | 1.6 | 43 | 1.6 | | | | | | | | | | | | | | |
| 11 | 0.9D + 1.6 (210-Wind) | Yes | Υ | | 1 | .9 | 11 | 1.6 | 44 | 1.6 | | | | | | | | | | | | | | |
| 12 | 0.9D + 1.6 (225-Wind) | Yes | Υ | | 1 | .9 | 12 | 1.6 | 45 | 1.6 | | | | | | | | | | | | | | |
| 13 | 0.9D + 1.6 (240-Wind) | Yes | Υ | | 1 | .9 | 13 | 1.6 | 46 | 1.6 | | | | | | | | | | | | | | |
| 14 | 0.9D + 1.6 (270-Wind) | Yes | Υ | | 1 | .9 | 14 | 1.6 | 47 | 1.6 | | | | | | | | | | | | | | |
| 15 | 0.9D + 1.6 (300-Wind) | Yes | Υ | | 1 | .9 | 15 | 1.6 | 48 | 1.6 | | | | | | | | | | | | | | |
| 16 | 0.9D + 1.6 (315-Wind) | Yes | Υ | | 1 | .9 | 16 | 1.6 | 49 | 1.6 | | | | | | | | | | | | | | |



: Ramaker & Associates : KLP : 23009

Oct 18, 2017 3:07 PM Checked By:_

Load Combinations (Continued)

| | Description | SoP | с DI | CEa | DI C | `E0 | ВΙС | Eo | DI C | Eo | DI C | `E0 | DI C | Eo | | Eo | DI C | ·E0 | DI C | `E0 | DI C | Eo. |
|-----|----------------------------|-------------|----------|--------------|------|------|-----|------|------|----------|------|-----|------|----|-----|----|------|-----|-------|-----|------|-----|
| 17 | 0.9D + 1.6 (330-Wind) | Yes Y | . З Ы | | | 1.6 | | | | га | BLC | ,га | BLC | га | DLC | га | BLC | га | . BLC | га | DLC | га |
| | 1.2D + 1.6 (0-Wind) | Yes Y | | | | | | 1.6 | | | | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | | | | | | | | | | |
| 19 | 1.2D + 1.6 (30-Wind) | | | | | 1.6 | | | | | | | | | | | | | | | | |
| 20 | 1.2D + 1.6 (45-Wind) | | | | | 1.6 | | 1.6 | | | | | | | | | | | | | | |
| 21 | 1.2D + 1.6 (60-Wind) | | | | | 1.6 | | 1.6 | | | | | | | | | | | | | | |
| 22 | 1.2D + 1.6 (90-Wind) | Yes Y | | | | 1.6 | | 1.6 | | | | | | | | | | | | | | |
| 23 | 1.2D + 1.6 (120-Wind) | Yes Y | | 1.2 | | | | 1.6 | | | | | | | | | | | | | | |
| 24 | 1.2D + 1.6 (135-Wind) | Yes Y | | | | 1.6 | | | | | | | | | | | | | | | | |
| 25 | 1.2D + 1.6 (150-Wind) | Yes Y | <u> </u> | | | 1.6 | | 1.6 | | | | | | | | | | | | | | |
| 26 | 1.2D + 1.6 (180-Wind) | Yes Y | · · | | | 1.6 | | | | | | | | | | | | | | | | |
| 27 | 1.2D + 1.6 (210-Wind) | Yes Y | <u> </u> | | | 1.6 | | | | | | | | | | | | | | | | |
| 28 | 1.2D + 1.6 (225-Wind) | Yes Y | | | | 1.6 | | | | | | | | | | | | | | | | |
| 29 | 1.2D + 1.6 (240-Wind) | Yes Y | <u> </u> | | | 1.6 | | | | | | | | | | | | | | | | |
| 30 | 1.2D + 1.6 (270-Wind) | Yes Y | | | | 1.6 | | | | | | | | | | | | | | | | |
| 31 | 1.2D + 1.6 (300-Wind) | Yes Y | <u> </u> | | | 1.6 | | | | | | | | | | | | | | | | |
| 32 | 1.2D + 1.6 (315-Wind) | Yes Y | | | | 1.6 | | | | | | | | | | | | | | | | |
| 33 | 1.2D + 1.6 (330-Wind) | Yes Y | <u> </u> | | | 1.6 | | | | | | | | | | | | | | | | |
| 34 | 1.2D + 1.0Di + 1.0 (0-Wi | | | | 18 | | 51 | | 19 | 1 | 52 | 1 | | | | | | | | | | |
| 35 | 1.2D + 1.0Di + 1.0 (30-W. | | <u> </u> | | | 1 | 51 | 1 | 20 | _1_ | 53 | | | | | | | | | | | |
| 36 | 1.2D + 1.0Di + 1.0 (45-W. | | | | 18 | | 51 | | 21 | 1 | 54 | 1 | | | | | | | | | | |
| 37 | 1.2D + 1.0Di + 1.0 (60-W. | | <u> </u> | | | | 51 | 1 | 22 | 1_ | 55 | 1 | | | | | | | | | | |
| 38 | 1.2D + 1.0Di + 1.0 (90-W. | | | | 18 | | 51 | 1 | 23 | 1 | 56 | 1 | | | | | | | | | | |
| 39 | 1.2D + 1.0Di + 1.0 (120 | | · | 1.2 | 18 | | 51 | 1 | 24 | _1_ | 57 | 1 | | | | | | | | | | |
| 40 | 1.2D + 1.0Di + 1.0 (135 | | | _ | | | 51 | 1 | 25 | 1 | 58 | 1 | | | | | | | | | | |
| 41 | 1.2D + 1.0Di + 1.0 (150 | | | | | | 51 | | 26 | _1_ | 59 | 1 | | | | | | | | | | |
| 42 | 1.2D + 1.0Di + 1.0 (180 | | | | | | 51 | 1 | 27 | 1 | 60 | 1 | | | | | | | | | | |
| 43 | 1.2D + 1.0Di + 1.0 (210 | | <u> </u> | <u> 1.2</u> | | | 51 | 1 | 28 | _1_ | 61 | 1 | | | | | | | | | | |
| 44 | 1.2D + 1.0Di + 1.0 (225 | | | | 18 | | 51 | 1 | 29 | 1 | 62 | 1 | | | | | | | | | | |
| 45 | 1.2D + 1.0Di + 1.0 (240 | | ' | | | | 51 | 1 | 30 | _1_ | 63 | 1 | | | | | | | | | | |
| | 1.2D + 1.0Di + 1.0 (270 | | | | 18 | | 51 | 1 | 31 | 1_ | 64 | 1 | | | | | | | | | | |
| 47 | 1.2D + 1.0Di + 1.0 (300 | | <u> </u> | | | | 51 | 1 | 32 | _1_ | 65 | 1 | | | | | | | | | | |
| 48 | 1.2D + 1.0Di + 1.0 (315 | | | 1 1.2 | | | 51 | | 33 | 1 | 66 | 1 | | | | | | | | | | |
| 49 | 1.2D + 1.0Di + 1.0 (330 | | <u> </u> | | | | 51 | _1_ | 34 | <u>1</u> | 67 | 1 | | | | | | | | | | |
| 50 | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | 1.5 | | | | | | | | | | | | | | |
| 51 | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| 52 | 1.0D + 1.5LL + 1.5 Railin. | | | 1 1 | | 1.5 | | 1.5 | | | | | | | | | | | | | | |
| 53 | 1.0D + 1.5LL + 1.5 Railin. | | <u> </u> | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| 54 | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| 55 | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | 1.5 | | | | | | | | | | | | | | |
| 56 | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | 1.5 | | | | | | | | | | | | | | |
| _57 | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| | 1.0D + 1.5LL + 1.5 Railin. | | | 1 | | 1.5 | | | | | | | | | | | | | | | | |
| | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| | | | | | | 1.5 | | | | | | | | | | | | | | | | |
| 63 | 1.0D + 1.5LL + 1.5 Railin. | | <u> </u> | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| 64 | 1.0D + 1.5LL + 1.5 Railin. | | | <u> 1</u> | | 1.5 | | | | | | | | | | | | | | | | |
| 65 | 1.0D + 1.5LL + 1.5 Railin. | | | 1 1 | | 1.5 | | | | | | | | | | | | | | | | |
| 66 | Serviceability (0-Wind) | Yes Y | | 1 1 | 2 | | | | | | | | | | | | | | | | | |
| 67 | Serviceability (30-Wind) | | <u> </u> | | 3 | | | | | | | | | | | | | | | | | |
| 68 | Serviceability (45-Wind) | | | 1 1 | 4 | | | .344 | | | | | | | | | | | | | | |
| 69 | Serviceability (60-Wind) | | | 1 1 | 5 | | | .344 | | | | | | | | | | | | | | |
| 70 | Serviceability (90-Wind) | | _ | 1 1 | _ | .344 | | | | | | | | | | | | | | | | |
| 71 | Serviceability (120-Wind) | | | 1 1 | 7 | _ | | | | | | | | | | | | | | | | |
| 72 | Serviceability (135-Wind) | | | 1 1 | | .344 | | | | | | | | | | | | | | | | |
| 73 | Serviceability (150-Wind) | res Y | | <u> 1</u> | ⊥ 9 | .344 | 42 | .344 | | | | | | | | | | | | | | |



Oct 18, 2017 3:07 PM Checked By:_

Load Combinations (Continued)

| | Description | So | P | S I | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa | BLC | Fa |
|----|---------------------------|-----|---|-----|-----|----|-----|------|-----|------|-----|----|-----|----|-----|----|-----|----|-----|----|-----|----|-----|----|
| 74 | Serviceability (180-Wind) | Yes | Υ | | 1 | 1 | 10 | .344 | 43 | .344 | | | | | | | | | | | | | | |
| 75 | Serviceability (210-Wind) | Yes | Υ | | 1 | 1 | 11 | .344 | 44 | .344 | | | | | | | | | | | | | | |
| 76 | Serviceability (225-Wind) | | | | 1 | 1 | 12 | .344 | 45 | .344 | | | | | | | | | | | | | | |
| 77 | Serviceability (240-Wind) | Yes | Υ | | 1 | 1 | 13 | .344 | 46 | .344 | | | | | | | | | | | | | | |
| 78 | Serviceability (270-Wind) | Yes | Υ | | 1 | 1 | 14 | .344 | 47 | .344 | | | | | | | | | | | | | | |
| 79 | Serviceability (300-Wind) | Yes | Υ | | 1 | 1 | 15 | .344 | 48 | .344 | | | | | | | | | | | | | | |
| 80 | Serviceability (315-Wind) | Yes | Υ | | 1 | 1 | 16 | .344 | 49 | .344 | | | | | | | | | | | | | | |
| 81 | Serviceability (330-Wind) | Yes | Υ | | 1 | 1 | 17 | .344 | 50 | .344 | | | | | | | | | | | | | | |

Envelope Joint Reactions

| | Joint | | X [lb] | LC | Y [lb] | LC | Z [lb] | LC | MX [lb-ft] | LC | MY [lb-ft] | LC | MZ [lb-ft] | LC |
|---|---------|-----|-----------|----|----------|----|-----------|----|------------|----|------------|----|------------|----|
| 1 | N94 | max | 2299.449 | 31 | 3529.095 | 39 | 1338.431 | 32 | 988.587 | 58 | 2252.798 | 27 | 7301.078 | 39 |
| 2 | | min | -2233.62 | 7 | 20.478 | 59 | -1299.445 | 8 | -3945.666 | 40 | -2227.09 | 19 | -1365.162 | 59 |
| 3 | N90 | max | 1506.328 | 14 | 3817.109 | 34 | 2599.499 | 2 | 9149.631 | 34 | 2594.802 | 6 | 557.699 | 6 |
| 4 | | min | -1456.581 | 6 | 189.326 | 10 | -2691.257 | 26 | -764.671 | 10 | -2698.48 | 14 | -633.802 | 59 |
| 5 | N91 | max | 2198.015 | 13 | 3663.131 | 45 | 1633.311 | 18 | 880.589 | 58 | 2242.184 | 17 | 610.779 | 5 |
| 6 | | min | -2272.83 | 21 | 172.896 | 5 | -1633.209 | 10 | -4383.789 | 44 | -2278.539 | 9 | -7612.621 | 45 |
| 7 | Totals: | max | 5684.079 | 30 | 10678.86 | 35 | 5537.715 | 2 | | | | | | |
| 8 | | min | -5645.972 | 6 | 2304.399 | 11 | -5575.281 | 26 | | | | | | |

Envelope AISC 13th(360-05): LRFD Steel Code Checks

| | Member | Shape | Code Check | Loc[ft] LC | Shear | . Loc[ft] | Dir | LC phi*Pnc [phi | i*Pnt [lb] | phi*Mn y | phi*Mn zCb Ed | gn |
|----|--------|----------|------------|------------|-------|-----------|-----|-----------------------|------------|----------|----------------|-----|
| 1 | H3 | PIPE 3.0 | .310 | 4.036 29 | .321 | 4.297 | | 30 28250.554 6 | 55205 | 5748.75 | 5748.75 2 H3 | 3-6 |
| 2 | H1 | PIPE 3.0 | .179 | 8.073 38 | .189 | 8.203 | | 36 28250.554 6 | 55205 | 5748.75 | 5748.75 1 H1- | -1b |
| 3 | PL2 | 1/2 x 6 | .248 | .644 22 | .250 | 0 | У | 58 53371.658 9 | 7200 | 12150 | 1012.5 1 H1- | -1b |
| 4 | H2 | PIPE 3.0 | .226 | 3.906 59 | .225 | 8.203 | | 25 28250.554 6 | 55205 | 5748.75 | 5748.75 2 H1- | -1b |
| 5 | PL3 | 1/2 x 6 | .256 | .644 19 | .260 | .819 | У | 24 53371.658 9 | 7200 | 12150 | 1012.5 1 H1- | -1b |
| 6 | PL1 | 1/2 x 6 | .255 | .644 25 | .351 | .967 | У | 30 53371.658 9 | 7200 | 12150 | 1012.5 1 H1- | -1b |
| 7 | SA1 | HSS4x4x4 | .729 | 0 47 | .140 | 0 | У | 47 95077.277 10 | 09188 | 12663 | 12663 3 H1- | -1b |
| 8 | SA3 | HSS4x4x4 | .702 | 6.5 42 | .129 | 6.5 | У | 47 95077.277 10 | 09188 | 12663 | 12663 3 H1- | -1b |
| 9 | SA2 | HSS4x4x4 | .664 | 6.5 37 | .144 | 6.5 | У | 37 95077.277 10 | 09188 | 12663 | 12663 3 H1- | -1b |
| 10 | A1 | HSS4x4x4 | .350 | 2.713 41 | .175 | 0 | Z | 54 106586.9 10 | 09188 | 12663 | 12663 1 H1- | -1b |
| 11 | A2 | HSS4x4x4 | .338 | 0 38 | .211 | 2.261 | Z | 29 106586.9 10 | 09188 | 12663 | 12663 1 H1- | -1b |
| 12 | C1 | HSS4x4x4 | .385 | 0 36 | .245 | 2.261 | Z | 29 106586.9 10 | 09188 | 12663 | 12663 1 H1- | -1b |
| 13 | B2 | HSS4x4x4 | .373 | 0 47 | .198 | 2.261 | Z | 23 106586.9 10 | 09188 | 12663 | 12663 1 H1- | -1b |
| 14 | B1 | HSS4x4x4 | .340 | 2.713 43 | .172 | 0 | Z | 54 106586.9 10 | 09188 | 12663 | 12663 1 H1- | -1b |
| 15 | C2 | HSS4x4x4 | .362 | 2.713 48 | .209 | .452 | Z | 23 106586.9 10 | 09188 | 12663 | 12663 1 H1- | -1b |
| 16 | L5 | L2x2x3 | .339 | 4.138 29 | .021 | 4.138 | У | 45 9921.867 23 | 3392.8 | 557.717 | 1239.29 2 H2 | 2-1 |
| 17 | L4 | L2x2x3 | .356 | 4.138 16 | .018 | 4.138 | Z | 39 9921.867 23 | 3392.8 | 557.717 | 1239.29 2 H2 | 2-1 |
| 18 | L2 | L2x2x3 | .339 | 4.138 11 | .021 | 4.138 | Z | 50 9921.867 23 | 3392.8 | 557.717 | 1229.662 2 H2 | 2-1 |
| 19 | L3 | L2x2x3 | .300 | 4.138 30 | .020 | 0 | Z | 39 9921.867 23 | 3392.8 | 557.717 | 1235.207 2 H2 | 2-1 |
| 20 | MP5 | PIPE 2.0 | .370 | 3.063 49 | .113 | 5.979 | | 30 17855.085 3 | 32130 | 1871.625 | 1871.625 2 H1- | -1b |
| 21 | MP7 | PIPE 3.0 | .293 | 3.063 42 | .092 | 3.063 | | 26 50160.801 6 | 55205 | 5748.75 | 5748.75 1 H1- | -1b |
| 22 | L6 | L2x2x3 | .355 | 4.138 6 | .018 | 4.138 | Z | 51 9921.867 23 | 3392.8 | 557.717 | 1239.29 2 H2 | 2-1 |
| 23 | L1 | L2x2x3 | .293 | 0 50 | .020 | 0 | Z | 35 9921.867 23 | 3392.8 | 557.717 | 1239.29 2 H2 | 2-1 |
| 24 | MP8 | PIPE 2.0 | .401 | 3.063 30 | .125 | 3.063 | | 19 17855.085 3 | 32130 | 1871.625 | 1871.625 1 H1- | -1b |
| 25 | MP6 | PIPE 3.0 | .304 | 3.021 38 | .068 | 5.938 | | 43 38176.7 6 | 55205 | 5748.75 | 5748.75 3 H1- | -1b |
| 26 | MP1 | PIPE 2.0 | .370 | 3.938 43 | .117 | 1.021 | | 22 17855.085 3 | 32130 | 1871.625 | 1871.625 1 H1- | -1b |
| 27 | MP2 | PIPE 3.0 | .277 | 3.063 47 | .070 | 3.063 | | 30 50160.801 6 | 55205 | 5748.75 | 5748.75 2 H1- | -1b |
| 28 | MP4 | PIPE_2.0 | .364 | 3.063 25 | .121 | 3.063 | | 31 17855.085 3 | 32130 | 1871.625 | 1871.625 1 H1- | -1b |
| 29 | MP3 | PIPE 3.0 | .294 | 3.021 36 | .067 | 5.938 | | 46 38176.7 6 | 55205 | | 5748.75 3 H1- | |
| 30 | MP9 | PIPE 2.0 | .349 | 3.063 38 | .130 | 5.979 | | 19 17855.085 3 | 32130 | 1871.625 | 1871.625 2 H1- | -1b |
| 31 | MP11 | PIPE 3.0 | .286 | 3.063 47 | .096 | 3.063 | | | 55205 | 5748.75 | 5748.75 2 H1- | -1b |
| 32 | MP12 | PIPE_2.0 | .348 | 3.063 34 | .101 | 5.979 | | 38 17855.085 3 | 32130 | 1871.625 | 1871.625 1 H1- | -1b |



Oct 18, 2017 3:07 PM Checked By:_

Envelope AISC 13th(360-05): LRFD Steel Code Checks (Continued)

| | Member | Shape | Code Check | Loc[ft] LC | Shear | Loc[ft] | Dir | LC J | ohi*Pnc [| phi*Pnt [lb |]phi*Mn y | phi*Mn zCb | Eqn |
|----|--------|------------|------------|------------|-------|---------|-----|------|-----------|-------------|-----------|------------|-------|
| 33 | MP10 | PIPE 3.0 | .325 | 3.021 29 | .065 | 5.938 | | 48 | 38176.7 | 65205 | 5748.75 | 5748.75 1 | H1-1b |
| 34 | TH3 | PIPE 2.0 | .352 | 8.594 34 | .144 | .521 | | 19 | 6295.422 | 32130 | 1871.625 | 1871.625 2 | H1-1b |
| 35 | TH1 | PIPE 2.0 | .357 | 8.594 44 | .101 | 8.594 | | 38 | 6295.422 | 32130 | 1871.625 | 1871.625 2 | H1-1b |
| 36 | TH2 | PIPE 2.0 | .371 | 3.906 45 | .122 | 11.979 | | 30 | 6295.422 | 32130 | 1871.625 | 1871.625 2 | H1-1b |
| 37 | AN1 | L2.5x2.5x4 | .118 | 0 22 | .351 | 0 | У | 14 | 36522.304 | 38556 | 1113.554 | 2537.388 2 | H2-1 |
| 38 | AN2 | L2.5x2.5x4 | .098 | 1.289 28 | .284 | 0 | У | 58 | 36522.304 | 38556 | 1113.554 | 2537.388 2 | H2-1 |
| 39 | AN3 | L2.5x2.5x4 | .103 | 1.289 58 | .312 | 1.289 | У | 58 | 36522.304 | 38556 | 1113.554 | 2537.388 2 | H2-1 |



DO MACRO UPGRADE PROJECT:

SITE NAME: UNIONVILLE/POLICE DEPT.

SITE CASCADE: CT33XC534-B

SITE ADDRESS: 319-321 NEW BRITAIN AVENUE

FARMINGTON, CT 06032

SITE TYPE: 190'-0" MONOPOLE

SITE INFORMATION

PROPERTY OWNER:

TOWN OF FARMINGTON I MONTEITH DRIVE FARMINGTON, CT 06032 PH.:860-675-2325

SITE ADDRESS:

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

GEOGRAPHIC COORDINATES:

LATITUDE: 41° 44′ 58.9986" N (41.749722) LONGITUDE: 72° 52′ 21″ W (-72.8725)

ZONING JURISDICTION:

TOWN OF FARMINGTON

ZONING DISTRICT:

COMMERCIAL/RESIDENTIAL

POWER COMPANY:

CONN. LIGHT \$ POWER PH.: (800) 286-2000

AAV PROVIDER:

PH.: (210) 821-4105

SPRINT CONSTRUCTION MANAGER:

NAME: MIKE DELIA PHONE: (781) 316-6348 E-MAIL: michael.delia@sprint.com

EQUIPMENT SUPPLIER:

ALCATEL-LUCENT 600-700 MOUNTAIN AVENUE MURRAY HILL, NJ 07974 PH.: (908) 508-8080


SITE ACQUISITION:

CHARLES CHERUNDOLO CONSULTING, INC. PARSIPPANY, NJ 07054 CONTACT: TOM JUPIN, PMP, PROJECT MANAGER CELL: (973) 819-9033 EMAIL: tom.jupin@cherundoloconsulting.com

PLANS PREPARED BY:

RAMAKER & ASSOCIATES, INC. CONTACT: KEITH BOHNSACK, PROJECT MANAGER PH : (608) 643-4100 EMAIL: kbohnsack@ramaker.com






LOCATION MAP

PROJECT DESCRIPTION

- INSTALL NEW EQUIPMENT IN EXISTING BTS CABINET *(1) RECTIFIER SHELF AND (3) RECTIFIERS
 *(1) BASE BAND UNIT
- INSTALL NEW BATTERY STRING IN EXISTING BATTERY CABINET
- INSTALL (3) PANEL ANTENNAS
- INSTALL (6) RRH'S ON TOWER
- INSTALL (1) HYBRIFLEX CABLE

APPLICABLE CODES



- I. INTERNATIONAL BUILDING CODE
- 2. ANSI/TIA-222 STRUCTURAL STANDARD FOR ANTENNA STRUCTURES
- 3. NEPA 780 LIGHTNING PROTECTION CODE
- 4. NATIONAL ELECTRIC CODE



| SHT NO: | SHEET TITLE: | REV: | ENGINEER: | |
|---------|---------------------------------------|------|-----------|-----------------|
| T-I | TITLE SHEET | - | JRS | |
| SP-I | SPRINT SPECIFICATIONS | - | JRS | |
| SP-2 | SPRINT SPECIFICATIONS | - | JRS | |
| SP-3 | SPRINT SPECIFICATIONS | - | JRS | |
| A- I | SITE PLAN | - | JRS | |
| A-2 | EQUIPMENT PLAN | - | JRS | |
| A-3 | BUILDING ELEVATION \$ ANTENNA DETAILS | - | JRS | |
| A-4 | RF DATA SHEET | - | JRS | |
| A-5 | FIBER PLUMBING DIAGRAM | - | JRS | Ja |
| A-6 | CABLE COLOR CODING | - | JRS | |
| A-7 | ANTENNA \$ RRH DETAILS | - | JRS | \cup |
| A-8 | EQUIPMENT DETAILS | - | JRS | |
| S-1 | STRUCTURAL NOTES | - | JRS | |
| 5-2 | STRUCTURAL DETAILS | - | JRS | |
| 5-3 | STRUCTURAL DETAILS | - | JRS | |
| 5-4 | STRUCTURAL DETAILS | - | JRS | I I |
| S-5 | STRUCTURAL DETAILS | - | JRS | ISSUE |
| 5-6 | STRUCTURAL DETAILS | - | JRS | PHASE PROJEC |
| E-I | EQUIPMENT UTILITY \$ GROUNDING PLAN | - | JRS | |
| E-2 | GROUNDING DETAILS | - | JRS | |
| E-3 | DC POWER DETAILS & PANEL SCHEDULES | - | JRS | |
| | | | | PROJEC |
| | | | | 319 |
| | | | | FARM |
| | | | | HAR |
| | | | | SHEET |
| | | | | |
| | | | | |
| | | | | |
| | | | | SC |
| | | | | |
| | | | | L |
| | | | | PROJ NUME |

SHEET INDEX

Sprint[®]

6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

hereby certify that this plan, specification, or report was by me or under my direct supervision and that I am a duly Professional Engineer under the laws of the State of <u>Con</u>





DATE 08/10/2017 UNIONVILLE / POLICE DEPARTMENT

CT33XC534-B

JECT INFORMATION: 9-32 | NEW BRITAIN AVENUE RMINGTON, CT 06032 RTFORD COUNTY

TITLE SHEET

CALE: NONE

23009

SHEET

SECTION OI 100 - SCOPE OF WORK

THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE CONSTRUCTION DRAWINGS AND ASSOCIATED OUTLINE SPECIFICATIONS AND THE SITE SPECIFIC WORK ORDER, DESCRIBE THE WORK TO BE PERFORMED BY THIS CONSTRUCTION CONTRACTOR (SUPPLIER).

- RELATED DOCUMENTS: A. THE REQUIREMENTS OF EACH SECTION OF THIS SPECIFICATION APPLY TO ALL SECTIONS, INDIVIDUALLY
- B. RELATED DOCUMENTS: THE CONTRACTOR SHALL COMPLY WITH THE MOST CURRENT VERSION OF THE
- FOLLOWING SUPPLEMENTAL REQUIREMENTS FOR INSTALLATION AND TESTING.

 1. EN-2012-001: (FIBER OPTIC, DC CABLE, AND DC CIRCUIT BREAKER TAGGING STANDARDS)
- TS-0200 (TRANSMISSION ANTENNA LINE ACCEPTANCE STANDARDS)
- 3.EL-0568: (FIBER TESTING POLICY)
- 4.NP-3 | 2-20 | : (EXTERIOR GROUNDING SYSTEM TESTING)
- 5.NP-760-500: ETHERNET, MICROWAVE, TESTING AND ACCEPTANCE

SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

NATIONALLY RECOGNIZED CODES AND STANDARDS:
THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:

- A. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 B. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF
- TELECOMMUNICATIONS EQUIPMENT.
 C. GR-I 089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR
- NETWORK TELECOMMUNICATIONS EQUIPMENT.

 D. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING
- NFPA 70 (NATIONAL ELECTRICAL CODE "NEC") AND NFPA 101 (LIFE SAFETY CODE). E. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
- F. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 G. AMERICAN CONCRETE INSTITUTE (ACI)

- . AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA) CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
- AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
- K. PORTLAND CEMENT ASSOCIATION (PCA)
- NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
- M. BRICK INDUSTRY ASSOCIATION (BIA)
- N. AMERICAN WELDING SOCIETY (AWS)
 O. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
- SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
- Q DOOR AND HARDWARE INSTITUTE (DHI)
- . OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
- S. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

- DEFINITIONS: A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: "SPRINT"; SPRINT NEXTEL CORPORATION AND IT'S OPERATING ENTITIES.
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR, SUPPLIER, CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK
- . CONSTRUCTION MANAGER ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT.

CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

ON-SITE SUPERVISION:
THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK

DRAWINGS REQUIRED AT JOBSITE:
THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

- THE JOBSITE DRAWINGS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED. REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S ARE VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS
- B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY

WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

 $\begin{array}{l} \underline{\text{CONTRACTOR:}} \\ \underline{\text{CONTRACTOR}} \text{ SHALL TAKE ALL } \underline{\text{MEASURES}} \text{ AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING} \\ \end{array}$ EXISTING EQUIPMENT AND PROPERTY.

USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:
CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT
SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT
TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTORS STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT

TEMPORARY UTILITIES AND FACILITIES:
THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS, TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY LITHUZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSOR'S OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

ACCESS TO WORK:
THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS

EXISTING CONDITIONS:
NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED

TO SELECT THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED

TO SELECT THE SPRINT CONTROL PRINT WRITTEN ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION O I 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

FURNISHED MATERIALS: COMPANY FURNISHED MATERIALS AND EQUIPMENT TO BE INSTALLED BY THE CONTRACTOR (OFIC) IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.

A.THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT

- I. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT
- 2.VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 3.TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN
- B.RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO
- SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 C.PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING
- D.COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
B.IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY

SECTION 01 300 - CELL SITE CONSTRUCTION

A.NO WORK SHALL COMMENCE PRIOR TO COMPANY'S ISSUANCE OF THE WORK ORDER. B.UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

- GENERAL REQUIREMENTS FOR CONSTRUCTION:

 A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH.

 AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING
- RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.

 B.EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS. C.CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS
 - JOHNTON.

 I. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
- 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.

 D.CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS, SHOULD AREAS OUTSIDE THE
- PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION

FUNCTIONAL REQUIREMENTS

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK, CONTRACTOR SHALL TAKE ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B.SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED C.MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D.PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
- PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
 PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS
- 3.MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND
- BACKHAUL (FIBER, COPPER, OR MICROWAVE).

 4.INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
 5.INSTALL ABOVE GROUND GROUNDING SYSTEMS, CONDUIT AND BOXES.
- G.PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
 7.INSTALL "H-FRAMES", CABINETS AND PADS AND PLATFORMS AS INDICATED.
- 8.INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED
- 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.

- LO. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS
- PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.

COMMISSIONING AND INTEGRATION ACTIVITIES PER APPLICABLE MOPS

- CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
- CONDUCT ALL REQUIRED TESTS AND INSPECTIONS
 PERFORM, DOCUMENT, AND CLOSE OUT ALL JURISDICTIONAL PERMITTING REQUIREMENTS AND ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES
- AND LANDLORDS. PERFORM ALL ADDITIONAL WORK AS IDENTIFIED IN SCOPE OF SERVICES ATTACHED TO THE SUPPLIER AGREEMENT FOR THIS PROJECT. THIS WORK MAY INCLUDE COMMISSIONING, INTEGRATION, SPECIAL WAREHOUSING, REVERSE LOGISTICS ACTIVITIES, ETC. PERFORM

DELIVERABLES:

A. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED TEST REPORTS AND DOCUMENTATION INCLUDED BUT

- PRODUCT SPECIFICATIONS FOR MATERIALS OR SPECIAL CONSTRUCTION IF REQUIESTED BY SPRINT
- 2. ACTUALIZE ALL CONSTRUCTION RELATED MILESTONES IN SITERRA AND COMPLETE ALL ON-LINE FORMS AND COMPLETE DOCUMENT UP-LOADS. UPLOAD ALL REQUIRED CLOSEOUT DOCUMENTS AND FINAL
- 3. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT LEFT ON SITE INSIDE BASE OF MAIN RF CABINET IN A PROTECTIVE POUCH.
- 4 ALL REQUIRED TEST REPORTS
- 5. REQUIRED CLOSEOUT DOCUMENTATION INCLUDING BUT NOT LIMITED TO:
- a. ALL JURISDICTIONAL PERMITTING AND OCCUPANCY INFORMATION b. PDF SCAN OF REDLINES PRODUCED IN THE FIELD
- c.ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS
- d.LIEN WAIVERS
- e.FINAL PAYMENT APPLICATION

 f. REQUIRED FINAL CONSTRUCTION PHOTOS
- g.CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS h. LISTS OF SUBCONTRACTORS
- B.PROVIDE ADDITIONAL DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 - I. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS. 2. PROJECT PROGRESS REPORTS.
 - 3. PRE-CONSTRUCTION MEETING NOTES
- SECTION O I 400 TESTS, INSPECTIONS, SUBMITTALS, AND PROJECT

A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT

- B.CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
- I. COAX SWEEPS AND FIBER TESTS PER TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE 2. POST CONSTRUCTION HEIGHT VERIFICATION, AZIMUTH AND DOWNTILT USING ELECTRONIC
- COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL. 3. CONCRETE BREAK TESTS
- 4. SITE RESISTANCE TO EARTH TEST
 5. STRUCTURAL BACKFILL COMPACTION TESTS
- 6. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- 7. ADDITIONAL TESTING AS REQUIRED ELSEWHERE IN THIS SPECIFICATION

- SUBMITTALS:

 A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE
- B.UPLOAD THE FOLLOWING TO SITERRA AS APPLICABLE INCLUDING BUT NOT LIMITED TO THE FOLLOWING: CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
- CHEMICAL GROUNDING SYSTEM
- 4 REINFORCEMENT CERTIFICATIONS
- STRUCTURAL BACKFILL TEST RESULTS
- SWEEP AND FIBER TESTS ANTENNA AZIMUTH AND DOWN-TILT VERIFICATION

COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT

8 POST CONSTRUCTION HEIGHT VERIFICATION ADDITIONAL SUBMITTALS MAY BE REQUIRED FOR SPECIAL CONSTRUCTION OR MINOR MATERIALS C.ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF

- A.EMPLOY AN AGENCY OF ENGINEERS AND SCIENTISTS WHO IS REGULARLY ENGAGED IN FIELD AND LABORATORY TESTING AND ANALYSIS. AGENCY SHALL HAVE BEEN IN BUSINESS A MINIMUM OF FIVE YEARS, AND BE LICENSED AS PROFESSIONAL ENGINEERS IN THE STATE WHERE THE PROJECT IS LOCATED.
- AGENCY IS SUBJECT TO APPROVAL BY COMPANY.

 I. AGENCY MUST HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.

 2. AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE,
- EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.

 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM,
- AASJTO, AND OTHER METHODS IS NEEDED. B.REQUIRED THIRD PARTY TESTS:
- SITE RESISTANCE TO EARTH TEST PER NP-3 | 2-20 |
 CONCRETE CYLINDER BREAK TESTS FOR TOWER PIER AND ANCHORS PER NATIONALLY RECOGNIZED
- 3. STRUCTURAL SOILS COMPACTION TESTS PER NATIONALLY RECOGNIZED STANDARDS REBAR PLACEMENT VERIFICATION WITH REPORT TESTING TENSION STUDY FOR ROCK ANCHORS
- 6. ALL THIRD PARTY TESTS AS REQUIRED BY LOCAL JURISDICTION C.REQUIRED TESTS BY CONTRACTOR
- I. COAX SWEEP TESTS PER SPRINT STANDARD TS-0200
 2. FIBER TESTS PER SPRINT STANDARD EL-0568
- . MICROWAVE LINK TESTS PER NP-760-500
- 4. ANTENNA AZIMUTHS AND DOWN TILT USING ELECTRONIC ALIGNMENT TOOL PER ANTENNA INSTALLATION SPECIFICATION HEREIN.



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.



10/26/201

0/26/17 REVISED RF AND STRUCTURAL DETAILS

DATE 08/10/2017

FINAL

UNIONVILLE / POLICE DEPARTMENT CT33XC534-B

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

SPRINT SPECIFICATIONS

SCALE: NONE

23009 SHEET

- POST CONSTRUCTION HEIGHT VERIFICATION AS REQUIRED HEREWITH IN THE TOWER INSTALLATION SPECIFICATIONS
- ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED HEREWITH IN THE ASPHALT PAVING SPECIFICATIONS
- FIELD QUALITY CONTROL TESTING AS SPECIFIED HEREWITH IN THE CONCRETE PAVING SPECIFICATIONS
- TESTING REQUIRED HEREWITH UNDER SPECIFICATIONS FOR AGGREGATE BASE FOR ROADWAYS
- 9. ALL OTHER TESTS REQUIRED BY LOCAL JURISDICTION
 D.INSPECTIONS BY COMPANY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN INSPECTION ACTIVITIES, FINAL ACCEPTANCE / PUNCH WALK REVIEW, AND/OR AS A RESULT OF TESTING
- E. SPRINT RESERVES THE RIGHT TO INSPECT THE CONSTRUCTION SITE AT ANY TIME VIA SITE WALKS AND/OR PHOTO REVIEWS. CONTRACTOR SHALL GIVE SPRINT 24 HOURS NOTICE PRIOR TO THE COMMENCEMENT
- OF THE FOLLOWING CONSTRUCTION ACTIVITIES AND PHOTOGRAPHS OF THE IN-PROGRESS WORK, I. GROUNDING SYSTEM AND BURIED UTILITIES INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A¢E OR SPRINT REPRESENTATIVE
- FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A FOR SPRINT REPRESENTATIVE.
- COMPACTION OF BACKFILL MATERIALS, AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS ASPHALT PAVING, AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD
- PRE AND POST CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES PRIOR TO CONSTRUCTION ACTIVITIES AND AFTER CONSTRUCTION IS COMPLETE, PROVIDE PHOTOGRAPHIC DOCUMENTATION OF ROOF, FLASHINGS, AND PARAPETS, BOTH BEFORE AND AFTER CONSTRUCTION IS COMPLETE
- TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 TOWER TOP AND INACCESSIBLE EQUIPMENT (RRUS, ANTENNAS, AND CABLING): PROVIDE PHOTOS
- OF THE BACKS OF ALL ANTENNAS, RRUS, COMBINERS, FILTERS, FIBER AND DC CABLING, CABLE COLOR CODING, EQUIPMENT GROUNDING AND CONNECTOR WATER PROOFING INCLUDING NAME PLATE AND SERIAL NUMBER FOR ALL SERIALIZED EQUIPMENT

- A FINAL ACCEPTANCE PLINCH WALK AND INSPECTION: AS IDENTIFIED IN THE SCOPE OF SERVICES, SPRINT WILL CONDUCT A FINAL PUNCH WALK OR FINAL DESK TOP PHOTO REVIEW (SITE MODIFICATIONS). PUNCH WALKS MUST BE SCHEDULED IN ADVANCE AS REQUIRED. AT THE PUNCH WALK / REVIEW. SPRINT MAY IDENTIFY CRITICAL DEFICIENCIES WHICH MUST BE CORRECTED PRIOR TO PUTTING SITE ON AIR. MINOR DEFICIENCIES MUST BE CORRECTED WITHIN 30 DAYS EXCEPT AS OTHERWISE REQUIRED. VERIFICATIONS OF CORRECTIONS MAY BE MADE BY COMPANY DURING A REPEAT SITE WALK OR DESK TOP PHOTO REVIEW AT COMPANYS SOLE DISCRETION
- B.CLOSEOUT DOCUMENTATION: ALL CLOSEOUT DOCUMENTATION AND PHOTOGRAPHS SHALL BE UPLOADED PRIOR TO FINAL ACCEPTANCE. SPRINT WILL REVIEW CLOSEOUT DOCUMENTATION FOR PRESENCE AND CONTENT. CLOSEOUT DOCUMENTATION SHALL INCLUDE BUT IS NOT LIMITED TO THE FOLLOWING AS APPLICABLE:
- COAX SWEEP TESTS:
- FIBER TESTS:
 JURISDICTION FINAL INSPECTION DOCUMENTATION
- REINFORCEMENT CERTIFICATION (MILL CERTIFICATION)
 CONCRETE MIX DESIGN AND PRODUCT DATA (TOWER FOUNDATION)

- LIEN WAIVERS AND RELEASES.
 POST -CONSTRUCTION HEIGHT VERIFICATION
- JURISDICTION CERTIFICATE OF OCCUPANCY ELECTRONIC ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
- STRUCTURAL BACKFILL TEST RESULTS (IF APPLICABLE)
 CELL SITE UTILITY SETUP
- 12. AS-BUILT REDUNE CONSTRUCTION DRAWINGS (PDF SCAN OF FIELD MARKS)
 13. AS-BUILT CONSTRUCTION DRAWINGS IN DWG AND PDF FORMATS
- 14. LIST OF SUB CONTRACTORS APPROVED PERMITTING DOCUMENTS
- FINAL SITE PHOTOS UP-LOADED TO SITERRA. INCLUDE THE FOLLOWING AS APPLICABLE:

 a. TOWER, ANTENNAS, RRUS, AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION
- STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX/CABLE LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN: PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR, PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING.-TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- b.ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
- c. SITE LAYOUT PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
- FROM ALL FOUR CORNERS.

 d. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE: PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.

- A, PROVIDE PROJECT CLOSEOUT GENERAL ARRANGEMENT PHOTOS OF ALL NEW WORK, THE FOLLOWING LIST REPRESENTS MINIMUM REQUIREMENTS AND MINIMUM QUANTITY. ADDITIONAL PHOTOS MAY BE REQUIRED TO ADEQUATELY DOCUMENT THE WORK.
 - ASR AND RE MPE SIGNAGE (IF NOT IN PLACE, SUPPLIER NOTIFIES EMS FIELD REPRESENTATIVE)

 - BACK OF ANTENNAS AND RRUS (I EACH SECTOR)
 BACK OF ANTENNAS AND RRUS (I EACH SECTOR) CLOSE UP SHOWING WEATHERPROOFING AND GROUNDING (AS REQUIRED). CLOSE-UP OF BACK SIDE OF EACH PERMANENT RRU SHOWING SERIAL NUMBER/BAR CODE
 - NUMBERDAR CODE.
 VIEW (I EACH SECTOR) ALONG THE AZIMUTH AND TILT OF THE ANTENNAS
 TOP OF TOWER FROM GROUND, I EACH SECTOR
 MAINLINE HYBRID CABLE ROUTE DOWN TOWER SHOWING FASTENERS AND SUPPORT

 - MAINLINE/HYBRID CABLE ROUTE ALONG ICE BRIDGE OR IN CABLE TRAY SHOWING FASTENERS AND
 - GROUND MOUNTED RRU RACKS (FRONT AND BACK)
 - FRONT, SIDE AND BACK ELEVATIONS OF ALL GROUND CABINETS
- LO. VIEW OF COMPOUND FROM A DISTANCE.
- VIEW OF EACH GROUND CABINET (POWER, RF, FIBER SPOOL, PPC POWER, PPC TELCO WITH DOOR
- 12. BACKHAUL FIBER MEET-ME-POINT AND CONDUIT ROUTE (MICROWAVE INSTALLATION IF NOT FIBER)
- 13. AAV NETWORK INTERFACE DEVICE OR MICROWAVE RADIO INSTALLATION

CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIONS TO DEFICIENCIES IDENTIFIED THROUGH TESTING, REVIEW OF SUBMITTALS, INSPECTIONS AND CLOSEOUT REVIEWS

SECTION O I 500 - PROJECT REPORTING

A CONTRACTOR SHALL REPORT TO SPRINT AT MINIMUM ON A WEEKLY BASIS VIA SITERRA BY LIPDATING ALL APPLICABLE POST END KEEPING MILESTONES WITH ACTUAL AND FORECASTED COMPLETION DATES.

B. ADDITIONAL REQUIREMENTS FOR REPORTING MAY BE IDENTIFIED ELSEWHERE OR REQUIRED BY THE SCOPE OF SERVICES OR SPRINTS LOCAL MARKET CONSTRUCTION MANAGER. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

SPRINT MAY HOLD PERIODIC PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

FINAL PROJECT ACCEPTANCE: PRIOR TO SPRINTS FINAL PROJECT ACCEPTANCE. ALL REQUIRED MILESTONE ACTUALS MUST BE UPDATED IN SITERRA AND ALL REQUIRED REPORTING TASKS MUST BE COMPLETE.

SECTION I I 700 - ANTENNA ASSEMBLY, REMOTE RADIO UNITS AND CABLE INSTALLATION

SUMMARY: THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRUS, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

THE NUMBER AND TYPE OF ANTENNAS AND RRU'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

JUMPERS AND CONNECTORS: FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRU'S AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRU'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE, MIN. LENGTH FOR JUMPER SHALL BE 10"-0".

REMOTE ELECTRICAL TILT (RET) CABLES:

MISCELLANEOUS:
INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS

- A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN I DEGREE.
- B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE

HYBRID CABLE INSTALLATION:

- A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS
- B THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS

C.EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.

- I. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE INSTALLED INSIDE MONOPOLE WITH CABLE SUPPORT GRIPS AS REQUIRED BY THE MANUFACTURER.
- 2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
 - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH AT 18" O.C. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
 - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
- 3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
- 4. CABLE INSTALLATION
 - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION
 - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES VILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS
 - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.
- 5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED
- 7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV I

6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 (CURRENT

WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED

- B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.
- COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR
- 2. SELF-AMALGAMATING TAPE: CLEAN SURFACES, APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE
- 3. 3M SLIM LOCK CLOSURE 7 I 6: SUBSTITUTIONS WILL NOT BE ALLOWED.
- 4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

SECTION 1 1 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBS)

SUMMARY

- A. THIS SECTION SPECIFIES MMBS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI)
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRED BY THE APPLICABLE INSTALLATION MOPS

C.COMPLY WITH MANUFACTURER'S INSTALLATION AND START-UP REQUIREMENTS.

DC CIRCUIT BREAKER LABELING

A.NEW DC CIRCUIT IS REQUIRED IN MMBS CABINET SHALL BE CLEARLY IDENTIFIED AS TO RRU BEING SERVICED.

SECTION 26 100 - BASIC ELECTRICAL REQUIREMENTS

<u>SUMMARY:</u> THIS SECTION SPECIFIES BASIC ELECTRICAL REQUIREMENTS FOR SYSTEMS AND COMPONENTS.

QUALITY ASSURANCE:

- A ALL EQUIPMENT FURNISHED UNDER DIVISION 26 SHALL CARRY UL LABELS AND LISTINGS WHERE SUCH LABELS AND LISTINGS ARE AVAILABLE IN THE INDUSTRY.
- B.MANUFACTURERS OF EQUIPMENT SHALL HAVE A MINIMUM OF THREE YEARS EXPERIENCE WITH THEIR EQUIPMENT INSTALLED AND OPERATING IN THE FIELD IN A USE SIMILAR TO THE PROPOSED USE FOR THIS
- C.MATERIALS AND EQUIPMENT: ALL MATERIALS AND EQUIPMENT SPECIFIED IN DIVISION 26 OF THE SAME TYPE SHALL BE OF THE SAME MANUFACTURER AND SHALL BE NEW, OF THE BEST QUALITY AND DESIGN, AND FREE FROM DEFECTS

SUPPORTING DEVICES

- A.MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING
- I. ALLIED TUBE AND CONDUIT
- 2. B-LINE SYSTEM.
- 3. UNISTRUT DIVERSIFIED PRODUCTS.
- 4. THOMAS # BETTS.

B.FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS

- I. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
- 2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED
- 3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
- 4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
- 5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY
- 6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL
- 7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
- 8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL
- 9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

ertification ¢ Seal:

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.



0/26/17 REVISED RF AND STRUCTURAL DETAILS

10/26/201

DATE 08/10/2017

FINAL

DATE DESCRIPTIO

UNIONVILLE / POLICE DEPARTMENT CT33XC534-B

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

SPRINT SPECIFICATIONS

SCALE: NONE

23009 SHEET

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
- I. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF
- 2. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS
- BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

- RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR UNDERGROUND RUNS. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS, CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS CAO. I., FEDERAL SPECIFICATION WV-C-58 | AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES, FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP
- D. FMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT
- LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCED G-FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRED BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (2 I MM)

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
 - CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL BY
 - CABLE TERMINATORS FOR LFMC SHALL BE ETCO CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKET COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL
- MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER. ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM:

- FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM TO THE EXTENT INDICATED ON THE DRAWINGS, SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS EXCEPT AS OTHERWISE NOTED.
- SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO-OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION

CONDUIT AND CONDUCTOR INSTALLATION:

A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS, EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED.
CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TICHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES, CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON

B.CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592





| -1 | 10/26/17 | REVISED RF AND STRUCTURAL DETAILS |
|------|----------|-----------------------------------|
| MARK | DATE | DESCRIPTION |

SUE FINAL

UNIONVILLE / POLICE DEPARTMENT

DATE 08/10/2017

CT33XC534-B

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

SPRINT SPECIFICATIONS

SCALE: NONE

23009 SP-3 SHEET






6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592



| | 10/26/17 | REVISED RF AND STRUCTURAL DETAILS |
|----------|----------|-----------------------------------|
| RK | DATE | DESCRIPTION |
| UE SE | | DATE 08/10/20 |

UNIONVILLE / POLICE DEPARTMENT CT33XC534-B

PROJECT INFORMATION:
3 | 9-32 | NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:

SITE PLAN

| 0 | 3.7 | 75' I | 7. | 5' I | | 15' |
|-------------------|-----|----------|------------------|---------------|----|-----|
| | | | | | | |
| 11" x 22" x | | | " = 1 " = 1 | 7.5' 3.75' | | |
| PROJECT NUMBER | [| | | 2300 | D9 | |
| SHEET | | | | Α_ | | |






6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592




UNIONVILLE / POLICE


DEPARTMENT CT33XC534-B

PROJECT INFORMATION:
3 | 9-32 | NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITLE:


EQUIPMENT PLAN







EQUIPMENT PLAN


SCALE: |" = 2.5'





EXISTING ANTENNA ARRAY







6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

ertification ¢ Seal:

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.




DATE DESCRIPTION FINAL DATE 08/10/2017 UNIONVILLE / POLICE

DEPARTMENT CT33XC534-B

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

BUILDING ELEVATIONS \$ ANTENNA DETAILS



RFDS Sheet

General Site Information

| Site ID | CT33XC534 |
|----------------|----------------------|
| Market | Northern Connecticut |
| Region | Northeast |
| MLA | N/A |
| Structure Type | Monopole |
| BTS Type | |
| | |

Equipment Vendor Alcatel-Lucent 41.749722 Lattitude -72.8725 Longitude LL SITE ID N/A

Solution ID

Siterra SR Equipment type **Equipment Vendor** Alcatel-Lucent Incremental Power Draw needed by added Equipment N/A

Base Equipment

| BBU | Kit |
|-----|---------|
| BBU | Kit Qty |

| ALU BBU Kit | |
|-------------|--|
| 1 | |
| | |

None

N/A N/A

N/A

| Top Hat | None |
|----------------------|------|
| Top Hat Qty | N/A |
| Top Hat Dimenstions | N/A |
| Top Hat Weight (lbs) | N/A |

Growth Cabinet

| Growth Cabinet Qty | |
|---------------------------------|---|
| Growth Cabinet Dimension | S |
| Growth Cabinet Weight | |

RF Path Information

| THE PARTY NAMED IN COLUMN |
|-----------------------------------|
| RRH |
| RRH Qty |
| RRH Dimensions |
| RRH Weight. lbs. |
| RRH Mount Weight. Lbs. |
| Power and Fiber Cable |
| Cable Qty |
| Weight perfoot. Lbs. |
| Diameter. Inches. |
| Length Ft. |
| Coax Jumper |
| Coax Jumper Qty |
| Coax Jumper Length. Feet. |
| Coax Jumper Weight |
| Coax Jumper Diameter. Inches |
| AISG Cable |
| AISG Cable Qty |
| AISG Diameter. Inches. |
| AISG Cable length. |
| Weight of entire AISG cable. Lbs. |
| |

| TD-RRH8x20-25 & RRH-2X50-800 |
|------------------------------|
| (3-EACH, 6-TOTAL) |
| SEE SHEET A-7 |
| SEE SHEET A-7 |
| SEE SHEET A-7 |
| ALU HYBRIFLEX |
| 1 |
| 1 |
| 1.54 |
| 225 |
| 2.5 JUMPER |
| 27 |
| 8 |
| 1.7 |
| 0.5 |
| COMMSCOPE ATCB-B01-006 |
| 3 |
| 0.315 |
| 8' |
| 1.3 |
| <u> </u> |

(calculated as antenna height plus 20%)

Antenna Sector Information

| Antenna make/model |
|-----------------------------------|
| Antenna qty |
| Antenna Dimensions. Inches |
| Antenna Weight. Lbs |
| Antenna Mounting Kit Weight. Lbs. |
| CL Height |
| Antenna Azimuth |
| Antenna Mechanical Downtilt |

Antenna etilt

| Sector 1 | Sector 2 | Sector 3 |
|----------------------|----------------------|----------------------|
| COMMSCOPE DT465B-2XR | COMMSCOPE DT465B-2XR | COMMSCOPE DT465B-2XR |
| 1 | 1 | 1 |
| 26"x18.6"x6.7" | 26"x18.6"x6.7" | 26"x18.6"x6.7" |
| 76.2 | 76.2 | 76.2 |
| 11.5 | 11.5 | 11.5 |
| 170 | 170 | 170 |
| 340 | 90 | 210 |
| 0 | 0 | 0 |
| -2 | -2 | -2 |

*RFDS SHEET WAS GENERATED BY RAMAKER \$ ASSOCIATES FROM PLAN OF RECORD (POR) PROVIDED BY SPRINT. CONTRACTOR SHALL VERIFY AND OBTAIN FINAL RFDS FROM SPRINT CONSTRUCTION MANAGER PRIOR TO CONSTRUCTION.



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

ertification # Seal:

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.



4. 2.5GHZ ANTENNA MUST BE AT LEAST 6" FROM 1.9GHZ ANTENNA, 30" FROM 800MHZ ANTENNA AND 30" FROM DUAL BAND 1.9GHZ AND 800MHZ

5. GENERAL CONTRACT IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN I DEGREE. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN O. I DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE
AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.

I. GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND C/L HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT BELOW, HALT ANTENNA WORK FOR

ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE

A MESSAGE TO RF ENGINEER) USING CONTACT INFORMATION ABOVE FOR FURTHER INSTRUCTIONS. IF

PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED, VERIFY

OPERATION OF ALL EXISTING SPRINT AIGE EQUIPMENT INCLUDING 800MHZ, I.9GHZ AND 2.5GHZ. TEST TO INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF

3. GENERAL CONTRACTOR MUST ENSURE THAT NO OBJECT IS LOCATED WITHIN 45 DEGREES OF LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5GHZ ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES

SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5GHZ ANTENNA AT SAME C/L HEIGHT AS

I .9GHZ ANTENNA AND EMAIL CORRECT C/L HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER, UPDATE AS-BUILD DRAWING WITH CORRECT C/L HEIGHT. ALSO EMAIL CORRECT I .9GHZ AND 800MHZ ANTENNA C/L HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF


2. AISG TESTS TO VERIFY OPERATION IS TO BE

APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX

SPRINT AND NON-SPRINT ANTENNAS.

SWEEP TEST SPREADSHEET.

NOTES:



FINAL DATE 08/10/2017 UNIONVILLE / POLICE

> DEPARTMENT CT33XC534-B

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY


SHEET TITLE:


RF DATA SHEET

SCALE: NONE


23009 SHEET A-4


8T8R DETAIL





RRH TO DISTRIBUTION BOX POWER CONNECTIVITY DETAIL





RRH TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL

Sprint[®]

6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

hereby certify that this plan, specification, or report was prepar by me or under my direct supervision and that I am a duly License Professional Engineer under the laws of the State of Connecticut



10/26/17 REVISED RF AND STRUCTURAL DETAILS

UNIONVILLE / POLICE DEPARTMENT

DATE 08/10/2017

CT33XC534-B PROJECT INFORMATION:
3 | 9-32 | NEW BRITAIN AVENUE FARMINGTON, CT 06032

HARTFORD COUNTY

FIBER PLUMBING DIAGRAM

SCALE: NONE


23009 SHEET A-5

BTS TO DISTRIBUTION BOX FIBER CONNECTIVITY DETAIL (4)


| 2.5 FREQUENCY | INDICA | ΓOR | ID |
|------------------|--------|-----|-----|
| 2500 -1 | YEL | WHT | GRN |
| 2500 -2 | YEL | WHT | RED |
| 2500 -3 | YEL | WHT | BRN |
| 2500 -4 | YEL | WHT | BLU |
| 2500 -5 | YEL | WHT | SLT |
| 2500 -6 | YEL | WHT | ORG |
| 2500 -7 | YEL | WHT | WHT |
| 2500 -8 | YEL | WHT | PPL |
| | _ | | • |
| | т п | | |
| St 421 | | | |


| NV | | |
|-----------|-----------|-----|
| FREQUENCY | INDICATOR | ID |
| 800-1 | YEL | GRN |
| 1900-1 | YEL | RED |
| 1900-2 | YEL | BRN |
| 1900-3 | YEL | BLU |
| 1900-4 | YEL | SLT |
| 800-1 | YEL | ORG |
| RESERVED | YEL | WHT |
| RESERVED | YEL | PPL |

| | | | Second | |
|---------|-------|------------|---------|------------|
| Sector | Cable | First Ring | Ring | Third Ring |
| 1 Alpha | 1 | Green | No Tape | No Tape |
| 1 | 2 | | No Tape | No Tape |
| 1 | 3 | Brown | No Tape | No Tape |
| 1 | 4 | White | No Tape | No Tape |
| 1 | 5 | Red | No Tape | No Tape |
| 1 | 6 | Grey | No Tape | No Tape |
| 1 | 7 | Purple | No Tape | No Tape |
| 1 | 8 | Orange | No Tape | No Tape |
| 2 Beta | 1 | Green | Green | No Tape |
| 2 | 2 | | | No Tape |
| 2 | 3 | Brown | Brown | No Tape |
| 2 | 4 | White | White | No Tape |
| 2 | 5 | Red | Red | No Tape |
| 2 | 6 | Grey | Grey | No Tape |
| 2 | 7 | Purple | Purple | No Tape |
| 2 | 8 | Orange | Orange | No Tape |
| 3 Gamma | 1 | Green | Green | Green |
| 3 | 2 | | | Blue |
| 3 | 3 | Brown | Brown | Brown |
| 3 | 4 | White | White | White |
| 3 | 5 | Red | Red | Red |
| 3 | 6 | Grey | Grey | Grey |
| 3 | 7 | Purple | Purple | Purple |
| 3 | 8 | Orange | Orange | Orange |









COLOR CODING CHARTS



CABLE MARKING NOTES

- I. ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED. UI APPROVED TAPE
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAKOUT UNIT. THERE SHALL BE I" SPACE BETWEEN EACH RING.
- 3. A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- 4. THE 2" COLORED TAPE(S) SHALL BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- 5. SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE SECOND CABLE IDENTIFIED BY BLUE BANDS OF TAPE
- 6. HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- 7. HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES
 SHALL BE LABELED WITH BOTH THE CABLE AND
 FREQUENCY.



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com


Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

ertification \$ Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.





I I 0/26/17 REVISED RF AND STRUCTURAL DETAILS TARK DATE DESCRIPTION

ISSUE FINAL

DATE 08/10/2017

PROJECT TITLE

UNIONVILLE / POLICE DEPARTMENT CT33XC534-B

PROJECT INFORMATION:
3 | 9-32 | NEW BRITAIN AVENUE
FARMINGTON, CT 06032
HARTFORD COUNTY

SHEET TITL

CABLE COLOR CODING

SCALE: NONE

PROJECT 23009
SHEET NUMBER A-6

RFS: APXVTM | 4-ALU- | 20

56.3" x 12.6" x 6.3" DIMENSIONS, HxWxD:

WEIGHT, WITHOUT PRE-MOUNTED BRACKETS: 55.12 lbs.

CONNECTOR: (9) XX" MINI-DIN FEMALE/BOTTOM

800MHz 2X50W Remote Radio Head (RRH)

Simultaneous CDMA & LTE Multi technology RRH 862-869 MHz

Any combination of CDMA and LTE carriers supported by 100W RF Power

2 CPRI-like Optical Connections for daisy chaining Software Switchable External Filter for use before

Public Safety is cleared

w/ Filter Dimensions: w/o Filter 480 mm (19") Height: 480 mm (19") Width: 330 mm (13") 330 mm (13") Depth: 218 mm (8.6") 310 (12.2") Weight: 24 kg (53 lbs) 29 kg (64 lbs)

49 liters, <29kg Power Supply: -48 VDC

Power Consumption: <400W Typical Operating Temp range -40°C to +55°C Option to mount on Ground at tower base **Bottom View**

Front/Top View

INTERNATION OF THE GO

Alcatel-Lucent's 800 RRH satisfies Sprint's requirements.

| MECHANICAL | | |
|-------------------|-------------------|--|
| DIMENSION (HxWxD) | 19" x 13" x 12.2" | |
| WEIGHT | 64 lbs | |

RRH MODEL: ALU #800 MHz 2x50W - RADIO SPECS

800 RRH DETAIL



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

hereby certify that this plan, specification, or report was in by me or under my direct supervision and that I am a duly L Professional Engineer under the laws of the State of Conne



I 10/26/17 REVISED RF AND STRUCTURAL DETAILS ARK DATE DESCRIPTION

DATE 08/10/2017


UNIONVILLE / POLICE DEPARTMENT CT33XC534-B

PROJECT INFORMATION: 3 | 9-32 | NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

ANTENNA & RRH DETAILS


SCALE: NONE

23009 SHEET A-7



SIDE VIEW





EXISTING COAX PORT IN THE CEILING ROUTE (I) NEW | 1/4" COAX IN EXISTING CABLE LADDER AND ICE BRIDGE, TO 2.5 ANTENNA AT ALPHA SECTOR EXISTING CABLE LADDER DISTRIBUTION BOX MOUNTED ON WALL - PROPOSED 2.5 EQUIPMENT AND RECTIFIER UNIT TO BE EXISTING SPRINT INSTALLED IN EXISTING 9927 EQUIPMENT ROOM IN BUILDING PROVIDE 2" METALLIC HUB AND RIGID-CONDUIT CONNECTOR AND INSTALL CONNECTION KIT THE EXISTING 9927 MT-BTS TO EXISTING FIBER DISTRIBUTION BOX WITH DC POWER CABLE ROUTE FROM CABINET

PROPOSED BATTERY STRING TO BE INSTALLED IN EXISTING BATTERY CABINET




EXISTING BBU CABINET

INSTALL NEW 2.5 EQUIPMENT, INCLUDING BASE BAND UNIT, CELL SITE ROUTER, RECTIFIERS, AND SURGE ARRESTORS AS NEEDED IN EXISTING MM-BTS CABINET



♯ FIBER CABLES



(4)

EXISTING MMBS CABINET SCALE: NTS

Sprint

6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.



10/26/17 REVISED RF AND STRUCTURAL DETAILS DATE 08/10/2017

FINAL

UNIONVILLE / POLICE

DEPARTMENT

CT33XC534-B 319-321 NEW BRITAIN AVENUE

FARMINGTON, CT 06032 HARTFORD COUNTY

EQUIPMENT DETAILS

SCALE: NONE

23009 SHEET A-8

GENERAL NOTES:

- ALL WORK PRESENTED ON THESE DRAWINGS MUST BE COMPLETED BY THE CONTRACTOR UNLESS NOTED OTHERWISE. THE CONTRACTOR MUST HAVE CONSIDERABLE EXPERIENCE IN PERFORMANCE OF WORK SIMILAR TO THAT DESCRIBED HEREIN. BY ACCEPTANCE OF THIS ASSIGNMENT, THE CONTRACTOR IS ATTESTING THAT HE DOES HAVE SUFFICIENT EXPERIENCE AND ABILITY, THAT HE IS KNOWLEDGEABLE OF THE WORK TO BE PERFORMED AND THAT HE IS PROPERLY LICENSED AND PROPERLY REGISTERED TO DO THIS WORK IN THE STATE AND/OR COUNTY IN WHICH IT IS TO BE PREFORMED.
- WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE CURRENT STATE BUILDING CODE.
- UNLESS SHOWN OR NOTED OTHERWISE ON THE CONTRACT DRAWINGS, OR IN THE SPECIFICATIONS, THE FOLLOWING NOTES SHALL APPLY TO THE MATERIALS LISTED HEREIN, AND TO THE PROCEDURES TO BE USED ON THIS PROJECT.
- ALL HARDWARE ASSEMBLY MANUFACTURERS' INSTRUCTIONS SHALL BE FOLLOWED EXACTLY AND SHALL SUPERSEDE ANY CONFLICTING NOTES ENCLOSED HEREIN.
- IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURE AND SEQUENCE TO INSURE THE SAFETY OF THE STRUCTURE AND ITS COMPONENT PARTS DURING ERECTION AND/OR FIELD MODIFICATIONS. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF TEMPORARY BRACING, GUYS OR TIE DOWNS THAT MAY BE NECESSARY. SUCH MATERIAL SHALL BE REMOVED AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER THE COMPLETION OF THE PROJECT.
- ALL DIMENSIONS, ELEVATIONS, AND EXISTING CONDITIONS SHOWN ON THE DRAWINGS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO BEGINNING ANY MATERIALS ORDERING, FABRICATION OR CONSTRUCTION WORK ON THIS PROJECT. CONTRACTOR SHALL NOT SCALE CONTRACT DRAWINGS IN LIEU OF FIELD VERIFICATIONS. ANY DISCREPANCIES SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF THE OWNER AND THE OWNER'S ENGINEER. THE DISCREPANCIES MUST BE RESOLVED BEFORE THE CONTRACTOR IS TO PROCEED WITH THE WORK. THE CONTRACT DOCUMENTS DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. OBSERVATION VISITS TO THE SITE BY THE OWNER AND/OR THE ENGINEER SHALL NOT INCLUDE INSPECTION OF THE PROTECTIVE MEASURES OR THE **PROCEDURES**
- ALL MATERIALS AND EQUIPMENT FURNISHED SHALL BE NEW AND OF GOOD QUALITY, FREE FROM FAULTS AND DEFECTS AND IN CONFORMANCE WITH THE CONTRACT DOCUMENTS. ANY AND ALL SUBSTITUTIONS MUST BE PROPERLY APPROVED AND AUTHORIZED IN WRITING BY THE OWNER AND ENGINEER PRIOR TO INSTALLATION THE CONTRACTOR SHALL FURNISH SATISFACTORY EVIDENCE AS TO THE KIND AND QUALITY OF THE MATERIALS AND EQUIPMENT BEING SUBSTITUTED
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT THIS PROJECT AND RELATED WORK COMPLIES WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL SAFETY CODES AND REGULATIONS GOVERNING THIS
- ACCESS TO THE PROPOSED WORK SITE MAY BE RESTRICTED. THE CONTRACTOR SHALL COORDINATE INTENDED CONSTRUCTION ACTIVITY, INCLUDING WORK SCHEDULE AND MATERIALS ACCESS, WITH THE RESIDENT LEASING AGENT FOR APPROVAL
- O. ALL PERMITS THAT MUST BE OBTAINED ARE THE RESPONSIBILITY OF THE CONTRACTOR, THE CONTRACTOR WILL BE RESPONSIBLE FOR ABIDING BY ALL CONDITIONS AND REQUIREMENTS OF THE PERMITS.
- IF APPLICABLE. ALL CONCRETE WORK SHALL COMPLY WITH LOCAL CODES AND THE ACI 318-11, "BUILDING REQUIREMENTS FOR STRUCTURAL CONCRETE".
- 2. 24 HOURS PRIOR TO THE BEGINNING OF ANY CONSTRUCTION, THE CONTRACTOR MUST NOTIFY THE APPLICABLE JURISDICTIONAL (STATE, COUNTY OR CITY) ENGINEER
- 3. ALL MATERIALS AND WORKMANSHIP SHALL BE WARRANTED FOR ONE YEAR FROM ACCEPTANCE DATE.
- 4. ALL TOWER DIMENSIONS SHALL BE VERIFIED WITH THE PLANS (LA TEST REVISION) PRIOR TO COMMENCING CONSTRUCTION. NOTIFY THE ENGINEER IMMEDIATELY IF ANY DISCREPANCIES ARE DISCOVERED. THE OWNER SHALL HAVE A SET OF APPROVED PLANS AVAILABLE AT THE SITE AT ALL TIMES WHILE WORK IS BEING PERFORMED A DESIGNATED RESPONSIBLE EMPLOYEE SHALL BE AVAILABLE FOR CONTACT BY GOVERNING AGENCY.
- . THE CLIMBING FACILITIES, SAFETY CLIMB AND ALL PARTS THEREOF

- SHALL NOT BE IMPEDED, MODIFIED OR ALTERED WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE TOWER OWNER OR ENGINEER OF RECORD
- 16. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN AND SHALL MEET ANSI/TIA 1019 (LATEST EDITION), OSHA, AND GENERAL INDUSTRY STANDARDS. ALL RIGGING PLANS SHALL ADHERE TO ANSI/TIA-1019 (LATEST EDITION).

STRUCTURAL STEEL NOTES:

- THE FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO THE AISC SPECIFICATION FOR MANUAL OF STEEL CONSTRUCTION, LOAD AND RESISTANCE FACTOR DESIGN (LRFD), L3TH FDITION
- UNLESS OTHERWISE NOTED, ALL STRUCTURAL ELEMENTS SHALL CONFORM TO THE FOLLOWING REQUIREMENTS: STRUCTURAL STEEL
- ANGLE: ASTM A36
- PIPE/TUBE: ASTM A500-46
 PLATE: ASTM A572-50 (SELF SUPPORTING AND GUYED TOWERS), UNLESS NOTED OTHERWISE

 UNLESS NOTED OTHERWISE
- PLATE: ASTM A572-65 (MONOPOLE)
- BOLTS: ASTM A325 TYPE I GALVANIZED HIGH STRENGTH BOLTS.
- U-BOLTS: ASTM A | 93 GRADE B7
- NUTS: ASTM A563 CARBON AND ALLOY STEEL NUTS.
- WASHERS: ASTM F436 HARDENED STEEL WASHERS.
- 3. ALL CONNECTIONS NOT FULLY DETAILED ON THESE PLANS SHALL BE DETAILED BY THE STEEL FABRICATOR IN ACCORDANCE WITH AISC SPECIFICATION FOR MANUAL OF STEEL CONSTRUCTION, LRFD, 13TH
- HOLES SHALL NOT BE FLAME CUT THROUGH STEEL UNLESS APPROVED BY THE ENGINEER.
- HOT -DIP GALVANIZE ALL ITEMS UNLESS OTHERWISE NOTED, AFTER FABRICATION WHERE PRACTICABLE. GALVANIZING: ASTM A I 23, ASTM, A153/A153M OR ASTM A653/A653M, G90, AS APPLICABLE. ADDITIONALLY, ALL NEW STEEL SHALL BE PAINTED TO MATCH EXISTING STEEL. CONTRACTOR SHALL OBTAIN WRITTEN PERMISSION TO PROTECT STEEL BY ANY OTHER MEANS.
- REPAIR DAMAGED SURFACES WITH GALVANIZING REPAIR METHOD AND PAINT CONFORMING TO ASTM A7BO OR BY APPLICATION OF STICK OR THICK PASTED MATERIAL SPECIFICALLY DESIGNED FOR REPAIR OF GALVANIZING. CLEAN AREAS TO BE REPAIRED AND REMOVE SLAG FROM WELDS. HEAT SURFACES TO WHICH STICK OR PASTE MATERIAL IS APPLIED, WITH A TORCH TO A TEMPERATURE SUFFICIENT TO MELT THE METALLICS IN STICK OR PASTED: SPREAD MOLTEN MATERIAL UNIFORMLY OVER SURFACES TO BE COATED AND WIPE OFF EXCESS MATERIAL. AFTER REPAIR, STEEL SHALL BE REPAINTED TO MATCH EXISTING FINISH (IF APPLICABLE).
- A NUT LOCKING DEVICE SHALL BE INSTALLED ON ALL PROPOSED AND/OR REPLACED BOLTS.
- ALL PROPOSED AND/OR REPLACED BOLTS SHALL BE OF SUFFICIENT LENGTH TO EXCLUDE THE THREADS FROM THE SHEAR PLANE.
- ALL PROPOSED AND/OR REPLACED BOLTS SHALL BE OF SUFFICIENT LENGTH SUCH THAT THE END OF THE BOLT BE AT LEAST FLUSH WITH THE FACE OF THE NUT. IT IS NOT PERMITTED FOR THE BOLT END TO BE BELOW THE FACE OF THE NUT AFTER TIGHTENING IS
- 10. GALVANIZED ASTM A325 BOLTS SHALL NOT BE REUSED.

WELDING NOTES:

- ALL WELDING SHALL BE IN ACCORDANCE WITH THE AWS DI. I/DI. IM: 2010 "STRUCTURAL WELDING CODE-STEEL"
- 2. ALL WELDING SHALL BE PERFORMED BY AWS CERTIFIED WELDERS.
- CONTRACTOR SHALL RETAIN AN AWS CERTIFIED WELD INSPECTOR TO PERFORM VISUAL INSPECTIONS ON FIELD WELDS
- GRIND THE SURFACE ADJACENT TO THE WELD FOR A DISTANCE OF 2" MINIMUM ALL AROUND, GRIND THE SURFACE OF THE ROD TO BE INSTALLED FOR A DISTANCE OF 2" MINIMUM ALL AROUND THE AREA TO BE WELDED. ENSURE BOTH AREAS ARE 100% FREE OF ALL GALVANIZING. SURFACES TO BE WELDED SHALL BE FREE FROM SCALE, SLAG, RUST, MOISTURE, GREASE OR ANY OTHER FOREIGN MATERIAL THAT WOULD PREVENT PROPER WELDING.
- DO NOT WELD IF THE TEMPERATURE OF THE STEEL IN THE VICINITY OF THE WELD AREA IS BELOW O DEG F. THE MINIMUM PREHEAT AND INTERPASS TEMPERATURE REQUIREMENTS SHALL COMPLY WITH SECTION 3.5.1 AND TABLE 3.2 OF THE AWS D1.1/D1.1M: 2010.

- DO NOT WELD ON WET ON FROST -COVERED SURFACES AND PROVIDE ADEQUATE PROTECTION FROM HIGH WINDS
- 7. FOR ALL WELDING, USE 70 KSI LOW HYDROGEN ELECTRODES ELECTRODES SHALL BE APPROPRIATE FOR THE WELDING POSITION REQUIRED TO MAKE THE JOINT.
- 8. AFTER FINAL INSPECTION, THE AREA OF THE WELDS, THE INSTALLATION AND ALL SURFACES DAMAGED BY WELDING OR GRINDING SHALL RECEIVE A COLD-GALVANIZED COATING. THIS COATING SHALL BE APPLIED BY BRUSH. THE GALVANIZING COMPOUND SHALL CONTAIN A MINIMUM OF 95% ± PURE ZINC THE FINISHED COATING SHALL BE A MINIMUM THICKNESS OF 3
- 9. FOR MONOPOLE TOWERS FULL PENETRATION WELDS IN THE VICINITY OF THE BASE OF THE TOWER ARE REQUIRED TO BE 100% NDE INSPECTED BY ULTRASONIC TESTING (UT) IN ACCORDANCE
- IO. FOR MONOPOLE TOWERS PARTIAL PENETRATION AND FILLET WELDS IN THE VICINITY OF THE BASE OF THE TOWER ARE REQUIRED TO BE 50% NDE INSPECTED BY MAGNETIC PARTICLE (MT) IN ACCORDANCE WITH AWS DI. I

BOLT TIGHTENING PROCEDURE:

- TIGHTEN CONNECTION BOLTS BY AISC "TURN OF THE NUT" METHOD, USING THE CHART BELOW.
- BOLT LENGTHS UP TO AND INCLUDING FOUR DIAMETERS 1/2" BOLTS UP TO AND INCLUDING 2.0 INCH LENGTH + 1/3 TURN BEYOND SNUG TIGHT
- 5/8" BOLTS UP TO AND INCLUDING 2.5 INCH LENGTH
- + I/3 TURN BEYOND SNUG TIGHT 3/4" BOLTS UP TO AND INCLUDING 3.0 INCH LENGTH
- + I/3 TURN BEYOND SNUG TIGHT
- 7/8" BOLTS UP TO AND INCLUDING 3.5 INCH LENGTH
- + I/3 TURN BEYOND SNUG TIGHT
- I" BOLTS UP TO AND INCLUDING 4.0 INCH LENGTH + I/3 TURN BEYOND SNUG TIGHT
- BOLT LENGTHS OVER FOUR DIAMETERS BUT NOT EXCEEDING EIGHT DIAMETERS
- 1/2" BOLTS 2.25 TO 4.0 INCH LENGTH
- + I/2 TURN BEYOND SNUG TIGHT
- 5/8" BOLTS 2.75 TO 5.0 INCH LENGTH + 1/2 TURN BEYOND SNUG TIGHT
- 3/4" BOLTS 3.25 TO 6.0 INCH LENGTH
- + 1/2 TURN BEYOND SNUG TIGHT
- 7/8" BOLTS 3.75 TO 7.0 INCH LENGTH + I/2 TURN BEYOND SNUG TIGHT
- I" BOLTS 4.25 TO 8.0 INCH LENGTH
- + I/2 TURN BEYOND SNUG TIGHT
- CONNECTION BOLTS SUBJECT TO DIRECT TENSION SHALL BE INSTALLED AND TIGHTENED AS PER SECTION 8.2.1 OF THE AISC SPECIFICATION FOR STRUCTURAL JOINTS USING A325 OR A490 BOLTS, LOCATED IN THE AISC MANUAL OF STEEL CONSTRUCTION. THE INSTALLATION PROCEDURE IS PARAPHRASED AS FOLLOWS
- 3. FASTENERS SHALL BE INSTALLED IN PROPERLY ALIGNED HOLES AND TIGHTENED BY ONE OF THE METHODS DESCRIBED IN SUBSECTION 8.2.1 THROUGH 8.2.4.
- TURN-OF-THE-NUT TIGHTENING BOLTS SHALL BE INSTALLED IN ALL HOLES OF THE CONNECTION AND BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION B. I, UNTIL ALL THE BOLTS ARE SIMULTANEOUSLY SNUG TIGHT AND THE CONNECTION IS FULLY COMPACTED. FOLLOWING THIS INITIAL OPERATION ALL BOLTS IN THE CONNECTION SHALL BE TIGHTENED FURTHER BY THE APPLICABLE AMOUNT OF ROTATION SPECIFIED ABOVE. DURING THE TIGHTENING OPERATION THERE SHALL BE NO ROTATION OF THE PART NOT TURNED BY THE WRENCH. TIGHTENING SHALL PROGRESS SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT IN A MANNER THAT WILL MINIMIZE RELAXATION OF PREVIOUSLY PRE-TENSIONED BOLTS
- ALL OTHER BOLTED CONNECTIONS SHALL BE BROUGHT TO A SNUG TIGHT CONDITION AS DEFINED IN SECTION 8.1 OF THE SPECIFICATION



6580 SPRINT PARKWAY **OVERLAND PARK, KANSAS 66251**



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

ertification # Seal:

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.



10/26/17 REVISED RF AND STRUCTURAL DETAILS

FINIAL

UNIONVILLE / POLICE DEPARTMENT

DATE 08/10/2017

CT33XC534-B


319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY


STRUCTURAL NOTES

SCALE: NONE

23009

S-1 SHEET





GENERAL NOTES

- I. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS PRIOR TO FABRICATION AND CONSTRUCTION.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING AND NEW COAXIAL CABLES AND OTHER EQUIPMENT DURING CONSTRUCTION
- 3. ANY EXISTING ATTACHMENTS AND/OR PROJECTIONS ON THE POLE THAT MAY INTERFERE WITH THE INSTALLATION OF THE REINFORCING SYSTEM WILL HAVE TO BE REMOVED, AND/OR RELOCATED, AND/OR REPLACED AND RE-INSTALLED AFTER THE REINFORCING IS SUCCESSFULLY COMPLETED. THE CONTRACTOR SHALL IDENTIFY AND COORDINATE THESE ITEMS PRIOR TO CONSTRUCTION WITH THE OWNER, TESTING AGENCY, AND ENGINEER.

STRUCTURAL STEEL

I. STRUCTURAL STEEL MATERIALS, FABRICATIONS, DETAILING, AND WORKMANSHIP SHALL CONFORM TO THE LATEST ADDITION OF THE FOLLOWING REFERENCE STANDARDS:

BY THE AMERICAN INSTITUTION OF STEEL CONSTRUCTION (AISC):

- A. "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS."
- B. "SPECIFICATIONS FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS," AS APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS OF THE ENGINEERING FOUNDATION.
- C. "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES" (PARAGRAPH 4.2.1 SPECIFICALLY EXCLUDED).

BY THE AMERICAN WELDING SOCIETY (AWS):


- A. "STRUCTURAL WELDING CODE STEEL DI.I."
- B. "SYMBOLS FOR WELDING AND NON-DESTRUCTIVE TESTING."
- 2. ANY MATERIAL OR WORKMANSHIP WHICH IS OBSERVED TO BE DEFECTIVE OR INCONSISTENT WITH THE CONTRACT DOCUMENTS SHALL BE CORRECTED, MODIFIED, OR REPLACED AT THE CONTRACTORS EXPENSE.
- 3. TIGHTEN ALL STRUCTURAL BOLTS, INCLUDING THE AJAX M20 BOLTS WITH SHEAR SLEEVES, ACCORDING TO THE REQUIREMENTS OF THE AISC "TURN OF THE NUT" METHOD. TIGHTEN BOLTS 1/3 TURN PAST THE SNUG TIGHT CONDITION AS DEFINED BY AISC.
- 4. WELDED CONNECTIONS SHALL CONFORM TO THE LATEST REVISED CODE OF THE AMERICAN WELDING SOCIETY, AWS DI.I. ALL WELD ELECTRODES SHALL BE E80XX UNLESS NOTED OTHERWISE ON THE DRAWINGS.
- ALL WELDED CONNECTIONS SHALL BE MADE BY WELDERS CERTIFIED BY AWS. CONTRACTOR SHALL SUBMIT WELDERS'
 CERTIFICATION AND QUALIFICATION DOCUMENTATION TO THE OWNER'S TESTING AGENCY FOR REVIEW AND APPROVAL
 PRIOR TO CONSTRUCTION.
- 6. STRUCTURAL STEEL PLATES SHALL CONFORM TO ASTM A572 GRADE 65 (FY = 65 KSI MIN.) UNLESS NOTED OTHERWISE ON THE DRAWINGS.
- 7. SURFACES OF EXISTING STEEL SHALL BE PREPARED AS REQUIRED FOR FIELD WELDING PER AWS.
 UNLESS OTHERWISE NOTED, ALL STEEL MEMBERS SHALL BE HOT-DIP GALVANIZED, AFTER FABRICATION, IN ACCORDANCE WITH ASTM A L 23.

TOUCH-UP OF GALVANIZING

I. THE CONTRACTOR SHALL TOUCH-UP ANY AND/OR ALL AREAS OF GALVANIZING ON THE EXISTING STRUCTURE OR NEW COMPONENTS THAT ARE DAMAGED OR ABRADED DURING CONSTRUCTION. GALVANIZED SURFACES DAMAGED DURING TRANSPORTATION OR ERECTION AND ASSEMBLY AS WELL AS ANY AND ALL ABRASIONS, CUTS, FIELD DRILLING, AND ALL FIELD WELDING SHALL BE TOUCHED UP WITH TWO (2) COATS OF ZRC-BRAND ZINC-RICH COLD GALVANIZING COMPOUND. FILM THICKNESS PER COAT SHALL BE: WET 3.0 MILS; DRY I.5 MILS. APPLY PER ZRC (MANUFACTURER) RECOMMENDED PROCEDURES. CONTACT ZRC AT I-800-831-3275 FOR PRODUCT INFORMATION.

PERPETUAL INSPECTION AND MAINTENANCE BY THE OWNER

- I. AFTER THE CONTRACTOR HAS SUCCESSFULLY COMPLETED THE INSTALLATION OF THE MONOPOLE REINFORCING SYSTEM AND THE WORK HAS BEEN ACCEPTED BY THE OWNER, THE OWNER WILL BE RESPONSIBLE FOR THE LONG TERM AND PERPETUAL INSPECTION AND MAINTENANCE OF THE POLE AND REINFORCING SYSTEM.
- 2. THE OWNER SHALL REFER TO TIA-222-G, SECTION 14 AND ANNEX J FOR RECOMMENDATIONS FOR MAINTENANCE AND INSPECTION. THE FREQUENCY OF THE INSPECTION AND MAINTENANCE INTERVALS IS TO BE DETERMINED BY THE OWNER BASED UPON ACTUAL SITE AND ENVIRONMENTAL CONDITIONS.





6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592





IO/26/17 REVISED RF AND STRUCTURAL DETAILS

K DATE DESCRIPTION

PROJECT TITLE:

UNIONVILLE / POLICE DEPARTMENT CT33XC534-B

DATE 08/10/2017

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY


SHEET TITLE:


STRUCTURAL DETAILS

SCALE: NONE

PROJECT 23009

NUMBER 5-4





| FORGEE | BOLT | AISC GROUP A MATERIAL: ASTM A325 AND PC8.8 (TENSILE STRESS, F_{0} = 120 K; | | AISC GROUP A MATERIAL: ASTM A325 AND PC8.8 (TENSILE STRESS, Fu = 1 | | AISC GROUP A MATERIAL: ASTM A325 AND PC8.8 (TENSILE STRESS, $F_U = 1$ | | 120 KSI MIN.) | |
|------------|------------------------|--|---------------------|--|---------------------|---|--|---------------|--|
| GROUP A | FORGEBOLT SIZE (MM) | LENGTH (IN) | WEIGHT EACH (LB) | GRIP RANGE (IN) | NOTE | COLOR CODE | | | |
| | 135 | 5.31 | 1.3 | ¾ TO I | | RED | | | |
| | 160 | 6.30 | 1.6 | ¾ TO 1½ | | GREEN | | | |
| FORGEBOLT | 195 | 7.68 | 1.9 | 1 ¼ TO 2 ¼ | | BLUE | | | |
| A325-PC8.8 | 260 | 10.24 | 2.6 | 2 TO 3½ | SPLICE BOLT | YELLOW | | | |
| | 365 | 14.37 | 3.6 | 3½ TO 5½ | FLANGE JUMP BOLT | ORANGE | | | |
| | 440 | 17.32 | 4.3 | 5½ TO 8½ | FLANGE JUMP BOLT | BLACK | | | |
| DTI NOTE | EACH GROUP A, | OUP A, A325/PC8.8, FORGEBOLT ASSEMBLY MUST HAVE A "SQUIRTER" DTI THAT IS COMPATIBLE WITH M20-PC8.8 BOLT. | | | OMPATIBLE WITH | 1 | | | |

BOLT HOLE NOTES:

- I. ALL SHOP DRILLED HOLES MUST BE NOMINAL 30MM Ø. THE MAX, SHOP DRILLED HOLE Ø IS I \mathcal{Y}_{c} "
- 2. ALL FIELD DRILLED HOLES MUST BE NOMINAL 30MM Ø. THE MAX. FIELD DRILLED HOLE Ø 15 30MM.

FORGEBOLT™ INSTALLATION:

- I. FOLLOW ALL MANUFACTURER/DISTRIBUTER RECOMMENDATIONS FOR INSTALLATION, TIGHTENING AND INSPECTION.
- 2. FIELD DRILL HOLES 30MM Ø.
- 3. SELECT CORRECT BOLT SIZE FOR INSTALLATION GRIP, SEE CONSTRUCTION PLANS.
- 4. INSERT BOLT ASSEMBLY THROUGH HOLES IN SHAFT REINFORCING PLATES AND SEAT THE HARDENED WASHER WI FLUSH AGAINST OUTSIDE OF PLATE.
- 5. HAND TIGHTEN NUT TO FINGER TIGHT.
- 6. TIGHTEN NUT TO PRETENSIONED CONDITION AND UNTIL DTI SHOWS PROPER INDICATION.
- 7. PROPERLY DOCUMENT AND INSPECT BOLT TIGHTENING.

NOTES

- I. ALL STRUCTURAL BOLTS MUST BE INSTALLED AND TIGHTENED TO THE PRETENSIONED CONDITION ACCORDING TO THE REQUIREMENTS OF THE RCSC "SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENTGH BOLTS", DEC. 31, 2009.
- 2. ALL STRUCTURAL BOLTS MUST BE INSPECTED ACCORDING TO THE REQUIREMENTS OF THE AISC "SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENTGH BOLTS", DEC. 31, 2009.

PRECISION TOWER PRODUCTS: PH: (888)-926-4857 EMAIL: INFO@PRECISIONTOWERPRODUCTS.COM WEB: WWW.PRECISIONTOWERPRODUCTS.COM

CONTAINS PROPRIETARY INFORMATION PATENT PENDING

© COPYRIGHT 2013 TO 2015 BY PTP, ALL RIGHTS RESERVED.



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592



I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Date: 10/26/2017

I IO/26/17 REVISED RF AND STRUCTURAL DETAILS

MARK DATE DESCRIPTION

PHASE FINAL

DATE | 08/10/2017

UNIONVILLE / POLICE DEPARTMENT CT33XC534-B

PROJECT INFORMATION:
3 | 9-32 | NEW BRITAIN AVENUE
FARMINGTON, CT 06032

SHEET TITLE:


STRUCTURAL DETAILS

SCALE: NONE

HARTFORD COUNTY

REMEET 23009
NUMBER S-5

INSTALLED FORGEBOLT™ ASSEMBLY DETAIL SCALE: NONE



| - | INTERIOR SIDE OF POLE SHAFT | EXTERIOR SIDE , OF POLE SHAFT | | SHIM PLATE AS REQUIRED, SEE NOTE 4 REINFORCING SPLICE PLATE |
|---|--------------------------------|----------------------------------|---|---|
| SHAFT REINFORCEMENT PLATE - POLE SHAFT WALL - | | | | SHOP DRILLED HOLE IN SHAFT REINFORCING ELEMENT, HOT DIP GALVANIZED PER ASTM A I 23. FIELD COAT WITH COLD GALVANIZING COMPOUND AFTER FIELD DRILLING. HOLE DIAMETER NOM. 30MM, I $\frac{3}{8}$ " MAX. |
| FIELD DRILLED HOLE IN SHAFT WALL, ——COAT WITH APPROVED COLD GALVANIZING COMPOUND, NOM. 30MM, I $^3\!\!/_6$ " MAX. | | | | HIGH TENSILE STEEL COIL SPRING |
| 4490M | | | | |
| NEXGEN2™ M2O BOLT HEAD, 29MM O.D. | | | | DOUBLE HEX SPLINED END OF BOLT FOR NEXTGEN2™ INSTALLATION TOOL. AFTER BOLT IS FULLY TENSIONED AND TIP IS SHEARED OFF. THE BOLT END SHOULD BE COATED WITH APPROVED COLD GALVANIZING COMPOUND. |
| NEXGEN2™ SPLIT WASHER SHEAR SLEEVE, ASTM A519 GRADE 4140 (Fu = 120 KSI MIN.) | | OUTERMO |) \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | NEXGEN2 [™] M20 TENSION CONTROLLED BOLT, ASTM A490M (Fu = 150 KSI MIN.). FIELD DETERMINE LENGTH REQUIRED. |
| SIZE: 1.143" O.D. x 0.800" I.D. | - | SHEAR PL GRIP | | NEXGEN2™ NUT, PRE LUBRICATED NEXGEN2™ WASHER |

NEXGEN2™ BOLT DETAILS

| PART NUMBER | BOLT LENGTH | SLEEVE LENGTH (INCH) | MIN. GRIP RANGE (INCH) | MAX. GRIP RANGE (INCH) |
|-------------|-------------|-------------------------|---------------------------|---------------------------|
| M20x36 | M20x95 | , Ne | 15√6 | 1 7/s |
| M20x48 | M20x95 | ા ૐ | 1 ¾e | ⊥ % |
| M20x57 | M20x95 | I % | 1 % | 2 ½ 4 |
| M20x68 | M20x135 | 2 | 2 1/4 | 2 1 X 6 |
| M20x96 | M20x135 | 2 % 6 | 2 1 X 6 | 3 ¾ |
| M20x127 | M20x165 | 3 | 3 ¾ | 5 |
| M20x212 | M20x250 | 4 | 5 | 8 % 6 |

NOTES:

- I. ALL SHOP DRILLED HOLES MUST BE NOMINAL 30MM Ø. THE MAX. SHOP DRILLED HOLE Ø 15 1 $rac{2}{3}$ G".
- 2. ALL FIELD DRILLED HOLES MUST BE NOMINAL 30MM Ø. THE MAX. FIELD DRILLED HOLE Ø 15 30MM.
- 3. THE NEXTGEN2™ SHALL BE MAGNI 363 COATED PER ASTM F2833 AS APPROPRIATE.
- 4. INSTALL PER MANUFACTURER'S INSTRUCTIONS.

5. SHIMS FOR MONOPOLE REINFORCEMENT MEMBER SHALL BE REQUIRED WHERE GAPS BETWEEN THE POLE SHAFT AND REINFORCING MEMBER EXIST AT FASTENER LOCATIONS. FOR INTERMEDIATE CONNECTIONS, THE MINIMUM SHIM LENGTH AND WIDTH SHALL BE THE WIDTH OF THE REINFORCING MEMBER. FOR TERMINATING CONNECTIONS, A CONTINUOUS SHIM PLATE (PREFERRED) OR EQUIVALENT INDIVIDUAL SHIM PLATES THE WIDTH OF THE REINFORCING MEMBER MAY BE USED. ADJACENT SHIM PLATE THICKNESS MAY TAPER IN INCREMENTS OF $N_{\rm G}$ and shall be no less than $N_{\rm G}$. Stacking of SHIMS IS PERMITTED. SHIMS GRATER THAN $N_{\rm G}$ in THICKNESS LOCATED WITHIN THE TERMINATION LENGTH OF THE SHAFT REINFORCEMENT PLATE.

INSPECTION NOTES AND PROCEDURES:

- I. REVIEW STRUCTURAL DESIGN DETAILS
- 2. VISUALLY INSPECT SHEARED BOLT ENDS TO ENSURE CORRECT TENSION WAS ACHIEVED.
- 3. VERIPY BOLT ENDS ARE SUFFICIENTLY COATED WITH APPROVED COLD GALVANIZED COMPOUNDS.

MANUFACTURER CONTACT:

ALLFASTENERS

ADDRESS:

15401 COMMERCE PARK DRIVE BROOKPARK, OHIO, USA 44142

PH: (440)-232-6060 WEB: WWW.ALLFASTENERS.COM



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251




855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

ertification \$ Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of <u>Connecticut</u>.



January Return 10/26/2017
Signature: Date:

I IO/26/17 REVISED RF AND STRUCTURAL DETAILS
MARK DATE DESCRIPTION

PHASE FINAL

DATE 08/10/2017

PROJECT TITLE

UNIONVILLE / POLICE
DEPARTMENT
CT33XC534-B

319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

SHEET TITL


STRUCTURAL DETAILS


SCALE: NONE

PROJECT 23009
SHEET NUMBER S-6

BOLT HOLE NOTES:

- I. ALL SHOP DRILLED HOLES MUST BE NOMINAL 30MM Ø. THE MAX, SHOP DRILLED HOLE Ø IS I $\frac{3}{2}$ 6".
- 2. ALL FIELD DRILLED HOLES MUST BE NOMINAL 30MM \varnothing . THE MAX. FIELD DRILLED HOLE \varnothing 1S 30MM.





ANTENNA GROUNDING DETAIL

GROUNDING NOTES:

- I. CONTRACTOR TO ENSURE PROPER SEQUENCING OF GROUNDING AND UNDERGROUND CONDUIT INSTALLATION TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM AND/OR DAMAGE TO THE CONDUIT.
- 2. ALL EXTERIOR GROUND CONDUCTORS SHALL BE #2 AWG SOLID TINNED COPPER UNLESS NOTED OTHERWISE.

 3. ALL GROUND CONNECTIONS BELOW GRADE SHALL BE EXOTHERMIC (CADWELD).
- 4. ALL GROUND CONNECTIONS ABOVE GRADE AND/OR INTERIOR SHALL BE COMPRESSION TYPE, TWO-HOLE LUGS OR DOUBLE-CRIMP "C" TAPS.

 5. CONTACT AREAS WHERE CONNECTIONS ARE MADE SHALL BE PREPARED TO A BARE.
- BRIGHT FINISH AND COATED WITH AN ANTI-OXIDATION MATERIAL BEFORE CONNECTIONS ARE MADE. 6. MAXIMUM RESISTANCE OF THE COMPLETED GROUND SYSTEM SHALL NOT EXCEED 5
- 7. WHERE GROUNDING CONNECTIONS ARE MADE TO PAINTED METAL SURFACES, PAINT SHALL BE REMOVED TO BEAR METAL TO ENSURE PROPER CONTACT AND
- 8. GROUND DEPTH SHALL BE 30" MINIMUM BELOW FINISHED GRADE, OR 6" BELOW FROST LINE, WHICHEVER IS GREATER.

| LEGEND: | | |
|---------------|-----------------------|--|
| | EXISTING GROUND CABLE | |
| | PROPOSED GROUND CABLE | |
| A | MECHANICAL CONNECTION | |
| | EXOTHERMIC CONNECTION | |
| — E — E — E — | PROPOSED ELECTRIC | |



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

ertification # Seal:

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.



0/26/17 REVISED RF AND STRUCTURAL DETAILS DATE DESCRIPTION DATE 08/10/2017

FINAL


UNIONVILLE / POLICE DEPARTMENT CT33XC534-B


319-321 NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

EQUIPMENT UTILITY \$ GROUNDING PLAN

SCALE: NONE

23009 SHEET E- 1






NOTES:
I. APPLY NO-OX TO LUG AND GROUND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.

2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED

GROUNDING CONDUCTOR INSTALLATION



TWO-HOLE LUG

SCALE: NTS



6580 SPRINT PARKWAY OVERLAND PARK, KANSAS 66251



855 Community Drive, Sauk City, WI 53583 Phone: 608-643-4100 Fax: 608-643-7999 www.Ramaker.com

Charles Cherundolo Consulting, Inc.

713 Clover Lane, Moscow, PA 18444 Phone: 570-840-5084 Fax: 570-842-5592

hereby certify that this plan, specification, or report was prepare by me or under my direct supervision and that I am a duly Licensec Professional Engineer under the laws of the State of <u>Connecticut</u>.



0/26/17 REVISED RF AND STRUCTURAL DETAILS DATE 08/10/2017

UNIONVILLE / POLICE

DEPARTMENT CT33XC534-B

PROJECT INFORMATION:
3 | 9-32 | NEW BRITAIN AVENUE FARMINGTON, CT 06032 HARTFORD COUNTY

GROUNDING DETAILS

SCALE: NONE

23009 E-2 SHEET

