



Filed by: Kri Pelletier, Property Specialist - SBA Communications
134 Flanders Rd., Suite 125, Westborough, MA 01581
508.251.0720 x 3804 - kpelletier@sbsite.com

December 12, 2018

Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

Notice of Exempt Modification
58A Montano Road, Glastonbury, CT 06033
41 41 58 Latitude / -72 33 50.4 Longitude
Sprint #: CT52XC103_DO Macro Upgrade

Dear Ms. Bachman:

Sprint currently maintains (3) panel antennas and (1) dish antenna at the 110-foot level of the existing 119' Monopole Tower at 58A Montano Road in Glastonbury, CT. The tower is owned by SBA 2012 TC Assets, LLC. The property is owned by Rose Marie Shaw. Sprint now intends to replace (3) existing panel antennas with (3) newer technology panel antennas at the 110-foot level of the tower. Sprint's proposed full scope of work is as follows:

Remove:

- (3) ALU 1900 MHz RRUs
- (6) ALU 800 MHz RRUs
- (3) ALU TD-RRH8x20-25 RRUs
- (1) Junction box on sector frame

Remove and Replace:

- Remove: (3) KMW ETCR 654L12H6 Panel Antennas
 - Replace with: (3) Nokia AAHC Panel Antennas
- Remove: (4) 1-1/4" fiber
 - Replace with: (3) 1.619" hybrid

At ground level – no change to existing lease area or compound (all equipment on existing pad):

- Remove: (1) Clearwire equipment cabinet
 - Replace with: (1) Sprint equipment cabinet
- Remove: (1) Clearwire GPS
 - Replace with: (1) Sprint GPS

Install:

- (1) PPC Cabinet on H-Frame
- (1) Battery Plinth Cabinet



Existing Equipment to Remain (Including entitlements):

- (3) standoff /dual sector mounts
- (2) ½" lines
- (2) Andrew VHLP2 18 Dish Antennas / (1) is actual – (1) is entitlement only

This facility was approved by Decision and Order of the Council on September 11, 2008. The tower was to be constructed as a monopole not to exceed a height of 120 feet above ground level and designed and constructed to include a yield point at the height of 82 feet above ground level. A D&M Plan was to be provided. A recalculated report of electromagnetic radio frequency report was to be submitted to the Council for changes in power density and space was to be provided on the tower for public/private entities and to the Town for public safety services. No further restrictions were set forth. This modification complies with all aforementioned condition(s).

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16.50j-72(b)(2). In accordance with R.C.S.A. § 16.50j-73, a copy of this letter is being sent to the Town of Glastonbury's Town Manager, Richard J. Johnson, and Director of Land Use & Planning Services, Khara Dodds, as well as to the property owner, Rose Marie Shaw. (Separate notice is not being sent to tower owner, as it belongs to SBA.)

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. §16.50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modification will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modification will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-referenced telecommunication facility constitute an exempt modifications under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

Kri Pelletier

Property Specialist / SBA COMMUNICATIONS CORPORATION

134 Flanders Rd., Suite 125

Westborough, MA 01581

508.251.0720 x3804 + T / 508.366.2610 + F / kpelletier@sbsite.com

Attachments

cc: Richard J. Johnson, Town Manager / with attachments

Glastonbury Town Hall, 2155 Main Street, Glastonbury, CT 06033

Khara Dodds, Director of Land Use & Planning Services / with attachments

Glastonbury Town Hall, 2155 Main Street, Glastonbury, CT 06033

Rose Marie Shaw / with attachments

58 Montano Road, Glastonbury, CT 06033



POWER DENSITY

SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Nokia MAA AAHC	Make / Model:	Nokia MAA AAHC	Make / Model:	Nokia MAA AAHC
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd
Height (AGL):	110 feet	Height (AGL):	110 feet	Height (AGL):	110 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	5,118.23	ERP (W):	5,118.23	ERP (W):	5,118.23
Antenna A2 MPE%	1.70 %	Antenna B2 MPE%	1.70 %	Antenna C2 MPE%	1.70 %

Microwave Backhaul Data								
Antenna Type:	Gain (dBd)	Height (feet AGL):	Frequency Bands	Channel Count	Total TX Power(W)	ERP (W)	MPE %	Sector
Andrew VHLP2-18	36.85 dBd	110	18 GHz	1	1	4,841.72	0.16	C

Site Composite MPE%	
Carrier	MPE%
SPRINT – Sector C	1.86 %
T-Mobile	3.27 %
Clearwire	0.17 %
AT&T	3.62 %
Verizon Wireless	3.94 %
Site Total MPE %:	12.86 %

SPRINT Sector A Total:	1.70 %
SPRINT Sector B Total:	1.70 %
SPRINT Sector C Total:	1.86 %
Site Total:	12.86 %

SPRINT_ Frequency Band / Technology (Sector C)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 2500 MHz (BRS) LTE	8	639.78	110	17.01	2500 MHz (BRS)	1000	1.70%
Sprint 18 GHz Microwave	1	4,841.72	110	1.61	18 GHz	1000	0.16%
Total:							1.86%

SPRINT Sector	Power Density Value (%)
Sector A:	1.70 %
Sector B:	1.70 %
Sector C:	1.86 %
SPRINT Maximum MPE % (Sector C):	1.86 %
Site Total:	12.86 %
Site Compliance Status:	COMPLIANT

ORIGIN ID:BBEA (508) 251-0720
KRIEGLER
964 COMMUNICATIONS CORPORATION
34 FLANDERS RD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US


SHIP DATE: 12DEC18
ACTWGT: 1.00 LB
CAD: 105843304INET4040

BILL SENDER

TO RICHARD J JOHNSON, TOWN MANAGER
GLASTONBURY TOWN HALL
2155 MAIN STREET

GLASTONBURY CT 06033

(508) 251-0720 X 3808 REF: 10-5692009-6089
NO. DEPT.
PO.



J18218081501uv

552J2/E4AF/DCA5

TRK# 7739 5071 7351
0201

THU - 13 DEC 10:30A
PRIORITY OVERNIGHT

EB BDLA 06033
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID: 88FEA (508) 251-0720
KRIPEL LETTERS
SBA COMMUNICATIONS CORPORATION
34 FLANDERS RD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US


SHIP DATE: 12DEC18
ACTWGTY: 1.00 LB
CAD: 105843304MNET4040
BILL SENDER

TO KHARA DOBBS, DIR OF LAND USE & PLAN
GLASTONBURY TOWN HALL
2155 MAIN STREET

GLASTONBURY CT 06033

(508) 251-0720 X 3808 REF: 105692009-6089
PO: DEPT:

552J2IE4AFIDCA5



TRK# 7739 5074 6196
0201

THU - 13 DEC 10:30A
PRIORITY OVERNIGHT

EB BDLA 06033
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID: 88FA (508) 251-0720
KRIPEL LETTERS
SBA COMMUNICATIONS CORPORATION
34 FLANDERS RD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US

SHIP DATE: 12DEC18
ACTWGT: 1.00 LB
CAD: 105843304NET4040
BILL SENDER

TO ROSE MARIE SHAW
58 MONTANO RD.

GLASTONBURY CT 06033
(508) 251-0720 X 3808 REF: 10-56-92009-6089
PO. DEPT.

552J2JE4AFIDCA5



J182118081501uv

TRK# 7739 5077 6740
THU - 13 DEC 10:30A
PRIORITY OVERNIGHT

EBBDLA 06033
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.



Owner of Record


GIS ID: 44800058
Owner: SHAW ROSE MARIE
Co-Owner:
Address: 58 MONTANO RD
City, State ZIP: GLASTONBURY, CT 06033-3324

Account Number: 44800058

Property Address: 58 MONTANO RD

Parcel Information

Map/Street/Lot G7 / 4480 / S0021 **Property ID:** 8132
Developer Lot ID: **Water:** Well
Parcel Acreage: 1.30 **Sewer:** Sewer Nbrhd
Zoning Code: AA **Census:** 5204



Property highlighted in blue

Valuation Summary

Item	Appraised Value	Assessed Value
Buildings	60300	42200
Land	402500	281800
Appurtenances	5800	4100
Total	468600	328100

Owner of Record

Owner of Record	Deed / Page	Sale Date	Sale Price
SHAW ROSE MARIE	1946/0211	10/07/2003	0
SHAW WILLIAM R+ROSE MARIE	0147/0396	07/01/1966	4500




Building Information

Building ID 8132

Year Constructed : 1931
Building Type : Residential
Style : Cape
Occupancy : Single Family
Stories : 1.5
Building Zone : AA
Roof Type : Gable
Roof Material : Asphalt Shingl
Est. Gross S.F. : 2458
Est. Living S.F. : 1278

Number of Rooms : 7
Number of Bedrooms : 03
Number of Bathrooms : 1
Number of Half-Baths : 0
Exterior Wall : Wood Shingles
Interior Wall : Plaster
Interior Floor : Hardwood
Interior Floor #2 : No entry
Air Conditioning Type : None
Heat Type : Forced Air
Fuel Type : Oil



Subarea Type	Est. Gross S.F.	Est. Living S.F.	Outbuilding Type	Est. Gross S.F.	Comments
First Floor	758	758	Garage	576.00	
Porch, Enclosed	56	0	Shed-Wood/Comp	120.00	
Porch, Open	48	0	Shed-Wood/Comp	192.00	
Slab	108	0			
Three Quarter Story	650	520			
Basement	650	0			
Wood Deck	188	0			



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT52XC103

Cutter Lane
58A Montano Road
Glastonbury, CT 06033

November 28, 2018

EBI Project Number: 6218007225

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	12.86 %



November 28, 2018

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT52XC103 – Cutter Lane**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **58A Montano Road, Glastonbury, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 2500 MHz (BRS) and 18 GHz microwave bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **58A Montano Road, Glastonbury, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 1 microwave channel (18 GHz) was considered for Sector C of the proposed installation. This channel has a transmit power of 1 Watt.
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.



- 4) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 5) The antennas used in this modeling are the **Nokia MAA AAHC** for transmission in the 2500 MHz (BRS) frequency bands as well as the **Andrew VHLP2-18** parabolic microwave dish for transmission in the 18 GHz microwave band. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antenna mounting height centerlines of the proposed panel antennas and microwave dish are **110 feet** above ground level (AGL) for **Sector A**, **110 feet** above ground level (AGL) for **Sector B** and **110 feet** above ground level (AGL) for Sector C.
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Nokia MAA AAHC	Make / Model:	Nokia MAA AAHC	Make / Model:	Nokia MAA AAHC
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd
Height (AGL):	110 feet	Height (AGL):	110 feet	Height (AGL):	110 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	5,118.23	ERP (W):	5,118.23	ERP (W):	5,118.23
Antenna A2 MPE%	1.70 %	Antenna B2 MPE%	1.70 %	Antenna C2 MPE%	1.70 %

Microwave Backhaul Data

Antenna Type:	Gain (dBd)	Height (feet AGL):	Frequency Bands	Channel Count	Total TX Power(W)	ERP (W)	MPE %	Sector
Andrew VHL2-18	36.85 dBd	110	18 GHz	1	1	4,841.72	0.16	C

Site Composite MPE%	
Carrier	MPE%
SPRINT – Sector C	1.86 %
T-Mobile	3.27 %
Clearwire	0.17 %
AT&T	3.62 %
Verizon Wireless	3.94 %
Site Total MPE %:	12.86 %

SPRINT Sector A Total:	1.70 %
SPRINT Sector B Total:	1.70 %
SPRINT Sector C Total:	1.86 %
Site Total:	12.86 %

SPRINT _ Frequency Band / Technology (Sector C)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 2500 MHz (BRS) LTE	8	639.78	110	17.01	2500 MHz (BRS)	1000	1.70%
Sprint 18 GHz Microwave	1	4,841.72	110	1.61	18 GHz	1000	0.16%
Total:							1.86%



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	1.70 %
Sector B:	1.70 %
Sector C:	1.86 %
SPRINT Maximum MPE % (Sector C):	1.86 %
Site Total:	12.86 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **12.86 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Tower Engineering Solutions

Phone (972) 483-0607, Fax (972) 975-9615
1320 Greenway Drive, Suite 600, Irving, Texas 75038

Structural Analysis Report

Existing 119 ft SABRE Monopole

Customer Name: SBA Communications Corp

Customer Site Number: CT13555-S

Customer Site Name: Montano

Carrier Name: Sprint Nextel

Carrier Site ID / Name: CT52XC103 / Cutter Lane

Site Location: 58A Montano Road

Glastonbury, Connecticut

Hartford County

Latitude: 41.699444

Longitude: -72.564000

Analysis Result:

Max Structural Usage: 35.2% [Pass]

Max Foundation Usage: 44.0% [Pass]

Additional Usage Caused by New Mount/Mount Modification: N/A



Report Prepared By: Tawfeeq Alajaj

Introduction

The purpose of this report is to summarize the analysis results on the 119 ft SABRE Monopole to support the proposed antennas and transmission lines in addition to those currently installed. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

Sources of Information

Tower Drawings	Tower Drawing prepared by Sabre, Job #09-11137 dated 11/19/08
Foundation Drawing	Foundation Drawing prepared by Sabre, Job #09-11137 dated 11/19/08
Geotechnical Report	Geotechnical Report prepared by TES, Project #082695.01 dated 10/27/08
Modification Drawings	N/A

Analysis Criteria

The rigorous analysis was performed in accordance with the requirements and stipulations of the ANSI/TIA/EIA 222-G. In accordance with this standard, the structure was analyzed using **TESPoles**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

Wind Speed Used in the Analysis:	Ultimate Design Wind Speed $V_{ult} = 125.0$ mph (3-Sec. Gust)/ Nominal Design Wind Speed $V_{asd} = 97.0$ mph (3-Sec. Gust)
Wind Speed with Ice:	50 mph (3-Sec. Gust) with 1" radial ice concurrent
Operational Wind Speed:	60 mph + 0" Radial ice
Standard/Codes:	ANSI/TIA/EIA 222-G / 2012 IBC / 2016 Connecticut State Building Code
Exposure Category:	B
Structure Class:	II
Topographic Category:	1
Crest Height:	0 ft
Seismic Parameters:	$S_S = 0.18$, $S_1 = 0.063$

This structural analysis is based upon the tower being classified as a Structure Class II; however, if a different classification is required subsequent to the date hereof, the tower classification will be changed to meet such requirement and a new structural analysis will be run.

Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	117.0	3	Ericsson - S11B12 - RRU	Platform w/ Hand Rail	(12) 1 5/8" (1) 1 5/8" Fiber	T-Mobile
2		3	Commscope - LNX-6515DS-A1M - Panel			
3		3	Ericsson - AIR 21 B2A/B4P - Panel			
4		3	Ericsson - AIR 21 B4A/B2P - Panel			
5		3	Ericsson - KRY 112 144/1 - TMA			
6	110.0	3	KMW ETCR-654L12H6 - Panel	(3) Standoff Mounts Ring Mount @ (+/-) 3 ft	(4) 1-1/4" Fiber (2) 1/2"	Sprint Nextel
7		2	Andrew - VHLP2-18 - Dish			
8		3	ALU 1900 MHz RRU			
9		6	ALU 800 MHz RRU			
10	100.0	3	ALU TD-RRH8x20-25 RRU	Platform w/ Hand Rail and kickers	(2) 1/2" Fiber (8) 3/4" DC (3) 3/8" RET	AT&T
11		3	ALU IBC700-1 – Filter			
12		12	CCI - HPA-65R-BUU-H8 - Panel			
13		12	Ericsson - RRU-11			
14		6	Ericsson - RRU-12			
15		6	Ericsson - RRUS-A2 Module			
16		3	Ericsson - RRU-32			
17	4	Raycap DC6-48-60-18-8F				
18	90.0	6	Andrew - LNX-6514DS-A1M - Panel	Low Profile Platform	(2) 1 5/8" Hybrid Cable	Verizon
19		6	Andrew - HBXX-6517DS-A2M - Panel			
20		3	ALU RRH2X60-AWS - RRH			
21		3	ALU RRH2x60-PCS - RRH			
22		3	ALU B13 RRH4x30 - RRH			
23		2	RFS DB-T1-6Z-8AB-0Z			

Proposed Carrier's Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier's final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
6	110.0	2	Andrew - VHLP2-18 - Dish	(3) dual sector mounts	(2) 1/2" (3) 1.619" Hybrid	Sprint Nextel
7		3	Nokia - AAHC - Panel			

All transmission lines are considered running inside of the pole shafts.

Analysis Results

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

	Pole shafts	Anchor Bolts	Base Plate	Flange Bolts	Flange Plate
Max. Usage:	35.2%	34.5%	26.8%	20.1%	10.2%
Pass/Fail	Pass	Pass	Pass	Pass	Pass

Foundations

	Moment (Kip-Ft)	Shear (Kips)	Axial (Kips)
Analysis Reactions	2265.8	25.8	79.9

The foundation has been investigated using the supplied documents and soils report and was found adequate. Therefore, no modification to the foundation will be required.

Operational Condition (Rigidity):

The maximum twist and sway of the microwave dishes under the operational wind speed as specified in the Analysis Criteria are listed in the table below:

Elevation (ft)	Antenna / Dish	Carrier	Twist (deg)	Sway (deg)
110.0	Andrew - VHLP2-18 - Dish	Sprint Nextel	0.001	0.403

It is recommended that the carriers review the twist and sway values of the microwave dishes.

Conclusions

Based on the analysis results, the existing structure and its foundation were found to be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the ANSI/TIA/EIA 222-G Standard under the design basic wind speed as specified in the Analysis Criteria.

Standard Conditions

1. This analysis was performed based on the information supplied to **(TES) Tower Engineering Solutions, LLC**. Verification of the information provided was not included in the Scope of Work for **TES**. The accuracy of the analysis is dependent on the accuracy of the information provided.
2. The analysis is based on the presumption that the tower members and components along with any existing reinforcement items have been correctly and properly designed, manufactured, installed and maintained.
3. All the existing structural members were assumed to be in good condition with no physical damage or deterioration associated with corrosion.
4. An initial tension of 10% of the break strength on all the existing guy wires was assumed in all the structural analyses of guyed towers unless different values were provided by the client. **TES** cannot take responsibility for the deviations in the analysis results because of differences in the initial tension forces of the existing guy wires.
5. Secondary component or connection secondary components, welds and bolts are assumed to be able to carry their intended original design loads. **TES** cannot take responsibility for verification of the adequacy on the connections, bolts and welds present in the structure.
6. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of **TES**. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed and/or ice loads are different from the minimum values recommended by the EIA/TIA-222 standard or other codes, **TES** should be notified in writing and the applicable minimum values provided by the client.
7. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. **TES** has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, **TES** should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
8. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
9. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

Usage Diagram - Max Ratio 35.20% at 0.0ft

Structure: CT13555-S-SBA
Site Name: Montano
Height: 119.00 (ft)
Base Elev: 0.000 (ft)

Code: EIA/TIA-222-G
Exposure: B
Gh: 1.1


8/17/2018



Page: 1


Dead Load Factor: 1.20
Wind Load Factor: 1.60

Load Case : 1.2D + 1.6W 97 mph Wind



Iterations: 18

Copyright © 2018 by Tower Engineering Solutions, LLC. All rights reserved.



Structure: CT13555-S-SBA

Type: Tapered
Site Name: Montano
Height: 119.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 18 Sided
Taper: 0.26403

8/17/2018

Page: 2



Shaft Properties

Seq	Length (ft)	Top (in)	Bottom (in)	Thick (in)	Joint Type	Taper	Grade (ksi)
1	53.00	44.82	58.81	0.438		0.26403	65
2	34.00	38.17	47.15	0.375	Slip	0.26403	65
3	38.00	28.14	38.17	0.313	Butt	0.26403	65

Discrete Appurtenances

Attach Elev (ft)	Force Elev (ft)	Qty	Description	Carrier
119.00	119.00	1	6' Lightning rod	
117.00	117.00	3	AIR 21 B2A B4P	T-Mobile
117.00	117.00	3	AIR 21 B4A B2P	T-Mobile
117.00	117.00	3	KRY 112 144/1	T-Mobile
117.00	117.00	1	Platform w/ Hand Rail	T-Mobile
117.00	117.00	3	S11B12	T-Mobile
117.00	117.00	3	LNx-6515DS-A1M	T-Mobile
113.00	113.00	1	3 ft Standoff	Sprint Nextel
110.00	110.00	3	AAHC	Sprint Nextel
110.00	110.00	3	dual sector mounts	Sprint Nextel
110.00	110.00	2	VHLP2-18	Sprint Nextel
107.00	107.00	1	Ring Mount	Sprint Nextel
100.00	100.00	12	HPA-65R-BUU-H8	AT&T
100.00	100.00	12	RRU-11	AT&T
100.00	100.00	6	RRU-12	AT&T
100.00	100.00	6	RRUS-A2	AT&T
100.00	100.00	3	RRU-32	AT&T
100.00	100.00	4	DC6-48-60-18-8F	AT&T
100.00	100.00	1	Platform w/ Hand Rail	AT&T
100.00	100.00	3	IBC700-1	AT&T
90.00	90.00	3	RRH2X60-AWS	Verizon
90.00	90.00	3	RRH2x60-PCS	Verizon
90.00	90.00	3	B13 RRH4x30	Verizon
90.00	90.00	2	DB-T1-6Z-8AB-0Z	Verizon
90.00	90.00	1	Low Profile Platform	Verizon
90.00	90.00	6	LNx-6514DS-A1M	Verizon
90.00	90.00	6	HBXX-6517DS-A2M	Verizon


Linear Appurtenances

Elev From (ft)	Elev To (ft)	Placement	Description	Carrier
0.00	117.00	Inside	1 5/8" Coax	T-Mobile
0.00	117.00	Inside	1 5/8" Fiber	T-Mobile
0.00	110.00	Inside	1.619" Hybrid	Sprint Nextel
0.00	110.00	Inside	1/2" Coax	Sprint Nextel
0.00	100.00	Inside	1/2" Fiber	AT&T
0.00	100.00	Inside	3/4" DC	AT&T
0.00	100.00	Inside	3/8" RET	AT&T
0.00	90.00	Inside	1 5/8" Hybrid Cable	Verizon

Anchor Bolts

Qty	Specifications	Grade (ksi)	Arrangement
20	2.25" 18J	75.0	Cluster

Base Plate



Structure: CT13555-S-SBA

Type: Tapered
Site Name: Montano
Height: 119.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 18 Sided
Taper: 0.26403

8/17/2018

Page: 3



Thickness (in)	Specifications (in)	Grade (ksi)	Geometry
3.2500	66.0	50.0	Clipped

Reactions

Load Case	Moment (FT-Kips)	Shear (Kips)	Axial (Kips)
1.2D + 1.6W 97 mph Wind	2265.8	25.8	44.0
0.9D + 1.6W 97 mph Wind	2255.6	25.8	33.0
1.2D + 1.0Di + 1.0Wi 50 mph Wind	644.3	7.4	79.9
1.2D + 1.0E	172.1	1.8	44.0
0.9D + 1.0E	171.3	1.8	33.0
1.0D + 1.0W 60 mph Wind	540.2	6.2	36.7


Structure: CT13555-S-SBA - Coax Line Placement

Type: Monopole
Site Name: Montano
Height: 119.00 (ft)

8/17/2018



Page: 4



Shaft Properties

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 5

Sec. No.	Shape	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Overlap (in)	Weight (lb)
1	18	53.000	0.4375	65		0.00	12,866
2	18	34.000	0.3750	65	Slip	72.00	5,823
3	18	38.000	0.3125	65	Flange	0.00	4,212
Total Shaft Weight:							22,901

Bottom

Top

Sec. No.	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Taper
1	58.81	0.00	81.05	34893.72	22.29	134.42	44.82	53.00	61.62	15333.6	16.65	102.4	0.264034
2	47.15	47.00	55.67	15389.65	20.76	125.73	38.17	81.00	44.99	8120.67	16.54	101.8	0.264034
3	38.17	81.00	37.55	6800.85	20.13	122.15	28.14	119.00	27.60	2700.33	14.47	90.05	0.264034

Load Summary

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 6

Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
1	119.00	6' Lightning rod	1	6.50	0.38	1.00	53.79	1.797	1.00	0.00	0.00
2	117.00	AIR 21 B2A B4P	3	91.50	6.09	0.83	324.13	7.546	0.83	0.00	0.00
3	117.00	AIR 21 B4A B2P	3	90.30	6.09	0.83	322.93	7.546	0.83	0.00	0.00
4	117.00	KRY 112 144/1	3	11.00	0.41	0.72	25.02	1.028	0.75	0.00	0.00
5	117.00	Platform w/ Hand Rail	1	1600.00	32.00	1.00	4331.08	68.318	1.00	0.00	0.00
6	117.00	S11B12	3	51.00	2.83	0.71	141.53	3.704	0.72	0.00	0.00
7	117.00	LNX-6515DS-A1M	3	50.30	11.47	0.84	351.85	15.719	0.84	0.00	0.00
8	113.00	3 ft Standoff	1	120.00	4.50	1.00	228.57	8.572	1.00	0.00	0.00
9	110.00	AAHC	3	104.00	4.20	0.75	280.52	5.295	0.75	0.00	0.00
10	110.00	dual sector mounts	3	350.00	4.00	1.00	728.99	7.609	1.00	0.00	0.00
11	110.00	VHLP2-18	2	27.00	4.68	1.00	153.50	6.327	1.00	1.00	0.00
12	107.00	Ring Mount	1	350.00	5.00	1.00	664.95	9.499	1.00	0.00	0.00
13	100.00	HPA-65R-BUU-H8	12	60.80	12.98	0.78	450.81	15.083	0.78	0.00	0.00
14	100.00	RRU-11	12	54.00	2.52	0.70	175.56	3.375	0.71	0.00	0.00
15	100.00	RRU-12	6	58.00	2.81	0.70	176.94	3.700	0.71	0.00	0.00
16	100.00	RRUS-A2	6	22.00	1.86	0.61	69.98	3.107	0.63	0.00	0.00
17	100.00	RRU-32	3	77.00	3.87	0.85	231.03	4.349	0.85	0.00	0.00
18	100.00	DC6-48-60-18-8F	4	32.80	1.47	1.00	114.45	2.366	1.00	0.00	0.00
19	100.00	Platform w/ Hand Rail	1	1875.00	43.80	1.00	5025.63	92.735	1.00	0.00	0.00
20	100.00	IBC700-1	3	63.30	1.31	0.91	127.63	2.459	0.91	0.00	0.00
21	90.00	RRH2X60-AWS	3	55.00	3.50	0.77	156.37	4.500	0.78	0.00	0.00
22	90.00	RRH2x60-PCS	3	55.00	1.51	0.78	136.76	2.228	0.79	0.00	0.00
23	90.00	B13 RRH4x30	3	57.20	2.71	0.88	155.50	4.311	0.88	0.00	0.00
24	90.00	DB-T1-6Z-8AB-OZ	2	44.00	4.10	0.91	352.98	5.115	1.00	0.00	0.00
25	90.00	Low Profile Platform	1	1500.00	22.00	1.00	3158.30	44.376	1.00	0.00	0.00
26	90.00	LNX-6514DS-A1M	6	38.80	8.17	0.82	264.46	11.747	0.82	0.00	0.00
27	90.00	HBXX-6517DS-A2M	6	47.00	8.55	0.80	304.22	12.248	0.80	0.00	0.00
Totals:			98	11,263.90			36,289.94				

Linear Appurtenances

Bottom Elev. (ft)	Top Elev. (ft)	Description	Exposed Width	Exposed
0.00	117.00	(12) 1 5/8" Coax	0.00	Inside
0.00	117.00	(1) 1 5/8" Fiber	0.00	Inside
0.00	110.00	(3) 1.619" Hybrid	0.00	Inside
0.00	110.00	(2) 1/2" Coax	0.00	Inside
0.00	100.00	(2) 1/2" Fiber	0.00	Inside
0.00	100.00	(8) 3/4" DC	0.00	Inside
0.00	100.00	(3) 3/8" RET	0.00	Inside
0.00	90.00	(2) 1 5/8" Hybrid Cable	0.00	Inside

Shaft Section Properties

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 7

Increment Length: 5 (ft)

Elev (ft)	Description	Thick (in)	Dia (in)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	Fpy (ksi)	S (in ³)	Weight (lb)
0.00		0.4375	58.810	81.055	34893.7	22.29	134.42	75.2	1168.	0.0
5.00		0.4375	57.490	79.221	32579.4	21.76	131.41	75.8	1116.	1363.5
10.00		0.4375	56.170	77.388	30369.7	21.23	128.39	76.4	1064.	1332.3
15.00		0.4375	54.849	75.555	28262.2	20.70	125.37	77.1	1014.	1301.1
20.00		0.4375	53.529	73.722	26254.6	20.16	122.35	77.7	966.0	1269.9
25.00		0.4375	52.209	71.889	24344.4	19.63	119.34	78.3	918.4	1238.7
30.00		0.4375	50.889	70.056	22529.1	19.10	116.32	78.9	872.0	1207.5
35.00		0.4375	49.569	68.223	20806.4	18.57	113.30	79.6	826.7	1176.3
40.00		0.4375	48.249	66.389	19173.9	18.04	110.28	80.2	782.7	1145.1
45.00		0.4375	46.928	64.556	17629.0	17.50	107.27	80.8	739.9	1113.9
47.00	Bot - Section 2	0.4375	46.400	63.823	17035.1	17.29	106.06	81.1	723.1	436.8
50.00		0.4375	45.608	62.723	16169.5	16.97	104.25	81.4	698.3	1209.4
53.00	Top - Section 1	0.3750	45.566	53.787	13878.3	20.01	121.51	0.0	0.0	1188.6
55.00		0.3750	45.038	53.158	13397.5	19.77	120.10	78.2	585.9	363.9
60.00		0.3750	43.718	51.587	12244.2	19.15	116.58	78.9	551.6	891.1
65.00		0.3750	42.398	50.016	11159.1	18.53	113.06	79.6	518.4	864.3
70.00		0.3750	41.078	48.445	10140.1	17.90	109.54	80.3	486.2	837.6
75.00		0.3750	39.757	46.873	9185.1	17.28	106.02	81.1	455.0	810.9
80.00		0.3750	38.437	45.302	8292.0	16.66	102.50	81.8	424.9	784.1
81.00	Top - Section 2	0.3750	38.173	44.988	8120.7	16.54	101.80	81.9	419.0	153.6
81.00	Bot - Section 3	0.3125	38.173	37.552	6800.8	19.85	122.15	77.7	350.9	
85.00		0.3125	37.117	36.504	6247.4	19.53	118.77	78.4	331.5	504.0
90.00		0.3125	35.797	35.195	5599.0	18.79	114.55	79.3	308.1	609.9
95.00		0.3125	34.477	33.886	4997.0	18.04	110.33	80.2	285.5	587.7
100.00		0.3125	33.157	32.576	4439.8	17.30	106.10	81.1	263.7	565.4
105.00		0.3125	31.836	31.267	3925.7	16.55	101.88	81.9	242.9	543.1
107.00		0.3125	31.308	30.743	3731.7	16.26	100.19	82.3	234.8	211.0
110.00		0.3125	30.516	29.957	3452.9	15.81	97.65	82.5	222.9	309.8
113.00		0.3125	29.724	29.172	3188.3	15.36	95.12	82.5	211.3	301.8
115.00		0.3125	29.196	28.648	3019.6	15.06	93.43	82.5	203.7	196.7
117.00		0.3125	28.668	28.124	2857.0	14.77	91.74	82.5	196.3	193.2
119.00		0.3125	28.140	27.600	2700.3	14.47	90.05	82.5	189.0	189.6
										22901.0

Wind Loading - Shaft


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 8

Load Case: 1.2D + 1.6W 97 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Iterations 18

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.70	16.018	17.62	403.87	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.70	16.018	17.62	394.80	0.650	0.000	5.00	24.603	15.99	450.8	0.0	1636.2
10.00		1.00	0.70	16.018	17.62	385.74	0.650	0.000	5.00	24.044	15.63	440.6	0.0	1598.7
15.00		1.00	0.70	16.018	17.62	376.67	0.650	0.000	5.00	23.486	15.27	430.4	0.0	1561.3
20.00		1.00	0.70	16.018	17.62	367.60	0.650	0.000	5.00	22.927	14.90	420.1	0.0	1523.9
25.00		1.00	0.70	16.018	17.62	358.54	0.650	0.000	5.00	22.369	14.54	409.9	0.0	1486.4
30.00		1.00	0.70	16.031	17.63	349.62	0.650	0.000	5.00	21.810	14.18	400.0	0.0	1449.0
35.00		1.00	0.73	16.753	18.43	348.13	0.650	0.000	5.00	21.252	13.81	407.3	0.0	1411.6
40.00		1.00	0.76	17.405	19.15	345.39	0.650	0.000	5.00	20.693	13.45	412.0	0.0	1374.2
45.00		1.00	0.79	18.000	19.80	341.64	0.650	0.000	5.00	20.134	13.09	414.6	0.0	1336.7
47.00	Bot - Section 2	1.00	0.80	18.225	20.05	339.90	0.650	0.000	2.00	7.897	5.13	164.7	0.0	524.2
50.00		1.00	0.81	18.551	20.41	337.06	0.650	0.000	3.00	11.869	7.71	251.9	0.0	1451.3
53.00	Top - Section 1	1.00	0.82	18.862	20.75	333.98	0.650	0.000	3.00	11.668	7.58	251.8	0.0	1426.3
55.00		1.00	0.83	19.063	20.97	337.41	0.650	0.000	2.00	7.667	4.98	167.2	0.0	436.7
60.00		1.00	0.85	19.543	21.50	331.62	0.650	0.000	5.00	18.776	12.20	419.8	0.0	1069.3
65.00		1.00	0.87	19.995	21.99	325.30	0.650	0.000	5.00	18.218	11.84	416.7	0.0	1037.2
70.00		1.00	0.89	20.422	22.46	318.53	0.650	0.000	5.00	17.659	11.48	412.6	0.0	1005.1
75.00		1.00	0.91	20.829	22.91	311.34	0.650	0.000	5.00	17.100	11.12	407.5	0.0	973.0
80.00		1.00	0.93	21.217	23.34	303.79	0.650	0.000	5.00	16.542	10.75	401.5	0.0	941.0
81.00	Top - Section 2	1.00	0.93	21.292	23.42	302.24	0.650	0.000	1.00	3.241	2.11	79.0	0.0	184.3
85.00		1.00	0.94	21.587	23.75	295.91	0.650	0.000	4.00	12.742	8.28	314.7	0.0	604.8
90.00	Appurtenance(s)	1.00	0.96	21.943	24.14	287.73	0.650	0.000	5.00	15.425	10.03	387.2	0.0	731.9
95.00		1.00	0.97	22.284	24.51	279.26	0.650	0.000	5.00	14.866	9.66	379.0	0.0	705.2
100.00	Appurtenance(s)	1.00	0.99	22.613	24.87	270.54	0.650	0.000	5.00	14.308	9.30	370.1	0.0	678.5
105.00		1.00	1.00	22.931	25.22	261.59	0.650	0.000	5.00	13.749	8.94	360.7	0.0	651.7
107.00	Appurtenance(s)	1.00	1.01	23.055	25.36	257.94	0.650	0.000	2.00	5.343	3.47	140.9	0.0	253.2
110.00	Appurtenance(s)	1.00	1.02	23.238	25.56	252.41	0.650	0.000	3.00	7.847	5.10	208.6	0.0	371.8
113.00	Appurtenance(s)	1.00	1.02	23.417	25.76	246.81	0.650	0.000	3.00	7.646	4.97	204.8	0.0	362.2
115.00		1.00	1.03	23.535	25.89	243.03	0.650	0.000	2.00	4.986	3.24	134.2	0.0	236.1
117.00	Appurtenance(s)	1.00	1.03	23.651	26.02	239.23	0.650	0.000	2.00	4.896	3.18	132.5	0.0	231.8
119.00	Appurtenance(s)	1.00	1.04	23.766	26.14	235.39	0.650	0.000	2.00	4.807	3.12	130.7	0.0	227.5
Totals:								119.00			9,521.7	27,481.1		


Discrete Appurtenance Forces

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Load Case: 1.2D + 1.6W 97 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Iterations 18

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	119.00	6' Lightning rod	1	23.766	26.142	1.00	1.00	0.38	7.80	0.000	0.000	15.89	0.00	0.00
2	117.00	AIR 21 B2A B4P	3	23.651	26.016	0.62	0.75	11.32	329.40	0.000	0.000	471.13	0.00	0.00
3	117.00	LNx-6515DS-A1M	3	23.651	26.016	0.63	0.75	21.58	181.08	0.000	0.000	898.07	0.00	0.00
4	117.00	S11B12	3	23.651	26.016	0.53	0.75	4.50	183.60	0.000	0.000	187.13	0.00	0.00
5	117.00	AIR 21 B4A B2P	3	23.651	26.016	0.62	0.75	11.32	325.08	0.000	0.000	471.13	0.00	0.00
6	117.00	KRY 112 144/1	3	23.651	26.016	0.54	0.75	0.67	39.60	0.000	0.000	27.69	0.00	0.00
7	117.00	Platform w/ Hand Rail	1	23.651	26.016	1.00	1.00	32.00	1920.00	0.000	0.000	1332.02	0.00	0.00
8	113.00	3 ft Standoff	1	23.417	25.759	1.00	1.00	4.50	144.00	0.000	0.000	185.46	0.00	0.00
9	110.00	dual sector mounts	3	23.238	25.561	1.00	1.00	12.00	1260.00	0.000	0.000	490.78	0.00	0.00
10	110.00	VHLP2-18	2	23.238	25.561	1.00	1.00	9.36	64.80	2.291	0.000	382.81	548.16	0.00
11	110.00	AAHC	3	23.238	25.561	0.60	0.80	7.56	374.40	0.000	0.000	309.19	0.00	0.00
12	107.00	Ring Mount	1	23.055	25.360	1.00	1.00	5.00	420.00	0.000	0.000	202.88	0.00	0.00
13	100.00	Platform w/ Hand Rail	1	22.613	24.875	1.00	1.00	43.80	2250.00	0.000	0.000	1743.22	0.00	0.00
14	100.00	DC6-48-60-18-8F	4	22.613	24.875	0.75	0.75	4.41	157.44	0.000	0.000	175.52	0.00	0.00
15	100.00	RRUS-A2	6	22.613	24.875	0.46	0.75	5.12	158.40	0.000	0.000	203.87	0.00	0.00
16	100.00	RRU-12	6	22.613	24.875	0.53	0.75	8.89	417.60	0.000	0.000	353.80	0.00	0.00
17	100.00	RRU-11	12	22.613	24.875	0.53	0.75	15.99	777.60	0.000	0.000	636.37	0.00	0.00
18	100.00	HPA-65R-BUJ-H8	12	22.613	24.875	0.58	0.75	91.00	875.52	0.000	0.000	3621.87	0.00	0.00
19	100.00	IBC700-1	3	22.613	24.875	0.68	0.75	2.68	227.88	0.000	0.000	106.63	0.00	0.00
20	100.00	RRU-32	3	22.613	24.875	0.64	0.75	7.38	277.20	0.000	0.000	293.88	0.00	0.00
21	90.00	RRH2x60-AWS	3	21.943	24.137	0.62	0.80	6.48	198.00	0.000	0.000	250.11	0.00	0.00
22	90.00	LNx-6514DS-A1M	6	21.943	24.137	0.66	0.80	32.20	279.36	0.000	0.000	1243.40	0.00	0.00
23	90.00	HBXX-6517DS-A2M	6	21.943	24.137	0.64	0.80	32.83	338.40	0.000	0.000	1267.95	0.00	0.00
24	90.00	Low Profile Platform	1	21.943	24.137	1.00	1.00	22.00	1800.00	0.000	0.000	849.63	0.00	0.00
25	90.00	RRH2x60-PCS	3	21.943	24.137	0.63	0.80	2.84	198.00	0.000	0.000	109.59	0.00	0.00
26	90.00	B13 RRH4x30	3	21.943	24.137	0.70	0.80	5.69	205.92	0.000	0.000	219.78	0.00	0.00
27	90.00	DB-T1-6Z-8AB-0Z	2	21.943	24.137	0.73	0.80	5.97	105.60	0.000	0.000	230.54	0.00	0.00

Totals: **13,516.68** **16,280.34**

Total Applied Force Summary


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 10

Load Case: 1.2D + 1.6W 97 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Iterations 18

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		450.83	1772.95	0.00	0.00
10.00		440.60	1735.52	0.00	0.00
15.00		430.36	1698.10	0.00	0.00
20.00		420.13	1660.67	0.00	0.00
25.00		409.89	1623.24	0.00	0.00
30.00		400.00	1585.82	0.00	0.00
35.00		407.30	1548.39	0.00	0.00
40.00		412.02	1510.96	0.00	0.00
45.00		414.62	1473.54	0.00	0.00
47.00		164.66	578.93	0.00	0.00
50.00		251.88	1533.39	0.00	0.00
53.00		251.77	1508.36	0.00	0.00
55.00		167.20	491.41	0.00	0.00
60.00		419.77	1206.08	0.00	0.00
65.00		416.70	1174.00	0.00	0.00
70.00		412.57	1141.92	0.00	0.00
75.00		407.48	1109.84	0.00	0.00
80.00		401.50	1077.76	0.00	0.00
81.00		78.95	211.70	0.00	0.00
85.00		314.68	714.23	0.00	0.00
90.00	(24) attachments	4558.20	3994.01	0.00	0.00
95.00		378.99	828.80	0.00	0.00
100.00	(47) attachments	7505.29	5943.70	0.00	0.00
105.00		360.68	753.13	0.00	0.00
107.00	(1) attachments	343.81	713.77	0.00	0.00
110.00	(8) attachments	1391.39	2131.83	548.16	0.00
113.00	(1) attachments	390.30	555.05	0.00	0.00
115.00		134.24	268.69	0.00	0.00
117.00	(16) attachments	3519.64	3243.17	0.00	0.00
119.00	(1) attachments	146.59	235.34	0.00	0.00
Totals:		25,802.04	44,024.30	548.16	0.00

Calculated Forces

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 11

Load Case: 1.2D + 1.6W 97 mph Wind

Iterations 18

Dead Load Factor 1.20
Wind Load Factor 1.60



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-44.00	-25.84	-0.55	-2265.7	0.00	2265.77	5484.43	2742.22	13159.3	6589.47	0.00	0.000	0.000	0.352
5.00	-42.19	-25.45	-0.55	-2136.5	0.00	2136.59	5405.01	2702.51	12673.3	6346.09	0.05	-0.090	0.000	0.345
10.00	-40.42	-25.07	-0.55	-2009.3	0.00	2009.34	5323.53	2661.77	12191.2	6104.68	0.19	-0.180	0.000	0.337
15.00	-38.68	-24.70	-0.55	-1883.9	0.00	1883.98	5239.98	2619.99	11713.4	5865.43	0.43	-0.271	0.000	0.329
20.00	-36.98	-24.33	-0.55	-1760.5	0.00	1760.51	5154.37	2577.18	11240.2	5628.50	0.76	-0.363	0.000	0.320
25.00	-35.32	-23.96	-0.55	-1638.8	0.00	1638.88	5066.69	2533.35	10772.0	5394.05	1.19	-0.455	0.000	0.311
30.00	-33.70	-23.60	-0.55	-1519.0	0.00	1519.08	4976.95	2488.47	10309.2	5162.27	1.72	-0.548	0.000	0.301
35.00	-32.12	-23.23	-0.55	-1401.0	0.00	1401.08	4885.14	2442.57	9851.98	4933.31	2.35	-0.640	0.000	0.291
40.00	-30.58	-22.85	-0.55	-1284.9	0.00	1284.93	4791.27	2395.63	9400.73	4707.35	3.07	-0.732	0.000	0.279
45.00	-29.09	-22.45	-0.55	-1170.6	0.00	1170.69	4695.33	2347.66	8955.81	4484.56	3.88	-0.823	0.000	0.267
47.00	-28.49	-22.30	-0.55	-1125.8	0.00	1125.80	4656.37	2328.19	8779.69	4396.37	4.23	-0.860	0.000	0.262
50.00	-26.94	-22.05	-0.55	-1058.9	0.00	1058.92	4597.32	2298.66	8517.56	4265.11	4.79	-0.914	0.000	0.254
53.00	-25.42	-21.79	-0.55	-992.78	0.00	992.78	3769.04	1884.52	6995.75	3503.08	5.39	-0.969	0.000	0.290
55.00	-24.91	-21.64	-0.55	-949.20	0.00	949.20	3738.97	1869.49	6858.18	3434.19	5.80	-1.005	0.000	0.283
60.00	-23.68	-21.24	-0.55	-840.99	-0.01	840.99	3662.35	1831.18	6517.42	3263.55	6.90	-1.100	0.000	0.264
65.00	-22.48	-20.83	-0.55	-734.80	-0.01	734.80	3583.67	1791.83	6181.48	3095.34	8.11	-1.191	0.000	0.244
70.00	-21.32	-20.43	-0.55	-630.63	-0.01	630.63	3502.92	1751.46	5850.70	2929.70	9.40	-1.278	-0.001	0.221
75.00	-20.19	-20.02	-0.55	-528.49	-0.01	528.49	3420.10	1710.05	5525.41	2766.81	10.79	-1.359	-0.001	0.197
80.00	-19.11	-19.61	-0.55	-428.38	-0.01	428.38	3335.22	1667.61	5205.95	2606.84	12.25	-1.434	-0.001	0.170
81.00	-18.88	-19.54	-0.55	-408.77	-0.01	408.77	3318.00	1659.00	5142.79	2575.22	12.55	-1.448	-0.001	0.165
81.00	-18.88	-19.54	-0.55	-408.77	-0.01	408.77	2626.87	1313.44	4085.05	2045.56	12.55	-1.448	-0.001	0.207
85.00	-18.16	-19.22	-0.55	-330.62	-0.01	330.62	2576.62	1288.31	3894.21	1950.00	13.79	-1.500	-0.001	0.177
90.00	-14.27	-14.57	-0.55	-234.51	-0.01	234.51	2511.95	1255.98	3659.15	1832.29	15.40	-1.564	-0.001	0.134
95.00	-13.45	-14.18	-0.55	-161.65	-0.01	161.65	2445.22	1222.61	3428.26	1716.68	17.07	-1.614	-0.001	0.100
100.00	-7.72	-6.51	-0.55	-90.75	-0.01	90.75	2376.41	1188.21	3201.88	1603.32	18.78	-1.650	-0.001	0.060
105.00	-6.97	-6.13	-0.55	-58.18	-0.01	58.18	2305.55	1152.77	2980.36	1492.40	20.52	-1.674	-0.001	0.042
107.00	-6.27	-5.77	-0.55	-45.92	-0.01	45.92	2276.62	1138.31	2893.19	1448.75	21.22	-1.682	-0.001	0.034
110.00	-4.18	-4.32	0.00	-28.61	0.00	28.61	2225.68	1112.84	2755.45	1379.77	22.28	-1.690	-0.002	0.023
113.00	-3.63	-3.91	0.00	-15.66	0.00	15.66	2167.31	1083.66	2612.10	1307.99	23.35	-1.696	-0.002	0.014
115.00	-3.37	-3.77	0.00	-7.84	0.00	7.84	2128.40	1064.20	2518.66	1261.20	24.06	-1.698	-0.002	0.008
117.00	-0.23	-0.15	0.00	-0.31	0.00	0.31	2089.48	1044.74	2426.92	1215.26	24.77	-1.699	-0.002	0.000
119.00	0.00	-0.15	0.00	0.00	0.00	0.00	2050.57	1025.29	2336.89	1170.18	25.48	-1.699	-0.002	0.000

Wind Loading - Shaft


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 12

Load Case: 0.9D + 1.6W 97 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 18

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.70	16.018	17.62	403.87	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.70	16.018	17.62	394.80	0.650	0.000	5.00	24.603	15.99	450.8	0.0	1227.1
10.00		1.00	0.70	16.018	17.62	385.74	0.650	0.000	5.00	24.044	15.63	440.6	0.0	1199.0
15.00		1.00	0.70	16.018	17.62	376.67	0.650	0.000	5.00	23.486	15.27	430.4	0.0	1171.0
20.00		1.00	0.70	16.018	17.62	367.60	0.650	0.000	5.00	22.927	14.90	420.1	0.0	1142.9
25.00		1.00	0.70	16.018	17.62	358.54	0.650	0.000	5.00	22.369	14.54	409.9	0.0	1114.8
30.00		1.00	0.70	16.031	17.63	349.62	0.650	0.000	5.00	21.810	14.18	400.0	0.0	1086.8
35.00		1.00	0.73	16.753	18.43	348.13	0.650	0.000	5.00	21.252	13.81	407.3	0.0	1058.7
40.00		1.00	0.76	17.405	19.15	345.39	0.650	0.000	5.00	20.693	13.45	412.0	0.0	1030.6
45.00		1.00	0.79	18.000	19.80	341.64	0.650	0.000	5.00	20.134	13.09	414.6	0.0	1002.6
47.00	Bot - Section 2	1.00	0.80	18.225	20.05	339.90	0.650	0.000	2.00	7.897	5.13	164.7	0.0	393.2
50.00		1.00	0.81	18.551	20.41	337.06	0.650	0.000	3.00	11.869	7.71	251.9	0.0	1088.5
53.00	Top - Section 1	1.00	0.82	18.862	20.75	333.98	0.650	0.000	3.00	11.668	7.58	251.8	0.0	1069.7
55.00		1.00	0.83	19.063	20.97	337.41	0.650	0.000	2.00	7.667	4.98	167.2	0.0	327.5
60.00		1.00	0.85	19.543	21.50	331.62	0.650	0.000	5.00	18.776	12.20	419.8	0.0	802.0
65.00		1.00	0.87	19.995	21.99	325.30	0.650	0.000	5.00	18.218	11.84	416.7	0.0	777.9
70.00		1.00	0.89	20.422	22.46	318.53	0.650	0.000	5.00	17.659	11.48	412.6	0.0	753.8
75.00		1.00	0.91	20.829	22.91	311.34	0.650	0.000	5.00	17.100	11.12	407.5	0.0	729.8
80.00		1.00	0.93	21.217	23.34	303.79	0.650	0.000	5.00	16.542	10.75	401.5	0.0	705.7
81.00	Top - Section 2	1.00	0.93	21.292	23.42	302.24	0.650	0.000	1.00	3.241	2.11	79.0	0.0	138.3
85.00		1.00	0.94	21.587	23.75	295.91	0.650	0.000	4.00	12.742	8.28	314.7	0.0	453.6
90.00	Appurtenance(s)	1.00	0.96	21.943	24.14	287.73	0.650	0.000	5.00	15.425	10.03	387.2	0.0	548.9
95.00		1.00	0.97	22.284	24.51	279.26	0.650	0.000	5.00	14.866	9.66	379.0	0.0	528.9
100.00	Appurtenance(s)	1.00	0.99	22.613	24.87	270.54	0.650	0.000	5.00	14.308	9.30	370.1	0.0	508.8
105.00		1.00	1.00	22.931	25.22	261.59	0.650	0.000	5.00	13.749	8.94	360.7	0.0	488.8
107.00	Appurtenance(s)	1.00	1.01	23.055	25.36	257.94	0.650	0.000	2.00	5.343	3.47	140.9	0.0	189.9
110.00	Appurtenance(s)	1.00	1.02	23.238	25.56	252.41	0.650	0.000	3.00	7.847	5.10	208.6	0.0	278.8
113.00	Appurtenance(s)	1.00	1.02	23.417	25.76	246.81	0.650	0.000	3.00	7.646	4.97	204.8	0.0	271.6
115.00		1.00	1.03	23.535	25.89	243.03	0.650	0.000	2.00	4.986	3.24	134.2	0.0	177.1
117.00	Appurtenance(s)	1.00	1.03	23.651	26.02	239.23	0.650	0.000	2.00	4.896	3.18	132.5	0.0	173.9
119.00	Appurtenance(s)	1.00	1.04	23.766	26.14	235.39	0.650	0.000	2.00	4.807	3.12	130.7	0.0	170.7
Totals:									119.00			9,521.7		20,610.9

Discrete Appurtenance Forces


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 13

Load Case: 0.9D + 1.6W 97 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 18

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	119.00	6' Lightning rod	1	23.766	26.142	1.00	1.00	0.38	5.85	0.000	0.000	15.89	0.00	0.00
2	117.00	AIR 21 B2A B4P	3	23.651	26.016	0.62	0.75	11.32	247.05	0.000	0.000	471.13	0.00	0.00
3	117.00	LNx-6515DS-A1M	3	23.651	26.016	0.63	0.75	21.58	135.81	0.000	0.000	898.07	0.00	0.00
4	117.00	S11B12	3	23.651	26.016	0.53	0.75	4.50	137.70	0.000	0.000	187.13	0.00	0.00
5	117.00	AIR 21 B4A B2P	3	23.651	26.016	0.62	0.75	11.32	243.81	0.000	0.000	471.13	0.00	0.00
6	117.00	KRY 112 144/1	3	23.651	26.016	0.54	0.75	0.67	29.70	0.000	0.000	27.69	0.00	0.00
7	117.00	Platform w/ Hand Rail	1	23.651	26.016	1.00	1.00	32.00	1440.00	0.000	0.000	1332.02	0.00	0.00
8	113.00	3 ft Standoff	1	23.417	25.759	1.00	1.00	4.50	108.00	0.000	0.000	185.46	0.00	0.00
9	110.00	dual sector mounts	3	23.238	25.561	1.00	1.00	12.00	945.00	0.000	0.000	490.78	0.00	0.00
10	110.00	VHLP2-18	2	23.238	25.561	1.00	1.00	9.36	48.60	2.291	0.000	382.81	548.16	0.00
11	110.00	AAHC	3	23.238	25.561	0.60	0.80	7.56	280.80	0.000	0.000	309.19	0.00	0.00
12	107.00	Ring Mount	1	23.055	25.360	1.00	1.00	5.00	315.00	0.000	0.000	202.88	0.00	0.00
13	100.00	Platform w/ Hand Rail	1	22.613	24.875	1.00	1.00	43.80	1687.50	0.000	0.000	1743.22	0.00	0.00
14	100.00	DC6-48-60-18-8F	4	22.613	24.875	0.75	0.75	4.41	118.08	0.000	0.000	175.52	0.00	0.00
15	100.00	RRUS-A2	6	22.613	24.875	0.46	0.75	5.12	118.80	0.000	0.000	203.87	0.00	0.00
16	100.00	RRU-12	6	22.613	24.875	0.53	0.75	8.89	313.20	0.000	0.000	353.80	0.00	0.00
17	100.00	RRU-11	12	22.613	24.875	0.53	0.75	15.99	583.20	0.000	0.000	636.37	0.00	0.00
18	100.00	HPA-65R-BUJ-H8	12	22.613	24.875	0.58	0.75	91.00	656.64	0.000	0.000	3621.87	0.00	0.00
19	100.00	IBC700-1	3	22.613	24.875	0.68	0.75	2.68	170.91	0.000	0.000	106.63	0.00	0.00
20	100.00	RRU-32	3	22.613	24.875	0.64	0.75	7.38	207.90	0.000	0.000	293.88	0.00	0.00
21	90.00	RRH2X60-AWS	3	21.943	24.137	0.62	0.80	6.48	148.50	0.000	0.000	250.11	0.00	0.00
22	90.00	LNx-6514DS-A1M	6	21.943	24.137	0.66	0.80	32.20	209.52	0.000	0.000	1243.40	0.00	0.00
23	90.00	HBXX-6517DS-A2M	6	21.943	24.137	0.64	0.80	32.83	253.80	0.000	0.000	1267.95	0.00	0.00
24	90.00	Low Profile Platform	1	21.943	24.137	1.00	1.00	22.00	1350.00	0.000	0.000	849.63	0.00	0.00
25	90.00	RRH2x60-PCS	3	21.943	24.137	0.63	0.80	2.84	148.50	0.000	0.000	109.59	0.00	0.00
26	90.00	B13 RRH4x30	3	21.943	24.137	0.70	0.80	5.69	154.44	0.000	0.000	219.78	0.00	0.00
27	90.00	DB-T1-6Z-8AB-0Z	2	21.943	24.137	0.73	0.80	5.97	79.20	0.000	0.000	230.54	0.00	0.00

Totals: 10,137.51

16,280.34

Total Applied Force Summary


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 14

Load Case: 0.9D + 1.6W 97 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 18

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		450.83	1329.71	0.00	0.00
10.00		440.60	1301.64	0.00	0.00
15.00		430.36	1273.57	0.00	0.00
20.00		420.13	1245.50	0.00	0.00
25.00		409.89	1217.43	0.00	0.00
30.00		400.00	1189.36	0.00	0.00
35.00		407.30	1161.29	0.00	0.00
40.00		412.02	1133.22	0.00	0.00
45.00		414.62	1105.15	0.00	0.00
47.00		164.66	434.20	0.00	0.00
50.00		251.88	1150.04	0.00	0.00
53.00		251.77	1131.27	0.00	0.00
55.00		167.20	368.56	0.00	0.00
60.00		419.77	904.56	0.00	0.00
65.00		416.70	880.50	0.00	0.00
70.00		412.57	856.44	0.00	0.00
75.00		407.48	832.38	0.00	0.00
80.00		401.50	808.32	0.00	0.00
81.00		78.95	158.78	0.00	0.00
85.00		314.68	535.67	0.00	0.00
90.00	(24) attachments	4558.20	2995.51	0.00	0.00
95.00		378.99	621.60	0.00	0.00
100.00	(47) attachments	7505.29	4457.78	0.00	0.00
105.00		360.68	564.85	0.00	0.00
107.00	(1) attachments	343.81	535.32	0.00	0.00
110.00	(8) attachments	1391.39	1598.87	548.16	0.00
113.00	(1) attachments	390.30	416.29	0.00	0.00
115.00		134.24	201.52	0.00	0.00
117.00	(16) attachments	3519.64	2432.38	0.00	0.00
119.00	(1) attachments	146.59	176.51	0.00	0.00
	Totals:	25,802.04	33,018.22	548.16	0.00

Calculated Forces

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 15

Load Case: 0.9D + 1.6W 97 mph Wind

Iterations 18

Dead Load Factor 0.90
Wind Load Factor 1.60



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-33.00	-25.83	-0.55	-2255.6	0.00	2255.63	5484.43	2742.22	13159.3	6589.47	0.00	0.000	0.000	0.348
5.00	-31.63	-25.43	-0.55	-2126.5	0.00	2126.50	5405.01	2702.51	12673.3	6346.09	0.05	-0.089	0.000	0.341
10.00	-30.29	-25.03	-0.55	-1999.3	0.00	1999.37	5323.53	2661.77	12191.2	6104.68	0.19	-0.179	0.000	0.333
15.00	-28.98	-24.64	-0.55	-1874.2	0.00	1874.22	5239.98	2619.99	11713.4	5865.43	0.43	-0.270	0.000	0.325
20.00	-27.70	-24.26	-0.55	-1751.0	0.00	1751.02	5154.37	2577.18	11240.2	5628.50	0.76	-0.361	0.000	0.317
25.00	-26.44	-23.88	-0.55	-1629.7	0.00	1629.73	5066.69	2533.35	10772.0	5394.05	1.19	-0.453	0.000	0.307
30.00	-25.22	-23.51	-0.55	-1510.3	0.00	1510.33	4976.95	2488.47	10309.2	5162.27	1.71	-0.545	0.000	0.298
35.00	-24.03	-23.13	-0.55	-1392.7	0.00	1392.77	4885.14	2442.57	9851.98	4933.31	2.33	-0.636	0.000	0.287
40.00	-22.86	-22.74	-0.55	-1277.1	0.00	1277.12	4791.27	2395.63	9400.73	4707.35	3.05	-0.728	0.000	0.276
45.00	-21.74	-22.34	-0.55	-1163.4	0.00	1163.41	4695.33	2347.66	8955.81	4484.56	3.86	-0.818	0.000	0.264
47.00	-21.29	-22.18	-0.55	-1118.7	0.00	1118.74	4656.37	2328.19	8779.69	4396.37	4.21	-0.855	0.000	0.259
50.00	-20.12	-21.93	-0.55	-1052.1	0.00	1052.19	4597.32	2298.66	8517.56	4265.11	4.77	-0.909	0.000	0.251
53.00	-18.98	-21.68	-0.55	-986.40	0.00	986.40	3769.04	1884.52	6995.75	3503.08	5.36	-0.963	0.000	0.287
55.00	-18.59	-21.52	-0.55	-943.05	0.00	943.05	3738.97	1869.49	6858.18	3434.19	5.77	-0.999	0.000	0.280
60.00	-17.66	-21.12	-0.55	-835.43	-0.01	835.43	3662.35	1831.18	6517.42	3263.55	6.87	-1.093	0.000	0.261
65.00	-16.75	-20.71	-0.55	-729.85	-0.01	729.85	3583.67	1791.83	6181.48	3095.34	8.06	-1.184	0.000	0.241
70.00	-15.87	-20.30	-0.55	-626.31	-0.01	626.31	3502.92	1751.46	5850.70	2929.70	9.35	-1.271	-0.001	0.218
75.00	-15.02	-19.89	-0.55	-524.81	-0.01	524.81	3420.10	1710.05	5525.41	2766.81	10.73	-1.351	-0.001	0.194
80.00	-14.21	-19.48	-0.55	-425.34	-0.01	425.34	3335.22	1667.61	5205.95	2606.84	12.18	-1.425	-0.001	0.168
81.00	-14.04	-19.41	-0.55	-405.85	-0.01	405.85	3318.00	1659.00	5142.79	2575.22	12.48	-1.439	-0.001	0.162
81.00	-14.04	-19.41	-0.55	-405.85	-0.01	405.85	2626.87	1313.44	4085.05	2045.56	12.48	-1.439	-0.001	0.204
85.00	-13.50	-19.10	-0.55	-328.21	-0.01	328.21	2576.62	1288.31	3894.21	1950.00	13.71	-1.491	-0.001	0.174
90.00	-10.61	-14.47	-0.55	-232.74	-0.01	232.74	2511.95	1255.98	3659.15	1832.29	15.31	-1.555	-0.001	0.131
95.00	-9.99	-14.08	-0.55	-160.40	-0.01	160.40	2445.22	1222.61	3428.26	1716.68	16.97	-1.605	-0.001	0.098
100.00	-5.74	-6.45	-0.55	-89.99	-0.01	89.99	2376.41	1188.21	3201.88	1603.32	18.67	-1.640	-0.001	0.059
105.00	-5.19	-6.08	-0.55	-57.72	-0.01	57.72	2305.55	1152.77	2980.36	1492.40	20.40	-1.664	-0.001	0.041
107.00	-4.66	-5.72	-0.55	-45.56	-0.01	45.56	2276.62	1138.31	2893.19	1448.75	21.10	-1.671	-0.001	0.034
110.00	-3.10	-4.28	0.00	-28.40	0.00	28.40	2225.68	1112.84	2755.45	1379.77	22.15	-1.680	-0.002	0.022
113.00	-2.70	-3.88	0.00	-15.55	0.00	15.55	2167.31	1083.66	2612.10	1307.99	23.21	-1.685	-0.002	0.013
115.00	-2.50	-3.74	0.00	-7.79	0.00	7.79	2128.40	1064.20	2518.66	1261.20	23.92	-1.687	-0.002	0.007
117.00	-0.17	-0.15	0.00	-0.30	0.00	0.30	2089.48	1044.74	2426.92	1215.26	24.62	-1.688	-0.002	0.000
119.00	0.00	-0.15	0.00	0.00	0.00	0.00	2050.57	1025.29	2336.89	1170.18	25.33	-1.688	-0.002	0.000


Wind Loading - Shaft

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Page: 16
	Struct Class: II	



Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 17

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.70	4.256	4.68	0.00	1.200	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.70	4.256	4.68	0.00	1.200	1.656	5.00	25.983	31.18	146.0	613.6	2249.7
10.00		1.00	0.70	4.256	4.68	0.00	1.200	1.775	5.00	25.523	30.63	143.4	644.2	2242.9
15.00		1.00	0.70	4.256	4.68	0.00	1.200	1.848	5.00	25.026	30.03	140.6	656.4	2217.7
20.00		1.00	0.70	4.256	4.68	0.00	1.200	1.902	5.00	24.512	29.41	137.7	660.5	2184.3
25.00		1.00	0.70	4.256	4.68	0.00	1.200	1.945	5.00	23.990	28.79	134.8	659.8	2146.2
30.00		1.00	0.70	4.260	4.69	0.00	1.200	1.981	5.00	23.461	28.15	131.9	656.0	2105.0
35.00		1.00	0.73	4.451	4.90	0.00	1.200	2.012	5.00	22.928	27.51	134.7	649.9	2061.5
40.00		1.00	0.76	4.625	5.09	0.00	1.200	2.039	5.00	22.392	26.87	136.7	642.1	2016.3
45.00		1.00	0.79	4.783	5.26	0.00	1.200	2.063	5.00	21.854	26.22	138.0	633.0	1969.7
47.00	Bot - Section 2	1.00	0.80	4.843	5.33	0.00	1.200	2.072	2.00	8.588	10.31	54.9	251.6	775.8
50.00		1.00	0.81	4.929	5.42	0.00	1.200	2.085	3.00	12.911	15.49	84.0	379.5	1830.8
53.00	Top - Section 1	1.00	0.82	5.012	5.51	0.00	1.200	2.097	3.00	12.716	15.26	84.1	375.6	1801.9
55.00		1.00	0.83	5.065	5.57	0.00	1.200	2.105	2.00	8.368	10.04	55.9	248.6	685.3
60.00		1.00	0.85	5.193	5.71	0.00	1.200	2.123	5.00	20.545	24.65	140.8	609.5	1678.8
65.00		1.00	0.87	5.313	5.84	0.00	1.200	2.140	5.00	20.001	24.00	140.3	596.9	1634.1
70.00		1.00	0.89	5.426	5.97	0.00	1.200	2.156	5.00	19.456	23.35	139.4	583.7	1588.9
75.00		1.00	0.91	5.534	6.09	0.00	1.200	2.171	5.00	18.910	22.69	138.1	570.0	1543.1
80.00		1.00	0.93	5.637	6.20	0.00	1.200	2.185	5.00	18.363	22.04	136.6	555.8	1496.8
81.00	Top - Section 2	1.00	0.93	5.657	6.22	0.00	1.200	2.188	1.00	3.606	4.33	26.9	110.6	294.9
85.00		1.00	0.94	5.736	6.31	0.00	1.200	2.198	4.00	14.208	17.05	107.6	433.0	1037.7
90.00	Appurtenance(s)	1.00	0.96	5.830	6.41	0.00	1.200	2.211	5.00	17.267	20.72	132.9	526.2	1258.1
95.00		1.00	0.97	5.921	6.51	0.00	1.200	2.223	5.00	16.719	20.06	130.7	510.8	1216.0
100.00	Appurtenance(s)	1.00	0.99	6.008	6.61	0.00	1.200	2.234	5.00	16.170	19.40	128.2	495.1	1173.6
105.00		1.00	1.00	6.093	6.70	0.00	1.200	2.245	5.00	15.620	18.74	125.6	479.1	1130.8
107.00	Appurtenance(s)	1.00	1.01	6.126	6.74	0.00	1.200	2.250	2.00	6.093	7.31	49.3	189.0	442.3
110.00	Appurtenance(s)	1.00	1.02	6.174	6.79	0.00	1.200	2.256	3.00	8.975	10.77	73.1	277.7	649.5
113.00	Appurtenance(s)	1.00	1.02	6.222	6.84	0.00	1.200	2.262	3.00	8.777	10.53	72.1	271.7	633.9
115.00		1.00	1.03	6.253	6.88	0.00	1.200	2.266	2.00	5.741	6.89	47.4	178.5	414.6
117.00	Appurtenance(s)	1.00	1.03	6.284	6.91	0.00	1.200	2.270	2.00	5.653	6.78	46.9	175.8	407.7
119.00	Appurtenance(s)	1.00	1.04	6.315	6.95	0.00	1.200	2.274	2.00	5.565	6.68	46.4	173.1	400.7
Totals:								119.00				3,205.0		41,288.4

Discrete Appurtenance Forces


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 17

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 17

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	119.00	6' Lightning rod	1	6.315	6.946	1.00	1.00	1.80	49.79	0.000	0.000	12.48	0.00	0.00
2	117.00	AIR 21 B2A B4P	3	6.284	6.913	0.62	0.75	14.14	1027.29	0.000	0.000	97.76	0.00	0.00
3	117.00	LNx-6515DS-A1M	3	6.284	6.913	0.63	0.75	29.71	889.84	0.000	0.000	205.36	0.00	0.00
4	117.00	S11B12	3	6.284	6.913	0.54	0.75	5.97	406.88	0.000	0.000	41.24	0.00	0.00
5	117.00	AIR 21 B4A B2P	3	6.284	6.913	0.62	0.75	14.14	1022.97	0.000	0.000	97.76	0.00	0.00
6	117.00	KRY 112 144/1	3	6.284	6.913	0.56	0.75	1.73	72.37	0.000	0.000	11.93	0.00	0.00
7	117.00	Platform w/ Hand Rail	1	6.284	6.913	1.00	1.00	68.32	4051.08	0.000	0.000	472.25	0.00	0.00
8	113.00	3 ft Standoff	1	6.222	6.844	1.00	1.00	8.57	372.57	0.000	0.000	58.66	0.00	0.00
9	110.00	dual sector mounts	3	6.174	6.792	1.00	1.00	22.83	2096.97	0.000	0.000	155.04	0.00	0.00
10	110.00	VHLP2-18	2	6.174	6.792	1.00	1.00	12.65	261.79	2.291	0.000	85.94	196.91	0.00
11	110.00	AAHC	3	6.174	6.792	0.60	0.80	9.53	903.96	0.000	0.000	64.73	0.00	0.00
12	107.00	Ring Mount	1	6.126	6.738	1.00	1.00	9.50	420.00	0.000	0.000	64.01	0.00	0.00
13	100.00	Platform w/ Hand Rail	1	6.008	6.609	1.00	1.00	92.74	5075.63	0.000	0.000	612.91	0.00	0.00
14	100.00	DC6-48-60-18-8F	4	6.008	6.609	0.75	0.75	7.10	391.71	0.000	0.000	46.91	0.00	0.00
15	100.00	RRUS-A2	6	6.008	6.609	0.47	0.75	8.75	384.41	0.000	0.000	57.84	0.00	0.00
16	100.00	RRU-12	6	6.008	6.609	0.53	0.75	11.86	1131.21	0.000	0.000	78.36	0.00	0.00
17	100.00	RRU-11	12	6.008	6.609	0.54	0.75	21.72	2236.37	0.000	0.000	143.53	0.00	0.00
18	100.00	HPA-65R-BUJ-H8	12	6.008	6.609	0.59	0.75	106.16	5555.64	0.000	0.000	701.61	0.00	0.00
19	100.00	IBC700-1	3	6.008	6.609	0.68	0.75	5.05	364.11	0.000	0.000	33.38	0.00	0.00
20	100.00	RRU-32	3	6.008	6.609	0.64	0.75	8.36	739.30	0.000	0.000	55.24	0.00	0.00
21	90.00	RRH2X60-AWS	3	5.830	6.413	0.63	0.80	8.46	441.07	0.000	0.000	54.23	0.00	0.00
22	90.00	LNx-6514DS-A1M	6	5.830	6.413	0.66	0.80	46.40	1353.67	0.000	0.000	297.61	0.00	0.00
23	90.00	HBXX-6517DS-A2M	6	5.830	6.413	0.64	0.80	47.21	1600.88	0.000	0.000	302.76	0.00	0.00
24	90.00	Low Profile Platform	1	5.830	6.413	1.00	1.00	44.38	3158.30	0.000	0.000	284.60	0.00	0.00
25	90.00	RRH2x60-PCS	3	5.830	6.413	0.63	0.80	4.24	443.28	0.000	0.000	27.20	0.00	0.00
26	90.00	B13 RRH4x30	3	5.830	6.413	0.70	0.80	9.12	455.06	0.000	0.000	58.46	0.00	0.00
27	90.00	DB-T1-6Z-8AB-0Z	2	5.830	6.413	0.80	0.80	8.18	669.45	0.000	0.000	52.49	0.00	0.00

Totals: 35,575.58

4,174.30

Total Applied Force Summary


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 18

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 17

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		145.97	2386.50	0.00	0.00
10.00		143.39	2379.73	0.00	0.00
15.00		140.59	2354.51	0.00	0.00
20.00		137.71	2321.13	0.00	0.00
25.00		134.77	2283.03	0.00	0.00
30.00		131.91	2241.79	0.00	0.00
35.00		134.72	2198.30	0.00	0.00
40.00		136.69	2153.08	0.00	0.00
45.00		137.97	2106.50	0.00	0.00
47.00		54.90	830.53	0.00	0.00
50.00		84.00	1912.89	0.00	0.00
53.00		84.12	1883.93	0.00	0.00
55.00		55.95	739.97	0.00	0.00
60.00		140.82	1815.59	0.00	0.00
65.00		140.26	1770.92	0.00	0.00
70.00		139.36	1725.66	0.00	0.00
75.00		138.14	1679.85	0.00	0.00
80.00		136.64	1633.58	0.00	0.00
81.00		26.93	322.29	0.00	0.00
85.00		107.57	1147.19	0.00	0.00
90.00	(24) attachments	1210.22	9516.60	0.00	0.00
95.00		130.67	1339.60	0.00	0.00
100.00	(47) attachments	1858.04	17175.54	0.00	0.00
105.00		125.63	1232.22	0.00	0.00
107.00	(1) attachments	113.28	902.81	0.00	0.00
110.00	(8) attachments	378.87	3973.03	196.91	0.00
113.00	(1) attachments	130.75	1055.38	0.00	0.00
115.00		47.39	447.20	0.00	0.00
117.00	(16) attachments	973.19	7910.67	0.00	0.00
119.00	(1) attachments	58.87	450.48	0.00	0.00
	Totals:	7,379.33	79,890.48	196.91	0.00

Calculated Forces

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 19

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Iterations 17

Dead Load Factor 1.20
Wind Load Factor 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-79.89	-7.40	-0.20	-644.34	0.00	644.34	5484.43	2742.22	13159.3	6589.47	0.00	0.000	0.000	0.112
5.00	-77.50	-7.28	-0.20	-607.36	0.00	607.36	5405.01	2702.51	12673.3	6346.09	0.01	-0.026	0.000	0.110
10.00	-75.12	-7.17	-0.20	-570.94	0.00	570.94	5323.53	2661.77	12191.2	6104.68	0.05	-0.051	0.000	0.108
15.00	-72.76	-7.06	-0.20	-535.07	0.00	535.07	5239.98	2619.99	11713.4	5865.43	0.12	-0.077	0.000	0.105
20.00	-70.43	-6.95	-0.20	-499.75	0.00	499.75	5154.37	2577.18	11240.2	5628.50	0.22	-0.103	0.000	0.102
25.00	-68.15	-6.85	-0.20	-464.98	0.00	464.98	5066.69	2533.35	10772.0	5394.05	0.34	-0.129	0.000	0.100
30.00	-65.90	-6.74	-0.20	-430.75	0.00	430.75	4976.95	2488.47	10309.2	5162.27	0.49	-0.155	0.000	0.097
35.00	-63.70	-6.63	-0.20	-397.06	0.00	397.06	4885.14	2442.57	9851.98	4933.31	0.67	-0.182	0.000	0.094
40.00	-61.55	-6.51	-0.20	-363.93	0.00	363.93	4791.27	2395.63	9400.73	4707.35	0.87	-0.208	0.000	0.090
45.00	-59.44	-6.38	-0.20	-331.38	0.00	331.38	4695.33	2347.66	8955.81	4484.56	1.10	-0.233	0.000	0.087
47.00	-58.61	-6.34	-0.20	-318.62	0.00	318.62	4656.37	2328.19	8779.69	4396.37	1.20	-0.244	0.000	0.085
50.00	-56.69	-6.26	-0.20	-299.61	0.00	299.61	4597.32	2298.66	8517.56	4265.11	1.36	-0.259	0.000	0.083
53.00	-54.81	-6.18	-0.20	-280.82	0.00	280.82	3769.04	1884.52	6995.75	3503.08	1.53	-0.275	0.000	0.095
55.00	-54.07	-6.14	-0.20	-268.47	0.00	268.47	3738.97	1869.49	6858.18	3434.19	1.65	-0.285	0.000	0.093
60.00	-52.25	-6.01	-0.20	-237.78	0.00	237.78	3662.35	1831.18	6517.42	3263.55	1.96	-0.312	0.000	0.087
65.00	-50.48	-5.88	-0.20	-207.72	0.00	207.72	3583.67	1791.83	6181.48	3095.34	2.30	-0.338	0.000	0.081
70.00	-48.75	-5.75	-0.20	-178.30	0.00	178.30	3502.92	1751.46	5850.70	2929.70	2.67	-0.362	0.000	0.075
75.00	-47.07	-5.62	-0.20	-149.53	0.00	149.53	3420.10	1710.05	5525.41	2766.81	3.06	-0.385	0.000	0.068
80.00	-45.44	-5.49	-0.20	-121.42	0.00	121.42	3335.22	1667.61	5205.95	2606.84	3.48	-0.406	0.000	0.060
81.00	-45.11	-5.46	-0.20	-115.93	0.00	115.93	3318.00	1659.00	5142.79	2575.22	3.56	-0.410	0.000	0.059
81.00	-45.11	-5.46	-0.20	-115.93	0.00	115.93	2626.87	1313.44	4085.05	2045.56	3.56	-0.410	0.000	0.074
85.00	-43.96	-5.36	-0.20	-94.08	0.00	94.08	2576.62	1288.31	3894.21	1950.00	3.91	-0.425	0.000	0.065
90.00	-34.46	-4.09	-0.20	-67.28	0.00	67.28	2511.95	1255.98	3659.15	1832.29	4.37	-0.443	0.000	0.050
95.00	-33.12	-3.95	-0.20	-46.84	0.00	46.84	2445.22	1222.61	3428.26	1716.68	4.84	-0.458	0.000	0.041
100.00	-15.96	-1.96	-0.20	-27.07	0.00	27.07	2376.41	1188.21	3201.88	1603.32	5.33	-0.468	0.000	0.024
105.00	-14.72	-1.82	-0.20	-17.28	0.00	17.28	2305.55	1152.77	2980.36	1492.40	5.82	-0.476	-0.001	0.018
107.00	-13.82	-1.70	-0.20	-13.63	0.00	13.63	2276.62	1138.31	2893.19	1448.75	6.02	-0.478	-0.001	0.015
110.00	-9.85	-1.29	0.00	-8.51	0.00	8.51	2225.68	1112.84	2755.45	1379.77	6.32	-0.480	-0.001	0.011
113.00	-8.80	-1.15	0.00	-4.64	0.00	4.64	2167.31	1083.66	2612.10	1307.99	6.62	-0.482	-0.001	0.008
115.00	-8.35	-1.10	0.00	-2.33	0.00	2.33	2128.40	1064.20	2518.66	1261.20	6.83	-0.483	-0.001	0.006
117.00	-0.45	-0.06	0.00	-0.13	0.00	0.13	2089.48	1044.74	2426.92	1215.26	7.03	-0.483	-0.001	0.000
119.00	0.00	-0.06	0.00	0.00	0.00	0.00	2050.57	1025.29	2336.89	1170.18	7.23	-0.483	-0.001	0.000


Seismic Segment Forces (Factored)

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 20

Load Case: 1.2D + 1.0E				Iterations 16
Gust Response Factor	1.10	Sds	0.19	Ss 0.18
Dead Load Factor	1.20	Seismic Load Factor	1.00	S1 0.06
Wind Load Factor	0.00	Structure Frequency	0.57	SA 0.06
				Seismic Importance Factor 1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00		0.00	0.00	0.00	0.00	0.00	
5.00		1363.4	0.00	0.04	0.02	20.37	
10.00		1332.2	0.01	0.06	0.03	29.04	
15.00		1301.0	0.03	0.07	0.04	32.61	
20.00		1269.8	0.05	0.07	0.04	34.07	
25.00		1238.7	0.08	0.07	0.04	34.82	
30.00		1207.5	0.12	0.07	0.03	35.37	
35.00		1176.3	0.16	0.07	0.03	35.64	
40.00		1145.1	0.21	0.06	0.02	35.20	
45.00		1113.9	0.27	0.05	0.01	33.37	
47.00	Bot - Section 2	436.85	0.29	0.05	0.01	12.73	
50.00		1209.4	0.33	0.04	0.01	32.93	
53.00	Top - Section 1	1188.5	0.37	0.03	0.01	29.00	
55.00		363.91	0.40	0.02	0.01	7.99	
60.00		891.06	0.48	-0.01	0.01	12.58	
65.00		864.33	0.56	-0.04	0.01	3.91	
70.00		837.60	0.65	-0.07	0.02	-4.14	
75.00		810.86	0.75	-0.10	0.04	-9.53	
80.00		784.13	0.85	-0.12	0.07	-10.60	
81.00	Top - Section 2	153.62	0.88	-0.12	0.08	-2.01	
85.00		503.99	0.96	-0.12	0.11	-4.27	
90.00	Appurtenance(s)	3214.3	1.08	-0.08	0.18	14.12	
95.00		587.66	1.20	0.01	0.26	15.01	
100.00	Appurtenance(s)	4850.0	1.33	0.17	0.37	267.85	
105.00		543.11	1.47	0.43	0.51	50.82	
107.00	Appurtenance(s)	561.01	1.53	0.57	0.58	62.47	
110.00	Appurtenance(s)	1725.8	1.61	0.83	0.69	242.82	
113.00	Appurtenance(s)	421.80	1.70	1.14	0.82	73.08	
115.00		196.75	1.77	1.38	0.92	38.72	
117.00	Appurtenance(s)	2675.4	1.83	1.66	1.02	593.28	
119.00	Appurtenance(s)	196.12	1.89	1.98	1.14	48.67	
Totals:		34,164.9				1,765.9	Total Wind: 25,802.0

Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required


Calculated Forces

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 21

Load Case: 1.2D + 1.0E						Iterations 16
Gust Response Factor	1.10			Sds	0.19	Ss 0.18
Dead Load Factor	1.20	Seismic Load Factor	1.00	Sd1	0.10	S1 0.06
Wind Load Factor	0.00	Structure Frequency	0.57	SA	0.06	Seismic Importance Factor 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-44.02	-1.80	0.00	-172.15	0.00	172.15	5484.43	2742.22	13159.3	6589.47	0.00	0.00	0.00	0.034
5.00	-42.25	-1.78	0.00	-163.16	0.00	163.16	5405.01	2702.51	12673.3	6346.09	0.00	-0.01	0.034	
10.00	-40.52	-1.76	0.00	-154.24	0.00	154.24	5323.53	2661.77	12191.2	6104.68	0.01	-0.01	0.033	
15.00	-38.82	-1.73	0.00	-145.45	0.00	145.45	5239.98	2619.99	11713.4	5865.43	0.03	-0.02	0.032	
20.00	-37.16	-1.70	0.00	-136.80	0.00	136.80	5154.37	2577.18	11240.2	5628.50	0.06	-0.03	0.032	
25.00	-35.53	-1.67	0.00	-128.31	0.00	128.31	5066.69	2533.35	10772.0	5394.05	0.09	-0.04	0.031	
30.00	-33.95	-1.64	0.00	-119.96	0.00	119.96	4976.95	2488.47	10309.2	5162.27	0.13	-0.04	0.030	
35.00	-32.40	-1.60	0.00	-111.78	0.00	111.78	4885.14	2442.57	9851.98	4933.31	0.18	-0.05	0.029	
40.00	-30.89	-1.57	0.00	-103.76	0.00	103.76	4791.27	2395.63	9400.73	4707.35	0.24	-0.06	0.028	
45.00	-29.41	-1.54	0.00	-95.91	0.00	95.91	4695.33	2347.66	8955.81	4484.56	0.30	-0.06	0.028	
47.00	-28.83	-1.53	0.00	-92.83	0.00	92.83	4656.37	2328.19	8779.69	4396.37	0.33	-0.07	0.027	
50.00	-27.30	-1.49	0.00	-88.25	0.00	88.25	4597.32	2298.66	8517.56	4265.11	0.37	-0.07	0.027	
53.00	-25.79	-1.47	0.00	-83.77	0.00	83.77	3769.04	1884.52	6995.75	3503.08	0.42	-0.08	0.031	
55.00	-25.30	-1.46	0.00	-80.84	0.00	80.84	3738.97	1869.49	6858.18	3434.19	0.45	-0.08	0.030	
60.00	-24.09	-1.45	0.00	-73.54	0.00	73.54	3662.35	1831.18	6517.42	3263.55	0.54	-0.09	0.029	
65.00	-22.92	-1.45	0.00	-66.30	0.00	66.30	3583.67	1791.83	6181.48	3095.34	0.64	-0.10	0.028	
70.00	-21.78	-1.45	0.00	-59.07	0.00	59.07	3502.92	1751.46	5850.70	2929.70	0.74	-0.10	0.026	
75.00	-20.67	-1.45	0.00	-51.83	0.00	51.83	3420.10	1710.05	5525.41	2766.81	0.85	-0.11	0.025	
80.00	-19.59	-1.45	0.00	-44.60	0.00	44.60	3335.22	1667.61	5205.95	2606.84	0.97	-0.12	0.023	
81.00	-19.38	-1.45	0.00	-43.15	0.00	43.15	3318.00	1659.00	5142.79	2575.22	1.00	-0.12	0.023	
81.00	-19.38	-1.45	0.00	-43.15	0.00	43.15	2626.87	1313.44	4085.05	2045.56	1.00	-0.12	0.028	
85.00	-18.66	-1.45	0.00	-37.36	0.00	37.36	2576.62	1288.31	3894.21	1950.00	1.10	-0.13	0.026	
90.00	-14.67	-1.43	0.00	-30.11	0.00	30.11	2511.95	1255.98	3659.15	1832.29	1.24	-0.13	0.022	
95.00	-13.84	-1.41	0.00	-22.98	0.00	22.98	2445.22	1222.61	3428.26	1716.68	1.38	-0.14	0.019	
100.00	-7.90	-1.13	0.00	-15.92	0.00	15.92	2376.41	1188.21	3201.88	1603.32	1.53	-0.15	0.013	
105.00	-7.15	-1.08	0.00	-10.27	0.00	10.27	2305.55	1152.77	2980.36	1492.40	1.69	-0.15	0.010	
107.00	-6.43	-1.01	0.00	-8.12	0.00	8.12	2276.62	1138.31	2893.19	1448.75	1.75	-0.15	0.008	
110.00	-4.30	-0.76	0.00	-5.08	0.00	5.08	2225.68	1112.84	2755.45	1379.77	1.85	-0.15	0.006	
113.00	-3.75	-0.69	0.00	-2.78	0.00	2.78	2167.31	1083.66	2612.10	1307.99	1.95	-0.15	0.004	
115.00	-3.48	-0.65	0.00	-1.40	0.00	1.40	2128.40	1064.20	2518.66	1261.20	2.01	-0.15	0.003	
117.00	-0.24	-0.05	0.00	-0.10	0.00	0.10	2089.48	1044.74	2426.92	1215.26	2.08	-0.15	0.000	
119.00	0.00	-0.05	0.00	0.00	0.00	0.00	2050.57	1025.29	2336.89	1170.18	2.14	-0.15	0.000	


Seismic Segment Forces (Factored)

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 22

Load Case: 0.9D + 1.0E				Iterations 16
Gust Response Factor	1.10	Sds	0.19	Ss 0.18
Dead Load Factor	0.90	Seismic Load Factor	1.00	Sd1 0.10
Wind Load Factor	0.00	Structure Frequency	0.57	SA 0.06
				Seismic Importance Factor 1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00		0.00	0.00	0.00	0.00	0.00	
5.00		1363.4	0.00	0.04	0.02	20.37	
10.00		1332.2	0.01	0.06	0.03	29.04	
15.00		1301.0	0.03	0.07	0.04	32.61	
20.00		1269.8	0.05	0.07	0.04	34.07	
25.00		1238.7	0.08	0.07	0.04	34.82	
30.00		1207.5	0.12	0.07	0.03	35.37	
35.00		1176.3	0.16	0.07	0.03	35.64	
40.00		1145.1	0.21	0.06	0.02	35.20	
45.00		1113.9	0.27	0.05	0.01	33.37	
47.00	Bot - Section 2	436.85	0.29	0.05	0.01	12.73	
50.00		1209.4	0.33	0.04	0.01	32.93	
53.00	Top - Section 1	1188.5	0.37	0.03	0.01	29.00	
55.00		363.91	0.40	0.02	0.01	7.99	
60.00		891.06	0.48	-0.01	0.01	12.58	
65.00		864.33	0.56	-0.04	0.01	3.91	
70.00		837.60	0.65	-0.07	0.02	-4.14	
75.00		810.86	0.75	-0.10	0.04	-9.53	
80.00		784.13	0.85	-0.12	0.07	-10.60	
81.00	Top - Section 2	153.62	0.88	-0.12	0.08	-2.01	
85.00		503.99	0.96	-0.12	0.11	-4.27	
90.00	Appurtenance(s)	3214.3	1.08	-0.08	0.18	14.12	
95.00		587.66	1.20	0.01	0.26	15.01	
100.00	Appurtenance(s)	4850.0	1.33	0.17	0.37	267.85	
105.00		543.11	1.47	0.43	0.51	50.82	
107.00	Appurtenance(s)	561.01	1.53	0.57	0.58	62.47	
110.00	Appurtenance(s)	1725.8	1.61	0.83	0.69	242.82	
113.00	Appurtenance(s)	421.80	1.70	1.14	0.82	73.08	
115.00		196.75	1.77	1.38	0.92	38.72	
117.00	Appurtenance(s)	2675.4	1.83	1.66	1.02	593.28	
119.00	Appurtenance(s)	196.12	1.89	1.98	1.14	48.67	
Totals:		34,164.9				1,765.9	Total Wind: 25,802.0

Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required


Calculated Forces

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 23

Load Case: 0.9D + 1.0E						Iterations 16
Gust Response Factor	1.10			Sds	0.19	Ss 0.18
Dead Load Factor	0.90	Seismic Load Factor	1.00	Sd1	0.10	S1 0.06
Wind Load Factor	0.00	Structure Frequency	0.57	SA	0.06	Seismic Importance Factor 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-33.02	-1.80	0.00	-171.32	0.00	171.32	5484.43	2742.22	13159.3	6589.47	0.00	0.00	0.00	0.032
5.00	-31.69	-1.78	0.00	-162.34	0.00	162.34	5405.01	2702.51	12673.3	6346.09	0.00	-0.01	0.031	
10.00	-30.39	-1.76	0.00	-153.43	0.00	153.43	5323.53	2661.77	12191.2	6104.68	0.01	-0.01	0.031	
15.00	-29.11	-1.73	0.00	-144.66	0.00	144.66	5239.98	2619.99	11713.4	5865.43	0.03	-0.02	0.030	
20.00	-27.87	-1.69	0.00	-136.03	0.00	136.03	5154.37	2577.18	11240.2	5628.50	0.06	-0.03	0.030	
25.00	-26.65	-1.66	0.00	-127.56	0.00	127.56	5066.69	2533.35	10772.0	5394.05	0.09	-0.03	0.029	
30.00	-25.46	-1.63	0.00	-119.25	0.00	119.25	4976.95	2488.47	10309.2	5162.27	0.13	-0.04	0.028	
35.00	-24.30	-1.60	0.00	-111.10	0.00	111.10	4885.14	2442.57	9851.98	4933.31	0.18	-0.05	0.027	
40.00	-23.16	-1.56	0.00	-103.12	0.00	103.12	4791.27	2395.63	9400.73	4707.35	0.24	-0.06	0.027	
45.00	-22.06	-1.53	0.00	-95.31	0.00	95.31	4695.33	2347.66	8955.81	4484.56	0.30	-0.06	0.026	
47.00	-21.63	-1.52	0.00	-92.25	0.00	92.25	4656.37	2328.19	8779.69	4396.37	0.33	-0.07	0.026	
50.00	-20.48	-1.49	0.00	-87.69	0.00	87.69	4597.32	2298.66	8517.56	4265.11	0.37	-0.07	0.025	
53.00	-19.34	-1.46	0.00	-83.23	0.00	83.23	3769.04	1884.52	6995.75	3503.08	0.42	-0.08	0.029	
55.00	-18.98	-1.45	0.00	-80.32	0.00	80.32	3738.97	1869.49	6858.18	3434.19	0.45	-0.08	0.028	
60.00	-18.07	-1.44	0.00	-73.07	0.00	73.07	3662.35	1831.18	6517.42	3263.55	0.54	-0.09	0.027	
65.00	-17.19	-1.44	0.00	-65.88	0.00	65.88	3583.67	1791.83	6181.48	3095.34	0.63	-0.10	0.026	
70.00	-16.33	-1.44	0.00	-58.70	0.00	58.70	3502.92	1751.46	5850.70	2929.70	0.74	-0.10	0.025	
75.00	-15.50	-1.44	0.00	-51.52	0.00	51.52	3420.10	1710.05	5525.41	2766.81	0.85	-0.11	0.023	
80.00	-14.69	-1.44	0.00	-44.33	0.00	44.33	3335.22	1667.61	5205.95	2606.84	0.97	-0.12	0.021	
81.00	-14.53	-1.44	0.00	-42.90	0.00	42.90	3318.00	1659.00	5142.79	2575.22	0.99	-0.12	0.021	
81.00	-14.53	-1.44	0.00	-42.90	0.00	42.90	2626.87	1313.44	4085.05	2045.56	0.99	-0.12	0.027	
85.00	-14.00	-1.44	0.00	-37.15	0.00	37.15	2576.62	1288.31	3894.21	1950.00	1.10	-0.13	0.024	
90.00	-11.00	-1.42	0.00	-29.96	0.00	29.96	2511.95	1255.98	3659.15	1832.29	1.23	-0.13	0.021	
95.00	-10.38	-1.40	0.00	-22.87	0.00	22.87	2445.22	1222.61	3428.26	1716.68	1.38	-0.14	0.018	
100.00	-5.92	-1.12	0.00	-15.85	0.00	15.85	2376.41	1188.21	3201.88	1603.32	1.53	-0.15	0.012	
105.00	-5.36	-1.07	0.00	-10.23	0.00	10.23	2305.55	1152.77	2980.36	1492.40	1.68	-0.15	0.009	
107.00	-4.82	-1.01	0.00	-8.08	0.00	8.08	2276.62	1138.31	2893.19	1448.75	1.74	-0.15	0.008	
110.00	-3.22	-0.76	0.00	-5.06	0.00	5.06	2225.68	1112.84	2755.45	1379.77	1.84	-0.15	0.005	
113.00	-2.81	-0.69	0.00	-2.77	0.00	2.77	2167.31	1083.66	2612.10	1307.99	1.93	-0.15	0.003	
115.00	-2.61	-0.65	0.00	-1.40	0.00	1.40	2128.40	1064.20	2518.66	1261.20	2.00	-0.15	0.002	
117.00	-0.18	-0.05	0.00	-0.10	0.00	0.10	2089.48	1044.74	2426.92	1215.26	2.06	-0.15	0.000	
119.00	0.00	-0.05	0.00	0.00	0.00	0.00	2050.57	1025.29	2336.89	1170.18	2.13	-0.15	0.000	

Wind Loading - Shaft


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 24

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 17

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00		1.00	0.70	6.129	6.74	249.82	0.650	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		1.00	0.70	6.129	6.74	244.21	0.650	0.000	5.00	24.603	15.99	107.8	0.0	1363.5
10.00		1.00	0.70	6.129	6.74	238.60	0.650	0.000	5.00	24.044	15.63	105.4	0.0	1332.3
15.00		1.00	0.70	6.129	6.74	232.99	0.650	0.000	5.00	23.486	15.27	102.9	0.0	1301.1
20.00		1.00	0.70	6.129	6.74	227.38	0.650	0.000	5.00	22.927	14.90	100.5	0.0	1269.9
25.00		1.00	0.70	6.129	6.74	221.78	0.650	0.000	5.00	22.369	14.54	98.0	0.0	1238.7
30.00		1.00	0.70	6.134	6.75	216.26	0.650	0.000	5.00	21.810	14.18	95.7	0.0	1207.5
35.00		1.00	0.73	6.410	7.05	215.34	0.650	0.000	5.00	21.252	13.81	97.4	0.0	1176.3
40.00		1.00	0.76	6.659	7.33	213.64	0.650	0.000	5.00	20.693	13.45	98.5	0.0	1145.1
45.00		1.00	0.79	6.887	7.58	211.32	0.650	0.000	5.00	20.134	13.09	99.1	0.0	1113.9
47.00	Bot - Section 2	1.00	0.80	6.973	7.67	210.25	0.650	0.000	2.00	7.897	5.13	39.4	0.0	436.8
50.00		1.00	0.81	7.098	7.81	208.49	0.650	0.000	3.00	11.869	7.71	60.2	0.0	1209.4
53.00	Top - Section 1	1.00	0.82	7.217	7.94	206.58	0.650	0.000	3.00	11.668	7.58	60.2	0.0	1188.6
55.00		1.00	0.83	7.294	8.02	208.71	0.650	0.000	2.00	7.667	4.98	40.0	0.0	363.9
60.00		1.00	0.85	7.477	8.22	205.12	0.650	0.000	5.00	18.776	12.20	100.4	0.0	891.1
65.00		1.00	0.87	7.650	8.42	201.22	0.650	0.000	5.00	18.218	11.84	99.6	0.0	864.3
70.00		1.00	0.89	7.814	8.60	197.03	0.650	0.000	5.00	17.659	11.48	98.7	0.0	837.6
75.00		1.00	0.91	7.969	8.77	192.58	0.650	0.000	5.00	17.100	11.12	97.4	0.0	810.9
80.00		1.00	0.93	8.118	8.93	187.91	0.650	0.000	5.00	16.542	10.75	96.0	0.0	784.1
81.00	Top - Section 2	1.00	0.93	8.147	8.96	186.95	0.650	0.000	1.00	3.241	2.11	18.9	0.0	153.6
85.00		1.00	0.94	8.260	9.09	183.04	0.650	0.000	4.00	12.742	8.28	75.2	0.0	504.0
90.00	Appurtenance(s)	1.00	0.96	8.396	9.24	177.97	0.650	0.000	5.00	15.425	10.03	92.6	0.0	609.9
95.00		1.00	0.97	8.526	9.38	172.74	0.650	0.000	5.00	14.866	9.66	90.6	0.0	587.7
100.00	Appurtenance(s)	1.00	0.99	8.652	9.52	167.35	0.650	0.000	5.00	14.308	9.30	88.5	0.0	565.4
105.00		1.00	1.00	8.774	9.65	161.81	0.650	0.000	5.00	13.749	8.94	86.3	0.0	543.1
107.00	Appurtenance(s)	1.00	1.01	8.821	9.70	159.55	0.650	0.000	2.00	5.343	3.47	33.7	0.0	211.0
110.00	Appurtenance(s)	1.00	1.02	8.891	9.78	156.13	0.650	0.000	3.00	7.847	5.10	49.9	0.0	309.8
113.00	Appurtenance(s)	1.00	1.02	8.960	9.86	152.67	0.650	0.000	3.00	7.646	4.97	49.0	0.0	301.8
115.00		1.00	1.03	9.005	9.91	150.33	0.650	0.000	2.00	4.986	3.24	32.1	0.0	196.7
117.00	Appurtenance(s)	1.00	1.03	9.049	9.95	147.97	0.650	0.000	2.00	4.896	3.18	31.7	0.0	193.2
119.00	Appurtenance(s)	1.00	1.04	9.093	10.00	145.60	0.650	0.000	2.00	4.807	3.12	31.3	0.0	189.6
Totals:								119.00			2,277.0	22,901.0		

Discrete Appurtenance Forces


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 25

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 17

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	119.00	6' Lightning rod	1	9.093	10.002	1.00	1.00	0.38	6.50	0.000	0.000	3.80	0.00	0.00
2	117.00	AIR 21 B2A B4P	3	9.049	9.954	0.62	0.75	11.32	274.50	0.000	0.000	112.66	0.00	0.00
3	117.00	LNx-6515DS-A1M	3	9.049	9.954	0.63	0.75	21.58	150.90	0.000	0.000	214.76	0.00	0.00
4	117.00	S11B12	3	9.049	9.954	0.53	0.75	4.50	153.00	0.000	0.000	44.75	0.00	0.00
5	117.00	AIR 21 B4A B2P	3	9.049	9.954	0.62	0.75	11.32	270.90	0.000	0.000	112.66	0.00	0.00
6	117.00	KRY 112 144/1	3	9.049	9.954	0.54	0.75	0.67	33.00	0.000	0.000	6.62	0.00	0.00
7	117.00	Platform w/ Hand Rail	1	9.049	9.954	1.00	1.00	32.00	1600.00	0.000	0.000	318.53	0.00	0.00
8	113.00	3 ft Standoff	1	8.960	9.856	1.00	1.00	4.50	120.00	0.000	0.000	44.35	0.00	0.00
9	110.00	dual sector mounts	3	8.891	9.780	1.00	1.00	12.00	1050.00	0.000	0.000	117.36	0.00	0.00
10	110.00	VHLP2-18	2	8.891	9.780	1.00	1.00	9.36	54.00	2.291	0.000	91.54	209.73	0.00
11	110.00	AAHC	3	8.891	9.780	0.60	0.80	7.56	312.00	0.000	0.000	73.94	0.00	0.00
12	107.00	Ring Mount	1	8.821	9.703	1.00	1.00	5.00	350.00	0.000	0.000	48.52	0.00	0.00
13	100.00	Platform w/ Hand Rail	1	8.652	9.517	1.00	1.00	43.80	1875.00	0.000	0.000	416.86	0.00	0.00
14	100.00	DC6-48-60-18-8F	4	8.652	9.517	0.75	0.75	4.41	131.20	0.000	0.000	41.97	0.00	0.00
15	100.00	RRUS-A2	6	8.652	9.517	0.46	0.75	5.12	132.00	0.000	0.000	48.75	0.00	0.00
16	100.00	RRU-12	6	8.652	9.517	0.53	0.75	8.89	348.00	0.000	0.000	84.60	0.00	0.00
17	100.00	RRU-11	12	8.652	9.517	0.53	0.75	15.99	648.00	0.000	0.000	152.18	0.00	0.00
18	100.00	HPA-65R-BUJ-H8	12	8.652	9.517	0.58	0.75	91.00	729.60	0.000	0.000	866.11	0.00	0.00
19	100.00	IBC700-1	3	8.652	9.517	0.68	0.75	2.68	189.90	0.000	0.000	25.50	0.00	0.00
20	100.00	RRU-32	3	8.652	9.517	0.64	0.75	7.38	231.00	0.000	0.000	70.28	0.00	0.00
21	90.00	RRH2X60-AWS	3	8.396	9.235	0.62	0.80	6.48	165.00	0.000	0.000	59.81	0.00	0.00
22	90.00	LNx-6514DS-A1M	6	8.396	9.235	0.66	0.80	32.20	232.80	0.000	0.000	297.34	0.00	0.00
23	90.00	HBXX-6517DS-A2M	6	8.396	9.235	0.64	0.80	32.83	282.00	0.000	0.000	303.21	0.00	0.00
24	90.00	Low Profile Platform	1	8.396	9.235	1.00	1.00	22.00	1500.00	0.000	0.000	203.17	0.00	0.00
25	90.00	RRH2x60-PCS	3	8.396	9.235	0.63	0.80	2.84	165.00	0.000	0.000	26.21	0.00	0.00
26	90.00	B13 RRH4x30	3	8.396	9.235	0.70	0.80	5.69	171.60	0.000	0.000	52.56	0.00	0.00
27	90.00	DB-T1-6Z-8AB-0Z	2	8.396	9.235	0.73	0.80	5.97	88.00	0.000	0.000	55.13	0.00	0.00

Totals: 11,263.90

3,893.16

Total Applied Force Summary


Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II



Page: 26

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 17

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		107.81	1477.46	0.00	0.00
10.00		105.36	1446.27	0.00	0.00
15.00		102.91	1415.08	0.00	0.00
20.00		100.47	1383.89	0.00	0.00
25.00		98.02	1352.70	0.00	0.00
30.00		95.65	1321.51	0.00	0.00
35.00		97.40	1290.33	0.00	0.00
40.00		98.53	1259.14	0.00	0.00
45.00		99.15	1227.95	0.00	0.00
47.00		39.38	482.45	0.00	0.00
50.00		60.23	1277.82	0.00	0.00
53.00		60.21	1256.97	0.00	0.00
55.00		39.98	409.51	0.00	0.00
60.00		100.38	1005.06	0.00	0.00
65.00		99.65	978.33	0.00	0.00
70.00		98.66	951.60	0.00	0.00
75.00		97.44	924.86	0.00	0.00
80.00		96.01	898.13	0.00	0.00
81.00		18.88	176.42	0.00	0.00
85.00		75.25	595.19	0.00	0.00
90.00	(24) attachments	1090.02	3328.34	0.00	0.00
95.00		90.63	690.66	0.00	0.00
100.00	(47) attachments	1794.76	4953.09	0.00	0.00
105.00		86.25	627.61	0.00	0.00
107.00	(1) attachments	82.22	594.81	0.00	0.00
110.00	(8) attachments	332.73	1776.52	209.73	0.00
113.00	(1) attachments	93.33	462.54	0.00	0.00
115.00		32.10	223.91	0.00	0.00
117.00	(16) attachments	841.66	2702.64	0.00	0.00
119.00	(1) attachments	35.05	196.12	0.00	0.00
	Totals:	6,170.11	36,686.92	209.73	0.00

Calculated Forces

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II




Page: 27

Load Case: 1.0D + 1.0W 60 mph Wind

Iterations 17

Dead Load Factor 1.00
Wind Load Factor 1.00



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-36.69	-6.18	-0.21	-540.22	0.00	540.22	5484.43	2742.22	13159.3	6589.47	0.00	0.000	0.000	0.089
5.00	-35.21	-6.08	-0.21	-509.34	0.00	509.34	5405.01	2702.51	12673.3	6346.09	0.01	-0.021	0.000	0.087
10.00	-33.76	-5.99	-0.21	-478.93	0.00	478.93	5323.53	2661.77	12191.2	6104.68	0.05	-0.043	0.000	0.085
15.00	-32.34	-5.90	-0.21	-448.99	0.00	448.99	5239.98	2619.99	11713.4	5865.43	0.10	-0.065	0.000	0.083
20.00	-30.95	-5.81	-0.21	-419.51	0.00	419.51	5154.37	2577.18	11240.2	5628.50	0.18	-0.087	0.000	0.081
25.00	-29.60	-5.72	-0.21	-390.48	0.00	390.48	5066.69	2533.35	10772.0	5394.05	0.28	-0.109	0.000	0.078
30.00	-28.28	-5.63	-0.21	-361.90	0.00	361.90	4976.95	2488.47	10309.2	5162.27	0.41	-0.130	0.000	0.076
35.00	-26.98	-5.54	-0.21	-333.75	0.00	333.75	4885.14	2442.57	9851.98	4933.31	0.56	-0.152	0.000	0.073
40.00	-25.72	-5.45	-0.21	-306.06	0.00	306.06	4791.27	2395.63	9400.73	4707.35	0.73	-0.174	0.000	0.070
45.00	-24.49	-5.35	-0.21	-278.83	0.00	278.83	4695.33	2347.66	8955.81	4484.56	0.93	-0.196	0.000	0.067
47.00	-24.01	-5.31	-0.21	-268.13	0.00	268.13	4656.37	2328.19	8779.69	4396.37	1.01	-0.205	0.000	0.066
50.00	-22.73	-5.25	-0.21	-252.19	0.00	252.19	4597.32	2298.66	8517.56	4265.11	1.14	-0.218	0.000	0.064
53.00	-21.47	-5.19	-0.21	-236.43	0.00	236.43	3769.04	1884.52	6995.75	3503.08	1.28	-0.231	0.000	0.073
55.00	-21.06	-5.16	-0.21	-226.04	0.00	226.04	3738.97	1869.49	6858.18	3434.19	1.38	-0.239	0.000	0.071
60.00	-20.06	-5.06	-0.21	-200.26	0.00	200.26	3662.35	1831.18	6517.42	3263.55	1.65	-0.262	0.000	0.067
65.00	-19.08	-4.96	-0.21	-174.96	0.00	174.96	3583.67	1791.83	6181.48	3095.34	1.93	-0.284	0.000	0.062
70.00	-18.12	-4.87	-0.21	-150.15	0.00	150.15	3502.92	1751.46	5850.70	2929.70	2.24	-0.305	0.000	0.056
75.00	-17.20	-4.77	-0.21	-125.82	0.00	125.82	3420.10	1710.05	5525.41	2766.81	2.57	-0.324	0.000	0.051
80.00	-16.30	-4.67	-0.21	-101.98	0.00	101.98	3335.22	1667.61	5205.95	2606.84	2.92	-0.341	0.000	0.044
81.00	-16.12	-4.65	-0.21	-97.31	0.00	97.31	3318.00	1659.00	5142.79	2575.22	2.99	-0.345	0.000	0.043
81.00	-16.12	-4.65	-0.21	-97.31	0.00	97.31	2626.87	1313.44	4085.05	2045.56	2.99	-0.345	0.000	0.054
85.00	-15.53	-4.58	-0.21	-78.70	0.00	78.70	2576.62	1288.31	3894.21	1950.00	3.29	-0.357	0.000	0.046
90.00	-12.21	-3.47	-0.21	-55.81	0.00	55.81	2511.95	1255.98	3659.15	1832.29	3.67	-0.373	0.000	0.035
95.00	-11.51	-3.38	-0.21	-38.46	0.00	38.46	2445.22	1222.61	3428.26	1716.68	4.07	-0.385	0.000	0.027
100.00	-6.57	-1.55	-0.21	-21.58	0.00	21.58	2376.41	1188.21	3201.88	1603.32	4.47	-0.393	0.000	0.016
105.00	-5.95	-1.46	-0.21	-13.84	0.00	13.84	2305.55	1152.77	2980.36	1492.40	4.89	-0.399	-0.001	0.012
107.00	-5.35	-1.37	-0.21	-10.93	0.00	10.93	2276.62	1138.31	2893.19	1448.75	5.06	-0.401	-0.001	0.010
110.00	-3.58	-1.03	0.00	-6.81	0.00	6.81	2225.68	1112.84	2755.45	1379.77	5.31	-0.403	-0.001	0.007
113.00	-3.12	-0.93	0.00	-3.73	0.00	3.73	2167.31	1083.66	2612.10	1307.99	5.56	-0.404	-0.001	0.004
115.00	-2.89	-0.90	0.00	-1.87	0.00	1.87	2128.40	1064.20	2518.66	1261.20	5.73	-0.404	-0.001	0.003
117.00	-0.20	-0.04	0.00	-0.07	0.00	0.07	2089.48	1044.74	2426.92	1215.26	5.90	-0.405	-0.001	0.000
119.00	0.00	-0.03	0.00	0.00	0.00	0.00	2050.57	1025.29	2336.89	1170.18	6.07	-0.405	-0.001	0.000

Final Analysis Summary

Structure: CT13555-S-SBA	Code: EIA/TIA-222-G	8/17/2018
Site Name: Montano	Exposure: B	
Height: 119.00 (ft)	Crest Height: 0.00	
Base Elev: 0.000 (ft)	Site Class: D - Stiff Soil	
Gh: 1.1	Topography: 1	Struct Class: II
		Page: 28



Reactions

Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)
1.2D + 1.6W 97 mph Wind	25.8	0.00	44.00	0.00	0.55	2265.77
0.9D + 1.6W 97 mph Wind	25.8	0.00	33.00	0.00	0.55	2255.63
1.2D + 1.0Di + 1.0Wi 50 mph Wind	7.4	0.00	79.89	0.00	0.20	644.34
1.2D + 1.0E	1.8	0.00	44.02	0.00	0.00	172.15
0.9D + 1.0E	1.8	0.00	33.02	0.00	0.00	171.32
1.0D + 1.0W 60 mph Wind	6.2	0.00	36.69	0.00	0.21	540.22

Max Stresses

Load Case	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Elev (ft)	Stress Ratio
1.2D + 1.6W 97 mph Wind	-44.00	-25.84	-0.55	-2265.7	0.00	-2265.7	5484.43	2742.2	13159.3	6589.47	0.00	0.352
0.9D + 1.6W 97 mph Wind	-33.00	-25.83	-0.55	-2255.6	0.00	-2255.6	5484.43	2742.2	13159.3	6589.47	0.00	0.348
1.2D + 1.0Di + 1.0Wi 50 mph Wind	-79.89	-7.40	-0.20	-644.34	0.00	-644.34	5484.43	2742.2	13159.3	6589.47	0.00	0.112
1.2D + 1.0E	-44.02	-1.80	0.00	-172.15	0.00	-172.15	5484.43	2742.2	13159.3	6589.47	0.00	0.034
0.9D + 1.0E	-33.02	-1.80	0.00	-171.32	0.00	-171.32	5484.43	2742.2	13159.3	6589.47	0.00	0.032
1.0D + 1.0W 60 mph Wind	-36.69	-6.18	-0.21	-540.22	0.00	-540.22	5484.43	2742.2	13159.3	6589.47	0.00	0.089



Monopole Mat Foundation Design

Date

8/17/2018

Customer Name:	Sprint Nextel	EIA/TIA Standard:	EIA-222-G
Site Name:		Structure Height (Ft.):	119
Site Number:	CT13555-S-SBA	Engineer Name:	T. Alajaj
Engr. Number:	59056	Engineer Login ID:	

Foundation Info Obtained from:

Drawings/Calculations

Structure Type:

Monopole

Analysis or Design?

Analysis

Base Reactions (Factored):

Axial Load (Kips):	79.9	Shear Force (Kips):	25.8
Uplift Force (Kips):	0.0	Moment (Kips-ft):	2265.8

Allowable overstress %: 5.0%

Foundation Geometries:

		Mods required -Yes/No ?:	No
Diameter of Pier (ft.):	7.0	Depth of Base BG (ft.):	6.0
Pier Height A. G. (ft.):	1.00	Thickness of Pad (ft):	2.00
Length of Pad (ft.):	26.5	Width of Pad (ft.):	26.5
Final Length of pad (ft)	26.5	Final width of pad (ft):	26.5
Control Value for Cell D18:	0	Control Value for Cell F18:	0

Material Properties and Rebar Info:

Concrete Strength (psi):	4000	Steel Elastic Modulus:	29000	ksi
Vertical bar yield (ksi)	60	Tie steel yield (ksi):	60	
Vertical Rebar Size #:	9	Tie / Stirrup Size #:	4	
Qty. of Vertical Rebars:	36	Tie Spacing (in):	12.0	
Pad Rebar Yield (Ksi):	60	Pad Steel Rebar Size (#):	8	
Concrete Cover (in.):	3	Unit Weight of Concrete:	150.0	pcf
Rebar at the bottom of the concrete pad:				
Qty. of Rebar in Pad (L):	45	Qty. of Rebar in Pad (W):	45	
Rebar at the top of the concrete pad:				
Qty. of Rebar in Pad (L):	45	Qty. of Rebar in Pad (W):	45	

Apply 1.35 factor for e/w Per G: 1.35

Soil Design Parameters:


Soil Unit Weight (pcf):	110.0	Soil Buoyant Weight:	37.6	Pcf
Water Table B.G.S. (ft):	99.0	Unit Weight of Water:	62.4	pcf
Ultimate Bearing Pressure (psf):	9000	Ultimate Skin Friction:	0	Psf
Consider Friction for O.T.M. (Y/N):	No	Consider Friction for bearing (Y/N):	No	
Consider soil hor. resist. for OTM.:	Yes	Reduction factor on the maximum soil bearing pressure:	1.00	
		Angle from Top of Pad:	30	
		Angle from Bottm of Pad:	25	
		Angle from Bottm of Pad:	25	

Foundation Analysis and Design:

Uplift Strength Reduction Factor:	0.75	Compression Strength Reduction Factor:	0.75
Total Dry Soil Volume (cu. Ft.):	2655.06	Total Dry Soil Weight (Kips):	292.06
Total Buoyant Soil Volume (cu. Ft.):	0.00	Total Buoyant Soil Weight (Kips):	0.00
Total Effective Soil Weight (Kips):	292.06	Weight from the Concrete Block at Top (K):	0.00
Total Dry Concrete Volume (cu. Ft.):	1596.92	Total Dry Concrete Weight (Kips):	239.54
Total Buoyant Concrete Volume (cu. Ft.):	0.00	Total Buoyant Concrete Weight (Kips):	0.00
Total Effective Concrete Weight (Kips):	239.54	Total Vertical Load on Base (Kips):	611.50

Check Soil Capacities:

Calculated Maxium Net Soil Pressure under the base (psf):	1574	<	Allowable Factored Soil Bearing (psf):	6750	0.23	OK!
Allowable Foundation Overturning Resistance (kips-ft.):	7397.9	>	Design Factored Momont (kips-ft):	2341	0.32	OK!
Factor of Safety Against Overturning (O. R. Moment/Design Moment):	3.16					OK!



Check the capacities of Reinforcing Concrete:

Strength reduction factor (Flexure and axial tension): 0.90 Strength reduction factor (Shear): 0.75
 Strength reduction factor (Axial compression): 0.65 Wind Load Factor on Concrete Design: 1.00

Load/
Capacity
Ratio

(1) Concrete Pier:

Vertical Steel Rebar Area (sq. in./each):	1.00	Tie / Stirrup Area (sq. in./each):	0.20		
Calculated Moment Capacity (Mn, Kips-Ft):	6026.1	> Design Factored Moment (Mu, Kips-Ft)	2394.8	0.40	OK!
Calculated Shear Capacity (Kips):	660.1	> Design Factored Shear (Kips):	25.8	0.04	OK!
Calculated Tension Capacity (Tn, Kips):	1944.0	> Design Factored Tension (Tu, Kips):	0.0	0.00	OK!
Calculated Compression Capacity (Pn, Kips):	9734.2	> Design Factored Axial Load (Pu, Kips):	79.9	0.01	OK!
Moment & Axial Strength Combination:	0.40	OK! Check Tie Spacing (Design/Required):		1	OK!
Pier Reinforcement Ratio:	0.006	Reinforcement Ratio is satisfied per ACI			

(2) Concrete Pad:

One-Way Design Shear Capacity (L-Direction, Kips):	618.4	> One-Way Factored Shear (L-D, Kips)	199.5	0.32	OK!
One-Way Design Shear Capacity (W-Direction, Kips):	618.4	> One-Way Factored Shear (W-D, Kips)	199.5	0.32	OK!
One-Way Design Shear Capacity (Corner-Corner, Kips):	631.5	> One-Way Factored Shear (CC, Kips):	189.6	0.30	OK!
Lower Steel Pad Reinforcement Ratio (L-Direct.):	0.0055	OK! Lower Steel Pad Reinf. Ratio (W-Direct)	0.0055		
Lower Steel Pad Moment Capacity (L-Direction, Kips-ft):	3121.7	> Moment at Bottom (L-Dir, K-Ft):	1093.7	0.35	OK!
Lower Steel Pad Moment Capacity (W-Direction, Kips-ft):	3121.7	> Moment at Bottom (W-Dir, K-Ft):	1093.7	0.35	OK!
Lower Steel Pad Moment Capacity (Corner-Corner, K-ft):	4363.5	> Moment at Bottom (C-C Dir, K-Ft):	1546.7	0.35	OK!
Upper Steel Pad Reinforcement Ratio (L-Direct.):	0.0055	OK! Upper Steel Reinf Ratio (W-Dir.):	0.0055		
Upper Steel Pad Moment Capacity (L-Direct, Kips-ft):	3121.7	> Moment at the top (L-Dir, K-Ft):	353.9	0.11	OK!
Upper Steel Pad Moment Capacity (W-Direct, Kips-ft):	3121.7	> Moment at the top (W-Dir, K-Ft):	353.9	0.11	OK!
Upper Steel Pad Moment Capacity (Corner-Corner, K-ft):	4363.5	> Moment at the top (C-C Dir, K-Ft):	331.4	0.08	OK!

(3) Check Punching Shear Capacity due to Moment in the Pier:

Moment transferred by punching shear:	906.3	k-ft.	Max. factored shear stress $v_{u,CD}$:	3.7	Psi
Max. factored shear stress $v_{u,AB}$:	16.1	Psi	Factored shear Strength ϕv_n :	189.7	Psi
Max. factored shear stress v_u :	16.1	Psi	Check Usage of Punching Shear Capacity:	0.08	0



Pier Foundation Design For Monopole			Date
			8/17/2018
Customer Name:	Sprint Nextel	EIA/TIA Standard:	EIA-222-G
Site Name:		Structure Height (Ft.):	119
Site Number:	CT13555-S-SBA	Engineer Name:	T. Alajaj
Engr. Number:	59056	Engineer Login ID:	

Foundation Info Obtained from: Drawings/Calculations

Structure Type: Monopole


Analysis or Design? Analysis

Base Reactions (Factored):

Axial Load (Kips):	79.9	Shear Force (Kips):	25.8
Uplift Force (Kips):	0.0	Moment (Kips-ft):	2265.8

Foundation Geometries:

Mods required -Yes/No ?:	No		ft.
Diameter of Pier (ft.):	7.0	Depth of Base B. G. S. :	29.0 ft.
Pier Height A. G. (ft.):	1.00		



Material Properties and Reabr Info:

Concrete Strength (psi):	4000	Steel Elastic Modulus:	29000	ksi
Vertical bar yield (ksi)	60	Tie steel yield strength:	60	ksi
Vertical Rebar Size #:	10	Tie / Stirrup Size #:	4	
Qty. of Vertical Rebars:	34	Tie Spacing:	12.0	in.
Concrete Cover (in.):	3	Concrete unit weight:	150.0	pcf

Soil Design Parameters:

Water Table B.G.S. (ft):	99.0	Unit weight of water:	62.4	psf
Ratio of Uplift/Axial Skin Friction:	1.0	Pullout failure Angle:	30	(°)
Skin Frictions are to be obtained from:	Soil Report			

Monopole Pier Foundation

Depth of Layers (ft)		γ_{soil} (pcf)	ϕ (°)	Cohesion (psf)	Ultimate Skin Friction (psf)	Ultimate Bearing (psf)	Soil Types					
Top	Bottom											
0.0	3.0	100	0	0	0	0	Sand					
3.0	25.0	110	33	0	1000	0	Sand					
25.0	30.0	105	30	0	1600	12000	Silt					
30.0	35.0											

Soil weight Increase Factor for bouyant soils (1.0 to 1.15): 1.1

Foundation Analysis and Design:

Uplift Strength Reduction Factor:	0.75	Soil Bearing Strength Reduction Factor:	0.75
Total Dry Soil Volume from Conical Failure (cu. Ft.):	13814	Dry Soil Weight from Conical Failure:	1281 Kips
Total Buoyant Soil Volume from Conical Failure (cu. Ft.):	0	Buoyant Soil Weight from Conical Failure (Kips):	0 Kips
Total Dry Concrete Volume (cu. Ft.):	1155	Total Dry Concrete Weight:	173.2 Kips
Total Buoyant Concrete Volume (cu. Ft.):	0.0	Total Buoyant Concrete Weight:	0.00 Kips
Total Effective Concrete Weight (Kips):	173.2	Total Effective Soil Weight:	1280.7 Kips
Total Effective Vertical Load on Base (Kips):	149.6		

Check Soil Capacities:

Allowable Foundation Overturning Resistance (kips-ft.):	10741.2	>	Design Factored Moment (kips-ft):	2794	Usage	0.26	OK!
Factor of Safety of Passive Soil Resistance against Moment:	3.84	OK!					

Check the capacities of Reinforcing Concrete:

Strength reduction factor (Flexure and axial tension):	0.90	Strength reduction factor (Shear):	0.75
Strength reduction factor (Axial compression):	0.65	Wind Load Factor on Concrete Design:	1.00

Reinforcing Concrete Pier:

Vertical Steel Rebar Area (sq. in./each):	1.27	Tie / Stirrup Area (sq. in./each):	0.20	Usage		
Calculated Moment Capacity (Mn, Kips-Ft):	7102.8	>	Design Factored Moment (Mu, K-Ft):	2377.4	0.33	OK!
Calculated Shear Capacity (Kips):	1120.9	>	Design Factored Shear (Kips):	217.0	0.19	OK!
Calculated Tension Capacity (Tn, Kips):	2331.7	>	Design Factored Tension (Tu Kips):	0.0	0.00	OK!
Calculated Compression Capacity (Pn, Kips):	9722	>	Design Factored Axial Load (Pu Kips):	79.9	0.01	OK!
Moment & Axial Strength Combination:	0.33	OK!	Max. Allowable Tie/Stirrup Spacing:	12.00	in.	
Pier Reinforcement Ratio:	0.008	Reinforcement Ratio is satisfied per ACI				





Mount Structural Analysis Report

Site Name: **CT13555-S Montano**
Site Number: **CT52XC103**
Project: **MIMO**

Prepared For: **Sprint**

Mount Description: **(3) Dual Sector Mounts**

Site Location: **58A Montano Rd
Glastonbury, CT
Hartford County
41.699444°, -72.5640°**

Design Codes: **ANSI/TIA-222-G
IBC 2012 w/ 2016 CT Building Code**

Analysis Load Case: **Sprint Final Configuration**

Analysis Result: **Adequate @ 94% - See Conclusion**



Revision 0
July 27, 2018

CT52XC103-PASSING-MOUNT-STRUCTURAL-ANALYSIS-07-27-18



1.0 Introduction

GeoStructural, LLC has completed a structural analysis for Sprint’s existing antenna mount assembly located at the CT13555-S Montano communications site in Hartford County, CT. The objective of the analysis was to determine the adequacy of the main mount assembly structural members to support Sprint’s final loading configuration. This analysis was completed at the request of ProTerra.

2.0 Analysis Procedure & Design Criteria

The mount structure has been analyzed to determine its compliance based on the minimum loading requirements of the following applicable building codes, design standards and design criteria:

- IBC 2012 – International Building Code w/ State Amendments and Adoptions.
- ANSI/TIA-222-G – Structural Standard for Antenna Supporting Structures and Antennas.
- AISC – Steel Construction Manual.
- ANSI/AWS D1.1 – Structural Welding Code.

Design Wind w/o ice = 125 mph (3-sec gust Ultimate Wind Speed per ASCE)	
Design Wind w/o ice = 97 mph (3-sec gust Equivalent per TIA-222-G Tower Code)	
Design Wind with ice = 50 mph (3-sec gust, 1" Ice)	Topographic Category 1
Exposure Category C	Structure Class II
Design Wind Force, $F_A = (q_z)(G_h)(EPA)_A$ [ANSI/TIA-222-G §2.6.9.2]	

The load effects due to factored loads and the strength level limit state load combinations of ANSI/TIA-222-G §2.3.2 have been evaluated and compared to the design strengths of the main mount structural members. The results of the analysis are illustrated in Sections 4.0 and 7.0. Refer to the Standard Conditions section of this report for information regarding the design criteria listed above.

All data required to complete our structural analysis was furnished by ProTerra. GeoStructural has not conducted a site visit or independent study to verify existing conditions and the results of this analysis are based solely on the information provided. The following documents were provided:

- | |
|---|
| <ul style="list-style-type: none"> • <u>Tower Structural Analysis</u>
TES, 09/29/15. • <u>Sprint – CT52XC103</u>
RFDS ID: 264749, Massive MIMO. |
|---|

If any of the existing or proposed conditions (appurtenance loading, member sizes, etc.) reported in this analysis are not properly represented, please contact our office immediately to request an amended report.

3.0 Appurtenance & Mount Information

Table 3.1 – Sprint Final Antenna Configuration^{1,2,3,4}

COR⁴	(Quantity) Appurtenance Make/Model	Mount Description
110'±	(3) NOKIA AAHC	(3) Dual Sector Mounts
	(1) 1'Ø Microwave w/ Radio	
	(2) 2.2'Ø Microwave w/ Radio	

1. *Proposed appurtenance and mount configurations are based on information obtained from the client. Refer to the Calculations & Software Output portion of this report for additional information regarding analysis loading.*
2. *Refer to antenna installation Construction Drawings (when applicable) for additional information regarding final antenna and equipment orientations. Refer to the Calculations & Software Output portion of this report for mount component member sizes and structural information.*
3. *Panel antennas to be installed in Position 1 and centered vertically on the face boom.*
4. *Microwave antennas to remain in their currently installed positions in Position 2.*

4.0 Analysis Results

Table 4.1 – Existing Mount Component Capacities

Load Case	Mount Component¹	% Capacity²	Result³
Final Sprint Configuration	Face Boom	94%	Adequate

1. *Refer to the Calculations & Software Output portion of this report for mount component member sizes and structural information.*
2. *Listed results are expressed as a percentage of available mount member capacity ($\Sigma\alpha Q_i / \Phi R_n$) based upon the material strengths listed in Table 4.2. 105% is an acceptable engineering allowable stress percentage for mount components.*
3. *Refer to the Calculations & Software Output portion of this report for main mount member factored load effects ($\Sigma\alpha Q_i$) and design strengths (ΦR_n).*

**Table 4.2 – Structural Component Material Strengths**

Structural Component	Nominal Strength/Material ¹
Pipe	$F_y = 35$ ksi (A53, Gr. B)
Tube	$F_y = 46$ ksi (A500, Gr. B)
Structural Shapes (L, C, W, etc.), Plate / Bar	$F_y = 36$ ksi (A36)
Uni-Strut	$F_y = 33$ ksi (A570, Gr. 33)
Connection Bolts	A325
Stainless Steel Bolts	18-8 Stainless, Grade 316/304 $F_y = 74$ ksi (Yield) & $F_u = 29$ ksi (Tension)
U-Bolts / Threaded Rod	SAE J429 Grade 2 (Substitution: ASTM A449) $F_y = 57$ ksi (Yield) & $F_u = 74$ ksi (Tension)
Welds	E70XX Electrodes

1. Strengths listed were assumed for this analysis and are based upon ASTM, AISC, RCSC, AWS and ACI preferred specification values. Values and materials are consistent with industry standards. Material strengths were taken from original design documents when available.

5.0 Conclusion & Recommendations

Based on Sprint's final equipment loading configuration, the existing mount assembly has sufficient capacity to support the loading considered in this analysis pursuant to the listed standards.

Installation Requirements:

- Antennas and equipment shall be installed centered vertically on the mount front face rails (limit vertical installation eccentricity).
- Panel antennas to be installed in Position 1.
- Microwave antennas to remain in their currently installed positions in Position 2.

Hoisting/Rigging and Maintenance Loading Note:

- This mount assembly is **not** rated for rigging, hoisting or worker maintenance loading of any kind. The results of this analysis assume no additional loading beyond the proposed final appurtenances is being applied to the mount structures. Hoisting/rigging or worker loading will create an overstress condition under design loading and is not allowed.

This analysis only encompasses the antenna mount assembly. The tower, overall mount support structure, foundation, etc. are beyond the scope of this analysis. If any of the existing or proposed conditions (appurtenance loading, member sizes, etc.) reported in this analysis are not properly represented, please contact our office immediately to request an amended report.

Prepared by:



Jesse Drennen, PE, MLE
208.761.7986
jesse.drennen@geostructural.com

Reviewed and Approved by:



Don George, PE, SE, MLSE
208.602.6569
don.george@geostructural.com



6.0 Standard Conditions

- All data required to complete our structural analysis was furnished by our client and provided record data. GeoStructural has not conducted a site visit or independent study to verify existing conditions and the results of this analysis are based solely on the information provided. It has been assumed that the tower, antenna support structure and foundation have been constructed according to the provided existing drawings, previous structural analysis reports, mapping documents, etc.
- The default Structure Classification is Class II in accordance with ANSI/TIA-222-G §A.2.2 & §A.15.3 and has been assumed for this analysis. The owner shall verify this classification conforms with original or desired reliability criteria.
- This analysis assumes that the structure has been properly installed and maintained in accordance with ANSI/TIA-222-G §15.5 and that no physical deterioration has occurred in any of the components of the structure. Damaged, missing, or rusted members were not considered.
- This analysis verifies the adequacy of the main components of the structure. Not all connections, welds, bolts, plates, etc. were individually detailed and analyzed. Where not specifically analyzed, the existing connection plates, welds, bolts, etc. were assumed adequate to develop the full capacity of the main structural members.
- No consideration has been made for unusual or extreme wind events, rime/in-cloud ice loadings, harmonic or nodal vibration, vortex shedding or other similar conditions.
- It is the owner's responsibility to determine the appropriate design wind speed and amount of ice accumulation beyond code minimum values that should be considered in the analysis.
- This analysis report does not constitute a maintenance and condition assessment. No certifications regarding maintenance and condition are expressed or implied. If desired, GeoStructural can provide these services under a subsequent contract.
- This analysis only encompasses the antenna mount assembly. The tower, overall mount support structure, foundation, etc. are beyond the scope of this analysis. If desired, GeoStructural can provide these services under a subsequent contract.



7.0 Attachments & Software Output

This Page Intentionally Left Blank



Envelope Only Solution

GeoStructural, LLC


Jesse Drennen, PE

CT52XC103


SK - 1

July 27, 2018 at 3:58 PM

CT52XC103_Mount Analysis_R0 1...




Code Check (Env)	
Black	No Calc
Red	> 1.0
Magenta	.90-1.0
Green	.75-.90
Cyan	.50-.75
Blue	0-.50




Member Code Checks Displayed (Enveloped)
Envelope Only Solution

GeoStructural, LLC	CT52XC103	SK - 2
Jesse Drennen, PE		July 27, 2018 at 3:58 PM
		CT52XC103_Mount Analysis_R0 1...



Shear Check
(Env)

- No Calc
- > 1.0
- .90-1.0
- .75-.90
- .50-.75
- 0-.50



Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

GeoStructural, LLC


Jesse Drennen, PE

CT52XC103


SK - 3

July 27, 2018 at 3:59 PM

CT52XC103_Mount Analysis_R0 1...




Section Sets	
PIPE_2.5	PIPE_2.5
HSS3.5x3.5x3	HSS3.5x3.5x3
WT6x2	WT6x2
3/8" x 6"	3/8" x 6"
RIGID	RIGID




Envelope Only Solution

GeoStructural, LLC	CT52XC103	SK - 4
Jesse Drennen, PE		July 27, 2018 at 3:59 PM
		CT52XC103_Mount Analysis_R0 1...





Material Sets	
■	RIGID
■	A36 Gr.36
■	A500 Gr.B Rect
■	A53 Gr.B



Envelope Only Solution

GeoStructural, LLC	CT52XC103	SK - 5
Jesse Drennen, PE		July 27, 2018 at 3:59 PM
		CT52XC103_Mount Analysis_R0 1...



Member Length (ft) Displayed
Envelope Only Solution

GeoStructural, LLC



Jesse Drennen, PE

CT52XC103

SK - 6

July 27, 2018 at 3:59 PM

CT52XC103_Mount Analysis_R0 1...



Member Length (ft) Displayed
 Loads: BLC 1, D
 Envelope Only Solution

GeoStructural, LLC



Jesse Drennen, PE

CT52XC103

SK - 7

July 27, 2018 at 3:59 PM

CT52XC103_Mount Analysis_R0 1...



Member Length (ft) Displayed
Loads: BLC 2, Di
Envelope Only Solution

GeoStructural, LLC



Jesse Drennen, PE

CT52XC103

SK - 8



July 27, 2018 at 3:59 PM

CT52XC103_Mount Analysis_R0 1...



Member Length (ft) Displayed
 Loads: BLC 5, Woz
 Envelope Only Solution

GeoStructural, LLC	CT52XC103	SK - 9
Jesse Drennen, PE		July 27, 2018 at 3:59 PM
		CT52XC103_Mount Analysis_R0 1...



Member Length (ft) Displayed
 Loads: BLC 6, Wox
 Envelope Only Solution

GeoStructural, LLC

Jesse Drennen, PE

CT52XC103

SK - 10

July 27, 2018 at 3:59 PM

CT52XC103_Mount Analysis_R0 1...

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...	Surface(P...
1	D	DL		-1		4			
2	Di	SL				4		6	
3	Lm [500]	LL				1			
4	Lv [250]	LL				2			
5	Woz	WL				4		6	
6	Wox	WL				4		6	
7	Wiz	WL				4		6	
8	Wix	WL				4		6	
9	Ez	EL				4			
10	Ex	EL				4			

Load Combination Design

	Description	ASIF	CD	Service	Hot Rol...	Cold Form...	Wood	Concrete	Masonry	Aluminum	Stainless	Connection
1	1) 1.4D				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
2	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
3	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
4	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
5	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
6	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
7	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
8	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
9	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
10	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
11	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
12	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
13	2) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
14	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
15	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
16	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
17	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
18	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
19	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
20	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
21	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
22	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
23	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
24	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
25	3) 0.9D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
26	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
27	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
28	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
29	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
30	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
31	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
32	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
33	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
34	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
35	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
36	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
37	4) 1.2D+1.0...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
38	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
39	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
40	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
41	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Load Combination Design (Continued)

	Description	ASIF	CD	Service	Hot Rol...	Cold Form...	Wood	Concrete	Masonry	Aluminum	Stainless	Connection
42	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
43	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
44	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
45	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
46	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
47	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
48	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
49	5) 1.2D+1.5L...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
50	6) 1.2D+1.5Lv				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
51	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
52	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
53	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
54	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
55	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
56	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
57	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
58	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
59	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
60	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
61	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
62	7) (1.2+0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
63	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
64	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
65	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
66	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
67	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
68	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
69	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
70	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
71	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
72	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
73	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
74	8) (0.9-0.2Sd...				Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm (1E...	Density[k/ft...	Yield[ksi]	Ry	Fu[ksi]	Rt
1	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
2	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
3	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A500 Gr.B RND	29000	11154	.3	.65	.49	42	1.4	58	1.3
5	A500 Gr.B Rect	29000	11154	.3	.65	.49	46	1.4	58	1.3
6	A53 Gr.B	29000	11154	.3	.65	.49	35	1.6	60	1.2
7	A500 Gr.B RND_1	29000	11154	.3	.65	.527	42	1.4	58	1.3
8	A500 Gr.B Rect_1	29000	11154	.3	.65	.527	46	1.4	58	1.3
9	A1085	29000	11154	.3	.65	.49	50	1.4	65	1.3

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design R...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	PIPE 1.5	PIPE 1.5	Beam	Pipe	A53 Gr.B	Typical	.749	.293	.293	.586
2	PIPE 2.0	PIPE 2.0	Beam	Pipe	A53 Gr.B	Typical	1.02	.627	.627	1.25
3	PIPE 2.5	PIPE 2.5	Beam	Pipe	A53 Gr.B	Typical	1.61	1.45	1.45	2.89
4	PIPE 3.0	PIPE 3.0	Beam	Pipe	A53 Gr.B	Typical	2.07	2.85	2.85	5.69
5	PIPE 3.5	PIPE 3.5	Beam	Pipe	A53 Gr.B	Typical	2.5	4.52	4.52	9.04
6	PIPE 4.0	PIPE 4.0	Beam	Pipe	A53 Gr.B	Typical	2.96	6.82	6.82	13.6

Hot Rolled Steel Section Sets (Continued)

	Label	Shape	Type	Design List	Material	Design R...	A [in ²]	Iyy [in ⁴]	Izz [in ⁴]	J [in ⁴]
7	PIPE 5.0	PIPE 5.0	Beam	Pipe	A53 Gr.B	Typical	4.01	14.3	14.3	28.6
8	HSS2x2x3	HSS2x2x3	Beam	Tube	A500 Gr.B R...	Typical	1.19	.641	.641	1.09
9	HSS3.5x3.5x3	HSS3.5x3.5x3	Beam	Tube	A500 Gr.B R...	Typical	2.24	4.05	4.05	6.56
10	HSS4x4x3	HSS4x4x3	Beam	Tube	A500 Gr.B R...	Typical	2.58	6.21	6.21	10
11	HSS4x4x4	HSS4x4x4	Beam	Tube	A500 Gr.B R...	Typical	3.37	7.8	7.8	12.8
12	HSS5x5x4	HSS5x5x4	Beam	Tube	A500 Gr.B R...	Typical	4.3	16	16	25.8
13	C3x3.5	C3x3.5	Beam	Channel	A36 Gr.36	Typical	1.09	.169	1.57	.023
14	C4x4.5	C4x4.5	Beam	Channel	A36 Gr.36	Typical	1.38	.289	3.65	.032
15	C5x6.7	C5x6.7	Beam	Channel	A36 Gr.36	Typical	1.97	.47	7.48	.055
16	L2.5x2.5x3	L2.5x2.5x3	Beam	Single Angle	A36 Gr.36	Typical	.901	.535	.535	.011
17	L2.5x2.5x4	L2.5x2.5x4	Beam	Single Angle	A36 Gr.36	Typical	1.19	.692	.692	.026
18	L3x3x3	L3x3x3	Beam	Single Angle	A36 Gr.36	Typical	1.09	.948	.948	.014
19	L3x3x4	L3x3x4	Beam	Single Angle	A36 Gr.36	Typical	1.44	1.23	1.23	.031
20	L3x3x6	L3x3x6	Beam	Single Angle	A36 Gr.36	Typical	2.11	1.75	1.75	.101
21	L3.5x3.5x4	L3.5x3.5x4	Beam	Single Angle	A36 Gr.36	Typical	1.7	2	2	.039
22	L4x4x4	L4x4x4	Beam	Single Angle	A36 Gr.36	Typical	1.93	3	3	.044
23	L5x3x6	L5x3x6	Beam	Single Angle	A36 Gr.36	Typical	2.86	2.01	7.35	.141
24	3/8"x2.5"	3/8"x2.5"	Beam	Single Angle	A36 Gr.36	Typical	.938	.011	.488	.04
25	1/2 x 6	1/2 x 6	Beam	BAR	A36 Gr.36	Typical	3	9	.063	.237
26	5/8SR	5/8SR	Beam	BAR	A36 Gr.36	Typical	.307	.007	.007	.015
27	LL2.5x2.5x3x3	LL2.5x2.5x3x3	Beam	Double Angle (3/8...	A36 Gr.36	Typical	1.8	2.46	1.07	.023
28	WT6x2	WT6x2	Beam	W Tee	A36 Gr.36	Typical	2.797	6.753	.967	.115
29	3/8" x 6"	3/8" x 6"	Beam	BAR	A36 Gr.36	Typical	2.25	.026	6.75	.101

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	M1	N1	N2		90	WT6x2	Beam	W Tee	A36 Gr.36	Typical
2	M2	N4	N3			HSS3.5x3.5x3	Beam	Tube	A500 Gr.B...	Typical
3	M3	N5	N1			3/8" x 6"	Beam	BAR	A36 Gr.36	Typical
4	M4	N6	N7			RIGID	None	None	RIGID	Typical
5	M5	N7	N8			RIGID	None	None	RIGID	Typical
6	M6	N9	N10			PIPE 2.5	Beam	Pipe	A53 Gr.B	Typical
7	M7	N5	N11			RIGID	None	None	RIGID	Typical
8	M8	N14	N2			3/8" x 6"	Beam	BAR	A36 Gr.36	Typical
9	M9	N15	N16			RIGID	None	None	RIGID	Typical
10	M10	N17	N18			RIGID	None	None	RIGID	Typical
11	M11	N19	N20			PIPE 2.5	Beam	Pipe	A53 Gr.B	Typical
12	M12	N14	N21			RIGID	None	None	RIGID	Typical

Envelope Joint Reactions


Joint		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC	
1	N4	max	.447	17	.893	32	.861	2	.115	14	.754	16	.358	11
2		min	-.447	11	.223	14	-.861	20	-1.27	32	-.737	10	-.118	29
3	Totals:	max	.447	17	.893	32	.861	2						
4		min	-.447	11	.223	14	-.861	20						

Envelope AISC 14th(360-10): LRFD Steel Code Checks

Member	Shape	Code Check	Loc[ft]	LC	Shear...Loc[ft]	Dir	LC	phi*Pnc...	phi*Pnt...	phi*Mn...	phi*Mn...	Cb	Eqn
1	M1	WT6x2	.936	2	.835	z	32	63.798	90.619	9.205	1.229	1...	H1-1b
2	M3	3/8" x 6"	.618	.75	.411	y	29	50.616	72.9	.57	9.113	1...	H1-1b
3	M8	3/8" x 6"	.292	.75	.295	y	5	50.616	72.9	.57	9.113	1...	H1-1b
4	M2	HSS3.5x3...	.149	0	.062	z	11	92.612	92.736	9.522	9.522	1...	H1-1b

Envelope AISC 14th(360-10): LRFD Steel Code Checks (Continued)


Member	Shape	Code Check	Loc[ft]	LC	Shear...	Loc[ft]	Dir	LC	phi*Pnc...	phi*Pnt...	phi*Mn...	phi*Mn...	Cb	Eqn
5	M6	PIPE 2.5	.097	3.75	31	.118	3.75	2	37.774	50.715	3.596	3.596	4...	H1-1b
6	M11	PIPE 2.5	.089	3.75	8	.011	3.75	8	37.774	50.715	3.596	3.596	2...	H1-1b



SITE NAME: CUTTER LANE
SITE NUMBER: CT52XC103
AUGMENT ID: CT-HFD0097Q17.1
SITE ADDRESS: 58A MONTANO ROAD
 GLASTONBURY, CT 06033
JURISDICTION: TOWN OF GLASTONBURY / CT SITING COUNCIL
SITE TYPE: EXISTING 119' MONOPOLE
PROGRAM: DO MACRO UPGRADE EQUIPMENT DEPLOYMENT



4 Bay Road, Building A
 Suite 200
 Hadley, MA 01031
 TEL: (508) 251-4918



PROJECT INFORMATION

SITE INFORMATION
 LATITUDE: 41° 41' 58.00" N (41.6994°)
 LONGITUDE: 72° 33' 50.40" W (-72.5640°)
 GROUND ELEVATION: 265'± AMSL (PER GOOGLE EARTH)
 STRUCTURE HEIGHT: 119'± AGL (FROM RECORD STRUCTURAL)
 STRUCTURE TYPE: MONOPOLE
 ZONING JURISDICTION: TOWN OF GLASTONBURY / CT SITING COUNCIL
 ZONING DISTRICT/OCCUPANCY: AA (RESIDENCE AA)
 COUNTY: HARTFORD

APPLICANT
 SPRINT
 1 INTERNATIONAL BLVD. SUITE 800
 MAHWAH, NJ 07495


PROPERTY OWNER:
 N/F ROSE MARIE SHAW
 58 MONTANO ROAD
 GLASTONBURY, CT 06033

TOWER OWNER:
 SBA TOWERS II LLC
 8051 CONGRESS AVENUE
 BOCA RATON, FL 33487
 (561) 995-7670


SBA SITE ID: CT13555-S
 SBA SITE NAME: MONTANO

SBA CONTACT:
 STEPHEN ROTH
 (860) 539-4920
 SROth@sbasite.com

LOCATION MAP N.T.S.



AREA MAP N.T.S.



DRAWING INDEX

SHEET NO.	SHEET DESCRIPTION	REV. NO.
T-1	TITLE SHEET	1
SP-1	OUTLINE SPECIFICATIONS	1
SP-2	OUTLINE SPECIFICATIONS	1
SP-3	OUTLINE SPECIFICATIONS	1
A-1	COMPOUND PLAN	1
A-2	ELEVATION AND ANTENNA PLANS	1
A-3	TOWER EQUIPMENT DETAILS	1
S-1	ANTENNA AND RRH MOUNTING DETAILS	1
S-2	EQUIPMENT DETAILS	1
E-1	ELECTRICAL AND GROUNDING DETAILS	1
E-2	ELECTRICAL AND GROUNDING DETAILS	1
RF-1	RF DATA SHEET	1
RF-2	PLUMBING DIAGRAM AND RAN WIRING	1

CODE COMPLIANCE

- 2016 CONNECTICUT STATE BUILDING CODE WITH AMENDMENTS.
- 2017 NATIONAL ELECTRICAL CODE WITH AMENDMENTS
- TIA-EIA-222-G

BASED ON INFORMATION PROVIDED BY SPRINT, THIS TELECOMMUNICATIONS EQUIPMENT DEPLOYMENT IS CONSIDERED AN ELIGIBLE FACILITY UNDER THE TAX RELIEF ACT OF 2012, 47 USC 1455(A), AND IS SUBJECT TO AN EXPEDITED ELIGIBLE FACILITIES REQUEST/REVIEW AND ZONING PRE-EMPTION FOR LOCAL DISCRETIONARY PERMITS (VARIANCE, SPECIAL PERMIT, SITE PLAN REVIEW).

APPROVALS

TITLE	SIGNATURE	DATE
PROJECT MANAGER:		
CONSTRUCTION:		
RF ENGINEER:		
ZONING/SITE ACQ:		
OPERATIONS:		
TOWER OWNER:		

THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.

SCOPE OF WORK

- REMOVE (1) EXISTING SPRINT (CLEARWIRE) TOWER TOP JUNCTION BOX.
- REMOVE EXISTING CABLING AND REPLACE WITH (1) HYBRID CABLE.
- REMOVE (3) EXISTING SPRINT (CLEARWIRE) PANEL ANTENNAS AND REPLACE WITH (3) NEW SPRINT PANEL ANTENNAS.
- REMOVE (3) EXISTING SPRINT (CLEARWIRE) RRHS.
- REMOVE EXISTING SPRINT (CLEARWIRE) EQUIPMENT CABINET AND REPLACE WITH NEW SPRINT EQUIPMENT CABINET.
- INSTALL NEW BATTERY PLINTH CABINET.
- REMOVE EXISTING SPRINT (CLEARWIRE) GPS ANTENNA AND REPLACE WITH NEW SPRINT GPS ANTENNA.
- INSTALL NEW SPRINT PPC MOUNTED TO A NEW H-FRAME.

GENERAL NOTES

- THIS IS AN UNMANNED TELECOMMUNICATION FACILITY AND NOT FOR HUMAN HABITATION:
 - ADA COMPLIANCE NOT REQUIRED.
 - POTABLE WATER OR SANITARY SERVICE IS NOT REQUIRED.
 - NO OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES REQUIRED.
- CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON JOB SITE. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. FAILURE TO NOTIFY THE ARCHITECT/ENGINEER PLACE THE RESPONSIBILITY ON THE CONTRACTOR TO CORRECT THE DISCREPANCIES AT THE CONTRACTOR'S EXPENSE.
- REFER TO THE ANTENNA MOUNT ANALYSIS PREPARED BY GEOSTRUCTURAL DATED JULY 27, 2018.

CALL CONNECTICUT ONE CALL
 (800) 922-4455
 CALL 3 WORKING DAYS
 BEFORE YOU DIG!



Know what's below.
 Call before you dig.
 www.call811.com

CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
 SITE NAME:
CUTTER LANE
 SITE ADDRESS:
 58A MONTANO ROAD
 GLASTONBURY, CT 06033

SHEET TITLE
 TITLE SHEET

SHEET NUMBER
 T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 1. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 2. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 3. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE - "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 4. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 5. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 6. AMERICAN CONCRETE INSTITUTE (ACI)
 7. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 8. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 9. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 10. PORTLAND CEMENT ASSOCIATION (PCA)
 11. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 12. BRICK INDUSTRY ASSOCIATION (BIA)
 13. AMERICAN WELDING SOCIETY (AWS)
 14. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 15. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 16. DOOR AND HARDWARE INSTITUTE (DHI)
 17. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 18. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER - ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

- A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
- B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
- C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.

1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

- A. TOP HAT
- B. HOW TO INSTALL A NEW CABINET
- C. BASE BAND UNIT IN EXISTING UNIT
- D. INSTALLATION OF BATTERIES
- E. INSTALLATION OF HYBRID CABLE
- F. INSTALLATION OF RRH'S
- G. CABLING
- H. TS-0200 REV 4 - ANTENNA LINE ACCEPTANCE STANDARDS
- I. SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1.
- J. COMMISSIONING MOPS
- K. SPRINT CELL SITE ENGINEERING NOTICE - EN-2013-002
- L. SPRINT ENGINEERING LETTER - EL-0504
- M. SPRINT ENGINEERING LETTER - EL-0568
- N. SPRINT TECHNICAL SPECIFICATION - TS-0193

1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

- A. CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 RECEIPT OF MATERIAL AND EQUIPMENT:

- A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
- B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 DELIVERABLES:

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 - CELL SITE CONSTRUCTION

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 NOTICE TO PROCEED:

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 FUNCTIONAL REQUIREMENTS:

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581 TEL: (508) 251-0720



4 Bay Road, Building A
Suite 200
Hadley, MA 01031 (413) 320-4918



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE

SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
OUTLINE SPECIFICATIONS

SHEET NUMBER
SP-1

CONTINUED FROM SP-1:

SECTION 01 400 - SUBMITTALS, TESTS, AND INSPECTIONS

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 SUBMITTALS:

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN.
- C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER SPRINT TS-0200 CURRENT VERSION ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD
 5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
 6. LIEN WAIVERS
 7. FINAL PAYMENT APPLICATION
 8. REQUIRED FINAL CONSTRUCTION PHOTOS
 9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
 10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPS

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPS

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY: WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.

1. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
2. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS:

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNALIGN ALIGNMENT TOOL (AAT)
 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- E. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- F. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.

3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.

A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.

1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING:
1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 500 - PROJECT REPORTING

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 WEEKLY REPORTS:

- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.

B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 PROJECT CONFERENCE CALLS:

- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 PROJECT TRACKING IN SMS:

- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

3.4 ADDITIONAL REPORTING:

- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 PROJECT PHOTOGRAPHS:

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 1. SHELTER AND TOWER OVERVIEW.
 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 5. PHOTOS OF TOWER SECTION STACKING.
 6. CONCRETE TESTING / SAMPLES.
 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 11. COAX CABLE ENTRY INTO SHELTER.
 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 25. ALL BTS GROUND CONNECTIONS.
 26. ALL GROUND TEST WELLS.
 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 30. GPS ANTENNAS.
 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 34. MASTER BUS BAR.
 35. TELCO BOARD AND NIU.
 36. ELECTRICAL DISTRIBUTION WALL.
 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 38. ENTRANCE TO EQUIPMENT ROOM.
 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
 41. ANTENNA AND MAST GROUNDING.
 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

SECTION 07 500 - ROOF CUTTING, PATCHING AND REPAIR

SUMMARY:

THIS SECTION SPECIFIES CUTTING AND PATCHING EXISTING ROOFING SYSTEMS WHERE CONDUIT OR CABLES EXIT THE BUILDING ONTO THE ROOF OR BUILDING-MOUNTED ANTENNAS, AND AS REQUIRED FOR WATERTIGHT PERFORMANCE. ROOFTOP ENTRY OPENINGS IN MEMBRANE ROOFTOPS SHALL BE CONSTRUCTED TO COMPLY WITH LANDLORD, ANY EXISTING WARRANTY, AND LOCAL JURISDICTIONAL STANDARDS.

1.4 SUBMITTALS:


- A. PRE-CONSTRUCTION ROOF PHOTOS: COMPLETE A ROOF INSPECTION PRIOR TO THE INSTALLATION OF SPRINT EQUIPMENT ON ANY ROOFTOP BUILD. AT A MINIMUM INSPECT AND PHOTOGRAPH (MINIMUM 3 EA.) ALL AREAS IMPACTED BY THE ADDITION OF THE SPRINT EQUIPMENT.
- B. PROVIDE SIMILAR PHOTOGRAPHS SHOWING ROOF CONDITIONS AFTER CONSTRUCTION (MINIMUM 3 EA.)
- C. ROOF INSPECTION PHOTOGRAPHS SHOULD BE UPLOADED WITH CLOSEOUT PHOTOGRAPHS.

SECTION 09 900 - PAINTING

QUALITY ASSURANCE:

- A. COMPLY WITH GOVERNING CODES AND REGULATIONS. PROVIDE PRODUCTS OF ACCEPTABLE MANUFACTURERS WHICH HAVE BEEN IN SATISFACTORY USE IN SIMILAR SERVICE FOR THREE YEARS. USE EXPERIENCED INSTALLERS. DELIVER, HANDLE, AND STORE MATERIALS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- B. COMPLY WITH ALL ENVIRONMENTAL REGULATIONS FOR VOLATILE ORGANIC COMPOUNDS.

CONTINUE SHEET SP-3



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE

SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
OUTLINE SPECIFICATIONS

SHEET NUMBER
SP-2

CONTINUED FROM SP-2:

MATERIALS:

- A. MANUFACTURERS: BENJAMIN MOORE, ICI DEVOE COATINGS, PPG, SHERWIN WILLIAMS OR APPROVED EQUAL. PROVIDE PREMIUM GRADE, PROFESSIONAL-QUALITY PRODUCTS FOR COATING SYSTEMS.

PAINT SCHEDULE:

- A. EXTERIOR ANTENNAE AND ANTENNA MOUNTING HARDWARE: ONE COAT OF PRIMER AND TWO FINISH COATS. PAINT FOR ANTENNAE SHALL BE NON-METALLIC BASED AND CONTAIN NO METALLIC PARTICLES. PROVIDE COLORS AND PATTERNS AS REQUIRED TO MASK APPEARANCE OF ANTENNAE ON ADJACENT BUILDING SURFACES AND AS ACCEPTABLE TO THE OWNER. REFER TO ANTENNA MANUFACTURER'S INSTRUCTIONS WHENEVER POSSIBLE.
- B. ROOF TOP CONSTRUCTION: TOUCH UP - PREPARE SURFACES TO BE REPAIRED. FOLLOW INDUSTRY STANDARDS AND REQUIREMENTS OF OWNER TO MATCH EXISTING COATING AND FINISH.

PAINTING APPLICATION:

- INSPECT SURFACES, REPORT UNSATISFACTORY CONDITIONS IN WRITING; BEGINNING WORK MEANS ACCEPTANCE OF SUBSTRATE.
- COMPLY WITH MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS FOR PREPARATION, PRIMING AND COATING WORK. COORDINATE WITH WORK OF OTHER SECTIONS.
- MATCH APPROVED MOCK-UPS FOR COLOR, TEXTURE, AND PATTERN. RE-COAT OR REMOVE AND REPLACE WORK WHICH DOES NOT MATCH OR SHOWS LOSS OF ADHESION.
- CLEAN UP, TOUCH UP AND PROTECT WORK.

TOUCHUP PAINTING:

- GALVANIZING DAMAGE AND ALL BOLTS AND NUTS SHALL BE TOUCHED UP AFTER TOWER ERECTION WITH "GALVANOX," "DRY GALV," OR "ZINC-IT."
- FIELD TOUCHUP PAINT SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.
- ALL METAL COMPONENTS SHALL BE HANDLED WITH CARE TO PREVENT DAMAGE TO THE COMPONENTS, THEIR PRESERVATIVE TREATMENT, OR THEIR PROTECTIVE COATINGS.

SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO HEADS AND CABLE INSTALLATION

SUMMARY:

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRH'S, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

ANTENNAS AND RRH'S:

THE NUMBER AND TYPE OF ANTENNAS AND RRH'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE:

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

JUMPERS AND CONNECTORS:

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRH'S AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRH'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE. DO NOT USE SUPERFLEX OUTDOORS. JUMPERS SHALL BE FACTORY FABRICATED IN APPROPRIATE LENGTHS WITH A MAXIMUM OF 4 FEET EXCESS PER JUMPER AND HAVE CONNECTORS AT EACH END, MANUFACTURED BY SUPPLIER. IF JUMPERS ARE FIELD FABRICATED, FOLLOW MANUFACTURER'S REQUIREMENTS FOR INSTALLATION OF CONNECTORS

REMOTE ELECTRICAL TILT (RET) CABLES:

MISCELLANEOUS:

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

ANTENNA INSTALLATION:

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

- A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.
- B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

HYBRID CABLES INSTALLATION:

- A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.
- C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.
 - FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE PERMANENTLY FASTENED TO THE COAX LADDER AT 4'-0" OC USING NON-MAGNETIC STAINLESS STEEL CLIPS.
 - FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBTS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
 - FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH @ 18" OC. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
 - DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
 - FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
 - CABLE INSTALLATION:
 - INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
 - CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS.
 - HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURERS RECOMMENDED MAXIMUM BEND RADIUS.

- GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
- HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED PER SPRINT TS 0200 CURRENT VERSION.
- HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE-EN 2012-001, REV 1

WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

- A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.
- B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.

- COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
- SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
- 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
- OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE.

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

DC CIRCUIT BREAKER LABELING

- A. LABEL CIRCUIT BREAKERS ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1.

SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE TRANSCIEVER STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

SUPPORTING DEVICES:

- A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
 - ALLIED TUBE AND CONDUIT
 - B-LINE SYSTEM
 - UNISTRUT DIVERSIFIED PRODUCTS
 - THOMAS & BETTS
- B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:
 - EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
 - POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
 - FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
 - TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
 - CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
 - MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
 - EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
 - DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
 - IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
- D. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
- E. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 - ELECTRICAL MATERIALS AND EQUIPMENT

CONDUIT:

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR ENCASED RUNS IN CONCRETE. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6- FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRE BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
 - CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL.
 - CABLE TERMINATORS FOR LFMC SHALL BE ETCO - CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKETED COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM AS INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS AS INDICATED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720



4 Bay Road, Building A
Suite 200
Hadley, MA 01031
TEL: (413) 320-4918



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ



SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE

SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
OUTLINE SPECIFICATIONS


SHEET NUMBER
SP-3



COMPOUND PLAN

SCALE: 1"=10' (11"x17")
1"=5' (22"x34")

1
A-1



1,4
S-2

REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) EQUIPMENT CABINET: INSTALL SPRINT EQUIPMENT CABINET ON BATTERY CABINET PLINTH

3,4
S-2

INSTALL SPRINT PPC CABINET ON H-FRAME

EXISTING CLEARWIRE EQUIPMENT CABINET TO BE REMOVED

EXISTING SPRINT (CLEARWIRE) JUNCTION BOX TO BE REMOVED, TYP.

REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) GPS

FEEDLINE SCHEDULE A AND B

2
A-2

EXISTING SPRINT (CLEARWIRE) ICE BRIDGE



INSTALL SPRINT BATTERY PLINTH CABINET ON EXISTING CONCRETE PAD

2,4
S-2

EXISTING SPRINT (CLEARWIRE) ICE BRIDGE

REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) GPS

EXISTING SPRINT (CLEARWIRE) ICE BRIDGE

2
A-2

FEEDLINE SCHEDULE A AND B

EXISTING SPRINT (CLEARWIRE) JUNCTION BOX TO BE REMOVED, TYP.

REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) GPS

REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) EQUIPMENT ON EXISTING CONCRETE PAD

ALL
S-2

EXISTING SPRINT (CLEARWIRE) 7'x7' LEASE AREA

1,4
S-2

REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) EQUIPMENT CABINET: INSTALL SPRINT EQUIPMENT CABINET ON BATTERY CABINET PLINTH

3,4
S-2

INSTALL SPRINT PPC CABINET ON H-FRAME

EXISTING CLEARWIRE EQUIPMENT CABINET TO BE REMOVED

2,4
S-2

INSTALL SPRINT BATTERY PLINTH CABINET ON EXISTING CONCRETE PAD




IMAGE SOURCE: PROTERRA 10/20/2017 (VIEW FROM SOUTHEAST)

EQUIPMENT PLAN PHOTO DETAIL

SCALE: N.T.S.

2
A-1

Sprint

1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641

SBA

SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720

ProTerra
DESIGN GROUP, LLC

4 Bay Road, Building A
Suite 200
Hadley, MA 01038
TEL: (413) 320-4918

STATE OF CONNECTICUT
THOMAS E. JOHNSON
No. 28192
LICENSED PROFESSIONAL ENGINEER
11/9/18

CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103

SITE NAME:
CUTTER LANE

SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
COMPOUND PLAN

SHEET NUMBER
A-1





IMAGE SOURCE: PROTERRA 10/20/2017

FEEDLINE SCHEDULE	FEEDLINE DESCRIPTION	LOCATION
A	EXISTING TO BE REMOVED: (3) 1/2" COAX, (3) 1/2" DC, AND (3) 1/2" HYBRID (PER COLO-APP) IN (2) FLEX CONDUIT TO 110' RAD EXISTING TO REMAIN: (1) 1/2" MICROWAVE DISH CABLE TO 110' RAD	UP INSIDE MONOPOLE TO RAD
B	PROPOSED: (1) HYBRID TRUNK MIMO TO 110' RAD;	UP INSIDE MONOPOLE TO RAD

TOWER ELEVATION PHOTO DETAIL
SCALE: N.T.S.



SPECIAL PRE-CONSTRUCTION WORK NOTE (SBA-PROVIDED TOWER STRUCTURAL ANALYSIS SPECIAL EQUIPMENT INSTALLATION REQUIREMENTS):
GENERAL CONTRACTOR SHALL FURNISH AND INSTALL ALL SPECIAL OR SUPPLEMENTAL ADDITIONAL TOWER-MOUNTED EQUIPMENT PER RECOMMENDATIONS FROM SBA-PROVIDED TOWER STRUCTURAL ANALYSIS FOR ANY SPECIAL SHIELDING OF TOWER TOP EQUIPMENT AND FOR ANY SPECIAL FEEDLINE BUNDLING OR RELOCATION.

EXISTING SPRINT MICROWAVE DISH TO REMAIN, TYP.
REMOVE AND REPLACE EXISTING SPRINT ANTENNA (LLPX310R), (TYP. OF 1 PER SECTOR, TOTAL OF 3)

NOTE:
REFER TO THE ANTENNA MOUNT ANALYSIS PREPARED BY GEOSTRUCTURAL DATED JULY 27, 2018.

ALL 1
S-1 A-3



REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) ANTENNA: INSTALL SPRINT MIMO ANTENNA [AAHC (64T64R)], (TYP. OF 1 PER SECTOR, TOTAL OF 3) MOUNTED TO ANTENNA MOUNTING PIPE



PROPOSED ANTENNA PLAN
SCALE: N.T.S.

SPECIAL INSTALLATION NOTE:
JUMPERS FROM RRHS TO ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY DISCREPANCY

NOTE:
VERIFY PROPOSED AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION



EXISTING ANTENNA PLAN
SCALE: N.T.S.

Sprint
1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641

SBA
SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720

ProTerra
DESIGN GROUP, LLC
4 Bay Road, Building A
Suite 200
Hadley, MA 01038
TEL: (413) 320-4918

STATE OF CONNECTICUT
THOMAS E. JOHNSON
No. 28192
LICENSED PROFESSIONAL ENGINEER
11/9/18

CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN


SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE
SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
ELEVATION AND ANTENNA PLANS

SHEET NUMBER
A-2


MIMO ANTENNA SPECIFICATIONS

MANUF.	NOKIA
MODEL #	2.5G MAA-AAHC(64T64R)
HEIGHT	25.6"
WIDTH	19.7"
DEPTH	9.6"
WEIGHT	103.7± LBS. (MOUNT BRACKETS NOT INCLUDED)



MIMO ANTENNA DETAIL

SCALE: N.T.S.




MAJOR RF EQUIPMENT LIST

(GC SHALL FURNISH AND INSTALL ALL OTHER MATERIALS AND EQUIPMENT NOT SUPPLIED BY SPRINT)

DESCRIPTION	QUANTITY	UNITS	MAKE/MODEL/MATERIAL	PROVIDED BY
ANTENNA	3	EA	2.5G MAA-AAHC(64T64R)	SPRINT
HYBRID TRUNK MIMO	1 @ 170'± FROM FIBER CABINET	LINEAR FEET LISTED [INCLUDES (2) 10' COILS]	NOKIA HYBRID	SPRINT
EQUIPMENT CABINET	1	EA	NOKIA 9712 LRO-21U	SPRINT
BATTERY CABINET	1	EA	NOKIA 3JR50450ABAA	SPRINT
PPC/TELCO CABINET	1	EA	PURCELL SYSTEMS, INC. (VERIFY MODEL WITH SPRINT)	SPRINT

SPRINT-PROVIDED EQUIPMENT SCHEDULE

SCALE: N.T.S.



HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE

MANUF: RFS
CABLE LENGTH DC CONDUCTOR CABLE DIAMETER


FIBER ONLY	LENGTH	DC CONDUCTOR	CABLE DIAMETER
HYBRIFLEX	<200'	8 AWG	1-1/4"
HYBRIFLEX	225-300'	6 AWG	1-1/4"
HYBRIFLEX	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-05CF 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft	
	MN: HB058-M12-075F	75 ft	
	MN: HB058-M12-10CF	100 ft	
	MN: HB058-M12-125F	125 ft	
	MN: HB058-M12-15CF	150 ft	
	MN: HB058-M12-175F	175 ft	
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft	
	MN: HB114-08U3M12-075F	75 ft	
	MN: HB114-08U3M12-100F	100 ft	
	MN: HB114-08U3M12-125F	125 ft	
	MN: HB114-08U3M12-150F	150 ft	
	MN: HB114-08U3M12-175F	175 ft	
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft	
	MN: HB114-13U3M12-250F	250 ft	
	MN: HB114-13U3M12-275F	275 ft	
	MN: HB114-13U3M12-300F	300 ft	
	4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
		MN: HB114-21U3M12-350F	350 ft
MN: HB114-21U3M12-375F		375 ft	


RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY		
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY		
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY		
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY		




2.5 HYBRID CABLE X-SECTION AND DATA

SCALE: N.T.S.



* NOTE: SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ


SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE
SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
**TOWER EQUIPMENT
DETAILS**

SHEET NUMBER
A-3



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:

CT52XC103

SITE NAME:

CUTTER LANE

SITE ADDRESS:


58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE

ANTENNA AND RRH MOUNTING DETAILS


SHEET NUMBER

S-1



1
A-3
REMOVE AND REPLACE EXISTING SPRINT (CLEARWIRE) ANTENNA: INSTALL SPRINT MIMO ANTENNA [AAHC (64T64R)], (TYP. OF 1 PER SECTOR, TOTAL OF 3) MOUNTED TO ANTENNA MOUNTING PIPE

2
S-1
ANTENNA AND RRH MOUNT PHOTO DETAIL
SCALE: N.T.S.



SPECIAL TOWER TOP EQUIPMENT INSTALLATION WORK NOTE (SAFETY-CLIMB ALIGNMENT REQUIREMENTS):
GENERAL CONTRACTOR SHALL ORIENT PROPOSED SPRINT COLLAR-MOUNTS SO THAT EXISTING SAFETY CLIMB CABLE IS NOT OBSTRUCTED/RE-ROUTED FROM VERTICAL ALIGNMENT AND IS NOT IN PHYSICAL CONTACT WITH EXISTING OR PROPOSED COLLAR-MOUNT HARDWARE. GENERAL CONTRACTOR SHALL INSTALL NEW OR ADDITIONAL SAFETY-CLIMB CABLE GUIDES IF ADDITIONAL CLEARANCE IS REQUIRED. ADDITIONAL CABLE GUIDES SHALL BE ATTACHED SECURELY TO THE POLE USING MECHANICAL FASTENERS OR FIELD WELDED BY A CERTIFIED WELDING TECHNICIAN.

800MHZ/1900MHZ ANTENNA AND RRH MOUNTING DETAIL


SCALE: N.T.S.

1
S-1

NOTE:
REFER TO THE ANTENNA MOUNT ANALYSIS PREPARED BY GEOSTRUCTURAL DATED JULY 27, 2018.


SPECIAL PRE-CONSTRUCTION WORK NOTE (SBA-PROVIDED TOWER STRUCTURAL ANALYSIS SPECIAL EQUIPMENT INSTALLATION REQUIREMENTS):
GENERAL CONTRACTOR SHALL FURNISH AND INSTALL ALL SPECIAL OR SUPPLEMENTAL ADDITIONAL TOWER-MOUNTED EQUIPMENT PER RECOMMENDATIONS FROM SBA-PROVIDED TOWER STRUCTURAL ANALYSIS FOR ANY SPECIAL SHIELDING OF TOWER TOP EQUIPMENT AND FOR ANY SPECIAL FEEDLINE BUNDLING OR RELOCATION.

EQUIPMENT CABINET	
MANUF.	NOKIA
MODEL #	9712 LRO-21U
HEIGHT	41"
WIDTH	25.6"
DEPTH	29.6"
WEIGHT	206 LBS. (EMPTY)



ANCHOR EQUIPMENT CABINET TO THE BATTERY CABINET PLINTH WITH MANUFACTURER SUPPLIED HARDWARE, (TOTAL OF 4)

BATTERY CABINET	
MANUF.	NOKIA
MODEL #	9712 BATTERY PLINTH (3JR50450ABAA)
HEIGHT	37.7"
WIDTH	25.6"
DEPTH	29.3"
WEIGHT	91 LBS. (EMPTY)



ANCHOR BATTERY CABINET TO CONCRETE PER MANUFACTURER SPECIFICATIONS OR MINIMUM OF 1/2" HDG HILTI KWIK BOLT SS 304 2 3/4" LONG WITH 2 1/4" NOMINAL EMBEDMENT PER CABINET, (TOTAL OF 4)

EQUIPMENT CABINET DETAIL


SCALE: N.T.S.

1
S-2

BATTERY CABINET DETAIL

SCALE: N.T.S.

2
S-2




PPC CABINET

MANUF.	PURCELL SYSTEMS, INC.
MODEL #	PPC (VERIFY WITH SPRINT MODEL)
HEIGHT	36"
WIDTH	26"
DEPTH	12.2"
WEIGHT	67± LBS

PPC DETAIL

SCALE: N.T.S.


3
S-2



GROUND LEVEL EQUIPMENT PLAN

SCALE: N.T.S.

4
S-2



PPC H-FRAME MOUNTING DETAIL

SCALE: N.T.S.

5
S-2




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720



4 Bay Road, Building A
Suite 200
Hadley, MA 01031
TEL: (413) 320-4918



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:

CT52XC103

SITE NAME:

CUTTER LANE

SITE ADDRESS:

58A MONTANO ROAD
GLASTONBURY, CT 06033


SHEET TITLE

EQUIPMENT
DETAILS

SHEET NUMBER

S-2





SYMBOL LEGEND

(X)	SPECIAL WORK NOTE
■	EXOTHERMIC CONNECTION
●	MECHANICAL CONNECTION
□	CABLE GROUNDING KIT

- ELECTRICAL NOTES**
- 1) ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
 - 2) THE ELECTRICAL CONTRACTOR SHALL COORDINATE ALL CONDUIT ROUTING WITH LOCAL UTILITY COMPANIES AND SPRINT CONSTRUCTION MANAGER.
 - 3) ALL CONDUITS ROUTED BELOW GRADE SHALL TRANSITION TO RIGID GALVANIZED ELBOWS WITH RIGID GALVANIZED STEEL CONDUIT ABOVE GRADE.
 - 4) ALL METAL CONDUITS SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
 - 5) GENERAL CONTRACTOR SHALL PROVIDE ALL DIRECT BURIED CONDUITS WITH PLASTIC WARNING TAPE IDENTIFYING CONTENTS. TAPE COLORS SHALL BE ORANGE FOR TELEPHONE AND RED FOR ELECTRIC.
 - 6) ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
 - 7) THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIALS DESCRIBED BY DRAWINGS AND SPECIFICATIONS INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM.
 - 8) GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND IS RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS.
 - 9) ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
 - 10) BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
 - 11) ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THIN INSULATION.
 - 12) RUN ELECTRICAL CONDUIT OR CABLE BETWEEN ELECTRICAL UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE PPC AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE. COORDINATE INSTALLATION WITH UTILITY COMPANY.
 - 13) RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
 - 14) FIBER OPTIC CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 770-OPTICAL FIBER CABLES AND RACEWAYS.
 - 15) COMMUNICATIONS CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 800-COMMUNICATIONS SYSTEMS.


IMPORTANT: VELCRO STRAPS ONLY MAY BE USED ON FIBER, CABLE TIES OR TIE WRAP MUST NOT BE USED ON FIBER

TYPICAL POWER AND GROUNDING ONE LINE DIAGRAMS

SCALE: N.T.S.

1
E-1

- SPECIAL WORK NOTE:**
1. G.C. TO FURNISH AND INSTALL ALL COMPONENTS TO UPGRADE EXISTING ELECTRICAL SERVICE, CONDUIT, CONDUCTOR, PPC AND MCB IN ACCORDANCE WITH SPRINT CONSTRUCTION STANDARDS NV 2.5 ADDENDUM "ENGINEERING NOTICE 2013-002 (POWER UPGRADES) REV.0" (OR CURRENT VERSION)
 2. G.C. TO FURNISH AND INSTALL UPGRADE THE EXISTING MMBTS BREAKER, CONDUCTOR, AND CONDUIT TO A MINIMUM NEC RATING.
 3. FOR NEW OR REPAIRED GROUNDING EQUIPMENT, REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):
 -ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-12 (OR CURRENT VERSION)
 -SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION).



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS


REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE

SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
ELECTRICAL AND GROUNDING DETAILS

SHEET NUMBER
E-1



SYMBOL LEGEND

- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- CABLE GROUNDING KIT
- GROUNDING/BONDING
- CONDUIT

UNLESS NOTED OTHERWISE, ALL BONDING CONDUCTORS ARE #2 SOLID TINNED BCW.

NOTE: EXISTING NV EQUIPMENT CONDUITS NOT SHOWN FOR CLARITY. REFER TO RECORD AS-BUILT NV PHOTOS AND NV AS-BUILT DRAWINGS


NOTE: HYBRIFLEX (FIBER & POWER) AND HYBRIFLEX (FIBER-ONLY) SHOWN. REFER TO RAN EQUIPMENT RFDS FOR SITE-SPECIFIC SCENARIO.

RAN EQUIPMENT GROUNDING SCHEMATIC

SCALE: N.T.S.

1
E-2

- PROTECTIVE GROUNDING SYSTEMS GENERAL NOTES:**
- GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250-GROUNDING AND BONDING.
 - GROUNDING SHALL BE IN ACCORDANCE WITH SPRINT SSEO DOCUMENTS 3.018.02.004 "BONDING, GROUNDING AND TRANSIENT PROTECTION FOR CELL SITES" AND 3.018.10.002 "SITE RESISTANCE TO EARTH TESTING".
 - PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
 - GROUND CONNECTIONS: CLEAN SURFACES THOROUGHLY BEFORE APPLYING GROUND LUGS OR CLAMPS. IF SURFACE IS COATED, REMOVE THE COATING, APPLY A NON-CORROSIVE APPROVED COMPOUND TO CLEAN SURFACE AND INSTALL LUGS OR CLAMPS. WHERE GALVANIZING IS REMOVED FROM METAL, IT SHALL BE PAINTED OR TOUCHED UP WITH "GALVAMOX" OR EQUAL.
 - ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
 - ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
 - ALL GROUND WIRES SHALL BE #2 SOLID TINNED BCW UNLESS NOTED OTHERWISE.
 - PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
 - GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
 - EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 SOLID TINNED BCW EQUIPMENT CABINETS WALL HAVE (2) CONNECTIONS.
 - GROUND HYBRIFLEX SHIELD AT TOP, BOTTOM AND AT TRANSITION TO HYBRIFLEX JUMPER CABLES AT EQUIPMENT CABINET ENTRANCE USING MANUFACTURER'S GUIDELINES. WHEN HYBRIFLEX CABLE EXCEEDS 200', GROUND AT INTERVALS NOT EXCEEDING 100'.
 - THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
 - EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL OTHERWISE. THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES, LONG BARREL LUGS OR DOUBLE CRIMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH AN ANTI-OXIDANT (THOMAS BETTS KOPR-SHILD) BEFORE MAKING THE CRIMP CONNECTIONS THE CONTRACTOR SHALL FOLLOW MANUFACTURER'S RECOMMENDED TORQUES ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS.
 - AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING, CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
 - THE MASTER GROUND BAR (MGB) SHALL BE MADE OF BARE 1/4"x2" COPPER (FOR OUTDOOR APPLICATIONS IT SHALL BE TINNED COPPER) AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE SECURING THE MGB SHALL ELECTRICAL INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENED.
 - ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
 - ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH SPRINT CONSTRUCTION MANAGER.
 - FOR NEW OR REPAIRED GROUNDING EQUIPMENT. REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):
-ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-12 (OR CURRENT VERSION)
-SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION)




- APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
- IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR

SCALE: N.T.S.

2
E-2



TWO HOLE LUG

SCALE: N.T.S.

3
E-2

Sprint

1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641

SBA

SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720

ProTerra
DESIGN GROUP, LLC

4 Bay Road, Building A
Suite 200
Hadley, MA 01031
TEL: (413) 320-4918

STATE OF CONNECTICUT
THOMAS E. JOHNSON
No. 28192
PROFESSIONAL ENGINEER
FOR SCHEMATIC 10/18/18

CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE

SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
ELECTRICAL AND GROUNDING DETAILS

SHEET NUMBER
E-2



RF Design Sheet

Site Identification	
Cascade	CT-HFD0097
SMS Schedule ID	
SMS Schedule Name	Massive MIMO
PID	
RRU OEM	Alcatel Lucent
Switch OEM	
RFDS Issue Date	2018-06-04 13:49:15.0
RFDS Revision Date	2018-06-08 19:38:48.0
RFDS Revision	1

Filter Analysis Complete	YES
RFDS - Issue Date	06/04/2018
Design Status	Complete
Project Description	Massive MIMO - Separated from KSU Augment

Battery Backup Cabinet Model	
Model Number	
Weight (Lbs.)	
Dimensions (In.)	
Manufacturer	

A&E Drawing Requirements	
Massive MIMO - Separated from KSU Augment	

Contact Information	
Engineer Email	Bill.M.Hastings@sprint.com
Sprint Badged RF Engineer	Bill Hastings
RF Engineer Email	Bill.M.Hastings@sprint.com
RF Engineer Phone	978-590-9700
RF Manager	Jonathan Hull
RF Manager Email	Jonathan.B.Hull@sprint.com
RF Manager Phone	617-233-2920

Carrier Count	
2500 LTE	3
1900 LTE	
1900 EVDO	
1900 Voice	
800 LTE	
800 Voice	

UE Relay Model	
Model Number	
Weight (Lbs.)	
Dimensions (In.)	
UE Relay Azimuth	
Manufacturer	
UE Relay CL Height (meters)	

Location Details	
Latitude	41.699453
Longitude	-72.564172
Market	Northern Connecticut
Region	Northeast
City	GLASTONBURY
State	CT
Zip Code	CT06033
County	HARTFORD

2500MHz	3
1900MHz	
800MHz	

GPS Antenna Model	
Model Number	
Weight (Lbs.)	
Dimensions (In.)	
Manufacturer	
GPS Antenna needed at site	

SPRINT CONSTRUCTION STANDARDS:

GENERAL CONTRACTOR SHALL ADHERE TO THE FOLLOWING SPRINT CONSTRUCTION STANDARDS.

- CONSTRUCTION STANDARDS: INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES - CURRENT VERSION, INCLUDING EXHIBITS A-M.
 - CONSTRUCTION SPECIFICATIONS: CONSTRUCTION STANDARDS EXHIBIT A - STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES (CURRENT VERSION).
 - GROUNDING STANDARDS: EXTERIOR GROUNDING SYSTEM DESIGN. GROUNDING STANDARDS (SUPPLEMENT): ANTI-THEFT UPDATE TO SPRINT GROUNDING 082412 AND SPRINT ENGINEERING LETTER EL-0504 DATED 04.20.12.
 - WEATHER PROOFING STANDARDS: EXCERPT FROM CONSTRUCTION STANDARDS EXHIBIT A, SECTION 3.6 WEATHERPROOFING CONNECTORS AND GROUND KITS.
 - COLOR CODING: SPRINT NEXTEL ANT AND LINE COLOR CODING PER SPRINT TS-0200 CURRENT VERSION.
 - GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND CL HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT IN RFDS, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING SPRINT-PROVIDED CONTACT INFORMATION FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE ANTENNA AT SAME CL HEIGHT AS PLAN AND EMAIL CORRECT CL HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILT DRAWING WITH CORRECT CL HEIGHT. ALSO EMAIL CORRECT ANTENNA CL HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
 - AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5G. TEST INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
 - GENERAL CONTRACTOR MUST INSURE THAT NO OBJECT IS LOCATED IN FRONT OF ANTENNA. THIS MEANS NO OBJECT IS TO BE LOCATED 45 DEGREES LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION.
 - GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREES. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL.
- HTTP://WWW.3ZTELECOM.COM/ANTENNA-ALIGNMENT-TOOL/.

NOTE:
VERIFY PROPOSED AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION


Band: 2500	Alpha	Beta	Gamma	Delta	Epsilon	Zeta
Radio Model						
Model Number	Nokia MIMO Integrated Radio/Antenna	Nokia MIMO Integrated Radio/Antenna	Nokia MIMO Integrated Radio/Antenna	N/A	N/A	N/A
Weight (lbs)	N/A	N/A	N/A	N/A	N/A	N/A
Dimensions	Refer to Antenna model for details	Refer to Antenna model for details	Refer to Antenna model for details	N/A	N/A	N/A
Manufacturer	Nokia	Nokia	Nokia	N/A	N/A	N/A
Number of RRUs needed	1	1	1	0	0	0

Band: 2500	Alpha	Beta	Gamma	Delta	Epsilon	Zeta
Antenna1						
Model Number	AAHC	AAHC	AAHC			
Weight (lbs)	103.7	103.7	103.7	N/A	N/A	N/A
Dimensions	25.6 x 19.7 x 9.64	25.6 x 19.7 x 9.64	25.6 x 19.7 x 9.64	N/A	N/A	N/A
Manufacturer	Nokia	Nokia	Nokia	N/A	N/A	N/A
Ant1 Top Jumper Make/Model/Qty	N/A	N/A	N/A	N/A	N/A	N/A
Ant 1 RF requested Diameter	N/A	N/A	N/A	N/A	N/A	N/A
Ant 1 RF requested Top Jumper Length(ft)	N/A	N/A	N/A	N/A	N/A	N/A
Antenna 1 Azimuth	0	120	240	N/A	N/A	N/A
Antenna 1 Mechanical DT	N/A	N/A	N/A	N/A	N/A	N/A
Antenna 1 Center Line (ft)	110.0065652	110.0065652	110.0065652	N/A	N/A	N/A
Antenna 1 Electrical DT	2	2	2	N/A	N/A	N/A
Antenna 1 Electrical DT 2	N/A	N/A	N/A	N/A	N/A	N/A
Antenna 1 Electrical DT 3	N/A	N/A	N/A	N/A	N/A	N/A
Antenna 1 Twist	N/A	N/A	N/A	N/A	N/A	N/A

NOTE: RFDS PROVIDED BY SPRINT DATED 06/04/2018. EXCERPTS TAKEN DEPICT RELEVANT RF DESIGN INFORMATION. A&E VENDOR SCOPE OF WORK LIMITED TO DESIGN OF MECHANICAL/STRUCTURAL EQUIPMENT ATTACHMENTS.

RF DATA SHEET

SCALE: N.T.S.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581 TEL: (508) 251-0720



4 Bay Road, Building A
Suite 200
Hadley, MA 01031 (413) 320-4918



CHECKED BY: JMM/TEJ

APPROVED BY: JMM/TEJ

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE
SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033




SHEET TITLE
RF DATA SHEET

SHEET NUMBER
RF-1

Prepared By Mark Elliott	Revision Date April 4, 2018	Revision Number R1
Approved By RAN Hardware & Antenna Teams	Approval Date Final-Macro Generated	




ALU mMIMO



Not to Scale

© Copyright Sprint 2018 - All Rights Reserved. Sprint Proprietary - For Internal Use Only. Unauthorized Disclosure Prohibited.


Nokia-A Site Upgrade: Adding 2500 and Second 800 RRH



2500 Radio 1	COLOR
YEL WHT	GRN
YEL WHT	BLU
YEL WHT	BRN
YEL WHT	WHT
YEL WHT	RED
YEL WHT	SLT
YEL WHT	PPL
YEL WHT	ORG

HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

BAND	INDICATOR	PORT	COLOR
800-1	YEL GRN	NV-1	GRN
1900-1	YEL RED	NV-2	BLU
1900-2	YEL BRN	NV-3	BRN
1900-3	YEL BLU	NV-4	WHT
1900-4	YEL SLT	NV-5	RED
800-2	YEL ORG	NV-6	SLT
SPARE	YEL WHT	NV-7	PPL
2500	YEL PPL	NV-8	ORG






Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
1	2	Blue	No Tape	No Tape
1	3	Brown	No Tape	No Tape
1	4	White	No Tape	No Tape
1	5	Red	No Tape	No Tape
1	6	Grey	No Tape	No Tape
1	7	Purple	No Tape	No Tape
1	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
2	2	Blue	Blue	No Tape
2	3	Brown	Brown	No Tape
2	4	White	White	No Tape
2	5	Red	Red	No Tape
2	6	Grey	Grey	No Tape
2	7	Purple	Purple	No Tape
2	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
3	2	Blue	Blue	Blue
3	3	Brown	Brown	Brown
3	4	White	White	White
3	5	Red	Red	Red
3	6	Grey	Grey	Grey
3	7	Purple	Purple	Purple
3	8	Orange	Orange	Orange

SPECIAL WORK NOTE:
CPRI BLOCK DIAGRAM SHOWN IS FOR SCHEMATIC ONLY. CONFIRM CPRI BLOCK WIRING DIAGRAM WITH THE CONSTRUCTION MANAGER PRIOR TO INSTALLATION.

- NOTES:
- ALL CABLES SHALL BE MARKED AT THE TOP AND BOTTOM WITH 2" COLORED TAPE, STENCIL TAG COLORED TAPE, OR COLORED HEAT SHRINK TUBING
 - COLORED TAPE MAY BE OBTAINED FROM GRAYBAR ELECTRONIC. UV STABILIZED TAPE OR HEAT SHRINK ARE PREFERRED.
 - THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE, AND THERE SHALL BE A 1" SPACE BETWEEN EACH RING.
 - THE CABLE COLOR CODE SHALL BE APPLIED IN ACCORDANCE TO TABLE 19-1.
 - TABLE 19-1 ONLY SHOWS 3 SECTORS, BUT ADDITIONAL SECTORS ARE EASILY SUPPORTED BY ADDING THE APPROPRIATE NUMBER OF COLORED RINGS TO THE CABLE COLOR CODE.
 - AFTER THE CABLE COLOR CODE IS APPLIED, THE FREQUENCY COLOR CODE, TABLE 19-2, MUST BE APPLIED FOR THE SPECIFIC FREQUENCY BAND IN USE ON A GIVEN LINE.
 - 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE.
 - THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
 - WRAP 2" COLORED TAPE A MINIMUM OF 3 TIMES AROUND THE COAX, AND KEEP THE TAPE IN THE SAME AREA AS MUCH AS POSSIBLE. THIS WILL ALLOW REMOVAL OF TAPE THAT FADES OR DISCOLORS DUE TO WEATHER.
 - EXAMPLES OF THE CABLE AND FREQUENCY COLOR CODES ARE SHOWN IN FIGURE 19-1 AND FIGURE 19-2.

NV FREQUENCY	INDICATOR	ID	2.5 FREQUENCY	INDICATOR	ID
800-1	YEL	GRN	2500-1	YEL	GRN
1900-1	YEL	RED	2500-2	YEL	RED
1900-2	YEL	BRN	2500-3	YEL	BRN
1900-3	YEL	BLU	2500-4	YEL	BLU
1900-4	YEL	SLT	2500-5	YEL	SLT
800-1	YEL	ORG	2500-6	YEL	ORG
RESERVED	YEL	WHT	2500-7	YEL	WHT
RESERVED	YEL	PPL	2500-8	YEL	PPL



Sprint
1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641

SBA
SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720

ProTerra
DESIGN GROUP, LLC
4 Bay Road, Building A
Suite 200
Hadley, MA 01031
TEL: (413) 320-4918

STATE OF CONNECTICUT
THOMAS E. JOHNSON
No. 28192
LICENSED PROFESSIONAL ENGINEER
11/9/18

CHECKED BY: JMM/TEJ
APPROVED BY: JMM/TEJ

REV.	DATE	DESCRIPTION	BY
1	11/09/18	CONSTRUCTION REVISED	PN
0	07/27/18	ISSUED FOR CONSTRUCTION	PN

SITE NUMBER:
CT52XC103
SITE NAME:
CUTTER LANE
SITE ADDRESS:
58A MONTANO ROAD
GLASTONBURY, CT 06033

SHEET TITLE
PLUMBING DIAGRAM AND RAN WIRING

SHEET NUMBER
RF-2