



CT33XC563

February 6, 2014

David Martin and
Members of the Siting Council
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

RE: Notice of Exempt Modification
15 North Granby Road
Granby, CT 06035
N 41° 57' 12.89"
W -72° 47' 37.44"

Dear Mr. Martin and Members of the Siting Council:

On behalf of Sprint Spectrum, SBA Communications is submitting an exempt modification application to the Connecticut Siting Council for modification of existing equipment at a tower facility located at 15 North Granby Road, Granby, CT.

The 15 North Granby Road facility consists of a 150' MONOPOLE Tower owned and operated by SBA Properties, LLC. In order to accommodate technological changes and enhance system performance in the State of Connecticut, Sprint Spectrum plans to modify the equipment configurations at many of its existing cell sites. Please accept this letter and attachments as notification, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter and attachments is being sent to the chief elected official of the municipality in which the affected cell site is located.

As part of Sprint's Network Vision modification project, Sprint desires to upgrade their equipment to meet the new standards of 4G technology. The new equipment will allow customers to download files and browse the internet at a high rate of speed while also allowing their phones to be compatible with the latest 4G technology.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site along with the required fee of \$625.

The changes to the facility do not constitute modifications as defined in Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be

significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2).

1. The overall height of the structure will be unaffected.
2. The proposed changes will not extend the site boundaries. There will be no effect on the site compound other than the new equipment cabinets.
3. The proposed changes will not increase the noise level at the existing facility by six decibels or more.
4. The changes in radio frequency power density will not increase the calculated “worst case” power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.

For the foregoing reasons, SBA Communications on behalf of Sprint Spectrum, respectfully submits that he proposed changes at the referenced site constitute exempt modifications under R.C.S.A. Section 16-50j-72(b)(2).

Please feel free to call me at (508) 251-0720 x 302 with any questions you may have concerning this matter.

Thank you,

Kri Pelletier
SBA Communications Corporation
33 Boston Post Road West Suite 320
Marlborough, MA 01752
508-251-0720 x 302 + T
508-251-1755 + F
203-446-7700 + C
kpelletier@sbsite.com



Sprint Spectrum Equipment Modification

15 North Granby Road, Granby, CT
Site number CT33XC563

Tower Owner: SBA Properties, LLC

Equipment Configuration: MONOPOLE Tower

Current and/or approved:

- (9) Andrew DB844H90E-XY
- (9) 1-1/4" Lines
- (3) RFS APXVSP18-C-A20
- (3) Alcatel Lucent 1900 MHz RRUs
- (3) Alcatel Lucent 800 MHz RRUs
- (3) Alcatel Lucent 800 MHz Filters
- (4) RFS ACU-A20-N RETs
- (3) 1-1/4" Fiber

Planned Modifications:

- (3) RFS APXVTM14-C-120
- (3) RFS APXVSP18-C-A20
- (3) Alcatel Lucent 1900 MHz RRUs
- (3) Alcatel Lucent 800 MHz RRUs
- (3) Alcatel Lucent 800 MHz Filters
- (4) RFS ACU-A20-N RETs
- (3) Alcatel Lucent TD-RRH8x20-25 RRUs
- (3) 1-1/4" Fiber
- (1) 0.7" Fiber Cable

Structural Information:

The attached structural analysis demonstrates that the tower and foundation will have adequate structural capacity to accommodate the proposed modifications.

Power Density:

The anticipated Maximum Composite contributions from the Sprint facility are 25.842% of the allowable FCC established general public limit. The anticipated composite MPE value for this site assuming all carriers present is 97.602% of the allowable FCC established general public limit sampled at the ground level.

Site Composite MPE %	
Carrier	MPE %
Sprint	25.842%
AT&T	17.540%
MetroPCS	6.810%
Nextel	2.540%
T-Mobile	1.920%
Town 1	10.110%
Town 2	32.840%
Total Site MPE %	97.602%



February 6, 2014

Mr. William F. Smith, Jr.
Town Manager
Town of Granby, CT
Granby Town Hall
15 North Granby Road
Granby, CT 06035

RE: Telecommunications Facility @ 15 North Granby Road, Granby, CT

Dear Mr. Smith,

In order to accommodate technological changes and enhance system performance in the State of Connecticut, Sprint Spectrum will be changing its equipment configuration at certain cell sites.

As required by Regulations of Connecticut State Agencies (R.C.S.A.) Section 16-50j-73, the Connecticut Siting Council has been notified of the changes and will review Sprint's proposal. Please accept this letter as notification under Section 16-50j-73 of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2).

The accompanying letter to the Siting Council fully describes Sprint's proposal for the referenced cell site. However, if you have any questions or require any further information on our plans or the Siting Council's procedures, please call me at (508) 251-0720 x 302.

Thank you,

Kri Pelletier
SBA Communications Company
33 Boston Post Road West, Suite 320
Marlborough, MA 01752
508-251-0720 x 302 + T
508-251-1755 + F
203-446-7700 + C
kpelletier@sbsite.com



**Structural Analysis for
SBA Network Services, Inc.**

150' Monopole Tower

**SBA Site Name: Granby-N. Granby
SBA Site ID: CT46134-A-00
Sprint Site ID: CT33XC563
Sprint Site Name: Granby Monopole**

FDH Project Number 1421RY1400

Analysis Results

Tower Components	94.6%	Sufficient
Foundation	78.5%	Sufficient

Prepared By:

Jeffrey B. Ray, EI
Project Engineer

Reviewed By:

Dennis D. Able, PE
Director – Structural Engineering
CT PE License No. 23247

FDH Engineering, Inc.
6521 Meriden Drive
Raleigh, NC 27616
(919) 755-1012
info@fdh-inc.com



January 29, 2014

TABLE OF CONTENTS

EXECUTIVE SUMMARY3

 Conclusions.....3

 Recommendations3

APPURTENANCE LISTING4

RESULTS.....5

GENERAL COMMENTS6

LIMITATIONS.....6

APPENDIX7

EXECUTIVE SUMMARY

At the request of SBA Network Services, Inc., FDH Engineering, Inc. performed a structural analysis of the monopole located in Granby, CT to determine whether the tower is structurally adequate to support both the existing and proposed loads pursuant to the *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA-222-F and 2005 Connecticut Building Code (CBC)*. Information pertaining to the existing/proposed antenna loading, current tower geometry, foundation dimensions, geotechnical data, and member sizes was obtained from:

- Seeman Engineering Solutions, LLC (Site No. CT2010) 150ft EEI Monopole Structural Analysis dated October 29, 2008
- Seeman Engineering Solutions, LLC (Site No. CT2010) Baseplate Modification Package dated February 6, 2009
- Engineered Endeavors, Inc. (Job No. 3934) 150' Monopole Structure & Foundation Design Calculations dated June 26, 1998
- Tectonic Engineering Solutions, P.C. (W.O No. 1170.C938) Subsurface Investigation Report dated June 18, 1998
- Vertical Solutions, Inc. (Project No. 121657 Rev. 0) Rigorous Structural Analysis dated September 7, 2012
- Vertical Solutions, Inc. (Site No. CT2010) Modification Drawings for a 150' Monopole dated September 7, 2012
- FDH Engineering, Inc. (Project No. 1331731400) Modification Drawings for a 150' Monopole dated September 11, 2013
- SBA Network Services, Inc.

The *basic design wind speed* per the *TIA/EIA-222-F* standards and *2005 CBC* is 80 mph without ice and 38 mph with 1" radial ice. Ice is considered to increase in thickness with height.

Conclusions

With the existing and proposed antennas from Sprint in place at 126 ft, the tower meets the requirements of the *TIA/EIA-222-F* standards and *2005 CBC*. Furthermore, provided the foundation was constructed per the original design drawings (see Engineered Endeavors, Inc. Job No. 3934) and given the soil parameters (see Tectonic Engineering Solutions, P.C. W.O No. 1170.C938), the foundation should have the necessary capacity to support both the proposed and existing loading. For a more detailed description of the analysis of the tower, see the **Results** section of this report. For a more detailed description of the analysis of the tower, see the **Results** section of this report.

Our structural analysis has been performed assuming all information provided to FDH Engineering, Inc. is accurate (i.e., the steel data, tower layout, existing antenna loading, and proposed antenna loading) and that the tower has been properly erected and maintained per the original design drawings.

Recommendations

To ensure the requirements of the *TIA/EIA-222-F* standards and *2005 CBC* are met with the existing and proposed loading in place, we have the following recommendations:

1. The proposed coax should be installed inside the pole's shaft.
2. RRU/RRH Stipulation: The proposed equipment may be installed in any arrangement as determined by the client.
3. Modifications listed in FDH Engineering, Inc. (Project No. 1331731400) Modification Drawings for a 150' Monopole dated September 11, 2013 must be installed as specified for this analysis to be valid.

APPURTENANCE LISTING

The proposed and existing antennas with their corresponding cables/coax lines are shown in **Table 1**. *If the actual layout determined in the field deviates from the layout, FDH Engineering, Inc. should be contacted to perform a revised analysis.*

Table 1 - Appurtenance Loading**Existing Loading:**

Antenna Elevation (ft)	Description	Coax and Lines ¹	Carrier	Mount Elevation (ft)	Mount Type
159	(1) 18' Omni	(3) 1/2"	Town of Granby	150	(1) Low Profile Platform
155	(1) 10' Omni				
150.7 ³	(9) Andrew DB844H90E-XY	(9) 1-1/4"	Sprint/Nextel		
150	(1) 10' Dipole (1) 3' Yagi	(1) 7/8"	Town of Granby		
138 ²	(3) Powerwave P65-17-XLH-RR (6) Ericsson RRUS-11 RRUs (6) Powerwave 7770.00 (6) Powerwave LGP21401 TMAs (6) Powerwave LGP21903 Diplexers	(12) 1-1/4" (3) Fiber Cables	AT&T	138	(1) Low Profile Platform
126	(3) RFS APXVSP18-C-A20 (3) Alcatel Lucent 1900 MHz RRUs (3) Alcatel Lucent 800 MHz RRUs (3) Alcatel Lucent 800 MHz Filters (4) RFS ACU-A20-N RETs	(3) 1-1/4" Fiber	Sprint	126	(1) Low Profile Platform
115	(3) EMS RR65-18-02DP (3) TMAs	(6) 1-5/8"	T-Mobile	115	Flush Mounted
100	(3) Kathrein 742 213	(6) 1-5/8"	Pocket Communications	100	Flush Mounted
80	---	---	---	80	(1) Empty Standoff

1. Coax installed inside the pole's shaft unless otherwise noted.

2. AT&T has (3) Fiber Cables installed inside (1) 3" Conduit to 138 ft.

3. Loading and coax must be removed prior to installation of proposed loading.

Proposed Loading:

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
126	(3) RFS APXVTM14-C-I20 (3) RFS APXVSP18-C-A20 (3) Alcatel Lucent 1900 MHz RRUs (3) Alcatel Lucent 800 MHz RRUs (3) Alcatel Lucent 800 MHz Filters (4) RFS ACU-A20-N RETs (3) Alcatel Lucent TD-RRH8x20-25 RRUs	(3) 1-1/4" Fiber (1) 0.7" Fiber Cable	Sprint	126	(1) Low Profile Platform

RESULTS

The following yield strength of steel for individual members was used for analysis:

Table 2 – Material Strength

Member Type	Yield Strength
Tower Shaft Sections	65 ksi
Base Plate	60 ksi
Anchor Bolts	75 ksi
Flat Plate Modifications	50 ksi

Table 3 displays the summary of the ratio (as a percentage) of force in the member to their capacities. Values greater than 100% indicate locations where the maximum force in the member exceeds its capacity. *Note: Capacities up to 100% are considered acceptable.* **Table 4** displays the maximum foundation reactions.

If the assumptions outlined in this report differ from actual field conditions, FDH Engineering, Inc. should be contacted to perform a revised analysis. Furthermore, as no information pertaining to the allowable twist and sway requirements for the existing or proposed appurtenances was provided, deflection and rotation were not taken into consideration when performing this analysis.

See the **Appendix** for detailed modeling information.

Table 3 - Summary of Working Percentage of Structural Components

Section No.	Elevation ft	Component Type	Size	% Capacity	Pass Fail
L1	150 – 111.213	Pole	TP24.48x17.5x0.188	77.3	Pass
L2	111.213 – 98	Pole	TP30.29x23.4592x0.25	88.3	Pass
	98 – 76.836	Modified Pole	TP30.29x23.4592x0.25	90.4	Pass
L3	76.836 – 43.499	Modified Pole	TP35.79x29.0103x0.313	92.6	Pass
L4	43.499 – 0	Modified Pole	TP43x34.2641x0.375	76.9	Pass
-	0	Anchor Bolts	(12) 2.25"Ø w/ BC=51"	78.0	Pass
			(3) 2.25"Ø w/ BC=58"	88.9	Pass
-	0	Base Plate	57"Ø PL x 1.75" thk	94.6	Pass

*Capacities include a 1/3 allowable stress increase for wind.

Table 4 - Maximum Base Reactions

Base Reactions	Current Analysis* (TIA/EIA-222-F)	Original Design (TIA/EIA-222-F)
Axial	38 k	22 k
Shear	26 k	22 k
Moment	2,604 k-ft	2,128 k-ft

* Foundation determined to be adequate per independent analysis.

GENERAL COMMENTS

This engineering analysis is based upon the theoretical capacity of the structure. It is not a condition assessment of the tower and its foundation. It is the responsibility of SBA Network Services, Inc. to verify that the tower modeled and analyzed is the correct structure (with accurate antenna loading information) modeled. If there are substantial modifications to be made or the assumptions made in this analysis are not accurate, FDH Engineering, Inc. should be notified immediately to perform a revised analysis.

LIMITATIONS

All opinions and conclusions are considered accurate to a reasonable degree of engineering certainty based upon the evidence available at the time of this report. All opinions and conclusions are subject to revision based upon receipt of new or additional/updated information. All services are provided exercising a level of care and diligence equivalent to the standard and care of our profession. No other warranty or guarantee, expressed or implied, is offered. Our services are confidential in nature and we will not release this report to any other party without the client's consent. The use of this engineering work is limited to the express purpose for which it was commissioned and it may not be reused, copied, or distributed for any other purpose without the written consent of FDH Engineering, Inc.

APPENDIX

DESIGNED APPURTENANCE LOADING



TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod	150	1900 MHz RRH	126
Beacon	150	1900 MHz RRH	126
Beacon	150	800 MHz RRH	126
10' Dipole	150	800 MHz RRH	126
3' Yagi	150	800 MHz RRH	126
18' Omni	150	800 MHz Filter	126
10' Omni	150	800 MHz Filter	126
(1) Low Profile Platform	150	800 MHz Filter	126
P65-17-XLH-RR w/Mount Pipe	138	(2) ACU-A20-N RET	126
P65-17-XLH-RR w/Mount Pipe	138	ACU-A20-N RET	126
P65-17-XLH-RR w/Mount Pipe	138	ACU-A20-N RET	126
(2) RRUS-11	138	APXVTM14-C-I20 w/Mount Pipe	126
(2) RRUS-11	138	APXVTM14-C-I20 w/Mount Pipe	126
(2) RRUS-11	138	APXVTM14-C-I20 w/Mount Pipe	126
(2) 7770.00 w/Mount Pipe	138	TD-RRH8x20-25	126
(2) 7770.00 w/Mount Pipe	138	TD-RRH8x20-25	126
(2) 7770.00 w/Mount Pipe	138	TD-RRH8x20-25	126
(2) LGP21401 TMA	138	(1) Low Profile Platform	126
(2) LGP21401 TMA	138	RR65-18-02DP w/Mount Pipe	115
(2) LGP21401 TMA	138	RR65-18-02DP w/Mount Pipe	115
(2) LGP21903 Diplexer	138	RR65-18-02DP w/Mount Pipe	115
(2) LGP21903 Diplexer	138	TMA	115
(2) LGP21903 Diplexer	138	TMA	115
(1) Low Profile Platform	138	TMA	115
APXSPP18-C-A20 w/Mount Pipe	126	742 213 w/ Mount Pipe	100
APXSPP18-C-A20 w/Mount Pipe	126	742 213 w/ Mount Pipe	100
APXSPP18-C-A20 w/Mount Pipe	126	742 213 w/ Mount Pipe	100
1900 MHz RRH	126	(1) Standoff	80

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

TOWER DESIGN NOTES

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.



Section	1	2	3	4
Length (ft)	38.79	37.96	37.67	48.50
Number of Sides	12	12	12	12
Thickness (in)	0.1875	0.2500	0.3125	0.3750
Socket Length (ft)	3.58	4.33	5.00	34.2895
Top Dia (in)	17.5000	23.4602	29.0636	43.0000
Bot Dia (in)	24.4800	30.3500	35.8100	
Grade	A572-65	A572-65	A572-65	A572-65
Weight (K)	1.7	2.8	4.1	7.6

FDH Engineering, Inc.
 6521 Meridian Drive, Suite 107
 Raleigh, North Carolina
 Phone: 9197551012
 FAX: 9197551031

Job: **Granby-N. Granby CT46134-A-00**
 Project: **1421RY1400**
 Client: SBA
 Code: TIA/EIA-222-F
 Path:
 Drawn by: Jeffrey B. Ray
 Date: 01/29/14
 App'd:
 Scale: NTS
 Dwg No. E-1

RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT33XC563

Granby Monopole
15 North Granby Road
Granby, CT 06035

January 13, 2014

January 13, 2014

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT33XC563– Granby Monopole

Site Total: 97.602% - MPE % in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 15 North Granby Road, Granby, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands band is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 15 North Granby Road, Granby, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 2 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications was used in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTMM-C-120. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTMM-C-120 has a 15.9 dBd gain value at its main lobe at 2500 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.
- 7) The antenna mounting height centerline for the existing and proposed antennas is **126 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT33XC563 - Granby Monopole
Site Address	15 North Granby Road, Granby, CT 06035
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	126	120	1/2 "	0.5	0	1386.9474	34.62609	3.46261%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	126	120	1/2 "	0.5	0	389.96892	9.735841	1.71708%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	40	1	40	13.4	126	120	1/2 "	0.5	0	779.93784	19.47168	3.43416%
Sector total Power Density Value:																8.614%	

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	126	120	1/2 "	0.5	0	1386.9474	34.62609	3.46261%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	126	120	1/2 "	0.5	0	389.96892	9.735841	1.71708%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	40	1	40	13.4	126	120	1/2 "	0.5	0	779.93784	19.47168	3.43416%
Sector total Power Density Value:																8.614%	

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss	ERP	Power Density Value	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	2	40	15.9	126	120	1/2 "	0.5	0	1386.9474	34.62609	3.46261%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	126	120	1/2 "	0.5	0	389.96892	9.735841	1.71708%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	40	1	40	13.4	126	120	1/2 "	0.5	0	779.93784	19.47168	3.43416%
Sector total Power Density Value:																8.614%	

Site Composite MPE %	
Carrier	MPE %
Sprint	25.842%
AT&T	17.540%
MetroPCS	6.810%
Nextel	2.540%
T-Mobile	1.920%
Town 1	10.110%
Town 2	32.840%
Total Site MPE %	97.602%

Summary

All calculations performed for this analysis yielded results that were within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **25.842% (8.614% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **97.602%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.


FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting

21 B Street
Burlington, MA 01803



COMPOUND PLAN
SCALE: 3/8"=1'-0"



RAN EQUIPMENT PHOTO DETAIL
SCALE: N.T.S.

Sprint
1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641

SBA
SBA COMMUNICATIONS CORP.
33 BOSTON POST ROAD WEST, SUITE 320
MARLBOROUGH, MA 01752
TEL: (508) 251-1807

PLANS PREPARED BY:
AEG ADVANCED
ENGINEERING GROUP, P.C.
Civil Engineering - Site Development
Surveying - Telecommunications
500 NORTH BROADWAY
EAST PROVIDENCE, RI 02914
PH: (401) 354-2403
FAX: (401) 633-6354



CHECKED BY: MRC

APPROVED BY: MRC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
0	01/30/14	ISSUED FOR BP	BDJ

SITE NUMBER:
CT33XC563
SITE NAME:
GRANBY MONOPOLE
SITE ADDRESS:
15 NORTH GRANBY RD
GRANBY, CT 06035

SHEET TITLE
COMPOUND PLAN




SHEET NUMBER
A-1

SPECIAL CONSTRUCTION NOTE:
 SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).
 * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
 * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
 * SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

NOTE:
 SPRINT RAD CENTER SHOWN IN TEXT BASED ON SBA-PROVIDED COLLOCATION APPLICATION, EQUIPMENT DATABASE, AND STRUCTURAL ANALYSIS. THE SBA-PROVIDED ANTENNA RAD CENTER SHALL SUPERSEDE ANY CONFLICTING INFORMATION DERIVED FROM THE SPRINT NV 2.5 RFDS.

SPRINT TOWER TOP WORK NOTE:
 PRIOR TO NEW INSTALLATION TO THE TOP OF TOWER, THE FOLLOWING ARE TO BE REMOVED:
 * NEXTEL CABLES TO ASSOCIATED HARDWARE


NOTE:
 EXISTING AZIMUTHS FROM SPRINT PLANS DATED 06/17/13



EXISTING PARTIAL ELEVATION PHOTO DETAIL
 SCALE: N.T.S.

ANTENNA STATUS LEGEND:

- EMPTY — EMPTY PIPE
- (E) — EXISTING
- (P) — INSTALL
- NV — SPRINT ANTENNA
- 2.5 — SPRINT ANTENNA



NOTES:
 1) VERIFY PROPOSED AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION
 2) EXISTING RRH'S NOT SHOWN FOR CLARITY

Sprint
 1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 TEL: (800) 357-7641

SBA
 SBA COMMUNICATIONS CORP.
 33 BOSTON POST ROAD WEST, SUITE 320
 MARLBOROUGH, MA 01752 TEL: (508) 251-1807

PLANS PREPARED BY:
AEG ADVANCED
 ENGINEERING GROUP, P.C.
 Civil Engineering - Site Development
 Surveying - Telecommunications
 500 NORTH BROADWAY PH: (401) 354-2403
 EAST PROVIDENCE, RI 02914 FAX: (401) 633-6354



CHECKED BY: MRC

APPROVED BY: MRC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
0	01/30/14	ISSUED FOR BP	BDJ

SITE NUMBER:
 CT33XC563
 SITE NAME:
 GRANBY MONOPOLE
 SITE ADDRESS:
 15 NORTH GRANBY RD
 GRANBY, CT 06035

SHEET TITLE
 ELEVATION AND ANTENNA PLANS

SHEET NUMBER
 A-2