



Northeast Site Solutions  
Denise Sabo  
4 Angela's Way, Burlington CT 06013  
203-435-3640  
denise@northeastsitesolutions.com

May 12, 2023

Members of the Siting Council  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

RE: Exempt Modification Application  
1081 North Street, Greenwich, CT 06831  
Latitude: 41.139306  
Longitude: -73.641806  
Site#: 807132\_Crown\_VZW

Dear Ms. Bachman:

Verizon Wireless is requesting to file an exempt modification for an existing tower located at 1081 North Street, Greenwich, CT 06831. Verizon Wireless currently maintains twelve (12) antennas at the 176-foot level of the existing 180-foot tower. The property and the tower are owned by Crown Castle. Verizon now intends to replace nine (9) antennas. The new antennas would be installed at the 176-foot level of the tower. This application includes mount modifications as show on the mount analysis dated May 5, 2023. The modification includes B2, B5 hardware that is both 4G (LTE), and 5G capable.

**Verizon Planned Modifications:**

**Remove:**

(6) Coax Lines

**Remove and Replace:**

- (3) Antel-BXA-70063 Antennas (REMOVE) - (3) SAMSUNG MT6407 Antennas (REPLACE)
- (3) AMPHENOL BXA-171063 Antennas (REMOVE) - (3) JMA MX06FR0860 Antennas (REPLACE)
- (3) POWERWAVE P65-15-XL-2 Antennas (REMOVE) - (3) JMA MX06FR0860 Antennas (REPLACE)
- (1) RFS-DB-T1-6Z-8AB-OZ OVP (REMOVE) – (1) RFS DBC1 – 12C – 24AB OVP (REPLACE)
- (3) Nokia UHD B4 RRH (REMOVE) – (3) Samsung RF4439D-25A RRH (REPLACE)
- (3) Nokia UHBA B13 RRH (REMOVE) – (3) Samsung RF440D-13A RRH (REPLACE)
- (1) Hybrid Cable (REMOVE) - (1) Hybrid Cable (REPLACE)

**Install New: NONE**

**Existing to Remain:**

- (3) Dummy/Spare Antennas
- (6) Coax Lines – 1-1/4"



The facility was approved by the Connecticut Siting Council, Docket No. 86 on February 17, 1988. Please see attached.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16- SOj-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-SOj-73, a copy of this letter is being sent to Fred Camillo, First Selectman for the Town of Greenwich, Patrick LaRow, AICP, Director of Planning, and Crown Castle is both the tower owner and property owner.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Verizon Wireless respectfully submits that the proposed modifications to the above referenced telecommunications facility constitute an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

Denise Sabo  
Mobile: 203-435-3640  
Fax: 413-521-0558  
Office: 4 Angela's Way, Burlington CT 06013  
Email: [denise@northeastsitesolutions.com](mailto:denise@northeastsitesolutions.com)



**NSS** **NORTHEAST**  
SITE SOLUTIONS  
*Turnkey Wireless Development*

Attachments

Cc: Fred Camillo, First Selectman  
Town of Greenwich  
Town Hall – Selectman’s Office  
101 Field Point Road  
Greenwich, CT 06830  
203.622.7700

Patrick LaRow, AICP, Director of Planning  
Town of Greenwich  
Town Hall – Planning & Zoning  
101 Field Point Road  
Greenwich, CT 06830  
203.622.7700

Crown Castle, Tower Owner & Property Owner

# Exhibit A

## **Original Facility Approval**

DOCKET NO. 86 - An application of Metro : Connecticut  
Mobile CTS of Fairfield County, Inc.,  
for a Certificate of Environmental Siting  
Compatibility and Public Need for Council  
cellular telephone antennas and  
associated equipment in the Towns of  
Greenwich, and Fairfield, Connecticut. February 17, 1988

DECISION AND ORDER

Pursuant to the forgoing opinion, the Connecticut Siting Council hereby directs that a Certificate of Environmental Compatibility and Public Need, as provided by Section 16-50k of the General Statutes of Connecticut (CGS) be issued to Metro Mobile CTS of Fairfield County, Inc. (Metro Mobile) for the construction, operation, and maintenance of cellular telephone tower sites and associated equipment at the "Greenwich AC/A" site off of North Street in Greenwich, and "Fairfield DE/A" site off of Wood House Road in Fairfield.

The proposed "Greenwich A" Riversville site, "Greenwich AC" Rockwood Lake site, and "Fairfield DE" sites are hereby denied.

The facilities shall be constructed, operated, and maintained as specified in the Council's record in this matter, and subject to the following conditions:

1. The monopole tower at the "Greenwich AC/A" Banksville site shall be no taller than necessary to provide the proposed service, and in no event shall exceed a total height of 213 feet, including antennas and associated equipment.
2. The monopole tower at the "Fairfield DE/A" site shall be no taller than necessary to provide the proposed service, and in no event shall exceed a total height of 173 feet, including antennas.

3. The facilities shall be constructed in accordance with all applicable federal, state, and municipal laws and regulations.
4. Unless necessary to comply with condition number 3, above, no lights shall be installed on these towers.
5. The Certificate Holder shall prepare development and management (D&M) plans for the Greenwich and Fairfield sites in compliance with sections 16-50j-75 through 16-50j-77 of the Regulations of State Agencies. The D&M plans shall provide for evergreen screening around the outside perimeters of the eight-foot chain link fences which will surround the sites.
6. The Certificate Holder or its successor shall notify the Council if and when directional antennas or any equipment other than that listed in this application are added to these facilities.
7. The Certificate Holder or its successor shall permit public or private entities to share space on the Greenwich and Fairfield towers for due consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
8. If these facilities do not provide, or permanently cease to provide, cellular service following completion of construction, this Decision and Order

shall be void, and the towers and all associated equipment in this application shall be dismantled and removed or reapplication for any new use shall be made to the Council before any such new use is made.

9. The Certificate Holder shall comply with any future radio frequency (RF) standards promulgated by State or federal regulatory agencies. Upon the establishment of any new governmental RF Standards, the facilities granted in this Decision and Order shall be brought into compliance with such standards.
10. Unless otherwise approved by the Council, this Decision and Order shall be void if all construction authorized herein is not completed within three years of the issuance of this Decision and Order, or within three years of the completion of any appeal taken in this Decision and Order.

Pursuant to CGS Section 16-50p, we hereby direct that a copy of this Decision and Order be served on each person listed below. A notice of issuance shall be published in the Greenwich Time, the Advocate, the Norwalk Hour, and Bridgeport Post.

By this Decision and Order the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of State Agencies.

The parties or intervenors to this proceeding are:

Metro Mobile CTS of Fairfield County, Inc. (Applicant)  
50 Rockland Street  
South Norwalk, CT 06854

ATTN: Peter Kelley, Vice President  
Michael Riley, General Manager

Howard L. Slater, Esq. (Its Attorneys)  
Jennifer Young Gaudet, Esq.  
Byrne, Slater, Sandler,  
Schulman & Rouse, P.C.  
330 Main Street - PO Box 3216  
Hartford, CT 06103

Fleischman and Walsh, P.C.  
1725 N Street, N.W.  
Washington, D.C. 20036

ATTN: Richard Rubin, Esq.

SNET Cellular, Inc.

Intervenor

Peter J. Tyrrell, Esq.  
Senior Attorney  
SNET Cellular, Inc.  
227 Church Street  
New Haven, CT 06506

(Its Attorney)

Joan Koloski  
11 Turner Lane  
Wilton, CT 06897

(Intervenor)

Town of Wilton

Party


Louis H. Reens  
Second Selectman  
Town of Wilton  
Town Hall  
238 Danbury Road  
Wilton, CT 06897

(Its Representative)



# Exhibit B

## Property Card



# TOWN OF GREENWICH TAX MAP 187 VOL 3

This map was produced from the Town of Greenwich Geographic Information System. The Town expressly disclaims any liability that may result from the use of this map. Aerial: 4/2/06, Data: 10/7/08, Map: 7/20/09. Copyright © 2005 by the Town of Greenwich.



Printed 03/06/2018 Card No. 1 of 1

Tax ID 187/017

**ADMINISTRATIVE INFORMATION**

PARCEL NUMBER  
11-1794

Parent Parcel Number

Property Address  
NORTH STREET 1081

Neighborhood  
2900 BANKSVILLE

Property Class  
270 Telecommunications

TAXING DISTRICT INFORMATION

Jurisdiction 57 Greenwich, CT

**OWNERSHIP**  
CROWN ATLANTIC COMPANY LLC  
PMB 353  
4017 WASHINGTON ROAD  
MCMURRAY, PA 15317  
LOT NO 52B & 52C NORTH ST W 113

**TRANSFER OF OWNERSHIP**

Date			Bk/Pg:
04/19/1999	CELCO PARTNERSHIP		3256, 203 \$875000
03/30/1998	METRO MOBILE CTS OF FFLD		3053, 308 \$816885
09/14/1990	PENCHO GOSPODINOFF		2068, 233 \$875000
10/14/1987	GOSPODINOFF NEDA, PENCHO & KALINKA G		1767, 253 \$0
04/21/1983	GOSPODINOFF NEDA		1306, 65667 \$0

**COMMERCIAL**

**VALUATION RECORD**

Assessment Year	10/01/2005	10/01/2010	10/01/2015	10/01/2016	10/01/2017
Reason for Change	2005 Reval	2010 Reval	2015 Prelim	2015 Final	2017 List
VALUATION	L 3006200	2301600	2071800	2071800	2071800
Market	B 95000	213200	610500	556300	556300
	T 3101200	2514800	2682300	2628100	2628100
VALUATION	L 2104340	1611120	1450260	1450260	1450260
70% Assessed	B 66500	149240	427350	389410	389410
	T 2170840	1760360	1877610	1839670	1839670

**LAND DATA AND CALCULATIONS**

Rating	Measured	Table	Prod. Factor	Land Type	Base Rate	Adjusted Rate	Extended Value	Influence Factor	Value
RA-4	Single Family 4	1	Primary Commercial		14.01	14.01	3453000 B	-40%	2071800
				246549.60					

Zoning: RA-4 Single Family 4  
 Legal Acres: 5.6600

BP14: 14-1010 nvc \$29,000 demo house 2016 GL  
 GEN: Boarded up dwlg depr @ 95% and telecommunications tower w/  
 ancillary improvements. Real estate owner owns tower.  
 LAND: V2068 P233 9/14/90 30x-- sf sold to 11-1240 reducing acreage  
 to 5.66t-acres.

Permit Number FilingDate Est. Cost Field Visit  
 Type Est. SqFt

Supplemental Cards  
 TRUE TAX VALUE 2071800

Supplemental Cards  
**TOTAL LAND VALUE 2071800**

# Exhibit C

## **Construction Drawings**



**VERIZON SITE NUMBER: 467981**  
**VERIZON SITE NAME: BANKSVILLE CT**  
**VERIZON FUZE ID: 16092558**  
**SITE TYPE: MONOPOLE**  
**TOWER HEIGHT: 175'-0"**  
**VERIZON MODIFICATION;4G\_850,4G\_PCS,5G\_850,5G\_LSUB6-PREP, 5G\_RADIO SWAP**

**BUSINESS UNIT #: 807132**  
**SITE ADDRESS: 1081 NORTH ST GREENWICH, CT 06831**  
**COUNTY: FAIRFIELD**  
**JURISDICTION: CONNECTICUT**  
**SITING COUNCIL**

**verizon**  
 20 ALEXANDER DRIVE, 2ND FLOOR  
 WALLINGFORD, CT 06492

**CROWN CASTLE**  
 1200 MACARTHUR BLVD, SUITE 200  
 MAHWAH, NJ 07430

**TOWER ENGINEERING PROFESSIONALS**  
 326 TRYON RD  
 RALEIGH, NC 27603  
 (919) 661-6351  
 TEP JOB #: 217127.749148

**VERIZON SITE NUMBER: 467981**  
**BU #: 807132**  
**BRG 133 943050**  
 1081 NORTH ST  
 GREENWICH, CT 06831  
 EXISTING 175'-0" MONOPOLE

**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK

**PROJECT DESCRIPTION**

THE CABLE OF THIS PROJECT IS TO ENHANCE BROADBAND CONNECTIVITY AND CAPACITY TO THE EXISTING ELIGIBLE WIRELESS FACILITY.

**TOWER SCOPE OF WORK:**

- REMOVE (9) ANTENNAS
- REMOVE (6) RRHS
- REMOVE (6) COAX CABLES
- REMOVE (1) HYBRID CABLE
- REMOVE (1) 6-OVP
- INSTALL PLATFORM MOUNT MODIFICATIONS
- INSTALL (3) SIDE BY SIDE ANTENNA BRACKETS
- INSTALL (9) ANTENNAS
- INSTALL (6) RRHS
- INSTALL (1) 12-OVP
- INSTALL (1) HYBRID CABLE

02/13/23

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SHEET NUMBER: T-1**      **REVISION: 2**

**SITE INFORMATION**

CROWN CASTLE USA INC. BRG 133 943050  
 SITE NAME:  
 SITE ADDRESS: 1081 NORTH ST GREENWICH, CT 06831  
 COUNTY: FAIRFIELD  
 MAP/PARCEL #: 541128-447299  
 AREA OF CONSTRUCTION: EXISTING  
 LATITUDE: 41° 08' 21.50"  
 LONGITUDE: -73° 38' 30.54"  
 LAT/LONG TYPE: NAD83  
 GROUND ELEVATION: 508 FT  
 CURRENT ZONING: RA-4  
 JURISDICTION: CONNECTICUT SITING COUNCIL  
 OCCUPANCY CLASSIFICATION: U  
 TYPE OF CONSTRUCTION: IIB  
 A.D.A. COMPLIANCE: FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION  
 PROPERTY OWNER: CROWN ATLANTIC COMPANY LLC AND PMB 353 4017 WASHINGTON RD MCMURRAY, PA 15317  
 TOWER OWNER: CROWN CASTLE 2000 CORPORATE DRIVE CANONSBURG, PA 15317  
 CARRIER/APPLICANT: VERIZON WIRELESS 20 ALEXANDER DRIVE, 2ND FLOOR WALLINGFORD, CT 06492  
 ELECTRIC PROVIDER: NORTHEAST UTILITIES (800) 286-2000  
 TELCO PROVIDER: LIGHTOWER (866) 482-8890

**DRAWING INDEX**

SHEET #	SHEET DESCRIPTION
T-1	TITLE SHEET
T-2	GENERAL NOTES
C-1	SITE PLAN
C-2	TOWER ELEVATION & ANTENNA PLANS
C-3	EQUIPMENT SCHEDULES
C-4	EQUIPMENT DETAILS
C-5	EQUIPMENT DETAILS
C-6	PLUMBING DIAGRAM
G-1	GROUNDING DETAILS
G-2	GROUNDING DETAILS
APPENDIX	MOUNT MODIFICATION DRAWINGS

ALL DRAWINGS CONTAINED HEREIN ARE FORMATTED FOR FULL SIZE. CONTRACTOR SHALL VERIFY ALL PLANS AND EXISTING DIMENSIONS AND CONDITIONS ON THE JOB SITE AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

**APPROVALS**

SIGNATURE	DATE
_____	_____
_____	_____
_____	_____
_____	_____

**CONTRACTOR PMI REQUIREMENTS**


PMI ACCESSED AT <https://pmi.vxwsmart.com>  
 SMART TOOL VENDOR PROJECT NUMBER: 10148652  
 VzW LOCATION CODE (PSLC): 467981  
 \*\*\* PMI AND REQUIREMENTS ALSO EMBEDDED IN MOUNT ANALYSIS REPORT

**MOUNT MODIFICATION REQUIRED**      **Y**

**VzW APPROVED SMART KIT VENDORS**

REFER TO MOUNT MODIFICATION DRAWINGS PAGE FOR VzW SMART KIT APPROVED VENDORS

**LOCATION MAP**



DRIVING DIRECTIONS FROM VERIZON LOCAL OFFICE (VERIZON WAY, BASKING RIDGE, NJ 07920)  
 HEAD NORTHWEST ON VERIZON WAY. USE THE RIGHT LANE TO TAKE THE RAMP ONTO N MAPLE AVE. USE THE RIGHT LANE TO TAKE THE RAMP ONTO I-287 N. MERGE WITH I-287 N. KEEP LEFT TO STAY ON I-287 N. TAKE THE I-87 S/NEW YORK STATE THRUWAY/I-287 EXIT TOWARD GOV MARIO M. CUOMO BR/NEW YORK CITY. MERGE WITH I-87 S. KEEP LEFT AT THE Y JUNCTION TO CONTINUE ON I-287 E. FOLLOW SIGNS FOR WHITE PLAINS/RYE. TAKE EXIT 9 S-N TOWARD HUTCHINSON PKWY/MERRITT PKWY. MERGE WITH WESTCHESTER AVE. USE THE RIGHT LANE TO TAKE THE RAMP TO WESTCHESTER AVE/NORTH HUTCHINSON PKWY/MERRITT PKWY. MERGE WITH HUTCHINSON RIVER PKWY N. KEEP RIGHT AT THE Y JUNCTION TO STAY ON HUTCHINSON RIVER PKWY N. CONTINUE ONTO CT-15 N. TAKE EXIT 31 FOR NORTH ST. TURN RIGHT ONTO NORTH STREET. TURN LEFT ONTO HURLINGHAM DR. TURN RIGHT ONTO COWDRAY PARK DR. TURN RIGHT.

**APPLICABLE CODES/REFERENCE DOCUMENTS**

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2022 CONNECTICUT BUILDING CODE/2021 IBC
MECHANICAL	2022 CONNECTICUT BUILDING CODE/2021 IMC
ELECTRICAL	2022 CONNECTICUT BUILDING CODE/2020 NEC

**REFERENCE DOCUMENTS:**

STRUCTURAL ANALYSIS: CROWN CASTLE  
 DATED: 09/07/2022

MOUNT ANALYSIS: MASER CONSULTING CONNECTICUT  
 DATED: 05/10/2022

RFDS REVISION: 2  
 DATED: 10/27/2022

ORDER ID: 631887  
 REVISION: 1

**PROJECT DESCRIPTION**

THE CABLE OF THIS PROJECT IS TO ENHANCE BROADBAND CONNECTIVITY AND CAPACITY TO THE EXISTING ELIGIBLE WIRELESS FACILITY.


**TOWER SCOPE OF WORK:**

- REMOVE (9) ANTENNAS
- REMOVE (6) RRHS
- REMOVE (6) COAX CABLES
- REMOVE (1) HYBRID CABLE
- REMOVE (1) 6-OVP
- INSTALL PLATFORM MOUNT MODIFICATIONS
- INSTALL (3) SIDE BY SIDE ANTENNA BRACKETS
- INSTALL (9) ANTENNAS
- INSTALL (6) RRHS
- INSTALL (1) 12-OVP
- INSTALL (1) HYBRID CABLE

**NOTE:**  
 PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE CROWN NOC AT (800) 788-7011 & CROWN CONSTRUCTION MANAGER

**PROJECT TEAM**

A&E FIRM: TOWER ENGINEERING PROFESSIONALS 326 TRYON ROAD RALEIGH, NC 27603 (919) 661-6351  
 JOSEPH T. CRESS - PROJECT MANAGER  
 SCOTT C. BRANTLEY - CIVIL ENGINEER  
 CROWN CASTLE USA INC. DISTRICT CONTACTS: 6325 ARDREY KELL ROAD, SUITE 600 CHARLOTTE, NC 28277  
 SARA REA LOADHOLDT - A&E SPECIALIST (704) 405-6548



**CROWN CASTLE USA INC. SITE ACTIVITY REQUIREMENTS:**

1. NOTICE TO PROCEED- NO WORK SHALL COMMENCE PRIOR TO CROWN CASTLE USA INC. WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE CROWN CASTLE USA INC. NOC AT 800-788-7011 & THE CROWN CASTLE USA INC. CONSTRUCTION MANAGER.
2. "LOOK UP" - CROWN CASTLE USA INC. SAFETY CLIMB REQUIREMENT: THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR CROWN CASTLE USA INC. POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND CROWN CASTLE USA INC. STANDARD CED-STD-10253, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
5. ALL SITE WORK TO COMPLY WITH QAS-STD-10068 "INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON CROWN CASTLE USA INC. TOWER SITE," CED-STD-10294 "STANDARD FOR INSTALLATION OF MOUNTS AND APPURTENANCES," AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS." IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE FOR APPROVAL BY CROWN CASTLE USA INC. PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES PRIOR TO THE START OF CONSTRUCTION.
10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND PROJECT SPECIFICATIONS. LATEST APPROVED REVISION.
12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF CONTRACTOR, TOWER OWNER, CROWN CASTLE USA INC., AND/OR LOCAL UTILITIES.
14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

**GREENFIELD GROUNDING NOTES:**

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTI-OXIDANT COATINGS (I.E. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 FT. OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (I.E., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY).

**GENERAL NOTES:**

1. FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:  
CONTRACTOR: GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION  
CARRIER: VERIZON  
TOWER OWNER: CROWN CASTLE USA INC.
2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CROWN CASTLE.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND CROWN CASTLE PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION AND IS TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF CROWN CASTLE USA INC.
13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.

**CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:**

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH ( $f_c$ ) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°F AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO ( $w/c$ ) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WFF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH ( $f_y$ ) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:  
#4 BARS AND SMALLER.....40 ksi  
#5 BARS AND LARGER.....60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:  
CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH.....3"  
CONCRETE EXPOSED TO EARTH OR WEATHER:  
#6 BARS AND LARGER.....2"  
#5 BARS AND SMALLER.....1-1/2"  
CONCRETE NOT EXPOSED TO EARTH OR WEATHER:  
SLAB AND WALLS.....3/4"  
BEAMS AND COLUMNS.....1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

**ELECTRICAL INSTALLATION NOTES:**

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
  - 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
  - 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (I.E. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. ALL TIE WRAPS SHALL BE CUT FLUSH WITH APPROVED CUTTING TOOL TO REMOVE SHARP EDGES.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.
16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (I.E. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3R (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR CROWN CASTLE USA INC. BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "VERIZON".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.

CONDUCTOR COLOR CODE		
SYSTEM	CONDUCTOR	COLOR
120/240V, 1Ø	A PHASE	BLACK
	B PHASE	RED
	NEUTRAL	WHITE
	GROUND	GREEN
120/208V, 3Ø	A PHASE	BLACK
	B PHASE	RED
	C PHASE	BLUE
	NEUTRAL	WHITE
	GROUND	GREEN
277/480V, 3Ø	A PHASE	BROWN
	B PHASE	ORANGE OR PURPLE
	C PHASE	YELLOW
	NEUTRAL	GREY
	GROUND	GREEN
DC VOLTAGE	POS (+)	RED**
	NEG (-)	BLACK**


\* SEE NEC 210.5(C)(1) AND (2)  
\*\* POLARITY MARKED AT TERMINATION

**ABBREVIATIONS:**

ANT	ANTENNA
(E)	EXISTING
FIF	FACILITY INTERFACE FRAME
GEN	GENERATOR
GPS	GLOBAL POSITIONING SYSTEM
GSM	GLOBAL SYSTEM FOR MOBILE
LTE	LONG TERM EVOLUTION
MGB	MASTER GROUND BAR
MW	MICROWAVE
(N)	NEW
NEC	NATIONAL ELECTRIC CODE
(P)	PROPOSED
PP	POWER PLANT
QTY	QUANTITY
RECT	RECTIFIER
RBS	RADIO BASE STATION
RETS	REMOTE ELECTRIC TILT
RDFS	RADIO FREQUENCY DATA SHEET
RRH	REMOTE RADIO HEAD
RRU	REMOTE RADIO UNIT
SIAD	SMART INTEGRATED DEVICE
TMA	TOWER MOUNTED AMPLIFIER
TYP	TYPICAL
UMTS	UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
W.P.	WORK POINT

**APWA UNIFORM COLOR CODE:**

<input type="checkbox"/> WHITE	PROPOSED EXCAVATION
<input type="checkbox"/> PINK	TEMPORARY SURVEY MARKINGS
<input type="checkbox"/> RED	ELECTRIC POWER LINES, CABLES, CONDUIT, AND LIGHTING CABLES
<input type="checkbox"/> YELLOW	GAS, OIL, STEAM, PETROLEUM, OR GASEOUS MATERIALS
<input type="checkbox"/> ORANGE	COMMUNICATION, ALARM OR SIGNAL LINES, CABLES, OR CONDUIT AND TRAFFIC LOOPS
<input type="checkbox"/> BLUE	POTABLE WATER
<input type="checkbox"/> PURPLE	RECLAIMED WATER, IRRIGATION, AND SLURRY LINES
<input type="checkbox"/> GREEN	SEWERS AND DRAIN LINES



**VERIZON SITE NUMBER:**  
**467981**


**BU #: 807132**  
**BRG 133 943050**

**1081 NORTH ST**  
**GREENWICH, CT 06831**

**EXISTING 175'-0" MONOPOLE**


**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK



**SHEET NUMBER:**  
**T-2**

**REVISION:**  
**2**



**verizon**

20 ALEXANDER DRIVE, 2ND FLOOR  
WALLINGFORD, CT 06492

**CROWN CASTLE**

1200 MACARTHUR BLVD, SUITE 200  
MAHWAH, NJ 07430



TOWER  
ENGINEERING  
PROFESSIONALS

326 TRYON RD  
RALEIGH, NC 27603  
(919) 661-6351

TEP JOB #: 217127.749148

VERIZON SITE NUMBER:  
**467981**

BU #: 807132  
BRG 133 943050

1081 NORTH ST  
GREENWICH, CT 06831

EXISTING 175'-0" MONOPOLE

**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK




02/13/23

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

SHEET NUMBER: **C-1** REVISION: **2**


1 SITE PLAN  
SCALE: 1/4"=1'-0" (FULL SIZE)  
1/8"=1'-0" (11x17)



NEW VERIZON MODIFIED PLATFORM MOUNT

NEW VERIZON EQUIPMENT  
 (6) JMA - MX06FRO860-03 ANTENNAS  
 (3) SAMSUNG - MT6407-77A ANTENNAS  
 (3) SAMSUNG - RF4440D-13A RRHs  
 (3) SAMSUNG - RF4439D-25A RRHs  
 (1) RFS - DBC1-12C-24AB-0Z 12-OVP  
 (3) COMMSCOPE - BSAMNT-SBS-1-2 SIDE BY SIDE MOUNTS  
 INSTALLED ON MODIFIED MOUNT

(E) VERIZON EQUIPMENT TO REMAIN  
 (3) SPARE ANTENNAS  
 INSTALLED ON MODIFIED MOUNT



**VERIZON EQUIPMENT**

ANTENNA CL: 176'-0"  
 MOUNT CL: 174'-0"

(E) 175'-0" MONOPOLE

(E) VERIZON FEEDLINES  
 (6) COAX CABLES (1-1/4")

NEW VERIZON FEEDLINE  
 (1) HYBRID CABLE (12X24)

(E) VERIZON FEEDLINES TO BE REMOVED  
 (6) COAX CABLES (1-1/4")  
 (1) HYBRID CABLE (6X12)

TOP OF CONCRETE  
 ELEV. = 0'-0"

1 TOWER ELEVATION  
 SCALE: 3/16"=1'-0" (FULL SIZE)  
 3/32"=1'-0" (11x17)

(E) VERIZON ANTENNA TO BE REMOVED  
 POWERWAVE - P65-15-XL-2  
 (3 TOTAL, 1 PER SECTOR)

(E) PLATFORM MOUNT  
 TO BE MODIFIED

(E) 175'-0" MONOPOLE

(BETA)  
 210° AZIMUTH

(GAMMA)  
 330° AZIMUTH

(E) VERIZON RRHs TO BE REMOVED  
 NOKIA - UHID B4 RRH 2x40  
 (3 TOTAL, 1 PER SECTOR)

(E) VERIZON ANTENNA TO BE REMOVED  
 ANTEL - BXA-80080/4CF FP  
 (3 TOTAL, 1 PER SECTOR)

(E) VERIZON RRHs TO BE REMOVED  
 NOKIA - UHBA B13 RRH 4X30  
 (3 TOTAL, 1 PER SECTOR)

(E) VERIZON OVP TO BE REMOVED  
 RFS - DB-T1-6Z-8AB-0Z 6-OVP  
 (1 TOTAL)

(ALPHA)  
 90° AZIMUTH

(E) VERIZON ANTENNA TO REMAIN SPARE  
 (3 TOTAL, 1 PER SECTOR)

(E) VERIZON ANTENNA TO BE REMOVED  
 AMPHENOL - BXA-171063-12BF-EDIN-2  
 (3 TOTAL, 1 PER SECTOR)

2 EXISTING ANTENNA PLAN  
 SCALE: 1/2"=1'-0" (FULL SIZE)  
 1/4"=1'-0" (11x17)

NEW VERIZON SIDE BY SIDE ANTENNA BRACKET  
 COMMSCOPE - BSAMNT-SBS-1-2  
 (3 TOTAL, 1 PER SECTOR)

(GAMMA)  
 330° AZIMUTH

700/850/  
 1900/AWS

NEW VERIZON 12-OVP  
 RFS/CELWAVE - DBC1-12C-24AB-0Z  
 (1 TOTAL)

NEW VERIZON ANTENNA  
 JMA - MX06FRO860-03  
 (6 TOTAL, 2 PER SECTOR)

700/850/  
 1900/AWS

700/850/  
 1900/AWS

(ALPHA)  
 90° AZIMUTH  
 (E) VERIZON ANTENNA  
 SPARE  
 (3 TOTAL, 1 PER SECTOR)

NEW VERIZON MODIFIED PLATFORM MOUNT

NEW VERIZON ANTENNA  
 SAMSUNG - MT6407-77A  
 (3 TOTAL, 1 PER SECTOR)

NEW VERIZON RRH  
 SAMSUNG - RF4440D-13A  
 (3 TOTAL, 1 PER SECTOR)

NEW VERIZON RRH  
 SAMSUNG - RF4439D-25A  
 (3 TOTAL, 1 PER SECTOR)

700/850/  
 1900/AWS

700/850/  
 1900/AWS

(BETA)  
 210° AZIMUTH

3 NEW ANTENNA PLAN  
 SCALE: 1/2"=1'-0" (FULL SIZE)  
 1/4"=1'-0" (11x17)

**INSTALLER NOTE:**

EXISTING AND PROPOSED ANTENNA/  
 EQUIPMENT POSITIONING SHOWN PER  
 RFDS. FIELD CONDITIONS MAY VARY.

**TOWER ANALYSIS NOTES:**

1. THE DESIGN DEPICTED IN THESE DRAWINGS IS VALID WHEN ACCOMPANIED BY A CORRESPONDING PASSING TOWER ANALYSIS.
2. CONSTRUCTION MANAGER / GENERAL CONTRACTOR SHALL REVIEW THE TOWER ANALYSIS FOR ANY CONDITIONS PRIOR TO INSTALLATION.
3. ANY REQUIRED TOWER MODIFICATION DESIGN OR TOWER REPLACEMENT SHALL BE APPROVED BY EOR.

**MOUNT ANALYSIS NOTES:**

1. THE DESIGN DEPICTED IN THESE DRAWINGS IS VALID WHEN ACCOMPANIED BY A CORRESPONDING PASSING MOUNT ANALYSIS.
2. CONSTRUCTION MANAGER / GENERAL CONTRACTOR SHALL REVIEW THE MOUNT ANALYSIS FOR ANY CONDITIONS PRIOR TO INSTALLATION.
3. ANY REQUIRED MOUNT MODIFICATION DESIGN OR MOUNT REPLACEMENT SHALL BE APPROVED BY EOR.

**verizon**

20 ALEXANDER DRIVE, 2ND FLOOR  
 WALLINGFORD, CT 06492

**CROWN CASTLE**

1200 MACARTHUR BLVD, SUITE 200  
 MAHWAH, NJ 07430

**TOWER ENGINEERING PROFESSIONALS**  
 326 TRYON RD  
 RALEIGH, NC 27603  
 (919) 661-6351

TEP JOB #: 217127.749148

VERIZON SITE NUMBER:  
**467981**

BU #: 807132  
 BRG 133 943050

1081 NORTH ST  
 GREENWICH, CT 06831

EXISTING 175'-0" MONOPOLE

**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK



02/13/23

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
 UNLESS THEY ARE ACTING UNDER THE DIRECTION  
 OF A LICENSED PROFESSIONAL ENGINEER,  
 TO ALTER THIS DOCUMENT.

SHEET NUMBER:

**C-2**

REVISION:

**2**




**verizon**

20 ALEXANDER DRIVE, 2ND FLOOR  
WALLINGFORD, CT 06492

**CROWN CASTLE**

1200 MACARTHUR BLVD, SUITE 200  
MAHWAH, NJ 07430



TOWER ENGINEERING PROFESSIONALS

326 TRYON RD  
RALEIGH, NC 27603  
(919) 661-6351

TEP JOB #: 217127.749148

VERIZON SITE NUMBER:  
**467981**

BU #: 807132  
BRG 133 943050

1081 NORTH ST  
GREENWICH, CT 06831

EXISTING 175'-0" MONOPOLE

ISSUED FOR:

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK



02/13/23

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER: **C-3** REVISION: **2**

ANTENNA/RRH SCHEDULE

SECTOR	STATUS	ANTENNA MANUFACTURER	ANTENNA MODEL	ANTENNA CENTERLINE	AZIMUTH	MECHANICAL DOWNTILTS	ELECTRICAL DOWNTILTS	TOWER EQUIPMENT MANUFACTURER	TOWER EQUIPMENT QTY/MODEL
A1	NEW	JAM	MX06FRO860-03	176'-0"	90°	*	*	SAMSUNG	(1) RF4440D-13A RRH
A2	NEW	JAM	MX06FRO860-03	176'-0"	90°	*	*	RFS	(1) DBC1-12C-24AB-0Z- 12-OVP
A3	EXISTING	-	SPARE	176'-0"	90°	*	*	SAMSUNG	(1) RF4439D-25A RRH
A4	NEW	SAMSUNG	MT6407-77A	176'-0"	90°	*	*	-	-
B1	EXISTING	-	SPARE	176'-0"	210°	*	*	-	-
B2	NEW	JAM	MX06FRO860-03	176'-0"	210°	*	*	SAMSUNG	(1) RF4440D-13A RRH
B3	NEW	JAM	MX06FRO860-03	176'-0"	210°	*	*	SAMSUNG	(1) RF4439D-25A RRH
B4	NEW	SAMSUNG	MT6407-77A	176'-0"	210°	*	*	-	-
C1	EXISTING	-	SPARE	176'-0"	330°	*	*	-	-
C2	NEW	JAM	MX06FRO860-03	176'-0"	330°	*	*	SAMSUNG	(1) RF4440D-13A RRH
C3	NEW	JAM	MX06FRO860-03	176'-0"	330°	*	*	SAMSUNG	(1) RF4439D-25A RRH
C4	NEW	SAMSUNG	MT6407-77A	176'-0"	330°	*	*	-	-


NOTE - NEW ANTENNA/EQUIPMENT SHOWN IN BOLD

\* - CONTRACTOR TO REFERENCE MOST RECENT RFDS FOR MECHANICAL AND ELECTRICAL DOWNTILTS

1 VERIZON TOWER EQUIPMENT SCHEDULE  
SCALE: NOT TO SCALE


CABLE SCHEDULE

STATUS	CABLE TYPE	MANUFACTURER (MODEL #)	SIZE	LENGTH	QTY
EXISTING	COAX	ANDREW (LDF6-50A)	1-1/4"	176'-0"±	6
NEW	HYBRID	RFS CELWAVE (HB158-U12S24-XXX-LI)	12X24	176'-0"±	1
TOTAL CABLE QTY:					7



2 BASE LEVEL DETAIL  
SCALE: NOT TO SCALE






**NOTES:**

- BSAMNT-SBS-1-2 KIT CONTAINS (2) 627281 MOUNTING BRACKETS.
- TORQUE THE M10 BOLT ASSEMBLY TO 37 N.m. PER MANUFACTURE'S RECOMMENDATIONS.


1 COMMSCOPE - BSAMNT-SBS-1-2  
SCALE: NOT TO SCALE

2 NOT USED  
SCALE: NOT TO SCALE



3 SAMSUNG - EP97-01585A BRACKET DETAIL  
SCALE: NOT TO SCALE

**INSTALLER NOTES:**  
ALL PIPES BRACKETS AND MISCELLANEOUS HARDWARE TO BE GALVANIZED UNLESS NOTED OTHERWISE.




4 ANTENNA & RRH MOUNTING DETAIL  
SCALE: NOT TO SCALE

**verizon**

20 ALEXANDER DRIVE, 2ND FLOOR  
WALLINGFORD, CT 06492

**CROWN CASTLE**

1200 MACARTHUR BLVD, SUITE 200  
MAHWAH, NJ 07430



**TOWER ENGINEERING PROFESSIONALS**

326 TRYON RD  
RALEIGH, NC 27603  
(919) 661-6351

TEP JOB #: 217127.749148

**VERIZON SITE NUMBER:  
467981**

**BU #: 807132  
BRG 133 943050**

1081 NORTH ST  
GREENWICH, CT 06831

EXISTING 175'-0" MONOPOLE

**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK



02/13/23



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SHEET NUMBER:**

**C-4**


**REVISION:**

**2**



JMA - MX06FRO660-03 ANTENNA  
WEIGHT: 83.00 LBS  
SIZE (HxWxD): 95.9X15.40X10.70 IN.

1 JMA WIRELESS - MX06FRO660-03  
SCALE: NOT TO SCALE




SAMSUNG TELECOMMUNICATIONS - MT6407-77A ANTENNA  
WEIGHT: 81.57 LBS  
SIZE (HxWxD): 35.06x16.06x5.51 IN.

2 SAMSUNG - MT6407-77A  
SCALE: NOT TO SCALE

FIBER NAMING CONVENTION	
Technology	(Equipment-Sector-OPTI #)
<b>DUPLEX FIBER RUN</b>	
5GmmW L0	5GmmW-A-0
<b>SIMPLEX FIBER RUN</b>	
CBRS L0	CBRS-A-0
CBRS L1	CBRS-A-1
LAA L0	LAA-A-0
High Band Dual Band L0	HB-A-0
High Band Dual Band L1	HB-A-1
Low Band Dual Band L0	LB-A-0
FDMIMO AWS L0	FDM-AWS-A-0
FDMIMO AWS L1	FDM-AWS-A-1
FDMIMO PCS L0	FDM-PCS-A-0
FDMIMO PCS L1	FDM-PCS-A-1

Rev. 2/23/2021

3 FIBER NAMING CONVENTION CHART  
SCALE: NOT TO SCALE



RFS/CELWAVE - DB-C1-12C-24AB-OZ 12-OVP  
WEIGHT: 32 LBS  
SIZE (HxWxD): 29.5X16.5X12.6 IN.

4 RFS/CELWAVE - DB-C1-12C-24AB-OZ 12-OVP  
SCALE: NOT TO SCALE

**verizon**

20 ALEXANDER DRIVE, 2ND FLOOR  
WALLINGFORD, CT 06492

**CROWN CASTLE**

1200 MACARTHUR BLVD, SUITE 200  
MAHWAH, NJ 07430

**TOWER ENGINEERING PROFESSIONALS**

326 TRYON RD  
RALEIGH, NC 27603  
(919) 661-6351

TEP JOB #: 217127.749148

VERIZON SITE NUMBER:  
**467981**


BU #: 807132  
BRG 133 943050

1081 NORTH ST  
GREENWICH, CT 06831

EXISTING 175'-0" MONOPOLE


**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK



RFS/CELWAVE - HB158-U12S24-XXX-LI  
WEIGHT: 1.7 LBS/FT  
DIAMETER: 1.99" (±.1")  
COAX EQUIVALENT: 1 1/8"

5 HCS DETAIL  
SCALE: NOT TO SCALE



SAMSUNG - RF4439D-25A  
WEIGHT: 74.7 LBS  
SIZE (HxWxD): 14.96X14.96X10.04IN.

6 SAMSUNG - RF4439D-25A  
SCALE: NOT TO SCALE



SAMSUNG - RF4440D-13A  
WEIGHT: 70.33 LBS  
SIZE (HxWxD): 14.96X14.96X9.05 IN.

7 SAMSUNG - RF4440D-13A  
SCALE: NOT TO SCALE



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:  
**C-5**

REVISION:  
**2**

**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK




02/13/23

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.




SHEET NUMBER: REVISION:


**C-6**

**2**



- Port 1 & 2 are for low band (698-896 MHz).
- Port 3,4,5, & 6 are for high band (1695-2360 MHz).
- Antenna Smart Bias Tee (SBT) is through port 1 for low band and port 3 for high band.
- AISG cable is only needed when drawn in the diagrams below, if it is not drawn then SBT is enough to control all RET motors.
- Not all SBT ports are needed to control RET, only green port connection to green port will control RET.






NOTES:

- DOUBLING UP "OR STACKING" OF CONNECTIONS IS NOT PERMITTED.
- EXTERIOR ANTIOXIDANT JOINT COMPOUND TO BE USED ON ALL EXTERIOR CONNECTIONS.
- GROUND BAR SHALL NOT BE ISOLATED FROM TOWER. MOUNT DIRECTLY TO ANTENNA MOUNT STEEL.


1 ANTENNA SECTOR GROUND BAR DETAIL  
SCALE: NOT TO SCALE



NOTES:

- EXTERIOR ANTIOXIDANT JOINT COMPOUND TO BE USED ON ALL EXTERIOR CONNECTIONS.
- GROUND BAR SHALL NOT BE ISOLATED FROM TOWER. MOUNT DIRECTLY TO TOWER STEEL (TOWER ONLY).
- GROUND BAR SHALL BE ISOLATED FROM BUILDING OR SHELTER.


2 TOWER/SHELTER GROUND BAR DETAIL  
SCALE: NOT TO SCALE



NOTES:

- GROUND ROD SHALL BE DRIVEN VERTICALLY, NOT TO EXCEED 45 DEGREES FROM THE VERTICAL
- GROUND WIRE SHALL BE MIN. 30" BELOW GRADE OR 6" BELOW FROST LINE. (WHICH EVER IS GREATER) AS PER N.E.C. ARTICLE 250-50(D)


3 INSPECTION WELL DETAIL  
SCALE: NOT TO SCALE




NOTES:

- NUMBER OF GROUNDING BARS MAY VARY DEPENDING ON THE TYPE OF TOWER, ANTENNA LOCATIONS AND CONNECTION ORIENTATION. COAXIAL CABLES EXCEEDING 200 FEET ON THE TOWER SHALL HAVE GROUND KITS AT THE MIDPOINT. PROVIDE AS REQUIRED.
- ONLY MECHANICAL CONNECTIONS ARE ALLOWED TO BE MADE TO CROWN CASTLE USA INC. TOWERS. ALL MECHANICAL CONNECTIONS SHALL BE TREATED WITH AN ANTI-OXIDANT COATING.
- ALL TOWER GROUNDING SYSTEMS SHALL COMPLY WITH THE REQUIREMENTS OF THE RECOGNIZED EDITION OF ANSI/TIA 222 AND NFPA 780.

4 TYPICAL ANTENNA CABLE GROUNDING  
SCALE: NOT TO SCALE



5 HARDWARE DETAIL FOR EXTERIOR CONNECTIONS  
SCALE: NOT TO SCALE



NOTES:

- GROUND ROD SHALL BE DRIVEN VERTICALLY, NOT TO EXCEED 45 DEGREES FROM THE VERTICAL
- GROUND WIRE SHALL BE MIN. 30" BELOW GRADE OR 6" BELOW FROST LINE. (WHICH EVER IS GREATER) AS PER N.E.C. ARTICLE 250-50(D)

6 GROUND ROD DETAIL  
SCALE: NOT TO SCALE

**verizon**

20 ALEXANDER DRIVE, 2ND FLOOR  
WALLINGFORD, CT 06492

**CROWN CASTLE**

1200 MACARTHUR BLVD, SUITE 200  
MAHWAH, NJ 07430

**TOWER ENGINEERING PROFESSIONALS**

326 TRYON RD  
RALEIGH, NC 27603  
(919) 661-6351

TEP JOB #: 217127.749148

VERIZON SITE NUMBER:  
**467981**

BU #: **807132**  
BRG **133 943050**

1081 NORTH ST  
GREENWICH, CT 06831

EXISTING 175'-0" MONOPOLE

ISSUED FOR:

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK



02/13/23


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER:

**G-1**

REVISION:


**2**



**NOTE:**

1. ERICO EXOTHERMIC "MOLD TYPES" SHOWN HERE ARE EXAMPLES. CONSULT WITH CONSTRUCTION MANAGER FOR SPECIFIC MOLDS TO BE USED FOR THIS PROJECT.
2. MOLD TYPE ONLY TO BE USED BELOW GRADE WHEN CONNECTING GROUND RING TO GROUND ROD.


**1 CADWELD GROUNDING CONNECTIONS**  
SCALE: NOT TO SCALE



**NOTES:**

1. DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.
2. GROUNDING KIT SHALL BE TYPE AND PART NUMBER AS SUPPLIED OR RECOMMENDED BY CABLE MANUFACTURER.
3. WEATHER PROOFING SHALL BE TWO-PART TAPE KIT. COLD SHRINK SHALL NOT BE USED.


**3 CABLE GROUND KIT CONNECTION**  
SCALE: NOT TO SCALE



**NOTES:**

1. DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO ANTENNA GROUND BAR.
2. WEATHER PROOFING SHALL BE TWO-PART TAPE KIT. COLD SHRINK SHALL NOT BE USED.


**4 GROUND CABLE CONNECTION**  
SCALE: NOT TO SCALE



**NOTES:**


1. DOWN LEAD (HOME RUN) CONDUCTORS ARE NOT TO BE INSTALLED ON CROWN CASTLE USA INC. TOWER, PER THE GROUNDING DOWN CONDUCTOR POLICY QAS-STD-10091. NO MODIFICATION OR DRILLING TO TOWER STEEL IS ALLOWED IN ANY FORM OR FASHION. CAD-WELDING ON THE TOWER AND/OR IN THE AIR ARE NOT PERMITTED.
2. OMIT INSULATOR WHEN MOUNTING TO TOWER STEEL OR PLATFORM STEEL. USE INSULATORS WHEN ATTACHING TO BUILDING OR SHELTERS.

**6 GROUND BAR DETAIL**  
SCALE: NOT TO SCALE



**7 LUG DETAIL**  
SCALE: NOT TO SCALE


WIRE SIZE	BURNDY LUG	BOLT SIZE
#6 AWG GREEN INSULATED	YA6C-2TC38	3/8" - 16 NC S 2 BOLT
#2 AWG SOLID TINNED	YA3C-2TC38	3/8" - 16 NC S 2 BOLT
#2 AWG STRANDED	YA2C-2TC38	3/8" - 16 NC S 2 BOLT
#2/0 AWG STRANDED	YA26-2TC38	3/8" - 16 NC S 2 BOLT
#4/0 AWG STRANDED	YA28-2N	1/2" - 16 NC S 2 BOLT




**NOTES:**

1. ALL GROUNDING LUGS ARE TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. ALL HARDWARE BOLTS, NUTS, LOCK WASHERS SHALL BE STAINLESS STEEL. ALL HARDWARE ARE TO BE AS FOLLOWS: BOLT, FLAT WASHER, GROUND BAR, GROUND LUG, FLAT WASHER AND NUT.


**2 MECHANICAL LUG CONNECTION**  
SCALE: NOT TO SCALE



**5 GROUNDWIRE INSTALLATION**  
SCALE: NOT TO SCALE



**8 TRANSITIONING GROUND DETAIL**  
SCALE: NOT TO SCALE



VERIZON SITE NUMBER:  
**467981**


BU #: **807132**  
BRG **133 943050**

1081 NORTH ST  
GREENWICH, CT 06831

EXISTING 175'-0" MONOPOLE

**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
0	09/28/22	SBP	CONSTRUCTION	RST
1	02/06/23	WAM	CONSTRUCTION	RST
2	02/13/23	SK	CONSTRUCTION	SPK



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER: **G-2** REVISION: **2**



MOUNT MODIFICATION DRAWINGS  
EXISTING 12.83' PLATFORM

TOWER OWNER: CROWN CASTLE  
TOWER OWNER SITE NUMBER: 807132

CARRIER SITE NAME: BANKSVILLE CT  
CARRIER SITE NUMBER: 467981  
FUZE ID: 16092558

1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY

LATITUDE: 41.139306° N  
LONGITUDE: 73.641806° W



www.colliersengineering.com

Copyright © 2022, Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, re-used, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.

Doing Business as MASER



**811** PROTECT YOURSELF  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE  
Know what's below.  
Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE: AS SHOWN JOB NUMBER: 22777017A

REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
0	05/13/22	ISSUED FOR CONSTRUCTION	PD	DRH

*Derek R. Hartzell*  
32710  
Digitally signed by Derek R. Hartzell  
Date: 2022.05.13 14:26:56-04'00'  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC-0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SITE NAME:  
BANKSVILLE CT  
467981  
1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY

STAMFORD  
1055 Washington Boulevard  
Stamford, CT 06901  
Phone: 203.324.0800  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
DOING BUSINESS AS MASER CONSULTING

TITLE SHEET

ST-1

DESIGN CRITERIA
<b>WIND LOADS</b> BASIC WIND SPEED (3 SECOND GUST), V = 115 MPH EXPOSURE CATEGORY B TOPOGRAPHIC METHOD II TOPOGRAPHIC CONSIDERED N/A MEAN BASE ELEVATION (AMSL) = 502.51'
<b>ICE LOADS</b> ICE WIND SPEED (3 SECOND GUST), V = 50 MPH ICE THICKNESS = 1.00 IN
<b>SEISMIC LOADS</b> SEISMIC DESIGN CATEGORY B SHORT TERM MCER GROUND MOTION, S <sub>s</sub> = .274 LONG TERM MCER GROUND MOTION, S <sub>i</sub> = .060

PROJECT INFORMATION
<b>APPLICANT/LESSEE</b> COMPANY: VERIZON WIRELESS <b>CLIENT REPRESENTATIVE</b> COMPANY: VERIZON WIRELESS <b>PROJECT MANAGER</b> COMPANY: COLLIERS ENGINEERING & DESIGN CONTACT: PETER ALBANO PHONE: 856.797.0412 E-MAIL: PETER.ALBANO@COLLIERSENGINEERING.COM
<b>CONTRACTOR PMI REQUIREMENTS</b> PMI LOCATION: HTTPS://PMI.VZWSMART.COM SMART TOOL PROJECT #: 10148652 VZW LOCATION CODE (PSLC): 467981 ANALYSIS DATE: 5/13/2022 PMI REQUIREMENTS EMBEDDED WITHIN MOUNT MODIFICATION REPORT

SHEET INDEX
SHEET DESCRIPTION
ST-1 TITLE SHEET
SBOM-1 BILL OF MATERIALS
SGN-1 GENERAL NOTES
SCF-1 CLIMBING FACILITY DETAIL
SS-1 MODIFICATION DETAILS
SS-2 MOUNT PHOTOS
SPECIFICATION SHEETS

**COPYRIGHT ©2022**  
**COLLIERS ENGINEERING & DESIGN**  
**ALL RIGHTS RESERVED**  
THIS DRAWING AND ALL THE INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT OF COLLIERS ENGINEERING & DESIGN.

## BILL OF MATERIALS

### SECTION 1 - VZWSMART KITS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS.)	WEIGHT (LBS.)	
1	VZWSMART	VZWSMART-PLK1	SUPPORT RAIL KIT	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1.	504	504	
1		VZWSMART-PLK5	KICKER KIT	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1.	291	291	
1		VZWSMART-PLK7	MONOPOLE COLLAR MOUNT ASSEMBLY			150	150
1		VZWSMART-MSK1	CROSSOVER PLATE			14	14

### SECTION 2 - OTHER REQUIRED PARTS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS.)	WEIGHT (LBS.)
3	-	-	84" LONG, P2 1/2 STD	GALVANIZED	41	122
1	SITE PRO 1	SCP10K	PIPE TO PIPE CLAMP SET	OR EOR APPROVED EQUAL, CONTACT MASER CONSULTING FOR APPROVAL OF SUBSTITUTION.	14	14
-	-	-	1/2" DIA. J429 GR-2 U-BOLTS	GALVANIZED	-	-
					TOTAL:	1095

- NOTES:**
1. THE MANUFACTURERS LISTED ARE THE APPROVED VENDORS FOR THE VZW MOUNT KITS. EACH MANUFACTURER WILL BE AWARE OF WHICH KITS HAVE BEEN THROUGH THE VZW APPROVAL PROCESS AND THEY ARE IN TURN APPROVED TO SELL. PLEASE NOTE THAT THE MATERIAL UTILIZED ON THE MOUNT MODIFICATIONS WILL BE REVIEWED AS A PART OF THE DESKTOP PMI COMPLETED BY THE SMART TOOL VENDOR. IT WILL BE REQUIRED THAT THE VZW KITS SPECIFIED ARE UTILIZED IN THE MODIFICATIONS.
  2. ALL MATERIALS REQUIRED FOR THE DESIGNED MODIFICATIONS BUT NOT LISTED IN THIS SHEET ARE ASSUMED TO BE PROVIDED BY THE CONTRACTOR.

VZWSMART KITS - APPROVED VENDORS	
<b>COMMSCOPE</b>	
CONTACT	SALVADOR ANGUIANO
PHONE	(817) 304-7492
EMAIL	SALVADOR.ANGUIANO@COMMSCOPE.COM
WEBSITE	WWW.COMMSCOPE.COM
<b>METROSITE FABRICATORS, LLC</b>	
CONTACT	KENT RAMEY
PHONE	(706) 335-7045 (O), (706) 982-9788 (M)
EMAIL	KENT@METROSITELLC.COM
WEBSITE	METROSITEFABRICATORS.COM
<b>PERFECTVISION</b>	
CONTACT	WIRELESS SALES
PHONE	(844) 887-6723
EMAIL	WWW.PERFECT-VISION.COM
WEBSITE	WIRELESSSALES@PERFECT-VISION.COM
<b>SABRE INDUSTRIES, INC.</b>	
CONTACT	ANGIE WELCH
PHONE	(866) 428-6937
EMAIL	AKWELCH@SABREINDUSTRIES.COM
WEBSITE	WWW.SABRESITESOLUTIONS.COM
<b>SITE PRO 1</b>	
CONTACT	PAULA BOSWELL
PHONE	(972) 236-9843
EMAIL	PAULA.BOSWELL@VALMONT.COM
WEBSITE	WWW.SITEPRO1.COM

VZWSMART KITS - APPROVED VENDORS	
<b>NEWAVE</b>	
CONTACT	NEWAVE SALES TEAM
PHONE	(971) 239-4762
EMAIL	SALES@NEWAVETC.COM
WEBSITE	WWW.NEWAVETC.COM
<b>BETTER METAL, LLC</b>	
CONTACT	DAVID STANSBERRY
PHONE	(615) 535-0990 (O), (615) 631-2520 (M)
EMAIL	DLS@BETTERMETAL.COM
WEBSITE	WWW.BETTERMETAL.COM



www.colliersengineering.com

Copyright © 2022, Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, re-used, distorted, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.



**PROTECT YOURSELF**  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE.  
Know what's below.  
Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT:  
WWW.CALL811.COM

SCALE: AS SHOWN      JOB NUMBER: 22777017A

REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
0	05/13/22	ISSUED FOR CONSTRUCTION	PD	DRH

Digitally signed by Derek R. Hartzell  
Date: 2022.05.13 14:27:07-04'00'  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC-0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
**BANKSVILLE CT**  
**467981**  
**1081 NORTH STREET**  
**GREENWICH, CT 06831**  
**FAIRFIELD COUNTY**

STAMFORD  
1055 Washington Boulevard  
Stamford, CT 06901  
Phone: 203.324.0800  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
DOING BUSINESS AS MASER CONSULTING

**BILL OF MATERIALS**

SHEET NUMBER: **SBOM-1**



**PROJECT NOTES**

- SEE MODIFICATION NOTES
- THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES, ORDINANCES, LAWS AND REGULATIONS OF ALL MUNICIPALITIES, UTILITY COMPANIES OR OTHER PUBLIC/GOVERNING AUTHORITIES.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS THAT MAY BE REQUIRED BY ANY FEDERAL, STATE, COUNTY OR MUNICIPAL AUTHORITIES.
- THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER, IN WRITING, OF ANY CONFLICTS, ERRORS OR OMISSIONS PRIOR TO THE SUBMISSION OF BIDS OR PERFORMANCE OF WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING ALL EXISTING SITE IMPROVEMENTS PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL REPAIR ANY DAMAGE AS A RESULT OF CONSTRUCTION OF THIS FACILITY AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
- THE SCOPE OF WORK FOR THIS PROJECT SHALL INCLUDE PROVIDING ALL MATERIALS, EQUIPMENT AND LABOR REQUIRED TO COMPLETE THIS PROJECT. ALL EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- THE CONTRACTOR SHALL VISIT THE PROJECT SITE PRIOR TO SUBMITTING THE BID TO VERIFY THAT THE PROJECT CAN BE CONSTRUCTED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND CONSTRUCTION DRAWINGS.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING DIMENSIONS AND CONDITIONS PRIOR TO COMMENCING ANY WORK. ALL DIMENSIONS OF EXISTING CONSTRUCTION SHOWN ON THESE DRAWINGS MUST BE VERIFIED. THE CONTRACTOR SHALL NOTIFY THE CONSTRUCTION MANAGER OF ANY DISCREPANCIES PRIOR TO ORDERING MATERIAL OR PROCEEDING WITH CONSTRUCTION.
- SINCE THE CELL SITE MAY BE ACTIVE, ALL SAFETY PRECAUTIONS MUST BE TAKEN WHEN WORKING AROUND HIGH LEVELS OF ELECTROMAGNETIC RADIATION. EQUIPMENT SHOULD BE SHUTDOWN PRIOR TO PERFORMING ANY WORK THAT COULD EXPOSE THE WORKERS TO DANGER. PERSONAL RF EXPOSURE MONITORS ARE REQUIRED TO BE WORN TO ALERT OF ANY POTENTIALLY DANGEROUS EXPOSURE LEVELS.
- NO NOISE, SMOKE, DUST OR ODOR WILL RESULT FROM THIS FACILITY AS TO CAUSE A NUISANCE.
- THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION (NO HANDICAP ACCESS IS REQUIRED).

**GENERAL NOTES**

- THESE MODIFICATIONS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE TELECOMMUNICATIONS INDUSTRY STANDARD TIA-222-H. MATERIALS AND SERVICES PROVIDED BY THE CONTRACTOR SHALL CONFORM TO THE ABOVE MENTIONED CODES.
- CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT DAMAGE TO EXISTING STRUCTURES. ANY DAMAGE TO EXISTING STRUCTURES AS A RESULT OF THE CONTRACTOR'S WORK OR FROM DAMAGE DUE TO OTHER CAUSES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS BEFORE BEGINNING WORK, ORDERING MATERIAL, AND PREPARING OF SHOP DRAWINGS. ANY DISCREPANCIES BETWEEN FIELD CONDITIONS AND THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ENGINEER. IF THE CONTRACTOR DISCOVERS ANY EXISTING CONDITIONS THAT ARE NOT REPRESENTED ON THESE DRAWINGS, OR ANY CONDITIONS THAT WOULD INTERFERE WITH THE INSTALLATION OF THE MODIFICATIONS, NOTIFY THE ENGINEER IMMEDIATELY.
- IT IS ASSUMED THAT ANY STRUCTURAL MODIFICATION WORK SPECIFIED ON THESE PLANS WILL BE ACCOMPLISHED BY KNOWLEDGEABLE WORKMEN WITH TOWER CONSTRUCTION EXPERIENCE.
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION METHODS, MEANS, TECHNIQUES, SEQUENCES, AND PROCEDURES.
- ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN AND SHALL MEET ANSII/TIA-322 (LATEST EDITION), OSHA, AND GENERAL INDUSTRY STANDARDS. ALL RIGGING PLANS SHALL ADHERE TO ANSII/TIA-322 (LATEST EDITION) INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION.
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PROGRAMS IN ACCORDANCE WITH APPLICABLE SAFETY CODES.
- WORK SHALL ONLY BE PERFORMED DURING CALM DRY DAYS (WINDS LESS THAN 30-MPH). THE STRUCTURE SHOWN ON THE DRAWINGS IS STRUCTURALLY SOUND ONLY IN THE COMPLETED FORM. THE

CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRENGTH AND STABILITY OF THE STRUCTURE DURING ERECTION. CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORT, SHORING, BRACING AND ANY OTHER STRUCTURAL SYSTEMS AS REQUIRED TO RESIST ALL FORCES THAT MAY OCCUR DURING HANDLING AND ERECTION UNTIL THE STRUCTURE IS FULLY COMPLETED. TEMPORARY SUPPORTS, BRACING AND OTHER STRUCTURAL SYSTEMS REQUIRED DURING CONSTRUCTION SHALL REMAIN THE CONTRACTOR'S PROPERTY AFTER THEIR USE.

- ALL INSTALLATIONS PERFORMED ON THIS STRUCTURE SHALL BE COMPLETED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE STANDARD FOR INSTALLATION, ALTERATION AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, ANSII/TIA-322.
- CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER SUPERVISION OF OWNER. ALL FENCE, STONE, GEOFABRIC, GROUNDING, AND SURROUNDING GRADE SHALL BE REPLACED AND REPAIRED AS REQUIRED TO ACHIEVE OWNER APPROVAL. POSITIVE DRAINAGE AWAY FROM TOWER SITE SHALL BE MAINTAINED.
- CONNECTIONS BETWEEN ITEMS SUPPORTED BY THE STRUCTURE AND THE STRUCTURE NOT SPECIFICALLY DETAILED IN THE CONTRACT DOCUMENTS ARE THE RESPONSIBILITY OF THE CONTRACTOR. SUCH CONNECTIONS SHALL BE DESIGNED, COORDINATED AND INSPECTED BY A PROFESSIONAL STRUCTURAL ENGINEER LICENSED IN THE STATE OF THE PROJECT. SUBMIT SIGNED AND SEALED CALCULATIONS DURING SHOP DRAWING REVIEW.
- DO NOT SCALE DRAWINGS.
- DO NOT USE THESE DRAWINGS FOR ANY OTHER SITE.
- ALL MATERIAL UTILIZED FOR THIS PROJECT MUST BE NEW AND FREE OF ANY DEFECTS. ANY MATERIAL SUBSTITUTIONS, INCLUDING BUT NOT LIMITED TO ALTERED SIZE AND/OR STRENGTHS, MUST BE APPROVED BY THE OWNER AND ENGINEER IN WRITING.
- THE MOUNT UNDER NO CIRCUMSTANCES SHOULD BE USED AS A TIE OFF POINT.

**STRUCTURAL STEEL**

- DESIGN, DETAILING, FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING PUBLICATIONS EXCEPT AS SPECIFICALLY INDICATED IN THE CONTRACT DOCUMENTS.
  - AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) MANUAL OF STEEL CONSTRUCTION (15TH EDITION)
  - SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS
  - AISC CODE OF STANDARD PRACTICE
- STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING UNLESS OTHERWISE SHOWN:
 

CHANNELS, ANGLES, PLATES, ETC.	ASTM A36 (GR 36)
STEEL PIPE	ASTM A53 (GR 35)
BOLTS	ASTM A325
NUTS	ASTM A563
LOCK WASHERS	LOCKING STRUCTURAL GRADE

- ALL SUBSTITUTIONS PROPOSED BY THE CONTRACTOR SHALL BE APPROVED IN WRITING BY THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO ENGINEER FOR VERIFYING THE SUBSTITUTE IS SUITABLE FOR USE AND MEETS ORIGINAL DESIGN CRITERIA. DIFFERENCES FROM THE ORIGINAL DESIGN, INCLUDING MAINTENANCE, REPAIR AND REPLACEMENT, SHALL BE NOTED. ESTIMATES OF COSTS/CREDITS ASSOCIATED WITH THE SUBSTITUTION (INCLUDING RE-DESIGN COSTS AND COSTS TO SUB-CONTRACTORS) SHALL BE PROVIDED TO THE ENGINEER. CONTRACTOR SHALL PROVIDE ADDITIONAL DOCUMENTATION AND/OR SPECIFICATIONS TO THE ENGINEER AS REQUESTED.
- PROVIDE STRUCTURAL STEEL SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION.
  - SUBMIT SHOP DRAWINGS TO  
PETER.ALBANO@COLLIERSENGINEERING.COM
  - PROVIDE MASER CONSULTING PROJECT # AND MASER CONSULTING PROJECT ENGINEER CONTACT IN THE BODY OF THE EMAIL.
- DRILL NO HOLES IN ANY NEW OR EXISTING STRUCTURAL STEEL MEMBERS OTHER THAN THOSE SHOWN ON STRUCTURAL DRAWINGS WITHOUT THE APPROVAL OF THE ENGINEER OF RECORD.
- GALVANIZED ASTM A325 BOLTS SHALL NOT BE REUSED.
- ALL NEW STEEL SHALL BE HOT BE DIPPED GALVANIZED FOR FULL WEATHER PROTECTION. IN ADDITION ALL NEW STEEL SHALL BE PAINTED TO MATCH EXISTING STEEL. CONTRACTOR SHALL OBTAIN WRITTEN PERMISSION TO PROTECT STEEL BY ANY OTHER MEANS.
- CONTRACTOR SHALL PROTECT CUT ENDS OF ALL FIELD-CUT STEEL WITH TWO (2) COATS OF COLD GALVANIZATION (ZINGA OR ZINC COTE).
- ALL BOLT ASSEMBLIES FOR STRUCTURAL MEMBERS REPRESENTED IN THIS DRAWING REQUIRE LOCKING DEVICES TO BE INSTALLED IN ACCORDANCE WITH TIA-222-H SECTION 4.9.2 REQUIREMENTS.
- WHERE CONNECTIONS ARE NOT FULLY DETAILED ON THESE DRAWINGS, FABRICATOR SHALL DESIGN CONNECTIONS TO RESIST LOADS AND FORCES WHERE SHOWN ON DRAWINGS AND AS OUTLINED IN SPECIFICATIONS.
- FOR MEMBERS BEING REPLACED, PROVIDE NEW BOLTS AND MATCH EXISTING SIZE AND GRADE. MAINTAIN AISC REQUIREMENTS FOR MINIMUM BOLT DISTANCE AND SPACING.


- ALL PROPOSED AND/OR REPLACED BOLTS SHALL BE OF SUFFICIENT LENGTH SUCH THAT THE END OF THE BOLT IS AT LEAST FLUSH WITH THE FACE OF THE NUT. IT IS NOT PERMITTED FOR THE BOLT END TO BE BELOW THE FACE OF THE NUT AFTER TIGHTENING IS COMPLETED.
- GALVANIZED ASTM A325 BOLTS SHALL NOT BE REUSED.
- ALL EXISTING PAINTED/GALVANIZED SURFACES DAMAGED DURING REHAB INCLUDING AREAS UNDER STIFFENER PLATES SHALL BE WIRE BRUSHED CLEAN, REPAIRED BY COLD GALVANIZING (ZINGA OR ZINC COTE), AND REPAINTED TO MATCH THE EXISTING FINISH (IF APPLICABLE).
- ALL HOLES IN STEEL MEMBERS SHALL BE SIZED 1/16" LARGER THAN THE BOLT DIAMETER. STANDARD HOLES SHALL BE USED UNLESS NOTED OTHERWISE.

**WELDING NOTES**

- ALL WELDING SHALL BE DONE IN ACCORDANCE WITH AWS D1.0 (LATEST EDITION). THIS SHALL INCLUDE A CERTIFIED WELD INSPECTION (CWI) FOR ACCEPTANCE OR REJECTION OF ALL WELDING OPERATIONS, PRE, DURING, AND POST INSTALLATION, USING THE ACCEPTANCE CRITERIA OF AWS D1.1.
- CONTRACTOR IS RESPONSIBLE FOR COMMISSIONING A THIRD PARTY CERTIFIED WELD INSPECTOR (CWI) THROUGHOUT THE ENTIRETY OF THE PROJECT. A PASSING CWI REPORT SHALL BE PROVIDED TO THE ENGINEER UPON COMPLETION OF THE PROJECT.
- THE CERTIFIED WELD INSPECTOR SHALL INDICATE, IN A WRITTEN CWI REPORT, THAT ALL WELDING OPERATIONS PRE, DURING, AND POST INSTALLATION WERE CONDUCTED IN ACCORDANCE WITH AWS D1.1 WITH PHOTOGRAPHS AND DOCUMENTATION SUPPORTING THE ACCEPTANCE OR REJECTION OF ALL WELDING. ALL CWI WELD INSPECTION DOCUMENTATION AND PHOTOS SHALL BE SUBMITTED DURING THE PMI.
- IN CASES WHERE A WELD IS SPECIFIED BETWEEN TWO MEMBERS IN WHICH THERE IS A GAP IN BETWEEN, THE WELD IS TO BE BUILT-UP SUCH THAT THE SIZE OF WELD ON THE MEMBER IS EQUAL TO THAT SHOWN IN THE DRAWINGS.
- OXY FUEL GAS WELDING OR BRAZING IS STRICTLY PROHIBITED. SPECIFICALLY, NO TORCH CUTTING IS PERMITTED ON SITE. ALL HOLES SHALL BE CUT WITH A GRINDER.
- CONTRACTOR SHALL EXERCISE CAUTION WHEN WELDING A GALVANIZED SURFACE.
- CONTRACTOR SHALL HAVE A FIRE PROTECTION PLAN IN PLACE THAT CONFORMS WITH ALL OSHA, ANSII/ASPP A10.48, ANSII Z49.1, AND LOCAL JURISDICTIONAL REQUIREMENTS.

BOLT SCHEDULE (IN.)				
BOLT DIAMETER	STANDARD HOLE	SHORT SLOT	MIN. EDGE DISTANCE	SPACING
1/2	9/16	9/16 x 11/16	7/8	1 1/2
5/8	11/16	11/16 x 7/8	1 1/8	1 7/8
3/4	13/16	13/16 x 1	1 1/4	2 1/4
7/8	15/16	15/16 x 1 1/8	1 1/2	2 5/8
1	1 1/16	1 1/16 x 1 5/16	1 3/4	3


WORKABLE GAGES (IN.)	
LEG	GAGE
4	2 1/2
3 1/2	2
3	1 3/4
2 1/2	1 3/8
2	1 1/8



**TYP. BOLT ASSEMBLY**

**NOTES:**

- ALL DIMENSIONS REPRESENTED IN THE ABOVE TABLES ARE AISC MINIMUM REQUIREMENTS. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS IN FIELD AND NOTIFY ENGINEER IF DISTANCES ARE LESS THAN THOSE PROVIDED.
- THE DIMENSIONS PROVIDED ARE MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS OF PROPOSED MEMBERS WITHIN THESE DRAWINGS MAY VARY FROM THE AISC MINIMUM REQUIREMENTS.
- SHORT SLOT HOLES SHALL ONLY BE USED WHEN DEPICTED IN THE DRAWINGS
- MATCH EXISTING GAGES WHEN APPLICABLE, UNLESS MINIMUM EDGE DISTANCES ARE COMPROMISED.



**811** PROTECT YOURSELF  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE.  
Know what's below. Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE:	AS SHOWN	JOB NUMBER:	22777017A
REV	DATE	DESCRIPTION	DRAWN BY / CHECKED BY
0	05/13/22	ISSUED FOR CONSTRUCTION	PD / DRH

*Derek R. Hartzell*  
32710  
PROFESSIONAL ENGINEER  
Digitally signed by Derek R. Hartzell  
Date: 2022.05.13 14:27:12-04'00'  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC-0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
**BANKSVILLE CT**  
**467981**  
**1081 NORTH STREET**  
**GREENWICH, CT 06831**  
**FAIRFIELD COUNTY**



**811** PROTECT YOURSELF  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE  
Know what's below. Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE:	AS SHOWN	JOB NUMBER:	22777017A
REV	DATE	DESCRIPTION	DRAWN BY / CHECKED BY
0	05/13/22	ISSUED FOR CONSTRUCTION	PD / DRH

*Derek R. Hartzell*  
32710  
LICENSURE NO. 32710  
PROFESSIONAL ENGINEER  
Digitally signed by Derek R. Hartzell  
Date: 2022.05.13 14:27:16-04'00'  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC-0000131


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
**BANKSVILLE CT**  
**467981**  
**1081 NORTH STREET**  
**GREENWICH, CT 06831**  
**FAIRFIELD COUNTY**

**Colliers** STAMFORD  
1055 Washington Boulevard  
Stamford, CT 06901  
Phone: 203.324.0800  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
DOING BUSINESS AS MASER CONSULTING

SHEET TITLE:  
**CLIMBING FACILITY DETAIL**


SHEET NUMBER:  
**SCF-1**



**1** CLIMBING FACILITY LOCATION  
SCALE : N.T.S.

**STRUCTURAL NOTES:**


- PER THE MOUNT MAPPING COMPLETED BY ONSIGHT SERVICES, LLC ON 4/8/2022, THE SAFETY CLIMB AND CLIMBING FACILITIES UP TO THE VERIZON MOUNT ELEVATION (172'-9") ARE IN GOOD CONDITION. COLLIERS ENGINEERING & DESIGN DOES NOT WARRANT THIS INFORMATION.
- INSTALL SHALL NOT CAUSE HARM TO THE STRUCTURE, CLIMBING FACILITY, SAFETY CLIMB, OR ANY SYSTEM INSTALLED ON THE STRUCTURE. TIMELY NOTICE AND DOCUMENTATION SHALL BE PROVIDED BY CONTRACTORS TO THE EOR (OF STRUCTURAL DESIGN) IF AN OBSTRUCTION WAS REQUIRED TO MEET THE RF SYSTEM DESIGN REQUIREMENTS AND PERFORMANCES.



ITEM #	QTY	PART NUMBER	DESCRIPTIONS
A	1	H42-0501-06	WIRE ROPE GUIDE (PERFECT VISION OR EQUIV)
B	1	PV-CMX-CG-BO	WIRE ROPE GUIDE (PERFECT VISION OR EQUIV)

**2** PROPOSED WIRE ROPE GUIDE ATTACHMENT - PLAN VIEW  
SCALE : N.T.S.

NOTE: CONTRACTOR SHALL ENSURE THAT WIRE ROPE GUIDE DOES NOT PUSH THE WIRE ROPE OUTSIDE OF THE VERTICAL PLANE OF THE SAFETY CLIMB. CONTRACT EOR WITH PHOTOS OF SAFETY CLIMB AND COLLAR FOR FURTHER DIRECTION IF NEEDED.



CLIMBING FACILITY PHOTO

**LEGEND:**

- PROPOSED
- RELOCATED
- EXISTING



MOUNT MODIFICATION SCHEDULE				
NO.	ELEVATION	QUANTITY	DESCRIPTION	NOTES
1		1	PROPOSED SUPPORT RAIL KIT (PART #: VZWSMART-PLK1)	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1. RADIO AND/OR TME POSITIONS SHALL BE ADJUSTED VERTICALLY AS NEEDED IN ORDER TO ACHIEVE INSTALLATION OF HORIZONTAL AS SHOWN. CONNECT PROPOSED SUPPORT RAIL PIPE TO MOUNT PIPE AT POSITION 5 (AS SEEN FROM BEHIND THE MOUNT) IN ALPHA SECTOR WITH CROSSOVER PLATE (PART #: VZWSMART-MSK1).
2	172'-9"	1	PROPOSED KICKER KIT (PART #: VZWSMART-PLK5))	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1. CONNECT OTHER END OF KICKER KIT TO MONOPOLE COLLAR MOUNT ASSEMBLY (PART #: VZWSMART-PLK7).
3		3	PROPOSED 84" LONG, P2 1/2 STD MOUNT PIPE	REMOVE AND REPLACE EXISTING MOUNT PIPE AT POSITION 3 (AS SEEN FROM BEHIND THE MOUNT) IN ALL SECTORS. CONNECT NEW MOUNT PIPE TO EXISTING CHANNEL FACE HORIZONTAL WITH (2) 1/2" DIA. U-BOLTS. CONNECT NEW MOUNT PIPE TO EXISTING INTERMEDIATE AND TOP ANGLE SUPPORT RAILS WITH (1) 1/2" DIA. U-BOLT AT EACH CONNECTION.

**NOTES:**  
MOUNT MEMBERS NOT SHOWN FOR CLARITY U.N.O.  
THREADED ROD FROM PROPOSED KITS SHALL BE TRIMMED TO EXTEND NO MORE THAN 3" BEYOND THE LOCK NUT. TREAT ALL CUT ENDS WITH (2) COATS OF COLD GALVANIZATION (ZINGA OR ZINC KOTE)



**811** PROTECT YOURSELF  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE  
Know what's below. Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE: AS SHOWN	JOB NUMBER: 22777017A			
REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
0	05/13/22	ISSUED FOR CONSTRUCTION	PD	DRH



*Derek R. Hartzell*  
32710  
LICENSED PROFESSIONAL ENGINEER  
Digitally signed by Derek R. Hartzell  
Date: 2022.05.13 14:27:17-04'00'  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC-0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
**BANKSVILLE CT**  
**467981**  
1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY


**Colliers** Engineering & Design  
**STAMFORD**  
1055 Washington Boulevard  
Stamford, CT 06901  
Phone: 203.324.0800  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
DOING BUSINESS AS MASER CONSULTING

**MODIFICATION DETAILS**

SHEET NUMBER: **SS-1**

**1** PROPOSED ISOMETRIC VIEW  
SCALE : N.T.S.


**2** PROPOSED SIDE ELEVATION VIEW (TYP. ALL SECTORS)  
SCALE : N.T.S.




MOUNT PHOTO 1



MOUNT PHOTO 2



MOUNT PHOTO 3



MOUNT PHOTO 4



**811** PROTECT YOURSELF  
 ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE.  
 Know what's below. Call before you dig.  
 FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE: AS SHOWN JOB NUMBER: 22777017A

REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
0	05/13/22	ISSUED FOR CONSTRUCTION	PD	DRH

*Derek R. Hartzell*  
 32710  
 Digitally signed by Derek R. Hartzell  
 Date: 2022.05.13 14:27:19-04'00'  
 COLLIER'S ENGINEERING & DESIGN CT, P.C.  
 C.T. JPC-0000131


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
 BANKSVILLE CT  
 467981  
 1081 NORTH STREET  
 GREENWICH, CT 06831  
 FAIRFIELD COUNTY



**Colliers** Engineering & Design  
 STAMFORD  
 1055 Washington Boulevard  
 Stamford, CT 06901  
 Phone: 203.324.0800  
 COLLIER'S ENGINEERING & DESIGN CT, P.C.  
 DOING BUSINESS AS MASER CONSULTING

SHEET TITLE:  
**MOUNT PHOTOS**


SHEET NUMBER:  
**SS-2**



PLAN VIEW



SECTION "A-A"



DETAIL "B"

**NOTES:**

1. HOT-DIPPED GALVANIZED PER ASTM A123.

VZW SMART-PLK1 (SUPPORT RAIL KIT)					
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	PST2875-12.5	2.5" PST (2.875" O.D. X 0.203" THK.) X 12'-6" A53 GR-B	PLK1-F1	292
2	3	L33375-3	L 3" X 3" X 3/8" X 3'-0" A36	PLK1-F1	66
3	3	CBP-L	CORNER BENT PLATE BRACKET	PLK1-F2	28
4	3	CBP-R	CORNER BENT PLATE BRACKET	PLK1-F2	28
5	60	MS02-625-300-500	RU-BOLT 5/8" X 3" I.W. X 5" I.L. A36 (OR EQUIV.)	RBC-1	82
6	24	---	BOLT 5/8" X 2" A325	---	9
7	12	PL375-857	PL 3/8" X 8 1/2" X 7'-0" A36	PLK1-F3	77
8	144	FW-625	5/8" HDG USS FLAT WASHER	---	12
9	144	LW-625	5/8" HDG LOCK WASHER	---	3
10	144	NUT-625	5/8" HDG HEX NUT	---	17
GALVANIZED WT					504

DRAWN BY: H.R. CHECKED BY: HMA





REV.	DESCRIPTION	BY	DATE
△	FIRST ISSUE	H.R.	05/08/20
△			
△			
△			

SHEET TITLE:


VZWSMART-PLK1  
 SUPPORT RAIL KIT

SHEET NUMBER: VZWSMART-PLK1 REV #: 0

**NOTE:**  
THE LOCATION OF KICKER AND EXISTING ANTENNA MOUNT SHOWN ON THE DRAWING IS FOR REPRESENTATION PURPOSE ONLY. SEE INSTALLATION DRAWINGS FOR ACTUAL INSTALLATION OF DETAILS.



SECTION "A-A"  
RECT. HSS MOUNTING



SECTION "A-A"  
ROUND PIPE MOUNTING

VZSMART-PLK5 (KICKER KIT)						
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT	
1	3	BRKW-XXX	BRACKET WELDMENT A36	PLK5-F3	43.8	
2	3	BRKW-XXXX	BRACKET WELDMENT A36	PLK5-F2	35.7	
3	6	L331875-8	L 3" X 3" X 3/16" X 8'-0" A36	PLK5-F4	182.9	
4	3	PL-KI	PL 5/8" X 6" X 9" A36	PLK5-F1	29.0	
5	12	---	THREADED ROD 5/8" DIA. X 1'-0" F1554-36 HDG	---	---	
6	6	---	BOLT 5/8" X 2" A325	---	---	
7	12	---	BOLT 5/8" X 2 1/2" A325	---	---	
8	42	FW-625	5/8" HDG USS FLAT WASHER	---	3	
9	42	LW-625	5/8" HDG LOCK WASHER	---	1	
10	42	NUT-625	5/8" HDG HEX NUT	---	5	
					GALVANIZED WT	291

**NOTES:**  
1. ALL HOLES ARE 11/16" DIA. U.N.O  
2. HOT-DIPPED GALVANIZED PER ASTM A123.  
3. FIT UP TO 6" SQ. TUBING OR 4 1/2" O.D. PIPE

**VzW**  
**SMART Tool**<sup>®</sup>  
**Vendor**

**verizon**<sup>✓</sup>

DRAWN BY: MN CHECKED BY: HMA/KW



REV.	DESCRIPTION	BY	DATE
△	FIRST ISSUE	MN	05/08/20
△			
△			
△			

SHEET TITLE:

VZSMART-PLK5  
KICKER KIT

SHEET NUMBER: REV #:

VZSMART-PLK5 0



NOTES:  
 1. FIT 12" TO 45" DIA MONOPOLE.  
 2. HOT-DIPPED GALVANIZED PER ASTM A123.


VZSMART-PLK7 (MONOPOLE COLLAR MOUNT ASSEMBLY)					
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	CM-1245	COLLAR MOUNT ASSEMBLY	PLK7-F1	147
2	6	---	THREADED ROD 5/8" X 4'-0" A193-B7	---	---
3	12	FW-625	5/8" HDG USS FLAT WASHER	---	1
4	12	LW-625	5/8" HDG LOCK WASHER	---	0
5	12	NUT-625	5/8" HDG HEX NUT	---	1
GALVANIZED WT					150

DRAWN BY: BT		CHECKED BY: HMA/KW	
REV.	DESCRIPTION	BY	DATE
△	FIRST ISSUE	BT	05/11/20
△			
△			
△			


SHEET TITLE:	
VZSMART-PLK7 MONOPOLE COLLAR MOUNT ASSEMBLY	
SHEET NUMBER:	REV #:
VZSMART-PLK7	0



FITS 2.375" O.D. AND 2.875" O.D.  
 VERTICAL PIPE.  
 (NOT INCLUDED IN THIS KIT)



FITS 2.375" O.D. AND 2.875" O.D.  
 HORIZONTAL PIPE.  
 (NOT INCLUDED IN THIS KIT)





NOTES:  
 1. HOT-DIPPED GALVANIZED PER ASTM A123.

VZWSMART-MSK1 (CROSSOVER PLATE)					
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	1	PL375-857	PL 3/8" X 8 1/2" X 0'-7" A36	MSK1-F1	6
2	4	MS02-625-300-500	RU-BOLT 5/8" X 3" I.W. X 5" I.L. A36 (OR EQUIV.)	RBC-1	5
3	8	FW-625	5/8" HDG USS FLAT WASHER	---	1
4	8	LW-625	5/8" HDG LOCK WASHER	---	0
5	8	NUT-625	5/8" HDG HEX NUT	---	1
GALVANIZED WT					14



DRAWN BY: H.R		CHECKED BY: HMA	
REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	H.R	05/08/20

SHEET TITLE:	
VZWSMART-MSK1 CROSSOVER PLATE	
SHEET NUMBER:	REV #:
VZWSMART-MSK1	0





FITS 1-1/2" TO 3-1/2" PIPE O.D.



PARTS LIST

ITEM	QTY	PART NO.	PART DESCRIPTION	LENGTH	UNIT WT.	NET WT.
1	8	SCP	CLAMP HALF, 1/2" THICK, 5-7/8"		1.25	10.00
2	B	C	1/2" THREADED ROD	D	E	F
3	16	G12NUT	1/2" HDG HEAVY 2H HEX NUT		0.07	1.14
4	16	G12LW	1/2" HDG LOCKWASHER		0.01	0.22
5	16	G12FW	1/2" HDG USS FLATWASHER		0.03	0.54

VARIABLE PARTS TABLE

ASSEMBLY "A"	QTY "B"	PART "C"	LENGTH "D"	UNIT WT. "E"	NET WT. "F"	TOTAL WEIGHT
SCP08K	4	G12R-8	8"	.45	1.78	13.23
SCP10K	4	G12R-10	10"	.56	2.23	13.68

TOLERANCE NOTES

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:  
 SAWED, SHEARED AND GAS CUT EDGES ( $\pm 0.030"$ )  
 DRILLED AND GAS CUT HOLES ( $\pm 0.030"$ ) - NO CONING OF HOLES  
 LASER CUT EDGES AND HOLES ( $\pm 0.010"$ ) - NO CONING OF HOLES  
 BENDS ARE  $\pm 1/2$  DEGREE  
 ALL OTHER MACHINING ( $\pm 0.030"$ )  
 ALL OTHER ASSEMBLY ( $\pm 0.060"$ )

PROPRIETARY NOTE:  
 THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF VALMONT INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT THE CONSENT OF VALMONT INDUSTRIES IS STRICTLY PROHIBITED.

DESCRIPTION

PIPE TO PIPE CLAMP SET  
 1-1/2" TO 3-1/2" PIPE  
 1/2" THICK CLAMP




Engineering Support Team:  
 1-888-753-7446

Locations:  
 New York, NY  
 Atlanta, GA  
 Los Angeles, CA  
 Plymouth, IN  
 Salem, OR  
 Dallas, TX

CPD NO.	DRAWN BY	ENG. APPROVAL
	KC8 8/21/2012	
CLASS	DRAWING USAGE	CHECKED BY
81	CUSTOMER	CEK 2/18/2013

PART NO.	SEE ASSEMBLY "A"	PAGE
DWG. NO.	SCPxxK	1 OF 1



VZSMART Standard Pipe		
VZSMART Number	Size	Length
P40-238X048	PIPE 2 SCH40 (2.375" OD x 0.154" THK)	48"
P40-238X072	PIPE 2 SCH40 (2.375" OD x 0.154" THK)	72"
P40-238X096	PIPE 2 SCH40 (2.375" OD x 0.154" THK)	96"
P40-238X120	PIPE 2 SCH40 (2.375" OD x 0.154" THK)	120"
P40-238X126	PIPE 2 SCH40 (2.375" OD x 0.154" THK)	126"
P40-238X150	PIPE 2 SCH40 (2.375" OD x 0.154" THK)	150"
P40-238X174	PIPE 2 SCH40 (2.375" OD x 0.154" THK)	174"
P40-278X048	PIPE 2.5 SCH40 (2.875" OD x 0.203" THK)	48"
P40-278X072	PIPE 2.5 SCH40 (2.875" OD x 0.203" THK)	72"
P40-278X096	PIPE 2.5 SCH40 (2.875" OD x 0.203" THK)	96"
P40-278X120	PIPE 2.5 SCH40 (2.875" OD x 0.203" THK)	120"
P40-278X126	PIPE 2.5 SCH40 (2.875" OD x 0.203" THK)	126"
P40-278X150	PIPE 2.5 SCH40 (2.875" OD x 0.203" THK)	150"
P40-278X174	PIPE 2.5 SCH40 (2.875" OD x 0.203" THK)	174"
P40-312X048	PIPE 3 SCH40 (3.5" OD x 0.216" THK)	48"
P40-312X072	PIPE 3 SCH40 (3.5" OD x 0.216" THK)	72"
P40-312X126	PIPE 3 SCH40 (3.5" OD x 0.216" THK)	126"
P40-312X150	PIPE 3 SCH40 (3.5" OD x 0.216" THK)	150"
P40-312X174	PIPE 3 SCH40 (3.5" OD x 0.216" THK)	174"

**NOTE:**  
 APPROVED SMART KIT VENDORS ARE ALLOWED TO SUBSTITUTE AT THEIR DISCRETION  
 PIPES LISTED ON THIS PAGE FOR CUSTOM LENGTH COMPONENTS OF MATCHING SIZE.  
 SUBSTITUTIONS SHALL MEET THE ORIGINAL STRUCTURAL INTENT.

- NOTES:**
1. ALL PIPE GRADE A53-B OR BETTER.
  2. HOT-DIPPED GALVANIZED PER ASTM A123.
  3. ALL HOLES ARE 11/16" DIA. U.N.O
  4. HOLES MAY OR MAY NOT BE PRESENT, DEPEND UPON MANUFACTURE DISCRETION.
  5. ALL FIELD CUT AND DRILLED SURFACES SHALL BE REPAIRED WITH A MINIMUM OF TWO COATS OF ZINGA OR ZINC COTE PER ASTM A780 AND MANUFACTURER'S RECOMMENDATIONS.

DRAWN BY: BT | CHECKED BY: HMA/KW

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	BT	08/04/21

SHEET TITLE:

VZSMART  
 STANDARD PIPE

SHEET NUMBER: VZSMART-PIPE | REV #: 0

# Exhibit D

## **Structural Analysis Report**

Date: May 09, 2023



Crown Castle  
8020 Katy Fwy  
Houston, TX 77024  
(713) 570-3000

**Subject:** Structural Analysis Report

**Carrier Designation:** Verizon Wireless Co-Locate  
**Site Number:** 5000381784  
**Site Name:** Banksville, CT

**Crown Castle Designation:** BU Number: 807132  
Site Name: BRG 133 943050  
JDE Job Number: 747512  
Work Order Number: 2228885  
Order Number: 651059 Rev. 0

**Engineering Firm Designation:** Crown Castle Project Number: 2228885

**Site Data:** 1081 North Street, Greenwich, FAIRFIELD County, CT  
Latitude 41° 8' 21.5", Longitude -73° 38' 30.54"  
175 Foot - Monopole Tower

Crown Castle is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

Sufficient Capacity - 75.9%

This analysis has been performed in accordance with the 2022 Connecticut State Building Code based upon an ultimate 3-second gust wind speed of 115 mph. Applicable Standard references and design criteria are listed in Section 2 - "Analysis Criteria".

Structural analysis prepared by: Mishka Stueber

Respectfully submitted by:

Mishka Stueber, P.E.  
Project Engineer

Digitally  
signed by  
Michelle A  
Stueber  
Date:  
2023.05.10  
13:18:04  
-05'00'

## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration  
Table 2 - Other Considered Equipment

### 3) ANALYSIS PROCEDURE

Table 3 - Documents Provided  
3.1) Analysis Method  
3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)  
Table 5 - Tower Component Stresses vs. Capacity - LC7  
4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

This tower is a 175 ft Monopole tower designed by VALMONT. The tower has been modified multiple times to accommodate additional loading.

## 2) ANALYSIS CRITERIA

<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Wind Speed:</b>	115 mph
<b>Exposure Category:</b>	B
<b>Topographic Factor:</b>	1
<b>Ice Thickness:</b>	1 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Service Wind Speed:</b>	60 mph

**Table 1 - Proposed Equipment Configuration**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
174.0	176.0	3	antel	ADA-85408580CF w/ Mount Pipe	6 1	1-1/4 1-5/8
		6	jma wireless	MX06FRO860-03 w/ Mount Pipe		
		1	rfs celwave	DB-C1-12C-24AB-0Z		
		3	samsung telecommunications	MT6407-77A w/ Mount Pipe		
		3	samsung telecommunications	RF4439D-25A		
		3	samsung telecommunications	RF4440D-13A		
	174.0	-	-	Mount Modifications		
		1	tower mounts	Platform Mount [LP 715-1_KCKR]		

**Table 2 - Other Considered Equipment**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
162.0	168.0	3	cci antennas	HPA-65R-BUU-H6 w/ Mount Pipe	4 1 1 2 4	1-5/8 Conduit 3/8 5/8 1-1/4
		3	ericsson	RRUS 11		
		3	ericsson	RRUS 32 B2		
		3	ericsson	RRUS-32 B30		
		2	kaelus	DBC0061F1V51-2		
		1	kathrein	800 10121 w/ Mount Pipe		
		1	powerwave technologies	7770.00 w/ Mount Pipe		
		4	powerwave technologies	LGP2140X		
		3	quintel technology	QS66512-2 w/ Mount Pipe		

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
	162.0	1	raycap	DC6-48-60-18-8C		
		1	raycap	DC6-48-60-18-8F		
		1	tower mounts	Platform Mount [LP 303-1]		
154.0	154.0	3	fujitsu	TA08025-B604	1	1-3/4
		3	fujitsu	TA08025-B605		
		3	jma wireless	MX08FRO665-21 w/ Mount Pipe		
		1	raycap	RDIDC-9181-PF-48		
		1	tower mounts	Commscope MC-PK8-DSH		
144.0	144.0	3	ericsson	AIR6449 B41_T-MOBILE w/ Mount Pipe	3	1-5/8
		3	ericsson	RADIO 4449 B71/B85A		
		3	ericsson	RADIO 4460 B2/B25 B66_TMO		
		3	rfs celwave	APXVAALL24_43-U-NA20 w/ Mount Pipe		
		1	tower mounts	Sector Mount [SM 502-3]		

### 3) ANALYSIS PROCEDURE

**Table 3 - Documents Provided**

Document	Reference	Source
4-GEOTECHNICAL REPORTS	4837566	CCISITES
4-POST-MODIFICATION INSPECTION	5456964	CCISITES
4-POST-MODIFICATION INSPECTION	3279736	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	1057735	CCISITES
4-TOWER MANUFACTURER DRAWINGS	1057736	CCISITES
4-TOWER REINFORCEMENT DESIGN/DRAWINGS/DATA	4856181	CCISITES
4-TOWER REINFORCEMENT DESIGN/DRAWINGS/DATA	3279725	CCISITES

#### 3.1) Analysis Method

tnxTower (version 8.1.4.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

tnxTower was used to determine the loads on the modified structure. Additional calculations were performed to determine the stresses in the reinforcing elements. These calculations are presented in Appendix C.

### 3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

### 4) ANALYSIS RESULTS

**Table 4 - Section Capacity (Summary)**

Elevation (ft)	Component Type	Size	Critical Element	% Capacity	Pass / Fail
175 - 170	Pole	TP23.025x22.125x0.2188	Pole	7.3%	Pass
170 - 165	Pole	TP23.925x23.025x0.2188	Pole	13.4%	Pass
165 - 160	Pole	TP24.825x23.925x0.2188	Pole	22.8%	Pass
160 - 155	Pole	TP25.725x24.825x0.2188	Pole	30.7%	Pass
155 - 150	Pole	TP27.435x25.725x0.2188	Pole	40.1%	Pass
150 - 145	Pole	TP27.087x26.188x0.3125	Pole	30.8%	Pass
145 - 140	Pole	TP27.987x27.087x0.3125	Pole	37.2%	Pass
140 - 135	Pole	TP28.887x27.987x0.3125	Pole	43.0%	Pass
135 - 130	Pole	TP29.787x28.887x0.3125	Pole	48.5%	Pass
130 - 125	Pole	TP30.687x29.787x0.3125	Pole	53.5%	Pass
125 - 120	Pole	TP31.587x30.687x0.3125	Pole	58.2%	Pass
120 - 115	Pole	TP32.487x31.587x0.3125	Pole	62.6%	Pass
115 - 110	Pole	TP33.387x32.487x0.3125	Pole	66.8%	Pass
110 - 105	Pole	TP34.287x33.387x0.3125	Pole	70.7%	Pass
105 - 101	Pole	TP35.997x34.287x0.3125	Pole	73.6%	Pass
101 - 94.5	Pole	TP35.552x34.382x0.375	Pole	62.7%	Pass
94.5 - 89.5	Pole	TP36.452x35.552x0.375	Pole	65.1%	Pass
89.5 - 84.5	Pole	TP37.352x36.452x0.375	Pole	67.5%	Pass
84.5 - 83.17	Pole	TP37.591x37.352x0.375	Pole	68.1%	Pass
83.17 - 82.92	Pole	TP37.636x37.591x0.375	Pole	68.2%	Pass
82.92 - 77.92	Pole	TP38.536x37.636x0.375	Pole	70.3%	Pass
77.92 - 72.92	Pole	TP39.436x38.536x0.375	Pole	72.4%	Pass
72.92 - 67.92	Pole	TP40.336x39.436x0.375	Pole	74.4%	Pass
67.92 - 65.5	Pole	TP40.772x40.336x0.375	Pole	75.3%	Pass
65.5 - 65.25	Pole	TP40.817x40.772x0.375	Pole	75.4%	Pass
65.25 - 64	Pole	TP41.042x40.817x0.375	Pole	75.9%	Pass
64 - 63.75	Pole + Reinf.	TP41.087x41.042x0.625	Reinf. 10 Tension Rupture	63.8%	Pass
63.75 - 58.75	Pole + Reinf.	TP41.987x41.087x0.625	Reinf. 10 Tension Rupture	65.4%	Pass
58.75 - 53.75	Pole + Reinf.	TP42.886x41.987x0.6125	Reinf. 10 Tension Rupture	66.8%	Pass



53.75 - 53	Pole + Reinf.	TP44.177x42.886x0.6125	Reinf. 10 Tension Rupture	67.0%	Pass
53 - 45.58	Pole + Reinf.	TP43.607x42.272x0.6438	Reinf. 10 Tension Rupture	67.6%	Pass
45.58 - 43	Pole + Reinf.	TP44.072x43.607x0.6438	Reinf. 10 Tension Rupture	68.2%	Pass
43 - 42.75	Pole + Reinf.	TP44.117x44.072x0.6938	Reinf. 10 Tension Rupture	65.9%	Pass
42.75 - 42.5	Pole + Reinf.	TP44.162x44.117x0.6938	Reinf. 10 Tension Rupture	65.9%	Pass
42.5 - 42.25	Pole + Reinf.	TP44.207x44.162x0.7813	Reinf. 10 Tension Rupture	56.9%	Pass
42.25 - 42	Pole + Reinf.	TP44.252x44.207x0.7813	Reinf. 10 Tension Rupture	56.9%	Pass
42 - 41.75	Pole + Reinf.	TP44.297x44.252x0.6813	Reinf. 10 Tension Rupture	64.8%	Pass
41.75 - 36.75	Pole + Reinf.	TP45.197x44.297x0.6813	Reinf. 10 Tension Rupture	65.9%	Pass
36.75 - 32	Pole + Reinf.	TP46.052x45.197x0.6688	Reinf. 10 Tension Rupture	66.9%	Pass
32 - 31.75	Pole + Reinf.	TP46.097x46.052x0.7188	Reinf. 9 Tension Rupture	61.6%	Pass
31.75 - 26.75	Pole + Reinf.	TP46.997x46.097x0.7063	Reinf. 9 Tension Rupture	62.6%	Pass
26.75 - 21.75	Pole + Reinf.	TP47.897x46.997x0.7063	Reinf. 9 Tension Rupture	63.5%	Pass
21.75 - 18	Pole + Reinf.	TP48.572x47.897x0.7063	Reinf. 9 Tension Rupture	64.2%	Pass
18 - 17.75	Pole + Reinf.	TP48.617x48.572x0.7063	Reinf. 9 Tension Rupture	64.2%	Pass
17.75 - 17	Pole + Reinf.	TP50.027x48.617x0.7063	Reinf. 9 Tension Rupture	64.4%	Pass
17 - 8.92	Pole + Reinf.	TP49.394x47.94x0.6625	Reinf. 1 Compression	67.9%	Pass
8.92 - 3.92	Pole + Reinf.	TP50.294x49.394x0.6625	Reinf. 1 Compression	68.6%	Pass
3.92 - 2.75	Pole + Reinf.	TP50.505x50.294x0.6625	Reinf. 1 Connection	68.7%	Pass
2.75 - 2.5	Pole + Reinf.	TP50.55x50.505x0.7125	Reinf. 12 Connection	66.7%	Pass
2.5 - 0	Pole + Reinf.	TP51x50.55x0.7125	Reinf. 12 Connection	67.0%	Pass
				Summary	
			Pole	75.9%	Pass
			Reinforcement	68.7%	Pass
			Overall	75.9%	Pass

**Table 5 - Tower Component Stresses vs. Capacity - LC7**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	64.9	Pass
1	Base Plate	0	41.5	Pass
1	Base Foundation (Structure)	0	70.2	Pass
1	Base Foundation (Soil Interaction)	0	6.8	Pass

<b>Structure Rating (max from all components) =</b>	<b>75.9%</b>
---	--------------

Notes:


- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

**4.1) Recommendations**

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

**APPENDIX A**  
**TNXTOWER OUTPUT**

Section	Length (ft)	Number of Sides	Thickness (in)	Socket Length (ft)	Top Dia (in)	Bot Dia (in)	Grade	Weight (K)
1	5.00	12	0.3125	4.50	24.825	24.825	0.3	0.3
2	5.00	12	0.3125	4.50	29.830	29.830	0.3	0.3
3	5.00	12	0.3125	4.50	34.835	34.835	0.3	0.3
4	5.00	12	0.3125	4.50	39.840	39.840	0.3	0.3
5	5.00	12	0.3125	4.50	44.845	44.845	0.3	0.3
6	5.00	12	0.3125	4.50	49.850	49.850	0.3	0.3
7	5.00	12	0.3125	4.50	54.855	54.855	0.3	0.3
8	5.00	12	0.3125	4.50	59.860	59.860	0.3	0.3
9	5.00	12	0.3125	4.50	64.865	64.865	0.3	0.3
10	5.00	12	0.3125	4.50	69.870	69.870	0.3	0.3
11	5.00	12	0.3125	4.50	74.875	74.875	0.3	0.3
12	5.00	12	0.3125	4.50	79.880	79.880	0.3	0.3
13	5.00	12	0.3125	4.50	84.885	84.885	0.3	0.3
14	5.00	12	0.3125	4.50	89.890	89.890	0.3	0.3
15	5.00	12	0.3125	4.50	94.895	94.895	0.3	0.3
16	5.00	12	0.3125	4.50	99.900	99.900	0.3	0.3
17	5.00	12	0.3125	4.50	104.905	104.905	0.3	0.3
18	5.00	12	0.3125	4.50	109.910	109.910	0.3	0.3
19	5.00	12	0.3125	4.50	114.915	114.915	0.3	0.3
20	5.00	12	0.3125	4.50	119.920	119.920	0.3	0.3
21	5.00	12	0.3125	4.50	124.925	124.925	0.3	0.3
22	5.00	12	0.3125	4.50	129.930	129.930	0.3	0.3
23	5.00	12	0.3125	4.50	134.935	134.935	0.3	0.3
24	5.00	12	0.3125	4.50	139.940	139.940	0.3	0.3
25	5.00	12	0.3125	4.50	144.945	144.945	0.3	0.3
26	5.00	12	0.3125	4.50	149.950	149.950	0.3	0.3
27	5.00	12	0.3125	4.50	154.955	154.955	0.3	0.3
28	5.00	12	0.3125	4.50	159.960	159.960	0.3	0.3
29	5.00	12	0.3125	4.50	164.965	164.965	0.3	0.3
30	5.00	12	0.3125	4.50	169.970	169.970	0.3	0.3
31	5.00	12	0.3125	4.50	174.975	174.975	0.3	0.3
32	5.00	12	0.3125	4.50	179.980	179.980	0.3	0.3
33	5.00	12	0.3125	4.50	184.985	184.985	0.3	0.3
34	5.00	12	0.3125	4.50	189.990	189.990	0.3	0.3
35	5.00	12	0.3125	4.50	194.995	194.995	0.3	0.3
36	5.00	12	0.3125	4.50	199.000	199.000	0.3	0.3
37	5.00	12	0.3125	4.50	204.005	204.005	0.3	0.3
38	5.00	12	0.3125	4.50	209.010	209.010	0.3	0.3
39	5.00	12	0.3125	4.50	214.015	214.015	0.3	0.3
40	5.00	12	0.3125	4.50	219.020	219.020	0.3	0.3
41	5.00	12	0.3125	4.50	224.025	224.025	0.3	0.3
42	5.00	12	0.3125	4.50	229.030	229.030	0.3	0.3
43	5.00	12	0.3125	4.50	234.035	234.035	0.3	0.3
44	5.00	12	0.3125	4.50	239.040	239.040	0.3	0.3
45	5.00	12	0.3125	4.50	244.045	244.045	0.3	0.3
46	5.00	12	0.3125	4.50	249.050	249.050	0.3	0.3
47	5.00	12	0.3125	4.50	254.055	254.055	0.3	0.3
48	5.00	12	0.3125	4.50	259.060	259.060	0.3	0.3
49	5.00	12	0.3125	4.50	264.065	264.065	0.3	0.3
50	5.00	12	0.3125	4.50	269.070	269.070	0.3	0.3




### MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

### TOWER DESIGN NOTES

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-H Standard.
3. Tower designed for a 115 mph basic wind in accordance with the TIA-222-H Standard.
4. Tower is also designed for a 50 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Risk Category II.
7. Topographic Category 1 with Crest Height of 0.00 ft
8. TOWER RATING: 75.9%



<b>Crown Castle</b> 8020 Katy Fwy Houston, TX 77024 The Pathway to Possible Phone: (713) 570-3000 FAX:		Job: <b>807132</b>		
		Project:	Client: Crown Castle	Drawn by: Mishka Stueber
		Code: TIA-222-H	Date: 05/09/23	Scale: NTS
		Path: C:\Users\mstueber1\SAP\Work Area\807132\WO 222885 - SAIProd\807132-R.dwg		Dwg No. E-1

## Tower Input Data

The tower is a monopole.  
 This tower is designed using the TIA-222-H standard.  
 The following design criteria apply:

- Tower is located in Fairfield County, Connecticut.
- Tower base elevation above sea level: 503.00 ft.
- Basic wind speed of 115 mph.
- Risk Category II.
- Exposure Category B.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 1.0000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- TOWER RATING: 75.9%.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used:  $K_{es}(F_w) = 0.95$ ,  $K_{es}(t_i) = 0.85$ .
- Maximum demand-capacity ratio is: 1.05.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

Consider Moments - Legs Consider Moments - Horizontals  Consider Moments - Diagonals Use Moment Magnification ✓ Use Code Stress Ratios ✓ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric	Distribute Leg Loads As Uniform Assume Legs Pinned  ✓ Assume Rigid Index Plate ✓ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension ✓ Bypass Mast Stability Checks ✓ Use Azimuth Dish Coefficients ✓ Project Wind Area of Appurt. Autocalc Torque Arm Areas Add IBC .6D+W Combination ✓ Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs	Use ASCE 10 X-Brace Ly Rules Calculate Forces in Supporting Bracing Members Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation ✓ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption <div style="background-color: #e0e0e0; text-align: center; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known
--	---	--

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	175.00-170.00	5.00	0.00	12	22.1250	23.0250	0.2188	0.8750	A572-65

# Monopole Base Plate Connection




Site Info	
BU #	807132
Site Name	BRG 133 943050
Order #	651059 Rev. 0

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	See Custom Sheet
$I_{ar}$ (in)	See Custom Sheet

Applied Loads	
Moment (kip-ft)	3940.80
Axial Force (kips)	77.59
Shear Force (kips)	30.54

\*TIA-222-H Section 15.5 Applied



Connection Properties	Analysis Results
-----------------------	------------------

**Anchor Rod Data**

GROUP 1: (16) 2-1/4"  $\phi$  bolts (A615-75 N;  $F_y=75$  ksi,  $F_u=100$  ksi) on 59.3" BC  
 GROUP 2: (4) 2"  $\phi$  bolts (A193 Gr. B7 N;  $F_y=105$  ksi,  $F_u=125$  ksi) on 62.5" BC  
 pos. (deg): 10, 80, 190, 280

**Base Plate Data**

63.5" OD x 2.75" Plate (A572-60;  $F_y=60$  ksi,  $F_u=75$  ksi)

**Stiffener Data**

N/A

**Pole Data**

51" x 0.4375" 12-sided pole (A572-65;  $F_y=65$  ksi,  $F_u=80$  ksi)

Anchor Rod Summary		(units of kips, kip-in)
<b>GROUP 1:</b>		
$P_u_t = 166.23$	$\phi P_n_t = 243.75$	<b>Stress Rating</b>
$V_u = 1.91$	$\phi V_n = 149.1$	<b>64.9%</b>
$M_u = n/a$	$\phi M_n = n/a$	<b>Pass</b>
<b>GROUP 2:</b>		
$P_u_t = 134.17$	$\phi P_n_t = 234.38$	<b>Stress Rating</b>
$V_u = 0$	$\phi V_n = 147.26$	<b>54.5%</b>
$M_u = n/a$	$\phi M_n = n/a$	<b>Pass</b>

Base Plate Summary		
Max Stress (ksi):	23.55	(Flexural)
Allowable Stress (ksi):	54	
Stress Rating:	<b>41.5%</b>	<b>Pass</b>

# CCIplate



Elevation (ft) 0 (Base)

note: Bending interaction not considered when Grout Considered = "Yes"

Bolt Group	Resist Axial	Resist Shear	Induce Plate Bending	Grout Considered	Apply at BARB Elevation	BARB CL Elevation (ft)
1	Yes	Yes	Yes	No	No	
2						

Custom Bolt Connection										
Bolt	Bolt Group ID	Location (deg.)	Diameter (in)	Material	Bolt Circle (in)	Eta Factor, n:	$l_{ar}$ (in):	Thread Type	Area Override, in <sup>2</sup>	Tension Only
1	1	0	2.25	A615-75	59.3	0.5	1.5	N-Included		No
2	1	22.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
3	1	45	2.25	A615-75	59.3	0.5	1.5	N-Included		No
4	1	67.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
5	1	90	2.25	A615-75	59.3	0.5	1.5	N-Included		No
6	1	112.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
7	1	135	2.25	A615-75	59.3	0.5	1.5	N-Included		No
8	1	157.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
9	1	180	2.25	A615-75	59.3	0.5	1.5	N-Included		No
10	1	202.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
11	1	225	2.25	A615-75	59.3	0.5	1.5	N-Included		No
12	1	247.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
13	1	270	2.25	A615-75	59.3	0.5	1.5	N-Included		No
14	1	292.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
15	1	315	2.25	A615-75	59.3	0.5	1.5	N-Included		No
16	1	337.5	2.25	A615-75	59.3	0.5	1.5	N-Included		No
17	2	10	2	A193 Gr. B7	62.5	0.5	1.5	N-Included		No
18	2	80	2	A193 Gr. B7	62.5	0.5	1.5	N-Included		No
19	2	190	2	A193 Gr. B7	62.5	0.5	1.5	N-Included		No
20	2	280	2	A193 Gr. B7	62.5	0.5	1.5	N-Included		No

## Plot Graphic



## Drilled Pier Foundation

BU # :	807132
Site Name:	BRG 133 943050
Order Number:	651059 Rev. 0
TIA-222 Revision:	H
Tower Type:	Monopole



Applied Loads	
Comp.	Uplift
Moment (kip-ft)	3940.8
Axial Force (kips)	77.6
Shear Force (kips)	30.52

Material Properties	
Concrete Strength, f <sub>c</sub> :	3 ksi
Rebar Strength, F <sub>y</sub> :	60 ksi
Tie Yield Strength, F <sub>y</sub> :	40 ksi

Pier Design Data	
Depth	30 ft
Ext. Above Grade	0.5 ft
Pier Section 1	
<i>From 0.5' above grade to 10' below grade</i>	
Pier Diameter	7 ft
Rebar Quantity	24
Rebar Size	14
Clear Cover to Ties	3 in
Tie Size	6
Tie Spacing	10 in

Rebar & Pier Options

Embedded Pole Inputs

Belled Pier Inputs

Pier Section 2	
<i>From 10' below grade to 30' below grade</i>	
Pier Diameter	7 ft
Rebar Quantity	24
Rebar Size	14
Clear Cover to Ties	3 in
Tie Size	
Tie Spacing	in

Analysis Results		
<b>Soil Lateral Check</b>		
	Compression	Uplift
D <sub>v=0</sub> (ft from TOC)	9.06	-
Soil Safety Factor	23.05	-
Max Moment (kip-ft)	4187.82	-
Rating*	5.5%	-
<b>Soil Vertical Check</b>		
	Compression	Uplift
Skin Friction (kips)	2312.86	-
End Bearing (kips)	1711.31	-
Weight of Concrete (kips)	211.28	-
Total Capacity (kips)	4024.17	-
Axial (kips)	288.88	-
Rating*	6.8%	-
<b>Reinforced Concrete Flexure</b>		
	Compression	Uplift
Critical Depth (ft from TOC)	8.75	-
Critical Moment (kip-ft)	4186.12	-
Critical Moment Capacity	8222.90	-
Rating*	48.5%	-
<b>Reinforced Concrete Shear</b>		
	Compression	Uplift
Critical Depth (ft from TOC)	19.78	-
Critical Shear (kip)	387.74	-
Critical Shear Capacity	525.77	-
Rating*	70.2%	-
<b>Structural Foundation Rating*</b>		<b>70.2%</b>
<b>Soil Interaction Rating*</b>		<b>6.8%</b>

\*Rating per TIA-222-H Section 15.5

Check Limitation	
Apply TIA-222-H Section 15.5:	<input checked="" type="checkbox"/>
N/A	<input type="checkbox"/>
Additional Longitudinal Rebar	
Input Effective Depths (else Actual):	<input type="checkbox"/>
Shear Design Options	
Check Shear along Depth of Pier:	<input checked="" type="checkbox"/>
Utilize Shear-Friction Methodology:	<input type="checkbox"/>
Override Critical Depth:	<input type="checkbox"/>

[Go to Soil Calculations](#)

Soil Profile													
Groundwater Depth	N/A			# of Layers	7								



Layer	Top (ft)	Bottom (ft)	Thickness (ft)	γ <sub>soil</sub> (pcf)	γ <sub>concrete</sub> (pcf)	Cohesion (ksf)	Angle of Friction (degrees)	Calculated Ultimate Skin Friction Comp (ksf)	Calculated Ultimate Skin Friction Uplift (ksf)	Ultimate Skin Friction Comp Override (ksf)	Ultimate Skin Friction Uplift Override (ksf)	Ult. Net Bearing Capacity (ksf)	SPT Blow Count	Soil Type
1	0	2	2	110	150	0	0	0.000	0.000	0.00	0.00			Cohesionless
2	2	3.3	1.3	115	150	0	0	0.000	0.000	0.00	0.00			Cohesionless
3	3.3	4	0.7	115	150	0	30	0.000	0.000	0.00	0.00			Cohesionless
4	4	5	1	125	150	0	35	0.000	0.000	0.00	0.00			Cohesionless
5	5	8	3	125	150	0	35	0.000	0.000	0.93	0.93			Cohesionless
6	8	10	2	170	150	15	0	6.750	6.750	1.22	1.22			Cohesive
7	10	30	20	170	150	15	0	6.75	6.75			54.6		Cohesive

# ASCE 7 Hazards Report

**Address:**  
No Address at This Location

**Standard:** ASCE/SEI 7-16  
**Risk Category:** II  
**Soil Class:** D - Default (see Section 11.4.3)

**Latitude:** 41.139306  
**Longitude:** -73.641817  
**Elevation:** 502.51 ft (NAVD 88)



## Wind

### Results:

Wind Speed	115 Vmph
10-year MRI	75 Vmph
25-year MRI	84 Vmph
50-year MRI	90 Vmph
100-year MRI	96 Vmph

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2  
Date Accessed: Tue May 09 2023

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2. Glazed openings need not be protected against wind-borne debris.







**Site Soil Class:**

**Results:**

$S_s$ :	0.274	$S_{D1}$ :	0.096
$S_1$ :	0.06	$T_L$ :	6
$F_a$ :	1.581	PGA :	0.167
$F_v$ :	2.4	PGA <sub>M</sub> :	0.245
$S_{MS}$ :	0.434	$F_{PGA}$ :	1.466
$S_{M1}$ :	0.143	$I_e$ :	1
$S_{DS}$ :	0.289	$C_v$ :	0.849

**Seismic Design Category: B**



**Data Accessed:**

**Tue May 09 2023**

**Date Source:**

**USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.**

## Ice

---

**Results:**

Ice Thickness: 1.00 in.  
Concurrent Temperature: 15 F  
Gust Speed 50 mph

**Data Source:** Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

**Date Accessed:** Tue May 09 2023

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

# Exhibit E

## **Mount Analysis**

Colliers Engineering & Design  
1055 Washington Boulevard  
Stamford, CT 06901  
860.395.0055  
peter.albano@collierseng.com

## Post-Modification Antenna Mount Analysis Report and PMI Requirements

Mount ReAnalysis-VZW

SMART Tool Project #: 10201832  
Colliers Engineering & Design Project #: 22777017 (Rev. 1)

May 5, 2023

### Site Information

Site ID: 5000381784-VZW / BANKSVILLE CT  
Site Name: BANKSVILLE CT  
Carrier Name: Verizon Wireless  
Address: 1081 North Street  
Greenwich, Connecticut 06831  
Fairfield County  
Latitude: 41.139306°  
Longitude: -73.641806°

### Structure Information

Tower Type: 175-Ft Monopole  
Mount Type: 12.83-Ft Platform

FUZE ID # 16092558

### Analysis Results

Platform: 55.7% **Pass w/ Modifications\***

**\*Antennas and equipment to be installed in compliance with PMI Requirements of this mount analysis.**

### \*\*\*Contractor PMI Requirements:

Included at the end of this MA report  
Available & Submitted via portal at <https://pmi.vzwsmart.com>  
For additional questions and support, please reach out to:  
[pmisupport@colliersengineering.com](mailto:pmisupport@colliersengineering.com)

Report Prepared By: Frank Centone



## **Executive Summary:**

The objective of this report is to summarize the analysis results of the antenna support mount including the proposed modifications at the subject facility for the final wireless telecommunications configuration, per the applicable codes and standards.

This analysis is inclusive of the mount structure only and does not address the structural capacity of the supporting structure. This mounting frame was not analyzed as an anchor attachment point for fall protection. All climbing activities are required to have a fall protection plan completed by a competent person.

## **Sources of Information:**

<b>Document Type</b>	<b>Remarks</b>
<i>Radio Frequency Data Sheet (RFDS)</i>	<i>Verizon RFDS, Site ID: 323417, dated October 27, 2022</i>
<i>Mount Mapping</i>	<i>Onsight Services LLC, Site ID: 4679814, dated April 8, 2022</i>
<i>Previous Mount Analysis</i>	<i>Maser Consulting Connecticut, Project #: 22777017A, dated May 10, 2022</i>
<i>Mount Modification Drawings</i>	<i>Maser Consulting Connecticut, Project #: 22777017A, dated May 5, 2023</i>

## **Analysis Criteria:**

Codes and Standards:	ANSI/TIA-222-H 2022 Connecticut State Building Code (CSBC), Effective October 1, 2022
Wind Parameters:	Basic Wind Speed (Ultimate 3-sec. Gust), $V_{ULT}$ : 120 mph Ice Wind Speed (3-sec. Gust): 50 mph Design Ice Thickness: 1.00 in Risk Category: II Exposure Category: B Topographic Category: 1 Topographic Feature Considered: N/A Topographic Method: N/A Ground Elevation Factor, $K_e$ : 0.982
Seismic Parameters:	$S_s$ : 0.274 g $S_1$ : 0.060 g
Maintenance Parameters:	Wind Speed (3-sec. Gust): 30 mph Maintenance Load, $L_v$ : 250 lbs. Maintenance Load, $L_m$ : 500 lbs.
Analysis Software:	RISA-3D (V17)

**Final Loading Configuration:**

The following equipment has been considered for the analysis of the mount:

Mount Elevation (ft)	Equipment Elevation (ft)	Quantity	Manufacturer	Model	Status
172.75	176.00	6	JMA Wireless	MX06FRO860-03	Added
		3	Samsung	MT6407-77A	
		3	Samsung	RF4439d-25A	
		3	Samsung	RF4440d-13A	
		1	RFS	DB-C1-12C-24AB-0Z	
		3	Unknown	Spare	Retained

The recent mount mapping did not report existing OVP units. However, it is acceptable to install up to any three (3) of the OVP model numbers listed below as required at any location other than the mount face without affecting the structural capacity of the mount. If OVP units are installed on the mount face, a mount re-analysis may be required.

Model Number	Ports	AKA
DB-B1-6C-12AB-0Z	6	OVP-6
RVZDC-6627-PF-48	12	OVP-12

**Standard Conditions:**

1. All engineering services are performed on the basis that the information provided to Colliers Engineering & Design and used in this analysis is current and correct. The existing equipment loading has been applied at locations determined from the supplied documentation. Any deviation from the loading locations specified in this report shall be communicated to Colliers Engineering & Design to verify deviation will not adversely impact the analysis.
2. Mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer’s specifications.

Obvious safety and structural issues/deficiencies noticed at the time of the mount mapping and reported in the Mount Mapping Report are assumed to be corrected and documented as part of the PMI process and are not considered in the mount analysis.

The mount analysis and the mount mapping are not a condition assessment of the mount. Proper maintenance and condition assessments are still required post analysis.

3. For mount analyses completed from other data sources (including new replacement mounts) and not specifically mapped in accordance with the NSTD-446 Standard, the mounts are assumed to have been properly fabricated, installed and maintained in good condition, twist free and plumb in accordance with its original design and manufacturer’s specifications.
4. All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
5. The mount was checked up to, and including, the bolts that fasten it to the mount collar/attachment and threaded rod connections in collar members if applicable. Local deformation and interaction between the mount collar/attachment and the supporting tower structure are outside the scope of this analysis.
6. All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. Colliers Engineering & Design is not responsible for the conclusion, opinions, and recommendations made by others based on the information supplied.

7. Structural Steel Grades have been assumed as follows, if applicable, unless otherwise noted in this analysis:
  - Channel, Solid Round, Angle, Plate      ASTM A36 (Gr. 36)
  - HSS (Rectangular)                              ASTM 500 (Gr. B-46)
  - Pipe    ASTM A53 (Gr. B-35)
  - Threaded Rod                                      F1554 (Gr. 36)
  - Bolts    ASTM A325
  
8. Any mount modifications listed under Sources of Information are assumed to have been installed per the design specifications.

**Discrepancies between in-field conditions and the assumptions listed above may render this analysis invalid unless explicitly approved by Colliers Engineering & Design.**

**Analysis Results:**

Component	Utilization %	Pass/Fail
Face Horizontal	36.4%	Pass
Standoff Horizontal	16.7%	Pass
Standoff Brace	43.6%	Pass
Standoff Tab	36.8%	Pass
Corner Plate	36.8%	Pass
Support Rail	25.9%	Pass
Support Rail Plate	5.6%	Pass
Mount Pipe	54.1%	Pass
Mod Replacement Mount Pipe	55.7%	Pass
Mod Kicker	10.2%	Pass
Mod Support Rail	22.9%	Pass
Mod Support Rail Corner	39.1%	Pass
Mount Connection	24.2%	Pass

<b>Structure Rating – (Controlling Utilization of all Components)</b>	<b>55.7%</b>
---	--------------

**Mount Steel (EPA)a per ANSI/TIA-222-H Section 2.6.11.2:**

Ice Thickness (In)	Mount Pipes Excluded		Mount Pipes Included	
	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)	Front (EPA)a (Sq. Ft.)	Side (EPA)a (Sq. Ft.)
0	57.3	57.3	73.9	73.9
0.5	69.1	69.1	92.5	92.5
1	80.1	80.1	110.1	110.1

**Notes:**

- (EPA)a values listed above may be used in the absence of more precise information
- (EPA)a values in the table above include 3 sector(s).
- Ka factors included in (EPA)a calculations

### **Requirements:**

The existing mount will be **SUFFICIENT** for the final loading configuration (attachment 2) **after the modifications detailed in attachment 3 are successfully completed.**

ANSI/ASSP rigging plan review services compliant with the requirements of ANSI/TIA 322 are available for a Construction Class IV site or other, if required. Separate review fees will apply.

### **Attachments:**

1. **Contractor Required PMI Report Deliverables**
2. Antenna Placement Diagrams
3. Mount Modification Drawings
4. Mount Photos
5. Mount Mapping Report (for reference only)
6. Analysis Calculations



# Mount Desktop – Post Modification Inspection (PMI) Report Requirements

## Documents & Photos Required from Contractor – Mount Modification

Electronic pdf version of this can be downloaded at <https://pmi.vzwsmart.com>  
For additional questions and support, please reach out to [pmisupport@colliersengineering.com](mailto:pmisupport@colliersengineering.com)

---

MDG #: 5000381784

SMART Project #: 10201832

Fuze Project ID: 16092558

**Purpose** – to upload the proper documentation to the SMART Tool in order to allow the SMART Tool engineering vendor to complete the required Mount Desktop review of the Post Modification Inspection Report.

- Contractor is responsible for making certain the photos provided as noted below provide confirmation that the modification was completed in accordance with the modification drawings.
- Contractor shall relay any data that can impact the performance of the mount or the mount modification, this includes safety issues.

### **Base Requirements:**

- If installation of the modification will cause damage to the structure, the climbing facility, or safety climb if present or any installed system, SMART Tool vendor to be notified prior to install. Any special photos outside of the standard requirements will be indicated on the drawings.
- Provide “as built drawings” showing contractor’s name, preparer’s signature, and date. Any deviations from the drawings (proposed modification) shall be shown. NOTE: If loading is different than what is conveyed in the post-modification passing mount analysis (MA) contact the SMART Tool vendor immediately.
- Each photo shall be time and date stamped.
- Photos should be high resolution.
- Contractor shall ensure that the safety climb wire rope is not adversely impacted by the install of the modification components. This may involve the install of wire rope guides, or other items to protect the wire rope. If there is conflict, contact the SMART Tool engineer for recommendations.
- The PMI can be accessed at the following portal: <https://pmi.vzwsmart.com>

### **Photo Requirements:**

- Photos taken at ground level
  - Photo of Gate Signs showing the tower owner, site name, and number.
  - Overall tower structure after installation of the modifications.
  - Photos of the mount after installation of the modifications; if the mounts are at different rad elevations, pictures must be provided for all elevations that the modifications were installed
- Photos taken at Mount Elevation
  - Photos showing the safety climb wire rope above and below the mount prior to modification.
  - Photos showing the climbing facility and safety climb if present.

- Photos showing each individual sector after installation of modifications. Each entire sector must be in one photo to show the interconnection of members.
  - These photos shall also certify that the placement and geometry of the equipment on the mount is as depicted in the antenna placement diagram in this form.
- Photos that show the model number of each antenna and piece of equipment installed per sector.
- Photos of each installed modification per the modification drawings; pictures shall also include connection hardware (U-bolts, bolts, nuts, all-threaded rods, etc.)
- Photos showing the distances (relative distance between collars) of the installed modifications from the appropriate reference locations shown in the modification drawings.
- Photos showing the installed modifications onto the tower (i.e. ring/collar mounts, tie-backs, V-bracing kits, etc.); if the existing mount elevation needs to be changed according to the modification drawings, an elevation measurement shall be provided before the elevation change.

**Material Certification:**

- Materials utilized must be as per specification on the drawings or the equivalent as validated by the SMART Tool vendor.
  - If the materials are as specified on the drawings
    - The contractor shall provide the packing list, or the materials certifications for the materials utilized to perform the mount modification
    - Commscope, Metrosite, Perfect Vision, Sabre, and Site Pro have all agreed to support Verizon vendors with the necessary material certifications
  - If seeking permission to use an equivalent
    - It is required that the SMART Tool engineering vendor approval of such is included in the contractor submission package. There may be an additional charge for approval if the equivalent submission doesn't meet specifications as prescribed in the drawings.

All hardware has been properly installed, and the existing hardware was inspected.

The material utilized was as specified on the SMART Tool engineering vendor Mount Modification Drawings and included in the material certification folder is a packing list or invoice for these materials.

OR

The material utilized was approved by a SMART Tool engineering vendor as an "equivalent" and this approval is included as part of the contractor submission.

**Antenna & Equipment Placement and Geometry Confirmation:**

The contractor certifies that the photos support and the equipment on the mount is as depicted on the sketch and table included in this form and with the mount analysis provided.

OR

- The contractor notes that the equipment on the mount is not in accordance with the sketch and has noted the differences below and provided photo documentation of any alterations.

**Comments:**

**Was the mount modification completed in conjunction with the equipment change / installation?**

- Yes       No

**Special Instructions / Validation as required from the MA or Mod Drawings:**

**Issue:**

1. Contractor shall install (1) proposed OVP at position 4 in alpha sector with pipe-to-pipe clamp (Part #: VZWSMART-MSK3). Max. unbraced length of threaded rod shall not exceed 3" (Refer to Placement Diagram).

**Response:**

**Special Instruction Confirmation:**

- The contractor has read and acknowledges the above special instructions.

**Comments:**

**Contractor certifies that the climbing facility / safety climb was not damaged prior to starting work:**

- Yes       No

**Contractor certifies no new damage created during the current installation:**

- Yes       No

**Contractor to certify the condition of the safety climb and verify no damage when leaving the site:**

- Safety Climb in Good Condition       Safety Climb Damaged


**Comments:**

--


**Certifying Individual:**

Company:	
Employee Name:	
Contact Phone:	
Email:	
Date:	

Plan View




Front View - Looking at Structure




Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A1	MX06FRO860-03	95.9	15.4	112.5	2	a	Front	36	-8	Added	
A1	MX06FRO860-03	95.9	15.4	112.5	2	b	Front	36	8	Added	
R3	RF4439d-25A	15	15	112.5	2	a	Behind	19.2	0	Added	
A8	Spare	70	5	77.5	3	a	Front	33	0	Retained	04/08/2022
R4	RF4440d-13A	15	15	77.5	3	a	Behind	18	0	Added	
A5	DB-C1-12C-24AB-0Z	29.5	16.5	42.5	4	a	Behind	12	0	Added	
R2	MT6407-77A	35.1	16.1	7	5	a	Front	29.04	0	Added	

Plan View




Front View - Looking at Structure




Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A8	Spare	70	5	112.5	2	a	Front	33	0	Retained	04/08/2022
R4	RF4440d-13A	15	15	112.5	2	a	Behind	18	0	Added	
A1	MX06FRO860-03	95.9	15.4	77.5	3	a	Front	33	-8	Added	
A1	MX06FRO860-03	95.9	15.4	77.5	3	b	Front	33	8	Added	
R3	RF4439d-25A	15	15	77.5	3	a	Behind	19.2	0	Added	
R2	MT6407-77A	35.1	16.1	7	4	a	Front	29.04	0	Added	

Plan View



Front View - Looking at Structure



Ref#	Model	Height (in)	Width (in)	H Dist Frm L.	Pipe #	Pipe Pos V	Ant Pos	C. Ant Frm T.	Ant H Off	Status	Validation
A8	Spare	70	5	112.5	2	a	Front	33	0	Retained	04/08/2022
R4	RF4440d-13A	15	15	112.5	2	a	Behind	18	0	Added	
A1	MX06FRO860-03	95.9	15.4	77.5	3	a	Front	33	-8	Added	
A1	MX06FRO860-03	95.9	15.4	77.5	3	b	Front	33	8	Added	
R3	RF4439d-25A	15	15	77.5	3	a	Behind	19.2	0	Added	
R2	MT6407-77A	35.1	16.1	7	4	a	Front	29.04	0	Added	



MOUNT MODIFICATION DRAWINGS  
EXISTING 12.83' PLATFORM

TOWER OWNER: CROWN CASTLE  
TOWER OWNER SITE NUMBER: 807132

CARRIER SITE NAME: BANKSVILLE CT  
CARRIER SITE NUMBER: 5000381784  
FUZE ID: 16092558

1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY

LATITUDE: 41.139306° N  
LONGITUDE: 73.641806° W



www.colliersengineering.com

Copyright © 2023, Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, re-used, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.



**811** PROTECT YOURSELF  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE  
Know what's below. Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE: AS SHOWN JOB NUMBER: 22777017

REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
1	05/05/23	ISSUED FOR CONSTRUCTION	FAC	PMA
0	05/13/22	ISSUED FOR CONSTRUCTION	PD	DRH

COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC-0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SITE NAME:

BANKSVILLE CT  
5000381784  
1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY

**Colliers** STAMFORD  
1055 Washington Boulevard  
Stamford, CT 06901  
Phone: 203.324.0800  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
DOING BUSINESS AS MASER CONSULTING  
Engineering & Design

SHEET TITLE: TITLE SHEET

SHEET NUMBER: ST-1

DESIGN CRITERIA
<p><u>WIND LOADS</u></p> <p>BASIC WIND SPEED (3 SECOND GUST), V = 120 MPH EXPOSURE CATEGORY B TOPOGRAPHIC CATEGORY: I TOPOGRAPHIC CONSIDERED: N/A TOPOGRAPHIC METHOD: N/A MEAN BASE ELEVATION (AMSL) = 502.51'</p> <p><u>ICE LOADS</u></p> <p>ICE WIND SPEED (3 SECOND GUST), V = 50 MPH ICE THICKNESS = 1.00 IN</p> <p><u>SEISMIC LOADS</u></p> <p>SEISMIC DESIGN CATEGORY B SHORT TERM MCER GROUND MOTION, S<sub>s</sub> = .274 LONG TERM MCER GROUND MOTION, S<sub>l</sub> = .060</p>

PROJECT INFORMATION
<p><u>APPLICANT/LESSEE</u></p> <p>COMPANY: VERIZON WIRELESS</p> <p><u>CLIENT REPRESENTATIVE</u></p> <p>COMPANY: VERIZON WIRELESS</p> <p><u>PROJECT MANAGER</u></p> <p>COMPANY: COLLIERS ENGINEERING &amp; DESIGN CONTACT: PETER ALBANO PHONE: 856.797.0412 E-MAIL: PETER.ALBANO@COLLIERSENG.COM</p>
<p><u>CONTRACTOR PMI REQUIREMENTS</u></p> <p>PMI LOCATION: HTTPS://PMI.VZWSMART.COM SMART TOOL PROJECT #: 10201832 VZW MDG #: 5000381784 ANALYSIS DATE: 5/5/2023</p>
PMI REQUIREMENTS EMBEDDED WITHIN MOUNT MODIFICATION REPORT

SHEET INDEX
SHEET DESCRIPTION
ST-1 TITLE SHEET
SBOM-1 BILL OF MATERIALS
SGN-1 GENERAL NOTES
SCF-1 CLIMBING FACILITY DETAIL
SS-1 MODIFICATION DETAILS
SS-2 MOUNT PHOTOS
SPECIFICATION SHEETS

**COPYRIGHT ©2023**  
**COLLIERS ENGINEERING & DESIGN**  
**ALL RIGHTS RESERVED**  
THIS DRAWING AND ALL THE INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE COPIED, REUSED, DISCLOSED, DISTRIBUTED OR RELIED UPON FOR ANY OTHER PURPOSE WITHOUT THE EXPRESS WRITTEN CONSENT OF COLLIERS ENGINEERING & DESIGN.



# BILL OF MATERIALS

## SECTION 1 - VZWSMART KITS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS.)	WEIGHT (LBS.)
1	VZWSMART	VZWSMART-PLK1	SUPPORT RAIL KIT	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1.	504	504
1		VZWSMART-PLK5	KICKER KIT	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1.	291	291
1		VZWSMART-PLK7	MONOPOLE COLLAR MOUNT ASSEMBLY		150	150
1		VZWSMART-MSK1	CROSSOVER PLATE		14	14
1		VZWSMART-MSK3	PIPE TO PIPE CLAMPS		20	20

## SECTION 2 - OTHER REQUIRED PARTS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS.)	WEIGHT (LBS.)
3	-	-	84" LONG, P2.5 SCH. 40 PIPE	GALVANIZED	41	123
-	-	-	1/2" DIA. J429 GR-2 U-BOLTS	GALVANIZED	-	-

## SECTION 3 - REQUIRED SAFETY CLIMB PARTS

QUANTITY	MANUFACTURER	PART NUMBER	DESCRIPTION	NOTES	UNIT WEIGHT (LBS.)	WEIGHT (LBS.)
1	PERFECT VISION	H42-0501-06	STANDOFF CLAMP BRACKET	OR EOR APPROVED EQUIVALENT	-	-
1	PERFECT VISION	PV-CMX-CG-BO	WIRE ROPE GUIDE	OR EOR APPROVED EQUIVALENT	-	-
<b>TOTAL:</b>						<b>1102</b>

**NOTES:**

- THE MANUFACTURERS LISTED ARE THE APPROVED VENDORS FOR THE VZW MOUNT KITS. EACH MANUFACTURER WILL BE AWARE OF WHICH KITS HAVE BEEN THROUGH THE VZW APPROVAL PROCESS AND THEY ARE IN TURN APPROVED TO SELL. PLEASE NOTE THAT THE MATERIAL UTILIZED ON THE MOUNT MODIFICATIONS WILL BE REVIEWED AS A PART OF THE DESKTOP PMI COMPLETED BY THE SMART TOOL VENDOR. IT WILL BE REQUIRED THAT THE VZW KITS SPECIFIED ARE UTILIZED IN THE MODIFICATIONS.
- ALL MATERIALS REQUIRED FOR THE DESIGNED MODIFICATIONS BUT NOT LISTED IN THIS SHEET ARE ASSUMED TO BE PROVIDED BY THE CONTRACTOR.

### VZWSMART KITS - APPROVED VENDORS

COMMSCOPE	
CONTACT	SALVADOR ANGUIANO
PHONE	(817) 304-7492
EMAIL	SALVADOR.ANGUIANO@COMMSCOPE.COM
WEBSITE	WWW.COMMSCOPE.COM
METROSITE FABRICATORS, LLC	
CONTACT	KENT RAMEY
PHONE	(706) 335-7045 (O), (706) 982-9788 (M)
EMAIL	KENT@METROSITELLC.COM
WEBSITE	METROSITEFABRICATORS.COM

PERFECTVISION	
CONTACT	WIRELESS SALES
PHONE	(844) 887-6723
EMAIL	WWW.PERFECT-VISION.COM
WEBSITE	WIRELESSSALES@PERFECT-VISION.COM
SABRE INDUSTRIES, INC.	
CONTACT	ANGIE WELCH
PHONE	(866) 428-6937
EMAIL	AKWELCH@SABREINDUSTRIES.COM
WEBSITE	WWW.SABRESITESOLUTIONS.COM

SITE PRO 1	
CONTACT	PAULA BOSWELL
PHONE	(972) 236-9843
EMAIL	PAULA.BOSWELL@VALMONT.COM
WEBSITE	WWW.SITEPRO1.COM
NEWAVE	
CONTACT	NEWAVE SALES TEAM
PHONE	(971) 239-4762
EMAIL	SALES@NEWAVETC.COM
WEBSITE	WWW.NEWAVETC.COM

BETTER METAL, LLC	
CONTACT	DAVID STANSBERRY
PHONE	(615) 535-0990 (O), (615) 631-2520 (M)
EMAIL	DLS@BETTERMETAL.COM
WEBSITE	WWW.BETTERMETAL.COM



www.colliersengineering.com

Copyright © 2023, Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were performed or to whom it is certified. This drawing may not be copied, reworked, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.




**811** PROTECT YOURSELF  
 ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE.  
 Know what's below. Call before you dig.  
 FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE: AS SHOWN	JOB NUMBER: 22777017
1 05/05/23 ISSUED FOR CONSTRUCTION	FAC PMA
0 05/13/22 ISSUED FOR CONSTRUCTION	PD DRH
REV DATE DESCRIPTION	DRAWN BY CHECKED BY

COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC-0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
  
**BANKSVILLE CT**  
**5000381784**  
  
 1081 NORTH STREET  
 GREENWICH, CT 06831  
 FAIRFIELD COUNTY



**BILL OF MATERIALS**

SHEET NUMBER: **SBOM-1**

**GENERAL NOTES**

- THESE MODIFICATIONS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE TELECOMMUNICATIONS INDUSTRY STANDARD TIA-222-H. MATERIALS AND SERVICES PROVIDED BY THE CONTRACTOR SHALL CONFORM TO THE ABOVE MENTIONED CODES.
- CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PREVENT DAMAGE TO EXISTING STRUCTURES. ANY DAMAGE TO EXISTING STRUCTURES AS A RESULT OF THE CONTRACTOR'S WORK OR FROM DAMAGE DUE TO OTHER CAUSES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
- CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS BEFORE BEGINNING WORK, ORDERING MATERIAL, AND PREPARING OF SHOP DRAWINGS. ANY DISCREPANCIES BETWEEN FIELD CONDITIONS AND THE CONTRACT DOCUMENTS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ENGINEER. IF THE CONTRACTOR DISCOVERS ANY EXISTING CONDITIONS THAT ARE NOT REPRESENTED ON THESE DRAWINGS, OR ANY CONDITIONS THAT WOULD INTERFERE WITH THE INSTALLATION OF THE MODIFICATIONS, NOTIFY THE ENGINEER IMMEDIATELY.
- IT IS ASSUMED THAT ANY STRUCTURAL MODIFICATION WORK SPECIFIED ON THESE PLANS WILL BE ACCOMPLISHED BY KNOWLEDGEABLE WORKMEN WITH TOWER CONSTRUCTION EXPERIENCE.
- THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION METHODS, MEANS, TECHNIQUES, SEQUENCES, AND PROCEDURES.
- ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN AND SHALL MEET ANSI/TIA-322 (LATEST EDITION), OSHA, AND GENERAL INDUSTRY STANDARDS. ALL RIGGING PLANS SHALL ADHERE TO ANSI/TIA-322 (LATEST EDITION) INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION.
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR INITIATING, MAINTAINING, AND SUPERVISING ALL SAFETY PROGRAMS IN ACCORDANCE WITH APPLICABLE SAFETY CODES.
- WORK SHALL ONLY BE PERFORMED DURING CALM DRY DAYS (WINDS LESS THAN 30-MPH). THE STRUCTURE SHOWN ON THE DRAWINGS IS STRUCTURALLY SOUND ONLY IN THE COMPLETED FORM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE STRENGTH AND STABILITY OF THE STRUCTURE DURING ERECTION. CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORT, SHORING, BRACING AND ANY OTHER STRUCTURAL SYSTEMS AS REQUIRED TO RESIST ALL FORCES THAT MAY OCCUR DURING HANDLING AND ERECTION UNTIL THE STRUCTURE IS FULLY COMPLETED. TEMPORARY SUPPORTS, BRACING AND OTHER STRUCTURAL SYSTEMS REQUIRED DURING CONSTRUCTION SHALL REMAIN THE CONTRACTOR'S PROPERTY AFTER THEIR USE.
- ALL INSTALLATIONS PERFORMED ON THIS STRUCTURE SHALL BE COMPLETED IN ACCORDANCE WITH THE GOVERNING PROVISIONS OF THE STANDARD FOR INSTALLATION, ALTERATION AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS, ANSI/TIA-322.
- CONTRACTOR SHALL SECURE SITE BACK TO EXISTING CONDITION UNDER SUPERVISION OF OWNER. ALL FENCE, STONE, GEOFABRIC, GROUNDING, AND SURROUNDING GRADE SHALL BE REPLACED AND REPAIRED AS REQUIRED TO ACHIEVE OWNER APPROVAL. POSITIVE DRAINAGE AWAY FROM TOWER SITE SHALL BE MAINTAINED.
- CONNECTIONS BETWEEN ITEMS SUPPORTED BY THE STRUCTURE AND THE STRUCTURE NOT SPECIFICALLY DETAILED IN THE CONTRACT DOCUMENTS ARE THE RESPONSIBILITY OF THE CONTRACTOR. SUCH CONNECTIONS SHALL BE DESIGNED, COORDINATED AND INSPECTED BY A PROFESSIONAL STRUCTURAL ENGINEER LICENSED IN THE STATE OF THE PROJECT. SUBMIT SIGNED AND SEALED CALCULATIONS DURING SHOP DRAWING REVIEW.
- DO NOT SCALE DRAWINGS.
- DO NOT USE THESE DRAWINGS FOR ANY OTHER SITE.
- ALL MATERIAL UTILIZED FOR THIS PROJECT MUST BE NEW AND FREE OF ANY DEFECTS. ANY MATERIAL SUBSTITUTIONS, INCLUDING BUT NOT LIMITED TO ALTERED SIZE AND/OR STRENGTHS, MUST BE APPROVED BY THE OWNER AND ENGINEER IN WRITING.
- THE MOUNT UNDER NO CIRCUMSTANCES SHOULD BE USED AS A TIE OFF POINT.


**STRUCTURAL STEEL**

- DESIGN, DETAILING, FABRICATION AND ERECTION OF STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING PUBLICATIONS EXCEPT AS SPECIFICALLY INDICATED IN THE CONTRACT DOCUMENTS.
  - AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) MANUAL OF STEEL CONSTRUCTION (15TH EDITION)
  - SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS
  - AISC CODE OF STANDARD PRACTICE
- STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING UNLESS OTHERWISE SHOWN:
 

CHANNELS, ANGLES, PLATES, ETC.	ASTM A36 (GR 36)
STEEL PIPE	ASTM A53 (GR 35)
BOLTS	ASTM A325
NUTS	ASTM A563
LOCK WASHERS	LOCKING STRUCTURAL GRADE
- ALL SUBSTITUTIONS PROPOSED BY THE CONTRACTOR SHALL BE APPROVED IN WRITING BY THE ENGINEER. CONTRACTOR SHALL PROVIDE DOCUMENTATION TO ENGINEER FOR VERIFYING THE SUBSTITUTE IS SUITABLE FOR USE AND MEETS ORIGINAL DESIGN CRITERIA. DIFFERENCES FROM THE ORIGINAL DESIGN, INCLUDING MAINTENANCE, REPAIR AND REPLACEMENT, SHALL BE NOTED. ESTIMATES OF COSTS/CREDITS ASSOCIATED WITH THE SUBSTITUTION (INCLUDING RE-DESIGN COSTS AND COSTS TO SUB-CONTRACTORS) SHALL BE PROVIDED TO THE ENGINEER. CONTRACTOR SHALL PROVIDE ADDITIONAL DOCUMENTATION AND/OR SPECIFICATIONS TO THE ENGINEER AS REQUESTED.
- PROVIDE STRUCTURAL STEEL SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO FABRICATION.
  - SUBMIT SHOP DRAWINGS TO  
PETER.ALBANO@COLLIERSENG.COM
  - PROVIDE COLLIERS ENGINEERING & DESIGN PROJECT # AND COLLIERS ENGINEERING & DESIGN PROJECT ENGINEER CONTACT IN THE BODY OF THE EMAIL.
- DRILL NO HOLES IN ANY NEW OR EXISTING STRUCTURAL STEEL MEMBERS OTHER THAN THOSE SHOWN ON STRUCTURAL DRAWINGS WITHOUT THE APPROVAL OF THE ENGINEER OF RECORD.
- GALVANIZED ASTM A325 BOLTS SHALL NOT BE REUSED.
- ALL NEW STEEL SHALL BE HOT BE DIPPED GALVANIZED FOR FULL WEATHER PROTECTION. IN ADDITION ALL NEW STEEL SHALL BE PAINTED TO MATCH EXISTING STEEL. CONTRACTOR SHALL OBTAIN WRITTEN PERMISSION TO PROTECT STEEL BY ANY OTHER MEANS.
- ALL BOLT ASSEMBLIES FOR STRUCTURAL MEMBERS REPRESENTED IN THIS DRAWING REQUIRE LOCKING DEVICES TO BE INSTALLED IN ACCORDANCE WITH TIA-222-H SECTION 4.9.2 REQUIREMENTS.
- WHERE CONNECTIONS ARE NOT FULLY DETAILED ON THESE DRAWINGS, FABRICATOR SHALL DESIGN CONNECTIONS TO RESIST LOADS AND FORCES WHERE SHOWN ON DRAWINGS AND AS OUTLINED IN SPECIFICATIONS.
- FOR MEMBERS BEING REPLACED, PROVIDE NEW BOLTS AND MATCH EXISTING SIZE AND GRADE. MAINTAIN AISC REQUIREMENTS FOR MINIMUM BOLT DISTANCE AND SPACING.
- ALL PROPOSED AND/OR REPLACED BOLTS SHALL BE OF SUFFICIENT LENGTH SUCH THAT THE END OF THE BOLT IS AT LEAST FLUSH WITH THE FACE OF THE NUT. IT IS NOT PERMITTED FOR THE BOLT END TO BE BELOW THE FACE OF THE NUT AFTER TIGHTENING IS COMPLETED.
- GALVANIZED ASTM A325 BOLTS SHALL NOT BE REUSED.
- ALL NEW STEEL SHALL BE HOT BE DIPPED GALVANIZED FOR FULL WEATHER PROTECTION. CONTRACTOR SHALL OBTAIN WRITTEN PERMISSION TO PROTECT STEEL BY ANY OTHER MEANS.
- ALL EXISTING PAINTED/GALVANIZED SURFACES DAMAGED DURING REHAB INCLUDING AREAS UNDER STIFFENER PLATES SHALL BE WIRE BRUSHED CLEAN, REPAIRED BY COLD GALVANIZING (ZINC COTE, OR EOR APPROVED EQUAL), AND REPAINTED TO MATCH THE EXISTING FINISH (IF APPLICABLE).
- ALL HOLES IN STEEL MEMBERS SHALL BE SIZED 1/16" LARGER THAN THE BOLT DIAMETER. STANDARD HOLES SHALL BE USED UNLESS NOTED OTHERWISE.

BOLT SCHEDULE (IN.)				
BOLT DIAMETER	STANDARD HOLE	SHORT SLOT	MIN. EDGE DISTANCE	SPACING
1/2	9/16	9/16 x 11/16	7/8	1 1/2
5/8	11/16	11/16 x 7/8	1 1/8	1 7/8
3/4	13/16	13/16 x 1	1 1/4	2 1/4
7/8	15/16	15/16 x 1 1/8	1 1/2	2 5/8
1	1 1/16	1 1/16 x 1 5/16	1 3/4	3


WORKABLE GAGES (IN.)	
LEG	GAGE
4	2 1/2
3 1/2	2
3	1 3/4
2 1/2	1 3/8
2	1 1/8



**TYP. BOLT ASSEMBLY**

**NOTES:**

- ALL DIMENSIONS REPRESENTED IN THE ABOVE TABLES ARE AISC MINIMUM REQUIREMENTS. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS IN FIELD AND NOTIFY ENGINEER IF DISTANCES ARE LESS THAN THOSE PROVIDED.
- THE DIMENSIONS PROVIDED ARE MINIMUM REQUIREMENTS. ACTUAL DIMENSIONS OF PROPOSED MEMBERS WITHIN THESE DRAWINGS MAY VARY FROM THE AISC MINIMUM REQUIREMENTS.
- SHORT SLOT HOLES SHALL ONLY BE USED WHEN DEPICTED IN THE DRAWINGS
- MATCH EXISTING GAGES WHEN APPLICABLE, UNLESS MINIMUM EDGE DISTANCES ARE COMPROMISED.




**811 PROTECT YOURSELF**  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE.  
Know what's below. Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE:	AS SHOWN	JOB NUMBER:	22777017
REV	DATE	DESCRIPTION	DRAWN BY / CHECKED BY
1	05/05/23	ISSUED FOR CONSTRUCTION	FAC / PMA
0	05/13/22	ISSUED FOR CONSTRUCTION	PD / DRH

**SITE NAME:**

**BANKSVILLE CT**  
5000381784  
1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY


**GENERAL NOTES**



**1** CLIMBING FACILITY LOCATION  
SCALE : N.T.S.

**STRUCTURAL NOTES:**


- PER THE MOUNT MAPPING COMPLETED BY ONSIGHT SERVICES, LLC. ON 4/8/2022, THE SAFETY CLIMB AND CLIMBING FACILITIES UP TO THE VERIZON MOUNT ELEVATION (172'-9") ARE IN GOOD CONDITION. COLLIERS ENGINEERING & DESIGN DOES NOT WARRANT THIS INFORMATION.
- INSTALL SHALL NOT CAUSE HARM TO THE STRUCTURE, CLIMBING FACILITY, SAFETY CLIMB, OR ANY SYSTEM INSTALLED ON THE STRUCTURE. TIMELY NOTICE AND DOCUMENTATION SHALL BE PROVIDED BY CONTRACTORS TO THE EOR (OF STRUCTURAL DESIGN) IF AN OBSTRUCTION WAS REQUIRED TO MEET THE RF SYSTEM DESIGN REQUIREMENTS AND PERFORMANCES.



ITEM #	QTY	PART NUMBER	DESCRIPTIONS
A	1	H42-0501-06	STANDOFF CLAMP BRACKET (PERFECT VISION OR EOR APPROVED EQ.)
B	1	PV-CMX-CG-BO	WIRE ROPE GUIDE (PERFECT VISION OR EOR APPROVED EQ.)

**2** PROPOSED WIRE ROPE GUIDE ATTACHMENT - PLAN VIEW  
SCALE : N.T.S.

NOTE: CONTRACTOR SHALL ENSURE THAT WIRE ROPE GUIDE DOES NOT PUSH THE WIRE ROPE OUTSIDE OF THE VERTICAL PLANE OF THE SAFETY CLIMB. CONTRACT EOR WITH PHOTOS OF SAFETY CLIMB AND COLLAR FOR FURTHER DIRECTION IF NEEDED.



CLIMBING FACILITY PHOTO

Copyright © 2023, Colliers Engineering & Design All Rights Reserved. This drawing and all the information contained herein is authorized for use only by the party for whom the services were contracted or to whom it is certified. This drawing may not be copied, reprinted, disclosed, distributed or relied upon for any other purpose without the express written consent of Colliers Engineering & Design.



**811** PROTECT YOURSELF  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE.  
Know what's below. Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE:	AS SHOWN	JOB NUMBER:	22777017
REV	DATE	DESCRIPTION	DRAWN BY / CHECKED BY
1	05/05/23	ISSUED FOR CONSTRUCTION	FAC / PMA
0	05/13/22	ISSUED FOR CONSTRUCTION	PD / DRH

COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC.0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
**BANKSVILLE CT**  
**5000381784**  
1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY

**Colliers** STAMFORD  
1055 Washington Boulevard  
Stamford, CT 06901  
Phone: 203.324.0800  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
DOING BUSINESS AS MASER CONSULTING

SHEET TITLE:  
**CLIMBING FACILITY DETAIL**

SHEET NUMBER:  
**SCF-1**

**LEGEND:**

- PROPOSED
- RELOCATED
- EXISTING

**MOUNT MODIFICATION SCHEDULE**

NO.	ELEVATION	QUANTITY	DESCRIPTION	NOTES
1		1	PROPOSED SUPPORT RAIL KIT (PART #: VZWSMART-PLK1)	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1. RADIO AND/OR TME POSITIONS SHALL BE ADJUSTED VERTICALLY AS NEEDED IN ORDER TO ACHIEVE INSTALLATION OF HORIZONTAL AS SHOWN. CONNECT PROPOSED SUPPORT RAIL PIPE TO MOUNT PIPE AT POSITON 5 (AS SEEN FROM BEHIND THE MOUNT) IN ALPHA SECTOR WITH CROSSOVER PLATE (PART #: VZWSMART-MSK1).
2	172'-9"	1	PROPOSED KICKER KIT (PART #: VZWSMART-PLK5)2	CONTRACTOR TO VERIFY THE LENGTH REQUIRED AND TRIM AS NECESSARY IN ACCORDANCE WITH THE 'STRUCTURAL STEEL' NOTES ON SHEET SGN-1. CONNECT OTHER END OF KICKER KIT TO MONOPOLE COLLAR MOUNT ASSEMBLY (PART #: VZWSMART-PLK7). SEE GENERAL NOTE B.
3		3	84" LONG, P2.5 SCH. 40 PIPE	REMOVE AND REPLACE EXISTING MOUNT PIPE AT POSITON 3 (AS SEEN FROM BEHIND THE MOUNT) IN ALL SECTORS. CONNECT NEW MOUNT PIPE TO EXISTING CHANNEL FACE HORIZONTAL WITH (2) 1/2" DIA. U-BOLTS. CONNECT NEW MOUNT PIPE TO EXISTING INTERMEDIATE AND TOP ANGLE SUPPORT RAILS WITH (1) 1/2" DIA. U-BOLT AT EACH CONNECTION.

**GENERAL NOTES:**

- A. CONTRACTOR SHALL VERIFY THAT NEW & EXISTING STEEL IS FREE OF CORROSION. VISIBLE MINOR CORROSION SHALL BE WIRE BRUSHED CLEAN AND TREATED WITH COLD GALVANIZATION. REPORT ANY SIGNIFICANT CORROSION TO EOR
- B. THREADED ROD FROM PROPOSED KITS SHALL BE TRIMMED TO EXTEND NO MORE THAN 3" BEYOND THE LOCK NUT. TREAT ALL CUT ENDS WITH (2) COATS OF COLD GALVANIZATION (ZINC KOTE, OR EOR APPROVED EQUAL).
- C. MOUNT MEMBERS NOT SHOWN FOR CLARITY U.N.O.



**PROTECT YOURSELF**  
ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE

Know what's below. Call before you dig.  
FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE: AS SHOWN JOB NUMBER: 22777017

REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
1	05/05/23	ISSUED FOR CONSTRUCTION	FAC	PMA
0	05/13/22	ISSUED FOR CONSTRUCTION	PD	DRH

COLLIERS ENGINEERING & DESIGN CT, P.C.  
C.T. JPC.0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


**SITE NAME:**

**BANKSVILLE CT**  
5000381784  
1081 NORTH STREET  
GREENWICH, CT 06831  
FAIRFIELD COUNTY

**Colliers** Engineering & Design  
STAMFORD  
1055 Washington Boulevard  
Stamford, CT 06901  
Phone: 203.324.0800  
COLLIERS ENGINEERING & DESIGN CT, P.C.  
DOING BUSINESS AS MASER CONSULTING


SHEET TITLE:  
**MODIFICATION DETAILS**

SHEET NUMBER:  
**SS-1**



**PROPOSED ISOMETRIC VIEW**

SCALE : N.T.S.




**PROPOSED SIDE ELEVATION VIEW (TYP. ALL SECTORS)**

SCALE : N.T.S.




MOUNT PHOTO 1



MOUNT PHOTO 2



MOUNT PHOTO 3



MOUNT PHOTO 4



**811** PROTECT YOURSELF  
 ALL STATES REQUIRE NOTIFICATION OF EXCAVATORS, DESIGNERS, OR ANY PERSON PREPARING TO DISTURB THE EARTH'S SURFACE ANYWHERE IN ANY STATE  
 Know what's below. Call before you dig.  
 FOR STATE SPECIFIC DIRECT PHONE NUMBERS VISIT: WWW.CALL811.COM

SCALE: AS SHOWN JOB NUMBER: 22777017

REV	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
1	05/05/23	ISSUED FOR CONSTRUCTION	FAC	PMA
0	05/13/22	ISSUED FOR CONSTRUCTION	PD	DRH

COLLIERS ENGINEERING & DESIGN CT, P.C.  
 C.T. JPC-0000131

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF THE RESPONSIBLE LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

**SITE NAME:**  
 BANKSVILLE CT  
 5000381784  
 1081 NORTH STREET  
 GREENWICH, CT 06831  
 FAIRFIELD COUNTY


**Colliers** Engineering & Design  
 STAMFORD  
 1055 Washington Boulevard  
 Stamford, CT 06901  
 Phone: 203.324.0800  
 COLLIERS ENGINEERING & DESIGN CT, P.C.  
 DOING BUSINESS AS MASER CONSULTING

SHEET TITLE:  
 MOUNT PHOTOS


SHEET NUMBER:  
 SS-2



FITS 2.375" O.D. AND 2.875" O.D.  
 VERTICAL PIPE.  
 (NOT INCLUDED IN THIS KIT)



FITS 2.375" O.D. AND 2.875" O.D.  
 HORIZONTAL PIPE.  
 (NOT INCLUDED IN THIS KIT)



FOR REFERENCE  
 ONLY

DRAWN BY: H.R. CHECKED BY: HMA

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	H.R.	05/08/20

SHEET TITLE:


VZSMART-MSK1  
 CROSSOVER PLATE

SHEET NUMBER: REV #:

VZSMART-MSK1 0

NOTES:  
 1. HOT-DIPPED GALVANIZED PER ASTM A123.

VZSMART-MSK1 (CROSSOVER PLATE)					
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	1	PL375-857	PL 3/8" X 8 1/2" X 0'-7" A36	MSK1-F1	6
2	4	MS02-625-300-500	RU-BOLT 5/8" X 3" I.W. X 5" I.L. A36 (OR EQUIV.)	RBC-1	5
3	8	FW-625	5/8" HDG USS FLAT WASHER	---	1
4	8	LW-625	5/8" HDG LOCK WASHER	---	0
5	8	NUT-625	5/8" HDG HEX NUT	---	1
GALVANIZED WT					14



VZWSMART-MSK3  
 PIPE TO PIPE CLAMPS

VZWSMART-MSK3 (PIPE TO PIPE CLAMPS)						
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT	
1	8	VCP	PL 1/2" X 2" X 8 5/8" A36 BENT PLATE	MSK3-F1	20	
2	4	---	THREADED ROD 5/8" DIA. X 1'-0" F1554-36 HDG	---	--	
3	16	FW-625	5/8" HDG USS FLAT WASHER	---	1	
4	16	LW-625	5/8" HDG LOCK WASHER	---	0	
5	16	NUT-625	5/8" HDG HEX NUT	---	2	
					GALVANIZED WT	20

NOTES:  
 1. HOT-DIPPED GALVANIZED PER ASTM A123.  
 2. FITS UP TO 4 1/2" O.D. PIPE


FOR REFERENCE  
 ONLY

DRAWN BY: BT      CHECKED BY: HMA/KW



REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	BT	05/08/20

SHEET TITLE:  
 VZWSMART-MSK3  
 PIPE TO PIPE CLAMPS


SHEET NUMBER: VZWSMART-MSK3      REV #: 0



PLAN VIEW



SECTION "A-A"



DETAIL "B"

NOTES:

1. HOT-DIPPED GALVANIZED PER ASTM A123.

VZW SMART-PLK1 (SUPPORT RAIL KIT)					
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	PST2875-12.5	2.5" PST (2.875" O.D. X 0.203" THK.) X 12'-6" A53 GR-B	PLK1-F1	292
2	3	L33375-3	L 3" X 3" X 3/8" X 3'-0" A36	PLK1-F1	66
3	3	CBP-L	CORNER BENT PLATE BRACKET	PLK1-F2	28
4	3	CBP-R	CORNER BENT PLATE BRACKET	PLK1-F2	28
5	60	MS02-625-300-500	RU-BOLT 5/8" X 3" I.W. X 5" I.L. A36 (OR EQUIV.)	RBC-1	82
6	24	---	BOLT 5/8" X 2" A325	---	9
7	12	PL375-857	PL 3/8" X 8 1/2" X 7'-0" A36	PLK1-F3	77
8	144	FW-625	5/8" HDG USS FLAT WASHER	---	12
9	144	LW-625	5/8" HDG LOCK WASHER	---	3
10	144	NUT-625	5/8" HDG HEX NUT	---	17
GALVANIZED WT					504

FOR REFERENCE  
 ONLY

DRAWN BY: H.R. CHECKED BY: HMA

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	H.R.	05/08/20






SHEET TITLE:

VZWSMART-PLK1  
 SUPPORT RAIL KIT

SHEET NUMBER: VZWSMART-PLK1 REV #: 0



NOTE:  
THE LOCATION OF KICKER AND EXISTING ANTENNA MOUNT SHOWN ON THE DRAWING IS FOR REPRESENTATION PURPOSE ONLY. SEE INSTALLATION DRAWINGS FOR ACTUAL INSTALLATION OF DETAILS.



VZSMART-PLK5 (KICKER KIT)					
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	BRKW-XXX	BRACKET WELDMENT A36	PLK5-F3	43.8
2	3	BRKW-XXXX	BRACKET WELDMENT A36	PLK5-F2	35.7
3	6	L331875-8	L 3" X 3" X 3/16" X 8'-0" A36	PLK5-F4	182.9
4	3	PL-KI	PL 5/8" X 6" X 9" A36	PLK5-F1	29.0
5	12	---	THREADED ROD 5/8" DIA. X 1'-0" F1554-36 HDG	---	---
6	6	---	BOLT 5/8" X 2" A325	---	---
7	12	---	BOLT 5/8" X 2 1/2" A325	---	---
8	42	FW-625	5/8" HDG USS FLAT WASHER	---	3
9	42	LW-625	5/8" HDG LOCK WASHER	---	1
10	42	NUT-625	5/8" HDG HEX NUT	---	5
GALVANIZED WT					291

NOTES:  
1. ALL HOLES ARE 11/16" DIA. U.N.O  
2. HOT-DIPPED GALVANIZED PER ASTM A123.  
3. FIT UP TO 6" SQ. TUBING OR 4 1/2" O.D. PIPE

VzW  
SMART Tool<sup>®</sup>  
Vendor

verizon

FOR REFERENCE ONLY

DRAWN BY: MN CHECKED BY: HMA/KW

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	MN	05/08/20

SHEET TITLE:

VZSMART-PLK5  
KICKER KIT

SHEET NUMBER: REV #:

VZSMART-PLK5 0





FOR REFERENCE  
 ONLY

DRAWN BY: BT CHECKED BY: HMA/KW

REV.	DESCRIPTION	BY	DATE
1	FIRST ISSUE	BT	05/11/20

SHEET TITLE:  
 VZSMART-PLK7  
 MONOPOLE COLLAR  
 MOUNT ASSEMBLY

SHEET NUMBER: VZSMART-PLK7  
 REV #: 0



- NOTES:
1. FIT 12" TO 45" DIA MONOPOLE.
  2. HOT-DIPPED GALVANIZED PER ASTM A123.

VZSMART-PLK7 (MONOPOLE COLLAR MOUNT ASSEMBLY)					
ITEM NO.	QTY.	PART NO.	DESCRIPTION	SHEET #	WT
1	3	CM-1245	COLLAR MOUNT ASSEMBLY	PLK7-F1	147
2	6	---	THREADED ROD 5/8" X 4'-0" A193-B7	---	---
3	12	FW-625	5/8" HDG USS FLAT WASHER	---	1
4	12	LW-625	5/8" HDG LOCK WASHER	---	0
5	12	NUT-625	5/8" HDG HEX NUT	---	1
GALVANIZED WT					150







**Observed Safety and Structural Issues During the Mount Mapping**

Issue #	Description of Issue	Photo #
1	Bird nest on Mount; cannot access without nest removal	31
2		
3		
4		
5		
6		
7		
8		

**Mapping Notes**

1. Please report any visible structural or safety issues observed on the antenna mounts (Damaged members, loose connections, tilting mounts, safety climb issues, etc.)
2. If the thickness of the existing pipes or tubing can't be obtained from a general tool (such as Caliper), please use an ultrasonic measurement tool (thickness gauge) to measure the thickness.
3. Please create all required detail sketches of the mounts and insert them into the "Sketches" tab.
4. Please measure and enter the bolt sizes and types under the Members Box in the spreadsheet of the mount type.
5. Take and label the photos of the tower, mounts, connections, antennas and all measurements. Minimum 50 photos are required.
6. Please measure and report the size and length of all existing antenna mounting pipes.
7. Please measure and report the antenna information for all sectors.
8. Don't delete or rearrange any sheet or contents of any sheet from this mapping form.

**Standard Conditions**

1. Obvious safety and structural issues/deficiencies noticed at the time of the mount mapping are to be reported in this mapping. However, this mount mapping is not a condition assessment of the mount.

**SMART Tool**<sup>©</sup>  
**Vendor**

**Antenna Mount Mapping Form (PATENT PENDING)**


FCC #

Tower Owner:	CROWN CASTLE	Mapping Date:	4/8/2022
Site Name:	BANKSVILLE CT	Tower Type:	MONOPOLE
Site Number or ID:	467981	Tower Height (Ft.):	175
Mapping Contractor:	ONSIGHT SERVICES	Mount Elevation (Ft.):	168.5


This antenna mapping form is the property of TES and under **PATENT PENDING**. The formation contained herein is considered confidential in nature and is to be used only for the specific customer it was intended for. Reproduction, transmission, publication, modification or disclosure by any method is prohibited except by express written permission of TES. All means and methods are the responsibility of the contractor and the work shall be compliant with ANSI/ASSE A 10.48, OSHA, FCC, FAA and other safety requirements that may apply. TES is not warranting the usability of the safety climb as it must be assessed prior to each use in compliance with OSHA requirements.

**Please Insert Sketches of the Antenna Mount**

**TOP VIEW**



**FRONT VIEW**



Please Insert Sketches of the Antenna Mount, cont'd


**AZIMUTH**

MOL @ 168.5°  
TOT @ 175° FT

(1) 1-1/8 COAX  
(2) 1-5/8 COAX



**GAMMA**  
260

**ALPHA**  
ANTENNA: 0  
MOUNT: 20



**BETA**  
140





Colliers Engineering & De...

Project No. 10201832

5000381784-VZW\_MT\_LO\_H

SK - 1

May 5, 2023 at 11:14 AM

5000381784-VZW\_MT\_LO\_H.r3d


**I. Mount-to-Tower Connection Check**

Custom Orientation Required  No

Tower Connection Bolt Checks  Yes


Bolt Orientation  Parallel

Bolt Quantity per Reaction:	4
$d_x$ (in) (Delta X of typ. bolt config. sketch):	6
$d_y$ (in) (Delta Y of typ. bolt config. sketch):	6
Bolt Type:	A325N
Bolt Diameter (in):	0.625
Required Tensile Strength / bolt (kips):	3.1
Required Shear Strength / bolt (kips):	1.6
Tensile Capacity / bolt (kips):	20.7
Shear Capacity / bolt (kips):	12.4
Bolt Overall Utilization:	<b>14.8%</b>



Tower Connection Baseplate Checks  Yes


Connecting Standoff Member Shape:	Rect Tube
Weld Stiffener Configuration:	No Stiffeners
Plate Width, $D_x$ (in):	8
Plate Height, $D_y$ (in):	8
$W_1$ (in):	4
$W_2$ (in):	4
Member Thickness (in):	0.25
Stiffener location $a_1$ (in):	
Stiffener location $b_1$ (in):	
Stiffener location $a_2$ (in):	
Stiffener location $b_2$ (in):	
$F_y$ (ksi, plate):	36
Plate Thickness (in):	0.75
Length of Yield Line, $L_y$ (in):	5.85
Bolt Eccentricity, $e$ (in):	1.65
$M_u$ (kip-in):	5.04
$\Phi * M_n$ (kip-in):	26.65
Plate Bending Utilization:	<b>18.9%</b>



Tower Connection Weld Checks

Weld Shape:  
Weld Stiffener Configuration:  
Stiffener Notch Length, n (in):  
Weld Size (1/16 in):  
W1 (in):  
W2 (in):  
Weld Total Length (in):  
 $Z_x$  (in<sup>3</sup>/in):  
 $Z_y$  (in<sup>3</sup>/in):  
 $J_p$  (in<sup>4</sup>/in):  
 $c_x$  (in)  
 $c_y$  (in)  
Required combined strength (kip/in):  
Weld Capacity (kip/in):  
Weld Utilization:

Yes
Rectangle
None
4
4
4
16.00
21.33
21.33
85.33
2.25
2.25
1.35
5.57
<b>24.2%</b>



# Exhibit F

## **Power Density/RF Emissions Report**



FOX HILL TELECOM

## Radio Frequency Emissions Analysis Report

Prepared for:



Crown Site ID: 807132\_BRG 133 943050  
Verizon Wireless Site Name: Banksville CT  
Verizon Wireless FUZE ID: 16092558

**Site Address:**

1081 North Street  
Greenwich, CT 06831

**May 11, 2023**

**Fox Hill Telecom Project Number: 230522**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>20.99 %</b>



May 11, 2023

Crown Castle  
1800 W. Park Drive  
Westborough, MA 01581

Emissions Analysis for:

Crown Castle Site: **807132 – BRG 133 943050**

**Verizon Wireless Site: Banksville CT**

Fox Hill Telecom, Inc (“Fox Hill”) was directed to analyze the proposed upgrades for Verizon Wireless to the Crown Castle facility located at **1081 North Street, Greenwich, CT**, for the purpose of determining whether the emissions from the Proposed Verizon Wireless Antenna Installation, in addition to all existing radio systems located on this property, are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.



General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 700 MHz frequency band & the 850 MHz cellular frequency band are approximately  $497 \mu\text{W}/\text{cm}^2$  and  $586 \mu\text{W}/\text{cm}^2$  respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS), and 3700 MHz CBRS frequency bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report the percentage of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.



## CALCULATIONS

Calculations were performed for the proposed upgrades to the Crown Castle facility for Verizon Wireless located at **1081 North Street, Greenwich, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65 for far field modeling calculations.

In OET-65, plane wave power densities in the far field of an antenna are calculated by considering antenna gain and reflective waves that would contribute to exposure.

Since the radiation pattern of an antenna has developed in the **far field** region the power gain in specific directions needs to be considered in exposure predictions to yield an Effective Radiated Power (ERP) in each specific direction from the antenna. Also, since the vertical radiation pattern of the antenna is considered, the exposure calculations would most likely be reduced significantly at ground level, resulting in a more realistic estimate of the actual exposure levels. To determine a worst-case scenario at each point along the calculation radials, each point was calculated using the antenna gain value at each angle of incident and compared against the result using an isotropic radiator at the antenna height with the greater of the two used to yield the more pessimistic far field value for each point along the calculation radial.

Additionally, to model a truly "worst case" prediction of exposure levels at or near a surface, such as at ground-level or on a rooftop, reflection off the surface of antenna radiation power can be assumed, resulting in a potential 1.6 times increase in power density in calculating far field power density values.

With these factors considered, the worst case **far field prediction model** utilized in this analysis is determined by the following equation:

Equation 9 per FCC OET65 for Far Field Modeling

$$S = \frac{33.4 \text{ ERP}}{R^2}$$

S = Power Density (in  $\mu\text{w}/\text{cm}^2$ )

ERP = Effective Radiated Power from antenna (watts)

R = Distance from the antenna (meters)

Predicted far field power density values for all carriers identified in this report were calculated 6 feet above the ground level and are displayed as a percentage of the applicable FCC standards. All emissions values for other carriers were calculated using the same Far Field model outlined above, using industry standard radio configurations and frequency band selection based upon available licenses in this geographic area for emissions contribution estimates.





For each Verizon Wireless sector, the following channel counts, frequency bands and power levels were utilized as shown in *Table 1*:

Technology	Frequency Band	Channel Count	Transmit Power per Channel (W)
LTE	700 MHz	4	40
LTE / 5G	850 MHz	4	40
LTE	1900 MHz (PCS)	4	40
LTE	2100 MHz (AWS)	4	40
5G	3700 MHz (C Band)	8	20

*Table 1: Channel Data Table*



# FOX HILL TELECOM

The following **Verizon Wireless** antennas listed in *Table 2 – Antenna Data* were used in the modeling for transmission in the 700 MHz, 850 MHz, 1900 MHz (PCS), 2100 MHz (AWS), 3500 MHz (CBRS) and 3700 MHz (C Band) frequency bands. This is based on feedback from Verizon Wireless regarding anticipated antenna selection. Maximum gain values for all antennas are listed in *Table 3 – Verizon Wireless Inventory and Power Data* below.

Sector	Antenna Number	Antenna Make / Model	Antenna Centerline (ft)
A	1	JMA MX06FRO860-03	176
A	2	JMA MX06FRO860-03	176
A	3	Samsung MT6407-77A	176
B	1	JMA MX06FRO860-03	176
B	2	JMA MX06FRO860-03	176
B	3	Samsung MT6407-77A	176
C	1	JMA MX06FRO860-03	176
C	2	JMA MX06FRO860-03	176
C	3	Samsung MT6407-77A	176

*Table 2: Antenna Data*

All calculations were done with respect to uncontrolled / general population threshold limits.



## RESULTS

Per the calculations completed for the proposed Verizon Wireless configurations *Table 3* shows resulting emissions power levels and percentages of the FCC’s allowable general population limit.

Antenna ID	Antenna Make / Model	Frequency Bands	Antenna Gain (dBd)	Channel Count	Total TX Power (W)	ERP (W)	MPE %
Antenna A1	JMA MX06FRO860-03	700 MHz / 850 MHz / 1900 MHz (PCS) / 2100 MHz (AWS)	13.15 / 12.25 / 15.75 / 16.05	8	320	9,223.78	1.37
Antenna A2	JMA MX06FRO860-03	700 MHz / 850 MHz / 1900 MHz (PCS) / 2100 MHz (AWS)	13.15 / 12.25 / 15.75 / 16.05	8	320	9,223.78	1.37
Antenna A3	Samsung MT6407-77A	3700 MHz (C Band)	23.15	8	132	27,263.02	4.48
Sector A Composite MPE%							<b>7.22</b>
Antenna B1	JMA MX06FRO860-03	700 MHz / 850 MHz / 1900 MHz (PCS) / 2100 MHz (AWS)	13.15 / 12.25 / 15.75 / 16.05	8	320	9,223.78	1.37
Antenna B2	JMA MX06FRO860-03	700 MHz / 850 MHz / 1900 MHz (PCS) / 2100 MHz (AWS)	13.15 / 12.25 / 15.75 / 16.05	8	320	9,223.78	1.37
Antenna B3	Samsung MT6407-77A	3700 MHz (C Band)	23.15	8	132	27,263.02	4.48
Sector B Composite MPE%							<b>7.22</b>
Antenna C1	JMA MX06FRO860-03	700 MHz / 850 MHz / 1900 MHz (PCS) / 2100 MHz (AWS)	13.15 / 12.25 / 15.75 / 16.05	8	320	9,223.78	1.37
Antenna C2	JMA MX06FRO860-03	700 MHz / 850 MHz / 1900 MHz (PCS) / 2100 MHz (AWS)	13.15 / 12.25 / 15.75 / 16.05	8	320	9,223.78	1.37
Antenna C3	Samsung MT6407-77A	3700 MHz (C Band)	23.15	8	132	27,263.02	4.48
Sector C Composite MPE%							<b>7.22</b>

*Table 3: Verizon Wireless Inventory and Power Data table*



*Table 4: All Carrier MPE Contributions* shows all additional identified carriers on site and their emissions contribution estimates, along with the newly calculated maximum Verizon Wireless far field emissions contributions per this report. FCC OET 65 specifies that for carriers utilizing directional antennas the highest recorded sector value be used for composite site emissions values due to their greatly reduced emissions contributions in the directions of the adjacent sectors. For this site, all three Verizon Wireless sectors have the same configuration yielding the same results for all three sectors. *Table 5* below shows a summary for each Verizon Wireless Sector as well as the composite estimated emissions value for the site.

<b>Site Composite MPE%</b>	
<b>Carrier</b>	<b>MPE%</b>
Verizon Wireless – Max Per Sector Value	<b>7.22 %</b>
AT&T	6.52 %
Dish Wireless	1.55 %
T-Mobile	5.70 %
<b>Site Total MPE %:</b>	<b>20.99 %</b>

*Table 4: All Carrier MPE Contributions*

Verizon Wireless Sector A Total:	7.22 %
Verizon Wireless Sector B Total:	7.22 %
Verizon Wireless Sector C Total:	7.22 %
Site Total:	20.99 %

*Table 5: Site MPE Summary*



Table 6 below details a breakdown by frequency band and technology for the MPE power values for the maximum calculated Verizon sector(s). For this site, all three Verizon Wireless sectors have the same configuration yielding the same results for all three sectors.

Verizon Wireless _ Frequency Band / Technology Max Power Values (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Verizon Wireless 700 MHz LTE	4	826.15	176	5.07	700 MHz	497	1.02%
Verizon Wireless 850 MHz LTE / 5G	4	671.52	176	5.51	850 MHz	586	0.94%
Verizon Wireless 1900 MHz (PCS) LTE	4	1,503.35	176	3.60	1900 MHz (PCS)	1000	0.36%
Verizon Wireless 2100 MHz (AWS) LTE	4	1,610.87	176	4.20	2100 MHz (AWS)	1000	0.42%
Verizon Wireless 3700 MHz (C Band) 5G	8	16.50	176	44.80	3700 MHz (C Band)	1000	4.48%
						<b>Total:</b>	<b>7.22 %</b>

Table 6: Verizon Wireless Maximum Sector MPE Power Values



## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Verizon Wireless facility as well as the site composite emissions estimates value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Verizon Wireless Sector	Power Density Value (%)
Sector A:	7.22 %
Sector B:	7.22 %
Sector C:	7.22 %
Verizon Wireless Maximum Total (per sector):	7.22 %
Site Total:	20.99 %
Site Compliance Status:	<b>COMPLIANT</b>


The estimated composite emissions value for this site, assuming all carriers present, is **20.99 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon the far field calculations performed for all carriers identified in this report.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite estimated values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan  
Principal RF Engineer  
**Fox Hill Telecom, Inc**  
Worcester, MA 01609  
(978)660-3998


# Exhibit G

## Recipient Mailings



FRED CAMILLO  
FIRST SELECTMAN-GREENWICH  
101 FIELD POINT RD  
GREENWICH CT 06830-6463

**USPS TRACKING #**




**9405 5036 9930 0544 6331 76**

DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
STE 1  
420 MAIN ST  
STURBRIDGE MA 01566-1359

**PRIORITY MAIL®**

Expected Delivery Date: 05/17/23  
Ref#: CR-807132  
**0000**

**C027**



**Click-N-Ship®**


**U.S. POSTAGE PAID**

Click-N-Ship®

**P**

usps.com 9405 5036 9930 0544 6331 76 0058 5000 0020 6830  
US POSTAGE \$9.65  
Flat Rate Env  
05/15/2023 Mailed from 01566 986757267611207

Electronic Rate Approved #038555749





Cut on dotted line.

## Instructions

- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0544 6331 76**

Trans. #:	588416159	Priority Mail® Postage:	<b>\$9.65</b>
Print Date:	05/15/2023	Total:	<b>\$9.65</b>
Ship Date:	05/15/2023		
Expected			
Delivery Date:	05/17/2023		

**From:** DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
STE 1  
420 MAIN ST  
STURBRIDGE MA 01566-1359

Ref#: CR-807132


**To:** FRED CAMILLO  
FIRST SELECTMAN-GREENWICH  
101 FIELD POINT RD  
GREENWICH CT 06830-6463

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.




Thank you for shipping with the United States Postal Service!  
Check the status of your shipment on the USPS Tracking® page at usps.com





PATRICK LAROW  
AICP, DIRECTOR OF PLANNING  
101 FIELD POINT RD  
GREENWICH CT 06830-6463

**USPS TRACKING #**



**9405 5036 9930 0544 6332 06**

DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
STE 1  
420 MAIN ST  
STURBRIDGE MA 01566-1359

**PRIORITY MAIL®**


Expected Delivery Date: 05/17/23  
Ref#: CR-807132  
**0000**

**C027**

**P**


usps.com 9405 5036 9930 0544 6332 06 0058 5000 0020 6830  
**\$9.65**  
**US POSTAGE**  
 Flat Rate Envoy

U.S. POSTAGE PAID  
Click-N-Ship®



05/15/2023 Mailed from 01566 986757267609801

Electronic Rate Approved #038555749



**Click-N-Ship®**

**UNITED STATES POSTAL SERVICE®**



Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

### Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0544 6332 06**

Trans. #: 588416159	Priority Mail® Postage: <b>\$9.65</b>
Print Date: 05/15/2023	Total: <b>\$9.65</b>
Ship Date: 05/15/2023	
Expected Delivery Date: 05/17/2023	


**From:** DEBORAH CHASE      Ref#: CR-807132  
 NORTHEAST SITE SOLUTIONS  
 STE 1  
 420 MAIN ST  
 STURBRIDGE MA 01566-1359

**To:** PATRICK LAROW  
 AICP, DIRECTOR OF PLANNING  
 101 FIELD POINT RD  
 GREENWICH CT 06830-6463

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.




Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com



CROWN CASTLE  
1800 W PARK DR  
WESTBOROUGH MA 01581-3926

**USPS TRACKING #**



**9405 5036 9930 0544 6332 20**

**P**

usps.com 9405 5036 9930 0544 6332 20 0058 5000 0010 1581  
**\$9.65**  
**US POSTAGE**  
 Flat Rate Envoy

U.S. POSTAGE PAID  
Click-N-Ship®

Mailed from 01566 986757267609533


DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
STE 1  
420 MAIN ST  
STURBRIDGE MA 01566-1359

**PRIORITY MAIL®**

Expected Delivery Date: 05/16/23  
Ref#: CR-807132  
**0000**

**C006**

Electronic Rate Approved #038555749





Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. **DO NOT PHOTO COPY OR ALTER LABEL.**
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, **DO NOT TAPE OVER BARCODE.** Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

### Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0544 6332 20**

Trans. #: 588416159	Priority Mail® Postage: <b>\$9.65</b>
Print Date: 05/15/2023	Total: <b>\$9.65</b>
Ship Date: 05/15/2023	
Expected Delivery Date: 05/16/2023	

**From:** DEBORAH CHASE      Ref#: CR-807132  
 NORTHEAST SITE SOLUTIONS  
 STE 1  
 420 MAIN ST  
 STURBRIDGE MA 01566-1359

**To:** CROWN CASTLE  
 1800 W PARK DR  
 WESTBOROUGH MA 01581-3926

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com