



Crown Castle  
3 Corporate Park Drive, Suite 101  
Clifton Park, NY 12065

June 7, 2022

Melanie A. Bachman  
Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

RE: **Notice of Exempt Modification for ATT  
Crown #806361; ATT Site ID CT2030  
131 Manor Road, Guilford, CT 06437  
Latitude: 41.330025/ Longitude: -72.721808**

Dear Ms. Bachman:

AT&T currently maintains twelve (12) antennas at the 137-foot level of the existing 150-foot monopole tower at 131 Manor Road, Guilford, CT. The tower is owned by Crown Castle USA Inc. and the property is owned by BW Bishop & Sons, Inc. AT&T now intends to replace six (6) antennas, relocate three (3) existing antennas, install six (6) new antennas and ancillary equipment at the 137-foot level. This modification may include B2, B5, B17, B14, B29, B30, B66 & n77 hardware that is 4G(LTE) and/or 5G NR capable through remote software configuration and either or both services may be turned on or off at various times.

**Panned Modification:**

**Tower:**

Installed New:

- (6) Ericsson-AIR6449 B77D + AIR6419 B77G Stacked Antennas
- (1) Raycap DC9-48-60-24-8C-EV Squid
- (3) 7/8" 6AWG DC Cables
- (1) 3/8" 24-pair Fiber Cable
- (3) Dual Radio Mounts
- (3) 2" Galvanized Pipes
- (3) Valmont-BBPM-K1 Crossover Hardware

Remove:

- (3) POWERWAVE-7770 Antennas
- (3) CCI-HPA-65R-BUU-H6 Antennas
- (6) POWERWAVE-LGP21901 Diplexers
- (6) POWERWAVE-LGP21404 TMAs

**Ground:**

Install New:

- (3) Vertiv Rectifiers in Vertiv Netsure 7100 DC Power Plant
- (1) GEN 2 DC 12
- (1) 6648 With XCEDE Cable

The Foundation for a Wireless World.

CrownCastle.com

Melanie A. Bachman

Page 2

This facility was approved by the CT Siting Council – Docket No.56 – Dated April 14, 1986. Please see attached.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to First Selectman Matthew T. Hoey, III, Town Planner Jaime Stein, and property owner BW Bishop & Sons, Inc.

The proposed modifications will not result in an increase in the height of the existing tower.

1. The proposed modifications will not require the extension of the site boundary.
2. The proposed modification will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
3. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communication Commission safety standard.
4. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
5. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, ATT respectfully submits that the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Domenica Tatasciore.

Sincerely,



Domenica Tatasciore  
Site Acquisition Specialist  
1800 W. Park Drive  
Westborough, MA 01581  
(508) 621-9161/ Domenica.Tatasciore@crowncastle.com

#### Attachments

cc:

Matthew T. Hoey, III, First Selectman  
Town of Guilford  
31 Park Street, Guilford CT 06437

Jaime Stein, Town Planner  
Town of Guilford  
31 Park Street, Guilford CT 06437

BW Bishop & Sons, Inc., Property Owner  
1355 Boston Post Road,  
Guilford CT 06437

Crown Castle, Tower Owner

(https://www.fedex.com/en-us/home.html)



FedEx® Tracking



777061823391



[ADD NICKNAME](#)

**Delivered**  
Wednesday, 6/8/2022 at 10:11 am



**DELIVERED**

Signed for by: K.QUERCIA



[GET STATUS UPDATES](#)

[OBTAIN PROOF OF DELIVERY](#)

**FROM**

Jeff Barbadora

1800 W. Park Drive  
WESTBOROUGH, MA US 01581  
781-970-0053

**TO**

Matthew T Hoey III, First Selectman  
Town of Guilford

31 Park Street  
GUILFORD, CT US 06437  
203-453-8015

[MANAGE DELIVERY](#)

Travel History

**TIME ZONE**

Local Scan Time



Wednesday, June 8,  
2022



10:11 AM	GUILFORD, CT	Delivered
8:56 AM	NORTH HAVEN, CT	On FedEx vehicle for delivery
8:07 AM	NORTH HAVEN, CT	At local FedEx facility
4:34 AM	NEWARK, NJ	Departed FedEx hub

(<https://www.fedex.com/en-us/home.html>)

11:58 PM	NEWARK, NJ	Arrived at FedEx hub
8:31 PM	FRAMINGHAM, MA	Left FedEx origin facility
5:57 PM	FRAMINGHAM, MA	Shipment arriving On-Time
5:41 PM	FRAMINGHAM, MA	Picked up
12:44 PM		Shipment information sent to FedEx

Expand History 

## Shipment Facts

<b>TRACKING NUMBER</b> 777061823391	<b>SERVICE</b> FedEx Priority Overnight	<b>WEIGHT</b> 0.5 lbs / 0.23 kgs
<b>DELIVERY ATTEMPTS</b> 1	<b>DELIVERED TO</b> Receptionist/Front Desk	<b>TOTAL PIECES</b> 1
<b>TOTAL SHIPMENT WEIGHT</b> 0.5 lbs / 0.23 kgs	<b>TERMS</b> Shipper	<b>SHIPPER REFERENCE</b> 799001.7680
<b>PACKAGING</b> FedEx Envelope	<b>SPECIAL HANDLING SECTION</b> Deliver Weekday	<b>SHIP DATE</b> 6/7/22 
<b>STANDARD TRANSIT</b> 6/8/22 before 10:30 am 	<b>ACTUAL DELIVERY</b> 6/8/22 at 10:11 am	

### OUR COMPANY

About FedEx(<https://www.fedex.com/en-us/about.html>)

Our Portfolio(<https://www.fedex.com/en-us/about/company-structure.html>)

Investor Relations(<https://investors.fedex.com/investor-home/default.aspx>)

Careers(<https://careers.fedex.com/fedex/>)

FedEx Blog(<https://www.fedex.com/en-us/blog.html>)

Corporate Responsibility(<https://www.fedex.com/en-us/about/corporate-social-responsibility.html>)

Newsroom(<https://newsroom.fedex.com/>)

Contact Us(<https://www.fedex.com/en-us/customer-support/contact-us.html>)

### MORE FROM FEDEX

FedEx Compatible(<https://www.fedex.com/en-us/compatible.html>)

FedEx Developer Portal(<https://developer.fedex.com/>)

FedEx Logistics(<https://www.fedex.com/en-us/logistics.html>)

FedEx Cross Border(<https://www.fedex.com/en-us/cross-border.html>)

ShopRunner(<https://www.fedex.com/en-us/shoprunner.html>)

### LANGUAGE

(https://www.fedex.com/en-us/home.html)



FedEx® Tracking



777061852674




[ADD NICKNAME](#)

**Delivered**  
Wednesday, 6/8/2022 at 10:08 am



**DELIVERED**

Signed for by: P.PIOMBINO



[GET STATUS UPDATES](#)

[OBTAIN PROOF OF DELIVERY](#)

**FROM**

Jeff Barbadora

1800 W. Park Drive  
WESTBOROUGH, MA US 01581  
781-970-0053

**TO**

Jaime Stein, Town Planner  
Town of Guilford

31 Park Street  
GUILFORD, CT US 06437  
203-453-8034

[MANAGE DELIVERY](#)

Travel History

**TIME ZONE**

Local Scan Time



Wednesday, June 8, 2022



10:08 AM	GUILFORD, CT	Delivered
8:55 AM	NORTH HAVEN, CT	On FedEx vehicle for delivery
8:16 AM	NORTH HAVEN, CT	At local FedEx facility
4:34 AM	NEWARK, NJ	Departed FedEx hub

(<https://www.fedex.com/en-us/home.html>)

11:58 PM	NEWARK, NJ	Arrived at FedEx hub
8:31 PM	FRAMINGHAM, MA	Left FedEx origin facility
5:57 PM	FRAMINGHAM, MA	Shipment arriving On-Time
5:41 PM	FRAMINGHAM, MA	Picked up
12:45 PM		Shipment information sent to FedEx

Expand History 

## Shipment Facts

<b>TRACKING NUMBER</b> 777061852674	<b>SERVICE</b> FedEx Priority Overnight	<b>WEIGHT</b> 0.5 lbs / 0.23 kgs
<b>DELIVERY ATTEMPTS</b> 1	<b>DELIVERED TO</b> Receptionist/Front Desk	<b>TOTAL PIECES</b> 1
<b>TOTAL SHIPMENT WEIGHT</b> 0.5 lbs / 0.23 kgs	<b>TERMS</b> Shipper	<b>SHIPPER REFERENCE</b> 799001.7680
<b>PACKAGING</b> FedEx Envelope	<b>SPECIAL HANDLING SECTION</b> Deliver Weekday	<b>SHIP DATE</b> 6/7/22 
<b>STANDARD TRANSIT</b> 6/8/22 before 10:30 am 	<b>ACTUAL DELIVERY</b> 6/8/22 at 10:08 am	

### OUR COMPANY

About FedEx(<https://www.fedex.com/en-us/about.html>)

Our Portfolio(<https://www.fedex.com/en-us/about/company-structure.html>)

Investor Relations(<https://investors.fedex.com/investor-home/default.aspx>)

Careers(<https://careers.fedex.com/fedex/>)

FedEx Blog(<https://www.fedex.com/en-us/blog.html>)

Corporate Responsibility(<https://www.fedex.com/en-us/about/corporate-social-responsibility.html>)

Newsroom(<https://newsroom.fedex.com/>)

Contact Us(<https://www.fedex.com/en-us/customer-support/contact-us.html>)

### MORE FROM FEDEX

FedEx Compatible(<https://www.fedex.com/en-us/compatible.html>)

FedEx Developer Portal(<https://developer.fedex.com/>)

FedEx Logistics(<https://www.fedex.com/en-us/logistics.html>)

FedEx Cross Border(<https://www.fedex.com/en-us/cross-border.html>)

ShopRunner(<https://www.fedex.com/en-us/shoprunner.html>)

### LANGUAGE

(https://www.fedex.com/en-us/home.html)



FedEx® Tracking



777061904219



[ADD NICKNAME](#)

**Delivered**  
Wednesday, 6/8/2022 at 9:45 am



**DELIVERED**

Signature release on file

[GET STATUS UPDATES](#)

[OBTAIN PROOF OF DELIVERY](#)

**FROM**

Jeff Barbadora

1800 W. Park Drive  
WESTBOROUGH, MA US 01581  
781-970-0053

**TO**

Property Owner  
BW Bishop & Sons, Inc

1355 Boston Post Road  
GUILFORD, CT US 06437  
508-621-9161

[MANAGE DELIVERY](#)

Travel History

**TIME ZONE**

Local Scan Time



Wednesday, June 8,  
2022

9:45 AM	GUILFORD, CT	Delivered Package delivered to recipient address - release authorized
8:56 AM	NORTH HAVEN, CT	On FedEx vehicle for delivery
8:06 AM	NORTH HAVEN, CT	At local FedEx facility
4:34 AM	NEWARK, NJ	Departed FedEx hub



Tuesday, June 7,  
2022

(<https://www.fedex.com/en-us/home.html>)

5:57 PM	FRAMINGHAM, MA	Shipment arriving On-Time
5:41 PM	FRAMINGHAM, MA	Picked up
12:48 PM		Shipment information sent to FedEx

Expand History 

## Shipment Facts

<b>TRACKING NUMBER</b> 777061904219	<b>SERVICE</b> FedEx Priority Overnight	<b>WEIGHT</b> 1 lbs / 0.45 kgs
<b>DELIVERY ATTEMPTS</b> 1	<b>TOTAL PIECES</b> 1	<b>TOTAL SHIPMENT WEIGHT</b> 1 lbs / 0.45 kgs
<b>TERMS</b> Shipper	<b>SHIPPER REFERENCE</b> 799001.7680	<b>PACKAGING</b> FedEx Envelope
<b>SPECIAL HANDLING SECTION</b> Deliver Weekday	<b>SHIP DATE</b> 6/7/22 	<b>STANDARD TRANSIT</b> 6/8/22 before 10:30 am 
<b>ACTUAL DELIVERY</b> 6/8/22 at 9:45 am		

## OUR COMPANY

About FedEx(<https://www.fedex.com/en-us/about.html>)

Our Portfolio(<https://www.fedex.com/en-us/about/company-structure.html>)

Investor Relations(<https://investors.fedex.com/investor-home/default.aspx>)

Careers(<https://careers.fedex.com/fedex/>)

FedEx Blog(<https://www.fedex.com/en-us/blog.html>)

Corporate Responsibility(<https://www.fedex.com/en-us/about/corporate-social-responsibility.html>)

Newsroom(<https://newsroom.fedex.com/>)

Contact Us(<https://www.fedex.com/en-us/customer-support/contact-us.html>)

## MORE FROM FEDEX

FedEx Compatible(<https://www.fedex.com/en-us/compatible.html>)

FedEx Developer Portal(<https://developer.fedex.com/>)

FedEx Logistics(<https://www.fedex.com/en-us/logistics.html>)

FedEx Cross Border(<https://www.fedex.com/en-us/cross-border.html>)

ShopRunner(<https://www.fedex.com/en-us/shoprunner.html>)

## LANGUAGE



Change Country/Territory(<https://www.fedex.com/?location=home>)



DOCKET NO. 56

AN APPLICATION OF METRO MOBILE CTS OF NEW HAVEN, INC., FOR A CERTIFICATE OF ENVIRONMENTAL COMPATIBILITY AND PUBLIC NEED FOR THE CONSTRUCTION, MAINTENANCE, AND OPERATION OF FACILITIES TO PROVIDE CELLULAR SERVICE IN NEW HAVEN COUNTY. : CONNECTICUT SITING  
: COUNCIL  
: April 14, 1986

D E C I S I O N A N D O R D E R

Pursuant to the foregoing opinion, the Council hereby directs that a certificate of environmental compatibility and public need as required by section 16-50k of the General Statutes of Connecticut (CGS) be issued to Metro Mobile CTS of New Haven, Inc., for the construction, maintenance, and operation of cellular mobile phone telecommunication towers and associated equipment in the towns of Wolcott, Naugatuck, West Haven (existing tower), Milford, Hamden (existing tower), Guilford, and North Branford subject to the conditions below.

1. The proposed and alternate Beacon Falls sites are rejected without prejudice.
2. The Wolcott tower shall be constructed to meet Zone C wind loading with 1" of radial ice and shall not exceed 180' in height excluding antennas.
3. The Naugatuck tower shall not exceed 160' in height, excluding antennas. The certificate holder shall offer to remove the existing privately owned, unused tower now on the site.
4. Any future actions requiring the removal of the existing West Haven or Hamden towers to be shared by the certificate holder shall also apply to the equipment mounted on those towers by the certificate holder, regardless of that equipment's status under Chapter 277a of the CGS.

5. The Milford tower shall be a monopole structure not to exceed 100' in height, excluding antennas.
6. The Guilford tower shall be a monopole structure not to exceed 150' in height, excluding antennas.
7. The North Branford Route 17 site is rejected. The North Branford East Reeds Gap Road tower shall not exceed 160' in height, excluding antennas.
8. The certificate holder shall submit a development and management plan for the Wolcott, Naugatuck, Milford, Hamden, Guilford, and North Branford sites pursuant to sections 16-50j-75 through 16-50j-77 of the RSA, except that irrelevant items in section 16-50j-76 need only be identified as such. In addition to the requirements of section 16-50j-76, the D&M plan shall provide plans for evergreen screening around the fenced perimeter at the Wolcott, Milford, Hamden, Guilford, and North Branford sites. The D&M plan shall include a proposal for painting the approved monopole structures to blend with the sky. Any changes to specifications in the D&M plan must be approved by the Council prior to facility operation.
9. All certified facilities shall be constructed, operated, and maintained as specified in the Council's record and in the site development and management plan required by order 8.
10. The certificate holder shall permit public or private entities to share space on the towers approved herein, for due consideration received, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing. In addition to complying with 16-50j-73, the

certificate holder shall notify the Council of the addition of any equipment to any approved tower.

11. A fence not lower than 8' shall surround each tower and associated equipment.
12. Unless necessary to comply with order 13, below, no lights shall be installed on any of these towers.
13. The facilities' construction and any future tower sharing shall be in accordance with all applicable federal, state, and municipal laws and regulations. Shared uses by entities not subject to jurisdiction pursuant to sections 16-50i and 16-50k of the CGS shall be subject to all applicable federal, state, and municipal laws and regulations.
14. Construction activities shall take place during daylight working hours.
15. This decision and order shall be void and the towers and associated equipment shall be dismantled and removed, or reapplication for any new use shall be made to the CSC before any such new use is made, if the towers do not provide or permanently cease to provide cellular service following completion of construction.
16. This decision and order shall be void if all construction authorized herein is not completed within three years of the issuance of this decision, or within three years of the completion of any appeal if appeal of this decision is taken, unless otherwise approved by the Council.

Pursuant to CGS section 16-50p, we hereby direct that a copy of the decision and order shall be served on each person listed below. A notice

of the issuance shall be published in The Record-Journal, The New Haven Register, The Branford Review, The Evening Sentinel, The Waterbury American, and The Waterbury Republican.

The parties to this proceeding are:

Metro Mobile CTS of New Haven, Inc. (Applicant)  
5 Eversley Avenue  
Norwalk, Connecticut 06855

ATTN: Armand Mascioli  
General Manager

Mr. Kevin B. Sullivan, Esq. (its attorneys)  
Byrne, Slater, Sandler, Shulman & Rouse, P.C.  
111 Pearl Street  
P.O. Box 3216  
Hartford, Connecticut 06103

Mr. Richard Rubin, Esq.  
Fleischman and Walsh, P.C.  
1725 N Street, N.W.  
Washington, D.C. 20036

Guilford Conservation Commission

represented by:

Mr. David B. Damer  
Chairman  
Guilford Conservation Commission  
440 Great Hill Road  
Guilford, Connecticut 06437

Mr. Robert W. Griswold, Jr.  
100 Rimmon Hill Road  
Beacon Falls, Connecticut 06403

Town of Hamden  
Memorial Town Hall  
2372 Whitney Avenue  
Hamden, Connecticut 06518

ATTN: Shirley Gonzales  
Town Planner

Guilford Planning and Zoning Commission

represented by:

Mr. David W. Fisher  
Chairman  
Town Hall  
31 Park Street  
Guilford, Connecticut 06437

Town of Hamden

represented by:

John DeNicola, Jr.  
Mayor  
Town of Hamden  
Memorial Town Hall  
2372 Whitney Avenue  
New Haven, Connecticut 06518

Citizens Park Council of New Haven

represented by:

Mr. John J. Ciarleglio  
President  
Citizens Park Council  
of New Haven  
36 Elmwood Road  
New Haven, Connecticut 06515

Mr. Thomas V. Keating  
343 Rimmon Hill Road  
Beacon Falls, Connecticut 06403

Ms. Evelyn M. Sirowich  
245 Rimmon Hill Road  
Beacon Falls, Connecticut 06403

Mr. Jack B. Levine  
11 White Birch Lane  
Beacon Falls, Connecticut 06403

Southern New England Telephone Company

represented by:

Mr. Peter J. Tyrrell, Esq.  
227 Church Street  
New Haven, Connecticut 06506

Mr. Dennis Bialecki  
96 West Road  
Beacon Falls, Connecticut 06403

Brittany Woods Homeowner's Association

represented by:

Mr. Stephen P. Del Sole, Esq.  
Del Sole & Del Sole  
152 Temple Street  
P.O. Box 405  
New Haven, Connecticut 06502-0405

Ms. Barbara G. Schlein  
Box 2993 Westville Station  
New Haven, Connecticut 06515

Mr. & Mrs. Joseph T. Farrell, Jr.  
334 Rimmon Hill Road  
Beacon Falls, Connecticut 06403

Town of Beacon Falls

represented by:

The Honorable Leonard F. D'Amico  
First Selectman  
10 Maple Avenue  
Beacon Falls, Connecticut 06403

West Rock Ridge Park Association

represented by:

Mr. William L. Doheny Jr., D.D.S.  
President  
220 Mountain Road  
Hamden, Connecticut 06514

Department of Parks,  
Recreation & Trees

represented by:

Mr. Robert G. Sheeley  
Director  
Parks, Recreation & Trees  
P.O. Box 1416  
New Haven, Connecticut 06506

Town of Wallingford

represented by:

William W. Dickinson, Jr.  
Mayor  
Municipal Building  
350 Center Street  
P.O. Box 427  
Wallingford, Connecticut 06492

New Haven Sierra Club

represented by:

Ms. Laurie Klein  
270 Edgewood Avenue  
New Haven, Connecticut 06511

Peter M. Lerner  
State Representative  
8 Merritt Avenue  
Woodbridge, Connecticut 06525

Carleton J. Benson  
State Representative  
161 Scott Road  
Prospect, Connecticut 06712

Dr. Stephen Collins (service waived)  
Vice Chairman  
West Rock State Park  
Advisory Council  
Bethany, Connecticut

Mr. Louis Melillo (service waived)  
985 Wintergreen Avenue  
Hamden, Connecticut

Mr. John McGeever (service waived)  
339 Rimmon Hill  
Beacon Falls, Connecticut 06403

Senator John Consoli (service waived)  
51 Luke Hill Road  
Bethany, Connecticut 06525

Representative George P. Bassing (service waived)  
14 Oakwood Drive  
Seymour, Connecticut 06483

Dr. George D. Whitney (service waived)  
858 Oakwood Road  
Orange, Connecticut

Mr. Steve Molnar (service waived)  
205 West Road  
Beacon Falls, Connecticut

Mr. James W. Grandy (service waived)  
President  
Hamden Land Conservation Trust  
Hamden, Connecticut

Senator Richard S. Eaton (service waived)  
269 Mulberry Point Road  
Guilford, Connecticut 06437

Representative Robert M. Ward  
719 Totoket Road  
Northford, Connecticut 06472

Town of North Branford

represented by:

Regina Smith  
1887 Middletown Avenue  
Northford, Connecticut 06472

John Gesmonde, Esquire  
3127 Whitney Avenue  
Hamden, Connecticut 06518

(service waived)

Richard A. Nizolek  
The Restland Farm Corporation  
Route 17  
Northford, Connecticut 06472

Mary Liska  
83 Reeds Gap Road  
Northford, Connecticut 06472

Ben Bullard  
50 Christmas Hill Road  
Guilford, Connecticut 06437

(service waived)

Roland Robichaud  
31 Berncliff Drive  
North Branford, Connecticut 06471

(service waived)

Irene Flynn  
1926 Middletown Avenue  
Northford, Connecticut 06472

(service waived)

Charles Pope  
199 Donalds Road  
Guilford, Connecticut 06437

Richard Abate  
131 Manor Road  
Guilford, Connecticut 06437

(service waived)

City of Milford

represented by:

Mayor Alberta Jagoe  
Alderman Maurice Condon  
Alderman Frederick Lisman  
City Hall  
River Street  
Milford, Connecticut 06460

Thomas Scelfo  
81 Berncliff Drive  
North Branford, Connecticut 06471

(service waived)



Senator Thomas Scott  
22 Meyers Court  
Milford, Connecticut 06460

(service waived)

Helen Moore  
385 Oronoque Road  
Milford, Connecticut 06460

(service waived)









William Barberi  
298 Oronoque Road  
Milford, Connecticut 06460

(service waived)

C E R T I F I C A T I O N

The undersigned members of the Connecticut Siting Council hereby certify that they have heard this case or read the record thereof, and that we voted as follows:


Dated at New Britain, Connecticut, this 14th day of April, 1986.

<u>Council Members</u>	<u>Vote Cast</u>
 _____ Gloria Dibble Pond Chairperson	Yes
_____ Commissioner John Downey Designee: Commissioner Peter G. Boucher	Absent
 _____ Commissioner Stanley Pad Designee: Christopher Cooper	No
 _____ Owen L. Clark	Yes
 _____ Mortimer A. Gelston	Yes
 _____ James G. Horsfall	Yes
 _____ Pamela B. Katz	Yes
 _____ William H. Smith	No
 _____ Colin C. Tait	No

STATE OF CONNECTICUT            )  
  :  
COUNTY OF HARTFORD            )        ss.        New Britain, April 14, 1986

I hereby certify that the foregoing is a true and correct copy of the decision and order issued by the Connecticut Siting Council, State of Connecticut.

ATTEST:

  
\_\_\_\_\_  
Christopher S. Wood, Executive Director  
Connecticut Siting Council




### Property Information

Owner	CARELTON JEFFREY
Address	131 MANOR RD
Mailing Address	131 MANOR RD GUILFORD , CT 06437
Land Use	- SINGLE FAMILY
Land Class	Residential

Census Tract	1903
Neighborhood	N030
Zoning	R-3
Acreage	0.69
Utilities	
Lot Setting/ Desc	/

### Photo



### PARCEL VALUATIONS (Assessed value = 70% of Appraised Value)

	Appraised	Assessed
Buildings	78929	55250
Outbuildings	0	0
Improvements		
Extras		
Land	144455	101120
Total	223384	156370
Previous		

### Construction Details

Year Built	1980
Stories	1
Building Style	1.0 RANCH
Building Use	Residential
Building Condition	GOOD
Total Rooms	7
Bedrooms	4
Full Bathrooms	2
Half Bathrooms	
Bath Style	
Kitchen Style	
Roof Style	GABLE
Roof Cover	ASPHALT

#### EXTERIOR WALLS:

Primary	VINYL
Secondary	

#### INTERIOR WALLS:

Primary	DRYWALL
Secondary	

#### FLOORS:

Primary	HARDWOOD
Secondary	

#### HEATING/AC:

Heating Type	BASEBOARD
Heating Fuel	ELECTRIC
AC Type	

#### BUILDING AREA:

Effective Building Area	
Gross Building Area	0
Total Living Area	1404


#### SALES HISTORY:

Sale Date	8/21/2014
Sale Price	218900
Book/ Page	0874/0888

# Town of Guilford, Connecticut - Assessment Parcel Map

Unique ID: 6

Address: 131 MANOR RD



Approximate Scale: 1 inch = 100 feet



Map Produced:  
August 2021

**Disclaimer:**  
This map is for informational purposes only.  
All information is subject to verification by any user.  
The Town of Guilford and its mapping contractors  
assume no legal responsibility  
for the information contained herein.

## Radio Frequency Safety Survey Report Predictive (RFSSRP) Prepared For AT&T



<b>Site Name:</b>	GUILFORD CENTRAL
<b>FA#</b>	10035042
<b>USID:</b>	61163
<b>Site ID:</b>	CT2030
<b>Address:</b>	131 MANOR RD GUILFORD, CT 06437
<b>County:</b>	NEW HAVEN
<b>Latitude:</b>	41.3300200
<b>Longitude:</b>	-72.7218050
<b>Structure Type:</b>	MONOPOLE
<b>Property Owner:</b>	BISHOP B W & SONS INC
<b>Pace Job:</b>	MRCTB055958
<b>RFDS technology:</b>	5G NR 1SR CBAND

### Report Information

**Report Writer:** Sumit Singh

**Report Generated Date:** 05-24-2022

### Compliance Statement

**AT&T Mobility Compliance Statement:** Based on the information collected, AT&T Mobility will be Compliant when the remediation recommended in section 5 or appropriate remediation determined by AT&T is implemented

## Table of Contents

1. Executive Summary .....	3
1.1 Site Summary.....	3
1.2 Signage Summary (Proposed).....	3
1.3 List of Documents used to prepare this Report.....	3
2. Site Scale Map .....	4
3. Antenna Inventory .....	5
4. Predicted Emission.....	7
4.1 Predictive Cumulative MPE Contribution from All Sources at Antennas Centerline Level (137 ft.).....	7
4.2 Predictive Cumulative MPE Contribution from All Sources at Ground Level (0 ft.) .....	8
5. Statement of Compliance.....	9
5.1 Statement of AT&T Mobility Compliance .....	9
Appendix A – Statement of Limiting Conditions .....	11
Appendix B – FCC Guidelines and Emissions Threshold Limits .....	12
Appendix C – Rules & Regulations .....	14
Appendix D – General Safety Recommendations .....	15
Appendix E – References.....	16
Appendix F – Proprietary Statement.....	19

## 1. Executive Summary

### 1.1 Site Summary

Max Predictive Spatial Average MPE% & Location on Site (General Public)	17212.90% on Antennas Centerline Level & at AT&T Sec-B antenna no. #B3-2
Max Predictive Spatial Average MPE% on Ground (General Public)	1.13%
AT&T Mobility Site Compliance	AT&T Mobility will be Compliant by implementing remediation recommended as per section 5 in this report.

**TABLE 1: Site Summary**

### 1.2 Signage Summary (Proposed)

AT&T Signage Locations	Sign Type									
	Safety Instructions	Notice Sign 2	Caution Sign 2	Caution Sign 2B	Caution Sign 2C	Caution 7"x7"	Warning Sign 1B	RF Exposure Map	Lock	Barriers
Access Point(s)				1						
Alpha										
Beta										
Gamma										


**TABLE 2: Signage Summary (Proposed)**

### 1.3 List of Documents used to prepare this Report

- 90% CD
- RFDS



## 2. Site Scale Map



AT&T Antenna		Proposed		Proposed Signage								Map Scale = 10 ft
	Panel		Barrier									
	OMNI		Posts									

### 3. Antenna Inventory

Ant ID	Operator	Antenna Mfg	Antenna Model	Antenna Type	FREQ. (MHz)	TECH.	AZ. (0)	H B W (0)	Antenna Gain (dBd)	Antenna Aperture (ft)	Transmitter Power (Watts)	Total Loss (dB)	Total ERP (Watts)	Total EIRP (Watts)
A2	AT&T	CCI	OPA65R-BU6D	Panel	700	LTE	40	73	12.15	6	120.00	0.5	1754.61	2878.60
A2	AT&T	CCI	OPA65R-BU6D	Panel	1900	LTE/5G	40	68	15.95	6	120.00	0.5	4209.02	6905.28
A3-1	AT&T	Ericsson	AIR 6419 B77G^	Panel	3450	5G	40	11	23.5	2.55	108.44*	0	24277.05*	39828.68*
A3-2	AT&T	Ericsson	AIR 6449 B77D^	Panel	3840	5G	40	11	23.5	2.55	108.44*	0	24277.05*	39828.68*
A4	AT&T	CCI	DMP65R-BU6D	Panel	700	LTE	40	74	11.85	6	120.00	0.5	1637.50	2686.47
A4	AT&T	CCI	DMP65R-BU6D	Panel	850	5G	40	63	12.45	6	120.00	0.5	1880.10	3084.47
A4	AT&T	CCI	DMP65R-BU6D	Panel	2100	LTE/5G	40	68	15.95	6	120.00	0.5	4209.02	6905.28
B2	AT&T	CCI	OPA65R-BU6D	Panel	700	LTE	160	73	12.15	6	120.00	0.5	1754.61	2878.60
B2	AT&T	CCI	OPA65R-BU6D	Panel	1900	LTE/5G	160	68	15.95	6	120.00	0.5	4209.02	6905.28
B3-1	AT&T	Ericsson	AIR 6419 B77G^	Panel	3450	5G	160	11	23.5	2.55	108.44*	0	24277.05*	39828.68*
B3-2	AT&T	Ericsson	AIR 6449 B77D^	Panel	3840	5G	160	11	23.5	2.55	108.44*	0	24277.05*	39828.68*
B4	AT&T	CCI	DMP65R-BU6D	Panel	700	LTE	160	74	11.85	6	120.00	0.5	1637.50	2686.47
B4	AT&T	CCI	DMP65R-BU6D	Panel	850	5G	160	63	12.45	6	120.00	0.5	1880.10	3084.47
B4	AT&T	CCI	DMP65R-BU6D	Panel	2100	LTE/5G	160	68	15.95	6	120.00	0.5	4209.02	6905.28
C2	AT&T	CCI	OPA65R-BU6D	Panel	700	LTE	280	73	12.15	6	120.00	0.5	1754.61	2878.60
C2	AT&T	CCI	OPA65R-BU6D	Panel	1900	LTE/5G	280	68	15.95	6	120.00	0.5	4209.02	6905.28
C3-1	AT&T	Ericsson	AIR 6419 B77G^	Panel	3450	5G	280	11	23.5	2.55	108.44*	0	24277.05*	39828.68*
C3-2	AT&T	Ericsson	AIR 6449 B77D^	Panel	3840	5G	280	11	23.5	2.55	108.44*	0	24277.05*	39828.68*
C4	AT&T	CCI	DMP65R-BU6D	Panel	700	LTE	280	74	11.85	6	120.00	0.5	1637.50	2686.47
C4	AT&T	CCI	DMP65R-BU6D	Panel	850	5G	280	63	12.45	6	120.00	0.5	1880.10	3084.47
C4	AT&T	CCI	DMP65R-BU6D	Panel	2100	LTE/5G	280	68	15.95	6	120.00	0.5	4209.02	6905.28

**Table 3.1: Antenna Inventory Table**

Note: ^ **Mechanical Tilt value of "0°" MUST be retained for C-BAND and/or DoD AAS antenna(s) at all times to ensure that "EME (Predictive) Study" shall remain valid.**

\* 75% TDD duty Cycle, 1.5dB Power Tolerance & 0.32 Power Reduction factor<sup>1</sup> are used to calculate Transmitter Power & ERP/EIRP


## Antenna Heights (Z)

Ant ID	Operator	Antenna Radiation Centerline	Z-Height from Ground
A2	AT&T	137.00	134.00
A3-1	AT&T	138.78	137.50
A3-2	AT&T	135.23	133.95
A4	AT&T	137.00	134.00
B2	AT&T	137.00	134.00
B3-1	AT&T	138.78	137.50
B3-2	AT&T	135.23	133.95
B4	AT&T	137.00	134.00
C2	AT&T	137.00	134.00
C3-1	AT&T	138.78	137.50
C3-2	AT&T	135.23	133.95
C4	AT&T	137.00	134.00

**Table 3.2: Antenna Height(s) Summary Table**

#### 4. Predicted Emission

##### 4.1 Predictive Cumulative MPE Contribution from All Sources at Antennas Centerline Level (137 ft.)



Max. Predictive Spatial Average MPE% = **17212.90%**

% of FCC General Public Exposure Limit (Predictive Spatial Average)


Non-Simulated	0-1	1-100	100-500	500-5000	>5000

Proposed Barrier

Proposed Posts

Map Scale = 10 ft

**4.2 Predictive Cumulative MPE Contribution from All Sources at Ground Level (0 ft.)**



Max. Predictive Spatial Average MPE% = 1.13%

% of FCC General Public Exposure Limit (Predictive Spatial Average)

Proposed Barrier   
 Proposed Posts

Non-Simulated	0-1	1-100	100-500	500-5000	>5000

Map Scale = 10 ft

## 5. Statement of Compliance

### 5.1 *Statement of AT&T Mobility Compliance*

At the time of our Analysis, AT&T Mobility is required to take action to fulfill their Obligations to comply with the FCC's mandate as defined in OET-65

#### Recommendations

##### AT&T Alpha Sector:

- No action required.

##### AT&T Beta Sector:

- No action required.


##### AT&T Gamma Sector:

- No action required.

##### Monopole:

- One Caution 2B Sign to be posted on Monopole at climbing access, facing outwards so approaching people can see as shown in "Recommendations Map – Detailed View" on page 10. (1 Total Sign)

Recommendations Map – Detailed View



<b>AT&amp;T Antenna</b> Panel OMNI		<b>Proposed</b> Barrier Posts		<b>Proposed Signage</b>							<b>Map Scale = 10 ft</b>
		Safety Instructions	Notice 2	Caution 2	Caution 2B	Caution 2C	Caution 7"x7"	Warning 1B	RF Exposure Map	Lock	

## Appendix A – Statement of Limiting Conditions

### General Model Assumptions

*In this site compliance report, it is assumed that all antennas are operating at full power at all times. AT&T has further recommended to assume a 75% duty cycle of maximum radiated power for all LTE & 5G carriers (& consider 100% duty cycle for all UMTS carriers).*

*In this site compliance report, it is assumed that Mechanical Tilt value of “0°” MUST be retained for C-BAND and/or DoD AAS<sup>^</sup> antenna(s) at all times to ensure that “EME (Predictive) Study” shall remain valid.*

*AT&T recommended to consider - For C-BAND and/or DoD AAS<sup>^</sup> antenna(s) 75% TDD duty Cycle, 1.5dB Power Tolerance & 0.32 Power Reduction factor<sup>1</sup> are used to calculate Transmitter Power & ERP/EIRP.*

*AT&T recommended to use worst-case tilts for the simulations.*

**Power Reduction Factor:** IEC Standard 62232: 2017 allows for a statistically conservative power density model to more realistically define the RF exposure area. AT&T recommends a “0.32” factor to calculate the “Actual Maximum” (time averaged) power value, which accounts for “Beam Scanning,” “Scheduling,” and “RBS Utilization” This recommended value is a conservative figure modelled and supported by other vendors and through measurements published in scientific articles and white papers by IEEE and others. Those publication are listed below:

1. IEEE Access, *Time-Averaged Realistic Maximum Power Levels for the Assessment of RF Exposure for 5G Radio Base Stations Using Massive MIMO* (Published Sept. 18, 2017 / BJÖRN THORS, ANDERS FURUSKÄR, DAVIDE COLOMBI, AND CHRISTER TÖRNEVIK)
2. IEEE Explore, *A Statistical Approach for RF Exposure Compliance Boundary Assessment in Massive MIMO Systems* (Published Jan. 25, 2018 / Paolo Baracca, Andreas Weber, Thorsten Wild, Christophe Grangeat)
3. IEEE Access, *In-situ Measurement Methodology for the Assessment of 5G NR Massive MIMO Base Station Exposure at Sub-6 GHz Frequencies* (Published Dec. 20, 2019 / SAM AERTS, LEEN VERLOOCK, MATTHIAS VAN DEN BOSSCHE, DAVIDE COLOMBI, LUC MARTENS, CHRISTER TÖRNEVIK AND WOUT JOSEPH)
4. Applied Sciences, *Analysis of the Actual Power and EMF Exposure from Base Stations in a Commercial 5G Network* (Published July 30, 2020 / Davide Colombi, Paramananda Joshi, Bo Xu, Fatemeh Ghasemifard, Vignesh Narasaraju and Christer Törnevik)
5. Ofcom Technical Report, *Electromagnetic Field (EMF) measurements near 5G mobile phone base stations* (Published Feb. 21, 2020 / Davide Colombi, Paramananda Joshi, Bo Xu, Fatemeh Ghasemifard, Vignesh Narasaraju and Christer Törnevik)

*MobileComm believes these areas to be safe for entry by occupationally trained personnel utilizing appropriate personal protective equipment (in most cases, a personal monitor). Thus, at any time, if power density measurements were made, we believe the real time measurements would indicate levels below those depicted in the RF emission diagram(s) in this report. By modelling in this way, MobileComm has conservatively shown exclusion areas – areas that should not be entered without the use of a personal monitor, carriers reducing power, or performing real-time measurements to indicate real-time exposure levels.*

### Use of Generic Antennas

*For the purposes of this report, the use of “Generic” as an antenna model, or “Other Carrier” for an operator means the information about a carrier, their FCC license and/or antenna information was not provided and could not be obtained while on site. In the event of unknown information, MobileComm will use our industry specific knowledge of equipment, antenna models, and transmit power to model the site. Information about similar facilities is used when the service is identified and associated with a particular antenna. If no information is available regarding the transmitting service associated with an unidentified antenna, using the antenna manufacturer’s published data regarding the antenna’s physical characteristics makes more conservative assumptions.*

*Where the frequency is unknown, MobileComm uses the closest frequency in the antenna’s range that corresponds to the highest Maximum Exposure Limit (MPE), resulting in a conservative analysis.*



## Appendix B – FCC Guidelines and Emissions Threshold Limits

All power density values used in this report were analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General Population/Uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the 700 and 800 MHz Bands is approximately  $467 \mu\text{W}/\text{cm}^2$  and  $567 \mu\text{W}/\text{cm}^2$  respectively, and the general population exposure limit for the 1900 MHz PCS and 2100 MHz AWS bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/Controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure, have been properly trained in RF safety and can exercise control over their exposure. Occupational/Controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure, have been trained in RF safety and can exercise control over his or her exposure by leaving the area or by some other appropriate means. The Occupational/Controlled exposure limits all utilized frequency bands is five (5) times the FCC's General Public / Uncontrolled exposure limit.

Additional details can be found in FCC OET 65.

Table 1: Limits for Maximum Permissible Exposure (MPE)				
(A) Limits for Occupational/Controlled Exposure				
Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (H) (A/m)	Power Density (S) (mW/cm <sup>2</sup> )	Averaging Time [E] <sup>2</sup> , [H] <sup>2</sup> , or S (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f <sup>2</sup> )*	6
30-300	61.4	0.163	1.0	6
300-1,500	--	--	f/300	6
1,500-100,000	--	--	5	6
(B) Limits for General Public/Uncontrolled Exposure				
Frequency Range (MHz)	Electric Field Strength (E) (V/m)	Magnetic Field Strength (H) (A/m)	Power Density (S) (mW/cm <sup>2</sup> )	Averaging Time [E] <sup>2</sup> , [H] <sup>2</sup> , or S (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f <sup>2</sup> )*	30
30-300	27.5	0.073	0.2	30
300-1,500	--	--	f/1,500	30
1,500-100,000	--	--	1.0	30

## Appendix C – Rules & Regulations

### Explanation of Applicable Rules and Regulations

*FCC has set forth guidelines in OET Bulletin 65 for human exposure to radio frequency electromagnetic fields. Currently, there are two different levels of MPE - General Public MPE and Occupational MPE. An individual classified as Occupational can be defined as an individual who has received appropriate RF training and meets the conditions outlined below. General Public is defined as anyone who does not meet the conditions of being Occupational. FCC Rules and Regulations define compliance in terms of total exposure to total RF energy, regardless of location of or proximity to the sources of energy.*

*It is the responsibility of all licensees to ensure these guidelines are maintained at all times. It is the ongoing responsibility of all licensees composing the site to maintain ongoing compliance with FCC rules and regulations.*

*A building owner or site manager can use this report as part of an overall RF Health and Safety Policy. It is important for building owners/site managers to identify areas in excess of the General Population MPE and ensure that only persons qualified as Occupational are granted access to those areas.*

### Occupational Environment Explained

*The FCC definition of Occupational exposure limits apply to persons who:*

- *are exposed to RF energy as a consequence of their employment;*
- *have been made aware of the possibility of exposure; and*
- *can exercise control over their exposure.*

*FCC guidelines go further to state that persons must complete RF Safety Awareness training and must be trained in the use of appropriate personal protective equipment.*

*In order to consider this site an Occupational Environment, the site must be controlled to prevent access by any individuals classified as the General Public. Compliance is also maintained when any non-occupational individuals (the General Public) are prevented from accessing areas indicated as Red or Yellow in the attached RF Emissions diagram. In addition, a person must be aware of the RF environment into which they are entering. This can be accomplished by an RF Safety Awareness class, and by appropriate written documentation such as this Site Compliance Report.*

## Appendix D – General Safety Recommendations

The following are general recommendations appropriate for any site with accessible areas in excess of 100% General Public MPE. These recommendations are not specific to this site. These are safety recommendations appropriate for typical site management, building management, and other tenant operations.

- All individuals needing access to the main site should be instructed to read and obey all posted placards and signs.
- The site should be routinely inspected and this or similar report updated with the addition of any antennas or upon any changes to the RF environment including:
  - adding new antennas that may have been located on the site
  - removing of any existing antennas
  - changes in the radiating power or number of RF emitters
- Post the appropriate SAFETY INSTRUCTIONS, NOTICE, CAUTION & WARNING sign at the main site access point(s) and other locations as required. Note: Please refer to RF Exposure Diagrams in the report section above, to inform everyone who has access to this site that beyond posted signs there may be levels in excess of the limits prescribed by the FCC. The signs below are examples of signs meeting FCC guidelines.



- Ensure that the site door remains locked (or appropriately controlled) to deny access to the general public if deemed as policy by the building/site owner.
- For a General Public environment the five color levels identified in measured RF emission diagram can be interpreted in the following manner:
  - White represents areas predicted to be greater than or equal to 0% and less than 1% of the MPE general public limits
  - Green represents areas predicted to be greater than or equal to 1% and less than 100% of the MPE general public limits
  - Blue represents areas predicted to be greater than or equal to 100% and lesser than 500% of the MPE general public limits.
  - Yellow represents areas predicted to be greater than or equal to 500% and lesser than 5000% of the MPE general public limits.
  - Red areas indicates safety predicted levels greater than or equal to 5000% of the MPE general public limits.

## Appendix E – References

### 1 - FCC Definition

*FCC defines an Occupational or Controlled environment as one where persons are exposed to RF fields as a consequence of their employment and where those persons exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Typical criteria for an Occupational or Controlled environment is restricted access (i.e. locked doors, gates, etc.) to areas where antennas are located coupled with proper RF warning signage.*

*FCC defines a site as a General Public or Uncontrolled environment when human exposure to RF fields occurs to the general public or in which persons who are exposed as a consequence of their employment may not be fully aware of the potential for exposure or cannot exercise control over the exposure. Typical criteria for a General Public or Uncontrolled environment are unrestricted access (i.e. unlocked or no restrictions) to areas where antennas are located without proper RF warning signage being posted.*

### 2 - Physical Testing measurement procedure and Tools

*The Narda Broadband Field Meter NBM-550 can make rapid conformance measurements with evaluation in the time domain when used in conjunction EA5091 probe. This probe is a so-called Shaped Probe, i.e. it is frequency weighted so that it automatically takes account of the FCC Occupational limit values. To collect data, the probe is pointed towards the potential source(s) of EME radiation and moved slowly from ground level up to slightly above head height (approx. 6 ft).*

*Spatial Average Measurement A technique used to average a minimum of ten (10) measurements taken in a ten (10) second interval from zero (0) to six (6) feet. This measurement is intended to model the average energy an average sized human body will absorb while present in an electromagnetic field of energy.*

### 3 - Site Safety Procedures

*The following items are general safety recommendations that should be administered on a site by site basis as needed by the carrier.*

**General Maintenance Work:** *Any maintenance personnel required to work immediately in front of antennas and / or in areas indicated as above 100% of the Occupational MPE limits should coordinate with the wireless operators to disable transmitters during their work activities.*

**Training and Qualification Verification:** *All personnel accessing areas indicated as exceeding the General Population MPE limits should have a basic understanding of EME awareness and RF Safety procedures when working around transmitting antennas. Awareness training increases a workers understanding to potential RF exposure scenarios. Awareness can be achieved in a number of ways (e.g. videos, formal classroom lecture or internet based courses).*

**Physical Access Control:** *Access restrictions to transmitting antennas locations is the primary element in a site safety plan. Examples of access restrictions are as follows:*

- *Locked door or gate*
- *Alarmed door*
- *Locked ladder access*
- *Restrictive Barrier at antenna locations (e.g. Chain link with posted RF Sign)*

**RF Signage:** *Everyone should obey all posted signs at all times. RF signs play an important role in properly warning a worker prior to entering into a potential RF Exposure area.*

**Assume all antennas are active:** *Due to the nature of telecommunications transmissions, an antenna transmits intermittently. Always assume an antenna is transmitting. Never stop in front of an antenna. If you have to pass by an antenna, move through as quickly and safely as possible thereby reducing any exposure to a minimum.*

**Maintain a 3 foot clearance from all antennas:** *There is a direct correlation between the strength of an EME field and the distance from the transmitting antenna. The further away from an antenna, the lower the corresponding EME field is.*

**Rooftop RF Emissions Diagram:** *Section 4 of this report contains an RF Emissions Diagram that outlines various theoretical Maximum Permissible Exposure (MPE) areas on the rooftop. This analysis is all theoretical and assumes a duty cycle of 75% for each transmitting antenna at full power. This analysis is a worst case scenario. This analysis is based on one of two access control criteria: General Public criteria means the access to the site is uncontrolled and anyone can gain access. Occupational criteria means the access is restricted and only properly trained individuals can gain access to the antenna locations.*

#### **4 - Definitions**

**Compliance-** *The determination of whether a site is safe or not with regards to Human Exposure to Radio Frequency Radiation from transmitting antennas.*

**Decibel (dB)** – *A unit for measuring power or strength of a signal.*

**Duty Cycle** – *The percent of pulse duration to the pulse period of a periodic pulse train. Also, may be a measure of the temporal transmission characteristic of an intermittently transmitting RF source such as a paging antenna by dividing average transmission duration by the average period for transmission. A duty cycle of 75% corresponds to continuous operation.*

**Effective (or Equivalent) Isotropic Radiated Power (EIRP)** – *The product of the power supplied to the antenna and the antenna gain in a given direction relative to an isotropic antenna, this product is divided by the cable losses*

**Effective Radiated Power (ERP)** – *In a given direction, the relative gain of a transmitting antenna with respect to the maximum directivity of a half wave dipole multiplied by the net power accepted by the antenna from the connecting transmitter.*

**Gain (of an antenna in dbd)** – *The ratio of the maximum intensity in a given direction to the maximum radiation in the same direction from a reference dipole. Gain is a measure of the relative efficiency of a directional antennas as compared to a reference dipole.*

**General Population/Uncontrolled Environment** – *Defined by the FCC, as an area where RFR exposure may occur to persons who are unaware of the potential for exposure and who have no control of their exposure. General Population is also referenced as General Public.*

**Generic Antenna** – *For the purposes of this report, the use of “Generic” as an antenna model means the antenna information was not provided and could not be obtained while on site. In the event of unknown information, MobileComm will use our industry specific knowledge of antenna models to select a worst case scenario antenna to model the site.*

**Isotropic Antenna** – *An antenna that is completely non-directional. In other words, an antenna that radiates energy equally in all directions.*

**Maximum Measurement** – *This measurement represents the single largest measurement recorded when performing a spatial average measurement.*



**Maximum Exposure Limit (MPE)** – *The RMS and peak electric and magnetic field strength, their squares, or the plane-wave equivalent power densities associated with these fields to which a person may be exposed without harmful effect and with acceptable safety factor.*

**Occupational/Controlled Environment** – *Defined by the FCC, as an area where Radio Frequency Radiation (RFR) exposure may occur to persons who are aware of the potential for exposure as a condition of employment or specific activity and can exercise control over their exposure.*

**Radio Frequency Radiation** – *Electromagnetic waves that are propagated from antennas through space.*

**Spatial Average Measurement** – *A technique used to average a minimum of ten (10) measurements taken in a ten (10) second interval from zero (0) to six (6) feet. This measurement is intended to model the average energy an average sized human body will absorb while present in an electromagnetic field of energy.*

**Transmitter Power Output (TPO)** – *The radio frequency output power of a transmitter's final radio frequency stage as measured at the output terminal while connected to a load.*

## Appendix F – Proprietary Statement

*This report was prepared for the use of AT&T Mobility, LLC to meet requirements specified in AT&T's corporate RF safety guidelines. It was performed in accordance with generally accepted practices of other consultants undertaking similar studies at the same time and in the same locale under like circumstances. The conclusions provided by MobileComm are based solely on the information provided by AT&T Mobility and all observations in this report are valid on the date of the investigation. Any additional information that becomes available concerning the site should be provided to MobileComm so that our conclusions may be revised and modified, if necessary. This report has been prepared in accordance with Standard Conditions for Engagement and authorized proposal, both of which are integral parts of this report. No other warranty, expressed or implied, is made.*










575 MOROSGO DRIVE  
ATLANTA, GA 30324-3300



1505 WESTLAKE AVENUE NORTH, SUITE 800  
SEATTLE, WA 98109



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.blgrp.com

AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE

ISSUED FOR:


REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT




B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

SHEET NUMBER: **C-1.1** REVISION: **1**



1 SITE PLAN  
SCALE: 1/4"=1'-0" (FULL SIZE)  
1/8"=1'-0" (11x17)




1:37067.006.01\_NHV\_102\_943127.dwg - Sheet: C-1.1 - User: kevin.turkall - Jun 03, 2022 - 2:50pm

AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE




1 EXISTING EQUIPMENT PLAN  
SCALE: 1/2"=1'-0" (FULL SIZE)  
1/4"=1'-0" (11x17)

- GROUND SCOPE OF WORK:
- INSTALL (3) VERTIV RECTIFIERS IN VERTIV NETSURE 7100 DC POWER PLANT
  - INSTALL (1) GEN 2 DC 12
  - INSTALL (1) 6648 WITH XCEDE CABLE

ISSUED FOR:

REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT



2 FINAL EQUIPMENT PLAN  
SCALE: 1/2"=1'-0" (FULL SIZE)  
1/4"=1'-0" (11x17)




B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER: **C-1.2** REVISION: **1**


1:37067.006.01\_NHV\_102\_943127.dwg - Sheet: C-1.2 - User: kevin.turkall - Jun 03, 2022 - 2:51pm



1 FINAL ELEVATION  
SCALE: NOT TO SCALE



2 EXISTING ANTENNA PLAN  
SCALE: 3/8"=1'-0" (FULL SIZE)  
3/16"=1'-0" (11x17)



3 FINAL ANTENNA PLAN  
SCALE: 3/8"=1'-0" (FULL SIZE)  
3/16"=1'-0" (11x17)

"LOOK UP" - CROWN CASTLE USA INC. SAFETY CLIMB REQUIREMENT:

THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR CROWN CASTLE USA INC. POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.

- INSTALLER NOTES:
1. REFERENCE C-3 FOR FINAL EQUIPMENT SCHEDULE.
  2. REFERENCE C-4 FOR NEW EQUIPMENT SPECIFICATIONS.
  3. CONTRACTOR TO VERIFY ALL ANTENNA TIP HEIGHTS DO NOT EXCEED BEACON BASE HEIGHT.
  4. 3'-0" MINIMUM DISTANCE REQUIRED BETWEEN LTE ANTENNAS ON SAME SECTOR.
  5. 6'-0" MINIMUM DISTANCE REQUIRED BETWEEN 700BC & 700DE ANTENNAS ON SAME SECTOR.
  6. 4'-0" MINIMUM DISTANCE REQUIRED BETWEEN LTE 700 ANTENNAS ON OPPOSING SECTORS.
  7. ALL ANTENNA MEASUREMENT DISTANCES MUST BE EDGE TO EDGE (RELOCATE ANTENNAS AS NEEDED).
  8. 8" MINIMUM DISTANCE REQUIRED BETWEEN ANTENNA & RADIO. SEE GENERIC EXAMPLE DETAIL ON SHEET C-4.

575 MOROSGO DRIVE  
ATLANTA, GA 30324-3300

1505 WESTLAKE AVENUE NORTH, SUITE 800  
SEATTLE, WA 98109

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.blgrp.com

AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE

ISSUED FOR:

REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT

6/3/22

B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SHEET NUMBER: **C-2** REVISION: **1**

1:37067.006.01\_NHV\_102\_943127.dwg - Sheet: C-2 - User: kevin.turkoll - Jun 03, 2022 - 2:51pm

FINAL EQUIPMENT SCHEDULE  
(VERIFY WITH CURRENT RFDS)

ALPHA																			
POSITION	ANTENNA				RADIO			DIPLEXER			TMA			SURGE PROTECTION		CABLES			
	TECH.	STATUS/MANUFACTURER MODEL	AZIMUTH	RAD CENTER	QTY.	STATUS/MODEL	LOCATION	QTY.	STATUS	LOCATION	QTY.	STATUS/MANUFACTURER MODEL	QTY.	STATUS/MODEL	QTY.	STATUS/TYPE	SIZE	LENGTH	
A1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
A2	LTE/5G	(E) CCI - OPA65R-BU6DA	40°	137'-0"	1	(E) 4478 B14	TOWER	-	-	-	-	-	1	(E) DC6-48-60-18-8F	2	(E) 8AWG DC	13/16"	187'-0"	
					1	(E) 8843 B2/B66A	TOWER								1	(E) 18 PAIR FIBER	3/8"	187'-0"	
A3	5G CABND/5G DOD	(N) ERICSSON - AIR6449 B77D+AIR6419 B77G STACKED	40°	138'-9" 135'-3"	-	INTEGRATED WITHIN	-	-	-	-	-	-	-	-	-	-	-	-	
A4	LTE/5G	(E) CCI - DMP65R-BU6DA	40°	137'-0"	1	(E) 4449 B5/B12	TOWER	-	-	-	-	-	-	-	2	(E) COAX	1-5/8"	187'-0"	
BETA																			
B1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
B2	LTE/5G	(E) CCI - OPA65R-BU6DA	160°	137'-0"	1	(E) 4478 B14	TOWER	-	-	-	-	-	1	(E) DC6-48-60-18-8F	2	(E) 8AWG DC	13/16"	187'-0"	
					1	(E) 8843 B2/B66A	TOWER								1	(E) 18 PAIR FIBER	3/8"	187'-0"	
B3	5G CABND/5G DOD	(N) ERICSSON - AIR6449 B77D+AIR6419 B77G STACKED	160°	138'-9" 135'-3"	-	INTEGRATED WITHIN	-	-	-	-	-	-	-	-	-	-	-	-	
B4	LTE/5G	(E) CCI - DMP65R-BU6DA	160°	137'-0"	1	(E) 4449 B5/B12	TOWER	-	-	-	-	-	-	-	2	(E) COAX	1-5/8"	187'-0"	
GAMMA																			
C1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
C2	LTE/5G	(E) CCI - OPA65R-BU6DA	280°	137'-0"	1	(E) 4478 B14	TOWER	-	-	-	-	-	1	(N) DC9-48-60-24-8C-EV	3	(E) 6AWG DC	7/8"	187'-0"	
					1	(E) 8843 B2/B66A	TOWER								1	(E) 24 PAIR FIBER	3/8"	187'-0"	
C3	5G CABND/5G DOD	(N) ERICSSON - AIR6449 B77D+AIR6419 B77G STACKED	280°	138'-9" 135'-3"	-	INTEGRATED WITHIN	-	-	-	-	-	-	-	-	-	-	-	-	
C4	LTE/5G	(E) CCI - DMP65R-BU6DA	280°	137'-0"	1	(E) 4449 B5/B12	TOWER	-	-	-	-	-	-	-	2	(E) COAX	1-5/8"	187'-0"	
															UNUSED FEEDLINES:	6	COAX	1-5/8"	187'-0"

NOTE:  
(E) - EXISTING  
(N) - NEW



AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE

ISSUED FOR:

REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT



B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SHEET NUMBER: **C-3** REVISION: **1**

1 FINAL ANTENNA AND FEEDLINE SCHEDULE  
SCALE: NOT TO SCALE


1:37067.006.01\_NHV\_102\_943127.dwg - Sheet: C-3 - User: kevin.turkoll - Jun 03, 2022 - 2:51pm

**INSTALLER NOTES:**

1. COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRHs RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING.
2. DO NOT OPEN RRH PACKAGES IN THE RAIN.
3. ALL PIPES, BRACKETS, AND MISCELLANEOUS HARDWARE TO BE GALVANIZED UNLESS NOTED OTHERWISE.
4. RRHs SHALL NOT BE INSTALLED CLOSER THAN 8" TO ANTENNAS.



1 STACKED ANTENNA MOUNTING DETAIL  
SCALE: NOT TO SCALE




2 DUAL RADIO MOUNT  
SCALE: NOT TO SCALE



3 NOT USED  
SCALE: NOT TO SCALE

**RAYCAP**  
DC9-48-60-24-8C-EV

RAYCAP - DC9-48-60-24-8C-EV  
SIZE: 10.24x31.40 IN.  
WEIGHT: 26.2 LBS  
NOMINAL OPERATING VOLTAGE: 48 VDC  
VOLTAGE PROTECTION RATING: 330 V  
WIND LOADING: 150 MPH SUSTAINED (105.7 LBS)  
WIND LOADING: 195 MPH GUST (213.6 LBS)



CONTRACTOR TO USE "THREAD LUBRICANT" ON MOUNTING BOLTS DURING INSTALLATION




**NOTES:**

1. REMOVE CABLE SEALING GLAND AND INSTALL M32x1.5 METRIC-T0-1" NPT ADAPTER (COOPER CROUSE-HINES P/N CAP 740 994 OR EQUIVALENT MFR) WHEN CONNECTING CONDUIT TO OVP.

6 SQUID MOUNTING DETAIL  
SCALE: NOT TO SCALE

**INSTALLER NOTES:**


1. COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRHs RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING.
2. DO NOT OPEN RRH PACKAGES IN THE RAIN.
3. ALL PIPES, BRACKETS, AND MISCELLANEOUS HARDWARE TO BE GALVANIZED UNLESS NOTED OTHERWISE.
4. RRHs SHALL NOT BE INSTALLED CLOSER THAN 8" TO ANTENNAS.



4 ANTENNA MOUNTING DETAIL  
SCALE: NOT TO SCALE

**INSTALLER NOTES:**

1. COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRHs RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING.
2. DO NOT OPEN RRH PACKAGES IN THE RAIN.
3. ALL PIPES, BRACKETS, AND MISCELLANEOUS HARDWARE TO BE GALVANIZED UNLESS NOTED OTHERWISE.
4. RRHs SHALL NOT BE INSTALLED CLOSER THAN 8" TO ANTENNAS.



5 DUAL RRH MOUNTING DETAIL  
SCALE: NOT TO SCALE

575 MOROSGO DRIVE  
ATLANTA, GA 30324-3300

1505 WESTLAKE AVENUE NORTH, SUITE 800  
SEATTLE, WA 98109

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.blgrp.com

AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE

**ISSUED FOR:**

REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT




6/3/22

B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SHEET NUMBER:	REVISION:
C-4	1

1:37067.006.01\_NHV\_102\_943127.dwg - Sheet: C-4 - User: kevin.turkall - Jun 03, 2022 - 2:51pm



ANTENNA DIMENSIONS (INCHES)				
MODEL	HEIGHT	WIDTH	DEPTH	WEIGHT
AIR6449 B77D	30.39"	15.87"	8.07"	81.60 lbs

1 ANTENNA DETAIL  
SCALE: NOT TO SCALE



ANTENNA DIMENSIONS (INCHES)				
MODEL	HEIGHT	WIDTH	DEPTH	WEIGHT
AIR6419 B77G	31.10"	16.10"	7.30"	44.0 lbs

2 ANTENNA DETAIL  
SCALE: NOT TO SCALE

3 NOT USED  
SCALE: NOT TO SCALE

575 MOROSGO DRIVE  
ATLANTA, GA 30324-3300

1505 WESTLAKE AVENUE NORTH, SUITE 800  
SEATTLE, WA 98109

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.blgrp.com

AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE

ISSUED FOR:

REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT



6/3/22

B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

SHEET NUMBER: **C-5** REVISION: **1**

4 NOT USED  
SCALE: NOT TO SCALE

5 NOT USED  
SCALE: NOT TO SCALE

6 NOT USED  
SCALE: NOT TO SCALE



GROUNDING PLAN LEGEND:

- GROUND WIRE
- EXOTHERMIC WELD
- MECHANICAL CONNECTION
- ⊙ COPPER GROUND ROD
- ⊗ GROUND ROD W/ TEST WELL

CELL REFERENCE GROUND BAR: POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUITS (ATT-TP-76416 7.6.7).

HATCH PLATE GROUND BAR: BOND TO THE INTERIOR GROUND RING WITH (2) #2 STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CELL SITE REFERENCE GROUND BAR MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) #2 STRANDED GREEN INSULATED COPPER CONDUCTORS.

EXTERIOR CABLE ENTRY PORT GROUND BARS: LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE (ATT-TP-76416 7.6.7.2).


DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICES CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR PER TP76300 SECTION H 6 AND TP76416 FIGURE 7-11 REQUIREMENTS.



575 MOROSGO DRIVE  
ATLANTA, GA 30324-3300



1505 WESTLAKE AVENUE NORTH, SUITE 800  
SEATTLE, WA 98109



1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.blgrp.com

AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE

ISSUED FOR:


REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT




B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

SHEET NUMBER: **G-1** REVISION: **1**




1 GROUNDING SCHEMATIC  
SCALE: NOT TO SCALE



NOTES:

1. DOUBLING UP "OR STACKING" OF CONNECTIONS IS NOT PERMITTED.
2. EXTERIOR ANTIOXIDANT JOINT COMPOUND TO BE USED ON ALL EXTERIOR CONNECTIONS.
3. GROUND BAR SHALL NOT BE ISOLATED FROM TOWER. MOUNT DIRECTLY TO ANTENNA MOUNT STEEL.

1 ANTENNA SECTOR GROUND BAR DETAIL  
SCALE: NOT TO SCALE




NOTES:

1. EXTERIOR ANTIOXIDANT JOINT COMPOUND TO BE USED ON ALL EXTERIOR CONNECTIONS.
2. GROUND BAR SHALL NOT BE ISOLATED FROM TOWER. MOUNT DIRECTLY TO TOWER STEEL (TOWER ONLY).
3. GROUND BAR SHALL BE ISOLATED FROM BUILDING OR SHELTER.

2 TOWER/SHELTER GROUND BAR DETAIL  
SCALE: NOT TO SCALE


WIRE SIZE	BURNDY LUG	BOLT SIZE
#6 GREEN INSULATED	YA6C-2TC38	3/8" - 16 NC SS 2 BOLT
#2 SOLID TINNED	YA3C-2TC38	3/8" - 16 NC SS 2 BOLT
#2 STRANDED	YA2C-2TC38	3/8" - 16 NC SS 2 BOLT
#2/0 STRANDED	YA26-2TC38	3/8" - 16 NC SS 2 BOLT
#4/0 STRANDED	YA28-2N	1/2" - 16 NC SS 2 BOLT




NOTE:

ALL GROUNDING LUGS ARE TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. ALL HARDWARE BOLTS, NUTS, LOCK WASHERS SHALL BE STAINLESS STEEL. ALL HARDWARE ARE TO BE AS FOLLOWS: BOLT, FLAT WASHER, GROUND BAR, GROUND LUG, FLAT WASHER AND NUT.

3 MECHANICAL LUG CONNECTION  
SCALE: NOT TO SCALE




4 GROUNDWIRE INSTALLATION  
SCALE: NOT TO SCALE




NOTES:

1. DOWN LEAD (HOME RUN) CONDUCTORS ARE NOT TO BE INSTALLED ON CROWN CASTLE USA INC. TOWER, PER THE GROUNDING DOWN CONDUCTOR POLICY QAS-STD-10091. NO MODIFICATION OR DRILLING TO TOWER STEEL IS ALLOWED IN ANY FORM OR FASHION, CAD-WELDING ON THE TOWER AND/OR IN THE AIR ARE NOT PERMITTED.
2. OMIT INSULATOR WHEN MOUNTING TO TOWER STEEL OR PLATFORM STEEL. USE INSULATORS WHEN ATTACHING TO BUILDING OR SHELTERS.


5 GROUND BAR DETAIL  
SCALE: NOT TO SCALE



SINGLE CONNECTOR AT GROUND BARS




SINGLE CONNECTOR AT STEEL OBJECTS



SINGLE CONNECTOR AT METALLIC/STEEL OBJECTS


8 HARDWARE DETAIL FOR EXTERIOR CONNECTIONS  
SCALE: NOT TO SCALE



NOTES:

1. DO NOT INSTALL CABLE GROUND KIT AT A BEND AND ALWAYS DIRECT GROUND WIRE DOWN TO GROUND BAR.
2. GROUNDING KIT SHALL BE TYPE AND PART NUMBER AS SUPPLIED OR RECOMMENDED BY CABLE MANUFACTURER.
3. WEATHER PROOFING SHALL BE TWO-PART TAPE KIT, COLD SHRINK SHALL NOT BE USED.

6 CABLE GROUND KIT CONNECTION  
SCALE: NOT TO SCALE



7 LUG DETAIL  
SCALE: NOT TO SCALE

575 MOROSGO DRIVE  
ATLANTA, GA 30324-3300

1505 WESTLAKE AVENUE NORTH, SUITE 800  
SEATTLE, WA 98109

1717 S. BOULDER  
SUITE 300  
TULSA, OK 74119  
PH: (918) 587-4630  
www.blgrp.com

AT&T SITE NUMBER: CTL02030

BU #: 806361  
NHV 102 943127

131 MANOR RD  
GUILFORD, CT 06437

EXISTING  
150'-0" MONOPOLE

ISSUED FOR:

REV	DATE	DRWN	DESCRIPTION	DES./QA
A	4/14/22	JTS	PRELIMINARY REVIEW	KT
0	5/27/22	KT	CONSTRUCTION	KT
1	6/3/22	JTS	CONSTRUCTION	KT



6/3/22

B&T ENGINEERING, INC.  
PEC.0001564  
Expires 2/10/23


IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.


SHEET NUMBER:


G-2


REVISION:

1









PARTS LIST						
ITEM	QTY	PART NO.	PART DESCRIPTION	LENGTH	UNIT WT.	NET WT.
1	2	SCX4	CROSSOVER PLATE	8 1/2 in	6.02	12.04
2	16	G12FW	1/2" HDG USS FLATWASHER		0.03	0.55
3	16	G12LW	1/2" HDG LOCKWASHER		0.01	0.22
4	16	G12NUT	1/2" HDG HEAVY 2H HEX NUT		0.07	1.15
5	4	G12R-8	1/2" x 8" THREADED ROD (HDG.)		0.35	1.41
6	4	X-UB1212	1/2" X 2-1/2" X 4-1/2" X 2" U-BOLT (HDG.)		0.63	2.50
TOTAL WT. #						17.87

**TOLERANCE NOTES**  
 TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:  
 SAWED, SHEARED AND GAS CUT EDGES ( $\pm 0.030"$ )  
 DRILLED AND GAS CUT HOLES ( $\pm 0.030"$ ) - NO CONING OF HOLES  
 LASER CUT EDGES AND HOLES ( $\pm 0.010"$ ) - NO CONING OF HOLES  
 BENDS ARE  $\pm 1/2$  DEGREE  
 ALL OTHER MACHINING ( $\pm 0.030"$ )  
 ALL OTHER ASSEMBLY ( $\pm 0.060"$ )

PROPRIETARY NOTE:  
 THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF VALMONT INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT THE CONSENT OF VALMONT INDUSTRIES IS STRICTLY PROHIBITED.

DESCRIPTION		
BACK TO BACK PIPE MOUNT		
CPD NO.	DRAWN BY	ENG. APPROVAL
	CEK 1/17/2013	
CLASS	SUB	DRAWING USAGE
81	03	CUSTOMER
		CHECKED BY
		BMC 1/18/2013

 A valmont COMPANY	Locations: New York, NY Atlanta, GA Los Angeles, CA Plymouth, IN Salem, OR Dallas, TX
	Engineering Support Team: 1-888-753-7446
PART NO.	BBPM-K1
DWG. NO.	BBPM-K1