

10 INDUSTRIAL AVE,  
SUITE 3  
MAHWAH NJ 07430

PHONE: 201.684.0055  
FAX: 201.684.0066



---

June 29, 2021

Members of the Siting Council  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

RE: Notice of Exempt Modification  
61 Moose Hill Road, Guilford, CT, 06437 (aka 79 Moose Hill Road)  
Latitude: 41.26746700  
Longitude: -72.71606000  
T-Mobile Site#: CTNH805A - L600

Dear Ms. Bachman:

T-Mobile currently maintains six (6) antennas at the 108-foot level of the existing 110-foot Monopole at the existing facility at 61 Moose Hill Road (aka 79 Moose Hill Road), in Guilford, CT. The property is owned by Leete Associates Inc. The tower is owned by American Tower. T-Mobile now intends to add three (3) new 600/700 MHz antennas. The new antennas support 5G services and will be installed at the same 108-foot level of the monopole.

**Planned Modifications:**

**Tower:**

Install New:

- (3) APXVAAR24 Antennas
- (3) Radio 4449
- (3) 6x24 Hybrid Cables

Existing to Remain:

- (3) AIR21 KRC118023 B2A B4P Antennas
- (3) AIR21 KRC118023 B2P B4A Antennas
- (3) KRY 112 489/2 TMAs
- (6) 1 5/8" Coax Cables
- (1) 1 1/4" Hybrid Cables

**Ground:**

Install New:

(2) BB6648

To Be Removed:

(1) DUS41

This tower facility was approved by the Siting Council in Docket No. 417 dated October 6, 2011. The proposed modification complies with the approval.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies§ 16- SOj-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.SA. § 16-SOj-73, a copy of this letter is being sent to First Selectman Matthew Hoey, Elected Official, and George Kral, Town Planner, as well as the property owner and tower owner.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S;A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, T-Mobile respectfully submits that the proposed modifications to the above referenced telecommunications facility constitute an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

**Eric Breun**

Transcend Wireless

Cell: 201-658-7728

Email: [ebreun@transcendwireless.com](mailto:ebreun@transcendwireless.com)

Attachments

cc: Matthew Hoey – as First Selectman of Guilford

George Kral - Town Planner


American Tower - Tower Owner

Leete Associates Inc - Property Owner

ERIC BREUN  
2016587728  
10 INDUSTRIAL AVE  
MAHWAH NJ 07430

1 LBS 1 OF 1

SHIP TO:  
TOWN PLANNER  
GEORGE KRAL  
50 BOSTON STREET  
**GUILFORD CT 06437**



**UPS GROUND**

TRACKING #: 1Z V25 742 03 9905 4198



BILLING: P/P

Reference #1: CTNH805A

XOL 21.06.14 NV45 260.0A 06/2021\*

ERIC BREUN  
2016587728  
10 INDUSTRIAL AVE  
MAHWAH NJ 07430

1 LBS

SHIP TO:  
AMERICAN TOWER CORPORATION  
10 PRESIDENTIAL WAY  
**WOBBURN MA 01801**



**UPS GROUND**



TRACKING #: 1Z V25 742 03 9566 4189



BILLING: P/P

Reference #1: CTNH805A  
XOL 21.06.14 NV45 260.0A 06/2021\*





## Property Summary Information

Parcel Data And Values

Sales

### Parcel Information

Location:	79 MOOSE HILL RD	Map and Parcel:	066064	Census Tract:	1902
Zoning:	R-8	Developer's Map:		Developer's Lot:	
Total Acreage:	163	Farm, Forest, Open Space Acres:	162	Unique ID:	4101

### Value Information

	Appraised Value	Assessed Value
Land	1,120,373	122,160
Buildings	0	0
Detached Outbuildings	0	0
Total	1,120,373	122,160


### Owner's Information

Owner's Data
LEETE ASSOCIATES INC PO BOX 45 GUILFORD, CT 06437

# Town of Guilford, Connecticut - Assessment Parcel Map

Unique ID: 4101

Address: 79 MOOSE HILL RD



Approximate Scale: 1 inch = 500 feet

0 350 700  
Feet

Map Produced:  
September 2020

## Disclaimer:

This map is for informational purposes only.  
All information is subject to verification by any user.  
The Town of Guilford and its mapping contractors  
assume no legal responsibility  
for the information contained herein.

**DOCKET NO. 417** - T-Mobile Northeast, LLC application for a Certificate of Environmental Compatibility and Public Need for the construction, maintenance and operation of a telecommunications facility located at Moose Hill Road, Guilford, Connecticut. } } }

Connecticut  
Siting  
Council

October 6, 2011

### **Decision and Order**

Pursuant to the foregoing Findings of Fact and Opinion, the Connecticut Siting Council (Council) finds that the effects associated with the construction, maintenance, and operation of a telecommunications facility, including effects on the natural environment; ecological integrity and balance; public health and safety; scenic, historic, and recreational values; forests and parks; air and water purity; and fish and wildlife are not disproportionate, either alone or cumulatively with other effects, when compared to need, are not in conflict with the policies of the State concerning such effects, and are not sufficient reason to deny the application, and therefore directs that a Certificate of Environmental Compatibility and Public Need, as provided by General Statutes § 16-50k, be issued to T-Mobile Northeast, LLC, hereinafter referred to as the Certificate Holder, for a telecommunications facility located off Moose Hill Road (Map 66, Lot 64) in Guilford, Connecticut.

Unless otherwise approved by the Council, the facility shall be constructed, operated, and maintained substantially as specified in the Council's record in this matter, and subject to the following conditions:

1. The tower shall be constructed as a monopole, no taller than necessary to provide the proposed telecommunications services, sufficient to accommodate the antennas of the applicant and other entities, both public and private, but such tower shall not exceed a height of 110 feet above ground level. The height at the top of the Certificate Holder's antennas shall not exceed 110 feet above ground level.
2. The Certificate Holder shall install a tower foundation and tower that is capable of supporting an extension. Any extension of the tower must be approved by the Council.
3. The Certificate Holder shall prepare a Development and Management (D&M) Plan for this site in compliance with Sections 16-50j-75 through 16-50j-77 of the Regulations of Connecticut State Agencies. The D&M Plan shall be served on the Town of Guilford for comment, and all parties and intervenors as listed in the service list, and submitted to and approved by the Council prior to the commencement of facility construction and shall include:
  - a) a final site plan(s) of site development to include specifications for the tower, tower foundation, antennas, equipment compound, radio equipment, access road, utility line, and landscaping;
  - b) construction plans for site clearing, grading, landscaping, water drainage, and erosion and sedimentation controls consistent with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended, and;
  - c) provisions for a contractor awareness program for the Eastern Box Turtle and Wood Turtle.

4. Prior to the commencement of operation, the Certificate Holder shall provide the Council worst-case modeling of the electromagnetic radio frequency power density of all proposed entities' antennas at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin No. 65, August 1997. The Certificate Holder shall ensure a recalculated report of the electromagnetic radio frequency power density be submitted to the Council if and when circumstances in operation cause a change in power density above the levels calculated and provided pursuant to this Decision and Order.
5. Upon the establishment of any new State or federal radio frequency standards applicable to frequencies of this facility, the facility granted herein shall be brought into compliance with such standards.
6. The Certificate Holder shall permit public or private entities to share space on the proposed tower for fair consideration, or shall provide any requesting entity with specific legal, technical, environmental, or economic reasons precluding such tower sharing.
7. The Certificate Holder shall provide reasonable space on the tower for no compensation for any Town of Guilford public safety services (police, fire and medical services), provided such use can be accommodated and is compatible with the structural integrity of the tower.
8. Unless otherwise approved by the Council, if the facility authorized herein is not fully constructed with at least one fully operational wireless telecommunications carrier providing wireless service within eighteen months from the date of the mailing of the Council's Findings of Fact, Opinion, and Decision and Order (collectively called "Final Decision"), this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made. The time between the filing and resolution of any appeals of the Council's Final Decision shall not be counted in calculating this deadline. Authority to monitor and modify this schedule, as necessary, is delegated to the Executive Director. The Certificate Holder shall provide written notice to the Executive Director of any schedule changes as soon as is practicable.
9. Any request for extension of the time period referred to in Condition 8 shall be filed with the Council not later than 60 days prior to the expiration date of this Certificate and shall be served on all parties and intervenors, as listed in the service list, and the Town of Guilford. Any proposed modifications to this Decision and Order shall likewise be so served.
10. If the facility ceases to provide wireless services for a period of one year, this Decision and Order shall be void, and the Certificate Holder shall dismantle the tower and remove all associated equipment or reapply for any continued or new use to the Council before any such use is made.
11. Any nonfunctioning antenna, and associated antenna mounting equipment, on this facility shall be removed within 60 days of the date the antenna ceased to function.
12. In accordance with Section 16-50j-77 of the Regulations of Connecticut State Agencies, the Certificate Holder shall provide the Council with written notice two weeks prior to the commencement of site construction activities. In addition, the Certificate Holder shall provide the Council with written notice of the completion of site construction, and the commencement of site operation.

13. The Certificate Holder shall remit timely payments associated with annual assessments and invoices submitted by the Council for expenses attributable to the facility under Conn. Gen. Stat. §16-50v.
14. This Certificate may be transferred in accordance with Conn. Gen. Stat. §16-50k(b), provided both the Certificate Holder/transferor and the transferee are current with payments to the Council for their respective annual assessments and invoices under Conn. Gen. Stat. §16-50v. In addition, both the Certificate Holder/transferor and the transferee shall provide the Council a written agreement as to the entity responsible for any quarterly assessment charges under Conn. Gen. Stat. §16-50v(b)(2) that may be associated with this facility.
15. The Certificate Holder shall maintain the facility and associated equipment, including but not limited to, the tower, tower foundation, antennas, equipment compound, radio equipment, access road, utility line and landscaping in a reasonable physical and operational condition that is consistent with this Decision and Order and a Development and Management Plan to be approved by the Council.
16. If the Certificate Holder is a wholly-owned subsidiary of a corporation or other entity and is sold/transferred to another corporation or other entity, the Council shall be notified of such sale and/or transfer and of any change in contact information for the individual or representative responsible for management and operations of the Certificate Holder within 30 days of the sale and/or transfer.

Pursuant to General Statutes § 16-50p, the Council hereby directs that a copy of the Findings of Fact, Opinion, and Decision and Order be served on each person listed below, and notice of issuance shall be published in the *New Haven Register*.

By this Decision and Order, the Council disposes of the legal rights, duties, and privileges of each party named or admitted to the proceeding in accordance with Section 16-50j-17 of the Regulations of Connecticut State Agencies.


The parties and intervenors to this proceeding are:

**Applicant**

T-Mobile Northeast LLC

**Its Representative**

Julie D. Kohler, Esq.  
Jesse A. Langer, Esq.  
Cohen and Wolf, P.C.  
1115 Broad Street  
Bridgeport, CT 06604



VICINITY MAP



**AMERICAN TOWER®**

ATC SITE NAME: GUILFORD CT

ATC SITE NUMBER: 284988

T-MOBILE SITE NAME: AMTRAK\_GUILFORD

T-MOBILE SITE NUMBER: CTNH805A

SITE ADDRESS: 61 MOOSE HILL ROAD  
GUILFORD, CONNECTICUT,  
06437

### T-MOBILE L600 ANTENNA AMENDMENT PLAN 67D92C OUTDOOR CONFIGURATION



LOCATION MAP

**Kimley » Horn**

COA: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601


REV.	DESCRIPTION	BY	DATE
▲	PRELIM	SM	04/16/21
○	ISSUED FOR CONSTRUCTION	CW	06/23/21
△			
△			
△			

ATC SITE NUMBER:  
**284988**

ATC SITE NAME:  
**GUILFORD CT**

T-MOBILE SITE NAME:  
**AMTRAK\_GUILFORD**

SITE ADDRESS:  
61 MOOSE HILL ROAD  
GUILFORD, CONNECTICUT, 06437



**T-Mobile**

DATE DRAWN:	06/23/21
ATC JOB NO:	13660479
CUSTOMER ID:	AMTRAK_GUILFORD
CUSTOMER #:	CTNH805A

### TITLE SHEET

SHEET NUMBER:	REVISION:
<b>G-001</b>	<b>0</b>



Call Before You Dig, Inc.



**Kimley » Horn**

COA: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

#### GENERAL CONSTRUCTION NOTES:

1. OWNER FURNISHED MATERIALS, T-MOBILE "THE COMPANY" WILL PROVIDE AND THE CONTRACTOR WILL INSTALL
  - A. BTS EQUIPMENT FRAME (PLATFORM) AND ICEBRIDGE SHELTER (GROUND BUILD/CO-Locate ONLY)
  - B. ACTELCO INTERFACE BOX (PPC)
  - C. ICE BRIDGE (CABLE TRAY WITH COVER) (GROUND BUILD/CO-Locate ONLY, GC TO FURNISH AND INSTALL FOR ROOFTOP INSTALLATION)
  - D. TOWERS, MONOPOLES
  - E. TOWER LIGHTING
  - F. GENERATORS & LIQUID PROPANE TANK
  - G. ANTENNA STANDARD BRACKETS, FRAMES AND PIPES FOR MOUNTING
  - H. ANTENNAS (INSTALLED BY OTHERS)
  - I. TRANSMISSION LINE
  - J. TRANSMISSION LINE JUMPERS
  - K. TRANSMISSION LINE CONNECTORS WITH WEATHERPROOFING KITS
  - L. TRANSMISSION LINE GROUND KITS
  - M. HANGERS
  - N. HOISTING GRIPS
  - O. BTS EQUIPMENT
2. THE CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL OTHER MATERIALS FOR THE COMPLETE INSTALLATION OF THE SITE INCLUDING, BUT NOT LIMITED TO, SUCH MATERIALS AS FENCING, STRUCTURAL STEEL SUPPORTING SUB-FRAME FOR PLATFORM, ROOFING LABOR AND MATERIALS, GROUNDRING RINGS, GROUNDRING WIRES, COPPER-CLAD OR XIT CHEMICAL GROUND ROD(S), BUSS BARS, TRANSFORMERS AND DISCONNECT SWITCHES WHERE APPLICABLE, TEMPORARY ELECTRICAL POWER, CONDUIT, LANDSCAPING, COMPOUND STONE, CRANES, CORE DRILLING, SLEEPERS AND RUBBER MATTING, REBAR, CONCRETE CAISSENS, PADS AND/OR AUGER MOUNTS, MISCELLANEOUS FASTENERS, CABLE TRAYS, NON-STANDARD ANTENNA FRAMES AND ALL OTHER MATERIAL AND LABOR REQUIRED TO COMPLETE THE JOB ACCORDING TO THE DRAWINGS AND SPECIFICATIONS. IT IS THE POSITION OF T-MOBILE TO APPLY FOR PERMITTING AND CONTRACTOR RESPONSIBLE FOR PICKUP AND PAYMENT OF REQUIRED PERMITS.
3. ALL WORK SHALL CONFORM TO ALL CURRENT APPLICABLE FEDERAL, STATE, AND LOCAL CODES, INCLUDING ANSI/EIA/TIA-222, AND COMPLY WITH ATC CONSTRUCTION SPECIFICATIONS.
4. CONTRACTOR SHALL CONTACT LOCAL 811 FOR IDENTIFICATION OF UNDERGROUND UTILITIES PRIOR TO START OF CONSTRUCTION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED INSPECTIONS.
6. ALL DIMENSIONS TO, OF, AND ON EXISTING BUILDINGS, DRAINAGE STRUCTURES, AND SITE IMPROVEMENTS SHALL BE VERIFIED IN FIELD BY CONTRACTOR WITH ALL DISCREPANCIES REPORTED TO THE ENGINEER.
7. DO NOT CHANGE SIZE OR SPACING OF STRUCTURAL ELEMENTS.
8. DETAILS SHOWN ARE TYPICAL; SIMILAR DETAILS APPLY TO SIMILAR CONDITIONS UNLESS OTHERWISE NOTED.
9. THESE DRAWINGS DO NOT INCLUDE NECESSARY COMPONENTS FOR CONSTRUCTION SAFETY WHICH SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
10. CONTRACTOR SHALL BRACE STRUCTURES UNTIL ALL STRUCTURAL ELEMENTS NEEDED FOR STABILITY ARE INSTALLED. THESE ELEMENTS ARE AS FOLLOWS: LATERAL BRACING, ANCHOR BOLTS, ETC.
11. CONTRACTOR SHALL DETERMINE EXACT LOCATION OF EXISTING UTILITIES, GROUNDS DRAINS, DRAIN PIPES, VENTS, ETC. BEFORE COMMENCING WORK.
12. INCORRECTLY FABRICATED, DAMAGED, OR OTHERWISE MISFITTING OR NONCONFORMING MATERIALS OR CONDITIONS SHALL BE REPORTED TO THE T-MOBILE REP PRIOR TO REMEDIAL OR CORRECTIVE ACTION. ANY SUCH REMEDIAL ACTION SHALL REQUIRE WRITTEN APPROVAL BY THE T-MOBILE REP PRIOR TO PROCEEDING.
13. EACH CONTRACTOR SHALL COOPERATE WITH THE T-MOBILE REP, AND COORDINATE HIS WORK WITH THE WORK OF OTHERS.
14. CONTRACTOR SHALL REPAIR ANY DAMAGE CAUSED BY CONSTRUCTION OF THIS PROJECT TO MATCH EXISTING PRE-CONSTRUCTION CONDITIONS TO THE SATISFACTION OF THE T-MOBILE CONSTRUCTION MANAGER.
15. ALL CABLE/CONDUIT ENTRY/EXIT PORTS SHALL BE WEATHERPROOFED DURING INSTALLATION USING A SILICONE SEALANT.
16. WHERE EXISTING CONDITIONS DO NOT MATCH THOSE SHOWN IN THIS PLAN SET, CONTRACTOR SHALL NOTIFY THE T-MOBILE REP AND ENGINEER OF RECORD IMMEDIATELY.
17. CONTRACTOR SHALL ENSURE ALL SUBCONTRACTORS ARE PROVIDED WITH A COMPLETE AND CURRENT SET OF DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT.
18. CONTRACTOR SHALL REMOVE ALL RUBBISH AND DEBRIS FROM THE SITE AT THE END OF EACH DAY.
19. CONTRACTOR SHALL COORDINATE WORK SCHEDULE WITH AMERICAN TOWER CORPORATION (ATC) AND TAKE PRECAUTIONS TO MINIMIZE IMPACT AND DISRUPTION OF OTHER OCCUPANTS OF THE FACILITY.
20. CONTRACTOR SHALL FURNISH T-MOBILE AND AMERICAN TOWER CORPORATION (ATC) WITH A PDF MARKED UP AS-BUILT SET OF DRAWINGS UPON COMPLETION OF WORK.
21. PRIOR TO SUBMISSION OF BID, CONTRACTOR SHALL COORDINATE WITH T-MOBILE REP TO DETERMINE WHAT, IF ANY, ITEMS WILL BE PROVIDED. ALL ITEMS NOT PROVIDED SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR. CONTRACTOR WILL INSTALL ALL ITEMS PROVIDED.
22. PRIOR TO SUBMISSION OF BID, CONTRACTOR SHALL COORDINATE WITH T-MOBILE REP TO DETERMINE IF ANY PERMITS WILL BE OBTAINED BY CONTRACTOR. ALL REQUIRED PERMITS NOT OBTAINED BY T-MOBILE MUST BE OBTAINED, AND PAID FOR, BY THE CONTRACTOR.
23. CONTRACTOR SHALL INSTALL ALL SITE SIGNAGE IN ACCORDANCE WITH T-MOBILE SPECIFICATIONS AND REQUIREMENTS.
24. CONTRACTOR SHALL SUBMIT ALL SHOP DRAWINGS TO T-MOBILE FOR REVIEW AND APPROVAL PRIOR TO FABRICATION.
25. ALL EQUIPMENT SHALL BE INSTALLED ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND LOCATED ACCORDING TO T-MOBILE SPECIFICATIONS, AND AS SHOWN IN THESE PLANS.
26. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE PROJECT DESCRIBED HEREIN. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT.
27. CONTRACTOR SHALL NOTIFY T-MOBILE REP A MINIMUM OF 48 HOURS IN ADVANCE OF POURING CONCRETE OR BACKFILLING ANY UNDERGROUND UTILITIES, FOUNDATIONS OR SEALING ANY WALL, FLOOR OR ROOF PENETRATIONS FOR ENGINEERING REVIEW AND APPROVAL.
28. CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SAFETY INCLUDING COMPLIANCE WITH ALL APPLICABLE OSHA STANDARDS AND RECOMMENDATIONS AND SHALL PROVIDE ALL NECESSARY SAFETY DEVICES INCLUDING PPE AND PPM AND CONSTRUCTION DEVICES SUCH AS WELDING AND FIRE PREVENTION, TEMPORARY SHORING, SCAFFOLDING, TRENCH BOXES/SLOPING, BARRIERS, ETC.
29. THE CONTRACTOR SHALL PROTECT AT HIS OWN EXPENSE, ALL EXISTING FACILITIES AND SUCH OF HIS NEW WORK LIABLE TO INJURY DURING THE CONSTRUCTION PERIOD. ANY DAMAGE CAUSED BY NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, OR BY THE ELEMENTS DUE TO NEGLECT ON THE PART OF THIS CONTRACTOR OR HIS REPRESENTATIVES, EITHER TO THE EXISTING WORK, OR TO HIS WORK OR THE WORK OF ANY OTHER CONTRACTOR, SHALL BE REPAIRED AT HIS EXPENSE TO THE OWNER'S SATISFACTION.
30. ALL WORK SHALL BE INSTALLED IN A FIRST CLASS, NEAT AND WORKMANLIKE MANNER BY MECHANICS SKILLED IN THE TRADE INVOLVED. THE QUALITY OF WORKMANSHIP SHALL BE SUBJECT TO THE APPROVAL OF THE T-MOBILE REP. ANY WORK FOUND BY THE T-MOBILE REP TO BE OF INFERIOR QUALITY AND/OR WORKMANSHIP SHALL BE REPLACED AND/OR REWORKED AT CONTRACTOR EXPENSE UNTIL APPROVAL IS OBTAINED.
31. IN ORDER TO ESTABLISH STANDARDS OF QUALITY AND PERFORMANCE, ALL TYPES OF MATERIALS LISTED HEREINAFTER BY MANUFACTURER'S NAMES AND/OR MANUFACTURER'S CATALOG NUMBER SHALL BE PROVIDED BY THESE MANUFACTURERS AS SPECIFIED.
32. T-MOBILE FURNISHED EQUIPMENT SHALL BE PICKED-UP AT THE T-MOBILE WAREHOUSE, NO LATER THAN 48HR AFTER BEING NOTIFIED INSURED, STORED, UNCRATE, PROTECTED AND INSTALLED BY THE CONTRACTOR WITH ALL APPURTENANCES REQUIRED TO PLACE THE EQUIPMENT IN OPERATION, READY FOR USE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE EQUIPMENT AFTER PICKING IT UP.
33. T-MOBILE OR HIS ARCHITECT/ENGINEER RESERVES THE RIGHT TO REJECT ANY EQUIPMENT OR MATERIALS WHICH, IN HIS OWN OPINION ARE NOT IN COMPLIANCE WITH THE CONTRACT DOCUMENTS, EITHER BEFORE OR AFTER INSTALLATION AND THE EQUIPMENT SHALL BE REPLACED WITH EQUIPMENT CONFORMING TO THE REQUIREMENTS OF THE CONTRACT DOCUMENTS BY THE CONTRACTOR AT NO COST TO T-MOBILE OR THEIR ARCHITECT/ENGINEER.

#### SPECIAL CONSTRUCTION

##### ANTENNA INSTALLATION NOTES:

1. WORK INCLUDED:
  - A. ANTENNA AND COAXIAL CABLES ARE FURNISHED BY T-MOBILE UNDER A SEPARATE CONTRACT. THE CONTRACTOR SHALL ASSIST ANTENNA INSTALLATION CONTRACTOR IN TERMS OF COORDINATION AND SITE ACCESS. ERECTION SUBCONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF PERSONNEL.
  - B. INSTALL ANTENNA AS INDICATED ON DRAWINGS AND T-MOBILE SPECIFICATIONS.
  - C. INSTALL GALVANIZED STEEL ANTENNA MOUNTS AS INDICATED ON DRAWINGS.
  - D. INSTALL FURNISHED GALVANIZED STEEL OR ALUMINUM WAVEGUIDE.
  - E. CONTRACTOR SHALL PROVIDE FOUR (4) SETS OF SWEEP TESTS USING ANRITZU-PACKARD 8713B RF SCALAR NETWORK ANALYZER. SUBMIT FREQUENCY DOMAIN REFLECTOMETER(FDR) TESTS RESULTS TO THE PROJECT MANAGER. SWEEP TESTS SHALL BE AS PER ATTACHED RFS "MINIMUM FIELD TESTING RECOMMENDED FOR ANTENNA AND HELIAX COAXIAL CABLE SYSTEMS" DATED 10/5/93. TESTING SHALL BE PERFORMED BY AN INDEPENDENT TESTING SERVICE AND BE BOUND AND SUBMITTED WITHIN ONE WEEK OF WORK COMPLETION.
  - F. INSTALL COAXIAL CABLES AND TERMINATING BETWEEN ANTENNAS AND EQUIPMENT PER MANUFACTURER'S RECOMMENDATIONS. WEATHERPROOF ALL CONNECTIONS BETWEEN THE ANTENNA AND EQUIPMENT PER MANUFACTURER'S REQUIREMENTS. TERMINATE ALL COAXIAL CABLE THREE (3) FEET IN EXCESS OF ENTRY PORT LOCATION UNLESS OTHERWISE STATED.
  - G. ANTENNA AND COAXIAL CABLE GROUNDING:
    - i. ALL EXTERIOR #6 GREEN GROUND WIRE "DAISY CHAIN" CONNECTIONS ARE TO BE WEATHER SEALED WITH RFS CONNECTORS/SPICE WEATHERPROOFING KIT #22123 OR EQUAL.
    - ii. ALL COAXIAL CABLE GROUNDING KITS ARE TO BE INSTALLED ON STRAIGHT RUNS OF COAXIAL CABLE (NOT WITHIN BENDS).

ALL DISCREPANCIES FROM WHAT IS SHOWN ON THESE CONSTRUCTION DRAWINGS SHALL BE COMMUNICATED TO ATC ENGINEERING IMMEDIATELY FOR CORRECTION OR RE-DESIGN. FAILURE TO COMMUNICATE DIRECTLY WITH ATC ENGINEERING OR ANY CHANGES FROM THE DESIGN CONDUCTED WITHOUT PRIOR APPROVAL FROM ATC ENGINEERING SHALL BE THE SOLE RESPONSIBILITY OF THE GENERAL CONTRACTOR.

#### GENERAL NOTES


SHEET NUMBER:	REVISION:
G-002	0

**T-Mobile**

DATE DRAWN:	06/23/21
ATC JOB NO:	13660479
CUSTOMER ID:	AMTRAK_GUILFORD
CUSTOMER #:	CTNH805A

#### GENERAL NOTES


SHEET NUMBER:	REVISION:
G-002	0



SITE PLAN NOTES:

1. THIS SITE PLAN REPRESENTS THE BEST PRESENT KNOWLEDGE AVAILABLE TO THE ENGINEER AT THE TIME OF THIS DESIGN. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO CONSTRUCTION AND VERIFY ALL EXISTING CONDITIONS RELATED TO THE SCOPE OF WORK FOR THIS PROJECT.
2. ICE BRIDGE, CABLE LADDER, COAX PORT, AND COAX CABLE ARE SHOWN FOR REFERENCE ONLY. CONTRACTOR SHALL CONFIRM THE EXACT LOCATION OF ALL PROPOSED AND EXISTING EQUIPMENT AND STRUCTURES DEPICTED ON THIS PLAN. BEFORE UTILIZING EXISTING CABLE SUPPORTS, COAX PORTS, INSTALLING NEW PORTS OR ANY OTHER EQUIPMENT, CONTRACTOR SHALL VERIFY ALL ASPECTS OF THE COMPONENTS MEET THE ATC SPECIFICATIONS.
3. NO ELECTRICAL SCOPE IS INCLUDED IN THIS PROJECT.

LEGEND	
ATS	GROUNDING TEST WELL
B	AUTOMATIC TRANSFER SWITCH
CSC	BOLLARD
D	CELL SITE CABINET
E	DISCONNECT
F	ELECTRICAL
GEN	FIBER
G	GENERATOR
HH, V	GENERATOR RECEPTACAL
IB	HAND HOLE, VAULT
K	ICE BRIDGE
LC	KENTROX BOX
M	LIGHTING CONTROL
PB	METER
PP	PULL BOX
T	POWER POLE
TRN	TELCO
	TRANSFORMER
	CHAINLINK FENCE



**PROPOSED CABLE LENGTH:**

1. ESTIMATED LENGTH OF PROPOSED CABLE IS **251'**. ESTIMATED LENGTH OF CABLE WAS PROVIDED BY CUSTOMER OR CALCULATED BY ADDING THE RAD CENTER AND THE DISTANCE FROM THE SHELTER ENTRY PLATE TO THE TOWER (ALONG THE ICE BRIDGE) AND A SAFETY FACTOR MEASUREMENT OF 15% (OF THE TWO PREVIOUS VALUES), CDS DEFER TO GREATEST CABLE LENGTH.
2. ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. IF ADEQUATE SPACE EXISTS, ROUTE CABLES THROUGH ENTRY PORT HOLE, UP INSIDE OF MONOPOLE, AND THROUGH EXIT PORT HOLE. IF ROUTING OUTSIDE THE MONOPOLE, ATTACH CABLES USING STAND-OFF ADAPTERS MOUNTED TO TOWER USING STAINLESS STEEL BANDING. ADEQUATELY SECURE CABLES USING EITHER APPROPRIATELY SIZED STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY CABLE MANUFACTURER.

1 DETAILED SITE PLAN  
0 10' 20'  
SCALE: 1"=10' (11X17)  
1"=5' (22X34)



COA: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

REV. DESCRIPTION BY DATE  
A PRELIM SM 04/16/21  
0 ISSUED FOR CONSTRUCTION CW 06/23/21  
△  
△  
△

ATC SITE NUMBER:  
**284988**

ATC SITE NAME:  
**GUILFORD CT**  
T-MOBILE SITE NAME:  
**AMTRAK\_GUILFORD**

SITE ADDRESS:  
61 MOOSE HILL ROAD  
GUILFORD, CONNECTICUT, 06437



DATE DRAWN: 06/23/21  
ATC JOB NO: 13660479  
CUSTOMER ID: AMTRAK\_GUILFORD  
CUSTOMER #: CTNH805A



DETAILED SITE PLAN  
SHEET NUMBER: C-101 REVISION: 0



SITE PLAN NOTES:

1. CONTRACTOR TO VERIFY THERE IS NO LIVE AAV FIBER RUNNING THROUGH EXISTING DEAD EQUIPMENT. IF SO, THIS WILL NEED TO BE RERUN THROUGH CONDUIT PRIOR TO REMOVING DEAD 2G (6201 CABS) EQUIPMENT.
2. REMOVE EXISTING 2G CABINETS, AND POWER / TELCO WHIPS ASSOCIATED WITH THE DEAD EQUIPMENT IF APPLICABLE.
3. ALL OPEN PORTS NEED TO BE SEALED / WEATHERPROOFED PROPERLY
4. ALL UNNEEDED / EXCESS EQUIPMENT AND GARBAGE TO BE REMOVED FROM EQUIPMENT AREA. DISPOSE OF MATERIALS PROPERLY OFF SITE.

T-MOBILE CM APPROVAL REQUIRED BEFORE INSTALLING CABINETS



**Kimley » Horn**


COA: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

REV.	DESCRIPTION	BY	DATE
△	PRELIM	SM	04/16/21
○	ISSUED FOR CONSTRUCTION	CW	06/23/21
△			
△			

ATC SITE NUMBER:  
**284988**

ATC SITE NAME:  
**GUILFORD CT**  
T-MOBILE SITE NAME:  
**AMTRAK\_GUILFORD**

SITE ADDRESS:  
61 MOOSE HILL ROAD  
GUILFORD, CONNECTICUT, 06437



**T-Mobile**

DATE DRAWN:	06/23/21
ATC JOB NO:	13660479
CUSTOMER ID:	AMTRAK_GUILFORD
CUSTOMER #:	CTNH805A

DETAILED GROUND  
PLAN

SHEET NUMBER:	REVISION:
<b>C-102</b>	<b>0</b>



Kimley » Horn

COA: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

REV.	DESCRIPTION	BY	DATE
A	PRELIM	SM	04/16/21
0	ISSUED FOR CONSTRUCTION	CW	06/23/21
△			
△			
△			
△			

ATC SITE NUMBER:  
**284988**


ATC SITE NAME:

**GUILFORD CT**

T-MOBILE SITE NAME:

**AMTRAK\_GUILFORD**SITE ADDRESS:  
61 MOOSE HILL ROAD  
GUILFORD, CONNECTICUT, 06437**T-Mobile**

DATE DRAWN:	06/23/21
ATC JOB NO:	13660479
CUSTOMER ID:	AMTRAK_GUILFORD
CUSTOMER #:	CTNH805A

**TOWER ELEVATION****TOWER NOTE:**

1. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONFIRM WITH THE PROJECT MANAGER THAT THEY HAVE THE MOST RECENT VERSION OF THE STRUCTURAL ANALYSIS BEFORE COMMENCING WORK. EXISTING AND PROPOSED TOWER APPURTENANCES, MOUNTS, AND ANTENNAS ARE SHOWN BASED ON THE STRUCTURAL ANALYSIS.
2. WHERE APPLICABLE, ALL NEW ANTENNAS, EQUIPMENT, MOUNTS, CABLING, ETC. SHALL BE PAINTED/SOCKED TO MATCH EXISTING EQUIPMENT IN ACCORDANCE WITH FAA, JURISDICTION, AND/OR OTHER LOCAL REQUIREMENTS.
3. ROUTE PROPOSED CABLES ALONG SAME PATH AS EXISTING CABLES AND IN ACCORDANCE WITH STRUCTURAL ANALYSIS. IF ADEQUATE SPACE EXISTS, ROUTE CABLES THROUGH ENTRY PORT HOLE, UP INSIDE OF MONOPOLE, AND THROUGH EXIT PORT HOLE. IF ROUTING OUTSIDE THE MONOPOLE, ATTACH CABLES USING STAND-OFF ADAPTERS MOUNTED TO TOWER USING STAINLESS STEEL BANDING. ADEQUATELY SECURE CABLES USING EITHER APPROPRIATELY SIZED STAINLESS STEEL SNAP-INS OR MOUNTING HARDWARE AND BRACKETS AS SPECIFIED BY CABLE MANUFACTURER.
4. TOWER ELEVATIONS ARE MEASURED FROM TOP OF BASE PLATE TO MATCH STRUCTURAL ANALYSIS. ELEVATIONS DO NOT REFLECT TRUE ABOVE GROUND LEVEL (A.G.L.)

SHEET NUMBER:	C-201
REVISION:	0





# Kimley » Horn

COA: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

REV.	DESCRIPTION	BY	DATE
A	PRELIM	SM	04/16/21
0	ISSUED FOR CONSTRUCTION	CW	06/23/21
△			
△			
△			

ATC SITE NUMBER:  
**284988**

ATC SITE NAME:  
**GUILFORD CT**  
T-MOBILE SITE NAME:  
**AMTRAK\_GUILFORD**

SITE ADDRESS:  
61 MOOSE HILL ROAD  
GUILFORD, CONNECTICUT, 06437




# T-Mobile

DATE DRAWN:	06/23/21
ATC JOB NO:	13660479
CUSTOMER ID:	AMTRAK_GUILFORD
CUSTOMER #:	CTNH805A


## CONSTRUCTION DETAILS

SHEET NUMBER:	C-501
REVISION:	0




1 PROPOSED ANTENNA MOUNTING DETAIL - TYPICAL

SCALE: N.T.S.




2 PROPOSED 5G ANTENNA MOUNTING DETAIL - TYPICAL

SCALE: N.T.S.



3 PROPOSED RRU MOUNTING DETAIL - TYPICAL

SCALE: N.T.S.



NOTE:

INSTALL HILTI KWIK BOLT ANCHORS STRICTLY PER INSTALLATION INSTRUCTIONS INCLUDED WITH PRODUCT OR FOUND ONLINE AT WWW.US.HILTI.COM. PROPER INSTALLATION IS CRITICAL FOR FULL PERFORMANCE.

4 CABINET ATTACHMENT DETAIL

SCALE: NOT TO SCALE



**Kimley » Horn**


COA: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

REV.	DESCRIPTION	BY	DATE
A	PRELIM	SM	04/16/21
0	ISSUED FOR CONSTRUCTION	CW	06/23/21
△			
△			
△			

ATC SITE NUMBER:  
**284988**

ATC SITE NAME:  
**GUILFORD CT**  
T-MOBILE SITE NAME:  
**AMTRAK\_GUILFORD**

SITE ADDRESS:  
61 MOOSE HILL ROAD  
GUILFORD, CONNECTICUT, 06437




**T-Mobile**

DATE DRAWN:	06/23/21
ATC JOB NO:	13660479
CUSTOMER ID:	AMTRAK_GUILFORD
CUSTOMER #:	CTNH805A


#### GROUNDING DETAILS

SHEET NUMBER:	E-501
REVISION:	0




1 TYPICAL ANTENNA GROUNDING DIAGRAM

SCALE: N.T.S.



2 CABLE GROUND KIT CONNECTION DETAIL

SCALE: N.T.S.




3 TOWER GROUND BAR DETAIL

SCALE: N.T.S.

#### ELECTRICAL NOTES:

1. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WITH THE T-MOBILE REPRESENTATIVE AND LOCAL UTILITY COMPANY FOR THE INSTALLATION OF CONDUITS, CONDUCTORS, BREAKERS, DISCONNECTS, OR ANY OTHER EQUIPMENT REQUIRED FOR ELECTRICAL SERVICE. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH LATEST EDITION OF THE STATE AND NATIONAL CODES, ORDINANCES AND REGULATIONS APPLICABLE TO THIS PROJECT.
2. ATC HAS NOT VERIFIED ANY EXISTING T-MOBILE GROUND EQUIPMENT OR ELECTRICAL LOADING. PROPOSED WORK BASED ON INSTALLATION CONFIGURATION PROVIDED BY T-MOBILE. CONTRACTOR TO VERIFY EXISTING T-MOBILE PANEL HAS SUFFICIENT SPACE FOR PROPOSED BREAKER. PROPOSED CABLE AND CONDUIT SHALL BE MINIMUM SIZE PER BELOW IN CHART.
3. FOR SPECIFIC CABINET / ANCILLARY EQUIPMENT WIRING REQUIREMENTS, THE T-MOBILE CONTRACTOR SHOULD REFERENCE DESIGN DOCUMENTS PROVIDED BY T-MOBILE FOR THIS CURRENT PROJECT CONFIGURATION, IN ACCORDANCE WITH LOCAL JURISDICTION REQUIREMENTS & NEC STANDARDS & PRACTICES.

OCPD SIZE	WIRE SIZE	GROUND SIZE	CONDUIT SIZE
80A/2P	2#3 AWG	#8 AWG	1-1/4"
100/2P	2#2 AWG	#8 AWG	1-1/4"
125A/2P	2#1 AWG	#8 AWG	1-1/2"
150A/2P	2#1/0 AWG	#8 AWG	1-1/2"



4 CABINET GROUNDING DETAIL

SCALE: N.T.S.

**Section 5 - RAN Equipment**

**Existing RAN Equipment**  
Template: 95A

Enclosure	1
Enclosure Type	RBS 6131
Baseband	DUW30 U2100 DUG20 G1900 DUS41 L1900 L2100
Radio	RU22 (x 6) U2100


**Proposed RAN Equipment**  
Template: 67D92C Outdoor

Enclosure	1
Enclosure Type	RBS 6131
Baseband	DUW30 U2100 DUG20 G1900 BB 6648 L1900 L2100 N600 L700 L600
Hybrid Cable System	Ericsson Hybrid Trunk 6/24 4AWG 100m (x 3)
Radio	RU22 (x 6) U2100

**RAN Scope of Work:**

- Replace(1) DUS41 with (1) BB6648 for L2100, L700, and L600.
- Add (1) BB6648 for 5G N600.
- Add (3) 6x24 HCS.
- Existing: (6) 1-5/8" Coaxial Lines; (1) HCS

1 CABINET CONFIGURATION  
SCALE: NOT TO SCALE







2 ANTENNA CONFIGURATION  
SCALE: NOT TO SCALE

NOTE: THIS SHEET CREATED BY OTHERS AND PROVIDED  
BY REQUEST OF CUSTOMER WITHOUT EDIT.

SUPPLEMENTAL

SHEET NUMBER: <b>R-601</b>	REVISION: <b>0</b>
-------------------------------	-----------------------

FRONT VIEWTOP VIEWFRONT VIEWTOP VIEW

**1 ANTENNA SPECIFICATIONS**  
FOR ILLUSTRATIVE PURPOSES ONLY - NOT TO SCALE

ANTENNA SPECIFICATIONS				
ANTENNA MODEL	A	B	C	WEIGHT (LBS)
APXVAARR24_43-U-NA20	95.9"	24.0"	8.7"	127.9

**2 RRU SPECIFICATIONS**  
FOR ILLUSTRATIVE PURPOSES ONLY - NOT TO SCALE

RRU SPECIFICATIONS				
RRU MODEL	A	B	C	WEIGHT (LBS)
RADIO 4449 B71+B85A	15.0"	13.2"	10.5"	75

SUPPLEMENTAL

SHEET NUMBER: <b>R-602</b>	REVISION: <b>0</b>
-------------------------------	-----------------------



This report was prepared for American Tower Corporation by




## Antenna Mount Analysis Report

**ATC Site Name** : Guilford CT, CT  
**ATC Site Number** : 284988  
**Engineering Number** : 13660479\_C8\_03  
**Mount Elevation** : 108 ft  
**Carrier** : T-Mobile  
**Carrier Site Name** : Amtrak\_Guilford  
**Carrier Site Number** : CTNH805A  
**Site Location** : Moose Hill Rd.  
Guilford, CT 06437  
41.267500, -72.716100  
**County** : New Haven  
**Date** : May 11, 2021  
**Max Usage** : 69%  
**Result** : Pass

Prepared By:  
Sorin Capra  
TEP No. 177168.534968

Reviewed By:  
  
05/11/2021



Eng. Number 13660479\_C8\_03  
May 11, 2021  
Page 1

### Introduction

The purpose of this report is to summarize results of the antenna mount analysis performed for T-Mobile at 108ft.

### Supporting Documents

<b>Spec Sheet</b>	Spec Sheet for SitePro RMQP
<b>Spec Sheet</b>	Spec Sheet for SitePro HRK12-3HD
<b>RFDS</b>	RFDS dated February 16, 2021
<b>Photos</b>	Site photos from 2018

### Analysis

This antenna mount was analyzed using RISA-3D v17 analysis software

<b>Basic Wind Speed:</b>	130 mph (Vult 3-Second Gust)
<b>Basic Wind Speed w/ Ice:</b>	50 mph (Vult 3-Second Gust) w/ 1.0" radial ice
<b>Codes:</b>	ANSI/TIA-222-H
<b>Risk Category:</b>	II
<b>Exposure Category:</b>	C
<b>Topographic Factor Procedure:</b>	Method 2
<b>Kzt:</b>	1.000
<b>Spectral Response:</b>	Ss = 0.202, S1 = 0.053
<b>Site Class:</b>	D – Default
<b>Live Loads:</b>	Lm = 500 lbs, Lv = 250 lbs

### Conclusion

Based on the analysis results, the antenna mount meets the requirements per the applicable codes listed above. The mount can support the equipment as described in this report. Analysis is based on new SitePro RMQP platform mount with SitePro HRK12-3HD handrail kit.

If the load differs from that described in this report or the provisions of this analysis are found to be invalid, another structural analysis should be performed

If you have any questions or require additional information, please contact American Tower via email at [Engineering@americantower.com](mailto:Engineering@americantower.com). Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

## SUPPLEMENTAL

SHEET NUMBER: R-603	REVISION: 0
------------------------	----------------

**DETAIL A**

**PARTS LIST**

ITEM	QTY	PART NO.	PART DESCRIPTION	LENGTH	UNIT WT.	NET WT.	
1	6	X-LWRM	RING MOUNT WELDMENT		68.81	412.85	
2	66	G58LW	5/8" HDG LOCKWASHER		0.03	1.72	
3	60	A58NUT	5/8" HDG A325 HEX NUT		0.13	7.79	
4	18	G58R-24	5/8" x 24" THREADED ROD (HDG.)		2.09	37.63	
4	18	G58R-48	5/8" x 48" THREADED ROD (HDG.)		4.18	75.27	
5	24	A58234	5/8" x 2-3/4" HDG A325 HEX BOLT	2 3/4 in	0.36	8.54	
6	24	A58FW	5/8" HDG A325 FLATWASHER		0.03	0.82	
7	36	X-UB1306	1/2" X 3-5/8" X 6" X 3" U-BOLT (HDG.)		0.83	29.82	
8	264	G12FW	1/2" HDG USS FLATWASHER	3/32 in	0.03	9.00	
9	252	G12LW	1/2" HDG LOCKWASHER	1/8 in	0.01	3.50	
10	252	G12NUT	1/2" HDG HEAVY 2H HEX NUT		0.07	18.05	
11	12	P296	2-3/8" X 96" SCH. 40 GALVANIZED PIPE	96 in	30.76	369.08	
12	84	X-UB1212	1/2" X 2-1/2" X 4-1/2" X 2" U-BOLT (HDG.)		0.60	50.17	
13	3	P3150	3-1/2" X 150" (3" SCH 40) GALVANIZED PIPE	150 in	94.80	284.40	
14	3	X-SV196	LOW PROFILE PLATFORM CORNER		212.10	636.31	
15	3	P2150	2-3/8" O.D. X 150" SCH 40 GALVANIZED PIPE	150 in	45.77	137.31	
16	12	SCX2	CROSSOVER PLATE	7 in	4.80	57.56	
17	15	SCX4	CROSSOVER PLATE	8 1/2 in	6.02	90.32	
18	6	G58NUT	5/8" HDG HEAVY 2H HEX NUT		0.13	0.78	
19	6	X-253993	PLATFORM REINFORCEMENT KIT ANGLE	52 25/32 in	14.33	85.99	
20	6	X-TBW	T-BRACKET WELDMENT		13.60	81.60	
21	6	G5802	5/8" x 2" HDG HEX BOLT GR5		0.27	1.62	
22	12	G12065	1/2" x 6-1/2" HDG HEX BOLT GR5 FULL THREAD	5 1/2 in	0.41	4.91	
23	3	X-AHCP	ANGLE HANDRAIL CORNER PLATE		12.92	38.76	
						TOTAL WT. #	2445.81

**DETAIL C**

**DETAIL B**

**DETAIL D**

**TOLERANCE NOTES**

TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE:  
SAWED, SHEARED AND GAS CUT EDGES ( $\pm 0.030"$ )  
DRILLED AND GAS CUT HOLES ( $\pm 0.030"$ ) - NO CONING OF HOLES  
LASER CUT EDGES AND HOLES ( $\pm 0.010"$ ) - NO CONING OF HOLES  
BENDS ARE  $\pm 1/2$  DEGREE  
ALL OTHER MACHINING ( $\pm 0.030"$ )  
ALL OTHER ASSEMBLY ( $\pm 0.060"$ )

**DESCRIPTION**  
12' 6" LOW PROFILE PLATFORM  
WITH TWELVE 2-3/8" ANTENNA MOUNTING  
PIPES, AND HANDRAIL

**SITE PRO 1**  
A valmont COMPANY

Locations:  
New York, NY  
Atlanta, GA  
Los Angeles, CA  
Plymouth, IN  
Salem, OR  
Dallas, TX

Engineering Support Team:  
1-888-753-7446

CPD NO. 4488 DRAWN BY CEK 7/14/2014 ENG. APPROVAL PART NO. RMQP-496-HK PAGE 3 OF 3

REV DESCRIPTION OF REVISIONS CPD BY DATE CLASS SUB DRAWING USAGE CHECKED BY DWG. NO. RMQP-496-HK


REVISION HISTORY

PROPRIETARY NOTE:  
THE DATA AND TECHNIQUES CONTAINED IN THIS DRAWING ARE PROPRIETARY INFORMATION OF VALMONT INDUSTRIES AND CONSIDERED A TRADE SECRET. ANY USE OR DISCLOSURE WITHOUT THE CONSENT OF VALMONT INDUSTRIES IS STRICTLY PROHIBITED.

SUPPLEMENTAL

SHEET NUMBER: R-604

REVISION: 0



<b>TOLERANCE NOTES</b> TOLERANCES ON DIMENSIONS, UNLESS OTHERWISE NOTED ARE: SAWED, SHEARED AND GAS CUT EDGES ( $\pm 0.030"$ ) DRILLED AND GAS CUT HOLES ( $\pm 0.030"$ ) - NO CONING OF HOLES LASER CUT EDGES AND HOLES ( $\pm 0.010"$ ) - NO CONING OF HOLES BENDS ARE $\pm 1/2$ DEGREE ALL OTHER MACHINING ( $\pm 0.030"$ ) ALL OTHER ASSEMBLY ( $\pm 0.060"$ )	DESCRIPTION HANDRAIL KIT FOR 12' SNUB NOSE PLATFORM			<b>SITE PRO</b> A valmont COMPANY	Locations: New York, NY Atlanta, GA Los Angeles, CA Plymouth, IN Salem, OR Dallas, TX
	CPD NO.	DRAWN BY CEK 4/6/2015	ENG. APPROVAL		
	81	02	DRAWING USAGE CUSTOMER	PART NO. HRA12	PAGE 1 OF 1
			CHECKED BY BMC 4/6/2015	DWG. NO. HRA12	

SUPPLEMENTAL

SHEET NUMBER: <b>R-605</b>	REVISION: <b>0</b>
-------------------------------	-----------------------



This report was prepared for American Tower Corporation by



---

## Antenna Mount Analysis Report

ATC Site Name : Guilford CT, CT  
ATC Site Number : 284988  
Engineering Number : 13660479\_C8\_03  
Mount Elevation : 108 ft  
Carrier : T-Mobile  
Carrier Site Name : Amtrak\_Guilford  
Carrier Site Number : CTNH805A  
Site Location : Moose Hill Rd.  
Guilford, CT 06437  
41.267500, -72.716100  
County : New Haven  
Date : May 11, 2021  
Max Usage : 69%  
Result : Pass

Prepared By:  
Sorin Capra  
TEP No. 177168.534968

Reviewed By:



05/11/2021



## Table of Contents

Introduction.....	1
Supporting Documents.....	1
Analysis.....	1
Conclusion.....	1
Antenna Loading.....	2
Structure Usages.....	2
Mount Layout .....	3
Standard Conditions .....	4
Calculations.....	Attached



## Introduction

The purpose of this report is to summarize results of the antenna mount analysis performed for T-Mobile at 108ft.

## Supporting Documents

Spec Sheet	Spec Sheet for SitePro RMQP
Spec Sheet	Spec Sheet for SitePro HRK12-3HD
RFDS	RFDS dated February 16, 2021
Photos	Site photos from 2018

## Analysis

This antenna mount was analyzed using RISA-3D v17 analysis software

Basic Wind Speed:	130 mph (Vult 3-Second Gust)
Basic Wind Speed w/ Ice:	50 mph (Vult 3-Second Gust) w/ 1.0" radial ice
Codes:	ANSI/TIA-222-H
Risk Category:	II
Exposure Category:	C
Topographic Factor Procedure:	Method 2
Kzt:	1.000
Spectral Response:	Ss = 0.202, S1 = 0.053
Site Class:	D – Default
Live Loads:	Lm = 500 lbs, Lv = 250 lbs

## Conclusion

Based on the analysis results, the antenna mount meets the requirements per the applicable codes listed above. The mount can support the equipment as described in this report. Analysis is based on new SitePro RMQP platform mount with SitePro HRK12-3HD handrail kit.

If the load differs from that described in this report or the provisions of this analysis are found to be invalid, another structural analysis should be performed

If you have any questions or require additional information, please contact American Tower via email at [Engineering@americantower.com](mailto:Engineering@americantower.com). Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

Antenna Loading


Mount Centerline (ft)	Antenna Centerline (ft)	Qty	Antenna Model
108	108	3	RFS APXVAARR24_43-U-NA20
		3	Ericsson AIR 21, 1.3M, B4A B2P
		3	Ericsson AIR 21, 1.3 M, B2A B4P
		3	Ericsson KRY 112 489/2
		3	Ericsson Radio 4449 B71 B85A

Structure Usage

Structural Component	Controlling Usage	Pass/Fail
Face Horizontals	20%	Pass
Support Rail	36%	Pass
Mount Pipes	69%	Pass
Standoff Members	48%	Pass
Grating Members	19%	Pass
Corner Members	59%	Pass
Mount to Tower Connection	54%	Pass



## Mount Layout





### Standard Conditions

All engineering services performed by TEP are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of TEP

It is the responsibility of the client to ensure that the information provided to TEP and used in the performance of our engineering services is correct and complete.

TEP assumes that all structures were constructed in accordance with the drawings and specifications.

TEP assumes that the mount has been maintained in accordance with the manufacturer's specification.

TEP assumes that all mount components are in sufficient condition to carry their full design capacity for this analysis.



Serviceability with respect to antenna twist, tilt, roll, or lateral translation, is not checked and is left to the carrier or tower owner to ensure conformance.

All material grades used for this analysis, unless verified by mount manufacturer design, were assumed per AISC Table 2-4, 15<sup>th</sup> Edition. See RISA 3-D output for confirmation on grades used in this analysis.

All connections are to be verified for condition and tightness by the installation contractor preceding any changes to the appurtenance mounting system and/or equipment attached to it.

Unless explicitly agreed by both the client and TEP, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. TEP is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.



Envelope Only Solution

Tower Engineering Profess...



VAA

TEP No. 177168.534968

SK - 1

May 7, 2021 at 5:16 PM

284988 - GUILFORD CT.r3d



Loads: BLC 2, We  
Envelope Only Solution


Tower Engineering Profess...
VAA
TEP No. 177168.534968

284988 - GUILFORD CT


SK - 2

May 7, 2021 at 5:16 PM

284988 - GUILFORD CT.r3d






Code Check (Env)	
No Calc	
> 1.0	
.90-1.0	
.75-.90	
.50-.75	
0.-.50	



Member Code Checks Displayed (Enveloped)  
Envelope Only Solution

Tower Engineering Profess...  
VAA  
TEP No. 177168.534968

SK - 3  
May 7, 2021 at 5:16 PM  
284988 - GUILFORD CT.r3d





Member Shear Checks Displayed (Enveloped)  
Envelope Only Solution

Tower Engineering Profess...  
VAA  
TEP No. 177168.534968

284988 - GUILFORD CT

SK - 4  
May 7, 2021 at 5:16 PM  
284988 - GUILFORD CT.r3d





Envelope Only Solution

Tower Engineering Profess...  
VAA  
TEP No. 177168.534968

284988 - GUILFORD CT

SK - 5  
May 7, 2021 at 5:16 PM  
284988 - GUILFORD CT.r3d



Envelope Only Solution



Tower Engineering Profess...
VAA
TEP No. 177168.534968

284988 - GUILFORD CT

SK - 6

May 7, 2021 at 5:16 PM

284988 - GUILFORD CT.r3d



Envelope Only Solution

Tower Engineering Profess...
VAA
TEP No. 177168.534968

284988 - GUILFORD CT

SK - 7

May 7, 2021 at 5:16 PM

284988 - GUILFORD CT.r3d



Company : Tower Engineering Professionals, Inc  
 Designer : VAA  
 Job Number : TEP No. 177168.534968  
 Model Name : 284988 - GUILFORD CT

May 7, 2021  
 5:17 PM  
 Checked By: SC

### **(Global) Model Settings**

Display Sections for Member Calcs	5
Max Internal Sections for Member Calcs	97
Include Shear Deformation?	Yes
Increase Nailing Capacity for Wind?	Yes
Include Warping?	Yes
Trans Load Btwn Intersecting Wood Wall?	Yes
Area Load Mesh (in^2)	144
Merge Tolerance (in)	.12
P-Delta Analysis Tolerance	0.50%
Include P-Delta for Walls?	Yes
Automatically Iterate Stiffness for Walls?	Yes
Max Iterations for Wall Stiffness	3
Gravity Acceleration (in/sec^2)	386.4
Wall Mesh Size (in)	24
Eigensolution Convergence Tol. (1.E-)	4
Vertical Axis	Y
Global Member Orientation Plane	XZ
Static Solver	Sparse Accelerated
Dynamic Solver	Accelerated Solver

Hot Rolled Steel Code	AISC 15th(360-16): LRFD
Adjust Stiffness?	Yes(Iterative)
RISAConnection Code	AISC 15th(360-16): LRFD
Cold Formed Steel Code	AISI S100-16: LRFD
Wood Code	None
Wood Temperature	< 100F
Concrete Code	None
Masonry Code	None
Aluminum Code	AA ADM1-15: LRFD - Building
Stainless Steel Code	AISC 14th(360-10): LRFD
Adjust Stiffness?	Yes(Iterative)

Number of Shear Regions	4
Region Spacing Increment (in)	4
Biaxial Column Method	Exact Integration
Parmer Beta Factor (PCA)	.65
Concrete Stress Block	Rectangular
Use Cracked Sections?	Yes
Use Cracked Sections Slab?	No
Bad Framing Warnings?	No
Unused Force Warnings?	Yes
Min 1 Bar Diam. Spacing?	No
Concrete Rebar Set	REBAR SET ASTMA615
Min % Steel for Column	1
Max % Steel for Column	8



Company : Tower Engineering Professionals, Inc  
 Designer : VAA  
 Job Number : TEP No. 177168.534968  
 Model Name : 284988 - GUILFORD CT

May 7, 2021  
 5:17 PM  
 Checked By: SC

### (Global) Model Settings, Continued

Seismic Code	ASCE 7-16
Seismic Base Elevation (in)	Not Entered
Add Base Weight?	Yes
Ct X	.02
Ct Z	.02
T X (sec)	Not Entered
T Z (sec)	Not Entered
R X	3
R Z	3
Ct Exp. X	.75
Ct Exp. Z	.75
SD1	1
SDS	1
S1	1
TL (sec)	5
Risk Cat	I or II
Drift Cat	Other
Om Z	1
Om X	1
Cd Z	4
Cd X	4
Rho Z	1
Rho X	1

### Hot Rolled Steel Properties

Label	E [ksi]	G [ksi]	Nu	Therm (/1E5 F)	Density[k/ft^3]	Yield[ksi]	Ry	Fu[ksi]	Rt
1 A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
2 A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
3 A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
4 A500 Gr.B RND	29000	11154	.3	.65	.527	42	1.4	58	1.3
5 A500 Gr.B Rect	29000	11154	.3	.65	.527	46	1.4	58	1.3
6 A53 Gr.B	29000	11154	.3	.65	.49	35	1.6	60	1.2
7 A1085	29000	11154	.3	.65	.49	50	1.25	65	1.15
8 A913 Gr.65	29000	11154	.3	.65	.49	65	1.1	80	1.1

### Hot Rolled Steel Section Sets

Label	Shape	Type	Design List	Material	Design Ru...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1 HR1A	W10X33	Beam	None	A992	Typical	9.71	36.6	171	.583

### Joint Boundary Conditions

Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-in/rad]	Y Rot.[k-in/rad]	Z Rot.[k-in/rad]
1 N8	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2 N9	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
3 N10	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

### Member Primary Data

Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1 M1	N1	N2			PIPE 3.0	None	None	A53 Gr.B	Typical
2 M2	N3	N4			PIPE 3.0	None	None	A53 Gr.B	Typical
3 M3	N5	N6			PIPE 3.0	None	None	A53 Gr.B	Typical
4 M4	N16	N8			HSS4X4X4	None	None	A500 Gr.B..	Typical
5 M5	N19	N9			HSS4X4X4	None	None	A500 Gr.B..	Typical

### Member Primary Data (Continued)

Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
6	M6	N22	N10		HSS4X4X4	None	None	A500 Gr.B..	Typical
7	M7	N66	N75		FB6x0.37	None	None	A36 Gr.36	Typical
8	M8	N72	N81		FB6x0.37	None	None	A36 Gr.36	Typical
9	M9	N78	N69		FB6x0.37	None	None	A36 Gr.36	Typical
10	M10	N12	N11		PIPE 2.0	None	None	A53 Gr.B	Typical
11	M11	N13	N14		RIGID	None	None	RIGID	Typical
12	M12	N46	N58		HSS4X4X4	None	None	A500 Gr.B..	Typical
13	M13	N16	N15	180	L2x2x3	Beam	None	A36 Gr.36	Typical
14	M14	N16	N17	90	L2x2x3	Beam	None	A36 Gr.36	Typical
15	M15	N54	N42		HSS4X4X4	None	None	A500 Gr.B..	Typical
16	M16	N19	N18	180	L2x2x3	Beam	None	A36 Gr.36	Typical
17	M17	N19	N20	90	L2x2x3	Beam	None	A36 Gr.36	Typical
18	M18	N22	N21	180	L2x2x3	Beam	None	A36 Gr.36	Typical
19	M19	N22	N23	90	L2x2x3	Beam	None	A36 Gr.36	Typical
20	M20	N50	N62		HSS4X4X4	None	None	A500 Gr.B..	Typical
21	M21	N27	N28		PIPE 2.5	None	None	A53 Gr.B	Typical
22	M22	N29	N30		PIPE 2.5	None	None	A53 Gr.B	Typical
23	M23	N31	N32		PIPE 2.5	None	None	A53 Gr.B	Typical
24	M24	N33	N34		RIGID	None	None	RIGID	Typical
25	M25	N41	N36	90	L2.5x2.5x3	Beam	None	A36 Gr.36	Typical
26	M26	N39	N40	90	L2.5x2.5x3	Beam	None	A36 Gr.36	Typical
27	M27	N38	N37	180	L2.5x2.5x3	Beam	None	A36 Gr.36	Typical
28	M28	N44	N45		RIGID	None	None	RIGID	Typical
29	M29	N42	N43		FB6x0.37	Beam	None	A36 Gr.36	Typical
30	M30	N43	N44		FB6x0.37	Beam	None	A36 Gr.36	Typical
31	M31	N48	N49		RIGID	None	None	RIGID	Typical
32	M32	N46	N47		FB6x0.37	Beam	None	A36 Gr.36	Typical
33	M33	N47	N48		FB6x0.37	Beam	None	A36 Gr.36	Typical
34	M34	N52	N53		RIGID	None	None	RIGID	Typical
35	M35	N50	N51		FB6x0.37	Beam	None	A36 Gr.36	Typical
36	M36	N51	N52		FB6x0.37	Beam	None	A36 Gr.36	Typical
37	M37	N56	N57		RIGID	None	None	RIGID	Typical
38	M38	N54	N55		FB6x0.37	Beam	None	A36 Gr.36	Typical
39	M39	N55	N56		FB6x0.37	Beam	None	A36 Gr.36	Typical
40	M40	N60	N61		RIGID	None	None	RIGID	Typical
41	M41	N58	N59		FB6x0.37	Beam	None	A36 Gr.36	Typical
42	M42	N59	N60		FB6x0.37	Beam	None	A36 Gr.36	Typical
43	M43	N64	N65		RIGID	None	None	RIGID	Typical
44	M44	N62	N63		FB6x0.37	Beam	None	A36 Gr.36	Typical
45	M45	N63	N64		FB6x0.37	Beam	None	A36 Gr.36	Typical
46	M46	N66	N67		FB6x0.37	None	None	A36 Gr.36	Typical
47	M47	N67	N68		RIGID	None	None	RIGID	Typical
48	M48	N69	N70		FB6x0.37	None	None	A36 Gr.36	Typical
49	M49	N70	N71		RIGID	None	None	RIGID	Typical
50	M50	N72	N73		FB6x0.37	None	None	A36 Gr.36	Typical
51	M51	N73	N74		RIGID	None	None	RIGID	Typical
52	M52	N75	N76		FB6x0.37	None	None	A36 Gr.36	Typical
53	M53	N76	N77		RIGID	None	None	RIGID	Typical
54	M54	N78	N79		FB6x0.37	None	None	A36 Gr.36	Typical
55	M55	N79	N80		RIGID	None	None	RIGID	Typical
56	M56	N81	N82		FB6x0.37	None	None	A36 Gr.36	Typical
57	M57	N82	N83		RIGID	None	None	RIGID	Typical
58	M58	N87	N86		PIPE 2.0	None	None	A53 Gr.B	Typical
59	M59	N84	N85		PIPE 2.0	None	None	A53 Gr.B	Typical
60	M60	N88	N89		PIPE 2.0	None	None	A53 Gr.B	Typical
61	M61	N91	N90		PIPE 2.0	None	None	A53 Gr.B	Typical
62	M62	N92	N93		RIGID	None	None	RIGID	Typical

**Member Primary Data (Continued)**

Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
63	M63	N94	N95		RIGID	None	None	RIGID	Typical
64	M64	N97	N96		PIPE 2.0	None	None	A53 Gr.B	Typical
65	M65	N98	N99		RIGID	None	None	RIGID	Typical
66	M66	N100	N101		RIGID	None	None	RIGID	Typical
67	M67	N103	N102		PIPE 2.0	None	None	A53 Gr.B	Typical
68	M68	N104	N105		RIGID	None	None	RIGID	Typical
69	M69	N106	N107		RIGID	None	None	RIGID	Typical
70	M70	N109	N108		PIPE 2.0	None	None	A53 Gr.B	Typical
71	M71	N110	N111		RIGID	None	None	RIGID	Typical
72	M72	N112	N113		RIGID	None	None	RIGID	Typical
73	M73	N115	N114		PIPE 2.0	None	None	A53 Gr.B	Typical
74	M74	N116	N117		RIGID	None	None	RIGID	Typical
75	M75	N118	N119		RIGID	None	None	RIGID	Typical
76	M76	N121	N120		PIPE 2.0	None	None	A53 Gr.B	Typical
77	M77	N122	N123		RIGID	None	None	RIGID	Typical
78	M78	N124	N125		RIGID	None	None	RIGID	Typical
79	M79	N127	N126		PIPE 2.0	None	None	A53 Gr.B	Typical
80	M80	N128	N129		RIGID	None	None	RIGID	Typical
81	M81	N130	N131		RIGID	None	None	RIGID	Typical
82	M82	N133	N132		PIPE 2.0	None	None	A53 Gr.B	Typical
83	M83	N134	N135		RIGID	None	None	RIGID	Typical
84	M84	N136	N137		RIGID	None	None	RIGID	Typical
85	M85	N139	N138		PIPE 2.0	None	None	A53 Gr.B	Typical
86	M86	N140	N141		RIGID	None	None	RIGID	Typical
87	M87	N142	N143		RIGID	None	None	RIGID	Typical
88	M88	N145	N144		PIPE 2.0	None	None	A53 Gr.B	Typical
89	M89	N146	N147		RIGID	None	None	RIGID	Typical
90	M90	N148	N149		RIGID	None	None	RIGID	Typical
91	M91	N151	N150		PIPE 2.0	None	None	A53 Gr.B	Typical
92	M92	N152	N153		RIGID	None	None	RIGID	Typical
93	M93	N154	N155		RIGID	None	None	RIGID	Typical

**Member Advanced Data**

Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
1	M1					Yes	** NA **			None
2	M2					Yes	** NA **			None
3	M3					Yes	** NA **			None
4	M4					Yes	** NA **			None
5	M5					Yes	** NA **			None
6	M6					Yes	** NA **			None
7	M7					Yes	** NA **			None
8	M8					Yes	** NA **			None
9	M9					Yes	** NA **			None
10	M10					Yes	** NA **			None
11	M11					Yes	** NA **			None
12	M12					Yes	** NA **			None
13	M13	BenPIN	BenPIN			Yes				None
14	M14	BenPIN	BenPIN			Yes				None
15	M15					Yes	** NA **			None
16	M16	BenPIN	BenPIN			Yes				None
17	M17	BenPIN	BenPIN			Yes				None
18	M18	BenPIN	BenPIN			Yes				None
19	M19	BenPIN	BenPIN			Yes				None
20	M20					Yes	** NA **			None
21	M21					Yes	** NA **			None

**Member Advanced Data (Continued)**

Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
22	M22					Yes	** NA **			None
23	M23					Yes	** NA **			None
24	M24					Yes	** NA **			None
25	M25					Yes				None
26	M26					Yes				None
27	M27					Yes				None
28	M28	BenPIN				Yes	** NA **			None
29	M29					Yes				None
30	M30					Yes				None
31	M31	BenPIN				Yes	** NA **			None
32	M32					Yes				None
33	M33					Yes				None
34	M34	BenPIN				Yes	** NA **			None
35	M35					Yes				None
36	M36					Yes				None
37	M37	BenPIN				Yes	** NA **			None
38	M38					Yes				None
39	M39					Yes				None
40	M40	BenPIN				Yes	** NA **			None
41	M41					Yes				None
42	M42					Yes				None
43	M43	BenPIN				Yes	** NA **			None
44	M44					Yes				None
45	M45					Yes				None
46	M46					Yes	** NA **			None
47	M47	BenPIN				Yes	** NA **			None
48	M48					Yes	** NA **			None
49	M49	BenPIN				Yes	** NA **			None
50	M50					Yes	** NA **			None
51	M51	BenPIN				Yes	** NA **			None
52	M52					Yes	** NA **			None
53	M53	BenPIN				Yes	** NA **			None
54	M54					Yes	** NA **			None
55	M55	BenPIN				Yes	** NA **			None
56	M56					Yes	** NA **			None
57	M57	BenPIN				Yes	** NA **			None
58	M58	BenPIN	BenPIN			Yes	** NA **			None
59	M59	BenPIN	BenPIN			Yes	** NA **			None
60	M60	BenPIN	BenPIN			Yes	** NA **			None
61	M61					Yes	** NA **			None
62	M62					Yes	** NA **			None
63	M63					Yes	** NA **			None
64	M64					Yes	** NA **			None
65	M65					Yes	** NA **			None
66	M66					Yes	** NA **			None
67	M67					Yes	** NA **			None
68	M68					Yes	** NA **			None
69	M69					Yes	** NA **			None
70	M70					Yes	** NA **			None
71	M71					Yes	** NA **			None
72	M72					Yes	** NA **			None
73	M73					Yes	** NA **			None
74	M74					Yes	** NA **			None
75	M75					Yes	** NA **			None
76	M76					Yes	** NA **			None
77	M77					Yes	** NA **			None
78	M78					Yes	** NA **			None

### Member Advanced Data (Continued)

Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
79 M79						Yes	** NA **			None
80 M80						Yes	** NA **			None
81 M81						Yes	** NA **			None
82 M82						Yes	** NA **			None
83 M83						Yes	** NA **			None
84 M84						Yes	** NA **			None
85 M85						Yes	** NA **			None
86 M86						Yes	** NA **			None
87 M87						Yes	** NA **			None
88 M88						Yes	** NA **			None
89 M89						Yes	** NA **			None
90 M90						Yes	** NA **			None
91 M91						Yes	** NA **			None
92 M92						Yes	** NA **			None
93 M93						Yes	** NA **			None

### Hot Rolled Steel Design Parameters

Label	Shape	Length[in]	Lbyy[in]	Lbzz[in]	Lcomp top[in]	Lcomp bot[in]	L-torqu...	Kyy	Kzz	Cb	Function
1 M1	PIPE 3.0	150			Lbyy						Lateral
2 M2	PIPE 3.0	150			Lbyy						Lateral
3 M3	PIPE 3.0	150			Lbvv						Lateral
4 M4	HSS4X4X4	63			Lbvv						Lateral
5 M5	HSS4X4X4	63			Lbvv						Lateral
6 M6	HSS4X4X4	63			Lbvv						Lateral
7 M7	FB6x0.37	4.959			Lbvv						Lateral
8 M8	FB6x0.37	4.959			Lbvv						Lateral
9 M9	FB6x0.37	4.959			Lbvv						Lateral
10 M10	PIPE 2.0	96			Lbvv						Lateral
11 M12	HSS4X4X4	53.507			Lbvv						Lateral
12 M13	L2x2x3	52.013			Lbvv						Lateral
13 M14	L2x2x3	52.013			Lbvv						Lateral
14 M15	HSS4X4X4	53.507			Lbvv						Lateral
15 M16	L2x2x3	52.013			Lbvv						Lateral
16 M17	L2x2x3	52.013			Lbvv						Lateral
17 M18	L2x2x3	52.013			Lbvv						Lateral
18 M19	L2x2x3	52.013			Lbvv						Lateral
19 M20	HSS4X4X4	53.507			Lbvv						Lateral
20 M21	PIPE 2.5	150			Lbvv			2.1	2.1		Lateral
21 M22	PIPE 2.5	150			Lbvv			2.1	2.1		Lateral
22 M23	PIPE 2.5	150			Lbvv			2.1	2.1		Lateral
23 M25	L2.5x2.5x3	12			Lbvv						Lateral
24 M26	L2.5x2.5x3	12			Lbvv						Lateral
25 M27	L2.5x2.5x3	12			Lbvv						Lateral
26 M29	FB6x0.37	3			Lbvv						Lateral
27 M30	FB6x0.37	2			Lbvv						Lateral
28 M32	FB6x0.37	3			Lbvv						Lateral
29 M33	FB6x0.37	2			Lbvv						Lateral
30 M35	FB6x0.37	3			Lbvv						Lateral
31 M36	FB6x0.37	2			Lbvv						Lateral
32 M38	FB6x0.37	3			Lbvv						Lateral
33 M39	FB6x0.37	2			Lbvv						Lateral
34 M41	FB6x0.37	3			Lbvv						Lateral
35 M42	FB6x0.37	2			Lbvv						Lateral
36 M44	FB6x0.37	3			Lbvv						Lateral
37 M45	FB6x0.37	2			Lbvv						Lateral

### Hot Rolled Steel Design Parameters (Continued)

Label	Shape	Length[in]	Lbyy[in]	Lbzz[in]	Lcomp top[in]	Lcomp bot[in]	L-torqu...	Kyy	Kzz	Cb	Function
38	M46	FB6x0.37	3								Lateral
39	M48	FB6x0.37	3								Lateral
40	M50	FB6x0.37	3								Lateral
41	M52	FB6x0.37	3								Lateral
42	M54	FB6x0.37	3								Lateral
43	M56	FB6x0.37	3								Lateral
44	M58	PIPE 2.0	69.735								Lateral
45	M59	PIPE 2.0	69.735								Lateral
46	M60	PIPE 2.0	69.735								Lateral
47	M61	PIPE 2.0	96				Lbyy				Lateral
48	M64	PIPE 2.0	96				Lbyy				Lateral
49	M67	PIPE 2.0	96				Lbyy				Lateral
50	M70	PIPE 2.0	96				Lbyy				Lateral
51	M73	PIPE 2.0	96				Lbyy				Lateral
52	M76	PIPE 2.0	96				Lbyy				Lateral
53	M79	PIPE 2.0	96				Lbyy				Lateral
54	M82	PIPE 2.0	96				Lbyy				Lateral
55	M85	PIPE 2.0	96				Lbyy				Lateral
56	M88	PIPE 2.0	96				Lbyy				Lateral
57	M91	PIPE 2.0	96				Lbyy				Lateral

### Basic Load Cases

BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...)	Surface(P...)
1	Self We	DL		-1.1				
2	We	DL				24		3
3	Ice We	DL				24	33	3
4	W0	WL				24	33	
5	W30	WL				48	66	
6	W60	WL				48	66	
7	W90	WL				24	33	
8	W120	WL				48	66	
9	W150	WL				48	66	
10	W0 + Ice	WL				24	33	
11	W30 + Ice	WL				48	66	
12	W60 + Ice	WL				48	66	
13	W90 + Ice	WL				24	33	
14	W120 + Ice	WL				48	66	
15	W150 + Ice	WL				48	66	
16	500lbs LM 1	LL			1			
17	500lbs LM 2	LL			1			
18	500lbs LM 3	LL			1			
19	500lbs LM 4	LL			1			
20	250lbs LV 5	LL			1			
21	250lbs LV 6	LL			1			
22	E0	EL	- .11			24		
23	E90	EL		.11		24		
24	BLC 2 Transient Area...	None					18	
25	BLC 3 Transient Area...	None					18	

### Load Combinations

Description	Solve	P...	S...	B...	Fa...																		
1	Dead	Yes	Y	1	1.4	2	1.4	0	0														
2	Dead + Wind 0	Yes	Y	1	1.2	2	1.2	4	1	0													
3	Dead + Wind 30	Yes	Y	1	1.2	2	1.2	5	1	0													





### **Member Point Loads (BLC 2 : We)**

	Member Label	Direction	Magnitude[lb.k-in]	Location[in.%]
1	M67	Y	-41.5	3
2	M64	Y	-63.95	3.05
3	M61	Y	-40.75	3
4	M91	Y	-41.5	3
5	M88	Y	-63.95	3.05
6	M85	Y	-40.75	3
7	M79	Y	-41.5	3
8	M76	Y	-63.95	3.05
9	M73	Y	-40.75	3
10	M67	Y	-41.5	53
11	M64	Y	-63.95	92.95
12	M61	Y	-40.75	53
13	M91	Y	-41.5	53
14	M88	Y	-63.95	92.95
15	M85	Y	-40.75	53
16	M79	Y	-41.5	53
17	M76	Y	-63.95	92.95
18	M73	Y	-40.75	53
19	M67	Y	-15.4	18
20	M64	Y	-75	18
21	M91	Y	-15.4	18
22	M88	Y	-75	18
23	M79	Y	-15.4	18
24	M76	Y	-75	18

### **Member Point Loads (BLC 3 : Ice We)**

	Member Label	Direction	Magnitude[lb.k-in]	Location[in.%]
1	M67	Y	-50.906	3
2	M64	Y	-148.22	3.05
3	M61	Y	-50.999	3
4	M91	Y	-50.906	3
5	M88	Y	-148.22	3.05
6	M85	Y	-50.999	3
7	M79	Y	-50.906	3
8	M76	Y	-148.22	3.05
9	M73	Y	-50.999	3
10	M67	Y	-50.906	53
11	M64	Y	-148.22	92.95
12	M61	Y	-50.999	53
13	M91	Y	-50.906	53
14	M88	Y	-148.22	92.95
15	M85	Y	-50.999	53
16	M79	Y	-50.906	53
17	M76	Y	-148.22	92.95
18	M73	Y	-50.999	53
19	M67	Y	-11.628	18
20	M64	Y	-33.259	18
21	M91	Y	-11.628	18
22	M88	Y	-33.259	18
23	M79	Y	-11.628	18
24	M76	Y	-33.259	18

### **Member Point Loads (BLC 4 : W0)**

	Member Label	Direction	Magnitude[lb.k-in]	Location[in.%]
1	M67	X	-143.65	3

### Member Point Loads (BLC 4 : W0) (Continued)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
2	M64	X	-480.684	3.05
3	M61	X	-144.655	3
4	M91	X	-113.483	3
5	M88	X	-278.472	3.05
6	M85	X	-112.927	3
7	M79	X	-113.483	3
8	M76	X	-278.472	3.05
9	M73	X	-112.927	3
10	M67	X	-143.65	53
11	M64	X	-480.684	92.95
12	M61	X	-144.655	53
13	M91	X	-113.483	53
14	M88	X	-278.472	92.95
15	M85	X	-112.927	53
16	M79	X	-113.483	53
17	M76	X	-278.472	92.95
18	M73	X	-112.927	53
19	M67	X	-26.556	18
20	M64	X	-78.362	18
21	M91	X	-19.524	18
22	M88	X	-66.341	18
23	M79	X	-19.524	18
24	M76	X	-66.341	18

### Member Point Loads (BLC 5 : W30)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	X	-115.696	3
2	M64	X	-357.911	3.05
3	M61	X	-116.116	3
4	M91	X	-115.696	3
5	M88	X	-357.911	3.05
6	M85	X	-116.116	3
7	M79	X	-89.571	3
8	M76	X	-182.79	3.05
9	M73	X	-88.638	3
10	M67	X	-115.696	53
11	M64	X	-357.911	92.95
12	M61	X	-116.116	53
13	M91	X	-115.696	53
14	M88	X	-357.911	92.95
15	M85	X	-116.116	53
16	M79	X	-89.571	53
17	M76	X	-182.79	92.95
18	M73	X	-88.638	53
19	M67	X	-20.968	18
20	M64	X	-64.393	18
21	M91	X	-20.968	18
22	M88	X	-64.393	18
23	M79	X	-14.878	18
24	M76	X	-53.983	18
25	M67	Z	66.797	3
26	M64	Z	206.64	3.05
27	M61	Z	67.039	3
28	M91	Z	66.797	3
29	M88	Z	206.64	3.05
30	M85	Z	67.039	3

**Member Point Loads (BLC 5 : W30) (Continued)**

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
31	M79	Z	51.714	3
32	M76	Z	105.534	3.05
33	M73	Z	51.175	3
34	M67	Z	66.797	53
35	M64	Z	206.64	92.95
36	M61	Z	67.039	53
37	M91	Z	66.797	53
38	M88	Z	206.64	92.95
39	M85	Z	67.039	53
40	M79	Z	51.714	53
41	M76	Z	105.534	92.95
42	M73	Z	51.175	53
43	M67	Z	12.106	18
44	M64	Z	37.178	18
45	M91	Z	12.106	18
46	M88	Z	37.178	18
47	M79	Z	8.59	18
48	M76	Z	31.167	18

**Member Point Loads (BLC 6 : W60)**

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	X	-56.742	3
2	M64	X	-139.236	3.05
3	M61	X	-56.463	3
4	M91	X	-71.825	3
5	M88	X	-240.342	3.05
6	M85	X	-72.328	3
7	M79	X	-56.742	3
8	M76	X	-139.236	3.05
9	M73	X	-56.463	3
10	M67	X	-56.742	53
11	M64	X	-139.236	92.95
12	M61	X	-56.463	53
13	M91	X	-71.825	53
14	M88	X	-240.342	92.95
15	M85	X	-72.328	53
16	M79	X	-56.742	53
17	M76	X	-139.236	92.95
18	M73	X	-56.463	53
19	M67	X	-9.762	18
20	M64	X	-33.17	18
21	M91	X	-13.278	18
22	M88	X	-39.181	18
23	M79	X	-9.762	18
24	M76	X	-33.17	18
25	M67	Z	98.279	3
26	M64	Z	241.164	3.05
27	M61	Z	97.797	3
28	M91	Z	124.404	3
29	M88	Z	416.284	3.05
30	M85	Z	125.275	3
31	M79	Z	98.279	3
32	M76	Z	241.164	3.05
33	M73	Z	97.797	3
34	M67	Z	98.279	53
35	M64	Z	241.164	92.95

### **Member Point Loads (BLC 6 : W60) (Continued)**

Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
36	M61	Z	97.797
37	M91	Z	124.404
38	M88	Z	416.284
39	M85	Z	125.275
40	M79	Z	98.279
41	M76	Z	241.164
42	M73	Z	97.797
43	M67	Z	16.908
44	M64	Z	57.453
45	M91	Z	22.998
46	M88	Z	67.864
47	M79	Z	16.908
48	M76	Z	57.453

### **Member Point Loads (BLC 7 : W90)**

Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	Z	103.428
2	M64	Z	211.068
3	M61	Z	102.35
4	M91	Z	133.594
5	M88	Z	413.28
6	M85	Z	134.079
7	M79	Z	133.594
8	M76	Z	413.28
9	M73	Z	134.079
10	M67	Z	103.428
11	M64	Z	211.068
12	M61	Z	102.35
13	M91	Z	133.594
14	M88	Z	413.28
15	M85	Z	134.079
16	M79	Z	133.594
17	M76	Z	413.28
18	M73	Z	134.079
19	M67	Z	17.18
20	M64	Z	62.334
21	M91	Z	24.212
22	M88	Z	74.355
23	M79	Z	24.212
24	M76	Z	74.355

### **Member Point Loads (BLC 8 : W120)**

Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	X	56.742
2	M64	X	139.236
3	M61	X	56.463
4	M91	X	56.742
5	M88	X	139.236
6	M85	X	56.463
7	M79	X	71.825
8	M76	X	240.342
9	M73	X	72.328
10	M67	X	56.742
11	M64	X	139.236
12	M61	X	56.463
13	M91	X	56.742

### **Member Point Loads (BLC 8 : W120) (Continued)**

Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
14 M88	X	139.236	92.95
15 M85	X	56.463	53
16 M79	X	71.825	53
17 M76	X	240.342	92.95
18 M73	X	72.328	53
19 M67	X	9.762	18
20 M64	X	33.17	18
21 M91	X	9.762	18
22 M88	X	33.17	18
23 M79	X	13.278	18
24 M76	X	39.181	18
25 M67	Z	98.279	3
26 M64	Z	241.164	3.05
27 M61	Z	97.797	3
28 M91	Z	98.279	3
29 M88	Z	241.164	3.05
30 M85	Z	97.797	3
31 M79	Z	124.404	3
32 M76	Z	416.284	3.05
33 M73	Z	125.275	3
34 M67	Z	98.279	53
35 M64	Z	241.164	92.95
36 M61	Z	97.797	53
37 M91	Z	98.279	53
38 M88	Z	241.164	92.95
39 M85	Z	97.797	53
40 M79	Z	124.404	53
41 M76	Z	416.284	92.95
42 M73	Z	125.275	53
43 M67	Z	16.908	18
44 M64	Z	57.453	18
45 M91	Z	16.908	18
46 M88	Z	57.453	18
47 M79	Z	22.998	18
48 M76	Z	67.864	18

### **Member Point Loads (BLC 9 : W150)**

Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1 M67	X	115.696	3
2 M64	X	357.911	3.05
3 M61	X	116.116	3
4 M91	X	89.571	3
5 M88	X	182.79	3.05
6 M85	X	88.638	3
7 M79	X	115.696	3
8 M76	X	357.911	3.05
9 M73	X	116.116	3
10 M67	X	115.696	53
11 M64	X	357.911	92.95
12 M61	X	116.116	53
13 M91	X	89.571	53
14 M88	X	182.79	92.95
15 M85	X	88.638	53
16 M79	X	115.696	53
17 M76	X	357.911	92.95
18 M73	X	116.116	53

### Member Point Loads (BLC 9 : W150) (Continued)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
19	M67	X	20.968	18
20	M64	X	64.393	18
21	M91	X	14.878	18
22	M88	X	53.983	18
23	M79	X	20.968	18
24	M76	X	64.393	18
25	M67	Z	66.797	3
26	M64	Z	206.64	3.05
27	M61	Z	67.039	3
28	M91	Z	51.714	3
29	M88	Z	105.534	3.05
30	M85	Z	51.175	3
31	M79	Z	66.797	3
32	M76	Z	206.64	3.05
33	M73	Z	67.039	3
34	M67	Z	66.797	53
35	M64	Z	206.64	92.95
36	M61	Z	67.039	53
37	M91	Z	51.714	53
38	M88	Z	105.534	92.95
39	M85	Z	51.175	53
40	M79	Z	66.797	53
41	M76	Z	206.64	92.95
42	M73	Z	67.039	53
43	M67	Z	12.106	18
44	M64	Z	37.178	18
45	M91	Z	8.59	18
46	M88	Z	31.167	18
47	M79	Z	12.106	18
48	M76	Z	37.178	18

### Member Point Loads (BLC 10 : W0 + Ice)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	X	-25.731	3
2	M64	X	-78.887	3.05
3	M61	X	-25.885	3
4	M91	X	-21.089	3
5	M88	X	-48.541	3.05
6	M85	X	-21.011	3
7	M79	X	-21.089	3
8	M76	X	-48.541	3.05
9	M73	X	-21.011	3
10	M67	X	-25.731	53
11	M64	X	-78.887	92.95
12	M61	X	-25.885	53
13	M91	X	-21.089	53
14	M88	X	-48.541	92.95
15	M85	X	-21.011	53
16	M79	X	-21.089	53
17	M76	X	-48.541	92.95
18	M73	X	-21.011	53
19	M67	X	-6.48	18
20	M64	X	-15.607	18
21	M91	X	-5.199	18
22	M88	X	-13.561	18
23	M79	X	-5.199	18

### Member Point Loads (BLC 10 : W0 + Ice) (Continued)

Member Label	Direction	Magnitude[lb,k-in]	Location[in, %]
24 M76	X	-13.561	18

### Member Point Loads (BLC 11 : W30 + Ice)

Member Label	Direction	Magnitude[lb,k-in]	Location[in, %]
1 M67	X	-20.943	3
2 M64	X	-59.558	3.05
3 M61	X	-21.01	3
4 M91	X	-20.943	3
5 M88	X	-59.558	3.05
6 M85	X	-21.01	3
7 M79	X	-16.923	3
8 M76	X	-33.278	3.05
9 M73	X	-16.789	3
10 M67	X	-20.943	53
11 M64	X	-59.558	92.95
12 M61	X	-21.01	53
13 M91	X	-20.943	53
14 M88	X	-59.558	92.95
15 M85	X	-21.01	53
16 M79	X	-16.923	53
17 M76	X	-33.278	92.95
18 M73	X	-16.789	53
19 M67	X	-5.242	18
20 M64	X	-12.925	18
21 M91	X	-5.242	18
22 M88	X	-12.925	18
23 M79	X	-4.133	18
24 M76	X	-11.154	18
25 M67	Z	12.092	3
26 M64	Z	34.386	3.05
27 M61	Z	12.13	3
28 M91	Z	12.092	3
29 M88	Z	34.386	3.05
30 M85	Z	12.13	3
31 M79	Z	9.771	3
32 M76	Z	19.213	3.05
33 M73	Z	9.693	3
34 M67	Z	12.092	53
35 M64	Z	34.386	92.95
36 M61	Z	12.13	53
37 M91	Z	12.092	53
38 M88	Z	34.386	92.95
39 M85	Z	12.13	53
40 M79	Z	9.771	53
41 M76	Z	19.213	92.95
42 M73	Z	9.693	53
43 M67	Z	3.026	18
44 M64	Z	7.462	18
45 M91	Z	3.026	18
46 M88	Z	7.462	18
47 M79	Z	2.386	18
48 M76	Z	6.44	18

### Member Point Loads (BLC 12 : W60 + Ice)

Member Label	Direction	Magnitude[lb,k-in]	Location[in, %]
1 M67	X	-10.544	3

### Member Point Loads (BLC 12 : W60 + Ice) (Continued)

	Member Label	Direction	Magnitude[lb.k-in]	Location[in.%]
2	M64	X	-24.271	3.05
3	M61	X	-10.506	3
4	M91	X	-12.865	3
5	M88	X	-39.443	3.05
6	M85	X	-12.943	3
7	M79	X	-10.544	3
8	M76	X	-24.271	3.05
9	M73	X	-10.506	3
10	M67	X	-10.544	53
11	M64	X	-24.271	92.95
12	M61	X	-10.506	53
13	M91	X	-12.865	53
14	M88	X	-39.443	92.95
15	M85	X	-12.943	53
16	M79	X	-10.544	53
17	M76	X	-24.271	92.95
18	M73	X	-10.506	53
19	M67	X	-2.6	18
20	M64	X	-6.781	18
21	M91	X	-3.24	18
22	M88	X	-7.803	18
23	M79	X	-2.6	18
24	M76	X	-6.781	18
25	M67	Z	18.263	3
26	M64	Z	42.038	3.05
27	M61	Z	18.196	3
28	M91	Z	22.283	3
29	M88	Z	68.318	3.05
30	M85	Z	22.417	3
31	M79	Z	18.263	3
32	M76	Z	42.038	3.05
33	M73	Z	18.196	3
34	M67	Z	18.263	53
35	M64	Z	42.038	92.95
36	M61	Z	18.196	53
37	M91	Z	22.283	53
38	M88	Z	68.318	92.95
39	M85	Z	22.417	53
40	M79	Z	18.263	53
41	M76	Z	42.038	92.95
42	M73	Z	18.196	53
43	M67	Z	4.503	18
44	M64	Z	11.744	18
45	M91	Z	5.611	18
46	M88	Z	13.516	18
47	M79	Z	4.503	18
48	M76	Z	11.744	18

### Member Point Loads (BLC 13 : W90 + Ice)

	Member Label	Direction	Magnitude[lb.k-in]	Location[in.%]
1	M67	Z	19.542	3
2	M64	Z	38.426	3.05
3	M61	Z	19.387	3
4	M91	Z	24.183	3
5	M88	Z	68.772	3.05
6	M85	Z	24.261	3

### Member Point Loads (BLC 13 : W90 + Ice) (Continued)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
7	M79	Z	24.183	3
8	M76	Z	68.772	3.05
9	M73	Z	24.261	3
10	M67	Z	19.542	53
11	M64	Z	38.426	92.95
12	M61	Z	19.387	53
13	M91	Z	24.183	53
14	M88	Z	68.772	92.95
15	M85	Z	24.261	53
16	M79	Z	24.183	53
17	M76	Z	68.772	92.95
18	M73	Z	24.261	53
19	M67	Z	4.773	18
20	M64	Z	12.879	18
21	M91	Z	6.053	18
22	M88	Z	14.925	18
23	M79	Z	6.053	18
24	M76	Z	14.925	18

### Member Point Loads (BLC 14 : W120 + Ice)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	X	10.544	3
2	M64	X	24.271	3.05
3	M61	X	10.506	3
4	M91	X	10.544	3
5	M88	X	24.271	3.05
6	M85	X	10.506	3
7	M79	X	12.865	3
8	M76	X	39.443	3.05
9	M73	X	12.943	3
10	M67	X	10.544	53
11	M64	X	24.271	92.95
12	M61	X	10.506	53
13	M91	X	10.544	53
14	M88	X	24.271	92.95
15	M85	X	10.506	53
16	M79	X	12.865	53
17	M76	X	39.443	92.95
18	M73	X	12.943	53
19	M67	X	2.6	18
20	M64	X	6.781	18
21	M91	X	2.6	18
22	M88	X	6.781	18
23	M79	X	3.24	18
24	M76	X	7.803	18
25	M67	Z	18.263	3
26	M64	Z	42.038	3.05
27	M61	Z	18.196	3
28	M91	Z	18.263	3
29	M88	Z	42.038	3.05
30	M85	Z	18.196	3
31	M79	Z	22.283	3
32	M76	Z	68.318	3.05
33	M73	Z	22.417	3
34	M67	Z	18.263	53
35	M64	Z	42.038	92.95



Company : Tower Engineering Professionals, Inc  
 Designer : VAA  
 Job Number : TEP No. 177168.534968  
 Model Name : 284988 - GUILFORD CT

May 7, 2021  
 5:17 PM  
 Checked By: SC

### Member Point Loads (BLC 14 : W120 + Ice) (Continued)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
36	M61	Z	18.196	53
37	M91	Z	18.263	53
38	M88	Z	42.038	92.95
39	M85	Z	18.196	53
40	M79	Z	22.283	53
41	M76	Z	68.318	92.95
42	M73	Z	22.417	53
43	M67	Z	4.503	18
44	M64	Z	11.744	18
45	M91	Z	4.503	18
46	M88	Z	11.744	18
47	M79	Z	5.611	18
48	M76	Z	13.516	18

### Member Point Loads (BLC 15 : W150 + Ice)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	X	20.943	3
2	M64	X	59.558	3.05
3	M61	X	21.01	3
4	M91	X	16.923	3
5	M88	X	33.278	3.05
6	M85	X	16.789	3
7	M79	X	20.943	3
8	M76	X	59.558	3.05
9	M73	X	21.01	3
10	M67	X	20.943	53
11	M64	X	59.558	92.95
12	M61	X	21.01	53
13	M91	X	16.923	53
14	M88	X	33.278	92.95
15	M85	X	16.789	53
16	M79	X	20.943	53
17	M76	X	59.558	92.95
18	M73	X	21.01	53
19	M67	X	5.242	18
20	M64	X	12.925	18
21	M91	X	4.133	18
22	M88	X	11.154	18
23	M79	X	5.242	18
24	M76	X	12.925	18
25	M67	Z	12.092	3
26	M64	Z	34.386	3.05
27	M61	Z	12.13	3
28	M91	Z	9.771	3
29	M88	Z	19.213	3.05
30	M85	Z	9.693	3
31	M79	Z	12.092	3
32	M76	Z	34.386	3.05
33	M73	Z	12.13	3
34	M67	Z	12.092	53
35	M64	Z	34.386	92.95
36	M61	Z	12.13	53
37	M91	Z	9.771	53
38	M88	Z	19.213	92.95
39	M85	Z	9.693	53
40	M79	Z	12.092	53

### Member Point Loads (BLC 15 : W150 + Ice) (Continued)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
41	M76	Z	34.386	92.95
42	M73	Z	12.13	53
43	M67	Z	3.026	18
44	M64	Z	7.462	18
45	M91	Z	2.386	18
46	M88	Z	6.44	18
47	M79	Z	3.026	18
48	M76	Z	7.462	18

### Member Point Loads (BLC 22 : E0)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	X	-4.471	3
2	M64	X	-6.89	3.05
3	M61	X	-4.39	3
4	M91	X	-4.471	3
5	M88	X	-6.89	3.05
6	M85	X	-4.39	3
7	M79	X	-4.471	3
8	M76	X	-6.89	3.05
9	M73	X	-4.39	3
10	M67	X	-4.471	53
11	M64	X	-6.89	92.95
12	M61	X	-4.39	53
13	M91	X	-4.471	53
14	M88	X	-6.89	92.95
15	M85	X	-4.39	53
16	M79	X	-4.471	53
17	M76	X	-6.89	92.95
18	M73	X	-4.39	53
19	M67	X	-1.659	18
20	M64	X	-8.08	18
21	M91	X	-1.659	18
22	M88	X	-8.08	18
23	M79	X	-1.659	18
24	M76	X	-8.08	18

### Member Point Loads (BLC 23 : E90)

	Member Label	Direction	Magnitude[lb,k-in]	Location[in.%]
1	M67	Z	4.471	3
2	M64	Z	6.89	3.05
3	M61	Z	4.39	3
4	M91	Z	4.471	3
5	M88	Z	6.89	3.05
6	M85	Z	4.39	3
7	M79	Z	4.471	3
8	M76	Z	6.89	3.05
9	M73	Z	4.39	3
10	M67	Z	4.471	53
11	M64	Z	6.89	92.95
12	M61	Z	4.39	53
13	M91	Z	4.471	53
14	M88	Z	6.89	92.95
15	M85	Z	4.39	53
16	M79	Z	4.471	53
17	M76	Z	6.89	92.95
18	M73	Z	4.39	53



**Envelope AISC 15th(360-16): LRFD Steel Code Checks (Continued)**

Member	Shape	Code Check	Loc[in]	LC Shear Che...	Loc[in]	Dir	LC phi*Pnc ...	phi*Pnt [...]	phi*Mn y...	phi*Mn z...	Cb	Eqn
35	M29	FB6x0.37	.262	0	10	.225	0	y	2269002.0...	71928	6.653	107.892 1.285 H1-1b
36	M35	FB6x0.37	.262	0	2	.225	0	y	1469002.0...	71928	6.653	107.892 1.285 H1-1b
37	M2	PIPE 3.0	.198	95.312	2	.096	50		928250.5...	65205	68.985	68.985 2.322 H1-1b
38	M1	PIPE 3.0	.198	54.687	10	.096	100		528250.5...	65205	68.985	68.985 2.322 H1-1b
39	M3	PIPE 3.0	.198	54.688	6	.096	100		1328250.5...	65205	68.985	68.985 2.321 H1-1b
40	M56	FB6x0.37	.192	3	8	.123	3	y	969001.8...	71928	6.653	107.892 2.179 H1-1b
41	M48	FB6x0.37	.192	3	12	.123	3	v	1369001.8...	71928	6.653	107.892 2.179 H1-1b
42	M52	FB6x0.37	.192	3	4	.123	3	y	569001.8...	71928	6.653	107.892 2.179 H1-1b
43	M54	FB6x0.37	.189	3	12	.156	0	y	569001.8...	71928	6.653	107.892 1.963 H1-1b
44	M50	FB6x0.37	.189	3	8	.156	0	y	1369001.8...	71928	6.653	107.892 1.964 H1-1b
45	M46	FB6x0.37	.189	3	4	.156	0	y	969001.8...	71928	6.653	107.892 1.964 H1-1b
46	M20	HSS4X4X4	.189	26.754	13	.067	.557	z	13128378...	139518	194.166	194.166 1.337 H1-1b
47	M12	HSS4X4X4	.189	26.754	5	.067	52.95	z	5128378...	139518	194.166	194.166 1.337 H1-1b
48	M15	HSS4X4X4	.189	26.754	9	.067	52.95	z	9128378...	139518	194.166	194.166 1.337 H1-1b
49	M17	L2x2x3	.187	25.465	8	.010	52.013	z	149123.422	23392.8	6.693	12.761 1.137 H2-1
50	M14	L2x2x3	.187	25.465	4	.010	52.013	z	229123.425	23392.8	6.693	12.761 1.137 H2-1
51	M19	L2x2x3	.187	25.465	12	.010	52.013	z	189123.425	23392.8	6.693	12.761 1.137 H2-1
52	M18	L2x2x3	.155	25.465	4	.010	52.013	y	249123.425	23392.8	6.693	12.761 1.137 H2-1
53	M13	L2x2x3	.155	25.465	8	.010	52.013	y	169123.422	23392.8	6.693	12.761 1.137 H2-1
54	M16	L2x2x3	.155	25.465	12	.010	52.013	y	209123.425	23392.8	6.693	12.761 1.137 H2-1
55	M60	PIPE 2.0	.049	34.868	4	.129	0		721432.0...	32130	22.459	22.459 1.136 H1-1b
56	M59	PIPE 2.0	.049	34.868	8	.129	0		1121432.0...	32130	22.459	22.459 1.136 H1-1b
57	M58	PIPE 2.0	.049	34.868	12	.129	0		321432.0...	32130	22.459	22.459 1.136 H1-1b


**SITE DETAILS**

Site Name/Code  
Date  
Engineer

284988 - GUILFORD CT  
05/07/2021  
VAA

**CONNECTION PARAMETERS**

Number of bolts	4
b - width of member	4
d - height of member	4
B - horizontal bolt spacing	7 in
D - vertical bolt spacing	7 in
Bolt Diameter	5/8 in
Section Shape	HSS
Weld Thickness	3/8 in
Tensile Area	0.31 in <sup>2</sup>
A <sub>b</sub>	0.23 in <sup>2</sup>
A <sub>n</sub>	A325
F <sub>ub</sub>	120 ksi
R <sub>b</sub>	1



Connection Sketch/Photo

**FLANGE LOADS**

Loadcase #	6
Bending Moment	M <sub>zz</sub> 90.57 kips-in
Bending Moment	M <sub>yy</sub> 0.89 kips-in
Torsional Moment	M <sub>xx</sub> 1.28 kips-in
Shear Force	V <sub>y</sub> 2.95 kips
Shear Force	V <sub>z</sub> 0.04 kips
Axial Force	P <sub>x</sub> 3.07 kips

**BOLT CHECK****Bolt Tension Capacity**

$$\phi R_{nt} = 0.75 * F_{ub} * A_n$$

$$\phi R_{nt} = 20.3 \text{ kips}$$

**Bolt Shear Capacity**

$$\phi R_{nv} = 0.75 * 0.625 * 0.8 * F_{ub} * A_b * R_b$$

$$\phi R_{nv} = 13.8 \text{ kips}$$

**Maximum Bolt Tension**

$$T_{ub} = F_{Mxx} + F_{Mzz} + T_y/4$$

$$T_{ub} = 7.30 \text{ kips}$$

**Maximum Bolt Shear**

$$V_{ub} = \sqrt{(V_x/4)^2 + (V_y/4)^2} + F_{My}$$

$$V_{ub} = 0.80 \text{ kips}$$

**Tension Ratio:**

$$35.9\% \text{ %}$$

PASS

**Shear Ratio:**

$$5.8\% \text{ %}$$

PASS

$$(T_{ub} / \phi R_{nt})^2 + (V_{ub} / \phi R_{nv})^2 < 1.0$$

OK

Ratio

13.2% PASS

**WELD CHECK**Filler Metal F<sub>EXX</sub>

70 ksi

Are stiffners present?

No

Weld Thk.

0.375 in

Base metal F<sub>u</sub>

58 ksi

Type of section

HSS

Length of Section [b]

4.0 in

Length of Section [d]

4.0 in

I<sub>total</sub>

16.00 in

I<sub>p</sub>85.33 in<sup>3</sup>S<sub>z</sub>21.33 in<sup>2</sup>S<sub>y</sub>21.33 in<sup>2</sup>R<sub>ux</sub>

4.48 kips/in

R<sub>uy</sub>

0.21 kips/in

R<sub>uz</sub>


0.03 kips/in

R<sub>u</sub>

4.48 kips/in

Allowable Weld Stress

8.35 kips/in



53.7% PASS

Connection Sketch

## ANSI/TIA-222H - WIND, ICE & SEISMIC LOAD CALCULATIONS

Site Code/Name
State
County
Structure Class
Exposure Category
Topographic Category
Mean Elevation of base of structure
Height Above Ground

284988 - GUILFORD CT

z <sub>s</sub>	Connecticut	<i>Reference</i>
	New Haven	<i>Table 2-1</i>
	II	
	C	<i>Section 2.6.5.1.2</i>
	1 - K <sub>zt</sub> = 1	<i>Section 2.6.6.2.1</i>
	51.46 ft	<i>ASCE7-16 Hazards</i>
z	108 ft	

Wind Parameters	
V	Basic wind speed
K <sub>d</sub>	Wind direction probability factor
G <sub>h</sub>	Gust effect factor
	Velocity Pressure (K <sub>a</sub> = 0.9)

V	130 mph	<i>ASCE7-16 Hazards Tool</i>
K <sub>d</sub>	0.95	<i>Section 16.6</i>
G <sub>h</sub>	1	<i>Section 16.6</i>
	47.49 psf	<i>Section 2.6.11.6</i>

Wind & Ice Parameters	
t <sub>i</sub>	Base windspeed in conjunction with ice, V
q <sub>ice</sub>	Base Ice thickness
	Ice Velocity Pressure (K <sub>a</sub> = 0.9)
t <sub>iz</sub>	Design Ice Thickness

t <sub>i</sub>	50 mph	<i>ASCE7-16 Hazards Tool</i>
q <sub>ice</sub>	1.00 in	<i>ASCE7-16 Hazards Tool</i>
	7.03 psf	<i>Section 2.6.11.6</i>
t <sub>iz</sub>	1.13 in	<i>Section 2.6.10</i>

Seismic Parameters	
S <sub>s</sub>	Site Soil Class
S <sub>1</sub>	Seismic Design Category
T <sub>L</sub>	Spectral Response at Short Periods
I <sub>s</sub>	Spectral Response at 1sec
R	Long Period Transition Period
F <sub>a</sub>	Seismic Importance Factor
S <sub>DS</sub>	Response modification coefficient
C <sub>s</sub>	Short-Period Site Coefficient
	Design Spectral Response at Short Periods
	Seismic Response Coefficient

D- Default	<i>Table 2-10</i>
B	<i>ASCE7-16 Hazards Tool</i>
0.202	<i>ASCE7-16 Hazards Tool</i>
0.053	<i>ASCE7-16 Hazards Tool</i>
6	<i>ASCE7-16 Hazards Tool</i>
1	<i>Table 2-3</i>
2	<i>Section 16.7</i>
1.6	<i>Table 2-11</i>
0.215	<i>Section 2.7.5</i>
0.108	<i>Section 2.7.7.1</i>

## ALPHA SECTOR

Position	Appurtenance properties						Wind		Ice	Seismic
	Manufacturer	Model	L [in]	W [in]	D [in]	Weight [lbs]	0° [lbs]	90° [lbs]	IceWeight [lbs]	E <sub>H</sub> [lbs]
1	Ericsson	AIR 21, 1.3M, B2A B4P	56.0	12.0	8.0	83.0	287.3	206.9	101.8	8.9
2	RFS	APXVAARR24_43-U-NA20	95.9	24.0	8.7	127.9	961.4	422.1	296.4	13.8
3	Ericsson	AIR 21, 1.3M, B4A B2P	56.0	12.1	7.9	81.5	289.3	204.7	102.0	8.8
1	Ericsson	KRY 112 489/2	11.0	6.1	3.9	15.4	26.6	17.2	11.6	1.7
2	Ericsson	Radio 4449 B71 B85A	15.0	13.2	10.5	75.0	78.4	62.3	33.3	8.1

## BETA SECTOR

Position	Appurtenance properties						Wind		Ice	Seismic
	Manufacturer	Model	L [in]	W [in]	D [in]	Weight [lbs]	0° [lbs]	90° [lbs]	IceWeight [lbs]	E <sub>H</sub> [lbs]
1	Ericsson	AIR 21, 1.3M, B2A B4P	56.0	12.0	8.0	83.0	227.0	267.2	101.8	8.9
2	RFS	APXVAARR24_43-U-NA20	95.9	24.0	8.7	127.9	556.9	826.6	296.4	13.8
3	Ericsson	AIR 21, 1.3M, B4A B2P	56.0	12.1	7.9	81.5	225.9	268.2	102.0	8.8
1	Ericsson	KRY 112 489/2	11.0	6.1	3.9	15.4	19.5	24.2	11.6	1.7
2	Ericsson	Radio 4449 B71 B85A	15.0	13.2	10.5	75.0	66.3	74.4	33.3	8.1

## GAMMA SECTOR


Position	Appurtenance properties						Wind		Ice	Seismic
	Manufacturer	Model	L [in]	W [in]	D [in]	Weight [lbs]	0° [lbs]	90° [lbs]	IceWeight [lbs]	E <sub>H</sub> [lbs]
1	Ericsson	AIR 21, 1.3M, B2A B4P	56.0	12.0	8.0	83.0	227.0	267.2	101.8	8.9
2	RFS	APXVAARR24_43-U-NA20	95.9	24.0	8.7	127.9	556.9	826.6	296.4	13.8
3	Ericsson	AIR 21, 1.3M, B4A B2P	56.0	12.1	7.9	81.5	225.9	268.2	102.0	8.8
1	Ericsson	KRY 112 489/2	11.0	6.1	3.9	15.4	19.5	24.2	11.6	1.7
2	Ericsson	Radio 4449 B71 B85A	15.0	13.2	10.5	75.0	66.3	74.4	33.3	8.1

# ASCE 7 Hazards Report

**Address:**  
No Address at This Location

**Standard:** ASCE/SEI 7-16  
**Risk Category:** II  
**Soil Class:** D - Default (see Section 11.4.3)

**Elevation:** 51.46 ft (NAVD 88)  
**Latitude:** 41.2675  
**Longitude:** -72.7161



## Wind

### Results:

Wind Speed:	122 Vmph	130 mph per Local Jurisdiction
10-year MRI	75 Vmph	
25-year MRI	85 Vmph	
50-year MRI	93 Vmph	
100-year MRI	100 Vmph	

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2

Date Accessed: Fri May 07 2021

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2. Glazed openings need not be protected against wind-borne debris.





## Seismic

**Site Soil Class:** D - Default (see Section 11.4.3)

**Results:**

$S_s$ :	0.202	$S_{D1}$ :	0.085
$S_1$ :	0.053	$T_L$ :	6
$F_a$ :	1.6	$PGA$ :	0.113
$F_v$ :	2.4	$PGA_M$ :	0.177
$S_{MS}$ :	0.322	$F_{PGA}$ :	1.575
$S_{M1}$ :	0.128	$I_e$ :	1
$S_{DS}$ :	0.215	$C_v$ :	0.703

**Seismic Design Category** B



**Data Accessed:**

Fri May 07 2021

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

## Ice

---

**Results:**

Ice Thickness: 1.00 in.

Concurrent Temperature: 15 F

Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

**Date Accessed:** Fri May 07 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.


In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.



---

## Structural Analysis Report

Structure : 109 ft Monopole  
ATC Site Name : GUILFORD CT, CT  
ATC Asset Number : 284988  
Engineering Number : 13660479\_C3\_02  
Proposed Carrier : T-MOBILE  
Carrier Site Name : Amtrak\_Guilford  
Carrier Site Number : CTNH805A  
Site Location : Moose Hill Road  
Guilford, CT 06437  
41.267500,-72.716100  
County : New Haven  
Date : June 14, 2021  
Max Usage : 35%  
Result : Pass



Prepared By:  
Josh Krehnbrink  
Structural Engineer

A handwritten signature in black ink that appears to read "Josh Krehnbrink".

Reviewed By:

Authorized by "EOR"  
14 Jun 2021 05:49:00

The word "cosign" in a stylized blue and red font.

COA: PEC.0001553



Eng. Number 13660479\_C3\_02

June 14, 2021

## Table of Contents

Introduction .....	1
Supporting Documents .....	1
Analysis .....	1
Conclusion.....	1
Existing and Reserved Equipment.....	2
Equipment to be Removed.....	2
Proposed Equipment .....	2
Structure Usages .....	3
Foundations .....	3
Deflection and Sway .....	3
Standard Conditions .....	4
Calculations .....	Attached

## Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 109 ft monopole to reflect the change in loading by T-MOBILE.

## Supporting Documents

<b>Tower Drawings</b>	Nello Drawing #147997, dated December 22, 2014
<b>Foundation Drawing</b>	Nello Drawing #147998, dated October 17, 2014
<b>Geotechnical Report</b>	AEG Site #CT0007, dated June 25, 2014
<b>Mount Analysis</b>	ATC Job #13660479_C8_03, dated May 11, 2021

## Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

<b>Basic Wind Speed:</b>	122 mph (3-Second Gust)
<b>Basic Wind Speed w/ Ice:</b>	50 mph (3-Second Gust) w/ 1" radial ice concurrent
<b>Code:</b>	ANSI/TIA-222-H / 2015 IBC / 2018 Connecticut State Building Code
<b>Exposure Category:</b>	C
<b>Risk Category:</b>	II
<b>Topographic Factor Procedure:</b>	Method 1
<b>Topographic Category:</b>	1
<b>Crest Height (H):</b>	0 ft
<b>Spectral Response:</b>	$S_s = 0.17, S_1 = 0.06$
<b>Site Class:</b>	D - Stiff Soil

## Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at [Engineering@americantower.com](mailto:Engineering@americantower.com). Please include the American Tower site name, site number, and engineering number in the subject line for any questions.



Eng. Number 13660479\_C3\_02

June 14, 2021

Page 2

### Existing and Reserved Equipment

Elev. <sup>1</sup> (ft)	Qty	Antenna	Mount Type	Lines	Carrier
108.0	3	Ericsson KRY 112 489/2	-	(6) 1 5/8" Coax	T-MOBILE
	3	Ericsson AIR 21, 1.3 M, B2A B4P			
	3	Ericsson AIR 21, 1.3M, B4A B2P			

### Equipment to be Removed

Elev. <sup>1</sup> (ft)	Qty	Antenna	Mount Type	Lines	Carrier
108.0	3	Ericsson Radio 4449 B12,B71	T-Arm	(1) 1 1/4" (1.25"-31.8mm) Fiber (3) 1 5/8" (1.63"-41.3mm) Fiber	T-MOBILE

### Proposed Equipment

Elev. <sup>1</sup> (ft)	Qty	Antenna	Mount Type	Lines	Carrier
108.0	3	Ericsson Radio 4449 B71 B85A	Triangular Platform with Handrails	(3) 1 5/8" Hybriflex	T-MOBILE
	3	RFS APXVAARR24_43-U-NA20			

<sup>1</sup>Contracted elevations are shown for appurtenances within contracted installation tolerances. Appurtenances outside of contract limits are shown at installed elevations.

Install proposed lines inside the pole shaft.

### Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Anchor Bolts	31%	Pass
Shaft	35%	Pass
Base Plate	6%	Pass

### Foundations

Reaction Component	Analysis Reactions	% of Usage
Moment (Kips-Ft)	1,272.7	31%
Axial (Kips)	26.3	10%
Shear (Kips)	17.5	21%

The structure base reactions resulting from this analysis were found to be acceptable through analysis based on geotechnical and foundation information, therefore no modification or reinforcement of the foundation will be required.

### Deflection and Sway\*

Antenna Elevation (ft)	Antenna	Carrier	Deflection (ft)	Sway (Rotation) (°)
108.0	Ericsson Radio 4449 B71 B85A	T-MOBILE	0.325	0.292
	Ericsson AIR 21, 1.3 M, B2A B4P			
	Ericsson AIR 21, 1.3M, B4A B2P			
	RFS APXVAARR24_43-U-NA20			

\*Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-H



## **Standard Conditions**

All engineering services performed by A.T. Engineering Service, PLLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of A.T. Engineering Service, PLLC

It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete.

All assets of American Tower Corporation, its affiliates and subsidiaries (collectively "American Tower") are inspected at regular intervals. Based upon these inspections and in the absence of information to the contrary, American Tower assumes that all structures were constructed in accordance with the drawings and specifications.

Unless explicitly agreed by both the client and A.T. Engineering Service, PLLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.

## Job Information

Client : T-MOBILE

Pole : 284988

Code: ANSI/TIA-222-H

Location : GUILFORD CT, CT

Description :

Risk Category : II

Shape : 18 Sides

Exposure : C

Height : 109.00 (ft)


Topo Method : Method 1

Base Elev (ft): 0.00

Topographic Category : 1

Taper: 0.24499/in/ft

© 2007 - 2021 by ATC IP LLC. All rights reserved.



## Sections Properties

Shaft Section	Length (ft)	Diameter (in) Accross Flats Top Bottom	Thick (in)	Joint Type	Overlap Length (in)	Steel Shape	Grade	
1	52.740	42.53	55.45	0.313	0.000	18 Sides	65	
2	20.000	39.76	44.66	0.313	Slip Joint	73.688	18 Sides	65
3	48.130	29.87	41.66	0.250	Slip Joint	68.750	18 Sides	65

## Discrete Appurtenance

Attach Elev (ft)	Force Elev (ft)	Qty	Description
108.000	108.000	3	Ericsson KRY 112 489/2
108.000	108.000	1	Generic Heavy Platform with
108.000	108.000	3	RFS APXVAARR24_43-U-NA20
108.000	108.000	3	Ericsson AIR 21, 1.3M, B4A B2P
108.000	108.000	3	Ericsson AIR 21, 1.3 M, B2A B4
108.000	108.000	3	Ericsson Radio 4449 B71 B85A

## Linear Appurtenance

Elev (ft) From	To	Description	Exposed To Wind
0.000	108.0	1 5/8" Coax	No
0.000	108.0	1 5/8" Hybriflex	No

## Load Cases

1.2D + 1.0W	122 mph with No Ice
0.9D + 1.0W	122 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 1.00 in Radial Ice
1.2D + 1.0Ev + 1.0Eh	Seismic
0.9D - 1.0Ev + 1.0Eh	Seismic (Reduced DL)
1.0D + 1.0W	Serviceability 60 mph

## Reactions


Load Case	Moment (kip-ft)	Shear (kip)	Axial (kip)
1.2D + 1.0W	1272.73	17.48	26.34
0.9D + 1.0W	1268.12	17.48	19.75
1.2D + 1.0Di + 1.0Wi	320.74	4.60	34.81
1.2D + 1.0Ev + 1.0Eh	101.53	1.17	25.98
0.9D - 1.0Ev + 1.0Eh	101.08	1.17	18.11
1.0D + 1.0W	274.77	3.78	21.96

## Dish Deflections

Load Case	Attach Elev (ft)	Deflection (in)	Rotation (deg)
	0.00	0.000	0.000

Load Case : 1.2D + 1.0W

Max Ratio 34.94% at 0.0 ft



---

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:15 PM

Customer: T-MOBILE

---

### Analysis Parameters

Location :	New Haven County, CT	Height (ft) :	109
Code :	ANSI/TIA-222-H	Base Diameter (in) :	55.46
Shape :	18 Sides	Top Diameter (in) :	29.88
Pole Type :	Taper	Taper (in/ft) :	0.245
Pole Manufacturer :	Nello Corp	Rotation (deg) :	0.00
Kd (non-service) :	0.95	Ke :	1.00

---

### Ice & Wind Parameters

Exposure Category:	C	Design Wind Speed Without Ice:	122 mph
Risk Category:	II	Design Wind Speed With Ice:	50 mph
Topographic Factor Procedure:	Method 1	Operational Wind Speed:	60 mph
Topographic Category:	1	Design Ice Thickness:	1.00 in
Crest Height:	0 ft	HMSL:	51.00 ft

---

### Seismic Parameters

Analysis Method:	Equivalent Lateral Force Method			
Site Class:	D - Stiff Soil			
Period Based on Rayleigh Method (sec):	1.20			
T <sub>L</sub> (sec):	6	p:	1	C <sub>s</sub> :
S <sub>s</sub> :	0.175	S <sub>1</sub> :	0.060	C <sub>s</sub> Max:
F <sub>a</sub> :	1.600	F <sub>v</sub> :	2.400	C <sub>s</sub> Min:
S <sub>ds</sub> :	0.187	S <sub>d1</sub> :	0.096	

---

### Load Cases

1.2D + 1.0W	122 mph with No Ice
0.9D + 1.0W	122 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 1.00 in Radial Ice
1.2D + 1.0Ev + 1.0Eh	Seismic
0.9D - 1.0Ev + 1.0Eh	Seismic (Reduced DL)
1.0D + 1.0W	Serviceability 60 mph

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:15 PM

Customer: T-MOBILE

**Shaft Section Properties**

Sect Info	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Joint Len (in)	Weight (lb)	Bottom						Top						Taper (in/ft)
							Dia (in)	Elev (ft)	Area (in <sup>2</sup> )	Ix (in <sup>4</sup> )	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (in <sup>2</sup> )	Ix (in <sup>4</sup> )	W/t Ratio	D/t Ratio	
1-18	52.740	0.3125	65		0.00	8,665	55.45	0.00	54.69	21012.4	29.53	177.46	42.53	52.74	41.88	9432.2	22.24	136.11	0.244999
2-18	20.000	0.3125	65	Slip	73.69	2,828	44.66	46.60	43.99	10932.6	23.44	142.93	39.76	66.60	39.13	7694.6	20.67	127.25	0.244999
3-18	48.130	0.2500	65	Slip	68.75	4,616	41.66	60.87	32.86	7122.7	27.63	166.67	29.87	109.00	23.51	2606.8	19.31	119.50	0.244999
Shaft Weight						16,110													

**Discrete Appurtenance Properties**

Attach Elev (ft)	Description	Qty	Ka	Vert Ecc (ft)	No Ice		Ice		Orientation Factor	Weight (lb)	EPAA (sf)	Orientation Factor
					Weight (lb)	EPAA (sf)	Weight (lb)	EPAA (sf)				
108.00	Ericsson KRY 112 489/2	3	0.75	0.000	15.40	0.650	0.50	26.80	1.044	0.50		
108.00	Ericsson Radio 4449 B71 B85A	3	0.75	0.000	75.00	1.650	0.50	113.82	2.198	0.50		
108.00	Ericsson AIR 21, 1.3 M, B2A B4P	3	0.75	0.000	83.00	6.049	0.71	177.21	7.445	0.71		
108.00	Ericsson AIR 21, 1.3M, B4A B2P	3	0.75	0.000	81.50	6.092	0.70	175.37	7.489	0.70		
108.00	RFS APXVAARR24_43-U-NA20	3	0.75	0.000	127.90	20.243	0.63	381.33	22.637	0.63		
108.00	Generic Heavy Platform with	1	1.00	0.000	3,750.00	59.800	1.00	5,487.05	76.743	1.00		
Totals	Num Loadings:6	16			4,898.40					8,110.64		

**Linear Appurtenance Properties**

## Load Case Azimuth (deg) :

Elev From (ft)	Elev To (ft)	Coax Dia (in)	Coax Wt (lb/ft)	Max Coax / Flat Row	Dist Between Rows (in)	Dist Between Cols (in)	Dist Azimuth (deg)	Exposed Face (in)	From Wind	To Carrier
0.00	108.00	6	1 5/8" Coax	N	0	0.00	0.00	0	0.00	N T-MOBILE
0.00	108.00	3	1 5/8" Hybriflex	N	0	0.00	0.00	0	0.00	N T-MOBILE

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:15 PM

Customer: T-MOBILE

Segment Properties (Max Len : 5. ft)

Seg Top Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in <sup>2</sup> )	Ix (in <sup>4</sup> )	W/t Ratio	D/t Ratio	F'y (ksi)	S (in <sup>3</sup> )	Z (in <sup>3</sup> )	Weight (lb)
0.00		0.3125	55.456	54.693	21,012.4	29.53	177.46	66.7	746.3	0.0	0.0
5.00		0.3125	54.231	53.478	19,642.9	28.84	173.54	67.5	713.4	0.0	920.2
10.00		0.3125	53.006	52.263	18,334.3	28.15	169.62	68.3	681.3	0.0	899.5
15.00		0.3125	51.781	51.048	17,085.1	27.45	165.70	69.1	649.9	0.0	878.9
20.00		0.3125	50.556	49.833	15,894.0	26.76	161.78	69.9	619.2	0.0	858.2
25.00		0.3125	49.331	48.618	14,759.5	26.07	157.86	70.7	589.3	0.0	837.5
30.00		0.3125	48.106	47.403	13,680.4	25.38	153.94	71.5	560.1	0.0	816.9
35.00		0.3125	46.881	46.188	12,655.2	24.69	150.02	72.4	531.7	0.0	796.2
40.00		0.3125	45.656	44.973	11,682.5	24.00	146.10	73.2	504.0	0.0	775.5
45.00		0.3125	44.431	43.758	10,761.1	23.31	142.18	74.0	477.0	0.0	754.8
46.60	Bot - Section 2	0.3125	44.039	43.370	10,476.9	23.09	140.93	74.2	468.6	0.0	237.1
50.00		0.3125	43.206	42.543	9,889.3	22.62	138.26	74.8	450.8	0.0	1,001.3
52.74	Top - Section 1	0.3125	43.160	42.497	9,857.3	22.59	138.11	74.8	449.8	0.0	792.9
55.00		0.3125	42.606	41.948	9,480.1	22.28	136.34	75.2	438.3	0.0	324.7
60.00		0.3125	41.381	40.733	8,680.0	21.59	132.42	76.0	413.1	0.0	703.4
60.87	Bot - Section 3	0.3125	41.168	40.522	8,545.5	21.47	131.74	76.2	408.8	0.0	120.3
65.00		0.3125	40.156	39.518	7,926.2	20.89	128.50	76.8	388.8	0.0	1,018.6
66.60	Top - Section 2	0.2500	40.264	31.750	6,422.8	26.64	161.06	70.1	314.2	0.0	387.7
70.00		0.2500	39.431	31.089	6,029.9	26.05	157.72	70.8	301.2	0.0	363.6
75.00		0.2500	38.206	30.117	5,481.8	25.18	152.82	71.8	282.6	0.0	520.7
80.00		0.2500	36.981	29.145	4,968.0	24.32	147.92	72.8	264.6	0.0	504.1
85.00		0.2500	35.756	28.173	4,487.3	23.46	143.02	73.8	247.2	0.0	487.6
90.00		0.2500	34.531	27.201	4,038.7	22.59	138.12	74.8	230.4	0.0	471.1
95.00		0.2500	33.306	26.229	3,621.1	21.73	133.22	75.8	214.1	0.0	454.5
100.0		0.2500	32.081	25.257	3,233.2	20.86	128.32	76.9	198.5	0.0	438.0
105.0		0.2500	30.856	24.285	2,874.1	20.00	123.42	77.9	183.5	0.0	421.5
108.0		0.2500	30.121	23.702	2,672.0	19.48	120.48	78.5	174.7	0.0	244.9
109.0		0.2500	29.876	23.507	2,606.8	19.31	119.50	78.7	171.9	0.0	80.3
											16,109.9

Load Case: 1.2D + 1.0W

122 mph with No Ice

18 Iterations

Gust Response Factor :1.10

Dead Load Factor :1.20

Wind Load Factor :1.00

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX	Dead Load	Wind FX	Torsion MY	Moment MZ	Dead Load	Wind FX	Dead Load	Wind FX	Dead Load	Torsion MY	
		(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb)	
0.00		286.1	0.0					0.0	0.0	286.1	0.0	0.0	
5.00		565.8	1,104.3					0.0	52.9	565.8	1,157.2	0.0	
10.00		553.1	1,079.4					0.0	52.9	553.1	1,132.4	0.0	
15.00		548.7	1,054.6					0.0	52.9	548.7	1,107.6	0.0	
20.00		558.8	1,029.8					0.0	52.9	558.8	1,082.8	0.0	
25.00		571.8	1,005.0					0.0	52.9	571.8	1,057.9	0.0	
30.00		579.6	980.2					0.0	52.9	579.6	1,033.1	0.0	
35.00		583.5	955.4					0.0	52.9	583.5	1,008.3	0.0	
40.00		584.6	930.6					0.0	52.9	584.6	983.5	0.0	
45.00		385.5	905.8					0.0	52.9	385.5	958.7	0.0	
46.60	Bot - Section 2	293.8	284.5					0.0	16.9	293.8	301.4	0.0	
50.00		361.5	1,201.6					0.0	36.0	361.5	1,237.6	0.0	
52.74	Top - Section 1	293.1	951.5					0.0	29.0	293.1	980.5	0.0	
55.00		422.5	389.6					0.0	23.9	422.5	413.6	0.0	
60.00		340.5	844.0					0.0	52.9	340.5	897.0	0.0	
60.87	Bot - Section 3	289.8	144.4					0.0	9.2	289.8	153.6	0.0	
65.00		331.6	1,222.3					0.0	43.7	331.6	1,266.0	0.0	
66.60	Top - Section 2	286.3	465.2					0.0	16.9	286.3	482.1	0.0	
70.00		476.1	436.3					0.0	36.0	476.1	472.3	0.0	
75.00		558.6	624.8					0.0	52.9	558.6	677.7	0.0	
80.00		548.1	605.0					0.0	52.9	548.1	657.9	0.0	
85.00		536.7	585.1					0.0	52.9	536.7	638.0	0.0	
90.00		524.6	565.3					0.0	52.9	524.6	618.2	0.0	
95.00		511.8	545.4					0.0	52.9	511.8	598.4	0.0	
100.00		498.3	525.6					0.0	52.9	498.3	578.5	0.0	
105.00		389.7	505.7					0.0	52.9	389.7	558.7	0.0	
108.00	Appurtenance(s)	184.9	293.9	5,640.9	0.0	0.0	5,878.1		0.0	31.8	5,825.8	6,203.8	0.0
109.00		40.9	96.4						0.0	0.0	40.9	96.4	0.0
								Totals:		17,747.2	26,353.0	0.00	0.00

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:16 PM

Customer: T-MOBILE

Load Case: 1.2D + 1.0W

122 mph with No Ice

18 Iterations

Gust Response Factor :1.10

Dead Load Factor :1.20

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-26.34	-17.48	0.00	-1,272.73	0.00	1,272.73	3,281.83	959.87	4,780.50	3,731.72	0.00	0.00	0.349
5.00	-25.16	-16.95	0.00	-1,185.33	0.00	1,185.33	3,248.05	938.55	4,570.48	3,610.80	0.05	-0.08	0.336
10.00	-24.00	-16.43	0.00	-1,100.57	0.00	1,100.57	3,212.50	917.22	4,365.18	3,489.67	0.18	-0.17	0.323
15.00	-22.88	-15.91	0.00	-1,018.43	0.00	1,018.43	3,175.17	895.90	4,164.60	3,368.46	0.40	-0.25	0.310
20.00	-21.77	-15.38	0.00	-938.88	0.00	938.88	3,136.05	874.58	3,968.73	3,247.31	0.70	-0.33	0.296
25.00	-20.70	-14.83	0.00	-862.00	0.00	862.00	3,095.17	853.25	3,777.58	3,126.34	1.09	-0.41	0.283
30.00	-19.65	-14.27	0.00	-787.87	0.00	787.87	3,052.50	831.93	3,591.15	3,005.71	1.56	-0.49	0.269
35.00	-18.63	-13.70	0.00	-716.54	0.00	716.54	3,008.05	810.61	3,409.44	2,885.53	2.12	-0.57	0.255
40.00	-17.63	-13.13	0.00	-648.05	0.00	648.05	2,961.83	789.28	3,232.44	2,765.96	2.76	-0.64	0.241
45.00	-16.67	-12.74	0.00	-582.42	0.00	582.42	2,913.83	767.96	3,060.17	2,647.11	3.47	-0.72	0.226
46.60	-16.36	-12.46	0.00	-562.04	0.00	562.04	2,898.10	761.14	3,006.05	2,609.27	3.72	-0.74	0.221
50.00	-15.12	-12.09	0.00	-519.68	0.00	519.68	2,864.05	746.64	2,892.61	2,529.14	4.27	-0.79	0.211
52.74	-14.14	-11.79	0.00	-486.55	0.00	486.55	2,862.14	745.83	2,886.36	2,524.70	4.73	-0.83	0.198
55.00	-13.72	-11.38	0.00	-459.90	0.00	459.90	2,839.02	736.19	2,812.26	2,471.71	5.14	-0.87	0.191
60.00	-12.82	-11.03	0.00	-403.03	0.00	403.03	2,786.60	714.87	2,651.72	2,355.29	6.08	-0.93	0.176
60.87	-12.67	-10.74	0.00	-393.43	0.00	393.43	2,777.29	711.16	2,624.27	2,335.14	6.25	-0.94	0.173
65.00	-11.40	-10.40	0.00	-349.06	0.00	349.06	2,732.39	693.55	2,495.91	2,240.06	7.09	-0.99	0.160
66.60	-10.92	-10.11	0.00	-332.43	0.00	332.43	2,002.34	557.21	2,013.77	1,651.20	7.42	-1.01	0.207
70.00	-10.45	-9.63	0.00	-298.05	0.00	298.05	1,979.98	545.61	1,930.79	1,598.56	8.16	-1.05	0.192
75.00	-9.77	-9.07	0.00	-249.88	0.00	249.88	1,945.62	528.55	1,811.96	1,521.39	9.30	-1.12	0.170
80.00	-9.11	-8.52	0.00	-204.51	0.00	204.51	1,909.49	511.49	1,696.90	1,444.63	10.50	-1.18	0.147
85.00	-8.48	-7.98	0.00	-161.91	0.00	161.91	1,871.57	494.44	1,585.61	1,368.40	11.76	-1.23	0.123
90.00	-7.87	-7.45	0.00	-122.02	0.00	122.02	1,831.88	477.38	1,478.10	1,292.85	13.07	-1.27	0.099
95.00	-7.28	-6.92	0.00	-84.79	0.00	84.79	1,790.40	460.32	1,374.36	1,218.10	14.43	-1.31	0.074
100.00	-6.71	-6.42	0.00	-50.16	0.00	50.16	1,747.15	443.26	1,274.40	1,144.29	15.81	-1.34	0.048
105.00	-6.16	-6.01	0.00	-18.08	0.00	18.08	1,702.13	426.20	1,178.21	1,071.56	17.22	-1.35	0.021
108.00	-0.10	-0.04	0.00	-0.04	0.00	0.04	1,674.26	415.97	1,122.31	1,028.50	18.07	-1.35	0.000
109.00	0.00	-0.04	0.00	0.00	0.00	0.00	1,664.82	412.55	1,103.97	1,014.25	18.36	-1.35	0.000

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:16 PM

Customer: T-MOBILE

Load Case: 0.9D + 1.0W

122 mph with No Ice (Reduced DL)

18 Iterations

Gust Response Factor :1.10

Dead Load Factor :0.90

Wind Load Factor :1.00

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces			Sum of Forces				
		Wind FX	Dead Load	Wind FX	Torsion MY	Moment MZ	Dead Load	Wind FX	Dead Load	Wind FX	Dead Load	Torsion MY	Moment MZ	
		(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb)	
0.00		286.1	0.0					0.0	0.0	286.1	0.0	0.0	0.0	
5.00		565.8	828.2					0.0	39.7	565.8	867.9	0.0	0.0	
10.00		553.1	809.6					0.0	39.7	553.1	849.3	0.0	0.0	
15.00		548.7	791.0					0.0	39.7	548.7	830.7	0.0	0.0	
20.00		558.8	772.4					0.0	39.7	558.8	812.1	0.0	0.0	
25.00		571.8	753.8					0.0	39.7	571.8	793.5	0.0	0.0	
30.00		579.6	735.2					0.0	39.7	579.6	774.9	0.0	0.0	
35.00		583.5	716.6					0.0	39.7	583.5	756.3	0.0	0.0	
40.00		584.6	698.0					0.0	39.7	584.6	737.6	0.0	0.0	
45.00		385.5	679.4					0.0	39.7	385.5	719.0	0.0	0.0	
46.60	Bot - Section 2	293.8	213.4					0.0	12.7	293.8	226.1	0.0	0.0	
50.00		361.5	901.2					0.0	27.0	361.5	928.2	0.0	0.0	
52.74	Top - Section 1	293.1	713.6					0.0	21.8	293.1	735.3	0.0	0.0	
55.00		422.5	292.2					0.0	17.9	422.5	310.2	0.0	0.0	
60.00		340.5	633.0					0.0	39.7	340.5	672.7	0.0	0.0	
60.87	Bot - Section 3	289.8	108.3					0.0	6.9	289.8	115.2	0.0	0.0	
65.00		331.6	916.7					0.0	32.8	331.6	949.5	0.0	0.0	
66.60	Top - Section 2	286.3	348.9					0.0	12.7	286.3	361.6	0.0	0.0	
70.00		476.1	327.2					0.0	27.0	476.1	354.2	0.0	0.0	
75.00		558.6	468.6					0.0	39.7	558.6	508.3	0.0	0.0	
80.00		548.1	453.7					0.0	39.7	548.1	493.4	0.0	0.0	
85.00		536.7	438.8					0.0	39.7	536.7	478.5	0.0	0.0	
90.00		524.6	424.0					0.0	39.7	524.6	463.6	0.0	0.0	
95.00		511.8	409.1					0.0	39.7	511.8	448.8	0.0	0.0	
100.00		498.3	394.2					0.0	39.7	498.3	433.9	0.0	0.0	
105.00		389.7	379.3					0.0	39.7	389.7	419.0	0.0	0.0	
108.00	Appurtenance(s)	184.9	220.4	5,640.9	0.0	0.0	4,408.6		0.0	23.8	5,825.8	4,652.8	0.0	0.0
109.00		40.9	72.3					0.0	0.0	40.9	72.3	0.0	0.0	
								Totals:			17,747.2	19,764.7	0.00	0.00

Load Case: 0.9D + 1.0W

122 mph with No Ice (Reduced DL)

18 Iterations

Gust Response Factor :1.10

Dead Load Factor :0.90

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-19.75	-17.48	0.00	-1,268.12	0.00	1,268.12	3,281.83	959.87	4,780.50	3,731.72	0.00	0.00	0.346
5.00	-18.86	-16.94	0.00	-1,180.74	0.00	1,180.74	3,248.05	938.55	4,570.48	3,610.80	0.05	-0.08	0.333
10.00	-17.99	-16.41	0.00	-1,096.06	0.00	1,096.06	3,212.50	917.22	4,365.18	3,489.67	0.18	-0.17	0.320
15.00	-17.14	-15.88	0.00	-1,014.02	0.00	1,014.02	3,175.17	895.90	4,164.60	3,368.46	0.39	-0.25	0.307
20.00	-16.31	-15.34	0.00	-934.62	0.00	934.62	3,136.05	874.58	3,968.73	3,247.31	0.70	-0.33	0.293
25.00	-15.50	-14.78	0.00	-857.92	0.00	857.92	3,095.17	853.25	3,777.58	3,126.34	1.09	-0.41	0.280
30.00	-14.71	-14.22	0.00	-784.00	0.00	784.00	3,052.50	831.93	3,591.15	3,005.71	1.56	-0.49	0.266
35.00	-13.94	-13.65	0.00	-712.90	0.00	712.90	3,008.05	810.61	3,409.44	2,885.53	2.11	-0.57	0.252
40.00	-13.19	-13.07	0.00	-644.67	0.00	644.67	2,961.83	789.28	3,232.44	2,765.96	2.74	-0.64	0.238
45.00	-12.46	-12.69	0.00	-579.30	0.00	579.30	2,913.83	767.96	3,060.17	2,647.11	3.46	-0.72	0.223
46.60	-12.23	-12.40	0.00	-559.01	0.00	559.01	2,898.10	761.14	3,006.05	2,609.27	3.70	-0.74	0.219
50.00	-11.30	-12.04	0.00	-516.84	0.00	516.84	2,864.05	746.64	2,892.61	2,529.14	4.25	-0.79	0.209
52.74	-10.56	-11.74	0.00	-483.86	0.00	483.86	2,862.14	745.83	2,886.36	2,524.70	4.71	-0.83	0.196
55.00	-10.25	-11.32	0.00	-457.34	0.00	457.34	2,839.02	736.19	2,812.26	2,471.71	5.11	-0.86	0.189
60.00	-9.57	-10.98	0.00	-400.73	0.00	400.73	2,786.60	714.87	2,651.72	2,355.29	6.05	-0.93	0.174
60.87	-9.46	-10.69	0.00	-391.18	0.00	391.18	2,777.29	711.16	2,624.27	2,335.14	6.22	-0.94	0.171
65.00	-8.51	-10.35	0.00	-347.04	0.00	347.04	2,732.39	693.55	2,495.91	2,240.06	7.06	-0.99	0.158
66.60	-8.15	-10.06	0.00	-330.49	0.00	330.49	2,002.34	557.21	2,013.77	1,651.20	7.39	-1.01	0.205
70.00	-7.79	-9.58	0.00	-296.29	0.00	296.29	1,979.98	545.61	1,930.79	1,598.56	8.12	-1.05	0.190
75.00	-7.28	-9.02	0.00	-248.37	0.00	248.37	1,945.62	528.55	1,811.96	1,521.39	9.25	-1.11	0.167
80.00	-6.79	-8.47	0.00	-203.26	0.00	203.26	1,909.49	511.49	1,696.90	1,444.63	10.45	-1.17	0.145
85.00	-6.32	-7.93	0.00	-160.90	0.00	160.90	1,871.57	494.44	1,585.61	1,368.40	11.71	-1.22	0.121
90.00	-5.86	-7.40	0.00	-121.25	0.00	121.25	1,831.88	477.38	1,478.10	1,292.85	13.01	-1.27	0.097
95.00	-5.42	-6.88	0.00	-84.25	0.00	84.25	1,790.40	460.32	1,374.36	1,218.10	14.36	-1.30	0.072
100.00	-5.00	-6.37	0.00	-49.84	0.00	49.84	1,747.15	443.26	1,274.40	1,144.29	15.74	-1.33	0.047
105.00	-4.59	-5.98	0.00	-17.97	0.00	17.97	1,702.13	426.20	1,178.21	1,071.56	17.14	-1.34	0.020
108.00	-0.07	-0.04	0.00	-0.04	0.00	0.04	1,674.26	415.97	1,122.31	1,028.50	17.99	-1.35	0.000
109.00	0.00	-0.04	0.00	0.00	0.00	0.00	1,664.82	412.55	1,103.97	1,014.25	18.27	-1.35	0.000

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:16 PM

Customer: T-MOBILE

Load Case: 1.2D + 1.0Di + 1.0Wi

50 mph with 1.00 in Radial Ice

17 Iterations

Gust Response Factor :1.10

Ice Dead Load Factor :1.00

Dead Load Factor :1.20

Ice Importance Factor :1.00

Wind Load Factor :1.00

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces						
		Wind FX	Dead Load	Wind FX	Torsion MY	Moment MZ	Dead Load	Wind FX	Dead Load	Wind FX	Dead Load	Torsion MY			
		(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb)			
0.00		81.2	0.0				0.0	0.0	81.2	0.0	0.0	0.0			
5.00		160.9	1,370.5				0.0	52.9	160.9	1,423.4	0.0	0.0			
10.00		157.7	1,370.5				0.0	52.9	157.7	1,423.4	0.0	0.0			
15.00		156.8	1,354.2				0.0	52.9	156.8	1,407.1	0.0	0.0			
20.00		160.0	1,332.6				0.0	52.9	160.0	1,385.5	0.0	0.0			
25.00		164.0	1,308.3				0.0	52.9	164.0	1,361.2	0.0	0.0			
30.00		166.5	1,282.2				0.0	52.9	166.5	1,335.1	0.0	0.0			
35.00		167.9	1,254.9				0.0	52.9	167.9	1,307.8	0.0	0.0			
40.00		168.5	1,226.7				0.0	52.9	168.5	1,279.7	0.0	0.0			
45.00		111.2	1,197.9				0.0	52.9	111.2	1,250.8	0.0	0.0			
46.60	Bot - Section 2	84.9	377.8				0.0	16.9	84.9	394.8	0.0	0.0			
50.00		104.5	1,400.2				0.0	36.0	104.5	1,436.2	0.0	0.0			
52.74	Top - Section 1	84.8	1,110.1				0.0	29.0	84.8	1,139.1	0.0	0.0			
55.00		122.4	519.5				0.0	23.9	122.4	543.4	0.0	0.0			
60.00		98.7	1,125.1				0.0	52.9	98.7	1,178.0	0.0	0.0			
60.87	Bot - Section 3	84.1	193.3				0.0	9.2	84.1	202.5	0.0	0.0			
65.00		96.3	1,452.6				0.0	43.7	96.3	1,496.3	0.0	0.0			
66.60	Top - Section 2	83.2	553.9				0.0	16.9	83.2	570.9	0.0	0.0			
70.00		138.6	621.9				0.0	36.0	138.6	657.9	0.0	0.0			
75.00		162.9	891.1				0.0	52.9	162.9	944.0	0.0	0.0			
80.00		160.1	864.7				0.0	52.9	160.1	917.6	0.0	0.0			
85.00		157.2	838.1				0.0	52.9	157.2	891.0	0.0	0.0			
90.00		154.0	811.3				0.0	52.9	154.0	864.3	0.0	0.0			
95.00		150.6	784.4				0.0	52.9	150.6	837.3	0.0	0.0			
100.00		147.0	757.3				0.0	52.9	147.0	810.2	0.0	0.0			
105.00		115.2	730.1				0.0	52.9	115.2	783.0	0.0	0.0			
108.00	Appurtenance(s)	55.5	425.9	1,169.2	0.0	0.0	8,376.1	0.0	31.8	1,224.8	8,833.7	0.0	0.0		
109.00		12.9	140.1					0.0	0.0	12.9	140.1	0.0	0.0		
Totals:												4,676.89	34,814.1	0.00	0.00

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:17 PM

Customer: T-MOBILE

Load Case: 1.2D + 1.0Di + 1.0Wi

50 mph with 1.00 in Radial Ice

17 Iterations

Gust Response Factor :1.10

Ice Dead Load Factor :1.00

Dead Load Factor :1.20

Ice Importance Factor :1.00

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-34.81	-4.60	0.00	-320.74	0.00	320.74	3,281.83	959.87	4,780.50	3,731.72	0.00	0.00	0.097
5.00	-33.39	-4.45	0.00	-297.73	0.00	297.73	3,248.05	938.55	4,570.48	3,610.80	0.01	-0.02	0.093
10.00	-31.96	-4.31	0.00	-275.47	0.00	275.47	3,212.50	917.22	4,365.18	3,489.67	0.04	-0.04	0.089
15.00	-30.55	-4.16	0.00	-253.94	0.00	253.94	3,175.17	895.90	4,164.60	3,368.46	0.10	-0.06	0.085
20.00	-29.17	-4.01	0.00	-233.14	0.00	233.14	3,136.05	874.58	3,968.73	3,247.31	0.18	-0.08	0.081
25.00	-27.81	-3.85	0.00	-213.11	0.00	213.11	3,095.17	853.25	3,777.58	3,126.34	0.27	-0.10	0.077
30.00	-26.47	-3.69	0.00	-193.86	0.00	193.86	3,052.50	831.93	3,591.15	3,005.71	0.39	-0.12	0.073
35.00	-25.16	-3.53	0.00	-175.40	0.00	175.40	3,008.05	810.61	3,409.44	2,885.53	0.53	-0.14	0.069
40.00	-23.88	-3.36	0.00	-157.77	0.00	157.77	2,961.83	789.28	3,232.44	2,765.96	0.69	-0.16	0.065
45.00	-22.63	-3.25	0.00	-140.95	0.00	140.95	2,913.83	767.96	3,060.17	2,647.11	0.87	-0.18	0.061
46.60	-22.23	-3.17	0.00	-135.74	0.00	135.74	2,898.10	761.14	3,006.05	2,609.27	0.93	-0.18	0.060
50.00	-20.80	-3.07	0.00	-124.96	0.00	124.96	2,864.05	746.64	2,892.61	2,529.14	1.06	-0.20	0.057
52.74	-19.66	-2.98	0.00	-116.56	0.00	116.56	2,862.14	745.83	2,886.36	2,524.70	1.18	-0.21	0.053
55.00	-19.12	-2.86	0.00	-109.83	0.00	109.83	2,839.02	736.19	2,812.26	2,471.71	1.28	-0.21	0.051
60.00	-17.94	-2.76	0.00	-95.53	0.00	95.53	2,786.60	714.87	2,651.72	2,355.29	1.51	-0.23	0.047
60.87	-17.74	-2.68	0.00	-93.13	0.00	93.13	2,777.29	711.16	2,624.27	2,335.14	1.55	-0.23	0.046
65.00	-16.24	-2.58	0.00	-82.08	0.00	82.08	2,732.39	693.55	2,495.91	2,240.06	1.76	-0.24	0.043
66.60	-15.67	-2.49	0.00	-77.96	0.00	77.96	2,002.34	557.21	2,013.77	1,651.20	1.84	-0.25	0.055
70.00	-15.01	-2.35	0.00	-69.49	0.00	69.49	1,979.98	545.61	1,930.79	1,598.56	2.02	-0.26	0.051
75.00	-14.07	-2.19	0.00	-57.72	0.00	57.72	1,945.62	528.55	1,811.96	1,521.39	2.30	-0.27	0.045
80.00	-13.15	-2.03	0.00	-46.76	0.00	46.76	1,909.49	511.49	1,696.90	1,444.63	2.59	-0.29	0.039
85.00	-12.26	-1.87	0.00	-36.62	0.00	36.62	1,871.57	494.44	1,585.61	1,368.40	2.90	-0.30	0.033
90.00	-11.40	-1.71	0.00	-27.28	0.00	27.28	1,831.88	477.38	1,478.10	1,292.85	3.21	-0.31	0.027
95.00	-10.56	-1.56	0.00	-18.71	0.00	18.71	1,790.40	460.32	1,374.36	1,218.10	3.54	-0.32	0.021
100.00	-9.75	-1.41	0.00	-10.92	0.00	10.92	1,747.15	443.26	1,274.40	1,144.29	3.88	-0.32	0.015
105.00	-8.97	-1.29	0.00	-3.88	0.00	3.88	1,702.13	426.20	1,178.21	1,071.56	4.21	-0.33	0.009
108.00	-0.14	-0.01	0.00	-0.01	0.00	0.01	1,674.26	415.97	1,122.31	1,028.50	4.42	-0.33	0.000
109.00	0.00	-0.01	0.00	0.00	0.00	0.00	1,664.82	412.55	1,103.97	1,014.25	4.49	-0.33	0.000

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:17 PM

Customer: T-MOBILE

Load Case: 1.0D + 1.0W

Serviceability 60 mph

17 Iterations

Gust Response Factor :1.10

Dead Load Factor :1.00

Wind Load Factor :1.00

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX	Dead Load	Wind FX	Torsion MY	Moment MZ	Dead Load	Wind FX	Dead Load	Wind FX	Dead Load	Torsion MY	
		(lb)	(lb)	(lb)	(lb-ft)	(lb-ft)	(lb)	(lb)	(lb)	(lb)	(lb)	(lb)	
0.00		61.9	0.0					0.0	0.0	61.9	0.0	0.0	
5.00		122.5	920.2					0.0	44.1	122.5	964.3	0.0	
10.00		119.7	899.5					0.0	44.1	119.7	943.6	0.0	
15.00		118.8	878.9					0.0	44.1	118.8	923.0	0.0	
20.00		120.9	858.2					0.0	44.1	120.9	902.3	0.0	
25.00		123.7	837.5					0.0	44.1	123.7	881.6	0.0	
30.00		125.4	816.9					0.0	44.1	125.4	861.0	0.0	
35.00		126.3	796.2					0.0	44.1	126.3	840.3	0.0	
40.00		126.5	775.5					0.0	44.1	126.5	819.6	0.0	
45.00		83.4	754.8					0.0	44.1	83.4	798.9	0.0	
46.60	Bot - Section 2	63.6	237.1					0.0	14.1	63.6	251.2	0.0	
50.00		78.2	1,001.3					0.0	30.0	78.2	1,031.3	0.0	
52.74	Top - Section 1	63.4	792.9					0.0	24.2	63.4	817.1	0.0	
55.00		91.4	324.7					0.0	19.9	91.4	344.6	0.0	
60.00		73.7	703.4					0.0	44.1	73.7	747.5	0.0	
60.87	Bot - Section 3	62.7	120.3					0.0	7.7	62.7	128.0	0.0	
65.00		71.8	1,018.6					0.0	36.4	71.8	1,055.0	0.0	
66.60	Top - Section 2	62.0	387.7					0.0	14.1	62.0	401.8	0.0	
70.00		103.0	363.6					0.0	30.0	103.0	393.6	0.0	
75.00		120.9	520.7					0.0	44.1	120.9	564.8	0.0	
80.00		118.6	504.1					0.0	44.1	118.6	548.2	0.0	
85.00		116.2	487.6					0.0	44.1	116.2	531.7	0.0	
90.00		113.5	471.1					0.0	44.1	113.5	515.2	0.0	
95.00		110.8	454.5					0.0	44.1	110.8	498.6	0.0	
100.00		107.8	438.0					0.0	44.1	107.8	482.1	0.0	
105.00		84.3	421.5					0.0	44.1	84.3	465.6	0.0	
108.00	Appurtenance(s)	40.0	244.9	1,220.7	0.0	0.0	4,898.4		0.0	26.5	1,260.8	5,169.8	0.0
109.00		8.9	80.3						0.0	0.0	8.9	80.3	0.0
								Totals:		3,840.69	21,960.8	0.00	0.00

Load Case: 1.0D + 1.0W

Serviceability 60 mph

17 Iterations

Gust Response Factor :1.10

Dead Load Factor :1.00

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-21.96	-3.78	0.00	-274.77	0.00	274.77	3,281.83	959.87	4,780.50	3,731.72	0.00	0.00	0.080
5.00	-20.99	-3.67	0.00	-255.86	0.00	255.86	3,248.05	938.55	4,570.48	3,610.80	0.01	-0.02	0.077
10.00	-20.05	-3.55	0.00	-237.53	0.00	237.53	3,212.50	917.22	4,365.18	3,489.67	0.04	-0.04	0.074
15.00	-19.13	-3.44	0.00	-219.77	0.00	219.77	3,175.17	895.90	4,164.60	3,368.46	0.09	-0.05	0.071
20.00	-18.22	-3.32	0.00	-202.58	0.00	202.58	3,136.05	874.58	3,968.73	3,247.31	0.15	-0.07	0.068
25.00	-17.34	-3.20	0.00	-185.97	0.00	185.97	3,095.17	853.25	3,777.58	3,126.34	0.24	-0.09	0.065
30.00	-16.48	-3.08	0.00	-169.96	0.00	169.96	3,052.50	831.93	3,591.15	3,005.71	0.34	-0.11	0.062
35.00	-15.64	-2.96	0.00	-154.55	0.00	154.55	3,008.05	810.61	3,409.44	2,885.53	0.46	-0.12	0.059
40.00	-14.82	-2.83	0.00	-139.77	0.00	139.77	2,961.83	789.28	3,232.44	2,765.96	0.59	-0.14	0.056
45.00	-14.02	-2.75	0.00	-125.60	0.00	125.60	2,913.83	767.96	3,060.17	2,647.11	0.75	-0.16	0.052
46.60	-13.77	-2.69	0.00	-121.21	0.00	121.21	2,898.10	761.14	3,006.05	2,609.27	0.80	-0.16	0.051
50.00	-12.74	-2.61	0.00	-112.07	0.00	112.07	2,864.05	746.64	2,892.61	2,529.14	0.92	-0.17	0.049
52.74	-11.92	-2.54	0.00	-104.92	0.00	104.92	2,862.14	745.83	2,886.36	2,524.70	1.02	-0.18	0.046
55.00	-11.57	-2.45	0.00	-99.17	0.00	99.17	2,839.02	736.19	2,812.26	2,471.71	1.11	-0.19	0.044
60.00	-10.83	-2.38	0.00	-86.90	0.00	86.90	2,786.60	714.87	2,651.72	2,355.29	1.31	-0.20	0.041
60.87	-10.70	-2.32	0.00	-84.83	0.00	84.83	2,777.29	711.16	2,624.27	2,335.14	1.35	-0.20	0.040
65.00	-9.64	-2.24	0.00	-75.26	0.00	75.26	2,732.39	693.55	2,495.91	2,240.06	1.53	-0.21	0.037
66.60	-9.24	-2.18	0.00	-71.67	0.00	71.67	2,002.34	557.21	2,013.77	1,651.20	1.60	-0.22	0.048
70.00	-8.85	-2.08	0.00	-64.26	0.00	64.26	1,979.98	545.61	1,930.79	1,598.56	1.76	-0.23	0.045
75.00	-8.28	-1.96	0.00	-53.87	0.00	53.87	1,945.62	528.55	1,811.96	1,521.39	2.01	-0.24	0.040
80.00	-7.73	-1.84	0.00	-44.09	0.00	44.09	1,909.49	511.49	1,696.90	1,444.63	2.27	-0.25	0.035
85.00	-7.20	-1.72	0.00	-34.90	0.00	34.90	1,871.57	494.44	1,585.61	1,368.40	2.54	-0.26	0.029
90.00	-6.69	-1.61	0.00	-26.30	0.00	26.30	1,831.88	477.38	1,478.10	1,292.85	2.82	-0.27	0.024
95.00	-6.19	-1.49	0.00	-18.28	0.00	18.28	1,790.40	460.32	1,374.36	1,218.10	3.11	-0.28	0.018
100.00	-5.71	-1.38	0.00	-10.81	0.00	10.81	1,747.15	443.26	1,274.40	1,144.29	3.41	-0.29	0.013
105.00	-5.24	-1.30	0.00	-3.90	0.00	3.90	1,702.13	426.20	1,178.21	1,071.56	3.72	-0.29	0.007
108.00	-0.08	-0.01	0.00	-0.01	0.00	0.01	1,674.26	415.97	1,122.31	1,028.50	3.90	-0.29	0.000
109.00	0.00	-0.01	0.00	0.00	0.00	0.00	1,664.82	412.55	1,103.97	1,014.25	3.96	-0.29	0.000

Equivalent Lateral Forces Method Analysis

Spectral Response Acceleration for Short Period ( $S_s$ ):	0.17
Spectral Response Acceleration at 1.0 Second Period ( $S_{d1}$ ):	0.06
Long-Period Transition Period ( $T_L$ ):	6
Importance Factor ( $I_E$ ):	1.00
Site Coefficient $F_a$ :	1.60
Site Coeffiecient $F_v$ :	2.40
Response Modification Coefficient (R):	1.50
Design Spectral Response Acceleration at Short Period ( $S_{ds}$ ):	0.19
Design Spectral Response Acceleration at 1.0 Second Period ( $S_{d1}$ ):	0.10
Seismic Response Coefficient ( $C_s$ ):	0.05
Upper Limit $C_s$	0.05
Lower Limit $C_s$	0.03
Period based on Rayleigh Method (sec):	1.20
Redundancy Factor (p):	1.00
Seismic Force Distribution Exponent (k):	1.35
Total Unfactored Dead Load:	21.96 k
Seismic Base Shear (E):	1.17 k

Load Case 1.2D + 1.0Ev + 1.0Eh

## Seismic

Segment	Height Above Base (ft)	Weight (lb)	$W_z$ (lb-ft)	$C_{vx}$	Horizontal Force (lb)	Vertical Force (lb)
27	108.50	80	45	0.007	9	99
26	106.50	271	147	0.024	28	336
25	102.50	466	240	0.039	46	576
24	97.50	482	232	0.038	44	597
23	92.50	499	224	0.036	43	617
22	87.50	515	215	0.035	41	637
21	82.50	532	205	0.033	39	658
20	77.50	548	194	0.032	37	678
19	72.50	565	183	0.030	35	699
18	68.30	394	117	0.019	22	487
17	65.80	402	114	0.019	22	497
16	62.94	1,055	282	0.046	54	1,305
15	60.44	128	32	0.005	6	158
14	57.50	747	177	0.029	34	925
13	53.87	345	75	0.012	14	426
12	51.37	817	166	0.027	32	1,011
11	48.30	1,031	193	0.031	37	1,276
10	45.80	251	44	0.007	8	311
9	42.50	799	126	0.020	24	989
8	37.50	820	109	0.018	21	1,014
7	32.50	840	92	0.015	18	1,040
6	27.50	861	75	0.012	14	1,065
5	22.50	882	59	0.010	11	1,091
4	17.50	902	43	0.007	8	1,116
3	12.50	923	28	0.005	5	1,142

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:17 PM

Customer: T-MOBILE

2	7.50	944	14	0.002	3	1,168
1	2.50	964	3	0.001	1	1,193
Ericsson KRY 112 489	108.00	46	26	0.004	5	57
Ericsson Radio 4449	108.00	225	124	0.020	24	278
Ericsson AIR 21, 1.3	108.00	249	138	0.022	26	308
Ericsson AIR 21, 1.3	108.00	244	135	0.022	26	303
RFS APXVAARR24_43-U-	108.00	384	212	0.035	41	475
Generic Heavy Platfo	108.00	3,750	2,075	0.338	396	4,640
		21,961	6,142	1.000	1,173	27,173

Load Case 0.9D - 1.0Ev + 1.0Eh

Seismic (Reduced DL)

Segment	Height Above Base (ft)	Weight (lb)	W <sub>z</sub> (lb-ft)	C <sub>vx</sub>	Horizontal Force (lb)	Vertical Force (lb)
27	108.50	80	45	0.007	9	69
26	106.50	271	147	0.024	28	234
25	102.50	466	240	0.039	46	402
24	97.50	482	232	0.038	44	416
23	92.50	499	224	0.036	43	430
22	87.50	515	215	0.035	41	444
21	82.50	532	205	0.033	39	459
20	77.50	548	194	0.032	37	473
19	72.50	565	183	0.030	35	487
18	68.30	394	117	0.019	22	340
17	65.80	402	114	0.019	22	347
16	62.94	1,055	282	0.046	54	910
15	60.44	128	32	0.005	6	110
14	57.50	747	177	0.029	34	645
13	53.87	345	75	0.012	14	297
12	51.37	817	166	0.027	32	705
11	48.30	1,031	193	0.031	37	890
10	45.80	251	44	0.007	8	217
9	42.50	799	126	0.020	24	689
8	37.50	820	109	0.018	21	707
7	32.50	840	92	0.015	18	725
6	27.50	861	75	0.012	14	743
5	22.50	882	59	0.010	11	761
4	17.50	902	43	0.007	8	778
3	12.50	923	28	0.005	5	796
2	7.50	944	14	0.002	3	814
1	2.50	964	3	0.001	1	832
Ericsson KRY 112 489	108.00	46	26	0.004	5	40
Ericsson Radio 4449	108.00	225	124	0.020	24	194
Ericsson AIR 21, 1.3	108.00	249	138	0.022	26	215
Ericsson AIR 21, 1.3	108.00	244	135	0.022	26	211
RFS APXVAARR24_43-U-	108.00	384	212	0.035	41	331
Generic Heavy Platfo	108.00	3,750	2,075	0.338	396	3,235
		21,961	6,142	1.000	1,173	18,945

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:17 PM

Customer: T-MOBILE

Load Case 1.2D + 1.0Ev + 1.0Eh

## Seismic

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-25.98	-1.17	0.00	-101.53	0.00	101.53	3,281.83	959.87	4,780.50	3,731.72	0.00	0.00	0.035
5.00	-24.81	-1.17	0.00	-95.66	0.00	95.66	3,248.05	938.55	4,570.48	3,610.80	0.00	-0.01	0.034
10.00	-23.67	-1.17	0.00	-89.79	0.00	89.79	3,212.50	917.22	4,365.18	3,489.67	0.01	-0.01	0.033
15.00	-22.55	-1.17	0.00	-83.94	0.00	83.94	3,175.17	895.90	4,164.60	3,368.46	0.03	-0.02	0.032
20.00	-21.46	-1.16	0.00	-78.11	0.00	78.11	3,136.05	874.58	3,968.73	3,247.31	0.06	-0.03	0.031
25.00	-20.40	-1.14	0.00	-72.33	0.00	72.33	3,095.17	853.25	3,777.58	3,126.34	0.09	-0.03	0.030
30.00	-19.36	-1.13	0.00	-66.61	0.00	66.61	3,052.50	831.93	3,591.15	3,005.71	0.13	-0.04	0.029
35.00	-18.34	-1.11	0.00	-60.98	0.00	60.98	3,008.05	810.61	3,409.44	2,885.53	0.17	-0.05	0.027
40.00	-17.35	-1.09	0.00	-55.44	0.00	55.44	2,961.83	789.28	3,232.44	2,765.96	0.23	-0.05	0.026
45.00	-17.04	-1.08	0.00	-50.01	0.00	50.01	2,913.83	767.96	3,060.17	2,647.11	0.29	-0.06	0.025
46.60	-15.77	-1.04	0.00	-48.29	0.00	48.29	2,898.10	761.14	3,006.05	2,609.27	0.31	-0.06	0.024
50.00	-14.76	-1.01	0.00	-44.75	0.00	44.75	2,864.05	746.64	2,892.61	2,529.14	0.35	-0.07	0.023
52.74	-14.33	-0.99	0.00	-41.99	0.00	41.99	2,862.14	745.83	2,886.36	2,524.70	0.39	-0.07	0.022
55.00	-13.40	-0.96	0.00	-39.74	0.00	39.74	2,839.02	736.19	2,812.26	2,471.71	0.42	-0.07	0.021
60.00	-13.25	-0.96	0.00	-34.93	0.00	34.93	2,786.60	714.87	2,651.72	2,355.29	0.50	-0.08	0.020
60.87	-11.94	-0.90	0.00	-34.10	0.00	34.10	2,777.29	711.16	2,624.27	2,335.14	0.52	-0.08	0.019
65.00	-11.44	-0.88	0.00	-30.39	0.00	30.39	2,732.39	693.55	2,495.91	2,240.06	0.59	-0.08	0.018
66.60	-10.96	-0.86	0.00	-28.98	0.00	28.98	2,002.34	557.21	2,013.77	1,651.20	0.62	-0.09	0.023
70.00	-10.26	-0.82	0.00	-26.07	0.00	26.07	1,979.98	545.61	1,930.79	1,598.56	0.68	-0.09	0.021
75.00	-9.58	-0.78	0.00	-21.97	0.00	21.97	1,945.62	528.55	1,811.96	1,521.39	0.77	-0.09	0.019
80.00	-8.92	-0.74	0.00	-18.05	0.00	18.05	1,909.49	511.49	1,696.90	1,444.63	0.88	-0.10	0.017
85.00	-8.28	-0.70	0.00	-14.33	0.00	14.33	1,871.57	494.44	1,585.61	1,368.40	0.98	-0.10	0.015
90.00	-7.67	-0.66	0.00	-10.82	0.00	10.82	1,831.88	477.38	1,478.10	1,292.85	1.09	-0.11	0.013
95.00	-7.07	-0.61	0.00	-7.52	0.00	7.52	1,790.40	460.32	1,374.36	1,218.10	1.21	-0.11	0.010
100.00	-6.50	-0.57	0.00	-4.45	0.00	4.45	1,747.15	443.26	1,274.40	1,144.29	1.33	-0.11	0.008
105.00	-6.16	-0.54	0.00	-1.62	0.00	1.62	1,702.13	426.20	1,178.21	1,071.56	1.45	-0.12	0.005
108.00	0.00	0.00	0.00	0.00	0.00	0.00	1,674.26	415.97	1,122.31	1,028.50	1.52	-0.12	0.000
109.00	0.00	0.00	0.00	0.00	0.00	0.00	1,664.82	412.55	1,103.97	1,014.25	1.54	-0.12	0.000

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:17 PM

Customer: T-MOBILE

Load Case 0.9D - 1.0Ev + 1.0EhSeismic (Reduced DL)Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-18.11	-1.17	0.00	-101.08	0.00	101.08	3,281.83	959.87	4,780.50	3,731.72	0.00	0.00	0.033
5.00	-17.30	-1.17	0.00	-95.21	0.00	95.21	3,248.05	938.55	4,570.48	3,610.80	0.00	-0.01	0.032
10.00	-16.50	-1.17	0.00	-89.35	0.00	89.35	3,212.50	917.22	4,365.18	3,489.67	0.01	-0.01	0.031
15.00	-15.72	-1.16	0.00	-83.51	0.00	83.51	3,175.17	895.90	4,164.60	3,368.46	0.03	-0.02	0.030
20.00	-14.96	-1.15	0.00	-77.69	0.00	77.69	3,136.05	874.58	3,968.73	3,247.31	0.06	-0.03	0.029
25.00	-14.22	-1.14	0.00	-71.93	0.00	71.93	3,095.17	853.25	3,777.58	3,126.34	0.09	-0.03	0.028
30.00	-13.50	-1.12	0.00	-66.23	0.00	66.23	3,052.50	831.93	3,591.15	3,005.71	0.13	-0.04	0.026
35.00	-12.79	-1.10	0.00	-60.62	0.00	60.62	3,008.05	810.61	3,409.44	2,885.53	0.17	-0.05	0.025
40.00	-12.10	-1.08	0.00	-55.10	0.00	55.10	2,961.83	789.28	3,232.44	2,765.96	0.22	-0.05	0.024
45.00	-11.88	-1.07	0.00	-49.70	0.00	49.70	2,913.83	767.96	3,060.17	2,647.11	0.28	-0.06	0.023
46.60	-10.99	-1.04	0.00	-47.99	0.00	47.99	2,898.10	761.14	3,006.05	2,609.27	0.30	-0.06	0.022
50.00	-10.29	-1.00	0.00	-44.47	0.00	44.47	2,864.05	746.64	2,892.61	2,529.14	0.35	-0.07	0.021
52.74	-9.99	-0.99	0.00	-41.72	0.00	41.72	2,862.14	745.83	2,886.36	2,524.70	0.39	-0.07	0.020
55.00	-9.35	-0.96	0.00	-39.49	0.00	39.49	2,839.02	736.19	2,812.26	2,471.71	0.42	-0.07	0.019
60.00	-9.23	-0.95	0.00	-34.71	0.00	34.71	2,786.60	714.87	2,651.72	2,355.29	0.50	-0.08	0.018
60.87	-8.32	-0.89	0.00	-33.88	0.00	33.88	2,777.29	711.16	2,624.27	2,335.14	0.52	-0.08	0.018
65.00	-7.98	-0.87	0.00	-30.19	0.00	30.19	2,732.39	693.55	2,495.91	2,240.06	0.59	-0.08	0.016
66.60	-7.64	-0.85	0.00	-28.79	0.00	28.79	2,002.34	557.21	2,013.77	1,651.20	0.61	-0.08	0.021
70.00	-7.15	-0.82	0.00	-25.90	0.00	25.90	1,979.98	545.61	1,930.79	1,598.56	0.67	-0.09	0.020
75.00	-6.68	-0.78	0.00	-21.82	0.00	21.82	1,945.62	528.55	1,811.96	1,521.39	0.77	-0.09	0.018
80.00	-6.22	-0.74	0.00	-17.93	0.00	17.93	1,909.49	511.49	1,696.90	1,444.63	0.87	-0.10	0.016
85.00	-5.78	-0.70	0.00	-14.23	0.00	14.23	1,871.57	494.44	1,585.61	1,368.40	0.98	-0.10	0.013
90.00	-5.35	-0.65	0.00	-10.74	0.00	10.74	1,831.88	477.38	1,478.10	1,292.85	1.09	-0.11	0.011
95.00	-4.93	-0.61	0.00	-7.47	0.00	7.47	1,790.40	460.32	1,374.36	1,218.10	1.20	-0.11	0.009
100.00	-4.53	-0.56	0.00	-4.42	0.00	4.42	1,747.15	443.26	1,274.40	1,144.29	1.32	-0.11	0.006
105.00	-4.29	-0.53	0.00	-1.60	0.00	1.60	1,702.13	426.20	1,178.21	1,071.56	1.44	-0.11	0.004
108.00	0.00	0.00	0.00	0.00	0.00	0.00	1,674.26	415.97	1,122.31	1,028.50	1.51	-0.11	0.000
109.00	0.00	0.00	0.00	0.00	0.00	0.00	1,664.82	412.55	1,103.97	1,014.25	1.54	-0.11	0.000

Site Number: 284988

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: GUILFORD CT, CT

Engineering Number:13660479\_C3\_02

6/14/2021 4:49:17 PM

Customer: T-MOBILE

Analysis Summary

Load Case	Reactions						Max Usage	
	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)	Elev (ft)	Interaction Ratio
1.2D + 1.0W	17.48	0.00	26.34	0.00	0.00	1272.73	0.00	0.35
0.9D + 1.0W	17.48	0.00	19.75	0.00	0.00	1268.12	0.00	0.35
1.2D + 1.0Di + 1.0Wi	4.60	0.00	34.81	0.00	0.00	320.74	0.00	0.10
1.2D + 1.0Ev + 1.0Eh	1.17	0.00	25.98	0.00	0.00	101.53	0.00	0.04
0.9D - 1.0Ev + 1.0Eh	1.17	0.00	18.11	0.00	0.00	101.08	0.00	0.03
1.0D + 1.0W	3.78	0.00	21.96	0.00	0.00	274.77	0.00	0.08


Site Name: Guilford CT, CT  
 Site Number: 284988  
 Tower Type: MP  
Design Loads (Factored) - Analysis per TIA-222-H Standards

## Monolithic Mat & Pier Foundation Analysis

Foundation Analysis Parameters		
Design / Analysis / Mapping:	Analysis	-
Compression/Leg:	26.3	k
Uplift/Leg:	0.0	k
Total Shear:	17.5	k
Moment:	1,272.7	k-ft
Tower + Appurtenance Weight:	26.3	k
Depth to Base of Foundation (l + t - h):	5	ft
Diameter of Pier (d):	7	ft
Length of Pier (l):	3.75	ft
Height of Pier above Ground (h):	1	ft
Width of Pad (W):	23.5	ft
Length of Pad (L):	23.5	ft
Thickness of Pad (t):	2.25	ft
Tower Leg Center to Center:	0	ft
Number of Tower Legs:	1	-
Tower Center from Mat Center:	0	ft
Depth Below Ground Surface to Water Table:	7	ft
Unit Weight of Concrete:	150	pcf
Unit Weight of Soil Above Water Table:	125	pcf
Unit Weight of Water:	62.4	pcf
Unit Weight of Soil Below Water Table:	62.6	pcf
Friction Angle of Uplift:	15	°
Coefficient of Shear Friction:	0.3	-
Ultimate Compressive Bearing Pressure:	20,000	psf
Ultimate Passive Pressure on Pad Face:	0	psf
f <sub>Soil</sub> and Concrete Weight:	0.9	-
f <sub>Soil</sub> :	0.75	-

Foundation Steel Parameters		
Shear/Leg (Compression):	11.7	k
Shear/Leg (Uplift):	9.6	k
Concrete Strength (f <sub>c</sub> ):	4,000	psi
Pad Tension Steel Depth:	23.44	in
Dead Load Factor:	0.9	-
f <sub>Shear</sub> :	0.75	-
f <sub>Flexure / Tension</sub> :	0.9	-
f <sub>Compression</sub> :	0.65	-
b:	0.85	-
Bottom Pad Rebar Size #:	9	-
# of Bottom Pad Rebar:	29	-
Pad Bottom Steel Area:	29.00	in <sup>2</sup>
Pad Steel F <sub>y</sub> :	60,000	psi
Top Pad Rebar Size #:	9	-
# of Top Pad Rebar:	29	-
Pad Top Steel Area:	29.00	in <sup>2</sup>
Pier Rebar Size #:	8	-
Pier Steel Area (Single Bar):	0.79	in <sup>2</sup>
# of Pier Rebar:	57	-
Pier Steel F <sub>y</sub> :	60,000	psi
Pier Cage Diameter:	76.0	in
Rebar Strain Limit:	0.008	-
Steel Elastic Modulus:	29,000	ksi
Tie Rebar Size #:	4	-
Tie Steel Area (Single Bar):	0.20	in <sup>2</sup>
Tie Spacing:	24.33	in
Tie Steel F <sub>y</sub> :	60,000	psi
Clear Cover:	3	in

Overturning Moment Usage		
Design OTM:	1377.7	k-ft
OTM Resistance:	4452.9	k-ft
Design OTM / OTM Resistance:	31%	Pass



Soil Bearing Pressure Usage		
Net Bearing Pressure:	1442	psf
Factored Nominal Bearing Pressure:	15000	psf
Factored Nominal (Net) Bearing Pressure:	10%	Pass
Load Direction Controlling Design Bearing Pressure:	Diagonal to Pad Edge	

Sliding Factor of Safety		
Ultimate Friction Resistance:	122.0	k
Ultimate Passive Pressure Resistance:	0.0	k
Total Factored Sliding Resistance:	91.5	k
Sliding Design / Sliding Resistance:	19%	Pass

Pad Strength Capacity		
Factored One Way Shear ( $V_u$ ):	130.0	k
One Way Shear Capacity ( $fV_c$ ):	627.0	k
$V_u / fV_c$ :	21%	Pass
Load Direction Controlling Shear Capacity:	Parallel to Pad Edge	
Lower Steel Pad Factored Moment ( $M_u$ ):	725.5	k-ft
Lower Steel Pad Moment Capacity ( $fM_n$ ):	2957.9	k-ft
$M_u / fM_n$ :	25%	Pass
Load Direction Controlling Flexural Capacity:	Parallel to Pad Edge	
Upper Steel Pad Factored Moment ( $M_u$ ):	357.2	k-ft
Upper Steel Pad Moment Capacity ( $fM_n$ ):	2957.9	k-ft
$M_u / fM_n$ :	12%	Pass
Lower Pad Flexural Reinforcement Ratio:	0.0044	<i>OK - ACI 318-14 7.6.1.1 &amp; 8.6.1.1</i>
Upper Pad Flexural Reinforcement Ratio:	0.0044	
Pad Shrinkage Reinforcement Ratio:	0.0088	<i>OK - ACI 318-14 24.4.3.2</i>
Lower Pad Reinforcement Spacing:	9.8	in
Upper Pad Reinforcement Spacing:	9.8	in
Ultimate Punching Shear Stress, $v_u$ :	24.06	psi
Nominal Punching Shear Capacity ( $f_c v_c$ ):	189.7	psi
$v_u / f_c v_c$ :	13%	Pass
Pier Moment Pad Flexure Transfer Ratio, $\gamma_f$ :	0.60	<i>TIA-222-H 9.4.2</i>
Moment Transfer Effective Flexural Width, $B_{eff}$ :	13.75	
Moment Transfer Through Pad Flexure:	9635.94	k-in
Moment Transfer Flexural Capacity ( $fM_{sc,f}$ ):	21718.98	k-in
$g_f M_{sc} / fM_{sc,f}$ :	0%	Pass

Pier Strength Capacity		
Factored Moment in Pier ( $M_u$ ):	1338.3	k-ft
Pier Moment Capacity ( $fM_n$ ):	7261.6	k-ft
$M_u / fM_n$ :	18%	Pass
Factored Shear in Pier ( $V_u$ ):	17.5	k
Pier Shear Capacity ( $fV_n$ ):	576.7	k
$V_u / fV_c$ :	3%	Pass
Pier Shear Reinforcement Ratio:	0.0004	<i>OK - No Ties Necessary for Shear - ACI 11.5.6.1</i>
Factored Tension in Pier ( $T_u$ ):	0.0	
Pier Tension Capacity ( $fT_n$ ):	2431.6	k
$T_u / fT_n$ :	0%	Pass
Factored Compression in Pier ( $P_u$ ):	26.3	k
Pier Compression Capacity ( $fP_n$ ):	9742.9	k
$P_u / fP_n$ :	0%	Pass
Pier Compression Reinforcement Ratio:	0.008	<i>OK - TIA-222-H 9.4.1</i>
Minimum Depth to Develop Vertical Rebar:	29	in
Minimum Hook Development Length:	19	in
Minimum Mat Thickness / Edge Distance from Pier:	22.0	in
Minimum Foundation Depth:	4.02	ft
$M_u / fB M_n + T_u / fT_n$ :	18%	Pass


## Base Plate & Anchor Rod Analysis

Pole Dimensions		
Number of Sides	18	-
Diameter	55.4559	in
Thickness	5/16	in
Orientation Offset		°

Base Reactions		
Moment, Mu	1,272.7	k-ft
Axial, Pu	26.3	k
Shear, Vu	17.5	k
Neutral Axis	90	°


Report Capacities		
Component	Capacity	Result
Base Plate	6%	Pass
Anchor Rods	31%	Pass
Dwyidag	-	-

Base Plate		
Shape	Round	-
Diameter, ø	68.5	in
Thickness	2 1/2	in
Grade	A572-50	
Yield Strength, Fy	50	ksi
Tensile Strength, Fu	65	ksi
Clip	N/A	in
Orientation Offset		°
Anchor Rod Detail	d	$\eta=0.5$
Clear Distance	3	in
Applied Moment, Mu	169.1	k
Bending Stress, $\phi M_n$	2862.9	k



Original Anchor Rods		
Arrangement	Radial	-
Quantity	14	-
Diameter, ø	2 1/4	in
Bolt Circle	62.5	in
Grade	A615-75	
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Spacing	14.0	in
Orientation Offset		°
Applied Force, Pu	74.4	k
Anchor Rods, $\phi P_n$	243.6	k

Stiffeners		
Arrangement	Radial	-
Quantity	7	-
Height	12.5	in
Width	3.5	in
Effective Width	3.500	in
Thickness	3/4	in
Effective Thickness	0.650	in
Notch	0.5	in
Flat Edge	1.5	in
Grade	A36	-
Yield Strength, Fy	36	ksi
Tensile Strength, Fu	58	ksi
Horizontal Weld	Fillet	
Horizontal Fillet Size	5/16	in
Bevel Depth	5/32	in
Vertical Weld	Fillet	
Vertical Fillet Size	5/16	in
Weld Strength	70	ksi
Electrode Coefficient	1	-
Orientation Offset	15	°
Vertical Weld, $\phi R_n$	158.0	k
Horz. Weld, $\phi R_n$	30.5	k
Ten. Capacity, $\phi T_n$	72.9	k
Comp. Capacity, $\phi P_n$	318.2	k



## Calculations for Monopole Base Plate & Anchor Rod Analysis

### Reaction Distribution

Reaction	Shear Vu	Moment Mu	Factor
-	k	k-ft	-
Base Forces	17.5	1272.7	1.00
Anchor Rod Forces	17.5	1272.7	1.00
Additional Bolt (Grp1) Forces	0.0	0.0	0.00
Additional Bolt (Grp2) Forces	0.0	0.0	0.00
Dywidag Forces	0.0	0.0	0.00
Stiffener Forces	3.6	263.5	0.21

### Geometric Properties

Section	Gross Area	Net Area	Individual Inertia	Threads per Inch	Moment of Inertia
-	in <sup>2</sup>	in <sup>2</sup>	in <sup>4</sup>	#	in <sup>4</sup>
Pole	53.8625	2.9924	0.0977		20474.85
Bolt	3.9761	3.2477	0.8393	4.5	20557.54
Bolt1	0.0000	0.0000	0.0000	0	0.00
Bolt2	0.0000	0.0000	0.0000	0	0.00
Dywidag	0.0000	0.0000	0.0000		0.00
Stiffener	1.9500	1.7550	9.2896		5345.93

### Base Plate

Shape	Round	-
Diameter, D	68.5	in
Thickness, t	2.5	in
Yield Strength, Fy	50	ksi
Tensile Strength, Fu	65	ksi
Base Plate Chord	40.211	in
Detail Type	d	-
Detail Factor	0.50	-
Clear Distance	3	-

### Anchor Rods

Anchor Rod Quantity, N	14	-
Rod Diameter, d	2.25	in
Bolt Circle, BC	62.5	in
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Applied Axial, Pu	74.4	k
Applied Shear, Vu	0.4	k
Compressive Capacity, $\phi P_n$	243.6	k
Tensile Capacity, $\phi R_{nt}$	0.306	OK
Interaction Capacity	0.309	OK

### Base Plate Stiffeners

Applied Axial Force, Pu	30.3	k
Applied Horizontal Force, Vu	0.26	k
<b>Vertical Weld</b>		
Vert.-to-Stiffener $a = e_x/l$	0.093	-
Spacing Ratio, k	0.060	-
Weld Coefficient, C	3.371	-
Compressive Capacity, $\phi P_n$	158.0	k
Vert.-to-Plate $a = e_x/l$	0.333	-
Spacing Ratio, k	0.060	-
Weld Coefficient, C	2.940	-
Shear Capacity, $\phi V_n$	137.8	k
$P_u/\phi_p P_n + V_u/\phi_v V_n$	0.194	OK

### External Base Plate

Chord Length AA	33.701	in
Additional AA	7.016	in
Section Modulus, Z	63.621	in <sup>3</sup>
Applied Moment, Mu	169.1	k-ft
Bending Capacity, $\phi M_n$	2862.9	k-ft
Capacity, Mu/ $\phi M_n$	0.059	OK
Chord Length AB	32.245	in
Additional AB	6.159	in
Section Modulus, Z	60.005	in <sup>3</sup>
Applied Moment, Mu	137.2	k-ft
Bending Capacity, $\phi M_n$	2700.2	k-ft
Capacity, Mu/ $\phi M_n$	0.051	OK
Bend Line Length	23.012	in
Additional Bend Line	29.050	in
Section Modulus, Z	81.346	in <sup>3</sup>
Applied Moment, Mu	169.1	k-ft
Bending Capacity, $\phi M_n$	3660.6	k-ft
Capacity, Mu/ $\phi M_n$	0.046	OK

### Horizontal Weld

Horz.-to-Stiffener $a = e_x/l$	0.167	-
Spacing Ratio, k	0.214	-
Weld Coefficient, C	2.240	-
Effective Fillet	0.313	in
Compressive Capacity, $\phi P_n$	29.4	k
Horz.-to-Pole $a = e_x/l$	0.595	-
Spacing Ratio, k	0.214	-
Weld Coefficient, C	2.320	-
Shear Capacity, $\phi V_n$	30.5	k
$P_u/\phi_p P_n + V_u/\phi_v V_n$	1.040	OK

### Plate Tension

Gross Cross Section	1.950	in <sup>2</sup>
Net Cross Section	1.755	in <sup>2</sup>
Tensile Capacity, $\phi T_n$	72.9	k
Capacity, Tu/ $\phi T_n$	0.208	OK

### Internal Base Plate

Arc Length	0.000	in
Section Modulus, Z	0.000	in <sup>3</sup>
Moment Arm	0.000	in
Applied Moment, Mu	0.0	k-ft
Bending Capacity, $\phi M_n$	0.0	k-ft
Capacity, Mu/ $\phi M_n$	0.046	OK

### Plate Compression

Radius of Gyration	0.188	in <sup>3</sup>
kl/r	39.97	-
$4.71 \sqrt{(E/F_y)}$	133.68	-
Buckling Stress(Fe)	179.2	-
Crit. Buckling Stress(Fcr)	157.1	ksi
Compressive Capacity, $\phi P_n$	318.2	k
Capacity, Pu/ $\phi P_n$	0.048	OK

RAN Template: 67D92C Outdoor	A&L Template: 67D92C_2xAIR+1OP
---------------------------------	-----------------------------------

CTNH805A\_L600\_5\_draft

Print Name: Standard (1)  
 PORs: L600\_5G POPs

## Section 1 - Site Information

**Site ID:** CTNH805A  
**Status:** Draft  
**Version:** 5  
**Project Type:** L600  
**Approved:** Not Approved  
**Approved By:** Not Approved  
**Last Modified:** 2/5/2021 9:3:17 AM  
**Last Modified By:** Richard.Kane@sprint.com

**Site Name:** Amtrak\_Guilford  
**Site Class:** Monopole  
**Site Type:** Structure Non Building  
**Plan Year:**  
**Market:** CONNECTICUT CT  
**Vendor:** Ericsson  
**Landlord:** T-Mobile USA Inc

**Latitude:** 41.26724500  
**Longitude:** -72.71620500  
**Address:** 79 Moose Hill Road  
**City, State:** Guilford, CT  
**Region:** NORTHEAST

**RAN Template:** 67D92C Outdoor

**AL Template:** 67D92C\_2xAIR+1OP

**Sector Count:** 3

**Antenna Count:** 9

**Coax Line Count:** 6

**TMA Count:** 3


**RRU Count:** 3

## Section 2 - Existing Template Images



95A\_2xAIR.JPG


95F.png

Mid-Band  
Passive  
Antenna



Notes:






Notes:

## Section 3 - Proposed Template Images

67D02C.JPG



Notes:

## Section 4 - Siteplan Images

----- This section is intentionally blank. -----

DRAFT

RAN Template: 67D92C Outdoor	A&L Template: 67D92C_2xAIR+1OP
---------------------------------	-----------------------------------

## Section 5 - RAN Equipment

### Existing RAN Equipment

Template: 95A

1

Enclosure	
Enclosure Type	RBS 6131
Baseband	DUW30 U2100    DUG20 G1900    DUS41 L1900 L2100
Radio	RU22 (x 6) U2100

### Proposed RAN Equipment

Template: 67D92C Outdoor

1

Enclosure	
Enclosure Type	RBS 6131
Baseband	DUW30 U2100    DUG20 G1900    BB 6648 L1900    BB 6648 L2100    N600 L600    L700
Hybrid Cable System	Ericsson Hybrid Trunk 6/24 4AWG 100m (x 3)
Radio	RU22 (x 6) U2100

#### RAN Scope of Work:

Replace(1) DUS41 with (1) BB6648 for L2100, L700, and L600.  
 Add (1) BB6648 for 5G N600.  
 Add (3) 6X24 HCS.

Existing: (6) 1-5/8" Coaxial Lines; (1) HCS

RAN Template: 67D92C Outdoor	A&L Template: 67D92C_2xAIR+1OP
---------------------------------	-----------------------------------

## Section 6 - A&L Equipment

Existing Template: 95A\_2xAIR  
Proposed Template: 67D92C\_2xAIR+1OP

### Sector 1 (Existing) view from behind

Coverage Type	A - Outdoor Macro			
Antenna	1		2	
Antenna Model	Ericsson - AIR21 KRC118023-1_B2A_B4P (Quad)		Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad)	
Azimuth	0		0	
M. Tilt	0		0	
Height	108		108	
Ports	P1	P2	P3	P4
Active Tech.	G1900 L1900	U2100		L2100
Dark Tech.				
Restricted Tech.				
Decomm. Tech.	U1900			
E. Tilt	2	2	2	2
Cables	Fiber Jumper - 15 ft. (x2)	1-5/8" Coax - 120 ft. (x2)		Fiber Jumper - 15 ft. (x2)
TMAs		Generic Twin Style 1B - AWS (AtAntenna)		
Diplexers / Combiners				
Radio				
Sector Equipment				

Unconnected Equipment:

Scope of Work:

<b>RAN Template:</b> 67D92C Outdoor	<b>A&amp;L Template:</b> 67D92C_2xAIR+1OP
--	--

CTNH805A\_L600\_5\_draft

**Print Name:** Standard (1)  
**PORs:** L600\_5G POPs

**Sector 1 (Proposed) view from behind**

Coverage Type	A - Outdoor Macro							
Antenna	<b>1</b>		<b>2</b>			<b>3</b>		
Antenna Model	Ericsson - AIR21 KRC118023-1_B2A_B4P (Quad)			RFS - APXVAARR24_43-U-NA20 (Octo)			Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad)	
Azimuth	0			0			0	
M. Tilt	0			0			0	
Height	108		108			108		
Ports	<b>P1</b>	<b>P2</b>	<b>P3</b>	<b>P4</b>	<b>P5</b>	<b>P6</b>	<b>P7</b>	<b>P8</b>
Active Tech.	L1900 G1900	U2100	L700 L600 N600	L700 L600 N600				L2100
Dark Tech.								
Restricted Tech.								
Decomm. Tech.	U1900							
E. Tilt	(2)	(2)	(2)	(2)		(2)	(2)	
Cables	Fiber Jumper - 15 ft. (x2)	1-5/8" Coax - 120 ft. (x2)	Coax Jumper (x2) Fiber Jumper - 15 ft.	Coax Jumper (x2)				Fiber Jumper - 15 ft. (x2)
TMAs		Generic Twin Style 1B - AWS (AtAntenna)						
Diplexers / Combiners								
Radio			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)				
Sector Equipment								

**Unconnected Equipment:****Scope of Work:**

New Platform with Three Mounts per Sector.  
AIR21 B2A/B4P for GSM, U1900, and U2100 in Position 1.  
Add (1) LB/MB Octo to Position 2.  
Add (1) Radio 4449 B71+B12 to Position 2 for L600 and L700.  
AIR21 B2P/B4A for L2100 in Position 3.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

RAN Template: 67D92C Outdoor	A&L Template: 67D92C_2xAIR+1OP
---------------------------------	-----------------------------------

## Sector 2 (Existing) view from behind

Coverage Type	A - Outdoor Macro			
Antenna	1		2	
Antenna Model	Ericsson - AIR21 KRC118023-1_B2A_B4P (Quad)		Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad)	
Azimuth	120		120	
M. Tilt	0		0	
Height	108		108	
Ports	P1	P2	P3	P4
Active Tech.	G1900 L1900	U2100		L2100
Dark Tech.				
Restricted Tech.				
Decomm. Tech.	U1900			
E. Tilt	(2)	(2)	(2)	(2)
Cables	Fiber Jumper - 15 ft. (x2)	1-5/8" Coax - 120 ft. (x2)		Fiber Jumper - 15 ft. (x2)
TMAs		Generic Twin Style 1B - AWS (AtAntenna)		
Diplexers / Combiners				
Radio				
Sector Equipment				

Unconnected Equipment:

Scope of Work:

--

<b>RAN Template:</b> 67D92C Outdoor	<b>A&amp;L Template:</b> 67D92C_2xAIR+1OP
--	--

CTNH805A\_L600\_5\_draft

**Print Name:** Standard (1)  
**PORs:** L600\_5G POPs

## Sector 2 (Proposed) view from behind

Coverage Type	A - Outdoor Macro							
Antenna	1		2		3			
Antenna Model	Ericsson - AIR21 KRC118023-1_B2A_B4P (Quad)		RFS - APXVAARR24_43-U-NA20 (Octo)				Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad)	
Azimuth	120		120				120	
M. Tilt	0		0				0	
Height	108		108				108	
Ports	P1	P2	P3	P4	P5	P6	P7	P8
Active Tech.	L1900 G1900	U2100	L700 L600 N600	L700 L600 N600				L2100
Dark Tech.								
Restricted Tech.								
Decomm. Tech.	U1900							
E. Tilt	(2)	(2)	(2)	(2)			(2)	
Cables	Fiber Jumper - 15 ft. (x2)	1-5/8" Coax - 120 ft. (x2)	Coax Jumper (x2) Fiber Jumper - 15 ft.	Coax Jumper (x2)				Fiber Jumper - 15 ft. (x2)
TMAs		Generic Twin Style 1B - AWS (AtAntenna)						
Diplexers / Combiners								
Radio			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)				
Sector Equipment								

## Unconnected Equipment:

## Scope of Work:

New Platform with Three Mounts per Sector.  
AIR21 B2A/B4P for GSM, U1900, and U2100 in Position 1.  
Add (1) LB/MB Octo to Position 2.  
Add (1) Radio 4449 B71+B12 to Position 2 for L600 and L700.  
AIR21 B2P/B4A for L2100 in Position 3.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

RAN Template: 67D92C Outdoor	A&L Template: 67D92C_2xAIR+1OP
---------------------------------	-----------------------------------

## Sector 3 (Existing) view from behind

Coverage Type	A - Outdoor Macro			
Antenna	1		2	
Antenna Model	Ericsson - AIR21 KRC118023-1_B2A_B4P (Quad)		Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad)	
Azimuth	240		240	
M. Tilt	0		0	
Height	108		108	
Ports	P1	P2	P3	P4
Active Tech.	G1900 L1900	U2100		L2100
Dark Tech.				
Restricted Tech.				
Decomm. Tech.	U1900			
E. Tilt	(2)	(2)	(2)	(2)
Cables	Fiber Jumper - 15 ft. (x2)	1-5/8" Coax - 120 ft. (x2)		Fiber Jumper - 15 ft. (x2)
TMAs		Generic Twin Style 1B - AWS (AtAntenna)		
Diplexers / Combiners				
Radio				
Sector Equipment				

Unconnected Equipment:

Scope of Work:

--

<b>RAN Template:</b> 67D92C Outdoor	<b>A&amp;L Template:</b> 67D92C_2xAIR+1OP
--	--

CTNH805A\_L600\_5\_draft

**Print Name:** Standard (1)  
**PORs:** L600\_5G POPs

## Sector 3 (Proposed) view from behind

Coverage Type	A - Outdoor Macro						
Antenna	1	2	3				
Antenna Model	Ericsson - AIR21 KRC118023-1_B2A_B4P (Quad)	RFS - APXVAARR24_43-U-NA20 (Octo)	Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad)				
Azimuth	240	240	240				
M. Tilt	0	0	0				
Height	108	108	108				
Ports	P1	P2	P3	P4	P5	P6	P7
Active Tech.	L1900 G1900	U2100	L700 L600 N600	L700 L600 N600			L2100
Dark Tech.							
Restricted Tech.							
Decomm. Tech.	U1900						
E. Tilt	(2)	(2)	(2)	(2)		(2)	
Cables	Fiber Jumper - 15 ft. (x2)	1-5/8" Coax - 120 ft. (x2)	Coax Jumper (x2) Fiber Jumper - 15 ft.	Coax Jumper (x2)			Fiber Jumper - 15 ft. (x2)
TMAs		Generic Twin Style 1B - AWS (AtAntenna)					
Diplexers / Combiners							
Radio			Radio 4449 B71+B85 (At Antenna)	SHARED Radio 4449 B71+B85 (At Antenna)			
Sector Equipment							

## Unconnected Equipment:

## Scope of Work:

New Platform with Three Mounts per Sector.  
AIR21 B2A/B4P for GSM, U1900, and U2100 in Position 1.  
Add (1) LB/MB Octo to Position 2.  
Add (1) Radio 4449 B71+B12 to Position 2 for L600 and L700.  
AIR21 B2P/B4A for L2100 in Position 3.

\*A dashed border indicates shared equipment. Any connected equipment is denoted with the SHARED keyword.

RAN Template: 67D92C Outdoor	A&L Template: 67D92C_2xAIR+1OP
---------------------------------	-----------------------------------

## Section 7 - Power Systems Equipment

### Existing Power Systems Equipment

----- This section is intentionally blank. -----

### Proposed Power Systems Equipment



## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CTNH805A

Amtrak\_Guilford  
79 Moose Hill Road  
Guilford, Connecticut 06437

**June 28, 2021**

**EBI Project Number: 6221003338**

Site Compliance Summary	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>8.32%</b>



June 28, 2021

T-Mobile  
Attn: Jason Overbey, RF Manager  
35 Griffin Road South  
Bloomfield, Connecticut 06002

### Emissions Analysis for Site: CTNH805A - Amtrak\_Guilford

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **79 Moose Hill Road in Guilford, Connecticut** for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately 400  $\mu\text{W}/\text{cm}^2$  and 467  $\mu\text{W}/\text{cm}^2$ , respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is 1000  $\mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## CALCULATIONS

Calculations were done for the proposed T-Mobile Wireless antenna facility located at 79 Moose Hill Road in Guilford, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 LTE channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 1 NR channel (600 MHz Band) was considered for each sector of the proposed installation. This Channel has a transmit power of 80 Watts.
- 3) 2 LTE channels (700 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 4) 4 GSM channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 5) 2 LTE channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 6) 2 UMTS channels (AWS Band - 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.



- 7) 2 LTE channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel.
- 8) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 9) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 10) The antennas used in this modeling are the Ericsson AIR 21 for the 1900 MHz / 1900 MHz / 2100 MHz channel(s), the RFS APXVAARR24\_43-U-NA20 for the 600 MHz / 600 MHz / 700 MHz channel(s), the Ericsson AIR 21 for the 2100 MHz channel(s) in Sector A, the Ericsson AIR 21 for the 1900 MHz / 1900 MHz / 2100 MHz channel(s), the RFS APXVAARR24\_43-U-NA20 for the 600 MHz / 600 MHz / 700 MHz channel(s), the Ericsson AIR 21 for the 2100 MHz channel(s) in Sector B, the Ericsson AIR 21 for the 1900 MHz / 1900 MHz / 2100 MHz channel(s), the RFS APXVAARR24\_43-U-NA20 for the 600 MHz / 600 MHz / 700 MHz channel(s), the Ericsson AIR 21 for the 2100 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 10 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 11) The antenna mounting height centerline of the proposed antennas is 108 feet above ground level (AGL).
- 12) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 13) Emissions from additional carriers were not included because other carrier emissions data is not entered for this site.



# EBI Consulting

environmental | engineering | due diligence

- 
- 14) All calculations were done with respect to uncontrolled / general population threshold limits.



## T-Mobile Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	Ericsson AIR 21	Make / Model:	Ericsson AIR 21	Make / Model:	Ericsson AIR 21
Frequency Bands:	1900 MHz / 1900 MHz / 2100 MHz	Frequency Bands:	1900 MHz / 1900 MHz / 2100 MHz	Frequency Bands:	1900 MHz / 1900 MHz / 2100 MHz
Gain:	15.35 dBd / 15.35 dBd / 15.35 dBd	Gain:	15.35 dBd / 15.35 dBd / 15.35 dBd	Gain:	15.35 dBd / 15.35 dBd / 15.35 dBd
Height (AGL):	108 feet	Height (AGL):	108 feet	Height (AGL):	108 feet
Channel Count:	8	Channel Count:	8	Channel Count:	8
Total TX Power (W):	300 Watts	Total TX Power (W):	300 Watts	Total TX Power (W):	300 Watts
ERP (W):	10,283.03	ERP (W):	10,283.03	ERP (W):	10,283.03
Antenna A1 MPE %:	<b>3.55%</b>	Antenna B1 MPE %:	<b>3.55%</b>	Antenna C1 MPE %:	<b>3.55%</b>
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVAARR24_43-U-NA20	Make / Model:	RFS APXVAARR24_43-U-NA20	Make / Model:	RFS APXVAARR24_43-U-NA20
Frequency Bands:	600 MHz / 600 MHz / 700 MHz	Frequency Bands:	600 MHz / 600 MHz / 700 MHz	Frequency Bands:	600 MHz / 600 MHz / 700 MHz
Gain:	12.95 dBd / 12.95 dBd / 13.35 dBd	Gain:	12.95 dBd / 12.95 dBd / 13.35 dBd	Gain:	12.95 dBd / 12.95 dBd / 13.35 dBd
Height (AGL):	108 feet	Height (AGL):	108 feet	Height (AGL):	108 feet
Channel Count:	5	Channel Count:	5	Channel Count:	5
Total TX Power (W):	200 Watts	Total TX Power (W):	200 Watts	Total TX Power (W):	200 Watts
ERP (W):	4,059.02	ERP (W):	4,059.02	ERP (W):	4,059.02
Antenna A2 MPE %:	<b>3.35%</b>	Antenna B2 MPE %:	<b>3.35%</b>	Antenna C2 MPE %:	<b>3.35%</b>
Antenna #:	3	Antenna #:	3	Antenna #:	3
Make / Model:	Ericsson AIR 21	Make / Model:	Ericsson AIR 21	Make / Model:	Ericsson AIR 21
Frequency Bands:	2100 MHz	Frequency Bands:	2100 MHz	Frequency Bands:	2100 MHz
Gain:	15.35 dBd	Gain:	15.35 dBd	Gain:	15.35 dBd
Height (AGL):	108 feet	Height (AGL):	108 feet	Height (AGL):	108 feet
Channel Count:	2	Channel Count:	2	Channel Count:	2
Total TX Power (W):	120 Watts	Total TX Power (W):	120 Watts	Total TX Power (W):	120 Watts
ERP (W):	4,113.21	ERP (W):	4,113.21	ERP (W):	4,113.21
Antenna A3 MPE %:	<b>1.42%</b>	Antenna B3 MPE %:	<b>1.42%</b>	Antenna C3 MPE %:	<b>1.42%</b>



Site Composite MPE %	
Carrier	MPE %
T-Mobile (Max at Sector A):	8.32%
no additional carriers	N/A
Site Total MPE % :	8.32%

T-Mobile MPE % Per Sector	
T-Mobile Sector A Total:	8.32%
T-Mobile Sector B Total:	8.32%
T-Mobile Sector C Total:	8.32%
Site Total MPE % :	8.32%

T-Mobile Maximum MPE Power Values (Sector A)							
T-Mobile Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
T-Mobile 1900 MHz GSM	4	1028.30	108.0	14.21	1900 MHz GSM	1000	1.42%
T-Mobile 1900 MHz LTE	2	2056.61	108.0	14.21	1900 MHz LTE	1000	1.42%
T-Mobile 2100 MHz UMTS	2	1028.30	108.0	7.11	2100 MHz UMTS	1000	0.71%
T-Mobile 600 MHz LTE	2	591.73	108.0	4.09	600 MHz LTE	400	1.02%
T-Mobile 600 MHz NR	1	1577.94	108.0	5.45	600 MHz NR	400	1.36%
T-Mobile 700 MHz LTE	2	648.82	108.0	4.48	700 MHz LTE	467	0.96%
T-Mobile 2100 MHz LTE	2	2056.61	108.0	14.21	2100 MHz LTE	1000	1.42%
						<b>Total:</b>	<b>8.32%</b>

- NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.



## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

T-Mobile Sector	Power Density Value (%)
Sector A:	8.32%
Sector B:	8.32%
Sector C:	8.32%
T-Mobile Maximum MPE % (Sector A):	8.32%
Site Total:	8.32%
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **8.32%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.