



December 21, 2022

VIA ELECTRONIC AND FEDERAL EXPRESS

Melanie A. Bachman, Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

New Cingular Wireless PCS, LLC (“AT&T”)
Notice of Exempt Modification
Emergency Back-up Generator
768 Gilead Street, Hebron, CT 06248
Lat.: 41.68629190; Long.: -072.41509890

Dear Ms. Bachman:

This letter and enclosures are respectfully submitted on behalf of New Cingular Wireless PCS, LLC (“AT&T”). AT&T currently maintains its wireless telecommunications facility on the existing tower located at 768 Gilead Street in the Town of Hebron, Connecticut. The underlying property is owned by Edward A. and Renee J. Ellis, and the tower is owned by SBA Properties Inc. AT&T submits this letter and enclosures to the Connecticut Siting Council (“Council”) to notify the Council of AT&T’s intent to perform modifications to the existing facility that do not have substantial adverse environmental effects and thus do not require a certificate pursuant to Section 16-50k of the Connecticut General Statutes.

AT&T intends to install one (1) new Generac 30kW Diesel Generator within the existing grade-level fenced equipment compound as demonstrated on the plans enclosed as Attachment 1.

AT&T’s existing facility supports its FirstNet program which provides first responders with priority access to AT&T’s network to ensure adequate communication capabilities in the event of emergency. AT&T’s proposed generator will ensure that critical communication capability for first responders and the public are not lost in the event of a loss of power.

AT&T’s proposed generator will also advance the State’s goal of natural disaster and emergency preparedness. As discussed in the Council’s Docket 432 Findings and Report and Docket 440 proceedings and Findings of Fact (Nos. 76- 77), in response to two significant storm events in 2011, the State formed a Two Storm Panel (the “Panel”) that evaluated Connecticut’s approach to planning and mitigation of impacts associated with emergencies and natural disasters. The Panel found that “wireless telecommunications service providers were not prepared to serve residential and business customers during a power outage” because certain companies had limited backup generator capacity.

GDIT

The Panel also noted that “[t]he failure of a large portion of Connecticut’s telecommunications system during the two storms is a life safety issue.” The Panel recommended that State regulatory bodies review “telecommunications services currently in place to verify that the vendors have sufficient generator and backhaul capacity to meet the emergency needs of consumers and businesses” and that the “Connecticut Siting Council should require continuity of service plans for any cellular tower to be erected.” The planned modifications will ensure continuity of services by reinforcing AT&T’s backup power and backhaul capacity to meet the emergency needs of first responders, consumers, and businesses in the event of a power outage.

The planned modifications to the facility fall squarely within the activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2) as the planned modifications:

- Will not result in an increase in the height of the existing structure;
- Will not require the extension of the site boundary;
- Will not increase noise levels at the facility by more than six decibels or more, or to levels that exceed state or local criteria since emergency backup generators are exempt from noise regulations as “noise created as a result of, or relating to, an emergency”;
- Will not increase radio frequency emission at the facility to a level at or above the Federal Communications Commission safety standards;
- Will not cause a change or alteration in the physical or environmental characteristics of the site; and
- Will not impair the structural integrity of the facility.

This modification complies with the aforementioned approval. AT&T’s proposed modification will maintain compliance with any relevant conditions these original approvals and any other subsequent approvals. The proposed modifications will have no impact on the existing tower structure itself or the radiofrequency emissions as the proposed modifications only consist of the addition of one new generator within the grade-level equipment compound. Thus, AT&T respectfully requests a waiver from submission of information relating to the existing tower structure or the radio-frequency emissions.

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73 for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-73. In accordance with R.C.S.A.

§ 16-50j-73, a copy of this letter and enclosure are being sent to the Andrew J. Tierney, Town Manager, Matthew Bordeaux, Town Planner, Edward A. and Renee J. Ellis, Property Owners and Tower Owner as stated above. Certification of Service is enclosed as Attachment 3.

GDIT

For the foregoing reasons, AT&T respectfully submits that the proposed modification to the above referenced wireless telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Very truly yours

Catherine Conklin

Catherine Conklin, Site Acquisition Specialist
General Dynamics Wireless Services
2586 Industry Lane, Suite 100
Norristown, PA 19403
(202) 568-0437
catherine.conklin@gdit.com

GENERAL DYNAMICS
Information Technology

CC:

Andrew J. Tierney, Town Manager
15 Gilead Street
Hebron, CT 06248
860-228-5971

Matthew Bordeaux, Town Planner
15 Gilead Street
Hebron, CT 06248
860-228-5971

Edward A. and Renee J. Ellis, Property Owners
768 Gilead Street
Hebron, CT 06248

SBA Property, Tower Owner

ATTACHMENT 1



at&t Mobility



SITE NAME: HEBRON NORTH CENTRAL
FA LOCATION CODE: 10071077


GENERATOR PROJECT
30KW GENERAC DIESEL GENERATOR
200A GENERAC ATS

768 GILEAD STREET
HEBRON, CT 06248

CONSULTANT:
GENERAL DYNAMICS
Information Technology, Inc.

GENERAL DYNAMICS
101 STATION DR
WESTWOOD, MA 02090

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



 12/19/2022
Date:

| MARK | DATE | DESCRIPTION |
|-------------|-------|------------------------|
| ISSUE PHASE | FINAL | DATE ISSUED 12/19/2022 |

HEBRON NORTH CENTRAL
FA ID # 10071077


PROJECT INFORMATION:
768 GILEAD STREET
HEBRON, CT 06248

SHEET TITLE:
TITLE SHEET

SCALE: NONE


PROJECT NUMBER: 57102
SHEET NUMBER: T-1

VICINITY MAP



SCOPE OF WORK

ADD STANDBY GENERATOR, ASSOCIATED CONCRETE PAD, AND UTILITY EQUIPMENT TO EXISTING AT&T EQUIPMENT AREA. THERE WILL BE NO CHANGE IN THE SIZE OR HEIGHT OF THE TOWER OR ANTENNAS.



TO OBTAIN LOCATION OF PARTICIPANTS' UNDERGROUND FACILITIES BEFORE YOU DIG IN CONNECTICUT

CALL BEFORE YOU DIG
811 OR 1-800-922-4455

CONNECTICUT PUBLIC ACT 87-71 REQUIRES MIN. 2 WORKING DAYS NOTICE BEFORE YOU EXCAVATE.

APPLICABLE BUILDING CODE & STANDARDS

ALL WORK AND MATERIALS SHALL BE PERFORMED AND INSTALLED IN ACCORDANCE WITH THE CURRENT EDITION OF THE FOLLOWING CODES AS ADOPTED BY THE GOVERNING LOCAL AUTHORITIES. NOTHING IN THESE PLANS ARE TO BE CONSTRUCTED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

- INTERNATIONAL BUILDING CODE 2021
- NATIONAL ELECTRIC CODE 2017
- AMERICAN CONCRETE INSTITUTE (ACI) 318, BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE
- AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC), MANUAL OF STEEL CONSTRUCTION
- TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA) 222-G, STRUCTURAL STANDARDS FOR STEEL TOWER AND ANTENNA SUPPORTING STRUCTURES
- TIA 607, COMMERCIAL BUILDING GROUNDING AND BONDING REQUIREMENTS FOR TELECOMMUNICATIONS

AERIAL VIEW OF SITE



PROJECT INFORMATION

PROJECT MANAGER:

MATTHEW HIGGINS
GENERAL DYNAMICS WIRELESS SERVICES
101 STATION DRIVE
WESTWOOD, MA 02090
EMAIL: Matthew.Higgins@GDIT.com

ENGINEER:

RAMAKER & ASSOCIATES, INC.
855 COMMUNITY DRIVE
SAUK CITY, WI 53583
PH.: (608) 643-4100
FAX: (608) 643-7999
CONTACT: TYLER BEATTY
EMAIL: tbeatty@ramaker.com

APPLICANT INFORMATION:

AT&T MOBILITY
7150 STANDARD DR
HANOVER, MD 21076

SITE DATA:

SITE NAME: HEBRON NORTH CENTRAL
FA NUMBER: 10071077

PROPERTY OWNER:

SBA
BROKEN SOUND PARKWAY
BOCA RATON, FL 33487

ADDRESS:

768 GILEAD STREET
HEBRON, CT 06248

COUNTY:

TOLLAND

LAT.: 41.6862919°
LONG.: -72.4150989°

GROUND ELEVATION:

633 FT AMSL

DO NOT SCALE DRAWINGS:
CONTRACTOR SHALL VERIFY ALL PLANS & EXISTING DIMENSIONS & CONDITIONS ON THE JOB SITE & SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK OR BE RESPONSIBLE FOR SAME.

THE INFORMATION CONTAINED IN THIS SET OF DOCUMENTS IS PROPRIETARY BY NATURE. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO THE CLIENT IS STRICTLY PROHIBITED.

SHEET INDEX

GENERAL:

T-1 TITLE SHEET

NOTES:

N-1 GENERAL NOTES

SITE:

A-1 SITE PLAN
A-2 SITE PLAN & EQUIPMENT LAYOUT
S-1 FOUNDATION DETAILS

ELECTRICAL & GROUNDING:

E-1 WIRING DETAILS
E-2 PANEL AND PENETRATION DETAILS
E-3 ATS, CONDUIT & GROUND ROD DETAILS
E-4 GENERAC GENERATOR SPECIFICATIONS
E-4.1 GENERAC GENERATOR SPECIFICATIONS
E-4.2 GENERAC GENERATOR SPECIFICATIONS
E-5 GENERAC ATS SPECIFICATIONS
E-5.1 GENERAC ATS SPECIFICATIONS

SIGNATURE BLOCK

AT&T MGR. _____ DATE _____

GENERAL DYNAMICS
CONSTRUCTION MGR. _____ DATE _____

SITE ACQUISITION _____ DATE _____

NOTES TO SUBCONTRACTOR:

1. THE GENERAL SUBCONTRACTOR MUST VERIFY ALL DIMENSIONS, CONDITIONS AND ELEVATIONS BEFORE PROCEEDING WITH THE WORK. ALL WORK SHALL BE PERFORMED IN A WORKMANLIKE MANNER IN ACCORDANCE WITH ACCEPTED CONSTRUCTION PRACTICES.
2. IT IS THE INTENTION OF THESE DRAWINGS TO SHOW THE COMPLETED INSTALLATION. THE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY BRACING, SHORING, TIES, FORM WORK, ETC. IN ACCORDANCE WITH ALL NATIONAL, STATE, AND LOCAL ORDINANCES, TO SAFELY EXECUTE ALL WORK AND SHALL BE RESPONSIBLE FOR SAME. ALL WORK SHALL BE IN ACCORDANCE WITH LOCAL CODES.
3. THE SUBCONTRACTOR SHALL USE ADEQUATE NUMBER OF SKILLED WORKMAN WHO ARE THOROUGHLY TRAINED AND EXPERIENCED IN THE NECESSARY CRAFTS AND WHO ARE COMPLETELY FAMILIAR WITH THE SPECIFIED REQUIREMENTS AND METHOD NEEDED FOR PROPER PERFORMANCE OF THE WORK.
4. CONSTRUCTION SUBCONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION SUBCONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING THE SAFETY OF ALL PERSONS AND PROPERTY, THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS AND CONSTRUCTION SUBCONTRACTOR FURTHER AGREES TO INDEMNIFY AND HOLD DESIGN ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH PERFORMANCE OF WORK ON THIS PROJECT.
5. SITE GROUNDING SHALL COMPLY WITH AT&T WIRELESS SERVICES TECHNICAL SPECIFICATIONS FOR FACILITY GROUNDING FOR CELL SITE STANDARDS, LATEST EDITION, AND COMPLY WITH AT&T TOWERS GROUNDING CHECKLIST, LATEST VERSION. WHEN NATIONAL AND LOCAL GROUNDING CODES ARE MORE STRINGENT THEY SHALL GOVERN. GROUNDING SHALL BE COMPLETED BEFORE ERECTION OF TOWER.
6. ALL WORK SHALL COMPLY WITH OSHA AND STATE SAFETY REQUIREMENTS. PROCEDURES FOR THE PROTECTION OF EXCAVATIONS, EXISTING CONSTRUCTION AND UTILITIES SHALL BE ESTABLISHED PRIOR TO FOUNDATION INSTALLATION. IF TEMPORARY LIGHTING AND MARKING IS REQUIRED BY THE FEDERAL AVIATION ADMINISTRATION (FAA), IT IS THE SUBCONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE NECESSARY LIGHTS AND NOTIFY THE PROPER AUTHORITIES IN THE EVENT OF A PROBLEM.
7. ALL WORK SHALL BE ACCOMPLISHED IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL CODES OR ORDINANCES. THE MOST STRINGENT CODE WILL APPLY IN THE CASE OF DISCREPANCIES OR DIFFERENCES IN THE CODE REQUIREMENTS.
8. ANY DAMAGE TO THE ADJACENT PROPERTIES WILL BE CORRECTED AT THE SUBCONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE LANDOWNER AND THE ENGINEER.
9. THE COMPLETE BID PACKAGE INCLUDES THESE CONSTRUCTION DRAWINGS ALONG WITH THE SPECIFICATIONS. SUBCONTRACTOR IS RESPONSIBLE FOR REVIEW OF TOTAL BID PACKAGE PRIOR TO BID SUBMITTAL.
10. SUBCONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UTILITIES WITHIN CONSTRUCTION LIMITS PRIOR TO CONSTRUCTION.
11. THE SUBCONTRACTOR IS RESPONSIBLE FOR MAINTAINING POSITIVE DRAINAGE ON THE SITE AT ALL TIMES. SILT AND EROSION CONTROL SHALL BE MAINTAINED ON THE DOWNSTREAM SIDE OF THE SITE AT ALL TIMES. ANY DAMAGE TO ADJACENT PROPERTIES WILL BE CORRECTED AT THE SUBCONTRACTOR'S EXPENSE.
12. CLEARING OF TREES AND VEGETATION ON THE SITE SHOULD BE HELD TO A MINIMUM. ONLY THE TREES NECESSARY FOR CONSTRUCTION OF THE FACILITIES SHALL BE REMOVED. ANY DAMAGE TO THE PROPERTY OUTSIDE THE LEASED PROPERTY SHALL BE REPAIRED BY THE SUBCONTRACTOR.
13. ALL SUITABLE BORROW MATERIAL FOR BACK FILL OF THE SITE SHALL BE INCLUDED IN THE BID. EXCESS TOPSOIL AND UNSUITABLE MATERIAL SHALL BE DISPOSED OF OFF SITE AT LOCATIONS APPROVED BY GOVERNING AGENCIES PRIOR TO DISPOSAL.
14. SEEDING AND MULCHING OF THE SITE WILL BE ACCOMPLISHED AS SOON AS POSSIBLE AFTER COMPLETION OF THE SITE DEVELOPMENT. THE SUBCONTRACTOR IS RESPONSIBLE FOR PROVIDING AND MAINTAIN AN ADEQUATE COVER OF VEGETATION OVER THE SITE FOR A ONE YEAR PERIOD.
15. PERMITS: THE SUBCONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING AND INCURRING THE COST OF ALL REQUIRED PERMITS, INSPECTIONS, CERTIFICATES, ETC.
16. RECORD DRAWINGS: MAINTAIN A RECORD OF ALL CHANGES, SUBSTITUTIONS BETWEEN WORK AS SPECIFIED AND INSTALLED. RECORD CHANGES ON A CLEAN SET OF CONTRACT DRAWINGS WHICH SHALL BE TURNED OVER TO THE CONSTRUCTION MANAGER UPON COMPLETION OF THE PROJECT.
17. THE PLANS SHOW SOME KNOWN SUBSURFACE STRUCTURES, ABOVE GROUND STRUCTURES AND/OR EXISTING UTILITIES BELIEVED TO BE IN THE WORKING AREA. IT IS THE RESPONSIBILITY OF THE SUBCONTRACTOR TO VERIFY ALL UTILITIES, PIPELINES AND OTHER STRUCTURES SHOWN OR NOT SHOWN ON THESE PLANS. THE SUBCONTRACTOR SHALL CONTACT THE LOCAL JURISDICTION'S DIGGER'S HOTLINE BEFORE DIGGING OR DRILLING. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED TO THE SATISFACTION OF THE OWNER AND ENGINEER AT THE SUBCONTRACTOR'S EXPENSE.

GENERAL NOTES:

1. THIS PROPOSAL IS FOR THE ADDITION OF A NEW GENERATOR ON A CONCRETE PAD TO AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY CONSISTING OF AN EQUIPMENT SHELTER AND TOWER.
2. THE PROPOSED FACILITY WILL BE UNMANNED AND DOES NOT REQUIRE POTABLE WATER OR SEWER SERVICE.
3. THE PROPOSED FACILITY IS UNMANNED AND IS NOT FOR HUMAN HABITAT. (NO HANDICAP

- ACCESS IS REQUIRED)
4. OCCUPANCY IS LIMITED TO PERIODIC MAINTENANCE AND INSPECTION, APPROXIMATELY 2 TIMES PER MONTH BY AT&T TECHNICIANS.
 5. OUTDOOR STORAGE AND SOLID WASTE CONTAINERS ARE NOT PROPOSED.
 6. ALL MATERIAL SHALL BE FURNISHED AND WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
 7. SUBCONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE CAUSED BY THE CONSTRUCTION OPERATION.
 8. SUBCONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTION REQUIRED FOR CONSTRUCTION.
 9. SUBCONTRACTOR SHALL REMOVE ALL TRASH AND DEBRIS FROM THE SITE ON A DAILY BASIS.

ELECTRICAL NOTES:
A. GENERAL

1. COORDINATE LOCATION AND POWER REQUIREMENTS OF ALL EQUIPMENT WITH AT&T AND EQUIPMENT SUPPLIER PRIOR TO INSTALLATION.
2. COORDINATE LOCATION AND REQUIREMENTS FOR ELECTRICAL AND TELEPHONE SERVICES WITH THE PROPERTY REPRESENTATIVE, AT&T AND UTILITY COMPANIES. ROUTING OF CONDUITS MAY BE MODIFIED TO MEET SITE REQUIREMENTS. EXACT CONDUIT ROUTING TO BE DETERMINED IN THE FIELD.
3. ALL WIRING AND EQUIPMENT SHOWN ON ELECTRICAL SHEETS SHALL BE FURNISHED AND INSTALLED UNDER ELECTRICAL PORTION OF CONTRACT UNLESS OTHERWISE NOTED
4. UNINTERRUPTED ELECTRICAL SERVICE FOR EXISTING EQUIPMENT SHALL BE MAINTAINED DURING THE INSTALLATION OF THE WORK DESCRIBED UNDER THESE DOCUMENTS. TEMPORARY EQUIPMENT, CABLES AND WHATEVER ELSE IS NECESSARY SHALL BE PROVIDED AS REQUIRED TO MAINTAIN ELECTRICAL SERVICE. TEMPORARY SERVICE FACILITIES, IF REQUIRED AT ANY TIME, SHALL NOT BE DISCONNECTED OR REMOVED UNTIL NEW SERVICE EQUIPMENT IS IN PROPER OPERATION. IF ANY SERVICE OR SYSTEM MUST BE INTERRUPTED, THE CONTRACTOR SHALL REQUEST PERMISSION IN WRITING STATING THE DATE, TIME, ETC. THE SERVICE WILL BE INTERRUPTED AND THE AREAS AFFECTED. THIS REQUEST SHALL BE MADE IN SUFFICIENT TIME FOR PROPER ARRANGEMENTS TO BE MADE. WRITTEN PERMISSION SHALL BE OBTAINED FROM THE OWNER BEFORE INTERRUPTING ELECTRICAL SERVICE.
5. COORDINATE NEW WORK WITH OTHER TRADES AND VERIFY EXISTING CONDITIONS TO AVOID INTERFERENCE. IN CASE OF INTERFERENCE, AT&T'S REPRESENTATIVE WILL DECIDE WHICH WORK IS TO BE RELOCATED, REGARDLESS OF WHICH WAS FIRST INSTALLED.
6. THE INSTALLATION MUST COMPLY WITH NEC AND ALL FEDERAL, STATE AND LOCAL RULES AND REGULATIONS.
7. THE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF SYSTEMS AND EQUIPMENT UNLESS OTHERWISE DEFINED BY DIMENSIONS OR DETAILS. EXACT EQUIPMENT LOCATIONS AND RACEWAY ROUTING SHALL BE GOVERNED BY ACTUAL FIELD CONDITIONS AND/OR DIRECTIONS FROM AT&T'S REPRESENTATIVE.
8. CONTRACTOR SHALL PAY ALL PERMITS AND FEES REQUIRED.
9. ALL MATERIALS SHALL BE FURNISHED AND WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF THE STANDARDS REFERENCED BELOW:
 - a. ANSI (AMERICAN NATIONAL STANDARDS INSTITUTE)
 - b. ASTM (AMERICAN SOCIETY FOR TESTING MATERIALS)
 - c. ETL (ELECTRICAL TESTING LABORATORY)
 - d. ICEA (INSULATED CABLE ENGINEERS ASSOCIATION)
 - e. IEEE (INSTITUTE OF ELECTRICAL AND ELECTRONIC ENGINEERS)
 - f. MBFU (NATIONAL BOARD OF FIRE UNDERWRITERS)
 - g. NESC (NATIONAL ELECTRICAL SAFETY CODE)
 - h. NEMA (NATIONAL ELECTRICAL MANUFACTURER'S ASSOCIATION)
 - i. NFPA (NATIONAL FIRE PROTECTION ASSOCIATION)
 - j. UL (UNDERWRITER'S LABORATORY)
10. CONTRACTOR SHALL REVIEW PLANS, DETAILS AND SPECIFICATIONS IN DETAIL AND ADJUST WORK TO CONFORM WITH ACTUAL SITE CONDITIONS SO THAT ELECTRICAL DEVICES AND EQUIPMENT WILL BE LOCATED AND READILY ACCESSIBLE. QUANTITIES LISTED IN MATERIAL LISTS ON THE DRAWINGS ARE FOR INFORMATION ONLY. THE CONTRACTOR SHALL PROVIDE HIS OWN TAKEOFF FOR MATERIAL QUANTITY AND TYPES BASED ON ACTUAL SITE CONDITIONS, IN ADDITION, CONTRACTOR SHALL PROVIDE ALL NECESSARY MATERIALS TO INSTALL EQUIPMENT FURNISHED BY AT&T OR ITS SUPPLIERS. ALL ITEMS NOT SPECIFICALLY MENTIONED HEREIN OR SHOWN ON THE DRAWINGS, BUT WHICH ARE OBVIOUSLY NECESSARY TO MAKE A COMPLETE WORKING INSTALLATION, SHALL BE INCLUDED.

- B. WIRING/CONDUIT
1. PROVIDE PULL BOXES AND JUNCTION BOXES WHERE SHOWN OR AS REQUIRED BY CODE SUCH THAT NO MORE THAN THE EQUIVALENT OF FOUR QUARTER BENDS (380 DEGREES TOTAL) EXIST IN A CONDUIT RUN.
 2. ALL POWER AND CONTROL/INDICATION WIRING SHALL BE TYPE THHN/THWN 800V RATED 75 DEGREES CELSIUS, UNLESS NOTED OTHERWISE.

3. SCHEDULE 80 PVC CONDUIT SHALL BE USED ABOVE GROUND, WHERE ABOVE GRADE IS DEFINED AS THE GROUND OF THE TURN-UP
4. BELL END OR TERMINAL ADAPTER MUST BE INSTALLED ON END OF PVC CONDUIT PER NEC 352.4G. 300.4 F. (3)
5. CONDUIT BENDS SHALL BE MADE IN ACCORDANCE WITH NEC TABLE 34G-1 O. NO RIGHT ANGLE DEVICE OTHER THAN STANDARD CONDUIT ELBOWS WITH 1/2" MINIMUM INSIDE SWEEPS FOR ALL CONDUITS 2" OR LARGER.
6. POWER WIRING SIZE SHALL NOT BE SMALLER THAN #12 AWG.
7. ALL WIRING SHALL BE COPPER. ALUMINUM WILL NOT BE ACCEPTABLE ALL POWER CIRCUITS SHALL CONTAIN A GROUND WIRE.
8. PHASE MARKINGS TO BE USED AT POWER CONDUCTOR TERMINATIONS.
9. CONTRACTOR SHALL ENSURE INTEGRITY IS MAINTAINED WHEN INSTALLING CONDUIT AND WIRING.
10. INSTALL PULL STRING IN ALL CONDUIT.

- C. EQUIPMENT
1. EQUIPMENT/PARTS CONNECTED TO EXISTING PANELS, DUCTS, ETC. SHALL MATCH THE CHARACTERISTICS (AVC, V, A) OF THAT EQUIPMENT.
 2. ALL ELECTRICAL EQUIPMENT OUTSIDE SHALL BE NEMA OR 3R RATED.


- D. GROUNDING
1. ALL GROUND CONNECTIONS TO BUILDING SHALL BE MADE USING TWO-HOLE CONNECTORS. PROVIDE STAINLESS STEEL BOLTS AND LOCK WASHERS ON ALL MECHANICAL GROUND CONNECTIONS.
 2. ALL EQUIPMENT SURFACES TO BE BONDED TO GROUNDING SYSTEM SHALL BE STRIPPED OF ALL PAINT AND DIRT. CONNECTIONS TO VARIOUS METALS SHALL BE OF A TYPE AS TO CAUSE A GALVANIC OR CORROSIVE REACTION. AREA SHALL BE REPAINTED FOLLOWING BONDING.
 3. ANY METALLIC ITEM WITHIN 6' OF GROUND CONDUCTORS MUST BE CONNECTED TO THE GROUNDING SYSTEM.
 4. EXTERIOR, ABOVE GRADE GROUND CONNECTIONS SHALL BE FURNISHED WITH A LIBERAL PROTECTIVE COATING OF ANTI-OXIDE COMPOUND.
 5. ALL MATERIALS AND LABOR REQUIRED FOR THE GROUNDING SYSTEM AS INDICATED ON THE PLANS AND DETAILS, AND AS DESCRIBED HEREIN SHALL BE FURNISHED BY THIS CONTRACTOR UNLESS OTHERWISE NOTED.
 6. EXACT LOCATION OF GROUND CONNECTION POINTS SHALL BE DETERMINED IN FIELD. ADJUST LOCATIONS INDICATED ON PLANS ACCORDING TO ACTUAL EQUIPMENT LOCATIONS TO KEEP THE GROUND CONNECTION CABLES AS SHORT AS PRACTICAL.
 7. PROVIDE ALL ELECTRICAL SYSTEM AND EQUIPMENT GROUNDS AS REQUIRED BY THE CURRENT EDITION OF THE NATIONAL ELECTRIC CODE AND THE CURRENT EDITION OF THE NATIONAL ELECTRICAL SAFETY CODE. BONDING JUMPERS WITH APPROVED GROUND FITTINGS SHALL BE INSTALLED AT ALL RACEWAYS, EQUIPMENT ENCLOSURES, PULL BOXES, ETC. TO MAINTAIN GROUND CONTINUITY WHERE REQUIRED BY CODE.
 8. ALL EQUIPMENT GROUND CONDUCTORS SHALL BE TIN COATED, #2 AWG COPPER UNLESS NOTED OTHERWISE ON THE DRAWINGS.
 9. PROVIDE PRE AND POST GROUND TEST RESULTS, USING CLAMP-ON TESTER. TEST RESULTS SHALL BE PHOTOS WITH DIGITAL TIME AND GPS STAMPED/EMBEDDED.

- E. INSPECTION/DOCUMENTATION
1. THE CONTRACTOR, UPON COMPLETION OF HIS WORK, SHALL PROVIDE AS-BUILT DRAWINGS. INFORMATION SHOULD BE GIVEN TO THE GENERAL CONTRACTOR FOR INCLUSION IN FINAL AS-BUILT SURVEY DOCUMENTS TO BE GIVEN TO THE OWNER.
 2. CONTRACTOR SHALL SUPPLY DOCUMENTATION ATTESTING TO THE COMPLETE GROUND SYSTEM'S RECEPTIVITY (MAX. 5 OHMS).
 3. AN ELECTRICAL INSPECTION SHALL BE MADE BY AND INSPECTING AGENCY APPROVED BY AT&T'S REPRESENTATIVE. CONTRACTOR SHALL COORDINATE ALL INSPECTIONS AND OBTAIN POWER COMPANY APPROVAL.
 4. CONTRACTOR SHALL HAVE ATS AND GENERATOR RELAY INSTALLATION AND CONNECTIONS INSPECTED BY OTHERS TO ENSURE THAT UL LISTING FOR THAT EQUIPMENT IS NOT VOIDED.



CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.
GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |

| ISSUE PHASE | FINAL | DATE ISSUED | 12/19/2022 |
|-------------|-------|-------------|------------|
| | | | |

PROJECT TITLE:
**HEBRON NORTH
 CENTRAL
 FA ID # 10071077**

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
GENERAL NOTES

SCALE: NONE

| | |
|----------------|-------|
| PROJECT NUMBER | 57102 |
| SHEET NUMBER | N-1 |




RAMAKER
 employee-owned
 (608) 643-4100 www.ramaker.com

PREPARED FOR:

CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.
 GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



[Signature] 12/19/2022
 Signature: Date:


| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |

| MARK | DATE | DESCRIPTION |
|-------------|-------|------------------------|
| ISSUE PHASE | FINAL | DATE ISSUED 12/19/2022 |


PROJECT TITLE:
**HEBRON NORTH
 CENTRAL
 FA ID # 10071077**

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
SITE PLAN



PROJECT NUMBER: **57102**
 SHEET NUMBER: **A-1**





SITE PLAN
 SCALE: 1" = 10'

SCOPE OF WORK DETAILS

- GENERAL:
- NEW GENERAC DIESEL GENERATOR PROVIDED BY GENERAL DYNAMICS & INSTALLED BY GENERAL CONTRACTOR, SEE E-4.
 - NEW 4'-0" X 10'-0" CONCRETE PAD PROVIDED & INSTALLED BY GENERAL CONTRACTOR (AS REQUIRED) SEE S-1
 - NEW GENERAC AUTOMATIC TRANSFER SWITCH PROVIDED BY GENERAL DYNAMICS & INSTALLED BY CONTRACTOR (AS REQUIRED) SEE E-3 & E-5.
 - CONTRACTOR TO VERIFY ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION
 - CONTRACTOR SHALL RESTORE & REPAIR ANY DAMAGED AREAS CAUSED BY CONSTRUCTION TO ORIGINAL OR BETTER CONDITION

- CONDUITS:
- INSTALL PULL STRING IN EACH CONDUIT
 - (1) NEW 2" AND (1) NEW 1" ELECTRICAL CONDUITS WITH CONDUCTORS TO RUN FROM NEW GENERATOR TO NEW ATS. CONDUIT PROVIDED AND INSTALLED BY GENERAL CONTRACTOR. SEE E-1, E-2 & E-3.
 - (1) NEW 1" ELECTRICAL CONDUIT WITH CONDUCTORS TO RUN FROM NEW GENERATOR TO AC PANEL. CONDUIT PROVIDED & INSTALLED BY GENERAL CONTRACTOR. SEE E-1, E-2 & E-3.
 - (1) NEW 1" ALARM CONDUIT & CABLING PROVIDED & INSTALLED BY GENERAL CONTRACTOR. SEE E-1, E-2 & E-3.


- GROUNDING:
- NEW EXOTHERMIC CONNECTION FROM EXISTING GROUND RING TO NEW MECHANICAL CONNECTION AT GENERATOR CHASSIS. GENERAL CONTRACTOR TO VERIFY LOCATION IN FIELD. LOCATE GROUND RODS NO MORE THAN 8'-0" APART.



PREPARED FOR:

CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.
 GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *[Signature]* Date: 12/19/2022


| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |

| ISSUE PHASE | DATE ISSUED |
|-------------|-------------|
| FINAL | 12/19/2022 |


PROJECT TITLE:
HEBRON NORTH CENTRAL
FA ID # 10071077

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248


SHEET TITLE:
SITE PLAN & EQUIPMENT LAYOUT



PROJECT NUMBER: 57102
 SHEET NUMBER: A-2



FOUNDATION PLAN
 SCALE: NTS



SECTION A-A
 SCALE: NTS

DOUBLE WALL FUEL TANK BASE SPECIFICATION

REF: ATT 30KW GENERATOR PACKAGE
 UL REGISTRATION NUMBER: MH18459
 U.L. 142 DOUBLE WALL FUEL TANK BASE SPECIFICATION
 FUEL TANK BASE CONSTRUCTION:

- BE CONSTRUCTED IN ACCORDANCE WITH UNDERWRITERS LABORATORIES STANDARD UL-142. BE CONSTRUCTED IN ACCORDANCE WITH FLAMMABLE & COMBUSTIBLE LIQUIDS CODE, NFPA 30; THE STANDARD FOR INSTALLATION & USE OF STATIONARY COMBUSTIBLE ENGINE & GAS TURBINES, NFPA 37; AND THE STANDARD FOR EMERGENCY & STANDBY POWER SYSTEMS, NFPA 110.
- ANCHORS MINIMUM (4) @ 5/8" FOR GEN-SET MOUNTING


SUB BASE TANK TESTING: PRIMARY TANK & SECONDARY CONTAINMENT BASIN SECTIONS SHALL BE PRESSURIZED AT 3-5 PSI AND LEAK-CHECKED TO ENSURE INTEGRITY OF SUB BASE WELD SEAMS PER UL-142 STANDARDS

FUEL FILL: 5 GALLON SPILL CONTAINMENT WITH ALARM

- 40% REMAINING FOR ALARM
- 20% REMAINING FOR SHUT-DOWN


FACTORY PRE-SET AT 95% FULL FOR ALARM

FUEL CONTAINMENT BASIN: SUB BASE TANK SHALL INCLUDE A WELDED STEEL CONTAINMENT BASIN, SIZED AT A MINIMUM OF 110% OF THE TANK CAPACITY TO PREVENT ESCAPE OF FUEL INTO THE ENVIRONMENT IN THE EVENT OF A TANK RUPTURE. A FUEL CONTAINMENT BASIN LEAK DETECTOR SWITCH SHALL BE PROVIDED.



SLIPJOINT DETAIL
 SCALE: NTS

NOTE:
 VERIFY WIRE AND CONDUIT QUANTITY & SIZES WITH GENERATOR MAKE & MODEL # PRIOR TO INSTALLATION. VERIFY ELECTRICAL REQUIREMENTS WITH LOCAL UTILITY PROVIDER.



* SEPARATION DIMENSION TO BE VERIFIED WITH LOCAL UTILITY COMPANY REQUIREMENTS

- NOTES:
- PROVIDE PVC CONDUIT BELOW GRADE EXCEPT AS NOTED BELOW.
 - PROVIDE RG5 CONDUIT AND ELBOWS AT STUB UP LOCATIONS (I.E. SERVICE POLE, BTS EQUIPMENT, ETC.)
 - INSTALL UTILITY PULLBOXES PER NEC.

UTILITY CONDUIT TRENCH
 SCALE: NTS

STRUCTURAL GENERAL NOTES

- GENERAL CONDITIONS
 - DESIGN & CONSTRUCTION OF ALL WORK SHALL CONFORM TO LOCAL BUILDING CODES, ACI 318-11. IN CASE OF CONFLICT BETWEEN THE CODES, STANDARDS, REGULATIONS, SPECIFICATIONS, GENERAL NOTES AND/OR MANUFACTURER'S REQUIREMENTS, USE THE MOST STRINGENT PROVISIONS.
 - IT IS THE EXPRESS INTENT OF PARTIES INVOLVED IN THIS PROJECT THAT THE CONTRACTOR OR SUBCONTRACTOR OR INDEPENDENT CONTRACTOR OR THE RESPECTIVE EMPLOYEES SHALL EXCULPATE THE ARCHITECT, THE ENGINEER, TECH. CONSTRUCTION MANAGER, THE OWNER, & THEIR AGENTS FROM ANY LIABILITY WHATSOEVER & HOLD THEM HARMLESS AGAINST LOSS, DAMAGES, LIABILITY OR ANY EXPENSE ARISING IN ANY MATTER FROM THE WRONGFUL OR NEGLIGENT ACT, OR FAILURE TO CARRY METHODS, TECHNIQUES OR PROCEDURES OR FAILURE TO CONFORM TO THE STATE SCAFFOLDING ACT IN CONNECTIONS WITH THE WORK.
 - DO NOT SCALE DRAWINGS
 - VERIFY ALL EQUIPMENT MOUNTING DIMENSIONS PER MANUFACTURER DRAWINGS
 - DESIGN LOADS ARE (GENERAC):


| | |
|----------------------------------|---------------------------|
| LIVE LOAD | : 100 PSF |
| EQUIPMENT SIZE | : 889.1" H, 106" W, 38" D |
| WEIGHT WITH WOODEN SHIPPING SKID | |
| ENCLOSED GENERATOR | : 3974 LBS |
- FOR DESIGN & ANALYSIS OF THE FOUNDATION, THE MINIMUM NET SOIL BEARING CAPACITY SHALL BE ASSUMED TO BE 2000 PSF.
- CONCRETE
 - MEET OR EXCEED THE FOLLOWING CODES & STANDARDS:

| | |
|-----------------|--|
| DESIGN | : ACI 318-11 |
| CONSTRUCTION | : ACI 301 |
| DETAILING | : CRSI MANUAL OF STANDARD PRACTICE |
| REINF. STEEL | : ASTM A 615 GRADE 60, DEFORMED |
| MIXING | : ASTM C 94. READY MIX CONCRETE |
| AIR ENTRAINMENT | : ACI 318 AND ASTM C-260 |
| AGGREGATE | : ASTM C 33 AND C 330 (FOR LIGHT WEIGHT) |
 - CONCRETE STRENGTH AT 28 DAYS SHALL BE 4000 PSI MINIMUM
 - DO NOT FIELD BEND OR WELD TO GRADE 60 REINFORCED STEEL
 - PROVIDE AIR ENTRAINMENT CONCRETE WITH AIR CONTENT OF 5 TO 7% FOR ALL CONCRETE EXPOSED TO EARTH OR WEATHER.
 - MAXIMUM AGGREGATE SIZE: 3/4"
 - DO NOT USE IN ADMIXTURE, WATER OR OTHER CONSTITUENTS OF CONCRETE WHICH HAS CALCIUM CHLORIDE.
 - MINIMUM COVER FOR REINFORCING STEEL SHALL BE AS SHOWN ON PLAN.
 - FOUNDATION & EXCAVATION NOTES
 - SLAB SHALL BE CONSTRUCTED UPON UNDISTURBED, NATURAL SUBGRADE OR COMPACTED GRANULAR FILL WITH AN ASSUMED MINIMUM NET ALLOWABLE BEARING CAPACITY OF 1800 PSF.
 - ALL ORGANIC AND/OR OTHER UNSUITABLE MATERIAL SHALL BE REMOVED FROM FOUNDATION & SLAB SUBGRADE & BACKFILL AREAS, & THEN BACKFILLED WITH ACCEPTABLE GRANULAR FILL COMPACTED TO 95% OF MAXIMUM DENSITY AT OPTIMUM MOISTURE CONTENT (ASTM D 1557).
 - THE CONTRACTOR SHALL PROVIDE ALL NECESSARY MEASURES TO PREVENT ANY WATER, FROST, OR ICE FROM PENETRATING ANY FOOTING OR STRUCTURAL SUBGRADE BEFORE & AFTER PLACING OF CONCRETE, AND UNTIL SUCH CONCRETE HAS FULLY CURED.

PREPARED FOR:

CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.
 GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: _____ Date: 12/19/2022

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |

| ISSUE PHASE | FINAL | DATE ISSUED | 12/19/2022 |
|-------------|-------|-------------|------------|
| | | | |

PROJECT TITLE:
HEBRON NORTH CENTRAL
 FA ID # 10071077

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
FOUNDATION DETAILS

SCALE: NONE

PROJECT NUMBER: 57102
 SHEET NUMBER: S-1

DIAGRAM CIRCUIT SCHEDULE

| NO. | FROM | TO | WIRES | GROUND | CONDUIT SIZE | FUNCTION |
|-----|-----------------------------------|---------------------------|---------------------------------------|-------------------------------|----------------|--|
| 1 | NORMAL POWER SOURCE | AUTOMATIC TRANSFER SWITCH | (3) 3/0 | (1) #4 | 2" | NORMAL POWER FEEDER TO ATS (CUT BACK EXISTING) |
| 2 | AUTOMATIC TRANSFER SWITCH | LOAD CENTER | (3) 3/0 | (1) #4 | 2" | POWER FEEDER FROM ATS TO PANEL |
| 3 | GENERATOR | AUTOMATIC TRANSFER SWITCH | (3) #1 | (1) #6 | 1-1/2" | EMERGENCY POWER FEEDER TO ATS |
| 4 | AUTOMATIC TRANSFER SWITCH | GENERATOR | (2) #10 | (1) #10 | 1" | START CIRCUIT |
| 5 | LOAD CENTER (DISTRIBUTION CENTER) | GENERATOR, ATS | (2) #12 (2) #12 (2) #12 | (1) #12 (1) #12 (1) #12 | 1" 1" 1" | CIRCUIT FOR GENERATOR BLOCK HEATER & BATTERY HEATER CIRCUIT FOR BATTERY CHARGER CIRCUIT FOR ATS |
| 6 | GENERATOR | AUTOMATIC TRANSFER SWITCH | 1 2-PAIR 24 AWG OR 2EA 6-PAIR CAT5 | N/A | 1" | ALARM CABLES (1) 12 PAIR 24 AWG. PROVIDE 24" OF SLACK CABLE. FINAL PUNCH DOWN IS BY AT&T TECH. LABEL ALL WIRES |
| 7 | AUTOMATIC TRANSFER SWITCH | ALARM BLOCK | 1 2-PAIR 24 AWG OR 2EA 6-PAIR CAT5 | N/A | 1" | ALARM CABLES (1) 12 PAIR 24 AWG (RUN TO PURCELL CABINET & INTO ALARM BOX). PROVIDE 24" OF SLACK CABLE. FINAL PUNCH DOWN IS BY AT&T TECH. LABEL ALL WIRES |

CIRCUIT DETAIL

SCALE: NTS

1

ALARM WIRE IDENTIFICATION CHART


| WIRE | ALARM |
|--|-------------------|
| BROWN BROWN / WHITE | GENERATOR RUNNING |
| GREEN GREEN / WHITE | CRITICAL FAULT |
| BLUE BLUE / WHITE | MINOR FAULT |
| ORANGE | LOW FUEL |
| ORANGE / WHITE BROWN * BROWN / WHITE * | FUEL LEAK |

*CAT5 CABLE ONLY, FROM 2ND CAT5 CABLE

ALARM WIRING IDENTIFICATION CHART

SCALE: NTS

2



PROPOSED WIRING DIAGRAM

SCALE: NTS

3



PREPARED FOR:




CONSULTANT:

GENERAL DYNAMICS
Information Technology, Inc.

GENERAL DYNAMICS
101 STATION DR
WESTWOOD, MA 02090

Certification & Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *[Signature]* Date: 12/19/2022

| MARK | DATE | DESCRIPTION |
|-------|-------|------------------------|
| ISSUE | FINAL | DATE ISSUED 12/19/2022 |

PROJECT TITLE:
HEBRON NORTH CENTRAL
FA ID # 10071077

PROJECT INFORMATION:
768 GILEAD STREET
HEBRON, CT 06248

SHEET TITLE:
WIRING DETAILS

SCALE: NONE

PROJECT NUMBER: 57102
SHEET NUMBER: E-1

AC Distribution Panel - Layout Diagram


| Breaker Position | Breaker Type | On/Off | Size | Circuit Label | Breaker Position | Breaker Type | On/Off | Size | Circuit Label |
|------------------|--------------|--------|------|-----------------------------|------------------|--------------|--------|------|---------------------|
| 1 | 1P | ON | N/A | GE PP 120V OUTLET | 2 | | | | |
| 3 | 1P | OFF | N/A | SPARE | 4 | 2P | ON | 30 | SURGE ARRESTOR |
| 5 | | | | GE POWER PLANT RECTIFIER #1 | 6 | 1P | ON | N/A | UNKNOWN |
| 7 | 2P | ON | N/A | | 8 | 1P | ON | N/A | PURCEL 120V OUTLET |
| 9 | | | | GE POWER PLANT RECTIFIER #2 | 10 | | | | |
| 11 | 2P | ON | N/A | | 12 | 2P | ON | N/A | UMTS |
| 13 | | | | GE POWER PLANT RECTIFIER #3 | 14 | 1P | ON | 20 | ATS |
| 15 | 2P | ON | N/A | | 16 | 1P | ON | 20 | BLOCK HEATER |
| 17 | | | | GE POWER PLANT RECTIFIER #4 | 18 | 1P | ON | 20 | BATTERY CHARGER |
| 19 | 2P | ON | N/A | | 20 | | | | EMPTY |
| 21 | | | | RECTIFIER #6 | 22 | 1P | ON | N/A | TELCO GFI |
| 23 | 2P | OFF | N/A | | 24 | 1P | ON | N/A | BACKBOARD GFI LIGHT |

PROPOSED 20A BREAKERS FOR ATS, BLOCK HEATER AND BATTERY CHARGER ON NEW AT#T GENERATOR

EXISTING PANEL SCHEDULE

SCALE: NTS

NOTE:
 1. IF EXISTING CONSTRUCTION VARIES FROM THIS DETAIL, AN EQUAL 3-HR U.L. PENETRATION APPROPRIATE FOR THE EXISTING WALL TYPE SHALL BE CONSTRUCTED
 2. GC SHALL USE NON-SHRINKING CAULK TO WEATHERSEAL ALL PENETRATIONS INTO OR THRU SHELTER WALL.



U.L. SYSTEM NO. C-AJ-1150
 CONDUIT THROUGH BEARING WALL SIMILAR TO U.L. DESIGN NO. U902
 F RATING = 3 HR
 T RATING = 0 HR


- FLOOR OR WALL ASSEMBLY : MINIMUM 4-1/2" THICK REINFORCED LIGHTWEIGHT OR NORMAL WEIGHT (100-150 PCF) CONCRETE. WALL MAY ALSO BE CONSTRUCTED OF ANY UL CLASSIFIED CONCRETE BLOCKS*. MAX DIAMETER OF OPENING IS 4". SEE CONCRETE BLOCKS (9CATZ) CATEGORY IN THE FIRE RESISTANCE DIRECTORY FOR NAMES OF MANUFACTURERS.
- THROUGH PENETRATIONS : ONE METALLIC PIPE OR CONDUIT TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF FLOOR OR WALL ASSEMBLY. THE ANNULAR SPACE SHALL BE MINIMUM 0". (POINT CONTACT) TO MAXIMUM 1-3/8". THE FOLLOWING TYPES AND SIZES OF METALLIC PIPES OR CONDUITS MAY BE USED:
 - STEEL PIPE-NOMINAL 6" DIAMETER (OR SMALLER) SCHEDULE 40 (OR HEAVIER) STEEL PIPE.
 - IRON PIPE-NOMINAL 6" DIAMETER (OR SMALLER) CAST OR DUCTILE IRON PIPE.
 - CONDUIT - NOMINAL 4" DIAMETER (OR SMALLER) STEEL ELECTRICAL METALLIC TUBING OR NOMINAL 3-1/2" DIAMETER (OR SMALLER) STEEL CONDUIT.
- PACKING MATERIAL: MINIMUM 6" THICKNESS OF MIN 4.0 PCF MINERAL WOOL BATTING INSULATION FIRMLY PACKED INTO OPENING AS A PERMANENT FORM. PACKING MATERIAL TO BE RECESSED FROM TOP SURFACE OF FLOOR OR FROM BOTH SURFACES OF WALL AS REQUIRED TO ACCOMMODATE THE REQUIRED THICKNESS OF FILL MATERIAL.
- FILL, VOID, OR CAVITY MATERIAL*: SEALANT: MINIMUM 1/4" THICKNESS OF FILL MATERIAL APPLIED WITHIN THE ANNULUS, FLUSH WITH TOP SURFACE OF FLOOR AND WITH BOTH SURFACES OF WALL. AT THE POINT CONTACT LOCATION BETWEEN PIPE AND CONCRETE, A MINIMUM 1/2" DIAMETER BEAD OF FILL MATERIAL SHALL BE APPLIED AT THE CONCRETE/PIPE INTERFACE ON THE TOP SURFACE OF FLOOR AND ON BOTH SURFACES OF WALL. W RATING APPLIES ONLY WHEN CP6015 OR CP604 SEALANT IS USED.

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC. : CP6015, CP604, CP606, OR F5-ONE SEALANT.

* BEARING THE UL CLASSIFICATION MARK.

OUTER WALL PENETRATION DETAIL (IF APPLICABLE)

SCALE: NTS



NOTE:
 CONTRACTOR TO LABEL WIRES WITH P-TOUCH OR SIMILAR LABELS ONLY. ABSOLUTELY NO HANDWRITTEN LABELS.

*CONTRACTOR TO UTILIZE NEXT AVAILABLE IN SEQUENCE SINGLE BREAKER POSITION FOR GENERATOR, BATTERY CHARGER, BATTERY HEATER AND BLOCK HEATER

CADWELD DETAILS


SCALE: NTS

PREPARED FOR:

CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.

GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: _____ Date: 12/19/2022

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |

| MARK | DATE | DESCRIPTION |
|-------------|-------|------------------------|
| ISSUE PHASE | FINAL | DATE ISSUED 12/19/2022 |

PROJECT TITLE:
HEBRON NORTH CENTRAL
FA ID # 10071077

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
PANEL AND PENETRATION DETAILS


SCALE: NONE

PROJECT NUMBER: 57102
 SHEET NUMBER: E-2


- 1 CONDUIT (TYP)
- 2 BUTTERFLY CLAMP AS REQUIRED
- 3 EXISTING WALL/CEILING
- 4 VERTICAL "UNISTRUT" P1000 T SERIES LENGTH BASED ON NUMBER OF CONDUIT TO BE MOUNTED

| WALL CONSTRUCTION TYPE | USE |
|-------------------------|--|
| HOLLOW | 3/8" DIA. TOGGLE BOLT |
| HOLLOW, AT STUD | 3/8" DIA. LAG SCREW |
| CONCRETE BLOCK (HOLLOW) | 3/8" DIA. HILTI HY-20 WITH SCREEN, MINIMUM EMBEDMENT 2-1/2" |
| CONCRETE (SOLID) | 3/8" DIA. HILTI HY-150 WITH SCREEN, MINIMUM EMBEDMENT 2-1/2" |

NOTE: USE GALVANIZED OR STAINLESS STEEL HARDWARE FOR WALL MOUNT & CONNECTIONS OF CHANNELS SPACE UNITS @ 5'-0" O.C. LENGTH OF RUN



CONDUIT WALL MOUNT
 SCALE: NTS




GROUND ROD DETAIL
 SCALE: NTS

- NOTE:
- GROUND RODS MAY BE:
 - COPPER CLAD STEEL
 - SOLID COPPER
 - GROUND RODS SHALL HAVE A MAXIMUM SPACING TWICE THE LENGTH OF ROD
 - SEE RESISTIVITY REPORT FOR VERIFICATION AS AVAILABLE
 - A LARGER CONDUCTOR SHALL BE REQUIRED IN AREAS HIGHLY PRONE TO LIGHTNING AND/OR AREAS WITH HIGHLY ACIDIC SOIL
 - GROUND RODS INSTALLED WITHIN CLOSE PROXIMITY TO TOWER OR WHEN SOIL IS AT OR BELOW 2,000 OHM-CM, SHALL BE GALVANIZED TO PREVENT GALVANIC CORROSION OF TOWER, (SEE ANSI/TIA-EIA-222-G)
 - PROVIDE (1) GROUND LEAD TO EACH SIDE OF THE GENERATOR

| WALL CONSTRUCTION TYPE | USE |
|-------------------------|--|
| HOLLOW | 3/8" DIA. TOGGLE BOLT |
| HOLLOW, AT STUD | 3/8" DIA. LAG SCREW |
| CONCRETE BLOCK (HOLLOW) | 7/16" DIA. HILTI HY-20 WITH SCREEN MINIMUM EMBEDMENT 2-1/2" |
| CONCRETE (SOLID) | 7/16" DIA. HILTI HY-150 WITH SCREEN MINIMUM EMBEDMENT 2-1/2" |

- NOTE:
- USE GALVANIZED OR STAINLESS STEEL HARDWARE FOR WALL MOUNT AND CONNECTION OF CHANNELS
 - GC SHALL USE NON-SHRINKING CAULK TO WEATHER SEAL ALL PENETRATIONS INTO OR THROUGH SHELTER WALL




GENERAC ATS MOUNTING DETAIL
 SCALE: NTS

RAMAKER
 employee-owned
 (608) 643-4100 www.ramaker.com

PREPARED FOR:

CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.
 GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *[Signature]* Date: 12/19/2022

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |

| ISSUE PHASE | DATE ISSUED |
|-------------|-------------|
| FINAL | 12/19/2022 |

PROJECT TITLE:
HEBRON NORTH CENTRAL
 FA ID # 10071077

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
ATS, CONDUIT & GROUND ROD DETAILS

SCALE: NONE

| | |
|----------------|-------|
| PROJECT NUMBER | 57102 |
| SHEET NUMBER | E-3 |

SD030 | 2.2L | 30 kW
INDUSTRIAL DIESEL GENERATOR SET
 EPA Certified Stationary Emergency



Standby Power Rating
 30 kW, 38 kVA, 60 Hz

Prime Power Rating*
 27 kW, 34 kVA, 60 Hz




Image used for illustration purposes only



*EPA Certified Prime ratings are not available in the US or its Territories

Codes and Standards

Not all codes and standards apply to all configurations. Contact factory for details.

- UL2200, UL508, UL489, UL142
- CSA C22.2
- BS5514 and DIN 6271
- SAE J1349
- NFPA 37, 70, 99, 110
- NEC700, 701, 702, 708
- ISO 3046, 7637, 8528, 9001
- NEMA ICS10, MG1, 250, ICS6, AB1
- ANSI C62.41

Powering Ahead

For over 50 years, Generac has provided innovative design and superior manufacturing.

Generac ensures superior quality by designing and manufacturing most of its generator components, including alternators, enclosures and base tanks, control systems and communications software.

Generac gensets utilize a wide variety of options, configurations and arrangements, allowing us to meet the standby power needs of practically every application.

Generac searched globally to ensure the most reliable engines power our generators. We choose only engines that have already been proven in heavy-duty industrial applications under adverse conditions.

Generac is committed to ensuring our customers' service support continues after their generator purchase.

SD030 | 2.2L | 30 kW
INDUSTRIAL DIESEL GENERATOR SET
 EPA Certified Stationary Emergency



STANDARD FEATURES

ENGINE SYSTEM

- Oil Drain Extension
- Air Cleaner
- Fan Guard
- Stainless Steel Flexible Exhaust Connection
- Factory Filled Oil and Coolant
- Radiator Duct Adapter (Open Set Only)
- Critical Silencer (Enclosed Unit Only)
- Engine Coolant Heater

Fuel System

- Fuel Lockoff Solenoid
- Primary Fuel Filter

Cooling System

- Closed Coolant Recovery System
- UV/Ozone Resistant Hoses
- Factory-Installed Radiator
- Radiator Drain Extension
- 50/50 Ethylene Glycol Antifreeze

Electrical System

- Battery Charging Alternator
- Battery Cables
- Battery Tray
- Rubber-Booted Engine Electrical Connections
- Solenoid Activated Starter Motor

ALTERNATOR SYSTEM

- UL2200 GENprotect™
- Class H Insulation Material
- 2/3 Pitch
- Skewed Stator
- Brushless Excitation
- Sealed Bearing
- Rotor Dynamically Spin Balanced
- Amortisseur Winding (3-Phase Only)
- Full Load Capacity Alternator
- Protective Thermal Switch

GENERATOR SET

- Internal Genset Vibration Isolation
- Separation of Circuits - High/Low Voltage
- Separation of Circuits - Multiple Breakers
- Wrapped Exhaust Piping
- Standard Factory Testing
- 2 Year Limited Warranty (Standby Rated Units)
- 1 Year Limited Warranty (Prime Rated Units)
- Silencer Mounted in the Discharge Hood (Enclosed Unit Only)

ENCLOSURE (If Selected)

- Rust-Proof Fasteners with Nylon Washers to Protect Finish
- High Performance Sound-Absorbing Material (Sound Attenuation Enclosures)
- Gasketed Doors
- Stamped Air-Intake Louvers
- Upward Facing Discharge Hoods (Radiator and Exhaust)
- Stainless Steel Lift Off Door Hinges
- Stainless Steel Lockable Handles
- RhinoCoat™ - Textured Polyester Powder Coat Paint

FUEL TANKS (If Selected)

- UL 142/ULC S601
- Double Wall
- Normal and Emergency Vents
- Sloped Top
- Sloped Bottom
- Factory Pressure Tested
- Rupture Basin Alarm
- Fuel Level
- Check Valve In Supply and Return Lines
- RhinoCoat™ - Textured Polyester Powder Coat Paint
- Stainless Steel Hardware

CONTROL SYSTEM



Digital H Control Panel- Dual 4x20 Display

Program Functions

- Programmable Crank Limiter
- 7-Day Programmable Exerciser
- Special Applications Programmable Logic Controller
- RS-232/485 Communications
- All Phase Sensing Digital Voltage Regulator
- 2-Wire Start Capability
- Data/Time Fault History (Event Log)
- Isochronous Governor Control
- Waterproof/Sealed Connectors

- Audible Alarms and Shutdowns
- Not in Auto (Flashing Light)
- Auto/Off/Manual Switch
- E-Stop (Red Mushroom-Type)
- NFPA110 Level I and II (Programmable)
- Customizable Alarms, Warnings, and Events
- Modbus® Protocol
- Predictive Maintenance Algorithm
- Sealed Boards
- Password Parameter Adjustment Protection
- Single Point Ground
- 16 Channel Remote Trending
- 0.2 msec High Speed Remote Trending
- Alarm Information Automatically Annunciated on the Display

Full System Status Display

- Power Output (kW)
- Power Factor
- kW Hours, Total, and Last Run
- Real/Reactive/Apparent Power
- All Phase AC Voltage
- All Phase Currents

- Oil Pressure
- Coolant Temperature
- Coolant Level
- Engine Speed
- Battery Voltage
- Frequency

Alarms and Warnings

- Oil Pressure
- Coolant Temperature
- Coolant Level
- Engine Overspeed
- Battery Voltage
- Alarms and Warnings Time and Date Stamped
- Snap Shots of Key Operation Parameters During Alarms and Warnings
- Alarms and Warnings Spelled Out (No Alarm Codes)




PREPARED FOR:



CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.

GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: _____ Date: 12/19/2022

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |

| ISSUE PHASE | FINAL | DATE ISSUED | 12/19/2022 |
|-------------|-------|-------------|------------|
|-------------|-------|-------------|------------|

PROJECT TITLE:
HEBRON NORTH CENTRAL
FA ID # 10071077

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
GENERAC 30KW GENERATOR SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER: 57102
 SHEET NUMBER: E-4

SPEC SHEET

1 of 6

SPEC SHEET

2 of 6

SD030 | 2.2L | 30 kW
INDUSTRIAL DIESEL GENERATOR SET
 EPA Certified Stationary Emergency



CONFIGURABLE OPTIONS

ENGINE SYSTEM

- Oil Heater
- Critical Silencer (Open Set Only)
- Radiator Stone Guard
- Level 1 Fan and Belt Guards (Open Set Only)

FUEL SYSTEM

- NPT Flexible Fuel Line

ELECTRICAL SYSTEM

- 10A UL Listed Battery Charger
- Battery Warmer

ALTERNATOR SYSTEM

- Alternator Upsizing
- Anti-Condensation Heater
- Tropical Coating
- Permanent Magnet Excitation

GENERATOR SET

- Extended Factory Testing
- 8 Position Load Center
- Pad Vibration Isolation

ENGINEERED OPTIONS

ENGINE SYSTEM

- Coolant Heater Isolation Ball Valves
- Fluid Containment Pan

CONTROL SYSTEM

- Spare Inputs (x4) / Outputs (x4)
- Battery Disconnect Switch

CIRCUIT BREAKER OPTIONS

- Main Line Circuit Breaker
- 2nd Main Line Circuit Breaker
- Shunt Trip and Auxiliary Contact
- Electronic Trip Breakers

ENCLOSURE

- Weather Protected Enclosure
- Level 1 Sound Attenuation
- Level 2 Sound Attenuation
- Level 2 Sound Attenuation with Motorized Dampers
- Steel Enclosure
- Aluminum Enclosure
- Up to 200 MPH Wind Load Rating (Contact Factory for Availability)
- AC/DC Enclosure Lighting Kit
- Door Alarm Switch
- Enclosure Heater
- Damper Alarm Contacts

WARRANTY (Standby Gensets Only)

- 2 Year Extended Limited Warranty
- 5 Year Limited Warranty
- 5 Year Extended Limited Warranty
- 7 Year Extended Limited Warranty
- 10 Year Extended Limited Warranty

ALTERNATOR SYSTEM

- 3rd Breaker System

GENERATOR SET

- Special Testing

CONTROL SYSTEM

- NFPA 110 Compliant 21-Light Remote Annunciator
- Remote Relay Assembly (8 or 16)
- Oil Temperature Indication and Alarm
- Remote E-Stop (Break Glass-Type, Surface Mount)
- Remote E-Stop (Red Mushroom-Type, Surface Mount)
- Remote E-Stop (Red Mushroom-Type, Flush Mount)
- 100 dB Alarm Horn
- Ground Fault Annunciation
- 120V GFCI and 240V Outlets
- Remote Communication - Modem
- 10A Engine Run Relay

FUEL TANKS (Size On Last Page)

- 8 in (203.2 mm) Fill Extension
- 13 in (330.2 mm) Fill Extension
- 19 in (482.6 mm) Fill Extension
- Overfill Protection Valve
- 5 Gallon Spill Box Return Hose
- 5 Gallon Spill Box
- Tank Risers
- Fuel Level Switch and Alarm
- 12' Vent System
- Fire Rated Stainless Steel Fuel Hose

FUEL TANKS

- UL2085 Tank
- Stainless Steel Tanks
- Special Fuel Tanks
- Vent Extensions

SD030 | 2.2L | 30 kW
INDUSTRIAL DIESEL GENERATOR SET
 EPA Certified Stationary Emergency



APPLICATION AND ENGINEERING DATA

ENGINE SPECIFICATIONS

General

| | |
|------------------------------------|-------------------------|
| Make | Perkins |
| EPA Emissions Compliance | Stationary Emergency |
| EPA Emissions Reference | See Emission Data Sheet |
| Cylinder # | 4 |
| Type | In-Line |
| Displacement - in ³ (L) | 135 (2.22) |
| Bore - in (mm) | 3.3 (84) |
| Stroke - in (mm) | 3.9 (100) |
| Compression Ratio | 23.3:1 |
| Intake Air Method | Turbocharged |
| Cylinder Head | Cast Iron |
| Piston Type | Aluminum |
| Crankshaft Type | Forged Steel |

Engine Governing

| | |
|-------------------------------------|------------------------|
| Governor | Electronic Isochronous |
| Frequency Regulation (Steady State) | ±0.5% |

Lubrication System

| | |
|-----------------------------|-------------|
| Oil Pump Type | Gear |
| Oil Filter Type | Full-Flow |
| Crankcase Capacity - qt (L) | 11.2 (10.6) |

Cooling System

| | |
|------------------------|-------------------------|
| Cooling System Type | Closed Recovery |
| Water Pump Type | Pre-Lubed, Self Sealing |
| Fan Type | Pusher |
| Fan Speed - RPM | 1,980 |
| Fan Diameter - in (mm) | 18 (457) |

Fuel System

| | |
|----------------------------|---------------------------------|
| Fuel Type | Ultra Low Sulfur Diesel Fuel #2 |
| Fuel Specifications | ASTM |
| Fuel Filtering (Microns) | 5 |
| Fuel Inject Pump | Distribution Injection Pump |
| Fuel Pump Type | Engine Driven Gear |
| Injector Type | Mechanical |
| Fuel Supply Line - in (mm) | 0.31 (7.9) ID |
| Fuel Return Line - in (mm) | 0.2 (4.8) ID |

Engine Electrical System

| | |
|----------------------------|------------------------------|
| System Voltage | 12 VDC |
| Battery Charger Alternator | Standard |
| Battery Size | See Battery Index 0161970SBY |
| Battery Voltage | 12 VDC |
| Ground Polarity | Negative |

ALTERNATOR SPECIFICATIONS

| | |
|-------------------------------------|---------------|
| Standard Model | K0035124Y21 |
| Poles | 4 |
| Field Type | Revolving |
| Insulation Class - Rotor | H |
| Insulation Class - Stator | H |
| Total Harmonic Distortion | <5% (3-Phase) |
| Telephone Interference Factor (TIF) | < 50 |

| | |
|------------------------------------|--------------------------|
| Standard Excitation | Brushless |
| Bearings | Single Sealed |
| Coupling | Direct via Flexible Disc |
| Load Capacity - Standby | 100% |
| Prototype Short Circuit Test | Yes |
| Voltage Regulator Type | Digital |
| Number of Sensed Phases | All |
| Regulation Accuracy (Steady State) | ±0.25% |



PREPARED FOR:




CONSULTANT:

GENERAL DYNAMICS
 Information Technology, Inc.

GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *[Signature]* Date: 12/19/2022

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |

| | | |
|-------------|-------|------------------------|
| MARK | DATE | DESCRIPTION |
| ISSUE PHASE | FINAL | DATE ISSUED 12/19/2022 |

PROJECT TITLE:
HEBRON NORTH CENTRAL
FA ID # 10071077

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
GENERAC 30KW GENERATOR SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER: 57102
 SHEET NUMBER: E-4.1

SPEC SHEET

3 of 6

SPEC SHEET

4 of 6

Copyright 2022 - Ramaker & Associates, Inc. - All Rights Reserved
 DRAWN BY: TRB CHECKED BY: MJR
 C:\Users\kbeaty\AppData\LocalTemp\AcPublish_1\B760V57102_1\0071077_Hebron North Central Generator ATT CDs.dwg Printed by: tbeaty on Dec 19, 2022 - 9:38pm

SD030 | 2.2L | 30 kW INDUSTRIAL DIESEL GENERATOR SET

EPA Certified Stationary Emergency

OPERATING DATA

POWER RATINGS

| | Standby |
|---------------------------------|-----------------|
| Single-Phase 120/240 VAC @1.0pf | 30 kW Amps: 125 |
| Three-Phase 120/208 VAC @0.8pf | 30 kW Amps: 104 |
| Three-Phase 120/240 VAC @0.8pf | 30 kW Amps: 90 |
| Three-Phase 277/480 VAC @0.8pf | 30 kW Amps: 45 |
| Three-Phase 346/600 VAC @0.8pf | 30 kW Amps: 36 |

MOTOR STARTING CAPABILITIES (skVA)

| skVA vs. Voltage Dip | | | |
|----------------------|-----|-------------|-----|
| 277/480 VAC | 30% | 208/240 VAC | 30% |
| K0035124Y21 | 61 | K0035124Y21 | 46 |
| K0040124Y21 | 76 | K0040124Y21 | 58 |
| K0050124Y21 | 98 | K0050124Y21 | 75 |

FUEL CONSUMPTION RATES*

| Fuel Pump Lift- ft (m) | Diesel - gph (Lph) | |
|--|--------------------|------------|
| | Percent Load | Standby |
| 3 (1) | 25% | 1.0 (3.7) |
| | 50% | 1.4 (5.2) |
| | 75% | 2.0 (7.5) |
| | 100% | 2.8 (10.5) |
| Total Fuel Pump Flow (Combustion + Return) - gph (Lph) | | |
| 16.6 (63) | | |

* Fuel supply installation must accommodate fuel consumption rates at 100% load.

COOLING

| | Standby |
|---|---|
| Coolant Flow | gpm (Lpm) 14.9 (56.2) |
| Coolant System Capacity | gal (L) 2.5 (9.5) |
| Heat Rejection to Coolant | BTU/hr (kW) 128,638 (136) |
| Inlet Air | scfm (m ³ /hr) 2,800 (4,757) |
| Maximum Operating Ambient Temperature | °F (°C) 122 (50) |
| Maximum Operating Ambient Temperature (Before Derate) | See Bulletin No. 0199280SSD |
| Maximum Radiator Backpressure | in H ₂ O (kPa) 0.5 (0.12) |

COMBUSTION AIR REQUIREMENTS

| Standby |
|--|
| Flow at Rated Power scfm (m ³ /min) |
| 88 (2.5) |

ENGINE

| | Standby |
|--------------------------|----------------------------|
| Rated Engine Speed | RPM 1,800 |
| Horsepower at Rated kW** | hp 49 |
| Piston Speed | ft/min (m/min) 1,181 (360) |
| BMEP | psi (kPa) 159 (1,096) |

** Refer to "Emissions Data Sheet" for maximum bHP for EPA and SCAQMD permitting purposes.


Deration - Operational characteristics consider maximum ambient conditions. Derate factors may apply under atypical site conditions. Please contact a Generac Power Systems Industrial Dealer for additional details. All performance ratings in accordance with ISO3046, BS5514, ISO8528, and DIN6271 standards.
Standby - See Bulletin 0187500SSB
Prime - See Bulletin 0187510SSB

GENERAC INDUSTRIAL POWER

SD030 | 2.2L | 30 kW INDUSTRIAL DIESEL GENERATOR SET


EPA Certified Stationary Emergency

DIMENSIONS AND WEIGHTS*




OPEN SET (Includes Exhaust Flex)

| Run Time - Hours | Usable Capacity - Gal (L) | L x W x H - in (mm) | Weight - lbs (kg) |
|------------------|---------------------------|--|-------------------|
| No Tank | - | 76.0 (1,930) x 37.4 (950) x 44.8 (1,138) | 1,641 (745) |
| 19 | 54 (204) | 76.0 (1,930) x 37.4 (950) x 57.8 (1,468) | 2,121 (963) |
| 47 | 132 (501) | 76.0 (1,930) x 37.4 (950) x 69.8 (1,773) | 2,351 (1,067) |
| 75 | 211 (799) | 76.0 (1,930) x 37.4 (950) x 81.8 (2,078) | 2,560 (1,162) |
| 107 | 300 (1,136) | 92.9 (2,360) x 37.4 (950) x 81.8 (2,078) | 2,623 (1,190) |




WEATHER PROTECTED ENCLOSURE

| Run Time - Hours | Usable Capacity - Gal (L) | L x W x H - in (mm) | Weight - lbs (kg) | |
|------------------|---------------------------|--|-------------------|-----------|
| | | | Steel | Aluminum |
| No Tank | - | 94.8 (2,409) x 38.0 (965) x 49.5 (1,258) | | |
| 19 | 54 (204) | 94.8 (2,409) x 38.0 (965) x 62.5 (1,588) | 372 (170) | 241 (110) |
| 47 | 132 (501) | 94.8 (2,409) x 38.0 (965) x 74.5 (1,893) | | |
| 75 | 211 (799) | 94.8 (2,409) x 38.0 (965) x 86.5 (2,198) | | |
| 107 | 300 (1,136) | 94.8 (2,409) x 38.0 (965) x 86.5 (2,198) | | |



LEVEL 1 ACOUSTIC ENCLOSURE

| Run Time - Hours | Usable Capacity - Gal (L) | L x W x H - in (mm) | Weight - lbs (kg) | |
|------------------|---------------------------|---|-------------------|-----------|
| | | | Steel | Aluminum |
| No Tank | - | 112.5 (2,857) x 38.0 (965) x 49.5 (1,258) | | |
| 19 | 54 (204) | 112.5 (2,857) x 38.0 (965) x 62.5 (1,582) | 505 (230) | 338 (154) |
| 47 | 132 (501) | 112.5 (2,857) x 38.0 (965) x 74.5 (1,893) | | |
| 75 | 211 (799) | 112.5 (2,857) x 38.0 (965) x 86.5 (2,198) | | |
| 107 | 300 (1,136) | 112.5 (2,857) x 38.0 (965) x 86.5 (2,198) | | |



LEVEL 2 ACOUSTIC ENCLOSURE

| Run Time - Hours | Usable Capacity - Gal (L) | L x W x H - in (mm) | Weight - lbs (kg) | |
|------------------|---------------------------|--|-------------------|-----------|
| | | | Steel | Aluminum |
| No Tank | - | 94.8 (2,407) x 38.0 (965) x 61.1 (1,551) | | |
| 19 | 54 (204) | 94.8 (2,407) x 38.0 (965) x 74.1 (1,881) | 510 (232) | 341 (155) |
| 47 | 132 (501) | 94.8 (2,407) x 38.0 (965) x 86.1 (2,186) | | |
| 75 | 211 (799) | 94.8 (2,407) x 38.0 (965) x 98.1 (2,491) | | |
| 107 | 300 (1,136) | 94.8 (2,407) x 38.0 (965) x 98.1 (2,491) | | |

* All measurements are approximate and for estimation purposes only. Specification characteristics may change without notice. Please contact a Generac Power Systems Industrial Dealer for detailed installation drawings.

Generac Power Systems, Inc. | P.O. Box 8 | Waukesha, WI 53189

P: (262) 544-4811 ©2018 Generac Power Systems, Inc. All rights reserved. All specifications are subject to change without notice.

Part No. 10000024842

Rev. B 08/27/18


RAMAKER
employee-owned
(608) 643-4100 www.ramaker.com

PREPARED FOR:

CONSULTANT:
GENERAL DYNAMICS
Information Technology, Inc.

GENERAL DYNAMICS
101 STATION DR
WESTWOOD, MA 02090

Certification & Seal:
I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: _____ Date: 12/19/2022

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |

ISSUE PHASE: FINAL DATE ISSUED: 12/19/2022

PROJECT TITLE:
HEBRON NORTH CENTRAL
FA ID # 10071077

PROJECT INFORMATION:
768 GILEAD STREET
HEBRON, CT 06248

SHEET TITLE:
GENERAC 30KW GENERATOR SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER: 57102
SHEET NUMBER: E-4.2

SPEC SHEET

5 of 6

SPEC SHEET

6 of 6

This document contains confidential or proprietary information of Ramaker & Associates, Inc. Neither this document nor the information herein is to be reproduced, distributed, used or disclosed either in whole or in part except as authorized by Ramaker and Associates, Inc.

**TTS Series
Switches**
**200 Amps
600 VAC**

GENERAC | **INDUSTRIAL
POWER**

TAS200

200A Automatic Transfer Switch

**TAS200
TAS200**

1 of 3 2 of 3



Image used for illustration purposes only.

The Generac TAS200 Automatic Transfer Switch

- Flexibility for multiple application installations
- Multiple generator support with 3 source panel
- Designed with a 6 inch touch screen controller for improved user interface
- Camlock functionality for mobile generator sources

Features

- **STEEL CONSTRUCTION**
- **NEMA 3R ENCLOSURE WITH HINGED "PADLOCKING" DOORS**
- **STAINLESS STEEL HARDWARE**
- **CAMLOCK "QUICK CONNECT" CAPABILITY**
- **OPERATIONAL STATUS VIEW VIA 6 INCH TOUCH SCREEN**
- **TEST FUNCTION - FAST TEST & NORMAL TEST**
- **UL1008 LISTED - FOR EMERGENCY SYSTEMS**

Optional Features

- **EXTENDED WARRANTY**
- **THREE-PHASE VOLTAGE CONFIGURATIONS**

Codes and Standards

Generac products are designed to the following standards:



UL1008,
UL508,
UL50,
CSA C22.2 No. 178



NEC 700, 701 and 702



NEMA 250

Application and Engineering Data

| Cabinet Specifications | |
|--------------------------------|---|
| Dimensions | 24"W x 12"D x 48"H |
| Weight | 210 lbs. |
| Construction | Single Chamber with Main Door |
| | Steel |
| | UL Type / NEMA 3R Rated |
| | Powder Coat Finish for Corrosion Resistance |
| | C-UL-US Listed - Automatic Transfer Switch |
| Mounting Options | Stainless Steel Hardware |
| | 3-Point Latching System with Pad-Lockable Handles |
| Installed | Wall |
| | H-frame |
| Pre-wired alarm terminal strip | |

| Electrical Specifications | |
|---|--|
| Voltage/Phase/Amps | 120/240 Single-Phase, 200A 120/208 3-Phase, 200A 120/240 3-Phase, 200A |
| Breaker | Eaton 200 amp Utility Breaker |
| | Eaton 200 amp Generator Breaker |
| Maximum RMS Symmetrical Fault Current - Amps | 25k AIC Rated |
| Protective Device Continuous Rating (Max) Amp | 200 |
| Input to Generator | 350MCM - #6 AWG |
| Output to Site | 350MCM - #6 AWG |
| Generator Annunciator Connector | Deutsch DTM04-12PA-L012 |
| Alarm Terminal Board | Generator Run Alarm |
| | Generator Fail - Shutdown Alarm |
| | Generator Fail - Non Shutdown Alarm |
| | Low Fuel Alarm |
| | Generator Theft Alarm |
| AC Utility Fail Alarm | |

| Camlock Component | |
|------------------------------------|---|
| Camlock Component | Shipped loose for multiple installation options |
| Dimensions | 9" W x 9.4" D x 24.25" H |
| 200A Camlock Generator Connection | Single-Phase: Black L1, Red L2, White-Neutral, Green-Ground |
| | 3-Phase: Black L1, Red L2, Blue L3, White-Neutral, Green-Ground |
| | Uses 4 CH E1016 Male Connectors |
| Mating Connector - CH E1016 Female | |



RAMAKER
employee-owned
(608) 643-4100 www.ramaker.com

PREPARED FOR:




CONSULTANT:

GENERAL DYNAMICS
Information Technology, Inc.

GENERAL DYNAMICS
101 STATION DR
WESTWOOD, MA 02090

Certification & Seal:

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *[Signature]* Date: 12/19/2022

| MARK | DATE | DESCRIPTION |
|-------------|-------|------------------------|
| ISSUE PHASE | FINAL | DATE ISSUED 12/19/2022 |

PROJECT TITLE:
**HEBRON NORTH
CENTRAL
FA ID # 10071077**

PROJECT INFORMATION:
768 GILEAD STREET
HEBRON, CT 06248

SHEET TITLE:
GENERAC ATS SPECIFICATIONS

SCALE: NONE


PROJECT NUMBER: 57102
SHEET NUMBER: E-5

TTS Control Systems

TAS200

3 of 3

Touch Screen Interface



INDICATORS AND BUTTONS

- | | |
|---|---|
| <ul style="list-style-type: none"> System Ready indicator Standby Operating indicator Utility Available indicator GEN/UTIL Switch Position indicator TVSS status | <ul style="list-style-type: none"> Normal Test button Fast Test button Return to Normal button Reset button Exercising indicator |
|---|---|

DETAILS SCREEN


| | |
|--|---|
| <p>System Settings:</p> <ul style="list-style-type: none"> System Voltage/Phases: <ul style="list-style-type: none"> 120/240V single phase (standard) 120/208V three phase (optional) 120/240V three phase (optional) Utility Fail Monitor: <ul style="list-style-type: none"> Under Voltage: 75-95% of nominal voltage Over Voltage: 105%-125% of nominal voltage Pickup (hysteresis): fixed at 5 volts Delay time: 0-60s Utility Interrupt Delay: 0-60s Return to Utility Timer: 1-30 minutes Transfer: <ul style="list-style-type: none"> In-phase, or Time-Delay-Neutral at 0.0-10.0s in 1 second increments | <p>Exercise Settings:</p> <ul style="list-style-type: none"> Time of day Day of week Exercise: <ul style="list-style-type: none"> Exercise with/without load Exercise once every 1, 2, or 4 weeks. Exercise time-of-day Exercise day of week Exercise duration: 15-30 minutes |
| | <p>Screen Settings:</p> <ul style="list-style-type: none"> Brightness & Contrast button Screen Calibration button Startup/Clean screen |
| | <p>Diagnostics:</p> <ul style="list-style-type: none"> Digital I/O bits status Voltage A/D readings |
| <p>Engine Settings:</p> <ul style="list-style-type: none"> Engine Warm-up timer: 0-20 minutes Generator Load Accept: <ul style="list-style-type: none"> Time-Delay-Neutral at 0.0-10.0s in 1 second increments Voltage: 85-95% of nominal Frequency: 85-95% of nominal Engine Minimum Run Timer: 5-30 minutes Engine Cooldown Timer: 0-20 minutes | <p>Mimic Diagram:</p> <ul style="list-style-type: none"> System Ready Transfer switch position Utility available Standby available Maintenance/Auto switch position Generator source TS position TVSS status |

Generac Power Systems, Inc. • S45 W29290 HWY. 59, Waukesha, WI 53189 • generac.com
 ©2013 Generac Power Systems, Inc. All rights reserved. All specifications are subject to change without notice. Bulletin 0195670SBY-B / Printed in U.S.A. 03/13/13



CONSULTANT:
GENERAL DYNAMICS
 Information Technology, Inc.
 GENERAL DYNAMICS
 101 STATION DR
 WESTWOOD, MA 02090

Certification & Seal:
 I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Connecticut.



Signature: *[Signature]* Date: 12/19/2022

| | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |

| MARK | DATE | DESCRIPTION |
|-------------|-------|------------------------|
| ISSUE PHASE | FINAL | DATE ISSUED 12/19/2022 |

PROJECT TITLE:
HEBRON NORTH CENTRAL
FA ID # 10071077

PROJECT INFORMATION:
 768 GILEAD STREET
 HEBRON, CT 06248

SHEET TITLE:
GENERAC ATS SPECIFICATIONS

SCALE: NONE

PROJECT NUMBER: 57102
 SHEET NUMBER: E-5.1

ATTACHMENT 2

The Assessor's office is responsible for the maintenance of records on the ownership of properties. Assessments are computed at 70% of the estimated market value of real property at the time of the last revaluation which was 2016.



Information on the Property Records for the Municipality of Hebron was last updated on 12/13/2021.



Parcel Information

| | | | | | |
|--------------------------|---------------|-------------------|-------------|-------------------|-------------|
| Location: | 768 GILEAD ST | Property Use: | Residential | Primary Use: | Residential |
| Unique ID: | 837 | Map Block Lot: | 44-27 | Acres: | 93.42 |
| 490 Acres: | 91.91 | Zone: | R-1 | Volume / Page: | 0568/0591 |
| Developers Map / Lot: | 26/38 | Census: | 5261 | | |

Value Information

| | Appraised Value | Assessed Value |
|-----------------------|-----------------|----------------|
| Land | 353,131 | 68,290 |
| Buildings | 230,669 | 161,470 |
| Detached Outbuildings | 240,652 | 168,460 |


| | Appraised Value | Assessed Value |
|-------|-----------------|----------------|
| Total | 824,452 | 398,220 |

Owner's Information

Owner's Data

ELLIS EDWARD A & RENEE J L/U
MAPLELEAF FARM LAND TRUST LLC
768 GILEAD ST
HEBRON CT 06248

Building 1



| | | | | | |
|-------------------------|---------------|-------------------|--------------|----------------|---------------|
| Building Use: | Single Family | Style: | Colonial | Living Area: | 2,930 |
| Stories: | 2.00 | Construction: | Wood Frame | Year Built: | 1850 |
| Total Rooms: | 10 | Bedrooms: | 4 | Full Baths: | 2 |
| Half Baths: | 0 | Fireplaces: | 0 | Heating: | Caste Iron |
| Fuel: | Oil | Cooling Percent: | 0 | Basement Area: | 1,188 |
| Basement Finished Area: | 0 | Basement Garages: | 0 | Roof Material: | Arch Shingles |
| Siding: | Vinyl Siding | Units: | One w/In Law | | |

Special Features

| | |
|--------------|-----|
| Solar Panels | 200 |
|--------------|-----|

Attached Components

| Type: | Year Built: | Area: |
|----------------|-------------|-------|
| Frame Barn | 1850 | 1,536 |
| Frame Barn | 1850 | 2,706 |
| Wood Deck | 1850 | 162 |
| Garage | 1850 | 556 |
| Enclosed Porch | 1850 | 196 |
| Open Porch | 1850 | 154 |
| Open Porch | 1850 | 56 |
| Open Porch | 1850 | 329 |
| Frame Shed | 1850 | 766 |
| Frame Shed | 1850 | 480 |

Detached Outbuildings

| Type: | Year Built: | Length: | Width: | Area: |
|------------|-------------|---------|--------|--------|
| Frame Shed | 1850 | 0.00 | 0.00 | 4,800 |
| Frame Shed | 1950 | 0.00 | 0.00 | 8,736 |
| Frame Shed | 1950 | 0.00 | 0.00 | 720 |
| Frame Shed | 2008 | 0.00 | 0.00 | 4,000 |
| Frame Shed | 1951 | 0.00 | 0.00 | 154 |
| Frame Shed | 1982 | 0.00 | 0.00 | 3,888 |
| Frame Shed | 2004 | 0.00 | 0.00 | 2,080 |
| Frame Shed | 1951 | 0.00 | 0.00 | 1,430 |
| Frame Shed | 1967 | 0.00 | 0.00 | 14,644 |

Owner History - Sales

| Owner Name | Volume | Page | Sale Date | Deed Type | Sale Price |
|------------------------------|--------|------|------------|------------|------------|
| ELLIS EDWARD A & RENEE J L/U | 0568 | 0591 | 05/18/2020 | Quit Claim | \$0 |
| ELLIS EDWARD A & RENEE J | 0167 | 0653 | 08/08/1994 | | \$0 |
| ELLIS KENNETH W | 0128 | 0107 | 08/17/1987 | | \$0 |

Building Permits

| Permit Number | Permit Type | Date Opened | Reason |
|---------------|-----------------------|-------------|--|
| 2021-0424 | Outbuilding/Yard Item | 08/05/2021 | 14 X 18 STRUCTURE |
| 27404 | Heating | 12/18/2018 | PROPANE GAS HEATER IN GARAGE |
| 26917 | Solar Panels | 02/22/2018 | 200 PANEL SOLAR SYSTEM; INSTALLED ON FARM ROOF |
| 25545 | Outbuilding/Yard Item | 08/05/2015 | |
| 21084 | Outbuilding/Yard Item | 05/16/2013 | |
| 2011-20526 | Electrical | 06/15/2011 | UPGRADE SERVICE |
| 2011-20457 | Roof | 05/18/2011 | INSTLL PV SYSTEM |

| Permit Number | Permit Type | Date Opened | Reason |
|---------------|-----------------------|-------------|-------------|
| 2010-1522 | Mechanical | 02/24/2010 | RMV UG TANK |
| 08-0476 | Outbuilding/Yard Item | 05/20/2008 | |
| 11766 | Mechanical | 07/30/2002 | |

Information Published With Permission From The Assessor



Town of Hebron, Connecticut

Web GIS Maps and Online Property Information

by [MainStreetGIS, LLC](#) [Town Website](#)

[User Guide](#) [Feedback](#) [Disclaimer](#)


Base Map: Town Base Map

768 GILEAD ST


[GIS Map](#) [Street View](#) [Tax Maps](#) [Other Maps](#) [GIS Links](#)

Layers **Property** Selection

768 GILEAD ST
44-27



- Zoom To
- External Property Card
- Abutters List
- Tax Map
- Property List
- Report an Issue



Google Maps 768 Gilead St



Imagery ©2021 Maxar Technologies, U.S. Geological Survey, USDA Farm Service Agency, Map data ©2021 200 ft

Petition No. 565
SBA Properties Inc.
Hebron, Connecticut
Staff Report
June 21, 2002

On June 19, 2002, Connecticut Siting Council (Council) member Gerald J. Heffernan with Robert Mercier of Council staff conducted an inspection of an existing 160-foot stealth monopole owned and operated by SBA Properties Inc. (SBA) and located at 768 Gilead Street in Hebron, Connecticut. SBA seeks a declaratory ruling from the Council that no Certificate of Environmental Compatibility and Public Need (Certificate) is required for this existing telecommunications facility. SBA also requests that the Council approve the proposed shared use of this facility by AT&T Wireless PCS, LLC (AT&T).

This petition was filed in response to the Council's letter to municipalities dated January 25, 2002. The letter requested that the owners of speculation and PCS towers which received municipal approval in the period between July 10 and December 17, 2001 submit a petition to the Council for a declaratory ruling as to whether such towers have a substantial adverse environmental effect. A tower application for this facility was filed with the town of Hebron on March 30, 2001. On October 16, 2001, the planning and zoning commission approved the construction of the tower, disguised as a flagpole.

The existing facility consists of a 160-foot stealth monopole located within a fenced, graveled compound. The 70-foot by 80-foot compound is located within a 100-foot by 100-foot lease area. The tower is designed for five telecommunication carriers. No carriers are currently located at the site. The facility is located on an active dairy farm zoned R-1, residential. Abutting properties include agricultural land to the north and west and rural residential to the east and south.

AT&T proposes to install six panel antennas at the 145-foot level and install two equipment cabinets on a concrete pad at the base of the tower. A structural analysis report indicates the tower can accommodate the proposed antenna loading.

The calculated worst-case radio frequency (RF) power density level for proposed telecommunications operations at the site would be approximately 6.8% of the applicable American National Standards Institute standard for exposure to uncontrolled environments.

SBA contends that the existing tower and proposed-shared use of the tower and associated building compound would not cause a substantial adverse environmental effect, and therefore, no certificate is required.

ATTACHMENT 3

ORIGIN ID:GAMA (301) 266-0258
CATHERINE CONKLIN
GENERAL DYNAMICS
4603 KEMPER STREET
ROCKVILLE, MD 20853
UNITED STATES US

SHIP DATE: 21DEC22
ACTWGT: 2.00 LB
CAD: 105486753/NET4530


BILL SENDER

TO **EDWARD & RENEE ELLIS**

768 GILEAD STREET

HEBRON CT 06248

REF: (860) 228-5971
INV/ PO: DEPT:



J224222101801uv


581J5/C8CF/FE2D

TRK# 0201 7708 5331 8300

THU - 22 DEC 12:00P
PRIORITY OVERNIGHT

EB SKKA

06248
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number. Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.



December 22, 2022

Dear Customer,

The following is the proof-of-delivery for tracking number: 770853318300

Delivery Information:

| | | | |
|--------------------------|--|---------------------------|--------------------|
| Status: | Delivered | Delivered To: | Residence |
| Signed for by: | Signature not required | Delivery Location: | 768 GILEAD ST |
| Service type: | FedEx Priority Overnight | | |
| Special Handling: | Deliver Weekday; Residential Delivery | | HEBRON, CT, 06248 |
| | | Delivery date: | Dec 22, 2022 16:28 |

Shipping Information:

| | | | |
|-------------------------|--------------|-------------------|----------------|
| Tracking number: | 770853318300 | Ship Date: | Dec 21, 2022 |
| | | Weight: | 2.0 LB/0.91 KG |

Recipient:
Edward & Renee Ellis,
768 Gilead Street
HEBRON, CT, US, 06248

Shipper:
Catherine Conklin, General Dynamics
4603 Kemper Street
ROCKVILLE, MD, US, 20853

Proof-of-delivery details appear below; however, no signature is available for this FedEx Express shipment because a signature was not required.

ORIGIN ID:GAMA (301) 266-0258
CATHERINE CONKLIN
GENERAL DYNAMICS
4603 KEMPER STREET
ROCKVILLE, MD 20853
UNITED STATES US


SHIP DATE: 21DEC22
ACT WGT: 2.00 LB
CAD: 105486753/NET4530

BILL SENDER

TO **ANDREW J. TIERNEY, TOWN MANAGER**
TOWN OF HEBRON
15 GILEAD STREET

HEBRON CT 06248


REF: (860) 228-5971
INV/ PO: DEPT:



TRK# 0201
7708 5327 3620

THU - 22 DEC 12:00P
PRIORITY OVERNIGHT

EB SKKA
CT-US **06248**
BDL



581J5/C8CF/FE2D

After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number. Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Dear Customer,

The following is the proof-of-delivery for tracking number: 770853273620

Delivery Information:


| | | | |
|--------------------------|--------------------------|---------------------------|-------------------------|
| Status: | Delivered | Delivered To: | Receptionist/Front Desk |
| Signed for by: | C.POMP | Delivery Location: | 15 GILEAD ST |
| Service type: | FedEx Priority Overnight | | |
| Special Handling: | Deliver Weekday | | HEBRON, CT, 06248 |
| | | Delivery date: | Dec 22, 2022 11:20 |

Shipping Information:

| | | | |
|-------------------------|--------------|-------------------|----------------|
| Tracking number: | 770853273620 | Ship Date: | Dec 21, 2022 |
| | | Weight: | 2.0 LB/0.91 KG |

Recipient:
Andrew J. Tierney, Town Manager, Town of Hebron
15 Gilead Street
HEBRON, CT, US, 06248

Shipper:
Catherine Conklin, General Dynamics
4603 Kemper Street
ROCKVILLE, MD, US, 20853



C. Pomp

ORIGIN ID:GAMA (301) 266-0258
CATHERINE CONKLIN
GENERAL DYNAMICS
4603 KEMPER STREET
ROCKVILLE, MD 20853
UNITED STATES US


SHIP DATE: 21DEC22
ACTWGT: 2.00 LB
CAD: 105486753/NET4530

BILL SENDER

TO **MATTHEW BORDEAUX, TOWN PLANNER**
TOWN OF HEBRON
15 GILEAD STREET

HEBRON CT 06248

REF: (860) 228-5971
INV/ PO/ DEPT:



J224222101801uv


581J5/C8CF/FE2D

TRK# 7708 5329 3861
0201

THU - 22 DEC 12:00P
PRIORITY OVERNIGHT

EB SKKA

06248
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.