



Filed by:
Kri Pelletier, Property Specialist - SBA Communications
134 Flanders Rd., Suite 125, Westborough, MA 01581
508.251.0720 x 3804 - kpelletier@sbsite.com

January 30, 2018

Melanie A. Bachman
Acting Executive Director
Connecticut Siting Council
Ten Franklin Square
New Britain, CT 06051

Notice of Exempt Modification
246 East Franklin Street, Danielson, CT
41 47 44.96 N
-71 52 13.2 W
Sprint #: CT23XC407_2.5

Dear Ms. Bachman:

Sprint currently maintains antennas at the 147-foot of the existing 155-foot Monopole Tower at 246 East Franklin Street in Danielson, CT. The property is owned by Charles R. Hutchins. The Tower is owned by SBA Properties LLC. Sprint now intends to add (3) newer technology cell antenna at the 147-foot level of the tower.

Please note: previous approval was given by the Siting Council on 8/22/2014 under EM-SPRINT-069-140807. A Notification of Construction Not Complete was sent 12/3/15. Sprint now intends to resume construction. The proposed full scope of work is as follows:

Remove: N/A

Remove and Replace: N/A

Install:

- (3) RFS APXVTM14-C-120 – Panel Antennas
- (3) ALU TD-RRH8x20-25 RRHs
- (1) 1-1/4" line

Existing Equipment to Remain (Including entitlements):

- (3) RFS APXVSP18-C-A20 – Panel Antennas
- (3) ALU 1900MHz RRH RRHs
- (3) ALU 800 MHz RRH RRHs
- (3) ALU 800 MHz Filters
- (4) RFS ACU-A20-N RETs
- (3) 1-1/4" lines



This facility was originally approved by the Town of Killingly's Planning and Zoning Commission under Special Permit 98-704 on 7/13/98. Approval was given for a telecommunications tower and associated equipment. There were no post-construction tower conditions set. This modification complies with all aforementioned conditions.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies §16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. §16.50j-72(b)(2). In accordance with R.C.S.A. § 16.50j-73, a copy of this letter is being sent to the Town of Killingly's Town Manager, Sean Hendricks, and Director of Planning and Development, Ann-Marie L. Aubrey, as well as to the Property Owner. (Separate notice is not being sent to the tower owner, as it belongs to SBA.)

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. §16.50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modification will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard.
5. The proposed modification will not cause a change or alteration in the physical or environmental characteristics of the site.
6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-referenced telecommunication facility constitute an exempt modifications under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,

Kri Pelletier
Property Specialist
SBA COMMUNICATIONS CORPORATION
134 Flanders Rd., Suite 125
Westborough, MA 01581
508.251.0720 x3804 + T
508.366.2610 + F
203.446.7700 + C
kpelletier@sbsite.com

Attachments

cc: Sean Hendricks, Town Manager / with attachments
Town of Killingly, Killingly Town Hall, 172 Main Street, Killingly, CT 06239
Ann-Marie L. Aubrey, Director of Planning and Development / with attachments
Town of Killingly, Killingly Town Hall, 172 Main Street, Killingly, CT 06239
Charles Hutchins / with attachments
246 E. Franklin Street, Killingly, CT 06239



POWER DENSITY

SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20
Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	147 feet	Height (AGL):	147 feet	Height (AGL):	147 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	7,537.38	ERP (W):	7,537.38	ERP (W):	7,537.38
Antenna A1 MPE%	1.54 %	Antenna B1 MPE%	1.54 %	Antenna C1 MPE%	1.54 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVTM14-C-I20	Make / Model:	RFS APXVTM14-C-I20	Make / Model:	RFS APXVTM14-C-I20
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	147 feet	Height (AGL):	147 feet	Height (AGL):	147 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	1.13 %	Antenna B2 MPE%	1.13 %	Antenna C2 MPE%	1.13 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	2.67 %
AT&T	4.64 %
MetroPCS	0.39 %
Verizon Wireless	2.13 %
T-Mobile	0.94 %
Site Total MPE %:	10.77 %

SPRINT Sector A Total:	2.67 %
SPRINT Sector B Total:	2.67 %
SPRINT Sector C Total:	2.67 %
Site Total:	10.77 %


SPRINT_ Max Values per Frequency Band / Technology Per Sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	147	0.79	850 MHz	567	0.14%
Sprint 850 MHz LTE	2	437.55	147	1.58	850 MHz	567	0.28%
Sprint 1900 MHz (PCS) CDMA	5	622.47	147	5.63	1900 MHz (PCS)	1000	0.56%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	147	5.63	1900 MHz (PCS)	1000	0.56%
Sprint 2500 MHz (BRS) LTE	8	778.09	147	11.26	2500 MHz (BRS)	1000	1.13%
Total:						2.67%	

ORIGIN ID:BBFA (508) 614-0389
RICK WOODS
SBA NETWORK SERVICES INC
134 FLANDERS ROAD
SUITE 125
WESTBOROUGH MA 01581
UNITED STATES US

SHIP DATE: 30JAN18
ACTWT: 1.00 LB
CAD: 105843304IN/EI3980
BILL SENDER

TO SEAN HENDRICKS, TOWN MANAGER
TOWN OF KILLINGLY
KILLINGLY TOWN HALL
172 MAIN STREET
KILLINGLY CT 06239
(508) 251-0720 X 3804
REF: 10-56-92009-6099
PO: DEPT:

552J11/122D/DC45



TRK# 7713 5656 9444
#0201

WED - 31 JAN 12:00P
PRIORITY OVERNIGHT

EB GONA

06239
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID:BBFA (508) 251-0720
KRI PELLETER
SBA COMMUNICATIONS CORPORATION
134 FLANDERS RD
SUITE 125
WESTBOROUGH MA 01581
UNITED STATES US

SHIP DATE: 30 JAN 18
ACTWGT: 1.00 LB
CAD: 105843304IN/EI 3980

BILL SENDER

TO ANN-MARIE AUBREY/DIR. PLANNING&DEV

TOWN OF KILLINGLY

KILLINGLY TOWN HALL

172 MAIN STREET

KILLINGLY CT 06239


(508) 314-0389

REF: 10-56-92009-6089

PO:

DEPT:

552J11122DICA5



J181110012001uy

TRK# 7713 5669 8281
0201

WED - 31 JAN 12:00P
PRIORITY OVERNIGHT

EBGONA

06239
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

ORIGIN ID:BBFA (508) 614-0389
RICK WOODS
SBA NETWORK SERVICES INC
134 FLANDERS ROAD
SUITE 125
WESTBOROUGH, MA 01581
UNITED STATES US

SHIP DATE: 30 JAN 18
ACTWGT: 1.00 LB
CAD: 105843304/INET3980

BILL SENDER

TO **CHARLES HUTCHINS**

246 E. FRANKLIN STREET


KILLINGLY CT 06239

(508) 251-0720 X 3804

REF: 10-56-92009-6039

PO:

DEPT:



J181118012601111

552J1/122D/DCA5

TRK# 7713 5671 1308
0201

WED - 31 JAN 12:00P
PRIORITY OVERNIGHT

EB GONA

06239
CT-US BDL



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.
2. Fold the printed page along the horizontal line.
3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com. FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim. Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss. Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our Service Guide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Situs : 246 E FRANKLIN ST

Map ID: 002601


Class: Single Family Residence

Card: 1 of 1

Printed: June 26, 2017

CURRENT OWNER
HUTCHINS CHARLES R 246 E FRANKLIN ST KILLINGLY CT 06239

GENERAL INFORMATION
Living Units 1
Neighborhood 102
Alternate Id 216-12
Vol / Pg 555/118
District 7
Zoning RURAL DEVELOPMENT
Class 100



Property Notes

Land Information				
Type	Size	Influence Factors	Influence %	Value
Primary	AC 5.5000			47,880
Primary	AC 0.5000			34,000
Waste	AC 1.0000			250
Rear	AC 10.0000			10,000
Total Acres: 17				
Spot: Location:				

Assessment Information					
	Assessed	Appraised	Cost	Income	
Land	64,470	92,100	92,100	0	92,100
Building	165,830	236,900	236,900	0	236,900
Total	230,300	329,000	329,000	0	329,000
Manual Override Reason					
Value Flag COST APPROACH				Base Date of Value 10/01/2013	
MONOPOLE/BLDG/ 127600				Effective Date of Value 10/01/2013	

Entrance Information			
Date	ID	Entry Code	Source
11/10/09	MHB	View ed	Asmt Staff
10/11/06	LA	Ext W/Info	Ow ner

Permit Information					
Date Issued	Number	Price	Purpose		% Complete
05/11/17	25284	40,000	97 BPP	Telecom -Modify Existing At&T Ant	995
08/03/15	23794	15,000	97 BPP	Repl Existing Antennaes & Add 3 I	995
12/11/14	23346	15,000	97 BPP	Repl Old Panel/Antennae Models \	995
10/06/14	23221	49,000	74 CRER	Nvc Maint Work - Add Steel Plates	997
08/28/14	23133	15,000	97 BPP	Add 3 New er Cell Antennas & As	995

Sales/Ownership History						
Transfer Date	Price	Type	Validity	Deed Reference	Deed Type	Grantee

Situs : 246 E FRANKLIN ST

Parcel Id: 002601

Class: Single Family Residence

Card: 1 of 1

Printed: June 26, 2017

Dwelling Information

Style Ranch Year Built 1960
 Story height 1 Eff Year Built
 Attic None Year Remodeled
 Exterior Walls Frame Amenities Wood Stove
 Masonry Trim x
 Color Brown In-law Apt No

Basement

Basement Full # Car Bsm't Gar 3
 FBLA Size x FBLA Type
 Rec Rm Size x Rec Rm Type

Heating & Cooling

Fireplaces

Heat Type Basic Stacks
 Fuel Type Oil Openings
 System Type Hot Water Pre-Fab

Room Detail

Bedrooms 4 Full Baths 2
 Family Rooms Half Baths
 Kitchens 1 Extra Fixtures 1
 Total Rooms 9
 Kitchen Type Typical Bath Type Typical
 Kitchen Remod No Bath Remod No

Adjustments

Int vs Ext Same Unfinished Area 1180
 Cathedral Ceiling x Unheated Area 1180


Grade & Depreciation

Grade C Market Adj
 Condition Poor Condition Functional
 CDU POOR Economic
 Cost & Design 0 % Good Ovr
 % Complete

Dwelling Computations

Base Price	117,684	% Good	40
Plumbing	4,400	% Good Override	
Basement	0	Functional	
Heating	0	Economic	
Attic	0	% Complete	
Other Features	-26,020	C&D Factor	
		Adj Factor	1
Subtotal	96,060	Additions	68,700
Ground Floor Area	1,132		
Total Living Area	4,142	Dwelling Value	107,100

Building Notes



Outbuilding Data

Type	Size 1	Size 2	Area	Qty	Yr Blt	Grade	Condition	Value
1s Lean To	4 x 12		48	1	2000	D	U	90
Poultry	11 x 12		132	1	2000	D	P	470
Frame Shed	x		174	1	2008	C	A	1,670

Condominium / Mobile Home Information

Complex Name
 Condo Model
 Unit Number
 Unit Level
 Unit Parking
 Model (MH)
 Unit Location
 Unit View
 Model Make (MH)

Addition Details

Line #	Low	1st	2nd	3rd	Value
1	50	10			24,200
2		35			
3	50	10	10		44,500



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT23XC407

Danielson
246 East Franklin Street
Danielson, CT 06239

October 27, 2017

EBI Project Number: 6217004752

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	10.77 %



October 27, 2017

SPRINT

Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Emissions Analysis for Site: **CT23XC407 – Danielson**

EBI Consulting was directed to analyze the proposed SPRINT facility located at **246 East Franklin Street, Danielson, CT**, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 850 MHz Band is approximately $567 \mu\text{W}/\text{cm}^2$. The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at **246 East Franklin Street, Danielson, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the **RFS APXVSP18-C-A20** and the **RFS APXVTM14-C-I20** for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are **147 feet** above ground level (AGL) for **Sector A**, **147 feet** above ground level (AGL) for **Sector B** and **147 feet** above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.



SPRINT Site Inventory and Power Data by Antenna

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20	Make / Model:	RFS APXVSPPI8-C-A20
Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	147 feet	Height (AGL):	147 feet	Height (AGL):	147 feet
Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	7,537.38	ERP (W):	7,537.38	ERP (W):	7,537.38
Antenna A1 MPE%	1.54 %	Antenna B1 MPE%	1.54 %	Antenna C1 MPE%	1.54 %
Antenna #:	2	Antenna #:	2	Antenna #:	2
Make / Model:	RFS APXVTM14-C-I20	Make / Model:	RFS APXVTM14-C-I20	Make / Model:	RFS APXVTM14-C-I20
Gain:	15.9 dBd	Gain:	15.9 dBd	Gain:	15.9 dBd
Height (AGL):	147 feet	Height (AGL):	147 feet	Height (AGL):	147 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	6,224.72	ERP (W):	6,224.72	ERP (W):	6,224.72
Antenna A2 MPE%	1.13 %	Antenna B2 MPE%	1.13 %	Antenna C2 MPE%	1.13 %

Site Composite MPE%	
Carrier	MPE%
SPRINT – Max per sector	2.67 %
AT&T	4.64 %
MetroPCS	0.39 %
Verizon Wireless	2.13 %
T-Mobile	0.94 %
Site Total MPE %:	10.77 %

SPRINT Sector A Total:	2.67 %
SPRINT Sector B Total:	2.67 %
SPRINT Sector C Total:	2.67 %
Site Total:	10.77 %

SPRINT _ Max Values per Frequency Band / Technology Per Sector	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	147	0.79	850 MHz	567	0.14%
Sprint 850 MHz LTE	2	437.55	147	1.58	850 MHz	567	0.28%
Sprint 1900 MHz (PCS) CDMA	5	622.47	147	5.63	1900 MHz (PCS)	1000	0.56%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	147	5.63	1900 MHz (PCS)	1000	0.56%
Sprint 2500 MHz (BRS) LTE	8	778.09	147	11.26	2500 MHz (BRS)	1000	1.13%
						Total:	2.67%

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	2.67 %
Sector B:	2.67 %
Sector C:	2.67 %
SPRINT Maximum Total (per sector):	2.67 %
Site Total:	10.77 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **10.77 %** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Tower Engineering Solutions

Phone (972) 483-0607, Fax (972) 975-9615
8445 Freepoint Parkway, Suite 375, Irving, Texas 75063

Structural Analysis Report

Existing 155 ft Nudd Corporation Monopole

Customer Name: SBA Communications Corp

Customer Site Number: CT00302-S

Customer Site Name: Danielson

Carrier Name: Sprint Nextel

Carrier Site ID / Name: CT23XC407 / Danielson

Site Location: 246 East Franklin Street

Danielson, Connecticut

Windham County

Latitude: 41.795822

Longitude: -71.870333

Analysis Result:

Max Structural Usage: 98.3% [Pass]

Max Foundation Usage: 60.0% [Pass]

Report Prepared By : Fabiyaye Arinyedokiari



Introduction

The purpose of this report is to summarize the analysis results on the 155 ft Nudd Corporation Monopole to support the proposed antennas and transmission lines in addition to those currently installed. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

Sources of Information

Tower Drawings	Nudd Corporation, Project #6410 dated October 27, 1998
Foundation Drawing	Nudd Corporation, Project #98-6410-4 dated November 2, 1998
Geotechnical Report	Jaworski Geotech, Inc., Project #C98423G dated October 14, 1998
Modification Drawings	Vertical Solutions, Inc., Job #TA2002007001-T1 dated October 7, 2002 Vertical Solutions, Inc., Job #TA2008007031-T3 dated November 10, 2008 Vertical Solutions, Inc., Job #TA2009007021-T2 dated July 16, 2009 FDH Engineering, Project #12-01571E S4 dated March 13, 2013 FDH Engineering, Project #1466VA1400 dated July 8, 2014

Analysis Criteria

The rigorous analysis was performed in accordance with the requirements and stipulations of the ANSI/TIA/EIA 222-G. In accordance with this standard, the structure was analyzed using **TESPoles**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

Wind Speed Used in the Analysis:	Ultimate Design Wind Speed $V_{ult} = 130.0$ mph (3-Sec. Gust)/ Nominal Design Wind Speed $V_{asd} = 101.0$ mph (3-Sec. Gust)
Wind Speed with Ice:	50 mph (3-Sec. Gust) with 1" radial ice concurrent
Operational Wind Speed:	60 mph + 0" Radial ice
Standard/Codes:	ANSI/TIA/EIA 222-G / 2012 IBC / 2016 Connecticut State Building Code
Exposure Category:	B
Structure Class:	II
Topographic Category:	3
Crest Height:	172 ft
Seismic Parameters:	$S_S = 0.171$, $S_1 = 0.062$

Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1	155.0	3	Commscope LNX-6514DS-A1M - Panel	(3) T-Frame w/ Platforms	(11) 1 5/8" (2) 1 5/8" Fiber	Verizon
2		3	BXA-70080-4BF - Panel			
3		6	Commscope HBXX-6517DS-A2M - Panel			
4		3	Alcatel Lucent RRH2X60-AWS			
5		3	Alcatel Lucent RRH2X60-PCS			
6		3	Alcatel Lucent RRH2X60-700			
7		6	RFS Celwave FD9R6004/2C-3L			
8		1	RFS DB-T1-6Z-8AB-0Z			
-	147.0	3	RFS APXVSP18-C-A20 - Panel	(3) T-Frame w/ Platforms	(4) 1 1/4"	Sprint Nextel
-		3	RFS APXVTM14-C-120 - Panel			
-		3	ALU TD-RRH8x20-25			
-		3	ALU 1900MHz RRH			
-		3	ALU 800 MHz RRH			
-		3	ALU 800 MHz Filters			
-		4	RFS ACU-A20-N RET			
16	137.0	6	DAPA 59212 - Panel	(3) T-Frame w/ Platforms	(6) 1 5/8"	T-Mobile
17	127.0	6	Powerwave 7770.00 - Panel	Low Profile Platform	(12) 1 5/8" (2) 3/4" DC (1) 7/16" Fiber	AT&T
18		3	CCI HPA-65R-BUU-H8 - Panel			
19		6	Powerwave LGP21401 - TMA			
20		3	Ericsson RRUS 11 - RRU			
21		3	Ericsson RRUS 32 B2 - RRU			
22		6	Powerwave LGP13519 - Diplexer			
23		1	Raycap DC6-48-60-18-8F			
24	117.0	6	Kathrein 742 351 - Panel	(3) T-Frames	(12) 1 5/8" (1) 3/8"	Metro PCS
25	35.0	1	Decibel DB589	(1) Standoff	(2) 7/8"	American Messaging

Proposed Carrier's Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier's final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
9	147.0	3	RFS APXVSP18-C-A20 - Panel	(3) T-Frame w/ Platforms	(4) 1 1/4"	Sprint Nextel
10		3	RFS APXVTM14-C-120 - Panel			
11		3	ALU TD-RRH8x20-25			
12		3	ALU 1900MHz RRH			
13		3	ALU 800 MHz RRH			
14		3	ALU 800 MHz Filters			
15		4	RFS ACU-A20-N RET			

All transmission lines are considered running inside of the pole shafts.

Analysis Results

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

	Pole shafts	Anchor Bolts	Base Plate	Reinforcement
Max. Usage:	94.6%	75.0%	52.7%	98.3%
Pass/Fail	Pass	Pass	Pass	Pass

Foundations

	Moment (Kip-Ft)	Shear (Kips)	Axial (Kips)
Analysis Reactions	4986.1	50.1	53.8

The foundation has been investigated using the supplied documents and soils report and was found adequate. A mat foundation was considered to be installed per Nudd drawings #98-6410-4 dated November 2, 1988 and photos. Therefore, no modification to the foundation will be required.

Operational Condition (Rigidity):

Operational characteristics of the tower are found to be within the limits prescribed by ANSI/TIA/EIA 222-G for the installed antennas. The maximum twist/sway at the elevation of the proposed equipment is 1.1626 degrees under the operational wind speed as specified in the Analysis Criteria.

Conclusions

Based on the analysis results, the existing structure and its foundation were found to be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the ANSI/TIA/EIA 222-G Standard under the design basic wind speed as specified in the Analysis Criteria.

Standard Conditions

1. This analysis was performed based on the information supplied to **(TES) Tower Engineering Solutions, LLC**. Verification of the information provided was not included in the Scope of Work for **TES**. The accuracy of the analysis is dependent on the accuracy of the information provided.
2. The analysis is based on the presumption that the tower members and components along with any existing reinforcement items have been correctly and properly designed, manufactured, installed and maintained.
3. All the existing structural members were assumed to be in good condition with no physical damage or deterioration associated with corrosion.
4. An initial tension of 10% of the break strength on all the existing guy wires was assumed in all the structural analyses of guyed towers unless different values were provided by the client. **TES** cannot take responsibility for the deviations in the analysis results because of differences in the initial tension forces of the existing guy wires.
5. Secondary component or connection secondary components, welds and bolts are assumed to be able to carry their intended original design loads. **TES** cannot take responsibility for verification of the adequacy on the connections, bolts and welds present in the structure.
6. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of **TES**. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed and/or ice loads are different from the minimum values recommended by the EIA/TIA-222 standard or other codes, **TES** should be notified in writing and the applicable minimum values provided by the client.
7. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. **TES** has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, **TES** should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
8. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
9. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

Usage Diagram - Max Ratio 94.57% at 0.0ft

Structure: CT00302-S-SBA
Site Name: Danielson
Height: 155.00 (ft)
Base Elev: 0.000 (ft)

Code: EIA/TIA-222-G
Exposure: B
Gh: 1.1


11/1/2017



Page: 1


Dead Load Factor: 1.20
Wind Load Factor: 1.60

Load Case : 1.2D + 1.6W 101 mph Wind



Iterations: 23

Copyright © 2017 by Tower Engineering Solutions, LLC. All rights reserved.



Structure: CT00302-S-SBA

Type: Tapered
Site Name: Danielson
Height: 155.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 12 Sided
Taper: 0.19129

11/1/2017

Page: 2



Shaft Properties


Seq	Length (ft)	Top (in)	Bottom (in)	Thick (in)	Joint Type	Taper	Grade (ksi)
1	42.00	45.87	53.90	0.433		0.19129	53
2	40.00	40.11	47.76	0.375	Slip	0.19129	53
3	30.00	36.15	41.88	0.313	Slip	0.19129	53
4	20.00	32.32	36.15	0.250	Butt	0.19129	50
5	40.00	26.13	33.78	0.250	Slip	0.19129	50

Discrete Appurtenances

Attach Elev (ft)	Force Elev (ft)	Qty	Description	Carrier
155.00	155.00	3	LNx-6514DS-A1M	Verizon
155.00	155.00	3	BXA-70080-4BF	Verizon
155.00	155.00	6	HBXX-6517DS-A2M	Verizon
155.00	155.00	3	RRH2X60-AWS	Verizon
155.00	155.00	3	RRH2X60-PCS	Verizon
155.00	155.00	3	RRH2X60-700	Verizon
155.00	155.00	6	FD9R6004/2C-3L	Verizon
155.00	155.00	1	DB-T1-6Z-8AB-0Z	Verizon
155.00	155.00	1	(3) T-Frame w/ Platforms	Verizon
147.00	147.00	1	(3) T-Frame w/ Platforms	Sprint Nextel
147.00	147.00	3	APXVSP18-C-A20	Sprint Nextel
147.00	147.00	3	APXVTM14-C-120	Sprint Nextel
147.00	147.00	3	TD-RRH8x20-25	Sprint Nextel
147.00	147.00	3	1900 MHz RRH	Sprint Nextel
147.00	147.00	3	800 MHz RRH	Sprint Nextel
147.00	147.00	3	800 MHz Filter	Sprint Nextel
147.00	147.00	4	ACU-A20-N	Sprint Nextel
137.00	137.00	6	59212	T-Mobile
137.00	137.00	1	(3) T-Frame w/ Platforms	T-Mobile
127.00	127.00	1	Low Profile	AT&T
127.00	127.00	6	7770.00	AT&T
127.00	127.00	3	HPA-65R-BUU-H8	AT&T
127.00	127.00	6	LGP21401	AT&T
127.00	127.00	3	RRUS 11	AT&T
127.00	127.00	3	RRUS 32 B2	AT&T
127.00	127.00	1	DC6-48-60-18-8F	AT&T
127.00	127.00	6	LGP13519	AT&T
117.00	117.00	3	T-Frames	Metro PCS
117.00	117.00	6	742 351	Metro PCS
35.00	39.60	1	DB589	American Messaging
35.00	35.00	1	3.58' Standoff	American Messaging

Linear Appurtenances

Elev From (ft)	Elev To (ft)	Placement	Description	Carrier
0.00	155.00	Inside	1 5/8" Coax	Verizon
0.00	155.00	Inside	1 5/8" Fiber	Verizon
0.00	147.00	Inside	1 1/4" Coax	Sprint Nextel
0.00	137.00	Inside	1 5/8" Coax	T-Mobile
0.00	127.00	Inside	1 5/8" Coax	AT&T
0.00	127.00	Inside	3" Conduit	AT&T
0.00	127.00	Inside	3/4" DC	AT&T
0.00	127.00	Inside	7/16" Fiber	AT&T
0.00	117.00	Inside	1 5/8" Coax	Metro PCS
0.00	117.00	Inside	3/8" Coax	Metro PCS



Structure: CT00302-S-SBA

Type: Tapered
Site Name: Danielson
Height: 155.00 (ft)
Base Elev: 0.00 (ft)

Base Shape: 12 Sided
Taper: 0.19129

11/1/2017

Page: 3



58.00	115.00	Outside	1.25" Reinforcing plate	
0.00	58.00	Outside	10"x1/2" Bent plate	
0.00	35.00	Inside	7/8" Coax	American Messaging

Anchor Bolts

Qty	Specifications	Grade (ksi)	Arrangement
18	2.00" A687	105.0	Radial

Base Plate

Thickness (in)	Specifications (in)	Grade (ksi)	Geometry
1.7500	67.0	36.0	Round

Reactions


Load Case	Moment (FT-Kips)	Shear (Kips)	Axial (Kips)
1.2D + 1.6W 101 mph Wind	4986.1	50.1	53.8
0.9D + 1.6W 101 mph Wind	4941.2	50.1	40.4
1.2D + 1.0Di + 1.0Wi 50 mph Wind	1228.0	11.3	102.6
1.2D + 1.0E	184.5	1.5	53.9
0.9D + 1.0E	182.6	1.5	40.5
1.0D + 1.0W 60 mph Wind	1094.4	11.1	44.9

Structure: CT00302-S-SBA - Coax Line Placement

Type: Monopole
Site Name: Danielson
Height: 155.00 (ft)

11/1/2017

Page: 4



Shaft Properties

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 5

Sec. No.	Shape	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Overlap (in)	Weight (lb)
1	12	42.000	0.4331	53		0.00	9,856
2	12	40.000	0.3750	53	Slip	72.00	7,160
3	12	30.000	0.3125	53	Slip	72.00	3,976
4	12	20.000	0.2500	50	Flange	0.00	1,862
5	12	40.000	0.2500	50	Slip	60.00	3,254
Total Shaft Weight:							26,107

Bottom

Top

Sec. No.	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (sqin)	Ix (in^4)	W/t Ratio	D/t Ratio	Taper
1	53.90	0.00	74.56	27207.27	31.20	124.45	45.87	42.00	63.36	16693.0	26.23	105.9	0.191290
2	47.76	36.00	57.22	16401.87	31.98	127.37	40.11	76.00	47.98	9670.66	26.52	106.9	0.191290
3	41.88	70.00	41.83	9227.84	33.77	134.03	36.15	100.00	36.06	5909.60	28.85	115.6	0.191290
4	36.15	100.0	28.90	4752.46	36.60	144.58	32.32	120.00	25.82	3389.11	32.50	129.2	0.191290
5	33.78	115.0	26.99	3872.14	34.06	135.11	26.13	155.00	20.83	1780.01	25.86	104.5	0.191290

Additional Steel

Elev From (ft)	Elev To (ft)	Qty	Description	Fy (ksi)	Fu (ksi)	Offset (in)	Intermediate Connectors		Termination Connectors			
							Description	Spacing (in)	Description	Spacing (in)	Lower Qty	Upper Qty
0.00	21.00	3	PLT 6"X1-1/4"(1.25" Hole)	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00		
11.50	16.50	1	PLT 6"X1-1/4"(1.25" Hole)	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00	11	11
21.00	41.00	3	PLT 6"X1-1/4"(1.25" Hole)	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00		
41.00	58.50	3	PLT 6"X1-1/4"(1.25" Hole)	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00		11
58.00	76.00	3	PLT 5"x1-1/4"(1.25"Hole)	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00	8	
76.00	96.00	3	PLT 4.5"x 1-1/4"(1.25"ho	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00		
96.00	113.5	3	PLT 3.5x1.25(1.25 Hole)	65	80	0.00	AJM20&sleeve	18.00	AJM20&sleeve	3.00		6

Load Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 6

Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
1	155.00	LNX-6514DS-A1M	3	38.40	8.17	0.83	287.05	12.152	0.83	0.00	0.00
2	155.00	BXA-70080-4BF	3	13.00	4.76	0.76	164.47	7.385	0.76	0.00	0.00
3	155.00	HBXX-6517DS-A2M	6	40.80	8.55	0.77	289.40	12.667	0.77	0.00	0.00
4	155.00	RRH2X60-AWS	3	55.00	3.50	0.67	167.86	4.613	0.67	0.00	0.00
5	155.00	RRH2X60-PCS	3	55.00	2.20	0.67	186.08	3.132	0.67	0.00	0.00
6	155.00	RRH2X60-700	3	46.00	1.88	0.67	154.30	2.743	0.67	0.00	0.00
7	155.00	FD9R6004/2C-3L	6	3.10	0.36	0.50	14.42	0.985	0.50	0.00	0.00
8	155.00	DB-T1-6Z-8AB-0Z	1	18.90	4.80	0.71	236.82	6.067	0.71	0.00	0.00
9	155.00	(3) T-Frame w/ Platforms	1	1620.00	25.00	1.00	3613.98	53.310	1.00	0.00	0.00
10	147.00	(3) T-Frame w/ Platforms	1	1620.00	25.00	1.00	3613.31	53.300	1.00	0.00	0.00
11	147.00	APXVSP18-C-A20	3	57.00	8.02	0.83	300.73	11.959	0.83	0.00	0.00
12	147.00	APXVTM14-C-120	3	56.00	6.34	0.79	301.28	7.951	0.79	0.00	0.00
13	147.00	TD-RRH8x20-25	3	70.00	4.05	0.69	239.41	5.233	0.69	0.00	0.00
14	147.00	1900 MHz RRH	3	60.00	2.31	0.67	477.97	3.231	0.67	0.00	0.00
15	147.00	800 MHz RRH	3	53.00	2.49	0.67	157.29	4.103	0.67	0.00	0.00
16	147.00	800 MHz Filter	3	8.80	0.78	0.69	33.68	1.692	0.69	0.00	0.00
17	147.00	ACU-A20-N	4	1.00	0.14	0.50	7.06	0.558	0.79	0.00	0.00
18	137.00	59212	6	40.00	4.97	0.66	281.07	7.797	0.66	0.00	0.00
19	137.00	(3) T-Frame w/ Platforms	1	1620.00	25.00	1.00	3612.87	53.294	1.00	0.00	0.00
20	127.00	Low Profile Platform-Round	1	1500.00	22.00	1.00	3345.27	46.899	1.00	0.00	0.00
21	127.00	7770.00	6	35.00	5.50	0.73	243.68	7.042	0.73	0.00	0.00
22	127.00	HPA-65R-BUU-H8	3	68.00	12.98	0.79	506.37	15.313	0.79	0.00	0.00
23	127.00	LGP21401	6	17.50	0.95	0.50	46.11	1.999	0.50	0.00	0.00
24	127.00	RRUS 11	3	50.70	2.52	0.67	188.40	3.472	0.67	0.00	0.00
25	127.00	RRUS 32 B2	3	60.00	2.74	0.67	196.55	3.800	0.67	0.00	0.00
26	127.00	DC6-48-60-18-8F	1	31.80	0.92	1.00	118.96	1.538	1.00	0.00	0.00
27	127.00	LGP13519	6	5.30	0.34	0.67	18.69	0.980	0.67	0.00	0.00
28	117.00	T-Frames	3	880.00	20.40	0.75	1850.19	34.858	0.75	0.00	0.00
29	117.00	742 351	6	29.80	5.38	0.61	164.18	8.181	0.61	0.00	0.00
30	35.00	DB589	1	11.50	1.38	1.00	63.95	4.630	1.00	0.00	4.60
31	35.00	3.58' Standoff	1	70.00	1.67	0.67	155.41	4.392	0.67	0.00	0.00
Totals:			99	12,237.90			36,769.00				

Linear Appurtenances

Bottom Elev. (ft)	Top Elev. (ft)	Description	Exposed Width	Exposed
0.00	155.00	(1) 1 5/8" Coax	0.00	Inside
0.00	155.00	(2) 1 5/8" Fiber	0.00	Inside
0.00	147.00	(4) 1 1/4" Coax	0.00	Inside
0.00	137.00	(6) 1 5/8" Coax	0.00	Inside
0.00	127.00	(12) 1 5/8" Coax	0.00	Inside
0.00	127.00	(1) 3" Conduit	0.00	Inside
0.00	127.00	(2) 3/4" DC	0.00	Inside
0.00	127.00	(1) 7/16" Fiber	0.00	Inside
0.00	117.00	(12) 1 5/8" Coax	0.00	Inside
0.00	117.00	(1) 3/8" Coax	0.00	Inside

Discrete Appurtenances

No.	Elev (ft)	Description	Qty	No Ice			Ice			Hor. Ecc. (ft)	Vert Ecc (ft)
				Weight (lb)	CaAa (sf)	CaAa Factor	Weight (lb)	CaAa (sf)	CaAa Factor		
58.00	115.00	(3) 1.25" Reinforcing plate		2.00		Outside					
0.00	58.00	(3) 10"x1/2" Bent plate		4.00		Outside					
0.00	35.00	(2) 7/8" Coax		0.00		Inside					

Shaft Section Properties

Structure: CT00302-S-SBA

Code: EIA/TIA-222-G

11/1/2017

Site Name: Danielson

Exposure: B

Height: 155.00 (ft)

Crest Height: 172.00

Base Elev: 0.000 (ft)

Site Class: C - Very Dense Soil

Gh: 1.1

Topography: 3

Struct Class: II

Page: 8



Increment Length: 5 (ft)

Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in^2)	Ix (in^4)	W/t Ratio	D/t Ratio	Fy (ksi)	Fb (ksi)	Weight (lb)	Additional Reinforcing			
											Area (in^2)	Ixp (in^4)	Iyp (in^4)	Weight (lb)
0.00	RB1	0.4331	53.900	74.564	27207.3	31.20	124.45	53	60	0.0	22.50	11335.6	5634.6	
5.00		0.4331	52.944	73.230	25773.1	30.61	122.24	53	61	1257.3	22.50	10945.7	5440.9	382.8
10.00		0.4331	51.987	71.896	24390.3	30.02	120.03	53	61	1234.6	22.50	10562.8	5250.7	382.8
11.50	RB2	0.4331	51.700	71.496	23985.3	29.84	119.37	53	61	365.9	30.00	10560.9	10206.1	153.1
15.00		0.4331	51.031	70.562	23057.8	29.43	117.83	53	62	845.9	30.00	10296.7	9948.1	357.3
16.50	RT2	0.4331	50.744	70.162	22667.8	29.25	117.16	53	62	359.1	22.50	10075.2	5008.4	114.8
20.00		0.4331	50.074	69.229	21774.8	28.84	115.62	53	62	830.1	22.50	9817.4	4880.4	268.0
21.00	RT1 RB3	0.4331	49.883	68.962	21524.0	28.72	115.18	53	62	235.1	22.50	9744.4	4844.1	76.6
25.00		0.4331	49.118	67.895	20540.3	28.24	113.41	53	63	931.4	22.50	9455.0	4700.4	306.2
30.00		0.4331	48.161	66.561	19353.3	27.65	111.20	53	63	1143.8	22.50	9099.5	4523.8	382.8
35.00		0.4331	47.205	65.227	18213.0	27.06	108.99	53	64	1121.1	22.50	8750.8	4350.6	382.8
36.00	Bot - Section 2	0.4331	47.014	64.960	17990.4	26.94	108.55	53	64	221.5	22.50	8681.8	4316.4	76.6
40.00		0.4331	46.248	63.893	17118.3	26.47	106.78	53	64	1649.5	22.50	8675.5	4312.8	306.2
41.00	RT3 RB4	0.4331	46.057	63.626	16904.8	26.35	106.34	53	64	408.1	22.50	8606.9	4278.7	76.6
42.00	Top - Section 1	0.3750	46.616	55.836	15238.7	31.16	124.31	53	60	406.4	22.50	8538.6	4244.8	76.6
45.00		0.3750	46.042	55.143	14678.4	30.75	122.78	53	61	566.5	22.50	8328.6	4136.7	229.7
50.00		0.3750	45.085	53.988	13775.3	30.07	120.23	53	61	928.4	22.50	7995.4	3971.4	382.8
55.00		0.3750	44.129	52.833	12910.0	29.39	117.68	53	62	908.7	22.50	7669.0	3809.5	382.8
58.00	RB5	0.3750	43.555	52.140	12408.7	28.98	116.15	53	62	535.8	41.25	12224.5	8463.6	421.0
58.50	RT4	0.3750	43.460	52.025	12326.4	28.91	115.89	53	62	88.6	18.75	4705.8	4705.8	31.9
60.00		0.3750	43.173	51.678	12081.8	28.70	115.13	53	62	264.7	18.75	4645.8	4645.8	95.7
65.00		0.3750	42.216	50.523	11289.7	28.02	112.58	53	63	869.4	18.75	4448.8	4448.8	318.9
70.00	Bot - Section 3	0.3750	41.260	49.368	10533.1	27.34	110.03	53	63	849.8	18.75	4256.1	4256.1	318.9
75.00		0.3750	40.303	48.213	9811.0	26.65	107.48	53	64	1533.7	18.75	4190.3	4190.3	318.9
76.00	Top - Section 2 RT5	0.3125	40.737	40.677	8484.5	32.79	130.36	53	59	302.4	16.88	3734.0	3734.0	57.4
80.00		0.3125	39.972	39.907	8011.7	32.13	127.91	53	60	548.4	16.88	3599.7	3599.7	229.7
85.00		0.3125	39.015	38.945	7445.9	31.31	124.85	53	60	670.8	16.88	3435.3	3435.3	287.1
90.00		0.3125	38.059	37.982	6907.4	30.49	121.79	53	61	654.4	16.88	3274.7	3274.7	287.1
95.00		0.3125	37.102	37.020	6395.6	29.67	118.73	53	62	638.0	16.88	3118.0	3118.0	287.1
96.00	RT6 RB7	0.3125	36.911	36.827	6296.3	29.51	118.12	53	62	125.6	13.13	2396.7	2396.7	44.7
100.00	Top - Section 3	0.3125	36.146	36.057	5909.6	28.85	115.67	53	62	496.0	13.13	2301.9	2301.9	178.6
100.00	Bot - Section 4	0.2500	36.146	28.896	4752.5	36.06	144.58	50	54					
105.00		0.2500	35.190	28.126	4382.6	35.57	140.76	50	54	485.1	13.13	2186.0	2186.0	223.3
110.00		0.2500	34.233	27.356	4032.5	34.55	136.93	50	55	472.0	13.13	2073.2	2073.2	223.3
113.50	RT7	0.2500	33.564	26.817	3798.8	33.83	134.25	50	56	322.6	13.13	1996.0	1996.0	156.3
115.00	Bot - Section 5	0.2500	33.277	26.586	3701.5	33.52	133.11	50	56	136.3				
117.00		0.2500	32.894	26.278	3574.3	33.11	131.58	50	56	362.5				
120.00	Top - Section 4	0.2500	32.820	26.219	3550.1	33.03	131.28	50	56	535.9				
125.00		0.2500	31.864	25.449	3246.4	32.01	127.45	50	57	439.5				
127.00		0.2500	31.481	25.141	3130.0	31.60	125.92	50	57	172.1				
130.00		0.2500	30.907	24.679	2960.6	30.98	123.63	50	58	254.3				
135.00		0.2500	29.951	23.909	2692.1	29.96	119.80	50	59	413.3				
137.00		0.2500	29.568	23.601	2589.4	29.55	118.27	50	59	161.7				
140.00		0.2500	28.994	23.139	2440.3	28.93	115.98	50	59	238.6				
145.00		0.2500	28.038	22.369	2204.7	27.91	112.15	50	60	387.1				
147.00		0.2500	27.655	22.061	2114.9	27.50	110.62	50	60	151.2				
150.00		0.2500	27.081	21.599	1984.8	26.88	108.33	50	61	222.9				
155.00		0.2500	26.125	20.829	1780.0	25.86	104.50	50	62	360.9				
Total Weight										26107.2	7818.3			

Wind Loading - Shaft

Structure: CT00302-S-SBA

Code: EIA/TIA-222-G

11/1/2017

Site Name: Danielson

Exposure: B

Height: 155.00 (ft)

Crest Height: 172.00

Base Elev: 0.000 (ft)

Site Class: C - Very Dense Soil

Gh: 1.1

Topography: 3

Struct Class: II

Page: 9



Load Case: 1.2D + 1.6W 101 mph Wind

Iterations 23

Dead Load Factor 1.20

Wind Load Factor 1.60



Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	2.18	0.70	37.885	41.67	580.38	1.000	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		2.10	0.70	36.515	40.17	559.69	1.000	0.000	5.00	23.044	23.04	1481.0	0.0	1508.7
10.00		2.03	0.70	35.247	38.77	539.94	1.000	0.000	5.00	22.632	22.63	1403.9	0.0	1481.5
11.50	RB2	2.01	0.70	34.884	38.37	534.19	1.000	0.000	1.50	6.709	6.71	411.9	0.0	439.1
15.00		1.96	0.70	34.070	37.48	521.09	1.000	0.000	3.50	15.510	15.51	930.0	0.0	1015.1
16.50	RT2	1.94	0.70	33.734	37.11	515.59	1.000	0.000	1.50	6.585	6.59	391.0	0.0	431.0
20.00		1.90	0.70	32.978	36.28	503.06	1.000	0.000	3.50	15.221	15.22	883.5	0.0	996.1
21.00	RT1 RB3	1.89	0.70	32.769	36.05	499.55	1.000	0.000	1.00	4.312	4.31	248.7	0.0	282.1
25.00		1.84	0.70	31.964	35.16	485.81	1.000	0.000	4.00	17.082	17.08	961.0	0.0	1117.7
30.00		1.79	0.70	31.048	34.15	469.47	1.000	0.000	5.00	20.981	20.98	1146.5	0.0	1372.6
35.00	Appurtenance(s)	1.74	0.73	31.530	34.68	463.70	1.000	0.000	5.00	20.569	20.57	1141.4	0.0	1345.3
36.00	Bot - Section 2	1.73	0.74	31.608	34.77	462.40	1.000	0.000	1.00	4.064	4.06	226.1	0.0	265.8
40.00		1.69	0.76	31.870	35.06	456.76	1.000	0.000	4.00	16.351	16.35	917.1	0.0	1979.4
41.00	RT3 RB4	1.68	0.77	31.925	35.12	455.26	1.000	0.000	1.00	4.046	4.05	227.4	0.0	489.8
42.00	Top - Section 1	1.67	0.77	31.976	35.17	453.73	1.000	0.000	1.00	4.030	4.03	226.8	0.0	487.7
45.00		1.65	0.79	32.108	35.32	456.41	1.000	0.000	3.00	11.991	11.99	677.6	0.0	679.7
50.00		1.60	0.81	32.271	35.50	448.06	1.000	0.000	5.00	19.655	19.65	1116.3	0.0	1114.0
55.00		1.57	0.83	32.378	35.62	439.28	1.000	0.000	5.00	19.242	19.24	1096.5	0.0	1090.5
58.00	RB5	1.55	0.85	32.422	35.66	433.86	1.000	0.000	3.00	11.347	11.35	647.5	0.0	643.0
58.50	RT4	1.54	0.85	32.427	35.67	432.95	1.000	0.000	0.50	1.877	1.88	107.1	0.0	106.3
60.00		1.53	0.85	32.444	35.69	430.19	1.000	0.000	1.50	5.606	5.61	320.1	0.0	317.6
65.00		1.50	0.87	32.478	35.73	420.89	1.000	0.000	5.00	18.417	18.42	1052.7	0.0	1043.3
70.00	Bot - Section 3	1.47	0.89	32.491	35.74	411.44	1.000	0.000	5.00	18.004	18.00	1029.6	0.0	1019.7
75.00		1.44	0.91	32.488	35.74	401.88	1.000	0.000	5.00	17.861	17.86	1021.3	0.0	1840.4
76.00	Top - Section 2 RT5	1.43	0.91	32.486	35.73	399.96	1.000	0.000	1.00	3.523	3.52	201.4	0.0	362.9
80.00		1.41	0.93	32.474	35.72	398.49	1.000	0.000	4.00	13.926	13.93	795.9	0.0	658.1
85.00		1.39	0.94	32.453	35.70	388.83	1.000	0.000	5.00	17.036	17.04	973.1	0.0	804.9
90.00		1.36	0.96	32.428	35.67	379.15	1.000	0.000	5.00	16.624	16.62	948.8	0.0	785.3
95.00		1.34	0.97	32.401	35.64	369.47	1.000	0.000	5.00	16.211	16.21	924.5	0.0	765.6
96.00	RT6 RB7	1.34	0.98	32.396	35.64	367.53	1.000	0.000	1.00	3.193	3.19	182.0	0.0	150.8
100.00	Top - Section 3	1.32	0.99	32.375	35.61	359.80	1.000	0.000	4.00	12.606	12.61	718.3	0.0	595.2
105.00		1.30	1.00	32.350	35.58	350.14	1.000	0.000	5.00	15.386	15.39	876.0	0.0	582.1
110.00		1.28	1.02	32.327	35.56	340.51	1.000	0.000	5.00	14.973	14.97	851.9	0.0	566.4
113.50	RT7	1.27	1.02	32.314	35.55	333.78	1.000	0.000	3.50	10.236	10.24	582.1	0.0	387.1
115.00	Bot - Section 5	1.27	1.03	32.309	35.54	330.90	1.000	0.000	1.50	4.325	4.32	245.9	0.0	163.5
117.00	Appurtenance(s)	1.26	1.03	32.302	35.53	327.06	1.000	0.000	2.00	5.795	5.80	329.5	0.0	435.0
120.00	Top - Section 4	1.25	1.04	32.294	35.52	321.31	1.000	0.000	3.00	8.569	8.57	487.0	0.0	643.1
125.00		1.24	1.05	32.284	35.51	316.73	1.000	0.000	5.00	13.951	13.95	792.7	0.0	527.4
127.00	Appurtenance(s)	1.23	1.06	32.281	35.51	312.91	1.000	0.000	2.00	5.465	5.46	310.5	0.0	206.6
130.00		1.22	1.07	32.279	35.51	307.19	1.000	0.000	3.00	8.074	8.07	458.7	0.0	305.1
135.00		1.21	1.08	32.279	35.51	297.69	1.000	0.000	5.00	13.126	13.13	745.7	0.0	496.0
137.00	Appurtenance(s)	1.20	1.08	32.280	35.51	293.89	1.000	0.000	2.00	5.135	5.13	291.7	0.0	194.0
140.00		1.20	1.09	32.284	35.51	288.20	1.000	0.000	3.00	7.579	7.58	430.6	0.0	286.3
145.00		1.18	1.10	32.295	35.52	278.74	1.000	0.000	5.00	12.301	12.30	699.2	0.0	464.6
147.00	Appurtenance(s)	1.18	1.10	32.300	35.53	274.96	1.000	0.000	2.00	4.805	4.80	273.1	0.0	181.4
150.00		1.17	1.11	32.311	35.54	269.30	1.000	0.000	3.00	7.083	7.08	402.8	0.0	267.4
155.00	Appurtenance(s)	1.16	1.12	32.332	35.56	259.87	1.000	0.000	5.00	11.476	11.48	653.0	0.0	433.1

Wind Loading - Shaft

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Struct Class: II	Page: 10



Totals:	155.00	30,839.5	31,328.6
----------------	---------------	-----------------	-----------------

Discrete Appurtenance Forces


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 11

Load Case: 1.2D + 1.6W 101 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Iterations 23

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	155.00	RRH2X60-AWS	3	32.332	35.565	0.54	0.80	5.63	198.00	0.000	0.000	320.26	0.00	0.00
2	155.00	LNx-6514DS-A1M	3	32.332	35.565	0.66	0.80	16.27	138.24	0.000	0.000	926.09	0.00	0.00
3	155.00	BXA-70080-4BF	3	32.332	35.565	0.61	0.80	8.68	46.80	0.000	0.000	494.05	0.00	0.00
4	155.00	HBXX-6517DS-A2M	6	32.332	35.565	0.62	0.80	31.60	293.76	0.000	0.000	1798.21	0.00	0.00
5	155.00	DB-T1-6Z-8AB-0Z	1	32.332	35.565	0.57	0.80	2.73	22.68	0.000	0.000	155.14	0.00	0.00
6	155.00	RRH2X60-PCS	3	32.332	35.565	0.54	0.80	3.54	198.00	0.000	0.000	201.30	0.00	0.00
7	155.00	RRH2X60-700	3	32.332	35.565	0.54	0.80	3.02	165.60	0.000	0.000	172.02	0.00	0.00
8	155.00	FD9R6004/2C-3L	6	32.332	35.565	0.40	0.80	0.86	22.32	0.000	0.000	49.17	0.00	0.00
9	155.00	(3) T-Frame w/ Platforms	1	32.332	35.565	1.00	1.00	25.00	1944.00	0.000	0.000	1422.60	0.00	0.00
10	147.00	(3) T-Frame w/ Platforms	1	32.300	35.530	1.00	1.00	25.00	1944.00	0.000	0.000	1421.22	0.00	0.00
11	147.00	ACU-A20-N	4	32.300	35.530	0.40	0.80	0.22	4.80	0.000	0.000	12.73	0.00	0.00
12	147.00	800 MHz Filter	3	32.300	35.530	0.55	0.80	1.29	31.68	0.000	0.000	73.43	0.00	0.00
13	147.00	800 MHz RRH	3	32.300	35.530	0.54	0.80	4.00	190.80	0.000	0.000	227.62	0.00	0.00
14	147.00	1900 MHz RRH	3	32.300	35.530	0.54	0.80	3.71	216.00	0.000	0.000	211.16	0.00	0.00
15	147.00	TD-RRH8x20-25	3	32.300	35.530	0.55	0.80	6.71	252.00	0.000	0.000	381.27	0.00	0.00
16	147.00	APXVTM14-C-120	3	32.300	35.530	0.63	0.80	12.02	201.60	0.000	0.000	683.36	0.00	0.00
17	147.00	APXVSP18-C-A20	3	32.300	35.530	0.66	0.80	15.98	205.20	0.000	0.000	908.21	0.00	0.00
18	137.00	59212	6	32.280	35.508	0.53	0.80	15.74	288.00	0.000	0.000	894.52	0.00	0.00
19	137.00	(3) T-Frame w/ Platforms	1	32.280	35.508	1.00	1.00	25.00	1944.00	0.000	0.000	1420.33	0.00	0.00
20	127.00	Low Profile	1	32.281	35.509	1.00	1.00	22.00	1800.00	0.000	0.000	1249.93	0.00	0.00
21	127.00	7770.00	6	32.281	35.509	0.58	0.80	19.27	252.00	0.000	0.000	1094.94	0.00	0.00
22	127.00	HPA-65R-BUU-H8	3	32.281	35.509	0.63	0.80	24.61	244.80	0.000	0.000	1398.22	0.00	0.00
23	127.00	LGP21401	6	32.281	35.509	0.40	0.80	2.28	126.00	0.000	0.000	129.54	0.00	0.00
24	127.00	RRUS 11	3	32.281	35.509	0.54	0.80	4.05	182.52	0.000	0.000	230.22	0.00	0.00
25	127.00	RRUS 32 B2	3	32.281	35.509	0.54	0.80	4.41	216.00	0.000	0.000	250.32	0.00	0.00
26	127.00	DC6-48-60-18-8F	1	32.281	35.509	0.80	0.80	0.74	38.16	0.000	0.000	41.82	0.00	0.00
27	127.00	LGP13519	6	32.281	35.509	0.54	0.80	1.09	38.16	0.000	0.000	62.12	0.00	0.00
28	117.00	742 351	6	32.302	35.532	0.49	0.80	15.75	214.56	0.000	0.000	895.57	0.00	0.00
29	117.00	T-Frames	3	32.302	35.532	0.56	0.75	34.42	3168.00	0.000	0.000	1957.13	0.00	0.00
30	35.00	3.58' Standoff	1	31.530	34.683	0.67	1.00	1.12	84.00	0.000	0.000	62.09	0.00	0.00
31	35.00	DB589	1	31.847	35.032	0.80	0.80	1.10	13.80	0.000	4.600	61.88	0.00	284.65
Totals:									14,685.48			19,206.48		

Total Applied Force Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II




Page: 12

Load Case: 1.2D + 1.6W 101 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.60



Iterations 23

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		1480.99	1807.53	0.00	0.00
10.00		1403.93	1780.30	0.00	0.00
11.50		411.91	528.78	0.00	0.00
15.00		930.03	1224.29	0.00	0.00
16.50		390.98	520.61	0.00	0.00
20.00		883.46	1205.22	0.00	0.00
21.00		248.68	341.90	0.00	0.00
25.00		960.99	1356.70	0.00	0.00
30.00		1146.52	1671.37	0.00	0.00
35.00	(2) attachments	1265.39	1741.93	0.00	284.65
36.00		226.09	324.31	0.00	0.00
40.00		917.15	2213.43	0.00	0.00
41.00		227.36	548.28	0.00	0.00
42.00		226.80	546.24	0.00	0.00
45.00		677.61	855.28	0.00	0.00
50.00		1116.33	1406.60	0.00	0.00
55.00		1096.51	1383.02	0.00	0.00
58.00		647.49	818.50	0.00	0.00
58.50		107.11	135.59	0.00	0.00
60.00		320.08	405.36	0.00	0.00
65.00		1052.75	1335.86	0.00	0.00
70.00		1029.57	1312.28	0.00	0.00
75.00		1021.29	2132.95	0.00	0.00
76.00		201.42	421.40	0.00	0.00
80.00		795.93	892.15	0.00	0.00
85.00		973.06	1097.51	0.00	0.00
90.00		948.76	1077.86	0.00	0.00
95.00		924.45	1058.21	0.00	0.00
96.00		182.04	209.28	0.00	0.00
100.00		718.27	829.27	0.00	0.00
105.00		876.00	874.67	0.00	0.00
110.00		851.92	858.95	0.00	0.00
113.50		582.13	591.91	0.00	0.00
115.00		245.93	251.32	0.00	0.00
117.00	(9) attachments	3182.15	3934.60	0.00	0.00
120.00		487.02	773.41	0.00	0.00
125.00		792.70	744.64	0.00	0.00
127.00	(29) attachments	4767.60	3191.10	0.00	0.00
130.00		458.67	386.22	0.00	0.00
135.00		745.70	631.12	0.00	0.00
137.00	(7) attachments	2606.58	2480.05	0.00	0.00
140.00		430.61	344.89	0.00	0.00
145.00		699.16	562.25	0.00	0.00
147.00	(23) attachments	4192.15	3266.58	0.00	0.00
150.00		402.81	316.53	0.00	0.00
155.00	(29) attachments	6191.86	3544.37	0.00	0.00

Total Applied Force Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 13

Totals:	<u>50,045.95</u>	<u>53,934.61</u>	<u>0.00</u>	<u>284.65</u>
----------------	------------------	------------------	-------------	---------------

Linear Appurtenance Segment Forces (Factored)


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 14

Load Case: 1.2D + 1.6W 101 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.60



Iterations 23

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.064	0.000	36.515	0.00	0.00
10.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.066	0.000	35.247	0.00	0.00
11.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	0.45	0.00	0.066	0.000	34.884	0.00	0.00
15.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	1.04	0.00	0.067	0.000	34.070	0.00	0.00
16.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	0.45	0.00	0.068	0.000	33.734	0.00	0.00
20.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	1.04	0.00	0.068	0.000	32.978	0.00	0.00
21.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.069	0.000	32.769	0.00	0.00
25.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	1.19	0.00	0.069	0.000	31.964	0.00	0.00
30.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.071	0.000	31.048	0.00	0.00
35.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.072	0.000	31.530	0.00	0.00
36.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.073	0.000	31.608	0.00	0.00
40.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	1.19	0.00	0.074	0.000	31.870	0.00	0.00
41.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.075	0.000	31.925	0.00	0.00
42.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.075	0.000	31.976	0.00	0.00
45.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	0.89	0.00	0.074	0.000	32.108	0.00	0.00
50.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.075	0.000	32.271	0.00	0.00
55.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.077	0.000	32.378	0.00	0.00
58.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	0.89	0.00	0.078	0.000	32.422	0.00	0.00
58.50	1.25" Reinforcing	Yes	0.50	0.000	2.50	0.10	0.00	0.056	0.000	32.427	0.00	0.00
60.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.31	0.00	0.056	0.000	32.444	0.00	0.00
65.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.057	0.000	32.478	0.00	0.00
70.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.058	0.000	32.491	0.00	0.00
75.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.059	0.000	32.488	0.00	0.00
76.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.21	0.00	0.060	0.000	32.486	0.00	0.00
80.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	0.83	0.00	0.060	0.000	32.474	0.00	0.00
85.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.061	0.000	32.453	0.00	0.00
90.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.063	0.000	32.428	0.00	0.00
95.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.064	0.000	32.401	0.00	0.00
96.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.21	0.00	0.065	0.000	32.396	0.00	0.00
100.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	0.83	0.00	0.066	0.000	32.375	0.00	0.00
105.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.068	0.000	32.350	0.00	0.00
110.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.070	0.000	32.327	0.00	0.00
113.50	1.25" Reinforcing	Yes	3.50	0.000	2.50	0.73	0.00	0.071	0.000	32.314	0.00	0.00
115.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.31	0.00	0.072	0.000	32.309	0.00	0.00
Totals:											0.0	0.0

Calculated Forces

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Page: 16
Struct Class: II		



155.00	0.00	-6.19	0.00	0.00	0.00	0.00	0.00	1153.35	576.68	1229.81	607.36	98.22	-5.333	0.000	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	-------	--------	-------	-------

Wind Loading - Shaft

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 18

Totals: 155.00

30,839.5

23,496.5

Discrete Appurtenance Forces


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 19

Load Case: 0.9D + 1.6W 101 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 23

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	155.00	RRH2X60-AWS	3	32.332	35.565	0.54	0.80	5.63	148.50	0.000	0.000	320.26	0.00	0.00
2	155.00	LNx-6514DS-A1M	3	32.332	35.565	0.66	0.80	16.27	103.68	0.000	0.000	926.09	0.00	0.00
3	155.00	BXA-70080-4BF	3	32.332	35.565	0.61	0.80	8.68	35.10	0.000	0.000	494.05	0.00	0.00
4	155.00	HBXX-6517DS-A2M	6	32.332	35.565	0.62	0.80	31.60	220.32	0.000	0.000	1798.21	0.00	0.00
5	155.00	DB-T1-6Z-8AB-0Z	1	32.332	35.565	0.57	0.80	2.73	17.01	0.000	0.000	155.14	0.00	0.00
6	155.00	RRH2X60-PCS	3	32.332	35.565	0.54	0.80	3.54	148.50	0.000	0.000	201.30	0.00	0.00
7	155.00	RRH2X60-700	3	32.332	35.565	0.54	0.80	3.02	124.20	0.000	0.000	172.02	0.00	0.00
8	155.00	FD9R6004/2C-3L	6	32.332	35.565	0.40	0.80	0.86	16.74	0.000	0.000	49.17	0.00	0.00
9	155.00	(3) T-Frame w/ Platforms	1	32.332	35.565	1.00	1.00	25.00	1458.00	0.000	0.000	1422.60	0.00	0.00
10	147.00	(3) T-Frame w/ Platforms	1	32.300	35.530	1.00	1.00	25.00	1458.00	0.000	0.000	1421.22	0.00	0.00
11	147.00	ACU-A20-N	4	32.300	35.530	0.40	0.80	0.22	3.60	0.000	0.000	12.73	0.00	0.00
12	147.00	800 MHz Filter	3	32.300	35.530	0.55	0.80	1.29	23.76	0.000	0.000	73.43	0.00	0.00
13	147.00	800 MHz RRH	3	32.300	35.530	0.54	0.80	4.00	143.10	0.000	0.000	227.62	0.00	0.00
14	147.00	1900 MHz RRH	3	32.300	35.530	0.54	0.80	3.71	162.00	0.000	0.000	211.16	0.00	0.00
15	147.00	TD-RRH8x20-25	3	32.300	35.530	0.55	0.80	6.71	189.00	0.000	0.000	381.27	0.00	0.00
16	147.00	APXVTM14-C-120	3	32.300	35.530	0.63	0.80	12.02	151.20	0.000	0.000	683.36	0.00	0.00
17	147.00	APXVSP18-C-A20	3	32.300	35.530	0.66	0.80	15.98	153.90	0.000	0.000	908.21	0.00	0.00
18	137.00	59212	6	32.280	35.508	0.53	0.80	15.74	216.00	0.000	0.000	894.52	0.00	0.00
19	137.00	(3) T-Frame w/ Platforms	1	32.280	35.508	1.00	1.00	25.00	1458.00	0.000	0.000	1420.33	0.00	0.00
20	127.00	Low Profile	1	32.281	35.509	1.00	1.00	22.00	1350.00	0.000	0.000	1249.93	0.00	0.00
21	127.00	7770.00	6	32.281	35.509	0.58	0.80	19.27	189.00	0.000	0.000	1094.94	0.00	0.00
22	127.00	HPA-65R-BUU-H8	3	32.281	35.509	0.63	0.80	24.61	183.60	0.000	0.000	1398.22	0.00	0.00
23	127.00	LGP21401	6	32.281	35.509	0.40	0.80	2.28	94.50	0.000	0.000	129.54	0.00	0.00
24	127.00	RRUS 11	3	32.281	35.509	0.54	0.80	4.05	136.89	0.000	0.000	230.22	0.00	0.00
25	127.00	RRUS 32 B2	3	32.281	35.509	0.54	0.80	4.41	162.00	0.000	0.000	250.32	0.00	0.00
26	127.00	DC6-48-60-18-8F	1	32.281	35.509	0.80	0.80	0.74	28.62	0.000	0.000	41.82	0.00	0.00
27	127.00	LGP13519	6	32.281	35.509	0.54	0.80	1.09	28.62	0.000	0.000	62.12	0.00	0.00
28	117.00	742 351	6	32.302	35.532	0.49	0.80	15.75	160.92	0.000	0.000	895.57	0.00	0.00
29	117.00	T-Frames	3	32.302	35.532	0.56	0.75	34.42	2376.00	0.000	0.000	1957.13	0.00	0.00
30	35.00	3.58' Standoff	1	31.530	34.683	0.67	1.00	1.12	63.00	0.000	0.000	62.09	0.00	0.00
31	35.00	DB589	1	31.847	35.032	0.80	0.80	1.10	10.35	0.000	4.600	61.88	0.00	284.65
Totals:									11,014.11			19,206.48		

Total Applied Force Summary


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 20

Load Case: 0.9D + 1.6W 101 mph Wind

Dead Load Factor 0.90
Wind Load Factor 1.60



Iterations 23

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		1480.99	1355.65	0.00	0.00
10.00		1403.93	1335.22	0.00	0.00
11.50		411.91	396.58	0.00	0.00
15.00		930.03	918.22	0.00	0.00
16.50		390.98	390.46	0.00	0.00
20.00		883.46	903.92	0.00	0.00
21.00		248.68	256.42	0.00	0.00
25.00		960.99	1017.53	0.00	0.00
30.00		1146.52	1253.53	0.00	0.00
35.00	(2) attachments	1265.39	1306.45	0.00	284.65
36.00		226.09	243.23	0.00	0.00
40.00		917.15	1660.07	0.00	0.00
41.00		227.36	411.21	0.00	0.00
42.00		226.80	409.68	0.00	0.00
45.00		677.61	641.46	0.00	0.00
50.00		1116.33	1054.95	0.00	0.00
55.00		1096.51	1037.27	0.00	0.00
58.00		647.49	613.87	0.00	0.00
58.50		107.11	101.69	0.00	0.00
60.00		320.08	304.02	0.00	0.00
65.00		1052.75	1001.90	0.00	0.00
70.00		1029.57	984.21	0.00	0.00
75.00		1021.29	1599.71	0.00	0.00
76.00		201.42	316.05	0.00	0.00
80.00		795.93	669.11	0.00	0.00
85.00		973.06	823.13	0.00	0.00
90.00		948.76	808.39	0.00	0.00
95.00		924.45	793.66	0.00	0.00
96.00		182.04	156.96	0.00	0.00
100.00		718.27	621.96	0.00	0.00
105.00		876.00	656.00	0.00	0.00
110.00		851.92	644.21	0.00	0.00
113.50		582.13	443.93	0.00	0.00
115.00		245.93	188.49	0.00	0.00
117.00	(9) attachments	3182.15	2950.95	0.00	0.00
120.00		487.02	580.06	0.00	0.00
125.00		792.70	558.48	0.00	0.00
127.00	(29) attachments	4767.60	2393.32	0.00	0.00
130.00		458.67	289.67	0.00	0.00
135.00		745.70	473.34	0.00	0.00
137.00	(7) attachments	2606.58	1860.04	0.00	0.00
140.00		430.61	258.67	0.00	0.00
145.00		699.16	421.68	0.00	0.00
147.00	(23) attachments	4192.15	2449.93	0.00	0.00
150.00		402.81	237.39	0.00	0.00
155.00	(29) attachments	6191.86	2658.27	0.00	0.00

Total Applied Force Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 21

Totals:	<u>50,045.95</u>	<u>40,450.96</u>	<u>0.00</u>	<u>284.65</u>
----------------	------------------	------------------	-------------	---------------

Linear Appurtenance Segment Forces (Factored)

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II




Page: 22

Load Case: 0.9D + 1.6W 101 mph Wind

Dead Load Factor 0.90

Wind Load Factor 1.60



Iterations 23

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.064	0.000	36.515	0.00	0.00
10.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.066	0.000	35.247	0.00	0.00
11.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	0.45	0.00	0.066	0.000	34.884	0.00	0.00
15.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	1.04	0.00	0.067	0.000	34.070	0.00	0.00
16.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	0.45	0.00	0.068	0.000	33.734	0.00	0.00
20.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	1.04	0.00	0.068	0.000	32.978	0.00	0.00
21.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.069	0.000	32.769	0.00	0.00
25.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	1.19	0.00	0.069	0.000	31.964	0.00	0.00
30.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.071	0.000	31.048	0.00	0.00
35.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.072	0.000	31.530	0.00	0.00
36.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.073	0.000	31.608	0.00	0.00
40.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	1.19	0.00	0.074	0.000	31.870	0.00	0.00
41.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.075	0.000	31.925	0.00	0.00
42.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.075	0.000	31.976	0.00	0.00
45.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	0.89	0.00	0.074	0.000	32.108	0.00	0.00
50.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.075	0.000	32.271	0.00	0.00
55.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.077	0.000	32.378	0.00	0.00
58.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	0.89	0.00	0.078	0.000	32.422	0.00	0.00
58.50	1.25" Reinforcing	Yes	0.50	0.000	2.50	0.10	0.00	0.056	0.000	32.427	0.00	0.00
60.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.31	0.00	0.056	0.000	32.444	0.00	0.00
65.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.057	0.000	32.478	0.00	0.00
70.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.058	0.000	32.491	0.00	0.00
75.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.059	0.000	32.488	0.00	0.00
76.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.21	0.00	0.060	0.000	32.486	0.00	0.00
80.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	0.83	0.00	0.060	0.000	32.474	0.00	0.00
85.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.061	0.000	32.453	0.00	0.00
90.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.063	0.000	32.428	0.00	0.00
95.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.064	0.000	32.401	0.00	0.00
96.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.21	0.00	0.065	0.000	32.396	0.00	0.00
100.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	0.83	0.00	0.066	0.000	32.375	0.00	0.00
105.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.068	0.000	32.350	0.00	0.00
110.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.070	0.000	32.327	0.00	0.00
113.50	1.25" Reinforcing	Yes	3.50	0.000	2.50	0.73	0.00	0.071	0.000	32.314	0.00	0.00
115.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.31	0.00	0.072	0.000	32.309	0.00	0.00
Totals:											0.0	0.0

Calculated Forces

Structure: CT00302-S-SBA
Site Name: Danielson
Height: 155.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: B
Crest Height: 172.00
Site Class: C - Very Dense Soil
Struct Class: II


11/1/2017
 Page: 23



Load Case: 0.9D + 1.6W 101 mph Wind

Iterations 23

Dead Load Factor 0.90
Wind Load Factor 1.60



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-40.36	-50.12	0.00	-4941.1	0.00	4941.18	4048.32	2024.16	8933.65	4411.99	0.00	0.000	0.000	0.935
5.00	-38.83	-48.78	0.00	-4690.5	0.00	4690.58	4007.22	2003.61	8683.49	4288.45	0.11	-0.208	0.000	0.910
10.00	-37.39	-47.46	0.00	-4446.6	0.00	4446.69	3964.98	1982.49	8434.18	4165.32	0.44	-0.416	0.000	0.885
11.50	-36.92	-47.10	0.00	-4375.5	0.00	4375.50	3952.09	1976.04	8359.57	4128.48	0.58	-0.480	0.000	0.747
15.00	-35.94	-46.22	0.00	-4210.6	0.00	4210.65	3921.60	1960.80	8185.84	4042.68	0.98	-0.604	0.000	0.731
16.50	-35.47	-45.89	0.00	-4141.3	0.00	4141.32	3908.36	1954.18	8111.55	4005.99	1.18	-0.658	0.000	0.853
20.00	-34.50	-45.05	0.00	-3980.7	0.00	3980.73	3877.07	1938.54	7938.63	3920.59	1.72	-0.804	0.000	0.835
21.00	-34.17	-44.86	0.00	-3935.6	0.00	3935.68	3868.03	1934.02	7889.33	3896.24	1.89	-0.846	0.000	0.830
25.00	-33.03	-43.99	0.00	-3756.2	0.00	3756.26	3831.41	1915.70	7692.66	3799.12	2.67	-1.012	0.000	0.810
30.00	-31.64	-42.93	0.00	-3536.3	0.00	3536.33	3784.60	1892.30	7448.09	3678.33	3.84	-1.217	0.000	0.785
35.00	-30.28	-41.70	0.00	-3321.4	0.00	3321.40	3736.66	1868.33	7205.04	3558.30	5.23	-1.421	0.000	0.759
36.00	-29.96	-41.52	0.00	-3279.7	0.00	3279.70	3726.93	1863.47	7156.62	3534.39	5.53	-1.462	0.000	0.754
40.00	-28.26	-40.61	0.00	-3113.6	0.00	3113.62	3687.57	1843.78	6963.65	3439.09	6.82	-1.625	0.000	0.728
41.00	-27.82	-40.39	0.00	-3073.0	0.00	3073.01	3677.62	1838.81	6915.58	3415.35	7.17	-1.666	0.000	0.723
42.00	-27.36	-40.19	0.00	-3032.6	0.00	3032.62	3033.05	1516.53	5788.55	2858.75	7.52	-1.707	0.000	0.777
45.00	-26.63	-39.57	0.00	-2912.0	0.00	2912.06	3011.75	1505.88	5675.99	2803.16	8.63	-1.828	0.000	0.816
50.00	-25.47	-38.51	0.00	-2714.2	0.00	2714.21	2975.34	1487.67	5488.97	2710.80	10.66	-2.040	0.000	0.782
55.00	-24.37	-37.45	0.00	-2521.6	0.00	2521.64	2937.79	1468.89	5302.79	2618.85	12.91	-2.250	0.000	0.748
58.00	-23.73	-36.81	0.00	-2409.3	0.00	2409.30	2914.71	1457.35	5191.54	2563.91	14.37	-2.375	0.000	0.563
58.50	-23.61	-36.71	0.00	-2390.8	0.00	2390.89	2910.82	1455.41	5173.04	2554.77	14.62	-2.392	0.000	0.684
60.00	-23.24	-36.43	0.00	-2335.8	0.00	2335.83	2899.09	1449.55	5117.58	2527.38	15.38	-2.451	0.000	0.674
65.00	-22.17	-35.41	0.00	-2153.6	0.00	2153.68	2859.26	1429.63	4933.49	2436.46	18.05	-2.642	0.000	0.640
70.00	-21.13	-34.40	0.00	-1976.6	0.00	1976.65	2818.28	1409.14	4750.64	2346.16	20.91	-2.828	0.000	0.606
75.00	-19.52	-33.33	0.00	-1804.6	0.00	1804.65	2776.16	1388.08	4569.18	2256.54	23.97	-3.010	0.000	0.566
76.00	-19.16	-33.15	0.00	-1771.3	0.00	1771.31	2161.97	1080.98	3608.45	1782.08	24.61	-3.047	0.000	0.636
80.00	-18.44	-32.37	0.00	-1638.7	0.00	1638.72	2139.97	1069.98	3503.61	1730.30	27.22	-3.191	0.000	0.660
85.00	-17.57	-31.41	0.00	-1476.8	0.00	1476.87	2111.44	1055.72	3372.88	1665.74	30.66	-3.382	0.000	0.613
90.00	-16.73	-30.47	0.00	-1319.8	0.00	1319.82	2081.77	1040.89	3242.65	1601.42	34.30	-3.565	0.000	0.566
95.00	-15.94	-29.52	0.00	-1167.5	0.00	1167.50	2050.97	1025.48	3113.05	1537.42	38.13	-3.739	0.000	0.517
96.00	-15.75	-29.35	0.00	-1137.9	0.00	1137.97	2044.67	1022.33	3087.22	1524.66	38.91	-3.773	0.000	0.547
100.00	-15.10	-28.64	0.00	-1020.5	0.00	1020.56	2019.02	1009.51	2984.22	1473.79	42.14	-3.914	0.000	0.505
100.00	-15.10	-28.64	0.00	-1020.5	0.00	1020.56	1394.49	697.25	2068.33	1021.47	42.14	-3.914	0.000	0.586
105.00	-14.43	-27.76	0.00	-877.38	0.00	877.38	1376.43	688.21	1986.77	981.19	46.32	-4.079	0.000	0.605
110.00	-13.78	-26.90	0.00	-738.58	0.00	738.58	1357.32	678.66	1905.17	940.89	50.69	-4.254	0.000	0.527
113.50	-13.35	-26.30	0.00	-644.44	0.00	644.44	1343.33	671.66	1848.11	912.71	53.85	-4.367	0.000	0.471
113.50	-13.35	-26.30	0.00	-644.44	0.00	644.44	1343.33	671.66	1848.11	912.71	53.85	-4.367	0.000	0.471
115.00	-13.14	-26.06	0.00	-604.99	0.00	604.99	1337.17	668.58	1823.68	900.65	55.22	-4.413	0.000	0.683
117.00	-10.41	-22.68	0.00	-552.88	0.00	552.88	1328.82	664.41	1791.13	884.57	57.09	-4.502	0.000	0.634
120.00	-9.81	-22.17	0.00	-484.85	0.00	484.85	1327.18	663.59	1784.85	881.47	59.96	-4.625	0.000	0.559
125.00	-9.27	-21.35	0.00	-374.00	0.00	374.00	1305.49	652.74	1703.72	841.41	64.90	-4.806	0.000	0.453
127.00	-7.27	-16.41	0.00	-331.29	0.00	331.29	1296.51	648.26	1671.38	825.43	66.92	-4.868	0.000	0.408
130.00	-6.99	-15.94	0.00	-282.06	0.00	282.06	1282.74	641.37	1623.00	801.54	70.01	-4.951	0.000	0.358
135.00	-6.57	-15.17	0.00	-202.36	0.00	202.36	1258.96	629.48	1542.80	761.93	75.25	-5.068	0.000	0.271
137.00	-4.94	-12.41	0.00	-172.03	0.00	172.03	1249.15	624.57	1510.90	746.18	77.38	-5.107	0.000	0.235
140.00	-4.70	-11.96	0.00	-134.80	0.00	134.80	1234.12	617.06	1463.26	722.65	80.60	-5.158	0.000	0.191
145.00	-4.34	-11.23	0.00	-75.00	0.00	75.00	1208.24	604.12	1384.50	683.75	86.03	-5.219	0.000	0.114
147.00	-2.28	-6.83	0.00	-52.54	0.00	52.54	1197.60	598.80	1353.24	668.32	88.22	-5.235	0.000	0.081
150.00	-2.08	-6.41	0.00	-32.05	0.00	32.05	1181.32	590.66	1306.64	645.30	91.51	-5.252	0.000	0.052

Calculated Forces

Structure: CT00302-S-SBA **Code:** EIA/TIA-222-G 11/1/2017
Site Name: Danielson **Exposure:** B
Height: 155.00 (ft) **Crest Height:** 172.00
Base Elev: 0.000 (ft) **Site Class:** C - Very Dense Soil
Gh: 1.1 **Topography:** 3 **Struct Class:** II Page: 24



155.00	0.00	-6.19	0.00	0.00	0.00	0.00	0.00	1153.35	576.68	1229.81	607.36	97.01	-5.264	0.000	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	-------	--------	-------	-------

Wind Loading - Shaft

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II




Page: 25

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Iterations 22

Dead Load Factor 1.20
Wind Load Factor 1.00



Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	2.18	0.70	9.285	10.21	0.00	1.200	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		2.10	0.70	8.949	9.84	0.00	1.200	2.148	5.00	24.834	29.80	293.4	766.1	2274.8
10.00		2.03	0.70	8.638	9.50	0.00	1.200	2.274	5.00	24.527	29.43	279.7	798.6	2280.1
11.50	RB2	2.01	0.70	8.549	9.40	0.00	1.200	2.298	1.50	7.283	8.74	82.2	240.9	680.0
15.00		1.96	0.70	8.350	9.18	0.00	1.200	2.340	3.50	16.875	20.25	186.0	565.8	1580.9
16.50	RT2	1.94	0.70	8.267	9.09	0.00	1.200	2.354	1.50	7.174	8.61	78.3	242.7	673.7
20.00		1.90	0.70	8.082	8.89	0.00	1.200	2.381	3.50	16.610	19.93	177.2	565.8	1561.9
21.00	RT1 RB3	1.89	0.70	8.031	8.83	0.00	1.200	2.387	1.00	4.710	5.65	49.9	161.5	443.7
25.00		1.84	0.70	7.834	8.62	0.00	1.200	2.408	4.00	18.688	22.43	193.2	642.5	1760.1
30.00		1.79	0.70	7.609	8.37	0.00	1.200	2.427	5.00	23.004	27.60	231.1	794.6	2167.1
35.00	Appurtenance(s)	1.74	0.73	7.727	8.50	0.00	1.200	2.440	5.00	22.602	27.12	230.5	783.9	2129.3
36.00	Bot - Section 2	1.73	0.74	7.746	8.52	0.00	1.200	2.442	1.00	4.471	5.37	45.7	156.3	422.1
40.00		1.69	0.76	7.811	8.59	0.00	1.200	2.449	4.00	17.984	21.58	185.4	627.0	2606.4
41.00	RT3 RB4	1.68	0.77	7.824	8.61	0.00	1.200	2.451	1.00	4.455	5.35	46.0	156.2	646.0
42.00	Top - Section 1	1.67	0.77	7.837	8.62	0.00	1.200	2.452	1.00	4.439	5.33	45.9	155.7	643.5
45.00		1.65	0.79	7.869	8.66	0.00	1.200	2.456	3.00	13.219	15.86	137.3	462.4	1142.1
50.00		1.60	0.81	7.909	8.70	0.00	1.200	2.460	5.00	21.705	26.05	226.6	756.8	1870.9
55.00		1.57	0.83	7.935	8.73	0.00	1.200	2.463	5.00	21.294	25.55	223.0	742.5	1833.0
58.00	RB5	1.55	0.85	7.946	8.74	0.00	1.200	2.464	3.00	12.579	15.10	131.9	440.2	1083.2
58.50	RT4	1.54	0.85	7.947	8.74	0.00	1.200	2.464	0.50	2.082	2.50	21.8	73.2	179.6
60.00		1.53	0.85	7.951	8.75	0.00	1.200	2.465	1.50	6.222	7.47	65.3	218.3	535.9
65.00		1.50	0.87	7.960	8.76	0.00	1.200	2.466	5.00	20.472	24.57	215.1	712.8	1756.1
70.00	Bot - Section 3	1.47	0.89	7.963	8.76	0.00	1.200	2.466	5.00	20.059	24.07	210.8	697.6	1717.3
75.00		1.44	0.91	7.962	8.76	0.00	1.200	2.466	5.00	19.916	23.90	209.3	692.3	2532.6
76.00	Top - Section 2 RT5	1.43	0.91	7.962	8.76	0.00	1.200	2.466	1.00	3.934	4.72	41.3	137.8	500.7
80.00		1.41	0.93	7.959	8.75	0.00	1.200	2.465	4.00	15.570	18.68	163.6	541.5	1199.6
85.00		1.39	0.94	7.953	8.75	0.00	1.200	2.465	5.00	19.090	22.91	200.4	661.4	1466.4
90.00		1.36	0.96	7.947	8.74	0.00	1.200	2.464	5.00	18.677	22.41	195.9	645.9	1431.2
95.00		1.34	0.97	7.941	8.73	0.00	1.200	2.464	5.00	18.264	21.92	191.4	630.5	1396.1
96.00	RT6 RB7	1.34	0.98	7.939	8.73	0.00	1.200	2.463	1.00	3.603	4.32	37.8	125.5	276.2
100.00	Top - Section 3	1.32	0.99	7.934	8.73	0.00	1.200	2.463	4.00	14.248	17.10	149.2	492.0	1087.2
105.00		1.30	1.00	7.928	8.72	0.00	1.200	2.462	5.00	17.438	20.93	182.5	599.6	1181.7
110.00		1.28	1.02	7.923	8.71	0.00	1.200	2.462	5.00	17.025	20.43	178.0	584.2	1150.5
113.50	RT7	1.27	1.02	7.919	8.71	0.00	1.200	2.461	3.50	11.671	14.01	122.0	401.4	788.5
115.00	Bot - Section 5	1.27	1.03	7.918	8.71	0.00	1.200	2.461	1.50	4.940	5.93	51.6	170.6	334.2
117.00	Appurtenance(s)	1.26	1.03	7.916	8.71	0.00	1.200	2.461	2.00	6.615	7.94	69.1	228.2	663.3
120.00	Top - Section 4	1.25	1.04	7.914	8.71	0.00	1.200	2.461	3.00	9.799	11.76	102.4	336.8	979.9
125.00		1.24	1.05	7.912	8.70	0.00	1.200	2.460	5.00	16.002	19.20	167.1	546.1	1073.5
127.00	Appurtenance(s)	1.23	1.06	7.911	8.70	0.00	1.200	2.460	2.00	6.285	7.54	65.6	216.0	422.6
130.00		1.22	1.07	7.911	8.70	0.00	1.200	2.460	3.00	9.304	11.16	97.2	318.5	623.6
135.00		1.21	1.08	7.911	8.70	0.00	1.200	2.460	5.00	15.176	18.21	158.5	515.5	1011.5
137.00	Appurtenance(s)	1.20	1.08	7.911	8.70	0.00	1.200	2.460	2.00	5.955	7.15	62.2	203.8	397.8
140.00		1.20	1.09	7.912	8.70	0.00	1.200	2.460	3.00	8.809	10.57	92.0	300.2	586.5
145.00		1.18	1.10	7.915	8.71	0.00	1.200	2.461	5.00	14.351	17.22	149.9	485.1	949.7
147.00	Appurtenance(s)	1.18	1.10	7.916	8.71	0.00	1.200	2.461	2.00	5.625	6.75	58.8	191.6	373.0
150.00		1.17	1.11	7.918	8.71	0.00	1.200	2.461	3.00	8.314	9.98	86.9	282.0	549.4
155.00	Appurtenance(s)	1.16	1.12	7.924	8.72	0.00	1.200	2.462	5.00	13.527	16.23	141.5	454.8	887.9

Wind Loading - Shaft

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Struct Class: II	Page: 26



Totals:	155.00	6,330.7	51,851.4
----------------	---------------	----------------	-----------------

Discrete Appurtenance Forces


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 27

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 22

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)
1	155.00	RRH2X60-AWS	3	7.924	8.716	0.54	0.80	7.42	476.29	0.000	0.000	64.66	0.00	0.00
2	155.00	LNx-6514DS-A1M	3	7.924	8.716	0.66	0.80	24.21	732.69	0.000	0.000	210.99	0.00	0.00
3	155.00	BXA-70080-4BF	3	7.924	8.716	0.61	0.80	13.47	409.12	0.000	0.000	117.40	0.00	0.00
4	155.00	HBXX-6517DS-A2M	6	7.924	8.716	0.62	0.80	46.82	1482.98	0.000	0.000	408.06	0.00	0.00
5	155.00	DB-T1-6Z-8AB-0Z	1	7.924	8.716	0.57	0.80	3.45	240.60	0.000	0.000	30.03	0.00	0.00
6	155.00	RRH2X60-PCS	3	7.924	8.716	0.54	0.80	5.04	591.23	0.000	0.000	43.89	0.00	0.00
7	155.00	RRH2X60-700	3	7.924	8.716	0.54	0.80	4.41	490.50	0.000	0.000	38.44	0.00	0.00
8	155.00	FD9R6004/2C-3L	6	7.924	8.716	0.40	0.80	2.36	76.45	0.000	0.000	20.61	0.00	0.00
9	155.00	(3) T-Frame w/ Platforms	1	7.924	8.716	1.00	1.00	53.31	3757.98	0.000	0.000	464.65	0.00	0.00
10	147.00	(3) T-Frame w/ Platforms	1	7.916	8.708	1.00	1.00	53.30	3757.31	0.000	0.000	464.11	0.00	0.00
11	147.00	ACU-A20-N	4	7.916	8.708	0.63	0.80	1.41	23.83	0.000	0.000	12.29	0.00	0.00
12	147.00	800 MHz Filter	3	7.916	8.708	0.55	0.80	2.80	91.31	0.000	0.000	24.40	0.00	0.00
13	147.00	800 MHz RRH	3	7.916	8.708	0.54	0.80	6.60	440.37	0.000	0.000	57.45	0.00	0.00
14	147.00	1900 MHz RRH	3	7.916	8.708	0.54	0.80	5.20	1424.32	0.000	0.000	45.24	0.00	0.00
15	147.00	TD-RRH8x20-25	3	7.916	8.708	0.55	0.80	8.67	760.24	0.000	0.000	75.45	0.00	0.00
16	147.00	APXVTM14-C-120	3	7.916	8.708	0.63	0.80	15.08	937.44	0.000	0.000	131.27	0.00	0.00
17	147.00	APXVSP18-C-A20	3	7.916	8.708	0.66	0.80	23.82	787.90	0.000	0.000	207.44	0.00	0.00
18	137.00	59212	6	7.911	8.702	0.53	0.80	24.70	1676.84	0.000	0.000	214.95	0.00	0.00
19	137.00	(3) T-Frame w/ Platforms	1	7.911	8.702	1.00	1.00	53.29	3756.87	0.000	0.000	463.77	0.00	0.00
20	127.00	Low Profile	1	7.911	8.702	1.00	1.00	46.90	3345.27	0.000	0.000	408.13	0.00	0.00
21	127.00	7770.00	6	7.911	8.702	0.58	0.80	24.68	1504.06	0.000	0.000	214.74	0.00	0.00
22	127.00	HPA-65R-BUU-H8	3	7.911	8.702	0.63	0.80	29.03	1559.90	0.000	0.000	252.66	0.00	0.00
23	127.00	LGP21401	6	7.911	8.702	0.40	0.80	4.80	262.84	0.000	0.000	41.75	0.00	0.00
24	127.00	RRUS 11	3	7.911	8.702	0.54	0.80	5.58	595.61	0.000	0.000	48.58	0.00	0.00
25	127.00	RRUS 32 B2	3	7.911	8.702	0.54	0.80	6.11	625.64	0.000	0.000	53.18	0.00	0.00
26	127.00	DC6-48-60-18-8F	1	7.911	8.702	0.80	0.80	1.23	107.62	0.000	0.000	10.70	0.00	0.00
27	127.00	LGP13519	6	7.911	8.702	0.54	0.80	3.15	102.30	0.000	0.000	27.43	0.00	0.00
28	117.00	742 351	6	7.916	8.708	0.49	0.80	23.96	857.04	0.000	0.000	208.61	0.00	0.00
29	117.00	T-Frames	3	7.916	8.708	0.56	0.75	58.82	7068.58	0.000	0.000	512.24	0.00	0.00
30	35.00	3.58' Standoff	1	7.727	8.500	0.67	1.00	2.94	89.41	0.000	0.000	25.01	0.00	0.00
31	35.00	DB589	1	7.805	8.585	0.80	0.80	3.70	55.45	0.000	4.600	31.80	0.00	146.29
Totals:									38,087.98			4,929.96		

Total Applied Force Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II




Page: 28

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20

Wind Load Factor 1.00



Iterations 22

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		293.36	2876.54	0.00	0.00
10.00		279.66	2896.84	0.00	0.00
11.50		82.19	865.91	0.00	0.00
15.00		185.99	2018.20	0.00	0.00
16.50		78.29	861.59	0.00	0.00
20.00		177.20	2002.60	0.00	0.00
21.00		49.93	569.73	0.00	0.00
25.00		193.24	2266.42	0.00	0.00
30.00		231.05	2802.29	0.00	0.00
35.00	(2) attachments	287.35	2910.87	0.00	146.29
36.00		45.72	548.27	0.00	0.00
40.00		185.41	3111.68	0.00	0.00
41.00		46.01	772.37	0.00	0.00
42.00		45.91	769.85	0.00	0.00
45.00		137.30	1521.59	0.00	0.00
50.00		226.59	2503.82	0.00	0.00
55.00		223.04	2466.24	0.00	0.00
58.00		131.93	1463.23	0.00	0.00
58.50		21.84	216.31	0.00	0.00
60.00		65.30	646.19	0.00	0.00
65.00		215.09	2123.68	0.00	0.00
70.00		210.84	2084.93	0.00	0.00
75.00		209.32	2900.27	0.00	0.00
76.00		41.34	574.25	0.00	0.00
80.00		163.56	1493.68	0.00	0.00
85.00		200.42	1833.94	0.00	0.00
90.00		195.93	1798.79	0.00	0.00
95.00		191.44	1763.64	0.00	0.00
96.00		37.76	349.75	0.00	0.00
100.00		149.22	1381.23	0.00	0.00
105.00		182.49	1549.14	0.00	0.00
110.00		178.04	1517.98	0.00	0.00
113.50		122.01	1045.68	0.00	0.00
115.00		51.63	444.40	0.00	0.00
117.00	(9) attachments	789.97	8705.90	0.00	0.00
120.00		102.37	1110.25	0.00	0.00
125.00		167.12	1290.72	0.00	0.00
127.00	(29) attachments	1122.81	8612.67	0.00	0.00
130.00		97.15	704.70	0.00	0.00
135.00		158.47	1146.67	0.00	0.00
137.00	(7) attachments	740.91	5885.54	0.00	0.00
140.00		92.00	645.08	0.00	0.00
145.00		149.93	1047.37	0.00	0.00
147.00	(23) attachments	1076.43	8634.83	0.00	0.00
150.00		86.90	598.50	0.00	0.00
155.00	(29) attachments	1540.22	9227.62	0.00	0.00

Total Applied Force Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Struct Class: II	Page: 29



Totals:	<u>11,260.70</u>	<u>102,561.7</u> 3	<u>0.00</u>	<u>146.29</u>
----------------	------------------	-----------------------	-------------	---------------

Linear Appurtenance Segment Forces (Factored)


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 30

Load Case: 1.2D + 1.0Di + 1.0Wi 50 mph Wind

Dead Load Factor 1.20
Wind Load Factor 1.00



Iterations 22

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	3.27	0.00	0.064	0.000	8.949	0.00	302.95
10.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	3.38	0.00	0.066	0.000	8.638	0.00	317.90
11.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	1.02	0.00	0.066	0.000	8.549	0.00	96.22
15.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	2.40	0.00	0.067	0.000	8.350	0.00	228.09
16.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	1.03	0.00	0.068	0.000	8.267	0.00	98.27
20.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	2.43	0.00	0.068	0.000	8.082	0.00	231.55
21.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.69	0.00	0.069	0.000	8.031	0.00	66.31
25.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	2.79	0.00	0.069	0.000	7.834	0.00	267.27
30.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	3.51	0.00	0.071	0.000	7.609	0.00	336.36
35.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	3.52	0.00	0.072	0.000	7.727	0.00	337.96
36.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.70	0.00	0.073	0.000	7.746	0.00	67.64
40.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	2.82	0.00	0.074	0.000	7.811	0.00	271.26
41.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.71	0.00	0.075	0.000	7.824	0.00	67.85
42.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.71	0.00	0.075	0.000	7.837	0.00	67.88
45.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	2.12	0.00	0.074	0.000	7.869	0.00	203.91
50.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	3.53	0.00	0.075	0.000	7.909	0.00	340.38
55.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	3.54	0.00	0.077	0.000	7.935	0.00	340.73
58.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	2.12	0.00	0.078	0.000	7.946	0.00	204.52
58.50	1.25" Reinforcing	Yes	0.50	0.000	2.50	0.31	0.00	0.056	0.000	7.947	0.00	7.50
60.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.93	0.00	0.056	0.000	7.951	0.00	22.50
65.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.10	0.00	0.057	0.000	7.960	0.00	75.05
70.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.10	0.00	0.058	0.000	7.963	0.00	75.06
75.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.10	0.00	0.059	0.000	7.962	0.00	75.06
76.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.62	0.00	0.060	0.000	7.962	0.00	15.01
80.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	2.48	0.00	0.060	0.000	7.959	0.00	60.03
85.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.10	0.00	0.061	0.000	7.953	0.00	75.02
90.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.10	0.00	0.063	0.000	7.947	0.00	74.99
95.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.09	0.00	0.064	0.000	7.941	0.00	74.96
96.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.62	0.00	0.065	0.000	7.939	0.00	14.99
100.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	2.48	0.00	0.066	0.000	7.934	0.00	59.94
105.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.09	0.00	0.068	0.000	7.928	0.00	74.90
110.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	3.09	0.00	0.070	0.000	7.923	0.00	74.87
113.50	1.25" Reinforcing	Yes	3.50	0.000	2.50	2.16	0.00	0.071	0.000	7.919	0.00	52.40
115.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.93	0.00	0.072	0.000	7.918	0.00	22.45
Totals:											0.0	4,701.8

Calculated Forces

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II
		Page: 32



155.00	0.00	-1.54	0.00	0.00	0.00	0.00	0.00	1153.35	576.68	1229.81	607.36	25.25	-1.391	0.000	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	-------	--------	-------	-------


Seismic Segment Forces (Factored)

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 33

Load Case: 1.2D + 1.0E					Iterations 20
Gust Response Factor	1.10			Sds 0.14	Ss 0.17
Dead Load Factor	1.20	Seismic Load Factor	1.00	Sd1 0.07	S1 0.06
Wind Load Factor	0.00	Structure Frequency	0.32	SA 0.02	Seismic Importance Factor 1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00	RB1	0.00	0.00	0.00	0.00	0.00	
5.00		1257.2	0.00	0.03	0.02	17.20	
10.00		1234.5	0.01	0.05	0.03	24.34	
11.50	RB2	365.95	0.01	0.06	0.03	7.62	
15.00		845.94	0.02	0.06	0.04	19.20	
16.50	RT2	359.14	0.02	0.06	0.04	8.35	
20.00		830.05	0.03	0.07	0.04	20.11	
21.00	RT1 RB3	235.12	0.03	0.07	0.04	5.75	
25.00		931.38	0.05	0.07	0.04	23.39	
30.00		1143.8	0.07	0.07	0.04	29.46	
35.00	Appurtenance(s)	1202.6	0.10	0.07	0.04	31.71	
36.00	Bot - Section 2	221.50	0.10	0.07	0.04	5.87	
40.00		1649.4	0.13	0.07	0.03	44.50	
41.00	RT3 RB4	408.14	0.13	0.07	0.03	11.06	
42.00	Top - Section 1	406.44	0.14	0.07	0.03	11.06	
45.00		566.45	0.16	0.07	0.03	15.57	
50.00		928.37	0.20	0.06	0.02	25.70	
55.00		908.72	0.24	0.06	0.02	24.70	
58.00	RB5	535.80	0.26	0.05	0.02	14.12	
58.50	RT4	88.61	0.27	0.05	0.02	2.32	
60.00		264.66	0.28	0.05	0.01	6.75	
65.00		869.42	0.33	0.04	0.01	19.15	
70.00	Bot - Section 3	849.77	0.39	0.02	0.01	13.84	
75.00		1533.6	0.44	0.00	0.01	12.49	
76.00	Top - Section 2 RT5 RB6	302.41	0.45	0.00	0.01	1.89	
80.00		548.42	0.50	-0.02	0.01	-0.97	
85.00		670.79	0.57	-0.04	0.01	-8.00	
90.00		654.41	0.64	-0.07	0.02	-13.46	
95.00		638.04	0.71	-0.09	0.03	-16.83	
96.00	RT6 RB7	125.64	0.73	-0.09	0.03	-3.41	
100.00	Top - Section 3	496.02	0.79	-0.11	0.05	-14.26	
105.00		485.09	0.87	-0.12	0.08	-13.37	
110.00		471.99	0.95	-0.12	0.11	-10.80	
113.50	RT7	322.60	1.01	-0.11	0.14	-5.68	
115.00	Bot - Section 5	136.29	1.04	-0.10	0.15	-2.02	
117.00	Appurtenance(s)	3181.3	1.08	-0.08	0.17	-34.01	
120.00	Top - Section 4	535.91	1.13	-0.05	0.21	-1.86	
125.00		439.54	1.23	0.03	0.28	4.92	
127.00	Appurtenance(s)	2586.8	1.27	0.08	0.31	46.52	
130.00		254.29	1.33	0.16	0.36	7.42	
135.00		413.34	1.43	0.35	0.47	20.90	
137.00	Appurtenance(s)	2021.6	1.48	0.44	0.52	121.48	
140.00		238.57	1.54	0.61	0.59	17.99	
145.00		387.14	1.65	0.96	0.75	40.18	
147.00	Appurtenance(s)	2689.5	1.70	1.12	0.81	312.41	
150.00		222.85	1.77	1.41	0.93	30.26	

Seismic Segment Forces (Factored)

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 34

155.00	Appurtenance(s)	2885.4	1.89	1.98	1.14	494.86	
	Totals:	38,345.1				1,368.5	Total Wind: 50,045.9

Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required

Calculated Forces

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



150.00	-3.54	-0.51	0.00	-2.55	0.00	2.55	1181.32	590.66	1306.64	645.30	4.02	-0.26	0.007
155.00	0.00	-0.49	0.00	0.00	0.00	0.00	1153.35	576.68	1229.81	607.36	4.29	-0.26	0.000


Seismic Segment Forces (Factored)

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 37

Load Case: 0.9D + 1.0E					Iterations 20
Gust Response Factor	1.10	Sds	0.14	Ss	0.17
Dead Load Factor	0.90	Seismic Load Factor	1.00	Sd1	0.07
Wind Load Factor	0.00	Structure Frequency	0.32	SA	0.02
					Seismic Importance Factor 1.00



Top Elev (ft)	Description	Wz (lb)	a	b	c	Lateral Fs (lb)	R: 1.50
0.00	RB1	0.00	0.00	0.00	0.00	0.00	
5.00		1257.2	0.00	0.03	0.02	17.20	
10.00		1234.5	0.01	0.05	0.03	24.34	
11.50	RB2	365.95	0.01	0.06	0.03	7.62	
15.00		845.94	0.02	0.06	0.04	19.20	
16.50	RT2	359.14	0.02	0.06	0.04	8.35	
20.00		830.05	0.03	0.07	0.04	20.11	
21.00	RT1 RB3	235.12	0.03	0.07	0.04	5.75	
25.00		931.38	0.05	0.07	0.04	23.39	
30.00		1143.8	0.07	0.07	0.04	29.46	
35.00	Appurtenance(s)	1202.6	0.10	0.07	0.04	31.71	
36.00	Bot - Section 2	221.50	0.10	0.07	0.04	5.87	
40.00		1649.4	0.13	0.07	0.03	44.50	
41.00	RT3 RB4	408.14	0.13	0.07	0.03	11.06	
42.00	Top - Section 1	406.44	0.14	0.07	0.03	11.06	
45.00		566.45	0.16	0.07	0.03	15.57	
50.00		928.37	0.20	0.06	0.02	25.70	
55.00		908.72	0.24	0.06	0.02	24.70	
58.00	RB5	535.80	0.26	0.05	0.02	14.12	
58.50	RT4	88.61	0.27	0.05	0.02	2.32	
60.00		264.66	0.28	0.05	0.01	6.75	
65.00		869.42	0.33	0.04	0.01	19.15	
70.00	Bot - Section 3	849.77	0.39	0.02	0.01	13.84	
75.00		1533.6	0.44	0.00	0.01	12.49	
76.00	Top - Section 2 RT5 RB6	302.41	0.45	0.00	0.01	1.89	
80.00		548.42	0.50	-0.02	0.01	-0.97	
85.00		670.79	0.57	-0.04	0.01	-8.00	
90.00		654.41	0.64	-0.07	0.02	-13.46	
95.00		638.04	0.71	-0.09	0.03	-16.83	
96.00	RT6 RB7	125.64	0.73	-0.09	0.03	-3.41	
100.00	Top - Section 3	496.02	0.79	-0.11	0.05	-14.26	
105.00		485.09	0.87	-0.12	0.08	-13.37	
110.00		471.99	0.95	-0.12	0.11	-10.80	
113.50	RT7	322.60	1.01	-0.11	0.14	-5.68	
115.00	Bot - Section 5	136.29	1.04	-0.10	0.15	-2.02	
117.00	Appurtenance(s)	3181.3	1.08	-0.08	0.17	-34.01	
120.00	Top - Section 4	535.91	1.13	-0.05	0.21	-1.86	
125.00		439.54	1.23	0.03	0.28	4.92	
127.00	Appurtenance(s)	2586.8	1.27	0.08	0.31	46.52	
130.00		254.29	1.33	0.16	0.36	7.42	
135.00		413.34	1.43	0.35	0.47	20.90	
137.00	Appurtenance(s)	2021.6	1.48	0.44	0.52	121.48	
140.00		238.57	1.54	0.61	0.59	17.99	
145.00		387.14	1.65	0.96	0.75	40.18	
147.00	Appurtenance(s)	2689.5	1.70	1.12	0.81	312.41	
150.00		222.85	1.77	1.41	0.93	30.26	

Seismic Segment Forces (Factored)

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 38

155.00	Appurtenance(s)	2885.4	1.89	1.98	1.14	494.86	
Totals:		38,345.1				1,368.5	Total Wind: 50,045.9

Seismic Base Shear is Less Than 50% of Wind Force - An Analysis is NOT Required

Calculated Forces

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Page: 40
Struct Class: II		




150.00	-2.66	-0.51	0.00	-2.53	0.00	2.53	1181.32	590.66	1306.64	645.30	3.97	-0.25	0.006
155.00	0.00	-0.49	0.00	0.00	0.00	0.00	1153.35	576.68	1229.81	607.36	4.23	-0.26	0.000

Wind Loading - Shaft

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Load Case: 1.0D + 1.0W 60 mph Wind	Iterations 22
Dead Load Factor 1.00	
Wind Load Factor 1.00	

Elev (ft)	Description	Kzt	Kz	qz (psf)	qzGh (psf)	C (mph-ft)	Cf	Ice Thick (in)	Tributary (ft)	Aa (sf)	CfAa (sf)	Wind Force X (lb)	Dead Load Ice (lb)	Tot Dead Load (lb)
0.00	RB1	2.18	0.70	13.370	14.71	344.78	1.000	0.000	0.00	0.000	0.00	0.0	0.0	0.0
5.00		2.10	0.70	12.887	14.18	332.49	1.000	0.000	5.00	23.044	23.04	326.7	0.0	1257.3
10.00		2.03	0.70	12.439	13.68	320.76	1.000	0.000	5.00	22.632	22.63	309.7	0.0	1234.6
11.50	RB2	2.01	0.70	12.311	13.54	317.34	1.000	0.000	1.50	6.709	6.71	90.9	0.0	365.9
15.00		1.96	0.70	12.023	13.23	309.56	1.000	0.000	3.50	15.510	15.51	205.1	0.0	845.9
16.50	RT2	1.94	0.70	11.905	13.10	306.29	1.000	0.000	1.50	6.585	6.59	86.2	0.0	359.1
20.00		1.90	0.70	11.638	12.80	298.85	1.000	0.000	3.50	15.221	15.22	194.9	0.0	830.1
21.00	RT1 RB3	1.89	0.70	11.564	12.72	296.76	1.000	0.000	1.00	4.312	4.31	54.8	0.0	235.1
25.00		1.84	0.70	11.280	12.41	288.60	1.000	0.000	4.00	17.082	17.08	212.0	0.0	931.4
30.00		1.79	0.70	10.957	12.05	278.89	1.000	0.000	5.00	20.981	20.98	252.9	0.0	1143.8
35.00	Appurtenance(s)	1.74	0.73	11.127	12.24	275.47	1.000	0.000	5.00	20.569	20.57	251.8	0.0	1121.1
36.00	Bot - Section 2	1.73	0.74	11.155	12.27	274.69	1.000	0.000	1.00	4.064	4.06	49.9	0.0	221.5
40.00		1.69	0.76	11.247	12.37	271.34	1.000	0.000	4.00	16.351	16.35	202.3	0.0	1649.5
41.00	RT3 RB4	1.68	0.77	11.267	12.39	270.45	1.000	0.000	1.00	4.046	4.05	50.1	0.0	408.1
42.00	Top - Section 1	1.67	0.77	11.285	12.41	269.54	1.000	0.000	1.00	4.030	4.03	50.0	0.0	406.4
45.00		1.65	0.79	11.331	12.46	271.14	1.000	0.000	3.00	11.991	11.99	149.5	0.0	566.5
50.00		1.60	0.81	11.389	12.53	266.17	1.000	0.000	5.00	19.655	19.65	246.2	0.0	928.4
55.00		1.57	0.83	11.426	12.57	260.96	1.000	0.000	5.00	19.242	19.24	241.9	0.0	908.7
58.00	RB5	1.55	0.85	11.442	12.59	257.74	1.000	0.000	3.00	11.347	11.35	142.8	0.0	535.8
58.50	RT4	1.54	0.85	11.444	12.59	257.20	1.000	0.000	0.50	1.877	1.88	23.6	0.0	88.6
60.00		1.53	0.85	11.450	12.59	255.56	1.000	0.000	1.50	5.606	5.61	70.6	0.0	264.7
65.00		1.50	0.87	11.462	12.61	250.03	1.000	0.000	5.00	18.417	18.42	232.2	0.0	869.4
70.00	Bot - Section 3	1.47	0.89	11.466	12.61	244.42	1.000	0.000	5.00	18.004	18.00	227.1	0.0	849.8
75.00		1.44	0.91	11.465	12.61	238.74	1.000	0.000	5.00	17.861	17.86	225.3	0.0	1533.7
76.00	Top - Section 2 RT5	1.43	0.91	11.465	12.61	237.60	1.000	0.000	1.00	3.523	3.52	44.4	0.0	302.4
80.00		1.41	0.93	11.460	12.61	236.73	1.000	0.000	4.00	13.926	13.93	175.6	0.0	548.4
85.00		1.39	0.94	11.453	12.60	230.99	1.000	0.000	5.00	17.036	17.04	214.6	0.0	670.8
90.00		1.36	0.96	11.444	12.59	225.24	1.000	0.000	5.00	16.624	16.62	209.3	0.0	654.4
95.00		1.34	0.97	11.435	12.58	219.49	1.000	0.000	5.00	16.211	16.21	203.9	0.0	638.0
96.00	RT6 RB7	1.34	0.98	11.433	12.58	218.34	1.000	0.000	1.00	3.193	3.19	40.2	0.0	125.6
100.00	Top - Section 3	1.32	0.99	11.425	12.57	213.74	1.000	0.000	4.00	12.606	12.61	158.4	0.0	496.0
105.00		1.30	1.00	11.416	12.56	208.00	1.000	0.000	5.00	15.386	15.39	193.2	0.0	485.1
110.00		1.28	1.02	11.409	12.55	202.28	1.000	0.000	5.00	14.973	14.97	187.9	0.0	472.0
113.50	RT7	1.27	1.02	11.404	12.54	198.28	1.000	0.000	3.50	10.236	10.24	128.4	0.0	322.6
115.00	Bot - Section 5	1.27	1.03	11.402	12.54	196.57	1.000	0.000	1.50	4.325	4.32	54.2	0.0	136.3
117.00	Appurtenance(s)	1.26	1.03	11.400	12.54	194.29	1.000	0.000	2.00	5.795	5.80	72.7	0.0	362.5
120.00	Top - Section 4	1.25	1.04	11.397	12.54	190.88	1.000	0.000	3.00	8.569	8.57	107.4	0.0	535.9
125.00		1.24	1.05	11.393	12.53	188.15	1.000	0.000	5.00	13.951	13.95	174.8	0.0	439.5
127.00	Appurtenance(s)	1.23	1.06	11.392	12.53	185.89	1.000	0.000	2.00	5.465	5.46	68.5	0.0	172.1
130.00		1.22	1.07	11.391	12.53	182.49	1.000	0.000	3.00	8.074	8.07	101.2	0.0	254.3
135.00		1.21	1.08	11.391	12.53	176.84	1.000	0.000	5.00	13.126	13.13	164.5	0.0	413.3
137.00	Appurtenance(s)	1.20	1.08	11.392	12.53	174.59	1.000	0.000	2.00	5.135	5.13	64.3	0.0	161.7
140.00		1.20	1.09	11.393	12.53	171.21	1.000	0.000	3.00	7.579	7.58	95.0	0.0	238.6
145.00		1.18	1.10	11.397	12.54	165.59	1.000	0.000	5.00	12.301	12.30	154.2	0.0	387.1
147.00	Appurtenance(s)	1.18	1.10	11.399	12.54	163.35	1.000	0.000	2.00	4.805	4.80	60.2	0.0	151.2
150.00		1.17	1.11	11.403	12.54	159.98	1.000	0.000	3.00	7.083	7.08	88.8	0.0	222.9
155.00	Appurtenance(s)	1.16	1.12	11.410	12.55	154.38	1.000	0.000	5.00	11.476	11.48	144.0	0.0	360.9

Wind Loading - Shaft

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Struct Class: II	Page: 42



Totals:	155.00	6,802.2	26,107.2
----------------	---------------	----------------	-----------------


Discrete Appurtenance Forces

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 22

No.	Elev (ft)	Description	Qty	qz (psf)	qzGh (psf)	CaAa x Ka	Ka	Total CaAa (sf)	Dead Load (lb)	Horiz Ecc (ft)	Vert Ecc (ft)	Wind FX (lb)	Mom Y (lb-ft)	Mom Z (lb-ft)	
1	155.00	RRH2X60-AWS	3	11.410	12.551	0.54	0.80	5.63	165.00	0.000	0.000	70.64	0.00	0.00	
2	155.00	LNx-6514DS-A1M	3	11.410	12.551	0.66	0.80	16.27	115.20	0.000	0.000	204.26	0.00	0.00	
3	155.00	BXA-70080-4BF	3	11.410	12.551	0.61	0.80	8.68	39.00	0.000	0.000	108.97	0.00	0.00	
4	155.00	HBXX-6517DS-A2M	6	11.410	12.551	0.62	0.80	31.60	244.80	0.000	0.000	396.63	0.00	0.00	
5	155.00	DB-T1-6Z-8AB-OZ	1	11.410	12.551	0.57	0.80	2.73	18.90	0.000	0.000	34.22	0.00	0.00	
6	155.00	RRH2X60-PCS	3	11.410	12.551	0.54	0.80	3.54	165.00	0.000	0.000	44.40	0.00	0.00	
7	155.00	RRH2X60-700	3	11.410	12.551	0.54	0.80	3.02	138.00	0.000	0.000	37.94	0.00	0.00	
8	155.00	FD9R6004/2C-3L	6	11.410	12.551	0.40	0.80	0.86	18.60	0.000	0.000	10.84	0.00	0.00	
9	155.00	(3) T-Frame w/ Platforms	1	11.410	12.551	1.00	1.00	25.00	1620.00	0.000	0.000	313.78	0.00	0.00	
10	147.00	(3) T-Frame w/ Platforms	1	11.399	12.539	1.00	1.00	25.00	1620.00	0.000	0.000	313.47	0.00	0.00	
11	147.00	ACU-A20-N	4	11.399	12.539	0.40	0.80	0.22	4.00	0.000	0.000	2.81	0.00	0.00	
12	147.00	800 MHz Filter	3	11.399	12.539	0.55	0.80	1.29	26.40	0.000	0.000	16.20	0.00	0.00	
13	147.00	800 MHz RRH	3	11.399	12.539	0.54	0.80	4.00	159.00	0.000	0.000	50.20	0.00	0.00	
14	147.00	1900 MHz RRH	3	11.399	12.539	0.54	0.80	3.71	180.00	0.000	0.000	46.58	0.00	0.00	
15	147.00	TD-RRH8x20-25	3	11.399	12.539	0.55	0.80	6.71	210.00	0.000	0.000	84.10	0.00	0.00	
16	147.00	APXVTM14-C-120	3	11.399	12.539	0.63	0.80	12.02	168.00	0.000	0.000	150.73	0.00	0.00	
17	147.00	APXVSP18-C-A20	3	11.399	12.539	0.66	0.80	15.98	171.00	0.000	0.000	200.32	0.00	0.00	
18	137.00	59212	6	11.392	12.531	0.53	0.80	15.74	240.00	0.000	0.000	197.30	0.00	0.00	
19	137.00	(3) T-Frame w/ Platforms	1	11.392	12.531	1.00	1.00	25.00	1620.00	0.000	0.000	313.28	0.00	0.00	
20	127.00	Low Profile	1	11.392	12.531	1.00	1.00	22.00	1500.00	0.000	0.000	275.69	0.00	0.00	
21	127.00	7770.00	6	11.392	12.531	0.58	0.80	19.27	210.00	0.000	0.000	241.51	0.00	0.00	
22	127.00	HPA-65R-BUU-H8	3	11.392	12.531	0.63	0.80	24.61	204.00	0.000	0.000	308.40	0.00	0.00	
23	127.00	LGP21401	6	11.392	12.531	0.40	0.80	2.28	105.00	0.000	0.000	28.57	0.00	0.00	
24	127.00	RRUS 11	3	11.392	12.531	0.54	0.80	4.05	152.10	0.000	0.000	50.78	0.00	0.00	
25	127.00	RRUS 32 B2	3	11.392	12.531	0.54	0.80	4.41	180.00	0.000	0.000	55.21	0.00	0.00	
26	127.00	DC6-48-60-18-8F	1	11.392	12.531	0.80	0.80	0.74	31.80	0.000	0.000	9.22	0.00	0.00	
27	127.00	LGP13519	6	11.392	12.531	0.54	0.80	1.09	31.80	0.000	0.000	13.70	0.00	0.00	
28	117.00	742 351	6	11.400	12.540	0.49	0.80	15.75	178.80	0.000	0.000	197.53	0.00	0.00	
29	117.00	T-Frames	3	11.400	12.540	0.56	0.75	34.42	2640.00	0.000	0.000	431.68	0.00	0.00	
30	35.00	3.58' Standoff	1	11.127	12.240	0.67	1.00	1.12	70.00	0.000	0.000	13.70	0.00	0.00	
31	35.00	DB589	1	11.239	12.363	0.80	0.80	1.10	11.50	0.000	4.600	13.65	0.00	62.78	
Totals:									12,237.90						4,236.31

Total Applied Force Summary


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 44

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 22

Elev (ft)	Description	Lateral FX (-) (lb)	Axial FY (-) (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)
0.00		0.00	0.00	0.00	0.00
5.00		326.66	1506.28	0.00	0.00
10.00		309.66	1483.58	0.00	0.00
11.50		90.85	440.65	0.00	0.00
15.00		205.13	1020.24	0.00	0.00
16.50		86.24	433.84	0.00	0.00
20.00		194.86	1004.35	0.00	0.00
21.00		54.85	284.92	0.00	0.00
25.00		211.96	1130.58	0.00	0.00
30.00		252.88	1392.81	0.00	0.00
35.00	(2) attachments	279.10	1451.61	0.00	62.78
36.00		49.87	270.26	0.00	0.00
40.00		202.29	1844.52	0.00	0.00
41.00		50.15	456.90	0.00	0.00
42.00		50.02	455.20	0.00	0.00
45.00		149.46	712.73	0.00	0.00
50.00		246.22	1172.17	0.00	0.00
55.00		241.85	1152.52	0.00	0.00
58.00		142.81	682.08	0.00	0.00
58.50		23.63	112.99	0.00	0.00
60.00		70.60	337.80	0.00	0.00
65.00		232.20	1113.22	0.00	0.00
70.00		227.09	1093.57	0.00	0.00
75.00		225.26	1777.46	0.00	0.00
76.00		44.43	351.17	0.00	0.00
80.00		175.56	743.46	0.00	0.00
85.00		214.63	914.59	0.00	0.00
90.00		209.27	898.21	0.00	0.00
95.00		203.90	881.84	0.00	0.00
96.00		40.15	174.40	0.00	0.00
100.00		158.43	691.06	0.00	0.00
105.00		193.22	728.89	0.00	0.00
110.00		187.91	715.79	0.00	0.00
113.50		128.40	493.26	0.00	0.00
115.00		54.24	209.43	0.00	0.00
117.00	(9) attachments	701.88	3278.83	0.00	0.00
120.00		107.42	644.51	0.00	0.00
125.00		174.84	620.54	0.00	0.00
127.00	(29) attachments	1051.57	2659.25	0.00	0.00
130.00		101.17	321.85	0.00	0.00
135.00		164.48	525.94	0.00	0.00
137.00	(7) attachments	574.93	2066.71	0.00	0.00
140.00		94.98	287.41	0.00	0.00
145.00		154.21	468.54	0.00	0.00
147.00	(23) attachments	924.65	2722.15	0.00	0.00
150.00		88.85	263.77	0.00	0.00
155.00	(29) attachments	1365.72	2953.64	0.00	0.00

Total Applied Force Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Struct Class: II	Page: 45



Totals:	<u>11,038.47</u>	<u>44,945.51</u>	<u>0.00</u>	<u>62.78</u>
----------------	------------------	------------------	-------------	--------------

Linear Appurtenance Segment Forces (Factored)


Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 46

Load Case: 1.0D + 1.0W 60 mph Wind

Dead Load Factor 1.00
Wind Load Factor 1.00



Iterations 22

Top Elev (ft)	Description	Wind Exposed	Length (ft)	Ca	Exposed Width (in)	Area (sqft)	CaAa (sqft)	Ra	Cf Adjust Factor	qz (psf)	F X (lb)	Dead Load (lb)
5.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.064	0.000	12.887	0.00	0.00
10.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.066	0.000	12.439	0.00	0.00
11.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	0.45	0.00	0.066	0.000	12.311	0.00	0.00
15.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	1.04	0.00	0.067	0.000	12.023	0.00	0.00
16.50	10"x1/2" Bent plate	Yes	1.50	0.000	3.56	0.45	0.00	0.068	0.000	11.905	0.00	0.00
20.00	10"x1/2" Bent plate	Yes	3.50	0.000	3.56	1.04	0.00	0.068	0.000	11.638	0.00	0.00
21.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.069	0.000	11.564	0.00	0.00
25.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	1.19	0.00	0.069	0.000	11.280	0.00	0.00
30.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.071	0.000	10.957	0.00	0.00
35.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.072	0.000	11.127	0.00	0.00
36.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.073	0.000	11.155	0.00	0.00
40.00	10"x1/2" Bent plate	Yes	4.00	0.000	3.56	1.19	0.00	0.074	0.000	11.247	0.00	0.00
41.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.075	0.000	11.267	0.00	0.00
42.00	10"x1/2" Bent plate	Yes	1.00	0.000	3.56	0.30	0.00	0.075	0.000	11.285	0.00	0.00
45.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	0.89	0.00	0.074	0.000	11.331	0.00	0.00
50.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.075	0.000	11.389	0.00	0.00
55.00	10"x1/2" Bent plate	Yes	5.00	0.000	3.56	1.48	0.00	0.077	0.000	11.426	0.00	0.00
58.00	10"x1/2" Bent plate	Yes	3.00	0.000	3.56	0.89	0.00	0.078	0.000	11.442	0.00	0.00
58.50	1.25" Reinforcing	Yes	0.50	0.000	2.50	0.10	0.00	0.056	0.000	11.444	0.00	0.00
60.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.31	0.00	0.056	0.000	11.450	0.00	0.00
65.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.057	0.000	11.462	0.00	0.00
70.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.058	0.000	11.466	0.00	0.00
75.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.059	0.000	11.465	0.00	0.00
76.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.21	0.00	0.060	0.000	11.465	0.00	0.00
80.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	0.83	0.00	0.060	0.000	11.460	0.00	0.00
85.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.061	0.000	11.453	0.00	0.00
90.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.063	0.000	11.444	0.00	0.00
95.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.064	0.000	11.435	0.00	0.00
96.00	1.25" Reinforcing	Yes	1.00	0.000	2.50	0.21	0.00	0.065	0.000	11.433	0.00	0.00
100.00	1.25" Reinforcing	Yes	4.00	0.000	2.50	0.83	0.00	0.066	0.000	11.425	0.00	0.00
105.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.068	0.000	11.416	0.00	0.00
110.00	1.25" Reinforcing	Yes	5.00	0.000	2.50	1.04	0.00	0.070	0.000	11.409	0.00	0.00
113.50	1.25" Reinforcing	Yes	3.50	0.000	2.50	0.73	0.00	0.071	0.000	11.404	0.00	0.00
115.00	1.25" Reinforcing	Yes	1.50	0.000	2.50	0.31	0.00	0.072	0.000	11.402	0.00	0.00
Totals:											0.0	0.0

Calculated Forces


Structure: CT00302-S-SBA
Site Name: Danielson
Height: 155.00 (ft)
Base Elev: 0.000 (ft)
Gh: 1.1

Code: EIA/TIA-222-G
Exposure: B
Crest Height: 172.00
Site Class: C - Very Dense Soil
Struct Class: II

11/1/2017
 Page: 47



Load Case: 1.0D + 1.0W 60 mph Wind	Iterations 22
Dead Load Factor 1.00	
Wind Load Factor 1.00	



Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation Sway (deg)	Rotation Twist (deg)	Stress Ratio
0.00	-44.94	-11.06	0.00	-1094.4	0.00	1094.42	4048.32	2024.16	8933.65	4411.99	0.00	0.000	0.000	0.214
5.00	-43.43	-10.76	0.00	-1039.1	0.00	1039.14	4007.22	2003.61	8683.49	4288.45	0.02	-0.046	0.000	0.208
10.00	-41.94	-10.47	0.00	-985.32	0.00	985.32	3964.98	1982.49	8434.18	4165.32	0.10	-0.092	0.000	0.202
11.50	-41.49	-10.40	0.00	-969.61	0.00	969.61	3952.09	1976.04	8359.57	4128.48	0.13	-0.106	0.000	0.171
15.00	-40.47	-10.20	0.00	-933.21	0.00	933.21	3921.60	1960.80	8185.84	4042.68	0.22	-0.134	0.000	0.168
16.50	-40.03	-10.13	0.00	-917.91	0.00	917.91	3908.36	1954.18	8111.55	4005.99	0.26	-0.146	0.000	0.195
20.00	-39.02	-9.95	0.00	-882.44	0.00	882.44	3877.07	1938.54	7938.63	3920.59	0.38	-0.178	0.000	0.191
21.00	-38.74	-9.91	0.00	-872.49	0.00	872.49	3868.03	1934.02	7889.33	3896.24	0.42	-0.187	0.000	0.190
25.00	-37.60	-9.72	0.00	-832.86	0.00	832.86	3831.41	1915.70	7692.66	3799.12	0.59	-0.224	0.000	0.186
30.00	-36.20	-9.49	0.00	-784.25	0.00	784.25	3784.60	1892.30	7448.09	3678.33	0.85	-0.270	0.000	0.180
35.00	-34.75	-9.22	0.00	-736.74	0.00	736.74	3736.66	1868.33	7205.04	3558.30	1.16	-0.315	0.000	0.174
36.00	-34.47	-9.18	0.00	-727.52	0.00	727.52	3726.93	1863.47	7156.62	3534.39	1.23	-0.324	0.000	0.173
40.00	-32.63	-8.98	0.00	-690.79	0.00	690.79	3687.57	1843.78	6963.65	3439.09	1.51	-0.360	0.000	0.167
41.00	-32.17	-8.93	0.00	-681.81	0.00	681.81	3677.62	1838.81	6915.58	3415.35	1.59	-0.369	0.000	0.166
42.00	-31.71	-8.89	0.00	-672.88	0.00	672.88	3033.05	1516.53	5788.55	2858.75	1.67	-0.378	0.000	0.178
45.00	-30.99	-8.76	0.00	-646.20	0.00	646.20	3011.75	1505.88	5675.99	2803.16	1.91	-0.405	0.000	0.187
50.00	-29.82	-8.53	0.00	-602.42	0.00	602.42	2975.34	1487.67	5488.97	2710.80	2.36	-0.452	0.000	0.179
55.00	-28.66	-8.29	0.00	-559.79	0.00	559.79	2937.79	1468.89	5302.79	2618.85	2.86	-0.499	0.000	0.172
58.00	-27.98	-8.15	0.00	-534.91	0.00	534.91	2914.71	1457.35	5191.54	2563.91	3.18	-0.527	0.000	0.129
58.50	-27.86	-8.13	0.00	-530.84	0.00	530.84	2910.82	1455.41	5173.04	2554.77	3.24	-0.530	0.000	0.157
60.00	-27.52	-8.07	0.00	-518.64	0.00	518.64	2899.09	1449.55	5117.58	2527.38	3.41	-0.544	0.000	0.155
65.00	-26.40	-7.85	0.00	-478.29	0.00	478.29	2859.26	1429.63	4933.49	2436.46	4.00	-0.586	0.000	0.148
70.00	-25.31	-7.63	0.00	-439.05	0.00	439.05	2818.28	1409.14	4750.64	2346.16	4.64	-0.627	0.000	0.140
75.00	-23.53	-7.39	0.00	-400.92	0.00	400.92	2776.16	1388.08	4569.18	2256.54	5.32	-0.668	0.000	0.131
76.00	-23.18	-7.35	0.00	-393.53	0.00	393.53	2161.97	1080.98	3608.45	1782.08	5.46	-0.676	0.000	0.147
80.00	-22.43	-7.18	0.00	-364.13	0.00	364.13	2139.97	1069.98	3503.61	1730.30	6.04	-0.708	0.000	0.153
85.00	-21.51	-6.97	0.00	-328.22	0.00	328.22	2111.44	1055.72	3372.88	1665.74	6.80	-0.750	0.000	0.142
90.00	-20.61	-6.76	0.00	-293.37	0.00	293.37	2081.77	1040.89	3242.65	1601.42	7.61	-0.791	0.000	0.131
95.00	-19.73	-6.55	0.00	-259.56	0.00	259.56	2050.97	1025.48	3113.05	1537.42	8.46	-0.830	0.000	0.120
96.00	-19.56	-6.52	0.00	-253.00	0.00	253.00	2044.67	1022.33	3087.22	1524.66	8.63	-0.837	0.000	0.127
100.00	-18.86	-6.36	0.00	-226.93	0.00	226.93	2019.02	1009.51	2984.22	1473.79	9.35	-0.869	0.000	0.118
100.00	-18.86	-6.36	0.00	-226.93	0.00	226.93	1394.49	697.25	2068.33	1021.47	9.35	-0.869	0.000	0.137
105.00	-18.13	-6.17	0.00	-195.12	0.00	195.12	1376.43	688.21	1986.77	981.19	10.28	-0.905	0.000	0.142
110.00	-17.42	-5.98	0.00	-164.28	0.00	164.28	1357.32	678.66	1905.17	940.89	11.25	-0.944	0.000	0.124
113.50	-16.93	-5.85	0.00	-143.35	0.00	143.35	1343.33	671.66	1848.11	912.71	11.95	-0.969	0.000	0.111
113.50	-16.93	-5.85	0.00	-143.35	0.00	143.35	1343.33	671.66	1848.11	912.71	11.95	-0.969	0.000	0.111
115.00	-16.72	-5.79	0.00	-134.58	0.00	134.58	1337.17	668.58	1823.68	900.65	12.26	-0.980	0.000	0.162
117.00	-13.45	-5.04	0.00	-122.99	0.00	122.99	1328.82	664.41	1791.13	884.57	12.67	-0.999	0.000	0.149
120.00	-12.80	-4.93	0.00	-107.87	0.00	107.87	1327.18	663.59	1784.85	881.47	13.31	-1.027	0.000	0.132
125.00	-12.18	-4.75	0.00	-83.22	0.00	83.22	1305.49	652.74	1703.72	841.41	14.41	-1.067	0.000	0.108
127.00	-9.54	-3.65	0.00	-73.72	0.00	73.72	1296.51	648.26	1671.38	825.43	14.86	-1.081	0.000	0.097
130.00	-9.22	-3.55	0.00	-62.76	0.00	62.76	1282.74	641.37	1623.00	801.54	15.54	-1.099	0.000	0.086
135.00	-8.70	-3.38	0.00	-45.03	0.00	45.03	1258.96	629.48	1542.80	761.93	16.71	-1.125	0.000	0.066
137.00	-6.64	-2.76	0.00	-38.28	0.00	38.28	1249.15	624.57	1510.90	746.18	17.18	-1.134	0.000	0.057
140.00	-6.36	-2.66	0.00	-29.99	0.00	29.99	1234.12	617.06	1463.26	722.65	17.90	-1.145	0.000	0.047
145.00	-5.89	-2.50	0.00	-16.68	0.00	16.68	1208.24	604.12	1384.50	683.75	19.11	-1.159	0.000	0.029
147.00	-3.19	-1.52	0.00	-11.69	0.00	11.69	1197.60	598.80	1353.24	668.32	19.59	-1.163	0.000	0.020
150.00	-2.93	-1.43	0.00	-7.13	0.00	7.13	1181.32	590.66	1306.64	645.30	20.32	-1.166	0.000	0.014

Calculated Forces

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Page: 48
Struct Class: II		



155.00	0.00	-1.37	0.00	0.00	0.00	0.00	0.00	1153.35	576.68	1229.81	607.36	21.55	-1.169	0.000	0.000
--------	------	-------	------	------	------	------	------	---------	--------	---------	--------	-------	--------	-------	-------

Final Analysis Summary

Structure: CT00302-S-SBA	Code: EIA/TIA-222-G	11/1/2017
Site Name: Danielson	Exposure: B	
Height: 155.00 (ft)	Crest Height: 172.00	
Base Elev: 0.000 (ft)	Site Class: C - Very Dense Soil	
Gh: 1.1	Topography: 3	Struct Class: II



Page: 49

Reactions

Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)
1.2D + 1.6W 101 mph Wind	50.1	0.00	53.84	0.00	0.00	4986.14
0.9D + 1.6W 101 mph Wind	50.1	0.00	40.36	0.00	0.00	4941.18
1.2D + 1.0Di + 1.0Wi 50 mph Wind	11.3	0.00	102.56	0.00	0.00	1227.96
1.2D + 1.0E	1.5	0.00	53.93	0.00	0.00	184.46
0.9D + 1.0E	1.5	0.00	40.45	0.00	0.00	182.58
1.0D + 1.0W 60 mph Wind	11.1	0.00	44.94	0.00	0.00	1094.42

Max Stresses

Load Case	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (-) (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Elev (ft)	Stress Ratio
1.2D + 1.6W 101 mph Wind	-53.84	-50.15	0.00	-4986.1	0.00	-4986.1	4048.32	2024.1	8933.65	4411.99	0.00	0.946
0.9D + 1.6W 101 mph Wind	-40.36	-50.12	0.00	-4941.1	0.00	-4941.1	4048.32	2024.1	8933.65	4411.99	0.00	0.935
1.2D + 1.0Di + 1.0Wi 50 mph Wind	-102.5	-11.31	0.00	-1227.9	0.00	-1227.9	4048.32	2024.1	8933.65	4411.99	0.00	0.250
1.2D + 1.0E	-20.17	-1.17	0.00	-37.96	0.00	-37.96	1337.17	668.58	1823.68	900.65	115.00	0.057
0.9D + 1.0E	-15.13	-1.15	0.00	-37.53	0.00	-37.53	1337.17	668.58	1823.68	900.65	115.00	0.053
1.0D + 1.0W 60 mph Wind	-44.94	-11.06	0.00	-1094.4	0.00	-1094.4	4048.32	2024.1	8933.65	4411.99	0.00	0.214

Additional Steel Summary

Elev From (ft)	Elev To (ft)	Member	Intermediate Connectors			Lower Termination				Upper Termination				Max Member			
			VQ/I (lb/in)	Vu (kips)	phi Vn (kips)	MQ/I (kips)	phi Vn (kips)	Num Reqd	Num Actual	MQ/I (kips)	phi Vn (kips)	Num Reqd	Num Actual	Pu (kips)	phi Pn (kips)	phi Tn (kips)	Ratio
0.0	21.0	(3) PLT-6"x1-1/4"(1.25" Hole)	303.1	5.46	37.1	350.1	37.1	10	0	321.2	37.1			350.11	413.6	356.25	0.983
11.5	16.5	(1) PLT-6"x1-1/4"(1.25" Hole)	-261.6	-4.71	37.1	292.0	37.1	8	11	285.3	37.1	8	11	291.95	413.6	356.25	0.820
21.0	41.0	(3) PLT-6"x1-1/4"(1.25" Hole)	318.6	5.73	37.1	321.2	37.1			292.3	37.1			321.23	413.6	356.25	0.902
41.0	58.5	(3) PLT-6"x1-1/4"(1.25" Hole)	352.7	6.35	37.1	292.3	37.1			217.8	37.1	6	11	304.70	413.6	356.25	0.855
58.0	76.0	(3) PLT-5"x1-1/4"(1.25" Hole)	-318.4	-5.73	37.1	202.2	37.1	6	8	204.6	37.1			238.51	344.6	281.25	0.848
76.0	96.0	(3) PLT-4.5"x 1-1/4"(1.25"ho	-340.5	-6.13	37.1	189.9	37.1			158.5	37.1			199.18	310.2	243.75	0.817
96.0	113.5	(3) PLT-3.5x1.25(1.25 Hole)	-351.0	-6.32	37.1	133.1	37.1			103.2	37.1	3	6	133.10	241.2	168.75	0.789



Monopole Mat Foundation Design

Date
10/31/2017

Customer Name:	Sprint Nextel	EIA/TIA Standard:	EIA-222-G
Site Name:	Danielson	Structure Height (Ft.):	155
Site Number:	CT00302-S-SBA	Engineer Name:	Arinyedokia
Engr. Number:	42110	Engineer Login ID:	

Foundation Info Obtained from:

Drawings/Calculations

Structure Type:

Monopole

Analysis or Design?

Analysis



Base Reactions (Factored):

Axial Load (Kips):	53.8	Shear Force (Kips):	50.1
Uplift Force (Kips):	0.0	Moment (Kips-ft):	4986.1

Allowable overstress %: 5.0%

Foundation Geometries:

		Mods required -Yes/No ?:	No
Diameter of Pier (ft.):	7.0	Depth of Base BG (ft.):	6.0
Pier Height A. G. (ft.):	0.00	Thickness of Pad (ft):	3.50
Length of Pad (ft.):	33	Width of Pad (ft.):	33
Final Length of pad (ft)	33.0	Final width of pad (ft):	33.0
Control Value for Cell D18:	0	Control Value for Cell F18:	0



Material Properties and Rebar Info:

Concrete Strength (psi):	3000	Steel Elastic Modulus:	29000	ksi
Vertical bar yield (ksi)	60	Tie steel yield (ksi):	60	
Vertical Rebar Size #:	14	Tie / Stirrup Size #:	4	
Qty. of Vertical Rebars:	25	Tie Spacing (in):	6.0	
Pad Rebar Yield (Ksi):	60	Pad Steel Rebar Size (#):	10	
Concrete Cover (in.):	3	Unit Weight of Concrete:	150.0	pcf
Rebar at the bottom of the concrete pad:				
Qty. of Rebar in Pad (L):	23	Qty. of Rebar in Pad (W):	23	
Rebar at the top of the concrete pad:				
Qty. of Rebar in Pad (L):	23	Qty. of Rebar in Pad (W):	23	

Apply 1.35 factor for e/w Per G: 1.35

Soil Design Parameters:

Soil Unit Weight (pcf):	130.0	Soil Buoyant Weight:	50.0	Pcf
Water Table B.G.S. (ft):	99.0	Unit Weight of Water:	62.4	pcf
Ultimate Bearing Pressure (psf):	32000	Ultimate Skin Friction:	0	Psf
Consider Friction for O.T.M. (Y/N):	No	Consider Friction for bearing (Y/N):	No	
Consider soil hor. resist. for OTM.:	No	Reduction factor on the maximum soil bearing pressure:	1.00	
		Angle from Top of Pad:	30	
		Angle from Bottm of Pad:	25	
		Angle from Bottm of Pad:	25	

Foundation Analysis and Design:

Uplift Strength Reduction Factor:	0.75	Compression Strength Reduction Factor:	0.75
Total Dry Soil Volume (cu. Ft.):	2626.29	Total Dry Soil Weight (Kips):	341.42
Total Buoyant Soil Volume (cu. Ft.):	0.00	Total Buoyant Soil Weight (Kips):	0.00
Total Effective Soil Weight (Kips):	341.42	Weight from the Concrete Block at Top (K):	0.00
Total Dry Concrete Volume (cu. Ft.):	3907.90	Total Dry Concrete Weight (Kips):	586.19
Total Buoyant Concrete Volume (cu. Ft.):	0.00	Total Buoyant Concrete Weight (Kips):	0.00
Total Effective Concrete Weight (Kips):	586.19	Total Vertical Load on Base (Kips):	981.44

Check Soil Capacities:

Calculated Maxium Net Soil Pressure under the base (psf):	1683	<	Allowable Factored Soil Bearing (psf):	24000	0.07	OK!
Allowable Foundation Overturning Resistance (kips-ft.):	14663.3	>	Design Factored Momont (kips-ft):	5287	0.36	OK!
Factor of Safety Against Overturning (O. R. Moment/Design Moment):	2.77					OK!

Load/
Capacity
Ratio

Check the capacities of Reinforcing Concrete:

Strength reduction factor (Flexure and axial tension): 0.90 Strength reduction factor (Shear): 0.75
 Strength reduction factor (Axial compression): 0.65 Wind Load Factor on Concrete Design: 1.00

Load/
Capacity
Ratio

(1) Concrete Pier:

Vertical Steel Rebar Area (sq. in./each):	2.25	Tie / Stirrup Area (sq. in./each):	0.20		
Calculated Moment Capacity (Mn,Kips-Ft):	8511.1	> Design Factored Moment (Mu, Kips-Ft)	5111.4	0.60	OK!
Calculated Shear Capacity (Kips):	724.1	> Design Factored Shear (Kips):	50.1	0.07	OK!
Calculated Tension Capacity (Tn, Kips):	3037.5	> Design Factored Tension (Tu Kips):	0.0	0.00	OK!
Calculated Compression Capacity (Pn, Kips):	7273.8	> Design Factored Axial Load (Pu Kips):	53.8	0.01	OK!
Moment & Axial Strength Combination:	0.60	OK! Check Tie Spacing (Design/Required):		0.5	OK!
Pier Reinforcement Ratio:	0.010	Reinforcement Ratio is satisfied per ACI			

(2).Concrete Pad:

One-Way Design Shear Capacity (L-Direction, Kips):	1248.5	> One-Way Factored Shear (L-D. Kips):	307.9	0.25	OK!
One-Way Design Shear Capacity (W-Direction, Kips):	1248.5	> One-Way Factored Shear (W-D., Kips)	307.9	0.25	OK!
One-Way Design Shear Capacity (Corner-Corner. Kips):	1500.8	> One-Way Factored Shear (C-C, Kips):	308.0	0.21	OK!
Lower Steel Pad Reinforcement Ratio (L-Direct.):	0.0019	OK! Lower Steel Pad Reinf. Ratio (W-Direc	0.0019		
Lower Steel Pad Moment Capacity (L-Direction. Kips-ft):	4930.1	> Moment at Bottom (L-Direct. K-Ft):	1509.0	0.31	OK!
Lower Steel Pad Moment Capacity (W-Direction. Kips-ft):	4930.1	> Moment at Bottom (W-Direct. K-Ft):	1509.0	0.31	OK!
Lower Steel Pad Moment Capacity (Corner-Corner,K-ft):	6943.8	> Moment at Bottom (C-C Dir. K-Ft):	2134.0	0.31	OK!
Upper Steel Pad Reinforcement Ratio (L-Direct.):	0.0019	OK! Upper Steel Reinf. Ratio (W-Direct.):	0.0019		
Upper Steel Pad Moment Capacity (L-Direction. Kips-ft):	4930.1	> Moment at the top (L-Dir Kips-Ft):	166.3	0.03	OK!
Upper Steel Pad Moment Capacity (W-Direction. Kips-ft):	4930.1	> Moment at the top (W-Dir Kips-Ft):	166.3	0.03	OK!
Upper Steel Pad Moment Capacity (Corner-Corner. K-ft):	6943.8	> Moment at the top (C-C Direc. K-Ft):	797.1	0.11	OK!

SPECIAL CONSTRUCTION NOTE:
 SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS.
 * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT.
 * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
 * SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

PROJECT: DO MACRO EQUIPMENT DEPLOYMENT
SITE NAME: DANIELSON
SITE CASCADE: CT23XC407-A
MARKET: NORTHERN CONNECTICUT
SBA SITE ID: CT00302-S/DANIELSON
SITE ADDRESS: 246 EAST FRANKLIN STREET DANIELSON, CT 6239
SITE TYPE: 159' GUYED TOWER




1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 TEL: (800) 357-7641




SBA COMMUNICATIONS CORP.
 134 FLANDERS ROAD, SUITE 125
 WESTBOROUGH, MA 01581
 TEL: (508) 251-0720
 FAX: (508) 251-1755



45 BEECHWOOD DRIVE
 N. ANDOVER, MA 01851
 TEL: (978) 557-5553
 FAX: (978) 336-5586



Sprint



NOTE:

OWNER AND TENANT MAY, FROM TIME TO TIME AT TENANT'S OPTION, REPLACE THIS EXHIBIT WITH AN EXHIBIT SETTING FORTH THE LEGAL DESCRIPTION OF THE SITE, OR WITH ENGINEERED OR AS-BUILT DRAWING DEPICTING THE SITE OR ILLUSTRATING STRUCTURAL MODIFICATIONS OR CONSTRUCTION PLANS OF THE SITE. ANY VISUAL OR TEXTUAL REPRESENTATION OF THE EQUIPMENT LOCATED WITHIN THE SITE CONTAINED IN THESE OTHER DOCUMENTS IS ILLUSTRATIVE ONLY, AND DOES NOT LIMIT THE RIGHTS OF SPRINT AS PROVIDED FOR IN THE AGREEMENT. THE LOCATIONS OF ANY ACCESS AND UTILITY EASEMENTS ARE ILLUSTRATIVE ONLY. ACTUAL LOCATIONS MAY BE DETERMINED BY TENANT AND/OR THE SERVICING UTILITY COMPANY IN COMPLIANCE WITH LOCAL LAWS AND REGULATIONS.

NOTE:

THESE PLANS ARE BASED ON INFORMATION OBTAINED SITE VISIT ON MAY 01, 2014. THE SPRINT CONTRACTOR IS RESPONSIBLE TO VERIFYING ALL ITEMS AND NOTIFYING THE ENGINEER OF RECORD AND DISCREPANCIES.

SITE INFORMATION	AREA MAP	PROJECT DESCRIPTION	DRAWING INDEX																																																																						
<p>PROPERTY OWNER: CHARLES R. HUTCHINS 246 EAST FRANKLIN STREET KILLINGLY, CT 6239</p> <p>TOWER OWNER: SBA PROPERTIES, LLC. 8051 CONGRESS AVENUE BOCA RATON, FL 33487 PHONE: (561)995-7670</p> <p>SBA REGIONAL SITE MANAGER: STEPHEN ROTH PHONE: 860-539-4920 SROth@sbasite.com</p> <p>LATITUDE (NAD83): GOOGLE EARTH 2-C CONFIRMATION 41° 47' 44.93" N 41.795814°</p> <p>LONGITUDE (NAD83): GOOGLE EARTH 2-C CONFIRMATION -71° 52' 13.37" W -71.870381°</p>	<p>LOCATION MAP GOOGLE EARTH 2-C CONFIRMATION</p>	<p>SPRINT EQUIPMENT MODIFICATIONS REQUIRED TO SUPPORT MODERNIZATION OF AN EXISTING WIRELESS COMMUNICATIONS FACILITY AND UTILIZATION OF FCC BROADBAND SPECTRUM LICENSE FOR 2.5GHz FREQUENCY, INCLUDING INSTALLATION OF:</p> <p>GROUND-LEVEL RAN EQUIPMENT, CONSISTING OF: * RETROFIT EXISTING MMBTS CABINET WITH (1) RECTIFIER SHELF, (3) RECTIFIERS, 2.5 RADIO ACCESS NETWORK (RAN) EQUIPMENT & BBU KIT * INSTALL (1) ADDITIONAL BATTERY STRING IN EXISTING BATTERY CABINET</p> <p>TOWER-TOP EQUIPMENT, INCLUDING INSTALLATION OF: * (3) PANEL ANTENNAS * (3) REMOTE RADIO HEADS (RRH) * (1) HYBRID CABLE (AND ASSOCIATED FIBER, DC POWER, COAXIAL CABLE JUMPERS AND ANTENNA REMOTE ELECTRICAL-TILT (RET) CABLE</p> <p>SPECIAL ZONING NOTE: BASED ON INFORMATION PROVIDED BY SPRINT REGULATORY COMPLIANCE PROFESSIONALS AND LEGAL COUNSEL, THIS TELECOMMUNICATIONS EQUIPMENT DEPLOYMENT IS CONSIDERED AN ELIGIBLE FACILITY UNDER THE TAX RELIEF ACT OF 2012, 47 USC 1455(A), AND IS SUBJECT TO AN EXPEDITED ELIGIBLE FACILITIES REQUEST/REVIEW AND ZONING PRE-EMPTION FOR LOCAL DISCRETIONARY PERMITS (VARIANCE, SPECIAL PERMIT, SITE PLAN REVIEW, ADMINISTRATIVE REVIEW).</p>	<table border="1"> <thead> <tr> <th>SHEET NO:</th> <th>SHEET TITLE</th> <th>REV</th> <th>CHK</th> <th>BY</th> </tr> </thead> <tbody> <tr> <td>T-1</td> <td>TITLE SHEET</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>SP-1</td> <td>OUTLINE SPECIFICATIONS</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>SP-2</td> <td>OUTLINE SPECIFICATIONS</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>SP-3</td> <td>OUTLINE SPECIFICATIONS</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>A-1</td> <td>COMPOUND PLAN</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>A-2</td> <td>ELEVATION AND ANTENNA PLANS</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>A-3</td> <td>RF DATA SHEET</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>A-4</td> <td>RAN WIRING DIAGRAM</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>A-5</td> <td>EQUIPMENT DETAILS</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>A-6</td> <td>EQUIPMENT DETAILS</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>S-1</td> <td>STRUCTURAL DETAILS</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>E-1</td> <td>ONE LINE DIAGRAM</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> <tr> <td>E-2</td> <td>GROUNDING DETAILS AND NOTES</td> <td>3</td> <td>BB</td> <td>DJM</td> </tr> </tbody> </table>	SHEET NO:	SHEET TITLE	REV	CHK	BY	T-1	TITLE SHEET	3	BB	DJM	SP-1	OUTLINE SPECIFICATIONS	3	BB	DJM	SP-2	OUTLINE SPECIFICATIONS	3	BB	DJM	SP-3	OUTLINE SPECIFICATIONS	3	BB	DJM	A-1	COMPOUND PLAN	3	BB	DJM	A-2	ELEVATION AND ANTENNA PLANS	3	BB	DJM	A-3	RF DATA SHEET	3	BB	DJM	A-4	RAN WIRING DIAGRAM	3	BB	DJM	A-5	EQUIPMENT DETAILS	3	BB	DJM	A-6	EQUIPMENT DETAILS	3	BB	DJM	S-1	STRUCTURAL DETAILS	3	BB	DJM	E-1	ONE LINE DIAGRAM	3	BB	DJM	E-2	GROUNDING DETAILS AND NOTES	3	BB	DJM
SHEET NO:	SHEET TITLE	REV	CHK	BY																																																																					
T-1	TITLE SHEET	3	BB	DJM																																																																					
SP-1	OUTLINE SPECIFICATIONS	3	BB	DJM																																																																					
SP-2	OUTLINE SPECIFICATIONS	3	BB	DJM																																																																					
SP-3	OUTLINE SPECIFICATIONS	3	BB	DJM																																																																					
A-1	COMPOUND PLAN	3	BB	DJM																																																																					
A-2	ELEVATION AND ANTENNA PLANS	3	BB	DJM																																																																					
A-3	RF DATA SHEET	3	BB	DJM																																																																					
A-4	RAN WIRING DIAGRAM	3	BB	DJM																																																																					
A-5	EQUIPMENT DETAILS	3	BB	DJM																																																																					
A-6	EQUIPMENT DETAILS	3	BB	DJM																																																																					
S-1	STRUCTURAL DETAILS	3	BB	DJM																																																																					
E-1	ONE LINE DIAGRAM	3	BB	DJM																																																																					
E-2	GROUNDING DETAILS AND NOTES	3	BB	DJM																																																																					
<p>COUNTY: WINDHAM</p> <p>POWER COMPANY: CL & P</p> <p>AAV PROVIDER: AT&T</p> <p>SPRINT CONSTRUCTION MANAGER: MICHAEL DELIA PHONE: 781-316-6348 Michael.DeLia@sprint.com</p> <p>EQUIPMENT SUPPLIER: ALCATEL-LUCENT 600 MOUNTAIN AVENUE MURRAY HILL, NJ 07974</p>	<p>LOCATION MAP GOOGLE EARTH 2-C CONFIRMATION</p>	<p>GENERAL NOTES</p> <ol style="list-style-type: none"> THIS IS AN UNMANNED TELECOMMUNICATION FACILITY AND NOT FOR HUMAN HABITATION: - ADA COMPLIANCE NOT REQUIRED. - POTABLE WATER OR SANITARY SERVICE IS NOT REQUIRED. - NO OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES REQUIRED. CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON JOB SITE. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. FAILURE TO NOTIFY THE ARCHITECT/ENGINEER PLACE THE RESPONSIBILITY ON THE CONTRACTOR TO CORRECT THE DISCREPANCIES AT THE CONTRACTOR'S EXPENSE. NEW CONSTRUCTION WILL CONFORM TO ALL APPLICABLE CODES AND ORDINANCES. BUILDING CODE: IBC 2012 W/ 2016 CT STATE BUILDING CODE AMENDMENTS ELECTRICAL CODE: 2014 NATIONAL ELECTRICAL CODE STRUCTURAL CODE: (TIA) 222-G STRUCTURAL STANDARDS FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS. <p>811 Know what's below. Call before you dig. www.CBYD.com</p>	<p>APPROVALS</p> <p>THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.</p> <p>SPRINT: _____ DATE: _____</p> <p>CONSTRUCTION MANAGER: _____ DATE: _____</p> <p>LEASING/SITE ACQUISITION: _____ DATE: _____</p> <p>RF ENGINEER: _____ DATE: _____</p> <p>LANDLORD/TOWER OWNER: _____ DATE: _____</p>																																																																						

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
 CT23XC407-A

SITE NAME:
 DANIELSON

SITE ADDRESS:
 246 EAST FRANKLIN STREET
 DANIELSON, CT 6239

SHEET TITLE

TITLE SHEET
 (DO MACRO)

SHEET NUMBER

T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 **PRECEDENCE:** SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.

1.4 **NATIONALLY RECOGNIZED CODES AND STANDARDS:**

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 2. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY –GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 3. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 4. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 5. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 6. AMERICAN CONCRETE INSTITUTE (ACI)
 - 7. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 8. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 9. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 - 10. PORTLAND CEMENT ASSOCIATION (PCA)
 - 11. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 12. BRICK INDUSTRY ASSOCIATION (BIA)
 - 13. AMERICAN WELDING SOCIETY (AWS)
 - 14. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 15. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 16. DOOR AND HARDWARE INSTITUTE (DHI)
 - 17. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 18. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 **DEFINITIONS:**

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1.6 **SITE FAMILIARITY:** CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.

1.7 **POINT OF CONTACT:** COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.

1.8 **ON-SITE SUPERVISION:** THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.

1.9 **DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE:** THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.

- A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
- B. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.

1.10 **USE OF JOB SITE:** THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

1.11 **UTILITIES SERVICES:** WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:

1.12 **PERMITS / FEES:** WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

1.13 **CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.**

1.14 **METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION:** CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

- A. TOP HAT
- B. HOW TO INSTALL A NEW CABINET
- C. BASE BAND UNIT IN EXISTING UNIT
- D. INSTALLATION OF BATTERIES
- E. INSTALLATION OF HYBRID CABLE
- F. INSTALLATION OF RRH'S
- G. CABLING
- H. SPRINT TS-0200 (CURRENT VERSION) – ANTENNA LINE ACCEPTANCE STANDARDS
- I. SPRINT CELL SITE ENGINEERING NOTICE – EN 2012-001, REV 1.
- J. COMMISSIONING MOPS
- K. SPRINT CELL SITE ENGINEERING NOTICE – EN-2013-002
- L. SPRINT ENGINEERING LETTER – EL-0504
- M. SPRINT ENGINEERING LETTER – EL-0568
- N. SPRINT TECHNICAL SPECIFICATION – TS-0193

1.15 **USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:**

A. CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET ACCESS, EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **TEMPORARY UTILITIES AND FACILITIES:** THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.

3.2 **ACCESS TO WORK:** THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.

3.3 **TESTING; REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS.** SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.

3.4 **DIMENSIONS:** VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 **EXISTING CONDITIONS:** NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **RECEIPT OF MATERIAL AND EQUIPMENT:**

- A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
- B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

3.2 **DELIVERABLES:**

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 **NOTICE TO PROCEED:**

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **FUNCTIONAL REQUIREMENTS:**

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 - 1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
 - 2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
 - 3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
 - 4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
 - 5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
 - 6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
 - 7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
 - 8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
 - 9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
 - 10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
 - 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
 - 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
 - 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
 - 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
 - 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
 - 16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
 - 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
 - 18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
 - 19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
 - 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 **GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:**

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 - 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 - 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 **DELIVERABLES:**

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 - 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 - 2. PROJECT PROGRESS REPORTS.
 - 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
 - 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 - 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01854
TEL: (978) 557-5553
FAX: (978) 336-5586



CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON

SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE
OUTLINE SPECIFICATIONS (DO MACRO)

SHEET NUMBER

SP-1

SECTION 01 400 – SUBMITTALS, TESTS, AND INSPECTIONS

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

1.3 **SUBMITTALS:**

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN.
- C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 **TESTS AND INSPECTIONS:**

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER SPRINT TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING;
 1. AZIMUTH, DOWNTILT, AGL – UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD
 5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
 6. LIEN WAIVERS
 7. FINAL PAYMENT APPLICATION
 8. REQUIRED FINAL CONSTRUCTION PHOTOS
 9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
 10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 **COMMISSIONING:** PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPS

1.6 **INTEGRATION:** PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPS

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **REQUIRED TESTS:**

- A. THIRD PARTY TESTING AGENCY: WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
 1. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
 2. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 **REQUIRED TESTS:**

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
 3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
 7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
 9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 **REQUIRED INSPECTIONS:**

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
 3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
 4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
 6. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS – ANTENNALIGN ALIGNMENT TOOL (AAT)
 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- E. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- F. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.

3.4 **DELIVERABLES:** TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.

- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 3. SITE RESISTANCE TO EARTH TEST.
 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS – PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING – TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 6. SITE LAYOUT – PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 500 – PROJECT REPORTING

PART 1 – GENERAL

1.1 **THE WORK:** THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 **RELATED DOCUMENTS:**

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 **WEEKLY REPORTS:**

A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.

B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 **PROJECT CONFERENCE CALLS:**

A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 **PROJECT TRACKING IN SMS:**

A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

3.4 **ADDITIONAL REPORTING:**

A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 **PROJECT PHOTOGRAPHS:**

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 1. SHELTER AND TOWER OVERVIEW.
 2. TOWER FOUNDATION(S) – FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 5. PHOTOS OF TOWER SECTION STACKING.
 6. CONCRETE TESTING / SAMPLES.
 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 8. BUILDING/WATER TANK FROM ROOF FOR TENANT IMPROVEMENTS OR COMMENTS.
 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 11. COAX CABLE ENTRY INTO SHELTER.
 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 25. ALL BTS GROUND CONNECTIONS.
 26. ALL GROUND TEST WELLS.
 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 30. GPS ANTENNAS.
 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 34. MASTER BUS BAR.
 35. TELCO BOARD AND NIU.
 36. ELECTRICAL DISTRIBUTION WALL.
 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 38. ENTRANCE TO EQUIPMENT ROOM.
 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 40. COAX GROUNDING –TOP AND BOTTOM OF TOWER.
 41. ANTENNA AND MAST GROUNDING.
 42. LANDSCAPING – WHERE APPLICABLE.

3.6 **FINAL PROJECT ACCEPTANCE:** COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

SECTION 07 500 – ROOF CUTTING, PATCHING AND REPAIR

SUMMARY:
THIS SECTION SPECIFIES CUTTING AND PATCHING EXISTING ROOFING SYSTEMS WHERE CONDUIT OR CABLES EXIT THE BUILDING ONTO THE ROOF OR BUILDING-MOUNTED ANTENNAS, AND AS REQUIRED FOR WATERTIGHT PERFORMANCE. ROOFTOP ENTRY OPENINGS IN MEMBRANE ROOFTOPS SHALL BE CONSTRUCTED TO COMPLY WITH LANDLORD, ANY EXISTING WARRANTY, AND LOCAL JURISDICTIONAL STANDARDS.

1.4 **SUBMITTALS:**

- A. **PRE-CONSTRUCTION ROOF PHOTOS:** COMPLETE A ROOF INSPECTION PRIOR TO THE INSTALLATION OF SPRINT EQUIPMENT ON ANY ROOFTOP BUILD. AT A MINIMUM INSPECT AND PHOTOGRAPH (MINIMUM 3 EA.) ALL AREAS IMPACTED BY THE ADDITION OF THE SPRINT EQUIPMENT.
- B. PROVIDE SIMILAR PHOTOGRAPHS SHOWING ROOF CONDITIONS AFTER CONSTRUCTION (MINIMUM 3 EA.)
- C. ROOF INSPECTION PHOTOGRAPHS SHOULD BE UPLOADED WITH CLOSEOUT PHOTOGRAPHS.

SECTION 09 900 – PAINTING

QUALITY ASSURANCE:

- A. COMPLY WITH GOVERNING CODES AND REGULATIONS. PROVIDE PRODUCTS OF ACCEPTABLE MANUFACTURERS WHICH HAVE BEEN IN SATISFACTORY USE IN SIMILAR SERVICE FOR THREE YEARS. USE EXPERIENCED INSTALLERS. DELIVER, HANDLE, AND STORE MATERIALS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
- B. COMPLY WITH ALL ENVIRONMENTAL REGULATIONS FOR VOLATILE ORGANIC COMPOUNDS.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01854
TEL: (978) 557-5553
FAX: (978) 336-5586



CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON

SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE
OUTLINE
SPECIFICATIONS
(DO MACRO)

SHEET NUMBER
SP-2

CONTINUED FROM SP-2:

MATERIALS:

- A. MANUFACTURERS: BENJAMIN MOORE, ICI DEVOE COATINGS, PPG, SHERWIN WILLIAMS OR APPROVED EQUAL. PROVIDE PREMIUM GRADE, PROFESSIONAL-QUALITY PRODUCTS FOR COATING SYSTEMS.

PAINT SCHEDULE:

- A. EXTERIOR ANTENNAE AND ANTENNA MOUNTING HARDWARE: ONE COAT OF PRIMER AND TWO FINISH COATS. PAINT FOR ANTENNAE SHALL BE NON-METALLIC BASED AND CONTAIN NO METALLIC PARTICLES. PROVIDE COLORS AND PATTERNS AS REQUIRED TO MASK APPEARANCE OF ANTENNAE ON ADJACENT BUILDING SURFACES AND AS ACCEPTABLE TO THE OWNER. REFER TO ANTENNA MANUFACTURER'S INSTRUCTIONS WHENEVER POSSIBLE.

- B. ROOF TOP CONSTRUCTION: TOUCH UP – PREPARE SURFACES TO BE REPAIRED. FOLLOW INDUSTRY STANDARDS AND REQUIREMENTS OF OWNER TO MATCH EXISTING COATING AND FINISH.

PAINTING APPLICATION:

1. INSPECT SURFACES, REPORT UNSATISFACTORY CONDITIONS IN WRITING; BEGINNING WORK MEANS ACCEPTANCE OF SUBSTRATE.
2. COMPLY WITH MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS FOR PREPARATION, PRIMING AND COATING WORK. COORDINATE WITH WORK OF OTHER SECTIONS.
3. MATCH APPROVED MOCK-UPS FOR COLOR, TEXTURE, AND PATTERN. RE-COAT OR REMOVE AND REPLACE WORK WHICH DOES NOT MATCH OR SHOWS LOSS OF ADHESION.
4. CLEAN UP, TOUCH UP AND PROTECT WORK.

TOUCHUP PAINTING:

1. GALVANIZING DAMAGE AND ALL BOLTS AND NUTS SHALL BE TOUCHED UP AFTER TOWER ERECTION WITH "GALVANOX," "DRY GALV," OR "ZINC-IT."
2. FIELD TOUCHUP PAINT SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.
3. ALL METAL COMPONENTS SHALL BE HANDLED WITH CARE TO PREVENT DAMAGE TO THE COMPONENTS, THEIR PRESERVATIVE TREATMENT, OR THEIR PROTECTIVE COATINGS.

SECTION 11 700 – ANTENNA ASSEMBLY, REMOTE RADIO HEADS AND CABLE INSTALLATION

SUMMARY:

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRH'S, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

ANTENNAS AND RRH'S:

THE NUMBER AND TYPE OF ANTENNAS AND RRH'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE:

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

JUMPERS AND CONNECTORS:

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRH'S AND ANTENNAS. JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRH'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE. DO NOT USE SUPERFLEX OUTDOORS. JUMPERS SHALL BE FACTORY FABRICATED IN APPROPRIATE LENGTHS WITH A MAXIMUM OF 4 FEET EXCESS PER JUMPER AND HAVE CONNECTORS AT EACH END, MANUFACTURED BY SUPPLIER. IF JUMPERS ARE FIELD FABRICATED, FOLLOW MANUFACTURER'S REQUIREMENTS FOR INSTALLATION OF CONNECTORS

REMOTE ELECTRICAL TILT (RET) CABLES:

MISCELLANEOUS:

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

ANTENNA INSTALLATION:

THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

- A. THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN 1 DEGREE.
- B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

HYBRID CABLES INSTALLATION:

- A. THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- B. THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.
- C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION.
 1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE PERMANENTLY FASTENED TO THE COAX LADDER AT 4'-0" OC USING NON-MAGNETIC STAINLESS STEEL CLIPS.
 2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE MMBTS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES:
 - a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH @ 18" OC. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.
 - b. DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY NELCO PRODUCTS OR EQUAL.
 3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
 4. CABLE INSTALLATION:
 - a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
 - b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS.
 - c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURER'S RECOMMENDED MAXIMUM BEND RADIUS.

5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED ON DRAWINGS.
6. HYBRID CABLE COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 REV 4.
7. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE – EN 2012-001, REV 1

WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND KITS:

- A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.
- B. WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES.
 1. COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING. PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
 2. SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.
 3. 3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
 4. OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

SECTION 11 800 – INSTALLATION OF MULTIMODAL BASE STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

DC CIRCUIT BREAKER LABELING

- A. LABEL CIRCUIT BREAKERS ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE – EN 2012-001, REV 1.

SECTION 11 800 – INSTALLATION OF MULTIMODAL BASE TRANSCIEVER STATIONS (MMBTS) AND RELATED EQUIPMENT

SUMMARY:

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- B. CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

SUPPORTING DEVICES:

- A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
 1. ALLIED TUBE AND CONDUIT
 2. B-LINE SYSTEM
 3. UNISTRUT DIVERSIFIED PRODUCTS
 4. THOMAS & BETTS
- B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:
 1. EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
 2. POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
 3. FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
 4. TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
 5. CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY.
 6. MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL.
 7. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
 8. DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
 9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.

SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH THE FOLLOWING:
- D. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
- E. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE SLABS.

ELECTRICAL IDENTIFICATION:

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET, INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

SECTION 26 200 – ELECTRICAL MATERIALS AND EQUIPMENT

CONDUIT:

- A. RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR ENCASED RUNS IN CONCRETE. RIGID CONDUIT AND FITTINGS SHALL BE STEEL, COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED – SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL.
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- D. EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- E. LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6- FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRE BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

HUBS AND BOXES:

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY O-Z/GEDNEY OR EQUAL.
 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO – CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES OR EQUAL.
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKETED COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- E. MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED EQUAL.

SUPPLEMENTAL GROUNDING SYSTEM

- A. FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM AS INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS AS INDICATED.
- B. SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO OX.
- C. STOLEN GROUND-BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

EXISTING STRUCTURE:

- A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE-ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

CONDUIT AND CONDUCTOR INSTALLATION:

- A. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01851
TEL: (978) 557-5553
FAX: (978) 336-5586

CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF


SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON

SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE
OUTLINE SPECIFICATIONS (DO MACRO)

SHEET NUMBER
SP-3



CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON


SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE

COMPOUND PLAN
(DO MACRO)

SHEET NUMBER

A-1




- 1 A-6 RETROFIT EXISTING MMBTS CABINET WITH (1) RECTIFIER SHELF, (3) RECTIFIERS, 2.5 RADIO ACCESS NETWORK (RAN) EQUIPMENT & BBU KIT
- 2 A-6 INSTALL (1) ADDITIONAL BATTERY STRING IN EXISTING BATTERY CABINET



SOURCE: HDG 05-02-14

RAN EQUIPMENT PHOTO DETAIL 2 A-1
SCALE: N.T.S.

COMPOUND PLAN 1 A-1
SCALE: 3/16"=1'-0"



NOTE:
SPRINT RAD CENTER SHOWN IN RED TEXT BASED ON SBA-PROVIDED COLLOCATION APPLICATION, EQUIPMENT DATABASE, AND STRUCTURAL ANALYSIS. THE SBA-PROVIDED ANTENNA RAD CENTER SHALL SUPERSEDE ANY CONFLICTING INFORMATION DERIVED FROM THE SPRINT NV 2.5 RFDS.

SPECIAL CONSTRUCTION NOTE:
THE SPRINT NETWORK VISION 2.5 GHZ TOWER TOP WORK IS CONTINGENT UPON COMPLETION OF ALL REQUIRED STRUCTURAL MODIFICATIONS, ENGINEERING CONSTRUCTION CONTROL INSPECTIONS, FINAL ENGINEERING AFFIDAVIT, AND ACCEPTANCE/APPROVAL BY SBA COMMUNICATIONS GROUP.

SPECIAL CONSTRUCTION NOTE:
SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS.
 * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT.
 * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
 * SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

NOTE:
EXISTING AZIMUTHS FROM SPRINT SITE AUDIT DATED 01/11/14

STRUCTURAL NOTES:
PRIOR TO COMMENCING CONSTRUCTION, GC SHALL REFER TO MOUNT ANALYSIS PROVIDED BY HDG DATED 1/22/2018 TO DETERMINE IF THERE ANY SUPPLEMENTAL OR SPECIAL INSTALLATION REQUIREMENTS, OR RELOCATION ARRANGEMENTS.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01851
TEL: (978) 557-5553
FAX: (978) 336-5586



CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON



SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE


ELEVATION AND
ANTENNA PLANS
(DO MACRO)

SHEET NUMBER

A-2



EXISTING PARTIAL ELEVATION PHOTO DETAIL
SCALE: N.T.S.




EXISTING ANTENNA PLAN
SCALE: N.T.S.

NOTES:
1) VERIFY PROPOSED AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION

SPECIAL WORK NOTE:
JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA CAN NOT EXCEED 15'. NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY DISCREPANCY.

ANTENNA STATUS LEGEND:


EMPTY	- EMPTY PIPE
(E)	- EXISTING
(P)	- INSTALL
NV	- SPRINT ANTENNA MODEL (APXVSP18-C-A20)
2.5	- SPRINT ANTENNA



PROPOSED ANTENNA PLAN
SCALE: N.T.S.

NOTE:
ROTATE EXISTING RRH COLLAR MOUNT TO ACCOMMODATE NEW PLATFORM REINFORCEMENT KIT INSTALLATION AS NECESSARY

NOTES:
GROUND EQUIPMENT NOT SHOWN FOR CLARITY.





RFDS Sheet

(by SBA Network Services 4/8/14. NOTE: General Contractor/Tower Crew shall verify that the latest RFDS is used for equipment installation.)

General Site Information

Site ID	CT23XC407	Equipment Vendor	ALU
Market	Northern Connecticut	Latitude	41.795830
Region	East	Longitude	-71.870329
MLA	SBA	LL SITE ID	CT00302-S
Structure Type	OTHER		
BTS Type	Outdoor Macro		
Solution ID	Not Available	Siterra SR Equipment Type	Outdoor Macro
		Equipment Vendor	ALU
		Incremental Power Draw Needed by Added Equipment	

Base Equipment

BBU Kit	ALU BBU Kit	Top Hat	None
BBU Kit Qty	1	Top Hat Qty	N/A
Growth Cabinet	None	Top Hat Dimensions (Inches)	N/A
Growth Cabinet Qty	N/A	Top Hat Weight (Lbs.)	N/A
Growth Cabinet Dimensions (Inches)	N/A		
Growth Cabinet Weight (Lbs.)	N/A		

RF Path Information

RRH	TD-RRH8x20-25	
RRH Qty	3	
RRH Dimensions (Inches)	26.1" x 18.6" x 6.7"	(** A&E SEE DETAIL 2/A-5)
RRH Weight (Lbs.)	70.0	
RRH Mount Weight (Lbs.)	10	
Power and Fiber Cable	ALU Fiber only	
Cable Qty	1	
Weight per Foot (Lbs.)	0.242	
Diameter (Inches)	0.730	
Hybrid Cable Length (Feet)	177	(Estimated by Sprint as Antenna CL plus 20%; DO NOT BOM using this length.)
Coax Jumper	Coax Jumper. Mfg TBD.	
Coax Jumper Qty	27	
Coax Jumper Length (Feet)	8	
Coax Jumper Weight (Lbs.)	1.7	
Coax Jumper Diameter (Inches)	0.5	
AISG Cable	Commscope ATCB-B01-006	
AISG Cable Qty	3	
AISG Diameter (Inches)	0.315	
AISG Cable Length (Feet)	8	
Weight of Entire AISG Cable (Lbs.)	1.3	

Antenna Sector Information

	Sector 1	Sector 2	Sector 3
Antenna Make/Model	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20	RFS APXV9TM14-ALU-I20
Antenna Qty	1	1	1
Antenna Dimensions (Inches)	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3	56.3 x 12.6 x 6.3
Antenna Weight (Lbs.)	55.1	55.1	55.1
Antenna Mounting Kit Weight (Lbs.)	11.5	11.5	11.5
CL Height (Feet)	147.0	147.0	147.0
Antenna Azimuth (Degrees)	0	120	240
Antenna Mechanical Downtilt (Degrees)	0	0	0
Antenna Etilt (Degrees)	-2	-2	-2
RF Filter Make/Model	N/A	N/A	N/A

Comments

RFDS generated 4/8/14 by SBA Network Services from Sprint Plan of Record dated 4/2/14.

Comments in Red Text provided by A&E Vendor.

IMPORTANT CONSTRUCTION NOTE: General Contractor/Tower Crew shall verify that the latest RFDS is used for equipment installation.

* Note: Antenna Rad Center based on SBA-Provided Collocation Application, Equipment Database, and Structural Analysis. The SBA-Provided Antenna Rad Center shall supersede any conflicting information derived from the Sprint NV 2.5 Database.

** Note: Sprint CM shall confirm Hybrid Cable Length, Coax Jumper Length and AISG Cable Length before preparing BOM. A&E Recommended Hybrid Cable Length based on NV 2.5 Equipment Audit plus 20 Feet for (2) 10-foot coils at each end of the fiber trunk.

SPRINT CONSTRUCTION STANDARDS:

GENERAL CONTRACTOR SHALL ADHERE TO THE FOLLOWING SPRINT CONSTRUCTION STANDARDS.

- CONSTRUCTION STANDARDS: INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES - (CURRENT VERSION), INCLUDING EXHIBITS A-M.
- CONSTRUCTION SPECIFICATIONS: CONSTRUCTION STANDARDS EXHIBIT A - STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES (CURRENT VERSION).
- GROUNDING STANDARDS: EXTERIOR GROUNDING SYSTEM DESIGN. GROUNDING STANDARDS (SUPPLEMENT): ANTI-THEFT UPDATE TO SPRINT GROUNDING 082412 AND SPRINT ENGINEERING LETTER EL-0504 DATED 04.20.12.
- WEATHER PROOFING STANDARDS: EXCERPT FROM CONSTRUCTION STANDARDS EXHIBIT A, SECTION 3.6 WEATHERPROOFING CONNECTORS AND GROUND KITS.
- COLOR CODING: SPRINT NEXTEL ANT AND LINE COLOR CODING PER SPRINT TS-0200 CURRENT VERSION.
- GENERAL CONTRACTOR TO FIELD VERIFY AZIMUTH AND CL HEIGHT AND MECHANICAL DOWNTILT. IF DIFFERENT THAN CALLED OUT IN RFDS, HALT ANTENNA WORK FOR ONE HOUR, CALL SPRINT RF ENGINEER (OR MANAGER IF RF ENGINEER DOES NOT ANSWER, BUT STILL LEAVE A MESSAGE TO RF ENGINEER) USING SPRINT-PROVIDED CONTACT INFORMATION FOR FURTHER INSTRUCTIONS. IF SPRINT DOES NOT RESPOND WITHIN ONE HOUR, PLACE 2.5G ANTENNA AT SAME CL HEIGHT AS 1.9G ANTENNA AND EMAIL CORRECT CL HEIGHT AND AZIMUTH TO SPRINT RF ENGINEER. UPDATE AS-BUILD DRAWING WITH CORRECT CL HEIGHT. ALSO EMAIL CORRECT 1900 MHZ AND 800 MHZ ANTENNA CL HEIGHT, AZIMUTH AND MECHANICAL DOWNTILT TO RF ENGINEER.
- AISG TESTS TO VERIFY OPERATION IS TO BE PERFORMED AFTER FINAL INSTALLATION OF ANTENNAS AND AISG CABLES HAVE BEEN CONNECTED. VERIFY OPERATION OF ALL EXISTING SPRINT AISG EQUIPMENT INCLUDING 800MHZ, 1.9GHZ AND 2.5G. TEST INCLUDE COMPLETE DOWNTILT, AZIMUTH (IF APPLICABLE) AND BEAMWIDTH SWINGS (IF APPLICABLE). DOCUMENT AISG TEST RESULTS IN COAX SWEEP TEST SPREADSHEET.
- GENERAL CONTRACTOR MUST INSURE THAT NO OBJECT IS LOCATED IN FRONT OF ANTENNA. THIS MEANS NO OBJECT IS TO BE LOCATED 45 DEGREES LEFT AND RIGHT OF FRONT OF ANTENNA OR 7 DEGREES UP AND DOWN FROM CENTER OF ANTENNA. IF THIS IS NOT POSSIBLE, CONTACT RF ENGINEER FOR FURTHER INSTRUCTION. IN ADDITION, 2.5G ANTENNA IS NOT TO BE PLACED IN FRONT OF ANY OTHER ANTENNA USING THE SAME 45 DEGREE RULE. THIS INCLUDES SPRINT AND NON-SPRINT ANTENNAS.
- GENERAL CONTRACTOR IS REQUIRED TO USE A DIGITAL ALIGNMENT TOOL TO SET AZIMUTH, ROLL AND DOWNTILT. AZIMUTH ACCURACY IS TO BE WITHIN 1 DEGREES. DOWNTILT AND ROLL (LEFT TO RIGHT TILT) IS TO BE WITHIN 0.1 DEGREES. IF FOR SOME REASON THIS ACCURACY CANNOT BE ACHIEVED, UPDATE AS-BUILT DRAWINGS AND EMAIL SPRINT RF ENGINEER WITH AS-BUILT SETTINGS. USE 3Z RF ALIGNMENT TOOL OR EQUIVALENT TOOL. [HTTP://WWW.3ZTELECOM.COM/ANTENNA-ALIGNMENT-TOOL/](http://www.3ztelecom.com/antenna-alignment-tool/).




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01851
TEL: (978) 557-5553
FAX: (978) 336-5586



CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON

SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE

RF DATA SHEET
(DO MACRO)

SHEET NUMBER


A-3

RF DATA SHEET

SCALE: N.T.S.


1

A-3




CABLE COLOR CODING DIAGRAM

SCALE: N.T.S.



ALU 2.5 ALU SCENARIO 1

SCALE: N.T.S.




RAN WIRING DIAGRAM: ALU EQUIPMENT

SCALE: N.T.S.

NOTE:

GENERAL CONTRACTOR/TOWER CREW SHALL VERIFY THAT THE LATEST RF DATA SHEET IS USED FOR EQUIPMENT INSTALLATION.



RFS 2.5 ALU SCENARIO 1

SCALE: N.T.S.

DC POWER INSTALLATION NOTE (FIBER-ONLY SCENARIO):

USE SPACE DC CABLES COILED UP AT TOWER TOP NV ARRAY TO POWER UP 2.5 RRH. INSIDE EXISTING FIBER DISTRIBUTION BOX, TIE SPARE DC CONDUCTORS INTO EXISTING DC BREAKER PANEL PER APPROVED DC WIRING CONNECTIVITY OPTION (BASED ON NV HYBRIFLEX CABLE LENGTH). CONSULT WITH SPRINT CM TO DETERMINE APPROPRIATE DC CONNECTIVITY OPTION, PLUMBING DIAGRAM AND DC BREAKER SIZE.




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01851
TEL: (978) 557-5553
FAX: (978) 336-5586



CONSTRUCTION/DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON

SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE

RAN WIRING
DIAGRAM
(DO MACRO)

SHEET NUMBER

A-4

HYBRID CABLE DC CONDUCTOR SIZE GUIDELINE					
MANUF:	RFS	CABLE	LENGTH	DC CONDUCTOR	CABLE DIAMETER
(*)		FIBER ONLY	VARIABLES	USE NV	HYBRIFLEX 5/8"
		HYBRIFLEX	<200'	8 AWG	1-1/4"
		HYBRIFLEX	225-300'	6 AWG	1-1/4"
		HYBRIFLEX	325-375'	4 AWG	1-1/4"

RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
(*)	MN: HB058-M12-200F	200 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
MN: HB114-08U3M12-200F	200 ft	
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-275F	275 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft

RFS HYBRIFLEX JUMPER CABLE SCHEDULE


Fiber Only (*)	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY.		
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY.		
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY.		
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
SPECIAL INSTALLATION NOTE: JUMPERS FROM 2.5 RRH TO 2.5 ANTENNA SHALL NOT EXCEED 15'. NOTIFY SPRINT CM OF ANY DISCREPANCY.		

* NOTE: SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.


2.5 HYBRID CABLE X-SECTION AND DATA

SCALE: N.T.S.


1
A-5




4 AWG




6 AWG & 8 AWG



FIBER ONLY




PLAN VIEW



2.5 ANTENNA SPECIFICATIONS


SCALE: N.T.S.

2
A-5



SIDE VIEW

FRONT VIEW



PLAN VIEW

2.5 RRH'S

SCALE: N.T.S.

3
A-5




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01851
TEL: (978) 557-5553
FAX: (978) 336-5586



CONSTRUCTION/DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMP AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON



SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239

SHEET TITLE

EQUIPMENT
DETAILS
(DO MACRO)

SHEET NUMBER

A-5



FRONT VIEW

EXISTING MMBTS OUTDOOR CABINET WITH 2.5 EQUIPMENT

SCALE: N.T.S.

1
A-6

SUFFICIENT SPACE IN EXISTING BBU CABINET FOR ADDITIONAL BATTERY STRINGS. INSTALL (1) ADDITIONAL BATTERY STRING IN EXISTING BATTERY CABINET.



SOURCE: HDG 05-02-14

FRONT VIEW

EXISTING 2.5 POWER BBU CABINET

SCALE: N.T.S.

2
A-6

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS			
REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF


SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON

SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239


SHEET TITLE
EQUIPMENT
DETAILS
(DO MACRO)

SHEET NUMBER
A-6



SECTION A-A

NOTE: ONE SECTOR SHOWN FOR CLARITY



2.5 ANTENNA AND RRH MOUNTING DETAIL

SCALE: N.T.S.

SPECIAL CONSTRUCTION NOTE:
 SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
 * COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY TOWER OWNER).
 * COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
 * GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.
 * SBA COMMUNICATIONS CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

STRUCTURAL NOTES:
 PRIOR TO COMMENCING CONSTRUCTION, GC SHALL REFER TO MOUNT ANALYSIS PROVIDED BY HDG DATED 1/22/2018 TO DETERMINE IF THERE ANY SUPPLEMENTAL OR SPECIAL INSTALLATION REQUIREMENTS, OR RELOCATION ARRANGEMENTS.

SPECIAL CONSTRUCTION NOTE:
 THE SPRINT NETWORK VISION 2.5 GHZ TOWER TOP WORK IS CONTINGENT UPON COMPLETION OF ALL REQUIRED STRUCTURAL MODIFICATIONS, ENGINEERING CONSTRUCTION CONTROL INSPECTIONS, FINAL ENGINEERING AFFIDAVIT, AND ACCEPTANCE/APPROVAL BY SBA COMMUNICATIONS GROUP.

INSTALLATION NOTES:

- CONTRACTOR TO ENSURE THAT RRH MOUNTING DOES NOT INTERFERE WITH CLIMBING LADDER/PEGS, CABLE CLIMB, OR COAX PORTS. MONOPOLE: COLLAR-MOUNT RRH CLUSTER SHALL PROVIDE AN OPENING BETWEEN ADJACENT RRH AT LEAST 30" WIDE CENTERED ON THE EXISTING SAFETY-CLIMB AND 30" DEEP FROM THE FACE OF THE POLE. SELF-SUPPORT: RRH LEG-MOUNT OR FACE-MOUNT SHALL PROVIDE AN UNOBSTRUCTED VERTICAL CLIMBING PASSAGE AT LEAST 30" WIDE AND 30" DEEP CENTERED ON THE LEG WITH THE CLIMBING LADDER/PEGS.
- CONTRACTOR TO VERIFY DIAMETER OF EXISTING MONOPOLE BEFORE ORDERING PARTS.
- CONTRACTOR TO VERIFY IN FIELD SIZE OF EXISTING MOUNTING PIPE TO BE 2-1/2" STD (2.88 O.D.) PIPE MAST (6'-0" LONG).
- VERIFY EXACT RRH AND ANTENNA MODEL & AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION.
- ROTATE EXISTING ANTENNA FRAME AS NEEDED TO ACCOMMODATE INSTALL ANTENNAS.
- RRH PLACEMENT FOR REFERENCE ONLY. CONTRACTOR SHALL PLACE RRH IN CORRECT ORDER MATCHING INSTALL ANTENNA PLACEMENT AND ENSURE THAT THERE IS ENOUGH CLEARANCE FOR RRHS TO BE PLACED ON THE INSIDE ON THE ANTENNA FRAME.
- INSTALL EQUIPMENT TO BE MOUNTED PER MANUFACTURERS SPECIFICATIONS.




2.5 ANTENNA AND RRH PHOTO DETAIL AND EQUIPMENT SCHEMATIC

SCALE: N.T.S.

HANDRAIL REINFORCEMENT KIT DETAIL

SCALE: N.T.S.



PLATFORM REINFORCEMENT KIT DETAIL

SCALE: N.T.S.




1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
 134 FLANDERS ROAD, SUITE 125
 WESTBOROUGH, MA 01581
 TEL: (508) 251-0720
 FAX: (508) 251-1755



45 BEECHWOOD DRIVE
 N. ANDOVER, MA 01851
 TEL: (978) 557-5553
 FAX: (978) 336-5586



CONSTRUCTION/DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF

SITE NUMBER:
 CT23XC407-A


SITE NAME:
 DANIELSON

SITE ADDRESS:
 246 EAST FRANKLIN STREET
 DANIELSON, CT 6239

SHEET TITLE
 STRUCTURAL
 DETAILS
 (DO MACRO)

SHEET NUMBER

S-1



TYPICAL POWER AND GROUNDING ONE LINE DIAGRAMS
 SCALE: N.T.S.

- ELECTRICAL NOTES**
- ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
 - THE ELECTRICAL CONTRACTOR SHALL COORDINATE ALL CONDUIT ROUTING WITH LOCAL UTILITY COMPANIES AND SPRINT CONSTRUCTION MANAGER.
 - ALL CONDUITS ROUTED BELOW GRADE SHALL TRANSITION TO RIGID GALVANIZED ELBOWS WITH RIGID GALVANIZED STEEL CONDUIT ABOVE GRADE.
 - ALL METAL CONDUITS SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
 - GENERAL CONTRACTOR SHALL PROVIDE ALL DIRECT BURIED CONDUITS WITH PLASTIC WARNING TAPE IDENTIFYING CONTENTS. TAPE COLORS SHALL BE ORANGE FOR TELEPHONE AND RED FOR ELECTRIC.
 - ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
 - THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIALS DESCRIBED BY DRAWINGS AND SPECIFICATIONS INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM.
 - GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND IS RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS.
 - ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
 - BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
 - ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THIN INSULATION.
 - RUN ELECTRICAL CONDUIT OR CABLE BETWEEN ELECTRICAL UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE PPC AS INDICATED ON THIS DRAWING. PROVIDE FULL LENGTH PULL ROPE. COORDINATE INSTALLATION WITH UTILITY COMPANY.
 - RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND BTS CABINET AS INDICATED ON THIS DRAWING PROVIDE FULL LENGTH PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT MEASURING TAPE AT EACH END.
 - FIBER OPTIC CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 770—OPTICAL FIBER CABLES AND RACEWAYS.
 - COMMUNICATIONS CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 800—COMMUNICATIONS SYSTEMS.




1 INTERNATIONAL BLVD, SUITE 800
 MAHWAH, NJ 07495
 TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
 134 FLANDERS ROAD, SUITE 125
 WESTBOROUGH, MA 01581
 TEL: (508) 251-0720
 FAX: (508) 251-1755



45 BEECHWOOD DRIVE
 N. ANDOVER, MA 01851
 TEL: (978) 557-5553
 FAX: (978) 336-5586



CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF


SITE NUMBER:
 CT23XC407-A

SITE NAME:
 DANIELSON

SITE ADDRESS:
 246 EAST FRANKLIN STREET
 DANIELSON, CT 6239

SHEET TITLE
 ONE LINE DIAGRAM
 (DO MACRO)

SHEET NUMBER
 E-1




EXISTING PPC BREAKER PANEL
 SCALE: N.T.S.

SYMBOL LEGEND

- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- CABLE GROUNDING KIT

UNLESS NOTED OTHERWISE, ALL BONDING CONDUCTORS ARE 2# SOLID TINNED BCW.



NOTE: HYBRIFLEX (FIBER & POWER) AND HYBRIFLEX (FIBER-ONLY) SHOWN. REFER TO RAN EQUIPMENT RFDS FOR SITE-SPECIFIC SCENARIO.

2.5 RAN EQUIPMENT GROUNDING SCHEMATIC 1
SCALE: N.T.S. E-2

- PROTECTIVE GROUNDING SYSTEMS GENERAL NOTES:**
- GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250—GROUNDING AND BONDING.
 - GROUNDING SHALL BE IN ACCORDANCE WITH SPRINT SSEO DOCUMENTS 3.018.02.004 "BONDING, GROUNDING AND TRANSIENT PROTECTION FOR CELL SITES" AND 3.018.10.002 "SITE RESISTANCE TO EARTH TESTING".
 - PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
 - GROUND CONNECTIONS: CLEAN SURFACES THOROUGHLY BEFORE APPLYING GROUND LUGS OR CLAMPS. IF SURFACE IS COATED, REMOVE THE COATING, APPLY A NON-CORROSIVE APPROVED COMPOUND TO CLEAN SURFACE AND INSTALL LUGS OR CLAMPS. WHERE GALVANIZING IS REMOVED FROM METAL, IT SHALL BE PAINTED OR TOUCHED UP WITH "GALVAMOX" OR EQUAL.
 - ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
 - ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
 - ALL GROUND WIRES SHALL BE #2 SOLID TINNED BCW UNLESS NOTED OTHERWISE.
 - PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
 - GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
 - EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 SOLID TINNED BCW EQUIPMENT CABINETS WALL HAVE (2) CONNECTIONS.
 - GROUND HYBRIFLEX SHIELD AT TOP, BOTTOM AND AT TRANSITION TO HYBRIFLEX JUMPER CABLES AT EQUIPMENT CABINET ENTRANCE USING MANUFACTURER'S GUIDELINES. WHEN HYBRIFLEX CABLE EXCEEDS 200', GROUND AT INTERVALS NOT EXCEEDING 100'.
 - THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
 - EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL OTHERWISE, THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES, LONG BARREL LUGS OR DOUBLE CRIMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH AN ANTI-OXIDANT (THOMAS BETTS KOPR-SHILD) BEFORE MAKING THE CRIMP CONNECTIONS THE CONTRACTOR SHALL FOLLOW MANUFACTURER'S RECOMMENDED TORQUES ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS.
 - AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING, CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF-TAPPING SCREWS.
 - THE MASTER GROUND BAR (MGB) SHALL BE MADE OF BARE 1/4"x2" COPPER (FOR OUTDOOR APPLICATIONS IT SHALL BE TINNED COPPER) AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE SECURING THE MGB SHALL ELECTRICAL INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENED.
 - ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
 - ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH SPRINT CONSTRUCTION MANAGER.
 - FOR NEW OR REPAIRED GROUNDING EQUIPMENT. REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):
-ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED: 08-24-12 (OR CURRENT VERSION)
-SPRINT ENGINEERING LETTER EL-0504 DATED: 04-20-12 (OR CURRENT VERSION)




1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641



SBA COMMUNICATIONS CORP.
134 FLANDERS ROAD, SUITE 125
WESTBOROUGH, MA 01581
TEL: (508) 251-0720
FAX: (508) 251-1755



45 BEECHWOOD DRIVE
N. ANDOVER, MA 01850
TEL: (978) 557-5553
FAX: (978) 336-5586



CONSTRUCTION DRAWINGS ARE VALID FOR SIX MONTHS AFTER ENGINEER OF RECORD'S STAMPED AND SIGNED SUBMITTAL DATE LISTED HEREIN

CHECKED BY: BB

APPROVED BY: DJC

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
3	01/26/18	ISSUED FOR CONSTRUCTION	DJM
2	05/16/14	ISSUED FOR CONSTRUCTION	SF
1	05/08/14	ISSUED FOR CONSTRUCTION	SF
0	05/02/14	ISSUED FOR CONSTRUCTION	SF


SITE NUMBER:
CT23XC407-A

SITE NAME:
DANIELSON

SITE ADDRESS:
246 EAST FRANKLIN STREET
DANIELSON, CT 6239


SHEET TITLE
GROUNDING DETAILS AND NOTES (DO MACRO)

SHEET NUMBER
E-2



- NOTES**
- APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
 - IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR 2
SCALE: N.T.S. E-2



TWO HOLE LUG 3
SCALE: N.T.S. E-2