PROJECT NARRATIVE

May 10, 2022

Melanie A. Bachman
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: Request of DISH Wireless LLC for an Order to Approve the Shared Use of an Existing Tower
8 Old Route 79, Madison, CT 06443
Latitude: 41'17'7.92" / Longitude: -72'36'4.83"

Dear Ms. Bachman:

Pursuant to Connecticut General Statutes ("C.G.S.") §16-50aa, as amended, DISH Wireless LLC ("DISH") hereby requests an order from the Connecticut Siting Council ("Council") to approve the shared use by DISH of an existing telecommunication tower at 8 Old Route 79 in Madison (the "Property"). The existing 148-foot monopole is owned by American Tower Corporation ("ATC"). The underlying property is owned by CK Builders LLC. DISH requests that the Council find that the proposed shared use of the ATC tower satisfies the criteria of C.G.S. §16-50aa and issue an order approving the proposed shared use. A copy of this filing is being sent to Peggy Lyons, First Selectwoman for the Town of Madison, Vincent Garofalo, Town of Madison Building Official and CK Builders LLC as the property owner.

Background

This facility his tower was approved as a monopole by the Town of Madison's Inland Wetlands Enforcement Officer on February 2, 1999. A copy of the approval letter is included in this filing. The existing ATC facility consists of a 148-foot monopole tower located within an existing leased area. Antennas are maintained by Others between the 152-foot level and 156-foot level. Sprint / Nextel currently maintains antennas at the 149-foot level and 97.5-foot level and 73-foot level. Verizon Wireless currently maintains antennas at the 140-foot level. AT&T Mobility currently maintains antennas at the 132-foot level. T-Mobile currently maintains antennas at the 120-foot level. Metro PCS currently maintains antennas at the 86-foot level. Equipment associated with these antennas are located at various positions within the tower and compound.

DISH is licensed by the Federal Communications Commission ("FCC") to provide wireless services throughout the State of Connecticut. DISH and ATC have agreed to the proposed shared use of the 8 Old Route 79 tower pursuant to mutually acceptable terms and conditions. Likewise, DISH and ATC have agreed to the proposed installation of equipment cabinets on the ground within the existing compound. ATC has authorized DISH to apply for all necessary permits and approvals that may be required to share the existing tower.
(See attached Letter of Authorization)

DISH proposes to install three (3) antennas, (1) Tower platform mount, (6) Remote radio units at the 110-foot level along with, (1) over voltage protection device (OVP) and (1) Hybrid cable. DISH will install an equipment cabinet on a 5'x7' equipment platform. DISH's Construction Drawings provide project specifications for all proposed site improvement locations.
The construction drawings also include specifications for DISH's proposed antenna and groundwork.

C.G.S. § 16-50aa(c)(1) provides that, upon written request for approval of a proposed shared use, "if the Council finds that the proposed shared use of the facility is technically, legally, environmentally and economically feasible and meets public safety concerns, the council shall issue an order approving such a shared use." DISH respectfully submits that the shared use of the tower satisfies these criteria.

A. Technical Feasibility. The existing ATC tower is structurally capable of supporting DISH's proposed improvements. The proposed shared use of this tower is, therefore, technically feasible. A Feasibility Structural Analysis Report ("Structural Report") prepared for this project confirms that this tower can support DISH's proposed loading. A copy of the Structural Report has been included in this application.

B. Legal Feasibility. Under C.G.S. § 16-50aa, the Council has been authorized to issue order approving the shared use of an existing tower such as the ATC tower. This authority complements the Council's prior-existing authority under C.G.S. § 16-50p to issue orders approving the construction of new towers that are subject to the Council's jurisdiction. In addition, § 16-50x(a) directs the Council to "give such consideration to the other state laws and municipal regulations as it shall deem appropriate" in ruling on requests for the shared use of existing tower facilities. Under the statutory authority vested in the Council, an order by the Council approving the requested shared use would permit the Applicant to obtain a building permit for the proposed installations.

C. Environmental Feasibility. The proposed shared use of the ATC tower would have a minimal environmental effect for the following reasons:

1. The proposed installation will have no visual impact on the area of the tower. DISH's equipment cabinet would be installed within the existing facility compound. DISH's shared use of this tower therefore will not cause any significant change or alteration in the physical or environmental characteristics of the existing site.

2. Operation of DISH's antennas at this site would not exceed the RF emissions standard adopted by the Federal Communications Commission ("FCC"). Included in the EME report of this filing are the approximation tables that demonstrate that DISH's proposed facility will operate well within the FCC RF emissions safety standards.

3. Under ordinary operating conditions, the proposed installation would not require the use of any water or sanitary facilities and would not generate air emissions or discharges to water bodies or sanitary facilities. After construction is complete the proposed installations would not generate any increased traffic to the ATC facility other than periodic maintenance. The proposed shared use of the ATC tower, would, therefore, have a minimal environmental effect, and is environmentally feasible.

D. **Economic Feasibility**. As previously mentioned, DISH has entered into an agreement with ATC for the shared use of the existing facility subject to mutually agreeable terms. The proposed tower sharing is, therefore, economically feasible.

E. **Public Safety Concerns**. As discussed above, the tower is structurally capable of supporting DISH's full array of three (3) antennas, (1) Tower platform mount, (6) Remote radio units, (1) over voltage protection device (OVP) and (1) Hybrid cable and all related equipment. DISH is not aware of any public safety concerns relative to the proposed sharing of the existing ATC tower.

Conclusion

For the reasons discussed above, the proposed shared use of the existing ATC tower at 8 Old Route 79 satisfies the criteria stated in C.G.S. §16-50aa and advances the Council's goal of preventing the unnecessary proliferation of towers in Connecticut. The Applicant, therefore, respectfully requests that the Council issue an order approving the prosed shared use.

Sincerely,

David Hoogasian

David Hoogasian
Project Manager

LETTER OF AUTHORIZATION

AMERICAN TOWER®
CORPORATION

LETTER OF AUTHORIZATION

Licensee: DISH WIRELESS L.L.C.
ATC Site No/ Name / 302540/ MADISON CT 6/ 13702514
Address: 8 OLD 79 MADISON, CT 06443-2685

I, Margaret Robinson, Senior Counsel for American Tower*, operator of the tower facility located at the address identified above (the "Tower Facility"), do hereby authorize **DISH WIRELESS L.L.C** its successors and assigns, and/or its agents **NETWORK BUILDING + CONSULTING** to act as American Tower's non-exclusive agent for the sole purpose of filing and consummating any land-use or building permit application(s) as may be required by the applicable permitting authorities for Licensee's telecommunications' installation.

We understand that this application may be denied, modified or approved with conditions. The above authorization is limited to the acceptance by Licensee only of conditions related to Licensee's installation and any such conditions of approval or modifications will be Licensee's sole responsibility.

Signature:

Print Name: Margaret Robinson
Senior Counsel
American Tower*

NOTARY BLOCK

Commonwealth of MASSACHUSETTS
County of Middlesex

This instrument was acknowledged before me by Margaret Robinson, Senior Counsel for American Tower*, personally known to me (or proved to me on the basis of satisfactory evidence) to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same.

WITNESS my hand and official seal, this 28th day of April 2022.

NOTARY SEAL

ANGELICA R. LEMOS-BARTHELEMY
Notary Public
COMMONWEALTH OF MASSACHUSETTS
My Commission Expires On
March 25, 2027

Notary Public
My Commission Expires: March 25, 2027

***American Tower includes all affiliates and subsidiaries of American Tower Corporation.**

ORIGINAL FACILITY APPROVAL

8 CAMPUS DRIVE
MADISON, CONNECTICUT 06443-2563
(203) 245-5632
FAX (203) 245-5613

TOW

L

Z 594 530 629

US Postal Service
Receipt for Certified Mail
No Insurance Coverage Provided.
Do not use for International Mail (See reverse)

Sent to: SMART SMR/Nextel Communications
Street & Number: 100 Corporate Place
Post Office, State, & ZIP Code: Rocky Hill, CT 06067

Postage	$ .33
Certified Fee	1.40
Special Delivery Fee	
Restricted Delivery Fee	
Return Receipt Showing to Whom & Date Delivered	
Return Receipt Showing to Whom, Date, & Address of Delivery	
TOTAL Postage & Fees	$ 1.73
Postmark or Date	FEB 2 1999 06443

PS Form 3800, April 1995

February 2, 1999

SMART SMR of New York, Inc.
Nextel Communications
100 Corporate Place
Rocky Hill, CT 06067

Re: Application 99-4: 8 OLD ROUTE 79. Request for Regulated Activity Permit to allow replacement of tower with monopole encroaching into the wetlands buffer.

Gentlemen:

At their regular meeting on February 1, 1999, the Madison Inland Wetlands Agency approved the application above referenced as presented at the meeting and as shown on the ***Site Plan Modification Plan*** and ***Site Plan Modification Plan Details,*** sheets C-1 and C-2, dated 11-09-98.

The duration of this permit is for two years, unless extended by the Agency, and all activities must be completed within this time.

Very truly yours,

Robert E Kuchta

Robert E. Kuchta
Inland Wetlands Enforcement Officer

For GLENN W. FALK
Chairman, Madison Inland Wetlands Agency

:drk

Copy to URS Greiner Woodward Clyde

ENGINEERING DRAWINGS

DISH WIRELESS, L.L.C. SITE ID:

BOHVN00146A

DISH WIRELESS, L.L.C. SITE ADDRESS:

8 OLD 79
MADISON, CT 06443-2685

BIRD WATCH SITE:
PLEASE CONTACT BIRD.WATCH@AMERICANTOWER.COM OR AMERICAN TOWER NOC AT 877-518-6937 FOR ASSISTANCE

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

TOWER SCOPE OF WORK:
- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
- INSTALL (1) PROPOSED ANTENNA PLATFORM MOUNT
- INSTALL PROPOSED JUMPERS
- INSTALL (6) PROPOSED RRHs (2 PER SECTOR)
- INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
- INSTALL (1) PROPOSED HYBRID CABLE
- REMOVE EXISTING EQUIPMENT AT 112'

GROUND SCOPE OF WORK:
- INSTALL (1) PROPOSED METAL PLATFORM
- INSTALL (1) PROPOSED HANDHOLE
- INSTALL (1) PROPOSED PPC CABINET
- INSTALL (1) PROPOSED EQUIPMENT CABINET
- INSTALL (1) PROPOSED POWER CONDUIT
- INSTALL (1) PROPOSED TELCO CONDUIT
- INSTALL (1) PROPOSED TELCO-FIBER BOX
- INSTALL (1) PROPOSED GPS UNIT
- INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
- INSTALL (1) PROPOSED CIENA BOX (IF REQUIRED)
- INSTALL (1) PROPOSED METER SOCKET
- REMOVE EXISTING EQUIPMENT AND PAD IN 5'X7' LEASE AREA

SITE INFORMATION

PROPERTY OWNER:	CK BUILDERS LLC
ADDRESS:	8 OLD ROUTE 79 MADISON, CT 06443
TOWER TYPE:	MONOPOLE
TOWER CO SITE ID:	302540
TOWER APP NUMBER:	13702514
COUNTY:	NEW HAVEN
LATITUDE (NAD 83):	41° 17' 7.92" N 41.28553333
LONGITUDE (NAD 83):	72° 36' 4.83" W -72.60134167
ZONING JURISDICTION:	CONNECTICUT SITING COUNCIL
ZONING DISTRICT:	R-1
PARCEL NUMBER:	104171
OCCUPANCY GROUP:	U
CONSTRUCTION TYPE:	II-B
POWER COMPANY:	EVERSOURCE
TELEPHONE COMPANY:	FRONTIER COMMUNICATIONS

PROJECT DIRECTORY

APPLICANT:	DISH WIRELESS, L.L.C. 5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120 (303) 706-5008
TOWER OWNER:	AMERICAN TOWER 10 PRESIDENTIAL WAY WOBURN, MA 01801
ENGINEER:	NB+C ENGINEERING SERVICES, LLC 8601 SIX FORKS ROAD, SUITE 540 RALEIGH, NC 27615
SITE ACQUISITION:	APRIL PARROTT APRIL.PARROTT@DISH.COM
CONSTRUCTION MANAGER:	JAVIER SOTO JAVIER.SOTO@DISH.COM
RF ENGINEER:	SYED ZAIDI SYED.ZAIDI@DISH.COM

CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

SITE PHOTO

DIRECTIONS

FROM NEW LONDON - TAKE I95 SOUTH TO EXIT 61 . TAKE LEFT AT OFF RAMP AND LEFT AT FIRST SET OF LIGHTS.

FROM NEW LONDON - TAKE I95 SOUTH TO EXIT 61 . TAKE LEFT AT OFF RAMP AND LEFT AT FIRST SET OF LIGHTS.

VICINITY MAP



NO SCALE

SHEET INDEX

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
RF-2	RF PLUMBING DIAGRAM
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

UNDERGROUND SERVICE ALERT CBYD 811
UTILITY NOTIFICATION CENTER OF CONNECTICUT
(800) 922-4455
WWW.CBYD.COM
CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION

811

GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

THE PROJECT DEPICTED IN THESE PLANS QUALIFIES AS AN ELIGIBLE FACILITIES REQUEST ENTITLED TO EXPEDITED REVIEW UNDER 47 U.S.C. § 1455(A) AS A MODIFICATION OF AN EXISTING WIRELESS TOWER THAT INVOLVES THE COLLOCATION, REMOVAL, AND/OR REPLACEMENT OF TRANSMISSION EQUIPMENT THAT IS NOT A SUBSTANTIAL CHANGE UNDER CFR § 1.61000 (B)(7).

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C™
TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT
JOSEPH CASIMIR KOTOWSKI
PEN.0028997
LICENSED
PROFESSIONAL ENGINEER
10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
TITLE SHEET

SHEET NUMBER
T-1

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.



OVERALL SITE PLAN

6' 4' 2' 0 5' 10'
3/16"=1'-0"

1

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. CONTRACTOR SHALL MAINTAIN A 10'-0" MINIMUM SEPARATION BETWEEN THE PROPOSED GPS UNIT, TRANSMITTING ANTENNAS AND EXISTING GPS UNITS.
3. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.



ENLARGED SITE PLAN

12" 6" 0 1' 2' 3' 4' 5' 6' 7'
3/8"=1'-0"

2

NOTES

1. THE SURVEY PROVIDED ON THIS SHEET IS PROVIDED FOR REFERENCE ONLY, THE UTILITY ROUTE AND EXISTING EASEMENTS MUST BE VERIFIED PRIOR TO CONSTRUCTION.



EXISTING SURVEY (BY OTHERS)

NO SCALE

3

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C
TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT
PEN.0028997
LICENSED PROFESSIONAL ENGINEER
10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
OVERALL AND ENLARGED SITE PLAN

SHEET NUMBER
A-1

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.



PROPOSED SOUTH ELEVATION

8' 4' 0 8' 16'
1/8"=1'-0"

1



ANTENNA LAYOUT

12" 6" 0 1' 2' 3'
3/4"=1'-0"

2

SECTOR	POSITION	ANTENNA						TRANSMISSION CABLE
		EXISTING OR PROPOSED	MANUFACTURER – MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZIMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA – MX08FRO665-21	5G	72.0" x 20.0"	0°	110'-0"	(1) HIGH-CAPACITY HYBRID CABLE (143' LONG)
BETA	B1	PROPOSED	JMA – MX08FRO665-21	5G	72.0" x 20.0"	120°	110'-0"	
GAMMA	C1	PROPOSED	JMA – MX08FRO665-21	5G	72.0" x 20.0"	240°	110'-0"	

SECTOR	POSITION	RRH	
		MANUFACTURER – MODEL NUMBER	TECHNOLOGY
ALPHA	A1	FUJITSU – TA08025-B604	N29,N71
	A1	FUJITSU – TA08025-B605	N66,N70
BETA	B1	FUJITSU – TA08025-B604	N29,N71
	B1	FUJITSU – TA08025-B605	N66,N70
GAMMA	C1	FUJITSU – TA08025-B604	N29,N71
	C1	FUJITSU – TA08025-B605	N66,N70

SECTOR	POSITION	OVP	
		MANUFACTURER – MODEL NUMBER	TECHNOLOGY
ALPHA	N/A	RAYCAP – RDIDC-9181-PF-48	N29,N66, N70,N71

NOTES

1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS.
2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.

ANTENNA SCHEDULE

NO SCALE

3

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C
TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT
JOSEPH ANDREW KOTOWSKI
PEN.0023997
LICENSED PROFESSIONAL ENGINEER
10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
ELEVATION, ANTENNA LAYOUT AND SCHEDULE

SHEET NUMBER
A-2



PLATFORM EQUIPMENT PLAN

12" 9" 6" 3" 0 1' 2"
1"=1'-0"

1

COMMSCOPE MTC4045LP 5X7 PLATFORM	
DIMENSIONS (HxWxD)	16"x84"x60"
TOTAL WEIGHT	423 LBS

NOTE:
GC TO PROVIDE EXTENDED THREAD FOR PLATFORM IF REQUIRED HEIGHT EXCEEDS 17"

NOTE:
PLATFORM MUST BE LEVEL WITHIN 1 DEGREE



PLATFORM DETAIL

NO SCALE

2

KENWOOD T1701KT5-5S H-FRAME	
UNISTRUT/SUPPORT RAIL	5
WEIGHT/ VOLUME	173.6 LBS



H-FRAME DETAIL

NO SCALE

3

NOT USED

NO SCALE

4

NOTES

1. CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
2. WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH WIRELESS, L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
3. EQUIPMENT CABINET OMITTED FOR CLARITY



FRONT ELEVATION



BACK ELEVATION

H-FRAME EQUIPMENT ELEVATION

12" 9" 6" 3" 0 1' 2"
1"=1'-0"

5

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT
PEN.0028997
LICENSED PROFESSIONAL ENGINEER
10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
EQUIPMENT PLATFORM AND H-FRAME DETAILS

SHEET NUMBER
A-3

CHARLES INDUSTRY HEX CUBE–PM639155N4

DIMENSIONS (HxWxD):	74"x32"x32"
POWER PLANT:	–48VDC ABB/600W
TOTAL WEIGHT (EMPTY)	408 LBS



PLAN



SIDE BACK SIDE FRONT

CABINET DETAIL | NO SCALE | 1

RAYCAP RDIAC–6512–P–240–MTS POWER & TELCO PROTECTION CABINET

DIMENSIONS (HxWxD)	40"x20"x10"
WEIGHT/ VOLUME	124 LBS
MANUAL TRANSFER SWITCH	200A
LOAD CENTER	30 POSITION
MAIN BREAKER	200A, 65kA AIC
GENERATOR RECEPTACLE	CAMLOCK
NEMA RATING	3R POWDER COATED ALUMINUM
SURGE PROTECTION DEVICE	UL 1449 4TH EDITION LISTED



PLAN SIDE FRONT

POWER PROTECTION CABINET (PPC) DETAIL | NO SCALE | 2

SQUARE D SAFETY SWITCH D324NRB

ENCLOSURE DIM (HxWxD)	29.25"x17.25"x8.25"
TOTAL WEIGHT (EMPTY)	45.33 LBS
MAX VOLTAGE/AMPS/WATT	240V/200A/48000W
ENCLOSURE RATING	OUTDOOR NEMA 3R

PLAN



SIDE BACK FRONT

SAFETY SWITCH | NO SCALE | 3

EATON METER SOCKET UNRRS213BEUSE

METER SOCKET TYPE	RING
ENCLOSURE DIM (HxWxD)	16"x12"x6"
MAIN AMPERE RATING	200A
WEIGHT	18 LBS



PLAN



SIDE BACK FRONT

METER SOCKET DETAIL | NO SCALE | 4

CIENA 3931 SERVICE DELIVERY SWITCH

DIMENSIONS (HxWxD)	17.0"x16.8"x7.0" 431x427x178mm
WEIGHT	28.6 LBS/13.0 KG
POWER INPUT	60W MAX

PLAN



FRONT SIDE BACK

CIENA DETAIL | NO SCALE | 5

CHARLES FIBER TELCO ENCLOSURE CUBE–MP1818WB–A

ENCLOSURE DIM (HxWxD)	18.0"x18.0"x9.25"
NEMA RATING	4X
THERMAL	SEALED
MOUNTING BACKBOARD	WOOD

PLAN

SIDE BACK FRONT

FIBER TELCO ENCLOSURE DETAIL | NO SCALE | 6

NOT USED | NO SCALE | 7

NOT USED | NO SCALE | 8



HYBRID CABLE RUN | NO SCALE | 9

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT · BRIAN KOTTENSTETTE · PEN.0028997 · LICENSED PROFESSIONAL ENGINEER

10/21/21

A&E PROJECT NUMBER
302540–13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443–2685

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-4

GPS DETAIL

NO SCALE | 1

PCTEL GPSGL-TMG-SPI-40NCB	
DIMENSIONS (DIAxH) MM/INCH	81x184mm 3.2"x7.25"
WEIGHT W/ACCESSORIES	075 lbs
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1590 ± 30MHz



BACK



TOP

SIDE

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE | 2



CABLES UNLIMITED HYBRID CABLE MINIMUM BEND RADIUSES

NO SCALE | 3



CU12PSM6P4XXX
(4 AWG CONDUCTORS)



CU12PSM9P6XXX
(6 AWG CONDUCTORS)



CU12PSM9P8XXX
(8 AWG CONDUCTORS)

NOT USED

NO SCALE | 4

NOT USED

NO SCALE | 5

NOT USED

NO SCALE | 6

NOT USED

NO SCALE | 7

NOT USED

NO SCALE | 8

NOT USED

NO SCALE | 9

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C
TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION



10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5

FUJITSU DUAL BAND TA08025-B604

DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"
WEIGHT	63.9 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V



PLAN



BACK SIDE FRONT

RRH DETAIL | NO SCALE | 1

FUJITSU TRIPLE BAND TA08025-B605

DIMENSIONS (HxWxD)	14.9"x15.7"x9"
WEIGHT	74.95 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V



PLAN



BACK SIDE FRONT

RRH DETAIL | NO SCALE | 2

SABRE DOUBLE Z-BRACKET G10123155

DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"





NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT

RRH MOUNT DETAIL | NO SCALE | 3

JMA WIRELESS MX08FRO665-21 ANTENNA

DIMENSIONS (HxWxD)	72.0"x20.0"x8.0"
TOTAL WEIGHT	64.5 LB
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE

PLAN



BACK SIDE FRONT

ANTENNA DETAIL | NO SCALE | 4

NOT USED | NO SCALE | 5

JMA ANTENNA MOUNT BRACKET #91900318

TOTAL WEIGHT (WITH BRACKETS)	18 lbs (8.18 Kg)
POLE DIAMETER RANGE	2.5" TO 4.5"

NOTE:
KIT #91900318: TOP AND BOTTOM BRACKETS FOR 4-,6-, AND 8-FOOT ANTENNAS

ANTENNA BRACKET NOT PART OF KIT

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT



ANTENNA BRACKET DETAIL | NO SCALE | 6

RAYCAP RDIDC-9181-PF-48 DC SURGE PROTECTION (OVP)

DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS

PLAN



SIDE BACK FRONT

SURGE SUPPRESSION DETAIL (OVP) | NO SCALE | 7

COMMSCOPE XP-2040 CROSSOVER PLATE

DIMENSIONS (HxW)	10"x12"
WEIGHT	11.023 LBS



RRH/OVP MOUNT DETAIL | NO SCALE | 8

COMMSCOPE MC-PK8-DSH

FACE WIDTH	96"
WEIGHT	1373.08 lbs
NOTE: 15" TO 38" O.D.	

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT





ANTENNA PLATFORM DETAIL | NO SCALE | 9

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT
PEN.0028997
LICENSED PROFESSIONAL ENGINEER
10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-6



UTILITY ROUTE PLAN

6' 4' 2' 0 5' 10'

3/16"=1'-0"

1

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND −48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY −48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH−IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST−CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS−BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. ALL TRENCHES IN COMPOUND TO BE HAND DUG

ELECTRICAL NOTES

NO SCALE

2

NOTES

1. THE SURVEY PROVIDED ON THIS SHEET IS PROVIDED FOR REFERENCE ONLY. THE UTILITY ROUTE AND EXISTING EASEMENTS MUST BE VERIFIED PRIOR TO CONSTRUCTION.



EXISTING SURVEY (BY OTHERS)

NO SCALE

3

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT · JOSEPH A. ROTANDO · PEN.0028997 · LICENSED PROFESSIONAL ENGINEER

10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
ELECTRICAL/FIBER ROUTE PLAN AND NOTES

SHEET NUMBER
E-1



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL) | NO SCALE | 1

TRENCHING NOTES

1. CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
2. TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
3. ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



TYPICAL UNDERGROUND TRENCH DETAIL | NO SCALE | 2



DARK TELCO BOX – INTERIOR WIRING LAYOUT | NO SCALE | 3

NOT USED | NO SCALE | 4

NOT USED | NO SCALE | 5

NOT USED | NO SCALE | 6

NOT USED | NO SCALE | 7

NOT USED | NO SCALE | 8

NOT USED | NO SCALE | 9

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
ELECTRICAL DETAILS

SHEET NUMBER
E-2



NOTE:
BRANCH CIRCUIT WIRING SUPPLYING RECTIFIERS ARE TO BE RATED UL1015, 105'C, 600V, AND PVC INSULATED, IN THE SIZES SHOWN IN THE ONE-LINE DIAGRAM. CONTRACTOR MAY SUBSTITUTE UL1015 WIRE FOR THWN-2 FOR CONVENIENCE OUTLET BRANCH CIRCUIT.

BREAKERS REQUIRED:
(4) 30A, 2P BREAKER – SQUARE D P/N:QO230
(1) 15A, 1P BREAKER – SQUARE D P/N:QO115

PPC ONE-LINE DIAGRAM — NO SCALE — 1

PROPOSED CHARLES PANEL SCHEDULE

LOAD SERVED	VOLT AMPS (WATTS) L1	VOLT AMPS (WATTS) L2	TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS) L1	VOLT AMPS (WATTS) L2	LOAD SERVED
PPC GFCI OUTLET	180		15A	1	A	2	30A	2880		ABB/GE INFINITY RECTIFIER 1
CHARLES GFCI OUTLET		180	15A	3	B	4			2880	
-SPACE-				5	A	6	30A	2880		ABB/GE INFINITY RECTIFIER 2
-SPACE-				7	B	8			2880	
-SPACE-				9	A	10	30A	2880		ABB/GE INFINITY RECTIFIER 3
-SPACE-				11	B	12			2880	
-SPACE-				13	A	14	30A	2880		ABB/GE INFINITY RECTIFIER 4
-SPACE-				15	B	16			2880	
-SPACE-				17	A	18				-SPACE-
-SPACE-				19	B	20				-SPACE-
-SPACE-				21	A	22				-SPACE-
-SPACE-				23	B	24				-SPACE-
VOLTAGE AMPS	180	180						11520	11520	
200A MCB, 1ϕ, 24 SPACE, 120/240V			L1		L2					
MB RATING: 65,000 AIC			11700		11700		VOLTAGE AMPS			
			98		98		AMPS			
			98				MAX AMPS			
			123				MAX 125%			

PANEL SCHEDULE — NO SCALE — 2

NOT USED — NO SCALE — 3

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION



10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE

SHEET NUMBER
E-3



TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE | 1

NOTES

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE | 2

- EXOTHERMIC CONNECTION
- MECHANICAL CONNECTION
- GROUND BUS BAR
- GROUND ROD
- TEST GROUND ROD WITH INSPECTION SLEEVE
- #2 AWG STRANDED & INSULATED
- #2 AWG SOLID COPPER TINNED
- BUSS BAR INSULATOR

GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH WIRELESS, L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

(A) EXTERIOR GROUND RING: #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.

(B) TOWER GROUND RING: THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.

(C) INTERIOR GROUND RING: #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.

(D) BOND TO INTERIOR GROUND RING: #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.

(E) GROUND ROD: UL LISTED COPPER CLAD STEEL. MINIMUM 5/8" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.

(F) CELL REFERENCE GROUND BAR: POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.

(G) HATCH PLATE GROUND BAR: BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.

(H) EXTERIOR CABLE ENTRY PORT GROUND BARS: LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.

(J) TELCO GROUND BAR: BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.

(K) FRAME BONDING: THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.

(L) INTERIOR UNIT BONDS: METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.

(M) FENCE AND GATE GROUNDING: METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.

(N) EXTERIOR UNIT BONDS: METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE

(P) ICE BRIDGE SUPPORTS: EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.

(Q) DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR

(R) TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR.

REFER TO DISH WIRELESS, L.L.C. GROUNDING NOTES.

GROUNDING KEY NOTES

NO SCALE | 3

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION



10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
GROUNDING PLANS AND NOTES

SHEET NUMBER
G-1

NOTES

EQUIPMENT CABINET OMITTED FOR CLARITY



H-FRAME GROUNDING DETAIL | NO SCALE | 1

NOTES

CABLE GROUNDING NOT REQUIRED WHEN ANTENNA IS LESS THAN 10' FROM CABINET



TYPICAL GPS UNIT GROUNDING | NO SCALE | 2



OUTDOOR CABINET GROUNDING | NO SCALE | 3



TRANSITIONING GROUND DETAIL | NO SCALE | 4



TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE | NO SCALE | 5



TYPICAL GROUND RING TRENCH | NO SCALE | 6

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT · BRIAN K. O'NEIL · PEN.0028997 · LICENSED PROFESSIONAL ENGINEER

10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-2

1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.
6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.
8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).

TYPICAL GROUNDING NOTES | NO SCALE | 1



TYPICAL EXTERIOR TWO HOLE LUG | NO SCALE | 2



TYPICAL INTERIOR TWO HOLE LUG | NO SCALE | 3



LUG DETAIL | NO SCALE | 4

NOT USED | NO SCALE | 5

NOT USED | NO SCALE | 6

NOT USED | NO SCALE | 7

NOT USED | NO SCALE | 8

NOT USED | NO SCALE | 9

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C
TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION



10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-3

RF JUMPER COLOR CODING

3/4" TAPE WIDTHS WITH 3/4" SPACING

LOW-BAND RRH –
(600MHz N71 BASEBAND) +
(850MHz N26 BAND) +
(700MHz N29 BAND) – OPTIONAL PER MARKET

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)



MID-BAND RRH –
(AWS BANDS N66+N70)

ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)



HYBRID/DISCREET CABLES

INCLUDE SECTOR BANDS BEING SUPPORTED
ALONG WITH FREQUENCY BANDS

EXAMPLE 1 – HYBRID, OR DISCREET, SUPPORTS
ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS

EXAMPLE 2 – HYBRID, OR DISCREET, SUPPORTS
CBRS ONLY, ALL SECTORS



FIBER JUMPERS TO RRHs

LOW-BAND RRH FIBER CABLES HAVE SECTOR
STRIPE ONLY



POWER CABLES TO RRHs

LOW-BAND RRH POWER CABLES HAVE SECTOR
STRIPE ONLY



RET MOTORS AT ANTENNAS



MICROWAVE RADIO LINKS

LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP WITH
THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE.
ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH
ADDITIONAL MW RADIO.

MICROWAVE CABLES WILL REQUIRE P-TOUCH
LABELS INSIDE THE CABINET TO IDENTIFY THE
LOCAL AND REMOTE SITE ID'S



RF CABLE COLOR CODES	NO SCALE	1

LOW BANDS (N71+N26)
OPTIONAL – (N29)
ORANGE

AWS
(N66+N70+H-BLOCK)
PURPLE

CBRS TECH
(3 GHz)
YELLOW

NEGATIVE SLANT PORT
ON ANT/RRH
WHITE

ALPHA SECTOR
RED

BETA SECTOR
BLUE

GAMMA SECTOR
GREEN

COLOR IDENTIFIER	NO SCALE	2

NOT USED	NO SCALE	3

NOT USED	NO SCALE	4

dish wireless.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION



10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
RF
CABLE COLOR CODES

SHEET NUMBER
RF-1



Fiber Patch Panel

Bottom Row	Pair 1	Pair 2	Pair 3	Pair 10	Open	Open
Middle Row	Pair 4	Pair 5	Pair 6	Pair 11	Open	Open
Top Row	Pair 7	Pair 8	Pair 9	Pair 12	Open	Open

Bottom OVP Layout

Circuit 1	Alpha Low Band
Circuit 2	Beta Low Band
Circuit 3	Gamma Low Band
Circuit 4	Alpha Mid Band
Circuit 5	Beta Mid Band
Circuit 6	Gamma Mid Band
Circuit 7	Alpha CBRS
Circuit 8	Beta CBRS
Circuit 9	Gamma CBRS
Circuit 10	Open
Circuit 11	Open
Circuit 12	Open



5G plumbing diagram JMA MX08FRO665-20
2-2-2(LB+MB)

CSR NCS540

Port	Interface	Description
0	Gi0/0/0/0	SiteBoss
1	Gi0/0/0/1	CBRS - Alpha
2	Gi0/0/0/2	CBRS - Beta
3	Gi0/0/0/3	CBRS - Gamma
4	Te0/0/0/4	Fujitsu Low Band RU - Alpha
5	Te0/0/0/5	Fujitsu Mid-Band RU - Alpha
6	Te0/0/0/6	Fujitsu Low-Band RU - Beta
7	Te0/0/0/7	Fujitsu Mid-Band RU - Beta
8	Te0/0/0/8	Fujitsu Low-Band RU - Gamma
9	Te0/0/0/9	Fujitsu Mid Band RU - Gamma
10	Te0/0/0/10	Fixed Wifi
11	Te0/0/0/11	Fixed Wifi
12	Te0/0/0/12	Fixed Wifi
13	Te0/0/0/13	Fixed Wifi
14	Te0/0/0/14	CBRS1
15	Te0/0/0/15	CBRS2
16	Te0/0/0/16	CBRS3
17	Gi0/0/0/17	SM1 - BMC
18	Gi0/0/0/18	SM2 - BMC
19	Te0/0/0/19	SM1 - Data 1
20	Te0/0/0/20	SM1 - Data 2
21	Te0/0/0/21	SM2 - Data 1
22	Te0/0/0/22	SM2 - Data 2
23	Te0/0/0/23	Reserved Uplink (EDC, LDC)
24	Te0/0/0/24	Blank/Future
25	Te0/0/0/25	Blank/Future
26	Te0/0/0/26	Fiber NIL
27	Te0/0/0/27	Fiber NIL
28	Te0/0/0/28	Blank/Future
29	Te0/0/0/29	Blank/Future



PLUMBING DIAGRAM

NO SCALE

1

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT LICENSED PROFESSIONAL ENGINEER PEN.0028997

10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
PLUMBING DIAGRAM

SHEET NUMBER
RF-2

LEGEND

EXOTHERMIC CONNECTION	
MECHANICAL CONNECTION	
BUSS BAR INSULATOR	
CHEMICAL ELECTROLYTIC GROUNDING SYSTEM	
TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM	T
EXOTHERMIC WITH INSPECTION SLEEVE	
GROUNDING BAR	
GROUND ROD	
TEST GROUND ROD WITH INSPECTION SLEEVE	T
SINGLE POLE SWITCH	$
DUPLEX RECEPTACLE	
DUPLEX GFCI RECEPTACLE	GFCI
FLUORESCENT LIGHTING FIXTURE (2) TWO LAMPS 48–T8	F
SMOKE DETECTION (DC)	SD
EMERGENCY LIGHTING (DC)	
SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW LED–1–25A400/51K–SR4–120–PE–DDBTXD	
CHAIN LINK FENCE	x x x x
WOOD/WROUGHT IRON FENCE	
WALL STRUCTURE	
LEASE AREA	
PROPERTY LINE (PL)	
SETBACKS	
ICE BRIDGE	
CABLE TRAY	
WATER LINE	W W W W W
UNDERGROUND POWER	UGP UGP UGP UGP UGP
UNDERGROUND TELCO	UGT UGT UGT UGT UGT
OVERHEAD POWER	OHP OHP OHP OHP
OVERHEAD TELCO	OHT OHT OHT OHT
UNDERGROUND TELCO/POWER	UGT/P UGT/P UGT/P UGT/P
ABOVE GROUND POWER	AGP AGP AGP AGP AGP
ABOVE GROUND TELCO	AGT AGT AGT AGT AGT
ABOVE GROUND TELCO/POWER	AGT/P AGT/P AGT/P AGT/P
WORKPOINT	W.P.
SECTION REFERENCE	XX / X–X
DETAIL REFERENCE	XX / X–X

ABBREVIATIONS

AB	ANCHOR BOLT
ABV	ABOVE
AC	ALTERNATING CURRENT
ADDL	ADDITIONAL
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AGL	ABOVE GROUND LEVEL
AIC	AMPERAGE INTERRUPTION CAPACITY
ALUM	ALUMINUM
ALT	ALTERNATE
ANT	ANTENNA
APPROX	APPROXIMATE
ARCH	ARCHITECTURAL
ATS	AUTOMATIC TRANSFER SWITCH
AWG	AMERICAN WIRE GAUGE
BATT	BATTERY
BLDG	BUILDING
BLK	BLOCK
BLKG	BLOCKING
BM	BEAM
BTC	BARE TINNED COPPER CONDUCTOR
BOF	BOTTOM OF FOOTING
CAB	CABINET
CANT	CANTILEVERED
CHG	CHARGING
CLG	CEILING
CLR	CLEAR
COL	COLUMN
COMM	COMMON
CONC	CONCRETE
CONSTR	CONSTRUCTION
DBL	DOUBLE
DC	DIRECT CURRENT
DEPT	DEPARTMENT
DF	DOUGLAS FIR
DIA	DIAMETER
DIAG	DIAGONAL
DIM	DIMENSION
DWG	DRAWING
DWL	DOWEL
EA	EACH
EC	ELECTRICAL CONDUCTOR
EL.	ELEVATION
ELEC	ELECTRICAL
EMT	ELECTRICAL METALLIC TUBING
ENG	ENGINEER
EQ	EQUAL
EXP	EXPANSION
EXT	EXTERIOR
EW	EACH WAY
FAB	FABRICATION
FF	FINISH FLOOR
FG	FINISH GRADE
FIF	FACILITY INTERFACE FRAME
FIN	FINISH(ED)
FLR	FLOOR
FDN	FOUNDATION
FOC	FACE OF CONCRETE
FOM	FACE OF MASONRY
FOS	FACE OF STUD
FOW	FACE OF WALL
FS	FINISH SURFACE
FT	FOOT
FTG	FOOTING
GA	GAUGE
GEN	GENERATOR
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GLB	GLUE LAMINATED BEAM
GLV	GALVANIZED
GPS	GLOBAL POSITIONING SYSTEM
GND	GROUND
GSM	GLOBAL SYSTEM FOR MOBILE
HDG	HOT DIPPED GALVANIZED
HDR	HEADER
HGR	HANGER
HVAC	HEAT/VENTILATION/AIR CONDITIONING
HT	HEIGHT
IGR	INTERIOR GROUND RING
IN	INCH
INT	INTERIOR
LB(S)	POUND(S)
LF	LINEAR FEET
LTE	LONG TERM EVOLUTION
MAS	MASONRY
MAX	MAXIMUM
MB	MACHINE BOLT
MECH	MECHANICAL
MFR	MANUFACTURER
MGB	MASTER GROUND BAR
MIN	MINIMUM
MISC	MISCELLANEOUS
MTL	METAL
MTS	MANUAL TRANSFER SWITCH
MW	MICROWAVE
NEC	NATIONAL ELECTRIC CODE
NM	NEWTON METERS
NO.	NUMBER
#	NUMBER
NTS	NOT TO SCALE
OC	ON–CENTER
OSHA	OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
OPNG	OPENING
P/C	PRECAST CONCRETE
PCS	PERSONAL COMMUNICATION SERVICES
PCU	PRIMARY CONTROL UNIT
PRC	PRIMARY RADIO CABINET
PP	POLARIZING PRESERVING
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESSURE TREATED
PWR	POWER CABINET
QTY	QUANTITY
RAD	RADIUS
RECT	RECTIFIER
REF	REFERENCE
REINF	REINFORCEMENT
REQ'D	REQUIRED
RET	REMOTE ELECTRIC TILT
RF	RADIO FREQUENCY
RMC	RIGID METALLIC CONDUIT
RRH	REMOTE RADIO HEAD
RRU	REMOTE RADIO UNIT
RWY	RACEWAY
SCH	SCHEDULE
SHT	SHEET
SIAD	SMART INTEGRATED ACCESS DEVICE
SIM	SIMILAR
SPEC	SPECIFICATION
SQ	SQUARE
SS	STAINLESS STEEL
STD	STANDARD
STL	STEEL
TEMP	TEMPORARY
THK	THICKNESS
TMA	TOWER MOUNTED AMPLIFIER
TN	TOE NAIL
TOA	TOP OF ANTENNA
TOC	TOP OF CURB
TOF	TOP OF FOUNDATION
TOP	TOP OF PLATE (PARAPET)
TOS	TOP OF STEEL
TOW	TOP OF WALL
TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSION
TYP	TYPICAL
UG	UNDERGROUND
UL	UNDERWRITERS LABORATORY
UNO	UNLESS NOTED OTHERWISE
UMTS	UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
UPS	UNITERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
VIF	VERIFIED IN FIELD
W	WIDE
W/	WITH
WD	WOOD
WP	WEATHERPROOF
WT	WEIGHT

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.

NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT PROFESSIONAL ENGINEER LICENSED PEN.0028997

10/21/21

A&E PROJECT NUMBER

302540–13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION

BOHVN00146A
8 OLD 79
MADISON, CT 06443–2685

SHEET TITLE

LEGEND AND ABBREVIATIONS

SHEET NUMBER

GN-1

SITE ACTIVITY REQUIREMENTS:

1. NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH WIRELESS, L.L.C. AND TOWER OWNER NOC & THE DISH WIRELESS, L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.

2. "LOOK UP" – DISH WIRELESS, L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:

THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH WIRELESS, L.L.C. AND DISH WIRELESS, L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.

3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.

4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH WIRELESS, L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).

5. ALL SITE WORK TO COMPLY WITH DISH WIRELESS, L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH WIRELESS, L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."

6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH WIRELESS, L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.

7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.

8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.

9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.

10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.

11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.

12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.

13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH WIRELESS, L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.

14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.

15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.

16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.

17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.

18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.

19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.

20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.

21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.

22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:

CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION

CARRIER:DISH WIRELESS, L.L.C.

TOWER OWNER:TOWER OWNER

2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.

3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.

4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.

5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.

6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.

7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.

8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.

9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.

10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.

11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.

12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH WIRELESS, L.L.C. AND TOWER OWNER

13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.

14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.

dish wireless

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT PEN.0028997 LICENSED PROFESSIONAL ENGINEER
10/21/21

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-2

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.

2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.

3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF PLACEMENT.

4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.

5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:

#4 BARS AND SMALLER 40 ksi

#5 BARS AND LARGER 60 ksi

6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:

- CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
- CONCRETE EXPOSED TO EARTH OR WEATHER:
- #6 BARS AND LARGER 2"
- #5 BARS AND SMALLER 1-1/2"
- CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
- SLAB AND WALLS 3/4"
- BEAMS AND COLUMNS 1-1/2"

7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.

2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.

3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.

4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.

4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.

4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.

5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.

6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).

7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.

8. TIE WRAPS ARE NOT ALLOWED.

9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.

10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.

11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.

12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.

13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).

14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.

15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.

17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.

18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.

19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.

20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.

21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).

22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).

23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.

24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.

25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.

26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.

27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH WIRELESS, L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.

28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.

29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH WIRELESS, L.L.C.".

30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.
NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

10/21/21

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-3

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.

2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.

3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.

4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.

5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.

6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.

7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.

8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.

9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.

10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.

11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.

12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.

13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.

14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.

15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.

16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.

17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.

18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.

19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.

20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).

21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.

STRUCTURAL STEEL NOTES:

1. STRUCTURAL STEEL SHALL CONFORM TO THE LATEST EDITION OF THE AISC "SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS."

2. STRUCTURAL STEEL ROLLED SHAPES, PLATES AND BARS SHALL CONFORM TO THE FOLLOWING ASTM DESIGNATIONS:

A. ASTM A-572, GRADE 50 – ALL W SHAPES, UNLESS NOTED OR A992 OTHERWISE

B. ASTM A-36 – ALL OTHER ROLLED SHAPES, PLATES AND BARS UNLESS NOTED OTHERWISE.

C. ASTM A-500, GRADE B – HSS SECTION (SQUARE, RECTANGULAR, AND ROUND)

D. ASTM A-325, TYPE SC OR N – ALL BOLTS FOR CONNECTING STRUCTURAL MEMBERS

E. ASTM F-1554 07 – ALL ANCHOR BOLTS, UNLESS NOTED OTHERWISE

3. ALL EXPOSED STRUCTURAL STEEL MEMBERS SHALL BE HOT-DIPPED GALVANIZED AFTER FABRICATION PER ASTM A123. EXPOSED STEEL HARDWARE AND ANCHOR BOLTS SHALL BE GALVANIZED PER ASTM A153 OR B695.

4. ALL FIELD CUT SURFACES, FIELD DRILLED HOLES AND GROUND SURFACES WHERE EXISTING PAINT OR GALVANIZATION REMOVAL WAS REQUIRED SHALL BE REPAIRED WITH (2) BRUSHED COATS OF ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURER'S RECOMMENDATIONS.

5. DO NOT DRILL HOLES THROUGH STRUCTURAL STEEL MEMBERS EXCEPT AS SHOWN AND DETAILED ON STRUCTURAL DRAWINGS.

6. CONNECTIONS:

A. ALL WELDING TO BE PERFORMED BY AWS CERTIFIED WELDERS AND CONDUCTED IN ACCORDANCE WITH THE LATEST EDITION OF THE AWS WELDING CODE D1.1.

B. ALL WELDS SHALL BE INSPECTED VISUALLY. 25% OF WELDS SHALL BE INSPECTED WITH DYE PENETRANT OR MAGNETIC PARTICLE TO MEET THE ACCEPTANCE CRITERIA OF AWS D1.1. REPAIR ALL WELDS AS NECESSARY.

C. INSPECTION SHALL BE PERFORMED BY AN AWS CERTIFIED WELD INSPECTOR.

D. IT IS THE CONTRACTORS RESPONSIBILITY TO PROVIDE BURNING/WELDING PERMITS AS REQUIRED BY LOCAL GOVERNING AUTHORITY AND IF REQUIRED SHALL HAVE FIRE DEPARTMENT DETAIL FOR ANY WELDING ACTIVITY.

E. ALL ELECTRODES TO BE LOW HYDROGEN, MATCHING FILLER METAL, PER AWS D1.1, UNLESS NOTED OTHERWISE.

F. MINIMUM WELD SIZE TO BE 0.1875 INCH FILLET WELDS, UNLESS NOTED OTHERWISE.

G. PRIOR TO FIELD WELDING GALVANIZING MATERIAL, CONTRACTOR SHALL GRIND OFF GALVANIZING ½" BEYOND ALL FIELD WELD SURFACES. AFTER WELD AND WELD INSPECTION IS COMPLETE, REPAIR ALL GROUND AND WELDED SURFACES WITH ZRC GALVILITE COLD GALVANIZING COMPOUND PER ASTM A780 AND MANUFACTURERS RECOMMENDATIONS.

H. THE CONTRACTOR SHALL PROVIDE ADEQUATE SHORING AND/OR BRACING WHERE REQUIRED DURING CONSTRUCTION UNTIL ALL CONNECTIONS ARE COMPLETE.

I. ANY FIELD CHANGES OR SUBSTITUTIONS SHALL HAVE PRIOR APPROVAL FROM THE ENGINEER, AND DISH WIRELESS L.L.C. PROJECT MANAGER IN WRITING

dish wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

NB+C TOTALLY COMMITTED.

NB+C ENGINEERING SERVICES, LLC.
8601 SIX FORKS ROAD, SUITE 540
RALEIGH, NC 27615
(919) 657-9131

DRAWN BY:	CHECKED BY:	APPROVED BY:
JOA	BIW	BIW

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	08/26/2021	ISSUED FOR REVIEW
0	10/21/2021	ISSUED FOR CONSTRUCTION

STATE OF CONNECTICUT LICENSED PROFESSIONAL ENGINEER PEN.0028997

10/21/21

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

A&E PROJECT NUMBER
302540-13702514

DISH WIRELESS, L.L.C.
PROJECT INFORMATION
BOHVN00146A
8 OLD 79
MADISON, CT 06443-2685

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-4

ENGINEERING:

STRUCTURAL ANALYSIS

MOUNT ANALYSIS

AMERICAN TOWER®
CORPORATION

Structural Analysis Report

Structure	:	**148 ft Monopole**
ATC Site Name	:	**Madison CT 6,CT**
ATC Site Number	:	**302540**
Engineering Number	:	**13702514_C3_03**
Proposed Carrier	:	**DISH WIRELESS L.L.C.**
Carrier Site Name	:	**BOHVN00146A**
Carrier Site Number	:	**BOHVN00146A**
Site Location	:	**8 Old 79** **Madison, CT 06443-2685** **41.2855, -72.6013**
County	:	**New Haven**
Date	:	**August 9, 2021**
Max Usage	:	**58%**
Result	:	**Pass**

Prepared By:

Jennifer Yu
Structural Engineer I

Reviewed By:

COA : PEC.0001553

Table of Contents

Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 148 ft Monopole to reflect the change in loading by DISH WIRELESS L.L.C..

Supporting Documents

Tower Drawings	Summit, PJF Job #29299-729, dated November 12, 1999
Foundation Drawing	Spectrasite Project #F301896.00, dated January 4, 2000
Geotechnical Report	Dr. Clarence Welti, P.E., P.C., dated November 19, 1999

Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	123 mph (3-second gust)
Basic Wind Speed w/ Ice:	50 mph (3-second gust) w/ 1.00" radial ice concurrent
Code:	ANSI/TIA-222-H / 2015 IBC / 2018 Connecticut State Building Code
Exposure Category:	B
Risk Category:	II
Topographic Factor Procedure:	Method 1
Topographic Category:	1
Crest Height (H):	0 ft
Crest Length (L):	0 ft
Spectral Response:	Ss = 0.20, S_1 = 0.05
Site Class:	D - Stiff Soil - Default

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

Existing and Reserved Equipment

Elev.[1] (ft)	Qty	Equipment	Mount Type	Lines	Carrier
157.0	1	Generic 18' Dipole	Triangular Low Profile Platform	(5) 7/8" Coax	OTHER
153.0	1	Generic 8' Omni			
152.0	1	Generic 8' Dipole			
149.0	12	Generic 48" x 8" Panel		(12) 1 1/4" Coax	SPRINT NEXTEL
140.0	3	Samsung B5/B13 RRH-BR04C	Triangular Low Profile Platform	(2) 1 5/8" (1.63"-41.3mm) Fiber (11) 1 5/8" Coax	VERIZON WIRELESS
	1	RFS DB-C1-12C-24AB-0Z			
	3	Samsung MT6407-77A			
	1	Commscope LNX-6514DS-A1M			
	2	Andrew LNX-8513DS-A1M			
	3	Samsung B2/B66A RRH-BR049			
	6	Commscope JAHH-65B-R3B			
	3	Samsung Outdoor CBRS 20W RRH –Clip-on Antenna			
	3	Commscope CBC78T-DS-43-2X			
	3	Samsung RT4401-48A			
132.0	2	Raycap DC6-48-60-18-8F ("Squid")	Triangular Platform with Handrails	(2) 0.39" (10mm) Fiber Trunk (4) 0.78" (19.7mm) 8 AWG 6 (12) 1 5/8" Coax (1) 2" conduit (3) 3" conduit	AT&T MOBILITY
	6	Powerwave Allgon TT19-08BP111-001			
	6	Powerwave Allgon LGP13519			
	3	Ericsson Radio 4449 B13, B5			
	3	Kathrein Scala 80010964			
	3	Commscope SBNHH-1D65A			
	3	KMW AM-X-CD-14-65-00T-RET			
	3	Ericsson RRUS-12 B2			
	3	Ericsson RRUS 32 B30 (53 lbs)			
	3	Ericsson RRUS A2 B2			
120.0	4	Ericsson Radio 4460 B25+B66	Square Low Profile Platform	(1) 1 1/4" Hybriflex Cable (16) 1 5/8" Coax (8) 1 5/8" Hybriflex	T-MOBILE
	4	RFS APX16DWV-16DWVS-E-A20			
	4	Ericsson Air6449 B41			
97.5	3	RFS APXV9TM14-ALU-I20	Triangular Platform with Handrails	(4) 1 1/4" Hybriflex Cable	SPRINT NEXTEL
	3	RFS APXVSPP18-C-A20			
	3	Alcatel-Lucent TD-RRH8x20-25 w/ Solar Shield			
	3	Alcatel-Lucent 800 MHz 2X50W RRH w/ Filter			
	3	Alcatel-Lucent 1900 MHz 4X45 RRH			
86.0	3	RFS APXV18-206517S-C	Collar	(6) 1 5/8" Coax	METRO PCS INC
73.0	1	Generic GPS	Flush	(1) 1/2" Coax	SPRINT NEXTEL

Equipment to be Removed

Elev.[1] (ft)	Qty	Antenna	Mount Type	Lines	Carrier
112.0	6	Generic 6.7" x 10.7" TTA	-	-	OTHER
	3	Generic 48" x 12" Panel			

Proposed Equipment

Elev.[1] (ft)	Qty	Equipment	Mount Type	Lines	Carrier
110.0	1	Commscope RDIDC-9181-PF-48	Triangular Platform with Handrails	(1) 1.60" (40.6mm) Hybrid	DISH WIRELESS L.L.C.
	3	Fujitsu TA08025-B604			
	3	Fujitsu TA08025-B605			
	3	JMA Wireless MX08FRO665-21			

[1] Contracted elevations are shown for appurtenances within contracted installation tolerances. Appurtenances outside of contract limits are shown at installed elevations.

Install proposed lines inside the pole shaft.

Standard Conditions

All engineering services performed by A.T. Engineering Service, PLLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of A.T. Engineering Service, PLLC

It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete.

All assets of American Tower Corporation, its affiliates, and subsidiaries (collectively "American Tower") are inspected at regular intervals. Based upon these inspections and in the absence of information to the contrary, American Tower assumes that all structures were constructed in accordance with the drawings and specifications.

Unless explicitly agreed by both the client and A.T. Engineering Service, PLLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.

JOB INFORMATION

Asset :	302540, Madison CT 6	Height :	148 ft
Client :	DISH WIRELESS L.L.C.	Base Width :	61.05
Code :	ANSI/TIA-222-H	Shape :	18 Sides



SITE PARAMETERS

Description :	148 ft Summit Monopole		
Base Elev (ft):	0.00	Structure Class:	II
Taper :	0.26300 (In/ft)	Exposure :	B
Topographic Category :	1	Topographic Feature:	
Topo Method :	Method 1		

SECTION PROPERTIES

Shaft Section	Length (ft)	Diameter (in) Across Flats Top	Diameter (in) Across Flats Bottom	Thick (in)	Joint Type	Overlap Length (in)	Shape	Steel Grade (ksi)
1	45.000	49.22	61.05	0.500		0.000	18 Sides	65
2	40.000	41.15	51.67	0.375	Slip Joint	78.000	18 Sides	65
3	40.000	32.70	43.23	0.312	Slip Joint	66.000	18 Sides	65
4	39.250	24.00	34.32	0.250	Slip Joint	51.000	18 Sides	65

DISCRETE APPURTENANCE

Attach Elev (ft)	Force Elev (ft)	Qty	Description
157.0	157.0	1	Generic 18' Dipole
153.0	153.0	1	Generic 8' Omni
152.0	152.0	1	Generic 8' Dipole
149.0	149.0	12	Generic 48" x 8" Panel
148.0	148.0	1	Flat Low Profile Platform
140.0	140.0	3	Commscope CBC78T-DS-43-2X
140.0	140.0	3	Samsung Outdoor CBRS 20W RRH –
140.0	140.0	3	Samsung RT4401-48A
140.0	140.0	3	Samsung B2/B66A RRH-BR049
140.0	140.0	3	Samsung B5/B13 RRH-BR04C
140.0	140.0	1	RFS DB-C1-12C-24AB-0Z
140.0	140.0	3	Samsung MT6407-77A
140.0	140.0	1	Commscope LNX-6514DS-A1M
140.0	140.0	2	Andrew LNX-8513DS-A1M
140.0	140.0	6	Commscope JAHH-65B-R3B
140.0	140.0	1	Flat Low Profile Platform
138.0	138.0	1	Collar
132.0	132.0	6	Powerwave Allgon LGP13519
132.0	132.0	6	Powerwave Allgon TT19-08BP111-
132.0	132.0	2	Raycap DC6-48-60-18-8F ("Squid
132.0	132.0	3	Ericsson Radio 4449 B13, B5
132.0	132.0	3	Ericsson RRUS A2 B2
132.0	132.0	3	Ericsson RRUS 32 B30 (53 lbs)
132.0	132.0	3	Ericsson RRUS-12 B2
132.0	132.0	3	KMW AM-X-CD-14-65-00T-RET
132.0	132.0	3	Commscope SBNHH-1D65A
132.0	132.0	1	Generic Mount Reinforcement
132.0	132.0	3	Kathrein Scala 80010964
132.0	132.0	1	Generic Flat Platform with Han
120.0	120.0	4	Ericsson Radio 4460 B25+B66
120.0	120.0	4	Ericsson Air6449 B41
120.0	120.0	4	RFS APX16DWV-16DWVS-E-A20
120.0	120.0	1	Generic Square Low Profile Pla
110.0	110.0	1	Commscope RDIDC-9181-PF-48
110.0	110.0	3	Fujitsu TA08025-B605
110.0	110.0	3	Fujitsu TA08025-B604
110.0	110.0	3	JMA Wireless MX08FRO665-21
110.0	110.0	1	Generic Flat Platform with Han
101.0	101.0	1	Flat Platform w/ Handrails
97.5	101.0	3	Alcatel-Lucent 800 MHz 2X50W R
97.5	101.0	3	Alcatel-Lucent 1900 MHz 4X45 R
97.5	101.0	3	Alcatel-Lucent TD-RRH8x20-25 w
97.5	101.0	3	RFS APXV9TM14-ALU-I20

JOB INFORMATION

Asset :	302540, Madison CT 6	Height :	148 ft
Client :	DISH WIRELESS L.L.C.	Base Width :	61.05
Code :	ANSI/TIA-222-H	Shape :	18 Sides

DISCRETE APPURTENANCE

Attach Elev (ft)	Force Elev (ft)	Qty	Description
97.5	101.0	3	RFS APXVSPP18-C-A20
89.0	89.0	1	Collar
86.0	89.0	3	RFS APXV18-206517S-C
73.0	75.0	1	Generic GPS

LINEAR APPURTENANCE

Elev From (ft)	Elev To (ft)	Description	Exp To Wind
0.0	157.0	7/8" Coax	No
0.0	153.0	7/8" Coax	No
0.0	152.0	7/8" Coax	No
0.0	149.0	1 1/4" Coax	No
0.0	140.0	1 5/8" Coax	No
0.0	140.0	1 5/8" (1.63"-41.3mm) Fiber	No
0.0	132.0	3" conduit	No
0.0	132.0	2" conduit	No
0.0	132.0	1 5/8" Coax	No
0.0	132.0	0.78" (19.7mm) 8 AWG 6	No
0.0	132.0	0.39" (10mm) Fiber Trunk	No
0.0	121.0	1 5/8" Coax	Yes
0.0	121.0	1 1/4" Hybriflex Cable	Yes
0.0	120.0	1 5/8" Hybriflex	No
0.0	110.0	1.60" (40.6mm) Hybrid	No
0.0	97.5	1 1/4" Hybriflex Cable	No
0.0	86.0	1 5/8" Coax	No
0.0	73.0	1/2" Coax	Yes

LOAD CASES

1.2D + 1.0W Normal	123 mph wind with no ice
0.9D + 1.0W Normal	123 mph wind with no ice
1.2D + 1.0Di + 1.0Wi Nor	50 mph wind with 1" radial ice
1.2D + 1.0Ev + 1.0Eh Nor	Seismic
0.9D - 1.0Ev + 1.0Eh Nor	Seismic (Reduced DL)
1.0D + 1.0W Service Norm	60 mph Wind with No Ice

REACTIONS

Load Case	Moment (kip-ft)	Shear (Kip)	Axial (Kip)
1.2D + 1.0W Normal	3871.77	35.68	73.05
0.9D + 1.0W Normal	3832.11	35.66	54.78
1.2D + 1.0Di + 1.0Wi Normal	932.36	8.65	94.99
1.2D + 1.0Ev + 1.0Eh Normal	215.87	1.83	73.14
0.9D - 1.0Ev + 1.0Eh Normal	213.09	1.83	50.35
1.0D + 1.0W Service Normal	819.04	7.59	60.90

DISH DEFLECTIONS

Load Case	Attach Elev (ft)	Deflection (in)	Rotation (deg)

ANALYSIS PARAMETERS

Location:	New Haven County,CT	Height:	148 ft
Type and Shape:	Taper, 18 Sides	Base Diameter:	61.05 in
Manufacturer:	Undetermined	Top Diameter:	24.00 in
K_d (non-service):	0.95	Taper:	0.2630 in/ft
K_e:	1.00	Rotation:	0.000°

ICE & WIND PARAMETERS

Exposure Category:	B	Design Wind Speed w/o Ice:	123 mph
Risk Category:	II	Design Wind Speed w/Ice:	50 mph
Topo Factor Procedure:	Method 1	Operational Wind Speed:	60 mph
Topographic Category:	1	Design Ice Thickness:	1.00 in
Crest Height:	0 ft	HMSL:	30.00 ft

SEISMIC PARAMETERS

Analysis Method:	Equivalent Lateral Force Method				
Site Class:	D - Stiff Soil			Period Based on Rayleigh Method (sec):	2.17
T_L (sec):	6	P:	1	$C_{s:}$	0.030
$S_{s:}$	0.205	$S_{1:}$	0.054	C_s Max:	0.030
$F_{a:}$	1.600	$F_{v:}$	2.400	C_s Min:	0.030
$S_{ds:}$	0.219	$S_{d1:}$	0.086		

LOAD CASES

1.2D + 1.0W Normal	123 mph wind with no ice
0.9D + 1.0W Normal	123 mph wind with no ice
1.2D + 1.0Di + 1.0Wi Normal	50 mph wind with 1" radial ice
1.2D + 1.0Ev + 1.0Eh Normal	Seismic
0.9D - 1.0Ev + 1.0Eh Normal	Seismic (Reduced DL)
1.0D + 1.0W Service Normal	60 mph Wind with No Ice

SHAFT SECTION PROPERTIES

Sect Info	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Slip Joint len (in)	Weight (lb)	Bottom Dia (in)	Bottom Elev (ft)	Bottom Area (in²)	Bottom Ix (in⁴)	Bottom W/t Ratio	Bottom D/t Ratio	Top Dia (in)	Top Elev (in)	Top Area (in²)	Top Ix (in⁴)	Top W/t Ratio	Top D/t Ratio	Taper (in/ft)
1-18	45.00	0.5000	65		0.00	13,276	61.05	0.000	96.09	44,509.9	19.77	122.10	49.22	45.00	77.31	23,179.0	15.59	98.43	0.2630
2-18	40.00	0.3750	65	Slip	78.00	7,458	51.67	38.500	61.06	20,300.6	22.53	137.80	41.15	78.50	48.54	10,197.3	17.59	109.74	0.2630
3-18	40.00	0.3125	65	Slip	66.00	5,083	43.23	73.000	42.56	9,902.9	22.63	138.32	32.70	113.00	32.13	4,259.3	16.69	104.66	0.2630
4-18	39.25	0.2500	65	Slip	51.00	3,064	34.32	108.750	27.04	3,965.7	22.45	137.29	24.00	148.00	18.85	1,343.0	15.16	96.00	0.2630
				Shaft Weight		28,881													

DISCRETE APPURTENANCE PROPERTIES

Attach Elev (ft)	Description	Qty	Ka	Vert Ecc (ft)	No Ice Weight (lb)	No Ice EPAa (sf)	No Ice Orientation Factor	Ice Weight (lb)	Ice EPAa (sf)	Ice Orientation Factor
157.00	Generic 18' Dipole	1	1.00	0.000	55.00	6.770	1.00	187.84	13.893	1.00
153.00	Generic 8' Omni	1	1.00	0.000	25.00	2.400	1.00	65.65	4.231	1.00
152.00	Generic 8' Dipole	1	1.00	0.000	25.00	3.010	1.00	84.56	6.115	1.00
149.00	Generic 48" x 8" Panel	12	0.80	0.000	20.00	3.615	0.73	78.91	4.860	0.73
148.00	Flat Low Profile Platform	1	1.00	0.000	1500.00	26.100	1.00	1931.79	38.824	1.00
140.00	Flat Low Profile Platform	1	1.00	0.000	1500.00	26.100	1.00	1929.53	38.757	1.00
140.00	Andrew LNX-8513DS-A1M	2	0.80	0.000	39.20	8.173	0.77	155.83	10.042	0.77
140.00	Commscope JAHH-65B-R3B	6	0.80	0.000	60.60	9.113	0.69	194.72	10.952	0.69
140.00	Commscope LNX-6514DS-A1M	1	0.80	0.000	38.80	8.173	1.00	155.44	10.042	1.00
140.00	Samsung MT6407-77A	3	0.80	0.000	81.60	4.709	0.61	149.17	5.716	0.61
140.00	RFS DB-C1-12C-24AB-0Z	1	0.80	0.000	32.00	4.056	1.00	116.26	4.961	1.00
140.00	Samsung B5/B13 RRH-BR04C	3	0.80	0.000	70.30	1.875	0.50	108.22	2.473	0.50
140.00	Samsung B2/B66A RRH-BR049	3	0.80	0.000	84.40	1.875	0.50	126.69	2.473	0.50
140.00	Samsung RT4401-48A	3	0.80	0.000	18.60	0.996	0.50	36.50	1.450	0.50
140.00	Samsung Outdoor CBRS 20W RRH –	3	0.80	0.000	4.40	0.892	0.50	16.34	1.316	0.50
140.00	Commscope CBC78T-DS-43-2X	3	0.80	0.000	20.70	0.552	0.50	35.35	0.889	0.50
138.00	Collar	1	1.00	0.000	560.00	8.500	1.00	869.81	13.202	1.00
132.00	Commscope SBNHH-1D65A	3	0.80	0.000	33.50	5.883	0.69	122.71	7.285	0.69
132.00	Generic Mount Reinforcement	1	1.00	0.000	200.00	7.500	1.00	327.55	12.435	1.00
132.00	Kathrein Scala 80010964	3	0.80	0.000	83.80	9.997	0.62	218.62	11.553	0.62
132.00	Generic Flat Platform with Han	1	1.00	0.000	2500.00	42.400	1.00	3670.78	56.222	1.00
132.00	Ericsson RRUS-12 B2	3	0.80	0.000	58.00	3.145	0.62	111.31	3.909	0.62
132.00	KMW AM-X-CD-14-65-00T-RET	3	0.80	0.000	36.40	4.994	0.66	109.75	6.225	0.66
132.00	Powerwave Allgon LGP13519	6	0.80	0.000	5.30	0.290	0.50	11.55	0.545	0.50
132.00	Powerwave Allgon TT19-08BP111-	6	0.80	0.000	16.00	0.553	0.50	29.31	0.890	0.50
132.00	Raycap DC6-48-60-18-8F ("Squid	2	0.80	0.000	31.80	1.470	1.00	72.46	1.930	1.00
132.00	Ericsson RRUS 32 B30 (53 lbs)	3	0.80	0.000	53.00	2.743	0.67	101.47	3.514	0.67
132.00	Ericsson RRUS A2 B2	3	0.80	0.000	22.00	2.064	0.67	51.06	2.686	0.67
132.00	Ericsson Radio 4449 B13, B5	3	0.80	0.000	70.60	1.969	0.50	113.03	2.583	0.50
120.00	Ericsson Air6449 B41	4	0.80	0.000	104.00	5.682	0.63	192.85	6.717	0.63
120.00	RFS APX16DWV-16DWVS-E-A20	4	0.80	0.000	40.70	6.586	0.60	116.86	7.998	0.60
120.00	Generic Square Low Profile Pla	1	1.00	0.000	2863.00	45.000	1.00	3799.19	82.196	1.00
120.00	Ericsson Radio 4460 B25+B66	4	0.80	0.000	109.00	2.564	0.67	166.62	3.251	0.67
110.00	Generic Flat Platform with Han	1	1.00	0.000	2500.00	42.400	1.00	3649.85	55.975	1.00
110.00	JMA Wireless MX08FRO665-21	3	0.75	0.000	64.50	12.489	0.64	230.86	14.308	0.64
110.00	Fujitsu TA08025-B605	3	0.75	0.000	75.00	1.962	0.50	115.55	2.557	0.50
110.00	Fujitsu TA08025-B604	3	0.75	0.000	63.90	1.962	0.50	101.65	2.557	0.50
110.00	Commscope RDIDC-9181-PF-48	1	0.75	0.000	21.90	1.867	1.00	58.73	2.450	1.00
101.00	Flat Platform w/ Handrails	1	1.00	0.000	2000.00	42.400	1.00	2912.13	55.860	1.00
97.50	Alcatel-Lucent 800 MHz 2X50W R	3	0.75	3.500	64.00	2.058	0.67	113.23	2.670	0.67
97.50	RFS APXV9TM14-ALU-I20	3	0.75	3.500	55.10	6.381	0.66	143.04	7.782	0.66
97.50	Alcatel-Lucent TD-RRH8x20-25 w	3	0.75	3.500	70.00	4.046	0.61	130.39	4.894	0.61
97.50	RFS APXVSPP18-C-A20	3	0.75	3.500	57.00	8.024	0.69	167.23	9.807	0.69
97.50	Alcatel-Lucent 1900 MHz 4X45 R	3	0.75	3.500	60.00	2.322	0.67	111.50	3.013	0.67
89.00	Collar	1	1.00	0.000	560.00	8.500	1.00	856.33	12.998	1.00
86.00	RFS APXV18-206517S-C	3	1.00	3.000	26.40	5.160	0.68	84.92	6.654	0.68
73.00	Generic GPS	1	1.00	2.000	10.00	0.900	1.00	28.15	1.297	1.00
Totals	Num Loadings: 47	128			19,798.50			32,861.66		

LINEAR APPURTENANCE PROPERTIES

Load Case Azimuth (deg) : 0.00

Elev From (ft)	Elev To (ft)	Qty	Description	Coax Dia (in)	Coax Wt (lb/ft)	Flat	Max Coax/ Row	Dist Between Rows(in)	Dist Between Cols(in)	Azimuth (deg)	Dist From Face	Exposed To Wind	Carrier

											(in)		
0.00	157.00	2	7/8" Coax	1.09	0.33	N	0	0	0	0	0	N	Other
0.00	153.00	1	7/8" Coax	1.09	0.33	N	0	0	0	0	0	N	Other
0.00	152.00	2	7/8" Coax	1.09	0.33	N	0	0	0	0	0	N	OTHER
0.00	149.00	12	1 1/4" Coax	1.55	0.63	N	0	0	0	0	0	N	SPRINT NEXTEL
0.00	140.00	11	1 5/8" Coax	1.98	0.82	N	0	0	0	0	0	N	VERIZON WIREL
0.00	140.00	2	1 5/8" (1.63"-41.3mm)	1.63	1.61	N	0	0	0	0	0	N	VERIZON WIREL
0.00	132.00	12	1 5/8" Coax	1.98	0.82	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	132.00	4	0.78" (19.7mm) 8 AWG	0.78	0.59	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	132.00	3	3" conduit	3.5	7.58	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	132.00	2	0.39" (10mm) Fiber Tr	0.39	0.06	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	132.00	1	2" conduit	2.38	3.65	N	0	0	0	0	0	N	AT&T MOBILITY
0.00	121.00	16	1 5/8" Coax	1.98	0.82	N	8	0.5	0.5	90	0.5	Y	T-MOBILE
0.00	121.00	1	1 1/4" Hybriflex Cabl	1.54	1	N	1	0	0	75	0.5	Y	T-MOBILE
0.00	120.00	8	1 5/8" Hybriflex	1.98	1.3	N	0	0	0	0	0	N	T-MOBILE
0.00	110.00	1	1.60" (40.6mm) Hybrid	1.6	2.34	N	0	0	0	0	0	N	DISH WIRELESS
0.00	97.50	4	1 1/4" Hybriflex Cabl	1.54	1	N	0	0	0	0	0	N	SPRINT NEXTEL
0.00	86.00	6	1 5/8" Coax	1.98	0.82	N	0	0	0	0	0	N	METRO PCS INC
0.00	73.00	1	1/2" Coax	0.63	0.15	N	1	0	0	30	0.5	Y	SPRINT NEXTEL

SEGMENT PROPERTIES

(Max Len: 5.ft)

Seg Top Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in^2)	Ix (in^4)	W/t Ratio	D/t Ratio	F'y (ksi)	S (in^3)	Z (in^3)	Weight (lb)
0.00		0.5000	61.050	96.089	44,509.90	19.77	122.10	78.2	1436.0	0.0	0.0
5.00		0.5000	59.735	94.003	41,672.40	19.30	119.47	78.7	1374.0	0.0	1,617.1
10.00		0.5000	58.420	91.916	38,958.20	18.84	116.84	79.2	1313.5	0.0	1,581.6
15.00		0.5000	57.105	89.829	36,364.40	18.38	114.21	79.8	1254.3	0.0	1,546.1
20.00		0.5000	55.790	87.742	33,888.40	17.91	111.58	80.3	1196.4	0.0	1,510.6
25.00		0.5000	54.475	85.655	31,527.40	17.45	108.95	80.9	1139.9	0.0	1,475.1
30.00		0.5000	53.160	83.568	29,278.70	16.98	106.32	81.4	1084.8	0.0	1,439.6
35.00		0.5000	51.845	81.481	27,139.60	16.52	103.69	82	1031.1	0.0	1,404.1
38.50	Bot - Section 2	0.5000	50.924	80.020	25,705.90	16.20	101.85	82.4	994.2	0.0	961.7
40.00		0.5000	50.530	79.394	25,107.30	16.06	101.06	82.5	978.7	0.0	717.3
45.00	Top - Section 1	0.3750	49.965	59.022	18,337.90	21.73	133.24	75.8	722.9	0.0	2,350.6
50.00		0.3750	48.650	57.457	16,917.40	21.11	129.73	76.6	684.9	0.0	990.9
55.00		0.3750	47.335	55.892	15,572.20	20.49	126.23	77.3	648.0	0.0	964.3
60.00		0.3750	46.020	54.327	14,300.30	19.88	122.72	78	612.0	0.0	937.6
65.00		0.3750	44.705	52.761	13,099.60	19.26	119.21	78.8	577.1	0.0	911.0
70.00		0.3750	43.390	51.196	11,968.00	18.64	115.71	79.5	543.3	0.0	884.4
73.00	Bot - Section 3	0.3750	42.601	50.257	11,321.40	18.27	113.60	79.9	523.4	0.0	517.8
75.00		0.3750	42.075	49.631	10,903.60	18.02	112.20	80.2	510.4	0.0	627.8
78.50	Top - Section 2	0.3125	41.779	41.128	8,934.80	21.81	133.69	75.7	421.2	0.0	1,079.8
80.00		0.3125	41.385	40.737	8,682.30	21.59	132.43	76	413.2	0.0	208.9
85.00		0.3125	40.069	39.433	7,874.70	20.85	128.22	76.9	387.1	0.0	682.0
86.00		0.3125	39.806	39.172	7,719.50	20.70	127.38	77.1	382.0	0.0	133.7
89.00		0.3125	39.017	38.389	7,266.00	20.25	124.86	77.6	366.8	0.0	395.9
90.00		0.3125	38.754	38.128	7,118.90	20.10	124.01	77.8	361.8	0.0	130.2
95.00		0.3125	37.439	36.824	6,413.00	19.36	119.81	78.6	337.4	0.0	637.6
97.50		0.3125	36.782	36.172	6,078.30	18.99	117.70	79.1	325.5	0.0	310.5
100.00		0.3125	36.124	35.520	5,755.40	18.62	115.60	79.5	313.8	0.0	304.9
101.00		0.3125	35.861	35.259	5,629.50	18.47	114.76	79.7	309.2	0.0	120.4
105.00		0.3125	34.809	34.215	5,144.40	17.88	111.39	80.4	291.1	0.0	472.8
108.75	Bot - Section 4	0.3125	33.823	33.237	4,715.60	17.32	108.23	81	274.6	0.0	430.4
110.00		0.3125	33.494	32.911	4,578.20	17.14	107.18	81.2	269.2	0.0	255.1
113.00	Top - Section 3	0.2500	33.205	26.149	3,588.10	21.66	132.82	75.9	212.8	0.0	602.1
115.00		0.2500	32.679	25.732	3,419.00	21.29	130.72	76.4	206.1	0.0	176.5
120.00		0.2500	31.364	24.688	3,019.70	20.36	125.46	77.5	189.6	0.0	428.9
125.00		0.2500	30.049	23.645	2,652.80	19.43	120.20	78.5	173.9	0.0	411.2
130.00		0.2500	28.734	22.601	2,316.80	18.50	114.94	79.6	158.8	0.0	393.4
132.00		0.2500	28.208	22.184	2,190.80	18.13	112.83	80.1	153.0	0.0	152.4
135.00		0.2500	27.419	21.558	2,010.50	17.58	109.68	80.7	144.4	0.0	223.3
138.00		0.2500	26.630	20.932	1,840.40	17.02	106.52	81.4	136.1	0.0	216.9
140.00		0.2500	26.104	20.515	1,732.50	16.65	104.42	81.8	130.7	0.0	141.0
145.00		0.2500	24.789	19.471	1,481.40	15.72	99.16	82.6	117.7	0.0	340.2
148.00		0.2500	24.000	18.845	1,343.00	15.16	96.00	82.6	110.2	0.0	195.6
								Totals:			28,881.3

Load Case: 1.2D + 1.0W Normal 123 mph wind with no ice 22 Iterations
Gust Response Factor: 1.10
Dead load Factor: 1.20
Wind Load Factor: 1.00

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-73.05	-35.68	0.00	-3,871.8	0.00	3,871.77	6,758.62	1,686.37	9,222.92	8,416.93	0.00	0	0.471
5.00	-70.45	-35.31	0.00	-3,693.4	0.00	3,693.37	6,657.98	1,649.74	8,826.71	8,110.05	0.07	-0.12	0.466
10.00	-67.91	-34.93	0.00	-3,516.8	0.00	3,516.85	6,555.29	1,613.12	8,439.20	7,806.21	0.26	-0.24	0.461
15.00	-65.40	-34.57	0.00	-3,342.2	0.00	3,342.19	6,450.55	1,576.49	8,060.39	7,505.59	0.58	-0.37	0.456
20.00	-62.94	-34.20	0.00	-3,169.4	0.00	3,169.36	6,343.77	1,539.87	7,690.27	7,208.36	1.04	-0.5	0.450
25.00	-60.52	-33.84	0.00	-2,998.4	0.00	2,998.36	6,234.93	1,503.25	7,328.86	6,914.68	1.63	-0.63	0.444
30.00	-58.14	-33.48	0.00	-2,829.2	0.00	2,829.17	6,124.05	1,466.62	6,976.14	6,624.72	2.35	-0.76	0.437
35.00	-55.82	-33.15	0.00	-2,661.8	0.00	2,661.79	6,011.12	1,430.00	6,632.12	6,338.64	3.22	-0.89	0.430
38.50	-54.23	-32.95	0.00	-2,545.8	0.00	2,545.75	5,930.85	1,404.36	6,396.48	6,140.79	3.91	-0.99	0.424
40.00	-53.15	-32.70	0.00	-2,496.3	0.00	2,496.33	5,896.14	1,393.37	6,296.80	6,056.62	4.23	-1.03	0.422
45.00	-49.69	-32.26	0.00	-2,332.8	0.00	2,332.82	4,028.71	1,035.84	4,639.55	4,111.86	5.38	-1.17	0.581
50.00	-47.84	-31.86	0.00	-2,171.5	0.00	2,171.50	3,959.48	1,008.37	4,396.77	3,933.24	6.67	-1.3	0.565
55.00	-46.03	-31.46	0.00	-2,012.2	0.00	2,012.19	3,888.20	980.90	4,160.52	3,756.41	8.13	-1.48	0.549
60.00	-44.24	-31.05	0.00	-1,854.9	0.00	1,854.87	3,814.88	953.43	3,930.79	3,581.54	9.78	-1.66	0.531
65.00	-42.50	-30.61	0.00	-1,699.6	0.00	1,699.63	3,739.51	925.96	3,707.59	3,408.81	11.61	-1.83	0.511
70.00	-40.80	-30.25	0.00	-1,546.6	0.00	1,546.56	3,662.08	898.49	3,490.91	3,238.38	13.62	-2.01	0.490
73.00	-39.79	-29.98	0.00	-1,455.8	0.00	1,455.76	3,614.65	882.01	3,364.03	3,137.29	14.92	-2.12	0.476
75.00	-38.76	-29.71	0.00	-1,395.8	0.00	1,395.81	3,582.61	871.03	3,280.75	3,070.41	15.82	-2.19	0.467
78.50	-37.03	-29.44	0.00	-1,291.8	0.00	1,291.81	2,803.83	721.80	2,703.37	2,392.99	17.47	-2.31	0.555
80.00	-36.56	-29.16	0.00	-1,247.6	0.00	1,247.65	2,786.75	714.93	2,652.18	2,355.62	18.21	-2.36	0.544
85.00	-35.12	-28.85	0.00	-1,101.9	0.00	1,101.87	2,728.50	692.04	2,485.09	2,231.98	20.79	-2.56	0.508
86.00	-34.74	-28.26	0.00	-1,071.8	0.00	1,071.81	2,716.60	687.46	2,452.32	2,207.43	21.32	-2.6	0.500
89.00	-33.26	-27.69	0.00	-987.0	0.00	987.04	2,680.42	673.73	2,355.33	2,134.18	22.99	-2.71	0.477
90.00	-32.95	-27.42	0.00	-959.4	0.00	959.35	2,668.19	669.15	2,323.43	2,109.89	23.56	-2.75	0.469
95.00	-31.60	-27.02	0.00	-822.3	0.00	822.26	2,605.84	646.26	2,167.21	1,989.53	26.54	-2.93	0.427
97.50	-29.91	-25.34	0.00	-749.9	0.00	749.93	2,573.90	634.81	2,091.13	1,930.05	28.09	-3.01	0.402
100.00	-29.26	-25.15	0.00	-686.6	0.00	686.57	2,541.44	623.37	2,016.42	1,871.06	29.69	-3.1	0.380
101.00	-26.69	-23.08	0.00	-661.4	0.00	661.42	2,528.32	618.79	1,986.91	1,847.61	30.35	-3.13	0.370
105.00	-25.69	-22.65	0.00	-569.1	0.00	569.12	2,474.99	600.48	1,871.07	1,754.65	33.02	-3.25	0.336
108.75	-24.77	-22.36	0.00	-484.2	0.00	484.18	2,423.81	583.31	1,765.62	1,668.80	35.62	-3.36	0.302
110.00	-20.74	-19.18	0.00	-456.2	0.00	456.24	2,406.50	577.59	1,731.16	1,640.47	36.51	-3.4	0.288
113.00	-19.71	-18.87	0.00	-398.7	0.00	398.70	1,786.92	458.92	1,366.00	1,211.99	38.67	-3.48	0.342
115.00	-19.28	-18.49	0.00	-361.0	0.00	360.97	1,768.50	451.59	1,322.75	1,180.21	40.14	-3.53	0.318
120.00	-13.82	-14.47	0.00	-268.5	0.00	268.53	1,721.02	433.28	1,217.66	1,101.60	43.91	-3.66	0.253
125.00	-12.96	-13.97	0.00	-196.2	0.00	196.16	1,671.50	414.97	1,116.92	1,024.32	47.80	-3.77	0.200
130.00	-12.13	-13.66	0.00	-126.3	0.00	126.31	1,619.93	396.65	1,020.53	948.55	51.80	-3.86	0.142
132.00	-7.37	-8.75	0.00	-99.0	0.00	98.99	1,598.72	389.33	983.19	918.69	53.42	-3.88	0.113
135.00	-7.03	-8.51	0.00	-72.8	0.00	72.75	1,566.31	378.34	928.49	874.44	55.87	-3.92	0.088
138.00	-6.06	-7.89	0.00	-47.2	0.00	47.23	1,533.15	367.35	875.35	830.84	58.34	-3.94	0.061
140.00	-2.72	-3.42	0.00	-31.5	0.00	31.46	1,510.64	360.03	840.79	802.17	59.99	-3.96	0.041
145.00	-2.27	-3.12	0.00	-14.3	0.00	14.34	1,446.60	341.72	757.45	728.72	64.14	-3.97	0.021
148.00	0.00	-2.95	0.00	-5.0	0.00	4.99	1,400.09	330.73	709.53	682.38	66.64	-3.98	0.007

Load Case: 0.9D + 1.0W Normal 123 mph wind with no ice 22 Iterations
Gust Response Factor: 1.10
Dead load Factor: 0.90
Wind Load Factor: 1.00

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-54.78	-35.66	0.00	-3,832.1	0.00	3,832.11	6,758.62	1,686.37	9,222.92	8,416.93	0.00	0	0.464
5.00	-52.81	-35.25	0.00	-3,653.8	0.00	3,653.82	6,657.98	1,649.74	8,826.71	8,110.05	0.06	-0.12	0.459
10.00	-50.89	-34.84	0.00	-3,477.6	0.00	3,477.59	6,555.29	1,613.12	8,439.20	7,806.21	0.26	-0.24	0.454
15.00	-48.99	-34.44	0.00	-3,303.4	0.00	3,303.40	6,450.55	1,576.49	8,060.39	7,505.59	0.58	-0.37	0.448
20.00	-47.13	-34.04	0.00	-3,131.2	0.00	3,131.22	6,343.77	1,539.87	7,690.27	7,208.36	1.03	-0.49	0.442
25.00	-45.29	-33.65	0.00	-2,961.0	0.00	2,961.02	6,234.93	1,503.25	7,328.86	6,914.68	1.61	-0.62	0.436
30.00	-43.50	-33.26	0.00	-2,792.8	0.00	2,792.77	6,124.05	1,466.62	6,976.14	6,624.72	2.33	-0.75	0.429
35.00	-41.74	-32.91	0.00	-2,626.5	0.00	2,626.49	6,011.12	1,430.00	6,632.12	6,338.64	3.18	-0.88	0.422
38.50	-40.54	-32.70	0.00	-2,511.3	0.00	2,511.29	5,930.85	1,404.36	6,396.48	6,140.79	3.86	-0.97	0.416
40.00	-39.72	-32.43	0.00	-2,462.2	0.00	2,462.24	5,896.14	1,393.37	6,296.80	6,056.62	4.18	-1.02	0.414
45.00	-37.11	-31.98	0.00	-2,300.1	0.00	2,300.07	4,028.71	1,035.84	4,639.55	4,111.86	5.31	-1.15	0.570
50.00	-35.71	-31.56	0.00	-2,140.2	0.00	2,140.16	3,959.48	1,008.37	4,396.77	3,933.24	6.59	-1.29	0.554
55.00	-34.32	-31.13	0.00	-1,982.4	0.00	1,982.37	3,888.20	980.90	4,160.52	3,756.41	8.03	-1.46	0.538
60.00	-32.97	-30.69	0.00	-1,826.7	0.00	1,826.72	3,814.88	953.43	3,930.79	3,581.54	9.66	-1.63	0.520
65.00	-31.64	-30.24	0.00	-1,673.3	0.00	1,673.27	3,739.51	925.96	3,707.59	3,408.81	11.46	-1.81	0.500
70.00	-30.36	-29.85	0.00	-1,522.1	0.00	1,522.10	3,662.08	898.49	3,490.91	3,238.38	13.45	-1.98	0.479
73.00	-29.59	-29.58	0.00	-1,432.5	0.00	1,432.47	3,614.65	882.01	3,364.03	3,137.29	14.73	-2.09	0.466
75.00	-28.81	-29.31	0.00	-1,373.3	0.00	1,373.31	3,582.61	871.03	3,280.75	3,070.41	15.62	-2.16	0.456
78.50	-27.50	-29.03	0.00	-1,270.7	0.00	1,270.74	2,803.83	721.80	2,703.37	2,392.99	17.25	-2.28	0.542
80.00	-27.14	-28.73	0.00	-1,227.2	0.00	1,227.19	2,786.75	714.93	2,652.18	2,355.62	17.97	-2.33	0.532
85.00	-26.05	-28.42	0.00	-1,083.5	0.00	1,083.52	2,728.50	692.04	2,485.09	2,231.98	20.52	-2.52	0.497
86.00	-25.77	-27.82	0.00	-1,053.9	0.00	1,053.88	2,716.60	687.46	2,452.32	2,207.43	21.05	-2.56	0.489
89.00	-24.65	-27.26	0.00	-970.4	0.00	970.41	2,680.42	673.73	2,355.33	2,134.18	22.70	-2.67	0.466
90.00	-24.42	-26.98	0.00	-943.2	0.00	943.15	2,668.19	669.15	2,323.43	2,109.89	23.26	-2.71	0.458
95.00	-23.39	-26.58	0.00	-808.3	0.00	808.27	2,605.84	646.26	2,167.21	1,989.53	26.19	-2.88	0.417
97.50	-22.13	-24.91	0.00	-737.0	0.00	737.05	2,573.90	634.81	2,091.13	1,930.05	27.72	-2.97	0.392
100.00	-21.65	-24.72	0.00	-674.8	0.00	674.78	2,541.44	623.37	2,016.42	1,871.06	29.30	-3.05	0.371
101.00	-19.74	-22.67	0.00	-650.1	0.00	650.06	2,528.32	618.79	1,986.91	1,847.61	29.94	-3.08	0.361
105.00	-18.98	-22.25	0.00	-559.4	0.00	559.38	2,474.99	600.48	1,871.07	1,754.65	32.58	-3.21	0.328
108.75	-18.29	-21.96	0.00	-476.0	0.00	475.96	2,423.81	583.31	1,765.62	1,668.80	35.14	-3.31	0.294
110.00	-15.30	-18.84	0.00	-448.5	0.00	448.52	2,406.50	577.59	1,731.16	1,640.47	36.02	-3.35	0.281
113.00	-14.53	-18.53	0.00	-392.0	0.00	392.00	1,786.92	458.92	1,366.00	1,211.99	38.14	-3.43	0.333
115.00	-14.21	-18.15	0.00	-354.9	0.00	354.93	1,768.50	451.59	1,322.75	1,180.21	39.59	-3.48	0.310
120.00	-10.16	-14.23	0.00	-264.2	0.00	264.17	1,721.02	433.28	1,217.66	1,101.60	43.30	-3.61	0.247
125.00	-9.51	-13.73	0.00	-193.0	0.00	193.04	1,671.50	414.97	1,116.92	1,024.32	47.14	-3.71	0.195
130.00	-8.90	-13.43	0.00	-124.4	0.00	124.39	1,619.93	396.65	1,020.53	948.55	51.07	-3.8	0.138
132.00	-5.39	-8.61	0.00	-97.5	0.00	97.53	1,598.72	389.33	983.19	918.69	52.67	-3.83	0.110
135.00	-5.15	-8.37	0.00	-71.7	0.00	71.71	1,566.31	378.34	928.49	874.44	55.09	-3.86	0.086
138.00	-4.42	-7.77	0.00	-46.6	0.00	46.60	1,533.15	367.35	875.35	830.84	57.52	-3.88	0.059
140.00	-1.98	-3.37	0.00	-31.1	0.00	31.06	1,510.64	360.03	840.79	802.17	59.15	-3.9	0.040
145.00	-1.66	-3.07	0.00	-14.2	0.00	14.21	1,446.60	341.72	757.45	728.72	63.23	-3.91	0.021
148.00	0.00	-2.95	0.00	-5.0	0.00	4.99	1,400.09	330.73	709.53	682.38	65.69	-3.92	0.007

Load Case: 1.2D + 1.0Di + 1.0Wi Normal		50 mph wind with 1" radial ice			21 Iterations
Gust Response Factor:	1.10	Ice Dead Load Factor	1.00		
Dead load Factor:	1.20			Ice Importance Factor	1.00
Wind Load Factor:	1.00				

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-94.99	-8.65	0.00	-932.4	0.00	932.36	6,758.62	1,686.37	9,222.92	8,416.93	0.00	0	0.125
5.00	-92.05	-8.55	0.00	-889.1	0.00	889.12	6,657.98	1,649.74	8,826.71	8,110.05	0.02	-0.03	0.123
10.00	-89.12	-8.45	0.00	-846.4	0.00	846.37	6,555.29	1,613.12	8,439.20	7,806.21	0.06	-0.06	0.122
15.00	-86.22	-8.35	0.00	-804.1	0.00	804.12	6,450.55	1,576.49	8,060.39	7,505.59	0.14	-0.09	0.121
20.00	-83.36	-8.26	0.00	-762.4	0.00	762.36	6,343.77	1,539.87	7,690.27	7,208.36	0.25	-0.12	0.119
25.00	-80.54	-8.16	0.00	-721.1	0.00	721.08	6,234.93	1,503.25	7,328.86	6,914.68	0.39	-0.15	0.117
30.00	-77.76	-8.06	0.00	-680.3	0.00	680.28	6,124.05	1,466.62	6,976.14	6,624.72	0.57	-0.18	0.115
35.00	-75.02	-7.98	0.00	-640.0	0.00	639.97	6,011.12	1,430.00	6,632.12	6,338.64	0.77	-0.21	0.113
38.50	-73.13	-7.92	0.00	-612.1	0.00	612.06	5,930.85	1,404.36	6,396.48	6,140.79	0.94	-0.24	0.112
40.00	-71.95	-7.85	0.00	-600.2	0.00	600.18	5,896.14	1,393.37	6,296.80	6,056.62	1.02	-0.25	0.111
45.00	-68.08	-7.74	0.00	-560.9	0.00	560.91	4,028.71	1,035.84	4,639.55	4,111.86	1.29	-0.28	0.153
50.00	-65.85	-7.63	0.00	-522.2	0.00	522.23	3,959.48	1,008.37	4,396.77	3,933.24	1.61	-0.31	0.149
55.00	-63.65	-7.52	0.00	-484.1	0.00	484.08	3,888.20	980.90	4,160.52	3,756.41	1.96	-0.36	0.145
60.00	-61.48	-7.42	0.00	-446.5	0.00	446.46	3,814.88	953.43	3,930.79	3,581.54	2.35	-0.4	0.141
65.00	-59.36	-7.31	0.00	-409.4	0.00	409.39	3,739.51	925.96	3,707.59	3,408.81	2.79	-0.44	0.136
70.00	-57.27	-7.21	0.00	-372.9	0.00	372.86	3,662.08	898.49	3,490.91	3,238.38	3.28	-0.48	0.131
73.00	-56.01	-7.15	0.00	-351.2	0.00	351.20	3,614.65	882.01	3,364.03	3,137.29	3.59	-0.51	0.128
75.00	-54.85	-7.08	0.00	-336.9	0.00	336.91	3,582.61	871.03	3,280.75	3,070.41	3.81	-0.53	0.125
78.50	-52.84	-7.01	0.00	-312.1	0.00	312.13	2,803.83	721.80	2,703.37	2,392.99	4.20	-0.56	0.149
80.00	-52.29	-6.95	0.00	-301.6	0.00	301.61	2,786.75	714.93	2,652.18	2,355.62	4.38	-0.57	0.147
85.00	-50.46	-6.87	0.00	-266.9	0.00	266.87	2,728.50	692.04	2,485.09	2,231.98	5.00	-0.62	0.138
86.00	-49.87	-6.74	0.00	-259.7	0.00	259.74	2,716.60	687.46	2,452.32	2,207.43	5.13	-0.63	0.136
89.00	-47.91	-6.60	0.00	-239.5	0.00	239.52	2,680.42	673.73	2,355.33	2,134.18	5.53	-0.65	0.130
90.00	-47.56	-6.54	0.00	-232.9	0.00	232.92	2,668.19	669.15	2,323.43	2,109.89	5.67	-0.66	0.128
95.00	-45.84	-6.44	0.00	-200.2	0.00	200.24	2,605.84	646.26	2,167.21	1,989.53	6.39	-0.71	0.118
97.50	-43.05	-6.08	0.00	-183.2	0.00	183.16	2,573.90	634.81	2,091.13	1,930.05	6.76	-0.73	0.112
100.00	-42.22	-6.04	0.00	-168.0	0.00	167.96	2,541.44	623.37	2,016.42	1,871.06	7.15	-0.75	0.106
101.00	-38.79	-5.57	0.00	-161.9	0.00	161.92	2,528.32	618.79	1,986.91	1,847.61	7.31	-0.76	0.103
105.00	-37.48	-5.47	0.00	-139.6	0.00	139.64	2,474.99	600.48	1,871.07	1,754.65	7.95	-0.79	0.095
108.75	-36.28	-5.41	0.00	-119.1	0.00	119.12	2,423.81	583.31	1,765.62	1,668.80	8.58	-0.81	0.086
110.00	-30.50	-4.71	0.00	-112.4	0.00	112.36	2,406.50	577.59	1,731.16	1,640.47	8.80	-0.82	0.081
113.00	-29.24	-4.63	0.00	-98.2	0.00	98.24	1,786.92	458.92	1,366.00	1,211.99	9.32	-0.84	0.098
115.00	-28.67	-4.55	0.00	-89.0	0.00	88.97	1,768.50	451.59	1,322.75	1,180.21	9.67	-0.85	0.092
120.00	-21.20	-3.51	0.00	-66.2	0.00	66.21	1,721.02	433.28	1,217.66	1,101.60	10.59	-0.89	0.072
125.00	-20.08	-3.39	0.00	-48.6	0.00	48.65	1,671.50	414.97	1,116.92	1,024.32	11.53	-0.91	0.060
130.00	-19.03	-3.30	0.00	-31.7	0.00	31.72	1,619.93	396.65	1,020.53	948.55	12.50	-0.93	0.045
132.00	-11.61	-2.17	0.00	-25.1	0.00	25.13	1,598.72	389.33	983.19	918.69	12.89	-0.94	0.035
135.00	-11.14	-2.10	0.00	-18.6	0.00	18.63	1,566.31	378.34	928.49	874.44	13.48	-0.95	0.028
138.00	-9.77	-1.93	0.00	-12.3	0.00	12.34	1,533.15	367.35	875.35	830.84	14.08	-0.96	0.021
140.00	-4.30	-0.90	0.00	-8.5	0.00	8.48	1,510.64	360.03	840.79	802.17	14.48	-0.96	0.013
145.00	-3.65	-0.81	0.00	-4.0	0.00	3.97	1,446.60	341.72	757.45	728.72	15.49	-0.96	0.008
148.00	0.00	-0.75	0.00	-1.5	0.00	1.53	1,400.09	330.73	709.53	682.38	16.10	-0.97	0.002

Load Case: 1.0D + 1.0W Service Normal 60 mph Wind with No Ice 20 Iterations
Gust Response Factor: 1.10
Dead load Factor: 1.00
Wind Load Factor: 1.00

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (ft-kips)	Phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-60.90	-7.59	0.00	-819.0	0.00	819.04	6,758.62	1,686.37	9,222.92	8,416.93	0.00	0	0.106
5.00	-58.80	-7.51	0.00	-781.1	0.00	781.08	6,657.98	1,649.74	8,826.71	8,110.05	0.01	-0.03	0.105
10.00	-56.74	-7.42	0.00	-743.5	0.00	743.54	6,555.29	1,613.12	8,439.20	7,806.21	0.05	-0.05	0.104
15.00	-54.71	-7.34	0.00	-706.4	0.00	706.43	6,450.55	1,576.49	8,060.39	7,505.59	0.12	-0.08	0.103
20.00	-52.71	-7.26	0.00	-669.7	0.00	669.73	6,343.77	1,539.87	7,690.27	7,208.36	0.22	-0.1	0.101
25.00	-50.75	-7.18	0.00	-633.4	0.00	633.44	6,234.93	1,503.25	7,328.86	6,914.68	0.34	-0.13	0.100
30.00	-48.83	-7.10	0.00	-597.6	0.00	597.56	6,124.05	1,466.62	6,976.14	6,624.72	0.50	-0.16	0.098
35.00	-46.94	-7.02	0.00	-562.1	0.00	562.08	6,011.12	1,430.00	6,632.12	6,338.64	0.68	-0.19	0.097
38.50	-45.64	-6.98	0.00	-537.5	0.00	537.49	5,930.85	1,404.36	6,396.48	6,140.79	0.83	-0.21	0.095
40.00	-44.78	-6.92	0.00	-527.0	0.00	527.02	5,896.14	1,393.37	6,296.80	6,056.62	0.89	-0.22	0.095
45.00	-41.95	-6.83	0.00	-492.4	0.00	492.40	4,028.71	1,035.84	4,639.55	4,111.86	1.14	-0.25	0.130
50.00	-40.47	-6.74	0.00	-458.3	0.00	458.26	3,959.48	1,008.37	4,396.77	3,933.24	1.41	-0.28	0.127
55.00	-39.02	-6.65	0.00	-424.6	0.00	424.55	3,888.20	980.90	4,160.52	3,756.41	1.72	-0.31	0.123
60.00	-37.60	-6.56	0.00	-391.3	0.00	391.29	3,814.88	953.43	3,930.79	3,581.54	2.07	-0.35	0.119
65.00	-36.21	-6.47	0.00	-358.5	0.00	358.49	3,739.51	925.96	3,707.59	3,408.81	2.45	-0.39	0.115
70.00	-34.84	-6.39	0.00	-326.2	0.00	326.16	3,662.08	898.49	3,490.91	3,238.38	2.88	-0.42	0.110
73.00	-34.02	-6.33	0.00	-307.0	0.00	306.98	3,614.65	882.01	3,364.03	3,137.29	3.15	-0.45	0.107
75.00	-33.20	-6.27	0.00	-294.3	0.00	294.32	3,582.61	871.03	3,280.75	3,070.41	3.34	-0.46	0.105
78.50	-31.78	-6.21	0.00	-272.4	0.00	272.37	2,803.83	721.80	2,703.37	2,392.99	3.69	-0.49	0.125
80.00	-31.43	-6.15	0.00	-263.0	0.00	263.05	2,786.75	714.93	2,652.18	2,355.62	3.85	-0.5	0.123
85.00	-30.26	-6.09	0.00	-232.3	0.00	232.30	2,728.50	692.04	2,485.09	2,231.98	4.39	-0.54	0.115
86.00	-29.95	-5.96	0.00	-226.0	0.00	225.95	2,716.60	687.46	2,452.32	2,207.43	4.50	-0.55	0.113
89.00	-28.72	-5.84	0.00	-208.1	0.00	208.07	2,680.42	673.73	2,355.33	2,134.18	4.86	-0.57	0.108
90.00	-28.50	-5.78	0.00	-202.2	0.00	202.23	2,668.19	669.15	2,323.43	2,109.89	4.98	-0.58	0.107
95.00	-27.41	-5.70	0.00	-173.3	0.00	173.33	2,605.84	646.26	2,167.21	1,989.53	5.61	-0.62	0.098
97.50	-25.95	-5.34	0.00	-158.1	0.00	158.08	2,573.90	634.81	2,091.13	1,930.05	5.93	-0.64	0.092
100.00	-25.43	-5.30	0.00	-144.7	0.00	144.73	2,541.44	623.37	2,016.42	1,871.06	6.27	-0.65	0.087
101.00	-23.23	-4.86	0.00	-139.4	0.00	139.43	2,528.32	618.79	1,986.91	1,847.61	6.41	-0.66	0.085
105.00	-22.40	-4.77	0.00	-120.0	0.00	119.98	2,474.99	600.48	1,871.07	1,754.65	6.97	-0.69	0.077
108.75	-21.65	-4.71	0.00	-102.1	0.00	102.09	2,423.81	583.31	1,765.62	1,668.80	7.52	-0.71	0.070
110.00	-18.16	-4.04	0.00	-96.2	0.00	96.20	2,406.50	577.59	1,731.16	1,640.47	7.71	-0.72	0.066
113.00	-17.30	-3.98	0.00	-84.1	0.00	84.08	1,786.92	458.92	1,366.00	1,211.99	8.17	-0.73	0.079
115.00	-16.96	-3.89	0.00	-76.1	0.00	76.13	1,768.50	451.59	1,322.75	1,180.21	8.48	-0.74	0.074
120.00	-12.24	-3.05	0.00	-56.7	0.00	56.66	1,721.02	433.28	1,217.66	1,101.60	9.27	-0.77	0.059
125.00	-11.51	-2.95	0.00	-41.4	0.00	41.40	1,671.50	414.97	1,116.92	1,024.32	10.09	-0.8	0.047
130.00	-10.82	-2.88	0.00	-26.7	0.00	26.67	1,619.93	396.65	1,020.53	948.55	10.94	-0.81	0.035
132.00	-6.59	-1.85	0.00	-20.9	0.00	20.91	1,598.72	389.33	983.19	918.69	11.28	-0.82	0.027
135.00	-6.31	-1.80	0.00	-15.4	0.00	15.37	1,566.31	378.34	928.49	874.44	11.80	-0.83	0.022
138.00	-5.47	-1.67	0.00	-10.0	0.00	9.98	1,533.15	367.35	875.35	830.84	12.32	-0.83	0.016
140.00	-2.44	-0.72	0.00	-6.6	0.00	6.65	1,510.64	360.03	840.79	802.17	12.67	-0.83	0.010
145.00	-2.06	-0.66	0.00	-3.0	0.00	3.04	1,446.60	341.72	757.45	728.72	13.55	-0.84	0.006
148.00	0.00	-0.63	0.00	-1.1	0.00	1.06	1,400.09	330.73	709.53	682.38	14.07	-0.84	0.002

EQUIVALENT LATERAL FORCES METHOD ANALYSIS

(Based on ASCE7-16 Chapters 11, 12 and 15)

Spectral Response Acceleration for Short Period (S_S):	0.205
Spectral Response Acceleration at 1.0 Second Period (S_1):	0.054
Long-Period Transition Period (T_L – Seconds):	6
Importance Factor (I_e):	1.000
Site Coefficient F_a:	1.600
Site Coefficient F_v:	2.400
Response Modification Coefficient (R):	1.500
Design Spectral Response Acceleration at Short Period (S_{ds}):	0.219
Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.086
Seismic Response Coefficient (C_s):	0.030
Upper Limit C_S:	0.030
Lower Limit C_S:	0.030
Period based on Rayleigh Method (sec):	2.170
Redundancy Factor (p):	1.000
Seismic Force Distribution Exponent (k):	1.840
Total Unfactored Dead Load:	60.900 k
Seismic Base Shear (E):	1.830 k

1.2D + 1.0Ev + 1.0Eh Normal **Seismic**

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
41	146.5	223	2,129	0.009	17	278
40	142.5	386	3,502	0.015	27	480
39	139	184	1,593	0.007	12	229
38	136.5	281	2,356	0.010	18	350
37	133.5	288	2,313	0.010	18	358
36	131	273	2,119	0.009	17	339
35	127.5	694	5,131	0.022	40	863
34	122.5	726	4,986	0.021	39	903
33	117.5	852	5,422	0.023	43	1,060
32	114	346	2,081	0.009	16	430
31	111.5	856	4,946	0.021	39	1,065
30	109.375	364	2,029	0.009	16	453
29	106.875	757	4,044	0.017	32	941
28	103	821	4,099	0.018	32	1,021
27	100.5	207	990	0.004	8	258
26	98.75	522	2,415	0.010	19	650
25	96.25	538	2,372	0.010	19	669
24	92.5	1,093	4,479	0.019	35	1,359
23	89.5	221	853	0.004	7	275
22	87.5	669	2,476	0.011	19	832
21	85.5	230	815	0.004	6	286
20	82.5	1,162	3,859	0.017	30	1,445
19	79.25	353	1,089	0.005	9	439
18	76.75	1,416	4,118	0.018	32	1,761
17	74	820	2,230	0.010	17	1,019
16	71.5	806	2,058	0.009	16	1,003
15	67.5	1,365	3,135	0.014	25	1,697
14	62.5	1,391	2,775	0.012	22	1,731
13	57.5	1,418	2,426	0.010	19	1,764
12	52.5	1,445	2,091	0.009	16	1,797
11	47.5	1,471	1,772	0.008	14	1,830
10	42.5	2,831	2,780	0.012	22	3,521
9	39.25	861	731	0.003	6	1,071
8	36.75	1,298	976	0.004	8	1,614

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
7	32.5	1,885	1,130	0.005	9	2,344
6	27.5	1,920	847	0.004	7	2,388
5	22.5	1,956	597	0.003	5	2,432
4	17.5	1,991	383	0.002	3	2,476
3	12.5	2,027	210	0.001	2	2,520
2	7.5	2,062	84	0.000	1	2,565
1	2.5	2,098	11	0.000	0	2,609
Generic 18' Dipole	148	55	535	0.002	4	68
Generic 8' Omni	148	25	243	0.001	2	31
Generic 8' Dipole	148	25	243	0.001	2	31
Generic 48" x 8" Panel	148	240	2,333	0.010	18	298
Flat Low Profile Platform	148	1,500	14,581	0.063	114	1,866
Flat Low Profile Platform	140	1,500	13,166	0.056	103	1,866
Commscope CBC78T-DS-43-2X	140	62	545	0.002	4	77
Samsung Outdoor CBRS 20W RRH –Clip-on Antenna	140	13	116	0.000	1	16
Samsung RT4401-48A	140	56	490	0.002	4	69
Samsung B2/B66A RRH-BR049	140	253	2,222	0.010	17	315
Samsung B5/B13 RRH-BR04C	140	211	1,851	0.008	15	262
RFS DB-C1-12C-24AB-0Z	140	32	281	0.001	2	40
Samsung MT6407-77A	140	245	2,149	0.009	17	304
Commscope LNX-6514DS-A1M	140	39	341	0.002	3	48
Andrew LNX-8513DS-A1M	140	78	688	0.003	5	98
Commscope JAHH-65B-R3B	140	364	3,191	0.014	25	452
Collar	138	560	4,787	0.020	38	696
Collar	89	560	2,138	0.009	17	696
Powerwave Allgon LGP13519	132	32	251	0.001	2	40
Powerwave Allgon TT19-08BP111-001	132	96	756	0.003	6	119
Raycap DC6-48-60-18-8F ("Squid")	132	64	501	0.002	4	79
Ericsson Radio 4449 B13, B5	132	212	1,668	0.007	13	263
Ericsson RRUS A2 B2	132	66	520	0.002	4	82
Ericsson RRUS 32 B30 (53 lbs)	132	159	1,253	0.005	10	198
Ericsson RRUS-12 B2	132	174	1,371	0.006	11	216
KMW AM-X-CD-14-65-00T-RET	132	109	860	0.004	7	136
Commscope SBNHH-1D65A	132	100	792	0.003	6	125
Generic Mount Reinforcement	132	200	1,576	0.007	12	249
Kathrein Scala 80010964	132	251	1,980	0.008	16	313
Generic Flat Platform with Handrails	132	2,500	19,694	0.084	154	3,109
Generic Flat Platform with Handrails	110	2,500	14,088	0.060	110	3,109
Ericsson Radio 4460 B25+B66	120	436	2,883	0.012	23	542
Ericsson Air6449 B41	120	416	2,751	0.012	22	517
RFS APX16DWV-16DWVS-E-A20	120	163	1,076	0.005	8	202
Generic Square Low Profile Platform	120	2,863	18,930	0.081	148	3,561
Commscope RDIDC-9181-PF-48	110	22	123	0.000	1	27
Fujitsu TA08025-B604	110	192	1,080	0.005	8	238
Fujitsu TA08025-B605	110	225	1,268	0.005	10	280
JMA Wireless MX08FRO665-21	110	194	1,090	0.005	9	241
Flat Platform w/ Handrails	101	2,000	9,634	0.041	76	2,487
Alcatel-Lucent 800 MHz 2X50W RRH w/ Filter	97.5	192	867	0.004	7	239
Alcatel-Lucent 1900 MHz 4X45 RRH	97.5	180	813	0.004	6	224
Alcatel-Lucent TD-RRH8x20-25 w/ Solar Shield	97.5	210	948	0.004	7	261
RFS APXV9TM14-ALU-I20	97.5	165	746	0.003	6	206
RFS APXVSPP18-C-A20	97.5	171	772	0.003	6	213
RFS APXV18-206517S-C	86	79	284	0.001	2	99
Generic GPS	73	10	27	0.000	0	12
		60,904	232,953	1.000	1,827	75,748

0.9D - 1.0Ev + 1.0Eh Normal **Seismic (Reduced DL)**

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
41	146.5	223	2,129	0.009	17	191
40	142.5	386	3,502	0.015	27	331

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
39	139	184	1,593	0.007	12	157
38	136.5	281	2,356	0.010	18	241
37	133.5	288	2,313	0.010	18	246
36	131	273	2,119	0.009	17	234
35	127.5	694	5,131	0.022	40	594
34	122.5	726	4,986	0.021	39	622
33	117.5	852	5,422	0.023	43	730
32	114	346	2,081	0.009	16	296
31	111.5	856	4,946	0.021	39	733
30	109.375	364	2,029	0.009	16	312
29	106.875	757	4,044	0.017	32	648
28	103	821	4,099	0.018	32	703
27	100.5	207	990	0.004	8	178
26	98.75	522	2,415	0.010	19	447
25	96.25	538	2,372	0.010	19	461
24	92.5	1,093	4,479	0.019	35	936
23	89.5	221	853	0.004	7	189
22	87.5	669	2,476	0.011	19	573
21	85.5	230	815	0.004	6	197
20	82.5	1,162	3,859	0.017	30	995
19	79.25	353	1,089	0.005	9	302
18	76.75	1,416	4,118	0.018	32	1,212
17	74	820	2,230	0.010	17	702
16	71.5	806	2,058	0.009	16	690
15	67.5	1,365	3,135	0.014	25	1,169
14	62.5	1,391	2,775	0.012	22	1,191
13	57.5	1,418	2,426	0.010	19	1,214
12	52.5	1,445	2,091	0.009	16	1,237
11	47.5	1,471	1,772	0.008	14	1,260
10	42.5	2,831	2,780	0.012	22	2,424
9	39.25	861	731	0.003	6	738
8	36.75	1,298	976	0.004	8	1,111
7	32.5	1,885	1,130	0.005	9	1,614
6	27.5	1,920	847	0.004	7	1,644
5	22.5	1,956	597	0.003	5	1,674
4	17.5	1,991	383	0.002	3	1,705
3	12.5	2,027	210	0.001	2	1,735
2	7.5	2,062	84	0.000	1	1,766
1	2.5	2,098	11	0.000	0	1,796
Generic 18' Dipole	148	55	535	0.002	4	47
Generic 8' Omni	148	25	243	0.001	2	21
Generic 8' Dipole	148	25	243	0.001	2	21
Generic 48" x 8" Panel	148	240	2,333	0.010	18	206
Flat Low Profile Platform	148	1,500	14,581	0.063	114	1,284
Flat Low Profile Platform	140	1,500	13,166	0.056	103	1,284
Commscope CBC78T-DS-43-2X	140	62	545	0.002	4	53
Samsung Outdoor CBRS 20W RRH –Clip-on Antenna	140	13	116	0.000	1	11
Samsung RT4401-48A	140	56	490	0.002	4	48
Samsung B2/B66A RRH-BR049	140	253	2,222	0.010	17	217
Samsung B5/B13 RRH-BR04C	140	211	1,851	0.008	15	181
RFS DB-C1-12C-24AB-0Z	140	32	281	0.001	2	27
Samsung MT6407-77A	140	245	2,149	0.009	17	210
Commscope LNX-6514DS-A1M	140	39	341	0.002	3	33
Andrew LNX-8513DS-A1M	140	78	688	0.003	5	67
Commscope JAHH-65B-R3B	140	364	3,191	0.014	25	311
Collar	138	560	4,787	0.020	38	480
Collar	89	560	2,138	0.009	17	480
Powerwave Allgon LGP13519	132	32	251	0.001	2	27
Powerwave Allgon TT19-08BP111-001	132	96	756	0.003	6	82
Raycap DC6-48-60-18-8F ("Squid")	132	64	501	0.002	4	54
Ericsson Radio 4449 B13, B5	132	212	1,668	0.007	13	181
Ericsson RRUS A2 B2	132	66	520	0.002	4	57
Ericsson RRUS 32 B30 (53 lbs)	132	159	1,253	0.005	10	136
Ericsson RRUS-12 B2	132	174	1,371	0.006	11	149
KMW AM-X-CD-14-65-00T-RET	132	109	860	0.004	7	94
Commscope SBNHH-1D65A	132	100	792	0.003	6	86
Generic Mount Reinforcement	132	200	1,576	0.007	12	171
Kathrein Scala 80010964	132	251	1,980	0.008	16	215
Generic Flat Platform with Handrails	132	2,500	19,694	0.084	154	2,141

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
Generic Flat Platform with Handrails	110	2,500	14,088	0.060	110	2,141
Ericsson Radio 4460 B25+B66	120	436	2,883	0.012	23	373
Ericsson Air6449 B41	120	416	2,751	0.012	22	356
RFS APX16DWV-16DWVS-E-A20	120	163	1,076	0.005	8	139
Generic Square Low Profile Platform	120	2,863	18,930	0.081	148	2,451
Commscope RDIDC-9181-PF-48	110	22	123	0.000	1	19
Fujitsu TA08025-B604	110	192	1,080	0.005	8	164
Fujitsu TA08025-B605	110	225	1,268	0.005	10	193
JMA Wireless MX08FRO665-21	110	194	1,090	0.005	9	166
Flat Platform w/ Handrails	101	2,000	9,634	0.041	76	1,713
Alcatel-Lucent 800 MHz 2X50W RRH w/ Filter	97.5	192	867	0.004	7	164
Alcatel-Lucent 1900 MHz 4X45 RRH	97.5	180	813	0.004	6	154
Alcatel-Lucent TD-RRH8x20-25 w/ Solar Shield	97.5	210	948	0.004	7	180
RFS APXV9TM14-ALU-I20	97.5	165	746	0.003	6	142
RFS APXVSPP18-C-A20	97.5	171	772	0.003	6	146
RFS APXV18-206517S-C	86	79	284	0.001	2	68
Generic GPS	73	10	27	0.000	0	9
		60,904	232,953	1.000	1,827	52,150

1.2D + 1.0Ev + 1.0Eh Normal **Seismic**

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (fr-kips)	Mu Mx (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (kips)	Phi Mn (kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-73.14	-1.83	0.00	-215.87	0.00	215.87	6,758.62	1,686.37	9,223	8,416.93	0.00	0.00	0.04
5.00	-70.57	-1.84	0.00	-206.72	0.00	206.72	6,657.98	1,649.74	8,827	8,110.05	0.00	-0.01	0.04
10.00	-68.05	-1.84	0.00	-197.53	0.00	197.53	6,555.29	1,613.12	8,439	7,806.21	0.01	-0.01	0.04
15.00	-65.58	-1.85	0.00	-188.32	0.00	188.32	6,450.55	1,576.49	8,060	7,505.59	0.03	-0.02	0.04
20.00	-63.14	-1.85	0.00	-179.07	0.00	179.07	6,343.77	1,539.87	7,690	7,208.36	0.06	-0.03	0.04
25.00	-60.76	-1.85	0.00	-169.82	0.00	169.82	6,234.93	1,503.25	7,329	6,914.68	0.09	-0.04	0.03
30.00	-58.41	-1.85	0.00	-160.57	0.00	160.57	6,124.05	1,466.62	6,976	6,624.72	0.13	-0.04	0.03
35.00	-56.80	-1.85	0.00	-151.33	0.00	151.33	6,011.12	1,430.00	6,632	6,338.64	0.18	-0.05	0.03
38.50	-55.73	-1.84	0.00	-144.87	0.00	144.87	5,930.85	1,404.36	6,396	6,140.79	0.22	-0.06	0.03
40.00	-52.21	-1.82	0.00	-142.11	0.00	142.11	5,896.14	1,393.37	6,297	6,056.62	0.24	-0.06	0.03
45.00	-50.38	-1.81	0.00	-133.00	0.00	133.00	4,028.71	1,035.84	4,640	4,111.86	0.30	-0.07	0.05
50.00	-48.58	-1.80	0.00	-123.94	0.00	123.94	3,959.48	1,008.37	4,397	3,933.24	0.38	-0.07	0.04
55.00	-46.81	-1.79	0.00	-114.93	0.00	114.93	3,888.20	980.90	4,161	3,756.41	0.46	-0.08	0.04
60.00	-45.08	-1.77	0.00	-105.99	0.00	105.99	3,814.88	953.43	3,931	3,581.54	0.55	-0.09	0.04
65.00	-43.39	-1.75	0.00	-97.13	0.00	97.13	3,739.51	925.96	3,708	3,408.81	0.66	-0.10	0.04
70.00	-42.38	-1.74	0.00	-88.37	0.00	88.37	3,662.08	898.49	3,491	3,238.38	0.77	-0.11	0.04
73.00	-41.35	-1.72	0.00	-83.15	0.00	83.15	3,614.65	882.01	3,364	3,137.29	0.84	-0.12	0.04
75.00	-39.59	-1.69	0.00	-79.70	0.00	79.70	3,582.61	871.03	3,281	3,070.41	0.89	-0.12	0.04
78.50	-39.15	-1.69	0.00	-73.78	0.00	73.78	2,803.83	721.80	2,703	2,392.99	0.99	-0.13	0.05
80.00	-37.71	-1.66	0.00	-71.25	0.00	71.25	2,786.75	714.93	2,652	2,355.62	1.03	-0.13	0.04
85.00	-37.42	-1.65	0.00	-62.97	0.00	62.97	2,728.50	692.04	2,485	2,231.98	1.18	-0.15	0.04
86.00	-36.49	-1.63	0.00	-61.32	0.00	61.32	2,716.60	687.46	2,452	2,207.43	1.21	-0.15	0.04
89.00	-35.52	-1.61	0.00	-56.42	0.00	56.42	2,680.42	673.73	2,355	2,134.18	1.30	-0.15	0.04
90.00	-34.16	-1.57	0.00	-54.81	0.00	54.81	2,668.19	669.15	2,323	2,109.89	1.34	-0.16	0.04
95.00	-33.49	-1.56	0.00	-46.94	0.00	46.94	2,605.84	646.26	2,167	1,989.53	1.50	-0.17	0.04
97.50	-31.70	-1.50	0.00	-43.04	0.00	43.04	2,573.90	634.81	2,091	1,930.05	1.59	-0.17	0.04
100.00	-31.44	-1.50	0.00	-39.28	0.00	39.28	2,541.44	623.37	2,016	1,871.06	1.68	-0.18	0.03
101.00	-27.93	-1.38	0.00	-37.78	0.00	37.78	2,528.32	618.79	1,987	1,847.61	1.72	-0.18	0.03
105.00	-26.99	-1.35	0.00	-32.26	0.00	32.26	2,474.99	600.48	1,871	1,754.65	1.87	-0.19	0.03
108.75	-26.54	-1.33	0.00	-27.20	0.00	27.20	2,423.81	583.31	1,766	1,668.80	2.02	-0.19	0.03
110.00	-21.58	-1.14	0.00	-25.53	0.00	25.53	2,406.50	577.59	1,731	1,640.47	2.07	-0.19	0.03
113.00	-21.15	-1.13	0.00	-22.10	0.00	22.10	1,786.92	458.92	1,366	1,211.99	2.19	-0.20	0.03
115.00	-20.09	-1.08	0.00	-19.85	0.00	19.85	1,768.50	451.59	1,323	1,180.21	2.28	-0.20	0.03
120.00	-14.36	-0.82	0.00	-14.45	0.00	14.45	1,721.02	433.28	1,218	1,101.60	2.49	-0.21	0.02
125.00	-13.50	-0.78	0.00	-10.34	0.00	10.34	1,671.50	414.97	1,117	1,024.32	2.71	-0.21	0.02
130.00	-13.16	-0.76	0.00	-6.44	0.00	6.44	1,619.93	396.65	1,021	948.55	2.94	-0.22	0.02
132.00	-7.87	-0.48	0.00	-4.92	0.00	4.92	1,598.72	389.33	983	918.69	3.03	-0.22	0.01
135.00	-7.52	-0.46	0.00	-3.48	0.00	3.48	1,566.31	378.34	928	874.44	3.17	-0.22	0.01
138.00	-6.60	-0.41	0.00	-2.10	0.00	2.10	1,533.15	367.35	875	830.84	3.31	-0.22	0.01
140.00	-2.57	-0.17	0.00	-1.28	0.00	1.28	1,510.64	360.03	841	802.17	3.40	-0.22	0.00
145.00	-2.29	-0.15	0.00	-0.45	0.00	0.45	1,446.60	341.72	757	728.72	3.64	-0.22	0.00

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (fr-kips)	Mu Mx (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (kips)	Phi Mn (kips)	Total Deflect (in)	Rotation (deg)	Ratio
148.00	0.00	-0.14	0.00	0.00	0.00	0.00	1,400.09	330.73	710	682.38	3.78	-0.22	0.00

0.9D - 1.0Ev + 1.0Eh Normal **Seismic (Reduced DL)**

CALCULATED FORCES

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (fr-kips)	Mu Mx (ft-kips)	Resultant Moment (ft-kips)	Phi Pn (kips)	Phi Vn (kips)	Phi Tn (kips)	Phi Mn (kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-50.35	-1.83	0.00	-213.09	0.00	213.09	6,758.62	1,686.37	9,223	8,416.93	0.00	0.00	0.03
5.00	-48.59	-1.83	0.00	-203.95	0.00	203.95	6,657.98	1,649.74	8,827	8,110.05	0.00	-0.01	0.03
10.00	-46.85	-1.84	0.00	-194.78	0.00	194.78	6,555.29	1,613.12	8,439	7,806.21	0.01	-0.01	0.03
15.00	-45.15	-1.84	0.00	-185.59	0.00	185.59	6,450.55	1,576.49	8,060	7,505.59	0.03	-0.02	0.03
20.00	-43.47	-1.84	0.00	-176.40	0.00	176.40	6,343.77	1,539.87	7,690	7,208.36	0.06	-0.03	0.03
25.00	-41.83	-1.84	0.00	-167.20	0.00	167.20	6,234.93	1,503.25	7,329	6,914.68	0.09	-0.03	0.03
30.00	-40.21	-1.83	0.00	-158.01	0.00	158.01	6,124.05	1,466.62	6,976	6,624.72	0.13	-0.04	0.03
35.00	-39.10	-1.83	0.00	-148.85	0.00	148.85	6,011.12	1,430.00	6,632	6,338.64	0.18	-0.05	0.03
38.50	-38.37	-1.82	0.00	-142.45	0.00	142.45	5,930.85	1,404.36	6,396	6,140.79	0.22	-0.05	0.03
40.00	-35.94	-1.80	0.00	-139.72	0.00	139.72	5,896.14	1,393.37	6,297	6,056.62	0.23	-0.06	0.03
45.00	-34.68	-1.79	0.00	-130.70	0.00	130.70	4,028.71	1,035.84	4,640	4,111.86	0.30	-0.06	0.04
50.00	-33.44	-1.78	0.00	-121.73	0.00	121.73	3,959.48	1,008.37	4,397	3,933.24	0.37	-0.07	0.04
55.00	-32.23	-1.77	0.00	-112.83	0.00	112.83	3,888.20	980.90	4,161	3,756.41	0.45	-0.08	0.04
60.00	-31.04	-1.75	0.00	-104.01	0.00	104.01	3,814.88	953.43	3,931	3,581.54	0.54	-0.09	0.04
65.00	-29.87	-1.73	0.00	-95.27	0.00	95.27	3,739.51	925.96	3,708	3,408.81	0.65	-0.10	0.04
70.00	-29.18	-1.71	0.00	-86.65	0.00	86.65	3,662.08	898.49	3,491	3,238.38	0.76	-0.11	0.04
73.00	-28.47	-1.70	0.00	-81.51	0.00	81.51	3,614.65	882.01	3,364	3,137.29	0.83	-0.12	0.03
75.00	-27.26	-1.66	0.00	-78.12	0.00	78.12	3,582.61	871.03	3,281	3,070.41	0.88	-0.12	0.03
78.50	-26.95	-1.66	0.00	-72.30	0.00	72.30	2,803.83	721.80	2,703	2,392.99	0.97	-0.13	0.04
80.00	-25.96	-1.63	0.00	-69.81	0.00	69.81	2,786.75	714.93	2,652	2,355.62	1.01	-0.13	0.04
85.00	-25.76	-1.62	0.00	-61.68	0.00	61.68	2,728.50	692.04	2,485	2,231.98	1.16	-0.14	0.04
86.00	-25.12	-1.60	0.00	-60.06	0.00	60.06	2,716.60	687.46	2,452	2,207.43	1.19	-0.14	0.04
89.00	-24.45	-1.58	0.00	-55.25	0.00	55.25	2,680.42	673.73	2,355	2,134.18	1.28	-0.15	0.04
90.00	-23.52	-1.54	0.00	-53.67	0.00	53.67	2,668.19	669.15	2,323	2,109.89	1.31	-0.15	0.03
95.00	-23.06	-1.53	0.00	-45.96	0.00	45.96	2,605.84	646.26	2,167	1,989.53	1.48	-0.16	0.03
97.50	-21.82	-1.47	0.00	-42.14	0.00	42.14	2,573.90	634.81	2,091	1,930.05	1.57	-0.17	0.03
100.00	-21.64	-1.47	0.00	-38.46	0.00	38.46	2,541.44	623.37	2,016	1,871.06	1.66	-0.17	0.03
101.00	-19.23	-1.35	0.00	-36.99	0.00	36.99	2,528.32	618.79	1,987	1,847.61	1.69	-0.17	0.03
105.00	-18.58	-1.32	0.00	-31.58	0.00	31.58	2,474.99	600.48	1,871	1,754.65	1.84	-0.18	0.03
108.75	-18.27	-1.31	0.00	-26.63	0.00	26.63	2,423.81	583.31	1,766	1,668.80	1.99	-0.19	0.02
110.00	-14.85	-1.12	0.00	-25.00	0.00	25.00	2,406.50	577.59	1,731	1,640.47	2.04	-0.19	0.02
113.00	-14.56	-1.10	0.00	-21.64	0.00	21.64	1,786.92	458.92	1,366	1,211.99	2.16	-0.19	0.03
115.00	-13.83	-1.06	0.00	-19.44	0.00	19.44	1,768.50	451.59	1,323	1,180.21	2.24	-0.20	0.02
120.00	-9.89	-0.80	0.00	-14.15	0.00	14.15	1,721.02	433.28	1,218	1,101.60	2.45	-0.20	0.02
125.00	-9.29	-0.76	0.00	-10.13	0.00	10.13	1,671.50	414.97	1,117	1,024.32	2.67	-0.21	0.02
130.00	-9.06	-0.75	0.00	-6.31	0.00	6.31	1,619.93	396.65	1,021	948.55	2.89	-0.21	0.01
132.00	-5.42	-0.47	0.00	-4.82	0.00	4.82	1,598.72	389.33	983	918.69	2.98	-0.22	0.01
135.00	-5.18	-0.45	0.00	-3.41	0.00	3.41	1,566.31	378.34	928	874.44	3.11	-0.22	0.01
138.00	-4.54	-0.40	0.00	-2.06	0.00	2.06	1,533.15	367.35	875	830.84	3.25	-0.22	0.01
140.00	-1.77	-0.16	0.00	-1.26	0.00	1.26	1,510.64	360.03	841	802.17	3.34	-0.22	0.00
145.00	-1.58	-0.15	0.00	-0.44	0.00	0.44	1,446.60	341.72	757	728.72	3.57	-0.22	0.00
148.00	0.00	-0.14	0.00	0.00	0.00	0.00	1,400.09	330.73	710	682.38	3.71	-0.22	0.00

ANALYSIS SUMMARY

	Reactions						Max Usage	
Load Case	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)	Elev (ft)	Interaction Ratio
1.2D + 1.0W Normal	35.68	0.00	73.05	0.00	0.00	3871.77	45.00	0.58
0.9D + 1.0W Normal	35.66	0.00	54.78	0.00	0.00	3832.11	45.00	0.57
1.2D + 1.0Di + 1.0Wi Normal	8.65	0.00	94.99	0.00	0.00	932.36	45.00	0.15
1.2D + 1.0Ev + 1.0Eh Normal	1.85	0.00	73.14	0.00	0.00	215.87	45.00	0.04
0.9D - 1.0Ev + 1.0Eh Normal	1.84	0.00	50.35	0.00	0.00	213.09	45.00	0.04
1.0D + 1.0W Service Normal	7.59	0.00	60.90	0.00	0.00	819.04	45.00	0.13

MOUNT ANALYSIS REPORT

September 15, 2021

Dish Wireless Site Name	BOHVN00146A
Dish Wireless Site Number	BOHVN00146A
ATC Site Name	Madison CT 6, CT
ATC Site Number	302540
Infinigy Job Number	1197-F0001-B
Client	ATC
Carrier	Dish Wireless
Site Location	8 Old 79 Madison, CT 06443-2685 New Haven County 41.2855 N NAD83 72.6013 W NAD83
Mount Type	8.0 ft Platform
Mount Elevation	110.0 ft AGL
Structural Usage Ratio	**29.3%**
Overall Result	**Pass**

The enclosed mount structural analysis has been performed in accordance with the 2018 Connecticut State Building Code (2015 IBC) based on an ultimate 3-second gust wind speed of 123 mph. The evaluation criteria and applicable codes are presented in the next section of this report.



CONTENTS

1. INTRODUCTION

Infinigy performed a structural analysis on the Dish Wireless proposed telecommunication equipment supporting Platform mounted to the existing structure located at the aforementioned address. All referenced supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The mount was analyzed using Risa-3D version 17.0.4 analysis software.

2. DESIGN/ANALYSIS PARAMETERS

Wind Speed	123 mph (3-Second Gust)
Wind Speed w/ ice	50 mph (3-Second Gust) w/ 1" ice
Code / Standard	TIA-222-H
Adopted Code	2018 Connecticut State Building Code (2015 IBC)
Risk Category	II
Exposure Category	B
Topographic Category	1
Seismic Spectral Response	S_s = 0.205 g / S_1 = 0.054 g
Live Load Wind Speed	60 mph
Man Live Load at Mid/End Points	250 lbs
Man Live Load at Mount Pipes	500 lbs

3. PROPOSED LOADING CONFIGURATION - 110.0 ft. AGL Platform

Antenna Centerline (ft)	Qty.	Appurtenance Manufacturers	Appurtenance Models
110.0	3	JMA WIRELESS	MX08FRO665-21
	3	FUJITSU	TA08025-B605
	3	FUJITSU	TA08025-B604
	1	RAYCAP	RDIDC-9181-PF-48

4. SUPPORTING DOCUMENTATION

Proposed Loading	Dish Wireless Asset ID CT-ATC-T-302540 Rev 1, Site #BOHVN00146A, dated July 09, 2021
Mount Manufacturer Drawings	Commscope Document # MC-PK8-DSH, dated March 08, 2021
Structural Analysis Report	ATC, Asset #302540, dated August 9, 2021

5. RESULTS

Components	Capacity	Pass/Fail
Mount Pipes	18.5%	Pass
Horizontals	11.1%	Pass
Standoffs	28.0%	Pass
Handrails	22.2%	Pass
Connections	29.3%	Pass
MOUNT RATING =	**29.3%**	**Pass**

Notes:
1. See additional documentation in Appendix for calculations supporting the capacity consumed and detailed mount connection calculations.

6. RECOMMENDATIONS

Infinigy recommends installing Dish Wireless's proposed equipment loading configuration on the mount at 110.0 ft. The installation shall be performed in accordance with the construction documents issued for this site.

Binita Yadav
Project Engineer I | **INFINIGY**

7. ASSUMPTIONS

The antenna mounting system was properly fabricated, installed and maintained in accordance with its original design and manufacturer's specifications.
The configuration of antennas, mounts, and other appurtenances are as specified in the proposed loading configuration table.
All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
The analysis will require revisions if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
Steel grades have been assumed as follows, unless noted otherwise: Channel, Solid Round, Plate, Built-up Angle — ASTM A1011 36 KSI Structural Angle — ASTM A529 Gr. 50 HSS (Rectangular) — ASTM A500-B GR 46 HSS (Circular) — ASTM A500-B GR 42 Pipe — ASTM A500 Gr C Connection Bolts — ASTM A325 U-Bolts — ASTM A307
All bolted connections are pretensioned in accordance with Table 8.2 of the RCSC 2014 Standard

8. LIABILITY WAIVER AND LIMITATIONS

Our structural calculations are completed assuming all information provided to Infinigy is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition as erected and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report, Infinigy should be notified immediately to assess the impact on the results of this report.

Our evaluation is completed using industry standard methods and procedures. The structural results, conclusions and recommendations contained in this report are proprietary and should not be used by others as their own. Infinigy is not responsible for decisions made by others that are or are not based on the stated assumptions and conclusions in this report.

This report is an evaluation of the mount structure only and does not determine the adequacy of the supporting structure, other carrier mounts or cable mounting attachments. The analysis of these elements is outside the scope of this analysis, are assumed to be adequate for the purpose of this report and to have been installed per their manufacturer requirements. This document is not for construction purposes.



Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Rendered
BY		Sept 14, 2021 at 2:25 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Wire Frame
BY		Sept 14, 2021 at 2:26 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Section Sets
BY		Sept 14, 2021 at 3:21 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Member Shapes
BY		Sept 14, 2021 at 3:59 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Material Sets
BY		Sept 14, 2021 at 3:59 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Member Length (in) Displayed
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Lengths
BY		Sept 14, 2021 at 4:00 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 1, Self Weight
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Self-Weight
BY		Sept 14, 2021 at 4:01 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 2, Wind Load AZI 0
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Wind Load AZI 000
BY		Sept 14, 2021 at 4:02 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 5, Wind Load AZI 90
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Wind Load AZI 090
BY		Sept 14, 2021 at 4:03 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 14, Distr. Wind Load Z
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Distr. Wind Load AZI 000
BY		Sept 14, 2021 at 4:04 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 15, Distr. Wind Load X
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Distr. Wind Load AZI 090
BY		Sept 14, 2021 at 4:04 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 16, Ice Weight
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Ice Weight
BY		Sept 14, 2021 at 4:05 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 17, Ice Wind Load AZI 0
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Ice Wind Load AZI 000
BY		Sept 14, 2021 at 4:06 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 20, Ice Wind Load AZI 90
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Ice Wind Load AZI 090
BY		Sept 14, 2021 at 4:07 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 29, Distr. Ice Wind Load Z
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Distr.Ice Wind Load AZI 000
BY		Sept 14, 2021 at 4:08 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 30, Distr. Ice Wind Load X
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Distr.Ice Wind Load AZI 090
BY		Sept 14, 2021 at 4:08 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 31, Seismic Load Z
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Seismic Load AZI 000
BY		Sept 14, 2021 at 4:09 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: BLC 32, Seismic Load X
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Seismic Load AZI 090
BY		Sept 14, 2021 at 4:11 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Loads: LL - Live Load
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Non-Concurrent Live Loads
BY		Sept 14, 2021 at 4:12 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Member Code Checks Displayed (Enveloped)
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Bending Check
BY		Sept 14, 2021 at 4:13 PM
1197-F0001-B		BOHVN00146A_loaded.r3d



Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

Infinigy Engineering, PLLC	BOHVN00146A	Shear Check
BY		Sept 14, 2021 at 4:13 PM
1197-F0001-B		BOHVN00146A_loaded.r3d

Program Inputs

PROJECT INFORMATION	
Client:	ATC
Carrier:	Dish Wireless
Engineer:	Binita Yadav

SITE INFORMATION		
Risk Category:	II	
Exposure Category:	B	
Topo Factor Procedure:	Method 1, Category 1	
Site Class:	D - Stiff Soil (Assumed)	
Ground Elevation:	24.23	ft *Rev H

MOUNT INFORMATION		
Mount Type:	Platform	
Num Sectors:	3	
Centerline AGL:	110.00	ft
Tower Height AGL:	148.00	ft

TOPOGRAPHIC DATA		
Topo Feature:	N/A	
Slope Distance:	N/A	ft
Crest Distance:	N/A	ft
Crest Height:	N/A	ft

FACTORS		
Directionality Fact. (K_d):	0.950	
Ground Ele. Factor (K_e):	0.999	*Rev H Only
Rooftop Speed-Up (K_s):	1.000	*Rev H Only
Topographic Factor (K_{zt}):	1.000	
Gust Effect Factor (G_h):	1.000	

CODE STANDARDS		
Building Code:	2015 IBC	
TIA Standard:	TIA-222-H	
ASCE Standard:	ASCE 7-16	

WIND AND ICE DATA		
Ultimate Wind (V_{ult}):	123	mph
Design Wind (V):	N/A	mph
Ice Wind (V_{ice}):	50	mph
Base Ice Thickness (t_i):	1	in
Flat Pressure:	74.663	psf
Round Pressure:	44.798	psf
Ice Wind Pressure:	7.403	psf

SEISMIC DATA		
Short-Period Accel. (S_s):	0.205	g
1-Second Accel. (S_1):	0.054	g
Short-Period Design (S_{DS}):	0.218	
1-Second Design (S_{D1}):	0.086	
Short-Period Coeff. (F_a):	1.600	
1-Second Coeff. (F_v):	2.400	
Amplification Factor (A_s):	3.000	
Response Mod. Coeff. (R):	2.000	

INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless

Infinigy Load Calculator V2.1.7

Program Inputs

ELEVATION VIEW



PLAN VIEW



INFINIGY
FROM ZERO TO INFINIGY
the solutions are endless

Infinigy Load Calculator V2.1.7

APPURTENANCE INFORMATION

Appurtenance Name	Elevation	Qty.	K_a	q_z (psf)	EPA_N (ft^2)	EPA_T (ft^2)	Wind F_z (lbs)	Wind F_x (lbs)	Weight (lbs)	Seismic F (lbs)	Member (α sector)
JMA WIRELESS MX08FRO665-21	110.0	3	0.90	37.33	8.01	3.21	269.12	107.85	64.50	21.16	MP1
FUJITSU TA08025-B605	110.0	3	0.90	37.33	1.96	1.19	65.97	39.95	74.95	24.58	MP1
FUJITSU TA08025-B604	110.0	3	0.90	37.33	1.96	1.03	65.97	34.71	63.93	20.97	MP1
RAYCAP RDIDC-9181-PF-48	110.0	1	0.90	37.33	1.87	1.07	62.72	35.84	21.85	7.17	MP10

ASCE 7 Hazards Report

Address:
No Address at This Location

Standard:	ASCE/SEI 7-16	**Elevation:**	24.23 ft (NAVD 88)
Risk Category:	II	**Latitude:**	41.2855
Soil Class:	D - Default (see Section 11.4.3)	**Longitude:**	-72.6013



Wind

Results:

Wind Speed:	123 Vmph
10-year MRI	75 Vmph
25-year MRI	85 Vmph
50-year MRI	94 Vmph
100-year MRI	100 Vmph

Data Source:	ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2
Date Accessed:	Tue Sep 14 2021

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2. Glazed openings need not be protected against wind-borne debris.

Seismic

Site Soil Class: D - Default (see Section 11.4.3)

Results:

S_S :	0.205	S_{D1} :	0.086
S_1 :	0.054	T_L :	6
F_a :	1.6	PGA :	0.114
F_v :	2.4	PGA_M :	0.18
S_{MS} :	0.327	F_{PGA} :	1.571
S_{M1} :	0.129	I_e :	1
S_{DS} :	0.218	C_v :	0.709

Seismic Design Category B









Data Accessed: Tue Sep 14 2021

Date Source: USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness:	1.00 in.
Concurrent Temperature:	15 F
Gust Speed:	50 mph
Data Source:	Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8
Date Accessed:	Tue Sep 14 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	S3	P1	P3			Square Tubing	Beam	None	A500 GR.C	Typical
2	GA4	P9	P12		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
3	GA3	P10	P11			Grating Angle	Beam	None	A529 Gr. 50	Typical
4	P3	P7	P8			Corner Plates	Beam	None	A1011 36 ...	Typical
5	S2	P13	P14			Square Tubing	Beam	None	A500 GR.C	Typical
6	GA2	P20	P23		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
7	GA1	P21	P22			Grating Angle	Beam	None	A529 Gr. 50	Typical
8	P2	P18	P19			Corner Plates	Beam	None	A1011 36 ...	Typical
9	S1	P24	P25			Square Tubing	Beam	None	A500 GR.C	Typical
10	GA6	P31	P34		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
11	GA5	P32	P33			Grating Angle	Beam	None	A529 Gr. 50	Typical
12	P1	P29	P30			Corner Plates	Beam	None	A1011 36 ...	Typical
13	H1	N43	N44			Face Pipes(3.5...	Beam	None	A500 GR.C	Typical
14	MP1	N66	N60			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
15	MP3	N63	N57			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
16	HR1	N67	N68			Handrail	Beam	None	A500 GR.C	Typical
17	CA8	N114A	N113A		180	Handrail Conn...	Beam	None	A1011 36 ...	Typical
18	CA9	N112A	N111A		180	Handrail Conn...	Beam	None	A1011 36 ...	Typical
19	CA7	N116A	N115A		180	Handrail Conn...	Beam	None	A1011 36 ...	Typical
20	M32	N48A	N70A			RIGID	None	None	RIGID	Typical
21	M35	N45	N69A			RIGID	None	None	RIGID	Typical
22	M36	N51	N71A			RIGID	None	None	RIGID	Typical
23	M39A	N54	N72A			RIGID	None	None	RIGID	Typical
24	CA3	P4	N122A			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
25	CA4	N124B	P4			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
26	CA1	P15	N122B			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
27	CA2	N123A	P15			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
28	CA5	P26	N125			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
29	CA6	N126	P26			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
30	M64	N126A	N125A			RIGID	None	None	RIGID	Typical
31	M65	N126	N125A			RIGID	None	None	RIGID	Typical
32	M66	N129	N128			RIGID	None	None	RIGID	Typical
33	M67	N124B	N128			RIGID	None	None	RIGID	Typical
34	M68	N132	N131			RIGID	None	None	RIGID	Typical
35	M69	N123A	N131			RIGID	None	None	RIGID	Typical
36	M70	N133	N132A			RIGID	None	None	RIGID	Typical
37	M71	N122B	N132A			RIGID	None	None	RIGID	Typical
38	M72	N135	N134			RIGID	None	None	RIGID	Typical
39	M73	N125	N134			RIGID	None	None	RIGID	Typical
40	M74	N138	N137			RIGID	None	None	RIGID	Typical
41	M75	N122A	N137			PL 2.375x0.5	None	None	A36 Gr.36	Typical
42	MP2	N75	N74			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
43	M43	N72B	N76			RIGID	None	None	RIGID	Typical
44	M44	N73	N77			RIGID	None	None	RIGID	Typical
45	H3	N81A	N82A			Face Pipes(3.5...	Beam	None	A500 GR.C	Typical
46	MP7	N90	N88			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
47	MP9	N89	N87			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
48	HR3	N91	N92			Handrail	Beam	None	A500 GR.C	Typical
49	M52	N84	N94			RIGID	None	None	RIGID	Typical
50	M53	N83A	N93			RIGID	None	None	RIGID	Typical
51	M54	N85	N95			RIGID	None	None	RIGID	Typical

Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
52	M55	N86	N96			RIGID	None	None	RIGID	Typical
53	H2	N109	N110			Face Pipes(3.5...	Beam	None	A500 GR.C	Typical
54	MP4	N118	N116			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
55	MP6	N117	N115			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
56	HR2	N119	N120			Handrail	Beam	None	A500 GR.C	Typical
57	M66A	N112	N122			RIGID	None	None	RIGID	Typical
58	M67A	N111	N121			RIGID	None	None	RIGID	Typical
59	M68A	N113	N123			RIGID	None	None	RIGID	Typical
60	M69A	N114	N124			RIGID	None	None	RIGID	Typical
61	MP8	N132B	N131A			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
62	M68B	N129B	N133B			RIGID	None	None	RIGID	Typical
63	M69B	N130A	N134A			RIGID	None	None	RIGID	Typical
64	MP5	N138A	N137A			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
65	M71B	N135A	N139			RIGID	None	None	RIGID	Typical
66	M72B	N136	N140			RIGID	None	None	RIGID	Typical
67	MP10	N124A	N125B			Antenna Pipes	Column	Wide Flange	A500 GR.C	Typical
68	M68D	N122C	N123B			RIGID	None	None	RIGID	Typical

Hot Rolled Steel Design Parameters

	Label	Shape	Length[in]	Lbyy[in]	Lbzz[in]	Lcomp top[in]	Lcomp bot[in]	L-torqu...	Kyy	Kzz	Cb	Function
1	S3	Square Tubi...	40			Lbyy						Lateral
2	GA4	Grating Angle	27.295			Lbyy						Lateral
3	GA3	Grating Angle	27.295			Lbyy						Lateral
4	P3	Corner Plates	42			Lbyy						Lateral
5	S2	Square Tubi...	40			Lbyy						Lateral
6	GA2	Grating Angle	27.295			Lbyy						Lateral
7	GA1	Grating Angle	27.295			Lbyy						Lateral
8	P2	Corner Plates	42			Lbyy						Lateral
9	S1	Square Tubi...	40			Lbyy						Lateral
10	GA6	Grating Angle	27.295			Lbyy						Lateral
11	GA5	Grating Angle	27.295			Lbyy						Lateral
12	P1	Corner Plates	42			Lbyy						Lateral
13	H1	Face Pipes(...	96			Lbyy						Lateral
14	MP1	Antenna Pip...	96			Lbyy						Lateral
15	MP3	Antenna Pip...	96			Lbyy						Lateral
16	HR1	Handrail	96			Lbyy						Lateral
17	CA8	Handrail Co...	42			Lbyy						Lateral
18	CA9	Handrail Co...	42			Lbyy						Lateral
19	CA7	Handrail Co...	42			Lbyy						Lateral
20	CA3	Channel(3.3...	33			Lbyy						Lateral
21	CA4	Channel(3.3...	33			Lbyy						Lateral
22	CA1	Channel(3.3...	33			Lbyy						Lateral
23	CA2	Channel(3.3...	33			Lbyy						Lateral
24	CA5	Channel(3.3...	33			Lbyy						Lateral
25	CA6	Channel(3.3...	33			Lbyy						Lateral
26	M75	PL 2.375x0.5	1.5			Lbyy						Lateral
27	MP2	Antenna Pip...	96			Lbyy						Lateral
28	H3	Face Pipes(...	96			Lbyy						Lateral
29	MP7	Antenna Pip...	96			Lbyy						Lateral
30	MP9	Antenna Pip...	96			Lbyy						Lateral

Hot Rolled Steel Design Parameters (Continued)

	Label	Shape	Length[in]	Lbyy[in]	Lbzz[in]	Lcomp top[in]	Lcomp bot[in]	L-torqu...	Kyy	Kzz	Cb	Function
31	HR3	Handrail	96			Lbyy						Lateral
32	H2	Face Pipes(...	96			Lbyy						Lateral
33	MP4	Antenna Pip...	96			Lbyy						Lateral
34	MP6	Antenna Pip...	96			Lbyy						Lateral
35	HR2	Handrail	96			Lbyy						Lateral
36	MP8	Antenna Pip...	96			Lbyy						Lateral
37	MP5	Antenna Pip...	96			Lbyy						Lateral
38	MP10	Antenna Pip...	24			Lbyy						Lateral

Member Advanced Data

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
1	S3						Yes				None
2	GA4						Yes				None
3	GA3						Yes				None
4	P3	BenPIN	BenPIN				Yes	Default			None
5	S2						Yes				None
6	GA2						Yes				None
7	GA1						Yes				None
8	P2	BenPIN	BenPIN				Yes	Default			None
9	S1						Yes	Default			None
10	GA6						Yes				None
11	GA5						Yes				None
12	P1	BenPIN	BenPIN				Yes	Default			None
13	H1						Yes				None
14	MP1						Yes	** NA **	+y+3		None
15	MP3						Yes	** NA **	+y+3		None
16	HR1						Yes				None
17	CA8	OOOOOX	OOOOOX				Yes				None
18	CA9	OOOOOX	OOOOOX				Yes				None
19	CA7	OOOOOX	OOOOOX				Yes	Default			None
20	M32						Yes	** NA **			None
21	M35						Yes	** NA **			None
22	M36						Yes	** NA **			None
23	M39A						Yes	** NA **			None
24	CA3						Yes	Default			None
25	CA4						Yes	Default			None
26	CA1						Yes	Default			None
27	CA2						Yes	Default			None
28	CA5						Yes	Default			None
29	CA6						Yes	Default			None
30	M64	BenPIN					Yes	** NA **			None
31	M65						Yes	** NA **			None
32	M66	BenPIN					Yes	** NA **			None
33	M67						Yes	** NA **			None
34	M68	BenPIN					Yes	** NA **			None
35	M69						Yes	** NA **			None
36	M70	BenPIN					Yes	** NA **			None
37	M71						Yes	** NA **			None
38	M72	BenPIN					Yes	** NA **			None
39	M73						Yes	** NA **			None

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
40	M74	BenPIN					Yes	** NA **			None
41	M75						Yes	** NA **			None
42	MP2						Yes	** NA **	+y+3		None
43	M43						Yes	** NA **			None
44	M44						Yes	** NA **			None
45	H3						Yes				None
46	MP7						Yes	** NA **	+y+3		None
47	MP9						Yes	** NA **	+y+3		None
48	HR3						Yes				None
49	M52						Yes	** NA **			None
50	M53						Yes	** NA **			None
51	M54						Yes	** NA **			None
52	M55						Yes	** NA **			None
53	H2						Yes				None
54	MP4						Yes	** NA **	+y+3		None
55	MP6						Yes	** NA **	+y+3		None
56	HR2						Yes				None
57	M66A						Yes	** NA **			None
58	M67A						Yes	** NA **			None
59	M68A						Yes	** NA **			None
60	M69A						Yes	** NA **			None
61	MP8						Yes	** NA **	+y+3		None
62	M68B						Yes	** NA **			None
63	M69B						Yes	** NA **			None
64	MP5						Yes	** NA **	+y+3		None
65	M71B						Yes	** NA **			None
66	M72B						Yes	** NA **			None
67	MP10						Yes	** NA **			None
68	M68D						Yes	** NA **			None

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[LB]
1	General				
2	RIGID		30	36.1	0
3	Total General		30	36.1	0
4					
5	Hot Rolled Steel				
6	A1011 36 Ksi	C3.38x2.06x0.25	6	198	98.255
7	A1011 36 Ksi	PL6.5x0.375	3	126	87.09
8	A1011 36 Ksi	L6.6x4.46x0.25	3	126	96.558
9	A36 Gr.36	PL 2.375x0.5	1	1.5	.505
10	A500 GR.C	2.88x0.120	3	288	84.974
11	A500 GR.C	HSS4X4X6	3	120	162.653
12	A500 GR.C	Pipe3.5x0.165	3	288	141.202
13	A500 GR.C	PIPE 2.5	10	888	405.407
14	A529 Gr. 50	L2x2x4	6	163.8	43.838
15	Total HR Steel		38	2199.3	1120.482

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design Rules	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Corner Plates	PL6.5x0.375	Beam	None	A1011 36 Ksi	Typical	2.438	.029	8.582	.11
2	6"x0.37" Plate	Plate 6x.37	Beam	None	A1011 36 Ksi	Typical	2.22	.025	6.66	.097
3	Grating Angle	L2x2x4	Beam	None	A529 Gr. 50	Typical	.944	.346	.346	.021
4	Face Pipes(...	Pipe3.5x0.165	Beam	None	A500 GR.C	Typical	1.729	2.409	2.409	4.819
5	Antenna Pipes	PIPE 2.5	Column	Wide Flange	A500 GR.C	Typical	1.61	1.45	1.45	2.89
6	Channel(3.3...	C3.38x2.06x...	Beam	None	A1011 36 Ksi	Typical	1.75	.715	3.026	.034
7	Square Tubing	HSS4X4X6	Beam	None	A500 GR.C	Typical	4.78	10.3	10.3	17.5
8	Handrail Con...	L6.6x4.46x0....	Beam	None	A1011 36 Ksi	Typical	2.703	4.759	12.473	.055
9	Handrail	2.88x0.120	Beam	None	A500 GR.C	Typical	1.04	.993	.993	1.985

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed	Area(Me...	Surface(...
1	Self Weight	DL		-1			13		3	
2	Wind Load AZI 0	WLZ					26			
3	Wind Load AZI 30	None					26			
4	Wind Load AZI 60	None					26			
5	Wind Load AZI 90	WLX					26			
6	Wind Load AZI 120	None					26			
7	Wind Load AZI 150	None					26			
8	Wind Load AZI 180	None					26			
9	Wind Load AZI 210	None					26			
10	Wind Load AZI 240	None					26			
11	Wind Load AZI 270	None					26			
12	Wind Load AZI 300	None					26			
13	Wind Load AZI 330	None					26			
14	Distr. Wind Load Z	WLZ						68		
15	Distr. Wind Load X	WLX						68		
16	Ice Weight	OL1					13	68	3	
17	Ice Wind Load AZI 0	OL2					26			
18	Ice Wind Load AZI 30	None					26			
19	Ice Wind Load AZI 60	None					26			
20	Ice Wind Load AZI 90	OL3					26			
21	Ice Wind Load AZI 120	None					26			
22	Ice Wind Load AZI 150	None					26			
23	Ice Wind Load AZI 180	None					26			
24	Ice Wind Load AZI 210	None					26			
25	Ice Wind Load AZI 240	None					26			
26	Ice Wind Load AZI 270	None					26			
27	Ice Wind Load AZI 300	None					26			
28	Ice Wind Load AZI 330	None					26			
29	Distr. Ice Wind Load Z	OL2						68		
30	Distr. Ice Wind Load X	OL3						68		
31	Seismic Load Z	ELZ			-.328		13			
32	Seismic Load X	ELX	-.328				13			
33	Service Live Loads	LL				3				
34	Maintenance Load 1	LL				1				
35	Maintenance Load 2	LL				1				
36	Maintenance Load 3	LL				1				
37	Maintenance Load 4	LL				1				

Basic Load Cases (Continued)

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed	Area(Me...	Surface(...
38	Maintenance Load 5	LL				1				
39	Maintenance Load 6	LL				1				
40	Maintenance Load 7	LL				1				
41	Maintenance Load 8	LL				1				
42	Maintenance Load 9	LL				1				
43	Maintenance Load 10	LL				1				
44	BLC 1 Transient Area Loads	None						9		
45	BLC 16 Transient Area Loads	None						9		

Load Combinations

	Description	S...	P...	S...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...
1	1.4DL	Yes	Y		1	1.4																		
2	1.2DL + 1WL AZI 0	Yes	Y		1	1.2	2	1	14	1	15													
3	1.2DL + 1WL AZI 30	Yes	Y		1	1.2	3	1	14	.866	15	.5												
4	1.2DL + 1WL AZI 60	Yes	Y		1	1.2	4	1	14	.5	15	.866												
5	1.2DL + 1WL AZI 90	Yes	Y		1	1.2	5	1	14		15	1												
6	1.2DL + 1WL AZI 120	Yes	Y		1	1.2	6	1	14	-.5	15	.866												
7	1.2DL + 1WL AZI 150	Yes	Y		1	1.2	7	1	14	-.866	15	.5												
8	1.2DL + 1WL AZI 180	Yes	Y		1	1.2	8	1	14	-1	15													
9	1.2DL + 1WL AZI 210	Yes	Y		1	1.2	9	1	14	-.866	15	-.5												
10	1.2DL + 1WL AZI 240	Yes	Y		1	1.2	10	1	14	-.5	15	-.866												
11	1.2DL + 1WL AZI 270	Yes	Y		1	1.2	11	1	14		15	-1												
12	1.2DL + 1WL AZI 300	Yes	Y		1	1.2	12	1	14	.5	15	-.866												
13	1.2DL + 1WL AZI 330	Yes	Y		1	1.2	13	1	14	.866	15	-.5												
14	0.9DL + 1WL AZI 0	Yes	Y		1	.9	2	1	14	1	15													
15	0.9DL + 1WL AZI 30	Yes	Y		1	.9	3	1	14	.866	15	.5												
16	0.9DL + 1WL AZI 60	Yes	Y		1	.9	4	1	14	.5	15	.866												
17	0.9DL + 1WL AZI 90	Yes	Y		1	.9	5	1	14		15	1												
18	0.9DL + 1WL AZI 120	Yes	Y		1	.9	6	1	14	-.5	15	.866												
19	0.9DL + 1WL AZI 150	Yes	Y		1	.9	7	1	14	-.866	15	.5												
20	0.9DL + 1WL AZI 180	Yes	Y		1	.9	8	1	14	-1	15													
21	0.9DL + 1WL AZI 210	Yes	Y		1	.9	9	1	14	-.866	15	-.5												
22	0.9DL + 1WL AZI 240	Yes	Y		1	.9	10	1	14	-.5	15	-.866												
23	0.9DL + 1WL AZI 270	Yes	Y		1	.9	11	1	14		15	-1												
24	0.9DL + 1WL AZI 300	Yes	Y		1	.9	12	1	14	.5	15	-.866												
25	0.9DL + 1WL AZI 330	Yes	Y		1	.9	13	1	14	.866	15	-.5												
26	1.2D + 1.0Di	Yes	Y		1	1.2	16	1																
27	1.2D + 1.0Di +1.0Wi AZI 0	Yes	Y		1	1.2	16	1	17	1	29	1	30											
28	1.2D + 1.0Di +1.0Wi AZI 30	Yes	Y		1	1.2	16	1	18	1	29	.866	30	.5										
29	1.2D + 1.0Di +1.0Wi AZI 60	Yes	Y		1	1.2	16	1	19	1	29	.5	30	.866										
30	1.2D + 1.0Di +1.0Wi AZI 90	Yes	Y		1	1.2	16	1	20	1	29		30	1										
31	1.2D + 1.0Di +1.0Wi AZI 120	Yes	Y		1	1.2	16	1	21	1	29	-.5	30	.866										
32	1.2D + 1.0Di +1.0Wi AZI 150	Yes	Y		1	1.2	16	1	22	1	29	-.866	30	.5										
33	1.2D + 1.0Di +1.0Wi AZI 180	Yes	Y		1	1.2	16	1	23	1	29	-1	30											
34	1.2D + 1.0Di +1.0Wi AZI 210	Yes	Y		1	1.2	16	1	24	1	29	-.866	30	-.5										
35	1.2D + 1.0Di +1.0Wi AZI 240	Yes	Y		1	1.2	16	1	25	1	29	-.5	30	-.866										
36	1.2D + 1.0Di +1.0Wi AZI 270	Yes	Y		1	1.2	16	1	26	1	29		30	-1										
37	1.2D + 1.0Di +1.0Wi AZI 300	Yes	Y		1	1.2	16	1	27	1	29	.5	30	-.866										
38	1.2D + 1.0Di +1.0Wi AZI 330	Yes	Y		1	1.2	16	1	28	1	29	.866	30	-.5										
39	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	1	32															

Load Combinations (Continued)

	Description	S...	P...	S...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...
40	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	.866	32	.5														
41	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	.5	32	.866														
42	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31		32	1														
43	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	-.5	32	.866														
44	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	-.866	32	.5														
45	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	-1	32															
46	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	-.866	32	-.5														
47	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	-.5	32	-.866														
48	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31		32	-1														
49	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	.5	32	-.866														
50	(1.2 + 0.2Sds)DL + 1.0E A...	Yes	Y		1	1.2...	31	.866	32	-.5														
51	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	1	32															
52	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	.866	32	.5														
53	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	.5	32	.866														
54	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31		32	1														
55	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	-.5	32	.866														
56	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	-.866	32	.5														
57	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	-1	32															
58	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	-.866	32	-.5														
59	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	-.5	32	-.866														
60	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31		32	-1														
61	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	.5	32	-.866														
62	(0.9 - 0.2Sds)DL + 1.0E AZ...	Yes	Y		1	.856	31	.866	32	-.5														
63	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	2	.238	14	.238	15		33	1.5										
64	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	3	.238	14	.206	15	.119	33	1.5										
65	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	4	.238	14	.119	15	.206	33	1.5										
66	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	5	.238	14		15	.238	33	1.5										
67	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	6	.238	14	-.119	15	.206	33	1.5										
68	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	7	.238	14	-.206	15	.119	33	1.5										
69	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	8	.238	14	-.238	15		33	1.5										
70	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	9	.238	14	-.206	15	-.119	33	1.5										
71	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	10	.238	14	-.119	15	-.206	33	1.5										
72	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	11	.238	14		15	-.238	33	1.5										
73	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	12	.238	14	.119	15	-.206	33	1.5										
74	1.0DL + 1.5LL + 1.0SWL (6...	Yes	Y		1	1	13	.238	14	.206	15	-.119	33	1.5										
75	1.2DL + 1.5LL	Yes	Y		1	1.2	33	1.5																
76	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	2	.059	14	.059	15											
77	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	3	.059	14	.052	15	.03										
78	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	4	.059	14	.03	15	.052										
79	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	5	.059	14		15	.059										
80	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	6	.059	14	-.03	15	.052										
81	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	7	.059	14	-.052	15	.03										
82	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	8	.059	14	-.059	15											
83	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	9	.059	14	-.052	15	-.03										
84	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	10	.059	14	-.03	15	-.052										
85	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	11	.059	14		15	-.059										
86	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	12	.059	14	.03	15	-.052										
87	1.2DL + 1.5LM-MP1 + 1S...	Yes	Y		1	1.2	34	1.5	13	.059	14	.052	15	-.03										
88	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	2	.059	14	.059	15											
89	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	3	.059	14	.052	15	.03										
90	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	4	.059	14	.03	15	.052										
91	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	5	.059	14		15	.059										

Load Combinations (Continued)

	Description	S...	P...	S...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...
92	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	6	.059	14	-.03	15	.052										
93	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	7	.059	14	-.052	15	.03										
94	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	8	.059	14	-.059	15											
95	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	9	.059	14	-.052	15	-.03										
96	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	10	.059	14	-.03	15	-.052										
97	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	11	.059	14		15	-.059										
98	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	12	.059	14	.03	15	-.052										
99	1.2DL + 1.5LM-MP2 + 1S...	Yes	Y		1	1.2	35	1.5	13	.059	14	.052	15	-.03										
100	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	2	.059	14	.059	15											
101	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	3	.059	14	.052	15	.03										
102	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	4	.059	14	.03	15	.052										
103	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	5	.059	14		15	.059										
104	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	6	.059	14	-.03	15	.052										
105	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	7	.059	14	-.052	15	.03										
106	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	8	.059	14	-.059	15											
107	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	9	.059	14	-.052	15	-.03										
108	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	10	.059	14	-.03	15	-.052										
109	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	11	.059	14		15	-.059										
110	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	12	.059	14	.03	15	-.052										
111	1.2DL + 1.5LM-MP3 + 1S...	Yes	Y		1	1.2	36	1.5	13	.059	14	.052	15	-.03										
112	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	2	.059	14	.059	15											
113	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	3	.059	14	.052	15	.03										
114	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	4	.059	14	.03	15	.052										
115	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	5	.059	14		15	.059										
116	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	6	.059	14	-.03	15	.052										
117	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	7	.059	14	-.052	15	.03										
118	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	8	.059	14	-.059	15											
119	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	9	.059	14	-.052	15	-.03										
120	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	10	.059	14	-.03	15	-.052										
121	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	11	.059	14		15	-.059										
122	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	12	.059	14	.03	15	-.052										
123	1.2DL + 1.5LM-MP4 + 1S...	Yes	Y		1	1.2	37	1.5	13	.059	14	.052	15	-.03										
124	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	2	.059	14	.059	15											
125	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	3	.059	14	.052	15	.03										
126	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	4	.059	14	.03	15	.052										
127	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	5	.059	14		15	.059										
128	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	6	.059	14	-.03	15	.052										
129	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	7	.059	14	-.052	15	.03										
130	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	8	.059	14	-.059	15											
131	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	9	.059	14	-.052	15	-.03										
132	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	10	.059	14	-.03	15	-.052										
133	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	11	.059	14		15	-.059										
134	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	12	.059	14	.03	15	-.052										
135	1.2DL + 1.5LM-MP5 + 1S...	Yes	Y		1	1.2	38	1.5	13	.059	14	.052	15	-.03										
136	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	2	.059	14	.059	15											
137	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	3	.059	14	.052	15	.03										
138	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	4	.059	14	.03	15	.052										
139	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	5	.059	14		15	.059										
140	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	6	.059	14	-.03	15	.052										
141	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	7	.059	14	-.052	15	.03										
142	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	8	.059	14	-.059	15											
143	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	9	.059	14	-.052	15	-.03										

Load Combinations (Continued)

	Description	S...	P...	S...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...
144	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	10	.059	14	-.03	15	-.052										
145	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	11	.059	14		15	-.059										
146	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	12	.059	14	.03	15	-.052										
147	1.2DL + 1.5LM-MP6 + 1S...	Yes	Y		1	1.2	39	1.5	13	.059	14	.052	15	-.03										
148	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	2	.059	14	.059	15											
149	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	3	.059	14	.052	15	.03										
150	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	4	.059	14	.03	15	.052										
151	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	5	.059	14		15	.059										
152	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	6	.059	14	-.03	15	.052										
153	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	7	.059	14	-.052	15	.03										
154	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	8	.059	14	-.059	15											
155	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	9	.059	14	-.052	15	-.03										
156	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	10	.059	14	-.03	15	-.052										
157	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	11	.059	14		15	-.059										
158	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	12	.059	14	.03	15	-.052										
159	1.2DL + 1.5LM-MP7 + 1S...	Yes	Y		1	1.2	40	1.5	13	.059	14	.052	15	-.03										
160	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	2	.059	14	.059	15											
161	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	3	.059	14	.052	15	.03										
162	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	4	.059	14	.03	15	.052										
163	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	5	.059	14		15	.059										
164	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	6	.059	14	-.03	15	.052										
165	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	7	.059	14	-.052	15	.03										
166	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	8	.059	14	-.059	15											
167	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	9	.059	14	-.052	15	-.03										
168	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	10	.059	14	-.03	15	-.052										
169	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	11	.059	14		15	-.059										
170	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	12	.059	14	.03	15	-.052										
171	1.2DL + 1.5LM-MP8 + 1S...	Yes	Y		1	1.2	41	1.5	13	.059	14	.052	15	-.03										
172	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	2	.059	14	.059	15											
173	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	3	.059	14	.052	15	.03										
174	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	4	.059	14	.03	15	.052										
175	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	5	.059	14		15	.059										
176	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	6	.059	14	-.03	15	.052										
177	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	7	.059	14	-.052	15	.03										
178	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	8	.059	14	-.059	15											
179	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	9	.059	14	-.052	15	-.03										
180	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	10	.059	14	-.03	15	-.052										
181	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	11	.059	14		15	-.059										
182	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	12	.059	14	.03	15	-.052										
183	1.2DL + 1.5LM-MP9 + 1S...	Yes	Y		1	1.2	42	1.5	13	.059	14	.052	15	-.03										
184	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	2	.059	14	.059	15											
185	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	3	.059	14	.052	15	.03										
186	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	4	.059	14	.03	15	.052										
187	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	5	.059	14		15	.059										
188	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	6	.059	14	-.03	15	.052										
189	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	7	.059	14	-.052	15	.03										
190	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	8	.059	14	-.059	15											
191	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	9	.059	14	-.052	15	-.03										
192	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	10	.059	14	-.03	15	-.052										
193	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	11	.059	14		15	-.059										
194	1.2DL + 1.5LM-MP10 + 1S...	Yes	Y		1	1.2	43	1.5	12	.059	14	.03	15	-.052										

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]
1	P24	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2	P13	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
3	P1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-ft]	LC	MZ [lb-ft]	LC
1	P24	max	879.869	6	1589.865	35	1339.243	2	723.766	16	1619.127	19	3686.127	132
2		min	-863.893	24	-352.761	16	-1329.016	20	-3184.071	84	-1636.941	13	-1340.188	16
3	P13	max	969.802	4	1717.378	31	1279.361	15	728.292	24	1734.181	15	1130.73	24
4		min	-967.483	22	-307.313	24	-1287.311	9	-2795.17	92	-1781.236	9	-4297.876	140
5	P1	max	1294	17	1604.467	27	669.232	2	4340.509	2	1476.291	11	1578.997	115
6		min	-1312.405	11	-370.015	20	-673.028	20	-1501.92	20	-1424.966	17	-856.974	157
7	Totals:	max	2996.812	17	4425.36	35	3173.179	2						
8		min	-2996.828	11	1532.768	53	-3173.172	20						

Joint Loads and Enforced Displacements (BLC 33 : Service Live Loads)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N72B	L	Y	-250
2	N129B	L	Y	-250
3	N135A	L	Y	-250

Joint Loads and Enforced Displacements (BLC 34 : Maintenance Load 1)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N70A	L	Y	-500

Joint Loads and Enforced Displacements (BLC 35 : Maintenance Load 2)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N69A	L	Y	-500

Joint Loads and Enforced Displacements (BLC 36 : Maintenance Load 3)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N76	L	Y	-500

Joint Loads and Enforced Displacements (BLC 37 : Maintenance Load 4)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N94	L	Y	-500

Joint Loads and Enforced Displacements (BLC 38 : Maintenance Load 5)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N93	L	Y	-500

Joint Loads and Enforced Displacements (BLC 39 : Maintenance Load 6)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N122	L	Y	-500

Joint Loads and Enforced Displacements (BLC 40 : Maintenance Load 7)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N121	L	Y	-500

Joint Loads and Enforced Displacements (BLC 41 : Maintenance Load 8)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N133B	L	Y	-500

Joint Loads and Enforced Displacements (BLC 42 : Maintenance Load 9)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N139	L	Y	-500

Joint Loads and Enforced Displacements (BLC 43 : Maintenance Load 10)

	Joint Label	L,D,M	Direction	Magnitude[(lb,lb-ft), (in,rad), (lb*s^...
1	N123B	L	Y	-500

Member Point Loads (BLC 1 : Self Weight)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	Y	-32.25	0
2	MP1	Y	-32.25	72
3	MP1	Y	-74.95	12
4	MP1	Y	-63.93	12
5	MP10	Y	-21.85	6
6	MP4	Y	-32.25	0
7	MP4	Y	-32.25	72
8	MP4	Y	-74.95	12
9	MP4	Y	-63.93	12
10	MP7	Y	-32.25	0
11	MP7	Y	-32.25	72
12	MP7	Y	-74.95	12
13	MP7	Y	-63.93	12

Member Point Loads (BLC 2 : Wind Load AZI 0)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	0	0
2	MP1	Z	-134.56	0
3	MP1	X	0	72
4	MP1	Z	-134.56	72
5	MP1	X	0	12
6	MP1	Z	-65.97	12
7	MP1	X	0	12
8	MP1	Z	-65.97	12
9	MP10	X	0	6
10	MP10	Z	-62.72	6
11	MP4	X	0	0
12	MP4	Z	-74.08	0
13	MP4	X	0	72
14	MP4	Z	-74.08	72
15	MP4	X	0	12
16	MP4	Z	-46.46	12

Member Point Loads (BLC 2 : Wind Load AZI 0) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
17	MP4	X	0	12
18	MP4	Z	-42.52	12
19	MP7	X	0	0
20	MP7	Z	-74.08	0
21	MP7	X	0	72
22	MP7	Z	-74.08	72
23	MP7	X	0	12
24	MP7	Z	-46.46	12
25	MP7	X	0	12
26	MP7	Z	-42.52	12

Member Point Loads (BLC 3 : Wind Load AZI 30)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-57.2	0
2	MP1	Z	-99.08	0
3	MP1	X	-57.2	72
4	MP1	Z	-99.08	72
5	MP1	X	-29.73	12
6	MP1	Z	-51.5	12
7	MP1	X	-29.08	12
8	MP1	Z	-50.36	12
9	MP10	X	-28	6
10	MP10	Z	-48.5	6
11	MP4	X	-57.2	0
12	MP4	Z	-99.08	0
13	MP4	X	-57.2	72
14	MP4	Z	-99.08	72
15	MP4	X	-29.73	12
16	MP4	Z	-51.5	12
17	MP4	X	-29.08	12
18	MP4	Z	-50.36	12
19	MP7	X	-26.96	0
20	MP7	Z	-46.7	0
21	MP7	X	-26.96	72
22	MP7	Z	-46.7	72
23	MP7	X	-19.98	12
24	MP7	Z	-34.6	12
25	MP7	X	-17.35	12
26	MP7	Z	-30.06	12

Member Point Loads (BLC 4 : Wind Load AZI 60)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-64.16	0
2	MP1	Z	-37.04	0
3	MP1	X	-64.16	72
4	MP1	Z	-37.04	72
5	MP1	X	-40.23	12
6	MP1	Z	-23.23	12
7	MP1	X	-36.82	12
8	MP1	Z	-21.26	12
9	MP10	X	-36.86	6

Member Point Loads (BLC 4 : Wind Load AZI 60) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
10	MP10	Z	-21.28	6
11	MP4	X	-116.53	0
12	MP4	Z	-67.28	0
13	MP4	X	-116.53	72
14	MP4	Z	-67.28	72
15	MP4	X	-57.13	12
16	MP4	Z	-32.99	12
17	MP4	X	-57.13	12
18	MP4	Z	-32.99	12
19	MP7	X	-64.16	0
20	MP7	Z	-37.04	0
21	MP7	X	-64.16	72
22	MP7	Z	-37.04	72
23	MP7	X	-40.23	12
24	MP7	Z	-23.23	12
25	MP7	X	-36.82	12
26	MP7	Z	-21.26	12

Member Point Loads (BLC 5 : Wind Load AZI 90)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-53.93	0
2	MP1	Z	0	0
3	MP1	X	-53.93	72
4	MP1	Z	0	72
5	MP1	X	-39.95	12
6	MP1	Z	0	12
7	MP1	X	-34.71	12
8	MP1	Z	0	12
9	MP10	X	-35.84	6
10	MP10	Z	0	6
11	MP4	X	-114.4	0
12	MP4	Z	0	0
13	MP4	X	-114.4	72
14	MP4	Z	0	72
15	MP4	X	-59.47	12
16	MP4	Z	0	12
17	MP4	X	-58.15	12
18	MP4	Z	0	12
19	MP7	X	-114.4	0
20	MP7	Z	0	0
21	MP7	X	-114.4	72
22	MP7	Z	0	72
23	MP7	X	-59.47	12
24	MP7	Z	0	12
25	MP7	X	-58.15	12
26	MP7	Z	0	12

Member Point Loads (BLC 6 : Wind Load AZI 120)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-64.16	0
2	MP1	Z	37.04	0

Member Point Loads (BLC 6 : Wind Load AZI 120) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
3	MP1	X	-64.16	72
4	MP1	Z	37.04	72
5	MP1	X	-40.23	12
6	MP1	Z	23.23	12
7	MP1	X	-36.82	12
8	MP1	Z	21.26	12
9	MP10	X	-36.86	6
10	MP10	Z	21.28	6
11	MP4	X	-64.16	0
12	MP4	Z	37.04	0
13	MP4	X	-64.16	72
14	MP4	Z	37.04	72
15	MP4	X	-40.23	12
16	MP4	Z	23.23	12
17	MP4	X	-36.82	12
18	MP4	Z	21.26	12
19	MP7	X	-116.53	0
20	MP7	Z	67.28	0
21	MP7	X	-116.53	72
22	MP7	Z	67.28	72
23	MP7	X	-57.13	12
24	MP7	Z	32.99	12
25	MP7	X	-57.13	12
26	MP7	Z	32.99	12

Member Point Loads (BLC 7 : Wind Load AZI 150)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-57.2	0
2	MP1	Z	99.08	0
3	MP1	X	-57.2	72
4	MP1	Z	99.08	72
5	MP1	X	-29.73	12
6	MP1	Z	51.5	12
7	MP1	X	-29.08	12
8	MP1	Z	50.36	12
9	MP10	X	-28	6
10	MP10	Z	48.5	6
11	MP4	X	-26.96	0
12	MP4	Z	46.7	0
13	MP4	X	-26.96	72
14	MP4	Z	46.7	72
15	MP4	X	-19.98	12
16	MP4	Z	34.6	12
17	MP4	X	-17.35	12
18	MP4	Z	30.06	12
19	MP7	X	-57.2	0
20	MP7	Z	99.08	0
21	MP7	X	-57.2	72
22	MP7	Z	99.08	72
23	MP7	X	-29.73	12
24	MP7	Z	51.5	12

Member Point Loads (BLC 7 : Wind Load AZI 150) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
25	MP7	X	-29.08	12
26	MP7	Z	50.36	12

Member Point Loads (BLC 8 : Wind Load AZI 180)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	0	0
2	MP1	Z	134.56	0
3	MP1	X	0	72
4	MP1	Z	134.56	72
5	MP1	X	0	12
6	MP1	Z	65.97	12
7	MP1	X	0	12
8	MP1	Z	65.97	12
9	MP10	X	0	6
10	MP10	Z	62.72	6
11	MP4	X	0	0
12	MP4	Z	74.08	0
13	MP4	X	0	72
14	MP4	Z	74.08	72
15	MP4	X	0	12
16	MP4	Z	46.46	12
17	MP4	X	0	12
18	MP4	Z	42.52	12
19	MP7	X	0	0
20	MP7	Z	74.08	0
21	MP7	X	0	72
22	MP7	Z	74.08	72
23	MP7	X	0	12
24	MP7	Z	46.46	12
25	MP7	X	0	12
26	MP7	Z	42.52	12

Member Point Loads (BLC 9 : Wind Load AZI 210)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	57.2	0
2	MP1	Z	99.08	0
3	MP1	X	57.2	72
4	MP1	Z	99.08	72
5	MP1	X	29.73	12
6	MP1	Z	51.5	12
7	MP1	X	29.08	12
8	MP1	Z	50.36	12
9	MP10	X	28	6
10	MP10	Z	48.5	6
11	MP4	X	57.2	0
12	MP4	Z	99.08	0
13	MP4	X	57.2	72
14	MP4	Z	99.08	72
15	MP4	X	29.73	12
16	MP4	Z	51.5	12
17	MP4	X	29.08	12

Member Point Loads (BLC 9 : Wind Load AZI 210) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
18	MP4	Z	50.36	12
19	MP7	X	26.96	0
20	MP7	Z	46.7	0
21	MP7	X	26.96	72
22	MP7	Z	46.7	72
23	MP7	X	19.98	12
24	MP7	Z	34.6	12
25	MP7	X	17.35	12
26	MP7	Z	30.06	12

Member Point Loads (BLC 10 : Wind Load AZI 240)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	64.16	0
2	MP1	Z	37.04	0
3	MP1	X	64.16	72
4	MP1	Z	37.04	72
5	MP1	X	40.23	12
6	MP1	Z	23.23	12
7	MP1	X	36.82	12
8	MP1	Z	21.26	12
9	MP10	X	36.86	6
10	MP10	Z	21.28	6
11	MP4	X	116.53	0
12	MP4	Z	67.28	0
13	MP4	X	116.53	72
14	MP4	Z	67.28	72
15	MP4	X	57.13	12
16	MP4	Z	32.99	12
17	MP4	X	57.13	12
18	MP4	Z	32.99	12
19	MP7	X	64.16	0
20	MP7	Z	37.04	0
21	MP7	X	64.16	72
22	MP7	Z	37.04	72
23	MP7	X	40.23	12
24	MP7	Z	23.23	12
25	MP7	X	36.82	12
26	MP7	Z	21.26	12

Member Point Loads (BLC 11 : Wind Load AZI 270)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	53.93	0
2	MP1	Z	0	0
3	MP1	X	53.93	72
4	MP1	Z	0	72
5	MP1	X	39.95	12
6	MP1	Z	0	12
7	MP1	X	34.71	12
8	MP1	Z	0	12
9	MP10	X	35.84	6
10	MP10	Z	0	6

Member Point Loads (BLC 11 : Wind Load AZI 270) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
11	MP4	X	114.4	0
12	MP4	Z	0	0
13	MP4	X	114.4	72
14	MP4	Z	0	72
15	MP4	X	59.47	12
16	MP4	Z	0	12
17	MP4	X	58.15	12
18	MP4	Z	0	12
19	MP7	X	114.4	0
20	MP7	Z	0	0
21	MP7	X	114.4	72
22	MP7	Z	0	72
23	MP7	X	59.47	12
24	MP7	Z	0	12
25	MP7	X	58.15	12
26	MP7	Z	0	12

Member Point Loads (BLC 12 : Wind Load AZI 300)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	64.16	0
2	MP1	Z	-37.04	0
3	MP1	X	64.16	72
4	MP1	Z	-37.04	72
5	MP1	X	40.23	12
6	MP1	Z	-23.23	12
7	MP1	X	36.82	12
8	MP1	Z	-21.26	12
9	MP10	X	36.86	6
10	MP10	Z	-21.28	6
11	MP4	X	64.16	0
12	MP4	Z	-37.04	0
13	MP4	X	64.16	72
14	MP4	Z	-37.04	72
15	MP4	X	40.23	12
16	MP4	Z	-23.23	12
17	MP4	X	36.82	12
18	MP4	Z	-21.26	12
19	MP7	X	116.53	0
20	MP7	Z	-67.28	0
21	MP7	X	116.53	72
22	MP7	Z	-67.28	72
23	MP7	X	57.13	12
24	MP7	Z	-32.99	12
25	MP7	X	57.13	12
26	MP7	Z	-32.99	12

Member Point Loads (BLC 13 : Wind Load AZI 330)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	57.2	0
2	MP1	Z	-99.08	0
3	MP1	X	57.2	72

Member Point Loads (BLC 13 : Wind Load AZI 330) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
4	MP1	Z	-99.08	72
5	MP1	X	29.73	12
6	MP1	Z	-51.5	12
7	MP1	X	29.08	12
8	MP1	Z	-50.36	12
9	MP10	X	28	6
10	MP10	Z	-48.5	6
11	MP4	X	26.96	0
12	MP4	Z	-46.7	0
13	MP4	X	26.96	72
14	MP4	Z	-46.7	72
15	MP4	X	19.98	12
16	MP4	Z	-34.6	12
17	MP4	X	17.35	12
18	MP4	Z	-30.06	12
19	MP7	X	57.2	0
20	MP7	Z	-99.08	0
21	MP7	X	57.2	72
22	MP7	Z	-99.08	72
23	MP7	X	29.73	12
24	MP7	Z	-51.5	12
25	MP7	X	29.08	12
26	MP7	Z	-50.36	12

Member Point Loads (BLC 16 : Ice Weight)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	Y	-87.973	0
2	MP1	Y	-87.973	72
3	MP1	Y	-44.498	12
4	MP1	Y	-41.63	12
5	MP10	Y	-40.561	6
6	MP4	Y	-87.973	0
7	MP4	Y	-87.973	72
8	MP4	Y	-44.498	12
9	MP4	Y	-41.63	12
10	MP7	Y	-87.973	0
11	MP7	Y	-87.973	72
12	MP7	Y	-44.498	12
13	MP7	Y	-41.63	12

Member Point Loads (BLC 17 : Ice Wind Load AZI 0)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	0	0
2	MP1	Z	-16.52	0
3	MP1	X	0	72
4	MP1	Z	-16.52	72
5	MP1	X	0	12
6	MP1	Z	-6.21	12
7	MP1	X	0	12
8	MP1	Z	-6.21	12
9	MP10	X	0	6

Member Point Loads (BLC 17 : Ice Wind Load AZI 0) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
10	MP10	Z	-6.11	6
11	MP4	X	0	0
12	MP4	Z	-12.63	0
13	MP4	X	0	72
14	MP4	Z	-12.63	72
15	MP4	X	0	12
16	MP4	Z	-5.3	12
17	MP4	X	0	12
18	MP4	Z	-5.09	12
19	MP7	X	0	0
20	MP7	Z	-12.63	0
21	MP7	X	0	72
22	MP7	Z	-12.63	72
23	MP7	X	0	12
24	MP7	Z	-5.3	12
25	MP7	X	0	12
26	MP7	Z	-5.09	12

Member Point Loads (BLC 18 : Ice Wind Load AZI 30)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-7.61	0
2	MP1	Z	-13.19	0
3	MP1	X	-7.61	72
4	MP1	Z	-13.19	72
5	MP1	X	-2.95	12
6	MP1	Z	-5.11	12
7	MP1	X	-2.92	12
8	MP1	Z	-5.05	12
9	MP10	X	-2.89	6
10	MP10	Z	-5.01	6
11	MP4	X	-7.61	0
12	MP4	Z	-13.19	0
13	MP4	X	-7.61	72
14	MP4	Z	-13.19	72
15	MP4	X	-2.95	12
16	MP4	Z	-5.11	12
17	MP4	X	-2.92	12
18	MP4	Z	-5.05	12
19	MP7	X	-5.67	0
20	MP7	Z	-9.82	0
21	MP7	X	-5.67	72
22	MP7	Z	-9.82	72
23	MP7	X	-2.5	12
24	MP7	Z	-4.33	12
25	MP7	X	-2.36	12
26	MP7	Z	-4.09	12

Member Point Loads (BLC 19 : Ice Wind Load AZI 60)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-10.94	0
2	MP1	Z	-6.32	0

Member Point Loads (BLC 19 : Ice Wind Load AZI 60) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
3	MP1	X	-10.94	72
4	MP1	Z	-6.32	72
5	MP1	X	-4.59	12
6	MP1	Z	-2.65	12
7	MP1	X	-4.41	12
8	MP1	Z	-2.55	12
9	MP10	X	-4.45	6
10	MP10	Z	-2.57	6
11	MP4	X	-14.31	0
12	MP4	Z	-8.26	0
13	MP4	X	-14.31	72
14	MP4	Z	-8.26	72
15	MP4	X	-5.38	12
16	MP4	Z	-3.1	12
17	MP4	X	-5.38	12
18	MP4	Z	-3.1	12
19	MP7	X	-10.94	0
20	MP7	Z	-6.32	0
21	MP7	X	-10.94	72
22	MP7	Z	-6.32	72
23	MP7	X	-4.59	12
24	MP7	Z	-2.65	12
25	MP7	X	-4.41	12
26	MP7	Z	-2.55	12

Member Point Loads (BLC 20 : Ice Wind Load AZI 90)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-11.34	0
2	MP1	Z	0	0
3	MP1	X	-11.34	72
4	MP1	Z	0	72
5	MP1	X	-5	12
6	MP1	Z	0	12
7	MP1	X	-4.72	12
8	MP1	Z	0	12
9	MP10	X	-4.82	6
10	MP10	Z	0	6
11	MP4	X	-15.23	0
12	MP4	Z	0	0
13	MP4	X	-15.23	72
14	MP4	Z	0	72
15	MP4	X	-5.91	12
16	MP4	Z	0	12
17	MP4	X	-5.84	12
18	MP4	Z	0	12
19	MP7	X	-15.23	0
20	MP7	Z	0	0
21	MP7	X	-15.23	72
22	MP7	Z	0	72
23	MP7	X	-5.91	12
24	MP7	Z	0	12

Member Point Loads (BLC 20 : Ice Wind Load AZI 90) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
25	MP7	X	-5.84	12
26	MP7	Z	0	12

Member Point Loads (BLC 21 : Ice Wind Load AZI 120)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-10.94	0
2	MP1	Z	6.32	0
3	MP1	X	-10.94	72
4	MP1	Z	6.32	72
5	MP1	X	-4.59	12
6	MP1	Z	2.65	12
7	MP1	X	-4.41	12
8	MP1	Z	2.55	12
9	MP10	X	-4.45	6
10	MP10	Z	2.57	6
11	MP4	X	-10.94	0
12	MP4	Z	6.32	0
13	MP4	X	-10.94	72
14	MP4	Z	6.32	72
15	MP4	X	-4.59	12
16	MP4	Z	2.65	12
17	MP4	X	-4.41	12
18	MP4	Z	2.55	12
19	MP7	X	-14.31	0
20	MP7	Z	8.26	0
21	MP7	X	-14.31	72
22	MP7	Z	8.26	72
23	MP7	X	-5.38	12
24	MP7	Z	3.1	12
25	MP7	X	-5.38	12
26	MP7	Z	3.1	12

Member Point Loads (BLC 22 : Ice Wind Load AZI 150)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-7.61	0
2	MP1	Z	13.19	0
3	MP1	X	-7.61	72
4	MP1	Z	13.19	72
5	MP1	X	-2.95	12
6	MP1	Z	5.11	12
7	MP1	X	-2.92	12
8	MP1	Z	5.05	12
9	MP10	X	-2.89	6
10	MP10	Z	5.01	6
11	MP4	X	-5.67	0
12	MP4	Z	9.82	0
13	MP4	X	-5.67	72
14	MP4	Z	9.82	72
15	MP4	X	-2.5	12
16	MP4	Z	4.33	12
17	MP4	X	-2.36	12

Member Point Loads (BLC 22 : Ice Wind Load AZI 150) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
18	MP4	Z	4.09	12
19	MP7	X	-7.61	0
20	MP7	Z	13.19	0
21	MP7	X	-7.61	72
22	MP7	Z	13.19	72
23	MP7	X	-2.95	12
24	MP7	Z	5.11	12
25	MP7	X	-2.92	12
26	MP7	Z	5.05	12

Member Point Loads (BLC 23 : Ice Wind Load AZI 180)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	0	0
2	MP1	Z	16.52	0
3	MP1	X	0	72
4	MP1	Z	16.52	72
5	MP1	X	0	12
6	MP1	Z	6.21	12
7	MP1	X	0	12
8	MP1	Z	6.21	12
9	MP10	X	0	6
10	MP10	Z	6.11	6
11	MP4	X	0	0
12	MP4	Z	12.63	0
13	MP4	X	0	72
14	MP4	Z	12.63	72
15	MP4	X	0	12
16	MP4	Z	5.3	12
17	MP4	X	0	12
18	MP4	Z	5.09	12
19	MP7	X	0	0
20	MP7	Z	12.63	0
21	MP7	X	0	72
22	MP7	Z	12.63	72
23	MP7	X	0	12
24	MP7	Z	5.3	12
25	MP7	X	0	12
26	MP7	Z	5.09	12

Member Point Loads (BLC 24 : Ice Wind Load AZI 210)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	7.61	0
2	MP1	Z	13.19	0
3	MP1	X	7.61	72
4	MP1	Z	13.19	72
5	MP1	X	2.95	12
6	MP1	Z	5.11	12
7	MP1	X	2.92	12
8	MP1	Z	5.05	12
9	MP10	X	2.89	6
10	MP10	Z	5.01	6

Member Point Loads (BLC 24 : Ice Wind Load AZI 210) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
11	MP4	X	7.61	0
12	MP4	Z	13.19	0
13	MP4	X	7.61	72
14	MP4	Z	13.19	72
15	MP4	X	2.95	12
16	MP4	Z	5.11	12
17	MP4	X	2.92	12
18	MP4	Z	5.05	12
19	MP7	X	5.67	0
20	MP7	Z	9.82	0
21	MP7	X	5.67	72
22	MP7	Z	9.82	72
23	MP7	X	2.5	12
24	MP7	Z	4.33	12
25	MP7	X	2.36	12
26	MP7	Z	4.09	12

Member Point Loads (BLC 25 : Ice Wind Load AZI 240)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	10.94	0
2	MP1	Z	6.32	0
3	MP1	X	10.94	72
4	MP1	Z	6.32	72
5	MP1	X	4.59	12
6	MP1	Z	2.65	12
7	MP1	X	4.41	12
8	MP1	Z	2.55	12
9	MP10	X	4.45	6
10	MP10	Z	2.57	6
11	MP4	X	14.31	0
12	MP4	Z	8.26	0
13	MP4	X	14.31	72
14	MP4	Z	8.26	72
15	MP4	X	5.38	12
16	MP4	Z	3.1	12
17	MP4	X	5.38	12
18	MP4	Z	3.1	12
19	MP7	X	10.94	0
20	MP7	Z	6.32	0
21	MP7	X	10.94	72
22	MP7	Z	6.32	72
23	MP7	X	4.59	12
24	MP7	Z	2.65	12
25	MP7	X	4.41	12
26	MP7	Z	2.55	12

Member Point Loads (BLC 26 : Ice Wind Load AZI 270)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	11.34	0
2	MP1	Z	0	0
3	MP1	X	11.34	72

Member Point Loads (BLC 26 : Ice Wind Load AZI 270) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
4	MP1	Z	0	72
5	MP1	X	5	12
6	MP1	Z	0	12
7	MP1	X	4.72	12
8	MP1	Z	0	12
9	MP10	X	4.82	6
10	MP10	Z	0	6
11	MP4	X	15.23	0
12	MP4	Z	0	0
13	MP4	X	15.23	72
14	MP4	Z	0	72
15	MP4	X	5.91	12
16	MP4	Z	0	12
17	MP4	X	5.84	12
18	MP4	Z	0	12
19	MP7	X	15.23	0
20	MP7	Z	0	0
21	MP7	X	15.23	72
22	MP7	Z	0	72
23	MP7	X	5.91	12
24	MP7	Z	0	12
25	MP7	X	5.84	12
26	MP7	Z	0	12

Member Point Loads (BLC 27 : Ice Wind Load AZI 300)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	10.94	0
2	MP1	Z	-6.32	0
3	MP1	X	10.94	72
4	MP1	Z	-6.32	72
5	MP1	X	4.59	12
6	MP1	Z	-2.65	12
7	MP1	X	4.41	12
8	MP1	Z	-2.55	12
9	MP10	X	4.45	6
10	MP10	Z	-2.57	6
11	MP4	X	10.94	0
12	MP4	Z	-6.32	0
13	MP4	X	10.94	72
14	MP4	Z	-6.32	72
15	MP4	X	4.59	12
16	MP4	Z	-2.65	12
17	MP4	X	4.41	12
18	MP4	Z	-2.55	12
19	MP7	X	14.31	0
20	MP7	Z	-8.26	0
21	MP7	X	14.31	72
22	MP7	Z	-8.26	72
23	MP7	X	5.38	12
24	MP7	Z	-3.1	12
25	MP7	X	5.38	12

Member Point Loads (BLC 27 : Ice Wind Load AZI 300) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
26	MP7	Z	-3.1	12

Member Point Loads (BLC 28 : Ice Wind Load AZI 330)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	7.61	0
2	MP1	Z	-13.19	0
3	MP1	X	7.61	72
4	MP1	Z	-13.19	72
5	MP1	X	2.95	12
6	MP1	Z	-5.11	12
7	MP1	X	2.92	12
8	MP1	Z	-5.05	12
9	MP10	X	2.89	6
10	MP10	Z	-5.01	6
11	MP4	X	5.67	0
12	MP4	Z	-9.82	0
13	MP4	X	5.67	72
14	MP4	Z	-9.82	72
15	MP4	X	2.5	12
16	MP4	Z	-4.33	12
17	MP4	X	2.36	12
18	MP4	Z	-4.09	12
19	MP7	X	7.61	0
20	MP7	Z	-13.19	0
21	MP7	X	7.61	72
22	MP7	Z	-13.19	72
23	MP7	X	2.95	12
24	MP7	Z	-5.11	12
25	MP7	X	2.92	12
26	MP7	Z	-5.05	12

Member Point Loads (BLC 31 : Seismic Load Z)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	Z	-10.578	0
2	MP1	Z	-10.578	72
3	MP1	Z	-24.584	12
4	MP1	Z	-20.969	12
5	MP10	Z	-7.167	6
6	MP4	Z	-10.578	0
7	MP4	Z	-10.578	72
8	MP4	Z	-24.584	12
9	MP4	Z	-20.969	12
10	MP7	Z	-10.578	0
11	MP7	Z	-10.578	72
12	MP7	Z	-24.584	12
13	MP7	Z	-20.969	12

Member Point Loads (BLC 32 : Seismic Load X)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
1	MP1	X	-10.578	0

Member Point Loads (BLC 32 : Seismic Load X) (Continued)

	Member Label	Direction	Magnitude[lb,lb-ft]	Location[in,%]
2	MP1	X	-10.578	72
3	MP1	X	-24.584	12
4	MP1	X	-20.969	12
5	MP10	X	-7.167	6
6	MP4	X	-10.578	0
7	MP4	X	-10.578	72
8	MP4	X	-24.584	12
9	MP4	X	-20.969	12
10	MP7	X	-10.578	0
11	MP7	X	-10.578	72
12	MP7	X	-24.584	12
13	MP7	X	-20.969	12

Member Distributed Loads (BLC 14 : Distr. Wind Load Z)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
1	S3	SZ	-74.663	-74.663	0	%100
2	GA4	SZ	-74.663	-74.663	0	%100
3	GA3	SZ	-74.663	-74.663	0	%100
4	P3	SZ	-74.663	-74.663	0	%100
5	S2	SZ	-74.663	-74.663	0	%100
6	GA2	SZ	-74.663	-74.663	0	%100
7	GA1	SZ	-74.663	-74.663	0	%100
8	P2	SZ	-74.663	-74.663	0	%100
9	S1	SZ	-74.663	-74.663	0	%100
10	GA6	SZ	-74.663	-74.663	0	%100
11	GA5	SZ	-74.663	-74.663	0	%100
12	P1	SZ	-74.663	-74.663	0	%100
13	H1	SZ	-44.798	-44.798	0	%100
14	MP1	SZ	-44.798	-44.798	0	%100
15	MP3	SZ	-44.798	-44.798	0	%100
16	HR1	SZ	-44.798	-44.798	0	%100
17	CA8	SZ	-74.663	-74.663	0	%100
18	CA9	SZ	-74.663	-74.663	0	%100
19	CA7	SZ	-74.663	-74.663	0	%100
20	M32	SZ	0	0	0	%100
21	M35	SZ	0	0	0	%100
22	M36	SZ	0	0	0	%100
23	M39A	SZ	0	0	0	%100
24	CA3	SZ	-74.663	-74.663	0	%100
25	CA4	SZ	-74.663	-74.663	0	%100
26	CA1	SZ	-74.663	-74.663	0	%100
27	CA2	SZ	-74.663	-74.663	0	%100
28	CA5	SZ	-74.663	-74.663	0	%100
29	CA6	SZ	-74.663	-74.663	0	%100
30	M64	SZ	0	0	0	%100
31	M65	SZ	0	0	0	%100
32	M66	SZ	0	0	0	%100
33	M67	SZ	0	0	0	%100
34	M68	SZ	0	0	0	%100
35	M69	SZ	0	0	0	%100

Member Distributed Loads (BLC 14 : Distr. Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
36	M70	SZ	0	0	0	%100
37	M71	SZ	0	0	0	%100
38	M72	SZ	0	0	0	%100
39	M73	SZ	0	0	0	%100
40	M74	SZ	0	0	0	%100
41	M75	SZ	-74.663	-74.663	0	%100
42	MP2	SZ	-44.798	-44.798	0	%100
43	M43	SZ	0	0	0	%100
44	M44	SZ	0	0	0	%100
45	H3	SZ	-44.798	-44.798	0	%100
46	MP7	SZ	-44.798	-44.798	0	%100
47	MP9	SZ	-44.798	-44.798	0	%100
48	HR3	SZ	-44.798	-44.798	0	%100
49	M52	SZ	0	0	0	%100
50	M53	SZ	0	0	0	%100
51	M54	SZ	0	0	0	%100
52	M55	SZ	0	0	0	%100
53	H2	SZ	-44.798	-44.798	0	%100
54	MP4	SZ	-44.798	-44.798	0	%100
55	MP6	SZ	-44.798	-44.798	0	%100
56	HR2	SZ	-44.798	-44.798	0	%100
57	M66A	SZ	0	0	0	%100
58	M67A	SZ	0	0	0	%100
59	M68A	SZ	0	0	0	%100
60	M69A	SZ	0	0	0	%100
61	MP8	SZ	-44.798	-44.798	0	%100
62	M68B	SZ	0	0	0	%100
63	M69B	SZ	0	0	0	%100
64	MP5	SZ	-44.798	-44.798	0	%100
65	M71B	SZ	0	0	0	%100
66	M72B	SZ	0	0	0	%100
67	MP10	SZ	-44.798	-44.798	0	%100
68	M68D	SZ	0	0	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
1	S3	SX	-74.663	-74.663	0	%100
2	GA4	SX	-74.663	-74.663	0	%100
3	GA3	SX	-74.663	-74.663	0	%100
4	P3	SX	-74.663	-74.663	0	%100
5	S2	SX	-74.663	-74.663	0	%100
6	GA2	SX	-74.663	-74.663	0	%100
7	GA1	SX	-74.663	-74.663	0	%100
8	P2	SX	-74.663	-74.663	0	%100
9	S1	SX	-74.663	-74.663	0	%100
10	GA6	SX	-74.663	-74.663	0	%100
11	GA5	SX	-74.663	-74.663	0	%100
12	P1	SX	-74.663	-74.663	0	%100
13	H1	SX	-44.798	-44.798	0	%100
14	MP1	SX	-44.798	-44.798	0	%100
15	MP3	SX	-44.798	-44.798	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
16	HR1	SX	-44.798	-44.798	0	%100
17	CA8	SX	-74.663	-74.663	0	%100
18	CA9	SX	-74.663	-74.663	0	%100
19	CA7	SX	-74.663	-74.663	0	%100
20	M32	SX	0	0	0	%100
21	M35	SX	0	0	0	%100
22	M36	SX	0	0	0	%100
23	M39A	SX	0	0	0	%100
24	CA3	SX	-74.663	-74.663	0	%100
25	CA4	SX	-74.663	-74.663	0	%100
26	CA1	SX	-74.663	-74.663	0	%100
27	CA2	SX	-74.663	-74.663	0	%100
28	CA5	SX	-74.663	-74.663	0	%100
29	CA6	SX	-74.663	-74.663	0	%100
30	M64	SX	0	0	0	%100
31	M65	SX	0	0	0	%100
32	M66	SX	0	0	0	%100
33	M67	SX	0	0	0	%100
34	M68	SX	0	0	0	%100
35	M69	SX	0	0	0	%100
36	M70	SX	0	0	0	%100
37	M71	SX	0	0	0	%100
38	M72	SX	0	0	0	%100
39	M73	SX	0	0	0	%100
40	M74	SX	0	0	0	%100
41	M75	SX	-74.663	-74.663	0	%100
42	MP2	SX	-44.798	-44.798	0	%100
43	M43	SX	0	0	0	%100
44	M44	SX	0	0	0	%100
45	H3	SX	-44.798	-44.798	0	%100
46	MP7	SX	-44.798	-44.798	0	%100
47	MP9	SX	-44.798	-44.798	0	%100
48	HR3	SX	-44.798	-44.798	0	%100
49	M52	SX	0	0	0	%100
50	M53	SX	0	0	0	%100
51	M54	SX	0	0	0	%100
52	M55	SX	0	0	0	%100
53	H2	SX	-44.798	-44.798	0	%100
54	MP4	SX	-44.798	-44.798	0	%100
55	MP6	SX	-44.798	-44.798	0	%100
56	HR2	SX	-44.798	-44.798	0	%100
57	M66A	SX	0	0	0	%100
58	M67A	SX	0	0	0	%100
59	M68A	SX	0	0	0	%100
60	M69A	SX	0	0	0	%100
61	MP8	SX	-44.798	-44.798	0	%100
62	M68B	SX	0	0	0	%100
63	M69B	SX	0	0	0	%100
64	MP5	SX	-44.798	-44.798	0	%100
65	M71B	SX	0	0	0	%100
66	M72B	SX	0	0	0	%100
67	MP10	SX	-44.798	-44.798	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
68	M68D	SX	0	0	0	%100

Member Distributed Loads (BLC 16 : Ice Weight)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
1	S3	Y	-9.35	-9.35	0	%100
2	GA4	Y	-5.452	-5.452	0	%100
3	GA3	Y	-5.452	-5.452	0	%100
4	P3	Y	-10.527	-10.527	0	%100
5	S2	Y	-9.35	-9.35	0	%100
6	GA2	Y	-5.452	-5.452	0	%100
7	GA1	Y	-5.452	-5.452	0	%100
8	P2	Y	-10.527	-10.527	0	%100
9	S1	Y	-9.35	-9.35	0	%100
10	GA6	Y	-5.452	-5.452	0	%100
11	GA5	Y	-5.452	-5.452	0	%100
12	P1	Y	-10.527	-10.527	0	%100
13	H1	Y	-6.378	-6.378	0	%100
14	MP1	Y	-5.516	-5.516	0	%100
15	MP3	Y	-5.516	-5.516	0	%100
16	HR1	Y	-5.523	-5.523	0	%100
17	CA8	Y	-12.531	-12.531	0	%100
18	CA9	Y	-12.531	-12.531	0	%100
19	CA7	Y	-12.531	-12.531	0	%100
20	M32	Y	-1.554	-1.554	0	%100
21	M35	Y	-1.554	-1.554	0	%100
22	M36	Y	-1.554	-1.554	0	%100
23	M39A	Y	-1.554	-1.554	0	%100
24	CA3	Y	-7.009	-7.009	0	%100
25	CA4	Y	-7.009	-7.009	0	%100
26	CA1	Y	-7.009	-7.009	0	%100
27	CA2	Y	-7.009	-7.009	0	%100
28	CA5	Y	-7.009	-7.009	0	%100
29	CA6	Y	-7.009	-7.009	0	%100
30	M64	Y	-1.554	-1.554	0	%100
31	M65	Y	-1.554	-1.554	0	%100
32	M66	Y	-1.554	-1.554	0	%100
33	M67	Y	-1.554	-1.554	0	%100
34	M68	Y	-1.554	-1.554	0	%100
35	M69	Y	-1.554	-1.554	0	%100
36	M70	Y	-1.554	-1.554	0	%100
37	M71	Y	-1.554	-1.554	0	%100
38	M72	Y	-1.554	-1.554	0	%100
39	M73	Y	-1.554	-1.554	0	%100
40	M74	Y	-1.554	-1.554	0	%100
41	M75	Y	-4.899	-4.899	0	%100
42	MP2	Y	-5.516	-5.516	0	%100
43	M43	Y	-1.554	-1.554	0	%100
44	M44	Y	-1.554	-1.554	0	%100
45	H3	Y	-6.378	-6.378	0	%100
46	MP7	Y	-5.516	-5.516	0	%100
47	MP9	Y	-5.516	-5.516	0	%100

Member Distributed Loads (BLC 16 : Ice Weight) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
48	HR3	Y	-5.523	-5.523	0	%100
49	M52	Y	-1.554	-1.554	0	%100
50	M53	Y	-1.554	-1.554	0	%100
51	M54	Y	-1.554	-1.554	0	%100
52	M55	Y	-1.554	-1.554	0	%100
53	H2	Y	-6.378	-6.378	0	%100
54	MP4	Y	-5.516	-5.516	0	%100
55	MP6	Y	-5.516	-5.516	0	%100
56	HR2	Y	-5.523	-5.523	0	%100
57	M66A	Y	-1.554	-1.554	0	%100
58	M67A	Y	-1.554	-1.554	0	%100
59	M68A	Y	-1.554	-1.554	0	%100
60	M69A	Y	-1.554	-1.554	0	%100
61	MP8	Y	-5.516	-5.516	0	%100
62	M68B	Y	-1.554	-1.554	0	%100
63	M69B	Y	-1.554	-1.554	0	%100
64	MP5	Y	-5.516	-5.516	0	%100
65	M71B	Y	-1.554	-1.554	0	%100
66	M72B	Y	-1.554	-1.554	0	%100
67	MP10	Y	-5.516	-5.516	0	%100
68	M68D	Y	-1.554	-1.554	0	%100

Member Distributed Loads (BLC 29 : Distr. Ice Wind Load Z)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
1	S3	SZ	-10.355	-10.355	0	%100
2	GA4	SZ	-13.307	-13.307	0	%100
3	GA3	SZ	-13.307	-13.307	0	%100
4	P3	SZ	-9.968	-9.968	0	%100
5	S2	SZ	-10.355	-10.355	0	%100
6	GA2	SZ	-13.307	-13.307	0	%100
7	GA1	SZ	-13.307	-13.307	0	%100
8	P2	SZ	-9.968	-9.968	0	%100
9	S1	SZ	-10.355	-10.355	0	%100
10	GA6	SZ	-13.307	-13.307	0	%100
11	GA5	SZ	-13.307	-13.307	0	%100
12	P1	SZ	-9.968	-9.968	0	%100
13	H1	SZ	-12.174	-12.174	0	%100
14	MP1	SZ	-13.211	-13.211	0	%100
15	MP3	SZ	-13.211	-13.211	0	%100
16	HR1	SZ	-13.201	-13.201	0	%100
17	CA8	SZ	-9.499	-9.499	0	%100
18	CA9	SZ	-9.499	-9.499	0	%100
19	CA7	SZ	-9.499	-9.499	0	%100
20	M32	SZ	0	0	0	%100
21	M35	SZ	0	0	0	%100
22	M36	SZ	0	0	0	%100
23	M39A	SZ	0	0	0	%100
24	CA3	SZ	-11.622	-11.622	0	%100
25	CA4	SZ	-11.622	-11.622	0	%100
26	CA1	SZ	-11.622	-11.622	0	%100
27	CA2	SZ	-11.622	-11.622	0	%100

Member Distributed Loads (BLC 29 : Distr. Ice Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
28	CA5	SZ	-11.622	-11.622	0	%100
29	CA6	SZ	-11.622	-11.622	0	%100
30	M64	SZ	0	0	0	%100
31	M65	SZ	0	0	0	%100
32	M66	SZ	0	0	0	%100
33	M67	SZ	0	0	0	%100
34	M68	SZ	0	0	0	%100
35	M69	SZ	0	0	0	%100
36	M70	SZ	0	0	0	%100
37	M71	SZ	0	0	0	%100
38	M72	SZ	0	0	0	%100
39	M73	SZ	0	0	0	%100
40	M74	SZ	0	0	0	%100
41	M75	SZ	-14.283	-14.283	0	%100
42	MP2	SZ	-13.211	-13.211	0	%100
43	M43	SZ	0	0	0	%100
44	M44	SZ	0	0	0	%100
45	H3	SZ	-12.174	-12.174	0	%100
46	MP7	SZ	-13.211	-13.211	0	%100
47	MP9	SZ	-13.211	-13.211	0	%100
48	HR3	SZ	-13.201	-13.201	0	%100
49	M52	SZ	0	0	0	%100
50	M53	SZ	0	0	0	%100
51	M54	SZ	0	0	0	%100
52	M55	SZ	0	0	0	%100
53	H2	SZ	-12.174	-12.174	0	%100
54	MP4	SZ	-13.211	-13.211	0	%100
55	MP6	SZ	-13.211	-13.211	0	%100
56	HR2	SZ	-13.201	-13.201	0	%100
57	M66A	SZ	0	0	0	%100
58	M67A	SZ	0	0	0	%100
59	M68A	SZ	0	0	0	%100
60	M69A	SZ	0	0	0	%100
61	MP8	SZ	-13.211	-13.211	0	%100
62	M68B	SZ	0	0	0	%100
63	M69B	SZ	0	0	0	%100
64	MP5	SZ	-13.211	-13.211	0	%100
65	M71B	SZ	0	0	0	%100
66	M72B	SZ	0	0	0	%100
67	MP10	SZ	-13.211	-13.211	0	%100
68	M68D	SZ	0	0	0	%100

Member Distributed Loads (BLC 30 : Distr. Ice Wind Load X)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
1	S3	SX	-10.355	-10.355	0	%100
2	GA4	SX	-13.307	-13.307	0	%100
3	GA3	SX	-13.307	-13.307	0	%100
4	P3	SX	-9.968	-9.968	0	%100
5	S2	SX	-10.355	-10.355	0	%100
6	GA2	SX	-13.307	-13.307	0	%100
7	GA1	SX	-13.307	-13.307	0	%100

Member Distributed Loads (BLC 30 : Distr. Ice Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
8	P2	SX	-9.968	-9.968	0	%100
9	S1	SX	-10.355	-10.355	0	%100
10	GA6	SX	-13.307	-13.307	0	%100
11	GA5	SX	-13.307	-13.307	0	%100
12	P1	SX	-9.968	-9.968	0	%100
13	H1	SX	-12.174	-12.174	0	%100
14	MP1	SX	-13.211	-13.211	0	%100
15	MP3	SX	-13.211	-13.211	0	%100
16	HR1	SX	-13.201	-13.201	0	%100
17	CA8	SX	-9.499	-9.499	0	%100
18	CA9	SX	-9.499	-9.499	0	%100
19	CA7	SX	-9.499	-9.499	0	%100
20	M32	SX	0	0	0	%100
21	M35	SX	0	0	0	%100
22	M36	SX	0	0	0	%100
23	M39A	SX	0	0	0	%100
24	CA3	SX	-11.622	-11.622	0	%100
25	CA4	SX	-11.622	-11.622	0	%100
26	CA1	SX	-11.622	-11.622	0	%100
27	CA2	SX	-11.622	-11.622	0	%100
28	CA5	SX	-11.622	-11.622	0	%100
29	CA6	SX	-11.622	-11.622	0	%100
30	M64	SX	0	0	0	%100
31	M65	SX	0	0	0	%100
32	M66	SX	0	0	0	%100
33	M67	SX	0	0	0	%100
34	M68	SX	0	0	0	%100
35	M69	SX	0	0	0	%100
36	M70	SX	0	0	0	%100
37	M71	SX	0	0	0	%100
38	M72	SX	0	0	0	%100
39	M73	SX	0	0	0	%100
40	M74	SX	0	0	0	%100
41	M75	SX	-14.283	-14.283	0	%100
42	MP2	SX	-13.211	-13.211	0	%100
43	M43	SX	0	0	0	%100
44	M44	SX	0	0	0	%100
45	H3	SX	-12.174	-12.174	0	%100
46	MP7	SX	-13.211	-13.211	0	%100
47	MP9	SX	-13.211	-13.211	0	%100
48	HR3	SX	-13.201	-13.201	0	%100
49	M52	SX	0	0	0	%100
50	M53	SX	0	0	0	%100
51	M54	SX	0	0	0	%100
52	M55	SX	0	0	0	%100
53	H2	SX	-12.174	-12.174	0	%100
54	MP4	SX	-13.211	-13.211	0	%100
55	MP6	SX	-13.211	-13.211	0	%100
56	HR2	SX	-13.201	-13.201	0	%100
57	M66A	SX	0	0	0	%100
58	M67A	SX	0	0	0	%100
59	M68A	SX	0	0	0	%100

Member Distributed Loads (BLC 30 : Distr. Ice Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
60	M69A	SX	0	0	0	%100
61	MP8	SX	-13.211	-13.211	0	%100
62	M68B	SX	0	0	0	%100
63	M69B	SX	0	0	0	%100
64	MP5	SX	-13.211	-13.211	0	%100
65	M71B	SX	0	0	0	%100
66	M72B	SX	0	0	0	%100
67	MP10	SX	-13.211	-13.211	0	%100
68	M68D	SX	0	0	0	%100

Member Distributed Loads (BLC 44 : BLC 1 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
1	S2	Y	-3.185	-3.185	16.404	40
2	GA2	Y	-1.605	-1.605	3.828	27.295
3	GA1	Y	-1.605	-1.605	3.828	27.295
4	S3	Y	-3.185	-3.185	16.404	40
5	GA4	Y	-1.605	-1.605	3.828	27.295
6	GA3	Y	-1.605	-1.605	3.828	27.295
7	S1	Y	-3.185	-3.185	16.404	40
8	GA6	Y	-1.605	-1.605	3.828	27.295
9	GA5	Y	-1.605	-1.605	3.828	27.295

Member Distributed Loads (BLC 45 : BLC 16 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft,F,psf]	End Magnitude[lb/ft,F,psf]	Start Location[in,..	End Location[in,...
1	S2	Y	-19.112	-19.112	16.404	40
2	GA2	Y	-9.631	-9.631	3.828	27.295
3	GA1	Y	-9.631	-9.631	3.828	27.295
4	S3	Y	-19.112	-19.112	16.404	40
5	GA4	Y	-9.631	-9.631	3.828	27.295
6	GA3	Y	-9.631	-9.631	3.828	27.295
7	S1	Y	-19.112	-19.112	16.404	40
8	GA6	Y	-9.631	-9.631	3.828	27.295
9	GA5	Y	-9.631	-9.631	3.828	27.295

Member Area Loads (BLC 1 : Self Weight)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
1	P22	P21	P20	P23	Y	Two Way	-1.75
2	P10	P11	P12	P9	Y	Two Way	-1.75
3	P31	P34	P33	P32	Y	Two Way	-1.75

Member Area Loads (BLC 16 : Ice Weight)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
1	P22	P21	P20	P23	Y	Two Way	-10.5
2	P10	P11	P12	P9	Y	Two Way	-10.5
3	P31	P34	P33	P32	Y	Two Way	-10.5

Envelope AISC 15th(360-16): LRFD Steel Code Checks

	Member	Shape	Code Check	Loc[in]	LC	Shear ...	Loc[in]	Dir	LC	phi*Pnc ...	phi*Pnt [lb]	phi*Mn y-y ...	phi*Mn z-z [l...	Cb	Eqn
1	S3	HSS4X...	.217	0	13	.111	0	y	114	188250....	197892	22045.5	22045.5	1.815	H1-1b
2	GA4	L2x2x4	.171	0	2	.012	27.295	y	9	29527.5...	42480	959.63	2190.068	2.198	H2-1
3	GA3	L2x2x4	.145	0	7	.016	27.295	y	30	29527.5...	42480	959.63	2190.068	2.197	H2-1
4	P3	PL6.5x...	.280	21	2	.130	36.312	y	5	3658.14	78975	616.993	7989.049	1.421	H1-1b
5	S2	HSS4X...	.221	0	5	.110	0	y	142	188250....	197892	22045.5	22045.5	1.804	H1-1b
6	GA2	L2x2x4	.156	0	12	.013	0	y	12	29527.5...	42480	959.63	2190.068	2.338	H2-1
7	GA1	L2x2x4	.146	0	6	.015	27.295	y	34	29527.5...	42480	959.63	2190.068	2.288	H2-1
8	P2	PL6.5x...	.275	21	6	.119	36.312	y	10	3658.14	78975	616.993	7967.186	1.417	H1-1b
9	S1	HSS4X...	.202	0	9	.108	0	y	86	188250....	197892	22045.5	22045.5	1.833	H1-1b
10	GA6	L2x2x4	.144	0	4	.012	0	y	4	29527.5...	42480	959.63	2190.068	2.298	H2-1
11	GA5	L2x2x4	.161	0	9	.016	27.295	z	2	29527.5...	42480	959.63	2190.068	2.191	H2-1
12	P1	PL6.5x...	.257	21	10	.130	36.312	y	2	3658.14	78975	616.993	7989.594	1.421	H1-1b
13	H1	Pipe3.5...	.106	31	10	.062	48		4	45873.0...	71580.6	6337.65	6337.65	2.084	H1-1b
14	MP1	PIPE_...	.128	70	11	.079	26		8	33487.3...	66654	4726.5	4726.5	2.631	H1-1b
15	MP3	PIPE_...	.126	70	5	.072	70		3	33487.3...	66654	4726.5	4726.5	4.415	H1-1b
16	HR1	2.88x0...	.213	6	4	.097	6		4	22491.6...	43076.493	3155.674	3155.674	1.917	H1-1b
17	CA8	L6.6x4...	.227	41.562	22	.032	42	z	4	51170.9...	87561	2464.809	7125.374	1.136	H2-1
18	CA9	L6.6x4...	.204	41.562	6	.028	42	z	12	51170.9...	87561	2464.809	7125.374	1.136	H2-1
19	CA7	L6.6x4...	.221	41.562	3	.030	42	z	8	51170.9...	87561	2464.809	7125.374	1.136	H2-1
20	CA3	C3.38x...	.249	0	2	.034	28.188	y	32	47760.0...	56700	2202.821	5751.945	1.619	H1-1b
21	CA4	C3.38x...	.258	33	2	.033	33	y	115	47760.0...	56700	2202.821	5751.945	1.635	H1-1b
22	CA1	C3.38x...	.250	0	6	.034	28.188	y	36	47760.0...	56700	2202.821	5751.945	1.623	H1-1b
23	CA2	C3.38x...	.244	33	6	.033	33	y	143	47760.0...	56700	2202.821	5751.945	1.627	H1-1b
24	CA5	C3.38x...	.255	0	10	.032	28.187	y	28	47760.0...	56700	2202.821	5751.945	1.624	H1-1b
25	CA6	C3.38x...	.240	33	10	.032	33	y	87	47760.0...	56700	2202.821	5751.945	1.629	H1-1b
26	M75	PL 2.3...	.225	1.5	12	.185	0	y	173	38256.8...	38475	400.783	1903.711	2.21	H1-1b
27	MP2	PIPE_...	.185	70	5	.066	70		5	33487.3...	66654	4726.5	4726.5	4.426	H1-1b
28	H3	Pipe3.5...	.111	31	2	.070	90		2	45873.0...	71580.6	6337.65	6337.65	1.933	H1-1b
29	MP7	PIPE_...	.122	70	9	.065	26		6	33487.3...	66654	4726.5	4726.5	3.382	H1-1b
30	MP9	PIPE_...	.145	70	2	.065	70		7	33487.3...	66654	4726.5	4726.5	3.326	H1-1b
31	HR3	2.88x0...	.219	6	2	.103	92		6	22491.6...	43076.493	3155.674	3155.674	1.782	H1-1b
32	H2	Pipe3.5...	.106	31	6	.050	48		12	45873.0...	71580.6	6337.65	6337.65	1.773	H1-1b
33	MP4	PIPE_...	.125	70	7	.072	26		4	33487.3...	66654	4726.5	4726.5	1.746	H1-1b
34	MP6	PIPE_...	.132	70	7	.071	70		6	33487.3...	66654	4726.5	4726.5	4.606	H1-1b
35	HR2	2.88x0...	.222	90	3	.111	92		4	22491.6...	43076.493	3155.674	3155.674	1.666	H1-1b
36	MP8	PIPE_...	.161	70	9	.070	70		3	33487.3...	66654	4726.5	4726.5	4.056	H1-1b
37	MP5	PIPE_...	.180	70	7	.056	70		7	33487.3...	66654	4726.5	4726.5	4.499	H1-1b
38	MP10	PIPE_...	.004	9	8	.004	9		8	63847.2...	66654	4726.5	4726.5	1.943	H1-1b

INFINIGY

FROM ZERO TO INFINIGY

the solutions are endless

Bolt Calculation Tool, V1.5.1

PROJECT DATA	
Site Name:	BOHVN00146A
Site Number:	BOHVN00146A
Connection Description:	Platform to Monopole

MAXIMUM BOLT LOADS		
Bolt Tension:	5963.84	lbs
Bolt Shear:	1629.77	lbs

WORST CASE BOLT LOADS[1]		
Bolt Tension:	5963.84	lbs
Bolt Shear:	408.25	lbs

BOLT PROPERTIES		
Bolt Type:	Bolt	-
Bolt Diameter:	0.625	in
Bolt Grade:	A325	-
# of Bolts:	4	-
Threads Excluded?	No	-

[1] *Worst case bolt loads correspond to Load combination #5 on member S2 in RISA-3D, which causes the maximum demand on the bolts.*

Member Information
I nodes of S3, S2, S1

BOLT CHECK		
Tensile Strength	20340.15	
Shear Strength	13805.83	
Max Tensile Usage	29.3%	
Max Shear Usage	11.8%	
Interaction Check (Worst Case)	0.09	***≤1.05***
Result	Pass	



POWER DENSITY STUDY

EBI Consulting

environmental | engineering | due diligence

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOHVN00146A

BOHVN00146A
8 Old 79
Madison, Connecticut 06443

April 19, 2022

EBI Project Number: 6222004012

Site Compliance Summary	
Compliance Status:	**COMPLIANT**
Site total MPE% of FCC general population allowable limit:	**39.45%**

April 19, 2022

Dish Wireless

Emissions Analysis for Site: BOHVN00146A - BOHVN00146A

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **8 Old 79** in **Madison, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu W/cm^2$). The number of $\mu W/cm^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu W/cm^2$). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately 400 $\mu W/cm^2$ and 467 $\mu W/cm^2$, respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is 1000 $\mu W/cm^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.

Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed Dish Wireless antenna facility located at 8 Old 79 in Madison, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.

2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.

3) 4 n66 channels (AWS Band - 2190 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.

4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

5) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative

estimate as gain reductions for these particular antennas are typically much higher in this direction.

6) The antennas used in this modeling are the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector A, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector B, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

7) The antenna mounting height centerline of the proposed antennas is 110 feet above ground level (AGL).

8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

9) All calculations were done with respect to uncontrolled / general population threshold limits.

Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	JMA MX08FRO665-21	Make / Model:	JMA MX08FRO665-21	Make / Model:	JMA MX08FRO665-21
Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz
Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd
Height (AGL):	110 feet	Height (AGL):	110 feet	Height (AGL):	110 feet
Channel Count:	12	Channel Count:	12	Channel Count:	12
Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts
ERP (W):	5,236.31	ERP (W):	5,236.31	ERP (W):	5,236.31
Antenna A1 MPE %:	**2.19%**	Antenna B1 MPE %:	**2.19%**	Antenna C1 MPE %:	**2.19%**

Site Composite MPE %	
Carrier	**MPE %**
Dish Wireless (Max at Sector A):	2.19%
AT&T	4.36%
Metro PCS	1.06%
Nextel	0.34%
T-Mobile	13.7%
Verizon	16.17%
Town	0.14%
Sprint	1.49%
Site Total MPE % :	39.45%

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	2.19%
Dish Wireless Sector B Total:	2.19%
Dish Wireless Sector C Total:	2.19%
Site Total MPE % :	39.45%

Dish Wireless Maximum MPE Power Values (Sector A)

Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (μW/cm²)	Frequency (MHz)	Allowable MPE (μW/cm²)	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	110.0	2.97	600 MHz n71	400	0.74%
Dish Wireless 1900 MHz n70	4	542.70	110.0	7.22	1900 MHz n70	1000	0.72%
Dish Wireless 2190 MHz n66	4	542.70	110.0	7.22	2190 MHz n66	1000	0.72%
						Total:	**2.19%**

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	2.19%
Sector B:	2.19%
Sector C:	2.19%
Dish Wireless Maximum MPE % (Sector A):	2.19%
Site Total:	39.45%
Site Compliance Status:	**COMPLIANT**

The anticipated composite MPE value for this site assuming all carriers present is **39.45%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

UNDERLYING PROPERTY INFORMATION

8 OLD ROUTE 79

Location	8 OLD ROUTE 79	**MBLU**	48/ 53/ / /
Unique ID#	00321200	**Owner**	CK BUILDERS LLC
Assessment	$299,500	**Appraisal**	$427,700
PID	3310	**Building Count**	1
Dev. Map			

Current Value

Appraisal					
Valuation Year	**Building**	**Extra Features**	**Outbuildings**	**Land**	**Total**
2021	$0	$0	$22,500	$405,200	$427,700
Assessment					
Valuation Year	**Building**	**Extra Features**	**Outbuildings**	**Land**	**Total**
2021	$0	$0	$15,800	$283,700	$299,500

Owner of Record

Owner	CK BUILDERS LLC	**Sale Price**	$0
Co-Owner		**Book & Page**	1340/0270
Care Of		**Sale Date**	12/21/2004

Ownership History

Ownership History			
Owner	**Sale Price**	**Book & Page**	**Sale Date**
CK BUILDERS LLC	$0	1340/0270	12/21/2004
TOWN OF MADISON	$0	0136/0597	01/12/1971

Building Information

Building 1 : Section 1

Year Built:
Living Area: 0

Building Attributes	
Field	**Description**

Style:	Vacant Land
Model	
Grade:	
Stories:	
Occupancy	
Exterior Wall 1	
Exterior Wall 2	
Roof Structure:	
Roof Cover	
Interior Wall 1	
Interior Wall 2	
Interior Flr 1	
Interior Flr 2	
Heat Fuel	
Heat Type:	
AC Type:	
Total Bedrooms:	
Total Bthrms:	
Total Half Baths:	
Total Xtra Fixtrs:	
Total Rooms:	
Bath Style:	
Kitchen Style:	
Num Kitchens	
Cndtn	
Fireplace(s)	
Xtra FPL Open	
Num Park	
Fireplaces	
Fndtn Cndtn	
Basement	

Building Photo

(https://images.vgsi.com/photos/MadisonCTPhotos//\01\01\78\64.jpg)

Building Sub-Areas (sq ft)
No Data for Building Sub-Areas

Extra Features

Extra Features
No Data for Extra Features

Land

Land Use

Use Code 4310

Land Line Valuation

Size (Acres) 1.02

Description TEL REL TW
Zone R-1

Outbuildings

Outbuildings						
Code	**Description**	**Sub Code**	**Sub Description**	**Size**	**Value**	**Bldg #**
FND	Foundation			1.00 UNITS	$22,500	1

NOTIFICATIONS

May 17, 2022

Dear Customer,

The following is the proof-of-delivery for tracking number: 776820958475

Delivery Information:

Status:	Delivered	**Delivered To:**	Shipping/Receiving
Signed for by:	S.IGNATURE ON FILE	**Delivery Location:**	8 CAMPUS DR
Service type:	FedEx 2Day		
Special Handling:	Deliver Weekday		MADISON, CT, 06443
		Delivery date:	May 12, 2022 12:19

Shipping Information:

Tracking number:	776820958475	**Ship Date:**	May 10, 2022
		Weight:	1.0 LB/0.45 KG

Recipient:
Peggy Lyons, First Selectwoman
8 Campus Drive
MADISON, CT, US, 06443

Shipper:
Corey Milan, NB+C
100 Apollo Dr.
Suite 303
CHELMSFORD, MA, US, 01824

Reference 100814

Thank you for choosing FedEx

May 17, 2022

Dear Customer,

The following is the proof-of-delivery for tracking number: 776820995079

Delivery Information:

Status:	Delivered	**Delivered To:**	Shipping/Receiving
Signed for by:	S.IGNATURE ON FILE	**Delivery Location:**	8 CAMPUS DR
Service type:	FedEx 2Day		
Special Handling:	Deliver Weekday		MADISON, CT, 06443
		Delivery date:	May 12, 2022 12:19

Shipping Information:

Tracking number:	776820995079	**Ship Date:**	May 10, 2022
		Weight:	1.0 LB/0.45 KG

Recipient:
Vincent Garofalo, Building Official
8 Campus Drive
MADISON, CT, US, 06443

Shipper:
Corey Milan, NB+C
100 Apollo Dr.
Suite 303
CHELMSFORD, MA, US, 01824

Reference 100814

Thank you for choosing FedEx

May 17, 2022

Dear Customer,

The following is the proof-of-delivery for tracking number: 776820872947

Delivery Information:

Status:	Delivered	**Delivered To:**	Shipping/Receiving
Signed for by:	S.IGNATURE NOT REQ	**Delivery Location:**	109 OLD DIKE RD
Service type:	FedEx 2Day		
Special Handling:	Deliver Weekday		TRUMBULL, CT, 06611
		Delivery date:	May 12, 2022 12:51

Shipping Information:

Tracking number:	776820872947	**Ship Date:**	May 10, 2022
		Weight:	1.0 LB/0.45 KG

Recipient:
CK Builders LLC - Owner,
109 Old Dike Road
TRUMBULL, CT, US, 06611

Shipper:
Corey Milan, NB+C
100 Apollo Dr.
Suite 303
CHELMSFORD, MA, US, 01824

Reference 100814

Thank you for choosing FedEx