

July 21, 2015

Honorable Robert Stein, Chairman, And Members of the Connecticut Siting Council Connecticut Siting Council 10 Franklin Square New Britain, Connecticut 06051

Re: Notice of Exempt Modification – Existing Sprint Telecommunication Facility at 239 Middle Turnpike East, Manchester, CT 06040

Dear Chairman Stein and Members of the Council:

Sprint intends to modify the existing telecommunications antennas and associated equipment at an existing multicarrier telecommunications tower at 239 Middle Turnpike in Manchester, Connecticut. Sprint operates under licenses issued by the Federal Communications Commission ("FCC") to provide cellular and PCS mobile telephone service in Hartford County, which includes the area to be served by Sprint's proposed installation.

In order to accommodate technological changes, implement 2.5 Modification capabilities, and enhance system performance in the State of Connecticut, Sprint plans to modify the equipment configurations at many of its existing cell sites. 2.5 Modification is a new high-performance air interface for cellular mobile communications. It is designed to increase the capacity and speed of mobile telephone networks.

Please accept this letter as notification to the Council, pursuant to R.C.S.A. Section 16-50j-73, of construction which constitutes an exempt modification pursuant to R.C.S.A. Section 16-50j-72(b)(2). In compliance with R.C.S.A. Section 16-50j-73, a copy of this letter is being sent to Mr. Scott Shanley, General Manager of the Town of Manchester.

Attached is a summary of the planned modifications, including power density calculations reflecting the change in Sprint's operations at the site. Also included is documentation of the structural sufficiency of the tower with proposed modifications to accommodate the revised antenna configuration.

## **Existing Facility**

The Manchester facility is located at 239 Middle Turnpike East at the Manchester Police Department. The facility is located at the Police Department, which is at the intersection of



Middle Turnpike East and Princeton Street. Site coordinates: 41.7844 N, - 72.5117 W.

The facility is owned by the Town Manchester with an address of 41 Center Street.

The existing facility consists of a 190' monopole tower with an existing chain link fence around the tower compound. Sprint currently operates wireless communications equipment at the facility and has six antennas mounted on the tower at a centerline of 153 feet.

## **Statutory Considerations**

The changes to the Manchester tower facility do not constitute a modification as defined in Connecticut General Statutes ("C.G.S.") Section 16-50i(d) because the general physical characteristics of the facility will not be significantly changed or altered. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in R.C.S.A. Section 16-50j-72(b)(2) because they will not result in any substantial adverse environmental effect.

- 1. The height of the overall structure will be unaffected.
- 2. The proposed changes will not affect the property boundaries. All new construction will take place inside the existing fenced compound.
- 3. The proposed additions will not increase the noise level at the existing facility by six decibels or more.
- 4. 2.5 Modernization will utilize additional radio frequencies newly licensed by the FCC for cellular mobile communications. However, the changes will not increase the calculated "worst case" power density for the combined operations at the site to a level at or above the applicable standard for uncontrolled environments as calculated for a mixed frequency site.



For the foregoing reasons, Sprint respectfully submits that the proposed changes at the referenced site constitute exempt modifications under R.C.S.A Section §16-50j-72(b)(2).

Respectfully yours,

Paul Reed

Real Estate Consultant

Enclosures:

Mr. Scott Shanley, General Manager, Town of Manchester

95 Ryan Drive Suite 1, Raynham, MA 02767 Office: 413.528.1634 Fax: 617.249.0819 preed@clinellc.com | www.centerlinecom.net

SPECIAL CONSTRUCTION NOTE: SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:

\* COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY A&E VENDOR)

COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR)

GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT

SPRINT CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S



## NOTE:

OWNER AND TENANT MAY, FROM TIME TO TIME AT TENANT'S OPTION, REPLACE THIS EXHIBIT WITH AN EXHIBIT SETTING FORTH THE LEGAL DESCRIPTION OF THE SITE, OR WITH ENGINEERED OR AS—BUILT DRAWING DEPICTING THE SITE OR ILLUSTRATING STRUCTURAL MODIFICATIONS OR CONSTRUCTION PLANS OF THE SITE. ANY VISUAL OR TEXTUAL REPRESENTATION OF THE EQUIPMENT LOCATED WITHIN THE SITE CONTAINED IN THESE OTHER DOCUMENTS IS ILLUSTRATIVE ONLY, AND DOES NOT LIMIT THE RIGHTS OF SPRINT AS PROVIDED FOR IN THE AGREEMENT. THE LOCATIONS OF ANY ACCESS AND UTILITY EASEMENTS ARE ILLUSTRATIVE ONLY, ACTUAL LOCATIONS MAY BE DETERMINED BY TENANT AND/OR THE SERVICING UTILITY COMPANY IN COMPLIANCE WITH LOCAL LAWS AND REGULATIONS.

STRUCTURAL NOTE: STRUCTURAL INFORMATION TAKEN FROM REVISED STRUCTURAL ANALYSIS PERFORMED BY HUDSON DESIGN GROUP LLC DATED: APRIL 10, 2015

PROJECT: 2.5 EQUIPMENT DEPLOYMENT

SITE NAME: MANCHESTER / POLICE TOWER

SITE CASCADE: CT43XC827

MARKET: NORTHERN CONNECTICUT

SITE ADDRESS: 239 MIDDLE TURNPIKE

MANCHESTER, CT 06040

SHEET NO:

SITE TYPE: 190' MONOPOLE

## SITE INFORMATION

## PROPERTY OWNER:

TOWN OF MANCHESTER 41 CENTER STREET MANCHESTER, CT

LATITUDE (NAD83):
GOOGLE EARTH 2-C CONFIRMATION 41° 47' 3.84" N

## LONGITUDE (NAD83):

GOOGLE EARTH 2-C CONFIRMATION

-72° 30 42.12" W -72.5117°

COUNTY:

HARTFORD, CT

## **ZONING JURISDICTION:**

TOWN OF MANCHESTER

## **ZONING DISTRICT:**

RURAL RESIDENTIAL

## POWER COMPANY:

CONNECTICUT LIGHT & POWER

## SPRINT MARKET MANAGER:


PETER GIARD PHONE: 508-801-0074 peter.giard@sprint.com

## SPRINT CM:

PETER CULBERT PHONE: 603-203-6446 PHONE: 603-969-0686 peter.culbert@sprint.com

## **EQUIPMENT SUPPLIER:**

ALCATEL-LUCENT 600 MOUNTAIN AVENUE MURRAY HILL, NJ 07974



SPRINT EQUIPMENT MODIFICATIONS REQUIRED TO SUPPORT MODERNIZATION OF AN EXISTING WIRELESS COMMUNICATIONS FACILITY AND UTILIZATION OF FCC BROADBAND SPECTRUM LICENSE FOR 2.5GHz FREQUENCY, INCLUDING INSTALLATION OF:

PROJECT DESCRIPTION

GROUND-LEVEL RAN EQUIPMENT, CONSISTING OF:
\* INSTALL NEW MMBTS CABINET WITH 2.5 RADIO ACCESS NETWORK (RAN) EQUIPMENT & BBU KIT

(1) ADDITIONAL BATTERY STRING(S) INSIDE EXISTING BATTERY BACKUP (BBU) CABINET

## MONOPOLE-TOP EQUIPMENT, INCLUDING INSTALLATION OF:

- \* (3) PANEL ANTENNAS
- \* (3) REMOTE RADIO HEADS (RRH)
- \* (1) HYBRID CABLE, AND ASSOCIATED FIBER, DC POWER, COAXIAL CABLE JUMPERS AND ANTENNA REMOTE ELECTRICAL-TILT (RET) CABLE

SPECIAL ZONING NOTE:
BASED ON INFORMATION PROVIDE BY SPRINT REGULATORY COMPLIANCE PROFESSIONALS AND LEGAL COUNSEL, THIS TELECOMMUNICATIONS EQUIPMENT DEPLOYMENT IS CONSIDERED AND ELIGIBLE FACILITY UNDER THE TAX RELIEF ACT OF 2012, 47 USC 1455(A), AND IS SUBJECT TO AN EXPEDITED ELIGIBLE FACILITIES REQUEST/REVIEW AND ZONING PRE-EMPTION FOR LOCAL DISCRETIONARY PERMITS (VARIANCE, SPECIAL PERMIT, SITE PLAN REVIEW, ADMINISTRATIVE REVIEW)

T-1	TITLE SHEET	2	BB	JA
SP-1	OUTLINE SPECIFICATIONS	2	BB	JA
SP-2	OUTLINE SPECIFICATIONS	2	BB	JA
SP-3	OUTLINE SPECIFICATIONS	2	BB	JA
A-1	COMPOUND PLAN	2	BB	JA
A-2	EQUIPMENT PLAN	2	BB	JA
A-3	ELEVATION	2	BB	JA
A-4	ANTENNA PLANS	2	BB	JA
A-5	RAN WIRING DIAGRAM	2	BB	JA
A-6	EQUIPMENT DETAILS	2	BB	JA
S-1	MODIFICATION ELEVATION & NOTES	2	BB	JA
S-2	MODIFICATION ELEVATION & NOTES	2	BB	JA
S-3	MODIFICATION ELEVATION & NOTES	2	BB	JA
S-4	STRUCTURAL DETAILS	2	BB	JA
E-1	ONE LINE DIAGRAM	2	BB	JA
E-2	GROUNDING DETAILS AND NOTES	2	BB	JA

DRAWING INDEX

REV CHK

BY

SHEET TITLE

## GENERAL NOTES

- 1. THIS IS AN UNMANNED TELECOMMUNICATION FACILITY AND NOT FOR HUMAN HABITATION:
- ADA COMPLIANCE NOT REQUIRED.
- POTABLE WATER OR SANITARY SERVICE IS NOT REQUIRED.
- NO OUTDOOR STORAGE OR ANY SOLID WASTE RECEPTACLES REQUIRED
   CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON JOB SITE, CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK, FAILURE TO NOTIFY THE ARCHITECT/ENGINEER PLACE THE RESPONSIBILITY ON THE CONTRACTOR
- TO CORRECT THE DISCREPANCIES AT THE CONTRACTOR'S EXPENSE. NEW CONSTRUCTION WILL CONFORM TO ALL APPLICABLE CODES AND

BUILDING CODE: 2009 IBC WITH NEW HAMPSHIRE AMENDMENTS ELECTRICAL CODE: 2005 NATIONAL ELECTRICAL CODE STRUCTURAL CODE: TIA/EIA—222—G STRUCTURAL STANDARDS FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS.



LANDLORD/

THE FOLLOWING PARTIES HEREBY APPROVE AND ACCEPT THESE DOCUMENTS AND AUTHORIZE THE CONTRACTOR TO PROCEED WITH THE CONSTRUCTION DESCRIBED HEREIN. ALL DOCUMENTS ARE SUBJECT TO REVIEW BY THE LOCAL BUILDING DEPARTMENT AND MAY IMPOSE CHANGES OR MODIFICATIONS.

**APPROVALS** 

PRINT:	 DATE:	
ONSTRUCTION ANAGER:	 DATE:	
ASING/ FE ACQUISITION:	DATE:	
ENGINEER:	DATE:	

DATE:







CHECKED BY:

APPROVED BY: DPH **SUBMITTALS** 

REV.	DATE	DESCRIPTION	BY
2	06/26/15	ISSUED FOR CONSTRUCTION	JA
		ISSUED FOR CONSTRUCTION	JA
0	02/10/14	ISSUED FOR REVIEW	NB
=			

SITE NUMBER: CT43XC827 SITE NAME:

MANCHESTER/POLICE TOWER

SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

TITLE SHEET

\_\_ ′

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

## SECTION 01 100 - SCOPE OF WORK

PART 1 - GENERAL

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES. CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR

### 1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS

#### 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:

- A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
- 1. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT. 2. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC
- CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT. 3. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING
- NFPA 70 (NATIONAL ELECTRICAL CODE "NEC") AND NFPA 101 (LIFE SAFETY CODE). 4. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
- 5. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
- AMERICAN CONCRETE INSTITUTE (ACI)
- 7. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
- 8. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
- 9. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) 10. PORTLAND CEMENT ASSOCIATION (PCA)
- 11. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
- 12. BRICK INDUSTRY ASSOCIATION (BIA)
- 13. AMERICAN WELDING SOCIETY (AWS)
- 14. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
- 15. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
- 16. DOOR AND HARDWARE INSTITUTE (DHI)
- 17. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
- 18. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

- WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- COMPANY: SPRINT CORPORATION
- ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK
- THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RÉLATED TO BUT NOT INCLUDED IN THE WORK.
- OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- CONSTRUCTION MANAGER ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT ...
- SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 <u>DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE:</u> THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH
- A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS
- DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
- . DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.

- 1.11 <u>UTILITIES SERVICES:</u> WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.
  - TOP HAT
  - HOW TO INSTALL A NEW CABINET
  - BASE BAND UNIT IN EXISTING UNIT INSTALLATION OF BATTERIES
  - INSTALLATION OF HYBRID CABLE
  - INSTALLATION OF RRH'S
  - CABLING
  - SPRINT TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS SPRINT CELL SITE ENGINEERING NOTICE EN 2012-001, REV 1.

  - SPRINT CELL SITE ENGINEERING NOTICE EN-2013-002 SPRINT ENGINEERING LETTER EL-0504 SPRINT ENGINEERING LETTER EL-0568

  - N. SPRINT TECHNICAL SPECIFICATION TS-0193
- USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:
  - CONTRACTOR WILL UTILIZE ITS BEST EFFORTS TO WORK WITH SPRINT ELECTRONIC PROJECT MANAGEMENT SYSTEMS. CONTRACTOR UNDERSTANDS THAT SUFFICIENT INTERNET EQUIVALENT TO "BROADBAND" OR BETTER, IS REQUIRED TO TIMELY AND EFFECTIVELY UTILIZE SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS AND AGREES TO MAINTAIN APPROPRIATE CONNECTIONS FOR CONTRACTOR'S STAFF AND OFFICES THAT ARE COMPATIBLE WITH SPRINT DATA AND DOCUMENT MANAGEMENT SYSTEMS

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 <u>TEMPORARY UTILITIES AND FACILITIES:</u> THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANĆE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.
- 3.5 <u>EXISTING CONDITIONS</u>: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND FNGINFFR.

## SECTION 01 200 - COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 - GENERAL

1.1 <u>THE WORK:</u> THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

## 1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION
- SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

## 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:

- A. COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE
- THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON
  - ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
    VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
  - TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
- RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
- PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
- COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.

- A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
- IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
- C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

## SECTION 01 300 - CELL SITE CONSTRUCTION

- 1.1 <u>THE WORK:</u> THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

## 1.3 NOTICE TO PROCEED:

- A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
- B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.
- PART 2 PRODUCTS (NOT USED)

PART 3 - EXECUTION

#### 3.1 FUNCTIONAL REQUIREMENTS:

- A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH
- B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
- C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
- D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  - PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
  - PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
  - MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
- INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATION CONDUITS. AND UNDERGROUND GROUNDING SYSTEM.
  - INSTALL ABOVE GROUND GROUNDING SYSTEMS.
- PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS
- INSTALL "H-FRAMES". CABINETS AND SHELTERS AS INDICATED
- INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
- ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
- PROVIDE SLABS AND EQUIPMENT PLATFORMS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS 13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
- 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER 15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
- INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
- 17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.

  18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE
- REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS. 19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY
- 20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

## 3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK. CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS. C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS
- IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN
- ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT

WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN

- THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN

## 3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.

  1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.


FORWARD NOTIFICATION).

- CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION). TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
- PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION)
- CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION) TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD
- NOTIFICATION) 11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR
- 12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS) 13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD
- 14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS. CONTINUE SHEET SP-2

**Sprint** 

MAHWAH, NJ 07495 EL: (800) 357-7641





CHECKED BY

APPROVED BY

SUBMITTALS DESCRIPTION 2 | 06/26/15 | ISSUED FOR CONSTRUCTION | J 1 06/23/15 ISSUED FOR CONSTRUCTION JA 0 02/10/14 ISSUED FOR REVIEW

CT43XC827 SITE NAME: MANCHESTER/POLICE TOWER SITE ADDRESS:

SITE NUMBER:

239 MIDDLE TURNPIKE

MANCHESTER, CT 06040

**OUTLINE SPECIFICATIONS** 

## SECTION 01 400 - SUBMITTALS, TESTS, AND INSPECTIONS

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

#### 1.3 SUBMITTALS

- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
- SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL.

  1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
- CONCRETE BREAK TESTS AS SPECIFIED HEREIN. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY
- ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS
- CHEMICAL GROUNDING DESIGN.
- C. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY NO VERBAL APPROVALS WILL BE CONSIDERED. THOSE REQUESTS MADE IN WRITING. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

## 1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
- 1. COAX SWEEPS AND FIBER TESTS PER SPRINT TS-0200 (CURRENT VERSION) ANTENNA LINE ACCEPTANCE STANDARDS
- 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING;
- 1. AZIMUTH, DOWNTILT, AGL UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
- 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
- PDF SCAN OF REDLINES PRODUCED IN FIELD
- ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
- LIEN WAIVERS
- FINAL PAYMENT APPLICATION
- 8. REQUIRED FINAL CONSTRUCTION PHOTOS
- 9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
- 10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).
- COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPS
- 1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPS

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

## 3.1 REQUIREMENTS FOR TESTING:

- THIRD PARTY TESTING AGENCY: WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
  - THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY
  - EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
  - 3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

## 3.2 REQUIRED TESTS:

- A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
- 1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
  ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY
- TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.

  3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE
- 4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND
- 5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
- 6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
  7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE 3.1 WEEKLY REPORTS:
- GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
- ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION

### 3.3 REQUIRED INSPECTIONS:

- A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.
- CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING
- GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL
- PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE
- FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
- COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY PRE— AND POST—CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING
- 5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL 3.4 ADDITIONAL REPORTING:
- PHOTOGRAPHS BY THIRD PARTY AGENCY. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS -
- ANTENNALIGN ALIGNMENT TOOL (AAT) THE ANTENNA CHECKLIST REPORT, BY A&E, SITE 3.5 PROJECT PHOTOGRAPHS: DOCUMENTED
- DEVELOPMENT REP, OR RF REP. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC.). SIGNED FORM SHOWING
- ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.

  COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE S 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER FOLIPMENT
- ALL AVAILABLE JURISDICTIONAL INFORMATION
- 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF
- CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 <u>DELIVERABLES</u>: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
  - CONCRETE MIX AND CYLINDER BREAK REPORTS
  - STRUCTURAL BACKFILL COMPACTION REPORTS.
  - SITE RESISTANCE TO FARTH TEST.
  - ANTENNA AZIMUTH AND DOWN TILT VERIFICATION TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER
- SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS"
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING:
  - TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
  - CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING:
- 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE: PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
- TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS: PHOTOGRAPHS TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR. EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING TOP AND BOTTOM: PHOTOS OF COAX GROUNDING--TOP AND BOTTOM: PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM
- MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.

  ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION: PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE: PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF:
- SITE LAYOUT PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
- FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL
- REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.

  ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

## SECTION 01 500 - PROJECT REPORTING

PART 1 - GENERAL

1.1 <u>THE WORK:</u> THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

## 1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE

B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

### 3.3 PROJECT TRACKING IN SMS:

A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
  - 1. SHELTER AND TOWER OVERVIEW.
  - TOWER FOUNDATION(S) FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
  - TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
  - TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS). PHOTOS OF TOWER SECTION STACKING.
  - CONCRETE TESTING / SAMPLES.
  - PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION
  - BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
- SHELTER FOUNDATION -- FORMS AND STEEL BEFORE POURING.
- 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
- COAX CABLE ENTRY INTO SHELTER
- 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR
- 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.

- 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
  17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY. LOCATIONS INCLUDING METER/DISCONNECT.
- ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL
- 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
  21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS
- AND BEND RADII). 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII)
- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 25. ALL BTS GROUND CONNECTIONS.
- 26. ALL GROUND TEST WELLS.
- 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
- 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'. 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
- 30. GPS ANTENNAS 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
- 32. DOGHOUSE/CABLE EXIT FROM ROOF.
- 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
- 34, MASTER BUS BAR.
- 35. TELCO BOARD AND NIU.
- 36. ELECTRICAL DISTRIBUTION WALL
- 38. FNTRANCE TO FQUIPMENT ROOM. 39. COAX WEATHERPROOFING—TOP AND BOTTOM OF TOWER.
- 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
- 41. ANTENNA AND MAST GROUNDING. 42. LANDSCAPING - WHERE APPLICABLE
- 3.6 <u>FINAL PROJECT ACCEPTANCE</u>: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS

## SECTION 07 500 - ROOF CUTTING, PATCHING AND REPAIR

В.

THIS SECTION SPECIFIES CUTTING AND PATCHING EXISTING ROOFING SYSTEMS WHERE CONDUIT OR CABLES EXIT THE BUILDING ONTO THE ROOF OR BUILDING-MOUNTED ANTENNAS. AND AS REQUIRED FOR WATERTIGHT PERFORMANCE, ROOFTOP ENTRY OPENINGS IN MEMBRANE ROOFTOPS SHALL BE CONSTRUCTED TO COMPLY WITH LANDLORD, ANY EXISTING WARRANTY, AND LOCAL JURISDICTIONAL STANDARDS.

## 1.4 SUBMITTALS:

- PRE-CONSTRUCTION ROOF PHOTOS: COMPLETE A ROOF INSPECTION PRIOR TO THE INSTALLATION SPRINT EQUIPMENT ON ANY ROOFTOP BUILD. AT A MINIMUM INSPECT AND PHOTOGRAPH (MINIMUM 3 EA.) ALL AREAS IMPACTED BY THE ADDITION OF THE SPRINT EQUIPMENT.
- PROVIDE SIMILAR PHOTOGRAPHS SHOWING ROOF CONDITIONS AFTER CONSTRUCTION (MINIMUM 3
- C. ROOF INSPECTION PHOTOGRAPHS SHOULD BE UPLOADED WITH CLOSEOUT PHOTOGRAPHS.

## SECTION 09 900 - PAINTING

## QUALITY ASSURANCE:

- A. COMPLY WITH GOVERNING CODES AND REGULATIONS, PROVIDE PRODUCTS OF ACCEPTABLE MANUFACTURERS WHICH HAVE BEEN IN SATISFACTORY USE IN SIMILAR SERVICE FOR THREE YEARS. USE EXPERIENCED INSTALLERS. DELIVER, HANDLE, AND STORE MATERIALS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
  - COMPLY WITH ALL ENVIRONMENTAL REGULATIONS FOR VOLATILE ORGANIC COMPOUNDS.



MAHWAH, NJ 07495 EL: (800) 357-7641

Hudson esian Groupus G NG 20 NORTH, SUITE 3090



CHECKED BY

APPROVED BY

SUBMITTALS DATE DESCRIPTION 2 | 06/26/15 | ISSUED FOR CONSTRUCTION | J 1 06/23/15 ISSUED FOR CONSTRUCTION JA 0 02/10/14 ISSUED FOR REVIEW

SITE NUMBER: CT43XC827 SITE NAME: MANCHESTER/POLICE TOWER

SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

OUTLINE **SPECIFICATIONS** 

SP-2

CONTINUE SHEET SP-3

## CONTINUED FROM SP-2:

## MATERIALS:

MANUFACTURERS: BENJAMIN MOORE, ICI DEVOE COATINGS, PPG, SHERWIN WILLIAMS OR APPROVED EQUAL. PROVIDE PREMIUM GRADE, PROFESSIONAL-QUALITY PRODUCTS FOR COATING SYSTEMS.

### PAINT SCHEDULE:

- A. EXTERIOR ANTENNAE AND ANTENNA MOUNTING HARDWARE: ONE COAT OF PRIMER AND TWO FINISH COATS. PAINT FOR ANTENNAE SHALL BE NON-METALLIC BASED AND CONTAIN NO METALLIC PARTICLES. PROVIDE COLORS AND PATTERNS AS REQUIRED TO MASK APPEARANCE OF ANTENNAE ON ADJACENT BUILDING SURFACES AND AS ACCEPTABLE TO THE OWNER. REFER TO ANTENNA MANUFACTURER'S INSTRUCTIONS WHENEVER POSSIBLE.
- B. ROOF TOP CONSTRUCTION: TOUCH UP PREPARE SURFACES TO BE REPAIRED. FOLLOW INDUSTRY STANDARDS AND REQUIREMENTS OF OWNER TO MATCH EXISTING COATING AND

### PAINTING APPLICATION:

- 1. INSPECT SURFACES, REPORT UNSATISFACTORY CONDITIONS IN WRITING; BEGINNING WORK MEANS ACCEPTANCE OF SUBSTRATE.
- 2. COMPLY WITH MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS FOR PREPARATION, PRIMING AND COATING WORK. COORDINATE WITH WORK OF OTHER SECTIONS.

  MATCH APPROVED MOCK-UPS FOR COLOR, TEXTURE, AND PATTERN, RE-COAT OR REMOVE
- AND REPLACE WORK WHICH DOES NOT MATCH OR SHOWS LOSS OF ADHESION.
- CLEAN UP, TOUCH UP AND PROTECT WORK.

## TOUCHUP PAINTING:

- GALVANIZING DAMAGE AND ALL BOLTS AND NUTS SHALL BE TOUCHED UP AFTER TOWER ERECTION WITH "GALVANOX," "DRY GALV," OR "ZINC—IT."
- 2. FIELD TOUCHUP PAINT SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.
- ALL METAL COMPONENTS SHALL BE HANDLED WITH CARE TO PREVENT DAMAGE TO THE COMPONENTS, THEIR PRESERVATIVE TREATMENT, OR THEIR PROTECTIVE COATINGS.

## SECTION 11 700 - ANTENNA ASSEMBLY, REMOTE RADIO HEADS AND CABLE INSTALLATION

#### SUMMARY:

THIS SECTION SPECIFIES INSTALLATION OF ANTENNAS, RRH'S, AND CABLE EQUIPMENT, INSTALLATION, AND TESTING OF COAXIAL FIBER CABLE.

### ANTENNAS AND RRH'S

THE NUMBER AND TYPE OF ANTENNAS AND RRH'S TO BE INSTALLED IS DETAILED ON THE CONSTRUCTION DRAWINGS.

HYBRID CABLE WILL BE DC/FIBER AND FURNISHED FOR INSTALLATION AT EACH SITE. CABLE SHALL BE INSTALLED PER THE CONSTRUCTION DRAWINGS AND THE APPLICABLE MANUFACTURER'S REQUIREMENTS.

#### JUMPERS AND CONNECTORS

FURNISH AND INSTALL 1/2" COAX JUMPER CABLES BETWEEN THE RRH'S AND ANTENNAS JUMPERS SHALL BE TYPE LDF 4, FLC 12-50, CR 540, OR FXL 540. SUPER-FLEX CABLES ARE NOT ACCEPTABLE. JUMPERS BETWEEN THE RRH'S AND ANTENNAS OR TOWER TOP AMPLIFIERS SHALL CONSIST OF 1/2 INCH FOAM DIELECTRIC, OUTDOOR RATED COAXIAL CABLE. DO NOT USE SUPERFLEX OUTDOORS. JUMPERS SHALL BE FACTORY FABRICATED IN APPROPRIATE LENGTHS WITH A MAXIMUM OF 4 FEET EXCESS PER JUMPER AND HAVE CONNECTORS AT EACH END, MANUFACTURED BY SUPPLIER. IF JUMPERS ARE FIELD FABRICATED, FOLLOW MANUFACTURER'S REQUIREMENTS FOR INSTALLATION OF CONNECTORS

## REMOTE ELECTRICAL TILT (RET) CABLES:

INSTALL SPLITTERS, COMBINERS, FILTERS PER RF DATA SHEET, FURNISHED BY SPRINT.

<u>ANTENNA INSTALLATION:</u>
THE CONTRACTOR SHALL ASSEMBLE ALL ANTENNAS ONSITE IN ACCORDANCE WITH THE INSTRUCTIONS SUPPLIED BY THE MANUFACTURER. ANTENNA HEIGHT, AZIMUTH, AND FEED ORIENTATION INFORMATION SHALL BE A DESIGNATED ON THE CONSTRUCTION DRAWINGS.

- THE CONTRACTOR SHALL POSITION THE ANTENNA ON TOWER PIPE MOUNTS SO THAT THE BOTTOM STRUT IS LEVEL. THE PIPE MOUNTS SHALL BE PLUMB TO WITHIN
- B. ANTENNA MOUNTING REQUIREMENTS: PROVIDE ANTENNA MOUNTING HARDWARE AS INDICATED ON THE DRAWINGS.

## HYBRID CABLES INSTALLATION:

- THE CONTRACTOR SHALL ROUTE, TEST, AND INSTALL ALL CABLES AS INDICATED ON THE CONSTRUCTION DRAWINGS AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- THE INSTALLED RADIUS OF THE CABLES SHALL NOT BE LESS THAN THE MANUFACTURER'S SPECIFICATIONS FOR BENDING RADII.
- C. EXTREME CARE SHALL BE TAKEN TO AVOID DAMAGE TO THE CABLES DURING HANDLING AND INSTALLATION. 1. FASTENING MAIN HYBRID CABLES: ALL CABLES SHALL BE PERMANENTLY FASTENED TO THE COAX
- LADDER AT 4'-0" OC USING NON-MAGNETIC STAINLESS STEEL CLIPS. 2. FASTENING INDIVIDUAL FIBER AND DC CABLES ABOVE BREAKOUT ENCLOSURE (MEDUSA), WITHIN THE
- MMBTS CABINET AND ANY INTERMEDIATE DISTRIBUTION BOXES: a. FIBER: SUPPORT FIBER BUNDLES USING 1/2" VELCRO STRAPS OF THE REQUIRED LENGTH @ 18"
- OC. STRAPS SHALL BE UV, OIL AND WATER RESISTANT AND SUITABLE FOR INDUSTRIAL INSTALLATIONS AS MANUFACTURED BY TEXTOL OR APPROVED EQUAL.

  DC: SUPPORT DC BUNDLES WITH ZIP TIES OF THE ADEQUATE LENGTH. ZIP TIES TO BE UV STABILIZED, BLACK NYLON, WITH TENSILE STRENGTH AT 12,000 PSI AS MANUFACTURED BY
- NELCO PRODUCTS OR EQUAL. 3. FASTENING JUMPERS: SECURE JUMPERS TO THE SIDE ARMS OR HEAD FRAMES USING STAINLESS STEEL TIE WRAPS OR STAINLESS STEEL BUTTERFLY CLIPS.
- 4. CABLE INSTALLATION:
- a. INSPECT CABLE PRIOR TO USE FOR SHIPPING DAMAGE, NOTIFY THE CONSTRUCTION MANAGER.
   b. CABLE ROUTING: CABLE INSTALLATION SHALL BE PLANNED TO ENSURE THAT THE LINES WILL BE PROPERLY ROUTED IN THE CABLE ENVELOP AS INDICATED ON THE DRAWINGS. AVOID TWISTING AND CROSSOVERS.
- c. HOIST CABLE USING PROPER HOISTING GRIPS. DO NOT EXCEED MANUFACTURES RECOMMENDED MAXIMUM BEND RADIUS.

- 5. GROUNDING OF TRANSMISSION LINES: ALL TRANSMISSION LINES SHALL BE GROUNDED AS INDICATED SECTION 26 200 ELECTRICAL MATERIALS AND EQUIPMENT ON DRAWINGS.
- COLOR CODING: ALL COLOR CODING SHALL BE AS REQUIRED IN TS 0200 REV 4. HYBRID CABLE LABELING: INDIVIDUAL HYBRID AND DC BUNDLES SHALL BE LABELED ALPHA-NUMERICALLY ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001,

## WEATHERPROOFING EXTERIOR CONNECTORS AND HYBRID CABLE GROUND

- A. ALL FIBER & COAX CONNECTORS AND GROUND KITS SHALL BE WEATHERPROOFED.
- WEATHERPROOFED USING ONE OF THE FOLLOWING METHODS. ALL INSTALLATIONS MUST BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INDUSTRY BEST PRACTICES
- COLD SHRINK: ENCOMPASS CONNECTOR IN COLD SHRINK TUBING AND PROVIDE A DOUBLE WRAP OF 2" ELECTRICAL TAPE EXTENDING 2" BEYOND TUBING, PROVIDE 3M COLD SHRINK CXS SERIES OR EQUAL.
- SELF-AMALGAMATING TAPE: CLEAN SURFACES. APPLY A DOUBLE WRAP OF SELF-AMALGAMATING TAPE 2" BEYOND CONNECTOR. APPLY A SECOND WRAP OF SELF-AMALGAMATING TAPE IN OPPOSITE DIRECTION. APPLY DOUBLE WRAP OF 2" WIDE ELECTRICAL TAPE EXTENDING 2" BEYOND THE SELF-AMALGAMATING TAPE.

  3M SLIM LOCK CLOSURE 716: SUBSTITUTIONS WILL NOT BE ALLOWED.
- OPEN FLAME ON JOB SITE IS NOT ACCEPTABLE

## SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE STATIONS (MMBTS) AND RELATED EQUIPMENT

## SUMMARY:

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS. BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

### DC CIRCUIT BREAKER LABELING

A. LABEL CIRCUIT BREAKERS ACCORDING TO SPRINT CELL SITE ENGINEERING NOTICE - EN 2012-001, REV 1.

## <u>SECTION 11 800 - INSTALLATION OF MULTIMODAL BASE TRANSCIEVER</u> STATIONS (MMBTS) AND RELATED EQUIPMENT

- A. THIS SECTION SPECIFIES MMBTS CABINETS, POWER CABINETS, AND INTERNAL EQUIPMENT INCLUDING BY NOT LIMITED TO RECTIFIERS, POWER DISTRIBUTION UNITS, BASE BAND UNITS, SURGE ARRESTORS, BATTERIES, AND SIMILAR EQUIPMENT FURNISHED BY THE COMPANY FOR INSTALLATION BY THE CONTRACTOR (OFCI).
- CONTRACTOR SHALL PROVIDE AND INSTALL ALL MISCELLANEOUS MATERIALS AND PROVIDE ALL LABOR REQUIRED FOR INSTALLATION EQUIPMENT IN EXISTING CABINET OR NEW CABINET AS SHOWN ON DRAWINGS AND AS REQUIRE BY THE APPLICABLE INSTALLATION MOPS.
- C. COMPLY WITH MANUFACTURERS INSTALLATION AND START-UP REQUIREMENTS

## SUPPORTING DEVICES:

- A. MANUFACTURED STRUCTURAL SUPPORT MATERIALS: SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY THE FOLLOWING:
  - ALLIED TUBE AND CONDUIT
- B-LINE SYSTEM
- UNISTRUT DIVERSIFIED PRODUCTS THOMAS & BETTS
- B. FASTENERS: TYPES, MATERIALS, AND CONSTRUCTION FEATURES AS FOLLOWS:
  - EXPANSION ANCHORS: CARBON STEEL WEDGE OR SLEEVE TYPE.
- POWER-DRIVEN THREADED STUDS: HEAT-TREATED STEEL, DESIGNED SPECIFICALLY FOR THE INTENDED SERVICE.
- FASTEN BY MEANS OF WOOD SCREWS ON WOOD.
- TOGGLE BOLTS ON HOLLOW MASONRY UNITS.
  CONCRETE INSERTS OR EXPANSION BOLTS ON CONCRETE OR SOLID MASONRY
- MACHINE SCREWS, WELDED THREADED STUDS, OR SPRING-TENSION CLAMPS ON STEEL. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE SHALL NOT BE PERMITTED.
- DO NOT WELD CONDUIT, PIPE STRAPS, OR ITEMS OTHER THAN THREADED STUDS TO STEEL STRUCTURES.
- 9. IN PARTITIONS OF LIGHT STEEL CONSTRUCTION, USE SHEET METAL SCREWS.

## SUPPORTING DEVICES:

- A. INSTALL SUPPORTING DEVICES TO FASTEN ELECTRICAL COMPONENTS SECURELY AND PERMANENTLY IN ACCORDANCE WITH NEC.
- B. COORDINATE WITH THE BUILDING STRUCTURAL SYSTEM AND WITH OTHER TRADES.
- C. UNLESS OTHERWISE INDICATED ON THE DRAWINGS, FASTEN ELECTRICAL ITEMS AND THEIR SUPPORTING HARDWARE SECURELY TO THE STRUCTURE IN ACCORDANCE WITH
- D. ENSURE THAT THE LOAD APPLIED BY ANY FASTENER DOES NOT EXCEED 25 PERCENT OF THE PROOF TEST LOAD.
- E. USE VIBRATION AND SHOCK-RESISTANT FASTENERS FOR ATTACHMENTS TO CONCRETE

## **ELECTRICAL IDENTIFICATION:**

- A. UPDATE AND PROVIDE TYPED CIRCUIT BREAKER SCHEDULES IN THE MOUNTING BRACKET. INSIDE DOORS OF AC PANEL BOARDS WITH ANY CHANGES MADE TO THE AC SYSTEM.
- B. BRANCH CIRCUITS FEEDING AVIATION OBSTRUCTION LIGHTING EQUIPMENT SHALL BE CLEARLY IDENTIFIED AS SUCH AT THE BRANCH CIRCUIT PANELBOARD.

### CONDUIT:

- RIGID GALVANIZED STEEL (RGS) CONDUIT SHALL BE USED FOR EXTERIOR LOCATIONS ABOVE GROUND AND IN UNFINISHED INTERIOR LOCATIONS AND FOR ENCASED RUNS IN CONCRETE. RIGID CONDUIT AND FITTINGS SHALL BE STEEL. COATED WITH ZINC EXTERIOR AND INTERIOR BY THE HOT DIP GALVANIZING PROCESS. CONDUIT SHALL BE PRODUCED TO ANSI SPECIFICATIONS C80.1, FEDERAL SPECIFICATION WW-C-581 AND SHALL BE LISTED WITH THE UNDERWRITERS' LABORATORIES. FITTINGS SHALL BE THREADED - SET SCREW OR COMPRESSION FITTINGS WILL NOT BE ACCEPTABLE. RGS CONDUITS SHALL BE MANUFACTURED BY ALLIED. REPUBLIC OR WHEATLAND.
- B. UNDERGROUND CONDUIT IN CONCRETE SHALL BE POLYVINYLCHLORIDE (PVC) SUITABLE FOR DIRECT BURIAL AS APPLICABLE. JOINTS SHALL BE BELLED, AND FLUSH SOLVENT WELDED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. CONDUIT SHALL BE CARLON ELECTRICAL PRODUCTS OR APPROVED EQUAL
- C. TRANSITIONS BETWEEN PVC AND RIGID (RGS) SHALL BE MADE WITH PVC COATED METALLIC LONG SWEEP RADIUS ELBOWS.
- EMT OR RIGID GALVANIZED STEEL CONDUIT MAY BE USED IN FINISHED SPACES CONCEALED IN WALLS AND CEILINGS. EMT SHALL BE MILD STEEL, ELECTRICALLY WELDED, ELECTRO-GALVANIZED OR HOT-DIPPED GALVANIZED AND PRODUCED TO ANSI SPECIFICATION C80.3, FEDERAL SPECIFICATION WW-C-563, AND SHALL BE UL LISTED. EMT SHALL BE MANUFACTURED BY ALLIED, REPUBLIC OR WHEATLAND, OR APPROVED EQUAL. FITTINGS SHALL BE METALLIC COMPRESSION. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE.
- LIQUID TIGHT FLEXIBLE METALLIC CONDUIT SHALL BE USED FOR FINAL CONNECTION TO EQUIPMENT. FITTINGS SHALL BE METALLIC GLAND TYPE COMPRESSION FITTINGS, MAINTAINING THE INTEGRITY OF CONDUIT SYSTEM. SET SCREW CONNECTIONS SHALL NOT BE ACCEPTABLE. MAXIMUM LENGTH OF FLEXIBLE CONDUIT SHALL NOT EXCEED 6-FEET. LFMC SHALL BE PROTECTED AND SUPPORTED AS REQUIRE BY NEC. MANUFACTURERS OF FLEXIBLE CONDUITS SHALL BE CAROL, ANACONDA METAL HOSE OR UNIVERSAL METAL HOSE, OR APPROVED EQUAL.
- F. MINIMUM SIZE CONDUIT SHALL BE 3/4 INCH (21MM).

## **HUBS AND BOXES:**

- A. AT ENTRANCES TO CABINETS OR OTHER EQUIPMENT NOT HAVING INTEGRAL THREADED HUBS PROVIDE METALLIC THREADED HUBS OF THE SIZE AND CONFIGURATION REQUIRED. HUB SHALL INCLUDE LOCKNUT AND NEOPRENE O-RING SEAL. PROVIDE IMPACT RESISTANT 105 DEGREE C PLASTIC BUSHINGS TO PROTECT CABLE INSULATION.
- B. CABLE TERMINATION FITTINGS FOR CONDUIT
- 1. CABLE TERMINATORS FOR RGS CONDUITS SHALL BE TYPE CRC BY 0-z/GEDNEY OR EQUAL 2. CABLE TERMINATORS FOR LFMC SHALL BE ETCO CL2075; OR MADE FOR THE PURPOSE PRODUCTS BY ROXTEC.
- C. EXTERIOR PULL BOXES AND PULL BOXES IN INTERIOR INDUSTRIAL AREAS SHALL BE PLATED CAST ALLOY, HEAVY DUTY, WEATHERPROOF, DUST PROOF, WITH GASKET, PLATED IRON ALLOY COVER AND STAINLESS STEEL COVER SCREWS, CROUSE-HINDS WAB SERIES
- D. CONDUIT OUTLET BODIES SHALL BE PLATED CAST ALLOY WITH SIMILAR GASKETED COVERS. OUTLET BODIES SHALL BE OF THE CONFIGURATION AND SIZE SUITABLE FOR THE APPLICATION. PROVIDE CROUSE-HINDS FORM 8 OR EQUAL.
- MANUFACTURER FOR BOXES AND COVERS SHALL BE HOFFMAN, SQUARE "D", CROUSE-HINDS, COOPER, ADALET, APPLETON, O-Z GEDNEY, RACO, OR APPROVED

## SUPPLEMENTAL GROUNDING SYSTEM

- FURNISH AND INSTALL A SUPPLEMENTAL GROUNDING SYSTEM AS INDICATED ON THE DRAWINGS. SUPPORT SYSTEM WITH NON-MAGNETIC STAINLESS STEEL CLIPS WITH RUBBER GROMMETS. GROUNDING CONNECTORS SHALL BE TINNED COPPER WIRE, SIZES AS INDICATED ON THE DRAWINGS. PROVIDE STRANDED OR SOLID BARE OR INSULATED CONDUCTORS AS INDICATED.
- SUPPLEMENTAL GROUNDING SYSTEM: ALL CONNECTIONS TO BE MADE WITH CAD WELDS, EXCEPT AT EQUIPMENT USE LUGS OR OTHER AVAILABLE GROUNDING MEANS AS REQUIRED BY MANUFACTURER; AT GROUND BARS USE TWO HOLE SPADES WITH NO OX
- C. STOLEN GROUND—BARS: IN THE EVENT OF STOLEN GROUND BARS, CONTACT SPRINT CM FOR REPLACEMENT INSTRUCTION USING THREADED ROD KITS.

## **EXISTING STRUCTURE:**

A. EXISTING EXPOSED WIRING AND ALL EXPOSED OUTLETS, RECEPTACLES, SWITCHES, DEVICES, BOXES, AND OTHER EQUIPMENT THAT ARE NOT TO BE UTILIZED IN THE COMPLETED PROJECT SHALL BE REMOVED OR DE—ENERGIZED AND CAPPED IN THE WALL, CEILING, OR FLOOR SO THAT THEY ARE CONCEALED AND SAFE. WALL, CEILING, OR FLOOR SHALL BE PATCHED TO MATCH THE ADJACENT CONSTRUCTION.

## CONDUIT AND CONDUCTOR INSTALLATION:

- CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER, PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND
- B. CONDUCTORS SHALL BE PULLED IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE.



MAHWAH, NJ 07495 EL: (800) 357-7641

Hudson esian Groupus G 'NG 20 NORTH, SUITE 3090 DOVER, MA 01845

CHECKED BY

APPROVED BY

SUBMITTALS DATE DESCRIPTION 2 | 06/26/15 | ISSUED FOR CONSTRUCTION | J 1 06/23/15 ISSUED FOR CONSTRUCTION JA 0 | 02/10/14 | ISSUED FOR REVIEW

DPH

SITE NUMBER: CT43XC827 SITE NAME: MANCHESTER/POLICE TOWER

SITE ADDRESS:

239 MIDDLE TURNPIKE

MANCHESTER, CT 06040

OUTLINE **SPECIFICATIONS** 

SP-3

DATED: APRIL 10, 2015 \_ x \_\_\_ x EXISTING FENCED—IN— GRAVEL COMPOUND REMOVE IDEN/NEXTEL VERSAFLEX CUBE CABINET. LUCENT WILL NEED TO ORDER EXPANSION KIT TO WIRE NEW 9929 GROWTH CABINET PROPOSED REMOVE EXISTING SPRINT/NEXTEL EQUIPMENT SHELTER AND EQUIPMENT EXISTING EQUIPMENT ON CONCRETE PAD (BY OTHERS) - EXISTING SPRINT AC PANEL & TELCO BOX **×** 3′−2″± EXISTING SPRINT FIBER DISTRIBUTION BOX EXISTING GENERATOR - EXISTING SPRINT EQUIPMENT (TYP.) EXISTING SPRINT HYBRIFLEX — CABLE (TYP.) PROPOSED INSTALL HYBRIFLEX -CABLE ALONG EXISTING COAX ROUTE (TOTAL OF 1) ALPHA SECTOR (SPRINT 2.5) 10° 1 A-6 BETA SECTOR (SPRINT 2.5) 100° EXISTING ICE BRIDGE -BY OTHERS (TYP.) EXISTING TOWN FIRE/EXC. SHELTER - EXISTING MONOPOLE EXISTING EQUIPMENT ON CONCRETE PAD (BY OTHERS) GAMMA SECTOR (SPRINT 2.5) 270 x — x — x — x — x — - REPLACE EXISTING 6' BLACK CHAIN LINK FENCE WITH AN 8' CHAIN LINK FENCE AND NEW ACCESS GATE 57'-7"± **COMPOUND PLAN** SCALE: 3/8"=1'-0"

STRUCTURAL NOTE: STRUCTURAL INFORMATION TAKEN FROM REVISED STRUCTURAL ANALYSIS PERFORMED BY HUDSON DESIGN GROUP LLC



1 International BLVD, Suite 800 Mahwah, NJ 07495 TEL: (800) 357-7641



600 OSGOOD STREET UILDING 20 NORTH, SUITE 3090 I. ANDOVER, MA 01845 TAX: (978) 336-55



CHECKED BY:

APPROVED BY:

	SI	UBMITTALS	
REV.	DATE	DESCRIPTION	BY
2	06/26/15	ISSUED FOR CONSTRUCTION	JA
		ISSUED FOR CONSTRUCTION	JA
0	02/10/14	ISSUED FOR REVIEW	NB

DPH


SITE NUMBER: CT43XC827 SITE NAME: MANCHESTER/POLICE TOWER


SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

COMPOUND PLAN

A-1

STRUCTURAL NOTE: STRUCTURAL INFORMATION TAKEN FROM REVISED STRUCTURAL ANALYSIS PERFORMED BY HUDSON DESIGN GROUP LLC DATED: APRIL 10, 2015





EXISTING — CLEARWIRE CABINET

RAN EQUIPMENT PHOTO DETAIL

SCALE: N.T.S.

2
A-2



1 INTERNATIONAL BLVD, SUITE 800 MAHWAH, NJ 07495 TEL: (800) 357-7641

Hudson Deelgn Groupuc

1600 OSGOOD STREET BUILDING 20 NORTH, SUITE 3090 TEL: (978) 557-5: N. ANDOVER, MA 01845 FAX: (978) 336-5:

OF CONNECTION

J. CREATOR

J.

CHECKED BY:

APPROVED BY:

	51	DRWILLAR2	
REV.	DATE	DESCRIPTION	BY
2	06/26/15	ISSUED FOR CONSTRUCTION	JA
		ISSUED FOR CONSTRUCTION	JA
0	02/10/14	ISSUED FOR REVIEW	NB

SITE NUMBER:

DPH

CT43XC827

SITE NAME:

MANCHESTER/POLICE

TOWER

SITE ADDRESS:

239 MIDDLE TURNPIKE


MANCHESTER, CT 06040

SHEET TIT

EQUIPMENT PLAN

SHEET NUMB

A-2



SPECIAL CONSTRUCTION NOTE:
SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
COMPLETION OF A CLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY A&E VENDOR).
COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
GO SHALL FUNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE—MENTIONED ANALYSIS AND ASSESSMENT.
SPRINT CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.

STRUCTURAL NOTE: STRUCTURAL INFORMATION TAKEN FROM REVISED STRUCTURAL ANALYSIS PERFORMED BY HUDSON DESIGN GROUP LLC DATED: APRIL 10, 2015



1 INTERNATIONAL BLVD, SUITE 800 MAHWAH, NJ 07495 TEL: (800) 357-7641

Hudson Design Groupuc

1600 OSGOOD STREET BUILDING 20 NORTH, SUITE 3090 N. ANDOVER, MA 01845



CHECKED BY:

APPROVED BY:

SUBMITTALS REV. DATE DESCRIPTION 2 06/26/15 ISSUED FOR CONSTRUCTION JA 1 06/23/15 ISSUED FOR CONSTRUCTION JA 0 02/10/14 ISSUED FOR REVIEW

DPH

SITE NUMBER: CT43XC827 SITE NAME:

MANCHESTER/POLICE TOWEŔ

SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

**ELEVATION** 

A-3

GRAPHIC SCALE 0 5'-4" 10'-8" 21'-4" **EAST ELEVATION** SCALE: 3/32" = 1'-0"


32'-0"

GROUND LEVEL

ELEV. 0'-0"± (AGL)

- SPECIAL CONSTRUCTION NOTE:
  SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
  SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
  \* COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY A&E VENDOR).
  \* COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).
  \* GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE—MENTIONED ANALYSIS AND ASSESSMENT.
  \* SPRINT CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING
  (AS NECESSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP—DRAWING APPROVALS, MATERIALS TEST RESULTS, AND FINAL ENGINEER'S AFFIDAVIT.








**EXISTING PARTIAL ELEVATION PHOTO DETAIL** 

SCALE: N.T.S.



STRUCTURAL INFORMATION TAKEN FROM REVISED STRUCTURAL ANALYSIS PERFORMED BY HUDSON DESIGN GROUP LLC DATED: APRIL 10, 2015

Sprint'

MAHWAH, NJ 07495 TEL: (800) 357-7641



500 OSGOOD STREET JILDING 20 NORTH, SUITE 3090 . ANDOVER, MA 01845

CHECKED BY:

DPH


APPROVED BY:

SUBMITTALS REV. DATE DESCRIPTION 2 06/26/15 ISSUED FOR CONSTRUCTION JA 1 06/23/15 ISSUED FOR CONSTRUCTION JA 0 02/10/14 ISSUED FOR REVIEW


SITE NUMBER: CT43XC827 SITE NAME: MANCHESTER/POLICE

TOWER SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

ANTENNA PLANS



## CABLE COLOR CODING DIAGRAM



ALU 2.5 ALU SCENARIO 1

BBU Capacity Exp

Baseband Unit

TD-LTE SM

TD-LTE SM

××××

XXXX

××××


0000000 0000000 0000000

××××



NOTE:

GENERAL CONTRACTOR SHALL VERIFY
THAT THE LATEST RF DATA SHEET IS
USED FOR EQUIPMENT INSTALLATION.



RFS 2.5 ALU SCENARIO 1
SCALE: N.T.S.







CHECKED BY: BB

APPROVED BY: DPH

	SUBMITTALS			
REV.	DATE	DESCRIPTION	BY	
2		ISSUED FOR CONSTRUCTION	JA	
1	06/23/15	ISSUED FOR CONSTRUCTION	JA	
0	02/10/14	ISSUED FOR REVIEW	NB	

SITE NUMBER:
CT43XC827
SITE NAME:
MANCHESTER/POLICE
TOWER
SITE ADDRESS:


SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

SHEET TIT

RAN WIRING DIAGRAM

SHEET NUM

A - 5



## RFS HYBRIFLEX RISER CABLE SCHEDULE

Fiber Only sting DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
<del>ပ</del> ြင်	MN: HB058-M12-075F	75 ft
e G	MN: HB058-M12-100F	100 ft
분 들	MN: HB058-M12-125F	125 ft
Fibe (Existing	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft

<u>.</u>	Hybrid cable  MN: HB114-08U 3M12-050F  3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC  Connectors, 11/4 cable, 50 ft	50 ft
Po	MN: HB114-08U 3M12-075F	75 ft
9	MN: HB114-08U 3M12-100F	100 ft
AWG	MN: HB114-08U 3M12-125F	125 ft
	: HB114-08U 3M12-150F	150 ft
	MN: HB114-08U 3M12-175F	175 ft
	MN: HB114-08U 3M12-200F	200 ft

		MN: HB114-08U 3M12-200F	200 ft
Power	(*)	Hybrid cable  MN: HB114-13U 3M12-225F  3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC  Connectors, 11/4 cable, 225 ft	225 ft
AWG		MN: HB114-13U 3M12-250F	250 ft
6 A		MN: HB114-13U 3M12-275F	275 ft
		MN: HB114-13U 3M12-300F	300 ft

Powe	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
AWG	MN: HB114-21U 3M12-350F	350 ft
0.00	MN: HB114-21U 3M12-375F	375 ft

## RES HYBRIFLEX JUMPER CABLE SCHEDULE

	Hybrid Jumper cable	
	MN: HBF012-M3-5F1	5 ft
on ly	5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	
	MN: HBF012-M3-10F1	10 ft
- Pe	MN: HBF012-M3-15F1 MN: HBF012-M3-20F1	15 ft
Œ		20 ft
	MN: HBF012-M3-25F1	25 ft
	M N: HBF012-M3-30F1	30 ft
	·	•


ower	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
9	MN: HBF058-08U1M3-10F1	10 ft
M (*)	M N: HBF058-08U1M3-15F1	15 ft
60	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft

Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
U	MN: HBF058-13U1M3-10F1	10 ft
AW	MN: HBF058-13U1M3-15F1	15 ft
9	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft


. er	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors,	5 ft
G Power	7/8 cable MN: HBF078-21U1M3-10F1	10 ft
AW G	MN: HBF078-21U1M3-15F1	15 ft
4	M N: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft


\* NOTE: SPRINT CM TO CONFIRM HYBRID RISER CABLE AND HYBRID JUMPER CABLE MODEL NUMBERS BEFORE PREPARING BOM.

2.5 HYBRID CABLE X-SECTION AND DATA




## 4 AWG







NOTE:

## FIBER ONLY



PLAN VIEW





PLAN VIEW


2.5 RRH'S (2) SCALE: N.T.S. A-6

12.6"

2.5 ANTENNA SPECIFICATIONS

6.3"


SCALE: N.T.S.



## PROPOSED MMBTS OUTDOOR CABINET WITH LTE 2.5 BBU EQUIPMENT

FRONT VIEW

SCALE: N.T.S.




MANUFACTURER	ALU	
MODEL	9929	
HEIGHT	63.65"	
WIDTH	31.5"	
DEPTH	35.5"	
TOTAL WEIGHT (FULLY LOADED)	1600 lbs	

EQUIPMENT SHALL BE ANCHORED PER MANUFACTURERS SPECIFICATIONS.



A-6



**EQUIPMENT** DETAILS

2 06/26/15 ISSUED FOR CONSTRUCTION JA 1 06/23/15 ISSUED FOR CONSTRUCTION JA 0 02/10/14 ISSUED FOR REVIEW

SITE NUMBER:

CT43XC827

SITE NAME: MANCHESTER/POLICE TOWER SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

Sprint'

INTERNATIONAL BLVD, SUITE 800

Hudson


Design Groupuc

500 OSGOOD STREET JILDING 20 NORTH, SUITE 3090 . ANDOVER, MA 01845

G

MAHWAH, NJ 07495 TEL: (800) 357-7641

A - 6



SPECIAL INSPECTION CHECKLIST					
BEFORE C	BEFORE CONSTRUCTION				
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY ENGINEER OF RECORD)	REPORT ITEM				
REQUIRED	ENGINEER OF RECORD APPROVED SHOP DRAWINGS <sup>1</sup>				
REQUIRED	MATERIAL SPECIFICATIONS REPORT <sup>2</sup>				
N/A	FABRICATOR NDE INSPECTION				
N/A	NDE REPORT OF MONOPOLE BASE PLATE (AS REQUIRED)				
REQUIRED	PACKING SLIPS <sup>3</sup>				
ADDITIONAL TESTING AND INSPECTIONS:					
DURING CONSTRUCTION					
CONSTRUCTION/INSTALLATION INSPECTIONS AND TESTING REQUIRED (COMPLETED BY ENGINEER OF RECORD)	REPORT ITEM				
REQUIRED	STEEL INSPECTIONS				
N/A	HIGH STRENGTH BOLT INSPECTIONS				
N/A	HIGH WIND ZONE INSPECTIONS				
N/A	FOUNDATION INSPECTIONS				
N/A	CONCRETE COMP. STRENGTH, SLUMP TESTS AND PLACEMENT				
N/A	POST INSTALLED ANCHOR ROD VERIFICATION				
N/A	BASE PLATE GROUT VERIFICATION				
REQUIRED	CERTIFIED WELD INSPECTION				
N/A	EARTHWORK: LIFT AND DENSITY				
N/A	ON SITE COLD GALVANIZING VERIFICATION				
N/A	GUY WIRE TENSION REPORT				

## NOTES:

N/A

REQUIRED

CONSTRUCTION/INSTALLATIO

INSPECTIONS AND TESTING REQUIRED

ENGINEER OF RECORD)

REQUIRED

N/A
REQUIRED

ADDITIONAL TESTING AND INSPECTIONS:

ADDITIONAL TESTING AND INSPECTIONS:

1. REQUIRED FOR ANY <u>NEW</u> SHOP FABRICATED FRP OR STEEL.

**AFTER CONSTRUCTION** 

STEEL & FRP INSPECTION

FINAL INSPECTION

MODIFICATION INSPECTOR REDLINE OR RECORD DRAWINGS<sup>5</sup>

POST INSTALLED ANCHOR ROD PULL-OUT TESTING

PHOTOGRAPHS

- 2. PROVIDED BY MANUFACTURER, REQUIRED IF HIGH STRENGTH BOLLTS OR STEEL.
- PROVIDED BY GENERAL CONTRACTOR; PROOF OF MATERIALS.
- HIGH WIND ZONE INSPECTION CATB 120MPH OR CAT C,D 110MPH INSPECT FRAMING OF WALLS, ANCHORING, FASTENING SCHEDULE.
- 5. AS REQUIRED; FOR ANY FIELD CHANGES TO THE ITEMS IN THIS TABLE.

#### GENERAL NOTES

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES AND ORDINANCES. IT IS THE CONTRACTORS RESPONSIBILITY TO OBTAIN ALL PERMITS NECESSARY TO COMPLETE THE PROJECT AND ABIDE BY ALL CONDITIONS AND REQUIREMENTS OF THE PERMITS.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFICATION OF ALL DIMENSIONS, ELEVATIONS, AND EXISTING CONDITIONS AT THE SITE BEFORE ORDERING ANY MATERIALS OR DOING ANY WORK. NO EXTRA CHARGE OR COMPENSATION SHALL BE ALLOWED DUE TO DIFFERENCE BETWEN ACTUAL DIMENSIONS AND DIMENSIONS INDICATED ON THE CONSTRUCTION DRAWINGS. ANY SUCH DISCREPANCY IN DIMENSION WHICH MAY BE FOUND SHALL BE SUBMITTED TO HUDSON DESIGN GROUP FOR CONSIDERATION BEFORE THE CONTRACTOR PROCEEDS WITH THE WORK IN THE AFFECTED AREA.
- INCORRECTLY FABRICATED, DAMAGED, OTHERWISE MISFITTING, OR NON-CONFORMING MATERIALS AND CONDITIONS SHALL BE REPORTED TO HUDSON DESIGN GROUP PRIOR TO ANY REMEDIAL OR CORRECTIVE ACTION. ALL ACTIONS SHALL REQUIRE HUDSON DESIGN GROUP, LLC APPROVAL.
- . IT IS THE CONTRACTORS SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURE AND SEQUENCE TO INSURE THE SAFETY OF THE STRUCTURE AND ITS COMPONENT PARTS DURING ERECTION AND/OR FIELD MODIFICATIONS. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF TEMPORARY BRACING, GUYS OR TIE DOWNS THAT MAY BE NECESSARY. SUCH MATERIAL SHALL BE REMOVED AFTER COMPLETION OF THE PROJECT.
- 5. CONTRACTOR SHALL PROMPTLY REMOVE ANY AND ALL DEBRIS FROM SITE AND RESTORE AS BEST AS POSSIBLE TO PRE-CONSTRUCTION CONDITION.

#### STEEL:

- ALL STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH THE LATEST AISC CODE AND ASTM SPECIFICATIONS.
- 2. ALL CONNECTIONS OF STRUCTURAL STEEL MEMBERS SHALL BE MADE USING SPECIFIED WELDS WITH WELDING ELECTRODES E-70XX OR SPECIFIED HIGH STRENGTH BOLTS TO BE ASTM A325N, THREAD INCLUDED WITH SHEAR PLANE UNLESS OTHERWISE NOTED.
- ALL BOLTED CONNECTIONS TO BE INSTALLED TO A SNUG-TIGHTENED CONDITION IN ACCORDANCE WITH AISC 13 PART 16.2, "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS", SECTION 8.1, UNIESS OTHERWISE NOTED.
- 4. ALL STEEL (EXCEPT A490 BOLTS), AFTER FABRICATION, SHALL BE HOT DIPPED GALVANIZED PER ASTM A-123. ALL DAMAGED SURFACES, WELDED AREAS AND AUTHORIZED NON-GALVANIZED MEMBERS OR PARTS (EXISTING OR NEW) SHALL BE PAINTED WITH 2 COATS OF ZRC COLD GALVANIZING COMPOUND.
- 5. ALL SHOP AND FIELD WELDING SHALL BE DONE BY WELDERS QUALIFIED AS DESCRIBED IN THE "AMERICAN WELDING SOCIETY'S STANDARD QUALIFICATION PROCEDURE" TO PERFORM THE TYPE OF WORK REQUIRED.
- STRUCTURAL STEEL MAY NOT BE TORCH CUT FOR FABRICATION. ALL STEEL FABRICATION MUST FOLLOW AISC STANDARDS.
- 7. NEW STEEL MEMBERS AND CONNECTIONS SHALL BE PAINTED TO MATCH EXISTING TOWER.

#### MISC. NOTES:

- . ALL MODIFICATIONS ARE ASSUMED TO BE MADE ON AN EMPTY TOWER. CONTRACTOR IS RESPONSIBLE TO MAKE PROVISIONS TO SUPPORT OR WORK AROUND EXISTING ANTENNAS AND TRANSMISSION LINES. MODIFICATIONS MUST BE CONTINUOUS THROUGH ALL A
- 2. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION.

#### FABRICATION NOTES:

- ALL DIMENSIONS ARE PRELIMINARY UNTIL FIELD VERIFIED BY CONTRACTOR. ANY CHANGES MUST BE APPROVED BY ENGINEER OF RECORD IN WRITING PRIOR TO FABRICATION AND INSTALLATION.
- NEW STEEL MEMBERS MUST HAVE SINGLE DRILLED HOLES. SLOTTED AND DOUBLE DRILLED HOLES ARE NOT ACCEPTABLE MEANS OF FABRICATION.

## CONTRACTOR QUALIFICATION NOTES:

- ALL REPAIRS SHALL BE PERFORMED BY A TOWER CONTRACTOR WITH A MINIMUM OF 5 YEARS EXPERIENCE IN TOWER ERECTION AND RETROFIT AND WITH WORKING KNOWLEDGE OF THE ANSI/TIA-222-G "STRUCTURAL STANDARD FOR ANTENNA SUPPORTING STRUCTURES AND ANTENNAS".
- CONTRACTOR IS RESPONSIBLE FOR ALL CONSTRUCTION MEANS AND METHODS. SHOULD THE CONTRACTOR REQUIRE DIRECT CONSULTATION, HUDSON DESIGN GROUP, LLC IS WILLING TO OFFER SERVICES BASED UPON AN AGREED FEE FOR THE WORK REQUIRED.
- 3. ALL SUBMITTAL INFORMATION MUST BE SENT TO HUDSON DESIGN GROUP, LLC 1600 OSGOOD ST. BUILDING 20N, SUITE 3090, NORTH ANDOVER, MA 01845 TEL: (978)557-5553, FAX: (978)336-5586. ANY VARIATION OF THESE SPECIFICATIONS OR DRAWINGS WITHOUT CONSENT FROM HUDSON DESIGN GROUP WILL VOID ANY RESPONSIBILITY OR LIABILITY FOR DAMAGE (MATERIAL OR PHYSICAL) TOWARDS HUDSON DESIGN

## JOB SITE SAFETY AND NOTES:

NEITHER THE PROFESSIONAL ACTIVITIES OF HUDSON DESIGN GROUP, LLC NOR THE PRESENCE OF HUDSON DESIGN GROUP, LLC OR EMPLOYEES AND SUB-CONSULTANTS AT THE CONSTRUCTION SITE, SHALL RELIEVE THE GENERAL CONTRACTOR AND/OR SUBCONTRACTORS AND ANY OTHER ENTITY OF THEIR OBLIGATIONS, DUTIES AND RESPONSIBILITES INCLUDING, BUT NOT LIMITED TO, CONSTRUCTION MEANS, METHODS, SEQUENCE, TECHNIQUES, OR PROCEDURES NECESSARY FOR PERFORMING, SUPERINTENDING OR COORDINATING ALL PORTIONS OF THE WORK OF CONSTRUCTION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND ANY HEALTH OR SAFETY PRECAUTIONS REQUIRED BY ANY REGULATORY AGENCIES. THE GENERAL CONTRACTOR AND/OR SUBCONTRACTOR IS SOLELY RESPONSIBLE FOR JOB SAFETY, AND WARRANTS THAT THIS INTENT IS EVIDENT BY ACCEPTING THIS WORK.

## SUBSTITUTES AND/OR EQUALS:

IF CONTRACTOR WISHES TO FURNISH OR USE A SUBSTITUTE ITEM OF MATERIAL OR EQUIPMENT, CONTRACTOR SHALL MAKE WRITTEN APPLICATION TO ENGINEER FOR ACCEPTANCE THEREOF, CERTIFYING THAT THE PROPOSED SUBSTITUTE WILL ADEQUATELY PERFORM THE FUNCTIONS AND ACHIEVE THE RESULTS CALLED FOR BY THE GENERAL DESIGN, BE SIMILAR IN SUBSTANCE TO THAT SPECIFIED, AND SUITED TO THE SAME USE AS THAT SPECIFIED, ALL VARIATIONS OF THE PROPOSED SUBSTITUTE FROM THAT SPECIFIED WILL BE IDENTIFIED IN THE APPLICATION AND AVAILABLE MAINTENANCE, REPAIR, AND REPLACEMENT SERVICE WILL BE INDICATED. THE APPLICATION WILL ALSO CONTAIN AN ITEMIZED ESTIMATE OF ALL COSTS OR CREDITS THAT WILL RESULT DIRECTLY OR INDIRECTLY FROM ACCEPTANCE OF SUCH SUBSTITUTE INCLUDING COSTS OF RESIGN AND CLAIMS OF OTHER CONTRACTORS AFFECTED BY THE RESULTING CHANCE, ALL OF WHICH WILL BE CONSIDERED BY ENGINEER IN EVALUATION OF THE PROPOSED SUBSTITUTE. ENGINEER MAY REQUIRE CONTRACTOR TO FURNISH ADDITIONAL DATA ABOUT THE PROPOSED SUBSTITUTE.

## NOTE:

REFER TO STRUCTURAL ANALYSIS BY: HUDSON DESIGN GROUP LLC DATED: APRIL 10, 2015 FOR THE CAPACITY OF THE EXISTING STRUCTURES TO SUPPORT THE PROPOSED EQUIPMENT.



1 INTERNATIONAL BLVD, SUITE 800 MAHWAH, NJ 07495 TEL: (800) 357-7641



600 OSGOOD STREET SUILDING 20 NORTH, SUITE 3090 J. ANDOVER, MA 01845

OF CONNECTOR AS A SECONDARY OF CONNECTOR AS A SECONDARY OF SECONDARY O

CHECKED BY:

APPROVED BY:

SUBMITTALS

REV. DATE DESCRIPTION BY

2 06/26/15 ISSUED FOR CONSTRUCTION JA
1 06/23/15 ISSUED FOR CONSTRUCTION JA
0 02/10/14 ISSUED FOR REVIEW NB

DPH

SITE NUMBER: CT43XC827

SITE NAME: MANCHESTER/POLICE TOWER


> SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040


> > SHEET TITL

MODIFICATION ELEVATION & NOTES

CHEET NI IM

S-1







Hudson Design Groupus

1600 OSGOOD STREET BUILDING 20 NORTH, SUITE 3090 N. ANDOVER, MA 01845

OF CONNECTOR AND A SERVICE OF CONNECTOR ASSETTION ASSETTION ASSETTION ASSETTION ASSETTION ASSETTION AS

CHECKED BY:

APPROVED BY:

DPH

CT43XC827

SITE NAME:

MANCHESTER/POLICE

TOWER

SITE ADDRESS:

SITE NUMBER:


SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040


SHEET TITLE

MODIFICATION ELEVATION & NOTES

SHEET NUME

S - 2





**SECTION A-A** 

INSTALL (1) HYBRID CABLE INSIDE MONOPOLE

SOURCE: HDG 02-12-14

ONE SECTOR SHOWN FOR CLARITY

INSTALL 2.5GHz ANTENNA MOUNTED TO EXISTING PIPE MAST

INSTALL 2.5GHz RRH MOUNTED TO PROPOSED RING MOUNT

2.5 ANTENNA AND RRH PHOTO DETAIL

S-4 /

INSTALL DOWNTILT BRACKET (TYP.) - INSTALL 2.5GHz ANTENNA A-4 PIPE SIZE) (SEE NOTE 3) (A) EXISTING SAFETY CLIMB ——
(SEE INSTALLATION NOTE 1) INSTALL 2.5GHz RRH MOUNTED TO PROPOSED MOUNTING PIPE. (MOUNT PER MANUFACTURERS SPECIFICATIONS) - EACH SECTOR: FURNISH AND INSTALL (8)

1/2" COAX CABLE JUMPERS, (1) 1/2"

CALIBRATION CABLE, AND (1) 1/2" RET

CABLE, TIE-WRAPS, CABLE BLOCKS/HANGERS,
CUSHIONS AND OTHER SUITABLE MEANS TO
SECURELY ATTACH AND FASTEN CABLES TO
TOWER STRUCTURE, ANTENNA SUPPORT
PLATFORM AND ANTENNA PIPE MAST. FURNISH AND INSTALL SITE PRO 1 UNIVERSAL RING MOUNT PART # LWRM OR APPROVED EQUAL (SEE INSTALLATION NOTE 1) FURNISH AND INSTALL 2-1/2" -STD (2.88 O.D.) PIPE MAST (3'-0" LONG) (TYP. OF 3) EACH SECTOR: INSTALL (1) HYBRID —
JUMPER CABLE FURNISH AND INSTALL
CABLE BLOCKS/HANGERS, CUSHIONS
AND OTHER SUITABLE MEANS TO
SECURELY ATTACH AND FASTEN
CABLE FOR HAD HAD FASTEN -EXISTING COAX PORT (BEYOND) (TYP.) A-4 EXISTING MONOPOLE

> NOTE: ONE SECTOR SHOWN FOR CLARITY 2.5 ANTENNA AND RRH MOUNTING DETAIL

SPECIAL CONSTRUCTION NOTE:
SPRINT TOWER TOP WORK IS CONTINGENT ON THE FOLLOWING:
COMPLETION OF A GLOBAL STRUCTURAL STABILITY ANALYSIS (PROVIDED BY A&E VENDOR).
COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL

COMPLETION OF AN ANTENNA/RRH MOUNT STRUCTURAL ASSESSMENT (PROVIDED BY A&E VENDOR).

GC SHALL FURNISH, INSTALL AND COMPLETE ALL REQUIRED STRUCTURAL MODIFICATIONS AS INDICATED IN BEFORE-MENTIONED ANALYSIS AND ASSESSMENT.

SPRINT CORPORATION SHALL PROVIDE WRITTEN ACCEPTANCE/APPROVAL FOR THE COMPLETION OF ALL TOWER/FOUNDATION STRUCTURAL MODIFICATIONS INCLUDING (AS NECSSARY) CONTROLLED CONSTRUCTION INSPECTIONS, SHOP-DRAWING APPROVALS, MATERIALS TEST RESULTS, AND EINAL ENVINEEPS'S ACTIONALY. FINAL ENGINEER'S AFFIDAVIT.

INSTALLATION NOTES:

1. EXPOSED ANTENNA AND RRH FOR ALL SECTORS TO BE PAINTED TO MATCH EXISTING CONDITIONS.

- 2. VERIFY EXACT RRH AND ANTENNA MODEL & AZIMUTHS WITH RF ENGINEER PRIOR TO INSTALLATION.
- 3. ROTATE EXISTING ANTENNA FRAME AS NEEDED TO ACCOMMODATE INSTALL ANTENNAS.
- 4. RRH PLACEMENT FOR REFERENCE ONLY. CONTRACTOR SHALL PLACE RRH IN CORRECT ORDER MATCHING INSTALL ANTENNA PLACEMENT AND ENSURE THAT THERE IS ENOUGH CLEARANCE FOR RRHS TO BE PLACED ON THE INSIDE ON THE ANTENNA FRAME.
- 5. INSTALL EQUIPMENT TO BE MOUNTED PER MANUFACTURERS SPECIFICATIONS.

Hudson Design Groupus G

Sprint'

I INTERNATIONAL BLVD, SUITE 800 MAHWAH, NJ 07495 TEL: (800) 357-7641

600 OSGOOD STREET UILDING 20 NORTH, SUITE 3090 I. ANDOVER, MA 01845

CHECKED BY:

DPH

APPROVED BY:

ı	П	SUBMITTALS			
		REV.	DATE	DESCRIPTION	BY
ı					
ı					
ı					
		2		ISSUED FOR CONSTRUCTION	JA
ı		1		ISSUED FOR CONSTRUCTION	JA
ı		0	02/10/14	ISSUED FOR REVIEW	NB

SITE NUMBER: CT43XC827 SITE NAME:

MANCHESTER/POLICE TOWER

SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

STRUCTURAL DETAILS

STRUCTURAL NOTE: STRUCTURAL INFORMATION TAKEN FROM REVISED STRUCTURAL ANALYSIS PERFORMED BY HUDSON DESIGN GROUP LLC DATED: APRIL 10, 2015


## SPECIAL WORK NOTE:

- (1).G.C. TO FURNISH AND INSTALL ALL COMPONENTS TO UPGRADE EXISTING ELECTRICAL SERVICE, CONDUIT, CONDUCTOR, PPC AND MCB IN ACCORDANCE WITH SPRINT CONSTRUCTION STANDARDS NV 2.5 ADDENDUM "ENGINEERING NOTICE 2013—002 (POWER UPGRADES) REV.0" (OR CURRENT VERSION)
- (POWER UPGRADES) REV.0" (OR CURRENT VERSION)

  2. G.C. TO FURNISH AND INSTALL UPGRADE THE EXISTING MMBTS BREAKER, CONDUCTOR, AND CONDUIT TO A MINIMUM NEC RATING FOR A 100-AMP, 240V CIRCUIT.
- 3. FOR NEW OR REPAIRED GROUNDING EQUIPMENT, REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):


  -ANTI-THEFT UPDATE TO SPRINT GROUNDING DATED 08-24-712 (OR CURRENT VERSION)

  -SPRINT ENGINEERING LETTER EL-0504 DATED 04-20-12 (OR CURRENT VERSION)



TYPICAL POWER AND GROUNDING ONE LINE DIAGRAMS
SCALE: N.T.S.





EXISTING PPC BREAKER PANEL SCALE: N.T.S.

E-1

## ELECTRICAL NOTES

- ALL ELECTRICAL WORK SHALL CONFORM TO THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE (NEC) AS WELL AS APPLICABLE STATE AND LOCAL CODES.
- 2) THE ELECTRICAL CONTRACTOR SHALL COORDINATE ALL CONDUIT ROUTING WITH LOCAL UTILITY COMPANIES AND SPRINT CONSTRUCTION MANAGER
- 3) ALL CONDUITS ROUTED BELOW GRADE SHALL TRANSITION TO RIGID GALVANIZED ELBOWS WITH RIGID GALVANIZED STEEL CONDUIT ABOVE GRADE.
- 4) ALL METAL CONDUITS SHALL BE PROVIDED WITH GROUNDING BUSHINGS.
- 5) GENERAL CONTRACTOR SHALL PROVIDE ALL DIRECT BURIED CONDUITS WITH PLASTIC WARNING TAPE IDENTIFYING CONTENTS. TAPE COLORS SHALL BE ORANGE FOR TELEPHONE AND RED FOR ELECTRIC.
- 6) ALL ELECTRICAL ITEMS SHALL BE U.L. APPROVED OR LISTED AND PROCURED PER SPECIFICATION REQUIREMENTS.
- 7) THE ELECTRICAL WORK INCLUDES ALL LABOR AND MATERIALS DESCRIBED BY DRAWINGS AND SPECIFICATIONS INCLUDING INCIDENTAL WORK TO PROVIDE COMPLETE OPERATING AND APPROVED ELECTRICAL SYSTEM
- 8) GENERAL CONTRACTOR SHALL PAY FEES FOR PERMITS, AND IS RESPONSIBLE FOR OBTAINING SAID PERMITS AND COORDINATION OF INSPECTIONS
- 9) ELECTRICAL AND TELCO WIRING OUTSIDE A BUILDING AND EXPOSED TO WEATHER SHALL BE IN WATER TIGHT GALVANIZED RIGID STEEL CONDUITS OR SCHEDULE 80 PVC (AS PERMITTED BY CODE) AND WHERE REQUIRED IN LIQUID TIGHT FLEXIBLE METAL OR NONMETALLIC CONDUITS.
- 10) BURIED CONDUIT SHALL BE SCHEDULE 40 PVC.
- 11) ELECTRICAL WIRING SHALL BE COPPER WITH TYPE XHHW, THWN, OR THIN INSULATION.
- 12) RUN ELECTRICAL CONDUIT OR CABLE BETWEEN ELECTRICAL UTILITY DEMARCATION POINT AND PROJECT OWNER CELL SITE PPC AS INDICATED ON THIS DRAWING, PROVIDE FULL LENGTH PULL ROPE. COORDINATE INSTALLATION WITH UTILITY COMPANY.
- 13) RUN TELCO CONDUIT OR CABLE BETWEEN TELEPHONE UTILITY
  DEMARCATION POINT AND PROJECT OWNER CELL SITE TELCO CABINET AND
  BTS CABINET AS INDICATED ON THIS DRAWING PROVIDE FULL LENGTH
  PULL ROPE IN INSTALLED TELCO CONDUIT. PROVIDE GREENLEE CONDUIT
  MEASURING TAPE AT EACH END.
- 14) FIBER OPTIC CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 770-OPTICAL FIBER CABLES AND RACEWAYS.
- 15) COMMUNICATIONS CIRCUITS SHALL BE IN ACCORDANCE WITH NEC ARTICLE 800-COMMUNICATIONS SYSTEMS.



1 INTERNATIONAL BLVD, SUITE 800 MAHWAH, NJ 07495 TEL: (800) 357-7641

Hudson Design Geoupus

600 OSGOOD STREET UILDING 20 NORTH, SUITE 3090 I. ANDOVER, MA 01845

OF CONNECTION

OF CON

CHECKED BY:

APPROVED BY:

DPH

SITE NUMBER: CT43XC827

SITE NAME: MANCHESTER/POLICE TOWER


SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

SHEET TITLE

ONE LINE DIAGRAM

CHEET MINNER

E-1



BUTT CONDUCTOR INSULATION UP AGAINST
THE CONNECTOR BARREL

INSPECTION WINDOW REQUIRED FOR
ALL INTERIOR TWO—HOLE CONNECTORS

EXTERNAL TOOTHED

3/8"øx1 1/2"

\$/\$ NUT

\$/\$ LOCK WASHER

APPROVED EQUAL

APPROVED EQUAL

1/4" MIN

S/\$ BOLT (1 OF 2)

TINNED COPPER GROUNDING BAR

PROTECTIVE GROUNDING SYSTEMS GENERAL NOTES:

- 1. GROUNDING SHALL BE IN ACCORDANCE WITH NEC ARTICLE 250-GROUNDING AND BONDING.
- GROUNDING SHALL BE IN ACCORDANCE WITH SPRINT SSEO DOCUMENTS 3.018.02.004
  "BONDING, GROUNDING AND TRANSIENT PROTECTION FOR CELL SITES" AND 3.018.10.002
  "SITE RESISTANCE TO EARTH TESTING".
- PROVIDE GROUND CONNECTIONS FOR ALL METALLIC STRUCTURES, ENCLOSURES, RACEWAYS AND OTHER CONDUCTIVE ITEMS ASSOCIATED WITH THE INSTALLATION OF CARRIER'S EQUIPMENT.
- 4. GROUND CONNECTIONS: CLEAN SURFACES THOROUGHLY BEFORE APPLYING GROUND LUGS OR CLAMPS. IF SURFACE IS COATED, REMOVE THE COATING, APPLY A NON-CORROSNE APPROVED COMPOUND TO CLEAN SURFACE AND INSTALL LUGS OR CLAMPS. WHERE GALVANIZIO IS REMOVED FROM METAL, IT SHALL BE PAINTED OR TOUCHED UP WITH "GALVAMOX" OR EQUAL.
- ALL GROUNDING WIRES SHALL PROVIDE A STRAIGHT, DOWNWARD PATH TO GROUND WITH GRADUAL BENDS AS REQUIRED. GROUND WIRES SHALL NOT BE LOOPED OR SHARPLY BENT.
- 6. ALL CLAMPS AND SUPPORTS USED TO SUPPORT THE GROUNDING SYSTEM CONDUCTORS AND PVC CONDUITS SHALL BE PVC TYPE (NON CONDUCTIVE). DO NOT USE METAL BRACKETS OR SUPPORTS WHICH WOULD FORM A COMPLETE RING AROUND ANY GROUNDING CONDUCTOR.
- 7. ALL GROUND WIRES SHALL BE #2 SOLID TINNED BCW UNLESS NOTED OTHERWISE.
- 8. PROVIDE DEDICATED #2 AWG COPPER GROUND WIRE FROM EACH ANTENNA MOUNTING PIPE TO ASSOCIATED CIGBE.
- 9. GROUND ANTENNA BASES, FRAMES, CABLE RACKS, AND OTHER METALLIC COMPONENTS WITH #2 INSULATED TINNED STRANDED COPPER GROUNDING CONDUCTORS AND CONNECT TO INSULATED SURFACE MOUNTED GROUND BARS. CONNECTION DETAILS SHALL FOLLOW MANUFACTURER'S SPECIFICATIONS FOR GROUNDING.
- 10. EACH EQUIPMENT CABINET SHALL BE CONNECTED TO THE MASTER ISOLATION GROUND BAR (MGB) WITH #2 SOLID TINNED BCW EQUIPMENT CABINETS WALL HAVE (2) CONNECTIONS.
- 11. GROUND HYBRIFLEX SHIELD AT TOP, BOTTOM AND AT TRANSITION TO HYBRIFLEX JUMPER CABLES AT EQUIPMENT CABINET ENTRANCE USING MANUFACTURER'S GUIDELINES. WHEN HYBRIFLEX CABLE EXCEEDS 200', GROUND AT INTERVALS NOT EXCEEDING 100'.
- 12. THE CONTRACTOR SHALL VERIFY THAT THE EXISTING GROUND BARS HAVE ENOUGH SPACE/HOLES FOR ADDITIONAL TWO HOLE LUGS.
- 13. EXOTHERMIC WELDING IS RECOMMENDED FOR GROUNDING CONNECTION WHERE PRACTICAL OTHERWISE. THE CONNECTION SHALL BE MADE USING COMPRESSION TYPE-2 HOLES, LONG BARREL LUGS OR DOUBLE CRIMP "C" CLAMP. THE COPPER CABLES SHALL BE COATED WITH AN ANTI-OXIDANT (THOMAS BETTS KOPR-SHILD) BEFORE MAKING THE CRIMP CONNECTIONS THE CONTRACTOR SHALL FOLLOW MANUFACTURER'S RECOMMENDED TORQUES ON THE BOLT ASSEMBLY TO SECURE CONNECTIONS.
- 14. AT ALL TERMINATIONS AT EQUIPMENT ENCLOSURES, PANEL, AND FRAMES OF EQUIPMENT AND WHERE EXPOSED FOR GROUNDING. CONDUCTOR TERMINATION SHALL BE PERFORMED UTILIZING TWO HOLE BOLTED TONGUE COMPRESSION TYPE LUGS WITH STAINLESS STEEL SELF—TAPPING SCREWS.
- 15. THE MASTER GROUND BAR (MGB) SHALL BE MADE OF BARE 1/4"x2" COPPER (FOR OUTDOOR APPLICATIONS IT SHALL BE TINNED COPPER) AND LARGE ENOUGH TO ACCOMMODATE THE REQUIRED NUMBER OF GROUND CONNECTIONS. THE HARDWARE SECURING THE MGB SHALL ELECTRICAL INSULATE THE MGB FROM ANY STRUCTURE TO WHICH IT IS FASTENCE.
- ALL BOLTS, WASHERS, AND NUTS USED ON GROUNDING CONNECTIONS SHALL BE STAINLESS STEEL.
- 17. ALL GROUNDING CONNECTIONS SHALL BE COATED WITH A COPPER SHIELD ANTI-CORROSIVE AGENT SUCH AS T&B KOPR SHIELD. VERIFY PRODUCT WITH SPRINT CONSTRUCTION MANAGER.
- FOR NEW OR REPAIRED GROUNDING EQUIPMENT. REFER TO SPRINT GROUNDING STANDARDS AND FOLLOWING (SUPPLEMENTS):
   —ANTI—THEFT UPDATE TO SPRINT GROUNDING DATED: 08-24-12 (OR CURRENT VERSION)
   —SPRINT ENGINEERING LETTER EL-0504 DATED: 04-20-12 (OR CURRENT VERSION)



1 INTERNATIONAL BLVD, SUITE 800 MAHWAH, NJ 07495 TEL: (800) 357-7641

Hudson Design Groupus G

600 OSGOOD STREET UILDING 20 NORTH, SUITE 3090 . ANDOVER, MA 01845

OF CONNEC J. CRESCO J. CRE

CHECKED BY:

APPROVED BY:

	SUBMITTALS				
REV.	DATE	DESCRIPTION	BY		
2		ISSUED FOR CONSTRUCTION	JA		
1		ISSUED FOR CONSTRUCTION	JA		
0	02/10/14	ISSUED FOR REVIEW	NB		

DPH

SITE NUMBER: CT43XC827

SITE NAME: MANCHESTER/POLICE TOWER

> SITE ADDRESS: 239 MIDDLE TURNPIKE MANCHESTER, CT 06040

> > SHEET TITLE

GROUNDING DETAILS AND NOTES

SHEET NUMBER

E-2

## NOTES

1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.

TWO HOLE SPADE, TO BE USED TO CONNECT TO GROUND BAR

2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.

## INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR

E-2

TWO HOLE LUG

SCALE: N.T.S.

3
E-2

# (Revised) STRUCTURAL ANALYSIS REPORT

For

## CT43XC827

MANCHESTER/POLICE TOWER

239 Middle Turnpike Manchester, CT 06040

## Antennas Mounted to the Monopole



Prepared for:



1 INTERNATIONAL BLVD, SUITE 800 MAHWAH, NJ 07495 TEL: (201) 684-4223

Dated: April 10, 2015

Prepared by:



1600 Osgood Street Bldg. 20N Suite 3090 North Andover, MA 01845 (P) 978.557.5553 (F) 978.336.5586

www.hudsondesigngroupllc.com





## **SCOPE OF WORK:**

Hudson Design Group LLC (HDG) has been authorized by Sprint to conduct a structural evaluation of the 183' monopole supporting the existing and proposed Sprint's antennas located at elevation 153' above the ground level.

This report represents this office's findings, conclusions and recommendations pertaining to the support of Sprint's existing and proposed antennas listed below.

Record drawings of the existing monopole prepared by Engineered Endeavors Inc., dated September 17, 2002, were available for our use. The previous structural analysis report prepared by Ramaker & Associates, Inc., dated November 26, 2012, was available and obtained for our use. The previous structural analysis report prepared by Destek Engineering, LLC, dated October 14, 2014, was also available and obtained for our use.

## **CONCLUSION SUMMARY:**

HDG performed structural analysis of the existing monopole with the following proposed modifications:

- 1. Add steel reinforcing plates to the existing monopole from El.1' to El.88'.
- 2. Add steel stiffener plates to the base plate of the monopole.

Estimated costs for materials and labor for the above mentioned tower modifications is estimated between \$70K-\$90K

Based on our evaluation, we have determined that the existing monopole with proposed modifications and foundation <u>are in conformance</u> with the ANSI/TIA-222-F Standard for the loading considered under the criteria listed in this report. <u>The monopole structure is rated at 95.7%</u> - (Pole section L3 from EL.88.0' to EL.133.1' Controlling).



## **APPURTANENCES CONFIGURATION:**

Tenant	Appurtenances		Mount
	Lighting Rod	194'	Low Profile Platform
	(2) 20' Dipole	184'	Low Profile Platform
T-MOBILE	T-MOBILE (3) AIR 21 B2A B4P Antennas		Low Profile Platform
T-MOBILE	(3) AIR 21 B4A B12P Antennas	163'	Low Profile Platform
T-MOBILE	(3) ATMAP1412D TMA	163'	Low Profile Platform
T-MOBILE	(3) RRUS 11	163'	Low Profile Platform
Sprint	(3) APXVSPP18 Antennas	153'	Low Profile Platform
Sprint	(3) RRH-800	153'	Low Profile Platform
Sprint	(6) RRH-1900	153'	Low Profile Platform
Sprint	(3) APXVTM14-C-120 Antennas	153'	Low Profile Platform
Sprint	(3) RRH8x20-25	151'	Ring Mount
	(3) 840-10054 Antennas	153'	Low Profile Platform
	(3) 860-10025 RCU	153'	Low Profile Platform
	Panel Antenna	153'	Low Profile Platform
	(2) 2' Dishes	150'	Low Profile Platform
	2.5' Dish	150'	Low Profile Platform
AT&T	(3) 800-10121 Antennas	143'	Low Profile Platform
AT&T	(2) OPA-65R-LCUU-H6 Antennas	143'	Low Profile Platform
AT&T	(4) OPA-65R-LCUU-H8 Antennas	143'	Low Profile Platform
AT&T (12) RRUs		143'	Low Profile Platform
AT&T	(3) A2 Modules	143'	Low Profile Platform
AT&T	(2) Surge Arrestors	143'	Low Profile Platform
	(2) 20' Omni	129'	Low Profile Platform
	20' Dipole	126'	Low Profile Platform
	(2) 3' Yagi	126'	Low Profile Platform
VERIZON	(6) LNX 6514DS-VTM Antennas	110'	Low Profile Platform
VERIZON	(6) HBX 6517DS-VTM Antennas	110'	Low Profile Platform
VERIZON	(3) RRH 2X40-AWS	110'	Low Profile Platform
VERIZON	(3) RRH 2X40-07U	110'	Low Profile Platform
VERIZON	(3) RRH 2X40-PCS	110'	Low Profile Platform
VERIZON	(2) DB-T1-6Z-8AB-0Z	110'	Low Profile Platform
	GPS	54'	1' Side Mount Standoff
POLICE	(4) VHLPX2-18 Dish	38.9'	1' Side Mount Standoff

<sup>\*</sup>Proposed SPRINT Appurtenances shown in Bold.



## **SPRINT EXISTING/PROPOSED COAX CABLES:**

	Tenant Coax Cables		Elev.	Mount
Sprint		(3) 1 1/4" Fiber Cables	153'	Inside Monopole

<sup>\*</sup>Proposed SPRINT Coax Cables shown in Bold.

## **ANALYSIS RESULTS SUMMARY:**

Component	Max. Stress Ratio	Elev. of Component (ft)	Pass/Fail	Comments
Pole Section-L1	13.8 %	166.5 – 184.0	PASS	
Pole Section-L2	66.1 %	133.1 – 166.5	PASS	
Pole Section-L3	95.7 %	88.0 – 133.1	PASS	Controlling
Pole Section-L4	92.2 %	43.9 – 88.0	PASS	
Pole Section-L5	88.9 %	1.0 – 43.9	PASS	
Base Plate	84.3 %	1.0	PASS	



## **DESIGN CRITERIA:**

1. EIA/TIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures

County: Hartford

Wind Load: 80 mph (fastest mile) 100 mph (3 second gust)

Nominal Ice Thickness: 1/2 inch

2. Approximate height above grade to proposed antennas: 153'-0"

\*Calculations and referenced documents are attached.

## **ASSUMPTIONS:**

- 1. The monopole dimensions, member sizes and strength of material are as indicated in the record drawings prepared by Engineered Endeavors Inc., dated September 17, 2002.
- 2. The appurtenances configuration is as stated in this report. All antennas, coax cables and waveguide cables are assumed to be properly installed and supported as per the manufacturer's requirements.
- 3. The monopole and foundation are properly constructed and maintained. All structural members and their connections are assumed to be in good condition and are free from defects with no deterioration to its member capacities.
- 4. The support mounts and platforms are not analyzed and are considered adequate to support the loading. The analysis is limited to the primary support structure itself.
- 5. All prior structural modification, if any, are assumed to be as per the data supplied (if available), and installed properly.



## **SUPPORT RECOMMENDATIONS:**

HDG recommends that the proposed antennas be mounted on the existing steel platform supported by the monopole; the proposed RRHs be mounted on the proposed mount pipes.

## ONGOING AND PERIODIC INSPTECTION AND MAINTENANCE:

After the Contractor has successfully completed the installation and the work has been accepted, the Owner will be responsible for the ongoing and periodic inspection and maintenance of the tower.

The owner shall refer to TIA/EIA-222-F for recommendations for maintenance and inspection. The frequency of the inspection and maintenance intervals is to be determined by the owner based upon actual site and environmental conditions. It is recommended that a complete and thorough inspection of the entire tower structural system be performed at least yearly and more frequently as conditions warrant. According to TIA/EIA-222-F section 14.1, Note 1: It is recommended that the structure be inspected after severe wind and/or ice storms or other extreme loading conditions.






**Photo 1:** Photo illustrating the Monopole with Appurtenances shown.



## **CALCULATIONS**



Hudson Jesign Group

## **DESIGNED APPURTENANCE LOADING**

TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod 2"x21'	184	Kathrein 800 10121 w/mount pipe	143
PiROD 13' Low Profile Platform	184	Kathrein 800 10121 w/mount pipe	143
20'-4 Bay Dipole	184	Ericsson RRUS-11	143
20'-4 Bay Dipole	184	Ericsson RRUS-11	143
PiROD 13' Low Profile Platform	163	Ericsson RRUS-11	143
(T-Mobile)	100	DC6-48-60-18-8F	143
ERICSSON AIR 21 B2A B4P w/ Mount	163	(2) OPA-65R-LCUU-H6 w/mount pipe	143
Pipe		(2) OPA-65R-LCUU-H8 w/mount pipe	143
ERICSSON AIR 21 B2A B4P w/ Mount	163	(2) OPA-65R-LCUU-H8 w/mount pipe	143
Pipe		Ericsson RRUS-12	143
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	163	Ericsson RRUS-12	143
RFS ATMAP1412D-1A20	163	Ericsson RRUS-12	143
RFS ATMAP1412D-1A20	163	Ericsson RRUS-32	143
RFS ATMAP1412D-1A20	163	Ericsson RRUS-32	143
ERICSSON AIR 21 B4A B12P-B8P w/	163	Ericsson RRUS-32	143
Mount Pipe	100	Ericsson RRUS-E2	143
ERICSSON AIR 21 B4A B12P-B8P w/	163	Ericsson RRUS-E2	143
Mount Pipe		Ericsson RRUS-E2	143
ERICSSON AIR 21 B4A B12P-B8P w/	163	Ericsson A2 Module	143
Mount Pipe		Ericsson A2 Module	143
Ericsson RRUS 11	163	Ericsson A2 Module	143
Ericsson RRUS 11	163	Surge Arrestor (DC6-48-60-18-8F)	143
Ericsson RRUS 11	163	20'-4 Bay Dipole	123
PiROD 13' Low Profile Platform (SPRINT - existing)	153	3' Yagi antenna	123
APXVSPP18-C w/mount pipe	153	3' Yagi antenna	123
		PiROD 13' Low Profile Platform	123
APXVSPP18-C w/mount pipe APXVSPP18-C w/mount pipe	153 153	Omni 2"x10'	123
2) RRH-1900	153	Omni 2"x10'	123
2) RRH-1900	153	(2) LNX 6514DS-VTM w/mount pipe	110
(2) RRH-1900	153	(2) LNX 6514DS-VTM w/mount pipe	110
RRH-800	153	(2) LNX 6514DS-VTM w/mount pipe	110
RRH-800	153	(2) HBX-6517DS-VTM w/mount pipe	110
RRH-800	153	(2) HBX-6517DS-VTM w/mount pipe	110
APXVTM14-C-120 w/mount pipe	153	(2) HBX-6517DS-VTM w/mount pipe	110
(SPRINT - proposed)	133	RRH 2X40-AWS+RDEM	110
APXVTM14-C-120 w/mount pipe	153	RRH 2X40-AWS+RDEM	110
APXVTM14-C-120 w/mount pipe	153	RRH 2X40-AWS+RDEM	110
340-10054 w/mount pipe	153	RRH 2X40-07U	110
340-10054 w/mount pipe	153	RRH 2X40-07U	110
340-10054 w/mount pipe	153	RRH 2X40-07U	110
Kathrein 860 10025 RCU	153	RRH 2X40-PCS	110
Kathrein 860 10025 RCU	153	RRH 2X40-PCS	110
Kathrein 860 10025 RCU	153	RRH 2X40-PCS	110
Panel Antenna 18"X18"	153	RFS DB-T1-6Z-8AB-0Z	110
Ring Mount	151	RFS DB-T1-6Z-8AB-0Z	110
RRH 8x20-25	151	PiROD 13' Low Profile Platform	110
RRH 8x20-25	151	(Verizon - proposed)	54
RRH 8x20-25	151	GPS	54
Andrew VHLP2-11	150	1' Side Mount Standoff	54
Andrew VHLPX2.5-11	150	1' Side Mount Standoff	38.9
Andrew VHLP2-11	150	1' Side Mount Standoff	38.9
PIROD 13' Low Profile Platform (ATI)	143	1' Side Mount Standoff	38.9
	143	Andrew VHLPX2-18-2WH/B	38.9
Kathrein 800 10121 w/mount pipe	143	Andrew VHLPX2-18-2WH/B	38.9

## **MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A E 72 G E	SE koj	90 kai			

## **TOWER DESIGN NOTES**

- 1. Tower is located in Hartford County, Connecticut.
- Tower designed for a 80.0 mph basic wind in accordance with the TIA/EIA-222-F Standard.
   Tower is also designed for a 69.3 mph basic wind with 0.50 in ice.
   Deflections are based upon a 50.0 mph wind.





## Hudson Design Group LLC

1600 Osgood Street Bldg. 20N Suite 3090 North Andover, MA 01845 Phone: (978) 557-5553 FAX: (978) 226-5586

	Job		
	CT43XC	827 MANCHESTER POI	LICE TOWER 1 of 11
	Project		Date
0		183 ft Monopole	10:42:00 04/10/15
	Client	ODDINIT	Designed by
		SPRINT	kw

## **Tower Input Data**

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Hartford County, Connecticut.

Basic wind speed of 80.0 mph.

Nominal ice thickness of 0.5000 in.

Ice density of 56.0 pcf.

A wind speed of 69.3 mph is used in combination with ice.

Temperature drop of 50.0 °F.

Deflections calculated using a wind speed of 50.0 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## **Tapered Pole Section Geometry**

Section	Elevation	Section	Splice	Number	Тор	Bottom	Wall	Bend	Pole Grade
		Length	Length	of	Diameter	Diameter	Thickness	Radius	
	ft	ft	ft	Sides	in	in	in	in	
L1	184.00-166.50	17.50	3.00	18	15.5000	19.3990	0.1875	0.7500	A572-65
									(65 ksi)
L2	166.50-133.08	36.42	3.83	18	18.3556	26.4010	0.2500	1.0000	A572-65
									(65 ksi)
L3	133.08-87.99	48.92	5.00	18	25.0549	35.8920	0.3750	1.5000	A572-65
									(65 ksi)
L4	87.99-43.91	49.08	6.17	18	34.0344	44.9030	0.4850	1.9400	A572-65
									(65 ksi)
L5	43.91-1.00	49.08		18	42.5667	53.5000	0.5400	2.1600	A572-65
									(65 ksi)

## **Monopole Base Plate Data**

Base Plate Dat	a
Base plate is square	
Base plate is grouted	$\checkmark$
Anchor bolt grade	A615-75
Anchor bolt size	2.2500 in
Number of bolts	18
Embedment length	84.0000 in
f'c	4.0 ksi
Grout space	4.0000 in
Base plate grade	A572-60
Base plate thickness	2.0000 in
Bolt circle diameter	62.0000 in
Outer diameter	68.0000 in
Inner diameter	43.0000 in
Base plate type	Stiffened Plate
Bolts per stiffener	1



## Hudson Design Group LLC

1600 Osgood Street Bldg. 20N Suite 3090 North Andover, MA 01845 Phone: (978) 557-5553 FAX: (978) 226-5586

	Job		Page
	CT43XC827	MANCHESTER POLICE TOWER	2 of 11
	Project		Date
)		183 ft Monopole	10:42:00 04/10/15
	Client	000WT	Designed by
		SPRINT	kw

Base Plate D	ata
Stiffener thickness	0.5000 in
Stiffener height	9.0000 in

## Feed Line/Linear Appurtenances - Entered As Area

Description	Face	Allow	Component	Placement	Total		$C_A A_A$	Weight
	or	Shield	Type		Number			
	Leg			ft			ft²/ft	plf
2" Conduit	A	No	CaAa (Out Of	153.00 - 6.00	2	No Ice	0.20	2.80
			Face)			1/2" Ice	0.30	4.33
1/2	Α	No	CaAa (Out Of	153.00 - 6.00	3	No Ice	0.06	0.25
			Face)			1/2" Ice	0.16	0.91
3/8	Α	No	Inside Pole	153.00 - 6.00	3	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
7/8	В	No	Inside Pole	184.00 - 6.00	4	No Ice	0.00	0.54
						1/2" Ice	0.00	0.54
1 5/8	В	No	Inside Pole	163.00 - 6.00	12	No Ice	0.00	1.04
(T-MOBILE)						1/2" Ice	0.00	1.04
1 5/8 Fiber Cable	В	No	Inside Pole	163.00 - 6.00	9	No Ice	0.00	1.04
(T-MOBILE)						1/2" Ice	0.00	1.04
1 1/4	В	No	Inside Pole	153.00 - 6.00	3	No Ice	0.00	0.66
(SPRINT)						1/2" Ice	0.00	0.66
1 5/8	В	No	Inside Pole	143.00 - 6.00	6	No Ice	0.00	1.04
(AT&T)						1/2" Ice	0.00	1.04
FB-L98B-002	В	No	Inside Pole	143.00 - 6.00	3	No Ice	0.00	0.25
(AT&T)						1/2" Ice	0.00	0.25
WR-VG122ST-BRDA	В	No	Inside Pole	143.00 - 6.00	6	No Ice	0.00	0.25
(AT&T)						1/2" Ice	0.00	0.25
1/2	В	No	Inside Pole	123.00 - 6.00	5	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
1/2	В	No	Inside Pole	54.00 - 6.00	1	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
1/2	В	No	Inside Pole	38.90 - 6.00	4	No Ice	0.00	0.25
						1/2" Ice	0.00	0.25
*******								
1 5/8 Fiber Cable	В	No	Inside Pole	110.00 - 6.00	2	No Ice	0.00	1.04
(VERIZON)						1/2" Ice	0.00	1.04

## **Discrete Tower Loads**

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	Placement		$C_AA_A$ Front	C <sub>A</sub> A <sub>A</sub> Side	Weight
			ft ft ft	٥	ft		ft <sup>2</sup>	ft <sup>2</sup>	lb
Lightning Rod 2"x21'	A	From Leg	1.00 0.00 10.00	0.0000	184.00	No Ice 1/2" Ice	4.20 6.33	4.20 6.33	80.00 112.30
PiROD 13' Low Profile Platform	A	None		0.0000	184.00	No Ice 1/2" Ice	15.70 20.10	15.70 20.10	1300.00 1765.00
20'-4 Bay Dipole	С	From Face	3.50 4.00 0.00	0.0000	184.00	No Ice 1/2" Ice	4.75 6.25	4.75 6.25	50.00 80.00
20'-4 Bay Dipole	C	From Face	3.50	0.0000	184.00	No Ice	4.75	4.75	50.00



J	lob	Page
	CT43XC827 MANCHESTER POLICE TOWER	3 of 11
	Project	Date
)	183 ft Monopole	10:42:00 04/10/15
	Client SPRINT	Designed by kw

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		$C_A A_A$ Front	$C_AA_A$ Side	Weight
	Leg		Vert						
			ft ft ft	0	ft		ft <sup>2</sup>	ft <sup>2</sup>	lb
			-4.00 0.00			1/2" Ice	6.25	6.25	80.00
******			0.00						
PiROD 13' Low Profile Platform (T-Mobile)	A	None		0.0000	163.00	No Ice 1/2" Ice	15.70 20.10	15.70 20.10	1300.00 1765.00
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	A	From Face	3.50 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	6.83 7.35	5.64 6.48	112.18 169.02
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	В	From Face	3.50 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	6.83 7.35	5.64 6.48	112.18 169.02
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	С	From Face	3.50 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	6.83 7.35	5.64 6.48	112.18 169.02
RFS ATMAP1412D-1A20	A	From Face	2.50 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	1.17 1.31	0.47 0.57	13.00 20.62
RFS ATMAP1412D-1A20	В	From Face	2.50 0.00	0.0000	163.00	No Ice 1/2" Ice	1.17 1.31	0.47 0.57	13.00 20.62
RFS ATMAP1412D-1A20	С	From Face	0.00 2.50 0.00	0.0000	163.00	No Ice 1/2" Ice	1.17 1.31	0.47 0.57	13.00 20.62
ERICSSON AIR 21 B4A B12P-B8P w/ Mount Pipe	A	From Face	0.00 3.50 0.00	0.0000	163.00	No Ice 1/2" Ice	11.34 12.00	9.07 10.30	160.55 248.37
ERICSSON AIR 21 B4A B12P-B8P w/ Mount Pipe	В	From Face	0.00 3.50 0.00	0.0000	163.00	No Ice 1/2" Ice	11.34 12.00	9.07 10.30	160.55 248.37
ERICSSON AIR 21 B4A B12P-B8P w/ Mount Pipe	C	From Face	0.00 3.50 0.00	0.0000	163.00	No Ice 1/2" Ice	11.34 12.00	9.07 10.30	160.55 248.37
Ericsson RRUS 11	A	From Face	0.00 2.50 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	2.94 3.17	1.25 1.41	55.00 74.32
Ericsson RRUS 11	В	From Face	2.50 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	2.94 3.17	1.25 1.41	55.00 74.32
Ericsson RRUS 11	C	From Face	2.50 0.00 0.00	0.0000	163.00	No Ice 1/2" Ice	2.94 3.17	1.25 1.41	55.00 74.32
******			0.00						
PiROD 13' Low Profile Platform	A	None		0.0000	153.00	No Ice 1/2" Ice	15.70 20.10	15.70 20.10	1300.00 1765.00
(SPRINT - existing) APXVSPP18-C w/mount pipe	A	From Face	3.50 0.00 0.00	0.0000	153.00	No Ice 1/2" Ice	8.50 9.15	6.95 8.13	82.55 150.56
APXVSPP18-C w/mount pipe	В	From Face	3.50 0.00 0.00	0.0000	153.00	No Ice 1/2" Ice	8.50 9.15	6.95 8.13	82.55 150.56
APXVSPP18-C w/mount pipe	С	From Face	3.50 0.00 0.00	0.0000	153.00	No Ice 1/2" Ice	8.50 9.15	6.95 8.13	82.55 150.56
(2) RRH-1900	A	From Face	1.00 0.00	0.0000	153.00	No Ice 1/2" Ice	2.71 2.95	3.66 3.92	60.00 88.32



	Job			Page
		CT43XC827	MANCHESTER POLICE TOWER	4 of 11
	Project			Date
90			183 ft Monopole	10:42:00 04/10/15
	Client		SPRINT	Designed by kw

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		$C_A A_A$ Front	$C_AA_A$ Side	Weight
	Leg		Vert ft ft ft	o	ft		$ft^2$	ft²	lb
(2) RRH-1900	В	From Face	0.00 1.00 0.00	0.0000	153.00	No Ice 1/2" Ice	2.71 2.95	3.66 3.92	60.00 88.32
(2) RRH-1900	C	From Face	0.00 1.00 0.00	0.0000	153.00	No Ice 1/2" Ice	2.71 2.95	3.66 3.92	60.00 88.32
RRH-800	A	From Face	0.00 1.00 0.00	0.0000	153.00	No Ice 1/2" Ice	2.49 2.71	3.22 3.46	64.00 91.74
RRH-800	В	From Face	0.00 1.00 0.00	0.0000	153.00	No Ice 1/2" Ice	2.49 2.71	3.22 3.46	64.00 91.74
RRH-800	C	From Face	0.00 1.00 0.00	0.0000	153.00	No Ice 1/2" Ice	2.49 2.71	3.22 3.46	64.00 91.74
******			0.00						
APXVTM14-C-120 w/mount pipe (SPRINT - proposed)	A	From Face	3.50 0.00 0.00	0.0000	153.00	No Ice 1/2" Ice	7.21 7.77	5.03 5.89	91.90 147.31
APXVTM14-C-120 w/mount pipe	В	From Face	3.50 0.00 0.00	0.0000	153.00	No Ice 1/2" Ice	7.21 7.77	5.03 5.89	91.90 147.31
APXVTM14-C-120 w/mount pipe	C	From Face	3.50 0.00	0.0000	153.00	No Ice 1/2" Ice	7.21 7.77	5.03 5.89	91.90 147.31
RRH 8x20-25	A	From Face	0.00 1.00 0.00	0.0000	151.00	No Ice 1/2" Ice	4.72 5.01	1.70 1.92	70.00 97.14
RRH 8x20-25	В	From Face	0.00 1.00 0.00	0.0000	151.00	No Ice 1/2" Ice	4.72 5.01	1.70 1.92	70.00 97.14
RRH 8x20-25	C	From Face	0.00 1.00 0.00	0.0000	151.00	No Ice 1/2" Ice	4.72 5.01	1.70 1.92	70.00 97.14
Ring Mount	C	None	0.00	0.0000	151.00	No Ice 1/2" Ice	1.40 2.40	1.40 2.40	90.00 130.00
840-10054 w/mount pipe	A	From Face	3.50 0.00	0.0000	153.00	No Ice 1/2" Ice	5.41 5.83	2.39 2.92	46.43 82.55
840-10054 w/mount pipe	В	From Face	0.00 3.50 0.00	0.0000	153.00	No Ice 1/2" Ice	5.41 5.83	2.39 2.92	46.43 82.55
840-10054 w/mount pipe	C	From Face	0.00 3.50 0.00	0.0000	153.00	No Ice 1/2" Ice	5.41 5.83	2.39 2.92	46.43 82.55
Kathrein 860 10025 RCU	A	From Face	0.00 2.50 0.00	0.0000	153.00	No Ice 1/2" Ice	0.16 0.23	0.14 0.20	1.20 2.76
Kathrein 860 10025 RCU	В	From Face	0.00 2.50 0.00	0.0000	153.00	No Ice 1/2" Ice	0.16 0.23	0.14 0.20	1.20 2.76
Kathrein 860 10025 RCU	C	From Face	0.00 2.50 0.00	0.0000	153.00	No Ice 1/2" Ice	0.16 0.23	0.14 0.20	1.20 2.76
		From Face	0.00						



	Job			Page
		CT43XC827	MANCHESTER POLICE TOWER	5 of 11
	Project	t		Date
00			183 ft Monopole	10:42:00 04/10/15
	Client		ODDINT	Designed by
			SPRINT	kw

*****	Leg		Lateral Vert ft ft ft	٥					
	A				ft		ft²	ft <sup>2</sup>	lb
ماد	A		0.00 0.00			1/2" Ice	3.39	0.67	30.30
****	A								
PiROD 13' Low Profile Platform		None		0.0000	123.00	No Ice 1/2" Ice	15.70 20.10	15.70 20.10	1300.00 1765.00
Omni 2"x10'	В	From Face	3.50 0.00 6.00	0.0000	123.00	No Ice 1/2" Ice	2.00 3.02	2.00 3.02	20.00 35.50
Omni 2"x10'	В	From Face	3.50 0.00	0.0000	123.00	No Ice 1/2" Ice	2.00 3.02	2.00 3.02	20.00 35.50
20'-4 Bay Dipole	С	From Face	6.00 3.50	0.0000	123.00	No Ice	4.75	4.75	50.00
20 -4 Bay Dipole	C	rioni race	0.00 3.00	0.0000	123.00	1/2" Ice	6.25	6.25	80.00
3' Yagi antenna	В	From Face	3.50 0.00	0.0000	123.00	No Ice 1/2" Ice	0.70 0.95	0.35 0.48	10.00 36.35
			3.00						
3' Yagi antenna	С	From Face	3.50 0.00	0.0000	123.00	No Ice 1/2" Ice	0.70 0.95	0.35 0.48	10.00 36.35
******			3.00						
1' Side Mount Standoff	C	From Face	1.00 0.00	0.0000	54.00	No Ice 1/2" Ice	1.00 1.50	1.00 1.50	30.00 50.00
GPS	C	From Face	0.00 3.00 0.00	0.0000	54.00	No Ice 1/2" Ice	0.21 0.32	0.21 0.32	5.00 7.52
******			0.00						
PiROD 13' Low Profile Platform	A	None		0.0000	143.00	No Ice 1/2" Ice	15.70 20.10	15.70 20.10	1300.00 1765.00
(AT&T) Kathrein 800 10121 w/mount pipe	A	From Face	3.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	5.72 6.21	4.81 5.49	78.15 128.24
Kathrein 800 10121 w/mount pipe	В	From Face	3.50 0.00	0.0000	143.00	No Ice 1/2" Ice	5.72 6.21	4.81 5.49	78.15 128.24
Kathrein 800 10121 w/mount pipe	C	From Face	0.00 3.50 0.00	0.0000	143.00	No Ice 1/2" Ice	5.72 6.21	4.81 5.49	78.15 128.24
			0.00						
Ericsson RRUS-11	A	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.26 3.50	1.38 1.56	50.70 71.57
Ericsson RRUS-11	В	From Face	2.50 0.00	0.0000	143.00	No Ice 1/2" Ice	3.26 3.50	1.38 1.56	50.70 71.57
Ericsson RRUS-11	C	From Face	0.00 2.50 0.00	0.0000	143.00	No Ice 1/2" Ice	3.26 3.50	1.38 1.56	50.70 71.57
DC6-48-60-18-8F	C	From Leg	0.00 2.00 0.00	0.0000	143.00	No Ice 1/2" Ice	1.27 1.46	1.27 1.46	20.00 35.12
*******			0.00						
(2) OPA-65R-LCUU-H6 w/mount pipe	A	From Face	3.50 0.00	0.0000	143.00	No Ice 1/2" Ice	10.65 11.30	7.53 8.56	112.53 192.76
(2) OPA-65R-LCUU-H8	В	From Face	0.00 3.50	0.0000	143.00	No Ice	13.34	9.83	140.11



	Job		Page
	CT43XC827	MANCHESTER POLICE TOWER	6 of 11
	Project		Date
)		183 ft Monopole	10:42:00 04/10/15
	Client	ODDIVIT	Designed by
		SPRINT	kw

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		$C_A A_A$ Front	$C_AA_A$ Side	Weigl
	208		Vert	٥	C.		c.2	$c^2$	11.
			ft ft	v	ft		ft <sup>2</sup>	$ft^2$	lb
w/mount pipe			0.00 0.00			1/2" Ice	14.18	11.34	239.3
(2) OPA-65R-LCUU-H8 w/mount pipe	C	From Face	3.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	13.34 14.18	9.83 11.34	140.1 239.3
Ericsson RRUS-12	A	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.67 3.93	1.49 1.67	58.00 81.22
Ericsson RRUS-12	В	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.67 3.93	1.49 1.67	58.00 81.22
Ericsson RRUS-12	С	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.67 3.93	1.49 1.67	58.00 81.22
Ericsson RRUS-32	A	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.87 4.15	2.76 3.02	77.00 104.9
Ericsson RRUS-32	В	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.87 4.15	2.76 3.02	77.00 104.9
Ericsson RRUS-32	С	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.87 4.15	2.76 3.02	77.00 104.9
Ericsson RRUS-E2	A	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.87 4.15	2.76 3.02	77.00 104.9
Ericsson RRUS-E2	В	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.87 4.15	2.76 3.02	77.00 104.9
Ericsson RRUS-E2	С	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	3.87 4.15	2.76 3.02	77.0 104.9
Ericsson A2 Module	A	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	2.42 2.63	0.54 0.67	22.0 34.7
Ericsson A2 Module	В	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	2.42 2.63	0.54 0.67	22.0 34.7
Ericsson A2 Module	С	From Face	2.50 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	2.42 2.63	0.54 0.67	22.00 34.7
Surge Arrestor (DC6-48-60-18-8F) ************************************	A	From Leg	2.00 0.00 0.00	0.0000	143.00	No Ice 1/2" Ice	1.27 1.46	1.27 1.46	20.0 35.1
PiROD 13' Low Profile Platform	C	None		0.0000	110.00	No Ice 1/2" Ice	15.70 20.10	15.70 20.10	1300. 1765.
(Verizon - proposed) (2) LNX 6514DS-VTM w/mount pipe	A	From Face	3.50 0.00 0.00	0.0000	110.00	No Ice 1/2" Ice	8.63 9.29	7.07 8.25	64.5. 133.5
(2) LNX 6514DS-VTM w/mount pipe	В	From Face	3.50 0.00 0.00	0.0000	110.00	No Ice 1/2" Ice	8.63 9.29	7.07 8.25	64.5. 133.5
(2) LNX 6514DS-VTM w/mount pipe	C	From Face	3.50 0.00 0.00	0.0000	110.00	No Ice 1/2" Ice	8.63 9.29	7.07 8.25	64.5 133.5



	Job			Page
		CT43XC827	MANCHESTER POLICE TOWER	7 of 11
	Projec	t		Date
00			183 ft Monopole	10:42:00 04/10/15
Client			Designed by	
			kw	

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement		$C_A A_A$ Front	$C_A A_A$ Side	Weight
	Les		Vert						
			ft ft	0	ft		ft <sup>2</sup>	ft <sup>2</sup>	lb
(2) HBX-6517DS-VTM	A	From Face	3.50	0.0000	110.00	No Ice	5.42	4.96	39.25
w/mount pipe	А	1 Tom 1 acc	0.00 0.00	0.0000	110.00	1/2" Ice	5.97	6.14	85.00
(2) HBX-6517DS-VTM w/mount pipe	В	From Face	3.50 0.00	0.0000	110.00	No Ice 1/2" Ice	5.42 5.97	4.96 6.14	39.25 85.00
(2) HBX-6517DS-VTM w/mount pipe	C	From Face	0.00 3.50 0.00	0.0000	110.00	No Ice 1/2" Ice	5.42 5.97	4.96 6.14	39.25 85.00
William Pipe			0.00			1/2 100	0.57	0.11	00.00
RRH 2X40-AWS+RDEM	A	From Face	2.50 0.00	0.0000	110.00	No Ice 1/2" Ice	3.77 4.04	2.23 2.46	47.60 73.79
RRH 2X40-AWS+RDEM	В	From Face	0.00 2.50	0.0000	110.00	No Ice	3.77	2.23	47.60
RKII 2A40-AW3+RDEW	Ь	110m race	0.00 0.00	0.0000	110.00	1/2" Ice	4.04	2.46	73.79
RRH 2X40-AWS+RDEM	C	From Face	2.50	0.0000	110.00	No Ice	3.77	2.23	47.60
			0.00 0.00			1/2" Ice	4.04	2.46	73.79
RRH 2X40-07U	A	From Face	2.50	0.0000	110.00	No Ice	2.29	1.21	50.00
			0.00 0.00			1/2" Ice	2.49	1.36	66.78
RRH 2X40-07U	В	From Face	2.50 0.00	0.0000	110.00	No Ice 1/2" Ice	2.29 2.49	1.21 1.36	50.00 66.78
RRH 2X40-07U	С	From Face	0.00 2.50	0.0000	110.00	No Ice	2.29	1.21	50.00
			0.00			1/2" Ice	2.49	1.36	66.78
RRH 2X40-PCS	A	From Face	2.50	0.0000	110.00	No Ice	2.57	2.02	55.00
			0.00 0.00			1/2" Ice	2.79	2.23	75.41
RRH 2X40-PCS	В	From Face	2.50	0.0000	110.00	No Ice	2.57	2.02	55.00
			0.00			1/2" Ice	2.79	2.23	75.41
RRH 2X40-PCS	C	From Face	2.50	0.0000	110.00	No Ice	2.57	2.02	55.00
			0.00			1/2" Ice	2.79	2.23	75.41
RFS DB-T1-6Z-8AB-0Z	В	From Face	1.50	0.0000	110.00	No Ice	5.60	2.33	44.00
			0.00			1/2" Ice	5.92	2.56	80.13
RFS DB-T1-6Z-8AB-0Z	С	From Face	1.50 0.00	0.0000	110.00	No Ice 1/2" Ice	5.60 5.92	2.33 2.56	44.00 80.13
			0.00						
**************************************	A	From Food	0.50	0.0000	29.00	No Iss	1.00	1.00	20.00
1' Side Mount Standoff	A	From Face	0.50 0.00 0.00	0.0000	38.90	No Ice 1/2" Ice	1.00 1.50	1.00 1.50	30.00 50.00
1' Side Mount Standoff	В	From Face	0.50	0.0000	38.90	No Ice	1.00	1.00	30.00
			0.00			1/2" Ice	1.50	1.50	50.00
1' Side Mount Standoff	С	From Face	0.50 0.00	0.0000	38.90	No Ice 1/2" Ice	1.00 1.50	1.00 1.50	30.00 50.00



1600 Osgood Street Bldg. 20N Suite 30 North Andover, MA 01845 Phone: (978) 557-5553 FAX: (978) 226-5586

	Job			Page
		CT43XC827	MANCHESTER POLICE TOWER	8 of 11
	Projec	et		Date
)			183 ft Monopole	10:42:00 04/10/15
	Client		OPPINIT	Designed by
			SPRINT	kw

Dishes											
Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter		Aperture Area	Weight
				ft	0	0	ft	ft		$ft^2$	lb
Andrew VHLP2-11	A	Paraboloid w/Radome	From Face	3.50 0.00 0.00	0.0000		150.00	2.00	No Ice 1/2" Ice	3.14 3.41	31.00 41.00
Andrew VHLPX2.5-11	В	Paraboloid w/Shroud (HP)	From Face	3.50 0.00 0.00	0.0000		150.00	2.50	No Ice 1/2" Ice	6.00 6.40	49.00 77.00
Andrew VHLP2-11	C	Paraboloid w/Radome	From Face	3.50 0.00 0.00	0.0000		150.00	2.00	No Ice 1/2" Ice	3.14 3.41	31.00 41.00
Andrew VHLPX2-18-2WH/B	A	Paraboloid w/Radome	From Face	2.00 0.00 0.00	0.0000		38.90	2.00	No Ice 1/2" Ice	3.14 3.41	25.00 35.00
Andrew VHLPX2-18-2WH/B	В	Paraboloid w/Radome	From Face	2.00 0.00 0.00	0.0000		38.90	2.00	No Ice 1/2" Ice	3.14 3.41	25.00 35.00
(2) Andrew VHLPX2-18-2WH/B	С	Paraboloid w/Radome	From Face	2.00 0.00 0.00	0.0000		38.90	2.00	No Ice 1/2" Ice	3.14 3.41	25.00 35.00

## **Load Combinations**

Comb.	Description
No.	
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
	-



1600 Osgood Street Bldg. 20N Suite 30 North Andover, MA 01845 Phone: (978) 557-5553 FAX: (978) 226-5586

	Job CT43XC	C827 MANCHESTER POL	LICE TOWER 9 of 11
)	Project	183 ft Monopole	Date 10:42:00 04/10/15
	Client	SPRINT	Designed by kw

Comb.	Description
No.	
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

## **Maximum Reactions**

Location	Condition	Gov.	Vertical	Horizontal, X	Horizontal, 2
		Load	lb	lb	lb
		Comb.			
Pole	Max. Vert	24	64424.89	31977.47	-135.40
	$Max. H_x$	11	53151.36	36359.64	-182.71
	Max. H <sub>z</sub>	2	53151.36	-230.38	36335.05
	Max. M <sub>x</sub>	2	4462772.09	-230.38	36335.05
	Max. M <sub>z</sub>	5	4468109.01	-36333.10	246.35
	Max. Torsion	9	2566.54	18354.94	-31557.65
	Min. Vert	1	53151.36	0.00	0.00
	Min. H <sub>x</sub>	5	53151.36	-36333.10	246.35
	Min. H <sub>z</sub>	8	53151.36	272.09	-36376.99
	Min. M <sub>x</sub>	8	-4466008.94	272.09	-36376.99
	Min. M <sub>z</sub>	11	-4470961.07	36359.64	-182.71
	Min. Torsion	3	-2629.11	-18388.28	31537.02

## **Tower Mast Reaction Summary**

Load	Vertical	$Shear_x$	$Shear_z$	Overturning	Overturning	Torque
Combination				Moment, $M_x$	Moment, $M_z$	
	lb	lb	lb	lb-ft	lb-ft	lb-ft
Dead Only	53151.36	0.00	0.00	-712.57	-598.81	-0.00
Dead+Wind 0 deg - No Ice	53151.36	230.38	-36335.05	-4462772.09	-34288.58	1910.03
Dead+Wind 30 deg - No Ice	53151.36	18388.28	-31537.02	-3873035.07	-2263502.74	2629.11
Dead+Wind 60 deg - No Ice	53151.36	31573.87	-18328.38	-2253075.22	-3882561.05	2517.37
Dead+Wind 90 deg - No Ice	53151.36	36333.10	-246.35	-34089.33	-4468109.01	1720.90
Dead+Wind 120 deg - No Ice	53151.36	31394.42	17943.63	2200224.36	-3861987.08	579.17
Dead+Wind 150 deg - No Ice	53151.36	18054.19	31393.34	3852890.47	-2219431.32	-711.98
Dead+Wind 180 deg - No Ice	53151.36	-272.09	36376.99	4466008.94	39589.59	-1718.42
Dead+Wind 210 deg - No Ice	53151.36	-18354.94	31557.65	3875984.65	2260940.18	-2566.54
Dead+Wind 240 deg - No Ice	53151.36	-31527.18	18286.29	2249562.04	3878865.56	-2488.36
Dead+Wind 270 deg - No Ice	53151.36	-36359.64	182.71	28258.24	4470961.07	-1759.91
Dead+Wind 300 deg - No Ice	53151.36	-31479.04	-17959.44	-2199563.67	3869056.90	-799.71
Dead+Wind 330 deg - No Ice	53151.36	-18038.05	-31431.92	-3859182.78	2211688.06	688.61
Dead+Ice+Temp	64424.89	0.00	0.00	-1381.36	-1173.21	0.02
Dead+Wind 0 deg+Ice+Temp	64424.89	174.24	-31949.41	-3985611.17	-27189.53	1836.21
Dead+Wind 30 deg+Ice+Temp	64424.89	16147.55	-27719.92	-3457656.51	-2018742.32	2301.66
Dead+Wind 60 deg+Ice+Temp	64424.89	27757.36	-16094.80	-2009604.46	-3466566.76	2045.35
Dead+Wind 90 deg+Ice+Temp	64424.89	31956.78	-187.51	-27134.38	-3991288.24	1232.88
Dead+Wind 120 deg+Ice+Temp	64424.89	27623.29	15803.89	1967460.87	-3451300.84	186.54
Dead+Wind 150 deg+Ice+Temp	64424.89	15897.33	27615.36	3441135.22	-1985466.65	-904.78
Dead+Wind 180 deg+Ice+Temp	64424.89	-207.34	31983.35	3986615.93	29943.10	-1682.08



1600 Osgood Street Bldg. 20N Suite 309 North Andover, MA 01845 Phone: (978) 557-5553 FAX: (978) 226-5586

	Јоь CT43XC827 MANCHEST	ER POLICE TOWER 10 of 11
)	Project 183 ft Mono	pole Date 10:42:00 04/10/15
	Client SPRINT	Designed by kw

Load	Vertical	$Shear_x$	$Shear_z$	Overturning	Overturning	Torque
Combination				Moment, $M_x$	Moment, $M_z$	
	lb	lb	lb	lb-ft	lb-ft	lb-ft
Dead+Wind 210 deg+Ice+Temp	64424.89	-16119.69	27736.06	3458353.11	2015018.76	-2251.13
Dead+Wind 240 deg+Ice+Temp	64424.89	-27718.53	16060.07	2004967.41	3461885.44	-2022.15
Dead+Wind 270 deg+Ice+Temp	64424.89	-31977.47	135.40	20604.79	3991995.62	-1264.51
Dead+Wind 300 deg+Ice+Temp	64424.89	-27691.59	-15817.42	-1968657.64	3455532.27	-363.81
Dead+Wind 330 deg+Ice+Temp	64424.89	-15884.89	-27646.37	-3447935.92	1977617.07	886.02
Dead+Wind 0 deg - Service	53151.36	89.99	-14193.39	-1747132.40	-13831.51	758.25
Dead+Wind 30 deg - Service	53151.36	7182.92	-12319.15	-1516360.03	-886360.89	1044.07
Dead+Wind 60 deg - Service	53151.36	12333.54	-7159.52	-882300.82	-1520074.01	1000.61
Dead+Wind 90 deg - Service	53151.36	14192.63	-96.23	-13775.53	-1749206.21	685.32
Dead+Wind 120 deg - Service	53151.36	12263.45	7009.23	860712.75	-1511958.70	232.22
Dead+Wind 150 deg - Service	53151.36	7052.42	12263.02	1507548.20	-869075.21	-280.74
Dead+Wind 180 deg - Service	53151.36	-106.29	14209.77	1747524.57	15088.27	-680.98
Dead+Wind 210 deg - Service	53151.36	-7169.90	12327.21	1516648.37	884538.06	-1019.32
Dead+Wind 240 deg - Service	53151.36	-12315.30	7143.08	880061.04	1517807.68	-990.35
Dead+Wind 270 deg - Service	53151.36	-14202.99	71.37	10629.52	1749545.12	-701.97
Dead+Wind 300 deg - Service	53151.36	-12296.50	-7015.41	-861330.02	1513928.68	-319.70
Dead+Wind 330 deg - Service	53151.36	-7046.12	-12278.09	-1510894.32	865233.37	272.72

## **Solution Summary**

	Sur	n of Applied Force.	s		Sum of Reaction	is	
Load	PX	PY	PZ	PX	PY	PZ	% Error
Comb.	lb	lb	lb	lb	lb	lb	
1	0.00	-53151.36	0.00	0.00	53151.36	0.00	0.000%
2	230.38	-53151.36	-36335.05	-230.38	53151.36	36335.05	0.000%
3	18388.28	-53151.36	-31537.02	-18388.28	53151.36	31537.02	0.000%
4	31573.87	-53151.36	-18328.38	-31573.87	53151.36	18328.38	0.000%
5	36333.10	-53151.36	-246.35	-36333.10	53151.36	246.35	0.000%
6	31394.42	-53151.36	17943.63	-31394.42	53151.36	-17943.63	0.000%
7	18054.19	-53151.36	31393.34	-18054.19	53151.36	-31393.34	0.000%
8	-272.09	-53151.36	36376.98	272.09	53151.36	-36376.99	0.000%
9	-18354.94	-53151.36	31557.65	18354.94	53151.36	-31557.65	0.000%
10	-31527.18	-53151.36	18286.29	31527.18	53151.36	-18286.29	0.000%
11	-36359.64	-53151.36	182.71	36359.64	53151.36	-182.71	0.000%
12	-31479.04	-53151.36	-17959.44	31479.04	53151.36	17959.44	0.000%
13	-18038.05	-53151.36	-31431.92	18038.05	53151.36	31431.92	0.000%
14	0.00	-64424.89	0.00	-0.00	64424.89	-0.00	0.000%
15	174.24	-64424.89	-31949.28	-174.24	64424.89	31949.41	0.000%
16	16147.55	-64424.89	-27719.91	-16147.55	64424.89	27719.92	0.000%
17	27757.35	-64424.89	-16094.80	-27757.36	64424.89	16094.80	0.000%
18	31956.65	-64424.89	-187.51	-31956.78	64424.89	187.51	0.000%
19	27623.28	-64424.89	15803.88	-27623.29	64424.89	-15803.89	0.000%
20	15897.33	-64424.89	27615.35	-15897.33	64424.89	-27615.36	0.000%
21	-207.33	-64424.89	31983.22	207.34	64424.89	-31983.35	0.000%
22	-16119.68	-64424.89	27736.05	16119.69	64424.89	-27736.06	0.000%
23	-27718.52	-64424.89	16060.07	27718.53	64424.89	-16060.07	0.000%
24	-31977.34	-64424.89	135.40	31977.47	64424.89	-135.40	0.000%
25	-27691.58	-64424.89	-15817.42	27691.59	64424.89	15817.42	0.000%
26	-15884.89	-64424.89	-27646.36	15884.89	64424.89	27646.37	0.000%
27	89.99	-53151.36	-14193.38	-89.99	53151.36	14193.39	0.000%
28	7182.92	-53151.36	-12319.15	-7182.92	53151.36	12319.15	0.000%
29	12333.54	-53151.36	-7159.52	-12333.54	53151.36	7159.52	0.000%
30	14192.62	-53151.36	-96.23	-14192.63	53151.36	96.23	0.000%
31	12263.44	-53151.36	7009.23	-12263.45	53151.36	-7009.23	0.000%
32	7052.42	-53151.36	12263.02	-7052.42	53151.36	-12263.02	0.000%
33	-106.29	-53151.36	14209.76	106.29	53151.36	-14209.77	0.000%
34	-7169.90	-53151.36	12327.21	7169.90	53151.36	-12327.21	0.000%



## Hudson Design Group LLC

1600 Osgood Street Bldg. 20N Suite 3090 North Andover, MA 01845 Phone: (978) 557-5553 FAX: (978) 226-5586

	Job		Page	
		CT43XC827	11 of 11	
	Project	t		Date
)			183 ft Monopole	10:42:00 04/10/15
	Client		ODDINIT	Designed by
	SP		SPRINT	kw

	Sun	n of Applied Force:	S				
Load	PX	PY	PZ	PX	PY	PZ	% Error
Comb.	lb	lb	lb	lb	lb	lb	
35	-12315.30	-53151.36	7143.08	12315.30	53151.36	-7143.08	0.000%
36	-14202.98	-53151.36	71.37	14202.99	53151.36	-71.37	0.000%
37	-12296.50	-53151.36	-7015.41	12296.50	53151.36	7015.41	0.000%
38	-7046.11	-53151.36	-12278.09	7046.12	53151.36	12278.09	0.000%

## **Maximum Tower Deflections - Service Wind**

Section	Elevation	Horz.	Gov.	Tilt	Twist
No.		Deflection	Load		
	ft	in	Comb.	0	0
L1	184 - 166.5	64.4825	29	3.1068	0.0194
L2	169.5 - 133.08	55.1277	29	3.0467	0.0119
L3	136.91 - 87.99	35.3750	29	2.6317	0.0059
L4	92.99 - 43.91	15.3054	29	1.6497	0.0022
L5	50.08 - 1	4.1874	29	0.7943	0.0008

## **Critical Deflections and Radius of Curvature - Service Wind**

Elevation	Appurtenance	Gov.	Deflection	Tilt	Twist	Radius of
		Load				Curvature
ft		Comb.	in	۰	۰	ft
184.00	Lightning Rod 2"x21'	29	64.4825	3.1068	0.0198	33076
163.00	PiROD 13' Low Profile Platform	29	50.9912	2.9974	0.0098	7086
153.00	PiROD 13' Low Profile Platform	29	44.7739	2.8875	0.0076	4474
151.00	RRH 8x20-25	29	43.5593	2.8608	0.0073	4165
150.00	Andrew VHLP2-11	29	42.9562	2.8468	0.0072	4026
143.00	PiROD 13' Low Profile Platform	29	38.8240	2.7392	0.0065	3261
123.00	PiROD 13' Low Profile Platform	29	28.0913	2.3455	0.0047	2730
110.00	PiROD 13' Low Profile Platform	29	22.0546	2.0467	0.0035	2675
54.00	1' Side Mount Standoff	29	4.8516	0.8642	0.0008	2614
38.90	Andrew VHLPX2-18-2WH/B	29	2.6588	0.6023	0.0006	3384

## **Section Capacity Table**

Section	Elevation	Component	Size	Critical	P	$SF*P_{allow}$	%	Pass
No.	ft	Type		Element	lb	lb	Capacity	Fail
L1	184 - 166.5	Pole	TP19.399x15.5x0.1875	1	-2483.51	573700.52	13.8	Pass
L2	166.5 - 133.08	Pole	TP26.401x18.3556x0.25	2	-11157.40	1043870.92	66.1	Pass
L3	133.08 - 87.99	Pole	TP35.892x25.0549x0.375	3	-22507.20	2129160.82	95.7	Pass
L4	87.99 - 43.91	Pole	TP44.903x34.0344x0.485	4	-34750.40	3445351.64	92.2	Pass
L5	43.91 - 1	Pole	TP53.5x42.5667x0.54	5	-48220.20	4449967.05	88.9	Pass
							Summary	
						Pole (L3)	95.7	Pass
						Base Plate	84.3	Pass
						RATING =	95.7	Pass

CCIFTS 1.1.103.14128 - Phase 1 Date: 4/9/2015

BU:	CT43XC827	
Site Name:		
App Number:	N/A	
Work Order:		<u> </u>

### **Monopole Drilled Pier**

## <u>Input</u> Criteria TIA Revision:

ACI 318 Revision: 2002 Seismic Category: В

Compression

53 kips Shear 37 kips 4489 k-ft Moment 0 kips Swelling Force

**Foundation Dimensions** 


Pier Diameter: 7 ft Ext. above grade: 1 ft Depth below grade: 31 ft

**Material Properties** 

Number of Rebar: 27 Rebar Size: 11 Tie Size 5 Rebar tensile strength: 60 ksi Concrete Strength: 4000 psi Ultimate Concrete Strain 0.003 in/in Clear Cover to Ties: 3 in

Soil Profile:

Profile 1



						Friction	Ultimate Uplift Skin	Ultimate Comp. Skin	Ultimate Bearing	
	Thickness	From	То	Unit Weight	Cohesion	Angle	Friction	Friction	Capacity	SPT 'N'
Layer	(ft)	(ft)	(ft)	(pcf)	(psf)	(deg)	(ksf)	(ksf)	(ksf)	Counts
1	3.5	0	3.5	100	0	0	0	0		
2	2.5	3.5	6	100	0	30				
3	10	6	16	37.6	0	30				
4	15	16	31	37.6	0	30				

## **Analysis Results**

Soil Lateral Capacity

5.94 ft Depth to Zero Shear: Max Moment, Mu: 4685.58 k-ft Soil Safety Factor: 2.22 Safety Factor Req'd: RATING: 90.0%

Soil Axial Capacity

Skin Friction (k): 106.41 kips End Bearing (k): 0.00 kips Comp. Capacity (k), φCn: 106.41 kips 68.90 kips Comp. (k), Cu: RATING: 64.7%

Concrete/Steel Check Mu (from soil analysis)

Dev. Length provided

 $\varphi \mathsf{Mn}$ 6753.53 k-ft RATING: 90.2% rho provided 0.76 0.33 OK rho required **Rebar Spacing** 7.36 Spacing required 22.56 OK Dev. Length required 24.81

6091.26 k-ft

53.51 OK

**Overall Foundation Rating:** 90.2%



# RADIO FREQUENCY FCC REGULATORY COMPLIANCE MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

**Sprint Existing Facility** 

Site ID: CT43XC827

Manchester Police Tower

239 Middle Turnpike Manchester, CT 06040

June 24, 2014

EBI Project Number: 62143492

21 B Street Burlington, MA 01803 Tel: (781) 273.2500 Fax: (781) 273.3311



June 24, 2014

Sprint Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:

CT43XC827 - Manchester Police Tower

Site Total: <u>55.49%</u> - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 239 Middle Turnpike, Manchester, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu$ W/cm2). The number of  $\mu$ W/cm2 calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu$ W/cm<sup>2</sup>). The general population exposure limit for the cellular band (850 MHz Band) is approximately 567  $\mu$ W/cm<sup>2</sup>, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is 1000  $\mu$ W/cm<sup>2</sup>. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 239 Middle Turnpike, Manchester, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 7 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.



- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **153 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

	Site ID	CT43XC827	- Manchester F	olice Tower												
	Site Addresss	239 Middle Tu	rnpike, Manche	ster, CT, 06040												
	Site Type		Monopole													
							Sector 1									
						Power										
						Out Per			Antenna Gain							Power
Antenna						Channel	Number of	Composite	(10 db	Antenna	analysis		Cable Loss	Additional		Density
Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power	reduction)	Height (ft)	height	Cable Size		Loss (dB)	ERP	Percentage
1a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	7	140	5.9	153	147	1/2 "	0.5	0	485.43	0.81%
1a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	153	147	1/2 "	0.5	0	39.00	0.11%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	153	147	1/2 "	0.5	0	138.69	0.41%
												Sector to	otal Power D	Density Value:	1.33%	
	Sector 2															
	1		1		l											1
						Power										
						Out Per			Antenna Gain							Power
Antenna						Channel	Number of	Composite	(10 db	Antenna	analysis		Cable Loss			Density
Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power	reduction)	Height (ft)	height	Cable Size	, ,	Loss (dB)	ERP	Percentage
2a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	7	140	5.9	153	147	1/2 "	0.5	0	485.43	0.81%
2a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	153	147	1/2 "	0.5	0	39.00	0.11%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	153	147	1/2 "	0.5	0	138.69	0.41%
												Sector to	otal Power L	Density Value:	1.33%	
							Sector 3									
										,			,			
						Dowe-										
						Power Out Per			Antenna Gain							Power
Antenna						Channel	Number of	Composite	(10 db	Antenna	analysis		Cable Loss	Additional		Density
Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	(Watts)	Channels	Power	reduction)	Height (ft)	height	Cable Size		Loss (dB)	ERP	Percentage
3a	RFS	APXVSPP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	7	140	5.9	153	147	1/2 "	0.5	0	485.43	0.81%
3a	RFS	APXVSPP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	153	147	1/2 "	0.5	0	39.00	0.11%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	153	147	1/2 "	0.5	0	138.69	0.41%
														Density Value:	1.33%	

Site Composite MPE %								
Carrier	MPE %							
Sprint	3.99%							
Town MFRE	0.96%							
Town MPD - ch 1	0.13%							
Town MPD - ch 2	0.15%							
Town MFD	0.26%							
Town services intercity	0.49%							
RAFS I/2	1.65%							
Town public works	0.73%							
Town Services EOC	0.73%							
Town FD	0.73%							
town SP hotline	0.97%							
Town Vol FD	0.56%							
Town Service - School	0.16%							
Htfd City FD	0.73%							
Tolland MUT	0.73%							
Sprint/Nextel iDEN	3.25%							
Clearwire	0.81%							
MetroPCS	4.02%							
T-Mobile	0.13%							
Verizon Wireless	16.80%							
AT&T	17.51%							
Total Site MPE %	55.49%							



## **Summary**

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are 3.99% (1.33% from sector 1, 1.33% from sector 2 and 1.33% from sector 3) of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **55.49**% of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan

RF Engineering Director

**EBI Consulting** 

21 B Street

Burlington, MA 01803