

Northeast Site Solutions Denise Sabo 4 Angela's Way, Burlington CT 06013 203-435-3640 denise@northeastsitesolutions.com

September 3, 2021

Members of the Siting Council Connecticut Siting Council Ten Franklin Square New Britain, CT 06051

RE: Tower Share Application 53 Slater Street, Manchester CT 06045 Latitude: 41.8050000 Longitude: -72.533611 Site# 876347\_Crown\_Dish

#### Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 53 Slater Street in Manchester, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900 5G MHz antenna and six (6) RRUs, at the 123-foot level of the existing 155-foot monopole tower, one (1) Fiber cables will also be installed. Dish Wireless LLC equipment cabinets will be placed within 7x5 lease area. Included are plans by Infinigy, dated August 13, 2021 Exhibit C. Also included is a structural analysis prepared by Crown Castle, dated May 29, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. This facility was approved by the Town of Manchester Planning and Zoning Commission on October 29, 1998. Please see attached Exhibit A.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to The Honorable Jay Moran, Mayor for the Town of Manchester Gary Anderson, Director of Planning, as well as the tower owner (Crown Castle) and property owner (One Hundred Twenty-One Connecticut Ave Assoc LLC)

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

- 1. The proposed modification will not result in an increase in the height of the existing structure. The top of the tower is 155-feet; Dish Wireless LLC proposed antennas will be located at a center line height of 123-feet.
- 2. The proposed modifications will not result in the increase of the site boundary as depicted on the attached site plan.



- 3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligent.
- 4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. As indicated in the attached power density calculations, the combined site operations will result in a total power density of 14.10% as evidenced by Exhibit F.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully indicates that the shared use of this facility satisfies these criteria.

- A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit D.
- B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this support tower in Manchester. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.
- C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 123-foot level of the existing 155-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.
- D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.
- E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing guyed tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Manchester.

Sincerely,

#### Denise Sabo

Denise Sabo

Mobile: 203-435-3640 Fax: 413-521-0558

Office: 4 Angela's Way, Burlington CT 06013 Email: denise@northeastsitesolutions.com



Attachments cc: The Honorable Jay Moran, Mayor Town of Manchester 41 Center Street Manchester, CT 06045

Steve Stephanou-Deputy General Manager Town of Manchester 41 Center Street Manchester, CT 06045

Gary Anderson, Director of Planning Town of Manchester – Planning and Zoning 494 Main Street Lincoln Center, 2nd FL Manchester, CT 06045

One Hundred Twenty-One Connecticut Ave Assoc LLC - Property Owner 9 Lake Lane, Ellington CT 06029

Crown Castle - Tower Owner

# Exhibit A

**Original Facility Approval** 

### VOL 2013 PG 259

# TOWN OF MANCHESTER PLANNING AND ZONING COMMISSION



### CERTIFICATE OF APPROVAL OF SPECIAL EXCEPTION

Owner of record:	Raglin Associates, c/o Sullivan Tile Dist.		
Property Address:	53 Slater Street		
Applicant:	Sprint Spectrum LP		
Regulation(s) cited	Article IV, Section 19.05	<u> </u>	

#### SPECIAL EXCEPTION GRANTED:

with modifications and the condition that a caveat addressing co-location requirements be submitted for staff review and filed on the land records by the applicant prior to any construction.

- \* ALL SITE WORK APPROVED BY THIS SPECIAL EXCEPTION MUST BE COMPLETED BY AUGUST 17, 2003 (5 yrs. From approval date). FAILURE TO COMPLETE ALL WORK WITHIN THE SPECIFIED TIME PERIOD WILL RESULT IN AUTOMATIC EXPIRATION OF THE APPROVAL.
- \* THIS CERTIFICATE MUST BE RECORDED IN THE LAND RECORDS IN THE OFFICE OF THE TOWN CLERK BEFORE THE SPECIAL EXCEPTION IS LAWFULLY EFFECTIVE.

CERTIFIED:

\*DATE ADOPTED: August 17, 1998

FILE NO. S-147

Frank Caversa
Secretary

Secretary

Planning and Zoning Commission

Received for Record on

SEP 11 1998 at 2:43 PM

Joseph V. Camposeo, Town Clerk

\_6. 1998 3:17PM

PROVAL SIGNATURE

### SPRINT POS TOWN OF MANCHESTER 41 CENTER STREET - P.O. BOX 191 MANCHESTER, CT 06045-0191

CONING PERMIT	(860) 647-3052	FAX: (860) 64	7-3144	
ERTIFICATION OF ZONING	COMPLIANCE REC	UEST		
ERMIT/APPLICATION NBR: ERMIT TYPE: ZONE	99 00000638	's#	DATE APPLIED: PREPARED BY: DATE ISSUED:	PAT21
ROPERTY ADDRESS: 3 SLATER STREET			LEGAL DÉSCRIPI	CION:
ENANT: THER NAME/ADDRESS:			CONTRACTOR NAM	ie/address:
AGLIN ASSOCIATES O SULLIVAN TILE DIST RAILROAD AVE UST HAVEN CT	06516			
HER: RINT PCS	The state of the s	500		Section 2015 17 (1997) 1997 (1997)
LUATION: CUPANCY TYPE: mensions of structure SCRIPTION OF OTHER BU VDITIONS:	: 150'	Plan	s for building:	
OTNL APPROVAL:		ADDINL P	ERMITS:	
: ^			· · · · · · · · · · · · · · · · · · ·	·
	ITE DEVELOPMENT ND EQUIPMENT CA Y PZC ON 8/17/9	BINETS TO		
= n	•	-	•	
				in government of the second of
<del>=</del> )-				
nt				
IS IS TO CERTIFY TH	AT THE ABOVE ST	PATED INFO	RMATION IS A PE	RMITTED AND

ORIGINAL

INNECTICUT, UPON AUTHORIZED SIGNATURE OF THE ZONING ENFORCEMENT OFFICER.

# Exhibit B

**Property Card** 

#### **53 SLATER STREET**

**Location** 53 SLATER STREET **Mblu** 56/ 5140/ 53/ /

Acct# 514000053 Owner ONE HUNDRED TWENTY ONE

CONN-

**Assessment** \$1,690,200 **Appraisal** \$2,414,500

PID 14616 Building Count 4

#### **Current Value**

Appraisal				
Valuation Year	Improvements	Land	Total	
2011	\$1,689,400	\$725,100	\$2,414,500	
Assessment				
Valuation Year	Improvements	Land	Total	
2011	\$1,182,600	\$507,600	\$1,690,200	

#### **Owner of Record**

**Owner** ONE HUNDRED TWENTY ONE CONN- **Sale Price** \$1,180,000

ECTICUT AVENUE ASSOCIATES LLC Certificate

 Address
 9 LAKE LANE
 Book & Page
 2683/ 224

 ELLINGTON, CT 06029
 Sale Date
 07/17/2003

Instrument 33

#### **Ownership History**

Ownership History					
Owner	Sale Price	Certificate	Book & Page	Instrument	Sale Date
ONE HUNDRED TWENTY ONE CONN-	\$1,180,000	С	2683/ 224	33	07/17/2003
RAGLIN ASSOCIATES LLC	\$0		2132/ 338		12/02/1999

#### **Building Information**

#### Building 1 : Section 1

 Year Built:
 1987

 Living Area:
 6333

 Replacement Cost:
 \$474,167

Replacement Cost

**Less Depreciation:** \$265,500

<b>Building Attributes</b>		
Field	Description	
STYLE	Service Shop	
MODEL	Ind/Comm	


#### **Building Photo**

Grade	Average
Stories:	1
Occupancy	4
Exterior Wall 1	Pre-finsh Metl
Exterior Wall 2	Brick Veneer
Roof Structure	Gable/Hip
Roof Cover	Enam Mtl Shing
Interior Wall 1	Wall Brd/Wood
Interior Wall 2	Minim/Masonry
Interior Floor 1	Concr-Finished
Interior Floor 2	
Heating Fuel	Gas
Heating Type	Forced Air-Duc
AC Type	Partial
Bldg Use	Industrial 96
Total Rooms	
Total Bedrms	00
Total Baths	0
1st Floor Use:	300
Heat/AC	Heat/AC Packag
Frame Type	Steel
Baths/Plumbing	Average
Ceiling/Wall	Ceil & Min WI
Rooms/Prtns	Average
Wall Height	14
% Comn Wall	0



(http://images.vgsi.com/photos/ManchesterCTPhotos/ $\00\03\43/03.jpg$ )

#### **Building Layout**



Building Sub-Areas (sq ft) <u>Le</u>			
Code	Description	Gross Area	Living Area
BAS	First Floor	5219	5219
AOF	Office, (Average)	1114	1114
WDK	Wood Deck	142	0
		6475	6333

**Building 2 : Section 1** 

 Year Built:
 1987

 Living Area:
 24306

 Replacement Cost:
 \$1,082,175

**Replacement Cost** 

**Less Depreciation:** \$606,000

<b>Building Attributes: Bldg 2 of 4</b>		
Field	Description	
STYLE	Pre-Eng Garage	
MODEL	Ind/Comm	
Grade	Average	
Stories:	1	
Occupancy	4	
Exterior Wall 1	Pre-finsh Metl	


#### **Building Photo**

Exterior Wall 2	Brick Veneer
Roof Structure	Gable/Hip
Roof Cover	Enam Mtl Shing
Interior Wall 1	Minim/Masonry
Interior Wall 2	
Interior Floor 1	Concr-Finished
Interior Floor 2	
Heating Fuel	Gas
Heating Type	Forced Air-Duc
AC Type	Partial
Bldg Use	Industrial 96
Total Rooms	
Total Bedrms	00
Total Baths	0
1st Floor Use:	300
Heat/AC	Heat AC Split
Frame Type	Steel
Baths/Plumbing	Average
Ceiling/Wall	Susp Ceil & WI
Rooms/Prtns	Average
Wall Height	22
% Comn Wall	0



(http://images.vgsi.com/photos/ManchesterCTPhotos/ $\00\03\43/04.jpg$ )

#### **Building Layout**



Building Sub-Areas (sq ft)			<u>Legend</u>
Code	Description	Gross Area	Living Area
BAS	First Floor	18510	18510
AOF	Office, (Average)	5796	5796
		24306	24306

#### **Building 3: Section 1**

 Year Built:
 1987

 Living Area:
 10320

 Replacement Cost:
 \$433,337

Replacement Cost

**Less Depreciation:** \$242,700

Building Attributes : Bldg 3 of 4		
Field	Description	
STYLE	Pre-Eng Garage	
MODEL	Ind/Comm	
Grade	Average	
Stories:	1	
Occupancy	12	
Exterior Wall 1	Pre-finsh Metl	
Exterior Wall 2	Brick Veneer	

#### **Building Photo**



 $\label{lem:mages.vgsi.com/photos/ManchesterCTPhotos/} $$ \left(\frac{3}{305.jpg}\right) $$$ 

Roof Structure	Gable/Hip
Roof Cover	Enam Mtl Shing
Interior Wall 1	Minim/Masonry
Interior Wall 2	
Interior Floor 1	Concr-Finished
Interior Floor 2	
Heating Fuel	Electric
Heating Type	Hot Air-no Duc
AC Type	None
Bldg Use	Industrial 96
Total Rooms	
Total Bedrms	00
Total Baths	0
1st Floor Use:	300
Heat/AC	None
Frame Type	Steel
Baths/Plumbing	Average
Ceiling/Wall	Ceil & Min WI
Rooms/Prtns	Average
Wall Height	18
% Comn Wall	0

#### **Building Layout**



	Building Sub-Areas (sq ft)		
Code	Description	Gross Area	Living Area
BAS	First Floor	10320	10320
		10320	10320

#### **Building 4 : Section 1**

 Year Built:
 2008

 Living Area:
 12000

 Replacement Cost:
 \$479,640

**Replacement Cost** 

**Less Depreciation:** \$465,300

Building Attributes : Bldg 4 of 4			
Field	Description		
STYLE	Pre-Eng Garage		
MODEL	Ind/Comm		
Grade	Average		
Stories:	1		
Occupancy	8		
Exterior Wall 1	Pre-finsh Metl		
Exterior Wall 2	Concr/Cinder		
Roof Structure	Gable/Hip		
Roof Cover	Enam Mtl Shing		
Interior Wall 1	Minim/Masonry		
Interior Wall 2			
Interior Floor 1	Concr-Finished		
Interior Floor 2			
Heating Fuel	Gas		

#### **Building Photo**



(http://images.vgsi.com/photos/ManchesterCTPhotos/ $\00\$  \43/06.jpg)

#### **Building Layout**

Heating Type	Hot Air-no Duc
AC Type	None
Bldg Use	Industrial 96
Total Rooms	00
Total Bedrms	00
Total Baths	0
1st Floor Use:	
Heat/AC	None
Frame Type	Steel
Baths/Plumbing	Average
Ceiling/Wall	Ceil & Min WI
Rooms/Prtns	Average
Wall Height	18
% Comn Wall	0



Building Sub-Areas (sq ft)			<u>Legend</u>
Code	ode Description		Living Area
BAS	First Floor	12000	12000
		12000	12000

#### **Extra Features**

Extra Features <u>Lege</u>				
Code	Description	Size	Value	Bldg #
A/C	Partial AC	5796 S.F.	\$6,500	2

#### Land

Land Use Land Line Valuation		tion	
Use Code	300	Size (Acres)	4.96
Description	Industrial 96	Frontage	0
Zone	IND	Depth	0
Neighborhood	5000	Assessed Value	\$507,600
Alt Land Appr	No	Appraised Value	\$725,100
Category			

#### Outbuildings

	Outbuildings <u>L</u>					Legend
Code	Description	Sub Code	Sub Description	Size	Value	Bldg #
PAV1	Paving Asphalt			13350 S.F.	\$19,200	4
PAV1	Paving Asphalt			37000 S.F.	\$17,800	1
FN3	Fence 6' Chain			300 L.F.	\$2,000	1
PAV2	Paving Concrete			96 S.F.	\$300	4
SHDT	Telephone Shed			319 S.F.	\$31,600	1
FN4	Fence 8' Chain			54 L.F.	\$900	1
SHDT	Telephone Shed			319 S.F.	\$31,600	1


#### **Valuation History**

_	
	Annualizati
	Appraisai

Valuation Year	Improvements	Land	Total
2010	\$1,766,600	\$760,300	\$2,526,900
2005	\$871,200	\$540,700	\$1,411,900
2000	\$1,082,500	\$540,700	\$1,623,200

Assessment					
Valuation Year	Improvements	Land	Total		
2010	\$1,236,700	\$532,300	\$1,769,000		
2005	\$609,900	\$378,500	\$988,400		
2000	\$757,800	\$378,500	\$1,136,300		

(c) 2014 Vision Government Solutions, Inc. All rights reserved.



# Exhibit C

**Construction Drawings** 

# O E S N wireless...

DISH Wireless L.L.C. SITE ID:

### BOBDL00092A

DISH Wireless L.L.C. SITE ADDRESS:

## **53 SLATER STREET MANCHESTER, CT 06040**

#### CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE BUILDING

2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS MECHANICAL ELECTRICAL 2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS 2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

	SHEET INDEX
SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

#### SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIPMENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

- TOWER SCOPE OF WORK:

  INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)

  INSTALL (1) PROPOSED ANTENNA PLATFORM MOUNT

  INSTALL PROPOSED JUMPERS

- INSTALL (6) PROPOSED RRUS (2 PER SECTOR)
  INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
- INSTALL (1) PROPOSED HYBRID CABLE

- GROUND SCOPE OF WORK:
   INSTALL (1) PROPOSED METAL PLATFORM
- EXISTING (1) ICE BRIDGE TO BE UTILIZED INSTALL (1) PROPOSED PPC CABINET
- INSTALL (1) PROPOSED EQUIPMENT CABINET
- INSTALL (1) PROPOSED POWER CONDUIT INSTALL (1) PROPOSED TELCO CONDUIT
- PROPOSED TELCO-FIBER BOX
- INSTALL (1) PROPOSED GPS UNIT
- INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
- INSTALL (1) PROPOSED CIENA BOX (IF REQUIRED)
  EXISTING METER SOCKET ON EXISTING H-FRAME TO BE UTILIZED

#### SITE PHOTO





**UNDERGROUND SERVICE ALERT CBYD 811** UTILITY NOTIFICATION CENTER OF CONNECTICUT (800) 922-4455 WWW.CBYD.COM

CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION

811

### **GENERAL NOTES**

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

#### 11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED


CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCFEDING WITH THE WORK.

SITE INFORMATION		PROJECT DIRECTORY	
PROPERTY OWNER: ADDRESS:	TBD TBD	APPLICANT:	DISH Wireless L.L.C. 5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120
TOWER TYPE:	MONOPOLE	TOWER OWNER:	CROWN CASTLE
TOWER CO SITE ID:	876347	TOWER OWNER.	2000 CORPORATE DRIVE CANONSBURG, PA 15317
TOWER APP NUMBER:	556605		(877) 486–9377
COUNTY:	HARTFORD	SITE DESIGNER:	INFINIGY 2500 W. HIGGINS RD. STE. 500
LATITUDE (NAD 83):	41° 48′ 18.00″ N 41.805000 N		HOFFMAN ESTATES, IL 60169 (847) 648–4068
LONGITUDE (NAD 83):			(047) 040 4000
ZONING JURISDICTION:	CONNECTICUT SITING COUNCIL	SITE ACQUISITION	I: NICHOLAS CURRY NICHOLAS.CURRY@CROWNCASTLE.COM
ZONING DISTRICT:	TBD	CONSTRUCTION IN	AANAGER: JAVIER SOTO
PARCEL NUMBER:	TBD	CONSTRUCTION	JAVIER.SOTO@DISH.COM
OCCUPANCY GROUP:	U	RF ENGINEER:	BOSSENER CHARLES BOSSEMER.CHARLES@DISH.COM
CONSTRUCTION TYPE:	V-B		DUSSEMER.CHARLES@DISH.CUM
POWER COMPANY:	TBD		
TELEPHONE COMPANY:	TBD		

#### **DIRECTIONS**

#### DIRECTIONS FROM TOURS OF DISTINCTION AIRPORT:

DEPART AND HEAD TOWARD MASSACO ST, TURN RIGHT ONTO MASSACO ST, TURN RIGHT ONTO US-202 W / CT-10 / HOPMEADOW ST, TURN LEFT ONTO CT-185 / HARTFORD RD, TURN LEFT ONTO CT-178 / LOEFFLER RD, BEAR RIGHT ONTO GABB RD, TURN RIGHT ONTO CT-189 / BLOOMFIELD AVE, TURN LEFT ONTO CT-218 / COTTAGE GROVE RD, PASS MCDONALD'S ON THE RIGHT IN, TAKE THE RAMP ON THE RIGHT FOR I-291 EAST AND HEAD TOWARD SOUTH WINDSOR, MINOR CONGESTION AT EXIT 5, HEAD ON THE RAMP RIGHT AND FOLLOW SIGNS FOR TOLLAND TURNPIKE, TURN LEFT ONTO TOLLAND TPKE, TURN LEFT TO STAY ON TOLLAND TPKE, TURN LEFT ONTO SLATER ST, TURN RIGHT, ARRIVE AT 53 SLATER STREET MANCHESTER, CT 06040






5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



2000 CORPORATE DRIVE CANONSBURG PA 15317

# INFINIGY 8

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, 1L 60169
PHONE: 847-648-4088 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW

RFDS REV #:

#### CONSTRUCTION **DOCUMENTS**

N/A

SUBMITTALS REV DATE DESCRIPTION A 06/14/2020 ISSUED FOR REVIEW 0 08/12/2020 ISSUED FOR CONSTRUCTION A&E PROJECT NUMBER

2039-Z5555C


BOBDL00092A 53 SLATER STREET

MANCHESTER, CT 06040 SHEET TITLE

TITLE SHEET


SHEET NUMBER

T-1





- 1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
- 2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
- 3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.
- 4. INFINIGY HAS NOT EVALUATED THE TOWER OR MOUNT STRUCTURE AND ASSUMES NO RESPONSIBILITY FOR THEIR STRUCTURAL INTEGRITY REGARDING PROPOSED LOADINGS. FINAL INSTALLATION SHALL COMPLY WITH RESULTS OF PASSING STRUCTURAL ANALYSES PERFORMED BY OTHERS.





EXISTING MONOPOLE

- EXISTING ENTRY PORT

BE REUSED BY DISH

PROPOSED DISH Wireless L.L.C. GPS UNIT

PROPOSED DISH Wireless L.L.C. EQUIPMENT ON PROPOSED STEEL PLATFORM



			AN	TENNA				TRANSMISSION CABLE
SECTOR	POSITION	EXISTING OR PROPOSED	MANUFACTURER — MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZIMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA WIRELESS-MX08FR0665-21	5G	72.0" × 20.0"	O.	123'-0"	(1) HIGH-CAPACITY
BETA	B1	PROPOSED	JMA WIRELESS-MX08FR0665-21	5G	72.0" x 20.0"	120°	123'-0"	(1) HIGH—CAPACITY HYBRID CABLE (180' LONG)
GAMMA	G1	PROPOSED	JMA WIRELESS-MX08FR0665-21	5G	72.0" × 20.0"	240°	123'-0"	(100 20110)

		POSITION	RRH		
	SECTOR		MANUFACTURER — MODEL NUMBER	TECHNOLOGY	
	ALPHA	A1	FUJITSU - TA08025-B604	5G	
	ALPHA	A1	FUJITSU - TA08025-B605	5G	
	BETA	B1	FUJITSU - TA08025-B604	5G	
l	DEIA	B1	FUJITSU - TA08025-B605	5G	
	CA1/0/4	G1	FUJITSU - TA08025-B604	5G	
ı	GAMMA	G1	FUJITSU - TA08025-B605	5G	

#### <u>NOTES</u>


1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS.

2" 6" 0

3/4"=1'-0

NO SCALE

 ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.








C CROWN CASTLE

> 2000 CORPORATE DRIVE CANONSBURG, PA 15317

# INFINIGY FROM ZERO TO INFINIGY

the solutions are endless 2500 W. HIGGINS RD. SUITE 500 | HOFFMAN ESTATES, IL 60169 PHONE: 847-648-4088 | FAX: 518-690-0793 WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW
RFDS REV ;	#:	N/A

## CONSTRUCTION DOCUMENTS

L			
Γ			SUBMITTALS
Ī	REV	DATE	DESCRIPTION
Γ	A	06/14/2020	ISSUED FOR REVIEW
Г	0	08/12/2020	ISSUED FOR CONSTRUCTION
Г		۵&F F	PROJECT NUMBER

WE PROJECT NUMBER

2039-Z5555C

DISH Wireless L.L.C. PROJECT INFORMATION


BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

ELEVATION, ANTENNA LAYOUT AND SCHEDULE

SHEET NUMBER


**A-2** 





ANTENNA SCHEDULE


<u>DULE</u>


PROPOSED NORTHEAST ELEVATION











5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



2000 CORPORATE DRIVE CANONSBURG, PA 15317

### INFINIGY8 FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

	ı	2520 251	,,			7.
130		RCD	SS		CJW	
ì	ı	DRAWN BY:	CHECKED	BY:	APPROVED	BY

#### CONSTRUCTION **DOCUMENTS**

		SUBMITTALS
REV	DATE	DESCRIPTION
A	06/14/2020	ISSUED FOR REVIEW
0	08/12/2020	ISSUED FOR CONSTRUCTION
	A&E F	PROJECT NUMBER

2039-Z5555C

DISH Wireless L.L.C. PROJECT INFORMATION


BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

ELECTRICAL/FIBER ROUTE PLAN AND NOTES

SHEET NUMBER

E-1



dësh wireless.

5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



2000 CORPORATE DRIVE CANONSBURG, PA 15317

# INFINIGY FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4086 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED	BY:	APPROVED	BY:
RCD	SS		CJW	
RFDS REV ;	#:		N	/A

# CONSTRUCTION DOCUMENTS

SUBMITTALS

2039-Z5555C

DISH Wireless L.L.C. PROJECT INFORMATION


BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

ELECTRICAL DETAILS

SHEET NUMBER

E-2



**NOTES** 

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(a) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

#12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A #10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A #8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A #6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358. 0.5" CONDUIT - 0.122 SQ. IN AREA

0.75" CONDUIT - 0.213 SQ. IN AREA 2.0" CONDUIT - 1.316 SQ. IN AREA 3.0" CONDUIT - 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.

#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN #10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND = 0.0633 SQ. IN

0.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.

#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN #10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND

= 0.1146 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.

3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN #6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND

NO SCALE

TOTAL = 0.8544 SQ. IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC ONE-LINE DIAGRAM

() ER. (ICE. IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

RFDS REV #

8/13/2021////

DRAWN BY: CHECKED BY: APPROVED BY CJW

5701 SOUTH SANTA FE DRIVE

LITTLETON, CO 80120

2000 CORPORATE DRIVE

CANONSBURG PA 15317

INFINIGY 8

FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, 1L 60169
PHONE: 847-648-4088 | FAX: 518-690-0793
WWW.INFINIGY.COM

OF CONNECTION OF

34916 CENSED.

**CROWN** 

#### CONSTRUCTION **DOCUMENTS**

N/A

	SUBMITTALS						
REV	DATE DESCRIPTION						
A	06/14/2020	ISSUED FOR REVIEW					
0	08/12/2020	20 ISSUED FOR CONSTRUCTION					

A&E PROJECT NUMBER

2039-Z5555C

DISH Wireless L.L.C. PROJECT INFORMATION


BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE


SHEET NUMBER

E-3




PANEL SCHEDULE

2 NOT USED NO SCALE NO SCALE



<u>NOTES</u>

. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



● EXOTHERMIC CONNECTION

■TEST GROUND ROD WITH INSPECTION SLEEVE

#6 AWG STRANDED & INSULAT

▲ BUSS BAR INSULATOR

#### **GROUNDING LEGEND**

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.

MECHANICAL CONNECTION

🖶 GROUND BUS BAR

GROUND ROD

 $(\bullet)$ 

- CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
- 3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

#### **GROUNDING KEY NOTES**

- (A) EXTERIOR GROUND RING: #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- B TOWER GROUND RING: THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- © INTERIOR GROUND RING: #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- D BOND TO INTERIOR GROUND RING: #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- (E) GROUND ROD: UL LISTED COPPER CLAD STEEL. MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- F CELL REFERENCE GROUND BAR: POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (3) HATCH PLATE GROUND BAR: BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) EXTERIOR CABLE ENTRY PORT GROUND BARS: LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING, BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- 1 TELCO GROUND BAR: BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- (K) INTERIOR UNIT BONDS: METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- FENCE AND GATE GROUNDING: METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- M EXTERIOR UNIT BONDS: METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- N ICE BRIDGE SUPPORTS: EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED CROWN BRIDGE LE
- DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIEY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR
- P TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR.

REFER TO DISH Wireless L.L.C. GROUNDING NOTES.

dësh wireless.


5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120

CROWN CASTLE

INFINIGY&
FROM ZERO TO INFINIGY

CANONSBURG PA 15317

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:	
RCD	SS	CJW	
RFDS REV	N/A		

CONSTRUCTION DOCUMENTS

	SUBMITTALS						
REV	DATE	DESCRIPTION					
Α	06/14/2020	ISSUED FOR REVIEW					
٥	08/12/2020	ISSUED FOR CONSTRUCTION					

A&E PROJECT NUMBER

2039-Z5555C

DISH Wireless L.L.C. PROJECT INFORMATION

BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

GROUNDING PLANS AND NOTES

SHEET NUMBER

G-1

TYPICAL ANTENNA GROUNDING PLAN


NO SCALE


12


**GROUNDING KEY NOTES** 


NO SCALE

`












5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120

**CROWN** 

2000 CORPORATE DRIVE CANONSBURG, PA 15317

### INFINIGY 8 FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFAM ESTATES, IL 60169
PHONE: 847-648-4088 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

	DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
	RCE	)	SS		CJW	

RFDS REV #:

#### CONSTRUCTION **DOCUMENTS**

N/A

SUBMITTALS REV DATE DESCRIPTION A 06/14/2020 ISSUED FOR REVIEW 0 08/12/2020 ISSUED FOR CONSTRUCTION A&E PROJECT NUMBER

2039-Z5555C


DISH Wireless L.L.C. PROJECT INFORMATION

BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE CABLE COLOR CODES

SHEET NUMBER

RF-1





5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



2000 CORPORATE DRIVE CANONSBURG, PA 15317

# INFINIGY &

the solutions are encless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-468 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
RCI	)	SS		CJW	

RFDS REV #:

CONSTRUCTION DOCUMENTS

N/A

SUBMITTALS				
REV	DATE	DESCRIPTION		
A	06/14/2020	ISSUED FOR REVIEW		
0	08/12/2020	ISSUED FOR CONSTRUCTION		
	A&F E	PO IECT NUMBER		

A&E PROJECT NUMBER

2039-Z5555C

PROJECT INFORMATION

BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

LEGEND AND ABBREVIATIONS

SHEET NUMBER

#### SITE ACTIVITY REQUIREMENTS:

- 1. NOTICE TO PROCEED NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER CONSTRUCTION MANAGER.
- 2. "LOOK UP" DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:

THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH WIReless L.L.C. AND DISH WIReless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.

- 3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
- 4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH WIFELDS L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
- 5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
- 6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- 7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- 8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- 9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
- 10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- 11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
- 12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
- 13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH WIReless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
- 14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
- 15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
- 16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
- 17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
- 18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
- 19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
- 20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
- 22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

#### **GENERAL NOTES:**

1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:

CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION

CARRIER:DISH Wireless L.L.C.

TOWER OWNER:TOWER OWNER

- 2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- 3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
- 4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD
- 5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
- 6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
- 7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- 8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
- 9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- 10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION
- 11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
- 12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
- 13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



CANONSBURG PA 15317

# INFINIGY FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
RCD	SS	CJW
RFDS REV	#:	N/A

## CONSTRUCTION DOCUMENTS

SUBMITTALS				
REV	DATE	DESCRIPTION		
A	06/14/2020	ISSUED FOR REVIEW		
0	08/12/2020	ISSUED FOR CONSTRUCTION		
A&E PROJECT NUMBER				

2039-Z5555C

DISH Wireless L.L.C. PROJECT INFORMATION

BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

#### CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

- ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
- UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
- ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°F AT TIME OF PLACEMENT.
- CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
- ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:

#4 BARS AND SMALLER 40 ksi

#5 BARS AND LARGER 60 ksi

- THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
- CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
- CONCRETE EXPOSED TO EARTH OR WEATHER:
- #6 BARS AND LARGER 2"
- #5 BARS AND SMALLER 1-1/2"
- · CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
- SLAB AND WALLS 3/4"
- BEAMS AND COLUMNS 1-1/2\*
- A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

#### **ELECTRICAL INSTALLATION NOTES:**

- ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
- CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
- WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
- ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
- EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
- ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
- PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
- TIE WRAPS ARE NOT ALLOWED.
- ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW. THWN. THWN-2. XHHW. XHHW-2. THW. THW-2. RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
- POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW. THWN. THWN-2. XHHW. XHHW-2. THW. THW-2. RHW. OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
- RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
- ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

- ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
- SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
- LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
- CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
- CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
- 21 WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
- 22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
- 23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING, CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
- METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND 27 TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
- THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
- 29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
- ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.




5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



2000 CORPORATE DRIVE CANONSBURG PA 15317

### **INFINIGY8** FROM ZERO TO INFINIGY

the solutions are endless 2500 W. HIGGINS RD. SUITE 500 | HOFFMAN ESTATES, IL 60169 PHONE: 847-648-4068 | FAX: 518-690-0793 WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY
RCD	SS	CJW
RFDS REV #	#:	N/A

#### CONSTRUCTION **DOCUMENTS**

SUBMITTALS			
REV	DATE DESCRIPTION		
A	06/14/2020 ISSUED FOR REVIEW		
0	08/12/2020 ISSUED FOR CONSTRUCTION		
A&E PROJECT NUMBER			

2039-Z5555C

DISH Wireless L.L.C. PROJECT INFORMATION

BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

> SHEET TITLE GENERAL NOTES

> > SHEET NUMBER

#### **GROUNDING NOTES:**

- 1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
- 2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
- 3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
- 4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
- 5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
- 6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
- 7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
- 8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
- 9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
- 10. USE OF  $90^{\circ}$  BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN  $45^{\circ}$  BENDS CAN BE ADEQUATELY SUPPORTED.
- 11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
- 12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
- 13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
- 14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
- 15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
- 16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
- 17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
- 18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
- 19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
- 20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
- 21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/O COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.




5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



2000 CORPORATE DRIVE CANONSBURG, PA 15317

# INFINIGY FROM ZERO TO INFINIGY

the solutions are endless
2500 W. HIGGINS RD. SUITE 500 |
HOFFMAN ESTATES, IL 60169
PHONE: 847-648-4068 | FAX: 518-690-0793
WWW.INFINIGY.COM



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

RCD SS CJW

RFDS REV #: N/A

### CONSTRUCTION DOCUMENTS

2039-Z5555C

DICII Windows I I

PROJECT INFORMATI

BOBDL00092A 53 SLATER STREET MANCHESTER, CT 06040

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

# Exhibit D

**Structural Analysis Report** 

Date: May 29, 2021



Crown Castle 2000 Corporate Drive Canonsburg, PA 15317 (724) 416-2000

Subject: Structural Analysis Report

Carrier Designation: DISH Network Co-Locate

Site Number: BOBDL00092A Site Name: CT-CCI-T-876347

Crown Castle Designation: BU Number: 876347

Site Name: BUCKLAND MALL

 JDE Job Number:
 650078

 Work Order Number:
 1966291

 Order Number:
 556605 Rev. 1

Engineering Firm Designation: Crown Castle Project Number: 1966291

Site Data: 53 Slater Street, MANCHESTER, Hartford County, CT

Latitude 41° 48′ 18″, Longitude -72° 32′ 1″

155 Foot - Monopole Tower

Crown Castle is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

**Sufficient Capacity** 

This analysis utilizes an ultimate 3-second gust wind speed of 125 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - "Analysis Criteria".

Structural analysis prepared by: Sudarshan Kasera

Respectfully submitted by:

Bradley E. Byrom, P.E., S.E. Senior Project Engineer



Digitally signed by Bradley E Byrom

Date: 2021.05.30 14:34:33 -04'00'

#### **TABLE OF CONTENTS**

#### 1) INTRODUCTION

#### 2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration
Table 2 - Other Considered Equipment

#### 3) ANALYSIS PROCEDURE

Table 3 - Documents Provided 3.1) Analysis Method 3.2) Assumptions

#### 4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)
Table 5 - Tower Component Stresses vs. Capacity - LC7
4.1) Recommendations

#### 5) APPENDIX A

tnxTower Output

#### 6) APPENDIX B

**Base Level Drawing** 

#### 7) APPENDIX C

**Additional Calculations** 

## 1) INTRODUCTION

This tower is a 155 ft Monopole tower designed by SUMMIT.

## 2) ANALYSIS CRITERIA

TIA-222 Revision: TIA-222-H

Risk Category:

Wind Speed: 125 mph

Exposure Category:CTopographic Factor:1Ice Thickness:2 inWind Speed with Ice:50 mphService Wind Speed:60 mph

**Table 1 - Proposed Equipment Configuration** 

Mounting Level (ft)	Flevation	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		3	fujitsu	TA08025-B604		
		3	fujitsu	TA08025-B605		
123.0	123.0	3	jma wireless	MX08FRO665-21 w/ Mount Pipe	1	1-1/2
		1	raycap	RDIDC-9181-PF-48		
		1 1	tower mounts	Commscope MC-PK8-DSH		

**Table 2 - Other Considered Equipment** 

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		3	alcatel lucent	TD-RRH8X20-25		
		3	argus technologies	LPX310R w/ Mount Pipe		
		3	rfs celwave_cfd	APXVSPP18-C-A20 w/ Mount Pipe		
	155.0	3	rfs celwave_cfd	APXVTM14-C-120 w/ Mount Pipe	3	1-1/4
155.0		3 samsung telecommunications WIMAX I	WIMAX DAP HEAD	2	5/8 1/2	
		1	tower mounts	Miscellaneous [NA 510-1]	of Feed Line Size (in)  3 1-1/4 2 5/8	
		1	tower mounts	Platform Mount [LP 1201-1]		
		1	andrew	VHLP1-23		
	151.0	1	andrew	VHLP2-11		
	131.0	1	andrew	VHLP2.5-18	2 5/8 5 1/2	
		3	dragonwave	HORIZON COMPACT		
		3	alcatel lucent	800MHz 2X50W RRH W/FILTER		
153.0	153.0	3	alcatel lucent	PCS 1900MHz 4x45W-65MHz	-	_
		1	tower mounts	Pipe Mount [PM 601-3]		
		1	tower mounts	Side Arm Mount [SO 104-3]		
143.0	145.0	6	cci antennas	TPX-070821	6	1-1/4

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
	3		cci antennas_cfd	OPA-65R-LCUU-H6 w/ Mount Pipe	4 1	3/4 3/8
		3	ericsson	RRUS 32		
		3	ericsson	RRUS 4449 B5/B12		
		3	ericsson	RRUS 8843 B2/B66A		
		3	kathrein	782 10253		
		3	kathrein_cfd	80010965 w/ Mount Pipe		
		3	raycap	DC6-48-60-18-8F		
	143.0	3	quintel technology_cfd	QS66512-2 w/ Mount Pipe		
		1	tower mounts	T-Arm Mount [TA 601-3]		
		3	ericsson	RADIO 4449 B12/B71		
		3	ericsson_cfd	AIR -32 B2A/B66AA	_	
133.0	133.0	3	ericsson_cfd	Ericsson Air 21 B4A B12P-B8P 6FT	7	1-5/8 1-3/8
		3	rfs celwave_cfd	APXVAARR24_43-U-NA20		
		1	tower mounts	Platform Mount [LP 302-1]		
		3	andrew_cfd	LNX-6512DS-T0M w/ Mount Pipe		
		6	commscope_cfd	SBNHH-1D65B w/ Mount Pipe		
		1	raycap	RVZDC-6627-PF-48		
		1	rfs celwave	DB-T1-6Z-8AB-0Z	of Feed Lines Si	
113.0	113.0	3	samsung telecommunications	RFV01U-D1A	8	1-5/8
		3	samsung telecommunications	RFV01U-D2A		
		1	tower mounts	Platform Mount [LP 1201-1]		
		3	VZW	Sub6 Antenna - VZS01 w/ Mount Pipe		
60.0	60.0	1	tower mounts	Side Arm Mount [SO 701-1]		

## 3) ANALYSIS PROCEDURE

**Table 3 - Documents Provided** 

Document	Reference	Source
4-GEOTECHNICAL REPORTS	1533476	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	1615406	CCISITES
4-TOWER MANUFACTURER DRAWINGS	2068033	CCISITES

## 3.1) Analysis Method

tnxTower (version 8.0.9.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has

calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

## 3.2) Assumptions

- 1) Tower and structures were maintained in accordance with the TIA-222 Standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

## 4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	155 - 115.5	Pole	TP29.308x22x0.25	1	-16.49	1276.15	52.8	Pass
L2	115.5 - 79.25	Pole	TP35.514x28.114x0.313	2	-27.55	2093.96	81.1	Pass
L3	79.25 - 43.75	Pole	TP41.456x34.057x0.375	3	-37.50	2932.47	86.1	Pass
L4	43.75 - 0	Pole	TP48.8x39.735x0.438	4	-55.16	4125.15	85.4	Pass
							Summary	
						Pole (L3)	86.1	Pass
						Rating =	86.1	Pass

Table 5 - Tower Component Stresses vs. Capacity - LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	86.5	Pass
1	Base Plate	0	65.9	Pass
1	Base Foundation (Structure)	0	56.1	Pass
1	Base Foundation (Soil Interaction)	0	53.8	Pass

Structure Rating (max from all components) =	86.5%
--	-------


Notes:

 See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

## 4.1) Recommendations

The tower and its foundation have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

# APPENDIX A TNXTOWER OUTPUT



#### **MATERIAL STRENGTH**

GRAD	E Fy	Fu	GRADE	Fy	Fu
A607-60	60 ksi	75 ksi	A607-65	65 ksi	80 ksi

#### **TOWER DESIGN NOTES**

- Tower is located in Hartford County, Connecticut.
- 2. Tower designed for Exposure C to the TIA-222-H Standard.
- Tower designed for a 125 mph basic wind in accordance with the TIA-222-H Standard.
- Tower is also designed for a 50 mph basic wind with 2.00 in ice. Ice is considered to increase in thickness with height.
- 5. Deflections are based upon a 60 mph wind.
- Tower Risk Category II.
   Topographic Category 1 with Crest Height of 0.00 ft
   TOWER RATING: 86.1%



## **Tower Input Data**

The tower is a monopole.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

- Tower is located in Hartford County, Connecticut.
- Tower base elevation above sea level: 196.00 ft.
- Basic wind speed of 125 mph.
- Risk Category II.
- Exposure Category C.
- Simplified Topographic Factor Procedure for wind speed-up calculations is used.
- Topographic Category: 1.
- Crest Height: 0.00 ft.
- Nominal ice thickness of 2.000 in.
- Ice thickness is considered to increase with height.
- Ice density of 56 pcf.
- A wind speed of 50 mph is used in combination with ice.
- Temperature drop of 50 °F.
- Deflections calculated using a wind speed of 60 mph.
- A non-linear (P-delta) analysis was used.
- Pressures are calculated at each section.
- Stress ratio used in pole design is 1.05.
- Tower analysis based on target reliabilities in accordance with Annex S.
- Load Modification Factors used: Kes(Fw) = 0.95, Kes(ti) = 0.85.
- Maximum demand-capacity ratio is: 1.
- Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## **Options**

Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification Use Code Stress Ratios

√ Use Code Safety Factors - Guys Escalate Ice Always Use Max Kz

Always Use Max Kz Use Special Wind Profile

Include Bolts In Member Capacity

Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) SR Members Have Cut Ends SR Members Are Concentric Distribute Leg Loads As Uniform Assume Legs Pinned

- √ Assume Rigid Index Plate
- √ Use Clear Špans For Wind Area
  Use Clear Spans For KL/r
  Retension Guys To Initial Tension
- √ Bypass Mast Stability Checks
- √ Use Azimuth Dish Coefficients
- √ Project Wind Area of Appurt.

Autocalc Torque Arm Areas

Add IBC .6D+W Combination

Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Treat Feed Line Bundles As Cylinder Ignore KL/ry For 60 Deg. Angle Legs Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation

 ✓ Consider Feed Line Torque Include Angle Block Shear Check Use TIA-222-H Bracing Resist. Exemption Use TIA-222-H Tension Splice Exemption

#### Poles

✓ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets Pole Without Linear Attachments Pole With Shroud Or No Appurtenances Outside and Inside Corner Radii Are Known

## Tapered Pole Section Geometry

Section	Elevation	Section	Splice	Number	Тор	Bottom	Wall	Bend	Pole Grade
	_	Length	Length	of	Diameter	Diameter	Thickness	Radius	
	ft	ft	ft	Sides	in	in	in	in	
L1	155.00-115.50	39.50	3.750	18	22.000	29.308	0.250	1.000	A607-60 (60 ksi)
L2	115.50-79.25	40.00	4.500	18	28.114	35.514	0.313	1.250	A607-65 (65 ksi)
L3	79.25-43.75	40.00	5.250	18	34.057	41.456	0.375	1.500	A607-65 (65 ksi)
L4	43.75-0.00	49.00		18	39.735	48.800	0.438	1.750	A607-65 (65 ksi)

Tapered	Pole	Pro	perties
---------	------	-----	---------

Section	Tip Dia.	Area	1	r	С	I/C	J	It/Q	W	w/t
	in	in²	in⁴	in	in	in³	in <sup>4</sup>	in²	in	
L1	22.301	17.259	1031.483	7.721	11.176	92.294	2064.324	8.631	3.432	13.728
	29.722	23.058	2459.697	10.316	14.888	165.208	4922.630	11.531	4.718	18.873
L2	29.204	27.576	2692.828	9.870	14.282	188.547	5389.199	13.791	4.398	14.074
	36.014	34.915	5466.104	12.497	18.041	302.980	10939.401	17.461	5.700	18.241
L3	35.369	40.089	5745.804	11.957	17.301	332.114	11499.168	20.049	5.334	14.224
	42.038	48.897	10425.542	14.584	21.060	495.048	20864.803	24.453	6.636	17.697
L4	41.267	54.569	10646.606	13.951	20.185	527.444	21307.222	27.290	6.223	14.225
	49.485	67.157	19844.888	17.169	24.790	800.507	39715.889	33.585	7.819	17.872

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals	Double Angle Stitch Bolt Spacing Redundants
ft	ft <sup>2</sup>	in				in	in	in
L1 155.00-			1	1	1			
115.50								
L2 115.50-			1	1	1			
79.25								
L3 79.25-			1	1	1			
43.75								
L4 43.75-0.00			1	1	1			

# Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From	Componen	Placement	Total Number	Number Per Row	Start/En d	Width or Diamete	Perimete r	Weight
		Torque Calculation	Type	ft	rvamoor	7 07 7 07	Position	r in	in	plf
***		- Caroaranorr								
Safety Line 3/8 **155**	Α	No	Surface Ar (CaAa)	155.00 - 0.00	1	1	0.000 0.000	0.375		0.220
2" Rigid Conduit	С	No	Surface Ar (CaAa)	155.00 - 0.00	2	2	0.250 0.250	2.000		2.800
FSJ4-50B(1/2)  *** ***	С	No	Surface Ar (CaAa)	155.00 - 0.00	5	2	0.000 0.000	0.530		0.140
CU12PSM9P6XXX(1- 1/2) **	A	No	Surface Ar (CaAa)	123.00 - 0.00	1	1	-0.250 -0.250	1.600		2.350

# Feed Line/Linear Appurtenances - Entered As Area

Description	Face or	Allow Shield	Exclude From	Componen t	Placement	Total Number		$C_A A_A$	Weight
	Leg		Torque Calculation	Type	ft			ftº/ft	plf
ATCB-B01-	С	No	No		155.00 - 0.00	3	No Ice	0.00	0.075
005(5/16)							1/2" Ice	0.00	0.075
, ,							1" Ice	0.00	0.075
							2" Ice	0.00	0.075
9776(5/8)	С	No	No	Inside Pole	155.00 - 0.00	1	No Ice	0.00	0.275
, ,							1/2" Ice	0.00	0.275
							1" Ice	0.00	0.275
							2" Ice	0.00	0.275
HB058-M12-	С	No	No	Inside Pole	155.00 - 0.00	1	No Ice	0.00	0.242
XXXF(5/8)	-					•	1/2" Ice	0.00	0.242
7000 (0/0)							1" Ice	0.00	0.242
							2" Ice	0.00	0.242
UD111 1 00111	С	No	No	Incido Dolo	155.00 0.00	2	No Ice		1.080
HB114-1-08U4-	C	No	No	inside Pole	155.00 - 0.00	3		0.00	
M5J(1-1/4)							1/2" Ice	0.00	1.080
							1" Ice	0.00	1.080
							2" Ice	0.00	1.080
**143**									
_DF6-50A(1-1/4)	Α	No	No	Inside Pole	143.00 - 0.00	6	No Ice	0.00	0.600
							1/2" Ice	0.00	0.600
							1" Ice	0.00	0.600
							2" Ice	0.00	0.600
FB-L98B-002-	Α	No	No	Inside Pole	143.00 - 0.00	1	No Ice	0.00	0.059
75000(3/8)							1/2" Ice	0.00	0.059
. 0000(0/0)							1" Ice	0.00	0.059
							2" lce	0.00	0.059
WR-VG86ST-	Α	No	No	Incido Polo	143.00 - 0.00	4	No Ice	0.00	0.584
BRD(3/4)	^	INO	NO	iliside i die	143.00 - 0.00	4	1/2" Ice	0.00	0.584
DKD(3/4)									
							1" Ice	0.00	0.584
OII D O					4.40.00.00.00		2" Ice	0.00	0.584
2" Rigid Conduit	Α	No	No	Inside Pole	143.00 - 0.00	2	No Ice	0.00	2.800
							1/2" Ice	0.00	2.800
							1" Ice	0.00	2.800
							2" Ice	0.00	2.800
**133**									
HCS 6X12	Α	No	No	Inside Pole	133.00 - 0.00	1	No Ice	0.00	1.700
6AWG(1-3/8)							1/2" Ice	0.00	1.700
, ,							1" Ice	0.00	1.700
							2" Ice	0.00	1.700
HCS 6X12	Α	No	No	Inside Pole	133.00 - 0.00	1	No Ice	0.00	2.400
4AWG(1-5/8)					.00.00	•	1/2" Ice	0.00	2.400
471110(1 0/0)							1" Ice	0.00	2.400
							2" Ice	0.00	2.400
LCF158-50JA-	Α	No	No	Incido Dolo	133.00 - 0.00	6	No Ice		0.800
	А	NO	No	inside Pole	133.00 - 0.00	О		0.00	
A0(1-5/8)							1/2" Ice	0.00	0.800
							1" Ice	0.00	0.800
							2" Ice	0.00	0.800
**113**	_								
561(1-5/8)	В	No	No	Inside Pole	113.00 - 0.00	6	No Ice	0.00	1.350
							1/2" Ice	0.00	1.350
							1" Ice	0.00	1.350
							2" Ice	0.00	1.350
HB158-U12S24-	В	No	No	Inside Pole	113.00 - 0.00	2	No Ice	0.00	3.200
XXX-LI(1-5/8)		-	-		<del>-</del>		1/2" Ice	0.00	3.200
							1" Ice	0.00	3.200
							2" lce	0.00	3.200
***							2 100	0.00	5.200

# Feed Line/Linear Appurtenances Section Areas

Tower Sectio	Tower Elevation	Face	$A_R$	$A_F$	C <sub>A</sub> A <sub>A</sub> In Face	C <sub>A</sub> A <sub>A</sub> Out Face	Weight
			••	••			.,
n	ft		ft <sup>2</sup>	ft²	ft <sup>2</sup>	ft <sup>2</sup>	K
L1	155.00-115.50	Α	0.000	0.000	2.681	0.000	0.50
		В	0.000	0.000	0.000	0.000	0.00
		С	0.000	0.000	19.987	0.000	0.41
L2	115.50-79.25	Α	0.000	0.000	7.159	0.000	0.84
		В	0.000	0.000	0.000	0.000	0.49
		С	0.000	0.000	18.343	0.000	0.37
L3	79.25-43.75	Α	0.000	0.000	7.011	0.000	0.82
		В	0.000	0.000	0.000	0.000	0.51
		С	0.000	0.000	17.963	0.000	0.37
L4	43.75-0.00	Α	0.000	0.000	8.641	0.000	1.01
		В	0.000	0.000	0.000	0.000	0.63
		С	0.000	0.000	22.137	0.000	0.45

# Feed Line/Linear Appurtenances Section Areas - With Ice

Tower	Tower	Face	Ice	$A_R$	$A_F$	$C_AA_A$	$C_A A_A$	Weight
Sectio	Elevation	or	Thickness			In Face	Out Face	
n	ft	Leg	in	ft²	ft <sup>2</sup>	ft²	ft <sup>2</sup>	K
L1	155.00-115.50	Α	1.956	0.000	0.000	21.071	0.000	0.78
		В		0.000	0.000	0.000	0.000	0.00
		С		0.000	0.000	63.623	0.000	1.24
L2	115.50-79.25	Α	1.893	0.000	0.000	35.527	0.000	1.35
		В		0.000	0.000	0.000	0.000	0.49
		С		0.000	0.000	58.388	0.000	1.14
L3	79.25-43.75	Α	1.808	0.000	0.000	33.897	0.000	1.29
		В		0.000	0.000	0.000	0.000	0.51
		С		0.000	0.000	56.061	0.000	1.08
L4	43.75-0.00	Α	1.633	0.000	0.000	40.289	0.000	1.55
		В		0.000	0.000	0.000	0.000	0.63
		С		0.000	0.000	67.233	0.000	1.27

## **Feed Line Center of Pressure**

Section	Elevation	$CP_X$	CPz	CP <sub>X</sub>	CPz
				Ice	Ice
	ft	in	in	in	in
L1	155.00-115.50	-1.691	2.778	-2.061	2.725
L2	115.50-79.25	-2.473	2.754	-3.162	2.875
L3	79.25-43.75	-2.559	2.846	-3.417	3.109
L4	43.75-0.00	-2.632	2.925	-3.631	3.315

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

## **Shielding Factor Ka**

Tower	Feed Line	Description	Feed Line	Ka	Ka
Section	Record No.		Segment	No Ice	Ice
			Elev.		
L	.1 2	Safety Line 3/8	115.50 -	1.0000	1.0000
		-	155.00		
L	.1 4	2" Rigid Conduit	115.50 -	1.0000	1.0000
		_	155.00		
L	.1 6	FSJ4-50B(1/2)	115.50 -	1.0000	1.0000
			155.00		
L	.1 25	CU12PSM9P6XXX(1-1/2)	115.50 -	1.0000	1.0000

Tower	Feed Line	Description	Feed Line	Ka	K <sub>a</sub>
Section	Record No.		Segment	No Ice	Ice
			Elev.		
			123.00		
L2	2	Safety Line 3/8	79.25 -	1.0000	1.0000
			115.50		
L2	4	2" Rigid Conduit	79.25 -	1.0000	1.0000
			115.50		
L2	6	FSJ4-50B(1/2)	79.25 -	1.0000	1.0000
			115.50		
L2	25	CU12PSM9P6XXX(1-1/2)	79.25 -	1.0000	1.0000
			115.50		
L3	2	Safety Line 3/8	43.75 -	1.0000	1.0000
			79.25		
L3	4	2" Rigid Conduit	43.75 -	1.0000	1.0000
		EQ 14 EQD(4/Q)	79.25	4 0000	4 0000
L3	6	FSJ4-50B(1/2)	43.75 -	1.0000	1.0000
	0.5	011400014000000000044 4 (0)	79.25	4 0000	4 0000
L3	25	CU12PSM9P6XXX(1-1/2)	43.75 -	1.0000	1.0000
	0	Cafata Lina 2/0	79.25	4 0000	4 0000
L4 L4	2	Safety Line 3/8	0.00 - 43.75	1.0000	1.0000
L4 L4	4	2" Rigid Conduit	0.00 - 43.75	1.0000	1.0000
	6	FSJ4-50B(1/2)	0.00 - 43.75	1.0000	1.0000
L4	25	CU12PSM9P6XXX(1-1/2)	0.00 - 43.75	1.0000	1.0000

D: 4 =	_	
Discrete 1	I OWET I	O A M S

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement
			Vert ft ft ft	0	ft
**155**					
APXVTM14-C-120 w/ Mount Pipe	Α	From Centroid-Leg	4.00 0.000	0.000	155.00
APXVTM14-C-120 w/ Mount Pipe	В	From Centroid-Leg	0.000 4.00 0.000 0.000	0.000	155.00
APXVTM14-C-120 w/ Mount Pipe	С	From Centroid-Leg	4.00 0.000	0.000	155.00
APXVSPP18-C-A20 w/ Mount Pipe	Α	From Centroid-Leg	0.000 4.00 0.000	0.000	155.00
APXVSPP18-C-A20 w/ Mount Pipe	В	From Centroid-Leg	0.000 4.00 0.000	0.000	155.00
APXVSPP18-C-A20 w/ Mount Pipe	С	From Centroid-Leg	0.000 4.00 0.000	0.000	155.00
LPX310R w/ Mount Pipe	Α	From Centroid-Leg	0.000 4.00 0.000	0.000	155.00
LPX310R w/ Mount Pipe	В	From Centroid-Leg	0.000 4.00 0.000	0.000	155.00
LPX310R w/ Mount Pipe	С	From Centroid-Leg	0.000 4.00 0.000	0.000	155.00
TD-RRH8X20-25	Α	From Centroid-Leg	0.000 4.00 0.000 0.000	0.000	155.00

Description	Face or Leg	Offset Type	Offsets: Horz Lateral	Azimuth Adjustment	Placement
	Leg		Vert ft	۰	ft
			ft ft		
TD-RRH8X20-25	В	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
TD-RRH8X20-25	С	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
WIMAX DAP HEAD	А	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
WIMAX DAP HEAD	В	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
WIMAX DAP HEAD	С	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
HORIZON COMPACT	Α	From Centroid-Leg	4.00 0.000 -4.000	0.000	155.00
HORIZON COMPACT	В	From Centroid-Leg	4.00 0.000	0.000	155.00
HORIZON COMPACT	С	From Centroid-Leg	-4.000 4.00 0.000 -4.000	0.000	155.00
2.4" Dia x 4-ft Mount Pipe	А	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
2.4" Dia x 4-ft Mount Pipe	В	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
2.4" Dia x 4-ft Mount Pipe	С	From Centroid-Leg	4.00 0.000 0.000	0.000	155.00
Miscellaneous [NA 510-1] Platform Mount [LP 1201-1] **153**	C C	None None	0.000	0.000 0.000	155.00 155.00
800MHz 2X50W RRH W/FILTER	А	From Leg	1.00 0.000 0.000	0.000	153.00
800MHz 2X50W RRH W/FILTER	В	From Leg	1.00 0.000 0.000	0.000	153.00
800MHz 2X50W RRH W/FILTER	С	From Leg	1.00 0.000 0.000	0.000	153.00
PCS 1900MHz 4x45W-65MHz	А	From Leg	1.00 0.000	0.000	153.00
PCS 1900MHz 4x45W-65MHz	В	From Leg	0.000 1.00 0.000	0.000	153.00
PCS 1900MHz 4x45W-65MHz	С	From Leg	0.000 1.00 0.000 0.000	0.000	153.00
Pipe Mount [PM 601-3] Side Arm Mount [SO 104-3] **143**	C C	None None	0.000	0.000 0.000	153.00 153.00
OPA-65R-LCUU-H6 w/ Mount Pipe	А	From Leg	4.00 0.000 2.000	0.000	143.00
OPA-65R-LCUU-H6 w/ Mount Pipe	В	From Leg	4.00 0.000 2.000	0.000	143.00
OPA-65R-LCUU-H6 w/ Mount Pipe	С	From Leg	4.00 0.000	0.000	143.00

Description	Face or	Offset Type	Offsets: Horz	Azimuth Adjustment	Placement
	Leg		Lateral Vert		
			ft	0	ft
			ft ft		
00040005 / Marrist Bira	Δ.	Face of the second	2.000	0.000	4.40.00
80010965 w/ Mount Pipe	Α	From Leg	4.00 0.000	0.000	143.00
			2.000		
80010965 w/ Mount Pipe	В	From Leg	4.00	0.000	143.00
			0.000 2.000		
80010965 w/ Mount Pipe	С	From Leg	4.00	0.000	143.00
			0.000		
QS66512-2 w/ Mount Pipe	Α	From Leg	2.000 4.00	0.000	143.00
45000 i 2 2 ii, iiidani i ipo	, ,		0.000	0.000	0.00
OCCCEAG O/ Mayort Din a	Б	F==== 1 ===	0.000	0.000	4.40.00
QS66512-2 w/ Mount Pipe	В	From Leg	4.00 0.000	0.000	143.00
			0.000		
QS66512-2 w/ Mount Pipe	С	From Leg	4.00	0.000	143.00
			0.000 0.000		
(2) TPX-070821	Α	From Leg	4.00	0.000	143.00
			0.000		
(2) TPX-070821	В	From Leg	2.000 4.00	0.000	143.00
(2) 11 7 07 002 1	D	r rom Log	0.000	0.000	140.00
(2) ==>( ==== (			2.000		
(2) TPX-070821	С	From Leg	4.00 0.000	0.000	143.00
			2.000		
782 10253	Α	From Leg	4.00	0.000	143.00
			0.000 2.000		
782 10253	В	From Leg	4.00	0.000	143.00
			0.000		
782 10253	С	From Leg	2.000 4.00	0.000	143.00
702 10233	O	1 Ioili Log	0.000	0.000	143.00
DD110 00	•		2.000	0.000	4.40.00
RRUS 32	Α	From Leg	4.00 0.000	0.000	143.00
			2.000		
RRUS 32	В	From Leg	4.00	0.000	143.00
			0.000 2.000		
RRUS 32	С	From Leg	4.00	0.000	143.00
			0.000		
RRUS 8843 B2/B66A	Α	From Leg	2.000 4.00	0.000	143.00
141.00 00 10 B2 B00/1	, ,	1 10111 20g	0.000	0.000	1 10.00
DDUO 0040 D0/D004	Б	En al Lan	2.000	0.000	4.40.00
RRUS 8843 B2/B66A	В	From Leg	4.00 0.000	0.000	143.00
			2.000		
RRUS 8843 B2/B66A	С	From Leg	4.00	0.000	143.00
			0.000 2.000		
DC6-48-60-18-8F	Α	From Leg	4.00	0.000	143.00
			0.000		
DC6-48-60-18-8F	В	From Leg	2.000 4.00	0.000	143.00
200 10 00 10 01	2		0.000	3.000	0.00
DOC 40 CO 40 CF	0	Feeren Land	2.000	0.000	4.40.00
DC6-48-60-18-8F	С	From Leg	4.00 0.000	0.000	143.00
			2.000		
RRUS 4449 B5/B12	Α	From Leg	4.00	0.000	143.00

Description	Face or	Offset Type	Offsets: Horz	Azimuth Adjustment	Placemer
	Leg		Lateral		
			Vert ft	0	ft
			ft ft		n
			0.000 2.000		
RRUS 4449 B5/B12	В	From Leg	4.00 0.000	0.000	143.00
RRUS 4449 B5/B12	С	From Leg	2.000 4.00 0.000	0.000	143.00
2.4" Dia x 8-ft Mount Pipe	Α	From Face	2.000 4.00 0.000	0.000	143.00
2.4" Dia x 8-ft Mount Pipe	В	From Face	4.000 4.00	0.000	143.00
2.4" Dia x 8-ft Mount Pipe	С	From Face	0.000 4.000 4.00	0.000	143.00
			0.000 4.000		
T-Arm Mount [TA 601-3]  **133**	C	None		0.000	143.00
AIR -32 B2A/B66AA	А	From Centroid-Leg	4.00 0.000 0.000	0.000	133.00
AIR -32 B2A/B66AA	В	From Centroid-Leg	4.00 0.000	0.000	133.00
AIR -32 B2A/B66AA	С	From Centroid-Leg	0.000 4.00 0.000	0.000	133.00
APXVAARR24_43-U-NA20	Α	From Centroid-Leg	0.000 4.00 0.000	0.000	133.00
APXVAARR24_43-U-NA20	В	From Centroid-Leg	0.000 4.00 0.000	0.000	133.00
APXVAARR24_43-U-NA20	С	From Centroid-Leg	0.000 4.00 0.000	0.000	133.00
Ericsson Air 21 B4A B12P-B8P 6FT	Α	From Centroid-Leg	0.000 4.00 0.000	0.000	133.00
Ericsson Air 21 B4A B12P-B8P 6FT	В	From Centroid-Leg	0.000 4.00 0.000	0.000	133.00
Ericsson Air 21 B4A B12P-B8P 6FT	С	From Centroid-Leg	0.000 4.00	0.000	133.00
RADIO 4449 B12/B71	Α	From Centroid-Leg	0.000 0.000 4.00	0.000	133.00
RADIO 4449 B12/B71	В	From Centroid-Leg	0.000 0.000 4.00	0.000	133.00
RADIO 4449 B12/B71	С	From Centroid-Leg	0.000 0.000 4.00	0.000	133.00
			0.000 0.000		
Platform Mount [LP 302-1]	С	None		0.000	133.00
MX08FRO665-21 w/ Mount Pipe	Α	From Leg	4.00 0.000 0.000	0.000	123.00
MX08FRO665-21 w/ Mount Pipe	В	From Leg	4.00 0.000 0.000	0.000	123.00
MX08FRO665-21 w/ Mount Pipe	С	From Leg	4.00 0.000	0.000	123.00

Description	Face	Offset	Offsets:	Azimuth	Placemer
	or	Туре	Horz	Adjustment	
	Leg		Lateral Vert		
			ft	o	ft
			ft		,,
			ft		
TA 00005 B004		Encort on	0.000	0.000	400.00
TA08025-B604	Α	From Leg	4.00	0.000	123.00
			0.000 0.000		
TA08025-B604	В	From Leg	4.00	0.000	123.00
17100020 8004		1 Tom Log	0.000	0.000	120.00
			0.000		
TA08025-B604	С	From Leg	4.00	0.000	123.00
			0.000		
TA00005 DC05	^	F 1	0.000	0.000	400.00
TA08025-B605	Α	From Leg	4.00 0.000	0.000	123.00
			0.000		
TA08025-B605	В	From Leg	4.00	0.000	123.00
		3	0.000		
			0.000		
TA08025-B605	С	From Leg	4.00	0.000	123.00
			0.000		
RDIDC-9181-PF-48	Α	From Log	0.000 4.00	0.000	123.00
KDIDG-9101-PF-40	A	From Leg	0.000	0.000	123.00
			0.000		
(2) 8' x 2" Mount Pipe	Α	From Leg	4.00	0.000	123.00
` '		ű	0.000		
			0.000		
(2) 8' x 2" Mount Pipe	В	From Leg	4.00	0.000	123.00
			0.000		
(2) 8' x 2" Mount Pipe	С	From Leg	0.000 4.00	0.000	123.00
(2) 6 X 2 Wount i ipe	C	r ioin Leg	0.000	0.000	123.00
			0.000		
Commscope MC-PK8-DSH	С	None		0.000	123.00
** **113**					
	٨	From Centroid-Leg	4.00	0.000	113.00
LNX-6512DS-T0M w/ Mount Pipe	Α	Fiorii Centrola-Leg	0.000	0.000	113.00
			0.000		
LNX-6512DS-T0M w/ Mount Pipe	В	From Centroid-Leg	4.00	0.000	113.00
			0.000		
LNIV OF LODGE TONE AND A TO	^	For a Co. 1 111	0.000	2 222	440.00
LNX-6512DS-T0M w/ Mount Pipe	С	From Centroid-Leg	4.00 0.000	0.000	113.00
			0.000		
(2) SBNHH-1D65B w/ Mount Pipe	Α	From Centroid-Leg	4.00	0.000	113.00
( , ==::::: 12002 ii, iiiodiki ipo			0.000	0.000	
			0.000		
(2) SBNHH-1D65B w/ Mount Pipe	В	From Centroid-Leg	4.00	0.000	113.00
			0.000		
(2) SBNHH-1D65B w/ Mount Pipe	С	From Centroid-Leg	0.000 4.00	0.000	113.00
(2) SONTH- IDOSO W/ WOUTH PIPE	C	From Centrola-Leg	4.00 0.000	0.000	113.00
			0.000		
Sub6 Antenna - VZS01 w/ Mount Pipe	Α	From Centroid-Leg	4.00	0.000	113.00
·		ŭ	0.000		
0.10.4	_	F 6	0.000		
Sub6 Antenna - VZS01 w/ Mount Pipe	В	From Centroid-Leg	4.00	0.000	113.00
			0.000 0.000		
Sub6 Antenna - VZS01 w/ Mount Pipe	С	From Centroid-Leg	4.00	0.000	113.00
2007 anomia v2001 w would lipe	J	1 10111 John John July	0.000	0.000	1 10.00
			0.000		
RVZDC-6627-PF-48	В	From Centroid-Leg	4.00	0.000	113.00
			0.000		
DD T4 07 045 07		F	0.000	2 222	440.0-
DB-T1-6Z-8AB-0Z	Α	From Centroid-Leg	4.00	0.000	113.00

Description	Face or	Offset Type	Offsets: Horz	Azimuth Adjustment	Placemen
	Leg	.,,,,,	Lateral	, ajaou nom	
	209		Vert		
			ft	0	ft
			ft		
			ft		
			0.000		
			0.000		
RFV01U-D1A	Α	From Centroid-Leg	4.00	0.000	113.00
		Ğ	0.000		
			0.000		
(2) RFV01U-D1A	В	From Centroid-Leg	4.00	0.000	113.00
		_	0.000		
			0.000		
(3) RFV01U-D2A	Α	From Centroid-Leg	4.00	0.000	113.00
			0.000		
			0.000		
Platform Mount [LP 1201-1] **60**	С	None		0.000	113.00
Side Arm Mount [SO 701-1]	Α	From Leg	1.50	0.000	60.00
1		-3	0.000		
			0.000		
***					

Dishes											
Description	Face or Leg	Dish Type	Offset Type	Offsets: Horz Lateral Vert	Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter			
				ft	0	0	ft	ft			
VHLP1-23	Α	Paraboloid w/Shroud (HP)	From Centroi	4.00 0.000	-64.000		155.00	1.27			
VHLP2.5-18	В	Paraboloid w/Shroud (HP)	d-Leg From Centroi	-4.000 4.00 0.000	21.000		155.00	2.50			
VHLP2-11	С	Paraboloid w/Shroud (HP)	d-Leg From	-4.000 4.00	13.000		155.00	2.00			
			Centroi d-Leg	0.000 -4.000							

# **Load Combinations**

Comb.		Description
No.		
1	Dead Only	
2	1.2 Dead+1.0 Wind 0 deg - No Ice	
3	0.9 Dead+1.0 Wind 0 deg - No Ice	
4	1.2 Dead+1.0 Wind 30 deg - No Ice	
5	0.9 Dead+1.0 Wind 30 deg - No Ice	
6	1.2 Dead+1.0 Wind 60 deg - No Ice	
7	0.9 Dead+1.0 Wind 60 deg - No Ice	
8	1.2 Dead+1.0 Wind 90 deg - No Ice	
9	0.9 Dead+1.0 Wind 90 deg - No Ice	
10	1.2 Dead+1.0 Wind 120 deg - No Ice	
11	0.9 Dead+1.0 Wind 120 deg - No Ice	
12	1.2 Dead+1.0 Wind 150 deg - No Ice	
13	0.9 Dead+1.0 Wind 150 deg - No Ice	
14	1.2 Dead+1.0 Wind 180 deg - No Ice	
15	0.9 Dead+1.0 Wind 180 deg - No Ice	
16	1.2 Dead+1.0 Wind 210 deg - No Ice	
17	0.9 Dead+1.0 Wind 210 deg - No Ice	
	-	

Comb.	Description
No.	
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35 36	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36 37	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp 1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service  Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

# **Maximum Member Forces**

Sectio	Elevation	Component	Condition	Gov.	Axial	Major Axis	Minor Axis
n	ft	Туре	Condition	Load	AMU	Moment	Moment
No.	74	1990		Comb.	K	kip-ft	kip-ft
L1	155 - 115.5	Pole	Max Tension	1	0.00	0.00	0.00
	100 110.0	1 010	Max. Compression	26	-46.24	0.30	-0.69
			Max. Mx	8	-16.52	-463.69	-5.29
			Max. My	2	-16.51	4.71	462.10
			Max. Vy	8	22.45	-463.69	-5.29
			Max. Vx	2	-22.46	4.71	462.10
			Max. Torque	4	22.40	7.71	-0.92
L2	115.5 -	Pole	Max Tension	1	0.00	0.00	0.00
	79.25	1 010	Wax Toriolori	•	0.00	0.00	0.00
			Max. Compression	26	-67.71	-0.94	0.75
			Max. Mx	8	-27.59	-1427.89	-11.69
			Max. My	2	-27.56	10.95	1432.27
			Max. Vy	8	29.36	-1427.89	-11.69
			Max. Vx	2	-29.56	10.95	1432.27
			Max. Torque	13			1.40
L3	79.25 -	Pole	Max Tension	1	0.00	0.00	0.00
	43.75						
			Max. Compression	26	-81.32	-0.14	0.03
			Max. Mx	8	-37.52	-2502.09	-18.98
			Max. My	2	-37.51	17.97	2513.02
			Max. Vy	8	32.37	-2502.09	-18.98
			Max. Vx	2	-32.53	17.97	2513.02
			Max. Torque	23			-1.52
L4	43.75 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	26	-103.94	1.10	-1.73
			Max. Mx	8	-55.16	-4170.34	-29.20
			Max. My	2	-55.16	27.50	4188.65
			Max. Vy	8	35.38	-4170.34	-29.20

Sectio	Elevation	Component	Condition	Gov.	Axial	Major Axis	Minor Axis
n	ft	Type		Load		Moment	Moment
No.				Comb.	K	kip-ft	kip-ft
			Max. Vx	2	-35.53	27.50	4188.65
			Max. Torque	23			-1.51

Mavimum	Reactions
IVIAXIIIIIII	Reactions

Location	Condition	Gov.	Vertical	Horizontal, X	Horizontal, Z
		Load	K	K	K
		Comb.			
Pole	Max. Vert	33	103.94	-0.04	-10.26
	Max. H <sub>x</sub>	20	55.20	35.29	0.26
	Max. H <sub>z</sub>	2	55.20	0.18	35.47
	Max. M <sub>x</sub>	2	4188.65	0.18	35.47
	Max. M <sub>z</sub>	8	4170.34	-35.31	-0.19
	Max. Torsion	13	1.50	-17.76	-30.68
	Min. Vert	23	41.40	30.65	17.83
	Min. H <sub>x</sub>	8	55.20	-35.31	-0.19
	Min. H <sub>z</sub>	14	55.20	-0.17	-35.40
	Min. M <sub>x</sub>	14	-4177.60	-0.17	-35.40
	Min. M <sub>z</sub>	20	-4165.65	35.29	0.26
	Min. Torsion	23	-1.51	30.65	17.83

# **Tower Mast Reaction Summary**

Load Combination	Vertical	Shear <sub>x</sub>	Shearz	Overturning Moment, M <sub>x</sub>	Overturning Moment, M <sub>z</sub>	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead Only	46.00	0.00	0.00	0.13	-0.27	0.00
1.2 Dead+1.0 Wind 0 deg -	55.20	-0.18	-35.47	-4188.65	27.50	1.34
No Ice						
0.9 Dead+1.0 Wind 0 deg - No Ice	41.40	-0.18	-35.47	-4106.15	26.99	1.36
1.2 Dead+1.0 Wind 30 deg - No Ice	55.20	17.50	-30.66	-3619.76	-2061.89	0.94
0.9 Dead+1.0 Wind 30 deg - No Ice	41.40	17.50	-30.66	-3548.45	-2021.18	0.94
1.2 Dead+1.0 Wind 60 deg - No Ice	55.20	30.58	-17.54	-2065.10	-3611.78	0.02
0.9 Dead+1.0 Wind 60 deg - No Ice	41.40	30.58	-17.54	-2024.49	-3540.44	0.01
1.2 Dead+1.0 Wind 90 deg - No Ice	55.20	35.31	0.19	29.20	-4170.34	-0.95
0.9 Dead+1.0 Wind 90 deg - No Ice	41.40	35.31	0.19	28.54	-4088.02	-0.97
1.2 Dead+1.0 Wind 120 deg - No Ice	55.20	30.64	17.76	2097.09	-3620.50	-1.37
0.9 Dead+1.0 Wind 120 deg - No Ice	41.40	30.64	17.76	2055.76	-3549.01	-1.40
1.2 Dead+1.0 Wind 150 deg - No Ice	55.20	17.76	30.68	3620.98	-2101.32	-1.48
0.9 Dead+1.0 Wind 150 deg - No Ice	41.40	17.76	30.68	3549.64	-2059.77	-1.50
1.2 Dead+1.0 Wind 180 deg - No Ice	55.20	0.17	35.40	4177.60	-27.16	-1.26
0.9 Dead+1.0 Wind 180 deg - No Ice	41.40	0.17	35.40	4095.31	-26.47	-1.28
1.2 Dead+1.0 Wind 210 deg - No Ice	55.20	-17.52	30.61	3611.56	2064.05	-0.92
0.9 Dead+1.0 Wind 210 deg - No Ice	41.40	-17.52	30.61	3540.40	2023.49	-0.92
1.2 Dead+1.0 Wind 240 deg - No Ice	55.20	-30.49	17.56	2067.44	3596.44	0.02

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>z</sub>	Overturning Moment, M <sub>x</sub>	Overturning Moment, M <sub>z</sub>	Torque
	K	K	K	kip-ft .	kip-ft	kip-ft
0.9 Dead+1.0 Wind 240 deg	41.40	-30.49	17.56	2026.74	3525.66	0.03
- No Ice						
1.2 Dead+1.0 Wind 270 deg	55.20	-35.29	-0.26	-41.20	4165.65	1.17
- No Ice 0.9 Dead+1.0 Wind 270 deg	41.40	-35.29	-0.26	-40.32	4083.65	1.19
- No Ice	11.10	00.20	0.20	10.02	1000.00	1.10
1.2 Dead+1.0 Wind 300 deg	55.20	-30.65	-17.83	-2108.99	3621.57	1.49
- No Ice						
0.9 Dead+1.0 Wind 300 deg	41.40	-30.65	-17.83	-2067.44	3550.25	1.51
- No Ice 1.2 Dead+1.0 Wind 330 deg	55.20	-17.81	-30.75	-3631.91	2108.83	1.46
- No Ice	55.20	-17.01	-30.73	-3031.91	2100.03	1.40
0.9 Dead+1.0 Wind 330 deg	41.40	-17.81	-30.75	-3560.38	2067.31	1.48
- No Ice						
1.2 Dead+1.0 Ice+1.0 Temp	103.94	0.00	0.00	1.73	1.10	0.00
1.2 Dead+1.0 Wind 0	103.94	-0.04	-10.27	-1350.95	7.25	0.26
deg+1.0 lce+1.0 Temp	102.04	F 10	0.00	1160.06	669.04	0.14
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	103.94	5.10	-8.88	-1168.06	-668.91	0.14
1.2 Dead+1.0 Wind 60	103.94	8.88	-5.10	-667.90	-1168.50	-0.07
deg+1.0 Ice+1.0 Temp	100.01	0.00	0.10	007.00	1100.00	0.07
1.2 Dead+1.0 Wind 90	103.94	10.25	0.04	8.34	-1349.18	-0.27
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 120	103.94	8.89	5.14	678.62	-1170.41	-0.34
deg+1.0 lce+1.0 Temp	102.04	E 1E	0.00	1171.75	677.00	0.22
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	103.94	5.15	8.89	11/1./5	-677.83	-0.33
1.2 Dead+1.0 Wind 180	103.94	0.04	10.26	1351.91	-5.16	-0.25
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 210	103.94	-5.10	8.87	1169.58	671.57	-0.14
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 240	103.94	-8.86	5.10	671.94	1166.95	0.08
deg+1.0 Ice+1.0 Temp 1.2 Dead+1.0 Wind 270	103.94	-10.25	-0.05	-7.57	1350.02	0.31
deg+1.0 lce+1.0 Temp	103.94	-10.23	-0.03	-1.51	1330.02	0.51
1.2 Dead+1.0 Wind 300	103.94	-8.89	-5.15	-677.82	1172.61	0.36
deg+1.0 Ice+1.0 Temp						
1.2 Dead+1.0 Wind 330	103.94	-5.16	-8.90	-1170.70	681.62	0.32
deg+1.0 Ice+1.0 Temp						
Dead+Wind 0 deg - Service	46.00	-0.04	-7.70	-900.41	5.66	0.30
Dead+Wind 30 deg - Service Dead+Wind 60 deg - Service	46.00 46.00	3.80 6.64	-6.66 -3.81	-778.09 -443.88	-443.51 -776.69	0.21 0.00
Dead+Wind 90 deg - Service	46.00	7.67	0.04	6.34	-776.69 -896.77	-0.21
Dead+Wind 120 deg - Service	46.00	6.65	3.86	450.92	-778.60	-0.21
Service	40.00	0.00	0.00	400.02	770.00	0.01
Dead+Wind 150 deg -	46.00	3.86	6.66	778.54	-452.00	-0.33
Service						
Dead+Wind 180 deg -	46.00	0.04	7.68	898.17	-6.08	-0.28
Service	40.00	0.00	0.04	770.40	440.40	0.00
Dead+Wind 210 deg -	46.00	-3.80	6.64	776.48	443.48	-0.20
Service Dead+Wind 240 deg -	46.00	-6.62	3.81	444.53	772.89	0.01
Service	<del>-</del> 0.00	-0.02	3.01	<del></del> .55	112.03	0.01
Dead+Wind 270 deg -	46.00	-7.66	-0.06	-8.77	895.27	0.26
Service						
Dead+Wind 300 deg -	46.00	-6.65	-3.87	-453.34	778.35	0.33
Service	40.00	2.07	0.00	700 70	450.40	0.00
Dead+Wind 330 deg -	46.00	-3.87	-6.68	-780.76	453.13	0.33

# **Solution Summary**

	Sui	m of Applied Force	es		Sum of Reaction	າຣ	
Load	PX	' PY	PZ	PX	PY	PZ	% Error
Comb.	K	K	K	K	K	K	
1	0.00	-46.00	0.00	0.00	46.00	0.00	0.000%

		n of Applied Force			Sum of Reaction		
Load	PX	PY	PZ	PX	PY	PZ	% Erroi
Comb.	K	K	K	K	K	K	
2	-0.18	-55.20	-35.47	0.18	55.20	35.47	0.000%
3	-0.18	-41.40	-35.47	0.18	41.40	35.47	0.000%
4	17.50	-55.20	-30.66	-17.50	55.20	30.66	0.000%
5	17.50	-41.40	-30.66	-17.50	41.40	30.66	0.000%
6	30.58	-55.20	-17.54	-30.58	55.20	17.54	0.000%
7	30.58	-41.40	-17.54	-30.58	41.40	17.54	0.000%
8	35.31	-55.20	0.19	-35.31	55.20	-0.19	0.000%
9	35.31	-41.40	0.19	-35.31	41.40	-0.19	0.000%
10	30.64	-55.20	17.76	-30.64	55.20	-17.76	0.000%
11	30.64	-41.40	17.76	-30.64	41.40	-17.76	0.000%
12	17.76	-55.20	30.68	-17.76	55.20	-30.68	0.000%
13	17.76	-41.40	30.68	-17.76	41.40	-30.68	0.000%
14	0.17	-55.20	35.40	-0.17	55.20	-35.40	0.000%
15	0.17	-41.40	35.40	-0.17	41.40	-35.40	0.000%
16	-17.52	-55.20	30.61	17.52	55.20	-30.61	0.000%
17	-17.52	-41.40	30.61	17.52	41.40	-30.61	0.000%
18	-30.49	-55.20	17.56	30.49	55.20	-17.56	0.000%
19	-30.49	-41.40	17.56	30.49	41.40	-17.56	0.000%
20	-35.29	-55.20	-0.26	35.29	55.20	0.26	0.000%
21	-35.29	-41.40	-0.26	35.29	41.40	0.26	0.000%
22	-30.65	-55.20	-17.83	30.65	55.20	17.83	0.000%
23	-30.65	-41.40	-17.83	30.65	41.40	17.83	0.000%
24	-17.81	-55.20	-30.75	17.81	55.20	30.75	0.000%
25	-17.81	-41.40	-30.75	17.81	41.40	30.75	0.000%
26	0.00	-103.94	0.00	0.00	103.94	0.00	0.000%
27	-0.04	-103.94	-10.27	0.04	103.94	10.27	0.000%
28	5.10	-103.94	-8.88	-5.10	103.94	8.88	0.000%
29	8.88	-103.94	-5.10	-8.88	103.94	5.10	0.000%
30	10.25	-103.94	0.04	-10.25	103.94	-0.04	0.000%
31	8.89	-103.94	5.14	-8.89	103.94	-5.14	0.000%
32	5.15	-103.94	8.89	-5.15	103.94	-8.89	0.000%
33	0.04	-103.94	10.26	-0.04	103.94	-10.26	0.000%
34	-5.10	-103.94	8.87	5.10	103.94	-8.87	0.000%
35	-8.86	-103.94	5.10	8.86	103.94	-5.10	0.000%
36	-10.25	-103.94	-0.05	10.25	103.94	0.05	0.000%
37	-8.89	-103.94	-5.15	8.89	103.94	5.15	0.000%
38	-5.16	-103.94	-8.90	5.16	103.94	8.90	0.000%
39	-0.04	-46.00	-7.70	0.04	46.00	7.70	0.000%
40	3.80	-46.00	-6.66	-3.80	46.00	6.66	0.000%
41	6.64	-46.00	-3.81	-6.64	46.00	3.81	0.000%
42	7.67	-46.00	0.04	-7.67	46.00	-0.04	0.000%
43	6.65	-46.00	3.86	-6.65	46.00	-3.86	0.000%
44	3.86	-46.00	6.66	-3.86	46.00	-6.66	0.000%
45	0.04	-46.00	7.68	-0.04	46.00	-7.68	0.000%
46	-3.80	-46.00	6.64	3.80	46.00	-6.64	0.000%
47	-6.62	-46.00	3.81	6.62	46.00	-3.81	0.000%
48	-7.66	-46.00	-0.06	7.66	46.00	0.06	0.000%
49	-6.65	-46.00	-3.87	6.65	46.00	3.87	0.000%
50	-3.87	-46.00	-6.68	3.87	46.00	6.68	0.000%

# **Non-Linear Convergence Results**

Load	Converged?	Number	Displacement	Force
Combination	_	of Cycles	Tolerance	Tolerance
1	Yes	4	0.0000001	0.0000001
2	Yes	5	0.0000001	0.00009813
3	Yes	5	0.0000001	0.00004136
4	Yes	7	0.0000001	0.00012059
5	Yes	6	0.0000001	0.00044063
6	Yes	7	0.0000001	0.00011901
7	Yes	6	0.0000001	0.00043452
8	Yes	5	0.0000001	0.00016704
9	Yes	5	0.0000001	0.00006501
10	Yes	7	0.0000001	0.00011900
11	Yes	6	0.00000001	0.00043350

40	V	7	0.00000004	0.00040040
12 13	Yes	7	0.0000001 0.0000001	0.00012218 0.00044613
	Yes	6		
14	Yes	5	0.00000001	0.00065178
15	Yes	5	0.0000001	0.00029659
16	Yes	7	0.0000001	0.00011773
17	Yes	6	0.0000001	0.00042952
18	Yes	7	0.0000001	0.00011912
19	Yes	6	0.0000001	0.00043522
20	Yes	5	0.0000001	0.00074894
21	Yes	5	0.0000001	0.00033940
22	Yes	7	0.0000001	0.00012254
23	Yes	6	0.0000001	0.00044738
24	Yes	7	0.0000001	0.00011932
25	Yes	6	0.0000001	0.00043430
26	Yes	4	0.0000001	0.0000001
27	Yes	6	0.00010438	0.00080967
28	Yes	7	0.0000001	0.00041480
29	Yes	7	0.0000001	0.00041277
30	Yes	6	0.00010440	0.00080874
31	Yes	7	0.0000001	0.00041535
32	Yes	7	0.0000001	0.00042139
33	Yes	6	0.00010436	0.00080894
34	Yes	7	0.0000001	0.00040951
35	Yes	7	0.0000001	0.00041006
36	Yes	6	0.00010437	0.00080870
37	Yes	7	0.0000001	0.00042217
38	Yes	7	0.0000001	0.00041744
39	Yes	4	0.0000001	0.00040537
40	Yes	5	0.0000001	0.00022937
41	Yes	5	0.0000001	0.00022033
42	Yes	4	0.0000001	0.00036529
43	Yes	5	0.0000001	0.00021894
44	Yes	5	0.0000001	0.00023633
45	Yes	4	0.0000001	0.00044024
46	Yes	5	0.00000001	0.00021278
47	Yes	5	0.00000001	0.00021210
48	Yes	4	0.00000001	0.00042461
49	Yes	5	0.00000001	0.00042401
50	Yes	5	0.00000001	0.00022054
	1 00		0.00000001	3.000 <u>L</u> 200 <del>1</del>

# **Maximum Tower Deflections - Service Wind**

Section	Elevation	Horz.	Gov.	Tilt	Twist
No.		Deflection	Load		
	ft	in	Comb.	0	0
L1	155 - 115.5	34.108	50	1.862	0.003
L2	119.25 - 79.25	20.667	50	1.653	0.002
L3	83.75 - 43.75	10.020	50	1.154	0.001
L4	49 - 0	3.380	50	0.639	0.000

# **Critical Deflections and Radius of Curvature - Service Wind**

Elevation	Appurtenance	Gov. Load	Deflection	Tilt	Twist	Radius of Curvature
ft		Comb.	in	0	0	ft
155.00	APXVTM14-C-120 w/ Mount Pipe	50	34.108	1.862	0.003	35280
153.00	800MHz 2X50W RRH W/FILTER	50	33.328	1.854	0.003	35280
151.00	VHLP1-23	50	32.547	1.847	0.003	35280
143.00	OPA-65R-LCUU-H6 w/ Mount Pipe	50	29.443	1.814	0.003	14700
133.00	AIR -32 B2A/B66AA	50	25.639	1.762	0.002	8017
123.00	MX08FRO665-21 w/ Mount Pipe	50	21.985	1.689	0.002	5513
113.00	LNX-6512DS-T0M w/ Mount Pipe	50	18.546	1.584	0.002	4706

Elevation	Appurtenance	Gov. Load	Deflection	Tilt	Twist	Radius of Curvature
ft		Comb.	in	٥	0	ft
60.00	Side Arm Mount [SO 701-1]	50	5.031	0.796	0.000	3398

# **Maximum Tower Deflections - Design Wind**

Section	Elevation	Horz.	Gov.	Tilt	Twist
No.		Deflection	Load		
	ft	in	Comb.	0	0
L1	155 - 115.5	158.382	24	8.683	0.014
L2	119.25 - 79.25	96.075	24	7.707	0.009
L3	83.75 - 43.75	46.632	24	5.381	0.004
L4	49 - 0	15.737	24	2.977	0.002

# **Critical Deflections and Radius of Curvature - Design Wind**

Elevation	Appurtenance	Gov. Load	Deflection	Tilt	Twist	Radius of Curvature
ft		Comb.	in	0	0	ft
155.00	APXVTM14-C-120 w/ Mount Pipe	24	158.382	8.683	0.014	7912
153.00	800MHz 2X50W RRH W/FILTER	24	154.763	8.648	0.014	7912
151.00	VHLP1-23	24	151.148	8.613	0.013	7912
143.00	OPA-65R-LCUU-H6 w/ Mount Pipe	24	136.760	8.461	0.012	3294
133.00	AIR -32 B2A/B66AA	24	119.131	8.217	0.010	1794
123.00	MX08FRO665-21 w/ Mount Pipe	24	102.188	7.872	0.009	1230
113.00	LNX-6512DS-T0M w/ Mount Pipe	24	86.235	7.383	0.008	1045
60.00	Side Arm Mount [SO 701-1]	24	23.419	3.707	0.002	736

# **Compression Checks**

## Pole Design Data

Section No.	Elevation	Size	L	Lu	KI/r	Α	$P_u$	φP <sub>n</sub>	Ratio P <sub>u</sub>
	ft		ft	ft		in²	K	K	$\frac{-\frac{a}{\phi P_n}}{\phi P_n}$
L1	155 - 115.5 (1)	TP29.308x22x0.25	39.50	0.00	0.0	22.507	-16.49	1215.38	0.014
L2	115.5 - 79.25 (2)	TP35.514x28.114x0.313	40.00	0.00	0.0	34.090	-27.55	1994.25	0.014
L3	79.25 - 43.75 (3)	TP41.456x34.057x0.375	40.00	0.00	0.0	47.741	-37.50	2792.83	0.013
L4	43.75 - 0 (4)	TP48.8x39.735x0.438	49.00	0.00	0.0	67.157	-55.16	3928.71	0.014

## **Pole Bending Design Data**

Section	Elevation	Size	M <sub>ux</sub>	$\phi M_{nx}$	Ratio	M <sub>uy</sub>	$\phi M_{nv}$	Ratio
No.					M <sub>ux</sub>		. ,	$M_{uy}$
	ft		kip-ft	kip-ft	$\phi M_{nx}$	kip-ft	kip-ft	$\phi M_{ny}$
L1	155 - 115.5 (1)	TP29.308x22x0.25	465.62	867.63	0.537	0.00	867.63	0.000

Section	Elevation	Size	M <sub>ux</sub>	$\phi M_{nx}$	Ratio	$M_{uy}$	$\phi M_{ny}$	Ratio
No.	ft		kip-ft	kip-ft	$\frac{M_{ux}}{\phi M_{nx}}$	kip-ft	kip-ft	$\frac{M_{uy}}{\phi M_{ny}}$
L2	115.5 - 79.25	TP35.514x28.114x0.313	1437.03	1720.89	0.835	0.00	1720.89	0.000
1.0	(2)	TD44_450::04_057::0_075	0500.00	0000 07	0.000	0.00	0000 07	0.000
L3	79.25 - 43.75 (3)	TP41.456x34.057x0.375	2520.32	2833.97	0.889	0.00	2833.97	0.000
L4	43.75 - 0 (4)	TP48.8x39.735x0.438	4199.76	4763.74	0.882	0.00	4763.74	0.000


	Pole Shear Design Data										
Section No.	Elevation	Size	Actual V <sub>u</sub>	φV <sub>n</sub>	Ratio V <sub>u</sub>	Actual T <sub>u</sub>	φ <i>T</i> <sub>n</sub>	Ratio T <sub>u</sub>			
	ft		K	K	$\phi V_n$	kip-ft	kip-ft	$\overline{\phi T_n}$			
L1	155 - 115.5 (1)	TP29.308x22x0.25	22.54	364.61	0.062	0.51	905.70	0.001			
L2	115.5 - 79.25 (2)	TP35.514x28.114x0.313	29.63	598.28	0.050	1.36	1800.73	0.001			
L3	79.25 - 43.75 (3)	TP41.456x34.057x0.375	32.61	837.85	0.039	1.46	2943.04	0.000			
L4	43.75 - 0 (4)	TP48.8x39.735x0.438	35.60	1178.61	0.030	1.46	4991.82	0.000			

Pole Interaction Design Data									
Section No.	Elevation	Ratio P <sub>u</sub>	Ratio M <sub>ux</sub>	Ratio M <sub>uy</sub>	Ratio V <sub>u</sub>	Ratio T <sub>u</sub>	Comb. Stress	Allow. Stress	Criteria
	ft	$\phi P_n$	$\phi M_{nx}$	$\phi M_{ny}$	$\phi V_n$	$\phi T_n$	Ratio	Ratio	
L1	155 - 115.5 (1)	0.014	0.537	0.000	0.062	0.001	0.554	1.050	4.8.2
L2	115.5 - 79.25 (2)	0.014	0.835	0.000	0.050	0.001	0.851	1.050	4.8.2
L3	79.25 - 43.75 (3)	0.013	0.889	0.000	0.039	0.000	0.904	1.050	4.8.2
L4	43.75 - 0 (4)	0.014	0.882	0.000	0.030	0.000	0.897	1.050	4.8.2

	Section Capacity Table							
Section No.	Elevation ft	Component Type	Size	Critical Element	P K	øP <sub>allow</sub> K	% Capacity	Pass Fail
L1	155 - 115.5	Pole	TP29.308x22x0.25	1	-16.49	1276.15	52.8	Pass
L2	115.5 - 79.25	Pole	TP35.514x28.114x0.313	2	-27.55	2093.96	81.1	Pass
L3	79.25 - 43.75	Pole	TP41.456x34.057x0.375	3	-37.50	2932.47	86.1	Pass
L4	43.75 - 0	Pole	TP48.8x39.735x0.438	4	-55.16	4125.15	85.4	Pass
							Summary	
						Pole (L3)	86.1	Pass
						RATING =	86.1	Pass

# APPENDIX B BASE LEVEL DRAWING





# APPENDIX C ADDITIONAL CALCULATIONS

## **Monopole Base Plate Connection**




Site Info					
BU#	876347				
Site Name	BUCKLAND MALL				
Order #	556605 Rev 1				

Analysis Considerations				
TIA-222 Revision	Н			
Grout Considered:	No			
I <sub>ar</sub> (in)	0.75			

Applied Loads				
Moment (kip-ft)	4199.76			
Axial Force (kips)	55.16			
Shear Force (kips)	35.60			

<sup>\*</sup>TIA-222-H Section 15.5 Applied



## **Connection Properties Anchor Rod Data**

(16) 2-1/4" ø bolts (A615-75 N; Fy=75 ksi, Fu=100 ksi) on 56" BC Anchor Spacing: 6 in

**Base Plate Data** 56" W x 3.25" Plate (A572-50; Fy=50 ksi, Fu=65 ksi); Clip: 6 in

#### Stiffener Data

N/A

## Pole Data


48.8" x 0.4375" 18-sided pole (A607-65; Fy=65 ksi, Fu=80 ksi)

· ·	a., 5.5 results	
Anchor Rod Summary		(units of kips, kip-in)
Pu_t = 221.39	φPn_t = 243.75	Stress Rating
Vu = 2.23	φVn = 149.1	86.5%
Mu = n/a	φMn = n/a	Pass
Base Plate Summary		
Max Stress (ksi):	31.12	(Flexural)
Allowable Stress (ksi):	45	
Stress Rating:	65.9%	Pass

CCIplate - Version 4.1.1 Analysis Date: 5/29/2021

## **Pier and Pad Foundation**

BU # : 876347 Site Name: BUCKLAND MALL App. Number: 556605 Rev 1





Top & Bot. Pad Rein. Different?:	
Block Foundation?:	
Rectangular Pad?:	

Superstructure Analysis Reactions					
Compression, P <sub>comp</sub> :	55.2	kips			
Base Shear, Vu_comp:	35.54	kips			
Moment, <b>M</b> <sub>u</sub> :	4199.75	ft-kips			
Tower Height, <b>H</b> :	155	ft			
BP Dist. Above Fdn, <b>bp</b> <sub>dist</sub> :	3	in			

Pier Properties		
Pier Shape:	Square	
Pier Diameter, dpier:	7	ft
Ext. Above Grade, E:	0.5	ft
Pier Rebar Size, <b>Sc</b> :	11	
Pier Rebar Quantity, mc:	32	
Pier Tie/Spiral Size, <b>St</b> :	5	
Pier Tie/Spiral Quantity, mt:	12	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, cc <sub>pier</sub> :	3	in

Pad Properties				
Depth, <b>D</b> :	10	ft		
Pad Width, <b>W</b> <sub>1</sub> :	23	ft		
Pad Thickness, T:	3	ft		
Pad Rebar Size (Bottom dir. 2), Sp <sub>2</sub> :	9			
Pad Rebar Quantity (Bottom dir. 2), mp <sub>2</sub> :	34			
Pad Clear Cover cc	3	in		

Material Properties					
Rebar Grade, Fy:	60	ksi			
Concrete Compressive Strength, F'c:	3	ksi			
Dry Concrete Density, δ <b>c</b> :	150	pcf			

Soil Properties				
Total Soil Unit Weight, γ:	115	pcf		
Ultimate Net Bearing, Qnet:	30.000	ksf		
Cohesion, Cu:	0.000	ksf		
Friction Angle, $oldsymbol{arphi}$ :	30	degrees		
SPT Blow Count, N <sub>blows</sub> :	15			
Base Friction, $\mu$ :	0.45			
Neglected Depth, N:	3.50	ft		
Foundation Bearing on Rock?	No			
Groundwater Depth, gw:	N/A	ft		

Foundation Analysis Checks					
	Capacity	Demand	Rating*	Check	
Lateral (Sliding) (kips)	405.43	35.54	8.3%	Pass	
Bearing Pressure (ksf)	23.36	3.23	13.8%	Pass	
Overturning (kip*ft)	8517.91	4581.81	53.8%	Pass	
Pier Flexure (Comp.) (kip*ft)	7583.52	4466.30	56.1%	Pass	
Pier Compression (kip)	23390.64	121.35	0.5%	Pass	
Pad Flexure (kip*ft)	4568.38	1659.79	34.6%	Pass	
Pad Shear - 1-way (kips)	709.93	278.50	37.4%	Pass	
Pad Shear - 2-way (Comp) (ksi)	0.164	0.045	26.1%	Pass	
Flexural 2-way (Comp) (kip*ft)	6333.75	2679.78	40.3%	Pass	

\*Rating per TIA-222-H Section 15.5

Structural Rating*:	56.1%
Soil Rating*:	53.8%

<--Toggle between Gross and Net



#### Address:


No Address at This Location


# **ASCE 7 Hazards Report**

Standard: ASCE/SEI 7-10 Elevation: 195.5 ft (NAVD 88)

Risk Category: || Latitude: 41.805

Soil Class: D - Stiff Soil Longitude: -72.533611





## Wind

#### Results:

Wind Speed: 123 Vmph 125 Vmph per Jurisdiction

 10-year MRI
 77 Vmph

 25-year MRI
 87 Vmph

 50-year MRI
 93 Vmph

 100-year MRI
 101 Vmph

Data Source: ASCE/SEI 7-10, Fig. 26.5-1A and Figs. CC-1–CC-4, incorporating errata of

March 12, 2014

Date Accessed: Mon Oct 26 2020

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.


Mountainous terrain, gorges, ocean promontories, and special wind regions should be examined for unusual wind conditions.



## **Seismic**

Site Soil Class: Results:	D - Stiff Soil			
S <sub>s</sub> :	0.178	S <sub>DS</sub> :	0.19	
$S_1$ :	0.064	S <sub>D1</sub> :	0.102	
Fa:	1.6	T <sub>L</sub> :	6	
F <sub>v</sub> :	2.4	PGA:	0.089	
S <sub>MS</sub> :	0.285	PGA <sub>M</sub> :	0.143	
S <sub>M1</sub> :	0.153	F <sub>PGA</sub> :	1.6	
		1.	1	

## Seismic Design Category B



Data Accessed: Mon Oct 26 2020

Date Source: USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating

Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with

ASCE/SEI 7-10 Ch. 21 are available from USGS.



#### **Ice**

Results:

Ice Thickness:1.00 in.Concurrent Temperature:5 F

Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Mon Oct 26 2020

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

# Exhibit E

**Mount Analysis** 

Date: August 2, 2021

Darcy Tarr Crown Castle 3530 Toringdon Way, Suite 300 Charlotte, NC 28277 (704) 405-6589



Trylon 1825 W. Walnut Hill Lane, Suite 302 Irving, TX 75038 214-930-1730

Subject: Mount Replacement Analysis Report

Carrier Designation: Dish Network Dish 5G

Carrier Site Number:BOBDL00092ACarrier Site Name:CT-CCI-T-876347

Crown Castle Designation: Crown Castle BU Number: 876347

Crown Castle Site Name:Buckland MallCrown Castle JDE Job Number:650078Crown Castle Order Number:556605 Rev. 1

Crown Castle Order Number. 550005 nev.

**Engineering Firm Designation:** Trylon Report Designation: 189041

Site Data: 53 Slater Street, Manchester, Hartford County, CT, 06040

Latitude 41°48'18.00" Longitude -72°32'1.00"

Structure Information: Tower Height & Type: 155.0 ft Monopole

Mount Elevation: 123.0 ft
Mount Type: 8.0 ft Platform

Dear Darcy Tarr,

Trylon is pleased to submit this "Mount Replacement Analysis Report" to determine the structural integrity of Dish Network's antenna mounting system with the proposed appurtenance and equipment addition on the abovementioned supporting tower structure. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point for fall protection or rigging is not part of this document.


The purpose of the analysis is to determine acceptability of the mount stress level. Based on our analysis we have determined the mount stress level to be:

Platform Sufficient\*
\*Sufficient upon completion of the changes listed in the 'Recommendations' section of this report.

This analysis utilizes an ultimate 3-second gust wind speed of 125 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Mount analysis prepared by: Aura Baltoiu

Respectfully Submitted by: Cliff Abernath, P.E.



#### **TABLE OF CONTENTS**

## 1) INTRODUCTION

## 2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

## 3) ANALYSIS PROCEDURE

Table 2 - Documents Provided

- 3.1) Analysis Method
- 3.2) Assumptions

## 4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

4.1) Recommendations

## 5) APPENDIX A

Wire Frame and Rendered Models

### 6) APPENDIX B

Software Input Calculations

### 7) APPENDIX C

Software Analysis Output

## 8) APPENDIX D

**Additional Calculations** 

## 9) APPENDIX E

Supplemental Drawings

## 1) INTRODUCTION

This is a proposed 3 sector 8.0 ft Platform, designed by Commscope.

### 2) ANALYSIS CRITERIA

Building Code: 2015 IBC / 2018 CTSBC

TIA-222 Revision: TIA-222-H

Risk Category:

Ultimate Wind Speed: 125 mph

**Exposure Category:** Topographic Factor at Base: 1.00 Topographic Factor at Mount: 1.00 Ice Thickness: 2.0 in Wind Speed with Ice: 50 mph Seismic S<sub>s</sub>: 0.178 Seismic S<sub>1</sub>: 0.064 Live Loading Wind Speed: 30 mph Man Live Load at Mid/End-Points: 250 lb Man Live Load at Mount Pipes: 500 lb

Table 1 - Proposed Equipment Configuration

	Table 1 110pooca =qaipinont oomigatation					
	Mount nterline (ft)	Antenna Centerline (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Mount / Modification Details
			3	JMA WIRELESS	MX08FRO665-21	0.0 ft Dietform
123.0		123.0	3	FUJITSU	TA08025-B604	8.0 ft Platform [Commscope, MC-
123.0	123.0	3	FUJITSU	TA08025-B605	PK8-C1	
			1	RAYCAP	RDIDC-9181-PF-48	PRO-CJ

#### 3) ANALYSIS PROCEDURE

**Table 2 - Documents Provided** 

. day to 2 documents to 1 documents and 1 docu						
Document	Remarks	Reference	Source			
Crown Application	Dish Network Application	556605, Rev.1	CCI Sites			
Mount Manufacturer Drawings	Commscope	MC-PK8-C	Trylon			

## 3.1) Analysis Method

RISA-3D (Version 17.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the antenna mounting system and calculate member stresses for various loading cases.

A tool internally developed, using Microsoft Excel, by Trylon was used to calculate wind loading on all appurtenances, dishes, and mount members for various load cases. Selected output from the analysis is included in Appendix B.

This analysis was performed in accordance with Crown Castle's ENG-SOW-10208 *Tower Mount Analysis* (Revision B).

## 3.2) Assumptions

- 1) The antenna mounting system was properly fabricated, installed and maintained in good condition in accordance with its original design and manufacturer's specifications.
- 2) The configuration of antennas, mounts, and other appurtenances are as specified in Table 1 and the referenced drawings.
- 3) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 4) The analysis will be required to be revised if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
- 5) Prior structural modifications to the tower mounting system are assumed to be installed as shown per available data.
- 6) Steel grades have been assumed as follows, unless noted otherwise:

Channel, Solid Round, Angle, Plate

HSS (Rectangular)

Pipe

ASTM A36 (GR 36)

ASTM A500 (GR B-46)

ASTM A335

Connection Bolts ASTM A325

This analysis may be affected if any assumptions are not valid or have been made in error. Trylon should be notified to determine the effect on the structural integrity of the antenna mounting system.

### 4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity (Platform, All Sectors)

	Cwitical					
Notes	Component	Critical Member	Centerline (ft)	% Capacity	Pass / Fail	
	Mount Pipe(s)	MP1		38.9	Pass	
1,2	Horizontal(s)	H1		10.4	Pass	
	Standoff(s)	SA2	]	61.3	Pass	
	Bracing(s)	PB2	123.0	45.4	Pass	
	Handrail(s)	M19		15.5	Pass	
	Corner Angle(s)	CP2		6.0	Pass	
	Plate(s)	CP5		25.4	Pass	
	Mount Connection(s)	-		24.5	Pass	

Structure Rating (max from all components) =	61.3%
--	-------

Notes:

2) Rating per TIA-222-H, Section 15.5

<sup>1)</sup> See additional documentation in "Appendix C - Software Analysis Output" for calculations supporting the % capacity consumed.

## 4.1) Recommendations


The mount has sufficient capacity to carry the proposed loading configuration. In order for the results of the analysis to be considered valid, the proposed mount listed below must be installed.

1. Commscope, MC-PK8-C.

No structural modifications are required at this time, provided that the above-listed changes are implemented.

# APPENDIX A WIRE FRAME AND RENDERED MODELS






#### **Envelope Only Solution**

Trylon		SK - 1
AB	876347	July 28, 2021 at 2:49 PM
189041		876347.r3d





#### **Envelope Only Solution**

Trylon		SK - 2
AB	876347	July 28, 2021 at 2:49 PM
189041		876347.r3d

# APPENDIX B SOFTWARE INPUT CALCULATIONS




#### Address:


No Address at This Location

# ASCE 7 Hazards Report

Standard: ASCE/SEI 7-10 Elevation: 195.35 ft (NAVD 88)

Risk Category: || Latitude: 41.804971 Soil Class: D - Stiff Soil Longitude: -72.533585






Wed Jul 28 2021



## **Seismic**

Site Soil Class: Results:	D - Stiff Soil			
S <sub>S</sub> :	0.178	$S_{ extsf{DS}}$ :	0.19	
$S_1$ :	0.064	S <sub>D1</sub> :	0.102	
Fa:	1.6	T <sub>L</sub> :	6	
F <sub>v</sub> :	2.4	PGA:	0.089	
$S_{MS}$ :	0.285	PGA <sub>M</sub> :	0.143	
S <sub>M1</sub> :	0.153	F <sub>PGA</sub> :	1.6	
		1 .	1	

#### Seismic Design Category B



Data Accessed: Wed Jul 28 2021

Date Source: USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating

Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with

ASCE/SEI 7-10 Ch. 21 are available from USGS.



#### **Ice**

Results:

Ice Thickness: 1.00 in.

Concurrent Temperature: 5 F

Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Wed Jul 28 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.



## TIA LOAD CALCULATOR 2.0

PROJECT DATA		
Job Code:	189041	
Carrier Site ID:	BOBDL00092A	
Carrier Site Name:	CT-CCI-T-876347	

CODES AND STANDARDS		
Building Code:	2015 IBC	
Local Building Code:	2018 CSBC	
Design Standard:	TIA-222-H	

0-5110-115				
STRUCTURE	STRUCTURE DETAILS			
Mount Type:	Platform			
Mount Elevation:	123.0	ft.		
Number of Sectors:	3			
Structure Type:	Monopole			
Structure Height:	155.0	ft.		

ANALYSIS CRITERIA			
Structure Risk Category:	II		
Exposure Category:	С		
Site Class:	D - Stiff Soil		
Ground Elevation:	195.35	ft.	

TOPOGRAPHIC DATA			
Topographic Category:	1.00		
Topographic Feature:	N/A		
Crest Point Elevation:	0.00	ft.	
Base Point Elevation:	0.00	ft.	
Crest to Mid-Height (L/2):	0.00	ft.	
Distance from Crest (x):	0.00	ft.	
Base Topo Factor (K <sub>zt</sub> ):	1.00		
Mount Topo Factor (K <sub>zt</sub> ):	1.00		

WIND PARAMETERS			
Design Wind Speed:	125	mph	
Wind Escalation Factor (K <sub>s</sub> ):	1.00		
Velocity Coefficient (K <sub>z</sub> ):	1.32		
Directionality Factor (K <sub>d</sub> ):	0.95		
Gust Effect Factor (Gh):	1.00		
Shielding Factor (K <sub>a</sub> ):	0.90		
Velocity Pressure (q <sub>z</sub> ):	49.88	psf	

ICE PARAMETERS			
Design Ice Wind Speed:	50	mph	
Design Ice Thickness (t <sub>i</sub> ):	2.00	in	
Importance Factor (I <sub>i</sub> ):	1.00		
Ice Velocity Pressure (qzi):	49.88	psf	
Mount Ice Thickness (tiz):	2.28	in	

WIND STRUCTURE CALCULATIONS		
Flat Member Pressure:	89.79	psf
Round Member Pressure:	53.87	psf
Ice Wind Pressure:	7.44	psf

SEISMIC PARAMETERS		
Importance Factor (I <sub>e</sub> ):	1.00	
Short Period Accel .(S <sub>s</sub> ):	0.178	g
1 Second Accel (S <sub>1</sub> ):	0.064	g
Short Period Des. (S <sub>DS</sub> ):	0.19	g
1 Second Des. (S <sub>D1</sub> ):	0.10	g
Short Period Coeff. (F <sub>a</sub> ):	1.60	
1 Second Coeff. (F <sub>v</sub> ):	2.40	
Response Coefficient (Cs):	0.09	
Amplification Factor (A <sub>S</sub> ):	1.20	

# **LOAD COMBINATIONS [LRFD]**

#	Description
1	1.4DL
2	1.2DL + 1WL 0 AZI
3	1.2DL + 1WL 30 AZI
4	1.2DL + 1WL 45 AZI
5	1.2DL + 1WL 60 AZI
6	1.2DL + 1WL 90 AZI
7	1.2DL + 1WL 120 AZI
8	1.2DL + 1WL 135 AZI
9	1.2DL + 1WL 150 AZI
10	1.2DL + 1WL 180 AZI
11	1.2DL + 1WL 210 AZI
12	1.2DL + 1WL 225 AZI
13	1.2DL + 1WL 240 AZI
14	1.2DL + 1WL 270 AZI
15	1.2DL + 1WL 300 AZI
16	1.2DL + 1WL 315 AZI
17	1.2DL + 1WL 330 AZI
18	0.9DL + 1WL 0 AZI
19	0.9DL + 1WL 30 AZI
20	0.9DL + 1WL 45 AZI
21	0.9DL + 1WL 60 AZI
22	0.9DL + 1WL 90 AZI
23	0.9DL + 1WL 120 AZI
24	0.9DL + 1WL 135 AZI
25	0.9DL + 1WL 150 AZI
26	0.9DL + 1WL 180 AZI
27	0.9DL + 1WL 210 AZI
28	0.9DL + 1WL 225 AZI
29	0.9DL + 1WL 240 AZI
30	0.9DL + 1WL 270 AZI 0.9DL + 1WL 300 AZI
31	
	0.9DL + 1WL 315 AZI
33	0.9DL + 1WL 330 AZI
34	1.2DL + 1DLi + 1WLi 0 AZI
35	1.2DL + 1DLi + 1WLi 30 AZI
36	1.2DL + 1DLi + 1WLi 45 AZI
37	1.2DL + 1DLi + 1WLi 60 AZI
38	1.2DL + 1DLi + 1WLi 90 AZI
39	1.2DL + 1DLi + 1WLi 120 AZI
40	1.2DL + 1DLi + 1WLi 135 AZI
41	1.2DL + 1DLi + 1WLi 150 AZI

#	Description
42	1.2DL + 1DLi + 1WLi 180 AZI
43	1.2DL + 1DLi + 1WLi 210 AZI
44	1.2DL + 1DLi + 1WLi 225 AZI
45	1.2DL + 1DLi + 1WLi 240 AZI
46	1.2DL + 1DLi + 1WLi 270 AZI
47	1.2DL + 1DLi + 1WLi 300 AZI
48	1.2DL + 1DLi + 1WLi 315 AZI
49	1.2DL + 1DLi + 1WLi 330 AZI
50	(1.2+0.2Sds) + 1.0E 0 AZI
51	(1.2+0.2Sds) + 1.0E 30 AZI
52	(1.2+0.2Sds) + 1.0E 45 AZI
53	(1.2+0.2Sds) + 1.0E 60 AZI
54	(1.2+0.2Sds) + 1.0E 90 AZI
55	(1.2+0.2Sds) + 1.0E 120 AZI
56	(1.2+0.2Sds) + 1.0E 135 AZI
57	(1.2+0.2Sds) + 1.0E 150 AZI
58	(1.2+0.2Sds) + 1.0E 180 AZI
59	(1.2+0.2Sds) + 1.0E 210 AZI
60	(1.2+0.2Sds) + 1.0E 225 AZI
61	(1.2+0.2Sds) + 1.0E 240 AZI
62	(1.2+0.2Sds) + 1.0E 270 AZI
63	(1.2+0.2Sds) + 1.0E 300 AZI
64	(1.2+0.2Sds) + 1.0E 315 AZI
65	(1.2+0.2Sds) + 1.0E 330 AZI
66	(0.9-0.2Sds) + 1.0E 0 AZI
67	(0.9-0.2Sds) + 1.0E 30 AZI
68	(0.9-0.2Sds) + 1.0E 45 AZI
69	(0.9-0.2Sds) + 1.0E 60 AZI
70	(0.9-0.2Sds) + 1.0E 90 AZI
71	(0.9-0.2Sds) + 1.0E 120 AZI
72	(0.9-0.2Sds) + 1.0E 135 AZI
73	(0.9-0.2Sds) + 1.0E 150 AZI
74	(0.9-0.2Sds) + 1.0E 180 AZI
75	(0.9-0.2Sds) + 1.0E 210 AZI
76	(0.9-0.2Sds) + 1.0E 225 AZI
77	(0.9-0.2Sds) + 1.0E 240 AZI
78	(0.9-0.2Sds) + 1.0E 270 AZI
79	(0.9-0.2Sds) + 1.0E 300 AZI
80	(0.9-0.2Sds) + 1.0E 315 AZI
81	(0.9-0.2Sds) + 1.0E 330 AZI
82-88	1.2D + 1.5 Lv1

#	Description
89	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP1
90	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP1
91	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP1
92	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP1
93	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP1
94	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP1
95	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP1
96	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP1
97	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP1
98	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP1
99	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP1
100	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP1
101	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP1
102	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP1
103	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP1
104	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP1
105	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP2
106	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP2
107	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP2
108	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP2
109	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP2
110	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP2
111	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP2
112	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP2
113	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP2
114	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP2
115	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP2
116	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP2
117	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP2
118	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP2
119	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP2
120	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP2

#	Description
121	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP3
122	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP3
123	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP3
124	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP3
125	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP3
126	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP3
127	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP3
128	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP3
129	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP3
130	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP3
131	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP3
132	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP3
133	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP3
134	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP3
135	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP3
136	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP3
137	1.2D + 1.5Lm + 1.0Wm 0 AZI - MP4
138	1.2D + 1.5Lm + 1.0Wm 30 AZI - MP4
139	1.2D + 1.5Lm + 1.0Wm 45 AZI - MP4
140	1.2D + 1.5Lm + 1.0Wm 60 AZI - MP4
141	1.2D + 1.5Lm + 1.0Wm 90 AZI - MP4
142	1.2D + 1.5Lm + 1.0Wm 120 AZI - MP4
143	1.2D + 1.5Lm + 1.0Wm 135 AZI - MP4
144	1.2D + 1.5Lm + 1.0Wm 150 AZI - MP4
145	1.2D + 1.5Lm + 1.0Wm 180 AZI - MP4
146	1.2D + 1.5Lm + 1.0Wm 210 AZI - MP4
147	1.2D + 1.5Lm + 1.0Wm 225 AZI - MP4
148	1.2D + 1.5Lm + 1.0Wm 240 AZI - MP4
149	1.2D + 1.5Lm + 1.0Wm 270 AZI - MP4
150	1.2D + 1.5Lm + 1.0Wm 300 AZI - MP4
151	1.2D + 1.5Lm + 1.0Wm 315 AZI - MP4
152	1.2D + 1.5Lm + 1.0Wm 330 AZI - MP4

<sup>\*</sup>This page shows an example of maintenance loads for (4) pipes, the number of mount pipe LCs may vary per site

# **EQUIPMENT LOADING**

Appurtenance Name/Location	Qty.	Elevation [ft]		EPA <sub>N</sub> (ft2)	EPA <sub>T</sub> (ft2)	Weight (lbs)
MX08FRO665-21	3	123	No Ice	8.01	3.21	82.50
MP2/MP5/MP8, 0/120/240			w/ Ice	10.18	5.12	392.28
TA08025-B604	3	123	No Ice	1.96	0.98	63.90
MP2/MP5/MP8, 0/120/240			w/ Ice	2.54	1.43	99.68
TA08025-B605	3	123	No Ice	1.96	1.13	75.00
MP2/MP5/MP8, 0/120/240			w/ Ice	2.54	1.60	105.88
RDIDC-9181-PF-48	1	123	No Ice	2.01	1.17	21.85
MP1, 0			w/ Ice	2.60	1.66	104.44
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			

# **EQUIPMENT LOADING [CONT.]**

Appurtenance Name/Location	Qty.	Elevation [ft]		EPA <sub>N</sub> (ft2)	EPA <sub>T</sub> (ft2)	Weight (lbs)
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
			w/ Ice			
			No Ice			
	-		w/ Ice			
			No Ice			
			w/ Ice			

# **EQUIPMENT WIND CALCULATIONS**

Appurtenance Name	Qty.	Elevation [ft]	<b>K</b> <sub>zt</sub>	K <sub>z</sub>	<b>K</b> <sub>d</sub>	t <sub>d</sub>	<b>q</b> z [psf]	<b>q</b> <sub>zi</sub> [psf]
MX08FRO665-21	3	123	1.00	1.32	0.95	2.28	49.88	7.98
TA08025-B604	3	123	1.00	1.32	0.95	2.28	49.88	7.98
TA08025-B605	3	123	1.00	1.32	0.95	2.28	49.88	7.98
RDIDC-9181-PF-48	1	123	1.00	1.32	0.95	2.28	49.88	7.98

# **EQUIPMENT LATERAL WIND FORCE CALCULATIONS**

Appurtenance Name	Qty.		0° 180°	30° 210°	60° 240°	90° 270°	120° 300°	150° 330°
MX08FRO665-21	3	No Ice	359.60	197.98	305.73	144.11	305.73	197.98
MP2/MP5/MP8, 0/120/240		w/ Ice	73.14	45.86	64.05	36.77	64.05	45.86
TA08025-B604	3	No Ice	88.15	55.07	77.12	44.05	77.12	55.07
MP2/MP5/MP8, 0/120/240		w/ Ice	18.25	12.28	16.26	10.30	16.26	12.28
TA08025-B605	3	No Ice	88.15	60.07	78.79	50.71	78.79	60.07
MP2/MP5/MP8, 0/120/240		w/ Ice	18.25	13.18	16.56	11.50	16.56	13.18
RDIDC-9181-PF-48	1	No Ice	90.32	61.91	80.85	52.44	80.85	61.91
MP1, 0		w/ Ice	18.66	13.59	16.97	11.90	16.97	13.59
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						

## **EQUIPMENT LATERAL WIND FORCE CALCULATIONS [CONT.]**

Appurtenance Name	Qty.		0° 180°	30° 210°	60° 240°	90° 270°	120° 300°	150° 330°
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						
		No Ice						
		w/ Ice						

# **EQUIPMENT SEISMIC FORCE CALCULATIONS**

Appurtenance Name	Qty.	Elevation [ft]	Weight [lbs]	<b>F</b> p [lbs]
MX08FRO665-21	3	123	82.5	9.40
TA08025-B604	3	123	63.9	7.28
TA08025-B605	3	123	75	8.54
RDIDC-9181-PF-48	1	123	21.85	2.49

# APPENDIX C SOFTWARE ANALYSIS OUTPUT

## fl, `cVUŁ'A cXY 'GYltijb[ g

Öãa]  æê ÁÙ^&cã[}•Á[¦ÁT^{ à^¦ÁÔæ}&•	ÍÁ
Tæ¢ÁQe^¦}æţÁÛ^&cā[}•Á[¦ÁT^{ à^¦ÁÔæ}&•	JΪÁ
Q&  å^AU@æ\AÖ^-{   { æ@]} N	ΫΛ•
Ó,&¦^æ•^Áræājā, *ÁÔæ) æ&ãcÂ;¦ÁY ā,åÑ	ΫΛ•
Q&  å^A/ æ  a * Ñ	ΫΛ•
V¦a)•ÁŠ[anàÁÔć; }ÁQ≀c^¦•^&cā]*Á∀[[åÁ∀a⊯ļÑ	Ÿ^•
Off^æ/S[æåÁT^•@/QjaaGD	FII
T^\*^Ā/[  ^\a) &^Á(a) D	ÈG
ÚĒÖ^ æðŌĒ æþ. • ã Á/[ ^¦æ} &^	€Ě€Ã
Q &  ` a^ ÁÚÉÖ   (æÁ; ¦Á æ  • Ñ	ΫΛ•
OE of { aeaa8ae  ^Áoo^   aeo^Ái   ca-} ^••Ái   Ái ae  •Ñ	Ÿ^•
Tæ¢Å@^¦æ@a[}•Á[¦ÁYæ ÁÙ@ã-}^••	Н
Ö laq ãĉ Á028&^  ^læaaaaaa } ÁÇaa Bo^& a GD	HÍÌÈ
YællÁT^•@ÁUā^ÁÇajĎ	G
Òā ^} •[  ' cā } ÁÔ[ ) ç^  * ^} &^ Á/   ÞÁÇF ÐÐ	1
X^¦ca8ædAOt¢ã	Z
Ő [[àæḥÁT^{ à^¦ÁU¦ã^}cææā[}ÁÚ æ}^	ÝŸ
Ùææ&ÁÚ[  ç^¦	Ù]æ•^ÁŒ&^ ^¦æe^å
Ö^}æ{ a&ÁÚ[  ç^	OĒ&^ ^¦æe^åÂÛ[ ç^¦
7 ( 1.0	
P[cÁÜ[   ^åÁÛc^^ ÁÔ[ å^	OEQÙÔÁFÍc@QHÍ€ËFÎDMÁSÜØÖ
Œåbੱ•œĤĴœÃ-}^••Ñ	Ÿ^• <b>@</b> \¦æāc^D
ÜQÜQEÔ[}}^&ca[}ÁÔ[å^	OEQÙŐÁFÍ c@ÓHÎ €ÉFÎ DIKÁSÜØÖ
Ô[  åÁØ[ ¦ { ^åÁÛc^  ÁÔ[ å^	OED)QÛF€€ÊFGKÊSÜØÖ
Y [ [ å ÆO[ å^	CEY ÖÁÞÖÙÉFÍ KÁDEÙÖ
Y [ [ åÁV^{ ] ^  æc	ŁÁF€€Ø
Ô[}& ^&\\delta[a^	OĐÔ (ÁHFÌ ÉFI
Tæ[}¦^ÂÔ[å^	OEÔQà H€ÉFHKÁÙ¢^} *c@
OF { a { AÔ[ a^	OEDFÁCIÉÖT FÉF€KÁSÜØÖÁFÁÓ ãåãj*
Ùæ∄  ^••ÂÛc^^ ÂÔ[ å^	OEDÙÔÁFI c@QHÎ €ËF€DMÂSÜØÖ
Œabŏ•œÛcã-} ^••Ñ	Ÿ^• <b>(Q1</b> \tema_r^D
Þ`{ à^¦Á; ÁÛ@^æÁÜ^*ã[}•	
Ü^* [4] } ÁÛ] æ&aj *ÁQ & ^{ ^} Ø [4] D	1
Óãæ¢ãæ∮Ô[ `{} ÁT^cQ[å	Ò¢æ&cÁQ;c^*¦æða[}
Úæl{^ÁÓ^œæÁØæ&q¦ÁÇÚÔOED	ÊÍ
Ô[ } &\^&\AUd^•• ÁO [ &\	Ü^&ca); * *  æ
W•^ÂÔ¦æ&\^åÂÛ^&æ{ } }•Ñ	Ϋ́Λ•
W•^ÁÔ¦æ&\^åÁÙ^&@aaa }•ÁÙ æàÑ	ΫΛ•
ÓæáÁØlæ(ã) *ÁVæl}ã) *•Ñ	Þ[
W, `•^åÆZ[¦&^ÁYæ}}ā, *•Ñ	ΫΛ•
TāļÁFÁÓæÁÖãæ(EÀÚ]æ&ā;*Ñ	Þ[
Ô[ } &\^&\AÜ\^àæ\AÙ\^c	ÜÒӌܴÙÒV´ŒÙVTŒÎFÍ
T \$\hat{A} A\hat{\hat{\O}} c^{\phi}  \hat{A}   \hat{\O}    \cdot \{ \}	F
Tág ÁÑ ÁÙ c^ Á [ ¦ÁÔ [   ° { ´}	

### fļ`cVUŁAcXY`GYhhjb[gž7cbhjbi YX

Ù^ã{ ã&ÁÔ[ å^	OĐÔÔÁ ËF€
Ù^ã{ ã&ÁÔæ ^ÁÔ ^çæã[}ÁÇ];D	Þ[ œ/Ò} e^\^å
Ođa Å Óær ^ ÁY ^ ãt @ Ň	ΫΛ•
ÔďÝ	È€G
Ô⁄AZ	ÆG
VÁÝÁG^&D	Þ[ 🐠 & \^å
VÆÆĞ^&D	Þ[ ðÔ) e\\^å
ÜŔ	H
ÜÆ	H
ÔớÔ¢] ĐÝ	ĚÍ
ÔÁÔ¢] ÉZ	ĚÍ
ÙÖF	F
ÙÖÙ	F
ÙĘ	F
VŠÁÇ^&D	İ
Üã∧ ÂÔæc	CA LÁCO
Öl ão ÁÖæc	U@\
U{ Æ	F
U{ Ä′	F
	F
ÔåÂÝ	F
ÜQÆ	F
Ü <b>@</b> Ř	F

## <chFc``YX'GhYY`DfcdYfl]Yg

	Šæà^	ÒÆX•ãã	ÕÆŽ•ãã	þř	V@^¦{ ÁÇEEFÒÍÁAØD	Ö^}•ãĉŽÐcâHá	Ÿã∿ åŽ <b>j•ã</b> ã	Ü^ Ø*Žj∙ãa Üc
F	ŒIJĠ	GJ€€€	FFFÍ I	ÈH	Ēί	ÈΙ	Í€€€€	FÈE ÎÍ€€€ FÈE
G	OEHÎ ÁÕ¦ÈHÎ	GJ€€€	FFFÍ I	ÈH	Ēί	ÈJ	HÎ €€€	FÉ   ÍÌ €€€ FÉG
Н	OÉÏGÁÕ¦Ě€	GJ€€€	FFFÍ I	ÈH	ĚÍ	ÈJ	Í€€€€	FÈE ÎÍ€€€ FÈE
1	OÍ €€ÃÕ¦ÈÓÁÜÞÖ	GJ€€€	FFFÍ I	ÈH	Ēί	ĚĞ	IŒ€€	FÈ I΀€ FÈH
ĺ	OÉ €€ÁÕ¦ÈÓÁÜ^&c	GJ€€€	FFFÍ I	ÈH	Ēί	ĚĞ	I΀€€	FÈE  ÎÌ€€€ FÈEH
Î	OÉ HÁÕ¦ ÈÓ	GJ€€€	FFFÍ I	ÈH	ĚÍ	ÈJ	HÍ €€€	FÉ Î€€€ FÉG
Ϊ	OEF€ÌÍ	GJ€€€	FFFÍ I	ÈH	ĚÍ	ÈJ	Í€€€€	FÈE ÎÍ€€€ FÈEH

### 7c`X': cfa YX'GhYY'DfcdYff]Yg

	Šæà^	ÒÆX•ãã	ÕÆX•ãã	Þř	V@o¦{ ÁQEEFÒÍÁAOI	OÖ^}•ãc°ŽİÐcâHá	ŸãN∣åŽj∙ãã	Ø*Žj•ãã
F	OÊÍHÁÙÙÁÕ¦HH	GJÍ €€	FFHI Î	ÈH	ĒÍ	ÈΙ	HH€€€	IÍ€€€
G	OÊÍHÂÙÙÆÕ¦Í€EF	GJÍ €€	FFHI Î	ÈH	ĒÍ	ÈΙ	í <del>ccc</del> €	îÍ€€€

### <chFc``YX'GhYY'GYWJcb'GYlg</pre>

	Šæè^	Ù@ <b>≱</b> ^	V^]^	Ö^∙ã}Æãc	Tæe^∖ãæ∳	Ö^• ã} Æ⊞	ÈOEÆÃ)Gá	Q^ÃŽAIá	Q:ÆÄjlá	RÁŽájIá
F	Ú æ•^•	ÎÉÄ¢€ÈHÏÄÁÚ æ¢	Ó^æŧ	ÜÒÔV	OÉ HÁÕ¦ ÈÓ	V^] a8æ	GÈ€Í	È€GÏ	ÌÈÎÌ	ÈEÎ
G	Õ¦ægā;*ÁÓ¦æs&ā;*	ŠŒ¢ŒH	Ó^æ{	Ùa; *  ^ ÁOE; *  ^	OEHÎ ÁÕ¦ÈHÎ	V^] a&ae	ĔŒ	ÈÜF	ÈÜF	È€J
Н	Ùœ <b>)</b> å[ ⊶•	ÚŒÓ HĚ	Ó^æ{	Úą^	OÉ HÁÕ¦ ÈÓ	V^]	ŒĚ	ΙĚG	ΙĚG	JÈ€I
- 1	Ùœ;) å[~ÁÓ¦æ&ã;*	ÔHÝÍ	Ó^æ{	Ô@#}}^	OEHÎ ÁÕ¦ÈHÎ	V^] a&ae	FÈΪ	ÈGIF	FÈÍ	ÈΗ
ĺ	Pæ}妿 <b>ä</b> •	ÚŒÓ′GÈE	Ó^æ{	Úą^	OÉ HÁÕ¦ ÈÓ	V^] a&ae	FÈ€G	ĖĠÏ	ĖĠ	FĚGÍ
Î	Pæ}妿ãjÁÔ[¦}^¦∙	ÎÊ¢IÈ΢€ÈĞ	Ó^æ{	Ùa; *  ^ ÁOE; *  ^	OEHÎ ÁÕ¦ÈHÎ	V^] a&ae	ŒË€G	ΙĖ̈́ÍͿ	FGÈ Ï H	ÈÉÍÍ
Ϊ	P[¦ã[}æ•	ÚŒÓ HĒ	Ó^æ{	Ú <b>ą</b> ^	OÉ HÁÕ¦ ÈÓ	V^] a&ae	ŒĚ	ΙĚG	ΙĚG	JÈ€l

### <chFc``YX`GhYY`GYWjcb`GYlg`ff'cbhjbi YXŁ</pre>

	Šæòn^∣	Ù@ <b></b> }^	V^]^	Ö^∙ã*}ÁŠãc	Tæe^¦ãæ⇔	Ö^• ã} Æ⊞	È05AŽAjGá	Q^Ãã Iá	áQ:Æğla	ιRÁŽβIá
Ì	T [ ັ } oÁÚā] ^•	ÚŒÓĆGÈE	Ó^æ	Úą ^	OÉ HÁÕ¦ ÈÓ	V^]	FÈ€G	ĒĠΪ	ĒĞ	FÈGÍ

#### 7c'X': cfa YX'GhYY'GYWJcb'GYhg

		Šæà^	Ù <b>@</b> ∯^	V^]^	Ö^∙ãt}ÆŠãac	Tæe^¦ãæ⊜	Ö^• ã} ÁÜ⊞	OEÆŽjGá	Q^Ãã[lá	Q:Æãjlá	RÁŽájlá
F	F	ÔØFŒ	ÌÔWFÈĠÍÝ€ÍÏ	Ó^æ	þ[}^	OÊÍHÂÙÙÁÕ¦HH	V^1 88æ	ĚÌF	ÈÉÍÏ	ΙÈF	È€€ÎH

#### >c]bhi6 ci bXUfm7 cbX]h]cbg

	R[ā]oÁŠæà∧	ÝÁŽÐajá	ŸÁŽÐajá	ZÁŽEAjá	ÝÁÜ[dĚŽËdĐæåá	ŸÁÜ[dĚŽËdĐæåá	ZÁÜ[dÈŽË-6Dæåá
F	ÞĞ	Ü^æ&a <b>i</b> }	Ü^æ <b>\$</b> æ <b>[</b> }	Ü^æ <b>&amp;</b> æ <b>[</b> ]	Ü^æ <b>\$a</b> [}	Ü^æ <b>&amp;a</b> {}}	Ü^æ <b>\$</b> æ <b>[</b> }
G	ÞF	Ü^æ&a <b>i</b> }	Ü^æ <b>\$</b> æ <b>[</b> }	Ü^æ <b>&amp;</b> æ <b>[</b> ]	Ü^æ <b>\$a</b> [ }	Ü^æ <b>&amp;a</b> [}	Ü^æ <b>\$</b> æ <b>[</b> }
Н	ÞFH	Ü^æ&a <b>i</b> }	Ü^æ <b>\$</b> æ <b>[</b> }	Ü^æ <b>&amp;</b> æ <b>[</b> ]	Ü^æ <b>\$</b> æ <b>[</b> }	Ü^æ <b>&amp;a</b> {}}	Ü^æ <b>\$</b> æ <b>[</b> }

#### 6 Ug]W@:UX'7 UgYg

	ÓŠÔÁÖ^•&¦∄[æ]}	Ôæ•^*[¦^	ÝÁÕ¦æçãĉ	ŸÁÕ¦æçãcî		R[ã]c	Ú[ã]c	Öãrdãaĭ l	₩c.	Ù`¦æ&∧ <u>⊞</u>
F	Ù^ -ÁY ^ ð @c	ÖŠ			Ë		FH		Н	
G	Ùd šc ¦^Ár a å Ár	Y ŠÝ						HH		
Н	Ùd šc ¦^Ár a åÄr	Y ŠŸ						HH		
	YāļåÁŠ[æåÁ€ÁOEZQ	Y ŠŸ Y ŠÝ					FH			
ĺ	YājåÁŠjæåÁH€ÁOZQ	Þ[}^					GÎ GÎ			
Î	YāļåÁŠ[æåÁlÍÁOEZQ	Þ[}^					Ĝ			
Ϊ	Yā)åÁŠ[æåÁ΀ÁOZQ	Þ[}^					Ĝ			
Ì	Yā}åÁŠ[æåÁJ€ÁOZQ	ΥŚΫ					FH			
J	YajåÁĞjæåÁFG€ÁOZQ	Þ[}^					G G G			
F€	YāļåÁŠĮæåÁFHÍÁOZQ	Þ[}^					Ĝ			
FF	YājåÁĞjæåÁFÍ€ÁOZQ	Þ[}^					Ĝ			
FG	<b>(3</b> ,^Á/ ^ā @c	UŠF					FH	HH	Н	
FH	Ùd `&c` ¦^ ÁQ&^ ÁY ā} å ÁY	UŠG						HH		
FI	Ùd `&c` ¦^ ÁQ&^ ÁY ð}, å ÁŸ	UŠH						HH		
FÍ	O&^ÁYajåÆŠ[æåÆÁOEZQ	UŠG					FH			
FÎ	Qa^ÁY ðjåÁŠ[æåÁH€ÁOEZQ	Þ[}^					Ĝ			
FΪ	O&∧ÁYajåÁŠ[æåÁNÍÁOEZQ	Þ[}^					G G			
FÌ	Q3vÁYa}åÁŠ[æåÁn€ÁOEZQ	Þ[}^								
FJ	O&^ÁYa}åÁŠ[æåÁJ€ÁOEZQ	UŠH					FH			
G€	Qs^ÁYajåÆŠ[æåÆFG€ÁOEZQ	Þ[}^					Ĝ			
GF	O&∧ÁYa}åÁŠ[æåÁFHÍÁOEZQ	Þ[}^					G G			
GG	Qa,^ÁYajåÁŠ[æåÁFÍ€ÁOEZQ	Þ[}^								
GH	Ù^ãr{ ã&ÁŠ[æåÁÝ	ÒŠÝ	⊞FI				FH			
G	Ù^ãr{ ã&ÁŠ[æåÁŸ	ÒŠŸ		⊞FFI			FH			
GÍ	Šãç^ÁŠ[æåÁFÁÇŠçD	ŠŠ					F			
Ĝ	Šãç^ÁŠ[æåÁGÁÇŠçD	ŠŠ					F			
GÏ	Šãç^ÁŠ[æåÁHÁŠÇD	ÒŚŸ ŠŠ ŠŠ ŠŠ ŠŠ ŠŠ					F			
GÌ	Šãç^ÁŠ[æåÁÁÁŠçD	ŠŠ					F			
GJ	Šãç^ÁŠ[æåÁÁÁŠçD	ŠŠ					F			
H€	Šãç^ÁŠ[æåÁÁÁŠçD						F			
HF	Tædich) ædisk Árja ár Árjá D	Þ[}^					F			
HG	Tædich) ædi & AŠjædi ÁGÁÇŠ D	Þ[}^					F			
HH	Tænig or sænig ænig ænig fænig	Þ[}^					F			

6 Ug]W@ UX'7 UgYg'ff cbhjbi YXŁ

	ÓŠÔÁÖ^•&¦ā];cā[}	Ôæz^*[¦^	ÝÁŐ¦æçãcî	ŸÁÕ¦æçãcî ZÁÕ¦æçãcî	R[ã]c	Ú[ą̃c	ÖãrdãaŭÈ	ÉCE^æÇT ÈÈÈ	Ù`¦æ&^ÈÈ
Н	Tænig (x) æg) & A Á Á (x) Þá D	Þ[}^				F			
HÍ	Tæ4ic^}æ4&^ÁŠiæáÁiÁÇŠ(D	Þ[}^				F			
HÎ	$T \approx \hat{A} \cdot \hat{A} \times A$	Þ[}^				F			
ΗÏ	Tænd c^) ænd & AŠ ænd Á ÁÇŠ D	Þ[}^				F			
HÌ	Tædich) ædi& ÁŠ ædiÁ ÁŠ D	Þ[}^				F			
HJ	Tædich) ædisk Áði ædisk Áði D	Þ[}^				F			
I€	ÓŠÔÁFÁV¦æ)•ãN} œÁŒ^æÆŠ[æå•	Þ[}^					J		
IF	ÓŠÔÁFGÁV¦æ}•ãN}ơÁŒ^æÆS[æå•	Þ[}^					J		

@UX'7ca V]bUhjcbg

<u> </u>	k rea vjborjeby													 	
	Ö^∙ &¦ā[ ca[{}]	Ù[  ç^	ÚÖ⊞	Ţ\$\$@ <u>#</u>	ÓŠÔ	Øæ&d[	ÓHEZERE	<b>EDÎÎZ</b> DEÎ	<u>ŤÓŠÔ</u>	Zeellijó	<del>ììì</del> o <del>dili</del>	ÉSOCIÉC C	EDEED SE	<b>Øæ⊞</b>	
F	FÈ ÖŠ	Ϋ́Λ•	Ŷ	ÖŠ FĖ											
G	FÉGÖSÁÉÁFY ŠÆÁOZQ	Ÿ^•	Ϋ́	ÖŠ FÉG	G	F_	H	I F							
Н	FÉGÖŠÆÁFY ŠÆH€ÁOEZQ	Ϋ́Λ∙	Ϋ	ÖŠ FÉG	G	ÈÎÎ	ΗĒ	Í F							
	FÉGÖSÁÉÁFY ŠÁLÍÁOEZO.	Ÿ^•	Ϋ́	ÖŠ FÉG	G	Ë€Ï	НЁ€Ї	ÎF							
ĺ	FÈCOSÁÉÁFY ŠÁÍ€ÁOEZQ	Ÿ^•	Ÿ	ÖŠ FÈG	G	Ě	ΗÈîî	ΪF							
Î	FÉGÖŠÆÁFYŠÁJ€ÁOZQ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	G		H F	ÌF							
Ϊ	FÈGÖŠÆÆFYŠÆFŒÆOZQ	Ÿ^•	Ϋ	ÖŠ FÈG	G	Η̈́	ΗÈîî	J F							
Ì	FÉGÖSÁÉÁFY ŠÁFHÍ ÁOZQ	Ÿ^•	Ϋ	ÖŠ FÈG	G	⊞̈́€Ï	НЁ€Ї	F€ F							
J	FÈGÖŠÆÆFYŠÆFÍ€ÆOZQ	Ÿ۸∙	Ϋ	ÖŠ FÈG	G	Ħîî	ΗĚ	FF F							
F€	FÈCOSÁÉÁFY ŠÁFÌ€ÁOZQ	Ÿ۸∙	Ϋ	ÖŠ FÉG	G	Ë	Н	ΙË							
FF	FÈCÖŠÆÁFYŠÆGF€ÁOZQ	Ÿ۸∙	Ÿ	ÖŠ FÉG	G	Ħîî	ΗЩ	ÍË							
FG	FÉGÖŠÆÁFY ŠÆGG ÁOZQ	Ϋ́^•	Ϋ	ÖŠ FÈG	G	⊞̈́€Ï	ΗŒÈ	Ë							
FH	FÈCOSÆÁFY ŠÁGI€ÁOZQ	Ÿ^•	Ϋ	ÖŠ F <b>È</b> G	G	Η̈́	ΗËÈ	Ë							
FI	FÉGÖŠÆÁFY ŠÆGÏ€ÁOZQ	Ϋ́Λ∙	Ÿ	ÖŠ F <b>È</b> G	G		НЁ	ìË							
FÍ	FÉGÖŠÆÁFY ŠÁH€€ÁOZQ	Ÿ^•	Ϋ	ÖŠ F <b>È</b> G	G	Ě	ΗËÈ	ÈJË							
FÎ	FÉGÖŠÆÁFY ŠÁHFÍ ÁOZQ	Ϋ́Λ∙	Ÿ	ÖŠ F <b>È</b> G	G	ÈEÏ	ΗŒÈ	È€Ë							
FΪ	FÉGÖŠÆÆFY ŠÆHH€ÆOZQ	Ϋ۸۰	Ÿ	ÖŠ FÈG	G	ÈÎÎ	НЩ								
FÌ	€ÈÖŠÆÆFYŠÆÆOZQ	Ϋ́Λ∙	Ÿ	ÖŠ 🗎	G	F	Н	I F							
FJ	€ÈÖŠÆÆFYŠÆHEÆOZQ	Ϋ۸۰	Ÿ	ÖŠ È	G	ÈÎÎ	ΗĚ	ĺΕ							
G€	€ÈÖŠÆÆFYŠÁNÍÁOEZQ	Ϋ́Λ∙	Ÿ	ÖŠ È	G	Ë€Ï	НЁ€Ї	ÎF							
GF	€ÈÖŠÆÆFYŠÂR€ÆOZQ	Ϋ۸۰	Ÿ	ÖŠ È	G	Ě	ΗÈÎÎ	ΪF							
GG	€ÈÖŠÆÆFYŠÁJ€ÁOZQ	Ϋ́Λ∙	Ÿ	ÖŠ È	G		H F	ÌΕ							
GH	€ÈÖŠÆÆFYŠÆFŒÆOZQ	Ÿ۸∙	Ϋ	ÖŠ È	G	Ħ	ΗÈÎÎ	J F							
G	€ÈÖŠÆÆFYŠÆFHÍÆOZQ	Ϋ́Λ∙	Ÿ	ÖŠ È	G	⊞̈́€Ï	НЁ€Ї								
GÍ	€ÈÖŠÆÉÁFYŠÆFÍ€ÁOZQ	Ÿ۸۰	Ÿ	ÖŠ	G	ĦÎÎÎ	ΗĚ								
GÎ	€ÈÖŠÆÉÆFYŠÆFÌ€ÁOZQ	Ϋ́Λ∙	Ÿ	ÖŠ	G	Ë	Н	ΙË							
ĠÏ	€ÈÖŠÆÆFYŠÆF€ÆOZQ	Ÿ۸۰	Ÿ	ÖŠ	G	Η̈́ÎÎ	НШ								
GÌ	€ÈÖŠÆÆFYŠÆGÍÆOZQ	Ϋ́Λ∙	Ÿ	ÖŠ È	G	⊞ï€ï	HEE								
GJ	€ÈÖŠÁÉÁFYŠÁGI€ÁOZQ	Ϋ۸۰	Ϋ́	ÖŠ 🗎	G	<u></u>	ΗŒÈÈ								
H€	€ÈÖŠÁÉÁFYŠÁGÏ€ÁOZQ	Ϋ́Λ∙	Ÿ	ÖŠ È	G		ΗË								
HF	€ÈÖŠÆÆFYŠÆH€ÉAOZQ	Ϋ۸۰	Ϋ́	ÖŠ 🗎	G	Ě	HEE								
	€ÈÖŠÆÆFYŠÆHFÍÁOZQ	Ϋ۸۰	Ϋ́	ÖŠ 🗎	G	<u>_</u> ÈEÏ	HEE								
	€ÈÖŠÆÆFYŠÆHEÁOZQ	Ϋ۸۰	Ϋ́	ÖŠ 🗎	G	ÈÎÎ	НШ								
H	FÉGÖSÁÉÁFÖSÁÉÁFY ŠÉÉ		Ϋ́	ÖŠ FĒG	UŠF	F		FI	FÍ	F					
HÍ	FÉGÖSÁÉÁFÖSÁÉÁFY ŠÉÉ		Ϋ́	ÖŠ FĒG	UŠF	F	FHÈ Î Î		FÎ	F					
HÎ	FÉGÖSÁÉÁFÖSÁÉÁFY ŠÍÐ		Ϋ́	ÖŠ FĒG	UŠF	F	FHË€Ï			F					
HÏ	FÉGÖSÁÉÁFÖSÁÉÁFY ŠÉÉ		Ϋ́	ÖŠ FĒG	UŠF	F		FI ÈÎÎ		F					
HÌ	FÉGÖSÁÉÁFÖSÁÉÁFY ŠÉÉ		Ϋ́	ÖŠ FĒG	UŠF	F		FI F	FJ	F					
HJ	FÉGÖSÁÉÁFÖSÁÉÁFY ŠÉÉ		Ϋ́	ÖŠ FĒG	UŠF	F	FH⊞			F					
		•	_ •			•	, , , ,							 -	

# @UX'7ca V]bUhjcbgʻf1/cbhjbi YXŁ

<u>@U</u>	(②c UX 7 ca V]bUnjc bg f7 c bnjb i YXŁ  Ö^• & a a a b ù     c^ ú o i i i i i i i i i i i i i i i i i i															
	Ö^• &¦ā cā}	Ù[  ç^	ÚÖĦ	! h&e⊘∰ŒÜÜ	ÓŠÔ	Øæ&di¦	ÓĦĠĦĤ	iio <sub>miii</sub>	ÓŠÔ.	⊘ <del>a<b>ùìi</b>Č</del> ìÀ	ÎZ⁄a <b>£ÌÌ</b> ĆĤ	ii Hecoii	ÉPACÁTTIC	¥ ¥HÓH	HÁHHA	ÌOa <b>i</b> ÌÌ
I€	FEGÖSÁÉÁFÖSÁÉÁFY ŠEÉ		Ϋ́	ÖŠ FEG	UŠF	F	FHE I			F				ر ا		
	FÉGÖSÁÉÁFÖSÁÉÁFY ŠÉÉ		Ϋ́	ÖŠ FĒG	UŠF	F	FHE E		Œ							
	FEGÖSÁEÁFÖSÁÆÁFY ŠEÉ		Ϋ	ÖŠ FĒG	UŠF	F	FH EF FI			Ë						
	FÉGÖSÁÉÁFÖSÁÆÁFY ŠÉÉ		Ÿ	ÖŠ FĒG	UŠF	F	FHE HE			Ë						
	FEGÖSÆÆFÖSÆÆFY ŠEE		Ϋ́	ÖŠ FĒG	UŠF	F	FHEE			Ë						
	FEGÖSÁÉÁFÖSÁÉÁFY ŠEÉ				UŠF											
	FÉGÖSÆÁFÖSÆÁFY SEE		Ÿ	ÖŠ FĖG	1 1	<u> </u>	FHE FI		_	Ë						
			Ÿ	ÖŠ FÈG	UŠF	<u> </u>	FH FI		FJ	Ë						
	FÈCOSAÉAFOSAÉAFY ŠÈÈ		Ÿ	ÖŠ FÈG	UŠF	<u>F</u>	FH Ě FI									
11	FÉGÖSÁÉÁFÖSÁÆÁFY ŠÉÉ		Ÿ	ÖŠ FĖG	UŠF	F	FHË€Ï FI		_	Ë						
	FEGÖSÆÆFÖSÆÆFY ŠEË		Ÿ	ÖŞ FEĞ	UŠF	<u> </u>	FHÈÎÎFI	Ħ	Œ	EF_						
	ÇFİEÉ€İĞÜå• DÆÆFİŒÖİİÈ		Ÿ	ÖŠ FÉCH	ÒŠÝ	F	ÒŒ									
	ÇFÉCÉ€ÉGÙå• DÆÆFÈ€ÒÈÈ		Ÿ	ÖŠ FĒGH	ÒŠÝ	ÈÎ	ÒŒĚ									
	ÇFÉEÉ€ÉGÙå• DÆÆFÈ€ÒÈÈ		Ÿ	ÖŠ FĚCH	ÒŠÝ	ËEÏ	ÒŒŒ									
	ÇFÉZÉ€ÉGÙå• DÆÆFÉEÓÈÈ		Ÿ	ÖŠ FĒGH	ÒŠÝ	Ė	Ò <b>III</b> ÎÎ									
	ÇFİĞÉ€İĞÜå• DÄÉÁFİĞĞÖİÜ		Ÿ	ÖŠ FÉGHÌ	ÒŠÝ		Ò⊯F									
ĺĺ	ÇFÊÇÉ€ÊĞÛå•DÆÆFÊĞÖÊÊ		Ϋ	ÖŠ FÍÐHÌ	ÒŠÝ	ËΪ	ÒЩÜÎÎ									
ĺÎ	ÇFÉCÉ€ÉSÙå•DÆÆFÉEÓEÉ		Ÿ	ÖŠ FÉGHÌ	ÒŠÝ	⊞̈́€Ϊ	ÒŒŒ									
ÍΪ	ÇFÊEÉ€ÊSÙå• DÆÆFÊEÒÊÊ	Ÿ^•	Ÿ	ÖŠ FÉGHÌ	ÒŠÝ	⊞îîî	ÒŒĚ									
	ÇFÉEÉ€ÉGÙå• DÆÆFÉEÓÉÉ		Ϋ	ÖŠ F <b>ÉCH</b> Ì	ÒŠÝ	Ë	ÒÈÈ									
	ÇFʌɀÊÈÙå• DÆÆÆÊÊÒÈÈ	Ÿ۸∙	Ÿ	ÖŠ F <b>ÉCH</b>	ÒŠÝ	ΉÎÎÎ	ÒŒŒ									
	ÇFʌɀÊĞÛå• DÆÆFÊĞÖÊÊ		Ÿ	ÖŠ FÉGH	ÒŠÝ	⊞ï€ï	ÒĦĦ									
	ÇFÉCÉ€ÉGÙª• DÆÆFÈEÒE		Ϋ́	ÖŠ FÉGH	ÒŠÝ	<u> </u>	ÒĦĦ Ħ									
	ÇFʌɀÊĞÛå• DÆÆFÊEÖÊÊ		Ϋ́	ÖŠ FÉGH	ÒŠÝ		ÒŒË									
	ÇFÉCÉ€ÉGÙå• DÆÆFEEÒÉÉ		Ÿ	ÖŠ F <b>É</b> GHÌ	ÒŠÝ	Ě	Ò E									
	(FÉCÉ€ÉGÙª• DÆÆFÈEÒÈÈ		Ϋ	ÖŠ F <b>É</b> CHÌ	ÒŠÝ	ĽĖ€Ï	Ò									
	(FÉEÉ€ÉGÙå• DÆÆFÈ€ÒÈÈ	•	Ÿ	ÖŠ FÉCH	ÒŠÝ	ÈÎÎ	ÒĦĦ									
	ŒÈ ËŒÈ Lª DÉÆÈ À	•	Ϋ́	ÖŠĖÎG	ÒŠÝ	<u> ΕΙΙ</u>	ÒŒ									
	ŒÈ ËËË CHÂ	•	Ÿ	ÖŠĖÎG	ÒŠÝ	<u>r</u> Èîî	ÒŒĚ									
	ŒÈJËŒĠŮå• DÆÆFŒÔÆ	•	Ϋ́	ÖŠĖĪG			OŒŒ E									
	ŒÈ ËË CÀ	•	-			<u>Ë€Ï</u>	Ò⊞EÎÎÎ									
			Ÿ	ÖŠ ÈÎG		Ě										
	ŒÙËŒÛå• DÆÆÆÒÆË		Ÿ		ÒŠÝ		ÒŒF									
	ŒÙËŒÛå• DÆÆÆÈÒÆÈ		Ÿ	ÖŠ ÈÎG	ÒŠÝ		Ò									
	ŒÙËŒŒŮå• DÆÆÆÈÒÆÈ		Ÿ	ÖŠ ÈÎG	ÒŠÝ	<u>∰</u> €Ï	ÒŒŒ									
	ŒÙËŒŒŮå• DÆÆÆÈÒÆÈ		Ÿ	ÖŠÈÎG	ÒŠÝ	<u> </u>	ÒŒĚ									
	ŒÙËŒŒŮå• DÆÆÆĚÔÆË		Ÿ	ÖŠ È G		Ë	ÒŒ									
	ŒÐËŒŒŮå• DÆÆÆŒÒÆ		Ϋ	ÖŠÈÎG		ЩÎÎ	ÒĦĦ									
	ŒÈJËŒĠÙå• DÆÆÆÈÒÆÈ			ÖŠÈĴG	OŠÝ		OHHI HE									
	ÇEÈ ËŒÈCÙå• DÆÆFÈCÒÆÈ		Ÿ	ÖŠ ÈÌG		Ш̈́	ÒHH H									
	Ç€ÈJËŒÈCÙå• DÆÆFÈ€ÒÆÈ		Ϋ	ÖŠ ÈÎG			ÒŒË									
	ÇEÈJËŒËGÙå•DÆÆFÈEÒÆË		Ϋ	ÖŠ ÈÌG	ÒŠÝ	Ě	ÒHH HÈ									
	ÇEÈJËŒËGÙå•DÆÆFEEÒÆË		Ϋ	ÖŠ ÈÎG		Ë€Ï	ÒŒŒ È									
	ÇEÈJËŒĒGÙå•DÆÆÆEÒÆË		Ϋ	ÖŠ ÈÎG		ÈÎÎ	ÒĦĦ									
ÌG	- V II // / V /V	Ÿ۸∙	Ÿ	ÖŠ FÉG	ď	FĚ										
ÌН		Ÿ۸•	Ÿ	ÖŠ FĒG	Ĝ	FĚ										
ìi	FÉGÖÆÆÆËÆĞH	Ÿ۸۰	Ϋ́	ÖŠ FĒG	GÏ	FĚ										
ìí	FÉGÖÆÆÆÐ ÁŠÇI	Ϋ́Λ•	Ÿ	ÖŠ FĒG	Ġ	FĚ										
ÌÎ	FÉGÖÆÆFĚÆÇÍ	Ÿ۸۰	Ÿ	ÖŠ FĒG	GJ	FĚ										
11	FÉGÖÆÆFÉÆĞÎ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	H€	FĚ										
	FÉGÖÆÆFĚ ŠÍÆÆFÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FĒG	HF	FĚ	I ŒÎÌ G	ì <b>r</b> €íì	Н							
	FÉGÖÆÆFĚ ŠÍÆÆFĒĒ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HF	FĚ	Í ŒÍ G			€GI						
	FÉGÖÆÆFĚ ŠÍÆÆFÈÈÈ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	-	FĚ	Î ŒÎ G			¥IF						
	FÎGÖAÉAFÎ Š. ÆÁFÎŒÎÎ		Ÿ		HF											
JF	FESUALARE S ALAREETT	Ÿ^•	Υ	ÖŠ FÉG	HF	FĚ	∣ÏŒίIG	TECN	Н	<b>E</b> I						

## @UX7ca V]bUhjcbgff/cbhjbi YXŁ

	A rea vjborjeby						( 20 )					 v .w	- 2007	
	Ö^• & ā cā }	Ù[  ç^				Øæ&d ¦			15 ( 5 )	<b>DetHO</b>	HOOME	ÐЩ	Zettol	HE DOUBLE
JG	FÈSÖÆÆFËŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ•	Ϋ́	ÖŠ FĒG	HF	FĚ			ÈÉ Ì					
	FÈGÖÁÉÁFÍL Š( ÁÉÁFÉEÍLÍ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HF	<u>FĚ</u>	J ŒÍÌ							$\perp$
JI	FÈGÖÁÉÁFÍL Š( ÁÉÁFÉEÍÍÍ	Ÿ۸•	Ÿ	ÖŠ FĒG	HF	<u>FĚ</u>		G EE H	ÈE F					
JI	FÈGÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ϋ۸∙	Ÿ	ÖŠ FĒG	HF	<u>FĚ</u>	FFEE Ì		È€GJ					
JÎ	FÈGÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FĖG	HF	F <u>Ě</u>	Edi		ÏЩ					
JΪ	FÈGÖÆÆFĚŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HF	FĚ	Í È€ÍÌ		ŒŒ					
JÌ	FÈGÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HF	FĚ		G⊞⊞H	ËEÈ					
	FÈGÖÁÉÁFÍL Š( ÁÉÁFIEEÍÐ)	Ÿ^•	Ÿ	ÖŠ FÈG	HF	FĚ		G⊞⊞H						
	FÈGÖÆÆFĚŠ(ÆÆÆÈÈÈ	ŸΛ•	Ÿ	ÖŠ FÈG	HF	FĚ		G <del>E</del>	ŒŒ					
	FÈGÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HF	FĚ	J 🖼 Ì	G ŒGJ H	Œ€Í					
	FÈGÖÆÆFĚŠ(ÆÆÆÈÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HF	FĚ		G E H	ËEÈ					
	FÈCÖÁÉÁFÉ Š( ÁÉÁFÈ€EE	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HF	FĚ	FFŒÍÌ	GÈ€ÍH	Ë€ÈÈ					
F€	FÈGÖÁÉÁFÉ ŠĮ ÁÉÁFÈEE	ŸΛ•	Ϋ	ÖŠ FĒG	HG	FĚ	Bear i	GŒÍÌ H						
F€Í	FÈGÖÆÆFĚŠ;ÆÆÆEÈ	Ÿ^•	Ϋ	ÖŠ FÈG	HG	FĚ	ĺ È€ÍÌ	GÈÉÍH	È€GJ					$\top$
F€Î	FÈGÖÁÉÁFÉ ŠĮ ÁÉÁFÈEE	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HG	FĚ		GE F H	ÈEIF					
F€Ï	FÈCÖÁÉÁFÉ Š(ÁEÁFÈ€ÈÈ	Ÿ۸∙	Ϋ	ÖŠ FÈG	HG	FĚ	Ϊ È€ÍÌ							$\Box$
	FÈCGÖÁÉÁFÉ Š( ÁÉÁFÈEÈÈ	Ÿ۸∙	Ÿ	ÖŠ FÈG	HG	FĚ	ÌÈÉÌ							
	FIÈSÖÆÆFIĚ Š(ÆÆFIÈEIE)	Ÿ۸•	Ϋ́	ÖŠ FÈG	HG	FĚ	J ÈÉÍ Ì							
	FÈGÖÁÉÁFÍÉ Š( ÁÉÁFÈEÍÈÈ	Ÿ۸∙	Ÿ	ÖŠ FÈG	HG	FĚ		G⊞⊞H	È F					
	FÈGÖÆÆFË Š(ÆÆFÈ€ÈÈ	Ÿ۸•	Ÿ	ÖŠ FĒG	HG	FĚ		G ⊞€Í H						$\overline{}$
	FÈGÖÆÆFË Š(ÆÆFÈEÈÈ	Ÿ۸∙	Ÿ	ÖŠ FĒG	HG	FĚ		G EE H	ΪЩ					
	FÈGÖÆÆFË Š(ÆÆFÈEÈÈ	Ÿ۸•	Ϋ́	ÖŠ FĒG	HG	FĚ		G ⊞€Í H	Ë€ÌÈ					$\overline{}$
	FÈGÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ϋ́Λ∙	Ϋ́	ÖŠ FĒG	HG	FĚ		G⊞⊞H	Ë€È					
FFÍ	FÈGÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ÿ۸•	Ϋ́	ÖŠ FĒG	HG	FĚ		G⊞EEH						
	FÈGÖÆÆFË Š(ÆÆFÈEÈÈ	Ÿ۸•	Ϋ́	ÖŠ FĒG	HG	FĚ		G ### H	<b>⊞€</b> ⊞È					
FFÏ	FÉGÖÁÉÁFÍL Š( ÁÉÁFIEEÍÐ)	Ÿ۸•	Ϋ́	ÖŠ FĒG	HG	FĚ		GEGJ H	Β					_
		Ÿ۸•	Ϋ́	ÖŠ FĒG	HG	FĚ	F£ŘÍÌ	GE F H	EEEE					
	FEGÖÆÆFE Š(ÆÆÆEE	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HG	FĚ		GŒÍ H	ËEÈ					_
	FEGÖÆÆFE Š(ÆÆÆEE	Ÿ۸•	Ϋ́	ÖŠ FÉG	HH	FĚ		GŒÌ H						
	FÉGÖÁÉÁFÍÍ Š( ÁÉÁFÉEÍÍÍ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	НН	FĚ	í ÉGÍ		È€GJ				_	-
	FÉGÖÁÉÁFIÍ Š( ÁÉÁFIÉÉIÍÍ	Ϋ́Λ•	Ϋ	ÖŠ FĒG	HH	FĚ		GEF H	È F					
	FÉGÖÁÉÁFIÍ Š( ÁÉÁFIÉÉIÍÍ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HH	FĚ	i Edi		ÈÉÍ					+-
FG	FÉGÖÁÉÁFÍÉ Š( ÁÉÁFÉEÍÉÍ	Ϋ́Λ•	Ϋ́	ÖŠ FĒG	HH	FĚ	È		ÈÌ					
	FESÖÆÆFE Š ÆÆFEE	Ÿ^•	Ÿ	ÖŠ FĒG	_		<del>- \ \ \ \</del>		ÈÉÍ					
	FEGÖÆÆTĚ ŠÍ ÆÆFEE	ÿ∧•	Ϋ́		HH	FĚ			EEI F					
FĜ	FEGÖÆÆFE Š ÆÆFEE	ÿ∧•	Ÿ		HH	FĚ		G Œ H						
FĞ	FEGÜÆÆTĚŠ, ÆÆFEE	γ∧• Ÿ۸•			HH	FĚ		G EE H	ŒGU Ï∰					
FG		•	Ÿ		HH	FĚ		G EE H	IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII					
	FÈSÖÆÆTĚŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FĒG	HH	FĚ		G EE H						
FH€		Ÿ۸∙	Ÿ	ÖŠ FĒG	HH	FĚ		G EE H						
FHF	FÈSÖÆÆTĚŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HH	FĚ		G EE H						
FHG	FÈCOÁÉÁFIĽŠ ÁÉÁFÈEÍÍÍ	Ϋ́Λ∙	Ÿ	ÖŠ FĒG	HH	FĚ		G E H	EEEEE					
	FÈCOÁÉÁFIĽŠ ÁÉÁFÈEÍÍÍ	Ϋ́Λ•	Ÿ	ÖŠ FÈG	HH	FĚ		GÈGJ H	EE					
	FÈSÖÆÆFËŠ ÆÆFÈEÈÈ	Ÿ۸•	Ÿ	ÖŠ FĒG	HH	FĚ		G E F H	EEEE EEE					
	FÈSÖÆÆFËŠ ÆÆFÈEÈÈ	Ÿ^•	Ÿ	ÖŠ FĒG	НН	<u>FĚ</u>		GÈÉÍ H	<b>⊞</b>					
FH	FÈSÖÆÆFËŠ(ÆÆFÈSÈË	Ϋ́Λ•	Ÿ	ÖŠ FĒG	Н	FĚ		GŒÍ H						
FH	FÈSÖÆÆFËŠ(ÆÆFÈSÈË		Ÿ	ÖŠ FĒG	Н	<u>FĚ</u>		G <b>È</b> ÉÍ H	È€GJ				$\perp$	
	FÈCOÁÉÁFIĽŠ ÁÉÁFIEEIÚ	Ÿ۸•	Ÿ	ÖŠ FĚG	Н	FĚ		G E F H						
	FÈCOÁÉÁFÍĽŠ( ÁÉÁFÍÆÍÐÉ	Ϋ۸∙	Ϋ	ÖŠ FÈG	Н	FĚ		G ÈŒGJ H						
	FÈGÖÆÆFË Š(ÆÆFÈ€ÈÈ		Ÿ	ÖŠ FĒG	Н	FĚ		GHI H						
	FÈGÖÆÆFË Š(ÆÆFEEÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FĖG	Н	₽Ě		G⊞⊞H						
	FÈGÖÆÆFË Š(ÆÆFEEÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	Н	FĚ		G⊞⊞H						
FIH	FÈCOÁEÁFIĽŠ ÁEÁFIEEIE	Ϋ́Λ∙	Ÿ	ÖŠ FÉG	Н	FĚ	FFŒ Ì	G⊞€ÍH	È€GJ					

## @UX7ca V]bUhjcbgff/cbhjbi YXŁ

© OX / Ca VjbOrjeby				۸č.	~	6 <del>22</del> - 2	****	د <del>بدد</del> یہ ۵	<u> </u>	<u> </u>		× ~~	~ 2224	<u> </u>
Ö^•&lājāa} FII FRESÖÆÆÆËŠ(ÆÆÆEEEE	Ù[  ç^			ÓŠÔ	Øæ&d ¦	1 1 1 1 1				HH5/SEHK	) <del>IIIO</del> DE <del>E</del>	E)III	200 <u>0</u>	##\/D##E
	Ϋ́Λ•	Ÿ	ÖŠ FĒG	Н	FĚ		G Œ H						4	
FIÍ FÌEGÖÆÆÆËŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ•	Ÿ		Н	FĚ	Í ÈÉÌ	G EE F						_	
FIÎ FÊGÖÆÆÆĚŠ(ÆÆÆÈÈÈ	Ϋ́Λ•	Ÿ	ÖŠ FÈG	Н	FĚ		G EEE H						_	
FI FIEGÖÆÆFE Š ÆÆFEEE	Ÿ۸•	Ÿ	ÖŠ FĒG	Н	FĚ	Ï Œ Ì	G EEE H						_	
FIÌ FÈSÖÆÆFËŠ(ÆÆFÈÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FÈG	Н	FĚ	È	G EEE F	/						
FIJ FÈSÖÆÆFĚŠ(ÆÆFÈÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FĒG	Н	FĚ	J È Ì							$\rightarrow$	
FÍ€ FÉSÖÆÆÆĚŠ(ÆÆÆÈÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FÈG	Н	FĚ		GE F F						_	
FÍF FÈSÖÆÆFĚŠ(ÆÆFÈÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FĚG	H	FĚ	FFŒ Ì							$\rightarrow$	
FÍG FÉGÖÆÆFÉŠ ÁÆÆFÉE	Ϋ́Λ∙	Ÿ	ÖŠ FĒG	HÍ	FĚ	Be ì	GŒÎ P							
FÍH FÈSÖÆÆÆĚŠ(ÆÆÆÈÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FÉG	ΗĹ	FĚ	ĺ Œĺì		È€GJ						
FÍI FÉSÖÆÆÆÉ Š(ÆÆÆÈE	Ϋ́Λ∙	Ÿ	ÖŠ FÉG	HĹ	FĚ	ÎÈÌ								
FÍÍ FÉSÖÆÆÆÉ Š(ÆÆÆÈÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÉG	HĹ	FĚ	ÏÈÉÌÌ								
FÍÎ FÈSÖÆÆÆËŠ(ÆÆÆÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÍ	FĚ	ÌÈÌ								
FÍÏ FÉSÖÆÆÆËŠ(ÆÆÆEÈÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÍ	FĚ	JŒÉÌ								
FÍÌ FÈSÖÆÆÆËŠ(ÆÆÆÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÍ	FĚ		GŒŒH							
FÍJ FÉGÖÆÆÆË ŠĮÆÆÆĒ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÍ	FĚ	FFŒÍÌ								
F΀ FÊSÖÆÆÆËŠ(ÆÆÆEÈÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÍ	FĚ	EE Ì	GŒŒ₽	ıЩ						
FÎF FÊSÖÆÆÆËŠ(ÆÆÆEÈÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FÉG	HÍ	FĚ	ÍŒÉÌ								
FÎG FÊSÖÆÆÆË ŠĮÆÆÆĒ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HÍ	FĚ	ΠȀÍÌ	G ⊞E H	ËEÈÈ						
FÎH FÊGÖÆÆÆËŠ(ÆÆÆÈ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HÍ	FĚ	j È€íì	G⊞EEEH	⊞€í						
FÎ   FÊSÖÆÆÆĚŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HÍ	FĚ	ÌÈÌ	G ### ⊦	EEEEE						
FÎÍ FÉGÖÆÆÆĚŠ(ÆÆÆÈEÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HÍ	FĚ		GÈŒJ ⊦	⊞€í						
FÎÎ FÊGÖÆÆHĚŠ(ÆÆÆÈ	Ϋ۸۰	Ϋ	ÖŠ FÉG	HÍ	FĚ		GE F							
FÎÏ FÊGÖÆÆHĚŠ(ÆÆÆÈ	Ϋ۸۰	Ϋ	ÖŠ FÉG	HÍ	FĚ								$\neg$	
FÎÌ FEGÖÆÆFĚŠ(ÆÆÆÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÎ	FĚ	È€ÎÌ								
FÎJ FÊGÖÆÆFĚŠ, ÆÆÆÈ	Ϋ۸۰	Ϋ́	ÖŠ FÉG	HÎ	FĚ	i Beiì		È€GJ						
FÏ € FÈSÖÆÆÆË Š(ÆÆÆÈE	Ϋ۸۰	Ϋ́	ÖŠ FÉG	HÎ	FĚ		GE F							
FÏ F FÈSÖÆÆFË Š(ÆÆFÈEÈÈ	Ÿ۸•	Ϋ́	ÖŠ FÉG	HÎ	FĚ	i Ï È€ÍÌ								$\top$
FÏ G FÊSÖÆÆFÊ Š(ÆÆFÈE	Ÿ۸•	Ϋ́	ÖŠ FÉG	HÎ	FĚ		GHIII H							
FÏ H FÊSÖÆÆFÊ Š(ÆÆFEE	Ϋ́Λ•	İΫ	ÖŠ FĒG	HÎ	FĚ	JŒÍÌ							_	
FÏ   FÌESÖÆÆFĒŠ Š ÆÆFĒĒ	Ÿ۸•	Ÿ	ÖŠ FĒG	HÎ	FĚ		G EEE H							
FÏÍ FÉGÖÆÆFÉŠ(ÆÆFEE	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HÎ	FĚ	FFE Ì								
FÏÎ FÎCOÁÉÁFÎÉ Š( ÁÉÁFÌÉÉÌÌÌÌ	Ÿ۸۰	Ϋ́	ÖŠ FĒG	HÎ	FĚ		G EEE H							
FÜÜ FÉGÖÆÆFÉ Š(ÆÆFÉE	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HÎ	FĚ	ÉÌ	G ⊞ÉÍ H						_	
FÏÌ FÈSÖÆÆFÈŠ(ÆÆFÈÈÈÈ	Ÿ۸۰	Ÿ	ÖŠ FĒG	HÎ	FĚ		G EEE H							
FÏ J FÊGÖÆÆÆË Š(ÆÆÆÈE	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HÎ	FĚ	i Edi							_	
FÌ € FÉSÖÆÆFÉ Š(ÆÆFÉE	Ÿ۸۰	Ÿ	ÖŠ FĒG	HÎ	FĚ		G FIFE H							
FÌ F FÈSÖÆÆÆË Š(ÆÆÆÈÈÈ	Ÿ۸۰	Ÿ	ÖŠ FĒG	HÎ	FĚ		G ÈEGJ ⊦						_	
	Ÿ۸۰	Ϋ	ÖŠ FĒG	HÎ	FĚ		GE F F							
FÌ H FÈGÖÆÆFË Š(ÆÆFEE	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HÎ	FĚ								_	
FI   FESÖÆÆFE Š ÆÆFEEE		Ϋ́	ÖŠ FEG	HÏ	FĚ		GŒÍ H							
FÌÍ FÈSÖÆÆFË Š(ÆÆFÈEÈÈ	γ∧• Ÿ∧•	Ÿ						È€GJ					-	
FÌÌ FÈSÖÆÆFË Š(ÆÆFÈEÈÈ		Ϋ́		HÏ	FĚ									
	Ÿ۸∙			HÏ	FĚ		GEF F							
FÌÏ FÈGÖÆÆFË Š(ÆÆFÈÈÈÈ	Ÿ۸∙	Ÿ	ÖŠ FĒG	HÏ	FĚ		GEG F							
FÌÌ FÈSÖÆÆFĚŠ(ÆÆÆÈÈÈ		Ÿ	ÖŠ FĒG	HÏ	FĚ		GHIII H							
FÌ J FÈSÖÆÆFĚ Š(ÆÆFÈÈÈÈ		Ÿ	ÖŠ FĒG	HÏ	FĚ		G EEE H							
FJ€ FÈSÖÆÆFĚŠ(ÆÆFÈÈÈÈ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HÏ	FĚ		G EEE H							
FJF FÉGÖÆÆÆĚŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ•	Ÿ	ÖŠ FĒG	HÏ	FĚ		G EE F							
FJG FÉGÖÆÆFÉ Š ÆÆFÈE		Ÿ	ÖŠ FĒG	HÏ	FĚ		G EEE F							
FJH FÈGÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ÿ۸•	Ÿ	ÖŠ FĒG	ΗÏ	FĚ		G EE F							
FJI FÈSÖÆÆFĚŠ(ÆÆFÈÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FĒG	HÏ	FĚ		G EEEE H							
FJÍ FÉGÖÆÆÆÉŠ(ÆÆÆÉEÈÈ	Ϋ́Λ∙	Ÿ	ÖŠ FÉG	HÏ	FĚ	<b>E</b>	G⊞EEEH	IEE						

## @UX'7ca V]bUh]cbg'ff'cbh]bi YXŁ

Ö^• &¦āl cāl}	Ù[  ç^	ÚÖĦ	D&SSQ ∰Ö∰ÜÚÉ	ÓŠÔ	Øæ&d ¦	
FJÎ FÊSÖÆÆÆĚŠ(ÆÆÆÈÈÈ	ÿ∧•	Ϋ́	ÖŠ FEG	HÏ	FĚ	
FJÏ FĚSÖÆÆÆĚŠ(ÆÆÆÈÈÈÈ	ΫΛ۰	Ϋ	ÖŠ FÈG	HÏ	FĚ	JEÉÌGEGIHEE
FJÌ FÈSÖÆÆFĚŠ(ÆÆÆÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÏ	FĚ	F€EÉÌGEIFHEEÈÈ
FJJ FÉGÖÆÆFĚŠ(ÆÆÆÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HÏ	FĚ	FFEI GEI HEE
GEE FIEGÖÆÆÆË Š; ÆÆÆEE	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÌ	FĚ	I E I G E I H
GEF FÉGÖÁÉÁFÍL Š( ÁÉÁFÉEÍÍÍÍ	Ϋ́Λ∙	Ÿ	ÖŠ FÈG	HÌ	FĚ	Í EÉ Ì G EÉÍ H EEGJ
GEG FÉGÖÆÆÆË Š(ÆÆÆEE	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	Î EEÎ Î G EEI F H EEI F
GEH FREGÖÆÆÆFE Š(ÆÆÆFEE	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	
GE FÉSÖÁÉÁFÉ ŠĮ ÁÉÁFÉEÉÉ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	
GÉ FÉGÖÁÉÁFIĚ ŠĮ ÁÉÁFÈEIE	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	J léi l G leeme H léi
GEÉ FÉSÖÁÉÁFÉ ŠĮ ÁÉÁFÉEÉÉ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	F€EEIG GEEEEE HEEE F
GE FÉSÖÁÉÁFIĚ ŠĮ ÁÉÁFÈEIE	Ÿ^•	Ϋ	ÖŠ FÈG	HÌ	FĚ	FFEE I G EEE H EEGJ
GE FESÖÆÆÆË Š(ÆÆÆEEEE	ΫΛ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	I BÉÌG BÉBÉH Ï BHÉ
GEJ FÉSÖÆÆFÉ Š(ÆÆFÈE	Ϋ́Λ∙	Ÿ	ÖŠ FÉG	HÌ	FĚ	Í EÍ Ì G EEÍ H EEE
GF€ FÈSÖÆÆFË Š(ÆÆFEE	Ϋ́Λ∙	Ÿ	ÖŠ FĒG	HÌ	FĚ	Î E Î G E E H E E
GFF FÉSÖÆÆFÉ Š(ÆÆFEE	Ϋ́Λ∙	Ÿ	ÖŠ FÉG	HÌ	FĚ	
GFG FÉSÖÆÆFÉ Š(ÆÆFEE	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	Î BÉ Î G FEE H BEE
GFH FÉSÖÆÆFÉ Š(ÆÆFEE	Ÿ <b>∧•</b>	Ϋ	ÖŠ FÉG	HÌ	FĚ	JEE J C EECH H EEE
GFI FÈSÖÆÆFË Š(ÆÆFÈEÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	F€BÍÌ GBIF H EEEE
GFÍ FÉSÖÆÆFÉ Š(ÆÆFEEE)	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HÌ	FĚ	FFEE I G EE H EEEEE
GFÎ FÊSÖÆÆÆËŠ(ÆÆÆEÈÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HJ	FĚ	
GFÏ FÈSÖÆÆFËŠ(ÆÆFÈEÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FÈG	HJ	FĚ	Í EÐ Ì G ÈEÍ H ÈEGJ
GFÌ FÈSÖÆÆFËŠ(ÆÆFÈEÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HJ	FĚ	Î BÉ Ì G BE F H BE F
GFJ FÈSÖÆÆFĚŠ(ÆÆFÈ€ÈÈ	Ÿ^•	Ÿ	ÖŠ FĒG	HJ	FĚ	Ï EÉ Ì G EEGJ H EÉ
GG€ FÈSÖÆÆFÈ Š(ÆÆFÈ€ÈÈ	Ϋ́Λ∙	Ϋ	ÖŠ FĒG	HJ	FĚ	Ì 笆Ì G Hffi H 笆ì
GOF FESÖÆÆFE Š(ÆÆFEEEE	Ϋ́Λ∙	Ÿ	ÖŠ FĒG	HJ	FĚ	J 笆 i G eee H lei
GGG FÉSÖÆÆFÉ Š(ÆÆFÈEÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FÈG	HJ	FĚ	F€EEÎG GEEEE HEEF
GGH FÈSÖÆÆFË Š(ÆÆFÈEÈÈ	Ÿ∧•	Ÿ	ÖŠ FÈG	HJ	FĚ	FFEE I G EE H EEGJ
GG FÉSÖÆÆFÉ Š(ÆÆFÈEÈÈÈ	Ÿ۸•	Ÿ	ÖŠ FÈG	HJ	FĚ	I BE I G BE H I BE
GG FÈSÖÆÆFË Š(ÆÆFÈ€ÈÈÈ	Ÿ∧•	Ÿ	ÖŠ FĒG	HJ	FĚ	
GG FÈSÖÆÆFĚŠ(ÆÆFÈEÈÈ	Ÿ۸•	Ÿ	ÖŠ FÈG	HJ	FĚ	
GG FÉSÖÆÆFÉ Š(ÆÆFÈEÈÈÈ	Ÿ^•	Ÿ	ÖŠ FĖG	HJ	FĚ	
GG FÉSÖÆÆFÉ Š(ÆÆFÈEÈÈÈ	Ÿ^•	Ÿ	ÖŠ FÈG	HJ	FĚ	Ì ĐÌ G F H H H
GGJ FÉGÖÆÆFÉ Š(ÆÆFÈEÈÈÈ	Ÿ^•	Ÿ	ÖŠ FĚG	HJ	FĚ	JEG GECO HEE
GH€ FÈSÖÆÆÆĚŠ(ÆÆÆÈÈÈÈ	Ϋ́Λ•	Ÿ	ÖŠ FÈG	HJ	FĚ	F€BÍGBFHEEÈ
GHF FESÖÆÆFE Š(ÆÆFEE	Ÿ∧•	Ÿ	ÖŠ FÉG	HJ	FĚ	FFEI GEI HEE

## 9bj YcdY'>c]bhFYUMjcbg

	R[ã]c		ÝÆjaá	ŠÔ	ŸÆjaá	ŠÔ	Z <i>Ä</i> Žjàá	ŠÔ	TÝÆÇàË∙cáŠ	Ô	ΤΫ́ΑξαμὰΕ̈́αά	ŠÔ	TZÁŽàËcá	ŠÔ
F	ÞĞ	{ æ¢	FÏÏ ŒÈÌ	Н	F€ÏFĚÍ	G€	GHJÎÈEI	Ш	ÍÌÏĚ ⊦	<del>I</del> F	Î FFË Ì	НН	G€IÎÈHÎ	Н
G		{ <b>a</b> }	ËFÏÎJÈ€Ï	ĞÏ	ËF€ÏÏÈÏ	FG	ËTIHÈÌ	HF	Ë GGFÈ€J  ⊦	Ì	ËĞİİÈİ	LF	ËG€IÎÈHU	FF
Н	ÞF	{ æ¢	FÌ€ÏÈH	FΪ	F€ÌÎÈCH		GÎÍËF	ΙÍ	IHÏJÈ€FI	Î	Î⊕HÈGJ	FJ	G€JÎÈI	GÍ
1		{ <b>a</b> }	ËFÌ€HÈGI	ď	ËF€ÏJĚH	HG	ËHHÈHG	Œ	ËΪ€ĚΓŒ	Œ	ËGÎJÌÈLÍ	ΙH	ËG€JÏÈJF	FΪ
ĺ	ÞFH	{ æ¢	HÌIĒG	FÌ	FÏJ€ĚÌ	Œ	GHI È	Н	ÏÌI∄G F	7	ΙΪJIÈΉ	Н	FÏ GF <b>È</b>	FI
Î		{ <b>a</b> }	ËHJOÈ G	F€	ËFÏJFÈ€I	FI	ËÏÏĒÌ	GÎ	ËÌH Î	Î	ËÎJĔÍ	GÎ	ËÏŒĒ	Œ
Ï	V[œ <b>∳</b> K	{ æ¢	HÜHÜH	FÌ	HGIĚÏ	Î	îììîÈì	ΙG						
Ì		{ <b>a</b>	ËHÏHÈH	F€	ËHGIĚÏ	FI	FĤÏĒÏ	ÎÎ						

## 9bj YcdY5=G7 '%) h fl \*\$!% L '@F: 8 'GhYY'7cXY7\ YWg

	T^{ à^¦	Ù <b>@</b> ∯^	Ô[ å^ÁÔ@^&\	Š[&Žajá	ŠÔ	
F	ÙŒ	ÚQÚÒ HĚ	ĒH	I€	ΙÍ	ÈEFG Î € JÎIIJFËÎÎÎÍ€ÎÎJÍHËÎJÍHË
G	ÙŒH	ÚQÚÒ´HĚ	₿FJ	I€	HJ	ÈEE
Н	ÙŒF	ÚQÚÒ´HĚ	È€H	I€	Н	ËJ€   €   FI ÎIIJF#ÎÎÎÍ€   ÏJÍH#ÎÎJÍH#ÎPFËà
- 1	ÚÓG	ÔHÝÍ	ÈÏÏ	ΗĖÎ	ΙÍ	ÈFÏÎÎÊĬI^IJHGIÎÈŒÏÎGÌJÌFÈGÎ F€I EEPFËFà
ĺ	ÚÓH	ÔHÝÍ	ÈΪG	ΗĒÎ	HJ	È ÎÎHĖ HÌHGIIÈ IÎGÌ JÌFĖGÎ IF€I Ė PFËà
Î	ÚÓF	ÔHÝÍ	ÈÍΗ	ΗĖÎ	IJ	ÈFÎÎÎÉ I^HÀHGÌ (ÌÈHÉ ÏÎGÌ JÌ FÈGÎ   F€I ÈHPFËFÀ
Ï	TÚF	ÚŒÓ′GÈE	È€J	ĺĺ	FÎ	<u>REÍÏÍÍ F</u> €ŒÌÎÎÊ ##GFH€ FÌÏF###ÌÏF###PF#Fà
Ì	ΤÚJ	ÚŒÓ′GÈE	ÈU€	ĺĺ	F€	<u>FE</u> IÍÍÍ   FÍGEÌÎÎ ##HGFH€ FÌÏF##FÌÏF###PFËFà
J	ΤÚΗ	ÚŒÓ′GÈE	ÈU€	ĺĺ	ĺ	<u>rej   j                                 </u>
F€	ΤÚΙ	ÚŒÓ′GÈE	ÈÌÍ	ĺĺ	F€	<u>FE</u> IÍ ÍÏ Ú GEÌÎÎ ##HOFH€ FÌÏF##FÌÏF##FPF#Fà
FF	ΤÚΪ	ÚŒÓ′GÈE	ÈHÍÎ	ĺĺÍ	ĺ	<u>FE</u> ÍGÍÏ FÎŒÎÎÎ ##HOFH€ FÎ Ï F##FÎ Î F##F PFËFÀ
FG	TÚG	ÚŒÓ′GÈE	ÈÁÍ	ÍΪ	Î	<u>FE</u> IJ           GEÌÎÎ ##HGFH€   FÌÏ F###F   PF#Fà
FH	ΤÚÎ	ÚŒÓ′GÈE	ÈHÍÍ	ÍΪ	FÍ	<u>FEÍFÍÏ I</u> ŒÌÎÎ <del>III CFH</del> € FÌ Ï FIIII Ì Ï FIIII PFËFÀ
FI	ΤÚÌ	ÚŒÓ′GÈE	ÈHÍH	ÍΪ	F€	<u>F</u> EJÍÏ F€GEÌÎÎ <del>IIII G</del> FH€ FÌÏ FIIII ÌÏ FIIII PFËFÀ
FÍ	ΤÚĺ	ÚŒÓ′GÈE	ÈΗΪ	ÍΪ	F€	<u>F</u> EIÌÍÏ F€GEÌÎÎ⊞HGFH€ FÌÏF⊞HÌÏF⊞HFPFEFà
FÎ	ÔÚÍ	ÎLĂÄ¢€ÈHÄÄÚ æe^	ÈĜΪ	GF	FH	EFI GF 1 G (I ) E (I ( E E E E E E E E E E E E E E E E
FΪ	ÔÚÎ	ÎLĂÄ¢€ÈHÄÄÚ aœ^	ÈĠÎ	GF	Ϊ	EFFG GF ^ H G (I ) HE ( I ( I HE ) HE ( I G HE HE )
FÌ	ÔÚI	ÎLĂÄ¢€ÈHÄÄÚ æe^	ĚĠÍ	GF	G	<u>EF</u> €Î GF ^ H  GÏÍIÌ #EÍÏÍÏ #EÌ HÐÎ ÎFÏÌ ####PFËFà
FJ	TFJ	ÚŒÓ′ GÈE	ÈÍÍ	G	F€	ÈFÎHG GFIJFÎ HÊGFH€ FÎ Ï FEHÊNÎ Î FEHÊNÎ
G€	TG€	ÚŒÓ′GÈE	ÈÍΓ	G	FÍ	<u>  EFÍÌ   ÏG     Ì</u>   FIJFÎ <del>  EH</del> GFH€   FÌ ÏF <del>  EHE</del> Ì ÏF <del>  EHE</del> ÈÌ
GF	TŒ	ÚQÚÒ′ GÈE	ÈÉÍ€	ΪG	ĺ	<u> </u> EFÍJ G   FGFIJFÎ ##HGFH€ FÎ Ï F###Î Ï F###PFËFÀ
GG	<b>ØPHG</b>	ŠŒ¢ŒH	ÈHÎ	€	FI	ÈEHÏ € ^   FFÌ €   HÈCHHU CHẾ Í Ï Ë GFFÌ CHÌ P CË
GH	ØP Œ	ŠŒ¢ŒH	ÈΗ	€	H€	ÈEHÎ € : IHFÌ €Ì I BÈSHU QHE Í Ï È GFFÌ QHEF PQË
G	<b>Ø</b> PFF	ŠQ¢Q¢H	ÈHG	€	Н	EEHÎ € : IJFÎ € I BÎBHU GÊÊÎÎ Î Ê GFFÎ JÊÊF P GÊF
GÍ	<b>Ø</b> PFG	ŠŒ¢ŒH	ÈFÌ	€	J	ÈEHÎ € ^HÎFÌ€ÌIÈÈHUGËËÍÏËGFFÏJËËFPGË
Ĝ	<b>ØP</b> GG	ŠQ¢Q¢H	ÈFG	€	G	EEHÍ € ^ IÎ FÌ € I BEHU GHÉÍ Ï É GFFÌ GHÉF P GÉ
GΪ	OOP ÁHF	ŠŒ¢ŒH	ÈFF€	€	Ĝ	ÈEHÍ € : HÌ FÌ €Ì I ÈÈHU GÉÉÍ Ï É GFFÌ GÉÉF P GÉ
Ġ	PF	ÚQÚÒ´ HẾ	ÌE€Í	l lì	F€Í	ËF€ ÏG F€ÎÎÎŒÎÌÏÉÏJÍHŒÏJÍHŒEPFËà
GJ	PH	ÚQÚÒ′ HĚ	È€I	ΙÌ	G€Ï	ÈE G FÍ΀ÎÎÎĖĖÌÏÍ€ÏJÍHĖĖJÍHĖĖ PFËà
H€	PG	ÚQÚÒ′ HĚ	ÈEH	ΙÌ	FÍJ	EEH   IG       Î   Î €Î Î Î EE Î I J Í HEE J Í HEEF   PFE à
HF	ÔÚG	ÎÈİ¢IÈL΢€ÈĞÍ	ÈÎI	IG	HF	È Î € Î J Î FFÏ € Î Î Î Î F G Î Î Î Î Î Î F Î Î Î Î Î P QÎ Î
HG	ÔÚH	ÎÈİ¢IÈİ¢€ÈĞÍ	ÈÉÎG	€	GF	ÈEIÎIG^FFÍFFÏ⊕ HÏÍÎF GÎI HEFFĞHEF PŒ
HH	ÔÚF	ÎÈ΢IÈ΢€ÈĞÍ	ÈÍÌ	G€EĬÎ	FÌ	E I I G î Î ÎFFÏ ⊕ ÏÎÎF G ÎI Œ FG Œ PŒ

### 9bj YcdY5=G=G%\$!%&. '@F: 8 7c 'X': cfa YX'GhYY 7cXY7\ YWg

T^{à^¦Ù@na}^^Ô[å^ÁÔ@^&\ ŠŢ&ŽājáŠÔÙ@ca#HHŠŢ&ŽÃHHŠTåŠÔ]@and\}Ž#H‡@and\}Ž#H‡@andT}HH‡@andT}HHÈÔàÔ{^^Ô{::Ò`} Þ[ÁÖæncæÁN[ÁÚ¦ā]dÁHHÉ

# APPENDIX D ADDITIONAL CALCUATIONS

Analysis date: 07/29/21




#### **BOLT TOOL 1.5.2**

Projec	t Data
Job Code:	189041
Carrier Site ID:	BOBDL00092A
Carrier Site Name:	CT-CCI-T-876347

Code							
Design Standard:	TIA-222-H						
Slip Check:	No						
Pretension Standard:	AISC						

Bolt Properties							
Connection Type:	Bolt						
Diameter:	0.625	in					
Grade:	A325						
Yield Strength (Fy):	92	ksi					
Ultimate Strength (Fu):	120	ksi					
Number of Bolts:	4						
Threads Included:	No						
Double Shear:	No						
Connection Pipe Size:	-	in					



Connection Description	
Standoff to Monopole	

Bolt C	heck*	
Tensile Capacity $(\phi T_n)$ :		lbs
Shear Capacity $(\phi V_n)$ :	17257.3	lbs
Tension Force (T <sub>u</sub> ):	5241.1	lbs
Shear Force (V <sub>u</sub> ):	743.1	lbs
Tension Usage:	24.5%	
Shear Usage:	4.1%	
Interaction:	24.5%	Pass
Controlling Member:	SA2	
Controlling LC:	42	


<sup>\*</sup>Rating per TIA-222-H Section 15.5

# APPENDIX E SUPPLEMENTAL DRAWINGS

ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT	NOTE NO.
1 MTC3006SB	STEEL BUNDLE FOR SNUB NOSE PLATFORM	1 402.64 LBS			
2 MCPK8CSB	PIPE STEEL BUNDLE FOR MC-PK8-C	1 464.27 LBS			
3 MCPK8CHWK	HARDWARE KIT FOR MC-PK8-C	1 543.22 LBS			

	REVISIONS								
REV.	ECN	DESCRIPTION	BY	DATE					
Α		Initial release	DRR	12/27/11					
В	8000005979	CHANGE NOSE CORNER BRKT, ADD GUB-4240	MSM	11/25/14					
С	8000007579	NEW RINGMOUNT WELDMENT DESIGN	RJC	04/07/15					


# FOR BOM ENTRY ONLY




NOTES:

1. CUSTOMER ASSEMBLY SHEETS 2-3.


property of ANDREW CORPORATION and may be only for the specific purpose authorized in wr Andrew Corporation.	be used iriting by	MSM	1 of 3	MC-PK8-C
Andrew Corporation.  ALL DIMENSIONS ARE IN INCHES U.O.S.  TOLERANCES UNLESS OTHERWISE SPECIFIED:		онохо ву: ТР	NTS	LOW PROFILE PLATFORM KIT 8' FACE
.X = ± .12 ANGLES .XX = ± .06 FRACTIONS	±2° ±1/32	10/18/11	A36, A500	ASSEMBLY DRAWING
.XXX= ± .03	11/02	REVISION:	GALV A123	WESTCHESTER, IL, 60154
DO NOT SCALE THIS PRINT		C	1410.14 LBS	ANDREW @ U.S.A.






#### NOTES:

- 1. ALL METRIC DIMENSIONS ARE IN BRACKETS.
  2. WILL FIT MONOPOLES 15"-38" OD.



	ITEM	PART NO.	DESCRIPTION	QTY.	WEIGHT
>	1	MC-RM1550-3	12" - 50" OD RINGMOUNT	1	230.42 LBS
	2	MTC300601	Low Profile Co-Location Platform Snub Nose	3	134.21 LBS
	3	MT195801	Corner Weldment Snub Nose Handrail	3	27.10 LBS
	4	XA2020.01	CROSS OVER ANGLE	9	2.65 LBS
	5	GUB-4356	1/2" X 3-5/8" X 6" GALV U-BOLT	18	0.82 LBS
	6	GUB-4355	1/2" X 3-5/8" X 5" GALV U-BOLT	12	0.71 LBS
	7	GUB-4240	1/2" X 2-1/2" X 4" GALV U-BOLT	48	0.56 LBS
	8	GB-04145	1/2" X 1-1/2" GALV BOLT KIT	12	0.13 LBS
	9	GWF-04	1/2" GALV FLAT WASHER	24	0.03 LBS
	10	GB-0520A	5/8" X 2" GALV BOLT KIT (A325)	12	0.27 LBS
	11	MT54796	3.50" OD X 96" GALV PIPE	3	60.28 LBS
	12	MT-651-96	Ø 2.375" OD X 96" PIPE	3	29.07 LBS
Ī	13	MT-651	2.375" OD x 72" PIPE	9	21.80 LBS
Ī	14	MT19617	MT196 Pipe Mount Plate	6	2.49 LBS
	15	MT21701	PIPE MOUNT PLATE	9	7.93 LBS

These drawings and specifications are the proprietary property of ANDREW CORPORATION and may be used only for the specific purpose authorized in writing by Andrew Corporation.	MSM	2 of 3	MC-PK8-C
LL DIMENSIONS ARE IN INCHES U.O.S.	онахиах вт: ТР	NTS	25" OD Snub Nose MT-196
OLERANCES UNLESS OTHERWISE SPECIFIED:  .X = $\pm$ .12 ANGLES $\pm$ 2'  .XX = $\pm$ .06 FRACTIONS $\pm$ 1/32	10/18/11	A36, A53	BRANG TYSE ASSEMBLY DRAWING
.XXX= ± .03  REMOVE BURRS AND BREAK EDGES .005	REVISION:	GALV A123	WESTCHESTER, IL, 60154
DO NOT SCALE THIS PRINT	C	1361.27 LBS	ANDREW & U.S.A.



NTS

A36, A53 FNSH GALV A123

1361.27 LBS

10/18/11

С

DO NOT SCALE THIS PRINT

25" OD Snub Nose MT-196

WESTCHESTER, IL. 60154

ASSEMBLY DRAWING

NOTES:

1. ALL METRIC DIMENSIONS ARE IN BRACKETS.

# Exhibit F

**Power Density/RF Emissions Report** 



## RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOBDL00092A

876347
53 Slater Street
Manchester, Connecticut 06040

August 30, 2021

EBI Project Number: 6221004804

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	14.10%



August 30, 2021

Dish Wireless

Emissions Analysis for Site: BOBDL00092A - 876347

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **53 Slater Street** in **Manchester**, **Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu$ W/cm²). The number of  $\mu$ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu$ W/cm²). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately 400  $\mu$ W/cm² and 467  $\mu$ W/cm², respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is 1000  $\mu$ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.



Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

#### **CALCULATIONS**

Calculations were done for the proposed Dish Wireless Wireless antenna facility located at 53 Slater Street in Manchester, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 4) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.



- 5) The antennas used in this modeling are the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz channel(s) in Sector A, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz channel(s) in Sector B, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antenna mounting height centerline of the proposed antennas is 123 feet above ground level (AGL).
- 7) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 8) All calculations were done with respect to uncontrolled / general population threshold limits.



# Dish Wireless Site Inventory and Power Data

Sector:	Α	Sector:	В	Sector:	С
Antenna #:	I	Antenna #:	I	Antenna #:	I
Make / Model:	JMA MX08FRO665- 21	Make / Model:	JMA MX08FRO665- 21	Make / Model:	JMA MX08FRO665- 21
Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz	Frequency Bands:	600 MHz / 1900 MHz
Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd
Height (AGL):	I23 feet	Height (AGL):	I23 feet	Height (AGL):	123 feet
Channel Count:	8	Channel Count:	8	Channel Count:	8
Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts	Total TX Power (W):	280 Watts
ERP (W):	3,065.51	ERP (W):	3,065.51	ERP (W):	3,065.51
Antenna A1 MPE %:	1.16%	Antenna BI MPE %:	1.16%	Antenna C1 MPE %:	1.16%

# environmental | engineering | due diligence

Site Composite MPE %				
Carrier	MPE %			
Dish Wireless (Max at Sector A):	1.16%			
Sprint	0.34%			
Clearwire	0.09%			
AT&T	4.26%			
T-Mobile	3.51%			
Verizon	4.74%			
Site Total MPE % :	14.10%			

Dish Wireless MPE % Per Sector				
Dish Wireless Sector A Total:	1.16%			
Dish Wireless Sector B Total:	1.16%			
Dish Wireless Sector C Total:	1.16%			
Site Total MPE % :	14.10%			

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (μW/cm²)	Frequency (MHz)	Allowable MPE (μW/cm²)	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	123.0	2.35	600 MHz n71	400	0.59%
Dish Wireless 1900 MHz n70	4	542.70	123.0	5.70	1900 MHz n70	1000	0.57%
						Total:	1.16%

<sup>•</sup> NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

### **Summary**

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)			
Sector A:	1.16%			
Sector B:	1.16%			
Sector C:	1.16%			
Dish Wireless Maximum MPE % (Sector A):	1.16%			
Site Total:	14.10%			
Site Compliance Status:	COMPLIANT			

The anticipated composite MPE value for this site assuming all carriers present is **14.10**% of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

# Exhibit G

# **Letter of Authorization**



4545 E River Rd, Suite 320 West Henrietta, NY 14586

Phone: (585) 445-5896 Fax: (724) 416-4461 www.crowncastle.com

#### **Crown Castle Letter of Authorization**

#### CT - CONNECTICUT SITING COUNCIL

Melanie A. Bachman Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

**Re:** Tower Share Application

Crown Castle telecommunications site at: 53 SLATER STREET, MANCHESTER, CT 06040

GLOBAL SIGNAL ACQUISITIONS II LLC ("Crown Castle") hereby authorizes DISH WIRELESS, LLC, including their Agent, to act as our Agent in the processing of all zoning applications, building permits and approvals through the CT - CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:


Crown Site ID/Name: 876347/BUCKLAND MALL Customer Site ID: BOBDL00092A/CT-CCI-T-876347 Site Address: 53 Slater Street, MANCHESTER, CT 06040

By: Date: 8/18/2021

Richard Zajac
Site Acquisition Specialist

# Exhibit H

**Recipient Mailings** 





#### Instructions

- 1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO **COPY OR ALTER LABEL.**
- 2. Place your label so it does not wrap around the edge of the package.
- 3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- 4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- 5. Mail your package on the "Ship Date" you selected when creating this label.

# Click-N-Ship® Label Record

#### **USPS TRACKING #:** 9405 5036 9930 0499 6229 73

543233750 09/09/2021 Trans. #: Print Date: Ship Date: 09/09/2021 09/13/2021 Delivery Date:

Priority Mail® Postage: Total:

\$7.95 \$7.95

Ref#: DS-876347

From: DEBORAH CHASE

NORTHEAST SITE SOLUTIONS

420 MAIN ST

STE 1

STURBRIDGE MA 01566-1359


**RICH ZAJAC** 

**CROWN CASTLE** 4545 E RIVER RD

**STE 320** 

W HENRIETTA NY 14586-9024

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.





#### Instructions

- 1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO **COPY OR ALTER LABEL.**
- 2. Place your label so it does not wrap around the edge of the package.
- 3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- 4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- 5. Mail your package on the "Ship Date" you selected when creating this label.

# Click-N-Ship® Label Record

#### **USPS TRACKING #:** 9405 5036 9930 0499 6230 00

543233750 09/09/2021 Trans. #: Print Date: Ship Date: 09/09/2021 09/13/2021 Delivery Date:

Total:

Priority Mail® Postage: \$7.95 \$7.95

Ref#: DS-876347

NORTHEAST SITE SOLUTIONS

420 MAIN ST

DEBORAH CHASE

STE 1

From:

**STURBRIDGE MA 01566-1359** 


JAY MORAN

MAYOR- MANCHESTER

41 CENTER ST

MANCHESTER CT 06040-5090

Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.





#### Instructions

- 1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO **COPY OR ALTER LABEL.**
- 2. Place your label so it does not wrap around the edge of the package.
- 3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- 4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- 5. Mail your package on the "Ship Date" you selected when creating this label.

# Click-N-Ship® Label Record

#### **USPS TRACKING #:** 9405 5036 9930 0499 6230 17

543233750 09/09/2021 Trans. #: Print Date: Ship Date: 09/09/2021 09/13/2021 Delivery Date:

Priority Mail® Postage: \$7.95 \$7.95 Total:

Ref#: DS-876347 From: DEBORAH CHASE

NORTHEAST SITE SOLUTIONS

420 MAIN ST

STE 1

STURBRIDGE MA 01566-1359

**GARY ANDERSON** 


DIRECTOR OF PLANNING AND ZONING-MANCHESTER

494 MAIN ST

LINCOLN CENTER 2ND FLOOR MANCHESTER CT 06040-4102

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.







#### Instructions

- 1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO **COPY OR ALTER LABEL.**
- 2. Place your label so it does not wrap around the edge of the package.
- 3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- 4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- 5. Mail your package on the "Ship Date" you selected when creating this label.

# Click-N-Ship® Label Record

#### **USPS TRACKING #:** 9405 5036 9930 0499 6230 24

543233750 09/09/2021 Trans. #: Print Date: Ship Date: 09/09/2021 09/13/2021 Delivery Date:

Priority Mail® Postage: Total:

\$7.95 \$7.95

Ref#: DS-876347

From: DEBORAH CHASE

NORTHEAST SITE SOLUTIONS

420 MAIN ST

STE 1


STURBRIDGE MA 01566-1359

STEVE STEPHANOU

41 CENTER ST

MANCHESTER CT 06040-5090

Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.





#### Instructions

- 1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO **COPY OR ALTER LABEL.**
- 2. Place your label so it does not wrap around the edge of the package.
- 3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- 4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- 5. Mail your package on the "Ship Date" you selected when creating this label.

# Click-N-Ship® Label Record

#### **USPS TRACKING #:** 9405 5036 9930 0499 6230 31

543233750 09/09/2021 Trans. #: Print Date: Ship Date: 09/09/2021 09/13/2021 Delivery Date:

Priority Mail® Postage: Total:

\$7.95 \$7.95

Ref#: DS-876347 From: DEBORAH CHASE

NORTHEAST SITE SOLUTIONS

420 MAIN ST

STE 1

STURBRIDGE MA 01566-1359

ONE HUNDRED TWENTY-ONE CONNECTICUT AVE

ASSOC LLC 9 LAKE LN

ELLINGTON CT 06029-3044

Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.

# 876347



#### FISKDALE 458 MAIN ST FISKDALE, MA 01518-9998 (800)275-8777

FISKDALE	E, MA 015 800)275-8	18-9998	
09/10/2021	007275-0	,,,,	10:52 AM
Product	Qty	Unit Price	Price
Prepaid Mail Ellington, CT Weight: 1 lb Acceptance Dat Fri 09/10/ Tracking #: 9405 5036	1 06029 4.50 oz te: /2021		\$0.00
Prepaid Mail Manchester, C' Weight: 1 lb Acceptance Da Fri 09/10 Tracking #: 9405 5036	4.50 oz te: /2021	99 6230	\$0.00 00
Prepaid Mail Manchester, C Weight: 1 lb Acceptance Da Fri 09/10 Tracking #: 9405 5036	T 06040 4.50 oz te: /2021	99 6230	\$0.00 17
Prepaid Mail Manchester, C Weight: 1 lb Acceptance Da Fri 09/10 Tracking #: 9405 5036	T 06040 4.50 oz te: /2021		\$0.00
Prepaid Mail West Henriett Weight: O lb Acceptance Da Fri 09/10 Tracking #: 9405 5036	a, NY 14 2.00 oz ate: 0/2021	!	\$0.00