



Crown Castle  
3530 Toringdon Way  
Suite 300  
Charlotte, NC 28277

Tel: 704-405-6600

[www.crowncastle.com](http://www.crowncastle.com)

March 21, 2014

Melanie A. Bachman  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**RE: Sprint PCS-Exempt Modification - Crown Site BU: 876347**  
**Sprint PCS Site ID: CT03XC211**  
**Located at: 53 Slater Street, Manchester, CT 06040**

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to The Honorable Leo V. Diana, Mayor for the Town of Manchester.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **53 Slater Street, Manchester, CT 06040**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

March 21, 2014

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Jeff Barbadora  
Real Estate Specialist


Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: The Honorable Leo V. Diana, Mayor  
Town of Manchester  
41 Center Street  
Manchester, CT 06040



PROJECT: 2.5 EQUIPMENT DEPLOYMENT  
 SITE NAME: BUCKLAND MALL  
 SITE CASCADE: CT03XC211  
 SITE NUMBER: 876347  
 SITE ADDRESS: 53 SLATER STREET  
 MANCHESTER, CT 06040  
 SITE TYPE: MONOPOLE TOWER  
 MARKET: NORTHERN CONNECTICUT

PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT	2/12/14	MAP	B
ISSUED FOR REVIEW	1/10/14	MAP	A

SITE NAME:

BUCKLAND MALL

SITE CASCADE:

CT03XC211

SITE ADDRESS:

51 SLATER STREET  
MANCHESTER, CT 06040

SHEET DESCRIPTION:

TITLE SHEET  
& PROJECT DATA

SHEET NUMBER:

T-1

SITE INFORMATION	AREA MAP	PROJECT DESCRIPTION	DRAWING INDEX																																										
<p><b>TOWER OWNER:</b> CROWN ATLANTIC COMPANY LLC 2000 CORPORATE DRIVE CANONSBURG, PA 15317 (704) 405-6555</p> <p><b>LATITUDE (NAD83):</b> 41° 48' 18" N 41.805°</p> <p><b>LONGITUDE (NAD83):</b> 72° 32' 1" W -72.533611°</p> <p><b>COUNTY:</b> HARTFORD</p> <p><b>ZONING JURISDICTION:</b> CONNECTICUT SITING COUNCIL</p> <p><b>ZONING DISTRICT:</b> RESIDENTIAL</p> <p><b>POWER COMPANY:</b> CONNECTICUT LIGHTS AND POWER (860) 947-2000</p> <p><b>AAV PROVIDER:</b> AT&amp;T (800) 246-8484</p> <p><b>SPRINT CM:</b> PETER CULBERT (603) 203-6446 (603) 969-0686 peter.culbert@sprint.com</p> <p><b>CROWN CASTLE CM:</b> JASON D'AMICO (860)209-0104 JASON.D'AMICO@CROWNCastle.COM</p>		<p>SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.</p> <ul style="list-style-type: none"> <li>INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS</li> <li>INSTALL (3) PANEL ANTENNAS</li> <li>INSTALL (3) RRU'S TO TOWER</li> <li>INSTALL (27) JUMPER CABLES</li> <li>INSTALL (1) HYBRID CABLE</li> <li>INSTALL (8) BATTERIES IN EXISTING BBU CABINET</li> </ul> <p>THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.</p>	<table border="1"> <thead> <tr> <th>SHEET NO:</th> <th>SHEET TITLE</th> <th>REV</th> </tr> </thead> <tbody> <tr> <td>T-1</td> <td>TITLE SHEET &amp; PROJECT DATA</td> <td>B</td> </tr> <tr> <td>SP-1</td> <td>SPRINT SPECIFICATIONS</td> <td>B</td> </tr> <tr> <td>SP-2</td> <td>SPRINT SPECIFICATIONS</td> <td>B</td> </tr> <tr> <td>SP-3</td> <td>SPRINT SPECIFICATIONS</td> <td>B</td> </tr> <tr> <td>A-1</td> <td>SITE PLAN</td> <td>B</td> </tr> <tr> <td>A-2</td> <td>TOWER ELEVATION &amp; CABLE PLAN</td> <td>B</td> </tr> <tr> <td>A-3</td> <td>ANTENNA LAYOUT &amp; MOUNTING DETAILS</td> <td>B</td> </tr> <tr> <td>A-4</td> <td>COLOR CODING AND NOTES</td> <td>B</td> </tr> <tr> <td>A-5</td> <td>EQUIPMENT &amp; MOUNTING DETAILS</td> <td>B</td> </tr> <tr> <td>A-6</td> <td>CIVIL DETAILS</td> <td>B</td> </tr> <tr> <td>A-7</td> <td>PLUMBING DIAGRAM</td> <td>B</td> </tr> <tr> <td>E-1</td> <td>ELECTRICAL &amp; GROUNDING PLAN</td> <td>B</td> </tr> <tr> <td>E-2</td> <td>ELECTRICAL &amp; GROUNDING DETAILS</td> <td>B</td> </tr> </tbody> </table>	SHEET NO:	SHEET TITLE	REV	T-1	TITLE SHEET & PROJECT DATA	B	SP-1	SPRINT SPECIFICATIONS	B	SP-2	SPRINT SPECIFICATIONS	B	SP-3	SPRINT SPECIFICATIONS	B	A-1	SITE PLAN	B	A-2	TOWER ELEVATION & CABLE PLAN	B	A-3	ANTENNA LAYOUT & MOUNTING DETAILS	B	A-4	COLOR CODING AND NOTES	B	A-5	EQUIPMENT & MOUNTING DETAILS	B	A-6	CIVIL DETAILS	B	A-7	PLUMBING DIAGRAM	B	E-1	ELECTRICAL & GROUNDING PLAN	B	E-2	ELECTRICAL & GROUNDING DETAILS	B
SHEET NO:	SHEET TITLE	REV																																											
T-1	TITLE SHEET & PROJECT DATA	B																																											
SP-1	SPRINT SPECIFICATIONS	B																																											
SP-2	SPRINT SPECIFICATIONS	B																																											
SP-3	SPRINT SPECIFICATIONS	B																																											
A-1	SITE PLAN	B																																											
A-2	TOWER ELEVATION & CABLE PLAN	B																																											
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	B																																											
A-4	COLOR CODING AND NOTES	B																																											
A-5	EQUIPMENT & MOUNTING DETAILS	B																																											
A-6	CIVIL DETAILS	B																																											
A-7	PLUMBING DIAGRAM	B																																											
E-1	ELECTRICAL & GROUNDING PLAN	B																																											
E-2	ELECTRICAL & GROUNDING DETAILS	B																																											
		<p><b>APPLICABLE CODES</b></p> <p>ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.</p> <ol style="list-style-type: none"> <li>INTERNATIONAL BUILDING CODE (2012 IBC)</li> <li>TIA-EIA-222-F OR LATEST EDITION</li> <li>NFPA 780 - LIGHTNING PROTECTION CODE</li> <li>2011 NATIONAL ELECTRIC CODE OR LATEST EDITION</li> <li>ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS</li> <li>CT BUILDING CODE</li> <li>LOCAL BUILDING CODE</li> <li>CITY/COUNTY ORDINANCES</li> </ol>																																											







**CONTINUE FROM SP-1**

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER.
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNA AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

**3.2 GENERAL REQUIREMENTS FOR CIVIL CONSTRUCTION:**

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
  1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
  2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

**3.3 DELIVERABLES:**

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
  1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
  2. PROJECT PROGRESS REPORTS.
  3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
  4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
  - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
  - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 SUBMITTALS:
  - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
  - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL
    1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
    2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
    3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
    4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
    5. CHEMICAL GROUNDING DESIGN
  - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

**1.4 TESTS AND INSPECTIONS:**

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
  1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
  2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
  3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
  1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
  2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
  3. ALL AVAILABLE JURISDICTIONAL INFORMATION
  4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

**3.1 REQUIREMENTS FOR TESTING:**

**A. THIRD PARTY TESTING AGENCY:**

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

**3.2 REQUIRED TESTS:**

**A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:**

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

**3.3 REQUIRED INSPECTIONS**

**A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.**

**B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:**

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH, DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNA ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT	2/12/14	MAP	B
ISSUED FOR REVIEW	1/10/14	MAP	A

SITE NAME:

**BUCKLAND MALL**

SITE CASCADE:

**CT03XC211**

SITE ADDRESS:

**51 SLATER STREET  
MANCHESTER, CT 06040**

SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:

**SP-2**



**CONTINUE FROM SP-2**

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
  - 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
  - 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
  - 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
  - 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
  - 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
- A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
- 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
  - 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
  - 3. SITE RESISTANCE TO EARTH TEST.
  - 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
  - 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
  - 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
- B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
- 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
  - 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
  - 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
  - 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
  - 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
  - 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
  - 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
  - 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
  - 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

**SECTION 01 400 - SUBMITTALS & TESTS**

**PART 1 - GENERAL**

1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

1.2 RELATED DOCUMENTS:

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
- B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.

**PART 2 - PRODUCTS (NOT USED)**

**PART 3 - EXECUTION**

3.1 WEEKLY REPORTS:

- A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
- B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.

3.2 PROJECT CONFERENCE CALLS:

- A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.

3.3 PROJECT TRACKING IN SMS:

- A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.

3.4 ADDITIONAL REPORTING:

- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.

3.5 PROJECT PHOTOGRAPHS:

- A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:

- 1. SHELTER AND TOWER OVERVIEW.
- 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
- 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
- 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
- 5. PHOTOS OF TOWER SECTION STACKING.
- 6. CONCRETE TESTING / SAMPLES.
- 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
- 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
- 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
- 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
- 11. COAX CABLE ENTRY INTO SHELTER.
- 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
- 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
- 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
- 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
- 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
- 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
- 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL.
- 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL.
- 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL.
- 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).

- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADII).
- 25. ALL BTS GROUND CONNECTIONS.
- 26. ALL GROUND TEST WELLS.
- 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
- 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
- 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
- 30. GPS ANTENNAS.
- 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
- 32. DOGHOUSE/CABLE EXIT FROM ROOF.
- 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
- 34. MASTER BUS BAR.
- 35. TELCO BOARD AND NIU.
- 36. ELECTRICAL DISTRIBUTION WALL.
- 37. CABLE ENTRY WITH SURGE SUPPRESSION.
- 38. ENTRANCE TO EQUIPMENT ROOM.
- 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
- 40. COAX GROUNDING -TOP AND BOTTOM OF TOWER.
- 41. ANTENNA AND MAST GROUNDING.
- 42. LANDSCAPING - WHERE APPLICABLE.

3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT	2/12/14	MAP	B
ISSUED FOR REVIEW	1/10/14	MAP	A

SITE NAME:

**BUCKLAND MALL**

SITE CASCADE:

**CT03XC211**

SITE ADDRESS:

**51 SLATER STREET  
MANCHESTER, CT 06040**



SHEET DESCRIPTION:

**SPRINT SPECIFICATIONS**

SHEET NUMBER:



**SP-3**

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:  
**Sprint**  
 6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:  
**INFINIGY** Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 353-000

MLA PARTNER:  
**CROWN CASTLE**

ENGINEERING LICENSE:  
  
 JOHN S. STEVENS  
 No. 24705  
 LICENSED PROFESSIONAL ENGINEER

DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT	2/12/14	MAP	B
ISSUED FOR REVIEW	1/10/14	MAP	A

SITE NAME:  
**BUCKLAND MALL**


SITE CASCADE:  
**CT03XC211**

SITE ADDRESS:  
 51 SLATER STREET  
 MANCHESTER, CT 06040

SHEET DESCRIPTION:  
**SITE PLAN**

SHEET NUMBER:  
**A-1**





DETAIL NOT USED

NO SCALE

2

TOWER ELEVATION

NO SCALE

1

DETAIL NOT USED

NO SCALE

3

DETAIL NOT USED

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT		2/12/14	MAP	B
ISSUED FOR REVIEW		1/10/14	MAP	A

SITE NAME:

BUCKLAND MALL

SITE CASCADE:

CT03XC211

SITE ADDRESS:

51 SLATER STREET  
MANCHESTER, CT 06040

SHEET DESCRIPTION:

TOWER ELEVATION  
& CABLE PLAN

SHEET NUMBER:

A-2



DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT		2/12/14	MAP	B
ISSUED FOR REVIEW		1/10/14	MAP	A

SITE NAME:  
**BUCKLAND MALL**

SITE CASCADE:  
**CT03XC211**

SITE ADDRESS:  
**51 SLATER STREET  
MANCHESTER, CT 06040**

SHEET DESCRIPTION:  
**ANTENNA LAYOUT  
& MOUNTING DETAILS**

SHEET NUMBER:  
**A-3**

**NOTE:**  
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET


THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.

**NOTE:**  
CONTRACTOR SHALL NOT INSTALL THE 2.5 RRU'S SUCH THAT THEY IMPEDE CLIMBING ACCESS ON THE TOWER.


**NOTE:**  
CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

**NOTE:**  
SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.


**NOTE:**  
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS




**EXISTING ANTENNA & RRU LAYOUT** NO SCALE 1



**FINAL ANTENNA LAYOUT** NO SCALE 2



**DETAIL NOT USED** NO SCALE 3




**TYPICAL ANTENNA & RRU MOUNTING DETAILS** NO SCALE 4

NV CABLES				
BAND	INDICATOR		PORT	COLOR
800-1	YEL	GRN	NV-1	GRN
1900-1	YEL	RED	NV-2	BLU
1900-2	YEL	BRN	NV-3	BRN
1900-3	YEL	BLU	NV-4	WHT
1900-4	YEL	SLT	NV-5	RED
800-2	YEL	ORG	NV-6	SLT
SPARE	YEL	WHT	NV-7	PPL
2500	YEL	PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL	WHT	GRN
YEL	WHT	BLU
YEL	WHT	BRN
YEL	WHT	WHT
YEL	WHT	RED
YEL	WHT	SLT
YEL	WHT	PPL
YEL	WHT	ORG

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2	Blue	No Tape	No Tape
	3		No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2	Blue	Blue	No Tape
	3			No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2	Blue	Blue	Blue
	3			
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL	GRN
1900-1	YEL	RED
1900-2	YEL	BRN
1900-3	YEL	BLU
1900-4	YEL	SLT
800-1	YEL	ORG
RESERVED	YEL	WHT
RESERVED	YEL	PPL

2.5 FREQUENCY	INDICATOR	ID
2500 -1	YEL	WHT
2500 -2	YEL	WHT
2500 -3	YEL	WHT
2500 -4	YEL	WHT
2500 -5	YEL	WHT
2500 -6	YEL	WHT
2500 -7	YEL	WHT
2500 -8	YEL	WHT



PLANS PREPARED FOR:

6580 Sprint Parkway  
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd  
Albany, NY 12205  
Office # (518) 690-0790  
Fax # (518) 690-0793  
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT		2/12/14	MAP	B
ISSUED FOR REVIEW		1/10/14	MAP	A

SITE NAME:

BUCKLAND MALL

SITE CASCADE:

CT03XC211

SITE ADDRESS:

51 SLATER STREET  
MANCHESTER, CT 06040

SHEET DESCRIPTION:


COLOR CODING AND NOTES

SHEET NUMBER:


A-4




RRU: ALCATEL LUCENT TD-RRH8X20  
 UNIT WEIGHT: 70LBS  
 UNIT COLOR: LIGHT GRAY



SIDE VIEW




FRONT VIEW



PLAN VIEW

**NOTES**  
 COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN



FRONT VIEW

- DS3 SURGE PROTECTOR
- POWER INJECTOR 5-8
- POWER INJECTOR 1-4
- 7210 SAS-M 2
- 7210 SAS-M 1
- 7205 SAR-B
- LTE-BBU 2.5GHz
- LTE-BBU FDD
- CDMA MT-BBU GROWTH
- CDMA MT-BBU PRIMARY
- PDP1
- PDP2
- 15MHz SPLITTER
- ETHERNET HUB SEC-B
- PRIMARY PROTECTION T1
- SEC-B #1, #1 & #3
- RECTIFIER SHELF PRIMARY
- RECTIFIER SHELF 2.5GHz

2.5 RRU'S

NO SCALE

1


NEW EQUIPMENT IN EXISTING CABINET

NO SCALE


2

ANTENNA: RFS APXVTM14-C-I20

RADOME MATERIAL: ASA  
 RADOME COLOR: LIGHT GRAY  
 DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)  
 WEIGHT: 52.9 lbs  
 CONNECTORS: (8) 4.1/9.5 DIN FEMALE  
 (1) NF - CALIBRATION CONNECTOR



PLAN VIEW



2.5 ANTENNA

NO SCALE

3

DETAIL NOT USED

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT	2/12/14	MAP	B
ISSUED FOR REVIEW	1/10/14	MAP	A

SITE NAME:

BUCKLAND MALL

SITE CASCADE:

CT03XC211

SITE ADDRESS:

51 SLATER STREET  
 MANCHESTER, CT 06040

SHEET DESCRIPTION:


EQUIPMENT &  
 MOUNTING DETAILS

SHEET NUMBER:


A-5








ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT	2/12/14	MAP	B
ISSUED FOR REVIEW	1/10/14	MAP	A

SITE NAME:

BUCKLAND MALL

SITE CASCADE:

CT03XC211

SITE ADDRESS:

51 SLATER STREET  
MANCHESTER, CT 06040

SHEET DESCRIPTION:

PLUMBING DIAGRAM

SHEET NUMBER:

A-7

DRAWING NOTICE:  
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
REVISED PER COMMENT	2/12/14	MAP	B
ISSUED FOR REVIEW	1/10/14	MAP	A

SITE NAME:  
**BUCKLAND MALL**

SITE CASCADE:  
**CT03XC211**

SITE ADDRESS:  
**51 SLATER STREET  
MANCHESTER, CT 06040**

SHEET DESCRIPTION:  
**ELECTRICAL &  
GROUNDING PLAN**


SHEET NUMBER:  
**E-1**

PLAN NOT USED

NO SCALE

1


- LEGEND:**
- G — EXISTING GROUND RING
  - CADWELD CONNECTION (EXOTHERMIC WELD)
  - ▲ MECHANICAL CONNECTION
  - ⊗ GROUND ROD
  - CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2



NOTE:  
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION


TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE

3



**NOTES**  
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

PLANS PREPARED FOR:  
**Sprint**  
 6580 Sprint Parkway  
 Overland Park, Kansas 66251

PLANS PREPARED BY:  
**INFINIGY** Design. Build. Deliver.  
 1033 Watervliet Shaker Rd  
 Albany, NY 12205  
 Office # (518) 690-0790  
 Fax # (518) 690-0793  
 JOB NUMBER 353-000

MLA PARTNER:  
**CROWN CASTLE**



DRAWING NOTICE:  
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:				
DESCRIPTION	DATE	BY	REV	
REVISED PER COMMENT	2/12/14	MAP	B	
ISSUED FOR REVIEW	1/10/14	MAP	A	

SITE NAME:  
**BUCKLAND MALL**

SITE CASCADE:  
**CT03XC211**


SITE ADDRESS:  
 51 SLATER STREET  
 MANCHESTER, CT 06040

SHEET DESCRIPTION:  
**ELECTRICAL & GROUNDING DETAILS**

SHEET NUMBER:  
**E-2**

**ELECTRICAL ONE-LINE DIAGRAM**


NO SCALE 1



**NOTES**  
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.  
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.


**INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR**

NO SCALE 2



**TWO HOLE LUG**

NO SCALE 3



**GROUNDING RISER DIAGRAM**

NO SCALE 4

Date: January 04, 2014

Patrick Byrum  
Crown Castle  
3530 Torringdon Way, Suite 300  
Charlotte, NC 28277



Crown Castle  
2000 Corporate Dr.  
Canonsburg, PA 15317  
(724) 413-2000

**Subject: Structural Analysis Report**

**Carrier Designation:** *Sprint PCS Co-Locate* Scenario 2.5A  
**Carrier Site Number:** CT03XC211  
**Carrier Site Name:** BUCKLAND MALL

**Crown Castle Designation:** **Crown Castle BU Number:** 876347  
**Crown Castle Site Name:** BUCKLAND MALL  
**Crown Castle JDE Job Number:** 214847  
**Crown Castle Work Order Number:** 576254  
**Crown Castle Application Number:** 173329 Rev. 3

**Engineering Firm Designation:** **Crown Castle Project Number:** 694694

**Site Data:** **53 Slater Street, MANCHESTER, Hartford County, CT**  
**Latitude 41° 48' 18", Longitude -72° 32' 1"**  
**155 Foot - Monopole Tower**

Dear Patrick Byrum,

Crown Castle is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 576254, in accordance with application 173329, revision 3.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC11: Existing + Reserved + Proposed Equipment **Sufficient Capacity**  
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.


This analysis has been performed in accordance with the TIA/EIA-222-F standard and 2005 CT State Building Code with 2009 amendment based upon a wind speed of 80 mph fastest mile.

All equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at Crown Castle appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Jeannette Messmer, EIT / AJF  
Respectfully submitted by:

Jamal A. Huwel, P.E.  
Manager, Engineering





## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

### 3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Components vs. Capacity

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

This tower is a 155 ft Monopole tower designed by SUMMIT in February of 2002. The tower was originally designed for a wind speed of 80 mph per TIA/EIA-222-F.

## 2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a fastest mile wind speed of 80 mph with no ice, 37.6 mph with 1 inch ice thickness and 50 mph under service loads.

**Table 1 - Proposed Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
155.0	155.0	3	alcatel lucent	TD-RRH8x20-25	1	5/8	
		3	rfs celwave	APXVTM14-C-120 w/ Mount Pipe			

**Table 2 - Existing and Reserved Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
155.0	155.0	3	argus technologies	LPX310R	3 3 3	1/2 5/16 1-1/4	1
		3	rfs celwave	APXVSP18-C-A20 w/ Mount Pipe			
		3	samsung telecommunication	WIMAX DAP HEAD			
		1	tower mounts	Platform Mount [LP 713-1]			
	151.0	1	andrew	VHLP1-23			
		1	andrew	VHLP2-11			
		1	andrew	VHLP2.5-18			
153.0	153.0	3	alcatel lucent	800MHz 2X50W RRH W/FILTER			
		3	alcatel lucent	PCS 1900MHz 4x45W-65MHz			
		1	tower mounts	Side Arm Mount [SO 102-3]			
145.0	145.0	6	ericsson	RRUS-11	1 6 2	3/8 1-1/4 3/4	1
		1	tower mounts	Side Arm Mount [SO 102-3]			
143.0	145.0	3	kathrein	800 10121 w/ Mount Pipe			
		3	kmw communications	AM-X-CD-16-65-00T-RET w/ Mount Pipe			
		6	powerwave tech	LGP21401			
	1	raycap	DC6-48-60-18-8F				
	143.0	1	tower mounts	T-Arm Mount [TA 702-3]			
133.0	133.0	3	ericsson	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	1	1-5/8	2



Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
		3	ericsson	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	12	1-5/8	1
		3	ericsson	KRY 112 144/1			
		1	tower mounts	Platform Mount [LP 403-1]			
113.0	113.0	3	alcatel lucent	RRH2X40-07-U	13 1	1-5/8 1/4	1
		3	alcatel lucent	RRH2x40-AWS			
		3	andrew	LNx-6512DS-T0M w/ Mount Pipe			
		3	antel	BXA-171063-12BF w/ Mount Pipe			
		2	antel	BXA-70063/6CFx2 w/ Mount Pipe			
		1	antel	BXA-70063/6CFx4 w/ Mount Pipe			
		1	rfs celwave	DB-T1-6Z-8AB-0Z			
		3	rymsa wireless	MG D3-800Tx w/ Mount Pipe			
		1	tower mounts	Platform Mount [LP 601-1]			
103.0	103.0	3	rfs celwave	APXV18-206517S-C w/ Mount Pipe	6	1-5/8	1
78.0	78.0	12	decibel	844G65VTZASX w/ Mount Pipe	12	7/8	3
		1	tower mounts	Platform Mount [LP 303-1]			
60.0	60.0	1	tower mounts	Side Arm Mount [SO 701-1]	1	1/2	1
		1	trimble	ACUTIME 2000			

- Notes:  
 1) Existing Equipment  
 2) Reserved Equipment  
 3) Equipment To Be Removed; Not Considered in Analysis

**Table 3 - Design Antenna and Cable Information**

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
155	155	9	Decibel	DB980H90		-
145	145	6	Allgon	7250.03		-
133	133	6	EMS	RR90-17-00DP PCS		-
50	50	1	Generic	GPS Antenna		-

**3) ANALYSIS PROCEDURE**

**Table 4 - Documents Provided**

Document	Remarks	Reference	Source
4-GEOTECHNICAL REPORTS	FDH Engineering, Inc.	1533476	CCISITES
4-TOWER FOUNDATION DRAWINGS/DESIGN/SPECS	Paul J. Ford	1615406	CCISITES
4-TOWER MANUFACTURER DRAWINGS	Paul J. Ford	2068033	CCISITES

### 3.1) Analysis Method

tnxTower (version 6.1.3.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

### 3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) When applicable, transmission cables are considered as structural components for calculating wind loads as allowed by TIA/EIA-222-F.

This analysis may be affected if any assumptions are not valid or have been made in error. Crown Castle should be notified to determine the effect on the structural integrity of the tower.

## 4) ANALYSIS RESULTS

**Table 5 - Section Capacity (Summary)**

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	155 - 115.5	Pole	TP29.308x22x0.25	1	-8.16	1080.07	59.4	Pass
L2	115.5 - 79.25	Pole	TP35.514x28.1142x0.3125	2	-15.29	1772.22	87.1	Pass
L3	79.25 - 43.75	Pole	TP41.456x34.0565x0.375	3	-23.01	2481.90	94.5	Pass
L4	43.75 - 0	Pole	TP48.8x39.7348x0.4375	4	-36.92	3491.31	94.5	Pass
							Summary	
						Pole (L3)	94.5	Pass
						Rating =	94.5	Pass

**Table 6 - Tower Component Stresses vs. Capacity - LC11**

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	0	87.8	Pass
1	Base Plate	0	71.9	Pass
1	Base Foundation	0	64.8	Pass

<b>Structure Rating (max from all components) =</b>	<b>94.5%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.


### 4.1) Recommendations

The tower and foundation have sufficient capacity to carry the existing, reserved, and proposed loading. No structural modifications are required at this time.



**APPENDIX A**  
**TNXTOWER OUTPUT**

Section	1	2	3	4
Length (ft)	39.50	40.00	40.00	49.00
Number of Sides	18	18	18	18
Thickness (in)	0.2500	0.3125	0.3750	0.4375
Socket Length (ft)	3.75	4.50	5.25	39.7348
Top Dia (in)	22.0000	28.1142	34.0565	39.7348
Bot Dia (in)	29.3080	35.5140	41.4560	48.8000
Grade	A607-60	A607-60	A607-65	A607-65
Weight (K)	2.7	4.3	6.1	10.1
				23.2



**DESIGNED APPURTENANCE LOADING**


TYPE	ELEVATION	TYPE	ELEVATION
LPX310R	155	DC6-48-60-18-8F	143
LPX310R	155	800 10121 w/ Mount Pipe	143
LPX310R	155	800 10121 w/ Mount Pipe	143
WIMAX DAP HEAD	155	(2) 5' x 2" Pipe Mount	133
WIMAX DAP HEAD	155	(2) 5' x 2" Pipe Mount	133
WIMAX DAP HEAD	155	(2) 5' x 2" Pipe Mount	133
HORIZON COMPACT	155	Platform Mount [LP 403-1]	133
HORIZON COMPACT	155	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	133
HORIZON COMPACT	155	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	133
9' x 2" Pipe Mount	155	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	133
9' x 2" Pipe Mount	155	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	133
9' x 2" Pipe Mount	155	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	133
APXVSP18-C-A20 w/ Mount Pipe	155	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	133
APXVSP18-C-A20 w/ Mount Pipe	155	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	133
APXVSP18-C-A20 w/ Mount Pipe	155	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	133
Platform Mount [LP 713-1]	155	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	133
TD-RRH8x20-25	155	ERICSSON AIR 21 B4A B2P w/ Mount Pipe	133
APXVTM14-C-120 w/ Mount Pipe	155	KRY 112 144/1	133
TD-RRH8x20-25	155	KRY 112 144/1	133
APXVTM14-C-120 w/ Mount Pipe	155	KRY 112 144/1	133
TD-RRH8x20-25	155	KRY 112 144/1	133
APXVTM14-C-120 w/ Mount Pipe	155	LNx-6512DS-T0M w/ Mount Pipe	113
VHLP2.5-18	155	LNx-6512DS-T0M w/ Mount Pipe	113
VHLP1-23	155	LNx-6512DS-T0M w/ Mount Pipe	113
VHLP2-11	155	RRH2x40-AWS	113
800MHz 2X50W RRH W/FILTER	153	RRH2x40-AWS	113
800MHz 2X50W RRH W/FILTER	153	RRH2x40-AWS	113
800MHz 2X50W RRH W/FILTER	153	RRH2x40-07-U	113
PCS 1900MHz 4x45W-65MHz	153	RRH2x40-07-U	113
PCS 1900MHz 4x45W-65MHz	153	RRH2x40-07-U	113
PCS 1900MHz 4x45W-65MHz	153	DB-T1-6Z-8AB-0Z	113
Side Arm Mount [SO 102-3]	153	Platform Mount [LP 601-1]	113
Side Arm Mount [SO 102-3]	145	BXA-70063/6CFx2 w/ Mount Pipe	113
(2) RRUS-11	145	BXA-70063/6CFx2 w/ Mount Pipe	113
(2) RRUS-11	145	BXA-70063/6CFx4 w/ Mount Pipe	113
(2) RRUS-11	145	MG D3-800Tx w/ Mount Pipe	113
AM-X-CD-16-65-00T-RET w/ Mount Pipe	143	MG D3-800Tx w/ Mount Pipe	113
T-Arm Mount [TA 702-3]	143	MG D3-800Tx w/ Mount Pipe	113
800 10121 w/ Mount Pipe	143	BXA-171063-12BF w/ Mount Pipe	113
(2) LGP21401	143	BXA-171063-12BF w/ Mount Pipe	113
(2) LGP21401	143	APXV18-206517S-C w/ Mount Pipe	103
(2) LGP21401	143	APXV18-206517S-C w/ Mount Pipe	103
AM-X-CD-16-65-00T-RET w/ Mount Pipe	143	APXV18-206517S-C w/ Mount Pipe	103
AM-X-CD-16-65-00T-RET w/ Mount Pipe	143	Side Arm Mount [SO 701-1]	60
AM-X-CD-16-65-00T-RET w/ Mount Pipe	143	ACUTIME 2000	60

**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A607-60	60 ksi	75 ksi	A607-65	65 ksi	80 ksi

**TOWER DESIGN NOTES**

1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 94.5%



<p><b>Crown Castle</b> 2000 Corporate Dr. Canonsburg, PA 15317 We Are Solutions Phone: (724) 413-2000 FAX:</p>	<b>Job: BU# 876347</b>		
	Project:		
	Client: Crown Castle	Drawn by: jmessmer	App'd:
	Code: TIA/EIA-222-F	Date: 01/03/14	Scale: NTS
	Path: R:\SA Models - Letters\Work Area\messmer\876347\876347.er		

## Tower Input Data

There is a pole section.  
 This tower is designed using the TIA/EIA-222-F standard.  
 The following design criteria apply:

- 4) Tower is located in Hartford County, Connecticut.
- 5) Basic wind speed of 80 mph.
- 6) Nominal ice thickness of 1.0000 in.
- 7) Ice thickness is considered to increase with height.
- 8) Ice density of 56 pcf.
- 9) A wind speed of 38 mph is used in combination with ice.
- 10) Temperature drop of 50 °F.
- 11) Deflections calculated using a wind speed of 50 mph.
- 12) A non-linear (P-delta) analysis was used.
- 13) Pressures are calculated at each section.
- 14) Stress ratio used in pole design is 1.333.
- 15) Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

- |  |  |  |
|--|--|--|
| Consider Moments - Legs<br>Consider Moments - Horizontals<br>Consider Moments - Diagonals<br>Use Moment Magnification<br>✓ Use Code Stress Ratios<br>✓ Use Code Safety Factors - Guys<br>✓ Escalate Ice<br>Always Use Max Kz<br>Use Special Wind Profile<br>Include Bolts In Member Capacity<br>Leg Bolts Are At Top Of Section<br>Secondary Horizontal Braces Leg<br>Use Diamond Inner Bracing (4 Sided)<br>Add IBC .6D+W Combination | Distribute Leg Loads As Uniform<br>Assume Legs Pinned<br>✓ Assume Rigid Index Plate<br>✓ Use Clear Spans For Wind Area<br>Use Clear Spans For KL/r<br>Retension Guys To Initial Tension<br>✓ Bypass Mast Stability Checks<br>✓ Use Azimuth Dish Coefficients<br>✓ Project Wind Area of Appurt.<br>Autocalc Torque Arm Areas<br>SR Members Have Cut Ends<br>✓ Sort Capacity Reports By Component<br>Triangulate Diamond Inner Bracing<br>Use TIA-222-G Tension Splice<br>Capacity Exemption | Treat Feedline Bundles As Cylinder<br>Use ASCE 10 X-Brace Ly Rules<br>Calculate Redundant Bracing Forces<br>Ignore Redundant Members in FEA<br>SR Leg Bolts Resist Compression<br>All Leg Panels Have Same Allowable<br>Offset Girt At Foundation<br>✓ Consider Feedline Torque<br>Include Angle Block Shear Check<br><div style="text-align: center; background-color: #e0e0e0; padding: 2px;">Poles</div> ✓ Include Shear-Torsion Interaction<br>Always Use Sub-Critical Flow<br>Use Top Mounted Sockets |
|--|--|--|

## Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	155.00-115.50	39.50	3.75	18	22.0000	29.3080	0.2500	1.0000	A607-60 (60 ksi)
L2	115.50-79.25	40.00	4.50	18	28.1142	35.5140	0.3125	1.2500	A607-65 (65 ksi)
L3	79.25-43.75	40.00	5.25	18	34.0565	41.4560	0.3750	1.5000	A607-65 (65 ksi)
L4	43.75-0.00	49.00		18	39.7348	48.8000	0.4375	1.7500	A607-65 (65 ksi)

## Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	I/Q in <sup>2</sup>	w in	w/t
---------	----------------	-------------------------	----------------------	---------	---------	------------------------	----------------------	------------------------	---------	-----



Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	I/Q in <sup>2</sup>	w in	w/t
L1	22.3394	17.2586	1031.4832	7.7212	11.1760	92.2945	2064.3237	8.6310	3.4320	13.728
	29.7601	23.0575	2459.6966	10.3156	14.8885	165.2082	4922.6297	11.5310	4.7182	18.873
L2	29.2523	27.5758	2692.8279	9.8696	14.2820	188.5468	5389.1990	13.7905	4.3981	14.074
	36.0619	34.9155	5466.1042	12.4965	18.0411	302.9804	10939.4008	17.4611	5.7005	18.241
L3	35.4272	40.0894	5745.8039	11.9569	17.3007	332.1137	11499.1684	20.0485	5.3339	14.224
	42.0955	48.8967	10425.5424	14.5838	21.0596	495.0483	20864.8031	24.4530	6.6363	17.697
L4	41.3340	54.5692	10646.6064	13.9505	20.1853	527.4439	21307.2218	27.2898	6.2233	14.225
	49.5528	67.1574	19844.8883	17.1687	24.7904	800.5070	39715.8890	33.5851	7.8188	17.872

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A <sub>r</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontals in
ft	ft <sup>2</sup>	in						
L1 155.00-115.50				1	1	1		
L2 115.50-79.25				1	1	1		
L3 79.25-43.75				1	1	1		
L4 43.75-0.00				1	1	1		

### Feed Line/Linear Appurtenances - Entered As Area

Description	Face or Leg	Allow Shield	Component Type	Placement	Total Number		C <sub>A</sub> A <sub>A</sub>	Weight
				ft			ft <sup>2</sup> /ft	plf
ATCB-B01-005( 5/16)	B	No	CaAa (Out Of Face)	155.00 - 0.00	3	No Ice	0.00	0.07
						1/2" Ice	0.00	0.57
						1" Ice	0.00	1.68
						2" Ice	0.00	5.73
						4" Ice	0.00	21.16
FSJ4-50B(1/2")	B	No	CaAa (Out Of Face)	155.00 - 0.00	5	No Ice	0.00	0.14
						1/2" Ice	0.00	0.76
						1" Ice	0.00	2.00
						2" Ice	0.00	6.30
						4" Ice	0.00	22.23
2" Rigid Conduit	B	No	CaAa (Out Of Face)	155.00 - 0.00	2	No Ice	0.20	2.80
						1/2" Ice	0.30	4.33
						1" Ice	0.40	6.47
						2" Ice	0.60	12.57
						4" Ice	1.00	32.12
* HB114-1-08U4-M5J(1 1/4")	C	No	Inside Pole	155.00 - 0.00	3	No Ice	0.00	1.08
						1/2" Ice	0.00	1.08
						1" Ice	0.00	1.08
						2" Ice	0.00	1.08
						4" Ice	0.00	1.08
HB058-M12-XXXF(5/8")	C	No	Inside Pole	155.00 - 0.00	1	No Ice	0.00	0.24
						1/2" Ice	0.00	0.24
						1" Ice	0.00	0.24
						2" Ice	0.00	0.24
						4" Ice	0.00	0.24
*** LDF6-50A(1-1/4")	A	No	Inside Pole	145.00 - 0.00	6	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
						2" Ice	0.00	0.66
						4" Ice	0.00	0.66
FB-L98B-002-75000( 3/8")	A	No	Inside Pole	143.00 - 0.00	1	No Ice	0.00	0.06
						1/2" Ice	0.00	0.06

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C <sub>AA</sub> ft <sup>2</sup> /ft	Weight plf
WR-VG86ST-BRD(3/4)	A	No	Inside Pole	143.00 - 0.00	2	1" Ice	0.00	0.06
						2" Ice	0.00	0.06
						4" Ice	0.00	0.06
						No Ice	0.00	0.59
						1/2" Ice	0.00	0.59
						1" Ice	0.00	0.59
						2" Ice	0.00	0.59
4" Ice	0.00	0.59						
***								
LCF158-50JA-A0(1 5/8")	A	No	Inside Pole	133.00 - 0.00	12	No Ice	0.00	0.08
						1/2" Ice	0.00	0.08
						1" Ice	0.00	0.08
						2" Ice	0.00	0.08
						4" Ice	0.00	0.08
MLE Hybrid 9Power/18Fiber RL 2(1 5/8)	A	No	CaAa (Out Of Face)	133.00 - 0.00	1	No Ice	0.16	1.07
						1/2" Ice	0.26	2.37
						1" Ice	0.36	4.28
						2" Ice	0.56	9.93
						4" Ice	0.96	28.56
***								
561(1-5/8")	B	No	Inside Pole	113.00 - 0.00	13	No Ice	0.00	1.35
						1/2" Ice	0.00	1.35
						1" Ice	0.00	1.35
						2" Ice	0.00	1.35
						4" Ice	0.00	1.35
ATCB-B01-060(1/4")	B	No	Inside Pole	113.00 - 0.00	1	No Ice	0.00	0.07
						1/2" Ice	0.00	0.07
						1" Ice	0.00	0.07
						2" Ice	0.00	0.07
						4" Ice	0.00	0.07
***								
AVA7-50(1-5/8)	B	No	CaAa (Out Of Face)	103.00 - 0.00	6	No Ice	0.00	0.70
						1/2" Ice	0.00	2.23
						1" Ice	0.00	4.38
						2" Ice	0.00	10.50
						4" Ice	0.00	30.07
***								
***								
LDF4-50A(1/2")	C	No	Inside Pole	60.00 - 0.00	1	No Ice	0.00	0.15
						1/2" Ice	0.00	0.15
						1" Ice	0.00	0.15
						2" Ice	0.00	0.15
						4" Ice	0.00	0.15

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>AA</sub> In Face ft <sup>2</sup>	C <sub>AA</sub> Out Face ft <sup>2</sup>	Weight K
L1	155.00-115.50	A	0.000	0.000	0.000	2.844	0.19
		B	0.000	0.000	0.000	15.800	0.26
		C	0.000	0.000	0.000	0.000	0.14
L2	115.50-79.25	A	0.000	0.000	0.000	5.891	0.26
		B	0.000	0.000	0.000	14.500	0.93
		C	0.000	0.000	0.000	0.000	0.13
L3	79.25-43.75	A	0.000	0.000	0.000	5.769	0.26
		B	0.000	0.000	0.000	14.200	1.01
		C	0.000	0.000	0.000	0.000	0.13
L4	43.75-0.00	A	0.000	0.000	0.000	7.110	0.32
		B	0.000	0.000	0.000	17.500	1.24
		C	0.000	0.000	0.000	0.000	0.16

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A <sub>R</sub> ft <sup>2</sup>	A <sub>F</sub> ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> In Face ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Out Face ft <sup>2</sup>	Weight K
L1	155.00-115.50	A	1.184	0.000	0.000	0.000	6.987	0.26
		B		0.000	0.000	0.000	34.502	1.44
		C		0.000	0.000	0.000	0.000	0.14
L2	115.50-79.25	A	1.138	0.000	0.000	0.000	14.472	0.42
		B		0.000	0.000	0.000	31.663	2.70
		C		0.000	0.000	0.000	0.000	0.13
L3	79.25-43.75	A	1.077	0.000	0.000	0.000	13.849	0.40
		B		0.000	0.000	0.000	30.361	2.96
		C		0.000	0.000	0.000	0.000	0.13
L4	43.75-0.00	A	1.000	0.000	0.000	0.000	16.535	0.48
		B		0.000	0.000	0.000	36.352	3.42
		C		0.000	0.000	0.000	0.000	0.16

### Feed Line Center of Pressure

Section	Elevation ft	CP <sub>X</sub> in	CP <sub>Z</sub> in	CP <sub>X</sub> Ice in	CP <sub>Z</sub> Ice in
L1	155.00-115.50	0.4256	0.1503	0.7165	0.2328
L2	115.50-79.25	0.4295	0.0465	0.7328	0.0363
L3	79.25-43.75	0.4415	0.0478	0.7656	0.0388
L4	43.75-0.00	0.4515	0.0489	0.7866	0.0410

### Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustmen t °	Placement ft	C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K	
LPX310R	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice	2.08	1.32	0.01
						1/2" Ice	2.35	1.58	0.03
						Ice	2.63	1.84	0.04
						1" Ice	3.29	2.39	0.08
						2" Ice	4.71	3.68	0.22
						4" Ice			
LPX310R	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice	2.08	1.32	0.01
						1/2" Ice	2.35	1.58	0.03
						Ice	2.63	1.84	0.04
						1" Ice	3.29	2.39	0.08
						2" Ice	4.71	3.68	0.22
						4" Ice			
LPX310R	C	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice	2.08	1.32	0.01
						1/2" Ice	2.35	1.58	0.03
						Ice	2.63	1.84	0.04
						1" Ice	3.29	2.39	0.08
						2" Ice	4.71	3.68	0.22
						4" Ice			
WIMAX DAP HEAD	A	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice	1.80	0.78	0.03
						1/2" Ice	1.99	0.92	0.04
						Ice	2.18	1.07	0.06
						1" Ice	2.59	1.39	0.09
						2" Ice	3.51	2.14	0.20
						4" Ice			
WIMAX DAP HEAD	B	From Leg	4.00 0.00 0.00	0.0000	155.00	No Ice	1.80	0.78	0.03
						1/2" Ice	1.99	0.92	0.04
						Ice	2.18	1.07	0.06
						1" Ice	2.59	1.39	0.09
						2" Ice	3.51	2.14	0.20
						4" Ice			



Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
WIMAX DAP HEAD	C	From Leg	4.00	0.0000	155.00	4" Ice			
						No Ice	1.80	0.78	0.03
						1/2"	1.99	0.92	0.04
						Ice	2.18	1.07	0.06
						1" Ice	2.59	1.39	0.09
HORIZON COMPACT	A	From Leg	4.00	0.0000	155.00	2" Ice	3.51	2.14	0.20
						4" Ice			
						No Ice	0.84	0.43	0.01
						1/2"	0.97	0.52	0.02
						Ice	1.10	0.63	0.03
HORIZON COMPACT	B	From Leg	4.00	0.0000	155.00	1" Ice	1.39	0.86	0.05
						2" Ice	2.08	1.43	0.12
						4" Ice			
						No Ice	0.84	0.43	0.01
						1/2"	0.97	0.52	0.02
HORIZON COMPACT	C	From Leg	4.00	0.0000	155.00	Ice	1.10	0.63	0.03
						1" Ice	1.39	0.86	0.05
						2" Ice	2.08	1.43	0.12
						4" Ice			
						No Ice	0.84	0.43	0.01
9' x 2" Pipe Mount	A	From Leg	4.00	0.0000	155.00	1/2"	0.97	0.52	0.02
						Ice	1.10	0.63	0.03
						1" Ice	1.39	0.86	0.05
						2" Ice	2.08	1.43	0.12
						4" Ice			
9' x 2" Pipe Mount	B	From Leg	4.00	0.0000	155.00	No Ice	2.14	2.14	0.07
						1/2"	3.07	3.07	0.08
						Ice	4.01	4.01	0.10
						1" Ice	5.13	5.13	0.17
						2" Ice	7.46	7.46	0.37
9' x 2" Pipe Mount	C	From Leg	4.00	0.0000	155.00	4" Ice			
						No Ice	2.14	2.14	0.07
						1/2"	3.07	3.07	0.08
						Ice	4.01	4.01	0.10
						1" Ice	5.13	5.13	0.17
* APXVSP18-C-A20 w/ Mount Pipe	A	From Leg	4.00	0.0000	155.00	2" Ice	7.46	7.46	0.37
						4" Ice			
						No Ice	8.50	6.95	0.08
						1/2"	9.15	8.13	0.15
						Ice	9.77	9.02	0.23
APXVSP18-C-A20 w/ Mount Pipe	B	From Leg	4.00	0.0000	155.00	1" Ice	11.03	10.84	0.41
						2" Ice	13.68	14.85	0.91
						4" Ice			
						No Ice	8.50	6.95	0.08
						1/2"	9.15	8.13	0.15
APXVSP18-C-A20 w/ Mount Pipe	C	From Leg	4.00	0.0000	155.00	Ice	9.77	9.02	0.23
						1" Ice	11.03	10.84	0.41
						2" Ice	13.68	14.85	0.91
						4" Ice			
						No Ice	8.50	6.95	0.08
Platform Mount [LP 713-1]	C	None			155.00	1/2"	9.15	8.13	0.15
						Ice	9.77	9.02	0.23
						1" Ice	11.03	10.84	0.41
						2" Ice	13.68	14.85	0.91
						4" Ice			
						No Ice	31.27	31.27	1.51
						1/2"	39.68	39.68	1.93
						Ice	48.09	48.09	2.35

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft		C <sub>A</sub> A <sub>A</sub> Front ft <sup>2</sup>	C <sub>A</sub> A <sub>A</sub> Side ft <sup>2</sup>	Weight K
						1" Ice	64.91	64.91	3.19
						2" Ice	98.55	98.55	4.86
						4" Ice			
***									
800MHz 2X50W RRH W/FILTER	A	From Leg	1.00 0.00 0.00	0.0000	153.00	No Ice	2.40	2.25	0.06
						1/2"	2.61	2.46	0.09
						Ice	2.83	2.68	0.11
						1" Ice	3.30	3.13	0.17
						2" Ice	4.34	4.15	0.34
						4" Ice			
800MHz 2X50W RRH W/FILTER	B	From Leg	1.00 0.00 0.00	0.0000	153.00	No Ice	2.40	2.25	0.06
						1/2"	2.61	2.46	0.09
						Ice	2.83	2.68	0.11
						1" Ice	3.30	3.13	0.17
						2" Ice	4.34	4.15	0.34
						4" Ice			
800MHz 2X50W RRH W/FILTER	C	From Leg	1.00 0.00 0.00	0.0000	153.00	No Ice	2.40	2.25	0.06
						1/2"	2.61	2.46	0.09
						Ice	2.83	2.68	0.11
						1" Ice	3.30	3.13	0.17
						2" Ice	4.34	4.15	0.34
						4" Ice			
PCS 1900MHz 4x45W-65MHz	A	From Leg	1.00 0.00 0.00	0.0000	153.00	No Ice	2.71	2.61	0.06
						1/2"	2.95	2.85	0.08
						Ice	3.20	3.09	0.11
						1" Ice	3.72	3.61	0.17
						2" Ice	4.86	4.74	0.35
						4" Ice			
PCS 1900MHz 4x45W-65MHz	B	From Leg	1.00 0.00 0.00	0.0000	153.00	No Ice	2.71	2.61	0.06
						1/2"	2.95	2.85	0.08
						Ice	3.20	3.09	0.11
						1" Ice	3.72	3.61	0.17
						2" Ice	4.86	4.74	0.35
						4" Ice			
PCS 1900MHz 4x45W-65MHz	C	From Leg	1.00 0.00 0.00	0.0000	153.00	No Ice	2.71	2.61	0.06
						1/2"	2.95	2.85	0.08
						Ice	3.20	3.09	0.11
						1" Ice	3.72	3.61	0.17
						2" Ice	4.86	4.74	0.35
						4" Ice			
Side Arm Mount [SO 102-3]	C	None		0.0000	153.00	No Ice	3.00	3.00	0.08
						1/2"	3.48	3.48	0.11
						Ice	3.96	3.96	0.14
						1" Ice	4.92	4.92	0.20
						2" Ice	6.84	6.84	0.32
						4" Ice			
***									
***									
800 10121 w/ Mount Pipe	A	From Leg	3.00 0.00 2.00	0.0000	143.00	No Ice	5.69	4.60	0.07
						1/2"	6.18	5.35	0.11
						Ice	6.68	6.05	0.17
						1" Ice	7.70	7.53	0.30
						2" Ice	9.86	10.83	0.68
						4" Ice			
800 10121 w/ Mount Pipe	B	From Leg	3.00 0.00 2.00	0.0000	143.00	No Ice	5.69	4.60	0.07
						1/2"	6.18	5.35	0.11
						Ice	6.68	6.05	0.17
						1" Ice	7.70	7.53	0.30
						2" Ice	9.86	10.83	0.68
						4" Ice			
800 10121 w/ Mount Pipe	C	From Leg	3.00 0.00 2.00	0.0000	143.00	No Ice	5.69	4.60	0.07
						1/2"	6.18	5.35	0.11
						Ice	6.68	6.05	0.17
						1" Ice	7.70	7.53	0.30
						2" Ice	9.86	10.83	0.68

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight	
			Horz	Lateral						Vert
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
(2) LGP21401	A	From Leg	3.00	0.00	0.0000	143.00	4" Ice			
							No Ice	0.00	0.23	0.01
							1/2" Ice	0.00	0.31	0.02
							1" Ice	0.00	0.40	0.03
							2" Ice	0.00	0.61	0.05
(2) LGP21401	B	From Leg	3.00	0.00	0.0000	143.00	4" Ice			
							No Ice	0.00	0.23	0.01
							1/2" Ice	0.00	0.31	0.02
							1" Ice	0.00	0.40	0.03
							2" Ice	0.00	0.61	0.05
(2) LGP21401	C	From Leg	3.00	0.00	0.0000	143.00	4" Ice			
							No Ice	0.00	0.23	0.01
							1/2" Ice	0.00	0.31	0.02
							1" Ice	0.00	0.40	0.03
							2" Ice	0.00	0.61	0.05
(2) RRUS-11	A	From Leg	3.00	0.00	0.0000	145.00	4" Ice			
							No Ice	3.25	1.37	0.05
							1/2" Ice	3.49	1.55	0.07
							1" Ice	3.74	1.74	0.09
							2" Ice	4.27	2.14	0.15
(2) RRUS-11	B	From Leg	3.00	0.00	0.0000	145.00	4" Ice			
							No Ice	3.25	1.37	0.05
							1/2" Ice	3.49	1.55	0.07
							1" Ice	3.74	1.74	0.09
							2" Ice	4.27	2.14	0.15
(2) RRUS-11	C	From Leg	3.00	0.00	0.0000	145.00	4" Ice			
							No Ice	3.25	1.37	0.05
							1/2" Ice	3.49	1.55	0.07
							1" Ice	3.74	1.74	0.09
							2" Ice	4.27	2.14	0.15
AM-X-CD-16-65-00T-RET w/ Mount Pipe	A	From Leg	3.00	0.00	0.0000	143.00	4" Ice			
							No Ice	8.50	6.30	0.07
							1/2" Ice	9.15	7.48	0.14
							1" Ice	9.77	8.37	0.21
							2" Ice	11.03	10.18	0.38
AM-X-CD-16-65-00T-RET w/ Mount Pipe	B	From Leg	3.00	0.00	0.0000	143.00	4" Ice			
							No Ice	8.50	6.30	0.07
							1/2" Ice	9.15	7.48	0.14
							1" Ice	9.77	8.37	0.21
							2" Ice	11.03	10.18	0.38
AM-X-CD-16-65-00T-RET w/ Mount Pipe	C	From Leg	3.00	0.00	0.0000	143.00	4" Ice			
							No Ice	8.50	6.30	0.07
							1/2" Ice	9.15	7.48	0.14
							1" Ice	9.77	8.37	0.21
							2" Ice	11.03	10.18	0.38
DC6-48-60-18-8F	A	From Leg	3.00	0.00	0.0000	143.00	4" Ice			
							No Ice	1.27	1.27	0.02
							1/2" Ice	1.46	1.46	0.04
							1" Ice	1.66	1.66	0.05
							2" Ice	2.09	2.09	0.10
Side Arm Mount [SO 102-3]	C	None			0.0000	145.00	4" Ice			
							No Ice	3.00	3.00	0.08
							1/2" Ice	3.48	3.48	0.11
							1" Ice	3.96	3.96	0.14
							1" Ice	4.92	4.92	0.20

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K	
			Horz Lateral ft	Vert ft						
T-Arm Mount [TA 702-3]	C	None			0.0000	143.00	2" Ice	6.84	6.84	0.32
							4" Ice			
							No Ice	5.64	5.64	0.34
							1/2" Ice	6.55	6.55	0.43
							1" Ice	7.46	7.46	0.52
							2" Ice	9.28	9.28	0.70
*** ERICSSON AIR 21 B2A B4P w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	133.00	No Ice	6.83	5.64	0.11	
						1/2" Ice	7.35	6.48	0.17	
						1" Ice	7.86	7.26	0.23	
						2" Ice	8.93	8.86	0.38	
						4" Ice	11.18	12.29	0.81	
						ERICSSON AIR 21 B2A B4P w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000
1/2" Ice	7.35	6.48	0.17							
1" Ice	7.86	7.26	0.23							
2" Ice	8.93	8.86	0.38							
4" Ice	11.18	12.29	0.81							
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000	133.00					
						1/2" Ice	7.35	6.48	0.17	
						1" Ice	7.86	7.26	0.23	
						2" Ice	8.93	8.86	0.38	
						4" Ice	11.18	12.29	0.81	
						ERICSSON AIR 21 B4A B2P w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000
1/2" Ice	7.35	6.48	0.17							
1" Ice	7.86	7.26	0.23							
2" Ice	8.93	8.86	0.38							
4" Ice	11.18	12.29	0.81							
ERICSSON AIR 21 B4A B2P w/ Mount Pipe	B	From Leg	4.00 0.00 0.00	0.0000	133.00					
						1/2" Ice	7.35	6.48	0.17	
						1" Ice	7.86	7.26	0.23	
						2" Ice	8.93	8.86	0.38	
						4" Ice	11.18	12.29	0.81	
						ERICSSON AIR 21 B4A B2P w/ Mount Pipe	C	From Leg	4.00 0.00 0.00	0.0000
1/2" Ice	7.35	6.48	0.17							
1" Ice	7.86	7.26	0.23							
2" Ice	8.93	8.86	0.38							
4" Ice	11.18	12.29	0.81							
KRY 112 144/1	A	From Leg	4.00 0.00 0.00	0.0000	133.00					
						1/2" Ice	0.50	0.27	0.01	
						1" Ice	0.59	0.35	0.02	
						2" Ice	0.81	0.53	0.03	
						4" Ice	1.36	1.00	0.08	
						KRY 112 144/1	B	From Leg	4.00 0.00 0.00	0.0000
1/2" Ice	0.50	0.27	0.01							
1" Ice	0.59	0.35	0.02							
2" Ice	0.81	0.53	0.03							
4" Ice	1.36	1.00	0.08							
KRY 112 144/1	C	From Leg	4.00 0.00 0.00	0.0000	133.00					
						1/2" Ice	0.50	0.27	0.01	
						1" Ice	0.59	0.35	0.02	
						2" Ice	0.81	0.53	0.03	
						4" Ice	1.36	1.00	0.08	
						(2) 5' x 2" Pipe Mount	A	From Leg	4.00 0.00	0.0000
1/2" Ice	1.39	1.39	0.04							



Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft	C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
			0.00			Ice 1.70	1.70	0.05
						1" Ice 2.35	2.35	0.08
						2" Ice 3.78	3.78	0.20
						4" Ice		
(2) 5' x 2" Pipe Mount	B	From Leg	4.00	0.0000	133.00	No Ice 1.00	1.00	0.03
			0.00			1/2" 1.39	1.39	0.04
			0.00			Ice 1.70	1.70	0.05
						1" Ice 2.35	2.35	0.08
						2" Ice 3.78	3.78	0.20
						4" Ice		
(2) 5' x 2" Pipe Mount	C	From Leg	4.00	0.0000	133.00	No Ice 1.00	1.00	0.03
			0.00			1/2" 1.39	1.39	0.04
			0.00			Ice 1.70	1.70	0.05
						1" Ice 2.35	2.35	0.08
						2" Ice 3.78	3.78	0.20
						4" Ice		
Platform Mount [LP 403-1]	C	None		0.0000	133.00	No Ice 18.85	18.85	1.50
						1/2" 24.30	24.30	1.80
						Ice 29.75	29.75	2.09
						1" Ice 40.65	40.65	2.69
						2" Ice 62.45	62.45	3.87
						4" Ice		
***								
BXA-70063/6CFx2 w/ Mount Pipe	A	From Leg	4.00	0.0000	113.00	No Ice 7.97	5.40	0.04
			0.00			1/2" 8.61	6.55	0.10
			0.00			Ice 9.22	7.41	0.17
						1" Ice 10.46	9.18	0.33
						2" Ice 13.07	12.93	0.79
						4" Ice		
BXA-70063/6CFx2 w/ Mount Pipe	B	From Leg	4.00	0.0000	113.00	No Ice 7.97	5.40	0.04
			0.00			1/2" 8.61	6.55	0.10
			0.00			Ice 9.22	7.41	0.17
						1" Ice 10.46	9.18	0.33
						2" Ice 13.07	12.93	0.79
						4" Ice		
BXA-70063/6CFx4 w/ Mount Pipe	C	From Leg	4.00	0.0000	113.00	No Ice 7.97	5.40	0.04
			0.00			1/2" 8.61	6.55	0.10
			0.00			Ice 9.22	7.41	0.17
						1" Ice 10.46	9.18	0.33
						2" Ice 13.07	12.93	0.79
						4" Ice		
MG D3-800Tx w/ Mount Pipe	A	From Leg	4.00	0.0000	113.00	No Ice 3.57	3.42	0.03
			0.00			1/2" 3.98	4.12	0.07
			0.00			Ice 4.39	4.78	0.11
						1" Ice 5.33	6.16	0.21
						2" Ice 7.34	9.18	0.52
						4" Ice		
MG D3-800Tx w/ Mount Pipe	B	From Leg	4.00	0.0000	113.00	No Ice 3.57	3.42	0.03
			0.00			1/2" 3.98	4.12	0.07
			0.00			Ice 4.39	4.78	0.11
						1" Ice 5.33	6.16	0.21
						2" Ice 7.34	9.18	0.52
						4" Ice		
MG D3-800Tx w/ Mount Pipe	C	From Leg	4.00	0.0000	113.00	No Ice 3.57	3.42	0.03
			0.00			1/2" 3.98	4.12	0.07
			0.00			Ice 4.39	4.78	0.11
						1" Ice 5.33	6.16	0.21
						2" Ice 7.34	9.18	0.52
						4" Ice		
BXA-171063-12BF w/ Mount Pipe	A	From Leg	4.00	0.0000	113.00	No Ice 4.97	5.23	0.04
			0.00			1/2" 5.52	6.39	0.09
			0.00			Ice 6.04	7.26	0.14
						1" Ice 7.09	9.05	0.27
						2" Ice 9.36	12.82	0.67
						4" Ice		

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
BXA-171063-12BF w/ Mount Pipe	B	From Leg	4.00	0.0000	113.00	No Ice	4.97	5.23	0.04
			0.00			1/2"	5.52	6.39	0.09
			0.00			Ice	6.04	7.26	0.14
						1" Ice	7.09	9.05	0.27
						2" Ice	9.36	12.82	0.67
BXA-171063-12BF w/ Mount Pipe	C	From Leg	4.00	0.0000	113.00	No Ice	4.97	5.23	0.04
			0.00			1/2"	5.52	6.39	0.09
			0.00			Ice	6.04	7.26	0.14
						1" Ice	7.09	9.05	0.27
						2" Ice	9.36	12.82	0.67
LNX-6512DS-T0M w/ Mount Pipe	A	From Leg	4.00	0.0000	113.00	No Ice	5.85	4.55	0.05
			0.00			1/2"	6.31	5.23	0.09
			0.00			Ice	6.77	5.91	0.15
						1" Ice	7.74	7.34	0.28
						2" Ice	9.80	10.46	0.65
LNX-6512DS-T0M w/ Mount Pipe	B	From Leg	4.00	0.0000	113.00	No Ice	5.85	4.55	0.05
			0.00			1/2"	6.31	5.23	0.09
			0.00			Ice	6.77	5.91	0.15
						1" Ice	7.74	7.34	0.28
						2" Ice	9.80	10.46	0.65
LNX-6512DS-T0M w/ Mount Pipe	C	From Leg	4.00	0.0000	113.00	No Ice	5.85	4.55	0.05
			0.00			1/2"	6.31	5.23	0.09
			0.00			Ice	6.77	5.91	0.15
						1" Ice	7.74	7.34	0.28
						2" Ice	9.80	10.46	0.65
RRH2x40-AWS	A	From Leg	4.00	0.0000	113.00	No Ice	2.52	1.59	0.04
			0.00			1/2"	2.75	1.80	0.06
			0.00			Ice	2.99	2.01	0.08
						1" Ice	3.50	2.46	0.13
						2" Ice	4.61	3.48	0.28
RRH2x40-AWS	B	From Leg	4.00	0.0000	113.00	No Ice	2.52	1.59	0.04
			0.00			1/2"	2.75	1.80	0.06
			0.00			Ice	2.99	2.01	0.08
						1" Ice	3.50	2.46	0.13
						2" Ice	4.61	3.48	0.28
RRH2x40-AWS	C	From Leg	4.00	0.0000	113.00	No Ice	2.52	1.59	0.04
			0.00			1/2"	2.75	1.80	0.06
			0.00			Ice	2.99	2.01	0.08
						1" Ice	3.50	2.46	0.13
						2" Ice	4.61	3.48	0.28
RRH2X40-07-U	A	From Leg	4.00	0.0000	113.00	No Ice	2.25	1.23	0.05
			0.00			1/2"	2.45	1.39	0.07
			0.00			Ice	2.66	1.55	0.09
						1" Ice	3.10	1.91	0.13
						2" Ice	4.10	2.73	0.27
RRH2X40-07-U	B	From Leg	4.00	0.0000	113.00	No Ice	2.25	1.23	0.05
			0.00			1/2"	2.45	1.39	0.07
			0.00			Ice	2.66	1.55	0.09
						1" Ice	3.10	1.91	0.13
						2" Ice	4.10	2.73	0.27
RRH2X40-07-U	C	From Leg	4.00	0.0000	113.00	No Ice	2.25	1.23	0.05
			0.00			1/2"	2.45	1.39	0.07
			0.00			Ice	2.66	1.55	0.09
						1" Ice	3.10	1.91	0.13
						2" Ice	4.10	2.73	0.27

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment t °	Placement ft		C <sub>AA</sub> Front ft <sup>2</sup>	C <sub>AA</sub> Side ft <sup>2</sup>	Weight K
DB-T1-6Z-8AB-0Z	A	From Leg	4.00 0.00 0.00	0.0000	113.00	4" Ice			
						No Ice	5.60	2.33	0.04
						1/2"	5.92	2.56	0.08
						Ice	6.24	2.79	0.12
						1" Ice	6.91	3.28	0.21
						2" Ice	8.37	4.37	0.45
Platform Mount [LP 601-1]	C	None		0.0000	113.00	4" Ice			
						No Ice	28.47	28.47	1.12
						1/2"	33.59	33.59	1.51
						Ice	38.71	38.71	1.91
						1" Ice	48.95	48.95	2.69
						2" Ice	69.43	69.43	4.26
*** APXV18-206517S-C w/ Mount Pipe	A	From Leg	0.50 0.00 0.00	0.0000	103.00	4" Ice			
						No Ice	5.40	4.70	0.05
						1/2"	5.96	5.86	0.10
						Ice	6.48	6.73	0.15
						1" Ice	7.55	8.51	0.28
						2" Ice	9.92	12.28	0.68
APXV18-206517S-C w/ Mount Pipe	B	From Leg	0.50 0.00 0.00	0.0000	103.00	4" Ice			
						No Ice	5.40	4.70	0.05
						1/2"	5.96	5.86	0.10
						Ice	6.48	6.73	0.15
						1" Ice	7.55	8.51	0.28
						2" Ice	9.92	12.28	0.68
APXV18-206517S-C w/ Mount Pipe	C	From Leg	0.50 0.00 0.00	0.0000	103.00	4" Ice			
						No Ice	5.40	4.70	0.05
						1/2"	5.96	5.86	0.10
						Ice	6.48	6.73	0.15
						1" Ice	7.55	8.51	0.28
						2" Ice	9.92	12.28	0.68
*** *** ACUTIME 2000	A	From Leg	3.00 0.00 0.00	0.0000	60.00	4" Ice			
						No Ice	0.30	0.30	0.00
						1/2"	0.37	0.37	0.00
						Ice	0.46	0.46	0.01
						1" Ice	0.65	0.65	0.02
						2" Ice	1.15	1.15	0.08
Side Arm Mount [SO 701-1]	A	None		0.0000	60.00	4" Ice			
						No Ice	0.85	1.67	0.07
						1/2"	1.14	2.34	0.08
						Ice	1.43	3.01	0.09
						1" Ice	2.01	4.35	0.12
						2" Ice	3.17	7.03	0.18
** TD-RRH8x20-25	A	From Leg	4.00 0.00 0.00	0.0000	155.00	4" Ice			
						No Ice	4.72	1.70	0.07
						1/2"	5.01	1.92	0.10
						Ice	5.32	2.15	0.13
						1" Ice	5.95	2.62	0.20
						2" Ice	7.31	3.68	0.40
APXVTM14-C-120 w/ Mount Pipe	A	From Leg	4.00 0.00 0.00	0.0000	155.00	4" Ice			
						No Ice	7.13	4.96	0.07
						1/2"	7.66	5.75	0.13
						Ice	8.18	6.47	0.19
						1" Ice	9.26	8.01	0.34
						2" Ice	11.53	11.41	0.75
TD-RRH8x20-25	B	From Leg	4.00 0.00 0.00	0.0000	155.00	4" Ice			
						No Ice	4.72	1.70	0.07
						1/2"	5.01	1.92	0.10
						Ice	5.32	2.15	0.13
						1" Ice	5.95	2.62	0.20
						2" Ice	7.31	3.68	0.40

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz Lateral	Vert					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.00	0.0000	155.00	No Ice	7.13	4.96	0.07
			0.00			1/2" Ice	7.66	5.75	0.13
			0.00			Ice	8.18	6.47	0.19
						1" Ice	9.26	8.01	0.34
						2" Ice	11.53	11.41	0.75
TD-RRH8x20-25	C	From Leg	4.00	0.0000	155.00	No Ice	4.72	1.70	0.07
			0.00			1/2" Ice	5.01	1.92	0.10
			0.00			Ice	5.32	2.15	0.13
						1" Ice	5.95	2.62	0.20
						2" Ice	7.31	3.68	0.40
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.00	0.0000	155.00	No Ice	7.13	4.96	0.07
			0.00			1/2" Ice	7.66	5.75	0.13
			0.00			Ice	8.18	6.47	0.19
						1" Ice	9.26	8.01	0.34
						2" Ice	11.53	11.41	0.75
		4" Ice							

### Dishes

Description	Face or Leg	Dish Type	Offset Type	Offsets:		Azimuth Adjustment	3 dB Beam Width	Elevation	Outside Diameter	Aperture Area	Weight		
				Horz Lateral	Vert								
				ft	ft	°	°	ft	ft	ft <sup>2</sup>	K		
VHLP2.5-18	B	Paraboloid w/Shroud (HP)	From Leg	4.00	80.0000	155.00	2.50	No Ice	6.68	0.05			
				0.00							1/2" Ice	7.06	0.05
				-4.00							1" Ice	7.46	0.06
											2" Ice	8.29	0.10
											4" Ice	10.08	0.26
VHLP1-23	A	Paraboloid w/o Radome	From Leg	4.00	0.0000	155.00	1.27	No Ice	1.28	0.01			
				0.00							1/2" Ice	1.45	0.02
				-4.00							1" Ice	1.62	0.02
											2" Ice	1.97	0.04
											4" Ice	2.66	0.07
VHLP2-11	C	Paraboloid w/o Radome	From Leg	4.00	75.0000	155.00	2.17	No Ice	3.72	0.03			
				0.00							1/2" Ice	4.01	0.05
				-4.00							1" Ice	4.30	0.07
											2" Ice	4.88	0.11
											4" Ice	6.04	0.19

### Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+Wind 0 deg - No Ice
3	Dead+Wind 30 deg - No Ice
4	Dead+Wind 60 deg - No Ice
5	Dead+Wind 90 deg - No Ice
6	Dead+Wind 120 deg - No Ice
7	Dead+Wind 150 deg - No Ice
8	Dead+Wind 180 deg - No Ice
9	Dead+Wind 210 deg - No Ice
10	Dead+Wind 240 deg - No Ice



Comb. No.	Description
11	Dead+Wind 270 deg - No Ice
12	Dead+Wind 300 deg - No Ice
13	Dead+Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+Wind 0 deg+Ice+Temp
16	Dead+Wind 30 deg+Ice+Temp
17	Dead+Wind 60 deg+Ice+Temp
18	Dead+Wind 90 deg+Ice+Temp
19	Dead+Wind 120 deg+Ice+Temp
20	Dead+Wind 150 deg+Ice+Temp
21	Dead+Wind 180 deg+Ice+Temp
22	Dead+Wind 210 deg+Ice+Temp
23	Dead+Wind 240 deg+Ice+Temp
24	Dead+Wind 270 deg+Ice+Temp
25	Dead+Wind 300 deg+Ice+Temp
26	Dead+Wind 330 deg+Ice+Temp
27	Dead+Wind 0 deg - Service
28	Dead+Wind 30 deg - Service
29	Dead+Wind 60 deg - Service
30	Dead+Wind 90 deg - Service
31	Dead+Wind 120 deg - Service
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

**Maximum Member Forces**

Sectio n No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	155 - 115.5	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-18.79	-1.35	-0.66
			Max. Mx	5	-8.19	-363.82	-1.46
			Max. My	8	-8.16	-4.37	-368.61
			Max. Vy	5	14.31	-363.82	-1.46
			Max. Vx	8	14.47	-4.37	-368.61
			Max. Torque	4			-2.23
L2	115.5 - 79.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-32.78	-3.96	-1.16
			Max. Mx	5	-15.33	-1063.69	-3.17
			Max. My	8	-15.29	-9.41	-1077.53
			Max. Vy	5	22.27	-1063.69	-3.17
			Max. Vx	8	22.56	-9.41	-1077.53
			Max. Torque	4			-2.11
L3	79.25 - 43.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-44.00	-7.28	-2.70
			Max. Mx	5	-23.03	-1889.32	-5.02
			Max. My	8	-23.01	-14.45	-1912.93
			Max. Vy	5	25.15	-1889.32	-5.02
			Max. Vx	8	25.43	-14.45	-1912.93
			Max. Torque	4			-1.80
L4	43.75 - 0	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-62.63	-12.15	-5.06
			Max. Mx	5	-36.92	-3202.44	-7.60
			Max. My	8	-36.92	-21.48	-3239.48
			Max. Vy	5	28.32	-3202.44	-7.60
			Max. Vx	8	28.59	-21.48	-3239.48
			Max. Torque	4			-1.87

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	21	62.63	-0.03	-8.48
	Max. H <sub>x</sub>	11	36.95	28.21	-0.08
	Max. H <sub>z</sub>	2	36.95	-0.07	28.53
	Max. M <sub>x</sub>	2	3233.43	-0.07	28.53
	Max. M <sub>z</sub>	5	3202.44	-28.28	-0.04
	Max. Torsion	10	1.21	24.41	-14.32
	Min. Vert	1	36.95	0.00	0.00
	Min. H <sub>x</sub>	5	36.95	-28.28	-0.04
	Min. H <sub>z</sub>	8	36.95	-0.12	-28.56
	Min. M <sub>x</sub>	8	-3239.48	-0.12	-28.56
	Min. M <sub>z</sub>	11	-3186.17	28.21	-0.08
	Min. Torsion	4	-1.87	-24.53	14.24

### Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	36.95	0.00	0.00	0.74	-2.00	0.00
Dead+Wind 0 deg - No Ice	36.95	0.07	-28.53	-3233.43	-12.78	1.64
Dead+Wind 30 deg - No Ice	36.95	14.11	-24.72	-2802.40	-1596.91	1.26
Dead+Wind 60 deg - No Ice	36.95	24.53	-14.24	-1612.43	-2778.82	1.87
Dead+Wind 90 deg - No Ice	36.95	28.28	0.04	7.60	-3202.44	1.54
Dead+Wind 120 deg - No Ice	36.95	24.46	14.43	1643.23	-2767.57	0.09
Dead+Wind 150 deg - No Ice	36.95	14.12	24.77	2811.73	-1598.50	-0.61
Dead+Wind 180 deg - No Ice	36.95	0.12	28.56	3239.48	-21.48	-0.53
Dead+Wind 210 deg - No Ice	36.95	-13.99	24.77	2811.04	1574.08	-0.61
Dead+Wind 240 deg - No Ice	36.95	-24.41	14.32	1626.53	2755.65	-1.21
Dead+Wind 270 deg - No Ice	36.95	-28.21	0.08	14.20	3186.17	-0.46
Dead+Wind 300 deg - No Ice	36.95	-24.43	-14.24	-1612.04	2759.05	0.49
Dead+Wind 330 deg - No Ice	36.95	-14.02	-24.75	-2806.41	1578.10	1.53
Dead+Ice+Temp	62.63	0.00	0.00	5.06	-12.15	0.00
Dead+Wind 0 deg+Ice+Temp	62.63	0.02	-8.47	-1008.82	-15.06	0.53
Dead+Wind 30 deg+Ice+Temp	62.63	4.19	-7.34	-873.53	-513.29	0.41
Dead+Wind 60 deg+Ice+Temp	62.63	7.29	-4.23	-500.58	-884.11	0.53
Dead+Wind 90 deg+Ice+Temp	62.63	8.41	0.01	7.20	-1017.31	0.40
Dead+Wind 120 deg+Ice+Temp	62.63	7.27	4.28	519.39	-881.05	-0.03
Dead+Wind 150 deg+Ice+Temp	62.63	4.20	7.35	886.20	-513.87	-0.25
Dead+Wind 180 deg+Ice+Temp	62.63	0.03	8.48	1020.52	-17.68	-0.24
Dead+Wind 210 deg+Ice+Temp	62.63	-4.16	7.35	886.01	483.60	-0.24
Dead+Wind 240 deg+Ice+Temp	62.63	-7.26	4.25	514.65	854.39	-0.36
Dead+Wind 270 deg+Ice+Temp	62.63	-8.39	0.02	8.64	989.50	-0.11
Dead+Wind 300 deg+Ice+Temp	62.63	-7.26	-4.23	-500.72	855.42	0.19
Dead+Wind 330 deg+Ice+Temp	62.63	-4.17	-7.34	-874.65	485.07	0.49
Dead+Wind 0 deg - Service	36.95	0.03	-11.15	-1264.86	-6.28	0.65
Dead+Wind 30 deg - Service	36.95	5.51	-9.66	-1096.18	-626.19	0.50
Dead+Wind 60 deg - Service	36.95	9.58	-5.56	-630.50	-1088.68	0.74
Dead+Wind 90 deg - Service	36.95	11.05	0.02	3.45	-1254.43	0.61
Dead+Wind 120 deg - Service	36.95	9.55	5.64	643.51	-1084.28	0.04

Load Combination	Vertical	Shear <sub>x</sub>	Shear <sub>z</sub>	Overturning Moment, M <sub>x</sub>	Overturning Moment, M <sub>z</sub>	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead+Wind 150 deg - Service	36.95	5.52	9.68	1100.78	-626.81	-0.24
Dead+Wind 180 deg - Service	36.95	0.05	11.16	1268.17	-9.68	-0.21
Dead+Wind 210 deg - Service	36.95	-5.46	9.67	1100.50	614.70	-0.24
Dead+Wind 240 deg - Service	36.95	-9.53	5.59	636.96	1077.04	-0.48
Dead+Wind 270 deg - Service	36.95	-11.02	0.03	6.03	1245.48	-0.18
Dead+Wind 300 deg - Service	36.95	-9.54	-5.56	-630.34	1078.37	0.19
Dead+Wind 330 deg - Service	36.95	-5.47	-9.67	-1097.75	616.27	0.60

### Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-36.95	0.00	0.00	36.95	0.00	0.000%
2	0.07	-36.95	-28.53	-0.07	36.95	28.53	0.000%
3	14.11	-36.95	-24.72	-14.11	36.95	24.72	0.000%
4	24.53	-36.95	-14.24	-24.53	36.95	14.24	0.000%
5	28.28	-36.95	0.04	-28.28	36.95	-0.04	0.000%
6	24.46	-36.95	14.43	-24.46	36.95	-14.43	0.000%
7	14.12	-36.95	24.77	-14.12	36.95	-24.77	0.000%
8	0.12	-36.95	28.56	-0.12	36.95	-28.56	0.000%
9	-13.99	-36.95	24.77	13.99	36.95	-24.77	0.000%
10	-24.41	-36.95	14.32	24.41	36.95	-14.32	0.000%
11	-28.21	-36.95	0.08	28.21	36.95	-0.08	0.000%
12	-24.43	-36.95	-14.24	24.43	36.95	14.24	0.000%
13	-14.02	-36.95	-24.75	14.02	36.95	24.75	0.000%
14	0.00	-62.63	0.00	-0.00	62.63	-0.00	0.000%
15	0.02	-62.63	-8.47	-0.02	62.63	8.47	0.000%
16	4.19	-62.63	-7.34	-4.19	62.63	7.34	0.000%
17	7.29	-62.63	-4.23	-7.29	62.63	4.23	0.000%
18	8.41	-62.63	0.01	-8.41	62.63	-0.01	0.000%
19	7.27	-62.63	4.28	-7.27	62.63	-4.28	0.000%
20	4.20	-62.63	7.35	-4.20	62.63	-7.35	0.000%
21	0.03	-62.63	8.48	-0.03	62.63	-8.48	0.000%
22	-4.16	-62.63	7.35	4.16	62.63	-7.35	0.000%
23	-7.26	-62.63	4.25	7.26	62.63	-4.25	0.000%
24	-8.39	-62.63	0.02	8.39	62.63	-0.02	0.000%
25	-7.26	-62.63	-4.23	7.26	62.63	4.23	0.000%
26	-4.17	-62.63	-7.34	4.17	62.63	7.34	0.000%
27	0.03	-36.95	-11.15	-0.03	36.95	11.15	0.000%
28	5.51	-36.95	-9.66	-5.51	36.95	9.66	0.000%
29	9.58	-36.95	-5.56	-9.58	36.95	5.56	0.000%
30	11.05	-36.95	0.02	-11.05	36.95	-0.02	0.000%
31	9.55	-36.95	5.64	-9.55	36.95	-5.64	0.000%
32	5.52	-36.95	9.68	-5.52	36.95	-9.68	0.000%
33	0.05	-36.95	11.16	-0.05	36.95	-11.16	0.000%
34	-5.46	-36.95	9.67	5.46	36.95	-9.67	0.000%
35	-9.53	-36.95	5.59	9.53	36.95	-5.59	0.000%
36	-11.02	-36.95	0.03	11.02	36.95	-0.03	0.000%
37	-9.54	-36.95	-5.56	9.54	36.95	5.56	0.000%
38	-5.47	-36.95	-9.67	5.47	36.95	9.67	0.000%

### Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.00000001	0.00000001
2	Yes	5	0.00000001	0.00010521
3	Yes	6	0.00000001	0.00009398
4	Yes	6	0.00000001	0.00008912
5	Yes	5	0.00000001	0.00011005
6	Yes	6	0.00000001	0.00009333
7	Yes	6	0.00000001	0.00009302
8	Yes	5	0.00000001	0.00005731
9	Yes	6	0.00000001	0.00009059
10	Yes	6	0.00000001	0.00009386
11	Yes	5	0.00000001	0.00005901
12	Yes	6	0.00000001	0.00009194
13	Yes	6	0.00000001	0.00008919
14	Yes	4	0.00000001	0.00007758
15	Yes	5	0.00000001	0.00063464
16	Yes	6	0.00000001	0.00011340
17	Yes	6	0.00000001	0.00011028
18	Yes	5	0.00000001	0.00063796
19	Yes	6	0.00000001	0.00011454
20	Yes	6	0.00000001	0.00011446
21	Yes	5	0.00000001	0.00063863
22	Yes	6	0.00000001	0.00010827
23	Yes	6	0.00000001	0.00011087
24	Yes	5	0.00000001	0.00061856
25	Yes	6	0.00000001	0.00010819
26	Yes	6	0.00000001	0.00010667
27	Yes	4	0.00000001	0.00048153
28	Yes	5	0.00000001	0.00023672
29	Yes	5	0.00000001	0.00021539
30	Yes	4	0.00000001	0.00052006
31	Yes	5	0.00000001	0.00023381
32	Yes	5	0.00000001	0.00023282
33	Yes	4	0.00000001	0.00024715
34	Yes	5	0.00000001	0.00022056
35	Yes	5	0.00000001	0.00023460
36	Yes	4	0.00000001	0.00027317
37	Yes	5	0.00000001	0.00022549
38	Yes	5	0.00000001	0.00021453

**Maximum Tower Deflections - Service Wind**

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	155 - 115.5	47.530	33	2.6238	0.0103
L2	119.25 - 79.25	28.726	33	2.2894	0.0043
L3	83.75 - 43.75	13.974	33	1.6036	0.0020
L4	49 - 0	4.729	33	0.8923	0.0008

**Critical Deflections and Radius of Curvature - Service Wind**

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
155.00	LPX310R	33	47.530	2.6238	0.0103	23861
153.00	800MHz 2X50W RRH W/FILTER	33	46.435	2.6102	0.0099	23861
151.00	VHLP2.5-18	33	45.341	2.5965	0.0095	23861
145.00	(2) RRUS-11	33	42.072	2.5539	0.0084	11930
143.00	800 10121 w/ Mount Pipe	33	40.989	2.5389	0.0080	9941
133.00	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	33	35.665	2.4530	0.0063	5422
113.00	BXA-70063/6CFx2 w/ Mount	33	25.778	2.1911	0.0036	3242



Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
103.00	Pipe APXV18-206517S-C w/ Mount	33	21.365	2.0069	0.0029	3105
60.00	Pipe ACUTIME 2000	33	7.034	1.1098	0.0011	2460

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	155 - 115.5	121.127	8	6.6901	0.0261
L2	119.25 - 79.25	73.258	8	5.8399	0.0108
L3	83.75 - 43.75	35.662	8	4.0927	0.0049
L4	49 - 0	12.076	8	2.2784	0.0021

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
155.00	LPX310R	8	121.127	6.6901	0.0261	9583
153.00	800MHz 2X50W RRH W/FILTER	8	118.340	6.6555	0.0251	9583
151.00	VHLP2.5-18	8	115.556	6.6208	0.0241	9583
145.00	(2) RRUS-11	8	107.235	6.5125	0.0212	4790
143.00	800 10121 w/ Mount Pipe	8	104.479	6.4743	0.0203	3991
133.00	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	8	90.925	6.2562	0.0158	2174
113.00	BXA-70063/6CFx2 w/ Mount Pipe	8	65.750	5.5896	0.0091	1295
103.00	APXV18-206517S-C w/ Mount Pipe	8	54.505	5.1204	0.0072	1236
60.00	ACUTIME 2000	8	17.959	2.8333	0.0029	968

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	KI/r	F <sub>a</sub> ksi	A in <sup>2</sup>	Actual P K	Allow. P <sub>a</sub> K	Ratio P P <sub>a</sub>
L1	155 - 115.5 (1)	TP29.308x22x0.25	39.50	0.00	0.0	36.000	22.5070	-8.16	810.25	0.010
L2	115.5 - 79.25 (2)	TP35.514x28.1142x0.3125	40.00	0.00	0.0	39.000	34.0898	-15.29	1329.50	0.012
L3	79.25 - 43.75 (3)	TP41.456x34.0565x0.375	40.00	0.00	0.0	39.000	47.7407	-23.01	1861.89	0.012
L4	43.75 - 0 (4)	TP48.8x39.7348x0.4375	49.00	0.00	0.0	39.000	67.1574	-36.92	2619.14	0.014

### Pole Bending Design Data

Section No.	Elevation ft	Size	Actual $M_x$ kip-ft	Actual $f_{bx}$ ksi	Allow. $F_{bx}$ ksi	Ratio $\frac{f_{bx}}{F_{bx}}$	Actual $M_y$ kip-ft	Actual $f_{by}$ ksi	Allow. $F_{by}$ ksi	Ratio $\frac{f_{by}}{F_{by}}$
L1	155 - 115.5 (1)	TP29.308x22x0.25	368.64	28.108	36.000	0.781	0.00	0.000	36.000	0.000
L2	115.5 - 79.25 (2)	TP35.514x28.1142x0.312 5	1077.5 7	44.781	39.000	1.148	0.00	0.000	39.000	0.000
L3	79.25 - 43.75 (3)	TP41.456x34.0565x0.375	1912.9 8	48.654	39.000	1.248	0.00	0.000	39.000	0.000
L4	43.75 - 0 (4)	TP48.8x39.7348x0.4375	3239.5 5	48.563	39.000	1.245	0.00	0.000	39.000	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual $V$ K	Actual $f_v$ ksi	Allow. $F_v$ ksi	Ratio $\frac{f_v}{F_v}$	Actual $T$ kip-ft	Actual $f_{vt}$ ksi	Allow. $F_{vt}$ ksi	Ratio $\frac{f_{vt}}{F_{vt}}$
L1	155 - 115.5 (1)	TP29.308x22x0.25	14.47	0.643	24.000	0.054	0.16	0.006	24.000	0.000
L2	115.5 - 79.25 (2)	TP35.514x28.1142x0.312 5	22.56	0.662	26.000	0.051	0.27	0.005	26.000	0.000
L3	79.25 - 43.75 (3)	TP41.456x34.0565x0.375	25.43	0.533	26.000	0.041	0.37	0.005	26.000	0.000
L4	43.75 - 0 (4)	TP48.8x39.7348x0.4375	28.60	0.426	26.000	0.033	0.53	0.004	26.000	0.000

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio $P$ $P_a$	Ratio $f_{bx}$ $F_{bx}$	Ratio $f_{by}$ $F_{by}$	Ratio $f_v$ $F_v$	Ratio $f_{vt}$ $F_{vt}$	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	155 - 115.5 (1)	0.010	0.781	0.000	0.054	0.000	0.792	1.333	H1-3+VT ✓
L2	115.5 - 79.25 (2)	0.012	1.148	0.000	0.051	0.000	1.160	1.333	H1-3+VT ✓
L3	79.25 - 43.75 (3)	0.012	1.248	0.000	0.041	0.000	1.260	1.333	H1-3+VT ✓
L4	43.75 - 0 (4)	0.014	1.245	0.000	0.033	0.000	1.260	1.333	H1-3+VT ✓

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	$P$ K	$SF \cdot P_{allow}$ K	% Capacity	Pass Fail
L1	155 - 115.5	Pole	TP29.308x22x0.25	1	-8.16	1080.07	59.4	Pass
L2	115.5 - 79.25	Pole	TP35.514x28.1142x0.3125	2	-15.29	1772.22	87.1	Pass
L3	79.25 - 43.75	Pole	TP41.456x34.0565x0.375	3	-23.01	2481.90	94.5	Pass
L4	43.75 - 0	Pole	TP48.8x39.7348x0.4375	4	-36.92	3491.31	94.5	Pass
Summary								
Pole (L3)							94.5	Pass
<b>RATING =</b>							<b>94.5</b>	<b>Pass</b>



**APPENDIX B**  
**BASE LEVEL DRAWING**





(INSTALLED—BUNDLED IN 2" CONDUIT)  
(1) 3/8" TO 143 FT LEVEL  
(2) 3/4" TO 143 FT LEVEL  
(INSTALLED)  
(6) 1-1/4" TO 143 FT LEVEL

(INSTALLED)  
(6) 1-5/8" TO 103 FT LEVEL


(INSTALLED—BUNDLED IN (2) 2" CONDUITS)  
(1) 5/16" TO 155 FT LEVEL  
(INSTALLED)  
(3) 1/2" TO 155 FT LEVEL  
(2) 5/16" TO 155 FT LEVEL

(RESERVED)  
(1) 1-5/8" TO 133 FT LEVEL  
(INSTALLED, EXTERNAL—TO BE REMOVED)  
(6) 1-5/8" TO 133 FT LEVEL  
(INSTALLED)  
(12) 1-5/8" TO 133 FT LEVEL

(INSTALLED)  
(1) 1/4" TO 113 FT LEVEL  
(13) 1-5/8" TO 113 FT LEVEL

(PROPOSED)  
(1) 5/8" TO 155 FT LEVEL  
(INSTALLED)  
(1) 1/2" TO 60 FT LEVEL  
(3) 1-1/4" TO 155 FT LEVEL

(INSTALLED—PROPOSED TO BE REMOVED)  
(12) 1-5/8" TO 78 FT LEVEL



**APPENDIX C**  
**ADDITIONAL CALCULATIONS**

## Square, Stiffened / Unstiffened Base Plate, Any Rod Material - Rev. F /G

- Assumptions:**
- 1) Rod groups at corners. Total # rods divisible by 4. Maximum total # of rods = 48 (12 per Corner).
  - 2) Rod Spacing = Straight Center-to-Center distance between any (2) adjacent rods (same corner)
  - 3) Clear space between bottom of leveling nut and top of concrete **not** exceeding  $(1) \times (\text{Rod Diameter})$

### Site Data

BU#: 876347	
Site Name: BUCKLAND MALL	
App #: 208207	
Anchor Rod Data	
Qty:	16
Diam:	2.25 in
Rod Material:	A615-J
Yield, Fy:	75 ksi
Strength, Fu:	100 ksi
Bolt Circle:	56 in
Anchor Spacing:	6 in

Base Reactions		
TIA Revision:	F	
Unfactored Moment, M:	3240	ft-kips
Unfactored Axial, P:	37	kips
Unfactored Shear, V:	29	kips

### Anchor Rod Results

TIA F --> Maximum Rod Tension: 171.3 Kips  
 Allowable Tension: 195.0 Kips  
 Anchor Rod Stress Ratio: 87.8% **Pass**

Plate Data	
W=Side:	56 in
Thick:	3.25 in
Grade:	50 ksi
Clip Distance:	6 in

### Base Plate Results

Base Plate Stress: 36.0 ksi  
 Allowable PL Bending Stress: 50.0 ksi  
 Base Plate Stress Ratio: 71.9% **Pass**

### Flexural Check

PL Ref. Data	
Yield Line (in):	30.40
Max PL Length:	30.40

Stiffener Data (Welding at both sides)	
Configuration:	Unstiffened
Weld Type:	**
Groove Depth:	in **
Groove Angle:	degrees
Fillet H. Weld:	<-- Disregard
Fillet V. Weld:	in
Width:	in
Height:	in
Thick:	in
Notch:	in
Grade:	ksi
Weld str.:	ksi

### N/A - Unstiffened


### Stiffener Results

Horizontal Weld : N/A  
 Vertical Weld: N/A  
 Plate Flex+Shear,  $f_b/F_b + (f_v/F_v)^2$ : N/A  
 Plate Tension+Shear,  $f_t/F_t + (f_v/F_v)^2$ : N/A  
 Plate Comp. (AISC Bracket): N/A

### Pole Results

Pole Punching Shear Check: N/A

Pole Data	
Diam:	48.8 in
Thick:	0.4375 in
Grade:	65 ksi
# of Sides:	18 "0" IF Round



Stress Increase Factor	
ASD ASIF:	1.333

\*\* Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

# Monopole Pier and Pad Foundation

BU #: 876347

Site Name: BUCKLAND MALL

App. Number: 208207

TIA-222 Revision: F



Design Reactions		
Shear, <b>S:</b>	29	kips
Moment, <b>M:</b>	3240	ft-kips
Tower Height, <b>H:</b>	155	ft
Tower Weight, <b>Wt:</b>	37	kips
Base Diameter, <b>BD:</b>	4.07	ft

Foundation Dimensions		
Depth, <b>D:</b>	10	ft
Pad Width, <b>W:</b>	23	ft
Neglected Depth, <b>N:</b>	3.33	ft
Thickness, <b>T:</b>	3.00	ft
Pier Diameter, <b>Pd:</b>	7.00	ft
Ext. Above Grade, <b>E:</b>	0.50	ft
BP Dist. Above Pier:	3	in.
Clear Cover, <b>Cc:</b>	3.0	in

Soil Properties		
Soil Unit Weight, $\gamma$ :	0.115	kcf
Ult. Bearing Capacity, <b>Bc:</b>	30.0	ksf
Angle of Friction, $\Phi$ :	30	deg
Cohesion, <b>Co:</b>	0.000	ksf
Passive Pressure, <b>Pp:</b>	3.500	ksf
Base Friction, $\mu$ :	0.45	

Material Properties		
Rebar Yield Strength, <b>Fy:</b>	60000	psi
Concrete Strength, <b>F'c:</b>	3000	psi
Concrete Unit Weight, $\delta_c$ :	0.150	kcf
Seismic Zone, <b>z:</b>	1	

Rebar Properties		
Pier Rebar Size, <b>Sp:</b>	11	
Pier Rebar Quantity, <b>mp:</b>	32	18
Pad Rebar Size, <b>Spad:</b>	9	
Pad Rebar Quantity, <b>mpad:</b>	33	9
Pier Tie Size, <b>St:</b>	5	4
Tie Quantity, <b>mt:</b>	12	7

Design Checks			
	Capacity/ Availability	Demand/ Limits	Check
<i>Req'd Pier Diam.(ft)</i>	7	5.57	<b>OK</b>
<i>Overturning (ft-kips)</i>	6120.19	3240.00	<b>52.9%</b>
<i>Shear Capacity (kips)</i>	318.84	29.00	<b>9.1%</b>
<i>Bearing (ksf)</i>	22.50	3.72	<b>16.5%</b>
<i>Pad Shear - 1-way (kips)</i>	735.51	476.89	<b>64.8%</b>
<i>Pad Shear - 2-way (kips)</i>	1949.60	126.90	<b>6.5%</b>
<i>Pad Moment Capacity (k-ft)</i>	4607.86	1352.87	<b>29.4%</b>
<i>Pier Moment Capacity (k-ft)</i>	5890.40	3457.50	<b>58.7%</b>

RADIO FREQUENCY FCC REGULATORY COMPLIANCE  
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC211

Buckland Mall

53 Slater Street  
Manchester, CT 06040

**March 20, 2014**

**EBI Project Number: 62141239**



March 20, 2014

Sprint  
Attn: RF Engineering Manager  
1 International Boulevard, Suite 800  
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:  
**CT03XC211 – Buckland Mall**

**Site Total: 88.907% - MPE % in full compliance**

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 53 Slater Street, Manchester, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limit for the cellular band (850 MHz Band) is approximately  $567 \mu\text{W}/\text{cm}^2$ , and the general population exposure limit for the 1900 MHz and 2500 MHz bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 53 Slater Street, Manchester, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario. Actual values seen from this site will be dramatically less than those shown in this report. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 4 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications was used in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTMM-C-120. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTMM-C-120 has a 15.9 dBd gain value at its main lobe at 2500 MHz. All calculations were performed assuming the main lobe of the antenna was focused at the base of the tower to present a worst case scenario.
- 7) The antenna mounting height centerline for the proposed antennas is **155 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC211 - Buckland Mall
Site Address	53 Slater Street, Manchester, CT 06040
Site Type	Monopole

**Sector 1**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	155	149	1/2 "	0.5	3	1390.2407	2.25125%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	155	149	1/2 "	0.5	3	195.44744	0.55819%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	155	149	1/2 "	0.5	3	390.89489	1.11638%
Sector total Power Density Value:																3.926%

**Sector 2**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	155	149	1/2 "	0.5	3	1390.2407	2.25125%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	155	149	1/2 "	0.5	3	195.44744	0.55819%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	155	149	1/2 "	0.5	3	390.89489	1.11638%
Sector total Power Density Value:																3.926%

**Sector 3**

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain in direction of sample point (dBd)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	4	80	15.9	155	149	1/2 "	0.5	3	1390.2407	2.25125%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	13.4	155	149	1/2 "	0.5	3	195.44744	0.55819%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	13.4	155	149	1/2 "	0.5	3	390.89489	1.11638%
Sector total Power Density Value:																3.926%

Site Composite MPE %	
Carrier	MPE %
Sprint	11.777%
Nextel	9.380%
Clearwire	0.790%
AT&T	16.810%
MetroPCS	11.460%
T-Mobile	0.200%
Verizon Wireless	38.490%
<b>Total Site MPE %</b>	<b>88.907%</b>

## Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **11.777% (3.926% from each sector)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **88.907%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



**Scott Heffernan**  
RF Engineering Director

**EBI Consulting**  
21 B Street  
Burlington, MA 01803