



Northeast Site Solutions  
Denise Sabo  
4 Angela's Way, Burlington CT 06013  
203-435-3640  
denise@northeastsitesolutions.com

March 31, 2022

Members of the Siting Council  
Connecticut Siting Council  
Ten Franklin Square  
New Britain, CT 06051

RE: Tower Share Application  
450 West Main Street, Meriden, CT 06451  
Latitude: 41.540036  
Longitude: -72.819033  
Site #: 842869\_Crown\_Dish

Dear Ms. Bachman:

This letter and attachments are submitted on behalf of Dish Wireless LLC. Dish Wireless LLC plans to install antennas and related equipment to the tower site located at 450 West Main Street, Meriden, Connecticut.

Dish Wireless LLC proposes to install three (3) 600/1900 MHz 5G antennas and six (6) RRUs, at the 55-foot level of the existing 100-foot monopole, one (1) Fiber cable will also be installed. Dish Wireless LLC equipment cabinets will be placed within a 7' x 5' lease area within the existing fenced compound. Included are plans by Kimley Horn, dated March 10, 2022, Exhibit C. Also included is a structural analysis prepared by B+T Group, dated July 20, 2021, confirming that the existing tower is structurally capable of supporting the proposed equipment. Attached as Exhibit D. The facility was approved by the Connecticut Siting Council, Petition No. 614 on March 11, 2003. Please see attached Exhibit A.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50aa, of Dish Wireless LLC intent to share a telecommunications facility pursuant to R.C.S.A. 16-50j-88. In accordance with R.C.S.A., a copy of this letter is being sent to Mayor Kevin Scarpato, Timothy Coon, Town Manager and Paul Dickson, Acting Director of Planning, Development & Enforcement for the City of Meriden, as well as the tower owner (Crown Castle) and property owner (Hunter Family Ltd Partnership).

The planned modifications of the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-89.

1. The proposed modification will not result in an increase in the height of the existing structure. The top of the existing tower is 100-feet and the Dish Wireless LLC antennas will be located at a centerline height of 55-feet.
2. The proposed modifications will not result in an increase of the site boundary as depicted on the attached site plan.



**NSS** **NORTHEAST**  
SITE SOLUTIONS

*Turnkey Wireless Development*

3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed local and state criteria. The incremental effect of the proposed changes will be negligent.

4. The operation of the proposed antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard. The combined site operations will result in a total power density of 97.89% as evidenced by Exhibit F.

Connecticut General Statutes 16-50aa indicates that the Council must approve the shared use of a telecommunications facility provided it finds the shared use is technically, legally, environmentally, and economically feasible and meets public safety concerns. As demonstrated in this letter, Dish Wireless LLC respectfully submits that the shared use of this facility satisfies these criteria.

A. Technical Feasibility. The existing monopole has been deemed structurally capable of supporting Dish Wireless LLC proposed loading. The structural analysis is included as Exhibit D.

B. Legal Feasibility. As referenced above, C.G.S. 16-50aa has been authorized to issue orders approving the shared use of an existing tower such as this monopole in Meriden. Under the authority granted to the Council, an order of the Council approving the requested shared use would permit Dish Wireless LLC to obtain a building permit for the proposed installation. Further, a Letter of Authorization is included as Exhibit G, authorizing Dish Wireless LLC to file this application for shared use.

C. Environmental Feasibility. The proposed shared use of this facility would have a minimal environmental impact. The installation of Dish Wireless LLC equipment at the 55-foot level of the existing 100-foot tower would have an insignificant visual impact on the area around the tower. Dish Wireless LLC ground equipment would be installed within the existing facility compound. Dish Wireless LLC shared use would therefore not cause any significant alteration in the physical or environmental characteristics of the existing site. Additionally, as evidenced by Exhibit F, the proposed antennas would not increase radio frequency emissions to a level at or above the Federal Communications Commission safety standard.

D. Economic Feasibility. Dish Wireless LLC will be entering into an agreement with the owner of this facility to mutually agreeable terms. As previously mentioned, the Letter of Authorization has been provided by the owner to assist Dish Wireless LLC with this tower sharing application.

E. Public Safety Concerns. As discussed above, the tower is structurally capable of supporting Dish Wireless LLC proposed loading. Dish Wireless LLC is not aware of any public safety concerns relative to the proposed sharing of the existing tower. Dish Wireless LLC intentions of providing new and improved wireless service through the shared use of this facility is expected to enhance the safety and welfare of local residents and individuals traveling through Meriden.

Sincerely,

*Denise Sabo*

Denise Sabo

Mobile: 203-435-3640

Fax: 413-521-0558

Office: 4 Angela's Way, Burlington CT 06013

Email: [denise@northeastsitesolutions.com](mailto:denise@northeastsitesolutions.com)



**NSS** **NORTHEAST**  
SITE SOLUTIONS  
*Turnkey Wireless Development*

Attachments

Cc: Mayor Kevin Scarpati  
City of Meriden  
142 East Main Street  
Meriden, CT 06450

Timothy Coon, Town Manager  
City of Meriden  
142 East Main Street  
Meriden, CT 06450

Paul Dickson, Acting Director of Planning, Development & Enforcement  
City of Meriden  
142 East Main Street  
Meriden, CT 06450

Hunter Family Ltd Partnership, Property Owner  
450 W Main Street  
Meriden, CT 06451

Crown Castle, Tower Owner

# Exhibit A

## **Original Facility Approval**

Petition No. 614  
AT&T Wireless PCS, LLC  
Staff Report  
March 11, 2003

On March 5, 2003, Connecticut Siting Council (Council) member Philip T. Ashton and Christina Lepage of the Council staff met with AT&T Wireless PCS, LLC (AT&T) representatives Anthony Gioffre III, and Charisma King at 450-478 West Main Street, Meriden, Connecticut for the inspection of an existing tower site. The existing property and structure are owned by Hunters Family Limited Partnership. AT&T proposes to replace the existing structure and is petitioning the Council for a declaratory ruling that no Certificate of Environmental Compatibility and Public Need (Certificate) is required for the modification.

The existing facility consists of a 100-foot guyed lattice tower, which is currently used by Hunter's Ambulance Company. AT&T proposes to replace the existing guyed lattice tower with a 100-foot monopole approximately 15 feet to the southeast. Existing antennas used by the ambulance company would be relocated to the top of the monopole. AT&T proposes to install 6 panel antennas at the 100-foot level of the proposed monopole. The proposed monopole would be designed to accommodate the antennas of two additional carriers.

The proposed equipment would be located at the base of the tower within 7-foot by 16-foot equipment pad. An 8-foot high stockade fence would surround the equipment compound. AT&T proposes to install a retaining wall along the southern portion of the equipment compound.

Access to the site would be via an existing driveway. AT&T proposes to provide utilities to the site overhead from an existing utility pole to the south. The utility corridor would cross over property recently purchased by Hunter's Ambulance Company. Two new poles would be necessary to install a utility line to the site. AT&T submits that the proposed overhead utility installation would cause the least amount of disturbance to the site and surrounding area, due to the presence of bedrock, sidewalks and a parking lot.

Surrounding land uses include a mix of residential and commercial uses. The proposed site is zoned Commercial. The calculated cumulative worst-case radio frequency power density would not exceed the applicable standard.

AT&T contends that it would not need to construct a telecommunications tower to provide coverage to this area of Meriden, and the proposed modification of the existing structure would not cause a substantial adverse environmental effect. Staff recommends approval, with the condition that the tower be situated so as to avoid the removal of an existing tree.

# Exhibit B

## Property Card



# CITY OF MERIDEN

## GIS Services

**PROPERTY INFORMATION** Location: **450 WEST MAIN ST** Map/Lot: 0612-0202-0001-0002

**OWNER INFORMATION** Owner(s): HUNTER FAMILY LTD PRTSHP Owner Address: 450 W MAIN ST  
MERIDEN, CT 06451

### BUILDING INFORMATION

**Card Number:** 1

Total Units: 0

OVERVIEW	
<b>Building ID</b>	9661
<b>Finished Area</b>	27,374
<b>Comm/Rental Units</b>	0
<b>Living Units</b>	0
<b>Building Type</b>	Mixed Use-M
<b>Year Built</b>	1980
<b>Effective Yr Built</b>	
<b>Building Number</b>	1
<b>Condo Name</b>	

INTERIOR DETAILS	
<b>Rooms</b>	
<b>BedRooms</b>	
<b>Full Bath</b>	0
<b>Full Bath Rating</b>	
<b>Half Bath</b>	0
<b>Half Bath Rating</b>	
<b>Kitchens</b>	0
<b>Kitchen Rating</b>	
<b>Fireplaces</b>	0

CONSTRUCTION DETAILS	
<b>Exterior</b>	Brick
<b>Roof Structure</b>	Gable
<b>Roof Cover</b>	Asphalt
<b>Quality</b>	C
<b>Heat Fuel</b>	Oil
<b>Heat Type</b>	Forced Air
<b>Prcnt. Heated</b>	100.00
<b>Prcnt. AC</b>	50.00
<b>Stories</b>	2 story
<b>Foundation</b>	Concrete

### Sub Area Summary

Building ID	Description	Total Area	Fin. Area	Perimeter
9661	1st FLOOR	4,980	4,980	388
9661	1st FLOOR	3,988	3,988	272
9661	2nd FLOOR	4,980	4,980	388
9661	CARPORT	4,312	0	284
9661	GARAGE	1,248	0	152
9661	OPEN PORCH	160	0	74

**Special Features**

No Special Features found.

**APPRAISAL INFORMATION**

Tax District: 2 District Name: INNER DISTRICT District Mill Rate: 43.41

Grand List  
Year: 2019

Land Appraised	Building Appraised	Yard Appraised	Total Appraised Value	Land Assessed	Building Assessed	Yard Assessed	Special Land Value	Total Assessed Value
\$487,100	\$1,578,500	\$42,800	\$2,108,400	\$340,970	\$1,104,950	\$29,960	\$0	\$1,475,880

Previous  
Year: 2018

Land Value	Building Value	Yard Items	Appraised Value	Land Value	Building Value	Yard Items	Assessed Value
\$487,400	\$1,578,400	\$42,800	\$2,108,600	\$341,180	\$1,104,880	\$29,960	\$1,476,020

**LAND INFORMATION**

Land Use	Zoning	Land Area	Neighborhood Description
Comm Bldg	C-2	2.60069	OUTER W. MAIN

\*Confirm zoning with Planning Office.  
Zoning map is the official document to determine zone.

**SALES INFORMATION**

Sale Date	Sale Price	Book	Page	Grantor	Grantee	Deed Type
12/31/1997	\$650,000	2322	336			

**ASSESSOR'S PERMIT HISTORY**




Date	Permit#	Description	Permit Type	Status	Cost
5/10/2017	B-17-334	REPLACE ROOF.		Closed	\$31,275
4/21/2017	B-17-267	REPLACE ANTENNA PANELS.ADD REMOTE RADIO HEADS TO CELL TOWER.		Closed	\$15,000
3/6/2017	B-17-109	AT&T REPLACE 3 ANTENNA & 3 RRU'S TO EXISTING EQUIPMENT.		Closed	\$20,000
7/15/2016	B-16-659	REPLACE 3 ANTENNAI W/NEW.		Closed	\$19,450
9/24/2015	B-15-743	AT&T ADD 3 ANTENNAE/3 RRU'S/1 FIBER LINE TO EXISTING EQUIPMENT ON TOWER.		Closed	\$20,000
6/22/2015	E-15-295	INSTALL NEW 150A SERVICE (VERIZON),aAPPROVED BY BLDG DEPT.		Closed	\$25,000
5/18/2015	E-15-210	NEW 200A/3PH/4W/ SERVICE FROM MDP TO SHELTER BLDG.		Closed	\$5,000
4/6/2015	P-15-64			Closed	\$10,000
2/20/2015	B-15-61	INSTALL ANTENNAE & GROUND EQUIPMENT FOR VERIZON WIRELESS TELE.		Closed	\$75,000
1/5/2015	B-14-285	ADD ANTENNAE TO EXISTING TOWER		Closed	\$15,000
7/21/2014	2157			Closed	\$30,000
6/6/2014	1664			Closed	\$8,000
6/6/2014	1665			Closed	\$1,000
2/25/2013	473	SPRINT - MODIF. TO TELEC. INSTALLATION ON MONOPOLE TOWER, REPL. 3 ANTENNA & CABLES AND ADD RRH'S AND NOTCH FILTERS BEHIND THE NEW ANTENNA ON TOWER, ADD CIENA EQUIP. ENCL. & FIBER JUNCTION BOX & EITHER RETROFIT OR REPLACE BTS CABINET WITHIN EQUIP. SHELTER.		Closed	\$30,000
12/21/2012	3950	AT&T - REMOVE & REPLACE ONE D.C. POWER CABINET, INSTALL NEW LTE EQUIPMENT ON OPEN SLAB, CONDUITS, AC & DC CIRCUITS, FIBER OPTICS, GROUNDING & BONDING.		Closed	\$3,800
11/1/2012	3422	AT&T - ADD 3 LTE ANTENNAS, SURGE ARRESTOR, RRU'S, PURCELL CABINET, CONCRETE PAD & DC/FIBER LINES		Closed	\$25,000
12/5/2003	4261	200 AMP SERV	CA	Closed	\$9,400
12/5/2003	4261	AT&T WIRELESS CELLSITE	CA	Closed	\$9,400
8/28/2003	3042	REP EX COMMUNI TOWER	CA	Closed	\$125,000
8/28/2003	3042	INSTALL COMMUNICA EQUIPME	CA	Closed	\$125,000
1/1/1900	3042	INSTALL COMMUNICA EQUIPME	CA	Closed	\$125,000
1/1/1900	4261	200 AMP SERV	CA	Closed	\$9,400
1/1/1900	3042	REP EX COMMUNI TOWER	CA	Closed	\$125,000
1/1/1900	4261	AT&T WIRELESS CELLSITE	CA	Closed	\$9,400

PROPERTY  
IMAGES



1 2



9663  
0612-0202-0001-0002  
1

# Exhibit C

## **Construction Drawings**



DISH Wireless L.L.C. SITE ID:

**BOHVN00156A**

DISH Wireless L.L.C. SITE ADDRESS:

**450-478 WEST MAIN STREET  
MERIDEN, CT 06451**

SCOPE OF WORK	
THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:	
<b>TOWER SCOPE OF WORK:</b>	
<ul style="list-style-type: none"> <li>• INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)</li> <li>• INSTALL (1) PROPOSED ANTENNA PLATFORM MOUNT</li> <li>• INSTALL PROPOSED JUMPERS</li> <li>• INSTALL (6) PROPOSED RRUs (2 PER SECTOR)</li> <li>• INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)</li> <li>• INSTALL (1) PROPOSED HYBRID CABLE</li> </ul>	
<b>GROUND SCOPE OF WORK:</b>	
<ul style="list-style-type: none"> <li>• INSTALL (1) PROPOSED METAL PLATFORM</li> <li>• INSTALL (1) PROPOSED PPC CABINET</li> <li>• INSTALL (1) PROPOSED EQUIPMENT CABINET</li> <li>• INSTALL (1) PROPOSED POWER CONDUIT</li> <li>• INSTALL (1) PROPOSED TELCO CONDUIT</li> <li>• INSTALL (1) PROPOSED TELCO-FIBER BOX</li> <li>• INSTALL (1) PROPOSED GPS UNIT</li> <li>• INSTALL (1) PROPOSED FIBER NID (IF REQUIRED)</li> <li>• DISH Wireless, L.L.C. TO UTILIZE EXISTING NEXTEL METER SOCKET AND DISCONNECT</li> <li>• DISH Wireless, L.L.C. TO UTILIZE EXISTING ICE BRIDGE</li> </ul>	


SITE INFORMATION	PROJECT DIRECTORY
PROPERTY OWNER: HUNTER FAMILY LTD PRTSHIP ADDRESS: 450 W MAIN ST MERIDEN, CT 06451	APPLICANT: DISH WIRELESS, LLC. 5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120
TOWER TYPE: MONOPOLE	TOWER OWNER: CROWN CASTLE 2000 CORPORATE DRIVE CANONSBURG, PA 15317 (877) 486-9377
CROWN CASTLE SITE ID: 842869	SITE DESIGNER: KIMLEY-HORN & ASSOCIATES 3875 EMBASSY PKWY, SUITE 280 AKRON, OH 44333 (216) 505-7771 COA #: PEC.0000738
CROWN CASTLE 553374	SITE ACQUISITION: VICTOR NUNEZ (917) 563-3682
APP NUMBER: NEW HAVEN	CONSTRUCTION MANAGER: JAMIER SOTO JAMIER.SOTO@DISH.COM
COUNTY: NEW HAVEN	RF ENGINEER: SYED ZAIDI SYED.ZAIDI@DISH.COM
LATITUDE (NAD 83): 41° 32' 24.11" N 41.540031°	
LONGITUDE (NAD 83): 72° 49' 8.47" W -72.819019°	
ZONING JURISDICTION: CONNECTICUT SITING COUNCIL	
ZONING DISTRICT: C-2	
PARCEL NUMBER: MERI-000612-000202-000001-000002	
OCCUPANCY GROUP: U	
CONSTRUCTION TYPE: II-B	
POWER COMPANY: CONNECTICUT LIGHT & POWER	
TELEPHONE COMPANY: TBD	



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: SEW	CHECKED BY: MCK	APPROVED BY: MCK
---------------	-----------------	------------------

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
TITLE SHEET

SHEET NUMBER  
**T-1**

**CONNECTICUT CODE OF COMPLIANCE**

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

**SHEET INDEX**

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES


**SITE PHOTO**



**DIRECTIONS**

DIRECTIONS FROM BRADLEY INTERNATIONAL AIRPORT:  
 x CONTINUE TO EAST GRANBY (0.9 MI)  
 x TAKE I-91 S TO LEWIS AVE IN MERIDEN. TAK EXIST 6 FROM I-691 W (34.5 MI)  
 x FOLLOW LEWIS AVE AND W MAIN ST TO S VINE ST (1.3 MI)

**VICINITY MAP**



UNDERGROUND SERVICE ALERT CBYD 811  
 UTILITY NOTIFICATION CENTER OF CONNECTICUT  
 (800) 922-4455  
 WWW.CBYD.COM  
 CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION



**GENERAL NOTES**

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.

**NOTES**

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

**NOTES**


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. CONTRACTOR SHALL MAINTAIN A 10'-0" MINIMUM SEPARATION BETWEEN THE PROPOSED GPS UNIT, TRANSMITTING ANTENNAS AND EXISTING GPS UNITS.
3. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Jensen-Frederat

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: SEW    CHECKED BY: MCK    APPROVED BY: MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless, L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451


SHEET TITLE  
OVERALL AND ENLARGED SITE PLAN

SHEET NUMBER


**A-1**




**OVERALL SITE PLAN**



1



**ENLARGED SITE PLAN**



2




**OVERALL UTILITY ROUTE PLAN**

NO SCALE


3

**NOTES**


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.




**PROPOSED WEST ELEVATION**



1



**ANTENNA LAYOUT**



2

SECTOR	POSITION	ANTENNA					TRANSMISSION CABLE	
		EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZIMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA - MX08FRO665-21	5G	72.0" x 20.0"	0°	55'-0"	(1) HIGH-CAPACITY HYBRID CABLE (90'-0" LONG)
BETA	B1	PROPOSED	JMA - MX08FRO665-21	5G	72.0" x 20.0"	120°	55'-0"	
GAMMA	C1	PROPOSED	JMA - MX08FRO665-21	5G	72.0" x 20.0"	240°	55'-0"	

SECTOR	POSITION	RRH		NOTES
		MANUFACTURER - MODEL NUMBER	TECHNOLOGY	
ALPHA	A1	FUJITSU - TA08025-B604	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.
	A1	FUJITSU - TA08025-B605	5G	
BETA	B1	FUJITSU - TA08025-B604	5G	
	B1	FUJITSU - TA08025-B605	5G	
GAMMA	C1	FUJITSU - TA08025-B604	5G	
	C1	FUJITSU - TA08025-B605	5G	

**ANTENNA SCHEDULE**

NO SCALE


3



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Frederick

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

SEW MCK MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

KHCLC-16938


DISH Wireless L.L.C. PROJECT INFORMATION

BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451


SHEET TITLE  
ELEVATION, ANTENNA LAYOUT AND SCHEDULE

SHEET NUMBER


**A-2**



PLATFORM EQUIPMENT PLAN




1




PLATFORM DETAIL

NO SCALE 2




H-FRAME DETAIL

NO SCALE 3




NOT USED

NO SCALE 4




FRONT ELEVATION



BACK ELEVATION

H-FRAME EQUIPMENT ELEVATION



5

- NOTES**
- CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
  - WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH Wireless L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
  - EQUIPMENT CABINET OMITTED FOR CLARITY

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

DocuSigned by  
Kyle Frederick

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK
RFDS REV #:		1

**CONSTRUCTION DOCUMENTS**


SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938


DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
EQUIPMENT PLATFORM AND H-FRAME DETAILS

SHEET NUMBER  
**A-3**



CABINET DETAIL      NO SCALE      1




POWER PROTECTION CABINET (PPC) DETAIL      NO SCALE      2

NOT USED      NO SCALE      3

NOT USED      NO SCALE      4


NOT USED      NO SCALE      5



FIBER TELCO ENCLOSURE DETAIL      NO SCALE      6

NOT USED      NO SCALE      7

NOT USED      NO SCALE      8




HYBRID CABLE RUN      NO SCALE      9



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
*Kyle Freeman*

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK
RFDS REV #:		1

### CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
**KHCLC-16938**


DISH Wireless L.L.C.  
PROJECT INFORMATION  
**BOHVN00156A**  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
**EQUIPMENT DETAILS**


SHEET NUMBER  
**A-4**




PCTEL GPSGL-TMG-SPI-40NCB	
DIMENSIONS (DIAxH) MM/INCH	81x184mm 3.2"x7.25"
WEIGHT W/ACCESSORIES	075 lbs
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1590 ± 30MHz





TOP



BACK



SIDE



GPS DETAIL

NO SCALE

1

GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE

2

CABLES UNLIMITED HYBRID CABLE  
MINIMUM BEND RADIUS

NO SCALE

3

NOT USED

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE


9



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Freeman

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451


SHEET TITLE  
EQUIPMENT DETAILS

SHEET NUMBER  
**A-5**


FUJITSU TRIPLE BAND TA08025-B605	
DIMENSIONS (HxWxD)	14.9"x15.7"x9"
WEIGHT	74.95 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V




PLAN



BACK




SIDE




FRONT


FUJITSU DUAL BAND TA08025-B604	
DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"
WEIGHT	63.9 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V




PLAN



BACK




SIDE




FRONT

SABRE DOUBLE Z-BRACKET C10123155	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



NOTE:  
OR DISH Wireless L.L.C.  
APPROVED EQUIVALENT



RRH DETAIL

NO SCALE

1

RRH DETAIL

NO SCALE

2

RRH MOUNT DETAIL

NO SCALE

3


JMA WIRELESS MX08FRO665-21 ANTENNA	
DIMENSIONS (HxWxD)	72.0"x20.0"x8.0"
TOTAL WEIGHT	82.5 LB
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE




PLAN



BACK



SIDE



FRONT

ANTENNA DETAIL

NO SCALE

4

NOT USED

NO SCALE

5

ANTENNA BRACKET DETAIL


NO SCALE

6


RAYCAP RDIC-9181-PF-48 DC SURGE PROTECTION (OVP)	
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS




PLAN



SIDE



BACK



FRONT


SURGE SUPPRESSION DETAIL (OVP)

NO SCALE

7


COMMSCOPE XP-2040 CROSSOVER PLATE	
DIMENSIONS (HxW)	10"x12"
WEIGHT	11 lbs

NOTE:  
OR DISH Wireless L.L.C.  
APPROVED EQUIVALENT




PLAN PLATE

SIDE PLATE



PLAN U-BOLT

SIDE U-BOLT





RRH/OVP MOUNT DETAIL

NO SCALE

8

COMMSCOPE MC-PK8-DSH	
FACE WIDTH	96"
WEIGHT	1373.08 lbs
NOTE: 15" TO 38" O.D.	

NOTE:  
OR DISH Wireless L.L.C.  
APPROVED EQUIVALENT



ANTENNA PLATFORM DETAIL

NO SCALE


9



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Freeman

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

SEW MCK MCK

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION

BOHVN00156A  
450-478 WEST MAIN  
STREET  
MERIDEN, CT 06451


SHEET TITLE  
EQUIPMENT DETAILS

SHEET NUMBER


A-6

**NOTES**

1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.
3. DUE TO UTILITY EASEMENT RIGHTS SPECIFIED IN THE GROUND LEASE, CUSTOMER MAY INSTALL EQUIPMENT WITHIN SPECIFIED UTILITY EASEMENT AREA. "PWR" AND "FBR" PATH DEPICTED ON A-1 AND E-1 REPRESENT PLANNED ROUTING BASED ON BEST AVAILABLE INFORMATION INCLUDING BUT NOT LIMITED TO A SURVEY, EXHIBITS, METES AND BOUNDS OF THE UTILITY EASEMENT, FIELD VERIFICATION, PRIOR PROJECT DOCUMENTATION AND OTHER REAL PROPERTY RIGHTS DOCUMENTS. WHEN INSTALLING THE UTILITIES PLEASE LOCATE AND FOLLOW EXISTING PATH. IF EXISTING PATH IS MATERIALLY INCONSISTENT WITH "PWR" AND "FBR" PATH DEPICTED ON A-1 AND E-1 AND SAID VARIANCE IS NOT NOTED ON CDs, PLEASE NOTIFY TOWER OWNER AS FURTHER COORDINATION MAY BE NEEDED.



**UTILITY ROUTE PLAN**



1


DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. ALL TRENCHES IN COMPOUND TO BE HAND DUG


**ELECTRICAL NOTES**

NO SCALE

2



**OVERALL UTILITY ROUTE PLAN**




3



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Frederick

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
ELECTRICAL/FIBER ROUTE PLAN AND NOTES

SHEET NUMBER

**E-1**

CARLON EXPANSION FITTINGS				
COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"

VARIES PER PART NUMBER

SLIP JOINT (SEE CHART FOR PART NUMBER)

NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

### TRENCHING NOTES

- CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
- TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
- ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.

SEE TRENCHING NOTE 1

BACKFILL PER SITE WORK SPECIFICATIONS (SEE GENERAL NOTES)

SLOPE TO SUIT SOIL CONDITION IN ACCORDANCE WITH LOCAL REGULATIONS SEE TRENCHING NOTE 2


30" OR 6" BELOW FROST LINE, WHICHEVER IS GREATER

UTILITY WARNING TAPE

SAND BEDDING PER SITE WORK SPECIFICATIONS

VERTICAL DEPTH SEE TRENCHING NOTE 2

EXPANSION JOINT DETAIL		NO SCALE	1	TYPICAL UNDERGROUND TRENCH DETAIL		NO SCALE	2	NOT USED		NO SCALE	3
------------------------	--	----------	---	-----------------------------------	--	----------	---	----------	--	----------	---



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL)		NO SCALE	4	NOT USED		NO SCALE	5	NOT USED		NO SCALE	6
---	--	----------	---	----------	--	----------	---	----------	--	----------	---

NOT USED		NO SCALE	7	NOT USED		NO SCALE	8	NOT USED		NO SCALE	9
----------	--	----------	---	----------	--	----------	---	----------	--	----------	---

NOT USED		NO SCALE	7	NOT USED		NO SCALE	8	NOT USED		NO SCALE	9
----------	--	----------	---	----------	--	----------	---	----------	--	----------	---

NOT USED		NO SCALE	7	NOT USED		NO SCALE	8	NOT USED		NO SCALE	9
----------	--	----------	---	----------	--	----------	---	----------	--	----------	---

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601

DocuSigned by  
Kyle Frederick

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK
RFDS REV #:		1

### CONSTRUCTION DOCUMENTS



SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
ELECTRICAL  
DETAILS

SHEET NUMBER  
**E-2**



**NOTE:**  
BRANCH CIRCUIT WIRING SUPPLYING RECTIFIERS ARE TO BE RATED UL1015, 105°C, 600V, AND PVC INSULATED, IN THE SIZES SHOWN IN THE ONE-LINE DIAGRAM. CONTRACTOR MAY SUBSTITUTE UL1015 WIRE FOR THWN-2 FOR CONVENIENCE OUTLET BRANCH CIRCUIT.

**BREAKERS REQUIRED:**  
(4) 30A, 2P BREAKER - SQUARE D P/N:Q0230  
(1) 15A, 1P BREAKER - SQUARE D P/N:Q0115

PPC ONE-LINE DIAGRAM

NO SCALE 1

PROPOSED CHARLES PANEL SCHEDULE										
LOAD SERVED	VOLT AMPS (WATTS)		TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS)		LOAD SERVED
	L1	L2						L1	L2	
PPC GFCI OUTLET	180	180	15A	1	A	2	30A	2880	2880	ABB/GE INFINITY RECTIFIER 1
CHARLES GFCI OUTLET	180	180	15A	3	B	4	30A	2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				5	A	6	30A	2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				7	B	8	30A	2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				9	A	10				-SPACE-
-SPACE-				11	B	12				-SPACE-
-SPACE-				13	A	14				-SPACE-
-SPACE-				15	B	16				-SPACE-
-SPACE-				17	A	18				-SPACE-
-SPACE-				19	B	20				-SPACE-
-SPACE-				21	A	22				-SPACE-
-SPACE-				23	B	24				-SPACE-
VOLTAGE AMPS		180	180					11520	11520	
200A MCB, 1ϕ, 24 SPACE, 120/240V				L1	L2					
MB RATING: 65,000 AIC				11700	11700					
				98	98					
				98						
				123						

PANEL SCHEDULE

NO SCALE 2

NOT USED

NO SCALE 3

NOTES

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED SHORT CIRCUIT CALCULATIONS AND THE AIC RATINGS FOR EACH DEVICE IS ADEQUATE TO PROTECT THE EQUIPMENT AND THE ELECTRICAL SYSTEM.

THE ENGINEER OF RECORD HAS PERFORMED ALL REQUIRED VOLTAGE DROP CALCULATIONS AND ALL BRANCH CIRCUIT AND FEEDERS COMPLY WITH THE NEC (LISTED ON T-1) ARTICLE 210.19(A)(1) FPN NO. 4.

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(a) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

#12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A  
#10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A  
#8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A  
#6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358.  
0.5" CONDUIT - 0.122 SQ. IN AREA  
0.75" CONDUIT - 0.213 SQ. IN AREA  
2.0" CONDUIT - 1.316 SQ. IN AREA  
3.0" CONDUIT - 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.  
#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN  
#10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND  
TOTAL = 0.0633 SQ. IN


0.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.  
#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN  
#10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND  
TOTAL = 0.1146 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.  
3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN  
#6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND  
TOTAL = 0.8544 SQ. IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK
RFDS REV #:	1	

CONSTRUCTION DOCUMENTS


SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE

SHEET NUMBER  
**E-3**




**TYPICAL EQUIPMENT GROUNDING PLAN**

NO SCALE 1


**NOTES**

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



**TYPICAL ANTENNA GROUNDING PLAN**

NO SCALE 2



**GROUNDING LEGEND**

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

**GROUNDING KEY NOTES**

- (A) **EXTERIOR GROUND RING:** #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- (B) **TOWER GROUND RING:** THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- (C) **INTERIOR GROUND RING:** #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- (D) **BOND TO INTERIOR GROUND RING:** #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- (E) **GROUND ROD:** UL LISTED COPPER CLAD STEEL, MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- (F) **CELL REFERENCE GROUND BAR:** POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (G) **HATCH PLATE GROUND BAR:** BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) **EXTERIOR CABLE ENTRY PORT GROUND BARS:** LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- (I) **TELCO GROUND BAR:** BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- (J) **FRAME BONDING:** THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- (K) **INTERIOR UNIT BONDS:** METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- (L) **FENCE AND GATE GROUNDING:** METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- (M) **EXTERIOR UNIT BONDS:** METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- (N) **ICE BRIDGE SUPPORTS:** EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.
- (O) **DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR**
- (P) **TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH Wireless L.L.C. GROUNDING NOTES.**

**GROUNDING KEY NOTES**


NO SCALE 3



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: SEW CHECKED BY: MCK APPROVED BY: MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938


DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
GROUNDING PLANS AND NOTES

SHEET NUMBER


**G-1**

**NOTES**  
EQUIPMENT CABINET OMITTED FOR CLARITY




**H-FRAME GROUNDING DETAIL**

NO SCALE 1




**TYPICAL GPS UNIT GROUNDING**

NO SCALE 2




**OUTDOOR CABINET GROUNDING**

NO SCALE 3




**TRANSITIONING GROUND DETAIL**

NO SCALE 4



**TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE**

NO SCALE 5



**TYPICAL GROUND RING TRENCH**


NO SCALE 6



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Freeman

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938



DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
GROUNDING DETAILS

SHEET NUMBER

**G-2**

1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.
6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.
8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).




**dish**  
wireless.

5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120

**Kimley»Horn**

COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Freeman

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLE-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
GROUNDING DETAILS

SHEET NUMBER  
**G-3**

TYPICAL GROUNDING NOTES


NO SCALE 1

TYPICAL EXTERIOR TWO HOLE LUG

NO SCALE 2

TYPICAL INTERIOR TWO HOLE LUG

NO SCALE 3



LUG DETAIL

NO SCALE 4

NOT USED

NO SCALE 5

NOT USED

NO SCALE 6

NOT USED

NO SCALE 7

NOT USED

NO SCALE 8

NOT USED

NO SCALE 9



HYBRID/DISCREET CABLES												3/4" TAPE WIDTHS WITH 3/4" SPACING																			
LOW-BAND RRH (600 MHz N71 BASEBAND) + (850 MHz N26 BAND) + (700 MHz N29 BAND) - OPTIONAL PER MARKET  ADD FREQUENCY COLOR TO SECTOR BAND (CBRS WILL USE YELLOW BAND)												ALPHA RRH				BETA RRH				GAMMA RRH											
												PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT				
MID-BAND RRH (AWS BANDS N66+N70)  ADD FREQUENCY COLOR TO SECTOR BAND (CBRS WILL USE YELLOW BANDS)												RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN								
												ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN	ORANGE	ORANGE	GREEN	GREEN				
HYBRID/DISCREET CABLES INCLUDE SECTOR BANDS BEING SUPPORTED ALONG WITH FREQUENCY BANDS.  EXAMPLE 1 - HYBRID, OR DISCREET, SUPPORTS ALL SECTORS, BOTH LOW-BANDS AND MID-BANDS.  EXAMPLE 2 - HYBRID, OR DISCREET, SUPPORTS CBRS ONLY, ALL SECTORS.  EXAMPLE 3 - MAIN COAX WITH GROUND MOUNTED RRHS.												EXAMPLE 1		EXAMPLE 2		EXAMPLE 3		CANISTER COAX #1 (ALPHA)		CANISTER COAX #2 (ALPHA)											
												RED	RED	RED	RED	RED	RED	RED	RED	RED	RED	RED	RED								
FIBER JUMPERS TO RRHS LOW-BAND HHR FIBER CABLES HAVE SECTOR STRIPE ONLY.												LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH									
												RED	ORANGE	RED	PURPLE	RED	PURPLE	BLUE	PURPLE	BLUE	PURPLE	GREEN	PURPLE	GREEN	PURPLE						
POWER CABLES TO RRHS LOW-BAND RRH POWER CABLES HAVE SECTOR STRIPE ONLY.												LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH		LOW BAND RRH		MID BAND RRH									
												RED	ORANGE	RED	PURPLE	RED	PURPLE	BLUE	PURPLE	BLUE	PURPLE	GREEN	PURPLE	GREEN	PURPLE						
RET MOTORS AT ANTENNAS RET CONTROL IS HANDLED BY THE MID-BAND RRH WHEN ONE SET OF RET PORTS EXIST ON ANTENNA.  SEPARATE RET CABLES ARE USED WHEN ANTENNA PORTS PROVIDE INPUTS FOR BOTH LOW AND MID BANDS.												ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND		ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND		ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND									
												IN	IN	IN	IN	IN	IN	IN	IN	IN	IN	IN	IN								
MICROWAVE RADIO LINKS LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP WITH THE AZIMUTH COLOR OVERLAPPING IN THE MIDDLE. ADD ADDITIONAL SECTOR COLOR BANDS FOR EACH ADDITIONAL MW RADIO.  MICROWAVE CABLES WILL REQUIRE P-TOUCH LABELS INSIDE THE CABINET TO IDENTIFY THE LOCAL AND REMOTE SITE ID'S.												FORWARD AZIMUTH OF 0-120 DEGREES		FORWARD AZIMUTH OF 120-240 DEGREES		FORWARD AZIMUTH OF 240-359 DEGREES															
												PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY												
												WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE								
												RED	RED	WHITE	RED	BLUE	BLUE	WHITE	BLUE	GREEN	GREEN	WHITE	GREEN								

RF CABLE COLOR CODES

1


NOT USED

4


LOW BANDS (N71+N26)  
OPTIONAL - (N29)



AWS  
(N66+N70+H-BLOCK)



CBRS TECH  
(3 GHz)



NEGATIVE SLANT PORT  
ON ANT/RRH



ALPHA SECTOR



BETA SECTOR



GAMMA SECTOR



COLOR IDENTIFIER

2

NOT USED

3

NOT USED


4



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Freeman

IT IS A VIOLATION OF LAW FOR ANY PERSON,  
UNLESS THEY ARE ACTING UNDER THE DIRECTION  
OF A LICENSED PROFESSIONAL ENGINEER,  
TO ALTER THIS DOCUMENT.

DRAWN BY: SEW  
CHECKED BY: MCK  
APPROVED BY: MCK

RFDS REV #: 1

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN  
STREET  
MERIDEN, CT 06451

SHEET TITLE  
RF  
CABLE COLOR CODES

SHEET NUMBER  
RF-1

EXOTHERMIC CONNECTION  
 MECHANICAL CONNECTION  
 BUSS BAR INSULATOR  
 CHEMICAL ELECTROLYTIC GROUNDING SYSTEM  
 TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM  
 EXOTHERMIC WITH INSPECTION SLEEVE  
 GROUNDING BAR  
 GROUND ROD  
 TEST GROUND ROD WITH INSPECTION SLEEVE  
 SINGLE POLE SWITCH  
 DUPLEX RECEPTACLE  
 DUPLEX GFCI RECEPTACLE  
 FLUORESCENT LIGHTING FIXTURE (2) TWO LAMPS 48-T8  
 SMOKE DETECTION (DC)  
 EMERGENCY LIGHTING (DC)  
 SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW  
 LED-1-25A400/51K-SR4-120-PE-DBBTXD  
 CHAIN LINK FENCE  
 WOOD/WROUGHT IRON FENCE  
 WALL STRUCTURE  
 LEASE AREA  
 PROPERTY LINE (PL)  
 SETBACKS  
 ICE BRIDGE  
 CABLE TRAY  
 WATER LINE  
 UNDERGROUND POWER  
 UNDERGROUND TELCO  
 OVERHEAD POWER  
 OVERHEAD TELCO  
 UNDERGROUND TELCO/POWER  
 ABOVE GROUND POWER  
 ABOVE GROUND TELCO  
 ABOVE GROUND TELCO/POWER  
 WORKPOINT  
 SECTION REFERENCE  
 DETAIL REFERENCE



**LEGEND**

AB	ANCHOR BOLT	IN	INCH
ABV	ABOVE	INT	INTERIOR
AC	ALTERNATING CURRENT	LB(S)	POUND(S)
ADDL	ADDITIONAL	LF	LINEAR FEET
AFF	ABOVE FINISHED FLOOR	LTE	LONG TERM EVOLUTION
AFG	ABOVE FINISHED GRADE	MAS	MASONRY
AGL	ABOVE GROUND LEVEL	MAX	MAXIMUM
AIC	AMPERAGE INTERRUPTION CAPACITY	MB	MACHINE BOLT
ALUM	ALUMINUM	MECH	MECHANICAL
ALT	ALTERNATE	MFR	MANUFACTURER
ANT	ANTENNA	MGB	MASTER GROUND BAR
APPROX	APPROXIMATE	MIN	MINIMUM
ARCH	ARCHITECTURAL	MISC	MISCELLANEOUS
ATS	AUTOMATIC TRANSFER SWITCH	MTL	METAL
AWG	AMERICAN WIRE GAUGE	MTS	MANUAL TRANSFER SWITCH
BATT	BATTERY	MW	MICROWAVE
BLDG	BUILDING	NEC	NATIONAL ELECTRIC CODE
BLK	BLOCK	NM	NEWTON METERS
BLKG	BLOCKING	NO.	NUMBER
BM	BEAM	#	NUMBER
BTC	BARE TINNED COPPER CONDUCTOR	NTS	NOT TO SCALE
BOF	BOTTOM OF FOOTING	OC	ON-CENTER
CAB	CABINET	OSHA	OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
CANT	CANTILEVERED	OPNG	OPENING
CHG	CHARGING	P/C	PRECAST CONCRETE
CLG	CEILING	PCS	PERSONAL COMMUNICATION SERVICES
CLR	CLEAR	PCU	PRIMARY CONTROL UNIT
COL	COLUMN	PRC	PRIMARY RADIO CABINET
COMM	COMMON	PP	POLARIZING PRESERVING
CONC	CONCRETE	PSF	POUNDS PER SQUARE FOOT
CONSTR	CONSTRUCTION	PSI	POUNDS PER SQUARE INCH
DBL	DOUBLE	PT	PRESSURE TREATED
DC	DIRECT CURRENT	PWR	POWER CABINET
DEPT	DEPARTMENT	QTY	QUANTITY
DF	DOUGLAS FIR	RAD	RADIUS
DIA	DIAMETER	RECT	RECTIFIER
DIAG	DIAGONAL	REF	REFERENCE
DIM	DIMENSION	REINF	REINFORCEMENT
DWG	DRAWING	REQ'D	REQUIRED
DWL	DOWEL	RET	REMOTE ELECTRIC TILT
EA	EACH	RF	RADIO FREQUENCY
EC	ELECTRICAL CONDUCTOR	RMC	RIGID METALLIC CONDUIT
EL	ELEVATION	RRH	REMOTE RADIO HEAD
ELEC	ELECTRICAL	RRU	REMOTE RADIO UNIT
EMT	ELECTRICAL METALLIC TUBING	RWY	RACEWAY
ENG	ENGINEER	SCH	SCHEDULE
EQ	EQUAL	SHT	SHEET
EXP	EXPANSION	SIAD	SMART INTEGRATED ACCESS DEVICE
EXT	EXTERIOR	SIM	SIMILAR
EW	EACH WAY	SPEC	SPECIFICATION
FAB	FABRICATION	SQ	SQUARE
FF	FINISH FLOOR	SS	STAINLESS STEEL
FG	FINISH GRADE	STD	STANDARD
FIF	FACILITY INTERFACE FRAME	STL	STEEL
FIN	FINISH(ED)	TEMP	TEMPORARY
FLR	FLOOR	THK	THICKNESS
FDN	FOUNDATION	TMA	TOWER MOUNTED AMPLIFIER
FOC	FACE OF CONCRETE	TN	TOE NAIL
FOM	FACE OF MASONRY	TOA	TOP OF ANTENNA
FOS	FACE OF STUD	TOC	TOP OF CURB
FOW	FACE OF WALL	TOF	TOP OF FOUNDATION
FS	FINISH SURFACE	TOP	TOP OF PLATE (PARAPET)
FT	FOOT	TOS	TOP OF STEEL
FTG	FOOTING	TOW	TOP OF WALL
GA	GAUGE	TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSION
GEN	GENERATOR	TYP	TYPICAL
GFCI	GROUND FAULT CIRCUIT INTERRUPTER	UG	UNDERGROUND
GLB	GLUE LAMINATED BEAM	UL	UNDERWRITERS LABORATORY
GLV	GALVANIZED	UNO	UNLESS NOTED OTHERWISE
GPS	GLOBAL POSITIONING SYSTEM	UMTS	UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
GND	GROUND	UPS	UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
GSM	GLOBAL SYSTEM FOR MOBILE	VIF	VERIFIED IN FIELD
HDG	HOT DIPPED GALVANIZED	W	WIDE
HDR	HEADER	W/	WITH
HGR	HANGER	WD	WOOD
HVAC	HEAT/VENTILATION/AIR CONDITIONING	WP	WEATHERPROOF
HT	HEIGHT	WT	WEIGHT
IGR	INTERIOR GROUND RING		


**ABBREVIATIONS**



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Frederick

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
LEGEND AND ABBREVIATIONS

SHEET NUMBER

**GN-1**

**SITE ACTIVITY REQUIREMENTS:**

1. NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
2. "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:  
THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

**GENERAL NOTES:**


1. FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:  
CONTRACTOR: GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION  
CARRIER: DISH Wireless L.L.C.  
TOWER OWNER: TOWER OWNER
2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Frederick

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCL-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
GENERAL NOTES

SHEET NUMBER  
**GN-2**

**CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:**

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:
  - #4 BARS AND SMALLER 40 ksi
  - #5 BARS AND LARGER 60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
  - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
  - CONCRETE EXPOSED TO EARTH OR WEATHER:
    - #6 BARS AND LARGER 2"
    - #5 BARS AND SMALLER 1-1/2"
  - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
    - SLAB AND WALLS 3/4"
    - BEAMS AND COLUMNS 1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

**ELECTRICAL INSTALLATION NOTES:**

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
  - 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
  - 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. TIE WRAPS ARE NOT ALLOWED.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.


16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Jensen

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
GENERAL NOTES

SHEET NUMBER  
**GN-3**

**GROUNDING NOTES:**


1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.



5701 SOUTH SANTA FE DRIVE  
LITTLETON, CO 80120



COA #: PEC.0000738  
421 FAYETTEVILLE ST, SUITE 600  
RALEIGH, NC 27601



DocuSigned by  
Kyle Freemant

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
SEW	MCK	MCK

RFDS REV #: 1

**CONSTRUCTION DOCUMENTS**

SUBMITTALS		
REV	DATE	DESCRIPTION
A	10/13/2021	ISSUED FOR REVIEW
0	03/10/2022	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER  
KHCLC-16938

DISH Wireless L.L.C.  
PROJECT INFORMATION  
BOHVN00156A  
450-478 WEST MAIN STREET  
MERIDEN, CT 06451

SHEET TITLE  
GENERAL NOTES

SHEET NUMBER  
**GN-4**

**Certificate Of Completion**

Envelope Id: 0A6A47CCBED44C5FABB076DAA15823B3

Status: Completed

Subject: Please DocuSign: BOHVN00156A\_FCD\_REV 0\_03.10.2022\_Sealed.pdf

Source Envelope:

Document Pages: 18

Signatures: 18

Envelope Originator:

Certificate Pages: 1

Initials: 0

Tariq Salameh

AutoNav: Enabled

401 Fayetteville St.

Enveloped Stamping: Enabled

Suite 600

Time Zone: (UTC-05:00) Eastern Time (US &amp; Canada)

Raleigh, NC 27601

Tariq.Salameh@kimley-horn.com

IP Address: 208.127.231.172

**Record Tracking**

Status: Original

Holder: Tariq Salameh

Location: DocuSign

3/16/2022 11:12:50 AM

Tariq.Salameh@kimley-horn.com

**Signer Events**


Kyle Freehart

kyle.freehart@kimley-horn.com

Kimley-Horn

Security Level: Email, Account Authentication  
(None)**Signature**

DocuSigned by:



D8BEE252A3804C1...

Signature Adoption: Pre-selected Style

Using IP Address: 208.127.231.172

**Timestamp**

Sent: 3/16/2022 11:14:06 AM

Viewed: 3/16/2022 11:15:24 AM

Signed: 3/16/2022 11:16:35 AM

**Electronic Record and Signature Disclosure:**

Not Offered via DocuSign

**In Person Signer Events****Signature****Timestamp****Editor Delivery Events****Status****Timestamp****Agent Delivery Events****Status****Timestamp****Intermediary Delivery Events****Status****Timestamp****Certified Delivery Events****Status****Timestamp****Carbon Copy Events****Status****Timestamp****Witness Events****Signature****Timestamp****Notary Events****Signature****Timestamp****Envelope Summary Events****Status****Timestamps**

Envelope Sent

Hashed/Encrypted

3/16/2022 11:14:06 AM

Certified Delivered

Security Checked

3/16/2022 11:15:24 AM

Signing Complete

Security Checked

3/16/2022 11:16:35 AM

Completed

Security Checked

3/16/2022 11:16:35 AM

**Payment Events****Status****Timestamps**

# Exhibit D

## **Structural Analysis Report**

Date: July 20, 2021



B+T Group  
1717 S. Boulder, Suite 300  
Tulsa, OK 74119  
(918) 587-4630

**Subject:** Structural Analysis Report

**Carrier Designation:** DISH Network Co-Locate  
**Site Number:** BOHVN00156A  
**Site Name:** CT-CCI-T-842869

**Crown Castle Designation:** BU Number: 842869  
**Site Name:** Meriden West Central  
**JDE Job Number:** 645144  
**Work Order Number:** 1966209  
**Order Number:** 553374 Rev. 0

**Engineering Firm Designation:** B+T Group Project Number: 92699.007.01

**Site Data:** 450-478 West Main Street, Meriden, New Haven County, CT  
Latitude 41° 32' 24.11", Longitude -72° 49' 8.47"  
100 Foot - Monopole Tower

B+T Group is pleased to submit this “**Structural Analysis Report**” to determine the structural integrity of the above-mentioned tower.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Proposed Equipment Configuration

**Sufficient Capacity - 54.9%**

This analysis utilizes an ultimate 3-second gust wind speed of 125 mph as required by the 2018 Connecticut State Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Structural analysis prepared by: Carly Smith

Respectfully submitted by: B+T Engineering, Inc.  
COA: PEC.0001564; Expires: 2/10/2022



Chad E. Tuttle, P.E.



## TABLE OF CONTENTS

### 1) INTRODUCTION

### 2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Configuration

Table 2 - Other Considered Equipment

### 3) ANALYSIS PROCEDURE

Table 3 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

### 4) ANALYSIS RESULTS

Table 4 - Section Capacity (Summary)

Table 5 - Tower Component Stresses vs. Capacity - LC7

4.1) Recommendations

### 5) APPENDIX A

tnxTower Output

### 6) APPENDIX B

Base Level Drawing

### 7) APPENDIX C

Additional Calculations

## 1) INTRODUCTION

This tower is a 100 ft. Monopole tower designed by Glen Martin Engineering, Inc.

## 2) ANALYSIS CRITERIA

<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Wind Speed:</b>	125 mph
<b>Exposure Category:</b>	B
<b>Topographic Factor:</b>	1
<b>Ice Thickness:</b>	1.5 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Service Wind Speed:</b>	60 mph

**Table 1 - Proposed Equipment Configuration**

Mounting Level (ft.)	Center Line Elevation (ft.)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
55.0	55.0	3	Fujitsu	TA08025-B604	1	1-3/8
		3	Fujitsu	TA08025-B605		
		3	JMA Wireless	MX08FRO665-21		
		1	Raycap	RDIDC-9181-PF-48		
		1	Commscope	MC-PK8-DSH		

**Table 2 - Other Considered Equipment**

Mounting Level (ft.)	Center Line Elevation (ft.)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	
100.0	112.0	1	Decibel	ASP-3711	6 6 8 2	1-1/4 3/4 1/2 3/8	
	106.0	3	Decibel	DB201-A			
		1	KMW Comm.	HB-X-AW-19-65-00T			
	103.0	3	Kathrein	80010965			
	100.0	100.0	3	CCI Antennas			DTMABP7819VG12A
			3	CCI Antennas			OPA-65R-LCUU-H6
			3	Ericsson			RRUS 11
			3	Ericsson			RRUS 32
			3	Ericsson			RRUS 32 B2
			3	Ericsson			RRUS 32 B66
			3	Ericsson			RRUS 4478 B14
			3	KMW Comm.			AM-X-CD-16-65-00T-RET
			3	Quintel Tech.			QS66512-2
			1	Raycap			DC6-48-60-0-8F
	2	Raycap	DC6-48-60-18-8F				
1	--	Platform Mount [LP 1302-1]					
97.0	4	Decibel	DB432-A				
86.0	90.0	3	Ericsson	AIR -32 B2A/B66AA	4	1-5/8	
		3	Ericsson	AIR6449 B41	6	7/8	

Mounting Level (ft.)	Center Line Elevation (ft.)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
		3	Ericsson	ERICSSON AIR 21 B2A B4P		
		3	Ericsson	KRY 112 144/1		
		3	Ericsson	RADIO 4449 B71 B85A_T-MOBILE		
		3	Ericsson	RRUS 4415 B25		
		3	RFS Celwave	APXVAARR24_43-U-NA20		
		86.0	1	--		
78.0	80.0	3	Alcatel Lucent	1900MHz RRH	--	--
		3	Alcatel Lucent	800 EXTERNAL NOTCH FILTER		
		3	Alcatel Lucent	TME-800MHZ RRH		
	78.0	1	--	Side Arm Mount [SO 104-3]		
76.0	79.0	3	Alcatel Lucent	TD-RRH8x20-25	3 1 1	1-1/4 3/4 5/8
		3	RFS Celwave	APXVSP18-C-A20		
		3	RFS Celwave	APXVTM14-C-120		
	76.0	1	--	Platform Mount [LP 303-1]		
65.0	65.0	3	Antel	BXA-70063/6CF	2	1-5/8
		6	JMA Wireless	MX06FRO660-03		
		2	RFS Celwave	DB-T1-6Z-8AB-0Z		
		3	Samsung Telecom.	RFV01U-D1A		
		3	Samsung Telecom.	RFV01U-D2A		
		3	VZW	Sub6 Antenna - VZS01		
		3	JMA Wireless	91900314-02 Dual Bracket		
		1	Site Pro 1	VZWSMART-PLK1 Support Rail Kit		
		1	--	Platform Mount [LP 303-1]		

### 3) ANALYSIS PROCEDURE

**Table 3 - Documents Provided**

Document	Reference	Source
Tower Manufacturer Drawing	4713237	CCI Sites
Foundation Drawings	4529387	CCI Sites
Geotech Report	4529388	CCI Sites
Crown CAD Package	Date: 07/09/2021	CCI Sites

#### 3.1) Analysis Method

tnxTower (version 8.1.1.0), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A. When applicable, Crown Castle has calculated and provided the effective area for panel antennas using approved methods following the intent of the TIA-222 standard.

**3.2) Assumptions**

- 1) The tower and structures were maintained in accordance with the - TIA-222 standard.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.

This analysis may be affected if any assumptions are not valid or have been made in error. B+T Group should be notified to determine the effect on the structural integrity of the tower.

**4) ANALYSIS RESULTS**

**Table 4 - Section Capacity (Summary)**

Section No.	Elevation (ft.)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	100 - 47	Pole	TP40.72x28x0.313	1	-27.883	2386.104	29.0	Pass
L2	47 - 0	Pole	TP51.37x38.655x0.375	2	-42.968	3747.093	43.3	Pass
							Summary	
						Pole (L2)	43.3	Pass
						Rating =	43.3	Pass

**Table 5 - Tower Component Stresses vs. Capacity - LC7**

Notes	Component	Elevation (ft.)	% Capacity	Pass / Fail
1,2	Anchor Rods	Base	35.6	Pass
1,2	Base Plate	Base	28.9	Pass
1,2	Base Foundation (Structure)	Base	21.2	Pass
1,2	Base Foundation (Soil Interaction)	Base	54.9	Pass

<b>Structure Rating (max from all components) =</b>	<b>54.9%</b>
---	--------------

Notes:


- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.
- 2) Rating per TIA-222-H Section 15.5.

**4.1) Recommendations**

The tower and its foundations have sufficient capacity to carry the proposed load configuration. No modifications are required at this time.

**APPENDIX A**  
**TNXTOWER OUTPUT**

Section	1	2
Length (ft)	53.000	53.000
Number of Sides	16	16
Thickness (in)	0.313	0.375
Socket Length (ft)	6.000	36.665
Top Dia (in)	28.000	51.370
Bot Dia (in)	40.720	
Grade	A572-65	A572-65
Weight (K)	6.1	9.6
		15.8




### MATERIAL STRENGTH


GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

### TOWER DESIGN NOTES

1. Tower is located in New Haven County, Connecticut.
2. Tower designed for Exposure B to the TIA-222-H Standard.
3. Tower designed for a 125 mph basic wind in accordance with the TIA-222-H Standard.
4. Tower is also designed for a 50 mph basic wind with 1.50 in ice. Ice is considered to increase in thickness with height.
5. Deflections are based upon a 60 mph wind.
6. Tower Risk Category II.
7. Topographic Category 1 with Crest Height of 0.000 ft
8. TIA-222-H Annex S
9. TOWER RATING: 43.2%



ALL REACTIONS  
ARE FACTORED





 <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job: 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 84286)</b>		
	Project: Client: Crown Castle Code: TIA-222-H Path:	Drawn by: Sampath Date: 07/17/21	App'd: Scale: NTS Dwg No. E-1


Vx Vz

Mx Mz



 <p><b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630</p>	Job: 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 84286)		
	Project:		
	Client: Crown Castle	Drawn by: Sampath	App'd:
	Code: TIA-222-H	Date: 07/17/21	Scale: NTS
	Path:	Dwg No. E-4	




	<b>B+T Group</b>		
	1717 S. Boulder, Suite 300		
	Tulsa, OK 74119		
	Phone: (918) 587-4630 FAX: (918) 587-4630		
Job: <b>92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 84286)</b>			
Project:		Drawn by: Sampath	App'd:
Client: Crown Castle		Date: 07/17/21	Scale: NTS
Code: TIA-222-H		Dwg No. E-5	
Path:			



# Feed Line Distribution Chart

## 0' - 100'

— Round   
 — Flat   
 — App In Face   
 — App Out Face   
 — Truss Leg



<p><b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630</p>	Job: <b>92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 84286)</b>		
	Project: _____		
	Client: <b>Crown Castle</b>	Drawn by: <b>Sampath</b>	App'd: _____
	Code: <b>TIA-222-H</b>	Date: <b>07/17/21</b>	Scale: <b>NTS</b>
	Path: _____	Dwg No. <b>E-7</b>	

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 1 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

## Tower Input Data

The tower is a monopole.

This tower is designed using the TIA-222-H standard.

The following design criteria apply:

Tower is located in New Haven County, Connecticut.

Tower base elevation above sea level: 165.000 ft.

Basic wind speed of 125 mph.

Risk Category II.

Exposure Category B.

Simplified Topographic Factor Procedure for wind speed-up calculations is used.

Topographic Category: 1.

Crest Height: 0.000 ft.

Nominal ice thickness of 1.500 in.

Ice thickness is considered to increase with height.

Ice density of 56.000 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50.000 °F.

Deflections calculated using a wind speed of 60 mph.

TIA-222-H Annex S.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.

Tower analysis based on target reliabilities in accordance with Annex S.

Load Modification Factors used:  $K_{es}(F_w) = 0.95$ ,  $K_{es}(t_i) = 0.85$ .

Maximum demand-capacity ratio is: 1.05.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

## Options

Consider Moments - Legs	Distribute Leg Loads As Uniform	Use ASCE 10 X-Brace Ly Rules
Consider Moments - Horizontals	Assume Legs Pinned	Calculate Redundant Bracing Forces
Consider Moments - Diagonals	√ Assume Rigid Index Plate	Ignore Redundant Members in FEA
Use Moment Magnification	√ Use Clear Spans For Wind Area	SR Leg Bolts Resist Compression
√ Use Code Stress Ratios	Use Clear Spans For KL/r	All Leg Panels Have Same Allowable
√ Use Code Safety Factors - Guys	Retension Guys To Initial Tension	Offset Girt At Foundation
Escalate Ice	√ Bypass Mast Stability Checks	√ Consider Feed Line Torque
Always Use Max Kz	√ Use Azimuth Dish Coefficients	Include Angle Block Shear Check
Use Special Wind Profile	√ Project Wind Area of Appurt.	Use TIA-222-H Bracing Resist. Exemption
Include Bolts In Member Capacity	Autocalc Torque Arm Areas	Use TIA-222-H Tension Splice Exemption
Leg Bolts Are At Top Of Section	Add IBC .6D+W Combination	Poles
Secondary Horizontal Braces Leg	Sort Capacity Reports By Component	√ Include Shear-Torsion Interaction
Use Diamond Inner Bracing (4 Sided)	Triangulate Diamond Inner Bracing	Always Use Sub-Critical Flow
SR Members Have Cut Ends	Treat Feed Line Bundles As Cylinder	Use Top Mounted Sockets
SR Members Are Concentric	Ignore KL/ry For 60 Deg. Angle Legs	Pole Without Linear Attachments
		Pole With Shroud Or No Appurtenances
		Outside and Inside Corner Radii Are
		Known

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 2 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

### Tapered Pole Section Geometry

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L1	100.000-47.000	53.000	6.000	16	28.000	40.720	0.313	1.250	A572-65 (65 ksi)
L2	47.000-0.000	53.000		16	38.655	51.370	0.375	1.500	A572-65 (65 ksi)

### Tapered Pole Properties

Section	Tip Dia. in	Area in <sup>2</sup>	I in <sup>4</sup>	r in	C in	I/C in <sup>3</sup>	J in <sup>4</sup>	Iu/Q in <sup>2</sup>	w in	w/t
L1	28.487	27.601	2673.045	9.857	14.280	187.188	5386.564	13.647	4.950	15.84
	41.457	40.281	8308.852	14.385	20.767	400.095	16743.510	19.917	7.481	23.94
L2	40.806	45.792	8477.194	13.628	19.714	430.008	17082.742	22.642	6.946	18.523
	52.303	61.003	20040.987	18.154	26.199	764.961	40385.419	30.163	9.476	25.27

Tower Elevation ft	Gusset Area ft <sup>2</sup> (per face)	Gusset Thickness in	Gusset Grade	Adjust. Factor A <sub>f</sub>	Adjust. Factor A <sub>r</sub>	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals in	Double Angle Stitch Bolt Spacing Horizontal in	Double Angle Stitch Bolt Spacing Redundants in
L1 100.000-47.000				1	1	1			
L2 47.000-0.000				1	1	1			

### Feed Line/Linear Appurtenances - Entered As Round Or Flat

Description	Sector	Exclude From Torque Calculation	Component Type	Placement ft	Total Number	Number Per Row	Start/End Position	Width or Diameter in	Perimeter in	Weight klf
* MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	A	No	Surface Ar (CaAa)	65.000 - 0.000	2	2	-0.450 - -0.360	1.625		0.001
* CU12PSM9P8XXX(1-3/8)	C	No	Surface Ar (CaAa)	55.000 - 0.000	1	1	-0.400 - -0.370	1.411		0.002
* *										

### Feed Line/Linear Appurtenances - Entered As Area



<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 4 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

### Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	$A_R$ ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$C_{AA}$ In Face ft <sup>2</sup>	$C_{AA}$ Out Face ft <sup>2</sup>	Weight K
L1	100.000-47.000	A	0.000	0.000	5.850	0.000	0.961
		B	0.000	0.000	0.000	0.000	0.108
		C	0.000	0.000	1.129	0.000	0.361
L2	47.000-0.000	A	0.000	0.000	15.275	0.000	0.919
		B	0.000	0.000	0.000	0.000	0.174
		C	0.000	0.000	6.632	0.000	0.497

### Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	$A_R$ ft <sup>2</sup>	$A_F$ ft <sup>2</sup>	$C_{AA}$ In Face ft <sup>2</sup>	$C_{AA}$ Out Face ft <sup>2</sup>	Weight K
L1	100.000-47.000	A	1.380	0.000	0.000	13.520	0.000	1.087
		B		0.000	0.000	0.000	0.000	0.108
		C		0.000	0.000	3.336	0.000	0.399
L2	47.000-0.000	A	1.229	0.000	0.000	35.303	0.000	1.249
		B		0.000	0.000	0.000	0.000	0.174
		C		0.000	0.000	19.599	0.000	0.718

### Feed Line Center of Pressure

Section	Elevation ft	$CP_x$ in	$CP_z$ in	$CP_x$ Ice in	$CP_z$ Ice in
L1	100.000-47.000	-0.770	0.436	-0.917	0.592
L2	47.000-0.000	-1.449	1.409	-1.475	1.885

Note: For pole sections, center of pressure calculations do not consider feed line shielding.

### Shielding Factor Ka

Tower Section	Feed Line Record No.	Description	Feed Line Segment Elev.	$K_a$ No Ice	$K_a$ Ice
L1	18	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	47.00 - 65.00	1.0000	1.0000
L1	20	CU12PSM9P8XXX(1-3/8)	47.00 - 55.00	1.0000	1.0000
L2	18	MLE HYBRID 9POWER/18FIBER RL 2(1-5/8)	0.00 - 47.00	1.0000	1.0000
L2	20	CU12PSM9P8XXX(1-3/8)	0.00 - 47.00	1.0000	1.0000

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 5 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

## Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>1</sub> Front	C <sub>A</sub> A <sub>1</sub> Side	Weight	
			Horz Lateral	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
Lightning Rod 1/2" x 8'	C	From Leg	4.000	0.000	0.000	100.000	No Ice	0.400	0.400	0.030
			0.000				1/2" Ice	1.212	1.212	0.035
			0.000				1" Ice	2.042	2.042	0.045
			4.000				2" Ice	3.557	3.557	0.081
* AM-X-CD-16-65-00T-RET	A	From Leg	4.000	0.000	0.000	100.000	No Ice	4.690	2.340	0.049
			0.000				1/2" Ice	5.150	2.770	0.095
			0.000				1" Ice	5.610	3.200	0.148
							2" Ice	6.570	4.100	0.272
AM-X-CD-16-65-00T-RET	B	From Leg	4.000	0.000	0.000	100.000	No Ice	4.690	2.340	0.049
			0.000				1/2" Ice	5.150	2.770	0.095
			0.000				1" Ice	5.610	3.200	0.148
							2" Ice	6.570	4.100	0.272
AM-X-CD-16-65-00T-RET	C	From Leg	4.000	0.000	0.000	100.000	No Ice	4.690	2.340	0.049
			0.000				1/2" Ice	5.150	2.770	0.095
			0.000				1" Ice	5.610	3.200	0.148
							2" Ice	6.570	4.100	0.272
OPA-65R-LCUU-H6	A	From Leg	4.000	0.000	0.000	100.000	No Ice	9.200	4.630	0.080
			0.000				1/2" Ice	9.970	5.340	0.137
			0.000				1" Ice	10.760	6.070	0.200
							2" Ice	12.390	7.570	0.347
OPA-65R-LCUU-H6	B	From Leg	4.000	0.000	0.000	100.000	No Ice	9.200	4.630	0.080
			0.000				1/2" Ice	9.970	5.340	0.137
			0.000				1" Ice	10.760	6.070	0.200
							2" Ice	12.390	7.570	0.347
OPA-65R-LCUU-H6	C	From Leg	4.000	0.000	0.000	100.000	No Ice	9.200	4.630	0.080
			0.000				1/2" Ice	9.970	5.340	0.137
			0.000				1" Ice	10.760	6.070	0.200
							2" Ice	12.390	7.570	0.347
80010965	A	From Leg	4.000	0.000	0.000	100.000	No Ice	12.230	4.210	0.109
			0.000				1/2" Ice	13.000	4.880	0.185
			3.000				1" Ice	13.790	5.570	0.269
							2" Ice	15.410	6.990	0.458
80010965	B	From Leg	4.000	0.000	0.000	100.000	No Ice	12.230	4.210	0.109
			0.000				1/2" Ice	13.000	4.880	0.185
			3.000				1" Ice	13.790	5.570	0.269
							2" Ice	15.410	6.990	0.458
80010965	C	From Leg	4.000	0.000	0.000	100.000	No Ice	12.230	4.210	0.109
			0.000				1/2" Ice	13.000	4.880	0.185
			3.000				1" Ice	13.790	5.570	0.269
							2" Ice	15.410	6.990	0.458
QS66512-2	A	From Leg	4.000	0.000	0.000	100.000	No Ice	4.010	3.370	0.111
			0.000				1/2" Ice	4.410	3.760	0.168
			0.000				1" Ice	4.810	4.150	0.232
							2" Ice	5.650	4.970	0.378
QS66512-2	B	From Leg	4.000	0.000	0.000	100.000	No Ice	4.010	3.370	0.111
			0.000				1/2" Ice	4.410	3.760	0.168
			0.000				1" Ice	4.810	4.150	0.232
							2" Ice	5.650	4.970	0.378

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		<b>Page</b>		6 of 21	
	<b>Project</b>				<b>Date</b>		19:35:35 07/17/21	
	<b>Client</b>		Crown Castle		<b>Designed by</b>		Sampath	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>1</sub> Front	C <sub>A</sub> A <sub>2</sub> Side	Weight	
			Horz	Lateral						Vert
QS66512-2	C	From Leg	4.000	0.000	0.000	100.000	No Ice	4.010	3.370	0.111
			0.000				1/2" Ice	4.410	3.760	0.168
			0.000				1" Ice	4.810	4.150	0.232
							2" Ice	5.650	4.970	0.378
HB-X-AW-19-65-00T	A	From Leg	4.000	0.000	0.000	100.000	No Ice	2.083	2.083	0.029
			0.000				1/2" Ice	3.175	3.175	0.055
			6.000				1" Ice	3.561	3.561	0.085
							2" Ice	4.361	4.361	0.159
ASP-3711	A	From Leg	4.000	0.000	0.000	100.000	No Ice	1.300	1.300	0.013
			0.000				1/2" Ice	2.340	2.340	0.017
			12.000				1" Ice	3.380	3.380	0.021
							2" Ice	5.460	5.460	0.029
DB201-A	A	From Leg	4.000	0.000	0.000	100.000	No Ice	1.100	1.100	0.025
			0.000				1/2" Ice	1.980	1.980	0.033
			6.000				1" Ice	2.860	2.860	0.040
							2" Ice	4.620	4.620	0.055
DB201-A	B	From Leg	4.000	0.000	0.000	100.000	No Ice	1.100	1.100	0.025
			0.000				1/2" Ice	1.980	1.980	0.033
			6.000				1" Ice	2.860	2.860	0.040
							2" Ice	4.620	4.620	0.055
DB201-A	C	From Leg	4.000	0.000	0.000	100.000	No Ice	1.100	1.100	0.025
			0.000				1/2" Ice	1.980	1.980	0.033
			6.000				1" Ice	2.860	2.860	0.040
							2" Ice	4.620	4.620	0.055
(2) DB432-A	B	From Leg	4.000	0.000	0.000	100.000	No Ice	0.300	0.300	0.005
			0.000				1/2" Ice	0.540	0.540	0.006
			-3.000				1" Ice	0.780	0.780	0.008
							2" Ice	1.260	1.260	0.011
(2) DB432-A	C	From Leg	4.000	0.000	0.000	100.000	No Ice	0.300	0.300	0.005
			0.000				1/2" Ice	0.540	0.540	0.006
			-3.000				1" Ice	0.780	0.780	0.008
							2" Ice	1.260	1.260	0.011
DTMABP7819VG12A	A	From Leg	4.000	0.000	0.000	100.000	No Ice	0.976	0.339	0.019
			0.000				1/2" Ice	1.100	0.419	0.026
			0.000				1" Ice	1.232	0.510	0.036
							2" Ice	1.517	0.714	0.060
DTMABP7819VG12A	B	From Leg	4.000	0.000	0.000	100.000	No Ice	0.976	0.339	0.019
			0.000				1/2" Ice	1.100	0.419	0.026
			0.000				1" Ice	1.232	0.510	0.036
							2" Ice	1.517	0.714	0.060
DTMABP7819VG12A	C	From Leg	4.000	0.000	0.000	100.000	No Ice	0.976	0.339	0.019
			0.000				1/2" Ice	1.100	0.419	0.026
			0.000				1" Ice	1.232	0.510	0.036
							2" Ice	1.517	0.714	0.060
RRUS 32	A	From Leg	4.000	0.000	0.000	100.000	No Ice	2.857	1.777	0.055
			0.000				1/2" Ice	3.083	1.968	0.077
			0.000				1" Ice	3.316	2.166	0.103
							2" Ice	3.805	2.583	0.165
RRUS 32	B	From Leg	4.000	0.000	0.000	100.000	No Ice	2.857	1.777	0.055
			0.000				1/2" Ice	3.083	1.968	0.077
			0.000				1" Ice	3.316	2.166	0.103
							2" Ice	3.805	2.583	0.165
RRUS 32	C	From Leg	4.000	0.000	0.000	100.000	No Ice	2.857	1.777	0.055
			0.000				1/2" Ice	3.083	1.968	0.077
			0.000				1" Ice	3.316	2.166	0.103
							2" Ice	3.805	2.583	0.165
(2) DC6-48-60-18-8F	A	From Leg	4.000	0.000	0.000	100.000	No Ice	1.212	1.212	0.033

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		<b>Page</b>	
	92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		7 of 21	
	<b>Project</b>		<b>Date</b>	
		19:35:35 07/17/21		
<b>Client</b>		<b>Designed by</b>		
Crown Castle		Sampath		

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>1</sub> Front	C <sub>A</sub> A <sub>1</sub> Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
			0.000			1/2" Ice	1.892	1.892	0.055
			0.000			1" Ice	2.105	2.105	0.080
						2" Ice	2.570	2.570	0.138
RRUS 4478 B14	A	From Leg	4.000	0.000	100.000	No Ice	1.843	1.059	0.060
			0.000			1/2" Ice	2.012	1.197	0.076
			0.000			1" Ice	2.190	1.342	0.094
						2" Ice	2.566	1.656	0.140
RRUS 4478 B14	B	From Leg	4.000	0.000	100.000	No Ice	1.843	1.059	0.060
			0.000			1/2" Ice	2.012	1.197	0.076
			0.000			1" Ice	2.190	1.342	0.094
						2" Ice	2.566	1.656	0.140
RRUS 4478 B14	C	From Leg	4.000	0.000	100.000	No Ice	1.843	1.059	0.060
			0.000			1/2" Ice	2.012	1.197	0.076
			0.000			1" Ice	2.190	1.342	0.094
						2" Ice	2.566	1.656	0.140
RRUS 32 B66	A	From Leg	4.000	0.000	100.000	No Ice	2.743	1.668	0.053
			0.000			1/2" Ice	2.965	1.855	0.074
			0.000			1" Ice	3.194	2.049	0.098
						2" Ice	3.675	2.458	0.157
RRUS 32 B66	B	From Leg	4.000	0.000	100.000	No Ice	2.743	1.668	0.053
			0.000			1/2" Ice	2.965	1.855	0.074
			0.000			1" Ice	3.194	2.049	0.098
						2" Ice	3.675	2.458	0.157
RRUS 32 B66	C	From Leg	4.000	0.000	100.000	No Ice	2.743	1.668	0.053
			0.000			1/2" Ice	2.965	1.855	0.074
			0.000			1" Ice	3.194	2.049	0.098
						2" Ice	3.675	2.458	0.157
DC6-48-60-0-8F	A	From Leg	4.000	0.000	100.000	No Ice	0.917	0.917	0.033
			0.000			1/2" Ice	1.458	1.458	0.051
			0.000			1" Ice	1.643	1.643	0.071
						2" Ice	2.042	2.042	0.119
RRUS 11	A	From Leg	4.000	0.000	100.000	No Ice	2.784	1.187	0.048
			0.000			1/2" Ice	2.992	1.334	0.068
			0.000			1" Ice	3.207	1.490	0.092
						2" Ice	3.658	1.833	0.150
RRUS 11	B	From Leg	4.000	0.000	100.000	No Ice	2.784	1.187	0.048
			0.000			1/2" Ice	2.992	1.334	0.068
			0.000			1" Ice	3.207	1.490	0.092
						2" Ice	3.658	1.833	0.150
RRUS 11	C	From Leg	4.000	0.000	100.000	No Ice	2.784	1.187	0.048
			0.000			1/2" Ice	2.992	1.334	0.068
			0.000			1" Ice	3.207	1.490	0.092
						2" Ice	3.658	1.833	0.150
RRUS 32 B2	A	From Leg	4.000	0.000	100.000	No Ice	2.731	1.668	0.053
			0.000			1/2" Ice	2.953	1.855	0.074
			0.000			1" Ice	3.182	2.049	0.098
						2" Ice	3.663	2.458	0.157
RRUS 32 B2	B	From Leg	4.000	0.000	100.000	No Ice	2.731	1.668	0.053
			0.000			1/2" Ice	2.953	1.855	0.074
			0.000			1" Ice	3.182	2.049	0.098
						2" Ice	3.663	2.458	0.157
RRUS 32 B2	C	From Leg	4.000	0.000	100.000	No Ice	2.731	1.668	0.053
			0.000			1/2" Ice	2.953	1.855	0.074
			0.000			1" Ice	3.182	2.049	0.098
						2" Ice	3.663	2.458	0.157
Platform Mount [LP 1302-1]	C	None		0.000	100.000	No Ice	56.400	56.400	2.413
						1/2" Ice	67.500	67.500	3.131



<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		<b>Page</b>	
	92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		8 of 21	
	<b>Project</b>		<b>Date</b>	
		19:35:35 07/17/21		
<b>Client</b>		<b>Designed by</b>		
Crown Castle		Sampath		

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>1</sub> Front	C <sub>A</sub> A <sub>1</sub> Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
							1" Ice	78.600	78.600	3.849
							2" Ice	100.800	100.800	5.285
*										
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	A	From Leg	4.000	0.000	86.000	No Ice	3.140	2.590	0.112	
			0.000			1/2" Ice	3.450	2.880	0.164	
			4.000			1" Ice	3.770	3.190	0.225	
						2" Ice	4.430	3.840	0.375	
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	B	From Leg	4.000	0.000	86.000	No Ice	3.140	2.590	0.112	
			0.000			1/2" Ice	3.450	2.880	0.164	
			4.000			1" Ice	3.770	3.190	0.225	
						2" Ice	4.430	3.840	0.375	
ERICSSON AIR 21 B2A B4P w/ Mount Pipe	C	From Leg	4.000	0.000	86.000	No Ice	3.140	2.590	0.112	
			0.000			1/2" Ice	3.450	2.880	0.164	
			4.000			1" Ice	3.770	3.190	0.225	
						2" Ice	4.430	3.840	0.375	
AIR -32 B2A/B66AA w/ Mount Pipe	A	From Leg	4.000	0.000	86.000	No Ice	3.760	3.150	0.194	
			0.000			1/2" Ice	4.120	3.490	0.252	
			4.000			1" Ice	4.480	3.840	0.320	
						2" Ice	5.240	4.580	0.485	
AIR -32 B2A/B66AA w/ Mount Pipe	B	From Leg	4.000	0.000	86.000	No Ice	3.760	3.150	0.194	
			0.000			1/2" Ice	4.120	3.490	0.252	
			4.000			1" Ice	4.480	3.840	0.320	
						2" Ice	5.240	4.580	0.485	
AIR -32 B2A/B66AA w/ Mount Pipe	C	From Leg	4.000	0.000	86.000	No Ice	3.760	3.150	0.194	
			0.000			1/2" Ice	4.120	3.490	0.252	
			4.000			1" Ice	4.480	3.840	0.320	
						2" Ice	5.240	4.580	0.485	
(3) KRY 112 144/1	A	From Leg	4.000	0.000	86.000	No Ice	0.350	0.175	0.011	
			0.000			1/2" Ice	0.426	0.234	0.014	
			4.000			1" Ice	0.509	0.301	0.019	
						2" Ice	0.698	0.456	0.032	
AIR6449 B41 w/ Mount Pipe	A	From Leg	4.000	0.000	86.000	No Ice	5.180	2.720	0.118	
			0.000			1/2" Ice	5.590	3.050	0.164	
			4.000			1" Ice	6.010	3.390	0.216	
						2" Ice	6.900	4.130	0.344	
AIR6449 B41 w/ Mount Pipe	B	From Leg	4.000	0.000	86.000	No Ice	5.180	2.720	0.118	
			0.000			1/2" Ice	5.590	3.050	0.164	
			4.000			1" Ice	6.010	3.390	0.216	
						2" Ice	6.900	4.130	0.344	
AIR6449 B41 w/ Mount Pipe	C	From Leg	4.000	0.000	86.000	No Ice	5.180	2.720	0.118	
			0.000			1/2" Ice	5.590	3.050	0.164	
			4.000			1" Ice	6.010	3.390	0.216	
						2" Ice	6.900	4.130	0.344	
APXVAARR24_43-U-NA20 w/ Mount Pipe	A	From Leg	4.000	0.000	86.000	No Ice	14.690	6.870	0.186	
			0.000			1/2" Ice	15.460	7.550	0.315	
			4.000			1" Ice	16.230	8.250	0.458	
						2" Ice	17.820	9.670	0.788	
APXVAARR24_43-U-NA20 w/ Mount Pipe	B	From Leg	4.000	0.000	86.000	No Ice	14.690	6.870	0.186	
			0.000			1/2" Ice	15.460	7.550	0.315	
			4.000			1" Ice	16.230	8.250	0.458	
						2" Ice	17.820	9.670	0.788	
APXVAARR24_43-U-NA20 w/ Mount Pipe	C	From Leg	4.000	0.000	86.000	No Ice	14.690	6.870	0.186	
			0.000			1/2" Ice	15.460	7.550	0.315	
			4.000			1" Ice	16.230	8.250	0.458	
						2" Ice	17.820	9.670	0.788	
RADIO 4449 B71 B85A_T-MOBILE	A	From Leg	4.000	0.000	86.000	No Ice	1.970	1.587	0.073	
			0.000			1/2" Ice	2.147	1.749	0.093	

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		<b>Page</b>	
	92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		9 of 21	
	<b>Project</b>		<b>Date</b>	
		19:35:35 07/17/21		
<b>Client</b>		<b>Designed by</b>		
Crown Castle		Sampath		

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>1</sub> Front	C <sub>A</sub> A <sub>1</sub> Side	Weight
			Horz Lateral ft	Vert ft					
				4.000			1" Ice 2.331	1.918	0.116
							2" Ice 2.721	2.280	0.170
RADIO 4449 B71 B85A_T-MOBILE	B	From Leg	4.000	0.000	86.000	No Ice 1.970	1.587	0.073	
			0.000			1/2" Ice 2.147	1.749	0.093	
			4.000			1" Ice 2.331	1.918	0.116	
						2" Ice 2.721	2.280	0.170	
RADIO 4449 B71 B85A_T-MOBILE	C	From Leg	4.000	0.000	86.000	No Ice 1.970	1.587	0.073	
			0.000			1/2" Ice 2.147	1.749	0.093	
			4.000			1" Ice 2.331	1.918	0.116	
						2" Ice 2.721	2.280	0.170	
RRUS 4415 B25	A	From Leg	4.000	0.000	86.000	No Ice 1.644	0.679	0.044	
			0.000			1/2" Ice 1.804	0.791	0.056	
			4.000			1" Ice 1.972	0.913	0.071	
						2" Ice 2.329	1.183	0.109	
RRUS 4415 B25	B	From Leg	4.000	0.000	86.000	No Ice 1.644	0.679	0.044	
			0.000			1/2" Ice 1.804	0.791	0.056	
			4.000			1" Ice 1.972	0.913	0.071	
						2" Ice 2.329	1.183	0.109	
RRUS 4415 B25	C	From Leg	4.000	0.000	86.000	No Ice 1.644	0.679	0.044	
			0.000			1/2" Ice 1.804	0.791	0.056	
			4.000			1" Ice 1.972	0.913	0.071	
						2" Ice 2.329	1.183	0.109	
Platform Mount [LP 305-1_HR-1]	C	None		0.000	86.000	No Ice 19.590	19.590	1.366	
						1/2" Ice 24.480	24.480	1.782	
						1" Ice 29.240	29.240	2.286	
						2" Ice 38.490	38.490	3.562	
*									
TME-800MHZ RRH	A	From Leg	2.000	0.000	78.000	No Ice 2.134	1.773	0.053	
			0.000			1/2" Ice 2.320	1.946	0.074	
			2.000			1" Ice 2.512	2.127	0.098	
						2" Ice 2.920	2.510	0.157	
TME-800MHZ RRH	B	From Leg	2.000	0.000	78.000	No Ice 2.134	1.773	0.053	
			0.000			1/2" Ice 2.320	1.946	0.074	
			2.000			1" Ice 2.512	2.127	0.098	
						2" Ice 2.920	2.510	0.157	
TME-800MHZ RRH	C	From Leg	2.000	0.000	78.000	No Ice 2.134	1.773	0.053	
			0.000			1/2" Ice 2.320	1.946	0.074	
			2.000			1" Ice 2.512	2.127	0.098	
						2" Ice 2.920	2.510	0.157	
1900MHz RRH	A	From Leg	2.000	0.000	78.000	No Ice 2.492	3.258	0.044	
			0.000			1/2" Ice 2.695	3.484	0.075	
			2.000			1" Ice 2.906	3.718	0.110	
						2" Ice 3.351	4.206	0.192	
1900MHz RRH	B	From Leg	2.000	0.000	78.000	No Ice 2.492	3.258	0.044	
			0.000			1/2" Ice 2.695	3.484	0.075	
			2.000			1" Ice 2.906	3.718	0.110	
						2" Ice 3.351	4.206	0.192	
1900MHz RRH	C	From Leg	2.000	0.000	78.000	No Ice 2.492	3.258	0.044	
			0.000			1/2" Ice 2.695	3.484	0.075	
			2.000			1" Ice 2.906	3.718	0.110	
						2" Ice 3.351	4.206	0.192	
800 EXTERNAL NOTCH FILTER	A	From Leg	2.000	0.000	78.000	No Ice 0.660	0.289	0.011	
			0.000			1/2" Ice 0.763	0.364	0.017	
			2.000			1" Ice 0.873	0.446	0.024	
						2" Ice 1.115	0.633	0.044	
800 EXTERNAL NOTCH FILTER	B	From Leg	2.000	0.000	78.000	No Ice 0.660	0.289	0.011	
			0.000			1/2" Ice 0.763	0.364	0.017	

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		<b>Page</b>		10 of 21	
	<b>Project</b>				<b>Date</b>		19:35:35 07/17/21	
	<b>Client</b>		Crown Castle		<b>Designed by</b>		Sampath	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Lateral					
			2.000				1" Ice 0.873	0.446	0.024
							2" Ice 1.115	0.633	0.044
800 EXTERNAL NOTCH FILTER	C	From Leg	2.000	0.000	78.000	No Ice	0.660	0.289	0.011
			0.000			1/2" Ice	0.763	0.364	0.017
			2.000			1" Ice	0.873	0.446	0.024
5' x 4" Std. Pipe	A	From Leg	2.000	0.000	78.000	2" Ice	1.115	0.633	0.044
			0.000			No Ice	1.606	1.606	0.054
			0.000			1/2" Ice	2.076	2.076	0.070
			2.000			1" Ice	2.397	2.397	0.090
5' x 4" Std. Pipe	B	From Leg	2.000	0.000	78.000	2" Ice	3.067	3.067	0.141
			0.000			No Ice	1.606	1.606	0.054
			0.000			1/2" Ice	2.076	2.076	0.070
			2.000			1" Ice	2.397	2.397	0.090
5' x 4" Std. Pipe	C	From Leg	2.000	0.000	78.000	2" Ice	3.067	3.067	0.141
			0.000			No Ice	1.606	1.606	0.054
			0.000			1/2" Ice	2.076	2.076	0.070
			2.000			1" Ice	2.397	2.397	0.090
Side Arm Mount [SO 104-3]	C	None		0.000	78.000	2" Ice	3.067	3.067	0.141
						No Ice	2.620	2.620	0.288
						1/2" Ice	3.300	3.300	0.408
						1" Ice	3.980	3.980	0.528
						2" Ice	5.350	5.350	0.768
*									
(2) APXVSP18-C-A20 w/ Mount Pipe	B	From Leg	4.000	0.000	76.000	No Ice	4.600	4.010	0.095
			0.000			1/2" Ice	5.050	4.450	0.160
			3.000			1" Ice	5.500	4.890	0.235
						2" Ice	6.440	5.820	0.419
APXVSP18-C-A20 w/ Mount Pipe	C	From Leg	4.000	0.000	76.000	No Ice	4.600	4.010	0.095
			0.000			1/2" Ice	5.050	4.450	0.160
			3.000			1" Ice	5.500	4.890	0.235
						2" Ice	6.440	5.820	0.419
(2) APXVTM14-C-120 w/ Mount Pipe	B	From Leg	4.000	0.000	76.000	No Ice	4.090	2.860	0.077
			0.000			1/2" Ice	4.480	3.230	0.127
			3.000			1" Ice	4.880	3.610	0.185
						2" Ice	5.710	4.400	0.331
APXVTM14-C-120 w/ Mount Pipe	C	From Leg	4.000	0.000	76.000	No Ice	4.090	2.860	0.077
			0.000			1/2" Ice	4.480	3.230	0.127
			3.000			1" Ice	4.880	3.610	0.185
						2" Ice	5.710	4.400	0.331
(2) TD-RRH8x20-25	B	From Leg	4.000	0.000	76.000	No Ice	3.704	1.294	0.066
			0.000			1/2" Ice	3.946	1.465	0.090
			3.000			1" Ice	4.196	1.642	0.117
						2" Ice	4.717	2.019	0.183
TD-RRH8x20-25	C	From Leg	4.000	0.000	76.000	No Ice	3.704	1.294	0.066
			0.000			1/2" Ice	3.946	1.465	0.090
			3.000			1" Ice	4.196	1.642	0.117
						2" Ice	4.717	2.019	0.183
(4) 6' x 2" Mount Pipe	A	From Leg	4.000	0.000	76.000	No Ice	1.425	1.425	0.022
			0.000			1/2" Ice	1.925	1.925	0.033
			2.000			1" Ice	2.294	2.294	0.048
						2" Ice	3.060	3.060	0.090
(2) 6' x 2" Mount Pipe	C	From Leg	4.000	0.000	76.000	No Ice	1.425	1.425	0.022
			0.000			1/2" Ice	1.925	1.925	0.033
			2.000			1" Ice	2.294	2.294	0.048
						2" Ice	3.060	3.060	0.090
Platform Mount [LP 303-1]	C	None		0.000	76.000	No Ice	14.690	14.690	1.250
						1/2" Ice	18.010	18.010	1.569

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		<b>Page</b>	
	92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		11 of 21	
	<b>Project</b>		<b>Date</b>	
		19:35:35 07/17/21		
<b>Client</b>		<b>Designed by</b>		
Crown Castle		Sampath		

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>1</sub> Front	C <sub>A</sub> A <sub>1</sub> Side	Weight	
			Horz	Vert						
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K	
						1" Ice	21.340	21.340	1.942	
						2" Ice	28.080	28.080	2.852	
*										
BXA-70063/6CF w/ Mount Pipe	A	From Leg	4.000	0.000	0.000	65.000	No Ice	7.340	5.510	0.058
			0.000				1/2" Ice	8.080	6.220	0.115
			0.000				1" Ice	8.830	6.940	0.183
							2" Ice	10.380	8.440	0.351
BXA-70063/6CF w/ Mount Pipe	B	From Leg	4.000	0.000	0.000	65.000	No Ice	7.340	5.510	0.058
			0.000				1/2" Ice	8.080	6.220	0.115
			0.000				1" Ice	8.830	6.940	0.183
							2" Ice	10.380	8.440	0.351
BXA-70063/6CF w/ Mount Pipe	C	From Leg	4.000	0.000	0.000	65.000	No Ice	7.340	5.510	0.058
			0.000				1/2" Ice	8.080	6.220	0.115
			0.000				1" Ice	8.830	6.940	0.183
							2" Ice	10.380	8.440	0.351
(2) DB-T1-6Z-8AB-0Z	C	From Leg	1.000	0.000	0.000	65.000	No Ice	4.800	2.000	0.044
			0.000				1/2" Ice	5.070	2.193	0.080
			0.000				1" Ice	5.348	2.393	0.120
							2" Ice	5.926	2.815	0.213
MX06FRO660-03	A	From Leg	4.000	0.000	0.000	65.000	No Ice	6.810	4.670	0.078
			0.000				1/2" Ice	7.370	5.190	0.147
			0.000				1" Ice	7.930	5.730	0.222
							2" Ice	9.110	6.850	0.393
MX06FRO660-03	B	From Leg	4.000	0.000	0.000	65.000	No Ice	6.810	4.670	0.078
			0.000				1/2" Ice	7.370	5.190	0.147
			0.000				1" Ice	7.930	5.730	0.222
							2" Ice	9.110	6.850	0.393
MX06FRO660-03	C	From Leg	4.000	0.000	0.000	65.000	No Ice	6.810	4.670	0.078
			0.000				1/2" Ice	7.370	5.190	0.147
			0.000				1" Ice	7.930	5.730	0.222
							2" Ice	9.110	6.850	0.393
MX06FRO660-03 w/ Mount Pipe	A	From Leg	4.000	0.000	0.000	65.000	No Ice	6.540	5.550	0.103
			0.000				1/2" Ice	7.060	6.050	0.185
			0.000				1" Ice	7.600	6.570	0.277
							2" Ice	8.700	7.650	0.496
MX06FRO660-03 w/ Mount Pipe	B	From Leg	4.000	0.000	0.000	65.000	No Ice	6.540	5.550	0.103
			0.000				1/2" Ice	7.060	6.050	0.185
			0.000				1" Ice	7.600	6.570	0.277
							2" Ice	8.700	7.650	0.496
MX06FRO660-03 w/ Mount Pipe	C	From Leg	4.000	0.000	0.000	65.000	No Ice	6.540	5.550	0.103
			0.000				1/2" Ice	7.060	6.050	0.185
			0.000				1" Ice	7.600	6.570	0.277
							2" Ice	8.700	7.650	0.496
Sub6 Antenna - VZS01 w/ Mount Pipe	A	From Leg	4.000	0.000	0.000	65.000	No Ice	4.915	2.687	0.101
			0.000				1/2" Ice	5.264	3.151	0.141
			0.000				1" Ice	5.623	3.631	0.186
							2" Ice	6.371	4.639	0.294
Sub6 Antenna - VZS01 w/ Mount Pipe	B	From Leg	4.000	0.000	0.000	65.000	No Ice	4.915	2.687	0.101
			0.000				1/2" Ice	5.264	3.151	0.141
			0.000				1" Ice	5.623	3.631	0.186
							2" Ice	6.371	4.639	0.294
Sub6 Antenna - VZS01 w/ Mount Pipe	C	From Leg	4.000	0.000	0.000	65.000	No Ice	4.915	2.687	0.101
			0.000				1/2" Ice	5.264	3.151	0.141
			0.000				1" Ice	5.623	3.631	0.186
							2" Ice	6.371	4.639	0.294
RFV01U-D1A	A	From Leg	4.000	0.000	0.000	65.000	No Ice	1.875	1.250	0.084
							1/2" Ice	2.045	1.393	0.103

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		<b>Page</b>		12 of 21	
	<b>Project</b>				<b>Date</b>		19:35:35 07/17/21	
	<b>Client</b>		Crown Castle		<b>Designed by</b>		Sampath	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>A</sub> A <sub>1</sub> Front	C <sub>A</sub> A <sub>1</sub> Side	Weight
			Horz	Vert					
			ft	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
			0.000				1" Ice 2.223	1.543	0.124
							2" Ice 2.601	1.865	0.175
RFV01U-D1A	B	From Leg	4.000	0.000	65.000		No Ice 1.875	1.250	0.084
			0.000				1/2" Ice 2.045	1.393	0.103
			0.000				1" Ice 2.223	1.543	0.124
							2" Ice 2.601	1.865	0.175
RFV01U-D1A	C	From Leg	4.000	0.000	65.000		No Ice 1.875	1.250	0.084
			0.000				1/2" Ice 2.045	1.393	0.103
			0.000				1" Ice 2.223	1.543	0.124
							2" Ice 2.601	1.865	0.175
RFV01U-D2A	A	From Leg	4.000	0.000	65.000		No Ice 1.875	1.013	0.070
			0.000				1/2" Ice 2.045	1.145	0.087
			0.000				1" Ice 2.223	1.284	0.106
							2" Ice 2.601	1.585	0.153
RFV01U-D2A	B	From Leg	4.000	0.000	65.000		No Ice 1.875	1.013	0.070
			0.000				1/2" Ice 2.045	1.145	0.087
			0.000				1" Ice 2.223	1.284	0.106
							2" Ice 2.601	1.585	0.153
RFV01U-D2A	C	From Leg	4.000	0.000	65.000		No Ice 1.875	1.013	0.070
			0.000				1/2" Ice 2.045	1.145	0.087
			0.000				1" Ice 2.223	1.284	0.106
							2" Ice 2.601	1.585	0.153
4' x 2.375" Pipe Mount	C	From Leg	1.000	0.000	65.000		No Ice 1.457	1.457	0.022
			0.000				1/2" Ice 1.748	1.748	0.031
			0.000				1" Ice 2.046	2.046	0.044
							2" Ice 2.664	2.664	0.082
8' x 2" Mount Pipe	A	From Leg	4.000	0.000	65.000		No Ice 1.900	1.900	0.029
			0.000				1/2" Ice 2.728	2.728	0.044
			0.000				1" Ice 3.401	3.401	0.063
							2" Ice 4.396	4.396	0.119
8' x 2" Mount Pipe	B	From Leg	4.000	0.000	65.000		No Ice 1.900	1.900	0.029
			0.000				1/2" Ice 2.728	2.728	0.044
			0.000				1" Ice 3.401	3.401	0.063
							2" Ice 4.396	4.396	0.119
8' x 2" Mount Pipe	C	From Leg	4.000	0.000	65.000		No Ice 1.900	1.900	0.029
			0.000				1/2" Ice 2.728	2.728	0.044
			0.000				1" Ice 3.401	3.401	0.063
							2" Ice 4.396	4.396	0.119
(2) Side Arm Mount [SO 102-3]	C	None		0.000	65.000		No Ice 3.600	3.600	0.075
							1/2" Ice 4.180	4.180	0.105
							1" Ice 4.750	4.750	0.135
							2" Ice 5.900	5.900	0.195
Platform Mount [LP 303-1_HR-1]	C	None		0.000	65.000		No Ice 17.090	17.090	1.495
							1/2" Ice 21.470	21.470	1.881
							1" Ice 25.720	25.720	2.346
							2" Ice 33.960	33.960	3.518
*									
MX08FRO665-21 w/ Mount Pipe	A	From Leg	4.000	0.000	55.000		No Ice 8.010	4.230	0.108
			0.000				1/2" Ice 8.520	4.690	0.194
			0.000				1" Ice 9.040	5.160	0.292
							2" Ice 10.110	6.120	0.522
MX08FRO665-21 w/ Mount Pipe	B	From Leg	4.000	0.000	55.000		No Ice 8.010	4.230	0.108
			0.000				1/2" Ice 8.520	4.690	0.194
			0.000				1" Ice 9.040	5.160	0.292
							2" Ice 10.110	6.120	0.522
MX08FRO665-21 w/ Mount Pipe	C	From Leg	4.000	0.000	55.000		No Ice 8.010	4.230	0.108
			0.000				1/2" Ice 8.520	4.690	0.194

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b>		<b>Page</b>	
	92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)		13 of 21	
	<b>Project</b>		<b>Date</b>	
		19:35:35 07/17/21		
<b>Client</b>		<b>Designed by</b>		
Crown Castle		Sampath		

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C <sub>AA</sub> Front	C <sub>AA</sub> Side	Weight
			Horz	Vert					
			Lateral	ft	°	ft	ft <sup>2</sup>	ft <sup>2</sup>	K
			ft	ft					
			0.000			1" Ice	9.040	5.160	0.292
						2" Ice	10.110	6.120	0.522
TA08025-B604	A	From Leg	4.000	0.000	55.000	No Ice	1.964	0.981	0.064
			0.000			1/2" Ice	2.138	1.112	0.081
			0.000			1" Ice	2.320	1.250	0.100
						2" Ice	2.705	1.548	0.148
TA08025-B604	B	From Leg	4.000	0.000	55.000	No Ice	1.964	0.981	0.064
			0.000			1/2" Ice	2.138	1.112	0.081
			0.000			1" Ice	2.320	1.250	0.100
						2" Ice	2.705	1.548	0.148
TA08025-B604	C	From Leg	4.000	0.000	55.000	No Ice	1.964	0.981	0.064
			0.000			1/2" Ice	2.138	1.112	0.081
			0.000			1" Ice	2.320	1.250	0.100
						2" Ice	2.705	1.548	0.148
TA08025-B605	A	From Leg	4.000	0.000	55.000	No Ice	1.964	1.129	0.075
			0.000			1/2" Ice	2.138	1.267	0.093
			0.000			1" Ice	2.320	1.411	0.114
						2" Ice	2.705	1.723	0.164
TA08025-B605	B	From Leg	4.000	0.000	55.000	No Ice	1.964	1.129	0.075
			0.000			1/2" Ice	2.138	1.267	0.093
			0.000			1" Ice	2.320	1.411	0.114
						2" Ice	2.705	1.723	0.164
TA08025-B605	C	From Leg	4.000	0.000	55.000	No Ice	1.964	1.129	0.075
			0.000			1/2" Ice	2.138	1.267	0.093
			0.000			1" Ice	2.320	1.411	0.114
						2" Ice	2.705	1.723	0.164
RDIDC-9181-PF-48	A	From Leg	4.000	0.000	55.000	No Ice	2.012	1.168	0.022
			0.000			1/2" Ice	2.189	1.311	0.040
			0.000			1" Ice	2.373	1.461	0.060
						2" Ice	2.763	1.784	0.110
(2) 8' x 2.375" Mount Pipe	A	From Leg	4.000	0.000	55.000	No Ice	1.900	1.900	0.029
			0.000			1/2" Ice	2.728	2.728	0.044
			0.000			1" Ice	3.401	3.401	0.063
						2" Ice	4.396	4.396	0.119
(2) 8' x 2.375" Mount Pipe	B	From Leg	4.000	0.000	55.000	No Ice	1.900	1.900	0.029
			0.000			1/2" Ice	2.728	2.728	0.044
			0.000			1" Ice	3.401	3.401	0.063
						2" Ice	4.396	4.396	0.119
(2) 8' x 2.375" Mount Pipe	C	From Leg	4.000	0.000	55.000	No Ice	1.900	1.900	0.029
			0.000			1/2" Ice	2.728	2.728	0.044
			0.000			1" Ice	3.401	3.401	0.063
						2" Ice	4.396	4.396	0.119
Commscope MC-PK8-DSH	C	None		0.000	55.000	No Ice	34.240	34.240	1.749
						1/2" Ice	62.950	62.950	2.099
						1" Ice	91.660	91.660	2.450
						2" Ice	149.080	149.080	3.151

\*

## Load Combinations

<p><b>tnxTower</b></p> <p><b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630</p>	<p><b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)</p>	<p><b>Page</b> 14 of 21</p>
	<p><b>Project</b></p>	<p><b>Date</b> 19:35:35 07/17/21</p>
	<p><b>Client</b> Crown Castle</p>	<p><b>Designed by</b> Sampath</p>

Comb. No.	Description
1	Dead Only
2	1.2 Dead+1.0 Wind 0 deg - No Ice
3	0.9 Dead+1.0 Wind 0 deg - No Ice
4	1.2 Dead+1.0 Wind 30 deg - No Ice
5	0.9 Dead+1.0 Wind 30 deg - No Ice
6	1.2 Dead+1.0 Wind 60 deg - No Ice
7	0.9 Dead+1.0 Wind 60 deg - No Ice
8	1.2 Dead+1.0 Wind 90 deg - No Ice
9	0.9 Dead+1.0 Wind 90 deg - No Ice
10	1.2 Dead+1.0 Wind 120 deg - No Ice
11	0.9 Dead+1.0 Wind 120 deg - No Ice
12	1.2 Dead+1.0 Wind 150 deg - No Ice
13	0.9 Dead+1.0 Wind 150 deg - No Ice
14	1.2 Dead+1.0 Wind 180 deg - No Ice
15	0.9 Dead+1.0 Wind 180 deg - No Ice
16	1.2 Dead+1.0 Wind 210 deg - No Ice
17	0.9 Dead+1.0 Wind 210 deg - No Ice
18	1.2 Dead+1.0 Wind 240 deg - No Ice
19	0.9 Dead+1.0 Wind 240 deg - No Ice
20	1.2 Dead+1.0 Wind 270 deg - No Ice
21	0.9 Dead+1.0 Wind 270 deg - No Ice
22	1.2 Dead+1.0 Wind 300 deg - No Ice
23	0.9 Dead+1.0 Wind 300 deg - No Ice
24	1.2 Dead+1.0 Wind 330 deg - No Ice
25	0.9 Dead+1.0 Wind 330 deg - No Ice
26	1.2 Dead+1.0 Ice+1.0 Temp
27	1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp
28	1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp
29	1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp
30	1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp
31	1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp
32	1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp
33	1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp
34	1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp
35	1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp
36	1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp
37	1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp
38	1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp
39	Dead+Wind 0 deg - Service
40	Dead+Wind 30 deg - Service
41	Dead+Wind 60 deg - Service
42	Dead+Wind 90 deg - Service
43	Dead+Wind 120 deg - Service
44	Dead+Wind 150 deg - Service
45	Dead+Wind 180 deg - Service
46	Dead+Wind 210 deg - Service
47	Dead+Wind 240 deg - Service
48	Dead+Wind 270 deg - Service
49	Dead+Wind 300 deg - Service
50	Dead+Wind 330 deg - Service

### Maximum Member Forces

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L1	100 - 47	Pole	Max Tension	26	0.000	0.000	0.000
			Max. Compression	26	-52.432	-1.467	-2.318
			Max. Mx	8	-27.883	-611.863	-1.582

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 15 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Axial K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L2	47 - 0	Pole	Max. My	14	-27.892	-1.187	-606.984
			Max. Vy	8	21.362	-611.863	-1.582
			Max. Vx	14	21.132	-1.187	-606.984
			Max. Torque	8			1.271
			Max Tension	1	0.000	0.000	0.000
			Max. Compression	26	-71.791	-0.668	-2.485
			Max. Mx	8	-42.968	-1844.755	-0.949
			Max. My	14	-42.968	-0.270	-1828.080
			Max. Vy	8	25.125	-1844.755	-0.949
			Max. Vx	14	24.901	-0.270	-1828.080
			Max. Torque	3			-0.317

### Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	31	71.791	-5.576	-3.199
	Max. H <sub>x</sub>	20	42.982	25.101	-0.013
	Max. H <sub>z</sub>	2	42.982	-0.013	24.876
	Max. M <sub>x</sub>	2	1825.949	-0.013	24.876
	Max. M <sub>z</sub>	8	1844.755	-25.101	0.013
	Max. Torsion	15	0.316	0.013	-24.876
	Min. Vert	25	32.237	12.539	21.537
	Min. H <sub>x</sub>	8	42.982	-25.101	0.013
	Min. H <sub>z</sub>	14	42.982	0.013	-24.876
	Min. M <sub>x</sub>	14	-1828.080	0.013	-24.876
	Min. M <sub>z</sub>	20	-1843.981	25.101	-0.013
	Min. Torsion	3	-0.317	-0.013	24.876

### Tower Mast Reaction Summary

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead Only	35.818	0.000	0.000	0.859	-0.307	0.000
1.2 Dead+1.0 Wind 0 deg - No Ice	42.982	0.013	-24.876	-1825.949	-0.504	0.313
0.9 Dead+1.0 Wind 0 deg - No Ice	32.237	0.013	-24.876	-1815.997	-0.406	0.317
1.2 Dead+1.0 Wind 30 deg - No Ice	42.982	12.562	-21.550	-1581.232	-922.675	0.265
0.9 Dead+1.0 Wind 30 deg - No Ice	32.237	12.562	-21.550	-1572.652	-917.418	0.273
1.2 Dead+1.0 Wind 60 deg - No Ice	42.982	21.745	-12.450	-912.540	-1597.717	0.147
0.9 Dead+1.0 Wind 60 deg - No Ice	32.237	21.745	-12.450	-907.704	-1588.682	0.157
1.2 Dead+1.0 Wind 90 deg - No Ice	42.982	25.101	-0.013	0.949	-1844.755	-0.009
0.9 Dead+1.0 Wind 90 deg - No Ice	32.237	25.101	-0.013	0.673	-1834.336	-0.001
1.2 Dead+1.0 Wind 120 deg - No Ice	42.982	21.731	12.427	914.470	-1597.599	-0.163



<p><b>tnxTower</b></p> <p><b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630</p>	<p><b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)</p>	<p><b>Page</b> 16 of 21</p>
	<p><b>Project</b></p>	<p><b>Date</b> 19:35:35 07/17/21</p>
	<p><b>Client</b> Crown Castle</p>	<p><b>Designed by</b> Sampath</p>

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
No Ice						
0.9 Dead+1.0 Wind 120 deg - No Ice	32.237	21.731	12.427	909.082	-1588.561	-0.157
1.2 Dead+1.0 Wind 150 deg - No Ice	42.982	12.539	21.537	1583.247	-922.472	-0.274
0.9 Dead+1.0 Wind 150 deg - No Ice	32.237	12.539	21.537	1574.117	-917.210	-0.273
1.2 Dead+1.0 Wind 180 deg - No Ice	42.982	-0.013	24.876	1828.080	-0.270	-0.312
0.9 Dead+1.0 Wind 180 deg - No Ice	32.237	-0.013	24.876	1817.582	-0.167	-0.316
1.2 Dead+1.0 Wind 210 deg - No Ice	42.982	-12.562	21.550	1583.364	921.900	-0.268
0.9 Dead+1.0 Wind 210 deg - No Ice	32.237	-12.562	21.550	1574.237	916.844	-0.275
1.2 Dead+1.0 Wind 240 deg - No Ice	42.982	-21.745	12.450	914.672	1596.942	-0.150
0.9 Dead+1.0 Wind 240 deg - No Ice	32.237	-21.745	12.450	909.289	1588.108	-0.160
1.2 Dead+1.0 Wind 270 deg - No Ice	42.982	-25.101	0.013	1.183	1843.981	0.008
0.9 Dead+1.0 Wind 270 deg - No Ice	32.237	-25.101	0.013	0.912	1833.763	-0.001
1.2 Dead+1.0 Wind 300 deg - No Ice	42.982	-21.731	-12.427	-912.338	1596.825	0.165
0.9 Dead+1.0 Wind 300 deg - No Ice	32.237	-21.731	-12.427	-907.496	1587.988	0.159
1.2 Dead+1.0 Wind 330 deg - No Ice	42.982	-12.539	-21.537	-1581.115	921.698	0.277
0.9 Dead+1.0 Wind 330 deg - No Ice	32.237	-12.539	-21.537	-1572.532	916.637	0.276
1.2 Dead+1.0 Ice+1.0 Temp	71.791	0.000	0.000	2.485	-0.668	-0.000
1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp	71.791	0.002	-6.402	-464.431	-0.768	-0.029
1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp	71.791	3.222	-5.546	-401.870	-235.777	-0.122
1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp	71.791	5.578	-3.203	-230.924	-407.809	-0.182
1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp	71.791	6.440	-0.002	2.601	-470.767	-0.193
1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp	71.791	5.576	3.199	236.134	-407.783	-0.153
1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp	71.791	3.218	5.543	407.098	-235.733	-0.071
1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp	71.791	-0.002	6.402	469.684	-0.717	0.029
1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp	71.791	-3.222	5.546	407.123	234.292	0.122
1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp	71.791	-5.578	3.203	236.177	406.324	0.182
1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp	71.791	-6.440	0.002	2.652	469.283	0.193
1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp	71.791	-5.576	-3.199	-230.880	406.299	0.153
1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp	71.791	-3.218	-5.543	-401.845	234.249	0.071
Dead+Wind 0 deg - Service	35.818	0.003	-5.412	-395.562	-0.346	0.069
Dead+Wind 30 deg - Service	35.818	2.733	-4.688	-342.461	-200.443	0.031
Dead+Wind 60 deg - Service	35.818	4.731	-2.709	-197.361	-346.917	-0.015
Dead+Wind 90 deg - Service	35.818	5.461	-0.003	0.858	-400.521	-0.057
Dead+Wind 120 deg - Service	35.818	4.728	2.704	199.085	-346.891	-0.084

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 17 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

Load Combination	Vertical K	Shear <sub>x</sub> K	Shear <sub>z</sub> K	Overturning Moment, M <sub>x</sub> kip-ft	Overturning Moment, M <sub>z</sub> kip-ft	Torque kip-ft
Dead+Wind 150 deg - Service	35.818	2.728	4.686	344.203	-200.398	-0.088
Dead+Wind 180 deg - Service	35.818	-0.003	5.412	397.330	-0.295	-0.069
Dead+Wind 210 deg - Service	35.818	-2.733	4.688	344.229	199.802	-0.031
Dead+Wind 240 deg - Service	35.818	-4.731	2.709	199.129	346.276	0.015
Dead+Wind 270 deg - Service	35.818	-5.461	0.003	0.910	399.879	0.057
Dead+Wind 300 deg - Service	35.818	-4.728	-2.704	-197.317	346.250	0.084
Dead+Wind 330 deg - Service	35.818	-2.728	-4.686	-342.435	199.757	0.088

## Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.000	-35.818	0.000	0.000	35.818	0.000	0.000%
2	0.013	-42.982	-24.876	-0.013	42.982	24.876	0.000%
3	0.013	-32.237	-24.876	-0.013	32.237	24.876	0.000%
4	12.562	-42.982	-21.550	-12.562	42.982	21.550	0.000%
5	12.562	-32.237	-21.550	-12.562	32.237	21.550	0.000%
6	21.745	-42.982	-12.450	-21.745	42.982	12.450	0.000%
7	21.745	-32.237	-12.450	-21.745	32.237	12.450	0.000%
8	25.101	-42.982	-0.013	-25.101	42.982	0.013	0.000%
9	25.101	-32.237	-0.013	-25.101	32.237	0.013	0.000%
10	21.731	-42.982	12.427	-21.731	42.982	-12.427	0.000%
11	21.731	-32.237	12.427	-21.731	32.237	-12.427	0.000%
12	12.539	-42.982	21.537	-12.539	42.982	-21.537	0.000%
13	12.539	-32.237	21.537	-12.539	32.237	-21.537	0.000%
14	-0.013	-42.982	24.876	0.013	42.982	-24.876	0.000%
15	-0.013	-32.237	24.876	0.013	32.237	-24.876	0.000%
16	-12.562	-42.982	21.550	12.562	42.982	-21.550	0.000%
17	-12.562	-32.237	21.550	12.562	32.237	-21.550	0.000%
18	-21.745	-42.982	12.450	21.745	42.982	-12.450	0.000%
19	-21.745	-32.237	12.450	21.745	32.237	-12.450	0.000%
20	-25.101	-42.982	0.013	25.101	42.982	-0.013	0.000%
21	-25.101	-32.237	0.013	25.101	32.237	-0.013	0.000%
22	-21.731	-42.982	-12.427	21.731	42.982	12.427	0.000%
23	-21.731	-32.237	-12.427	21.731	32.237	12.427	0.000%
24	-12.539	-42.982	-21.537	12.539	42.982	21.537	0.000%
25	-12.539	-32.237	-21.537	12.539	32.237	21.537	0.000%
26	0.000	-71.791	0.000	0.000	71.791	0.000	0.000%
27	0.002	-71.791	-6.402	-0.002	71.791	6.402	0.000%
28	3.222	-71.791	-5.545	-3.222	71.791	5.546	0.000%
29	5.578	-71.791	-3.203	-5.578	71.791	3.203	0.000%
30	6.440	-71.791	-0.002	-6.440	71.791	0.002	0.000%
31	5.576	-71.791	3.199	-5.576	71.791	-3.199	0.000%
32	3.218	-71.791	5.543	-3.218	71.791	-5.543	0.000%
33	-0.002	-71.791	6.402	0.002	71.791	-6.402	0.000%
34	-3.222	-71.791	5.545	3.222	71.791	-5.546	0.000%
35	-5.578	-71.791	3.203	5.578	71.791	-3.203	0.000%
36	-6.440	-71.791	0.002	6.440	71.791	-0.002	0.000%
37	-5.576	-71.791	-3.199	5.576	71.791	3.199	0.000%
38	-3.218	-71.791	-5.543	3.218	71.791	5.543	0.000%
39	0.003	-35.818	-5.412	-0.003	35.818	5.412	0.000%
40	2.733	-35.818	-4.688	-2.733	35.818	4.688	0.000%
41	4.731	-35.818	-2.709	-4.731	35.818	2.709	0.000%
42	5.461	-35.818	-0.003	-5.461	35.818	0.003	0.000%
43	4.728	-35.818	2.704	-4.728	35.818	-2.704	0.000%
44	2.728	-35.818	4.686	-2.728	35.818	-4.686	0.000%
45	-0.003	-35.818	5.412	0.003	35.818	-5.412	0.000%

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 18 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
46	-2.733	-35.818	4.688	2.733	35.818	-4.688	0.000%
47	-4.731	-35.818	2.709	4.731	35.818	-2.709	0.000%
48	-5.461	-35.818	0.003	5.461	35.818	-0.003	0.000%
49	-4.728	-35.818	-2.704	4.728	35.818	2.704	0.000%
50	-2.728	-35.818	-4.686	2.728	35.818	4.686	0.000%

## Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.0000001	0.0000001
2	Yes	4	0.0000001	0.00001921
3	Yes	4	0.0000001	0.00001159
4	Yes	4	0.0000001	0.00029744
5	Yes	4	0.0000001	0.00019610
6	Yes	4	0.0000001	0.00029416
7	Yes	4	0.0000001	0.00019351
8	Yes	4	0.0000001	0.00001854
9	Yes	4	0.0000001	0.00001095
10	Yes	4	0.0000001	0.00029053
11	Yes	4	0.0000001	0.00019098
12	Yes	4	0.0000001	0.00030269
13	Yes	4	0.0000001	0.00019934
14	Yes	4	0.0000001	0.00001940
15	Yes	4	0.0000001	0.00001173
16	Yes	4	0.0000001	0.00029055
17	Yes	4	0.0000001	0.00019113
18	Yes	4	0.0000001	0.00029516
19	Yes	4	0.0000001	0.00019434
20	Yes	4	0.0000001	0.00001863
21	Yes	4	0.0000001	0.00001102
22	Yes	4	0.0000001	0.00030054
23	Yes	4	0.0000001	0.00019804
24	Yes	4	0.0000001	0.00028709
25	Yes	4	0.0000001	0.00018909
26	Yes	4	0.0000001	0.00000001
27	Yes	4	0.0000001	0.00021846
28	Yes	4	0.0000001	0.00022749
29	Yes	4	0.0000001	0.00022928
30	Yes	4	0.0000001	0.00022304
31	Yes	4	0.0000001	0.00023164
32	Yes	4	0.0000001	0.00023135
33	Yes	4	0.0000001	0.00022245
34	Yes	4	0.0000001	0.00022980
35	Yes	4	0.0000001	0.00022937
36	Yes	4	0.0000001	0.00022068
37	Yes	4	0.0000001	0.00022716
38	Yes	4	0.0000001	0.00022610
39	Yes	4	0.0000001	0.00000001
40	Yes	4	0.0000001	0.00000496
41	Yes	4	0.0000001	0.00000509
42	Yes	4	0.0000001	0.00000001
43	Yes	4	0.0000001	0.00000481
44	Yes	4	0.0000001	0.00000534
45	Yes	4	0.0000001	0.00000001
46	Yes	4	0.0000001	0.00000491

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 19 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

47	Yes	4	0.00000001	0.00000487
48	Yes	4	0.00000001	0.00000001
49	Yes	4	0.00000001	0.00000532
50	Yes	4	0.00000001	0.00000001

### Maximum Tower Deflections - Service Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	100 - 47	5.152	42	0.404	0.001
L2	53 - 0	1.630	42	0.272	0.000

### Critical Deflections and Radius of Curvature - Service Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
100.000	Lightning Rod 1/2" x 8'	42	5.152	0.404	0.001	85107
86.000	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	42	3.971	0.372	0.001	30395
78.000	TME-800MHZ RRH	42	3.325	0.352	0.000	19342
76.000	(2) APXVSP18-C-A20 w/ Mount Pipe	42	3.170	0.346	0.000	17730
65.000	BXA-70063/6CF w/ Mount Pipe	42	2.368	0.314	0.000	12158
55.000	MX08FRO665-21 w/ Mount Pipe	42	1.741	0.280	0.000	9528

### Maximum Tower Deflections - Design Wind

Section No.	Elevation ft	Horz. Deflection in	Gov. Load Comb.	Tilt °	Twist °
L1	100 - 47	23.709	8	1.857	0.003
L2	53 - 0	7.509	8	1.254	0.000

### Critical Deflections and Radius of Curvature - Design Wind

Elevation ft	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
100.000	Lightning Rod 1/2" x 8'	8	23.709	1.857	0.003	18551
86.000	ERICSSON AIR 21 B2A B4P w/ Mount Pipe	8	18.275	1.710	0.002	6625
78.000	TME-800MHZ RRH	8	15.306	1.619	0.002	4215
76.000	(2) APXVSP18-C-A20 w/ Mount Pipe	8	14.590	1.594	0.001	3864
65.000	BXA-70063/6CF w/ Mount Pipe	8	10.901	1.448	0.001	2649

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 20 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

Elevation	Appurtenance	Gov. Load Comb.	Deflection in	Tilt °	Twist °	Radius of Curvature ft
55.000	MX08FRO665-21 w/ Mount Pipe	8	8.019	1.289	0.000	2075

### Compression Checks

### Pole Design Data

Section No.	Elevation ft	Size	L ft	L <sub>u</sub> ft	Kl/r	A in <sup>2</sup>	P <sub>u</sub> K	φP <sub>n</sub> K	Ratio P <sub>u</sub> / φP <sub>n</sub>
L1	100 - 47 (1)	TP40.72x28x0.313	53.000	0.000	0.0	38.846	-27.883	2272.480	0.012
L2	47 - 0 (2)	TP51.37x38.655x0.375	53.000	0.000	0.0	61.003	-42.968	3568.660	0.012

### Pole Bending Design Data

Section No.	Elevation ft	Size	M <sub>ux</sub> kip-ft	φM <sub>ux</sub> kip-ft	Ratio M <sub>ux</sub> / φM <sub>ux</sub>	M <sub>uy</sub> kip-ft	φM <sub>uy</sub> kip-ft	Ratio M <sub>uy</sub> / φM <sub>uy</sub>
L1	100 - 47 (1)	TP40.72x28x0.313	611.865	2103.400	0.291	0.000	2103.400	0.000
L2	47 - 0 (2)	TP51.37x38.655x0.375	1844.758	4179.683	0.441	0.000	4179.683	0.000

### Pole Shear Design Data

Section No.	Elevation ft	Size	Actual V <sub>u</sub> K	φV <sub>n</sub> K	Ratio V <sub>u</sub> / φV <sub>n</sub>	Actual T <sub>u</sub> kip-ft	φT <sub>n</sub> kip-ft	Ratio T <sub>u</sub> / φT <sub>n</sub>
L1	100 - 47 (1)	TP40.72x28x0.313	21.362	681.743	0.031	0.163	2329.483	0.000
L2	47 - 0 (2)	TP51.37x38.655x0.375	25.125	1070.600	0.023	0.009	4787.300	0.000

### Pole Interaction Design Data

Section No.	Elevation ft	Ratio P <sub>u</sub> / φP <sub>n</sub>	Ratio M <sub>ux</sub> / φM <sub>ux</sub>	Ratio M <sub>uy</sub> / φM <sub>uy</sub>	Ratio V <sub>u</sub> / φV <sub>n</sub>	Ratio T <sub>u</sub> / φT <sub>n</sub>	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	100 - 47 (1)	0.012	0.291	0.000	0.031	0.000	0.304	1.050	4.8.2 ✓
L2	47 - 0 (2)	0.012	0.441	0.000	0.023	0.000	0.454	1.050	4.8.2 ✓

<b>tnxTower</b>  <b>B+T Group</b> 1717 S. Boulder, Suite 300 Tulsa, OK 74119 Phone: (918) 587-4630 FAX: (918) 587-4630	<b>Job</b> 92699.007.01 - MERIDEN WEST CENTRAL, CT (BU# 842869)	<b>Page</b> 21 of 21
	<b>Project</b>	<b>Date</b> 19:35:35 07/17/21
	<b>Client</b> Crown Castle	<b>Designed by</b> Sampath

### Section Capacity Table

Section No.	Elevation ft	Component Type	Size	Critical Element	P K	$\phi P_{allow}$ K	% Capacity	Pass Fail	
L1	100 - 47	Pole	TP40.72x28x0.313	1	-27.883	2386.104	29.0	Pass	
L2	47 - 0	Pole	TP51.37x38.655x0.375	2	-42.968	3747.093	43.2	Pass	
							Summary		
							Pole (L2)	43.2	Pass
							<b>RATING =</b>	<b>43.2</b>	<b>Pass</b>

**APPENDIX B**  
**BASE LEVEL DRAWING**

(OTHER CONSIDERED EQUIPMENT)  
(8) 1/2" TO 100 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(1) 5/8" TO 76 FT LEVEL  
(1) 3/4" TO 76 FT LEVEL  
(3) 1-1/4" TO 76 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(2) 3/8" TO 100 FT LEVEL  
(6) 3/4" TO 100 FT LEVEL  
(6) 1-1/4" TO 100 FT LEVEL


(PROPOSED EQUIPMENT CONFIGURATION)  
(1) 1-3/8" TO 55 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(2) 1-5/8" TO 65 FT LEVEL

(OTHER CONSIDERED EQUIPMENT)  
(6) 7/8" TO 86 FT LEVEL  
(4) 1-5/8" TO 86 FT LEVEL

CLIMBING PEGS  
W/ SAFETY CLIMB

BUSINESS UNIT: 842869





**APPENDIX C**  
**ADDITIONAL CALCULATIONS**

# Monopole Base Plate Connection




Site Info	
BU #	842869
Site Name	RIDEN WEST CENTRAL
Order #	553374, Rev. 0

Analysis Considerations	
TIA-222 Revision	H
Grout Considered:	No
$I_{ar}$ (in)	1

Applied Loads	
Moment (kip-ft)	1844.76
Axial Force (kips)	42.97
Shear Force (kips)	25.13

\*TIA-222-H Section 15.5 Applied



Connection Properties	Analysis Results
-----------------------	------------------

<b>Anchor Rod Data</b>
(20) 2-1/2" $\phi$ bolts (A572-50 N; $F_y=50$ ksi, $F_u=65$ ksi) on 59" BC
<b>Base Plate Data</b>
69" OD x 3" Plate (A36; $F_y=36$ ksi, $F_u=58$ ksi)
<b>Stiffener Data</b>
N/A
<b>Pole Data</b>
51.37" x 0.375" 16-sided pole (A572-65; $F_y=65$ ksi, $F_u=80$ ksi)

Anchor Rod Summary		<i>(units of kips, kip-in)</i>
$Pu_t = 72.84$	$\phi Pn_t = 195$	<b>Stress Rating</b>
$Vu = 1.26$	$\phi Vn = 119.65$	<b>35.6%</b>
$Mu = n/a$	$\phi Mn = n/a$	<b>Pass</b>
<b>Base Plate Summary</b>		
Max Stress (ksi):	9.84	(Flexural)
Allowable Stress (ksi):	32.4	
Stress Rating:	<b>28.9%</b>	<b>Pass</b>

# Pier and Pad Foundation



BU #: 842869  
 Site Name: MERIDEN WEST C  
 App. Number: 553374, Rev. 0

TIA-222 Revision: H  
 Tower Type: Monopole

Top & Bot. Pad Rein. Different?:   
 Block Foundation?:   
 Rectangular Pad?:

Superstructure Analysis Reactions		
Compression, $P_{comp}$ :	42.98	kips
Base Shear, $V_{u\_comp}$ :	25.1	kips
Moment, $M_u$ :	1844.76	ft-kips
Tower Height, $H$ :	100	ft
BP Dist. Above Fdn, $bp_{dist}$ :	3.25	in

Foundation Analysis Checks				
	Capacity	Demand	Rating*	Check
<i>Lateral (Sliding) (kips)</i>	191.13	25.10	12.5%	Pass
<i>Bearing Pressure (ksf)</i>	6.62	2.38	36.0%	Pass
<i>Overtuning (kip*ft)</i>	3757.94	2064.91	54.9%	Pass
<i>Pier Flexure (Comp.) (kip*ft)</i>	16131.72	1995.36	11.8%	Pass
<i>Pier Compression (kip)</i>	40734.72	112.10	0.3%	Pass
<i>Pad Flexure (kip*ft)</i>	3474.94	553.48	15.2%	Pass
<i>Pad Shear - 1-way (kips)</i>	576.22	120.49	19.9%	Pass
<i>Pad Shear - 2-way (Comp) (ksi)</i>	0.190	0.027	13.7%	Pass
<i>Flexural 2-way (Comp) (kip*ft)</i>	5377.97	1197.22	21.2%	Pass

Pier Properties		
Pier Shape:	Square	
Pier Diameter, $dpier$ :	8	ft
Ext. Above Grade, $E$ :	1	ft
Pier Rebar Size, $Sc$ :	11	
Pier Rebar Quantity, $mc$ :	60	
Pier Tie/Spiral Size, $St$ :	4	
Pier Tie/Spiral Quantity, $mt$ :	7	
Pier Reinforcement Type:	Tie	
Pier Clear Cover, $cc_{pier}$ :	3	in

\*Rating per TIA-222-H Section 15.5

Structural Rating*:	21.2%
Soil Rating*:	54.9%

Pad Properties		
Depth, $D$ :	7.5	ft
Pad Width, $W_1$ :	20	ft
Pad Thickness, $T$ :	2.5	ft
Pad Rebar Size (Bottom dir. 2), $Sp_2$ :	9	
Pad Rebar Quantity (Bottom dir. 2), $mp_2$ :	32	
Pad Clear Cover, $cc_{pad}$ :	3	in

Material Properties		
Rebar Grade, $F_y$ :	60	ksi
Concrete Compressive Strength, $F'_c$ :	4	ksi
Dry Concrete Density, $\delta_c$ :	150	pcf

Soil Properties		
Total Soil Unit Weight, $\gamma$ :	110	pcf
Ultimate Net Bearing, $Q_{net}$ :	8.000	ksf
Cohesion, $C_u$ :	0.000	ksf
Friction Angle, $\phi$ :	30	degrees
SPT Blow Count, $N_{blows}$ :		
Base Friction, $\mu$ :	0.35	
Neglected Depth, $N$ :	3.50	ft
Foundation Bearing on Rock?	No	
Groundwater Depth, $gw$ :	N/A	ft



<--Toggle between Gross and Net

# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-10  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 165.37 ft (NAVD 88)  
**Latitude:** 41.540031  
**Longitude:** -72.819019





**Site Soil Class:** D - Stiff Soil

**Results:**

$S_s$ :	0.184	$S_{DS}$ :	0.196
$S_1$ :	0.063	$S_{D1}$ :	0.101
$F_a$ :	1.6	$T_L$ :	6
$F_v$ :	2.4	PGA :	0.094
$S_{MS}$ :	0.294	PGA <sub>M</sub> :	0.151
$S_{M1}$ :	0.151	F <sub>PGA</sub> :	1.6
		$I_e$ :	1

**Seismic Design Category** B



**Data Accessed:**

Sat Jul 17 2021

**Date Source:**

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

## Ice

---

### Results:

Ice Thickness: 0.75 in.  
Concurrent Temperature: 15 F  
Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

**Date Accessed:** Sat Jul 17 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

---

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

# Exhibit E

## **Mount Analysis**



Date: **September 13, 2021**

Jacob Montoya  
Crown Castle  
2055 S. Stearman Drive  
Chandler, AZ 85286  
(480) 298-9641

POD Group  
1033 E Turkeyfoot Lake Rd. Suite 206  
Akron, OH 44312  
(330) 961.7432  
[aherkenhoff@podgrp.com](mailto:aherkenhoff@podgrp.com)

**Subject:** **Mount Analysis Report**

**Carrier Designation:** **DISH Network**  
**Carrier Site Number:** **BOHVN00156A**  
**Carrier Site Name:** **CT-CCI-T-842869**

**Crown Castle Designation:** **Crown Castle BU Number:** **842869**  
**Crown Castle Site Name:** **MERIDEN WEST CENTRAL**  
**Crown Castle JDE Job Number:** **645144**  
**Crown Castle Order Number:** **553374 Rev 2**

**Engineering Firm Designation:** **POD Report Designation:** **21-108451**

**Site Data:** **450-478 West Main Street, Meriden, New Haven County, CT 06451**  
**Latitude 41° 32' 24.11" Longitude -72° 49' 8.47"**

**Structure Information:** **Tower Height & Type:** **100 ft Monopole**  
**Mount Elevation:** **55 ft**  
**Mount Type:** **8 ft Platform with Support Rails**

Dear Jacob Montoya,

POD Group is pleased to submit this "Mount Analysis Report" to determine the structural integrity of DISH Network's antenna mounting system with the proposed appurtenance and equipment addition on the abovementioned supporting tower structure. Analysis of the existing supporting tower structure is to be completed by others and therefore is not part of this analysis. Analysis of the antenna mounting system as a tie-off point for fall protection or rigging is not part of this document.

The purpose of the analysis is to determine acceptability of the mount stress level. Based on our analysis we have determined the mount stress level to be:

**8 ft Platform with Support Rails (Multiple Sector) Sufficient\***  
**\*The mount has sufficient capacity once the loading changes, as described in Section 4.1**  
**Recommendations of this report, are completed.**

This analysis utilizes an ultimate 3-second gust wind speed of 123 mph as required by the 2015 International Building Code. Applicable Standard references and design criteria are listed in Section 2 - Analysis Criteria.

Mount structural analysis prepared by: Joseph Martin

Respectfully submitted by:



**Jason Cheronis**

Digitally signed  
by Jason  
Cheronis  
Date: 2021.09.13  
10:21:06 -04'00'

Jason Cheronis, PE  
Connecticut PE#: 0032793



## TABLE OF CONTENTS

- 1) **INTRODUCTION**
- 2) **ANALYSIS CRITERIA**
  - Table 1 – Proposed Equipment Configuration
- 3) **ANALYSIS PROCEDURE**
  - Table 2 – Documents Provided
  - 3.1) Analysis Method
  - 3.2) Assumptions
- 4) **ANALYSIS RESULTS**
  - Table 3 - Mount Component Stresses vs. Capacity
  - 4.1) Recommendations
- 5) **APPENDIX A**
  - Wire Frame and Rendered Models
- 6) **APPENDIX B**
  - Software Input Calculations
- 7) **APPENDIX C**
  - Software Analysis Output
- 8) **APPENDIX D**
  - Additional Calculations
- 9) **APPENDIX E**
  - Design Criteria
- 10) **APPENDIX F**
  - Mount Specification Sheets

## 1) INTRODUCTION

This mount is a proposed 8 ft Platform with Support Rails designed by Commscope, P/N: MC-PK8-DSH. This mount is to be installed at the 55 ft elevation on the 100 ft Monopole.

## 2) ANALYSIS CRITERIA

<b>Building Code:</b>	2015 IBC
<b>TIA-222 Revision:</b>	TIA-222-H
<b>Risk Category:</b>	II
<b>Ultimate Wind Speed:</b>	123 mph
<b>Exposure Category:</b>	B
<b>Topographic Factor at Base:</b>	1.000
<b>Topographic Factor at Mount:</b>	1.000
<b>Ice Thickness:</b>	1.0 in
<b>Wind Speed with Ice:</b>	50 mph
<b>Seismic S<sub>s</sub>:</b>	0.184
<b>Seismic S<sub>1</sub>:</b>	0.063
<b>Live Loading Wind Speed:</b>	30 mph
<b>Man Live Load at Mid/End-Points:</b>	250 lb
<b>Man Live Load at Mount Pipes:</b>	500 lb

**Table 1 - Proposed Equipment Configuration**

Mount Centerline (ft)	Antenna Centerline (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Mount / Modification Details	Note
55	55	3	JMA WIRELESS	MX08FRO665-21	8 ft Platform with Support Rails	-
		3	FUJITSU	TA08025-B604		
		3	FUJITSU	TA08025-B605		
		1	RAYCAP	RDIDC-9181-PF-48		

## 3) ANALYSIS PROCEDURE

**Table 2 - Documents Provided**

Document	Remarks	Reference	Source
Crown Application	-	Crown Castle App #: 553374 Rev 2 Dated: 04/28/2021	Crown Castle
Structural Analysis	-	B+T Group Report #: 92699.007.01 Dated: 07/20/2021	Crown Castle
Proposed Base Levels Drawings	-	Crown Castle Sheet #: A1-55 Dated: 07/09/2021	Crown Castle
Mount Specification Sheets	-	Commscope Part #: MC-PK8-DSH Dated: 03/17/2021	Commscope

### 3.1) Analysis Method

RISA-3D (Version 17.0.4), a commercially available analysis software package, was used to create a three-dimensional model of the antenna mounting system and calculate member stresses for various loading cases. Selected output from the analysis are included in the Appendices.

A tool internally developed, using Microsoft Excel, by POD Group, was used to calculate wind loading on all appurtenances, dishes, and mount members for various load cases. Selected output from the calculations is included in Appendix B.

This analysis was performed in accordance with Crown Castle's ENG-SOW-10208 Tower Mount Analysis (Revision B).

### 3.2) Assumptions

- 1) The antenna mounting system was properly fabricated, installed, and maintained in good condition in accordance with its original design, TIA Standards, and/or manufacturer's specifications. This is not a condition assessment of the mount, structure, or foundation.
- 2) The configuration of antennas, mounts, and other appurtenances are as specified in Table 1 and the referenced drawings.
- 3) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 4) The weight of the mount was increased 10% in the analysis to account for connections, coax, and jumpers.
- 5) The purpose of this report is to assess the feasibility of adding appurtenances usually accompanied by transmission lines to the structure. POD Group does not analyze the fabrication of the mount or structure (including welding).
- 6) The analysis will be required to be revised if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.
- 7) Steel grades have been used as follows, unless noted otherwise:
  - a. Angles, Plates, Channels                      ASTM A529 (GR 50)
  - b. Plates    ASTM A1011 (GR 36)
  - c. HSS (Rectangular), Pipes                      ASTM 500 (GR C)
  - d. Connection Bolts                                      ASTM A325

If any of these assumptions are not valid or have been made in error, this analysis may be affected, and POD Group should be allowed to review any new information to determine its effect on the structural integrity of the mount.

#### 4) ANALYSIS RESULTS

**Table 3 - Mount Component Stresses vs. Capacity (8 ft Platform with Support Rails)**

Notes	Component	Critical Member	Centerline (ft)	% Capacity	Pass / Fail
1	Crossarm	CR4	55	16.0	Pass
	Standoff	SO2		18.8	Pass
	Plate	PL6		36.2	Pass
	Angle	ANGLE2		6.8	Pass
	Mount Pipe	MP ALPHA2		8.0	Pass
	Face	FACE1		6.2	Pass
	Rail	RAIL1		6.3	Pass
	Standoff Flange Plate Bolts	-		2.3	Pass
	Standoff Flange Plate	-		22.9	Pass

<b>Structure Rating (max from all components) =</b>	<b>36.2%</b>
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Software Analysis Output" and "Appendix D – Additional Calculations" for calculations supporting the % capacity

#### 4.1) Recommendations


The mount has sufficient capacity to carry the proposed loading configuration. In order for the results of the analysis to be considered valid, the loading modification listed below must be completed.

1. The proposed mount by Commscope, P/N: MC-PK8-DSH, is to be installed per manufacturer specifications, centered at 55 ft.
  - o All critical measurements and manufacturer specifications for the above specified modification part shall be field verified prior to material ordering.
  - o The contractor shall provide shop drawings to POD Group prior to material ordering and/or fabrication of the above specified modification part.
  - o Any substitutes, additions, or alterations shall be approved by POD Group prior to material ordering and/or fabrication.

If any of these guidelines are not met, POD Group shall not be held liable.

## **APPENDIX A**

### **Wire Frame and Rendered Models**



POD



JMM

21-108451

842869

Sept 13, 2021 at 9:02 AM

MC-PK8-DSH - Copy.r3d



POD


JMM

21-108451

842869

Sept 13, 2021 at 9:04 AM

MC-PK8-DSH - Copy.r3d





POD  
JMM  
21-108451

842869



Sept 13, 2021 at 9:04 AM  
MC-PK8-DSH - Copy.r3d





Member Length (ft) Displayed

POD	842869	
JMM		Sept 13, 2021 at 9:04 AM
21-108451		MC-PK8-DSH - Copy.r3d



Loads: LC 2, 1.2D + 1.0W(0)

POD

JMM

21-108451

842869

Sept 13, 2021 at 9:04 AM

MC-PK8-DSH - Copy.r3d

**APPENDIX B**  
**Software Input Calculations**



**POD Job #** 21-108451  
**Site Number** 842869  
**Site Name** Meriden West Central

**General Site Information**

Mount Type	SFP	Risk Category	II	I (seismic)	1	Use CFD	Yes
V (Wind Speed)	123	I(ice)	1	Sms	0.294		
Zs	165.37			Sm1	0.151	width (ft)	height (ft)
ti	1	Ss	0.184	Sds	0.196	8	4
Vi	50	S1	0.063	Sd1	0.101		
Kzt	1	Soil Site Class	D	Seismic Design Category			
Exposure	B	Fa	1.600	B			
zg	1200	Fv	2.400	Seismic Analysis Not Required			
α	7			R	2 TIA-222-H 16.7		
Kmin	0.7	Tower Type	Monopole	As	1 TIA-222-H 16.7		
G <sub>H</sub>	1	Tower Height	100	Cs, Min	0.03 TIA-222-H 2.7.7.1.1		
Ke	0.99			Cs	0.098133333 TIA-222-H 2.7.7.1.1		
K <sub>D</sub>	0.95						
K <sub>a</sub>	0.9						

**Appurtenance Information**

Model	Shielded	% Shielded	Centerline	Centerline on MP	Spacing (in)	Azimuth	Sector	Quantity	MP #
MX08FRO665-21			55	4	60		A/B/C	1 2	2
TA08025-B604			55	4			A/B/C	1 2	2
TA08025-B605			55	4			A/B/C	1 2	2
RDI/DC-9181-PF-48			55	4			A	1 2	2

**Mount Information**

Elevation (ft)	55	Grating Thickness (in)	1
K <sub>z</sub>	0.83	Grating Ice Weight (k/ft <sup>2</sup> )	0.013
K <sub>iz</sub>	1.05		
t <sub>iz</sub>	1.05		


Mount Pipes	Length (ft)	Width (in)	Centerline
	8	2.875	55

**Round Members**

Member	Length (ft)	Width (in)	Frame Member	# of Members
Rail On	8	2.875	Yes	2
Rail Off	8	2.875	No	1
Face On	8	3.5	Yes	2
Face Off	8	3.5	No	1

**Flat Members**

Member	Length (ft)	Width (in)	Shape	A	B	C	D	Frame Member	# of Members
SO	3.4	4	Square HSS	4	0.375	4		No	3
RPL	3.5	4.5	Angle	4.5	0.25			No	3
Plate	0.25	0.5	Channel	0	2	0	0.5	No	18
Crossarm	2.75	3.38	Channel	2.06	3.38	0.25	0.25	No	6
CPL	3.5	0.375	Channel	0	6.5	0	0.375	No	3
Angle	2.3	2	Angle	2	0.25			No	6



**Appurtenance Wind Calculations**

Model	Height	Width	Depth	Weight (lbs)		Kz	qz (lb/ft <sub>2</sub> )	(EPA) <sub>N</sub> (ft <sup>2</sup> )	(EPA) <sub>S</sub> (ft <sup>2</sup> )	Front	Side	Wind Force (Kip: Alpha)	
MX08FRO665-21	72.0	20.0	20.0	8.0	82.5		0.83	30.47	8.01	3.21	0.244	0.098	0.207
TA08025-B604	15.0	15.8	7.9	63.9			0.83	30.47	1.77	0.88	0.054	0.027	0.047
TA08025-B605	15.0	15.8	9.1	75.0			0.83	30.47	1.77	1.02	0.054	0.031	0.048
RDIDC-9181-PF-48	16.6	14.6	8.5	21.9			0.83	30.47	1.81	1.05	0.055	0.032	0.049

**Appurtenance Ice Calculations**

Model	tiz (in)	Height	Width	Depth	Weight (lbs)		Kiz	qz (lb/ft <sub>2</sub> )	(EPA) <sub>N</sub> (ft <sup>2</sup> )	(EPA) <sub>S</sub> (ft <sup>2</sup> )	Front	Side	W
MX08FRO665-21	1.05	74.10	22.10	10.10	163.09		1.05	5.03	8.20	3.75	0.041	0.019	
TA08025-B604	1.05	17.06	17.85	9.97	38.40		1.05	5.03	1.33	0.75	0.007	0.004	
TA08025-B605	1.05	17.06	17.85	11.16	41.06		1.05	5.03	1.33	0.83	0.007	0.004	
RDIDC-9181-PF-48	1.05	18.67	16.67	10.56	40.43		1.05	5.03	1.36	0.86	0.007	0.004	

**Round Members**

Member	q <sub>z</sub> (lb/ft <sup>2</sup> )	Ar	C	Wind Calculations				Ice Calculations				
				Rr	Cf	EPA (ft <sup>2</sup> )	Load (k/ft)	Width (in)	Weight (k/ft)	q <sub>z</sub> (lb/ft <sup>2</sup> )	Arice	Rrice
Rail On	30.47	3.83	26.22	0.59	1.20	1.22	0.005	4.98	0.01	5.03	6.64	0.64
Rail Off	30.47	1.92	26.22	0.59	1.20	1.22	0.002	4.98	0.01	5.03	3.32	0.64
Face On	30.47	4.67	31.91	0.59	1.20	1.48	0.006	5.60	0.01	5.03	7.47	0.64
Face Off	30.47	2.33	31.91	0.59	1.20	1.48	0.003	5.60	0.01	5.03	3.74	0.64

**Flat Members**

Member	q <sub>z</sub> (lb/ft <sup>2</sup> )	Af	Cf	Wind Calculations			Ice Calculations				
				EPA	Load (k/ft)		Width (in)	Weight (k/ft)	q <sub>z</sub> (lb/ft <sup>2</sup> )	Arice	Rrice
SO	30.47	3.40	1.25	1.28	0.006	6.10	0.01	5.03	5.19	0.64	
RPL	30.47	3.94	2.00	2.36	0.010	6.60	0.01	5.03	5.78	0.64	
Plate	30.47	0.19	2.00	0.02	0.001	2.60	0.00	5.03	0.98	0.64	
Crossarm	30.47	4.65	2.00	1.39	0.008	5.48	0.01	5.03	7.54	0.64	
CPL	30.47	0.33	2.00	0.20	0.001	2.48	0.01	5.03	2.17	0.64	
Angle	30.47	2.30	2.00	0.69	0.005	4.10	0.00	5.03	4.72	0.64	

**Appurtenance Seismic Calculations**

Model	Weight	Sds	p	Cs	As	Ev	Eh
MX08FRO665-21	82.5	0.196	1.000	0.098	1.000	0.003	0.008
TA08025-B604	63.9	0.196	1.000	0.098	1.000	0.003	0.006
TA08025-B605	75.0	0.196	1.000	0.098	1.000	0.003	0.007
RDIDC-9181-PF-48	21.9	0.196	1.000	0.098	1.000	0.001	0.002

**APPENDIX C**  
**Software Analysis Output**



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

### Hot Rolled Steel Design Parameters

	Label	Shape	Length[ft]	Lbyy[ft]	Lbzz[ft]	Lcomp top[...]	Lcomp bot[...]	L-torq...	Kyy	Kzz	Cb	Functi...
1	SO3	HSS4X4X6	3.333			Lbyy						Lateral
2	SO2	HSS4X4X6	3.333			Lbyy						Lateral
3	SO1	HSS4X4X6	3.333			Lbyy						Lateral
4	RPL3	L6.6x4.46x...	3.5			Lbyy						Lateral
5	RPL2	L6.6x4.46x...	3.5			Lbyy						Lateral
6	RPL1	L6.6x4.46x...	3.5			Lbyy						Lateral
7	RAIL3	PIPE 2.5	8			Lbyy						Lateral
8	RAIL2	PIPE 2.5	8			Lbyy						Lateral
9	RAIL1	PIPE 2.5	8			Lbyy						Lateral
10	PL18	2 x 0.5	.25			Lbyy						Lateral
11	PL17	2 x 0.5	.173			Lbyy						Lateral
12	PL16	2 x 0.5	.25			Lbyy						Lateral
13	PL15	2 x 0.5	.195			Lbyy						Lateral
14	PL14	2 x 0.5	.25			Lbyy						Lateral
15	PL13	2 x 0.5	.173			Lbyy						Lateral
16	PL12	2 x 0.5	.25			Lbyy						Lateral
17	PL11	2 x 0.5	.25			Lbyy						Lateral
18	PL10	2 x 0.5	.195			Lbyy						Lateral
19	PL9	2 x 0.5	.173			Lbyy						Lateral
20	PL8	2 x 0.5	.25			Lbyy						Lateral
21	PL7	2 x 0.5	.195			Lbyy						Lateral
22	PL6	2 x 0.5	.25			Lbyy						Lateral
23	PL5	2 x 0.5	.25			Lbyy						Lateral
24	PL4	2 x 0.5	.25			Lbyy						Lateral
25	PL3	2 x 0.5	.25			Lbyy						Lateral
26	PL2	2 x 0.5	.25			Lbyy						Lateral
27	PL1	2 x 0.5	.25			Lbyy						Lateral
28	MP GAMMA3	PIPE 2.5	8			Lbyy						Lateral
29	MP GAMMA2	PIPE 2.5	8			Lbyy						Lateral
30	MP GAMMA1	PIPE 2.5	8			Lbyy						Lateral
31	MP BETA3	PIPE 2.5	8			Lbyy						Lateral
32	MP BETA2	PIPE 2.5	8			Lbyy						Lateral
33	MP BETA1	PIPE 2.5	8			Lbyy						Lateral
34	MP ALPHA3	PIPE 2.5	8			Lbyy						Lateral
35	MP ALPHA2	PIPE 2.5	8			Lbyy						Lateral
36	MP ALPHA1	PIPE 2.5	8			Lbyy						Lateral
37	FACE3	Pipe3.5x0....	8			Lbyy						Lateral
38	FACE2	Pipe3.5x0....	8			Lbyy						Lateral
39	FACE1	Pipe3.5x0....	8			Lbyy						Lateral
40	CR6	C3.38x2.0...	2.525			Lbyy						Lateral
41	CR5	C3.38x2.0...	2.525			Lbyy						Lateral
42	CR4	C3.38x2.0...	2.525			Lbyy						Lateral
43	CR3	C3.38x2.0...	2.525			Lbyy						Lateral
44	CR2	C3.38x2.0...	2.525			Lbyy						Lateral
45	CR1	C3.38x2.0...	2.525			Lbyy						Lateral
46	CPL3	PL6.5x0.375	3			Lbyy						Lateral
47	CPL2	PL6.5x0.375	3			Lbyy						Lateral
48	CPL1	PL6.5x0.375	3			Lbyy						Lateral
49	ANGLE6	L2x2x4	2.275			Lbyy						Lateral
50	ANGLE5	L2x2x4	2.275			Lbyy						Lateral
51	ANGLE4	L2x2x4	2.275			Lbyy						Lateral
52	ANGLE3	L2x2x4	2.275			Lbyy						Lateral
53	ANGLE2	L2x2x4	2.275			Lbyy						Lateral
54	ANGLE1	L2x2x4	2.275			Lbyy						Lateral



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Primary Data**

	Label	I Joint	J Joint	K Joint	Rotate...	Section/Shape	Type	Design List	Material	Design ...
1	SO3	P25	P24		270	HSS4X4X6	Beam	SquareTube	A500 GR.C	Typical
2	SO2	P3	P1		90	HSS4X4X6	Beam	SquareTube	A500 GR.C	Typical
3	SO1	P14	P13		270	HSS4X4X6	Beam	SquareTube	A500 GR.C	Typical
4	RPL3	N116A	N115A		90	L6.6x4.46x0.25	Beam	Single Angle	A529 Gr. 50	Typical
5	RPL2	N112A	N111A		270	L6.6x4.46x0.25	Beam	Single Angle	A529 Gr. 50	Typical
6	RPL1	N114A	N113A		270	L6.6x4.46x0.25	Beam	Single Angle	A529 Gr. 50	Typical
7	RAIL3	N67	N68		270	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
8	RAIL2	N91	N92		270	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
9	RAIL1	N119	N120		90	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
10	PL18	N143	N146		90	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
11	PL17	N143	N141		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
12	PL16	N134	N149		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
13	PL15	N140A	N134		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
14	PL14	N135B	N136B		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
15	PL13	N135B	N123A		90	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
16	PL12	N154	N157		90	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
17	PL11	N137	N138		90	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
18	PL10	N122A	N137		90	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
19	PL9	N154	N152		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
20	PL8	N132A	N160		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
21	PL7	N151	N132A		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
22	PL6	N158A	N157A		90	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
23	PL5	N161	N162		90	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
24	PL4	N167	N166		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
25	PL3	N169	N170		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
26	PL2	N176	N175		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
27	PL1	N178	N179		270	2 x 0.5	Beam	RECT	A1011 36 Ksi	Typical
28	MP GAMMA3	N57	N63		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
29	MP GAMMA2	N74	N75		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
30	MP GAMMA1	N60	N66		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
31	MP BETA3	N87	N89		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
32	MP BETA2	N131A	N132B		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
33	MP BETA1	N88	N90		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
34	MP ALPHA3	N115	N117		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
35	MP ALPHA2	N137A	N138A		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
36	MP ALPHA1	N116	N118		300	PIPE 2.5	Beam	Pipe	A500 GR.C	Typical
37	FACE3	N43	N44		270	Pipe3.5x0.165	Beam	Pipe	A500 GR.C	Typical
38	FACE2	N81A	N82A		270	Pipe3.5x0.165	Beam	Pipe	A500 GR.C	Typical
39	FACE1	N109	N110		90	Pipe3.5x0.165	Beam	Pipe	A500 GR.C	Typical
40	CR6	N182	N152		270	C3.38x2.06x0...	Beam	Channel	A529 Gr. 50	Typical
41	CR5	N181	N140A		270	C3.38x2.06x0...	Beam	Channel	A529 Gr. 50	Typical
42	CR4	N177A	N122A		90	C3.38x2.06x0...	Beam	Channel	A529 Gr. 50	Typical
43	CR3	N178A	N141		90	C3.38x2.06x0...	Beam	Channel	A529 Gr. 50	Typical
44	CR2	N173	N151		90	C3.38x2.06x0...	Beam	Channel	A529 Gr. 50	Typical
45	CR1	N174	N123A		90	C3.38x2.06x0...	Beam	Channel	A529 Gr. 50	Typical
46	CPL3	N169	N175		90	PL6.5x0.375	Beam	RECT	A1011 36 Ksi	Typical
47	CPL2	N161	N166		270	PL6.5x0.375	Beam	RECT	A1011 36 Ksi	Typical
48	CPL1	N178	N157A		270	PL6.5x0.375	Beam	RECT	A1011 36 Ksi	Typical
49	ANGLE6	P32	P33		90	L2x2x4	Beam	Single Angle	A529 Gr. 50	Typical
50	ANGLE5	P31	P34		180	L2x2x4	Beam	Single Angle	A529 Gr. 50	Typical
51	ANGLE4	P21	P22		90	L2x2x4	Beam	Single Angle	A529 Gr. 50	Typical
52	ANGLE3	P9	P12		180	L2x2x4	Beam	Single Angle	A529 Gr. 50	Typical
53	ANGLE2	P10	P11		270	L2x2x4	Beam	Single Angle	A529 Gr. 50	Typical
54	ANGLE1	P20	P23			L2x2x4	Beam	Single Angle	A529 Gr. 50	Typical
55	42	N180	P18		180	RIGID	None	None	RIGID	Typical
56	41	P30	N177		180	RIGID	None	None	RIGID	Typical





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Primary Data (Continued)**

	Label	I Joint	J Joint	K Joint	Rotate...	Section/Shape	Type	Design List	Material	Design ...
57	40	N171	P29			RIGID	None	None	RIGID	Typical
58	39	P8	N168			RIGID	None	None	RIGID	Typical
59	38	N163	N164			RIGID	None	None	RIGID	Typical
60	37	P19	N160A			RIGID	None	None	RIGID	Typical
61	36	N159	N158		270	RIGID	None	None	RIGID	Typical
62	35	N139A	N138B		90	RIGID	None	None	RIGID	Typical
63	34	N156	N155		270	RIGID	None	None	RIGID	Typical
64	33	N137B	N136A		90	RIGID	None	None	RIGID	Typical
65	32	N132C	P32			RIGID	None	None	RIGID	Typical
66	31	N148	N147		90	RIGID	None	None	RIGID	Typical
67	30	N133C	P33			RIGID	None	None	RIGID	Typical
68	29	N134B	P34			RIGID	None	None	RIGID	Typical
69	28	N131B	P31			RIGID	None	None	RIGID	Typical
70	27	N145	N144		90	RIGID	None	None	RIGID	Typical
71	26	N128B	P21			RIGID	None	None	RIGID	Typical
72	25	N129A	P22			RIGID	None	None	RIGID	Typical
73	24	N130	P23			RIGID	None	None	RIGID	Typical
74	23	N127	P20			RIGID	None	None	RIGID	Typical
75	22	N124A	P10			RIGID	None	None	RIGID	Typical
76	21	N123B	P9			RIGID	None	None	RIGID	Typical
77	20	N126B	P12			RIGID	None	None	RIGID	Typical
78	19	N125B	P11			RIGID	None	None	RIGID	Typical
79	18	N48A	N70A		90	RIGID	None	None	RIGID	Typical
80	17	N45	N69A		90	RIGID	None	None	RIGID	Typical
81	16	N51	N71A		90	RIGID	None	None	RIGID	Typical
82	15	N54	N72A		90	RIGID	None	None	RIGID	Typical
83	14	N72B	N76		90	RIGID	None	None	RIGID	Typical
84	13	N73	N77		90	RIGID	None	None	RIGID	Typical
85	12	N84	N94		270	RIGID	None	None	RIGID	Typical
86	11	N83A	N93		270	RIGID	None	None	RIGID	Typical
87	10	N85	N95		270	RIGID	None	None	RIGID	Typical
88	9	N86	N96		270	RIGID	None	None	RIGID	Typical
89	8	N112	N122		270	RIGID	None	None	RIGID	Typical
90	7	N111	N121		270	RIGID	None	None	RIGID	Typical
91	6	N113	N123		270	RIGID	None	None	RIGID	Typical
92	5	N129B	N133B		270	RIGID	None	None	RIGID	Typical
93	4	N114	N124		270	RIGID	None	None	RIGID	Typical
94	3	N130A	N134A		270	RIGID	None	None	RIGID	Typical
95	2	N135A	N139		270	RIGID	None	None	RIGID	Typical
96	1	N136	N140		270	RIGID	None	None	RIGID	Typical
97	M97	P15	N174			RIGID	None	None	RIGID	Typical
98	M98	P15	N173			RIGID	None	None	RIGID	Typical
99	M99	P4	N178A			RIGID	None	None	RIGID	Typical
100	M100	P4	N177A			RIGID	None	None	RIGID	Typical
101	M101	P26	N182			RIGID	None	None	RIGID	Typical
102	M102	P26	N181			RIGID	None	None	RIGID	Typical

**Member Advanced Data**

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
1	SO3						Yes	Default			None
2	SO2						Yes	Default			None
3	SO1						Yes	Default			None
4	RPL3						Yes	Default			None
5	RPL2						Yes	Default			None
6	RPL1						Yes	Default			None



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Advanced Data (Continued)**

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
7	RAIL3						Yes				None
8	RAIL2						Yes				None
9	RAIL1						Yes				None
10	PL18						Yes	Default			None
11	PL17						Yes				None
12	PL16						Yes	Default			None
13	PL15						Yes				None
14	PL14						Yes	Default			None
15	PL13						Yes				None
16	PL12						Yes	Default			None
17	PL11						Yes	Default			None
18	PL10						Yes				None
19	PL9						Yes				None
20	PL8						Yes	Default			None
21	PL7						Yes				None
22	PL6						Yes	Default			None
23	PL5						Yes				None
24	PL4						Yes	Default			None
25	PL3						Yes				None
26	PL2						Yes	Default			None
27	PL1						Yes				None
28	MP GAMM...						Yes				None
29	MP GAMM...						Yes				None
30	MP GAMM...						Yes				None
31	MP BETA3						Yes				None
32	MP BETA2						Yes				None
33	MP BETA1						Yes				None
34	MP ALPHA3						Yes				None
35	MP ALPHA2						Yes				None
36	MP ALPHA1						Yes				None
37	FACE3						Yes				None
38	FACE2						Yes				None
39	FACE1						Yes	Default			None
40	CR6						Yes	Default			None
41	CR5						Yes	Default			None
42	CR4						Yes	Default			None
43	CR3						Yes	Default			None
44	CR2						Yes	Default			None
45	CR1						Yes	Default			None
46	CPL3						Yes	Default			None
47	CPL2						Yes	Default			None
48	CPL1						Yes	Default			None
49	ANGLE6						Yes				None
50	ANGLE5						Yes				None
51	ANGLE4						Yes				None
52	ANGLE3						Yes	Default			None
53	ANGLE2						Yes				None
54	ANGLE1						Yes				None
55	42		OOOXOO				Yes	** NA **			None
56	41	OOOXOO					Yes	** NA **			None
57	40		OOOXOO				Yes	** NA **			None
58	39	OOOXOO					Yes	** NA **			None
59	38		OOOXOO				Yes	** NA **			None
60	37	OOOXOO					Yes	** NA **			None
61	36	OOOXOO					Yes	** NA **			None
62	35	OOOXOO					Yes	** NA **			None
63	34	OOOXOO					Yes	** NA **			None



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Advanced Data (Continued)**

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat...	Analysis ...	Inactive	Seismic...
64	33	OOOXOO					Yes	** NA **			None
65	32						Yes	** NA **			None
66	31	OOOXOO					Yes	** NA **			None
67	30						Yes	** NA **			None
68	29						Yes	** NA **			None
69	28						Yes	** NA **			None
70	27	OOOXOO					Yes	** NA **			None
71	26						Yes	** NA **			None
72	25						Yes	** NA **			None
73	24						Yes	** NA **			None
74	23						Yes	** NA **			None
75	22						Yes	** NA **			None
76	21						Yes	** NA **			None
77	20						Yes	** NA **			None
78	19						Yes	** NA **			None
79	18						Yes	** NA **			None
80	17						Yes	** NA **			None
81	16						Yes	** NA **			None
82	15						Yes	** NA **			None
83	14						Yes	** NA **			None
84	13						Yes	** NA **			None
85	12						Yes	** NA **			None
86	11						Yes	** NA **			None
87	10						Yes	** NA **			None
88	9						Yes	** NA **			None
89	8						Yes	** NA **			None
90	7						Yes	** NA **			None
91	6						Yes	** NA **			None
92	5						Yes	** NA **			None
93	4						Yes	** NA **			None
94	3						Yes	** NA **			None
95	2						Yes	** NA **			None
96	1						Yes	** NA **			None
97	M97						Yes	** NA **			None
98	M98						Yes	** NA **			None
99	M99						Yes	** NA **			None
100	M100						Yes	** NA **			None
101	M101						Yes	** NA **			None
102	M102						Yes	** NA **			None

**Hot Rolled Steel Properties**

	Label	E [ksi]	G [ksi]	Nu	Therm (/1E...Density[k/ft...	Yield[ksi]	Ry	Fu[ksi]	Rt	
1	A992	29000	11154	.3	.65	.49	50	1.1	65	1.1
2	A36 Gr.36	29000	11154	.3	.65	.49	36	1.5	58	1.2
3	A572 Gr.50	29000	11154	.3	.65	.49	50	1.1	65	1.1
4	A500 Gr.B RND	29000	11154	.3	.65	.527	42	1.4	58	1.3
5	A500 Gr.B Rect	29000	11154	.3	.65	.527	46	1.4	58	1.3
6	A53 Gr.B	29000	11154	.3	.65	.49	35	1.6	60	1.2
7	A1085	29000	11154	.3	.65	.49	50	1.4	65	1.3
8	A913 Gr.65	29000	11154	.3	.65	.49	65	1.1	80	1.1
9	A500 GR.C	29000	11154	.3	.65	.49	46	1.6	60	1.2
10	A529 Gr. 50	29000	11154	.3	.65	.49	50	1.1	65	1.1
11	A1011-33Ksi	29000	11154	.3	.65	.49	33	1.5	58	1.2
12	A1011 36 Ksi	29000	11154	.3	.65	.49	36	1.5	58	1.2
13	A1018 50 Ksi	29000	11154	.3	.65	.49	50	1.5	65	1.2



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 1 : Live Load)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	FACE1	Z	-5	0

**Member Point Loads (BLC 2 : Wind Load (0))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.122	6.5
2	MP ALPHA2	Y	-.122	1.5
3	MP BETA2	Y	-.067	6.5
4	MP BETA2	Y	-.067	1.5
5	MP GAMMA2	Y	-.067	6.5
6	MP GAMMA2	Y	-.067	1.5
7	MP ALPHA2	Y	-.054	4
8	MP BETA2	Y	-.034	4
9	MP GAMMA2	Y	-.034	4
10	MP ALPHA2	Y	-.054	4
11	MP BETA2	Y	-.037	4
12	MP GAMMA2	Y	-.037	4
13	MP ALPHA2	Y	-.055	4

**Member Point Loads (BLC 3 : Dead Load)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Z	-.041	6.5
2	MP ALPHA2	Z	-.041	1.5
3	MP BETA2	Z	-.041	6.5
4	MP BETA2	Z	-.041	1.5
5	MP GAMMA2	Z	-.041	6.5
6	MP GAMMA2	Z	-.041	1.5
7	MP ALPHA2	Z	-.064	4
8	MP BETA2	Z	-.064	4
9	MP GAMMA2	Z	-.064	4
10	MP ALPHA2	Z	-.075	4
11	MP BETA2	Z	-.075	4
12	MP GAMMA2	Z	-.075	4
13	MP ALPHA2	Z	-.022	4

**Member Point Loads (BLC 4 : Wind Load (30))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.09	6.5
2	MP ALPHA2	Y	-.09	1.5
3	MP ALPHA2	X	-.052	6.5
4	MP ALPHA2	X	-.052	1.5
5	MP BETA2	Y	-.042	6.5
6	MP BETA2	Y	-.042	1.5
7	MP BETA2	X	-.024	6.5
8	MP BETA2	X	-.024	1.5
9	MP GAMMA2	Y	-.09	6.5
10	MP GAMMA2	Y	-.09	1.5
11	MP GAMMA2	X	-.052	6.5
12	MP GAMMA2	X	-.052	1.5
13	MP ALPHA2	Y	-.041	4
14	MP ALPHA2	X	-.024	4
15	MP BETA2	Y	-.023	4
16	MP BETA2	X	-.013	4
17	MP GAMMA2	Y	-.041	4
18	MP GAMMA2	X	-.024	4



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 4 : Wind Load (30)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
19	MP ALPHA2	Y	-.042	4
20	MP ALPHA2	X	-.024	4
21	MP BETA2	Y	-.027	4
22	MP BETA2	X	-.015	4
23	MP GAMMA2	Y	-.042	4
24	MP GAMMA2	X	-.024	4
25	MP ALPHA2	Y	-.043	4
26	MP ALPHA2	X	-.025	4

**Member Point Loads (BLC 5 : Wind Load (60))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.034	6.5
2	MP ALPHA2	Y	-.034	1.5
3	MP ALPHA2	X	-.058	6.5
4	MP ALPHA2	X	-.058	1.5
5	MP BETA2	Y	-.034	6.5
6	MP BETA2	Y	-.034	1.5
7	MP BETA2	X	-.058	6.5
8	MP BETA2	X	-.058	1.5
9	MP GAMMA2	Y	-.061	6.5
10	MP GAMMA2	Y	-.061	1.5
11	MP GAMMA2	X	-.106	6.5
12	MP GAMMA2	X	-.106	1.5
13	MP ALPHA2	Y	-.017	4
14	MP ALPHA2	X	-.029	4
15	MP BETA2	Y	-.017	4
16	MP BETA2	X	-.029	4
17	MP GAMMA2	Y	-.027	4
18	MP GAMMA2	X	-.047	4
19	MP ALPHA2	Y	-.018	4
20	MP ALPHA2	X	-.032	4
21	MP BETA2	Y	-.018	4
22	MP BETA2	X	-.032	4
23	MP GAMMA2	Y	-.027	4
24	MP GAMMA2	X	-.047	4
25	MP ALPHA2	Y	-.019	4
26	MP ALPHA2	X	-.033	4

**Member Point Loads (BLC 6 : Wind Load (90))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	X	-.049	6.5
2	MP ALPHA2	X	-.049	1.5
3	MP BETA2	X	-.104	6.5
4	MP BETA2	X	-.104	1.5
5	MP GAMMA2	X	-.104	6.5
6	MP GAMMA2	X	-.104	1.5
7	MP ALPHA2	X	-.027	4
8	MP BETA2	X	-.047	4
9	MP GAMMA2	X	-.047	4
10	MP ALPHA2	X	-.031	4
11	MP BETA2	X	-.048	4
12	MP GAMMA2	X	-.048	4
13	MP ALPHA2	X	-.032	4

**Member Point Loads (BLC 7 : Wind Load (120))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
--	--------------	-----------	-------------------	----------------



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 7 : Wind Load (120)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.034	6.5
2	MP ALPHA2	Y	.034	1.5
3	MP ALPHA2	X	-.058	6.5
4	MP ALPHA2	X	-.058	1.5
5	MP BETA2	Y	.061	6.5
6	MP BETA2	Y	.061	1.5
7	MP BETA2	X	-.106	6.5
8	MP BETA2	X	-.106	1.5
9	MP GAMMA2	Y	.034	6.5
10	MP GAMMA2	Y	.034	1.5
11	MP GAMMA2	X	-.058	6.5
12	MP GAMMA2	X	-.058	1.5
13	MP ALPHA2	Y	.017	4
14	MP ALPHA2	X	-.029	4
15	MP BETA2	Y	.027	4
16	MP BETA2	X	-.047	4
17	MP GAMMA2	Y	.017	4
18	MP GAMMA2	X	-.029	4
19	MP ALPHA2	Y	.018	4
20	MP ALPHA2	X	-.032	4
21	MP BETA2	Y	.027	4
22	MP BETA2	X	-.047	4
23	MP GAMMA2	Y	.018	4
24	MP GAMMA2	X	-.032	4
25	MP ALPHA2	Y	.019	4
26	MP ALPHA2	X	-.033	4

**Member Point Loads (BLC 8 : Wind Load (150))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.09	6.5
2	MP ALPHA2	Y	.09	1.5
3	MP ALPHA2	X	-.052	6.5
4	MP ALPHA2	X	-.052	1.5
5	MP BETA2	Y	.09	6.5
6	MP BETA2	Y	.09	1.5
7	MP BETA2	X	-.052	6.5
8	MP BETA2	X	-.052	1.5
9	MP GAMMA2	Y	.042	6.5
10	MP GAMMA2	Y	.042	1.5
11	MP GAMMA2	X	-.024	6.5
12	MP GAMMA2	X	-.024	1.5
13	MP ALPHA2	Y	.041	4
14	MP ALPHA2	X	-.024	4
15	MP BETA2	Y	.041	4
16	MP BETA2	X	-.024	4
17	MP GAMMA2	Y	.023	4
18	MP GAMMA2	X	-.013	4
19	MP ALPHA2	Y	.042	4
20	MP ALPHA2	X	-.024	4
21	MP BETA2	Y	.042	4
22	MP BETA2	X	-.024	4
23	MP GAMMA2	Y	.027	4
24	MP GAMMA2	X	-.015	4
25	MP ALPHA2	Y	.043	4
26	MP ALPHA2	X	-.025	4



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 9 : Wind Load (180))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.122	6.5
2	MP ALPHA2	Y	.122	1.5
3	MP BETA2	Y	.067	6.5
4	MP BETA2	Y	.067	1.5
5	MP GAMMA2	Y	.067	6.5
6	MP GAMMA2	Y	.067	1.5
7	MP ALPHA2	Y	.054	4
8	MP BETA2	Y	.034	4
9	MP GAMMA2	Y	.034	4
10	MP ALPHA2	Y	.054	4
11	MP BETA2	Y	.037	4
12	MP GAMMA2	Y	.037	4
13	MP ALPHA2	Y	.055	4

**Member Point Loads (BLC 10 : Wind Load (210))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.09	6.5
2	MP ALPHA2	Y	.09	1.5
3	MP ALPHA2	X	.052	6.5
4	MP ALPHA2	X	.052	1.5
5	MP BETA2	Y	.042	6.5
6	MP BETA2	Y	.042	1.5
7	MP BETA2	X	.024	6.5
8	MP BETA2	X	.024	1.5
9	MP GAMMA2	Y	.09	6.5
10	MP GAMMA2	Y	.09	1.5
11	MP GAMMA2	X	.052	6.5
12	MP GAMMA2	X	.052	1.5
13	MP ALPHA2	Y	.041	4
14	MP ALPHA2	X	.024	4
15	MP BETA2	Y	.023	4
16	MP BETA2	X	.013	4
17	MP GAMMA2	Y	.041	4
18	MP GAMMA2	X	.024	4
19	MP ALPHA2	Y	.042	4
20	MP ALPHA2	X	.024	4
21	MP BETA2	Y	.027	4
22	MP BETA2	X	.015	4
23	MP GAMMA2	Y	.042	4
24	MP GAMMA2	X	.024	4
25	MP ALPHA2	Y	.043	4
26	MP ALPHA2	X	.025	4

**Member Point Loads (BLC 11 : Wind Load (240))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.034	6.5
2	MP ALPHA2	Y	.034	1.5
3	MP ALPHA2	X	.058	6.5
4	MP ALPHA2	X	.058	1.5
5	MP BETA2	Y	.034	6.5
6	MP BETA2	Y	.034	1.5
7	MP BETA2	X	.058	6.5
8	MP BETA2	X	.058	1.5
9	MP GAMMA2	Y	.061	6.5
10	MP GAMMA2	Y	.061	1.5
11	MP GAMMA2	X	.106	6.5



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 11 : Wind Load (240)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
12	MP GAMMA2	X	.106	1.5
13	MP ALPHA2	Y	.017	4
14	MP ALPHA2	X	.029	4
15	MP BETA2	Y	.017	4
16	MP BETA2	X	.029	4
17	MP GAMMA2	Y	.027	4
18	MP GAMMA2	X	.047	4
19	MP ALPHA2	Y	.018	4
20	MP ALPHA2	X	.032	4
21	MP BETA2	Y	.018	4
22	MP BETA2	X	.032	4
23	MP GAMMA2	Y	.027	4
24	MP GAMMA2	X	.047	4
25	MP ALPHA2	Y	.019	4
26	MP ALPHA2	X	.033	4

**Member Point Loads (BLC 12 : Wind Load (270))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	X	.049	6.5
2	MP ALPHA2	X	.049	1.5
3	MP BETA2	X	.104	6.5
4	MP BETA2	X	.104	1.5
5	MP GAMMA2	X	.104	6.5
6	MP GAMMA2	X	.104	1.5
7	MP ALPHA2	X	.027	4
8	MP BETA2	X	.047	4
9	MP GAMMA2	X	.047	4
10	MP ALPHA2	X	.031	4
11	MP BETA2	X	.048	4
12	MP GAMMA2	X	.048	4
13	MP ALPHA2	X	.032	4

**Member Point Loads (BLC 13 : Wind Load (300))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.034	6.5
2	MP ALPHA2	Y	-.034	1.5
3	MP ALPHA2	X	.058	6.5
4	MP ALPHA2	X	.058	1.5
5	MP BETA2	Y	-.061	6.5
6	MP BETA2	Y	-.061	1.5
7	MP BETA2	X	.106	6.5
8	MP BETA2	X	.106	1.5
9	MP GAMMA2	Y	-.034	6.5
10	MP GAMMA2	Y	-.034	1.5
11	MP GAMMA2	X	.058	6.5
12	MP GAMMA2	X	.058	1.5
13	MP ALPHA2	Y	-.017	4
14	MP ALPHA2	X	.029	4
15	MP BETA2	Y	-.027	4
16	MP BETA2	X	.047	4
17	MP GAMMA2	Y	-.017	4
18	MP GAMMA2	X	.029	4
19	MP ALPHA2	Y	-.018	4
20	MP ALPHA2	X	.032	4
21	MP BETA2	Y	-.027	4
22	MP BETA2	X	.047	4





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 13 : Wind Load (300)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
23	MP GAMMA2	Y	-.018	4
24	MP GAMMA2	X	.032	4
25	MP ALPHA2	Y	-.019	4
26	MP ALPHA2	X	.033	4

**Member Point Loads (BLC 14 : Wind Load (330))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	-.09	6.5
2	MP ALPHA2	Y	-.09	1.5
3	MP ALPHA2	X	.052	6.5
4	MP ALPHA2	X	.052	1.5
5	MP BETA2	Y	-.09	6.5
6	MP BETA2	Y	-.09	1.5
7	MP BETA2	X	.052	6.5
8	MP BETA2	X	.052	1.5
9	MP GAMMA2	Y	-.042	6.5
10	MP GAMMA2	Y	-.042	1.5
11	MP GAMMA2	X	.024	6.5
12	MP GAMMA2	X	.024	1.5
13	MP ALPHA2	Y	-.041	4
14	MP ALPHA2	X	.024	4
15	MP BETA2	Y	-.041	4
16	MP BETA2	X	.024	4
17	MP GAMMA2	Y	-.023	4
18	MP GAMMA2	X	.013	4
19	MP ALPHA2	Y	-.042	4
20	MP ALPHA2	X	.024	4
21	MP BETA2	Y	-.042	4
22	MP BETA2	X	.024	4
23	MP GAMMA2	Y	-.027	4
24	MP GAMMA2	X	.015	4
25	MP ALPHA2	Y	-.043	4
26	MP ALPHA2	X	.025	4

**Member Point Loads (BLC 15 : Maintenance (0))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	-.007	6.5
2	MP ALPHA2	Y	-.007	1.5
3	MP BETA2	Y	-.004	6.5
4	MP BETA2	Y	-.004	1.5
5	MP GAMMA2	Y	-.004	6.5
6	MP GAMMA2	Y	-.004	1.5
7	MP ALPHA2	Y	-.003	4
8	MP BETA2	Y	-.002	4
9	MP GAMMA2	Y	-.002	4
10	MP ALPHA2	Y	-.003	4
11	MP BETA2	Y	-.002	4
12	MP GAMMA2	Y	-.002	4
13	MP ALPHA2	Y	-.003	4

**Member Point Loads (BLC 16 : Maintenance (30))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	-.005	6.5
2	MP ALPHA2	Y	-.005	1.5
3	MP ALPHA2	X	-.003	6.5



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 16 : Maintenance (30)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
4	MP ALPHA2	X	-.003	1.5
5	MP BETA2	Y	-.003	6.5
6	MP BETA2	Y	-.003	1.5
7	MP BETA2	X	-.001	6.5
8	MP BETA2	X	-.001	1.5
9	MP GAMMA2	Y	-.005	6.5
10	MP GAMMA2	Y	-.005	1.5
11	MP GAMMA2	X	-.003	6.5
12	MP GAMMA2	X	-.003	1.5
13	MP ALPHA2	Y	-.002	4
14	MP ALPHA2	X	-.001	4
15	MP BETA2	Y	-.001	4
16	MP BETA2	X	-.0008	4
17	MP GAMMA2	Y	-.002	4
18	MP GAMMA2	X	-.001	4
19	MP ALPHA2	Y	-.002	4
20	MP ALPHA2	X	-.001	4
21	MP BETA2	Y	-.002	4
22	MP BETA2	X	-.000921	4
23	MP GAMMA2	Y	-.002	4
24	MP GAMMA2	X	-.001	4
25	MP ALPHA2	Y	-.003	4
26	MP ALPHA2	X	-.001	4

**Member Point Loads (BLC 17 : Maintenance (60))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.002	6.5
2	MP ALPHA2	Y	-.002	1.5
3	MP ALPHA2	X	-.003	6.5
4	MP ALPHA2	X	-.003	1.5
5	MP BETA2	Y	-.002	6.5
6	MP BETA2	Y	-.002	1.5
7	MP BETA2	X	-.003	6.5
8	MP BETA2	X	-.003	1.5
9	MP GAMMA2	Y	-.004	6.5
10	MP GAMMA2	Y	-.004	1.5
11	MP GAMMA2	X	-.006	6.5
12	MP GAMMA2	X	-.006	1.5
13	MP ALPHA2	Y	-.001	4
14	MP ALPHA2	X	-.002	4
15	MP BETA2	Y	-.001	4
16	MP BETA2	X	-.002	4
17	MP GAMMA2	Y	-.002	4
18	MP GAMMA2	X	-.003	4
19	MP ALPHA2	Y	-.001	4
20	MP ALPHA2	X	-.002	4
21	MP BETA2	Y	-.001	4
22	MP BETA2	X	-.002	4
23	MP GAMMA2	Y	-.002	4
24	MP GAMMA2	X	-.003	4
25	MP ALPHA2	Y	-.001	4
26	MP ALPHA2	X	-.002	4

**Member Point Loads (BLC 18 : Maintenance (90))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	X	-.003	6.5



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 18 : Maintenance (90)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
2	MP ALPHA2	X	-.003	1.5
3	MP BETA2	X	-.006	6.5
4	MP BETA2	X	-.006	1.5
5	MP GAMMA2	X	-.006	6.5
6	MP GAMMA2	X	-.006	1.5
7	MP ALPHA2	X	-.002	4
8	MP BETA2	X	-.003	4
9	MP GAMMA2	X	-.003	4
10	MP ALPHA2	X	-.002	4
11	MP BETA2	X	-.003	4
12	MP GAMMA2	X	-.003	4
13	MP ALPHA2	X	-.002	4

**Member Point Loads (BLC 19 : Maintenance (120))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.002	6.5
2	MP ALPHA2	Y	.002	1.5
3	MP ALPHA2	X	-.003	6.5
4	MP ALPHA2	X	-.003	1.5
5	MP BETA2	Y	.004	6.5
6	MP BETA2	Y	.004	1.5
7	MP BETA2	X	-.006	6.5
8	MP BETA2	X	-.006	1.5
9	MP GAMMA2	Y	.002	6.5
10	MP GAMMA2	Y	.002	1.5
11	MP GAMMA2	X	-.003	6.5
12	MP GAMMA2	X	-.003	1.5
13	MP ALPHA2	Y	.001	4
14	MP ALPHA2	X	-.002	4
15	MP BETA2	Y	.002	4
16	MP BETA2	X	-.003	4
17	MP GAMMA2	Y	.001	4
18	MP GAMMA2	X	-.002	4
19	MP ALPHA2	Y	.001	4
20	MP ALPHA2	X	-.002	4
21	MP BETA2	Y	.002	4
22	MP BETA2	X	-.003	4
23	MP GAMMA2	Y	.001	4
24	MP GAMMA2	X	-.002	4
25	MP ALPHA2	Y	.001	4
26	MP ALPHA2	X	-.002	4

**Member Point Loads (BLC 20 : Maintenance (150))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.005	6.5
2	MP ALPHA2	Y	.005	1.5
3	MP ALPHA2	X	-.003	6.5
4	MP ALPHA2	X	-.003	1.5
5	MP BETA2	Y	.005	6.5
6	MP BETA2	Y	.005	1.5
7	MP BETA2	X	-.003	6.5
8	MP BETA2	X	-.003	1.5
9	MP GAMMA2	Y	.003	6.5
10	MP GAMMA2	Y	.003	1.5
11	MP GAMMA2	X	-.001	6.5
12	MP GAMMA2	X	-.001	1.5



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 20 : Maintenance (150)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
13	MP ALPHA2	Y	.002	4
14	MP ALPHA2	X	-.001	4
15	MP BETA2	Y	.002	4
16	MP BETA2	X	-.001	4
17	MP GAMMA2	Y	.001	4
18	MP GAMMA2	X	-.0008	4
19	MP ALPHA2	Y	.002	4
20	MP ALPHA2	X	-.001	4
21	MP BETA2	Y	.002	4
22	MP BETA2	X	-.001	4
23	MP GAMMA2	Y	.002	4
24	MP GAMMA2	X	-.000921	4
25	MP ALPHA2	Y	.003	4
26	MP ALPHA2	X	-.001	4

**Member Point Loads (BLC 21 : Maintenance (180))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	.007	6.5
2	MP ALPHA2	Y	.007	1.5
3	MP BETA2	Y	.004	6.5
4	MP BETA2	Y	.004	1.5
5	MP GAMMA2	Y	.004	6.5
6	MP GAMMA2	Y	.004	1.5
7	MP ALPHA2	Y	.003	4
8	MP BETA2	Y	.002	4
9	MP GAMMA2	Y	.002	4
10	MP ALPHA2	Y	.003	4
11	MP BETA2	Y	.002	4
12	MP GAMMA2	Y	.002	4
13	MP ALPHA2	Y	.003	4

**Member Point Loads (BLC 22 : Maintenance (210))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	.005	6.5
2	MP ALPHA2	Y	.005	1.5
3	MP ALPHA2	X	.003	6.5
4	MP ALPHA2	X	.003	1.5
5	MP BETA2	Y	.003	6.5
6	MP BETA2	Y	.003	1.5
7	MP BETA2	X	.001	6.5
8	MP BETA2	X	.001	1.5
9	MP GAMMA2	Y	.005	6.5
10	MP GAMMA2	Y	.005	1.5
11	MP GAMMA2	X	.003	6.5
12	MP GAMMA2	X	.003	1.5
13	MP ALPHA2	Y	.002	4
14	MP ALPHA2	X	.001	4
15	MP BETA2	Y	.001	4
16	MP BETA2	X	.0008	4
17	MP GAMMA2	Y	.002	4
18	MP GAMMA2	X	.001	4
19	MP ALPHA2	Y	.002	4
20	MP ALPHA2	X	.001	4
21	MP BETA2	Y	.002	4
22	MP BETA2	X	.000921	4
23	MP GAMMA2	Y	.002	4



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 22 : Maintenance (210)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
24	MP GAMMA2	X	.001	4
25	MP ALPHA2	Y	.003	4
26	MP ALPHA2	X	.001	4

**Member Point Loads (BLC 23 : Maintenance (240))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	.002	6.5
2	MP ALPHA2	Y	.002	1.5
3	MP ALPHA2	X	.003	6.5
4	MP ALPHA2	X	.003	1.5
5	MP BETA2	Y	.002	6.5
6	MP BETA2	Y	.002	1.5
7	MP BETA2	X	.003	6.5
8	MP BETA2	X	.003	1.5
9	MP GAMMA2	Y	.004	6.5
10	MP GAMMA2	Y	.004	1.5
11	MP GAMMA2	X	.006	6.5
12	MP GAMMA2	X	.006	1.5
13	MP ALPHA2	Y	.001	4
14	MP ALPHA2	X	.002	4
15	MP BETA2	Y	.001	4
16	MP BETA2	X	.002	4
17	MP GAMMA2	Y	.002	4
18	MP GAMMA2	X	.003	4
19	MP ALPHA2	Y	.001	4
20	MP ALPHA2	X	.002	4
21	MP BETA2	Y	.001	4
22	MP BETA2	X	.002	4
23	MP GAMMA2	Y	.002	4
24	MP GAMMA2	X	.003	4
25	MP ALPHA2	Y	.001	4
26	MP ALPHA2	X	.002	4

**Member Point Loads (BLC 24 : Maintenance (270))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	X	.003	6.5
2	MP ALPHA2	X	.003	1.5
3	MP BETA2	X	.006	6.5
4	MP BETA2	X	.006	1.5
5	MP GAMMA2	X	.006	6.5
6	MP GAMMA2	X	.006	1.5
7	MP ALPHA2	X	.002	4
8	MP BETA2	X	.003	4
9	MP GAMMA2	X	.003	4
10	MP ALPHA2	X	.002	4
11	MP BETA2	X	.003	4
12	MP GAMMA2	X	.003	4
13	MP ALPHA2	X	.002	4

**Member Point Loads (BLC 25 : Maintenance (300))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.002	6.5
2	MP ALPHA2	Y	-.002	1.5
3	MP ALPHA2	X	.003	6.5
4	MP ALPHA2	X	.003	1.5



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 25 : Maintenance (300)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
5	MP BETA2	Y	-.004	6.5
6	MP BETA2	Y	-.004	1.5
7	MP BETA2	X	.006	6.5
8	MP BETA2	X	.006	1.5
9	MP GAMMA2	Y	-.002	6.5
10	MP GAMMA2	Y	-.002	1.5
11	MP GAMMA2	X	.003	6.5
12	MP GAMMA2	X	.003	1.5
13	MP ALPHA2	Y	-.001	4
14	MP ALPHA2	X	.002	4
15	MP BETA2	Y	-.002	4
16	MP BETA2	X	.003	4
17	MP GAMMA2	Y	-.001	4
18	MP GAMMA2	X	.002	4
19	MP ALPHA2	Y	-.001	4
20	MP ALPHA2	X	.002	4
21	MP BETA2	Y	-.002	4
22	MP BETA2	X	.003	4
23	MP GAMMA2	Y	-.001	4
24	MP GAMMA2	X	.002	4
25	MP ALPHA2	Y	-.001	4
26	MP ALPHA2	X	.002	4

**Member Point Loads (BLC 26 : Maintenance (330))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.005	6.5
2	MP ALPHA2	Y	-.005	1.5
3	MP ALPHA2	X	.003	6.5
4	MP ALPHA2	X	.003	1.5
5	MP BETA2	Y	-.005	6.5
6	MP BETA2	Y	-.005	1.5
7	MP BETA2	X	.003	6.5
8	MP BETA2	X	.003	1.5
9	MP GAMMA2	Y	-.003	6.5
10	MP GAMMA2	Y	-.003	1.5
11	MP GAMMA2	X	.001	6.5
12	MP GAMMA2	X	.001	1.5
13	MP ALPHA2	Y	-.002	4
14	MP ALPHA2	X	.001	4
15	MP BETA2	Y	-.002	4
16	MP BETA2	X	.001	4
17	MP GAMMA2	Y	-.001	4
18	MP GAMMA2	X	.0008	4
19	MP ALPHA2	Y	-.002	4
20	MP ALPHA2	X	.001	4
21	MP BETA2	Y	-.002	4
22	MP BETA2	X	.001	4
23	MP GAMMA2	Y	-.002	4
24	MP GAMMA2	X	.000921	4
25	MP ALPHA2	Y	-.003	4
26	MP ALPHA2	X	.001	4

**Member Point Loads (BLC 27 : Ice Dead Load)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Z	-.082	6.5
2	MP ALPHA2	Z	-.082	1.5



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 27 : Ice Dead Load) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
3	MP BETA2	Z	-.082	6.5
4	MP BETA2	Z	-.082	1.5
5	MP GAMMA2	Z	-.082	6.5
6	MP GAMMA2	Z	-.082	1.5
7	MP ALPHA2	Z	-.038	4
8	MP BETA2	Z	-.038	4
9	MP GAMMA2	Z	-.038	4
10	MP ALPHA2	Z	-.041	4
11	MP BETA2	Z	-.041	4
12	MP GAMMA2	Z	-.041	4
13	MP ALPHA2	Z	-.04	4

**Member Point Loads (BLC 28 : Ice Wind Load (0))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	-.021	6.5
2	MP ALPHA2	Y	-.021	1.5
3	MP BETA2	Y	-.012	6.5
4	MP BETA2	Y	-.012	1.5
5	MP GAMMA2	Y	-.012	6.5
6	MP GAMMA2	Y	-.012	1.5
7	MP ALPHA2	Y	-.007	4
8	MP BETA2	Y	-.004	4
9	MP GAMMA2	Y	-.004	4
10	MP ALPHA2	Y	-.007	4
11	MP BETA2	Y	-.005	4
12	MP GAMMA2	Y	-.005	4
13	MP ALPHA2	Y	-.007	4

**Member Point Loads (BLC 29 : Ice Wind Load (30))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	-.015	6.5
2	MP ALPHA2	Y	-.015	1.5
3	MP ALPHA2	X	-.009	6.5
4	MP ALPHA2	X	-.009	1.5
5	MP BETA2	Y	-.008	6.5
6	MP BETA2	Y	-.008	1.5
7	MP BETA2	X	-.005	6.5
8	MP BETA2	X	-.005	1.5
9	MP GAMMA2	Y	-.015	6.5
10	MP GAMMA2	Y	-.015	1.5
11	MP GAMMA2	X	-.009	6.5
12	MP GAMMA2	X	-.009	1.5
13	MP ALPHA2	Y	-.005	4
14	MP ALPHA2	X	-.003	4
15	MP BETA2	Y	-.003	4
16	MP BETA2	X	-.002	4
17	MP GAMMA2	Y	-.005	4
18	MP GAMMA2	X	-.003	4
19	MP ALPHA2	Y	-.005	4
20	MP ALPHA2	X	-.003	4
21	MP BETA2	Y	-.004	4
22	MP BETA2	X	-.002	4
23	MP GAMMA2	Y	-.005	4
24	MP GAMMA2	X	-.003	4
25	MP ALPHA2	Y	-.005	4
26	MP ALPHA2	X	-.003	4



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 30 : Ice Wind Load (60))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	-.006	6.5
2	MP ALPHA2	Y	-.006	1.5
3	MP ALPHA2	X	-.011	6.5
4	MP ALPHA2	X	-.011	1.5
5	MP BETA2	Y	-.006	6.5
6	MP BETA2	Y	-.006	1.5
7	MP BETA2	X	-.011	6.5
8	MP BETA2	X	-.011	1.5
9	MP GAMMA2	Y	-.01	6.5
10	MP GAMMA2	Y	-.01	1.5
11	MP GAMMA2	X	-.018	6.5
12	MP GAMMA2	X	-.018	1.5
13	MP ALPHA2	Y	-.002	4
14	MP ALPHA2	X	-.004	4
15	MP BETA2	Y	-.002	4
16	MP BETA2	X	-.004	4
17	MP GAMMA2	Y	-.003	4
18	MP GAMMA2	X	-.006	4
19	MP ALPHA2	Y	-.002	4
20	MP ALPHA2	X	-.004	4
21	MP BETA2	Y	-.002	4
22	MP BETA2	X	-.004	4
23	MP GAMMA2	Y	-.003	4
24	MP GAMMA2	X	-.006	4
25	MP ALPHA2	Y	-.002	4
26	MP ALPHA2	X	-.004	4

**Member Point Loads (BLC 31 : Ice Wind Load (90))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	X	-.009	6.5
2	MP ALPHA2	X	-.009	1.5
3	MP BETA2	X	-.018	6.5
4	MP BETA2	X	-.018	1.5
5	MP GAMMA2	X	-.018	6.5
6	MP GAMMA2	X	-.018	1.5
7	MP ALPHA2	X	-.004	4
8	MP BETA2	X	-.006	4
9	MP GAMMA2	X	-.006	4
10	MP ALPHA2	X	-.004	4
11	MP BETA2	X	-.006	4
12	MP GAMMA2	X	-.006	4
13	MP ALPHA2	X	-.004	4

**Member Point Loads (BLC 32 : Ice Wind Load (120))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.006	6.5
2	MP ALPHA2	Y	.006	1.5
3	MP ALPHA2	X	-.011	6.5
4	MP ALPHA2	X	-.011	1.5
5	MP BETA2	Y	.01	6.5
6	MP BETA2	Y	.01	1.5
7	MP BETA2	X	-.018	6.5
8	MP BETA2	X	-.018	1.5
9	MP GAMMA2	Y	.006	6.5
10	MP GAMMA2	Y	.006	1.5
11	MP GAMMA2	X	-.011	6.5





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 32 : Ice Wind Load (120)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
12	MP GAMMA2	X	-.011	1.5
13	MP ALPHA2	Y	.002	4
14	MP ALPHA2	X	-.004	4
15	MP BETA2	Y	.003	4
16	MP BETA2	X	-.006	4
17	MP GAMMA2	Y	.002	4
18	MP GAMMA2	X	-.004	4
19	MP ALPHA2	Y	.002	4
20	MP ALPHA2	X	-.004	4
21	MP BETA2	Y	.003	4
22	MP BETA2	X	-.006	4
23	MP GAMMA2	Y	.002	4
24	MP GAMMA2	X	-.004	4
25	MP ALPHA2	Y	.002	4
26	MP ALPHA2	X	-.004	4

**Member Point Loads (BLC 33 : Ice Wind Load (150))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.015	6.5
2	MP ALPHA2	Y	.015	1.5
3	MP ALPHA2	X	-.009	6.5
4	MP ALPHA2	X	-.009	1.5
5	MP BETA2	Y	.015	6.5
6	MP BETA2	Y	.015	1.5
7	MP BETA2	X	-.009	6.5
8	MP BETA2	X	-.009	1.5
9	MP GAMMA2	Y	.008	6.5
10	MP GAMMA2	Y	.008	1.5
11	MP GAMMA2	X	-.005	6.5
12	MP GAMMA2	X	-.005	1.5
13	MP ALPHA2	Y	.005	4
14	MP ALPHA2	X	-.003	4
15	MP BETA2	Y	.005	4
16	MP BETA2	X	-.003	4
17	MP GAMMA2	Y	.003	4
18	MP GAMMA2	X	-.002	4
19	MP ALPHA2	Y	.005	4
20	MP ALPHA2	X	-.003	4
21	MP BETA2	Y	.005	4
22	MP BETA2	X	-.003	4
23	MP GAMMA2	Y	.004	4
24	MP GAMMA2	X	-.002	4
25	MP ALPHA2	Y	.005	4
26	MP ALPHA2	X	-.003	4

**Member Point Loads (BLC 34 : Ice Wind Load (180))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.021	6.5
2	MP ALPHA2	Y	.021	1.5
3	MP BETA2	Y	.012	6.5
4	MP BETA2	Y	.012	1.5
5	MP GAMMA2	Y	.012	6.5
6	MP GAMMA2	Y	.012	1.5
7	MP ALPHA2	Y	.007	4
8	MP BETA2	Y	.004	4
9	MP GAMMA2	Y	.004	4



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 34 : Ice Wind Load (180)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
10	MP ALPHA2	Y	.007	4
11	MP BETA2	Y	.005	4
12	MP GAMMA2	Y	.005	4
13	MP ALPHA2	Y	.007	4

**Member Point Loads (BLC 35 : Ice Wind Load (210))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.015	6.5
2	MP ALPHA2	Y	.015	1.5
3	MP ALPHA2	X	.009	6.5
4	MP ALPHA2	X	.009	1.5
5	MP BETA2	Y	.008	6.5
6	MP BETA2	Y	.008	1.5
7	MP BETA2	X	.005	6.5
8	MP BETA2	X	.005	1.5
9	MP GAMMA2	Y	.015	6.5
10	MP GAMMA2	Y	.015	1.5
11	MP GAMMA2	X	.009	6.5
12	MP GAMMA2	X	.009	1.5
13	MP ALPHA2	Y	.005	4
14	MP ALPHA2	X	.003	4
15	MP BETA2	Y	.003	4
16	MP BETA2	X	.002	4
17	MP GAMMA2	Y	.005	4
18	MP GAMMA2	X	.003	4
19	MP ALPHA2	Y	.005	4
20	MP ALPHA2	X	.003	4
21	MP BETA2	Y	.004	4
22	MP BETA2	X	.002	4
23	MP GAMMA2	Y	.005	4
24	MP GAMMA2	X	.003	4
25	MP ALPHA2	Y	.005	4
26	MP ALPHA2	X	.003	4

**Member Point Loads (BLC 36 : Ice Wind Load (240))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	.006	6.5
2	MP ALPHA2	Y	.006	1.5
3	MP ALPHA2	X	.011	6.5
4	MP ALPHA2	X	.011	1.5
5	MP BETA2	Y	.006	6.5
6	MP BETA2	Y	.006	1.5
7	MP BETA2	X	.011	6.5
8	MP BETA2	X	.011	1.5
9	MP GAMMA2	Y	.01	6.5
10	MP GAMMA2	Y	.01	1.5
11	MP GAMMA2	X	.018	6.5
12	MP GAMMA2	X	.018	1.5
13	MP ALPHA2	Y	.002	4
14	MP ALPHA2	X	.004	4
15	MP BETA2	Y	.002	4
16	MP BETA2	X	.004	4
17	MP GAMMA2	Y	.003	4
18	MP GAMMA2	X	.006	4
19	MP ALPHA2	Y	.002	4
20	MP ALPHA2	X	.004	4



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 36 : Ice Wind Load (240)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
21	MP BETA2	Y	.002	4
22	MP BETA2	X	.004	4
23	MP GAMMA2	Y	.003	4
24	MP GAMMA2	X	.006	4
25	MP ALPHA2	Y	.002	4
26	MP ALPHA2	X	.004	4

**Member Point Loads (BLC 37 : Ice Wind Load (270))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	X	.009	6.5
2	MP ALPHA2	X	.009	1.5
3	MP BETA2	X	.018	6.5
4	MP BETA2	X	.018	1.5
5	MP GAMMA2	X	.018	6.5
6	MP GAMMA2	X	.018	1.5
7	MP ALPHA2	X	.004	4
8	MP BETA2	X	.006	4
9	MP GAMMA2	X	.006	4
10	MP ALPHA2	X	.004	4
11	MP BETA2	X	.006	4
12	MP GAMMA2	X	.006	4
13	MP ALPHA2	X	.004	4

**Member Point Loads (BLC 38 : Ice Wind Load (300))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.006	6.5
2	MP ALPHA2	Y	-.006	1.5
3	MP ALPHA2	X	.011	6.5
4	MP ALPHA2	X	.011	1.5
5	MP BETA2	Y	-.01	6.5
6	MP BETA2	Y	-.01	1.5
7	MP BETA2	X	.018	6.5
8	MP BETA2	X	.018	1.5
9	MP GAMMA2	Y	-.006	6.5
10	MP GAMMA2	Y	-.006	1.5
11	MP GAMMA2	X	.011	6.5
12	MP GAMMA2	X	.011	1.5
13	MP ALPHA2	Y	-.002	4
14	MP ALPHA2	X	.004	4
15	MP BETA2	Y	-.003	4
16	MP BETA2	X	.006	4
17	MP GAMMA2	Y	-.002	4
18	MP GAMMA2	X	.004	4
19	MP ALPHA2	Y	-.002	4
20	MP ALPHA2	X	.004	4
21	MP BETA2	Y	-.003	4
22	MP BETA2	X	.006	4
23	MP GAMMA2	Y	-.002	4
24	MP GAMMA2	X	.004	4
25	MP ALPHA2	Y	-.002	4
26	MP ALPHA2	X	.004	4

**Member Point Loads (BLC 39 : Ice Wind Load (330))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Y	-.015	6.5

**Member Point Loads (BLC 39 : Ice Wind Load (330)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
2	MP ALPHA2	Y	-.015	1.5
3	MP ALPHA2	X	.009	6.5
4	MP ALPHA2	X	.009	1.5
5	MP BETA2	Y	-.015	6.5
6	MP BETA2	Y	-.015	1.5
7	MP BETA2	X	.009	6.5
8	MP BETA2	X	.009	1.5
9	MP GAMMA2	Y	-.008	6.5
10	MP GAMMA2	Y	-.008	1.5
11	MP GAMMA2	X	.005	6.5
12	MP GAMMA2	X	.005	1.5
13	MP ALPHA2	Y	-.005	4
14	MP ALPHA2	X	.003	4
15	MP BETA2	Y	-.005	4
16	MP BETA2	X	.003	4
17	MP GAMMA2	Y	-.003	4
18	MP GAMMA2	X	.002	4
19	MP ALPHA2	Y	-.005	4
20	MP ALPHA2	X	.003	4
21	MP BETA2	Y	-.005	4
22	MP BETA2	X	.003	4
23	MP GAMMA2	Y	-.004	4
24	MP GAMMA2	X	.002	4
25	MP ALPHA2	Y	-.005	4
26	MP ALPHA2	X	.003	4

**Member Point Loads (BLC 40 : Earthquake (x-direction))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	X	-.004	6.5
2	MP ALPHA2	X	-.004	1.5
3	MP BETA2	X	-.004	6.5
4	MP BETA2	X	-.004	1.5
5	MP GAMMA2	X	-.004	6.5
6	MP GAMMA2	X	-.004	1.5
7	MP ALPHA2	X	-.006	4
8	MP BETA2	X	-.006	4
9	MP GAMMA2	X	-.006	4
10	MP ALPHA2	X	-.007	4
11	MP BETA2	X	-.007	4
12	MP GAMMA2	X	-.007	4
13	MP ALPHA2	X	-.002	4

**Member Point Loads (BLC 41 : Earthquake (y-direction))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft, %]
1	MP ALPHA2	Y	-.004	6.5
2	MP ALPHA2	Y	-.004	1.5
3	MP BETA2	Y	-.004	6.5
4	MP BETA2	Y	-.004	1.5
5	MP GAMMA2	Y	-.004	6.5
6	MP GAMMA2	Y	-.004	1.5
7	MP ALPHA2	Y	-.006	4
8	MP BETA2	Y	-.006	4
9	MP GAMMA2	Y	-.006	4
10	MP ALPHA2	Y	-.007	4
11	MP BETA2	Y	-.007	4
12	MP GAMMA2	Y	-.007	4



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Point Loads (BLC 41 : Earthquake (y-direction)) (Continued)**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
13	MP ALPHA2	Y	-0.002	4

**Member Point Loads (BLC 42 : Earthquake (z-direction))**

	Member Label	Direction	Magnitude[k,k-ft]	Location[ft,%]
1	MP ALPHA2	Z	-0.002	6.5
2	MP ALPHA2	Z	-0.002	1.5
3	MP BETA2	Z	-0.002	6.5
4	MP BETA2	Z	-0.002	1.5
5	MP GAMMA2	Z	-0.002	6.5
6	MP GAMMA2	Z	-0.002	1.5
7	MP ALPHA2	Z	-0.003	4
8	MP BETA2	Z	-0.003	4
9	MP GAMMA2	Z	-0.003	4
10	MP ALPHA2	Z	-0.003	4
11	MP BETA2	Z	-0.003	4
12	MP GAMMA2	Z	-0.003	4
13	MP ALPHA2	Z	-0.000858	4

**Member Distributed Loads (BLC 2 : Wind Load (0))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft,%]	End Location[ft,%]
1	SO3	PY	-0.006	-0.006	0	0
2	SO2	PY	-0.006	-0.006	0	0
3	SO1	PY	-0.006	-0.006	0	0
4	RPL3	PY	-0.01	-0.01	0	0
5	RPL2	PY	-0.01	-0.01	0	0
6	RPL1	PY	-0.01	-0.01	0	0
7	RAIL3	PY	-0.005	-0.005	0	0
8	RAIL2	PY	-0.005	-0.005	0	0
9	RAIL1	PY	-0.002	-0.002	0	0
10	PL18	PY	-0.001	-0.001	0	0
11	PL17	PY	-0.001	-0.001	0	0
12	PL16	PY	-0.001	-0.001	0	0
13	PL15	PY	-0.001	-0.001	0	0
14	PL14	PY	-0.001	-0.001	0	0
15	PL13	PY	-0.001	-0.001	0	0
16	PL12	PY	-0.001	-0.001	0	0
17	PL11	PY	-0.001	-0.001	0	0
18	PL10	PY	-0.001	-0.001	0	0
19	PL9	PY	-0.001	-0.001	0	0
20	PL8	PY	-0.001	-0.001	0	0
21	PL7	PY	-0.001	-0.001	0	0
22	PL6	PY	-0.001	-0.001	0	0
23	PL5	PY	-0.001	-0.001	0	0
24	PL4	PY	-0.001	-0.001	0	0
25	PL3	PY	-0.001	-0.001	0	0
26	PL2	PY	-0.001	-0.001	0	0
27	PL1	PY	-0.001	-0.001	0	0
28	MP GAMMA3	PY	-0.008	-0.008	0	0
29	MP GAMMA2	PY	-0.008	-0.008	0	0
30	MP GAMMA1	PY	-0.008	-0.008	0	0
31	MP BETA3	PY	-0.008	-0.008	0	0
32	MP BETA2	PY	-0.008	-0.008	0	0
33	MP BETA1	PY	-0.008	-0.008	0	0
34	MP ALPHA3	PY	-0.008	-0.008	0	0
35	MP ALPHA2	PY	-0.008	-0.008	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 2 : Wind Load (0)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
36	MP ALPHA1	PY	-0.008	-0.008	0	0
37	FACE3	PY	-0.006	-0.006	0	0
38	FACE2	PY	-0.006	-0.006	0	0
39	FACE1	PY	-0.003	-0.003	0	0
40	CR6	PY	-0.008	-0.008	0	0
41	CR5	PY	-0.008	-0.008	0	0
42	CR4	PY	-0.008	-0.008	0	0
43	CR3	PY	-0.008	-0.008	0	0
44	CR2	PY	-0.008	-0.008	0	0
45	CR1	PY	-0.008	-0.008	0	0
46	CPL3	PY	-0.000857	-0.000857	0	0
47	CPL2	PY	-0.000857	-0.000857	0	0
48	CPL1	PY	-0.000857	-0.000857	0	0
49	ANGLE6	PY	-0.005	-0.005	0	0
50	ANGLE5	PY	-0.005	-0.005	0	0
51	ANGLE4	PY	-0.005	-0.005	0	0
52	ANGLE3	PY	-0.005	-0.005	0	0
53	ANGLE2	PY	-0.005	-0.005	0	0
54	ANGLE1	PY	-0.005	-0.005	0	0

**Member Distributed Loads (BLC 4 : Wind Load (30))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-0.005	-0.005	0	0
2	SO2	PY	-0.005	-0.005	0	0
3	SO1	PY	-0.005	-0.005	0	0
4	RPL3	PY	-0.009	-0.009	0	0
5	RPL2	PY	-0.009	-0.009	0	0
6	RPL1	PY	-0.009	-0.009	0	0
7	RAIL3	PY	-0.004	-0.004	0	0
8	RAIL2	PY	-0.004	-0.004	0	0
9	RAIL1	PY	-0.002	-0.002	0	0
10	PL18	PY	-0.000989	-0.000989	0	0
11	PL17	PY	-0.000989	-0.000989	0	0
12	PL16	PY	-0.000989	-0.000989	0	0
13	PL15	PY	-0.000989	-0.000989	0	0
14	PL14	PY	-0.000989	-0.000989	0	0
15	PL13	PY	-0.000989	-0.000989	0	0
16	PL12	PY	-0.000989	-0.000989	0	0
17	PL11	PY	-0.000989	-0.000989	0	0
18	PL10	PY	-0.000989	-0.000989	0	0
19	PL9	PY	-0.000989	-0.000989	0	0
20	PL8	PY	-0.000989	-0.000989	0	0
21	PL7	PY	-0.000989	-0.000989	0	0
22	PL6	PY	-0.000989	-0.000989	0	0
23	PL5	PY	-0.000989	-0.000989	0	0
24	PL4	PY	-0.000989	-0.000989	0	0
25	PL3	PY	-0.000989	-0.000989	0	0
26	PL2	PY	-0.000989	-0.000989	0	0
27	PL1	PY	-0.000989	-0.000989	0	0
28	MP GAMMA3	PY	-0.007	-0.007	0	0
29	MP GAMMA2	PY	-0.007	-0.007	0	0
30	MP GAMMA1	PY	-0.007	-0.007	0	0
31	MP BETA3	PY	-0.007	-0.007	0	0
32	MP BETA2	PY	-0.007	-0.007	0	0
33	MP BETA1	PY	-0.007	-0.007	0	0
34	MP ALPHA3	PY	-0.007	-0.007	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 4 : Wind Load (30)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
35	MP ALPHA2	PY	-0.007	-0.007	0	0
36	MP ALPHA1	PY	-0.007	-0.007	0	0
37	FACE3	PY	-0.005	-0.005	0	0
38	FACE2	PY	-0.005	-0.005	0	0
39	FACE1	PY	-0.002	-0.002	0	0
40	CR6	PY	-0.007	-0.007	0	0
41	CR5	PY	-0.007	-0.007	0	0
42	CR4	PY	-0.007	-0.007	0	0
43	CR3	PY	-0.007	-0.007	0	0
44	CR2	PY	-0.007	-0.007	0	0
45	CR1	PY	-0.007	-0.007	0	0
46	CPL3	PY	-0.000742	-0.000742	0	0
47	CPL2	PY	-0.000742	-0.000742	0	0
48	CPL1	PY	-0.000742	-0.000742	0	0
49	ANGLE6	PY	-0.004	-0.004	0	0
50	ANGLE5	PY	-0.004	-0.004	0	0
51	ANGLE4	PY	-0.004	-0.004	0	0
52	ANGLE3	PY	-0.004	-0.004	0	0
53	ANGLE2	PY	-0.004	-0.004	0	0
54	ANGLE1	PY	-0.004	-0.004	0	0
55	SO3	PX	-0.003	-0.003	0	0
56	SO2	PX	-0.003	-0.003	0	0
57	SO1	PX	-0.003	-0.003	0	0
58	RPL3	PX	-0.005	-0.005	0	0
59	RPL2	PX	-0.005	-0.005	0	0
60	RPL1	PX	-0.005	-0.005	0	0
61	RAIL3	PX	-0.002	-0.002	0	0
62	RAIL2	PX	-0.002	-0.002	0	0
63	RAIL1	PX	-0.001	-0.001	0	0
64	PL18	PX	-0.000571	-0.000571	0	0
65	PL17	PX	-0.000571	-0.000571	0	0
66	PL16	PX	-0.000571	-0.000571	0	0
67	PL15	PX	-0.000571	-0.000571	0	0
68	PL14	PX	-0.000571	-0.000571	0	0
69	PL13	PX	-0.000571	-0.000571	0	0
70	PL12	PX	-0.000571	-0.000571	0	0
71	PL11	PX	-0.000571	-0.000571	0	0
72	PL10	PX	-0.000571	-0.000571	0	0
73	PL9	PX	-0.000571	-0.000571	0	0
74	PL8	PX	-0.000571	-0.000571	0	0
75	PL7	PX	-0.000571	-0.000571	0	0
76	PL6	PX	-0.000571	-0.000571	0	0
77	PL5	PX	-0.000571	-0.000571	0	0
78	PL4	PX	-0.000571	-0.000571	0	0
79	PL3	PX	-0.000571	-0.000571	0	0
80	PL2	PX	-0.000571	-0.000571	0	0
81	PL1	PX	-0.000571	-0.000571	0	0
82	MP GAMMA3	PX	-0.004	-0.004	0	0
83	MP GAMMA2	PX	-0.004	-0.004	0	0
84	MP GAMMA1	PX	-0.004	-0.004	0	0
85	MP BETA3	PX	-0.004	-0.004	0	0
86	MP BETA2	PX	-0.004	-0.004	0	0
87	MP BETA1	PX	-0.004	-0.004	0	0
88	MP ALPHA3	PX	-0.004	-0.004	0	0
89	MP ALPHA2	PX	-0.004	-0.004	0	0
90	MP ALPHA1	PX	-0.004	-0.004	0	0
91	FACE3	PX	-0.003	-0.003	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 4 : Wind Load (30)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
92	FACE2	PX	-0.003	-0.003	0	0
93	FACE1	PX	-0.001	-0.001	0	0
94	CR6	PX	-0.004	-0.004	0	0
95	CR5	PX	-0.004	-0.004	0	0
96	CR4	PX	-0.004	-0.004	0	0
97	CR3	PX	-0.004	-0.004	0	0
98	CR2	PX	-0.004	-0.004	0	0
99	CR1	PX	-0.004	-0.004	0	0
100	CPL3	PX	-0.000428	-0.000428	0	0
101	CPL2	PX	-0.000428	-0.000428	0	0
102	CPL1	PX	-0.000428	-0.000428	0	0
103	ANGLE6	PX	-0.002	-0.002	0	0
104	ANGLE5	PX	-0.002	-0.002	0	0
105	ANGLE4	PX	-0.002	-0.002	0	0
106	ANGLE3	PX	-0.002	-0.002	0	0
107	ANGLE2	PX	-0.002	-0.002	0	0
108	ANGLE1	PX	-0.002	-0.002	0	0

**Member Distributed Loads (BLC 5 : Wind Load (60))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-0.003	-0.003	0	0
2	SO2	PY	-0.003	-0.003	0	0
3	SO1	PY	-0.003	-0.003	0	0
4	RPL3	PY	-0.005	-0.005	0	0
5	RPL2	PY	-0.005	-0.005	0	0
6	RPL1	PY	-0.005	-0.005	0	0
7	RAIL3	PY	-0.002	-0.002	0	0
8	RAIL2	PY	-0.002	-0.002	0	0
9	RAIL1	PY	-0.001	-0.001	0	0
10	PL18	PY	-0.000571	-0.000571	0	0
11	PL17	PY	-0.000571	-0.000571	0	0
12	PL16	PY	-0.000571	-0.000571	0	0
13	PL15	PY	-0.000571	-0.000571	0	0
14	PL14	PY	-0.000571	-0.000571	0	0
15	PL13	PY	-0.000571	-0.000571	0	0
16	PL12	PY	-0.000571	-0.000571	0	0
17	PL11	PY	-0.000571	-0.000571	0	0
18	PL10	PY	-0.000571	-0.000571	0	0
19	PL9	PY	-0.000571	-0.000571	0	0
20	PL8	PY	-0.000571	-0.000571	0	0
21	PL7	PY	-0.000571	-0.000571	0	0
22	PL6	PY	-0.000571	-0.000571	0	0
23	PL5	PY	-0.000571	-0.000571	0	0
24	PL4	PY	-0.000571	-0.000571	0	0
25	PL3	PY	-0.000571	-0.000571	0	0
26	PL2	PY	-0.000571	-0.000571	0	0
27	PL1	PY	-0.000571	-0.000571	0	0
28	MP GAMMA3	PY	-0.004	-0.004	0	0
29	MP GAMMA2	PY	-0.004	-0.004	0	0
30	MP GAMMA1	PY	-0.004	-0.004	0	0
31	MP BETA3	PY	-0.004	-0.004	0	0
32	MP BETA2	PY	-0.004	-0.004	0	0
33	MP BETA1	PY	-0.004	-0.004	0	0
34	MP ALPHA3	PY	-0.004	-0.004	0	0
35	MP ALPHA2	PY	-0.004	-0.004	0	0
36	MP ALPHA1	PY	-0.004	-0.004	0	0





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 5 : Wind Load (60)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
37	FACE3	PY	-0.003	-0.003	0 0
38	FACE2	PY	-0.003	-0.003	0 0
39	FACE1	PY	-0.001	-0.001	0 0
40	CR6	PY	-0.004	-0.004	0 0
41	CR5	PY	-0.004	-0.004	0 0
42	CR4	PY	-0.004	-0.004	0 0
43	CR3	PY	-0.004	-0.004	0 0
44	CR2	PY	-0.004	-0.004	0 0
45	CR1	PY	-0.004	-0.004	0 0
46	CPL3	PY	-0.000428	-0.000428	0 0
47	CPL2	PY	-0.000428	-0.000428	0 0
48	CPL1	PY	-0.000428	-0.000428	0 0
49	ANGLE6	PY	-0.002	-0.002	0 0
50	ANGLE5	PY	-0.002	-0.002	0 0
51	ANGLE4	PY	-0.002	-0.002	0 0
52	ANGLE3	PY	-0.002	-0.002	0 0
53	ANGLE2	PY	-0.002	-0.002	0 0
54	ANGLE1	PY	-0.002	-0.002	0 0
55	SO3	PX	-0.005	-0.005	0 0
56	SO2	PX	-0.005	-0.005	0 0
57	SO1	PX	-0.005	-0.005	0 0
58	RPL3	PX	-0.009	-0.009	0 0
59	RPL2	PX	-0.009	-0.009	0 0
60	RPL1	PX	-0.009	-0.009	0 0
61	RAIL3	PX	-0.004	-0.004	0 0
62	RAIL2	PX	-0.004	-0.004	0 0
63	RAIL1	PX	-0.002	-0.002	0 0
64	PL18	PX	-0.000989	-0.000989	0 0
65	PL17	PX	-0.000989	-0.000989	0 0
66	PL16	PX	-0.000989	-0.000989	0 0
67	PL15	PX	-0.000989	-0.000989	0 0
68	PL14	PX	-0.000989	-0.000989	0 0
69	PL13	PX	-0.000989	-0.000989	0 0
70	PL12	PX	-0.000989	-0.000989	0 0
71	PL11	PX	-0.000989	-0.000989	0 0
72	PL10	PX	-0.000989	-0.000989	0 0
73	PL9	PX	-0.000989	-0.000989	0 0
74	PL8	PX	-0.000989	-0.000989	0 0
75	PL7	PX	-0.000989	-0.000989	0 0
76	PL6	PX	-0.000989	-0.000989	0 0
77	PL5	PX	-0.000989	-0.000989	0 0
78	PL4	PX	-0.000989	-0.000989	0 0
79	PL3	PX	-0.000989	-0.000989	0 0
80	PL2	PX	-0.000989	-0.000989	0 0
81	PL1	PX	-0.000989	-0.000989	0 0
82	MP GAMMA3	PX	-0.007	-0.007	0 0
83	MP GAMMA2	PX	-0.007	-0.007	0 0
84	MP GAMMA1	PX	-0.007	-0.007	0 0
85	MP BETA3	PX	-0.007	-0.007	0 0
86	MP BETA2	PX	-0.007	-0.007	0 0
87	MP BETA1	PX	-0.007	-0.007	0 0
88	MP ALPHA3	PX	-0.007	-0.007	0 0
89	MP ALPHA2	PX	-0.007	-0.007	0 0
90	MP ALPHA1	PX	-0.007	-0.007	0 0
91	FACE3	PX	-0.005	-0.005	0 0
92	FACE2	PX	-0.005	-0.005	0 0
93	FACE1	PX	-0.002	-0.002	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 5 : Wind Load (60)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
94	CR6	PX	-0.007	-0.007	0	0
95	CR5	PX	-0.007	-0.007	0	0
96	CR4	PX	-0.007	-0.007	0	0
97	CR3	PX	-0.007	-0.007	0	0
98	CR2	PX	-0.007	-0.007	0	0
99	CR1	PX	-0.007	-0.007	0	0
100	CPL3	PX	-0.000742	-0.000742	0	0
101	CPL2	PX	-0.000742	-0.000742	0	0
102	CPL1	PX	-0.000742	-0.000742	0	0
103	ANGLE6	PX	-0.004	-0.004	0	0
104	ANGLE5	PX	-0.004	-0.004	0	0
105	ANGLE4	PX	-0.004	-0.004	0	0
106	ANGLE3	PX	-0.004	-0.004	0	0
107	ANGLE2	PX	-0.004	-0.004	0	0
108	ANGLE1	PX	-0.004	-0.004	0	0

**Member Distributed Loads (BLC 6 : Wind Load (90))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PX	-0.006	-0.006	0	0
2	SO2	PX	-0.006	-0.006	0	0
3	SO1	PX	-0.006	-0.006	0	0
4	RPL3	PX	-0.01	-0.01	0	0
5	RPL2	PX	-0.01	-0.01	0	0
6	RPL1	PX	-0.01	-0.01	0	0
7	RAIL3	PX	-0.005	-0.005	0	0
8	RAIL2	PX	-0.005	-0.005	0	0
9	RAIL1	PX	-0.002	-0.002	0	0
10	PL18	PX	-0.001	-0.001	0	0
11	PL17	PX	-0.001	-0.001	0	0
12	PL16	PX	-0.001	-0.001	0	0
13	PL15	PX	-0.001	-0.001	0	0
14	PL14	PX	-0.001	-0.001	0	0
15	PL13	PX	-0.001	-0.001	0	0
16	PL12	PX	-0.001	-0.001	0	0
17	PL11	PX	-0.001	-0.001	0	0
18	PL10	PX	-0.001	-0.001	0	0
19	PL9	PX	-0.001	-0.001	0	0
20	PL8	PX	-0.001	-0.001	0	0
21	PL7	PX	-0.001	-0.001	0	0
22	PL6	PX	-0.001	-0.001	0	0
23	PL5	PX	-0.001	-0.001	0	0
24	PL4	PX	-0.001	-0.001	0	0
25	PL3	PX	-0.001	-0.001	0	0
26	PL2	PX	-0.001	-0.001	0	0
27	PL1	PX	-0.001	-0.001	0	0
28	MP GAMMA3	PX	-0.008	-0.008	0	0
29	MP GAMMA2	PX	-0.008	-0.008	0	0
30	MP GAMMA1	PX	-0.008	-0.008	0	0
31	MP BETA3	PX	-0.008	-0.008	0	0
32	MP BETA2	PX	-0.008	-0.008	0	0
33	MP BETA1	PX	-0.008	-0.008	0	0
34	MP ALPHA3	PX	-0.008	-0.008	0	0
35	MP ALPHA2	PX	-0.008	-0.008	0	0
36	MP ALPHA1	PX	-0.008	-0.008	0	0
37	FACE3	PX	-0.006	-0.006	0	0
38	FACE1	PX	-0.006	-0.006	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 6 : Wind Load (90)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
39	FACE2	PX	-.003	-.003	0	0
40	CR6	PX	-.008	-.008	0	0
41	CR5	PX	-.008	-.008	0	0
42	CR4	PX	-.008	-.008	0	0
43	CR3	PX	-.008	-.008	0	0
44	CR2	PX	-.008	-.008	0	0
45	CR1	PX	-.008	-.008	0	0
46	CPL3	PX	-.000857	-.000857	0	0
47	CPL2	PX	-.000857	-.000857	0	0
48	CPL1	PX	-.000857	-.000857	0	0
49	ANGLE6	PX	-.005	-.005	0	0
50	ANGLE5	PX	-.005	-.005	0	0
51	ANGLE4	PX	-.005	-.005	0	0
52	ANGLE3	PX	-.005	-.005	0	0
53	ANGLE2	PX	-.005	-.005	0	0
54	ANGLE1	PX	-.005	-.005	0	0

**Member Distributed Loads (BLC 7 : Wind Load (120))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.003	.003	0	0
2	SO2	PY	.003	.003	0	0
3	SO1	PY	.003	.003	0	0
4	RPL3	PY	.005	.005	0	0
5	RPL2	PY	.005	.005	0	0
6	RPL1	PY	.005	.005	0	0
7	RAIL3	PY	.002	.002	0	0
8	RAIL2	PY	.002	.002	0	0
9	RAIL1	PY	.001	.001	0	0
10	PL18	PY	.000571	.000571	0	0
11	PL17	PY	.000571	.000571	0	0
12	PL16	PY	.000571	.000571	0	0
13	PL15	PY	.000571	.000571	0	0
14	PL14	PY	.000571	.000571	0	0
15	PL13	PY	.000571	.000571	0	0
16	PL12	PY	.000571	.000571	0	0
17	PL11	PY	.000571	.000571	0	0
18	PL10	PY	.000571	.000571	0	0
19	PL9	PY	.000571	.000571	0	0
20	PL8	PY	.000571	.000571	0	0
21	PL7	PY	.000571	.000571	0	0
22	PL6	PY	.000571	.000571	0	0
23	PL5	PY	.000571	.000571	0	0
24	PL4	PY	.000571	.000571	0	0
25	PL3	PY	.000571	.000571	0	0
26	PL2	PY	.000571	.000571	0	0
27	PL1	PY	.000571	.000571	0	0
28	MP GAMMA3	PY	.004	.004	0	0
29	MP GAMMA2	PY	.004	.004	0	0
30	MP GAMMA1	PY	.004	.004	0	0
31	MP BETA3	PY	.004	.004	0	0
32	MP BETA2	PY	.004	.004	0	0
33	MP BETA1	PY	.004	.004	0	0
34	MP ALPHA3	PY	.004	.004	0	0
35	MP ALPHA2	PY	.004	.004	0	0
36	MP ALPHA1	PY	.004	.004	0	0
37	FACE3	PY	.003	.003	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 7 : Wind Load (120)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
38	FACE1	PY	.003	.003	0 0
39	FACE2	PY	.001	.001	0 0
40	CR6	PY	.004	.004	0 0
41	CR5	PY	.004	.004	0 0
42	CR4	PY	.004	.004	0 0
43	CR3	PY	.004	.004	0 0
44	CR2	PY	.004	.004	0 0
45	CR1	PY	.004	.004	0 0
46	CPL3	PY	.000428	.000428	0 0
47	CPL2	PY	.000428	.000428	0 0
48	CPL1	PY	.000428	.000428	0 0
49	ANGLE6	PY	.002	.002	0 0
50	ANGLE5	PY	.002	.002	0 0
51	ANGLE4	PY	.002	.002	0 0
52	ANGLE3	PY	.002	.002	0 0
53	ANGLE2	PY	.002	.002	0 0
54	ANGLE1	PY	.002	.002	0 0
55	SO3	PX	-.005	-.005	0 0
56	SO2	PX	-.005	-.005	0 0
57	SO1	PX	-.005	-.005	0 0
58	RPL3	PX	-.009	-.009	0 0
59	RPL2	PX	-.009	-.009	0 0
60	RPL1	PX	-.009	-.009	0 0
61	RAIL3	PX	-.004	-.004	0 0
62	RAIL2	PX	-.004	-.004	0 0
63	RAIL1	PX	-.002	-.002	0 0
64	PL18	PX	-.000989	-.000989	0 0
65	PL17	PX	-.000989	-.000989	0 0
66	PL16	PX	-.000989	-.000989	0 0
67	PL15	PX	-.000989	-.000989	0 0
68	PL14	PX	-.000989	-.000989	0 0
69	PL13	PX	-.000989	-.000989	0 0
70	PL12	PX	-.000989	-.000989	0 0
71	PL11	PX	-.000989	-.000989	0 0
72	PL10	PX	-.000989	-.000989	0 0
73	PL9	PX	-.000989	-.000989	0 0
74	PL8	PX	-.000989	-.000989	0 0
75	PL7	PX	-.000989	-.000989	0 0
76	PL6	PX	-.000989	-.000989	0 0
77	PL5	PX	-.000989	-.000989	0 0
78	PL4	PX	-.000989	-.000989	0 0
79	PL3	PX	-.000989	-.000989	0 0
80	PL2	PX	-.000989	-.000989	0 0
81	PL1	PX	-.000989	-.000989	0 0
82	MP GAMMA3	PX	-.007	-.007	0 0
83	MP GAMMA2	PX	-.007	-.007	0 0
84	MP GAMMA1	PX	-.007	-.007	0 0
85	MP BETA3	PX	-.007	-.007	0 0
86	MP BETA2	PX	-.007	-.007	0 0
87	MP BETA1	PX	-.007	-.007	0 0
88	MP ALPHA3	PX	-.007	-.007	0 0
89	MP ALPHA2	PX	-.007	-.007	0 0
90	MP ALPHA1	PX	-.007	-.007	0 0
91	FACE3	PX	-.005	-.005	0 0
92	FACE1	PX	-.005	-.005	0 0
93	FACE2	PX	-.002	-.002	0 0
94	CR6	PX	-.007	-.007	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 7 : Wind Load (120)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
95	CR5	PX	-.007	-.007	0	0
96	CR4	PX	-.007	-.007	0	0
97	CR3	PX	-.007	-.007	0	0
98	CR2	PX	-.007	-.007	0	0
99	CR1	PX	-.007	-.007	0	0
100	CPL3	PX	-.000742	-.000742	0	0
101	CPL2	PX	-.000742	-.000742	0	0
102	CPL1	PX	-.000742	-.000742	0	0
103	ANGLE6	PX	-.004	-.004	0	0
104	ANGLE5	PX	-.004	-.004	0	0
105	ANGLE4	PX	-.004	-.004	0	0
106	ANGLE3	PX	-.004	-.004	0	0
107	ANGLE2	PX	-.004	-.004	0	0
108	ANGLE1	PX	-.004	-.004	0	0

**Member Distributed Loads (BLC 8 : Wind Load (150))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.005	.005	0	0
2	SO2	PY	.005	.005	0	0
3	SO1	PY	.005	.005	0	0
4	RPL3	PY	.009	.009	0	0
5	RPL2	PY	.009	.009	0	0
6	RPL1	PY	.009	.009	0	0
7	RAIL3	PY	.004	.004	0	0
8	RAIL2	PY	.004	.004	0	0
9	RAIL1	PY	.002	.002	0	0
10	PL18	PY	.000989	.000989	0	0
11	PL17	PY	.000989	.000989	0	0
12	PL16	PY	.000989	.000989	0	0
13	PL15	PY	.000989	.000989	0	0
14	PL14	PY	.000989	.000989	0	0
15	PL13	PY	.000989	.000989	0	0
16	PL12	PY	.000989	.000989	0	0
17	PL11	PY	.000989	.000989	0	0
18	PL10	PY	.000989	.000989	0	0
19	PL9	PY	.000989	.000989	0	0
20	PL8	PY	.000989	.000989	0	0
21	PL7	PY	.000989	.000989	0	0
22	PL6	PY	.000989	.000989	0	0
23	PL5	PY	.000989	.000989	0	0
24	PL4	PY	.000989	.000989	0	0
25	PL3	PY	.000989	.000989	0	0
26	PL2	PY	.000989	.000989	0	0
27	PL1	PY	.000989	.000989	0	0
28	MP GAMMA3	PY	.007	.007	0	0
29	MP GAMMA2	PY	.007	.007	0	0
30	MP GAMMA1	PY	.007	.007	0	0
31	MP BETA3	PY	.007	.007	0	0
32	MP BETA2	PY	.007	.007	0	0
33	MP BETA1	PY	.007	.007	0	0
34	MP ALPHA3	PY	.007	.007	0	0
35	MP ALPHA2	PY	.007	.007	0	0
36	MP ALPHA1	PY	.007	.007	0	0
37	FACE3	PY	.005	.005	0	0
38	FACE1	PY	.005	.005	0	0
39	FACE2	PY	.002	.002	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 8 : Wind Load (150)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft,%]	End Location[ft,%]
40	CR6	PY	.007	.007	0 0
41	CR5	PY	.007	.007	0 0
42	CR4	PY	.007	.007	0 0
43	CR3	PY	.007	.007	0 0
44	CR2	PY	.007	.007	0 0
45	CR1	PY	.007	.007	0 0
46	CPL3	PY	.000742	.000742	0 0
47	CPL2	PY	.000742	.000742	0 0
48	CPL1	PY	.000742	.000742	0 0
49	ANGLE6	PY	.004	.004	0 0
50	ANGLE5	PY	.004	.004	0 0
51	ANGLE4	PY	.004	.004	0 0
52	ANGLE3	PY	.004	.004	0 0
53	ANGLE2	PY	.004	.004	0 0
54	ANGLE1	PY	.004	.004	0 0
55	SO3	PX	-.003	-.003	0 0
56	SO2	PX	-.003	-.003	0 0
57	SO1	PX	-.003	-.003	0 0
58	RPL3	PX	-.005	-.005	0 0
59	RPL2	PX	-.005	-.005	0 0
60	RPL1	PX	-.005	-.005	0 0
61	RAIL3	PX	-.002	-.002	0 0
62	RAIL2	PX	-.002	-.002	0 0
63	RAIL1	PX	-.001	-.001	0 0
64	PL18	PX	-.000571	-.000571	0 0
65	PL17	PX	-.000571	-.000571	0 0
66	PL16	PX	-.000571	-.000571	0 0
67	PL15	PX	-.000571	-.000571	0 0
68	PL14	PX	-.000571	-.000571	0 0
69	PL13	PX	-.000571	-.000571	0 0
70	PL12	PX	-.000571	-.000571	0 0
71	PL11	PX	-.000571	-.000571	0 0
72	PL10	PX	-.000571	-.000571	0 0
73	PL9	PX	-.000571	-.000571	0 0
74	PL8	PX	-.000571	-.000571	0 0
75	PL7	PX	-.000571	-.000571	0 0
76	PL6	PX	-.000571	-.000571	0 0
77	PL5	PX	-.000571	-.000571	0 0
78	PL4	PX	-.000571	-.000571	0 0
79	PL3	PX	-.000571	-.000571	0 0
80	PL2	PX	-.000571	-.000571	0 0
81	PL1	PX	-.000571	-.000571	0 0
82	MP GAMMA3	PX	-.004	-.004	0 0
83	MP GAMMA2	PX	-.004	-.004	0 0
84	MP GAMMA1	PX	-.004	-.004	0 0
85	MP BETA3	PX	-.004	-.004	0 0
86	MP BETA2	PX	-.004	-.004	0 0
87	MP BETA1	PX	-.004	-.004	0 0
88	MP ALPHA3	PX	-.004	-.004	0 0
89	MP ALPHA2	PX	-.004	-.004	0 0
90	MP ALPHA1	PX	-.004	-.004	0 0
91	FACE3	PX	-.003	-.003	0 0
92	FACE1	PX	-.003	-.003	0 0
93	FACE2	PX	-.001	-.001	0 0
94	CR6	PX	-.004	-.004	0 0
95	CR5	PX	-.004	-.004	0 0
96	CR4	PX	-.004	-.004	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 8 : Wind Load (150)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
97	CR3	PX	-.004	-.004	0	0
98	CR2	PX	-.004	-.004	0	0
99	CR1	PX	-.004	-.004	0	0
100	CPL3	PX	-.000428	-.000428	0	0
101	CPL2	PX	-.000428	-.000428	0	0
102	CPL1	PX	-.000428	-.000428	0	0
103	ANGLE6	PX	-.002	-.002	0	0
104	ANGLE5	PX	-.002	-.002	0	0
105	ANGLE4	PX	-.002	-.002	0	0
106	ANGLE3	PX	-.002	-.002	0	0
107	ANGLE2	PX	-.002	-.002	0	0
108	ANGLE1	PX	-.002	-.002	0	0

**Member Distributed Loads (BLC 9 : Wind Load (180))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.006	.006	0	0
2	SO2	PY	.006	.006	0	0
3	SO1	PY	.006	.006	0	0
4	RPL3	PY	.01	.01	0	0
5	RPL2	PY	.01	.01	0	0
6	RPL1	PY	.01	.01	0	0
7	RAIL3	PY	.005	.005	0	0
8	RAIL2	PY	.005	.005	0	0
9	RAIL1	PY	.002	.002	0	0
10	PL18	PY	.001	.001	0	0
11	PL17	PY	.001	.001	0	0
12	PL16	PY	.001	.001	0	0
13	PL15	PY	.001	.001	0	0
14	PL14	PY	.001	.001	0	0
15	PL13	PY	.001	.001	0	0
16	PL12	PY	.001	.001	0	0
17	PL11	PY	.001	.001	0	0
18	PL10	PY	.001	.001	0	0
19	PL9	PY	.001	.001	0	0
20	PL8	PY	.001	.001	0	0
21	PL7	PY	.001	.001	0	0
22	PL6	PY	.001	.001	0	0
23	PL5	PY	.001	.001	0	0
24	PL4	PY	.001	.001	0	0
25	PL3	PY	.001	.001	0	0
26	PL2	PY	.001	.001	0	0
27	PL1	PY	.001	.001	0	0
28	MP GAMMA3	PY	.008	.008	0	0
29	MP GAMMA2	PY	.008	.008	0	0
30	MP GAMMA1	PY	.008	.008	0	0
31	MP BETA3	PY	.008	.008	0	0
32	MP BETA2	PY	.008	.008	0	0
33	MP BETA1	PY	.008	.008	0	0
34	MP ALPHA3	PY	.008	.008	0	0
35	MP ALPHA2	PY	.008	.008	0	0
36	MP ALPHA1	PY	.008	.008	0	0
37	FACE3	PY	.006	.006	0	0
38	FACE1	PY	.006	.006	0	0
39	FACE2	PY	.003	.003	0	0
40	CR6	PY	.008	.008	0	0
41	CR5	PY	.008	.008	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 9 : Wind Load (180)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
42	CR4	PY	.008	.008	0	0
43	CR3	PY	.008	.008	0	0
44	CR2	PY	.008	.008	0	0
45	CR1	PY	.008	.008	0	0
46	CPL3	PY	.000857	.000857	0	0
47	CPL2	PY	.000857	.000857	0	0
48	CPL1	PY	.000857	.000857	0	0
49	ANGLE6	PY	.005	.005	0	0
50	ANGLE5	PY	.005	.005	0	0
51	ANGLE4	PY	.005	.005	0	0
52	ANGLE3	PY	.005	.005	0	0
53	ANGLE2	PY	.005	.005	0	0
54	ANGLE1	PY	.005	.005	0	0

**Member Distributed Loads (BLC 10 : Wind Load (210))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.005	.005	0	0
2	SO2	PY	.005	.005	0	0
3	SO1	PY	.005	.005	0	0
4	RPL3	PY	.009	.009	0	0
5	RPL2	PY	.009	.009	0	0
6	RPL1	PY	.009	.009	0	0
7	RAIL3	PY	.004	.004	0	0
8	RAIL2	PY	.004	.004	0	0
9	RAIL1	PY	.002	.002	0	0
10	PL18	PY	.000989	.000989	0	0
11	PL17	PY	.000989	.000989	0	0
12	PL16	PY	.000989	.000989	0	0
13	PL15	PY	.000989	.000989	0	0
14	PL14	PY	.000989	.000989	0	0
15	PL13	PY	.000989	.000989	0	0
16	PL12	PY	.000989	.000989	0	0
17	PL11	PY	.000989	.000989	0	0
18	PL10	PY	.000989	.000989	0	0
19	PL9	PY	.000989	.000989	0	0
20	PL8	PY	.000989	.000989	0	0
21	PL7	PY	.000989	.000989	0	0
22	PL6	PY	.000989	.000989	0	0
23	PL5	PY	.000989	.000989	0	0
24	PL4	PY	.000989	.000989	0	0
25	PL3	PY	.000989	.000989	0	0
26	PL2	PY	.000989	.000989	0	0
27	PL1	PY	.000989	.000989	0	0
28	MP GAMMA3	PY	.007	.007	0	0
29	MP GAMMA2	PY	.007	.007	0	0
30	MP GAMMA1	PY	.007	.007	0	0
31	MP BETA3	PY	.007	.007	0	0
32	MP BETA2	PY	.007	.007	0	0
33	MP BETA1	PY	.007	.007	0	0
34	MP ALPHA3	PY	.007	.007	0	0
35	MP ALPHA2	PY	.007	.007	0	0
36	MP ALPHA1	PY	.007	.007	0	0
37	FACE1	PY	.005	.005	0	0
38	FACE2	PY	.005	.005	0	0
39	FACE3	PY	.002	.002	0	0
40	CR6	PY	.007	.007	0	0





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 10 : Wind Load (210)) (Continued)**

	Member Label	Direction	Start Magnitude[k/ft...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
41	CR5	PY	.007	.007	0	0
42	CR4	PY	.007	.007	0	0
43	CR3	PY	.007	.007	0	0
44	CR2	PY	.007	.007	0	0
45	CR1	PY	.007	.007	0	0
46	CPL3	PY	.000742	.000742	0	0
47	CPL2	PY	.000742	.000742	0	0
48	CPL1	PY	.000742	.000742	0	0
49	ANGLE6	PY	.004	.004	0	0
50	ANGLE5	PY	.004	.004	0	0
51	ANGLE4	PY	.004	.004	0	0
52	ANGLE3	PY	.004	.004	0	0
53	ANGLE2	PY	.004	.004	0	0
54	ANGLE1	PY	.004	.004	0	0
55	SO3	PX	.003	.003	0	0
56	SO2	PX	.003	.003	0	0
57	SO1	PX	.003	.003	0	0
58	RPL3	PX	.005	.005	0	0
59	RPL2	PX	.005	.005	0	0
60	RPL1	PX	.005	.005	0	0
61	RAIL3	PX	.002	.002	0	0
62	RAIL2	PX	.002	.002	0	0
63	RAIL1	PX	.001	.001	0	0
64	PL18	PX	.000571	.000571	0	0
65	PL17	PX	.000571	.000571	0	0
66	PL16	PX	.000571	.000571	0	0
67	PL15	PX	.000571	.000571	0	0
68	PL14	PX	.000571	.000571	0	0
69	PL13	PX	.000571	.000571	0	0
70	PL12	PX	.000571	.000571	0	0
71	PL11	PX	.000571	.000571	0	0
72	PL10	PX	.000571	.000571	0	0
73	PL9	PX	.000571	.000571	0	0
74	PL8	PX	.000571	.000571	0	0
75	PL7	PX	.000571	.000571	0	0
76	PL6	PX	.000571	.000571	0	0
77	PL5	PX	.000571	.000571	0	0
78	PL4	PX	.000571	.000571	0	0
79	PL3	PX	.000571	.000571	0	0
80	PL2	PX	.000571	.000571	0	0
81	PL1	PX	.000571	.000571	0	0
82	MP GAMMA3	PX	.004	.004	0	0
83	MP GAMMA2	PX	.004	.004	0	0
84	MP GAMMA1	PX	.004	.004	0	0
85	MP BETA3	PX	.004	.004	0	0
86	MP BETA2	PX	.004	.004	0	0
87	MP BETA1	PX	.004	.004	0	0
88	MP ALPHA3	PX	.004	.004	0	0
89	MP ALPHA2	PX	.004	.004	0	0
90	MP ALPHA1	PX	.004	.004	0	0
91	FACE1	PX	.003	.003	0	0
92	FACE2	PX	.003	.003	0	0
93	FACE3	PX	.001	.001	0	0
94	CR6	PX	.004	.004	0	0
95	CR5	PX	.004	.004	0	0
96	CR4	PX	.004	.004	0	0
97	CR3	PX	.004	.004	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 10 : Wind Load (210)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
98	CR2	PX	.004	.004	0	0
99	CR1	PX	.004	.004	0	0
100	CPL3	PX	.000428	.000428	0	0
101	CPL2	PX	.000428	.000428	0	0
102	CPL1	PX	.000428	.000428	0	0
103	ANGLE6	PX	.002	.002	0	0
104	ANGLE5	PX	.002	.002	0	0
105	ANGLE4	PX	.002	.002	0	0
106	ANGLE3	PX	.002	.002	0	0
107	ANGLE2	PX	.002	.002	0	0
108	ANGLE1	PX	.002	.002	0	0

**Member Distributed Loads (BLC 11 : Wind Load (240))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.003	.003	0	0
2	SO2	PY	.003	.003	0	0
3	SO1	PY	.003	.003	0	0
4	RPL3	PY	.005	.005	0	0
5	RPL2	PY	.005	.005	0	0
6	RPL1	PY	.005	.005	0	0
7	RAIL3	PY	.002	.002	0	0
8	RAIL2	PY	.002	.002	0	0
9	RAIL1	PY	.001	.001	0	0
10	PL18	PY	.000571	.000571	0	0
11	PL17	PY	.000571	.000571	0	0
12	PL16	PY	.000571	.000571	0	0
13	PL15	PY	.000571	.000571	0	0
14	PL14	PY	.000571	.000571	0	0
15	PL13	PY	.000571	.000571	0	0
16	PL12	PY	.000571	.000571	0	0
17	PL11	PY	.000571	.000571	0	0
18	PL10	PY	.000571	.000571	0	0
19	PL9	PY	.000571	.000571	0	0
20	PL8	PY	.000571	.000571	0	0
21	PL7	PY	.000571	.000571	0	0
22	PL6	PY	.000571	.000571	0	0
23	PL5	PY	.000571	.000571	0	0
24	PL4	PY	.000571	.000571	0	0
25	PL3	PY	.000571	.000571	0	0
26	PL2	PY	.000571	.000571	0	0
27	PL1	PY	.000571	.000571	0	0
28	MP GAMMA3	PY	.004	.004	0	0
29	MP GAMMA2	PY	.004	.004	0	0
30	MP GAMMA1	PY	.004	.004	0	0
31	MP BETA3	PY	.004	.004	0	0
32	MP BETA2	PY	.004	.004	0	0
33	MP BETA1	PY	.004	.004	0	0
34	MP ALPHA3	PY	.004	.004	0	0
35	MP ALPHA2	PY	.004	.004	0	0
36	MP ALPHA1	PY	.004	.004	0	0
37	FACE1	PY	.003	.003	0	0
38	FACE2	PY	.003	.003	0	0
39	FACE3	PY	.001	.001	0	0
40	CR6	PY	.004	.004	0	0
41	CR5	PY	.004	.004	0	0
42	CR4	PY	.004	.004	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 11 : Wind Load (240)) (Continued)**

Member Label	Direction	Start Magnitude[k/ft...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
43	CR3	PY	.004	.004	0 0
44	CR2	PY	.004	.004	0 0
45	CR1	PY	.004	.004	0 0
46	CPL3	PY	.000428	.000428	0 0
47	CPL2	PY	.000428	.000428	0 0
48	CPL1	PY	.000428	.000428	0 0
49	ANGLE6	PY	.002	.002	0 0
50	ANGLE5	PY	.002	.002	0 0
51	ANGLE4	PY	.002	.002	0 0
52	ANGLE3	PY	.002	.002	0 0
53	ANGLE2	PY	.002	.002	0 0
54	ANGLE1	PY	.002	.002	0 0
55	SO3	PX	.005	.005	0 0
56	SO2	PX	.005	.005	0 0
57	SO1	PX	.005	.005	0 0
58	RPL3	PX	.009	.009	0 0
59	RPL2	PX	.009	.009	0 0
60	RPL1	PX	.009	.009	0 0
61	RAIL3	PX	.004	.004	0 0
62	RAIL2	PX	.004	.004	0 0
63	RAIL1	PX	.002	.002	0 0
64	PL18	PX	.000989	.000989	0 0
65	PL17	PX	.000989	.000989	0 0
66	PL16	PX	.000989	.000989	0 0
67	PL15	PX	.000989	.000989	0 0
68	PL14	PX	.000989	.000989	0 0
69	PL13	PX	.000989	.000989	0 0
70	PL12	PX	.000989	.000989	0 0
71	PL11	PX	.000989	.000989	0 0
72	PL10	PX	.000989	.000989	0 0
73	PL9	PX	.000989	.000989	0 0
74	PL8	PX	.000989	.000989	0 0
75	PL7	PX	.000989	.000989	0 0
76	PL6	PX	.000989	.000989	0 0
77	PL5	PX	.000989	.000989	0 0
78	PL4	PX	.000989	.000989	0 0
79	PL3	PX	.000989	.000989	0 0
80	PL2	PX	.000989	.000989	0 0
81	PL1	PX	.000989	.000989	0 0
82	MP GAMMA3	PX	.007	.007	0 0
83	MP GAMMA2	PX	.007	.007	0 0
84	MP GAMMA1	PX	.007	.007	0 0
85	MP BETA3	PX	.007	.007	0 0
86	MP BETA2	PX	.007	.007	0 0
87	MP BETA1	PX	.007	.007	0 0
88	MP ALPHA3	PX	.007	.007	0 0
89	MP ALPHA2	PX	.007	.007	0 0
90	MP ALPHA1	PX	.007	.007	0 0
91	FACE1	PX	.005	.005	0 0
92	FACE2	PX	.005	.005	0 0
93	FACE3	PX	.002	.002	0 0
94	CR6	PX	.007	.007	0 0
95	CR5	PX	.007	.007	0 0
96	CR4	PX	.007	.007	0 0
97	CR3	PX	.007	.007	0 0
98	CR2	PX	.007	.007	0 0
99	CR1	PX	.007	.007	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 11 : Wind Load (240)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
100	CPL3	PX	.000742	.000742	0	0
101	CPL2	PX	.000742	.000742	0	0
102	CPL1	PX	.000742	.000742	0	0
103	ANGLE6	PX	.004	.004	0	0
104	ANGLE5	PX	.004	.004	0	0
105	ANGLE4	PX	.004	.004	0	0
106	ANGLE3	PX	.004	.004	0	0
107	ANGLE2	PX	.004	.004	0	0
108	ANGLE1	PX	.004	.004	0	0

**Member Distributed Loads (BLC 12 : Wind Load (270))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PX	.006	.006	0	0
2	SO2	PX	.006	.006	0	0
3	SO1	PX	.006	.006	0	0
4	RPL3	PX	.01	.01	0	0
5	RPL2	PX	.01	.01	0	0
6	RPL1	PX	.01	.01	0	0
7	RAIL3	PX	.005	.005	0	0
8	RAIL2	PX	.005	.005	0	0
9	RAIL1	PX	.002	.002	0	0
10	PL18	PX	.001	.001	0	0
11	PL17	PX	.001	.001	0	0
12	PL16	PX	.001	.001	0	0
13	PL15	PX	.001	.001	0	0
14	PL14	PX	.001	.001	0	0
15	PL13	PX	.001	.001	0	0
16	PL12	PX	.001	.001	0	0
17	PL11	PX	.001	.001	0	0
18	PL10	PX	.001	.001	0	0
19	PL9	PX	.001	.001	0	0
20	PL8	PX	.001	.001	0	0
21	PL7	PX	.001	.001	0	0
22	PL6	PX	.001	.001	0	0
23	PL5	PX	.001	.001	0	0
24	PL4	PX	.001	.001	0	0
25	PL3	PX	.001	.001	0	0
26	PL2	PX	.001	.001	0	0
27	PL1	PX	.001	.001	0	0
28	MP GAMMA3	PX	.008	.008	0	0
29	MP GAMMA2	PX	.008	.008	0	0
30	MP GAMMA1	PX	.008	.008	0	0
31	MP BETA3	PX	.008	.008	0	0
32	MP BETA2	PX	.008	.008	0	0
33	MP BETA1	PX	.008	.008	0	0
34	MP ALPHA3	PX	.008	.008	0	0
35	MP ALPHA2	PX	.008	.008	0	0
36	MP ALPHA1	PX	.008	.008	0	0
37	FACE1	PX	.006	.006	0	0
38	FACE2	PX	.006	.006	0	0
39	FACE3	PX	.003	.003	0	0
40	CR6	PX	.008	.008	0	0
41	CR5	PX	.008	.008	0	0
42	CR4	PX	.008	.008	0	0
43	CR3	PX	.008	.008	0	0
44	CR2	PX	.008	.008	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 12 : Wind Load (270)) (Continued)**

	Member Label	Direction	Start Magnitude[k/ft...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
45	CR1	PX	.008	.008	0	0
46	CPL3	PX	.000857	.000857	0	0
47	CPL2	PX	.000857	.000857	0	0
48	CPL1	PX	.000857	.000857	0	0
49	ANGLE6	PX	.005	.005	0	0
50	ANGLE5	PX	.005	.005	0	0
51	ANGLE4	PX	.005	.005	0	0
52	ANGLE3	PX	.005	.005	0	0
53	ANGLE2	PX	.005	.005	0	0
54	ANGLE1	PX	.005	.005	0	0

**Member Distributed Loads (BLC 13 : Wind Load (300))**

	Member Label	Direction	Start Magnitude[k/ft...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-.003	-.003	0	0
2	SO2	PY	-.003	-.003	0	0
3	SO1	PY	-.003	-.003	0	0
4	RPL3	PY	-.005	-.005	0	0
5	RPL2	PY	-.005	-.005	0	0
6	RPL1	PY	-.005	-.005	0	0
7	RAIL3	PY	-.002	-.002	0	0
8	RAIL2	PY	-.002	-.002	0	0
9	RAIL1	PY	-.001	-.001	0	0
10	PL18	PY	-.000571	-.000571	0	0
11	PL17	PY	-.000571	-.000571	0	0
12	PL16	PY	-.000571	-.000571	0	0
13	PL15	PY	-.000571	-.000571	0	0
14	PL14	PY	-.000571	-.000571	0	0
15	PL13	PY	-.000571	-.000571	0	0
16	PL12	PY	-.000571	-.000571	0	0
17	PL11	PY	-.000571	-.000571	0	0
18	PL10	PY	-.000571	-.000571	0	0
19	PL9	PY	-.000571	-.000571	0	0
20	PL8	PY	-.000571	-.000571	0	0
21	PL7	PY	-.000571	-.000571	0	0
22	PL6	PY	-.000571	-.000571	0	0
23	PL5	PY	-.000571	-.000571	0	0
24	PL4	PY	-.000571	-.000571	0	0
25	PL3	PY	-.000571	-.000571	0	0
26	PL2	PY	-.000571	-.000571	0	0
27	PL1	PY	-.000571	-.000571	0	0
28	MP GAMMA3	PY	-.004	-.004	0	0
29	MP GAMMA2	PY	-.004	-.004	0	0
30	MP GAMMA1	PY	-.004	-.004	0	0
31	MP BETA3	PY	-.004	-.004	0	0
32	MP BETA2	PY	-.004	-.004	0	0
33	MP BETA1	PY	-.004	-.004	0	0
34	MP ALPHA3	PY	-.004	-.004	0	0
35	MP ALPHA2	PY	-.004	-.004	0	0
36	MP ALPHA1	PY	-.004	-.004	0	0
37	FACE1	PY	-.003	-.003	0	0
38	FACE2	PY	-.003	-.003	0	0
39	FACE3	PY	-.001	-.001	0	0
40	CR6	PY	-.004	-.004	0	0
41	CR5	PY	-.004	-.004	0	0
42	CR4	PY	-.004	-.004	0	0
43	CR3	PY	-.004	-.004	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 13 : Wind Load (300)) (Continued)**

	Member Label	Direction	Start Magnitude[k/ft...]	End Magnitude[k/ft...]	Start Location[ft,%]	End Location[ft,%]
44	CR2	PY	-.004	-.004	0	0
45	CR1	PY	-.004	-.004	0	0
46	CPL3	PY	-.000428	-.000428	0	0
47	CPL2	PY	-.000428	-.000428	0	0
48	CPL1	PY	-.000428	-.000428	0	0
49	ANGLE6	PY	-.002	-.002	0	0
50	ANGLE5	PY	-.002	-.002	0	0
51	ANGLE4	PY	-.002	-.002	0	0
52	ANGLE3	PY	-.002	-.002	0	0
53	ANGLE2	PY	-.002	-.002	0	0
54	ANGLE1	PY	-.002	-.002	0	0
55	SO3	PX	.005	.005	0	0
56	SO2	PX	.005	.005	0	0
57	SO1	PX	.005	.005	0	0
58	RPL3	PX	.009	.009	0	0
59	RPL2	PX	.009	.009	0	0
60	RPL1	PX	.009	.009	0	0
61	RAIL3	PX	.004	.004	0	0
62	RAIL2	PX	.004	.004	0	0
63	RAIL1	PX	.002	.002	0	0
64	PL18	PX	.000989	.000989	0	0
65	PL17	PX	.000989	.000989	0	0
66	PL16	PX	.000989	.000989	0	0
67	PL15	PX	.000989	.000989	0	0
68	PL14	PX	.000989	.000989	0	0
69	PL13	PX	.000989	.000989	0	0
70	PL12	PX	.000989	.000989	0	0
71	PL11	PX	.000989	.000989	0	0
72	PL10	PX	.000989	.000989	0	0
73	PL9	PX	.000989	.000989	0	0
74	PL8	PX	.000989	.000989	0	0
75	PL7	PX	.000989	.000989	0	0
76	PL6	PX	.000989	.000989	0	0
77	PL5	PX	.000989	.000989	0	0
78	PL4	PX	.000989	.000989	0	0
79	PL3	PX	.000989	.000989	0	0
80	PL2	PX	.000989	.000989	0	0
81	PL1	PX	.000989	.000989	0	0
82	MP GAMMA3	PX	.007	.007	0	0
83	MP GAMMA2	PX	.007	.007	0	0
84	MP GAMMA1	PX	.007	.007	0	0
85	MP BETA3	PX	.007	.007	0	0
86	MP BETA2	PX	.007	.007	0	0
87	MP BETA1	PX	.007	.007	0	0
88	MP ALPHA3	PX	.007	.007	0	0
89	MP ALPHA2	PX	.007	.007	0	0
90	MP ALPHA1	PX	.007	.007	0	0
91	FACE1	PX	.005	.005	0	0
92	FACE2	PX	.005	.005	0	0
93	FACE3	PX	.002	.002	0	0
94	CR6	PX	.007	.007	0	0
95	CR5	PX	.007	.007	0	0
96	CR4	PX	.007	.007	0	0
97	CR3	PX	.007	.007	0	0
98	CR2	PX	.007	.007	0	0
99	CR1	PX	.007	.007	0	0
100	CPL3	PX	.000742	.000742	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 13 : Wind Load (300)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
101	CPL2	PX	.000742	.000742	0	0
102	CPL1	PX	.000742	.000742	0	0
103	ANGLE6	PX	.004	.004	0	0
104	ANGLE5	PX	.004	.004	0	0
105	ANGLE4	PX	.004	.004	0	0
106	ANGLE3	PX	.004	.004	0	0
107	ANGLE2	PX	.004	.004	0	0
108	ANGLE1	PX	.004	.004	0	0

**Member Distributed Loads (BLC 14 : Wind Load (330))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-.005	-.005	0	0
2	SO2	PY	-.005	-.005	0	0
3	SO1	PY	-.005	-.005	0	0
4	RPL3	PY	-.009	-.009	0	0
5	RPL2	PY	-.009	-.009	0	0
6	RPL1	PY	-.009	-.009	0	0
7	RAIL3	PY	-.004	-.004	0	0
8	RAIL2	PY	-.004	-.004	0	0
9	RAIL1	PY	-.002	-.002	0	0
10	PL18	PY	-.000989	-.000989	0	0
11	PL17	PY	-.000989	-.000989	0	0
12	PL16	PY	-.000989	-.000989	0	0
13	PL15	PY	-.000989	-.000989	0	0
14	PL14	PY	-.000989	-.000989	0	0
15	PL13	PY	-.000989	-.000989	0	0
16	PL12	PY	-.000989	-.000989	0	0
17	PL11	PY	-.000989	-.000989	0	0
18	PL10	PY	-.000989	-.000989	0	0
19	PL9	PY	-.000989	-.000989	0	0
20	PL8	PY	-.000989	-.000989	0	0
21	PL7	PY	-.000989	-.000989	0	0
22	PL6	PY	-.000989	-.000989	0	0
23	PL5	PY	-.000989	-.000989	0	0
24	PL4	PY	-.000989	-.000989	0	0
25	PL3	PY	-.000989	-.000989	0	0
26	PL2	PY	-.000989	-.000989	0	0
27	PL1	PY	-.000989	-.000989	0	0
28	MP GAMMA3	PY	-.007	-.007	0	0
29	MP GAMMA2	PY	-.007	-.007	0	0
30	MP GAMMA1	PY	-.007	-.007	0	0
31	MP BETA3	PY	-.007	-.007	0	0
32	MP BETA2	PY	-.007	-.007	0	0
33	MP BETA1	PY	-.007	-.007	0	0
34	MP ALPHA3	PY	-.007	-.007	0	0
35	MP ALPHA2	PY	-.007	-.007	0	0
36	MP ALPHA1	PY	-.007	-.007	0	0
37	FACE3	PY	-.005	-.005	0	0
38	FACE2	PY	-.005	-.005	0	0
39	FACE1	PY	-.002	-.002	0	0
40	CR6	PY	-.007	-.007	0	0
41	CR5	PY	-.007	-.007	0	0
42	CR4	PY	-.007	-.007	0	0
43	CR3	PY	-.007	-.007	0	0
44	CR2	PY	-.007	-.007	0	0
45	CR1	PY	-.007	-.007	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 14 : Wind Load (330)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
46	CPL3	PY	-.000742	-.000742	0 0
47	CPL2	PY	-.000742	-.000742	0 0
48	CPL1	PY	-.000742	-.000742	0 0
49	ANGLE6	PY	-.004	-.004	0 0
50	ANGLE5	PY	-.004	-.004	0 0
51	ANGLE4	PY	-.004	-.004	0 0
52	ANGLE3	PY	-.004	-.004	0 0
53	ANGLE2	PY	-.004	-.004	0 0
54	ANGLE1	PY	-.004	-.004	0 0
55	SO3	PX	.003	.003	0 0
56	SO2	PX	.003	.003	0 0
57	SO1	PX	.003	.003	0 0
58	RPL3	PX	.005	.005	0 0
59	RPL2	PX	.005	.005	0 0
60	RPL1	PX	.005	.005	0 0
61	RAIL3	PX	.002	.002	0 0
62	RAIL2	PX	.002	.002	0 0
63	RAIL1	PX	.001	.001	0 0
64	PL18	PX	.000571	.000571	0 0
65	PL17	PX	.000571	.000571	0 0
66	PL16	PX	.000571	.000571	0 0
67	PL15	PX	.000571	.000571	0 0
68	PL14	PX	.000571	.000571	0 0
69	PL13	PX	.000571	.000571	0 0
70	PL12	PX	.000571	.000571	0 0
71	PL11	PX	.000571	.000571	0 0
72	PL10	PX	.000571	.000571	0 0
73	PL9	PX	.000571	.000571	0 0
74	PL8	PX	.000571	.000571	0 0
75	PL7	PX	.000571	.000571	0 0
76	PL6	PX	.000571	.000571	0 0
77	PL5	PX	.000571	.000571	0 0
78	PL4	PX	.000571	.000571	0 0
79	PL3	PX	.000571	.000571	0 0
80	PL2	PX	.000571	.000571	0 0
81	PL1	PX	.000571	.000571	0 0
82	MP GAMMA3	PX	.004	.004	0 0
83	MP GAMMA2	PX	.004	.004	0 0
84	MP GAMMA1	PX	.004	.004	0 0
85	MP BETA3	PX	.004	.004	0 0
86	MP BETA2	PX	.004	.004	0 0
87	MP BETA1	PX	.004	.004	0 0
88	MP ALPHA3	PX	.004	.004	0 0
89	MP ALPHA2	PX	.004	.004	0 0
90	MP ALPHA1	PX	.004	.004	0 0
91	FACE3	PX	.003	.003	0 0
92	FACE2	PX	.003	.003	0 0
93	FACE1	PX	.001	.001	0 0
94	CR6	PX	.004	.004	0 0
95	CR5	PX	.004	.004	0 0
96	CR4	PX	.004	.004	0 0
97	CR3	PX	.004	.004	0 0
98	CR2	PX	.004	.004	0 0
99	CR1	PX	.004	.004	0 0
100	CPL3	PX	.000428	.000428	0 0
101	CPL2	PX	.000428	.000428	0 0
102	CPL1	PX	.000428	.000428	0 0





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 14 : Wind Load (330)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
103	ANGLE6	PX	.002	.002	0	0
104	ANGLE5	PX	.002	.002	0	0
105	ANGLE4	PX	.002	.002	0	0
106	ANGLE3	PX	.002	.002	0	0
107	ANGLE2	PX	.002	.002	0	0
108	ANGLE1	PX	.002	.002	0	0

**Member Distributed Loads (BLC 15 : Maintenance (0))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-.00034	-.00034	0	0
2	SO2	PY	-.00034	-.00034	0	0
3	SO1	PY	-.00034	-.00034	0	0
4	RPL3	PY	-.000612	-.000612	0	0
5	RPL2	PY	-.000612	-.000612	0	0
6	RPL1	PY	-.000612	-.000612	0	0
7	RAIL3	PY	-.000276	-.000276	0	0
8	RAIL2	PY	-.000276	-.000276	0	0
9	RAIL1	PY	-.000138	-.000138	0	0
10	PL18	PY	-6.8e-5	-6.8e-5	0	0
11	PL17	PY	-6.8e-5	-6.8e-5	0	0
12	PL16	PY	-6.8e-5	-6.8e-5	0	0
13	PL15	PY	-6.8e-5	-6.8e-5	0	0
14	PL14	PY	-6.8e-5	-6.8e-5	0	0
15	PL13	PY	-6.8e-5	-6.8e-5	0	0
16	PL12	PY	-6.8e-5	-6.8e-5	0	0
17	PL11	PY	-6.8e-5	-6.8e-5	0	0
18	PL10	PY	-6.8e-5	-6.8e-5	0	0
19	PL9	PY	-6.8e-5	-6.8e-5	0	0
20	PL8	PY	-6.8e-5	-6.8e-5	0	0
21	PL7	PY	-6.8e-5	-6.8e-5	0	0
22	PL6	PY	-6.8e-5	-6.8e-5	0	0
23	PL5	PY	-6.8e-5	-6.8e-5	0	0
24	PL4	PY	-6.8e-5	-6.8e-5	0	0
25	PL3	PY	-6.8e-5	-6.8e-5	0	0
26	PL2	PY	-6.8e-5	-6.8e-5	0	0
27	PL1	PY	-6.8e-5	-6.8e-5	0	0
28	MP GAMMA3	PY	-.000469	-.000469	0	0
29	MP GAMMA2	PY	-.000469	-.000469	0	0
30	MP GAMMA1	PY	-.000469	-.000469	0	0
31	MP BETA3	PY	-.000469	-.000469	0	0
32	MP BETA2	PY	-.000469	-.000469	0	0
33	MP BETA1	PY	-.000469	-.000469	0	0
34	MP ALPHA3	PY	-.000469	-.000469	0	0
35	MP ALPHA2	PY	-.000469	-.000469	0	0
36	MP ALPHA1	PY	-.000469	-.000469	0	0
37	FACE3	PY	-.000336	-.000336	0	0
38	FACE2	PY	-.000336	-.000336	0	0
39	FACE1	PY	-.000168	-.000168	0	0
40	CR6	PY	-.000459	-.000459	0	0
41	CR5	PY	-.000459	-.000459	0	0
42	CR4	PY	-.000459	-.000459	0	0
43	CR3	PY	-.000459	-.000459	0	0
44	CR2	PY	-.000459	-.000459	0	0
45	CR1	PY	-.000459	-.000459	0	0
46	CPL3	PY	-5.1e-5	-5.1e-5	0	0
47	CPL2	PY	-5.1e-5	-5.1e-5	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 15 : Maintenance (0)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
48	CPL1	PY	-5.1e-5	-5.1e-5	0	0
49	ANGLE6	PY	-0.00272	-0.00272	0	0
50	ANGLE5	PY	-0.00272	-0.00272	0	0
51	ANGLE4	PY	-0.00272	-0.00272	0	0
52	ANGLE3	PY	-0.00272	-0.00272	0	0
53	ANGLE2	PY	-0.00272	-0.00272	0	0
54	ANGLE1	PY	-0.00272	-0.00272	0	0

**Member Distributed Loads (BLC 16 : Maintenance (30))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-0.00294	-0.00294	0	0
2	SO2	PY	-0.00294	-0.00294	0	0
3	SO1	PY	-0.00294	-0.00294	0	0
4	RPL3	PY	-0.00053	-0.00053	0	0
5	RPL2	PY	-0.00053	-0.00053	0	0
6	RPL1	PY	-0.00053	-0.00053	0	0
7	RAIL3	PY	-0.00239	-0.00239	0	0
8	RAIL2	PY	-0.00239	-0.00239	0	0
9	RAIL1	PY	-0.0012	-0.0012	0	0
10	PL18	PY	-5.9e-5	-5.9e-5	0	0
11	PL17	PY	-5.9e-5	-5.9e-5	0	0
12	PL16	PY	-5.9e-5	-5.9e-5	0	0
13	PL15	PY	-5.9e-5	-5.9e-5	0	0
14	PL14	PY	-5.9e-5	-5.9e-5	0	0
15	PL13	PY	-5.9e-5	-5.9e-5	0	0
16	PL12	PY	-5.9e-5	-5.9e-5	0	0
17	PL11	PY	-5.9e-5	-5.9e-5	0	0
18	PL10	PY	-5.9e-5	-5.9e-5	0	0
19	PL9	PY	-5.9e-5	-5.9e-5	0	0
20	PL8	PY	-5.9e-5	-5.9e-5	0	0
21	PL7	PY	-5.9e-5	-5.9e-5	0	0
22	PL6	PY	-5.9e-5	-5.9e-5	0	0
23	PL5	PY	-5.9e-5	-5.9e-5	0	0
24	PL4	PY	-5.9e-5	-5.9e-5	0	0
25	PL3	PY	-5.9e-5	-5.9e-5	0	0
26	PL2	PY	-5.9e-5	-5.9e-5	0	0
27	PL1	PY	-5.9e-5	-5.9e-5	0	0
28	MP GAMMA3	PY	-0.00406	-0.00406	0	0
29	MP GAMMA2	PY	-0.00406	-0.00406	0	0
30	MP GAMMA1	PY	-0.00406	-0.00406	0	0
31	MP BETA3	PY	-0.00406	-0.00406	0	0
32	MP BETA2	PY	-0.00406	-0.00406	0	0
33	MP BETA1	PY	-0.00406	-0.00406	0	0
34	MP ALPHA3	PY	-0.00406	-0.00406	0	0
35	MP ALPHA2	PY	-0.00406	-0.00406	0	0
36	MP ALPHA1	PY	-0.00406	-0.00406	0	0
37	FACE3	PY	-0.00291	-0.00291	0	0
38	FACE2	PY	-0.00291	-0.00291	0	0
39	FACE1	PY	-0.00146	-0.00146	0	0
40	CR6	PY	-0.00398	-0.00398	0	0
41	CR5	PY	-0.00398	-0.00398	0	0
42	CR4	PY	-0.00398	-0.00398	0	0
43	CR3	PY	-0.00398	-0.00398	0	0
44	CR2	PY	-0.00398	-0.00398	0	0
45	CR1	PY	-0.00398	-0.00398	0	0
46	CPL3	PY	-4.4e-5	-4.4e-5	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 16 : Maintenance (30)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]	
47	CPL2	PY	-4.4e-5	-4.4e-5	0	0
48	CPL1	PY	-4.4e-5	-4.4e-5	0	0
49	ANGLE6	PY	-0.00235	-0.00235	0	0
50	ANGLE5	PY	-0.00235	-0.00235	0	0
51	ANGLE4	PY	-0.00235	-0.00235	0	0
52	ANGLE3	PY	-0.00235	-0.00235	0	0
53	ANGLE2	PY	-0.00235	-0.00235	0	0
54	ANGLE1	PY	-0.00235	-0.00235	0	0
55	SO3	PX	-0.0017	-0.0017	0	0
56	SO2	PX	-0.0017	-0.0017	0	0
57	SO1	PX	-0.0017	-0.0017	0	0
58	RPL3	PX	-0.00306	-0.00306	0	0
59	RPL2	PX	-0.00306	-0.00306	0	0
60	RPL1	PX	-0.00306	-0.00306	0	0
61	RAIL3	PX	-0.00138	-0.00138	0	0
62	RAIL2	PX	-0.00138	-0.00138	0	0
63	RAIL1	PX	-6.9e-5	-6.9e-5	0	0
64	PL18	PX	-3.4e-5	-3.4e-5	0	0
65	PL17	PX	-3.4e-5	-3.4e-5	0	0
66	PL16	PX	-3.4e-5	-3.4e-5	0	0
67	PL15	PX	-3.4e-5	-3.4e-5	0	0
68	PL14	PX	-3.4e-5	-3.4e-5	0	0
69	PL13	PX	-3.4e-5	-3.4e-5	0	0
70	PL12	PX	-3.4e-5	-3.4e-5	0	0
71	PL11	PX	-3.4e-5	-3.4e-5	0	0
72	PL10	PX	-3.4e-5	-3.4e-5	0	0
73	PL9	PX	-3.4e-5	-3.4e-5	0	0
74	PL8	PX	-3.4e-5	-3.4e-5	0	0
75	PL7	PX	-3.4e-5	-3.4e-5	0	0
76	PL6	PX	-3.4e-5	-3.4e-5	0	0
77	PL5	PX	-3.4e-5	-3.4e-5	0	0
78	PL4	PX	-3.4e-5	-3.4e-5	0	0
79	PL3	PX	-3.4e-5	-3.4e-5	0	0
80	PL2	PX	-3.4e-5	-3.4e-5	0	0
81	PL1	PX	-3.4e-5	-3.4e-5	0	0
82	MP GAMMA3	PX	-0.00234	-0.00234	0	0
83	MP GAMMA2	PX	-0.00234	-0.00234	0	0
84	MP GAMMA1	PX	-0.00234	-0.00234	0	0
85	MP BETA3	PX	-0.00234	-0.00234	0	0
86	MP BETA2	PX	-0.00234	-0.00234	0	0
87	MP BETA1	PX	-0.00234	-0.00234	0	0
88	MP ALPHA3	PX	-0.00234	-0.00234	0	0
89	MP ALPHA2	PX	-0.00234	-0.00234	0	0
90	MP ALPHA1	PX	-0.00234	-0.00234	0	0
91	FACE3	PX	-0.00168	-0.00168	0	0
92	FACE2	PX	-0.00168	-0.00168	0	0
93	FACE1	PX	-8.4e-5	-8.4e-5	0	0
94	CR6	PX	-0.0023	-0.0023	0	0
95	CR5	PX	-0.0023	-0.0023	0	0
96	CR4	PX	-0.0023	-0.0023	0	0
97	CR3	PX	-0.0023	-0.0023	0	0
98	CR2	PX	-0.0023	-0.0023	0	0
99	CR1	PX	-0.0023	-0.0023	0	0
100	CPL3	PX	-2.5e-5	-2.5e-5	0	0
101	CPL2	PX	-2.5e-5	-2.5e-5	0	0
102	CPL1	PX	-2.5e-5	-2.5e-5	0	0
103	ANGLE6	PX	-0.00136	-0.00136	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 16 : Maintenance (30)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
104	ANGLE5	PX	-0.00136	-0.00136	0	0
105	ANGLE4	PX	-0.00136	-0.00136	0	0
106	ANGLE3	PX	-0.00136	-0.00136	0	0
107	ANGLE2	PX	-0.00136	-0.00136	0	0
108	ANGLE1	PX	-0.00136	-0.00136	0	0

**Member Distributed Loads (BLC 17 : Maintenance (60))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-0.0017	-0.0017	0	0
2	SO2	PY	-0.0017	-0.0017	0	0
3	SO1	PY	-0.0017	-0.0017	0	0
4	RPL3	PY	-0.00306	-0.00306	0	0
5	RPL2	PY	-0.00306	-0.00306	0	0
6	RPL1	PY	-0.00306	-0.00306	0	0
7	RAIL3	PY	-0.00138	-0.00138	0	0
8	RAIL2	PY	-0.00138	-0.00138	0	0
9	RAIL1	PY	-6.9e-5	-6.9e-5	0	0
10	PL18	PY	-3.4e-5	-3.4e-5	0	0
11	PL17	PY	-3.4e-5	-3.4e-5	0	0
12	PL16	PY	-3.4e-5	-3.4e-5	0	0
13	PL15	PY	-3.4e-5	-3.4e-5	0	0
14	PL14	PY	-3.4e-5	-3.4e-5	0	0
15	PL13	PY	-3.4e-5	-3.4e-5	0	0
16	PL12	PY	-3.4e-5	-3.4e-5	0	0
17	PL11	PY	-3.4e-5	-3.4e-5	0	0
18	PL10	PY	-3.4e-5	-3.4e-5	0	0
19	PL9	PY	-3.4e-5	-3.4e-5	0	0
20	PL8	PY	-3.4e-5	-3.4e-5	0	0
21	PL7	PY	-3.4e-5	-3.4e-5	0	0
22	PL6	PY	-3.4e-5	-3.4e-5	0	0
23	PL5	PY	-3.4e-5	-3.4e-5	0	0
24	PL4	PY	-3.4e-5	-3.4e-5	0	0
25	PL3	PY	-3.4e-5	-3.4e-5	0	0
26	PL2	PY	-3.4e-5	-3.4e-5	0	0
27	PL1	PY	-3.4e-5	-3.4e-5	0	0
28	MP GAMMA3	PY	-0.00234	-0.00234	0	0
29	MP GAMMA2	PY	-0.00234	-0.00234	0	0
30	MP GAMMA1	PY	-0.00234	-0.00234	0	0
31	MP BETA3	PY	-0.00234	-0.00234	0	0
32	MP BETA2	PY	-0.00234	-0.00234	0	0
33	MP BETA1	PY	-0.00234	-0.00234	0	0
34	MP ALPHA3	PY	-0.00234	-0.00234	0	0
35	MP ALPHA2	PY	-0.00234	-0.00234	0	0
36	MP ALPHA1	PY	-0.00234	-0.00234	0	0
37	FACE3	PY	-0.00168	-0.00168	0	0
38	FACE2	PY	-0.00168	-0.00168	0	0
39	FACE1	PY	-8.4e-5	-8.4e-5	0	0
40	CR6	PY	-0.0023	-0.0023	0	0
41	CR5	PY	-0.0023	-0.0023	0	0
42	CR4	PY	-0.0023	-0.0023	0	0
43	CR3	PY	-0.0023	-0.0023	0	0
44	CR2	PY	-0.0023	-0.0023	0	0
45	CR1	PY	-0.0023	-0.0023	0	0
46	CPL3	PY	-2.5e-5	-2.5e-5	0	0
47	CPL2	PY	-2.5e-5	-2.5e-5	0	0
48	CPL1	PY	-2.5e-5	-2.5e-5	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 17 : Maintenance (60)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
49	ANGLE6	PY	-0.00136	-0.00136	0 0
50	ANGLE5	PY	-0.00136	-0.00136	0 0
51	ANGLE4	PY	-0.00136	-0.00136	0 0
52	ANGLE3	PY	-0.00136	-0.00136	0 0
53	ANGLE2	PY	-0.00136	-0.00136	0 0
54	ANGLE1	PY	-0.00136	-0.00136	0 0
55	SO3	PX	-0.00294	-0.00294	0 0
56	SO2	PX	-0.00294	-0.00294	0 0
57	SO1	PX	-0.00294	-0.00294	0 0
58	RPL3	PX	-0.0053	-0.0053	0 0
59	RPL2	PX	-0.0053	-0.0053	0 0
60	RPL1	PX	-0.0053	-0.0053	0 0
61	RAIL3	PX	-0.00239	-0.00239	0 0
62	RAIL2	PX	-0.00239	-0.00239	0 0
63	RAIL1	PX	-0.0012	-0.0012	0 0
64	PL18	PX	-5.9e-5	-5.9e-5	0 0
65	PL17	PX	-5.9e-5	-5.9e-5	0 0
66	PL16	PX	-5.9e-5	-5.9e-5	0 0
67	PL15	PX	-5.9e-5	-5.9e-5	0 0
68	PL14	PX	-5.9e-5	-5.9e-5	0 0
69	PL13	PX	-5.9e-5	-5.9e-5	0 0
70	PL12	PX	-5.9e-5	-5.9e-5	0 0
71	PL11	PX	-5.9e-5	-5.9e-5	0 0
72	PL10	PX	-5.9e-5	-5.9e-5	0 0
73	PL9	PX	-5.9e-5	-5.9e-5	0 0
74	PL8	PX	-5.9e-5	-5.9e-5	0 0
75	PL7	PX	-5.9e-5	-5.9e-5	0 0
76	PL6	PX	-5.9e-5	-5.9e-5	0 0
77	PL5	PX	-5.9e-5	-5.9e-5	0 0
78	PL4	PX	-5.9e-5	-5.9e-5	0 0
79	PL3	PX	-5.9e-5	-5.9e-5	0 0
80	PL2	PX	-5.9e-5	-5.9e-5	0 0
81	PL1	PX	-5.9e-5	-5.9e-5	0 0
82	MP GAMMA3	PX	-0.00406	-0.00406	0 0
83	MP GAMMA2	PX	-0.00406	-0.00406	0 0
84	MP GAMMA1	PX	-0.00406	-0.00406	0 0
85	MP BETA3	PX	-0.00406	-0.00406	0 0
86	MP BETA2	PX	-0.00406	-0.00406	0 0
87	MP BETA1	PX	-0.00406	-0.00406	0 0
88	MP ALPHA3	PX	-0.00406	-0.00406	0 0
89	MP ALPHA2	PX	-0.00406	-0.00406	0 0
90	MP ALPHA1	PX	-0.00406	-0.00406	0 0
91	FACE3	PX	-0.00291	-0.00291	0 0
92	FACE2	PX	-0.00291	-0.00291	0 0
93	FACE1	PX	-0.00146	-0.00146	0 0
94	CR6	PX	-0.00398	-0.00398	0 0
95	CR5	PX	-0.00398	-0.00398	0 0
96	CR4	PX	-0.00398	-0.00398	0 0
97	CR3	PX	-0.00398	-0.00398	0 0
98	CR2	PX	-0.00398	-0.00398	0 0
99	CR1	PX	-0.00398	-0.00398	0 0
100	CPL3	PX	-4.4e-5	-4.4e-5	0 0
101	CPL2	PX	-4.4e-5	-4.4e-5	0 0
102	CPL1	PX	-4.4e-5	-4.4e-5	0 0
103	ANGLE6	PX	-0.00235	-0.00235	0 0
104	ANGLE5	PX	-0.00235	-0.00235	0 0
105	ANGLE4	PX	-0.00235	-0.00235	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 17 : Maintenance (60)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
106	ANGLE3	PX	-0.00235	-0.00235	0	0
107	ANGLE2	PX	-0.00235	-0.00235	0	0
108	ANGLE1	PX	-0.00235	-0.00235	0	0

**Member Distributed Loads (BLC 18 : Maintenance (90))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PX	-0.0034	-0.0034	0	0
2	SO2	PX	-0.0034	-0.0034	0	0
3	SO1	PX	-0.0034	-0.0034	0	0
4	RPL3	PX	-0.00612	-0.00612	0	0
5	RPL2	PX	-0.00612	-0.00612	0	0
6	RPL1	PX	-0.00612	-0.00612	0	0
7	RAIL3	PX	-0.00276	-0.00276	0	0
8	RAIL2	PX	-0.00276	-0.00276	0	0
9	RAIL1	PX	-0.00138	-0.00138	0	0
10	PL18	PX	-6.8e-5	-6.8e-5	0	0
11	PL17	PX	-6.8e-5	-6.8e-5	0	0
12	PL16	PX	-6.8e-5	-6.8e-5	0	0
13	PL15	PX	-6.8e-5	-6.8e-5	0	0
14	PL14	PX	-6.8e-5	-6.8e-5	0	0
15	PL13	PX	-6.8e-5	-6.8e-5	0	0
16	PL12	PX	-6.8e-5	-6.8e-5	0	0
17	PL11	PX	-6.8e-5	-6.8e-5	0	0
18	PL10	PX	-6.8e-5	-6.8e-5	0	0
19	PL9	PX	-6.8e-5	-6.8e-5	0	0
20	PL8	PX	-6.8e-5	-6.8e-5	0	0
21	PL7	PX	-6.8e-5	-6.8e-5	0	0
22	PL6	PX	-6.8e-5	-6.8e-5	0	0
23	PL5	PX	-6.8e-5	-6.8e-5	0	0
24	PL4	PX	-6.8e-5	-6.8e-5	0	0
25	PL3	PX	-6.8e-5	-6.8e-5	0	0
26	PL2	PX	-6.8e-5	-6.8e-5	0	0
27	PL1	PX	-6.8e-5	-6.8e-5	0	0
28	MP GAMMA3	PX	-0.00469	-0.00469	0	0
29	MP GAMMA2	PX	-0.00469	-0.00469	0	0
30	MP GAMMA1	PX	-0.00469	-0.00469	0	0
31	MP BETA3	PX	-0.00469	-0.00469	0	0
32	MP BETA2	PX	-0.00469	-0.00469	0	0
33	MP BETA1	PX	-0.00469	-0.00469	0	0
34	MP ALPHA3	PX	-0.00469	-0.00469	0	0
35	MP ALPHA2	PX	-0.00469	-0.00469	0	0
36	MP ALPHA1	PX	-0.00469	-0.00469	0	0
37	FACE3	PX	-0.00336	-0.00336	0	0
38	FACE1	PX	-0.00336	-0.00336	0	0
39	FACE2	PX	-0.00168	-0.00168	0	0
40	CR6	PX	-0.00459	-0.00459	0	0
41	CR5	PX	-0.00459	-0.00459	0	0
42	CR4	PX	-0.00459	-0.00459	0	0
43	CR3	PX	-0.00459	-0.00459	0	0
44	CR2	PX	-0.00459	-0.00459	0	0
45	CR1	PX	-0.00459	-0.00459	0	0
46	CPL3	PX	-5.1e-5	-5.1e-5	0	0
47	CPL2	PX	-5.1e-5	-5.1e-5	0	0
48	CPL1	PX	-5.1e-5	-5.1e-5	0	0
49	ANGLE6	PX	-0.00272	-0.00272	0	0
50	ANGLE5	PX	-0.00272	-0.00272	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 18 : Maintenance (90)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
51	ANGLE4	PX	-.000272	-.000272	0	0
52	ANGLE3	PX	-.000272	-.000272	0	0
53	ANGLE2	PX	-.000272	-.000272	0	0
54	ANGLE1	PX	-.000272	-.000272	0	0

**Member Distributed Loads (BLC 19 : Maintenance (120))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.00017	.00017	0	0
2	SO2	PY	.00017	.00017	0	0
3	SO1	PY	.00017	.00017	0	0
4	RPL3	PY	.000306	.000306	0	0
5	RPL2	PY	.000306	.000306	0	0
6	RPL1	PY	.000306	.000306	0	0
7	RAIL3	PY	.000138	.000138	0	0
8	RAIL2	PY	.000138	.000138	0	0
9	RAIL1	PY	6.9e-5	6.9e-5	0	0
10	PL18	PY	3.4e-5	3.4e-5	0	0
11	PL17	PY	3.4e-5	3.4e-5	0	0
12	PL16	PY	3.4e-5	3.4e-5	0	0
13	PL15	PY	3.4e-5	3.4e-5	0	0
14	PL14	PY	3.4e-5	3.4e-5	0	0
15	PL13	PY	3.4e-5	3.4e-5	0	0
16	PL12	PY	3.4e-5	3.4e-5	0	0
17	PL11	PY	3.4e-5	3.4e-5	0	0
18	PL10	PY	3.4e-5	3.4e-5	0	0
19	PL9	PY	3.4e-5	3.4e-5	0	0
20	PL8	PY	3.4e-5	3.4e-5	0	0
21	PL7	PY	3.4e-5	3.4e-5	0	0
22	PL6	PY	3.4e-5	3.4e-5	0	0
23	PL5	PY	3.4e-5	3.4e-5	0	0
24	PL4	PY	3.4e-5	3.4e-5	0	0
25	PL3	PY	3.4e-5	3.4e-5	0	0
26	PL2	PY	3.4e-5	3.4e-5	0	0
27	PL1	PY	3.4e-5	3.4e-5	0	0
28	MP GAMMA3	PY	.000234	.000234	0	0
29	MP GAMMA2	PY	.000234	.000234	0	0
30	MP GAMMA1	PY	.000234	.000234	0	0
31	MP BETA3	PY	.000234	.000234	0	0
32	MP BETA2	PY	.000234	.000234	0	0
33	MP BETA1	PY	.000234	.000234	0	0
34	MP ALPHA3	PY	.000234	.000234	0	0
35	MP ALPHA2	PY	.000234	.000234	0	0
36	MP ALPHA1	PY	.000234	.000234	0	0
37	FACE3	PY	.000168	.000168	0	0
38	FACE1	PY	.000168	.000168	0	0
39	FACE2	PY	8.4e-5	8.4e-5	0	0
40	CR6	PY	.00023	.00023	0	0
41	CR5	PY	.00023	.00023	0	0
42	CR4	PY	.00023	.00023	0	0
43	CR3	PY	.00023	.00023	0	0
44	CR2	PY	.00023	.00023	0	0
45	CR1	PY	.00023	.00023	0	0
46	CPL3	PY	2.5e-5	2.5e-5	0	0
47	CPL2	PY	2.5e-5	2.5e-5	0	0
48	CPL1	PY	2.5e-5	2.5e-5	0	0
49	ANGLE6	PY	.000136	.000136	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 19 : Maintenance (120)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
50	ANGLE5	PY	.000136	.000136	0 0
51	ANGLE4	PY	.000136	.000136	0 0
52	ANGLE3	PY	.000136	.000136	0 0
53	ANGLE2	PY	.000136	.000136	0 0
54	ANGLE1	PY	.000136	.000136	0 0
55	SO3	PX	-.000294	-.000294	0 0
56	SO2	PX	-.000294	-.000294	0 0
57	SO1	PX	-.000294	-.000294	0 0
58	RPL3	PX	-.00053	-.00053	0 0
59	RPL2	PX	-.00053	-.00053	0 0
60	RPL1	PX	-.00053	-.00053	0 0
61	RAIL3	PX	-.000239	-.000239	0 0
62	RAIL2	PX	-.000239	-.000239	0 0
63	RAIL1	PX	-.00012	-.00012	0 0
64	PL18	PX	-5.9e-5	-5.9e-5	0 0
65	PL17	PX	-5.9e-5	-5.9e-5	0 0
66	PL16	PX	-5.9e-5	-5.9e-5	0 0
67	PL15	PX	-5.9e-5	-5.9e-5	0 0
68	PL14	PX	-5.9e-5	-5.9e-5	0 0
69	PL13	PX	-5.9e-5	-5.9e-5	0 0
70	PL12	PX	-5.9e-5	-5.9e-5	0 0
71	PL11	PX	-5.9e-5	-5.9e-5	0 0
72	PL10	PX	-5.9e-5	-5.9e-5	0 0
73	PL9	PX	-5.9e-5	-5.9e-5	0 0
74	PL8	PX	-5.9e-5	-5.9e-5	0 0
75	PL7	PX	-5.9e-5	-5.9e-5	0 0
76	PL6	PX	-5.9e-5	-5.9e-5	0 0
77	PL5	PX	-5.9e-5	-5.9e-5	0 0
78	PL4	PX	-5.9e-5	-5.9e-5	0 0
79	PL3	PX	-5.9e-5	-5.9e-5	0 0
80	PL2	PX	-5.9e-5	-5.9e-5	0 0
81	PL1	PX	-5.9e-5	-5.9e-5	0 0
82	MP GAMMA3	PX	-.000406	-.000406	0 0
83	MP GAMMA2	PX	-.000406	-.000406	0 0
84	MP GAMMA1	PX	-.000406	-.000406	0 0
85	MP BETA3	PX	-.000406	-.000406	0 0
86	MP BETA2	PX	-.000406	-.000406	0 0
87	MP BETA1	PX	-.000406	-.000406	0 0
88	MP ALPHA3	PX	-.000406	-.000406	0 0
89	MP ALPHA2	PX	-.000406	-.000406	0 0
90	MP ALPHA1	PX	-.000406	-.000406	0 0
91	FACE3	PX	-.000291	-.000291	0 0
92	FACE1	PX	-.000291	-.000291	0 0
93	FACE2	PX	-.000146	-.000146	0 0
94	CR6	PX	-.000398	-.000398	0 0
95	CR5	PX	-.000398	-.000398	0 0
96	CR4	PX	-.000398	-.000398	0 0
97	CR3	PX	-.000398	-.000398	0 0
98	CR2	PX	-.000398	-.000398	0 0
99	CR1	PX	-.000398	-.000398	0 0
100	CPL3	PX	-4.4e-5	-4.4e-5	0 0
101	CPL2	PX	-4.4e-5	-4.4e-5	0 0
102	CPL1	PX	-4.4e-5	-4.4e-5	0 0
103	ANGLE6	PX	-.000235	-.000235	0 0
104	ANGLE5	PX	-.000235	-.000235	0 0
105	ANGLE4	PX	-.000235	-.000235	0 0
106	ANGLE3	PX	-.000235	-.000235	0 0





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 19 : Maintenance (120)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
107	ANGLE2	PX	-.000235	-.000235	0	0
108	ANGLE1	PX	-.000235	-.000235	0	0

**Member Distributed Loads (BLC 20 : Maintenance (150))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.000294	.000294	0	0
2	SO2	PY	.000294	.000294	0	0
3	SO1	PY	.000294	.000294	0	0
4	RPL3	PY	.00053	.00053	0	0
5	RPL2	PY	.00053	.00053	0	0
6	RPL1	PY	.00053	.00053	0	0
7	RAIL3	PY	.000239	.000239	0	0
8	RAIL2	PY	.000239	.000239	0	0
9	RAIL1	PY	.00012	.00012	0	0
10	PL18	PY	5.9e-5	5.9e-5	0	0
11	PL17	PY	5.9e-5	5.9e-5	0	0
12	PL16	PY	5.9e-5	5.9e-5	0	0
13	PL15	PY	5.9e-5	5.9e-5	0	0
14	PL14	PY	5.9e-5	5.9e-5	0	0
15	PL13	PY	5.9e-5	5.9e-5	0	0
16	PL12	PY	5.9e-5	5.9e-5	0	0
17	PL11	PY	5.9e-5	5.9e-5	0	0
18	PL10	PY	5.9e-5	5.9e-5	0	0
19	PL9	PY	5.9e-5	5.9e-5	0	0
20	PL8	PY	5.9e-5	5.9e-5	0	0
21	PL7	PY	5.9e-5	5.9e-5	0	0
22	PL6	PY	5.9e-5	5.9e-5	0	0
23	PL5	PY	5.9e-5	5.9e-5	0	0
24	PL4	PY	5.9e-5	5.9e-5	0	0
25	PL3	PY	5.9e-5	5.9e-5	0	0
26	PL2	PY	5.9e-5	5.9e-5	0	0
27	PL1	PY	5.9e-5	5.9e-5	0	0
28	MP GAMMA3	PY	.000406	.000406	0	0
29	MP GAMMA2	PY	.000406	.000406	0	0
30	MP GAMMA1	PY	.000406	.000406	0	0
31	MP BETA3	PY	.000406	.000406	0	0
32	MP BETA2	PY	.000406	.000406	0	0
33	MP BETA1	PY	.000406	.000406	0	0
34	MP ALPHA3	PY	.000406	.000406	0	0
35	MP ALPHA2	PY	.000406	.000406	0	0
36	MP ALPHA1	PY	.000406	.000406	0	0
37	FACE3	PY	.000291	.000291	0	0
38	FACE1	PY	.000291	.000291	0	0
39	FACE2	PY	.000146	.000146	0	0
40	CR6	PY	.000398	.000398	0	0
41	CR5	PY	.000398	.000398	0	0
42	CR4	PY	.000398	.000398	0	0
43	CR3	PY	.000398	.000398	0	0
44	CR2	PY	.000398	.000398	0	0
45	CR1	PY	.000398	.000398	0	0
46	CPL3	PY	4.4e-5	4.4e-5	0	0
47	CPL2	PY	4.4e-5	4.4e-5	0	0
48	CPL1	PY	4.4e-5	4.4e-5	0	0
49	ANGLE6	PY	.000235	.000235	0	0
50	ANGLE5	PY	.000235	.000235	0	0
51	ANGLE4	PY	.000235	.000235	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 20 : Maintenance (150)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft,%]	End Location[ft,%]
52	ANGLE3	PY	.000235	.000235	0 0
53	ANGLE2	PY	.000235	.000235	0 0
54	ANGLE1	PY	.000235	.000235	0 0
55	SO3	PX	-.00017	-.00017	0 0
56	SO2	PX	-.00017	-.00017	0 0
57	SO1	PX	-.00017	-.00017	0 0
58	RPL3	PX	-.000306	-.000306	0 0
59	RPL2	PX	-.000306	-.000306	0 0
60	RPL1	PX	-.000306	-.000306	0 0
61	RAIL3	PX	-.000138	-.000138	0 0
62	RAIL2	PX	-.000138	-.000138	0 0
63	RAIL1	PX	-6.9e-5	-6.9e-5	0 0
64	PL18	PX	-3.4e-5	-3.4e-5	0 0
65	PL17	PX	-3.4e-5	-3.4e-5	0 0
66	PL16	PX	-3.4e-5	-3.4e-5	0 0
67	PL15	PX	-3.4e-5	-3.4e-5	0 0
68	PL14	PX	-3.4e-5	-3.4e-5	0 0
69	PL13	PX	-3.4e-5	-3.4e-5	0 0
70	PL12	PX	-3.4e-5	-3.4e-5	0 0
71	PL11	PX	-3.4e-5	-3.4e-5	0 0
72	PL10	PX	-3.4e-5	-3.4e-5	0 0
73	PL9	PX	-3.4e-5	-3.4e-5	0 0
74	PL8	PX	-3.4e-5	-3.4e-5	0 0
75	PL7	PX	-3.4e-5	-3.4e-5	0 0
76	PL6	PX	-3.4e-5	-3.4e-5	0 0
77	PL5	PX	-3.4e-5	-3.4e-5	0 0
78	PL4	PX	-3.4e-5	-3.4e-5	0 0
79	PL3	PX	-3.4e-5	-3.4e-5	0 0
80	PL2	PX	-3.4e-5	-3.4e-5	0 0
81	PL1	PX	-3.4e-5	-3.4e-5	0 0
82	MP GAMMA3	PX	-.000234	-.000234	0 0
83	MP GAMMA2	PX	-.000234	-.000234	0 0
84	MP GAMMA1	PX	-.000234	-.000234	0 0
85	MP BETA3	PX	-.000234	-.000234	0 0
86	MP BETA2	PX	-.000234	-.000234	0 0
87	MP BETA1	PX	-.000234	-.000234	0 0
88	MP ALPHA3	PX	-.000234	-.000234	0 0
89	MP ALPHA2	PX	-.000234	-.000234	0 0
90	MP ALPHA1	PX	-.000234	-.000234	0 0
91	FACE3	PX	-.000168	-.000168	0 0
92	FACE1	PX	-.000168	-.000168	0 0
93	FACE2	PX	-8.4e-5	-8.4e-5	0 0
94	CR6	PX	-.00023	-.00023	0 0
95	CR5	PX	-.00023	-.00023	0 0
96	CR4	PX	-.00023	-.00023	0 0
97	CR3	PX	-.00023	-.00023	0 0
98	CR2	PX	-.00023	-.00023	0 0
99	CR1	PX	-.00023	-.00023	0 0
100	CPL3	PX	-2.5e-5	-2.5e-5	0 0
101	CPL2	PX	-2.5e-5	-2.5e-5	0 0
102	CPL1	PX	-2.5e-5	-2.5e-5	0 0
103	ANGLE6	PX	-.000136	-.000136	0 0
104	ANGLE5	PX	-.000136	-.000136	0 0
105	ANGLE4	PX	-.000136	-.000136	0 0
106	ANGLE3	PX	-.000136	-.000136	0 0
107	ANGLE2	PX	-.000136	-.000136	0 0
108	ANGLE1	PX	-.000136	-.000136	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 21 : Maintenance (180))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
1	SO3	PY	.00034	.00034	0	0
2	SO2	PY	.00034	.00034	0	0
3	SO1	PY	.00034	.00034	0	0
4	RPL3	PY	.000612	.000612	0	0
5	RPL2	PY	.000612	.000612	0	0
6	RPL1	PY	.000612	.000612	0	0
7	RAIL3	PY	.000276	.000276	0	0
8	RAIL2	PY	.000276	.000276	0	0
9	RAIL1	PY	.000138	.000138	0	0
10	PL18	PY	6.8e-5	6.8e-5	0	0
11	PL17	PY	6.8e-5	6.8e-5	0	0
12	PL16	PY	6.8e-5	6.8e-5	0	0
13	PL15	PY	6.8e-5	6.8e-5	0	0
14	PL14	PY	6.8e-5	6.8e-5	0	0
15	PL13	PY	6.8e-5	6.8e-5	0	0
16	PL12	PY	6.8e-5	6.8e-5	0	0
17	PL11	PY	6.8e-5	6.8e-5	0	0
18	PL10	PY	6.8e-5	6.8e-5	0	0
19	PL9	PY	6.8e-5	6.8e-5	0	0
20	PL8	PY	6.8e-5	6.8e-5	0	0
21	PL7	PY	6.8e-5	6.8e-5	0	0
22	PL6	PY	6.8e-5	6.8e-5	0	0
23	PL5	PY	6.8e-5	6.8e-5	0	0
24	PL4	PY	6.8e-5	6.8e-5	0	0
25	PL3	PY	6.8e-5	6.8e-5	0	0
26	PL2	PY	6.8e-5	6.8e-5	0	0
27	PL1	PY	6.8e-5	6.8e-5	0	0
28	MP GAMMA3	PY	.000469	.000469	0	0
29	MP GAMMA2	PY	.000469	.000469	0	0
30	MP GAMMA1	PY	.000469	.000469	0	0
31	MP BETA3	PY	.000469	.000469	0	0
32	MP BETA2	PY	.000469	.000469	0	0
33	MP BETA1	PY	.000469	.000469	0	0
34	MP ALPHA3	PY	.000469	.000469	0	0
35	MP ALPHA2	PY	.000469	.000469	0	0
36	MP ALPHA1	PY	.000469	.000469	0	0
37	FACE3	PY	.000336	.000336	0	0
38	FACE1	PY	.000336	.000336	0	0
39	FACE2	PY	.000168	.000168	0	0
40	CR6	PY	.000459	.000459	0	0
41	CR5	PY	.000459	.000459	0	0
42	CR4	PY	.000459	.000459	0	0
43	CR3	PY	.000459	.000459	0	0
44	CR2	PY	.000459	.000459	0	0
45	CR1	PY	.000459	.000459	0	0
46	CPL3	PY	5.1e-5	5.1e-5	0	0
47	CPL2	PY	5.1e-5	5.1e-5	0	0
48	CPL1	PY	5.1e-5	5.1e-5	0	0
49	ANGLE6	PY	.000272	.000272	0	0
50	ANGLE5	PY	.000272	.000272	0	0
51	ANGLE4	PY	.000272	.000272	0	0
52	ANGLE3	PY	.000272	.000272	0	0
53	ANGLE2	PY	.000272	.000272	0	0
54	ANGLE1	PY	.000272	.000272	0	0

**Member Distributed Loads (BLC 22 : Maintenance (210))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
--	--------------	-----------	------------------------	----------------------	----------------------	--------------------



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 22 : Maintenance (210)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.000294	.000294	0	0
2	SO2	PY	.000294	.000294	0	0
3	SO1	PY	.000294	.000294	0	0
4	RPL3	PY	.00053	.00053	0	0
5	RPL2	PY	.00053	.00053	0	0
6	RPL1	PY	.00053	.00053	0	0
7	RAIL3	PY	.000239	.000239	0	0
8	RAIL2	PY	.000239	.000239	0	0
9	RAIL1	PY	.00012	.00012	0	0
10	PL18	PY	5.9e-5	5.9e-5	0	0
11	PL17	PY	5.9e-5	5.9e-5	0	0
12	PL16	PY	5.9e-5	5.9e-5	0	0
13	PL15	PY	5.9e-5	5.9e-5	0	0
14	PL14	PY	5.9e-5	5.9e-5	0	0
15	PL13	PY	5.9e-5	5.9e-5	0	0
16	PL12	PY	5.9e-5	5.9e-5	0	0
17	PL11	PY	5.9e-5	5.9e-5	0	0
18	PL10	PY	5.9e-5	5.9e-5	0	0
19	PL9	PY	5.9e-5	5.9e-5	0	0
20	PL8	PY	5.9e-5	5.9e-5	0	0
21	PL7	PY	5.9e-5	5.9e-5	0	0
22	PL6	PY	5.9e-5	5.9e-5	0	0
23	PL5	PY	5.9e-5	5.9e-5	0	0
24	PL4	PY	5.9e-5	5.9e-5	0	0
25	PL3	PY	5.9e-5	5.9e-5	0	0
26	PL2	PY	5.9e-5	5.9e-5	0	0
27	PL1	PY	5.9e-5	5.9e-5	0	0
28	MP GAMMA3	PY	.000406	.000406	0	0
29	MP GAMMA2	PY	.000406	.000406	0	0
30	MP GAMMA1	PY	.000406	.000406	0	0
31	MP BETA3	PY	.000406	.000406	0	0
32	MP BETA2	PY	.000406	.000406	0	0
33	MP BETA1	PY	.000406	.000406	0	0
34	MP ALPHA3	PY	.000406	.000406	0	0
35	MP ALPHA2	PY	.000406	.000406	0	0
36	MP ALPHA1	PY	.000406	.000406	0	0
37	FACE1	PY	.000291	.000291	0	0
38	FACE2	PY	.000291	.000291	0	0
39	FACE3	PY	.000146	.000146	0	0
40	CR6	PY	.000398	.000398	0	0
41	CR5	PY	.000398	.000398	0	0
42	CR4	PY	.000398	.000398	0	0
43	CR3	PY	.000398	.000398	0	0
44	CR2	PY	.000398	.000398	0	0
45	CR1	PY	.000398	.000398	0	0
46	CPL3	PY	4.4e-5	4.4e-5	0	0
47	CPL2	PY	4.4e-5	4.4e-5	0	0
48	CPL1	PY	4.4e-5	4.4e-5	0	0
49	ANGLE6	PY	.000235	.000235	0	0
50	ANGLE5	PY	.000235	.000235	0	0
51	ANGLE4	PY	.000235	.000235	0	0
52	ANGLE3	PY	.000235	.000235	0	0
53	ANGLE2	PY	.000235	.000235	0	0
54	ANGLE1	PY	.000235	.000235	0	0
55	SO3	PX	.00017	.00017	0	0
56	SO2	PX	.00017	.00017	0	0
57	SO1	PX	.00017	.00017	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 22 : Maintenance (210)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
58	RPL3	PX	.000306	.000306	0	0
59	RPL2	PX	.000306	.000306	0	0
60	RPL1	PX	.000306	.000306	0	0
61	RAIL3	PX	.000138	.000138	0	0
62	RAIL2	PX	.000138	.000138	0	0
63	RAIL1	PX	6.9e-5	6.9e-5	0	0
64	PL18	PX	3.4e-5	3.4e-5	0	0
65	PL17	PX	3.4e-5	3.4e-5	0	0
66	PL16	PX	3.4e-5	3.4e-5	0	0
67	PL15	PX	3.4e-5	3.4e-5	0	0
68	PL14	PX	3.4e-5	3.4e-5	0	0
69	PL13	PX	3.4e-5	3.4e-5	0	0
70	PL12	PX	3.4e-5	3.4e-5	0	0
71	PL11	PX	3.4e-5	3.4e-5	0	0
72	PL10	PX	3.4e-5	3.4e-5	0	0
73	PL9	PX	3.4e-5	3.4e-5	0	0
74	PL8	PX	3.4e-5	3.4e-5	0	0
75	PL7	PX	3.4e-5	3.4e-5	0	0
76	PL6	PX	3.4e-5	3.4e-5	0	0
77	PL5	PX	3.4e-5	3.4e-5	0	0
78	PL4	PX	3.4e-5	3.4e-5	0	0
79	PL3	PX	3.4e-5	3.4e-5	0	0
80	PL2	PX	3.4e-5	3.4e-5	0	0
81	PL1	PX	3.4e-5	3.4e-5	0	0
82	MP GAMMA3	PX	.000234	.000234	0	0
83	MP GAMMA2	PX	.000234	.000234	0	0
84	MP GAMMA1	PX	.000234	.000234	0	0
85	MP BETA3	PX	.000234	.000234	0	0
86	MP BETA2	PX	.000234	.000234	0	0
87	MP BETA1	PX	.000234	.000234	0	0
88	MP ALPHA3	PX	.000234	.000234	0	0
89	MP ALPHA2	PX	.000234	.000234	0	0
90	MP ALPHA1	PX	.000234	.000234	0	0
91	FACE1	PX	.000168	.000168	0	0
92	FACE2	PX	.000168	.000168	0	0
93	FACE3	PX	8.4e-5	8.4e-5	0	0
94	CR6	PX	.00023	.00023	0	0
95	CR5	PX	.00023	.00023	0	0
96	CR4	PX	.00023	.00023	0	0
97	CR3	PX	.00023	.00023	0	0
98	CR2	PX	.00023	.00023	0	0
99	CR1	PX	.00023	.00023	0	0
100	CPL3	PX	2.5e-5	2.5e-5	0	0
101	CPL2	PX	2.5e-5	2.5e-5	0	0
102	CPL1	PX	2.5e-5	2.5e-5	0	0
103	ANGLE6	PX	.000136	.000136	0	0
104	ANGLE5	PX	.000136	.000136	0	0
105	ANGLE4	PX	.000136	.000136	0	0
106	ANGLE3	PX	.000136	.000136	0	0
107	ANGLE2	PX	.000136	.000136	0	0
108	ANGLE1	PX	.000136	.000136	0	0

**Member Distributed Loads (BLC 23 : Maintenance (240))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.00017	.00017	0	0
2	SO2	PY	.00017	.00017	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 23 : Maintenance (240)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
3	SO1	PY	.00017	.00017	0 0
4	RPL3	PY	.000306	.000306	0 0
5	RPL2	PY	.000306	.000306	0 0
6	RPL1	PY	.000306	.000306	0 0
7	RAIL3	PY	.000138	.000138	0 0
8	RAIL2	PY	.000138	.000138	0 0
9	RAIL1	PY	6.9e-5	6.9e-5	0 0
10	PL18	PY	3.4e-5	3.4e-5	0 0
11	PL17	PY	3.4e-5	3.4e-5	0 0
12	PL16	PY	3.4e-5	3.4e-5	0 0
13	PL15	PY	3.4e-5	3.4e-5	0 0
14	PL14	PY	3.4e-5	3.4e-5	0 0
15	PL13	PY	3.4e-5	3.4e-5	0 0
16	PL12	PY	3.4e-5	3.4e-5	0 0
17	PL11	PY	3.4e-5	3.4e-5	0 0
18	PL10	PY	3.4e-5	3.4e-5	0 0
19	PL9	PY	3.4e-5	3.4e-5	0 0
20	PL8	PY	3.4e-5	3.4e-5	0 0
21	PL7	PY	3.4e-5	3.4e-5	0 0
22	PL6	PY	3.4e-5	3.4e-5	0 0
23	PL5	PY	3.4e-5	3.4e-5	0 0
24	PL4	PY	3.4e-5	3.4e-5	0 0
25	PL3	PY	3.4e-5	3.4e-5	0 0
26	PL2	PY	3.4e-5	3.4e-5	0 0
27	PL1	PY	3.4e-5	3.4e-5	0 0
28	MP GAMMA3	PY	.000234	.000234	0 0
29	MP GAMMA2	PY	.000234	.000234	0 0
30	MP GAMMA1	PY	.000234	.000234	0 0
31	MP BETA3	PY	.000234	.000234	0 0
32	MP BETA2	PY	.000234	.000234	0 0
33	MP BETA1	PY	.000234	.000234	0 0
34	MP ALPHA3	PY	.000234	.000234	0 0
35	MP ALPHA2	PY	.000234	.000234	0 0
36	MP ALPHA1	PY	.000234	.000234	0 0
37	FACE1	PY	.000168	.000168	0 0
38	FACE2	PY	.000168	.000168	0 0
39	FACE3	PY	8.4e-5	8.4e-5	0 0
40	CR6	PY	.00023	.00023	0 0
41	CR5	PY	.00023	.00023	0 0
42	CR4	PY	.00023	.00023	0 0
43	CR3	PY	.00023	.00023	0 0
44	CR2	PY	.00023	.00023	0 0
45	CR1	PY	.00023	.00023	0 0
46	CPL3	PY	2.5e-5	2.5e-5	0 0
47	CPL2	PY	2.5e-5	2.5e-5	0 0
48	CPL1	PY	2.5e-5	2.5e-5	0 0
49	ANGLE6	PY	.000136	.000136	0 0
50	ANGLE5	PY	.000136	.000136	0 0
51	ANGLE4	PY	.000136	.000136	0 0
52	ANGLE3	PY	.000136	.000136	0 0
53	ANGLE2	PY	.000136	.000136	0 0
54	ANGLE1	PY	.000136	.000136	0 0
55	SO3	PX	.000294	.000294	0 0
56	SO2	PX	.000294	.000294	0 0
57	SO1	PX	.000294	.000294	0 0
58	RPL3	PX	.00053	.00053	0 0
59	RPL2	PX	.00053	.00053	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 23 : Maintenance (240)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
60	RPL1	PX	.00053	.00053	0	0
61	RAIL3	PX	.000239	.000239	0	0
62	RAIL2	PX	.000239	.000239	0	0
63	RAIL1	PX	.00012	.00012	0	0
64	PL18	PX	5.9e-5	5.9e-5	0	0
65	PL17	PX	5.9e-5	5.9e-5	0	0
66	PL16	PX	5.9e-5	5.9e-5	0	0
67	PL15	PX	5.9e-5	5.9e-5	0	0
68	PL14	PX	5.9e-5	5.9e-5	0	0
69	PL13	PX	5.9e-5	5.9e-5	0	0
70	PL12	PX	5.9e-5	5.9e-5	0	0
71	PL11	PX	5.9e-5	5.9e-5	0	0
72	PL10	PX	5.9e-5	5.9e-5	0	0
73	PL9	PX	5.9e-5	5.9e-5	0	0
74	PL8	PX	5.9e-5	5.9e-5	0	0
75	PL7	PX	5.9e-5	5.9e-5	0	0
76	PL6	PX	5.9e-5	5.9e-5	0	0
77	PL5	PX	5.9e-5	5.9e-5	0	0
78	PL4	PX	5.9e-5	5.9e-5	0	0
79	PL3	PX	5.9e-5	5.9e-5	0	0
80	PL2	PX	5.9e-5	5.9e-5	0	0
81	PL1	PX	5.9e-5	5.9e-5	0	0
82	MP GAMMA3	PX	.000406	.000406	0	0
83	MP GAMMA2	PX	.000406	.000406	0	0
84	MP GAMMA1	PX	.000406	.000406	0	0
85	MP BETA3	PX	.000406	.000406	0	0
86	MP BETA2	PX	.000406	.000406	0	0
87	MP BETA1	PX	.000406	.000406	0	0
88	MP ALPHA3	PX	.000406	.000406	0	0
89	MP ALPHA2	PX	.000406	.000406	0	0
90	MP ALPHA1	PX	.000406	.000406	0	0
91	FACE1	PX	.000291	.000291	0	0
92	FACE2	PX	.000291	.000291	0	0
93	FACE3	PX	.000146	.000146	0	0
94	CR6	PX	.000398	.000398	0	0
95	CR5	PX	.000398	.000398	0	0
96	CR4	PX	.000398	.000398	0	0
97	CR3	PX	.000398	.000398	0	0
98	CR2	PX	.000398	.000398	0	0
99	CR1	PX	.000398	.000398	0	0
100	CPL3	PX	4.4e-5	4.4e-5	0	0
101	CPL2	PX	4.4e-5	4.4e-5	0	0
102	CPL1	PX	4.4e-5	4.4e-5	0	0
103	ANGLE6	PX	.000235	.000235	0	0
104	ANGLE5	PX	.000235	.000235	0	0
105	ANGLE4	PX	.000235	.000235	0	0
106	ANGLE3	PX	.000235	.000235	0	0
107	ANGLE2	PX	.000235	.000235	0	0
108	ANGLE1	PX	.000235	.000235	0	0

**Member Distributed Loads (BLC 24 : Maintenance (270))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PX	.00034	.00034	0	0
2	SO2	PX	.00034	.00034	0	0
3	SO1	PX	.00034	.00034	0	0
4	RPL3	PX	.000612	.000612	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 24 : Maintenance (270)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft.%,]	End Location[ft.%,]
5	RPL2	PX	.000612	.000612	0	0
6	RPL1	PX	.000612	.000612	0	0
7	RAIL3	PX	.000276	.000276	0	0
8	RAIL2	PX	.000276	.000276	0	0
9	RAIL1	PX	.000138	.000138	0	0
10	PL18	PX	6.8e-5	6.8e-5	0	0
11	PL17	PX	6.8e-5	6.8e-5	0	0
12	PL16	PX	6.8e-5	6.8e-5	0	0
13	PL15	PX	6.8e-5	6.8e-5	0	0
14	PL14	PX	6.8e-5	6.8e-5	0	0
15	PL13	PX	6.8e-5	6.8e-5	0	0
16	PL12	PX	6.8e-5	6.8e-5	0	0
17	PL11	PX	6.8e-5	6.8e-5	0	0
18	PL10	PX	6.8e-5	6.8e-5	0	0
19	PL9	PX	6.8e-5	6.8e-5	0	0
20	PL8	PX	6.8e-5	6.8e-5	0	0
21	PL7	PX	6.8e-5	6.8e-5	0	0
22	PL6	PX	6.8e-5	6.8e-5	0	0
23	PL5	PX	6.8e-5	6.8e-5	0	0
24	PL4	PX	6.8e-5	6.8e-5	0	0
25	PL3	PX	6.8e-5	6.8e-5	0	0
26	PL2	PX	6.8e-5	6.8e-5	0	0
27	PL1	PX	6.8e-5	6.8e-5	0	0
28	MP GAMMA3	PX	.000469	.000469	0	0
29	MP GAMMA2	PX	.000469	.000469	0	0
30	MP GAMMA1	PX	.000469	.000469	0	0
31	MP BETA3	PX	.000469	.000469	0	0
32	MP BETA2	PX	.000469	.000469	0	0
33	MP BETA1	PX	.000469	.000469	0	0
34	MP ALPHA3	PX	.000469	.000469	0	0
35	MP ALPHA2	PX	.000469	.000469	0	0
36	MP ALPHA1	PX	.000469	.000469	0	0
37	FACE1	PX	.000336	.000336	0	0
38	FACE2	PX	.000336	.000336	0	0
39	FACE3	PX	.000168	.000168	0	0
40	CR6	PX	.000459	.000459	0	0
41	CR5	PX	.000459	.000459	0	0
42	CR4	PX	.000459	.000459	0	0
43	CR3	PX	.000459	.000459	0	0
44	CR2	PX	.000459	.000459	0	0
45	CR1	PX	.000459	.000459	0	0
46	CPL3	PX	5.1e-5	5.1e-5	0	0
47	CPL2	PX	5.1e-5	5.1e-5	0	0
48	CPL1	PX	5.1e-5	5.1e-5	0	0
49	ANGLE6	PX	.000272	.000272	0	0
50	ANGLE5	PX	.000272	.000272	0	0
51	ANGLE4	PX	.000272	.000272	0	0
52	ANGLE3	PX	.000272	.000272	0	0
53	ANGLE2	PX	.000272	.000272	0	0
54	ANGLE1	PX	.000272	.000272	0	0

**Member Distributed Loads (BLC 25 : Maintenance (300))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft.%,]	End Location[ft.%,]
1	SO3	PY	-.00017	-.00017	0	0
2	SO2	PY	-.00017	-.00017	0	0
3	SO1	PY	-.00017	-.00017	0	0





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 25 : Maintenance (300)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
4	RPL3	PY	-0.000306	-0.000306	0	0
5	RPL2	PY	-0.000306	-0.000306	0	0
6	RPL1	PY	-0.000306	-0.000306	0	0
7	RAIL3	PY	-0.000138	-0.000138	0	0
8	RAIL2	PY	-0.000138	-0.000138	0	0
9	RAIL1	PY	-6.9e-5	-6.9e-5	0	0
10	PL18	PY	-3.4e-5	-3.4e-5	0	0
11	PL17	PY	-3.4e-5	-3.4e-5	0	0
12	PL16	PY	-3.4e-5	-3.4e-5	0	0
13	PL15	PY	-3.4e-5	-3.4e-5	0	0
14	PL14	PY	-3.4e-5	-3.4e-5	0	0
15	PL13	PY	-3.4e-5	-3.4e-5	0	0
16	PL12	PY	-3.4e-5	-3.4e-5	0	0
17	PL11	PY	-3.4e-5	-3.4e-5	0	0
18	PL10	PY	-3.4e-5	-3.4e-5	0	0
19	PL9	PY	-3.4e-5	-3.4e-5	0	0
20	PL8	PY	-3.4e-5	-3.4e-5	0	0
21	PL7	PY	-3.4e-5	-3.4e-5	0	0
22	PL6	PY	-3.4e-5	-3.4e-5	0	0
23	PL5	PY	-3.4e-5	-3.4e-5	0	0
24	PL4	PY	-3.4e-5	-3.4e-5	0	0
25	PL3	PY	-3.4e-5	-3.4e-5	0	0
26	PL2	PY	-3.4e-5	-3.4e-5	0	0
27	PL1	PY	-3.4e-5	-3.4e-5	0	0
28	MP GAMMA3	PY	-0.000234	-0.000234	0	0
29	MP GAMMA2	PY	-0.000234	-0.000234	0	0
30	MP GAMMA1	PY	-0.000234	-0.000234	0	0
31	MP BETA3	PY	-0.000234	-0.000234	0	0
32	MP BETA2	PY	-0.000234	-0.000234	0	0
33	MP BETA1	PY	-0.000234	-0.000234	0	0
34	MP ALPHA3	PY	-0.000234	-0.000234	0	0
35	MP ALPHA2	PY	-0.000234	-0.000234	0	0
36	MP ALPHA1	PY	-0.000234	-0.000234	0	0
37	FACE1	PY	-0.000168	-0.000168	0	0
38	FACE2	PY	-0.000168	-0.000168	0	0
39	FACE3	PY	-8.4e-5	-8.4e-5	0	0
40	CR6	PY	-0.00023	-0.00023	0	0
41	CR5	PY	-0.00023	-0.00023	0	0
42	CR4	PY	-0.00023	-0.00023	0	0
43	CR3	PY	-0.00023	-0.00023	0	0
44	CR2	PY	-0.00023	-0.00023	0	0
45	CR1	PY	-0.00023	-0.00023	0	0
46	CPL3	PY	-2.5e-5	-2.5e-5	0	0
47	CPL2	PY	-2.5e-5	-2.5e-5	0	0
48	CPL1	PY	-2.5e-5	-2.5e-5	0	0
49	ANGLE6	PY	-0.000136	-0.000136	0	0
50	ANGLE5	PY	-0.000136	-0.000136	0	0
51	ANGLE4	PY	-0.000136	-0.000136	0	0
52	ANGLE3	PY	-0.000136	-0.000136	0	0
53	ANGLE2	PY	-0.000136	-0.000136	0	0
54	ANGLE1	PY	-0.000136	-0.000136	0	0
55	SO3	PX	.000294	.000294	0	0
56	SO2	PX	.000294	.000294	0	0
57	SO1	PX	.000294	.000294	0	0
58	RPL3	PX	.00053	.00053	0	0
59	RPL2	PX	.00053	.00053	0	0
60	RPL1	PX	.00053	.00053	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 25 : Maintenance (300)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
61	RAIL3	PX	.000239	.000239	0	0
62	RAIL2	PX	.000239	.000239	0	0
63	RAIL1	PX	.00012	.00012	0	0
64	PL18	PX	5.9e-5	5.9e-5	0	0
65	PL17	PX	5.9e-5	5.9e-5	0	0
66	PL16	PX	5.9e-5	5.9e-5	0	0
67	PL15	PX	5.9e-5	5.9e-5	0	0
68	PL14	PX	5.9e-5	5.9e-5	0	0
69	PL13	PX	5.9e-5	5.9e-5	0	0
70	PL12	PX	5.9e-5	5.9e-5	0	0
71	PL11	PX	5.9e-5	5.9e-5	0	0
72	PL10	PX	5.9e-5	5.9e-5	0	0
73	PL9	PX	5.9e-5	5.9e-5	0	0
74	PL8	PX	5.9e-5	5.9e-5	0	0
75	PL7	PX	5.9e-5	5.9e-5	0	0
76	PL6	PX	5.9e-5	5.9e-5	0	0
77	PL5	PX	5.9e-5	5.9e-5	0	0
78	PL4	PX	5.9e-5	5.9e-5	0	0
79	PL3	PX	5.9e-5	5.9e-5	0	0
80	PL2	PX	5.9e-5	5.9e-5	0	0
81	PL1	PX	5.9e-5	5.9e-5	0	0
82	MP GAMMA3	PX	.000406	.000406	0	0
83	MP GAMMA2	PX	.000406	.000406	0	0
84	MP GAMMA1	PX	.000406	.000406	0	0
85	MP BETA3	PX	.000406	.000406	0	0
86	MP BETA2	PX	.000406	.000406	0	0
87	MP BETA1	PX	.000406	.000406	0	0
88	MP ALPHA3	PX	.000406	.000406	0	0
89	MP ALPHA2	PX	.000406	.000406	0	0
90	MP ALPHA1	PX	.000406	.000406	0	0
91	FACE1	PX	.000291	.000291	0	0
92	FACE2	PX	.000291	.000291	0	0
93	FACE3	PX	.000146	.000146	0	0
94	CR6	PX	.000398	.000398	0	0
95	CR5	PX	.000398	.000398	0	0
96	CR4	PX	.000398	.000398	0	0
97	CR3	PX	.000398	.000398	0	0
98	CR2	PX	.000398	.000398	0	0
99	CR1	PX	.000398	.000398	0	0
100	CPL3	PX	4.4e-5	4.4e-5	0	0
101	CPL2	PX	4.4e-5	4.4e-5	0	0
102	CPL1	PX	4.4e-5	4.4e-5	0	0
103	ANGLE6	PX	.000235	.000235	0	0
104	ANGLE5	PX	.000235	.000235	0	0
105	ANGLE4	PX	.000235	.000235	0	0
106	ANGLE3	PX	.000235	.000235	0	0
107	ANGLE2	PX	.000235	.000235	0	0
108	ANGLE1	PX	.000235	.000235	0	0

**Member Distributed Loads (BLC 26 : Maintenance (330))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-.000294	-.000294	0	0
2	SO2	PY	-.000294	-.000294	0	0
3	SO1	PY	-.000294	-.000294	0	0
4	RPL3	PY	-.00053	-.00053	0	0
5	RPL2	PY	-.00053	-.00053	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 26 : Maintenance (330)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
6	RPL1	PY	-0.00053	-0.00053	0 0
7	RAIL3	PY	-0.000239	-0.000239	0 0
8	RAIL2	PY	-0.000239	-0.000239	0 0
9	RAIL1	PY	-0.00012	-0.00012	0 0
10	PL18	PY	-5.9e-5	-5.9e-5	0 0
11	PL17	PY	-5.9e-5	-5.9e-5	0 0
12	PL16	PY	-5.9e-5	-5.9e-5	0 0
13	PL15	PY	-5.9e-5	-5.9e-5	0 0
14	PL14	PY	-5.9e-5	-5.9e-5	0 0
15	PL13	PY	-5.9e-5	-5.9e-5	0 0
16	PL12	PY	-5.9e-5	-5.9e-5	0 0
17	PL11	PY	-5.9e-5	-5.9e-5	0 0
18	PL10	PY	-5.9e-5	-5.9e-5	0 0
19	PL9	PY	-5.9e-5	-5.9e-5	0 0
20	PL8	PY	-5.9e-5	-5.9e-5	0 0
21	PL7	PY	-5.9e-5	-5.9e-5	0 0
22	PL6	PY	-5.9e-5	-5.9e-5	0 0
23	PL5	PY	-5.9e-5	-5.9e-5	0 0
24	PL4	PY	-5.9e-5	-5.9e-5	0 0
25	PL3	PY	-5.9e-5	-5.9e-5	0 0
26	PL2	PY	-5.9e-5	-5.9e-5	0 0
27	PL1	PY	-5.9e-5	-5.9e-5	0 0
28	MP GAMMA3	PY	-0.000406	-0.000406	0 0
29	MP GAMMA2	PY	-0.000406	-0.000406	0 0
30	MP GAMMA1	PY	-0.000406	-0.000406	0 0
31	MP BETA3	PY	-0.000406	-0.000406	0 0
32	MP BETA2	PY	-0.000406	-0.000406	0 0
33	MP BETA1	PY	-0.000406	-0.000406	0 0
34	MP ALPHA3	PY	-0.000406	-0.000406	0 0
35	MP ALPHA2	PY	-0.000406	-0.000406	0 0
36	MP ALPHA1	PY	-0.000406	-0.000406	0 0
37	FACE3	PY	-0.000291	-0.000291	0 0
38	FACE2	PY	-0.000291	-0.000291	0 0
39	FACE1	PY	-0.000146	-0.000146	0 0
40	CR6	PY	-0.000398	-0.000398	0 0
41	CR5	PY	-0.000398	-0.000398	0 0
42	CR4	PY	-0.000398	-0.000398	0 0
43	CR3	PY	-0.000398	-0.000398	0 0
44	CR2	PY	-0.000398	-0.000398	0 0
45	CR1	PY	-0.000398	-0.000398	0 0
46	CPL3	PY	-4.4e-5	-4.4e-5	0 0
47	CPL2	PY	-4.4e-5	-4.4e-5	0 0
48	CPL1	PY	-4.4e-5	-4.4e-5	0 0
49	ANGLE6	PY	-0.000235	-0.000235	0 0
50	ANGLE5	PY	-0.000235	-0.000235	0 0
51	ANGLE4	PY	-0.000235	-0.000235	0 0
52	ANGLE3	PY	-0.000235	-0.000235	0 0
53	ANGLE2	PY	-0.000235	-0.000235	0 0
54	ANGLE1	PY	-0.000235	-0.000235	0 0
55	SO3	PX	.00017	.00017	0 0
56	SO2	PX	.00017	.00017	0 0
57	SO1	PX	.00017	.00017	0 0
58	RPL3	PX	.000306	.000306	0 0
59	RPL2	PX	.000306	.000306	0 0
60	RPL1	PX	.000306	.000306	0 0
61	RAIL3	PX	.000138	.000138	0 0
62	RAIL2	PX	.000138	.000138	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 26 : Maintenance (330)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
63	RAIL1	PX	6.9e-5	6.9e-5	0	0
64	PL18	PX	3.4e-5	3.4e-5	0	0
65	PL17	PX	3.4e-5	3.4e-5	0	0
66	PL16	PX	3.4e-5	3.4e-5	0	0
67	PL15	PX	3.4e-5	3.4e-5	0	0
68	PL14	PX	3.4e-5	3.4e-5	0	0
69	PL13	PX	3.4e-5	3.4e-5	0	0
70	PL12	PX	3.4e-5	3.4e-5	0	0
71	PL11	PX	3.4e-5	3.4e-5	0	0
72	PL10	PX	3.4e-5	3.4e-5	0	0
73	PL9	PX	3.4e-5	3.4e-5	0	0
74	PL8	PX	3.4e-5	3.4e-5	0	0
75	PL7	PX	3.4e-5	3.4e-5	0	0
76	PL6	PX	3.4e-5	3.4e-5	0	0
77	PL5	PX	3.4e-5	3.4e-5	0	0
78	PL4	PX	3.4e-5	3.4e-5	0	0
79	PL3	PX	3.4e-5	3.4e-5	0	0
80	PL2	PX	3.4e-5	3.4e-5	0	0
81	PL1	PX	3.4e-5	3.4e-5	0	0
82	MP GAMMA3	PX	.000234	.000234	0	0
83	MP GAMMA2	PX	.000234	.000234	0	0
84	MP GAMMA1	PX	.000234	.000234	0	0
85	MP BETA3	PX	.000234	.000234	0	0
86	MP BETA2	PX	.000234	.000234	0	0
87	MP BETA1	PX	.000234	.000234	0	0
88	MP ALPHA3	PX	.000234	.000234	0	0
89	MP ALPHA2	PX	.000234	.000234	0	0
90	MP ALPHA1	PX	.000234	.000234	0	0
91	FACE3	PX	.000168	.000168	0	0
92	FACE2	PX	.000168	.000168	0	0
93	FACE1	PX	8.4e-5	8.4e-5	0	0
94	CR6	PX	.00023	.00023	0	0
95	CR5	PX	.00023	.00023	0	0
96	CR4	PX	.00023	.00023	0	0
97	CR3	PX	.00023	.00023	0	0
98	CR2	PX	.00023	.00023	0	0
99	CR1	PX	.00023	.00023	0	0
100	CPL3	PX	2.5e-5	2.5e-5	0	0
101	CPL2	PX	2.5e-5	2.5e-5	0	0
102	CPL1	PX	2.5e-5	2.5e-5	0	0
103	ANGLE6	PX	.000136	.000136	0	0
104	ANGLE5	PX	.000136	.000136	0	0
105	ANGLE4	PX	.000136	.000136	0	0
106	ANGLE3	PX	.000136	.000136	0	0
107	ANGLE2	PX	.000136	.000136	0	0
108	ANGLE1	PX	.000136	.000136	0	0

**Member Distributed Loads (BLC 27 : Ice Dead Load)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	Z	-.008	-.008	0	0
2	SO2	Z	-.008	-.008	0	0
3	SO1	Z	-.008	-.008	0	0
4	RPL3	Z	-.009	-.009	0	0
5	RPL2	Z	-.009	-.009	0	0
6	RPL1	Z	-.009	-.009	0	0
7	RAIL3	Z	-.005	-.005	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 27 : Ice Dead Load) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
8	RAIL2	Z	-0.005	-0.005	0	0
9	RAIL1	Z	-0.005	-0.005	0	0
10	PL18	Z	-0.004	-0.004	0	0
11	PL17	Z	-0.004	-0.004	0	0
12	PL16	Z	-0.004	-0.004	0	0
13	PL15	Z	-0.004	-0.004	0	0
14	PL14	Z	-0.004	-0.004	0	0
15	PL13	Z	-0.004	-0.004	0	0
16	PL12	Z	-0.004	-0.004	0	0
17	PL11	Z	-0.004	-0.004	0	0
18	PL10	Z	-0.004	-0.004	0	0
19	PL9	Z	-0.004	-0.004	0	0
20	PL8	Z	-0.004	-0.004	0	0
21	PL7	Z	-0.004	-0.004	0	0
22	PL6	Z	-0.004	-0.004	0	0
23	PL5	Z	-0.004	-0.004	0	0
24	PL4	Z	-0.004	-0.004	0	0
25	PL3	Z	-0.004	-0.004	0	0
26	PL2	Z	-0.004	-0.004	0	0
27	PL1	Z	-0.004	-0.004	0	0
28	MP GAMMA3	Z	-0.005	-0.005	0	0
29	MP GAMMA2	Z	-0.005	-0.005	0	0
30	MP GAMMA1	Z	-0.005	-0.005	0	0
31	MP BETA3	Z	-0.005	-0.005	0	0
32	MP BETA2	Z	-0.005	-0.005	0	0
33	MP BETA1	Z	-0.005	-0.005	0	0
34	MP ALPHA3	Z	-0.005	-0.005	0	0
35	MP ALPHA2	Z	-0.005	-0.005	0	0
36	MP ALPHA1	Z	-0.005	-0.005	0	0
37	FACE3	Z	-0.006	-0.006	0	0
38	FACE2	Z	-0.006	-0.006	0	0
39	FACE1	Z	-0.006	-0.006	0	0
40	CR6	Z	-0.008	-0.008	0	0
41	CR5	Z	-0.008	-0.008	0	0
42	CR4	Z	-0.008	-0.008	0	0
43	CR3	Z	-0.008	-0.008	0	0
44	CR2	Z	-0.008	-0.008	0	0
45	CR1	Z	-0.008	-0.008	0	0
46	CPL3	Z	-0.007	-0.007	0	0
47	CPL2	Z	-0.007	-0.007	0	0
48	CPL1	Z	-0.007	-0.007	0	0
49	ANGLE6	Z	-0.005	-0.005	0	0
50	ANGLE5	Z	-0.005	-0.005	0	0
51	ANGLE4	Z	-0.005	-0.005	0	0
52	ANGLE3	Z	-0.005	-0.005	0	0
53	ANGLE2	Z	-0.005	-0.005	0	0
54	ANGLE1	Z	-0.005	-0.005	0	0

**Member Distributed Loads (BLC 28 : Ice Wind Load (0))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-0.000925	-0.000925	0	0
2	SO2	PY	-0.000925	-0.000925	0	0
3	SO1	PY	-0.000925	-0.000925	0	0
4	RPL3	PY	-0.002	-0.002	0	0
5	RPL2	PY	-0.002	-0.002	0	0
6	RPL1	PY	-0.002	-0.002	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 28 : Ice Wind Load (0)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
7	RAIL3	PY	-.001	-.001	0	0
8	RAIL2	PY	-.001	-.001	0	0
9	RAIL1	PY	-.000725	-.000725	0	0
10	PL18	PY	-.000632	-.000632	0	0
11	PL17	PY	-.000632	-.000632	0	0
12	PL16	PY	-.000632	-.000632	0	0
13	PL15	PY	-.000632	-.000632	0	0
14	PL14	PY	-.000632	-.000632	0	0
15	PL13	PY	-.000632	-.000632	0	0
16	PL12	PY	-.000632	-.000632	0	0
17	PL11	PY	-.000632	-.000632	0	0
18	PL10	PY	-.000632	-.000632	0	0
19	PL9	PY	-.000632	-.000632	0	0
20	PL8	PY	-.000632	-.000632	0	0
21	PL7	PY	-.000632	-.000632	0	0
22	PL6	PY	-.000632	-.000632	0	0
23	PL5	PY	-.000632	-.000632	0	0
24	PL4	PY	-.000632	-.000632	0	0
25	PL3	PY	-.000632	-.000632	0	0
26	PL2	PY	-.000632	-.000632	0	0
27	PL1	PY	-.000632	-.000632	0	0
28	MP GAMMA3	PY	-.002	-.002	0	0
29	MP GAMMA2	PY	-.002	-.002	0	0
30	MP GAMMA1	PY	-.002	-.002	0	0
31	MP BETA3	PY	-.002	-.002	0	0
32	MP BETA2	PY	-.002	-.002	0	0
33	MP BETA1	PY	-.002	-.002	0	0
34	MP ALPHA3	PY	-.002	-.002	0	0
35	MP ALPHA2	PY	-.002	-.002	0	0
36	MP ALPHA1	PY	-.002	-.002	0	0
37	FACE3	PY	-.002	-.002	0	0
38	FACE2	PY	-.002	-.002	0	0
39	FACE1	PY	-.000815	-.000815	0	0
40	CR6	PY	-.001	-.001	0	0
41	CR5	PY	-.001	-.001	0	0
42	CR4	PY	-.001	-.001	0	0
43	CR3	PY	-.001	-.001	0	0
44	CR2	PY	-.001	-.001	0	0
45	CR1	PY	-.001	-.001	0	0
46	CPL3	PY	-.000601	-.000601	0	0
47	CPL2	PY	-.000601	-.000601	0	0
48	CPL1	PY	-.000601	-.000601	0	0
49	ANGLE6	PY	-.000995	-.000995	0	0
50	ANGLE5	PY	-.000995	-.000995	0	0
51	ANGLE4	PY	-.000995	-.000995	0	0
52	ANGLE3	PY	-.000995	-.000995	0	0
53	ANGLE2	PY	-.000995	-.000995	0	0
54	ANGLE1	PY	-.000995	-.000995	0	0

**Member Distributed Loads (BLC 29 : Ice Wind Load (30))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-.000801	-.000801	0	0
2	SO2	PY	-.000801	-.000801	0	0
3	SO1	PY	-.000801	-.000801	0	0
4	RPL3	PY	-.001	-.001	0	0
5	RPL2	PY	-.001	-.001	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 29 : Ice Wind Load (30)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
6	RPL1	PY	-0.001	-0.001	0	0
7	RAIL3	PY	-0.001	-0.001	0	0
8	RAIL2	PY	-0.001	-0.001	0	0
9	RAIL1	PY	-0.000627	-0.000627	0	0
10	PL18	PY	-0.000547	-0.000547	0	0
11	PL17	PY	-0.000547	-0.000547	0	0
12	PL16	PY	-0.000547	-0.000547	0	0
13	PL15	PY	-0.000547	-0.000547	0	0
14	PL14	PY	-0.000547	-0.000547	0	0
15	PL13	PY	-0.000547	-0.000547	0	0
16	PL12	PY	-0.000547	-0.000547	0	0
17	PL11	PY	-0.000547	-0.000547	0	0
18	PL10	PY	-0.000547	-0.000547	0	0
19	PL9	PY	-0.000547	-0.000547	0	0
20	PL8	PY	-0.000547	-0.000547	0	0
21	PL7	PY	-0.000547	-0.000547	0	0
22	PL6	PY	-0.000547	-0.000547	0	0
23	PL5	PY	-0.000547	-0.000547	0	0
24	PL4	PY	-0.000547	-0.000547	0	0
25	PL3	PY	-0.000547	-0.000547	0	0
26	PL2	PY	-0.000547	-0.000547	0	0
27	PL1	PY	-0.000547	-0.000547	0	0
28	MP GAMMA3	PY	-0.002	-0.002	0	0
29	MP GAMMA2	PY	-0.002	-0.002	0	0
30	MP GAMMA1	PY	-0.002	-0.002	0	0
31	MP BETA3	PY	-0.002	-0.002	0	0
32	MP BETA2	PY	-0.002	-0.002	0	0
33	MP BETA1	PY	-0.002	-0.002	0	0
34	MP ALPHA3	PY	-0.002	-0.002	0	0
35	MP ALPHA2	PY	-0.002	-0.002	0	0
36	MP ALPHA1	PY	-0.002	-0.002	0	0
37	FACE3	PY	-0.001	-0.001	0	0
38	FACE2	PY	-0.001	-0.001	0	0
39	FACE1	PY	-0.000706	-0.000706	0	0
40	CR6	PY	-0.001	-0.001	0	0
41	CR5	PY	-0.001	-0.001	0	0
42	CR4	PY	-0.001	-0.001	0	0
43	CR3	PY	-0.001	-0.001	0	0
44	CR2	PY	-0.001	-0.001	0	0
45	CR1	PY	-0.001	-0.001	0	0
46	CPL3	PY	-0.000521	-0.000521	0	0
47	CPL2	PY	-0.000521	-0.000521	0	0
48	CPL1	PY	-0.000521	-0.000521	0	0
49	ANGLE6	PY	-0.000862	-0.000862	0	0
50	ANGLE5	PY	-0.000862	-0.000862	0	0
51	ANGLE4	PY	-0.000862	-0.000862	0	0
52	ANGLE3	PY	-0.000862	-0.000862	0	0
53	ANGLE2	PY	-0.000862	-0.000862	0	0
54	ANGLE1	PY	-0.000862	-0.000862	0	0
55	SO3	PX	-0.000463	-0.000463	0	0
56	SO2	PX	-0.000463	-0.000463	0	0
57	SO1	PX	-0.000463	-0.000463	0	0
58	RPL3	PX	-0.000801	-0.000801	0	0
59	RPL2	PX	-0.000801	-0.000801	0	0
60	RPL1	PX	-0.000801	-0.000801	0	0
61	RAIL3	PX	-0.000725	-0.000725	0	0
62	RAIL2	PX	-0.000725	-0.000725	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 29 : Ice Wind Load (30)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
63	RAIL1	PX	-0.000362	-0.000362	0	0
64	PL18	PX	-0.000316	-0.000316	0	0
65	PL17	PX	-0.000316	-0.000316	0	0
66	PL16	PX	-0.000316	-0.000316	0	0
67	PL15	PX	-0.000316	-0.000316	0	0
68	PL14	PX	-0.000316	-0.000316	0	0
69	PL13	PX	-0.000316	-0.000316	0	0
70	PL12	PX	-0.000316	-0.000316	0	0
71	PL11	PX	-0.000316	-0.000316	0	0
72	PL10	PX	-0.000316	-0.000316	0	0
73	PL9	PX	-0.000316	-0.000316	0	0
74	PL8	PX	-0.000316	-0.000316	0	0
75	PL7	PX	-0.000316	-0.000316	0	0
76	PL6	PX	-0.000316	-0.000316	0	0
77	PL5	PX	-0.000316	-0.000316	0	0
78	PL4	PX	-0.000316	-0.000316	0	0
79	PL3	PX	-0.000316	-0.000316	0	0
80	PL2	PX	-0.000316	-0.000316	0	0
81	PL1	PX	-0.000316	-0.000316	0	0
82	MP GAMMA3	PX	-.001	-.001	0	0
83	MP GAMMA2	PX	-.001	-.001	0	0
84	MP GAMMA1	PX	-.001	-.001	0	0
85	MP BETA3	PX	-.001	-.001	0	0
86	MP BETA2	PX	-.001	-.001	0	0
87	MP BETA1	PX	-.001	-.001	0	0
88	MP ALPHA3	PX	-.001	-.001	0	0
89	MP ALPHA2	PX	-.001	-.001	0	0
90	MP ALPHA1	PX	-.001	-.001	0	0
91	FACE3	PX	-0.000815	-0.000815	0	0
92	FACE2	PX	-0.000815	-0.000815	0	0
93	FACE1	PX	-0.000408	-0.000408	0	0
94	CR6	PX	-0.000665	-0.000665	0	0
95	CR5	PX	-0.000665	-0.000665	0	0
96	CR4	PX	-0.000665	-0.000665	0	0
97	CR3	PX	-0.000665	-0.000665	0	0
98	CR2	PX	-0.000665	-0.000665	0	0
99	CR1	PX	-0.000665	-0.000665	0	0
100	CPL3	PX	-0.000301	-0.000301	0	0
101	CPL2	PX	-0.000301	-0.000301	0	0
102	CPL1	PX	-0.000301	-0.000301	0	0
103	ANGLE6	PX	-0.000498	-0.000498	0	0
104	ANGLE5	PX	-0.000498	-0.000498	0	0
105	ANGLE4	PX	-0.000498	-0.000498	0	0
106	ANGLE3	PX	-0.000498	-0.000498	0	0
107	ANGLE2	PX	-0.000498	-0.000498	0	0
108	ANGLE1	PX	-0.000498	-0.000498	0	0

**Member Distributed Loads (BLC 30 : Ice Wind Load (60))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-0.000463	-0.000463	0	0
2	SO2	PY	-0.000463	-0.000463	0	0
3	SO1	PY	-0.000463	-0.000463	0	0
4	RPL3	PY	-0.000801	-0.000801	0	0
5	RPL2	PY	-0.000801	-0.000801	0	0
6	RPL1	PY	-0.000801	-0.000801	0	0
7	RAIL3	PY	-0.000725	-0.000725	0	0





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 30 : Ice Wind Load (60)) (Continued)**

	Member Label	Direction	Start Magnitude[k/ft...	End Magnitude[k/ft...	Start Location[ft,%]	End Location[ft,%]
8	RAIL2	PY	-0.000725	-0.000725	0	0
9	RAIL1	PY	-0.000362	-0.000362	0	0
10	PL18	PY	-0.000316	-0.000316	0	0
11	PL17	PY	-0.000316	-0.000316	0	0
12	PL16	PY	-0.000316	-0.000316	0	0
13	PL15	PY	-0.000316	-0.000316	0	0
14	PL14	PY	-0.000316	-0.000316	0	0
15	PL13	PY	-0.000316	-0.000316	0	0
16	PL12	PY	-0.000316	-0.000316	0	0
17	PL11	PY	-0.000316	-0.000316	0	0
18	PL10	PY	-0.000316	-0.000316	0	0
19	PL9	PY	-0.000316	-0.000316	0	0
20	PL8	PY	-0.000316	-0.000316	0	0
21	PL7	PY	-0.000316	-0.000316	0	0
22	PL6	PY	-0.000316	-0.000316	0	0
23	PL5	PY	-0.000316	-0.000316	0	0
24	PL4	PY	-0.000316	-0.000316	0	0
25	PL3	PY	-0.000316	-0.000316	0	0
26	PL2	PY	-0.000316	-0.000316	0	0
27	PL1	PY	-0.000316	-0.000316	0	0
28	MP GAMMA3	PY	-0.001	-0.001	0	0
29	MP GAMMA2	PY	-0.001	-0.001	0	0
30	MP GAMMA1	PY	-0.001	-0.001	0	0
31	MP BETA3	PY	-0.001	-0.001	0	0
32	MP BETA2	PY	-0.001	-0.001	0	0
33	MP BETA1	PY	-0.001	-0.001	0	0
34	MP ALPHA3	PY	-0.001	-0.001	0	0
35	MP ALPHA2	PY	-0.001	-0.001	0	0
36	MP ALPHA1	PY	-0.001	-0.001	0	0
37	FACE3	PY	-0.000815	-0.000815	0	0
38	FACE2	PY	-0.000815	-0.000815	0	0
39	FACE1	PY	-0.000408	-0.000408	0	0
40	CR6	PY	-0.000665	-0.000665	0	0
41	CR5	PY	-0.000665	-0.000665	0	0
42	CR4	PY	-0.000665	-0.000665	0	0
43	CR3	PY	-0.000665	-0.000665	0	0
44	CR2	PY	-0.000665	-0.000665	0	0
45	CR1	PY	-0.000665	-0.000665	0	0
46	CPL3	PY	-0.000301	-0.000301	0	0
47	CPL2	PY	-0.000301	-0.000301	0	0
48	CPL1	PY	-0.000301	-0.000301	0	0
49	ANGLE6	PY	-0.000498	-0.000498	0	0
50	ANGLE5	PY	-0.000498	-0.000498	0	0
51	ANGLE4	PY	-0.000498	-0.000498	0	0
52	ANGLE3	PY	-0.000498	-0.000498	0	0
53	ANGLE2	PY	-0.000498	-0.000498	0	0
54	ANGLE1	PY	-0.000498	-0.000498	0	0
55	SO3	PX	-0.000801	-0.000801	0	0
56	SO2	PX	-0.000801	-0.000801	0	0
57	SO1	PX	-0.000801	-0.000801	0	0
58	RPL3	PX	-0.001	-0.001	0	0
59	RPL2	PX	-0.001	-0.001	0	0
60	RPL1	PX	-0.001	-0.001	0	0
61	RAIL3	PX	-0.001	-0.001	0	0
62	RAIL2	PX	-0.001	-0.001	0	0
63	RAIL1	PX	-0.000627	-0.000627	0	0
64	PL18	PX	-0.000547	-0.000547	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 30 : Ice Wind Load (60)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
65	PL17	PX	-0.000547	-0.000547	0	0
66	PL16	PX	-0.000547	-0.000547	0	0
67	PL15	PX	-0.000547	-0.000547	0	0
68	PL14	PX	-0.000547	-0.000547	0	0
69	PL13	PX	-0.000547	-0.000547	0	0
70	PL12	PX	-0.000547	-0.000547	0	0
71	PL11	PX	-0.000547	-0.000547	0	0
72	PL10	PX	-0.000547	-0.000547	0	0
73	PL9	PX	-0.000547	-0.000547	0	0
74	PL8	PX	-0.000547	-0.000547	0	0
75	PL7	PX	-0.000547	-0.000547	0	0
76	PL6	PX	-0.000547	-0.000547	0	0
77	PL5	PX	-0.000547	-0.000547	0	0
78	PL4	PX	-0.000547	-0.000547	0	0
79	PL3	PX	-0.000547	-0.000547	0	0
80	PL2	PX	-0.000547	-0.000547	0	0
81	PL1	PX	-0.000547	-0.000547	0	0
82	MP GAMMA3	PX	-0.002	-0.002	0	0
83	MP GAMMA2	PX	-0.002	-0.002	0	0
84	MP GAMMA1	PX	-0.002	-0.002	0	0
85	MP BETA3	PX	-0.002	-0.002	0	0
86	MP BETA2	PX	-0.002	-0.002	0	0
87	MP BETA1	PX	-0.002	-0.002	0	0
88	MP ALPHA3	PX	-0.002	-0.002	0	0
89	MP ALPHA2	PX	-0.002	-0.002	0	0
90	MP ALPHA1	PX	-0.002	-0.002	0	0
91	FACE3	PX	-0.001	-0.001	0	0
92	FACE2	PX	-0.001	-0.001	0	0
93	FACE1	PX	-0.000706	-0.000706	0	0
94	CR6	PX	-0.001	-0.001	0	0
95	CR5	PX	-0.001	-0.001	0	0
96	CR4	PX	-0.001	-0.001	0	0
97	CR3	PX	-0.001	-0.001	0	0
98	CR2	PX	-0.001	-0.001	0	0
99	CR1	PX	-0.001	-0.001	0	0
100	CPL3	PX	-0.000521	-0.000521	0	0
101	CPL2	PX	-0.000521	-0.000521	0	0
102	CPL1	PX	-0.000521	-0.000521	0	0
103	ANGLE6	PX	-0.000862	-0.000862	0	0
104	ANGLE5	PX	-0.000862	-0.000862	0	0
105	ANGLE4	PX	-0.000862	-0.000862	0	0
106	ANGLE3	PX	-0.000862	-0.000862	0	0
107	ANGLE2	PX	-0.000862	-0.000862	0	0
108	ANGLE1	PX	-0.000862	-0.000862	0	0

**Member Distributed Loads (BLC 31 : Ice Wind Load (90))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PX	-0.000925	-0.000925	0	0
2	SO2	PX	-0.000925	-0.000925	0	0
3	SO1	PX	-0.000925	-0.000925	0	0
4	RPL3	PX	-0.002	-0.002	0	0
5	RPL2	PX	-0.002	-0.002	0	0
6	RPL1	PX	-0.002	-0.002	0	0
7	RAIL3	PX	-0.001	-0.001	0	0
8	RAIL2	PX	-0.001	-0.001	0	0
9	RAIL1	PX	-0.000725	-0.000725	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 31 : Ice Wind Load (90)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft.%]	End Location[ft.%]
10	PL18	PX	-.000632	-.000632	0	0
11	PL17	PX	-.000632	-.000632	0	0
12	PL16	PX	-.000632	-.000632	0	0
13	PL15	PX	-.000632	-.000632	0	0
14	PL14	PX	-.000632	-.000632	0	0
15	PL13	PX	-.000632	-.000632	0	0
16	PL12	PX	-.000632	-.000632	0	0
17	PL11	PX	-.000632	-.000632	0	0
18	PL10	PX	-.000632	-.000632	0	0
19	PL9	PX	-.000632	-.000632	0	0
20	PL8	PX	-.000632	-.000632	0	0
21	PL7	PX	-.000632	-.000632	0	0
22	PL6	PX	-.000632	-.000632	0	0
23	PL5	PX	-.000632	-.000632	0	0
24	PL4	PX	-.000632	-.000632	0	0
25	PL3	PX	-.000632	-.000632	0	0
26	PL2	PX	-.000632	-.000632	0	0
27	PL1	PX	-.000632	-.000632	0	0
28	MP GAMMA3	PX	-.002	-.002	0	0
29	MP GAMMA2	PX	-.002	-.002	0	0
30	MP GAMMA1	PX	-.002	-.002	0	0
31	MP BETA3	PX	-.002	-.002	0	0
32	MP BETA2	PX	-.002	-.002	0	0
33	MP BETA1	PX	-.002	-.002	0	0
34	MP ALPHA3	PX	-.002	-.002	0	0
35	MP ALPHA2	PX	-.002	-.002	0	0
36	MP ALPHA1	PX	-.002	-.002	0	0
37	FACE3	PX	-.002	-.002	0	0
38	FACE1	PX	-.002	-.002	0	0
39	FACE2	PX	-.000815	-.000815	0	0
40	CR6	PX	-.001	-.001	0	0
41	CR5	PX	-.001	-.001	0	0
42	CR4	PX	-.001	-.001	0	0
43	CR3	PX	-.001	-.001	0	0
44	CR2	PX	-.001	-.001	0	0
45	CR1	PX	-.001	-.001	0	0
46	CPL3	PX	-.000601	-.000601	0	0
47	CPL2	PX	-.000601	-.000601	0	0
48	CPL1	PX	-.000601	-.000601	0	0
49	ANGLE6	PX	-.000995	-.000995	0	0
50	ANGLE5	PX	-.000995	-.000995	0	0
51	ANGLE4	PX	-.000995	-.000995	0	0
52	ANGLE3	PX	-.000995	-.000995	0	0
53	ANGLE2	PX	-.000995	-.000995	0	0
54	ANGLE1	PX	-.000995	-.000995	0	0

**Member Distributed Loads (BLC 32 : Ice Wind Load (120))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft.%]	End Location[ft.%]
1	SO3	PY	.000463	.000463	0	0
2	SO2	PY	.000463	.000463	0	0
3	SO1	PY	.000463	.000463	0	0
4	RPL3	PY	.000801	.000801	0	0
5	RPL2	PY	.000801	.000801	0	0
6	RPL1	PY	.000801	.000801	0	0
7	RAIL3	PY	.000725	.000725	0	0
8	RAIL2	PY	.000725	.000725	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 32 : Ice Wind Load (120)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
9	RAIL1	PY	.000362	.000362	0	0
10	PL18	PY	.000316	.000316	0	0
11	PL17	PY	.000316	.000316	0	0
12	PL16	PY	.000316	.000316	0	0
13	PL15	PY	.000316	.000316	0	0
14	PL14	PY	.000316	.000316	0	0
15	PL13	PY	.000316	.000316	0	0
16	PL12	PY	.000316	.000316	0	0
17	PL11	PY	.000316	.000316	0	0
18	PL10	PY	.000316	.000316	0	0
19	PL9	PY	.000316	.000316	0	0
20	PL8	PY	.000316	.000316	0	0
21	PL7	PY	.000316	.000316	0	0
22	PL6	PY	.000316	.000316	0	0
23	PL5	PY	.000316	.000316	0	0
24	PL4	PY	.000316	.000316	0	0
25	PL3	PY	.000316	.000316	0	0
26	PL2	PY	.000316	.000316	0	0
27	PL1	PY	.000316	.000316	0	0
28	MP GAMMA3	PY	.001	.001	0	0
29	MP GAMMA2	PY	.001	.001	0	0
30	MP GAMMA1	PY	.001	.001	0	0
31	MP BETA3	PY	.001	.001	0	0
32	MP BETA2	PY	.001	.001	0	0
33	MP BETA1	PY	.001	.001	0	0
34	MP ALPHA3	PY	.001	.001	0	0
35	MP ALPHA2	PY	.001	.001	0	0
36	MP ALPHA1	PY	.001	.001	0	0
37	FACE3	PY	.000815	.000815	0	0
38	FACE1	PY	.000815	.000815	0	0
39	FACE2	PY	.000408	.000408	0	0
40	CR6	PY	.000665	.000665	0	0
41	CR5	PY	.000665	.000665	0	0
42	CR4	PY	.000665	.000665	0	0
43	CR3	PY	.000665	.000665	0	0
44	CR2	PY	.000665	.000665	0	0
45	CR1	PY	.000665	.000665	0	0
46	CPL3	PY	.000301	.000301	0	0
47	CPL2	PY	.000301	.000301	0	0
48	CPL1	PY	.000301	.000301	0	0
49	ANGLE6	PY	.000498	.000498	0	0
50	ANGLE5	PY	.000498	.000498	0	0
51	ANGLE4	PY	.000498	.000498	0	0
52	ANGLE3	PY	.000498	.000498	0	0
53	ANGLE2	PY	.000498	.000498	0	0
54	ANGLE1	PY	.000498	.000498	0	0
55	SO3	PX	-.000801	-.000801	0	0
56	SO2	PX	-.000801	-.000801	0	0
57	SO1	PX	-.000801	-.000801	0	0
58	RPL3	PX	-.001	-.001	0	0
59	RPL2	PX	-.001	-.001	0	0
60	RPL1	PX	-.001	-.001	0	0
61	RAIL3	PX	-.001	-.001	0	0
62	RAIL2	PX	-.001	-.001	0	0
63	RAIL1	PX	-.000627	-.000627	0	0
64	PL18	PX	-.000547	-.000547	0	0
65	PL17	PX	-.000547	-.000547	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 32 : Ice Wind Load (120)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
66	PL16	PX	-.000547	-.000547	0	0
67	PL15	PX	-.000547	-.000547	0	0
68	PL14	PX	-.000547	-.000547	0	0
69	PL13	PX	-.000547	-.000547	0	0
70	PL12	PX	-.000547	-.000547	0	0
71	PL11	PX	-.000547	-.000547	0	0
72	PL10	PX	-.000547	-.000547	0	0
73	PL9	PX	-.000547	-.000547	0	0
74	PL8	PX	-.000547	-.000547	0	0
75	PL7	PX	-.000547	-.000547	0	0
76	PL6	PX	-.000547	-.000547	0	0
77	PL5	PX	-.000547	-.000547	0	0
78	PL4	PX	-.000547	-.000547	0	0
79	PL3	PX	-.000547	-.000547	0	0
80	PL2	PX	-.000547	-.000547	0	0
81	PL1	PX	-.000547	-.000547	0	0
82	MP GAMMA3	PX	-.002	-.002	0	0
83	MP GAMMA2	PX	-.002	-.002	0	0
84	MP GAMMA1	PX	-.002	-.002	0	0
85	MP BETA3	PX	-.002	-.002	0	0
86	MP BETA2	PX	-.002	-.002	0	0
87	MP BETA1	PX	-.002	-.002	0	0
88	MP ALPHA3	PX	-.002	-.002	0	0
89	MP ALPHA2	PX	-.002	-.002	0	0
90	MP ALPHA1	PX	-.002	-.002	0	0
91	FACE3	PX	-.001	-.001	0	0
92	FACE1	PX	-.001	-.001	0	0
93	FACE2	PX	-.000706	-.000706	0	0
94	CR6	PX	-.001	-.001	0	0
95	CR5	PX	-.001	-.001	0	0
96	CR4	PX	-.001	-.001	0	0
97	CR3	PX	-.001	-.001	0	0
98	CR2	PX	-.001	-.001	0	0
99	CR1	PX	-.001	-.001	0	0
100	CPL3	PX	-.000521	-.000521	0	0
101	CPL2	PX	-.000521	-.000521	0	0
102	CPL1	PX	-.000521	-.000521	0	0
103	ANGLE6	PX	-.000862	-.000862	0	0
104	ANGLE5	PX	-.000862	-.000862	0	0
105	ANGLE4	PX	-.000862	-.000862	0	0
106	ANGLE3	PX	-.000862	-.000862	0	0
107	ANGLE2	PX	-.000862	-.000862	0	0
108	ANGLE1	PX	-.000862	-.000862	0	0

**Member Distributed Loads (BLC 33 : Ice Wind Load (150))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.000801	.000801	0	0
2	SO2	PY	.000801	.000801	0	0
3	SO1	PY	.000801	.000801	0	0
4	RPL3	PY	.001	.001	0	0
5	RPL2	PY	.001	.001	0	0
6	RPL1	PY	.001	.001	0	0
7	RAIL3	PY	.001	.001	0	0
8	RAIL2	PY	.001	.001	0	0
9	RAIL1	PY	.000627	.000627	0	0
10	PL18	PY	.000547	.000547	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 33 : Ice Wind Load (150)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
11	PL17	PY	.000547	.000547	0 0
12	PL16	PY	.000547	.000547	0 0
13	PL15	PY	.000547	.000547	0 0
14	PL14	PY	.000547	.000547	0 0
15	PL13	PY	.000547	.000547	0 0
16	PL12	PY	.000547	.000547	0 0
17	PL11	PY	.000547	.000547	0 0
18	PL10	PY	.000547	.000547	0 0
19	PL9	PY	.000547	.000547	0 0
20	PL8	PY	.000547	.000547	0 0
21	PL7	PY	.000547	.000547	0 0
22	PL6	PY	.000547	.000547	0 0
23	PL5	PY	.000547	.000547	0 0
24	PL4	PY	.000547	.000547	0 0
25	PL3	PY	.000547	.000547	0 0
26	PL2	PY	.000547	.000547	0 0
27	PL1	PY	.000547	.000547	0 0
28	MP GAMMA3	PY	.002	.002	0 0
29	MP GAMMA2	PY	.002	.002	0 0
30	MP GAMMA1	PY	.002	.002	0 0
31	MP BETA3	PY	.002	.002	0 0
32	MP BETA2	PY	.002	.002	0 0
33	MP BETA1	PY	.002	.002	0 0
34	MP ALPHA3	PY	.002	.002	0 0
35	MP ALPHA2	PY	.002	.002	0 0
36	MP ALPHA1	PY	.002	.002	0 0
37	FACE3	PY	.001	.001	0 0
38	FACE1	PY	.001	.001	0 0
39	FACE2	PY	.000706	.000706	0 0
40	CR6	PY	.001	.001	0 0
41	CR5	PY	.001	.001	0 0
42	CR4	PY	.001	.001	0 0
43	CR3	PY	.001	.001	0 0
44	CR2	PY	.001	.001	0 0
45	CR1	PY	.001	.001	0 0
46	CPL3	PY	.000521	.000521	0 0
47	CPL2	PY	.000521	.000521	0 0
48	CPL1	PY	.000521	.000521	0 0
49	ANGLE6	PY	.000862	.000862	0 0
50	ANGLE5	PY	.000862	.000862	0 0
51	ANGLE4	PY	.000862	.000862	0 0
52	ANGLE3	PY	.000862	.000862	0 0
53	ANGLE2	PY	.000862	.000862	0 0
54	ANGLE1	PY	.000862	.000862	0 0
55	SO3	PX	-.000463	-.000463	0 0
56	SO2	PX	-.000463	-.000463	0 0
57	SO1	PX	-.000463	-.000463	0 0
58	RPL3	PX	-.000801	-.000801	0 0
59	RPL2	PX	-.000801	-.000801	0 0
60	RPL1	PX	-.000801	-.000801	0 0
61	RAIL3	PX	-.000725	-.000725	0 0
62	RAIL2	PX	-.000725	-.000725	0 0
63	RAIL1	PX	-.000362	-.000362	0 0
64	PL18	PX	-.000316	-.000316	0 0
65	PL17	PX	-.000316	-.000316	0 0
66	PL16	PX	-.000316	-.000316	0 0
67	PL15	PX	-.000316	-.000316	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 33 : Ice Wind Load (150)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
68	PL14	PX	-0.000316	-0.000316	0	0
69	PL13	PX	-0.000316	-0.000316	0	0
70	PL12	PX	-0.000316	-0.000316	0	0
71	PL11	PX	-0.000316	-0.000316	0	0
72	PL10	PX	-0.000316	-0.000316	0	0
73	PL9	PX	-0.000316	-0.000316	0	0
74	PL8	PX	-0.000316	-0.000316	0	0
75	PL7	PX	-0.000316	-0.000316	0	0
76	PL6	PX	-0.000316	-0.000316	0	0
77	PL5	PX	-0.000316	-0.000316	0	0
78	PL4	PX	-0.000316	-0.000316	0	0
79	PL3	PX	-0.000316	-0.000316	0	0
80	PL2	PX	-0.000316	-0.000316	0	0
81	PL1	PX	-0.000316	-0.000316	0	0
82	MP GAMMA3	PX	-0.001	-0.001	0	0
83	MP GAMMA2	PX	-0.001	-0.001	0	0
84	MP GAMMA1	PX	-0.001	-0.001	0	0
85	MP BETA3	PX	-0.001	-0.001	0	0
86	MP BETA2	PX	-0.001	-0.001	0	0
87	MP BETA1	PX	-0.001	-0.001	0	0
88	MP ALPHA3	PX	-0.001	-0.001	0	0
89	MP ALPHA2	PX	-0.001	-0.001	0	0
90	MP ALPHA1	PX	-0.001	-0.001	0	0
91	FACE3	PX	-0.000815	-0.000815	0	0
92	FACE1	PX	-0.000815	-0.000815	0	0
93	FACE2	PX	-0.000408	-0.000408	0	0
94	CR6	PX	-0.000665	-0.000665	0	0
95	CR5	PX	-0.000665	-0.000665	0	0
96	CR4	PX	-0.000665	-0.000665	0	0
97	CR3	PX	-0.000665	-0.000665	0	0
98	CR2	PX	-0.000665	-0.000665	0	0
99	CR1	PX	-0.000665	-0.000665	0	0
100	CPL3	PX	-0.000301	-0.000301	0	0
101	CPL2	PX	-0.000301	-0.000301	0	0
102	CPL1	PX	-0.000301	-0.000301	0	0
103	ANGLE6	PX	-0.000498	-0.000498	0	0
104	ANGLE5	PX	-0.000498	-0.000498	0	0
105	ANGLE4	PX	-0.000498	-0.000498	0	0
106	ANGLE3	PX	-0.000498	-0.000498	0	0
107	ANGLE2	PX	-0.000498	-0.000498	0	0
108	ANGLE1	PX	-0.000498	-0.000498	0	0

**Member Distributed Loads (BLC 34 : Ice Wind Load (180))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.000925	.000925	0	0
2	SO2	PY	.000925	.000925	0	0
3	SO1	PY	.000925	.000925	0	0
4	RPL3	PY	.002	.002	0	0
5	RPL2	PY	.002	.002	0	0
6	RPL1	PY	.002	.002	0	0
7	RAIL3	PY	.001	.001	0	0
8	RAIL2	PY	.001	.001	0	0
9	RAIL1	PY	.000725	.000725	0	0
10	PL18	PY	.000632	.000632	0	0
11	PL17	PY	.000632	.000632	0	0
12	PL16	PY	.000632	.000632	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 34 : Ice Wind Load (180)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
13	PL15	PY	.000632	.000632	0	0
14	PL14	PY	.000632	.000632	0	0
15	PL13	PY	.000632	.000632	0	0
16	PL12	PY	.000632	.000632	0	0
17	PL11	PY	.000632	.000632	0	0
18	PL10	PY	.000632	.000632	0	0
19	PL9	PY	.000632	.000632	0	0
20	PL8	PY	.000632	.000632	0	0
21	PL7	PY	.000632	.000632	0	0
22	PL6	PY	.000632	.000632	0	0
23	PL5	PY	.000632	.000632	0	0
24	PL4	PY	.000632	.000632	0	0
25	PL3	PY	.000632	.000632	0	0
26	PL2	PY	.000632	.000632	0	0
27	PL1	PY	.000632	.000632	0	0
28	MP GAMMA3	PY	.002	.002	0	0
29	MP GAMMA2	PY	.002	.002	0	0
30	MP GAMMA1	PY	.002	.002	0	0
31	MP BETA3	PY	.002	.002	0	0
32	MP BETA2	PY	.002	.002	0	0
33	MP BETA1	PY	.002	.002	0	0
34	MP ALPHA3	PY	.002	.002	0	0
35	MP ALPHA2	PY	.002	.002	0	0
36	MP ALPHA1	PY	.002	.002	0	0
37	FACE3	PY	.002	.002	0	0
38	FACE1	PY	.002	.002	0	0
39	FACE2	PY	.000815	.000815	0	0
40	CR6	PY	.001	.001	0	0
41	CR5	PY	.001	.001	0	0
42	CR4	PY	.001	.001	0	0
43	CR3	PY	.001	.001	0	0
44	CR2	PY	.001	.001	0	0
45	CR1	PY	.001	.001	0	0
46	CPL3	PY	.000601	.000601	0	0
47	CPL2	PY	.000601	.000601	0	0
48	CPL1	PY	.000601	.000601	0	0
49	ANGLE6	PY	.000995	.000995	0	0
50	ANGLE5	PY	.000995	.000995	0	0
51	ANGLE4	PY	.000995	.000995	0	0
52	ANGLE3	PY	.000995	.000995	0	0
53	ANGLE2	PY	.000995	.000995	0	0
54	ANGLE1	PY	.000995	.000995	0	0

**Member Distributed Loads (BLC 35 : Ice Wind Load (210))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.000801	.000801	0	0
2	SO2	PY	.000801	.000801	0	0
3	SO1	PY	.000801	.000801	0	0
4	RPL3	PY	.001	.001	0	0
5	RPL2	PY	.001	.001	0	0
6	RPL1	PY	.001	.001	0	0
7	RAIL3	PY	.001	.001	0	0
8	RAIL2	PY	.001	.001	0	0
9	RAIL1	PY	.000627	.000627	0	0
10	PL18	PY	.000547	.000547	0	0
11	PL17	PY	.000547	.000547	0	0





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 35 : Ice Wind Load (210)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
12	PL16	PY	.000547	.000547	0 0
13	PL15	PY	.000547	.000547	0 0
14	PL14	PY	.000547	.000547	0 0
15	PL13	PY	.000547	.000547	0 0
16	PL12	PY	.000547	.000547	0 0
17	PL11	PY	.000547	.000547	0 0
18	PL10	PY	.000547	.000547	0 0
19	PL9	PY	.000547	.000547	0 0
20	PL8	PY	.000547	.000547	0 0
21	PL7	PY	.000547	.000547	0 0
22	PL6	PY	.000547	.000547	0 0
23	PL5	PY	.000547	.000547	0 0
24	PL4	PY	.000547	.000547	0 0
25	PL3	PY	.000547	.000547	0 0
26	PL2	PY	.000547	.000547	0 0
27	PL1	PY	.000547	.000547	0 0
28	MP GAMMA3	PY	.002	.002	0 0
29	MP GAMMA2	PY	.002	.002	0 0
30	MP GAMMA1	PY	.002	.002	0 0
31	MP BETA3	PY	.002	.002	0 0
32	MP BETA2	PY	.002	.002	0 0
33	MP BETA1	PY	.002	.002	0 0
34	MP ALPHA3	PY	.002	.002	0 0
35	MP ALPHA2	PY	.002	.002	0 0
36	MP ALPHA1	PY	.002	.002	0 0
37	FACE1	PY	.001	.001	0 0
38	FACE2	PY	.001	.001	0 0
39	FACE3	PY	.000706	.000706	0 0
40	CR6	PY	.001	.001	0 0
41	CR5	PY	.001	.001	0 0
42	CR4	PY	.001	.001	0 0
43	CR3	PY	.001	.001	0 0
44	CR2	PY	.001	.001	0 0
45	CR1	PY	.001	.001	0 0
46	CPL3	PY	.000521	.000521	0 0
47	CPL2	PY	.000521	.000521	0 0
48	CPL1	PY	.000521	.000521	0 0
49	ANGLE6	PY	.000862	.000862	0 0
50	ANGLE5	PY	.000862	.000862	0 0
51	ANGLE4	PY	.000862	.000862	0 0
52	ANGLE3	PY	.000862	.000862	0 0
53	ANGLE2	PY	.000862	.000862	0 0
54	ANGLE1	PY	.000862	.000862	0 0
55	SO3	PX	.000463	.000463	0 0
56	SO2	PX	.000463	.000463	0 0
57	SO1	PX	.000463	.000463	0 0
58	RPL3	PX	.000801	.000801	0 0
59	RPL2	PX	.000801	.000801	0 0
60	RPL1	PX	.000801	.000801	0 0
61	RAIL3	PX	.000725	.000725	0 0
62	RAIL2	PX	.000725	.000725	0 0
63	RAIL1	PX	.000362	.000362	0 0
64	PL18	PX	.000316	.000316	0 0
65	PL17	PX	.000316	.000316	0 0
66	PL16	PX	.000316	.000316	0 0
67	PL15	PX	.000316	.000316	0 0
68	PL14	PX	.000316	.000316	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 35 : Ice Wind Load (210)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
69	PL13	PX	.000316	.000316	0	0
70	PL12	PX	.000316	.000316	0	0
71	PL11	PX	.000316	.000316	0	0
72	PL10	PX	.000316	.000316	0	0
73	PL9	PX	.000316	.000316	0	0
74	PL8	PX	.000316	.000316	0	0
75	PL7	PX	.000316	.000316	0	0
76	PL6	PX	.000316	.000316	0	0
77	PL5	PX	.000316	.000316	0	0
78	PL4	PX	.000316	.000316	0	0
79	PL3	PX	.000316	.000316	0	0
80	PL2	PX	.000316	.000316	0	0
81	PL1	PX	.000316	.000316	0	0
82	MP GAMMA3	PX	.001	.001	0	0
83	MP GAMMA2	PX	.001	.001	0	0
84	MP GAMMA1	PX	.001	.001	0	0
85	MP BETA3	PX	.001	.001	0	0
86	MP BETA2	PX	.001	.001	0	0
87	MP BETA1	PX	.001	.001	0	0
88	MP ALPHA3	PX	.001	.001	0	0
89	MP ALPHA2	PX	.001	.001	0	0
90	MP ALPHA1	PX	.001	.001	0	0
91	FACE1	PX	.000815	.000815	0	0
92	FACE2	PX	.000815	.000815	0	0
93	FACE3	PX	.000408	.000408	0	0
94	CR6	PX	.000665	.000665	0	0
95	CR5	PX	.000665	.000665	0	0
96	CR4	PX	.000665	.000665	0	0
97	CR3	PX	.000665	.000665	0	0
98	CR2	PX	.000665	.000665	0	0
99	CR1	PX	.000665	.000665	0	0
100	CPL3	PX	.000301	.000301	0	0
101	CPL2	PX	.000301	.000301	0	0
102	CPL1	PX	.000301	.000301	0	0
103	ANGLE6	PX	.000498	.000498	0	0
104	ANGLE5	PX	.000498	.000498	0	0
105	ANGLE4	PX	.000498	.000498	0	0
106	ANGLE3	PX	.000498	.000498	0	0
107	ANGLE2	PX	.000498	.000498	0	0
108	ANGLE1	PX	.000498	.000498	0	0

**Member Distributed Loads (BLC 36 : Ice Wind Load (240))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	.000463	.000463	0	0
2	SO2	PY	.000463	.000463	0	0
3	SO1	PY	.000463	.000463	0	0
4	RPL3	PY	.000801	.000801	0	0
5	RPL2	PY	.000801	.000801	0	0
6	RPL1	PY	.000801	.000801	0	0
7	RAIL3	PY	.000725	.000725	0	0
8	RAIL2	PY	.000725	.000725	0	0
9	RAIL1	PY	.000362	.000362	0	0
10	PL18	PY	.000316	.000316	0	0
11	PL17	PY	.000316	.000316	0	0
12	PL16	PY	.000316	.000316	0	0
13	PL15	PY	.000316	.000316	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 36 : Ice Wind Load (240)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft,%]	End Location[ft,%]
14	PL14	PY	.000316	.000316	0	0
15	PL13	PY	.000316	.000316	0	0
16	PL12	PY	.000316	.000316	0	0
17	PL11	PY	.000316	.000316	0	0
18	PL10	PY	.000316	.000316	0	0
19	PL9	PY	.000316	.000316	0	0
20	PL8	PY	.000316	.000316	0	0
21	PL7	PY	.000316	.000316	0	0
22	PL6	PY	.000316	.000316	0	0
23	PL5	PY	.000316	.000316	0	0
24	PL4	PY	.000316	.000316	0	0
25	PL3	PY	.000316	.000316	0	0
26	PL2	PY	.000316	.000316	0	0
27	PL1	PY	.000316	.000316	0	0
28	MP GAMMA3	PY	.001	.001	0	0
29	MP GAMMA2	PY	.001	.001	0	0
30	MP GAMMA1	PY	.001	.001	0	0
31	MP BETA3	PY	.001	.001	0	0
32	MP BETA2	PY	.001	.001	0	0
33	MP BETA1	PY	.001	.001	0	0
34	MP ALPHA3	PY	.001	.001	0	0
35	MP ALPHA2	PY	.001	.001	0	0
36	MP ALPHA1	PY	.001	.001	0	0
37	FACE1	PY	.000815	.000815	0	0
38	FACE2	PY	.000815	.000815	0	0
39	FACE3	PY	.000408	.000408	0	0
40	CR6	PY	.000665	.000665	0	0
41	CR5	PY	.000665	.000665	0	0
42	CR4	PY	.000665	.000665	0	0
43	CR3	PY	.000665	.000665	0	0
44	CR2	PY	.000665	.000665	0	0
45	CR1	PY	.000665	.000665	0	0
46	CPL3	PY	.000301	.000301	0	0
47	CPL2	PY	.000301	.000301	0	0
48	CPL1	PY	.000301	.000301	0	0
49	ANGLE6	PY	.000498	.000498	0	0
50	ANGLE5	PY	.000498	.000498	0	0
51	ANGLE4	PY	.000498	.000498	0	0
52	ANGLE3	PY	.000498	.000498	0	0
53	ANGLE2	PY	.000498	.000498	0	0
54	ANGLE1	PY	.000498	.000498	0	0
55	SO3	PX	.000801	.000801	0	0
56	SO2	PX	.000801	.000801	0	0
57	SO1	PX	.000801	.000801	0	0
58	RPL3	PX	.001	.001	0	0
59	RPL2	PX	.001	.001	0	0
60	RPL1	PX	.001	.001	0	0
61	RAIL3	PX	.001	.001	0	0
62	RAIL2	PX	.001	.001	0	0
63	RAIL1	PX	.000627	.000627	0	0
64	PL18	PX	.000547	.000547	0	0
65	PL17	PX	.000547	.000547	0	0
66	PL16	PX	.000547	.000547	0	0
67	PL15	PX	.000547	.000547	0	0
68	PL14	PX	.000547	.000547	0	0
69	PL13	PX	.000547	.000547	0	0
70	PL12	PX	.000547	.000547	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 36 : Ice Wind Load (240)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
71	PL11	PX	.000547	.000547	0	0
72	PL10	PX	.000547	.000547	0	0
73	PL9	PX	.000547	.000547	0	0
74	PL8	PX	.000547	.000547	0	0
75	PL7	PX	.000547	.000547	0	0
76	PL6	PX	.000547	.000547	0	0
77	PL5	PX	.000547	.000547	0	0
78	PL4	PX	.000547	.000547	0	0
79	PL3	PX	.000547	.000547	0	0
80	PL2	PX	.000547	.000547	0	0
81	PL1	PX	.000547	.000547	0	0
82	MP GAMMA3	PX	.002	.002	0	0
83	MP GAMMA2	PX	.002	.002	0	0
84	MP GAMMA1	PX	.002	.002	0	0
85	MP BETA3	PX	.002	.002	0	0
86	MP BETA2	PX	.002	.002	0	0
87	MP BETA1	PX	.002	.002	0	0
88	MP ALPHA3	PX	.002	.002	0	0
89	MP ALPHA2	PX	.002	.002	0	0
90	MP ALPHA1	PX	.002	.002	0	0
91	FACE1	PX	.001	.001	0	0
92	FACE2	PX	.001	.001	0	0
93	FACE3	PX	.000706	.000706	0	0
94	CR6	PX	.001	.001	0	0
95	CR5	PX	.001	.001	0	0
96	CR4	PX	.001	.001	0	0
97	CR3	PX	.001	.001	0	0
98	CR2	PX	.001	.001	0	0
99	CR1	PX	.001	.001	0	0
100	CPL3	PX	.000521	.000521	0	0
101	CPL2	PX	.000521	.000521	0	0
102	CPL1	PX	.000521	.000521	0	0
103	ANGLE6	PX	.000862	.000862	0	0
104	ANGLE5	PX	.000862	.000862	0	0
105	ANGLE4	PX	.000862	.000862	0	0
106	ANGLE3	PX	.000862	.000862	0	0
107	ANGLE2	PX	.000862	.000862	0	0
108	ANGLE1	PX	.000862	.000862	0	0

**Member Distributed Loads (BLC 37 : Ice Wind Load (270))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PX	.000925	.000925	0	0
2	SO2	PX	.000925	.000925	0	0
3	SO1	PX	.000925	.000925	0	0
4	RPL3	PX	.002	.002	0	0
5	RPL2	PX	.002	.002	0	0
6	RPL1	PX	.002	.002	0	0
7	RAIL3	PX	.001	.001	0	0
8	RAIL2	PX	.001	.001	0	0
9	RAIL1	PX	.000725	.000725	0	0
10	PL18	PX	.000632	.000632	0	0
11	PL17	PX	.000632	.000632	0	0
12	PL16	PX	.000632	.000632	0	0
13	PL15	PX	.000632	.000632	0	0
14	PL14	PX	.000632	.000632	0	0
15	PL13	PX	.000632	.000632	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 37 : Ice Wind Load (270)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
16	PL12	PX	.000632	.000632	0	0
17	PL11	PX	.000632	.000632	0	0
18	PL10	PX	.000632	.000632	0	0
19	PL9	PX	.000632	.000632	0	0
20	PL8	PX	.000632	.000632	0	0
21	PL7	PX	.000632	.000632	0	0
22	PL6	PX	.000632	.000632	0	0
23	PL5	PX	.000632	.000632	0	0
24	PL4	PX	.000632	.000632	0	0
25	PL3	PX	.000632	.000632	0	0
26	PL2	PX	.000632	.000632	0	0
27	PL1	PX	.000632	.000632	0	0
28	MP GAMMA3	PX	.002	.002	0	0
29	MP GAMMA2	PX	.002	.002	0	0
30	MP GAMMA1	PX	.002	.002	0	0
31	MP BETA3	PX	.002	.002	0	0
32	MP BETA2	PX	.002	.002	0	0
33	MP BETA1	PX	.002	.002	0	0
34	MP ALPHA3	PX	.002	.002	0	0
35	MP ALPHA2	PX	.002	.002	0	0
36	MP ALPHA1	PX	.002	.002	0	0
37	FACE1	PX	.002	.002	0	0
38	FACE2	PX	.002	.002	0	0
39	FACE3	PX	.000815	.000815	0	0
40	CR6	PX	.001	.001	0	0
41	CR5	PX	.001	.001	0	0
42	CR4	PX	.001	.001	0	0
43	CR3	PX	.001	.001	0	0
44	CR2	PX	.001	.001	0	0
45	CR1	PX	.001	.001	0	0
46	CPL3	PX	.000601	.000601	0	0
47	CPL2	PX	.000601	.000601	0	0
48	CPL1	PX	.000601	.000601	0	0
49	ANGLE6	PX	.000995	.000995	0	0
50	ANGLE5	PX	.000995	.000995	0	0
51	ANGLE4	PX	.000995	.000995	0	0
52	ANGLE3	PX	.000995	.000995	0	0
53	ANGLE2	PX	.000995	.000995	0	0
54	ANGLE1	PX	.000995	.000995	0	0

**Member Distributed Loads (BLC 38 : Ice Wind Load (300))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-.000463	-.000463	0	0
2	SO2	PY	-.000463	-.000463	0	0
3	SO1	PY	-.000463	-.000463	0	0
4	RPL3	PY	-.000801	-.000801	0	0
5	RPL2	PY	-.000801	-.000801	0	0
6	RPL1	PY	-.000801	-.000801	0	0
7	RAIL3	PY	-.000725	-.000725	0	0
8	RAIL2	PY	-.000725	-.000725	0	0
9	RAIL1	PY	-.000362	-.000362	0	0
10	PL18	PY	-.000316	-.000316	0	0
11	PL17	PY	-.000316	-.000316	0	0
12	PL16	PY	-.000316	-.000316	0	0
13	PL15	PY	-.000316	-.000316	0	0
14	PL14	PY	-.000316	-.000316	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 38 : Ice Wind Load (300)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
15	PL13	PY	-.000316	-.000316	0 0
16	PL12	PY	-.000316	-.000316	0 0
17	PL11	PY	-.000316	-.000316	0 0
18	PL10	PY	-.000316	-.000316	0 0
19	PL9	PY	-.000316	-.000316	0 0
20	PL8	PY	-.000316	-.000316	0 0
21	PL7	PY	-.000316	-.000316	0 0
22	PL6	PY	-.000316	-.000316	0 0
23	PL5	PY	-.000316	-.000316	0 0
24	PL4	PY	-.000316	-.000316	0 0
25	PL3	PY	-.000316	-.000316	0 0
26	PL2	PY	-.000316	-.000316	0 0
27	PL1	PY	-.000316	-.000316	0 0
28	MP GAMMA3	PY	-.001	-.001	0 0
29	MP GAMMA2	PY	-.001	-.001	0 0
30	MP GAMMA1	PY	-.001	-.001	0 0
31	MP BETA3	PY	-.001	-.001	0 0
32	MP BETA2	PY	-.001	-.001	0 0
33	MP BETA1	PY	-.001	-.001	0 0
34	MP ALPHA3	PY	-.001	-.001	0 0
35	MP ALPHA2	PY	-.001	-.001	0 0
36	MP ALPHA1	PY	-.001	-.001	0 0
37	FACE1	PY	-.000815	-.000815	0 0
38	FACE2	PY	-.000815	-.000815	0 0
39	FACE3	PY	-.000408	-.000408	0 0
40	CR6	PY	-.000665	-.000665	0 0
41	CR5	PY	-.000665	-.000665	0 0
42	CR4	PY	-.000665	-.000665	0 0
43	CR3	PY	-.000665	-.000665	0 0
44	CR2	PY	-.000665	-.000665	0 0
45	CR1	PY	-.000665	-.000665	0 0
46	CPL3	PY	-.000301	-.000301	0 0
47	CPL2	PY	-.000301	-.000301	0 0
48	CPL1	PY	-.000301	-.000301	0 0
49	ANGLE6	PY	-.000498	-.000498	0 0
50	ANGLE5	PY	-.000498	-.000498	0 0
51	ANGLE4	PY	-.000498	-.000498	0 0
52	ANGLE3	PY	-.000498	-.000498	0 0
53	ANGLE2	PY	-.000498	-.000498	0 0
54	ANGLE1	PY	-.000498	-.000498	0 0
55	SO3	PX	.000801	.000801	0 0
56	SO2	PX	.000801	.000801	0 0
57	SO1	PX	.000801	.000801	0 0
58	RPL3	PX	.001	.001	0 0
59	RPL2	PX	.001	.001	0 0
60	RPL1	PX	.001	.001	0 0
61	RAIL3	PX	.001	.001	0 0
62	RAIL2	PX	.001	.001	0 0
63	RAIL1	PX	.000627	.000627	0 0
64	PL18	PX	.000547	.000547	0 0
65	PL17	PX	.000547	.000547	0 0
66	PL16	PX	.000547	.000547	0 0
67	PL15	PX	.000547	.000547	0 0
68	PL14	PX	.000547	.000547	0 0
69	PL13	PX	.000547	.000547	0 0
70	PL12	PX	.000547	.000547	0 0
71	PL11	PX	.000547	.000547	0 0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 38 : Ice Wind Load (300)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
72	PL10	PX	.000547	.000547	0	0
73	PL9	PX	.000547	.000547	0	0
74	PL8	PX	.000547	.000547	0	0
75	PL7	PX	.000547	.000547	0	0
76	PL6	PX	.000547	.000547	0	0
77	PL5	PX	.000547	.000547	0	0
78	PL4	PX	.000547	.000547	0	0
79	PL3	PX	.000547	.000547	0	0
80	PL2	PX	.000547	.000547	0	0
81	PL1	PX	.000547	.000547	0	0
82	MP GAMMA3	PX	.002	.002	0	0
83	MP GAMMA2	PX	.002	.002	0	0
84	MP GAMMA1	PX	.002	.002	0	0
85	MP BETA3	PX	.002	.002	0	0
86	MP BETA2	PX	.002	.002	0	0
87	MP BETA1	PX	.002	.002	0	0
88	MP ALPHA3	PX	.002	.002	0	0
89	MP ALPHA2	PX	.002	.002	0	0
90	MP ALPHA1	PX	.002	.002	0	0
91	FACE1	PX	.001	.001	0	0
92	FACE2	PX	.001	.001	0	0
93	FACE3	PX	.000706	.000706	0	0
94	CR6	PX	.001	.001	0	0
95	CR5	PX	.001	.001	0	0
96	CR4	PX	.001	.001	0	0
97	CR3	PX	.001	.001	0	0
98	CR2	PX	.001	.001	0	0
99	CR1	PX	.001	.001	0	0
100	CPL3	PX	.000521	.000521	0	0
101	CPL2	PX	.000521	.000521	0	0
102	CPL1	PX	.000521	.000521	0	0
103	ANGLE6	PX	.000862	.000862	0	0
104	ANGLE5	PX	.000862	.000862	0	0
105	ANGLE4	PX	.000862	.000862	0	0
106	ANGLE3	PX	.000862	.000862	0	0
107	ANGLE2	PX	.000862	.000862	0	0
108	ANGLE1	PX	.000862	.000862	0	0

**Member Distributed Loads (BLC 39 : Ice Wind Load (330))**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
1	SO3	PY	-.000801	-.000801	0	0
2	SO2	PY	-.000801	-.000801	0	0
3	SO1	PY	-.000801	-.000801	0	0
4	RPL3	PY	-.001	-.001	0	0
5	RPL2	PY	-.001	-.001	0	0
6	RPL1	PY	-.001	-.001	0	0
7	RAIL3	PY	-.001	-.001	0	0
8	RAIL2	PY	-.001	-.001	0	0
9	RAIL1	PY	-.000627	-.000627	0	0
10	PL18	PY	-.000547	-.000547	0	0
11	PL17	PY	-.000547	-.000547	0	0
12	PL16	PY	-.000547	-.000547	0	0
13	PL15	PY	-.000547	-.000547	0	0
14	PL14	PY	-.000547	-.000547	0	0
15	PL13	PY	-.000547	-.000547	0	0
16	PL12	PY	-.000547	-.000547	0	0



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Member Distributed Loads (BLC 39 : Ice Wind Load (330)) (Continued)**

Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/f...	Start Location[ft, %]	End Location[ft, %]
17	PL11	PY	-0.000547	-0.000547	0 0
18	PL10	PY	-0.000547	-0.000547	0 0
19	PL9	PY	-0.000547	-0.000547	0 0
20	PL8	PY	-0.000547	-0.000547	0 0
21	PL7	PY	-0.000547	-0.000547	0 0
22	PL6	PY	-0.000547	-0.000547	0 0
23	PL5	PY	-0.000547	-0.000547	0 0
24	PL4	PY	-0.000547	-0.000547	0 0
25	PL3	PY	-0.000547	-0.000547	0 0
26	PL2	PY	-0.000547	-0.000547	0 0
27	PL1	PY	-0.000547	-0.000547	0 0
28	MP GAMMA3	PY	-0.002	-0.002	0 0
29	MP GAMMA2	PY	-0.002	-0.002	0 0
30	MP GAMMA1	PY	-0.002	-0.002	0 0
31	MP BETA3	PY	-0.002	-0.002	0 0
32	MP BETA2	PY	-0.002	-0.002	0 0
33	MP BETA1	PY	-0.002	-0.002	0 0
34	MP ALPHA3	PY	-0.002	-0.002	0 0
35	MP ALPHA2	PY	-0.002	-0.002	0 0
36	MP ALPHA1	PY	-0.002	-0.002	0 0
37	FACE3	PY	-0.001	-0.001	0 0
38	FACE2	PY	-0.001	-0.001	0 0
39	FACE1	PY	-0.000706	-0.000706	0 0
40	CR6	PY	-0.001	-0.001	0 0
41	CR5	PY	-0.001	-0.001	0 0
42	CR4	PY	-0.001	-0.001	0 0
43	CR3	PY	-0.001	-0.001	0 0
44	CR2	PY	-0.001	-0.001	0 0
45	CR1	PY	-0.001	-0.001	0 0
46	CPL3	PY	-0.000521	-0.000521	0 0
47	CPL2	PY	-0.000521	-0.000521	0 0
48	CPL1	PY	-0.000521	-0.000521	0 0
49	ANGLE6	PY	-0.000862	-0.000862	0 0
50	ANGLE5	PY	-0.000862	-0.000862	0 0
51	ANGLE4	PY	-0.000862	-0.000862	0 0
52	ANGLE3	PY	-0.000862	-0.000862	0 0
53	ANGLE2	PY	-0.000862	-0.000862	0 0
54	ANGLE1	PY	-0.000862	-0.000862	0 0
55	SO3	PX	.000463	.000463	0 0
56	SO2	PX	.000463	.000463	0 0
57	SO1	PX	.000463	.000463	0 0
58	RPL3	PX	.000801	.000801	0 0
59	RPL2	PX	.000801	.000801	0 0
60	RPL1	PX	.000801	.000801	0 0
61	RAIL3	PX	.000725	.000725	0 0
62	RAIL2	PX	.000725	.000725	0 0
63	RAIL1	PX	.000362	.000362	0 0
64	PL18	PX	.000316	.000316	0 0
65	PL17	PX	.000316	.000316	0 0
66	PL16	PX	.000316	.000316	0 0
67	PL15	PX	.000316	.000316	0 0
68	PL14	PX	.000316	.000316	0 0
69	PL13	PX	.000316	.000316	0 0
70	PL12	PX	.000316	.000316	0 0
71	PL11	PX	.000316	.000316	0 0
72	PL10	PX	.000316	.000316	0 0
73	PL9	PX	.000316	.000316	0 0



**Member Distributed Loads (BLC 39 : Ice Wind Load (330)) (Continued)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
74	PL8	PX	.000316	.000316	0	0
75	PL7	PX	.000316	.000316	0	0
76	PL6	PX	.000316	.000316	0	0
77	PL5	PX	.000316	.000316	0	0
78	PL4	PX	.000316	.000316	0	0
79	PL3	PX	.000316	.000316	0	0
80	PL2	PX	.000316	.000316	0	0
81	PL1	PX	.000316	.000316	0	0
82	MP GAMMA3	PX	.001	.001	0	0
83	MP GAMMA2	PX	.001	.001	0	0
84	MP GAMMA1	PX	.001	.001	0	0
85	MP BETA3	PX	.001	.001	0	0
86	MP BETA2	PX	.001	.001	0	0
87	MP BETA1	PX	.001	.001	0	0
88	MP ALPHA3	PX	.001	.001	0	0
89	MP ALPHA2	PX	.001	.001	0	0
90	MP ALPHA1	PX	.001	.001	0	0
91	FACE3	PX	.000815	.000815	0	0
92	FACE2	PX	.000815	.000815	0	0
93	FACE1	PX	.000408	.000408	0	0
94	CR6	PX	.000665	.000665	0	0
95	CR5	PX	.000665	.000665	0	0
96	CR4	PX	.000665	.000665	0	0
97	CR3	PX	.000665	.000665	0	0
98	CR2	PX	.000665	.000665	0	0
99	CR1	PX	.000665	.000665	0	0
100	CPL3	PX	.000301	.000301	0	0
101	CPL2	PX	.000301	.000301	0	0
102	CPL1	PX	.000301	.000301	0	0
103	ANGLE6	PX	.000498	.000498	0	0
104	ANGLE5	PX	.000498	.000498	0	0
105	ANGLE4	PX	.000498	.000498	0	0
106	ANGLE3	PX	.000498	.000498	0	0
107	ANGLE2	PX	.000498	.000498	0	0
108	ANGLE1	PX	.000498	.000498	0	0

**Member Distributed Loads (BLC 43 : BLC 3 Transient Area Loads)**

	Member Label	Direction	Start Magnitude[k/f...	End Magnitude[k/ft...	Start Location[ft, %]	End Location[ft, %]
1	ANGLE3	Z	-.015	-.015	.227	2.275
2	ANGLE2	Z	-.014	-.02	.227	1.251
3	ANGLE2	Z	-.02	-.026	1.251	2.275
4	ANGLE4	Z	-.014	-.02	.227	1.251
5	ANGLE4	Z	-.02	-.026	1.251	2.275
6	ANGLE1	Z	-.01	-.02	.227	2.275
7	ANGLE6	Z	-.014	-.02	.227	1.251
8	ANGLE6	Z	-.02	-.026	1.251	2.275
9	ANGLE5	Z	-.01	-.02	.227	2.275

**Member Area Loads (BLC 3 : Dead Load)**

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[k/ksf]
1	P11	P12	P9	P10	Z	Two Way	-.01
2	P20	P21	P22	P23	Z	Two Way	-.01
3	P32	P33	P34	P31	Z	Two Way	-.01



Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

### Envelope Joint Reactions

	Joint		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
1	P24	max	.862	11	.344	2	1.522	21	3.273	21	.352	11	1.039	29
2		min	-.862	29	-.303	20	.511	2	.849	2	-.352	29	-1.04	11
3	P13	max	.514	8	.77	5	1.57	33	-.368	17	-.77	14	1.074	5
4		min	-.48	26	-.79	23	.533	14	-1.758	36	-2.9	33	-1.079	23
5	P1	max	.485	14	.767	35	1.683	10	-.369	23	3.206	10	1.078	17
6		min	-.522	32	-.787	17	.532	26	-2.608	7	.767	26	-1.076	35
7	Totals:	max	1.696	11	1.74	2	4.442	9						
8		min	-1.696	29	-1.752	20	2.598	26						

### Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distributed Area(Me...)	Surface(P...
1	Live Load	DL					1		
2	Wind Load (0)	DL					13	54	
3	Dead Load	DL			-1.1		13		3
4	Wind Load (30)	DL					26	108	
5	Wind Load (60)	DL					26	108	
6	Wind Load (90)	DL					13	54	
7	Wind Load (120)	DL					26	108	
8	Wind Load (150)	DL					26	108	
9	Wind Load (180)	DL					13	54	
10	Wind Load (210)	DL					26	108	
11	Wind Load (240)	DL					26	108	
12	Wind Load (270)	DL					13	54	
13	Wind Load (300)	DL					26	108	
14	Wind Load (330)	DL					26	108	
15	Maintenance (0)	DL					13	54	
16	Maintenance (30)	DL					26	108	
17	Maintenance (60)	DL					26	108	
18	Maintenance (90)	DL					13	54	
19	Maintenance (120)	DL					26	108	
20	Maintenance (150)	DL					26	108	
21	Maintenance (180)	DL					13	54	
22	Maintenance (210)	DL					26	108	
23	Maintenance (240)	DL					26	108	
24	Maintenance (270)	DL					13	54	
25	Maintenance (300)	DL					26	108	
26	Maintenance (330)	DL					26	108	
27	Ice Dead Load	DL					13	54	
28	Ice Wind Load (0)	DL					13	54	
29	Ice Wind Load (30)	DL					26	108	
30	Ice Wind Load (60)	DL					26	108	
31	Ice Wind Load (90)	DL					13	54	
32	Ice Wind Load (120)	DL					26	108	
33	Ice Wind Load (150)	DL					26	108	
34	Ice Wind Load (180)	DL					13	54	
35	Ice Wind Load (210)	DL					26	108	
36	Ice Wind Load (240)	DL					26	108	
37	Ice Wind Load (270)	DL					13	54	
38	Ice Wind Load (300)	DL					26	108	
39	Ice Wind Load (330)	DL					26	108	
40	Earthquake (x-directi...	DL	-.108				13		
41	Earthquake (y-directio...	DL		-.108			13		
42	Earthquake (z-directi...	DL			-.043		13		
43	BLC 3 Transient Area..	None						9	





Company : POD  
 Designer : JMM  
 Job Number : 21-108451  
 Model Name : 842869

Sept 13, 2021  
 9:04 AM  
 Checked By: \_\_\_\_\_

**Envelope AISC 14th(360-10): LRFD Steel Code Checks (Continued)**

Member	Shape	Code Check	Loc[ft]	LC	Shear Ch...	Lo...	Dir	LC	phi*P...	phi*P...	phi*M...	phi*M...	Cb	Eqn	
11	CPL2	PL6.5x0...	.128	1.5	34	.192	.25	y	19	4.979	78.975	.617	9.493	1.448	H1-1b
12	PL8	2 x 0.5	.138	.125	5	.191	0	y	26	31.671	32.4	.338	1.35	3.116	H1-1b
13	PL16	2 x 0.5	.139	.125	29	.188	0	y	14	31.671	32.4	.338	1.35	3.116	H1-1b
14	PL13	2 x 0.5	.172	.173	5	.158	.173	y	20	32.048	32.4	.338	1.35	1.228	H1-1b
15	PL17	2 x 0.5	.164	.173	2	.152	.173	y	32	32.048	32.4	.338	1.35	1.392	H1-1b
16	PL9	2 x 0.5	.165	.173	14	.150	.173	y	8	32.048	32.4	.338	1.35	1.389	H1-1b
17	PL10	2 x 0.5	.184	0	35	.147	0	y	20	31.954	32.4	.338	1.35	1.251	H1-1b
18	PL7	2 x 0.5	.177	0	20	.141	0	y	8	31.954	32.4	.338	1.35	1.269	H1-1b
19	PL15	2 x 0.5	.179	0	8	.140	0	y	32	31.954	32.4	.338	1.35	1.27	H1-1b
20	CPL1	PL6.5x0...	.106	1.5	32	.090	2.75	y	23	4.979	78.975	.617	8.415	1.283	H1-1b
21	CPL3	PL6.5x0...	.106	1.5	20	.086	.25	y	29	4.979	78.975	.617	8.444	1.288	H1-1b
22	CR4	C3.38x2...	.160	2.525	15	.080	2.2...	z	18	63.34	78.75	3.059	7.989	1.666	H1-1b
23	CR2	C3.38x2...	.156	2.525	3	.077	2.2...	z	6	63.34	78.75	3.059	7.989	1.668	H1-1b
24	CR5	C3.38x2...	.153	2.525	27	.076	2.2...	z	30	63.34	78.75	3.059	7.989	1.67	H1-1b
25	CR1	C3.38x2...	.152	2.525	27	.076	2.2...	z	24	63.34	78.75	3.059	7.989	1.665	H1-1b
26	CR3	C3.38x2...	.148	2.525	3	.074	2.2...	z	36	63.34	78.75	3.059	7.989	1.668	H1-1b
27	CR6	C3.38x2...	.145	2.525	15	.072	2.2...	z	12	63.34	78.75	3.059	7.989	1.668	H1-1b
28	SO2	HSS4X...	.188	3.333	16	.067	3.3...	y	4	188.25	197.8...	22.046	22.046	1.916	H1-1b
29	RAIL1	PIPE_2.5	.054	7.5	29	.063	.333		17	33.487	66.654	4.727	4.727	1.752	H1-1b
30	RAIL3	PIPE_2.5	.053	.5	35	.062	.333		5	33.487	66.654	4.727	4.727	1.752	H1-1b
31	RAIL2	PIPE_2.5	.054	7.5	5	.061	7.6...		35	33.487	66.654	4.727	4.727	1.752	H1-1b
32	SO1	HSS4X...	.157	3.333	27	.038	3.3...	y	2	188.25	197.8...	22.046	22.046	2.063	H1-1b
33	SO3	HSS4X...	.152	3.333	27	.036	3.3...	y	26	188.25	197.8...	22.046	22.046	2.064	H1-1b
34	FACE1	Pipe3.5...	.062	4	27	.035	.25		37	45.873	71.581	6.338	6.338	1.801	H1-1b
35	MP ALPHA2	PIPE_2.5	.080	2.167	29	.028	2.1...		29	33.487	66.654	4.727	4.727	3.852	H1-1b
36	MP BETA2	PIPE_2.5	.077	2.167	5	.028	2.1...		5	33.487	66.654	4.727	4.727	3.279	H1-1b
37	MP GAMMA2	PIPE_2.5	.076	2.167	17	.027	2.1...		35	33.487	66.654	4.727	4.727	2.783	H1-1b
38	FACE3	Pipe3.5...	.056	4	3	.027	4		2	45.873	71.581	6.338	6.338	1.789	H1-1b
39	FACE2	Pipe3.5...	.057	4	3	.027	4		2	45.873	71.581	6.338	6.338	1.79	H1-1b
40	MP ALPHA1	PIPE_2.5	.068	2.167	26	.024	2.1...		23	33.487	66.654	4.727	4.727	4.253	H1-1b
41	MP ALPHA3	PIPE_2.5	.069	2.167	14	.023	2.1...		17	33.487	66.654	4.727	4.727	4.271	H1-1b
42	MP BETA1	PIPE_2.5	.067	2.167	2	.023	2.1...		35	33.487	66.654	4.727	4.727	4.145	H1-1b
43	MP GAMMA1	PIPE_2.5	.065	2.167	14	.023	2.1...		11	33.487	66.654	4.727	4.727	4.334	H1-1b
44	MP GAMMA3	PIPE_2.5	.067	2.167	2	.023	2.1...		5	33.487	66.654	4.727	4.727	4.328	H1-1b
45	MP BETA3	PIPE_2.5	.065	2.167	26	.022	2.1...		29	33.487	66.654	4.727	4.727	4.214	H1-1b
46	ANGLE2	L2x2x4	.068	0	16	.012	0	y	15	29.528	42.48	.96	2.19	2.027	H2-1
47	ANGLE4	L2x2x4	.066	0	14	.012	0	y	3	29.528	42.48	.96	2.19	2.407	H2-1
48	ANGLE1	L2x2x4	.066	0	14	.012	0	z	27	29.528	42.48	.96	2.19	2.354	H2-1
49	ANGLE3	L2x2x4	.067	0	26	.012	0	z	3	29.528	42.48	.96	2.19	2.37	H2-1
50	ANGLE6	L2x2x4	.064	0	2	.012	0	y	27	29.528	42.48	.96	2.19	2.401	H2-1
51	ANGLE5	L2x2x4	.066	0	2	.012	0	z	15	29.528	42.48	.96	2.19	2.346	H2-1
52	RPL2	L6.6x4....	.087	0	20	.007	0	y	17	50.616	121.6...	2.465	7.125	2.036	H2-1
53	RPL1	L6.6x4....	.086	3.5	20	.007	3.5	y	23	50.616	121.6...	2.465	7.125	2.018	H2-1
54	RPL3	L6.6x4....	.081	0	32	.007	0	y	29	50.616	121.6...	2.465	7.125	2.061	H2-1

**APPENDIX D**  
**Additional Calculations**



**POD Job #** 21-108451  
**Site Number** 842869  
**Site Name** Meriden West Central

Calculations Based on TIA-222-H

**Reactions from RISA-3D**

Moment 3.273 ft-kip  
 Axial 0.862 kips  
 Shear 1.683 kips

**Capacities**

<b>Bolts</b>	<b>2.3%</b>
<b>Flange Plate</b>	<b>22.9%</b>

**Bolt Information**

Grade A325  
 Threads in Shear Plane Included  
 Diameter 0.625 in.  
 Bolt Spacing 7 in.  
 Number of Rods 4

**Flange Plate Information**

Width 9 in.  
 Thickness 0.625 in.  
 Grade A572-50

**Standoff Information**


Standoff Member HSS  
 Flat-Flat 4 in.  
 Thickness 0.375 in.

**Bolt Calculations**

$\phi$  0.75  
 $A_{nt}$  0.226 in<sup>2</sup>  
 $A_b$  0.307 in<sup>2</sup>  
 $F_u$  120 ksi  
 $\phi R_{nv}$  13.81 kips  
 $\phi R_{nt}$  20.34 kips  
 $V$  0.42 kips  
 $F$  3.02 kips  
 Capacity 2.3%

**Flange Plate Calculations**

$\phi$  0.9  
 $F_y$  50 ksi  
 $t_{min}$  0.19 in  
 $Z$  0.9 in<sup>3</sup>  
 $\phi M_n$  39.6 in-kip  
 $M_u$  9.1 in-kip  
 Capacity 22.9%





**APPENDIX E**  
**Design Criteria**

# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-10  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 165.37 ft (NAVD 88)  
**Latitude:** 41.540031  
**Longitude:** -72.819019



## Wind

### Results:

Wind Speed:	123 Vmph
10-year MRI	77 Vmph
25-year MRI	87 Vmph
50-year MRI	93 Vmph
100-year MRI	100 Vmph

**Data Source:** ASCE/SEI 7-10 Fig. 26.5-1A and Figs. CC-1-CC-4, and Section 26.5.2, incorporating errata of March 12, 2014

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-10 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is in a hurricane-prone region as defined in ASCE/SEI 7-10 Section 26.2. Glazed openings need not be protected against wind-borne debris.





**Site Soil Class:** D - Stiff Soil

**Results:**

$S_s$ :	0.184	$S_{DS}$ :	0.196
$S_1$ :	0.063	$S_{D1}$ :	0.101
$F_a$ :	1.6	$T_L$ :	6
$F_v$ :	2.4	PGA :	0.094
$S_{MS}$ :	0.294	PGA <sub>M</sub> :	0.151
$S_{M1}$ :	0.151	F <sub>PGA</sub> :	1.6
		$I_e$ :	1

**Seismic Design Category** B



**Data Accessed:**

Thu Sep 09 2021

**Date Source:**



USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.

# ASCE 7 Hazards Report

**Address:**  
No Address at This  
Location

**Standard:** ASCE/SEI 7-16  
**Risk Category:** II  
**Soil Class:** D - Stiff Soil

**Elevation:** 165.37 ft (NAVD 88)  
**Latitude:** 41.540031  
**Longitude:** -72.819019



## Ice

### Results:

Ice Thickness: 1.00 in.  
Concurrent Temperature: 15 F  
Gust Speed: 50 mph

**Data Source:** Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

**Date Accessed:** Thu Sep 09 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.


ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

**APPENDIX F**  
**Mount Specification Sheets**

NOTES:

- 1.0 GENERAL
  - 1.1 ALL METRIC DIMENSIONS ARE IN BRACKETS
  - 1.2 FOR PATENTS, SEE WWW.CS-PAT.COM
- 2.0 DESIGN NOTES
  - 2.1 TORQUE U-BOLTS TO 44 FT-LBS
- 3.0 MANUFACTURING/SPECIAL REQUIREMENTS
- 4.0 TEST
- 5.0 PACKAGING



REV.	ECN	DESCRIPTION	BY	DATE
A	10272PC	INITIAL RELEASE	HDAI	03/09/2021

**PATENT PENDING**

**COMMScope, INC. OF NORTH CAROLINA**

TOLERANCES	SAP MATERIAL MASTER
1 PLACE .X ± .25	3 PLACE .XXX ± 0.06
2 PLACE .XX ± 0.12	ANGLES ± 2°

FINISH	MATERIAL
GALV A123	A500, A1011/A1018

NAME	DATE	TITLE
CE MRC 02/17/20	03/16/2021	
RW ROGHANSON	03/16/2021	
AD BCROSS	03/17/2021	
RE FA1024	02/27/2020	
ECN 10272PC		

SCALE	DOCUMENT NO.
1:32	MC-PK8-DSH




  

SIZE	VERSION	MODEL	DRAWING	SHEET
C	01	AD	AD	1 OF 3

DENSITY	lbs/in <sup>3</sup>
MASS	lbs
VOLUME	in <sup>3</sup>
SURFACE AREA	in <sup>2</sup>
HEIGHT	96"
LENGTH	46"
WIDTH	29"

NOTES:



ITEM	PART NO.	DESCRIPTION	QTY.
1	MC-RM1550-3	12" - 50" OD RINGMOUNT	1
2	MITC300602	SECTOR WELDMENT FOR SNUB NOSE PLATFORM	3
3	MIT195801	Corner Weldment Snub Nose Handrail	3
4	GB-0520A	5/8" X 2" GALV. BOLT KIT (A325)	12
5	MIT54796	3.50" OD X 96" GALV PIPE	3
6	MIT546120	2.875" O.D. X 120" PIPE	3
7	GW-04	1/2" GALV FLAT WASHER	12
8	GLB-4355	1/2" X 3-5/8" X 5" GALV U-BOLT	12
9	MITC300618	MOUNTING PLATE FOR MIT-196	6
10	GB-04205	1/2" X 2" GALV BOLT KIT	12
11	MIT-219M-H	3.5" OD X 2-7/8" OD Clamp Bracket Assembly	9
12	GLB-4352	1/2" X 3" X 5-1/4" GALV U-BOLT	12
13	MIT54496	$\phi 2.875$ " O.D. X 96 PIPE	9
14	XP-2525	CROSSOVER PLATE KIT, 2-7/8 OD X 2-7/8 OD	9

COMMSCOPE, INC. OF NORTH CAROLINA

LOW PROFILE PLATFORM FACE


SCALE  
**C** 1:32

DOCUMENT NO.  
MC-PK8-DSH


DRAWING STATUS	AD	A
	00	
REVISION		
SHEET		

© 2021 CommScope, Inc.


NOTES:




DETAIL A  
SCALE 1 : 4




WITH ANTENNAS



DETAIL B  
SCALE 1 : 4



DETAIL C  
SCALE 1 : 4



DETAIL D  
SCALE 1 : 4

COMMSCOPE, INC. OF NORTH CAROLINA

TITLE

LOW PROFILE PLATFORM FACE

SIZE  
SCALE  
**C**  
1:24

DOCUMENT NO.  
MC-PK8-DSH

DRAWING	
VERSION	STATUS
00	AD
REVISION	A

SHEET  
3 OF 3

© 2021 CommScope, Inc.

# Exhibit F

## **Power Density/RF Emissions Report**



**RADIO FREQUENCY EMISSIONS ANALYSIS REPORT  
EVALUATION OF HUMAN EXPOSURE POTENTIAL  
TO NON-IONIZING EMISSIONS**

**Dish Wireless Existing Facility**

**Site ID: BOHVN00156A**

**842869**

**450-478 West Main Street  
Meriden, Connecticut 06451**

**November 18, 2021**

**EBI Project Number: 6221007193**

<b>Site Compliance Summary</b>	
Compliance Status:	<b>COMPLIANT</b>
Site total MPE% of FCC general population allowable limit:	<b>97.89%</b>

November 18, 2021

Dish Wireless

Emissions Analysis for Site: BOHVN00156A - 842869

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **450-478 West Main Street** in **Meriden, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The number of  $\mu\text{W}/\text{cm}^2$  calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ( $\mu\text{W}/\text{cm}^2$ ). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately  $400 \mu\text{W}/\text{cm}^2$  and  $467 \mu\text{W}/\text{cm}^2$ , respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is  $1000 \mu\text{W}/\text{cm}^2$ . Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.

Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

## **CALCULATIONS**

Calculations were done for the proposed Dish Wireless Wireless antenna facility located at 450-478 West Main Street in Meriden, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) 4 n66 channels (AWS Band - 2190 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative

estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector A, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector B, the JMA MX08FRO665-20 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline of the proposed antennas is 55 feet above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 9) All calculations were done with respect to uncontrolled / general population threshold limits.

## Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	I	Antenna #:	I	Antenna #:	I
Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20	Make / Model:	JMA MX08FRO665-20
Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz
Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd
Height (AGL):	55 feet	Height (AGL):	55 feet	Height (AGL):	55 feet
Channel Count:	12	Channel Count:	12	Channel Count:	12
Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts
ERP (W):	5,236.31	ERP (W):	5,236.31	ERP (W):	5,236.31
Antenna AI MPE %:	<b>9.85%</b>	Antenna BI MPE %:	<b>9.85%</b>	Antenna CI MPE %:	<b>9.85%</b>

Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	9.85%
Hunters	37.97%
AT&T	9.77%
T-Mobile	28.9%
Sprint	1.27%
Verizon	10.13%
<b>Site Total MPE % :</b>	<b>97.89%</b>

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	9.85%
Dish Wireless Sector B Total:	9.85%
Dish Wireless Sector C Total:	9.85%
<b>Site Total MPE % :</b>	<b>97.89%</b>

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ( $\mu\text{W}/\text{cm}^2$ )	Frequency (MHz)	Allowable MPE ( $\mu\text{W}/\text{cm}^2$ )	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	55.0	13.40	600 MHz n71	400	3.35%
Dish Wireless 1900 MHz n70	4	542.70	55.0	32.50	1900 MHz n70	1000	3.25%
Dish Wireless 2190 MHz n66	4	542.70	55.0	32.50	2190 MHz n66	1000	3.25%
						<b>Total:</b>	<b>9.85%</b>

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

## Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	9.85%
Sector B:	9.85%
Sector C:	9.85%
Dish Wireless Maximum MPE % (Sector A):	9.85%
Site Total:	97.89%
Site Compliance Status:	<b>COMPLIANT</b>

The anticipated composite MPE value for this site assuming all carriers present is **97.89%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were within the allowable 100% threshold standard per the federal government.

# Exhibit G

## **Letter of Authorization**





4545 E River Rd, Suite 320  
West Henrietta, NY 14586

Phone: (585) 445-5896  
Fax: (724) 416-4461  
www.crowncastle.com

## **Crown Castle Letter of Authorization**

### **CT - CONNECTICUT SITING COUNCIL**

Melanie A. Bachman  
Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

**Re: Tower Share Application**  
**Crown Castle telecommunications site at:**  
**450-478 WEST MAIN STREET, MERIDEN, CT 06451**

CCATT LLC ("Crown Castle") hereby authorizes DISH Wireless LLC, including their Agent, to act as our Agent in the processing of all zoning applications, building permits and approvals through the CT - CONNECTICUT SITING COUNCIL for the existing wireless communications site described below:


**Crown Site ID/Name: 842869/MERIDEN WEST CENTRAL**  
**Customer Site ID: BOHVN00156A/CT-CCI-T-842869**  
**Site Address: 450-478 WEST MAIN STREET, MERIDEN, CT 06451**

Crown Castle

By:  Date: 3/29/2022  
Richard Zajac  
Site Acquisition Specialist

# Exhibit H

## Recipient Mailings



**USPS TRACKING #**

**9405 5036 9930 0212 5844 27**

Electronic Rate Approved #038555749

**P**

04/05/2022

**US POSTAGE**

Flat Rate Env

**U.S. POSTAGE PAID**

Click-N-Ship®

Mailed from 01566

**UNITED STATES POSTAL SERVICE®**

**Click-N-Ship®**

usps.com 9405 5036 9930 0212 5844 27 0089 5000 0031 4586

**US POSTAGE**

Flat Rate Env

Expected Delivery Date: 04/08/22

Ref#: DS-842869

**0006**

**R013**

**PRIORITY MAIL 2-DAY™**

DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
420 MAIN ST  
STE 1  
STURBRIDGE MA 01566-1359

SHIP TO: RICH ZAJAC  
CROWN CASTLE  
4545 E RIVER RD  
STE 320  
W HENRIETTA NY 14586-9024



Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

### Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0212 5844 27**

Trans. #: 560465878	Priority Mail® Postage: <b>\$8.95</b>
Print Date: 04/05/2022	Total: <b>\$8.95</b>
Ship Date: 04/05/2022	
Expected Delivery Date: 04/08/2022	

**From:** DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
420 MAIN ST  
STE 1  
STURBRIDGE MA 01566-1359

Ref#: DS-842869


**To:** RICH ZAJAC  
CROWN CASTLE  
4545 E RIVER RD  
STE 320  
W HENRIETTA NY 14586-9024

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!

Check the status of your shipment on the USPS Tracking® page at usps.com



**UNITED STATES  
POSTAL SERVICE®**

**Click-N-Ship®**

**P**

USPS.com 9405 5036 9930 0212 5844 34 0089 5000 0010 6450  
**US POSTAGE**  
 Flat Rate Env  
**U.S. POSTAGE PAID**  
Click-N-Ship®

04/05/2022 Mailed from 01566


**PRIORITY MAIL 2-DAY™**

Expected Delivery Date: 04/08/22  
 Ref#: DS-842869  
**0006**

**C052**

SHIP TO: KEVIN SCARPATI  
 MAYOR- MERIDEN  
 142 E MAIN ST  
 MERIDEN CT 06450-5605

**USPS TRACKING #**



**9405 5036 9930 0212 5844 34**

Electronic Rate Approved #038555749



Cut on dotted line.

## Instructions


1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record

<b>USPS TRACKING # :</b>	
<b>9405 5036 9930 0212 5844 34</b>	
Trans. #:	560465878
Print Date:	04/05/2022
Ship Date:	04/05/2022
Expected Delivery Date:	04/08/2022
Priority Mail® Postage:	<b>\$8.95</b>
Total:	<b>\$8.95</b>
<b>From:</b>	DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359
<b>To:</b>	KEVIN SCARPATI MAYOR- MERIDEN 142 E MAIN ST MERIDEN CT 06450-5605
	Ref#: DS-842869
* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.	



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com



**UNITED STATES  
POSTAL SERVICE®**

**Click-N-Ship®**

**P**

usps.com 9405 5036 9930 0212 5844 41 0089 5000 0010 6451  
**US POSTAGE**  
 Flat Rate Env  
**U.S. POSTAGE PAID**  
Click-N-Ship®

04/05/2022 Mailed from 01566


**PRIORITY MAIL 2-DAY™**

Expected Delivery Date: 04/08/22  
 Ref#: DS-842869  
**0006**

**C054**

SHIP TO: TIMOTHY COON  
 CITY MANAGER  
 142E MAIN ST  
 MERIDEN CT 06451-5121

**USPS TRACKING #**



**9405 5036 9930 0212 5844 41**

Electronic Rate Approved #038555749



Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

### Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0212 5844 41**

Trans. #: 560465878	Priority Mail® Postage: <b>\$8.95</b>
Print Date: 04/05/2022	Total: <b>\$8.95</b>
Ship Date: 04/05/2022	
Expected Delivery Date: 04/08/2022	

**From:** DEBORAH CHASE  
 NORTHEAST SITE SOLUTIONS  
 420 MAIN ST  
 STE 1  
 STURBRIDGE MA 01566-1359


Ref#: DS-842869

**To:** TIMOTHY COON  
 CITY MANAGER  
 142E MAIN ST  
 MERIDEN CT 06451-5121

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!  
 Check the status of your shipment on the USPS Tracking® page at usps.com



**USPS TRACKING #**

**9405 5036 9930 0212 5844 58**

Electronic Rate Approved #038555749

**SHIP TO:** PAUL DICKSON  
ACTING DIRECTOR - PLANNING & ENFORCEMENT  
142 E MAIN ST  
MERIDEN CT 06450-5605

**C052**

**P**

**US POSTAGE**  
Flat Rate Env  
\$8.95

**U.S. POSTAGE PAID**  
Click-N-Ship®

Mailed from 01566

**PRIORITY MAIL 2-DAY™**

DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
420 MAIN ST  
STE 1  
STURBRIDGE MA 01566-1359

Expected Delivery Date: 04/08/22  
Ref#: DS-842869  
**0006**

**UNITED STATES POSTAL SERVICE®**

**Click-N-Ship®**

usps.com  
9405 5036 9930 0212 5844 58 0089 5000 0010 6450



Cut on dotted line.

### Instructions

1. Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
2. Place your label so it does not wrap around the edge of the package.
3. Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
4. To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
5. Mail your package on the "Ship Date" you selected when creating this label.

### Click-N-Ship® Label Record

**USPS TRACKING # :**  
**9405 5036 9930 0212 5844 58**

Trans. #: 560465878	Priority Mail® Postage: <b>\$8.95</b>
Print Date: 04/05/2022	Total: <b>\$8.95</b>
Ship Date: 04/05/2022	
Expected Delivery Date: 04/08/2022	

**From:** DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
420 MAIN ST  
STE 1  
STURBRIDGE MA 01566-1359


Ref#: DS-842869

**To:** PAUL DICKSON  
ACTING DIRECTOR - PLANNING & ENFORCEMENT  
142 E MAIN ST  
MERIDEN CT 06450-5605

\* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.



Thank you for shipping with the United States Postal Service!  
Check the status of your shipment on the USPS Tracking® page at usps.com



**USPS TRACKING #**

**9405 5036 9930 0212 5844 65**

Electronic Rate Approved #038555749

**SHIP TO:**

HUNTER FAMILY LTD PARTNERSHIP  
450 W MAIN ST  
MERIDEN CT 06451-2766

**C015**

**P**

04/05/2022 Mailed from 01566

**PRIORITY MAIL 2-DAY™**

DEBORAH CHASE  
NORTHEAST SITE SOLUTIONS  
420 MAIN ST  
STE 1  
STURBRIDGE MA 01566-1359

Expected Delivery Date: 04/08/22  
Ref#: DS-842869  
**0006**

**UNITED STATES POSTAL SERVICE®**

**Click-N-Ship®**

usps.com 9405 5036 9930 0212 5844 65 0089 5000 0010 6451  
**US POSTAGE**  
Flat Rate Env  
**U.S. POSTAGE PAID**  
click-n-ship®



Cut on dotted line.

## Instructions

- Each Click-N-Ship® label is unique. Labels are to be used as printed and used only once. DO NOT PHOTO COPY OR ALTER LABEL.
- Place your label so it does not wrap around the edge of the package.
- Adhere your label to the package. A self-adhesive label is recommended. If tape or glue is used, DO NOT TAPE OVER BARCODE. Be sure all edges are secure.
- To mail your package with PC Postage®, you may schedule a Package Pickup online, hand to your letter carrier, take to a Post Office™, or drop in a USPS collection box.
- Mail your package on the "Ship Date" you selected when creating this label.

## Click-N-Ship® Label Record

<b>USPS TRACKING # :</b>	
<b>9405 5036 9930 0212 5844 65</b>	
Trans. #:	560465878
Print Date:	04/05/2022
Ship Date:	04/05/2022
Expected Delivery Date:	04/08/2022
Priority Mail® Postage:	<b>\$8.95</b>
Total:	<b>\$8.95</b>
<b>From:</b>	DEBORAH CHASE NORTHEAST SITE SOLUTIONS 420 MAIN ST STE 1 STURBRIDGE MA 01566-1359
<b>To:</b>	HUNTER FAMILY LTD PARTNERSHIP 450 W MAIN ST MERIDEN CT 06451-2766
	Ref#: DS-842869
* Retail Pricing Priority Mail rates apply. There is no fee for USPS Tracking® service on Priority Mail service with use of this electronic rate shipping label. Refunds for unused postage paid labels can be requested online 30 days from the print date.	



Thank you for shipping with the United States Postal Service!  
Check the status of your shipment on the USPS Tracking® page at usps.com

842869 Crown  
Dish



FARMINGTON  
210 MAIN ST  
FARMINGTON, CT 06032-9998  
(800)275-8777

04/05/2022

03:20 PM

Product	Qty	Unit Price	Price
---------	-----	------------	-------

Prepaid Mail	1		\$0.00
West Henrietta, NY 14586			
Weight: 0 lb 1.90 oz			
Acceptance Date:			
Tue 04/05/2022			
Tracking #:			
9405 5036 9930 0212 5844 27			

Prepaid Mail	1		\$0.00
Meriden, CT 06451			
Weight: 0 lb 8.80 oz			
Acceptance Date:			
Tue 04/05/2022			
Tracking #:			
9405 5036 9930 0212 5844 65			

Prepaid Mail	1		\$0.00
Meriden, CT 06450			
Weight: 0 lb 8.80 oz			
Acceptance Date:			
Tue 04/05/2022			
Tracking #:			
9405 5036 9930 0212 5844 58			

Prepaid Mail	1		\$0.00
Meriden, CT 06451			
Weight: 0 lb 8.70 oz			
Acceptance Date:			
Tue 04/05/2022			
Tracking #:			
9405 5036 9930 0212 5844 41			

Prepaid Mail	1		\$0.00
Meriden, CT 06450			
Weight: 0 lb 8.80 oz			
Acceptance Date:			
Tue 04/05/2022			
Tracking #:			
9405 5036 9930 0212 5844 34			

Grand Total: \$0.00

\*\*\*\*\*  
Every household in the U.S. is now  
eligible to receive a second set  
of 4 free test kits.  
Go to [www.covidtests.gov](http://www.covidtests.gov)  
\*\*\*\*\*