



April 24, 2018

Melanie A. Bachman Acting Executive Director Connecticut Siting Council 10 Franklin Square New Britain, CT 06051

RE: Notice of Exempt Modification for Sprint Crown Site BU: 842870

Sprint Site ID: CT23XC552

434 Boston Post Road, Milford, New Haven County, CT 06460

Latitude: 41° 13' 42.69"/ Longitude: -73° 4' 12.47"

Dear Ms. Bachman:

Sprint currently maintains (3) antennas at the 150-foot level of the existing 150-foot monopole at 434 Boston Post Road, Milford, Connecticut 06460. The tower is owned by Crown Castle. The property is owned by the City of Milford. Sprint intends to install (3) antennas, (4) lines, and (6) RRHs.

The facility was approved by the Connecticut Siting Council's Petition No. 487 on October 19, 2000. This approval was given without conditions.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.S.C.A. § 16-50j-73, a copy of this letter is being sent to Mr. Benjamin G. Blake, Mayor, City of Milford, as the City is the property owner, Mr. David Sulkis, City Planner, City of Milford, and Crown Castle is the tower owner.

- 1. The proposed modifications will not result in an increase in the height of the existing tower.
- 2. The proposed modifications will not require the extension of the site boundary.
- 3. The proposed modification will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
- 4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communication Commission safety standard.
- 5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.

The Foundation for a Wireless World.

CrownCastle.com

6. The existing structure and its foundation can support the proposed loading.

For the foregoing reasons, Sprint respectfully submits that the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Anne Marie Zsamba.

Sincerely,

Anne Marie Zsamba, Esq.

Real Estate Specialist

3 Corporate Park Drive, Suite 101, Clifton Park, NY 12065

(518) 350-3639

annemarie.zsamba.contractor@crowncastle.com

Attachments:

Tab 1: Exhibit-A: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-B: Structural Modification Report

Tab 3: Exhibit-C: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mr. Benjamin G. Blake, Mayor

City of Milford 110 River Street Milford, CT 06460 (203) 783-3201

David Sulkis, City Planner City of Milford 70 West River Street Milford, CT 06460 (203) 783-3245 Petition No. 487
VoiceStream Wireless
North Branford, Connecticut
Staff Report
October 19, 2000

On October 17, 2000, Connecticut Siting Council (Council) member Dr. William H. Smith and Christina Lepage and Joel Rinebold of the Council staff met with VoiceStream Wireless (VoiceStream) representative Brendan Sharkey west of Route 22, North Branford, Connecticut for inspection of an electric transmission structure. The property and structure is owned by Connecticut Light and Power Co. (CL&P). VoiceStream Wireless, with the agreement of CL&P, proposes to modify the structure by installing antennas and associated equipment for telecommunications use and is petitioning the Council for a declaratory ruling that no Certificate of Environmental Compatibility and Public Need (Certificate) is required for the modification.

VoiceStream proposes the installation of three EMS dual-pol antennas on top of a 3-inch wide pipe mast extension. The antennas will extend approximately 10-feet 8-inches above the existing 91-foot 6-inch transmission line monopole structure (#4955). The height at the top of the antennas will be about 102-feet 2-inches above ground level (AGL) with the centerline at 99-feet 10-inches AGL. This design requires a minimum of six feet above the CL&P shield wire. The structural analysis suggests that the existing guy be replaced and that an additional guy be added to the other side to ensure the capability of the structure to support the proposed equipment.

The Nortel S8000 equipment cabinet will be mounted on a 10'x12' concrete slab in a 15'x20' fenced compound at the base of the tower facing Route 22. A second Nortel S8000 equipment is proposed for future installation if the site begins generating significant traffic and the structure is able to accommodate additional loading. The equipment cabinet does not require any protective structures or air conditioning; therefore no audible noise will be created. Power and telephone service to the site will be provided from an underground conduit to the west side of Route 22 and then routed overhead to an existing utility pole on the east side of the highway.

The Algonquin gas line will serve as access to the site as currently used by CL&P. Trenching for the site will be at a required depth of between 12 and 36 inches, depending on the terrain, and will span from the tower to the western edge of Route 22. CL&P has already contacted Algonquin Gas about the proposed installation.


Petition 487 Staff Report October 19, 2000 Page 2

The proposed site is located directly west of Route 22 in North Branford. The zoning designation of this site is R-80 residential. Land use in the surrounding area is primarily woodland, with some distant single-family residences and the Evergreen Woods senior facility through the woods to the west. The closest residence to the proposed site is approximately 600 feet to the north.

VoiceStream contends that the increase in height of this monopole structure will not result in a substantial environmental effect. The proposed project will prevent the construction of a new tower in the area. VoiceStream also states that the PCS antennas will blend in with the existing transmission line structure and the placement of the associated equipment, which will be directly underneath the existing tower, will limit the disturbance created by construction activities.

The worst-case power density for the telecommunications operations at the site has been calculated to be 2.12% of the applicable standard for uncontrolled environments.

VoiceStream submits that the proposed modification of the structure would not require a Certificate because it will reduce the need for a new telecommunications tower by utilizing an existing structure and contends that the proposed installation will not cause a substantial adverse environmental effect.



Map Block Lot

064 930 6 A

Account


023341

Property Information

Property Location	434 BOSTON POST RD								
Owner	CITY OF M	ILFORD							
Co-Owner	C/O AT&T MBLTY-TAX DEPT								
Mailina Addusa	575 MOROSGO DR								
Mailing Address	ATLANTA	GA	30324						
Land Use	434V	V CELL TOWER MDL-00							
Land Class	1								
Zoning Code									
Census Tract									

Neighborhood	D
Acreage	0
Utilities	All Public,Public Sewer
Lot Setting/Desc	
Additional Info	

Photo



Sketch

Primary Construction Details

Year Built	
Stories	
Building Style	
Building Use	
Building Condition	
Floors	
Total Rooms	

Bedrooms	
Full Bathrooms	
Half Bathrooms	
Bath Style	
Kitchen Style	
Roof Style	
Roof Cover	

Exterior Walls	
Interior Walls	
Heating Type	
Heating Fuel	
АС Туре	
Gross Bldg Area	
Total Living Area	

Map Block Lot

064 930 6 A

Account

023341

Valuation	Summary
ranamon	Juillialy

(Assessed value = 70% of Appraised Value)

Item	Appraised	Assessed				
Buildings						
Extras	0					
Improvements						
Outbuildings	450000	315000				
Land	0	0				
Total	450000	315000				

Sub Areas

Subarea Type	Gross Area (sq ft)	Living Area (sq ft)
	:	
····		
Fotal Area		0

Outbuilding and Extra Items

Туре	Description
CEL TWR SITE	1 UNITS
-	

Sales History

Owner of Record

Book/ Page

Sale Date

Sale Price

CITY OF MILFORD

02435/0430

11/22/1999



PROJECT:

SITE NAME:

DO MACRO UPGRADE

Sprint Manage Company Company

MILFORD

CT23XC552

SITE CASCADE:

842870

SITE NUMBER:

FROM ZERO TO INFINIGY
FROM ZERO TO INFINIGH
FROM ZERO TO INFINIGH
FROM ZERO TO INFINIGH
FROM ZERO TO INFINIG

434 BOSTON POST ROAD MILFORD, CT 06460

SITE ADDRESS:

SELF SUPPORT TOWER

CROWN

SITE TYPE:

MARKET:

SITE INFORMATION

LONGITUDE (NADB3): -73 4" 12.47" W -73.070131

LATITUDE (NADBS): 41° 13° 42 69° N 41.238825

ZONING JURISDICTION: OTY OF METORO

COUNTY: NEW HANDA

ZONING DISTRICT:

NEW ENGLAND

			-	=	=	-			۲	_		-		-	1		브		_	1	3 3	<u>.</u>	١ī				_	ع ا	_			_	L	
		ğ	ŀ	-	۰	9	9	-	°	•	٥	•	٩	Ţ	L		T	Γ	L		I	I			Γ		L		Γ			Γ	Ī	
	DRAWING INDEX	SHEET TIME	TIME SHEET & PROJECT DATA	SPROFT SPECIFICATIONS	SPRINT SPECIFICATIONS	STE FLAN	TONER ELEVATIONS & CABLE PLAN	AMERICA LAYOUT & MOMENTING DETAILS	EQUIPMENT & MOUNTING DETAILS	CIME, DETAILS	PLINGSHIG ONCORNE	ELECTRICAL & GROUNDING DETAILS	ELECTRICAL & GROUNDING DETAILS																					
-		SHEET NO.	ī	į) j	Į	-2	7	Į	Ţ	Į	Ĭ,	5-2																					†
PRODUCT DESCRIPTION	COUNTY DESCRIPTION OF THE PROPERTY OF THE PROP	TELECOMENSIONS FACILITY	PSTALL 2.5 EQUIPMENT MYRIC EXISTING N.Y. MARS CARRET	* HSDAL (6) PODEL ANDRESS AND REPLACE (3) EXERNIC ANTERNS	* BESTALL (6) KRESTS TO TOMER	The state of the s	Separat (4) manual control	• REDIENE (5) WIRKED CHAIRS							NEXT PLANS HAVE BEEN DEPENDED FOR THE LANGUAGEMENT OF IN COMM.	MANAGED TRECOMMENCEDES FACTOR ORIGIN OR ESCED BY SPIRIT IN	ACCORDING THE DAY SCHOOL OF MINE THE MAN THE PASSED OF SPRING THEORY FOR	THE CONSTRUCTION LINEARS ACCOMPANDED BY A PASSAGE STATEMENT.	CONTROL BREAKS PROPERTY BY A LEGICAL STRUCTURE. BREAKER.	THE PROPERTY OF THE PARTY OF THE PARTY OF THE PARTY.	APPROVED TRANSPORT	A COMPANY WARES	ALL WOOK SHILL BE PETERBED AND MATERIALS WISHING BY	CODES AS ACTUALS OF THE CAPACIAL CONTRACT CONTRACTOR	ACTIVITY IN THESE PLANS IS TO BE CONSIDER TO PERMIT WORK	MAT CONFORMAC TO THESE CODES.	1. WIESENGOROU, SCHOOL COST COST CONT. SALV	2 Person on Lary Compa	A. Mart. 780 - Unitable: Profession cone	A ART CERES MEDICAL CO. TOTAL CO. CALLED CO.	MACH RECENT ENGINES	A And Marine Core	- valywani membrass	
AREA MAP		The second secon										THE REPORT OF THE PARTY OF THE			では、10mm	The state of the s	The state of the s	第一次では、100mmに対象が形式をよっている。 100mmに対象が形式をよっている。			LOCATION MAP	~	Aleja .	2000	4	igh.	S. S			Active Angestan	Anthonia Company	€	South Land	1

434 BOSTON POST ROAD MILFORD, CT 06460

CT23XC552

atte cascage:

MILFORD

TITLE SHEET
& PROJECT DATA

Accellenting &

SPRINT CONSTRUCTION: POWER COMPANY; UNITED ELIMINATING COMPANY (800) 722-5884

T-1

THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONSTRUCTION.

SECTION OF 100 - SCOPE OF WORK

1.1 THE WIDGE THESE STANDARD CONSTRUCTION SPECIPICITIONS IN CONJUNCTION THE WIDGE STANDARD STANDARDS FOR WINELESS SITES, COMPINED COCCUMENTS AND THE CONSTRUCTION DEWNINGS DESCRIBE WORK TO BE PERFORMED BY THE CONTRACTION.

1.2 RELATED DOCUMENTS:

A. THE RECUMEMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

R. SPRINT STANDARD CONSTRUCTION DETAILS FOR WRIGESS STESSARE INCLIDED IN AND MADE A PART OF THESE SPECIFICATIONS HERBRITH.

1.4 PREZIDENCE SNOLLD COMPLYN OCCUR BITMERT THE STANDARD CHRENKENTON BETALLED STEEN WERENESTE STEEN BOLDINGHE OF SYNUNDED OLDSFROLLAND BETALLED STEEN AND THE OWNSTRUCTION ROMANICE, INTOMOTON OF THE CONSTRUCTION ROMANICE, WITH SPORT SYNOL CONSTRUCTION ROMANICE, WITH SYNOL CONSTRUCTION WITH SYNUNDS SYNL TWO PRESIDENCE, WHITH SYNOL CONSTRUCTION ROMANICES, WITH SYNOL CONSTRUCTION ROMANICES, WITH SYNOL CONSTRUCTION

1.4 MATICHALLY RECOGNIZED CADES AND STANDA

A. THE WORK SHALL COURTY WITH APPLICABLE NATIONAL AND LOCAL CORES AND STANDARDS. LATEST DATEN, AND PORTIONS THEMEDF, INCLUDED BUT NOT LIMITED. TO THE FOLLOWING.

1. CR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION

5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANIFACTURE OF TELECOMMUNICATIONS EQUIPMENT.

MICAUL FRE PROTECTION ASSOCIATION CODES ARD STANDARDS (NEPA). 3. GR-1089 CORE, ELECTROMAGNETIC COMPARIBILITY AND ELECTRICAL SAFETY - GENERIC CRITICAL FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.

ALERICAN SOCIETY FOR TESTING OF MATERIALS (ASTA)

INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (REE)

AMERICAN CONCINCTE INSTITUTE (ACI)

AMERICAN WIRE PRODUCERS ASSOCIATION (AMPN) COMCRETE REINFORCING STEEL INSTITUTE (CRSJ)

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICALS (MISHRO)

11. PORTLAND CEMENT ASSOCIATION (PCA)

12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)

13. BRICK WOUSTRY ASSOCIATION (BIA)

14. AMERICAN WELDING SOCIETY (AWS)

15. WITOWAL ROOFING CONTRACTORS ASSOCIATION (NRCA)

16. SHEET METAL AND AR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SEACON)

18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA) 17. DOOK AND HARDWINE INSTITUTE (DHI)

19. APPLICABLE BULDING CODES INCLUDING UNEITHOU BUILDING CODE, SCUINERIN BUILDING CODE, BOCA, AND THE WITENATIONAL BUILDING CODE.

work the SLM of USKS and responsiblines dentifed in the contract Documents.

COMPANY, SPRINT CORPORATION

ENJAKEPS SYNOMMOUS WITH ARCHITECT & ENGRIEDR AND YARS, THE DESIGNAL HANNO PROFESSIONAL HOSPONSHILITY FOR DESIGN OF THE PROJECT PROJECT OF THE

CONTRACTOR CONSTRUCTOR CONTRACTOR CONSTRUCTOR VENDOR HEMODIAL OR BEILITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOUNTS. THE WORLD

THEO PARTY VOLOGY OR ARBYCH, A VENOOR OR ARBYCH SEEJUED SEPARATLY BY THE COMPANY, ALE, DIE COMPANY, ALE, DIE COMPANY, ALE, DIE COMPANY, ALE, DIE COMPANY DIE PROMINE MORBINED IN THE WORK. ACCOMPANY SPECTOD DIESE RELATED TO BUT NOT MACHINED IN THE WORK.

OFCE CHRER FLRNISHER, CONTRACTOR INSTALLED EXCEPLENT.

CONSTRUCTION MANAGER — ALL PROJECTS RELATED COMMENSATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

1 WITH PARLIANCE, COMPANIONE SHALL OF RESPONSEES FOR THE MAN ADDRESS. THE CONSTRUCTION OF THE CONSTRUCTION OF THE CONSTRUCTION OF THE STATE OF THE CONSTRUCTION OF THE STATE O

1-2 POSET OF CREACE; CRAMMANDORDR BETWEEN SPRING AND THE CONTRACTOR SPRILL. THE THROUGH THE SPRING CONSTRUCTION MANAGER, APPORTED TO MANAGE. THE PROJECT FOR STRUCT.

A ON-SITE ENCORPORTORE THE COMPRISED SHALL SUPERIORS AND PRICES THE WORK
14 MOUNTED STREET STREET OF CONTRACTIONS AND STREET STREET.
CHRISTORY SHALL ENCORPORT ON STREET S

13 DOWNESS, SPLETSKINDS AND DETAKS REQUISED AL ADBRIET HE CONSTRUCTOR CONTROLLY WAS AND LIVED A FIRE LESS OF THE CONSTRUCTOR DOWNESS, SILVED WAS DESCRIBED AND THE STREAM CONSTRUCTION SCHAFFEN FOR WRITES SITS AND HE STREAM CONSTRUCTION FOR WRITESS SITS AND THE STREAM MANUAL HEACHER CONSTRUCTION FOR WRITESS SITS AND THE STREAM MANUAL HEACHER CONSTRUCTION FOR THE STREAM CONSTRUCTION.

THE LIGHT DIRECT STREAMORE WE DELSE SHE BE CERTY WHO WAY HE FOR FIXEN BITH AND OWNERS BE UNCENTURED ON BY BITE ST. BITH AND OWNERS BE UNCENTURED ON BY BITE ST. BITH AND OWNERS BE UNCENTURED ON BY BITH AND OWNERS AND OWNE

NOTICE, ACE MODICED TO SAME NOTICE. INCREMENTED BAY EX-TROUNED TO SAME AND SAME NOTICE. CONTINUES, AND SAME NOTICE. SAME OF REPORTS OF PART OF WICH THE WORK TO PRODUCE SAME NOTICE. OURSINGTION BOARDS OF ANY WIGHTON PROCK TO PRODUCE WITH THE WARRY.

MANCHANIS STANM FOR THE RESIDENCES HALLOSS MANCHANIS CHEERER FOR STANKING STANKING TO THE RECURSED LICENMENT. STANKING THE RECURSED LICENMENT. STANKING THE WAS THE RECURSED LICENMENT OF COMPANY OF C

1.10 USE OF JOB STIE THE COMPRISTOR SHALL COMERNE ALL CONSCRUZION AND RELATED OFFENDER MILLIONES SCHOOL OF WINDOWS AND EQUIPMENT, FRANKES, AND WISTE STORAGE TO THE LEVER PHACKES, AND WISTE STORAGE TO THE LEVER PHACKES, AND WISTE STORAGE TO THE LEVER PHACKES OFFENDER TO PROVIDE THE LEVER PHACKES CHACKES CHACKES THE PHACKES OF THE LEVER PHACKES THE PHACKES OFFENDER TO THE LEVER PHACKES THE PHACKES OFFENDER TO THE LEVER PHACKES OFFENDER TO THE PHACKES OFF

1.11 INTERES SCHOOLS, WHOSE MEDISORERY TO CUT EXISTING PROS. GLEATHON, WRISE, ADMINIST, OURSE, TO., OF INTER SCHOOLS, OF THE, OWNERSON, ON CAMBRINGHOUSE SYSTEMS, THEY SHILL BE. CUT AND CHAPTE JAY STROME PLACES OF CHAPTE AND CHAPTE JAY STROME PLACES OF CHAPTER STROME SHALLS.

1.12 PERMS / FERS. WERN BOUNEDS HAVEA HERWELD OF COMMERCIAN FIR RE PARK IN A PHRAZA ULIUPP PROMORER HER STONECE ID HIS CONSTRUCTOR PROMOSER. PRINCES, PRINCES, PRINCES, SALES, SA

1/3 CONTROLLOR SHULL THE ALL MENSIONS AND PROPER ALL MATRIM, HEICESHAY FOR PROTECTING DISSING EXPENDER AND PROPERTY.

1.14 METHODS OF PROMEDIATE (MOVE) FOR CONCINCIONE COMPANIA SMIL PERTON WORK AS DESIGNED IN THE PULLORING INSTALLARIES AND COMMISSION MOVES.

NOTE: IN SHOKE-FORM SPECIFICATIONS ON THE INDUNINES, A/E TO RESERT LIST OF APPLICABLE MOPS WILLIAMS EM-2012-COT, EM-2013-COZ, EM-CSOM, AND TS-0185

PART 2 - PRODUCTS (NOT USED) PART 3 - EXECUTION

1.15 USE OF ELECTRONIC PROJECT IMMEGIENT SYSTEMS

ALT BROGNET WITHER SON FACURES, THE CARBOLOGY BOALD ON PRESCRICE FOR ALL THE PROPERTY (ALTER SON FOLKE) BECKNOON THE CARBOLOGY SON FOLKES BECKNOON FOLKES THE PROPERTY OF ACCESS AND PROPERTY OF ACCESS AND PROPERTY OF ACCESSING OF THE WAY WERE ALTERED TO THE WAY WERE HE DEFINED WE THE THE THE PROPERTY OF THE CONTRIBUTION OF THE PROPERTY OF THE PROP

AJ ACCES TO WHICH THE CONTRACTORS SHALL PROPER ACCESS TO THE JUB SEE THRE ALMOSTED CONFORM PRESONNEL AND ARMITISCED INTERESTRAINES OF THE ARCHITECT/ENGINESS DARRIES OF THE WING.

ALTSTERNER, RECORDERABING TOWN TOSTONE OF THIS COMPRINCING SPALL THE AS AND CONTROL AND THE BROWNING STATES OF THE CONTROL OF THE STATES OF TH

A DUMPICONS, NEWFY DRIENSINGS MICHAED ON IDOMENICS WITH THEIR DIMPINISMS. BEFORE FRENCHION OR ORDERED OF INTERPRES, DO NOT SCARE EXPRESS.

1.5 DESING CONTINUES UNITY THE SPHAR CONSTRUCTION BANAGES OF EXCENSIVE CONTINUES DEFENSE THAN THOSE MICHAELD ON THE INSURINGE, DO HOT RELADICATION THE PRESENCE OF HOT RELADICATION THE PRESENCE OF HOT RELADICATION WITHOUT PROPERTY. FROM THE

SECTION Of 200 — COMPANY FURNISHED MATERIAL AND EQUIPMENT PART 1 — GENERAL

1.1 THE WORK THERE STANDARD CONSTRUCTON SPECIFICATIONS IN CONLINCTION WITH THE OTHER CHARGE CONSTRUCTION DAYMENTS DESCRIBE THE WORK TO BE PERFORMED BY THE CHARGOLOGY.

6580 Sprint Pertures Overland Park, Kenson 6 Sprint

1.2 RELATED DOCUMENTS

A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.

B. STRWT STRUMAD CONSTRUCTOR DETAINS FOR WHILE SS STES ARE INCLUDED IN AND MINE A PART OF TAKES SPECIATIONS HERBITH.

PART 2 - PROBUCTS (NOT USED) PART 3 - EXECUTION

3.1 récort of motora, and couparient a. A company pronésed materal and equipaent is dentred on the RP days speet in the constitution documents.

THE CONTRACTOR IS RESPONSEDE FOR SPRINT PROVIDED MATERIAL AND EXEMPLEM AND UPON RECEPT SAULT.

2. VENLY COMPLETENESS AND CONDITION OF ALL DELINERES, 1 ACCEPT DELIVERES AS SHEPPED AND TAKE RECEPT,

dave responsibility for Equipaent and Provide Insurance Protection as resumed in Agreebyr.

MINOLOGISMS: +-

RECORD ANY LOTECTS OR DAMACES AND WITHIN THENCY—FOLK HOUSS, AFTER SECSEF, REPORT TO SYRAIT OR IS DESCANTED PROJECT REPRESENDATION SHOCK.

S. PROVIDE SEDURE AND MEDESSARY WEATHER PROTECTED WAYER-CUSTOD.

8. COORDWATE SAFE AND SECURE TRANSPORTATION OF WATERAL AND TOTAL PROPERTY DELINERS AND OFF—LONDING FROM COMPINATION'S WATER-CLIENT TO SITE.

A. COMPLETE SHEPPING AND RECEIPT DOCAMENTATION IN ACCREMANCE WITH COMPANY PROCEED.

B. IF APPLEABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTAIN REPORT AS RECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.

C. UPLOND DOCHEDGRICH MTD STOWN SITE MANAGERINT SYSTEM (SMS) AND/OR PROMISE HARD CORPY DOCHEDWATCON AS REQUESTED.

SECTION 01 300 - CELL SITE CONSTRUCTION CO. PART 1 - GENERAL

1.1 The which these structed construction specificals in community the other countest construction the construction because the wave to be perfenced in the confinction deviates the

A. The regimenents of this section apply to all sections in this specification. 1.2 NEARED DOCUMENTS:

8. SPRONT STANDARD CONSTRUCTION DETAILS FOR WIRELESS STEES ARE ENCLIDED IN AND MADE A FIRST OF TRESS SPECIFICATIONS HERBERT. 1.3 MODES TO PROSE

A. NO WORK SHALL COMMENCE PROOR TO COMPANY'S WRITISH NUTICE TO PROCEED AND THE ISSUANCE OF THE WORK CROSES.

THE ORDER LOTTERING.

WHEN THE PROPERTY OF THE STATES AND ACCESSED THE WORKE TO PROJECT
CONTINUENT WILL CONTINUE THE CONTINUENT OF MANY OF THE STATES

FROM TO WINN STATE, THE WAY ARROW. TO BE ALL STITE, COSTINUENT OF THE STATES

FROM TO BOOK STATE, THE WAY ARROW. TO BE ALL STITE, COSTINUENT OF THE STATES

FROM TO BOOK STATE, THE WAY ARROW. TO BE ALL STITE, COSTINUENT OF THE STATES

FROM THE STATES AND ACCESSED. B. LIFOR RESENTAND NOTICE TO PROCEED, CONTOXCTOR SAVAL FULLY PERCORAL MODE STATES THAN WITH AN ORGANIZATION, PRELIESS THAN

PART 2 - PRODUCTS (NOT USED) PART 3 - EXECUTION

A THE ACTIVITIES CEREMED IN THE PROJECTOR INSPECTOR LABORILA ACTIONS AN PROSESSED TO SECURE AND THE PROPERTY OF THE PROSESSED TO SECURE ACTION ACTION TO SECURE ACTION ACTION TO SECURE ACTION AC

B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HERBIR, AND CHIMIN REQUIRED APPROVALS WALE THE WORK IS BEING PERFORMED. C. MANNE AND CONDUCT ALL FELD CONSTRUCTION SERVICE RELATED ACTUALIES

D. PROMDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCOMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING

NEINGY ZERO TO INFINIGY bbs watervillet fanker no j Albung, nv 1,1 Phoogs (11-194-194) j Kurt utvebery nveni influjij com **za jeden** (20-10)





		THESE DOCUMENTS ARE COMPANION AND ARE
PAN STATE OF	- DRAMMONDE	THEM BOCKANEWS AR

THEM DOCHMENTS ARE COMPROPRITING AND AND THE SOLE PROPRIES OF SOME MANTED OR REDISTIBLITIES WITHOUT THE EXPRESS MANTED OR REDISTIBLITIES WITHOUT THE EXPRESS WITHING COMPERED OF SPRINT.
--

F	Š	F	L	L	9	4	
ь.	ă				H/O/H	S BUTELY	ŀ
NEWBIONES:	DESCRIPTION				SSLED FOR CONSTRUCTION	SOLD FOR REALIN	

MILFORD

CI23XCS52

434 BOSTON POST ROAD MILFORD, CT 06460 EET DESCRIPTION: - SPRINT SPECIFICATIONS

SP-1

CONTINUE FROM SP-1

- 1. PERFORM ANY REDURED SITE ENVIRONMENTAL MITIGATION.
- PREPATE GROUND SITES; PROMDE DE-GRUBERING; AND ROUGH AND FRAM, GRUDHIQ, AND COMPOUND SURFACE TREATMENTS.
 - WANGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTLITIES HIGHBING ELECTRICAL AND TELCO BACKGOWE.
 - 4. INSTALL UNDERSOUND FACILIES BAZLUDBAS UNDERGROUND POWER AND COMMANICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
 - S. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
- PROVIDE NEW HAY. INSTALLATIONS AND MODIFICATIONS.
- 7. NSTALL "H-FRANES", CABINETS AND SHELTERS AS INDICATED.
- 8. HISTOLL ROADS, ACCESS WAYS, CURBS AND DRAMS AS APOICATED.
- ACCOMPLISH REDURED ADDITIONER OF EXISTING FACULTIES.
 - 10, PROMOE ANTENIA, SLIPPORT STRUCTURE FOUNDATIONS.
- 12. INSTALL COMPOUND FENCING, SIGHT SHELLONG, LANDSCAPING AND ACCESS BANBELFS. 11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
 - 13. PERTORN MSPECTICH AND MATERIAL TESTING AS REGULARD HENERWE'TE
 - 14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTED
- 15. NSTALL FIXED GENERATOR SETS AND DRIER STANDEY POWER SOLUTIONS
- 18. BETALL TOWERS, ANTENNA SIPPORT STRUCTURES AND PLATFORMS ON EXSING TOWERS AS REQUIRED.
- 17. MSTALL CELL SITE PADIOS, MISDOWAYE, CPS. CONVAL LAMEDIE, ANTIDANS, COSS. BAND COVERES, TOWER TOP AMPLETIS, LOW MISSE TAMERERS. AND RELATIO EQUIPMENT.
 - 18, PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL. DOCUMENTS. THAT LAY BE REQUIRED BY COVENIABRY AGENCES AND LABOCAES.
 - 19. PERFORM, AMEDIAND, AND COM SMEEP TESTING AND LANCE ANY AND ALL NECESSARY CORRECTIONS.
- 20, RDMAP ON STE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSET S NEEDED UNTIL STE IS DESMED SUBSTANTALLY CIMPLETE AND PLACED "ON AR".
- 3.2 ODNERAL REGURGACINIS FOR CIVIL, CONSTRUCTION:
- Compactor Spall Ked? The Stif File film accumulative waste water beings, and these, compactor spall, redwire from the Sif Li Remaind Rubbish individuals. Theorem from the Sif Li Remaind Rubbish individuals. Theorem Fachings, and Subolus Mattheway.
- CONTRACT ANY HAZFOODS CARBONALE PREDAINTONS TO DISCORER AND
 LIDOUTE ART HAZFOODS CHRIMING. THE HAZFOODS CONDITION WHICH
 HAS HAZFOODS CHRIMING AND HAZFOODS CONDITION WHICH
 HAS HAZFOOD HAZFOODS TO FIDENCE MAN HAZFOODS CHRIMING CONTRACTOR WAS NOT CHRIMING TO FRENCH WITH A PRESENT STORY WHOM IN HER APPEADS ANSI AND
 HAZFOODS CHAMING THE WARRING THE WARRING THE WAS NOT HAT
 RE FIGURED TO LICED THE WARRING THE WAS NOT HAT
 RE FIGURED TO THE WARRING THE WAS NOT HAT
 RE FIGURED TO THE WARRING THE WARRING THE WARRING. eriement rooms shull at all times be amataned troom clent-and Clen of debas.
- COMPACTOR ACREES TO USE DARE WHEE ON THE SITE AND SWILL NOT TAKE WATTOR THY WILL OR WASSILT IN OR CAUSE THE HAZMODIS COUNTINN TO BE FUFFHER RELEASED IN THE EMPROMEDY, OR TO FURTHER REPOSE INSTITUTING THE WASONED TO STATIFFE
- D. COMRACTOR'S ATTAINES SHALL BE RESTRICTED TO THE PROLEST LIMITS, SECULD AGES UNITED. THE REALIZED THAT SERVICE & PETGETHE DIFF. CONTINUELTING SHALL IMMEDIATES, REVIEW HEBY TO GROWING, CONDITION
 - E, CONDUCT TESTING AS REQUIRED HENERAL

3.3 DELMERABLES:

- A. CONTRACTOR SHALL REMEW, APPROVE, AND SUBMIT TO SPRONT SHOP DISMINISHED PRODUCT DATA, SALPLES, AND SHALAR SLIBHITALS AS REQUIRED MENERALITIES.
- B. PROMDE DOCKMENTATION BACLIONNS, BUT NOT LIMITED TO, THE FOLLDWAY.

 DOCKMENTATION SHALL BE FORMANDED IN ORIGINAL FORMAT AND/OR UPLOADED.

 WITO SAGS.
- 1. ALL CORRESPONDENCE AND PRELIMBARRY CONSTRUCTION REPORTS. 2. PROJECT PROCRESS REPORTS.
- CAN. CONSTRUCTION START DATE (POPULATE FIELD IN SAIS AND/OR FURNIAND NOTPLICATION).
 - ELECTRICAL SERVICE COMPLETION DATE (POPILATE FIELD IN SAIS AND/OR PORWARD MOTERCATION).

- Lines and anterna install diver (Poppeane field in sigs and/on Formation notification).
- Poper result due (populate field in sus and/or forend noteinmen).
- TELED REVOY DATE (POPULATE, FIELD IN SUS AND/EN FURNING NOTIFICIEDAR).
- FPC (OR SEELER) INSTALL DATE (POPULATE FIELD IN SINS AND/OR FERN NOTIFICATION).
- TOWER CONSTRUCTION START DATE (POPULATE PIELD # 545 AND/OR FORWRO HOSPONION).
- 10, TOWER CONSTRUCTOR CHIEFETE DATE (POCKLATE FELD IN SAS AND/OR FORMATO MOTIFICION).
- 11. BTS AND RAZIO EQUIPARA DELINENDA À SIE DATE (POPULATE PIELD IN SIES AMB/DR PURIUMED MODERNARA).
- 12. Neiwork opforions handoff chickaest (hac weld) complete (upload) Form in Ses)
 - 13. CHI. CONSTRUCTON CONFLEX DATE (POPOLATE FRED IN SUS AND/OR PORMAD MOTECULOR).
- 14, STE CONSTRUCTION PROCRESS PROTRES LINEONOED BATO SAS. SECTION OF 400 - SUBMITTALS & TESTS
 PART 1 - GENERAL
- 1.1 THE WORN, THERE STANDARD CONCINUENTAL SCHOOLSCHEE IN COMMUNICAL WITH THE CHEEK CONTRACT OF DECLINARIES FOR DECLINARIES AND DECLINARIES OF DECLINARIES OF THE CONTRACTION.
- - 1.2 REATED DOCUMENTS:
 - A. THE REGIMENENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIALISM.
- B. SPRINT STANDARD CONSTRUCTION DETAILS FOR WHELEXS STAISS AND REQUIDED IN AND LINDE A PAGE OF THESE SPECIFICATIONS SPECIFICAL. 1.3 SUBMETERS.
- A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION ON AND THESE SPECIFICATIONS.

- 1. CONSTRUE MIX-DESIRES FOR TOMER FOMENCIALS, ANCHORES PIETS, AND CONSTRUE PARKS. B. SUBAIT THE FULLDWING TO COMPANY REPRESENCIATINE FOR APPROVING
- 2. CONDICTE BREAK TISTS AS STEEDED HERRY.
- 4. ALL EXPENDER AND IMPRIMES SO EXPORED ON THE CONSTITUTION DISTRICT. A SPECIAL FINESHES FOR INTERESE SPICES, F. AMC
 - 5. CHERTA GROWING DESIGN
- ALTENNACE OF THE CANADATES AND ALLEGACIES. WE ALTENDACE TO THE AMBIGNES. WHICH STREETS SHALL BE STREETED TO SHARE OF STREETS THE ENGINEER. ENGINEER ENGINEER. ENGINEER

1.4 TESTS AND INSPECTATIONS

- A. THE CONTRACTOR SHALL BE RESPONDEDE FOR ALL CONSTITUTION TESTS, INCREMENTING.
- 1. COXX SIREDS AND FIREN TESTS PER CHRESOT VENSOR OF SPRINT'S TS-1200 AREDINA LINE ACCEPTANCE STANDARDS.

R. COMPACTOR SHALL ACCIMENTED TESTING MILITIMES BUT NOT TAKED TO THE FOLLOWING:

- 2. A2., AZMATH AND DOMERAT USING ELETROBAL COMMERCIAL MADE-FOR-THE-PREPOSE ANTENIA, ALCAMENT TOXI.
- COMENCERS SHALL RE RESPONSELE FOR ANY AND ALL CHROCKERS TO ANY WORK RECIFIED AS UNIVERSELY OF USING, AND THE WISPELTING ACTIVITIES AND FUR AS
 - REQUISED CLOSEDUT DOCLAEMONTAN ANCLUCES, BAT IS NOT LANTED TO THE FOLLOWISE.
- AZNATIR, DOMENTI AZ. UNICAD REDORF REDA AKERSAN ALGONOM TOXI. TO STEED NEX AGE. NEXALLED AZNATIL, UNICATILI, AGE MAST TO STEED NEX AGE. SECONOMICAL SECONOMICAL AGE. MAST
- Schweie Burche Photochers of Kier top and Backersele Etaelded Egerhen
- . POF SOW OF REQUEES PRODUCED IN FIELD 3. AL ADEASTE JATEOUTIONAL MEDINATES

- PING, PANEDIT APPLICATION
- 9 CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEPICEMENT TITLES. B. REQUIRED FINAL CONSTRUCTION PHOTOS

NEINIGY &

6389 Sprint Partaray Overland Part, Kenses 65

Sprint

- SO, ALL POST KIP TAKE MOLLICHE DOCUMENT UPLONDS COMPLETED IN SITERAL (SPERKES DOCUMENT REPOSTORY OF RECORD).
 - 1.5 COMPESSIONERS: PERFORM ALL COMMESSIONERS AS REQUIRED BY APPLICABLE MODE.

The solutions are endless
These Steles at | Alban, by 122
These Steles at | Alban, by 122
These Steles | Alban, by 122
West-Little | Alban, by FROM ZERO TO INFINIG

- 1.8 Interdedick Perform all intervation activities as required by Applicable Mode.
- PART 2 PRODUCTS (NOT USED) PART 3 EXECUTION

 - 3.8 REPARTMENTS FOR TESTINGS

CASTLE

- A WEST THE ISE OF A TABLE PARTY MIDEPARENT TESTING AGENCY ES REGARDLY TO AGRICITY MAY IS SECURIFIED MAY FERTONE SICH WORK CHA REGALDLE BASSE IN THE STATE WEST THE PROJECT IS LOCATED AND HAVE A TABLE CHARLES MAY FOR FLOUR, MALLEL MATERIAL, MICLIDARD THE STAL, ROCK, AND ERMANDRICH COUNTING.
- The Theo pyriv testing aethy is to se parilar woy the applicable Recordings for the 16513 to be done, equipaent to be used, and aesocato houth and safity esiles,

- 3. EXPERIENCE IN SOULS, CONCRETE, INISTANCE, ACCRETATE, AND ASSING, AND CHERR METHOGS IS NEEDED.
- A. DIPERRONE BI SOUS, CONCRETE, MICHORAYE, AND ASPINAT TESTING USING ASIM, ANSATO, AND OTHER METHODS IS REFEREN.
 - 3.2 RECURSO TESTS
- CONCRETE CHANGE BREAK TESTS FOR THE TOWER AND ARCHOR POSANDAGAR AS SPECIFED IN SECTION PURILAND CENENT CONCRETE PARMA. CONTRACTOR SHALL ACCOURTISM TESTING INQUITING BUT NOT LIMITED TO THE FOLLOWING

MISSONAL ETT CENSED

- ASTRUT ROMBAY COMPACTED THOMESS, SURFACE SMOOTHAGES, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION. HOT MIX ASTRUCT POWER.
- FREED GLIMITY CONTROL, TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAYMAG.

THESE DOCUMENTS ARE CONTIDENTIAL AND INTEGRAL SHOWN NOT REPRODUCED, DESCRIPTION OF SPAULT ON EXPERIENCE ON REDISTRIBLY WITHOUT THE REPRESS WAITTEN CONSENT.

- TESTING REQUIRED LINDER SECTION: AGGREGATE BASE FOR ACCESS ROJUS, PAUS AND ANCHOR LOCATIONS
 - SHE RESISTANCE TO EATH TESTING PER DOMBIT; CELL SITE GROLINDAD SYSTEM (PENSIN). E. STRENGTON BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
- anteria, med com smetp tests fer equalt, anterna transmission line. Acceptiblics symbologs.
- 8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS

20 FOR CONSTRUCTION 20 FOR RENDW

9. ALL OTHER TESTS REDURNED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

- A SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE,
- B. CONDUCT RESPECTORS INCLIDENG BUT NOT LIMITED TO THE FOLLOWING
- GROUNDING SYSTEM NEGRALTHEN FROM TO EARTH CONCENTATION DOCUMENTED WHY BRITISH. PHOTOGRAPHS BY CONTRACTOR, APPROVED BY AME ON SYMPHIC REPRESENTATION.
- FORIENC FOR CONCRETE AND REBAR PLACEMENT PRICE TO POUR DOCKMENTED WITH LOGGEL PHOTOGRAPHS BY CONTINUETOR, APPROXED BY ARE OR STAFFI REPRESENTANCE.
 - CONFECTION OF BUCKTLL MATERIALS, AGGREGATE BASE FOR ROADS, PADS, AND MATERIALS AND SAVED BUCKTLL FOR CONCRETE AND PROCES, OF DESPEROENT PIRRO PARTY ASSIST.
- PRE— AND POST-CONSTRUCTION ROOTTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACULTIES.
- TOMER ERECTION SECTION STACKING AND PLAITORM ATACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIS PARTY AGENCY.
 - Mitowa azbaith , down the And Per Semesht tool sunsidht Bestrakents Mitowalich Algment tool (Art)
- **SP-2**

SPRINT SPECIFICATIONS

434 BOSTON POST ROAD MILFORD, CT 06460

CT23XC552

MIL FORD

CONTINUE FROM SP-2

- 7. VERFICKTION DOCUMENTED WITH THE ANTENNA CHECKLEST REPORT, BY ALK. SITE DEVELOPMENT REP, OR RF REP.
- B. FIVAL WISPECTION CHERGLEST AND HANDOFF WALK (HOC.). SERVED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO HE UPLOADED INTO SMS.
- 9. COXX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VA SUB FOR REAPPROVAL.

 - 10, SOAN—ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND EMCCESSBLE SERVALZED EQUEPAINT
- 11. ALL AVALABLE SUBSDICTIONAL INFORMATION
- THE CONTRACTOR SHALL BE RESPONSELE FOR ANY AND ALL CORRECTIONS TO ANY WORK DEPOSITIONS & UNIOCASTIVABLE ON SITE RESPECTION ACTIVATES AND/OR AS A RESULT OF TESTING. 12, POF SOAN OF REDUNES PRODUCED IN FIELD
- OVERFACTION RESPICTANCE NO ORGENITE RESISTENCE SAME IS DOCUMENTED BY THE COMPRISON WHILE RESISTENCE AND PROTOCEMPELS PROTOCEMPELS PROTOCEMPELS PROTOCEMPELS AND TO EXPENSE SAME THE STREET COMMENTED IN THE PROTOCEMPELD INTO COMMENTED IN THE PROTOCEMPELD INTO MAD BY LABOR THE PROTOCEMPELD INTO MAD BY LABOR SAME WITH THE STREET CHANGES, STE NAME, DESCRIPTION, AND MAD.
 - 2.4 delagabeles 1837 and inspection redorts and closody documentation sall. BE UTLODOS TO THE SUS AND/OR FORMACED TO SPART FOR RELIESON INTO THE PERMACH SITE RIES.
 - A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PRONDED AS APPLICABLE.
 - 1. CONCRETE LIN AND CYLNDER BREAK REPORTS
- 2. STRUCTURAL BACKGEL COMPACTION REPORTS.
- SITE RESISTANCE TO EARTH TEST.
- ANTENDA AZIMUTH AND DOWN TILT VERFICATION
- tower erection inspections and alkandarys documentary tower inspolled per supplicits requireders and the applicate sections herein.
 - COXX CABLE SHEEP TEXTS PER COMPANYS "ANTEXUM LINE ADCEPTANCE STANDARDS". REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING
- TEST WELLS, AND TREACHES, PHOTOGRAPHS OF ALL TEST WELLS, PROCEEDING ALL OPEN ECOMMITINES AND TREACHER PROCEED BOOMETLAND SHOWN A TAPE MENSURE WISHER IN THE EXCHANDINES ROCKING OFFILE.
- CONDATS, CONDUCTORS AND GROUNDINGS. PHOTOGRAPHS SHOWER THEYN PERFECTIVES AND CONFIDENCES SHOWER SHOWER THEY SHOWER SHOWER
- CONCINCTE TROBA WE DESIDENTIALLY CONTINUE TROBAGO AT TROBE AND ELIDINARY FROM THE TRANSPORTER TRANSPORTER TO A SHARING SHARING
- - ROT TUDE RE-CANGERICAN AND PACE ASSESSMENT VOUR MEPETIDIS NO PARTICIPATION VOUR MEPETIDIS NO PACE NO PACE DISCUSSION OF PROTECTION OF RECURSION OF THE COOK AND INTEGER TO RECEIVE AND PACE TO PACE THAT WAY ON A SECULD OF PROTECTION OF PROTECTION OF THE THAT WAY NOT A SECULD OF THAT WAS NOT A SECURD OF THAT WAS NOT A SECULD OF THAT WAS NOT A SECURD OF THE WAS NOT A SECURD OF THAT WAS NOT A SECURD OF THAT WAS NOT A SECURD OF THAT WAS NOT A SECURD OF THE WAS NOT A SECURD OF THAT WAS NOT A SECURD OF THE WAS NOT A SECURD OF THE WAS NOT A SECURD O
- SATE LAYOUT PROTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORRESTS.
- RECURED MATERIALS CERTIFICATIONS: COMPRETE MIX DESIGNS; MAI. CERTIFICATION FOR ALL PENYTHCING AND STRUCTURAL, STREET, AND ASPHALT PANNE MIX DESIGN.
- ANY AND ALL SUBMITIALS BY THE JURISDICTION OR COMPANY.

ECTION OF 400 - SUBMITTALS & TESTS ARE 1 - GENERAL

1.3 THE WATER THESE STANDARD CONSTRUCTION SPESSOODERS A CONSIDERING WITH THE GUISS CONTINUED DOCUMENTS AND THE CONSTRUCTION DOMINIOS DESCRIPE THE WATER THE FUNDAMENT OF THE CONTINUEDS.

12 RELATED DOCUMENTS

- A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICALIZAR.
- B. SPRING STANDARD CONSTRUCTION DETAILS FOR WRELESS STEEN ARE INCLUDED BY AND ANDE A PART OF THESE SPECIALIZATIONS HANCING.

PART 2 - PRODUCTS (NOT USED) PART 3 - EXECUTION

- 3.1 WEDAY REPORTS:
- CONTRICTOR SHELL PROVING SYMBAT WITH WEIGHT SCHOOLS SKHOOLS AND STATEMENT OF STATEM
- B. REPORT NECESARIEM WILL BE TRANSLADTED TO SPORT WA ELECTRONE MEMS A REQUEST, DISS WETRINGON WILL PROPILE A BASS FOR PRINCESS, MONTRING AND PARKETS.

32 PROJECT COMPRENES CALLS.

- A STRANT STATE WESTERN PROJECT COMESTICATE COURS COMPOCING WILL BE CESTINGS OF A STRANG CONTROLLING AND STOCKNE LECENSING OF COMPOCING AND STRANG CONTROLLING CONTROLLING AND STRANG CONTROLLING AND STRANG CONTROLLING AND STRANG CONTROL AND ST
- S.S. PROJECT TRACOGUE DE SALES
- A. CONTRUCROS SHALL PROPEE SINFEREE UPDATES AND PROJECTIONS OR THE SILES System can a regal gross.

34 ADDIDOWL REPORTHES

- A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE AZOED TO THE REPORT AS DEJENDANDED TO BE RESCONDALY MEDICINGRAF BY COMPANY.
- FIEL HEIDLE, PHODOSOPHIS OF COMPLIED SITE IN LAFE FORMET IN THE SISSEMILIED LEGISOPHER STREET, FROM LEGISOPHER SIZE OF PHODOSOPHERS SHALL BE CLEARLY LARELD WITH SIZE AND RESIZE AND SERVED HEIDLE OF LIBERTY, AND SERVED HEIDLE OF LIBERTY, AND SERVED HEIDLES, AND REMOVED THE SERVED HEIDLES, AND SERVED HEIDLE
- 1. ISHELTER AND TONER CAESANCE
- TOPER FOUNDATION(S) FORMS MED STEEL BEFOXE FOUR (ENCH ANCYFE ON GLYED FOREISS).
- TOWER FUNDAMES) FOUR WITH WENDER IN USE (EACH ANCHOR OR CAYED TOWERS).
- TOWER STEEL AS BEING ASSIALED WITO MEET (SHOW ANCHOR STEEL ON CONTO TOWERS).
- CONCRETE TESTING / SAUPLES.
- PHOTOS OF TOWER SECTION SYNCHOLS.
- PLAZEG OF ANCHOR BOLTS IN TURER FOUNDAMEN
- s. Brichig/Brief Daix fixth kidd for torne wydolenis or co
 - 9. SHELTER FOLKSMICH -FORMS AND STEEL BEFORE POURHE I'D. SHELTER FOUNDING FORR WITH VERSION IN USE.

 - H. COK CHEE BARY NO SHETER.
- 12. PLOPORM MECHANICAL COMMECTIONS TO TOWNS/MEMBRINE
- 13, ROOFTOP PRE AND PUSY CONSTRUCTION PROTOS TO MIZLUGE PENETR AND BRITISION CERSIS.
- 14. PHOTOS OF TOWNER TOP COME LINE COCOR COOMS AND COLOR COMPAG GROUND LEMEL.
- 15. PHOTOS OF ALL APPROPRIATE COMPANY OR RESULATION SIGNAE.
 - 18. PHOTOS OF EXAMPLEIT BOLT DOWN MEDIC SPECIES.
- 18. EECHACIL TRENCH(S) WITH ELECTRICAL / COMDUIT BETONE BACKELL 17. POWER AND TELCO EMENORE, TO COMPANY ENCLOSURE. TELCO SUPPLY LOCATIONS MICHIGANG METRY/DISCONDESS.
- 19. ELECTRICAL TRENCH(S) WITH FORL-BACKED TAPE REFUNE FURTHER INCO
- 21. Tâlco Trench wer for-gaced tafe betwee forder back 20. FELCO TRENCH WITH TELEPHONE / CONDUST ELEGNE BACKFILL
- 22. SHEITER GROUND-RING THENCH WITH GROUND-HINE BETOKE BACKTEE (SHO) ALL CAD WELDS AND HIDD ROOM).
- 23, TOWER GROUND-RANG TRENCH WITH CHOUND-WAS BESTONE BACKRILL (SICHE Ale cad Welles and Group Radig.

6380 Sprint Partway Overland Part, Kansas 66251

Sprint

24. FENCE CROUND-RING TRENCH WITH CROUND-WITE BETOKE BACKFLL (SHOW ALL CAD WELDS AND BEND RACK).

25. ALL HIS GROUND CONNECTIONS.

25. ALL GROUND TEST WELLS,

NFINIGY® Anna Scientife Commence of the FROM ZERO TO INFINIG

CASTLE

- 33. Buch section of Anthanas, one photograph Loomas at the section and the from being showns the prolifere constant area. 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 - JA. MASTER BUS BAR.

29. HARC LIMITS INCLUDING CONDENSERS ON SPLIT SYSTEMS. 28. ADDITIONAL GROUNDING POWITS ON TOWERS ABOVE 2001. 27. ANTERNA GROUND BAR AND EQUIPMENT GROUND BAR,

31. CHRE TRNY AND/OR WANGELING BREDGE,

IN USA ACCOURAGE.

- 25, TELCO BOMPO AND INEL

- 36. ELECTRICAL DISTRIBUTION WALL.

- - SA. ENTRANCE TO EXITINGED ROOM,
- 37, CABLE ENTRY WITH SURGE SUPPRESSION
- 29. COXX WEATHERSHOUTHG-TOP AND BOTTOM OF TOWER.
 - 40, COAX GROUNDING -TOP AND BOSTOM OF TOMER. 45. ANTENNA AND NAST CROLADS
- 42. LANGSCHOPRIG. WHÉTE, APPLICAGE,
 24. RANGSCHOPRIG. WHÉTE, APPLICAGE,
 25. RENEWIT, CONTROCT DOCUMENTS OF THE STAND HIGHORD CHARRACTEN
 STANDARDS FOR MESLESS STEEN AND FATOR STEEN.



SPACE NO.			ı,
DESCRIPTION	DATE	ДB	PEV
			Γ
	Γ		Ι
		Γ	
		Γ	I
SUED FOR CONSTRUCTION	34,04/10	K	•
CLIED FOR REPORTS	OZ /Jan/TB	ď	E
			ľ


MILFORD


CT23XC552


434 BOSTON POST ROAD MILPORD, CT 06460


SPRINT SPECIFICATIONS


SP-3




















February 12, 2018

Chanhdara Ratsavong Crown Castle 3530 Toringdon Way Suite 300 Charlotte, NC 28277 (980) 209-8234



B+T Group 1717 S. Boulder, Suite 300 Tulsa, OK 74119 (918) 587-4630 btwo@btgrp.com

Subject:

Structural Analysis Report

Carrier Designation:

Sprint PCS Co-Locate Carrier Site Number: Carrier Site Name:

CT23XC552 MILFORD

Crown Castle Designation:

Engineering Firm Designation:

Crown Castle BU Number: Crown Castle Site Name: Crown Castle JDE Job Number: Crown Castle Work Order Number: Crown Castle Application Number:

MILFORD 474267 1521848 418412 Rev. 1

842870

B+T Group Project Number:

91292.008.01

Site Data:

434 Boston Post Road, Milford, New Haven County, CT

Latitude 41° 13' 42.69", Longitude -73° 4' 12.47"

150 Foot - Self Support Tower

Dear Chanhdara Ratsavong,

B+T Group is pleased to submit this "Structural Analysis Report" to determine the structural integrity of the above-mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural 'Statement of Work' and the terms of Crown Castle Purchase Order Number 1138061, in accordance with application 418412, revision 1.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment

Note: See Table 1 and Table 2 for the proposed and existing/reserved loading, respectively.

Sufficient Capacity

This analysis has been performed in accordance with the 2016 Connecticut State Building Code based upon an ultimate 3-second gust wind speed of 125 mph converted to a nominal 3-second gust wind speed of 97 mph per Section 1609.3 as required for use in the TIA-222-G Standard per Exception #5 of Section 1609.1.1. Exposure Category C and Risk Category II were used in this analysis.

All equipment proposed in this report shall be installed in accordance with the attached drawings for the determined available structural capacity to be effective.

We at *B+T Group* appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Jacob Johnson, E.I.T.

Respectfully submitted by: B&T Engineering, Inc.

COA: PEC.0001564 Expires: 02/10/2018

Scott S. Vance, P.E

tnxTower Report - version 7.0.5.1



TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 - Tower Components vs. Capacity

4.1) Recommendations

5) APPENDIX A

tnxTower Output

6) APPENDIX B

Base Level Drawing

7) APPENDIX C

Additional Calculations

1) INTRODUCTION

This tower is a 150 ft. Self-Support tower designed by PiRod Inc. in March of 2000. The tower was originally designed for a wind speed of 85 mph per TIA/EIA-222-F. This tower has been modified by GPD Group in 2012 and those modifications were incorporated in this analysis.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA-222-G Structural Standards for Steel Antenna Towers and Antenna Supporting Structures using a 3-second gust wind speed of 97 mph with no ice, 50 mph with 0.75-inch ice thickness and 60 mph under service loads, exposure category C with topographic category 1 and crest height of 0 feet.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Elevation	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
	402.0	3	Alcatel Lucent	RRH2X50-800			
400.0	103.0	3	Alcatel Lucent	TD-RRH8X20-25	3	1-1/4	
100.0	400.0	3	Commscope	DT465B-2XR	1	7/8	
1	100.0	3	Site Pro	STK-U Stiff Arm Kit			

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines		Note
The state of the s	160.0	2	Sinclair	SC226-SFXSNM		F /0	
150.0	151.0	2	Radiowaves	HPLPD1-18	6	5/8 3/8	1
	150.0	1		Platform Mount [LP 405-1]	1	3/0	
		3	Andrew	SBNHH-1D65A			
		3	Cci Antennas	OPA-65R-LCUU-H4			
		1 Commscope WCS-IMFQ-AMT			7.0		
	3 Ericsson RRUS 32 B2		2	7/8 3/8	2		
		3	Ericsson	RRUS 32 B30]	0,0	
		3	Powerwave Tech	LGP21401			
141.0	141.0	1	Raycap	DC6-48-60-18-8F			
		3	Ericsson	RRUS 11 B2			
		3	Powerwave Tech	7020.00]		
		3	Powerwave Tech	7770.00	12	1-5/8 5/8	1
		3	Powerwave Tech	LGP21401] 1	3/8	
		1	Raycap	DC6-48-60-18-8F			
		1		Sector Mount [SM 410-3]		ļ <u>.</u>	
130.0	130.0	2	Terrawave	M5160160P10006	2	7/8	1 1
130.0	130.0	2		Side Arm Mount [SO 301-1]] 2	170	
	128,0	1	Sinclair	SC229-SFXLDF			
118.0	120.0	1	Sinclair	SC320	2	7/8	1
	118.0	2		Side Arm Mount [SO 306-1]			
	114.0	1		Sector Mount [SM 307-3]			
114.0	112.0	3	Commscope	LNX-6515DS-VTM	18	1-5/8	1
	112.0	3	Ericsson	ERICSSON AIR 21 B2A B4P			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
		3	Ericsson	ERICSSON AIR 21 B4A B2P			
114.0	112.0	3	Ericsson	KRY 112 71]		1
		3	Ericsson	RRUS 11 B12			
400.0	400.0	3	Alcatel Lucent	800MHZ 2X50W RRH W/FILTER			
103.0	103.0	3	Alcatel Lucent	PCS 1900MHZ 2X40W] -	1	
		1		Pipe Mount [PM 601-3]] .		
		3	Rfs Celwave	APXVSPP18-C-A20			1
100.0	100.0	1		Sector Mount [SM 406-3]]		
			==	purt.	3	1-1/4	3
		6	Antel	BXA-171063/8CF			
		6	Antel	LPA-80063/4CF			
90.0	90.0	1	Rfs Celwave	DB-T1-6Z-8AB-0Z	12	1-5/8	
00.0	88.0		Rfs Celwave	FD9R6004/2C-3L	12	1-5/0	'
		3	Swedcom	SWCP 2x5514			
	88.0	1		Sector Mount [SM 408-3]			<u> </u>
65.0	65.0	3	Rfs Celwave	APXV18-206517S-C 6		1-5/8	4
50.0	50.0	1 .	Pctel	GPS-TMG-HR-26NCM	1	1/2	1

Notes:

- 1)
- Existing Equipment
 Reserved Equipment
 Equipment To Be Removed; Not Considered In This Analysis
 Abandoned Equipment considered In This Analysis 3) 4)

Table 3 - Design Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	r Antenna Model		Feed Line Size (in)
		4	Celwave	PD201		
150	150	3	Scala	PR950	7	1 5/8
		1	Generic	LP Platform		
440	140	12	Allgon	7184	12	1 5/8
140	140	3	Generic	T-Frames	12	1 5/6
405	125	1	Celwave	PD201	1	1 5/8
125	125	1	Generic	3' Stand off	<u> </u>	1 5/6
		1	Celwave	PD201		, , , , , , , , , , , , , , , , , , , ,
115	115	1	Celwave	PD220-DT	2	1 5/8
i		2	Generic	3' Stand off		

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Remarks	Reference	Source
Online Order Information	Sprint Co-Locate, Rev# 1	418412	CCI Sites
Tower Manufacturer Drawing	PiRod Inc., Eng. File No. A-116849-Q-92250	4480661	CCI Sites
Tower Modification Drawing	GPD Group, Job No. 2012762.86,	4713244	CCI Sites

Document	Remarks	Reference	Source
Post Modification Inspection	GPD Group, Job No. 2012858.01,	4713239	CCI Sites
Mount Analysis Report	Infinigy, Project No. 526-103	Date:01/23/2018	CCI Sites
Foundation Drawing	PiRod Inc., Eng. File No. A-116849-Q-92250	4480652	CCI Sites
Geotech Report	Clarence Welti Associates, Date: 01/17/2000	5359323	CCI Sites
Antenna Configuration	Crown CAD Package	Date: 02/02/2018	CCI Sites

3.1) Analysis Method

tnxTower (version 7.0.5.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) Tower and structures were built in accordance with the manufacturer's specifications.
- 2) The tower and structures have been maintained in accordance with the manufacturer's specification.
- 3) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 4) Mount areas and weights are assumed based on photographs provided.
- The existing base plate grout was considered in this analysis. Grout must be maintained and inspected periodically, and must be replaced if damaged or cracked. Refer to crown document ENG-BUL-10122, Tower Base Plate Grout Inspection and Classification.

This analysis may be affected if any assumptions are not valid or have been made in error. B+T Group should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
T1	150 - 147.583	Leg	1 1/2	2	-7.035	51.350	13,7	Pass
T2	147.583 - 130	Leg	1 1/2	14	-24.051	51.350	46.8	Pass
T3	130 - 110	Leg	2	71	-63.188	111.705	56.6	Pass
T4	110 - 100	Leg	Pirod 105244	135	-69.534	142.493	48.8	Pass
T5	100 - 80	Leg	Pirod 105216	146	-109.484	142.493	76.8	Pass
Т6	80 - 60	Leg	Pirod 105217	167	-165.668	214.859	77.1	Pass
T7	60 - 40	Leg	Pirod 105218	185	-208.475	300.681	69.3	Pass
T8	40 - 20	Leg	Pirod 105218	202	-249.159	300.681	82.9	Pass
T9	20 - 0	Leg	Pirod 105219	217	-287.025	399.868	71.8	Pass
T1	150 - 147.583	Diagonal	3/4	8	-1.602	5.311	30.2	Pass
T2	147,583 - 130	Diagonal	3/4	22	-3.105	4.879	63.6	Pass
- T3	130 - 110	Diagonal	7/8	79	-5,298	7,820	67.8	Pass
T4	110 - 100	Diagonal	L2 1/2x2 1/2x3/16	143	-9,037	13,558	66.7 73.7 (b)	Pass
T5	100 - 80	Diagonal	L2 1/2x2 1/2x3/8	155	-15.135	20.328	74.5	Pass
Т6	80 - 60	Diagonal	L3x3x3/16	174	-8.776	14.947	58.7 75.6 (b)	Pass
T7	60 - 40	Diagonal	L3x3x3/16	189	-8.695	12.112	71.8 74.6 (b)	Pass
T8	40 - 20	Diagonal	L3x3x5/16	208	-9.306	15.594	59.7	Pass

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
Т9	20 - 0	Diagonal	L3x3x5/16	223	-10.654	12.868	82,8	Pass
T2	14 7.583 - 130	Horizontal	7/8	35	-0.324	5.109	6.3	Pass
Т3	130 - 110	Horizontal	3/4	127	-0.720	2.563	28.1	Pass
T5	100 - 80	Horizontal	L3x3x3/16	159	-9.149	17,168	53.3 97.3 (b)	Pass
T1	150 - 14 7.583	Top Girt	5x1/2	4	-1.180	9.674	12.2	Pass
T2	147.583 - 130	Top Girt	7/8	18	-0.113	5.917	1.9	Pass
T3	130 - 110	Top Girt	7/8	74	-1.301	4.878	26.7	Pass
T4	110 - 100	Top Girt	L3x3x3/16	137	0.891	28.679	3.1 7.6 (b)	Pass
T5	100 - 80	Top Girt	L3x3x3/16	151	-6.112	19.238	31.8 65.3 (b)	Pass
Т6	80 - 60	Top Girt	L3x3x3/16	171	-6.745	13.961	48.3 70.5 (b)	Pass
T2	147.583 - 130	Bottom Girt	7/8	19	-1.222	4.831	25.3	Pass
Т3	130 - 110	Bottom Girt	7/8	76	-1.551	3.967	39.1	Pass
							Summary	
						Leg (T8)	82.9	Pass
						Diagonal (T9)	82.8	Pass
						Horizontal (T5)	97.3	Pass
						Top Girt (T6)	70.5	Pass
						Bottom Girt (T3)	39.1	Pass
						Bolt Checks	97.3	Pass
						Rating =	97.3	Pass

Table 6 - Tower Component Stresses vs. Capacity - LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods	Base	54.3	Pass
1	Base Foundation (Structure)	Base	14.6	Pass
1	Base Foundation (Soil Interaction)	Base	41.3	Pass

Structure Rating (max from all components) =	97.3%
--	-------

Notes:

4.1) Recommendations

The tower and its foundation have sufficient to carry the final load configuration. No modifications are required at this time.

¹⁾ See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.



RADIO FREQUENCY EMISSIONS ANALYSIS REPORT EVALUATION OF HUMAN EXPOSURE POTENTIAL TO NON-IONIZING EMISSIONS

SPRINT Existing Facility

Site ID: CT23XC552

Milford 434 Boston Post Road Milford, CT 06460

April 16, 2018

EBI Project Number: 6218002840

Site Complian	ce Summary
Compliance Ştatus:	COMPLIANT
Site total MPE% of	
FCC general	19.46 %
population	13.40 70
allowable limit:	



April 16, 2018

SPRINT Attn: RF Engineering Manager 1 International Boulevard, Suite 800 Mahwah, NJ 07495

Emissions Analysis for Site: CT23XC552 - Milford

EBI Consulting was directed to analyze the proposed SPRINT facility located at 434 Boston Post Road. Milford, CT, for the purpose of determining whether the emissions from the Proposed SPRINT Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (µW/cm2). The number of $\mu W/cm^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

General population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (µW/cm²). The general population exposure limits for the 850 MHz Band is approximately 567 μW/cm². The general population exposure limit for the 1900 MHz (PCS) and 2500 MHz (BRS) bands is 1000 μW/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed SPRINT Wireless antenna facility located at 434 Boston Post Road, Milford, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since SPRINT is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 1 CDMA channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 2) 2 LTE channels (850 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.
- 3) 5 CDMA channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 16 Watts per Channel.
- 4) 2 LTE channels (1900 MHz (PCS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 5) 8 LTE channels (2500 MHz (BRS)) were considered for each sector of the proposed installation. These Channels have a transmit power of 20 Watts per Channel.



- 6) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 7) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 8) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the Commscope DT465B-2XR for transmission in the 850 MHz, 1900 MHz (PCS) and 2500 MHz (BRS) frequency bands. This is based on feedback from the carrier with regards to anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 9) The antenna mounting height centerlines of the proposed antennas are 100 feet above ground level (AGL) for Sector A, 100 feet above ground level (AGL) for Sector B and 100 feet above ground level (AGL) for Sector C.
- 10) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculations were done with respect to uncontrolled / general population threshold limits.

Fax: (781) 273.3311



SPRINT Site Inventory and Power Data by Antenna

Sector:	Α	Sector:	В	Sector:	c
Antenna #:	1	Antenna#:	1	Antenna #:	1
Make/Model:	RFS APXVSPP18-C-A20	Make / Model:	RFS APXVSPP18-C-A20	Make / Model	RFS APXVSPP18-C-A20
Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd	Gain:	13.4 / 15.9 dBd
Height (AGL):	100 feet	Height (AGL):	100 feet	Height (AGL):	100 feet
Frequency-Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)	Frequency Bands	850 MHz / 1900 MHz (PCS)
Channel Count	10	Channel Count	10	Channel Count	10
Total TX Power(W)	220 Watts	Total TX Power(W):	220 Watts	Total TX Power(W):	220 Watts
ERP (W):	7,537.38	ERP(W):	7,537.38	ERP (W):	7,537.38
Antenna A l MPE%	3.48 %	Antenna B1 MPE%	3.478%	Antenna CI MPE%	3.48 %
Antenna #:	2	Antenna #:	2	Antenna#:	2
Make / Model	Commscope DT465B-2XR	Make / Model:	Commscope DT465B-2XR	Make / Model	Commscope DT465B-2XR
Gain:	15.05 dBd	Gain:	15.05 dBd	Gain:	15.05 dBd
Height (AGL):	100 feet	Height (AGL):	100 feet	Height (AGL):	100 feet
Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)	Frequency Bands	2500 MHz (BRS)
Channel Count	8	Channel Count	8	Channel Count	8
Total TX Power(W):	160 Watts	Total TX Power(W)	160 Watts	Total TX Power(W):	160 Watts
ERP (W):	5,118.23	ERP (W):	5,118.23	ERP (W):	5,118.23
Antenna A2 MPE%	2.08 %	Antenna B2 MPE%	2.08 %	Antenna C2 MPE%	2.08 %

Site Composite MPE%				
Carrier	MPE%			
SPRINT - Max per sector	5.56 %			
Town Antennas	0.30 %			
T-Mobile	1.53 %			
MetroPCS	1.96 %			
XM Satellite Radio	2.85 %			
Verizon Wireless	5.73 %			
AT&T	1.53 %			
Site Total MPE %:	19.46 %			

SPRINT Sector A Total:	5.56 %
SPRINT Sector B Total:	
	5.56 %
SPRINT Sector C Total:	5.56 %
	and the state of t
Site Total:	19.46 %

SPRINT Frequency Band / Technology (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (μW/cm²)	Frequency (MHz)	Allowable MPE (μW/cm²)	Calculated % MPE
Sprint 850 MHz CDMA	1	437.55	100	1.78	850 MHz	567	0.31%
Sprint 850 MHz LTE	2	437.55	100	3.56	850 MHz	567	0.63%
Sprint 1900 MHz (PCS) CDMA	5	622.47	100	12.66	1900 MHz (PCS)	1000	1.27%
Sprint 1900 MHz (PCS) LTE	2	1,556.18	100	12.66	1900 MHz (PCS)	1000	1.27%
Sprint 2500 MHz (BRS) LTE	8	639.78	100	20.82	2500 MHz (BRS)	1000	2.08%
		of the and it			新华纪号(1886年) 1886年	Total:	5.56%



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the SPRINT facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

SPRINT Sector	Power Density Value (%)
Sector A:	5.56 %
Sector B:	5.56 %
Sector C:	5.56 %
SPRINT Maximum	5.56 %
Total (per sector):	3.36 76
Site Total:	19.46 %
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **19.46** % of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Fax: (781) 273.3311

Zsamba, Anne Marie (Contractor)

From:

Sent: To:

Subject:


Tracking Updates @ fedex.com

Wednesday, April 25, 2018 9:49 AM Zsamba, Anne Marie (Contractor)

FedEx Shipment 772067964060 Delivered


Your package has been delivered

Tracking # 772067964060



Ship date: Tue, 4/24/2018

Rebecca Alescio Crown Castle Clifton Park, NY 12065 US



Delivery date: Wed, 4/25/2018 9:44 am David Sulkis, City Planner City of Milford 70 West River Street MILFORD, CT 06460

US

Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number:

772067964060

Status:

Delivered:

04/25/2018 09:44 AM Signed for By:

M.LAFOND

Invoice number:

982896

Reference:

1766.668

Signed for by:

M.LAFOND

Delivery location:

MILFORD, CT

Delivered to:

Receptionist/Front

Desk

Service type:

FedEx Priority

Overnight

Packaging type:

FedEx Pak

Number of pieces:

1

Weight:

1.00 lb.

Special

Adult Signature

handling/Services:

Required

Deliver Weekday

Standard transit:

4/25/2018 by

10:30 am


Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 8:49 AM CDT on 04/25/2018.

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above. Standard transit is the date and time the package is scheduled to be delivered by, based on the selected service, destination and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our <u>privacy policy</u>. All rights reserved.

Thank you for your business.



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.

2. Fold the printed page along the horizontal line.

3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com.FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery,misdelivery,or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim.Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental,consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss.Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

Zsamba, Anne Marie (Contractor)

From:

Sent:

To:

Subject:

TrackingUpdates@fedex.com

Wednesday, April 25, 2018 9:53 AM Zsamba, Anne Marie (Contractor)

FedEx Shipment 772067954070 Delivered

Your package has been delivered

Tracking # 772067954070

Ship date: Tue, 4/24/2018

Rebecca Alescio Crown Castle

US

Clifton Park, NY 12065



Delivery date: Wed. 4/25/2018

9:49 am

Mr. Benjamin G. Blake, Mayor

City of Milford 110 River

Street MILFORD, CT 06460

US

Shipment Facts

Our records indicate that the following package has been delivered.

Tracking number:

772067954070

Status:

Delivered:

04/25/2018 09:49 AM Signed for By:

L.DICOCCO

Invoice number:

982896

Reference:

1766.668

Signed for by:

L.DICOCCO

Delivery location:

MILFORD, CT

Delivered to:

Receptionist/Front

Desk

Service type:

FedEx Priority

Overnight

Packaging type:

FedEx Pak

Number of pieces:

Weight:

1.00 lb.

1

Special

Adult Signature

handling/Services:

Required

Deliver Weekday

Standard transit:

4/25/2018 by

10:30 am


Please do not respond to this message. This email was sent from an unattended mailbox. This report was generated at approximately 8:53 AM CDT on 04/25/2018

All weights are estimated.

To track the latest status of your shipment, click on the tracking number above. Standard transit is the date and time the package is scheduled to be delivered by, based on the selected service, destination and ship date. Limitations and exceptions may apply. Please see the FedEx Service Guide for terms and conditions of service, including the FedEx Money-Back Guarantee, or contact your FedEx Customer Support representative.

© 2018 Federal Express Corporation. The content of this message is protected by copyright and trademark laws under U.S. and international law. Review our <u>privacy policy</u>. All rights reserved.

Thank you for your business.



After printing this label:


1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.

2. Fold the printed page along the horizontal line.

3. Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com.FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery,misdelivery,or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim.Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental,consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss.Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.



After printing this label:

1. Use the 'Print' button on this page to print your label to your laser or inkjet printer.

2. Fold the printed page along the horizontal line.

Warning: Use only the printed original label for shipping. Using a photocopy of this label for shipping purposes is fraudulent and could result in additional billing charges, along with the cancellation of your FedEx account number.

Use of this system constitutes your agreement to the service conditions in the current FedEx Service Guide, available on fedex.com.FedEx will not be responsible for any claim in excess of \$100 per package, whether the result of loss, damage, delay, non-delivery, misdelivery, or misinformation, unless you declare a higher value, pay an additional charge, document your actual loss and file a timely claim.Limitations found in the current FedEx Service Guide apply. Your right to recover from FedEx for any loss, including intrinsic value of the package, loss of sales, income interest, profit, attorney's fees, costs, and other forms of damage whether direct, incidental, consequential, or special is limited to the greater of \$100 or the authorized declared value. Recovery cannot exceed actual documented loss.Maximum for items of extraordinary value is \$1,000, e.g. jewelry, precious metals, negotiable instruments and other items listed in our ServiceGuide. Written claims must be filed within strict time limits, see current FedEx Service Guide.

^{3.} Place label in shipping pouch and affix it to your shipment so that the barcode portion of the label can be read and scanned.