

280 Trumbull Street  
Hartford, CT 06103-3597  
Main (860) 275-8200  
Fax (860) 275-8299  
kbaldwin@rc.com  
Direct (860) 275-8345

ORIGINAL

June 8, 2012

RECEIVED  
JUN 11 2012

CONNECTICUT  
SITING COUNCIL

David Martin  
Siting Analyst  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051

Re: **EM-VER-085-120227A – Cellco Partnership d/b/a Verizon Wireless  
500 Moose Hill Road, Monroe, Connecticut**

Dear Mr. Martin:

On March 16, 2012, the Siting Council acknowledged receipt of Cellco's notice of intent to modify its telecommunications facility at 500 Moose Hill Road in Monroe. The modification involved the replacement of Cellco's existing antennas and the installation of six cable diplexers.

As a condition of this acknowledgement, Cellco was required to provide the Council with a letter stating that the recommendations specified in the structural report were implemented. Attached is a Tower Modification Certification Letter verifying that this condition has been satisfied. All construction associated with these modifications has now been completed.

If you have any questions please do not hesitate to contact me or Rachel Mayo.

Sincerely,



Kenneth C. Baldwin

Attachment  
Copy to: Sandy M. Carter  
Brian Ragozzine  
Mark Gauger



Law Offices

BOSTON

PROVIDENCE

HARTFORD

NEW LONDON

STAMFORD

WHITE PLAINS

NEW YORK CITY

ALBANY

SARASOTA

www.rc.com

Centered on Solutions<sup>SM</sup>

May 23, 2012

**Mr. Mark Gauger**  
Verizon Wireless  
99 East River Drive  
East Hartford, Connecticut 06108

**Re: Existing Telecommunications Facility Tower Modification Certification Letter**

**Project:** Verizon ~ Monroe East  
500 Moose Hill Road  
Monroe, CT

**Tower Owner:** SBA Communications Corporation  
5900 Broken Sound Parkway NW  
Boca Raton, Florida 33487

**Engineer:** FDH Engineering  
2730 Rowland Ave Raleigh, NC 27615

**Contractor:** Construction Services of Branford  
63-3 North Branford Road Branford, CT 06405

**Centek Project No.:** 12005.CO5

Dear Mr. Gauger,


We are providing this "Existing Telecommunications Facility Tower Modification Certification Letter" with regard to the antenna upgrade by Verizon Wireless at the above referenced project.

The following are the basis for substantiating compliance with the design documents prepared by FDH Engineering:

- Review of the FDH structural analysis dated 1/11/2012.
- Field observations by Centek personnel of coax installation on 5/23/2012 which determined all coax lines and diplexers were installed according to the recommendations of the structural analysis report prepared by FDH on 1/11/2012.

The work under this Contract has been reviewed and found, to the Engineer's best knowledge, information and belief, to be completed in general compliance with the documents referenced above.

Sincerely,



Carlo F. Centore, PE  
Principal ~ Structural Engineer



CC: Rachel Mayo, Tim Parks, Aleksey Tyurin



# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

[www.ct.gov/csc](http://www.ct.gov/csc)

March 16, 2012

Kenneth C. Baldwin, Esq.  
Robinson & Cole LLP  
280 Trumbull Street  
Hartford, CT 06103

RE: **EM-VER-085-120227A** - Cellco Partnership d/b/a Verizon Wireless notice of intent to modify an existing telecommunications facility located at 500 Moose Hill Road, Monroe, Connecticut.

Dear Attorney Baldwin:

The Connecticut Siting Council (Council) hereby acknowledges your notice to modify this existing telecommunications facility, pursuant to Section 16-50j-73 of the Regulations of Connecticut State Agencies with the following conditions:


- The coax lines and diplexers be installed in accordance with the recommendations made in the Structural Analysis Report prepared by FDH Engineering dated January 11, 2012 and stamped by Christopher Murphy; and
- Following the installation of the proposed equipment, Verizon shall provide documentation certifying that the installation complied with the engineer's recommendation.
- Any deviation from the proposed modification as specified in this notice and supporting materials with Council shall render this acknowledgement invalid;
- Any material changes to this modification as proposed shall require the filing of a new notice with the Council;
- Not less than 45 days after completion of construction, the Council shall be notified in writing that construction has been completed;
- The validity of this action shall expire one year from the date of this letter; and
- The applicant may file a request for an extension of time beyond the one year deadline provided that such request is submitted to the Council not less than 60 days prior to the expiration;

The proposed modifications including the placement of all necessary equipment and shelters within the tower compound are to be implemented as specified here and in your notice dated February 21, 2012. The modifications are in compliance with the exception criteria in Section 16-50j-72 (b) of the Regulations of Connecticut State Agencies as changes to an existing facility site that would not increase tower height, extend the boundaries of the tower site, increase noise levels at the tower site boundary by six decibels, and increase the total radio frequencies electromagnetic radiation power density measured at

the tower site boundary to or above the standard adopted by the State Department of Environmental Protection pursuant to General Statutes § 22a-162. This facility has also been carefully modeled to ensure that radio frequency emissions are conservatively below State and federal standards applicable to the frequencies now used on this tower.

This decision is under the exclusive jurisdiction of the Council. Please be advised that the validity of this action shall expire one year from the date of this letter. Any additional change to this facility will require explicit notice to this agency pursuant to Regulations of Connecticut State Agencies Section 16-50j-73. Such notice shall include all relevant information regarding the proposed change with cumulative worst-case modeling of radio frequency exposure at the closest point of uncontrolled access to the tower base, consistent with Federal Communications Commission, Office of Engineering and Technology, Bulletin 65. Thank you for your attention and cooperation.

Very truly yours,



Linda Roberts  
Executive Director

LR/CDM/laf

c: The Honorable Stephen Vavrek, First Selectman, Town of Monroe  
David Killeen, Planning Administrator, Town of Monroe  
Hollis Redding, SBA



# STATE OF CONNECTICUT

## CONNECTICUT SITING COUNCIL

Ten Franklin Square, New Britain, CT 06051

Phone: (860) 827-2935 Fax: (860) 827-2950

E-Mail: [siting.council@ct.gov](mailto:siting.council@ct.gov)

[www.ct.gov/csc](http://www.ct.gov/csc)

February 28, 2012

The Honorable Stephen Vavrek  
First Selectman  
Town of Monroe  
Town Hall  
7 Fan Hill Road  
Monroe, CT 06468-1800

RE: **EM-VER-085-120227A** - Cellco Partnership d/b/a Verizon Wireless notice of intent to modify an existing telecommunications facility located at 500 Moose Hill Road, Monroe, Connecticut.

Dear First Selectman Vavrek:

The Connecticut Siting Council (Council) received this request to modify an existing telecommunications facility, pursuant to Regulations of Connecticut State Agencies Section 16-50j-72.

If you have any questions or comments regarding this proposal, please call me or inform the Council by March 13, 2012.

Thank you for your cooperation and consideration.

Very truly yours,

Linda Roberts  
Executive Director

LR/jbw


Enclosure: Notice of Intent

c: David Killeen, Town of Monroe

280 Trumbull Street  
Hartford, CT 06103-3597  
Main (860) 275-8200  
Fax (860) 275-8299  
kbaldwin@rc.com  
Direct (860) 275-8345

February 21, 2012

Linda Roberts  
Executive Director  
Connecticut Siting Council  
10 Franklin Square  
New Britain, CT 06051



Re: **Notice of Exempt Modification – Antenna Swap**  
**500 Moose Hill Road, Monroe, Connecticut**

Dear Ms. Roberts:

Cellco Partnership d/b/a Verizon Wireless (“Cellco”) currently maintains twelve (12) wireless telecommunications antennas at the 99-foot level on the existing 150-foot tower at the above-referenced address. The tower is owned by SBA. The Council approved Cellco’s use of the tower in 2005. Cellco now intends to modify its installation by replacing all of its existing antennas with four (4) model APL866513-42T0 cellular antennas; two (2) model LPA-80063-6CF cellular antennas; two (2) model BXA-171063-8BF PCS antennas; one (1) model BXA-171063-12BF PCS antenna; one (1) model BXA-70063-6CF LTE antenna; one (1) model SLCP 2X6014 LTE antenna; and one (1) model BXA-70063-4CF LTE antenna, all at the same 99-foot level on the tower. Cellco also intends to install six (6) coax cable diplexers directly behind its antennas. Attached behind Tab 1 are the specifications for the replacement antennas and cable diplexers.



*Law Offices*

BOSTON

PROVIDENCE

HARTFORD

NEW LONDON

STAMFORD

WHITE PLAINS

NEW YORK CITY

ALBANY

SARASOTA

www.rc.com

Please accept this letter as notification pursuant to R.C.S.A. § 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In accordance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Steve Vavrek, First Selectman of the Town of Monroe. A copy of this letter is also being sent to St. John The Baptist Greek Catholic Cemetery Association, Inc., the owners of the property on which the tower is located.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. § 16-50j-72(b)(2).

# ROBINSON & COLE<sup>LLP</sup>


Linda Roberts  
February 21, 2012  
Page 2

1. The proposed modifications will not result in an increase in the overall height of the existing tower. Cellco's replacement antennas and diplexers will be located at the 99-foot level on the 150-foot tower.
2. The proposed modifications do not involve any change to ground-mounted equipment and, therefore, will not require the extension of the site boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.
4. The operation of the replacement antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative power density table for Cellco's modified facility is included behind Tab 2.

Also attached is a Structural Analysis confirming that the tower and foundation can support Cellco's proposed modifications. (See Tab 3). Consistent with the recommendation #1 on page 3 of the Structural Analysis, Cellco's existing coax cables are currently attached to the exterior of the monopole and are "double stacked". No coax cable changes are proposed as a part of this filing.

For the foregoing reasons, Cellco respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2).

Sincerely,



Kenneth C. Baldwin

Enclosures

Copy to:

Steve Vavrek, Monroe First Selectman  
St. John The Baptist Greek Catholic Cemetery Association, Inc.  
Sandy M. Carter






Maximizer® Log Periodic Antenna, 806-894, 65deg, 15.1dBi, 1.2m, FET, 0deg

**Product Description**

The Celwave® Maximizer series is a log periodic dipole array which uses a patented design to achieve a front-to-back ratio of 45 dB, the highest front-to-back ratio in the industry. Maximizers are available to cover ESMR, AMPS, PCS and DCS frequency ranges. They use RFS's patented monolithic CELLite® technology, which eliminates cable and soldered joints to reduce the possibility of inter-modulation products. The CELLite technology assures high reliability and excellent repeatability of electrical characteristics. The cellular Maximizers are available in 65°, 80° and 90° horizontal beamwidths and the PCS/DCS Maximizers are available in 65° and 90° horizontal beamwidths. Patent number 6,133,889.

**Features/Benefits**

- 45 dB front-to-back ratio reduces co-channel interference.
- Monolithic construction reduces IM.
- No solder joints, high reliability.
- Surface treated components prevent galvanic corrosion.
- UV stabilized radome assures long life without radome deterioration due to UV exposure.



FRONT

BACK

**Technical Specifications**

**Electrical Specifications**


Frequency Range, MHz	806-894
Horizontal Beamwidth, deg	65
Vertical Beamwidth, deg	15
Electrical Downtilt, deg	0
Gain, dBi (dBd)	15.1 (13)
1st Upper Sidelobe Suppression, dB	>20
Upper Sidelobe Suppression, dB	>20
Front-To-Back Ratio, dB	45
Polarization	Vertical
VSWR	< 1.5:1
Impedance, Ohms	50
Maximum Power Input, W	500
Lightning Protection	Direct Ground

**Mechanical Specifications**


Dimensions - HxWxD, mm (in)	1219 x 234 x 203 (48 x 9.2 x 8)
Weight w/o Mtg Hardware, kg (lb)	7 (15.7)
Shipping Weight, kg (lb)	9.1 (20)
Packing Dimensions, HxWxD, mm (in)	1594 x 343 x 349 (62.75 x 13.5 x 13.75)

**Ordering Information**

Mounting Hardware	APM21-3
-------------------	---------



Vertical Pattern



Horizontal Pattern

**Other Documentation**

All information contained in the present datasheet is subject to confirmation at time of ordering



# LPA-80063-6CF-EDIN-X


V-Pol | Log Periodic | 63° | 14.5 dBd

Replace "X" with desired electrical downtilt.

Antenna is also available with NE connector(s). Replace "EDIN" with "NE" in the model number when ordering.



Electrical Characteristics		
Frequency bands	806-960 MHz	
Polarization	Vertical	
Horizontal beamwidth	63°	
Vertical beamwidth	10°	
Gain	14.5 dBd (16.6 dBi)	
Electrical downtilt (X)	0, 2, 4, 5, 6, 8, 10	
Impedance	50Ω	
VSWR	≤1.4:1	
Null fill	5% (-26.02 dB)	
Input power	500 W	
Lightning protection	Direct Ground	
Connector(s)	1 Port / EDIN or NE / Female / Center (Back)	
Mechanical Characteristics		
Dimensions Length x Width x Depth	1805 x 385 x 332 mm      71.1 x 15.2 x 13.1 in	
Depth of antenna with z-bracket	372 mm      14.6 in	
Weight without mounting brackets	12.3 kg      27 lbs	
Survival wind speed	> 201 km/hr      > 125 mph	
Wind area	Front: 0.70 m <sup>2</sup> Side: 0.59 m <sup>2</sup> Front: 7.5 ft <sup>2</sup> Side: 6.3 ft <sup>2</sup>	
Wind load @ 161 km/hr (100 mph)	Front: 885 N    Side: 757 N      Front: 199 lbf    Side: 170 lbf	
Mounting Options		
	Part Number      Fits Pipe Diameter      Weight	
3-Point Mounting & Downtilt Bracket Kit (0-20°)	21700000      50-102 mm    2.0-4.0 in      11 kg    25 lbs	
Lock-Down Brace	If the lock-down brace is used, the maximum diameter of the mounting pipe is 88.9 mm or 3.5 in.	




Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

## BXA-171063-8BF-EDIN-X


Replace "X" with desired electrical downtilt.

X-Pol | FET Panel | 63° | 17.4 dBi




Electrical Characteristics	1710-2170 MHz		
Frequency bands	1710-1880 MHz	1850-1990 MHz	1920-2170 MHz
Polarization	±45°	±45°	±45°
Horizontal beamwidth	68°	65°	60°
Vertical beamwidth	7°	7°	7°
Gain	14.5 dBd / 16.6 dBi	14.9 dBd / 17.0 dBi	15.3 dBd / 17.4 dBi
Electrical downtilt (X)	0, 2, 4, 8		
Impedance	50Ω		
VSWR	≤1.5:1		
First upper sidelobe	< -17 dB		
Front-to-back isolation	> 30 dB		
In-band isolation	> 28 dB		
IM3 (20W carrier)	< -150 dBc		
Input power	300 W		
Lightning protection	Direct Ground		
Connector(s)	2 Ports / EDIN / Female / Bottom		
Operating temperature	-40° to +60° C / -40° to +140° F		
Mechanical Characteristics			
Dimensions Length x Width x Depth	1232 x 154 x 105 mm	48.5 x 6.1 x 4.1 in	
Depth with t-brackets	133 mm	5.2 in	
Weight without mounting brackets	4.8 kg	10.5 lbs	
Survival wind speed	296 km/hr	184 mph	
Wind area	Front: 0.19 m <sup>2</sup> Side: 0.14 m <sup>2</sup>	Front: 2.0 ft <sup>2</sup>	Side: 1.5 ft <sup>2</sup>
Wind load @ 161 km/hr (100 mph)	Front: 281 N Side: 223 N	Front: 63 lbf	Side: 50 lbf
Mounting Options	Part Number	Fits Pipe Diameter	Weight
2-Point Mounting Bracket Kit	26799997	50-102 mm 2.0-4.0 in	2.3 kg 5 lbs
2-Point Mounting & Downtilt Bracket Kit	26799999	50-102 mm 2.0-4.0 in	3.6 kg 8 lbs
Concealment Configurations	For concealment configurations, order BXA-171063-8BF-EDIN-X-FP		

**BXA-171063-8BF-EDIN-X**




Horizontal | 1710-1880 MHz  
**BXA-171063-8BF-EDIN-0**




0° | Vertical | 1710-1880 MHz

**BXA-171063-8BF-EDIN-X**




Horizontal | 1850-1990 MHz  
**BXA-171063-8BF-EDIN-0**




0° | Vertical | 1850-1990 MHz

**BXA-171063-8BF-EDIN-X**



Horizontal | 1920-2170 MHz  
**BXA-171063-8BF-EDIN-0**




0° | Vertical | 1920-2170 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

**BXA-171063-8BF-EDIN-X**


X-Pol | FET Panel | 63° | 17.4 dBi

**BXA-171063-8BF-EDIN-2**




2° | Vertical | 1710-1880 MHz

**BXA-171063-8BF-EDIN-4**




4° | Vertical | 1710-1880 MHz

**BXA-171063-8BF-EDIN-8**




8° | Vertical | 1710-1880 MHz

**BXA-171063-8BF-EDIN-2**




2° | Vertical | 1850-1990 MHz

**BXA-171063-8BF-EDIN-4**




4° | Vertical | 1850-1990 MHz

**BXA-171063-8BF-EDIN-8**




8° | Vertical | 1850-1990 MHz

**BXA-171063-8BF-EDIN-2**




2° | Vertical | 1920-2170 MHz

**BXA-171063-8BF-EDIN-4**



4° | Vertical | 1920-2170 MHz

**BXA-171063-8BF-EDIN-8**




8° | Vertical | 1920-2170 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

## BXA-171063-12BF-EDIN-X


Replace "X" with desired electrical downtilt.

X-Pol | FET Panel | 63° | 19.0 dBi




Electrical Characteristics	1710-2170 MHz				
Frequency bands	1710-1880 MHz	1850-1990 MHz	1920-2170 MHz		
Polarization	±45°	±45°	±45°		
Horizontal beamwidth	68°	65°	60°		
Vertical beamwidth	4.5°	4.5°	4.5°		
Gain	16.1 dBd / 18.2 dBi	16.5 dBd / 18.6 dBi	16.9 dBd / 19.0 dBi		
Electrical downtilt (X)	0, 2, 5				
Impedance	50Ω				
VSWR	≤1.5:1				
First upper sidelobe	< -17 dB				
Front-to-back ratio	> 30 dB				
In-band isolation	> 28 dB				
IM3 (20W carrier)	< -150 dBc				
Input power	300 W				
Lightning protection	Direct Ground				
Connector(s)	2 Ports / EDIN / Female / Bottom				
Operating temperature	-40° to +60° C / -40° to +140° F				
Mechanical Characteristics					
Dimensions Length x Width x Depth	1820 x 154 x 105 mm	71.7 x 6.1 x 4.1 in			
Depth with z-brackets	133 mm	5.2 in			
Weight without mounting brackets	6.8 kg	15 lbs			
Survival wind speed	> 201 km/hr				
Wind area	Front: 0.28 m <sup>2</sup> Side: 0.19 m <sup>2</sup>	Front: 3.1 ft <sup>2</sup> Side: 2.1 ft <sup>2</sup>			
Wind load @ 161 km/hr (100 mph)	Front: 460 N Side: 304 N	Front: 103 lbf Side: 68 lbf			
Mounting Options	Part Number	Fits Pipe Diameter		Weight	
2-Point Mounting Bracket Kit	26799997	50-102 mm	2.0-4.0 in	2.3 kg	5 lbs
2-Point Mounting & Downtilt Bracket Kit	26799999	50-102 mm	2.0-4.0 in	3.6 kg	8 lbs
Concealment Configurations	For concealment configurations, order BXA-171063-12BF-EDIN-X-FP				

BXA-171063-12BF-EDIN-X




Horizontal | 1710-1880 MHz  
BXA-171063-12BF-EDIN-0




0° | Vertical | 1710-1880 MHz

BXA-171063-12BF-EDIN-X




Horizontal | 1850-1990 MHz  
BXA-171063-12BF-EDIN-0




0° | Vertical | 1850-1990 MHz

BXA-171063-12BF-EDIN-X



Horizontal | 1920-2170 MHz  
BXA-171063-12BF-EDIN-0




0° | Vertical | 1920-2170 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.


**BXA-171063-12BF-EDIN-X**

X-Pol | FET Panel | 63° | 19.0 dBi

**BXA-171063-12BF-EDIN-2**




2° | Vertical | 1710-1880 MHz  
**BXA-171063-12BF-EDIN-5**




5° | Vertical | 1710-1880 MHz

**BXA-171063-12BF-EDIN-2**




2° | Vertical | 1850-1990 MHz  
**BXA-171063-12BF-EDIN-5**




5° | Vertical | 1850-1990 MHz

**BXA-171063-12BF-EDIN-2**



2° | Vertical | 1920-2170 MHz  
**BXA-171063-12BF-EDIN-5**



5° | Vertical | 1920-2170 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

## BXA-70063-6CF-EDIN-X

X-Pol | FET Panel | 63° | 14.5 dBd


Replace "X" with desired electrical downtilt.

Antenna is also available with NE connector(s). Replace "EDIN" with "NE" in the model number when ordering.




Electrical Characteristics	696-900 MHz		
Frequency bands	696-806 MHz	806-900 MHz	
Polarization	±45°		
Horizontal beamwidth	65°	63°	
Vertical beamwidth	13°	11°	
Gain	14.0 dBd (16.1 dBi)	14.5 dBd (16.6 dBi)	
Electrical downtilt (X)	0, 2, 3, 4, 5, 6, 8, 10		
Impedance	50Ω		
VSWR	≤1.35:1		
Upper sidelobe suppression (0°)	-18.3 dB	-18.2 dB	
Front-to-back ratio (+/-30°)	-33.4 dB	-36.3 dB	
Null fill	5% (-26.02 dB)		
Isolation between ports	< -25 dB		
Input power with EDIN connectors	500 W		
Input power with NE connectors	300 W		
Lightning protection	Direct Ground		
Connector(s)	2 Ports / EDIN or NE / Female / Center (Back)		
Mechanical Characteristics			
Dimensions Length x Width x Depth	1804 x 285 x 132 mm	71.0 x 11.2 x 5.2 in	
Depth with z-brackets	172 mm	6.8 in	
Weight without mounting brackets	7.9 kg	17 lbs	
Survival wind speed	> 201 km/hr	> 125 mph	
Wind area	Front: 0.51 m <sup>2</sup> Side: 0.24 m <sup>2</sup>	Front: 5.5 ft <sup>2</sup> Side: 2.6 ft <sup>2</sup>	
Wind load @ 161 km/hr (100 mph)	Front: 759 N Side: 391 N	Front: 169 lbf Side: 89 lbf	
Mounting Options	Part Number	Fits Pipe Diameter	Weight
3-Point Mounting & Downtilt Bracket Kit	36210008	40-115 mm 1.57-4.5 in	6.9 kg 15.2 lbs
Concealment Configurations	For concealment configurations, order BXA-70063-6CF-EDIN-X-FP		

BXA-70063-6CF-EDIN-X




Horizontal | 750 MHz

BXA-70063-6CF-EDIN-0




0° | Vertical | 750 MHz


BXA-70063-6CF-EDIN-2




2° | Vertical | 750 MHz



Horizontal | 850 MHz



0° | Vertical | 850 MHz




2° | Vertical | 850 MHz

Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

**BXA-70063-6CF-EDIN-X**


X-Pol | FET Panel | 63° | 14.5 dBd

**BXA-70063-6CF-EDIN-3**




3° | Vertical | 750 MHz

**BXA-70063-6CF-EDIN-4**




4° | Vertical | 750 MHz


**BXA-70063-6CF-EDIN-5**




5° | Vertical | 750 MHz



3° | Vertical | 850 MHz




4° | Vertical | 850 MHz




5° | Vertical | 850 MHz

**BXA-70063-6CF-EDIN-6**




6° | Vertical | 750 MHz

**BXA-70063-6CF-EDIN-8**




8° | Vertical | 750 MHz


**BXA-70063-6CF-EDIN-10**




10° | Vertical | 750 MHz



6° | Vertical | 850 MHz



8° | Vertical | 850 MHz



10° | Vertical | 850 MHz


Quoted performance parameters are provided to offer typical or range values only and may vary as a result of normal manufacturing and operational conditions. Extreme operational conditions and/or stress on structural supports is beyond our control. Such conditions may result in damage to this product. Improvements to product may be made without notice.

# SLCP 2x6014

Dual (2x) Circularly Polarized log-periodic antenna

## Features

- ❑ Transmit Diversity Gain
- ❑ Can be configured to combine space & polarization diversity
- ❑ Outstanding performance over the entire band (700 - 800 MHz)
- ❑ Excellent Axial Ratio
- ❑ Optimized for 4G & 3G systems
- ❑ Low intermodulation
- ❑ Improved Side-to-side rejection
- ❑ Fading reduction
- ❑ Excellent isolation between ports



## Electrical specifications

Frequency range:	<b>700-800 MHz</b>
Impedance:	<b>50 ohm</b>
Connector type:	<b>7/16 Din</b>
Return loss:	<b>18 dB</b>
Polarization:	<b>Circular</b>
Gain ea. port [Circular]:	<b>2x14 dBdC</b>
Gain ea. port [Linear]:	<b>2x11 dBdL</b>
Axial Ratio:	<b>2 dB</b>
Isolation between ports (TX band):	<b>30 dB</b>
Front-to-back ratio:	<b>30 dB</b>
Intermodulation (2x20W):	<b>IM3 150 dB</b>
	<b>IM5 160 dB</b>
	<b>IM7/9 170 dB</b>
Power rating:	<b>2x 500 W</b>
H-plane (-3 dB point):	<b>2x 55°</b>
V-plane (-3 dB point):	<b>2x 16°</b>
Lightning protection:	<b>DC grounded</b>

## Mechanical specifications

Overall height:	<b>53 in</b>	<b>[1346 mm]</b>
Width:	<b>14 in</b>	<b>[356 mm]</b>
Depth:	<b>11 in</b>	<b>[279 mm]</b>
Weight (excluding brackets):	<b>20 lbs</b>	<b>[9 Kg]</b>
Wind load measured up to:	<b>150 mph</b>	<b>[240 Km/h]</b>
Wind area (side of antenna):	<b>5.15 sq. ft.</b>	<b>[0.48 sq.m]</b>
Lateral thrust at 113 mph/ 180 Km/h (worst case):	<b>263 lbs</b>	<b>[1171 N]</b>

## Materials

Radiating Elements:	<b>Aluminum</b>
Transformer (Power distribution)	<b>Ceramic PCB</b>
Chassis:	<b>Aluminum</b>
Radome:	<b>Grey Fiberglass/PVC</b>
Mounting bolts:	<b>Stainless steel</b>

*The SLCP 2x6014 is made in the U.S.A.*



# Slant $\pm 45^\circ$ Dual Polarized FET Panel $63^\circ$ / 13 dBd 696-900 MHz

## Mechanical specifications

Length	1205 mm	47.4 in
Width	285 mm	11.2 in
Depth	126 mm	5.0 in
Depth with z-bracket	166 mm	6.5 in
Weight <sup>4)</sup>	4.5 kg	9.9 lbs
Wind Area Fore/Aft	0.36 m <sup>2</sup>	3.9 ft <sup>2</sup>
Wind Area Side	0.15 m <sup>2</sup>	1.7 ft <sup>2</sup>
Max Wind Survivability	>201 km/hr	>125 mph
Wind Load @ 100 mph (161 km/hr)		
Fore/Aft	522 N	117 lbf
Side	244 N	55 lbf

Antenna consisting of aluminum alloy with brass feedlines covered by a UV safe fiberglass radome. RoHS compliant.

## Mounting & Downtilting

Mounting hardware attaches to pipe diameter  $\varnothing 50$ -160 mm;  $\varnothing 2.0$ -6.3 in.

Mounting Bracket Kit	36210002
Downtilt Bracket Kit	36114003

## Electrical specifications

Frequency Range	696-900 MHz
Impedance	50 $\Omega$
Connector <sup>3)</sup>	NE or E-DIN Female 2 ports / Center
VSWR <sup>1)</sup>	$\leq 1.4:1$
Polarization	Slant $\pm 45^\circ$
Isolation Between Ports <sup>1)</sup>	< -30 dB
Gain <sup>1)</sup>	13.0 dBd 15.0 dBi
Power Rating <sup>2)</sup>	500 W
Half Power Angle <sup>1)</sup>	
Horizontal Beamwidth	63 $^\circ$
Vertical Beamwidth	15 $^\circ$
Electrical downtilt <sup>5)</sup>	0 $^\circ$
Null fill <sup>1)</sup>	5%
Lightning protection	Direct ground
Patented Dipole Design: U.S. Patent No. 6,608,600 B2	

1) Typical values.

2) Power rating limited by connector only.


3) NE indicates an elongated N connector.  
E-DIN indicates an elongated DIN connector.

4) Antenna weight does not include brackets.


5) Add'l downtilts may be available. Check website for details.

Improvements to mechanical and/or electrical performance of the antenna may be made without notice.

Radiation-pattern<sup>1)</sup>  
750 MHz




Horizontal




Vertical

850 MHz



Horizontal




Vertical

696-900 MHz

## BXA-70063/4CF

When ordering replace "\_\_\_" with connector type.



Featuring our Exclusive  
3T Technology™  
Antenna Design:

- Watercut brass feedline assembly for consistent performance.
- Unique feedline design eliminates the need for conventional solder joints in the signal path.
- A non-collinear system with access to every radiating element for broad bandwidth and superior performance.
- Air as insulation for virtually no internal signal loss.

### Warranty:

This antenna is under a five-year limited warranty for repair or replacement.


Revision Date: 10/27/08



## ShareLite Wideband Diplexer – In-line 698-960 MHz/1710-2200 MHz, DC pass in high frequency path

## Product Description

The ShareLite FD9R6004 Series of diplexers are designed to enable feeder sharing between systems in the 698-960 MHz range and in the 1710-2200 MHz range. The diplexer is equipped with in-line connector placement so it can be installed in the BTS cabinet or at the tower top. This is especially valuable in crowded sites or when the feeders are not easily accessible. Due to its wideband design, the FD9R6004 Series can accommodate many combining solutions between 698-960 MHz and 1710-2200 MHz systems such as LTE 700 MHz, Cellular 800 MHz with PCS, GSM900 with GSM1800, or GSM900 with UMTS. This diplexer features a highly selective filter. It provides a high level of isolation between ports, while keeping the insertion loss on both paths at an extremely low level. The FD9R6004 diplexers are available with various DC pass options, helpful in configurations with or without the Tower Mount Amplifiers installed.



## Features/Benefits

- LTE ready design
- Extremely Low Insertion Loss
- High level of Rejection between bands – Protection against interferences
- Extremely High Power Handling Capability
- Integrated DC block/bypass versions available
- Very compact & small size design – Easy installation and reduced tower load
- In-line long-neck connectors for easy connection & waterproofing
- Exceptional reliability & environmental protection (IP 67)
- Equipped with 1 \* Breathable Vent – Prevent any humidity inside the product
- Mounting hardware for Wall and Pole mount provided (P/N SEM2-1A)
- Grounding already provided through the mounting bracket
- Kit available for easy dual mount

## Technical Specifications

Product Type	Diplexer/Cross Band Coupler
Frequency Range 1, MHz	698-960
Frequency Range 2, MHz	1710-2200
Application	LTE700, GSM900, UMTS, GSM1800, Cellular 800, PCS
Configuration	Sharelite Single diplexer, outdoor, DC pass in the 1710-2170MHz path, with mounting hardware SEM2-1A
Mounting	Wall Mounting: With 4 screws (maximum 6mm diameter); Pole Mounting: With included clamp set 40-110mm (1.57-4.33)
Return Loss All Ports Min/Typ, dB	19/23
Power Handling Continuous, Max, W	1250 at common port; 750 in low frequency path & 500 in high frequency path
Power Handling Peak, Max, W	15000 in low frequency path & 8000 in high frequency path
Impedance, Ohms	50
Insertion Loss, Path 1, dB	0.07 typ.
Insertion Loss, Path 2, dB	0.13 typ.
Rejection Between Bands Min/Typ, dB	58/64@698-960MHz; 60/70@1710-2200MHz
IMP Level at the COM Port, Typ, dBm	-112 @ 2x43
DC Pass in Low Frequency Path	No
DC Pass in High Frequency Path	Yes
Temperature Range, °C (°F)	-40 to +60 (-40 to +140)
Environmental	ETSI 300-019-2-4 Class 4.1E
Ingress Protection	IP 67
Lightning Protection	EN/IEC61000-4-5 Level 4
Connectors	In-line long-neck 7-16-Female
Weight, kg (lb)	1.2 (2.6)
Shipping Weight, kg (lb)	3.2 (7) for 2 * single units in 1 * box, 9.8 (21.6) for 6 * units = 3 * Boxes in 1 * overwrap
Dimensions, H x W x D, mm (in)	147 x 164 x 37 (5.8 x 6.5 x 1.5)
Shipping Dimensions, H x W x D, mm (in)	254 x 406 x 82 (10 x 16 x 3.2) for 2 * Single Units in 1 * box, 280 x 406 x 241 (11 x 16 x 9.5) for 6 * units = 3 * Boxes in 1 * overwrap
Volume, L	0.43
Housing	Aluminum

## Notes

All information contained in the present datasheet is subject to confirmation at time of ordering




ShareLite Wideband Diplexer – In-line 698-960 MHz/1710-2200 MHz, DC pass in high frequency path

Other Documentation

FD9R6004/2C-3L Installation Instructions: [Wideband\\_Diplexer\\_Installation\\_Rev5.pdf](#)

Selection Guide Diplexer 698-960 / 1710-2200MHz					
	Model Number	Full DC Pass	DC Pass High Band	DC Pass Low Band	Mounting Hardware Included
Single	FD9R6004/1C-3L				X
	FD9R6004/2C-3L				X
	FD9R6004/3C-3L				X
Dual	KIT-FD9R6004/1C-DL				X
	KIT-FD9R6004/2C-DL				X
	KIT-FD9R6004/3C-DL				X



The FD9R6004 Series is upgradeable to a Dual Diplexer kit by means of 2 diplexers and mounting hardware kits SEM2-1A and SEM2-3

Mounting Hardware and Ground Cable Ordering Information		
Model Number	Description	
SEM2-1A	Mounting Hardware, Pole mount $\phi$ 40-110mm (Included with the Single and Dual Diplexer) Wall Screws M6 (Not included with the product)	
SEM2-3	Assembly kit for 2 pcs of FD9R6004/xC-3L (Can be ordered separately but included with the Dual Diplexer Kit)	
CA020-2	Ground Cable, 2m, includes lugs (Optional)	
CA030-2	Ground Cable, 2m, includes lugs (Optional)	
SEM6	Mounting Hardware for 6 Diplexers, Tower Base (Optional)	

All information contained in the present datasheet is subject to confirmation at time of ordering





FDH Engineering, Inc., 2730 Rowland Rd. Raleigh, NC 27615, Ph. 919.755.1012, Fax 919.755.1031

**Structural Analysis for  
SBA Network Services, Inc.**

**149' Monopole Tower**

**SBA Site Name: Moosehill  
SBA Site ID: CT13056-A  
Verizon Site Name: Monroe East**

**FDH Project Number 12-01211E S1**

**Analysis Results**

Tower Components	86.2%	Sufficient
Foundation	86.6%	Sufficient


Prepared By:

Sean O'Sullivan, EI  
Project Engineer

Reviewed By:

Christopher M Murphy, PE  
President  
CT PE License No. 25842

FDH Engineering, Inc.  
2730 Rowland Rd.  
Raleigh, NC 27615  
(919) 755-1012  
info@fdh-inc.com



January 11, 2012

*Prepared pursuant to TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures*

**TABLE OF CONTENTS**

EXECUTIVE SUMMARY .....3  
    Conclusions .....3  
    Recommendations .....3  
APPURTENANCE LISTING .....4  
RESULTS .....5  
GENERAL COMMENTS .....6  
LIMITATIONS .....6  
APPENDIX .....7

## EXECUTIVE SUMMARY

At the request of SBA Network Services, Inc., FDH Engineering, Inc. performed a structural analysis of the monopole located in Monroe, CT to determine whether the tower is structurally adequate to support both the existing and proposed loads pursuant to the *Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA-222-F*. Information pertaining to the existing/proposed antenna loading, current tower geometry, geotechnical data, and member sizes was obtained from:

- Sabre Communications Corporation (Job No. 02-03107 Revision A) Structural Design Report dated April 3, 2002
- FDH, Inc. (Job No. 08-07121T Revised) TIA Inspection Report dated November 10, 2008
- SBA Network Services, Inc.

The *basic design wind speed* per the *TIA/EIA-222-F* standards is 85 mph without ice and 38 mph with 3/4" radial ice. Ice is considered to increase in thickness with height.

## Conclusions

With the existing and proposed antennas from Verizon in place at 99 ft, the tower meets the requirements of the *TIA/EIA-222-F* standards provided the **Recommendations** listed below are satisfied. Furthermore, provided the foundations were designed and constructed to support the original design reactions (see Sabre Job No. 02-03107 Revision A), the foundation should have the necessary capacity to support both the existing and proposed loading. For a more detailed description of the analysis of the tower, see the **Results** section of this report.

Our structural analysis has been performed assuming all information provided to FDH Engineering, Inc. is accurate (i.e., the steel data, tower layout, existing antenna loading, and proposed antenna loading) and that the tower has been properly erected and maintained per the original design drawings.

## Recommendations

To ensure the requirements of the *TIA/EIA-222-F* standards are met with the existing and proposed loading in place, we have the following recommendations:

1. The existing coax should be installed outside the pole's shaft double-stacked.
2. The proposed diplexers should be installed directly behind the proposed panel antennas.

## APPURTENANCE LISTING

The proposed and existing antennas with their corresponding cables/coax lines are shown in **Table 1**. *If the actual layout determined in the field deviates from the layout, FDH Engineering, Inc. should be contacted to perform a revised analysis.*

**Table 1 - Appurtenance Loading**

### Existing Loading:

Antenna Elevation (ft)	Description	Coax and Lines <sup>1</sup>	Carrier	Mount Elevation (ft)	Mount Type
152.5	(1) Decibel DB404-B Dipole	(1) 7/8"	Town of Monroe	149	(1) Pipe Mount
147 <sup>2</sup>	(6) Decibel 948F85T2E-M (3) Argus LLPX310R (1) Andrew VHLP2-11 Dish (1) Andrew VHLP800-11-DW1 Dish (3) Samsung U-RAS Flexible RRHs	(6) 1-5/8" (6) 5/16" (2) 1/2"	Sprint/ Clearwire	147	(1) 12.5' Low Profile Platform
139	(6) Powerwave 7770 (3) Powerwave P65-16 (6) Powerwave LGP 21401 TMAs (6) Powerwave LGP 13519 Diplexers (6) Ericsson RRUS-11 RRHs (1) Raycap DC6-48-60-18-8F Surge Suppressor	(12) 1-1/4" (1) 0.393" (2) 0.645"	AT&T	139	(1) 13' Low Profile Platform
---	---	---	---	128	(1) 12.5' Low Profile Platform
121	(9) EMS RR90-17-02DP (3) RFS APX16DWV-16DWVS-A20 (6) Powerwave LGP13901 TMAs (3) RFS ATMAA1412D-1A20 TMAs	(18) 1-5/8" (6) 7/8"	T-Mobile	121	(1) 13' Low Profile Platform
109	(12) Decibel DB844H90E-XY	(12) 7/8"	Nextel	109	(1) 14' Low Profile Platform
99 <sup>3</sup>	(6) Antel LPA-80090/4CF (6) Antel LPA-185090/8CF	(12) 1-5/8"	Verizon	99	(1) 12.5' Low Profile Platform
64 <sup>4</sup>	(1) Decibel 260B GPS	(1) 1/2"	Sprint	64	(1) 3' Standoff

1. Coax installed inside the pole's shaft unless otherwise noted.
2. The (6) 1-5/8" coax for Sprint/Clearwire is installed on the outside of the pole's shaft in a single row.
3. The coax for Verizon at 99 ft is installed on the outside of the pole's shaft double stacked.
4. The coax for Sprint at 64 ft is installed on the outside of the pole's shaft.

### Proposed Loading:

Antenna Elevation (ft)	Description	Coax and Lines	Carrier	Mount Elevation (ft)	Mount Type
99	(1) Antel BXA-70063/4CF (1) Swedcom SLCP 2x6014F (2) Antel LPA-80063/6CF (4) Celwave APL866513-42TO (1) Antel BXA-171063/12BF (2) Antel BXA-171063/8BF (1) Antel BXA-70063/6CF (6) RFS FD9R6004/2C-3L Diplexers	(12) 1-5/8"	Verizon	99	(1) 12.5' Low Profile Platform



## RESULTS

The following yield strength of steel for individual members was used for analysis:

**Table 2 - Material Strength**

Member Type	Yield Strength
Tower Shaft Sections	65 ksi
Flange Plate	60 ksi
Flange Bolts	Fu = 120 ksi
Base Plate	60 ksi
Anchor Bolts	75 ksi

**Table 3** displays the summary of the ratio (as a percentage) of force in the member to their capacities. Values greater than 100% indicate locations where the maximum force in the member exceeds its capacity. *Note: Capacities up to 100% are considered acceptable.* **Table 4** displays the maximum foundation reactions.

If the assumptions outlined in this report differ from actual field conditions, FDH Engineering, Inc. should be contacted to perform a revised analysis. Furthermore, as no information pertaining to the allowable twist and sway requirements for the existing or proposed appurtenances was provided, deflection and rotation were not taken into consideration when performing this analysis.

See the **Appendix** for detailed modeling information

**Table 3 - Summary of Working Percentage of Structural Components**

Section No.	Elevation ft	Component Type	Size	% Capacity	Pass Fail
L1	149 - 129	Pole	TP28.82x24x0.1875	24.3	Pass
	129	Flange Bolts	(8) 1" $\phi$ w/ BC = 32.5"	50.1	Pass
	129	Flange Plate	36.25" $\phi$ PL x 1" thk.	47.5	Pass
L2	129 - 96	Pole	TP36.9x28.82x0.25	42.9	Pass
L3	96 - 47.25	Pole	TP48.15x35.237x0.3125	83.8	Pass
L4	47.25 - 0	Pole	TP58.91x46.0768x0.375	86.2	Pass
		Anchor Bolts	(16) 2.25" $\phi$ w/ BC = 66"	83.1	Pass
		Base Plate	64" Square PL x 3" thk.	66.3	Pass

**Table 4 - Maximum Base Reactions**

Base Reactions	Current Analysis (TIA/EIA-222-F)	Original Design (TIA/EIA-222-F)
Axial	43 k	45 k
Shear	35 k	39 k
Moment	3,623 k-ft	4,184 k-ft

## GENERAL COMMENTS

This engineering analysis is based upon the theoretical capacity of the structure. It is not a condition assessment of the tower and its foundation. It is the responsibility of SBA Network Services, Inc. to verify that the tower modeled and analyzed is the correct structure (with accurate antenna loading information) modeled. If there are substantial modifications to be made or the assumptions made in this analysis are not accurate, FDH Engineering, Inc. should be notified immediately to perform a revised analysis.


## LIMITATIONS

All opinions and conclusions are considered accurate to a reasonable degree of engineering certainty based upon the evidence available at the time of this report. All opinions and conclusions are subject to revision based upon receipt of new or additional/updated information. All services are provided exercising a level of care and diligence equivalent to the standard and care of our profession. No other warranty or guarantee, expressed or implied, is offered. Our services are confidential in nature and we will not release this report to any other party without the client's consent. The use of this engineering work is limited to the express purpose for which it was commissioned and it may not be reused, copied, or distributed for any other purpose without the written consent of FDH Engineering, Inc.


## APPENDIX

**DESIGNED APPURTENANCE LOADING**

Section	1	2	3	4
Length (ft)	20.00	33.00	53.50	53.25
Number of Sides	18	18	18	18
Thickness (in)	0.1875	0.2500	0.3125	0.3750
Socket Length (ft)		4.75	6.00	46.0768
Top Dia (in)	24.0000	28.8200	35.2370	58.9100
Bot Dia (in)	28.8200	36.9000	48.1500	
Grade			A572-65	
Weight (K)	1.1	2.9	7.5	11.2



TYPE	ELEVATION	TYPE	ELEVATION
Lightning Rod	149	RFS - APX16DWW-16DWWVS-A20 w/ mount pipe (T-Mobile)	121
Pipe Mount	149	RFS - APX16DWW-16DWWVS-A20 w/ mount pipe (T-Mobile)	121
Decibel - DB404-B Dipole (Town of Monroe)	149	RFS - APX16DWW-16DWWVS-A20 w/ mount pipe (T-Mobile)	121
Pipe Mount (Town of Monroe)	149	RFS - APX16DWW-16DWWVS-A20 w/ mount pipe (T-Mobile)	121
(2) Decibel - 948F85T2E-M w/ mount pipe (Sprint)	147	RFS - ATMAA1412D-1A20 TMA (T-Mobile)	121
(2) Decibel - 948F85T2E-M w/ mount pipe (Sprint)	147	RFS - ATMAA1412D-1A20 TMA (T-Mobile)	121
(2) Decibel - 948F85T2E-M w/ mount pipe (Sprint)	147	RFS - ATMAA1412D-1A20 TMA (T-Mobile)	121
(2) Decibel - 948F85T2E-M w/ mount pipe (Sprint)	147	RFS - ATMAA1412D-1A20 TMA (T-Mobile)	121
Argus LLPX310R w/ Mount Pipe (Sprint)	147	(2) LGP13901 TMA (T-Mobile)	121
Argus LLPX310R w/ Mount Pipe (Sprint)	147	13' Low Profile Platform (T-Mobile)	121
Argus LLPX310R w/ Mount Pipe (Sprint)	147	(3) RR90-17-02DP w/Mount Pipe (T-Mobile)	121
U-RAS Flexible RRH ODU (Sprint)	147	(3) RR90-17-02DP w/Mount Pipe (T-Mobile)	121
U-RAS Flexible RRH ODU (Sprint)	147	(3) RR90-17-02DP w/Mount Pipe (T-Mobile)	121
U-RAS Flexible RRH ODU (Sprint)	147	(2) LGP13901 TMA (T-Mobile)	121
12.5' Low Profile Platform (Sprint)	147	(2) LGP13901 TMA (T-Mobile)	121
VHLP2-11 (Clearwire)	147	(4) DB844H90E-XY w/Mount Pipe (Nextel)	109
VHLP800-11-DW1 (Clearwire)	147	(4) DB844H90E-XY w/Mount Pipe (Nextel)	109
(2) Powerwave - 7770 w/ mount pipe (ATI)	139	14' Low Profile Platform (Nextel)	109
(2) Powerwave - LGP21401 TMAs (ATI)	139	(4) DB844H90E-XY w/Mount Pipe (Nextel)	109
(2) Powerwave - LGP21401 TMAs (ATI)	139	(2) Powerwave - LGP21401 TMAs (ATI)	99
(2) Powerwave - LGP21401 TMAs (ATI)	139	(2) Powerwave - LGP21401 TMAs (ATI)	99
(2) Powerwave - LGP21401 TMAs (ATI)	139	(2) Powerwave - LGP21401 TMAs (ATI)	99
(2) Powerwave - LGP13514 Diplexers (ATI)	139	(2) Powerwave - LGP13514 Diplexers (ATI)	99
(2) Powerwave - LGP13514 Diplexers (ATI)	139	(2) Powerwave - LGP13514 Diplexers (ATI)	99
(2) Powerwave - LGP13514 Diplexers (ATI)	139	(2) Powerwave - LGP13514 Diplexers (ATI)	99
Pipe Mount (ATI)	139	APL866513-42T0 w/ Mount Pipe (Verizon)	99
Pipe Mount (ATI)	139	APL866513-42T0 w/ Mount Pipe (Verizon)	99
Pipe Mount (ATI)	139	APL866513-42T0 w/ Mount Pipe (Verizon)	99
13' Low Profile Platform (ATI)	139	APL866513-42T0 w/ Mount Pipe (Verizon)	99
Powerwave - P65-16 w/ mount pipe (ATI)	139	APL866513-42T0 w/ Mount Pipe (Verizon)	99
Powerwave - P65-16 w/ mount pipe (ATI)	139	Antel BXA-171063/12BF w/ Mount Pipe (Verizon)	99
Powerwave - P65-16 w/ mount pipe (ATI)	139	Antel BXA-171063/12BF w/ Mount Pipe (Verizon)	99
(2) Ericsson RRUS-11 RRH (ATI)	139	BXA-171063/8BF w/ Mount Pipe (Verizon)	99
(2) Ericsson RRUS-11 (ATI)	139	BXA-171063/8BF w/ Mount Pipe (Verizon)	99
(2) Ericsson RRUS-11 (ATI)	139	BXA-171063/8BF w/ Mount Pipe (Verizon)	99
Raycap - DC6-48-60-18-8F Surge Protection (ATI)	139	BXA-171063/8BF w/ Mount Pipe (Verizon)	99
(2) Powerwave - 7770 w/ mount pipe (ATI)	139	BXA-171063/8BF w/ Mount Pipe (Verizon)	99
(2) Powerwave - 7770 w/ mount pipe (ATI)	139	(2) FD9R6004/2C-3L Diplexer (Verizon)	99
(2) Powerwave - 7770 w/ mount pipe (ATI)	139	(2) FD9R6004/2C-3L Diplexer (Verizon)	99
(4) Pipe Mount	128	(2) FD9R6004/2C-3L Diplexer (Verizon)	99
(4) Pipe Mount	128	(2) FD9R6004/2C-3L Diplexer (Verizon)	99
(4) Pipe Mount	128	3' Standoff	64
12.5' Low Profile Platform	128	Decibel - 26OB GPS	64



**MATERIAL STRENGTH**

GRADE	Fy	Fu	GRADE	Fy	Fu
A572-65	65 ksi	80 ksi			

**TOWER DESIGN NOTES**

1. Tower is located in Fairfield County, Connecticut.
2. Tower designed for a 85 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 0.75 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 86.2%

<p>Tower Analysis</p>	<p><b>FDH Engineering, Inc.</b></p> <p>2730 Rowland Road Raleigh, NC 27615 Phone: (919) 755-1012 FAX: (919) 755-1031</p>	<p>Job: <b>Moosehill, CT13056-A</b></p> <p>Project: <b>12-01211E S1</b></p>
	<p>Client: SBA Network</p> <p>Code: TIA/EIA-222-F</p> <p>Path:</p>	<p>Drawn by: Sean O'Sullivan</p> <p>Date: 01/11/12</p> <p>Scale: NTS</p> <p>Dwg No. E-1</p>
	<p>App'd:</p>	
	<p>Scale: NTS</p>	
	<p>Dwg No. E-1</p>	