

PROJECT NARRATIVE

October 25, 2021

Melanie A. Bachman
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Re: Request of DISH Wireless LLC for an Order to Approve the Shared Use of an Existing Tower
20 Antolini Road New Hartford, CT 06057
Latitude: 41°49'41.02" / Longitude: -73°00'56.46"

Dear Ms. Bachman:

Pursuant to Connecticut General Statutes ("C.G.S.") §16-50aa, as amended, DISH Wireless LLC ("DISH") hereby requests an order from the Connecticut Siting Council ("Council") to approve the shared use by DISH of an existing telecommunication tower at 20 Antolini Road in New Hartford (the "Property"). The existing 151-foot monopole tower is owned by American Tower Corporation ("ATC"). The underlying property is owned by the South End Fire District. DISH requests that the Council find that the proposed shared use of the ATC tower satisfies the criteria of C.G.S. §16-50aa and issue an order approving the proposed shared use. A copy of this filing is being sent to Daniel V. Jerram, First Selectman for the Town of New Hartford, Jerry Monroe, Town of New Hartford Building Official & the South End Fire District as the property owner.

Background

The existing ATC facility consists of a 151-foot monopole tower located within an existing leased area. The SD Fire Department currently maintains antennas at the 160-foot level and 155-foot level. Sprint/Nextel currently maintains antennas at the 151-foot level and 52-foot level. Verizon Wireless currently maintains antennas at the 142-foot level. T-Mobile currently maintains antennas at the 125-foot level. AT&T Mobility currently maintains antennas at the 82-foot level. Equipment associated with these antennas are located at various positions within the tower and compound.

DISH is licensed by the Federal Communications Commission ("FCC") to provide wireless services throughout the State of Connecticut. DISH and Crown Castle have agreed to the proposed shared use of the 20 Antolini Road tower pursuant to mutually acceptable terms and conditions. Likewise, DISH and ATC have agreed to the proposed installation of equipment cabinets on the ground on the south side of the tower within the existing compound. ATC has authorized DISH to apply for all necessary permits and approvals that may be required to share the existing tower.
(See attached Letter of Authorization)

DISH proposes to install three (3) antennas, (1) Tower platform mount, (6) Remote radio units at the 114-foot level along with, (1) over voltage protection device (OVP) and (1) Hybrid cable. DISH will install an equipment cabinet on a 5'x7' equipment platform. DISH's Construction Drawings provide project specifications for all proposed site improvement locations.

The construction drawings also include specifications for DISH's proposed antenna and groundwork.

C.G.S. § 16-50aa(c)(1) provides that, upon written request for approval of a proposed shared use, "if the Council finds that the proposed shared use of the facility is technically, legally, environmentally and economically feasible and meets public safety concerns, the council shall issue an order approving such a shared use." DISH respectfully submits that the shared use of the tower satisfies these criteria.

A. Technical Feasibility. The existing ATC tower is structurally capable of supporting DISH's proposed improvements. The proposed shared use of this tower is, therefore, technically feasible. A Feasibility Structural Analysis Report ("Structural Report") prepared for this project confirms that this tower can support DISH's proposed loading. A copy of the Structural Report has been included in this application.

B. Legal Feasibility. Under C.G.S. § 16-50aa, the Council has been authorized to issue order approving the shared use of an existing tower such as the ATC tower. This authority complements the Council's prior-existing authority under C.G.S. § 16-50p to issue orders approving the construction of new towers that are subject to the Council's jurisdiction. In addition, § 16-50x(a) directs the Council to "give such consideration to the other state laws and municipal regulations as it shall deem appropriate" in ruling on requests for the shared use of existing tower facilities. Under the statutory authority vested in the Council, an order by the Council approving the requested shared use would permit the Applicant to obtain a building permit for the proposed installations.

C. Environmental Feasibility. The proposed shared use of the ATC tower would have a minimal environmental effect for the following reasons:

- 1.** The proposed installation will have no visual impact on the area of the tower. DISH's equipment cabinet would be installed within the existing facility compound. DISH's shared use of this tower therefore will not cause any significant change or alteration in the physical or environmental characteristics of the existing site.
- 2.** Operation of DISH's antennas at this site would not exceed the RF emissions standard adopted by the Federal Communications Commission ("FCC"). Included in the EME report of this filing are the approximation tables that demonstrate that DISH's proposed facility will operate well within the FCC RF emissions safety standards.
- 3.** Under ordinary operating conditions, the proposed installation would not require the use of any water or sanitary facilities and would not generate air emissions or discharges to water bodies or sanitary facilities. After construction is complete the proposed installations would not generate any increased traffic to the ATC facility other than periodic maintenance. The proposed shared use of the ATC tower, would, therefore, have a minimal environmental effect, and is environmentally feasible.

D. **Economic Feasibility.** As previously mentioned, DISH has entered into an agreement with ATC for the shared use of the existing facility subject to mutually agreeable terms. The proposed tower sharing is, therefore, economically feasible.

E. **Public Safety Concerns.** As discussed above, the tower is structurally capable of supporting DISH's full array of three (3) antennas, (1) Tower platform mount, (6) Remote radio units, (1) over voltage protection device (OVP) and (1) Hybrid cable and all related equipment. DISH is not aware of any public safety concerns relative to the proposed sharing of the existing ATC tower

Conclusion

For the reasons discussed above, the proposed shared use of the existing ATC tower at 20 Antolini Road satisfies the criteria stated in C.G.S. §16-50aa and advances the Council's goal of preventing the unnecessary proliferation of towers in Connecticut. The Applicant, therefore, respectfully requests that the Council issue an order approving the proposed shared use.

Sincerely,

David Hoogasian

David Hoogasian
Project Manager

LETTER OF AUTHORIZATION



AMERICAN TOWER®
CORPORATION

LETTER OF AUTHORIZATION
LICENSEE: DISH WIRELESS L.L.C.

I, Margaret Robinson, Senior Counsel for American Tower*, owner/operator of the tower facility located at the address identified above (the "Tower Facility"), do hereby authorize DISH WIRELESS L.L.C., its successors and assigns, and/or its agent, (collectively, the "Licensee") to act as American Tower's non-exclusive agent for the sole purpose of filing and consummating any land-use or building permit application(s) as may be required by the applicable permitting authorities for Licensee's telecommunications' installation.

We understand that this application may be denied, modified or approved with conditions. The above authorization is limited to the acceptance by Licensee only of conditions related to Licensee's installation and any such conditions of approval or modifications will be Licensee's sole responsibility.

*American Tower includes all affiliates and subsidiaries of American Tower Corporation.

Project #	ATC Site #	ATC Site Name	ATC Site Address
13688133	208450	Enfield	1A Ecology Drive, Enfield CT
13700322	209115	Ridgefield 2	320 Old Stagecoach Road, Ridgefield, CT
13688136	209185	Burlington 2	87 Monce Road, Burlington CT
13700320	209271	Brookfield 2	100 Pocono Road, Brookfield CT
13693702	243036	WEST HAVEN & RT 162 CT	668 Jones Hill Road, West Haven CT
13693677	280501	ROXBURY CT	377 Southbury Road, Roxbury CT
13685406	281416	WILLINGTON CT	196 Tolland Turnpike, Willington CT
13709418	281862	BRIDGEWATER CT	111 SECOND HILL RD, Bridgewater CT
13693659	283418	NORTH HAVEN CT	50 Devine Street, North Haven CT
13694329	283419	PINE ORCHARD BRANFORD CT	123 Pine Orchard Road, Branford CT
13694332	283422	SHORT BEACH BRANFORD CT	171 Short Beach Road, Branford CT
13698427	283423	NAUGATUCK CT	880 Andrew Mountain Road, Naugatuck CT
13685464	283563	MANSFIELD CT	343 Daleville Road, Willington CT
13692735	284983	OLD LYME CT	61-1 Buttonball Road, Old Lyme CT
13693120	284984	PAWCATUCK CT	166 Pawcatuck Ave, Pawcatuck CT
13693144	284988	GUILFORD CT	Moose Hill Road, Guilford CT
13694582	302465	Colchester CT 6	355 Route 85, Colchester CT
13683501	302468	Petro Lock	99 Meadow St, Hartford CT
13685427	302469	Bridgeport CT 2	1069 Connecticut Avenue, Bridgeport CT
13683503	302472	Andover-bunker Hill Road	104 Bunker Hill Road, Andover CT
13683507	302473	E H F R - Prestige Park	310 Prestige Park Road, East Hartford CT



AMERICAN TOWER®
CORPORATION

Project #	ATC Site #	ATC Site Name	ATC Site Address
13683510	302474	South Windsor	391 Niederwerfer Road, South Windsor CT
13683513	302483	Brln - Berlin	286 Beckley Road, Berlin CT
13692185	302488	Cntn - Canton	4 Hoffmann Road, Canton CT
13692173	302495	Tolland CT	56 Ruops Road, Tolland CT
13694579	302496	Clch - Colchester	Chestnut Hill Road, Colchester CT
13701212	302501	Plymouth CT 3	297 North Street, Plymouth CT
13685414	302515	SMFR - North	5 High Ridge Park Road, Stamford CT
13702496	302516	Mlfd - Milford	438 Bridgeport Ave, Milford CT
13688395	302518	Newtown CT 3	25 Meridian Ridge Drive, Newton CT
13692174	302529	Vernon CT 6	777 Talcotville Road, Vernon Rockville CT
13693124	311014	NORWICH CT	202 N Wawecus Hill Rd, Norwich CT
13702522	311305	GLFD-GUILFORD REBUILD CT	10 Tanner Marsh Road, Guilford CT
13693127	370623	MONTVILLE CT	139 Sharp Hill Road, Uncasville CT
13681964	370625	Old Saybrook	77 Springbrook Road, Old Saybrook CT
13702535	383660	North Madison Volunteer FD	864 Opening Hill Road, Madison CT
13702538	411180	Good Hill CT	481 GOOD HILL ROAD, Woodbury CT
13693709	411182	Nepaug CT	20 Antolini Road, New Hartford CT
13693131	411183	WATERFORD CT	53 Dayton Rd., Waterford CT
13693135	411184	SALEM CT SQA	399 West Road, Salem CT
13692177	411186	West Granby, CT CT	207 West Granby Road, Granby CT
13692178	411187	Hartford North 2 CT	811 Blue Hills Avenue, Bloomfield CT
13693705	411188	Southbury CT	111 Upper Fishrock Road, Southbury CT
13692179	411256	CANTON CT	14 CANTON SPRINGS ROAD, Canton CT
13681988	411257	Middle Haddam Road-CROWN CT	191 Middle Haddam Rd, Portland CT
13692180	411258	Farmington North 2 CT	199 Town Farm Road, Farmington CT
13692182	411259	CT Collinsville CAC 802816 CT	650 Albany Turnpike, Collinsville CT
13692184	416862	SUFFIELD SW CT CT	106 South Grand St., West Suffield CT
13694578	6260	NORTH STONINGTON CT	118C Wintechog Hill Rd., off of Rt. 2, North Stonington CT
13681397	88013	Killingworth	131 Little City Road, Killingworth CT

Signature:

Print Name: Margaret Robinson
Senior Counsel
American Tower*



AMERICAN TOWER®
CORPORATION

**LETTER OF AUTHORIZATION
LICENSEE: DISH WIRELESS L.L.C.**


NOTARY BLOCK


Commonwealth of MASSACHUSETTS
County of Middlesex

This instrument was acknowledged before me by Margaret Robinson, Senior Counsel for American Tower*, personally known to me (or proved to me on the basis of satisfactory evidence) to be the person whose name is subscribed to the within instrument and acknowledged to me that he executed the same.

WITNESS my hand and official seal, this 10th day of September 2021.

NOTARY SEAL



Notary Public 
My Commission Expires: March 14, 2025

ENGINEERING DRAWINGS



DISH Wireless L.L.C. SITE ID:

BOHVN00005A

DISH Wireless L.L.C. SITE ADDRESS:

**20 ANTOLINI ROAD
NEW HARTFORD, CT 06057**

PROJECT NOTES

THE PROJECT DEPICTED IN THESE PLANS QUALIFIES AS AN ELIGIBLE FACILITIES REQUEST ENTITLED TO EXPEDITED REVIEW UNDER 47 U.S.C. 1455(A) AS A MODIFICATION OF AN EXISTING WIRELESS TOWER THAT INVOLVES THE COLLOCATION REMOVAL AND/OR REPLACEMENT OF TRANSMISSION EQUIPMENT THAT IS NOT A SUBSTANTIAL CHANGE UNDER CFR 1.61000 (B)(7).

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

TOWER SCOPE OF WORK:

- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
- INSTALL (1) PROPOSED TOWER PLATFORM MOUNT
- INSTALL (1) PROPOSED JUMPERS
- INSTALL (6) PROPOSED RRUs (2 PER SECTOR)
- INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP)
- INSTALL (1) PROPOSED HYBRID CABLE

GROUND SCOPE OF WORK:

- INSTALL (1) PROPOSED METAL PLATFORM
- INSTALL (1) PROPOSED ICE BRIDGE
- INSTALL (1) PROPOSED PPC CABINET
- INSTALL (1) PROPOSED EQUIPMENT CABINET
- INSTALL (1) PROPOSED POWER CONDUIT
- INSTALL (1) PROPOSED TELCO CONDUIT
- INSTALL (1) PROPOSED TELCO-FIBER BOX
- INSTALL (1) PROPOSED GPS UNIT
- INSTALL (1) PROPOSED SAFETY SWITCH (IF REQUIRED)
- INSTALL (1) PROPOSED FIBER NID (IF REQUIRED)
- INSTALL (1) PROPOSED METER SOCKET
- INSTALL (1) PROPOSED FIBER HAND HOLE

SITE INFORMATION

PROPERTY OWNER: SOUTH END FIRE DISTRICT
ADDRESS: 20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

TOWER TYPE: MONOPOLE

TOWER CO SITE ID: 411182

TOWER APP NUMBER: 13693709

COUNTY: LITCHFIELD

LATITUDE (NAD 83): 41° 49' 41.02" N
41.828061

LONGITUDE (NAD 83): 73° 0' 56.46" W
-73.015683

ZONING JURISDICTION: LITCHFIELD COUNTY

ZONING DISTRICT: R2

PARCEL NUMBER: 021-007-42B

OCCUPANCY GROUP: U

CONSTRUCTION TYPE: II-B

POWER COMPANY: T.B.D.

TELEPHONE COMPANY: T.B.D.

PROJECT DIRECTORY

APPLICANT: DISH Wireless L.L.C.
5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120
(303) 706-5008


TOWER OWNER: AMERICAN TOWER CORPORATION
10 PRESIDENTIAL WAY
WOBURN, MA 01801
(781) 926-4500

SITE DESIGNER: B+T GROUP
1717 S. BOULDER AVE, SUITE 300
TULSA, OK 74119
(918) 587-4630

SITE ACQUISITION: KENNETH R. BRADBURY II
(781) 926-4770

CONSTRUCTION MANAGER: JAVIER SOTO
javier.soto@dish.com

RF ENGINEER: SYED ZAIDI
syed.zaidi@dish.com




DIRECTIONS

DIRECTIONS FROM BRADLEY INTERNATIONAL AIRPORT:

CONTINUE TO BRADLEY INTERNATIONAL AIRPORT CON, HEAD NORTH TOWARD BRADLEY INTERNATIONAL AIRPORT, SLIGHT LEFT ONTO BRADLEY INTERNATIONAL AIRPORT, SLIGHT LEFT, FOLLOW CT-20 W AND CT-219 S TO ANTOLINI RD IN NEW HARTFORD, CONTINUE ONTO BRADLEY INTERNATIONAL AIRPORT CON, TAKE THE CT-20 W EXIT TOWARD E GRANBY/GRANBY, CONTINUE ONTO CT-20 W, SLIGHT LEFT ONTO CT-20 W/W GRANBY RD CONTINUE TO FOLLOW CT-20 W, TURN LEFT ONTO CT-219 S, TURN LEFT ONTO CT-179 S/CT-219 S CONTINUE TO FOLLOW CT-219 S, SLIGHT RIGHT ONTO CT-318 W, TURN LEFT TOWARD CT-219 S, SLIGHT RIGHT ONTO CT-219 S, CONTINUE STRAIGHT ONTO ANTOLINI RD, DESTINATION WILL BE ON THE LEFT, ARRIVE AT BOHVN00005A.

UNDERGROUND SERVICE ALERT CBYD 811
UTILITY NOTIFICATION CENTER OF CONNECTICUT
(800) 922-4455
WWW.CBYD.COM

CALL 2 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION



GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE, NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.


CONNECTICUT CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

CODE TYPE	CODE
BUILDING	2018 CT STATE BUILDING CODE/2015 IBC W/ CT AMENDMENTS
MECHANICAL	2018 CT STATE BUILDING CODE/2015 IMC W/ CT AMENDMENTS
ELECTRICAL	2018 CT STATE BUILDING CODE/2017 NEC W/ CT AMENDMENTS

SHEET INDEX

SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
LS-1	SITE SURVEY
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PLATFORM AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES



IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM
RFDS REV #:	1.0	

CONSTRUCTION DOCUMENTS

SUBMITTALS

REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
TITLE SHEET

SHEET NUMBER
T-1

PROJECT SUMMARY

FIELD SURVEY DATE: 02/20/16
 SITE ADDRESS: 20 ANTONINI ROAD, NEW HARTFORD, CT

PARCEL INFORMATION
 OWNER: SOUTH END FIRE DISTRICT
 OWNER ADDRESS: 20 ANTONINI ROAD, NEW HARTFORD, CT
 APN: 00247301 MAP 21, BLOCK 7, LOT 42B VOLUME 103, PG. 417

TOTAL AREAS
 PARENT PARCEL: 1.52± ACRES (PER TAX RECORDS)
 ATC LEASE AREA: 6,005 SQ.FT.; 0.138 ACRES

BASIS OF BEARINGS
 BEARINGS ARE BASED ON CONNECTICUT STATE PLANE COORDINATE SYSTEM BY GPS OBSERVATION.

COORDINATES BASED ON CONNECTICUT STATE PLANE COORDINATE SYSTEM.

FLOODPLAIN:
 PER THE FEMA FLOODPLAIN MAPS, THE SITE IS LOCATED IN AN AREA DESIGNATED AS ZONE G.
 COMMUNITY PANEL NO.: 09004800128 DATED: 02/03/1982

ENCROACHMENT STATEMENT:
 COMPOUND FENCE LIES OUTSIDE OF THE 75'X75' ATC LEASE AREA. THIS WOULD BE REMEDIATED BY INCREASING THE SIZE OF THE LEASE AREA AS SHOWN PER THE AS-SURVEYED LEGAL DESCRIPTION SHOWN HEREON.

TOWER INFORMATION:
 LATITUDE: 41° 49' 41.02" N, NAD 83
 LONGITUDE: 73° 07' 56.44" W, NAD 83
 GROUND ELEVATION AT BASE OF TOWER: 744.0' FEET (AMSL) NAVD 1988
 TOP OF TOWER HEIGHT ABOVE GROUND: 150.8' (AGL)
 ELEVATION OF TOP OF TOWER: 894.8' (AMSL) NAVD 1988
 TOP OF LIGHTNING ROD: 169.3'
 ELEVATION OF TOP OF HIGHEST APPURTENANCE: 913.3' (AMSL) NAVD 1988

SURVEYOR'S NOTES

- THERE IS ACCESS TO THE ATC LEASE AREA FROM ANTONINI ROAD.
- THE LOCATIONS OF ALL UTILITIES SHOWN ON THE SURVEY ARE FROM VISIBLE SURFACE EVIDENCE ONLY.
- AT THE TIME OF THIS SURVEY THERE WAS NO OBSERVABLE SURFACE EVIDENCE OF EARTH MOVING WORK, BUILDING CONSTRUCTION OR BUILDING ADDITIONS WITHIN RECENT MONTHS.
- AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVABLE EVIDENCE OF THE SUBJECT PROPERTY BEING USED AS A SOLID WASTE DUMP, SLUMP OR SANITARY LANDFILL.
- AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVABLE EVIDENCE OF ANY RECENT CHANGES IN STREET RIGHT-OF-WAY LINES EITHER COMPLETED OR PROPOSED, AND AVAILABLE FROM THE CONTROLLING JURISDICTION.
- AT THE TIME OF THIS SURVEY, THERE WAS NO OBSERVABLE EVIDENCE OF ANY RECENT STREET OR SIDEWALK CONSTRUCTION OR REPAIRS.
- THIS SURVEY DOES NOT CONSTITUTE A BOUNDARY SURVEY OF THE PARENT TRACT. ANY PARENT TRACT PROPERTY LINES SHOWN HEREON ARE FROM SUPPLIED INFORMATION AND MAY NOT BE FIELD VERIFIED.
- THIS IS A SURVEY OF AN EXISTING ATC LEASE PARCEL WITHIN AN EXISTING PARCEL OF LAND, THE BOUNDARIES OF WHICH HAVE NOT BEEN SURVEYED.
- THERE WAS NO VISIBLE EVIDENCE OF UTILITIES SERVICING THE SITE, THEREFORE UNABLE TO PROVIDE AN AS-SURVEYED UTILITY EASEMENT.
- ALL CALLS ARE MEASURED UNLESS OTHERWISE NOTED.
- UNLESS OTHERWISE SPECIFIED, UTILITY POLES DID NOT IDENTIFY OWNERSHIP.
- THIS SURVEY IS A HORIZONTAL ACCURACY CLASS AA AND A TOPOGRAPHICAL ACCURACY CLASS T-1 AS DEFINED IN SEC. 20-309B-11 OF THE CONNECTICUT STANDARDS FOR SURVEYS.
- THE ATC LEASE AREA LIES WHOLLY WITHIN THE PARENT PARCEL.

ZONING INFORMATION

TOWN OF NEW HARTFORD ZONING, TOWN HALL, SECOND FLOOR
 830 MAIN ST., NEW HARTFORD, CT
 860-378-7977

AT THE TIME OF SURVEY ZONING INFORMATION WAS NOT PROVIDED.

LEGAL DESCRIPTIONS

SCORE REPORT LEGAL DESCRIPTION (PARENT PARCEL - FOR INFORMATION ONLY - NOT SURVEYED):

ALL THAT CERTAIN PIECE OR PARCEL OF LAND SITUATED IN THE TOWN OF NEW HARTFORD, COUNTY OF LITCHFIELD AND STATE OF CONNECTICUT AND MORE PARTICULARLY SHOWN ON A MAP ENTITLED "MAP OF LAND OWNED BY THE TOWN OF NEW HARTFORD TO BE CONVEYED TO SOUTH END FIRE DISTRICT, U.S. ROUTE 202 NEW HARTFORD, CONNECTICUT SCALE 1" = 40' SEPT. 7, 1982, REVISED EAST LINE - AUGUST 1984", WHICH MAP WAS PREPARED BY NASCIMBENI & JAHNE, SURVEYORS, SAID PARCEL CONTAINS 104,166 SQ. FEET (2.39 ACRES).

PARCEL NUMBER: 00247301

ATC LEASE AREA - (AS-SURVEYED)

SITUATED IN THE TOWN OF NEW HARTFORD, COUNTY OF LITCHFIELD AND STATE OF CONNECTICUT, BEING A PORTION OF THAT TRACT OF LAND CONVEYED TO SOUTH END FIRE DISTRICT IN VOLUME 103, PAGE 417, NEW HARTFORD RECORDS AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

THE POINT OF BEGINNING HAVING CONNECTICUT STATE PLANE COORDINATES OF N 862,607.03, E 927,556.19;
 THENCE SOUTH 83°15'13" EAST, A DISTANCE OF 76.50 FEET TO A POINT HAVING COORDINATES N 862,598.214, E 927,630.669;
 THENCE SOUTH 06°44'42" WEST, A DISTANCE OF 78.50 FEET TO A POINT HAVING COORDINATES N 862,520.258, E 927,621.446;
 THENCE NORTH 83°15'13" WEST, A DISTANCE OF 76.50 FEET TO A POINT HAVING COORDINATES N 862,529.244, E 927,545.476;
 THENCE NORTH 06°44'42" EAST, A DISTANCE OF 78.50 FEET TO THE POINT OF BEGINNING.

HAVING AN AREA OF 6,005 SQUARE FEET (0.138 ACRES) OF LAND, MORE OR LESS.



NOTE: AT THE TIME OF SURVEY THERE WERE NO DESCRIPTIONS OF THE LEASE AREA AND/OR ANY EASEMENTS PROVIDED TO THE SURVEYOR.

NOTE: UNABLE TO DEPICT PARENT PARCEL WITHOUT THE MAP REFERENCED IN THE PARENT PARCEL DESCRIPTION (MAP ENTITLED "MAP OF LAND OWNED BY THE TOWN OF NEW HARTFORD TO BE CONVEYED TO SOUTH END FIRE DISTRICT, U.S. ROUTE 202 NEW HARTFORD, CONNECTICUT SCALE 1" = 40' SEPT. 7, 1982, REVISED EAST LINE - AUGUST 1984")

NOTES CORRESPONDING TO SCORE REPORT


THE SCORE REPORT ISSUED BY RELTCO INC. FILE NO. 153432CT, EFFECTIVE DATE OF SEPTEMBER 15, 2016 CONTAINS THE FOLLOWING SURVEY RELATED ITEMS:

- SUBJECT TO NOTICE OF LEASE BETWEEN SOUTH END FIRE DISTRICT, A MUNICIPAL CORPORATION AND LITCHFIELD ACQUISITION CORPORATION D/B/A AT&T WIRELESS CORPORATION, DATED MAY 24, 2001 AND FILED ON JUNE 28, 2001 IN (BOOK) 192, (PAGE) 0101, OF THE OFFICIAL PROPERTY RECORDS OF LITCHFIELD COUNTY, CONNECTICUT.
 AFFECTS ATC LEASE AREA - NO PLOTTABLE MATTERS.
- SUBJECT TO ELECTRIC DISTRIBUTION EASEMENT BETWEEN SOUTH END FIRE DISTRICT AND LITCHFIELD ACQUISITION CORPORATION D/B/A AT&T WIRELESS SERVICES, DATED MAY 2, 2001 AND FILED ON JUNE 28, 2001 IN (BOOK) 192, (PAGE) 0105, OF THE OFFICIAL PROPERTY RECORDS OF LITCHFIELD COUNTY, CONNECTICUT.
 AFFECTS ATC LEASE AREA - NOT PLOTTABLE, REFERENCED EXHIBIT (MAP NO. 1862) IS ILLEGIBLE.
- SUBJECT TO MEMORANDUM OF ASSIGNMENT AND ASSUMPTION AGREEMENT BETWEEN ALL TEL NEWCO LLC, A DELAWARE LIMITED LIABILITY COMPANY, SUCCESSOR IN INTEREST TO LITCHFIELD ACQUISITIONS CORPORATION, D/B/A AT&T WIRELESS SERVICES AND CELCO PARTNERSHIP, A DELAWARE GENERAL PARTNERSHIP, D/B/A VERIZON WIRELESS, DATED MAY 30, 2008 AND FILED ON JULY 10, 2008 IN (BOOK) 255, (PAGE) 150, OF THE OFFICIAL PROPERTY RECORDS OF LITCHFIELD COUNTY, CONNECTICUT.
 AFFECTS ATC LEASE AREA - NO PLOTTABLE MATTERS.
- ALONG WITH MEMORANDUM OF LEASE BETWEEN CELCO PARTNERSHIP, D/B/A VERIZON WIRELESS AND OMNIPPOINT COMMUNICATIONS INC., DATED NOVEMBER 20, 2008 AND FILED ON MARCH 3, 2011 IN (BOOK) 267, (PAGE) 767, OF THE OFFICIAL PROPERTY RECORDS OF LITCHFIELD COUNTY, CONNECTICUT.
 AFFECTS ATC LEASE AREA - NO PLOTTABLE MATTERS.
- SUBJECT TO PARTIAL ASSIGNMENT OF EASEMENT RIGHTS BETWEEN THE CONNECTICUT LIGHT AND POWER COMPANY TO THE SOUTHERN NEW ENGLAND TELEPHONE COMPANY D/B/A AT&T CONNECTICUT, A CONNECTICUT CORPORATION, DATED NOVEMBER 3, 2008 AND FILED ON FEBRUARY 25, 2009 IN (BOOK) 257, (PAGE) 581, OF THE OFFICIAL PROPERTY RECORDS OF LITCHFIELD COUNTY, CONNECTICUT.
 AFFECTS ATC LEASE AREA - NO PLOTTABLE ITEMS.



3 PARENT PARCEL

PENDING UPON RECEIPT OF PARENT PARCEL MAP



AMERICAN TOWER®
ATC TOWER SERVICES, INC.
 3500 REGENCY PARKWAY
 SUITE 100
 CARY, NC 27518
 PHONE: (919) 468-0112
 FAX: (919) 466-5415

THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATION AS INSTRUMENTS OR SERVICE ARE THE EXCLUSIVE PROPERTY OF AMERICAN TOWER. THEIR USE AND PUBLICATION SHALL BE RESTRICTED TO THE ORIGINAL SITE FOR WHICH THEY ARE PREPARED. ANY USE OR DISCLOSURE OTHER THAN THAT WHICH RELATES TO AMERICAN TOWER OR THE SPECIFIED CARRIER IS STRICTLY PROHIBITED. TITLE TO THESE DOCUMENTS SHALL REMAIN THE PROPERTY OF AMERICAN TOWER WHETHER OR NOT THE PROJECT IS EXECUTED. NEITHER THE ARCHITECT NOR THE ENGINEER WILL BE PROVIDING ON-SITE CONSTRUCTION REVIEW OF THIS PROJECT. CONTRACTOR(S) MUST VERIFY ALL DIMENSIONS AND ADVISE AMERICAN TOWER OF ANY DISCREPANCIES. ANY PRIOR ISSUANCE OF THIS DRAWING IS SUPERSEDED BY THE LATEST VERSION ON FILE WITH AMERICAN TOWER.

REV.	DESCRIPTION	BY	DATE
0	PRELIM	LKC	9.29.16
1	GENERAL COMMENTS	LKC	11.21.16

ATC SITE NUMBER:
411182

ATC SITE NAME:
NEPAUG CT

SITE ADDRESS:
 20 ANTONINI ROAD
 NEW HARTFORD, CT 06057

THIS IS TO CERTIFY THAT THE UNDERSIGNED AT THE REQUEST AND FOR THE EXCLUSIVE USE OF AMERICAN TOWER CORPORATION AND RELTCO INC. RESIDENTIAL LENDERS TITLE CO. HAS PERFORMED THIS AS-BUILT SURVEY OF THE ATC LEASE AREA ONLY, FROM THE RECORD SOURCES AND ACTUAL FIELD SURVEY ON SEPTEMBER 22, 2016 IN ACCORDANCE WITH THE MINIMUM STANDARDS FOR PROPERTY BOUNDARY SURVEYS. ALL LINEAR AND ANGULAR VALUES SHOWN ARE BASED UPON DEED OR RECORD INFORMATION UNLESS OTHERWISE NOTED.

DATE OF PLAT OR MAP: SEPTEMBER 29, 2016

PRELIMINARY SURVEY

TIMOTHY R. DURR
 PLS:
 IN THE STATE OF CONNECTICUT

LMS SURVEYING LTD
 P.O. Box 65 Sharon Center, OH 44274
 Phone: 330-239-6812 / Fax: 330-239-1529

DRAWN BY: LKC
 APPROVED BY: TDR
 DATE DRAWN: 9.29.16
 JOB NO: B-160751

AS-BUILT SURVEY

SHEET NUMBER: **V-101** REVISION: **1**

Work Coordinated By:

811

Know what's below.
 Call before you dig.

National Land Survey Consultants
 surveys@coxlevin.com
 781-640-3309 • www.coxlevin.com

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. CONTRACTOR SHALL MAINTAIN A 10'-0" MINIMUM SEPARATION BETWEEN THE PROPOSED GPS UNIT, TRANSMITTING ANTENNAS AND EXISTING GPS UNITS.
3. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER
10 PRESIDENTIAL WAY
WOBURN, MA 01801

B+T GRP
1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
DAS DAS RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS



SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
OVERALL AND ENLARGED
SITE PLAN


SHEET NUMBER
A-1




OVERALL SITE PLAN



1



ENLARGED SITE PLAN



2



NOTE: A BOUNDARY SURVEY OF THE EXISTING EASEMENT WAS NOT AVAILABLE AT CONSTRUCTION DRAWING CREATION. LICENSEE WILL NEED TO OBTAIN A UTILITY EASEMENT AND CONSTRUCTION CONTRACTOR MUST FIELD VERIFY ALL PROPOSED UTILITY ROUTES ARE WITHIN THE OBTAINED EASEMENT.


SURVEY

NO SCALE

3

NOTES


1. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
2. ANTENNA AND MW DISH SPECIFICATIONS REFER TO ANTENNA SCHEDULE AND TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS
3. EXISTING EQUIPMENT AND FENCE OMITTED FOR CLARITY.




(1) PROPOSED DISH WIRELESS L.L.C. HYBRID CABLE ROUTED INSIDE POLE

PROPOSED DISH WIRELESS L.L.C. ICE BRIDGE
 PROPOSED DISH WIRELESS L.L.C. GPS UNIT
 PROPOSED DISH WIRELESS L.L.C. EQUIPMENT ON PROPOSED STEEL PLATFORM


PROPOSED NORTH ELEVATION



1



ANTENNA LAYOUT



2

SECTOR	POSITION	ANTENNA					TRANSMISSION CABLE	
		EXISTING OR PROPOSED	MANUFACTURER - MODEL NUMBER	TECHNOLOGY	SIZE (HxW)	AZIMUTH	RAD CENTER	FEED LINE TYPE AND LENGTH
ALPHA	A1	PROPOSED	JMA WIRELESS-MX08FR0665-21	5G	72.0" x 20.0"	0°	114'-0"	(1) HIGH-CAPACITY HYBRID CABLE (150' LONG)
BETA	B1	PROPOSED	JMA WIRELESS-MX08FR0665-21	5G	72.0" x 20.0"	120°	114'-0"	
GAMMA	C1	PROPOSED	JMA WIRELESS-MX08FR0665-21	5G	72.0" x 20.0"	240°	114'-0"	

SECTOR	POSITION	RRH		NOTES
		MANUFACTURER - MODEL NUMBER	TECHNOLOGY	
ALPHA	A1	FUJITSU - TA08025-B605	5G	1. CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS. 2. ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.
	A1	FUJITSU - TA08025-B604	5G	
BETA	B1	FUJITSU - TA08025-B605	5G	
	B1	FUJITSU - TA08025-B604	5G	
GAMMA	C1	FUJITSU - TA08025-B605	5G	
	C1	FUJITSU - TA08025-B604	5G	

EXISTING OR PROPOSED	OVP	
	MANUFACTURER - MODEL NUMBER	SIZE (HxWxD)
PROPOSED	RAYCAP-RDIDC-9181-PF-48	16"x14"x8"

ANTENNA SCHEDULE

NO SCALE

3



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
DAS DAS RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C. PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
ELEVATION, ANTENNA LAYOUT AND SCHEDULE

SHEET NUMBER
A-2



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
EQUIPMENT PLATFORM AND
H-FRAME DETAILS


SHEET NUMBER
A-3

NOTES

- CONTRACTOR TO BURY PLATFORM FEET WITH A MINIMUM OF 2" OF FILL PER EXISTING SITE SURFACE
- WEED BARRIER FABRIC TO BE ADDED AT DISCRETION OF DISH Wireless L.L.C. CONSTRUCTION MANAGER AT TIME OF CONSTRUCTION. ONE SHEET 8'x8' INSTALLED UNDER ALL FOUR FEET OF THE PLATFORM (4 MIL BLACK PLASTIC)
- EQUIPMENT CABINET OMITTED FOR CLARITY



PLATFORM EQUIPMENT PLAN




1

COMMSCOPE MTC4045LP
5X7 PLATFORM

DIMENSIONS (HxWxD)	16"x84"x60"
TOTAL WEIGHT	423 LBS

NOTE:
GC TO PROVIDE EXTENDED
THREAD FOR PLATFORM IF
REQUIRED HEIGHT EXCEEDS 17"





PLATFORM DETAIL

NO SCALE 2

COMMSCOPE MTC4045HFLD
H-FRAME

UNISTRUT/SUPPORT RAILS QTY	5
WEIGHT	59.74 lbs

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT




H-FRAME DETAIL


NO SCALE 3

NOT USED

NO SCALE 4




FRONT ELEVATION




BACK ELEVATION


H-FRAME EQUIPMENT ELEVATION




5




CABINET DETAIL NO SCALE 1




POWER PROTECTION CABINET (PPC) DETAIL NO SCALE 2




SAFETY SWITCH DETAIL NO SCALE 3




METER SOCKET DETAIL NO SCALE 4




FIBER NID ENCLOSURE DETAIL NO SCALE 5




FIBER TELCO ENCLOSURE DETAIL NO SCALE 6



ICE BRIDGE DETAIL NO SCALE 7



TYPICAL ICE BRIDGE CONCRETE PIER DETAIL NO SCALE 8



HYBRID CABLE RUN NO SCALE 9

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

10 PRESIDENTIAL WAY
WOBURN, MA 01801

1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com

10/17/21

B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM
RFDS REV #:	1.0	

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION

BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-4


PCTEL GPSGL-TMG-SPI-40NCB	
DIMENSIONS (DIAxH) MM/INCH	81x184mm 3.2"x7.25"
WEIGHT W/ACCESSORIES	075 lbs
CONNECTOR	N-FEMALE
FREQUENCY RANGE	1590 ± 30MHz



BACK



TOP




SIDE

GPS DETAIL

NO SCALE


1



GPS MINIMUM SKY VIEW REQUIREMENTS

NO SCALE

2



CABLES UNLIMITED HYBRID CABLE
MINIMUM BEND RADIUSES

NO SCALE

3

NOT USED

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
D	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01





DISH Wireless L.L.C.
PROJECT INFORMATION

BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER
A-5

FUJITSU TRIPLE BAND TA08025-B605	
DIMENSIONS (HxWxD)	14.9"x15.7"x9"
WEIGHT	74.95 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V







BACK

SIDE

FRONT

FUJITSU DUAL BAND TA08025-B604	
DIMENSIONS (HxWxD)	14.9"x15.7"x7.8"
WEIGHT	63.9 lbs
CONNECTOR TYPE	4.3-10 RF CONNECTOR
POWER SUPPLY	DC -58~-36V





BACK

SIDE

FRONT

SABRE DOUBLE Z-BRACKET C10123155	
DIMENSIONS (HxWxD) (1 BRACKET)	5"x20"x1-13/16"
WEIGHT (FULL ASSEMBLY)	35.79 lbs
PACKAGE QUANTITY	4

#	DESCRIPTION
1	PLATE, CHANNEL BRACKET
2	RRH Z BRACKET, 3/16"
3	THREADED ROD ASSEMBLY 1/2"x12"



NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT

RRH DETAIL

NO SCALE

1

RRH DETAIL

NO SCALE




2

RRH MOUNT DETAIL

NO SCALE

3

JMA MX08FRO665-21	
DIMENSIONS (HxWxD)	72"x20.0"x8.0"
RF PORTS, CONNECTOR TYPE	8 x 4.3-10 FEMALE
WEIGHT	64.5 lbs
WEIGHT WITH BRACKETS	82.5 lbs



SIDE

FRONT

ANTENNA DETAIL

NO SCALE

4

NOT USED

NO SCALE





5

ANTENNA BRACKET DETAIL

NO SCALE

6

RAYCAP RDIC-9181-PF-48 DC SURGE PROTECTION (OVP)	
DIMENSIONS (HxWxD)	18.98"x14.39"x8.15"
WEIGHT	21.82 LBS



SIDE

BACK

FRONT

SURGE SUPPRESSION DETAIL (OVP)



NO SCALE

7

COMMSCOPE XP-2040
CROSSOVER PLATE

DIMENSIONS (HxW)	10"x12"
WEIGHT	11 lbs

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT



PLAN
U-BOLT

SIDE
U-BOLT

RRH/OVP MOUNT DETAIL

NO SCALE



8

COMMSCOPE
MC-PK8-DSH

FACE WIDTH	96"
WEIGHT	1373.08 lbs

NOTE:
OR DISH Wireless L.L.C.
APPROVED EQUIVALENT

NOTE: 15" TO 38" O.D.



ANTENNA PLATFORM DETAIL

NO SCALE

9

dish
wireless.

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER
10 PRESIDENTIAL WAY
WOBURN, MA 01801

B+T GRP
1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



10/17/21
B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION
DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057


SHEET TITLE
EQUIPMENT DETAILS

SHEET NUMBER


A-6

NOTES

1. CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
2. ANTENNAS AND MOUNTS OMITTED FOR CLARITY.
3. THE GROUND LEASE DOES NOT SPECIFY OUR UTILITY RIGHTS. "PWR" AND "FBR" PATH DEPICTED ON A-1 AND E-1 ARE BASED ON BEST AVAILABLE INFORMATION INCLUDING BUT NOT LIMITED TO FIELD VERIFICATION, PRIOR PROJECT DOCUMENTATION AND OTHER REAL PROPERTY RIGHTS DOCUMENTS. WHEN INSTALLING THE UTILITIES PLEASE LOCATE AND FOLLOW EXISTING PATH. IF EXISTING PATH IS NOT AN OPTION PLEASE NOTIFY TOWER OWNER AS FURTHER COORDINATION MAY BE NEEDED.



UTILITY ROUTE PLAN



1

DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING +24V AND -48V CONDUCTORS. RED MARKINGS SHALL IDENTIFY +24V AND BLUE MARKINGS SHALL IDENTIFY -48V.

1. CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
2. ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
4. CONDUIT ROUGH-IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS. VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
9. INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250. THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
13. ALL TRENCHES IN COMPOUND TO BE HAND DUG.
14. A BOUNDARY SURVEY OF THE EXISTING EASEMENT WAS NOT AVAILABLE AT CONSTRUCTION DRAWING CREATION. LICENSEE WILL NEED TO OBTAIN A UTILITY EASEMENT AND CONSTRUCTION CONTRACTOR MUST FIELD VERIFY ALL PROPOSED UTILITY ROUTES ARE WITHIN THE OBTAINED EASEMENT.



ELECTRICAL NOTES

NO SCALE

2



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION


A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
ELECTRICAL/FIBER ROUTE
PLAN AND NOTES

SHEET NUMBER
E-1



CARLON EXPANSION FITTINGS				
COUPLING END PART#	MALE TERMINAL ADAPTER END PART#	SIZE	STD CTN QTY.	TRAVEL LENGTH
E945D	E945DX	1/2"	20	4"
E945E	E945EX	3/4"	15	4"
E945F	E945FX	1"	10	4"
E945G	E945GX	1 1/4"	5	4"
E945H	E945HX	1 1/2"	5	4"
E945J	E945JX	2"	15	8"
E945K	E945KX	2 1/2"	10	8"
E945L	E945LX	3"	10	8"
E945M	E945MX	3 1/2"	5	8"
E945N	E945NX	4"	5	8"
E945P	E945PX	5"	1	8"
E945R	E945RX	6"	1	8"



NOTE: CONTRACTOR TO INSTALL EXPANSION FITTING SLIP JOINT AT METER CENTER CONDUIT TERMINATION, AS PER LOCAL UTILITY POLICY, ORDINANCE AND/OR SPECIFIED REQUIREMENT.

TRENCHING NOTES

- CONTRACTOR SHALL RESTORE THE TRENCH TO ITS ORIGINAL CONDITIONS BY EITHER SEEDING OR SODDING GRASS AREAS, OR REPLACING ASPHALT OR CONCRETE AREAS TO ITS ORIGINAL CROSS SECTION.
- TRENCHING SAFETY; INCLUDING, BUT NOT LIMITED TO SOIL CLASSIFICATION, SLOPING, AND SHORING, SHALL BE GOVERNED BY THE CURRENT OSHA TRENCHING AND EXCAVATION SAFETY STANDARDS.
- ALL CONDUITS SHALL BE INSTALLED IN COMPLIANCE WITH THE CURRENT NATIONAL ELECTRIC CODE (NEC) OR AS REQUIRED BY THE LOCAL JURISDICTION, WHICHEVER IS THE MOST STRINGENT.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057


SHEET TITLE
ELECTRICAL DETAILS

SHEET NUMBER
E-2

EXPANSION JOINT DETAIL NO SCALE 1

TYPICAL UNDERGROUND TRENCH DETAIL NO SCALE 2

DARK TELCO BOX – INTERIOR WIRING LAYOUT NO SCALE 3



LIT TELCO BOX – INTERIOR WIRING LAYOUT (OPTIONAL) NO SCALE 4



NOT USED NO SCALE 5

NOT USED NO SCALE 6

NOT USED NO SCALE 7

NOT USED NO SCALE 8

NOT USED NO SCALE 9



NOTES

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(a) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

#12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A
#10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A
#8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A
#6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358.
0.5" CONDUIT - 0.122 SQ. IN AREA
0.75" CONDUIT - 0.213 SQ. IN AREA
2.0" CONDUIT - 1.316 SQ. IN AREA
3.0" CONDUIT - 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.
#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN
#10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND
TOTAL = 0.0633 SQ. IN

0.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.
#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN
#10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND
TOTAL = 0.1146 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.
3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN
#6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND
TOTAL = 0.8544 SQ. IN

3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC ONE-LINE DIAGRAM

NO SCALE 1

PROPOSED CHARLES PANEL SCHEDULE

LOAD SERVED	VOLT AMPS (WATTS)		TRIP	CKT #	PHASE	CKT #	TRIP	VOLT AMPS (WATTS)		LOAD SERVED
	L1	L2						L1	L2	
PPC GFCI OUTLET	180	180	15A	1	A	2	30A	2880	2880	ABB/GE INFINITY RECTIFIER 1
CHARLES GFCI OUTLET			15A	3	B	4				
-SPACE-				5	A	6	30A	2880	2880	ABB/GE INFINITY RECTIFIER 2
-SPACE-				7	B	8				
-SPACE-				9	A	10	30A	2880	2880	ABB/GE INFINITY RECTIFIER 3
-SPACE-				11	B	12				
-SPACE-				13	A	14	30A	2880	2880	ABB/GE INFINITY RECTIFIER 4
-SPACE-				15	B	16				
-SPACE-				17	A	18				-SPACE-
-SPACE-				19	B	20				-SPACE-
-SPACE-				21	A	22				-SPACE-
-SPACE-				23	B	24				-SPACE-
VOLTAGE AMPS	180	180						11520	11520	
200A MCB, 1φ, 24 SPACE, 120/240V				L1	L2					
MB RATING: 65,000 AIC				11700	11700					
				98	98					VOLTAGE AMPS
										AMPS
										MAX AMPS
										MAX 125%

PANEL SCHEDULE

NO SCALE 2

NOT USED

NO SCALE 3



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: DAS
CHECKED BY: DAS
APPROVED BY: RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS


REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
ELECTRICAL ONE-LINE, FAULT
CALCS & PANEL SCHEDULE

SHEET NUMBER
E-3




TYPICAL EQUIPMENT GROUNDING PLAN

NO SCALE 1


NOTES

1. ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC MANUFACTURER. THIS LAYOUT IS FOR REFERENCE ONLY



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE 2



GROUNDING LEGEND

1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
2. CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- (A) EXTERIOR GROUND RING: #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- (B) TOWER GROUND RING: THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- (C) INTERIOR GROUND RING: #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN INSULATED CONDUCTOR.
- (D) BOND TO INTERIOR GROUND RING: #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE BUILDING.
- (E) GROUND ROD: UL LISTED COPPER CLAD STEEL, MINIMUM 1/2" DIAMETER BY EIGHT FEET LONG. GROUND RODS SHALL BE INSTALLED WITH INSPECTION SLEEVES. GROUND RODS SHALL BE DRIVEN TO THE DEPTH OF GROUND RING CONDUCTOR.
- (F) CELL REFERENCE GROUND BAR: POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- (G) HATCH PLATE GROUND BAR: BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) EXTERIOR CABLE ENTRY PORT GROUND BARS: LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING. BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- (I) TELCO GROUND BAR: BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- (J) FRAME BONDING: THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- (K) INTERIOR UNIT BONDS: METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE INTERIOR GROUND RING.
- (L) FENCE AND GATE GROUNDING: METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH GATE POST AND ACROSS GATE OPENINGS.
- (M) EXTERIOR UNIT BONDS: METALLIC OBJECTS, EXTERNAL TO OR MOUNTED TO THE BUILDING, SHALL BE BONDED TO THE EXTERIOR GROUND RING. USING #2 TINNED SOLID COPPER WIRE
- (N) ICE BRIDGE SUPPORTS: EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED GROUND RING.
- (O) DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVERTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE REFERENCE GROUND BAR
- (P) TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO PROPOSED ANTENNA MOUNT COLLAR. REFER TO DISH Wireless L.L.C. GROUNDING NOTES.

GROUNDING KEY NOTES

NO SCALE 3



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01


DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
GROUNDING PLANS
AND NOTES

SHEET NUMBER

G-1


NOTES
EQUIPMENT CABINET OMITTED FOR CLARITY



H-FRAME GROUNDING DETAIL


NO SCALE 1

NOTES
CABLE GROUNDING NOT REQUIRED WHEN ANTENNA IS LESS THAN 10' FROM CABINET




TYPICAL GPS UNIT GROUNDING

NO SCALE 2




OUTDOOR CABINET GROUNDING

NO SCALE 3




TRANSITIONING GROUND DETAIL

NO SCALE 4



TYPICAL TEST GROUND ROD WITH INSPECTION SLEEVE

NO SCALE 5



TYPICAL GROUND RING TRENCH

NO SCALE 6



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION



A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-2

1. EXOTHERMIC WELD (2) TWO, #2 AWG BARE TINNED SOLID COPPER CONDUCTORS TO GROUND BAR. ROUTE CONDUCTORS TO BURIED GROUND RING AND PROVIDE PARALLEL EXOTHERMIC WELD.
2. ALL EXTERIOR GROUNDING HARDWARE SHALL BE STAINLESS STEEL 3/8" DIAMETER OR LARGER. ALL HARDWARE 18-8 STAINLESS STEEL INCLUDING LOCK WASHERS, COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
3. FOR GROUND BOND TO STEEL ONLY: COAT ALL SURFACES WITH AN ANTI-OXIDANT COMPOUND BEFORE MATING.
4. DO NOT INSTALL CABLE GROUNDING KIT AT A BEND AND ALWAYS DIRECT GROUND CONDUCTOR DOWN TO GROUNDING BUS.
5. NUT & WASHER SHALL BE PLACED ON THE FRONT SIDE OF THE GROUND BAR AND BOLTED ON THE BACK SIDE.
6. ALL GROUNDING PARTS AND EQUIPMENT TO BE SUPPLIED AND INSTALLED BY CONTRACTOR.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING ADDITIONAL GROUND BAR AS REQUIRED.
8. ENSURE THE WIRE INSULATION TERMINATION IS WITHIN 1/8" OF THE BARREL (NO SHINERS).



TYPICAL GROUNDING NOTES

NO SCALE

1

TYPICAL EXTERIOR TWO HOLE LUG


NO SCALE

2

TYPICAL INTERIOR TWO HOLE LUG

NO SCALE

3



LUG DETAIL

NO SCALE

4

NOT USED

NO SCALE

5

NOT USED

NO SCALE

6

NOT USED

NO SCALE

7

NOT USED

NO SCALE

8

NOT USED

NO SCALE

9

dish
wireless

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120

AMERICAN TOWER
10 PRESIDENTIAL WAY
WOBURN, MA 01801

B+T GRP
1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:

DAS DAS RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
D	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
GROUNDING DETAILS

SHEET NUMBER
G-3

HYBRID/DISCREET CABLES

3/4" TAPE WIDTHS WITH 3/4" SPACING

LOW-BAND RRH
(600 MHz N71 BASEBAND) +
(850 MHz N26 BAND) +
(700 MHz N29 BAND) - OPTIONAL PER MARKET
ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BAND)

ALPHA RRH				BETA RRH				GAMMA RRH			
PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT	PORT 1 + SLANT	PORT 2 - SLANT	PORT 3 + SLANT	PORT 4 - SLANT
RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
ORANGE	ORANGE	RED	RED	ORANGE	ORANGE	BLUE	BLUE	ORANGE	ORANGE	GREEN	GREEN
	WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE		WHITE (-) PORT	ORANGE	ORANGE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

MID-BAND RRH
(AWS BANDS N66+N70)
ADD FREQUENCY COLOR TO SECTOR BAND
(CBRS WILL USE YELLOW BANDS)

RED	RED	RED	RED	BLUE	BLUE	BLUE	BLUE	GREEN	GREEN	GREEN	GREEN
PURPLE	PURPLE	RED	RED	PURPLE	PURPLE	BLUE	BLUE	PURPLE	PURPLE	GREEN	GREEN
	WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE		WHITE (-) PORT	PURPLE	PURPLE
			WHITE (-) PORT				WHITE (-) PORT				WHITE (-) PORT

HYBRID/DISCREET CABLES

INCLUDE SECTOR BANDS BEING SUPPORTED
ALONG WITH FREQUENCY BANDS.
EXAMPLE 1 - HYBRID, OR DISCREET, SUPPORTS
ALL SECTORS, BOTH LOW-BANDS AND
MID-BANDS.
EXAMPLE 2 - HYBRID, OR DISCREET, SUPPORTS
CBRS ONLY, ALL SECTORS.
EXAMPLE 3 - MAIN COAX WITH GROUND
MOUNTED RRHS.

EXAMPLE 1	EXAMPLE 2	EXAMPLE 3 COAX #1 (ALPHA)	COAX #2 (ALPHA)
RED	RED	RED	RED
BLUE	BLUE		
GREEN	GREEN		
ORANGE	YELLOW		
PURPLE			

CONTRACTOR TO REFER TO FINAL
CONSTRUCTION RFDS FOR ALL RD DETAILS.
FINAL RFDS IS IN NEXSYSONE.

FIBER JUMPERS TO RRHS

LOW-BAND HHR FIBER CABLES HAVE SECTOR
STRIPE ONLY.

LOW BAND RRH	MID BAND RRH	LOW BAND RRH	MID BAND RRH	LOW BAND RRH	MID BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
ORANGE	PURPLE	ORANGE	PURPLE	ORANGE	PURPLE

POWER CABLES TO RRHS

LOW-BAND RRH POWER CABLES HAVE SECTOR
STRIPE ONLY.

LOW BAND RRH	MID BAND RRH	LOW BAND RRH	MID BAND RRH	LOW BAND RRH	MID BAND RRH
RED	RED	BLUE	BLUE	GREEN	GREEN
ORANGE	PURPLE	ORANGE	PURPLE	ORANGE	PURPLE

RET MOTORS AT ANTENNAS

RET CONTROL IS HANDLED BY THE MID-BAND
RRH WHEN ONE SET OF RET PORTS EXIST ON
ANTENNA.
SEPARATE RET CABLES ARE USED WHEN
ANTENNA PORTS PROVIDE INPUTS FOR BOTH
LOW AND MID BANDS.

ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND		ANTENNA 1 MID BAND		ANTENNA 1 LOW BAND	
IN	IN	IN	IN	IN	IN	IN	IN
RED	RED	BLUE	BLUE	GREEN	GREEN	PURPLE	ORANGE
PURPLE	ORANGE	PURPLE	ORANGE	PURPLE	ORANGE		

MICROWAVE RADIO LINKS

LINKS WILL HAVE A 1.5-2 INCH WHITE WRAP
WITH THE AZIMUTH COLOR OVERLAPPING IN THE
MIDDLE.
ADD ADDITIONAL SECTOR COLOR BANDS FOR
EACH ADDITIONAL MW RADIO.
MICROWAVE CABLES WILL REQUIRE P-TOUCH
LABELS INSIDE THE CABINET TO IDENTIFY THE
LOCAL AND REMOTE SITE ID'S.

FORWARD AZIMUTH OF 0-120 DEGREES		FORWARD AZIMUTH OF 120-240 DEGREES		FORWARD AZIMUTH OF 240-359 DEGREES	
PRIMARY	SECONDARY	PRIMARY	SECONDARY	PRIMARY	SECONDARY
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
RED	RED	BLUE	BLUE	GREEN	GREEN
WHITE	WHITE	WHITE	WHITE	WHITE	WHITE
	RED	BLUE	BLUE	GREEN	GREEN
	WHITE	WHITE	WHITE	WHITE	WHITE

RF CABLE COLOR CODES

1

NOT USED

4

LOW BANDS (N71+N26)
OPTIONAL - (N29)

ORANGE

CBRS TECH
(3 GHz)

YELLOW

AWS
(N66+N70+H-BLOCK)

PURPLE

NEGATIVE SLANT PORT
ON ANT/RRH

WHITE

ALPHA SECTOR

RED

BETA SECTOR

BLUE

GAMMA SECTOR

GREEN

COLOR IDENTIFIER

2

NOT USED

3

NOT USED

4

dish
wireless

5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B+T GRP
1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON,
UNLESS THEY ARE ACTING UNDER THE DIRECTION
OF A LICENSED PROFESSIONAL ENGINEER,
TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY:
DAS DAS RCM

RFDS REV #: 1.0

CONSTRUCTION
DOCUMENTS

REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION


BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
RF
CABLE COLOR CODES


SHEET NUMBER

RF-1


EXOTHERMIC CONNECTION
 MECHANICAL CONNECTION
 BUSS BAR INSULATOR
 CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 TEST CHEMICAL ELECTROLYTIC GROUNDING SYSTEM
 EXOTHERMIC WITH INSPECTION SLEEVE
 GROUNDING BAR
 GROUND ROD
 TEST GROUND ROD WITH INSPECTION SLEEVE




SINGLE POLE SWITCH
 DUPLEX RECEPTACLE
 DUPLEX GFCI RECEPTACLE
 FLUORESCENT LIGHTING FIXTURE (2) TWO LAMPS 48-T8




SMOKE DETECTION (DC)
 EMERGENCY LIGHTING (DC)
 SECURITY LIGHT W/PHOTOCELL LITHONIA ALXW
 LED-1-25A400/51K-SR4-120-PE--DDBTXD




CHAIN LINK FENCE
 WOOD/WROUGHT IRON FENCE
 WALL STRUCTURE
 LEASE AREA




PROPERTY LINE (PL)
 SETBACKS




ICE BRIDGE
 CABLE TRAY
 WATER LINE



UNDERGROUND POWER
 UNDERGROUND TELCO
 OVERHEAD POWER
 OVERHEAD TELCO
 UNDERGROUND TELCO/POWER
 ABOVE GROUND POWER
 ABOVE GROUND TELCO
 ABOVE GROUND TELCO/POWER
 WORKPOINT



SECTION REFERENCE



DETAIL REFERENCE



LEGEND

AB ANCHOR BOLT	IN INCH
ABV ABOVE	INT INTERIOR
AC ALTERNATING CURRENT	LB(S) POUND(S)
ADDL ADDITIONAL	LF LINEAR FEET
AFF ABOVE FINISHED FLOOR	LTE LONG TERM EVOLUTION
AFG ABOVE FINISHED GRADE	MAS MASONRY
AGL ABOVE GROUND LEVEL	MAX MAXIMUM
AIC AMPERAGE INTERRUPTION CAPACITY	MB MACHINE BOLT
ALUM ALUMINUM	MECH MECHANICAL
ALT ALTERNATE	MFR MANUFACTURER
ANT ANTENNA	MGB MASTER GROUND BAR
APPROX APPROXIMATE	MIN MINIMUM
ARCH ARCHITECTURAL	MISC MISCELLANEOUS
ATS AUTOMATIC TRANSFER SWITCH	MTL METAL
AWG AMERICAN WIRE GAUGE	MTS MANUAL TRANSFER SWITCH
BATT BATTERY	MW MICROWAVE
BLDG BUILDING	NEC NATIONAL ELECTRIC CODE
BLK BLOCK	NM NEWTON METERS
BLKG BLOCKING	NO. NUMBER
BM BEAM	# NUMBER
BTC BARE TINNED COPPER CONDUCTOR	NTS NOT TO SCALE
BOF BOTTOM OF FOOTING	OC ON-CENTER
CAB CABINET	OSHA OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
CANT CANTILEVERED	OPNG OPENING
CHG CHARGING	P/C PRECAST CONCRETE
CLG CEILING	PCS PERSONAL COMMUNICATION SERVICES
CLR CLEAR	PCU PRIMARY CONTROL UNIT
COL COLUMN	PRC PRIMARY RADIO CABINET
COMM COMMON	PP POLARIZING PRESERVING
CONC CONCRETE	PSF POUNDS PER SQUARE FOOT
CONSTR CONSTRUCTION	PSI POUNDS PER SQUARE INCH
DBL DOUBLE	PT PRESSURE TREATED
DC DIRECT CURRENT	PWR POWER CABINET
DEPT DEPARTMENT	QTY QUANTITY
DF DOUGLAS FIR	RAD RADIUS
DIA DIAMETER	RECT RECTIFIER
DIAG DIAGONAL	REF REFERENCE
DIM DIMENSION	REINF REINFORCEMENT
DWG DRAWING	REQ'D REQUIRED
DWL DOWEL	RET REMOTE ELECTRIC TILT
EA EACH	RF RADIO FREQUENCY
EC ELECTRICAL CONDUCTOR	RMC RIGID METALLIC CONDUIT
EL ELEVATION	RRH REMOTE RADIO HEAD
ELEC ELECTRICAL	RRU REMOTE RADIO UNIT
EMT ELECTRICAL METALLIC TUBING	RWY RACEWAY
ENG ENGINEER	SCH SCHEDULE
EQ EQUAL	SHT SHEET
EXP EXPANSION	SIAD SMART INTEGRATED ACCESS DEVICE
EXT EXTERIOR	SIM SIMILAR
EW EACH WAY	SPEC SPECIFICATION
FAB FABRICATION	SQ SQUARE
FF FINISH FLOOR	SS STAINLESS STEEL
FG FINISH GRADE	STD STANDARD
FIF FACILITY INTERFACE FRAME	STL STEEL
FIN FINISH(ED)	TEMP TEMPORARY
FLR FLOOR	THK THICKNESS
FDN FOUNDATION	TMA TOWER MOUNTED AMPLIFIER
FOC FACE OF CONCRETE	TN TOE NAIL
FOM FACE OF MASONRY	TOA TOP OF ANTENNA
FOS FACE OF STUD	TOC TOP OF CURB
FOW FACE OF WALL	TOF TOP OF FOUNDATION
FS FINISH SURFACE	TOP TOP OF PLATE (PARAPET)
FT FOOT	TOS TOP OF STEEL
FTG FOOTING	TOW TOP OF WALL
GA GAUGE	TVSS TRANSIENT VOLTAGE SURGE SUPPRESSION
GEN GENERATOR	TYP TYPICAL
GFCI GROUND FAULT CIRCUIT INTERRUPTER	UG UNDERGROUND
GLB GLUE LAMINATED BEAM	UL UNDERWRITERS LABORATORY
GLV GALVANIZED	UNO UNLESS NOTED OTHERWISE
GPS GLOBAL POSITIONING SYSTEM	UMTS UNIVERSAL MOBILE TELECOMMUNICATIONS SYSTEM
GND GROUND	UPS UNINTERRUPTIBLE POWER SYSTEM (DC POWER PLANT)
GSM GLOBAL SYSTEM FOR MOBILE	VIF VERIFIED IN FIELD
HDG HOT DIPPED GALVANIZED	W WIDE
HDR HEADER	W/ WITH
HGR HANGER	WD WOOD
HVAC HEAT/VENTILATION/AIR CONDITIONING	WP WEATHERPROOF
HT HEIGHT	WT WEIGHT
IGR INTERIOR GROUND RING	

ABBREVIATIONS



5701 SOUTH SANTA FE DRIVE
 LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
 153557.001.01

DISH Wireless L.L.C.
 PROJECT INFORMATION
 BOHVN00005A
 20 ANTOLINI ROAD
 NEW HARTFORD, CT 06057

SHEET TITLE
 LEGEND AND ABBREVIATIONS

SHEET NUMBER
 GN-1

SITE ACTIVITY REQUIREMENTS:


- NOTICE TO PROCEED – NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER OWNER CONSTRUCTION MANAGER.
- "LOOK UP" – DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:
THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH Wireless L.L.C. AND DISH Wireless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.
- PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
- ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH Wireless L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
- ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
- ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
- CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
- ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH Wireless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
- THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
- THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
- THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
- THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
- CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
- THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
- NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

- FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:
CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION
CARRIER:DISH Wireless L.L.C.
TOWER OWNER:TOWER OWNER
- THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
- NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
- SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
- PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
- ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
- THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-2

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST-IN-PLACE CONCRETE.
2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90°f AT TIME OF PLACEMENT.
4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES. AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:
 - #4 BARS AND SMALLER 40 ksi
 - #5 BARS AND LARGER 60 ksi
6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
 - CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
 - CONCRETE EXPOSED TO EARTH OR WEATHER:
 - #6 BARS AND LARGER 2"
 - #5 BARS AND SMALLER 1-1/2"
 - CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
 - SLAB AND WALLS 3/4"
 - BEAMS AND COLUMNS 1-1/2"
7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
 - 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
 - 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR-CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
8. TIE WRAPS ARE NOT ALLOWED.
9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

16. ELECTRICAL METALLIC TUBING (EMT) OR METAL-CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION-TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY-COATED OR NON-CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-3

GROUNDING NOTES:

1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
2. THE CONTRACTOR SHALL PERFORM IEEE FALL-OF-POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
13. COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/0 COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.



5701 SOUTH SANTA FE DRIVE
LITTLETON, CO 80120



AMERICAN TOWER
10 PRESIDENTIAL WAY
WOBURN, MA 01801



1717 S. BOULDER
SUITE 300
TULSA, OK 74119
PH: (918) 587-4630
www.btgrp.com



B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:	CHECKED BY:	APPROVED BY:
DAS	DAS	RCM

RFDS REV #: 1.0

CONSTRUCTION DOCUMENTS

SUBMITTALS		
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	10/17/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER
153557.001.01

DISH Wireless L.L.C.
PROJECT INFORMATION
BOHVN00005A
20 ANTOLINI ROAD
NEW HARTFORD, CT 06057

SHEET TITLE
GENERAL NOTES

SHEET NUMBER
GN-4

ENGINEERING:
STRUCTURAL ANALYSIS
MOUNT ANALYSIS



AMERICAN TOWER®
CORPORATION

This report was prepared for American Tower Corporation by




Structural Analysis Report

Structure : 145 ft Monopole
ATC Site Name : Nepaug CT, CT
ATC Asset Number : 411182
Engineering Number : 13693709_C3_02
Proposed Carrier : DISH WIRELESS L.L.C.
Carrier Site Name : BOHVN00005A
Carrier Site Number : BOHVN00005A
Site Location : 20 Antolini Road
New Hartford, CT 06057-3326
41.828100,-73.015700
County : Litchfield
Date : July 12, 2021
Max Usage : 81%
Result : Pass

Prepared By:
Ravi Siddharth Raja

Reviewed By:



Tyler M. Barker
CLS Engineering PLLC
PE # 32402 Exp. 1/31/2021
COA # PEC.001833 Exp. 8/14/2022
07/13/2021



Table of Contents

Introduction 1

Supporting Documents..... 1

Analysis..... 1

Conclusion..... 1

Existing and Reserved Equipment..... 2

Equipment to be Removed 2

Proposed Equipment..... 3

Structure Usages.....3

Foundations3

Deflection and Sway3

Standard Conditions4

Calculations..... Attached

Introduction

The purpose of this report is to summarize results of a structural analysis performed on the 145 ft monopole to reflect the change in loading by DISH WIRELESS L.L.C..

Supporting Documents

Tower Drawings	EI Project #8859 Rev. 2, dated March 30, 2001 Tower Mapping by TEP, Project#05598, dated July 7, 2005
Foundation Drawing	URS Grenier Woodward Clyde Project #F301682.04, dated October 13, 2000
Geotechnical Report	Dr. Clarence Welti Site Location: 20 Antolini Road, New Hartford, CT., dated March 27, 2000

Analysis

The tower was analyzed using American Tower Corporation's tower analysis software. This program considers an elastic three-dimensional model and second-order effects per ANSI/TIA-222.

Basic Wind Speed:	115 mph (3-Second Gust)
Basic Wind Speed w/ Ice:	50 mph (3-Second Gust) w/ 1" radial ice concurrent
Code:	ANSI/TIA-222-H / 2015 IBC / 2018 Connecticut State Building Code
Exposure Category:	B
Risk Category:	II
Topographic Factor Procedure:	Method 1
Topographic Category:	1
Crest Height (H):	0 ft
Spectral Response:	$S_s = 0.17, S_1 = 0.05$
Site Class:	D - Stiff Soil

Conclusion

Based on the analysis results, the structure meets the requirements per the applicable codes listed above. The tower and foundation can support the equipment as described in this report.

If you have any questions or require additional information, please contact American Tower via email at Engineering@americantower.com. Please include the American Tower site name, site number, and engineering number in the subject line for any questions.

Existing and Reserved Equipment

Elev. ¹ (ft)	Qty	Equipment	Mount Type	Lines	Carrier
160.0	1	RFS PD620-2	Triangular Low Profile Platform	(1) 7/8" Coax	OTHER
155.0	1	Generic 12' Omni	Triangular Low Profile Platform	(1) 7/8" Coax	
151.0	3	Alcatel-Lucent RRH2x50-08	Triangular Low Profile Platform	(4) 1 1/4" Hybriflex Cable (1) 1/2" Coax	SPRINT NEXTEL
	3	Alcatel-Lucent 800 MHz RRH			
	3	Alcatel-Lucent 1900MHz RRH			
	3	Alcatel-Lucent ALU 800MHz External Notch Filter			
	1	PCTEL GPS-TMG-HR-26N			
	3	Alcatel-Lucent TD-RRH8x20-25 w/ Solar Shield			
	3	Commscope DT465B-2XR			
3	RFS APXVSP18-C-A20				
145.0	1	Generic GPS	T-Arm	(1) 7/8" Coax (12) 1 5/8" Coax	VERIZON WIRELESS
142.0	6	Amphenol Antel LPA-80040-4CF-EDIN-X			
	3	Amphenol Antel BXA-70040/6CF			
	1	VZW Unused Reserve (0 sqin)			
140.0	6	Generic TTA			
	3	Amphenol Antel BXA-171040-8CF			
125.0	1	Generic E-911 GPS			
	3	Commscope LNX-6515DS-A1M (43.7 lb)			
	6	RFS APX16DWV-16DWV-S-E-ACU			
	3	RFS ATMAA1412D-1A20			
	3	RFS ATM1900D-1CWA			
82.0	3	Spinner 756529	Triangular Platform with Handrails	(2) 0.39" (10mm) Fiber Trunk (1) 0.45" (11.5mm) Fiber (5) 0.78" (19.7mm) 8 AWG 6 (2) 2" conduit (3) 3" conduit (12) 7/8" Coax	AT&T MOBILITY
	6	Powerwave Allgon LGP21901			
	6	Powerwave Allgon LGP21401			
	1	Raycap DC6-48-60-18-8F(32.8 lbs)			
	3	Ericsson RRUS 4478 B14			
	3	Ericsson RRUS 4449 B5, B12			
	4	CCI DMP65R-BU6DA			
	2	CCI DMP65R-BU8D			
	3	Powerwave Allgon 7770.00			
	1	Raycap DC9-48-60-24-8C-EV			
	3	Ericsson Radio 8843 - B2 + B66A (w/ protruding items)			
52.0	1	PCTEL GPS-TMG-HR-26N	Stand-Off	(1) 1/2" Coax	SPRINT NEXTEL

Equipment to be Removed

Elev. ¹ (ft)	Qty	Equipment	Mount Type	Lines	Carrier
No loading was considered as removed as part of this analysis.					

Proposed Equipment

Elev. ¹ (ft)	Qty	Equipment	Mount Type	Lines	Carrier
114.0	1	Commscope RDIDC-9181-PF-48	Triangular Platform with Handrails	(1) 1.60" (40.6mm) Hybrid	DISH WIRELESS L.L.C.
	3	Fujitsu TA08025-B604			
	3	Fujitsu TA08025-B605			
	3	JMA Wireless MX08FRO665-21			

¹ Contracted elevations are shown for appurtenances within contracted installation tolerances. Appurtenances outside of contract limits are shown at installed elevations.

Install proposed lines inside the pole shaft.

Structure Usages

Structural Component	Controlling Usage	Pass/Fail
Anchor Bolts	36%	Pass
Shaft	49%	Pass
Base Plate	81%	Pass
Flange Plate	58%	Pass

Foundations

Reaction Component	Original Design Reactions	Factored Design Reactions*	Analysis Reactions	% of Design
Moment (Kips-Ft)	3,128.4	4,223.3	2,397.8	57%
Shear (Kips)	29.2	39.4	23.0	59%

* The design reactions are factored by 1.35 per ANSI/TIA-222-H, Sec. 15.6.2

The structure base reactions resulting from this analysis are acceptable when compared to those shown on the original structure drawings, therefore no modification or reinforcement of the foundation will be required.

Deflection and Sway*

Antenna Elevation (ft)	Antenna	Carrier	Deflection (ft)	Sway (Rotation) (°)
114.0	Commscope RDIDC-9181-PF-48	DISH WIRELESS L.L.C.	0.995	1.037
	Fujitsu TA08025-B604			
	Fujitsu TA08025-B605			
	JMA Wireless MX08FRO665-21			

*Deflection and Sway was evaluated considering a design wind speed of 60 mph (3-Second Gust) per ANSI/TIA-222-H



Standard Conditions

All engineering services performed by A.T. Engineering Service, PLLC are prepared on the basis that the information used is current and correct. This information may consist of, but is not limited to the following:

- Information supplied by the client regarding antenna, mounts and feed line loading
- Information from drawings, design and analysis documents, and field notes in the possession of A.T. Engineering Service, PLLC


It is the responsibility of the client to ensure that the information provided to A.T. Engineering Service, PLLC and used in the performance of our engineering services is correct and complete.

All assets of American Tower Corporation, its affiliates and subsidiaries (collectively "American Tower") are inspected at regular intervals. Based upon these inspections and in the absence of information to the contrary, American Tower assumes that all structures were constructed in accordance with the drawings and specifications.

Unless explicitly agreed by both the client and A.T. Engineering Service, PLLC, all services will be performed in accordance with the current revision of ANSI/TIA-222.

All services are performed, results obtained, and recommendations made in accordance with generally accepted engineering principles and practices. A.T. Engineering Service, PLLC is not responsible for the conclusions, opinions and recommendations made by others based on the information supplied herein.


© 2007 - 2021 by ATC IP LLC. All rights reserved.



Job Information	
Client : DISH WIRELESS L.L.C.	
Pole : 411182	Code: ANSI/TIA-222-H
Location : Nepaug CT, CT	
Description : 145' EEI Monopole	Risk Category : II
Shape : 18 Sides	Exposure : B
Height : 145.00 (ft)	Topo Method : Method 1
Base Elev (ft): 0.00	Topographic Category : 1
Taper: 0.22844in/ft)	

Sections Properties						
Section	Length (ft)	Diameter (in)		Thick Joint (in)	Overlap Length (in)	Steel Grade
		Across Flats Top	Across Flats Bottom			
1	48.794	38.60	49.75	0.438	0.000	18 Sides 65
2	40.122	31.46	40.63	0.375	67.063	18 Sides 65
3	35.328	25.08	33.15	0.313	55.906	18 Sides 65
4	31.003	18.00	25.08	0.188	0.000	18 Sides 65

Discrete Appurtenance			
Attach Elev (ft)	Force Elev (ft)	Qty	Description
145.000	151.000	3	Commscope DT465B-2XR
145.000	151.000	3	RFS APXVSP18-C-A20
145.000	151.000	3	Alcatel-Lucent TD-RRH8x20-25
145.000	151.000	3	Alcatel-Lucent 1900MHz RRH
145.000	151.000	3	Alcatel-Lucent 800 MHz RRH
145.000	151.000	3	Alcatel-Lucent RRH2x50-08
145.000	151.000	3	Alcatel-Lucent ALU 800MHz
145.000	151.000	1	PCTEL GPS-TMG-HR-26N
145.000	155.000	1	Generic 12' Omni
145.000	160.000	1	RFS PD620-2
145.000	145.000	1	Flat Low Profile Platform
145.000	142.000	1	Generic GPS
142.000	142.000	1	VZW Unused Reserve (0 sqin)
142.000	141.000	3	Amphenol Antel BXA-
142.000	141.000	6	Amphenol Antel LPA-80040-
140.000	141.000	3	Amphenol Antel BXA-171040-
140.000	141.000	6	Generic TTA
138.000	138.000	3	Round T-Arm
125.000	125.000	3	Round T-Arm
125.000	125.000	6	RFS APX16DWV-16DWV-S-E-
125.000	125.000	3	RFS ATMAA1412D-1A20
125.000	125.000	3	RFS ATM1900D-1CWA
125.000	125.000	3	Commscope LNX-6515DS-A1M
125.000	125.000	1	Generic E-911 GPS
114.000	114.000	1	Generic Flat Platform with Han
114.000	114.000	3	JMA Wireless MX08FRO665-21
114.000	114.000	3	Fujitsu TA08025-B605
114.000	114.000	3	Fujitsu TA08025-B604
114.000	114.000	1	Commscope RDIDC-9181-PF-48
90.000	90.000	1	Empty Flat Low Profile Platfor
82.000	82.000	2	CCI DMP65R-BU8D
82.000	82.000	3	Powerwave Allgon 7770.00
82.000	82.000	1	Raycap DC9-48-60-24-8C-EV
82.000	82.000	3	Ericsson Radio 8843 - B2 + B66
82.000	82.000	4	CCI DMP65R-BU6DA
82.000	82.000	3	Ericsson RRUS 4449 B5, B12
82.000	82.000	3	Ericsson RRUS 4478 B14
82.000	82.000	1	Raycap DC6-48-60-18-8F(32.8 lb
82.000	82.000	6	Powerwave Allgon LGP21401
82.000	82.000	6	Powerwave Allgon LGP21901
82.000	82.000	3	Spinner 756529
80.000	80.000	1	Generic Flat Platform with Han
52.000	52.000	1	Stand-Off
52.000	52.000	1	PCTEL GPS-TMG-HR-26N




Linear Appurtenance			
Elev (ft)		Description	Exposed To Wind
From	To		
0.000	52.000	1/2" Coax	Yes
0.000	82.000	0.39" (10mm)	No
0.000	82.000	0.39" (10mm)	No
0.000	82.000	0.45" (11.5mm)	No
0.000	82.000	0.78" (19.7mm) 8	No
0.000	82.000	2" conduit	No
0.000	82.000	3" conduit	No
0.000	82.000	3" conduit	No
0.000	82.000	7/8" Coax	No
0.000	114.0	1.60" (40.6mm)	No
0.000	125.0	1 5/8" Coax	Yes
0.000	125.0	1 5/8" Coax	No
0.000	125.0	1 5/8" Coax	No
0.000	125.0	1/2" Coax	No
0.000	140.0	1 5/8" Coax	No
0.000	142.0	1 5/8" Coax	No
0.000	145.0	7/8" Coax	No
0.000	151.0	1 1/4" Hybriflex	No
0.000	151.0	1/2" Coax	No
0.000	155.0	7/8" Coax	No
0.000	160.0	7/8" Coax	No

Load Cases	
1.2D + 1.0W	115 mph with No Ice
0.9D + 1.0W	115 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 1.00 in Radial Ice
1.2D + 1.0Ev + 1.0Eh	Seismic
0.9D - 1.0Ev + 1.0Eh	Seismic (Reduced DL)
1.0D + 1.0W	Serviceability 60 mph

Reactions			
Load Case	Moment (kip-ft)	Shear (kip)	Axial (kip)
1.2D + 1.0W	2397.84	23.03	51.99
0.9D + 1.0W	2367.63	23.01	38.98
1.2D + 1.0Di + 1.0Wi	664.57	6.42	68.04
1.2D + 1.0Ev + 1.0Eh	190.34	1.70	51.68
0.9D - 1.0Ev + 1.0Eh	187.48	1.69	36.05
1.0D + 1.0W	579.56	5.61	43.35

Dish Deflections			
Load Case	Attach Elev (ft)	Deflection (in)	Rotation (deg)
	0.00	0.000	0.000

Load Case : 1.2D + 1.0W
Max Ratio 49.46% at 48.8 ft



Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:33 PM

Customer: DISH WIRELESS L.L.C.

Analysis Parameters

Location :	Litchfield County, CT	Height (ft) :	145
Code :	ANSI/TIA-222-H	Base Diameter (in) :	49.75
Shape :	18 Sides	Top Diameter (in) :	18.00
Pole Type :	Taper	Taper (in/ft) :	0.228
Pole Manufacturer :	EEI	Rotation (deg) :	0.00
Kd (non-service) :	0.95	Ke :	0.97

Ice & Wind Parameters

Exposure Category:	B	Design Wind Speed Without Ice:	115 mph
Risk Category:	II	Design Wind Speed With Ice:	50 mph
Topographic Factor Procedure:	Method 1	Operational Wind Speed:	60 mph
Topographic Category:	1	Design Ice Thickness:	1.00 in
Crest Height:	0 ft	HMSL:	744.00 ft

Seismic Parameters

Analysis Method:	Equivalent Lateral Force Method		
Site Class:	D - Stiff Soil		
Period Based on Rayleigh Method (sec):	2.31		
T_L (sec):	6	p :	1.3
S_s :	0.174	S_1 :	0.054
F_a :	1.600	F_v :	2.400
S_{ds} :	0.186	S_{d1} :	0.086
		C_s :	0.030
		C_s Max:	0.030
		C_s Min:	0.030

Load Cases

1.2D + 1.0W	115 mph with No Ice
0.9D + 1.0W	115 mph with No Ice (Reduced DL)
1.2D + 1.0Di + 1.0Wi	50 mph with 1.00 in Radial Ice
1.2D + 1.0Ev + 1.0Eh	Seismic
0.9D - 1.0Ev + 1.0Eh	Seismic (Reduced DL)
1.0D + 1.0W	Serviceability 60 mph

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:33 PM

Customer: DISH WIRELESS L.L.C.

Shaft Section Properties

Sect Info	Length (ft)	Thick (in)	Fy (ksi)	Joint Type	Slip Joint Len (in)	Weight (lb)	Bottom						Top							
							Dia (in)	Elev (ft)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	Dia (in)	Elev (ft)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	Taper (in/ft)	
1-18	48.794	0.4375	65		0.00	10,084	49.75	0.00	68.47	21037.5	18.29	113.71	38.60	48.79	53.00	9753.0	13.80	88.24	0.228448	
2-18	40.122	0.3750	65	Slip	67.06	5,797	40.63	43.21	47.91	9809.0	17.34	108.35	31.46	83.33	37.00	4518.4	13.03	83.90	0.228448	
3-18	35.328	0.3125	65	Slip	55.91	3,435	33.15	78.67	32.57	4438.4	16.94	106.09	25.08	114.00	24.57	1904.5	12.39	80.26	0.228448	
4-18	31.003	0.1880	65	Butt	0.00	1,344	25.08	114.00	14.85	1163.1	21.76	133.42	18.00	145.00	10.63	426.0	15.12	95.74	0.228448	
Shaft Weight						20,659														

Discrete Appurtenance Properties

Attach Elev (ft)	Description	Qty	Ka	Vert Ecc (ft)	Weight (lb)	No Ice EPAa (sf)	Orientation Factor	Weight (lb)	Ice EPAa (sf)	Orientation Factor
145.00	PCTEL GPS-TMG-HR-26N	1	0.80	6.000	0.60	0.090	1.00	3.82	0.210	1.00
145.00	Alcatel-Lucent ALU 800MHz	3	0.80	6.000	8.80	0.667	0.50	20.51	1.034	0.50
145.00	Generic GPS	1	1.00	-3.000	10.00	0.900	1.00	29.46	1.325	1.00
145.00	Alcatel-Lucent RRH2x50-08	3	0.80	6.000	52.90	1.701	0.50	92.31	2.275	0.50
145.00	Alcatel-Lucent 800 MHz RRH	3	0.80	6.000	53.00	2.134	0.67	102.09	2.785	0.67
145.00	Alcatel-Lucent 1900MHz RRH	3	0.80	6.000	44.00	3.258	0.72	116.45	4.049	0.72
145.00	Generic 12' Omni	1	0.80	10.000	40.00	3.600	1.00	100.38	6.457	1.00
145.00	Alcatel-Lucent TD-RRH8x20-25	3	0.80	6.000	70.00	4.046	0.61	132.86	4.929	0.61
145.00	RFS PD620-2	1	0.80	15.000	53.00	7.170	1.00	170.23	12.004	1.00
145.00	RFS APXVSP18-C-A20	3	0.80	6.000	57.00	8.024	0.69	171.73	9.879	0.69
145.00	Commscope DT465B-2XR	3	0.80	6.000	58.00	9.098	0.69	192.37	10.940	0.69
145.00	Flat Low Profile Platform	1	1.00	0.000	1,500.00	26.100	1.00	1,930.90	38.798	1.00
142.00	VZW Unused Reserve (0 sqin)	1	0.80	0.000	0.00	0.000	0.90	0.00	0.000	0.90
142.00	Amphenol Antel LPA-80040-4CF-	6	0.80	-1.000	18.00	4.995	0.74	109.52	6.222	0.74
142.00	Amphenol Antel BXA-70040/6CF	3	0.80	-1.000	37.50	14.249	0.62	227.09	16.127	0.62
140.00	Generic TTA	6	0.80	1.000	10.00	1.200	0.50	33.87	1.681	0.50
140.00	Amphenol Antel BXA-171040-8CF	3	0.80	1.000	13.00	5.089	0.64	82.37	6.346	0.64
138.00	Round T-Arm	3	0.75	0.000	250.00	9.700	0.67	388.31	15.156	0.67
125.00	Generic E-911 GPS	1	0.80	0.000	5.00	0.580	1.00	21.77	0.870	1.00
125.00	RFS ATM1900D-1CWA	3	0.80	0.000	8.40	0.717	0.50	19.97	1.090	0.50
125.00	RFS ATMAA1412D-1A20	3	0.80	0.000	13.00	1.000	0.50	30.37	1.437	0.50
125.00	RFS APX16DWV-16DWV-S-E-ACU	6	0.80	0.000	39.60	6.077	0.60	93.29	7.424	0.60
125.00	Round T-Arm	3	0.75	0.000	250.00	9.700	0.67	386.82	15.097	0.67
125.00	Commscope LNX-6515DS-A1M	3	0.80	0.000	43.70	11.445	0.70	193.89	13.564	0.70
114.00	Commscope RDIDC-9181-PF-48	1	0.75	0.000	21.90	1.867	1.00	58.89	2.452	1.00
114.00	Fujitsu TA08025-B604	3	0.75	0.000	63.90	1.962	0.50	101.80	2.560	0.50
114.00	Fujitsu TA08025-B605	3	0.75	0.000	75.00	1.962	0.50	115.72	2.560	0.50
114.00	JMA Wireless MX08FRO665-21	3	0.75	0.000	64.50	12.489	0.64	231.55	14.316	0.64
114.00	Generic Flat Platform with	1	1.00	0.000	2,500.00	42.400	1.00	3,654.62	56.031	1.00
90.00	Empty Flat Low Profile Platform	1	1.00	0.000	1,500.00	26.100	1.00	1,910.10	38.185	1.00
82.00	Spinner 756529	3	0.75	0.000	1.50	0.142	0.50	4.90	0.324	0.50
82.00	Powerwave Allgon LGP21901	6	0.75	0.000	5.50	0.200	0.50	10.32	0.401	0.50
82.00	Powerwave Allgon LGP21401	6	0.75	0.000	14.10	1.104	0.50	29.77	1.552	0.50
82.00	Raycap DC6-48-60-18-8F(32.8	1	0.75	0.000	32.80	1.470	1.00	71.55	1.909	1.00
82.00	Ericsson RRUS 4478 B14	3	0.75	0.000	59.90	1.842	0.50	94.63	2.405	0.50
82.00	Ericsson RRUS 4449 B5, B12	3	0.75	0.000	71.00	1.969	0.50	111.48	2.555	0.50
82.00	Ericsson Radio 8843 - B2 + B66A	3	0.75	0.000	75.00	1.980	0.50	119.93	2.567	0.50
82.00	Raycap DC9-48-60-24-8C-EV	1	0.75	0.000	16.00	4.788	1.00	97.09	5.712	1.00
82.00	Powerwave Allgon 7770.00	3	0.75	0.000	35.00	5.508	0.65	112.65	6.152	0.65
82.00	CCI DMP65R-BU6DA	4	0.75	0.000	79.40	12.709	0.63	241.20	14.461	0.63
82.00	CCI DMP65R-BU8D	2	0.75	0.000	95.70	17.871	0.72	309.19	20.186	0.72
80.00	Generic Flat Platform with	1	1.00	0.000	2,500.00	42.400	1.00	3,613.51	55.546	1.00
52.00	PCTEL GPS-TMG-HR-26N	1	1.00	0.000	0.60	0.090	1.00	3.51	0.198	1.00
52.00	Stand-Off	1	1.00	0.000	100.00	3.000	0.67	129.25	3.940	0.67
Totals	Num Loadings:44	117			13,527.40			24,188.32		

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:33 PM

Customer: DISH WIRELESS L.L.C.

Linear Appurtenance Properties Load Case Azimuth (deg) : 0

Elev From (ft)	Elev To (ft)	Qty	Description	Coax Dia (in)	Coax Wt (lb/ft)	Max Coax / Flat Row	Dist Between Rows (in)	Dist Between Cols (in)	Azimuth (deg)	Dist From Face (in)	Exposed To Wind	Carrier
0.00	160.00	1	7/8" Coax	1.09	0.33	N 0	0.00	0.00	0	0.00	N	Other
0.00	155.00	1	7/8" Coax	1.09	0.33	N 0	0.00	0.00	0	0.00	N	Other
0.00	151.00	4	1 1/4" Hybriflex Cable	1.54	1.00	N 0	0.00	0.00	0	0.00	N	SPRINT NEXTEL
0.00	151.00	1	1/2" Coax	0.63	0.15	N 0	0.00	0.00	0	0.00	N	SPRINT NEXTEL
0.00	145.00	1	7/8" Coax	1.09	0.33	N 0	0.00	0.00	0	0.00	N	VERIZON WIRELESS
0.00	142.00	6	1 5/8" Coax	1.98	0.82	N 0	0.00	0.00	0	0.00	N	VERIZON WIRELESS
0.00	140.00	6	1 5/8" Coax	1.98	0.82	N 0	0.00	0.00	0	0.00	N	VERIZON WIRELESS
0.00	125.00	6	1 5/8" Coax	1.98	0.82	N 6	0.00	0.00	90	0.00	Y	T-MOBILE
0.00	125.00	12	1 5/8" Coax	1.98	0.82	N 0	0.00	0.00	0	0.00	N	T-MOBILE
0.00	125.00	18	1 5/8" Coax	1.98	0.82	N 0	0.00	0.00	0	0.00	N	T-MOBILE
0.00	125.00	1	1/2" Coax	0.63	0.15	N 0	0.00	0.00	0	0.00	N	T-MOBILE
0.00	114.00	1	1.60" (40.6mm) Hybrid	1.60	2.34	N 0	0.00	0.00	0	0.00	N	DISH WIRELESS
0.00	82.00	1	0.39" (10mm) Fiber	0.39	0.06	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	82.00	1	0.39" (10mm) Fiber	0.39	0.06	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	82.00	1	0.45" (11.5mm) Fiber	0.45	0.08	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	82.00	5	0.78" (19.7mm) 8 AWG	0.78	0.59	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	82.00	2	2" conduit	2.38	3.65	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	82.00	1	3" conduit	3.50	7.58	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	82.00	2	3" conduit	3.50	7.58	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	82.00	12	7/8" Coax	1.09	0.33	N 0	0.00	0.00	0	0.00	N	AT&T MOBILITY
0.00	52.00	1	1/2" Coax	0.63	0.15	N 1	0.00	0.00	90	0.00	Y	SPRINT NEXTEL

Segment Properties (Max Len : 5. ft)

Seg Top Elev (ft)	Description	Thick (in)	Flat Dia (in)	Area (in ²)	Ix (in ⁴)	W/t Ratio	D/t Ratio	F'y (ksi)	S (in ³)	Z (in ³)	Weight (lb)
0.00		0.4375	49.750	68.474	21,037.5	18.29	113.71	79.9	832.9	0.0	0.0
5.00		0.4375	48.608	66.888	19,609.2	17.83	111.10	80.4	794.6	0.0	1,151.5
10.00		0.4375	47.466	65.302	18,247.0	17.37	108.49	81.0	757.2	0.0	1,124.5
15.00		0.4375	46.323	63.716	16,949.5	16.91	105.88	81.5	720.7	0.0	1,097.5
20.00		0.4375	45.181	62.130	15,715.0	16.45	103.27	82.1	685.1	0.0	1,070.6
25.00		0.4375	44.039	60.544	14,541.9	15.99	100.66	82.6	650.4	0.0	1,043.6
30.00		0.4375	42.897	58.958	13,428.7	15.53	98.05	82.6	616.6	0.0	1,016.6
35.00		0.4375	41.754	57.371	12,373.8	15.07	95.44	82.6	583.7	0.0	989.6
40.00		0.4375	40.612	55.785	11,375.6	14.60	92.83	82.6	551.7	0.0	962.6
43.21	Bot - Section 2	0.4375	39.880	54.768	10,764.8	14.31	91.15	82.6	531.7	0.0	603.0
45.00		0.4375	39.470	54.199	10,432.7	14.14	90.22	82.6	520.6	0.0	623.7
48.79	Top - Section 1	0.3750	39.353	46.392	8,905.0	16.74	104.94	81.7	445.7	0.0	1,297.6
50.00		0.3750	39.078	46.064	8,717.6	16.61	104.21	81.9	439.4	0.0	189.7
52.00		0.3750	38.621	45.520	8,412.5	16.40	102.99	82.1	429.0	0.0	311.6
55.00		0.3750	37.935	44.705	7,968.3	16.07	101.16	82.5	413.7	0.0	460.5
60.00		0.3750	36.793	43.345	7,263.2	15.54	98.11	82.6	388.8	0.0	749.0
65.00		0.3750	35.651	41.986	6,601.0	15.00	95.07	82.6	364.7	0.0	725.9
70.00		0.3750	34.509	40.626	5,980.3	14.46	92.02	82.6	341.3	0.0	702.8
75.00		0.3750	33.366	39.267	5,399.8	13.93	88.98	82.6	318.7	0.0	679.6
78.67	Bot - Section 3	0.3750	32.528	38.269	4,998.6	13.53	86.74	82.6	302.7	0.0	484.0
80.00		0.3750	32.224	37.907	4,858.1	13.39	85.93	82.6	296.9	0.0	319.3
82.00		0.3750	31.767	37.363	4,652.0	13.17	84.71	82.6	288.4	0.0	474.2
83.33	Top - Section 2	0.3125	32.089	31.517	4,020.7	16.34	102.68	82.2	246.8	0.0	311.2
85.00		0.3125	31.707	31.138	3,877.5	16.13	101.46	82.4	240.9	0.0	178.2
90.00		0.3125	30.565	30.005	3,469.5	15.48	97.81	82.6	223.6	0.0	520.1
95.00		0.3125	29.422	28.872	3,091.1	14.84	94.15	82.6	206.9	0.0	500.9
100.0		0.3125	28.280	27.739	2,741.3	14.19	90.50	82.6	190.9	0.0	481.6
105.0		0.3125	27.138	26.607	2,419.0	13.55	86.84	82.6	175.6	0.0	462.3
110.0		0.3125	25.996	25.474	2,123.0	12.90	83.19	82.6	160.9	0.0	443.0
114.0	Top - Section 3	0.3125	25.082	24.568	1,904.5	12.39	80.26	82.6	149.5	0.0	340.3
114.0	Bot - Section 4	0.1880	25.082	14.854	1,163.1	21.76	133.42	75.8	91.3	0.0	0.0
114.0		0.1880	25.082	14.854	1,163.0	21.76	133.41	75.8	91.3	0.0	0.1
115.0		0.1880	24.853	14.718	1,131.3	21.55	132.20	76.1	89.7	0.0	50.3
120.0		0.1880	23.711	14.036	981.3	20.48	126.12	77.3	81.5	0.0	244.6
125.0		0.1880	22.569	13.355	845.2	19.40	120.05	78.6	73.8	0.0	233.0
130.0		0.1880	21.427	12.673	722.2	18.33	113.97	79.8	66.4	0.0	221.4
135.0		0.1880	20.284	11.991	611.9	17.26	107.90	81.1	59.4	0.0	209.8
138.0		0.1880	19.599	11.582	551.4	16.62	104.25	81.9	55.4	0.0	120.3
140.0		0.1880	19.142	11.310	513.4	16.19	101.82	82.4	52.8	0.0	77.9
142.0		0.1880	18.685	11.037	477.1	15.76	99.39	82.6	50.3	0.0	76.0
145.0		0.1880	18.000	10.628	426.0	15.12	95.74	82.6	46.6	0.0	110.6
20,659.4											

Load Case: 1.2D + 1.0W	115 mph with No Ice	24 Iterations
Gust Response Factor :1.10		
Dead Load Factor :1.20		
Wind Load Factor :1.00		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		183.1	0.0					0.0	0.0	183.1	0.0	0.0	0.0
5.00		361.9	1,381.8					0.0	505.7	361.9	1,887.6	0.0	0.0
10.00		353.4	1,349.4					0.0	505.7	353.4	1,855.2	0.0	0.0
15.00		344.9	1,317.1					0.0	505.7	344.9	1,822.8	0.0	0.0
20.00		336.4	1,284.7					0.0	505.7	336.4	1,790.4	0.0	0.0
25.00		327.9	1,252.3					0.0	505.7	327.9	1,758.0	0.0	0.0
30.00		323.2	1,219.9					0.0	505.7	323.2	1,725.6	0.0	0.0
35.00		324.9	1,187.5					0.0	505.7	324.9	1,693.3	0.0	0.0
40.00		269.1	1,155.1					0.0	505.7	269.1	1,660.9	0.0	0.0
43.21	Bot - Section 2	165.9	723.6					0.0	324.3	165.9	1,047.8	0.0	0.0
45.00		188.2	748.4					0.0	181.5	188.2	929.9	0.0	0.0
48.79	Top - Section 1	168.4	1,557.2					0.0	383.8	168.4	1,940.9	0.0	0.0
50.00		108.0	227.6					0.0	122.0	108.0	349.6	0.0	0.0
52.00	Appurtenance(s)	168.3	374.0	59.3	0.0	0.0	120.7	0.0	202.3	227.6	697.0	0.0	0.0
55.00		268.6	552.6					0.0	302.9	268.6	855.5	0.0	0.0
60.00		334.1	898.8					0.0	504.8	334.1	1,403.7	0.0	0.0
65.00		331.2	871.1					0.0	504.8	331.2	1,375.9	0.0	0.0
70.00		327.5	843.3					0.0	504.8	327.5	1,348.2	0.0	0.0
75.00		280.6	815.6					0.0	504.8	280.6	1,320.4	0.0	0.0
78.67	Bot - Section 3	161.1	580.9					0.0	370.5	161.1	951.3	0.0	0.0
80.00	Appurtenance(s)	107.8	383.1	1,353.9	0.0	0.0	3,000.0	0.0	134.4	1,461.7	3,517.5	0.0	0.0
82.00	Appurtenance(s)	107.2	569.1	2,112.1	0.0	0.0	1,683.1	0.0	201.9	2,219.3	2,454.1	0.0	0.0
83.33	Top - Section 2	96.0	373.4					0.0	74.9	96.0	448.3	0.0	0.0
85.00		210.9	213.9					0.0	94.3	210.9	308.1	0.0	0.0
90.00	Appurtenance(s)	311.7	624.2	861.9	0.0	0.0	1,800.0	0.0	281.9	1,173.6	2,706.1	0.0	0.0
95.00		304.7	601.0					0.0	281.9	304.7	883.0	0.0	0.0
100.00		297.2	577.9					0.0	281.9	297.2	859.9	0.0	0.0
105.00		289.2	554.8					0.0	281.9	289.2	836.7	0.0	0.0
110.00		253.4	531.7					0.0	281.9	253.4	813.6	0.0	0.0
114.00	Top - Section 3	110.9	408.4					0.0	225.4	110.9	633.8	0.0	0.0
114.00	Appurtenance(s)	27.4	0.2	2,339.0	0.0	0.0	3,758.5	0.0	0.1	2,366.3	3,758.8	0.0	0.0
115.00		160.9	60.4					0.0	53.6	160.9	114.0	0.0	0.0
120.00		262.5	293.5					0.0	267.9	262.5	561.4	0.0	0.0
125.00	Appurtenance(s)	252.8	279.6	1,954.3	0.0	0.0	1,425.5	0.0	267.9	2,207.2	1,973.0	0.0	0.0
130.00		242.7	265.7					0.0	89.9	242.7	355.6	0.0	0.0
135.00		187.5	251.8					0.0	89.9	187.5	341.7	0.0	0.0
138.00	Appurtenance(s)	113.5	144.4	545.6	0.0	0.0	900.0	0.0	53.9	659.1	1,098.3	0.0	0.0
140.00	Appurtenance(s)	88.6	93.5	401.6	0.0	401.6	118.8	0.0	36.0	490.2	248.2	0.0	0.0
142.00	Appurtenance(s)	108.0	91.3	1,462.2	0.0	-1,462.2	264.6	0.0	24.1	1,570.2	380.0	0.0	0.0
145.00	Appurtenance(s)	64.1	132.7	3,126.9	0.0	14,983.6	3,161.6	0.0	18.5	3,191.0	3,312.8	0.0	0.0
Totals:										23,140.7	52,018.9	0.00	0.00

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:38 PM

Customer: DISH WIRELESS L.L.C.

Load Case: 1.2D + 1.0W

115 mph with No Ice

24 Iterations

Gust Response Factor :1.10

Dead Load Factor :1.20

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-51.99	-23.03	0.00	-2,397.84	0.00	2,397.84	4,923.42	1,201.72	5,352.67	4,990.47	0.00	0.00	0.491
5.00	-50.04	-22.81	0.00	-2,282.69	0.00	2,282.69	4,841.97	1,173.88	5,107.60	4,793.23	0.08	-0.16	0.487
10.00	-48.12	-22.58	0.00	-2,168.67	0.00	2,168.67	4,758.98	1,146.05	4,868.28	4,598.35	0.34	-0.32	0.482
15.00	-46.23	-22.36	0.00	-2,055.76	0.00	2,055.76	4,674.44	1,118.21	4,634.70	4,405.95	0.76	-0.48	0.477
20.00	-44.38	-22.13	0.00	-1,943.98	0.00	1,943.98	4,588.36	1,090.38	4,406.86	4,216.14	1.36	-0.65	0.471
25.00	-42.56	-21.91	0.00	-1,833.31	0.00	1,833.31	4,498.09	1,062.54	4,184.76	4,026.66	2.13	-0.82	0.465
30.00	-40.77	-21.69	0.00	-1,723.75	0.00	1,723.75	4,380.25	1,034.71	3,968.40	3,817.43	3.09	-1.00	0.461
35.00	-39.02	-21.45	0.00	-1,615.32	0.00	1,615.32	4,262.42	1,006.87	3,757.79	3,613.78	4.23	-1.17	0.457
40.00	-37.31	-21.24	0.00	-1,508.06	0.00	1,508.06	4,144.58	979.03	3,552.92	3,415.71	5.55	-1.35	0.451
43.21	-36.23	-21.11	0.00	-1,439.97	0.00	1,439.97	4,069.03	961.19	3,424.59	3,291.66	6.50	-1.47	0.447
45.00	-35.27	-20.96	0.00	-1,402.09	0.00	1,402.09	4,026.74	951.20	3,353.79	3,223.22	7.07	-1.54	0.444
48.79	-33.30	-20.79	0.00	-1,322.56	0.00	1,322.56	3,411.63	814.18	2,866.55	2,731.35	8.35	-1.68	0.495
50.00	-32.93	-20.71	0.00	-1,297.49	0.00	1,297.49	3,393.84	808.42	2,826.18	2,697.72	8.78	-1.73	0.491
52.00	-32.21	-20.52	0.00	-1,256.07	0.00	1,256.07	3,364.13	798.88	2,759.86	2,642.23	9.52	-1.81	0.486
55.00	-31.30	-20.31	0.00	-1,194.51	0.00	1,194.51	3,319.09	784.57	2,661.85	2,559.69	10.70	-1.93	0.477
60.00	-29.84	-20.04	0.00	-1,092.94	0.00	1,092.94	3,220.32	760.71	2,502.44	2,407.25	12.83	-2.14	0.464
65.00	-28.41	-19.75	0.00	-992.76	0.00	992.76	3,119.32	736.85	2,347.95	2,257.87	15.18	-2.34	0.450
70.00	-27.01	-19.46	0.00	-893.99	0.00	893.99	3,018.31	712.99	2,198.38	2,113.27	17.74	-2.55	0.433
75.00	-25.64	-19.20	0.00	-796.67	0.00	796.67	2,917.31	689.13	2,053.73	1,973.46	20.52	-2.75	0.413
78.67	-24.67	-19.04	0.00	-726.22	0.00	726.22	2,843.19	671.62	1,950.71	1,873.90	22.69	-2.89	0.397
80.00	-21.21	-17.42	0.00	-700.89	0.00	700.89	2,816.31	665.27	1,914.01	1,838.43	23.50	-2.95	0.389
82.00	-18.86	-15.10	0.00	-666.04	0.00	666.04	2,775.90	655.73	1,859.49	1,785.76	24.75	-3.03	0.380
83.33	-18.40	-15.00	0.00	-645.99	0.00	645.99	2,331.02	553.12	1,587.63	1,521.08	25.60	-3.08	0.433
85.00	-18.06	-14.82	0.00	-620.92	0.00	620.92	2,310.11	546.48	1,549.70	1,489.14	26.69	-3.15	0.426
90.00	-15.38	-13.55	0.00	-546.83	0.00	546.83	2,229.24	526.59	1,439.00	1,384.22	30.10	-3.36	0.403
95.00	-14.47	-13.24	0.00	-479.09	0.00	479.09	2,145.07	506.71	1,332.40	1,281.15	33.74	-3.57	0.381
100.00	-13.58	-12.94	0.00	-412.88	0.00	412.88	2,060.90	486.83	1,229.90	1,182.06	37.59	-3.78	0.357
105.00	-12.73	-12.64	0.00	-348.18	0.00	348.18	1,976.73	466.94	1,131.51	1,086.97	41.65	-3.98	0.327
110.00	-11.90	-12.36	0.00	-285.00	0.00	285.00	1,892.56	447.06	1,037.22	995.86	45.91	-4.16	0.293
114.00	-11.26	-12.22	0.00	-235.59	0.00	235.59	1,825.27	431.17	964.78	925.89	49.45	-4.30	0.261
114.00	-11.26	-12.22	0.00	-235.59	0.00	235.59	1,013.43	260.69	586.17	519.26	49.45	-4.30	0.467
114.00	-7.68	-9.58	0.00	-235.56	0.00	235.56	1,013.41	260.69	586.14	519.24	49.46	-4.30	0.463
115.00	-7.56	-9.43	0.00	-225.98	0.00	225.98	1,007.45	258.29	575.44	511.41	50.36	-4.36	0.451
120.00	-6.98	-9.15	0.00	-178.83	0.00	178.83	976.71	246.33	523.38	472.67	55.06	-4.61	0.387
125.00	-5.17	-6.81	0.00	-133.06	0.00	133.06	944.43	234.37	473.79	434.68	60.01	-4.84	0.312
130.00	-4.82	-6.55	0.00	-99.00	0.00	99.00	910.60	222.41	426.67	397.54	65.18	-5.03	0.255
135.00	-4.48	-6.35	0.00	-66.24	0.00	66.24	875.23	210.45	382.02	361.37	70.54	-5.20	0.189
138.00	-3.44	-5.59	0.00	-47.20	0.00	47.20	853.26	203.27	356.41	340.17	73.82	-5.27	0.144
140.00	-3.23	-5.08	0.00	-35.61	0.00	35.61	838.31	198.49	339.83	326.27	76.04	-5.32	0.114
142.00	-3.00	-3.49	0.00	-25.44	0.00	25.44	820.01	193.70	323.65	311.38	78.27	-5.35	0.086
145.00	0.00	-3.19	0.00	-14.98	0.00	14.98	789.63	186.53	300.11	288.62	81.64	-5.39	0.052

Load Case: 0.9D + 1.0W	115 mph with No Ice (Reduced DL)	24 Iterations
Gust Response Factor :1.10		
Dead Load Factor :0.90		
Wind Load Factor :1.00		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		183.1	0.0					0.0	0.0	183.1	0.0	0.0	0.0
5.00		361.9	1,036.4					0.0	379.3	361.9	1,415.7	0.0	0.0
10.00		353.4	1,012.1					0.0	379.3	353.4	1,391.4	0.0	0.0
15.00		344.9	987.8					0.0	379.3	344.9	1,367.1	0.0	0.0
20.00		336.4	963.5					0.0	379.3	336.4	1,342.8	0.0	0.0
25.00		327.9	939.2					0.0	379.3	327.9	1,318.5	0.0	0.0
30.00		323.2	914.9					0.0	379.3	323.2	1,294.2	0.0	0.0
35.00		324.9	890.6					0.0	379.3	324.9	1,269.9	0.0	0.0
40.00		269.1	866.4					0.0	379.3	269.1	1,245.7	0.0	0.0
43.21	Bot - Section 2	165.9	542.7					0.0	243.2	165.9	785.9	0.0	0.0
45.00		188.2	561.3					0.0	136.1	188.2	697.4	0.0	0.0
48.79	Top - Section 1	168.4	1,167.9					0.0	287.8	168.4	1,455.7	0.0	0.0
50.00		108.0	170.7					0.0	91.5	108.0	262.2	0.0	0.0
52.00	Appurtenance(s)	168.3	280.5	59.3	0.0	0.0	90.5	0.0	151.7	227.6	522.7	0.0	0.0
55.00		268.6	414.5					0.0	227.2	268.6	641.6	0.0	0.0
60.00		334.1	674.1					0.0	378.6	334.1	1,052.8	0.0	0.0
65.00		331.2	653.3					0.0	378.6	331.2	1,031.9	0.0	0.0
70.00		327.5	632.5					0.0	378.6	327.5	1,011.1	0.0	0.0
75.00		280.6	611.7					0.0	378.6	280.6	990.3	0.0	0.0
78.67	Bot - Section 3	161.1	435.6					0.0	277.9	161.1	713.5	0.0	0.0
80.00	Appurtenance(s)	107.8	287.4	1,353.9	0.0	0.0	2,250.0	0.0	100.8	1,461.7	2,638.1	0.0	0.0
82.00	Appurtenance(s)	107.2	426.8	2,112.1	0.0	0.0	1,262.3	0.0	151.5	2,219.3	1,840.6	0.0	0.0
83.33	Top - Section 2	96.0	280.0					0.0	56.2	96.0	336.2	0.0	0.0
85.00		210.9	160.4					0.0	70.7	210.9	231.1	0.0	0.0
90.00	Appurtenance(s)	311.7	468.1	861.9	0.0	0.0	1,350.0	0.0	211.5	1,173.6	2,029.6	0.0	0.0
95.00		304.7	450.8					0.0	211.5	304.7	662.2	0.0	0.0
100.00		297.2	433.4					0.0	211.5	297.2	644.9	0.0	0.0
105.00		289.2	416.1					0.0	211.5	289.2	627.5	0.0	0.0
110.00		253.4	398.7					0.0	211.5	253.4	610.2	0.0	0.0
114.00	Top - Section 3	110.9	306.3					0.0	169.1	110.9	475.4	0.0	0.0
114.00	Appurtenance(s)	27.4	0.1	2,339.0	0.0	0.0	2,818.9	0.0	0.1	2,366.3	2,819.1	0.0	0.0
115.00		160.9	45.3					0.0	40.2	160.9	85.5	0.0	0.0
120.00		262.5	220.1					0.0	200.9	262.5	421.1	0.0	0.0
125.00	Appurtenance(s)	252.8	209.7	1,954.3	0.0	0.0	1,069.1	0.0	200.9	2,207.2	1,479.7	0.0	0.0
130.00		242.7	199.3					0.0	67.4	242.7	266.7	0.0	0.0
135.00		187.5	188.8					0.0	67.4	187.5	256.2	0.0	0.0
138.00	Appurtenance(s)	113.5	108.3	545.6	0.0	0.0	675.0	0.0	40.4	659.1	823.7	0.0	0.0
140.00	Appurtenance(s)	88.6	70.1	401.6	0.0	401.6	89.1	0.0	27.0	490.2	186.2	0.0	0.0
142.00	Appurtenance(s)	108.0	68.4	1,462.2	0.0	-1,462.2	198.4	0.0	18.1	1,570.2	285.0	0.0	0.0
145.00	Appurtenance(s)	64.1	99.5	3,126.9	0.0	14,983.6	2,371.2	0.0	13.9	3,191.0	2,484.6	0.0	0.0
Totals:										23,140.7	39,014.2	0.00	0.00

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:43 PM

Customer: DISH WIRELESS L.L.C.

Load Case: 0.9D + 1.0W

115 mph with No Ice (Reduced DL)

24 Iterations

Gust Response Factor :1.10

Dead Load Factor :0.90

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-38.98	-23.01	0.00	-2,367.63	0.00	2,367.63	4,923.42	1,201.72	5,352.67	4,990.47	0.00	0.00	0.483
5.00	-37.50	-22.75	0.00	-2,252.57	0.00	2,252.57	4,841.97	1,173.88	5,107.60	4,793.23	0.08	-0.16	0.478
10.00	-36.05	-22.49	0.00	-2,138.82	0.00	2,138.82	4,758.98	1,146.05	4,868.28	4,598.35	0.33	-0.32	0.473
15.00	-34.62	-22.24	0.00	-2,026.36	0.00	2,026.36	4,674.44	1,118.21	4,634.70	4,405.95	0.75	-0.48	0.468
20.00	-33.22	-21.98	0.00	-1,915.18	0.00	1,915.18	4,588.36	1,090.38	4,406.86	4,216.14	1.34	-0.64	0.462
25.00	-31.84	-21.73	0.00	-1,805.26	0.00	1,805.26	4,498.09	1,062.54	4,184.76	4,026.66	2.10	-0.81	0.456
30.00	-30.49	-21.48	0.00	-1,696.59	0.00	1,696.59	4,380.25	1,034.71	3,968.40	3,817.43	3.05	-0.98	0.452
35.00	-29.16	-21.22	0.00	-1,589.17	0.00	1,589.17	4,262.42	1,006.87	3,757.79	3,613.78	4.17	-1.16	0.447
40.00	-27.87	-21.00	0.00	-1,483.05	0.00	1,483.05	4,144.58	979.03	3,552.92	3,415.71	5.48	-1.33	0.441
43.21	-27.05	-20.86	0.00	-1,415.74	0.00	1,415.74	4,069.03	961.19	3,424.59	3,291.66	6.41	-1.45	0.437
45.00	-26.32	-20.70	0.00	-1,378.32	0.00	1,378.32	4,026.74	951.20	3,353.79	3,223.22	6.97	-1.52	0.435
48.79	-24.84	-20.53	0.00	-1,299.79	0.00	1,299.79	3,411.63	814.18	2,866.55	2,731.35	8.23	-1.65	0.484
50.00	-24.56	-20.44	0.00	-1,275.03	0.00	1,275.03	3,393.84	808.42	2,826.18	2,697.72	8.65	-1.70	0.481
52.00	-24.01	-20.24	0.00	-1,234.15	0.00	1,234.15	3,364.13	798.88	2,759.86	2,642.23	9.38	-1.78	0.475
55.00	-23.32	-20.02	0.00	-1,173.43	0.00	1,173.43	3,319.09	784.57	2,661.85	2,559.69	10.54	-1.90	0.466
60.00	-22.21	-19.72	0.00	-1,073.35	0.00	1,073.35	3,220.32	760.71	2,502.44	2,407.25	12.64	-2.10	0.453
65.00	-21.12	-19.43	0.00	-974.73	0.00	974.73	3,119.32	736.85	2,347.95	2,257.87	14.96	-2.30	0.439
70.00	-20.06	-19.13	0.00	-877.60	0.00	877.60	3,018.31	712.99	2,198.38	2,113.27	17.48	-2.50	0.423
75.00	-19.03	-18.86	0.00	-781.96	0.00	781.96	2,917.31	689.13	2,053.73	1,973.46	20.21	-2.70	0.404
78.67	-18.29	-18.69	0.00	-712.76	0.00	712.76	2,843.19	671.62	1,950.71	1,873.90	22.34	-2.85	0.388
80.00	-15.71	-17.12	0.00	-687.89	0.00	687.89	2,816.31	665.27	1,914.01	1,838.43	23.14	-2.90	0.380
82.00	-13.97	-14.83	0.00	-653.65	0.00	653.65	2,775.90	655.73	1,859.49	1,785.76	24.37	-2.98	0.372
83.33	-13.62	-14.73	0.00	-633.96	0.00	633.96	2,331.02	553.12	1,587.63	1,521.08	25.21	-3.03	0.423
85.00	-13.37	-14.54	0.00	-609.34	0.00	609.34	2,310.11	546.48	1,549.70	1,489.14	26.28	-3.10	0.416
90.00	-11.36	-13.29	0.00	-536.66	0.00	536.66	2,229.24	526.59	1,439.00	1,384.22	29.63	-3.31	0.393
95.00	-10.67	-12.99	0.00	-470.20	0.00	470.20	2,145.07	506.71	1,332.40	1,281.15	33.21	-3.51	0.373
100.00	-10.00	-12.68	0.00	-405.27	0.00	405.27	2,060.90	486.83	1,229.90	1,182.06	36.99	-3.71	0.348
105.00	-9.35	-12.38	0.00	-341.85	0.00	341.85	1,976.73	466.94	1,131.51	1,086.97	40.98	-3.91	0.320
110.00	-8.73	-12.11	0.00	-279.93	0.00	279.93	1,892.56	447.06	1,037.22	995.86	45.17	-4.09	0.286
114.00	-8.25	-11.98	0.00	-231.51	0.00	231.51	1,825.27	431.17	964.78	925.89	48.66	-4.23	0.255
114.00	-8.25	-11.98	0.00	-231.51	0.00	231.51	1,013.43	260.69	586.17	519.26	48.66	-4.23	0.456
114.00	-5.61	-9.41	0.00	-231.47	0.00	231.47	1,013.41	260.69	586.14	519.24	48.66	-4.23	0.453
115.00	-5.51	-9.26	0.00	-222.06	0.00	222.06	1,007.45	258.29	575.44	511.41	49.55	-4.28	0.441
120.00	-5.07	-8.99	0.00	-175.76	0.00	175.76	976.71	246.33	523.38	472.67	54.17	-4.53	0.378
125.00	-3.75	-6.68	0.00	-130.81	0.00	130.81	944.43	234.37	473.79	434.68	59.04	-4.76	0.306
130.00	-3.49	-6.43	0.00	-97.41	0.00	97.41	910.60	222.41	426.67	397.54	64.12	-4.95	0.250
135.00	-3.23	-6.23	0.00	-65.26	0.00	65.26	875.23	210.45	382.02	361.37	69.38	-5.11	0.185
138.00	-2.47	-5.50	0.00	-46.59	0.00	46.59	853.26	203.27	356.41	340.17	72.61	-5.19	0.141
140.00	-2.32	-4.99	0.00	-35.19	0.00	35.19	838.31	198.49	339.83	326.27	74.79	-5.23	0.111
142.00	-2.18	-3.41	0.00	-25.20	0.00	25.20	820.01	193.70	323.65	311.38	76.99	-5.26	0.084
145.00	0.00	-3.19	0.00	-14.98	0.00	14.98	789.63	186.53	300.11	288.62	80.30	-5.30	0.052

Load Case: 1.2D + 1.0Di + 1.0Wi	50 mph with 1.00 in Radial Ice	24 Iterations
Gust Response Factor :1.10	Ice Dead Load Factor :1.00	
Dead Load Factor :1.20		Ice Importance Factor :1.00
Wind Load Factor :1.00		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		58.7	0.0					0.0	0.0	58.7	0.0	0.0	0.0
5.00		116.2	1,620.8					0.0	544.1	116.2	2,164.9	0.0	0.0
10.00		113.9	1,610.5					0.0	547.8	113.9	2,158.3	0.0	0.0
15.00		111.4	1,585.6					0.0	549.7	111.4	2,135.3	0.0	0.0
20.00		108.9	1,555.8					0.0	551.0	108.9	2,106.9	0.0	0.0
25.00		106.3	1,523.6					0.0	552.1	106.3	2,075.7	0.0	0.0
30.00		105.0	1,489.8					0.0	552.9	105.0	2,042.7	0.0	0.0
35.00		105.8	1,454.9					0.0	553.6	105.8	2,008.6	0.0	0.0
40.00		87.7	1,419.3					0.0	554.3	87.7	1,973.5	0.0	0.0
43.21	Bot - Section 2	54.1	891.7					0.0	355.7	54.1	1,247.4	0.0	0.0
45.00		61.4	843.9					0.0	199.2	61.4	1,043.0	0.0	0.0
48.79	Top - Section 1	55.0	1,756.0					0.0	421.4	55.0	2,177.4	0.0	0.0
50.00		35.3	290.7					0.0	134.0	35.3	424.7	0.0	0.0
52.00	Appurtenance(s)	55.1	477.8	15.1	0.0	0.0	145.2	0.0	222.3	70.3	845.2	0.0	0.0
55.00		88.1	706.4					0.0	330.8	88.1	1,037.2	0.0	0.0
60.00		109.7	1,149.5					0.0	551.6	109.7	1,701.0	0.0	0.0
65.00		109.0	1,116.2					0.0	551.9	109.0	1,668.1	0.0	0.0
70.00		108.0	1,082.7					0.0	552.2	108.0	1,635.0	0.0	0.0
75.00		92.7	1,049.0					0.0	552.5	92.7	1,601.5	0.0	0.0
78.67	Bot - Section 3	53.3	749.0					0.0	405.7	53.3	1,154.7	0.0	0.0
80.00	Appurtenance(s)	35.7	444.9	335.3	0.0	0.0	3,858.5	0.0	147.2	371.0	4,450.6	0.0	0.0
82.00	Appurtenance(s)	35.5	660.8	468.5	0.0	0.0	3,218.0	0.0	221.2	504.0	4,100.0	0.0	0.0
83.33	Top - Section 2	31.8	433.9					0.0	87.7	31.8	521.6	0.0	0.0
85.00		70.1	289.3					0.0	110.4	70.1	399.8	0.0	0.0
90.00	Appurtenance(s)	103.8	842.8	238.4	0.0	0.0	2,117.1	0.0	330.4	342.1	3,290.4	0.0	0.0
95.00		101.7	813.0					0.0	330.7	101.7	1,143.7	0.0	0.0
100.00		99.5	783.1					0.0	330.9	99.5	1,114.0	0.0	0.0
105.00		97.2	753.0					0.0	331.1	97.2	1,084.1	0.0	0.0
110.00		85.4	722.8					0.0	331.3	85.4	1,054.1	0.0	0.0
114.00	Top - Section 3	37.5	556.7					0.0	265.0	37.5	821.7	0.0	0.0
114.00	Appurtenance(s)	9.3	0.3	562.7	0.0	0.0	5,261.2	0.0	0.2	571.9	5,261.6	0.0	0.0
115.00		54.6	97.2					0.0	63.5	54.6	160.8	0.0	0.0
120.00		89.3	470.2					0.0	317.7	89.3	787.9	0.0	0.0
125.00	Appurtenance(s)	86.4	448.9	484.5	0.0	0.0	2,430.1	0.0	317.9	570.9	3,196.9	0.0	0.0
130.00		83.4	427.5					0.0	89.9	83.4	517.4	0.0	0.0
135.00		64.7	406.0					0.0	89.9	64.7	495.9	0.0	0.0
138.00	Appurtenance(s)	39.3	234.2	161.2	0.0	0.0	1,224.9	0.0	53.9	200.5	1,513.1	0.0	0.0
140.00	Appurtenance(s)	30.8	152.2	97.8	0.0	97.8	394.1	0.0	36.0	128.6	582.2	0.0	0.0
142.00	Appurtenance(s)	37.7	148.7	327.2	0.0	-327.2	1,140.8	0.0	24.1	364.8	1,313.7	0.0	0.0
145.00	Appurtenance(s)	22.4	216.1	810.1	0.0	3,896.9	4,796.7	0.0	18.5	832.5	5,031.2	0.0	0.0
Totals:										6,452.56	68,041.6	0.00	0.00

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:48 PM

Customer: DISH WIRELESS L.L.C.

Load Case: 1.2D + 1.0Di + 1.0Wi

50 mph with 1.00 in Radial Ice

24 Iterations

Gust Response Factor :1.10

Ice Dead Load Factor :1.00

Dead Load Factor :1.20

Ice Importance Factor :1.00

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-68.04	-6.42	0.00	-664.57	0.00	664.57	4,923.42	1,201.72	5,352.67	4,990.47	0.00	0.00	0.147
5.00	-65.87	-6.35	0.00	-632.47	0.00	632.47	4,841.97	1,173.88	5,107.60	4,793.23	0.02	-0.04	0.146
10.00	-63.71	-6.29	0.00	-600.70	0.00	600.70	4,758.98	1,146.05	4,868.28	4,598.35	0.09	-0.09	0.144
15.00	-61.57	-6.22	0.00	-569.26	0.00	569.26	4,674.44	1,118.21	4,634.70	4,405.95	0.21	-0.13	0.142
20.00	-59.45	-6.16	0.00	-538.15	0.00	538.15	4,588.36	1,090.38	4,406.86	4,216.14	0.38	-0.18	0.141
25.00	-57.37	-6.09	0.00	-507.37	0.00	507.37	4,498.09	1,062.54	4,184.76	4,026.66	0.59	-0.23	0.139
30.00	-55.33	-6.02	0.00	-476.92	0.00	476.92	4,380.25	1,034.71	3,968.40	3,817.43	0.86	-0.28	0.138
35.00	-53.31	-5.95	0.00	-446.81	0.00	446.81	4,262.42	1,006.87	3,757.79	3,613.78	1.17	-0.33	0.136
40.00	-51.34	-5.89	0.00	-417.05	0.00	417.05	4,144.58	979.03	3,552.92	3,415.71	1.54	-0.37	0.135
43.21	-50.09	-5.85	0.00	-398.17	0.00	398.17	4,069.03	961.19	3,424.59	3,291.66	1.80	-0.41	0.133
45.00	-49.04	-5.80	0.00	-387.67	0.00	387.67	4,026.74	951.20	3,353.79	3,223.22	1.96	-0.43	0.132
48.79	-46.86	-5.75	0.00	-365.65	0.00	365.65	3,411.63	814.18	2,866.55	2,731.35	2.31	-0.46	0.148
50.00	-46.44	-5.73	0.00	-358.71	0.00	358.71	3,393.84	808.42	2,826.18	2,697.72	2.43	-0.48	0.147
52.00	-45.59	-5.68	0.00	-347.25	0.00	347.25	3,364.13	798.88	2,759.86	2,642.23	2.64	-0.50	0.145
55.00	-44.55	-5.61	0.00	-330.23	0.00	330.23	3,319.09	784.57	2,661.85	2,559.69	2.96	-0.54	0.142
60.00	-42.84	-5.53	0.00	-302.16	0.00	302.16	3,220.32	760.71	2,502.44	2,407.25	3.55	-0.59	0.139
65.00	-41.17	-5.44	0.00	-274.52	0.00	274.52	3,119.32	736.85	2,347.95	2,257.87	4.20	-0.65	0.135
70.00	-39.53	-5.35	0.00	-247.31	0.00	247.31	3,018.31	712.99	2,198.38	2,113.27	4.91	-0.70	0.130
75.00	-37.93	-5.27	0.00	-220.54	0.00	220.54	2,917.31	689.13	2,053.73	1,973.46	5.68	-0.76	0.125
78.67	-36.77	-5.22	0.00	-201.20	0.00	201.20	2,843.19	671.62	1,950.71	1,873.90	6.28	-0.80	0.120
80.00	-32.32	-4.80	0.00	-194.25	0.00	194.25	2,816.31	665.27	1,914.01	1,838.43	6.51	-0.82	0.117
82.00	-28.23	-4.24	0.00	-184.65	0.00	184.65	2,775.90	655.73	1,859.49	1,785.76	6.85	-0.84	0.114
83.33	-27.71	-4.21	0.00	-179.02	0.00	179.02	2,331.02	553.12	1,587.63	1,521.08	7.09	-0.85	0.130
85.00	-27.31	-4.15	0.00	-171.98	0.00	171.98	2,310.11	546.48	1,549.70	1,489.14	7.39	-0.87	0.127
90.00	-24.02	-3.79	0.00	-151.20	0.00	151.20	2,229.24	526.59	1,439.00	1,384.22	8.33	-0.93	0.120
95.00	-22.87	-3.69	0.00	-132.28	0.00	132.28	2,145.07	506.71	1,332.40	1,281.15	9.34	-0.99	0.114
100.00	-21.76	-3.59	0.00	-113.84	0.00	113.84	2,060.90	486.83	1,229.90	1,182.06	10.41	-1.05	0.107
105.00	-20.67	-3.49	0.00	-95.89	0.00	95.89	1,976.73	466.94	1,131.51	1,086.97	11.53	-1.10	0.099
110.00	-19.62	-3.40	0.00	-78.44	0.00	78.44	1,892.56	447.06	1,037.22	995.86	12.71	-1.15	0.089
114.00	-18.80	-3.35	0.00	-64.85	0.00	64.85	1,825.27	431.17	964.78	925.89	13.69	-1.19	0.080
114.00	-18.80	-3.35	0.00	-64.85	0.00	64.85	1,013.43	260.69	586.17	519.26	13.69	-1.19	0.144
114.00	-13.55	-2.67	0.00	-64.84	0.00	64.84	1,013.41	260.69	586.14	519.24	13.69	-1.19	0.138
115.00	-13.38	-2.63	0.00	-62.16	0.00	62.16	1,007.45	258.29	575.44	511.41	13.94	-1.20	0.135
120.00	-12.60	-2.53	0.00	-49.04	0.00	49.04	976.71	246.33	523.38	472.67	15.24	-1.27	0.117
125.00	-9.41	-1.90	0.00	-36.37	0.00	36.37	944.43	234.37	473.79	434.68	16.61	-1.34	0.094
130.00	-8.89	-1.81	0.00	-26.88	0.00	26.88	910.60	222.41	426.67	397.54	18.04	-1.39	0.077
135.00	-8.40	-1.74	0.00	-17.82	0.00	17.82	875.23	210.45	382.02	361.37	19.52	-1.43	0.059
138.00	-6.89	-1.50	0.00	-12.61	0.00	12.61	853.26	203.27	356.41	340.17	20.43	-1.46	0.045
140.00	-6.31	-1.36	0.00	-9.50	0.00	9.50	838.31	198.49	339.83	326.27	21.04	-1.47	0.037
142.00	-5.01	-0.96	0.00	-6.78	0.00	6.78	820.01	193.70	323.65	311.38	21.66	-1.48	0.028
145.00	0.00	-0.83	0.00	-3.90	0.00	3.90	789.63	186.53	300.11	288.62	22.59	-1.49	0.014

Load Case: 1.0D + 1.0W	Serviceability 60 mph	23 Iterations
Gust Response Factor :1.10		
Dead Load Factor :1.00		
Wind Load Factor :1.00		

Applied Segment Forces Summary

Seg Elev (ft)	Description	Shaft Forces		Discrete Forces			Linear Forces		Sum of Forces				
		Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Torsion MY (lb-ft)	Moment MZ (lb-ft)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Wind FX (lb)	Dead Load (lb)	Torsion MY (lb-ft)	Moment MZ (lb)
0.00		44.6	0.0					0.0	0.0	44.6	0.0	0.0	0.0
5.00		88.1	1,151.5					0.0	421.5	88.1	1,573.0	0.0	0.0
10.00		86.1	1,124.5					0.0	421.5	86.1	1,546.0	0.0	0.0
15.00		84.0	1,097.5					0.0	421.5	84.0	1,519.0	0.0	0.0
20.00		81.9	1,070.6					0.0	421.5	81.9	1,492.0	0.0	0.0
25.00		79.9	1,043.6					0.0	421.5	79.9	1,465.0	0.0	0.0
30.00		78.7	1,016.6					0.0	421.5	78.7	1,438.0	0.0	0.0
35.00		79.1	989.6					0.0	421.5	79.1	1,411.1	0.0	0.0
40.00		65.5	962.6					0.0	421.5	65.5	1,384.1	0.0	0.0
43.21	Bot - Section 2	40.4	603.0					0.0	270.2	40.4	873.2	0.0	0.0
45.00		45.8	623.7					0.0	151.2	45.8	774.9	0.0	0.0
48.79	Top - Section 1	41.0	1,297.6					0.0	319.8	41.0	1,617.4	0.0	0.0
50.00		26.3	189.7					0.0	101.6	26.3	291.3	0.0	0.0
52.00	Appurtenance(s)	41.0	311.6	14.4	0.0	0.0	100.6	0.0	168.6	55.4	580.8	0.0	0.0
55.00		65.4	460.5					0.0	252.4	65.4	712.9	0.0	0.0
60.00		81.4	749.0					0.0	420.7	81.4	1,169.7	0.0	0.0
65.00		80.7	725.9					0.0	420.7	80.7	1,146.6	0.0	0.0
70.00		79.8	702.8					0.0	420.7	79.8	1,123.5	0.0	0.0
75.00		68.3	679.6					0.0	420.7	68.3	1,100.3	0.0	0.0
78.67	Bot - Section 3	39.2	484.0					0.0	308.7	39.2	792.8	0.0	0.0
80.00	Appurtenance(s)	26.3	319.3	329.8	0.0	0.0	2,500.0	0.0	112.0	356.0	2,931.3	0.0	0.0
82.00	Appurtenance(s)	26.1	474.2	514.4	0.0	0.0	1,402.6	0.0	168.3	540.5	2,045.1	0.0	0.0
83.33	Top - Section 2	23.4	311.2					0.0	62.4	23.4	373.6	0.0	0.0
85.00		51.4	178.2					0.0	78.6	51.4	256.8	0.0	0.0
90.00	Appurtenance(s)	75.9	520.1	209.9	0.0	0.0	1,500.0	0.0	235.0	285.8	2,255.1	0.0	0.0
95.00		74.2	500.9					0.0	235.0	74.2	735.8	0.0	0.0
100.00		72.4	481.6					0.0	235.0	72.4	716.5	0.0	0.0
105.00		70.4	462.3					0.0	235.0	70.4	697.3	0.0	0.0
110.00		61.7	443.0					0.0	235.0	61.7	678.0	0.0	0.0
114.00	Top - Section 3	27.0	340.3					0.0	187.8	27.0	528.2	0.0	0.0
114.00	Appurtenance(s)	6.7	0.1	569.7	0.0	0.0	3,132.1	0.0	0.1	576.3	3,132.4	0.0	0.0
115.00		39.2	50.3					0.0	44.7	39.2	95.0	0.0	0.0
120.00		63.9	244.6					0.0	223.3	63.9	467.9	0.0	0.0
125.00	Appurtenance(s)	61.6	233.0	476.0	0.0	0.0	1,187.9	0.0	223.3	537.6	1,644.2	0.0	0.0
130.00		59.1	221.4					0.0	74.9	59.1	296.3	0.0	0.0
135.00		45.7	209.8					0.0	74.9	45.7	284.7	0.0	0.0
138.00	Appurtenance(s)	27.6	120.3	132.9	0.0	0.0	750.0	0.0	44.9	160.5	915.3	0.0	0.0
140.00	Appurtenance(s)	21.6	77.9	97.8	0.0	97.8	99.0	0.0	30.0	119.4	206.9	0.0	0.0
142.00	Appurtenance(s)	26.3	76.0	356.1	0.0	-356.1	220.5	0.0	20.1	382.4	316.7	0.0	0.0
145.00	Appurtenance(s)	15.6	110.6	761.6	0.0	3,649.4	2,634.7	0.0	15.4	777.2	2,760.7	0.0	0.0
Totals:										5,636.10	43,349.1	0.00	0.00

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:53 PM

Customer: DISH WIRELESS L.L.C.

Load Case: 1.0D + 1.0W

Serviceability 60 mph

23 Iterations

Gust Response Factor :1.10

Dead Load Factor :1.00

Wind Load Factor :1.00

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-43.35	-5.61	0.00	-579.56	0.00	579.56	4,923.42	1,201.72	5,352.67	4,990.47	0.00	0.00	0.125
5.00	-41.77	-5.54	0.00	-551.53	0.00	551.53	4,841.97	1,173.88	5,107.60	4,793.23	0.02	-0.04	0.124
10.00	-40.22	-5.48	0.00	-523.81	0.00	523.81	4,758.98	1,146.05	4,868.28	4,598.35	0.08	-0.08	0.122
15.00	-38.70	-5.43	0.00	-496.38	0.00	496.38	4,674.44	1,118.21	4,634.70	4,405.95	0.18	-0.12	0.121
20.00	-37.20	-5.37	0.00	-469.25	0.00	469.25	4,588.36	1,090.38	4,406.86	4,216.14	0.33	-0.16	0.119
25.00	-35.73	-5.31	0.00	-442.42	0.00	442.42	4,498.09	1,062.54	4,184.76	4,026.66	0.52	-0.20	0.118
30.00	-34.29	-5.25	0.00	-415.88	0.00	415.88	4,380.25	1,034.71	3,968.40	3,817.43	0.75	-0.24	0.117
35.00	-32.88	-5.19	0.00	-389.64	0.00	389.64	4,262.42	1,006.87	3,757.79	3,613.78	1.02	-0.28	0.116
40.00	-31.49	-5.14	0.00	-363.70	0.00	363.70	4,144.58	979.03	3,552.92	3,415.71	1.34	-0.33	0.114
43.21	-30.62	-5.10	0.00	-347.24	0.00	347.24	4,069.03	961.19	3,424.59	3,291.66	1.57	-0.36	0.113
45.00	-29.84	-5.06	0.00	-338.08	0.00	338.08	4,026.74	951.20	3,353.79	3,223.22	1.71	-0.37	0.112
48.79	-28.22	-5.02	0.00	-318.87	0.00	318.87	3,411.63	814.18	2,866.55	2,731.35	2.02	-0.41	0.125
50.00	-27.93	-5.00	0.00	-312.81	0.00	312.81	3,393.84	808.42	2,826.18	2,697.72	2.12	-0.42	0.124
52.00	-27.35	-4.95	0.00	-302.81	0.00	302.81	3,364.13	798.88	2,759.86	2,642.23	2.30	-0.44	0.123
55.00	-26.63	-4.90	0.00	-287.95	0.00	287.95	3,319.09	784.57	2,661.85	2,559.69	2.58	-0.47	0.121
60.00	-25.46	-4.83	0.00	-263.44	0.00	263.44	3,220.32	760.71	2,502.44	2,407.25	3.10	-0.52	0.117
65.00	-24.31	-4.76	0.00	-239.28	0.00	239.28	3,119.32	736.85	2,347.95	2,257.87	3.67	-0.57	0.114
70.00	-23.18	-4.69	0.00	-215.47	0.00	215.47	3,018.31	712.99	2,198.38	2,113.27	4.28	-0.61	0.110
75.00	-22.08	-4.63	0.00	-192.02	0.00	192.02	2,917.31	689.13	2,053.73	1,973.46	4.95	-0.66	0.105
78.67	-21.28	-4.59	0.00	-175.05	0.00	175.05	2,843.19	671.62	1,950.71	1,873.90	5.48	-0.70	0.101
80.00	-18.35	-4.20	0.00	-168.95	0.00	168.95	2,816.31	665.27	1,914.01	1,838.43	5.67	-0.71	0.098
82.00	-16.32	-3.64	0.00	-160.55	0.00	160.55	2,775.90	655.73	1,859.49	1,785.76	5.97	-0.73	0.096
83.33	-15.94	-3.61	0.00	-155.72	0.00	155.72	2,331.02	553.12	1,587.63	1,521.08	6.18	-0.74	0.109
85.00	-15.68	-3.57	0.00	-149.68	0.00	149.68	2,310.11	546.48	1,549.70	1,489.14	6.44	-0.76	0.107
90.00	-13.43	-3.26	0.00	-131.84	0.00	131.84	2,229.24	526.59	1,439.00	1,384.22	7.27	-0.81	0.101
95.00	-12.69	-3.19	0.00	-115.53	0.00	115.53	2,145.07	506.71	1,332.40	1,281.15	8.14	-0.86	0.096
100.00	-11.97	-3.12	0.00	-99.58	0.00	99.58	2,060.90	486.83	1,229.90	1,182.06	9.07	-0.91	0.090
105.00	-11.28	-3.04	0.00	-84.00	0.00	84.00	1,976.73	466.94	1,131.51	1,086.97	10.05	-0.96	0.083
110.00	-10.60	-2.98	0.00	-68.78	0.00	68.78	1,892.56	447.06	1,037.22	995.86	11.08	-1.00	0.075
114.00	-10.07	-2.94	0.00	-56.88	0.00	56.88	1,825.27	431.17	964.78	925.89	11.94	-1.04	0.067
114.00	-10.07	-2.94	0.00	-56.88	0.00	56.88	1,013.43	260.69	586.17	519.26	11.94	-1.04	0.120
114.00	-6.95	-2.31	0.00	-56.88	0.00	56.88	1,013.41	260.69	586.14	519.24	11.94	-1.04	0.116
115.00	-6.85	-2.28	0.00	-54.56	0.00	54.56	1,007.45	258.29	575.44	511.41	12.16	-1.05	0.114
120.00	-6.38	-2.21	0.00	-43.19	0.00	43.19	976.71	246.33	523.38	472.67	13.29	-1.11	0.098
125.00	-4.75	-1.64	0.00	-32.14	0.00	32.14	944.43	234.37	473.79	434.68	14.49	-1.17	0.079
130.00	-4.45	-1.58	0.00	-23.93	0.00	23.93	910.60	222.41	426.67	397.54	15.73	-1.21	0.065
135.00	-4.17	-1.53	0.00	-16.02	0.00	16.02	875.23	210.45	382.02	361.37	17.03	-1.25	0.049
138.00	-3.25	-1.35	0.00	-11.43	0.00	11.43	853.26	203.27	356.41	340.17	17.82	-1.27	0.037
140.00	-3.05	-1.23	0.00	-8.62	0.00	8.62	838.31	198.49	339.83	326.27	18.36	-1.28	0.030
142.00	-2.74	-0.84	0.00	-6.17	0.00	6.17	820.01	193.70	323.65	311.38	18.90	-1.29	0.023
145.00	0.00	-0.78	0.00	-3.65	0.00	3.65	789.63	186.53	300.11	288.62	19.71	-1.30	0.013

Equivalent Lateral Forces Method Analysis

Spectral Response Acceleration for Short Period (S_s):	0.17
Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.05
Long-Period Transition Period (T_L):	6
Importance Factor (I_E):	1.00
Site Coefficient F_a :	1.60
Site Coefficient F_v :	2.40
Response Modification Coefficient (R):	1.50
Design Spectral Response Acceleration at Short Period (S_{ds}):	0.19
Design Spectral Response Acceleration at 1.0 Second Period (S_{d1}):	0.09
Seismic Response Coefficient (C_s):	0.03
Upper Limit C_s	0.03
Lower Limit C_s	0.03
Period based on Rayleigh Method (sec):	2.31
Redundancy Factor (p):	1.30
Seismic Force Distribution Exponent (k):	1.91
Total Unfactored Dead Load:	43.35 k
Seismic Base Shear (E):	1.69 k

Load Case 1.2D + 1.0Ev + 1.0Eh

Seismic

Segment	Height Above Base (ft)	Weight (lb)	W_z (lb-ft)	C_{vx}	Horizontal Force (lb)	Vertical Force (lb)
39	143.50	126	1,621	0.008	14	156
38	141.00	96	1,197	0.006	10	119
37	139.00	108	1,306	0.007	11	133
36	136.50	165	1,933	0.010	17	204
35	132.50	285	3,147	0.016	28	352
34	127.50	296	3,044	0.016	27	367
33	122.50	456	4,343	0.022	38	564
32	117.50	468	4,114	0.021	36	579
31	114.50	95	795	0.004	7	117
30	114.00	0	2	0.000	0	0
29	112.00	528	4,239	0.022	37	653
28	107.50	678	5,032	0.026	44	839
27	102.50	697	4,726	0.024	41	863
26	97.50	717	4,415	0.023	39	886
25	92.50	736	4,101	0.021	36	910
24	87.50	755	3,786	0.020	33	934
23	84.16	257	1,196	0.006	10	318
22	82.66	374	1,681	0.009	15	462
21	81.00	642	2,781	0.014	24	795
20	79.33	431	1,794	0.009	16	534
19	76.83	793	3,103	0.016	27	981
18	72.50	1,100	3,856	0.020	34	1,361
17	67.50	1,123	3,436	0.018	30	1,390
16	62.50	1,147	3,028	0.016	26	1,418
15	57.50	1,170	2,635	0.014	23	1,447

14	53.50	713	1,400	0.007	12	882
13	51.00	480	861	0.004	8	594
12	49.40	291	491	0.003	4	360
11	46.90	1,617	2,471	0.013	22	2,001
10	44.10	775	1,053	0.005	9	959
9	41.60	873	1,062	0.005	9	1,080
8	37.50	1,384	1,381	0.007	12	1,712
7	32.50	1,411	1,072	0.006	9	1,746
6	27.50	1,438	795	0.004	7	1,779
5	22.50	1,465	552	0.003	5	1,812
4	17.50	1,492	348	0.002	3	1,846
3	12.50	1,519	187	0.001	2	1,879
2	7.50	1,546	72	0.000	1	1,913
1	2.50	1,573	9	0.000	0	1,946
PCTEL GPS-TMG-HR-26N	145.00	1	8	0.000	0	1
Alcatel-Lucent ALU 8	145.00	26	347	0.002	3	33
Generic GPS	145.00	10	131	0.001	1	12
Alcatel-Lucent RRH2x	145.00	159	2,083	0.011	18	196
Alcatel-Lucent 800 M	145.00	159	2,087	0.011	18	197
Alcatel-Lucent 1900M	145.00	132	1,733	0.009	15	163
Generic 12' Omni	145.00	40	525	0.003	5	49
Alcatel-Lucent TD-RR	145.00	210	2,756	0.014	24	260
RFS PD620-2	145.00	53	696	0.004	6	66
RFS APXVSP18-C-A20	145.00	171	2,245	0.012	20	212
Commscope DT465B-2XR	145.00	174	2,284	0.012	20	215
Flat Low Profile Pla	145.00	1,500	19,689	0.102	172	1,856
VZW Unused Reserve (142.00	0	0	0.000	0	0
Amphenol Antel LPA-8	142.00	108	1,362	0.007	12	134
Amphenol Antel BXA-7	142.00	112	1,419	0.007	12	139
Generic TTA	140.00	60	737	0.004	6	74
Amphenol Antel BXA-1	140.00	39	479	0.002	4	48
Round T-Arm	138.00	750	8,959	0.046	78	928
Generic E-911 GPS	125.00	5	49	0.000	0	6
RFS ATM1900D-1CWA	125.00	25	249	0.001	2	31
RFS ATMAA1412D-1A20	125.00	39	386	0.002	3	48
RFS APX16DWV-16DWV-S	125.00	238	2,351	0.012	21	294
Round T-Arm	125.00	750	7,420	0.038	65	928
Commscope LNX-6515DS	125.00	131	1,297	0.007	11	162
Commscope RDIDC-9181	114.00	22	182	0.001	2	27
Fujitsu TA08025-B604	114.00	192	1,591	0.008	14	237
Fujitsu TA08025-B605	114.00	225	1,868	0.010	16	278
JMA Wireless MX08FRO	114.00	193	1,606	0.008	14	239
Generic Flat Platfor	114.00	2,500	20,751	0.107	182	3,093
Empty Flat Low Profi	90.00	1,500	7,936	0.041	69	1,856
Spinner 756529	82.00	4	20	0.000	0	6
Powerwave Allgon LGP	82.00	33	146	0.001	1	41
Powerwave Allgon LGP	82.00	85	375	0.002	3	105
Raycap DC6-48-60-18-	82.00	33	145	0.001	1	41
Ericsson RRUS 4478 B	82.00	180	796	0.004	7	222
Ericsson RRUS 4449 B	82.00	213	944	0.005	8	264
Ericsson Radio 8843	82.00	225	997	0.005	9	278
Raycap DC9-48-60-24-	82.00	16	71	0.000	1	20
Powerwave Allgon 777	82.00	105	465	0.002	4	130
CCI DMP65R-BU6DA	82.00	318	1,407	0.007	12	393
CCI DMP65R-BU8D	82.00	191	848	0.004	7	237
Generic Flat Platfor	80.00	2,500	10,567	0.055	92	3,093
PCTEL GPS-TMG-HR-26N	52.00	1	1	0.000	0	1
Stand-Off	52.00	100	186	0.001	2	124
		43,349	193,258	1.000	1,691	53,628

Load Case 0.9D - 1.0Ev + 1.0Eh

Seismic (Reduced DL)

Segment	Height Above Base (ft)	Weight (lb)	W _z (lb-ft)	C _{vx}	Horizontal Force (lb)	Vertical Force (lb)
39	143.50	126	1,621	0.008	14	109
38	141.00	96	1,197	0.006	10	83
37	139.00	108	1,306	0.007	11	93
36	136.50	165	1,933	0.010	17	143
35	132.50	285	3,147	0.016	28	246
34	127.50	296	3,044	0.016	27	256
33	122.50	456	4,343	0.022	38	394
32	117.50	468	4,114	0.021	36	404
31	114.50	95	795	0.004	7	82
30	114.00	0	2	0.000	0	0
29	112.00	528	4,239	0.022	37	456
28	107.50	678	5,032	0.026	44	585
27	102.50	697	4,726	0.024	41	602
26	97.50	717	4,415	0.023	39	618
25	92.50	736	4,101	0.021	36	635
24	87.50	755	3,786	0.020	33	652
23	84.16	257	1,196	0.006	10	222
22	82.66	374	1,681	0.009	15	322
21	81.00	642	2,781	0.014	24	554
20	79.33	431	1,794	0.009	16	372
19	76.83	793	3,103	0.016	27	684
18	72.50	1,100	3,856	0.020	34	949
17	67.50	1,123	3,436	0.018	30	969
16	62.50	1,147	3,028	0.016	26	989
15	57.50	1,170	2,635	0.014	23	1,009
14	53.50	713	1,400	0.007	12	615
13	51.00	480	861	0.004	8	414
12	49.40	291	491	0.003	4	251
11	46.90	1,617	2,471	0.013	22	1,396
10	44.10	775	1,053	0.005	9	669
9	41.60	873	1,062	0.005	9	753
8	37.50	1,384	1,381	0.007	12	1,194
7	32.50	1,411	1,072	0.006	9	1,218
6	27.50	1,438	795	0.004	7	1,241
5	22.50	1,465	552	0.003	5	1,264
4	17.50	1,492	348	0.002	3	1,287
3	12.50	1,519	187	0.001	2	1,311
2	7.50	1,546	72	0.000	1	1,334
1	2.50	1,573	9	0.000	0	1,357
PCTEL GPS-TMG-HR-26N	145.00	1	8	0.000	0	1
Alcatel-Lucent ALU 8	145.00	26	347	0.002	3	23
Generic GPS	145.00	10	131	0.001	1	9
Alcatel-Lucent RRH2x	145.00	159	2,083	0.011	18	137
Alcatel-Lucent 800 M	145.00	159	2,087	0.011	18	137
Alcatel-Lucent 1900M	145.00	132	1,733	0.009	15	114
Generic 12' Omni	145.00	40	525	0.003	5	35
Alcatel-Lucent TD-RR	145.00	210	2,756	0.014	24	181
RFS PD620-2	145.00	53	696	0.004	6	46
RFS APXVSP18-C-A20	145.00	171	2,245	0.012	20	148
Commscope DT465B-2XR	145.00	174	2,284	0.012	20	150
Flat Low Profile Pla	145.00	1,500	19,689	0.102	172	1,294
VZW Unused Reserve (142.00	0	0	0.000	0	0
Amphenol Antel LPA-8	142.00	108	1,362	0.007	12	93
Amphenol Antel BXA-7	142.00	112	1,419	0.007	12	97
Generic TTA	140.00	60	737	0.004	6	52
Amphenol Antel BXA-1	140.00	39	479	0.002	4	34
Round T-Arm	138.00	750	8,959	0.046	78	647

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:54 PM

Customer: DISH WIRELESS L.L.C.

Generic E-911 GPS	125.00	5	49	0.000	0	4
RFS ATM1900D-1CWA	125.00	25	249	0.001	2	22
RFS ATMAA1412D-1A20	125.00	39	386	0.002	3	34
RFS APX16DWV-16DWV-S	125.00	238	2,351	0.012	21	205
Round T-Arm	125.00	750	7,420	0.038	65	647
Commscope LNX-6515DS	125.00	131	1,297	0.007	11	113
Commscope RDIDC-9181	114.00	22	182	0.001	2	19
Fujitsu TA08025-B604	114.00	192	1,591	0.008	14	165
Fujitsu TA08025-B605	114.00	225	1,868	0.010	16	194
JMA Wireless MX08FRO	114.00	193	1,606	0.008	14	167
Generic Flat Platfor	114.00	2,500	20,751	0.107	182	2,157
Empty Flat Low Profi	90.00	1,500	7,936	0.041	69	1,294
Spinner 756529	82.00	4	20	0.000	0	4
Powerwave Allgon LGP	82.00	33	146	0.001	1	28
Powerwave Allgon LGP	82.00	85	375	0.002	3	73
Raycap DC6-48-60-18-	82.00	33	145	0.001	1	28
Ericsson RRUS 4478 B	82.00	180	796	0.004	7	155
Ericsson RRUS 4449 B	82.00	213	944	0.005	8	184
Ericsson Radio 8843	82.00	225	997	0.005	9	194
Raycap DC9-48-60-24-	82.00	16	71	0.000	1	14
Powerwave Allgon 777	82.00	105	465	0.002	4	91
CCI DMP65R-BU6DA	82.00	318	1,407	0.007	12	274
CCI DMP65R-BU8D	82.00	191	848	0.004	7	165
Generic Flat Platfor	80.00	2,500	10,567	0.055	92	2,157
PCTEL GPS-TMG-HR-26N	52.00	1	1	0.000	0	1
Stand-Off	52.00	100	186	0.001	2	86
		43,349	193,258	1.000	1,691	37,405

Load Case 1.2D + 1.0Ev + 1.0Eh

Seismic

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-51.68	-1.70	0.00	-190.34	0.00	190.34	4,923.42	1,201.72	5,352.67	4,990.47	0.00	0.00	0.049
5.00	-49.77	-1.71	0.00	-181.87	0.00	181.87	4,841.97	1,173.88	5,107.60	4,793.23	0.01	-0.01	0.048
10.00	-47.89	-1.71	0.00	-173.34	0.00	173.34	4,758.98	1,146.05	4,868.28	4,598.35	0.03	-0.03	0.048
15.00	-46.04	-1.72	0.00	-164.77	0.00	164.77	4,674.44	1,118.21	4,634.70	4,405.95	0.06	-0.04	0.047
20.00	-44.23	-1.73	0.00	-156.16	0.00	156.16	4,588.36	1,090.38	4,406.86	4,216.14	0.11	-0.05	0.047
25.00	-42.45	-1.73	0.00	-147.54	0.00	147.54	4,498.09	1,062.54	4,184.76	4,026.66	0.17	-0.07	0.046
30.00	-40.70	-1.73	0.00	-138.91	0.00	138.91	4,380.25	1,034.71	3,968.40	3,817.43	0.25	-0.08	0.046
35.00	-38.99	-1.72	0.00	-130.28	0.00	130.28	4,262.42	1,006.87	3,757.79	3,613.78	0.34	-0.09	0.045
40.00	-37.91	-1.72	0.00	-121.68	0.00	121.68	4,144.58	979.03	3,552.92	3,415.71	0.44	-0.11	0.045
43.21	-36.95	-1.71	0.00	-116.18	0.00	116.18	4,069.03	961.19	3,424.59	3,291.66	0.52	-0.12	0.044
45.00	-34.95	-1.69	0.00	-113.11	0.00	113.11	4,026.74	951.20	3,353.79	3,223.22	0.57	-0.12	0.044
48.79	-34.59	-1.69	0.00	-106.70	0.00	106.70	3,411.63	814.18	2,866.55	2,731.35	0.67	-0.13	0.049
50.00	-34.00	-1.68	0.00	-104.66	0.00	104.66	3,393.84	808.42	2,826.18	2,697.72	0.70	-0.14	0.049
52.00	-32.99	-1.67	0.00	-101.29	0.00	101.29	3,364.13	798.88	2,759.86	2,642.23	0.76	-0.15	0.048
55.00	-31.54	-1.65	0.00	-96.28	0.00	96.28	3,319.09	784.57	2,661.85	2,559.69	0.86	-0.16	0.047
60.00	-30.12	-1.63	0.00	-88.01	0.00	88.01	3,220.32	760.71	2,502.44	2,407.25	1.03	-0.17	0.046
65.00	-28.73	-1.60	0.00	-79.86	0.00	79.86	3,119.32	736.85	2,347.95	2,257.87	1.22	-0.19	0.045
70.00	-27.37	-1.57	0.00	-71.84	0.00	71.84	3,018.31	712.99	2,198.38	2,113.27	1.42	-0.20	0.043
75.00	-26.39	-1.55	0.00	-63.97	0.00	63.97	2,917.31	689.13	2,053.73	1,973.46	1.65	-0.22	0.041
78.67	-25.86	-1.54	0.00	-58.29	0.00	58.29	2,843.19	671.62	1,950.71	1,873.90	1.82	-0.23	0.040
80.00	-21.97	-1.40	0.00	-56.24	0.00	56.24	2,816.31	665.27	1,914.01	1,838.43	1.89	-0.24	0.038
82.00	-19.77	-1.33	0.00	-53.43	0.00	53.43	2,775.90	655.73	1,859.49	1,785.76	1.99	-0.24	0.037
83.33	-19.46	-1.32	0.00	-51.67	0.00	51.67	2,331.02	553.12	1,587.63	1,521.08	2.06	-0.25	0.042
85.00	-18.52	-1.28	0.00	-49.47	0.00	49.47	2,310.11	546.48	1,549.70	1,489.14	2.14	-0.25	0.041
90.00	-15.76	-1.17	0.00	-43.05	0.00	43.05	2,229.24	526.59	1,439.00	1,384.22	2.42	-0.27	0.038
95.00	-14.87	-1.13	0.00	-37.19	0.00	37.19	2,145.07	506.71	1,332.40	1,281.15	2.71	-0.29	0.036
100.00	-14.01	-1.09	0.00	-31.53	0.00	31.53	2,060.90	486.83	1,229.90	1,182.06	3.02	-0.30	0.033
105.00	-13.17	-1.05	0.00	-26.08	0.00	26.08	1,976.73	466.94	1,131.51	1,086.97	3.34	-0.32	0.031
110.00	-12.51	-1.01	0.00	-20.85	0.00	20.85	1,892.56	447.06	1,037.22	995.86	3.68	-0.33	0.028
114.00	-12.51	-1.01	0.00	-16.82	0.00	16.82	1,825.27	431.17	964.78	925.89	3.96	-0.34	0.025
114.00	-12.51	-1.01	0.00	-16.82	0.00	16.82	1,013.43	260.69	586.17	519.26	3.96	-0.34	0.045
114.00	-8.52	-0.75	0.00	-16.82	0.00	16.82	1,013.41	260.69	586.14	519.24	3.96	-0.34	0.041
115.00	-7.94	-0.71	0.00	-16.07	0.00	16.07	1,007.45	258.29	575.44	511.41	4.04	-0.35	0.039
120.00	-7.38	-0.67	0.00	-12.51	0.00	12.51	976.71	246.33	523.38	472.67	4.41	-0.36	0.034
125.00	-5.54	-0.53	0.00	-9.14	0.00	9.14	944.43	234.37	473.79	434.68	4.80	-0.38	0.027
130.00	-5.19	-0.50	0.00	-6.48	0.00	6.48	910.60	222.41	426.67	397.54	5.20	-0.39	0.022
135.00	-4.99	-0.49	0.00	-3.95	0.00	3.95	875.23	210.45	382.02	361.37	5.62	-0.40	0.017
138.00	-3.93	-0.39	0.00	-2.49	0.00	2.49	853.26	203.27	356.41	340.17	5.87	-0.41	0.012
140.00	-3.69	-0.37	0.00	-1.71	0.00	1.71	838.31	198.49	339.83	326.27	6.04	-0.41	0.010
142.00	-3.26	-0.33	0.00	-0.98	0.00	0.98	820.01	193.70	323.65	311.38	6.21	-0.41	0.007
145.00	0.00	-0.30	0.00	0.00	0.00	0.00	789.63	186.53	300.11	288.62	6.47	-0.41	0.000

Load Case 0.9D - 1.0Ev + 1.0Eh

Seismic (Reduced DL)

Calculated Forces

Seg Elev (ft)	Pu FY (-) (kips)	Vu FX (-) (kips)	Tu MY (ft-kips)	Mu MZ (ft-kips)	Mu MX (ft-kips)	Resultant Moment (ft-kips)	phi Pn (kips)	phi Vn (kips)	phi Tn (ft-kips)	phi Mn (ft-kips)	Total Deflect (in)	Rotation (deg)	Ratio
0.00	-36.05	-1.69	0.00	-187.48	0.00	187.48	4,923.42	1,201.72	5,352.67	4,990.47	0.00	0.00	0.045
5.00	-34.71	-1.70	0.00	-179.01	0.00	179.01	4,841.97	1,173.88	5,107.60	4,793.23	0.01	-0.01	0.045
10.00	-33.40	-1.71	0.00	-170.51	0.00	170.51	4,758.98	1,146.05	4,868.28	4,598.35	0.03	-0.03	0.044
15.00	-32.11	-1.71	0.00	-161.98	0.00	161.98	4,674.44	1,118.21	4,634.70	4,405.95	0.06	-0.04	0.044
20.00	-30.85	-1.71	0.00	-153.43	0.00	153.43	4,588.36	1,090.38	4,406.86	4,216.14	0.11	-0.05	0.043
25.00	-29.61	-1.71	0.00	-144.88	0.00	144.88	4,498.09	1,062.54	4,184.76	4,026.66	0.17	-0.06	0.043
30.00	-28.39	-1.71	0.00	-136.33	0.00	136.33	4,380.25	1,034.71	3,968.40	3,817.43	0.24	-0.08	0.042
35.00	-27.20	-1.70	0.00	-127.80	0.00	127.80	4,262.42	1,006.87	3,757.79	3,613.78	0.33	-0.09	0.042
40.00	-26.44	-1.69	0.00	-119.31	0.00	119.31	4,144.58	979.03	3,552.92	3,415.71	0.44	-0.11	0.041
43.21	-25.77	-1.69	0.00	-113.88	0.00	113.88	4,069.03	961.19	3,424.59	3,291.66	0.51	-0.12	0.041
45.00	-24.38	-1.67	0.00	-110.86	0.00	110.86	4,026.74	951.20	3,353.79	3,223.22	0.56	-0.12	0.040
48.79	-24.13	-1.66	0.00	-104.54	0.00	104.54	3,411.63	814.18	2,866.55	2,731.35	0.66	-0.13	0.045
50.00	-23.71	-1.66	0.00	-102.53	0.00	102.53	3,393.84	808.42	2,826.18	2,697.72	0.69	-0.14	0.045
52.00	-23.01	-1.64	0.00	-99.22	0.00	99.22	3,364.13	798.88	2,759.86	2,642.23	0.75	-0.14	0.044
55.00	-22.00	-1.62	0.00	-94.29	0.00	94.29	3,319.09	784.57	2,661.85	2,559.69	0.84	-0.15	0.043
60.00	-21.01	-1.60	0.00	-86.17	0.00	86.17	3,220.32	760.71	2,502.44	2,407.25	1.01	-0.17	0.042
65.00	-20.04	-1.57	0.00	-78.16	0.00	78.16	3,119.32	736.85	2,347.95	2,257.87	1.20	-0.18	0.041
70.00	-19.09	-1.54	0.00	-70.30	0.00	70.30	3,018.31	712.99	2,198.38	2,113.27	1.40	-0.20	0.040
75.00	-18.41	-1.52	0.00	-62.59	0.00	62.59	2,917.31	689.13	2,053.73	1,973.46	1.62	-0.22	0.038
78.67	-18.03	-1.50	0.00	-57.02	0.00	57.02	2,843.19	671.62	1,950.71	1,873.90	1.79	-0.23	0.037
80.00	-15.32	-1.38	0.00	-55.03	0.00	55.03	2,816.31	665.27	1,914.01	1,838.43	1.85	-0.23	0.035
82.00	-13.79	-1.30	0.00	-52.27	0.00	52.27	2,775.90	655.73	1,859.49	1,785.76	1.95	-0.24	0.034
83.33	-13.57	-1.29	0.00	-50.55	0.00	50.55	2,331.02	553.12	1,587.63	1,521.08	2.02	-0.24	0.039
85.00	-12.92	-1.26	0.00	-48.39	0.00	48.39	2,310.11	546.48	1,549.70	1,489.14	2.10	-0.25	0.038
90.00	-10.99	-1.15	0.00	-42.10	0.00	42.10	2,229.24	526.59	1,439.00	1,384.22	2.37	-0.26	0.035
95.00	-10.37	-1.11	0.00	-36.36	0.00	36.36	2,145.07	506.71	1,332.40	1,281.15	2.66	-0.28	0.033
100.00	-9.77	-1.07	0.00	-30.82	0.00	30.82	2,060.90	486.83	1,229.90	1,182.06	2.96	-0.30	0.031
105.00	-9.18	-1.02	0.00	-25.49	0.00	25.49	1,976.73	466.94	1,131.51	1,086.97	3.28	-0.31	0.028
110.00	-8.73	-0.98	0.00	-20.38	0.00	20.38	1,892.56	447.06	1,037.22	995.86	3.61	-0.32	0.025
114.00	-8.73	-0.98	0.00	-16.45	0.00	16.45	1,825.27	431.17	964.78	925.89	3.89	-0.33	0.023
114.00	-8.73	-0.98	0.00	-16.45	0.00	16.45	1,013.43	260.69	586.17	519.26	3.89	-0.33	0.040
114.00	-5.94	-0.73	0.00	-16.45	0.00	16.45	1,013.41	260.69	586.14	519.24	3.89	-0.33	0.038
115.00	-5.54	-0.70	0.00	-15.71	0.00	15.71	1,007.45	258.29	575.44	511.41	3.96	-0.34	0.036
120.00	-5.15	-0.66	0.00	-12.23	0.00	12.23	976.71	246.33	523.38	472.67	4.32	-0.36	0.031
125.00	-3.87	-0.52	0.00	-8.94	0.00	8.94	944.43	234.37	473.79	434.68	4.70	-0.37	0.025
130.00	-3.62	-0.49	0.00	-6.33	0.00	6.33	910.60	222.41	426.67	397.54	5.10	-0.38	0.020
135.00	-3.48	-0.48	0.00	-3.86	0.00	3.86	875.23	210.45	382.02	361.37	5.51	-0.39	0.015
138.00	-2.74	-0.38	0.00	-2.44	0.00	2.44	853.26	203.27	356.41	340.17	5.76	-0.40	0.010
140.00	-2.57	-0.36	0.00	-1.67	0.00	1.67	838.31	198.49	339.83	326.27	5.92	-0.40	0.008
142.00	-2.27	-0.32	0.00	-0.96	0.00	0.96	820.01	193.70	323.65	311.38	6.09	-0.40	0.006
145.00	0.00	-0.30	0.00	0.00	0.00	0.00	789.63	186.53	300.11	288.62	6.35	-0.40	0.000

Site Number: 411182

Code: ANSI/TIA-222-H

© 2007 - 2021 by ATC IP LLC. All rights reserved.

Site Name: Nepaug CT, CT

Engineering Number: 13693709_C3_02

7/12/2021 3:51:54 PM

Customer: DISH WIRELESS L.L.C.

Analysis Summary

Load Case	Reactions						Max Usage	
	Shear FX (kips)	Shear FZ (kips)	Axial FY (kips)	Moment MX (ft-kips)	Moment MY (ft-kips)	Moment MZ (ft-kips)	Elev (ft)	Interaction Ratio
1.2D + 1.0W	23.03	0.00	51.99	0.00	0.00	2397.84	48.79	0.49
0.9D + 1.0W	23.01	0.00	38.98	0.00	0.00	2367.63	48.79	0.48
1.2D + 1.0Di + 1.0Wi	6.42	0.00	68.04	0.00	0.00	664.57	48.79	0.15
1.2D + 1.0Ev + 1.0Eh	1.70	0.00	51.68	0.00	0.00	190.34	48.79	0.05
0.9D - 1.0Ev + 1.0Eh	1.69	0.00	36.05	0.00	0.00	187.48	48.79	0.05
1.0D + 1.0W	5.61	0.00	43.35	0.00	0.00	579.56	48.79	0.13




Base Plate & Anchor Rod Analysis

Pole Dimensions		
Number of Sides	18	-
Diameter	49.75	in
Thickness	7/16	in
Orientation Offset		°

Base Reactions		
Moment, Mu	2,397.8	k-ft
Axial, Pu	52.0	k
Shear, Vu	23.0	k
Neutral Axis	243	°

Report Capacities		
Component	Capacity	Result
Base Plate	81%	Pass
Anchor Rods	36%	Pass
Dwyidag	-	-

Base Plate		
Shape	Round	-
Diameter, ϕ	75	in
Thickness	2 3/4	in
Grade	A572-60	
Yield Strength, Fy	60	ksi
Tensile Strength, Fu	75	ksi
Clip	N/A	in
Orientation Offset		°
Anchor Rod Detail	d	$\eta=0.5$
Clear Distance	4	in
Applied Moment, Mu	2154.3	k
Bending Stress, ϕMn	2676.2	k



Original Anchor Rods		
Arrangement	Radial	-
Quantity	20	-
Diameter, ϕ	2 1/4	in
Bolt Circle	69	in
Grade	A615-75	
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Spacing	10.8	in
Orientation Offset		°
Applied Force, Pu	87.9	k
Anchor Rods, ϕPn	243.6	k

Calculations for Monopole Base Plate & Anchor Rod Analysis

Reaction Distribution

Reaction	Shear Vu	Moment Mu	Factor
-	k	k-ft	-
Base Forces	23.0	2397.8	1.00
Anchor Rod Forces	23.0	2397.8	1.00
Additional Bolt (Grp1) Forces	0.0	0.0	0.00
Additional Bolt (Grp2) Forces	0.0	0.0	0.00
Dywidag Forces	0.0	0.0	0.00
Stiffener Forces	0.0	0.0	0.00

Geometric Properties

Section	Gross Area	Net Area	Individual Inertia	Threads per Inch	Moment of Inertia
-	in ²	in ²	in ⁴	#	in ⁴
Pole	67.4338	3.7463	0.2401		20501.87
Bolt	3.9761	3.2477	0.8393	4.5	36057.13
Bolt1	0.0000	0.0000	0.0000	0	0.00
Bolt2	0.0000	0.0000	0.0000	0	0.00
Dywidag	0.0000	0.0000	0.0000		0.00
Stiffener	0.0000	0.0000	0.0000		0.00

Base Plate

Shape	Round	-
Diameter, D	75	in
Thickness, t	2.75	in
Yield Strength, Fy	60	ksi
Tensile Strength, Fu	75	ksi
Base Plate Chord	56.124	in
Detail Type	d	-
Detail Factor	0.50	-
Clear Distance	4	-

Anchor Rods

Anchor Rod Quantity, N	20	-
Rod Diameter, d	2.25	in
Bolt Circle, BC	69	in
Yield Strength, Fy	75	ksi
Tensile Strength, Fu	100	ksi
Applied Axial, Pu	87.9	k
Applied Shear, Vu	0.3	k
Compressive Capacity, ϕP_n	243.6	k
Tensile Capacity, ϕR_n	0.361	OK
Interaction Capacity	0.363	OK

External Base Plate

Chord Length AA	51.232	in
Additional AA	5.500	in
Section Modulus, Z	107.259	in ³
Applied Moment, Mu	2154.3	k-ft
Bending Capacity, ϕM_n	5792.0	k-ft
Capacity, Mu/ ϕM_n	0.372	OK

Chord Length AB	50.472	in
Additional AB	5.500	in
Section Modulus, Z	105.822	in ³
Applied Moment, Mu	2025.6	k-ft
Bending Capacity, ϕM_n	5714.4	k-ft
Capacity, Mu/ ϕM_n	0.354	OK

Bend Line Length	26.213	in
Additional Bend Line	0.000	in
Section Modulus, Z	49.559	in ³
Applied Moment, Mu	2154.3	k-ft
Bending Capacity, ϕM_n	2676.2	k-ft
Capacity, Mu/ ϕM_n	0.805	OK

Internal Base Plate

Arc Length	0.000	in
Section Modulus, Z	0.000	in ³
Moment Arm	0.000	in
Applied Moment, Mu	0.0	k-ft
Bending Capacity, ϕM_n	0.0	k-ft
Capacity, Mu/ ϕM_n		

Flange Plate Analysis

Flange Plate	Plate Type	Flange	114ft
	Pole Diameter	25.125	in
	Pole Thickness	0.1875	in
	Plate Diameter	32	in
	Plate Thickness	1 1/2	in
	Plate Fy	65	ksi
	Weld Length	3/16	in
	f _s Resistance	199.48	k-in
	Applied	37.46	k-in

Code Rev. **H**


Date	7/12/2021
Engineer	Ravi siddharth Raja
Site #	411182
Carrier	Dish Wireless

Moment 235.6 k-ft
Axial 11.3 k

Required Flange Thickness:
0.65 in OK

Stiffeners	#	
------------	---	--

Bolts	#	12	
	Bolt Circle	29	in
	(R)adial / (S)quare	R	
	Diameter	1	in
	Hole Diameter	1 1/8	in
	Type	A325	
	Fy	92	ksi
	Fu	120	ksi
	f _s Resistance	54.52	k
	Applied	31.54	k



Reinforcement	#	
---------------	---	--

Plate Stress Ratio:
19% Pass

Bolt Stress Ratio:
58% Pass

Extra Bolts O	#	
---------------	---	--


INFINIGY

MOUNT ANALYSIS REPORT

September 15, 2021

Dish Wireless Site Name	BOHVN00005A
Dish Wireless Site Number	BOHVN00005A
ATC Site Name	Nepaug CT, CT
ATC Site Number	411182
Infinigy Job Number	1197-F0001-B
Client	ATC
Carrier	Dish Wireless
Site Location	20 Antolini Road New Hartford, CT 06057 Litchfield County 41.828061 N NAD83 73.015683 W NAD83
Mount Type	8.0 ft Platform
Mount Elevation	114.0 ft AGL
Structural Usage Ratio	28.1%
Overall Result	Pass

The enclosed mount structural analysis has been performed in accordance with the 2018 Connecticut State Building Code (2015 IBC) based on an ultimate 3-second gust wind speed of 115 mph. The evaluation criteria and applicable codes are presented in the next section of this report.



CONTENTS

1. Introduction
2. Design/Analysis Parameters
3. Proposed Loading Configuration
4. Supporting Documentation
5. Results
6. Recommendations
7. Assumptions
8. Liability Waiver and Limitations
9. Calculations

1. INTRODUCTION

Infinigy performed a structural analysis on the Dish Wireless proposed telecommunication equipment supporting Platform mounted to the existing structure located at the aforementioned address. All referenced supporting documents have been obtained from the client and are assumed to be accurate and applicable to this site. The mount was analyzed using Risa-3D version 17.0.4 analysis software.

2. DESIGN/ANALYSIS PARAMETERS

Wind Speed	115 mph (3-Second Gust)
Wind Speed w/ ice	50 mph (3-Second Gust) w/ 1" ice
Code / Standard	TIA-222-H
Adopted Code	2018 Connecticut State Building Code (2015 IBC)
Risk Category	II
Exposure Category	B
Topographic Category	1
Calculated Crest Height	0 ft
Seismic Spectral Response	$S_s = 0.174 \text{ g} / S_1 = 0.054 \text{ g}$
Live Load Wind Speed	60 mph
Man Live Load at Mid/End Points	250 lbs
Man Live Load at Mount Pipes	500 lbs

3. PROPOSED LOADING CONFIGURATION - 114.0 ft. AGL Platform

Antenna Centerline (ft)	Qty.	Appurtenance Manufacturers	Appurtenance Models
114.0	3	JMA WIRELESS	MX08FRO665-21
	3	FUJITSU	TA08025-B605
	3	FUJITSU	TA08025-B604
	1	RAYCAP	RDIDC-9181-PF-48

4. SUPPORTING DOCUMENTATION

Proposed Loading	Dish Wireless Asset ID CT-ATC-T-411182 Rev 1, Site #BOHVN00005A, dated July 12, 2021
Mount Manufacturer Drawings	Commscope Document # MC-PK8-DSH, dated March 08, 2021
Structural Analysis Report	ATC, Asset #411182, dated July 12, 2021

5. RESULTS

Components	Capacity	Pass/Fail
Mount Pipes	16.1%	Pass
Horizontals	9.6%	Pass
Standoffs	24.9%	Pass
Handrails	19.2%	Pass
Connections	28.1%	Pass
MOUNT RATING =	28.1%	Pass

Notes:

1. See additional documentation in Appendix for calculations supporting the capacity consumed and detailed mount connection calculations.

6. RECOMMENDATIONS

Infinigy recommends installing Dish Wireless's proposed equipment loading configuration on the mount at 114.0 ft. The installation shall be performed in accordance with the construction documents issued for this site.

Alisha Khadka
Project Engineer II | [INFINIGY](#)

7. ASSUMPTIONS



The antenna mounting system was properly fabricated, installed and maintained in accordance with its original design and manufacturer's specifications.	
The configuration of antennas, mounts, and other appurtenances are as specified in the proposed loading configuration table.	
All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.	
The analysis will require revisions if the existing conditions in the field differ from those shown in the above-referenced documents or assumed in this analysis. No allowance was made for any damaged, missing, or rusted members.	
Steel grades have been assumed as follows, unless noted otherwise:	
Channel, Solid Round, Plate, Built-up Angle	ASTM A1011 36 KSI
Structural Angle	ASTM A529 Gr. 50
HSS (Rectangular)	ASTM A500-B GR 46
HSS (Circular)	ASTM A500-B GR 42
Pipe	ASTM A500 Gr C
Connection Bolts	ASTM A325
U-Bolts	ASTM A307
All bolted connections are pretensioned in accordance with Table 8.2 of the RCSC 2014 Standard	

8. LIABILITY WAIVER AND LIMITATIONS

Our structural calculations are completed assuming all information provided to Infinigy is accurate and applicable to this site. For the purposes of calculations, we assume an overall structure condition as erected and all members and connections to be free of corrosion and/or structural defects. The structure owner and/or contractor shall verify the structure's condition prior to installation of any proposed equipment. If actual conditions differ from those described in this report, Infinigy should be notified immediately to assess the impact on the results of this report.

Our evaluation is completed using industry standard methods and procedures. The structural results, conclusions and recommendations contained in this report are proprietary and should not be used by others as their own. Infinigy is not responsible for decisions made by others that are or are not based on the stated assumptions and conclusions in this report.

This report is an evaluation of the mount structure only and does not determine the adequacy of the supporting structure, other carrier mounts or cable mounting attachments. The analysis of these elements is outside the scope of this analysis, are assumed to be adequate for the purpose of this report and to have been installed per their manufacturer requirements. This document is not for construction purposes.



Envelope Only Solution

Infinigy Engineering

AK



1197-F0001-B

BOHVN00005A

Rendered

Sept 14, 2021 at 3:43 PM

BOHVN00005A_loaded.r3d





Envelope Only Solution

Infinigy Engineering
AK
1197-F0001-B



BOHVN00005A

Wireframe
Sept 14, 2021 at 3:44 PM
BOHVN00005A_loaded.r3d



Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Section Sets
AK		Sept 14, 2021 at 3:45 PM
1197-F0001-B		BOHVN00005A_loaded.r3d



Envelope Only Solution

Infinigy Engineering

AK



1197-F0001-B

BOHVN00005A

Member Shapes



Sept 14, 2021 at 3:45 PM

BOHVN00005A_loaded.r3d





Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Material Sets
AK		Sept 14, 2021 at 3:46 PM
1197-F0001-B		BOHVN00005A_loaded.r3d





Member Length (in) Displayed
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Member Lengths
AK		Sept 14, 2021 at 3:46 PM
1197-F0001-B		BOHVN00005A_loaded.r3d



Loads: BLC 1, Self Weight
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Self Weight
AK		Sept 14, 2021 at 3:47 PM
1197-F0001-B		BOHVN00005A_loaded.r3d





Loads: BLC 2, Wind Load AZI 0
Envelope Only Solution

Infinigy Engineering
AK
1197-F0001-B



BOHVN00005A

Wind Load AZI 0
Sept 14, 2021 at 3:47 PM
BOHVN00005A_loaded.r3d



Loads: BLC 5, Wind Load AZI 90
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Wind Load AZI 90
AK		Sept 14, 2021 at 3:48 PM
1197-F0001-B		BOHVN00005A_loaded.r3d





Loads: BLC 14, Distr. Wind Load Z
Envelope Only Solution

Infinigy Engineering
AK
1197-F0001-B



BOHVN00005A

Distr. Wind Load AZI 000
Sept 14, 2021 at 3:49 PM
BOHVN00005A_loaded.r3d



Loads: BLC 15, Distr. Wind Load X
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Distr. Wind Load AZI 090
AK		Sept 14, 2021 at 4:11 PM
1197-F0001-B		BOHVN00005A_loaded.r3d





Loads: BLC 16, Ice Weight
Envelope Only Solution

Infinigy Engineering
AK
1197-F0001-B

BOHVN00005A

Ice Weight
Sept 14, 2021 at 3:49 PM
BOHVN00005A_loaded.r3d



Loads: BLC 17, Ice Wind Load AZI 0
Envelope Only Solution

Infinigy Engineering

AK



1197-F0001-B

BOHVN00005A

Ice + Wind Load AZI 000

Sept 14, 2021 at 5:43 PM

BOHVN00005A_loaded.r3d



Loads: BLC 20, Ice Wind Load AZI 90
Envelope Only Solution

Infinigy Engineering

AK



1197-F0001-B

BOHVN00005A

Ice + Wind Load AZI 090



Sept 14, 2021 at 3:50 PM

BOHVN00005A_loaded.r3d





Loads: BLC 29, Distr. Ice Wind Load Z
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Distr. Ice + Wind Load AZI 000
AK		Sept 14, 2021 at 4:04 PM
1197-F0001-B		BOHVN00005A_loaded.r3d





Loads: BLC 30, Distr. Ice Wind Load X
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Distr. Ice + Wind Load AZI 090
AK		Sept 14, 2021 at 4:04 PM
1197-F0001-B		BOHVN00005A_loaded.r3d





Loads: BLC 31, Seismic Load Z
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Seismic Load AZI 000
AK		Sept 14, 2021 at 3:52 PM
1197-F0001-B		BOHVN00005A_loaded.r3d



Loads: BLC 32, Seismic Load X
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Seismic Load AZI 090
AK		Sept 14, 2021 at 3:52 PM
1197-F0001-B		BOHVN00005A_loaded.r3d



Loads: LL - Live Load
Envelope Only Solution


Infinigy Engineering
AK
1197-F0001-B

BOHVN00005A


Non-concurrent Live Loads

Sept 14, 2021 at 3:53 PM

BOHVN00005A_loaded.r3d




Code Check (Env)	
Black	No Calc
Red	> 1.0
Magenta	.90-1.0
Green	.75-.90
Cyan	.50-.75
Blue	0-.50




Member Code Checks Displayed (Enveloped)
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Bending Check
AK		Sept 14, 2021 at 3:53 PM
1197-F0001-B		BOHVN00005A_loaded.r3d



Shear Check (Env)	
Black	No Calc
Red	> 1.0
Magenta	.90-1.0
Green	.75-.90
Cyan	.50-.75
Blue	0.-.50



Member Shear Checks Displayed (Enveloped)
Envelope Only Solution

Infinigy Engineering	BOHVN00005A	Shear Check
AK		Sept 14, 2021 at 3:54 PM
1197-F0001-B		BOHVN00005A_loaded.r3d

Program Inputs

PROJECT INFORMATION		
Client:	ATC	
Carrier:	Dish Wireless	
Engineer:	Alisha Khadka	

SITE INFORMATION		
Risk Category:	II	
Exposure Category:	B	
Topo Factor Procedure:	Method 1, Category 1	
Site Class:	D - Stiff Soil (Assumed)	
Ground Elevation:	744.89	ft *Rev H

MOUNT INFORMATION		
Mount Type:	Platform	
Num Sectors:	3	
Centerline AGL:	114.00	ft
Tower Height AGL:	145.00	ft

TOPOGRAPHIC DATA		
Topo Feature:	N/A	
Slope Distance:	N/A	ft
Crest Distance:	N/A	ft
Crest Height:	N/A	ft

FACTORS		
Directionality Fact. (K_d):	0.950	
Ground Ele. Factor (K_e):	0.973	*Rev H Only
Rooftop Speed-Up (K_s):	1.000	*Rev H Only
Topographic Factor (K_{zt}):	1.000	
Gust Effect Factor (G_h):	1.000	

CODE STANDARDS		
Building Code:	2015 IBC	
TIA Standard:	TIA-222-H	
ASCE Standard:	ASCE 7-16	



WIND AND ICE DATA		
Ultimate Wind (V_{ult}):	115	mph
Design Wind (V):	N/A	mph
Ice Wind (V_{ice}):	50	mph
Base Ice Thickness (t_i):	1	in
Flat Pressure:	64.239	psf
Round Pressure:	38.543	psf
Ice Wind Pressure:	7.286	psf

SEISMIC DATA		
Short-Period Accel. (S_s):	0.174	g
1-Second Accel. (S_1):	0.054	g
Short-Period Design (S_{DS}):	0.186	
1-Second Design (S_{D1}):	0.086	
Short-Period Coeff. (F_a):	1.600	
1-Second Coeff. (F_v):	2.400	
Amplification Factor (A_s):	3.000	
Response Mod. Coeff. (R):	2.000	



Infinigy Load Calculator V2.1.7

Program Inputs



Infinigy Load Calculator V2.1.7


APPURTENANCE INFORMATION												
Appurtenance Name	Elevation	Qty.	K _a	q _z (psf)	EPA _N (ft ²)	EPA _T (ft ²)	Wind F _z (lbs)	Wind F _x (lbs)	Weight (lbs)	Seismic F (lbs)	Member (α sector)	
JMA WIRELESS MX08FRO665-21	114.0	3	0.90	32.12	8.01	3.21	231.55	92.79	64.50	17.96	MP1	
FUJITSU TA08025-B605	114.0	3	0.90	32.12	1.96	1.19	56.76	34.37	74.95	20.87	MP1	
FUJITSU TA08025-B604	114.0	3	0.90	32.12	1.96	1.03	56.76	29.86	63.93	17.80	MP1	
RAYCAP RDIDC-9181-PF-48	114.0	1	0.90	32.12	1.87	1.07	53.96	30.83	21.85	6.08	MP10	

ASCE 7 Hazards Report

Address:
No Address at This
Location

Standard: ASCE/SEI 7-16
Risk Category: II
Soil Class: D - Default (see
Section 11.4.3)

Elevation: 744.89 ft (NAVD 88)
Latitude: 41.828061
Longitude: -73.015683



Wind

Results:

Wind Speed:	115 Vmph
10-year MRI	75 Vmph
25-year MRI	84 Vmph
50-year MRI	89 Vmph
100-year MRI	95 Vmph

Data Source: ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2

Date Accessed: Tue Sep 14 2021

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).





Site is not in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2.

Site Soil Class: D - Default (see Section 11.4.3)

Results:

S_S :	0.174	S_{D1} :	0.086
S_1 :	0.054	T_L :	6
F_a :	1.6	PGA :	0.092
F_v :	2.4	PGA _M :	0.148
S_{MS} :	0.279	F_{PGA} :	1.6
S_{M1} :	0.129	I_e :	1
S_{DS} :	0.186	C_v :	0.7

Seismic Design Category B



Data Accessed:

Tue Sep 14 2021

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-16 and ASCE/SEI 7-16 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-16 Ch. 21 are available from USGS.

Ice

Results:

Ice Thickness: 1.00 in.
Concurrent Temperature: 5 F
Gust Speed: 50 mph

Data Source: Standard ASCE/SEI 7-16, Figs. 10-2 through 10-8

Date Accessed: Tue Sep 14 2021

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 500-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided “as is” and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

Member Primary Data

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
1	S3	P1	P3			Square Tubing	Beam	None	A500 GR.C	Typical
2	GA4	P9	P12		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
3	GA3	P10	P11			Grating Angle	Beam	None	A529 Gr. 50	Typical
4	P3	P7	P8			Corner Plates	Beam	None	A1011 36 ...	Typical
5	S2	P13	P14			Square Tubing	Beam	None	A500 GR.C	Typical
6	GA2	P20	P23		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
7	GA1	P21	P22			Grating Angle	Beam	None	A529 Gr. 50	Typical
8	P2	P18	P19			Corner Plates	Beam	None	A1011 36 ...	Typical
9	S1	P24	P25			Square Tubing	Beam	None	A500 GR.C	Typical
10	GA6	P31	P34		270	Grating Angle	Beam	None	A529 Gr. 50	Typical
11	GA5	P32	P33			Grating Angle	Beam	None	A529 Gr. 50	Typical
12	P1	P29	P30			Corner Plates	Beam	None	A1011 36 ...	Typical
13	H1	N43	N44			Face Pipes(3...	Beam	None	A500 GR.C	Typical
14	MP1	N66	N60			Antenna Pipes	Beam	None	A500 GR.C	Typical
15	MP3	N63	N57			Antenna Pipes	Beam	None	A500 GR.C	Typical
16	HR1	N67	N68			Handrail	Beam	None	A500 GR.C	Typical
17	CA8	N114A	N113A		180	Handrail Conn...	Beam	None	A1011 36 ...	Typical
18	CA9	N112A	N111A		180	Handrail Conn...	Beam	None	A1011 36 ...	Typical
19	CA7	N116A	N115A		180	Handrail Conn...	Beam	None	A1011 36 ...	Typical
20	M32	N48A	N70A			RIGID	None	None	RIGID	Typical
21	M35	N45	N69A			RIGID	None	None	RIGID	Typical
22	M36	N51	N71A			RIGID	None	None	RIGID	Typical
23	M39A	N54	N72A			RIGID	None	None	RIGID	Typical
24	CA3	P4	N122A			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
25	CA4	N124B	P4			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
26	CA1	P15	N122B			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
27	CA2	N123A	P15			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
28	CA5	P26	N125			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
29	CA6	N126	P26			Channel(3.38x...	Beam	None	A1011 36 ...	Typical
30	M64	N126A	N125A			RIGID	None	None	RIGID	Typical
31	M65	N126	N125A			RIGID	None	None	RIGID	Typical
32	M66	N129	N128			RIGID	None	None	RIGID	Typical
33	M67	N124B	N128			RIGID	None	None	RIGID	Typical
34	M68	N132	N131			RIGID	None	None	RIGID	Typical
35	M69	N123A	N131			RIGID	None	None	RIGID	Typical
36	M70	N133	N132A			RIGID	None	None	RIGID	Typical
37	M71	N122B	N132A			RIGID	None	None	RIGID	Typical
38	M72	N135	N134			RIGID	None	None	RIGID	Typical
39	M73	N125	N134			RIGID	None	None	RIGID	Typical
40	M74	N138	N137			RIGID	None	None	RIGID	Typical
41	M75	N122A	N137			PL 2.375x0.5	None	None	A36 Gr.36	Typical
42	MP2	N75	N74			Antenna Pipes	Beam	None	A500 GR.C	Typical
43	M43	N72B	N76			RIGID	None	None	RIGID	Typical
44	M44	N73	N77			RIGID	None	None	RIGID	Typical
45	H3	N81A	N82A			Face Pipes(3...	Beam	None	A500 GR.C	Typical
46	MP7	N90	N88			Antenna Pipes	Beam	None	A500 GR.C	Typical
47	MP9	N89	N87			Antenna Pipes	Beam	None	A500 GR.C	Typical
48	HR3	N91	N92			Handrail	Beam	None	A500 GR.C	Typical
49	M52	N84	N94			RIGID	None	None	RIGID	Typical
50	M53	N83A	N93			RIGID	None	None	RIGID	Typical
51	M54	N85	N95			RIGID	None	None	RIGID	Typical
52	M55	N86	N96			RIGID	None	None	RIGID	Typical
53	H2	N109	N110			Face Pipes(3...	Beam	None	A500 GR.C	Typical
54	MP4	N118	N116			Antenna Pipes	Beam	None	A500 GR.C	Typical
55	MP6	N117	N115			Antenna Pipes	Beam	None	A500 GR.C	Typical
56	HR2	N119	N120			Handrail	Beam	None	A500 GR.C	Typical

Member Primary Data (Continued)

	Label	I Joint	J Joint	K Joint	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rules
57	M66A	N112	N122			RIGID	None	None	RIGID	Typical
58	M67A	N111	N121			RIGID	None	None	RIGID	Typical
59	M68A	N113	N123			RIGID	None	None	RIGID	Typical
60	M69A	N114	N124			RIGID	None	None	RIGID	Typical
61	MP8	N132B	N131A			Antenna Pipes	Beam	None	A500 GR.C	Typical
62	M68B	N129B	N133B			RIGID	None	None	RIGID	Typical
63	M69B	N130A	N134A			RIGID	None	None	RIGID	Typical
64	MP5	N138A	N137A			Antenna Pipes	Beam	None	A500 GR.C	Typical
65	M71B	N135A	N139			RIGID	None	None	RIGID	Typical
66	M72B	N136	N140			RIGID	None	None	RIGID	Typical
67	M67B	N119A	N120A			RIGID	None	None	RIGID	Typical
68	MP10	N121A	N122C			Antenna Pipes	Beam	None	A500 GR.C	Typical

Hot Rolled Steel Design Parameters

	Label	Shape	Length[in]	Lbyy[in]	Lbzz[in]	Lcomp top[in]	Lcomp bot[in]	L-torqu...	Kyy	Kzz	Cb	Function
1	S3	Square Tubi...	40			Lbyy						Lateral
2	GA4	Grating Angle	27.295			Lbyy						Lateral
3	GA3	Grating Angle	27.295			Lbyy						Lateral
4	P3	Corner Plates	42			Lbyy						Lateral
5	S2	Square Tubi...	40			Lbyy						Lateral
6	GA2	Grating Angle	27.295			Lbyy						Lateral
7	GA1	Grating Angle	27.295			Lbyy						Lateral
8	P2	Corner Plates	42			Lbyy						Lateral
9	S1	Square Tubi...	40			Lbyy						Lateral
10	GA6	Grating Angle	27.295			Lbyy						Lateral
11	GA5	Grating Angle	27.295			Lbyy						Lateral
12	P1	Corner Plates	42			Lbyy						Lateral
13	H1	Face Pipes(...	96			Lbyy						Lateral
14	MP1	Antenna Pip...	96			Lbyy						Lateral
15	MP3	Antenna Pip...	96			Lbyy						Lateral
16	HR1	Handrail	96			Lbyy						Lateral
17	CA8	Handrail Co...	42			Lbyy						Lateral
18	CA9	Handrail Co...	42			Lbyy						Lateral
19	CA7	Handrail Co...	42			Lbyy						Lateral
20	CA3	Channel(3.3...	33			Lbyy						Lateral
21	CA4	Channel(3.3...	33			Lbyy						Lateral
22	CA1	Channel(3.3...	33			Lbyy						Lateral
23	CA2	Channel(3.3...	33			Lbyy						Lateral
24	CA5	Channel(3.3...	33			Lbyy						Lateral
25	CA6	Channel(3.3...	33			Lbyy						Lateral
26	M75	PL 2.375x0.5	1.5			Lbyy						Lateral
27	MP2	Antenna Pip...	96			Lbyy						Lateral
28	H3	Face Pipes(...	96			Lbyy						Lateral
29	MP7	Antenna Pip...	96			Lbyy						Lateral
30	MP9	Antenna Pip...	96			Lbyy						Lateral
31	HR3	Handrail	96			Lbyy						Lateral
32	H2	Face Pipes(...	96			Lbyy						Lateral
33	MP4	Antenna Pip...	96			Lbyy						Lateral
34	MP6	Antenna Pip...	96			Lbyy						Lateral
35	HR2	Handrail	96			Lbyy						Lateral
36	MP8	Antenna Pip...	96			Lbyy						Lateral
37	MP5	Antenna Pip...	96			Lbyy						Lateral
38	MP10	Antenna Pip...	48			Lbyy						Lateral

Member Advanced Data

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat..	Analysis ...	Inactive	Seismic...
1	S3						Yes				None
2	GA4						Yes				None
3	GA3						Yes				None
4	P3	BenPIN	BenPIN				Yes	Default			None
5	S2						Yes				None
6	GA2						Yes				None
7	GA1						Yes				None
8	P2	BenPIN	BenPIN				Yes	Default			None
9	S1						Yes	Default			None
10	GA6						Yes				None
11	GA5						Yes				None
12	P1	BenPIN	BenPIN				Yes	Default			None
13	H1						Yes	Default			None
14	MP1						Yes	Default	+y+3		None
15	MP3						Yes		+y+3		None
16	HR1						Yes				None
17	CA8	OOOOOX	OOOOOX				Yes				None
18	CA9	OOOOOX	OOOOOX				Yes				None
19	CA7	OOOOOX	OOOOOX				Yes	Default			None
20	M32						Yes	** NA **			None
21	M35						Yes	** NA **			None
22	M36						Yes	** NA **			None
23	M39A						Yes	** NA **			None
24	CA3						Yes	Default			None
25	CA4						Yes	Default			None
26	CA1						Yes	Default			None
27	CA2						Yes	Default			None
28	CA5						Yes	Default			None
29	CA6						Yes	Default			None
30	M64	BenPIN					Yes	** NA **			None
31	M65						Yes	** NA **			None
32	M66	BenPIN					Yes	** NA **			None
33	M67						Yes	** NA **			None
34	M68	BenPIN					Yes	** NA **			None
35	M69						Yes	** NA **			None
36	M70	BenPIN					Yes	** NA **			None
37	M71						Yes	** NA **			None
38	M72	BenPIN					Yes	** NA **			None
39	M73						Yes	** NA **			None
40	M74	BenPIN					Yes	** NA **			None
41	M75						Yes	** NA **			None
42	MP2						Yes		+y+3		None
43	M43						Yes	** NA **			None
44	M44						Yes	** NA **			None
45	H3						Yes				None
46	MP7						Yes		+y+3		None
47	MP9						Yes		+y+3		None
48	HR3						Yes				None
49	M52						Yes	** NA **			None
50	M53						Yes	** NA **			None
51	M54						Yes	** NA **			None
52	M55						Yes	** NA **			None
53	H2						Yes				None
54	MP4						Yes		+y+3		None
55	MP6						Yes		+y+3		None
56	HR2						Yes				None

Member Advanced Data (Continued)

	Label	I Release	J Release	I Offset[in]	J Offset[in]	T/C Only	Physical	Defl Rat..	Analysis ...	Inactive	Seismic...
57	M66A						Yes	** NA **			None
58	M67A						Yes	** NA **			None
59	M68A						Yes	** NA **			None
60	M69A						Yes	** NA **			None
61	MP8						Yes		+y+3		None
62	M68B						Yes	** NA **			None
63	M69B						Yes	** NA **			None
64	MP5						Yes		+y+3		None
65	M71B						Yes	** NA **			None
66	M72B						Yes	** NA **			None
67	M67B						Yes	** NA **			None
68	MP10						Yes	Default			None

Material Takeoff

	Material	Size	Pieces	Length[in]	Weight[LB]
1	General				
2	RIGID		30	36.1	0
3	Total General		30	36.1	0
4					
5	Hot Rolled Steel				
6	A1011 36 Ksi	C3.38x2.06x0.25	6	198	98.255
7	A1011 36 Ksi	PL6.5x0.375	3	126	87.09
8	A1011 36 Ksi	L6.6x4.46x0.25	3	126	96.558
9	A36 Gr.36	PL 2.375x0.5	1	1.5	.505
10	A500 GR.C	2.88x0.120	3	288	84.974
11	A500 GR.C	HSS4X4X6	3	120	162.653
12	A500 GR.C	Pipe3.5x0.165	3	288	141.202
13	A500 GR.C	PIPE 2.5	10	912	416.364
14	A529 Gr. 50	L2x2x4	6	163.8	43.838
15	Total HR Steel		38	2223.3	1131.439

Hot Rolled Steel Section Sets

	Label	Shape	Type	Design List	Material	Design ...	A [in2]	Iyy [in4]	Izz [in4]	J [in4]
1	Corner Plates	PL6.5x0.375	Beam	None	A1011 36 Ksi	Typical	2.438	.029	8.582	.11
2	6"x0.37" Plate	Plate 6x.37	Beam	None	A1011 36 Ksi	Typical	2.22	.025	6.66	.097
3	Grating Angle	L2x2x4	Beam	None	A529 Gr. 50	Typical	.944	.346	.346	.021
4	Face Pipes(3.5x.16)	Pipe3.5x0.1...	Beam	None	A500 GR.C	Typical	1.729	2.409	2.409	4.819
5	Antenna Pipes	PIPE 2.5	Beam	None	A500 GR.C	Typical	1.61	1.45	1.45	2.89
6	Channel(3.38x2.06)	C3.38x2.06...	Beam	None	A1011 36 Ksi	Typical	1.75	.715	3.026	.034
7	Square Tubing	HSS4X4X6	Beam	None	A500 GR.C	Typical	4.78	10.3	10.3	17.5
8	Handrail Connector	L6.6x4.46x...	Beam	None	A1011 36 Ksi	Typical	2.703	4.759	12.473	.055
9	Handrail	2.88x0.120	Beam	None	A500 GR.C	Typical	1.04	.993	.993	1.985

Basic Load Cases

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distrib...	Area(Me...	Surface(...
1	Self Weight	DL		-1			13		3	
2	Wind Load AZI 0	WLZ					26			
3	Wind Load AZI 30	None					26			
4	Wind Load AZI 60	None					26			
5	Wind Load AZI 90	WLX					26			
6	Wind Load AZI 120	None					26			
7	Wind Load AZI 150	None					26			

Basic Load Cases (Continued)

	BLC Description	Category	X Gravity	Y Gravity	Z Gravity	Joint	Point	Distrib...	Area(Me...	Surface(...
8	Wind Load AZI 180	None					26			
9	Wind Load AZI 210	None					26			
10	Wind Load AZI 240	None					26			
11	Wind Load AZI 270	None					26			
12	Wind Load AZI 300	None					26			
13	Wind Load AZI 330	None					26			
14	Distr. Wind Load Z	WLZ						68		
15	Distr. Wind Load X	WLX						68		
16	Ice Weight	OL1					13	68	3	
17	Ice Wind Load AZI 0	OL2					26			
18	Ice Wind Load AZI 30	None					26			
19	Ice Wind Load AZI 60	None					26			
20	Ice Wind Load AZI 90	OL3					26			
21	Ice Wind Load AZI 120	None					26			
22	Ice Wind Load AZI 150	None					26			
23	Ice Wind Load AZI 180	None					26			
24	Ice Wind Load AZI 210	None					26			
25	Ice Wind Load AZI 240	None					26			
26	Ice Wind Load AZI 270	None					26			
27	Ice Wind Load AZI 300	None					26			
28	Ice Wind Load AZI 330	None					26			
29	Distr. Ice Wind Load Z	OL2						68		
30	Distr. Ice Wind Load X	OL3						68		
31	Seismic Load Z	ELZ			-278		13			
32	Seismic Load X	ELX	-278				13			
33	Service Live Loads	LL				3				
34	Maintenance Load 1	LL				1				
35	Maintenance Load 2	LL				1				
36	Maintenance Load 3	LL				1				
37	Maintenance Load 4	LL				1				
38	Maintenance Load 5	LL				1				
39	Maintenance Load 6	LL				1				
40	Maintenance Load 7	LL				1				
41	Maintenance Load 8	LL				1				
42	Maintenance Load 9	LL				1				
43	Maintenance Load 10	LL				1				
44	BLC 1 Transient Area Loads	None						9		
45	BLC 16 Transient Area Loads	None						9		

Load Combinations

	Description	S...	PDe...	SRSS	BLC	Factor	BLC Fac...	BLC Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...
1	1.4DL	Y...	Y		1	1.4														
2	1.2DL + 1WL AZI 0	Y...	Y		1	1.2	2	1	14	1	15									
3	1.2DL + 1WL AZI 30	Y...	Y		1	1.2	3	1	14	.866	15	.5								
4	1.2DL + 1WL AZI 60	Y...	Y		1	1.2	4	1	14	.5	15	.866								
5	1.2DL + 1WL AZI 90	Y...	Y		1	1.2	5	1	14		15	1								
6	1.2DL + 1WL AZI 120	Y...	Y		1	1.2	6	1	14	-.5	15	.866								
7	1.2DL + 1WL AZI 150	Y...	Y		1	1.2	7	1	14	-.8	15	.5								
8	1.2DL + 1WL AZI 180	Y...	Y		1	1.2	8	1	14	-1	15									
9	1.2DL + 1WL AZI 210	Y...	Y		1	1.2	9	1	14	-.8	15	-.5								
10	1.2DL + 1WL AZI 240	Y...	Y		1	1.2	10	1	14	-.5	15	-.8								
11	1.2DL + 1WL AZI 270	Y...	Y		1	1.2	11	1	14		15	-1								
12	1.2DL + 1WL AZI 300	Y...	Y		1	1.2	12	1	14	.5	15	-.8								
13	1.2DL + 1WL AZI 330	Y...	Y		1	1.2	13	1	14	.866	15	-.5								
14	0.9DL + 1WL AZI 0	Y...	Y		1	.9	2	1	14	1	15									

Load Combinations (Continued)

	Description	S...	PDe...	SRSS	BLC	Factor	BLC	Fac...	BLC	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...	Fac...	B...
72	1.0DL + 1.5LL + 1.0SWL (...)	Y..	Y		1	1	11	.272	14		15	-2...	33	1.5							
73	1.0DL + 1.5LL + 1.0SWL (...)	Y..	Y		1	1	12	.272	14	.136	15	-2...	33	1.5							
74	1.0DL + 1.5LL + 1.0SWL (...)	Y..	Y		1	1	13	.272	14	.236	15	-1...	33	1.5							
75	1.2DL + 1.5LL	Y..	Y		1	1.2	33	1.5													
76	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	2	.068	14	.068	15								
77	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	3	.068	14	.059	15	.034							
78	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	4	.068	14	.034	15	.059							
79	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	5	.068	14		15	.068							
80	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	6	.068	14	-.0...	15	.059							
81	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	7	.068	14	-.0...	15	.034							
82	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	8	.068	14	-.0...	15								
83	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	9	.068	14	-.0...	15	-.0...							
84	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	10	.068	14	-.0...	15	-.0...							
85	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	11	.068	14		15	-.0...							
86	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	12	.068	14	.034	15	-.0...							
87	1.2DL + 1.5LM-MP1 + 1S...	Y..	Y		1	1.2	34	1.5	13	.068	14	.059	15	-.0...							
88	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	2	.068	14	.068	15								
89	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	3	.068	14	.059	15	.034							
90	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	4	.068	14	.034	15	.059							
91	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	5	.068	14		15	.068							
92	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	6	.068	14	-.0...	15	.059							
93	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	7	.068	14	-.0...	15	.034							
94	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	8	.068	14	-.0...	15								
95	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	9	.068	14	-.0...	15	-.0...							
96	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	10	.068	14	-.0...	15	-.0...							
97	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	11	.068	14		15	-.0...							
98	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	12	.068	14	.034	15	-.0...							
99	1.2DL + 1.5LM-MP2 + 1S...	Y..	Y		1	1.2	35	1.5	13	.068	14	.059	15	-.0...							
100	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	2	.068	14	.068	15								
101	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	3	.068	14	.059	15	.034							
102	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	4	.068	14	.034	15	.059							
103	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	5	.068	14		15	.068							
104	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	6	.068	14	-.0...	15	.059							
105	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	7	.068	14	-.0...	15	.034							
106	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	8	.068	14	-.0...	15								
107	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	9	.068	14	-.0...	15	-.0...							
108	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	10	.068	14	-.0...	15	-.0...							
109	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	11	.068	14		15	-.0...							
110	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	12	.068	14	.034	15	-.0...							
111	1.2DL + 1.5LM-MP3 + 1S...	Y..	Y		1	1.2	36	1.5	13	.068	14	.059	15	-.0...							
112	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	2	.068	14	.068	15								
113	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	3	.068	14	.059	15	.034							
114	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	4	.068	14	.034	15	.059							
115	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	5	.068	14		15	.068							
116	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	6	.068	14	-.0...	15	.059							
117	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	7	.068	14	-.0...	15	.034							
118	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	8	.068	14	-.0...	15								
119	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	9	.068	14	-.0...	15	-.0...							
120	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	10	.068	14	-.0...	15	-.0...							
121	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	11	.068	14		15	-.0...							
122	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	12	.068	14	.034	15	-.0...							
123	1.2DL + 1.5LM-MP4 + 1S...	Y..	Y		1	1.2	37	1.5	13	.068	14	.059	15	-.0...							
124	1.2DL + 1.5LM-MP5 + 1S...	Y..	Y		1	1.2	38	1.5	2	.068	14	.068	15								
125	1.2DL + 1.5LM-MP5 + 1S...	Y..	Y		1	1.2	38	1.5	3	.068	14	.059	15	.034							
126	1.2DL + 1.5LM-MP5 + 1S...	Y..	Y		1	1.2	38	1.5	4	.068	14	.034	15	.059							
127	1.2DL + 1.5LM-MP5 + 1S...	Y..	Y		1	1.2	38	1.5	5	.068	14		15	.068							
128	1.2DL + 1.5LM-MP5 + 1S...	Y..	Y		1	1.2	38	1.5	6	.068	14	-.0...	15	.059							

Load Combinations (Continued)

	Description	S...	PDe...	SRSS	BLC	Factor	BLC	Fac...	BLC	Fac...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...	Fa...	B...						
186	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	4	.068	14.034	15.059																									
187	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	5	.068	14	15.068																									
188	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	6	.068	14	-0.15.059																									
189	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	7	.068	14	-0.15.034																									
190	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	8	.068	14	-0.15																									
191	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	9	.068	14	-0.15-0.0..																									
192	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	10	.068	14	-0.15-0.0..																									
193	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	11	.068	14	15-0.0..																									
194	1.2DL + 1.5LM-MP10 + 1S..Y..		Y		1	1.2	43	1.5	12	.068	14.034	15-0.0..																									

Joint Boundary Conditions

	Joint Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot.[k-ft/rad]	Y Rot.[k-ft/rad]	Z Rot.[k-ft/rad]
1	P24	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
2	P13	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction
3	P1	Reaction	Reaction	Reaction	Reaction	Reaction	Reaction

Envelope Joint Reactions

	Joint		X [lb]	LC	Y [lb]	LC	Z [lb]	LC	MX [lb-ft]	LC	MY [lb-...]	LC	MZ [lb-ft]	LC
1	P24	max	710.32	6	1499.9...	35	1080.755	13	520.714	16	1362.9...	19	3666.7...	132
2		min	-695.122	24	-260.852	16	-1072.575	19	-3175.929	84	-1381....	13	-1045....	16
3	P13	max	898.63	4	1834.5...	31	1173.79	15	549.192	24	1528.6...	15	778.474	24
4		min	-895.767	22	-145.554	24	-1182.225	9	-2810.524	92	-1576....	9	-4316....	140
5	P1	max	1112.203	17	1605.5...	27	576.218	2	3960.598	2	1273.7...	11	1578.3...	115
6		min	-1130.307	11	-244.916	20	-578.642	20	-1121.927	20	-1222....	17	-856.851	157
7	Totals:	max	2596.937	5	4460.4...	33	2748.457	14						
8		min	-2596.934	23	1554.0...	51	-2748.46	8						

Member Point Loads (BLC 1 : Self Weight)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	Y	-32.25	0
2	MP1	Y	-32.25	72
3	MP1	Y	-74.95	12
4	MP1	Y	-63.93	12
5	MP10	Y	-21.85	24
6	MP4	Y	-32.25	0
7	MP4	Y	-32.25	72
8	MP4	Y	-74.95	12
9	MP4	Y	-63.93	12
10	MP7	Y	-32.25	0
11	MP7	Y	-32.25	72
12	MP7	Y	-74.95	12
13	MP7	Y	-63.93	12

Member Point Loads (BLC 2 : Wind Load AZI 0)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	0	0
2	MP1	Z	-115.77	0
3	MP1	X	0	72
4	MP1	Z	-115.77	72
5	MP1	X	0	12
6	MP1	Z	-56.76	12
7	MP1	X	0	12

Member Point Loads (BLC 2 : Wind Load AZI 0) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
8	MP1	Z	-56.76	12
9	MP10	X	0	24
10	MP10	Z	-53.96	24
11	MP4	X	0	0
12	MP4	Z	-63.74	0
13	MP4	X	0	72
14	MP4	Z	-63.74	72
15	MP4	X	0	12
16	MP4	Z	-39.97	12
17	MP4	X	0	12
18	MP4	Z	-36.58	12
19	MP7	X	0	0
20	MP7	Z	-63.74	0
21	MP7	X	0	72
22	MP7	Z	-63.74	72
23	MP7	X	0	12
24	MP7	Z	-39.97	12
25	MP7	X	0	12
26	MP7	Z	-36.58	12

Member Point Loads (BLC 3 : Wind Load AZI 30)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-49.21	0
2	MP1	Z	-85.24	0
3	MP1	X	-49.21	72
4	MP1	Z	-85.24	72
5	MP1	X	-25.58	12
6	MP1	Z	-44.31	12
7	MP1	X	-25.02	12
8	MP1	Z	-43.33	12
9	MP10	X	-24.09	24
10	MP10	Z	-41.72	24
11	MP4	X	-49.21	0
12	MP4	Z	-85.24	0
13	MP4	X	-49.21	72
14	MP4	Z	-85.24	72
15	MP4	X	-25.58	12
16	MP4	Z	-44.31	12
17	MP4	X	-25.02	12
18	MP4	Z	-43.33	12
19	MP7	X	-23.2	0
20	MP7	Z	-40.18	0
21	MP7	X	-23.2	72
22	MP7	Z	-40.18	72
23	MP7	X	-17.19	12
24	MP7	Z	-29.77	12
25	MP7	X	-14.93	12
26	MP7	Z	-25.86	12

Member Point Loads (BLC 4 : Wind Load AZI 60)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-55.2	0
2	MP1	Z	-31.87	0
3	MP1	X	-55.2	72
4	MP1	Z	-31.87	72
5	MP1	X	-34.62	12

Member Point Loads (BLC 4 : Wind Load AZI 60) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
6	MP1	Z	-19.99	12
7	MP1	X	-31.68	12
8	MP1	Z	-18.29	12
9	MP10	X	-31.71	24
10	MP10	Z	-18.31	24
11	MP4	X	-100.26	0
12	MP4	Z	-57.89	0
13	MP4	X	-100.26	72
14	MP4	Z	-57.89	72
15	MP4	X	-49.16	12
16	MP4	Z	-28.38	12
17	MP4	X	-49.16	12
18	MP4	Z	-28.38	12
19	MP7	X	-55.2	0
20	MP7	Z	-31.87	0
21	MP7	X	-55.2	72
22	MP7	Z	-31.87	72
23	MP7	X	-34.62	12
24	MP7	Z	-19.99	12
25	MP7	X	-31.68	12
26	MP7	Z	-18.29	12

Member Point Loads (BLC 5 : Wind Load AZI 90)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-46.4	0
2	MP1	Z	0	0
3	MP1	X	-46.4	72
4	MP1	Z	0	72
5	MP1	X	-34.37	12
6	MP1	Z	0	12
7	MP1	X	-29.86	12
8	MP1	Z	0	12
9	MP10	X	-30.83	24
10	MP10	Z	0	24
11	MP4	X	-98.43	0
12	MP4	Z	0	0
13	MP4	X	-98.43	72
14	MP4	Z	0	72
15	MP4	X	-51.16	12
16	MP4	Z	0	12
17	MP4	X	-50.03	12
18	MP4	Z	0	12
19	MP7	X	-98.43	0
20	MP7	Z	0	0
21	MP7	X	-98.43	72
22	MP7	Z	0	72
23	MP7	X	-51.16	12
24	MP7	Z	0	12
25	MP7	X	-50.03	12
26	MP7	Z	0	12

Member Point Loads (BLC 6 : Wind Load AZI 120)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-55.2	0
2	MP1	Z	31.87	0
3	MP1	X	-55.2	72

Member Point Loads (BLC 6 : Wind Load AZI 120) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
4	MP1	Z	31.87	72
5	MP1	X	-34.62	12
6	MP1	Z	19.99	12
7	MP1	X	-31.68	12
8	MP1	Z	18.29	12
9	MP10	X	-31.71	24
10	MP10	Z	18.31	24
11	MP4	X	-55.2	0
12	MP4	Z	31.87	0
13	MP4	X	-55.2	72
14	MP4	Z	31.87	72
15	MP4	X	-34.62	12
16	MP4	Z	19.99	12
17	MP4	X	-31.68	12
18	MP4	Z	18.29	12
19	MP7	X	-100.26	0
20	MP7	Z	57.89	0
21	MP7	X	-100.26	72
22	MP7	Z	57.89	72
23	MP7	X	-49.16	12
24	MP7	Z	28.38	12
25	MP7	X	-49.16	12
26	MP7	Z	28.38	12

Member Point Loads (BLC 7 : Wind Load AZI 150)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-49.21	0
2	MP1	Z	85.24	0
3	MP1	X	-49.21	72
4	MP1	Z	85.24	72
5	MP1	X	-25.58	12
6	MP1	Z	44.31	12
7	MP1	X	-25.02	12
8	MP1	Z	43.33	12
9	MP10	X	-24.09	24
10	MP10	Z	41.72	24
11	MP4	X	-23.2	0
12	MP4	Z	40.18	0
13	MP4	X	-23.2	72
14	MP4	Z	40.18	72
15	MP4	X	-17.19	12
16	MP4	Z	29.77	12
17	MP4	X	-14.93	12
18	MP4	Z	25.86	12
19	MP7	X	-49.21	0
20	MP7	Z	85.24	0
21	MP7	X	-49.21	72
22	MP7	Z	85.24	72
23	MP7	X	-25.58	12
24	MP7	Z	44.31	12
25	MP7	X	-25.02	12
26	MP7	Z	43.33	12

Member Point Loads (BLC 8 : Wind Load AZI 180)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	0	0

Member Point Loads (BLC 8 : Wind Load AZI 180) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
2	MP1	Z	115.77	0
3	MP1	X	0	72
4	MP1	Z	115.77	72
5	MP1	X	0	12
6	MP1	Z	56.76	12
7	MP1	X	0	12
8	MP1	Z	56.76	12
9	MP10	X	0	24
10	MP10	Z	53.96	24
11	MP4	X	0	0
12	MP4	Z	63.74	0
13	MP4	X	0	72
14	MP4	Z	63.74	72
15	MP4	X	0	12
16	MP4	Z	39.97	12
17	MP4	X	0	12
18	MP4	Z	36.58	12
19	MP7	X	0	0
20	MP7	Z	63.74	0
21	MP7	X	0	72
22	MP7	Z	63.74	72
23	MP7	X	0	12
24	MP7	Z	39.97	12
25	MP7	X	0	12
26	MP7	Z	36.58	12

Member Point Loads (BLC 9 : Wind Load AZI 210)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	49.21	0
2	MP1	Z	85.24	0
3	MP1	X	49.21	72
4	MP1	Z	85.24	72
5	MP1	X	25.58	12
6	MP1	Z	44.31	12
7	MP1	X	25.02	12
8	MP1	Z	43.33	12
9	MP10	X	24.09	24
10	MP10	Z	41.72	24
11	MP4	X	49.21	0
12	MP4	Z	85.24	0
13	MP4	X	49.21	72
14	MP4	Z	85.24	72
15	MP4	X	25.58	12
16	MP4	Z	44.31	12
17	MP4	X	25.02	12
18	MP4	Z	43.33	12
19	MP7	X	23.2	0
20	MP7	Z	40.18	0
21	MP7	X	23.2	72
22	MP7	Z	40.18	72
23	MP7	X	17.19	12
24	MP7	Z	29.77	12
25	MP7	X	14.93	12
26	MP7	Z	25.86	12

Member Point Loads (BLC 10 : Wind Load AZI 240)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	55.2	0
2	MP1	Z	31.87	0
3	MP1	X	55.2	72
4	MP1	Z	31.87	72
5	MP1	X	34.62	12
6	MP1	Z	19.99	12
7	MP1	X	31.68	12
8	MP1	Z	18.29	12
9	MP10	X	31.71	24
10	MP10	Z	18.31	24
11	MP4	X	100.26	0
12	MP4	Z	57.89	0
13	MP4	X	100.26	72
14	MP4	Z	57.89	72
15	MP4	X	49.16	12
16	MP4	Z	28.38	12
17	MP4	X	49.16	12
18	MP4	Z	28.38	12
19	MP7	X	55.2	0
20	MP7	Z	31.87	0
21	MP7	X	55.2	72
22	MP7	Z	31.87	72
23	MP7	X	34.62	12
24	MP7	Z	19.99	12
25	MP7	X	31.68	12
26	MP7	Z	18.29	12

Member Point Loads (BLC 11 : Wind Load AZI 270)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	46.4	0
2	MP1	Z	0	0
3	MP1	X	46.4	72
4	MP1	Z	0	72
5	MP1	X	34.37	12
6	MP1	Z	0	12
7	MP1	X	29.86	12
8	MP1	Z	0	12
9	MP10	X	30.83	24
10	MP10	Z	0	24
11	MP4	X	98.43	0
12	MP4	Z	0	0
13	MP4	X	98.43	72
14	MP4	Z	0	72
15	MP4	X	51.16	12
16	MP4	Z	0	12
17	MP4	X	50.03	12
18	MP4	Z	0	12
19	MP7	X	98.43	0
20	MP7	Z	0	0
21	MP7	X	98.43	72
22	MP7	Z	0	72
23	MP7	X	51.16	12
24	MP7	Z	0	12
25	MP7	X	50.03	12
26	MP7	Z	0	12

Member Point Loads (BLC 12 : Wind Load AZI 300)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	55.2	0
2	MP1	Z	-31.87	0
3	MP1	X	55.2	72
4	MP1	Z	-31.87	72
5	MP1	X	34.62	12
6	MP1	Z	-19.99	12
7	MP1	X	31.68	12
8	MP1	Z	-18.29	12
9	MP10	X	31.71	24
10	MP10	Z	-18.31	24
11	MP4	X	55.2	0
12	MP4	Z	-31.87	0
13	MP4	X	55.2	72
14	MP4	Z	-31.87	72
15	MP4	X	34.62	12
16	MP4	Z	-19.99	12
17	MP4	X	31.68	12
18	MP4	Z	-18.29	12
19	MP7	X	100.26	0
20	MP7	Z	-57.89	0
21	MP7	X	100.26	72
22	MP7	Z	-57.89	72
23	MP7	X	49.16	12
24	MP7	Z	-28.38	12
25	MP7	X	49.16	12
26	MP7	Z	-28.38	12

Member Point Loads (BLC 13 : Wind Load AZI 330)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	49.21	0
2	MP1	Z	-85.24	0
3	MP1	X	49.21	72
4	MP1	Z	-85.24	72
5	MP1	X	25.58	12
6	MP1	Z	-44.31	12
7	MP1	X	25.02	12
8	MP1	Z	-43.33	12
9	MP10	X	24.09	24
10	MP10	Z	-41.72	24
11	MP4	X	23.2	0
12	MP4	Z	-40.18	0
13	MP4	X	23.2	72
14	MP4	Z	-40.18	72
15	MP4	X	17.19	12
16	MP4	Z	-29.77	12
17	MP4	X	14.93	12
18	MP4	Z	-25.86	12
19	MP7	X	49.21	0
20	MP7	Z	-85.24	0
21	MP7	X	49.21	72
22	MP7	Z	-85.24	72
23	MP7	X	25.58	12
24	MP7	Z	-44.31	12
25	MP7	X	25.02	12
26	MP7	Z	-43.33	12

Member Point Loads (BLC 16 : Ice Weight)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	Y	-88.319	0
2	MP1	Y	-88.319	72
3	MP1	Y	-44.683	12
4	MP1	Y	-41.804	12
5	MP10	Y	-40.731	24
6	MP4	Y	-88.319	0
7	MP4	Y	-88.319	72
8	MP4	Y	-44.683	12
9	MP4	Y	-41.804	12
10	MP7	Y	-88.319	0
11	MP7	Y	-88.319	72
12	MP7	Y	-44.683	12
13	MP7	Y	-41.804	12

Member Point Loads (BLC 17 : Ice Wind Load AZI 0)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	0	0
2	MP1	Z	-16.27	0
3	MP1	X	0	72
4	MP1	Z	-16.27	72
5	MP1	X	0	12
6	MP1	Z	-6.14	12
7	MP1	X	0	12
8	MP1	Z	-6.14	12
9	MP10	X	0	24
10	MP10	Z	-6.04	24
11	MP4	X	0	0
12	MP4	Z	-12.47	0
13	MP4	X	0	72
14	MP4	Z	-12.47	72
15	MP4	X	0	12
16	MP4	Z	-5.24	12
17	MP4	X	0	12
18	MP4	Z	-5.04	12
19	MP7	X	0	0
20	MP7	Z	-12.47	0
21	MP7	X	0	72
22	MP7	Z	-12.47	72
23	MP7	X	0	12
24	MP7	Z	-5.24	12
25	MP7	X	0	12
26	MP7	Z	-5.04	12

Member Point Loads (BLC 18 : Ice Wind Load AZI 30)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-7.5	0
2	MP1	Z	-12.99	0
3	MP1	X	-7.5	72
4	MP1	Z	-12.99	72
5	MP1	X	-2.92	12
6	MP1	Z	-5.06	12
7	MP1	X	-2.89	12
8	MP1	Z	-5	12
9	MP10	X	-2.86	24
10	MP10	Z	-4.96	24
11	MP4	X	-7.5	0

Member Point Loads (BLC 18 : Ice Wind Load AZI 30) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
12	MP4	Z	-12.99	0
13	MP4	X	-7.5	72
14	MP4	Z	-12.99	72
15	MP4	X	-2.92	12
16	MP4	Z	-5.06	12
17	MP4	X	-2.89	12
18	MP4	Z	-5	12
19	MP7	X	-5.6	0
20	MP7	Z	-9.7	0
21	MP7	X	-5.6	72
22	MP7	Z	-9.7	72
23	MP7	X	-2.47	12
24	MP7	Z	-4.28	12
25	MP7	X	-2.34	12
26	MP7	Z	-4.04	12

Member Point Loads (BLC 19 : Ice Wind Load AZI 60)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-10.8	0
2	MP1	Z	-6.23	0
3	MP1	X	-10.8	72
4	MP1	Z	-6.23	72
5	MP1	X	-4.54	12
6	MP1	Z	-2.62	12
7	MP1	X	-4.36	12
8	MP1	Z	-2.52	12
9	MP10	X	-4.4	24
10	MP10	Z	-2.54	24
11	MP4	X	-14.09	0
12	MP4	Z	-8.13	0
13	MP4	X	-14.09	72
14	MP4	Z	-8.13	72
15	MP4	X	-5.31	12
16	MP4	Z	-3.07	12
17	MP4	X	-5.31	12
18	MP4	Z	-3.07	12
19	MP7	X	-10.8	0
20	MP7	Z	-6.23	0
21	MP7	X	-10.8	72
22	MP7	Z	-6.23	72
23	MP7	X	-4.54	12
24	MP7	Z	-2.62	12
25	MP7	X	-4.36	12
26	MP7	Z	-2.52	12

Member Point Loads (BLC 20 : Ice Wind Load AZI 90)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-11.2	0
2	MP1	Z	0	0
3	MP1	X	-11.2	72
4	MP1	Z	0	72
5	MP1	X	-4.94	12
6	MP1	Z	0	12
7	MP1	X	-4.67	12
8	MP1	Z	0	12
9	MP10	X	-4.77	24

Member Point Loads (BLC 20 : Ice Wind Load AZI 90) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
10	MP10	Z	0	24
11	MP4	X	-15	0
12	MP4	Z	0	0
13	MP4	X	-15	72
14	MP4	Z	0	72
15	MP4	X	-5.84	12
16	MP4	Z	0	12
17	MP4	X	-5.77	12
18	MP4	Z	0	12
19	MP7	X	-15	0
20	MP7	Z	0	0
21	MP7	X	-15	72
22	MP7	Z	0	72
23	MP7	X	-5.84	12
24	MP7	Z	0	12
25	MP7	X	-5.77	12
26	MP7	Z	0	12

Member Point Loads (BLC 21 : Ice Wind Load AZI 120)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-10.8	0
2	MP1	Z	6.23	0
3	MP1	X	-10.8	72
4	MP1	Z	6.23	72
5	MP1	X	-4.54	12
6	MP1	Z	2.62	12
7	MP1	X	-4.36	12
8	MP1	Z	2.52	12
9	MP10	X	-4.4	24
10	MP10	Z	2.54	24
11	MP4	X	-10.8	0
12	MP4	Z	6.23	0
13	MP4	X	-10.8	72
14	MP4	Z	6.23	72
15	MP4	X	-4.54	12
16	MP4	Z	2.62	12
17	MP4	X	-4.36	12
18	MP4	Z	2.52	12
19	MP7	X	-14.09	0
20	MP7	Z	8.13	0
21	MP7	X	-14.09	72
22	MP7	Z	8.13	72
23	MP7	X	-5.31	12
24	MP7	Z	3.07	12
25	MP7	X	-5.31	12
26	MP7	Z	3.07	12

Member Point Loads (BLC 22 : Ice Wind Load AZI 150)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-7.5	0
2	MP1	Z	12.99	0
3	MP1	X	-7.5	72
4	MP1	Z	12.99	72
5	MP1	X	-2.92	12
6	MP1	Z	5.06	12
7	MP1	X	-2.89	12

Member Point Loads (BLC 22 : Ice Wind Load AZI 150) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
8	MP1	Z	5	12
9	MP10	X	-2.86	24
10	MP10	Z	4.96	24
11	MP4	X	-5.6	0
12	MP4	Z	9.7	0
13	MP4	X	-5.6	72
14	MP4	Z	9.7	72
15	MP4	X	-2.47	12
16	MP4	Z	4.28	12
17	MP4	X	-2.34	12
18	MP4	Z	4.04	12
19	MP7	X	-7.5	0
20	MP7	Z	12.99	0
21	MP7	X	-7.5	72
22	MP7	Z	12.99	72
23	MP7	X	-2.92	12
24	MP7	Z	5.06	12
25	MP7	X	-2.89	12
26	MP7	Z	5	12

Member Point Loads (BLC 23 : Ice Wind Load AZI 180)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	0	0
2	MP1	Z	16.27	0
3	MP1	X	0	72
4	MP1	Z	16.27	72
5	MP1	X	0	12
6	MP1	Z	6.14	12
7	MP1	X	0	12
8	MP1	Z	6.14	12
9	MP10	X	0	24
10	MP10	Z	6.04	24
11	MP4	X	0	0
12	MP4	Z	12.47	0
13	MP4	X	0	72
14	MP4	Z	12.47	72
15	MP4	X	0	12
16	MP4	Z	5.24	12
17	MP4	X	0	12
18	MP4	Z	5.04	12
19	MP7	X	0	0
20	MP7	Z	12.47	0
21	MP7	X	0	72
22	MP7	Z	12.47	72
23	MP7	X	0	12
24	MP7	Z	5.24	12
25	MP7	X	0	12
26	MP7	Z	5.04	12

Member Point Loads (BLC 24 : Ice Wind Load AZI 210)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	7.5	0
2	MP1	Z	12.99	0
3	MP1	X	7.5	72
4	MP1	Z	12.99	72
5	MP1	X	2.92	12

Member Point Loads (BLC 24 : Ice Wind Load AZI 210) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
6	MP1	Z	5.06	12
7	MP1	X	2.89	12
8	MP1	Z	5	12
9	MP10	X	2.86	24
10	MP10	Z	4.96	24
11	MP4	X	7.5	0
12	MP4	Z	12.99	0
13	MP4	X	7.5	72
14	MP4	Z	12.99	72
15	MP4	X	2.92	12
16	MP4	Z	5.06	12
17	MP4	X	2.89	12
18	MP4	Z	5	12
19	MP7	X	5.6	0
20	MP7	Z	9.7	0
21	MP7	X	5.6	72
22	MP7	Z	9.7	72
23	MP7	X	2.47	12
24	MP7	Z	4.28	12
25	MP7	X	2.34	12
26	MP7	Z	4.04	12

Member Point Loads (BLC 25 : Ice Wind Load AZI 240)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	10.8	0
2	MP1	Z	6.23	0
3	MP1	X	10.8	72
4	MP1	Z	6.23	72
5	MP1	X	4.54	12
6	MP1	Z	2.62	12
7	MP1	X	4.36	12
8	MP1	Z	2.52	12
9	MP10	X	4.4	24
10	MP10	Z	2.54	24
11	MP4	X	14.09	0
12	MP4	Z	8.13	0
13	MP4	X	14.09	72
14	MP4	Z	8.13	72
15	MP4	X	5.31	12
16	MP4	Z	3.07	12
17	MP4	X	5.31	12
18	MP4	Z	3.07	12
19	MP7	X	10.8	0
20	MP7	Z	6.23	0
21	MP7	X	10.8	72
22	MP7	Z	6.23	72
23	MP7	X	4.54	12
24	MP7	Z	2.62	12
25	MP7	X	4.36	12
26	MP7	Z	2.52	12

Member Point Loads (BLC 26 : Ice Wind Load AZI 270)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	11.2	0
2	MP1	Z	0	0
3	MP1	X	11.2	72

Member Point Loads (BLC 26 : Ice Wind Load AZI 270) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
4	MP1	Z	0	72
5	MP1	X	4.94	12
6	MP1	Z	0	12
7	MP1	X	4.67	12
8	MP1	Z	0	12
9	MP10	X	4.77	24
10	MP10	Z	0	24
11	MP4	X	15	0
12	MP4	Z	0	0
13	MP4	X	15	72
14	MP4	Z	0	72
15	MP4	X	5.84	12
16	MP4	Z	0	12
17	MP4	X	5.77	12
18	MP4	Z	0	12
19	MP7	X	15	0
20	MP7	Z	0	0
21	MP7	X	15	72
22	MP7	Z	0	72
23	MP7	X	5.84	12
24	MP7	Z	0	12
25	MP7	X	5.77	12
26	MP7	Z	0	12

Member Point Loads (BLC 27 : Ice Wind Load AZI 300)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	10.8	0
2	MP1	Z	-6.23	0
3	MP1	X	10.8	72
4	MP1	Z	-6.23	72
5	MP1	X	4.54	12
6	MP1	Z	-2.62	12
7	MP1	X	4.36	12
8	MP1	Z	-2.52	12
9	MP10	X	4.4	24
10	MP10	Z	-2.54	24
11	MP4	X	10.8	0
12	MP4	Z	-6.23	0
13	MP4	X	10.8	72
14	MP4	Z	-6.23	72
15	MP4	X	4.54	12
16	MP4	Z	-2.62	12
17	MP4	X	4.36	12
18	MP4	Z	-2.52	12
19	MP7	X	14.09	0
20	MP7	Z	-8.13	0
21	MP7	X	14.09	72
22	MP7	Z	-8.13	72
23	MP7	X	5.31	12
24	MP7	Z	-3.07	12
25	MP7	X	5.31	12
26	MP7	Z	-3.07	12

Member Point Loads (BLC 28 : Ice Wind Load AZI 330)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	7.5	0

Member Point Loads (BLC 28 : Ice Wind Load AZI 330) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
2	MP1	Z	-12.99	0
3	MP1	X	7.5	72
4	MP1	Z	-12.99	72
5	MP1	X	2.92	12
6	MP1	Z	-5.06	12
7	MP1	X	2.89	12
8	MP1	Z	-5	12
9	MP10	X	2.86	24
10	MP10	Z	-4.96	24
11	MP4	X	5.6	0
12	MP4	Z	-9.7	0
13	MP4	X	5.6	72
14	MP4	Z	-9.7	72
15	MP4	X	2.47	12
16	MP4	Z	-4.28	12
17	MP4	X	2.34	12
18	MP4	Z	-4.04	12
19	MP7	X	7.5	0
20	MP7	Z	-12.99	0
21	MP7	X	7.5	72
22	MP7	Z	-12.99	72
23	MP7	X	2.92	12
24	MP7	Z	-5.06	12
25	MP7	X	2.89	12
26	MP7	Z	-5	12

Member Point Loads (BLC 31 : Seismic Load Z)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	Z	-8.978	0
2	MP1	Z	-8.978	72
3	MP1	Z	-20.866	12
4	MP1	Z	-17.798	12
5	MP10	Z	-6.083	24
6	MP4	Z	-8.978	0
7	MP4	Z	-8.978	72
8	MP4	Z	-20.866	12
9	MP4	Z	-17.798	12
10	MP7	Z	-8.978	0
11	MP7	Z	-8.978	72
12	MP7	Z	-20.866	12
13	MP7	Z	-17.798	12

Member Point Loads (BLC 32 : Seismic Load X)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
1	MP1	X	-8.978	0
2	MP1	X	-8.978	72
3	MP1	X	-20.866	12
4	MP1	X	-17.798	12
5	MP10	X	-6.083	24
6	MP4	X	-8.978	0
7	MP4	X	-8.978	72
8	MP4	X	-20.866	12
9	MP4	X	-17.798	12
10	MP7	X	-8.978	0
11	MP7	X	-8.978	72
12	MP7	X	-20.866	12

Member Point Loads (BLC 32 : Seismic Load X) (Continued)

	Member Label	Direction	Magnitude[lb.lb-ft]	Location[in.%]
13	MP7	X	-17.798	12

Joint Loads and Enforced Displacements (BLC 33 : Service Live Loads)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N72B	L	Y	-250
2	N135A	L	Y	-250
3	N129B	L	Y	-250

Joint Loads and Enforced Displacements (BLC 34 : Maintenance Load 1)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N70A	L	Y	-500

Joint Loads and Enforced Displacements (BLC 35 : Maintenance Load 2)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N69A	L	Y	-500

Joint Loads and Enforced Displacements (BLC 36 : Maintenance Load 3)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N76	L	Y	-500

Joint Loads and Enforced Displacements (BLC 37 : Maintenance Load 4)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N94	L	Y	-500

Joint Loads and Enforced Displacements (BLC 38 : Maintenance Load 5)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N93	L	Y	-500

Joint Loads and Enforced Displacements (BLC 39 : Maintenance Load 6)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N122	L	Y	-500

Joint Loads and Enforced Displacements (BLC 40 : Maintenance Load 7)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N121	L	Y	-500

Joint Loads and Enforced Displacements (BLC 41 : Maintenance Load 8)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N133B	L	Y	-500

Joint Loads and Enforced Displacements (BLC 42 : Maintenance Load 9)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N139	L	Y	-500

Joint Loads and Enforced Displacements (BLC 43 : Maintenance Load 10)

	Joint Label	L,D,M	Direction	Magnitude[(lb.lb-ft), (in.rad), (lb*s^2...]
1	N120A	L	Y	-500

Member Distributed Loads (BLC 14 : Distr. Wind Load Z)

Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[in, %]	End Location[in, %]
1	S3	-64.239	-64.239	0	%100
2	GA4	-64.239	-64.239	0	%100
3	GA3	-64.239	-64.239	0	%100
4	P3	-64.239	-64.239	0	%100
5	S2	-64.239	-64.239	0	%100
6	GA2	-64.239	-64.239	0	%100
7	GA1	-64.239	-64.239	0	%100
8	P2	-64.239	-64.239	0	%100
9	S1	-64.239	-64.239	0	%100
10	GA6	-64.239	-64.239	0	%100
11	GA5	-64.239	-64.239	0	%100
12	P1	-64.239	-64.239	0	%100
13	H1	-38.543	-38.543	0	%100
14	MP1	-38.543	-38.543	0	%100
15	MP3	-38.543	-38.543	0	%100
16	HR1	-38.543	-38.543	0	%100
17	CA8	-64.239	-64.239	0	%100
18	CA9	-64.239	-64.239	0	%100
19	CA7	-64.239	-64.239	0	%100
20	M32	0	0	0	%100
21	M35	0	0	0	%100
22	M36	0	0	0	%100
23	M39A	0	0	0	%100
24	CA3	-64.239	-64.239	0	%100
25	CA4	-64.239	-64.239	0	%100
26	CA1	-64.239	-64.239	0	%100
27	CA2	-64.239	-64.239	0	%100
28	CA5	-64.239	-64.239	0	%100
29	CA6	-64.239	-64.239	0	%100
30	M64	0	0	0	%100
31	M65	0	0	0	%100
32	M66	0	0	0	%100
33	M67	0	0	0	%100
34	M68	0	0	0	%100
35	M69	0	0	0	%100
36	M70	0	0	0	%100
37	M71	0	0	0	%100
38	M72	0	0	0	%100
39	M73	0	0	0	%100
40	M74	0	0	0	%100
41	M75	-64.239	-64.239	0	%100
42	MP2	-38.543	-38.543	0	%100
43	M43	0	0	0	%100
44	M44	0	0	0	%100
45	H3	-38.543	-38.543	0	%100
46	MP7	-38.543	-38.543	0	%100
47	MP9	-38.543	-38.543	0	%100
48	HR3	-38.543	-38.543	0	%100
49	M52	0	0	0	%100
50	M53	0	0	0	%100
51	M54	0	0	0	%100
52	M55	0	0	0	%100
53	H2	-38.543	-38.543	0	%100
54	MP4	-38.543	-38.543	0	%100
55	MP6	-38.543	-38.543	0	%100
56	HR2	-38.543	-38.543	0	%100

Member Distributed Loads (BLC 14 : Distr. Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft,F...	Start Location[in, %]	End Location[in, %]
57	M66A	SZ	0	0	0	%100
58	M67A	SZ	0	0	0	%100
59	M68A	SZ	0	0	0	%100
60	M69A	SZ	0	0	0	%100
61	MP8	SZ	-38.543	-38.543	0	%100
62	M68B	SZ	0	0	0	%100
63	M69B	SZ	0	0	0	%100
64	MP5	SZ	-38.543	-38.543	0	%100
65	M71B	SZ	0	0	0	%100
66	M72B	SZ	0	0	0	%100
67	M67B	SZ	0	0	0	%100
68	MP10	SZ	-38.543	-38.543	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft,F...	Start Location[in, %]	End Location[in, %]
1	S3	SX	-64.239	-64.239	0	%100
2	GA4	SX	-64.239	-64.239	0	%100
3	GA3	SX	-64.239	-64.239	0	%100
4	P3	SX	-64.239	-64.239	0	%100
5	S2	SX	-64.239	-64.239	0	%100
6	GA2	SX	-64.239	-64.239	0	%100
7	GA1	SX	-64.239	-64.239	0	%100
8	P2	SX	-64.239	-64.239	0	%100
9	S1	SX	-64.239	-64.239	0	%100
10	GA6	SX	-64.239	-64.239	0	%100
11	GA5	SX	-64.239	-64.239	0	%100
12	P1	SX	-64.239	-64.239	0	%100
13	H1	SX	-38.543	-38.543	0	%100
14	MP1	SX	-38.543	-38.543	0	%100
15	MP3	SX	-38.543	-38.543	0	%100
16	HR1	SX	-38.543	-38.543	0	%100
17	CA8	SX	-64.239	-64.239	0	%100
18	CA9	SX	-64.239	-64.239	0	%100
19	CA7	SX	-64.239	-64.239	0	%100
20	M32	SX	0	0	0	%100
21	M35	SX	0	0	0	%100
22	M36	SX	0	0	0	%100
23	M39A	SX	0	0	0	%100
24	CA3	SX	-64.239	-64.239	0	%100
25	CA4	SX	-64.239	-64.239	0	%100
26	CA1	SX	-64.239	-64.239	0	%100
27	CA2	SX	-64.239	-64.239	0	%100
28	CA5	SX	-64.239	-64.239	0	%100
29	CA6	SX	-64.239	-64.239	0	%100
30	M64	SX	0	0	0	%100
31	M65	SX	0	0	0	%100
32	M66	SX	0	0	0	%100
33	M67	SX	0	0	0	%100
34	M68	SX	0	0	0	%100
35	M69	SX	0	0	0	%100
36	M70	SX	0	0	0	%100
37	M71	SX	0	0	0	%100
38	M72	SX	0	0	0	%100
39	M73	SX	0	0	0	%100
40	M74	SX	0	0	0	%100
41	M75	SX	-64.239	-64.239	0	%100

Member Distributed Loads (BLC 15 : Distr. Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft,F...]	Start Location[in, %]	End Location[in, %]
42	MP2	SX	-38.543	-38.543	0	%100
43	M43	SX	0	0	0	%100
44	M44	SX	0	0	0	%100
45	H3	SX	-38.543	-38.543	0	%100
46	MP7	SX	-38.543	-38.543	0	%100
47	MP9	SX	-38.543	-38.543	0	%100
48	HR3	SX	-38.543	-38.543	0	%100
49	M52	SX	0	0	0	%100
50	M53	SX	0	0	0	%100
51	M54	SX	0	0	0	%100
52	M55	SX	0	0	0	%100
53	H2	SX	-38.543	-38.543	0	%100
54	MP4	SX	-38.543	-38.543	0	%100
55	MP6	SX	-38.543	-38.543	0	%100
56	HR2	SX	-38.543	-38.543	0	%100
57	M66A	SX	0	0	0	%100
58	M67A	SX	0	0	0	%100
59	M68A	SX	0	0	0	%100
60	M69A	SX	0	0	0	%100
61	MP8	SX	-38.543	-38.543	0	%100
62	M68B	SX	0	0	0	%100
63	M69B	SX	0	0	0	%100
64	MP5	SX	-38.543	-38.543	0	%100
65	M71B	SX	0	0	0	%100
66	M72B	SX	0	0	0	%100
67	M67B	SX	0	0	0	%100
68	MP10	SX	-38.543	-38.543	0	%100

Member Distributed Loads (BLC 16 : Ice Weight)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft,F...]	Start Location[in, %]	End Location[in, %]
1	S3	Y	-9.389	-9.389	0	%100
2	GA4	Y	-5.477	-5.477	0	%100
3	GA3	Y	-5.477	-5.477	0	%100
4	P3	Y	-10.57	-10.57	0	%100
5	S2	Y	-9.389	-9.389	0	%100
6	GA2	Y	-5.477	-5.477	0	%100
7	GA1	Y	-5.477	-5.477	0	%100
8	P2	Y	-10.57	-10.57	0	%100
9	S1	Y	-9.389	-9.389	0	%100
10	GA6	Y	-5.477	-5.477	0	%100
11	GA5	Y	-5.477	-5.477	0	%100
12	P1	Y	-10.57	-10.57	0	%100
13	H1	Y	-6.406	-6.406	0	%100
14	MP1	Y	-5.542	-5.542	0	%100
15	MP3	Y	-5.542	-5.542	0	%100
16	HR1	Y	-5.548	-5.548	0	%100
17	CA8	Y	-12.582	-12.582	0	%100
18	CA9	Y	-12.582	-12.582	0	%100
19	CA7	Y	-12.582	-12.582	0	%100
20	M32	Y	-1.566	-1.566	0	%100
21	M35	Y	-1.566	-1.566	0	%100
22	M36	Y	-1.566	-1.566	0	%100
23	M39A	Y	-1.566	-1.566	0	%100
24	CA3	Y	-7.04	-7.04	0	%100
25	CA4	Y	-7.04	-7.04	0	%100
26	CA1	Y	-7.04	-7.04	0	%100

Member Distributed Loads (BLC 16 : Ice Weight) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft,F...	Start Location[in, %]	End Location[in, %]
27	CA2	Y	-7.04	-7.04	0	%100
28	CA5	Y	-7.04	-7.04	0	%100
29	CA6	Y	-7.04	-7.04	0	%100
30	M64	Y	-1.566	-1.566	0	%100
31	M65	Y	-1.566	-1.566	0	%100
32	M66	Y	-1.566	-1.566	0	%100
33	M67	Y	-1.566	-1.566	0	%100
34	M68	Y	-1.566	-1.566	0	%100
35	M69	Y	-1.566	-1.566	0	%100
36	M70	Y	-1.566	-1.566	0	%100
37	M71	Y	-1.566	-1.566	0	%100
38	M72	Y	-1.566	-1.566	0	%100
39	M73	Y	-1.566	-1.566	0	%100
40	M74	Y	-1.566	-1.566	0	%100
41	M75	Y	-4.922	-4.922	0	%100
42	MP2	Y	-5.542	-5.542	0	%100
43	M43	Y	-1.566	-1.566	0	%100
44	M44	Y	-1.566	-1.566	0	%100
45	H3	Y	-6.406	-6.406	0	%100
46	MP7	Y	-5.542	-5.542	0	%100
47	MP9	Y	-5.542	-5.542	0	%100
48	HR3	Y	-5.548	-5.548	0	%100
49	M52	Y	-1.566	-1.566	0	%100
50	M53	Y	-1.566	-1.566	0	%100
51	M54	Y	-1.566	-1.566	0	%100
52	M55	Y	-1.566	-1.566	0	%100
53	H2	Y	-6.406	-6.406	0	%100
54	MP4	Y	-5.542	-5.542	0	%100
55	MP6	Y	-5.542	-5.542	0	%100
56	HR2	Y	-5.548	-5.548	0	%100
57	M66A	Y	-1.566	-1.566	0	%100
58	M67A	Y	-1.566	-1.566	0	%100
59	M68A	Y	-1.566	-1.566	0	%100
60	M69A	Y	-1.566	-1.566	0	%100
61	MP8	Y	-5.542	-5.542	0	%100
62	M68B	Y	-1.566	-1.566	0	%100
63	M69B	Y	-1.566	-1.566	0	%100
64	MP5	Y	-5.542	-5.542	0	%100
65	M71B	Y	-1.566	-1.566	0	%100
66	M72B	Y	-1.566	-1.566	0	%100
67	M67B	Y	-1.566	-1.566	0	%100
68	MP10	Y	-5.542	-5.542	0	%100

Member Distributed Loads (BLC 29 : Distr. Ice Wind Load Z)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft,F...	Start Location[in, %]	End Location[in, %]
1	S3	SZ	-10.202	-10.202	0	%100
2	GA4	SZ	-13.118	-13.118	0	%100
3	GA3	SZ	-13.118	-13.118	0	%100
4	P3	SZ	-9.82	-9.82	0	%100
5	S2	SZ	-10.202	-10.202	0	%100
6	GA2	SZ	-13.118	-13.118	0	%100
7	GA1	SZ	-13.118	-13.118	0	%100
8	P2	SZ	-9.82	-9.82	0	%100
9	S1	SZ	-10.202	-10.202	0	%100
10	GA6	SZ	-13.118	-13.118	0	%100
11	GA5	SZ	-13.118	-13.118	0	%100

Member Distributed Loads (BLC 29 : Distr. Ice Wind Load Z) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[in, %]	End Location[in, %]
12	P1	SZ	-9.82	-9.82	0	%100
13	H1	SZ	-11.999	-11.999	0	%100
14	MP1	SZ	-13.024	-13.024	0	%100
15	MP3	SZ	-13.024	-13.024	0	%100
16	HR1	SZ	-13.014	-13.014	0	%100
17	CA8	SZ	-9.357	-9.357	0	%100
18	CA9	SZ	-9.357	-9.357	0	%100
19	CA7	SZ	-9.357	-9.357	0	%100
20	M32	SZ	0	0	0	%100
21	M35	SZ	0	0	0	%100
22	M36	SZ	0	0	0	%100
23	M39A	SZ	0	0	0	%100
24	CA3	SZ	-11.453	-11.453	0	%100
25	CA4	SZ	-11.453	-11.453	0	%100
26	CA1	SZ	-11.453	-11.453	0	%100
27	CA2	SZ	-11.453	-11.453	0	%100
28	CA5	SZ	-11.453	-11.453	0	%100
29	CA6	SZ	-11.453	-11.453	0	%100
30	M64	SZ	0	0	0	%100
31	M65	SZ	0	0	0	%100
32	M66	SZ	0	0	0	%100
33	M67	SZ	0	0	0	%100
34	M68	SZ	0	0	0	%100
35	M69	SZ	0	0	0	%100
36	M70	SZ	0	0	0	%100
37	M71	SZ	0	0	0	%100
38	M72	SZ	0	0	0	%100
39	M73	SZ	0	0	0	%100
40	M74	SZ	0	0	0	%100
41	M75	SZ	-14.082	-14.082	0	%100
42	MP2	SZ	-13.024	-13.024	0	%100
43	M43	SZ	0	0	0	%100
44	M44	SZ	0	0	0	%100
45	H3	SZ	-11.999	-11.999	0	%100
46	MP7	SZ	-13.024	-13.024	0	%100
47	MP9	SZ	-13.024	-13.024	0	%100
48	HR3	SZ	-13.014	-13.014	0	%100
49	M52	SZ	0	0	0	%100
50	M53	SZ	0	0	0	%100
51	M54	SZ	0	0	0	%100
52	M55	SZ	0	0	0	%100
53	H2	SZ	-11.999	-11.999	0	%100
54	MP4	SZ	-13.024	-13.024	0	%100
55	MP6	SZ	-13.024	-13.024	0	%100
56	HR2	SZ	-13.014	-13.014	0	%100
57	M66A	SZ	0	0	0	%100
58	M67A	SZ	0	0	0	%100
59	M68A	SZ	0	0	0	%100
60	M69A	SZ	0	0	0	%100
61	MP8	SZ	-13.024	-13.024	0	%100
62	M68B	SZ	0	0	0	%100
63	M69B	SZ	0	0	0	%100
64	MP5	SZ	-13.024	-13.024	0	%100
65	M71B	SZ	0	0	0	%100
66	M72B	SZ	0	0	0	%100
67	M67B	SZ	0	0	0	%100
68	MP10	SZ	-13.024	-13.024	0	%100

Member Distributed Loads (BLC 30 : Distr. Ice Wind Load X)

Member Label	Direction	Start Magnitude[lb/ft....	End Magnitude[lb/ft.F...	Start Location[in, %]	End Location[in, %]
1	S3	-10.202	-10.202	0	%100
2	GA4	-13.118	-13.118	0	%100
3	GA3	-13.118	-13.118	0	%100
4	P3	-9.82	-9.82	0	%100
5	S2	-10.202	-10.202	0	%100
6	GA2	-13.118	-13.118	0	%100
7	GA1	-13.118	-13.118	0	%100
8	P2	-9.82	-9.82	0	%100
9	S1	-10.202	-10.202	0	%100
10	GA6	-13.118	-13.118	0	%100
11	GA5	-13.118	-13.118	0	%100
12	P1	-9.82	-9.82	0	%100
13	H1	-11.999	-11.999	0	%100
14	MP1	-13.024	-13.024	0	%100
15	MP3	-13.024	-13.024	0	%100
16	HR1	-13.014	-13.014	0	%100
17	CA8	-9.357	-9.357	0	%100
18	CA9	-9.357	-9.357	0	%100
19	CA7	-9.357	-9.357	0	%100
20	M32	0	0	0	%100
21	M35	0	0	0	%100
22	M36	0	0	0	%100
23	M39A	0	0	0	%100
24	CA3	-11.453	-11.453	0	%100
25	CA4	-11.453	-11.453	0	%100
26	CA1	-11.453	-11.453	0	%100
27	CA2	-11.453	-11.453	0	%100
28	CA5	-11.453	-11.453	0	%100
29	CA6	-11.453	-11.453	0	%100
30	M64	0	0	0	%100
31	M65	0	0	0	%100
32	M66	0	0	0	%100
33	M67	0	0	0	%100
34	M68	0	0	0	%100
35	M69	0	0	0	%100
36	M70	0	0	0	%100
37	M71	0	0	0	%100
38	M72	0	0	0	%100
39	M73	0	0	0	%100
40	M74	0	0	0	%100
41	M75	-14.082	-14.082	0	%100
42	MP2	-13.024	-13.024	0	%100
43	M43	0	0	0	%100
44	M44	0	0	0	%100
45	H3	-11.999	-11.999	0	%100
46	MP7	-13.024	-13.024	0	%100
47	MP9	-13.024	-13.024	0	%100
48	HR3	-13.014	-13.014	0	%100
49	M52	0	0	0	%100
50	M53	0	0	0	%100
51	M54	0	0	0	%100
52	M55	0	0	0	%100
53	H2	-11.999	-11.999	0	%100
54	MP4	-13.024	-13.024	0	%100
55	MP6	-13.024	-13.024	0	%100
56	HR2	-13.014	-13.014	0	%100
57	M66A	0	0	0	%100

Member Distributed Loads (BLC 30 : Distr. Ice Wind Load X) (Continued)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[in.%]	End Location[in.%]
58	M67A	SX	0	0	0	%100
59	M68A	SX	0	0	0	%100
60	M69A	SX	0	0	0	%100
61	MP8	SX	-13.024	-13.024	0	%100
62	M68B	SX	0	0	0	%100
63	M69B	SX	0	0	0	%100
64	MP5	SX	-13.024	-13.024	0	%100
65	M71B	SX	0	0	0	%100
66	M72B	SX	0	0	0	%100
67	M67B	SX	0	0	0	%100
68	MP10	SX	-13.024	-13.024	0	%100

Member Distributed Loads (BLC 44 : BLC 1 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[in.%]	End Location[in.%]
1	S2	Y	-3.185	-3.185	16.404	40
2	GA2	Y	-1.605	-1.605	3.828	27.295
3	GA1	Y	-1.605	-1.605	3.828	27.295
4	S3	Y	-3.185	-3.185	16.404	40
5	GA4	Y	-1.605	-1.605	3.828	27.295
6	GA3	Y	-1.605	-1.605	3.828	27.295
7	S1	Y	-3.185	-3.185	16.404	40
8	GA6	Y	-1.605	-1.605	3.828	27.295
9	GA5	Y	-1.605	-1.605	3.828	27.295

Member Distributed Loads (BLC 45 : BLC 16 Transient Area Loads)

	Member Label	Direction	Start Magnitude[lb/ft....]	End Magnitude[lb/ft.F...]	Start Location[in.%]	End Location[in.%]
1	S2	Y	-19.294	-19.294	16.404	40
2	GA2	Y	-9.723	-9.723	3.828	27.295
3	GA1	Y	-9.723	-9.723	3.828	27.295
4	S3	Y	-19.294	-19.294	16.404	40
5	GA4	Y	-9.723	-9.723	3.828	27.295
6	GA3	Y	-9.723	-9.723	3.828	27.295
7	S1	Y	-19.294	-19.294	16.404	40
8	GA6	Y	-9.723	-9.723	3.828	27.295
9	GA5	Y	-9.723	-9.723	3.828	27.295

Member Area Loads (BLC 1 : Self Weight)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
1	P22	P21	P20	P23	Y	Two Way	-1.75
2	P10	P11	P12	P9	Y	Two Way	-1.75
3	P31	P34	P33	P32	Y	Two Way	-1.75

Member Area Loads (BLC 16 : Ice Weight)

	Joint A	Joint B	Joint C	Joint D	Direction	Distribution	Magnitude[psf]
1	P22	P21	P20	P23	Y	Two Way	-10.6
2	P10	P11	P12	P9	Y	Two Way	-10.6
3	P31	P34	P33	P32	Y	Two Way	-10.6

Envelope AISC 15th(360-16): LRFD Steel Code Checks

	Memb...	Shape	Code Check	Loc[in]	LC	Shear C...Loc[in]	Dir	LC	phi*Pnc...	phi*Pnt...	phi*Mn y-y	phi*Mn z-z	Cb	Eqn
1	P3	PL6.5x0.375	.249	21	2	.118 36.312	y	5	3658.14	78975	616.993	8027.274	1.4...	H1-...
2	P2	PL6.5x0.375	.245	21	6	.105 36.312	y	10	3658.14	78975	616.993	7996.199	1.4...	H1-...

Envelope AISC 15th(360-16): LRFD Steel Code Checks (Continued)

Memb...	Shape	Code Check	Loc[in]	LC	Shear C...	Loc[in]	Dir	LC	phi*Pnc...	phi*Pnt...	phi*Mn y-y	phi*Mn z-z	Cb	Eqn
3	CA4	C3.38x2.06x0...	.231	33	2	.033	33	y	115	47760....	56700	2202.821	5751.945	1.6...H1-...
4	CA5	C3.38x2.06x0...	.229	0	10	.033	28.187	y	28	47760....	56700	2202.821	5751.945	1.6...H1-...
5	P1	PL6.5x0.375	.227	21	10	.116	36.312	y	2	3658.14	78975	616.993	8023.812	1.4...H1-...
6	CA1	C3.38x2.06x0...	.226	0	6	.034	28.188	y	36	47760....	56700	2202.821	5751.945	1.6...H1-...
7	CA3	C3.38x2.06x0...	.225	0	2	.034	28.188	y	32	47760....	56700	2202.821	5751.945	1.6...H1-...
8	CA2	C3.38x2.06x0...	.219	33	6	.033	33	y	143	47760....	56700	2202.821	5751.945	1.63H1-...
9	CA6	C3.38x2.06x0...	.215	33	10	.032	33	y	87	47760....	56700	2202.821	5751.945	1.6...H1-...
10	S2	HSS4X4X6	.204	0	7	.111	0	y	142	188250...	197892	22045.5	22045.5	1.8...H1-...
11	S3	HSS4X4X6	.197	0	13	.111	0	y	114	188250...	197892	22045.5	22045.5	1.8...H1-...
12	M75	PL 2.375x0.5	.194	1.5	6	.185	0	y	173	38256....	38475	400.783	1903.711	1.5...H1-...
13	CA8	L6.6x4.46x0.25	.193	41.562	22	.028	42	z	4	51170....	87561	2464.809	7125.374	1.1...H2-1
14	HR2	2.88x0.120	.192	90	3	.096	92		4	22491....	43076....	3155.674	3155.674	1.6...H1-...
15	CA7	L6.6x4.46x0.25	.190	41.562	3	.026	42	z	8	51170....	87561	2464.809	7125.374	1.1...H2-1
16	HR3	2.88x0.120	.188	6	2	.089	92		6	22491....	43076....	3155.674	3155.674	1.7...H1-...
17	HR1	2.88x0.120	.185	6	4	.085	6		4	22491....	43076....	3155.674	3155.674	1.9...H1-...
18	S1	HSS4X4X6	.181	0	9	.107	0	y	86	188250...	197892	22045.5	22045.5	1.8...H1-...
19	CA9	L6.6x4.46x0.25	.174	41.562	18	.025	42	z	12	51170....	87561	2464.809	7125.374	1.1...H2-1
20	MP2	PIPE 2.5	.161	70	5	.057	70		5	33487....	66654	4726.5	4726.5	4.4...H1-...
21	MP5	PIPE 2.5	.156	70	7	.048	70		7	33487....	66654	4726.5	4726.5	4.4...H1-...
22	GA4	L2x2x4	.148	0	2	.010	27.295	y	9	29527....	42480	959.63	2190.068	2.1...H2-1
23	MP8	PIPE 2.5	.139	70	9	.060	70		3	33487....	66654	4726.5	4726.5	4.0...H1-...
24	GA5	L2x2x4	.139	0	9	.015	27.295	y	38	29527....	42480	959.63	2190.068	2.1...H2-1
25	GA2	L2x2x4	.135	0	12	.011	0	y	12	29527....	42480	959.63	2190.068	2.3...H2-1
26	GA1	L2x2x4	.127	0	6	.015	27.295	y	34	29527....	42480	959.63	2190.068	2.2...H2-1
27	MP9	PIPE 2.5	.126	70	2	.057	70		7	33487....	66654	4726.5	4726.5	3.3...H1-...
28	GA3	L2x2x4	.125	0	7	.016	27.295	y	30	29527....	42480	959.63	2190.068	2.1...H2-1
29	GA6	L2x2x4	.125	0	4	.011	0	y	4	29527....	42480	959.63	2190.068	2.2...H2-1
30	MP6	PIPE 2.5	.115	70	7	.062	70		6	33487....	66654	4726.5	4726.5	4.66H1-...
31	MP1	PIPE 2.5	.111	70	11	.068	26		8	33487....	66654	4726.5	4726.5	2.6...H1-...
32	MP4	PIPE 2.5	.109	70	7	.063	26		4	33487....	66654	4726.5	4726.5	1.6...H1-...
33	MP3	PIPE 2.5	.109	70	5	.062	70		3	33487....	66654	4726.5	4726.5	4.4...H1-...
34	MP7	PIPE 2.5	.107	70	9	.056	26		6	33487....	66654	4726.5	4726.5	3.3...H1-...
35	H3	Pipe3.5x0.165	.096	31	2	.063	90		2	45873....	71580.6	6337.65	6337.65	1.9...H1-...
36	H1	Pipe3.5x0.165	.092	31	10	.054	48		4	45873....	71580.6	6337.65	6337.65	2.1...H1-...
37	H2	Pipe3.5x0.165	.091	31	6	.050	90		143	45873....	71580.6	6337.65	6337.65	1.7...H1-...
38	MP10	PIPE 2.5	.004	24	6	.001	24		6	56116....	66654	4726.5	4726.5	1.5...H1-...

Bolt Calculation Tool, V1.5.1

PROJECT DATA	
Site Name:	BOHVN00005A
Site Number:	BOHVN00005A
Connection Description:	Platform to Monopole

MAXIMUM BOLT LOADS		
Bolt Tension:	5498.39	lbs
Bolt Shear:	3886.11	lbs


WORST CASE BOLT LOADS ¹		
Bolt Tension:	0.00	lbs
Bolt Shear:	3886.11	lbs

BOLT PROPERTIES		
Bolt Type:	Bolt	-
Bolt Diameter:	0.625	in
Bolt Grade:	A325	-
# of Bolts:	4	-
Threads Excluded?	No	-

¹ Worst case bolt loads correspond to Load combination #1 on member S1 in RISA-3D, which causes the maximum demand on the bolts.

Member Information
I nodes of S3, S2, S1

BOLT CHECK		
Tensile Strength	20340.15	
Shear Strength	13805.83	
Max Tensile Usage	27.0%	
Max Shear Usage	28.1%	
Interaction Check (Worst Case)	0.08	≤1.05
Result	Pass	



POWER DENSITY STUDY

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS

Dish Wireless Existing Facility

Site ID: BOHVN00005A

BOHVN00005A
20 Antolini Road
New Hartford, Connecticut 06057

October 5, 2021

EBI Project Number: 6221003997

Site Compliance Summary	
Compliance Status:	COMPLIANT
Site total MPE% of FCC general population allowable limit:	25.47%

October 5, 2021

Dish Wireless

Emissions Analysis for Site: BOHVN00005A - BOHVN00005A

EBI Consulting was directed to analyze the proposed Dish Wireless facility located at **20 Antolini Road** in **New Hartford, Connecticut** for the purpose of determining whether the emissions from the Proposed Dish Wireless Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits; therefore, it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limits for the 600 MHz and 700 MHz frequency bands are approximately $400 \mu\text{W}/\text{cm}^2$ and $467 \mu\text{W}/\text{cm}^2$, respectively. The general population exposure limit for the 1900 MHz (PCS), 2100 MHz (AWS) and 11 GHz frequency bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure.

Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed Dish Wireless Wireless antenna facility located at 20 Antolini Road in New Hartford, Connecticut using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since Dish Wireless is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was focused at the base of the tower. For this report, the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 4 n71 channels (600 MHz Band) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 4 n70 channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 3) 4 n66 channels (AWS Band - 2190 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 40 Watts per Channel.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations, the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used in this direction. This value is a very conservative

estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector A, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector B, the JMA MX08FRO665-21 for the 600 MHz / 1900 MHz / 2190 MHz channel(s) in Sector C. This is based on feedback from the carrier with regard to anticipated antenna selection. All Antenna gain values and associated transmit power levels are shown in the Site Inventory and Power Data table below. The maximum gain of the antenna per the antenna manufacturer's supplied specifications, minus 20 dB for directional panel antennas and 20 dB for highly focused parabolic microwave dishes, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline of the proposed antennas is 114 feet above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 9) All calculations were done with respect to uncontrolled / general population threshold limits.

Dish Wireless Site Inventory and Power Data

Sector:	A	Sector:	B	Sector:	C
Antenna #:	1	Antenna #:	1	Antenna #:	1
Make / Model:	JMA MX08FRO665-21	Make / Model:	JMA MX08FRO665-21	Make / Model:	JMA MX08FRO665-21
Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz	Frequency Bands:	600 MHz / 1900 MHz / 2190 MHz
Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd	Gain:	17.45 dBd / 22.65 dBd / 22.65 dBd
Height (AGL):	114 feet	Height (AGL):	114 feet	Height (AGL):	114 feet
Channel Count:	12	Channel Count:	12	Channel Count:	12
Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts	Total TX Power (W):	440 Watts
ERP (W):	5,236.31	ERP (W):	5,236.31	ERP (W):	5,236.31
Antenna AI MPE %:	2.03%	Antenna BI MPE %:	2.03%	Antenna CI MPE %:	2.03%

Site Composite MPE %	
Carrier	MPE %
Dish Wireless (Max at Sector A):	2.03%
AT&T	16.11%
Metro PCS	0.57%
T-Mobile	1.22%
Nextel	0.74%
South End FD	0.07%
Sprint	2.47%
Verizon	2.26%
Site Total MPE % :	25.47%

Dish Wireless MPE % Per Sector	
Dish Wireless Sector A Total:	2.03%
Dish Wireless Sector B Total:	2.03%
Dish Wireless Sector C Total:	2.03%
Site Total MPE % :	25.47%

Dish Wireless Maximum MPE Power Values (Sector A)							
Dish Wireless Frequency Band / Technology (Sector A)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density ($\mu\text{W}/\text{cm}^2$)	Frequency (MHz)	Allowable MPE ($\mu\text{W}/\text{cm}^2$)	Calculated % MPE
Dish Wireless 600 MHz n71	4	223.68	114.0	2.76	600 MHz n71	400	0.69%
Dish Wireless 1900 MHz n70	4	542.70	114.0	6.69	1900 MHz n70	1000	0.67%
Dish Wireless 2190 MHz n66	4	542.70	114.0	6.69	2190 MHz n66	1000	0.67%
						Total:	2.03%

• NOTE: Totals may vary by approximately 0.01% due to summation of remainders in calculations.

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish Wireless facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Wireless Sector	Power Density Value (%)
Sector A:	2.03%
Sector B:	2.03%
Sector C:	2.03%
Dish Wireless Maximum MPE % (Sector A):	2.03%
Site Total:	25.47%
Site Compliance Status:	COMPLIANT

The anticipated composite MPE value for this site assuming all carriers present is **25.47%** of the allowable FCC established general population limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



November 09, 2021

Dear Customer,

The following is the proof-of-delivery for tracking number: 775110051311

Delivery Information:

Status:	Delivered	Delivered To:	Residence
Signed for by:	Signature not required	Delivery Location:	95 E COTTON HILL ROAD
Service type:	FedEx 2Day		
Special Handling:	Deliver Weekday; Residential Delivery		NEW HARTFORD, CT, 06057
		Delivery date:	Nov 9, 2021 11:50

Shipping Information:

Tracking number:	775110051311	Ship Date:	Nov 5, 2021
		Weight:	1.0 LB/0.45 KG

Recipient:
South End Fire District,
20 Antolini Road
NEW HARTFORD, CT, US, 06057

Shipper:
Corey Milan, NB+C
100 Apollo Dr.
Suite 303
CHELMSFORD, MA, US, 01824

Reference 100814

Thank you for choosing FedEx

Dear Customer,

The following is the proof-of-delivery for tracking number: 775110024947

Delivery Information:

Status:	Delivered	Delivered To:	Receptionist/Front Desk
Signed for by:	C.HAYWARD	Delivery Location:	530 MAIN ST
Service type:	FedEx 2Day		
Special Handling:	Deliver Weekday		NEW HARTFORD, CT, 06057
		Delivery date:	Nov 9, 2021 15:00

Shipping Information:

Tracking number:	775110024947	Ship Date:	Nov 5, 2021
		Weight:	1.0 LB/0.45 KG

Recipient:
Jerry Monroe,
530 Main Street
PO Box 316
NEW HARTFORD, CT, US, 06057

Shipper:
Corey Milan, NB+C
100 Apollo Dr.
Suite 303
CHELMSFORD, MA, US, 01824

Reference 100814

Dear Customer,

The following is the proof-of-delivery for tracking number: 775109996248

Delivery Information:

Status:	Delivered	Delivered To:	Receptionist/Front Desk
Signed for by:	C.HAYWARD	Delivery Location:	530 MAIN ST
Service type:	FedEx 2Day		
Special Handling:	Deliver Weekday		NEW HARTFORD, CT, 06057
		Delivery date:	Nov 9, 2021 15:00

Shipping Information:

Tracking number:	775109996248	Ship Date:	Nov 5, 2021
		Weight:	1.0 LB/0.45 KG

Recipient:
Daniel V. Jerram,
530 Main Street
PO Box 316
NEW HARTFORD, CT, US, 06057

Shipper:
Corey Milan, NB+C
100 Apollo Dr.
Suite 303
CHELMSFORD, MA, US, 01824

Reference 100814