



Crown Castle
3530 Torington Way, Suite 300
Charlotte, NC 28277

June 26, 2014

Melanie A. Bachman
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

RE: Sprint PCS-Exempt Modification - Crown Site BU: 876332
Sprint PCS Site ID: CT03XC084
Located at: 36 Prospect Street, Newington, CT 06109

Dear Ms. Bachman:

This letter and exhibits are submitted on behalf of Sprint PCS (Sprint). Sprint is making modifications to certain existing sites in its Connecticut system in order to implement their 2.5GHz LTE technology. Please accept this letter and exhibits as notification, pursuant to § 16-50j-73 of the Regulations of Connecticut State Agencies (“R.C.S.A.”), of construction that constitutes an exempt modification pursuant to R.C.S.A. § 16-50j-72(b)(2). In compliance with R.C.S.A. § 16-50j-73, a copy of this letter is being sent to Mr. John Salomone, Manager for Town of Newington.

Sprint plans to modify the existing wireless communications facility owned by Crown Castle and located at **36 Prospect Street, Newington, CT 06109**. Attached are a compound plan and elevation depicting the planned changes (Exhibit-1), and documentation of the structural sufficiency of the structure to accommodate the revised antenna configuration (Exhibit-2). Also included is a power density table report reflecting the modification to Sprint’s operations at the site (Exhibit-3).

The changes to the facility do not constitute a modification as defined in Connecticut General Statutes (“C.G.S.”) § 16-50i(d) because the general physical characteristics of the facility will not be significantly changed. Rather, the planned changes to the facility fall squarely within those activities explicitly provided for in the R.C.S.A. § 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing tower. Sprint’s additional antennas will be located at the same elevation on the existing tower.
2. There will be no proposed modifications to the ground and no extension of boundaries.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more.

Melanie A. Bachman

June 26, 2014

Page 2

4. A Structural Modification Report confirming that the tower and foundation can support Sprint's proposed modifications is included as Exhibit-2.
5. The operation of the additional antennas will not increase radio frequency (RF) emissions at the facility to a level at or above the Federal Communications Commission (FCC) adopted safety standard. A cumulative General Power Density table report for Sprint's modified facility is included as Exhibit-3.

For the foregoing reasons, Sprint respectfully submits the proposed modifications to the above-reference telecommunications facility constitutes an exempt modification under R.C.S.A. § 16-50j-72(b)(2). Please send approval/rejection letter to Attn: Donna Neal.

Sincerely,



Jeff Barbadora
Real Estate Specialist


Enclosures

Tab 1: Exhibit-1: Compound plan and elevation depicting the planned changes

Tab 2: Exhibit-2: Structural Modification Report

Tab 3: Exhibit-3: General Power Density Table Report (RF Emissions Analysis Report)

cc: Mr. John Salomone, Manager
Town of Newington
131 Cedar Street
Newington, CT 06111-2644




PROJECT: 2.5 EQUIPMENT DEPLOYMENT
 SITE NAME: 36 PROSPECT ST
 SITE CASCADE: CT03XC084
 SITE NUMBER: 876332
 SITE ADDRESS: 36 PROSPECT ST
 NEWINGTON, CT 06109
 SITE TYPE: MONOPOLE TOWER
 MARKET: NORTHERN CONNECTICUT

PLANS PREPARED FOR:
Sprint
 6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 353-000

MLA PARTNER:
CROWN CASTLE



DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
	ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:
36 PROSPECT ST

SITE CASCADE:
CT03XC084

SITE ADDRESS:
**36 PROSPECT ST
 NEWINGTON, CT 06109**

SHEET DESCRIPTION:
TITLE SHEET & PROJECT DATA

SHEET NUMBER:
T-1

SITE INFORMATION	AREA MAP	PROJECT DESCRIPTION	DRAWING INDEX																																										
<p>TOWER OWNER: CROWN ATLANTIC COMPANY LLC 2000 CORPORATE DRIVE CANONSBURG, PA 15317 (704) 405-6555</p> <p>LATITUDE (NAD83): 41° 41' 23.66" N 41.689906°</p> <p>LONGITUDE (NAD83): 72° 42' 18.85" W -72.705236°</p> <p>COUNTY: HARTFORD</p> <p>ZONING JURISDICTION: CONNECTICUT SITING COUNCIL</p> <p>ZONING DISTRICT: RESIDENTIAL</p> <p>POWER COMPANY: CONNECTICUT LIGHT & POWER (860) 947-2000</p> <p>SPRINT PM: PETER GIARD (508) 801-0074 peter.giard@sprint.com</p> <p>SPRINT CM: PETER CULBERT (603) 203-6446 (603) 989-0686 peter.culbert@sprint.com</p> <p>CROWN CASTLE CM: JASON D'AMICO (860) 209-0104 JASON.D'AMICO@CROWNCastle.COM</p>		<p>SPRINT PROPOSES TO MODIFY AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY.</p> <ul style="list-style-type: none"> INSTALL 2.5 EQUIPMENT IN EXISTING N.V. MMBS CABINET INSTALL (3) PANEL ANTENNAS INSTALL (3) RRU'S TO TOWER INSTALL (27) JUMPER CABLES INSTALL (1) FIBER CABLE INSTALL (4) BATTERIES IN EXISTING BBU CABINET <p>THESE PLANS HAVE BEEN DEVELOPED FOR THE MODIFICATION OF AN EXISTING UNMANNED TELECOMMUNICATIONS FACILITY OWNED OR LEASED BY SPRINT IN ACCORDANCE WITH THE SCOPE OF WORK PROVIDED BY SPRINT. INFINIGY HAS INCORPORATED THIS SCOPE OF WORK IN THE PLANS. THESE PLANS ARE NOT FOR CONSTRUCTION UNLESS ACCOMPANIED BY A PASSING STRUCTURAL STABILITY ANALYSIS PREPARED BY A LICENSED STRUCTURAL ENGINEER. STRUCTURAL ANALYSIS MUST INCLUDE BOTH TOWER AND MOUNT.</p>	<table border="1"> <thead> <tr> <th>SHEET NO:</th> <th>SHEET TITLE</th> <th>REV</th> </tr> </thead> <tbody> <tr> <td>T-1</td> <td>TITLE SHEET & PROJECT DATA</td> <td>0</td> </tr> <tr> <td>SP-1</td> <td>SPRINT SPECIFICATIONS</td> <td>0</td> </tr> <tr> <td>SP-2</td> <td>SPRINT SPECIFICATIONS</td> <td>0</td> </tr> <tr> <td>SP-3</td> <td>SPRINT SPECIFICATIONS</td> <td>0</td> </tr> <tr> <td>A-1</td> <td>SITE PLAN</td> <td>0</td> </tr> <tr> <td>A-2</td> <td>TOWER ELEVATION & CABLE PLAN</td> <td>0</td> </tr> <tr> <td>A-3</td> <td>ANTENNA LAYOUT & MOUNTING DETAILS</td> <td>0</td> </tr> <tr> <td>A-4</td> <td>COLOR CODING & NOTES</td> <td>0</td> </tr> <tr> <td>A-5</td> <td>EQUIPMENT & MOUNTING DETAILS</td> <td>0</td> </tr> <tr> <td>A-6</td> <td>CIVIL DETAILS</td> <td>0</td> </tr> <tr> <td>A-7</td> <td>PLUMBING DIAGRAM</td> <td>0</td> </tr> <tr> <td>E-1</td> <td>ELECTRICAL & GROUNDING PLAN</td> <td>0</td> </tr> <tr> <td>E-2</td> <td>ELECTRICAL & GROUNDING DETAILS</td> <td>0</td> </tr> </tbody> </table>	SHEET NO:	SHEET TITLE	REV	T-1	TITLE SHEET & PROJECT DATA	0	SP-1	SPRINT SPECIFICATIONS	0	SP-2	SPRINT SPECIFICATIONS	0	SP-3	SPRINT SPECIFICATIONS	0	A-1	SITE PLAN	0	A-2	TOWER ELEVATION & CABLE PLAN	0	A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0	A-4	COLOR CODING & NOTES	0	A-5	EQUIPMENT & MOUNTING DETAILS	0	A-6	CIVIL DETAILS	0	A-7	PLUMBING DIAGRAM	0	E-1	ELECTRICAL & GROUNDING PLAN	0	E-2	ELECTRICAL & GROUNDING DETAILS	0
SHEET NO:	SHEET TITLE	REV																																											
T-1	TITLE SHEET & PROJECT DATA	0																																											
SP-1	SPRINT SPECIFICATIONS	0																																											
SP-2	SPRINT SPECIFICATIONS	0																																											
SP-3	SPRINT SPECIFICATIONS	0																																											
A-1	SITE PLAN	0																																											
A-2	TOWER ELEVATION & CABLE PLAN	0																																											
A-3	ANTENNA LAYOUT & MOUNTING DETAILS	0																																											
A-4	COLOR CODING & NOTES	0																																											
A-5	EQUIPMENT & MOUNTING DETAILS	0																																											
A-6	CIVIL DETAILS	0																																											
A-7	PLUMBING DIAGRAM	0																																											
E-1	ELECTRICAL & GROUNDING PLAN	0																																											
E-2	ELECTRICAL & GROUNDING DETAILS	0																																											
	<p>LOCATION MAP</p>	<p>APPLICABLE CODES</p> <p>ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALL IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES.</p> <ol style="list-style-type: none"> INTERNATIONAL BUILDING CODE (2012 IBC) TIA-EIA-222-G OR LATEST EDITION NFPA 780 - LIGHTNING PROTECTION CODE 2011 NATIONAL ELECTRIC CODE OR LATEST EDITION ANY OTHER NATIONAL OR LOCAL APPLICABLE CODES, MOST RECENT EDITIONS CT BUILDING CODE LOCAL BUILDING CODE CITY/COUNTY ORDINANCES 																																											



THESE OUTLINE SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT STANDARD CONSTRUCTION SPECIFICATIONS, INCLUDING CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.

SECTION 01 100 – SCOPE OF WORK

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE SPRINT CONSTRUCTION STANDARDS FOR WIRELESS SITES, CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 PRECEDENCE: SHOULD CONFLICTS OCCUR BETWEEN THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES INCLUDING THE STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE CONSTRUCTION DRAWINGS, INFORMATION ON THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE. NOTIFY SPRINT CONSTRUCTION MANAGER IF THIS OCCURS.
- 1.4 NATIONALLY RECOGNIZED CODES AND STANDARDS:
 - A. THE WORK SHALL COMPLY WITH APPLICABLE NATIONAL AND LOCAL CODES AND STANDARDS, LATEST EDITION, AND PORTIONS THEREOF, INCLUDED BUT NOT LIMITED TO THE FOLLOWING:
 - 1. GR-63-CORE NEBS REQUIREMENTS: PHYSICAL PROTECTION
 - 5. GR-78-CORE GENERIC REQUIREMENTS FOR THE PHYSICAL DESIGN AND MANUFACTURE OF TELECOMMUNICATIONS EQUIPMENT.
 - 3. GR-1089 CORE, ELECTROMAGNETIC COMPATIBILITY AND ELECTRICAL SAFETY -GENERIC CRITERIA FOR NETWORK TELECOMMUNICATIONS EQUIPMENT.
 - 4. NATIONAL FIRE PROTECTION ASSOCIATION CODES AND STANDARDS (NFPA) INCLUDING NFPA 70 (NATIONAL ELECTRICAL CODE – "NEC") AND NFPA 101 (LIFE SAFETY CODE).
 - 5. AMERICAN SOCIETY FOR TESTING OF MATERIALS (ASTM)
 - 6. INSTITUTE OF ELECTRONIC AND ELECTRICAL ENGINEERS (IEEE)
 - 7. AMERICAN CONCRETE INSTITUTE (ACI)
 - 8. AMERICAN WIRE PRODUCERS ASSOCIATION (AWPA)
 - 9. CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
 - 10. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
 - 11. PORTLAND CEMENT ASSOCIATION (PCA)
 - 12. NATIONAL CONCRETE MASONRY ASSOCIATION (NCMA)
 - 13. BRICK INDUSTRY ASSOCIATION (BIA)
 - 14. AMERICAN WELDING SOCIETY (AWS)
 - 15. NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
 - 16. SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
 - 17. DOOR AND HARDWARE INSTITUTE (DHI)
 - 18. OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA)
 - 19. APPLICABLE BUILDING CODES INCLUDING UNIFORM BUILDING CODE, SOUTHERN BUILDING CODE, BOCA, AND THE INTERNATIONAL BUILDING CODE.

1.5 DEFINITIONS:

- A. WORK: THE SUM OF TASKS AND RESPONSIBILITIES IDENTIFIED IN THE CONTRACT DOCUMENTS.
- B. COMPANY: SPRINT CORPORATION
- C. ENGINEER: SYNONYMOUS WITH ARCHITECT & ENGINEER AND "A&E". THE DESIGN PROFESSIONAL HAVING PROFESSIONAL RESPONSIBILITY FOR DESIGN OF THE PROJECT.
- D. CONTRACTOR: CONSTRUCTION CONTRACTOR; CONSTRUCTION VENDOR; INDIVIDUAL OR ENTITY WHO AFTER EXECUTION OF A CONTRACT IS BOUND TO ACCOMPLISH THE WORK.
- E. THIRD PARTY VENDOR OR AGENCY: A VENDOR OR AGENCY ENGAGED SEPARATELY BY THE COMPANY, A&E, OR CONTRACTOR TO PROVIDE MATERIALS OR TO ACCOMPLISH SPECIFIC TASKS RELATED TO BUT NOT INCLUDED IN THE WORK.
- F. OFCI: OWNER FURNISHED, CONTRACTOR INSTALLED EQUIPMENT.
- G. CONSTRUCTION MANAGER – ALL PROJECTS RELATED COMMUNICATION TO FLOW THROUGH SPRINT REPRESENTATIVE IN CHARGE OF PROJECT...

- 1.6 SITE FAMILIARITY: CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIMSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE SPRINT CONSTRUCTION MANAGER PRIOR TO THE COMMENCEMENT OF WORK. NO COMPENSATION WILL BE AWARDED BASED ON CLAIM OF LACK OF KNOWLEDGE OR FIELD CONDITIONS.
- 1.7 POINT OF CONTACT: COMMUNICATION BETWEEN SPRINT AND THE CONTRACTOR SHALL FLOW THROUGH THE SINGLE SPRINT CONSTRUCTION MANAGER APPOINTED TO MANAGE THE PROJECT FOR SPRINT.
- 1.8 ON-SITE SUPERVISION: THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL EMPLOY A COMPETENT SUPERINTENDENT WHO SHALL BE IN ATTENDANCE AT THE SITE AT ALL TIMES DURING PERFORMANCE OF THE WORK.
- 1.9 DRAWINGS, SPECIFICATIONS AND DETAILS REQUIRED AT JOBSITE: THE CONSTRUCTION CONTRACTOR SHALL MAINTAIN A FULL SET OF THE CONSTRUCTION DRAWINGS, STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES AND THE STANDARD CONSTRUCTION SPECIFICATIONS FOR WIRELESS SITES AT THE JOBSITE FROM MOBILIZATION THROUGH CONSTRUCTION COMPLETION.
 - A. THE JOBSITE DRAWINGS, SPECIFICATIONS AND DETAILS SHALL BE CLEARLY MARKED DAILY IN RED PENCIL WITH ANY CHANGES IN CONSTRUCTION OVER WHAT IS DEPICTED IN THE DOCUMENTS. AT CONSTRUCTION COMPLETION, THIS JOBSITE MARKUP SET SHALL BE DELIVERED TO THE COMPANY OR COMPANY'S DESIGNATED REPRESENTATIVE TO BE FORWARDED TO THE COMPANY'S A&E VENDOR FOR PRODUCTION OF "AS-BUILT" DRAWINGS.
 - B. DETAILS ARE INTENDED TO SHOW DESIGN INTENT. MODIFICATIONS MAY BE REQUIRED TO SUIT JOB DIMENSIONS OR CONDITIONS, AND SUCH MODIFICATIONS SHALL BE INCLUDED AS PART OF THE WORK. CONTRACTOR SHALL NOTIFY SPRINT CONSTRUCTION MANAGER OF ANY VARIATIONS PRIOR TO PROCEEDING WITH THE WORK.
 - C. DIMENSIONS SHOWN ARE TO FINISH SURFACES UNLESS NOTED OTHERWISE. SPACING BETWEEN EQUIPMENT IS THE REQUIRED CLEARANCE. SHOULD THERE BE ANY QUESTIONS REGARDING THE CONTRACT DOCUMENTS, EXISTING CONDITIONS AND/OR DESIGN INTENT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE SPRINT CONSTRUCTION MANAGER PRIOR TO PROCEEDING WITH THE WORK.
- 1.10 USE OF JOB SITE: THE CONTRACTOR SHALL CONFINE ALL CONSTRUCTION AND RELATED OPERATIONS INCLUDING STAGING AND STORAGE OF MATERIALS AND EQUIPMENT, PARKING, TEMPORARY FACILITIES, AND WASTE STORAGE TO THE LEASE PARCEL UNLESS OTHERWISE PERMITTED BY THE CONTRACT DOCUMENTS.
- 1.11 UTILITIES SERVICES: WHERE NECESSARY TO CUT EXISTING PIPES, ELECTRICAL WIRES, CONDUITS, CABLES, ETC., OF UTILITY SERVICES, OR OF FIRE PROTECTION OR COMMUNICATIONS SYSTEMS, THEY SHALL BE CUT AND CAPPED AT SUITABLE PLACES OR WHERE SHOWN. ALL SUCH ACTIONS SHALL BE COORDINATED WITH THE UTILITY COMPANY INVOLVED:
- 1.12 PERMITS / FEES: WHEN REQUIRED THAT A PERMIT OR CONNECTION FEE BE PAID TO A PUBLIC UTILITY PROVIDER FOR NEW SERVICE TO THE CONSTRUCTION PROJECT, PAYMENT OF SUCH FEE SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 1.13 CONTRACTOR SHALL TAKE ALL MEASURES AND PROVIDE ALL MATERIAL NECESSARY FOR PROTECTING EXISTING EQUIPMENT AND PROPERTY.
- 1.14 METHODS OF PROCEDURE (MOPS) FOR CONSTRUCTION: CONTRACTOR SHALL PERFORM WORK AS DESCRIBED IN THE FOLLOWING INSTALLATION AND COMMISSIONING MOPS.

NOTE: IN SHORT-FORM SPECIFICATIONS ON THE DRAWINGS, A/E TO INSERT LIST OF APPLICABLE MOPS INCLUDING EN-2012-001, EN-2013-002, EL-0568, AND TS-0193
- 1.15 USE OF ELECTRONIC PROJECT MANAGEMENT SYSTEMS:

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 TEMPORARY UTILITIES AND FACILITIES: THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TEMPORARY UTILITIES AND FACILITIES NECESSARY EXCEPT AS OTHERWISE INDICATED IN THE CONSTRUCTION DOCUMENTS. TEMPORARY UTILITIES AND FACILITIES INCLUDE POTABLE WATER, HEAT, HVAC, ELECTRICITY, SANITARY FACILITIES, WASTE DISPOSAL FACILITIES, AND TELEPHONE/COMMUNICATION SERVICES. PROVIDE TEMPORARY UTILITIES AND FACILITIES IN ACCORDANCE WITH OSHA AND THE AUTHORITY HAVING JURISDICTION. CONTRACTOR MAY UTILIZE THE COMPANY ELECTRICAL SERVICE IN THE COMPLETION OF THE WORK WHEN IT BECOMES AVAILABLE. USE OF THE LESSORS OR SITE OWNER'S UTILITIES OR FACILITIES IS EXPRESSLY FORBIDDEN EXCEPT AS OTHERWISE ALLOWED IN THE CONTRACT DOCUMENTS.
- 3.2 ACCESS TO WORK: THE CONTRACTOR SHALL PROVIDE ACCESS TO THE JOB SITE FOR AUTHORIZED COMPANY PERSONNEL AND AUTHORIZED REPRESENTATIVES OF THE ARCHITECT/ENGINEER DURING ALL PHASES OF THE WORK.
- 3.3 TESTING: REQUIREMENTS FOR TESTING BY THIS CONTRACTOR SHALL BE AS INDICATED HEREWITH, ON THE CONSTRUCTION DRAWINGS, AND IN THE INDIVIDUAL SECTIONS OF THESE SPECIFICATIONS. SHOULD COMPANY CHOOSE TO ENGAGE ANY THIRD-PARTY TO CONDUCT ADDITIONAL TESTING, THE CONTRACTOR SHALL COOPERATE WITH AND PROVIDE A WORK AREA FOR COMPANY'S TEST AGENCY.
- 3.4 DIMENSIONS: VERIFY DIMENSIONS INDICATED ON DRAWINGS WITH FIELD DIMENSIONS BEFORE FABRICATION OR ORDERING OF MATERIALS. DO NOT SCALE DRAWINGS.

3.5 EXISTING CONDITIONS: NOTIFY THE SPRINT CONSTRUCTION MANAGER OF EXISTING CONDITIONS DIFFERING FROM THOSE INDICATED ON THE DRAWINGS. DO NOT REMOVE OR ALTER STRUCTURAL COMPONENTS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ARCHITECT AND ENGINEER.

SECTION 01 200 – COMPANY FURNISHED MATERIAL AND EQUIPMENT

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 RECEIPT OF MATERIAL AND EQUIPMENT:
 - A. A COMPANY FURNISHED MATERIAL AND EQUIPMENT IS IDENTIFIED ON THE RF DATA SHEET IN THE CONSTRUCTION DOCUMENTS.
 - B. THE CONTRACTOR IS RESPONSIBLE FOR SPRINT PROVIDED MATERIAL AND EQUIPMENT AND UPON RECEIPT SHALL:
 - 1. ACCEPT DELIVERIES AS SHIPPED AND TAKE RECEIPT.
 - 2. VERIFY COMPLETENESS AND CONDITION OF ALL DELIVERIES.
 - 3. TAKE RESPONSIBILITY FOR EQUIPMENT AND PROVIDE INSURANCE PROTECTION AS REQUIRED IN AGREEMENT.
 - 4. RECORD ANY DEFECTS OR DAMAGES AND WITHIN TWENTY-FOUR HOURS AFTER RECEIPT, REPORT TO SPRINT OR ITS DESIGNATED PROJECT REPRESENTATIVE OF SUCH.
 - 5. PROVIDE SECURE AND NECESSARY WEATHER PROTECTED WAREHOUSING.
 - 6. COORDINATE SAFE AND SECURE TRANSPORTATION OF MATERIAL AND EQUIPMENT, DELIVERING AND OFF-LOADING FROM CONTRACTOR'S WAREHOUSE TO SITE.
- 3.2 DELIVERABLES:
 - A. COMPLETE SHIPPING AND RECEIPT DOCUMENTATION IN ACCORDANCE WITH COMPANY PRACTICE.
 - B. IF APPLICABLE, COMPLETE LOST/STOLEN/DAMAGED DOCUMENTATION REPORT AS NECESSARY IN ACCORDANCE WITH COMPANY PRACTICE, AND AS DIRECTED BY COMPANY.
 - C. UPLOAD DOCUMENTATION INTO SPRINT SITE MANAGEMENT SYSTEM (SMS) AND/OR PROVIDE HARD COPY DOCUMENTATION AS REQUESTED.

SECTION 01 300 – CELL SITE CONSTRUCTION CO.

PART 1 – GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.
- 1.3 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

- 1.4 NOTICE TO PROCEED
 - A. NO WORK SHALL COMMENCE PRIOR TO COMPANY'S WRITTEN NOTICE TO PROCEED AND THE ISSUANCE OF THE WORK ORDER.
 - B. UPON RECEIVING NOTICE TO PROCEED, CONTRACTOR SHALL FULLY PERFORM ALL WORK NECESSARY TO PROVIDE SPRINT WITH AN OPERATIONAL WIRELESS FACILITY.

TOWER OWNER NOTIFICATION
 ONCE THE CONTRACTOR HAS RECEIVED AND ACCEPTED THE NOTICE TO PROCEED, CONTRACTOR WILL CONTACT THE CROWN CASTLE CONSTRUCTION MANAGER OF RECORD (NOTED ON THE FIRST PAGE ON THIS CONSTRUCTION DRAWING) A MINIMUM OF 48 HOURS PRIOR TO WORK START. UPON ARRIVAL TO THE JOB SITE, CONTRACTOR CREW IS REQUIRED CALL 1-800-788-7011 TO NOTIFY THE CROWN CASTLE NOC WORK HAS BEGUN.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION

- 3.1 FUNCTIONAL REQUIREMENTS:
 - A. THE ACTIVITIES DESCRIBED IN THIS PARAGRAPH REPRESENT MINIMUM ACTIONS AND PROCESSES REQUIRED TO SUCCESSFULLY COMPLETE THE WORK. THE ACTIVITIES DESCRIBED ARE NOT EXHAUSTIVE, AND CONTRACTOR SHALL TAKE ANY AND ALL ACTIONS AS NECESSARY TO SUCCESSFULLY COMPLETE THE CONSTRUCTION OF A FULLY FUNCTIONING WIRELESS FACILITY AT THE SITE IN ACCORDANCE WITH COMPANY PROCESSES.
 - B. SUBMIT SPECIFIC DOCUMENTATION AS INDICATED HEREIN, AND OBTAIN REQUIRED APPROVALS WHILE THE WORK IS BEING PERFORMED.
 - C. MANAGE AND CONDUCT ALL FIELD CONSTRUCTION SERVICE RELATED ACTIVITIES
 - D. PROVIDE CONSTRUCTION ACTIVITIES TO THE EXTENT REQUIRED BY THE CONTRACT DOCUMENTS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

36 PROSPECT ST
NEWINGTON, CT 06109

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-1

CONTINUE FROM SP-1

1. PERFORM ANY REQUIRED SITE ENVIRONMENTAL MITIGATION.
2. PREPARE GROUND SITES; PROVIDE DE-GRUBBING; AND ROUGH AND FINAL GRADING, AND COMPOUND SURFACE TREATMENTS.
3. MANAGE AND CONDUCT ALL ACTIVITIES FOR INSTALLATION OF UTILITIES INCLUDING ELECTRICAL AND TELCO BACKHAUL.
4. INSTALL UNDERGROUND FACILITIES INCLUDING UNDERGROUND POWER AND COMMUNICATIONS CONDUITS, AND UNDERGROUND GROUNDING SYSTEM.
5. INSTALL ABOVE GROUND GROUNDING SYSTEMS.
6. PROVIDE NEW HVAC INSTALLATIONS AND MODIFICATIONS.
7. INSTALL "H-FRAMES", CABINETS AND SHELTERS AS INDICATED.
8. INSTALL ROADS, ACCESS WAYS, CURBS AND DRAINS AS INDICATED.
9. ACCOMPLISH REQUIRED MODIFICATION OF EXISTING FACILITIES.
10. PROVIDE ANTENNA SUPPORT STRUCTURE FOUNDATIONS.
11. PROVIDE SLABS AND EQUIPMENT PLATFORMS.
12. INSTALL COMPOUND FENCING, SIGHT SHIELDING, LANDSCAPING AND ACCESS BARRIERS.
13. PERFORM INSPECTION AND MATERIAL TESTING AS REQUIRED HEREINAFTER.
14. CONDUCT SITE RESISTANCE TO EARTH TESTING AS REQUIRED HEREINAFTER
15. INSTALL FIXED GENERATOR SETS AND OTHER STANDBY POWER SOLUTIONS.
16. INSTALL TOWERS, ANTENNA SUPPORT STRUCTURES AND PLATFORMS ON EXISTING TOWERS AS REQUIRED.
17. INSTALL CELL SITE RADIOS, MICROWAVE, GPS, COAXIAL MAINLINE, ANTENNAS, CROSS BAND COUPLERS, TOWER TOP AMPLIFIERS, LOW NOISE AMPLIFIERS AND RELATED EQUIPMENT.
18. PERFORM, DOCUMENT, AND CLOSE OUT ANY CONSTRUCTION CONTROL DOCUMENTS THAT MAY BE REQUIRED BY GOVERNMENT AGENCIES AND LANDLORDS.
19. PERFORM ANTENNAL AND COAX SWEEP TESTING AND MAKE ANY AND ALL NECESSARY CORRECTIONS.
20. REMAIN ON SITE MOBILIZED THROUGHOUT HAND-OFF AND INTEGRATION TO ASSIST AS NEEDED UNTIL SITE IS DEEMED SUBSTANTIALLY COMPLETE AND PLACED "ON AIR."

3.2 GENERAL REQUIREMENTS FOR CIVL CONSTRUCTION:

- A. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH. AT THE COMPLETION OF THE WORK, CONTRACTOR SHALL REMOVE FROM THE SITE ALL REMAINING RUBBISH, IMPLEMENTS, TEMPORARY FACILITIES, AND SURPLUS MATERIALS.
- B. EQUIPMENT ROOMS SHALL AT ALL TIMES BE MAINTAINED "BROOM CLEAN" AND CLEAR OF DEBRIS.
- C. CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO DISCOVER AND LOCATE ANY HAZARDOUS CONDITION.
 1. IN THE EVENT CONTRACTOR ENCOUNTERS ANY HAZARDOUS CONDITION WHICH HAS NOT BEEN ABATED OR OTHERWISE MITIGATED, CONTRACTOR AND ALL OTHER PERSONS SHALL IMMEDIATELY STOP WORK IN THE AFFECTED AREA AND NOTIFY COMPANY IN WRITING. THE WORK IN THE AFFECTED AREA SHALL NOT BE RESUMED EXCEPT BY WRITTEN NOTIFICATION BY COMPANY.
 2. CONTRACTOR AGREES TO USE CARE WHILE ON THE SITE AND SHALL NOT TAKE ANY ACTION THAT WILL OR MAY RESULT IN OR CAUSE THE HAZARDOUS CONDITION TO BE FURTHER RELEASED IN THE ENVIRONMENT, OR TO FURTHER EXPOSE INDIVIDUALS TO THE HAZARD.
- D. CONTRACTOR'S ACTIVITIES SHALL BE RESTRICTED TO THE PROJECT LIMITS. SHOULD AREAS OUTSIDE THE PROJECT LIMITS BE AFFECTED BY CONTRACTOR'S ACTIVITIES, CONTRACTOR SHALL IMMEDIATELY RETURN THEM TO ORIGINAL CONDITION
- E. CONDUCT TESTING AS REQUIRED HEREIN.

3.3 DELIVERABLES:

- A. CONTRACTOR SHALL REVIEW, APPROVE, AND SUBMIT TO SPRINT SHOP DRAWINGS, PRODUCT DATA, SAMPLES, AND SIMILAR SUBMITTALS AS REQUIRED HEREINAFTER
- B. PROVIDE DOCUMENTATION INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING. DOCUMENTATION SHALL BE FORWARDED IN ORIGINAL FORMAT AND/OR UPLOADED INTO SMS.
 1. ALL CORRESPONDENCE AND PRELIMINARY CONSTRUCTION REPORTS.
 2. PROJECT PROGRESS REPORTS.
 3. CIVIL CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
 4. ELECTRICAL SERVICE COMPLETION DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).

5. LINES AND ANTENNA INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
6. POWER INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
7. TELCO READY DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
8. PPC (OR SHELTER) INSTALL DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
9. TOWER CONSTRUCTION START DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
10. TOWER CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
11. BTS AND RADIO EQUIPMENT DELIVERED AT SITE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
12. NETWORK OPERATIONS HANDOFF CHECKLIST (HOC WALK) COMPLETE (UPLOAD FORM IN SMS)
13. CIVIL CONSTRUCTION COMPLETE DATE (POPULATE FIELD IN SMS AND/OR FORWARD NOTIFICATION).
14. SITE CONSTRUCTION PROGRESS PHOTOS UNLOADED INTO SMS.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HERewith.
- 1.3 SUBMITTALS:
 - A. THE WORK IN ALL ASPECTS SHALL COMPLY WITH THE CONSTRUCTION DRAWINGS AND THESE SPECIFICATIONS.
 - B. SUBMIT THE FOLLOWING TO COMPANY REPRESENTATIVE FOR APPROVAL
 1. CONCRETE MIX-DESIGNS FOR TOWER FOUNDATIONS, ANCHORS PIERS, AND CONCRETE PAVING.
 2. CONCRETE BREAK TESTS AS SPECIFIED HEREIN.
 3. SPECIAL FINISHES FOR INTERIOR SPACES, IF ANY.
 4. ALL EQUIPMENT AND MATERIALS SO IDENTIFIED ON THE CONSTRUCTION DRAWINGS.
 5. CHEMICAL GROUNDING DESIGN
 - D. ALTERNATES: AT THE COMPANY'S REQUEST, ANY ALTERNATIVES TO THE MATERIALS OR METHODS SPECIFIED SHALL BE SUBMITTED TO SPRINT'S CONSTRUCTION MANAGER FOR APPROVAL PRIOR TO BEING SHIPPED TO SITE. SPRINT WILL REVIEW AND APPROVE ONLY THOSE REQUESTS MADE IN WRITING. NO VERBAL APPROVALS WILL BE CONSIDERED. SUBMITTAL FOR APPROVAL SHALL INCLUDE A STATEMENT OF COST REDUCTION PROPOSED FOR USE OF ALTERNATE PRODUCT.

1.4 TESTS AND INSPECTIONS:

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION TESTS, INSPECTIONS AND PROJECT DOCUMENTATION.
- B. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:
 1. COAX SWEEPS AND FIBER TESTS PER TS-0200 REV 4 ANTENNA LINE ACCEPTANCE STANDARDS.
 2. AGL, AZIMUTH AND DOWNTILT USING ELECTRONIC COMMERCIAL MADE-FOR-THE-PURPOSE ANTENNA ALIGNMENT TOOL.
 3. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- C. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES, BUT IS NOT LIMITED TO THE FOLLOWING:
 1. AZIMUTH, DOWNTILT, AGL - UPLOAD REPORT FROM ANTENNA ALIGNMENT TOOL TO SITERRA TASK 465. INSTALLED AZIMUTH, DOWNTILT, AND AGL MUST CONFORM TO THE RF DATA SHEETS. SWEEP AND FIBER TESTS
 2. SCANABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
 3. ALL AVAILABLE JURISDICTIONAL INFORMATION
 4. PDF SCAN OF REDLINES PRODUCED IN FIELD

5. ELECTRONIC AS-BUILT DRAWINGS IN AUTOCAD AND PDF FORMATS. ANY FIELD CHANGE MUST BE REFLECTED BY MODIFYING THE PLANS, ELEVATIONS, AND DETAILS IN THE DRAWING SETS. GENERAL NOTES INDICATING MODIFICATIONS WILL NOT BE ACCEPTED. CHANGES SHALL BE HIGHLIGHTED AS "CLOUDS" IDENTIFIED AS THE "AS-BUILT" CONDITION.
6. LIEN WAIVERS
7. FINAL PAYMENT APPLICATION
8. REQUIRED FINAL CONSTRUCTION PHOTOS
9. CONSTRUCTION AND COMMISSIONING CHECKLIST COMPLETE WITH NO DEFICIENT ITEMS
10. ALL POST NTP TASKS INCLUDING DOCUMENT UPLOADS COMPLETED IN SITERRA (SPRINTS DOCUMENT REPOSITORY OF RECORD).

1.5 COMMISSIONING: PERFORM ALL COMMISSIONING AS REQUIRED BY APPLICABLE MOPs

1.6 INTEGRATION: PERFORM ALL INTEGRATION ACTIVITIES AS REQUIRED BY APPLICABLE MOPs

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 REQUIREMENTS FOR TESTING:

A. THIRD PARTY TESTING AGENCY:

1. WHEN THE USE OF A THIRD PARTY INDEPENDENT TESTING AGENCY IS REQUIRED, THE AGENCY THAT IS SELECTED MUST PERFORM SUCH WORK ON A REGULAR BASIS IN THE STATE WHERE THE PROJECT IS LOCATED AND HAVE A THOROUGH UNDERSTANDING OF LOCAL AVAILABLE MATERIALS, INCLUDING THE SOIL, ROCK, AND GROUNDWATER CONDITIONS.
2. THE THIRD PARTY TESTING AGENCY IS TO BE FAMILIAR WITH THE APPLICABLE REQUIREMENTS FOR THE TESTS TO BE DONE, EQUIPMENT TO BE USED, AND ASSOCIATED HEALTH AND SAFETY ISSUES.
3. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.
4. EXPERIENCE IN SOILS, CONCRETE, MASONRY, AGGREGATE, AND ASPHALT TESTING USING ASTM, AASJTO, AND OTHER METHODS IS NEEDED.

3.2 REQUIRED TESTS:

A. CONTRACTOR SHALL ACCOMPLISH TESTING INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. CONCRETE CYLINDER BREAK TESTS FOR THE TOWER AND ANCHOR FOUNDATIONS AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
2. ASPHALT ROADWAY COMPACTED THICKNESS, SURFACE SMOOTHNESS, AND COMPACTED DENSITY TESTING AS SPECIFIED IN SECTION: HOT MIX ASPHALT PAVING.
3. FIELD QUALITY CONTROL TESTING AS SPECIFIED IN SECTION: PORTLAND CEMENT CONCRETE PAVING.
4. TESTING REQUIRED UNDER SECTION: AGGREGATE BASE FOR ACCESS ROADS, PADS AND ANCHOR LOCATIONS
5. STRUCTURAL BACKFILL COMPACTION TESTS FOR THE TOWER FOUNDATION.
6. SITE RESISTANCE TO EARTH TESTING PER EXHIBIT: CELL SITE GROUNDING SYSTEM DESIGN.
7. ANTENNA AND COAX SWEEP TESTS PER EXHIBIT: ANTENNA TRANSMISSION LINE ACCEPTANCE STANDARDS.
8. GROUNDING AT ANTENNA MASTS FOR GPS AND ANTENNAS
9. ALL OTHER TESTS REQUIRED BY COMPANY OR JURISDICTION.

3.3 REQUIRED INSPECTIONS

A. SCHEDULE INSPECTIONS WITH COMPANY REPRESENTATIVE.

B. CONDUCT INSPECTIONS INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

1. GROUNDING SYSTEM INSTALLATION PRIOR TO EARTH CONCEALMENT DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
2. FORMING FOR CONCRETE AND REBAR PLACEMENT PRIOR TO POUR DOCUMENTED WITH DIGITAL PHOTOGRAPHS BY CONTRACTOR, APPROVED BY A&E OR SPRINT REPRESENTATIVE.
3. COMPACTION OF BACKFILL MATERIALS; AGGREGATE BASE FOR ROADS, PADS, AND ANCHORS; ASPHALT PAVING; AND SHAFT BACKFILL FOR CONCRETE AND WOOD POLES, BY INDEPENDENT THIRD PARTY AGENCY.
4. PRE- AND POST-CONSTRUCTION ROOFTOP AND STRUCTURAL INSPECTIONS ON EXISTING FACILITIES.
5. TOWER ERECTION SECTION STACKING AND PLATFORM ATTACHMENT DOCUMENTED BY DIGITAL PHOTOGRAPHS BY THIRD PARTY AGENCY.
6. ANTENNA AZIMUTH , DOWN TILT AND PER SUNLIGHT TOOL SUNSIGHT INSTRUMENTS - ANTENNALIGN ALIGNMENT TOOL (AAT)

PLANS PREPARED FOR:



PLANS PREPARED BY:



MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

**36 PROSPECT ST
NEWINGTON, CT 06109**

SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:

SP-2

CONTINUE FROM SP-2

- 7. VERIFICATION DOCUMENTED WITH THE ANTENNA CHECKLIST REPORT, BY A&E, SITE DEVELOPMENT REP, OR RF REP.
- 8. FINAL INSPECTION CHECKLIST AND HANDOFF WALK (HOC). SIGNED FORM SHOWING ACCEPTANCE BY FIELD OPS IS TO BE UPLOADED INTO SMS.
- 9. COAX SWEEP AND FIBER TESTING DOCUMENTS SUBMITTED VIA SMS FOR RF APPROVAL.
- 10. SCAN-ABLE BARCODE PHOTOGRAPHS OF TOWER TOP AND INACCESSIBLE SERIALIZED EQUIPMENT
- 11. ALL AVAILABLE JURISDICTIONAL INFORMATION
- 12. PDF SCAN OF REDLINES PRODUCED IN FIELD
- C. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL CORRECTIONS TO ANY WORK IDENTIFIED AS UNACCEPTABLE IN SITE INSPECTION ACTIVITIES AND/OR AS A RESULT OF TESTING.
- D. CONSTRUCTION INSPECTIONS AND CORRECTIVE MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR WITH WRITTEN REPORTS AND PHOTOGRAPHS. PHOTOGRAPHS MUST BE DIGITAL AND OF SUFFICIENT QUALITY TO CLEARLY SHOW THE SITE CONSTRUCTION. PHOTOGRAPHS MUST CLEARLY IDENTIFY THE PHOTOGRAPHED ITEM AND BE LABELED WITH THE SITE CASCADE NUMBER, SITE NAME, DESCRIPTION, AND DATE.
- 3.4 DELIVERABLES: TEST AND INSPECTION REPORTS AND CLOSEOUT DOCUMENTATION SHALL BE UPLOADED TO THE SMS AND/OR FORWARDED TO SPRINT FOR INCLUSION INTO THE PERMANENT SITE FILES.
 - A. THE FOLLOWING TEST AND INSPECTION REPORTS SHALL BE PROVIDED AS APPLICABLE.
 - 1. CONCRETE MIX AND CYLINDER BREAK REPORTS.
 - 2. STRUCTURAL BACKFILL COMPACTION REPORTS.
 - 3. SITE RESISTANCE TO EARTH TEST.
 - 4. ANTENNA AZIMUTH AND DOWN TILT VERIFICATION
 - 5. TOWER ERECTION INSPECTIONS AND MEASUREMENTS DOCUMENTING TOWER INSTALLED PER SUPPLIER'S REQUIREMENTS AND THE APPLICABLE SECTIONS HEREIN.
 - 6. COAX CABLE SWEEP TESTS PER COMPANY'S "ANTENNA LINE ACCEPTANCE STANDARDS".
 - B. REQUIRED CLOSEOUT DOCUMENTATION INCLUDES THE FOLLOWING;
 - 1. TEST WELLS AND TRENCHES: PHOTOGRAPHS OF ALL TEST WELLS; PHOTOGRAPHS SHOWING ALL OPEN EXCAVATIONS AND TRENCHING PRIOR TO BACKFILLING SHOWING A TAPE MEASURE VISIBLE IN THE EXCAVATIONS INDICATING DEPTH.
 - 2. CONDUITS, CONDUCTORS AND GROUNDING: PHOTOGRAPHS SHOWING TYPICAL INSTALLATION OF CONDUCTORS AND CONNECTORS; PHOTOGRAPHS SHOWING TYPICAL BEND RADIUS OF INSTALLED GROUND WIRES AND GROUND ROD SPACING;
 - 3. CONCRETE FORMS AND REINFORCING: CONCRETE FORMING AT TOWER AND EQUIPMENT/SHELTER PAD/FOUNDATIONS - PHOTOGRAPHS SHOWING ALL REINFORCING STEEL, UTILITY AND CONDUIT STUB OUTS; PHOTOGRAPHS SHOWING CONCRETE POUR OF SHELTER SLAB/FOUNDATION, TOWER FOUNDATION AND GUY ANCHORS WITH VIBRATOR IN USE; PHOTOGRAPHS SHOWING EACH ANCHOR ON GUYED TOWERS, BEFORE CONCRETE POUR.
 - 4. TOWER, ANTENNAS AND MAINLINE: INSPECTION AND PHOTOGRAPHS OF SECTION STACKING; INSPECTION AND PHOTOGRAPHS OF PLATFORM COMPONENT ATTACHMENT POINTS; PHOTOGRAPHS OF TOWER TOP GROUNDING; PHOTOS OF TOWER COAX LINE COLOR CODING AT THE TOP AND AT GROUND LEVEL; INSPECTION AND PHOTOGRAPHS OF OPERATIONAL OF TOWER LIGHTING, AND PLACEMENT OF FAA REGISTRATION SIGN; PHOTOGRAPHS SHOWING ADDITIONAL GROUNDING POINTS FOR TOWERS GREATER THAN 200 FEET.; PHOTOS OF ANTENNA GROUND BAR, EQUIPMENT GROUND BAR, AND MASTER GROUND BAR; PHOTOS OF GPS ANTENNA(S); PHOTOS OF EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA; PHOTOS OF COAX WEATHERPROOFING - TOP AND BOTTOM; PHOTOS OF COAX GROUNDING--TOP AND BOTTOM; PHOTOS OF ANTENNA AND MAST GROUNDING; PHOTOS OF COAX CABLE ENTRY INTO SHELTER; PHOTOS OF PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 5. ROOF TOPS: PRE-CONSTRUCTION AND POST-CONSTRUCTION VISUAL INSPECTION AND PHOTOGRAPHS OF THE ROOF AND INTERIOR TO DETERMINE AND DOCUMENT CONDITIONS; ROOF TOP CONSTRUCTION INSPECTIONS AS REQUIRED BY THE JURISDICTION; PHOTOGRAPHS OF CABLE TRAY AND/OR ICE BRIDGE; PHOTOGRAPHS OF DOGHOUSE/CABLE EXIT FROM ROOF;
 - 6. SITE LAYOUT - PHOTOGRAPHS OF THE OVERALL COMPOUND, INCLUDING EQUIPMENT PLATFORM FROM ALL FOUR CORNERS.
 - 7. FINISHED UTILITIES: CLOSE-UP PHOTOGRAPHS OF THE PPC BREAKER PANEL; CLOSE-UP PHOTOGRAPH OF THE INSIDE OF THE TELCO PANEL AND NIU; CLOSE-UP PHOTOGRAPH OF THE POWER METER AND DISCONNECT; PHOTOS OF POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE; PHOTOGRAPHS AT METER BOX AND/OR FACILITY DISTRIBUTION PANEL.
 - 8. REQUIRED MATERIALS CERTIFICATIONS: CONCRETE MIX DESIGNS; MILL CERTIFICATION FOR ALL REINFORCING AND STRUCTURAL STEEL; AND ASPHALT PAVING MIX DESIGN.
 - 9. ANY AND ALL SUBMITTALS BY THE JURISDICTION OR COMPANY.

SECTION 01 400 - SUBMITTALS & TESTS

PART 1 - GENERAL

- 1.1 THE WORK: THESE STANDARD CONSTRUCTION SPECIFICATIONS IN CONJUNCTION WITH THE OTHER CONTRACT DOCUMENTS AND THE CONSTRUCTION DRAWINGS DESCRIBE THE WORK TO BE PERFORMED BY THE CONTRACTOR.
- 1.2 RELATED DOCUMENTS:
 - A. THE REQUIREMENTS OF THIS SECTION APPLY TO ALL SECTIONS IN THIS SPECIFICATION.
 - B. SPRINT "STANDARD CONSTRUCTION DETAILS FOR WIRELESS SITES" ARE INCLUDED IN AND MADE A PART OF THESE SPECIFICATIONS HEREWITH.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

- 3.1 WEEKLY REPORTS:
 - A. CONTRACTOR SHALL PROVIDE SPRINT WITH WEEKLY REPORTS SHOWING PROJECT STATUS. THIS STATUS REPORT FORMAT WILL BE PROVIDED TO THE CONTRACTOR BY SPRINT. THE REPORT WILL CONTAIN SITE ID NUMBER, THE MILESTONES FOR EACH SITE, INCLUDING THE BASELINE DATE, ESTIMATED COMPLETION DATE AND ACTUAL COMPLETION DATE.
 - B. REPORT INFORMATION WILL BE TRANSMITTED TO SPRINT VIA ELECTRONIC MEANS AS REQUIRED. THIS INFORMATION WILL PROVIDE A BASIS FOR PROGRESS MONITORING AND PAYMENT.
- 3.2 PROJECT CONFERENCE CALLS:
 - A. SPRINT MAY HOLD WEEKLY PROJECT CONFERENCE CALLS. CONTRACTOR WILL BE REQUIRED TO COMMUNICATE SITE STATUS, MILESTONE COMPLETIONS AND UPCOMING MILESTONE PROJECTIONS, AND ANSWER ANY OTHER SITE STATUS QUESTIONS AS NECESSARY.
- 3.3 PROJECT TRACKING IN SMS:
 - A. CONTRACTOR SHALL PROVIDE SCHEDULE UPDATES AND PROJECTIONS IN THE SMS SYSTEM ON A WEEKLY BASIS.
- 3.4 ADDITIONAL REPORTING:
 - A. ADDITIONAL OR ALTERNATE REPORTING REQUIREMENTS MAY BE ADDED TO THE REPORT AS DETERMINED TO BE REASONABLY NECESSARY BY COMPANY.
- 3.5 PROJECT PHOTOGRAPHS:
 - A. FILE DIGITAL PHOTOGRAPHS OF COMPLETED SITE IN JPEG FORMAT IN THE SMS PHOTO LIBRARY FOR THE RESPECTIVE SITE. PHOTOGRAPHS SHALL BE CLEARLY LABELED WITH SITE NUMBER, NAME AND DESCRIPTION, AND SHALL INCLUDE AT A MINIMUM THE FOLLOWING AS APPLICABLE:
 - 1. SHELTER AND TOWER OVERVIEW.
 - 2. TOWER FOUNDATION(S) - FORMS AND STEEL BEFORE POUR (EACH ANCHOR ON GUYED TOWERS).
 - 3. TOWER FOUNDATION(S) POUR WITH VIBRATOR IN USE (EACH ANCHOR ON GUYED TOWERS).
 - 4. TOWER STEEL AS BEING INSTALLED INTO HOLE (SHOW ANCHOR STEEL ON GUYED TOWERS).
 - 5. PHOTOS OF TOWER SECTION STACKING.
 - 6. CONCRETE TESTING / SAMPLES.
 - 7. PLACING OF ANCHOR BOLTS IN TOWER FOUNDATION.
 - 8. BUILDING/WATER TANK FROM ROAD FOR TENANT IMPROVEMENTS OR COMMENTS.
 - 9. SHELTER FOUNDATION--FORMS AND STEEL BEFORE POURING.
 - 10. SHELTER FOUNDATION POUR WITH VIBRATOR IN USE.
 - 11. COAX CABLE ENTRY INTO SHELTER.
 - 12. PLATFORM MECHANICAL CONNECTIONS TO TOWER/MONOPOLE.
 - 13. ROOFTOP PRE AND POST CONSTRUCTION PHOTOS TO INCLUDE PENETRATIONS AND INTERIOR CEILING.
 - 14. PHOTOS OF TOWER TOP COAX LINE COLOR CODING AND COLOR CODING AT GROUND LEVEL.
 - 15. PHOTOS OF ALL APPROPRIATE COMPANY OR REGULATORY SIGNAGE.
 - 16. PHOTOS OF EQUIPMENT BOLT DOWN INSIDE SHELTER.
 - 17. POWER AND TELCO ENTRANCE TO COMPANY ENCLOSURE AND POWER AND TELCO SUPPLY LOCATIONS INCLUDING METER/DISCONNECT.
 - 18. ELECTRICAL TRENCH(S) WITH ELECTRICAL / CONDUIT BEFORE BACKFILL
 - 19. ELECTRICAL TRENCH(S) WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL
 - 20. TELCO TRENCH WITH TELEPHONE / CONDUIT BEFORE BACKFILL
 - 21. TELCO TRENCH WITH FOIL-BACKED TAPE BEFORE FURTHER BACKFILL
 - 22. SHELTER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 23. TOWER GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).

- 24. FENCE GROUND-RING TRENCH WITH GROUND-WIRE BEFORE BACKFILL (SHOW ALL CAD WELDS AND BEND RADI).
 - 25. ALL BTS GROUND CONNECTIONS.
 - 26. ALL GROUND TEST WELLS.
 - 27. ANTENNA GROUND BAR AND EQUIPMENT GROUND BAR.
 - 28. ADDITIONAL GROUNDING POINTS ON TOWERS ABOVE 200'.
 - 29. HVAC UNITS INCLUDING CONDENSERS ON SPLIT SYSTEMS.
 - 30. GPS ANTENNAS.
 - 31. CABLE TRAY AND/OR WAVEGUIDE BRIDGE.
 - 32. DOGHOUSE/CABLE EXIT FROM ROOF.
 - 33. EACH SECTOR OF ANTENNAS; ONE PHOTOGRAPH LOOKING AT THE SECTOR AND ONE FROM BEHIND SHOWING THE PROJECTED COVERAGE AREA.
 - 34. MASTER BUS BAR.
 - 35. TELCO BOARD AND NIU.
 - 36. ELECTRICAL DISTRIBUTION WALL.
 - 37. CABLE ENTRY WITH SURGE SUPPRESSION.
 - 38. ENTRANCE TO EQUIPMENT ROOM.
 - 39. COAX WEATHERPROOFING--TOP AND BOTTOM OF TOWER.
 - 40. COAX GROUNDING --TOP AND BOTTOM OF TOWER.
 - 41. ANTENNA AND MAST GROUNDING.
 - 42. LANDSCAPING - WHERE APPLICABLE.
- 3.6 FINAL PROJECT ACCEPTANCE: COMPLETE ALL REQUIRED REPORTING TASKS PER CONTRACT, CONTRACT DOCUMENTS OR THE SPRINT INTEGRATED CONSTRUCTION STANDARDS FOR WIRELESS SITES AND UPLOAD INTO SITERRA.

PLANS PREPARED FOR:



6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:




Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

**36 PROSPECT ST
NEWINGTON, CT 06109**



SHEET DESCRIPTION:

SPRINT SPECIFICATIONS

SHEET NUMBER:



SP-3

INFORMATION CONTAINED WITHIN DRAWINGS ARE BASED ON PROVIDED INFORMATION AND ARE NOT THE RESULT OF A FIELD SURVEY.



OVERALL SITE PLAN

SCALE: AS NOTED 1



SPRINT EQUIPMENT PLAN

SCALE: AS NOTED 2

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

36 PROSPECT ST
NEWINGTON, CT 06109

SHEET DESCRIPTION:

SITE PLAN

SHEET NUMBER:


A-1

NOTE:
FOR ADDITIONAL STRUCTURAL
INFORMATION, REFER TO
STRUCTURAL ANALYSIS COMPLETED
BY SSOE GROUP DATED 5/14/14

NOTE:
CONTRACTOR SHALL NOT INSTALL THE
2.5 RRU'S SUCH THAT THEY IMPEDE
CLIMBING ACCESS ON THE TOWER.

NOTE:
SEE DETAIL 2 ON A-3
FOR ANTENNA LAYOUT

NOTE:
SPRINT TOWER TOP WORK CONTINGENT ON FOLLOWING:
COMPLETION OF STRUCTURAL ANALYSIS PROVIDED BY
CROWN CASTLE, COMPLETION OF ANTENNA/RRH
MOUNTING ASSESSMENT (PROVIDED BY AE)



PLANS PREPARED FOR:
Sprint
6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:
CROWN CASTLE



DRAWING NOTICE:
THESE DOCUMENTS ARE CONFIDENTIAL AND ARE
THE SOLE PROPERTY OF SPRINT AND MAY NOT BE
REPRODUCED, DISSEMINATED OR REDISTRIBUTED
WITHOUT THE EXPRESS WRITTEN CONSENT OF
SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		5/22/14	AHS	0

SITE NAME:
36 PROSPECT ST

SITE CASCADE:
CT03XC084

SITE ADDRESS:
**36 PROSPECT ST
NEWINGTON, CT 06109**

SHEET DESCRIPTION:
**TOWER ELEVATION
& CABLE PLAN**


SHEET NUMBER:
A-2

DETAIL NOT USED NO SCALE 2

TOWER ELEVATION NO SCALE 1

DETAIL NOT USED NO SCALE 3

DETAIL NOT USED NO SCALE 4




0' = TRUE NORTH

EXISTING ANTENNA & RRU LAYOUT

NO SCALE

1




0' = TRUE NORTH

FINAL ANTENNA LAYOUT

NO SCALE

2



NOTES:

- CUT DC CONDUCTORS TO LENGTH.
- COIL FIBER CABLE AND SECURE AT SIDE OF RRU.
- DO NOT EXCEED BEND RADIUS.

NOTE:
CONTRACTOR TO POSITION RRU ON MOUNT BEHIND ANTENNA SUCH THAT THE RRU DOES NOT INTERFERE WITH THE EXISTING PLATFORM/T-ARM MOUNTING HARDWARE.

NOTE:
SPARE DC CABLES ARE COILED UP ON NV RRHS AT SPRINT ARRAY. THESE ARE TO BE USED TO POWER UP THE 2.5 RRHS AND TIED INTO EXISTING DC BREAKERS INSIDE THE FIBER JUNCTION BOX LOCATED AT EQUIPMENT.

NOTE:
THE DIAGRAM IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO REFER TO PASSING STRUCTURAL ANALYSIS FOR ANTENNA AND RRU MOUNTING DETAILS.

DETAIL NOT USED

NO SCALE

3

TYPICAL ANTENNA & RRU MOUNTING DETAILS

NO SCALE

4

THE CONFIGURATION PLANS ARE BASED ON PROVIDED INFORMATION AND ARE FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR TO VERIFY FIELD CONDITIONS PRIOR TO CONSTRUCTION.

NOTE:
JUMPERS FROM 2.5 RRH TO THE 2.5 ANTENNA CANNOT EXCEED 15 FEET

PLANS PREPARED FOR:

Sprint
6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design. Build. Deliver.
1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

36 PROSPECT ST
NEWINGTON, CT 06109

SHEET DESCRIPTION:

ANTENNA LAYOUT & MOUNTING DETAILS

SHEET NUMBER:


A-3

NV CABLES			
BAND	INDICATOR	PORT	COLOR
800-1	YEL GRN	NV-1	GRN
1900-1	YEL RED	NV-2	BLU
1900-2	YEL BRN	NV-3	BRN
1900-3	YEL BLU	NV-4	WHT
1900-4	YEL SLT	NV-5	RED
800-2	YEL ORG	NV-6	SLT
SPARE	YEL WHT	NV-7	PPL
2500	YEL PPL	NV-8	ORG

HYBRID	
HYBRID	COLOR
1	GRN
2	BLU
3	BRN
4	WHT
5	RED
6	SLT
7	PPL
8	ORG

2.5 Band		
2500 Radio 1	COLOR	
YEL	WHT	GRN
YEL	WHT	BLU
YEL	WHT	BRN
YEL	WHT	WHT
YEL	WHT	RED
YEL	WHT	SLT
YEL	WHT	PPL
YEL	WHT	ORG

Figure 1: Antenna Orientation






NOTES:

- ALL CABLES SHALL BE MARKED WITH 2" WIDE, UV STABILIZED, UL APPROVED TAPE.
- THE FIRST RING SHALL BE CLOSEST TO THE END OF THE CABLE AND SPACED APPROXIMATELY 2" FROM THE END CONNECTOR, WEATHERPROOFING, OR BREAK-OUT CYLINDER. THERE SHALL BE A 1" SPACE BETWEEN EACH RING FOR THE CABLE IDENTIFIER, AND NO SPACES BETWEEN THE FREQUENCY BANDS.
- A 2" GAP SHALL SEPARATE THE CABLE COLOR CODE FROM THE FREQUENCY COLOR CODE. THE 2" COLOR RINGS FOR THE FREQUENCY CODE SHALL BE PLACED NEXT TO EACH OTHER WITH NO SPACES.
- THE 2" COLORED TAPE(S) SHALL EACH BE WRAPPED A MINIMUM OF 3 TIMES AROUND THE INDIVIDUAL CABLES, AND THE TAPE SHALL BE KEPT IN THE SAME LOCATION AS MUCH AS POSSIBLE.
- SITES WITH MORE THAN FOUR (4) SECTORS WILL REQUIRE ADDITIONAL RINGS FOR EACH SECTOR, FOLLOWING THE PATTERN. HIGH CAPACITY SITES WILL USE THE NEXT COLOR IN THE SEQUENCE FOR ADDITIONAL CABLES IN EACH SECTOR.
- HYBRID FIBER CABLE SHALL BE SECTOR IDENTIFIED INSIDE THE CABINET ON FREQUENCY BUNDLES, ON THE SEALTITE, ON THE MAIN LINE UPON EXIT OF SEALTITE, AND BEFORE AND AFTER THE BREAKOUT UNIT (MEDUSA), AS WELL AS BEFORE AND AFTER ANY ENTRANCE OR EXIT.
- HFC "MAIN TRUNK" WILL NOT BE MARKED WITH THE FREQUENCY CODES, AS IT CONTAINS ALL FREQUENCIES.
- INDIVIDUAL POWER PAIRS AND FIBER BUNDLES SHALL BE LABELED WITH BOTH THE CABLE AND FREQUENCY.

Sector	Cable	First Ring	Second Ring	Third Ring
1 Alpha	1	Green	No Tape	No Tape
	2	No Tape	No Tape	No Tape
	3	Brown	No Tape	No Tape
	4	White	No Tape	No Tape
	5	Red	No Tape	No Tape
	6	Grey	No Tape	No Tape
	7	Purple	No Tape	No Tape
	8	Orange	No Tape	No Tape
2 Beta	1	Green	Green	No Tape
	2	No Tape	No Tape	No Tape
	3	Brown	Brown	No Tape
	4	White	White	No Tape
	5	Red	Red	No Tape
	6	Grey	Grey	No Tape
	7	Purple	Purple	No Tape
	8	Orange	Orange	No Tape
3 Gamma	1	Green	Green	Green
	2	No Tape	No Tape	No Tape
	3	Brown	Brown	Brown
	4	White	White	White
	5	Red	Red	Red
	6	Grey	Grey	Grey
	7	Purple	Purple	Purple
	8	Orange	Orange	Orange

NV FREQUENCY	INDICATOR	ID
800-1	YEL GRN	GRN
1900-1	YEL RED	RED
1900-2	YEL BRN	BRN
1900-3	YEL BLU	BLU
1900-4	YEL SLT	SLT
800-1	YEL ORG	ORG
RESERVED	YEL WHT	WHT
RESERVED	YEL PPL	PPL

2.5 FREQUENCY	INDICATOR		ID
2500 -1	YEL	WHT	GRN
2500 -2	YEL	WHT	RED
2500 -3	YEL	WHT	BRN
2500 -4	YEL	WHT	BLU
2500 -5	YEL	WHT	SLT
2500 -6	YEL	WHT	ORG
2500 -7	YEL	WHT	WHT
2500 -8	YEL	WHT	PPL



PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793
JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

36 PROSPECT ST
NEWINGTON, CT 06109

SHEET DESCRIPTION:


COLOR CODING AND NOTES

SHEET NUMBER:


A-4

RRU: ALCATEL LUCENT TD-RRH8X20


COLOR: LIGHT GREY
WEIGHT: 70 LBS.



SIDE VIEW




FRONT VIEW



PLAN VIEW

NOTES

COMPLY WITH MANUFACTURERS INSTRUCTIONS TO ENSURE THAT ALL RRU'S RECEIVE ELECTRICAL POWER WITHIN 24 HOURS OF BEING REMOVED FROM THE MANUFACTURER'S PACKAGING. DO NOT OPEN RRU PACKAGES IN THE RAIN



FRONT VIEW

2.5 RRU

NO SCALE

1


NEW EQUIPMENT IN EXISTING CABINET

NO SCALE


2

ANTENNA: RFS APXVTM14-C-I20

RADOME MATERIAL: ASA
 RADOME COLOR: LIGHT GRAY
 DIMENSIONS, HxWxD.in(mim): 56.3"x12.6"x6.3" (1430x320x160mm)
 WEIGHT: 52.9 lbs
 CONNECTORS: (8) 4.1/9.5 DIN FEMALE
 (1) NF - CALIBRATION CONNECTOR



PLAN VIEW



2.5 ANTENNA

NO SCALE

3

DETAIL NOT USED

NO SCALE

4

PLANS PREPARED FOR:



PLANS PREPARED BY:



1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:



ENGINEERING LICENSE:



DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

36 PROSPECT ST
 NEWINGTON, CT 06109

SHEET DESCRIPTION:




EQUIPMENT &
 MOUNTING DETAILS

SHEET NUMBER:

A-5

RFS HYBRIFLEX RISER CABLE SCHEDULE


Fiber Only (Existing DC Power)	Hybrid cable MN: HB058-M12-050F 12x multi-mode fiber pairs, Top: Outdoor protected connectors, Bottom: LC Connectors, 5/8 cable, 50 ft	50 ft
	MN: HB058-M12-075F	75 ft
	MN: HB058-M12-100F	100 ft
	MN: HB058-M12-125F	125 ft
	MN: HB058-M12-150F	150 ft
	MN: HB058-M12-175F	175 ft
	MN: HB058-M12-200F	200 ft
8 AWG Power	Hybrid cable MN: HB114-08U3M12-050F 3x 8 AWG power pairs, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 50 ft	50 ft
	MN: HB114-08U3M12-075F	75 ft
	MN: HB114-08U3M12-100F	100 ft
	MN: HB114-08U3M12-125F	125 ft
	MN: HB114-08U3M12-150F	150 ft
	MN: HB114-08U3M12-175F	175 ft
6 AWG Power	Hybrid cable MN: HB114-13U3M12-225F 3x 6 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 225 ft	225 ft
	MN: HB114-13U3M12-250F	250 ft
	MN: HB114-13U3M12-300F	300 ft
4 AWG Power	Hybrid cable MN: HB114-21U3M12-325F 3x 4 AWG power pair, 12x multi-mode fiber pairs, Outdoor rated connectors & LC Connectors, 1 1/4 cable, 325 ft	325 ft
	MN: HB114-21U3M12-350F	350 ft
	MN: HB114-21U3M12-375F	375 ft



RFS HYBRIFLEX JUMPER CABLE SCHEDULE

Fiber Only	Hybrid Jumper cable MN: HBF012-M3-5F1 5 ft, 3x multi-mode fiber pairs, Outdoor & LC connectors, 1/2 cable	5 ft
	MN: HBF012-M3-10F1	10 ft
	MN: HBF012-M3-15F1	15 ft
	MN: HBF012-M3-20F1	20 ft
	MN: HBF012-M3-25F1	25 ft
	MN: HBF012-M3-30F1	30 ft
8 AWG Power	Hybrid Jumper cable MN: HBF058-08U1M3-5F1 5 ft, 1x 8 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-08U1M3-10F1	10 ft
	MN: HBF058-08U1M3-15F1	15 ft
	MN: HBF058-08U1M3-20F1	20 ft
	MN: HBF058-08U1M3-25F1	25 ft
	MN: HBF058-08U1M3-30F1	30 ft
6 AWG Power	Hybrid Jumper cable MN: HBF058-13U1M3-5F1 5 ft, 1x 6 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 5/8 cable	5 ft
	MN: HBF058-13U1M3-10F1	10 ft
	MN: HBF058-13U1M3-15F1	15 ft
	MN: HBF058-13U1M3-20F1	20 ft
	MN: HBF058-13U1M3-25F1	25 ft
	MN: HBF058-13U1M3-30F1	30 ft
4 AWG Power	Hybrid Jumper cable MN: HBF078-21U1M3-5F1 5 ft, 1x 4 AWG power pair, 3x multi-mode fiber pairs, Outdoor & LC Connectors, 7/8 cable	5 ft
	MN: HBF078-21U1M3-10F1	10 ft
	MN: HBF078-21U1M3-15F1	15 ft
	MN: HBF078-21U1M3-20F1	20 ft
	MN: HBF078-21U1M3-25F1	25 ft
	MN: HBF078-21U1M3-30F1	30 ft

NOTE:
SPRINT CM TO CONFIRM HYBRID OR FIBER RISER CABLE AND HYBRID OR FIBER JUMPER CABLE MODEL NUMBERS IF HYBRID CABLES ARE REQUIRED BEFORE PREPARING BOM.



FIBER JUNCTION BOX PENETRATION

NO SCALE 2

2.5 CABLE CROSS SECTION DATA

NO SCALE 1

DETAIL NOT USED

NO SCALE 3

PLANS PREPARED FOR:

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

Design. Build. Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 890-0790
Fax # (518) 890-0793

JOB NUMBER 353-000

MLA PARTNER:

ENGINEERING LICENSE:

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:
36 PROSPECT ST

SITE CASCADE:
CT03XC084

SITE ADDRESS:
36 PROSPECT ST
NEWINGTON, CT 06109

SHEET DESCRIPTION:
CIVIL DETAILS

SHEET NUMBER:
A-6

DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0


SITE NAME:
36 PROSPECT ST

SITE CASCADE:
CT03XC084


SITE ADDRESS:
 36 PROSPECT ST
 NEWINGTON, CT 06109

SHEET DESCRIPTION:
CIVIL DETAILS


SHEET NUMBER:
A-7



ALU 2.5 ALU SCENARIO 1



RAN WIRING DIAGRAM



RF 2.5 ALU SCENARIO 1

PLANS PREPARED FOR:

Sprint

6580 Sprint Parkway
Overland Park, Kansas 66251

PLANS PREPARED BY:

INFINIGY Design.
Build.
Deliver.

1033 Watervliet Shaker Rd
Albany, NY 12205
Office # (518) 690-0790
Fax # (518) 690-0793

JOB NUMBER 353-000

MLA PARTNER:

CROWN CASTLE

ENGINEERING LICENSE:




PLAN NOT USED

NO SCALE

1

LEGEND:


- EXISTING GROUND RING
- CADWELD CONNECTION (EXOTHERMIC WELD)
- ▲ MECHANICAL CONNECTION
- ⊗ GROUND ROD
- CABLE GROUND KIT



TYPICAL ANTENNA GROUNDING PLAN

NO SCALE

2



NOTE:
DEPICTION IS FOR CONCEPTUAL PURPOSES ONLY. CONTRACTOR IS TO FIELD VERIFY PRIOR TO CONSTRUCTION

TYPICAL EQUIPMENT GROUNDING PLAN (ELEVATION)

NO SCALE

3

DRAWING NOTICE:

THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:

DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION	5/22/14	AHS	0

SITE NAME:

36 PROSPECT ST

SITE CASCADE:

CT03XC084

SITE ADDRESS:

36 PROSPECT ST
NEWINGTON, CT 06109


SHEET DESCRIPTION:

ELECTRICAL & GROUNDING PLAN

SHEET NUMBER:

E-1

NOTES
 CG SHALL REFERENCE ALL SPECS FOR "CONNECTING THE POWER SUPPLY" OF THE NEW INSTALLATION DOCUMENTS, FOR ALL CONNECTION SPECIFICATIONS.



CIRCUIT SCHEDULE			
NO	FROM	TO	CONFIGURATION
①	UTILITY SOURCE	METER/DISCONNECT	EXISTING
②	METER/DISCONNECT	TRANSFER & LOAD CENTER	EXISTING
③	TRANSFER & LOAD CENTER	GENERATOR RECEPTACLE	EXISTING
④	TRANSFER & LOAD CENTER	EXISTING SPRINT BBU CABINET	EXISTING
⑤	TRANSFER & LOAD CENTER	EXISTING SPRINT MMBS CABINET	EXISTING

PLANS PREPARED FOR:
Sprint
 6580 Sprint Parkway
 Overland Park, Kansas 66251

PLANS PREPARED BY:
INFINIGY Design, Build, Deliver.
 1033 Watervliet Shaker Rd
 Albany, NY 12205
 Office # (518) 690-0790
 Fax # (518) 690-0793
 JOB NUMBER 353-000

MLA PARTNER:
CROWN CASTLE



DRAWING NOTICE:
 THESE DOCUMENTS ARE CONFIDENTIAL AND ARE THE SOLE PROPERTY OF SPRINT AND MAY NOT BE REPRODUCED, DISSEMINATED OR REDISTRIBUTED WITHOUT THE EXPRESS WRITTEN CONSENT OF SPRINT.

REVISIONS:	DESCRIPTION	DATE	BY	REV
ISSUED FOR CONSTRUCTION		5/22/14	AHS	0

SITE NAME:
36 PROSPECT ST

SITE CASCADE:
CT03XC084


SITE ADDRESS:
**36 PROSPECT ST
 NEWINGTON, CT 06109**

SHEET DESCRIPTION:
**ELECTRICAL &
 GROUNDING DETAILS**


SHEET NUMBER:
E-2

ELECTRICAL ONE-LINE DIAGRAM

NO SCALE 1




NOTES
 1. APPLY NO-OX TO LUG AND BAR CONTACT SURFACE. DO NOT COAT INLINE LUG.
 2. IF STOLEN GROUND BARS ARE ENCOUNTERED, CONTACT SPRINT CM FOR REPLACEMENT THREADED ROD KIT.



TWO HOLE LUG

NO SCALE 3



GROUNDING RISER DIAGRAM

NO SCALE 4

INSTALLATION OF GROUNDING CONDUCTOR TO GROUNDING BAR

NO SCALE 2

Date: **May 14, 2014**



Patrick Byrum
Crown Castle
3530 Toringdon Way, Suite 300
Charlotte, NC 28277
(704) 405-6532

SSOE Group
320 Seven Springs Way, Ste. 350
Brentwood, TN 37027
(615) 661-7585
akulkarni@ssoe.com

Subject: **Structural Analysis Report**

Carrier Designation: **Sprint PCS Co-Locate** Scenario 2.5B
Carrier Site Number: CT03XC084

Crown Castle Designation: **Crown Castle BU Number:** 876332
Crown Castle Site Name: 36 Prospect Street
Crown Castle JDE Job Number: 286428
Crown Castle Work Order Number: 758020
Crown Castle Application Number: 245362 Rev. 1

Engineering Firm Designation: **SSOE Project Number:** 014-00546-00

Site Data: **36 Prospect Street, Newington, CT 06109, Hartford County**
Latitude 41° 41' 23.66", Longitude -72° 42' 18.85"
136 Foot - Summit Monopole Tower

Dear Mr. Patrick Byrum,

SSOE Group is pleased to submit this “**Structural Analysis Report**” to determine the structural integrity of the above mentioned tower. This analysis has been performed in accordance with the Crown Castle Structural ‘Statement of Work’ and the terms of Crown Castle Purchase Order Number 644929, in accordance with application 245362, revision 1.

The purpose of the analysis is to determine acceptability of the tower stress level. Based on our analysis we have determined the tower stress level for the structure and foundation, under the following load case, to be:

LC7: Existing + Reserved + Proposed Equipment **Sufficient Capacity**
Note: See Table I and Table II for the proposed and existing/reserved loading, respectively.


The analysis has been performed in accordance with the TIA/EIA-222-F standard and 2005 CT Building Code with 2009 amendment based upon a wind speed of 80 mph fastest mile.

We at SSOE Group appreciate the opportunity of providing our continuing professional services to you and Crown Castle. If you have any questions or need further assistance on this or any other projects please give us a call.

Structural analysis prepared by: Anjali Kulkarni

Respectfully submitted by:

Barry W. Burgess, P.E.
Section Manager



5/14/14

TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Antenna and Cable Information

Table 2 - Existing and Reserved Antenna and Cable Information

Table 3 - Design Antenna and Cable Information

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

3.1) Analysis Method

3.2) Assumptions

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Table 6 – Tower Component Stresses vs. Capacity

4.1) Recommendations

5) DISCLAIMER OF WARRANTIES

6) APPENDIX A

tnxTower Output

7) APPENDIX B

Base Level Drawing

8) APPENDIX C

Additional Calculations

1) INTRODUCTION

The existing 136' monopole consists of six major sections. From 0' to 120' the tower has twelve sides and is evenly tapered, measuring 47.98" (flat-flat) at the base to 22.00" (flat-flat) at the top. From 120' to 136' the tower consists of a 10' and a 6' pipe section measuring 8" and 3" in diameter, respectively. The structure is galvanized and has no tower lighting.

The tower was originally designed to 120' for Sprint Spectrum by Summit Manufacturing of Hazelton, Pennsylvania for a 90 mph wind speed with 0.5" radial ice in accordance with ANSI/EIA-TIA-222-F.

2) ANALYSIS CRITERIA

The structural analysis was performed for this tower in accordance with the requirements of TIA/EIA-222-F Structural Standards for Steel Antenna Towers and Antenna Supporting Structures and the 2005 Connecticut Building Code using a fastest mile wind speed of 80 mph with no ice, 38 mph with 1" ice thickness and 50 mph under service loads.

Table 1 - Proposed Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
120.0	121.0	3	Alcatel Lucent	TD-RRH8x20-25	1	1-1/4	1
		3	RFS Celwave	APXVTM14-C-120 w/ Mount Pipe			

Note:

- 1) See Appendix B for the proposed coax layout.

Table 2 - Existing and Reserved Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
120.0	121.0	3	RFS Celwave	APXVSPP18-C-A20 w/ Mount Pipe	3	1-1/4	
	120.0	1		Platform Mount [LP 712-1]			
116.0	118.0	3	Alcatel Lucent	PCS 1900MHz 4x45W-65MHz			
	116.0	1		Side Arm Mount [SO 102-3]			
	114.0	3	Alcatel Lucent	800MHz 2X50W RRH W/FILTER			

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)	Note
106.0	106.0	1	Kathrein	800 10735 K w/ Mount Pipe	1 3	1-5/8 5/8	1
		3	Amphenol	BXA-171063-12CF-EDIN-X w/ Mount Pipe			
		3	Alcatel Lucent	RRH2x40-AWS			
		1	RFS Celwave	DB-T1-6Z-8AB-0Z	3 12	1/2 1-1/4	
		2	Andrew	LNx-6514DS-T4M w/ Mount Pipe			
		3	Antel	BXA-185063/8CF w/ Mount Pipe			
		6	Decibel	DB846F65ZAXY w/ Mount Pipe			
		6	RFS Celwave	FD9R6004/2C-3L			
		1		Platform Mount [LP 713-1]			
65.0	66.0	1	Alcatel Lucent	KS24019-L112A	1	1/2	
	65.0	1		Side Arm Mount [SO 701-1]			

Notes:

- Reserved loading.

Table 3 - Design Antenna and Cable Information

Mounting Level (ft)	Center Line Elevation (ft)	Number of Antennas	Antenna Manufacturer	Antenna Model	Number of Feed Lines	Feed Line Size (in)
120.0	120.0	12	Decibel	DB980 H90	-	-
		1		14' LP Platform		
105.0	105.0	12	Allgon	ALP9212N	-	-
		1		14' LP Platform		
95.0	95.0	12	Allgon	ALP9212	-	-
		1		14' LP Platform		
80.0	80.0	2	Celwave	PD10017	-	-
		2		6' Stiff Arm		
39.0	39.0	1	Generic	GPS & Mount	-	-

3) ANALYSIS PROCEDURE

Table 4 - Documents Provided

Document	Remarks	Reference	Source
Manufacturer Drawings	Paul J. Ford Job #: A29297-211, dated 4/17/97	Doc ID #: 1440581	Crown DMZ
Foundation Design	Paul J. Ford Job #: A29297-211, dated 4/17/97	Doc ID #: 1615432	Crown DMZ
Geotechnical Report	Dr. Clarence Welti, P.E., dated 9/15/96	Doc ID #: 1529724	Crown DMZ

3.1) Analysis Method

tnxTower (version 6.1.4.1), a commercially available analysis software package, was used to create a three-dimensional model of the tower and calculate member stresses for various loading cases. Selected output from the analysis is included in Appendix A.

3.2) Assumptions

- 1) The tower was constructed in accordance with its original design and maintained per the manufacturer's specifications.
- 2) The configuration of antennas, transmission cables, mounts and other appurtenances are as specified in Tables 1 and 2 and the referenced drawings.
- 3) Mount sizes, weights, and manufacturers are best estimates based on photos provided and determined without the benefit of a site visit by SSOE.
- 4) All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 5) All foundation steel reinforcing is assumed to have been designed to meet or exceed the load carrying capacity of the surrounding soils unless otherwise specified in this report.
- 6) All equipment model numbers, quantities, and centerline elevations are as provided in the CCI CAD package, dated 5/1/14 with any adjustments as noted below.

This analysis may be affected if any assumptions are not valid or have been made in error. SSOE should be notified to determine the effect on the structural integrity of the tower.

4) ANALYSIS RESULTS

Table 5 - Section Capacity (Summary)

Section No.	Elevation (ft)	Component Type	Size	Critical Element	P (K)	SF*P_allow (K)	% Capacity	Pass / Fail
L1	136 - 129.5	Pole	TP3x3x0.216	1	-0.04	52.88	8.6	Pass
L2	129.5 - 129	Pole	TP8x3x0.216	2	-0.04	52.88	8.6	Pass
L3	129 - 120.5	Pole	TP8x8x0.322	3	-0.26	217.42	4.8	Pass
L4	120.5 - 120	Pole	TP22x8x0.322	4	-0.27	217.42	4.8	Pass
L5	120 - 87.5	Pole	TP29.476x22x0.1875	5	-6.72	738.14	60.4	Pass
L6	87.5 - 58.75	Pole	TP35.715x28.2384x0.25	6	-10.02	1263.78	73.8	Pass
L7	58.75 - 32.25	Pole	TP41.311x34.1798x0.375	7	-14.95	2493.91	54.1	Pass
L8	32.25 - 0	Pole	TP47.98x39.3533x0.4375	8	-24.41	3481.85	54.9	Pass
							Summary	
						Pole (L6)	73.8	Pass
						Rating =	73.8	Pass

Table 6 - Tower Component Stresses vs. Capacity – LC7

Notes	Component	Elevation (ft)	% Capacity	Pass / Fail
1	Anchor Rods		49.3%	Pass
1	Base Plate		53.1%	Pass

Foundation	Vector	Design Load	Actual Load	Ratio
Base	Moment	3250.0 kips-ft	1823.8 kip-ft	56.1%
	Compression	31.0 kips	24.4 kips	78.7%
	Shear	31.0 kips	21.8 kips	70.3%

Structure Rating (max from all components) =	78.7%
---	--------------

Notes:

- 1) See additional documentation in "Appendix C – Additional Calculations" for calculations supporting the % capacity consumed.

4.1) Recommendations

The existing tower and its foundations are sufficient for the proposed loads and do not require modifications.

5) DISCLAIMER OF WARRANTIES

SSOE Group has not performed a site visit to the tower to verify member sizes or antenna/coax loading. SSOE Group shall be contacted immediately if the existing conditions are not as represented on the tower elevation contained in this report in order to evaluate the significance of the discrepancy. SSOE Group has not performed a condition assessment of the tower foundation. This report does not replace a full tower inspection. The tower and foundation are assumed to have been properly fabricated, erected and maintained and to be in good condition, twist free, and plumb.

The engineering services rendered by SSOE Group in connection with this structural analysis are limited to a computer analysis of the tower structure and theoretical capacity of its main structural members. All tower components have been assumed to resist dead loads only when no other loads are applied. No allowance has been made for any damaged, bent, missing, loose, or rusted members (above and below ground). No allowance has been made for any loose bolts or cracked welds.

For the purposes of this report, SSOE Group has assumed that all connections in the tower are sufficient to develop the allowable strength of the associated members. SSOE Group has not performed engineering analysis to verify adequacy of these connections.

It is the owner's responsibility to determine the amount of ice accumulation, if any, that should be considered in the structural analysis.



The attached sketches are a schematic representation of the analyzed tower. If any material is fabricated from these sketches, the contractor shall be responsible for field verifying the existing conditions, proper fit, and clearances in the field. Any mentions of structural modifications are reasonable estimates and should not be used as a construction document. Construction documents depicting the required modification are obtainable from SSOE Group, but are beyond the scope of this report.

Miscellaneous items such as antenna mounts, etc., have not been designed or detailed as part of our work. We recommend that material of suitable size and strength be purchased from a reputable tower manufacturer.

SSOE Group makes no warranties, expressed and/or implied, in connection with this report and disclaims any liability arising from material, fabrication, and erection of this tower. SSOE Group will not be responsible whatsoever for, or on account of, consequential or incidental damages sustained by any person, firm, or organization as a result of any data or conclusions contained in this report. The maximum liability of SSOE Group pursuant to this report will be limited to the total fee received for preparation of this report.

APPENDIX A
TNXTOWER OUTPUT

Section	1	2	3	4	5	6	7	8
Length (ft)	6.50	0.50	8.50	0.50	32.50	32.50	31.00	37.50
Number of Sides	1	1	1	1	12	12	12	12
Thickness (in)	0.1600	0.3220	0.3220	0.1875	0.2500	0.2500	0.3750	0.4375
Socket Length (ft)	1600.2160	0.2160	0.2160	3.75	4.50	5.25	5.25	39.3533
Top Dia (in)	8.0000	8.0000	8.0000	22.0000	28.2384	34.1798	34.1798	47.9800
Bot Dia (in)	8.0000	8.0000	8.0000	22.0000	35.7150	41.3110	41.3110	47.9800
Grade	A53-B-35	A53-B-35	A53-B-35	A53-B-35	A572-60	A572-60	A572-65	A572-65
Weight (K)	0.0	0.0	0.2	0.0	1.7	2.8	4.8	7.8



DESIGNED APPURTENANCE LOADING

TYPE	ELEVATION	TYPE	ELEVATION
Platform Mount [LP 712-1]	120	(2) DB846F65ZAXY w/ Mount Pipe	106
APXVSP18-C-A20 w/ Mount Pipe	120	(2) DB846F65ZAXY w/ Mount Pipe	106
APXVSP18-C-A20 w/ Mount Pipe	120	(2) DB846F65ZAXY w/ Mount Pipe	106
APXVSP18-C-A20 w/ Mount Pipe	120	BXA-185063/8CF w/ Mount Pipe	106
TD-RRH8x20-25	120	BXA-185063/8CF w/ Mount Pipe	106
TD-RRH8x20-25	120	BXA-185063/8CF w/ Mount Pipe	106
TD-RRH8x20-25	120	BXA-171063-12CF-EDIN-X w/ Mount Pipe	106
APXVTM14-C-120 w/ Mount Pipe	120	BXA-171063-12CF-EDIN-X w/ Mount Pipe	106
APXVTM14-C-120 w/ Mount Pipe	120	BXA-171063-12CF-EDIN-X w/ Mount Pipe	106
APXVTM14-C-120 w/ Mount Pipe	120	BXA-171063-12CF-EDIN-X w/ Mount Pipe	106
APXVTM14-C-120 w/ Mount Pipe	120	BXA-171063-12CF-EDIN-X w/ Mount Pipe	106
(3) 2" x 6" Mount Pipe	120	800 10735 K w/ Mount Pipe	106
(3) 2" x 6" Mount Pipe	120	LNX-6514DS-T4M w/ Mount Pipe	106
(3) 2" x 6" Mount Pipe	120	LNX-6514DS-T4M w/ Mount Pipe	106
Side Arm Mount [SO 102-3]	116	(2) FD9R6004/2C-3L	106
PCS 1900MHz 4x45W-65MHz	116	(2) FD9R6004/2C-3L	106
PCS 1900MHz 4x45W-65MHz	116	(2) FD9R6004/2C-3L	106
PCS 1900MHz 4x45W-65MHz	116	(2) FD9R6004/2C-3L	106
800MHz 2X50W RRH W/FILTER	116	RRH2X40-AWS	106
800MHz 2X50W RRH W/FILTER	116	RRH2X40-AWS	106
800MHz 2X50W RRH W/FILTER	116	RRH2X40-AWS	106
2" x 6" Mount Pipe	116	DB-T1-6Z-8AB-0Z	106
2" x 6" Mount Pipe	116	Side Arm Mount [SO 701-1]	65
2" x 6" Mount Pipe	116	KS24019-L112A	65
Platform Mount [LP 713-1]	106		

MATERIAL STRENGTH

GRADE	Fy	Fu	GRADE	Fy	Fu
A53-B-35	35 ksi	63 ksi	A572-65	65 ksi	80 ksi
A572-60	60 ksi	75 ksi			

TOWER DESIGN NOTES


1. Tower is located in Hartford County, Connecticut.
2. Tower designed for a 80 mph basic wind in accordance with the TIA/EIA-222-F Standard.
3. Tower is also designed for a 38 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 50 mph wind.
5. TOWER RATING: 73.8%

SSOE Group		Job: BU 876332	
320 Seven Springs Way, Suite 350		Project: 014-00546-00	
Brentwood, TN 37027		Client: CCI	Drawn by: 14327
Phone: (615) 661-7585		Code: TIA/EIA-222-F	Date: 05/14/14
FAX: (615) 661-7569		Path: c:\dgn\0967707\876332.eri	Scale: NTS
			Dwg No. E-1

Feed Line Distribution Chart

0' - 136'

— Round
 — Flat
 — App In Face
 — App Out Face
 — Truss Leg



SSOE Group		Job: BU 876332	
320 Seven Springs Way, Suite 350		Project: 014-00546-00	
Brentwood, TN		Client: CCI	Drawn by: 14646
Phone: (615) 661-7858		Code: TIA/EIA-222-F	Date: 05/14/14
FAX: (615) 661-7569		Path: C:\Users\14646\Desktop\876332\Working\trnx\876332.er	Scale: NTS
			Dwg No. E-7

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	1 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Tower Input Data

There is a pole section.

This tower is designed using the TIA/EIA-222-F standard.

The following design criteria apply:

Tower is located in Hartford County, Connecticut.

Basic wind speed of 80 mph.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 38 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 50 mph.

A non-linear (P-delta) analysis was used.

Pressures are calculated at each section.

Stress ratio used in pole design is 1.333.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options

- | | | |
|--|--|---|
| <ul style="list-style-type: none"> Consider Moments - Legs Consider Moments - Horizontals Consider Moments - Diagonals Use Moment Magnification √ Use Code Stress Ratios √ Use Code Safety Factors - Guys √ Escalate Ice Always Use Max Kz Use Special Wind Profile Include Bolts In Member Capacity Leg Bolts Are At Top Of Section Secondary Horizontal Braces Leg Use Diamond Inner Bracing (4 Sided) Add IBC .6D+W Combination | <ul style="list-style-type: none"> Distribute Leg Loads As Uniform Assume Legs Pinned √ Assume Rigid Index Plate √ Use Clear Spans For Wind Area Use Clear Spans For KL/r Retension Guys To Initial Tension √ Bypass Mast Stability Checks √ Use Azimuth Dish Coefficients √ Project Wind Area of Appurt. Autocalc Torque Arm Areas SR Members Have Cut Ends Sort Capacity Reports By Component Triangulate Diamond Inner Bracing Use TIA-222-G Tension Splice Capacity Exemption | <ul style="list-style-type: none"> Treat Feedline Bundles As Cylinder Use ASCE 10 X-Brace Ly Rules Calculate Redundant Bracing Forces Ignore Redundant Members in FEA SR Leg Bolts Resist Compression All Leg Panels Have Same Allowable Offset Girt At Foundation √ Consider Feedline Torque Include Angle Block Shear Check <li style="text-align: center;">Poles √ Include Shear-Torsion Interaction Always Use Sub-Critical Flow Use Top Mounted Sockets |
|--|--|---|

Tapered Pole Section Geometry

Section	Elevation	Section Length	Splice Length	Number of Sides	Top Diameter	Bottom Diameter	Wall Thickness	Bend Radius	Pole Grade
	ft	ft	ft		in	in	in	in	
L1	136.00-129.50	6.50	0.00	Round	3.0000	3.0000	0.2160		A53-B-35 (35 ksi)
L2	129.50-129.00	0.50	0.00	Round	3.0000	8.0000	0.2160		A53-B-35 (35 ksi)
L3	129.00-120.50	8.50	0.00	Round	8.0000	8.0000	0.3220		A53-B-35 (35 ksi)
L4	120.50-120.00	0.50	0.00	Round	8.0000	22.0000	0.3220		A53-B-35 (35 ksi)
L5	120.00-87.50	32.50	3.75	12	22.0000	29.4760	0.1875	0.7500	A572-60

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job BU 876332	Page 2 of 15
	Project 014-00546-00	Date 18:55:39 05/14/14
	Client CCI	Designed by 14327

Section	Elevation ft	Section Length ft	Splice Length ft	Number of Sides	Top Diameter in	Bottom Diameter in	Wall Thickness in	Bend Radius in	Pole Grade
L6	87.50-58.75	32.50	4.50	12	28.2384	35.7150	0.2500	1.0000	(60 ksi) A572-60
L7	58.75-32.25	31.00	5.25	12	34.1798	41.3110	0.3750	1.5000	(60 ksi) A572-65
L8	32.25-0.00	37.50		12	39.3533	47.9800	0.4375	1.7500	(65 ksi) A572-65 (65 ksi)

Tapered Pole Properties

Section	Tip Dia. in	Area in ²	I in ⁴	r in	C in	I/C in ³	J in ⁴	I/Q in ²	w in	w/t
L1	3.0000	1.8892	1.8413	0.9873	1.5000	1.2275	3.6826	0.9440	0.0000	0
	3.0000	1.8892	1.8413	0.9873	1.5000	1.2275	3.6826	0.9440	0.0000	0
L2	3.0000	1.8892	1.8413	0.9873	1.5000	1.2275	3.6826	0.9440	0.0000	0
	8.0000	5.2821	40.0365	2.7531	4.0000	10.0091	80.0731	2.6395	0.0000	0
L3	8.0000	7.7670	57.3355	2.7170	4.0000	14.3339	114.6709	3.8812	0.0000	0
	8.0000	7.7670	57.3355	2.7170	4.0000	14.3339	114.6709	3.8812	0.0000	0
L4	8.0000	7.7670	57.3355	2.7170	4.0000	14.3339	114.6709	3.8812	0.0000	0
	22.0000	21.9293	1288.4548	7.6652	11.0000	117.1323	2576.9097	10.9581	0.0000	0
L5	22.7761	13.1693	799.7595	7.8089	11.3960	70.1790	1620.5296	6.4815	5.3935	28.765
	30.5158	17.6829	1936.1299	10.4853	15.2686	126.8049	3923.1240	8.7030	7.3971	39.451
L6	30.1276	22.5306	2252.7622	10.0198	14.6275	154.0089	4564.7070	11.0889	6.8979	27.592
	36.9749	28.5493	4583.3363	12.6965	18.5004	247.7430	9287.0819	14.0511	8.9016	35.606
L7	36.4572	40.8193	5953.9787	12.1021	17.7051	336.2856	12064.3751	20.0900	8.1552	21.747
	42.7683	49.4302	10572.7826	14.6551	21.3991	494.0761	21423.3239	24.3281	10.0663	26.844
L8	41.9919	54.8226	10597.3562	13.9319	20.3850	519.8603	21473.1168	26.9820	9.3742	21.427
	49.6726	66.9755	19322.6161	17.0202	24.8536	777.4562	39152.8588	32.9633	11.6861	26.711

Tower Elevation	Gusset Area (per face)	Gusset Thickness	Gusset Grade	Adjust. Factor A _f	Adjust. Factor A _r	Weight Mult.	Double Angle Stitch Bolt Spacing Diagonals	Double Angle Stitch Bolt Spacing Horizontals
ft	ft ²	in					in	in
L1				1	1	1		
136.00-129.50								
L2				1	1	1		
129.50-129.00								
L3				1	1	1		
129.00-120.50								
L4				1	1	1		
120.50-120.00								
L5				1	1	1		
120.00-87.50								
L6 87.50-58.75				1	1	1		
L7 58.75-32.25				1	1	1		
L8 32.25-0.00				1	1	1		

Feed Line/Linear Appurtenances - Entered As Area

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	3 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Description	Face or Leg	Allow Shield	Component Type	Placement ft	Total Number		C _{AA}	Weight
								plf
HB114-1-08U4-M5J(1 1/4")	A	No	Inside Pole	120.00 - 8.00	3	No Ice	0.00	1.08
						1/2" Ice	0.00	1.08
						1" Ice	0.00	1.08
						2" Ice	0.00	1.08
						4" Ice	0.00	1.08
LDF4-50A(1/2")	A	No	Inside Pole	65.00 - 8.00	1	No Ice	0.00	0.15
						1/2" Ice	0.00	0.15
						1" Ice	0.00	0.15
						2" Ice	0.00	0.15
						4" Ice	0.00	0.15
LDF6-50A(1-1/4")	C	No	Inside Pole	106.00 - 8.00	12	No Ice	0.00	0.66
						1/2" Ice	0.00	0.66
						1" Ice	0.00	0.66
						2" Ice	0.00	0.66
						4" Ice	0.00	0.66
LDF4-50A(1/2")	C	No	Inside Pole	106.00 - 8.00	3	No Ice	0.00	0.15
						1/2" Ice	0.00	0.15
						1" Ice	0.00	0.15
						2" Ice	0.00	0.15
						4" Ice	0.00	0.15
HB058-1-08U1-S1J(5/8")	C	No	Inside Pole	106.00 - 8.00	3	No Ice	0.00	0.70
						1/2" Ice	0.00	0.70
						1" Ice	0.00	0.70
						2" Ice	0.00	0.70
						4" Ice	0.00	0.70
HB158-1-08U8-S8J18(1-5/8)	C	No	Inside Pole	106.00 - 8.00	1	No Ice	0.00	1.30
						1/2" Ice	0.00	1.30
						1" Ice	0.00	1.30
						2" Ice	0.00	1.30
						4" Ice	0.00	1.30
5/8" Step Bolts	C	No	CaAa (Out Of Face)	120.00 - 8.00	1	No Ice	0.04	1.00
						1/2" Ice	0.14	1.56
						1" Ice	0.24	2.73
						2" Ice	0.44	6.91
						4" Ice	0.84	22.58
Safety Line 3/8	C	No	CaAa (Out Of Face)	120.00 - 8.00	1	No Ice	0.04	0.22
						1/2" Ice	0.14	0.75
						1" Ice	0.24	1.28
						2" Ice	0.44	2.34
						4" Ice	0.84	4.46
HB114-1-08U4-M5J(1 1/4")	A	No	Inside Pole	120.00 - 8.00	1	No Ice	0.00	1.08
						1/2" Ice	0.00	1.08
						1" Ice	0.00	1.08
						2" Ice	0.00	1.08
						4" Ice	0.00	1.08

Feed Line/Linear Appurtenances Section Areas

Tower Section	Tower Elevation ft	Face	A _R	A _F	C _{AA} In Face	C _{AA} Out Face	Weight
			ft ²	ft ²	ft ²	ft ²	K
L1	136.00-129.50	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
L2	129.50-129.00	A	0.000	0.000	0.000	0.000	0.00
		B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
L3	129.00-120.50	A	0.000	0.000	0.000	0.000	0.00

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	4 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Tower Section	Tower Elevation ft	Face	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L4	120.50-120.00	B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
		A	0.000	0.000	0.000	0.000	0.00
L5	120.00-87.50	B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	0.000	0.00
		A	0.000	0.000	0.000	0.000	0.14
L6	87.50-58.75	B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	2.573	0.26
		A	0.000	0.000	0.000	0.000	0.13
L7	58.75-32.25	B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	2.276	0.37
		A	0.000	0.000	0.000	0.000	0.12
L8	32.25-0.00	B	0.000	0.000	0.000	0.000	0.00
		C	0.000	0.000	0.000	2.098	0.34
		A	0.000	0.000	0.000	0.000	0.11
		C	0.000	0.000	0.000	1.920	0.32

Feed Line/Linear Appurtenances Section Areas - With Ice

Tower Section	Tower Elevation ft	Face or Leg	Ice Thickness in	A _R ft ²	A _F ft ²	C _{AA} In Face ft ²	C _{AA} Out Face ft ²	Weight K
L1	136.00-129.50	A	1.182	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L2	129.50-129.00	A	1.178	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L3	129.00-120.50	A	1.173	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L4	120.50-120.00	A	1.168	0.000	0.000	0.000	0.000	0.00
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	0.000	0.00
L5	120.00-87.50	A	1.147	0.000	0.000	0.000	0.000	0.14
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	17.478	0.37
L6	87.50-58.75	A	1.099	0.000	0.000	0.000	0.000	0.13
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	15.461	0.48
L7	58.75-32.25	A	1.038	0.000	0.000	0.000	0.000	0.12
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	13.751	0.43
L8	32.25-0.00	A	1.000	0.000	0.000	0.000	0.000	0.11
		B		0.000	0.000	0.000	0.000	0.00
		C		0.000	0.000	0.000	11.992	0.39

Feed Line Center of Pressure

Section	Elevation ft	CP _X in	CP _Z in	CP _X Ice in	CP _Z Ice in
L1	136.00-129.50	0.0000	0.0000	0.0000	0.0000

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	5 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Section	Elevation	CP _x	CP _z	CP _x	CP _z
	ft	in	in	Ice in	Ice in
L2	129.50-129.00	0.0000	0.0000	0.0000	0.0000
L3	129.00-120.50	0.0000	0.0000	0.0000	0.0000
L4	120.50-120.00	0.0000	0.0000	0.0000	0.0000
L5	120.00-87.50	-0.0992	0.0573	-0.5214	0.3010
L6	87.50-58.75	-0.0999	0.0577	-0.5501	0.3176
L7	58.75-32.25	-0.1003	0.0579	-0.5524	0.3189
L8	32.25-0.00	-0.0745	0.0430	-0.4121	0.2379

Discrete Tower Loads

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	C _A A _A Front ft ²	C _A A _A Side ft ²	Weight K	
Platform Mount [LP 712-1]	C	None		0.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	24.53 29.94 35.35 46.17 67.81	24.53 29.94 35.35 46.17 67.81	1.34 1.65 1.96 2.58 3.82
APXVSPP18-C-A20 w/ Mount Pipe	A	From Centroid-Le g	3.76 1.37 1.00	20.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.26 8.81 9.36 10.50 12.88	6.71 7.66 8.49 10.20 13.98	0.08 0.14 0.22 0.39 0.87
APXVSPP18-C-A20 w/ Mount Pipe	B	From Centroid-Le g	3.76 1.37 1.00	15.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.26 8.81 9.36 10.50 12.88	6.71 7.66 8.49 10.20 13.98	0.08 0.14 0.22 0.39 0.87
APXVSPP18-C-A20 w/ Mount Pipe	C	From Centroid-Le g	3.76 1.37 1.00	-25.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	8.26 8.81 9.36 10.50 12.88	6.71 7.66 8.49 10.20 13.98	0.08 0.14 0.22 0.39 0.87
TD-RRH8x20-25	A	From Centroid-Le g	3.76 1.37 1.00	20.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.72 5.01 5.32 5.95 7.31	1.70 1.92 2.15 2.62 3.68	0.07 0.10 0.13 0.20 0.40
TD-RRH8x20-25	B	From Centroid-Le g	3.76 1.37 1.00	15.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.72 5.01 5.32 5.95 7.31	1.70 1.92 2.15 2.62 3.68	0.07 0.10 0.13 0.20 0.40
TD-RRH8x20-25	C	From Centroid-Le g	3.76 1.37 1.00	-25.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	4.72 5.01 5.32 5.95 7.31	1.70 1.92 2.15 2.62 3.68	0.07 0.10 0.13 0.20 0.40
APXVTM14-C-120 w/ Mount Pipe	A	From Centroid-Le g	3.76 1.37 1.00	20.0000	120.00	No Ice 1/2" Ice 1" Ice 2" Ice 4" Ice	7.13 7.66 8.18 9.26	4.96 5.75 6.47 8.01	0.08 0.13 0.19 0.34

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	6 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral Vert					
APXVTM14-C-120 w/ Mount Pipe	B	From Centroid-Le g	3.76	15.0000	120.00	4" Ice	11.53	11.41	0.75
			1.37			No Ice	7.13	4.96	0.08
			1.00			1/2" Ice	7.66	5.75	0.13
						1" Ice	8.18	6.47	0.19
						2" Ice	9.26	8.01	0.34
APXVTM14-C-120 w/ Mount Pipe	C	From Centroid-Le g	3.76	-25.0000	120.00	4" Ice	11.53	11.41	0.75
			1.37			No Ice	7.13	4.96	0.08
			1.00			1/2" Ice	7.66	5.75	0.13
						1" Ice	8.18	6.47	0.19
						2" Ice	9.26	8.01	0.34
(3) 2" x 6' Mount Pipe	A	From Centroid-Le g	3.76	0.0000	120.00	4" Ice	11.53	11.41	0.75
			1.37			No Ice	1.20	1.20	0.03
			0.00			1/2" Ice	1.80	1.80	0.04
						1" Ice	2.17	2.17	0.05
						2" Ice	2.93	2.93	0.09
(3) 2" x 6' Mount Pipe	B	From Centroid-Le g	3.76	0.0000	120.00	4" Ice	4.57	4.57	0.23
			1.37			No Ice	1.20	1.20	0.03
			0.00			1/2" Ice	1.80	1.80	0.04
						1" Ice	2.17	2.17	0.05
						2" Ice	2.93	2.93	0.09
(3) 2" x 6' Mount Pipe	C	From Centroid-Le g	3.76	0.0000	120.00	4" Ice	4.57	4.57	0.23
			1.37			No Ice	1.20	1.20	0.03
			0.00			1/2" Ice	1.80	1.80	0.04
						1" Ice	2.17	2.17	0.05
						2" Ice	2.93	2.93	0.09
Side Arm Mount [SO 102-3]	C	None		0.0000	116.00	4" Ice	4.57	4.57	0.23
						No Ice	3.00	3.00	0.08
						1/2" Ice	3.48	3.48	0.11
						1" Ice	3.96	3.96	0.14
						2" Ice	4.92	4.92	0.20
PCS 1900MHz 4x45W-65MHz	A	From Leg	0.94	20.0000	116.00	4" Ice	6.84	6.84	0.32
			0.34			No Ice	2.71	2.61	0.06
			2.00			1/2" Ice	2.95	2.85	0.08
						1" Ice	3.20	3.09	0.11
						2" Ice	3.72	3.61	0.17
PCS 1900MHz 4x45W-65MHz	B	From Leg	0.94	15.0000	116.00	4" Ice	4.86	4.74	0.35
			0.34			No Ice	2.71	2.61	0.06
			2.00			1/2" Ice	2.95	2.85	0.08
						1" Ice	3.20	3.09	0.11
						2" Ice	3.72	3.61	0.17
PCS 1900MHz 4x45W-65MHz	C	From Leg	0.94	-25.0000	116.00	4" Ice	4.86	4.74	0.35
			0.34			No Ice	2.71	2.61	0.06
			2.00			1/2" Ice	2.95	2.85	0.08
						1" Ice	3.20	3.09	0.11
						2" Ice	3.72	3.61	0.17
800MHz 2X50W RRH W/FILTER	A	From Leg	0.94	20.0000	116.00	4" Ice	4.86	4.74	0.35
			0.34			No Ice	2.40	2.25	0.06
			-2.00			1/2" Ice	2.61	2.46	0.09
						1" Ice	2.83	2.68	0.11
						2" Ice	3.30	3.13	0.17
800MHz 2X50W RRH W/FILTER	B	From Leg	0.94	15.0000	116.00	4" Ice	4.34	4.15	0.34
			0.34			No Ice	2.40	2.25	0.06
			-2.00			1/2" Ice	2.61	2.46	0.09
						1" Ice	2.83	2.68	0.11
						2" Ice	3.30	3.13	0.17
800MHz 2X50W RRH	C	From Leg	0.94	-25.0000	116.00	4" Ice	4.34	4.15	0.34
						No Ice	2.40	2.25	0.06

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	7 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight	
			Horz	Vert						ft
W/FILTER			0.34							
			-2.00			1/2" Ice	2.61	2.46	0.09	
						1" Ice	2.83	2.68	0.11	
						2" Ice	3.30	3.13	0.17	
						4" Ice	4.34	4.15	0.34	
2" x 6' Mount Pipe	A	From Leg	0.94		0.0000	116.00	No Ice	1.20	1.20	0.03
			0.34				1/2" Ice	1.80	1.80	0.04
			0.00				1" Ice	2.17	2.17	0.05
							2" Ice	2.93	2.93	0.09
							4" Ice	4.57	4.57	0.23
2" x 6' Mount Pipe	B	From Leg	0.94		0.0000	116.00	No Ice	1.20	1.20	0.03
			0.34				1/2" Ice	1.80	1.80	0.04
			0.00				1" Ice	2.17	2.17	0.05
							2" Ice	2.93	2.93	0.09
							4" Ice	4.57	4.57	0.23
2" x 6' Mount Pipe	C	From Leg	0.94		0.0000	116.00	No Ice	1.20	1.20	0.03
			0.34				1/2" Ice	1.80	1.80	0.04
			0.00				1" Ice	2.17	2.17	0.05
							2" Ice	2.93	2.93	0.09
							4" Ice	4.57	4.57	0.23
Platform Mount [LP 713-1]	C	None			0.0000	106.00	No Ice	31.27	31.27	1.51
							1/2" Ice	39.68	39.68	1.93
							1" Ice	48.09	48.09	2.35
							2" Ice	64.91	64.91	3.19
							4" Ice	98.55	98.55	4.86
(2) DB846F65ZAXY w/ Mount Pipe	A	From Centroid-Face	3.46		30.0000	106.00	No Ice	7.27	7.82	0.05
			2.00				1/2" Ice	7.88	9.01	0.11
			0.00				1" Ice	8.48	9.91	0.19
							2" Ice	9.72	11.81	0.37
							4" Ice	12.33	15.98	0.87
(2) DB846F65ZAXY w/ Mount Pipe	B	From Centroid-Face	3.46		30.0000	106.00	No Ice	7.27	7.82	0.05
			2.00				1/2" Ice	7.88	9.01	0.11
			0.00				1" Ice	8.48	9.91	0.19
							2" Ice	9.72	11.81	0.37
							4" Ice	12.33	15.98	0.87
(2) DB846F65ZAXY w/ Mount Pipe	C	From Centroid-Face	3.46		30.0000	106.00	No Ice	7.27	7.82	0.05
			2.00				1/2" Ice	7.88	9.01	0.11
			0.00				1" Ice	8.48	9.91	0.19
							2" Ice	9.72	11.81	0.37
							4" Ice	12.33	15.98	0.87
BXA-185063/8CF w/ Mount Pipe	A	From Centroid-Face	3.46		30.0000	106.00	No Ice	3.18	3.00	0.03
			2.00				1/2" Ice	3.56	3.61	0.06
			0.00				1" Ice	3.96	4.24	0.09
							2" Ice	4.86	5.53	0.19
							4" Ice	6.77	8.42	0.47
BXA-185063/8CF w/ Mount Pipe	B	From Centroid-Face	3.46		30.0000	106.00	No Ice	3.18	3.00	0.03
			2.00				1/2" Ice	3.56	3.61	0.06
			0.00				1" Ice	3.96	4.24	0.09
							2" Ice	4.86	5.53	0.19
							4" Ice	6.77	8.42	0.47
BXA-185063/8CF w/ Mount Pipe	C	From Centroid-Face	3.46		30.0000	106.00	No Ice	3.18	3.00	0.03
			2.00				1/2" Ice	3.56	3.61	0.06
			0.00				1" Ice	3.96	4.24	0.09
							2" Ice	4.86	5.53	0.19
							4" Ice	6.77	8.42	0.47
BXA-171063-12CF-EDIN-X w/ Mount Pipe	A	From Centroid-Face	3.46		30.0000	106.00	No Ice	5.03	5.29	0.04
			2.00				1/2" Ice	5.58	6.46	0.09
			0.00				1" Ice	6.10	7.35	0.14

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job		BU 876332		Page		8 of 15	
	Project		014-00546-00		Date		18:55:39 05/14/14	
	Client		CCI		Designed by		14327	

Description	Face or Leg	Offset Type	Offsets:		Azimuth Adjustment	Placement	C _{AA} Front	C _{AA} Side	Weight
			Horz	Lateral					
BXA-171063-12CF-EDIN-X w/ Mount Pipe	B	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	7.17	9.15	0.27
						4" Ice	9.44	12.95	0.68
						No Ice	5.03	5.29	0.04
						1/2" Ice	5.58	6.46	0.09
						1" Ice	6.10	7.35	0.14
BXA-171063-12CF-EDIN-X w/ Mount Pipe	C	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	7.17	9.15	0.27
						4" Ice	9.44	12.95	0.68
						No Ice	5.03	5.29	0.04
						1/2" Ice	5.58	6.46	0.09
						1" Ice	6.10	7.35	0.14
800 10735 K w/ Mount Pipe	A	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	7.17	9.15	0.27
						4" Ice	9.44	12.95	0.68
						No Ice	8.97	5.49	0.06
						1/2" Ice	9.65	6.71	0.12
						1" Ice	10.30	7.69	0.19
LNX-6514DS-T4M w/ Mount Pipe	B	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	11.61	9.56	0.36
						4" Ice	14.37	13.51	0.84
						No Ice	8.57	7.00	0.06
						1/2" Ice	9.22	8.19	0.13
						1" Ice	9.84	9.08	0.20
LNX-6514DS-T4M w/ Mount Pipe	C	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	11.10	10.90	0.38
						4" Ice	13.75	14.93	0.89
						No Ice	8.57	7.00	0.06
						1/2" Ice	9.22	8.19	0.13
						1" Ice	9.84	9.08	0.20
(2) FD9R6004/2C-3L	A	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	11.10	10.90	0.38
						4" Ice	13.75	14.93	0.89
						No Ice	0.37	0.08	0.00
						1/2" Ice	0.45	0.14	0.01
						1" Ice	0.54	0.20	0.01
(2) FD9R6004/2C-3L	B	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	0.75	0.34	0.02
						4" Ice	1.28	0.74	0.06
						No Ice	0.37	0.08	0.00
						1/2" Ice	0.45	0.14	0.01
						1" Ice	0.54	0.20	0.01
(2) FD9R6004/2C-3L	C	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	0.75	0.34	0.02
						4" Ice	1.28	0.74	0.06
						No Ice	0.37	0.08	0.00
						1/2" Ice	0.45	0.14	0.01
						1" Ice	0.54	0.20	0.01
RRH2X40-AWS	A	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	0.75	0.34	0.02
						4" Ice	1.28	0.74	0.06
						No Ice	2.52	1.59	0.04
						1/2" Ice	2.75	1.80	0.06
						1" Ice	2.99	2.01	0.08
RRH2X40-AWS	B	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	3.44	2.43	0.12
						4" Ice	4.36	3.27	0.20
						No Ice	2.52	1.59	0.04
						1/2" Ice	2.75	1.80	0.06
						1" Ice	2.99	2.01	0.08
RRH2X40-AWS	C	From Centroid-Fa ce	3.46	30.0000	106.00	2" Ice	3.44	2.43	0.12
						4" Ice	4.36	3.27	0.20
						No Ice	2.52	1.59	0.04
						1/2" Ice	2.75	1.80	0.06
						1" Ice	2.99	2.01	0.08
RRH2X40-AWS			3.46	30.0000	106.00	2" Ice	3.44	2.43	0.12
						4" Ice	4.36	3.27	0.20
						No Ice	2.52	1.59	0.04
						1/2" Ice	2.75	1.80	0.06
						1" Ice	2.99	2.01	0.08

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	9 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Description	Face or Leg	Offset Type	Offsets: Horz Lateral Vert ft ft ft	Azimuth Adjustment °	Placement ft	CAA Front ft ²	CAA Side ft ²	Weight K	
DB-T1-6Z-8AB-0Z	B	From Centroid-Face	3.46	30.0000	106.00	No Ice	5.60	2.33	0.04
			2.00			1/2" Ice	5.92	2.56	0.08
			0.00			1" Ice	6.24	2.79	0.12
						2" Ice	6.91	3.28	0.21
						4" Ice	8.37	4.37	0.45
Side Arm Mount [SO 701-1]	C	From Face	1.00	0.0000	65.00	No Ice	0.85	1.67	0.07
			0.00			1/2" Ice	1.14	2.34	0.08
			0.00			1" Ice	1.43	3.01	0.09
						2" Ice	2.01	4.35	0.12
						4" Ice	3.17	7.03	0.18
KS24019-L112A	C	From Face	2.00	0.0000	65.00	No Ice	0.16	0.16	0.01
			0.00			1/2" Ice	0.22	0.22	0.01
			1.00			1" Ice	0.30	0.30	0.01
						2" Ice	0.48	0.48	0.02
						4" Ice	0.95	0.95	0.06

Load Combinations

Comb. No.	Description
1	Dead Only
2	Dead+ Wind 0 deg - No Ice
3	Dead+ Wind 30 deg - No Ice
4	Dead+ Wind 60 deg - No Ice
5	Dead+ Wind 90 deg - No Ice
6	Dead+ Wind 120 deg - No Ice
7	Dead+ Wind 150 deg - No Ice
8	Dead+ Wind 180 deg - No Ice
9	Dead+ Wind 210 deg - No Ice
10	Dead+ Wind 240 deg - No Ice
11	Dead+ Wind 270 deg - No Ice
12	Dead+ Wind 300 deg - No Ice
13	Dead+ Wind 330 deg - No Ice
14	Dead+Ice+Temp
15	Dead+ Wind 0 deg+Ice+Temp
16	Dead+ Wind 30 deg+Ice+Temp
17	Dead+ Wind 60 deg+Ice+Temp
18	Dead+ Wind 90 deg+Ice+Temp
19	Dead+ Wind 120 deg+Ice+Temp
20	Dead+ Wind 150 deg+Ice+Temp
21	Dead+ Wind 180 deg+Ice+Temp
22	Dead+ Wind 210 deg+Ice+Temp
23	Dead+ Wind 240 deg+Ice+Temp
24	Dead+ Wind 270 deg+Ice+Temp
25	Dead+ Wind 300 deg+Ice+Temp
26	Dead+ Wind 330 deg+Ice+Temp
27	Dead+ Wind 0 deg - Service
28	Dead+ Wind 30 deg - Service
29	Dead+ Wind 60 deg - Service
30	Dead+ Wind 90 deg - Service
31	Dead+ Wind 120 deg - Service

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	10 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

<i>Comb. No.</i>	<i>Description</i>
32	Dead+Wind 150 deg - Service
33	Dead+Wind 180 deg - Service
34	Dead+Wind 210 deg - Service
35	Dead+Wind 240 deg - Service
36	Dead+Wind 270 deg - Service
37	Dead+Wind 300 deg - Service
38	Dead+Wind 330 deg - Service

Maximum Member Forces

<i>Section No.</i>	<i>Elevation ft</i>	<i>Component Type</i>	<i>Condition</i>	<i>Gov. Load Comb.</i>	<i>Force K</i>	<i>Major Axis Moment kip-ft</i>	<i>Minor Axis Moment kip-ft</i>
L1	136 - 129.5	Pole	Max Tension	11	0.00	0.00	-0.00
			Max. Compression	14	-0.08	0.00	0.00
			Max. Mx	5	-0.04	-0.27	0.00
			Max. My	8	-0.04	0.00	-0.27
			Max. Vy	5	0.08	-0.27	0.00
			Max. Vx	8	0.08	0.00	-0.27
			Max. Torque	3			
L2	129.5 - 129	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-0.09	0.00	0.00
			Max. Mx	5	-0.04	-0.31	0.00
			Max. My	8	-0.04	0.00	-0.31
			Max. Vy	5	0.09	-0.31	0.00
			Max. Vx	8	0.09	0.00	-0.31
			Max. Torque	4			
L3	129 - 120.5	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-0.43	0.00	0.00
			Max. Mx	5	-0.26	-1.72	0.00
			Max. My	8	-0.26	0.00	-1.72
			Max. Vy	5	0.24	-1.72	0.00
			Max. Vx	8	0.24	0.00	-1.72
			Max. Torque	4			
L4	120.5 - 120	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-0.47	0.00	0.00
			Max. Mx	5	-0.28	-1.84	0.00
			Max. My	8	-0.28	0.00	-1.85
			Max. Vy	5	0.26	-1.84	0.00
			Max. Vx	2	-0.26	-0.00	1.85
			Max. Torque	4			
L5	120 - 87.5	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-14.68	-0.44	-0.13
			Max. Mx	5	-6.75	-246.22	1.96
			Max. My	8	-6.72	1.85	-254.14
			Max. Vy	5	12.48	-246.22	1.96
			Max. Vx	8	12.71	1.85	-254.14
			Max. Torque	3			
L6	87.5 - 58.75	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-19.40	-0.29	-0.48
			Max. Mx	5	-10.03	-633.01	3.20
			Max. My	8	-10.02	3.33	-647.50
			Max. Vy	5	15.24	-633.01	3.20
			Max. Vx	8	15.44	3.33	-647.50
			Max. Torque	3			
L7	58.75 - 32.25	Pole	Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-25.78	-0.13	-0.57
			Max. Mx	5	-14.96	-1058.69	4.48
			Max. My	8	-14.95	4.68	-1078.36

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	11 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Section No.	Elevation ft	Component Type	Condition	Gov. Load Comb.	Force K	Major Axis Moment kip-ft	Minor Axis Moment kip-ft
L8	32.25 - 0	Pole	Max. Vy	5	17.81	-1058.69	4.48
			Max. Vx	8	18.00	4.68	-1078.36
			Max. Torque	8			-0.30
			Max Tension	1	0.00	0.00	0.00
			Max. Compression	14	-37.42	0.06	-0.69
			Max. Mx	11	-24.41	1796.65	-6.89
			Max. My	8	-24.41	6.62	-1823.77
			Max. Vy	11	-21.57	1796.65	-6.89
			Max. Vx	8	21.77	6.62	-1823.77
			Max. Torque	8			-0.32

Maximum Reactions

Location	Condition	Gov. Load Comb.	Vertical K	Horizontal, X K	Horizontal, Z K
Pole	Max. Vert	21	37.42	0.01	-6.32
	Max. H _x	11	24.42	21.56	-0.05
	Max. H _z	2	24.42	-0.05	21.76
	Max. M _x	2	1823.21	-0.05	21.76
	Max. M _z	5	1796.64	-21.56	0.05
	Max. Torsion	2	0.31	-0.05	21.76
	Min. Vert	1	24.42	0.00	0.00
	Min. H _x	5	24.42	-21.56	0.05
	Min. H _z	8	24.42	0.05	-21.76
	Min. M _x	8	-1823.77	0.05	-21.76
	Min. M _z	11	-1796.65	21.56	-0.05
	Min. Torsion	8	-0.32	0.05	-21.76

Tower Mast Reaction Summary

Load Combination	Vertical K	Shear _x K	Shear _z K	Overturning Moment, M _x kip-ft	Overturning Moment, M _z kip-ft	Torque kip-ft
Dead Only	24.42	0.00	0.00	0.27	0.01	0.00
Dead+Wind 0 deg - No Ice	24.42	0.05	-21.76	-1823.21	-6.61	-0.31
Dead+Wind 30 deg - No Ice	24.42	10.82	-18.87	-1582.22	-904.03	-0.27
Dead+Wind 60 deg - No Ice	24.42	18.70	-10.92	-917.20	-1559.23	-0.14
Dead+Wind 90 deg - No Ice	24.42	21.56	-0.05	-6.33	-1796.64	0.02
Dead+Wind 120 deg - No Ice	24.42	18.65	10.84	906.32	-1552.63	0.19
Dead+Wind 150 deg - No Ice	24.42	10.74	18.82	1576.18	-892.58	0.30
Dead+Wind 180 deg - No Ice	24.42	-0.05	21.76	1823.77	6.62	0.32
Dead+Wind 210 deg - No Ice	24.42	-10.82	18.87	1582.78	904.04	0.26
Dead+Wind 240 deg - No Ice	24.42	-18.70	10.92	917.76	1559.24	0.13
Dead+Wind 270 deg - No Ice	24.42	-21.56	0.05	6.89	1796.65	-0.03
Dead+Wind 300 deg - No Ice	24.42	-18.65	-10.84	-905.76	1552.64	-0.18
Dead+Wind 330 deg - No Ice	24.42	-10.74	-18.82	-1575.62	892.59	-0.28
Dead+Ice+Temp	37.42	0.00	0.00	0.69	0.06	0.00
Dead+Wind 0 deg+Ice+Temp	37.42	0.01	-6.32	-556.19	-1.13	-0.15
Dead+Wind 30 deg+Ice+Temp	37.42	3.15	-5.47	-482.17	-277.36	-0.07
Dead+Wind 60 deg+Ice+Temp	37.42	5.45	-3.17	-278.76	-479.26	0.02
Dead+Wind 90 deg+Ice+Temp	37.42	6.29	-0.01	-0.46	-552.73	0.11
Dead+Wind 120 deg+Ice+Temp	37.42	5.45	3.15	278.15	-478.08	0.17

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	12 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Load Combination	Vertical	Shear _x	Shear _z	Overturning Moment, M _x	Overturning Moment, M _z	Torque
	K	K	K	kip-ft	kip-ft	kip-ft
Dead+Wind 150 deg+Ice+Temp	37.42	3.14	5.47	482.42	-275.32	0.18
Dead+Wind 180 deg+Ice+Temp	37.42	-0.01	6.32	557.62	1.22	0.15
Dead+Wind 210 deg+Ice+Temp	37.42	-3.15	5.47	483.60	277.45	0.07
Dead+Wind 240 deg+Ice+Temp	37.42	-5.45	3.17	280.19	479.35	-0.03
Dead+Wind 270 deg+Ice+Temp	37.42	-6.29	0.01	1.89	552.82	-0.11
Dead+Wind 300 deg+Ice+Temp	37.42	-5.45	-3.15	-276.72	478.17	-0.17
Dead+Wind 330 deg+Ice+Temp	37.42	-3.14	-5.47	-480.99	275.41	-0.18
Dead+Wind 0 deg - Service	24.42	0.02	-8.54	-717.86	-2.58	-0.12
Dead+Wind 30 deg - Service	24.42	4.25	-7.41	-622.94	-356.05	-0.10
Dead+Wind 60 deg - Service	24.42	7.34	-4.29	-361.03	-614.11	-0.05
Dead+Wind 90 deg - Service	24.42	8.47	-0.02	-2.31	-707.62	0.01
Dead+Wind 120 deg - Service	24.42	7.32	4.25	357.11	-611.53	0.07
Dead+Wind 150 deg - Service	24.42	4.22	7.39	620.91	-351.57	0.12
Dead+Wind 180 deg - Service	24.42	-0.02	8.54	718.41	2.59	0.13
Dead+Wind 210 deg - Service	24.42	-4.25	7.41	623.49	356.06	0.10
Dead+Wind 240 deg - Service	24.42	-7.34	4.29	361.58	614.12	0.05
Dead+Wind 270 deg - Service	24.42	-8.47	0.02	2.86	707.64	-0.01
Dead+Wind 300 deg - Service	24.42	-7.32	-4.25	-356.55	611.54	-0.07
Dead+Wind 330 deg - Service	24.42	-4.22	-7.39	-620.35	351.58	-0.11

Solution Summary

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
1	0.00	-24.42	0.00	0.00	24.42	0.00	0.000%
2	0.05	-24.42	-21.76	-0.05	24.42	21.76	0.000%
3	10.82	-24.42	-18.87	-10.82	24.42	18.87	0.000%
4	18.70	-24.42	-10.92	-18.70	24.42	10.92	0.000%
5	21.56	-24.42	-0.05	-21.56	24.42	0.05	0.000%
6	18.65	-24.42	10.84	-18.65	24.42	-10.84	0.000%
7	10.74	-24.42	18.82	-10.74	24.42	-18.82	0.000%
8	-0.05	-24.42	21.76	0.05	24.42	-21.76	0.000%
9	-10.82	-24.42	18.87	10.82	24.42	-18.87	0.000%
10	-18.70	-24.42	10.92	18.70	24.42	-10.92	0.000%
11	-21.56	-24.42	0.05	21.56	24.42	-0.05	0.000%
12	-18.65	-24.42	-10.84	18.65	24.42	10.84	0.000%
13	-10.74	-24.42	-18.82	10.74	24.42	18.82	0.000%
14	0.00	-37.42	0.00	0.00	37.42	0.00	0.000%
15	0.01	-37.42	-6.32	-0.01	37.42	6.32	0.000%
16	3.15	-37.42	-5.47	-3.15	37.42	5.47	0.000%
17	5.45	-37.42	-3.17	-5.45	37.42	3.17	0.000%
18	6.29	-37.42	-0.01	-6.29	37.42	0.01	0.000%
19	5.45	-37.42	3.15	-5.45	37.42	-3.15	0.000%
20	3.14	-37.42	5.47	-3.14	37.42	-5.47	0.000%
21	-0.01	-37.42	6.32	0.01	37.42	-6.32	0.000%
22	-3.15	-37.42	5.47	3.15	37.42	-5.47	0.000%
23	-5.45	-37.42	3.17	5.45	37.42	-3.17	0.000%
24	-6.29	-37.42	0.01	6.29	37.42	-0.01	0.000%
25	-5.45	-37.42	-3.15	5.45	37.42	3.15	0.000%
26	-3.14	-37.42	-5.47	3.14	37.42	5.47	0.000%
27	0.02	-24.42	-8.54	-0.02	24.42	8.54	0.000%
28	4.25	-24.42	-7.41	-4.25	24.42	7.41	0.000%
29	7.34	-24.42	-4.29	-7.34	24.42	4.29	0.000%
30	8.47	-24.42	-0.02	-8.47	24.42	0.02	0.000%
31	7.32	-24.42	4.25	-7.32	24.42	-4.25	0.000%
32	4.22	-24.42	7.39	-4.22	24.42	-7.39	0.000%
33	-0.02	-24.42	8.54	0.02	24.42	-8.54	0.000%

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	13 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Load Comb.	Sum of Applied Forces			Sum of Reactions			% Error
	PX K	PY K	PZ K	PX K	PY K	PZ K	
34	-4.25	-24.42	7.41	4.25	24.42	-7.41	0.000%
35	-7.34	-24.42	4.29	7.34	24.42	-4.29	0.000%
36	-8.47	-24.42	0.02	8.47	24.42	-0.02	0.000%
37	-7.32	-24.42	-4.25	7.32	24.42	4.25	0.000%
38	-4.22	-24.42	-7.39	4.22	24.42	7.39	0.000%

Non-Linear Convergence Results

Load Combination	Converged?	Number of Cycles	Displacement Tolerance	Force Tolerance
1	Yes	4	0.0000001	0.0000001
2	Yes	4	0.0000001	0.00022457
3	Yes	5	0.0000001	0.00008980
4	Yes	5	0.0000001	0.00009546
5	Yes	4	0.0000001	0.00018221
6	Yes	5	0.0000001	0.00009052
7	Yes	5	0.0000001	0.00008899
8	Yes	4	0.0000001	0.00032032
9	Yes	5	0.0000001	0.00009726
10	Yes	5	0.0000001	0.00008978
11	Yes	4	0.0000001	0.00009771
12	Yes	5	0.0000001	0.00008984
13	Yes	5	0.0000001	0.00009319
14	Yes	4	0.0000001	0.00000001
15	Yes	5	0.0000001	0.00008219
16	Yes	5	0.0000001	0.00009726
17	Yes	5	0.0000001	0.00009729
18	Yes	5	0.0000001	0.00008151
19	Yes	5	0.0000001	0.00009679
20	Yes	5	0.0000001	0.00009684
21	Yes	5	0.0000001	0.00008247
22	Yes	5	0.0000001	0.00009787
23	Yes	5	0.0000001	0.00009699
24	Yes	5	0.0000001	0.00008130
25	Yes	5	0.0000001	0.00009597
26	Yes	5	0.0000001	0.00009676
27	Yes	4	0.0000001	0.00006210
28	Yes	4	0.0000001	0.00037776
29	Yes	4	0.0000001	0.00042909
30	Yes	4	0.0000001	0.00004149
31	Yes	4	0.0000001	0.00039119
32	Yes	4	0.0000001	0.00037593
33	Yes	4	0.0000001	0.00007037
34	Yes	4	0.0000001	0.00044320
35	Yes	4	0.0000001	0.00037939
36	Yes	4	0.0000001	0.00003513
37	Yes	4	0.0000001	0.00038480
38	Yes	4	0.0000001	0.00041248

Compression Checks

tnxTower SSOE Group 320 Seven Springs Way, Suite 350 Brentwood, TN 37027 Phone: (615) 661-7585 FAX: (615) 661-7569	Job	BU 876332	Page	15 of 15
	Project	014-00546-00	Date	18:55:39 05/14/14
	Client	CCI	Designed by	14327

Section No.	Elevation ft	Ratio P P _a	Ratio f _{bx} F _{bx}	Ratio f _{by} F _{by}	Ratio f _v F _v	Ratio f _{vt} F _{vt}	Comb. Stress Ratio	Allow. Stress Ratio	Criteria
L1	136 - 129.5 (1)	0.001	0.114	0.000	0.006	0.000	0.115	1.333	H1-3+VT ✓
L2	129.5 - 129 (2)	0.001	0.114	0.000	0.007	0.000	0.115	1.333	H1-3+VT ✓
L3	129 - 120.5 (3)	0.002	0.062	0.000	0.004	0.000	0.064	1.333	H1-3+VT ✓
L4	120.5 - 120 (4)	0.002	0.062	0.000	0.005	0.000	0.064	1.333	H1-3+VT ✓
L5	120 - 87.5 (5)	0.012	0.791	0.000	0.063	0.001	0.805	1.333	H1-3+VT ✓
L6	87.5 - 58.75 (6)	0.011	0.973	0.000	0.047	0.000	0.984	1.333	H1-3+VT ✓
L7	58.75 - 32.25 (7)	0.008	0.713	0.000	0.029	0.000	0.721	1.333	H1-3+VT ✓
L8	32.25 - 0 (8)	0.009	0.722	0.000	0.025	0.000	0.731	1.333	H1-3+VT ✓

Section Capacity Table


Section No.	Elevation ft	Component Type	Size	Critical Element	P K	SF*P _{allow} K	% Capacity	Pass Fail
L1	136 - 129.5	Pole	TP3x3x0.216	1	-0.04	52.88	8.6	Pass
L2	129.5 - 129	Pole	TP8x3x0.216	2	-0.04	52.88	8.6	Pass
L3	129 - 120.5	Pole	TP8x8x0.322	3	-0.26	217.42	4.8	Pass
L4	120.5 - 120	Pole	TP22x8x0.322	4	-0.27	217.42	4.8	Pass
L5	120 - 87.5	Pole	TP29.476x22x0.1875	5	-6.72	738.14	60.4	Pass
L6	87.5 - 58.75	Pole	TP35.715x28.2384x0.25	6	-10.02	1263.78	73.8	Pass
L7	58.75 - 32.25	Pole	TP41.311x34.1798x0.375	7	-14.95	2493.91	54.1	Pass
L8	32.25 - 0	Pole	TP47.98x39.3533x0.4375	8	-24.41	3481.85	54.9	Pass

Summary ELC: Existing/Proposed/Reserved

Pole (L6) Rating = 73.8 Pass

73.8 Pass

APPENDIX B
BASE LEVEL DRAWING



(PROPOSED)
(1) 1-1/4" TO 120 FT LEVEL
(INSTALLED)
(1) 1/2" TO 86 FT LEVEL
(3) 1-1/4" TO 120 FT LEVEL

(PROPOSED)
(3) 5/8" TO 106 FT LEVEL
(1) 1-5/8" TO 106 FT LEVEL
(INSTALLED)
(3) 1/2" TO 106 FT LEVEL
(12) 1-1/4" TO 106 FT LEVEL

APPENDIX C
ADDITIONAL CALCULATIONS

Square, Stiffened / Unstiffened Base Plate, Any Rod Material - Rev. F /G

- Assumptions:**
- 1) Rod groups at corners. Total # rods divisible by 4. Maximum total # of rods = 48 (12 per Corner).
 - 2) Rod Spacing = Straight Center-to-Center distance between any (2) adjacent rods (same corner)
 - 3) Clear space between bottom of leveling nut and top of concrete **not** exceeding $(1) \times (\text{Rod Diameter})$

Site Data

BU#: 876332
 Site Name: 36 Prospect Street
 App #: 245362 Rev. 1

Anchor Rod Data

Qty:	16	
Diam:	2.25	in
Rod Material:	A615-J	
Yield, Fy:	75	ksi
Strength, Fu:	100	ksi
Bolt Circle:	56	in
Anchor Spacing:	6	in

Plate Data

W=Side:	56	in
Thick:	3	in
Grade:	50	ksi
Clip Distance:	0	in

Stiffener Data (Welding at both sides)

Configuration:	Unstiffened	
Weld Type:		**
Groove Depth:		in **
Groove Angle:		degrees
Fillet H. Weld:		<-- Disregard
Fillet V. Weld:		in
Width:		in
Height:		in
Thick:		in
Notch:		in
Grade:		ksi
Weld str.:		ksi

Pole Data

Diam:	47.98	in
Thick:	0.4375	in
Grade:	65	ksi
# of Sides:	12	"0" IF Round

Stress Increase Factor

ASD ASIF:	1.333	
-----------	-------	--

** Note: for complete joint penetration groove welds the groove depth must be exactly 1/2 the stiffener thickness for calculation purposes

Base Reactions

TIA Revision:	F	
Unfactored Moment, M:	1823.8	ft-kips
Unfactored Axial, P:	24.4	kips
Unfactored Shear, V:	21.8	kips

Anchor Rod Results

TIA F --> Maximum Rod Tension: 96.2 Kips
 Allowable Tension: 195.0 Kips
 Anchor Rod Stress Ratio: 49.3% **Pass**

Base Plate Results

Base Plate Stress: 26.6 ksi
 Allowable PL Bending Stress: 50.0 ksi
 Base Plate Stress Ratio: 53.1% **Pass**

Flexural Check

PL Ref. Data

Yield Line (in):	31.22
Max PL Length:	31.22


N/A - Unstiffened

Stiffener Results

Horizontal Weld : N/A
 Vertical Weld: N/A
 Plate Flex+Shear, $f_b/F_b + (f_v/F_v)^2$: N/A
 Plate Tension+Shear, $f_t/F_t + (f_v/F_v)^2$: N/A
 Plate Comp. (AISC Bracket): N/A

Pole Results

Pole Punching Shear Check: N/A



RADIO FREQUENCY FCC REGULATORY COMPLIANCE
MAXIMUM PERMISSIBLE EXPOSURE (MPE) ASSESSMENT

Sprint Existing Facility

Site ID: CT03XC084

36 Prospect Street

36 Prospect Street
Newington, CT 06109

June 24, 2014

EBI Project Number: 62143502

June 24, 2014

Sprint
Attn: RF Engineering Manager
1 International Boulevard, Suite 800
Mahwah, NJ 07495

Re: Radio Frequency Maximum Permissible Exposure (MPE) Assessment for Site:
CT03XC084 - 36 Prospect Street

Site Total: 46.92% - MPE% in full compliance

EBI Consulting was directed to analyze the proposed upgrades to the existing Sprint facility located at 36 Prospect Street, Newington, CT, for the purpose of determining whether the radio frequency (RF) exposure levels from the proposed Sprint equipment upgrades on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the cellular band (850 MHz Band) is approximately $567 \mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz and 2500 MHz bands is $1000 \mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed upgrades to the existing Sprint Wireless antenna facility located at 36 Prospect Street, Newington, CT, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. All calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6 foot person standing at the base of the tower.

For all calculations, all emissions were calculated using the following assumptions:

- 1) 3 channels in the 1900 MHz Band were considered for each sector of the proposed installation.
- 2) 1 channel in the 800 MHz Band was considered for each sector of the proposed installation
- 3) 2 channels in the 2500 MHz Band were considered for each sector of the proposed installation.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.
- 5) For the following calculations the sample point was the top of a six foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.

- 6) The antennas used in this modeling are the RFS APXVSPP18-C-A20 and the RFS APXVTM14-C-I20. This is based on feedback from the carrier with regards to anticipated antenna selection. The RFS APXVSPP18-C-A20 has a 15.9 dBd gain value at its main lobe at 1900 MHz and 13.4 dBd at its main lobe for 850 MHz. The RFS APXVTM14-C-I20 has a 15.9 dBd gain value at its main lobe at 2500 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline for the proposed antennas is **121 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.

All calculation were done with respect to uncontrolled / general public threshold limits

Site ID	CT03XC084 - 36 Prospect Street
Site Address	36 Prospect Street, Newington, CT, 06109
Site Type	Monopole

Sector 1

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
1a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	121	115	1/2 "	0.5	0	208.04	0.57%
1a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	121	115	1/2 "	0.5	0	39.00	0.19%
1B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	121	115	1/2 "	0.5	0	138.69	0.66%
Sector total Power Density Value:																1.42%

Sector 2

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
2a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	121	115	1/2 "	0.5	0	208.04	0.57%
2a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	121	115	1/2 "	0.5	0	39.00	0.19%
2B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	121	115	1/2 "	0.5	0	138.69	0.66%
Sector total Power Density Value:																1.42%

Sector 3

Antenna Number	Antenna Make	Antenna Model	Radio Type	Frequency Band	Technology	Power Out Per Channel (Watts)	Number of Channels	Composite Power	Antenna Gain (10 db reduction)	Antenna Height (ft)	analysis height	Cable Size	Cable Loss (dB)	Additional Loss (dB)	ERP	Power Density Percentage
3a	RFS	APXVSP18-C-A20	RRH	1900 MHz	CDMA / LTE	20	3	60	5.9	121	115	1/2 "	0.5	0	208.04	0.57%
3a	RFS	APXVSP18-C-A20	RRH	850 MHz	CDMA / LTE	20	1	20	3.4	121	115	1/2 "	0.5	0	39.00	0.19%
3B	RFS	APXVTMM14-C-120	RRH	2500 MHz	CDMA / LTE	20	2	40	5.9	121	115	1/2 "	0.5	0	138.69	0.66%
Sector total Power Density Value:																1.42%

Site Composite MPE %	
Carrier	MPE %
Sprint	4.25%
Verizon Wireless	42.67%
Total Site MPE %	46.92%

Summary

All calculations performed for this analysis yielded results that were well within the allowable limits for general public Maximum Permissible Exposure (MPE) to radio frequency energy.

The anticipated Maximum Composite contributions from the Sprint facility are **4.25% (1.42% from sector 1, 1.42% from sector 2 and 1.42% from sector 3)** of the allowable FCC established general public limit considering all three sectors simultaneously sampled at the ground level.

The anticipated composite MPE value for this site assuming all carriers present is **46.92%** of the allowable FCC established general public limit sampled at 6 feet above ground level. This total composite site value is based upon MPE values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.



Scott Heffernan
RF Engineering Director

EBI Consulting
21 B Street
Burlington, MA 01803